

1US\$=108JP Yen=14,100VND

No.	Description	Specification	Unit	Quantity	Unit Price			COMBINED TOTAL COST (VND)			Remarks
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)	
1	Foreman	1*(r*d1*1.0) Local	M/day	2.64	0	0.00	146,392	0.00	386,475	L	101000
2	Skilled Labor	1*(r*d1*1.0) Local	M/day	2.64	0	0.00	118,898	0.00	313,891	L	104000
3	Rigger	1*(r*d1*2.0) Local	M/day	5.28	0	0.00	118,898	0.00	627,781	L	105000
4	Common Labor	1*(r*d1*2.0) Local	M/day	5.28	0	0.00	58,671	0.00	309,783	L	103000
5	Press in pile driver	1*(1.51*r*s*d1) H750mm	day in demand	3.99	27,352	0.00	0	0.00	14,248,050	EL	151000
6	Reverse Circulation Drill	1*(1.51*r*s*d1) 11.2t, 75kW	day in demand	3.19	29,344	0.00	0	0.00	12,220,914	EL	132000
7	Crawler Crane	1*(r*e1*d1) 40t	day	2.61	0	0.00	2,059,353	0.00	5,374,911	EL	118500
8	Crawler Crane	1*(r*e2*d1) 40t	day	1.80	0	0.00	2,059,353	0.00	3,706,835	EL	118500
9	Backhoe	1*(1.09*r*s*d1) 0.6m3	day	2.30	0	0.00	970,542	0.00	2,232,247	EL	101000
10	Miscellaneous Fee	30 % of above			0				11,156,592		
11	Concrete Production Class - D	Q=π/4*D²*L*(1+)	m3	156.36	565	0.00	355,059	1.82	71,063,272	PC	211500
12	Concrete Piling (Plain, RC Structure)	Q=π/4*D²*L*(1+) Pump(Less than 50m³/day)	m3	156.36	532	0.00	16,398	0.00	13,424,124	PC	221100
13	Concrete Transportation	Q=π/4*D²*L*(1+) Truck Mixer (3.5km)	m3	156.36	441	0.00	13,013	0.00	11,037,171	PC	251800
14	Slush Tank (Slush Container)	1*(1.51*r*s*d1) 30m3	day in demand	0.00	1,146	0.00	0	0.00	0	EL	132500
15	Loading, Transportation ( L = 2.0 km )	Q=π/4*D²*L*(1+)	m3	60.32	0	0.00	8,427	0.00	508,317	PC	135500
16	Rebar Fabrication of Pile	D10-D14	t	1.23	0	0.00	297,537	265.42	4,974,833	PC	452001
17	Rebar Fabrication of Pile	D16-D25	t	4.58	0	0.00	297,537	265.42	18,502,961	PC	452002
18	Rebar Fabrication of Pile	D28-D32	t	3.29	0	0.00	297,537	265.42	13,287,476	PC	452003
Summary											
per nos											
REMARKS											

r=1, d1=2.64, c1=0.99, e2=0.68, s=0.8, D=1.5m, L=79m, b=0.12

Summary										
per nos										
REMARKS										
183,375,634										
183,375,634										



































CAN THO BRIDGE CONSTRUCTION PROJECT

Process Cost Equipment/Depression(CI)(PT-girder) (Girder Production) Unit: 1 lot 511161 Sheet #: PC

No.	Description	Specification	Unit	Quantity	Unit Price				COMBINED TOTAL COST (VND)	Remarks
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)		
1	Tensioning Jack	400t	day in demand	1,364.00	4,050	0.00	0	0.00	721,215,000	EL 178030
2	Gantry Crane	3t lifting force	day in demand	675.00	3,038	0.00	0	0.00	267,723,750	EL 145000
3	Electric Hoist	3t lifting force	day in demand	675.00	549	0.00	0	0.00	48,380,625	EL 146000
4	Track (per100m) for Gantry Crane	30kg/m including Sleeper	day in demand	675.00	1,070	0.00	0	0.00	94,293,750	EL 147000
5	Wheel Crane	Hydraulic 25t	day in demand	3.00	0	0.00	1,148,366	0.00	3,445,098	EL 123100
6	Hydraulic Jack	196.1kN (20t)	day in demand	2,688.00	367	0.00	0	0.00	128,792,533	EL 148000
7	Hydraulic Pump	Electric 1.5kW	day in demand	1,344.00	2,044	0.00	0	0.00	358,653,867	EL 149000
8	Hydraulic Jack Extrude Table	75t	day in demand	2,688.00	437	0.00	0	0.00	153,357,867	EL 150000
9	Lever Block	29.4kN (3.0t) * 1.5m	day in demand	1,344.00	85	0.00	0	0.00	14,914,667	EL 151000
10	Tilehole	29.4kN (3.0t)	day in demand	1,344.00	169	0.00	0	0.00	29,653,867	EL 152000
11	Side Loader (for PC Girder)	Steel Bowl Type 294.2kN (30t) 1*2*A	day in demand	1,344.00	871	0.00	0	0.00	152,831,467	EL 153000
12	Steel Form Work for Post Tension I-Beam	L40m (212.123m2)	day in demand	672.00	0	0.00	0	39.63	375,502,176	EL 154014
13	Mill Table for Post Tension I-Beam	L40m(L41m), w=0.65m	day in demand	672.00	0	0.00	0	8.59	81,391,968	EL 155014
Summary									2,430,156,634	
per lot									2,430,156,634	

A=(n/s\*(s-1)/s)\*1.4 (days) ; n= 189 (The number of girder), s=4 (The number of Mill Table)

B=3 (days) ; Setting and Removal of Gantry Crane

C=10 (days) ; Transportation of Tension Jack

REMARKS





















1US\$=108JP Yen=14,100VND

CAN THO BRIDGE CONSTRUCTION PROJECT

Process Cost      Equipment/Depression(Can Tho Side)      Erection (PTI-girder)      Unit: 1      lot      Sheet #: PC      512151

No.	Description	Specification	Unit	Quantity	Unit Price				Local Currency (VND)	Local Currency (US\$)	COMBINED TOTAL COST (VND)	Remarks
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)				
1	Erection Girder	97(40m-84.6)	1"D	128.63	0	0.00	0	186.77	0	338,741,643	EL 190040	
2	Pulling Roller	30t	1*12 rollers'D	1,543.61	301	0.00	0	0.00	0	60,659,636	EL 191000	
3	Steel Bent	Self weight 11.48t	1"D	128.63	4,475	0.00	0	0.00	0	75,150,258	EL 191100	
4	Miscellaneous Fee	2.5 % of above								11,863,788		
5	Device for hanging girder	392.3kN(40)	1*1*2'D	257.27	9,803	0.00	0	0.00	0	329,263,461	EL 200500	
6	Slng for PC girder...	588.4kN (40)	1*1*2'D	257.27	184	0.00	0	0.00	0	6,180,239	EL 200320	
7	Wire Rope	d16 per 100m	1*2*2'D	514.54	90	0.00	0	0.00	0	6,045,897	EL 200400	
8	Miscellaneous Fee	1.5 % of above								5,122,344		
9	Side Loader (for PC Girder)	Steel Bowl Type 294.2kN (40) 1*2'D		257.27	951	0.00	0	0.00	0	31,942,244	EL 153010	
10	Hydraulic Jack	50t Double Acting Type	1*4'D	0.00	612	0.00	0	0.00	0	0	EL 148010	
11	Hydraulic Jack Extrude Table	50t * 150	1*4'D	514.54	311	0.00	0	0.00	0	20,891,761	EL 150010	
12	Hydraulic Pump	Electric 2.2kW	1*2'D	257.27	2,705	0.00	0	0.00	0	90,855,569	EL 149010	
13	Tilehole	15.7kN (1.6)	1*2'D	257.27	103	0.00	0	0.00	0	3,459,592	EL 152010	
14	Lever Block	29.4kN (3.0t) * 1.5m	1*2'D	257.27	85	0.00	0	0.00	0	2,854,989	EL 151000	
15	Miscellaneous Fee									1,500,042		
16	Winch	Double Drum Type 3t	1*1'D	128.63	6,325	0.00	0	0.00	0	106,218,042	EL 182010	
17	Sheave	d400*2	1*2'D	257.27	268	0.00	0	0.00	0	9,001,544	EL 182070	
18	Wire Rope	d16 per 100m	1*800/100*D	1,029.07	90	0.00	0	0.00	0	12,091,533	EL 200400	
19	Miscellaneous Fee	1 % of above								1,275,111		
20	Erection Tools for Precast Girder	1*1'D		128.63	2,785	0.00	0	0.00	0	46,769,569	EL 168010	
21	Track (per100m) for Precast Girder	30kg/m including Sleeper	1*1*(1.23*1+1*S)/1	166.20	1,045	0.00	0	0.00	0	22,674,758	EL 147010	
Summary												
per lot										1,182,560,023		
REMARKS												

97(40m-84.6 girder)  
Days in demand = (Girder Erection + Installation and Removal of Erection Equipment + Move of Erection Equipment) \* 2.1

1US\$=108JP Yen=14,100VND

CAN THO BRIDGE CONSTRUCTION PROJECT

Process Cost Equipment/Depression(Cu Lao Lac) Erection (P.T)-girder Unit: 1 lot

Sheet #: PC 512152

No.	Description	Specification	Unit	Quantity	Unit Price			COMBINED TOTAL			Remarks
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)	COST (VND)		
1	Erection Girder	97(40m-84.6)	1*D	628.76	0	0.00	0	186.77	1,655,812,491	EL	190040
2	Pulling Roller	30tf	1*12 rollers*D	7,545.17	301	0.00	0	0.00	296,504,200	EL	191000
3	Steel Bent	Self weight 11.48t	1*D	628.76	4,475	0.00	0	0.00	367,344,297	EL	191100
4	Miscellaneous Fee	2.5 % of above							57,991,525		
5	Device for hanging girder	392.3kN(40t)	1*1*2*D	1,257.53	9,803	0.00	0	0.00	1,609,432,358	EL	200500
6	Slings for PC girder...	588.4kN (40t)	1*1*2*D	1,257.53	184	0.00	0	0.00	30,208,728	EL	200320
7	Wire Rope	d16 per 100m	1*2*2*D	2,515.06	90	0.00	0	0.00	29,551,903	EL	200400
8	Miscellaneous Fee	1.5 % of above							25,037,895		
9	Side Loader (for PC Girder)	Steel Bowl Type 294.2kN (40t) 1*2*D	1*4*D	1,257.53	951	0.00	0	0.00	156,132,825	EL	153010
10	Hydraulic Jack	50tf Double Acting Type	1*4*D	0.00	612	0.00	0	0.00	0	EL	148010
11	Hydraulic Jack Extend Table	50tf * 150	1*4*D	2,515.06	311	0.00	0	0.00	102,118,467	EL	150010
12	Hydraulic Pump	Electric 2.2KW	1*2*D	1,257.53	2,705	0.00	0	0.00	444,100,258	EL	149010
13	Tilehole	15.7kN (1.6t)	1*2*D	1,257.53	103	0.00	0	0.00	16,910,339	EL	152010
14	Lever Block	29.4kN (3.0t) * 1.5m	1*2*D	1,257.53	85	0.00	0	0.00	13,955,083	EL	151000
15	Miscellaneous Fee								7,332,170		
16	Winch	Double Drum Type 3t	1*1*D	628.76	6,325	0.00	0	0.00	519,207,303	EL	182010
17	Sheave	d400*2	1*2*D	1,257.53	268	0.00	0	0.00	43,999,572	EL	182070
18	Wire Rope	d16 per 100m	1*800/100*D	5,030.11	90	0.00	0	0.00	59,103,806	EL	200400
19	Miscellaneous Fee	1 % of above							6,223,107		
20	Erection Tools for Precast Girder	1*1*D	1*1*D	628.76	2,785	0.00	0	0.00	228,615,442	EL	168010
21	Track (per100m) for Precast Girder	30kg/m including Sleeper	1*1*(1.23**1*S)/1	4,584.95	1,045	0.00	0	0.00	625,527,308	EL	147010
22	Heavy Track Carrier for girder	Doublegags Rotary Type 40t	1*2*D	1,257.53	2,869	0.00	0	0.00	471,025,383	EL	198015
Summary											
per lot											
6,766,134,459											

REMARKS 97(40m-84.6 girder)

Days in demand = (Girder Erection + Installation and Removal of Erection Equipment + Move of Erection Equipment) \* 2.1

CAN THO BRIDGE CONSTRUCTION PROJECT

Process Cost Equipment/Depression(Vinh Long Side)

Erection (PTI-girder)

Unit: 1

lot

Sheet #: PC 512153

No.	Description	Specification	Unit	Quantity	Unit Price				COMBINED TOTAL COST (VND)	Remarks
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)		
1	Erection Girder	97(40m-84.6)	day in demand	462.05	0	0.00	0	186.77	1,216,788,828	EL 190040
2	Pulling Roller	30t	day in demand	5,544.65	301	0.00	0	0.00	217,889,389	EL 191000
3	Steel Bent	Self weight 11.48t	day in demand	462.05	4,475	0.00	0	0.00	269,946,328	EL 191100
4	Miscellaneous Fee	2.5 % of above							42,615,614	
5	Device for hanging girder	392.3kN(40t)	day in demand	924.11	9,803	0.00	0	0.00	1,182,709,306	EL 200500
6	Sling for PC girder...	588.4kN (40t)	day in demand	924.11	184	0.00	0	0.00	22,199,144	EL 200320
7	Wire Rope	d16 per 100m	day in demand	1,848.22	90	0.00	0	0.00	21,716,611	EL 200400
8	Miscellaneous Fee	1.5 % of above							18,399,376	
9	Side Loader (for PC Girder)	Steel Bowl Type 294.2kN (40t) 1*2*D	day in demand	924.11	951	0.00	0	0.00	114,736,008	EL 152010
10	Hydraulic Jack	50t Double Acting Type	day in demand	0.00	612	0.00	0	0.00	0	EL 148010
11	Hydraulic Jack Extrude Table	50t * 150	day in demand	1,848.22	311	0.00	0	0.00	75,042,811	EL 150010
12	Hydraulic Pump	Electric 2.2kW	day in demand	924.11	2,705	0.00	0	0.00	326,352,072	EL 149010
13	Tilehole	15.7kN (1.6t)	day in demand	924.11	103	0.00	0	0.00	12,426,669	EL 152010
14	Lever Block	29.4kN (3.0t) * 1.5m	day in demand	924.11	85	0.00	0	0.00	10,255,008	EL 151000
15	Miscellaneous Fee								5,588,126	
16	Winch	Double Drum Type 3t	day in demand	462.05	6,325	0.00	0	0.00	381,544,172	EL 182010
17	Sheave	d400*2	day in demand	924.11	268	0.00	0	0.00	32,333,519	EL 182070
18	Wire Rope	d16 per 100m	day in demand	3,696.43	90	0.00	0	0.00	43,433,092	EL 200400
19	Miscellaneous Fee	1 % of above							4,573,168	
20	Erection Tools for Precast Girder	1*1*D	day in demand	462.05	2,785	0.00	0	0.00	168,000,064	EL 168010
21	Track (per 100m) for Precast Girder	30kg/m including Sleeper	day in demand	2,445.19	1,045	0.00	0	0.00	333,598,689	EL 147010
Summary										
									4,499,947,934	
									4,499,947,934	

97(40m-84.6 girder)

Days in demand = (Girder Erection + Installation and Removal of Erection Equipment + Move of Erection Equipment) \* 2.1

REMARKS



























CAN THO BRIDGE CONSTRUCTION PROJECT

Process Cost		Equipment/Depression(Can/ThoSId)		Segment Fabric(PTL-girder)		Unit: 1		Sheet #: PC		lot	
No.	Description	Specification	Unit	Quantity	Unit Price	Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)	COMBINED TOTAL COST (VND)	Remarks
1	Truck Crane	40 - 45t	day in demand	18.00	0	0.00	0.00	2,077,756	0.00	37,399,608	EL 123030
2	Heavy Track Carrier for girder	Doublegauge Rotary Type 40t	day in demand	93.60	2,869	0.00	0.00	0	0.00	35,059,128	EL 198015
3	Heavy Track Carrier for girder	Doublegauge 15t	day in demand	374.40	1,793	0.00	0.00	0	0.00	87,641,814	EL 198017
4	Hydraulic Jack	50t with Inner Pump type	day in demand	187.20	406	0.00	0.00	0	0.00	9,922,614	EL 148050
5	Track (per100m) for Precast Girder	30kg/m including Slepker	day in demand	23.03	1,045	0.00	0.00	0	0.00	3,141,950	EL 147010
6	Tensioning Jack	400t	day in demand	93.60	4,050	0.00	0.00	0	0.00	49,491,000	EL 178030
6	Tensioning Jack Pump	3.7kW	day in demand	93.60	2,290	0.00	0.00	0	0.00	27,983,800	EL 179000
6	Lever Block	29.4kN (3.0t) * 1.5m	day in demand	187.20	85	0.00	0.00	0	0.00	2,077,400	EL 151000
9	Gas Regulator	Oxygen	day in demand	46.80	15	0.00	0.00	0	0.00	91,650	EL 198020
10	Gas Regulator	Acetylene	day in demand	46.80	16	0.00	0.00	0	0.00	97,786	EL 198030
11	Gas Cutting Apparatus	Acetylene	day in demand	46.80	15	0.00	0.00	0	0.00	91,650	EL 174000
12	Grouting Pump	(15-30 l/min)	day in demand	18.10	868	0.00	0.00	0	0.00	2,051,158	EL 181000
13	Groat Mixer	(100 l/min)	day in demand	18.10	341	0.00	0.00	0	0.00	805,789	EL 180000
Summary											
										255,855,347	
per lot											
										255,855,347	
REMARKS											
D1=0.52* nos of segmen of one girder* nos of girder/nos of table											
nos of segment for one girder											
D2=0.6* nos of girder * 7.3											

1US\$=108JP Yen=14,100VND

CAN THO BRIDGE CONSTRUCTION PROJECT										Unit: 1	lot	
Process Cost										Sheet #: PC	514162	
Equipment/Depression(Cu Lao Lat)										Segment Fabric(PTI-girder)		
No.	Description	Specification	Unit	Quantity	Unit Price			COMBINED TOTAL COST (VND)			Remarks	
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)		
1	Truck Crane	40 - 45t	day in demand	153.00	0	0.00	2,077,756	0.00	0.00	317,896,568	EL	123030
2	Heavy Track Carrier for girder	Doublegag Rotary Type 40t	day in demand	795.60	2,869	0.00	0	0.00	0.00	298,002,978	EL	198015
3	Heavy Track Carrier for girder	Doublegag 15t	day in demand	3,182.40	1,793	0.00	0	0.00	0.00	744,955,614	EL	198017
4	Hydraulic Jack	50t with Inner Pump type	day in demand	1,591.20	406	0.00	0	0.00	0.00	84,342,414	EL	148050
5	Track (per100m) for Precast Girder	30kg/m including Sleeper	day in demand	195.72	1,045	0.00	0	0.00	0.00	26,702,136	EL	147010
6	Tensioning Jack	400t	day in demand	795.60	4,050	0.00	0	0.00	0.00	420,673,500	EL	178020
6	Tensioning Jack Pump	3.7KW	day in demand	795.60	2,290	0.00	0	0.00	0.00	237,862,300	EL	179000
9	Gas Regulator	29.4kN (3.0t) * 1.5m	day in demand	1,591.20	85	0.00	0	0.00	0.00	17,657,900	EL	151000
9	Gas Regulator	Oxygen	day in demand	397.80	15	0.00	0	0.00	0.00	779,025	EL	198020
10	Gas Regulator	Acetylene	day in demand	397.80	16	0.00	0	0.00	0.00	830,986	EL	198030
11	Gas Cutting Apparatus	Acetylene	day in demand	397.80	15	0.00	0	0.00	0.00	779,025	EL	174000
12	Grouting Pump	(15-30 l/min)	day in demand	99.10	868	0.00	0	0.00	0.00	11,230,258	EL	181000
13	Grout Mixer	(100 l/min)	day in demand	99.10	341	0.00	0	0.00	0.00	4,411,864	EL	180000
Summary												
per lot												
2,166,124,668												
2,166,124,668												

D1=0.52\* nos of segmen of one girder\* nos of girder/nos of table  
 nos of segment for one girder  
 D2=0.6\* nos of girder + 7.3

REMARKS

1US\$=108JP Yen=14,100VND

CAN THO BRIDGE CONSTRUCTION PROJECT

Process Cost Equipment/Depression(Vinh Long Side) Segment: Fabric(PTI-girder) Unit: 1 lot 514263 Sheet #: PC

No.	Description	Specification	Unit	Quantity	Unit Price				Local Currency (VND)	Local Currency (US\$)	COMBINED TOTAL COST (VND)	Remarks
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)				
1	Truck Crane	40 - 45t	day in demand	108.00	0	0.00	2,077,756	0.00	0.00	224,397,648	EL 125030	
2	Heavy Track Carrier for girder	Doublegige Rotary Type 40t	day in demand	561.60	2,869	0.00	0	0.00	0.00	210,355,028	EL 198035	
3	Heavy Track Carrier for girder	Doublegige 15t	day in demand	2,246.40	1,793	0.00	0	0.00	0.00	525,851,014	EL 198017	
4	Hydraulic Jack	50t with Inner Pump type	day in demand	1,123.20	406	0.00	0	0.00	0.00	59,535,814	EL 148050	
5	Track (per100m) for Precast Girder	30kg/m including Sleeper	day in demand	138.15	1,045	0.00	0	0.00	0.00	18,847,914	EL 147010	
6	Tensioning Jack Pump	400t	day in demand	561.60	4,050	0.00	0	0.00	0.00	296,946,000	EL 178030	
6	Tensioning Jack Pump	3.7kW	day in demand	561.60	2,290	0.00	0	0.00	0.00	167,962,800	EL 179000	
6	Tensioning Jack Pump	29.4kN (3.0t) * 1.5m	day in demand	1,123.20	85	0.00	0	0.00	0.00	12,464,400	EL 151000	
9	Gas Regulator	Oxygen	day in demand	280.80	15	0.00	0	0.00	0.00	549,900	EL 198020	
10	Gas Regulator	Acetylene	day in demand	280.80	16	0.00	0	0.00	0.00	586,586	EL 198030	
11	Gas Cutting Apparatus	Acetylene	day in demand	280.80	15	0.00	0	0.00	0.00	549,900	EL 174000	
12	Grouting Pump	(15-30 l/min)	day in demand	72.10	868	0.00	0	0.00	0.00	8,170,558	EL 181000	
13	Grout Mixer	(100 l/min)	day in demand	72.10	341	0.00	0	0.00	0.00	3,209,839	EL 180000	
	Summary									1,529,367,401		
	per lot									1,529,367,401		

REMARKS  
 D1=0.52\* nos of segmen of one girder\* nos of girder/nos of table  
 n=nos of segment for one girder  
 D2=0.6\* nos of girder + 7.3























1US\$=108JP Yen=14,100VND

CAN THO BRIDGE CONSTRUCTION PROJECT

Process Cost (450kN, 1S19.3)

Unit: 10

Sheet #: FC

Transverse Prestressing Work (PTI-girder)

515152

Remarks

No.	Description	Specification	Unit	Quantity	Unit Price			COMBINED TOTAL COST (VND)			Remarks
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)	
1	Foreman	Local 1*0.4	M/day	0.40	0	0.00	146,392	0.00	0.00	58,557	L 101000
2	Skilled Labor	Local 1*1.3	M/day	1.30	0	0.00	118,898	0.00	0.00	154,567	L 104000
3	Common Labor	Local 1*0.8	M/day	0.80	0	0.00	58,671	0.00	0.00	46,937	L 103000
4	Anchorage of PC Cable (Fixed Side)	ITI19.3	nos	10.00	2,728	0.00	0	0.00	0.00	3,561,556	M 140035
5	Anchorage of PC Cable (Tensioning Side)	ITI19.3	nos	10.00	2,320	0.00	0	0.00	0.00	3,028,889	M 140055
Summary											
per cable											
REMARKS											

6,850,505

685,051

1US\$=108JP Yen=14,100VND

CAN THO BRIDGE CONSTRUCTION PROJECT  
 Process Cost Transverse Prestressing Work (PTI-girder) (570KN, IS21.8) Unit: 10 cable  
 Sheet #: PC 515153

No.	Description	Specification	Unit	Quantity	Unit Price			COMBINED TOTAL COST (VND)			Remarks
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)	
1	Foreman	Local 1*0.4	M/day	0.40	0	0.00	146,392	0.00	58,557	101000	
2	Skilled Labor	Local 1*1.3	M/day	1.30	0	0.00	118,898	0.00	154,567	104000	
3	Common Labor	Local 1*0.8	M/day	0.80	0	0.00	58,671	0.00	46,937	103000	
4	Anchorages of PC Cable (Fixed Side)	IT19.3	nos	10.00	2,728	0.00	0	0.00	3,561,556	140035	
5	Anchorages of PC Cable (Tensioning Side)	IT19.3	nos	10.00	2,320	0.00	0	0.00	3,028,889	140055	
Summary											
per cable											
REMARKS											
685,505											
685,051											









