

1US\$=108JP Yen=14,100VND

CAN THO BRIDGE CONSTRUCTION PROJECT

Process Cost Stay Cable Anchorage Installation (MB) (Pylon Side) type 2 Unit: 1 set Sheet #: PC 615332

No.	Description	Specification	Unit	Quantity	Unit Price			COMBINED TOTAL COST (VND)			Remarks	
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)	Local Currency (VND)	Local Currency (US\$)		
1	Stay Cable Anchorage Installation (MB)	(Pylon Side)(1/2)	set	1.00	0	0.00	0	0.00	0	0	615310	0 PC
2	Stay Cable Anchorage Installation (MB)	(Pylon Side)(2/2)	set	1.00	0	0.00	0	0.00	0	0	615320	0 PC
3	Foreman	1*0.5	M/day	0.50	32,100	0.00	0	0.00	0	0	130000	L
4	Skilled labor	1*4.0	M/day	4.00	9,550	0.00	0	0.00	0	0	131000	L
5	Carpenter	1*4.0	M/day	4.00	0	0.00	96,255	0.00	0	0	112000	L
6	Welder	1*2.0	M/day	2.00	0	0.00	96,255	0.00	0	0	111000	L
7	Anchorage of Stay Cable (Pylon Side)	Type 2	set	1.00	0	4,155.89	0	0.00	0	0	200312	M
Summary											66,258,218	
per set											66,258,218	
REMARKS												

1US\$=108JP Yen=14,100VND

CAN THO BRIDGE CONSTRUCTION PROJECT												
Process Cost												
Protective Pipe Installation (MB)												
Unit: 100 m												
Sheet #: PC 615430												
No.	Description	Specification	Unit	Quantity	Unit Price			COMBINED TOTAL COST (VND)			Remarks	
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)	Local Currency (VND)	Local Currency (US\$)		
1	Foreman	Foreign	M/day	1.50	32,100	0.00	0	0.00	0	6,286,250	L	130000
2	Skilled labor	Foreign	M/day	14.00	9,550	0.00	0	0.00	0	17,455,278	L	131000
3	Common Labor	Local	M/day	14.00	0	0.00	58,671	0.00	0	821,394	L	103000
4	Protective Pipe Installation (MB)	(1/3)	lot		0	0.00	0	0.00	0	0	PC	615400
5	Protective Pipe Installation (MB)	(2/3)	lot		0	0.00	0	0.00	0	0	PC	615410
6	Protective Pipe Installation (MB)	(3/3)	lot		0	0.00	0	0.00	0	0	PC	615420
7	Miscellaneous Fee	5 % of above								1,228,146		
Summary												
per m												
REMARKS												
										25,791,068		
										257,911		

1US\$=108JP Yen=14,100VND

CAN THO BRIDGE CONSTRUCTION PROJECT												
Process Cost												
Unit: 1 m3												
Sheet #: PC 615490												
No.	Description	Specification	Unit	Quantity	Unit Price			COMBINED TOTAL			Remarks	
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)		
1	Foreman	1*2.5	M/day	2.50	32,100	0.00	0	0.00	0	0.00	10,477,083 L	130000
2	Skilled labor	1*12.0	M/day	12.00	9,550	0.00	0	0.00	0	0.00	14,961,667 L	131000
3	Common Labor	1*7.5	M/day	7.50	0	0.00	58,671	0.00	0	0.00	440,033 L	103000
4	Portland Cement	1.290/m3*1.25	t	1.61	0	0.00	696,291	0.00	0	0.00	1,121,029 M	106000
5	Admixture for Grout in Stay Cable Pipe	15.5kg/m3*1.25	kg	19.38	0	2.46	0	0.00	0	0.00	672,147 M	200410
6					0		0		0		0	
7					0		0		0		0	
8					0		0		0		0	
9					0		0		0		0	
10					0		0		0		0	
11					0		0		0		0	
12	Ancillary Materials	1.5 % of above Material Cost									10,082	
Summary											27,682,041	
per m3											27,682,041	
REMARKS												

1US\$=108JP Yen=14,100VND

CAN THO BRIDGE CONSTRUCTION PROJECT
 Process Cost

Soil improvement No.4

Unit: 1

Sheet #: PC

.lot

618290

No.	Description	Specification	Unit	Quantity	Unit Price				COMBINED TOTAL COST (VND)		Remarks
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)			
1	Spreading & Compaction (Temporary Yard)	Aggregate I=200mm	m2	195,000	0	0.00	33,202	0.00	6,474,390,000	703110	PC
2	Loading, Transportation (L=2.0 km)	L/C	m3	52,000	0	0.00	8,427	0.00	438,204,000	135500	PC
3											
4											
5											
6											
7											
8											
9											
10											
Summary									6,912,594,000		
per lot									6,912,594,000		
REMARKS											
L=1.2, C=0.9											

1US\$=108JP Yen=14,100VND

CAN THO BRIDGE CONSTRUCTION PROJECT												
Expansion Joint Installation (MB)												
300mm												
Unit: 10 nos.												
Sheet #: 521510 619110												
No.	Description	Specification	Unit	Quantity	Unit Price			COMBINED TOTAL COST (VND)			Remarks	
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)		
1	Foreman	Foreign	M/day	1.60	32,100	0	0.00	0	0.00	6,705,333	L	130000
2	Skilled labor	Foreign	M/day	5.60	9,550	0	0.00	0	0.00	6,982,111	L	131000
3	Common Labor	Local	M/day	6.40	0	58,671	0.00	58,671	0.00	375,494	L	103000
4	Miscellaneous Fee	15 % of above								2,109,441		
5	Generator	Gasoline 2KVA	day in demand	1.00	0	68,620	0.00	68,620	0.00	68,620	EL	137110
7	Air Compressor	5m3/min	day in demand	1.00	0	283,251	0.00	283,251	0.00	283,251	EL	187110
8	Rebar Cutter & Rebar Bender		day in demand	1.30	0	103,206	0.00	103,206	0.00	134,168	EL	175000
9	Truck Crane	5t	day in demand	1.00	0	292,034	0.00	292,034	0.00	292,034	EL	123050
10	Expansion Joint	300mm	m	10.00	706,400	0	0.00	0	0.00	922,244,444	M	150630
Summary											939,194,897	
per nos.											93,919,490	
REMARKS												

