

JAPAN INTERNATIONAL COOPERATION AGENCY (JICA)

**MINISTRY OF TECHNIQUE AND INTERNATIONAL COOPERATION (SETCO)
NATIONAL SERVICE AUTHORITY FOR WATER SUPPLY AND SEWERAGE (SANAA)**

THE STUDY

**ON WATER SUPPLY SYSTEM
FOR TEGUCIGALPA URBAN AREA
IN THE REPUBLIC OF HONDURAS**

FINAL REPORT

SUPPORTING REPORT

JANUARY 2001

PACIFIC CONSULTANTS INTERNATIONAL

Foreign Currency Exchange Rates Applied in the Study

Currency	Exchange Rate/USD
Honduran Lempiras (Lps)	14.87
Japanese Yen (JPY)	107.9

(Rate as of the end of June 2000)

CONTENTS OF SUPPORTING REPORT

SUPPORTING-A GEOLOGICAL SURVEY

1	GROUNDWATER.....	A - 1
1.1	AQUIFER TYPE.....	A - 1
1.2	HYDROGEOLOGICAL CHARACTERISTICS.....	A - 2
1.3	POSSIBILITY OF THE GROUNDWATER DEVELOPMENT FOR WATER SUPPLY	A - 3
1.4	RECOMMENDATION.....	A - 4
2.	GEOLOGY.....	A - 9
2.1	REGIONAL GEOLOGY.....	A - 9
2.2	SEISMICITY	A -11
3.	GEOLOGICAL STUDY FOR DAM.....	A -17
3.1	GEOLOGICAL INVESTIGATION.....	A -17
3.2	LOS LAURELES II DAM.....	A -18
3.3	SABACUANTE DAM.....	A -21

SUPPORTING-B TOPOGRAPHICAL SURVEY

1.	GENERAL.....	B - 1
2.	ITEMS OF SURVEY.....	B - 1
3.	PURPOSES OF SURVEY.....	B - 1
4.	SURVEY RESULTS.....	B - 2
4.1	TOPOGRAPHIC MAP.....	B - 2
4.2	RIVER SURVEY	B - 2
4.3	RESERVOIR SURVEY.....	B - 2
4.4	SEDIMENT TEST.....	B - 2

SUPPORTING-C LEAKAGE STUDY

1.	INTRODUCTION	C - 1
2.	FIELD SURVEY	C - 1
2.1	PURPOSES.....	C - 1
2.2	METHODS	C - 1
2.3	RESULTS OF FIELD SURVEY	C - 3
3.	ANALYSIS OF SANAA LEAKAGE REPAIRING RECORDS.....	C - 6
3.1	SANAA LEAKAGE REPAIRING.....	C - 6
3.2	CHARACTERISTICS OF LEAKAGE (BASED ON 1999 RECORDS).....	C - 6
4.	CONCLUSION.....	C - 7
4.1	LEAKAGE AMOUNT.....	C - 7
4.2	LEAKAGE CONTROL PLAN.....	C - 7
4.3	LEAKAGE CONTROL PROJECT.....	C - 8

SUPPORTING-D ENVIRONMENTAL IMPACT ASSESSMENT

1.	ENVIRONMENTAL STUDY ON DAM PROJECTS	D - 1
1.1	GENERAL.....	D - 1
1.2	LEGAL FRAMEWORK.....	D - 1
1.3	CANDIDATE SITES AND RESERVOIR AREAS FOR DAM PROJECTS IN MASTER PLAN.....	D - 4
1.4	EXPERIENCE IN RESETTLEMENT PROJECT FOR CONCEPCION DAM	D - 7
1.5	MATEO CITY HOUSING PROJECT.....	D - 7
1.6	FOREST FIRES	D -11
1.7	POPULATION	D -12
2.	WATER QUALITY ANALYSES.....	D -14
2.1	GENERAL.....	D -14

2.2	WATER QUALITY STANDARDS IN HONDURAS	D -14
2.3	WATER QUALITY OBSERVATION IN THE BASIN	D -16
2.4	INDUSTRIES/URBAN & MILITARY SETTLEMENTS IN GUACERIQUE RIVER BASIN.....	D -17
2.5	WATER QUALITY SIMULATION	D -19
3.	ENVIRONMENTAL IMPACT ASSESSMENT (EIA)	D -21
3.1	PROCEDURES TO OBTAIN ENVIRONMENTAL LICENSE	D -21
3.2	RESULTS OF PRELIMINARY ENVIRONMENTAL IMPACT ASSESSMENT.....	D -22
4.	CONCLUSIONS AND RECOMMENDATIONS	D -24
	REFERENCES	D -47
	ABBREVIATIONS.....	D -49

SUPPORTING-E WATER UTILIZATION SURVEY

1.	SURVEY DESIGN.....	E - 1
1.1	OBJECTIVES	E - 1
1.2	SURVEY METHOD	E - 1
1.3	SAMPLING DESIGN.....	E - 1
1.4	DESIGN OF QUESTIONNAIRES.....	E - 2
1.5	SURVEY PROCEDURE	E - 4
2.	FIELD SURVEY	E - 5
3.	ANALYSIS OF DOMESTIC USERS OF SANAA.....	E - 5
3.1	MAJOR ATTRIBUTES OF EACH CLASS	E - 5
3.2	WATER UTILIZATION	E - 6
3.3	WILLINGNESS TO PAY.....	E - 9
4.	ANALYSIS OF NON-DOMESTIC USERS OF SANAA	E -11
4.1	GENERAL CHARACTERISTICS.....	E -11
4.2	WATER UTILIZATION	E -11
4.3	WILLINGNESS TO PAY	E -12
5.	ANALYSIS OF NONUSERS OF SANAA	E -13
5.1	MAJOR ATTRIBUTES	E -13
5.2	WATER UTILIZATION	E -13
5.3	WILLINGNESS TO PAY.....	E -14
ANNEX-1	QUESTIONNAIRES FOR DOMESTIC USERS	
ANNEX-2	QUESTIONNAIRES FOR NON-DOMESTIC USERS	
ANNEX-3	QUESTIONNAIRES FOR NONUSERS	

SUPPORTING-F HYDROLOGICAL ANALYSIS

1.	GENERAL	F - 1
1.1	INTRODUCTION	F - 1
1.2	OBJECTIVE AND SCOPE	F - 1
1.3	GENERAL HYDROLOGICAL CONDITION	F - 2
1.4	LITERATURE REVIEW	F - 2
2.	GUACERIQUE RIVER BASIN	F - 5
2.1	RIVER CONDITION	F - 5
2.2	AVAILABLE DATA	F - 5
2.3	FREQUENCY ANALYSIS	F - 7
2.4	RAINFALL – RUNOFF ANALYSIS	F - 9
2.5	WATER BALANCE ANALYSIS	F -10
3.	SABACUANTE RIVER BASIN	F -19
3.1	RIVER CONDITION	F -19
3.2	AVAILABLE DATA	F -19
3.3	FREQUENCY ANALYSIS	F -20

3.4 RAINFALL – RUNOFF ANALYSIS	F-20
3.5 WATER BALANCE ANALYSIS	F-21
4. TATUMBLA RIVER BASIN	F-24
4.1 RIVER CONDITION	F-24
4.2 AVAILABLE DATA	F-24
4.3 FREQUENCY ANALYSIS	F-25
4.4 RAINFALL – RUNOFF ANALYSIS	F-26
4.5 WATER BALANCE ANALYSIS	F-27
5. PROPOSED LOS LAURELES II DAM	F-28
5.1 HYDRAULIC SIMULATION	F-28
5.2 HYDRAULIC SIMULATION RESULTS	F-32
5.3 DAM OPERATION FOR WATER SUPPLY	F-34
5.4 DAM OPERATION FOR FLOOD CONTROL	F-35
6. REFERENCES	F-46
APPENDIX F	
AF.1 THEORETICAL APPROACH	AF-1
AF.1.1 FREQUENCY ANALYSIS	AF-1
AF.1.2 RAINFALL – RUNOFF ANALYSIS	AF-3
AF.1.3 HYDRAULIC SIMULATION	AF-5
AF.2 SUPPLEMENTAL DATA ON GUACERIQUE RIVER BASIN	AF-7
AF.3 SUPPLEMENTAL DATA ON SABACUANTE RIVER BASIN	AF-18
AF.4 SUPPLEMENTAL DATA ON TATUMBLA RIVER BASIN	AF-21

SUPPORTING-G POPULATION PROJECTION AND WATER DEMAND FORECAST

1. INTRODUCTION	G-1
1.1 GENERAL	G-1
1.2 WATER SUPPLY POLICIES	G-1
1.3 WATER DEMAND FORECAST METHOD	G-2
2. POPULATION PROJECTION	G-2
2.1 BOUNDARY OF URBAN AREA	G-2
2.2 ESTIMATION OF EXISTING POPULATION	G-3
2.3 PROJECTION OF TOTAL URBAN POPULATION	G-4
2.4 POPULATION PROJECTION FOR EACH NEIGHBORHOOD	G-5
3. SERVICE AREA AND SERVICE POPULATION	G-8
3.1 SERVICE AREA	G-8
3.2 CLASSIFICATION OF NEIGHBORHOODS	G-8
3.3 SERVICE POPULATION PROJECTION	G-9
4. ANALYSIS ON EXISTING WATER CONSUMPTION	G-10
4.1 BASE DATA	G-10
4.2 COMPOSITION OF EXISTING WATER CONSUMPTIONS	G-10
4.3 EXISTING UNIT WATER CONSUMPTION AND DEMAND FOR DOMESTIC USE	G-11
5. WATER DEMAND FORECAST	G-12
5.1 DOMESTIC USE	G-12
5.2 NON-DOMESTIC USE	G-12
5.3 RESULT OF WATER DEMAND FORECAST	G-13
REFERENCES	G-23

SUPPORTING-H WATER SOURCE DEVELOPMENT PLAN

1. GENERAL	H-1
2. REVIEW OF PREVIOUS STUDIES AND PLAN	H-1
2.1 CHRONOLOGY OF PLANS FOR WATER SUPPLY SYSTEM	H-1
2.2 1978-1986 M/P	H-2

2.3	1985-1986 DEMAND PROJECTION BY BCEOM	H - 2
2.4	1987 M/P	H - 2
2.5	1990 REVISED M/P	H - 2
3.	WATER RESOURCES POTENTIAL IN THE STUDY AREA.....	H - 2
3.1	ISOHYETAL MAP OF THE AREA	H - 2
3.2	GROUND WATER OF THE AREA.....	H - 2
3.3	WATER RESOURCES POTENTIAL IN THE AREA	H - 3
4.	PRESENT WATER RESOURCES USE IN THE STUDY AREA.....	H - 3
4.1	WATER USE FOR AGRICULTURE.....	H - 3
4.2	WATER USE BY SANAA.....	H - 4
4.3	PROBLEMS OF WATER SOURCES	H - 5
5.	CANDIDATE PROJECTS FOR WATER SOURCE DEVELOPMENT	H - 6
5.1	GENERAL.....	H - 6
5.2	LOS LAURELES II DAM.....	H - 6
5.3	SEDIMENT EXCAVATION WITH LOS LAURELES II DAM.....	H - 6
5.4	SEDIMENT EXCAVATION WITHOUT LOS LAURELES II DAM	H - 7
5.5	QUIEBRA MONTES DAM	H - 7
5.6	SABACUANTE DAM.....	H - 7
5.7	TATUMBLA DAM.....	H - 8
6.	SELECTION OF WATER SOURCE DEVELOPMENT PROJECTS FOR THE MASTER PLAN.....	H - 8
6.1	GENERAL.....	H - 8
6.2	LOS LAURELES II DAM.....	H - 9
6.3	QUIEBRA MONTES DAM	H - 12
7.	SELECTION OF WATER SOURCE DEVELOPMENT PROJECTS FOR THE FEASIBILITY STUDY	H - 13
7.1	GENERAL.....	H - 13
7.2	SELECTION CRITERIA.....	H - 13
7.3	SELECTION OF THE PROJECTS	H - 13
7.4	CONCLUSION	H - 14
8.	FEASIBILITY STUDY FOR THE PRIORITY PROJECT.....	H - 15
8.1	GENERAL.....	H - 15
8.2	FURTHER STUDIES FOR LOS LAURELES II DAM	H - 15
8.3	OPERATION AND MAINTENANCE.....	H - 17
8.4	ORGANIZATION.....	H - 20
8.5	CONSTRUCTION PLAN.....	H - 20
8.6	COST ESTIMATE.....	H - 20

SUPPORTING-I FACILITY PLANNING FOR WATER SOURCE DEVELOPMENT

1.	DESIGN OF LOS LAURELES II DAM	I - 1
1.1	DESIGN DESCRIPTION OF LOS LAURELES II DAM AND RESERVOIR.....	I - 1
1.2	STUDY OF LAYOUT AND TYPE OF LOS LAURELES II DAM	I - 3
1.3	STABILITY ANALYSIS OF DAM BODY	I - 5
1.4	HYDRAULIC ANALYSIS OF SPILLWAY	I - 7
1.5	DESIGN OF SEDIMENT CONTROL STRUCTURE.....	I - 7
2.	DESIGN DESCRIPTION OF QUIEBRA MONTES DAM AND RESERVOIR	I - 8
3.	DESIGN DESCRIPTION OF SABACUANTE DAM AND RESERVOIR.....	I - 11
4.	DESIGN DESCRIPTION OF TATUMBLA DAM AND RESERVOIR.....	I - 13

SUPPORTING-J WATER SUPPLY SYSTEM PLANNING

1.	INTRODUCTION	J - 1
2.	EXISTING CONDITIONS OF WATER SUPPLY SYSTEM.....	J - 1

2.1	OUTLINE.....	J - 1
2.2	INTAKE FACILITY.....	J - 3
2.3	CONDUCTION FACILITY	J - 3
2.4	WATER TREATMENT PLANT.....	J - 5
2.5	TRANSMISSION FACILITY.....	J - 8
2.6	WATER DISTRIBUTION FACILITY	J -12
3.	RECENT AND ON-GOING PROJECT.....	J -16
3.1	OUTLINE.....	J -16
3.2	MAIN PROJECTS EXECUTED DURING THE LAST FIVE YEARS.....	J -19
3.3	OTHER PROJECTS.....	J -26
4.	SYSTEM PLANNING OF CONDUCTION AND TREATMENT SYSTEMS.....	J -27
4.1	PLANNING APPROACH	J -27
4.2	ALTERNATIVE STUDIES FOR SYSTEM OPTIMIZATION.....	J -29
4.3	RESULT OF SYSTEM PLANNING OF CONDUCTION AND TREATMENT SYSTEMS	J -32
5.	SYSTEM PLANNING OF DISTRIBUTION SYSTEM.....	J -33
5.1	PLANNING APPROACH	J -33
5.2	PROPOSED DISTRIBUTION AREAS FOR THE YEAR 2015	J -34
5.3	INSTITUTIONAL RECOMMENDATIONS CONCERNING DISTRIBUTION SYSTEM.....	J -34

SUPPORTING-K FACILITY PLANNING OF WATER SUPPLY SYSTEM

1.	PLANNING BASIS.....	K - 1
2.	FACILITY PLAN OF QUIEBRA MONTES WTP AND ITS CONDUCTION LINE.....	K - 1
2.1	CONDUCTION FACILITY	K - 1
2.2	QUIEBRA MONTES WTP.....	K - 2
2.3	FACILITIES REQUIRED FOR JOINT OPERATION WITH LOS LAURELES WTP.....	K - 3
3.	FACILITY PLAN OF TRANSMISSION FACILITIES	K - 4
3.1	PLANNING CONDITIONS	K - 4
3.2	DESIGN CRITERIA	K - 5
3.3	QUIEBRA MONTES SYSTEM	K - 5
3.4	LOS LAURELES SYSTEM	K - 8
3.5	CONCEPCION SYSTEM.....	K -10
3.6	PICACHO SYSTEM	K -15
3.7	OPERATING CONDITIONS	K -16
4.	FACILITY PLAN OF DISTRIBUTION FACILITIES	K -18
4.1	DISTRIBUTION RESERVOIR.....	K -18
4.2	DISTRIBUTION PIPELINES.....	K -23
5.	FACILITY PLAN FOR WATER SUPPLY SYSTEM BY TANK LORRIES	K -28
6.	OPERATION AND MAINTENANCE PLAN	K -29
6.1	OUTLINE.....	K -29
6.2	OPERATION OF PICACHO WATER TREATMENT PLANT.....	K -29
6.3	WATER QUANTITY CONTROL.....	K -30
6.4	WATER QUALITY CONTROL.....	K -30
6.5	DAILY OPERATION AND MAINTENANCE ACTIVITIES.....	K -30
6.6	REQUIRED PERSONNEL	K -31

SUPPORTING-L COST ESTIMATES

1.	COST ESTIMATES FOR WATER SOURCE FACILITIES	L - 1
1.1	LOS LAURELES II DAM PROJECT	L - 1
1.2	QUIEBRA MONTES DAM PROJECT.....	L - 1
2.	WATER SUPPLY FACILITIES	L - 1
2.1	CONSTRUCTION COST FOR FACILITIES OF MASTER PLAN.....	L - 1

2.2	OPERATION AND MAINTENANCE COST OF WATER SUPPLY FACILITIES	L -11
2.3	INVESTMENT SCHEDULE OF MASTER PLAN	L -28
3.	PROCUREMENT CONDITIONS IN THE FEASIBILITY STUDY	L -31
3.1	CONSTRUCTION MATERIALS	L -31
3.2	CONSTRUCTION EQUIPMENT.....	L -32
3.3	CAPABILITY OF CONSTRUCTION COMPANIES.....	L -32
4.	CONSTRUCTION-RELATED PRICES	L -36
4.1	INTRODUCTION	L -36
4.2	LONG-TERM VARIATION OF CONSTRUCTION-RELATED PRICES	L -36
4.3	PRESENT STATUS OF PRICES.....	L -36
4.4	PRICES USED IN COST ESTIMATE.....	L -43
5.	CALCULATION OF WORKABLE DAYS.....	L -43
5.1	WORKING DAYS BY CALENDAR.....	L -43
5.2	NUMBER OF DAYS OF RAINFALL.....	L -53
5.3	CALCULATION OF WORKABLE DAYS	L -55
6.	COST ESTIMATE	L -56
6.1	BASIS OF COST ESTIMATION	L -56
6.2	CONSTRUCTION METHOD	L -57
6.3	IMPLEMENTATION SCHEDULE AND TOTAL INVESTMENT	L -60
7.	A STUDY ON DREDGING OF LOS LAURELES RESERVOIR	L -66
7.1	FEATURES OF DREDGING SYSTEM.....	L -66
7.2	SYSTEM COMPONENT AND COST	L -66

SUPPORTING-M ORGANIZATION PLAN

1.	INTRODUCTION	M - 1
2.	SANAA ORGANIZATION	M - 1
2.1	OUTLINE.....	M - 1
2.2	SANAA STRUCTURE REFORM	M - 1
3.	ORGANIZATION PLAN OF SANAA METROPOLITAN DIVISION.....	M - 2
3.1	EXISTING ORGANIZATION	M - 2
3.2	PROPOSED ORGANIZATION PLAN	M - 4
3.3	REQUIRED PERSONNEL	M - 7
	REFERENCES	M -14

SUPPORTING-N FINANCIAL AND ECONOMIC ANALYSIS

1.	FINANCIAL ANALYSIS	N - 1
1.1	INTRODUCTION	N - 1
1.2	PLANNING METHOD.....	N - 1
1.3	FINANCIAL COSTS.....	N - 2
1.4	REPAYMENT SCHEDULE	N - 3
1.5	STRUCTURE OF CASH FLOW STATEMENT	N - 4
1.6	STUDY ON TARIFF LEVEL	N - 4
1.7	PROPOSED FINANCIAL PLAN.....	N - 6
2.	ECONOMIC ANALYSIS	N - 6
2.1	INTRODUCTION	N - 6
2.2	ECONOMIC BENEFITS.....	N - 6
2.3	ECONOMIC COSTS.....	N - 7
2.4	RESULTS OF ECONOMIC EVALUATION	N - 8

LIST OF TABLES

SUPPORTING-A GEOLOGICAL SURVEY

Table A.1.1	Well Inventory in Tegucigalpa managed by SANAA	A - 5
Table A.2.1	Geology in and around the Study Area	A - 9
Table A.2.2	Expected Peak Acceleration for the Ground	A -11
Table A.2.3	Chronology of the Earthquakes and Volcanic Activities in Honduras (3 sheets)	A -14
Table A.3.1	Contents of Geological Investigation	A -17
Table A.3.2	Seismic Exploration	A -17
Table A.3.3	Rock Soundness Classification for Pyroclastics.....	A -20
Table A.3.4	The Result of Lugeon Test	A -21
Table A.3.5	The Result of Lugeon Test	A -24

SUPPORTING-B TOPOGRAPHICAL SURVEY

Table B.1.1	Items of Topographical Survey	B - 1
Table B.1.2	Items of Reservoir Survey.....	B - 1
Table B.3.1	Physical Properties of Sediment.....	B - 2

SUPPORTING-C LEAKAGE STUDY

Table C.2.1	Features of the Selected Areas for Field Survey	C - 2
Table C.2.2	Survey Areas and Number of Houses Selected for Water Consumption Rates Measurement.....	C - 3
Table C.2.3	Length of Pipelines Surveyed for Leakage Sound detection.....	C - 3
Table C.2.4	Summary of Results of the Time Serial Fluctuation Measurement	C - 4
Table C.2.5	Calculation of Unaccounted Water based on Minimum Flow.....	C - 4
Table C.2.6	Leakage Ratios Estimated Based on Water Inflow and Water Consumption rates.....	C - 5
Table C.2.7	Located Leakage	C - 6
Table C.3.1	Leakage Occurrence by Pipe Size, Material and Causes	C -10
Table C.4.1	Required Manpower and Equipment for Strengthening Leakage Rearing Capacity	C - 9
Table C.4.2	Required Devices for Water Quantity Measurement.....	C - 9

SUPPORTING-D ENVIRONMENTAL IMPACT ASSESSMENT

Table D.1.1	Classification of Environmental Regulations and Penalties related to Industries (By-laws of the Gral. Law of Environment, 1993).....	D -26
Table D.1.2	Land Use Condition in the Basins of the Study Area.....	D - 4
Table D.1.3	Flora Species in the Guacerique River Basin	D - 5
Table D.1.4	Fauna Species in the Guacerique River Basin.....	D -27
Table D.1.5	Land Use in the Guacerique River Basin (Low Stream)	D - 6
Table D.1.6	Characteristics of the Housing Project Ciudad Mateo.....	D - 8
Table D.1.7	Type of Houses under Construction of Housing Project Ciudad Mateo.....	D - 8
Table D.1.8	Advance Condition of the Housing Project Ciudad Mateo	D - 8
Table D.1.9	Mitigation Measures for the Housing Project Ciudad Mateo	D - 9
Table D.1.10	Options for Solving the Problem of Mateo City (according to L. Ferraté).....	D -28
Table D.1.11	Statistics on Forest Fires in Honduras.....	D -11
Table D.1.12	Forest Fires in the Watersheds of Tegucigalpa.....	D -12
Table D.1.13	Population at Guacerique River Basin (1/2).....	D -29
Table D.1.13	Population at Guacerique River Basin (2/2).....	D -30
Table D.1.14	Summary of Population Projections at Guacerique Basin (2000-2055).....	D -14
Table D.2.1	Characteristics of Drinking Water Treatment Plants in Tegucigalpa.....	D -14
Table D.2.2	Standards for Drinking Water Quality.....	D -31
Table D.2.3	Standards for Discharges of Waste Waters to Receiver Bodies.....	D -32

Table D.2.4	Standards for Discharges of Waste Waters to Sewer Networks.....	D -15
Table D.2.5	Standards for Quality Control in Water Bodies Assigned for Drinking Water Supply to the People (Draft as of August/2000).....	D -33
Table D.2.6	Characteristics of Industries/Urban & Military Settlements located along Guacerique River Basin (1/3).....	D -34
Table D.2.6	Characteristics of Industries/Urban & Military Settlements located along Guacerique River Basin (2/3).....	D -35
Table D.2.6	Characteristics of Industries/Urban & Military Settlements located along Guacerique River Basin (3/3).....	D -36
Table D.2.7	Results of Water Quality Analysis at Oxidation Lagoon of Monte Real Housing Project	D -18
Table D.3.1	Conditions for a Project to Submit an EIA.....	D -37
Table D.3.2	Procedures for Obtaining the Environmental License (EL)	D -38
Table D.3.3	Stages of Projects for Elaboration of EIA.....	D -22
Table D.3.4	Environmental Impacts and Mitigation Measures on the Construction of Dam Los Laureles II.....	D -23
Table D.3.5	Protected Species of Flora with Vulnerability in Guacerique River Basin.....	D -23
Table D.3.6	Protected Species of Fauna Living in Guacerique River Basin.....	D -24
Table AD.1.1	Water Quality at Guacerique River (1999).....	1
Table AD.1.2	Water Quality at Sabacuante and Tatumbra Rivers (1999).....	2
Table AD.1.3	Water Quality at El Picacho (1999).....	3
Table AD.1.4	Water Quality at Los Laureles Reservoir (1999).....	4
Table AD.1.5	Water Quality at Concepcion Reservoir (1999)	5
Table AD.1.6	Water Quality at Los Laureles Treatment Plan (After Treatment) (1999).....	6
Table AD.1.7	Water Quality at Concepcion Treatment Plan (After Treatment) (1999).....	7
Table AD.1.8	Water Quality at Picacho Treatment Plan (After Treatment) (1999).....	8
Table AD.1.9	Water Quality at the Distribution Network (April/1999)	9
Table AD.1.10	Water Quality at the Distribution Network (April/1999)	10
Table AD.2.1	Vertical Sampling at Concepcion and Los Laureles Dam: Dry season (7 Samples).....	11
Table AD.2.2	Water Quality Analysis in Rivers: Dry Season (6 samples)	12
Table AD.2.3	Drinking Water Analysis (Dry Season).....	13
Table AD.2.4	Drinking Water Analysis (Dry Season).....	14
Table AD.2.5	Drinking Water Analysis (Dry Season).....	15
Table AD.2.6	Water Quality Analysis in Rivers: Rainy Season (8 samples).....	16
Table AD.2.7	Vertical Sampling at Concepcion and Los Laureles Dam: Rainy season (7 Samples)	17
Table AD.2.8	Drinking Water Analysis (Rainy Season)	18
Table AD.2.9	Drinking Water Analysis (Rainy Season)	19
Table AD.2.10	Drinking Water Analysis (Rainy Season)	20

SUPPORTING-E WATER UTILIZATION SURVEY

Table E.1.1	Selected Neighborhoods for Domestic User Samples.....	E - 2
Table E.1.2	Selected Neighborhoods for Non-user Samples.....	E - 2
Table E.2.1	Availability of Collected Samples.....	E - 5
Table E.3.1	Major Attributes.....	E - 5
Table E.3.2	Water Supply Service Duration and Possession of Storage Tank.....	E - 6
Table E.3.3	Drinking Water Source and Bottle Water Expense.....	E - 7
Table E.3.4	Water Pressure	E - 7
Table E.3.5	Color of Water.....	E - 7
Table E.3.6	Taste of Water	E - 8
Table E.3.7	Micrometer Coverage	E - 8
Table E.3.8	Water Consumption	E - 9
Table E.3.9	Acceptance to Pay for the Better Service.....	E - 9
Table E.3.10	Estimation of Willingness to Pay for the Better Service	E -10
Table E.3.11	Comparison of the Present Water Expense and WTP	E -10
Table E.3.12	Acceptance to Pay for the Existing Service	E -10

Table E.3.13	Estimation of Willingness to Pay for the Existing Service.....	E -10
Table E.3.14	Result of WTP Estimation	E -11
Table E.4.1	Industrial Category of Samples.....	E -11
Table E.4.2	Water Supply Service Duration and Possession of Storage Tank.....	E -11
Table E.4.3	Water Pressure and Quality.....	E -12
Table E.4.4	Acceptance to Pay for the Better Service.....	E -12
Table E.4.5	Estimation of Willingness to Pay	E -12
Table E.4.6	Acceptance to Pay for the Existing Service	E -13
Table E.4.7	Willingness to Pay for the Existing Service	E -13
Table E.5.1	Major Attributes.....	E -13
Table E.5.2	Consumption of Water from Private Vender and SANAA Tank Lorry	E -14
Table E.5.3	Water Quantity and Quality	E -14
Table E.5.4	Acceptance to Pay.....	E -14
Table E.5.5	Estimation of Willingness to Pay	E -14

SUPPORTING-F HYDROLOGICAL ANALYSIS

Table F.1.1	Precipitation in the Study Area	F - 2
Table F.1.2	Summary of the Proposed Dams by SANAA in 1989	F - 3
Table F.1.3	Maximum Yield of the Existing Los Laureles Dam	F - 3
Table F.2.1	Drainage Basins of Guacerique River	F - 5
Table F.2.2	Rainfall Stations in the Guacerique River Basin	F - 5
Table F.2.3	Stream Gauging Stations in the Guacerique River Basin	F - 6
Table F.2.4	Raifall and Stream Gauging Stations in the Guacerique River Basin	F -15
Table F.2.5	Average Flow Rate in the Guacerique River Basin	F - 6
Table F.2.6	Annual Rainfall at Batallon, Quiebra Montes and Toncontin Stations	F - 7
Table F.2.7	Peak Rainfall during the Hurricane Mitch in 1998	F - 8
Table F.2.8	Design Maximum Daily Rainfall in the Guacerique River Basin	F - 8
Table F.2.9	Minimum Flow at Guacerique II Station	F - 9
Table F.2.10	Parameters in the Rainfall-runoff Analysis	F - 9
Table F.2.11	Runoff in the Guacerique River Basin	F -10
Table F.2.12	Water Balance Calculation for the Existing Los Laureles Dam	F -11
Table F.2.13	Maximum Yield of the Existing Los Laureles Dam	F -11
Table F.2.14	Maximum Yield of the Proposed Los Laureles II Dam	F -12
Table F.2.15	Maximum Yield of the Proposed Quiebra Montes Dam	F -12
Table F.2.16 (1)	Maximum Yields of Two Dams (Los Laureles and Los Laureles II).....	F -13
Table F.2.16 (2)	Maximum Yields of Two Dams (Los Laureles and Quiebra Montes).....	F -13
Table F.2.17	Maximum Yields of Three Dams	F -14
Table F.3.1	Drainage Basins of Sabacuante River	F -19
Table F.3.2	Rainfall Stations in the Sabacuante River Basin	F -19
Table F.3.3	Stream Gauging Station in the Sabacuante River Basin	F -19
Table F.3.4	Average Flow Rate in the Sabacuante River Basin	F -20
Table F.3.5	Design Maximum Daily Rainfall in the Sabacuante River Basin	F -20
Table F.3.6	Parameters in the Rainfall-runoff Analysis	F -21
Table F.3.7	Runoff in the Sabacuante River Basin	F -21
Table F.3.8	Maximum Yield of the Proposed Sabacuante Dam	F -21
Table F.4.1	Drainage Basin of Tatumbra River	F -24
Table F.4.2	Rainfall Station in the Tatumbra River Basin	F -24
Table F.4.3	Stream Gauging Station in the Tatumbra River Basin	F -24
Table F.4.4	Average Flow Rate in the Tatumbra River Basin	F -25
Table F.4.5	Average Annual Rainfall at El Incienso Station and El Aguacate Station.....	F -25
Table F.4.6	Design Maximum Daily Rainfall in Tatumbra River Basin	F -25

Table F.4.7	Parameters in the Rainfall-runoff Analysis	F -26
Table F.4.8	Runoff in the Tatumbla River Basin	F -26
Table F.4.9	Maximum Yield of the Proposed Tatumbla Dam	F -27
Table F.5.1	Coordinates of the Controlled Sections in Guacerique River	F -43
Table F.5.2	Coordinates of the Cross Sections in the River Model	F -29
Table F.5.3	Calculation Cases in the Hydraulic Simulation	F -30
Table F.5.4	Water Level from Hydraulic Simulation	F -32
Table F.5.5	Water Level at the Mateo Bridge	F -32
Table F.5.6	River Bed and Bank Height	F -33
Table F.5.7	Concentration Time in the Guacerique River Basin	F -38
Table F.5.8	Calculation Cases for the Impact of Gate Opening	F -41
Table F.5.9	Water Level with Different Gate Condition	F -41
Table AF.2.1	Annual Rainfall in the Guacerique River Basin	AF - 7
Table AF.2.2	Maximum, Minimum and Average Flow Rate in the Guacerique River Basin	AF - 8
Table AF.2.3	Maximum Daily and Annual Rainfall at Toncontin Station	AF - 9
Table AF.2.4	Annual Minimum Flow Rate in Guacerique River	AF -10
Table AF.2.5	H-V Curves for the Existing and Proposed Dams in the Study Area	AF -11
Table AF.3.1	Maximum, Minimum and Average Flow Rate in the Sabacuante River Basin	AF -18
Table AF.4.1	Maximum, Minimum and Average Flow Rate in the Tatumbla River Basin	AF -20

SUPPORTING-G POPULATION PROJECTION AND WATER DEMAND FORECAST

Table G.2.1	Average Household Size from 1997 to 1999.....	G - 3
Table G.2.2	Previous Projections of Urban Population in Tegucigalpa	G - 4
Table G.2.3	Projection of Total Urban Population in Tegucigalpa	G - 5
Table G.2.4	Planned Urbanization and Planned Extension of Neighborhood	G - 7
Table G.2.5	Concept of Annual Population Growth.....	G - 8
Table G.2.6	Population Projection by Neighborhood (4 sheets).....	G -14
Table G.3.1	Classification of Neighborhood by SANAA.....	G - 9
Table G.3.2	Result of Service Population Projection.....	G - 9
Table G.4.1	SANAA Sales Records from November 1999 to March 2000.....	G -18
Table G.4.2	Accounted Water Rate for Non-measured and Measured Customers.....	G -10
Table G.4.3	Composition of Water Consumption by Water Use.....	G -11
Table G.4.4	SANAA Design Standards of Unit Water Demand.....	G -11
Table G.4.5	Actual Water Consumption by Water Utilization Survey.....	G -12
Table G.5.1	Adopted Unit Water Demand.....	G -12
Table G.5.2	Result of Water Demand Forecast.....	G -19
Table G.5.3	Comparison of Water Demands in 2000 and 2015.....	G -13

SUPPORTING-H WATER SOURCE DEVELOPMENT PLAN

Table H.2.1	Chronology of Water Supply Master Plan	H - 1
Table H.4.1	Four Water Source Systems used by SANAA.....	H - 4
Table H.4.2	Present Yield Capacity of Each System	H - 4
Table H.4.3	Yield Capacity after Rehabilitation.....	H - 5
Table H.4.4	Water Source Shortage Mechanism	H - 5
Table H.4.5	Solution Alternatives	H - 5
Table H.5.1	Candidate Projects for Master Plan.....	H - 6
Table H.6.1.1	Comparison of Costs for Candidate Projects	H - 8
Table H.6.1.2	Comparison of Candidate Projects.....	H - 8
Table H.6.1.3	Water Supply System Plan	H - 9
Table H.7.1	Comparison of Two Projects.....	H -14

SUPPORTING-I FACILITY PLANNING FOR WATER SOURCE DEVELOPMENT

Table I.1.1	Stability Analysis.....	I - 6
-------------	-------------------------	-------

SUPPORTING-J WATER SUPPLY SYSTEM PLANNING

Table J.2.1	Water Sales Records of Los Filtros Water Filling Station	J - 2
Table J.2.2	Depth and Number of the Wells.....	J - 3
Table J.2.3	List of Existing Wells.....	J -36
Table J.2.4	Conduction Facility.....	J - 5
Table J.2.5	Design Capacity of Water Treatment Capacity	J - 6
Table J.2.6	Annual Conduction and Production Water Rate.....	J - 6
Table J.2.7	Example of Water Quality Analysis.....	J - 8
Table J.2.8	List of Existing Pumping Stations	J -37
Table J.2.9	Supply Condition of Distribution Areas in April 2000 (2 sheets)	J -38
Table J.2.10	Actual Water Distribution in April 2000	J -40
Table J.2.11	List of Distribution Sites.....	J -14
Table J.2.12	List of Distribution Reservoirs in Operation as of April 2000	J -41
Table J.2.13	Population and Demand by Distribution Area in 2000	J -42
Table J.3.1	Demand and Production in 1990.....	J -17
Table J.3.2	List of the Main Recent Projects (7 sheets).....	J -19
Table J.4.1	Deficit of Production Capacity on Average Daily Base	J -28
Table J.4.2	Existing Yield Capacity and Conduction and Treatment Capacities	J -29
Table J.4.3	Required Construction Cost for Each Alternative.....	J -30
Table J.4.4	Required Construction Cost for Each Alternative.....	J -31
Table J.4.5	Cost Comparison of Alternatives	J -32
Table J.4.6	Planning Bases of Queibra Montes and Los Laureles Subsystems	J -32
Table J.4.7	Production Rate of Each Subsystem	J -32
Table J.5.1	Proposed Distribution Areas in 2015 (5 sheets).....	J -43
Table J.5.2	Population and Water Demand by Distribution Area in 2015	J -48
Table J.5.3	Summary of Proposed Distribution System	J -49

SUPPORTING-K FACILITY PLANNING OF WATER SUPPLY SYSTEM

Table K.1.1	Base of Design Water Rate of Each Facility	K - 1
Table K.2.1	Specifications of Conduction Facility	K - 1
Table K.2.2	Design Criteria of Water Treatment Plant	K - 2
Table K.2.3	Design Water Qualities of Queibra Montes WTP	K - 3
Table K.2.4	Specifications of Major Facilities	K - 3
Table K.2.5	Design Criteria.....	K - 4
Table K.2.6	Specifications of Bypass Pipeline.....	K - 4
Table K.3.1	Design Criteria for Transmission Facility	K - 5
Table K.3.2	Design Hypothesis – Queibra Montes System.....	K - 6
Table K.3.3	List of Proposed Transmission Lines	K -32
Table K.3.4	List of Pumping Stations in 2015.....	K -33
Table K.3.5	Los Laureles System – Priority Criteria.....	K - 9
Table K.3.6	Design Criteria – Los Laureles System.....	K -10
Table K.3.7	Concepcion System – Priority Criteria.....	K -11
Table K.3.8	Concepcion System - Design Hypotheses.....	K -12
Table K.3.9	Production Assignment to Picacho Distribution Reservoirs	K -16
Table K.4.1	Design Criteria for Distribution Reservoir.....	K -18
Table K.4.2	Necessary Reservoir Capacities in 2015 (3 sheets).....	K -34
Table K.4.3	List of Distribution Reservoirs in 2015.....	K -37
Table K.4.4	Design Criteria for Distribution Pipeline	K -23

Table K.4.5	Summary of Facility Plan of Distribution Network	K -28
Table K.5.1	Expansion of Water Filling Stations and Tank Lorries.....	K -28
Table K.5.2	Design Condition of Required Tank Lorries	K -29
Table K.6.1	Major Check Items for Operation and Maintenance Works.....	K -31
Table K.6.2	Required Personnel for Operation of Proposed Projects	K -31

SUPPORTING-L COST ESTIMATES

Table L.1.1	Cost Estimate of Construction of Queibra Montes Dam.....	L - 2
Table L.2.1	Total Construction Cost for Facilities of Master Plan	L - 1
Table L.2.2	Total Construction Cost for Facilities of Master Plan	L - 3
Table L.2.3	Direct Construction Cost for Facilities of Master Plan and Breakdowns (2 sheets).....	L - 4
Table L.2.4	Cost for Newly Developed Distribution Pipeline.....	L - 7
Table L.2.5	Cost Estimate of Queibra Montes Water Treatment Plant.....	L - 8
Table L.2.6	Direct Construction Cost of Pumping Stations	L - 9
Table L.2.7	Cost Estimate for Installation of Water Meters	L - 9
Table L.2.8	Summary of Operation and Maintenance Cost	L -12
Table L.2.9	Investment and O/M Cost of Los Laureles WTP	L -14
Table L.2.10	Investment and O/M Cost of Conduction Facility	L -15
Table L.2.11	Investment and O/M Cost of Water Treatment Plant	L -16
Table L.2.12	Detail of O/M Cost / Electricity	L -13
Table L.2.13	Investment and O/M Cost of Transmission Pipeline.....	L -17
Table L.2.14	Investment and O/M Cost of Pumping Stations.....	L -18
Table L.2.15	Investment and O/M Cost of Distribution Reservoirs	L -19
Table L.2.16	Investment and O/M Cost of Distribution Pipeline.....	L -20
Table L.2.17	Investment and O/M Cost for Water Tank Lorries	L -22
Table L.2.18	Detailed Operation and Maintenance Costs for Tank Lorries Facilities (2 sheets).....	L -23
Table L.2.19	Investment and O/M Cost of Water Meters and Water Supply Pipe	L -25
Table L.2.20	Investment and O/M Cost of Flow Meters of Existing WTPs.....	L -26
Table L.2.21	Investment and O/M Cost of Flow Meters of Existing Pumping Stations	L -27
Table L.2.22	Investment and O/M Cost of Water Flow Meters of Existing Distribution Reservoirs	L -28
Table L.2.23	Investment Schedule (Construction of Facilities of Master Plan)	L -29
Table L.2.24	Investment Schedule of Master Plan.....	L -30
Table L.3.1	Construction Companies and Providers of Materials (2 sheets).....	L -33
Table L.3.2	Consultant Companies in Honduras.....	L -35
Table L.4.1	Variation of Market Prices of Construction Materials/ Equipment/ Labors in Lempiras	L -37
Table L.4.2	Variation of Market Prices of Construction Materials/ Equipment/ Labors in USD	L -38
Table L.4.3	Exchange Rate of Lempiras for US Dollar (1994 - 2000).....	L -39
Table L.4.4	Quoted Unit Prices of Labor (Tegucigalpa)	L -44
Table L.4.5	Institutional Payments added to Basic Wages for Labors.....	L -45
Table L.4.6	Quotation of Leasing Price of Construction Equipment (2 sheets)	L -46
Table L.4.7	Quoted Unit Prices of Construction Materials	L -48
Table L.4.8	Operation Cost of Construction Equipment (3 sheets).....	L -49
Table L.4.9	Labor Cost of Construction Work in Tegucigalpa.....	L -52
Table L.5.1	Number of Days of Rainfall.....	L -53
Table L.5.2	Monthly Rainfall (Tegucigalpa, 1963 - 1998).....	L -54
Table L.5.3	Averaged Rainfall per One Rainy Day (Tegucigalpa, 1963 - 1998).....	L -55
Table L.6.1	Design Mix of Concrete.....	L -59
Table L.6.2	Cost Comparison of Aggregate and Concrete	L -59
Table L.6.3	Plan of Aggregate Production	L -60
Table L.6.4	Plan of Concrete Production and Placing.....	L -60
Table L.6.5	Construction Schedule of Los Laureles II Dam	L -61

Table L.6.6	Estimation of Construction Cost (Los Laureles II Dam).....	L -63
Table L.6.7	Yearly Expense Program of Construction Cost.....	L -64
Table L.6.8	Investment Schedule of Los Laureles II Dam.....	L -65
Table L.7.1	Depreciation Cost of Dredging System.....	L -69

SUPPORTING-M ORGANIZATION PLAN

Table M.2.1	Number of Personnel in Divisions of SANAA.....	M - 2
Table M.3.1	Breakdown of Staff Number in the Metropolitan Division.....	M - 4
Table M.3.2	Preliminary Implementation Schedule for Commercial System.....	M - 6
Table M.3.3	Required Staff for Operation and Maintenance.....	M - 9
Table M.3.4	Required Number of Staff for Metropolitan Division.....	M - 7
Table M.3.5	Number of Service Users per One Staff.....	M - 8
Table M.3.6	Breakdown of Required Staffs for Metropolitan Division.....	M -10
Table M.3.7	Comparison of Staff Requirement.....	M - 8

SUPPORTING-N FINANCIAL AND ECONOMIC ANALYSIS

Table N.1.1	Structure of Cash Flow Statement.....	N - 4
Table N.1.2	Existing Tariff Level.....	N - 4
Table N.1.3	Domestic Tariff Level based on Affordability and Willingness to Pay.....	N - 5
Table N.1.4	Results of Sensitivity Analysis of FIRR.....	N - 6
Table N.2.1	Estimated Willingness to Pay of the Domestic Users.....	N - 7
Table N.2.2	Results of Sensitivity Analysis of EIRR.....	N - 8

LIST OF FIGURES

SUPPORTING-A GEOLOGICAL SURVEY

Figure A.1.1	Pumping yield and Depth.....	A - 7
Figure A.1.2	Hydrogeological Map in the Study Area.....	A - 8
Figure A.2.1	Geological Map in the Study Area.....	A - 8
Figure A.2.2	Distribution Map of Earthquake in the Central America.....	A -13
Figure A.3.1	Geological Information in the Basin of Los Laureles II Dam.....	A -25
Figure A.3.2	Geological Map of the Los Laureles II Reservoir (2 sheets).....	A -27
Figure A.3.3	Geological Profile of the Military Base	A -31
Figure A.3.4	Geological Map of the Los Laureles II Dam.....	A -33
Figure A.3.5	Geological Section of the Los Laureles II Dam Axis (A-A').....	A -35
Figure A.3.6	Geological Profiles of the Los Laureles II Dam (B-B', C-C')	A -37
Figure A.3.7	Rock Soundness Classification Map of the Los Laureles II Dam Axis.....	A -39
Figure A.3.8	Lugeon Map of the Los Laureles II Dam Axis (A-A').....	A -41
Figure A.3.9	Geological Information in the basin of Sabacuante Dam.....	A -43
Figure A.3.10	Geological Map of the Sabacuante Reservoir (3 sheets).....	A -45
Figure A.3.11	Geological Map of the Sabacuante Dam	A -51
Figure A.3.12	Geological Section of the Sabacuante Dam Axis (A-A') and Profile (B-B')	A -53
Figure A.3.13	Rock Soundness Classification Map of the Sabacuante Dam Axis.....	A -55
Figure A.3.14	Lugeon Map of the Sabacuante Dam Axis (A-A')	A -57

SUPPORTING-B TOPOGRAPHICAL SURVEY

Figure B.3.1	Topographic Map of Los Laureles II Reservoir	B - 4
Figure B.3.2	Topographic Map of Sabacuante Reservoir	B - 5
Figure B.3.3	Topographic Map of Los Laureles II Dam Site.....	B - 6
Figure B.3.4	Topographic Map of Sabacuante Dam Site	B - 7
Figure B.3.5	River Profile of Los Laurels Reservoir	B - 8
Figure B.3.6	Location Map of Sections (Los Laureles II Reservoir).....	B - 9
Figure B.3.7	Sections of Los Laureles II Reservoir (1/3)	B -10
Figure B.3.8	Sections of Los Laureles II Reservoir (2/3)	B -11
Figure B.3.9	Sections of Los Laureles II Reservoir (3/3)	B -12
Figure B.3.10	River Profile of Sabacuante Reservoir	B -13
Figure B.3.11	Sections of Sabacuante Reservoir (1/2)	B -14
Figure B.3.12	Sections of Sabacuante Reservoir (2/2)	B -15
Figure B.3.13	Topographic Map of Los Laureles Reservoir.....	B -16
Figure B.3.14	H-V Relationship of Los Laureles Reservoir	B -17
Figure B.3.15	Location Map of Sediment Sampling.....	B -18
Figure B.3.16	Grain Size Distribution of Sediment	B -19

SUPPORTING-D ENVIRONMENTAL IMPACT ASSESSMENT

Figure D.1.1	Forestry Protected Zones in the Study Area.....	D -39
Figure D.1.2	Example of Resettlement Project in Concepcion Dam.....	D -40
Figure D.1.3	Location of the Mateo City Housing Project.....	D -41
Figure D.1.4	Projection of Population at the Guacerique River Basin (2000—2055).....	D -13
Figure D.2.1	Application of the Current Water Quality Standards along the Hydric Network	D -42
Figure D.2.2	Sampling Points at Guacerique River Basin by SANAA (1999)	D -43
Figure D.2.3	Sampling Points at Los Laureles Reservoir by SANAA (1999)	D -44
Figure D.2.4	Sampling Points for Water Quality Survey by JICA Study (2000)	D -45
Figure D.2.5	Location of Industries/Urban & Military Settlements at Guacerique River Basin	D -46

Figure D.2.6 Simulated Eutrophication of Los Laureles II Reservoir according to Different Scenario	D -20
Figure AD.2.1 Profile of Temperature at Reservoirs	21
Figure AD.2.2 Profile of Turbidity at Reservoirs.....	22
Figure AD.2.3 Profile of PH at Reservoirs	23
Figure AD.2.4 Profile of Conductivity at Reservoirs.....	24
Figure AD.2.5 Profile of Total Dissolved Solids at Reservoirs.....	25
Figure AD.2.6 Profile of Dissolved Oxygen at Reservoirs	26
Figure AD.2.7 Profile of Manganese at Reservoirs	27

SUPPORTING-F HYDROLOGICAL ANALYSIS

Figure F.1.1 Drainage Basins in the Study Area	F - 4
Figure F.2.1 Relationship of Maximum Daily Rainfall and Return Period at Toncontin Station	F -16
Figure F.2.2 Recorded Rainfall at Toncontin during the Hurricane Mitch	F - 8
Figure F.2.3 Relationship of Minimum Flow Rate and Probability of Non-exceedance in the Guacerique River Basin	F -17
Figure F.2.4 Relationship of Maximum Flow Rate and Return Period in the Guacerique River Basin	F -18
Figure F.2.5 Simulated Hydrograph during the Hurricane Mitch in Guacerique River.....	F -10
Figure F.3.1 Relationship of Maximum Daily Rainfall and Return Period in the Sabacuante River Basin	F -22
Figure F.3.2 Relationship of Maximum Flow Rate and Return Period in the Sabacuante River Basin	F -23
Figure F.5.1 Hydrograph during the Hurricane Mitch	F -31
Figure F.5.2 Longitudinal Water Level Profile from Hydraulic Simulation	F -44
Figure F.5.3 Inundated Area from the Hydraulic Simulation	F -45
Figure F.5.4 Annual Variation of Flow Rate in Guacerique River	F -34
Figure F.5.5 Relationship of Flow Rate and Accumulated Rainfall	F -38
Figure F.5.6 Relationship of Gate Height and Outflow	F -40
Figure F.5.7 Inflow/outflow Hydrograph and Reservoir Water Level Change	F -42
Figure AF.2.1 Relationship of Rainfall and Simulated Hydrograph	AF -12
Figure AF.2.2 (1) Storage Volume of the Existing Los Laureles Dam	AF -13
Figure AF.2.2 (2) Storage Volume of the Proposed Los Laureles II Dam	AF -14
Figure AF.2.2 (3) Storage Volume of the Proposed Quiebra Montes Dam	AF -15
Figure AF.2.2 (4) Storage Volume of 2 Dams (Existing Los Laureles + Proposed Los Laureles II)	AF -16
Figure AF.2.2 (5) Storage Volume of 2 Dams (Existing Los Laureles + Proposed Quiebra Montes)	AF -17
Figure AF.2.2 (6) Storage Volume of 3 Dams (Los Laureles + Proposed Los Laureles II & Quiebra Montes)	AF -18
Figure AF.3.1 Storage Volume of the Proposed Sabacuante Dam	AF -20
Figure AF.4.1 Storage Volume of the Proposed Tatumbula Dam	AF -22

SUPPORTING-G POPULATION PROJECTION AND WATER DEMAND FORECAST

Figure G.2.1 Urbanization Limit of Tegucigalpa	G -20
Figure G.2.2 Existing Urban Area of Tegucigalpa.....	G -21
Figure G.2.3 Trend of Total Urban Population in Tegucigalpa	G - 5
Figure G.3.1 Planned Water Supply Service Area in 2015	G -22

SUPPORTING-H WATER SOURCE DEVELOPMENT PLAN

Figure H.3.1 Isohyetal Map of the Area.....	H -21
Figure H.3.2 Surface Water Resources Potential in the Area.....	H -22
Figure H.4.1 Land Use Map of the Area.....	H -23
Figure H.4.2 Comparison of Discharge at Guacerique II Station.....	H -24
Figure H.5.1 Candidate Sites of Water Resources Development	H -25
Figure H.5.2 Planning Flow of Los Laureles II Dam.....	H -26

Figure H.5.3	Sediment Distribution in Los Laureles Reservoir	H -27
Figure H.5.4	Planning Flow of Sabacuante Dam	H -28
Figure H.6.1	Water Surface Profile during Flood	H -29
Figure H.6.2	General Layout of Los Laureles II Dam	H -30
Figure H.6.3	H-V Relationship of Los Laureles II Reservoir	H -31
Figure H.6.4	Location of Alleged Land Slide	H -32
Figure H.6.5	Profile of the Slope	H -33
Figure H.6.6	Area to be Acquired.....	H -34
Figure H.6.7	Location of Sediment Excavation	H -35
Figure H.6.8	General Layout of Queibra Montes Dam (1/2)	H -36
Figure H.6.9	General Layout of Queibra Montes Dam (2/2)	H -37
Figure H.6.10	H-V Relationship of Queibra Montes Reservoir	H -38
Figure H.8.1	Relationship between the Development and Water Quality	H -39
Figure H.8.2	Flood Forecasting System.....	H -40
Figure H.8.3	Warning System.....	H -41
Figure H.8.4	Sediment Control Structure.....	H -42
Figure H.8.5	Location of Road and Pump Relocation	H -43
Figure H.8.6	Construction Schedule of Los Laureles II Dam	H -44

SUPPORTING-I FACILITY PLANNING FOR WATER SOURCE DEVELOPMENT

Figure I.1.1	Los Laureles II Dam Curve of Reservoir Capacity and Area.....	I -17
Figure I.1.2	Los Laureles II Dam Plan	I -18
Figure I.1.3	Los Laureles II Dam Profile (1).....	I -19
Figure I.1.4	Los Laureles II Dam Profile (2).....	I -20
Figure I.1.5	Los Laureles II Dam Section (1).....	I -21
Figure I.1.6	Los Laureles II Dam Section (2).....	I -22
Figure I.1.7	Los Laureles II Dam Section (3).....	I -23
Figure I.1.8	Los Laureles II Dam (Plan-1) Reservoir and Plan	I -24
Figure I.1.9	Los Laureles II Dam (Plan 1) Profile and Section	I -25
Figure I.1.10	Los Laureles II Dam (Plan -2) Reservoir and Plan.....	I -26
Figure I.1.11	Los Laureles II Dam (Plan-2) Profile and Section	I -27
Figure I.1.12	Los Laureles II Dam (Plan-3) Reservoir and Plan	I -28
Figure I.1.13	Los Laureles II Dam (Plan-3) Profile and Section	I -29
Figure I.1.14	Los Laureles II Dam (Plan-4) Reservoir and Plan	I -30
Figure I.1.15	Los Laureles II Dam (Plan-4) Profile and Section	I -31
Figure I.1.16	Sediment Control Structure Plan and Profile	I -32
Figure I.1.17	Sediment Control Structure Section.....	I -33
Figure I.2.1	Storage and Area of Queibra Montes Reservoir.....	I -34
Figure I.2.2	Queibra Montes Dam Plan and Section of Dam	I -35
Figure I.2.3	Queibra Montes Dam Profile of Dam and Spillway.....	I -36
Figure I.3.1	Storage and Area of Sabacuante Reservoir	I -37
Figure I.3.2	Sabacuante Dam Plan	I -38
Figure I.3.3	Sabacuante Dam Profile and Section	I -39
Figure I.4.1	Storage and Area of Tatumbra Reservoir	I -40

SUPPORTING-J WATER SUPPLY SYSTEM PLANNING

Figure J.2.1	Schematic Drawing of Existing Water Supply System	J -50
Figure J.2.2	General Layout of Existing Water Supply System.....	J -51
Figure J.2.3	Location of Picacho Conduction Lines	J -52
Figure J.2.4	Location of Los Laureles and Concepcion Conduction Lines.....	J -53
Figure J.2.5	Layout of Existing Picacho WTP.....	J -54

Figure J.2.6	Layout of Existing Concepcion WTP	J -55
Figure J.2.7	Flow Sheet of Existing Picacho WTP	J -56
Figure J.2.8	Flow Sheet of Existing Los Laureles and Concepcion WTPs.....	J -57
Figure J.2.9	Layout of Existing Transmission Facilities	J -58
Figure J.2.10	Flow Diagram of Existing Transmission System	J -59
Figure J.2.11	Flow Diagram of Picacho Transmission System in 2000.....	J -60
Figure J.2.12	Flow Diagram of Los Laureles Transmission System in 2000.....	J -61
Figure J.2.13	Flow Diagram of Concepcion Transmission System in 2000	J -62
Figure J.4.1	Schematic Drawing of Demand Fluctuation	J -27
Figure J.4.2	Candidate Sites for Queibra Montes WTP	J -63
Figure J.5.1	Proposed Distribution Areas in 2015	J -64

SUPPORTING-K FACILITY PLANNING OF WATER SUPPLY SYSTEM

Figure K.2.1	Flow Sheet of Treatment Process of Queibra Montes WTP.....	K -38
Figure K.2.2	Layout of Queibra Montes WTP.....	K -39
Figure K.2.3	Hydraulic Profile of Queibra Montes WTP	K -40
Figure K.3.1	General Map of Proposed Transmission System in 2015.....	K -41
Figure K.3.2	Diagram of Queibra Montes Transmission System in 2015.....	K -42
Figure K.3.3	Diagram of Los Laureles Transmission System in 2015.....	K -43
Figure K.3.4	Diagram of Concepcion Transmission System in 2015	K -44
Figure K.3.5	Diagram of Picacho Transmission System in 2015.....	K -45
Figure K.5.1	Location of Proposed Water Filling Stations in 2015.....	K -46

SUPPORTING-L COST ESTIMATES

Figure L.4.1	Variation of Price of Construction Materials in Tegucigalpa	L -40
Figure L.4.2	Variation of Leasing Price of Construction Equipment.....	L -41
Figure L.4.3	Variation of Construction Labor Prices in Tegucigalpa.....	L -42
Figure L.6.1	Location Map of Disposal Site.....	L -58
Figure L.7.1	System Components of Assumed Dredger (1/2).....	L -67
Figure L.7.2	System Components of Assumed Dredger (2/2).....	L -68

SUPPORTING-M ORGANIZATION PLAN

Figure M.2.1	Existing Organization Chart of SANAA.....	M -11
Figure M.3.1	Existing Organization Chart of SANAA Metropolitan Division.....	M -12
Figure M.3.2	Proposed Organization Chart of SANAA Metropolitan Division	M -13