

4.1-7 Thickness of Sand Layer of Filters in Mohara WTP

Existing Mohara WTP does not have any reserve of filter media, and washing, verification of grain size distribution, and supplement of filter media.

Figure 4.1-7-1 presents the results of measurements of sand layer thickness at filters No. 5 and 8.

At the filter No.5, since backwashing is supposed to be biased to eastern side filter, thickness of western side filter is almost equal to design thickness at 4 feet or 1.22 m, while eastern side filter shows a range from 2' 6" to 2' 10", 2' 8" or 0.81 m in average, which is equivalent to 41 cm decrease of filter layer thickness.

At filter No. 8, there is no difference between two filter units, and their thickness is 3' 1" to 3' 4", 3' 2" in average, and 25 cm decrease of thickness.

This decrease is enough to make surface washing ineffective. In the proposed project, purchase of reserve filter media and sand washing machine are planned for regular maintenance work of filter media.





Figure 4.1-7-1 Filter Media Depth of Existing Rapid Sand Filter

4.1-8-1






FIGURE 4.1-8-1 LAYOUT PLAN OF EXISTING FACILITIES




INTAKE PUMP
 SCALE 1 : 100

Figure 4.1-8-3 EXISTING INTAKE PUMP




Plan
Scale 1 : 1000





Section
Scale 1 : 250

FIGURE 4.1-8-4 EXISTING DESILTING BASIN




PLAN
SCALE 1:75




SECTION
SCALE 1:75

FIGURE 4.1-8-5 RAPID MIXING CHAMBER




PLAN
 SCALE 1:150




SECTION A-A
 SCALE 1:150

FIGURE 4.1-8-6 EXISTING CLARIFIER




PLAN
SCALE 1:150




SECTION A-A
SCALE 1:150

FIGURE 4.1-8-7 EXISTING FILTER



Plan
Scale 1 : 200



Section A-A
Scale 1 : 200

FIGURE 4.1-8-8 EXISTING SLUDGE TANK


Table 4.1-9-1 Results of Jar Tests

| | Raw Water | | Jar Test Results -1 | | | | Jar Test Results -2 | | | | Jar Test Results -3 | | | | Jar Test Results -4 | | | | Jar Test Results -5 | | | | Jar Test Results -6 | | | | Applied (ppm) | |
|------------|-----------|-------|---------------------|------|-------|-------|---------------------|------|-------|-------|---------------------|------|-------|-------|---------------------|------|-------|-------|---------------------|------|-------|-------|---------------------|------|-------|-------|---------------|------|
| | pH | Turb. | Alum | Lime | pH | Turb. | Alum | Lime | pH | Turb. | Alum | Lime | pH | Turb. | Alum | Lime | pH | Turb. | Alum | Lime | pH | Turb. | Alum | Lime | pH | Turb. | Alum | Lime |
| 1998/10/1 | 7.194 | 120 | 15 | 0 | 6.874 | 4.80 | 20 | 0 | 6.688 | 3.80 | 25 | 0 | 6.419 | 2.20 | 15 | 5 | 7.029 | 4.00 | 20 | 5 | 6.902 | 3.20 | 25 | 5 | 6.816 | 1.00 | 20 | 5 |
| 1998/10/4 | 7.166 | 120 | 15 | 0 | 6.811 | 5.00 | 20 | 0 | 6.580 | 3.80 | 25 | 0 | 6.402 | 1.60 | 15 | 5 | 6.978 | 4.20 | 20 | 5 | 6.889 | 3.00 | 25 | 5 | 6.828 | 0.98 | 20 | 5 |
| 1998/10/6 | 7.180 | 130 | 15 | 0 | 6.879 | 5.60 | 20 | 0 | 6.602 | 4.00 | 25 | 0 | 6.398 | 2.00 | 15 | 5 | 7.070 | 4.80 | 20 | 5 | 6.938 | 3.20 | 25 | 5 | 6.721 | 0.98 | 20 | 5 |
| 1998/10/16 | 7.029 | 100 | 15 | 0 | 6.912 | 5.00 | 20 | 0 | 6.842 | 4.20 | 25 | 0 | 6.701 | 3.40 | 15 | 5 | 7.012 | 4.20 | 20 | 5 | 6.901 | 3.40 | 25 | 5 | 6.882 | 2.00 | 20 | 5 |
| 1998/10/21 | 7.048 | 130 | 20 | 0 | 6.872 | 4.60 | 25 | 0 | 6.678 | 2.80 | 30 | 0 | 6.502 | 1.20 | 20 | 5 | 7.112 | 3.80 | 25 | 5 | 6.998 | 2.20 | 30 | 5 | 6.902 | 0.98 | 20 | 5 |
| 1998/10/22 | 7.214 | 120 | 20 | 0 | 7.046 | 4.40 | 25 | 0 | 6.902 | 3.20 | 30 | 0 | 6.698 | 2.00 | 20 | 5 | 7.228 | 3.60 | 25 | 5 | 7.016 | 3.00 | 30 | 5 | 6.922 | 1.80 | 20 | 5 |
| 1999/1/19 | 7.104 | 100 | 15 | 0 | 6.831 | 5.80 | 20 | 0 | 6.629 | 3.80 | 25 | 0 | 6.502 | 1.40 | 15 | 5 | 7.077 | 3.20 | 20 | 5 | 6.905 | 3.00 | 25 | 5 | 6.748 | 0.98 | 20 | 5 |
| 1999/1/21 | 7.190 | 80 | 15 | 0 | 6.938 | 5.60 | 20 | 0 | 6.780 | 3.40 | 25 | 0 | 6.572 | 1.00 | 15 | 5 | 7.098 | 3.00 | 20 | 5 | 6.982 | 2.80 | 25 | 5 | 6.749 | 0.90 | 20 | 5 |
| 1999/1/22 | 7.210 | 100 | 15 | 0 | 6.911 | 5.60 | 20 | 0 | 6.802 | 3.80 | 25 | 0 | 6.592 | 1.20 | 15 | 5 | 7.148 | 4.20 | 20 | 5 | 7.009 | 3.00 | 25 | 5 | 6.872 | 0.98 | 20 | 5 |
| 1999/1/24 | 7.239 | 110 | 15 | 0 | 6.982 | 5.80 | 20 | 0 | 6.770 | 4.00 | 25 | 0 | 6.580 | 1.40 | 15 | 5 | 7.118 | 4.20 | 20 | 5 | 7.018 | 3.20 | 25 | 5 | 6.832 | 1.00 | 20 | 5 |
| 1999/1/25 | 7.204 | 120 | 20 | 0 | 6.829 | 5.60 | 25 | 0 | 6.652 | 3.80 | 30 | 0 | 6.428 | 1.20 | 20 | 5 | 7.098 | 4.00 | 25 | 5 | 6.942 | 2.80 | 30 | 5 | 6.708 | 0.90 | 25 | 5 |
| 1999/1/26 | 7.280 | 130 | 20 | 0 | 6.905 | 6.00 | 25 | 0 | 6.818 | 4.20 | 30 | 0 | 6.662 | 1.60 | 20 | 5 | 7.108 | 4.40 | 25 | 5 | 7.019 | 3.00 | 30 | 5 | 6.839 | 0.98 | 25 | 5 |
| 1999/1/27 | 7.192 | 150 | 20 | 0 | 6.928 | 6.20 | 25 | 0 | 6.712 | 4.40 | 30 | 0 | 6.548 | 2.00 | 20 | 5 | 7.142 | 4.80 | 25 | 5 | 7.002 | 3.20 | 30 | 5 | 6.815 | 1.20 | 25 | 5 |
| 1999/2/24 | 7.273 | 80 | 15 | 0 | 7.002 | 5.00 | 20 | 0 | 6.873 | 3.60 | 25 | 0 | 6.608 | 1.20 | 15 | 5 | 7.140 | 4.20 | 20 | 5 | 7.017 | 3.00 | 25 | 5 | 6.910 | 0.98 | 20 | 5 |
| 1999/2/25 | 7.126 | 70 | 10 | 0 | 6.642 | 4.80 | 15 | 0 | 6.472 | 4.00 | 20 | 0 | 6.280 | 1.20 | 10 | 5 | 7.077 | 4.00 | 15 | 5 | 6.992 | 3.20 | 20 | 5 | 6.748 | 0.88 | 15 | 5 |
| 1999/2/26 | 7.302 | 50 | 10 | 0 | 7.029 | 4.40 | 15 | 0 | 6.902 | 3.60 | 20 | 0 | 6.773 | 1.00 | 10 | 5 | 7.166 | 3.80 | 15 | 5 | 7.092 | 2.80 | 20 | 5 | 7.002 | 0.80 | 15 | 5 |
| 1999/3/11 | 7.315 | 40 | 15 | 0 | 7.185 | 2.00 | 20 | 0 | 7.096 | 1.40 | 25 | 0 | 6.982 | 1.00 | 15 | 5 | 7.580 | 2.20 | 20 | 5 | 7.482 | 1.80 | 25 | 5 | 7.390 | 1.20 | 10 | 5 |
| 1999/3/18 | 7.204 | 80 | 15 | 0 | 6.902 | 5.60 | 20 | 0 | 6.742 | 4.00 | 25 | 0 | 6.501 | 2.00 | 15 | 5 | 7.148 | 4.20 | 20 | 5 | 7.079 | 2.80 | 25 | 5 | 6.920 | 1.40 | 20 | 5 |
| 1999/3/19 | 7.288 | 50 | 10 | 0 | 6.939 | 5.20 | 15 | 0 | 6.682 | 3.80 | 20 | 0 | 6.429 | 3.20 | 10 | 5 | 7.192 | 4.00 | 15 | 5 | 7.112 | 3.20 | 20 | 5 | 7.002 | 2.80 | 15 | 5 |
| 1999/3/27 | 7.394 | 50 | 10 | 0 | 7.078 | 5.40 | 15 | 0 | 6.912 | 3.60 | 20 | 0 | 6.886 | 1.80 | 10 | 5 | 7.428 | 4.40 | 15 | 5 | 7.216 | 3.00 | 20 | 5 | 7.002 | 1.20 | 15 | 5 |
| 1999/3/31 | 7.280 | 50 | 10 | 0 | 6.929 | 5.20 | 15 | 0 | 6.772 | 3.80 | 20 | 0 | 6.520 | 1.20 | 10 | 5 | 7.198 | 4.00 | 15 | 5 | 7.120 | 3.00 | 20 | 5 | 6.982 | 0.98 | 15 | 5 |
| 1999/5/24 | 7.188 | 350 | 35 | 0 | 6.742 | 5.80 | 40 | 0 | 6.477 | 4.60 | 45 | 0 | 6.328 | 2.40 | 35 | 10 | 7.180 | 4.60 | 40 | 10 | 7.102 | 2.80 | 45 | 10 | 6.821 | 1.00 | 40 | 10 |
| 1999/6/23 | 7.024 | 660 | 40 | 0 | 6.587 | 6.80 | 45 | 0 | 6.218 | 4.20 | 50 | 0 | 5.886 | 2.40 | 40 | 10 | 7.287 | 5.20 | 45 | 10 | 7.004 | 3.80 | 50 | 10 | 6.896 | 2.00 | 45 | 10 |
| 1999/6/24 | 7.180 | 640 | 40 | 0 | 6.724 | - | 45 | 0 | 6.560 | - | 50 | 0 | 6.228 | - | 40 | 5 | 7.024 | - | 45 | 5 | 6.896 | - | 50 | 5 | 6.602 | - | 45 | 5 |
| 1999/7/12 | 6.948 | 780 | 50 | 0 | 6.581 | 10.40 | 55 | 0 | 6.324 | 5.20 | 60 | 0 | 6.018 | 3.80 | 50 | 10 | 7.129 | 7.00 | 55 | 10 | 7.002 | 4.40 | 60 | 10 | 6.924 | 3.20 | 60 | 10 |
| 1999/7/13 | 6.987 | 830 | 55 | 0 | 6.524 | 16.20 | 60 | 0 | 6.218 | 6.40 | 65 | 0 | 5.892 | 4.00 | 55 | 10 | 7.180 | 10.40 | 60 | 10 | 7.087 | 5.80 | 65 | 10 | 6.924 | 3.40 | 65 | 10 |
| 1999/7/14 | 7.024 | 750 | 50 | 0 | 6.619 | 9.80 | 55 | 0 | 6.427 | 5.00 | 60 | 0 | 6.027 | 3.60 | 50 | 10 | 7.214 | 6.80 | 55 | 10 | 7.016 | 4.00 | 60 | 10 | 6.892 | 3.00 | 55 | 10 |
| 1999/8/8 | 7.204 | 160 | 15 | 0 | 6.982 | 6.20 | 20 | 0 | 6.742 | 5.00 | 25 | 0 | 6.680 | 3.20 | 15 | 10 | 7.199 | 4.80 | 20 | 10 | 7.149 | 3.20 | 25 | 10 | 7.021 | 2.60 | 20 | 10 |
| 1999/8/9 | 7.110 | 250 | 20 | 0 | 6.916 | 5.80 | 25 | 0 | 6.802 | 4.40 | 30 | 0 | 6.615 | 3.40 | 20 | 10 | 7.148 | 4.60 | 25 | 10 | 7.098 | 3.00 | 30 | 10 | 7.021 | 2.80 | 25 | 10 |
| 1999/8/10 | 7.098 | 370 | 30 | 0 | 6.877 | 6.40 | 35 | 0 | 6.692 | 4.80 | 40 | 0 | 6.429 | 3.20 | 30 | 10 | 7.120 | 4.80 | 35 | 10 | 7.002 | 3.00 | 40 | 10 | 6.911 | 2.80 | 35 | 10 |
| 1999/8/11 | 6.901 | 540 | 30 | 0 | 6.744 | 6.60 | 35 | 0 | 6.529 | 5.20 | 40 | 0 | 6.388 | 3.80 | 30 | 10 | 7.098 | 4.80 | 35 | 10 | 6.998 | 3.20 | 40 | 10 | 6.792 | 2.80 | 35 | 10 |
| 1999/8/12 | 7.116 | 780 | 45 | 0 | 6.904 | 6.80 | 50 | 0 | 6.742 | 5.00 | 55 | 0 | 6.528 | 4.20 | 45 | 10 | 7.129 | 5.00 | 50 | 10 | 7.090 | 3.20 | 55 | 10 | 6.982 | 2.80 | 50 | 10 |
| 1999/8/13 | 6.928 | 830 | 55 | 0 | 6.649 | 6.60 | 60 | 0 | 6.528 | 5.20 | 65 | 0 | 6.471 | 4.60 | 55 | 10 | 7.028 | 5.00 | 60 | 10 | 6.940 | 3.20 | 65 | 10 | 6.742 | 2.80 | 60 | 10 |
| 1999/8/14 | 6.992 | 750 | 50 | 0 | 6.782 | 6.20 | 55 | 0 | 6.577 | 4.80 | 60 | 0 | 6.329 | 3.80 | 50 | 10 | 6.986 | 4.40 | 55 | 10 | 6.892 | 3.20 | 60 | 10 | 6.642 | 2.60 | 55 | 10 |
| 1999/8/16 | 6.824 | 600 | 35 | 0 | 6.572 | 7.00 | 40 | 0 | 6.281 | 4.60 | 50 | 0 | 6.004 | 2.40 | 35 | 5 | 6.781 | 5.40 | 40 | 5 | 6.502 | 3.80 | 50 | 5 | 6.321 | 2.00 | 40 | 10 |
| 1999/9/16 | 7.228 | 140 | 20 | 0 | 7.002 | 5.80 | 25 | 0 | 6.817 | 4.00 | 30 | 0 | 6.577 | 1.20 | 20 | 5 | 7.143 | 5.00 | 25 | 5 | 7.077 | 2.80 | 30 | 5 | 6.902 | 0.98 | 25 | 5 |
| 1999/9/17 | 7.180 | 150 | 20 | 0 | 6.992 | 5.20 | 25 | 0 | 6.742 | 4.20 | 30 | 0 | 6.580 | 3.00 | 20 | 5 | 7.129 | 4.80 | 25 | 5 | 7.015 | 3.00 | 30 | 5 | 6.877 | 2.00 | 25 | 5 |
| 1999/9/20 | 7.177 | 280 | 30 | 0 | 6.920 | 6.60 | 35 | 0 | 6.742 | 4.40 | 40 | 0 | 6.529 | 2.80 | 30 | 5 | 7.119 | 5.20 | 35 | 5 | 7.071 | 3.00 | 40 | 5 | 6.870 | 2.00 | 35 | 5 |
| 1999/9/21 | 6.912 | 250 | 30 | 0 | 6.740 | 5.80 | 35 | 0 | 6.556 | 4.20 | 40 | 0 | 6.402 | 2.20 | 30 | 5 | 7.099 | 5.00 | 35 | 5 | 7.001 | 3.00 | 40 | 5 | 6.872 | 1.80 | 35 | 5 |
| 1999/9/23 | 7.012 | 200 | 20 | 0 | 6.748 | 5.80 | 25 | 0 | 6.580 | 4.40 | 30 | 0 | 6.426 | 3.80 | 20 | 5 | 7.109 | 5.20 | 25 | 5 | 6.998 | 4.00 | 30 | 5 | 6.804 | 3.40 | 30 | 5 |
| 1999/9/24 | 7.099 | 200 | 25 | 0 | 6.811 | 5.80 | 30 | 0 | 6.572 | 4.20 | 35 | 0 | 6.402 | 2.20 | 25 | 5 | 7.092 | 5.00 | 30 | 5 | 7.007 | 2.80 | 35 | 5 | 6.874 | 1.20 | 30 | 5 |
| 1999/9/25 | 7.116 | 140 | 20 | 0 | 6.921 | 6.00 | 25 | 0 | 6.742 | 4.00 | 30 | 0 | 6.502 | 2.60 | 20 | 5 | 7.098 | 5.20 | 25 | 5 | 7.021 | 3.20 | 30 | 5 | 6.877 | 1.40 | 25 | 5 |
| 1999/9/27 | 7.109 | 100 | 15 | 0 | 6.824 | 5.60 | 20 | 0 | 6.587 | 3.80 | 25 | 0 | 6.329 | 1.40 | 15 | 5 | 7.202 | 4.60 | 20 | 5 | 6.981 | 3.40 | 25 | 5 | 6.754 | 1.00 | 20 | 5 |
| 1999/9/29 | 7.210 | 90 | 20 | 0 | 6.996 | 4.40 | 25 | 0 | 6.724 | 3.00 | 30 | 0 | 6.518 | 1.80 | 20 | 5 | 7.110 | 3.20 | 25 | 5 | 6.995 | 2.40 | 30 | 5 | 6.580 | 1.00 | 20 | 5 |
| 1999/10/1 | 7.119 | 100 | 15 | 0 | 6.817 | 5.20 | 20 | 0 | 6.577 | 3.80 | 25 | 0 | 6.288 | 1.40 | 15 | 5 | 7.102 | 4.60 | 20 | 5 | 7.002 | 3.00 | 25 | 5 | 6.749 | 1.00 | 20 | 5 |
| 1999/10/3 | 7.142 | 160 | 15 | 0 | 6.882 | 5.40 | 20 | 0 | 6.629 | 3.80 | 25 | 0 | 6.420 | 1.80 | 15 | 5 | 7.112 | 4.80 | 20 | 5 | 7.012 | 3.20 | 25 | 5 | 6.811 | 1.40 | 20 | 5 |
| 1999/10/3 | 7.199 | 80 | 20 | 0 | 6.924 | 3.80 | 25 | 0 | 6.584 | 2.80 | 30 | 0 | 6.402 | 1.20 | 20 | 5 | 7.109 | 2.80 | 25 | 5 | 6.987 | 2.00 | 30 | 5 | 6.826 | 0.80 | 20 | 5 |
| 1999/10/4 | 7.098 | 150 | 20 | 0 | 6.821 | 6.00 | 25 | 0 | 6.584 | 3.80 | 30 | 0 | 6.412 | 2.00 | 20 | 5 | 6.984 | 4.60 | 25 | 5 | 6.802 | 3.40 | 30 | 5 | 6.715 | 1.20 | 25 | 5 |
| 1999/10/12 | 7.188 | 120 | 20 | 0 | 6.929 | 5.40 | 25 | 0 | 6.681 | 3.60 | 30 | 0 | 6.472 | 1.20 | 20 | 5 | 7.112 | 3.80 | 25 | 5 | 7.001 | 2.80 | 30 | 5 | 6.772 | 0.82 | 25 | 5 |
| 1999/10/18 | 7.028 | 100 | 15 | 0 | 6.642 | 4.80 | 20 | 0 | | | | | | | | | | | | | | | | | | | | |

Table 4.1-9-1 Results of Jar Tests

| | Raw Water | | Jar Test Results -1 | | | | Jar Test Results -2 | | | | Jar Test Results -3 | | | | Jar Test Results -4 | | | | Jar Test Results -5 | | | | Jar Test Results -6 | | | | Applied (ppm) | |
|-------------|-----------|-------|---------------------|------|-------|-------|---------------------|------|-------|-------|---------------------|------|-------|-------|---------------------|------|-------|-------|---------------------|------|-------|-------|---------------------|------|-------|-------|---------------|------|
| | pH | Turb. | Alum | Lime | pH | Turb. | Alum | Lime | pH | Turb. | Alum | Lime | pH | Turb. | Alum | Lime | pH | Turb. | Alum | Lime | pH | Turb. | Alum | Lime | pH | Turb. | Alum | Lime |
| 1999/11/18 | 7.346 | 60 | 15 | 0 | 7.102 | 4.20 | 20 | 0 | 6.929 | 3.60 | 25 | 0 | 6.742 | 1.80 | 15 | 5 | 7.194 | 3.20 | 20 | 5 | 7.112 | 2.80 | 25 | 5 | 6.988 | 1.00 | 20 | 5 |
| 1999/11/19 | 7.316 | 50 | 10 | 0 | 7.015 | 4.80 | 15 | 0 | 6.872 | 3.60 | 20 | 0 | 6.539 | 1.40 | 10 | 5 | 7.179 | 4.00 | 15 | 5 | 7.102 | 3.00 | 20 | 5 | 7.008 | 0.98 | 15 | 5 |
| 1999/11/24 | 7.314 | 60 | 15 | 0 | 7.112 | 4.00 | 20 | 0 | 7.004 | 3.40 | 25 | 0 | 6.872 | 1.20 | 15 | 5 | 7.328 | 3.80 | 20 | 5 | 7.168 | 3.00 | 25 | 5 | 7.002 | 0.80 | 20 | 5 |
| 1999/11/26 | 7.291 | 70 | 15 | 0 | 7.102 | 5.40 | 20 | 0 | 6.985 | 4.00 | 25 | 0 | 6.724 | 1.40 | 15 | 5 | 7.286 | 4.20 | 20 | 5 | 7.110 | 3.40 | 25 | 5 | 6.985 | 1.00 | 20 | 5 |
| 1999/11/27 | 7.318 | 100 | 15 | 0 | 7.126 | 5.40 | 20 | 0 | 6.994 | 4.00 | 25 | 0 | 6.724 | 1.80 | 15 | 5 | 7.386 | 4.40 | 20 | 5 | 7.210 | 3.60 | 25 | 5 | 7.002 | 1.40 | 20 | 5 |
| 1999/11/29 | 7.294 | 100 | 20 | 0 | 6.987 | 5.00 | 25 | 0 | 6.784 | 3.80 | 30 | 0 | 6.569 | 1.40 | 20 | 5 | 7.248 | 4.20 | 25 | 5 | 7.102 | 3.00 | 30 | 5 | 6.994 | 1.00 | 25 | 5 |
| 1999/11/30 | 7.336 | 110 | 20 | 0 | 7.118 | 5.60 | 25 | 0 | 6.996 | 4.00 | 30 | 0 | 6.804 | 1.80 | 20 | 5 | 7.412 | 4.80 | 25 | 5 | 7.248 | 3.40 | 30 | 5 | 7.007 | 1.20 | 25 | 5 |
| 1999/12/1 | 7.314 | 80 | 15 | 0 | 7.124 | 4.60 | 20 | 0 | 7.002 | 3.80 | 25 | 0 | 6.918 | 1.20 | 15 | 5 | 7.298 | 3.80 | 20 | 5 | 7.116 | 3.00 | 25 | 5 | 7.001 | 0.80 | 20 | 5 |
| 1999/12/3 | 7.296 | 80 | 15 | 0 | 7.086 | 4.80 | 20 | 0 | 6.824 | 3.80 | 25 | 0 | 6.635 | 1.20 | 15 | 5 | 7.268 | 4.20 | 20 | 5 | 7.024 | 3.20 | 25 | 5 | 6.896 | 0.80 | 20 | 5 |
| 1999/12/5 | 7.314 | 90 | 15 | 0 | 7.126 | 5.40 | 20 | 0 | 6.927 | 4.00 | 25 | 0 | 6.715 | 1.40 | 15 | 5 | 7.328 | 4.80 | 20 | 5 | 7.204 | 2.40 | 25 | 5 | 7.086 | 1.00 | 20 | 5 |
| 1999/12/6 | 7.294 | 100 | 15 | 0 | 7.018 | 6.00 | 20 | 0 | 6.813 | 4.20 | 25 | 0 | 6.597 | 2.00 | 15 | 5 | 7.286 | 5.60 | 20 | 5 | 7.048 | 3.80 | 25 | 5 | 6.904 | 1.40 | 20 | 5 |
| 1999/12/7 | 7.288 | 110 | 15 | 0 | 7.046 | 7.20 | 20 | 0 | 6.872 | 4.80 | 25 | 0 | 6.605 | 2.80 | 15 | 5 | 7.278 | 6.20 | 20 | 5 | 7.124 | 4.00 | 25 | 5 | 6.987 | 2.00 | 25 | 5 |
| 2000/1/1 | 7.296 | 110 | 20 | 0 | 7.002 | 5.00 | 25 | 0 | 6.815 | 3.60 | 30 | 0 | 6.570 | 2.20 | 20 | 5 | 7.179 | 4.20 | 25 | 5 | 7.139 | 3.00 | 30 | 5 | 6.982 | 1.80 | 25 | 5 |
| 2000/1/5 | 7.270 | 100 | 15 | 0 | 7.128 | 5.40 | 20 | 0 | 6.877 | 3.60 | 25 | 0 | 6.592 | 2.20 | 15 | 5 | 7.192 | 4.60 | 20 | 5 | 7.118 | 3.20 | 25 | 5 | 6.872 | 1.80 | 20 | 5 |
| 2000/1/10 | 7.328 | 80 | 15 | 0 | 7.010 | 5.00 | 20 | 0 | 6.865 | 3.40 | 25 | 0 | 6.670 | 1.80 | 15 | 5 | 7.192 | 4.00 | 20 | 5 | 7.149 | 3.00 | 25 | 5 | 6.992 | 1.40 | 20 | 5 |
| 2000/1/12 | 7.316 | 60 | 15 | 0 | 7.102 | 4.80 | 20 | 0 | 6.874 | 3.60 | 25 | 0 | 6.668 | 1.40 | 15 | 5 | 7.177 | 4.00 | 20 | 5 | 7.112 | 2.80 | 25 | 5 | 6.910 | 0.98 | 20 | 5 |
| 2000/1/14 | 7.269 | 70 | 15 | 0 | 7.021 | 5.20 | 20 | 0 | 6.896 | 4.00 | 25 | 0 | 6.648 | 1.80 | 15 | 5 | 7.310 | 4.60 | 20 | 5 | 7.124 | 3.40 | 25 | 5 | 7.002 | 1.20 | 20 | 5 |
| 2000/1/19 | 7.269 | 60 | 15 | 0 | 7.002 | 4.60 | 20 | 0 | 6.812 | 3.40 | 25 | 0 | 6.579 | 1.60 | 15 | 5 | 7.139 | 3.80 | 20 | 5 | 7.102 | 2.80 | 25 | 5 | 6.829 | 1.00 | 20 | 5 |
| 2000/1/24 | 7.402 | 90 | 15 | 0 | 7.102 | 5.00 | 20 | 0 | 6.829 | 4.20 | 25 | 0 | 6.677 | 1.80 | 15 | 5 | 7.174 | 3.50 | 20 | 5 | 7.133 | 3.00 | 25 | 5 | 6.838 | 1.00 | 20 | 5 |
| 2000/1/26 | 7.314 | 80 | 20 | 0 | 7.102 | 5.40 | 25 | 0 | 6.981 | 3.40 | 30 | 0 | 6.786 | 1.40 | 20 | 5 | 7.324 | 4.20 | 25 | 5 | 7.218 | 3.00 | 30 | 5 | 7.106 | 1.00 | 20 | 5 |
| 2000/1/28 | 7.262 | 90 | 15 | 0 | 7.082 | 5.20 | 20 | 0 | 6.742 | 3.80 | 25 | 0 | 6.580 | 1.40 | 15 | 5 | 7.158 | 4.60 | 20 | 5 | 7.102 | 3.20 | 25 | 5 | 6.839 | 1.00 | 25 | 5 |
| 2000/1/30 | 7.216 | 70 | 15 | 0 | 7.062 | 5.00 | 20 | 0 | 6.810 | 4.00 | 25 | 0 | 6.572 | 1.20 | 15 | 5 | 7.169 | 4.60 | 20 | 5 | 7.116 | 3.00 | 25 | 5 | 6.811 | 1.00 | 20 | 5 |
| 2000/2/3 | 7.421 | 40 | 15 | 0 | 7.029 | 4.60 | 20 | 0 | 6.872 | 3.80 | 25 | 0 | 6.654 | 1.40 | 15 | 5 | 7.196 | 3.80 | 20 | 5 | 7.142 | 3.00 | 25 | 5 | 6.982 | 0.98 | 20 | 5 |
| 2000/2/4 | 7.324 | 30 | 15 | 0 | 7.102 | 4.60 | 20 | 0 | 6.792 | 3.40 | 25 | 0 | 6.588 | 1.20 | 15 | 5 | 7.189 | 4.20 | 20 | 5 | 7.112 | 2.80 | 25 | 5 | 6.877 | 0.92 | 20 | 5 |
| 2000/2/7 | 7.328 | 30 | 15 | 0 | 7.072 | 4.80 | 20 | 0 | 6.815 | 3.60 | 25 | 0 | 6.602 | 1.00 | 15 | 5 | 7.176 | 4.40 | 20 | 5 | 7.116 | 2.80 | 25 | 5 | 6.928 | 0.96 | 20 | 5 |
| 2000/3/7 | 7.529 | 35 | 15 | 0 | 7.120 | 3.40 | 20 | 0 | 6.906 | 1.80 | 25 | 0 | 6.724 | 1.00 | 15 | 5 | 7.840 | 3.80 | 20 | 5 | 7.329 | 2.00 | 25 | 5 | 7.167 | 1.20 | 20 | 5 |
| 2000/3/10 | 7.486 | 40 | 15 | 0 | 7.114 | 4.20 | 20 | 0 | 6.921 | 3.00 | 25 | 0 | 6.204 | 1.40 | 15 | 5 | 7.548 | 4.40 | 20 | 5 | 7.269 | 3.40 | 25 | 5 | 7.072 | 1.80 | 15 | 5 |
| 2000/3/14 | 7.412 | 50 | 15 | 0 | 7.144 | 4.60 | 20 | 0 | 6.980 | 3.40 | 25 | 0 | 6.695 | 1.00 | 15 | 5 | 7.648 | 5.20 | 20 | 5 | 7.269 | 3.80 | 25 | 5 | 7.088 | 1.60 | 20 | 5 |
| 2000/3/15 | 7.482 | 40 | 15 | 0 | 7.136 | 4.00 | 20 | 0 | 6.948 | 2.80 | 25 | 0 | 6.655 | 1.00 | 15 | 5 | 7.658 | 4.40 | 20 | 5 | 7.280 | 3.20 | 25 | 5 | 7.110 | 1.80 | 20 | 5 |
| 2000/3/16 | 7.462 | 100 | 15 | 0 | 7.148 | 5.20 | 20 | 0 | 6.792 | 4.20 | 25 | 0 | 6.570 | 1.40 | 15 | 5 | 7.199 | 4.80 | 20 | 5 | 7.162 | 3.20 | 25 | 5 | 6.517 | 0.96 | 20 | 5 |
| 2000/3/17 | 7.512 | 180 | 20 | 0 | 7.149 | 5.40 | 25 | 0 | 6.922 | 4.00 | 30 | 0 | 6.574 | 1.80 | 20 | 5 | 7.226 | 4.60 | 25 | 5 | 7.182 | 3.20 | 30 | 5 | 6.811 | 1.00 | 25 | 5 |
| 2000/3/18 | 7.499 | 270 | 35 | 0 | 7.088 | 5.80 | 40 | 0 | 6.678 | 4.20 | 45 | 0 | 6.482 | 2.60 | 35 | 5 | 7.206 | 5.20 | 40 | 5 | 7.174 | 3.00 | 45 | 5 | 6.877 | 1.00 | 40 | 5 |
| 2000/3/19 | 7.281 | 280 | 35 | 0 | 6.698 | 6.00 | 40 | 0 | 6.324 | 4.00 | 45 | 0 | 6.128 | 2.20 | 35 | 5 | 6.988 | 4.80 | 40 | 5 | 6.786 | 3.40 | 45 | 5 | 6.540 | 1.60 | 40 | 10 |
| 2000/3/20 | 7.429 | 250 | 35 | 0 | 6.988 | 5.20 | 40 | 0 | 6.675 | 2.80 | 45 | 0 | 6.328 | 1.00 | 35 | 5 | 7.226 | 3.40 | 40 | 5 | 7.084 | 2.00 | 45 | 5 | 6.898 | 0.80 | 35 | 5 |
| 1999/10/11* | 7.004 | 92 | 15 | 0 | 6.886 | 5.40 | 20 | 0 | 6.710 | 4.20 | 25 | 0 | 6.624 | 2.00 | 15 | 5 | 7.102 | 4.20 | 20 | 5 | 6.996 | 3.80 | 25 | 5 | 6.910 | 1.80 | 20 | 5 |
| 1999/10/14* | 7.198 | 76 | 15 | 0 | 7.084 | 5.60 | 20 | 0 | 6.886 | 4.20 | 25 | 0 | 6.702 | 3.00 | 15 | 5 | 7.188 | 4.40 | 20 | 5 | 7.096 | 3.80 | 25 | 5 | 6.994 | 2.60 | 20 | 5 |
| 1999/10/15* | 7.196 | 88 | 15 | 0 | 7.124 | 5.40 | 20 | 0 | 6.902 | 4.00 | 25 | 0 | 6.798 | 2.80 | 15 | 5 | 7.264 | 4.20 | 20 | 5 | 7.112 | 3.80 | 25 | 5 | 7.086 | 2.40 | 20 | 5 |
| 1999/10/16* | 7.206 | 86 | 15 | 0 | 7.180 | 5.20 | 20 | 0 | 6.964 | 4.00 | 25 | 0 | 6.815 | 3.20 | 15 | 5 | 7.368 | 4.40 | 20 | 5 | 7.164 | 3.80 | 25 | 5 | 7.092 | 2.80 | 20 | 5 |
| 1999/10/16* | 7.218 | 86 | 15 | 0 | 7.180 | 5.00 | 20 | 0 | 6.964 | 3.80 | 25 | 0 | 6.815 | 3.00 | 15 | 5 | 7.268 | 4.40 | 20 | 5 | 7.164 | 3.60 | 25 | 5 | 7.092 | 2.80 | 20 | 5 |
| 1999/10/17* | 7.280 | 64 | 15 | 0 | 7.124 | 5.20 | 20 | 0 | 7.002 | 4.00 | 25 | 0 | 6.896 | 1.40 | 15 | 5 | 7.264 | 4.60 | 20 | 5 | 7.118 | 3.80 | 25 | 5 | 6.996 | 1.00 | 20 | 5 |
| 1999/10/18* | 7.028 | 76 | 15 | 0 | 6.894 | 5.20 | 20 | 0 | 6.678 | 4.00 | 25 | 0 | 6.510 | 1.80 | 15 | 5 | 7.118 | 4.40 | 20 | 5 | 6.996 | 3.60 | 25 | 5 | 6.804 | 1.20 | 20 | 5 |
| 1999/10/18* | 7.238 | 56 | 15 | 0 | 7.109 | 4.80 | 20 | 0 | 6.924 | 3.80 | 25 | 0 | 6.785 | 1.20 | 15 | 5 | 7.228 | 4.00 | 20 | 5 | 7.134 | 3.20 | 25 | 5 | 6.986 | 0.80 | 20 | 5 |
| 1999/10/19* | 7.284 | 60 | 15 | 0 | 7.018 | 5.00 | 20 | 0 | 6.896 | 3.80 | 25 | 0 | 6.628 | 1.40 | 15 | 5 | 7.296 | 4.00 | 20 | 5 | 7.124 | 3.40 | 25 | 5 | 7.006 | 1.00 | 20 | 5 |
| 1999/10/7* | 7.124 | 90 | 15 | 0 | 6.974 | 6.20 | 20 | 0 | 6.712 | 4.00 | 25 | 0 | 6.568 | 3.40 | 15 | 5 | 7.169 | 5.60 | 20 | 5 | 7.004 | 4.80 | 25 | 5 | 6.990 | 3.20 | 25 | 5 |
| 1999/10/9* | 7.218 | 94 | 15 | 0 | 7.124 | 5.40 | 20 | 0 | 7.002 | 4.00 | 25 | 0 | 6.929 | 2.80 | 15 | 5 | 7.206 | 4.00 | 20 | 5 | 7.102 | 3.80 | 25 | 5 | 6.998 | 2.20 | 20 | 5 |
| 1999/2/23* | 7.264 | 44 | 10 | 0 | 7.102 | 5.80 | 15 | 0 | 6.998 | 4.00 | 20 | 0 | 6.877 | 1.80 | 10 | 5 | 7.250 | 4.80 | 15 | 5 | 7.118 | 3.80 | 20 | 5 | 7.002 | 1.60 | 15 | 5 |
| 1999/2/27* | 7.296 | 36 | 10 | 0 | 7.109 | 5.00 | 15 | 0 | 7.084 | 3.80 | 20 | 0 | 6.998 | 1.40 | 10 | 5 | 7.312 | 4.00 | 15 | 5 | 7.248 | 3.40 | 20 | 5 | 7.106 | 1.20 | 15 | 5 |
| 1999/2/28* | 7.246 | 40 | 10 | 0 | 7.204 | 5.60 | 15 | 0 | 7.176 | 4.20 | 20 | 0 | 7.008 | 1.40 | 10 | 5 | 7.324 | 4.40 | 15 | 5 | 7.234 | 3.20 | 20 | 5 | 7.180 | 1.00 | 15 | 5 |
| 1999/4/20* | 7.394 | 168 | 20 | 0 | 7.012 | 7.40 | 25 | 0 | 6.814 | 4.00 | 30 | 0 | 6.675 | 2.20 | 20 | 5 | 7.284 | 5.00 | 25 | 5 | 7.170 | 3.60 | 30 | 5 | 6.998 | 2.00 | 25 | 5 |
| 1999/8/21* | 7.024 | 94 | 15 | 0 | 6.496 | 5.40 | 20 | 0 | 6.214 | 3.80 | 25 | 0 | 6.008 | | | | | | | | | | | | | | | |

Figure 4.1-9 Raw Water Turbidity vs. Alum Dosing Rate



4.1-9-3




FIGURE 4.1-10-1 SAMPLING POINT FOR WATER QUALITY ANALYSIS IN KALURGHAT IRP&BPS (Sampling Date 3.19.2000)

4.1-11 Monthly Water Production of Existing Facilities (1999)

| (unit: m3/day) | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | Daily Avg. |
|---------------------------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| MOD I | | | | | | | | | | | | | |
| Khulshi TW | 618 | 610 | 508 | 479 | 511 | 525 | 550 | 606 | 626 | 505 | 346 | 368 | 521 |
| Almas TW | 2,353 | 2,147 | 2,137 | 1,986 | 1,886 | 3,190 | 4,030 | 4,175 | 4,062 | 4,304 | 3,961 | 3,907 | 3,185 |
| Love Lane TW | 1,378 | 1,341 | 1,278 | 1,232 | 1,247 | 1,196 | 1,120 | 1,248 | 1,269 | 1,247 | 1,311 | 5,161 | 1,591 |
| Jubilee Road TW | 3,978 | 4,136 | 3,740 | 3,476 | 3,751 | 3,722 | 3,828 | 3,752 | 3,701 | 3,771 | 3,704 | 3,684 | 3,769 |
| Ice Factory Road TW | 2,308 | 2,135 | 2,345 | 1,990 | 2,275 | 2,260 | 2,209 | 2,269 | 2,231 | 2,216 | 2,243 | 2,295 | 2,233 |
| Collegiate School TW | 2,311 | 2,775 | 2,048 | 2,428 | 2,029 | 2,309 | 2,697 | 2,171 | 2,652 | 3,188 | 3,381 | 3,307 | 2,606 |
| Sader Ghat TW | 3,028 | 2,254 | 2,664 | 710 | 2,591 | 2,760 | 2,717 | 503 | 2,976 | 2,037 | 1,829 | 1,848 | 2,160 |
| Police Line TW | 742 | 596 | 439 | 978 | 705 | 591 | 531 | 2,705 | 621 | 584 | 506 | 582 | 801 |
| Agrabad No.3 TW | 661 | 1,128 | 500 | 541 | 585 | 582 | 655 | 598 | 594 | 573 | 633 | 801 | 651 |
| Nalapara TW | 2,848 | 587 | 3,099 | 719 | 2,972 | 2,614 | 2,301 | 2,134 | 2,383 | 2,310 | 2,545 | 3,004 | 2,310 |
| Halishahar II TW | 1,148 | 1,393 | 1,186 | 604 | 1,100 | 1,070 | 1,091 | 1,015 | 1,207 | 1,151 | 1,179 | 1,105 | 1,103 |
| Firojshah -I TW | 673 | 622 | 559 | 719 | 591 | 592 | 644 | 624 | 657 | 612 | 767 | 531 | 632 |
| Firiojshah II TW | 956 | 705 | 739 | 4,697 | 740 | 759 | 780 | 776 | 761 | 388 | 761 | 758 | 1,064 |
| Goalpara TW | 5,183 | 4,983 | 4,782 | 2,836 | 4,946 | 4,960 | 4,822 | 4,899 | 4,935 | 6,245 | 2,582 | 2,296 | 4,458 |
| Agrabad No.1 TW | 725 | 2,926 | 1,077 | 2,227 | 1,075 | 1,070 | 1,101 | 1,122 | 1,108 | 1,082 | 1,122 | 1,152 | 1,302 |
| Mehedibag TW | 4,570 | 4,401 | 4,224 | 3,982 | 4,000 | 3,603 | 3,833 | 3,810 | 3,843 | 3,773 | 3,355 | 2,963 | 3,860 |
| MOD I Total (A) | 33,479 | 32,738 | 31,327 | 29,606 | 31,003 | 31,803 | 32,910 | 32,408 | 33,626 | 33,987 | 30,225 | 33,764 | 32,246 |
| MOD II | | | | | | | | | | | | | |
| No. 1 TW | 2,168 | 2,104 | 1,472 | 1,125 | 1,235 | 1,681 | 1,065 | 1,153 | 1,031 | 1,173 | 1,055 | 1,186 | 1,366 |
| No. 2 TW | 1,516 | 2,201 | 2,864 | 3,458 | 3,201 | 2,799 | 2,236 | 2,027 | 1,546 | 1,419 | 1,366 | 1,359 | 2,164 |
| No. 3 TW | 2,907 | 2,727 | 2,200 | 1,228 | 821 | 855 | 849 | 698 | 781 | 851 | 788 | 861 | 1,290 |
| No. 4 TW | 2,817 | 2,455 | 2,081 | 1,209 | 1,108 | 914 | 798 | 671 | 683 | 687 | 807 | 706 | 1,239 |
| No. 5 TW | 1,404 | 1,314 | 1,333 | 1,022 | 901 | 1,409 | 3,596 | 3,712 | 3,806 | 3,532 | 3,349 | 2,829 | 2,359 |
| No. 6 TW | 3,212 | 3,191 | 3,045 | 1,505 | 1,376 | 1,271 | 733 | 720 | 840 | 740 | 688 | 534 | 1,478 |
| No. 7 TW | 3,670 | 3,700 | 3,588 | 3,602 | 3,670 | 3,708 | 3,393 | 3,562 | 2,750 | 2,711 | 2,861 | 2,593 | 3,315 |
| No. 8 TW | 2,636 | 2,495 | 2,939 | 2,408 | 1,718 | 1,657 | 1,498 | 1,745 | 1,575 | 1,474 | 1,702 | 1,503 | 1,943 |
| No. 9 TW | 1,924 | 1,865 | 782 | 714 | 696 | 1,447 | 2,863 | 2,635 | 2,574 | 1,903 | 1,555 | 1,183 | 1,678 |
| No. 10 TW | 2,672 | 2,527 | 2,221 | 2,223 | 1,822 | 2,250 | 1,756 | 2,383 | 1,853 | 2,240 | 2,379 | 2,405 | 2,226 |
| No. 11 TW | 3,229 | 3,619 | 2,426 | 2,716 | 3,098 | 3,396 | 3,110 | 3,075 | 3,480 | 4,898 | 3,668 | 4,030 | 3,395 |
| No. 12 TW | 3,993 | 3,535 | 2,969 | 3,034 | 2,365 | 3,154 | 3,989 | 4,107 | 3,936 | 3,481 | 2,731 | 2,138 | 3,285 |
| No. 13 TW | 2,987 | 4,549 | 4,115 | 3,848 | 5,425 | 5,268 | 4,778 | 4,879 | 4,118 | 4,534 | 4,699 | 4,633 | 4,486 |
| No. 14 TW | 530 | 494 | 461 | 480 | 631 | 1,052 | 1,070 | 1,100 | 207 | 903 | 1,377 | 1,962 | 859 |
| No. 15 TW | 2,378 | 2,372 | 2,268 | 1,654 | 1,573 | 1,458 | 1,566 | 1,172 | 1,253 | 1,173 | 1,056 | 965 | 1,570 |
| No. 16 TW | 3,995 | 3,806 | 3,778 | 3,252 | 3,611 | 3,421 | 2,401 | 1,808 | 1,631 | 1,472 | 1,314 | 1,009 | 2,618 |
| No. 17 TW | 1,189 | 1,166 | 1,114 | 1,117 | 1,116 | 1,150 | 893 | 3,256 | 3,858 | 3,686 | 3,471 | 4,959 | 2,255 |
| No. 18 TW | - | - | 2,210 | 3,831 | 2,681 | 1,751 | 1,490 | 1,108 | 1,157 | 837 | 947 | 1,690 | 1,482 |
| No. 19 TW | 4,324 | 4,196 | 4,077 | 4,493 | 5,646 | 5,751 | 5,638 | 5,488 | 5,325 | 5,047 | 3,988 | 4,959 | 4,917 |
| No. 20 TW | 2,914 | 2,837 | 2,554 | 3,405 | 3,342 | 3,308 | 3,053 | 3,562 | 3,392 | 3,296 | 3,633 | 3,398 | 3,226 |
| No. 21 TW | 2,990 | 2,399 | 2,376 | 2,323 | 2,504 | 2,339 | 2,390 | 2,206 | 2,245 | 1,945 | 1,929 | 1,690 | 2,235 |
| No. 22 TW | 3,369 | 2,374 | 3,189 | 3,011 | 3,339 | 3,311 | 2,914 | 4,137 | 3,734 | 3,842 | 3,790 | 4,119 | 3,436 |
| No. 23 TW | 1,692 | 1,580 | 1,474 | 1,339 | 1,335 | 992 | 1,211 | 3,913 | 4,169 | 4,078 | 4,026 | 4,165 | 2,504 |
| No. 24 TW | 2,644 | 2,369 | 2,091 | 2,546 | 2,665 | 2,533 | 2,882 | 3,031 | 3,215 | 2,460 | 2,561 | 2,673 | 2,641 |
| MOD II Total (B) | 60,659 | 59,874 | 57,627 | 55,543 | 55,882 | 56,875 | 56,172 | 62,149 | 59,161 | 58,381 | 55,741 | 57,550 | 57,965 |
| (A) + (B) | 94,139 | 92,612 | 88,954 | 85,149 | 86,885 | 88,678 | 89,083 | 94,557 | 92,787 | 92,367 | 85,967 | 91,314 | 90,210 |
| Kalurghat B.P.S. (C) | 46,638 | 45,850 | 43,201 | 44,488 | 44,993 | 45,189 | 47,218 | 48,826 | 47,590 | 46,905 | 44,932 | 44,601 | 45,873 |
| Mohara W.T.P. (D) | 90,417 | 90,680 | 90,002 | 90,813 | 90,745 | 90,503 | 89,785 | 89,966 | 90,018 | 89,780 | 89,831 | 90,465 | 90,246 |
| PRODUCTION TOTAL | | | | | | | | | | | | | |
| (A) + (B) + (D) | 184,555 | 183,292 | 178,955 | 175,962 | 177,630 | 179,181 | 178,867 | 184,523 | 182,805 | 182,147 | 175,798 | 181,779 | 180,457 |
| DISTRIBUTION TOTAL | | | | | | | | | | | | | |
| (A) + (C) + (D) | 170,534 | 169,268 | 164,529 | 164,907 | 166,741 | 167,495 | 169,913 | 171,200 | 171,234 | 170,672 | 164,988 | 168,830 | 168,365 |
| Distribution / Product. | 92% | 92% | 92% | 94% | 94% | 93% | 95% | 93% | 94% | 94% | 94% | 93% | 93% |
| Groundwater / Product. | 51% | 51% | 50% | 48% | 49% | 49% | 50% | 51% | 51% | 51% | 49% | 50% | 50% |
| Groundwater / Distribut. | 47% | 46% | 45% | 45% | 46% | 46% | 47% | 47% | 47% | 47% | 46% | 46% | 46% |
| MOD II / G.W. Product. | 64% | 65% | 65% | 65% | 64% | 64% | 63% | 66% | 64% | 63% | 65% | 63% | 64% |
| Kalurghat / MOD II | 77% | 77% | 75% | 80% | 81% | 79% | 84% | 79% | 80% | 80% | 81% | 78% | 79% |

Source: CWASA

CHAPTER 6

SYUDY ON MANAGERIAL ASPECTS OF WATER WORKS

6.2 Study on Chittagong Water Supply and Sewerage Authority

6.2-1 Organization/Institution of CWASA

Table 6.2-1-1 Summary of Manpower

| No | Name of Post (Class 1) | Sanctioned | Existing | Revised | Sanctioned (Revised) | Present |
|----|---|-----------------|------------|------------|----------------------|------------|
| | (Class – 1) | Before 21.12.83 | | 21.12.83 | After 21.12.83 | 2.4.2000 |
| 1 | Chairman | 1 | 1 | 1 | 1 | 1 |
| 2 | Member | - | - | - | 3 | 1 |
| 3 | Chief Engineer | 1 | 1 | 1 | 1 | - |
| 4 | Commercial Manager | 1 | - | 1 | 1 | 1 |
| 5 | Secretary | 1 | 1 | 1 | 1 | 1 |
| 6 | Superintending Engineer | 2 | 2 | 2 | 2 | 2 |
| 7 | Chief Accountant | 1 | 1 | 1 | 1 | 1 |
| 8 | Chief Revenue Officer | 1 | 1 | 1 | 1 | 1 |
| 9 | Executive Engineer | 8 | 6 | 6 | 6 | 6 |
| 10 | Senior Superintendent (Re-designated as Executive Engineer in the same scale) | 1 | - | 1 | 1 | 1 |
| 11 | Deputy Chief Accountant | 2 | 2 | 2 | 2 | 1 |
| 12 | Deputy Chief (Dev.) | 1 | - | 1 | 1 | 1 |
| 13 | Magistrate | - | - | - | 1 | 1 |
| 14 | Deputy Secretary | 1 | 1 | 1 | 1 | 1 |
| 15 | Senior Audit Officer | - | - | 1 | 1 | 1 |
| 16 | Computer Programmer | - | - | - | 1 | 1 |
| 17 | Assistant Secretary | 2 | 2 | 2 | 2 | 2 |
| 18 | Medical Officer | - | - | - | 1 | 1 |
| 19 | Asstt. Chief (Dev.) | 1 | 1 | 1 | 1 | 1 |
| 20 | Reserch Officer | 1 | 1 | 1 | 1 | 1 |
| 21 | Asstt. Engineer | 12 | 12 | 12 | 12 | 12 |
| 22 | Junior Superintendent (Re-designated as Asstt. Engineer in the same scale) | 1 | 1 | 1 | 1 | 1 |
| 23 | Superintendent Water Works | 1 | 1 | 1 | 1 | 1 |
| 24 | Internal Audit Officer | 1 | 1 | - | - | - |
| 25 | Public Relation Officer | 1 | - | 1 | 1 | - |
| 26 | Revenue Officer | 3 | 2 | 3 | 3 | 3 |
| 27 | Accounts Officer | 3 | 3 | 2 | 2 | 2 |
| 28 | Budget Officer | 1 | - | 1 | 1 | 1 |
| 29 | Purchase Officer | 1 | 1 | 1 | 1 | - |
| 30 | Estate Officer | 1 | 1 | 1 | 1 | 1 |
| 31 | Chemist & Quality Central Officer | - | - | - | - | 1 |
| | Total Class – 1 | 50 | 42 | 47 | 53 | 48 |
| | Total Class – 2 | 36 | 30 | 32 | 21 | 21 |
| | Total Class – 3 | 559 | 475 | 539 | 538 | 521 |
| | Total Class – 4 | 123 | 104 | 100 | 125 | 160 |
| | Grand Total | 768 | 651 | 718 | 737 | 750 |

The Feasibility Study on Extension and Expansion of Mohara Water Treatment Plant in Chittagong City

Questionnaire Form
“Citizen’s Awareness on Water Supply Service and Environmental Sanitation”

To the People of Chittagong

This questionnaire survey is intended to obtain information on awareness, willingness and affordability, as well as actual conditions of Chittagong people for improvement of existing water supply and sanitation conditions in the City of Chittagong being undertaken by the joint effort of the Japan International Cooperation Agency (JICA) and Chittagong Water Supply and Sewerage Authority (CWASA).

Any answer to this questionnaire survey will not used other than the above-mentioned purpose.

Thank you,

JICA Study Team and CWASA

1. Location for Residence

Name of Street, Ward and Thana:

Street, _____ Ward No. _____, Thana No. _____

2. Housing

2.1 Type of Housing

- Pucca
- Semi-Pucca
- Kutcha

2.2 Year of Construction:

- Built before 1980
- Built between 1981 and 1990
- Built between 1991 and 1995
- Built after 1996

3. Family / Income

(1) Number of inhabitant: _____ persons

(2) Number of family: _____ family

(3) Number of income earners: _____ person

(4) Sum of annual income:

How much is average annual income of your family?

_____ TK (= monthly income _____ TK/month)

- (5) Main income source:
- Government
 - Private company
 - Independent business
 - Other: Specify _____

3.2 Expenditure (monthly average)

(1) Total Expenditure: _____ TK/month(100%)

1) Expense of housing: _____ (_____ %)

2) Expenses of food: _____ (_____ %)

3) Expenses of fuel and lighting: _____ (_____ %)

4) Education: _____ (_____ %)

5) Transportation/communication: _____ (_____ %)

6) Water bill expense: _____ (_____ %)

7) Sewerage bill expense: _____ (_____ %)

8) Others: _____ (_____ %)

4. Water Supply Condition

4.1 Source of Drinking Water

(1) Do you obtain the water from CWASA?:

Yes, a) By house connection;

How many people use the house connection?

_____ persons

b) By hydrant;

Could you guest how many people use the hydrant?

_____ persons

No,

1) If no, what is your water source for drinking?

Private shallow well

Other: Please specify _____

2) If no, what is your water source for cloth washing?

- Private shallow well
 Stream water/pond water
 Other: Please specify _____

4.2 Metering

(1) Do you have a water meter at your resident? Yes, or No
If yes, is it functioning? Good, or Not correct

(2) When did it install? Before 1980
 1981~ 1990
 1991~ 1995
 1996 ~

4.3 Awareness / Willingness / Affordability

(1) Do you encounter water supply interruption? Yes, or No

If yes, how many hours a day could you get tap water?
_____ hours a day at; day-time, or evening/night time

(2) What is/are the most important improvement of water supply conditions for you, if you may request CWASA? (more than one answer is available)

- Continuous supply(no interruption when you want)
 Enough water pressure for your floor
 Safe for drinking
 Good quality water supply (What did you expected iron content or offensive smell/taste?)
 Cheap water charge
 Other : specify _____

(3) Upon improvement of water supply conditions, do you have willing to pay water charge which may be required for CWASA's investment program, as you consume based on the water meter reading?

- No, present water charge is maximum to pay. How much is it now? _____ TK
 Up to 1.5 times of present (up to _____ TK/month)
 Up to 2.0 times (up to _____ TK/month)
 Up to 2.5 times (up to _____ TK/month)
 Up to 3.0 times (up to _____ TK/month)
 More than 3.0times (more than _____ TK/month)

5. Sanitary Condition

5.1 Toilet Facility

(1) Type of toilet

- Flushing by tap water
- Pour flush
- Pit latrine
- No toilet

5.2 Disposal

(1) Disposal of wastewater from toilet

- Discharge to sewer line
- Discharge to septic tank
- Discharge to drainage line
- Discharge to road/pond

(2) Disposal of wastewater from kitchen and bath room

- Discharge to sewer line
- Discharge to septic tank
- Discharge to drainage line
- Discharge to road/pond

(3) Do you have experience of overflowing or flooding from sewer pipeline or drainage facility nearby your house ?

- Yes, or No

If yes, how often and how long does it happen?

_____ time/s a year, and _____ days for every flooding

6. Water Related Hygiene Conditions

(1) Does your family member have experience of sickness(e.g. diarrhea, dysentery, skin disease) by the usage of tap water?

- Yes, or No

(2) Do you know occurrence of health hazard being caused by unsanitary water source (e.g. shallow well nearby septic tank) or by polluted city water?

- Yes, or No

Thank you.

CHAPTER 7

BASIC PLAN FOR DEVELOPMENT OF WATER SUPPLY SYSTEM

7.4-1 COMPARISON STUDY FOR LOCATION OF DISTRIBUTION RESERVOIR

The study was carried out on the following 7 alternatives taking account of location of land to construct the reservoir and distribution method¹ (refer to attached figures).

- Case I-a: Construction of a new reservoir at Khulshi Hill.
- Case I-b: Construction of a new reservoir at Nasirabad Hill (back of the Tea Board Factory).
- Case I-c: Construction of a new reservoir at the CWASA Nasirabad storage yard.

- Case II-a: Construction of a new reservoir beside of existing Battali Hill reservoir.
- Case II-b: Demolition of existing Battali Hill reservoir and reconstruction of a new reservoir with appropriate big capacity.

- Case III-a: Construction of new reservoir at new Mohara plant.
- Case III-b: Construction of new reservoir at new Mohara plant with a new reservoir and a booster pump station at CWASA Nasirabad storage site.

Case I-b above was further divided into the following 3 alternatives.

- Case I-b-1: Construction of a new ground reservoir at Nasirabad Hill with a head tank, and transmission to new Battali Hill reservoir through a branched pipeline.
- Case I-b-2: Construction of a new elevated reservoir at Nasirabad Hill. Other is the same to Case I-b-1
- Case I-b-3: Construction of new ground reservoir with a head tank at Nasirabad Hill

Case I-c above was also further divided into the following 2 alternatives.

- Case I-c-1: Construction of new ground reservoir at CWASA Nasirabad storage yard with a head tank, and branched water is boosted to new Battali Hill head tank.
- Case I-c-2: Construction of a new elevated reservoir at CWASA Nasirabad storage yard, and transmission to new Battali Hill reservoir through a branched pipeline.

Case III-a above was also further divided into the following 3 alternatives.


- Case III-a-1: Direct distribution from a new reservoir at the Mohara plant without any head tank and reservoir outside of the plant.
- Case III-a-2: Direct distribution from a new reservoir at the Mohara plant and through new Battali Hill head tank.
- Case III-a-3: Direct distribution from a new reservoir at the Mohara plant through new Battali Hill head tank.

Note: Construction of a new reservoir at the Mohara WTP is possible in the premises of the plant without further land acquisition, though slight land acquisition for treatment facilities is needed.


¹ Capacity of facilities, i.e. pumps, pipes and reservoirs were decided as minimum requirements for examined system. Actual facilities shall be designed including surplus capacity for ease of operation.

Distribution System by Location of Reservoir 1/4


Alternative I-a (Khulshi Reservoir)



Alternative I-b-1 (Nasirabad + New Battali Hill Reservoirs)




Alternative I-b-2 (Nasirabad Elevated + New Battali Hill Reservoirs)




LEGEND :

- MWTP : Mohara Water Treatment Plant (Expansion)
- KRG / KRE : Khulshi Reservoir (Ground / Elevated Tank)
- NRG / NRE : Nasirabad Reservoir (Ground / Elevated Tank)
- E-BR / N-BR : Existing / New Battali Hill Reservoir
- P : Lift Pump


Alternative I-b-3 (Nasirabad Reservoir)



Alternative I-c-1 (CWASA Nasirabad Reservoir + Battali Hill Head Tank)




Alternative I-c-2 (CWASA Nasirabad Elevated + New Battali Hill Reservoirs)




LEGEND :

- MWTP : Mohara Water Treatment Plant (Expansion)
- KRG / KRE : Khulshi Reservoir (Ground / Elevated Tank)
- NRG / NRE : Nasirabad Reservoir (Ground / Elevated Tank)
- E-BR / N-BR : Existing / New Battali Hill Reservoir
- P : Lift Pump


Alternative II-a (Existing + New Battali Hill Reservoirs)



Alternative II-b (New Battali Hill Reservoir)




Alternative III-a-1 (Mohara WTP Direct Distribution)




LEGEND :

- MWTP : Mohara Water Treatment Plant (Expansion)
- KRG / KRE : Khulshi Reservoir (Ground / Elevated Tank)
- NRG / NRE : Nasirabad Reservoir (Ground / Elevated Tank)
- E-BR / N-BR : Existing / New Battali Hill Reservoir
- P : Lift Pump


Alternative III-a-2 (Mohara WTP Direct Distribution + Battali Hill Head Tank)



Alternative III-a-3 (New Battali Hill Head Tank)



Alternative III-b (Mohara WTP Direct Distribution + Nasirabad BPS + Battali Hill Head Tank)



LEGEND :

- MWTP : Mohara Water Treatment Plant (Expansion)
- KRG / KRE : Khulshi Reservoir (Ground / Elevated Tank)
- NRG / NRE : Nasirabad Reservoir (Ground / Elevated Tank)
- E-BR / N-BR : Existing / New Battali Hill Reservoir
- P : Lift Pump


Evaluation Results on Alternatives

| | 1. Stability | 2. Ease of System Control | 3. Ease of Maintenance | 4. Construction cost | 5. O & M Cost | 6. Total Cost NPV | 7. Availability of land | 8. Workability and Compensation | 9. Necessity of Existing Battal Hill Rsvr Demolition | Total |
|-----------------------------|--------------|---------------------------|------------------------|----------------------|---------------|-------------------|-------------------------|---------------------------------|--|----------|
| Weight | 7 | 5 | 3 | 1 | 1 | 7 | 5 | 3 | 7 | |
| Evaluation Result: | | | | | | | | | | |
| I-a | B | A | C | B | D | B | C | A | A | 3A3B2C1D |
| I-b-1 | B | A | C | C | C | C | C | C | D | 1A1B6C1D |
| I-b-2 | A | A | B | B | B | B | C | C | D | 2A4B2C1D |
| I-b-3 | B | A | C | B | D | C | C | A | A | 3A2B3C1D |
| I-c-1 | C | A | C | D | C | D | A | C | B | 2A1B4C2D |
| I-c-2 | A | A | B | B | B | B | A | C | D | 3A4B1C1D |
| II-b | A | A | B | B | B | B | A | C | D | 3A4B1C1D |
| III-a-1 | D | D | A | A | A | A | A | A | A | 7A0B0C2D |
| III-a-2 | D | C | A | B | A | B | A | C | B | 3A3B2C1D |
| III-a-3 | C | B | A | C | C | C | A | C | B | 2A2B5C0D |
| III-b | D | C | C | D | C | D | A | C | B | 1A1B4C3D |
| Weighted Point (Total) | | | | | | | | | | |
| I-a | 21.0 | 25.0 | 3.0 | 3.0 | -1.0 | 21.0 | 5.0 | 15.0 | 35.0 | 127.0 |
| III-a-1 | -7.0 | -5.0 | 15.0 | 5.0 | 5.0 | 35.0 | 25.0 | 15.0 | 35.0 | 123.0 |
| I-c-2 | 35.0 | 25.0 | 9.0 | 3.0 | 3.0 | 21.0 | 25.0 | 3.0 | -7.0 | 117.0 |
| II-b | 35.0 | 25.0 | 9.0 | 3.0 | 3.0 | 21.0 | 25.0 | 3.0 | -7.0 | 117.0 |
| I-b-3 | 21.0 | 25.0 | 3.0 | 3.0 | -1.0 | 7.0 | 5.0 | 15.0 | 35.0 | 113.0 |
| I-b-2 | 35.0 | 25.0 | 9.0 | 3.0 | 3.0 | 21.0 | 5.0 | 3.0 | -7.0 | 97.0 |
| III-a-3 | 7.0 | 15.0 | 15.0 | 1.0 | 1.0 | 7.0 | 25.0 | 3.0 | 21.0 | 95.0 |
| III-a-2 | -7.0 | 5.0 | 15.0 | 3.0 | 5.0 | 21.0 | 25.0 | 3.0 | 21.0 | 91.0 |
| I-c-1 | 7.0 | 25.0 | 3.0 | -1.0 | 1.0 | -7.0 | 25.0 | 3.0 | 21.0 | 77.0 |
| I-b-1 | 21.0 | 25.0 | 3.0 | 1.0 | 1.0 | 7.0 | 5.0 | 3.0 | -7.0 | 59.0 |
| III-b | -7.0 | 5.0 | 3.0 | -1.0 | 1.0 | -7.0 | 25.0 | 3.0 | 21.0 | 43.0 |
| Weighted Point (Technical) | | | | | | | | | | |
| I-b-2 | 35.0 | 25.0 | 9.0 | | | | | 3.0 | | 72.0 |
| I-c-2 | 35.0 | 25.0 | 9.0 | | | | | 3.0 | | 72.0 |
| II-b | 35.0 | 25.0 | 9.0 | | | | | 3.0 | | 72.0 |
| I-a | 21.0 | 25.0 | 3.0 | | | | | 15.0 | | 64.0 |
| I-b-3 | 21.0 | 25.0 | 3.0 | | | | | 15.0 | | 64.0 |
| I-b-1 | 21.0 | 25.0 | 3.0 | | | | | 3.0 | | 52.0 |
| III-a-3 | 7.0 | 15.0 | 15.0 | | | | | 3.0 | | 40.0 |
| I-c-1 | 7.0 | 25.0 | 3.0 | | | | | 3.0 | | 38.0 |
| III-a-1 | -7.0 | -5.0 | 15.0 | | | | | 15.0 | | 18.0 |
| III-a-2 | -7.0 | 5.0 | 15.0 | | | | | 3.0 | | 16.0 |
| III-b | -7.0 | 5.0 | 3.0 | | | | | 3.0 | | 4.0 |
| Weighted Point (Economical) | | | | | | | | | | |
| III-a-1 | | | | 5.0 | 5.0 | 35.0 | | | | 45.0 |
| III-a-2 | | | | 3.0 | 5.0 | 21.0 | | | | 29.0 |
| I-b-2 | | | | 3.0 | 3.0 | 21.0 | | | | 27.0 |
| I-c-2 | | | | 3.0 | 3.0 | 21.0 | | | | 27.0 |
| II-b | | | | 3.0 | 3.0 | 21.0 | | | | 27.0 |
| I-a | | | | 3.0 | -1.0 | 21.0 | | | | 23.0 |
| I-b-1 | | | | 1.0 | 1.0 | 7.0 | | | | 9.0 |
| I-b-3 | | | | 3.0 | -1.0 | 7.0 | | | | 9.0 |
| III-a-3 | | | | 1.0 | 1.0 | 7.0 | | | | 9.0 |
| I-c-1 | | | | -1.0 | 1.0 | -7.0 | | | | -7.0 |
| III-b | | | | -1.0 | 1.0 | -7.0 | | | | -7.0 |
| Weighted Point (Practical) | | | | | | | | | | |
| III-a-1 | | | | | | | 25.0 | 15.0 | 35.0 | 75.0 |
| I-a | | | | | | | 5.0 | 15.0 | 35.0 | 55.0 |
| I-b-3 | | | | | | | 5.0 | 15.0 | 35.0 | 55.0 |
| I-c-1 | | | | | | | 25.0 | 3.0 | 21.0 | 49.0 |
| III-a-2 | | | | | | | 25.0 | 3.0 | 21.0 | 49.0 |
| III-a-3 | | | | | | | 25.0 | 3.0 | 21.0 | 49.0 |
| III-b | | | | | | | 25.0 | 3.0 | 21.0 | 49.0 |
| I-c-2 | | | | | | | 25.0 | 3.0 | -7.0 | 21.0 |
| II-b | | | | | | | 25.0 | 3.0 | -7.0 | 21.0 |
| I-b-1 | | | | | | | 5.0 | 3.0 | -7.0 | 1.0 |
| I-b-2 | | | | | | | 5.0 | 3.0 | -7.0 | 1.0 |

| | |
|------------------|----|
| Evaluation point | |
| A: | 5 |
| B: | 3 |
| C: | 1 |
| D: | -1 |

| | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 |
|----------------------------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| | I-a | I-b-1 | I-b-2 | I-b-3 | I-c-1 | I-c-2 | II-b | III-a-1 | III-a-2 | III-a-3 | III-b |
| 1. Construction Cost | 1,424 | 1,603 | 1,423 | 1,501 | 1,770 | 1,469 | 1,465 | 1,302 | 1,498 | 1,543 | 1,733 |
| Ratio to Case I-a (=1.00) | 1.00 | 1.13 | 1.00 | 1.05 | 1.24 | 1.03 | 1.03 | 0.91 | 1.05 | 1.08 | 1.22 |
| Ratio to Least Case (=1.00) | 1.09 | 1.23 | 1.09 | 1.15 | 1.36 | 1.13 | 1.13 | 1.00 | 1.15 | 1.18 | 1.33 |
| | B | C | B | B | D | B | B | A | B | C | D |
| 2. Annual O & M Cost | 46.1 | 41.8 | 37.7 | 47.1 | 43.3 | 37.7 | 38.8 | 35.3 | 36.8 | 42.8 | 42.4 |
| Ratio to Case I-a (=1.00) | 1.00 | 0.91 | 0.82 | 1.02 | 0.94 | 0.82 | 0.84 | 0.77 | 0.80 | 0.93 | 0.92 |
| Ratio to Least Case (=1.00) | 1.31 | 1.18 | 1.07 | 1.33 | 1.23 | 1.07 | 1.10 | 1.00 | 1.04 | 1.21 | 1.20 |
| | D | C | B | D | C | B | B | A | A | C | C |
| 3. Net Present Value at 7.5% | 1,692 | 1,796 | 1,596 | 1,771 | 1,965 | 1,635 | 1,640 | 1,477 | 1,656 | 1,754 | 1,920 |
| Ratio to Case I-a (=1.00) | 1.00 | 1.06 | 0.94 | 1.05 | 1.16 | 0.97 | 0.97 | 0.87 | 0.98 | 1.04 | 1.13 |
| Ratio to Least Case (=1.00) | 1.15 | 1.22 | 1.08 | 1.20 | 1.33 | 1.11 | 1.11 | 1.00 | 1.12 | 1.19 | 1.30 |
| 7.5% | B | C | B | C | D | B | B | A | B | C | D |
| Order | 6 | 9 | 2 | 8 | 11 | 3 | 4 | 1 | 5 | 7 | 10 |

7.4-1-7



NPV of Costs for Alternative I-a

| | | | | |
|---|---------------|-------------|---------------|-----------------|
| Direct Cost | | | | |
| 1. Mohara WTP | | | | |
| | Civil Works-1 | 65,437,000 | Plant | Civil Total |
| | Civil Works-2 | 284,713,837 | Trans. Pipe. | 350,150,837 |
| | M&E Works | 207,171,000 | | |
| 2. Khulshi Hill Reservoir | | | | |
| | Civil Works | 169,592,000 | Land Aq. Area | Unit Land Price |
| | M&E Works | 92,742,000 | 17,000 | 8,500 |
| | | | m2 | Tk/m2 |
| 3. Distribution Pipes | | | | |
| | Civil Works | 203,862,290 | | |
| | M&E Works | 0 | | |
| TOTAL 1,423,897,659 (including 25% OH & Profit) | | | | |
| | Civil Works | 904,506,409 | Land Cost | 144,500,000 |
| | M&E Works | 374,891,250 | | |

(unit: TAKA)

| Year | CURRENT COST | | | | Total | NET PRESENT VALUE |
|------|---------------|-------------|-------------|-------------|-------------|-------------------|
| | Initial Costs | | | O & M Costs | | |
| | Land | Civil Works | M&E Works | | | |
| 1 | 144,500,000 | 301,502,136 | | | 446,002,136 | 1,692,365,388 |
| 2 | | 301,502,136 | 74,978,250 | | 376,480,386 | 7.5% |
| 3 | | 301,502,136 | 299,913,000 | | 601,415,136 | |
| 4 | | | | 46,129,793 | 46,129,793 | |
| 5 | | | | 46,129,793 | 46,129,793 | |
| 6 | | | | 46,129,793 | 46,129,793 | |
| 7 | | | | 46,129,793 | 46,129,793 | |
| 8 | | | | 46,129,793 | 46,129,793 | |
| 9 | | | | 46,129,793 | 46,129,793 | |
| 10 | | | | 46,129,793 | 46,129,793 | |
| 11 | | | | 46,129,793 | 46,129,793 | |
| 12 | | | | 46,129,793 | 46,129,793 | |
| 13 | | | | 46,129,793 | 46,129,793 | |
| 14 | | | | 46,129,793 | 46,129,793 | |
| 15 | | | | 46,129,793 | 46,129,793 | |
| 16 | | | | 46,129,793 | 46,129,793 | |
| 17 | | | | 46,129,793 | 46,129,793 | |
| 18 | | | 149,956,500 | 46,129,793 | 196,086,293 | |
| 19 | | | | 46,129,793 | 46,129,793 | |
| 20 | | | | 46,129,793 | 46,129,793 | |
| 21 | | | | 46,129,793 | 46,129,793 | |
| 22 | | | | 46,129,793 | 46,129,793 | |
| 23 | | | | 46,129,793 | 46,129,793 | |
| 24 | | | | 46,129,793 | 46,129,793 | |
| 25 | | | | 46,129,793 | 46,129,793 | |
| 26 | | | | 46,129,793 | 46,129,793 | |
| 27 | | | | 46,129,793 | 46,129,793 | |
| 28 | | | | 46,129,793 | 46,129,793 | |
| 29 | | | | 46,129,793 | 46,129,793 | |
| 30 | | | | 46,129,793 | 46,129,793 | |
| 31 | | | | 46,129,793 | 46,129,793 | |
| 32 | | | | 46,129,793 | 46,129,793 | |
| 33 | | -90,450,641 | -37,489,125 | 46,129,793 | -81,809,973 | |

7.4-1-8

NPV of Costs for Alternative I-b-1

| | | | | |
|---|---------------|---------------|---------------|-----------------|
| Direct Cost | | | | |
| 1. Mohara WTP | | | | |
| | Civil Works-1 | 65,437,000 | Plant | Civil Total |
| | Civil Works-2 | 378,488,975 | Trans. Pipe. | 443,925,975 |
| | M&E Works | 205,974,000 | | |
| 2. Nasirabad Reservoir | | | | |
| | Civil Works | 95,336,000 | Land Aq. Area | Unit Land Price |
| | M&E Works | 78,161,000 | 7,000 | 5,600 |
| | | | m2 | Tk/m2 |
| 3. New Battali Hill Reservoir | | | | |
| | Civil Works | 122,529,000 | | |
| | M&E Works | 0 | | |
| 4. Old Battali Hill Reservoir Rebuilt | | | | |
| | Civil Works | 114,434,000 | | |
| | M&E Works | 0 | | |
| 5. Distribution Pipes | | | | |
| | Civil Works | 190,445,479 | | |
| | M&E Works | 0 | | |
| TOTAL 1,602,706,818 (including 25% OH & Profit) | | | | |
| | Civil Works | 1,208,338,068 | Land Cost | 39,200,000 |
| | M&E Works | 355,168,750 | | |

(unit: TAKA)

| Year | CURRENT COST | | | | Total | NET PRESENT VALUE |
|------|---------------|--------------|-------------|-------------|--------------|-------------------|
| | Initial Costs | | | O & M Costs | | |
| | Land | Civil Works | M&E Works | | | |
| 1 | 39,200,000 | 402,779,356 | | | 441,979,356 | 1,795,730,203 |
| 2 | | 402,779,356 | 71,033,750 | | 473,813,106 | 7.5% |
| 3 | | 402,779,356 | 284,135,000 | | 686,914,356 | |
| 4 | | | | 41,797,848 | 41,797,848 | |
| 5 | | | | 41,797,848 | 41,797,848 | |
| 6 | | | | 41,797,848 | 41,797,848 | |
| 7 | | | | 41,797,848 | 41,797,848 | |
| 8 | | | | 41,797,848 | 41,797,848 | |
| 9 | | | | 41,797,848 | 41,797,848 | |
| 10 | | | | 41,797,848 | 41,797,848 | |
| 11 | | | | 41,797,848 | 41,797,848 | |
| 12 | | | | 41,797,848 | 41,797,848 | |
| 13 | | | | 41,797,848 | 41,797,848 | |
| 14 | | | | 41,797,848 | 41,797,848 | |
| 15 | | | | 41,797,848 | 41,797,848 | |
| 16 | | | | 41,797,848 | 41,797,848 | |
| 17 | | | | 41,797,848 | 41,797,848 | |
| 18 | | | 142,067,500 | 41,797,848 | 183,865,348 | |
| 19 | | | | 41,797,848 | 41,797,848 | |
| 20 | | | | 41,797,848 | 41,797,848 | |
| 21 | | | | 41,797,848 | 41,797,848 | |
| 22 | | | | 41,797,848 | 41,797,848 | |
| 23 | | | | 41,797,848 | 41,797,848 | |
| 24 | | | | 41,797,848 | 41,797,848 | |
| 25 | | | | 41,797,848 | 41,797,848 | |
| 26 | | | | 41,797,848 | 41,797,848 | |
| 27 | | | | 41,797,848 | 41,797,848 | |
| 28 | | | | 41,797,848 | 41,797,848 | |
| 29 | | | | 41,797,848 | 41,797,848 | |
| 30 | | | | 41,797,848 | 41,797,848 | |
| 31 | | | | 41,797,848 | 41,797,848 | |
| 32 | | | | 41,797,848 | 41,797,848 | |
| 33 | | -120,833,807 | -35,516,875 | 41,797,848 | -114,552,834 | |

NPV of Costs for Alternative I-b-2

| Direct Cost | | | | |
|---|---------------|---------------|-----------------|-------------|
| 1. Mohara WTP | | | | |
| Civil Works-1 | 65,437,000 | Plant | | Civil Total |
| Civil Works-2 | 377,828,630 | Trans. Pipe. | | 443,265,630 |
| M&E Works | 205,974,000 | | | |
| 2. Nasirabad Reservoir | | | | |
| | | Land Aq. Area | Unit Land Price | |
| Civil Works | 48,707,000 | 3,000 | 5,600 | |
| M&E Works | 0 | m2 | Tk/m2 | |
| 3. New Battali Hill Reservoir | | | | |
| Civil Works | 122,529,000 | | | |
| M&E Works | 0 | | | |
| 4. Old Battali Hill Reservoir Rebuilt | | | | |
| Civil Works | 114,434,000 | | | |
| M&E Works | 0 | | | |
| 5. Distribution Pipes | | | | |
| Civil Works | 190,445,479 | | | |
| M&E Works | 0 | | | |
| TOTAL 1,423,493,886 (including 25% OH & Profit) | | | | |
| Civil Works | 1,149,226,386 | Land Cost | | 16,800,000 |
| M&E Works | 257,467,500 | | | |

(unit: TAKA)

| Year | CURRENT COST | | | | Total | NET PRESENT VALUE |
|------|---------------|--------------|-------------|-------------|--------------|-------------------|
| | Initial Costs | | | O & M Costs | | |
| | Land | Civil Works | M&E Works | | | |
| 1 | 16,800,000 | 383,075,462 | | | 399,875,462 | 1,595,867,518 |
| 2 | | 383,075,462 | 51,493,500 | | 434,568,962 | 7.5% |
| 3 | | 383,075,462 | 205,974,000 | | 589,049,462 | |
| 4 | | | | 37,719,795 | 37,719,795 | |
| 5 | | | | 37,719,795 | 37,719,795 | |
| 6 | | | | 37,719,795 | 37,719,795 | |
| 7 | | | | 37,719,795 | 37,719,795 | |
| 8 | | | | 37,719,795 | 37,719,795 | |
| 9 | | | | 37,719,795 | 37,719,795 | |
| 10 | | | | 37,719,795 | 37,719,795 | |
| 11 | | | | 37,719,795 | 37,719,795 | |
| 12 | | | | 37,719,795 | 37,719,795 | |
| 13 | | | | 37,719,795 | 37,719,795 | |
| 14 | | | | 37,719,795 | 37,719,795 | |
| 15 | | | | 37,719,795 | 37,719,795 | |
| 16 | | | | 37,719,795 | 37,719,795 | |
| 17 | | | | 37,719,795 | 37,719,795 | |
| 18 | | | 102,987,000 | 37,719,795 | 140,706,795 | |
| 19 | | | | 37,719,795 | 37,719,795 | |
| 20 | | | | 37,719,795 | 37,719,795 | |
| 21 | | | | 37,719,795 | 37,719,795 | |
| 22 | | | | 37,719,795 | 37,719,795 | |
| 23 | | | | 37,719,795 | 37,719,795 | |
| 24 | | | | 37,719,795 | 37,719,795 | |
| 25 | | | | 37,719,795 | 37,719,795 | |
| 26 | | | | 37,719,795 | 37,719,795 | |
| 27 | | | | 37,719,795 | 37,719,795 | |
| 28 | | | | 37,719,795 | 37,719,795 | |
| 29 | | | | 37,719,795 | 37,719,795 | |
| 30 | | | | 37,719,795 | 37,719,795 | |
| 31 | | | | 37,719,795 | 37,719,795 | |
| 32 | | | | 37,719,795 | 37,719,795 | |
| 33 | | -114,922,639 | -25,746,750 | 37,719,795 | -102,949,594 | |

7.4-1-9

NPV of Costs for Alternative I-b-3

| Direct Cost | | | | |
|---|-------------|---------------|-----------------|-------------|
| 1. Mohara WTP | | | | |
| Civil Works-1 | 65,437,000 | Plant | | Civil Total |
| Civil Works-2 | 206,273,235 | Trans. Pipe. | | 271,710,235 |
| M&E Works | 183,837,000 | | | |
| 2. Nasirabad Reservoir | | | | |
| | | Land Aq. Area | Unit Land Price | |
| Civil Works | 205,105,000 | 20,000 | 5,600 | |
| M&E Works | 192,969,000 | m2 | Tk/m2 | |
| 3. Distribution Pipes | | | | |
| Civil Works | 257,525,436 | | | |
| M&E Works | 0 | | | |
| TOTAL 1,500,933,339 (including 25% OH & Profit) | | | | |
| Civil Works | 917,925,839 | Land Cost | | 112,000,000 |
| M&E Works | 471,007,500 | | | |

(unit: TAKA)

| Year | CURRENT COST | | | | Total | NET PRESENT VALUE |
|------|---------------|-------------|-------------|-------------|-------------|-------------------|
| | Initial Costs | | | O & M Costs | | |
| | Land | Civil Works | M&E Works | | | |
| 1 | 112,000,000 | 305,975,280 | | | 417,975,280 | 1,770,885,595 |
| 2 | | 305,975,280 | 94,201,500 | | 400,176,780 | 7.5% |
| 3 | | 305,975,280 | 376,806,000 | | 682,781,280 | |
| 4 | | | | 47,090,955 | 47,090,955 | |
| 5 | | | | 47,090,955 | 47,090,955 | |
| 6 | | | | 47,090,955 | 47,090,955 | |
| 7 | | | | 47,090,955 | 47,090,955 | |
| 8 | | | | 47,090,955 | 47,090,955 | |
| 9 | | | | 47,090,955 | 47,090,955 | |
| 10 | | | | 47,090,955 | 47,090,955 | |
| 11 | | | | 47,090,955 | 47,090,955 | |
| 12 | | | | 47,090,955 | 47,090,955 | |
| 13 | | | | 47,090,955 | 47,090,955 | |
| 14 | | | | 47,090,955 | 47,090,955 | |
| 15 | | | | 47,090,955 | 47,090,955 | |
| 16 | | | | 47,090,955 | 47,090,955 | |
| 17 | | | | 47,090,955 | 47,090,955 | |
| 18 | | | 188,403,000 | 47,090,955 | 235,493,955 | |
| 19 | | | | 47,090,955 | 47,090,955 | |
| 20 | | | | 47,090,955 | 47,090,955 | |
| 21 | | | | 47,090,955 | 47,090,955 | |
| 22 | | | | 47,090,955 | 47,090,955 | |
| 23 | | | | 47,090,955 | 47,090,955 | |
| 24 | | | | 47,090,955 | 47,090,955 | |
| 25 | | | | 47,090,955 | 47,090,955 | |
| 26 | | | | 47,090,955 | 47,090,955 | |
| 27 | | | | 47,090,955 | 47,090,955 | |
| 28 | | | | 47,090,955 | 47,090,955 | |
| 29 | | | | 47,090,955 | 47,090,955 | |
| 30 | | | | 47,090,955 | 47,090,955 | |
| 31 | | | | 47,090,955 | 47,090,955 | |
| 32 | | | | 47,090,955 | 47,090,955 | |
| 33 | | -91,792,584 | -47,100,750 | 47,090,955 | -91,802,379 | |

NPV of Costs for Alternative I-c-1

| | | | | |
|---|---------------|---------------|---------------|-----------------|
| Direct Cost | | | | |
| 1. Mohara WTP | | | | |
| | Civil Works-1 | 65,437,000 | Plant | Civil Total |
| | Civil Works-2 | 410,024,801 | Trans. Pipe. | 475,461,801 |
| | M&E Works | 155,910,000 | | |
| 2. Nasirabad Reservoir | | | | |
| | | | Land Aq. Area | Unit Land Price |
| | Civil Works | 202,176,000 | 13,000 | 5,600 |
| | M&E Works | 246,977,000 | m2 | Tk/m2 |
| 3. New Battali Hill Reservoir | | | | |
| | Civil Works | 77,661,000 | | |
| | M&E Works | 0 | | |
| 4. Distribution Pipes | | | | |
| | Civil Works | 199,664,932 | | |
| | M&E Works | 0 | | |
| TOTAL 1,770,113,416 (including 25% OH & Profit) | | | | |
| | Civil Works | 1,193,704,666 | Land Cost | 72,800,000 |
| | M&E Works | 503,608,750 | | |

(unit: TAKA)

| Year | CURRENT COST | | | | Total | NET PRESENT VALUE |
|------|---------------|--------------|-------------|-------------|--------------|-------------------|
| | Initial Costs | | | O & M Costs | | |
| | Land | Civil Works | M&E Works | | | |
| 1 | 72,800,000 | 397,901,555 | | | 470,701,555 | 1,964,616,815 |
| 2 | | 397,901,555 | 100,721,750 | | 498,623,305 | 7.5% |
| 3 | | 397,901,555 | 402,887,000 | | 800,788,555 | |
| 4 | | | | 43,282,248 | 43,282,248 | |
| 5 | | | | 43,282,248 | 43,282,248 | |
| 6 | | | | 43,282,248 | 43,282,248 | |
| 7 | | | | 43,282,248 | 43,282,248 | |
| 8 | | | | 43,282,248 | 43,282,248 | |
| 9 | | | | 43,282,248 | 43,282,248 | |
| 10 | | | | 43,282,248 | 43,282,248 | |
| 11 | | | | 43,282,248 | 43,282,248 | |
| 12 | | | | 43,282,248 | 43,282,248 | |
| 13 | | | | 43,282,248 | 43,282,248 | |
| 14 | | | | 43,282,248 | 43,282,248 | |
| 15 | | | | 43,282,248 | 43,282,248 | |
| 16 | | | | 43,282,248 | 43,282,248 | |
| 17 | | | | 43,282,248 | 43,282,248 | |
| 18 | | | 201,443,500 | 43,282,248 | 244,725,748 | |
| 19 | | | | 43,282,248 | 43,282,248 | |
| 20 | | | | 43,282,248 | 43,282,248 | |
| 21 | | | | 43,282,248 | 43,282,248 | |
| 22 | | | | 43,282,248 | 43,282,248 | |
| 23 | | | | 43,282,248 | 43,282,248 | |
| 24 | | | | 43,282,248 | 43,282,248 | |
| 25 | | | | 43,282,248 | 43,282,248 | |
| 26 | | | | 43,282,248 | 43,282,248 | |
| 27 | | | | 43,282,248 | 43,282,248 | |
| 28 | | | | 43,282,248 | 43,282,248 | |
| 29 | | | | 43,282,248 | 43,282,248 | |
| 30 | | | | 43,282,248 | 43,282,248 | |
| 31 | | | | 43,282,248 | 43,282,248 | |
| 32 | | | | 43,282,248 | 43,282,248 | |
| 33 | | -119,370,467 | -50,360,875 | 43,282,248 | -126,449,094 | |

7.4-1-10

NPV of Costs for Alternative I-c-2

| | | | | |
|---|---------------|---------------|---------------|-----------------|
| Direct Cost | | | | |
| 1. Mohara WTP | | | | |
| | Civil Works-1 | 65,437,000 | Plant | Civil Total |
| | Civil Works-2 | 393,282,393 | Trans. Pipe. | 458,719,393 |
| | M&E Works | 205,974,000 | | |
| 2. Nasirabad Reservoir | | | | |
| | | | Land Aq. Area | Unit Land Price |
| | Civil Works | 53,738,000 | 3,000 | 5,600 |
| | M&E Works | 0 | m2 | Tk/m2 |
| 3. New Battali Hill Reservoir | | | | |
| | Civil Works | 122,529,000 | | |
| | M&E Works | 0 | | |
| 4. Old Battali Hill Reservoir Rebuilt | | | | |
| | Civil Works | 122,816,000 | | |
| | M&E Works | 0 | | |
| 5. Distribution Pipes | | | | |
| | Civil Works | 198,208,092 | | |
| | M&E Works | 0 | | |
| TOTAL 1,469,280,606 (including 25% OH & Profit) | | | | |
| | Civil Works | 1,195,013,106 | Land Cost | 16,800,000 |
| | M&E Works | 257,467,500 | | |

(unit: TAKA)

| Year | CURRENT COST | | | | Total | NET PRESENT VALUE |
|------|---------------|--------------|-------------|-------------|--------------|-------------------|
| | Initial Costs | | | O & M Costs | | |
| | Land | Civil Works | M&E Works | | | |
| 1 | 16,800,000 | 398,337,702 | | | 415,137,702 | 1,635,136,387 |
| 2 | | 398,337,702 | 51,493,500 | | 449,831,202 | 7.5% |
| 3 | | 398,337,702 | 205,974,000 | | 604,311,702 | |
| 4 | | | | 37,719,795 | 37,719,795 | |
| 5 | | | | 37,719,795 | 37,719,795 | |
| 6 | | | | 37,719,795 | 37,719,795 | |
| 7 | | | | 37,719,795 | 37,719,795 | |
| 8 | | | | 37,719,795 | 37,719,795 | |
| 9 | | | | 37,719,795 | 37,719,795 | |
| 10 | | | | 37,719,795 | 37,719,795 | |
| 11 | | | | 37,719,795 | 37,719,795 | |
| 12 | | | | 37,719,795 | 37,719,795 | |
| 13 | | | | 37,719,795 | 37,719,795 | |
| 14 | | | | 37,719,795 | 37,719,795 | |
| 15 | | | | 37,719,795 | 37,719,795 | |
| 16 | | | | 37,719,795 | 37,719,795 | |
| 17 | | | | 37,719,795 | 37,719,795 | |
| 18 | | | 102,987,000 | 37,719,795 | 140,706,795 | |
| 19 | | | | 37,719,795 | 37,719,795 | |
| 20 | | | | 37,719,795 | 37,719,795 | |
| 21 | | | | 37,719,795 | 37,719,795 | |
| 22 | | | | 37,719,795 | 37,719,795 | |
| 23 | | | | 37,719,795 | 37,719,795 | |
| 24 | | | | 37,719,795 | 37,719,795 | |
| 25 | | | | 37,719,795 | 37,719,795 | |
| 26 | | | | 37,719,795 | 37,719,795 | |
| 27 | | | | 37,719,795 | 37,719,795 | |
| 28 | | | | 37,719,795 | 37,719,795 | |
| 29 | | | | 37,719,795 | 37,719,795 | |
| 30 | | | | 37,719,795 | 37,719,795 | |
| 31 | | | | 37,719,795 | 37,719,795 | |
| 32 | | | | 37,719,795 | 37,719,795 | |
| 33 | | -119,501,311 | -25,746,750 | 37,719,795 | -107,528,266 | |

NPV of Costs for Alternative II-b

| | | | |
|---|---------------|--------------|-------------|
| Direct Cost | | | |
| 1. Mohara WTP | | | |
| Civil Works-1 | 65,437,000 | Plant | Civil Total |
| Civil Works-2 | 396,245,787 | Trans. Pipe. | 461,682,787 |
| M&E Works | 206,278,000 | | |
| 2. New Battali Hill Reservoir | | | |
| Civil Works | 160,368,000 | | |
| M&E Works | 0 | | |
| 3. Old Battali Hill Reservoir Rebuilt | | | |
| Civil Works | 122,816,000 | | |
| M&E Works | 0 | | |
| 4. Distribution Pipes | | | |
| Civil Works | 221,162,179 | | |
| M&E Works | 0 | | |
| TOTAL 1,465,383,708 (including 25% OH & Profit) | | | |
| Civil Works | 1,207,536,208 | Land Cost | 0 |
| M&E Works | 257,847,500 | | |

(unit: TAKA)

| Year | CURRENT COST | | | | NET PRESENT VALUE | |
|------|---------------|--------------|-------------|-------------|-------------------|---------------|
| | Initial Costs | | | O & M Costs | | Total |
| | Land | Civil Works | M&E Works | | | |
| 1 | 0 | 402,512,069 | | | 402,512,069 | 1,640,460,432 |
| 2 | | 402,512,069 | 51,569,500 | | 454,081,569 | 7.5% |
| 3 | | 402,512,069 | 206,278,000 | | 608,790,069 | |
| 4 | | | | 38,757,275 | 38,757,275 | |
| 5 | | | | 38,757,275 | 38,757,275 | |
| 6 | | | | 38,757,275 | 38,757,275 | |
| 7 | | | | 38,757,275 | 38,757,275 | |
| 8 | | | | 38,757,275 | 38,757,275 | |
| 9 | | | | 38,757,275 | 38,757,275 | |
| 10 | | | | 38,757,275 | 38,757,275 | |
| 11 | | | | 38,757,275 | 38,757,275 | |
| 12 | | | | 38,757,275 | 38,757,275 | |
| 13 | | | | 38,757,275 | 38,757,275 | |
| 14 | | | | 38,757,275 | 38,757,275 | |
| 15 | | | | 38,757,275 | 38,757,275 | |
| 16 | | | | 38,757,275 | 38,757,275 | |
| 17 | | | | 38,757,275 | 38,757,275 | |
| 18 | | | 103,139,000 | 38,757,275 | 141,896,275 | |
| 19 | | | | 38,757,275 | 38,757,275 | |
| 20 | | | | 38,757,275 | 38,757,275 | |
| 21 | | | | 38,757,275 | 38,757,275 | |
| 22 | | | | 38,757,275 | 38,757,275 | |
| 23 | | | | 38,757,275 | 38,757,275 | |
| 24 | | | | 38,757,275 | 38,757,275 | |
| 25 | | | | 38,757,275 | 38,757,275 | |
| 26 | | | | 38,757,275 | 38,757,275 | |
| 27 | | | | 38,757,275 | 38,757,275 | |
| 28 | | | | 38,757,275 | 38,757,275 | |
| 29 | | | | 38,757,275 | 38,757,275 | |
| 30 | | | | 38,757,275 | 38,757,275 | |
| 31 | | | | 38,757,275 | 38,757,275 | |
| 32 | | | | 38,757,275 | 38,757,275 | |
| 33 | | -120,753,621 | -25,784,750 | 38,757,275 | -107,781,096 | |

7.4-1-11

NPV of Costs for Alternative III-a-1

| | | | |
|---|-------------|--------------|-------------|
| Direct Cost | | | |
| 1. Mohara WTP | | | |
| Civil Works-1 | 112,018,000 | Plant | Civil Total |
| Civil Works-2 | 0 | Trans. Pipe. | 112,018,000 |
| M&E Works | 342,981,667 | | |
| 2. Distribution Pipes | | | |
| Civil Works | 586,503,289 | | |
| M&E Works | 0 | | |
| TOTAL 1,301,878,695 (including 25% OH & Profit) | | | |
| Civil Works | 873,151,611 | Land Cost | 0 |
| M&E Works | 428,727,084 | | |

(unit: TAKA)

| Year | CURRENT COST | | | | NET PRESENT VALUE | |
|------|---------------|-------------|-------------|-------------|-------------------|---------------|
| | Initial Costs | | | O & M Costs | | Total |
| | Land | Civil Works | M&E Works | | | |
| 1 | 0 | 291,050,537 | | | 291,050,537 | 1,477,424,744 |
| 2 | | 291,050,537 | 85,745,417 | | 376,795,954 | 7.5% |
| 3 | | 291,050,537 | 342,981,667 | | 634,032,204 | |
| 4 | | | | 35,297,671 | 35,297,671 | |
| 5 | | | | 35,297,671 | 35,297,671 | |
| 6 | | | | 35,297,671 | 35,297,671 | |
| 7 | | | | 35,297,671 | 35,297,671 | |
| 8 | | | | 35,297,671 | 35,297,671 | |
| 9 | | | | 35,297,671 | 35,297,671 | |
| 10 | | | | 35,297,671 | 35,297,671 | |
| 11 | | | | 35,297,671 | 35,297,671 | |
| 12 | | | | 35,297,671 | 35,297,671 | |
| 13 | | | | 35,297,671 | 35,297,671 | |
| 14 | | | | 35,297,671 | 35,297,671 | |
| 15 | | | | 35,297,671 | 35,297,671 | |
| 16 | | | | 35,297,671 | 35,297,671 | |
| 17 | | | | 35,297,671 | 35,297,671 | |
| 18 | | | 171,490,834 | 35,297,671 | 206,788,505 | |
| 19 | | | | 35,297,671 | 35,297,671 | |
| 20 | | | | 35,297,671 | 35,297,671 | |
| 21 | | | | 35,297,671 | 35,297,671 | |
| 22 | | | | 35,297,671 | 35,297,671 | |
| 23 | | | | 35,297,671 | 35,297,671 | |
| 24 | | | | 35,297,671 | 35,297,671 | |
| 25 | | | | 35,297,671 | 35,297,671 | |
| 26 | | | | 35,297,671 | 35,297,671 | |
| 27 | | | | 35,297,671 | 35,297,671 | |
| 28 | | | | 35,297,671 | 35,297,671 | |
| 29 | | | | 35,297,671 | 35,297,671 | |
| 30 | | | | 35,297,671 | 35,297,671 | |
| 31 | | | | 35,297,671 | 35,297,671 | |
| 32 | | | | 35,297,671 | 35,297,671 | |
| 33 | | -87,315,161 | -42,872,708 | 35,297,671 | -94,890,199 | |

NPV of Costs for Alternative III-a-2

| | | | |
|---|---------------|--------------|-------------|
| Direct Cost | | | |
| 1. Mohara WTP | | | |
| Civil Works-1 | 120,109,000 | Plant | Civil Total |
| Civil Works-2 | 27,685,182 | Trans. Pipe. | 147,794,182 |
| M&E Works | 294,444,000 | | |
| 3. New Battali Hill Reservoir | | | |
| Civil Works | 82,879,000 | | |
| M&E Works | 0 | | |
| 4. Distribution Pipes | | | |
| Civil Works | 673,558,967 | | |
| M&E Works | 0 | | |
| TOTAL 1,498,345,186 (including 25% OH & Profit) | | | |
| Civil Works | 1,130,290,186 | Land Cost | 0 |
| M&E Works | 368,055,000 | | |

(unit: TAKA)

| Year | CURRENT COST | | | | Total | NET PRESENT VALUE |
|------|--------------|--------------|-------------|-------------|--------------|-------------------|
| | Land | Civil Works | M&E Works | O & M Costs | | |
| 1 | 0 | 376,763,395 | | | 376,763,395 | 1,656,229,465 |
| 2 | | 376,763,395 | 73,611,000 | | 450,374,395 | 7.5% |
| 3 | | 376,763,395 | 294,444,000 | | 671,207,395 | |
| 4 | | | | 36,758,310 | 36,758,310 | |
| 5 | | | | 36,758,310 | 36,758,310 | |
| 6 | | | | 36,758,310 | 36,758,310 | |
| 7 | | | | 36,758,310 | 36,758,310 | |
| 8 | | | | 36,758,310 | 36,758,310 | |
| 9 | | | | 36,758,310 | 36,758,310 | |
| 10 | | | | 36,758,310 | 36,758,310 | |
| 11 | | | | 36,758,310 | 36,758,310 | |
| 12 | | | | 36,758,310 | 36,758,310 | |
| 13 | | | | 36,758,310 | 36,758,310 | |
| 14 | | | | 36,758,310 | 36,758,310 | |
| 15 | | | | 36,758,310 | 36,758,310 | |
| 16 | | | | 36,758,310 | 36,758,310 | |
| 17 | | | | 36,758,310 | 36,758,310 | |
| 18 | | | 147,222,000 | 36,758,310 | 183,980,310 | |
| 19 | | | | 36,758,310 | 36,758,310 | |
| 20 | | | | 36,758,310 | 36,758,310 | |
| 21 | | | | 36,758,310 | 36,758,310 | |
| 22 | | | | 36,758,310 | 36,758,310 | |
| 23 | | | | 36,758,310 | 36,758,310 | |
| 24 | | | | 36,758,310 | 36,758,310 | |
| 25 | | | | 36,758,310 | 36,758,310 | |
| 26 | | | | 36,758,310 | 36,758,310 | |
| 27 | | | | 36,758,310 | 36,758,310 | |
| 28 | | | | 36,758,310 | 36,758,310 | |
| 29 | | | | 36,758,310 | 36,758,310 | |
| 30 | | | | 36,758,310 | 36,758,310 | |
| 31 | | | | 36,758,310 | 36,758,310 | |
| 32 | | | | 36,758,310 | 36,758,310 | |
| 33 | | -113,029,019 | -36,805,500 | 36,758,310 | -113,076,209 | |

NPV of Costs for Alternative III-a-3

| | | | |
|---|---------------|--------------|-------------|
| Direct Cost | | | |
| 1. Mohara WTP | | | |
| Civil Works-1 | 119,760,000 | Plant | Civil Total |
| Civil Works-2 | 444,453,335 | Trans. Pipe. | 564,213,335 |
| M&E Works | 333,110,000 | | |
| 2. New Battali Hill Reservoir | | | |
| Civil Works | 104,316,000 | | |
| M&E Works | 0 | | |
| 3. Distribution Pipes | | | |
| Civil Works | 232,403,525 | | |
| M&E Works | 0 | | |
| TOTAL 1,542,553,575 (including 25% OH & Profit) | | | |
| Civil Works | 1,126,166,075 | Land Cost | 0 |
| M&E Works | 416,387,500 | | |

(unit: TAKA)

| Year | CURRENT COST | | | | Total | NET PRESENT VALUE |
|------|--------------|--------------|-------------|-------------|--------------|-------------------|
| | Land | Civil Works | M&E Works | O & M Costs | | |
| 1 | 0 | 375,388,692 | | | 375,388,692 | 1,754,002,972 |
| 2 | | 375,388,692 | 83,277,500 | | 458,666,192 | 7.5% |
| 3 | | 375,388,692 | 333,110,000 | | 708,498,692 | |
| 4 | | | | 42,754,595 | 42,754,595 | |
| 5 | | | | 42,754,595 | 42,754,595 | |
| 6 | | | | 42,754,595 | 42,754,595 | |
| 7 | | | | 42,754,595 | 42,754,595 | |
| 8 | | | | 42,754,595 | 42,754,595 | |
| 9 | | | | 42,754,595 | 42,754,595 | |
| 10 | | | | 42,754,595 | 42,754,595 | |
| 11 | | | | 42,754,595 | 42,754,595 | |
| 12 | | | | 42,754,595 | 42,754,595 | |
| 13 | | | | 42,754,595 | 42,754,595 | |
| 14 | | | | 42,754,595 | 42,754,595 | |
| 15 | | | | 42,754,595 | 42,754,595 | |
| 16 | | | | 42,754,595 | 42,754,595 | |
| 17 | | | | 42,754,595 | 42,754,595 | |
| 18 | | | 166,555,000 | 42,754,595 | 209,309,595 | |
| 19 | | | | 42,754,595 | 42,754,595 | |
| 20 | | | | 42,754,595 | 42,754,595 | |
| 21 | | | | 42,754,595 | 42,754,595 | |
| 22 | | | | 42,754,595 | 42,754,595 | |
| 23 | | | | 42,754,595 | 42,754,595 | |
| 24 | | | | 42,754,595 | 42,754,595 | |
| 25 | | | | 42,754,595 | 42,754,595 | |
| 26 | | | | 42,754,595 | 42,754,595 | |
| 27 | | | | 42,754,595 | 42,754,595 | |
| 28 | | | | 42,754,595 | 42,754,595 | |
| 29 | | | | 42,754,595 | 42,754,595 | |
| 30 | | | | 42,754,595 | 42,754,595 | |
| 31 | | | | 42,754,595 | 42,754,595 | |
| 32 | | | | 42,754,595 | 42,754,595 | |
| 33 | | -112,616,608 | -41,638,750 | 42,754,595 | -111,500,763 | |

7.4-1-12

NPV of Costs for Alternative III-b

| Direct Cost | | | | |
|---|---------------|---------------|-----------------|-------------|
| 1. Mohara WTP | | | | |
| Civil Works-1 | 65,437,000 | Plant | | Civil Total |
| Civil Works-2 | 144,078,638 | Trans. Pipe. | | 209,515,638 |
| M&E Works | 160,408,000 | | | |
| 2. Nasirabad Reservoir | | | | |
| | | Land Aq. Area | Unit Land Price | |
| Civil Works | 156,514,000 | 13,000 | 5,600 | |
| M&E Works | 175,020,000 | m2 | Tk/m2 | |
| 3. New Battali Hill Reservoir | | | | |
| Civil Works | 82,879,000 | | | |
| M&E Works | 0 | | | |
| 4. Distribution Pipes | | | | |
| Civil Works | 543,816,814 | | | |
| M&E Works | 0 | | | |
| TOTAL 1,732,991,815 (including 25% OH & Profit) | | | | |
| Civil Works | 1,240,906,815 | Land Cost | | 72,800,000 |
| M&E Works | 419,285,000 | | | |

(unit: TAKA)

| Year | CURRENT COST | | | | Total | NET PRESENT VALUE |
|------|---------------|--------------|-------------|-------------|--------------|-------------------|
| | Initial Costs | | | O & M Costs | | |
| | Land | Civil Works | M&E Works | | | |
| 1 | 72,800,000 | 413,635,605 | | | 486,435,605 | 1,919,786,809 |
| 2 | | 413,635,605 | 83,857,000 | | 497,492,605 | 7.5% |
| 3 | | 413,635,605 | 335,428,000 | | 749,063,605 | |
| 4 | | | | 42,439,010 | 42,439,010 | |
| 5 | | | | 42,439,010 | 42,439,010 | |
| 6 | | | | 42,439,010 | 42,439,010 | |
| 7 | | | | 42,439,010 | 42,439,010 | |
| 8 | | | | 42,439,010 | 42,439,010 | |
| 9 | | | | 42,439,010 | 42,439,010 | |
| 10 | | | | 42,439,010 | 42,439,010 | |
| 11 | | | | 42,439,010 | 42,439,010 | |
| 12 | | | | 42,439,010 | 42,439,010 | |
| 13 | | | | 42,439,010 | 42,439,010 | |
| 14 | | | | 42,439,010 | 42,439,010 | |
| 15 | | | | 42,439,010 | 42,439,010 | |
| 16 | | | | 42,439,010 | 42,439,010 | |
| 17 | | | | 42,439,010 | 42,439,010 | |
| 18 | | | 167,714,000 | 42,439,010 | 210,153,010 | |
| 19 | | | | 42,439,010 | 42,439,010 | |
| 20 | | | | 42,439,010 | 42,439,010 | |
| 21 | | | | 42,439,010 | 42,439,010 | |
| 22 | | | | 42,439,010 | 42,439,010 | |
| 23 | | | | 42,439,010 | 42,439,010 | |
| 24 | | | | 42,439,010 | 42,439,010 | |
| 25 | | | | 42,439,010 | 42,439,010 | |
| 26 | | | | 42,439,010 | 42,439,010 | |
| 27 | | | | 42,439,010 | 42,439,010 | |
| 28 | | | | 42,439,010 | 42,439,010 | |
| 29 | | | | 42,439,010 | 42,439,010 | |
| 30 | | | | 42,439,010 | 42,439,010 | |
| 31 | | | | 42,439,010 | 42,439,010 | |
| 32 | | | | 42,439,010 | 42,439,010 | |
| 33 | | -124,090,682 | -41,928,500 | 42,439,010 | -123,580,172 | |

7.4-1-13

Case I – a Khulushi Reservoir

Unit : Taka

| No | Name of Facility | Item | Dimension | Unit | Unit Cost | Quantity | Price | Note | E&M | Civil |
|-----|----------------------------------|---------------------------------|---------------------------------------|------|-----------|----------|---------------|----------------|-------------|-------------|
| 1 | Mohara WTP | | | | | | | | | |
| 1-1 | Clear Well | Civil Work | 6.716 m ³ | L.S. | | 1 | 53,290,000 | | | 53,290,000 |
| | | Mechanical & Electrical Cost | | L.S. | | 1 | 9,561,000 | | 9,561,000 | |
| 1-2 | Transmission Pump House | Civil Work | | L.S. | | 1 | 12,147,000 | | | 12,147,000 |
| 1-3 | Transmission Pump | Mechanical & Electrical Cost | 15.8m ³ /min *84.m *4 (+1) | L.S. | | 1 | 98,706,000 | | 98,706,000 | |
| 1-4 | Power Receiving Facility | | 3,000 KVA | L.S. | | 1 | 19,296,000 | | 19,296,000 | |
| 1-5 | Generator | | 1,500 KVA *2 | L.S. | | 1 | 79,608,000 | | 79,608,000 | |
| 1-6 | Transmission Pipe | | DIP900mmT | m | 18,924 | 15,045 | 284,713,837 | | | 284,713,837 |
| | Sub Total | | | | | | 557,321,837 | ¥1,476,902,867 | 207,171,000 | 350,150,837 |
| 2 | Khulushi Reservoir | | | | | | | | | |
| 2-1 | Distribution Reservoir | Ground Reservoir | 16,200 m ³ | L.S. | | 1 | 83,268,000 | | | 83,268,000 |
| | | Elevated Tank | dia18m *7mD *16mH | L.S. | | 1 | 22,052,000 | | | 22,052,000 |
| | | Lift Pump | 13.1m ³ /min *25m *3 (+1) | L.S. | | 1 | 65,794,000 | | 65,794,000 | |
| | | Pump House | | L.S. | | 1 | 4,240,000 | | | 4,240,000 |
| | | Power Receiving Facility | 500 KVA | L.S. | | 1 | 4,393,000 | | 4,393,000 | |
| | | Generator | 250 KVA *2 | L.S. | | 1 | 22,555,000 | | 22,555,000 | |
| | | Administration Building | | L.S. | | 1 | 1,779,000 | | | 1,779,000 |
| | | Implant Piping | | L.S. | | 1 | 30,836,000 | | | 30,836,000 |
| | | Earth Work | | L.S. | | 1 | 18,230,000 | | | 18,230,000 |
| | | Road Work | | L.S. | | 1 | 8,123,000 | | | 8,123,000 |
| | | Lighting | | L.S. | | 1 | 1,064,000 | | | 1,064,000 |
| | Sub Total | | | | | | 262,334,000 | ¥695,185,100 | 92,742,000 | 169,592,000 |
| 3 | Distribution Pipe | | | | | | | | | |
| 3-1 | Distribution Pipes | | DIP1000mmD | m | 23,472 | 1,140 | 26,757,852 | | | 26,757,852 |
| | | | DIP900mmD | m | 19,825 | 910 | 18,041,023 | | | 18,041,023 |
| | | | DIP800mmD | m | 16,587 | 2,875 | 47,687,338 | | | 47,687,338 |
| | | | DIP700mmD | m | 13,651 | 200 | 2,730,200 | | | 2,730,200 |
| | | | DIP600mmD | m | 11,570 | 985 | 11,396,253 | | | 11,396,253 |
| | | | DIP500mmD | m | 9,085 | 3,513 | 31,915,254 | | | 31,915,254 |
| | | | DIP450mmD | m | 7,931 | 810 | 6,424,110 | | | 6,424,110 |
| | | | DIP400mmD | m | 6,918 | 0 | 0 | | | 0 |
| | | | DIP350mmD | m | 6,076 | 420 | 2,552,088 | | | 2,552,088 |
| | | | DIP300mmD | m | 5,235 | 3,225 | 16,882,553 | | | 16,882,553 |
| | | | PVC250mmD | m | 6,477 | 4,065 | 26,328,192 | | | 26,328,192 |
| | | | PVC200mmD | m | 4,629 | 2,840 | 13,147,428 | | | 13,147,428 |
| | Sub Total | | | | | 20,983 | 203,862,290 | ¥540,235,069 | 0 | 203,862,290 |
| | Total (Direct Construction Cost) | | | | | | 1,023,518,127 | ¥2,712,323,036 | 299,913,000 | 723,605,127 |
| 4 | Overhead & Profit etc | 25% of Direct Construction Cost | | L.S. | | 1 | 255,879,532 | | 74,978,250 | 180,901,282 |
| | Grand Total | | | | | | 1,279,397,659 | ¥2,712,323,036 | 374,891,250 | 904,506,409 |

Case I - b - 1 New Battali and Nasirabad Reservoir

Unit: Taka

| No | Name of Facility | Item | Dimension | Unit | Unit Cost | Quantity | Price | Note | E&M | Civil |
|---------------------------------|----------------------------------|-----------------------------------|---|------|-----------|----------|---------------|-----------------------------|-------------|---------------|
| 1 Mohara WTP | | | | | | | | | | |
| 1-1 | Clear Well | Civil Work | 6.716 m ³ | L.S. | | 1 | 53,290,000 | | | 53,290,000 |
| | | Mechanical & Electrical Cos | | L.S. | | 1 | 9,561,000 | | 9,561,000 | |
| 1-2 | Transmission Pump House | Civil Work | | L.S. | | 1 | 12,147,000 | | | 12,147,000 |
| 1-3 | Transmission Pump | Mechanical & Electrical Cos | 15.8m ³ /min × 80 m × 4 (+1) | L.S. | | 1 | 97,509,000 | | | 97,509,000 |
| 1-4 | Power Receiving Facility | Mechanical & Electrical Cos | 3,000 KVA | L.S. | | 1 | 19,296,000 | | | 19,296,000 |
| 1-5 | Generator | Mechanical & Electrical Cos | 1,500 KVA × 2 | L.S. | | 1 | 79,608,000 | | | 79,608,000 |
| 1-4 | Transmission Pipe | | DIP1000mmT | m | 22,405 | 10,400 | 233,010,960 | | | 233,010,960 |
| | | | DIP900mmT | m | 18,924 | 3,180 | 98,027,097 | | | 98,027,097 |
| | | | DIP900mmT | m | 28,386 | 580 | 16,464,011 | near Battali Hill Reservoir | | 16,464,011 |
| | | | DIP400mmT | m | 6,603 | 500 | 3,301,725 | | | 3,301,725 |
| | | Reinstallation | DIP900mmR | m | 26,401 | 580 | 15,312,696 | near Battali Hill Reservoir | | 15,312,696 |
| | | Reinstallation ACP to DIP | DIP600mmT | m | 22,088 | 370 | 8,172,486 | near Battali Hill Reservoir | | 8,172,486 |
| | | Transmission Route Rehabilitation | | L.S. | | 1 | 4,200,000 | Stair & Retaining Wall | | 4,200,000 |
| | Sub Total | | | | | | 649,899,975 | ¥1,722,234,932 | 205,974,000 | 443,925,975 |
| 2 Nasirabad Reservoir | | | | | | | | | | |
| 2-1 | Distribution Reservoir | Ground Reservoir | 4,800 m ³ | E.S. | | 1 | 38,087,000 | | | 38,087,000 |
| | | Elevated Tank | dia15m × 6mD × 18mH | L.S. | | 1 | 19,767,000 | | | 19,767,000 |
| | | Lift Pump | 7.8m ³ /min × 23m × 3 (+1) | L.S. | | 1 | 56,603,000 | | 56,603,000 | |
| | | Pump House | | L.S. | | 1 | 3,994,000 | | | 3,994,000 |
| | | Power Receiving Facility | 400 KVA | L.S. | | 1 | 3,514,000 | | 3,514,000 | |
| | | Generator | 200 KVA × 2 | L.S. | | 1 | 18,044,000 | | 18,044,000 | |
| | | Administration Building | | L.S. | | 1 | 1,779,000 | | | 1,779,000 |
| | | Implant Piping | | L.S. | | 1 | 16,785,000 | | | 16,785,000 |
| | | Earth Work | | L.S. | | 1 | 9,923,000 | | | 9,923,000 |
| | | Road Work | | L.S. | | 1 | 4,422,000 | | | 4,422,000 |
| | | Lighting | | L.S. | | 1 | 579,000 | | | 579,000 |
| | Sub Total | | | | | | 173,497,000 | ¥459,767,050 | 78,161,000 | 95,336,000 |
| 3 New Battali Reservoir | | | | | | | | | | |
| 3-1 | Distribution Reservoir | Ground Reservoir 4 Basin | 13,200 m ³ | L.S. | | 1 | 67,848,000 | | | 67,848,000 |
| | | Implant Piping | | L.S. | | 1 | 22,979,000 | | | 22,979,000 |
| | | Earth Work | | L.S. | | 1 | 16,456,000 | | | 16,456,000 |
| | | Road Work | | L.S. | | 1 | 3,666,000 | | | 3,666,000 |
| | | Lighting | | L.S. | | 1 | 480,000 | | | 480,000 |
| | | Retaining Wall | | L.S. | | 1 | 11,100,000 | | | 11,100,000 |
| | Sub Total | | | | | | 122,529,000 | ¥324,701,850 | 0 | 122,529,000 |
| 4 Old Battali Reservoir Rebuilt | | | | | | | | | | |
| 4-1 | Distribution Reservoir | Ground Reservoir | 13,700 m ³ | L.S. | | 1 | 70,418,000 | Rebuilt | | 70,418,000 |
| | | Implant Piping | | L.S. | | 1 | 23,410,000 | | | 23,410,000 |
| | | Earth Work | | L.S. | | 1 | 8,382,000 | | | 8,382,000 |
| | | Road Work | | L.S. | | 1 | 3,735,000 | | | 3,735,000 |
| | | Lighting | | L.S. | | 1 | 489,000 | | | 489,000 |
| | | Demolition Cost | | L.S. | | 1 | 8,000,000 | | | 8,000,000 |
| | Sub Total | | | | | | 114,434,000 | ¥103,250,100 | 0 | 114,434,000 |
| 5 Distribution Pipe | | | | | | | | | | |
| 5-1 | Distribution Pipes | | DIP1000mmD | m | 35,208 | 370 | 13,026,849 | near Battali Hill Reservoir | | 13,026,849 |
| | | | DIP1000mmD | m | 23,472 | 80 | 1,877,744 | | | 1,877,744 |
| | | | DIP900mmD | m | 19,825 | 0 | 0 | | | 0 |
| | | | DIP800mmD | m | 16,587 | 3,410 | 56,561,329 | | | 56,561,329 |
| | | | DIP700mmD | m | 13,651 | 1,000 | 13,651,000 | | | 13,651,000 |
| | | | DIP600mmD | m | 11,570 | 2,475 | 28,635,255 | | | 28,635,255 |
| | | | DIP500mmD | m | 9,085 | 3,670 | 33,341,583 | | | 33,341,583 |
| | | | DIP450mmD | m | 7,931 | 1,545 | 12,253,395 | | | 12,253,395 |
| | | | DIP400mmD | m | 6,918 | 600 | 4,150,740 | | | 4,150,740 |
| | | | DIP350mmD | m | 6,076 | 420 | 2,552,088 | | | 2,552,088 |
| | | | DIP300mmD | m | 5,235 | 2,270 | 11,883,223 | | | 11,883,223 |
| | | | PVC250mmD | m | 6,477 | 1,285 | 8,322,688 | | | 8,322,688 |
| | | | PVC200mmD | m | 4,629 | 905 | 4,189,585 | | | 4,189,585 |
| | Sub Total | | | | | 18,030 | 190,445,479 | ¥504,680,521 | 0 | 190,445,479 |
| | Total (Direct Construction Cost) | | | | | | 1,250,805,454 | ¥3,314,634,453 | 284,135,000 | 966,670,454 |
| 6 Overhead & Profit etc. | | | | | | | | | | |
| | | 25% of Direct Construction Cost | | L.S. | | 1 | 312,701,363 | | 71,033,750 | 241,667,613 |
| | | | | | | | | | 0 | 0 |
| | Grand Total | | | | | | 1,563,506,817 | ¥3,314,634,453 | 355,168,750 | 1,208,338,067 |

Case I – b – 2 New Battali and Nasirabad Reservoir

Unit : Taka

| No. | Name of Facility | Item | Dimcasion | Unit | Unit Cost | Quantity | Price | Note | E&M | Civil |
|-----|----------------------------------|-----------------------------------|--------------------------|------|-----------|----------|---------------|-----------------------------|-------------|---------------|
| 1 | Mohara WTP | | | | | | | | | |
| 1-1 | Clear Well | Civil Work | 6,716 m3 | L.S. | | 1 | 53,290,000 | | | 53,290,000 |
| | | Mechanical & Electrical Cost | | L.S. | | 1 | 9,561,000 | | 9,561,000 | |
| 1-2 | Transmission Pump House | Civil Work | | L.S. | | 1 | 12,147,000 | | | 12,147,000 |
| 1-3 | Transmission Pump | Mechanical & Electrical Cost | 15.8m3/min ×80.m ×4 (+1) | L.S. | | 1 | 97,509,000 | | | 97,509,000 |
| 1-4 | Power Receiving Facility | | 3,000 KVA | L.S. | | 1 | 19,296,000 | | | 19,296,000 |
| 1-5 | Generator | | 1,500 KVA ×2 | L.S. | | 1 | 79,608,000 | | | 79,608,000 |
| 1-4 | Transmission Pipe | | DIP1000mmT | m | 22,405 | 10,400 | 233,010,960 | | | 233,010,960 |
| | | | DIP900mmT | m | 18,924 | 5,180 | 98,027,097 | | | 98,027,097 |
| | | | DIP900mmT | m | 28,386 | 580 | 16,464,011 | near Battali Hill Reservoir | | 16,464,011 |
| | | | DIP400mmT | m | 6,603 | 400 | 2,641,380 | | | 2,641,380 |
| | | Reinstallation | DIP900mmT | m | 26,401 | 580 | 15,312,696 | near Battali Hill Reservoir | | 15,312,696 |
| | | Reinstallation ACP to DIP | DIP600mmT | m | 22,088 | 370 | 8,172,486 | near Battali Hill Reservoir | | 8,172,486 |
| | | Transmission Route Rehabilitation | | L.S. | | 1 | 4,200,000 | Stair & Retaining Wall | | 4,200,000 |
| | Sub Total | | | | | | 649,239,630 | ¥1,720,485,018 | 205,974,000 | 443,265,630 |
| 2 | Nasirabad Reservoir | | | | | | | | | |
| 2-1 | Distribution Reservoir | Elevated Tank | dia24m ×9mD ×18mH | L.S. | | 1 | 30,624,000 | | | 30,624,000 |
| | | Implant Piping | | L.S. | | 1 | 8,134,000 | | | 8,134,000 |
| | | Earth Work | | L.S. | | 1 | 6,615,000 | | | 6,615,000 |
| | | Road Work | | L.S. | | 1 | 2,948,000 | | | 2,948,000 |
| | | Lighting | | L.S. | | 1 | 386,000 | | | 386,000 |
| | Sub Total | | | | | | 48,707,000 | ¥129,073,550 | 0 | 48,707,000 |
| 3 | New Battali Reservoir | | | | | | | | | |
| 3-1 | Distribution Reservoir | Ground Reservoir 4 Basin | 13,200 m3 | L.S. | | 1 | 67,848,000 | | | 67,848,000 |
| | | Implant Piping | | L.S. | | 1 | 22,979,000 | | | 22,979,000 |
| | | Earth Work | | L.S. | | 1 | 16,456,000 | | | 16,456,000 |
| | | Road Work | | L.S. | | 1 | 3,666,000 | | | 3,666,000 |
| | | Lighting | | L.S. | | 1 | 480,000 | | | 480,000 |
| | | Retaining Wall | | L.S. | | 1 | 11,100,000 | | | 11,100,000 |
| | Sub Total | | | | | | 122,529,000 | ¥324,701,850 | 0 | 122,529,000 |
| 4 | Old Battali Reservoir Rebuilt | | | | | | | | | |
| 4-1 | Distribution Reservoir | Ground Reservoir | 13,700 m3 | L.S. | | 1 | 70,418,000 | Rebuilt | | 70,418,000 |
| | | Implant Piping | | L.S. | | 1 | 23,410,000 | | | 23,410,000 |
| | | Earth Work | | L.S. | | 1 | 8,382,000 | | | 8,382,000 |
| | | Road Work | | L.S. | | 1 | 3,735,000 | | | 3,735,000 |
| | | Lighting | | L.S. | | 1 | 489,000 | | | 489,000 |
| | | Demolition Cost | | L.S. | | 1 | 8,000,000 | | | 8,000,000 |
| | Sub Total | | | | | | 114,434,000 | ¥303,250,100 | 0 | 114,434,000 |
| 5 | Distribution Pipe | | | | | | | | | |
| 5-1 | Distribution Pipes | | DIP1000mmD | m | 35,208 | 370 | 13,026,849 | near Battali Hill Reservoir | | 13,026,849 |
| | | | DIP1000mmD | m | 23,472 | 80 | 1,877,744 | | | 1,877,744 |
| | | | DIP900mmD | m | 19,825 | 0 | 0 | | | 0 |
| | | | DIP800mmD | m | 16,587 | 3,410 | 56,561,329 | | | 56,561,329 |
| | | | DIP700mmD | m | 13,651 | 1,000 | 13,651,000 | | | 13,651,000 |
| | | | DIP600mmD | m | 11,570 | 2,475 | 28,635,255 | | | 28,635,255 |
| | | | DIP500mmD | m | 9,085 | 3,670 | 33,341,583 | | | 33,341,583 |
| | | | DIP450mmD | m | 7,931 | 1,545 | 12,253,395 | | | 12,253,395 |
| | | | DIP400mmD | m | 6,918 | 600 | 4,150,740 | | | 4,150,740 |
| | | | DIP350mmD | m | 6,076 | 420 | 2,552,088 | | | 2,552,088 |
| | | | DIP300mmD | m | 5,235 | 2,270 | 11,883,223 | | | 11,883,223 |
| | | | PVC250mmD | m | 6,477 | 1,285 | 8,322,688 | | | 8,322,688 |
| | | | PVC200mmD | m | 4,629 | 905 | 4,189,585 | | | 4,189,585 |
| | Sub Total | | | | | 18,030 | 190,445,479 | ¥504,680,521 | 0 | 190,445,479 |
| | Total (Direct Construction Cost) | | | | | | 1,125,355,109 | ¥2,982,191,039 | 205,974,000 | 919,381,109 |
| 6 | Overhead & Profit etc. | 25% of Direct Construction Cost | | L.S. | | 1 | 281,338,777 | | 51,493,500 | 229,845,277 |
| | Grand Total | | | | | | 1,406,693,886 | ¥2,982,191,039 | 257,467,500 | 1,149,226,386 |

Case I -b-3 Nasirabad Reservoir

Unit: Taka

| No | Name of Facility | Item | Dimension | Unit | Unit Cost | Quantity | Price | Note | E&M | Civil | |
|------------------------------|---|---------------------------------|--------------------------|------|-----------|----------|----------------------|-----------------------|-----------------------|--------------------|--------------------|
| 1 Mohara WTP | | | | | | | | | | | |
| 1-1 | Clear Well | Civil Work | 6,716 m3 | L.S. | | 1 | 53,290,000 | | | 53,290,000 | |
| | | Mechanical & Electrical Cost | | L.S. | | 1 | 9,561,000 | | 9,561,000 | | |
| 1-2 | Transmission Pump House | Civil Work | | L.S. | | 1 | 12,147,000 | | | 12,147,000 | |
| 1-3 | Transmission Pump | Mechanical & Electrical Cos | 15.8m3/min ×63.m ×4 (+1) | L.S. | | 1 | 91,856,000 | | 91,856,000 | | |
| 1-4 | Power Receiving Facility | Mechanical & Electrical Cos | 2,500 KVA | L.S. | | 1 | 16,080,000 | | 16,080,000 | | |
| 1-5 | Generator | Mechanical & Electrical Cos | 1,250 KVA ×2 | L.S. | | 1 | 66,340,000 | | 66,340,000 | | |
| 1-4 | Transmission Pipe | | DIP900mmT | m | 18,924 | 10,900 | 206,273,235 | | | 206,273,235 | |
| | Sub Total | | | | | | 455,547,235 | ¥1,207,200,173 | 183,837,000 | 271,710,235 | |
| 2 Nasirabad Reservoir | | | | | | | | | | | |
| 2-1 | Distribution Reservoir | Ground Reservoir | 19,500 m3 | L.S. | | 1 | 100,230,000 | | | 100,230,000 | |
| | | Elevated Tank | dia22m ×8mD ×23mH | L.S. | | 1 | 31,247,000 | | | 31,247,000 | |
| | | Lift Pump | 31.2m3/min ×31m ×3 (+1) | L.S. | | 1 | 112,126,000 | | 112,126,000 | | |
| | | Pump House | | L.S. | | 1 | 9,275,000 | | | 9,275,000 | |
| | | Power Receiving Facility | 1,500 KVA | L.S. | | 1 | 13,178,000 | | 13,178,000 | | |
| | | Generator | 750 KVA ×2 | L.S. | | 1 | 67,665,000 | | 67,665,000 | | |
| | | Administration Building | | L.S. | | 1 | 1,779,000 | | | 1,779,000 | |
| | | Inplant Piping | | L.S. | | 1 | 32,494,000 | | | 32,494,000 | |
| | | Earth Work | | L.S. | | 1 | 20,001,000 | | | 20,001,000 | |
| | | Road Work | | L.S. | | 1 | 8,912,000 | | | 8,912,000 | |
| | | Lighting | | L.S. | | 1 | 1,167,000 | | | 1,167,000 | |
| | Sub Total | | | | | | 398,074,000 | ¥1,054,896,100 | 192,969,000 | 205,105,000 | |
| 3 Distribution Pipe | | | | | | | | | | | |
| 3-1 | Distribution Pipes | DIP1100mmD | | m | 26,542 | 4,050 | 107,494,695 | | | 107,494,695 | |
| | | DIP1000mmD | | m | 23,472 | 0 | 0 | | | 0 | |
| | | DIP900mmD | | m | 19,825 | 1,980 | 39,254,094 | | | 39,254,094 | |
| | | DIP800mmD | | m | 16,587 | 1,820 | 30,188,158 | | | 30,188,158 | |
| | | DIP700mmD | | m | 13,651 | 1,700 | 23,206,700 | | | 23,206,700 | |
| | | DIP600mmD | | m | 11,570 | 0 | 0 | | | 0 | |
| | | DIP500mmD | | m | 9,085 | 2,010 | 18,260,649 | | | 18,260,649 | |
| | | DIP450mmD | | m | 7,931 | 1,900 | 15,068,900 | | | 15,068,900 | |
| | | DIP400mmD | | m | 6,918 | 600 | 4,150,740 | | | 4,150,740 | |
| | | DIP350mmD | | m | 6,076 | 440 | 2,673,616 | | | 2,673,616 | |
| | | DIP300mmD | | m | 5,235 | 1,910 | 9,998,659 | | | 9,998,659 | |
| | | PVC250mmD | | m | 6,477 | 430 | 2,785,024 | | | 2,785,024 | |
| | | PVC200mmD | | m | 4,629 | 960 | 4,444,201 | | | 4,444,201 | |
| | Sub Total | | | | | 17,800 | 257,525,436 | ¥682,442,406 | 0 | 257,525,436 | |
| | Total (Direct Construction Cost) | | | | | | | 1,111,146,671 | ¥2,944,538,679 | 376,806,000 | 734,340,671 |
| 5 | Overhead & Profit etc. | 25% of Direct Construction Cost | | | L.S. | | 1 | 277,786,668 | | 94,201,500 | 183,585,168 |
| | Grand Total | | | | | | 1,388,933,339 | ¥2,944,538,679 | 471,007,500 | 917,925,839 | |

Case I -c-1 Nasirabad Reservoir and New Battali Reservoir

Unit : Taka

| No | Name of Facility | Item | Dimension | Unit | Unit Cost | Quantity | Price | Note | E&M | Civil |
|-----|----------------------------------|-----------------------------------|-------------------------|------|-----------|----------|---------------|----------------------------------|-------------|---------------|
| 1 | Mohara WTP | | | | | | | | | |
| 1-1 | Clear Well | Civil Work | 6.716 m3 | L.S. | | 1 | 53,290,000 | | | 53,290,000 |
| | | Mechanical & Electrical Cost | | L.S. | | 1 | 9,561,000 | | 9,561,000 | |
| 1-2 | Transmission Pump House | Civil Work | | L.S. | | 1 | 12,147,000 | | | 12,147,000 |
| 1-3 | Transmission Pump | Mechanical & Electrical Cost | 15.8m3/min *37m *4 (+1) | L.S. | | 1 | 80,413,000 | | | 80,413,000 |
| 1-4 | Power Receiving Facility | Mechanical & Electrical Cost | 2,000 KVA | L.S. | | 1 | 12,864,000 | | | 12,864,000 |
| 1-5 | Generator | Mechanical & Electrical Cost | 1,000 KVA *2 | L.S. | | 1 | 53,072,000 | | | 53,072,000 |
| 1-6 | Transmission Pipe | | | m | 22,405 | 12,255 | 274,572,050 | Mohara WTP to Nasirabad Re. | | 274,572,050 |
| | | | | m | 22,405 | 3,940 | 88,275,306 | Nasirabad Re. to Battali Hill Re | | 88,275,306 |
| | | | | m | 33,607 | 580 | 19,492,263 | near Battali Hill Reservoir | | 19,492,263 |
| | | Reinstallation | DIP900mmT | m | 26,401 | 580 | 15,312,696 | near Battali Hill Reservoir | | 15,312,696 |
| | | Reinstallation ACP to DIP | DIP600mmT | m | 22,088 | 370 | 8,172,486 | near Battali Hill Reservoir | | 8,172,486 |
| | | Transmission Route Rehabilitation | | L.S. | | 1 | 4,200,000 | Stair & Retaining Wall | | 4,200,000 |
| | Sub Total | | | | | | 631,271,801 | ¥1,673,135,271 | 155,910,000 | 475,461,801 |
| 2 | Nasirabad Reservoir | | | | | | | | | |
| 2-1 | Distribution Reservoir | Ground Reservoir | 19,200 m3 | L.S. | | 1 | 98,688,000 | | | 98,688,000 |
| | | Elevated Tank | dia15m *6mD *27.4mH | L.S. | | 1 | 24,389,000 | | | 24,389,000 |
| | | Lift Pump | 7.8m3/min *35m *3 (+1) | L.S. | | 1 | 62,867,000 | to Elevated Tank | | 62,867,000 |
| | | Lift Pump | 23.4m3/min *51m *3 (+1) | L.S. | | 1 | 118,174,000 | to Battali Hill New Reservoir | | 118,174,000 |
| | | Pump House | | L.S. | | 1 | 15,230,000 | | | 15,230,000 |
| | | Power Receiving Facility | 2,000 KVA | L.S. | | 1 | 12,864,000 | | | 12,864,000 |
| | | Generator | 1,000 KVA *2 | L.S. | | 1 | 53,072,000 | | | 53,072,000 |
| | | Administration Building | | L.S. | | 1 | 1,779,000 | | | 1,779,000 |
| | | Implant Piping | | L.S. | | 1 | 32,243,000 | | | 32,243,000 |
| | | Earth Work | | L.S. | | 1 | 19,846,000 | | | 19,846,000 |
| | | Road Work | | L.S. | | 1 | 8,843,000 | | | 8,843,000 |
| | | Lighting | | L.S. | | 1 | 1,158,000 | | | 1,158,000 |
| | Sub Total | | | | | | 449,153,000 | ¥1,190,255,450 | 246,977,000 | 202,176,000 |
| 3 | New Battali Reservoir | | | | | | | | | |
| 3-1 | Distribution Reservoir | Ground Reservoir | 3,250 m3 | L.S. | | 1 | 25,788,000 | | | 25,788,000 |
| | | Implant Piping | | L.S. | | 1 | 20,327,000 | | | 20,327,000 |
| | | Earth Work | | L.S. | | 1 | 16,331,000 | | | 16,331,000 |
| | | Road Work | | L.S. | | 1 | 3,638,000 | | | 3,638,000 |
| | | Lighting | | L.S. | | 1 | 477,000 | | | 477,000 |
| | | Retaining Wall | | L.S. | | 1 | 11,100,000 | | | 11,100,000 |
| | Sub Total | | | | | | 77,661,000 | ¥205,801,650 | 0 | 77,661,000 |
| 4 | Distribution Pipe | | | | | | | | | |
| 4-1 | Distribution Pipes | | | m | 35,208 | 370 | 13,026,849 | near Battali Hill Reservoir | | 13,026,849 |
| | | | | m | 23,472 | 80 | 1,877,744 | | | 1,877,744 |
| | | | | m | 19,825 | 0 | 0 | | | 0 |
| | | | | m | 16,587 | 3,410 | 56,561,329 | | | 56,561,329 |
| | | | | m | 13,651 | 1,700 | 23,206,700 | | | 23,206,700 |
| | | | | m | 11,370 | 1,875 | 21,693,375 | | | 21,693,375 |
| | | | | m | 9,085 | 1,990 | 18,078,951 | | | 18,078,951 |
| | | | | m | 7,931 | 700 | 5,551,700 | | | 5,551,700 |
| | | | | m | 6,918 | 600 | 4,150,740 | | | 4,150,740 |
| | | | | m | 6,076 | 4,565 | 27,738,766 | | | 27,738,766 |
| | | | | m | 5,235 | 2,685 | 14,055,707 | | | 14,055,707 |
| | | | | m | 6,477 | 700 | 4,533,760 | | | 4,533,760 |
| | | | | m | 4,629 | 1,985 | 9,189,312 | | | 9,189,312 |
| | Sub Total | | | | | 20,660 | 199,664,932 | ¥529,112,070 | 0 | 199,664,932 |
| | Total (Direct Construction Cost) | | | | | | 1,357,850,733 | ¥3,598,304,442 | 402,887,000 | 954,963,733 |
| 5 | Overhead & Profit etc. | 25% of Direct Construction Cost | | L.S. | | 1 | 339,462,683 | | 100,721,750 | 238,740,933 |
| | Grand Total | | | | | | 1,697,313,416 | ¥3,598,304,442 | 503,608,750 | 1,193,704,666 |

Case I -- c -- 2 New Battali and Nasirabad Reservoir

Unit : Taka

| No. | Name of Facility | Item | Dimension | Unit | Unit Cost | Quantity | Price | Note | E&M | Civil |
|--|----------------------------------|-----------------------------------|---------------------------------------|------|-----------|----------|---------------|-----------------------------|-------------|---------------|
| 1 Mohara WTP | | | | | | | | | | |
| 1-1 | Clear Well | Civil Work | 6,716 m ³ | L.S. | | 1 | 53,290,000 | | | 53,290,000 |
| | | Mechanical & Electrical Cost | | L.S. | | 1 | 9,561,000 | | 9,561,000 | |
| 1-2 | Transmission Pump House | Civil Work | | L.S. | | 1 | 12,147,000 | | | 12,147,000 |
| 1-3 | Transmission Pump | Mechanical & Electrical Cost | 15.8m ³ /min ×80 m ×4 (+1) | L.S. | | 1 | 97,509,000 | | 97,509,000 | |
| 1-4 | Power Receiving Facility | | 3,000 KVA | L.S. | | 1 | 19,296,000 | | 19,296,000 | |
| 1-5 | Generator | | 1,500 KVA ×2 | L.S. | | 1 | 79,608,000 | | 79,608,000 | |
| 1-4 | Transmission Pipe | | DIP1000mmT | m | 22,405 | 12,255 | 274,572,050 | | | 274,572,050 |
| | | | DIP900mmT | m | 18,924 | 3,940 | 74,561,151 | | | 74,561,151 |
| | | | DIP900mmT | m | 28,386 | 580 | 16,464,011 | near Battali Hill Reservoir | | 16,464,011 |
| | | Reinstallation | DIP900mmT | m | 26,401 | 580 | 15,312,696 | near Battali Hill Reservoir | | 15,312,696 |
| | | Reinstallation ACP to DIP | DIP600mmT | m | 22,088 | 370 | 8,172,486 | near Battali Hill Reservoir | | 8,172,486 |
| | | Transmission Route Rehabilitation | | L.S. | | 1 | 4,200,000 | Stair & Retaining Wall | | 4,200,000 |
| | Sub Total | | | | | | 664,693,393 | ¥1,761,437,491 | 205,974,000 | 458,719,393 |
| 2 Nasirabad Reservoir | | | | | | | | | | |
| 2-1 | Distribution Reservoir | Elevated Tank | día24m ×9mD ×24.4mH | L.S. | | 1 | 35,655,000 | | | 35,655,000 |
| | | Implant Piping | | L.S. | | 1 | 8,134,000 | | | 8,134,000 |
| | | Earth Work | | L.S. | | 1 | 6,615,000 | | | 6,615,000 |
| | | Road Work | | L.S. | | 1 | 2,948,000 | | | 2,948,000 |
| | | Lighting | | L.S. | | 1 | 386,000 | | | 386,000 |
| | Sub Total | | | | | | 53,738,000 | ¥142,405,700 | 0 | 53,738,000 |
| 3 New Battali Reservoir | | | | | | | | | | |
| 3-1 | Distribution Reservoir | Ground Reservoir 4 Basin | 13,200 m ³ | L.S. | | 1 | 67,848,000 | | | 67,848,000 |
| | | Implant Piping | | L.S. | | 1 | 22,979,000 | | | 22,979,000 |
| | | Earth Work | | L.S. | | 1 | 16,456,000 | | | 16,456,000 |
| | | Road Work | | L.S. | | 1 | 3,666,000 | | | 3,666,000 |
| | | Lighting | | L.S. | | 1 | 480,000 | | | 480,000 |
| | | Retaining Wall | | L.S. | | 1 | 11,100,000 | | | 11,100,000 |
| | Sub Total | | | | | | 122,529,000 | ¥324,701,850 | 0 | 122,529,000 |
| 4 Old Battali Reservoir Rebuilt | | | | | | | | | | |
| 4-1 | Distribution Reservoir | Ground Reservoir | 13,700 m ³ | L.S. | | 1 | 70,418,000 | Rebuilt | | 70,418,000 |
| | | Implant Piping | | L.S. | | 1 | 23,410,000 | | | 23,410,000 |
| | | Earth Work | | L.S. | | 1 | 16,764,000 | | | 16,764,000 |
| | | Road Work | | L.S. | | 1 | 3,735,000 | | | 3,735,000 |
| | | Lighting | | L.S. | | 1 | 489,000 | | | 489,000 |
| | | Demolition Cost | | L.S. | | 1 | 8,000,000 | | | 8,000,000 |
| | Sub Total | | | | | | 122,816,000 | ¥325,462,400 | 0 | 122,816,000 |
| 5 Distribution Pipe | | | | | | | | | | |
| 5-1 | Distribution Pipes | | DIP1000mmD | m | 35,208 | 370 | 13,026,849 | near Battali Hill Reservoir | | 13,026,849 |
| | | | DIP1000mmD | m | 23,472 | 80 | 1,877,744 | | | 1,877,744 |
| | | | DIP900mmD | m | 19,825 | 0 | 0 | | | 0 |
| | | | DIP800mmD | m | 16,587 | 3,410 | 56,561,329 | | | 56,561,329 |
| | | | DIP700mmD | m | 13,651 | 1,000 | 13,651,000 | | | 13,651,000 |
| | | | DIP600mmD | m | 11,570 | 2,575 | 29,792,235 | | | 29,792,235 |
| | | | DIP500mmD | m | 9,085 | 1,990 | 18,078,951 | | | 18,078,951 |
| | | | DIP450mmD | m | 7,931 | 700 | 5,551,700 | | | 5,551,700 |
| | | | DIP400mmD | m | 6,918 | 600 | 4,150,740 | | | 4,150,740 |
| | | | DIP350mmD | m | 6,076 | 4,565 | 27,738,766 | | | 27,738,766 |
| | | | DIP300mmD | m | 5,235 | 2,685 | 14,055,707 | | | 14,055,707 |
| | | | PVC250mmD | m | 6,477 | 700 | 4,533,760 | | | 4,533,760 |
| | | | PVC200mmD | m | 4,629 | 1,985 | 9,189,312 | | | 9,189,312 |
| | Sub Total | | | | | 20,660 | 198,208,092 | ¥525,251,444 | 0 | 198,208,092 |
| | Total (Direct Construction Cost) | | | | | | 1,161,984,485 | ¥3,079,258,886 | 205,974,000 | 956,010,485 |
| 6 Overhead & Profit etc. | | | | | | | | | | |
| | | 25% of Direct Construction Cost | | L.S. | | 1 | 290,496,121 | | 51,493,500 | 239,002,621 |
| | Grand Total | | | | | | 1,452,480,607 | ¥3,079,258,886 | 257,467,500 | 1,195,013,107 |

Case II – b New Battali Reservoir

Unit : Taka

| No. | Name of Facility | Item | Dimension | Unit | Unit Cost | Quantity | Price | Note | E&M | Civil |
|-----|----------------------------------|-----------------------------------|---------------------------------------|------|-----------|----------|---------------|-----------------------------|-------------|---------------|
| 1 | Mohara WTP | | | | | | | | | |
| 1-1 | Clear Well | Civil Work | 6,716 m ³ | L.S. | | 1 | 53,290,000 | | | 53,290,000 |
| | | Mechanical & Electrical Cost | | L.S. | | 1 | 9,561,000 | | 9,561,000 | |
| 1-2 | Transmission Pump House | Civil Work | | L.S. | | 1 | 12,147,000 | | | 12,147,000 |
| 1-3 | Transmission Pump | Mechanical & Electrical Cos | 15.8m ³ /min ×81.m ×4 (+1) | L.S. | | 1 | 97,813,000 | | 97,813,000 | |
| 1-4 | Power Receiving Facility | Mechanical & Electrical Cos | 3,000 KVA | L.S. | | 1 | 19,296,000 | | 19,296,000 | |
| 1-5 | Generator | Mechanical & Electrical Cos | 1,500 KVA ×2 | L.S. | | 1 | 79,608,000 | | 79,608,000 | |
| 1-4 | Transmission Pipe | | DIP1000mmT | m | 22,405 | 15,580 | 349,068,342 | | | 349,068,342 |
| 1-4 | Transmission Pipe | | DIP1000mmT | m | 33,607 | 580 | 19,492,263 | near Battali Hill Reservoir | | 19,492,263 |
| | | Reinstallation | DIP900mmT | m | 26,401 | 580 | 15,312,696 | near Battali Hill Reservoir | | 15,312,696 |
| | | Reinstallation ACP to DIP | DIP600mmT | m | 22,088 | 370 | 8,172,486 | near Battali Hill Reservoir | | 8,172,486 |
| | | Transmission Route Rehabilitation | | L.S. | | 1 | 4,200,000 | Stair & Retaining Wall | | 4,200,000 |
| | Sub Total | | | | | | 667,960,787 | ¥1,770,096,086 | 206,278,000 | 461,682,787 |
| 2 | New Battali Reservoir | | | | | | | | | |
| 2-1 | Distribution Reservoir | Ground Reservoir | 19,360 m ³ | L.S. | | 1 | 99,511,000 | | | 99,511,000 |
| | | Implant Piping | | L.S. | | 1 | 24,806,000 | | | 24,806,000 |
| | | Earth Work | | L.S. | | 1 | 19,929,000 | | | 19,929,000 |
| | | Road Work | | L.S. | | 1 | 4,440,000 | | | 4,440,000 |
| | | Lighting | | L.S. | | 1 | 582,000 | | | 582,000 |
| | | Retaining Wall | | L.S. | | 1 | 11,100,000 | | | 11,100,000 |
| | Sub Total | | | | | | 160,368,000 | ¥424,975,200 | 0 | 160,368,000 |
| 3 | Old Battali Reservoir Rebuilt | | | | | | | | | |
| 3-1 | Distribution Reservoir | Ground Reservoir | 13,700 m ³ | L.S. | | 1 | 70,418,000 | Rebuilt | | 70,418,000 |
| | | Implant Piping | | L.S. | | 1 | 23,410,000 | | | 23,410,000 |
| | | Earth Work | | L.S. | | 1 | 16,764,000 | | | 16,764,000 |
| | | Road Work | | L.S. | | 1 | 3,735,000 | | | 3,735,000 |
| | | Lighting | | L.S. | | 1 | 489,000 | | | 489,000 |
| | | Demolition Cost | | L.S. | | 1 | 8,000,000 | | | 8,000,000 |
| | Sub Total | | | | | | 122,816,000 | ¥325,462,400 | 0 | 122,816,000 |
| 4 | Distribution Pipe | | | | | | | | | |
| 4-1 | Distribution Pipes | | DIP1100mmD | m | 39,813 | 370 | 14,730,755 | near Battali Hill Reservoir | | 14,730,755 |
| | | | DIP1100mmD | m | 26,542 | 80 | 2,123,352 | | | 2,123,352 |
| | | | DIP1000mmD | m | 23,472 | 0 | 0 | | | 0 |
| | | | DIP900mmD | m | 19,825 | 0 | 0 | | | 0 |
| | | | DIP800mmD | m | 16,587 | 4,785 | 79,368,317 | | | 79,368,317 |
| | | | DIP700mmD | m | 13,651 | 2,595 | 35,424,345 | | | 35,424,345 |
| | | | DIP600mmD | m | 11,570 | 0 | 0 | | | 0 |
| | | | DIP500mmD | m | 9,085 | 2,005 | 18,215,225 | | | 18,215,225 |
| | | | DIP450mmD | m | 7,951 | 1,810 | 14,355,110 | | | 14,355,110 |
| | | | DIP400mmD | m | 6,918 | 600 | 4,150,740 | | | 4,150,740 |
| | | | DIP350mmD | m | 6,076 | 4,065 | 24,700,566 | | | 24,700,566 |
| | | | DIP300mmD | m | 5,235 | 3,485 | 18,243,627 | | | 18,243,627 |
| | | | PVC250mmD | m | 6,477 | 270 | 1,748,736 | | | 1,748,736 |
| | | | PVC200mmD | m | 4,629 | 1,750 | 8,101,408 | | | 8,101,408 |
| | Sub Total | | | | | 21,815 | 221,162,179 | ¥586,079,775 | 0 | 221,162,179 |
| | Total (Direct Construction Cost) | | | | | | 1,172,306,966 | ¥3,106,613,461 | 206,278,000 | 966,028,966 |
| 5 | Overhead & Profit etc. | 25% of Direct Construction Cost | | L.S. | | 1 | 293,076,742 | | 51,569,500 | 241,507,242 |
| | Grand Total | | | | | | 1,465,383,708 | ¥3,106,613,461 | 257,847,500 | 1,207,536,208 |

Case III-a-1 Nasirabad Reservoir and New Battali Reservoir

Unit: Taka

| No. | Name of Facility | Item | Dimension | Unit | Unit Cost | Quantity | Price | Note | E&M | Civil |
|-----|----------------------------------|---------------------------------|--------------------------------------|------|-----------|----------|---------------|-------------------------------------|-------------|-------------|
| 1 | Mohara WTP | | | | | | | | | |
| 1-1 | Clear Water Reservoir | Civil Work | 17,280 m ³ | L.S. | | 1 | 88,820,000 | | | 88,820,000 |
| | | Mechanical & Electrical Cost | | L.S. | | 1 | 9,391,000 | | 9,391,000 | |
| 1-2 | Distribution Pump House | Civil Work | | L.S. | | 1 | 18,036,000 | | | 18,036,000 |
| 1-3 | Inplant Piping | | DIP1200mmTP | m | 25,810 | 200 | 5,162,000 | Connection Pipe of Clearwell to LPS | | 5,162,000 |
| 1-4 | Distribution Pump | Mechanical & Electrical Cost | 18.m ³ /min ×61.m ×2 | L.S. | | 1 | 75,310,000 | 1 Pump Flow Control | 75,310,000 | |
| 1-5 | Distribution Pump | Mechanical & Electrical Cost | 30.m ³ /min ×61.m ×2 (+1) | L.S. | | 1 | 111,238,667 | 1 Pump Flow Control | 111,238,667 | |
| 1-5 | Pump Control Facilities | Mechanical & Electrical Cost | | L.S. | | 1 | 15,000,000 | | 15,000,000 | |
| 1-6 | Power Receiving Facility | Mechanical & Electrical Cost | 4,000 KVA | L.S. | | 1 | 25,728,000 | | 25,728,000 | |
| 1-7 | Generator | Mechanical & Electrical Cost | 2,000 KVA ×2 | L.S. | | 1 | 106,144,000 | | 106,144,000 | |
| | Sub Total | | | | | | 454,999,667 | ¥1,205,749,117 | 342,981,667 | 112,018,000 |
| 2 | Distribution Pipe | | | | | | | | | |
| 2-1 | Distribution Pipes | | DIP1400mmD | m | 40,800 | 0 | 0 | | | 0 |
| | | | DIP1200mmD | m | 31,495 | 12,140 | 382,351,728 | | | 382,351,728 |
| | | | DIP1100mmD | m | 26,542 | 1,910 | 50,695,029 | | | 50,695,029 |
| | | | DIP1000mmD | m | 23,472 | 1,980 | 46,474,164 | | | 46,474,164 |
| | | | DIP900mmD | m | 19,825 | 1,820 | 36,082,046 | | | 36,082,046 |
| | | | DIP800mmD | m | 16,587 | 1,700 | 28,197,730 | | | 28,197,730 |
| | | | DIP700mmD | m | 13,651 | 0 | 0 | | | 0 |
| | | | DIP600mmD | m | 11,570 | 0 | 0 | | | 0 |
| | | | DIP500mmD | m | 9,085 | 2,480 | 22,530,552 | | | 22,530,552 |
| | | | DIP450mmD | m | 7,931 | 825 | 6,543,075 | | | 6,543,075 |
| | | | DIP400mmD | m | 6,918 | 0 | 0 | | | 0 |
| | | | DIP350mmD | m | 6,076 | 420 | 2,552,088 | | | 2,552,088 |
| | | | DIP300mmD | m | 5,235 | 735 | 3,847,652 | | | 3,847,652 |
| | | | PVC250mmD | m | 6,477 | 430 | 2,785,024 | | | 2,785,024 |
| | | | PVC200mmD | m | 4,629 | 960 | 4,444,201 | | | 4,444,201 |
| | Sub Total | | | | | 25,400 | 586,503,289 | ¥1,554,233,715 | 0 | 586,503,289 |
| | Total (Direct Construction Cost) | | | | | | 1,041,502,955 | ¥2,759,982,832 | 342,981,667 | 698,521,289 |
| 5 | Overhead & Profit etc. | 25% of Direct Construction Cost | | L.S. | | 1 | 260,375,739 | | 85,745,417 | 174,630,322 |
| | Grand Total | | | | | | 1,301,878,694 | ¥2,759,982,832 | 428,727,083 | 873,151,611 |

Case III - a - 2 New Battali Reservoir

Unit : Taka

| No. | Name of Facility | Item | Dimension | Unit | Unit Cost | Quantity | Price | Note | E&M | Civil |
|--------------------------|----------------------------------|-----------------------------------|-------------------------|------|-----------|----------|---------------|-------------------------------------|-------------|---------------|
| 1 Mohara WTP | | | | | | | | | | |
| 1-1 | Clear Well | Civil Work | 20,000 m3 | L.S. | | 1 | 102,800,000 | | | 102,800,000 |
| | | Mechanical & Electrical Cost | | L.S. | | 1 | 9,561,000 | | 9,561,000 | |
| 1-2 | Distribution Pump House | Civil Work | | L.S. | | 1 | 12,147,000 | | | 12,147,000 |
| 1-3 | Inplant Piping | | DIP1200mmTP | m | 25,810 | 200 | 5,162,000 | Connection Pipe of Clearwell to LPS | | 5,162,000 |
| 1-4 | Distribution Pump | Mechanical & Electrical Cos | 74.m3/min ×74.m ×4 (+1) | L.S. | | 1 | 138,011,000 | | 138,011,000 | |
| 1-5 | Pump Control Facilities | Mechanical & Electrical Cos | | L.S. | | 1 | 15,000,000 | | | 15,000,000 |
| 1-6 | Power Receiving Facility | Mechanical & Electrical Cos | 4,000 KVA | L.S. | | 1 | 25,728,000 | | | 25,728,000 |
| 1-7 | Generator | Mechanical & Electrical Cos | 2,000 KVA ×2 | L.S. | | 1 | 106,144,000 | | 106,144,000 | |
| 1-8 | Transmission Pipe | Reinstallation | DIP900mmT | m | 26,401 | 580 | 15,312,696 | | | 15,312,696 |
| | | Reinstallation ACP to DIP | DIP600mmT | m | 22,088 | 370 | 8,172,486 | | | 8,172,486 |
| | | Transmission Route Rehabilitation | | L.S. | | 1 | 4,200,000 | Stair & Retaining Wall | | 4,200,000 |
| | Sub Total | | | | | | 442,238,182 | ¥1,171,931,182 | 294,444,000 | 147,794,182 |
| 2 New Battali Reservoir | | | | | | | | | | |
| 2-1 | Distribution Reservoir | Ground Reservoir | 3,250 m3 | L.S. | | 1 | 31,006,000 | | | 31,006,000 |
| | | Inplant Piping | | L.S. | | 1 | 20,327,000 | | | 20,327,000 |
| | | Earth Work | | L.S. | | 1 | 16,331,000 | | | 16,331,000 |
| | | Road Work | | L.S. | | 1 | 3,638,000 | | | 3,638,000 |
| | | Lighting | | L.S. | | 1 | 477,000 | | | 477,000 |
| | | Retaining Wall | | L.S. | | 1 | 11,100,000 | | | 11,100,000 |
| | Sub Total | | | | | | 82,879,000 | ¥219,629,350 | 0 | 82,879,000 |
| 3 Distribution Pipe | | | | | | | | | | |
| 3-1 | Distribution Pipes | | DIP1200mmD | m | 31,495 | 15,580 | 490,695,216 | | | 490,695,216 |
| | | | DIP1200mmD | m | 47,243 | 580 | 27,400,824 | near Battali Hill Reservoir | | 27,400,824 |
| | | | DIP1100mmD | m | 26,542 | 0 | 0 | | | 0 |
| | | | DIP1000mmD | m | 35,208 | 370 | 13,026,849 | near Battali Hill Reservoir | | 13,026,849 |
| | | | DIP1000mmD | m | 23,472 | 80 | 1,877,744 | | | 1,877,744 |
| | | | DIP900mmD | m | 19,825 | 0 | 0 | | | 0 |
| | | | DIP800mmD | m | 16,587 | 3,410 | 56,561,329 | | | 56,561,329 |
| | | | DIP700mmD | m | 13,651 | 1,700 | 23,206,700 | | | 23,206,700 |
| | | | DIP600mmD | m | 11,570 | 1,375 | 15,908,475 | | | 15,908,475 |
| | | | DIP500mmD | m | 9,085 | 1,990 | 18,078,951 | | | 18,078,951 |
| | | | DIP450mmD | m | 7,931 | 715 | 5,670,665 | | | 5,670,665 |
| | | | DIP400mmD | m | 6,918 | 600 | 4,150,740 | | | 4,150,740 |
| | | | DIP350mmD | m | 6,076 | 420 | 2,552,088 | | | 2,552,088 |
| | | | DIP300mmD | m | 5,235 | 1,090 | 5,706,041 | | | 5,706,041 |
| | | | PVC250mmD | m | 6,477 | 700 | 4,533,760 | | | 4,533,760 |
| | | | PVC200mmD | m | 4,629 | 905 | 4,189,585 | | | 4,189,585 |
| | Sub Total | | | | | 29,515 | 673,558,967 | ¥1,784,931,264 | 0 | 673,558,967 |
| | Total (Direct Construction Cost) | | | | | | 1,198,676,149 | ¥3,176,491,796 | 294,444,000 | 904,232,149 |
| 5 Overhead & Profit etc. | | | | | | | | | | |
| | | 25% of Direct Construction Cost | | L.S. | | 1 | 299,669,037 | | 73,611,000 | 226,058,037 |
| | Grand Total | | | | | | 1,498,345,187 | ¥3,176,491,796 | 368,055,000 | 1,130,290,187 |

Case III - a - 3 New Battali Reservoir

Unit : Taka

| No. | Name of Facility | Item | Dimension | Unit | Unit Cost | Quantity | Price | Note | E&M | Civil |
|-----|----------------------------------|-----------------------------------|-------------------------|------|-----------|----------|---------------|--|-------------|---------------|
| 1 | Mohara WTP | | | | | | | | | |
| 1-1 | Clear Well | Civil Work | 20,000 m3 | L.S. | | 1 | 102,800,000 | | | 102,800,000 |
| | | Mechanical & Electrical Cost | | L.S. | | 1 | 9,561,000 | | 9,561,000 | |
| 1-2 | Transmission Pump House | Civil Work | | L.S. | | 1 | 12,147,000 | | | 12,147,000 |
| 1-3 | Inplant Piping | | DIP1200mmTP | m | 25,810 | 100 | 2,581,000 | Connection Pipe of Clearwell to LPS | | 2,581,000 |
| | | | DIP1100mmTP | m | 22,320 | 100 | 2,232,000 | Connection Pipe of LPS to Distri. Pipe | | 2,232,000 |
| 1-4 | Transmission Pump | Mechanical & Electrical Cost | 24.m3/min x87.m x4 (+1) | L.S. | | 1 | 143,709,000 | | 143,709,000 | |
| 1-5 | Pump Control Facilities | Mechanical & Electrical Cost | | L.S. | | 1 | 15,000,000 | | 15,000,000 | |
| 1-6 | Power Receiving Facility | Mechanical & Electrical Cost | 5,000 KVA | L.S. | | 1 | 32,160,000 | | 32,160,000 | |
| 1-7 | Generator | Mechanical & Electrical Cost | 2,500 KVA x2 | L.S. | | 1 | 132,680,000 | | 132,680,000 | |
| 1-8 | Transmission Pipe | | DIP1100mmT | m | 25,335 | 15,580 | 394,726,311 | | | 394,726,311 |
| | | | DIP1100mmT | m | 38,003 | 580 | 22,041,842 | near Battali Hill Reservoir | | 22,041,842 |
| | | Reinstallation | DIP900mmT | m | 26,401 | 580 | 15,312,696 | | | 15,312,696 |
| | | Reinstallation ACP to DIP | DIP600mmT | m | 22,088 | 370 | 8,172,486 | | | 8,172,486 |
| | | Transmission Route Rehabilitation | | L.S. | | 1 | 4,200,000 | Stair & Retaining Wall | | 4,200,000 |
| | Sub Total | | | | | | 897,323,335 | ¥2,377,906,836 | 333,110,000 | 564,213,335 |
| 2 | New Battali Reservoir | | | | | | | | | |
| 2-1 | Distribution Reservoir | Ground Reservoir | 4,550 m3 | L.S. | | 1 | 44,973,000 | | | 44,973,000 |
| | | Inplant Piping | | L.S. | | 1 | 24,051,000 | | | 24,051,000 |
| | | Earth Work | | L.S. | | 1 | 19,323,000 | | | 19,323,000 |
| | | Road Work | | L.S. | | 1 | 4,305,000 | | | 4,305,000 |
| | | Lighting | | L.S. | | 1 | 564,000 | | | 564,000 |
| | | Retaining Wall | | L.S. | | 1 | 11,100,000 | | | 11,100,000 |
| | Sub Total | | | | | | 104,316,000 | ¥276,437,400 | 0 | 104,316,000 |
| 3 | Distribution Pipe | | | | | | | | | |
| 3-1 | Distribution Pipes | | DIP1200mmD | m | 47,243 | 370 | 17,479,836 | near Battali Hill Reservoir | | 17,479,836 |
| 3-1 | Distribution Pipes | | DIP1200mmD | m | 31,495 | 80 | 2,519,616 | | | 2,519,616 |
| | | | DIP1000mmD | m | 23,472 | 0 | 0 | | | 0 |
| | | | DIP900mmD | m | 19,825 | 2,500 | 49,563,250 | | | 49,563,250 |
| | | | DIP800mmD | m | 16,587 | 2,285 | 37,901,067 | | | 37,901,067 |
| | | | DIP700mmD | m | 13,651 | 2,595 | 35,424,345 | | | 35,424,345 |
| | | | DIP600mmD | m | 11,570 | 0 | 0 | | | 0 |
| | | | DIP500mmD | m | 9,085 | 2,005 | 18,215,225 | | | 18,215,225 |
| | | | DIP450mmD | m | 7,931 | 1,810 | 14,355,110 | | | 14,355,110 |
| | | | DIP400mmD | m | 6,918 | 600 | 4,150,740 | | | 4,150,740 |
| | | | DIP350mmD | m | 6,076 | 4,065 | 24,700,566 | | | 24,700,566 |
| | | | DIP300mmD | m | 5,235 | 3,485 | 18,243,627 | | | 18,243,627 |
| | | | PVC250mmD | m | 6,477 | 270 | 1,748,736 | | | 1,748,736 |
| | | | PVC200mmD | m | 4,629 | 1,750 | 8,101,408 | | | 8,101,408 |
| | Sub Total | | | | | 21,815 | 232,403,525 | ¥615,869,341 | 0 | 232,403,525 |
| | Total (Direct Construction Cost) | | | | | | 1,234,042,859 | ¥3,270,213,577 | 333,110,000 | 900,932,859 |
| 5 | Overhead & Profit etc. | 25% of Direct Construction Cost | | L.S. | | 1 | 308,510,715 | | 83,277,500 | 225,233,215 |
| | Grand Total | | | | | | 1,542,553,574 | ¥3,270,213,577 | 416,387,500 | 1,126,166,074 |

Case III-b Nasirabad Reservoir and New Battali Reservoir

Unit: Taka

| No. | Name of Facility | Item | Dimension | Unit | Unit Cost | Quantity | Price | Note | E&M | Civil |
|-----|----------------------------------|-----------------------------------|---------------------------------------|------|-----------|----------|---------------|-----------------------------------|-------------|---------------|
| 1 | Mohara WTP | | | | | | | | | |
| 1-1 | Clear Well | Civil Work | 6,716 m ³ | L.S. | | 1 | 53,290,000 | | | 53,290,000 |
| | | Mechanical & Electrical Cost | | L.S. | | 1 | 9,561,000 | | 9,561,000 | |
| 1-2 | Transmission Pump House | Civil Work | | L.S. | | 1 | 12,147,000 | | | 12,147,000 |
| 1-3 | Distribution Pump | Mechanical & Electrical Cost | 15.8m ³ /min ×46 m ×4 (+1) | L.S. | | 1 | 84,911,000 | | 84,911,000 | |
| 1-4 | Power Receiving Facility | Mechanical & Electrical Cost | 2,000 KVA | L.S. | | 1 | 12,864,000 | | 12,864,000 | |
| 1-5 | Generator | Mechanical & Electrical Cost | 1000 KVA ×2 | L.S. | | 1 | 53,072,000 | | 53,072,000 | |
| 1-6 | Transmission Pipe | | | | | | | | | |
| | | | DIP1000mmT | m | 22,405 | 4,325 | 96,901,193 | Nasirabad Re. to Battali Hill Re. | | 96,901,193 |
| | | | DIP1000mmT | m | 33,607 | 580 | 19,492,263 | near Battali Hill Reservoir | | 19,492,263 |
| | | Reinstallation | DIP900mmT | m | 26,401 | 580 | 15,312,696 | near Battali Hill Reservoir | | 15,312,696 |
| | | Reinstallation ACP to DIP | DIP600mmT | m | 22,088 | 370 | 8,172,486 | near Battali Hill Reservoir | | 8,172,486 |
| | | Transmission Route Rehabilitation | | L.S. | | 1 | 4,200,000 | Stair & Retaining Wall | | 4,200,000 |
| | Sub Total | | | | | | 369,923,638 | ¥980,297,639 | 160,408,000 | 209,515,638 |
| 2 | Nasirabad Reservoir | | | | | | | | | |
| 2-1 | Distribution Reservoir | Ground Reservoir | 16,800 m ³ | L.S. | | 1 | 86,352,000 | | | 86,352,000 |
| | | Lift Pump | 23.4m ³ /min ×51m ×3 (+1) | L.S. | | 1 | 109,084,000 | to Battali Hill New Reservoir | 109,084,000 | |
| | | Pump House | | L.S. | | 1 | 10,302,000 | | | 10,302,000 |
| | | Power Receiving Facility | 2,000 KVA | L.S. | | 1 | 12,864,000 | | 12,864,000 | |
| | | Generator | 1000 KVA ×2 | L.S. | | 1 | 53,072,000 | | 53,072,000 | |
| | | Administration Building | | L.S. | | 1 | 1,779,000 | | | 1,779,000 |
| | | Implant Piping | | L.S. | | 15 | 30,160,000 | | | 30,160,000 |
| | | Earth Work | | L.S. | | 1 | 18,565,000 | | | 18,565,000 |
| | | Road Work | | L.S. | | 1 | 8,272,000 | | | 8,272,000 |
| | | Lighting | | L.S. | | 1 | 1,084,000 | | | 1,084,000 |
| | Sub Total | | | | | | 331,534,000 | ¥878,565,100 | 175,020,000 | 156,514,000 |
| 3 | New Ballali Reservoir | | | | | | | | | |
| 3-1 | Distribution Reservoir | Ground Reservoir | 3,250 m ³ | L.S. | | 1 | 31,006,000 | | | 31,006,000 |
| | | Implant Piping | | L.S. | | 1 | 20,327,000 | | | 20,327,000 |
| | | Earth Work | | L.S. | | 1 | 16,331,000 | | | 16,331,000 |
| | | Road Work | | L.S. | | 1 | 3,638,000 | | | 3,638,000 |
| | | Lighting | | L.S. | | 1 | 477,000 | | | 477,000 |
| | | Retaining Wall | | L.S. | | 1 | 11,100,000 | | | 11,100,000 |
| | Sub Total | | | | | | 82,879,000 | ¥219,629,350 | 0 | 82,879,000 |
| 4 | Distribution Pipe | | | | | | | | | |
| 4-1 | Distribution Pipes | | | | | | | | | |
| | | | DIP1000mmD | m | 35,208 | 370 | 13,026,849 | near Battali Hill Reservoir | | 13,026,849 |
| | | | DIP1000mmD | m | 23,472 | 13,705 | 321,681,019 | | | 321,681,019 |
| | | | DIP900mmD | m | 19,825 | 3,535 | 70,082,436 | | | 70,082,436 |
| | | | DIP800mmD | m | 16,587 | 3,410 | 56,561,329 | | | 56,561,329 |
| | | | DIP700mmD | m | 13,651 | 1,000 | 13,651,000 | | | 13,651,000 |
| | | | DIP600mmD | m | 11,570 | 2,075 | 24,007,335 | | | 24,007,335 |
| | | | DIP500mmD | m | 9,085 | 1,990 | 18,078,951 | | | 18,078,951 |
| | | | DIP450mmD | m | 7,931 | 715 | 5,670,665 | | | 5,670,665 |
| | | | DIP400mmD | m | 6,918 | 600 | 4,150,740 | | | 4,150,740 |
| | | | DIP350mmD | m | 6,076 | 435 | 2,643,234 | | | 2,643,234 |
| | | | DIP300mmD | m | 5,235 | 1,045 | 3,470,471 | | | 3,470,471 |
| | | | PVC250mmD | m | 6,477 | 700 | 4,533,760 | | | 4,533,760 |
| | | | PVC200mmD | m | 4,629 | 920 | 4,259,026 | | | 4,259,026 |
| | Sub Total | | | | | 30,500 | 543,816,814 | ¥1,441,114,557 | 0 | 543,816,814 |
| | Total (Direct Construction Cost) | | | | | | 1,328,153,452 | ¥3,519,606,647 | 335,428,000 | 992,725,452 |
| 5 | Overhead & Profit etc. | 25% of Direct Construction Cost | | L.S. | | 1 | 332,038,363 | | 83,857,000 | 248,181,363 |
| | Grand Total | | | | | | 1,660,191,814 | ¥3,519,606,647 | 419,285,000 | 1,240,906,814 |

Electrical Cost of Alternatives

| Alternative No. | Item | Pump Capacity | Pump Capacity | | | | | | | Electrical charge | | | Maintenance Cost (1%) | | Total | |
|-----------------|-------------------|-------------------|---------------|----------|---------------|--------|----------|---------------------|----------------------------|-------------------|--------|------|-----------------------|------------|-------------|-----------|
| | | | Q (m3/min) | H (m) | Power (kw) | Pieces | Stand-by | Total Power (kw) | Operation Hours (hours) | kWh/day | Cost | | M&E Cost (Taka) | Taka/year | Taka/year | |
| 1 | Case I -a | Transmission Pump | Mohara | 15.8 | 84.0 | 360 | 4 | 1 | 1,440 | 24 | 34,560 | | | | | |
| | Lift Pump | Khulushi | | 13.1 | 25.0 | 100 | 3 | 1 | 300 | 16 | 4,800 | | | | | |
| | Total | | | | | | | | 1,740 | | 39,360 | 2.95 | 116,112 | 42,380,880 | 374,891,250 | 3,748,913 |
| 2 | Case I -b-1 | Transmission Pump | Mohara | 15.8 | 80.0 | 340 | 4 | 1 | 1,360 | 24 | 32,640 | | | | | |
| | Lift Pump | Nasirabad | | 7.8 | 23.0 | 60 | 3 | 1 | 180 | 16 | 2,880 | | | | | |
| | Total | | | | | | | | 1,540 | | 35,520 | 2.95 | 104,784 | 38,246,160 | 355,168,750 | 3,551,688 |
| 3 | Case I -b-2 | Transmission Pump | Mohara | 15.8 | 80.0 | 340 | 4 | 1 | 1,360 | 24 | 32,640 | | | | | |
| | Lift Pump | Nasirabad | | - | - | - | - | - | 0 | 16 | 0 | | | | | |
| | Total | | | | | | | | 1,360 | | 32,640 | 2.95 | 96,288 | 35,145,120 | 257,467,500 | 2,574,675 |
| 5 | Case I -b-3 | Transmission Pump | Mohara | 15.8 | 63.0 | 270 | 4 | 1 | 1,080 | 24 | 25,920 | | | | | |
| | Lift Pump | Nasirabad | | 31.2 | 31.0 | 280 | 3 | 1 | 840 | 16 | 13,440 | | | | | |
| | Total | | | | | | | | 1,920 | | 39,360 | 2.95 | 116,112 | 42,380,880 | 471,007,500 | 4,710,075 |
| 6 | Case I -c-1 | Transmission Pump | Mohara | 15.8 | 37.0 | 160 | 4 | 1 | 640 | 24 | 15,360 | | | | | |
| | Lift Pump | Nasirabad | | 7.8 | 35.0 | 80 | 3 | 1 | 240 | 16 | 3,840 | | | | | |
| | Lift Pump | Nasirabad | | 23.4 | 51.0 | 340 | 3 | 1 | 1,020 | 16 | 16,320 | | | | | |
| | Total | | | | | | | | 1,900 | | 35,520 | 2.95 | 104,784 | 38,246,160 | 503,608,750 | 5,036,088 |
| 1 | Case I -c-2 | Transmission Pump | Mohara | 15.8 | 80.0 | 340 | 4 | 1 | 1,360 | 24 | 32,640 | | | | | |
| | Lift Pump | New Battali | | - | - | - | - | - | 0 | 16 | 0 | | | | | |
| | Total | | | | | | | | 1,360 | | 32,640 | 2.95 | 96,288 | 35,145,120 | 257,467,500 | 2,574,675 |
| 7 | Case II -b | Transmission Pump | Mohara | 15.8 | 81.0 | 350 | 4 | 1 | 1,400 | 24 | 33,600 | | | | | |
| | Lift Pump | New Battali | | - | - | - | - | - | 0 | 16 | 0 | | | | | |
| | Total | | | | | | | | 1,400 | | 33,600 | 2.95 | 99,120 | 36,178,800 | 257,847,500 | 2,578,475 |
| 8 | Case III -a-1 | Distribution Pump | Mohara | 18.0 | 61.0 | 300 | 2 | 0 | 600 | 18 | 10,800 | | | | | |
| | Distribution Pump | Mohara | | 30.0 | 61.0 | 500 | 2 | 1 | 1,000 | 18 | 18,000 | | | | | |
| | Total | | | | | | | | 1,600 | | 28,800 | 2.95 | 84,960 | 31,010,400 | 428,727,083 | 4,287,271 |
| 9 | Case III -a-2 | Distribution Pump | Mohara | 24.0 | 74.0 | 480 | 4 | 1 | 1,920 | 16 | 30,720 | | | | | |
| | Total | | | | | | | | 1,920 | | 30,720 | 2.95 | 90,624 | 33,077,760 | 368,055,000 | 3,680,550 |
| 10 | Case III -a-3 | Distribution Pump | Mohara | 24.0 | 87.0 | 560 | 4 | 1 | 2,240 | 16 | 35,840 | | | | | |
| | Total | | | | | | | | 2,240 | | 35,840 | 2.95 | 105,728 | 38,590,720 | 416,387,500 | 4,163,875 |
| 11 | Case III -b | Transmission Pump | Mohara | 15.8 | 46.0 | 200 | 4 | 1 | 800 | 24 | 19,200 | | | | | |
| | Lift Pump | Nasirabad | | 23.4 | 51.0 | 340 | 3 | 1 | 1,020 | 16 | 16,320 | | | | | |
| | Total | | | | | | | | 1,820 | | 35,520 | 2.95 | 104,784 | 38,246,160 | 419,285,000 | 4,192,850 |

7.4-1-25

| | | | |
|-------------------|---------------|-----------------------|-----------|
| Pump Efficiency | 70 % | | |
| Operation Hours | 24 Hours | for Transmission Pump | |
| | 16 Hours | for Lift Pump | (=24/1.5) |
| Power Supply Cost | 2.95 Taka/kwh | | |




FIGURE 7.4-1-1 LAYOUT PLAN OF PROPOSED KHULSHI RESERVOIR (Alternative Case I-a)




FIGURE 7.4-1-2 LAYOUT PLAN OF PROPOSED NASIRABAD RESERVOIR (Alternative Case I-b-1)




FIGURE 7.4-1-4 LAYOUT PLAN OF PROPOSED NASIRABAD RESERVOIR (Alternative Case I-b-2)





FIGURE 7.4-1-6 LAYOUT PLAN OF PROPOSED NASIRABAD RESERVOIR (Alternative Case I-c-1)






Approx. Construction Limit Line :
150 ft Contour Line + 20m Distance

Approx. Construction Limit Line :
Slope foot + 6m Distance

FIGURE 7.4-1-8 FUTURE-2 LAYOUT OF BATTALI HILL RESERVOIR
(Alternative Case II-b)






FIGURE 7.4-1-10 FUTURE LAYOUT OF BATTAIL HILL RESERVOIR
(Alternative Case III-a-2 & III-b)

7.4-1-35




FIGURE 7.4-1-11 FUTURE LAYOUT OF BATTALI HILL RESERVOIR
(Alternative Case III-a-3)

7.4-1-36




FIGURE 7.4-1-12 LAYOUT PLAN OF PROPOSED NASIRABAD RESERVOIR (Alternative Case III-b)




FIGURE 7.4-2-1 PROPOSED FACILITIES OF KARNAPHULI WATER TREATMENT PLANT (2010)




Figure 7.4-2-2 LAYOUT PLAN OF PROPOSED SALIMPUR RESERVOIR (2010)




Figure 7.4-2-3 Proposed Transmission / Distribution Network (Basic Plan Phase 1, 2005)




Figure 7.4-2-4 Proposed Transmission / Distribution Network (Basic Plan Phase 2, 2010)

7.4-3 Hydraulic Analysis of Transmission / Distribution Network for Basic Plan

A dynamic hydraulic analysis of transmission / distribution network was conducted for extended period of 72 hours. Software used for the analysis was “Cybernet” version 3.5 by Haestad Methods Inc. USA. The software was developed based on research conducted by the U.S. Environmental protection Agency (EPA).

The analysis was carried out for 72 hours to verify capacities of pumps, reservoirs, and pipelines. Therefore, computation results presented herewith are only for peak time, i.e. 09:00 hours. However, computation results for reservoirs are presented for 72 hours for perusal.

Computation results presented herewith are;

1. Junction Report (for peak time of 09:00hrs)
2. Pipe Report (for peak time of 09:00hrs)
3. Detailed Report for Tank (Reservoir)

Pipes with number 2000 or more means pipes to be developed in Phase 1 by 2005. And pipes with number 3000 or more means pipes to be developed in Phase 2 by 2010.

Hourly water demand fluctuation to be applied in the analysis was assumed as presented in attached sheet with a peak rate of 1.5.

Relationship between Nodes and Wards are also presented herewith.

7.4-3-1 Hourly Fluctuation of Distribution Flow

| Peak hour | 1.7 | | 1.6 | | 1.5 (Adopted) | | 1.4 | | Peak hour | 1.7 | | 1.6 | | 1.5 (Adopted) | | 1.4 | |
|------------------------|-------|--------|------------|--------|---------------|--------------|------------|--------|--------------|--------------|--------|------------|--------|---------------|--------------|-------|--------|
| | Rate | Excess | Rate | Excess | Rate | Excess | Rate | Excess | | Rate | Excess | Rate | Excess | Rate | Excess | Rate | Excess |
| 0:00 | 0.35 | 0.000 | 0.44 | 0.000 | 0.54 | 0.000 | 0.63 | 0.000 | 12:00 | 1.35 | 0.350 | 1.30 | 0.300 | 1.25 | 0.250 | 1.20 | 0.200 |
| 0:15 | 0.34 | 0.000 | 0.43 | 0.000 | 0.53 | 0.000 | 0.62 | 0.000 | 12:15 | 1.33 | 0.325 | 1.28 | 0.279 | 1.23 | 0.232 | 1.19 | 0.186 |
| 0:30 | 0.33 | 0.000 | 0.42 | 0.000 | 0.52 | 0.000 | 0.61 | 0.000 | 12:30 | 1.30 | 0.300 | 1.26 | 0.257 | 1.21 | 0.214 | 1.17 | 0.171 |
| 0:45 | 0.31 | 0.000 | 0.41 | 0.000 | 0.51 | 0.000 | 0.61 | 0.000 | 12:45 | 1.28 | 0.275 | 1.24 | 0.236 | 1.20 | 0.196 | 1.16 | 0.157 |
| 1:00 | 0.30 | 0.000 | 0.40 | 0.000 | 0.50 | 0.000 | 0.60 | 0.000 | 13:00 | 1.25 | 0.250 | 1.21 | 0.214 | 1.18 | 0.179 | 1.14 | 0.143 |
| 1:15 | 0.29 | 0.000 | 0.39 | 0.000 | 0.49 | 0.000 | 0.59 | 0.000 | 13:15 | 1.23 | 0.225 | 1.19 | 0.193 | 1.16 | 0.161 | 1.13 | 0.129 |
| 1:30 | 0.28 | 0.000 | 0.38 | 0.000 | 0.48 | 0.000 | 0.59 | 0.000 | 13:30 | 1.20 | 0.200 | 1.17 | 0.171 | 1.14 | 0.143 | 1.11 | 0.114 |
| 1:45 | 0.26 | 0.000 | 0.37 | 0.000 | 0.47 | 0.000 | 0.58 | 0.000 | 13:45 | 1.18 | 0.175 | 1.15 | 0.150 | 1.13 | 0.125 | 1.10 | 0.100 |
| 2:00 | 0.25 | 0.000 | 0.36 | 0.000 | 0.46 | 0.000 | 0.57 | 0.000 | 14:00 | 1.15 | 0.150 | 1.13 | 0.129 | 1.11 | 0.107 | 1.09 | 0.086 |
| 2:15 | 0.24 | 0.000 | 0.35 | 0.000 | 0.46 | 0.000 | 0.56 | 0.000 | 14:15 | 1.14 | 0.138 | 1.12 | 0.118 | 1.10 | 0.098 | 1.08 | 0.079 |
| 2:30 | 0.23 | 0.000 | 0.34 | 0.000 | 0.45 | 0.000 | 0.56 | 0.000 | 14:30 | 1.13 | 0.125 | 1.11 | 0.107 | 1.09 | 0.089 | 1.07 | 0.071 |
| 2:45 | 0.21 | 0.000 | 0.32 | 0.000 | 0.44 | 0.000 | 0.55 | 0.000 | 14:45 | 1.11 | 0.113 | 1.10 | 0.096 | 1.08 | 0.080 | 1.06 | 0.064 |
| 3:00 | 0.20 | 0.000 | 0.31 | 0.000 | 0.43 | 0.000 | 0.54 | 0.000 | 15:00 | 1.10 | 0.100 | 1.09 | 0.086 | 1.07 | 0.071 | 1.06 | 0.057 |
| 3:15 | 0.19 | 0.000 | 0.30 | 0.000 | 0.42 | 0.000 | 0.54 | 0.000 | 15:15 | 1.13 | 0.125 | 1.11 | 0.107 | 1.09 | 0.089 | 1.07 | 0.071 |
| 3:30 | 0.18 | 0.000 | 0.29 | 0.000 | 0.41 | 0.000 | 0.53 | 0.000 | 15:30 | 1.15 | 0.150 | 1.13 | 0.129 | 1.11 | 0.107 | 1.09 | 0.086 |
| 3:45 | 0.16 | 0.000 | 0.28 | 0.000 | 0.40 | 0.000 | 0.52 | 0.000 | 15:45 | 1.18 | 0.175 | 1.15 | 0.150 | 1.13 | 0.125 | 1.10 | 0.100 |
| 4:00 | 0.15 | 0.000 | 0.27 | 0.000 | 0.39 | 0.000 | 0.51 | 0.000 | 16:00 | 1.20 | 0.200 | 1.17 | 0.171 | 1.14 | 0.143 | 1.11 | 0.114 |
| 4:15 | 0.19 | 0.000 | 0.30 | 0.000 | 0.42 | 0.000 | 0.54 | 0.000 | 16:15 | 1.25 | 0.250 | 1.21 | 0.214 | 1.18 | 0.179 | 1.14 | 0.143 |
| 4:30 | 0.23 | 0.000 | 0.34 | 0.000 | 0.45 | 0.000 | 0.56 | 0.000 | 16:30 | 1.30 | 0.300 | 1.26 | 0.257 | 1.21 | 0.214 | 1.17 | 0.171 |
| 4:45 | 0.26 | 0.000 | 0.37 | 0.000 | 0.47 | 0.000 | 0.58 | 0.000 | 16:45 | 1.35 | 0.350 | 1.30 | 0.300 | 1.25 | 0.250 | 1.20 | 0.200 |
| 5:00 | 0.30 | 0.000 | 0.40 | 0.000 | 0.50 | 0.000 | 0.60 | 0.000 | 17:00 | 1.40 | 0.400 | 1.34 | 0.343 | 1.29 | 0.286 | 1.23 | 0.229 |
| 5:15 | 0.46 | 0.000 | 0.54 | 0.000 | 0.62 | 0.000 | 0.69 | 0.000 | 17:15 | 1.44 | 0.438 | 1.38 | 0.375 | 1.31 | 0.313 | 1.25 | 0.250 |
| 5:30 | 0.63 | 0.000 | 0.68 | 0.000 | 0.73 | 0.000 | 0.79 | 0.000 | 17:30 | 1.48 | 0.475 | 1.41 | 0.407 | 1.34 | 0.339 | 1.27 | 0.271 |
| 5:45 | 0.79 | 0.000 | 0.82 | 0.000 | 0.85 | 0.000 | 0.88 | 0.000 | 17:45 | 1.51 | 0.513 | 1.44 | 0.439 | 1.37 | 0.366 | 1.29 | 0.293 |
| 6:00 | 0.95 | 0.000 | 0.96 | 0.000 | 0.96 | 0.000 | 0.97 | 0.000 | 18:00 | 1.55 | 0.550 | 1.47 | 0.471 | 1.39 | 0.393 | 1.31 | 0.314 |
| 6:15 | 1.04 | 0.038 | 1.03 | 0.032 | 1.03 | 0.027 | 1.02 | 0.021 | 18:15 | 1.54 | 0.538 | 1.46 | 0.461 | 1.38 | 0.384 | 1.31 | 0.307 |
| 6:30 | 1.13 | 0.125 | 1.11 | 0.107 | 1.09 | 0.089 | 1.07 | 0.071 | 18:30 | 1.53 | 0.525 | 1.45 | 0.450 | 1.38 | 0.375 | 1.30 | 0.300 |
| 6:45 | 1.21 | 0.213 | 1.18 | 0.182 | 1.15 | 0.152 | 1.12 | 0.121 | 18:45 | 1.51 | 0.513 | 1.44 | 0.439 | 1.37 | 0.366 | 1.29 | 0.293 |
| 7:00 | 1.30 | 0.300 | 1.26 | 0.257 | 1.21 | 0.214 | 1.17 | 0.171 | 19:00 | 1.50 | 0.500 | 1.43 | 0.429 | 1.36 | 0.357 | 1.29 | 0.286 |
| 7:15 | 1.38 | 0.375 | 1.32 | 0.321 | 1.27 | 0.268 | 1.21 | 0.214 | 19:15 | 1.44 | 0.438 | 1.38 | 0.375 | 1.31 | 0.313 | 1.25 | 0.250 |
| 7:30 | 1.45 | 0.450 | 1.39 | 0.386 | 1.32 | 0.321 | 1.26 | 0.257 | 19:30 | 1.38 | 0.375 | 1.32 | 0.321 | 1.27 | 0.268 | 1.21 | 0.214 |
| 7:45 | 1.53 | 0.525 | 1.45 | 0.450 | 1.38 | 0.375 | 1.30 | 0.300 | 19:45 | 1.31 | 0.313 | 1.27 | 0.268 | 1.22 | 0.223 | 1.18 | 0.179 |
| 8:00 | 1.60 | 0.600 | 1.51 | 0.514 | 1.43 | 0.429 | 1.34 | 0.343 | 20:00 | 1.25 | 0.250 | 1.21 | 0.214 | 1.18 | 0.179 | 1.14 | 0.143 |
| 8:15 | 1.63 | 0.625 | 1.54 | 0.536 | 1.45 | 0.446 | 1.36 | 0.357 | 20:15 | 1.16 | 0.163 | 1.14 | 0.139 | 1.12 | 0.116 | 1.09 | 0.093 |
| 8:30 | 1.65 | 0.650 | 1.56 | 0.557 | 1.46 | 0.464 | 1.37 | 0.371 | 20:30 | 1.08 | 0.075 | 1.06 | 0.064 | 1.05 | 0.054 | 1.04 | 0.043 |
| 8:45 | 1.68 | 0.675 | 1.58 | 0.579 | 1.48 | 0.482 | 1.39 | 0.386 | 20:45 | 0.99 | 0.000 | 0.99 | 0.000 | 0.99 | 0.000 | 0.99 | 0.000 |
| 9:00 | 1.70 | 0.700 | 1.60 | 0.600 | 1.50 | 0.500 | 1.40 | 0.400 | 21:00 | 0.90 | 0.000 | 0.91 | 0.000 | 0.93 | 0.000 | 0.94 | 0.000 |
| 9:15 | 1.69 | 0.688 | 1.59 | 0.589 | 1.49 | 0.491 | 1.39 | 0.393 | 21:15 | 0.83 | 0.000 | 0.85 | 0.000 | 0.87 | 0.000 | 0.90 | 0.000 |
| 9:30 | 1.68 | 0.675 | 1.58 | 0.579 | 1.48 | 0.482 | 1.39 | 0.386 | 21:30 | 0.75 | 0.000 | 0.79 | 0.000 | 0.82 | 0.000 | 0.86 | 0.000 |
| 9:45 | 1.66 | 0.663 | 1.57 | 0.568 | 1.47 | 0.473 | 1.38 | 0.379 | 21:45 | 0.68 | 0.000 | 0.72 | 0.000 | 0.77 | 0.000 | 0.81 | 0.000 |
| 10:00 | 1.65 | 0.650 | 1.56 | 0.557 | 1.46 | 0.464 | 1.37 | 0.371 | 22:00 | 0.60 | 0.000 | 0.66 | 0.000 | 0.71 | 0.000 | 0.77 | 0.000 |
| 10:15 | 1.63 | 0.625 | 1.54 | 0.536 | 1.45 | 0.446 | 1.36 | 0.357 | 22:15 | 0.56 | 0.000 | 0.62 | 0.000 | 0.69 | 0.000 | 0.75 | 0.000 |
| 10:30 | 1.60 | 0.600 | 1.51 | 0.514 | 1.43 | 0.429 | 1.34 | 0.343 | 22:30 | 0.53 | 0.000 | 0.59 | 0.000 | 0.66 | 0.000 | 0.73 | 0.000 |
| 10:45 | 1.58 | 0.575 | 1.49 | 0.493 | 1.41 | 0.411 | 1.33 | 0.329 | 22:45 | 0.49 | 0.000 | 0.56 | 0.000 | 0.63 | 0.000 | 0.71 | 0.000 |
| 11:00 | 1.55 | 0.550 | 1.47 | 0.471 | 1.39 | 0.393 | 1.31 | 0.314 | 23:00 | 0.45 | 0.000 | 0.53 | 0.000 | 0.61 | 0.000 | 0.69 | 0.000 |
| 11:15 | 1.50 | 0.500 | 1.43 | 0.429 | 1.36 | 0.357 | 1.29 | 0.286 | 23:15 | 0.43 | 0.000 | 0.51 | 0.000 | 0.59 | 0.000 | 0.67 | 0.000 |
| 11:30 | 1.45 | 0.450 | 1.39 | 0.386 | 1.32 | 0.321 | 1.26 | 0.257 | 23:30 | 0.40 | 0.000 | 0.49 | 0.000 | 0.57 | 0.000 | 0.66 | 0.000 |
| 11:45 | 1.40 | 0.400 | 1.34 | 0.343 | 1.29 | 0.286 | 1.23 | 0.229 | 23:45 | 0.38 | 0.000 | 0.46 | 0.000 | 0.55 | 0.000 | 0.64 | 0.000 |
| Total | 96.00 | | 21.99 | | 96.00 | | 18.85 | | 96.00 | 15.71 | | 96.00 | | 15.71 | | 96.00 | |
| Peak | 1.70 | | | | 1.60 | | 1.50 | | 1.50 | | | 1.40 | | 1.40 | | 1.40 | |
| Min. Required Capacity | | | 5.50 hours | | 4.71 hours | | 3.93 hours | | | | | 3.14 hours | | | | | |

