PROJECT: SIHANOUKVILLE CCGT Tabke 2.3-8 (1) CALCULATED DISCHARGE SEPTEMBER 2000

LOCATION: PREY TRENG (POND)

DATE		DISCHAR	GE AT TIN	IE (CMS.)	MASSIF	REMARK			
DATE	6:00	9:00	12:00	15:00	18:00	RAIN	NO RAIN	TIME	
16/09/00	0.117	0.342	0.657	0.938	0.790	1		9:40 - 12:00	
17/09/00	0.538	0.511	0.484	0.458	0.458			MKVacakatraal	
18/09/00	0.433	0.409	0.409	0.409	0.386				
19/09/00	0.386	0.386	0.386	0.364	0.364				
20/09/00	0.346	0.342	0.333	0.333	0.321			***************************************	
21/09/00	0.301	0.301	0.293	0.285	0.301	/		15:00 - 18:00	
22/09/00	0.342	0.333	0.321	0.433	0.790	/		12:40 - 14:30	
23/09/00	0.722	0.657	0.626	0.722	0.938	/		12:00 - 20:00	
24/09/00	1.263	1.235	1.146	1.102	0.938				
25/09/00	0.722	0.657	0.596	0.538	0.538				
26/09/00	0.527	0.484	0.484	0.196	0.117	/		18:00 - 20:00	
27/09/00	0.626	0.596	0.538	0.567	0.626	/		12:00 - 14:00	
28/09/00	0.584	0.567	0.538	0.511	0.484				
29/09/00	0.458	0.443	0.433	0.409	0.386				
30/09/00	0.386	0.364	0.342	0.474	0.484	/		12:00 - 15:00	

PROJECT: SIHANOUKVILLE CCGT Table 2.3-8 (2) CALCULATED DISCHARGE OCTOBER 2000

LOCATION: PREY TRENG (POND)

DATE		DISCHAR	GE AT TIM	IE (CMS.)	HINNOR.	A RESE	REMAR	2K
DATE	6:00	9:00	12:00	15:00	18:00	RAIN	NO RAIN	TIME
01/10/00	0.386	0.474	0.474	0.657	0.644	/		11:00 - 14:00
02/10/00	0.584	0.550	0.511	0.484	0.484			
03/10/00	0.458	0.433	0.433	0.424	0.395	1		18:00 - 19:00
04/10/00	0.474	0.458	0.438	0.414	0.409	/		18:00 - 19:00
05/10/00	0.538	0.511	0.500	0.484	0.458	/		18:00 - 24:00
06/10/00	1.172	1.002	0.923	0.848	0.826			
07/10/00	0.755	0.722	0.708	0.689	0.657			
08/10/00	0.626	0.608	0.584	0.608	0.567	/		12:00 - 14:00
09/10/00	0.538	0.538	1.190	3.029	2.724	/		8:00 - 10:00
10/10/00	1.583	1.478	1.282	1.282	1.691	/		12:00 - 15:00
11/10/00	1.478	1.691	1.922	1.805	1.691	/		8:00 - 12:00
12/10/00	1.190	1.018	1.018	1.018	1.018	/		18:00 - 22:00
13/10/00	3.524	3.354	3.029	2.438	2.874			
14/10/00	1.691	1.583	1.478	1.478	1.583			
15/10/00	2.069	1.958	1.805	1.583	1.478			
16/10/00	1.691	1.583	1.478	1.190	1.102			
17/10/00	0.938	0.900	0.862	0.862	0.826			
18/10/00	0.790	0.790	0.790	0.722	1.018	/		15:00 - 18:00
19/10/00	0.790	0.755	0.722	0.689	0.657			
20/10/00	0.657	0.657	0.626	0.596	0.538			
21/10/00	0.484	0.484	0.484	0.458	0.433			
22/10/00	0.433	0.433	0.409	0.409	0.386			
23/10/00	0.368	0.368	0.386	0.458	0.567	/		12:00 - 20:00
24/10/00	0.364	0.364	0.433	0.458	0.458			
25/10/00	0.433	0.409	0.409	0.409	0.409			
26/10/00	0.342	0.342	0.342	0.342	0.342			-
27/10/00	0.321	0.321	0.301	0.301	0.293		1	
28/10/00	0.282	0.282	0.274	0.263	0.364			
29/10/00	0.351	0.342	0.342	0.364	0.386	7		12:00 - 14:00
30/10/00	0.301	0.301	0.321	0.342	0.377	7	 	12:00 - 15:00
31/10/00	0.433	0.433	0.424	0.409	0.386		1	

PROJECT: SIHANOUKVILLE CCGT Table 2.3-8 (3) CALCULATED DISCHARGE NOVEMBER 2000

LOCATION: PREY TRENG (POND)

DATE		DISCHAR(GE AT TIM	ME (CMS.)		ALC: Y	REMAR	₹.
DATE	6:00	9.00	12:00	15:00	18:00	RAIN	NO RAIN	TIME
01/11/00	0.364	0.342	0.342	0.342	0.342		,	
02/11/00	0.342	0.342	0.338	0.333	0.321			
03/11/00	0.301	0.301	0.293	0.282	0.282		3	
04/11/00	0.263	0.263	0.263	0.263	0.263			
05/11/00	0.263	0.267	0.267	0.270	0.274	/		10:00 - 12:00
06/11/00	0.245	0.228	0.228	0.222	0.215			
07/11/00	0.212	0.212	0.206	0.202	0.202			
08/11/00	0.196	0.196	0.196	0.193	0.190			
09/11/00	0.190	0.190	0.187	0.187	0.187			
10/11/00	0.181	0.181	0.181	0.176	0.167			
11/11/00	0.162	0.162	0.154	0.154	0.154			
12/11/00	0.141	0.141	0.141	0.141	0.117	/		18:00-20:00
13/11/00	0.212	0.206	0.202	0.196	0.190			
14/11/00	0.159	0.159	0.154	0.154	0.149			
15/11/00	0.146	0.146	0.146	0.141	0.141			
16/11/00	0.141	0.141	0.141	0.141	0.141			
17/11/00	0.141	0.141	0.141	0.141	0.141	/		18:00-20:00
18/11/00	0.146	0.146	0.146	0.143	0.143			
19/11/00	0.143	0.141	0.141	0.141	0.141			
20/11/00	0.136	0.136	0.129	0.122	0.117			
21/11/00	0.113	0.113	0.109	0.106	0.106			
22/11/00	0.102	0.102	0.100	0.100	0.096			
23/11/00	0.368	0.368	0.386	0.458	0.567			
24/11/00	0.096	0.096	0.096	0.096	0.096			
25/11/00	0.096	0.096	0.096	0.096	0.100	/		15:00-17:00
26/11/00	0.100	0.096	0.096	0.096	0.096	/		19:00-24:00
27/11/00	0.173	0.173	0.173	0.173	0.293			
28/11/00	0.117	0.117	0.115	0.113	0.109			
29/11/00	0.096	0.096	0.096	0.092	0.092		7	_
30/11/00	0.092	0.092	0.092	0.090	0.090			

PROJECT : SIHANOUKVILLE CCGT Tabel 2.3-8 (4) CALCULATED DISCHARGE DECEMBER 2000

LOCATION: PREY TRENG (POND)

DATE		Martin Military	optodk			REMARK		
		9:00	12:00	15:00	18:00	RAIN	NO RAIN	TIME
01/12/00	0.088	0.086	0.086	0.085	0.085			
02/12/00	0.081	0.081	0.081	0.077	0.076			
03/12/00	0.076	0.076	0.074	0.074	0.074			
04/12/00	0.074	0.074	0.074	0.072	0.072			
05/12/00	0.072	0.071	0.071	0.069	0.069			
06/12/00	0.067	0.067	0.067	0.066	0.064			
07/12/00	0.064	0.064	0.064	0.063	0.061	Ī		
08/12/00	0.071	0.069	0.069	0.069	0.069			
09/12/00	0.076	0.076	0.076	0.072	0.072	/		4:00-9:00
10/12/00	0.069	0.069	0.069	0.067	0.066			
11/12/00	0.077	0.081	0.085	0.088	0.092			
12/12/00	0.106	0.111	0.115	0.119	0.124		1	
13/12/00	0.141	0.141	0.141	0.141	0.117	T		
14/12/00	0.212	0.205	0.202	0.196	0.190			
15/12/00	0.159	0.159	0.154	0.154	0.148			-
16/12/00	0.061	0.061	0.061	0.061	0.061			
17/12/00	0.061	0.061	0.060	0.060	0.060			
18/12/00	0.058	0.058	0.058	0.058	0.058			
19/12/00	0.057	0.057	0.057	0.057	0.057			
20/12/00	0.057	0.057	0.057	0.061	0.061	/		12:00 - 18:00
21/12/00	0.096	0.096	0.094	0.094	0.092			
22/12/00	0.086	0.085	0.085	0.081	0.077			
23/12/00	0.069	0.066	0.064	0.061	0.061	T		
24/12/00	0.058	0.058	0.058	0.058	0.058			
25/12/00	0.058	0.058	0.058	0.055	0.055			
26/12/00	0.050	0.050	0.047	0.045	0.045			
27/12/00	0.045	0.045	0.045	0.046	0.047	/	T	12:00 - 18:00
28/12/00	0.047	0.047	0.047	0.046	0.046	1		
29/12/00	0.046	0.046	0.046	0.045	0.045			
30/12/00	0.045	0.045	0.045	0.045	0.045			
31/12/00	0.045	0.045	0.045	0.045	0.045	ļ		

PROJECT : SIHANOUKVILLE CCGT Table 2.3-8 (5) CALCULATED DISCHARGE JANUARY 2001

LOCATION: PREY TRENG (POND)

DATE	-0.000	DISCHAR	GE AT TIM	REMARK				
DATE	6:00	9:00	12:00	15:00	18:00	RAIN	NO RAIN	TIME
01/01/01	0.045	0.045	0.045	0.045	0.045			
02/01/01	0.045	0.045	0.045	0.045	0.045	/		18:00-20:00
03/01/01	0.047	0.047	0.047	0.047	0.047			
04/01/01	0.047	0.047	0.047	0.047	0.047			
05/01/01	0.046	0.046	0.046	0.046	0.046			
06/01/01	0.045	0.045	0.045	0.045	0.045			
07/01/01	0.045	0.045	0.045	0.045	0.045			
08/01/01	0.045	0.045	0.045	0.043	0.043	/		18:00-02:00
09/01/01	0.064	0.064	0.064	0.064	0.077			
10/01/01	0.096	0.096	0.096	0.092	0.088			
11/01/01	0.069	0.067	0.064	0.064	0.061			
12/01/01	0.061	0.061	0.061	0.058	0.055			
13/01/01	0.055	0.055	0.055	0.052	0.064	/		15:00-23:00
14/01/01	0.106	0.106	0.106	0.096	0.096			
15/01/01	0.117	0.117	0.113	0.102	0.098	/		03:00-06:00
16/01/01	0.077	0.074	0.071	0.067	0.064		-	
17/01/01	0.064	0.064	0.064	0.061	0.061			
18/01/01	0.058	0.058	0.058	0.055	0.052			
19/01/01	0.052	0.052	0.052	0.050	0.050			
20/01/01	0.050	0.050	0.050	0.050	0.050			
21/01/01	0.047	0.047	0.047	0.047	0.069	/		15:00-23:00
22/01/01	0.069	0.069	0.067	0.064	0.061			
23/01/01	0.061	0.061	0.061	0.061	0.061			
24/01/01	0.058	0.058	0.055	0.055	0.055			
25/01/01	0.052	0.050	0.047	0.047	0.045			
26/01/01	0.041	0.041	0.041	0.039	0.039			
27/01/01	0.037	0.037	0.037	0.037	0.037			
28/01/01	0.037	0.037	0.037	0.037	0.037			
29/01/01	0.035	0.035	0.035	0.035	0.035			
30/01/01	0.025	0.025	0.025	0.025	0.025	/		18:00-20:0
31/01/01	0.025	0.025	0.025	0.025	0.025	-		

PROJECT : SIHANOUKVILLE CCGT Table 2.3-8 (6) CALCULATED DISCHARGE FEBRUARY 2001

LOCATION: PREY TRENG (POND)

DATE		DISCHAI	RGE AT TIM	E (CMS.)		Element (S)	REMARK		
DATE	6:00	9:00	12:00	15:00	18:00	RAIN	NO RAIN	TIME	
01/02/01	0.047	0.047	0.047	0.047	0.045				
02/02/01	0.042	0.042	0.042	0.042	0.122	/		14:00-18:00	
03/02/01	0.122	0.122	0.122	0.117	0.196				
04/02/01	0.081	0.077	0.074	0.071	0.069				
05/02/01	0.064	0.064	0.064	0.061	0.058				
06/02/01	0.055	0.055	0.052	0.052	0.050				
07/02/01	0.050	0.050	0.050	0.047	0.047				
08/02/01	0.047	0.047	0.045	0.045	0.045				
09/02/01	0.045	0.045	0.042	0.042	0.040				
10/02/01	0.040	0.040	0.037	0.037	0.037				
11/02/01	0.035	0.035	0.035	0.033	0.031				
12/02/01	0.031	0.031	0.031	0.031	0.030			-	
13/02/01	0.029	0.029	0.029	0.029	0.028				
14/02/01	0.027	0.027	0.027	0.027	0.027				
15/02/01	0.035	0.035	0.035	0.035	0.035	/		03:00-06:00	
16/02/01	0.033	0.032	0.032	0.032	0.031				
17/02/01	0.031	0.031	0.028	0.028	0.028				
18/02/01	0.025	0.025	0.025	0.025	0.025				
19/02/01	0.025	0.025	0.025	0.025	0.025				
20/02/01	0.025	0.025	0.025	0.025	0.025				
21/02/01	0.023	0.023	0.023	0.023	0.023				
22/02/01	0.021	0.021	0.021	0.021	0.021				
23/02/01	0.020	0.020	0.020	0.020	0.020				
24/02/01	0.020	0.020	0.020	0.020	0.019				
25/02/01	0.017	0.017	0.017	0.017	0.017				
26/02/01	0.017	0.017	0.017	0.017	0.017		,		
27/02/01	0.017	. 0.017	0.017	0.017	0.017				
28/02/01	0.017	0.017	0.017	0.017	0.017				
				·					
				ļ		1	1		

Table 2.5-1 SUMMARY OF BORING WORK (Offshore)

1	Bored Hole	Co-ordinate	linate	Ground Level	Number of	Number of	Soil Coring	Rock Coring	Number of Soil Coring Rock Coring Total Depth of
III	No.	Z	Ξ	(msl)	UD-Sampling	SPT	(m.)	(m)	Bored Hole (m.)
П	BH-10	1,182,977.327 341,173.277	341,173.277	-5.00	1	15	7.15	12.85	20.00
2	BH-11	1,182,977.327 341,279.777	341,279.777	-2.00	Г	10	4.75	15.25	20.00
.CO	3 BH-12	1,182,477.327 341,209.277	341,209.277	:		17	8.30	14.25	22.55
4	BH-13	1,182,477.327 341,077.277	341,077.277	-5.00		19	9.50	8.00	17.50
		TOTAL	T		4	61	29.70	50.35	80.05

Table 2.5-2 (1) Summary of Physical Properties Test Results of Borehole No.BH-10 - BH-13

_		_					-	_		_	_				_	_		_	_
	Soil Description		Sity SAND	Poorly graded SAND with sit	Sandy SILT	Silty SAND	Sitstone	Sity SAND	Sity SAND	Silty SAND	Sandstone	Silty SAND	Silty SAND	Silty SAND	Sandstone	Silty SAND	Silty SAND	Sily SAND	Sandstone
	nscs		SM	SP-SM	M	SM	Rock	SM	SM.	WS	Rock	SM	SMS	SM	Rock	SM	SM	SM	Rock
	Colour		Dark Greenish Gray	Dark Greenish Gray	Grayish Olive Green	Dusky Blue Green		Light Olive Gray	Light Olive Gray	Olive Gray		Dusky Blue Green	Moderate Olive Brown	Light Gray		Dusky Blue Green	Dusky Blue Green	Light Gray	
SPT	z :	Value	0	-	-			12		7		0		89			-	>50	
Modulus	@ 50% cu	(lon/m²)					12,179*				160,182				326,687				136,086
Shear Ith		9					213				1,226				2,127				834
Undrained Shea Strength.	(ton/m²)	Ы				9.0			9.0				0.7			4.0			
	3	i i				п		_	2				4			2			
	÷	_	50	9	20	60		1,4	56	17		17	50	20		24	26	15	
Size (%)		Fine	20	09	44	68	-	35	64	92		65	7.2	77		92	99	76	
Grain S	Sand	nip4	59	27	2	10		0	8	4		17	4	3	1	80	80	7	
ľ		Coers			-	0		0	0	8		-	0	0		0	-	-	
	Grana	5	0	40	0	0		0	0	0		0	0	٥		-	0	N	
Specific	Gravity	5	2.64	2.67	2.61	2.65		2.69	2.69	2.64		2.66	2.60.	2.67		2.68	2.68	2.67	
Plasticity Specific	Index	(%)	ď	NP	NP	Ν		Α	δ	Ν		ΑN	NP	ΝP		ΝP	ΑN	Νb	
Liquid	-	(%)	ď	Ν	Ν	٩		δ	Š	ď		dΝ	Ν	ΔN		ΜN	Ν	ΝÞ	
Total	Weight	(ton/m³)				1.92	2.24		1.85		2.33		1.95		2.31	1.78			2.42
Water	Content	ĝ.	26.3	21.1	45.1	31.6	2.2	27.0	35.0	24.6	0.3	22.7	21.6	17.0	0.4	9000	22.9	14.5	6.0
(m)	P.		2.95	4.95	5,45	00.9	13.05	1.45	2.50	3.45	10.20	2.95	7.00	7.45	15.50	3.00	4.95	9.45	15.30
Depth (m)	From		2.50	4.50	5.00	5.00	11.55	1.00	1.50	3.00	8.80	2.50	6.00	7.00	14.20	2.00	.4.50	9.00	13.80
	Sample No.		SS-6	55-10	\$5-11	UD-1	C-5	55-3	UD-1	58-7	5	9-88	UD-1	S-15	ર	UD-1	SS-10	55-19	5
	Borehole Sample No. No.		BH-10	BH-10	BH-10	BH-10	BH-10	BH-11	BH-11	BH-11	BH-11	BH-12	BH-12	BH-12	BH-12	BH-13	BH-13	BH-13	BH-13

Table 2.5-2 (3) Summary of Isotropically Consolidated Triaxial Drained Test (CID) Results

Г						_							_
	Soil Description	Silty SAND			Silty SAND				Silty SAND			Silty SAND	
	nscs		SM		SM			SM			Ws		
	Colour	Dusky Blue Green				Light Olive Gray			Moderate Olive Brown			Dusky Blue Green	
	(degree)		34.7		32.0			36.8				27.7	
	c' (ton/m²)	0.0				0.2			0.0			8.0	
Undrained	Modulus @50%, E _{so} (ton/m²)	929	593	1046	132	117	381	214	1979	2037	308	184	477
Undrained	Strength, c _u (ton/m²)	4.4	6.9	16.3	1.7	2.4	4.9	3.3	10.3	18.5	2.4	2.9	5.0
iai	Total Unit Weight (ton/m²)	1.87	1.94	1.98	1.81	1.89	1.94	2.10	2.12	2.13	1.99	1.97	1.96
· Initial	Water Content (%)	3.1	28.4	27.5	39.6	33.2	29.9	22.7	17.4	17.3	26.8	29.3	30.3
Effective	Effective Confining Stress, o'c (ton/m²)		6.0	12.0	1.0	2.0	4.0	3.0	6.00	12.0	1.0	2.0	4.0
(m)			6.00		2.50		7.00		3.00				
Depth	Prom To		9.00			1.50		6.00		2.00			
	Sample No.		nD-1			UD-1			D-1-			UD-1	
	Borehole S No.		BH-10			BH-11			BH-12		BH-13		

Table 2.5-2 (4) Summary of Unconfined Compression Test on Rock Sample

Rock Description		Siltstone	Sandstone	Sandstone	Sandstone
Strain at	(%)	3.5	1.7	1.1	1.0
Undrained Modulus @	50% cu (ton/m²)	12,179	160,182	326,687	136,086
Unconfined	Strength, q (ton/m²)	427	2,452	4,253	1,668
Undrained Shear	Strength, c, (ton/m²)	213	1,226	2,127	834
Total Unit	(ton/m³)	2.24	2.33	2.31	2.42
Water	(%)	2.2	0.3	0.4	0.3
Depth (m)	To	12.75	9.53	14.66	14.40
Depti	From	12.50	9.25	14.40	14.15
Sample No.		C-5	C-7	C-5	C-4
Borehole No.		BH-10	BH-11	BH-12	BH-13

Table 2.6-1 Tidal Harmonic Constituents at CCGT Project Site

Position Lat. 10⁰ 41' 57" N, Long. 103⁰ 32' 51". Time Zone -7.0h.

Symbol	(V ₀ +u)p	F(large)	H(amp.) cm	K(phase) Degree
M ₂	183.72	0.9783	13.7	14.9
N ₂	159.09	0.9783	1.4	17.6
S ₂	357.10	1.0000	4.3	46.8
O ₁	228.90	1.1047	21.2	114.7
K ₁	318.76	1.0619	24.6	122.2
K ₂	98.20	1.1759	1.2	46.8
L ₂	346.27	0.8404	0.4	12.2
2N ₂	134.46	0.9783	0.2	20.3
R ₂	132.19	1.0000	0.0	46.8
T ₂	42.00	1.0000	0.3	46.8
λ_2	150.74	0.9783	0.1	29.7
μ_2	12.06	0.9783	0.3	343.0
ν ₂	36.70	0.9783	0.3	17.3
J ₁	339.45	1.0855	1.7	125.9
M ₁	207.83	1.0093	1.5	118.5
001	220.74	1.4089	0.9	129.6
P ₁	30.50	1.0000	8.1	122.2
Q ₁	204.27	1.1047	4.1	111.0
2Q ₁	179.63	1.1047	0.6	107.3
RHO₁	81.88	1.1047	0.8	111.5
M ₄	7.44	0.9571	0.3	246.5
M ₆	191.16	0.9363	0.6	168.6
M ₈	14.88	0.9160	0.3	310.2
S ₄	354.20	1.0000	0.1	323.6
S ₆	351.30	1.0000	0.1	218.0