

## **List of drawings and tables**

Fig. 1-1-1	Improvement of News & Information Program
Fig. 1-1-2	Compositional percentages of the various programs for National Program
Fig. 2-2-1	Project Site at TVRI Headquarter
Fig. 2-2-2	Final Modified Plan for Requested Equipment
Fig. 2-2-3	Comparison Between Requested and Alternative Plan of Digital Archive System
Fig. 2-2-4	Flow of Registration and Storage System for Broadcast Tape
Fig. 2-2-5	Flow of Various Tape Formats (draft)
Fig. 2-2-6	Project Site
	(1/2) Layout of New News Division (ex-RTF building 1st Floor)
	(2/2) Layout of New News Division (ex-RTF building 2nd Floor)
Fig. 2-2-7	1 to 1 Editing System (A)
	(1/3) Video and Control Signal Connection Diagram
	(2/3) External View of Console
	(3/3) Layout of Equipment
Fig. 2-2-8	1 to 1 Editing System (B)
	(1/3) Video and Control Signal Connection Diagram
	(2/3) External View of Console
	(3/3) Layout of Equipment
Fig. 2-2-9	A/B Roll Editing System-1
	(1/4) Video and Control Signal Connection Diagram
	(2/4) Audio Signal Connection Diagram
	(3/4) External View of Console
	(4/4) Layout of Equipment
Fig. 2-2-10	A/B Roll Editing System-2
	(1/2) Video and Control Signal Connection Diagram
	(2/2) Layout of Equipment
Fig. 2-2-11	Non-Linear Editing System
	(1/3) Connection Diagram
	(2/3) External View of Console
	(3/3) Layout of Equipment

- Fig. 2-2-12 On-air VTR System in Continuity Studio 1 and 2  
(1/3) Connection Diagram  
(2/3) External View of Rack (Continuity Studio-1)  
(3/3) External View of Rack (Continuity Studio-2)
- Fig. 2-2-13 Program Exchange VTR System  
(1/3) Video and Control Signal Connection Diagram  
(2/3) Audio Signal Connection Diagram  
(3/3) External View of Rack
- Fig. 2-2-14 Foreign Program Recording System  
(1/3) Video and Control Signal Connection Diagram  
(2/3) Audio Signal Connection Diagram  
(3/3) External View of Racks
- Fig. 2-2-15 Studio Recording VTR System in Studio 6  
(1/6) Video Signal Connection Diagram  
(2/6) Audio Signal Connection Diagram  
(3/6) External View of Racks  
(4/6) External View of Console  
(5/6) External View of Monitor Shelf  
(6/6) Layout of Sub Control Room
- Fig. 2-2-16 Studio Recording VTR System in Studio 10  
(1/3) Video Signal Connection Diagram  
(2/3) Audio Signal Connection Diagram  
(3/3) External View of Racks
- Fig. 2-2-17 Broadcast Tape Storage System  
(1/4) Connection Diagram  
(2/4) External View of Racks  
(3/4) Floor Layout of Control Room  
(4/4) Layout of Racks
- Fig. 2-2-18 Scopes of Power-supply and Grounding Works
- Fig. 2-2-19 Supervisory System
- Fig. 2-4-1 Repair Work Flow Chart (In the case of using spare part/unit as an example)

Table 1-1-1	TVRI Program Schedule (Nationwide Broadcasts)
Table 1-1-2	TVRI Program Schedule (Metropolitan Area Broadcasts)
Table 1-1-3	Usage Track Records of Editing Equipment
Table 1-1-4	Usage Track Records of News Coverage Cameras
Table 1-1-5	Principal Economic Indices in Indonesia
Table 2-2-1	Current Status of Existing Cameras
Table 2-2-2	Daily Time Schedule of Foreign Program Recording System
Table 2-2-3	Comparison of Digital Archive Systems
Table 2-2-4	Equipment Specifications
Table 2-2-5	Implementation Schedule
Table 2-3-1	Cost of Renovation / Relocation Works to be undertaken by the Indonesian Side
Table 2-4-1	The Numbers of Employees at News Division (Division II) by Role
Table 2-5-1	Maintenance/Renewal Cost Ratio of Broadcasting Equipment
Table 2-5-2	Formula for Calculating Maintenance Cost at TVRI
Table 2-5-3	Purchase Cost of Spare Parts/Units in Developing Countries
Table 2-5-4	Increase in Power Demand after Implementation of the Project