

Japan International Cooperation Agency (JICA)

Ministry of Infrastructure (MOI)

Post and Telecommunication Authority (PTA)

**THE MASTER PLAN STUDY**  
**FOR**  
**DEVELOPMENT OF RURAL TELECOMMUNICATION**  
**SYSTEM**  
**IN**  
**MONGOLIA**  
**FINAL REPORT**  
**VOLUME III**  
**FEASIBILITY STUDY**

JICA LIBRARY



1172146(1)

**FEBRUARY 2003**

**Japan Telecommunications Engineering and Consulting Service (JTEC)**  
**and**  
**Pacific Consultants International (PCI)**  
**TOKYO, JAPAN**

SSS

JR

03-35

**CURRENCY AND EQUIVALENT UNITS**

**(As of July, 2002)**

**Currency Unit = Mongolian Tugrik (Tg)**

**US\$ 1.00 = Tg 1,099.47**

**Tg 1,000 = US\$ 0.9095**

**Currency Unit = Japanese Yen (JPY)**

**JPY 1,000 = US\$ 8.361**

**US\$ 1.00 = JPY 119.60**

**Japan International Cooperation Agency (JICA)**

**Ministry of Infrastructure (MOI)**

**Post and Telecommunication Authority (PTA)**

**THE MASTER PLAN STUDY  
FOR  
DEVELOPMENT OF RURAL TELECOMMUNICATION  
SYSTEM  
IN  
MONGOLIA  
FINAL REPORT  
VOLUME III  
FEASIBILITY STUDY**

**FEBRUARY 2003**

**Japan Telecommunications Engineering and Consulting Service (JTEC)  
and  
Pacific Consultants International (PCI)  
TOKYO, JAPAN**



1172146【1】

## PREFACE

In response to a request from the Government of Mongolia, the Government of Japan decided to conduct a master plan study for Development of Rural Telecommunication System in Mongolia and entrusted the study to the Japan International Cooperation Agency (JICA).


JICA sent to Mongolia a study team headed by Mr. Hideo MITSUHASHI, Japan Telecommunications Engineering and Consulting Service, three times between March 2002 and February 2003. In addition, JICA set up an advisory committee headed by Mr. Junichi Shioya, Deputy Director, International Cooperation Division, Ministry of Public Management, Home Affairs, Posts and Telecommunications of Japan, which examined the Study from specialist and technical points of view.

The team held discussions with the officials concerned of the Government of Mongolia, and conducted field surveys at the study area. After the team returned to Japan, further studies were made and this final report was prepared.

I hope that this report will contribute to the promotion of the project and to the enhancement of friendly relations between our two countries.

I wish to express my sincere appreciation to the officials concerned of the Government of Mongolia for their close cooperation extended to the team.

February 2003



---

Takao Kawakami  
President  
Japan International Cooperation Agency



Mr. Takao Kawakami  
President  
Japan International Cooperation Agency

February 2003

Dear Mr. Takao Kawakami

**Letter of Transmittal**

It is a great pleasure for us to submit to you the Master Plan Study Report for Development of Rural Telecommunication System in Mongolia.

This report has been prepared by Japan Telecommunications Engineering and Consulting Services (JTEC) and Pacific Consultants International (PCI), based on a contract with JICA. The study team conducted the works from March 2002 to February 2003.

The study aims at formulating the master plan for the development of rural telecommunication system in Mongolia up to the year 2020 and feasibility study for priority projects which will be implemented by the year 2006 in Mongolia.

Objective area of the study covered the rural areas through whole country for the master plan and several targets areas for the feasibility study. Through field surveys and analyses of data/information collected, the master plan has been drawn up covering mainly development targets and strategies, demand forecast, network development plan, facilities plan, implementation plan, operation/maintenance/human resource plans, as well as cost estimate and project evaluation. The feasibility study has been made for priority projects in three Aimags identified as a result of the master plan study.

We wish to take this opportunity to express our deep gratitude to the officials concerned of the Japan International Cooperation Agency and other authorities concerned of the Government of Japan. We wish to offer our sincere appreciation to the officials concerned of Ministry of Infrastructure, Post and Telecommunication Authority and other authorities concerned of the Government of Mongolia for their unlimited cooperation and assistance extended to the study team in connection with the execution of their duties.

Finally, we earnestly hope that this report will contribute to future telecommunications development in Mongolia.

Very truly yours



Hideo Mitsuhashi



Team Leader

Master Plan Study for Development of  
Rural Telecommunication System in Mongolia






# MAP OF MONGOLIA



- Industry
- Metal working
- Chemical industry
- Woodworking industry
- Industry of building materials
- Light industry
- Food industry
- Extractive industry
- Coal
- Brown coal
- White sh.
- Copper
- Power Station
- Thermoelectric
- Rice agriculture
- May and silk farm cattle for Selenge
- Meat and milk farm cattle for Baitan Khentii
- Cattle (sheep farm fodder Khengai Khirgaid)
- Cattle (sheep farm on the Dornod pasture)
- Pig (Lena Depression cattle farm)
- Wool
- Fur
- Coal gas and sheep breeding Govt.
- Border zones
- Sea Routes

- CAPITAL AND ADMINISTRATIVE**
- ULAANBAATAR Capital of the MPR
  - DUNDKHALAN Centres regions (provinces)
  - Centres districts
  - Centres
  - from 30 000 to 100 000 inhabitants
  - from 10 000 to 30 000 inhabitants
  - from 5 000 to 10 000 inhabitants
  - under 5 000 inhabitants
- BOUNDARIES**
- International Boundary of the MPR
  - Boundary of the provinces
- COMMUNICATIONS**
- Railways
  - Motor highways and Motor Roads
  - Main Roads, Routes
  - Other
- CONVENTIONAL SIGN**
- River (Depth in meters)
  - Subirrigation
  - Dry Courses (sand)
  - Lakes (fresh and lakes salt)
  - Lakes seasonal
  - Wells, Springs
  - Swamps or Marshes (Siltation)
  - Sands
  - Heights above Sea Level in meters
  - Eternel Snows and Glaciers
  - Ancient Embankments
  - Cores
- DEPTH AND HEIGHT SCALES IN METERS**
- Scale: 1:12,000,000





## **EXECUTIVE SUMMARY**

---

## EXECUTIVE SUMMARY

### 1. General

This report covers the Feasibility Study for the target projects of which were selected from the short term plan up to 2008 of the Master Plan Study.


### 2. Selection of Priority Projects for Feasibility Study

For the selection of priority projects, Regions, Aimags and Sums were studied and analysed in consideration of national development policy. Major criteria for the prioritisation of Aimag in Region were as:

- (a) Development Needs and Potentials for Rural Development.
- (b) Economic Indicators of Rural Areas.
- (c) Technical Factors in Sums.

Through prioritisation procedure of Aimag in Region, three Aimags were selected for the feasibility study finally, that is, Uvurkhangai, Selenge, and Darkhan-Uul. In succession to the Aimag selection, Sums were selected under the criteria as:

- Comprehensive analysis and evaluation of Sums,
- Priority evaluation of Sums by PTA.
- Planned Inter-Sum centres.
- Demand in 2020.



Sums selected for the feasibility study are:

#### Uvurkhangai:

Bayan-Undur, Burd, Bat-Ulzii, Bayangol, Esunzuil, ZB Ulaan, Nariinteel, Sant, Uyanga, Khujirt, and Kharkhorin. (Total 10 Sums).

#### Selenge and Darkhan-Uul:

Altanbulag, Eruu, Zuunburen, Tsaganuur, Shaamar, Sant, Orkhontuul, Khutul, Zuunkharaa, Bayangol (Baruunkharaa), Tunkhel, Sharingol. (Total 12 Sums).

### 3. Demand Forecast

All Sum centres in Uvurkhangai, Selenge, and Darkhan-Uul were the objects of the microscopic demand forecast, though Bag areas were excluded. The microscopic demand was forecast based on the data collected from sample households, public organisations, and business companies in selected Sum centres, in addition to the statistic data obtained through the study. The demand forecast counted on the number of existing subscribers, waiting applicants, unexpressed demand, and that which could shift from mobile demand.

**Table 3-1 Demand Forecast**

| Aimag       | Macro Demand Forecast |         | Micro Demand Forecast |         |
|-------------|-----------------------|---------|-----------------------|---------|
|             | Demand in 2020        | Density | Demand in 2020        | Density |
| Uvurkhangai | 4,444                 | 0.18    | 4,931                 | 0.19    |
| Selenge     | 5,359                 | 0.06    | 6,628                 | 0.08    |
| Darkhan Uul | 1,765                 | 0.1     | 1,862                 | 0.1     |
| Total       | 11,568                | 0.09    | 13,420                | 0.1     |

### 4. Scope of Project

The Feasibility Study is focused to design the Sum centre network and links to connect them with Uvurkhangai, Selenge, and Darkhan-Uul Aimag centre. The plan is established under the conditions that the proposed expansion and improvement be realised solely as part of MT network which is possessed by PTA.

**Table 4-1 Main Scope of Project**

| Items               |                      | Facilities              | Quantities |
|---------------------|----------------------|-------------------------|------------|
| Switching System    |                      | Number of Exchanges     | 22         |
|                     |                      | Line Unit               | 6,580      |
| Transmission System | Optical Fibre System | Cable Length (km)       | 9.4        |
|                     |                      | Multiplessor            | 8          |
|                     | Mincrowave System    | Number of Links         | 44         |
| Access System       | Wired System         | Number of Exchanges     | 18         |
|                     |                      | Cable Pairs             | 4,450      |
|                     | Wireless System      | Number of Exchanges     | 4          |
|                     |                      | Number of Cell Stations | 20         |
| IT Services         | IT Spot              | Number of Spots         | 22         |

## 5. Project Cost

Project cost is estimated as follows.

(in US\$ 1,000)

| Items               |                      | Total Cost | Foreign Currency Portion | Local Currency Portion |
|---------------------|----------------------|------------|--------------------------|------------------------|
| Switchin System     |                      | 2,062      | 2,057                    | 5                      |
| Transmission System | Optical Fibre System | 609        | 521                      | 88                     |
|                     | Microwave System     | 4,927      | 4,285                    | 642                    |
| Access System       | Wiered System        | 1,764      | 1,273                    | 491                    |
|                     | Wireless System      | 2,743      | 2,652                    | 91                     |
| Power Plant         |                      | 243        | 216                      | 27                     |
| IT Services         |                      | 248        | 0                        | 248                    |
| Contingency         |                      | 630        | 550                      | 80                     |
| Consultancy Fee     |                      | 1,008      | 1,008                    | 0                      |
| Total               |                      | 14,234     | 12,562                   | 1,672                  |

## 6. Financial Evaluation

The evaluation is done under the assumptions that a) project evaluation period is 2005 to 2020 (16 years), consisting of one year of “construction” and 15 years of “operations; b) all revenues and costs are expressed at the fixed prices at the end of 2001; and c) exchange rate is fixed at Tugrug 1,102 for one U.S. Dollar (at the end of 2001).

In the base case analysis, Financial Internal Rate of Return on Investment (FIRROI) is 2.197%. Dramatic improvements both in cash flow and profitability are brought about in contrast with the Master Plan. The single year cash flow would be positive every year of operations. Positive profit would be realised in the 7th year of operations. Financial self-sufficiency would be achieved in the 10th year of operations. Theses figures clearly indicate financial soundness of the project. Although the value of FIRROI is not much different from that of the Master Plan, total difference exists in substance. Subsidies would be necessary for 6 years, but the total amount would be as small as 600,000 U.S. dollars. If the subsidies are disbursed from the Universal Service Obligations Fund, a discounted front-end lump sum payment can be adopted to minimise the amount of subsidies.

In the sensitivity analysis, when revenues increase by 10% including adjustment of tariffs, FIRROI would be 3.249%, bringing financial self-sufficiency in the 4th year of



## CONTENTS

### VOLUME I      SUMMARY

### VOLUME II      MASTER PLAN

### VOLUME III      FEASIBILITY STUDY

#### EXECUTIVE SUMMARY

#### CHAPTER 1   INTRODUCTION

|       |  |     |
|-------|--|-----|
| 1.1   | Background of the Priority Projects .....                                | 1-1 |
| 1.1.1 | General.....   | 1-1 |
| 1.1.2 | Objectives of the Study.....   | 1-2 |
| 1.2   | Selection of Priority Projects for Feasibility Study .....               | 1-3 |
| 1.2.1 | Selection of Priority Projects .....                                     | 1-3 |
| 1.2.2 | Priority Projects and Projects Site Selected for Feasibility Study ..... | 1-3 |
| 1.3   | Precondition of the Feasibility Project .....                            | 1-4 |
| 1.3.1 | General.....   | 1-4 |
| 1.3.2 | Impacts by Participation of Private Operators.....                       | 1-5 |
| 1.3.3 | Microscopic Demand Forecast for Feasibility Study .....                  | 1-5 |
| 1.4   | Work Schedule for the Feasibility Study.....                             | 1-6 |
| 1.4.1 | Overall Time Schedule .....  | 1-6 |
| 1.4.2 | Progress in the Second Study in Mongolia.....                            | 1-6 |
| 1.4.3 | Progress in the Second Work in Japan .....                               | 1-7 |
| 1.5   | The Study Team and the Parties Concerned.....                            | 1-7 |
| 1.5.1 | JICA Study Team .....  | 1-7 |
| 1.5.2 | Counterpart from Mongolian Side.....                                     | 1-7 |
| 1.5.3 | JICA Advisory Committee .....  | 1-7 |

#### CHAPTER 2   PRESENT STATUS OF TELECOMMUNICATIONS

|       |   |      |
|-------|---|------|
| 2.1   | General.....                                    | 2-1  |
| 2.2   | Socio-economic Status of the Project Area ..... | 2-1  |
| 2.3   | Existing Facilities and Services .....          | 2-4  |
| 2.3.1 | Switching System.....                           | 2-4  |
| 2.3.2 | Transmission System.....                        | 2-8  |
| 2.3.3 | Access Network System.....                      | 2-14 |
| 2.3.4 | Power System.....                               | 2-18 |
| 2.3.5 | IT System.....                                  | 2-19 |



**CHAPTER 3 DEMAND FORECAST**

|       |  |      |
|-------|--|------|
| 3.1   | Telephone Demand .....                             | 3-1  |
| 3.1.1 | General.....                                       | 3-1  |
| 3.1.2 | Concept of the Microscopic Demand Forecast.....    | 3-1  |
| 3.1.3 | Data Collection .....                              | 3-3  |
| 3.1.4 | Site Survey Result.....                            | 3-5  |
| 3.1.5 | Present Demand Estimation.....                     | 3-11 |
| 3.1.6 | Future Demand Estimation .....                     | 3-20 |
| 3.1.7 | Fulfilment Plan of the Forecasted Sum Demand ..... | 3-25 |
| 3.1.8 | Estimation Result.....                             | 3-29 |
| 3.2   | IT Demand .....                                    | 3-31 |
| 3.2.1 | Method of Demand Forecast .....                    | 3-31 |
| 3.2.2 | Results of IT Demand Forecast .....                | 3-32 |

**CHAPTER 4 TECHNICAL PLAN**

|        |  |      |
|--------|--|------|
| 4.1    | General.....                                   | 4-1  |
| 4.2    | Switching Network Plan .....                   | 4-1  |
| 4.2.1  | Basic Concept .....                            | 4-1  |
| 4.2.2  | Existing Switching Network.....                | 4-1  |
| 4.2.3  | Proposed switching network.....                | 4-3  |
| 4.3    | Traffic Forecast and Circuit Calculation ..... | 4-5  |
| 4.3.1  | Purpose of Traffic Forecast .....              | 4-5  |
| 4.3.2  | Numerical Data for Calculation.....            | 4-5  |
| 4.3.3  | Subscriber Line Calling Rate.....              | 4-6  |
| 4.3.4  | Required Number of Circuits.....               | 4-6  |
| 4.4    | Numbering Plan .....                           | 4-7  |
| 4.4.1  | Existing Numbering Plan.....                   | 4-7  |
| 4.4.2  | Proposed Numbering Plan .....                  | 4-8  |
| 4.5    | Signalling System.....                         | 4-9  |
| 4.6    | Charging System.....                           | 4-9  |
| 4.7    | Interconnection Plan .....                     | 4-10 |
| 4.8    | Synchronisation Plan .....                     | 4-14 |
| 4.9    | Transmission Plan.....                         | 4-14 |
| 4.9.1  | Optical Fibre Transmission Plan .....          | 4-14 |
| 4.9.2  | Radio Transmission Network Plan.....           | 4-15 |
| 4.10   | Access Network Plan .....                      | 4-18 |
| 4.10.1 | Wired Access Network System .....              | 4-18 |
| 4.10.2 | Wireless Access Network System .....           | 4-19 |
| 4.11   | Power System .....                             | 4-23 |
| 4.12   | IT Plan .....                                  | 4-25 |
| 4.12.1 | Internet and IP Network.....                   | 4-25 |
| 4.12.2 | Internet Traffic Forecast .....                | 4-26 |

**CHAPTER 5 FACILITIES PLAN**

|       |   |      |
|-------|---|------|
| 5.1   | General.....  | 5-1  |
| 5.2   | Switching Facilities .....                                | 5-1  |
| 5.2.1 | Switching System General Features .....                   | 5-1  |
| 5.2.2 | Services to be Provided .....                             | 5-2  |
| 5.2.3 | Dimensioning of Switching System .....                    | 5-2  |
| 5.2.4 | Scope of Work and Cost Estimate .....                     | 5-4  |
| 5.2.5 | Operation and Maintenance Centre at Aimag .....           | 5-5  |
| 5.2.6 | Aimag Centre Switching System.....                        | 5-5  |
| 5.3   | Transmission Facilities .....                             | 5-5  |
| 5.3.1 | Digital Microwave Transmission Facilities.....            | 5-5  |
| 5.3.2 | Optical Fibre Transmission Facility .....                 | 5-19 |
| 5.4   | Access Network Facilities .....                           | 5-25 |
| 5.4.1 | Wired Access Network .....                                | 5-25 |
| 5.4.2 | Wireless Access Network .....                             | 5-28 |
| 5.5   | Power Supply Facilities .....                             | 5-37 |
| 5.6   | IT Facilities.....  | 5-40 |
| 5.7   | Land and Building .....                                   | 5-43 |
| 5.7.1 | Switching Facilities .....                                | 5-43 |
| 5.7.2 | Outdoor Installation of Microwave Repeater Stations ..... | 5-43 |
| 5.7.3 | Antenna Supports.....                                     | 5-44 |
| 5.7.4 | Main Power Supply .....                                   | 5-44 |
| 5.7.5 | Access Roads to the Sites .....                           | 5-44 |
| 5.7.6 | Fencing and Safety Measures .....                         | 5-45 |

**CHAPTER 6 PROJECT IMPLEMENTATION PLAN**

|       |  |      |
|-------|--|------|
| 6.1   | Implementation Schedule .....  | 6-1  |
| 6.1.1 | General.....   | 6-1  |
| 6.1.2 | Basic Policy .....   | 6-1  |
| 6.1.3 | Implementation Schedule of Grant Aid Project from<br>Japanese Government ..... | 6-2  |
| 6.1.4 | Implementation Schedule of Ordinary Project .....                              | 6-6  |
| 6.2   | Management on Project Implementation.....                                      | 6-9  |
| 6.2.1 | Quick Start and Smooth Advance of the Project .....                            | 6-9  |
| 6.2.2 | Organisation.....  | 6-9  |
| 6.2.3 | Attentions on Technical Matters.....   | 6-10 |

**CHAPTER 7 OPERATION AND MAINTENANCE PLAN**

|       |   |     |
|-------|---|-----|
| 7.1   | Basic Policy .....                                  | 7-1 |
| 7.2   | O/M Plan of Each System.....                        | 7-2 |
| 7.2.1 | Switching System .....                              | 7-2 |
| 7.2.2 | Transmission System(Radio, Optical Fibre, WLL)..... | 7-2 |
| 7.2.3 | Outside Plant.....                                  | 7-2 |

|       |  |     |
|-------|--|-----|
| 7.2.4 | Power System .....                       | 7-2 |
| 7.2.5 | IT System.....                           | 7-3 |
| 7.3   | Main O/M Works .....                     | 7-3 |
| 7.3.1 | Sum Centre .....                         | 7-3 |
| 7.3.2 | Aimag Centre.....                        | 7-4 |
| 7.4   | Maintenance Equipment and Material ..... | 7-5 |
| 7.5   | Recommendations.....                     | 7-6 |

## **CHAPTER 8 HUMAN RESOURCE DEVELOPMENT AND TRAINING PLAN**

|       |   |     |
|-------|---|-----|
| 8.1   | Human Resource Development Plan .....         | 8-1 |
| 8.1.1 | Present Staff.....                            | 8-1 |
| 8.1.2 | Staff Plan of the Project.....                | 8-3 |
| 8.2   | Training Plan .....                           | 8-4 |
| 8.2.1 | Trainees and Required Skill Level .....       | 8-5 |
| 8.2.2 | Training Place, Facility and Instructor ..... | 8-5 |
| 8.2.3 | Duration of Training.....                     | 8-6 |
| 8.2.4 | Summary of Training Plan.....                 | 8-6 |
| 8.3   | Organisation and Management .....             | 8-9 |
| 8.4   | Recommendations.....                          | 8-9 |

## **CHAPTER 9 PROJECT COST ESTIMATE**

|     |   |     |
|-----|---|-----|
| 9.1 | General.....  | 9-1 |
| 9.2 | Objective Sum Centres .....                           | 9-1 |
| 9.3 | Scope of Work and Precondition for Cost Estimate..... | 9-2 |
| 9.4 | Total Project Cost Estimate .....                     | 9-2 |

## **CHAPTER 10 FINANCIAL EVALUATION**

|      |  |      |
|------|--|------|
| 10.1 | General.....   | 10-1 |
| 10.2 | Annual Records (1999-2001) of Revenues and Expenditures of<br>the Selected Sums for F/S..... | 10-1 |
| 10.3 | Preconditions for Financial Evaluation .....   | 10-3 |
| 10.4 | Financial Evaluation of Project .....  | 10-4 |
| 10.5 | Conclusion of Financial Evaluation.....  | 10-7 |

## **CHAPTER 11 RECOMMENDATIONS**

|      |                                     |      |
|------|-------------------------------------|------|
| 11.1 | Switching System .....              | 11-1 |
| 11.2 | Transmission System .....           | 11-1 |
| 11.3 | Wired Access Network.....           | 11-2 |
| 11.4 | Power Supply Facilities .....       | 11-3 |
| 11.5 | IT Facilities.....                  | 11-3 |
| 11.6 | Land and Building .....             | 11-3 |
| 11.7 | Project Implementation.....         | 11-4 |
| 11.8 | Operation and Maintenance Plan..... | 11-5 |

|       |  |      |
|-------|--|------|
| 11.9  | Human Resource Development and Training Plan ..... | 11-5 |
| 11.10 | Financial Aspect .....                             | 11-5 |

**CHAPTER 12 COMPREHENSIVE ASSESSMENT OF FEASIBILITY STUDY PROJECT**

|        |   |      |
|--------|---|------|
| 12.1   | General.....  | 12-1 |
| 12.2   | Present Status of Project Areas .....                                       | 12-1 |
| 12.3   | Proposed Facilities Plan .....  | 12-3 |
| 12.4   | Analysis and Assessment of Feasibility Study Project .....                  | 12-5 |
| 12.4.1 | Social Appropriateness .....  | 12-5 |
| 12.4.2 | Technical Appropriateness .....   | 12-6 |
| 12.4.3 | Economic Appropriateness .....  | 12-6 |
| 12.4.4 | Financial Appropriateness .....   | 12-7 |
| 12.4.5 | Organisational and Management Appropriateness .....                         | 12-7 |
| 12.4.6 | Appropriateness for Environment Protection .....                            | 12-8 |
| 12.5   | Issues and Attentions for Implementation of Feasibility Study Project ..... | 12-8 |
| 12.6   | Conclusion .....  | 12-9 |

**ANNEXES OF VOLUME III**

**PART-1 MASTER PLAN**

**PART-2 FEASIBILITY STUDY**

|         |                             |
|---------|-----------------------------|
| ANNEX 1 | MICROSCOPIC DEMAND FORECAST |
| ANNEX 2 | SWITCHING SYSTEM            |
| ANNEX 3 | RADIO TRANSMISSION SYSTEM   |
| ANNEX 4 | WIRED ACCESS NETWORK SYSTEM |
| ANNEX 5 | POWER SYSTEM AND SUPPLY     |
| ANNEX 6 | IT SYSTEM                   |
| ANNEX 7 | FINANCIAL CALCULATION DATA  |

**VOLUME IV SUPPORTING DATA**

**VOLUME V DATA BOOK**

## LIST OF FIGURES

### CHAPTER 1 INTRODUCTION

Figure 1.2-1 A Flow of Project Formation ..... 1-4

### CHAPTER 2 PRESENT STATUS OF TELECOMMUNICATIONS

Figure 2.3.1-1 Path between Sum and Aimag Centre ..... 2-6

Figure 2.3.2.2-1 Mongolian Railway Company Fibre Optic Transmission Systems .... 2-13

### CHAPTER 3 DEMAND FORECAST

Figure 3.1.4-1 Affordable Payment..... 3-8

Figure 3.1.4-2 Deviation of Affordable Payment..... 3-9

Figure 3.1.4-3 Affordable Payment with Income..... 3-9

Figure 3.1.6-1 Apply of Growth rate of Macro Demand Density ..... 3-20

Figure 3.1.8-1 Relation of Average Income  
and Household Demand Density per Population ..... 3-29

Figure 3.1.8-2 Relation of Public and Business Organisation Demand Density  
and Population of Sum Centres ..... 3-30

Figure 3.2-1 Flow of Demand Forecast of Internet ..... 3-31

### CHAPTER 4 TECHNICAL PLAN

Figure 4.2.2-1 (1/2) Existing Switch Network - Uvurkhangai ..... 4-2

Figure 4.2.2-1 (2/2) Existing Switch Network - Selenge and Darkhan -Uul..... 4-2

Figure 4.2.3-1 (1/2) Proposed Switch Network - Uvurkhangai..... 4-4

Figure 4.2.3-1 (2/2) Proposed Switch Network - Selenge and Darkhan -Uul ..... 4-5

Figure 4.7-1 Demarcation Point 1 ..... 4-10

Figure 4.7-2 Demarcation Point 2 ..... 4-11

Figure 4.7-3 Demarcation Point 3 ..... 4-12

Figure 4.7-4 Demarcation Point 4 ..... 4-13

Figure 4.9.2.1-1 Proposed Power Supply Facilities  
for Microwave Repeater Station ..... 4-17

Figure 4.11-1 Typical Block Diagram for Power Supply Facilities ..... 4-24

Figure 4.12.1-1 IP Networking in Sum Area..... 4-25

### CHAPTER 5 FACILITIES PLAN

Figure 5.3.1-1 Digital Microwave Link Configuration for Uvurkhangai..... 5-9

Figure 5.3.2.2-1 FOTS Plan for Selenge/ Darhan-Uul Aimags..... 5-21

Figure 5.3.2.2-2 FOTS Plan for Uvurkhangai Aimag ..... 5-21

Figure 5.3.2.2-3 Demarcation point between MRC and MTC..... 5-22

Figure 5.4.1-1 Relation between Number of Lines and Cost/Line..... 5-26

Figure 5.5-1 Typical Power Receiving Plan..... 5-37

Figure 5.5-2 Stand-by Power Supply Plan ..... 5-38

---

|              |   |      |
|--------------|---|------|
| Figure 5.5-3 | Typical Power Supply Facility Plan.....                 | 5-38 |
| Figure 5.6-1 | An Idea of IT Network Configuration in Sum Centre ..... | 5-41 |

## LIST OF TABLES

### CHAPTER 1 INTRODUCTION

|             |   |      |
|-------------|---|------|
| Table 1.4-1 | Work Schedule of the Study .....  | 1-6  |
| Table 1.5-1 | List of JICA Study Team Members .....   | 1-8  |
| Table 1.5-2 | List of JICA Advisory Committee Members.....  | 1-8  |
| Table 1.5-3 | List of Project Officers of JICA Headquarters.....  | 1-9  |
| Table 1.5-4 | List of Counterparts .....  | 1-9  |
| Table 1.5-5 | List of Attendees Who Made Comments.....  | 1-10 |
| Table 1.5-6 | List of Members of Scientific and Technical Council of<br>Communication Sector (Non-executive) /STCCS/..... | 1-10 |

### CHAPTER 2 PRESENT STATUS OF TELECOMMUNICATIONS

|               |   |      |
|---------------|---|------|
| Table 2.2     | Socio-economic Profiles of the project Area.....            | 2-3  |
| Table 2.3.1-1 | Switch Capacity and Line in Use of Uvurkhangai.....         | 2-4  |
| Table 2.3.1-2 | Switch Capacity and Line in Use of Selenge/Darkhan-Uul..... | 2-5  |
| Table 2.3.1-3 | Sum Switch Facilities in Uvurkhangai .....                  | 2-7  |
| Table 2.3.1-4 | Sum Switch Facilities in Selenge and Darkhan Uul .....      | 2-8  |
| Table 2.3.3-1 | Sample Site Data by Field Survey .....                      | 2-15 |

### CHAPTER 3 DEMAND FORECAST

|                |  |      |
|----------------|--|------|
| Table 3.1.4-1  | Fixed Telephone and Mobile Demand in Sampled Household .....             | 3-5  |
| Table 3.1.4-2  | Income Brackets.....   | 3-6  |
| Table 3.1.4-3  | Selection of Telephone in Sampled Household.....                         | 3-6  |
| Table 3.1.4-4  | Redistribution rate of Telephone Selection “Both” .....                  | 3-6  |
| Table 3.1.4-5  | Shifting Mobile Demand to Fix Telephone Demand.....                      | 3-7  |
| Table 3.1.4-6  | Fixed demand without the consideration of Affordability.....             | 3-7  |
| Table 3.1.4-7  | Payment available rate in each Income bracket .....                      | 3-10 |
| Table 3.1.4-8  | Affordable Demand and Density per Household<br>in Sampled Household..... | 3-10 |
| Table 3.1.4-9  | Demand and Demand density in Sampled Business Company .....              | 3-10 |
| Table 3.1.4-10 | Demand and Demand density in Sampled Public Organisation .....           | 3-11 |
| Table 3.1.4-11 | Arranged Demand Density per Public Organisation.....                     | 3-11 |
| Table 3.1.4-12 | Arranged Demand Density per Business Company.....                        | 3-11 |
| Table 3.1.5-1  | Household Fix Present Demand .....                                       | 3-14 |
| Table 3.1.5-2  | Present Public Demand in Each Sum Centre.....                            | 3-15 |
| Table 3.1.5-3  | Present Business Demand in each Sum Centre .....                         | 3-16 |
| Table 3.1.5-4  | Present Mobile Demand in Each Sum Centre .....                           | 3-17 |
| Table 3.1.5-5  | Shifting Mobile Demand in Each Sum Centre .....                          | 3-18 |
| Table 3.1.5-6  | Fixed Telephone Total Present .....                                      | 3-19 |

|                                  |   |      |
|----------------------------------|---|------|
| Table 3.1.6-1                    | Fixed Telephone Demand (2002 to 2020) .....                                 | 3-22 |
| Table 3.1.6-2                    | Shifting Mobile Demand (2002 to 2020).....                                  | 3-23 |
| Table 3.1.6-3                    | Fixed Telephone Micro Demand including<br>Shifted Mobile Demand.....        | 3-24 |
| Table 3.1.7-1                    | Priority Sum Centre in Uvurkhangai Aimag .....                              | 3-25 |
| Table 3.1.7-2                    | Priority Sum Centre in Selenge Aimag.....                                   | 3-25 |
| Table 3.1.7-3                    | Priority Sum Centre in Darkhan-Uul Aimag .....                              | 3-25 |
| Table 3.1.7-4                    | Fulfilment Plan .....   | 3-26 |
| Table 3.1.7-5                    | Microscopic Demand Forecast in FS Project Areas .....                       | 3-27 |
| Table 3.1.7-6                    | New Subscriber Connection Plan .....  | 3-28 |
| Table 3.1.8-1                    | Comparison of Micro Demand and Macro Demand .....                           | 3-29 |
| Table 3.2-1                      | Number of Organisations in the Target Sums of F/S.....                      | 3-32 |
| Table 3.2-2                      | Internet Demand in the Target Sums of F/S .....                             | 3-33 |
| <b>CHAPTER 4 TECHNICAL PLAN</b>  |   |      |
| Table 4.3.4-1 (1/2)              | Required Number of Circuits - Uvurkhangai .....                             | 4-6  |
| Table 4.3.4-1 (2/2)              | Required Number of Circuits - Selenge and Darkhan-Uul.....                  | 4-7  |
| Table 4.4.2-1                    | Numbering Plan of Target Aimags .....                                       | 4-8  |
| Table 4.9-1                      | System Parameters.....  | 4-16 |
| Table 4.10.1-1                   | Electrical Standards of the Cables .....                                    | 4-18 |
| Table 4.12.2-1                   | Subscriber's Ratio in Each Phase .....                                      | 4-26 |
| Table 4.12.2-2                   | Internet Traffic in the Subjected Sums of F/S .....                         | 4-27 |
| <b>CHAPTER 5 FACILITIES PLAN</b> |   |      |
| Table 5.2.3-1 (1/2)              | Proposed Switching Capacity - Uvurkhangai .....                             | 5-3  |
| Table 5.2.3-1 (2/2)              | Proposed Switching Capacity - Selenge and Darkhan-Uul .....                 | 5-3  |
| Table 5.2.4-1                    | Switch Facilities Cost (CIF) .....  | 5-4  |
| Table 5.3.1-1                    | Transmission Link Configurations .....                                      | 5-6  |
| Table 5.3.1-2                    | Proposed 7 GHz P-P Digital Microwave<br>Trunk Transmission Lines .....      | 5-7  |
| Table 5.3.1-3                    | Transmission Link Configurations .....                                      | 5-10 |
| Table 5.3.1.3-1                  | Cost of Digital Microwave Radio Link System Uvurkhangai .....               | 5-13 |
| Table 5.3.1.3-2                  | Cost of Digital Microwave Radio Link System Selenge<br>and Darkhan Uul..... | 5-14 |
| Table 5.3.2.3-1                  | Bill of Quantity for Uvurkhangai Aimag.....                                 | 5-23 |
| Table 5.3.2.3-2                  | Bill of Quantity for Selenge/Dalkhan-Uul Aimags.....                        | 5-24 |
| Table 5.3.2.4-1                  | FOTS Cost Estimate (Total) .....  | 5-24 |
| Table 5.3.2.4-2                  | FOTS Cost Estimate for Uvurkhangai Aimag.....                               | 5-25 |
| Table 5.3.2.4-3                  | FOTS Cost Estimate for Selenge/ Dalkhan-Uul Aimags.....                     | 5-25 |
| Table 5.4.1-1                    | Bill of Quantity .....  | 5-26 |



|   |  |      |
|---|--|------|
| Table 5.4.1-2   | Number of Lines in F/S Project Sum Centres.....  | 5-27 |
| Table 5.4.2-6-1   | PMP/TDMA-WLL Project Cost (Uvurkhangai) .....  | 5-32 |
| Table 5.4.2-6-2   | PMP/TDMA-WLL Project Cost (Selenge and Darkhan-Uul).....   | 5-33 |
| Table 5.5-1   | Summary of Generators .....  | 5-39 |
| Table 5.6-1   | Kinds and Number of Apparatus at IT-spot in Sum Area .....   | 5-42 |
| Table 5.6-2   | Initial Cost of IT-spot in Sum Area .....  | 5-42 |
| <b>CHAPTER 6 PROJECT IMPLEMENTATION PLAN</b>                  |  |      |
| Table 6.1-1   | Overall Implementation Schedule for Rehabilitation<br>and Expansion Project for Rural Telecommunication System<br>in Mongolia (Quick Case).....                        | 6-3  |
| Table 6.1-2   | Overall Implementation Schedule for Rehabilitation<br>and Expansion Project for Rural Telecommunication System<br>in Mongolia (Normal Case) .....                      | 6-3  |
| Table 6.1-3   | Detailed Implementation Schedule for Rehabilitation<br>and Expansion Project for Rural Telecommunication System<br>in Mongolia (E/N is in the Beginning of Year) ..... | 6-4  |
| Table 6.1-4   | Detailed Implementation Schedule for Rehabilitation<br>and Expansion Project for Rural Telecommunication System<br>in Mongolia (E/N is in the Middle of Year) .....    | 6-5  |
| Table 6.1-5   | Overall Implementation Schedule for Rehabilitation<br>and Expansion Project for Rural Telecommunication System<br>in Mongolia.....                                     | 6-7  |
| Table 6.1-6   | Detailed Implementation Schedule for Rehabilitation<br>and Expansion Project for Rural Telecommunication System<br>in Mongolia.....                                    | 6-8  |
| <b>CHAPTER 7 OPERATION AND MAINTENANCE PLAN</b>               |  |      |
| Table 7.4-1   | Maintenance Material List .....  | 7-6  |
| Table 7.4-2   | Maintenance Equipment List .....   | 7-6  |
| Table 7.5-1   | QoS performance Indicator .....  | 7-7  |
| Table 7.5-2   | Target Fault ratio and Fault clearance rate.....   | 7-7  |
| Table 7.5-3   | Target Figure of Call completion rate.....   | 7-7  |
| <b>CHAPTER 8 HUMAN RESOURCE DEVELOPMENT AND TRAINING PLAN</b> |  |      |
| Table 8.1-1   | Number of Staff in Uvurkhangai .....   | 8-2  |
| Table 8.1-2   | Number of Staff in Darkhan-Uul .....   | 8-2  |
| Table 8.1-3   | Number of Staff in Selenge .....   | 8-3  |
| Table 8.2-1   | Summary of Training Plan.....  | 8-7  |
| Table 8.2-2   | Training Course and Number of Trainees .....   | 8-8  |

**CHAPTER 9 PROJECT COST ESTIMATION**

|             |   |     |
|-------------|---|-----|
| Table 9.4-1 | Project Cost Estimate.....                                  | 9-3 |
| Table 9.4-2 | Project Cost Estimate for Uvukhangai.....                   | 9-3 |
| Table 9.4-3 | Project Cost Estimate for Selenge/ Dalkhan-Uul Aimags ..... | 9-3 |

**CHAPTER 10 FINANCIAL EVALUATION**

|              |  |      |
|--------------|--|------|
| Table 10.1-1 | Revenues and Expenditures of Selected 5 Sums of Uvurkhangai .....          | 10-2 |
| Table 10.1-2 | Revenues and Expenditures of Selected Sums<br>of Selenge/Darkhan-Uul ..... | 10-2 |
| Table 10.2   | Subscriber Development Plan.....   | 10-4 |
| Table 10.3   | Summary of Income and Cash Flow Projection .....                           | 10-5 |
| Table 10.4-1 | Sensitivity-Revenue .....  | 10-6 |
| Table 10.4-2 | Sensitivity-O/M Cost .....   | 10-6 |
| Table 10.4-3 | Sensitivity-Investment Cost.....   | 10-7 |

### Acronyms

#### **A**

|       |  |
|-------|--|
| AC    | : Alternating Current                        |
| ADB   | : Asian Development Bank                     |
| ADM   | : Add-Drop Multiplexer                       |
| ADPCM | : Adaptive Differential PCM                  |
| ADS   | : Active Double Star                         |
| ADSL  | : Asymmetric Digital Subscriber Line         |
| AHEC  | : Agency Hygiene and Epidemiological Control |
| AMA   | : Automatic Message Accounting               |
| AMPS  | : Advanced Mobile Phone Service              |
| AN    | : Access Node                                |
| AP    | : Affordability Parity                       |
| ATC   | : Automatic Telephone Station                |
| ATIS  | : Automatic Terminal Information Service     |
| ATM   | : Asynchronous Transfer Mode                 |

#### **B**

|        |  |
|--------|--|
| B-ISDN | : Broad-band Integrated Services Digital Network |
| BOT    | : Build, Operate and Transfer                    |
| BRI    | : Basic Rate Interface                           |
| BRS    | : Base Radio Station                             |
| BSC    | : Base Station Controller                        |
| BSMS   | : Base Site Management System                    |
| BTS    | : Base Transceiver Station                       |

#### **C**

|       |   |
|-------|---|
| CAD   | : Computer Aided Design                               |
| CAGR  | : Compounded Annual Growth Rate                       |
| CAP   | : Carrierless Amplitude/Phase Modulation              |
| CAPEX | : Capital Expenditure                                 |
| CATV  | : Cable Television Service or Cable Television System |
| CBR   | : Constant Bit Rate                                   |
| CC    | : Country Code  |
| CCP   | : Cross-Connection Point                              |
| CCR   | : Call Completion Rate                                |
| CCS   | : Common Channel Signalling                           |
| CCT   | : Circuit   |
| CDMA  | : Code Division Multiple Access                       |

---

|                 |  |
|-----------------|--|
| CDR             | : Call Data Recording                  |
| Ch              | : Channel                              |
| CIC             | : Carrier Identification Code          |
| CIF             | : Cost, Insurance and Freight          |
| CLR             | : Circuit Loudness Rating              |
| CMTS            | : Cellular Mobile Telephone Service    |
| CO <sub>2</sub> | : Carbon Dioxide                       |
| C/P             | : Counterpart                          |
| CPE             | : Customer Premises Equipment          |
| CPI             | : Consumer Price Index                 |
| CPM             | : Critical Path Method                 |
| CR              | : Calling Rate                         |
| CRC             | : Communications Regulatory Commission |
| CRE             | : Corrected Reference Equivalent       |
| CS              | : Cell Station                         |
| CSS             | : Customer Service System              |
| CT              | : Central Terminal                     |
| CTC             | : Community Telephone-service Centres  |
| CUG             | : Closed User Group                    |

**D**

|        |   |
|--------|---|
| DAMA   | : Demand Assigned Multiple Access                     |
| D-AMPS | : Digital AMPS  |
| DC     | : Direct Current                                      |
| DCF    | : Discounted Cash Flow                                |
| DCME   | : Digital Circuit Multiplex Equipment                 |
| DCN    | : Data Communications Network                         |
| DDD    | : Domestic Direct Dialling or Distant Direct Dialling |
| DDF    | : Digital Distribution Frame                          |
| DEURAS | : Detect Unlicensed Radio Station                     |
| DF/R   | : Draft Final Report                                  |
| DG     | : Diesel Generator                                    |
| D/L    | : Distribution Line (Power)                           |
| DLC    | : Digital Loop Carrier                                |
| DMT    | : Discrete Multi-Tone                                 |
| DNC    | : Destination Network Code                            |
| DP     | : Distribution Point                                  |
| DRCS   | : Digital Radio Concentration System                  |
| DSMX   | : Analogue-Digital Conversion system                  |

---

|          |   |
|----------|---|
| DSP      | : Digital Signal Processing                       |
| DTMF     | : Dual-Tone Multi-Frequency Signalling            |
| <b>E</b> |   |
| E-10B    | : Type of Switch of Alcatel in France             |
| EA       | : Energy Authority of Mongolia                    |
| EAP      | : Economically Active Population                  |
| EC       | : Electronic Commerce                             |
| EC       | : Exchange Code                                   |
| EIA      | : Environmental Impact Assessment                 |
| EIRR     | : Economic Internal Rate of Return                |
| Erl      | : Erlang  |
| ERMES    | : European Radio Message System                   |
| ES       | : Erred Second                                    |
| ESR      | : Erred Second Ratio                              |
| EU       | : European Union                                  |
| EWSD     | : Type of Switch of Siemens in German             |
| Ex.      | : Telephone Exchange                              |
| <b>F</b> |   |
| FDI      | : Foreign Direct Investment                       |
| FDMA     | : Frequency Division Multiple Access              |
| FIFTA    | : Foreign Investment and Foreign Trade Agency     |
| FIRR     | : Financial Internal Rate of Return               |
| FIRROI   | : Financial Internal Rate of Return on Investment |
| FIRROE   | : Financial Internal Rate of Return on Equity     |
| FM       | : Facilities Management                           |
| FOB      | : Free On Board                                   |
| F/R      | : Final Report                                    |
| F/S, FS  | : Feasibility Study                               |
| FTR      | : File Transfer Protocol                          |
| FTTC     | : Fibre-To-The-Curve                              |
| FTTH     | : Fibre-To-The-Home                               |
| FTTO     | : Fibre-To-The-Office                             |
| FTTZ     | : Fibre-To-The-Zone                               |
| FWA      | : Fixed Wireless Access                           |
| FY       | : Fiscal Year                                     |
| <b>G</b> |   |
| GDP      | : Gross Domestic Product                          |
| GMSK     | : Gaussian Filtered Minimum Shift                 |

---

|      |   |
|------|---|
| GNI  | : Gross National Income                   |
| GNP  | : Gross National Product                  |
| GOJ  | : Government of Japan                     |
| GOM  | : Government of Mongolia                  |
| GOS  | : Grade of Service                        |
| GRDE | : Gross Regional Domestic Expenditure     |
| GRDP | : Gross Regional Domestic Product         |
| GSM  | : Global System for Mobile Communications |
| G/T  | : Gain/Temperature                        |
| GTZ  | : Gesellschaft fuer Technische Zusammen   |
| GW   | : Gateway                                 |

**H**

|       |  |
|-------|--|
| HDI   | : Human Development Index                    |
| HDSL  | : High-bit-rate Digital Subscriber Line      |
| HDTV  | : High Definition Tele Vision                |
| HF    | : High Frequency                             |
| HLR   | : Home Location Register                     |
| HRD   | : Human Resource Development                 |
| HRX   | : Hypothetical Reference Configuration       |
| HSD   | : High Speed Digital Transmission Service    |
| HSDLC | : High Speed Digital Leased Circuits Service |

**I**

|              |  |
|--------------|--|
| IAP          | : Internet Access Provider                                 |
| IBO          | : Input Back Off   |
| IC           | : Incoming   |
| ICP          | : Internet Content Provider                                |
| IC/R         | : Inception Report   |
| ICT          | : Information and Communication Technology                 |
| IDC          | : Insulation Displacement Contact                          |
| IDD          | : International Direct Dialling                            |
| IDR          | : Intermediate Digital Record                              |
| IMF          | : International Monetary Fund                              |
| IMT-2000     | : International Mobile Telecommunications 2000             |
| IN           | : Intelligent Network                                      |
| INMARSAT     | : International Maritime Satellite Organisations           |
| INTELSAT     | : International Telecommunications Satellite Organisations |
| INTERIX      | : Internet Index   |
| INTERSPUTNIK | : International Organisation of Space Communications       |

---

|          |   |
|----------|---|
| INTS     | : International Transit Switch  |
| IP       | : Internet Protocol   |
| IRR      | : Internal Rate of Return   |
| ISC      | : International gateway Switching Centre  |
| ISDN     | : Integrated Service Digital Network  |
| ISMC     | : International Switching Maintenance Centre  |
| ISO      | : International Standardization Organisation  |
| ISP      | : Internet Service Provider   |
| IT       | : Information Technology  |
| ITMC     | : International Transmission Maintenance Centre                                       |
| IT/R     | : Interim Report  |
| ITS      | : Integrated Transceiver System   |
| ITSP     | : Internet Telephony Service Provider   |
| ITU      | : International Telecommunications Union  |
| ITU-T    | : International Telecommunications Union<br>Telecommunications Standardization Sector |
| <b>J</b> |   |
| JBIC     | : Japan Bank of International Cooperation   |
| JEC      | : Standard of the Japanese Electro-technical Committee                                |
| JEM      | : The Standard of Japan Electrical Manufacture Association                            |
| J/V      | : Joint Venture   |
| JICA     | : Japan International Cooperation Agency  |
| JIS      | : Japanese Industrial Standard  |
| JP, JP ¥ | : Japanese Yen  |
| JTEC     | : Japan Telecommunications Engineering and Consulting<br>Service                      |
| <b>K</b> |   |
| KfW      | : Kreditanstalt für Wiederaufbau  |
| KT       | : Korean Telecom  |
| <b>L</b> |   |
| LAN      | : Local Area Network  |
| LDC      | : Less Developed Country  |
| LE       | : Local Exchange  |
| LLDC     | : Least among Less Developed Country  |
| LR       | : Loudness Rating   |
| LRE      | : Low Rate Encoding   |
| LSMS     | : Living Standard Measurement Survey  |
| LTM      | : Local Tandem Switch   |

**M**

|          |   |
|----------|---|
| MAP21    | : Mongolian Action Program for the 21th Century   |
| MC       | : Maintenance Centre  |
| MCAC     | : Mongolian Communications Asset Company  |
| MDC      | : Mongolian Data Company  |
| MDF      | : Main Distribution Frame   |
| MH       | : Manhole   |
| MIX      | : Mongolia Internet Exchange  |
| MOFA     | : Ministry of Food and Agriculture  |
| M/M      | : Minutes of Meeting  |
| MNDP     | : Mongolian National Democratic Party   |
| MOBIX    | : Mobile Index  |
| MOECS    | : Ministry of Education, Culture and Science  |
| MOFA     | : Ministry of Food and Agriculture  |
| MOFE     | : Ministry of Finance and Economics   |
| MOH      | : Ministry of Health  |
| MOI      | : Ministry of Infrastructure  |
| MOID     | : Ministry of Infrastructure Development (ex-MOI)                                       |
| MOIT     | : Ministry of Industry and Trade  |
| MONE     | : Ministry of Nature and Environment  |
| MOSSL    | : Ministry of Social Safety and Labour  |
| MOSTEC   | : Ministry of Science, Technology, Education and Culture                                |
| MOT      | : Ministry of Telecommunications (ex-MOI)   |
| MOT      | : Ministry of Telecommunications  |
| MOTB     | : Mongolian Tourism Board   |
| MP, M/P  | : Master Plan or Master Plan Study  |
| MPHPT    | : Ministry of Public management, Home Affairs, Posts and<br>Telecommunications of Japan |
| MRC, MRZ | : Mongolian Railway Company   |
| MRTC     | : Ministry of Roads, Transport and Communications                                       |
| MRTV     | : Mongolian Radio and Television  |
| MS       | : Mobile Station  |
| MS       | : Multiplex Section   |
| MSC      | : Mobile service Switching Centre   |
| MSDP     | : Mongolian Social Democratic Party   |
| MSU      | : Main Switch Unit  |
| MSU      | : Multi Subscriber Unit   |
| MT       | : Mini Terminal   |



---

|          |  |
|----------|--|
| MT       | : Mongolia Telecom                                     |
| MTB      | : Mongolian Tourism Board                              |
| MTC      | : Mongolian Telecommunications Company                 |
| MTBF     | : Mean Time Between Failure                            |
| MTSPS    | : Mongolian Telecommunications Sector Policy Statement |
| MTP      | : Message Transfer Part                                |
| MW       | : Microwave System                                     |
| <b>N</b> |  |
| NCC      | : New Common Carrier                                   |
| NCSM     | : national Centre for Standardisation and Meteorology  |
| NDC      | : National Destination Code                            |
| NDF      | : Nordic Development Fund                              |
| NE       | : Network Element                                      |
| NEAX-61  | : Type of Switch of NEC in Japan                       |
| N-ISDN   | : Narrow-band Integrated Services Digital Network      |
| NMS      | : Network Management System                            |
| NMC      | : National management Centre                           |
| NORAD    | : Norwegian Agency for Development Co-operation        |
| NOx      | : Nitrogen Oxide                                       |
| NP       | : Network Performance                                  |
| NPV      | : Net Present Value                                    |
| NSO      | : National Statistical Office of Mongolia              |
| NTC      | : National Transit Centre                              |
| NTT      | : Nippon Telegraph and Telephone Corporation           |
| <b>O</b> |  |
| OAM      | : Operation, Administration and Maintenance            |
| OAN      | : Optical Access Network                               |
| OBO      | : Output Back Off                                      |
| ODA      | : Official Development Assistance                      |
| ODF      | : Optical Distribution Frame                           |
| OECD     | : Organisation of Economic Cooperation Development     |
| OECF     | : Overseas Economic Cooperation Fund                   |
| OFC      | : Optical Fibre Cable                                  |
| OFTS     | : Optical Fibre Transmission System                    |
| OG       | : Outgoing   |
| OJT      | : On-the-Job Training                                  |
| OLR      | : Overall Loudness Rating                              |

---

|         |  |
|---------|--|
| OLT     | : Optical Line Termination             |
| OM, O&M | : Operation and Maintenance            |
| OMC     | : Operation and Maintenance Centre     |
| ONT     | : Optical Network Termination          |
| ONU     | : Optical Network Unit                 |
| OPEX    | : Operating Expenditure                |
| OPMC    | : Outside Plant Maintenance Centre     |
| OPS     | : Optical Power Splitter               |
| OQPSK   | : Offset Quadrature Phase Shift Keying |
| OS      | : Operation System                     |
| OSI     | : Open System Interconnection          |
| OSP     | : Outside Plant                        |

**P**

|           |  |
|-----------|--|
| PABX, PBX | : Private Automatic Branch Exchange or Private Branch Exchange |
| PAP       | : Poverty Alleviation Program                                  |
| PC        | : Personal Computer  |
| PC        | : Primary Centre   |
| PCI       | : Pacific Consultants International                            |
| PCM       | : Pulse Code Modulation  |
| PCM       | : Project Cycle Management                                     |
| PDC       | : Personal Digital Cellular                                    |
| PDH       | : Plesiochronous Digital Hierarchy                             |
| PDS       | : Passive Double Star  |
| PHS       | : Personal Handy-phone System                                  |
| PMP, P-MP | : Point-to-Multi Point   |
| POI       | : Point Of Interface   |
| PON       | : Passive Optical Network                                      |
| POTS      | : Plain Old Telephone Service                                  |
| PTP       | : Point-to-Point   |
| PPP       | : Purchasing Power Parity                                      |
| P/R       | : Progress Report  |
| PRC       | : Primary Reference Clock                                      |
| PRI       | : Primary Rate Interface                                       |
| PSC       | : Provisional Switching Centre                                 |
| PSTN      | : Public Switched Telephone Network                            |
| PTA       | : Post and Telecommunication Authority of Mongolia             |

---

|          |  |
|----------|--|
| PV       | : Photovoltaic   |
| PVC      | : Permanent Virtual Circuit  |
| <b>Q</b> |  |
| QA       | : Q Adapter  |
| QOS      | : Quality of Service   |
| QPSK     | : Quadrature Phase Shift Keying  |
| <b>R</b> |  |
| RE       | : Reference Equivalent   |
| RLR      | : Receive Loudness Rating  |
| RMC      | : Regional Management Centre   |
| RR       | : Radio Regulation   |
| RSU      | : Remote Subscriber Unit   |
| RT       | : Remote Terminal  |
| RU       | : Repeater Unit  |
| <b>S</b> |  |
| SASE     | : Stand Alone Synchronization Equipment  |
| SCF      | : Standard Conversion Factor   |
| SCPC     | : Single Channel Per Carrier   |
| SCR      | : Successful Call Rate   |
| SCR      | : Subscriber Radio System  |
| SDH      | : Synchronous Digital Hierarchy  |
| SDM      | : Space Division Multiplexing  |
| SDSL     | : Symmetric Digital Subscriber Line  |
| SDX-RB   | : Type of Switch in Korea  |
| SE       | : Secondary Centre   |
| SES      | : Severely Erred Second  |
| SESR     | : Severely Erred Second Ratio  |
| SFD      | : Saturation Flux Density  |
| SIM      | : Subscriber Identity Module   |
| SINPO    | : SINPO (Signal Interference Noise atmospheric Propagation disturbance Overall readability) Code |
| SL       | : Subscriber Line  |
| SLA      | : Service Level Agreement  |
| SLIC     | : Subscriber Line Interface Circuits   |
| SLR      | : Send Loudness Rating   |
| SME      | : Small and Medium Enterprise  |
| SN       | : Subscriber Number  |
| SO       | : Service Order  |

---

|                |   |
|----------------|---|
| SOHO           | : Small Office/Home Office  |
| SOx            | : Sulphuric Oxide   |
| SS             | : Single Star   |
| SSC            | : Secondary Switching Centre  |
| SS7            | : Signalling System No7   |
| SSU            | : Single Subscriber Unit  |
| SSU            | : Synchronization Supply Unit   |
| STD            | : Subscriber Trunk Dialling   |
| STM            | : Synchronous Transfer Mode   |
| STP            | : Signal Transfer Point   |
| STP            | : Switched Transit Plan   |
| STS            | : Site Transmission System  |
| SU             | : Subscriber Unit   |
| SUS            | : Site Utility System   |
| SV             | : Supply Volume   |
| SW             | : Switch or Switching   |
| S/W            | : Scope of Work   |
| SWOT           | : Strength, Weakness, Opportunity and Threat (Analysis)                 |
| <b>T</b>       |   |
| TC             | : Trunk Code  |
| TCU            | : TDM Control Unit  |
| TDD            | : Time Division Duplex  |
| TDM            | : Tandem  |
| TDMA           | : Time Division Multiple Access   |
| Tg.            | : Tugirg (Mongolian Currency Unit)                                      |
| TLS            | : Toll and Local Switch   |
| TMN            | : Telecommunications Management Network                                 |
| TQC            | : Total Quality Control   |
| T/R            | : Terms of Reference  |
| <b>U</b>       |   |
| UHF            | : Ultra High Frequency  |
| UNDP           | : United Nations Development Program                                    |
| UNESCO         | : United Nations Educational , Scientific, and Cultural<br>Organisation |
| UR             | : Unavailability Ratio  |
| USD, US\$, US¢ | : United States Dollar, United States Cent                              |
| UB             | : Ulaanbaatar   |
| <b>V</b>       |   |

---

|          |  |
|----------|--|
| VAT      | : Value Added Tax                            |
| VBR      | : Variable Bit Rate                          |
| VDSL     | : Very high-bit-rate Digital Subscriber Line |
| VDU      | : Visual Display Unit                        |
| VHF      | : Very High Frequency                        |
| VGT      | : Voice Grade Transmission Service           |
| VLR      | : Visitors' Location Register                |
| VOD      | : Video On Demand                            |
| VoIP     | : Voice-over-IP                              |
| VPN      | : Virtual Private Network                    |
| VSAT     | : Very Small Aperture Terminals              |
| <b>W</b> |  |
| WAC      | : WLL Access Controller                      |
| WAN      | : Wide Area Network                          |
| WAP      | : Wireless Application Protocol              |
| W-CDMA   | : Wide-band Code Division Multiple Access    |
| WCS      | : WLL Cell Station                           |
| WDM      | : Wavelength Division Multiplexing           |
| WLL      | : Wireless Local Loop                        |
| WP       | : Working Paper                              |
| WRC      | : World Radio communication Conference       |
| WS       | : Work Station                               |
| WSU      | : WLL Subscriber Unit                        |
| WTO      | : World Trade Organisation                   |
| WTX      | : Wireless Telephone Exchange                |
| WWF      | : World Wide Fund for Nature Conservation    |
| WWW      | : World Wide Web                             |
| <b>X</b> |  |
| XB       | : Crossbar Switch                            |
| xDSL     | : Digital Subscriber Line                    |
| <b>Y</b> |  |
| <b>Z</b> |  |
| ZUD      | : Natural Disaster                           |

## **CHAPTER 1**

### **INTRODUCTION**

---

## **CHAPTER 1**

### **INTRODUCTION**

#### **1.1 Background of the Priority Projects**

##### **1.1.1 General**

Recognising that the rural telecommunications network development is essential to improve such basic needs of life as education, medical care, etc., and in consideration of the gap found between the urban and rural areas, the Government of Mongolia intends to establish a telecommunications network which could contribute to life level improvement in the rural areas and the local economic development. The rural telecommunications network development is an important theme of the country to be placed under the international assistance.

The network in the rural areas, especially those of the level lower than the capital Ulaanbaatar and Aimag centres, remains intact. The telecommunications facilities are composed of aged analogue switches, microwave radio links, and open wires transmission links introduced by Russia in 1980's. The poor quality of communication of such telecommunications facilities could be a reason bringing about isolation from modern society. The telephone line density in the rural areas was only 2.27 lines per 100 inhabitants as of December 2001 (except for the capital Ulaanbaatar and major cities of Darhan Uul, Orhon, Baganuur and Nalaikh) and the mobile telephone was not available there at all.

Mongolia is a vast country with sparse population. Commercial investment to the rural areas is very difficult, even latest technologies are applied, for such conditions. It is essential for the Government of Mongolia, where it wishes to realise the development of the telecommunications network in such rural areas as a long term target, counts on the possibility of various funding schemes including state expenditure, international loan, and/or contribution of monopolised operator.

In such context, the Government of Mongolia requested the Government of Japan to conduct a master plan study for development of rural telecommunications network which covers the whole rural areas of the country, and contributes to the development in the rural areas. In reply to the request, JICA dispatched a preliminary study team in September 2001 and concluded Scope of Work and Minutes of Meeting.

### **1.1.2 Objectives of the Study**

The objectives of this Master Plan Study are categorised into Phase-I and Phase-II Studies as follows:

- **Phase-I Study**

To formulate a long-term plan up to the year 2020 for the development of the rural telecommunication system covering the whole Mongolian territory.

- **Phase-II Study**

To conduct a feasibility study on the priority project(s) identified in consequence of the Phase-I Study.

This Volume-III of the Study Report covers a Feasibility Study for priority projects in three (3) Aimags selected from an urgent development program in the Master Plan for the development of telecommunications networks in Mongolia up to the year 2020. The priority projects aim to be completed by the year 2008. The feasibility study as Phase-II Study has been carried out in accordance with the work plan and schedule of the study which were discussed and agreed upon between MOI/PTA and JICA. The study work has been done both in Mongolia and in Japan. The major items of the feasibility study are referred to in the following:

The Feasibility Study in Mongolia (1 September - 30 October 2002)

- (a) Explanation and discussion of the Interim Report;
- (b) Decision of objective priority projects for feasibility study;
- (c) Collection of data and information regarding priority projects from a view of both technical and socio-economic points;
- (d) Field survey for objective priority projects;
- (e) Preparation of scope of work for objective priority projects;
- (f) Preparation of a working paper of basic conditions and basic facilities design for feasibility study;
- (g) Explanation and discussion of scope of work for objective priority projects; and
- (h) Technology transfer through field survey and project basic design.

The Feasibility Study in Japan (15 November - 28 November 2002)

- (a) Technical specifications for projects;



- (b) Operation and maintenance plan required for facilities after completion of feasibility study projects;
- (c) Manning plan required for facilities after completion of feasibility study projects;
- (d) Organization plan required after completion of feasibility study projects;
- (e) Financial plan for feasibility study projects;
- (f) Evaluation of feasibility study projects;
- (g) Implementation programme of urgent need projects;
- (h) Preparation of human resources development plan;
- (i) Recommendations; and
- (j) Preparation of the Draft Final Report consisting of master plan and feasibility study.

## **1.2 Selection of Priority Projects for Feasibility Study**

### **1.2.1 Selection of Priority Projects**

In the Phase-I Study for preparing a Master Plan, a project implementation plan up to the year 2020 was prepared. The project implementation plan consists of short-term, medium-term and long-term plans. The priority projects for the feasibility study were selected from the short-term plan as an urgent programme consisting of projects in 21 Aimags, which aims to meet rapidly growing telephone demand and to catch up 100% fulfilment to the waiting demand in the top priority Sums by the year 2008. The details of the project formation and selection of the priority projects for the feasibility study are referred to in Chapter 16 of Volume-II. The following figures 1.2-1 shows a flow of project formation:

### **1.2.2 Priority Projects and Projects Site Selected for Feasibility Study**

Through the discussion between MOI/PTA and JICA Study Team in the beginning of September 2002, it was agreed that the feasibility study for the rehabilitation and expansion of the rural telecommunications system was conducted in the following Aimags during the Second Study in Mongolia:

- (a) Uvurkhangai;
- (b) Selenge; and
- (c) Darkhan-Uul

Selection of Uvurkhangai Aimag was the top Aimag as the result of the rural development priority in Chapter 16 of Volume-III. Selection of Selenge and Darkhan-Uul Aimag was the top Aimag as the urgent rural development needs such as the mergence of two Aimag, the establishment of free trade zone, the biggest granary area in Mongolia, the utilisation of the existing digital microwave and optical fibre cable system.




Figure 1.2-1 A Flow of Project Formation

### 1.3 Precondition of the Feasibility Project

#### 1.3.1 General

Up the present, private participation in the telecommunications services has been promoted in Mongolia. In addition, the fixed telephone services, the mobile telephone services and the international telecommunications services are opened to private operators under the telecommunications policy in Mongolia. In those circumstances, there will be

difficulty to make detailed planning and design in the feasibility study without any precondition, because the network configuration and supply volume, etc., will be unforeseeable depending on business strategies of respective private operators. Accordingly this feasibility study is carried out in consideration of the following:

- Participation of Fixed, WLL (Wireless Local Loop), Mobile, International Telecommunications and Internet Services Private Operators
- Microscopic Demand Forecast for Feasibility Study

### **1.3.2 Impacts by Participation of Private Operators**

By participation of fixed, WLL, mobile, international telecommunications, Internet services private operators, the feasibility study is carried out taking into account:

- (a) Quicker network expansion by both PTA/MT and private operators will bring higher telephone DEL supply speed.
- (b) The higher supply speed will bring more expressed demand by activating suppressed demand.
- (c) By sound competition among PTA/MT and private operators, including mobile telephone operators, international telecommunications operators, and Internet services providers, various qualities service will be much improved.
- (d) Corporate efficiency of PTA/MT will be much improved by the competition.
- (e) A burden for the Government in the telecommunications sector will be reduced.

Considering the above, this feasibility study is carried out on condition that the future telephone demand consists of satisfied demand (DEL) + registered waiters + suppressed demand.

### **1.3.3 Microscopic Demand Forecast for Feasibility Study**

By participation of fixed, WLL, mobile, international telecommunications, Internet services private operators, the feasibility study is carried out on condition that:

- (a) Telephone demand forecast obtained from the microscopic demand forecast approach, which basic data collection was carried out by individual enquiries and answers through site survey, was used for the facilities planning under the feasibility study.

- (b) The mobile telephone demand in Sum centres during un-available mobile telephone services period was shifted into the fixed telephone demand.
- (c) WLL demand in Sum centre was considered as a part of the fixed demand forecast, because WLL services is limited in the capital city only.
- (d) The demand forecast in some Sum centres, in which MT withdrew, was not considered in the facilities planning under the feasibility study.

#### 1.4 Work Schedule for the Feasibility Study

##### 1.4.1 Overall Time Schedule

The Study period consisting of Phase-I and Phase-II Study is from the end of March 2002 up to the middle of February 2003. The time schedule of this Study is shown in Table 1.4-1. The feasibility study was carried out in the period of the Second Study in Mongolia and the Second Work in Japan.

**Table 1.4-1 Work Schedule of the Study**

| Study Stages                     | 2002               |           | 2003     |
|----------------------------------|--------------------|-----------|----------|
| First Study in Mongolia          | 3.5M               |           |          |
| First Work in Japan              |                    | 2M        |          |
| Second Study in Mongolia         |                    |           | 2M       |
| Second Work in Japan             |                    |           | 1.5M     |
| Discussion of Draft Final Report |                    |           | 2W       |
| Preparation of Final Report      |                    |           | 1.5M     |
| Submission of Report             | IC/R P/R           | IT/R W/P  | DF/R F/R |
| IC/R:                            | Inception report   | M: Months |          |
| P/R:                             | Progress Report    | W: Weeks  |          |
| IT/R:                            | Interim Report     |           |          |
| DF/R:                            | Draft Final Report |           |          |
| F/R:                             | Final Report       |           |          |

##### 1.4.2 Progress in the Second Study in Mongolia

During the Second Study in Mongolia from September 1 to October 30, 2002, the Study Team carried out the following work together with counterparts:

- (a) Explanation and discussion of Interim Report submitted from the study team;
- (b) Selection of priority projects for feasibility study
- (c) Collection of data and information for feasibility study;
- (d) Field survey for priority projects selected for feasibility study;

- (e) Preparation of a working paper of basic conditions and basic facilities design for feasibility study and outline of project scope;
- (f) Technology transfer through field survey and project basic design;
- (g) Explanation and discussion of basic conditions of feasibility study and outlines of project scope.

### **1.4.3 Progress in the Second Work in Japan**

During the Second Work in Japan from November 15 to November 28, 2002, the Study Team prepared a draft final report consisting of a master plan and feasibility study. The Study Team carried out the following work:

- (a) Modification of the master plan submitted as Interim Report;
- (b) Basic design and cost estimate for the priority project selected for the feasibility study;
- (c) Evaluation of the objective priority projects selected for the feasibility study;
- (d) Preparation of a draft final report consisting of a master plan study and feasibility study.

## **1.5 The Study Team and the Parties Concerned**

### **1.5.1 JICA Study Team**

JICA Study Team members participated in the Second Study in Mongolia are listed in the following Table 1.5-1.

### **1.5.2 Counterpart from Mongolian Side**

Counterparts from Mongolian side officially assigned and participated in this Study are listed in the following Table 1.5-2. In addition, many officers other than mentioned in the table below have co-operated to the study team through the study period.

### **1.5.3 JICA Advisory Committee**

Member of JICA advisory committee and project officers of JICA Headquarters are listed in the following Table 1.5-3 and 1.5-4, respectively.

**Table 1.5-1 List of JICA Study Team Members**

| Name of Member       | Duty-in-charge   | Belonging to |
|----------------------|--|--------------|
| Mr. MITSUHASHI Hideo | Team Leader, Telecommunication Services  | JTEC         |
| Mr. KUBO Katsuhei    | Socio-Economic and Financial Analysis  | JTEC         |
| Mr. KUSANO Makine    | Rural Development  | PCI          |
| Mr. UCHIYAMA Suzuo   | Demand Forecast  | JTEC         |
| Mr. ISHIHARA Yasuo   | Network Planning, Traffic Forecast, Switching System                               | JTEC         |
| Mr. ISHIGAKI Hideaki | Radio System, International Facility Plan, Radio Frequency Management              | JTEC         |
| Mr. OKAMOTO Masazumi | Outside Plant Plan (Cable Work, Civil Work and Subscriber Terminal)                | JTEC         |
| Mr. HOSODA Tomio     | Transmission Network Plan, Transmission Facility Plan                              | JTEC         |
| Mr. KASAI Takashi    | Power Plant Facility Plan  | PCI          |
| Mr. MIHARA Noboru    | IT Network Plan, IT Demand Forecast  | PCI          |
| Mr. MARUYAMA Iwao    | Operation and Maintenance Plan   | JTEC         |
| Mr. TANAKA Makoto    | Organisation and Management Plan, Human Resource Development Plan, Institute Issue | JTEC         |
| Mr. NEGISHI Yukio    | Administrative Support   | JTEC         |
| Ms. ABIKO Sanae      | Interpreter  | JTEC         |

Note: JTEC: Japan Telecommunications Engineering and Consulting Services

PCI: Pacific Consultants International

**Table 1.5-2 List of JICA Advisory Committee Members**

| Name             | Duty-in-charge                        | Affiliated to  |
|------------------|---------------------------------------|--|
| SHIOYA Junichi   | Chairman<br>Telecommunication Policy  | Deputy Director,<br>International Cooperation<br>Division, Telecommunications<br>Bureau, Ministry of Public<br>Management, Home Affairs,<br>Posts and Telecommunications               |
| ISHIZUKA Hiroshi | Member<br>Rural Communication<br>Plan | Assistant Director, Technology<br>Policy Division, Information and<br>Communications Policy Bureau,<br>Ministry of Public Management,<br>Home Affairs, Posts and<br>Telecommunications |

**Table 1.5-3 List of Project Officers of JICA Headquarters**

| Name            | Duty-in-charge  | Affiliated to   |
|-----------------|-----------------|---|
| ENDO Hiroaki    | Project Officer | Second Development Study Division<br>Social Development Study Department,<br>Japan International Co-operation<br>Agency |
| OKUDA Hisakatsu | Project Officer | Second Development Study Division<br>Social Development Study Department,<br>Japan International Co-operation<br>Agency |

**Table 1.5-4 List of Counterparts**

| Duty-in-charge   | Name                | Affiliated to |
|--|---------------------|---------------|
| Chairman (Leader)  | Mr. N. Nansaljav    | PTA           |
| Socio-Economic and Financial Analysis  | Mr. T. Ganbat       | PTA           |
|  | Mr. N. Norovjav     | PTA           |
| Rural Development  | Mr. D. Naranbayar   | MT            |
|  | Ms. N. Bolormaa     | PTA           |
| Demand Forecast  | Mr. Ts. Usukhbayar  | PTA           |
| Network Planning, Traffic Forecast,<br>Switching System                                  | Mr. N. Bilgee       | PTA           |
|  | Mr. B. Davaatseren  | PTA           |
| Radio System, International Facility Plan,<br>Radio Frequency Management                 | Mr. M. Naranbaatar  | CRC           |
| Outside Plant Plan (Cable Work, Civil<br>Work and Subscriber Terminal)                   | Ms. Uugantsetseg    | PTA           |
|  | Mr. S. Tugsbileg    | PTA           |
| Transmission Network Plan, Transmission<br>Facility Plan                                 | Mr. N. Baatarsuren  | PTA           |
|  | Mr. Ch. Davaajav    | PTA           |
| Power Plant Facility Plan  | Mr. D. Agchbayar    | PTA           |
| IT Network Plan, IT Demand Forecast  | Mr. Ch. Zolbayar    | PTA           |
|  | Mr. G. Enkhbayar    | PTA           |
| Operation and Maintenance Plan   | Mr. T. Ochir        | PTA           |
|  | Mr. D. Tserenchimed | PTA           |
| Organisation and Management Plan,<br>Human Resource Development Plan,<br>Institute Issue | Mr. Ts. Bold        | PTA           |
|  | Mr. B. Amgalanbat   | MOI           |

**Table 1.5-5 List of Attendees Who Made Comments**

| Name                | Affiliated to | Duty in Charge   |
|---------------------|---------------|--|
| Mr. G. Basanjav     | MOI           | Director, Policy and Coordination Department of Road, Transport, Information, Communication and Tourism (PCDRTICT) |
| Mr. N. Naranmandakh | MOI           | Senior Officer, PCDRTICT   |
| Mr. G. Battur       | PTA           | General Director   |
| Mr. B. Davaastseren | PTA           | Deputy Director General  |
| Mr. O. Battogtokh   | CRC           | Deputy Director General  |
| Mr. B. Baatar       | CRC           | Director   |
| Ms. U. Tamir        | CRC           | Director   |
| Mr. M. Mend-Ochir   | CRC           | Director   |
| Mr. N. Bolor        | MT            | Technical Director   |

**Table 1.5-6 List of Members of Scientific and Technical Council of Communication Sector (Non-executive) /STCCS/**

| Name               | Degrees                      | Duty in Charge     |
|--------------------|------------------------------|--------------------|
| Mr. B. Sukhbaatar  | Sc. D., Prof, CEng.          | Director of STCCS  |
| Mr. Ts. Bold       | Ph. D., Assist. Prof.        | Secretary of STCCS |
| Mr. N. Nansaljav   | Ph. D., Asisst. Prof., CEng. | Member of STCCS    |
| Mr. G. Tsogbadrakh | Ph. D. Prof., CEng.          | Member of STCCS    |
| Mr. B. Damdinsuren | Ph. D., Prof., CEng.         | Member of STCCS    |
| Mr. L. Batkhisig   | Ph. D., CEng.                | Member of STCCS    |
| Ms. G. Bayarsuren  | Ph. D.                       | Member of STCCS    |
| Mr. I. Norovjav    | M. Sc.                       | Member of STCCS    |



## **CHAPTER 2**

### **PRESENT STATUS OF TELECOMMUNICATIONS**

---

## CHAPTER 2

### PRESENT STATUS OF TELECOMMUNICATIONS

#### 2.1 General

The telecommunications network in target area is exploited by MT, MRC, Mobicom, and Skytel. MT provides fixed line telephone service in Aimag centres, Sum centres, and some Bags. MRC provides fixed line telephone service in the settlements along the railway. Mobicom and Skytel provide mobile phone service in the Aimag centres and a few Sum centres. Internet service is available through dial-up connection in Aimag centres and in some Sum exchanges connected through digital inter-exchange link.

All of the Sum centres are provided with telephony service. The number of MT subscriber lines is 3,000 in Uvurkhangai, 3,329 in Selenge, and 5,871 in Darkhan-Uul as of August 2002. Forty-six (46) MT exchanges were counted in the target three (3) Aimags. Most of them have only several dozen subscriber lines, but Kharkhorin, Zuunkharaa, and Khutul exchanges have several hundred subscriber lines.

The physical transmission network is made up with digital microwave transmission system, optical fibre transmission system, open-wire transmission system, and metallic cables of subscriber access network. The MT switching systems in Aimag centres are digital, and those in Sum centres are mostly analogue and others are digital PBXs.

#### 2.2 Socio-economic Status of the Project Area

##### (1) General

The project Area, consisting of 10 selected Sums in Uvurkhangai Aimag and 12 selected Sums in Selenge/Darkhan-Uul Aimags area, currently has a total of 3,242 rural telephone subscribers (1,274 in Uvurkhangai and 1,968 in Selenge/Darkhan-Uul) that corresponds to 2.5% of the national base fixed telephone subscribers. This composition ratio, according to the feasibility study plan, would once reach some 3.3% in 2006 taking in those transferred from mobile telephone and would become stabilised at 2.8% in the long-range. The number of telephone subscribers in the project Area would reach 10,410 in 2020, the target year for both of the Feasibility Study and the Master Plan.

Upon reviewing the main issues and development directions of regional and rural development activities being elaborated, formulated or implemented in the country under the policy as approved by the parliament in June 2001 (See Chapter 2 of the Master Plan), the Study Team made a comparative evaluation among the five economic regions and the comprising Aimags in each region on the grounds of rural development potential and key economic factors to support its selection of the candidate sites of the feasibility study having high telecommunications development priority.

As a result, Khangai region, followed by Central region, was selected as the top priority region and Uvurkhangai was ranked at the top priority Aimag concurrently with Arkhangai Aimag, and Selenge Aimag was among the four second ranking Aimags in the Central region.

Socio-economic profiles of the project Area is shown in Table 2.2

## (2) Socio-economic profiles

Table 2.2 Socio-economic Profiles of the project Area

|                            | Population 2001        |                         |                                 | GRDP<br>2001<br>Current Price<br>(Tg.mln) | Household<br>2001<br>Sum Centre<br>(households) |
|----------------------------|------------------------|-------------------------|---------------------------------|---|---|
|                            | Total Sum<br>(persons) | Sum Centre<br>(persons) | Other<br>Than S.C.<br>(persons) |   |   |
| <b>Uvurkhangai</b>         |                        |                         |                                 |   |   |
| Burd                       | 3,896                  | 607                     | 3,289                           | 0   | 0   |
| Bat-Ulzii                  | 5,750                  | 1,837                   | 3,913                           | 0   | 649   |
| Bayangol                   | 4,747                  | 896                     | 3,853                           | 98.3                                      | 173   |
| Esunzuil                   | 3,820                  | 1,003                   | 2,817                           | 898.4                                     | 244   |
| ZB Ulaan                   | 5,106                  | 669                     | 4,437                           | 0   | 253   |
| Nariinteel                 | 4,279                  | 1,386                   | 2,893                           | 6.1                                       | 339   |
| Sant                       | 3,878                  | 730                     | 3,148                           | 8.9                                       | 170   |
| Uyanga                     | 7,824                  | 1,343                   | 6,481                           | 679.2                                     | 394   |
| Khuzirt                    | 0                      | 0                       | 0                               | 151.7                                     | 2,193   |
| Kharkhorin                 | 13,444                 | 8,523                   | 4,921                           | 69.9                                      | 3,453   |
| Total                      | 55,645                 | 15,757                  | 39,888                          |   | 8,025   |
|                            | 100%                   | 28.3%                   | 71.7%                           |   |   |
| <b>Selenge/Darkhan-Uul</b> |                        |                         |                                 |   |   |
| khutul                     | 8,755                  | 6,596                   | 2,159                           | 0   | 2,068   |
| Zuunkharaa                 | 22,304                 | 15,461                  | 6,843                           | 14,036                                    | 3,597   |
| Bayangol                   | 5,261                  | 3,580                   | 1,681                           | 2,440                                     | 1,182   |
| Tunkhel                    | 3,526                  | 3,526                   | 0                               | 0   | 710   |
| Shariin gol                | 8,619                  | 7,722                   | 897                             | 9,778                                     | 2,131   |
| Altanbulag                 | 3,812                  | 3,206                   | 606                             | 327.8                                     | 710   |
| Eruu                       | 3,130                  | 2,745                   | 655                             | 1,200                                     | 681   |
| Zuunburen                  | 2,245                  | 1,998                   | 247                             | 161.3                                     | 396   |
| Sant                       | 2,053                  | 1,601                   | 452                             | 62.5                                      | 532   |
| Tsuganuur                  | 4,326                  | 3,073                   | 1,253                           | 110.6                                     | 976   |
| Orkhontuul                 | 4,002                  | 3,500                   | 502                             | 385.6                                     | 878   |
| Shaamar                    | 4,409                  | 3,426                   | 983                             | 144.2                                     | 1,030   |
| Total                      | 72,442                 | 56,164                  | 16,278                          |   | 33,595  |
|                            | 100%                   | 77.5%                   | 22.5%                           |   |   |

## 2.3 Existing Facilities and Services

### 2.3.1 Switching System

#### (1) Uvurkhangai Aimag

The Sum centres are all furnished with telephony service. There are 11 analogue switch units and 7 digital switch units in Uvurkhangai Aimag for the telephony service. Out of the 19 Sum centres, Bayan-Undur is not furnished with switching unit but the telephone service is provided through a distant subscriber line from the Aimag centre. The Bayan-Undur had formerly an analogue switching unit, but it was removed as power was not supplied for a long time and not working.

Total switch capacity is 4,008 lines, including 1,760 lines of Aimag centre, as of September 2002.

**Table 2.3.1-1 Switch Capacity and Line in Use of Uvurkhangai**

| Aimag/Sum    | Switch Capacity | Lines in use |
|--------------|-----------------|--------------|
| Aimag centre | 1,760           | 1,644        |
| Sum centres  | 2,248           | 1,356        |
| Total        | 4,008           | 3,000        |

#### (2) Selenge and Darkhan-Uul Aimags

The Administrative limit does not coincide completely with the service area of MT Telecomm Centres. Some Sum/Bag centres of Selenge Aimag fall into Darkhan-Uul Telecom Centre service area.

Total number of Sum/Bag centres in Selenge and Darkhan Uul Aimag where the exchange is installed is 22 in total. Telephony service of Tunkhel (Selenge) and Salkhit (Darkhan-Uul) are not provided with MT exchanges, but with MRC exchanges.

The existing Sum switching systems are analogue and digital, that is, 17 analogue units and 5 digital units. Total switch capacity is 11,980 lines, including 8,272 lines of Aimag centre, as of September 2002.

**Table 2.3.1-2 Switch Capacity and Line in Use of Selenge/Darkhan-Uul**

| Aimags/Sum   | Switch Capacity | Lines in use |
|--------------|-----------------|--------------|
| Aimag centre | 8,272           | 7,020        |
| Sum centres  | 3,709           | 2,647        |
| Total        | 11,980          | 9,427        |

**(3) Aimag Centre Switch**

Arvaikheer (Uvurkhangai) Aimag centre switching unit is a digital, which is a product of Germany. It is "SDE", a family of EWSD digital switching system of Siemens. It was installed in 1997 and its capacity is 1,760 subscriber lines. A total of 1,644 subscriber lines are in use and the spare is only 116 lines. The SDE has two (2) 2Mbps links with Ulaanbaatar, one is connected to EWSD and another to E-10B. The SDE is running satisfactorily.

The Arvaikheer Aimag centre switching system capacity shall be expanded synchronising with accommodation of new Sum centre switching units. The existing Aimag centre switching system is almost fully used. It shall be expanded in capacity of inter-exchange circuits, as well as traffic capacity of call handling.

Sukhbaatar (Selenge) Aimag centre switching unit is a digital, which is a product of Germany. It is "SDE", a family of EWSD digital switching system of Siemens. It was installed in 1997 and its capacity is 1,888 subscriber lines. A total of 1,376 subscriber lines are in use and the spare is only 504 lines. The SDE has three (3) 2Mbps links with Ulaanbaatar, that is, to EWSD, E10-B and MRC switch, and one (1) 2Mbps link with Darkhan. The SDE is running satisfactorily.

The Sukhbaatar Aimag centre switching system capacity shall be expanded synchronising with accommodation of new Sum centre switching units. The existing Aimag centre switching system will not be enough to accommodate new switches in Sum centres. It shall be expanded in capacity of inter-exchange circuits, as well as traffic capacity of call handling.

Darkhan-Uul Aimag centre switching unit is a digital, which is a product of Germany. It is "EWSD" digital switching system of Siemens installed in New Darkhan, which has a Remote Switch Unit (RSU) in Old Darkhan. The host and RSU were installed in 1997. The host switch capacity is 4,384 subscriber lines and that of RSU is 2,000 subscriber lines. A total of 5,644 (3,917 of Host switch + 1,727 of RSU) subscriber lines are in use and the spare is only 740 lines. The SDE host switch has ten (10) 2Mbps links in total. The EWSD is running satisfactory.


The Darkhan-Uul Aimag centre switching system capacity shall be expanded synchronising with accommodation of new Sum centre switching units. The existing Aimag centre switching system will not be enough to accommodate new switches in Sum centres. It shall be expanded in capacity of inter-exchange circuits, as well as traffic capacity of call handling.

**(4) Sum/Bag Centre Switch**

In Uvurkhangai Aimag, Sum centres have respectively a switching system, except Bayan-Undur where a switching system was removed in 2001 as power supply was suspended for a long time. The switching systems are C12/48, ATCK50/200, KXTD, EM-48, and others. Sum centre exchanges have difficulties in maintenance due to out-moded product, faulty hardware, spare parts purchase delay, etc. Some exchanges are running only winter seasons due to insufficient power supply in summer.

In Selenge Aimag and Darkhan-Uul, Sum centres have respectively a switching system. The switching systems are HICOM, C12/48, ATCK50/200, KXTD, and others. Sum centre exchanges have difficulties in maintenance due to out-moded product, faulty hardware, spare parts purchase delay, etc. MT has withdrawn from telecommunication service in Salkhit Bag centre since June 2001 and Tunkhel since March 2002. The Dulaankhaan Bag centre switch is of a capacity of 100 subscriber line and has only five (5) subscribers.

Most of Sum centre switches are PBXs which are not connected directly with Aimag centre switch, but connected by means of distant subscriber line which is terminated by a telephone apparatus at the Sum centre. Accordingly, the trunk call services are realised through operator assistance. Figure 2.3.1-1 shows a connection pattern between PBX in Sum centre and local switch in Aimag centre.



**Figure 2.3.1-1 Path between Sum and Aimag Centre**

Table 2.3.1-3 and Table 2.3.1-4 show the switching facilities including trunk call service mode in Uvurkhangai Aimag and Selenge/Darkhan Uul Aimag, respectively.

**Table 2.3.1-3 Sum Switch Facilities in Uvurkhangai**

| No. | Aimag/Sum            | Switching Facilities |      |              | Working Conditions |              | Trunk Call Service |               |
|-----|----------------------|----------------------|------|--------------|--------------------|--------------|--------------------|---------------|
|     |                      | Model                | Type | Capacity     | Status             | Power        | O/G                | I/C           |
| 1   | Aimag center         | SDE                  | D    | 1,760        | Working            | Central Grid | Yes                | Yes           |
| 2   | Bayan-Undur          | Not exist            | ---  | 0            | No Hardware        | ---          | Thru operator      | Thru operator |
| 3   | Burd                 | C-12/48              | D    | 48           | Working            | Central Grid | Thru operator      | Thru operator |
| 4   | Bat-Ulzii            | C-12/48              | D    | 48           | Working            | Central Grid | Thru operator      | Thru operator |
| 5   | BB-Ulaan             | ATC-50/200           | A    | 50           | Seasonal           | Sum Diesel   | Thru operator      | Thru operator |
| 6   | Bayangol             | C-12/48              | D    | 48           | Working            | Central Grid | Thru operator      | Thru operator |
| 7   | Guchin-Uls           | KXTD-500             | D    | 100          | Working            | Solar        | Dialling "9"       | Thru operator |
| 8   | Esonzuun-Zyil        | ATC-50               | A    | 100          | Working            | Central Grid | Thru operator      | Thru operator |
| 9   | Ulziit               | ATC-40/80            | A    | 40           | Working            | Central Grid | Thru operator      | Thru operator |
| 10  | ZB Ulaan             | ATC-50               | A    | 50           | Working            | Central Grid | Thru operator      | Thru operator |
| 11  | Bogd                 | C-12/48              | D    | 48           | Working            | Solar        | Thru operator      | Thru operator |
| 12  | Nariinteel           | ATC-50/200           | A    | 50           | Seasonal           | Sum Diesel   | Thru operator      | Thru operator |
| 13  | Sant                 | ATC-50/200           | A    | 50           | Working            | Central Grid | Thru operator      | Thru operator |
| 14  | Taragt               | ATC-50/200           | A    | 50           | Working            | Central Grid | Thru operator      | Thru operator |
| 15  | Tugrug               | EM-48                | D    | 48           | Working            | Central Grid | Thru operator      | Thru operator |
| 16  | Uyanga               | ATC-50/202           | A    | 200          | Working            | Central Grid | Thru operator      | Thru operator |
| 17  | Kharkhandulaan       | ATC-50/203           | A    | 50           | Seasonal           | Sum Diesel   | Thru operator      | Thru operator |
| 18  | Khujirt              | KXT-336              | D    | 262          | Working            | Central Grid | Dialling "9"       | Thru operator |
| 19  | Kharkhorin           | ATC-100/2000         | A    | 1,000        | Working            | Central Grid | Thru operator      | Thru operator |
| 20  | Uurkhai in Baynteeeg | National Product     | A    | 6            | Paused             | Solar        | Thru operator      | Thru operator |
|     | <b>Total</b>         | ---                  | ---  | <b>4,008</b> | ---                | ---          | ---                | ---           |

Field Survey-2



Table 2.3.1-4 Sum Switch Facilities in Selenge and Darkhan Uul

| No.                               | Aimag/Sum                | Switching Facilities |      |              | Working Conditions       |              | Trunk Call Service |               |
|-----------------------------------|--------------------------|----------------------|------|--------------|--------------------------|--------------|--------------------|---------------|
|                                   |                          | Model                | Type | Capacity     | Status                   | Power        | O/G                | I/C           |
| 11                                | Selenge Aimag            | SDE                  | D    | 1,888        | Working                  | Central Grid | Yes                | Yes           |
| 12                                | Altanbulag               | HICOM                | D    | 200          | Working                  | Central Grid | Thru operator      | Thru operator |
| 13                                | Eruu                     | ATCK-100/2000        | A    | 100          | Working                  | Central Grid | Thru operator      | Thru operator |
| 14                                | Zuunburen                | Panasonic            | D    | 32           | Working                  | Central Grid | Thru operator      | Thru operator |
| 15                                | Khushaat                 | ATCK-50/200          | A    | 50           | Working                  | Central Grid | Thru operator      | Thru operator |
| 16                                | Orkhon                   | C-12/48              | D    | 48           | Working                  | Central Grid | Thru operator      | Thru operator |
| 17                                | Sant                     | ATCK-50/200          | A    | 50           | Working                  | Central Grid | Thru operator      | Thru operator |
| 18                                | Khuder                   | ATCK-50/200          | A    | 50           | Working                  | Central Grid | Thru operator      | Thru operator |
| 19                                | Tsagaannuur              | ATCK-50/200          | A    | 100          | Working                  | Central Grid | Thru operator      | Thru operator |
| 20                                | Bugant                   | ATCK-50/200          | A    | 100          | Working                  | Central Grid | Thru operator      | Thru operator |
| 21                                | Orkhontuul               | ATCK-50/200          | A    | 50           | Working                  | Central Grid | Thru operator      | Thru operator |
| 22                                | Baruunburen (Bayangol)   | ATCK-50/200          | A    | 100          | Working                  | Central Grid | Thru operator      | Thru operator |
| 23                                | Dulaankhaan              | ATCK-50/200          | A    | 100          | Working                  | Central Grid | Thru operator      | Thru operator |
| 24                                | Javkhlant                | ATCK-50/200          | A    | 50           | Working                  | Central Grid | Thru operator      | Thru operator |
| 25                                | Shaamar                  | ATCK-50/200          | A    | 100          | Working                  | Central Grid | Thru operator      | Thru operator |
| 26                                | Tushig                   | ATCK-50/200          | A    | 50           | Working                  | Central Grid | Thru operator      | Thru operator |
| <b>Homing To Darkhan-Uul EWSD</b> |                          |                      |      |              |                          |              |                    |               |
| 27                                | Saikhan (Nomgon)         | ATCK-50/200          | A    | 100          | Working                  | Central Grid | Thru operator      | Thru operator |
| 28                                | Khutul                   | ATCK-100/2000        | A    | 600          | Working                  | Central Grid | Thru operator      | Thru operator |
| 29                                | Zuunkharaa               | HICOM                | D    | 700          | Working                  | Central Grid | STD with "9"       | DID           |
| 30                                | Bayangol                 | Panasonic-330        | D    | 228          | Working                  | Central Grid | Thru operator      | Thru operator |
| 31                                | Tunkhel                  | ATCK-50/200          | A    | ---          | MT has withdrawn in 2002 |              | Via MRC            | Via MRC       |
|                                   | <b>Sub-total</b>         | ---                  | ---  | <b>4,696</b> | ---                      | ---          | ---                | ---           |
| 51                                | <b>Darkhan-Uul</b>       | EWSD                 | D    | 6,384        | Working                  | Central Grid |                    |               |
| 52                                | Shariin gol              | ATCK-100/200         | A    | 500          | Working                  | Central Grid | Thru operator      | Thru operator |
| 53                                | Khongor                  | ATCK-50/200          | A    | 150          | Working                  | Central Grid | Thru operator      | Thru operator |
| 54                                | Orkhon                   | ATCK-50/200          | A    | 150          | Working                  | Sum Engine   | Thru operator      | Thru operator |
| 55                                | Salkhit (R/D of Khongor) | ---                  | ---  | ---          | MT has withdrawn in 2001 |              | Via MRC            | Via MRC       |
|                                   | <b>Sub-total</b>         | ---                  | ---  | <b>7,184</b> | ---                      | ---          | ---                | ---           |

Field Survey-2

## 2.3.2 Transmission System

### 2.3.2.1 Existing Transmission Network

#### (1) Uvurkhangai Aimag

The Aimag centre of Uvurkhangai (Arvaikheer) is connected with microwave radio relay station (MW 111), which is a terminal station of western route digital microwave trunk transmission network (NERA digital radio relay SDH-STM-1 system constructed in 1997).

The approach link from MW 111 to aimag center is established by NERA PDH digital radio relay (34 Mbps) and it is terminated by PCM Ericsson 60 channel Multiplexer. The path length is 13 Km and it uses radio frequency bands at 7 GHz.

Total five microwave repeater stations (MW 108, 109, 110, 112 and 113) and one terminal station (MW 111) in Uvurkhangai consist of the national trunk transmission network

in western route. The location, altitude and tower height of existing microwave radio relay stations is shown in Annex 3 Table 2.3.2.1-1. In order to expand digital cellular mobile telephone service to western and southern rural areas MobiCom Corporation is now under construction of digital microwave radio links at 34 Mbps on the existing MT microwave national trunk transmission routes. It is expected to complete by end of October in 2002. The frequency allocations of NERA SDH-STM-1 system and MobiCom PDH Paso Link system are shown in Annex 3 Figure 2.3.2.1-1. Uvurkhangai aimag existing microwave radio-relay link configuration is also shown in Annex 3 Figure 2.3.2.1-1.

The approach transmission line from existing microwave radio-relay station 108 to Kharkhorin Sum centre telecom office is established by digital microwave radio-relay used at 7 GHz band. The NEC DRM770 microwave equipment is installed at the terminal stations (MW 108 and Kharkhorin telecom office).

The 50 Pair metallic cable line is now used for the approach link between existing microwave radio-relay station 109 and Khujirt Sum centre telecom office. Excepting for Kharkhorin and Khujirt sum centres the analogue network of open wire lines (OB 3-3, OB 12-3 system) are used to connect sum centre subscribers to aimag centre switching system. Each open wire line is carrying 1 to 6 traffic channels.

Total length of open wire carrier transmission system in Uvurkhangai is about 1700 Km. Uvurkhangai aimag communication office is now controlling 20-branch office, 19 of them is located in rural areas (in 18 Sums). In the AC communication office it is available for telephone service to put 100 % automatic telephone connection into inter-aimag and long distance telephone calls. A digital microwave transmission system and PCM transmission equipment is installed at Kharkhorin and Hujirt telecom office. Switching system is now installed in 15 sum telecom offices. In Bayan-Undur, Baruunbayan-Ulaan and Khairkhandulaan sums the auto switching system is still not introduced. In Uvurkhangai aimag the auto-switching system was introduced in 3 sums for the past 3 years and in 5 sums its operation was changed from manual switching connection to auto switching connection.

The survey was implemented in the following sites:

- Microwave radio relay station: MW 111, MW 110, MW 109 and MW 108
- Aimag center: Arvaikheer
- Sum centres: Uyanga, Zuunbayan-Ulaan, Bat Ulzy, Guching-US, Khujirt, Sant, Bayangol, Toglog, Kharkhorin

Data book Table.2.3.2.1-1 shows the summary records about current telecommunications service and the facilities implemented in Field Survey.

Microwave radio relay repeater station is now manned and maintained by 24 hours shift staff members. Analogue microwave radio transmission link has been replaced by digital microwave transmission system but the KURS-4 Russian made radio equipment and 4 GHz frequency used antenna is still remained in the existing microwave relay station.

In Uyanga sum, new sum center is now being build it is about 1 km far from existing sum center. It is, therefore, required to make the service improvement to both new and old sum centres.

Concerning the Line Of Sight visibility from MW 110 to Zuunbayan-Ulaan it was found that there is no problem in building a digital microwave radio link by one hop path design.

MobiCom and Skytel corporations in Arvaikheer, Hujirt and Kharkhorin have provided digital cellular mobile communications service.

In case of introduction of WLL in Kharkhorin, it is requested to cover a Tourist Camp village it is 9 Km far from Sum center.

Regarding the construction of new digital microwave path link it is requested to extend the path link to mining village Bayanteeg that is 23 Km far from MW 113 station. Annex 3 Table 2.3.2.1-1 shows the quantity of HF IC-78 radio station in Uvurkhangai Sum center and Bag provided by ODA of Japan in 2001. Total 133 sets of HF transceiver equipment has been distributed and effectively used for emergency communication purpose.

## **(2) Selenge and Darkhan-Uul Aimag**

National inter-province toll transmission lines from Ulaanbaatar is terminated at Darkhan-Uul Aimag Telecom Office through PDH 34 Mbps Optical Fibre Cable system that approach transmission line is connected with MW 306 digital microwave radio-relay terminal station and MW 306 station is located at 4.5 Km far from Darkhan.

In the northern toll transmission route passing through Selenge Aimag and Darkhan-Uul Aimag there are two terminal stations (Darkhan MW 306 and Sukhbaatar MW 308) and three repeater stations (Zuun Baruun Haraa MW 304, Nomgon MW 305 and Orkhon S.A.A

MW 307). NERA PDH 34 Mbps Digital Microwave Radio-Relay System now establishes it in Mongolia northern route. The northern route is terminated at Darkhan MW 306 station and is terminated at Sukhbaatar MW 308.

The Optical Fiber Cable (OFC, 8C) with 34 Mbps (16 x E1) is extended from MW 308 radio-relay station to Selenge Aimag Telecom Office. The distance of OFC is about 25 Km. The existing microwave radio-relay link configurations and the frequency allocation used is shown in Annex 3 Figure 2.3.2.1-2.

The STM-1 FOTS equipment (SMS-600V, NEC) is installed at Darkhan Telecom Office. The MRC Optical Fiber Cable Network with SDH system is laid along the Railway Road in Selenge Aimag and Darkhan-Uul Aimag. The OFC network configuration is also shown in Figure 2.2-1. The installation of 1402 Km long Optical Fibre Cable Network (OFCN) with SDH-STM-1 system (12 Cores) alongside the Mongolian Railway Road from North to South in Mongolia was completed in year of 2000. In Selenge and Darkhan-Uul it is possible to make OFCN branching by inserting ADM equipment (STM-1) from the following stations: Zuunkharaa, Salkhit, Darkhan, Sukhbaatar, Khutul and Orkhontuul.

All of MT toll transmission line between Aimag center and Sum center has been established by analogue Open Wire carrier transmission system (OB 3-3, OB 12-3) in Selenge and Darkhan-Uul Aimag. The total length of Open Wire carrier transmission lines reaches about 1380 Km.

Selenge Aimag communication office is now controlling 16 branch offices, 15 of them is located in rural areas (13 Sums). In the communication office it is available for telephone service to put 76.9 % automatic telephone connection into inter-province and long distance telephone calls. Switching system is now working in 13 sum telecom offices. In Khuder, Tushing and Khushaat sums the auto switching system is still not introduced. In Selenge aimag auto-switching system has been introduced in 4 sums during 3 years period and in 5 sums its operation was changed from manual switching connection to auto switching connection.

Darkhan-Uul aimag communication office is now managing operation and maintenance matters concerned with 10 branch offices including the following five Sum centres that belongs to Selenge Aimag administratively: Dzuunhaaraa, Saikhan (Hutul + Nomgon bag), Bayangol (Baruunhaaraa), Sumber and Tunkhel.

In Sumber and Tunkhel sums the auto switching system is still not introduced. MT Telecom branch office in Tunkhel Sum centre was made withdrawal and service provided by only MRC telecom office.

The survey was implemented in the following sites:

- Microwave radio relay station: MW304, MW305, MW306, MW307 and MW308
- Aimag centres: Darkhan, Sukhbaatar
- Sum centres: Altanbulag, Tsaganuur, Zuunburen, Sharin-gol, Eruu, Shamar, Hutul, Sant, Baruunburen, Orkhon-tuur, Dzuunharaa

Data book Table 2.2-1 shows the survey record of Darkhan-Uul Aimag centre and Sum centres.

Concerning installation of new digital microwave radio-relay system it is possible to utilize the existing microwave building facilities (Antenna tower, building, power supply etc.) , and also, possible to branch out from the existing microwave radio-relay stations (MW 304, MW 305, MW 307 and MW 308 radio-relay stations) to extend the Sum centres, however, present NERA PDH microwave transmission capacity is almost fully occupied, therefore, it is requested to make an additional establishment of microwave transmission route along the route from MW 304 to MW 308 for the purpose of rural telecommunication development between Aimag centre and Sum centres.

Concerning digitisation of transmission path from Darkhan to Orkhontuul it is requested to provide approach digital microwave link from nearest MRC Orkhontuul Railroad station to MT Orkhontuul Sum center Telecom Office by way of one radio-relay stations and the link distance is 18 Km.

Concerning digitization of transmission path from Darkhan to Dzuunharaa it is requested to replace existing old type 2 Mbps microwave radio-relay equipment by new digital microwave radio-relay equipment in the link between MW 304 microwave radio-relay station and MT Dzuunharaa Telecom Office.


MobiCom and Skytel corporations in Darkhan, Sukhbaatar, Altanbulag, Khutul and Zuunkharaa have provided digital cellular mobile communications service at present time.

The feasibility study of introduction of WLL (Wireless Local Loop) system was made in Sharin-Gol, Khutul and Zuunkharaa Sum centres and it is required to install the WLL system to overlay on the existing Metallic Cable system for future demand increase.

Annex 3 Table 2.3.2.1-2 shows the quantity of HF IC-78 radio station in Selenge and Darkhan-Uul Sum centres and Bags provided by ODA of Japan in 2001. Total 71 sets of HF transceiver equipment has been distributed and used effectively for emergency purpose in Selenge Aimag. Total 37 sets of HF transceiver equipment has been distributed in Darkhan Uul, however, those HF transceiver equipment are not used effectively because of popularity of mobile telecommunication services.

**2.3.2.2 Existing Optical Fibre Transmission Network**

Analogue Open wire systems are mainly used as transmission system from the Aimag Centre and Sum Centres, and there is no FOTS (Fibre Optic Transmission System) in Uvurkhangai Aimags, while the FOTS owned by MRC (Mongolian Railway Company) run from Ulaanbaatar to Sukhbaatar in Selenge Aimag ( and to Russia) with a branch route from Salkhit in Dalkhaan-Uul Aimag to Orkhontuul in Selenge Aimag. The MRC facilities will be used in the Project. The detail of FOTS of MRC is shown in Figure 2.3.2-1.



**Figure 2.3.2.2-1 Mongolian Railway Company Fibre Optic Transmission Systems**

### **2.3.3 Access Network System**

#### **(1) Wired Access Network**

##### **a) The Present Status of Existing Facilities of Sum Centres**

##### **i) Number of cable routes from a telecommunication office**

Though the number of cable routes from a telecommunication office is determined based on the scale and form of Sum centre, it is three directions in many cases. The branch route is prepared in Ger areas that are distributed outside the central area of Sum centres.

##### **ii) Cable system**

Aerial cable system has been adopted in almost all Sum centres. Direct buried cable was laid in 1968 as a part existing route in Khujirt telecommunication office. Zuunkharaa telecommunication office that is the biggest Sum centre, has an underground duct system of about 1.4km.

##### **iii) The construction fiscal year of outside plant**

Outside plant of almost all Sum centres were built in the 1980s has been remarkably deteriorated. Shortage of cable capacity is also caused at present.

##### **iv) Detailed information related to outside plant in site survey Sum centres**

The detailed information collected from site survey is shown in 2.3.3-1.

Appropriate plant records with cable drawings were not holed and not updated in Sum centres. The plant records attached in Vol. V were prepared based on present status of outside plant of sampled Sum centres that were studied by our site survey.

Table 2.3.3-1 Sample Site Data by Field Survey

As of Sep., 2002

| Items                           |                   | Uvurkhngai |       |                                | Selenge   |         |                | Darhan                                  |
|---------------------------------|-------------------|------------|-------|--------------------------------|-----------|---------|----------------|---|
|                                 |                   | ZB Ulaan   | Burd  | Hujirt                         | Zuunburen | Shaamar | Sant           | Zuunharaa                               |
| Scale of Sum Centre             | Scale of Town     | Middle     | Small | Big                            | Small     | Big     | (M.)-Big       | Biggest                                 |
| Diameter of the Sum Centre      | Long (km)         | 5.0        | 3.5   | 4.0                            | 3.0       | 4.0     | 3.0            | 7.0                                     |
|                                 | Short (km)        | 3.7        | 3.0   | 3.0                            | 3.0       | 3.5     | 2.0            | 5.0                                     |
| Population                      | 2002              | 1,025      | 927   | 4,000                          | 1,726     | 2,400   | 2,063          | 22,300                                  |
| Household                       | 2002              | 209        | 165   | (889)                          | 396       | 600     | 374            | 5,108                                   |
| Percentage of Residential Class | High              |            |       | 20%                            |           | 5%      | 5%             | 50%                                     |
|                                 | Middle            | 10%        | 10%   | 50%                            | 5%        | 15%     | 5%             | 30%                                     |
|                                 | Low               | 90%        | 90%   | 30%                            | 95%       | 80%     | 90%            | 20%                                     |
| Public institution              | Government office | 1          | 1     | 1                              | 1         | 1       | 1              | 1                                       |
|                                 | School            | 1          | 1     | 1                              | 1         | 1       | 1              | 3                                       |
|                                 | Hospital          | 1          | 1     | 1                              | 1         | 1       | 1              | 2                                       |
|                                 | Kindergarten      | 1          | 1     | 2                              | 1         | 1       | 1              | 3                                       |
|                                 | Bank              | 1          | 1     | 1                              | 1         | 1       | 1              | 2                                       |
|                                 | Telecom office    | 1          | 1     | 1                              | 1         | 1       | 1              | 2                                       |
|                                 | Others            |            |       | 2                              |           | 1       | 2              | 4                                       |
|                                 |                   |            |       | Police Sanatorium (Hot spring) |           | College | Police College | Police Court<br>Factory<br>Fire station |
| Total                           |                   | 6          | 6     | 9                              | 6         | 7       | 8              | 17                                      |
| Existing main line              |                   | 50         | 48    | 225                            | 7         | 72      | 33             | 700                                     |
| Waiting list                    |                   | 26         | 32    | 30                             | 2         | 16      | 18             | 88                                      |
| No. of exchange entrance cable  | pcs               | 3          | 1     | 3                              | 1         | 5       | 3              | 12                                      |
| Total cable sheath length       | km                | 1.3        | 1.0   | 13.5                           | 0.015     | 3.0     | 0.4            | 31                                      |
| Pole                            | ea                | 72         | 73    |                                | 12        | 13      | 50             | 220                                     |
| DP                              | ea                | 3          | 5     | 27                             | 1         | 5       | 3              | 93                                      |
| Furthest DP from Exchange       | km                | 0.5        | 0.6   | 2.9                            | 0.15      | 1.3     | 0.2            | 4                                       |
| Open wire (from AC)             | km                | 54         | (35)  |                                | 45        | 21.7    | 62             | 32                                      |
| Open wire (intra SC)            | circuit           |            |       |                                |           | 2       | 3              |   |
| Open wire (to Bag)              | km                |            |       |                                |           |         |                | 54                                      |

## b) The feature of Sum centre

All Sum centres have been constructed by a unification concept based on the local city development master plan. The notable feature of Sum centres is as follows:

- i) The public institutions and the apartments are arranged in the central area of the Sum centre.
- ii) There are 6 public institutions of a government office such as a telecommunication office, a bank, a hospital, and a school, a kindergarten in small size Sum centres. In large-scale Sum centre, there are a college, a court, a fire department, a factory, etc. adding to the organization stated in the small size Sum centres and total of 8-9 public institutions.
- iii) The telecommunication office is generally located in the central part of a Sum centre.
- iv) Clear roads only exist in the central are of a Sum centre.



- v) There is no clear road to Ger areas. However, the future road plan are decided in Sum centre city master plan and cable route planning should follow the road plan
- vi) The Sum centre city master plan is still under progress and there are many vacant spaces in the central area of Sum centre.
- vii) There are some blocks of Ger area outside central area of Sum centre.
- viii) The access network service area covers up to the outskirts of those Ger areas
- ix) The form of the service area looks like an ellipse form and the length of major axes is 3.0-5.0km, and minor axes id 2.0-3.5km that is not affected by area size and population of Sum centres.

c) Issues on the outside plant

- i) Improvement of the entrance cables to the telecommunication office

The standard of the entrance cable in PTA, Mongolia is underground cable system with manhole in front of telecommunication office and inside trench of a telecommunication office. However, actual lead-in cables are installed through the hole on the wall of telecommunication office with improper angle of cable curvature and in adequate protection in the majority of Sum centres other than large size Sum centres is entrance cable

Lead-in point of cable at the telecommunication office is the most important portion in access cable network.

Aerial lead-in method should be applied for telephone office in majority of Sum centres other than large size Sum centres. It is necessary to prepare the leading- in pole in front of a telecommunication office in the optimal position and to secure proper angular of cable curvature and the cable protection at the lead-in portion.

- ii) Cable network area

The standard of cable network area in PTA, Mongolia limits the area within central area of Sum centre and the cables installed in Ger area are very few.

However, the following concepts are recommendable in the universal service and marketing strategy point of view.

- The cable section should be extended to the permanent residence Ger area to reduce the subscriber's installation cost for new subscriber connection.
- The cable section should be extended to the seasonal Ger areas even if it is a specific period.
- Public telephone should be installed in the seasonal Ger areas for the people who cannot install a telephone.

iii) Existing facility

Existing cables were installed in 2 periods during in 1984 - 1989, and in 1997 - 2001.

Since existing facilities were installed with poor construction manner and present quality of the cable network have been lower, almost all existing facilities should be renewed.

Even if some cables have enough quality, it is still necessary to rearrange the capacity of cables and/or the position of the distribution points.

Therefore, the existing facility should be replaced with new one in the project in principle.

### **2.3.4 Power System**

#### **(1) General**

Power supply situations at the Sums selected for the Feasibility Study are as indicated in Annex 5-1, while various power supply types at the Sums are exhibited in Annex 5-2. Codes in the “Current Power Supply Types” column in Annex 5-1 correspond with those indicated in Annex 5-2. In addition, typical power supply system diagrams for MW repeater stations are provided, for reference, as indicated in Annex 5-3.

Power supply facilities at the target Sums are summarized as follows:

#### **(2) Darkhan-uul Aimag**

All of the telecom offices at the Sums in the Darkhan-uul Aimag are supplied with electricity from Central Energy System. Power supply to the telecom systems is comparatively reliable and stable.

The telecom office at the Aimag centre is provided with a stand-alone diesel generator with rated capacity of 100kW that, in combination with two battery banks, supports switching system during power failure.

#### **(3) Selenge Aimag**

All of the telecom offices at the Sums in the Selenge Aimag are supplied with electricity from Central Energy System. Power supply to the telecom systems in the Aimag is comparatively reliable and stable.

The telecom office at the Aimag centre is provided with a stand-alone diesel generator with rated capacity of 60kW that, in combination with a battery bank, supports switching system during power failure.

#### **(4) Uvurkhangai Aimag**

Telecom offices at the majority of the Sums in the Uvurkhangai Aimag are supplied with electricity from Central Energy System. Back-up diesel generators are installed at a few telecom offices that receive electricity from Central Energy System.

Sums that are not connected with Central Energy System are supplied with electricity from diesel generating stations located at the Sum centres. Almost all of the diesel generators were provided under grant aid of Japan for the last three years. Power supply capabilities by the diesel generators appear to be high.

Some of such Sum centres are provided with stand-alone PV systems of small capacity ranging from 0.4kW to 0.8kW to feed power to small power consuming equipment.

### **2.3.5 IT System**

There are eight (8) ISP in Mongolia at present. And more than 30,000 people use Internet and 9,000 peoples have their own account as of 2001. But around 95 % of total users are inhabitants of Ulaanbaatar. ISP's service area is not restricted within Ulaanbaatar, but their routers (connection nodes) are only located Ulaanbaatar and Erdenet.

In rural area, Internet connection from Aimag centre and some Sum centres is possible basically through dial-up connection. However as stated in Annex 6.1, actual users are very limited. Only each one 10-years junior high school in Bayangol Sum (Uvurkhangai Aimag) or Zuunkharaa Sum (Selenge Aimag) is the subscriber of Internet among the surveyed 200 organizations. One person who lives in Eruu Sum (Selenge Aimag) has Internet account among the surveyed 300 persons.

That low penetration rate at Aimag and Sum areas are mainly due to high charge of long distance communication (in addition to provider's fee, 20 Tg long distance charge per minute are required), low speed connection depending on the old telecommunication facilities, lack of consumable money of the peoples and less opportunity of PC buying or using. These situations should be cleared one-by-one but as early as possible for rapid improvement of rural ICT environment.

Internet café is open at MT offices in Darkhan-Uul Aimag centre and Selenge Sum centre. RailNet has announced that he opened Internet café at Zuunkharaa railway station recently.