

Annex E2.3.1 Water Intake for Domestic Use in the Study Area (Implementation Status of Piped Water Supply in South Sumatra) (2/2)

| No | Location | | Status | Number of Population | Capacity (L/S) | Type of Source | Managed by | Implementation Status | Type of Connection | | Source of Fund | Implementation Period | |
|----|----------|-----------------|--------|----------------------|----------------|----------------|-------------|-----------------------|--------------------|----|----------------|-----------------------|------------|
| | Regency | Town | | | | | | | MC | PT | | Start | Completion |
| 43 | Lahat | Lahat (1) | BNA | 76,179 | 20.0 | River | BPAM | Working | 1,810 | 18 | APBN/ADB | 1980 | 1982 |
| 44 | | Lahat (2) | | 65,621 | 20.0 | River | BPAM | Commisioning | 1,549 | 23 | APBN/ADB | 1986 | 1989 |
| 45 | | Pagaralam (1) | | 20,467 | 20.0 | River | BPAM | Working | 1,086 | 10 | APBN | 1980 | 1982 |
| 46 | | Pagaralam (2) | | 36,776 | 10.0 | River | PPSAB | Commisioning | 964 | 12 | APBN/ADB | 1985 | 1988 |
| 47 | | Tebing Tinggi | | 15,081 | 10.0 | River | PPSAB | Commisioning | 1 | 26 | APBN/ADB | 1985 | 1988 |
| 48 | | Fajar Bulan | IKK | 9,549 | 2.5 | River | PPSAB/BPAM | Working | 180 | 9 | APBN | 1985 | 1987 |
| 49 | | Kota Agung | | 3,911 | 2.5 | River | PPSAB/BPAM | Working | 180 | 9 | APBN | 1985 | 1987 |
| 50 | | Pendopo Lintang | | 8,512 | 5.0 | River | APBN/FRENCH | Under Design | 360 | 18 | APBN/FRENCH | 1988 | 1990 |
| 51 | | Arahan | | 5,895 | 10.0 | River | PPSAB | Construction | 1,018 | 24 | APBN/ADB | 1988 | 1990 |
| 52 | | Bungamas | | 6,034 | 10.0 | River | PPSAB | Construction | 1,018 | 24 | APBN/ADB | 1988 | 1990 |
| 53 | | Muara Pinang | | 11,782 | 10.0 | River | PPSAB | Construction | 1,018 | 24 | APBN/ADB | 1988 | 1990 |
| 54 | | Padang Tepong | | 6,029 | 10.0 | River | PPSAB | Construction | 1,018 | 24 | APBN/ADB | 198 | 1990 |
| 55 | | Jarai | | 3,005 | 2.5 | - | PPSAB | Under Design | - | - | APBN/ADB | 1991 | 1993 |
| 56 | | Terkul | | 3,129 | 2.5 | - | PPSAB | Under Design | - | - | APBN/ADB | 1991 | 1993 |
| 57 | | Karang Dalo | | 6,666 | 5.0 | - | PPSAB | Under Design | - | - | APBN/ADB | 1991 | 1993 |
| 58 | | Bandar | | 3,003 | 2.5 | - | PPSAB | Under Design | - | - | APBN/ADB | 1991 | 1993 |
| | | Total | | 281,639 | | | | | | | | | |

| No | Location | | Status | Number of Population | Capacity (L/S) | Type of Source | Managed by | Implementation Status | Type of Connection | | Source of Fund | Implementation Period | |
|----|------------|---------------|--------|----------------------|----------------|----------------|-------------|-----------------------|--------------------|----|----------------|-----------------------|------------|
| | Regency | Town | | | | | | | MC | PT | | Start | Completion |
| 59 | Musi Rawas | Lubuk Linggau | BNA | 61,555 | 80.0 | Surface Water | BPAM | Working | 3,500 | 18 | APBN/DUTCH | 1979 | 1982 |
| 60 | | Srikaton | IKK | 1,307 | 10.0 | River | APBN/FRENCH | Under Design | 720 | 36 | APBN/FRENCH | 1988 | 1990 |
| 61 | | Muara Beliti | | 5,244 | 2.5 | River | PPSAB | Construction | 180 | 9 | APBN/FRENCH | 1988 | 1990 |
| 62 | | Muara Kelingi | | 3,777 | 2.5 | River | PPSAB | Construction | 180 | 9 | APBN/FRENCH | 1988 | 1990 |
| 63 | | Bingin Teluk | | 6,148 | 2.5 | River | PPSAB | Construction | 180 | 9 | APBN/FRENCH | 1988 | 1990 |
| 64 | | Muara Rupit | | 3,451 | 5.0 | Drill Well | PPSAB | Construction | 509 | 12 | APBN/ADB | 1988 | 1990 |
| 65 | | Muara Lakitan | | 6,272 | 5.0 | Drill Well | PPSAB | Construction | 509 | 12 | APBN/ADB | 1988 | 1990 |
| 66 | | Jayaloka | | 3,541 | 5.0 | Drill Well | PPSAB | Construction | 509 | 12 | APBN/ADB | 1988 | 1990 |
| 67 | | Surulangun | | 6,388 | 10.0 | River | PPSAB | Construction | 1,018 | 24 | APBN/ADB | 1988 | 1990 |
| 68 | | Terawas | | 3,209 | 2.5 | - | PPSAB | Under Design | - | - | APBN/ADB | 1991 | 1993 |
| 69 | | Tanah Periuk | | 5,799 | 5.0 | - | PPSAB | Under Design | - | - | APBN/ADB | 1991 | 1993 |
| | | Total | | 106,691 | | | | | | | | | |

| No | Location | | Status | Number of Population | Capacity (L/S) | Type of Source | Managed by | Implementation Status | Type of Connection | | Source of Fund | Implementation Period | |
|----|-----------------|---------------|--------|----------------------|----------------|----------------|-------------|-----------------------|--------------------|----|----------------|-----------------------|------------|
| | Regency | Town | | | | | | | MC | PT | | Start | Completion |
| 70 | Musi Banyu Asin | Sekayu | BNA | 15,218 | 20.0 | River | BPAM | Working | 1,220 | 10 | APBN | 1980 | 1982 |
| 71 | | Betung | | 24,023 | 20.0 | River | BPAM | Commisioning | 1,600 | 34 | APBN/ADB | 1985 | 1988 |
| 72 | | Mariana | IKK | 9,468 | 5.0 | River | PPSAB/BPAM | Working | 360 | 18 | APBN | 1983 | 1987 |
| 73 | | Babat Toman | | 7,684 | 5.0 | River | APBN/FRENCH | Construction | 360 | 18 | APBN/FRENCH | 1988 | 1990 |
| 74 | | Bayung Lincir | | 3,952 | 2.5 | River | APBN/FRENCH | Under Design | 180 | 9 | APBN/FRENCH | 1988 | 1990 |
| 75 | | Sungai Lilin | | 4,141 | 5.0 | - | PPSAB | Under Design | - | - | APBN/ADB | 1991 | 1993 |
| 76 | | Sukarame | | 3,287 | 2.5 | - | PPSAB | Under Design | - | - | APBN/ADB | 1991 | 1993 |
| 77 | | Sungsang | | 4,612 | 5.0 | - | PPSAB | Under Design | - | - | APBN/ADB | 1991 | 1993 |
| | | Total | | 72,385 | | | | | | | | | |

Source : PPSAB September 1989