

**ANNEX 22**  
**OPTIONS FOR**  
**THE 2<sup>ND</sup> STAGE PROJECT SCALE**

## **ANNEX 22      OPTIONS FOR THE 2<sup>ND</sup> STAGE PROJECT SCALE**

The scale of the 2<sup>nd</sup> Stage is rather large for international or Lao PDR's own funding even though economic and financial viability was confirmed. Therefore, in order to adapt the 2<sup>nd</sup> Stage Project to appropriate capital investment scale, efforts on water conservation and reduction of UFW are also indispensable by the NPVC. After completion of the 1<sup>st</sup> Stage Project, feasibility study will be required to implement the 2<sup>nd</sup> Stage. During the feasibility study for the 2<sup>nd</sup> Stage, scale of the 2<sup>nd</sup> Stage will be reviewed. In case that the maximum water demand is reduced by promotion of water conservation and reduction of UFW than estimated by the Study, implementation of the 2<sup>nd</sup> Stage will be able to be divided into two phases, 30,000 and 30,000 m<sup>3</sup>/day or to be reduced to 50,000 m<sup>3</sup>/day from 60,000 m<sup>3</sup>/day.

Figure 1-1 shows Two-Phase implementation of the 2<sup>nd</sup> Stage and Figure 1-2 shows the case that scale of the 2<sup>nd</sup> Stage is reduced from 60,000 m<sup>3</sup>/day to 50,000 m<sup>3</sup>/day by promotion of water conservation and UFW reduction. Such modification of scale of the 2<sup>nd</sup> Stage will reduce financial impacts to the NPVC. These options for the scale of the 2<sup>nd</sup> Stage should be reviewed during the feasibility study for the 2<sup>nd</sup> Stage.

Figure 1-1 Two Phase Implementation of the 2<sup>nd</sup> Stage Project




Figure 1-2 Reduction of the 2<sup>nd</sup> Stage Project Scale from 60,000 to 50,000 m<sup>3</sup>/day

