

**STUDY ON AUGMENTATION OF  
WATER SUPPLY AND SANITATION  
FOR  
THE GOA STATE  
IN THE REPUBLIC OF INDIA**

**Volume IV  
Appendix for Master Plan**

November 2006

**JAPAN INTERNATIONAL COOPERATION AGENCY**

---

**NIHON SUIDO CONSULTANTS CO., LTD.  
and  
NJS CONSULTANTS CO., LTD.**

<b>GE</b>
<b>JR</b>
<b>06-069</b>

## **PREFACE**

In response to a request made by the Government of Republic of India, the Government of Japan decided to conduct the Study on Augmentation of Water Supply and Sanitation for the Goa State in the Republic of India and entrusted the study to the Japan International Cooperation Agency (JICA).

JICA sent to India a study team headed by Mr. Takemasa MAMIYA of Nihon Suido Consultants Co., Ltd. between March 2005 and October 2006. The study team was composed of members from Nihon Suido Consultants Co., Ltd. and NJS Consultants Co., Ltd. JICA also established an Advisory Committee headed by Mr. Yoshiki OMURA, Senior Advisor, Institute for International Cooperation JICA, which, from time to time during the course of the study, provided specialist advice on technical aspects of the study.

The team held discussions with the officials concerned of the Government of the Republic of India and conducted field surveys at the study area. Upon returning to Japan, the team conducted further studies and prepared present report.

I hope that this report will contribute to the promotion of this project and to the enhancement of friendly relationship between our two countries.

Finally, I wish to express my sincere appreciation to the officials concerned of the Government of India and Government of Goa for their close cooperation extended to the team.

November, 2006

Ariyuki MATSUMOTO  
Vice-President  
Japan International Cooperation Agency

November, 2006

Mr. Ariyuki MATSUMOTO  
Vice-President  
Japan International Cooperation Agency

## **Letter of Transmittal**

Dear Sir,

We are pleased to submit to you this Final Report on the Study on Augmentation of Water Supply and Sanitation for the Goa State in the Republic of India. This report incorporates the views and suggestions of the authorities concerned of the Government of Japan, including your Agency. It also includes the comments made on the Draft Final Report by Public Works Department of the Government of Goa and Ministry of Urban Development of the Government of the Republic of India and other government agencies concerned of the Republic of India.

The Final Report comprises a total of six volumes as listed below.

- Volume I : Executive Summary
- Volume II : Main Report: Master Plan
- Volume III : Main Report: Feasibility Study
- Volume IV : Annex for Master Plan
- Volume V : Annex for Feasibility Study
- Volume VI : Drawings


This report contains the Study Team's findings, conclusions and recommendations derived from the three phases of the Study. The main objective of the Phase I was to conduct a reconnaissance survey. That of Phase II was to formulate a long term master plan and to identify priority projects, whilst that of the Phase III was to examine the feasibility of the priority projects which had previously been identified in Master Plan during the course of the Phase II.

We wish to take this opportunity to express our sincere gratitude to your Agency, the Ministry of Foreign Affairs and the Ministry of Health, Labour and Welfare of the Government of Japan for their valuable advice and suggestions. We would also like to express our deep appreciation to the relevant officers of Public Works Department of the Government of Goa and Ministry of Urban Development of the Government of the Republic of India for their close cooperation and assistance extended to us throughout our Study.


Very truly yours,

Takemasa Mamiya, Team Leader  
Study on Augmentation of Water Supply  
And Sanitation for Goa State in the  
Republic of India

# Structure of Report



# Location Map



## **VOLUME IV: APPENDIX FOR VOLUME II MAIN REPORT – MASTER PLAN**

### **Appendix for Chapter 1: Introduction**

M11 Minutes of Meetings

### **Appendix for Chapter 2: Sewerage System**

M21 Objectives of the Study and Study Area

### **Appendix for Chapter 3: Existing Condition of the Water Supply and Sanitation/ Sewerage Systems**

M31 Existing Water Supply System  
M32 Data Concerning Number of Connection and Water Consumption  
Provided by PWD Goa  
M33 Water Quality Analysis for Water Supply System  
M34 Results of Leakage Survey  
M35 Existing Sanitation System  
M36 Water Quality Analysis for Sanitation  
M37 Site Visit Reports  
M38 Water Supply and Sewerage Tariff Structure  
M39 Results of Public Awareness Surveys

### **Appendix for Chapter 4: Future Population and Water Demand**

M41 Estimation of Future Population  
M42 Future Water Consumption

### **Appendix for Chapter 5: Water Supply Master Plan**

M51 Service Area and Water Demand  
M52 Planning for Water Treatment Plant  
M53 Results of Hydraulic Analysis  
M54 Case Study of Applying 200 LPCD for All Areas in Goa  
M55 Ganjem and Maisal Schemes as the Emergency Measures  
M56 Evaluation on the Availability of Flowing Additional 50 MLD Water  
through the Existing 1400 MM Transmission Mains  
M57 Alternative Study on Selection of Clear Water Transmission Main  
for Salaulim WSS  
M58 Alternative Study on Proposed WTP Location

### **Appendix for Chapter 6: Master Plan for Sanitation**

M61 Basic Condition for Master Plan  
M62 Design Criteria for Sewerage Facilities  
M63 Master Plan for Sewerage Facilities  
M64 Required Land Area for New Sewage Treatment Plants

### **Appendix for Chapter 7: Operation and Maintenance**

M71 Local Organization and Arrangements Document  
M72 Water & Sanitation Quality Monitoring

M73 Asset Management Process

**Appendix for Chapter 9: Preliminary Cost Estimates and Implementation Schedule**

M91 Calculation basis of Water Supply Cost for Master Plan

M92 Breakdown of Water Supply Cost

M93 Breakdown of Sanitation Cost

**Appendix for Chapter 10: Economic and Financial Evaluation**

M101 Methodology of Economic and Financial Evaluation

M102 Economic and Financial Evaluation of Master Plan for Water Supply

M103 Economic and Financial Evaluation of Master Plan for Sanitation

M104 Financial Plan of PHE with the Master Plan for Water Supply and Sanitation

**Appendix for Chapter 11: Social Considerations and Initial Environmental Examination**

M111 Public Consultation

M112 Environmental and Social Considerations for Implementation

M113 Initial Environmental Examination

## ABBREVIATIONS

ACP	Asbestos Cement Pipe
ADB	Asian Development Bank
ATP	Affordability to Pay
BOD	Biochemical Oxigen Demand
CE	Chief Engineer
CI	Cast Iron
CMMS	Computerised Maintenance Management System
COD	Chemical Oxygen Demand
CPWD	Central Public Works Department
CRZ	Coastal Regulation Zone
CSM	Customer Service Management
D	Diameter
DI	Ductile Cast Iron
DSR	Debt-service Ratio
DST&E	Department of Science, Technology and Environment
EE	Executive Engineer
EIA	Environmental Impact Assessment
FS, F/S	Feasibility Study
GDP	Gross Domestic Product
GI	Galvanised Iron
GIS	Geographical Information System
GLR	Ground Level Reservoir
GOG	Government of Goa
GOI	Government of India
GOJ	Government of Japan
GRDP	Gross Regional Domestic Product
GSDP	Gross State Domestic Product
GVA	Gross Value Added
HDPE	High-density Polyethylene
IEE	Initial Environmental Examination
IS	Information Systems
JBIC	Japan Bank for International Cooperation
JICA	Japan International Cooperation Agency
KPI	Key Performance Indicator
lpcd	Per Capita Water Demand (liter per capita day)
M&E	Machinery and Electricity
MBR	Master Balancing Reservoir
MIS	Management Information System
MLD	Million Liter per Day
MNF	Minimum Night Flow
MOF	Ministry of Finance
MOUD	Ministry of Urban Development
MP, M/P	Master Plan



## **ABBREVIATIONS**

MS	Mild Steel
NPV	Net Present Value
NRPP	NRW Reduction Pilot Project
NRW	Non Revenue Water
NTU	Nephelometric Turbidity Unit
ODA	Official Development Assistance
OECD	Organization for Economic Cooperation and Development
OHR	Over Head Reservoir
PHE	Public Health Engineering
PSC	Prestressed Concrete
PSP	Public Stand Post
PVC	Polyvinyl Chloride
PWD	Public Works Department
RCC	Regional Control Centre
RL	Reduced Level (Height above specified datum level)
SC	Steering Committee
SCM	Supply Chain Management
SE	Superintending Engineer
SS	Suspended Solids
STP	Sewage Treatment Plant
TOR	Terms of Reference
UFW	Unaccounted-for Water
WSS	Water Supply Scheme
WTP	Water Treatment Plant
WTP	Willingness To Pay

# **APPENDIX M1**

This appendix is reference to and supporting data of

## **Volume 2 Main Report – Master Plan Chapter 1 Introduction**

M11      Minutes of Meetings

---

**Appendix M11:**


**Minutes of Meetings**

**Contents for Appendix M11**

M11.1 Minutes of Meetings..... M11-1

**SCOPE OF WORK  
FOR  
STUDY  
ON  
AUGMENTATION  
OF  
WATER SUPPLY AND SANITATION  
FOR THE GOA STATE  
IN THE REPUBLIC OF INDIA  
AGREED UPON BETWEEN  
PUBLIC WORKS DEPARTMENT,  
THE GOVERNMENT OF GOA  
AND  
JAPAN INTERNATIONAL COOPERATION AGENCY**


New Delhi, September 22, 2004



Mr. M Rajamani  
Joint Secretary  
Ministry of Urban Development,  
The Government of India



Mr. Omura Yoshiki  
Leader  
Preparatory Study Team  
Japan International Cooperation Agency  
(JICA)



Ms. Debashree Mukherejee  
Secretary  
Public Works Department,  
The Government of Goa

## I INTRODUCTION

In response to the request of the Government of the Republic of India (hereinafter referred to as "the Government of India"), the Government of Japan decided to conduct Study of Augmentation of Water Supply and Sanitation for the Goa State in the Republic of India (hereinafter referred to as "the Study") in accordance with the relevant laws and regulations in force in Japan.

Accordingly, the Japan International Cooperation Agency (hereinafter referred to as "JICA") the official agency responsible for the implementation of the technical cooperation programs of the Government of Japan, will undertake the Study in close cooperation with the authorities concerned of the Republic of India.

The present document sets forth the Scope of Work with regard to the Study and will be valid after notification of approval by JICA Headquarters. It will be informed through JICA India office to the Government of India.

## II OBJECTIVES OF THE STUDY

The objectives of the Study are:

1. To formulate a master plan for augmentation of water supply and sanitation in the Goa state
2. To conduct feasibility study on priority project(s) which will be selected from the master plan
3. To pursue technology transfer to the counterpart personnel in the course of the Study


## III STUDY AREA

The Study shall cover the areas shown in the attached sheet of Appendix 1.

## IV SCOPE OF THE STUDY

Phase I : Basic Study

- A. Review of the existing (current) water supply and sanitation system
  1. Collection and analyses of existing data and information
  2. Survey and investigation of existing water supply system
    - (1) Water sources
    - (2) Water supply facilities
    - (3) Water consumption
  3. Survey and investigation of existing sanitation system
    - (1) Sanitation facilities
    - (2) Sanitary condition
    - (3) Water quality
  4. Survey of present conditions
    - (1) Social and economic analysis



1 6



- (2) Legislation
- (3) Institutional structures
- (4) Financial conditions
- (5) Environmental control and management
- (6) Public hygiene, awareness, and participation
5. Problem analyses

Phase II :Formulation of a master plan and conducting feasibility study on priority project(s)


- A. Formulation of a master plan
  1. Establishment of scope, goals and strategies for water supply and sanitation
  2. Planning framework
    - (1) population growth and urbanization
    - (2) social and economic growth
    - (3) amount of water source potential, water demand, and sewage quantity
  3. Formulation of master plan
    - (1) Water supply and sanitation system
    - (2) Institutional structures and duties
    - (3) Finance
    - (4) Management, operation and maintenance
    - (5) Water quality monitoring plan
    - (6) Public participation
  4. Technical assistance for initial environmental examination (IEE) and holding of workshop(s)
  5. Preliminary cost estimation and financial plan
  6. Evaluation of the master plan
  7. Selection of priority project(s)
- B. Feasibility Study on priority project(s)
  1. Supplemental survey
  2. Confirmation of the framework of the plan
  3. Outline of future facilities
  4. Management, operation and maintenance plan
  5. Economic and financial analysis
  6. Project cost
  7. Technical assistance for environmental impact assessment (EIA) and holding workshop(s)
  8. Implementation plan
  9. Project evaluation
- C. Seminar(s) for technical transfer

## V STUDY SCHEDULE

The Study will be carried out in accordance with the attached tentative work schedule.  
(Appendix 2)

## VI REPORTS

JICA will prepare and submit the following reports in English to the Government of India:



2





1. Inception Report:

Twenty (20) copies at the commencement of the Study. This report will describe such as study schedule, methodology, and manning schedule.

2. Progress Report

Twenty (20) copies at the first work period in India.

3. Interim Report:

Twenty (20) copies at the beginning of Phase2

4 Draft Final Report:

Twenty (20) copies at the end of the Study in India

The Government of India shall submit their comments within one(1) month after the receipt of the Draft Final Report.

5. Final Report:

Thirty (30) copies

## VII UNDERTAKING OF THE GOVERNMENT OF INDIA

1. To facilitate the smooth conduct of the Study, the Government of India shall take the following necessary measures:

- (1) To provide security related information on as well as measures to ensure the the safety of the Japanese study team (hereinafter referred to as "the Study Team"),
- (2) To permit the members of the Study Team to enter, leave and sojourn in India for the duration of their assignment therein, and exempt them from foreign registration requirements and consular fees,
- (3) To exempt the members of the Study Team from taxes, duties, fees and any other charges on equipment, machinery, vehicles, and other materials brought into India for the conduct of the Study,
- (4) To exempt the members of the Study Team from income tax and charges of any kind imposed on or in connection with any emoluments or allowances paid to the members of the Team for their services in connection with the implementation of the Study,
- (5) To provide necessary facilities to the Study Team for remittance as well as utilization of the funds introduced into India from Japan in connection with the implementation of the Study,
- (6) To secure permission for the Study Team to enter into private properties or restricted areas for the implementation of the Study,
- (7) To secure permission for the Study Team to take all data and documents including photographs and maps related to the Study out of India to Japan, and



3



2



(8) To provide medical services as needed. Its expenses will be chargeable to members of the Study Team.

2. The Government of India shall bear claims, if any arises, against the members of the Study Team resulting from, occurring in the course of, or otherwise connected with, the discharge of their duties in the implementation of the Study, except when such claims arise from gross negligence or wilful misconduct on the part of the member of the Team.

3. Public Works Department of the Government of Goa (hereinafter referred to as "PWD") shall act as a counterpart agency to the Study Team and also as a coordinating body in relation with other governmental and non-governmental organizations concerned for the smooth implementation of the Study.

4. PWD shall, at its own expense, provide the Study Team with the following, in cooperation with other organizations concerned:

- (1) security-related information on as well as measures to ensure the safety of the Japanese study team
- (2) information on as well as support in obtaining medical services
- (3) available data and information related to the Study
- (4) counterpart personnel
- (5) suitable office space with necessary equipment in the Goa State, and
- (6) credentials or identification cards

#### VII CONSULTATION

JICA and PWD shall consult with each other in respect of any matter that may arise from or in connection with the Study.

*Majumdar*

*Kay*


No.	Name	Designation	Organization
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			



# AUGMENTATION OF SANITATION

# GOA STATE

Appendix I (2)



Misani *[Signature]* i

**TENTATIVE SCHEDULE**

Month	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20
Schedule	[Large empty box for project details]																			
	△ IC/R					△ P/R					△ IT/R						△ DF/R		△ F/R	

Remarks: IC/R : Inception Report

P/R : Progress Report

IT/R : Interim Report

DF/R : Draft Final Report

F/R : Final Report


*[Handwritten signature]*

*[Handwritten signature]*

*[Handwritten mark]*

MINUTES OF MEETING  
ON  
PREPARATION OF SCOPE OF WORK  
FOR  
STUDY  
ON  
AUGMENTATION  
OF  
WATER SUPPLY AND SANITATION  
FOR THE GOA STATE  
IN THE REPUBLIC OF INDIA  
AGREED UPON BETWEEN  
PUBLIC WORKS DEPARTMENT,  
THE GOVERNMENT OF GOA  
AND  
JAPAN INTERNATIONAL COOPERATION AGENCY


New Delhi, September 22, 2004



Mr. M Rajamani  
Joint Secretary  
Ministry of Urban Development,  
The Government of India



Mr. Omura Yoshiki  
Leader  
Preparatory Study Team  
Japan International Cooperation Agency  
(JICA)



Ms. Debashree Mukherejee  
Secretary  
Public Works Department,  
The Government of Goa

In response to the official request of the Government of the Republic of India, the Japan International Cooperation Agency (hereinafter referred to as "JICA") dispatched the Preparatory Study Team (hereinafter referred to as "the Team") headed by Mr. Omura Yoshiki, to India from September 12 to September 28, 2004 to discuss and agree on the Scope of Work (hereinafter referred to as "S/W") for "Study on Augmentation of Water Supply and Sanitation for the Goa State in the Republic of India."

During its stay in India, the Team carried out field surveys in the study area, and held a series of discussions with Public Works Department, the Government of Goa (hereinafter referred to as "PWD"), and other authorities concerned.

The Minutes of Meeting have been prepared for the better understanding of the S/W agreed upon between Indian side and the Team on September 22, 2004.

The main items that were discussed and agreed by both sides are summarized as follows. The list of participants is attached in the Appendix 1.

1 The title of the study

Both sides agreed that the title of the study would be "Study on Augmentation of Water Supply and Sanitation for the Goa State in the Republic of India" (hereinafter referred to as "the Study").

2 Target year

Both sides agreed that the target year of the Master Plan should be 2020.

3 Study areas

The Study shall cover the areas shown in Scope of Work. Regarding the master plan for sanitation, the following areas will be covered.

- Margao municipality
- Ponda municipality
- Mapusa municipality
- Coastal belt of south Goa
- Coastal belt of north Goa
- Panaji municipality and its surrounding area ( Provorum, Taleigao, Dona Paula, Caranzalem, St. Cruz, Mercedes, Ribandar )

4 Water supply system

PWD explained that the current water supply system consisted of 7 centralized piped subsystems and future plan should be of the same nature.

5 Counterpart personnel

The Team requested PWD to assign counterpart personnel in the each expertise corresponding to the Study Team members. PWD agreed to select counterpart personnel before the commencement of the Study and assign them in timely manner.



1



## 6 Steering Committee

Both sides agreed that PWD would set up a steering committee for the smooth implementation of the Study. It will consist of the representatives of relevant organizations under the chairmanship of PWD. Organizations as follows are assumed to join the committee at the present moment. The Japanese Study Team and JICA resident representative will also attend the committee.

(The Government of India)

- Ministry of Urban Development

(The Government of Goa)

- Department of Environment
- Department of Water Resources
- Department of Financial and Planning
- Department of Municipal Administration
- Municipalities and Panchayats relevant to the Study

## 7 Environmental and social considerations

The Team explained JICA's environmental and social consideration guidelines, and that it will be applied to the Study.

PWD understood the policy of JICA's guidelines, and agreed in principle to the following responsibilities and requirements.

- Based on the guidelines, PWD shall be responsible for conducting Initial Environmental Examination (IEE) in collaboration with the Study Team.
- The Study Team shall provide PWD with technical support in order to conduct IEE.
- In the course of conducting IEE, public consultation with communities and stakeholders shall be included if necessary.
- The disclosure of information such as study reports is necessary to ensure the participation and dialogues with various stakeholders, in order to achieve appropriate environmental and social considerations.
- The above-mentioned responsibilities and requirements will also be applied when EIA is judged to be necessary.

## 8 Training of Counterpart personnel

PWD requested that counterpart personnel take advantage of training in Japan related to the Study to promote effective technology transfer.

The Team agreed to convey this request to JICA headquarters.

## 9 Workshop

Workshops will be jointly held by PWD and the Study Team to provide opportunities of dialogue with stakeholders.

Both sides agreed that the subjects of workshops would be discussed and settled during the Study period.

## 10 Reports

Both sides agreed that the results of the Study would be open to the public, in principle, in



is

order to achieve maximum use of the study results.

11 Undertaking of the Government of Goa

- 1) The Government of Goa agreed to provide the Study Team all available data (including geographical maps and photographs) and information related to the Study.
- 2) The Government of Goa agreed that 2 vehicles with drivers and office space with office furniture, air-conditioning, telephone lines and electricity would be provided in the Goa State for the use by the Study Team.
- 3) The Government of Goa agreed to allocate enough number of secretaries for the Study Team if needed.

12 Work Schedule

The Team explained PWD that the Study was scheduled for approximately 20 months as shown in Scope of Work, Appendix 2.

13 Others

Upon PWD's enquiry on duration needed up to implementation, the Team suggested as general information, the following example:

- Process in an external financing agency  
(fact finding, project appraisal and loan agreement): 12 months
- Consultant selection, Detailed design, Prequalification of contractors, Tendering, and Contract signing : 25 months
- Construction works : 36 months- 48 months









List of Participants

&lt;Indian side&gt;

Government of India

Mr. Prashant I.A.S  
 Mr. M Rajamani I.A.S  
 Mr. Savitur Prasad I.D.A.S

Director, Ministry of Finance (Japan)  
 Joint Secretary, Ministry of Urban Development  
 Director, Ministry of Urban Development

Government of Goa

Mr. Monohar Parrikar  
  
 Mr. Shri Digambar Kamat  
  
 Mr. Ramakrishna Dhavlikar  
  
 Mr. Dev Singh Negi I.A.S  
 Mr. Alban Couto  
 Mr. N.P.S. Varde I.A.S

Chief Minister (Home, Finance,  
 General Administration, Education)  
 Minister  
 for Power, Urban Development & Mines  
 Minister for PWD, Archives,  
 Archaeology, Museum, & Fisheries  
 Chief Secretary  
 Advisor  
 Director & Joint Secretary,  
 Department of Environment  
 Secretary (Finance) and Planning

Public Works Department, Government of Goa

Ms. Debashree Mukherjee I.A.S  
 Mr. Prakash P. Borkar  
 Mr. V. L. Kamat  
 Mr. Arvind A. Patil

Secretary  
 Principal Chief Engineer  
 Chief Engineer  
 Executive Engineer

&lt;Japanese side&gt;

Preparatory Study Team

Mr. Yoshiki Omura  
 Mr. Haruo Iwahori  
 Ms. Akiko Bushimata  
 Mr. Itsuo Nozawa  
 Mr. Taketoshi Fujiyama  
  
 Mr. Kenichiro Sugiyama

Leader / Water Supply Planning  
 Sanitation Planning  
 Study planning / Preliminary Evaluation  
 Water Supply System  
 Sanitation management /  
 Environmental Consideration  
 Organization and Management /  
 Social Consideration

JBIC

Mr. Fusato Tanaka  
 Ms. Kumiko Uchida

JBIC Indian Office  
 JBIC H.D.Q.

JICA India Office

Mr. Toshifumi Sakai  
 Mr. Daisuke Iijima

Resident Representative  
 Assistant Resident Representative





i

**THE STUDY  
ON  
AUGMENTATION OF WATER SUPPLY AND SANITATION FOR  
THE GOA STATE  
IN  
THE REPUBLIC OF INDIA**

**MINUTES OF MEETING  
ON THE  
INCEPTION REPORT**

Agreed upon in Delhi on March 11<sup>th</sup> 2005  
between



---

**Mr. M. Rajamani**  
Joint Secretary  
Ministry of Urban Development  
The Government of India



---

**Mr. Mamiya Takemasa**  
Team Leader  
JICA Study Team

Witnessed by



---

**Mr. Omura Yoshiki**  
Chairman of JICA Advisory Committee  
Senior Advisor  
Institute for International Cooperation  
Japan International Cooperation Agency



---

**Ms. Debashree Mukherjee**  
Secretary  
Public Works Department,  
The Government of Goa

## MINUTES OF MEETING

The Ministry of Urban Development, the Government of India (hereinafter referred to as "MOUD") and Public Works Department, the Government of Goa (hereinafter referred to as "PWD"), as the Counterpart Agencies for the Study on Augmentation of Water Supply and Sanitation for the Goa State in the Republic of India (hereinafter referred to as "the Study"), held the Inception Meeting with the Japan International Cooperation Agency (hereinafter referred to as "JICA"), JICA Advisory Committee and the JICA Study Team (hereinafter referred to as "the Japanese side"), chaired by Mr. M. Rajamani, Joint Secretary of the MOUD, on March 11<sup>th</sup> 2005. The participants of the meeting are listed in the Attachment.

JICA fielded a JICA Study Team headed by Mr. Mamiya Takemasa and comprising members from Nihon Suido Consultants Co., Ltd. and NJS Consultants Co., Ltd. to implement the Study, and a JICA Advisory Committee chaired by Mr. Omura Yoshiki, Senior Advisor, Institute for International Cooperation, JICA, to oversee the Study implementation. The Study Team has been dispatched to Goa to commence the Study in cooperation with the PWD.

JICA Study Team presented twenty (20) copies of the Inception Report in English. During the meeting the JICA Study Team explained the main contents of the report, work plan/schedule and expected study outputs. Indian side agreed on the contents of the Inception Report with some comments. The main comments and agreements reached during the meeting were as follows:

### 1. Target Year of a Master Plan



The MOUD and the PWD requested an extension of the target year of the Master Plan to year 2025 from 2020, which was previously agreed among the MOUD, the PWD and the JICA on September 22, 2004. The JICA agreed the extension to 2025 subject to provision of Goa development plans and other estimates being given to the JICA Study Team for its reference by the PWD.

### 2. Forecast of Future Population and Water Demand/Sewage Flow

The MOUD and the PWD requested and the Japanese side agreed that future population and water demand/sewage flow should be carefully forecast considering "floating population" and migration such as tourists and seasonal workers to Goa. For the prediction, PWD agreed to provide information/data required concerning number of such populations.

### 3. Questionnaire Survey Area

The PWD informed that it would conduct house-to-house baseline survey from April 2005 in rural area (covering whole State of Goa excluding cities of Mapusa, Panaji, Ponda, and Margao) concerning water supply and sanitation. Both sides agreed that the JICA questionnaire survey





would be reviewed and conducted in only urban areas. The JICA Study Team requested, and PWD agreed to provide its survey results to the JICA Study Team in around May 2005.

#### 4. MOUD/PWD Assistancess Requested

Both parties confirmed contents of "Chapter 7 Responsibilities of the Government of India" and "Annex 3 List of Data/Information Required" of the Inception Report. The JICA Study Team specially requested and the MOUD/PWD agreed to provide assistance among others:

- Provision of complete set of topographical map of Goa state in middle of April 2005
- Customs clearance when the JICA Study Team brings study equipment such as ultra-sonic flow meters, pressure recorders and etc. into India
- Excavation and backfilling of meter pits for installation of ultra-sonic flow meters during leakage survey
- Replacement of malfunctioning meters/stop cocks in pilot areas for leakage survey



**Attachment**

**List of Participants**

**[Indian side]**

Government of India

Mr. M Rajamani I. A. S.	Joint Secretary, Ministry of Urban Development (MOUD)
Mr. Savitur Prasad I. D. A. S.	Director, MOUD
Mr. Sumit Chatterjee	Under Secretary (PHE II), MOUD
Mr. R. Sethuraman	Joint Advisor (PHEE), CPHEEO, MOUD
Mr. N. N. Hotchandani	Assistant Advisor (PHE), CPHEEO, MOUD

Government of Goa

Ms. Debashree Mukherjee I. A. S.	Secretary
----------------------------------	-----------

**[Japanese side]**

JICA Advisory Committee

Mr. Omura Yoshiki	Chairman of the Advisory Committee Senior Advisor (Water Supply Development) Institute for International Cooperation JICA
-------------------	--

Ms. Kamata Hiroko	Member of the Advisory Committee Senior Advisor (Environmental Management, Water Supply and Sanitation) Institute for International Cooperation JICA
-------------------	--

JICA Tokyo Headquarters

Ms. Sawada Hiromi	Water Resources and Disaster Management Team I, Group III (Water Resources and Disaster Management), Global Environmental Department, JICA
-------------------	---


JICA India Office

Mr. Iijima Daisuke	Assistant Resident Representative
--------------------	-----------------------------------

JICA Study Team

Mr. Mamiya Takemasa	Team Leader/Water Supply Planning Nihon Suido Consultants Co., Ltd.
Mr. Sano Hirofumi	Co-Team Leader/Sewerage Planning NJS Consultants Co. Ltd.


Attachment - I



**THE STUDY  
ON  
AUGMENTATION OF WATER SUPPLY AND SANITATION FOR  
THE GOA STATE  
IN  
THE REPUBLIC OF INDIA**

**MINUTES OF MEETING  
ON THE  
PROGRESS REPORT**

Agreed upon in Goa on December 1<sup>st</sup> 2005  
between



**Mr. Wachasundar Anand Madhav,**  
Chief Engineer I,  
Public Works Department,  
The Government of Goa



**Mr. Mamiya Takemasa**  
Team Leader  
JICA Study Team

Approved by



**Ms. Debashree Mukherjee**  
Secretary  
Public Works Department,  
The Government of Goa

## MINUTES OF MEETING

The Public Works Department, the Government of Goa (hereinafter referred to as "PWD"), as the Counterpart Agency for the Study on Augmentation of Water Supply and Sanitation for the Goa State in the Republic of India (hereinafter referred to as "the Study"), held the meeting with the JICA Study Team (hereinafter referred to as "the Study Team"), chaired by Mr. Wachasundar Anand Madhav, Chief Engineer I, Public Works Department, the Government of Goa, on November 9th 2005. The participants of the meeting are listed in the Attachment.

The Study Team had already presented twenty (20) copies of the Progress Report. During the meeting the Study Team explained the main contents and the Indian side agreed on the contents of the Progress Report with some comments. The main comments and agreements reached during the meeting were as follows:

### **1. Future Water Source**

The JICA Study Team requested and the Indian side agreed to evaluate availability of future water source for each water supply scheme based on future water requirement presented in the Progress Report. The results of the evaluation will be informed by the Department of Water Resources by the end of November 2005.

### **2. Water Recycle**

The Indian side asked whether water recycle (water reuse) for large housing complex will be taken into account in the course of the preparation of Master Plan. The JICA Study Team replied that water recycle should be considered depending on the water resource availability. Since the water recycle system is usually costly because it requires dual pipe system and advanced wastewater treatment. Application of the recycle system seems not feasible for domestic use.

### **3. Water Conservation**

The Indian side stated that continuous water supply (24 hours for 7 days a week) should be carefully planned since large quantity of water will be wasted upon achievement of the continuous supply. The Study Team replied that public relation activities concerning water conservation will be indispensable together with system improvements.

### **4. Industrial Water Demand**

The Indian side requested and the JICA Study Team agreed that the future industrial water demand should be cross checked with the demand projection by the Goa Industrial Development Corporation.

**5. Area-wise Water Demand**

The Indian side requested and the JICA Study Team agreed that more detailed area-wise water demand allocation should be presented although Taluka-wise demand is presented in the Progress Report.

**6. Evaluation of Water Quality**

Both sides agreed that safety of water for water supply should be evaluated based on "Recommended Guidelines for Physical and Chemical Parameters" which is included in the "Manual on Water Supply and Treatment Third Edition, Central Public Health and Environmental Engineering Organization, Ministry of Urban Development, the Government of India, 1999 May".

**7. Consultation/Discussion with Other Departments Concerned of the Government of Goa**

The Indian side recommended and the JICA Study Team agreed that consultation/discussion with other departments concerned of the Government of Goa is indispensable for preparation of the Master Plan. The JICA Study Team requested and the Indian side agreed to assist the JICA Study Team for holding such meetings with these departments concerned.



## Attachment

### List of Participants

#### 【Indian side】

##### PWD Goa

Mr. Wachasundar Anand Madhav	Chief Engineer I
Mr. T.K.Nambiar	Superintendent Engineer
Mr. Arvind A. Patil	Executive Engineer
Mr. Dilip Khaunte	Technical Assistant

##### Department of Water Resources

Mr.S.D.Sayanak	Chief Engineer
----------------	----------------

##### Department of Health Services

Mr. A.V.Salelkar	Director
------------------	----------

##### Department of Municipal Administration

Mr. Vyankatesh. N.Sawant	Engineering Assistant
--------------------------	-----------------------

##### Department of Industries, Trade and Commerce

Mr. Prasad Lodayekar	General Manager
----------------------	-----------------

##### Department of Country Planning

Mr. Subhash Nilekarni	Landscape Architect
-----------------------	---------------------

#### 【Japanese side】

##### JICA Study Team

Mr. Mamiya Takemasa	Team Leader/Water Supply Planning
Mr. Sano Hirofumi	Co-Team Leader/Sewerage Planning
Mr. Takehiko Oga	Water Supply Facility Planning
Mr. Eiichi Ishii	Water Supply Pipeline Planning
Mr. Shusaku Ueno	Sewerage Facility Planning
Mr. Tony De Seta	Operation and Maintenance / NRW Reduction Planning
Mr. Tetsuo Wada	Water Supply Facility Planning - II

**THE STUDY  
ON  
AUGMENTATION OF WATER SUPPLY AND SANITATION FOR  
THE GOA STATE  
IN  
THE REPUBLIC OF INDIA**

**MINUTES OF MEETING  
ON THE  
INTERIM REPORT**

Agreed upon in Goa on June 29 2006  
between

**Mr. Wachasundar Anand Madhav,**  
Chief Engineer I,  
Public Works Department,  
Government of Goa

**Mr. Mamiya Takemasa**  
Team Leader  
JICA Study Team

Approved by

**Mr. Santosh Dattatraya Vaidya, I.A.S.,**  
Secretary PWD,  
Government of Goa

## MINUTES OF MEETING

The Public Works Department, the Government of Goa (hereinafter referred to as "PWD"), as the Counterpart Agency for the Study on Augmentation of Water Supply and Sanitation for the Goa State in the Republic of India (hereinafter referred to as "the Study"), held the meeting with the JICA Study Team (hereinafter referred to as "the Study Team"), on April 27th 2006. The participants of the meeting are listed in the Attachment.

The Study Team had already presented twenty (20) copies of the Interim Report to Indian side beforehand with the meeting. During the meeting the Study Team explained the main contents of the Interim Report, which describes Master plan, and the Indian side accepted the Interim Report in principle. The main comments and agreements reached during the meeting were as follows:

### 1. Additional information to the Master Plan

The Indian side requested the Study Team to include description on additional water sources of Ganjem and Moisal and emergency measures into the Report. According to verbal explanation by the Indian side, these sources are recently made available to water supply. The Indian side also explained that the state government was planning to construct small scale water treatment plants with self-finance utilizing these water sources to mitigate urgent water need until completion of Stage 1 projects in 2012. The Study Team requested, and the Indian side agreed to urgently provide the Study Team with detailed information concerning the water sources for inclusion into the Master Plan.

### 2. Higher unit consumption

The Indian side requested presentation of a case with higher unit consumptions. The Study Team replied that such a case with demand forecast based on higher unit consumptions will be made, and sketches of facility plan will be drawn. The case study will be annexed into the Master Plan.

### 3. Selection of Priority Projects

The Study Team explained about selected priority projects for the Feasibility Study as follows :

- Expansion (100 MLD) and rehabilitation of Salaulim Water Treatment Plant including transmission mains and reservoirs required for the system expansion,
- Establishment of new sewerage system in Mapusa,
- Establishment of new sewerage system in North Coastal Belt area, and
- Expansion of existing Margao sewerage system.

The Indian side agreed on the selected priority projects, and agreed to proceed to the Feasibility Study. The Indian side also requested that the Draft Final Report refer to the proposed emergency mitigation measures to be implemented with self-finance.



#### 4. Treatment Method of Sewage Treatment Plant (STP)

The Study Team explained to the Indian side several alternative methods of sewage treatment with their advantages and disadvantages from aspects of qualitative and quantitative. For the expansion of the existing STP, the same method as the existing system would be adopted, namely Sequencing Batch Reactor (SBR) method for Panaji STP and conventional activated sludge method for Margao STP. For the new STPs, although both Oxidation Ditch (OD) method and Aerated Lagoon (AL) method showed advantages comparing with other methods, the Study Team recommended, and the Indian side agreed to employ the OD method for the Study. Because the AL method requires huge land space comparing with the OD, it must be difficult to procure such huge land space around the areas in which sewage treatment plants are required, and the OD method has advantages in odor problem comparing to the AL method especially for tourism area in North and South Coastal Belts.

While, the Feasibility Study shall be conducted by adopting OD method, the Indian side requested and the JICA Study Team agreed to include technical information concerning the SBR method such as dimensions of facilities, drawings of plant layout and major structures including rough cost estimate in the Draft Final Report.



**Attachment**

**List of Participants**

**[Indian side]**

Government of Goa

Mr. J.P.Singh	Chief Secretary
Mr. S.D.Vaidya	Secretary
Mr. Alban Couto	Advisor

Department of Water Resources

Mr. S.T.Nadkarni	Chief Engineer
------------------	----------------

Department of Finances

Mr. Anupani Kishore	Jr Secretary
---------------------	--------------

GSPCB

Mr. A.K.Vazirani	M.Secretary
------------------	-------------

PWD Goa

Mr. Wachasundar Anand Madhav	Chief Engineer
Mr. Arvind A. Patil	Executive Engineer
Mr. K.R.Shrikant	Executive Engineer
Mr. Karunakaran.P	Jr Engineer

**[Japanese side]**

Japan International Cooperation Agency

Ms. Kamata Hiroko	Advisory Committee
Mr. Ito Kozo	Deputy Resident Representative

JICA Study Team


Mr. Mamiya Takemasa	Team Leader/Water Supply Planning
Mr. Sano Hirofumi	Co-Team Leader/Sewerage Planning
Mr. Oga Takehiko	Water Supply Facility Planning
Mr. Fukushima Daisuke	Study Coordinator




**THE STUDY  
ON  
AUGMENTATION OF WATER SUPPLY AND SANITATION FOR  
THE GOA STATE  
IN  
THE REPUBLIC OF INDIA**

**MINUTES OF MEETING  
ON THE  
DRAFT FINAL REPORT**


Agreed upon in New Delhi on October 4, 2006  
between



**Mr. M. Rajamani, I.A.S.,**  
Joint Secretary,  
Ministry of Urban Development  
The Government of India




**Mr. Mamiya Takemasa**  
Team Leader  
JICA Study Team

for 

**Mr. Santosh Dattatraya Vaidya,**  
I.A.S, Secretary PWD,  
Government of Goa

Witnessed by



**Mr. Omura Yoshiki**  
Chairman of JICA Advisory Committee  
Senior Advisor  
Institute for International Cooperation  
Japan International Cooperation Agency

## MINUTES OF MEETING

The Public Works Department, the Government of Goa (hereinafter referred to as "PWD"), as the Counterpart Agency for "the Study on Augmentation of Water Supply and Sanitation for the Goa State in the Republic of India" (hereinafter referred to as "the Study"), held the meeting with the JICA Study Team (hereinafter referred to as "the Study Team"), on September 28th 2006. The participants of the meeting are listed in the Attachment.

The Study Team had already presented twenty (20) copies of the Draft Final Report to Indian side. During the meeting the Study Team explained the main contents of the Draft Final Report, which describes the Master Plan and the Feasibility Study, and the Indian side agreed on the contents of the Draft Final Report with some comments. The main comments and agreements reached during the meeting were as follows:

### 1. Land Acquisition Costs for Sewage Treatment Plants (STPs)

The Indian side requested to consider the appropriate estimation of the land acquisition costs in the Final Report. According to the Indian side, the proposed STP sites of Mapusa and Baga have selected at the community land and there will be no problems of land acquisition, however, certain amount of costs should be compensated to the community. The Study Team agreed that the request would be considered and additional costs be reflected in the Final Report.

### 2. Calculation of Unit Cost of Supply Service



The Indian side requested and the Study Team agreed to calculate the unit cost of supply service (Rs./m<sup>3</sup>) of water supply under condition that all projects proposed in the Master Plan were implemented.

### 3. Cost of Distribution System

The Indian side pointed out that the costs for distribution system improvement were not included in the cost estimate of the priority project. The Study Team explained that the costs for distribution system were included in cost estimates in the Master Plan (Table 92.1, Volume II), but not part of the priority projects since this would be developed gradually as the demand increases and the system expands. The Indian side requested and the Study Team agreed to present the costs required for distribution system for the Stage I project in the Final Report. The Indian side stated that they will explore appropriate sources of financing for this component.

### 4. Water and Sewerage Combined Tariff Schedule


The Indian side requested to consider the possibility of cross-subsidy from water supply revenue to



sewerage expenses. The Indian side pointed out that the sewerage charge was billed at certain percentages of water charge in the present tariff system, therefore, the Indian side requested to consider the water/sewerage combined tariff schedule which is applied same tariff increase rate. The Study Team stated that such combined case could be shown in the Final Report for reference. However, the study team emphasized a principle that operation and maintenance costs for sewerage should be recovered by sewerage tariff revenue without cross-subsidy and in case of water supply, the capital costs should also be recovered.

**5. Finalization of the Draft Final Report**

The JICA Study Team explained and the Indian side agreed that should there be any further comments from the Indian side, these comments should be congregated by the Indian side and submitted to the JICA India Office by 3<sup>rd</sup> of November 2006. Upon receipt of the comments from the Indian side, the Draft Final Report will be finalized as the Final Report taking account of those comments from the Indian side. The Final Report will be submitted to the Indian side in December 2006 through the JICA India Office.





**Attachment**

**List of Participants**

**[Indian side]**

Ministry of Urban Development, the Government of India

Mr. M Rajamani, I. A. S.	Joint Secretary, Ministry of Urban Development (MOUD)
Mr. Savitur Prasad, I. D. A. S.	Director, MOUD
Mr. B.B. Uppal	Deputy Advisor, MOUD
Mr. M. Deendayalan	Assistant Advisor, MOUD
Mr. M. Shankar Narayanan	Assistant Advisor, MOUD

Government of Goa

Mr. S.D.Vaidya, I.A.S.	Secretary PWD
Mr. Alban Couto	Advisor
Mr.Dattaram Sardessai	Joint Secretary (Finance)

Directorate of Planning, Statistics & Evaluation

Mr. H.G.P. Chimulkar	Research Assistant
----------------------	--------------------

Directorate of Panchayat


Mr. Shri.P.T.Nipanikar	Block Development Officer (H.Q.)
------------------------	----------------------------------

Goa State Pollution Control Board

Mr. S.Joglekar	Assistant Executive Engineer
----------------	------------------------------

PWD Goa

Mr. Wachasundar Anand Madhav	Chief Engineer
Mr. Arvind A. Patil	Executive Engineer
Mr. K.R.Shrikant	Executive Engineer
Mr. G.M.N. Parrikar	Executive Engineer
Mr. K.H. Kamaladinni	Executive Engineer
Mr. Karunakaran P	Junior Engineer



Attachment - 1

**【Japanese side】**

Japan International Cooperation Agency

Mr. Omura Yoshiki  
Ms. Sawada Hiromi

Chairman of JICA Advisory Committee  
Water Resources and Disaster Management  
Team I, Group III (Water Resources and  
Disaster Management), Global Environmental  
Department, JICA

JICA India Office



Mr. Subroto Talukdar

Senior Programme Officer

JICA Study Team

Mr. Mamiya Takemasa  
Mr. Sano Hirofumi  
Mr. Wilfrido C. Barreiro  
Mr. Daizo Iwata

Team Leader/Water Supply Planning  
Co-Team Leader/Sewerage Planning  
Organization and Legislation  
Economic and Financial Analysis



## **APPENDIX M2**

This appendix is reference to and supporting data of

**Volume 2 Main Report – Master Plan  
Chapter 2 Objectives of the Study and Study Area**

M21      Soil Corrosiveness Survey

---

**Appendix M21:**

**Soil Corrosiveness Survey**

## **Contents for Appendix M21**

M21.1	Methodology .....	M21-1
M21.2	Results of Analysis .....	M21-1

## M21 Soil Corrosiveness Survey

### M21.1 Methodology

Soil samples, one sample at Salaulim and the other sample from Opa were taken to examine soil corrosiveness. Corrosiveness analysis were conducted conforming to method defined by ANSI (American National Standard Institute, A 21.5) and by German Standard for water and gas, DVGW (Duetschen Verein des Gas und Wasserfaches,GW 9) .

According to the ANSI, in case that the total score becomes more than 10, the soil has corrosiveness and appropriate corrosion protection for underground pipeline is recommended. As of DVGW standard, soil corrosiveness is categorized as follows

Total Score	Soil Corrosiveness
0 or more	Not corrosive
0 to -4	Scant corrosive
-5 to -10	Corrosive
Less than -10	Highly Corrosive

### M21.2 Results of Analysis

Results of analysis are as shown on Table M21.2.1.

**Table M21.2.1 Results of Soil Corrosiveness Analysis**

#### Soil Analysis

	Sample No. 1: Salaulim			Sample No. 2: Opa		
	Analysis Results	Score		Analysis Results	Score	
		ANSI	DVGW		ANSI	DVGW
Kind of Soil	Clay	-	-2	Sand	-	+2
Groundwater	-	-	-	-	-	-
Soil Condition	Original	-	0	Original	-	0
Specific Resistance (ohm-cm) , Original	30700	-	-	91800	-	-
Specific Resistance (ohm-cm) , Saturated by water	22900	-	-	34900	0	0
Water Content (%)	31.6	2	-	22.7	2	-

Percentage of Water Content (%)	24.0	-	-1	18.5	-	0
E Redox (mV)	620	0	+2	516	0	+2
Sulfide	None	0	0	None	0	0
Sulfur Content (%)	0.009	-	-	0.006	-	-
Forced Oxidation pH by H2O2	7	-	-	6	-	-
Score (Sub-Total)	-	2	-1	-	2	+4

### Analysis of Abstracted Water from Soil

	Sample No. 1: Salaulim			Sample No. 2: Opa		
	Analysis Results	Score		Analysis Results	Score	
		ANSI	DVGW		ANSI	DVGW
Specific Resistance (ohm-cm), Original	16667	0	0	109529	-	-
pH	6.4	0	0	5.8	0	-2
SO <sub>2,4</sub> (mg/l)	5	-	0	1	-	0
Cl <sup>-</sup> (mg/l)	Less than 1	-	0	Less than 1	-	0
Total Residue (mg/l)	43	-	-	4	-	-
Acidity (mg/l)	3	-	-	2	-	-
Alkalinity (mg/l)	2	-	-	1	-	-
Score (Sub-Total)	-	0	0	-	0	-2

### Total Score

Sample	No. 1: Salaulim	No. 2: Opa
ANSI	2	2
DVGW	-1	+2

According to the ANSI standard, total scores for both sample are less than 10, therefore, these samples are judged not corrosive. As for DVGW, sample No. 1 shows scant corrosive and No. 2 is not corrosive.

## **APPENDIX M3**

This appendix is reference to and supporting data of

**Volume 2 Main Report – Master Plan**  
**Chapter 3 Existing Condition of the Water Supply  
and Sanitation/ Sewerage Sustersms**

M31	Existing Water Supply System
M32	Data Concerning Number of Connection and Water Consumption Provided by PWD Goa
M33	Water Quality Analysis for Water Supply System
M34	Results of Leakage Survey
M35	Existing Sanitation System
M36	Water Quality Analysis for Sanitation
M37	Site Visit Reports
M38	Water Supply and Sewerage Tariff Structure
M39	Results of Public Awareness Surveys



---

**Appendix M31**

**Existing Water Supply System**

## **Contents for Appendix M31**

M31.1	Salaulim Water Supply Scheme .....	M31-1
M31.2	Opa Water Supply Scheme .....	M31-47
M31.3	Chandel Water Supply Scheme .....	M31-80
M31.4	Assonora Water Supply Scheme .....	M31-94
M31.5	Sanquelim Water Supply Scheme .....	M31-118
M31.6	Dabose Water Supply Scheme .....	M31-141
M31.7	Canacona Water Supply Scheme .....	M31-155
M31.8	Rural Water Supply Scheme .....	M31-168

## **Appendix M31.1 Salaulim Water Supply Scheme**

The Salaulim facility was commissioned in 1989 and has a design capacity of 160 MLD although we are told that the plant is currently producing approximately 170 MLD. The raw water pump house supplies water to the plant via 2 No.1000mm rising mains approximately 1 km from the intake. It is expected that the plant will be augmented with a further 40 MLD some time next year (currently being tendered). Plans are also well developed for a new proposed plant of 200 MLD for which the green field site has already been secured. Water for the existing and proposed plants is via the Selaulim Dam.

Table M31.1.1 lists the summary of asset data for the WTP and Table M31.1.2 contains detailed asset data for the WTP. The plant schematic is shown on Figure M31.1.1.

Observations for Operation and Maintenance of Salaulim Water Treatment Plant are as follows.

Both the raw water pumping compound and the treatment plant compound are adequately gated, fenced and secured by 24 hour on-site security personnel. The plant is operated and maintained 24 hours a day, using a three shift system.

The existing flow measurement devices (which are electromagnetic) are out of service. Therefore, the amount of raw water that is supplied to the plant, and the amount of clean water that is fed to the transmission system via the clean water reservoir, is estimated based on the pump design capacities and the number of pumping hours.

The raw water pump house has eight pumps each with a capacity of 1,181 m<sup>3</sup>. The maintenance standards are good, however the drive couplings/shafts are not adequately guarded. The study team understood that the 10 tonne O/H crane has not been tested since it was installed in 1989. The chains have been replaced periodically, however records of changes to chains and lifting tackle have not been maintained.

Records of hours of pumping, loads etc are logged, however maintenance records are not kept. Monthly oiling and greasing occurs routinely, however all other maintenance is carried out on a reactive basis. For example, pumps are oiled and greased and the impellers are replaced only when reduced discharge is noted. No operation and maintenance manuals are available and training for new staff is only provided on the job by existing more, experienced staff. Due regard for staff safety during maintenance activities was noted during the site visit (e.g. fuses

are removed when staff work on pumps), however there are no written or formal safety systems.

The treatment plant is manually controlled. Most of the equipment appears to be in good working order (including the alum and lime mixers), considering their age. In generally, good maintenance standards are evident, however the pump couplings/shafts are not adequately guarded.

Records of hours of pumping, loads, filter backwashing, clear water reservoir levels etc are logged. However, there are no maintenance logs for repairs or maintenance.

Laboratory staff keep record logs of chemical usage and treatment parameters.

Disinfection is achieved using gas chlorination. The gas chlorination uses one tonne cylinders. Normally there are approximately five cylinders in the chlorine house at any one time, of which four are vacuum chlorinators (“Aqua Pura Corp – Pune” provide the spares). Chlorinator maintenance is performed in-house, however chlorinators are not periodically calibrated and maintenance records are not kept. Maintenance, installation standards and operation practices for chlorination are generally poor. Ammonia solution is used to detect leakages at connection joints. An immersion tank is the only facility available on-site to detect or contain gas leaks, however it is not easily accessible in an emergency. Personal breathing apparatus is available in the laboratory but it is not used or maintained. The cylinders, chlorinators and the contact tank are connected together using a combination of small bore PVC and flexible plastic hoses. These are not safe for this purpose.

The clean water reservoir has two compartments and is cleaned annually. The reservoir is cleaned manually by approximately 120 unskilled contract labours. The labours hose down the internal surfaces and flush the system clean. The cover is removed during this process to provide natural ventilation, however no safety precautions, safety equipment or safe working systems exist.

Tables M31.1.3 to M31.1.7 and Figures M31.1.2 and M31.1.3 show the data on daily flow rate of raw water and transmitted water, water quality and chemical dosage at Salaulim Water Treatment Plant. Table M31.1.8 shows records on power outages at Salaulim Water Treatment Plant.

Table M31.1.9 shows a list of existing reservoirs for Salaulim Water Supply Scheme.

**Table M31.1.1 Summary of Asset Register of Salaulim Water Treatment Plant**

Name of Facility		Contents of Facility	Remarks
Raw Water Intake & Raw Water Transmission Facility	Intake Well	3-Gates at Each 3 Stages Inlet Opening	Salaulim Dam
	Pump & Motor	Vertical Turbine Self Water Lubricated Pump: <sup>Q</sup> 1,181m <sup>3</sup> /hr × <sup>H</sup> 94.56m × 410kw × 4 units/system (1 – Standby) × 2 systems	Design Capability of Intake Pump = 85MLD/system
	Rising Main	D1,000mm × 450m × M.S.P. (Gunning) × 1 Line D1,000mm × 550m × M.S.P. (Gunning) × 1 Line	
	Air Chamber	Each 1 unit/system × 2 systems(Negative Pressure Measure)	Not Working
	Zero Valve	1 unit/system × 2 systems (Positive Pressure Measure)	
	Flow Meter	Electromagnetic Flow Meter: 1 unit/system × 2 systems	Not Working
Treatment Facility	Aerator	Cascade Type: Each 1 unit/system × 2 systems	
	Parshal Flume & Flash Mixer	Each 1 unit/system × 2 systems (for Chemical Dosing)	
	Clariflocculator	Circular Horizontal Flow Type with Center Feed/Peripheral Collection Flocculation & Clarifier: <sup>D</sup> 40.0m (Flocc. Zone 17.6m) × <sup>WD</sup> 3.35m × 2 units/system × 2 systems Detention Period: Flocculation – 29min Clarifier – 2 hrs <sup>1)</sup> Surface Loading for Clarifier: 40 m <sup>3</sup> /m <sup>2</sup> /d (28 mm/min) <sup>2)</sup>	1): 2~2.5 hrs 2): 30~40m <sup>3</sup> /m <sup>2</sup> /d
	Filter	Gravity Rapid Sand Filter Type <sup>W</sup> 3.35m × <sup>L</sup> 9.52m × 2cells/basin × 6 basins/system × 2 systems Effective Size of Sand:0.70mm, Depth of Sand: 0.835m Filter Area: 31.9 m <sup>2</sup> /cell, 63.8 m <sup>2</sup> /basin Filtration Rate: 9.1 m/hr <sup>3)</sup> (219 m/d) Air Scouring Rate: 51m/hr/cell <sup>4)</sup> (0.85m <sup>3</sup> /min/m <sup>2</sup> /cell) Backwash Rate: 30m/hr/cell <sup>5)</sup> (0.50m <sup>3</sup> /min/m <sup>2</sup> /cell)	Based on Specifications of Air Blower & Backwash Pump 3): Higher than Standard(4.8~6.0m/hr) 4): 36~54m/hr 5): 24~36m/hr
Clear Water Transmission Facility	Parshal Flume	1unit for Chlorination	
	Clear Water Reservoir	Total Volume=6,745 m <sup>3</sup> /2units Retention Time: 1.0 hr	
Chemical Feeding Facility	Alum Feeding Facility	Dry Aluminum Sulfate Solution Tank: 4 units	
	Lime Feeding Facility	Powder Lime Solution Tank: 4 units	
	Disinfection Facility	Liquid Chlorine (1 tone Container – net 900kg) Chlorinator: 5 units (3 units for Pre-Cl, 2 units for Post-Cl)	
Laboratory	Frequency of Sampling & Analysis	In-Service, Jar Test: Not in Service Every Hour: pH, Turbidity, R-Cl Daily: Turbidity, pH, Alkalinity, Hardness, Chlorine, Mn, Fe, D.O.,R-Cl	
Note: 1) ~ 4) are referring to “Manual on Water Supply and Treatment, Third Edition – Revised and Updated, May 1999”			





Table M31.1.2

Present Conditions of Salaulim Water Treatment Plant (2/11)

Name of Facility		Contents of Facility		Remarks																
Design Capacity of Raw Water Intake & Treated Facility	MLD m <sup>3</sup> /d	163 163,000	: 1.88% Loss :based on 23 hrs instead of 24 hrs		<p>□ Desing Capacity was estimated 5% losses (backwash drain, clarifier's sludge drain, etc.) of nominal capacity reasonable in stead of 23 hours pump running hours which was informed from WTP.</p>															
<b>Head Water Works : Raw Water Intake</b>																				
Design Capacity of Water Treatment Plant	MLD m <sup>3</sup> /d	163 163,000		<p>: 2% Loss</p>																
Intake Channel	Width Length Height Depth (Below LWL) H.W.L... L.W.L.	3.0 : at Bottom 210.0 29.0 : Varying up to 25 m																		
Box Culvert	Width Height Length Water Depth Velocity (Below LWL)	2.0 2.0 195.0 at LWL																		
Wet Well (Pump Well)	Width Length Depth Area Water Depth Volume (Below LWL) Detention Period	9.40 11.40 28.70 200.0 : more than at LWL																		
Pump House & Control Room	Width Length Area of Floor																			
<table border="1"> <thead> <tr> <th colspan="2">Past Record of L. W.L.</th> </tr> <tr> <th>Date</th> <th>Level (m)</th> </tr> </thead> <tbody> <tr> <td>03.06.2000</td> <td>29.90</td> </tr> <tr> <td>04.06.2001</td> <td>31.85</td> </tr> <tr> <td>13.06.2002</td> <td>31.34</td> </tr> <tr> <td>16.06.2003</td> <td>30.08</td> </tr> <tr> <td>08.06.2004</td> <td>31.40</td> </tr> <tr> <td>16.06.2005</td> <td>29.82</td> </tr> </tbody> </table>					Past Record of L. W.L.		Date	Level (m)	03.06.2000	29.90	04.06.2001	31.85	13.06.2002	31.34	16.06.2003	30.08	08.06.2004	31.40	16.06.2005	29.82
Past Record of L. W.L.																				
Date	Level (m)																			
03.06.2000	29.90																			
04.06.2001	31.85																			
13.06.2002	31.34																			
16.06.2003	30.08																			
08.06.2004	31.40																			
16.06.2005	29.82																			



Table M31.1.2 Present Conditions of Salaulim Water Treatment Plant (3/11)

Name of Facility		Contents of Facility		Remarks
Raw Water Pump	Capacity	328.1		<input type="checkbox"/> No. 5 Pump retrofitted with new Pump (Q=1,180 m <sup>3</sup> /hr, H=94 m, 3 stages) trial employment operation on 16 May 2005. <input type="checkbox"/> Pump deficiency decrease year by year. <input type="checkbox"/> Rated capacity in normally and dry season are estimated 1,100 m <sup>3</sup> /hr and 1,020 m <sup>3</sup> /hr respectively.. <input type="checkbox"/> Total raw water capacity is estimated based on the above estimated capacity and pumping running hours. <input type="checkbox"/> Capacity of intake pumps in parallel running operation are not equal to multiple capacity due to insufficient desing of manifold pipe. <input type="checkbox"/> Flow control for raw water conduct to operate by number of pumps in spate of without flow control device despite of varying water level about 25 m in yearly in impoundage. <input type="checkbox"/> Spare parts of mechanical & electrical equipment will be replaced each 15,000 running hours per 2 years. <input type="checkbox"/> Pump performance curve and O & M manual are not in services. <input type="checkbox"/> 8 pumps are operated in summer season without no standby.
		19,685		
		19,685		
		1,181.0		
		28,344		
	Number	8 : 6-Duty	1-System 4-Pumps (1-Standby)	
	Stand-by	2		
	Total Capacity	163,000	: Design pump running hours : 23 hours.	
	Head	94.559		
	Column Pipe Length	25.0		
	Type of Pump	Vertical Turbine Selfwater Lubricated Pump		
	Number of Stages	4.0		
	Maker	Jyoti Ltd.		
Year of Manufacture	1989			
Assessment of Condition	Working			
Raw Water Motor	Motor Output	550		
		410		
	Number	10 : 8 months installed & 2 No. standby		
	Maker	Kirlosker Electric Co.		
	Type of Motor	Induction Motor		
Year of Manufacture	1989			
Assessment of Condition	Good		MOCB:Bad	
Level Meter		Not Provided		
Crane	Capacity	10		
	Type	Semi E.O.T. EOT: Electric Operated Travelling		
	Lift of Crane	7.5		
	Span of Crane	8.5		
	Long Travel	17.5		
	Maker	R.D.Verama & Co.		
Assessment of Condition	Working			

Table M31.1.2

Present Conditions of Salaulim Water Treatment Plant (4/11)

Name of Facility		Contents of Facility		Remarks
Electrical Equipment	Incomers Panel			
	Number	unit	3	
	Assessment of Condition		Working	
	Motor Control Panel			
	Number	unit	8	
	Assessment of Condition		Working	
	Bus Coupler			
	Number	unit	3	
	Assessment of Condition		Working	
	L.T. Panel			
Number	unit	1		
Assessment of Condition		Working		
Capacitors				
Number	unit	8		
Assessment of Condition		Working		
<b>Substation (Transformers)</b>				
Number of Transformer		(1)	(2)	(3)
		33kV/3.3 kV	33kV/440V	33kV/440V
Pole Mounted / Pad Mounted		Outdoor	Outdoor	Outdoor
Capacity	kVA	2,000	250	160
Number	Unit	3	1	1
Stand-by		Note 1)	Note 2)	Note 3)
Maker		1	-	-
		G.E.C.(General Electric Company)	I.T.L.(Indian Transformers Ltd.)	I.T.Ltd.
Commissioned		1998	1998	1998
Likely Design Life	Year	20	18	18
Last Replacement		Not Replaced		
Assessment of Condition		Good, but one of (1) 2,000 kVA was broken on 28 Jun '05, and repair to finish till around 10 July '05.		

□ Electrical Department has provided two 33KV feeders one from the Xeldem Substation, exclusively for Salauli water works. And the second feeder is from Sanvordem (Vaddem) Substation which is a standby feeder. Load is changed over to Vaddem feeder only when the Xeldem feeder is reported faulty. The above two Substation are supplied power from Ponda power substation supplied from Maharashtra and Karthaka States., which is solely power substation with standby system in Goa State.

Note 1): For supplying power to the pumps. One for standby.

Note 2): For supplying power to the treatment plant, substation, wet well and pump house lighting in case the 160 kVA fails.

Note 3): For supplying for substation, wet well and pump house lighting. For supplying the essential load of treatment plant in case of 250 kVA fails.

Table M31.1.2

Present Conditions of Salaulim Water Treatment Plant (5/11)

Name of Facility		Contents of Facility		Remarks
Other Electrical Equipment	Outdoor Vacuum Circuit Breaker	Number	3	Used for metering poupose  Used for metering poupose  Battery supplies 110V for various controls/relays.
		Assessment of Condition	Working	
	Current Transformer	Number	6	
		Assessment of Condition	Working	
	Potential Transformer	Number	6	
		Assessment of Condition	Working	
	Lighting Arrester	Number	5	
		Assessment of Condition	Working	
	Battery with Charger	Maker	Chabhi Electricals	
		Assessment of Condition	Working	
	Oil Filtration Plant	Number	1	
		Assessment of Condition	Working	
<b>Rising Main (Raw Water Transmission Line)</b>				
Rising Main (Raw Water Transmission Line)			① ②	Protection against erosion: Guniting : Reinforced Cement Mortal Coating  C= 110 D= 1.00 200 MLD Q= 0.943 1.179  ① ②  : Protection against upsurge pressure
	Diameter	mm	1,000	
	Length	m	450 550	
	Material		M.S. M.S.	
	Velocity	m/sec	1.201 1.201	
	Head Loss	m	0.721 0.881	
	Assessment of Condition	Pipe Valve	Good Good	
	Number	unit	2	
		Assessment of Condition	Working	
		Number	unit	
Air Chamber		Assessment of Condition	Not Working	☐ Intake pump manufacturer under trial employment will be planning to install and measure by portable ultrasonic flow meter.
	Flow Meter	Number	2	
		Type	Electromagnetic Flow Meter	
	Assessment of Condition		Not Working	

Table M31.1.2

Present Conditions of Salaulim Water Treatment Plant (6/11)

Name of Facility		Contents of Facility		Remarks
		Answer to Questionnaire	Cal. on Design Cap.	
Aerator	Design Capacity	m <sup>3</sup> /hr/unit	3,333.33	3,395.83
		m <sup>3</sup> /d/unit	80,000	81,500
	Number	Unit	2	
	Construction Material		R.C.C.	
	Diameter	m	5.5	
	EL. of Top Aerate	m	120.00	
	Assessment of Condition		Working	
	Number	unit	2	
	Assessment of Condition		Working	
	Number	unit	2	
Assessment of Condition		Working		
Clarifiers / Settling Tank (Clariflocculator Basin)	Design Capacity	m <sup>3</sup> /min/unit	27.78	28.30
		m <sup>3</sup> /hr/unit	1,666.67	1,697.92
		m <sup>3</sup> /d/unit	40,000	40,750
	Number	unit	4	
	Construction Material		R.C.C.	
	Overall Diameter	m	40.00	
	Flocc. Zone Dia.	m	17.60	
	Water Depth	m	3.35	
	Frequency of Desludging		Once a day Twice a day at Mn high content	
	Volume			
Overall	m <sup>3</sup> /unit	4,209.7		
Flocculation Zone	m <sup>3</sup> /unit	815.0		
Clarifying Zone	m <sup>3</sup> /unit	3,394.7		
Detention Period		Re-Calcu.		
Flocculation Zone	min	30	29.3	
Clarifying Zone	min	180	122.2	
Surface Area	m <sup>2</sup> /unit	1,013.35		
Surface Loading	mm/min	27.4		
W.L. of Clarifier	m	118.50		
Assessment of Condition		Working		

: Aeration Fountain

Parshal flume can be measured raw water flow in stead of flow meter which is not working.

35.37

23.0

96.0

1.6hrs

2 ~ 2.5 hr

OK

30 ~ 40 m<sup>3</sup>/d/m<sup>2</sup> = 20.8 ~ 27.8 mm/min

120.0 OK

27.9 OK

Table M31.1.2

Present Conditions of Salaulim Water Treatment Plant (7/11)

Name of Facility		Contents of Facility		Remarks
Flocculator	Number unit	4		
	Construction Material	M.S.		
	Drive Motor	HP kW	2.0 750 rpm 1.5 Maker: ABB Motor	
	Reduction Gear		50 : 1	
	Rotating Bridge		Peripheral Type	
	Assessment of Condition		Working	
Drive Arrangement of Bridge	Number unit	4		
	Carriage	HP kW	2.0 1,500 rpm 1.5 Maker: ABB Motor	
	Reduction Gear		1 : 5	
	Chain Sprocket Ratio		1 : 5	
	Chain Sprocket Ratio		1 : 5	
	Assessment of Condition		Working	
Filter	Number Unit	12	Answer to Questionnaire Cal. on Design Cap.	: 1 unit divided 2 independent cells.
	Construction Material		R.C.C.	
	Type		Rapid Dand Gravity	
	Design Capacity	m <sup>3</sup> /hr/unit m <sup>3</sup> /d/unit	550 13,200 566.7 13,600	14,553.6
	Width	m	9.52	
	Length	m	6.70	
	Filtered Area	m <sup>2</sup> /unit	63.78	
	Velocity	m <sup>3</sup> /d/m <sup>2</sup>	206.9	228.2
	Filter Media			: Rather high filtration rate : 4.8~6.0m/hr (115~144m <sup>3</sup> /d/m <sup>2</sup> ) : 0.45~0.70mm : 0.60~0.75m
	Sand		Effective Size - 0.70mm	
	Depth of Sand	mm	835	
	Support of Underdrain		3 Layers × 350 mm Depth, 3 Layer × 175 mm Depth	
	Type of Underdrain System		CI Pipe Laterals	
	Year Replacement of Media		Replacement of top layer (20 cm) every 2 years	
	Water Level of Filter	m	118.20	
	Assessment of Condition		Working	

Table M31.1.2

Present Conditions of Salaulim Water Treatment Plant (8/11)

Name of Facility		Contents of Facility		Remarks
Filter Washing Method	Air Scouring Rate	m <sup>3</sup> /min/m <sup>2</sup>	0.85 : at per 1 cell using 2 pumps OK	: 36~54 m/hr (0.60~0.90 m <sup>3</sup> /min/m <sup>2</sup> ) : 1 cell = 3 min, another cell = 9 min : 24~36 m/hr (0.40~0.60 m <sup>3</sup> /min/m <sup>2</sup> ) : 1 cell = 14 min, another cell = 6 min Back Wash 3,800 m <sup>3</sup> /d Drain Water = Max. = 7,600 m <sup>3</sup> /d <input type="checkbox"/> Dosing rate of Pre-CL increase the rate in case of high Mn content.
	Air Scouring Time	min	0.43 : at per 1 unit using 2 pump NO	
	Backwash Rate	m <sup>3</sup> /min/m <sup>2</sup>	5	
	Backwashing Time	min	0.50 : at per 1 cell using 2 pumps OK	
	Frequency of Washing		0.37 : at per 1 unit using 3 pump NO	
			10	
Backwash Pump & Motor	Capacity	m <sup>3</sup> /min	7.92	
	Number	m <sup>3</sup> /hr	475.0	
	Stand-by	unit	4.0	
	Total Capacity	unit	2.0	
	Head	m <sup>3</sup> /min	15.83	
	Type of Pump	m <sup>3</sup> /d	22,800	
	Motor Output	m	7.1	
	Maker		Vertical Turbine Selfwater Lubricated Pump	
	Assessment of Condition	HP	37.8	
		kW	28.2	
Air Blower	Capacity		Warthington Prv. Ltd.	
	Number		Working	
	Stand-by		Working	
	Total Capacity	m <sup>3</sup> /min	13.6	
	Head	m <sup>3</sup> /hr	815.0	
	Motor Output	unit	3	
	Maker	unit	1	
	Assessment of Condition	m <sup>3</sup> /min	27.2	
		m <sup>3</sup> /d	39,120	
			3,500 mmWG	
	HP	20.1		
	kW	15.0		
		Swam Pneumatics Prv. Ltd.		
		Working		

Table M31.1.2

Present Conditions of Salaulim Water Treatment Plant (9/11)

Name of Facility		Contents of Facility		Remarks
Parshal Flume	Number Assessment of Condition	unit Working	2	
Clear Water Reservoir	Number of C.W.R.	Unit	(1) (2)	
	Width	m	31.2 50.0	
	Length	m	24.0 15.0	
	Water Depth	m	4.5 4.5	
	Number	Unit	1 1	
	Volume	m <sup>3</sup>	3,370 3,375	
	Last Date of Cleaning			
	Total	m <sup>3</sup>	6,745	
	Detention Time	hr	1.0	
	Water Level	m	H.W.L. +117.15 m L.W.L. +110.65 m (Bottom of Clear Water Reservoir)	
Assessment of Condition		Good		
<b>Chemical Facility</b>				
Alum Feeding Facility	Number	Unit	4	Production Site : Manufacture by Goa
	Stand-by			
Lime Feeding Facility	Alum Storage Volume		At least 1 month	Production Site : Rajasthan
	Assessment of Condition		Working	
Disinfection System	Number	Unit	4	Production Site : Mumbai, Karwar
	Stand-by			
	Lime Storage Volume		At least 1 month	
	Assessment of Condition		Working	
	Chemical Used		1 ton (Net: 900 kg) Container	
	Type of Plant & Machinery		Aquapura Make Chlorinator	
	Capacity	kg/hr	7.0	
	Number	Unit	5 : 3 for Pre-CL, 2 for Post-CL	
	Stand-by		1	
	Safety Measures Taken		Neutralization Tanks with Caustic Soda Solution Solution are available : Protection Masks	
Commissioned		1992		
Storage Volume		At least 1 month		
Assessment of Condition		Working		

Table M31.1.2

Present Conditions of Salaulim Water Treatment Plant (10/11)

Name of Facility	Contents of Facility	Remarks
<b>Laboratory</b>		
Chemical Testing Laboratory	In-service Physical, Chemical & Bacteriological	<input type="checkbox"/> Sampling send to laboratory of Marugao and Panaji for water quality analysis ever once a month.  <input type="checkbox"/> Mn : Nov.~Mar. - Very Low Content
Jar Testing	Not in-service	
Availability of Skilled Chemists	Four (Lab. Technician)	
Availability of Required Chemicals	Good : Min. storage for Alum, lime & Chlorine 1 month is 1 month.	
Use of Test Reports	As per Format	
Frequency of Sampling & Analysis	Every Hour: pH, Turb. R. Cl, Daily : Other (Turb., pH, Alkalinity, Hardness, Chloride, Mn, Fe, D.O., Fe, R.-Cl) Test : RAW water 1 time/week : Clear water daily	
General Quality of Water	Good	
Raw Water Quality	Turb. Mn (seasonal high), Low pH	
Clear Water Quality	Good	
<b>Equipment Status</b>		
Flow Meters	Not-Working	
Other Operating Valves	Working	
<b>Other Important Assets</b>		
Valve's Condition	Working	
Visible Leakage and Locations	Nil	
Wastewater Disposal Arrangements	Disposal through Canal to Dam Impoundage	



Table M31.1.2

Present Conditions of Salaulim Water Treatment Plant (11/11)

<b>Organization &amp; Staff Deployed</b>			
General Shift	08:30 am → 05:30 pm		
Working Hour :			
Staff Deployed :		1 Person	Assistant Engineer
		2 Persons	Junior Engineer : in charge of Intake Pumping Station & Treatment Plant
		2 Persons	Chemist
		1 Person	Electrician
		2 Persons	Mechanic
		2 Persons	Helper
		12 Persons	Labour
		22 Persons	Total
Shift in Plant Operation	3 Shifting System Covering 24 Hours		
Working Hour :	ⓐ: 06:00 am → 02:00 pm, ⓑ: 02:00 pm → 10:00 pm, ⓒ: 10:00 pm → 06:00 am		
Grouping Staff Deployed :		1 Person	Junior Engineer : 02:00 pm → 06:00 am on alternate days (1 of 2 Junior Engineers is Electrician to be promoted in shift charge)
		3 Persons	Intake
		4 Persons	Clarifier & Filter
		4 Persons	Chemical : including 1-Chemist
		12 Persons	Total
Staff Deployed at the Plant		Person	Qualification
Management Staff - Engineers		Year of Service	Service at plant
Assistant Engineer	1 B.E. (Mech)	24	2 : 11 years at Verna Pumping Station
Junior Engineer	1 D.M.E.	23	10 : in charge of Treatment Plant
	1 D.E.E.	9	9 : in charge of Intake Pumping Station
	1 D.E.E.	4	4 : in charge of shifting
Sub-total	4		
Skilled Staff - Operators / Quality Testing			
Lab - Technician (Chemist)	2 BSC (Chemist)	14	14
Chlorine Operator ?	1 S.S.C.	13	13
Filter Operator ?	2 S.S.C.	12	12
Other Skilled Staff ?	45		
Sub-total	50		
Unskilled Staff	55		
Total Number	109		













**Table M31.1.4 Water Quality at Salaulim WTP in 2003 (1/6)**

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated
1-Jan-03	6.56	8.46	0.9	0.4	16	28	17	34	5.5	6	1.2		6.2	6.8				1.2
2-Jan-03	6.56	8.50	0.9	0.3	15	28	17	33	5.5	6	1.2		6.2	7				1.2
3-Jan-03	6.63	8.54	0.8	0.2	16.0	29.0	18.0	36.0	6.0	6.5	0.2		6.0	6.8				1.2
4-Jan-03																		
5-Jan-03																		
6-Jan-03																		
7-Jan-03	6.98	8.00	0.8	0.2	17.0	27.0	18.0	30.0	6.0	6.5			6.2	7.0				1.2
8-Jan-03	6.70	7.98	0.8	0.2	16.0	24.0	17.0	28.0	6.0	6.5			6.4	7.0				1.2
9-Jan-03																		
10-Jan-03	7.00	7.65	0.8	0.2	17.0	23.0	18.0	26.0	6.0	6.5			6.0	6.8			0.2	0.8
11-Jan-03																		
12-Jan-03																		
13-Jan-03																		
14-Jan-03	6.97	7.37	1.0	0.3	16.0	19.0	17.0	21.0	6.0	6.0			6.0	7.0			0.3	0.7
15-Jan-03	6.98	7.39	0.8	0.2	16.0	20.0	18.0	21.0	6.0	6.5			6.0	7.2			0.3	0.8
16-Jan-03	6.95	7.34	0.8	0.2	16.0	19.0	17.0	21.0	6.0	6.5			6.2	7.0			0.3	0.8
17-Jan-03	6.90	7.38	1.0	0.3	16.0	19.0	17.0	20.0	6.0	6.5			6.0	6.8			0.2	0.8
18-Jan-03																		
19-Jan-03																		
20-Jan-03																		
21-Jan-03	6.89	7.32	0.8	0.2	16.0	19.0	17.0	21.0	5.5	6.0			6.0	6.8			0.3	0.8
22-Jan-03	6.95	7.30	0.8	0.3	15.0	19.0	17.0	21.0	5.5	6.0			6.2	6.8			0.3	0.8
23-Jan-03																		
24-Jan-03	6.80	7.20	0.8	0.2	15.0	18.0	17.0	20.0	5.5	6.0			6.0	6.8			0.1	1.0
25-Jan-03																		
26-Jan-03																		
27-Jan-03																		
28-Jan-03	6.80	7.25	0.8	0.3	15.0	17.0	17.0	20.0	6.0	6.5			6.0	7.0			0.1	1.0
29-Jan-03	6.95	7.23	0.8	0.3	15.0	18.0	18.0	21.0	6.0	6.5			6.2	7.0			0.3	0.8
30-Jan-03																		
31-Jan-03	6.90	7.25	1.0	0.5	15.0	18.0	18.0	20.0	6.0	6.0			6.2	7.2			0.3	0.7
Max	7.0	8.5	1.0	0.5	17.0	29.0	18.0	36.0	6.0	6.5			6.4	7.2	0	0	0.3	1.2
Min	6.6	7.2	0.8	0.2	15.0	17.0	17.0	20.0	5.5	6.0			6.0	6.8	0.00	0.00	0.1	0.7
Average	6.9	7.5	0.8	0.3	15.8	20.6	17.4	23.3	5.9	6.3			6.1	6.9	#DIV/0!	#DIV/0!	0.2	0.9

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated
1-Feb-03	6.98	7.25	0.8	0.3	15.0	18.0	17.0	21.0	6.0	6.0			6.0	7.0			0.1	0.7
2-Feb-03	6.97	7.24	0.8	0.3	15.0	18.0	17.0	21.0	6.0	6.5			6.2	7.0			0.3	1.0
3-Feb-03	6.97	7.32	1.0	0.3	15.0	19.0	18.0	21.0	6.0	6.5			6.0	6.8			0.3	0.8
4-Feb-03	6.80	7.20	1.5	0.6	17.0	20.0	18.0	22.0	6.0	6.5			6.0	7.0			0.2	0.8
5-Feb-03	6.80	7.20	1.3	0.7	17.0	19.0	18.0	21.0	6.0	6.5			6.0	7.2			0.2	0.7
6-Feb-03																		
7-Feb-03																		
8-Feb-03																		
9-Feb-03																		
10-Feb-03																		
11-Feb-03																		
12-Feb-03																		
13-Feb-03																		
14-Feb-03																		
15-Feb-03																		
16-Feb-03																		
17-Feb-03																		
18-Feb-03	6.88	7.20	1.4	0.7	16.0	20.0	18.0	22.0	5.5	6.0			6.0	6.8			0.2	0.7
19-Feb-03	6.87	7.05	1.4	0.7	16.0	18.0	18.0	19.0	5.5	6.0			6.2	7.0			0.2	0.7
20-Feb-03																		
21-Feb-03																		
22-Feb-03																		
23-Feb-03																		
24-Feb-03	6.70	7.12	1.2	0.5	15.0	18.0	16.0	19.0	6.0	6.5			6.2	6.8			0.3	0.7
25-Feb-03	6.75	7.05	1.4	0.6	16.0	19.0	18.0	20.0	5.5	6.0			6.0	7.0			0.2	0.7
26-Feb-03	6.68	7.00	1.7	0.6	15.0	17.0	18.0	20.0	5.5	6.0			6.0	7.0			0.3	0.7
27-Feb-03																		
28-Feb-03	6.58	7.34	1.5	0.6	14.0	19.0	16.0	21.0	6.0	6.5			6.0	6.8			0.2	0.7
Max	7.0	7.3	1.7	0.7	17.0	20.0	18.0	22.0	6.0	6.5			6.2	7.2	0	0	0.3	0.8
Min	6.6	7.0	1.0	0.3	14.0	17.0	16.0	19.0	5.5	6.0			6.0	6.8	0.00	0.00	0.2	0.7
Average	6.8	7.2	1.4	0.6	15.7	18.8	17.6	20.6	5.8	6.3			6.0	6.9	#DIV/0!	#DIV/0!	0.2	0.7



**Table M31.1.4 Water Quality at Salaulim WTP in 2003 (2/6)**

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated
1-Mar-03																		
2-Mar-03																		
3-Mar-03																		
4-Mar-03																		
5-Mar-03																		
6-Mar-03	6.63	7.71	1.6	0.7	15.0	20.0	17.0	25.0	5.5	6.0	0.3		6.2	6.8			0.3	0.8
7-Mar-03	6.54	8.00	1.5	0.7	16.0	26.0	17.0	30.0	6.0	6.5	0.3		6.0	7.0			0.2	0.6
8-Mar-03	6.59	8.10	1.8	0.7	16.0	27.0	17.0	31.0	6.0	6.5	0.4		6.2	7.0			0.3	0.8
9-Mar-03	6.57	8.08	1.8	0.7	16.0	27.0	18.0	30.0	6.0	6.5	0.5		6.0	7.0				1.2
10-Mar-03	6.62	7.90	1.8	0.6	17.0	26.0	19.0	30.0	6.0	6.5	0.4		6.0	7.0				1.0
11-Mar-03																		
12-Mar-03	6.63	7.90	1.6	0.7	17.0	25.0	18.0	30.0	6.0	6.5	0.3		6.0	7.0				1.0
13-Mar-03	6.76	8.24	1.4	0.4	17.0	25.0	18.0	30.0	5.5	6.5	0.4		6.0	6.8				1.2
14-Mar-03	6.72	8.37	1.6	0.4	16.0	26.0	18.0	32.0	6.0	6.5	0.4		6.2	6.8				1.2
15-Mar-03	6.65	8.18	1.5	0.5	16.0	25.0	18.0	32.0	6.0	6.5	0.3		6.0	6.8				1.2
16-Mar-03																		
17-Mar-03																		
18-Mar-03																		
19-Mar-03																		
20-Mar-03																		
21-Mar-03	6.90	8.38	1.8	0.7	16.0	27.0	18.0	34.0	6.5	7.0	0.5		6.0	6.8				1.2
22-Mar-03																		
23-Mar-03																		
24-Mar-03																		
25-Mar-03	6.70	8.10	1.5	0.7	16.0	25.0	18.0	30.0	6.5	7.0	0.8		6.0	6.8				1.2
26-Mar-03	6.70	8.05	1.5	0.7	16.0	25.0	18.0	30.0	6.5	6.5	0.4		6.0	7.0				1.0
27-Mar-03	6.75	8.18	1.5	0.7	16.0	27.0	18.0	32.0	6.6	7.0	0.4		6.0	7.0				1.2
28-Mar-03																		
29-Mar-03																		
30-Mar-03																		
31-Mar-03																		
Max	6.9	8.4	1.8	0.7	17.0	27.0	19.0	34.0	6.6	7.0	0.8	0.0	6.2	7.0	0	0	0.3	1.2
Min	6.5	7.7	1.4	0.4	15.0	20.0	17.0	25.0	5.5	6.0	0.3	0.0	6.0	6.8	0.00	0.00	0.2	0.6
Average	6.7	8.1	1.6	0.6	16.2	25.5	17.8	30.5	6.1	6.6	0.4	#DIV/0!	6.0	6.9	#DIV/0!	#DIV/0!	0.3	1.0

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated
1-Apr-03	6.80	7.70	1.4	0.6	15.0	24.0	17.0	25.0	6.0	6.5	0.4		6.0	7.0				1
2-Apr-03	6.85	8.40	1.2	0.6	16.0	26.0	17.0	27.0	6.0	6.5	0.3		6.0	7.0				1
3-Apr-03																		
4-Apr-03																		
5-Apr-03																		
6-Apr-03																		
7-Apr-03																		
8-Apr-03	6.86	7.75	1.8	0.7	16.0	24.0	17.0	26.0	6.0	6.5	0.3		6.2	7.0				1.0
9-Apr-03	6.81	7.53	1.6	0.6	15.0	22.0	16.0	24.0	6.0	6.5	0.4		6.2	6.8				1.0
10-Apr-03																		
11-Apr-03	6.80	7.70	1.8	0.7	17.0	24.0	18.0	28.0	6.0	6.5	0.4		6.0	7.0				1.0
12-Apr-03																		
13-Apr-03																		
14-Apr-03																		
15-Apr-03	6.98	7.60	1.8	0.5	18.0	24.0	20.0	26.0	6.0	6.5			6.2	7.2			0.3	0.6
16-Apr-03																		
17-Apr-03																		
18-Apr-03																		
19-Apr-03																		
20-Apr-03																		
21-Apr-03																		
22-Apr-03	6.95	7.25	2.0	0.8	17.0	21.0	18.0	23.0	6.0	6.5			6.2	7.0			0.3	0.7
23-Apr-03	6.98	7.20	2.8	1.4	17.0	20.0	19.0	24.0	6.0	6.5			6.2	7.0			0.3	0.6
24-Apr-03																		
25-Apr-03																		
26-Apr-03																		
27-Apr-03																		
28-Apr-03																		
29-Apr-03	7.00	7.28	3.3	1.5	17.0	22.0	19.0	24.0	6.5	7.0			6.0	7.0			0.2	0.6
30-Apr-03																		
Max	7.0	7.8	3.3	1.5	18.0	24.0	20.0	28.0	6.5	7.0	0.4	0.0	6.2	7.2	0	0	0.3	1.0
Min	6.8	7.2	1.6	0.5	15.0	20.0	16.0	23.0	6.0	6.5	0.3	0.0	6.0	6.8	0.00	0.00	0.2	0.6
Average	6.9	7.5	2.2	0.9	16.7	22.4	18.1	25.0	6.1	6.6	0.4	#DIV/0!	6.1	7.0	#DIV/0!	#DIV/0!	0.3	0.8

**Table M31.1.4 Water Quality at Salaulim WTP in 2003 (3/6)**

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L		
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated	
1-May-03																			
2-May-03	6.90	7.28	3	1.5	17.0	20.0	19.0	23.0	6.5	7.0			6.2	7.4			0.3	0.5	
3-May-03																			
4-May-03																			
5-May-03																			
6-May-03	7.05	7.28	2.8	1.2	17.0	20.0	18.0	23.0	6.0	6.5			6.0	7.0			0.2	0.6	
7-May-03	7.00	7.18	2.0	1.2	18.0	20.0	20.0	22.0	6.0	6.5			6.0	7.2			0.2	0.6	
8-May-03																			
9-May-03																			
10-May-03																			
11-May-03																			
12-May-03	6.94	7.24	2.2	1.2	17	19	18	22	6.0	6.5			6.2	7.0			0.1	0.5	
13-May-03	7.03	7.15	1.5	0.7	16	20	19	22	6.5	7.0			6.0	7.2	0.04		0.2	0.6	
14-May-03	7.10	7.32	1.5	0.5	17	21	20	23	6.5	7.0			6.0	7.2	0.04		0.3	0.6	
15-May-03																			
16-May-03	7.10	7.26	1.5	0.5	17	19	19	22	6.0	6.5			6.2	7.0	0.04		0.3	0.6	
17-May-03	7.14	7.32	1.6	0.5	17	19	19	22	6.0	6.5			6.2	7.2	0.04		0.3	0.6	
18-May-03																			
19-May-03																			
20-May-03	7.14	7.35	1.6	0.6	17	19	20	23	6.0	6.5			6.4	7.2	0.04		0.3	0.6	
21-May-03	7.14	7.36	1.6	0.5	17	20	20	23	6.0	6.5			6.2	7.0	0.02		0.3	0.6	
22-May-03	7.03	7.30	1.5	0.5	17	19	18	22	6.0	6.5			6.4	7.0	0.04		0.3	0.6	
23-May-03	7.11	7.36	1.5	0.5	17	20	18	23	6.0	6.5			6.2	7.2	0.04		0.3	0.6	
24-May-03	7.06	7.32	1.5	0.5	17	19	18	20	6.0	6.5			6.2	7.0	0.02		0.3	0.6	
25-May-03																			
26-May-03	7.08	7.36	1.5	0.5	17	20	18	22	6.0	6.5			6.2	7.2	0.04		0.3	0.6	
27-May-03	7.10	7.39	1.5	0.5	17	20	19	23	6.0	6.5			6.2	7.0	0.04		0.3	0.6	
28-May-03	7.08	7.20	2.7	1.0	18	20	20	24	6.0	7.0			6.0	7.2	0.04		0.2	0.6	
29-May-03	7.10	7.32	2.0	0.8	17	19	20	23	5.5	6.5			6.0	7.2	0.04		0.2	0.6	
30-May-03	7.14	7.26	2.7	1.2	17	18	20	23	6.0	7.0			6.0	7.0	0.01	0.01	0.2	0.6	
31-May-03	7.10	7.25	2.8	1.0	17	19	19	22	6.0	7.0			6.0	7.0	0.01		0.2	0.5	
Max	7.1	7.4	2.8	1.2	18.0	21.0	20.0	24.0	6.5	7.0	0.0	0.0	6.4	7.2	0.04	0.01	0.3	0.6	
Min	6.9	7.2	1.5	0.5	16.0	18.0	18.0	20.0	5.5	6.5	0.0	0.0	6.0	7.0	0.01	0.01	0.1	0.5	
Average	7.1	7.3	1.9	0.7	17.1	19.5	19.1	22.4	6.0	6.6	#DIV/0!	#DIV/0!	6.1	7.1	0.03	0.01	0.3	0.6	

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L		
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated	
1-Jun-03																			
2-Jun-03	7.02	7.26	2.6	1.4	16.0	19.0	18.0	22.0	6.0	6.5			6.2	7	0.01		0.2	0.6	
3-Jun-03	7.02	7.25	2.5	1.5	16.0	19.0	19.0	22.0	6.0	6.5			6.2	7.0	0.01		0.2	0.6	
4-Jun-03	7.01	7.26	2.4	1.4	16.0	19.0	18.0	22.0	6.0	6.5			6.4	7.2	0.01		0.2	0.6	
5-Jun-03	7.03	7.22	2.4	1.2	16.0	19.0	18.0	22.0	6.0	6.5			6.2	7.0	0.01		0.2	0.6	
6-Jun-03	7.04	7.22	2.4	1.2	16.0	18.0	18.0	22.0	6.0	6.5			6.4	7.0	0.01		0.2	0.6	
7-Jun-03																			
8-Jun-03	7.04	7.24	2.4	1.2	16.0	19.0	18.0	23.0	6.0	6.5			6.4	7.2	0.01		0.2	0.6	
9-Jun-03	7.04	7.23	2.4	1.2	16.0	18.0	18.0	22.0	6.0	6.5			6.4	7.0	0.02		0.2	0.5	
10-Jun-03	7.10	7.32	2.8	1.2	17.0	20.0	18.0	22.0	6.5	7.0			6.2	7.4	0.04	0.01	0.2	0.6	
11-Jun-03	7.05	7.20	2.9	1.3	18.0	21.0	19.0	23.0	6.0	6.5			6.4	7.8	0.05	0.01	0.2	0.6	
12-Jun-03	7.06	7.23	2.8	1.4	17.0	20.0	18.0	23.0	6.0	6.5			6.4	7.4	0.06	0.01	0.2	0.4	
13-Jun-03	7.10	7.40	3.0	1.5	17.0	20.0	19.0	23.0	6.0	6.5			6.4	7.2	0.06	0.01	0.2	0.6	
14-Jun-03	7.08	7.39	3.0	1.5	17.0	20.0	19.0	24.0	6.0	6.5			6.4	7.2	0.06	0.02	0.2	0.5	
15-Jun-03	7.03	7.31	6.0	2.0	17.0	20.0	18.0	23.0	6.0	6.5			6.2	7.0	0.08	0.02	0.2	0.6	
16-Jun-03																			
17-Jun-03	6.96	7.84	4.2	1.2	16.0	22.0	18.0	25.0	6.0	6.5	0.1		6.4	7.2	0.08	0.02	0.2	0.6	
18-Jun-03	7.01	7.98	7.0	2.0	18.0	22.0	19.0	25.0	6.0	6.5	0.3		6.4	7.0	0.06	0.02	0.2	0.6	
19-Jun-03	7.04	7.96	6.4	2.2	18.0	22.0	19.0	26.0	6.0	6.5	0.3		6.4	7.2	0.05	0.02	0.2	0.6	
20-Jun-03	7.16	8.47	7.0	2.0	18.0	24.0	20.0	30.0	6.0	6.5	0.3		6.2	7.4	0.05	0.05	0.2	0.6	
21-Jun-03	7.10	8.07	7.6	2.2	18.0	23.0	20.0	26.0	6.0	6.5	0.3		6.2	7.2	0.05	0.02	0.2	0.6	
22-Jun-03																			
23-Jun-03	6.87	7.61	18.2	2.5	20.0	26.0	22.0	32.0	6.0	6.5	3.2	0.05	6.4	7.0	0.08	0.05		0.5	
24-Jun-03	6.90	8.04	22.0	1.8	20.0	26.0	22.0	33.0	6.0	6.5	3.6	0.3	6.2	7.4	0.7	0.05		1.2	
25-Jun-03	6.78	8.10	25.0	2.3	21.0	30.0	24.0	37.0	6.0	6.5	3	0.2	6.2	7.4	0.5	0.05		1.0	
26-Jun-03	6.81	8.21	24.0	2.2	21.0	32.0	25.0	37.0	6.0	6.5	3	0.2	6.2	7.2	0.5	0.05		1.0	
27-Jun-03	6.67	8.03	28.0	2.5	20.0	31.0	24.0	36.0	6.0	6.5	2.8	0.1	6.4	7.2	0.8	0.06		1.2	
28-Jun-03	6.86	8.41	22.0	2.2	18.0	32.0	21.0	36.0	6.0	6.5	1.8	0.05	6.4	7.2	0.5	0.03		1.2	
29-Jun-03																			
30-Jun-03	6.81	8.48	20.0	2.0	18.0	29.0	20.0	36.0	6.0	6.5	1.2		6.4	7.4	0.6	0.05		0.6	
Max	7.2	8.5	28.0	2.5	21.0	32.0	25.0	37.0	6.5	7.0	3.6	0.3	6.4	7.8	0.8	0.06	0.2	1.2	
Min	6.7	7.2	2.4	1.2	16.0	18.0	18.0	22.0	6.0	6.5	0.1	0.1	6.2	7.0	0.01	0.01	0.2	0.4	
Average	7.0	7.7	9.4	1.7	17.7	23.0	19.8	27.1	6.0	6.5	1.7	0.2	6.3	7.2	0.18	0.03	0.2	0.7	

**Table M31.1.4 Water Quality at Salaulim WTP in 2003 (4/6)**

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated
1-Jul-03	6.78	8.03	20	1.8	18.0	27.0	19.0	31.0	6.0	6.5	1.0		6.2	7.2	0.60	0.05		0.6
2-Jul-03	6.70	7.91	20	2	16.0	25.0	18.0	32.0	6.0	6.5	0.8		6.2	7	0.80	0.06		1
3-Jul-03	6.71	7.93	18.0	2.0	16.0	24.0	18.0	32.0	6.0	6.5	0.8		6.2	7.2	0.60	0.05		1.0
4-Jul-03	6.71	7.85	15.0	2.0	16.0	24.0	18.0	29.0	6.0	6.5	0.6		6.4	7.2	0.70	0.06		1.0
5-Jul-03																		
6-Jul-03																		
7-Jul-03																		
8-Jul-03	6.83	7.64	10.0	2.0	16.0	22.0	18.0	25.0	6.0	6.5	0.3		6.2	7.0	0.60	0.05		1.0
9-Jul-03	6.81	7.67	6.0	1.8	16.0	20.0	17.0	24.0	6.0	6.5			6.4	7.2	0.40	0.02		0.8
10-Jul-03	6.75	7.60	6.0	2.1	16.0	19.0	17.0	23.0	6.0	6.5			6.4	7.0	0.40	0.01		1.0
11-Jul-03	6.82	7.60	5.0	2.0	17.0	20.0	17.0	23.0	6.0	6.5			6.4	7.2	0.10	0.02		1.0
12-Jul-03	6.93	7.56	5.0	2.0	17.0	19.0	18.0	22.0	6.0	6.5			6.4	7.2	0.20	0.02		0.8
13-Jul-03																		
14-Jul-03	6.86	7.51	5.0	1.8	17.0	19.0	18.0	22.0	6.0	6.5			6.4	7.2	0.10	0.02	0.2	0.8
15-Jul-03	6.80	7.60	4.0	2.0	17.0	20.0	18.0	22.0	6.0	6.5			6.4	7.2	0.10	0.05	0.2	0.6
16-Jul-03	6.85	7.64	4.5	1.6	17.0	20.0	18.0	23.0	6.0	6.5			6.4	7.2	0.10	0.05	0.2	0.7
17-Jul-03	6.82	7.60	5.0	1.6	17.0	20.0	18.0	22.0	6.0	6.5			6.2	7.0	0.10	0.05	0.2	0.5
18-Jul-03	6.87	7.61	4.5	1.6	16.0	20.0	18.0	23.0	6.0	6.5			6.4	7.0	0.10	0.02		1.0
19-Jul-03	6.86	7.62	4.0	1.5	16.0	19.0	17.0	22.0	6.0	6.5			6.2	7.2	0.01	0.05	0.2	0.8
20-Jul-03																		
21-Jul-03	6.81	7.59	4.0	1.5	16.0	19.0	17.0	22.0	6.0	6.5			6.6	7.3	0.20	0.01	0.2	0.6
22-Jul-03	6.80	7.54	4.0	1.8	16.0	20.0	17.0	23.0	6.0	6.5			6.4	7.2	0.20	0.02		1.0
23-Jul-03	6.80	7.60	3.8	1.8	16.0	19.0	17.0	22.0	6.0	6.5			6.4	7.2	0.20	0.02		0.6
24-Jul-03	6.81	7.59	4.0	1.6	16.0	19.0	17.0	21.0	6.0	6.5			6.4	7.2	0.20	0.01	0.2	0.8
25-Jul-03	6.80	7.63	3.5	1.7	15.0	20.0	17.0	24.0	6.0	6.5			6.4	7.2	0.50		0.2	0.6
26-Jul-03	6.80	7.63	4.0	1.5	16.0	19.0	17.0	23.0	6.0	6.5			6.4	7.0	0.10	0.05	0.2	0.6
27-Jul-03																		
28-Jul-03	6.72	7.58	3.5	1.5	16.0	18.0	17.0	22.0	6.0	6.5			6.4	7.0	0.01		0.2	0.6
29-Jul-03	6.65	7.57	4.0	1.0	16.0	19.0	17.0	23.0	6.0	6.5			6.2	7.2	0.05		0.2	0.6
30-Jul-03	6.60	7.60	4.0	1.8	15.0	20.0	18.0	23.0	6.0	6.5			6.2	7.4	0.10	0.05	0.2	0.6
31-Jul-03	6.64	7.59	3.8	1.6	16.0	20.0	17.0	23.0	6.0	6.5			6.2	7.2	0.10	0.05	0.2	0.6
Max	6.9	7.9	18.0	2.1	17.0	24.0	18.0	32.0	6.0	6.5	0.8	0.0	6.6	7.4	0.7	0.06	0.2	1.0
Min	6.6	7.5	3.5	1.0	15.0	18.0	17.0	21.0	6.0	6.5	0.3	0.0	6.2	7.0	0.01	0.01	0.2	0.5
Average	6.8	7.6	5.7	1.7	16.2	20.0	17.4	23.4	6.0	6.5	0.6	#DIV/0!	6.3	7.2	0.22	0.03	0.2	0.8

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated
1-Aug-03	6.66	7.50	3.0	1.0	11.0	19.0	17.0	22.0	6.0	6.5			6.2	7.4	0.05		0.2	0.5
2-Aug-03	6.60	7.42	3.0	1.0	15.0	18.0	17.0	20.0	6.0	6.5			6.2	7.2	0.05		0.2	0.6
3-Aug-03																		
4-Aug-03	6.51	7.20	3.0	1.0	15.0	17.0	16.0	19.0	6.0	6.5			6.4	7.2	0.02	0.05	0.2	0.6
5-Aug-03	6.54	7.22	3.0	1.0	16.0	18.0	17.0	20.0	6.0	6.5			6.4	7.2	0.05		0.2	0.6
6-Aug-03	6.60	7.29	3.0	1.5	17.0	20.0	18.0	22.0	6.0	6.5			6.4	7.2	0.05	0.02	0.2	0.6
7-Aug-03	6.58	7.26	3.0	1.0	16.0	19.0	18.0	22.0	6.0	6.5			6.4	7.0	0.08	0.03	0.2	0.4
8-Aug-03	6.62	7.37	3.0	1.0	16.0	19.0	18.0	23.0	6.0	6.5			6.2	7.0	0.05	0.02	0.2	0.5
9-Aug-03	6.48	7.24	3.0	1.0	15.0	18.0	18.0	22.0	6.0	6.5			6.2	7.0	0.05		0.2	0.6
10-Aug-03	6.51	7.28	3.0	1.0	16.0	19.0	18.0	22.0	6.0	6.5			6.4	7.2	0.05		0.2	0.6
11-Aug-03																		
12-Aug-03	6.50	7.53	3.0	1.0	16.0	20.0	18.0	23.0	6.0	6.5			6.2	7.4	0.05		0.2	0.5
13-Aug-03	6.57	7.52	3.0	1.0	15.0	20.0	17.0	23.0	6.0	6.5			6.2	7.2	0.05		0.2	0.6
14-Aug-03	6.51	7.41	3.0	1.0	15.0	19.0	17.0	22.0	6.0	6.5			6.4	7.2	0.03		0.2	0.6
15-Aug-03	6.50	7.41	3.0	1.0	15.0	19.0	17.0	21.0	6.0	6.5			6.2	7.0	0.05		0.2	0.6
16-Aug-03	6.43	7.36	3.0	1.0	15.0	18.0	17.0	21.0	6.0	6.5			6.2	7.0	0.04		0.2	0.6
17-Aug-03																		
18-Aug-03																		
19-Aug-03	6.47	7.33	3.0	1.0	15.0	18.0	16.0	22.0	6.0	6.5			6.4	7.0	0.05		0.2	0.6
20-Aug-03	6.40	7.28	3.0	1.0	15.0	17.0	16.0	21.0	6.0	6.5			6.2	7.0	0.08	0.01	0.2	0.6
21-Aug-03	6.41	7.31	3.0	1.0	16.0	19.0	17.0	22.0	6.0	6.5			6.4	7.2	0.04		0.2	0.6
22-Aug-03	6.50	7.30	3.0	1.2	15.0	19.0	17.0	22.0	6.0	6.5			6.4	7.0	0.04		0.2	0.5
23-Aug-03	6.50	7.30	3.0	1.0	15.0	19.0	17.0	21.0	6.0	6.5			6.2	7.0	0.03		0.2	0.6
24-Aug-03																		
25-Aug-03	6.51	7.31	2.5	0.8	1.0	18.0	17.0	21.0	6.0	6.5			6.4	7.0	0.04		0.2	0.5
26-Aug-03	6.50	7.30	2.8	1.0	15.0	19.0	17.0	21.0	6.0	6.5			6.2	7.0	0.03		0.2	0.5
27-Aug-03	6.46	7.27	3.0	1.0	15.0	19.0	17.0	21.0	6.0	6.5			6.4	7.0	0.03		0.2	0.6
28-Aug-03	6.53	7.31	3.0	1.0	15.0	19.0	17.0	22.0	6.0	6.5			6.2	7.0	0.03		0.2	0.6
29-Aug-03	6.48	7.29	3.0	1.0	15.0	18.0	17.0	21.0	6.0	6.5			6.4	7.2	0.04		0.2	0.5
30-Aug-03																		
31-Aug-03																		
Max	6.6	7.5	3.0	1.5	17.0	20.0	18.0	23.0	6.0	6.5	0.0	0.0	6.4	7.4	0.08	0.05	0.2	0.6
Min	6.4	7.2	2.5	0.8	1.0	17.0	16.0	19.0	6.0	6.5	0.0	0.0	6.2	7.0	0.02	0.01	0.2	0.4
Average	6.5	7.3	3.0	1.0	14.7	18.7	17.1	21.5	6.0	6.5	#DIV/0!	#DIV/0!	6.3	7.1	0.04	0.03	0.2	0.6

**Table M31.1.4 Water Quality at Salaulim WTP in 2003 (5/6)**

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated
1-Sep-03	6.55	7.25	2.9	1.5	15.0	19.0	17.0	21.0	6.0	6.5			6.4	7.2	0.05	0.05	0.2	0.6
2-Sep-03																		
3-Sep-03	6.43	7.22	2.8	1.2	14.0	19.0	17.0	21.0	6.0	6.0			6.2	7.0	0.01	0.02	0.2	0.6
4-Sep-03	6.30	7.40	3.0	1.2	14.0	19.0	16.0	23.0	6.0	6.5			6.2	7.0	0.05	0.05	0.2	0.6
5-Sep-03	6.33	7.53	3.0	1.5	14.0	19.0	17.0	22.0	6.0	6.5			6.2	7.2	0.05	0.03	0.2	0.6
6-Sep-03	6.34	7.47	3.0	1.0	14.0	20.0	17.0	23.0	6.0	6.5			6.4	7.0	0.04		0.2	0.5
7-Sep-03																		
8-Sep-03	6.33	7.31	3.0	1.0	15.0	19.0	17.0	22.0	6.0	6.5			6.2	7.0	0.03		0.2	0.6
9-Sep-03	6.40	7.40	3.0	1.5	15.0	19.0	17.0	21.0	6.0	6.5			6.2	7.4	0.05	0.05	0.2	0.6
10-Sep-03	6.40	7.40	3.0	1.2	14.0	19.0	17.0	21.0	6.0	6.0			6.0	7.4	0.05	0.02	0.2	0.6
11-Sep-03	6.41	7.43	3.5	1.2	14.0	19.0	17.0	22.0	6.0	6.5			6.2	7.2	0.05	0.02	0.2	0.6
12-Sep-03	6.60	7.30	3.0	1.2	15.0	19.0	17.0	21.0	6.0	6.5			6.2	7.0	0.05		0.2	0.6
13-Sep-03	6.47	7.31	3.0	1.0	14.0	19.0	17.0	21.0	6.0	6.5			6.2	7.0	0.05	0.01	0.2	0.6
14-Sep-03																		
15-Sep-03	6.43	7.30	2.5	1.0	14.0	19.0	17.0	22.0	6.0	6.5			6.4	7.2	0.03		0.2	0.6
16-Sep-03	6.62	7.28	3.0	1.2	16.0	20.0	17.0	23.0	6.5	6.5			6.5	7.8	0.05		0.2	0.6
17-Sep-03																		
18-Sep-03	6.32	7.21	3.8	1.4	14.0	18.0	16.0	21.0	6.0	6.5			6.4	7.4	0.03		0.2	0.8
19-Sep-03	6.55	7.35	3.0	1.2	15.0	20.0	17.0	22.0	6.0	6.5			6.6	7.8	0.1		0.2	0.6
20-Sep-03	6.50	7.30	3.4	1.2	15.0	19.0	16.0	21.0	6.0	6.5			6.5	7.6	0.04		0.2	0.6
21-Sep-03																		
22-Sep-03	6.85	7.54	2.0	1.0	15.0	19.0	17.0	22.0	6.0	6.5			6.4	7.4	0.02		0.2	0.6
23-Sep-03	6.90	7.60	2.0	1.0	15.0	20.0	16.0	22.0	6.0	6.5			6.6	7.8	0.02		0.2	0.7
24-Sep-03	6.91	7.49	2.0	1.0	15.0	20.0	16.0	22.0	6.0	6.5			6.6	7.4	0.01		0.2	0.8
25-Sep-03	6.97	7.41	2.0	0.8	15.0	19.0	16.0	21.0	6.0	6.5			6.5	7.4			0.2	0.8
26-Sep-03	7.02	7.32	2.0	1.0	15.0	19.0	17.0	23.0	6.0	6.5			6.6	7.8	0.02		0.2	1.0
27-Sep-03	7.03	7.34	2.0	1.0	15.0	18.0	17.0	22.0	6.0	6.5			6.4	7.6	0.01		0.2	1.0
28-Sep-03																		
29-Sep-03	7.02	7.35	2.8	0.6	16.0	19.0	17.0	22.0	5.5	6.0			6.4	7.8	0.0	0.02	0.2	0.8
30-Sep-03	7.01	7.34	2.2	0.8	16.0	19.0	17.0	21.0	5.5	6.0			6.6	7.6	0.0		0.2	1.2
Max	7.0	7.6	3.8	1.5	16.0	20.0	17.0	23.0	6.5	6.5	0.0	0.0	6.6	7.8	0.05	0.05	0.2	1.2
Min	6.3	7.2	2.0	0.6	14.0	18.0	16.0	21.0	5.5	6.0	0.0	0.0	6.0	7.0	0.01	0.01	0.2	0.5
Average	6.6	7.4	2.7	1.1	14.7	19.1	16.7	21.8	6.0	6.4	#DIV/0!	#DIV/0!	6.4	7.4	0.03	0.03	0.2	0.7

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated
1-Oct-03	6.84	7.32	2.8	0.7	16.0	19.0	18.0	22.0	5.5	6.0			6.6	7.8	0.05		0.2	1.0
2-Oct-03	6.48	7.36	2.5	1.0	15.0	19.0	17.0	21.0	5.5	6.0			6.4	7.6	0.05	0.02	0.2	0.8
3-Oct-03	6.93	7.24	2.5	1.0	15.0	18.0	16.0	21.0	5.5	6.0			6.6	7.6	0.02		0.2	1.2
4-Oct-03	6.94	7.31	2.5	1.0	15.0	19.0	17.0	21.0	5.5	6.0			6.4	7.4	0.05	0.02	0.2	1.0
5-Oct-03	6.98	7.32	2.5	1.0	15.0	18.0	17.0	21.0	5.5	6.0			6.6	7.4	0.02		0.2	0.8
6-Oct-03	7.00	7.36	2.0	1.0	15.0	18.0	17.0	21.0	5.5	6.0			6.6	7.8	0.05	0.02	0.2	0.8
7-Oct-03	7.10	7.45	2.5	1.0	15.0	19.0	17.0	21.0	5.5	6.0			6.6	7.8				
8-Oct-03	7.14	7.47	1.8	0.8	16.0	19.0	17.0	22.0	5.5	6.0			6.8	7.8	0.05		0.2	0.8
9-Oct-03	7.05	7.37	2.2	1.0	15.0	19.0	16.0	20.0	5.5	5.5			6.8	7.6	0.02		0.2	0.8
10-Oct-03																		
11-Oct-03	7.02	7.29	2.2	0.8	15.0	19.0	16.0	20.0	5.5	6.0			6.6	7.6	0.02		0.2	0.8
12-Oct-03	7.02	7.33	2.0	1.0	4.0	19.0	16.0	20.0	5.5	5.5			6.8	7.6	0.02		0.20	0.8
13-Oct-03																		
14-Oct-03	6.95	7.30	2.0	0.8	14.0	19.0	16.0	21.0	5.5	6.0			6.6	7.6	0.05	0.02	0.2	0.9
15-Oct-03	6.94	7.31	1.8	1.0	14.0	19.0	16.0	20.0	5.5	6.0			6.4	7.6	0.05		0.20	0.8
16-Oct-03	6.96	7.28	2.0	1.0	14.0	18.0	16.0	20.0	6.0	6.0			6.6	7.6	0.05	0.02	0.2	0.8
17-Oct-03	7.05	7.25	1.8	0.8	15.0	19.0	16.0	21.0	6.0	6.5			6.4	7.6			0.2	1.0
18-Oct-03	6.98	7.24	1.8	1.0	15.0	18.0	16.0	20.0	6.0	6.5			6.6	7.6			0.2	0.8
19-Oct-03																		
20-Oct-03	7.00	7.31	2.0	0.8	15.0	19.0	16.0	21.0	6.0	6.0			6.6	7.4	0.04		0.2	0.8
21-Oct-03	6.95	7.28	1.8	1.0	15.0	19.0	17.0	22.0	6.0	6.5			6.4	7.4	0.05		0.2	0.8
22-Oct-03	6.90	7.27	1.8	0.7	15.0	19.0	16.0	20.0	6.0	6.0			6.2	7.4			0.2	1.0
23-Oct-03	6.98	7.29	2.0	0.8	15.0	19.0	16.0	21.0	6.0	6.5			6.2	7.2	0.02		0.2	0.8
24-Oct-03																		
25-Oct-03	7.00	7.30	2.0	0.8	15.0	19.0	16.0	21.0	5.5	6.0			6.4	7.4	0.03		0.2	0.8
26-Oct-03																		
27-Oct-03	6.48	7.30	2.0	1.0	14.0	18.0	15.0	20.0	6.0	6.0			6.4	7.6	0.02		0.2	0.8
28-Oct-03	6.89	7.23	1.8	0.8	15.0	19.0	16.0	21.0	6.0	6.5			6.0	7.8	0.05		0.2	0.8
29-Oct-03	6.90	7.24	2.0	0.8	14.0	19.0	16.0	21.0	6.0	6.5			6.4	7.6	0.04	0.02	0.2	0.8
30-Oct-03	6.93	7.24	2.0	0.8	14.0	19.0	16.0	22.0	6.0	6.5			6.6	7.8	0.03	0.02	0.2	0.8
31-Oct-03	6.85	7.29	1.5	0.8	15.0	19.0	15.0	22.0	6.0	6.5			6.6	7.8	0.05	0.02	0.2	0.8
Max	7.1	7.5	2.5	1.0	16.0	19.0	17.0	22.0	6.0	6.5	0.0	0.0	6.8	7.8	0.05	0.02	0.2	1.2
Min	6.5	7.2	1.5	0.7	4.0	18.0	15.0	20.0	5.5	5.5	0.0	0.0	6.0	7.2	0.02	0.02	0.2	0.8
Average	7.0	7.3	2.0	0.9	14.3	18.8	16.2	20.8	5.8	6.1	#DIV/0!	#DIV/0!	6.5	7.6	0.04	0.02	0.2	0.8

**Table M31.1.4 Water Quality at Salaulim WTP in 2003 (6/6)**

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L		
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated	
1-Nov-03																			
2-Nov-03	6.81	7.24	1.8	1.0	15.0	19.0	15.0	21.0	6.0	6.5			6.6	7.6	0.04	0.02	0.2	0.8	
3-Nov-03	6.41	7.25	1.5	0.8	14.0	19.0	16.0	20.0	6.0	6.5			6.6	7.8	0.04	0.02	0.2	0.8	
4-Nov-03	6.90	7.30	1.6	0.7	15.0	19.0	16.0	22.0	6.0	6.0			6.4	7.6	0.05	0.02	0.2	0.8	
5-Nov-03	6.41	7.29	1.6	0.8	15.0	18.0	16.0	21.0	6.0	6.5			6.4	7.6	0.03	0.02	0.2	0.8	
6-Nov-03	6.98	7.30	1.8	0.8	15.0	19.0	16.0	21.0	6.0	6.5			6.6	7.6	0.04	0.02	0.2	0.5	
7-Nov-03	7.04	7.40	1.8	0.8	16.0	20.0	17.0	22.0	6.0	6.5			6.4	7.6	0.05	0.02	0.2	0.8	
8-Nov-03	7.00	7.30	1.5	0.8	15.0	20.0	16.0	22.0	6.0	6.5			6.4	7.4	0.04	0.02	0.2	0.9	
9-Nov-03																			
10-Nov-03	7.03	7.36	1.5	0.8	15.0	19.0	16.0	21.0	6.0	6.5			6.6	7.6	0.04	0.02	0.2	0.8	
11-Nov-03	7.07	7.32	1.6	0.7	15.0	19.0	17.0	22.0	6.0	6.5			6.6	7.4	0.05	0.02	0.2	0.6	
12-Nov-03	7.10	7.38	1.8	0.9	16.0	20.0	17.0	22.0	6.0	6.5			6.6	7.6	0.05	0.05	0.2	1.0	
13-Nov-03	7.04	7.39	1.5	0.8	15.0	20.0	16.0	22.0	6.0	6.5			6.6	7.4	0.05	0.02	0.2	0.8	
14-Nov-03	7.07	7.38	1.8	0.9	16.0	21.0	17.0	23.0	6.0	6.5			6.4	7.2	0.05	0.05	0.2	0.8	
15-Nov-03																			
16-Nov-03																			
17-Nov-03	7.00	7.35	1.4	0.8	15.0	21.0	16.0	22.0	6.0	6.5			6.4	7.4	0.04	0.02	0.2	1.0	
18-Nov-03	7.02	7.32	1.7	0.8	15.0	20.0	16.0	22.0	6.0	6.5			6.4	7.6	0.05	0.05	0.2	0.8	
19-Nov-03	7.02	7.36	1.4	0.8	15.0	20.0	16.0	22.0	6.0	6.5			6.4	7.4	0.04	0.02	0.2	0.5	
20-Nov-03	7.00	7.39	1.2	0.8	15.0	19.0	16.0	21.0	6.0	6.0			6.6	7.4	0.05	0.02	0.2	0.6	
21-Nov-03	7.06	7.44	1.5	0.9	16.0	20.0	18.0	24.0	6.0	6.5			6.4	7.2	0.04	0.02	0.2	1.0	
22-Nov-03	7.01	7.38	1.4	0.8	16.0	19.0	18.0	22.0	6.0	6.5			6.4	7.2	0.03	0.02	0.2	0.8	
23-Nov-03																			
24-Nov-03	7.04	7.41	1.4	0.8	15.0	20.0	17.0	22.0	6.0	6.5			6.4	7.4	0.03	0.01	0.2	0.8	
25-Nov-03	7.10	7.38	2.0	1.0	17.0	21.0	19.0	24.0	6.0	6.5	0.2		6.6	7.2	0.02	0.02	0.2	1.0	
26-Nov-03	7.06	7.57	2.0	1.0	16.0	20.0	18.0	24.0	6.0	6.5	0.1		6.4	7.4	0.03	0.02	0.2	0.8	
27-Nov-03	7.08	7.61	1.4	0.8	16.0	22.0	17.0	24.0	6.0	6.5	0.2		6.4	7.2	0.04	0.02	0.2	0.8	
28-Nov-03	7.08	7.67	1.4	0.8	16.0	22.0	17.0	25.0	6.0	6.5	0.2		6.4	7.2	0.04	0.01	0.2	0.8	
29-Nov-03	7.03	7.56	1.8	0.8	15.0	22.0	17.0	24.0	6.0	6.5	0.2		6.6	7.4	0.03	0.01	0.2	0.6	
30-Nov-03																			
Max	7.1	7.7	2.0	1.0	17.0	22.0	19.0	25.0	6.0	6.5	0.2	0.0	6.6	7.8	0.05	0.05	0.2	1.0	
Min	6.4	7.3	1.2	0.7	14.0	18.0	16.0	20.0	6.0	6.0	0.1	0.0	6.4	7.2	0.02	0.01	0.2	0.5	
Average	7.0	7.4	1.6	0.8	15.4	20.0	16.7	22.3	6.0	6.5	0.2	#DIV/0!	6.5	7.4	0.04	0.02	0.2	0.8	

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated
1-Dec-03	7.02	7.65	1.4	1.0	16.0	22.0	17.0	25.0	6.0	6.5	0.3		6.4	7.2	0.03	0.02	0.2	1.0
2-Dec-03	7.00	7.73	1.5	0.8	17.0	23.0	19.0	27.0	6.0	6.5	0.4		6.6	7.4	0.04	0.02	0.2	0.8
3-Dec-03																		
4-Dec-03																		
5-Dec-03	7.00	7.59	1.2	0.6	16.0	22.0	19.0	26.0	6.0	6.5	0.4		6.2	7.2	0.04	0.01		1.2
6-Dec-03																		
7-Dec-03																		
8-Dec-03	7.01	8.10	1.0	0.7	16.0	26.0	17.0	29.0	6.0	6.5	0.4		6.4	7.4	0.30	0.02		1.2
9-Dec-03	6.94	8.29	2.0	0.9	18.0	27.0	20.0	31.0	6.0	6.5	0.4		6.2	7.4	0.05	0.04		1.5
10-Dec-03	6.90	8.25	2.0	1.0	18.0	28.0	20.0	32.0	6.0	6.5	0.4		6.4	7.4	0.05	0.04		1.5
11-Dec-03	6.91	8.19	2.0	1.0	18.0	27.0	19.0	32.0	6.0	6.5	0.4		6.2	7.4	0.04	0.02		1.4
12-Dec-03	6.95	8.04	2.2	1.0	18.0	26.0	19.0	30.0	6.0	6.5	0.3		6.2	7.4	0.05	0.03		1.6
13-Dec-03	6.90	8.21	2.0	1.0	17.0	26.0	19.0	31.0	6.0	6.5	0.4		6.4	7.4	0.04	0.02		1.6
14-Dec-03																		
15-Dec-03	7.01	8.01	1.2	0.8	17.0	26.0	18.0	31.0	6.0	6.5	0.4		6.4	7.4	0.04	0.02		1.5
16-Dec-03	7.02	8.15	1.5	1.0	18.0	27.0	20.0	32.0	5.5	6.0	0.4		6.4	7.2	0.04	0.04		1.5
17-Dec-03	6.95	8.17	1.8	1.0	18.0	28.0	20.0	33.0	6.0	6.5	0.4		6.2	7.4	0.05	0.02		1.5
18-Dec-03	7.00	8.18	1.6	1.0	18.0	27.0	20.0	32.0	6.0	6.5	0.5		6.4	7.4	0.04	0.03		1.5
19-Dec-03																		
20-Dec-03	7.00	8.15	1.6	1.0	18.0	26.0	19.0	30.0	6.0	6.5	0.4		6.2	7.4	0.03	0.02		1.5
21-Dec-03																		
22-Dec-03	7.00	8.14	1.5	1.0	18.0	27.0	20.0	32.0	6.0	6.5	0.5		6.4	7.4	0.04	0.02		1.5
23-Dec-03	6.95	8.00	1.5	1.0	20.0	29.0	22.0	34.0	6.0	6.5	0.4		6.2	7.0	0.03	0.02		1.5
24-Dec-03	7.00	8.01	1.5	1.0	19.0	29.0	22.0	34.0	6.0	6.5	0.5		6.2	7.2	0.04	0.02		1.5
25-Dec-03																		
26-Dec-03	7.02	8.06	1.5	1.0	19.0	29.0	21.0	32.0	6.0	6.5	0.5		6.4	7.2	0.03	0.02		1.5
27-Dec-03	7.03	8.13	1.5	1.0	17.0	28.0	19.0	32.0	6.0	6.0	0.4		6.2	7.2	0.03	0.02		1.5
28-Dec-03																		
29-Dec-03	7.04	8.21	1.2	1.0	17.0	27.0	18.0	32.0	6.0	6.5	0.3		6.4	7.2	0.04	0.02		1.5
30-Dec-03	7.06	8.26	0.4	1.0	18.0	28.0	19.0	32.0	6.0	6.5	0.2		6.4	7.4	0.03	0.02		1.5
31-Dec-03	7.01	7.95	1.5	1.0	17.0	25.0	18.0	30.0	6.0	6.5	0.1		6.4	7.6	0.03	0.02		1.4
Max	7.1	8.3	2.2	1.0	20.0	29.0	22.0	34.0	6.0	6.5	0.5	0.0	6.4	7.6	0.3	0.04	0.0	1.6
Min	6.9	7.6	0.4	0.6	16.0	22.0	17.0	26.0	5.5	6.0	0.1	0.0	6.2	7.0	0.03	0.01	0.0	1.2
Average	7.0	8.1	1.5	1.0	17.8	26.9	19.5	31.4	6.0	6.5	0.4	#DIV/0!	6.3	7.3	0.05	0.02	#DIV/0!	1.5

**Table M31.1.5 Water Quality at Salaulim WTP in 2004 (1/6)**

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L		
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated	
1-Jan-04																			
2-Jan-04	7.0	7.8	1.5	1.0	17.0	26.0	20.0	29.0	6.0	6.5			6.2	7.4	0.04	0.02	0.2	1.0	
3-Jan-04																			
4-Jan-04																			
5-Jan-04	7.0	7.7	1.5	1.0	17.0	24.0	18.0	25.0	6.0	6.5			6.4	7.2	0.04	0.02	0.2	1.0	
6-Jan-04	7.0	7.7	1.4	1.0	16.0	24.0	17.0	25.0	6.0	6.5			6.6	7.4	0.03	0.03	0.2	1.0	
7-Jan-04	7.1	7.7	1.5	0.8	18.0	25.0	20.0	28.0	5.5	6.0			6.6	7.4	0.07	0.02	0.2	0.8	
8-Jan-04	7.1	7.5	1.2	0.7	17.0	24.0	18.0	26.0	6.0	6.0			6.4	7.4	0.05	0.03	0.2	0.8	
9-Jan-04	7.1	7.5	1.2	0.8	17.0	23.0	19.0	26.0	6.0	6.5			6.6	7.4	0.05	0.03	0.2	1.0	
10-Jan-04	7.1	7.5	1.2	0.8	17.0	22.0	19.0	26.0	6.0	6.5			6.4	7.4	0.04	0.03	0.2	0.8	
11-Jan-04	7.0	7.5	1.2	0.8	17.0	23.0	19.0	27.0	6.0	6.5			6.6	7.6	0.03	0.02	0.2	1.0	
12-Jan-04	7.1	7.5	1.4	1.0	17.0	22.0	19.0	26.0	6.0	6.5			6.6	7.4	0.06	0.04	0.2	1.0	
13-Jan-04	7.0	7.5	1.2	0.8	17.0	22.0	18.0	26.0	6.0	6.5			6.4	7.2	0.05	0.03	0.2	1.0	
14-Jan-04	7.0	7.5	1.2	0.8	17.0	22.0	18.0	25.0	6.0	6.5			6.6	7.4	0.04	0.04	0.2	0.5	
15-Jan-04	7.0	7.5	1.2	0.8	17.0	22.0	19.0	25.0	6.0	6.5			6.4	7.4	0.05	0.03	0.2	0.8	
16-Jan-04	7.1	7.5	1.2	0.8	16.0	23.0	20.0	26.0	6.0	6.5			6.2	7.3	0.05	0.04	0.2	0.8	
17-Jan-04	7.0	7.5	1.2	0.8	16.0	23.0	19.0	26.0	6.0	6.5			6.2	7.2	0.04	0.02	0.2	0.8	
18-Jan-04	7.0	7.5	1.2	0.8	16.0	22.0	18.0	26.0	6.0	6.5			6.4	7.4	0.04	0.03	0.2	1.0	
19-Jan-04	7.0	7.5	1.2	0.7	17.0	23.0	18.0	26.0	6.0	6.5			6.4	7.2	0.04	0.02	0.2	0.5	
20-Jan-04	7.1	7.5	1.4	1.0	17.0	23.0	19.0	26.0	6.0	6.5			6.0	7.2	0.06	0.03	0.2	0.5	
21-Jan-04	7.1	7.4	1.2	1.0	16.0	22.0	18.0	24.0	5.5	6.0			6.4	7.2	0.04	0.02	0.2	0.6	
22-Jan-04	7.0	7.5	1.2	0.8	16.0	23.0	19.0	25.0	6.0	6.0			6.6	7.4	0.04	0.03	0.2	1.0	
23-Jan-04	7.1	7.5	1.2	0.8	16.0	22.0	19.0	25.0	6.0	6.0			6.4	7.4	0.05	0.03	0.2	1.0	
24-Jan-04	7.0	7.5	1.2	0.7	15.0	22.0	19.0	25.0	6.0	6.5			6.6	7.4	0.05	0.04	0.2	0.8	
25-Jan-04	7.0	7.5	1.2	0.8	15.0	23.0	19.0	26.0	6.0	6.0			6.4	7.2	0.04	0.03	0.2	0.8	
26-Jan-04	7.0	7.5	1.2	0.8	15.0	22.0	19.0	26.0	6.0	6.5			6.6	7.4	0.05	0.02	0.2	0.8	
27-Jan-04	7.1	7.4	7.0	0.8	15.0	21.0	19.0	24.0	6.0	6.0			6.4	7.4	0.05	0.02	0.2	0.8	
28-Jan-04	7.1	7.5	1.4	1.0	16.0	23.0	18.0	24.0	6.0	6.0			6.2	7.6	0.05	0.02	0.2	1.0	
29-Jan-04	7.1	7.5	1.2	0.8	15.0	23.0	18.0	25.0	6.0	6.5			6.2	7.4	0.04	0.03	0.2	0.8	
30-Jan-04	7.1	7.5	1.4	0.8	16.0	22.0	18.0	25.0	6.0	6.5			6.4	7.6	0.06	0.02	0.2	0.8	
31-Jan-04	7.2	7.5	1.2	1.0	16.0	23.0	18.0	25.0	6.0	6.5			6.4	7.4	0.05	0.03	0.2	1.0	
Max	7.2	7.8	7.0	1.0	18.0	26.0	20.0	29.0	6.0	6.5			6.6	7.6	0.07	0.04	0.2	1.0	
Min	7.0	7.4	1.2	0.7	15.0	21.0	17.0	24.0	5.5	6.0			6.0	7.2	0.03	0.02	0.2	0.5	
Average	7.1	7.5	1.5	0.8	16.3	22.8	18.6	25.6	6.0	6.4			6.4	7.4	0.05	0.03	0.2	0.8	

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated
1-Feb-04	7.12	7.52	1.2	0.8	15.0	23.0	18.0	25.0	6.0	6.5			6.2	7.4	0.04	0.02	0.2	0.8
2-Feb-04	7.14	7.44	1.5	0.6	17.0	21.0	19.0	24.0	6.0	6.0			6.4	7.6	0.04	0.03	0.2	0.8
3-Feb-04	7.14	7.52	1.2	0.8	16.0	22.0	19.0	25.0	6.0	6.5			6.6	7.4	0.04	0.02	0.2	0.6
4-Feb-04	7.15	7.50	1.4	0.7	17.0	21.0	19.0	23.0	6.0	6.0			6.6	7.6	0.04	0.03	0.2	1.0
5-Feb-04	7.12	7.49	1.4	0.8	17.0	21.0	18.0	23.0	6.0	6.0			6.4	7.4	0.04	0.02	0.2	0.6
6-Feb-04	7.20	7.56	1.6	0.8	16.0	21.0	18.0	24.0	6.0	6.0			6.4	7.6	0.02	0.03	0.2	1.0
7-Feb-04	7.15	7.56	1.4	0.8	16.0	21.0	17.0	24.0	6.0	6.5			6.4	7.4	0.05	0.03	0.2	1.0
8-Feb-04	7.15	7.52	1.4	0.8	17.0	22.0	18.0	24.0	6.0	6.5			6.2	7.4	0.04	0.02	0.2	0.8
9-Feb-04	7.17	7.58	1.2	0.7	17.0	22.0	18.0	25.0	6.0	6.5			6.4	7.6	0.04	0.03	0.2	1.0
10-Feb-04	7.11	7.49	1.2	0.8	17.0	21.0	18.0	24.0	6.0	6.5			6.6	7.6	0.04	0.04	0.2	0.8
11-Feb-04	7.17	7.58	1.2	0.8	17.0	21.0	18.0	24.0	6.0	6.5			6.6	7.8	0.05	0.03	0.2	1.0
12-Feb-04	7.14	7.49	1.2	0.8	17.0	21.0	18.0	23.0	6.0	6.5			6.4	7.6	0.04	0.03	0.2	0.8
13-Feb-04	7.12	7.50	1.2	0.8	17.0	22.0	18.0	24.0	6.0	6.5			6.6	7.6	0.05	0.04	0.2	0.8
14-Feb-04	7.15	7.49	1.2	0.8	17.0	21.0	18.0	23.0	6.0	6.0			6.4	7.4	0.04	0.02	0.2	0.8
15-Feb-04	7.13	7.50	1.2	0.8	17.0	21.0	18.0	22.0	6.0	6.5			6.6	7.6	0.03	0.02	0.2	0.8
16-Feb-04	7.14	7.52	1.2	0.8	17.0	22.0	18.0	24.0	6.0	6.5			6.4	7.4	0.03	0.02	0.2	0.8
17-Feb-04	7.16	7.50	1.2	0.7	16.0	22.0	19.0	25.0	6.0	6.0			6.6	7.8	0.05	0.03	0.2	1.0
18-Feb-04	7.15	7.50	1.0	0.6	16.0	21.0	19.0	25.0	6.0	6.5			6.6	7.6	0.06	0.04	0.2	1.0
19-Feb-04	7.15	7.52	1.0	0.7	16.0	22.0	19.0	25.0	6.0	6.5			6.4	7.6	0.05	0.03	0.2	1.2
20-Feb-04	7.15	7.52	1.0	0.7	17.0	22.0	18.0	25.0	6.0	6.5			6.6	7.8	0.07	0.04	0.2	1.0
21-Feb-04	7.14	7.51	1.0	0.6	17.0	22.0	18.0	25.0	6.0	6.5			6.4	7.6	0.05	0.03	0.2	0.8
22-Feb-04	7.11	7.49	1.0	0.6	16.0	21.0	18.0	24.0	6.0	6.5			6.6	7.6	0.06	0.04	0.2	0.6
23-Feb-04	7.15	7.54	1.0	0.6	17.0	21.0	18.0	25.0	6.0	6.5			6.6	7.6	0.05	0.04	0.2	1.0
24-Feb-04	7.13	7.54	1.0	0.7	17.0	22.0	18.0	25.0	6.0	6.5			6.4	7.4	0.05	0.03	0.2	0.8
25-Feb-04	7.05	7.44	1.0	0.7	17.0	21.0	18.0	23.0	6.0	6.5			6.6	7.8	0.06	0.03	0.2	1.0
26-Feb-04	7.10	7.48	1.0	0.8	17.0	21.0	18.0	22.0	6.0	6.5			6.4	7.6	0.05	0.04	0.2	0.6
27-Feb-04																		
28-Feb-04	7.13	7.52	1.0	0.7	17.0	22.0	18.0	23.0	6.0	6.5			6.6	7.6	0.06	0.03	0.2	0.8
29-Feb-04	7.12	7.48	1.0	0.7	17.0	22.0	18.0	24.0	6.0	6.5			6.6	7.6	0.04	0.02	0.2	0.8
Max	7.2	7.6	1.6	0.8	17.0	22.0	19.0	25.0	6.0	6.5			6.6	7.8	0.07	0.04	0.2	1.2
Min	7.1	7.4	1.0	0.6	16.0	21.0	17.0	22.0	6.0	6.0			6.2	7.4	0.02	0.02	0.2	0.6
Average	7.1	7.5	1.2	0.7	16.7	21.5	18.2	24.0	6.0	6.4			6.5	7.6	0.05	0.03	0.2	0.9

**Table M31.1.5 Water Quality at Salaulim WTP in 2004 (2/6)**

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated
1-Mar-04	7.10	7.49	1.0	0.8	16.0	21.0	18.0	24.0	6.0	6.5			6.8	7.6	0.03	0.02	0.2	0.8
2-Mar-04	7.15	7.42	1.0	0.7	15.0	20.0	18.0	25.0	6.0	6.5			6.6	7.4	0.06	0.04	0.2	0.8
3-Mar-04	7.05	7.39	1.0	0.8	15.0	20.0	18.0	25.0	6.0	6.5			6.4	7.4	0.05	0.03	0.2	1.0
4-Mar-04	7.02	7.38	1.0	0.8	15.0	20.0	17.0	22.0	6.0	6.5			6.4	7.4	0.04	0.03	0.2	0.8
5-Mar-04	7.04	7.35	1.0	0.6	15.0	20.0	18.0	24.0	6.0	6.5			6.4	7.6	0.05	0.04	0.2	1.0
6-Mar-04	7.03	7.34	1.0	0.6	15.0	20.0	17.0	22.0	6.0	6.5			6.4	7.4	0.05	0.03	0.2	0.8
7-Mar-04																		
8-Mar-04	7.09	7.41	1.0	0.7	16.0	21.0	18.0	23.0	6.0	6.5			6.6	7.4	0.06	0.04	0.2	0.6
9-Mar-04	6.95	7.36	1.0	0.8	15.0	20.0	18.0	24.0	6.0	6.5			6.4	7.2	0.05	0.04	0.2	1.0
10-Mar-04	6.86	7.38	1.0	0.8	15.0	21.0	18.0	23.0	6.0	6.5			6.8	7.6	0.05	0.04	0.2	1.0
11-Mar-04	6.93	7.34	1.0	0.8	15.0	20.0	17.0	22.0	6.0	6.5			6.6	7.4	0.05	0.03	0.2	0.8
12-Mar-04	6.85	7.28	1.0	0.8	15.0	20.0	17.0	22.0	6.0	6.5			6.6	7.8	0.05	0.02	0.2	1.0
13-Mar-04	6.81	7.39	1.0	0.8	15.0	21.0	17.0	23.0	6.0	6.5			6.4	7.6	0.05	0.03	0.2	1.0
14-Mar-04	6.91	7.61	1.0	0.8	16.0	23.0	19.0	24.0	6.0	6.5			6.6	7.6	0.04	0.02	0.2	1.0
15-Mar-04	6.96	7.60	1.0	0.8	16.0	22.0	18.0	26.0	6.0	6.5	0.1		6.4	7.4	0.05	0.03	0.2	1.0
16-Mar-04	6.95	7.59	1.0	0.8	16.0	22.0	18.0	25.0	6.0	6.5	0.05		6.6	7.8	0.06	0.04	0.2	0.8
17-Mar-04	6.90	7.58	1.0	0.8	15.0	22.0	18.0	27.0	6.0	6.5	0.1		6.6	7.8			0.2	0.8
18-Mar-04	6.94	7.61	1.0	0.8	15.0	22.0	18.0	26.0	6.0	6.5	0.1		6.4	7.6			0.2	0.8
19-Mar-04	6.96	7.54	1.2	0.8	17.0	22.0	18.0	28.0	6.5	6.5	0.25		6.4	7.6			0.2	0.7
20-Mar-04	6.98	7.76	1.4	1.0	16.0	23.0	18.0	28.0	6.0	6.5	0.3		6.4	7.4			0.2	1.0
21-Mar-04	7.00	7.81	1.4	1.0	16.0	23.0	19.0	28.0	6.0	6.5	0.3		6.6	7.4			0.2	0.8
22-Mar-04	7.01	7.76	1.4	1.0	16.0	22.0	18.0	27.0	6.0	6.5	0.3		6.4	7.4			0.2	0.6
23-Mar-04	6.96	7.84	1.4	1.0	15.0	23.0	17.0	27.0	6.0	6.5	0.4		6.4	7.4			1.2	
24-Mar-04	7.00	7.85	1.2	1.0	15.0	24.0	19.0	30.0	6.0	6.5	0.35		6.4	7.6			1.5	
25-Mar-04	6.98	7.93	1.2	1.0	15.0	24.0	18.0	29.0	6.0	6.5	0.4		6.6	7.6			1.4	
26-Mar-04	7.00	7.96	1.2	0.8	15.0	25.0	17.0	31.0	6.0	6.5	0.4		6.4	7.4			1.4	
27-Mar-04	7.00	8.01	1.2	0.8	15.0	26.0	18.0	32.0	6.0	6.5	0.4		6.4	7.2			1.5	
28-Mar-04	7.00	8.10	1.2	0.8	16.0	26.0	18.0	32.0	6.0	6.5	0.4		6.6	7.4			1.4	
29-Mar-04	7.00	8.10	1.2	1.0	16.0	26.0	19.0	32.0	6.0	6.5	0.4		6.4	7.2			1.4	
30-Mar-04	7.00	8.11	1.2	1.0	16.0	26.0	19.0	33.0	6.0	6.5	0.45		6.6	7.4			1.4	
31-Mar-04	7.08	8.05	1.4	1.0	17.0	26.0	19.0	32.0	6.0	7.0	0.5		6.6	7.6			1.4	
Max	7.1	8.1	1.4	1.0	17.0	26.0	19.0	33.0	6.5	7.0	0.5	0.0	6.8	7.8	0.06	0.04	0.2	1.5
Min	6.8	7.3	1.0	0.6	15.0	20.0	17.0	22.0	6.0	6.5	0.1	0.0	6.4	7.2	0.04	0.02	0.2	0.6
Average	7.0	7.7	1.1	0.8	15.5	22.5	18.0	26.7	6.0	6.5	0.3	#DIV/0!	6.5	7.5	0.05	0.03	0.2	1.0

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated
1-Apr-04	7.01	8.00	1.4	1.0	16.0	26.0	19.0	31.0	6.0	6.5	0.6		6.6	7.4				1.4
2-Apr-04	7.15	8.10	1.5	1.0	17.0	26.0	19.0	34.0	6.0	6.5	0.7		6.6	7.4				1.4
3-Apr-04	7.06	8.08	1.4	1.0	16.0	26.0	19.0	33.0	6.0	6.5	0.6		6.6	7.6				1.4
4-Apr-04	7.08	8.07	1.5	1.0	16.0	26.0	19.0	32.0	6.0	6.5	0.5		6.4	7.4				0.8
5-Apr-04	6.98	8.10	1.5	1.0	16.0	27.0	18.0	33.0	6.0	6.5	0.5		6.6	7.4				1.5
6-Apr-04	7.02	8.02	1.5	1.0	17.0	26.0	19.0	34.0	6.0	6.5	0.5		6.6	7.2				1.4
7-Apr-04	7.20	8.17	1.2	0.8	17.0	25.0	20.0	34.0	6.0	6.5	0.5		6.6	7.6	0.05	0.02		1.4
8-Apr-04	7.20	8.23	1.4	1.0	17.0	27.0	19.0	34.0	6.0	6.5	0.5		6.6	7.4	0.05	0.03		1.2
9-Apr-04	7.14	8.20	1.4	1.0	17.0	26.0	19.0	34.0	6.0	6.5	0.5		6.4	7.4	0.04	0.02		1.2
10-Apr-04	7.16	8.20	1.4	1.0	17.0	27.0	19.0	35.0	6.0	6.5	0.5		6.6	7.6	0.04	0.02		1.2
11-Apr-04																		
12-Apr-04	7.14	8.26	1.4	1.0	17.0	27.0	19.0	35.0	6.0	6.5	0.3		6.6	7.4	0.04	0.02		1.5
13-Apr-04	7.20	8.45	1.2	0.8	16.0	27.0	20.0	33.0	6.0	6.5	0.1		6.4	7.2	0.05	0.03		1.5
14-Apr-04	7.00	7.85	1.2	0.8	16.0	23.0	20.0	29.0	6.0	6.5	0.2		6.4	7.4	0.06	0.02		1.5
15-Apr-04	7.06	7.53	1.2	0.8	16.0	23.0	18.0	25.0	6.0	6.5	0.1		6.4	7.2	0.05	0.03		1.5
16-Apr-04	7.15	7.70	1.2	0.8	16.0	22.0	18.0	25.0	6.0	6.5	0.1		6.6	7.6	0.06	0.03		1.5
17-Apr-04	7.15	7.67	1.2	0.8	17.0	22.0	18.0	24.0	6.0	6.5	0.1		6.6	7.6	0.06	0.02		1.5
18-Apr-04	7.16	7.67	1.2	0.8	16.0	22.0	18.0	24.0	6.0	6.5	0.1		6.4	7.2	0.05	0.03		1.4
19-Apr-04	7.13	7.70	1.2	0.8	16.0	23.0	18.0	24.0	6.0	6.5	0.1		6.6	7.4	0.05	0.02	0.2	1.2
20-Apr-04	7.12	7.67	1.2	0.8	16.0	22.0	18.0	24.0	6.0	6.5	0.1		6.4	7.2	0.04	0.02	0.2	1.0
21-Apr-04	7.20	7.82	1.4	1.0	16.0	21.0	19.0	25.0	6.5	7.0			6.6	7.4	0.05	0.02	0.2	1.0
22-Apr-04	7.18	7.78	1.2	1.0	16.0	21.0	19.0	25.0	6.0	6.5			6.4	7.4	0.04	0.02	0.2	0.8
23-Apr-04	7.22	7.81	1.2	1.0	16.0	22.0	20.0	27.0	6.5	7.0	0.1		6.4	7.6	0.05	0.02	0.2	0.8
24-Apr-04	7.16	7.71	1.2	0.8	16.0	21.0	19.0	26.0	6.5	7.0	0.1		6.4	7.4	0.04	0.02	0.2	0.8
25-Apr-04	7.18	7.79	1.4	0.8	16.0	22.0	19.0	26.0	6.0	6.5	0.1		6.6	7.4	0.05	0.03	0.2	0.6
26-Apr-04	7.14	7.73	1.4	0.8	16.0	21.0	18.0	25.0	6.0	6.5	0.1		6.4	7.4	0.04	0.02	0.2	0.8
27-Apr-04	7.20	7.80	1.5	1.0	17.0	22.0	18.0	26.0	6.0	6.5	0.1		6.4	7.6	0.05	0.02	0.2	0.8
28-Apr-04	7.20	7.75	1.5	1.0	17.0	22.0	18.0	27.0	6.5	7.0			6.4	7.6	0.05	0.02	0.2	0.8
29-Apr-04	7.16	7.76	1.4	1.0	16.0	21.0	18.0	26.0	6.5	7.0	0.1		6.4	7.4	0.04	0.02	0.2	0.8
30-Apr-04	7.24	7.83	1.4	0.8	16.0	22.0	18.0	27.0	6.5	7.0			6.2	7.4	0.05	0.03	0.2	0.8
Max	7.2	8.5	1.5	1.0	17.0	27.0	20.0	35.0	6.5	7.0	0.6	0.0	6.6	7.6	0.06	0.03	0.2	1.5
Min	7.0	7.5	1.2	0.8	16.0	21.0	18.0	24.0	6.0	6.5	0.1	0.0	6.4	7.2	0.04	0.02	0.2	0.6
Average	7.1	7.9	1.3	0.9	16.3	23.6	18.7	28.6	6.1	6.6	0.3	#DIV/0!	6.3	7.4	0.05	0.02	0.2	1.1

**Table M31.1.5 Water Quality at Salaulim WTP in 2004 (3/6)**

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated
1-May-04	7.21	7.60	1.2	0.8	16.0	22.0	18.0	26.0	6.5	7.0			6.4	7.4	0.06	0.03	0.2	0.8
2-May-04	7.20	7.64	1.2	0.8	16.0	22.0	18.0	26.0	6.5	7.0			6.4	7.4	0.06	0.03	0.2	0.8
3-May-04	7.18	7.71	1.2	0.8	16.0	22.0	18.0	25.0	6.5	7.0	0.1		6.4	7.2	0.06	0.04	0.2	0.8
4-May-04	7.14	7.65	1.2	0.8	16.0	21.0	18.0	26.0	6.0	6.5			6.4	7.4	0.05	0.02	0.2	0.8
5-May-04	7.15	7.64	1.4	0.8	16.0	21.0	18.0	25.0	6.0	6.5			6.4	7.2	0.05	0.02	0.2	0.8
6-May-04	7.18	7.71	1.4	0.8	16.0	22.0	19.0	26.0	6.0	6.5	0.1		6.4	7.2	0.05	0.02	0.2	0.8
7-May-04	7.15	7.69	1.2	0.8	16.0	22.0	18.0	25.0	6.0	6.5	0.1		6.2	7.2	0.04	0.02	0.2	0.8
8-May-04																		
9-May-04																		
10-May-04	7.27	7.69	1.2	0.8	17	22	19	25	6.0	6.5			6.4	7.2	0.04	0.02	0.2	0.8
11-May-04	7.29	7.61	1.2	0.8	17	22	19	24	6.0	6.5			6.6	7.2	0.04	0.03	0.2	0.8
12-May-04	7.26	7.58	1.2	0.8	17	22	19	24	6.0	6.5			6.4	7.4	0.05	0.02	0.2	0.8
13-May-04	7.26	7.60	1.2	0.8	16	21	18	24	6.0	6.5			6.4	7.2	0.04	0.02	0.2	0.8
14-May-04	7.30	7.61	1.2	0.8	16	21	18	24	6.0	6.5			6.6	7.4	0.04	0.02	0.2	0.8
15-May-04	7.27	7.60	1.2	0.8	16	21	17	24	6.0	6.5			6.4	7.2	0.05	0.02	0.2	0.8
16-May-04	7.29	7.60	1.2	0.8	16	22	17	24	6.0	6.5			6.6	7.4	0.04	0.02	0.2	0.8
17-May-04	7.32	7.61	1.0	0.7	16	20	17	23	6.0	6.5			6.4	7.2	0.05	0.02	0.2	0.8
18-May-04	7.28	7.57	1.0	0.8	16	21	17	22	6.0	6.5			6.4	7.4	0.06	0.02	0.2	0.8
19-May-04	7.35	7.64	1.4	1.0	15	20	17	22	6.0	6.5			6.6	7.7	0.05	0.02	0.2	0.8
20-May-04																		
21-May-04	7.30	7.67	2.5	1.0	17	21	19	24	5.5	6.0			6.4	7.4	0.05	0.02	0.2	0.8
22-May-04	7.30	7.66	2.3	1.0	17	21	20	24	6.0	6.5			6.4	7.6	0.06	0.02	0.2	0.8
23-May-04	7.32	7.62	2.8	1.0	17	21	19	24	6.0	6.5			6.6	7.4	0.05	0.02	0.2	0.6
24-May-04	7.34	7.67	2.5	1.0	17	22	20	25	6.0	6.0			6.6	7.6	0.07	0.04	0.2	0.8
25-May-04																		
26-May-04	7.35	7.65	2.5	1.0	17	22	20	25	6.0	6.0			6.4	7.6	0.05	0.03	0.2	0.8
27-May-04																		
28-May-04	7.28	7.59	2.9	1.2	17	21	21	25	6.0	6.5			6.6	7.8	0.06	0.03	0.2	0.8
29-May-04	7.27	7.61	3.5	1.0	16	21	20	24	6.0	6.5			6.6	7.6	0.05	0.03	0.2	0.8
30-May-04	7.30	7.65	3.0	1.2	17	21	19	24	6.0	6.5			6.4	7.4	0.05	0.03	0.2	0.8
31-May-04	7.31	7.62	2.4	1.2	17	21	18	24	6.0	6.5			6.6	7.4	0.04	0.02	0.2	0.8
Max	7.4	7.7	3.5	1.2	17.0	22.0	21.0	26.0	6.5	7.0	0.1	0.0	6.6	7.8	0.07	0.04	0.2	0.8
Min	7.1	7.6	1.0	0.7	15.0	20.0	17.0	22.0	5.5	6.0	0.1	0.0	6.2	7.2	0.04	0.02	0.2	0.6
Average	7.3	7.6	1.8	0.9	16.4	21.3	18.5	24.3	6.0	6.5	0.1	#DIV/0!	6.5	7.4	0.05	0.02	0.2	0.8

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated
1-Jun-04	7.21	7.54	2.6	1	17.0	20.0	18.0	23.0	6.5	7.0			6.4	7.6	0.05	0.03	0.2	0.8
2-Jun-04	7.28	7.62	3	1	17.0	21.0	18.0	24.0	6.5	7.0			6.4	7.6	0.05	0.03	0.2	0.8
3-Jun-04																		
4-Jun-04	7.32	7.59	2.4	1.0	18.0	21.0	20.0	25.0	6.5	7.0			6.6	7.2	0.06	0.02	0.2	0.8
5-Jun-04	7.30	7.56	2.2	1.0	18.0	21.0	19.0	25.0	6.5	7.0			6.6	7.4	0.05	0.03	0.2	0.8
6-Jun-04	7.26	7.59	2.5	1.0	17.0	21.0	19.0	24.0	6.5	7.0			6.4	7.2	0.06	0.03	0.2	0.8
7-Jun-04	7.26	7.54	2.4	1.0	17.0	20.0	18.0	24.0	6.0	6.5			6.4	7.2	0.04	0.02	0.2	0.8
8-Jun-04	7.28	7.60	2.5	1.2	18	20	20	23	6.5	7.0	0.1		6.4	7.2	0.06	0.03	0.2	0.8
9-Jun-04	7.25	7.54	3.2	1.5	18	20	20	22	6.0	6.5			6.4	7.2	0.05	0.03	0.2	1.0
10-Jun-04	7.24	7.53	3.2	1.2	17	20	20	22	6.0	6.5			6.4	7.2	0.04	0.02	0.2	1.0
11-Jun-04	6.48	7.46	7.2	1.4	16	19	17	20	6.0	6.5			6.4	7.2	0.05	0.02	0.2	0.8
12-Jun-04	7.00	7.50	6.0	1.6	16	19	17	21	6.0	6.5			6.6	7.4	0.06	0.03	0.2	1.0
13-Jun-04																		
14-Jun-04	7.00	7.51	8.2	1.8	16	19	17	20	6.0	6.5	0.3		6.4	7.4	0.06	0.03	0.2	1.0
15-Jun-04	7.01	7.60	8.6	1.8	16	20	17	21	6.0	6.5	1.2		6.2	7.2	0.06	0.04	0.2	0.8
16-Jun-04	7.05	8.06	8.0	1.8	18	27	22	36	6.0	6.5	1.8		6.4	7.6	0.06	0.03	1.5	1.5
17-Jun-04	7.00	8.31	6.0	1.5	18	28	20	34	6.0	6.5	1.5		6.4	7.4	0.06	0.04	1.5	1.5
18-Jun-04	7.08	8.37	6.0	1.7	18	28	21	35	6.0	6.5	1.5		6.4	7.4	0.06	0.03	1.6	1.6
19-Jun-04	7.04	8.39	7.4	1.8	18	28	20	34	6.0	6.5	1.8		6.4	7.4	0.06	0.04	1.5	1.5
20-Jun-04	7.04	8.38	7.0	16.0	18	29	21	35	6.0	6.5	1.5		6.4	7.2	0.06	0.03	1.5	1.5
21-Jun-04	7.12	8.42	7.0	1.5	18	28	21	35	6.0	6.5	1.7		6.6	7.4	0.05	0.02	1.5	1.5
22-Jun-04	7.08	8.41	7.2	1.5	19	28	20	34	6.0	6.5	1.6		6.4	7.2	0.06	0.03	1.6	1.6
23-Jun-04	7.10	8.23	6.5	1.7	19	27	21	33	6.0	6.5	1.4		6.4	7.2	0.06	0.02	1.5	1.5
24-Jun-04	7.03	8.09	5.0	1.4	17	26	18	29	6.0	6.5	1		6.4	7.4	0.05	0.03	1.5	1.5
25-Jun-04	7.10	8.00	5.8	1.2	18	27	19	34	6.0	6.5	1		6.6	7.4	0.06	0.04	1.5	1.5
26-Jun-04	7.09	8.00	6.0	1.2	18	27	19	32	6.0	6.5	1		6.4	7.2	0.05	0.02	1.5	1.5
27-Jun-04	7.04	7.95	6.0	1.2	18	26	20	32	6.0	6.5	1		6.4	7.4	0.06	0.04	1.5	1.5
28-Jun-04	7.09	7.88	4.2	1.0	18	24	19	28	6.0	6.5	0.8		6.2	7.2	0.05	0.02	1.6	1.6
29-Jun-04	7.13	7.70	5.0	1.0	18	25	19	29	6.0	6.5	0.3		6.9	7.6	0.1	0.03	1.8	1.8
30-Jun-04	6.95	7.59	4.0	1.0	17	25	18	20	6.0	6.5	0.3		6.6	7.9	0.05	0.02	1.6	1.6
Max	7.3	8.4	8.6	16.0	19.0	29.0	22.0	36.0	6.5	7.0	1.8	0.0	6.9	7.9	0.06	0.04	0.2	1.8
Min	6.5	7.5	2.2	1.0	16.0	19.0	17.0	20.0	6.0	6.5	0.1	0.0	6.2	7.2	0.04	0.02	0.2	0.8
Average	7.1	7.9	5.4	1.9	17.6	24.0	19.3	28.0	6.1	6.6	1.1	#DIV/0!	6.5	7.3	0.06	0.03	0.2	1.3



**Table M31.1.5 Water Quality at Salaulim WTP in 2004 (4/6)**

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated
1-Jul-04	7.01	7.65	4.4	1	17.0	23.0	18.0	28.0	6.0	6.5	0.2		6.4	7.4	0.05	0.03		0.8
2-Jul-04	6.96	7.48	5	1	17.0	23.0	18.0	25.0	6.0	6.5	0.3		6.4	7.6	0.06	0.03		1.8
3-Jul-04	7.00	7.45	4.0	1.0	17.0	21.0	18.0	25.0	6.0	6.5	0.3		6.6	7.4	0.1	0.03		1.5
4-Jul-04	7.01	7.42	3.8	1.0	17.0	20.0	18.0	24.0	6.0	6.5	0.2		6.4	7.2	0.04	0.03		1.8
5-Jul-04	7.10	7.59	4.0	1.0	18.0	21.0	19.0	25.0	6.0	6.5	0.1		6.6	7.4	0.05	0.03		1.8
6-Jul-04	7.15	7.62	2.8	1.0	17.0	22.0	18.0	27.0	6.0	6.5			6.4	7.6	0.06	0.03	0.0	1.0
7-Jul-04	7.14	7.50	2.5	1.0	17.0	22.0	18.0	26.0	6.0	6.5			6.4	7.4	0.05	0.03	0.2	1.0
8-Jul-04	7.13	7.46	2.8	1.0	17.0	21.0	18.0	24.0	6.0	6.5			6.4	7.2	0.06	0.04	0.2	1.0
9-Jul-04	7.12	7.47	2.6	1.0	17.0	22.0	18.0	25.0	6.0	6.5			6.6	7.4	0.05	0.03	0.2	0.8
10-Jul-04	7.10	7.48	2.8	1.0	16.0	22.0	18.0	25.0	6.0	6.5			6.6	7.4	0.06	0.04	0.2	0.8
11-Jul-04	7.09	7.46	2.8	1.0	16.0	22.0	18.0	24.0	6.0	6.5			6.4	7.2	0.05	0.02	0.2	0.8
12-Jul-04	7.12	7.54	2.5	1.0	18.0	22.0	19.0	24.0	6.0	6.5			6.6	7.4	0.05	0.02	0.2	1.0
13-Jul-04	7.16	7.52	2.3	1.0	18.0	22.0	18.0	25.0	6.0	6.5			6.4	7.4	0.06	0.03	0.2	1.0
14-Jul-04	7.14	7.50	2.8	1.0	18.0	22.0	20.0	24.0	6.0	6.5			6.4	7.8	0.05	0.03	0.2	0.8
15-Jul-04	7.14	7.50	2.2	1.0	17.0	22.0	19.0	24.0	6.0	6.5			6.4	7.6	0.05	0.02	0.2	0.8
16-Jul-04	7.16	7.60	2.4	0.8	17.0	22.0	19.0	25.0	6.0	6.5			6.6	7.6	0.05	0.02	0.2	0.8
17-Jul-04	7.20	7.61	2.0	1.0	17.0	21.0	19.0	25.0	6.0	6.5			6.4	7.4	0.06	0.04	0.2	0.8
18-Jul-04	7.21	7.62	2.4	1.0	18.0	23.0	19.0	25.0	6.0	6.5			6.6	7.4	0.06	0.04	0.2	0.8
19-Jul-04	7.20	7.61	2.0	0.8	18.0	22.0	19.0	24.0	6.0	6.5			6.6	7.6	0.05	0.04	0.2	0.8
20-Jul-04	7.25	7.64	2.0	0.8	18.0	20.0	18.0	22.0	6.0	6.5			6.6	7.4	0.06	0.03	0.2	1.0
21-Jul-04	7.18	7.65	2.0	1.0	16.0	20.0	19.0	23.0	6.0	6.5			6.4	7.6	0.04	0.04	0.2	1.0
22-Jul-04	7.20	7.62	1.8	0.8	17.0	20.0	19.0	24.0	6.0	6.5			6.4	7.5	0.05	0.03	0.2	1.0
23-Jul-04	7.20	7.60	1.8	0.8	17.0	20.0	19.0	23.0	6.0	6.5			6.6	7.4	0.05	0.04	0.2	1.0
24-Jul-04	7.20	7.60	1.8	0.8	16.0	20.0	19.0	23.0	6.5	7.0			6.6	7.6	0.06	0.04	0.2	1.0
25-Jul-04	7.21	7.60	2.0	1.0	17.0	21.0	19.0	25.0	6.5	7.0			6.4	7.4	0.05	0.04	0.2	1.0
26-Jul-04	7.21	7.60	2.0	0.8	16.0	20.0	19.0	24.0	6.0	6.5			6.6	7.6	0.06	0.04	0.2	0.8
27-Jul-04	7.02	7.40	2.2	1.0	16.0	20.0	18.0	23.0	6.0	6.5			6.4	7.6	0.06	0.04	0.2	0.8
28-Jul-04	7.00	7.44	1.8	0.8	16.0	20.0	18.0	24.0	6.0	6.5			6.4	7.4	0.05	0.04	0.2	0.8
29-Jul-04	6.98	7.50	1.8	0.8	17.0	20.0	18.0	24.0	6.0	6.5			6.4	7.4	0.1	0.04	0.2	1.0
30-Jul-04	6.98	7.35	1.8	1.0	16.0	19.0	18.0	22.0	6.5	7.0			6.8	7.4	0.1	0.09	0.2	1.0
31-Jul-04	7.00	7.42	1.6	0.8	17.0	19.0	18.0	22.0	6.0	6.5			6.6	7.4	0.1	0.04	0.2	1.0
Max	7.3	7.7	4.0	1.0	18.0	23.0	20.0	27.0	6.5	7.0	0.3	0.0	6.8	7.8	0.06	0.09	0.2	1.8
Min	7.0	7.4	1.6	0.8	16.0	19.0	18.0	22.0	6.0	6.5	0.1	0.0	6.4	7.2	0.04	0.02	0.0	0.8
Average	7.1	7.5	2.4	0.9	17.0	21.0	18.5	24.1	6.1	6.6	0.2	#DIV/0!	6.5	7.5	0.05	0.04	0.2	1.0

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated
1-Aug-04	6.90	7.35	1.8	0.8	16.0	19.0	18.0	22.0	6.0	7.0			6.6	7.6	0.05	0.04	0.2	1.0
2-Aug-04	6.98	7.39	1.8	0.8	16.0	20.0	17.0	22.0	6.0	6.5			6.4	7.4	0.06	0.03	0.2	1.0
3-Aug-04	6.95	7.40	2.0	1.0	16.0	20.0	18.0	22.0	6.0	6.5			6.6	7.4	0.05	0.04	0.2	0.8
4-Aug-04	6.95	7.38	2.2	1.0	16.0	19.0	18.0	22.0	6.0	6.5			6.8	7.2	0.05	0.04	0.2	0.8
5-Aug-04	6.96	7.35	2.0	1.0	16.0	19.0	17.0	22.0	6.0	6.5			6.6	7.4	0.05	0.04	0.2	1.0
6-Aug-04	7.00	7.38	2.5	1.0	16.0	19.0	18.0	23.0	6.0	6.5			6.6	7.2	0.06	0.05	0.2	1.0
7-Aug-04	7.00	7.39	2.2	1.0	17.0	19.0	18.0	22.0	6.0	6.5			6.4	7.2	0.05	0.04	0.2	0.8
8-Aug-04	6.98	7.39	2.6	1.0	17.0	19.0	18.0	22.0	6.0	6.5			6.6	7.4	0.06	0.04	0.2	0.8
9-Aug-04	7.00	7.40	2.2	1.0	17.0	19.0	18.0	22.0	6.0	6.5			6.4	7.4	0.05	0.03	0.2	1.0
10-Aug-04	7.02	7.42	2.8	1.0	15.0	19.0	17.0	22.0	6.0	6.0			6.6	7.2	0.06	0.03	0.2	0.6
11-Aug-04	6.90	7.40	2.9	1.0	15.0	19.0	16.0	22.0	6.0	6.0			6.6	7.4	0.05	0.03	0.2	1.0
12-Aug-04	6.98	7.38	4.0	1.0	16.0	19.0	17.0	21.0	6.0	6.5			6.4	7.4	0.06	0.03	0.2	0.8
13-Aug-04	6.95	7.32	3.8	1.0	15.0	18.0	17.0	22.0	6.0	6.0			6.6	7.4	0.05	0.04		1.5
14-Aug-04	6.95	7.33	4.2	1.4	15.0	19.0	17.0	21.0	6.0	6.5			6.4	7.4	0.06	0.04	0.2	0.8
15-Aug-04	6.97	7.33	5.2	1.4	15.0	19.0	17.0	22.0	6.0	6.0			6.6	7.4	0.05	0.04	0.2	1.0
16-Aug-04	7.00	7.32	5.0	1.2	16.0	19.0	17.0	22.0	6.0	6.0			6.4	7.4	0.06	0.04	0.2	0.6
17-Aug-04	7.04	7.31	6.2	1.2	15.0	19.0	16.0	23.0	6.5	7.0	0.1		6.8	7.4	0.08	0.05	0.2	1.0
18-Aug-04	7.01	7.25	6.5	1.3	15.0	19.0	17.0	23.0	6.5	7.0			7.0	7.8	0.1	0.05	0.2	1.0
19-Aug-04	6.97	7.38	6.8	1.2	15.0	19.0	17.0	22.0	6.5	7.0			6.8	7.6	0.1	0.04	0.2	1.0
20-Aug-04	7.00	7.30	6.0	1.2	15.0	19.0	18.0	21.0	6.5	7.0			6.6	7.4	0.15	0.05	0.2	0.8
21-Aug-04	7.00	7.29	6.0	1.2	15.0	18.0	17.0	21.0	6.0	6.5			6.8	7.6	0.1	0.04	0.2	1.0
22-Aug-04	7.00	7.33	5.5	1.0	17.0	19.0	18.0	22.0	6.0	6.5			6.6	7.4	0.08	0.04	0.2	0.8
23-Aug-04	7.00	7.34	5.0	1.0	16.0	19.0	17.0	21.0	6.0	6.5			6.6	7.6	0.1	0.04	0.2	0.6
24-Aug-04	6.98	7.33	4.4	1.0	16.0	19.0	18.0	21.0	6.0	6.5			6.8	7.6	0.1	0.04	0.2	1.0
25-Aug-04	7.00	7.32	4.0	1.0	16.0	19.0	18.0	20.0	6.0	6.5			6.6	7.4	0.08	0.04	0.2	0.8
26-Aug-04	7.00	7.34	4.0	1.0	16.0	18.0	18.0	20.0	6.0	6.5			6.6	7.6	0.1	0.05	0.2	0.6
27-Aug-04	7.00	7.32	3.4	1.0	16.0	19.0	18.0	21.0	6.0	6.5			6.4	7.6	0.08	0.05	0.2	0.8
28-Aug-04	7.00	7.30	3.5	1.0	16.0	19.0	18.0	20.0	6.0	6.5			6.6	7.4	0.1	0.04	0.2	0.8
29-Aug-04	7.00	7.28	3.0	1.0	16.0	18.0	18.0	20.0	6.5	7.0			6.8	7.4	0.1	0.05	0.2	0.8
30-Aug-04	7.00	7.31	3.0	1.0	16.0	19.0	17.0	21.0	6.5	7.0			6.6	7.6	0.1	0.04	0.2	1.0
31-Aug-04	7.00	7.32	3.0	1.2	16.0	19.0	18.0	22.0	6.0	6.5			6.8	7.6	0.1	0.05	0.2	0.8
Max	7.0	7.4	6.8	1.4	17.0	20.0	18.0	23.0	6.5	7.0	0.1	0.0	7	7.8	0.15	0.05	0.2	1.5
Min	6.9	7.3	2.0	1.0	15.0	18.0	16.0	20.0	6.0	6.0	0.1	0.0	6.4	7.2	0.05	0.03	0.2	0.6
Average	7.0	7.3	3.9	1.1	15.8	18.9	17.4	21.6	6.1	6.5	0.1	#DIV/0!	6.6	7.4	0.08	0.04	0.2	0.9

**Table M31.15 Water Quality at Salaulim WTP in 2004 (5/6)**

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated
1-Sep-04	7.00	7.33	3.0	1.0	16.0	19.0	17.0	21.0	6.0	6.5			6.6	7.6	0.08	0.04	0.2	0.8
2-Sep-04	7.00	7.26	3.0	1.0	16.0	18.0	17.0	20.0	6.0	6.5			6.8	7.4	0.1	0.05	0.2	0.8
3-Sep-04	7.00	7.25	4.0	1.0	15.0	19.0	17.0	21.0	6.0	6.5			6.8	7.6	0.08	0.05	0.2	1.0
4-Sep-04	7.00	7.26	3.0	1.0	16.0	19.0	18.0	22.0	6.0	6.5			6.8	7.6	0.08	0.05	0.2	0.8
5-Sep-04	7.00	7.27	3.0	1.0	16.0	18.0	18.0	22.0	6.0	6.5			6.6	7.4	0.08	0.04	0.2	0.8
6-Sep-04	6.93	7.25	2.5	1.0	16.0	19.0	17.0	21.0	6.0	6.5			6.8	7.6	0.1	0.05	0.2	0.3
7-Sep-04	6.95	7.29	3.0	1.0	16.0	20.0	17.0	22.0	6.0	6.5			6.6	7.4	0.1	0.06	0.2	1.0
8-Sep-04	6.92	7.30	3.4	1.0	15.0	19.0	17.0	22.0	6.0	6.5			6.4	7.5	0.1	0.05	0.2	1.0
9-Sep-04	6.91	7.30	3.0	1.0	15.0	19.0	17.0	22.0	6.0	6.5			6.6	7.4	0.1	0.05	0.2	0.8
10-Sep-04	6.90	7.22	2.8	1.0	16.0	19.0	18.0	21.0	6.0	6.5			6.6	7.6	0.1	0.05	0.2	0.8
11-Sep-04	6.90	7.25	3.0	1.0	16.0	19.0	17.0	21.0	6.0	6.5			6.8	7.4	0.1	0.05	0.2	0.8
12-Sep-04	6.96	7.29	2.8	1.0	16.0	19.0	17.0	22.0	6.0	6.5			6.6	7.4	0.1	0.05	0.2	0.8
13-Sep-04	6.90	7.25	2.5	1.0	16.0	19.0	17.0	21.0	6.0	6.5			6.4	7.4	0.1	0.05	0.2	0.8
14-Sep-04	6.95	7.23	2.6	1.0	16.0	19.0	18.0	22.0	6.0	6.5			6.2	7.4	0.08	0.05	0.2	1.0
15-Sep-04	6.91	7.30	2.0	0.8	16.0	20.0	17.0	23.0	6.0	6.5			6.5	7.4	0.07	0.04	0.2	1.0
16-Sep-04																		
17-Sep-04	6.90	7.36	2.5	1.0	15.0	19.0	16.0	21.0	6.0	6.5			6.4	7.2	0.08	0.05	0.2	1.0
18-Sep-04	6.97	7.23	2.0	1.0	15.0	19.0	16.0	20.0	6.0	6.5			6.3	7.3	0.06	0.04	0.2	0.8
19-Sep-04	7.00	7.29	2.3	1.0	15.0	19.0	17.0	22.0	6.0	6.5			6.2	7.6	0.1	0.07	0.2	1.0
20-Sep-04	6.90	7.26	2.8	1.0	15.0	18.0	17.0	21.0	6.0	6.0			6.4	7.2	0.1	0.05	0.2	1.0
21-Sep-04	6.95	7.23	2.0	1.0	15.0	18.0	16.0	20.0	6.0	6.5			6.2	7.4	0.08	0.04	0.2	1.0
22-Sep-04	6.90	7.22	1.8	1.0	15.0	18.0	17.0	21.0	6.0	6.5			6.6	7.4	0.08	0.05	0.2	1.0
23-Sep-04	6.90	7.23	2.0	1.0	16.0	18.0	17.0	21.0	6.0	6.5			6.6	7.4	0.1	0.05	0.2	0.8
24-Sep-04	6.93	7.27	2.2	1.0	16.0	18.0	17.0	22.0	6.0	6.5			6.4	0.2	0.08	0.05	0.2	0.8
25-Sep-04	6.90	7.22	2.0	1.0	15.0	18.0	17.0	21.0	6.0	6.5			6.4	7.4	0.08	0.05	0.2	0.8
26-Sep-04	6.90	7.23	2.4	1.0	15.0	18.0	17.0	21.0	6.0	6.5	0.1		6.6	7.4	0.1	0.05	0.2	0.8
27-Sep-04	6.99	7.15	2.4	1.0	16.0	19.0	17.0	22.0	6.0	6.5			6.4	7.4	0.08	0.05	0.2	1.0
28-Sep-04	6.90	7.21	2.0	1.0	16.0	18.0	17.0	22.0	6.0	6.5			6.4	7.4	0.08	0.05	0.2	0.8
29-Sep-04	6.97	7.20	1.8	1.0	16.0	19.0	17.0	21.0	6.0	6.5			6.6	7.2	0.1	0.05	0.2	1.0
30-Sep-04	6.95	7.21	2.0	1.0	16.0	19.0	17.0	21.0	6.0	6.5			6.6	7.4	0.1	0.05	0.2	0.8
Max	7.0	7.4	4.0	1.0	16.0	20.0	18.0	23.0	6.0	6.5	0.1	0.0	6.8	7.6	0.1	0.07	0.2	1.0
Min	6.9	7.2	1.8	0.8	15.0	18.0	16.0	20.0	6.0	6.0	0.1	0.0	6.2	0.2	0.06	0.04	0.2	0.3
Average	6.9	7.3	2.5	1.0	15.6	18.7	17.0	21.4	6.0	6.5	0.1	#DIV/0!	6.5	7.1	0.09	0.05	0.2	0.9

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated
1-Oct-04	6.93	7.20	4.0	1.0	16.0	18.0	17.0	20.0	6.0	6.5			6.4	7.2	0.08	0.05		0.8
2-Oct-04	6.96	7.21	3.0	1.0	16.0	18.0	17.0	21.0	6.0	6.5			6.6	7.4	0.10	0.05		0.8
3-Oct-04	6.95	7.21	2.5	1.0	16.0	18.0	17.0	22.0	6.0	6.5			6.4	7.2	0.08	0.04	0.2	0.8
4-Oct-04	6.90	7.21	2.5	1.0	16.0	19.0	17.0	21.0	6.0	6.5			6.4	7.2	0.10	0.05	0.2	0.8
5-Oct-04	6.90	7.16	1.5	1.0	16.0	18.0	17.0	20.0	6.0	6.5			6.6	7.4	0.08	0.05	0.2	0.8
6-Oct-04	6.99	7.29	1.8	1.0	15.0	18.0	17.0	21.0	6.0	6.5			6.6	7.2	0.10	0.05	0.2	1.0
7-Oct-04	6.90	7.20	2.0	1.0	16.0	18.0	17.0	20.0	6.0	6.5			6.4	7.2	0.08	0.05	0.2	1.0
8-Oct-04	6.90	7.20	2.2	1.0	16.0	19.0	17.0	22.0	6.0	6.5			6.6	7.4	0.08	0.06	0.2	1.0
9-Oct-04	6.90	7.20	1.8	0.8	16.0	18.0	17.0	21.0	6.0	6.5			6.4	7.4	0.08	0.06	0.2	0.8
10-Oct-04	6.90	7.20	2.0	1.0	16.0	19.0	17.0	21.0	6.0	6.5			6.6	7.4	0.08	0.06	0.2	0.8
11-Oct-04																		
12-Oct-04	6.90	7.20	2.4	1.0	15.0	18.0	16.0	21.0	6.0	6.5			6.6	7.2	0.10	0.06	0.2	0.8
13-Oct-04	6.97	7.24	2.0	1.0	15.0	19.0	16.0	21.0	6.0	6.5			6.4	7.4	0.08	0.04	0.2	0.8
14-Oct-04	6.95	7.20	2.0	1.0	15.0	18.0	16.0	21.0	6.0	6.5			6.6	7.4	0.08	0.03	0.2	0.8
15-Oct-04	6.94	7.26	2.5	1.0	15.0	18.0	17.0	21.0	6.0	6.5			6.6	7.4	0.08	0.06	0.2	1.0
16-Oct-04	6.95	7.24	2.2	1.0	16.0	18.0	17.0	21.0	6.0	6.5			6.6	7.4	0.06	0.05	0.2	0.8
17-Oct-04	6.91	7.22	2.2	1.0	16.0	18.0	17.0	21.0	6.0	6.5			6.6	7.4	0.08	0.05	0.2	0.8
18-Oct-04	6.91	7.20	2.0	1.0	16.0	17.0	17.0	21.0	6.0	6.5			6.4	7.4	0.08	0.06	0.2	0.8
19-Oct-04	6.94	7.25	2.3	0.8	15.0	19.0	17.0	22.0	6.0	6.5			6.6	7.2	0.10	0.05	0.2	0.8
20-Oct-04	6.93	7.23	2.0	1.0	15.0	18.0	17.0	22.0	6.0	6.5			6.4	7.2	0.10	0.05	0.2	0.8
21-Oct-04	6.91	7.20	2.0	1.0	15.0	18.0	16.0	21.0	6.0	6.5			6.6	7.4	0.08	0.05	0.2	0.8
22-Oct-04	6.93	7.21	2.0	1.0	16.0	18.0	17.0	21.0	6.0	6.5			6.6	7.4	0.08	0.04	0.2	0.8
23-Oct-04	6.92	7.20	2.0	1.0	16.0	17.0	17.0	21.0	6.0	6.5			6.4	7.2	0.10	0.05	0.2	0.8
24-Oct-04	6.92	7.23	2.0	1.0	16.0	18.0	17.0	22.0	6.6	6.5			6.6	7.4	0.08	0.04	0.2	0.8
25-Oct-04	6.90	7.22	2.0	1.0	16.0	17.0	17.0	21.0	6.0	6.5			6.4	7.2	0.10	0.05	0.2	0.8
26-Oct-04	7.00	7.29	2.4	1.0	15.0	18.0	16.0	20.0	6.0	6.5			6.4	7.2	0.08	0.07	0.2	0.8
27-Oct-04	7.00	7.30	2.0	1.0	15.0	19.0	17.0	21.0	6.0	6.5			6.9	7.9	0.08	0.06	0.2	0.8
28-Oct-04	6.97	7.28	2.0	1.0	15.0	18.0	17.0	21.0	6.0	6.5			6.4	7.4	0.10	0.05	0.2	0.8
29-Oct-04	6.99	7.32	1.8	0.8	15.0	18.0	17.0	20.0	6.0	6.5			6.6	7.9	0.08	0.06	0.2	0.8
30-Oct-04	6.98	7.30	2.0	1.0	15.0	18.0	17.0	21.0	6.0	6.5			6.6	7.4	0.10	0.05	0.2	1.0
31-Oct-04																		
Max	7.0	7.3	2.5	1.0	16.0	19.0	17.0	22.0	6.6	6.5	0.0	0.0	6.9	7.9	0.1	0.07	0.2	1.0
Min	6.9	7.2	1.5	0.8	15.0	17.0	16.0	20.0	6.0	6.5	0.0	0.0	6.4	7.2	0.06	0.03	0.2	0.8
Average	6.9	7.2	2.1	1.0	15.5	18.1	16.8	21.0	6.0	6.5	#DIV/0!	#DIV/0!	6.5	7.4	0.09	0.05	0.2	0.8

**Table M31.15 Water Quality at Salaulim WTP in 2004 (6/6)**

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated
1-Nov-04	6.95	7.26	2.0	1.0	15.0	18.0	16.0	20.0	6.0	6.5			6.4	7.4	0.08	0.04	0.2	0.8
2-Nov-04																		
3-Nov-04																		
4-Nov-04	6.95	7.28	2.0	1.0	16.0	18.0	17.0	22.0	6.0	6.5			6.6	7.4	0.10	0.05	0.2	0.8
5-Nov-04	7.03	7.38	1.8	1.0	17.0	20.0	18.0	21.0	6.0	6.5			6.4	7.6	0.08	0.05	0.2	1.0
6-Nov-04	6.98	7.30	2.0	1.0	16.0	19.0	18.0	22.0	6.0	6.5			6.6	7.4	0.08	0.05	0.2	0.8
7-Nov-04	6.46	7.28	1.8	1.0	16.0	19.0	18.0	21.0	6.0	6.5			6.4	7.4	0.10	0.05	0.2	1.0
8-Nov-04																		
9-Nov-04	7.01	7.32	1.8	1.0	17.0	19.0	18.0	22.0	6.0	6.5			6.4	7.2	0.08	0.05	0.2	0.8
10-Nov-04	7.07	7.32	1.8	1.0	16.0	19.0	16.0	20.0	6.0	6.5			6.4	7.4	0.06	0.04	0.2	0.8
11-Nov-04																		
12-Nov-04	6.97	7.30	2.0	1.0	16.0	19.0	17.0	21.0	6.0	6.5			6.4	7.2	0.06	0.04	0.2	0.8
13-Nov-04	6.94	7.30	2.0	0.8	16.0	18.0	17.0	21.0	6.0	6.5			6.6	7.4	0.08	0.04	0.2	0.8
14-Nov-04	6.98	7.30	2.0	1.0	16.0	19.0	17.0	22.0	6.0	6.5			6.4	7.2	0.08	0.04	0.2	0.8
15-Nov-04	7.00	7.34	2.0	1.0	16.0	19.0	17.0	22.0	6.0	6.5	0.1		6.4	7.4	0.08	0.05	0.2	0.8
16-Nov-04	7.00	7.36	2.0	1.0	16.0	19.0	17.0	24.0	6.0	6.5	0.1		6.6	7.4	0.06	0.04	0.2	0.8
17-Nov-04	7.02	7.42	2.0	1.0	16.0	20.0	17.0	24.0	6.0	6.5	0.1		6.4	7.2	0.08	0.05	0.2	0.8
18-Nov-04																		
19-Nov-04	7.08	7.39	2.2	1.0	15.0	19.0	17.0	22.0	6.5	6.7			6.6	7.4	0.08	0.05	0.2	0.8
20-Nov-04	7.03	7.38	1.8	1.0	16.0	20.0	17.0	22.0	6.5	7.0	0.1		6.2	7.4	0.08	0.05	0.2	0.8
21-Nov-04																		
22-Nov-04	7.07	7.46	2.0	1.0	16.0	21.0	17.0	25.0	6.5	7.0	0.1		6.4	7.4	0.08	0.06	0.2	0.8
23-Nov-04	7.06	7.48	2.0	1.0	16.0	21.0	17.0	24.0	6.0	6.5	0.1		6.4	7.6	0.08	0.05	0.2	1.0
24-Nov-04	7.00	7.54	1.8	1.0	16.0	22.0	17.0	25.0	6.0	6.5	0.1		6.6	7.6	0.06	0.04	0.2	0.8
25-Nov-04	7.01	7.47	1.5	1.0	16.0	21.0	17.0	24.0	6.0	6.5	0.1		6.6	7.4	0.06	0.04	0.2	0.8
26-Nov-04	7.03	7.43	1.8	1.0	16.0	21.0	17.0	25.0	6.0	6.5	0.2		6.9	7.9	0.08	0.05	0.2	1.0
27-Nov-04	7.03	7.46	2.2	1.0	16.0	22.0	17.0	24.0	6.0	6.5	0.1		6.6	7.4	0.08	0.05	0.2	0.8
28-Nov-04	7.03	7.46	2.4	1.0	16.0	21.0	17.0	24.0	6.0	6.5	0.1		6.4	7.2	0.08	0.04	0.2	0.6
29-Nov-04	7.02	7.44	2.0	1.0	16.0	20.0	17.0	23.0	6.0	6.5	0.1		6.6	7.4	0.06	0.05	0.2	0.8
30-Nov-04	7.00	7.42	2.0	1.2	16.0	20.0	17.0	22.0	6.0	6.5	0.2		6.6	7.4	0.08	0.05	0.2	0.8
Max	7.1	7.5	2.4	1.2	17.0	22.0	18.0	25.0	6.5	7.0	0.2	0.0	6.9	7.9	0.1	0.06	0.2	1.0
Min	6.5	7.3	1.5	0.8	15.0	18.0	16.0	20.0	6.0	6.5	0.1	0.0	6.2	7.2	0.06	0.04	0.2	0.6
Average	7.0	7.4	2.0	1.0	16.0	19.8	17.1	22.7	6.1	6.6	0.1	#DIV/0!	6.5	7.4	0.08	0.05	0.2	0.8

Date	pH		Turbidity NTU		Alkalinity mg/L		Hardness mg/L		Chloride ion mg/L		Mn <sup>2+</sup> mg/L		DO mg/L		Iron mg/L		Residual Chlorine mg/L	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Pre	Treated
1-Dec-04	7.08	7.60	1.5	0.9	15.0	21.0	16.0	24.0	6.5	7.0	0.1		6.6	7.4	0.06	0.05	0.2	1.0
2-Dec-04	7.04	7.55	2.0	1.0	16.0	21.0	17.0	24.0	6.0	6.5	0.2		6.6	7.4	0.08	0.05	0.2	0.6
3-Dec-04	7.04	7.62	2.0	1.0	16.0	21.0	17.0	24.0	6.0	6.5	0.1		6.4	7.2	0.06	0.04	0.2	0.8
4-Dec-04	7.00	7.61	2.0	1.0	16.0	20.0	17.0	24.0	6.0	6.5	0.1		6.6	7.4	0.08	0.04	0.2	1.0
5-Dec-04	6.98	7.61	1.8	1.0	16.0	22.0	17.0	25.0	6.0	6.5	0.2		6.4	7.4	0.06	0.04	0.2	0.8
6-Dec-04																		
7-Dec-04																		
8-Dec-04																		
9-Dec-04	7.00	7.61	2.0	1.0	16.0	21.0	17.0	25.0	6.0	6.5	0.2		6.4	7.2	0.08	0.04		1.2
10-Dec-04	7.00	7.55	2.0	1.0	17.0	21.0	18.0	26.0	6.0	7.0	0.2		6.4	7.4	0.06	0.06		1.5
11-Dec-04																		
12-Dec-04	7.00	7.62	2.0	1.0	16.0	22.0	18.0	25.0	6.0	6.5	0.2		6.6	7.4	0.08	0.04		1.2
13-Dec-04	7.00	7.69	2.0	1.0	16.0	22.0	17.0	25.0	6.5	7.0	0.2		6.4	7.4	0.08	0.06		1.4
14-Dec-04	6.95	7.70	1.8	0.8	16.0	23.0	17.0	26.0	6.5	7.0	0.2		6.2	7.4	0.06	0.04		1.4
15-Dec-04	7.00	7.68	1.8	0.9	16.0	22.0	17.0	26.0	6.0	6.5	0.2		6.2	7.6	0.05	0.05		1.6
16-Dec-04																		
17-Dec-04	7.00	7.98	2.0	0.8	16.0	25.0	18.0	29.0	6.0	7.0	0.4		6.2	7.0	0.06	0.05		1.5
18-Dec-04	7.04	8.12	1.6	0.9	16.0	26.0	18.0	31.0	6.0	7.0	0.3		6.4	7.2	0.05	0.05		1.4
19-Dec-04																		
20-Dec-04	7.00	8.04	2.2	0.8	16.0	25.0	18.0	30.0	6.5	7.0	0.3		6.2	7.0	0.08	0.05		1.5
21-Dec-04	7.02	8.11	2.0	0.8	16.0	25.0	17.0	30.0	6.0	7.0	0.4		6.2	7.2	0.08	0.04		1.6
22-Dec-04	7.05	8.14	2.0	1.0	16.0	25.0	18.0	31.0	6.0	7.0	0.3		6.2	7.2	0.06	0.05		1.6
23-Dec-04	7.01	8.03	2.2	1.0	16.0	25.0	18.0	31.0	6.0	7.0	0.4		6.2	7.0	0.08	0.05		1.6
24-Dec-04	7.00	8.03	2.0	1.0	16.0	24.0	17.0	29.0	6.0	6.5	0.4		6.4	7.2	0.08	0.04		1.4
25-Dec-04	7.00	7.79	2.0	1.0	15.0	22.0	17.0	26.0	6.0	6.5	0.2		6.2	7.2	0.06	0.04		1.4
26-Dec-04	7.00	7.82	2.0	1.0	15.0	23.0	16.0	25.0	6.0	6.5	0.1		6.4	7.2	0.06	0.04		1.4
27-Dec-04	7.00	7.72	2.0	1.0	15.0	22.0	17.0	25.0	6.0	6.5	0.5		6.4	7.4	0.08	0.05		1.4
28-Dec-04	7.04	7.60	1.8	0.8	15.0	21.0	17.0	23.0	6.0	6.5	0.5		6.2	7.0	0.06	0.04		1.4
29-Dec-04	7.12	7.61	2.4	1.0	16.0	20.0	17.0	24.0	6.0	6.5	0.5		6.2	7.2	0.05	0.05		1.2
30-Dec-04																		
31-Dec-04	7.01	7.42	2.0	1.0	15.0	19.0	17.0	22.0	6.0	6.5			6.2	7.2	0.06	0.04	0.2	0.8
Max	7.1	8.1	2.4	1.0	17.0	26.0	18.0	31.0	6.5	7.0	0.4	0.0	6.6	7.6	0.08	0.06	0.2	1.6
Min	7.0	7.4	1.6	0.8	15.0	19.0	16.0	22.0	6.0	6.5	0.1	0.0	6.2	7.0	0.05	0.04	0.2	0.8
Average	7.0	7.8	2.0	0.9	15.8	22.5	17.3	26.5	6.1	6.7	0.2	#DIV/0!	6.3	7.2	0.07	0.05	0.2	1.3

**Table M31.1.6 Results on Manganese Concentration of Raw Water at Salaulim WTP in 1997 and from 2000 to 2004 (1/2)**

Date	1997		2000		2001		2002		2003		2004		Date	1997		2000		2001		2002		2003		2004	
	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated		Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated	Raw	Treated
Max	1.8	0.1	2.8	0.0	3.0	0.0	2.0	0.0	3.6	0.3	1.8	0.0	Max	1.8	0.1	2.8	0.0	3.0	0.0	2.0	0.0	3.6	0.3	1.8	0.0
Min	0.1	0.1	0.1	0.0	0.1	0.0	0.1	0.0	0.1	0.1	0.1	0.0	Min	0.1	0.1	0.1	0.0	0.1	0.0	0.1	0.0	0.1	0.1	0.1	0.0
Average	0.1	0.0	0.0	0.0	0.2	0.0	0.1	0.0	0.1	0.0	0.1	0.0	Average	0.1	0.0	0.0	0.0	0.2	0.0	0.1	0.0	0.1	0.0	0.1	0.0
1-Jan	0.4				0.5				1.2				1-Apr	0.3				0.6				0.4		0.6	
2-Jan	1.0				0.6				1.2				2-Apr	0.5				0.6				0.4		0.7	
3-Jan	1.0		0.6		0.5				0.2				3-Apr					0.5				0.3		0.6	
4-Jan	0.8				0.5			0.2					4-Apr	0.5				0.4				0.5		0.5	
5-Jan	1.0		0.1		0.4			0.2					5-Apr	0.5				0.5				0.5		0.5	
6-Jan	0.8				0.4								6-Apr	0.8				0.4						0.5	
7-Jan	1.0				0.4								7-Apr	1.0				0.4						0.5	
8-Jan	0.8		0.1		0.4								8-Apr	1.0				0.4						0.5	
9-Jan	0.8				0.3			0.2	0.1				9-Apr	0.8				0.4				0.4		0.5	
10-Jan					0.2				0.1				10-Apr	0.8				0.4				0.5		0.5	
11-Jan					0.2								11-Apr	0.8				0.4				0.5			
12-Jan	0.4				0.2								12-Apr	1.0				0.4				0.4		0.3	
13-Jan	0.5				0.2								13-Apr	1.0				0.4				0.3		0.1	
14-Jan	0.6				0.2								14-Apr	0.8				0.2						0.2	
15-Jan	0.6				0.1								15-Apr	1.0				0.3						0.1	
16-Jan	0.2												16-Apr	1.0				0.2				0.4		0.1	
17-Jan					0.2								17-Apr	0.8				0.4				0.2		0.1	
18-Jan					0.1								18-Apr	0.6				0.4				0.3		0.1	
19-Jan					0.1								19-Apr	0.8				0.4				0.1			
20-Jan					0.1								20-Apr	0.8				0.4							
21-Jan					0.1								21-Apr	0.3				0.3							
22-Jan					0.1								22-Apr	0.4				0.4							
23-Jan					0.1								23-Apr	0.6				0.4				0.2		0.1	
24-Jan					0.2								24-Apr	0.5				0.4				0.2		0.1	
25-Jan													25-Apr	0.3				0.4				0.1		0.1	
26-Jan	0.1				0.1								26-Apr	0.2				0.4				0.2		0.1	
27-Jan	0.1				0.1								27-Apr	0.3				0.4						0.1	
28-Jan	0.2												28-Apr	0.3				0.4							
29-Jan													29-Apr	0.8				0.5						0.1	
30-Jan													30-Apr	0.1				0.3				0.2			
31-Jan																									
1-Feb													1-May	0.2				0.3				0.1			
2-Feb													2-May	0.2				0.3							
3-Feb													3-May	0.2				0.4							0.1
4-Feb													4-May	0.3				0.4							
5-Feb					0.1								5-May	0.4				0.4							
6-Feb					0.1								6-May	0.3				0.4							0.1
7-Feb					0.2								7-May	0.2				0.4							0.1
8-Feb					0.2								8-May	0.2				0.4							
9-Feb					0.1								9-May	0.2				0.4							
10-Feb					0.1								10-May	0.2				0.5							
11-Feb					0.2								11-May	0.1				0.4				0.8			
12-Feb					0.1								12-May	0.1				0.3							
13-Feb					0.1								13-May	0.1				0.3							
14-Feb					0.1								14-May					0.3							
15-Feb					0.1								15-May					0.2							
16-Feb					0.1								16-May					0.2							
17-Feb					0.1								17-May												
18-Feb	0.1				0.1								18-May												
19-Feb					0.1								19-May												
20-Feb					0.1								20-May												
21-Feb					0.2								21-May												
22-Feb					0.2								22-May												
23-Feb					0.1								23-May												
24-Feb					0.1								24-May												
25-Feb					0.2								25-May												
26-Feb					0.2								26-May												
27-Feb					0.2								27-May												
28-Feb					0.2								28-May												
29-Feb													29-May												
30-Feb													30-May												
31-Feb													31-May												
1-Mar					0.4								1-Jun												
2-Mar					0.4								2-Jun												
3-Mar					0.4								3-Jun												
4-Mar	0.1				0.4								4-Jun												
5-Mar					0.4								5-Jun												
6-Mar					0.8					0.3			6-Jun												
7-Mar					0.6					0.3			7-Jun												
8-Mar					0.7					0.4			8-Jun												
9-Mar					0.6					0.5			9-Jun			2.4									0.1
10-Mar																									






Figure M31.1.2 Fluctuation on Manganese Concentration of Raw Water at Salaulim WTP in 1997 and from 2000 to 2004

**Table M31.1.7 Monthly Water Quality of Salaulim WTP Analysed by PWD's Laboratory from January 2003 to May 2005 (1/2)**

	Color			Odor			Taste			Turbidity (NTU)			pH			Specific Conductivity (/u mhos/cm)		
	Raw	Filtered	Treated	Raw	Filtered	Treated	Raw	Filtered	Treated	Raw	Filtered	Treated	Raw	Filtered	Treated	Raw	Filtered	Treated
Jan-03	0	0		Unobjectable			Unobjectable			2.3	1.5		6.9	7.1		41.1	49.4	
Feb-03	0	0		Unobjectable			Unobjectable			0.8	0.3		6.7	7.1		44.3	53.8	
Mar-03	0	0		Unobjectable			Unobjectable			3.2	1.2		6.3	7.3		51.0	72.4	
Apr-03	0	0		Unobjectable			Unobjectable			3.0	1.5		6.7	6.8		58.4	59.8	
May-03	0	0		Unobjectable			Unobjectable			3.2	2.0		6.8	6.8		56.6	58.9	
Jun-03	0	0		Unobjectable			Unobjectable			13.6	2.5		6.1	7.6		46.5	73.7	
Jul-03	0	0		Unobjectable			Unobjectable			3.8	1.5		6.7	7.2		43.3	62.7	
Aug-03	0	0		Unobjectable			Unobjectable			2.8	1.0		6.4	6.8		38.8	47.7	
Sep-03	0	0		Unobjectable			Unobjectable			3.3	0.9		6.9	7.1		47.4	56.0	
Oct-03	0	0		Unobjectable			Unobjectable			1.0	0.6		6.9	7.2		39.9	53.2	
Nov-03	0	0		Unobjectable			Unobjectable			1.3	0.8		6.8	7.0		42.4	53.8	
Dec-03	0	0		Unobjectable			Unobjectable			0.9	0.5		7.0	7.9		47.3	63.0	
Jan-04	0	0		Unobjectable			Unobjectable			1.4	0.5		7.0	8.8		46.7	60.8	
Feb-04	0	0		Unobjectable			Unobjectable			1.4	0.3		7.3	7.5		41.2	47.6	
Mar-04	0	0	0	Unobjectable			Unobjectable			2.0	0.7	0.7	6.8	7.2	7.0	47.1	56.0	56.7
Apr-04	0	0	0	Unobjectable			Unobjectable			2.9	0.5	0.5	6.8	7.9	7.5	48.6	70.3	71.4
May-04	0	0	0	Unobjectable			Unobjectable			6.3	1.6	1.5	7.3	7.1	7.1	102.4	101.4	109.5
Jun-04	0	0	0	Unobjectable			Unobjectable			2.6	1.3	1.0	6.8	7.0	7.1	53.1	56.3	56.0
Jul-04	0	0	0	Unobjectable			Unobjectable			6.2	1.4	1.0	6.7	7.9	7.7	55.2	64.7	64.9
Aug-04	0	0	0	Unobjectable			Unobjectable			4.8	1.5	1.4	7.0	7.2	7.2	48.1	52.1	53.5
Sep-04	0	0	0	Unobjectable			Unobjectable			4.8	2.0	1.4	6.9	7.3	7.2	50.8	51.2	52.2
Oct-04	0	0	0	Unobjectable			Unobjectable			1.0	0.5	0.4	7.1	7.3	7.2	48.8	40.0	40.4
Nov-04	0	0	0	Unobjectable			Unobjectable			1.0	0.8	0.9	6.7	6.8	6.8	44.3	50.8	53.6
Dec-04	0	0	0	Unobjectable			Unobjectable			2.0	1.2	1.5	7.2	7.5	8.1	44.6	56.0	56.9
Jan-05	0	0	0	Unobjectable			Unobjectable			1.8	1.0	1.0	7.2	7.5	7.5	45.8	54.6	56.5
Feb-05	0	0	0	Unobjectable			Unobjectable			2.0	1.7	1.7	6.9	7.1	7.1	44.5	56.3	57.0
Mar-05	0	0	0	Unobjectable			Unobjectable			2.5	1.3	1.3	6.7	7.1	7.0	45.9	58.6	58.5
Apr-05	0	0	0	Unobjectable			Unobjectable			3.0	1.5	1.3	6.5	7.1	7.1	53.2	65.5	65.7
May-05	0	0	0	Unobjectable			Unobjectable			3.4	1.9	2.0	7.1	7.2	7.2	50.3	59.8	62.2
Max	0.0	0.0	0.0							13.6	2.5	2.0	7.3	8.8	8.1	102.4	101.4	109.5
Min	0.0	0.0	0.0	Unobjectable			Unobjectable			0.8	0.3	0.4	6.1	6.8	6.8	38.8	40.0	40.4
Ave	0.0	0.0	0.0							3.0	1.2	1.2	6.8	7.3	7.3	49.2	58.8	61.0


	Total Solids (mg/L)			Total Dissolved Solids(TDS) (mg/L)			Suspended Solids (mg/L)			Total Hardness as CaCO <sub>3</sub> (TA) (mg/L)			Ca <sup>2+</sup> (mg/L)			Mg <sup>2+</sup> (mg/L)		
	Raw	Filtered	Treated	Raw	Filtered	Treated	Raw	Filtered	Treated	Raw	Filtered	Treated	Raw	Filtered	Treated	Raw	Filtered	Treated
Jan-03	26.0	31.0		26.0	31.0		0.0	0.0		12.0	14.0		3.6	4.4		0.8	0.3	
Feb-03	29.0	35.0		29.0	35.0		0.0	0.0		13.0	16.0		3.6	1.8		1.0	1.0	
Mar-03	33.0	45.0		32.0	46.0		1.5	0.0		17.0	28.0		3.6	8.4		2.0	2.0	
Apr-03	38.0	39.0		37.0	39.0		1.0	0.0		23.0	24.0		4.0	4.4		3.3	3.3	
May-03	38.0	37.0		36.0	37.0		2.0	0.0		25.0	25.0		4.8	4.8		3.3	3.3	
Jun-03	34.0	47.0		30.0	47.0		4.0	0.0		19.0	37.0		3.6	9.6		2.5	3.3	
Jul-03	29.5	40.0		28.0	40.0		1.5	0.0		15.0	23.0		3.6	6.0		1.5	2.0	
Aug-03	26.0	31.0		25.0	31.0		1.0	0.0		16.0	20.0		3.2	4.8		2.0	2.0	
Sep-03	31.5	36.0		30.0	36.0		1.5	0.0		16.0	23.0		3.2	6.0		2	2.0	
Oct-03	26.0	34.5		26.0	34.5		0.0	0.0		16.0	20.0		3.2	5.6		2.0	1.0	
Nov-03	27.0	34.0		27.0	34.0		0.0	0.0		16.0	22.0		3.6	5.6		1.8	2.0	
Dec-03	30.0	39.0		30.0	39.0		0.0	0.0		17.0	26.0		3.6	6.4		2.0	2.5	
Jan-04	30.0	39.0		30.0	39.0		0.0	0.0		16.0	25.0		3.6	6.4		1.8	2.3	
Feb-04	26.0	30.0		26.0	30.0		0.0	0.0		14.0	19.0		3.6	5.2		1.3	1.5	
Mar-04	29.5	36.0	36.0	30.0	36.0	36.0	0.5	0.0	0.0	15.0	20.0	20.0	3.6	5.6	5.6	1.5	1.5	1.5
Apr-04	31.5	45.0	45.5	31.0	45.0	45.5	0.5	0.0	0.0	15.0	25.0	25.0	3.2	7.2	7.2	1.8	1.8	1.8
May-04	67.0	65.0	70.0	65.0	65.0	70.0	2.0	0.0	0.0	40.0	40.0	40.0	10.0	10.0	10.0	3.8	3.8	3.8
Jun-04	34.0	36.0	36.0	33.5	36.0	36.0	0.5	0.0	0.0	14.0	16.0	16.0	3.2	4.0	4.0	1.5	1.5	1.5
Jul-04	37.5	41.5	41.5	35.5	41.5	41.5	2.0	0.0	0.0	18.0	26.0	26.0	4.4	7.2	7.2	1.8	2.0	2.0
Aug-04	32.0	33.0	34.0	31.0	33.0	34.0	1.0	0.0	0.0	17.0	20.0	20.0	4.0	4.8	4.8	1.8	2.0	2.0
Sep-04	33.0	33.0	33.5	32.0	33.0	33.5	1.0	0.0	0.0	15.0	19.0	19.0	4.0	4.8	4.8	1.3	1.8	1.8
Oct-04	31.0	31.5	31.5	31.0	31.5	31.5	0.0	0.0	0.0	17.0	17.0	17.0	4.8	4.8	4.8	1.3	1.3	1.3
Nov-04	28.0	32.5	34.0	28.0	32.5	34.0	0.0	0.0	0.0	14.0	18.0	18.0	3.6	4.8	4.8	1.3	1.5	1.5
Dec-04	29.5	36.0	36.5	28.5	36.0	36.5	0.0	0.0	0.0	15.0	20.0	21.0	3.6	5.6	6.0	1.5	1.5	1.5
Jan-05	29.5	35.0	36.0	29.0	35.0	36.0	0.5	0.0	0.0	14.0	17.0	17.0	3.6	4.8	4.8	1.2	1.3	1.3
Feb-05	28.0	36.0	36.0	28.0	36.0	36.0	0.0	0.0	0.0	13.0	17.0	17.0	3.2	4.8	4.8	1.3	1.3	1.3
Mar-05	29.0	37.5	37.5	29.0	37.5	37.5	0.0	0.0	0.0	14.0	18.0	18.0	3.2	4.8	4.8	1.5	1.5	1.5
Apr-05	35.0	42.0	42.0	34.0	42.0	42.0	1.0	0.0	0.0	19.0	25.0	25.0	5.2	7.2	7.2	1.5	1.8	1.8
May-05	33.0	38.0	40.0	32.0	38.0	40.0	1.0	0.0	0.0	17.0	20.0	20.0	4.0	5.2	5.2	1.8	1.8	1.8
Max	67.0	65.0	70.0	65.0	65.0	70.0	4.0	0.0	0.0	40.0	40.0	40.0	10.0	10.0	10.0	3.8	3.8	3.8
Min	26.0	30.0	31.5	25.0	30.0	31.5	0.0	0.0	0.0	12.0	14.0	16.0	3.2	1.8	4.0	0.8	0.3	1.3
Ave	32.1	37.8	39.3	31.4	37.8	39.3	0.8	0.0	0.0	17.0	22.1	21.3	3.9	5.7	5.7	1.8	1.9	1.7

**Table M31.1.7 Monthly Water Quality of Salaulim WTP Analysed by PWD's Laboratory from January 2003 to May 2005 (2/2)**


	Cl <sup>-</sup>			Total Alkalinity as CaCO <sub>3</sub>			SO <sub>4</sub> <sup>-</sup>			Fe <sup>2+</sup>			Mn <sup>2+</sup>			NO <sub>3</sub> <sup>-</sup>			KMnO <sub>4</sub> oxidizability as O <sub>2</sub>		
	Raw	Filtered	Treated	Raw	Filtered	Treated	Raw	Filtered	Treated	Raw	Filtered	Treated	Raw	Filtered	Treated	Raw	Filtered	Treated	Raw	Filtered	Treated
Jan-03	6.0	6.0		12.0	13.0		0.0	0.0		0.05	0.05		0.00	0.00		0.6	0.0		0.2	0.0	
Feb-03	6.0	6.0		13.0	16.0		0.0	0.0		0.05	0.05		0.24	0.00		0.4	0.0		0.2	0.0	
Mar-03	6.0	6.0		16.0	29.0		0.0	0.0		0.06	0.05		0.00	0.00		1.3	0.0		0.2	0.0	
Apr-03	6.0	6.0		21.0	23.0		0.0	0.0		0.30	0.05		0.00	0.00		0.7	0.0		0.2	0.0	
May-03	6.0	6.0		23.0	23.0		0.0	0.0		0.06	0.05		0.00	0.00		0.4	0.0		0.2	0.0	
Jun-03	4.0	4.0		20.0	32.0		0.0	0.0		0.45	0.06		0.00	0.00		0.8	0.0		0.4	0.0	
Jul-03	6.0	6.0		16.0	20.0		0.0	0.0		0.10	0.05		0.00	0.00		0.9	0.0		0.3	0.0	
Aug-03	6.0	6.0		17.0	17.0		0.0	0.0		0.20	0.05		0.00	0.00		0.4	0.0		0.3	0.0	
Sep-03	6	6.0		17.0	20.0		0.0	0.0		0.05	0.05		0.00	0.00		0.8	0.0		0.2	0.0	
Oct-03	6.0	6.0		23.0	25.0		0.0	0.0		0.10	0.05		0.00	0.00		0.9	0.0		0.2	0.0	
Nov-03	6.0	6.0		20.0	23.0		0.0	0.0		0.05	0.05		0.10	0.00		0.4	0.0		0.2	0.0	
Dec-03	6.0	6.0		18.0	24.0		0.0	0.0		0.06	0.05		0.08	0.00		0.8	0.0		0.4	0.0	
Jan-04	6.0	6.0		18.0	26.0		0.0	0.0		0.10	0.05		0.00	0.00		1.9	0.0		0.4	0.0	
Feb-04	6.0	6.0		18.0	22.0		0.0	0.0		0.05	0.05		0.00	0.00		1.5	0.0		0.3	0.0	
Mar-04	6.0	6.0	6.0	20.0	23.0	23.0	0.0	0.0	0.0	0.12	0.05	0.05	0.00	0.00	0.00	1.2	0.0	0.0	0.3	0.0	0.0
Apr-04	6.0	6.0	6.0	21.0	35.0	32.0	0.0	0.0	0.0	0.08	0.05	0.05	0.00	0.00	0.00	1.0	0.0	0.0	0.3	0.0	0.0
May-04	7.0	7.0	9.0	44.0	44.4	44.0	0.0	0.0	0.0	0.60	0.10	0.10	0.00	0.00	0.00	1.4	0.0	0.0	0.6	0.0	0.0
Jun-04	7.0	7.0	7.0	15.0	18.0	18.0	0.0	0.0	0.0	0.06	0.05	0.05	0.00	0.00	0.00	0.6	0.0	0.0	0.2	0.0	0.0
Jul-04	7.0	7.0	7.0	17.0	28.0	28.0	0.0	0.0	0.0	0.30	0.05	0.05	0.12	0.00	0.00	0.8	0.0	0.0	0.4	0.0	0.0
Aug-04	6.0	6.0	7.0	17.0	18.0	18.0	0.0	0.0	0.0	0.20	0.10	0.10	0.00	0.00	0.00	0.5	0.0	0.0	0.3	0.0	0.0
Sep-04	6.0	6.0	7.0	16.0	21.0	21.0	0.0	0.0	0.0	0.06	0.06	0.06	0.00	0.00	0.00	0.4	0.0	0.0	0.2	0.0	0.0
Oct-04	6.0	6.0	6.0	18.0	19.0	19.0	0.0	0.0	0.0	0.06	0.05	0.05	0.00	0.00	0.00	0.0	0.0	0.0	0.0	0.0	0.0
Nov-04	6.0	6.0	7.0	16.0	19.0	19.0	0.0	0.0	0.0	0.06	0.05	0.05	0.10	0.00	0.00	0.2	0.0	0.0	0.0	0.0	0.0
Dec-04	6.0	6.0	6.0	19.0	24.0	25.0	0.0	0.0	0.0	0.06	0.05	0.05	0.00	0.00	0.00	0.0	0.0	0.0	0.2	0.0	0.0
Jan-05	6.0	7.0	8.0	18.0	19.0	19.0	0.0	0.0	0.0	0.40	0.06	0.06	0.00	0.00	0.00	0.0	0.0	0.0	0.0	0.0	0.0
Feb-05	6.0	6.0	6.0	17.0	21.0	21.0	0.0	0.0	0.0	0.06	0.05	0.05	0.00	0.00	0.00	0.6	0.0	0.0	0.3	0.0	0.0
Mar-05	7.0	7.0	7.0	16.0	20.0	20.0	0.0	0.0	0.0	0.10	0.06	0.06	0.00	0.00	0.00	0.4	0.0	0.0	0.2	0.0	0.0
Apr-05	7.0	7.0	8.0	17.0	25.0	25.0	0.0	0.0	0.0	0.10	0.06	0.06	0.12	0.00	0.00	0.5	0.0	0.0	0.3	0.0	0.0
May-05	6.0	8.0	10.0	17.0	18.0	18.0	0.0	0.0	0.0	0.20	0.10	0.10	0.00	0.00	0.00	0.8	0.0	0.0	0.3	0.0	0.0
Max	7.0	8.0	10.0	44.0	44.4	44.0	0.0	0.0	0.0	0.60	0.10	0.10	0.24	0.00	0.00	1.9	0.0	0.0	0.6	0.0	0.0
Min	4.0	4.0	6.0	12.0	13.0	18.0	0.0	0.0	0.0	0.05	0.05	0.05	0.00	0.00	0.00	0.0	0.0	0.0	0.0	0.0	0.0
Ave	6.1	6.2	7.1	18.6	22.9	23.3	0.0	0.0	0.0	0.14	0.06	0.06	0.03	0.00	0.00	0.7	0.0	0.0	0.3	0.0	0.0

	BOD at 27°C and 3days			DO			F <sup>-</sup>			Al <sup>3+</sup>			Plate Count on nutrient agar			MPN of Coliform			MPN of E.Coli.		
	Raw	Filtered	Treated	Raw	Filtered	Treated	Raw	Filtered	Treated	Raw	Filtered	Treated	Raw	Filtered	Treated	Raw	Filtered	Treated	Raw	Filtered	Treated
Jan-03	0.5	0.0					0.0	0.0		0.00	0.00		0.0	0.0		0.0	0.0	0.0	0.0	0.0	0.0
Feb-03	0.5	0.0					0.0	0.0		0.00	0.00		0.0	0.0		0.0	0.0	0.0	0.0	0.0	0.0
Mar-03	0.5	0.0					0.0	0.0		0.00	0.00		86.0	2.0		1,100.0	0.0	0.0	150.0	0.0	0.0
Apr-03	0.5	0.0					0.0	0.0		0.00	0.00		0.0	0.0		0.0	0.0	0.0	0.0	0.0	0.0
May-03	0.5	0.0					0.0	0.0		0.00	0.00		0.0	0.0		0.0	0.0	0.0	0.0	0.0	0.0
Jun-03	1.0	0.0					0.0	0.0		0.00	0.33		0.0	0.0		0.0	0.0	0.0	0.0	0.0	0.0
Jul-03	1.0	0.0					0.0	0.0		0.00	0.21		0.0	0.0		0.0	0.0	0.0	0.0	0.0	0.0
Aug-03	0.5	0.0					0.0	0.0		0.00	0.04		127.0	3.0		150.0	0.0	0.0	93.0	0.0	0.0
Sep-03	0.5	0.0					0.0	0.0		0.00	0.02		140.0	1.0		93.0	0.0	0.0	43.0	0.0	0.0
Oct-03	0.5	0.0		7.1	7.2		0.0	0.0		0.00	0.04		137.0	0.0		460.0	0.0	0.0	240.0	0.0	0.0
Nov-03	0.5	0.0		7.1	7.2		0.0	0.0		0.00	0.04		70.0	28.0	1.0	430.0	0.0	0.0	230.0	0.0	0.0
Dec-03	1.9	0.0		7.2			0.0	0.0		0.00	0.05		82.0	13.0	0.0	460.0	23.0	0.0	460.0	0.0	0.0
Jan-04	1.2	0.0		7.3	7.4		0.0	0.0		0.00	0.00		82.0	13.0	0.0	460.0	23.0	0.0	460.0	0.0	0.0
Feb-04	0.8	0.0		7.3	7.4		0.0	0.0		0.00	0.00		88.0	40.0	0.0	460.0	460.0	0.0	460.0	240.0	0.0
Mar-04	0.8	0.0	0.0	7.2	7.3	7.3	0.0	0.0	0.0	0.00	0.00	0.00	104.0	4.0	2.0	43.0	0.0	0.0	23.0	0.0	0.0
Apr-04	0.6	0.0	0.0	7.2	7.4	7.5	0.0	0.0	0.0	0.00	0.00	0.00	135.0	75.0	2.0	240.0	93.0	0.0	9.0	7.0	0.0
May-04	1.2	0.0	0.0	6.9	7.0	7.2	0.0	0.0	0.0	0.00	0.00	0.00	107.0	67.0	2.0	1,100.0	460.0	0.0	460.0	93.0	0.0
Jun-04	0.6	0.0	0.0	6.9	7.5	7.5	0.0	0.0	0.0	0.00	0.00	0.00	87.0	12.0	1.0	240.0	4.0	0.0	240.0	0.0	0.0
Jul-04	1.1	0.0	0.0	7.1	7.2	7.2	0.0	0.0	0.0	0.00	0.10	0.10	220.0	140.0	3.0	93.0	93.0	0.0	43.0	21.0	0.0
Aug-04	0.5	0.0	0.0	7.0	7.3	7.4	0.0	0.0	0.0	0.00	0.05	0.05	123.0	12.0	0.0	240.0	43.0	0.0	93.0	0.0	0.0
Sep-04	0.5	0.0	0.0	7.0	7.4	7.4	0.0	0.0	0.0	0.00	0.05	0.05	192.0	15.0	0.0	240.0	21.0	0.0	21.0	0.0	0.0
Oct-04	0.0	0.0	0.0	7.2	7.4	7.4	0.0	0.0	0.0	0.00	0.04	0.04	180.0	4.0	0.0	460.0	9.0	0.0	240.0	0.0	0.0
Nov-04	0.0	0.0	0.0	7.1	7.3	7.4	0.0	0.0	0.0	0.00	0.01	0.01	140.0	25.0	2.0	460.0	39.0	0.0	21.0	7.0	0.0
Dec-04	0.5	0.0	0.0	7.5	7.6	7.6	0.0	0.0	0.0	0.00	0.01	0.01	71.0	12.0	2.0	1,100.0	23.0	0.0	240.0	4.0	0.0
Jan-05	0.0	0.0	0.0	7.5	7.6	7.6	0.0	0.0	0.0	0.00	0.01	0.01	88.0	5.0	3.0	93.0	0.0	0.0	28.0	0.0	0.0
Feb-05	0.5	0.0	0.0	7.3	7.5	7.5	0.0	0.0	0.0	0.00	0.00	0.00	45.0	35.0	2.0	93.0	4.0	0.0	0.0	0.0	0.0
Mar-05	0.5	0.0	0.0	7.5	7.8	7.8	0.0	0.0	0.0	0.00	0.00	0.00	112.0	12.0	0.0	93.0	15.0	0.0	23.0	0.0	0.0
Apr-05	0.5	0.0	0.0	7.4	7.6	7.6	0.0	0.0	0.0	0.00	0.00	0.00	178.0	15.0	2.0	460.0	4.0	0.0	240.0	0.0	0.0
May-05	0.6	0.0	0.0	7.0	7.2	7.2	0.0	0.0	0.0	0.00	0.02	0.02	120.0	35.0	0.0	1,100.0	3.0	0.0	23.0	0.0	0.0
Max	1.9	0.0	0.0	7.5	7.8	7.8	0.0	0.0	0.0	0.33	0.10	0.10	220.0	140.0	3.0	1,100.0	460.0	0.0	460.0	240.0	0.0
Min	0.0	0.0	0.0	6.9	7.0	7.2	0.0	0.0	0.0	0.00	0.00	0.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Ave	0.6	0.0	0.0	7.2	7.4	7.4	0.0	0.0	0.0	0.00	0.04	0.02	93.6	19.6	1.2	333.4	45.4	0.0	132.4	12.8	0.0





**Figure M31.1.3 Monthly Water Quality of Salaulim WTP Analysed by PWD's Laboratory from January 2003 to May 2005 (1/2)**




**Figure M31.1.3 Monthly Water Quality of Salaulim WTP Analysed by PWD's Laboratory from January 2003 to May 2005 (2/2)**

**Table M31.1.8 Records on Power Interruption at Salaulim WTP (1/3)**

Year	2003	Ave.	6.1	Max.	95.0	Min.	1.0	Unit: min.				
Date	Jan.	Feb.	Mar.	Apr.	May	Jun.	Jul.	Aug.	Sep.	Oct.	Nov.	Dec.
1			30.0			23.0	81.0	16.0		34.0		
2	1.0			11.0		4.0				15.0	3.0	
3	5.0	5.0	18.0			14.0		4.0		26.0	5.0	
4		9.0								63.6		
5		95.0				2.0				2.0	4.0	
6			27.0		35.0	2.0				3.0		
7	7.0		27.0		6.0			1.0	4.0	23.0	25.0	
8			1.0			17.0	59.0				40.0	
9					12.0		12.0	5.0	4.0	8.0	12.0	
10					1.0	8.0	10.0	16.0		4.0	2.0	
11	12.0			66.0	3.0	14.0					2.0	
12	4.0		15.0	3.0	2.0		20.0		26.0	29.0		
13									9.0	21.0		2.0
14	10.0			2.0		3.0	46.0	2.0	13.0		10.0	2.0
15					25.0					6.0	2.0	
16						8.0	6.0		1.0			2.0
17					2.0	64.2	4.0		7.0	2.0		
18		50.0			3.0	29.0	3.0		7.0	10.0	2.0	
19		18.0			4.0	16.0	31.0		9.0	44.0	9.0	
20		10.0				4.0	2.0			4.0	10.0	
21		23.0		1.0	20.0	27.0			5.0	4.0	1.0	
22				45.0	2.0			7.0	5.0	11.0	9.0	1.2
23				35.0		1.0			2.0	1.0	55.0	2.0
24					5.0	19.0		2.0		11.0		
25	15.0		1.0	12.0	4.0		9.0	4.0		4.0		2.0
26					10.0		12.0	9.0				
27	2.0			17.0			10.0	2.0	5.0			20.0
28				5.0			4.0	17.0	30.0	9.0	13.0	2.0
29		-	15.0						37.0	5.0	8.0	
30		-		22.0					23.0	3.0	6.0	
31		-		-	25.0	-			-	5.0	-	
Total (min./month)	56.0	210.0	134.0	219.0	159.0	255.2	309.0	85.0	187.0	347.6	218.0	33.2
Ave. (min./day)	1.8	7.5	4.3	7.3	5.1	8.5	10.0	2.7	6.2	11.2	7.3	1.1
Max. (min./day)	15.0	95.0	30.0	66.0	35.0	64.2	81.0	17.0	37.0	63.6	55.0	20.0
Min. (min./day)	1.0	5.0	1.0	1.0	1.0	1.0	2.0	1.0	1.0	1.0	1.0	1.2


Note: Average interruption period means the interruption minutes per day per month .



**Table M31.1.8 Records on Power Interruption at Salaulim WTP (2/3)**

Year	2004	Ave.	8.7	Max.	318.6	Min.	0.1	Unit: min.				
Date	Jan.	Feb.	Mar.	Apr.	May	Jun.	Jul.	Aug.	Sep.	Oct.	Nov.	Dec.
1				23.0	2.0	1.3			18.0			
2		4.0		1.0	42.0	7.0						
3		5.0		30.0	14.0			27.0	24.0			
4			3.0	45.0		5.0		95.4		7.0	10.0	
5	15.0		5.0		79.2			17.0				17.0
6	37.0				5.0		51.0	1.0				2.0
7	66.0				2.0			6.0				
8	2.0	5.0		7.0	9.0	26.0		1.0				1.0
9	6.0			10.0		318.6	3.0	23.0		1.0	33.0	
10	60.0				0.1	1.1			66.0	26.0	1.0	16.0
11	4.0				2.0			8.0	3.0	10.0	10.0	
12				1.0		1.0		25.0	2.0			5.0
13			50.0			274.2		7.0	7.0	40.0		
14						183.6			9.0			16.0
15	37.0	3.0	13.0		5.0	73.8	2.0		14.0	25.0		1.0
16		6.0				12.0	50.0	30.0	30.0			
17			3.0			5.0	63.0		30.0		5.0	
18						20.0	7.0	21.0		1.0		
19	10.0			25.0		14.0						
20	1.0	66.0		56.0		17.0		4.0		2.0		
21	1.0	2.0		2.0	4.0	3.0				11.0		
22		2.0		3.0		5.0			3.0			
23	1.0					6.0			5.0	4.0		
24	2.0	3.0	2.0			1.0					75.0	
25	5.0							64.8		2.0		
26							3.0		4.0	15.0		
27			35.0				4.0	11.0	15.0			3.0
28								2.0	2.0		61.8	5.0
29		60.0		18.0	30.0	1.0		17.0	5.0			
30		-			5.0		55.0		2.0			
31		-		-		-	15.0		-		-	
<b>Total (min./month)</b>	247.0	156.0	111.0	221.0	199.3	975.6	253.0	360.2	239.0	144.0	195.8	66.0
<b>Ave. (min./day)</b>	8.0	5.6	3.6	7.4	6.4	32.5	8.2	11.6	8.0	4.6	6.5	2.1
<b>Max. (min./day)</b>	66.0	66.0	50.0	56.0	79.2	318.6	63.0	95.4	66.0	40.0	75.0	17.0
<b>Min. (min./day)</b>	1.0	2.0	2.0	1.0	0.1	1.0	2.0	1.0	2.0	1.0	1.0	1.0

Note: Average interruption period means the interruption minutes per day per month .



**Table M31.1.8 Records on Power Interruption at Salaulim WTP (3/3)**

Year	2005	Ave.	4.8	Max.	124.8	Min.	0.1	Unit: min.				
Date	Jan.	Feb.	Mar.	Apr.	May	Jun.	Jul.	Aug.	Sep.	Oct.	Nov.	Dec.
1			2.0			47.0						
2				15.0								
3												
4												
5		2.0				1.0						
6						9.0						
7	2.0	11.0	5.0		0.3							
8						2.0						
9	12.0	1.0										
10	8.0											
11	7.0				0.7							
12			2.0									
13			9.0		0.2							
14	3.0		40.0		0.2							
15												
16			41.0	11.0	0.2							
17		3.0		4.0	0.3	20.0						
18					0.5	40.0						
19		4.0	2.0		0.5	7.0						
20			14.0	10.0	60.0	7.0						
21			2.0		53.0							
22												
23				69.6	2.0	31.0						
24												
25						4.0						
26												
27			5.0		0.2	50.0						
28					0.2	18.0						
29		-			2.0	124.8						
30		-	55.0		51.0	2.0						
31		-		-	0.1	-			-		-	
<b>Total (min./month)</b>	32.0	21.0	177.0	109.6	171.3	362.8	0.0	0.0	0.0	0.0	0.0	0.0
<b>Ave. (min./day)</b>	1.0	0.8	5.7	3.7	5.5	12.1	0.0	0.0	0.0	0.0	0.0	0.0
<b>Max. (min./day)</b>	12.0	11.0	55.0	69.6	60.0	124.8	0.0	0.0	0.0	0.0	0.0	0.0
<b>Min. (min./day)</b>	2.0	1.0	2.0	4.0	0.1	1.0	0.0	0.0	0.0	0.0	0.0	0.0

Note: Average interruption period means the interruption minutes per day per month .




Table M31.1.9

List of Reservoirs for the Salaulim Water Supply Scheme (1/3)

Series No.	Tap -ping No.	Tapping Main		Name of GLR / OHR / Sump (Name of Location)	GLR / OHR / Sump			Elevation (m)		Supply Area		Remarks
		Dia. (mm)	Material		Type	Capacity (m3)	GL	HWL	LWL	Talhaka	Village Name	
1				CWR (Salaulim WTP)	GLR	3,370	115.15	110.50				Bottom EL of Outlet Chamber=110.0m
2					GLR	3,370	115.15	110.50				
3	0	300	CIP	Xelpem (1990)	GLR	200	83.00				Xelpem(30), Cotarli(29), Mugulil(28)	
4		300	CIP	Sanguem	GLR	200	40.00				Cotarli(29), Sanguem(MI)(50), Costi(25), Uguent(32)	
5		300	CIP	Pontemol (1993)	GLR	800	61.00				Quepem Cacora(MCI)(37)	
6	1	200	ACIP	Malakernem (1990)	GLR	100	76.00				Molcamem(14):2,000persons	
7	2	200	CIP	Zambaulim (1995)	GLR	300	58.00				Rivona(43)(Zambaulim Village)	
8		200	CIP	Rivona (1992)	GLR	200	60.00				Rivona(43):Supply from Kushavari River	Idle
9	3	300	CIP	Shivoi (1992)	GLR	800	70.00				Sirvoil(9)	Idle-Not Accessible
10	7	350	CIP	Veroda (1995)	GLR	800	46.00				Cuncolim(48):from Feb. '06	Idle
11		300	CIP	Velim	GLR	800	42.00				Velim(38)	Idle
12		300	CIP	Balli	Sump	400	15.00				Quepem	w/Pump House
13					GLR	650	115.00				Bali(17), Fatorpa(18), Tiloi(22):7,000persons	
14		300	CIP	Khanaginim	GLR	25	40.00				Naquerim(20):500persons, from Spring	Not Commission
15	10	200	CIP	Baida (1993)	Sump	300	16.00				Chinchinim (CT)(47):from Jan. '06	w/Pump House
16					GLR	300	40.00				Chinchinim (CT)(47):from Jan. '06	
17		150	CIP	Deusa	GLR	100	32.00				Duessua(35)	
18		200	CIP	Sarzora	GLR	300	41.00				Sarzora(31), Cuncolim(48):Mar./Apr. '06	Idle
19	11	250	CIP	Chandor	GLR	150	53.00				Chandor(28), Cavorim(27)	
20	12	250	CIP	St. Jose De Areal	GLR	800	40.00				Sao Jose de Areal(CT)(46), Dicarpaile(26)	
21	14	300	CIP	Curtorim	Sump	100	14.00				Curtorim(20), Macasana(18)	w/Pump House
22					GLR	300	75.00				-ditto-	
23		300	CIP	Curtorim (1990)	GLR	650	65.00				-ditto-	
24				Makazana	GLR	100	40.00				Macasana(18):from Jun. '06	Idle
25		300	CIP	Guirdolim (1990)	GLR	300	58.00				Guirdolim(19):from Jun. '06	Idle
26	15	600	CIP	Borda (1980)	GLR	800	55.00	58.80			Margao(40)	w/Pump House
27					GLR	800	55.00	58.80			-ditto-	
28		600	CIP	Aquem (1990)	GLR	800	63.00	66.80			-ditto-	Idle
29					GLR	800	63.00	66.80			-ditto-	
30		600	CIP	Monte Hill (Aquem) 1990	OHR	150	80.00	107.50			-ditto-	Pumping from Borda
31	18	400	CIP	Monte Hill (1975)	GLR	500	42.50	45.80			-ditto-	
32					GLR	500	42.50	45.80			-ditto-	
33		400	CIP	Monte Hill (2005)	GLR	4,000	44.00	48.00			-ditto-	Sep. '05 in Completion
34		400	CIP	Monte Hill (TB Hospital)	GLR	800	65.00	68.80			-ditto-	from Monte Hill (1975)
35		600	MSP	Gogol (Jan. 2000)	Sump	1,500	53.00	56.00			-ditto-	w/Pump House
36		600	MSP	Margao MBR : Gogol (2000)	GLR	10,000	110.00	114.00			-ditto-	
37		300	CIP	Near MBR : Margao	GLR	800	55.00	58.80			-ditto-	
38		150	CIP	Vasant Nagar : Margao	GLR	150	70.00	73.80			-ditto-	
39		400	CIP	Fatorda (1992)	GLR	800	55.00	58.80			Salceete	
40		400	CIP	Gavli Wada (2004)	Sump	400	26.50	29.20			-ditto-	w/Pump House
41		400	CIP	Dongar Wada (2004)	GLR	800	56.00	59.80			-ditto-	

**Table M31.1.9 List of Reservoirs for the Salaulim Water Supply Scheme (2/3)**

Series No.	Tap -ping No.	Tapping Main		Name of GLR / OHR / Sump (Name of Location)	GLR / OHR / Sump			Supply Area			Remarks
		Di. (mm)	Material		Type	Capacity (m3)	Elevation (m)	Taluka	Village Name		
					GL	HWL	LWL				
42	20	500	CIP	Colva (1980)	GLR	300	42.00		ditto-	Colva(12), Vanelim(13), Seraulim(14), Duncolim(15), Betalbatim(10), Gandaulim(11),	Idle
43				Betalbatim	OHR	150	16.00		ditto-	Betalbatim(10), Gonsuat(9)	
44	21	150	CIP	Damon Raia	GLR	800	62.00	65.80	ditto-	Raia(16)	
45	44	250	CIP	Camurlim (2003)	Sump	400	36.00		ditto-	Raia(16), Camurlim(4), Loutulim(3)	w/Pump House
46	46	250	CIP	Camurlim	GLR	800	52.00		ditto-	Loutulim(3)	w/Pump House
47	47	250	CIP	Loutulim (2000)	Sump	400	36.00		ditto-	Loutulim(3)	
48	48				GLR	300	60.00		ditto-		
49	49	250	CIP		GLR	800	60.00		ditto-		
50	50	150	CIP	Raia (2000)	Sump	400	15.00		ditto-	Raia(16), Rachol(17)	w/Pump House
51	51	150	CIP	Collea Dongor - Raia (1980)	GLR	300	55.00		ditto-		
52	23			Monora Raia (1985)	OHR	300	55.00		ditto-	Raia(16)	Idle
53	53				GLR	150	55.00		ditto-		Idle-Not Accessible
54	24			Nuven(2001)	GLR	800	68.00		ditto-	Nuven(5), Calat(6), Major(7), Utorda(8)	
55	55			Nuven(2005)	Sump	400	28.00		ditto-		w/Pump House
56	28	200	ACP	Cansua (1987)	GLR	300	46.00		ditto-	Nago(1), Verna(2), Gonsuat(9)	
57	57	200	ACP	Curlim (1985)	GLR	300	46.00		ditto-	Mormugao Cortalim(3)	
58	Verma			Verna P.S. (1992)	Sump	1,500	56.00	40.00		Cortalim(3)	w/Pump House
59				Verna MBR (1992)	GLR	10,000	113.00	100.00			
60	31	200	CIP	Upasagar, Sancele (1997)	GLR	300	95.00		Mormugao	Sancoale(CT)(14)	
61		250	CIP	Nagoa (1995)	GLR	800	54.00		Salceete	Nago(1)	
62	37			Dabolim (2000)	GLR	300	52.00		Mormugao	Dabolim(1)	w/Pump House
63				Dabolim (1985)	OHR	150	73.00		ditto-	Dabolim(1)	Idle
64	38	100	CIP	Quelossim (1982)	GLR	300	27.00		ditto-	Cortalim(3), Quelossim(4)	
65		100		Rua Escrao De Maria (1982)	GLR	150	50.00		Salceete	Loutulim(3)	
66				Cortalim (1980)	GLR	300	27.00		Mormugao	Sancoale(CT)(14)	Not Accessible
67		80	CIP	St. Jacino Island (1985)	GLR	25	22.00		ditto-	Cortalim(3)	Not Located / Idle
68		150	CIP	Sancole	GLR	150	50.00		ditto-	Sao Jacinto Island(2)	
69		200	CIP	Head-Land Sada (1992)	GLR	800	55.00		ditto-	Dabolim(1), Sancoale(CT)(14)	Idle
70		200	CIP	Head-Land Sada (2004)	OHR	650	55.00		ditto-		
71		200	CIP	Head-Land Sada (2004)	GLR	800	55.00		ditto-		
72		200	CIP	PHE Qrts, Sada (1982)	GLR	300	53.00		ditto-	Mormugao(MC)(12)-Ward(1)-(5)	w/Pump House
73		250	CIP	Mid-Land Sada : MPT (1980)	OHR	150	53.00		ditto-		w/Pump House
74		200	CIP	Chicalim (2000)	GLR	300	47.00		ditto-		w/Pump House
75	38	200	CIP	Chicalim (1981)	OHR	300	45.00		Mormugao	Chicalim(13), Part of Dabolim(1)	w/Pump House
76		200	CIP		OHR	300	45.00		ditto-		w/Pump House
77		200	CIP		OHR	300	45.00		ditto-		w/Pump House

**Table M31.1.9 List of Reservoirs for the Salaulim Water Supply Scheme (3/3)**

Series No.	Tap -ping No.	Tapping Main		Name of GLR / OHR / Sump (Name of Location)	GLR / OHR / Sump		Elevation (m)			Supply Area		Remarks
		Dia. (mm)	Material		Type	Capacity (m3)	GL	HWL	LWL	Talhaka	Village Name	
78	38	250	CIP	New Vaddem : Sai Baba Temple (1982)	GLR	300	40.00					w/Pump House
79					OHR	150	40.00					
80					GLR	800	40.00				Mormugao(MC)(12): Ward(1)~(5)	w/Pump House
81					GLR	800	35.00					
82		300	CIP	INS Gomantak, Vasco	GLR	800	35.00					from Monte Hill (1975)
83	39	250	CIP	Issoreim (1990)	GLR	300	52.00					
84		250	CIP	Bogmalo (1982)	GLR	150	45.00					
85	44	300	CIP	New Vaddem Bharat Nagar (2000)	GLR	800	47.00				Issoreim(7), Chicolna(8)	Idle
86					OHR	650	47.00					
87	47			Baina (1980)	GLR	300	32.00					
88		250	CIP	Mangor (2005)	GLR	800	31.00					
89		250	CIP	Mangor (1975)	GLR	300	31.00					
90					OHR	650	31.00					w/Pump House
91	48	250	CIP	Gandhi Nagar (1997)	GLR	800	34.00					
				<b>Total</b>		<b>71,990</b>						
				<b>Retention Time</b>			<b>10.8 hrs</b>					

Note: GL=Ground Level, HWL=High Water Level in Reservoir, LWL=Low Water Level in Reservoir, GLR=Ground Level Reservoir, OHR=Over Head Reservoir, Sump=Pumping Suction Well, MBR=Master Balancing Reservoir