



Figure-5.23 General Plan Flood Prevention Project for Badung River

5.4.4 Mati River

(1) Flow Capacity of Current Condition

The result of river flow calculation is shown in Figure-5.24. According to this result, minimum flow capacity of current river flow is estimated from $100\text{m}^3/\text{sec}$ to $130\text{m}^3/\text{sec}$.