

The Democratic Republic of Timor Leste
The Project for the Capacity Building of Road Maintenance in Timor Leste

Final Report

Table of Contents

Location Map
Arterial Roads in Timor Leste
Photographs
Table of Contents
Abbreviations

	Page
Chapter I INTRODUCTION	I-1
1.1 Background of the Project	I-1
1.2 Purpose of the Project	I-1
1.3 Project Overall Goal and Outputs	I-2
1.4 Counterpart Agency	I-2
1.5 The Project Area	I-6
Chapter II PROJECT IMPLEMENTATION	II-1
2.1 Basic information of the Project	II-1
2.2 Project Design Matrix	II-2
2.3 Project Implementation Process	II-2
2.4 Project Input	II-6
2.4.1 Input by Japanese side	II-6
2.4.2 Input by East Timor side	II-8
2.5 Minutes of Meeting for Joint Steering Committee Meeting	II-9
2.6 Achieved Progress of the Project (CBRM)	II-10
Chapter III PROJECT ACTIVITIES	III-1
3.1 First Year Work (Preparatory Work in Japan)	III-1
3.2 First (1 st) Field Work	III-1
3.2.1 Outline of 1 st Field Work	III-1
3.2.2 Explanation and discussion of Inception Report	III-3
3.2.3 Capacity building to DRBFC	III-3
3.2.4 Capacity building to IGE	III-5
3.2.5 Regular meeting, Joint Steering Committee meeting, seminar and website	III-7
3.2.6 Work done by sub-contractor of CBRM	III-9
3.3 Second (2 nd) Year Work, Phase 1 and Interruption of 2 nd Year Work	III-10
3.3.1 Outline	III-10

	<u>Page</u>
3.3.2 Second (2 nd) Field Work, Phase 1	III-10
3.3.3 Interruption of 2 nd Field Work, Phase 1 and 2 nd Home Work, Phase 1	III-11
3.4 Resumption of 2 nd Year Work (2 nd Field Work, Phase 2)	III-13
3.4.1 Resumption of 2 nd Field Work, Phase 2	III-13
3.4.2 Outline of 2 nd Field Work, Phase 2	III-13
3.4.3 Capacity building to DRBFC	III-17
3.4.4 Capacity building to IGE	III-21
3.4.5 Capacity building through the Case Study	III-25
3.4.6 Meetings, seminars/ workshop and website	III-30
3.5 Third (3 rd) Field Work	III-33
3.5.1 Outline of 3 rd Field Work	III-33
3.5.2 Capacity Building to DRBFC.....	III-37
3.5.3 Capacity building to IGE	III-39
3.5.4 Capacity building through the Case Study	III-41
3.5.5 Meetings, seminars/ workshop and website	III-46
Chapter IV ACHIEVEMENT BY THE PROJECT	IV-1
4.1 Achievement regarding Capacity Building to DRBFC	IV-1
4.1.1 Road maintenance inventory	IV-1
4.1.2 Road Maintenance Plan	IV-6
4.1.3 Manual for Reporting System in normal condition	IV-7
4.1.4 Manual for Reporting System in disaster condition	IV-9
4.1.5 Capacity building to staff of DRBFC	IV-10
4.2 Achievement regarding Capacity Building to IGE	IV-14
4.2.1 Outline of capacity building to IGE	IV-14
4.2.2 Technical assistance on equipment management system for IGE	IV-15
4.2.3 Mechanic training	IV-21
4.2.4 Operator training	IV-26
4.3 Capacity Building through the Case Study	IV-31
4.3.1 Selection of work field	IV-31
4.3.2 Preparation of work in DRBFC and IGE	IV-32
4.3.3 Execution of work	IV-34
4.3.4 Completion of work	IV-37
4.3.5 Achievement and evaluation of activities through the Case Study	IV-37
4.4 Products by the Project	IV-39
4.4.1 Road maintenance inventory database	IV-39
4.4.2 Road Maintenance Plan	IV-42
4.4.3 Manual for Reporting System in Normal Condition	IV-42
4.4.4 Manual for Reporting System in Emergency Case by Disaster	IV-43
4.4.5 Equipment management database	IV-43
4.4.6 Training material and textbook	IV-43

	<u>Page</u>
4.4.7 Other reports submitted by CBRM	IV-47
Chapter V PROJECT EVALUATION	V-1
5.1 Summary of Achievements	V-1
5.2 Relevance	V-5
5.3 Effectiveness	V-6
5.4 Efficiency	V-12
5.5 Impact	V-14
5.6 Sustainability	V-16
Chapter VI CONCLUSION, RECOMMENDATIONS AND LESSON LEARNED	VI-1
6.1 Conclusion	VI-1
6.2 Recommendations	VI-1
6.3 Lesson Learned	VI-4