# 7.8 Intersection Plan

# (1) General

Intersections are complex and severe individual locations because of many vehicular movements (through, left-turn and right-turn from each approach road) and pedestrian crossings. On the other hand, the project cost and more resettlement will be required if high-grade and over specification interchange types are applied. The study of intersection types is to control or manage the conflicts in a manner that ensures safety and efficient movement of both vehicles and pedestrians.

# (2) Design Standards

Design standards used are "Standard Specifications for Geometric Design of Urban Roads, March 1992", "Guideline for Geometric Design of Inter-City Roads, September 1997" and "Indonesian Highway Capacity Manual (HCM) 1997" published by DGH/MPW. The items which are not included in the above standards were referred to the Road Geometric Design Standards in Japan and the Policy on Geometric Design of Highways and Streets, AASHTO.

# (3) Design Traffic Volume

Intersection types are planned based on the peak hour traffic volume after 10 years from the opening of the project roads, in accordance with Indonesia road design standards. The opening of service for the F/S routes in this study is assumed to be in 2010, and the estimated future traffic volume in 2020 is adopted for the peak hour traffic volumes for the study.

# (4) Selection of Intersection Types

Selection of intersection types is made based on the number of lanes of crossroads. The crossing with grade separation should be provided for Type I and Type II crossings with partial access control and crossing more than 4 lanes according to the Indonesian road design standards. However, grade separation requires a flyover bridge and it is very costly. Therefore, the traffic signal control type at-grade intersection was given priority as much as it can meet the traffic demand and traffic safety.

Alternative intersection plans are made for major intersection and evaluated on the technical, economical and environmental aspects based on the general evaluation criteria in Table 7.16.

	Evaluat	ion Items	Full Control Interchange	Grade Separation with Access	At-grade Intersection with Signal Control	Roundabout without Signal Control	At-grade Intersection without Signal Control
		Low Volume Traffic (ADT<40000)	Р	Р	G	F	В
	Traffic Capacity	Medium Volume Traffic (ADT4000-60000)	G	F	F	Р	В
Technical		High Volume Traffic (ADT>60000)	VG	G	F	Р	В
Aspects	Stage App	olication	В	Р	F	VG	F
	Safety		VG	G	F	Р	В
	Operation Facilities	and Maintenance of	VG	G	F	G	G
	Others lik	e multiple accesses	-	G	F	F	В
Economical Aspect	Construct	ion Cost	В	Р	G	G	VG
Environmenta	Resettlem	lent	В	Р	G	F	G
l Aspect	Pollution		VG	G	Р	F	F

 Table 7.16
 General Evaluation Criteria for Intersection Type Selection

Note: VG:Very Good, G:Good, F:Fair, P:Poor, B:Bad Source:JICA Study Team

Source.SICA Study Team

#### (5) Locations of Major Intersections

The location map and list of the major intersections on the Trans-Sulawesi Mamminasata Road and Mamminasa Bypass are shown in **Figure 7.13**.



Figure 7.13 Location Map of Intersections and Identification No

# (6) Intersection Plan for Representative Intersections

# 1) TS-2 (Trans-Sulawesi Road / Sultan Alauddin Road)

This intersection is located at the border of Makassar City and Gowa Regency. Three roads (Trans-Sulawesi Road, Sultan Alauddin Road and Syeh Yusuf Road) cross at this intersection. The alternative intersections include signal-controlled at-grade intersection (Type-1), grade-separate intersection (Type-2) and full cloverleaf interchange (Type-3) as illusrated in **Figure 7.14**. The grade-separate intersection type is proposed because of large existing and future traffic volume.



Source of Base photo : Google earth

Figure 7.14 Alternative Intersection Plans for TS-2 IC

#### 2) TS-5 (Trans-Sulawesi Road / Perintis Kemerdekaan Road)

This intersection is a branch point of Trans-Sulawesi Road from Perintis Kemerdekaan Road to Middle Ring Road. The existing Perintis Kemerdekaan Road has a 4-lane road and it is under widening to 6 lanes by DGH. This intersection is surrounded by office buildings and a college campus in the north and an open swamp in the south. The alternative intersections planned are signal-controlled at-grade intersection and two trumpet type interchanges as illustrated in **Figure 7.15**. The at-grade intersection with signal control was proposed as it can take the traffic without saturation by the year 2023 and considering its lower construction cost. Upgrading of this intersection to a grade-separate intersection will be required in the future.



Source of Base photo : Google earth



 MB-1 (Mamminasa Bypass / Hertasning Road) and MB-2 (Mamminasa Bypass / Abdullah Daeng Sirua Road)

Both the intersections MB-1 and MB-2 cross at Hertasning Road at approximately 15 km from the Makassar City center. These are located in a rural area. The planned alternative intersections are signal-controlled at-grade intersection (Type-1) and roundabout (Type-2) as illustrated in **Figure 7.16**. Roundabout type intersection was recommended taking operation and maintenance at the rural area into consideration.



Source of Base photo : Google earth

Figure 7.16Alternative Intersection Plans for MB-1 IC

# 4) Evaluation and Selection of Type of Intersections

Alternative intersections are evaluated and the most advantageous type was selected for each intersection. In the case of evaluated scours are almost same, the most economical type was selected. **Table 7.17** shows the evaluation results.

Main Road	Crossroad	IC No.	Location (Current Area Division)	Full Control Interchange	Grade Separation with Access	At-grade Intersection with Signal Control	Roundabout without Signal Control	At-grade Intersection without Signal Control
q	National Rd. / Mamminasa BP	TS-1	Gowa (Rural)	29.5	31.5	38.0	35.8	24.3
a Roa	National Rd. / Local Rd.	TS-2	Makassar /Gowa (Urban)	30.8	36.0	35.8	34.0	30.0
lasata	Hertasning Rd.	TS-3	Makassar (Urban)	33.3	32.0	33.5	32.3	29.3
mmin	ADS Rd.	TS-4	Makassar (Urban)	31.8	29.5	35.0	27.0	30.0
vesi Ma	Perintis Rd.	TS-5	Makassar (Urban)	33.0	33.0	33.5	32.5	29.3
Sulav	Ir. Sutami Rd.	TS-6	Makassar (Urban)	-	-	-	-	-
rans-	Mamminasa BP	TS-7	Maros (Semi- urban)	29.3	33.0	34.3	33.0	29.5
⊢	Mamminasa BP	TS-8	Maros (Semi- urban)	29.5	31.0	38.0	37.0	30.5
asa s	Hertasning Rd.	MB-1	Gowa (Rural)	30.3	32.0	39.5	40.3	33.5
nmin typas	ADS Rd.	MB-2	Gowa (Rural)	30.3	32.0	39.5	40.3	33.5
Mar B	National Rd.	MB-3	Maros (Urban)	24.5	26.0	37.3	36.3	30.3
Notes:		Selecte	d Type					

 Table 7.17
 Summary of Intersection Type Evaluation and Selection

Notes: Sele Source: JICA Study Team

# 7.9 Bridge Plan

# (1) Number and Length of Bridges

On the routes of the Mamminasa Bypass, Abdullah Daeng Sirua Road, Hertasning Road and Trans-Sulawesi Mamminasata Road, there are a total of 34 bridges and 34 box culverts crossing over rivers or canals as summarized in the following table. A total length of the bridges and the box culverts is 167 m and 1,168 m respectively.

	-						-	
Road Name	L<10m (	Box Culvert)	L=10-10	00m (bridge)	L>100m (	major bridge)	, , , , , , , , , , , , , , , , , , ,	Total
	Number	Length (m)	Number	Length (m)	Number	Length (m)	Number	Length (m)
Mamminasa Bypass	27	109	12	211	2	280	41	600
Trans-Sulawesi Road	3	25	13	46	2	529	18	600
Hertasning Road	1	10	1	20			2	30
A.D.Sirua Road	3	23	4	82			7	105
Total	34	167	30	359	4	809	68	1,335

 Table 7.18
 Bridges and Box-culverts on the F/S Roads

The following four bridges having a length of more than 100 m were categorized as major bridges in the F/S and subjected to a structure scale examination and subjected to preliminary design:

- Bridge No.1-5, Maros Bridge (length 126 m) on Mamminasa Bypass
- Bridge No.1-15, Jeneberang No.1 Bridge (length 154 m) on Mamminasa Bypass
- Bridge No.2-6, Tallo Bridge (length 136 m) on Trans-Sulawesi Mamminasata Road
- BBridge No.2-10, Jeneberang No.2 Bridge (length 393 m) on Trans-Sulawesi Mamminasata Road.

The standard PC I girder is applied for the bridges of 10 - 100 m long. The standard box culverts were used for the structures of less than 10 m long.

# (2) Design Standard

The Indonesian Standard "Bridge Design Code and Manual (BMS 1993)" was applied in bridge design for the F/S. The design loads and materials are followed to this Bridge Design Manual and other Indonesian standards.

The effect of an earthquake on simple structures can be simulated by an equivalent static load as described in Bridge Design Manual. Large, complex or important bridges require a full dynamic analysis. However, the structure type were examined and selected without dynamic analysis in the F/S stage.

## (3) Standard Bridge Cross Section

The following shows standard cross sections for major brides.

# <u>4-Lane Bridge</u>



# 6-Lane Bridge



Source: JICA Study Team

## 8-Lane Bridge



Figure 7.17 Cross Section of Major Bridges

# (4) Major Bridge Plan

#### 1) Site Condition

The following four bridges longer than 100 m were examined for their structure scale by preliminary design. The site conditions for those bridges are shown in Figures 7.18 to 7.21.



Source: JICA Study team on Google Earth Photo Figure 7.18 Maros Bridge on Mamminasa Bypass



Figure 7.19 Jeneberang No.1 Bridge on Mamminasa Bypass



Source: JICA Study team on Google Earth Photo

Figure 7.20 Tallo Bridge on Trans-Sulawesi Mamminasata Road



Figure 7.21 Jeneberang No.2 Bridge on Trans-Sulawesi Mamminasata Road

#### 2) Selection of Structure Type for Major Bridges

**Table 7.19** shows common structure types and applicable span length applicable for the project bridges. The span arrangement and alignment layout are the key elements to determine the superstructure types. The alternative superstructure types considered are Steel I girder, Steel box girder, Steel truss, Steel arch, PC I girder, PC U Girder, PC box girder and PC arch. A comparison study was made for bridge types including aesthetic aspects.



Table 7.19Applicable Span Length by Bridge Type

Source: Bridge Design Manual, Japan Pre-stressed Concrete Contractors Association, Japan Association of Steel Bridge Construction and some modification by the JICA Study Team for application in Indonesia

The major four major bridges studied are crossing rivers. Since there are no bridges planned with an abutment height of less than 5 m, a cantilever abutment (Reverse T type) was selected. The pile vent or a multi-column type should be avoided for piers of major bridges.

Pile foundation was selected because the depth of the bearing stratum is approximately from 10 to 20 m. Bored piles are used for the foundation of major bridges.

3) Alternative Bridge Plans

Alternative bridge plans and concept designs were made for the following four major bridges and evaluated on stability, construction easiness, maintenance, aesthetics and construction costs.

- i) Maros Bridge, Mamminasa Bypass (See **Table 7.20**)
- ii) Jeneberang No.1 Bridge, Mamminasa Bypass (See **Table 7.21**)
- iii) Tallo Bridge, Trans Sulawesi Road (See Table 7.22)
- iv) Jeneberang No.2 Bridge, Trans Sulawesi Road (See Table 7.23)

The Maros Bridge, Tallo Bridge and Jeneberang No.2 Bridge located in the Makassar urban area were subjected to aesthetic comparative study considering the landscape.

Evaluation	Best option	рәриәшшоәәл 10 <sub>N</sub>	Vot recommended from cost saving view point	Recommended as an alternative on aesthetics view point as it is located in urban area
Description	Alternative 1 is PC1 gitder bridge. The muin gitder (dength: 31.5m) can be controlled easily to ensure quality since it is a manufactured structure, this transportation to the site is required. Cantilever butment, single column pier and bored pile foundation are adopted for substructures since local contractors have much experience in the construction of this type. The total construction cost is the least. Cost Estimite 53,30,000 (2) Substructure 5,330,000 (2) Substructure 5,330,000 (2) Substructure 5,330,000 (2) Substructure 2,220,000 Stability ConstructionMantenaned Asthetis cost 10,01 AL 100% 23,1146,000 Stability ConstructionMantenaned Asthetis cost 10,000 Stability Cost Cost Cost Cost Cost Cost Cost Cost	Alternative 2 is PC1 grider bridge with a longer span. The main grider (ength: 42.0m and becompleted easily to ensure quality since it is a manufactured structures that is transportation to the site is required. However, since the grider is long, construction is difficult. As for substructures, the same construction method as that for Alternative 1 is adopted.       Cost Estimate     23,334,000       (1) Superstructure     23,334,000       (2) Substructure     23,321,000       (3) Foundation     127%     29,321,000       Substructure     127%     29,321,000       Substructure     127%     70       10     20     20     20       Substructure     127%     29,321,000       Substructure     127%     29,321,000       Substructure     127%     20,321,000       Substructure     127%     20,321,000       Substructure     127%     20,321,000	Alternative 3 is steel 1 girder bridge. The main girder (length2.2m) is exceller in the quality sepect since it is manufactured at factory, but its transportation to the site is required. Construction materials are to be procured overseas. The total construction cost is higher than Alternative I. Cost Estimate (Thousand Rupah) (1) Superstructure 26,228,000 (2) Subructure 138% 11,954,000 (3) Foundation 138% 201 (3) Cost Mantenade Anthenis 201 (1) Superstructure 201 (1) Superstructure 201 (1) Superstructure 201 (1) Superstructure 201 (2) Subructure 201 (3) Foundation 201 (4)	$\label{eq:construction} Alternative 4 is Niesel-Lables bridge. The main grider (length: 125 4m) is exceeding the manufactured at factory, but its transportation to has the significant of construction materials are to be procured arguined. The total construction cost is the highest. Construction (1) Superstructure 15, 178,000 (1) Substructure 2099% 61, 372,000 TOTAL 2009 10 (1) 20 (1) 3 ($
Cross Section				
Lavout of Maros Bridee (Bridee No.1-5)				
	Alternative I PC 4span I Girder Bridge	Alternative 2 PC 3span I Girder Bridge	Alternative 3 Steel I Girder Bridge	Alternative 4 Vidense Bridge Videlsonse Bridge

# Table 7.20 Comparison of Bridge Types for Maros Bridge



#### Table 7.21 Comparison of Bridge Types for Jeneberang No.1 Bridge

	Layout of Tallo Bridge (Bridge No. 2-6)	oss Section (one side bridge)	Description	Evaluatior
Alternative I PC 4span I Girder Bridge			emative 1 is PC 1 grider bridge. The main grider (length: 0m) can be controlled existive on ensure quality since (1 is mitted. Cantilever aburment, single column piet and bored i uired. Cantilever aburment, single column piet and bored i for abstructures since (local traterors have much experience in the construction of this traterors have much experience in the construction of this superstructure 5, 093, 3000 TAL 160 16 8 6 6 100 17 01 200 / 100 761 161 16 16 10 100 17 01 200 / 100 100 161 16 10 100 17 01 200 / 100 100 161 16 10 100 17 01 200 / 100 100 161 16 10 100 17 01 200 / 100 100 18 00 100 100 100 100 100 100 18 00 100 100 100 100 100 100 100 100 10	Best option
Alternative 2 PC 3span I Girder Bridge		Attended to the second	emative 2 is PC 1 grider bridge with a longer synn. The in grider (lengh: 46.00) can be controlled easily to usynctrion to the site is required. However, since the deris long, construction is difficult. As for substructures, acter is long, construction is difficult. As for substructures, acter is long, construction is difficult. As for substructures, acter is long, construction method as that for Alternative 1 is pred. Superstructure 3,864,000 Substructure 3,864,000 TAL 1255% 27,249,000 TAL 14 8 6 Contaction 1255% 27,249,000 TAL 16 14 8 16 12 12 12 12 10 10 10 10 10 10 10 10 10 10 10 10 10	Not recommended
Alternative 3 PC Box Girder Bridge			emative 4 is PC box grider bridge. The main grider rate span length: 600m is deleted as the cambiever struction method in the site. Since the span length is g, construction is difficult. The total construction cost is highest. highest. highest. Superstructure 5,586,000 Substructure 5,586,000 Substructure 5,586,000 PTAL 15,396, 200 PTAL 15,396, 200 PTAL 200 ability Construction Maintenned Availabelas Cost 100 22,775,000 PTAL 15,000 PTAL 15,000 PTAL 0,000 PTAL	Vot recommended from cost saving view point
Alternative 4 Nielsen-Lohse Bridge			emaily 5 is Niesel-Lohas bridge. The main guider agar. 135 Syn Siesel-Lohas bridge. The annia guider and 135 Syn Sie secellent in the quality aspect since its mitted. Construction materials are to be procured arreas. Since the spun length is long, construction is fedul. The total construction cost is the highest. Superstructure 1,404,000 Substructure 1,404,000 Substructure 229% 49,717,000 Minneaund Anahana Asabris Cost 13 18 10 6 20 20 20 20 20 20 20 20 20 20	Recommended as an alternative on aesthetics view point as it is located in urban area
Source:	JICA Study Team		-	

# Table 7.22 Comparison of Bridge Types for Tallo Bridge



# Table 7.23 Comparison of Bridge Types for Jeneberang No.2 Bridge

## 4) Evaluation of Alternative Bridge Plans

The PC-I girder was selected as the most appropriate type on its economic advantage and construction efficiency in **Table 7.24**. However, it would be possible to select arch bridge by giving priority on aesthetic aspects. Though construction cost of PC arch and steel arch is approximately 200% - 230% higher than PC I girder, their advantage might be justified as a monument of the urban area. The economic indicators (EIRR, NPV, B/C) would not be deteriorated much by bridge type as the project is evaluated as road development project.

# Table 7.24 Evaluation of Alternative Bridge Type for Major Bridges

#### Maros Bridge

#### Bridge Length: 126m

Dhuge Length. 12	-0111							
Area / Alternative	Structure Types	Span	Stability	Construction	Maintenance	Aesthetics	Cost	Total
Urban			20%	20%	10%	20%	30%	100%
Alternative 1	PC I Girder	31.5m x 4	16%	16%	8%	6%	30%	76%
Alternative 2	PC I Girder	42m x 3	16%	14%	8%	8%	24%	70%
Alternative 3	Steel I Girder	42m x 3	18%	15%	6%	8%	20%	67%
Alternative 4	Nielsen Lose (Arch)	126m	18%	10%	6%	20%	13%	67%

#### Jeneberang No. 1 Bridge

Bridge Length: 154m									
Area / Alternative	Structure Types	Span	Stability	Construction	Maintenance	Aesthetics	Cost	Total	
Rural			20%	20%	10%	10%	40%	100%	
Alternative 1	PC I Girder	30.8m x 5	12%	16%	8%	4%	40%	80%	
Alternative 2	PC I Girder	38.5m x 4	12%	14%	8%	5%	39%	78%	
Alternative 3	Steel I Girder	38.5m x 4	14%	14%	6%	5%	29%	68%	
Source: IICA Study	Toom								

Source: JICA Study Team

#### Tallo Bridge

#### Bridge Length: 136m

Area / Alternative	Structure Types	Span	Stability	Construction	Maintenance	Aesthetics	Cost	Total
Urban			20%	20%	10%	20%	30%	100%
Alternative 1	PC I Girder	34m x 4	16%	16%	8%	6%	30%	76%
Alternative 2	PC I Girder	45m+46m+45m	16%	14%	8%	8%	24%	70%
Alternative 3	PC Box Girder	38m+60m+38m	16%	12%	8%	12%	20%	68%
Alternative 4	Nielsen Lose (Arch)	136m	18%	10%	6%	20%	13%	67%

Source: JICA Study Team

#### Jeneberang No. 2 Bridge

#### Bridge Length: 393m

Area / Alternative	Structure Types	Span	Stability	Construction	Maintenance	Aesthetics	Cost	Total
Urban			20%	20%	10%	20%	30%	100%
Alternative 1	PC I Girder	31mx2+33mx10	16%	16%	8%	6%	30%	76%
Alternative 2	PC I Girder	42mx2+44mx7	16%	14%	8%	8%	24%	70%
Alternative 3	Nielsen Lose (Arch)	130mx3	18%	10%	6%	20%	13%	67%

Source: JICA Study Team

#### (5) Minor Bridges

Superstructure types of minor bridges used for the project are box-culverts for less than 10m span, PC hollow slab for span length of 10-16m and PC I Girder for 16 - 35 m span common and economical structure types in Indonesia.

Reversed T type abutment is applied for the substructure and PC pile (tube and/or square) foundation is selected as the depth of the bearing stratum is approximately 10 to 30 m.

# 7.10 Preliminary Design of F/S Roads

# (1) General

The Study Team has designed roadways, intersections, bridges, pavement, drainage and other structures for the F/S roads in accordance with the design standards, road development concept, and route alignments established in Sections 7.4 - 7.9. The engineering design was based on the results of natural condition survey (topography, hydrology and geotechnical conditions) and their analysis. Overall accuracy of preliminary designs is within 10 - 15% allowable for the F/S stage.

The design results are reflected to the Drawings in Volume 2-2 (Preliminary Design Drawings). The road sections which are currently under execution or going to be implemented by 2010 by DGH and/or regional governments were not included in the preliminary design.

# (2) Roadways

The preliminary design of roadways was made for the F/S roads on the topographic survey maps. Topographic survey data, including the photo-mosaic of the road from aerial survey, were calibrated when drawing the horizontal alignments on the topographic maps. Digital Terrain Model was then prepared from the cross section survey point data and contours from ortho-photo after creating 3-dimensional features like existing road, existing ditches, canal, etc. and other road features. Typical cross section templates for the F/S road were created and used for calculating the earthworks and other works quantities.

#### (3) Intersections

Preliminary design of major intersections on the Trans-Sulawesi Mamminasata Road and the Mamminasa Bypass were conducted based on topographic survey, traffic forecasts, intersection capacity analysis by IHCM and road alignment design. The list and type of intersections are as shown in **Table 7.24**.

There are two flyover intersections crossing at Ir Sutami Toll Road and Sultan Alauddin Road. As the flyover of Ir Sutami Toll Road is constructed by the on-going BOT project, it was excluded in this F/S preliminary design.

Dood	ID	Location	Current	No.of	Domonka
Koau	IJ	Location	Station	Legs	Kemarks
	TS-1	Existing National Road	34+840	3	At-grade with signal control
ad		(Sungguminasa – Takalar			
Ro		Road)			
isata	TS-2	Existing National Road	26+200	6	At-grade with flyover for
nina		(Sultan Alauddin Road)			Trans-Sulawesi Road
amr	TS-3	Hertasning Road	23+900	4	At-grade with signal control
si M	TS-4	Abdullah Daeng Sirua	20+325	4	At-grade with signal control
twe		Road			
Sula	TS-5	Perintis Kemerdekaan	19+100	3	At-grade with signal control
ans-		Road			
Τr	TS-6	Ir. Sutami Toll Road	8+700	4	Flyover and at grade under
					on-going BOP project
	TS-7	Mamminasa	0+000	3	At-grade with signal control
		Bypass(North) at national			
ISS		road of Maros-Pangkep			
3ypa	TS-8	Mamminasa	0+000	3	At-grade with signal control
sa E		Bypass(North) at national			
nina		road of Makassar-Maros			
amn	MB-1	Hertasning Road	27+100	4	Roundabout
Μ	MB-2	Abdullah Daeng Sirua	23+350	4	Roundabout
		Road			
	MB-3	National Road	2+630	4	At-grade with signal control

Table 7.25List and Type of Intersections

Source: JICA Study Team

#### (4) Bridges

Preliminary design has been conducted for four bridges having a length of more than 100 m. General view drawings of the structures proposed as optimal are provided in Volume2-2: Preliminary Design Drawings.

#### (5) Pavement

1) Approach for Pavement Design

The pavement is one of the most essential parts of roadway and its cost is substantial. Bina Marga has RDS (Road Design System) as a module of the IRMS. However, as it is under a review, the JICA Study Team designed the pavement for the F/S roads based on "AASHTO Guide for Design of Pavement Structures, 1993".

Both flexible (asphalt concrete) and rigid pavement (Portland cement concrete pavement) are studied and evaluated.

# 2) Design Load

The design ESAL was estimated for a period of 10 years for flexible pavement and for 20 years for rigid pavement. Overloaded condition was not considered much as it should be controlled by weigh bridges located at inlets/outlets of the F/S roads.

3) Construction and Productivity

There would not be much difference in equipment requirements. Asphalt concrete pavement construction requires mixing plant, paver, trucks and compaction equipment while concrete pavement requires concrete mixing plant, trucks and paver. Major materials for the asphalt concrete are asphalt and aggregate. Those for the concrete pavement are cement, aggregate and steel bars. Daily construction productivity would not differ much if a slip form paver is used for the concrete pavement construction as it can produce 700-800 m<sup>2</sup> per day as experienced by the Ir Sutami Toll Road Project. The biggest difference is that asphalt concrete pavement can open to traffic just 1-2 hours after construction while the concrete pavement requires 14 days.

4) Evaluation of Pavement Types

The Study Team made an evaluation on the pavement types taking technical and economic points analyzed in the above into consideration. The life cycle cost of pavement consists of initial investment, periodic maintenance and routine maintenance costs. A turning point of the rigid pavement advantage seems to exist at 20 million CESA or at 7 million CESA for AC. This point is equivalent to 23 cm slab thickness of concrete pavement.

The rigid pavement is also has advantages if the CBR of available subgrade materials (borrowed materials) is less than 8%. The rigid pavement has advantages in the urban area if there are many accessed and traffic signals as flexible pavement is damaged by rutting, shoving and/or spilled oil by stop-start action of vehicles. The Study Team recommended the application of the flexible and rigid pavements for the F/S roads as shown in **Table 7.26**. Rigid pavement is recommended for the Maros-Jl.Ir.Sutami section and the Middle Ring Road section of the Trans-Sulawesi Mamminasata Road.

# Table 7.26Design Condition and Pavement Types for F/S Roads

Road Link		Section	Location	Cut or Fill	Subgrade	Design CE	ESA (10^ <sup>6</sup> )	Type of F	Pavement
					Strength	10 years	20 years	Flexible	Rigid
					(CBR)	period	period	Pavement	Pavement
Trans-Sulawesi	Α	Maros-JI.Ir.Sutami IC	Urban	Cut*/ Fill	8%		34.0		0
Mamminacata	В	Middle Ring	Urban	Fill	6%		21.0		0
Deed	С	Middle Ring Access	Urban	Fill	8%	9.0		0	
Road	D	Boka-Takalar	Semi-urban	Fill	8%	4.0		0	
Mamminasa	Α	North Section	Semi-urban	Fill	8%	4.0		0	
Durana	В	Middle Section	Urban	Cut*/ Fill	8%	4.0		0	
Буразз	С	South Section	Semi-urban	Fill	8%	4.0		0	
JI. Hertasning		Gowa Section	Semi-urban	Fill	8%	4.0		0	
JI.Abdullah Daeng	Α	Makkassar City	Urban	Cut*/ Fill	8%	4.0		0	
Sirua Road	R	Maroc/Gowa Soction	Somi urbon	Cill	Q0/	4.0		0	

Note: \* improvement of subgrade to CBR 8% with replacing the top of subgrade for cur section with selected materials. Source: JICA Study Team

5) Pavement Thickness Design

Table 7.27 summarizes the pavement structures for the F/S roads.

Road Link		Section		Sura	afce		Base	e and Sub	base	Sub-
			AC (W)	AC (B)	AC	PCC	Class A	Class B	SCB	grade
					(base)					CBR
Trans-Sulawesi	Α	Maros-JI.Ir.Sutami IC				26		20	10	8%
Mamminasata	В	Middle Ring				24		20	10	6%
Road	С	Middle Ring Access	4	4	5		20	30		8%
	D	Boka-Takalar	4	6			20	30		8%
Mamminasa	Α	North Section	4	6			20	30		8%
Bypass	В	Middle Section	4	6			20	30		8%
51	С	South Section	4	6			20	30		8%
JI. Hertasning		Gowa Section	4	6			20	30		8%
JI.Abdullah Daeng	А	Makkassar City	4	6			20	30		8%
Sirua Road	В	Maros/Gowa Section	4	6			20	30		8%

 Table 7.27
 Summary of Pavement Thickness for F/S roads

Source: JICA Study Team

#### (6) Drainage and Other Structures

#### 1) Drainage Design

Drainage design along the F/S roads was carried out based on the design run off from the adjacent areas. According to the drainage design standard of Indonesia, the design period for culverts along the arterial road is 10 years and 5 years for roadside ditches.

Figures 7.22 and 7.23 show standard cross sections of road side ditch and drainage pipe and catch pit.



Figure 7.22 Standard Cross Section of Road Side Ditch



Figure 7.23 Standard Cross of Drainage Pipe and Catch Pit

#### 2) Soft Ground Countermeasure Structures

A 470m-long deep soft ground is located in the Tallo swamp area at the entrance of Middle Ring Road from Jl. Perintis Kemerdekaan. RC slab on PC-piles is recommended as a soft ground countermeasure as illustrated in **Figure 7.24**.





3) Retaining Wall (Reinforced Earth Wall)

Reinforced earth retaining walls was planned at the flyover section between the Middle Ring Road/Jl. Sultan Alaudin intersection and Jeneberang River Bridge to properly arrange the vertical alignment and minimize resettlement.

#### (7) Miscellaneous

1) Grade Separated Pedestrian Crossing Facilities

Pedestrian bridges and box culverts are planned for safe pedestrian crossings. These are located at heavily traffic intersections near public facilities such as hospital, school and mosque. The box culverts are planned on embankment sections as alternative of the pedestrian bridge. The gentle access slopes will be planned for the pedestrian bridges for convenience to disabled peoples, senior citizens and cyclists.

2) Traffic Safety Facilities (Street Light, Markings and Road Signs)

Street light are installed at intersections and along urban road sections of the F/S roads. Location of the street light installation will be on the median, and the twin bulb type is recommended.

Road markings and traffic signs are deigned in compliance with the Indonesian standard and site conditions.

# 7.11 Construction Plan

#### (1) General

The construction methods widely used at the project area are adapted while paying attention to quality, period, cost, environmental influence and safety.

**Table 7.28** shows major work items and estimated quantities by the F/S road based on the preliminary design.

Item	Unit	Mamminasa Bypass	Trans Sulawesi	Hertasning Road	A.D. Sirua	Total
Mortared Stonework	m3	184,721	154,978	13,719	44,865	398,283
Common Excavation	m3	1,026,978	376,227	60,212	671,719	2,135,136
Common Embankment	m3	2,999,660	961,307	178,096	773,379	4,912,442
Selected Embankment	m3	18,469	25,447	892	3,814	48,622
Aggregate Base Class A	m3	149,737	91,640	14,984	44,146	300,507
Aggregate Base Class B	m3	233,357	193,751	23,352	68,798	519,258
Cement Treated Sub Base	m3	0	22,277	0	0	22,277
Asphaltic Concrete-Wearing Course (3-5cm)	m2	1,479,056	954,207	146,910	434,790	3,014,963
Asphaltic Concrete-Binder Course	m3	0	23,885	13,719	0	37,604
Asphaltic Concrete-Base Course	m3	0	15,036	6,624	0	21,660
Portland Cement Concrete Pavement	m3	0	62,655	0	0	62,655
Structural Concrete	m3	54,320	73,453	4,421	2,481	134,675
Precast Unit Type I Girder (16-35m)	nos	416	458	11	18	903
Reinforcing Steel	ton	2,296	3,032	154	268	5,750

Table 7.28Major Construction Quantities

# (2) **Procurement Plan**

The design and construction plans were made to use the construction materials available in or vicinity of the project areas as much as possible. Coarse and fine aggregate (sand) are available from the upstream of Bili0bili Dam. Borrow materials for embankment are also available along or vicinity of the F/S roads.

Steel materials are mostly brought from Surabaya. Cement is available from two cement producers (Bosowa Cement and Tonasa Cement) located between Maros and Pangkajene.

# (3) Construction Procedures

The project is either the existing road widening or new construction. Major works are earth works for widening, drainage, bridges, pavement, and countermeasures against soft ground and road facilities. The common procedures used in the project area or Indonesia will be used.

# 7.12 Road Development Methods in Harmony with Urban Development

# (1) Necessity of Applying Urban Development System for Road Development

The F/S and Pre-F/S roads were routed or aligned meandering through urbanized areas to avoid resettlement. However, some part of the roads needs to pass through the densely built-up areas. To solve land acquisition and resettlement conflict, urban development system could be applied in the course of road development so as to ease the frictions between road development (new or widening). A plan could be made to arrange (or adjust) the existing plots, buildings and infrastructure which would lead to benefiting both sides. The urban development system will contribute to a wider range of road routing alternatives and leading to effective and efficient urban road network establishment.

# (2) Possible Frictions between Road Development and Urban Settlements

For optimistic road routes selection for part of Trans-Sulawesi Road, Outer Ring Road, Abdullah Daeng Road and Mamminasata Bypass, there are some areas where frictions with the existing urban built-up areas may take place. One of the methods avoiding these frictions would be application of land readjustment system for the urban development areas.

#### (3) Land Readjustment System for Road Development Method

The land readjustment system (LR system), which is basically defined as urban area-wide development system providing urban serviced land, has been considered to be one of the most effective systems for developing road network including arterial, collector and local roads. Because its system is designed not to evict the landholders and leaseholders from the project site so as to minimize the friction between road development and human settlement. The LR system is classified into the following 3 types:

- Area-wide Land Readjustment

- Roadside-LR Type Road Development
- Roadside-Improvement Road Development

The first one, "Area-wide Land Readjustment" is a LR full scale system to develop urban areas covering considerably a wider range of area, say 10 to several hundreds hectares, comprising urban land development and infrastructure. The second and third ones are systems more specified to arterial road development. The project areas are correspondingly limited to smaller areas where the arterial roads are planned to pass through. While "Roadside-LR type Road Development" focuses on some sections of arterial road belts, "Roadside-Improvement Road Development" covers land plots influenced by the arterial road construction.

# (4) Indonesian Context and Sulawesi

"Land Readjustment system" or "Land consolidation system (K/T: Konsolidasi Tanah)" in Indonesia version, has been established and a number of projects have been implemented using this system throughout the country under the authority or responsibility of land administration, especially the National Land Agency (BPN). It might be possible to apply the existing LR system with some modification to secure the ROW and agreement of the affected communities for the projects to be implemented in the medium-long term.

# 8 ENVIRONMENTAL CONSIDERATIONS

# 8.1 Basic Approaches for Environmental Considerations

Both the Indonesian AMDAL (EIA) regulations and the JICA Guidelines for Environmental and Social Considerations have been applied for the environmental considerations studies for the F/S roads. IEE has been applied for the evaluation of the alternative routes and development concepts to select the most appropriate plan of the F/S roads. On the other hand, EIA is a more in-depth environmental impact survey based on the selection of the most appropriate route by using the IEE-level evaluation in terms of engineering, economic and environmental aspects.

# 8.2 Scope of the Study for EIA

The EIAs have been conducted for the selected routes as the best or the most practical ones through the IEEs. The EIAs for the F/S roads are classified into two groups: the 1<sup>st</sup> group is the Trans-Sulawesi Road Mamminasata Section, the national road or proposed national road with the highest priority, and the other group is the Mamminasa Bypass, Hertasning Road and Abdullah Daeng Sirua Road as shown in **Table 8.1**. The EIA report has been prepared for each group.

Table 0.1 Of oupling of 175 K	loaus IVI LIA
Road Name	Group
(1) Trans-Sulawesi Road Mamminasata Section	Group 1
(1) Mamminasa Bypass	
(2) Hertasning Road	Group 2
(3) Abdullah Daeng Sirua Road	

Table 8.1Grouping of F/S Roads for EIA

#### 8.3 Study Areas

The Study areas cover Kabupaten Maros, Kabupaten Gowa, Kabupaten Takalar and Makassar City in South Sulawesi Province. **Table 8.2** shows the location of the Study areas in the regencies concerned.

No.	FS and	d Pre-FS Road	Regency (Kota / Kabupaten)						
			Makassar	Maros	Gowa	Takalar			
1	Mamminasa E	Bypass		0	0	0			
2	Trans- Sulawesi	Maros-Middle Ring Road IC (Jl. Perintis)	0	0					
	Mamminasata	Middle Ring Road	0						
	(Total Length:	Middle Ring Road	0		0				
	58 km)	Access	_		_				
		Middle Ring Road			0	0			
		Access - Takalar			ũ	÷			
3	Hertasning Roa	ad	Works		0				
	_		Completed		0				
4	Abdullah Daen	ig Sirua Road	0	0	0				
5	Outer Ring Roa	ad	0	0	0				

Table 8.2Locations of Study Areas

Note: O The regency where the F/S roads pass through.

# 8.4 Results of EIA (AMDAL) Studies

The draft of the AMDAL Final Report (ANDAL, RKL and RPL) for the Group 1 project was presented and discussed in the AMDAL Committee/AMDAL Appraisal Technical Team Meeting on August 20<sup>th</sup>, 2007. The approval of those final AMDAL documents was stipulated by the Decree of Head of Bappedalda South Sulawesi Province No.660/746/II/Bapedalda, dated on September 28<sup>th</sup>, 2007.

On the other hand, the draft of the AMDAL TOR for the Group 2 project was presented and discussed in the AMDAL Committee/AMDAL Appraisal Technical Team Meeting on November 27<sup>th</sup>, 2007. The approval of those final AMDAL documents was stipulated by the degree of Head of Bappedalda South Sulawesi dated on December 7<sup>th</sup> 2007.

# 8.5 Results of EIA Studies (Trans-Sulawesi Road Mamminasata Section)

#### a) **Pre-construction Stage**

The major impact during the pre-construction stage is the land acquisition and resettlement required for the right of way of the planned road development. The estimated number of the PAPs for the resettlement is 2723 which is composed of 1115 houses, 1483 small shops and 125 public buildings alongside the planned road, as shown in Table 8.3. On the other hand, the area required for the land acquisition is estimated at 1.19 square km. The number is subject to change as a result of the final designing of the road.

	House (No.)	Shop (No.)	Public Building (No.)	Total (No.)	
	Maros - JI. Sutami IC (Maros Section)	283	905	40	1228
Section A	Maros - JI. Sutami IC (Makassar Section)	37	178	27	242
	Perintis Road	0	0	0	0
Section B		92	16	2	110
Section C		42	10	2	54
Section D		661	374	54	1089
Total		1115	1483	125	2723

Table 8.3	<b>Estimated Number of PAPs</b>
(Trans-Sulawe	esi Road Mamminasata Section)

It seems that the impacts on the natural environment in the pre-construction stage are almost nothing. However, it is important to sufficiently consider the construction plan, schedule and mitigation measures in this stage.

# b) Construction Stage

# 1) Air Pollution

As the number of construction machines and conveyance trucks and vehicles are limited, it seems that the impacts on the air quality are relatively small compared with the present condition. However, as the construction is mainly implemented during dry season, the countermeasures, sprinkling water, cleaning of road and so on are critical to reduce the dust and TSP.

# 2) Noise Level

Noise of the construction machines and vehicles can be reduced by the regular maintenance and efficiently scheduled operation. The noise around the construction areas should be monitored so that countermeasures can be taken timely. For example, the noise impact could be reduced by a proper schedule of the operating hours of construction machines, especially near the hospitals, schools and mosques.

# 3) Water Pollution

The road construction will increase TSS in the near-by river bodies. However, it can be minimized by installing temporary sedimentation ponds at an early stage of the construction. Construction of bridge piers in river needs to adopt the steel sheet pile method or other similar methods in order to avoid turbid water. It is also important to enforce regular monitoring to evaluate the conditions against the river water standard.

# 4) Fauna and Flora

The endemic and protected species of fauna and flora are not mentioned in/around project site on the previous investigation reports. Only common species of fauna and flora are confirmed, and the precious diversity of biota is not discovered too.

If some unique species and/or other precious kinds to be conserved are found during construction and post-construction phase, it is necessary to take the proper measures for fauna and flora, i.e. limited protection zone, bedded in other place etc.

# c) Post-Construction

# 1) Air Pollution

The forecasted air quality data is not exceeded the Environmental Standard except TSP. It is considered that the TSP can be controlled by spraying water, road side plantation, cleaning of road and maintenance of pavement.

It seems that the air quality in future will be not deteriorated so seriously comparing with Environmental Standard by the regulation of exhaust gas, reduction of traffic jam and proper road maintenance etc.

## 2) Noise Level

After the completion of the project, noise will be caused by the operating vehicles on the road. In the future, as it is guessed that the traffic density will be increased certainly, countermeasures for hospital and schools along the target streets are necessary to be planned the protection against traffic noise impact.

# 3) Water Quality

During the operation phase, it is judged that there is no cause of wastewater discharge from target road.

# 8.6 Results of EIA Studies (Mamminasa Bypass, Hertasning and Abdullah Daeng Sirua Road)

# a) **Pre-construction Stage**

The major impact during the pre-construction stage is the land acquisition and resettlement required for the right of way of the planned road development. The estimated number of the PAPs to be resettled is shown as **Table 8.4**. On the other hand, the area required for the land acquisition is estimated at 1.895 square km. The numbers are subject to change as a result of the final designing of the roads.

(Maminassa Bypass, Hertasning Road, and Abdullah Sirua Road)													
Name of Roads	House (No.)	Shop (No.)	Public Building (No.)	Total (No.)									
Maminassa Bypass	56	9	0	65									
Hertasning Road	283	25	8	316									
Abdullah Daeng Sirua Road	205	63	8	276									
Total	544	97	16	657									

Table 8.4	Estimated Number of PAPs
Aaminassa Bypass.	Hertasning Road, and Abdullah Sirua Road)

The impacts for natural environment in the pre-construction phase are almost nothing in the same manner as Trans-Sulawesi Road Mamminasata Section.

#### b) Construction Stage

The impacts and evaluations for natural environment during the construction phase also are almost same as Trans-Sulawesi Road Mamminasata Section.

#### c) Post-Construction Stage

# 1) Air Pollution

All air quality data do not exceed the Environmental Standard, but total suspended particulate (TSP) and PM10 are relatively high. It is considered that the TSP and PM10 can be controlled

by spraying water, road side plantation, cleaning of road and maintenance of pavement.

# 2) Noise Level

The peak noise levels of Mamminasa Bypass, Hertasning Road and Abdullah Daeng Sirua Road exceed Environmental Standard (70 dB(A)) in commercial and service area.

# 3) Water Quality

During the operation phase, it is judged that there is no cause of wastewater discharge from the planned road.

# 8.7 Mitigation Measures and Monitoring

Effective environmental management during pre-construction and construction requires the establishment of effective institutional arrangements for the implementation of the Environmental Management Plan (RKL) as well as the proper Environmental Monitoring Plan (RPL). The RKL has been prepared to deal with the following mitigation measures.

Pollution concerning this project are considered such as air pollution, noise, vibration and water pollution that directly caused by construction activities. In any case, the proper troubleshooting is essential to go forward with construction and operation favorably. For the operation phase, air pollution and noise level caused by the vehicles needs to be evaluated. The air quality and noise level do not deteriorate simply and immediately at the time of increasing the traffic density as main cause of air pollution and noise. Natural impacts caused by this project are estimated such as terrestrial biota (fauna and flora), aquatic biota (fish and aquatic plant) in and around project site. Landscape is not so significant for construction activities. The Environmental Monitoring Plan (RPL) has been also prepared to respond to these mitigation measures.

Environmental Impacts	Construction phase	Post-Construction phase
Air Pollution	-Sprinkling water along access road	-Sprinkling water along roads
	-Washing tires of trucks and construction	-Road cleaning
	machines	-Reducing vehicles speed
	-Using cover sheets for trucks	-Maintenance of pavement
	-Regular maintenance	-Roadside plantation
	-Efficient operation schedule	-Environmental buffer zone
	-Using good quality fuel	
Noise	-Reducing vehicles speed	-Reducing vehicles speed
	(especially nearby residential area)	(especially nearby residential area)
	-Regular maintenance	-Maintenance of pavement
	-Efficient operation schedule	-Roadside plantation
	•	-Environmental buffer zone
Vibration	-Reducing vehicles speed	-Reducing vehicles speed
	(especially nearby residential area)	(especially nearby residential area)
	-Regular maintenance	-Maintenance of pavement
	-Efficient operation schedule	-Roadside plantation
		-Environmental buffer zone

 Table 8.5
 Outline of Mitigation Measures

Water Pollution	<ul> <li>-Considering to set up temporary sediment pond</li> <li>-Adopting the sheet pile method and so on for the construction</li> <li>-Prohibiting disposal of oil and grease, dumping of garbage</li> <li>-Setting up sewerage system for labor camp</li> </ul>	No source of water pollution
	-Separate collection of litter and garbage in labor camp -Managing garbage disposal	
Terrestrial Biota	<ul> <li>-No endemic and protected species of fauna and flora (excluding the birds)</li> <li><if and="" endemic="" found="" or="" protected="" species=""></if></li> <li>-Confirmation of existence of species</li> <li>-Report to public authorities</li> <li>-Implementation of removing and transplantation plan</li> <li>-Effective conservation and protection program</li> </ul>	Not significant impacts of fauna and flora
Aquatic Biota	<ul> <li>-No endemic and protected species of fauna and flora</li> <li><if and="" endemic="" found="" or="" protected="" species=""></if></li> <li>-Confirmation of existence of species</li> <li>-Report to public authorities</li> <li>-Implementation of removing and transplantation plan</li> <li>-Effective conservation and protection program</li> </ul>	Not significant impacts of aquatic fauna and flora
Landscape	<ul> <li>-Green planting along the access road</li> <li>-Proper maintenance for trees and plant along the access road (adopt system etc.)</li> <li>-Encouragement to the green plantation for surrounding</li> </ul>	<ul> <li>Proper maintenance for trees and plants along the road (adopt system etc.)</li> <li>Encouragement of the green plantation for surrounding</li> </ul>

Regarding the Mamminasa Bypass, Hertasning and Abdullah Daeng Sirua Roads, the mitigation measures against pollution factors are almost same as Trans-Sulawesi Road Mamminasata Section. On the other hand, almost of project area is cultivation land for paddy, vegetables and corn etc. But some parts of the project road area are remaining as copses, so it cannot be denied there is no possibility of natural habitat of endemic and protected fauna and flora. Therefore, if some unique species and/or other precious kinds to be conserved are found, it is necessary to take the proper measures, i.e. limited protection zone, bedded in other place etc.

Moreover, there are many fruit trees around the houses and in the project area. It is expected that as many fruits trees as possible are protected from the project. Because of these fruits trees are resource of money income for surrounding residents. It is very effective for eco-friendly road project to design the buffer zone including some existing copses.

#### 8.8 Implementation of Public Consultations

In accordance with the regulations of the AMDAL consultation procedures, a series of public consultations including the following meetings have been held. The 3<sup>rd</sup> meeting for each project was held in response to the special requirement by the JICA Guidelines for Environmental and Social Considerations.

No.	Schedule	No. of Participans	Participants					
Trans S	ulawesi Mamminasata Ro	ad Section						
1	April 2-9, 2007 249 Community, representatives of related villages, related institutions							
2	May 8, 2007	51	Technical Team and Committee members					
3	June 7, 2007	68	Related institutions and communities					
4	August 20, 2007	51	Technical Team and Committee members					
Mammii	nasa Bypass, Hertasning	and Abdullah D	Daeng Sirua Road					
1	May 26 – June 7 2007	245	Community, representatives of related villages, related institutions					
2	September 3, 2007	45	Technical Team and Committee members					
3	September 11, 2007	112	Related institutions and communities					
4	November 27, 2007	50	Technical Team and Committee members					

# Table 8.6 Implementation of Public Consultations



Figure 8.1 Procedure for Public Consultations

# 8.9 **Preparation for LARAP Policy Framework**

A Land Acquisition and Resettlement Action Plan (LARAP) is a document required for any project which results in the physical resettlement of people, and it must specify the procedures and actions it should take in order to properly resettle and compensate PAPs and communities. According to the basic concept of the JICA guidelines, a LARAP is required to ensure that their incomes and living standards of PAPs should be restored to at least pre-project levels and are not worse off than they would have been without the project. More specifically, a LARAP should be prepared as a detailed plan for mitigating the land acquisition impacts in an attempt:

- to ensure that the social and economic livelihood of PAPs is recovered at least the pre-project level;
- to provide policy and procedural guidelines for the acquisition of land and other assets, compensation, and resettlement;
- to identify households that will be adversely affected by the Project, where they are located, what compensation and related alleviating measures are to be provided and how and when these measures will be implemented; and
- to provide a plan on for the community participation of the PAPs could be involved in the various stages of the project, including the implementation of the RAP

Since the full-scale detailed LARAP for the Trans-Sulawesi Mamminasa Section will be formulated after the feasibility study, apart from the EIA reports, in an attempt to mitigate the negative impacts by the land acquisition and resettlement, the policy framework for the LARAP was formulated. In case of formulating the final full-scale LARAP, the following contents should be included as the full-scale LARAP.

- Results of Socio-economic Survey
- Outline of Land Acquisition and Compensation Package
- Institutional Set-up for LAC (Land Acquisition Committee)
- Budgetary Arrangement
- Public Consultations
- Grievance Mechanizm
- Monitoring and Evaluation

The required acquisition for the land and structures based on the results of the baseline survey of the LARAP policy framework are worked out as follows.

Section		Length Necessary Road (km) Width (m)		House (No.)	Shop (No.)	Public Building (No.)	Total (No.)
Section A	Maros - Jl. Sutami IC (Maros Section)	4	12	283	905	40	1228
	Maros - Jl. Sutami IC (Makassar Section)	4	12	37	178	27	242
	Perintis Road	12	0	0	0	0	0
Section B		7	42	92	16	2	110
Section C		9	40	42	10	2	54
Section D		22	20	661	374	54	1089
Total		58		1115	1483	125	2723

# Table 8.7 Estimated Required Land Acquisition and structures compensation for Trans-Sulawesi Mamminasa Section

The section of the Perintis Road is the on-going project of the Indonesian Government, and, therefore, this section is not included in the Trans-Sulawesi Road Project. As a result, the costs for the land acquisition and resettlement required for the Perintis Road would not be included in the project cost of the Trans-Sulawesi Road Project.

The difference of the compensation unit price between the public buildings and houses/stores is derived from the locations of those facilities. (The public buildings are normally located in the center of the towns.) In addition to the compensation for these properties, the compensation for the loss of business opportunities during the resettlement or relocation should be included in the final version of the LARAP in accordance with the compensation policies of the Indonesian Government.

The compensation package includes a wide range of compensation measures like cash compensation and institutional support provided to eligible PAPs. Major compensation packages include:

- Loss of land;
- Loss of structures;
- Loss of productive trees; and
- Loss of commune and public assets
- Allowances for socially vulnerable households

The amount of compensation for the land is determined based on the combination of land price for tax purposes (NJOP) and market price. According to the Regulation of Agrarian State Minister/Head of Land Agency No 1/1994 article 17, compensation for certificated land will be 100% of the agreement price, while compensation for non certificated land will be 90% of the agreement price.

The most important point on compensation and entitlement policies for PAPs under is the comprehensive and complete application of the concept of "Replacement Cost".

"Replacement Cost" is defined that it is an amount needed for obtaining or replacing acquired land or property with similar land or property with equivalent or better productive capacity at current market price/value without deduction of any salvage or depreciation and take no account of the influence by development project on the value of the acquired land or property, plus the cost of transferring or registering the rights to the new land or property.

# 9. COST ESTIMATE AND PROJECT EVALUATION

## 9.1 Cost Estimate

#### (1) Composition of Project Cost

The construction cost was estimated based on the result of the preliminary engineering design, quantities of major work items and assumptions on the percentages of overhead and profit of the contractor and physical contingency.

The components of the project cost are shown in **Figure 9.1**.



Figure 9.1 Project Cost Component

#### (2) Conditions of Cost Estimate

Cost estimate was made based on the following conditions:

- i) Time of cost estimate: May 2007
- ii) Foreign currency: US dollar
- iii) Exchange rate: 1 US dollar = Rp. 9,322 (Bank of Indonesia, 16 May 2007)
- iv) Taxes: Not included for the economic evaluation but included in the project implementation plan as a part of the project cost.

Construction unit prices applied to the cost estimate were set based on the standard unit prices in South Sulawesi Province (Harga Satuan Pokok Kegiatan (HSPK), 2006) and also referring to the contract unit prices in the past and on-going projects.

# (3) **Project Cost Estimation**

The project cost was estimated by project and sub-section established in the implementation planning taking contract packaging or stage into account as illustrated in **Figure 9.2**.



Figure 9.2 Sub-Sections of the Project Road for Cost Estimation

# (4) Maintenance Cost

Road maintenance activities are divided into routine maintenance and periodic maintenance. The routine maintenance includes inspection and patrol, cleaning of road surface/drainage facilities, trimming/cutting of trees/grass, pothole patching and crack sealing and repairs of road facilities. The periodic maintenance includes overlay for AC pavement and partial reconstruction. Those costs are estimated and reflected to economic evaluation.

# (5) Cost Estimate for Implementation Plan

# 1) Mamminasa Bypass

Mamminasa Bypass was divided into four (4) sub-sections taking the appropriate construction timing into consideration. The project cost and its disbursement was estimated by sub-section set out in the above and distributed in **Table 9.1**.

	Itom	Estimated Amount	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
	item	(M. Rp.)		1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
1. M	amminasa Bypass	49.1 km																		
	Maros Bynass Section (North)	5.0 km																		
	Land Acquisition and	0.0									20%	40%	40%							
	Compensation									-		2004	2594	2504						
	Detailed Design and Supervision Services											30%	35%	35%						
	Construction												50%	50%						
	Administraition										25%	25%	25%	25%						
	Maintenance Routine																			
	Maintananca Quarlay nar 5 Vaare																			_
	Wannenance Overlay per 5 Tears																			
	Maros Bypass Section (North)										_									
	Land Acquisition and Compensation	10,763									2,153	4,305	4,305							
	Detailed Design and Supervision	6,128										1,838	2,145	2,145						
	Construction	87,543											43,771	43.771						
	Administraition	1,751									438	438	438	438						
	Maintenance Routine	1,233													206	206	206	206	206	206
	Maintenance Overlay per 5 Years	4,112																	4,112	
	Total	111,529									2,590	6,581	50,659	46,354	206	206	206	206	4,317	206
	Man Carlo Contra	100%			1						2.3%	5.9%	45.4%	41.6%	0.2%	0.2%	0.2%	0.2%	3.9%	0.2%
<u> </u>	widdle Section (KIMA Acces	s-JI. Malíno) (	wiiddle	south)																
		19.7 km																		
	Land Acquisition and Compensation							20%	40%	40%					[					
	Detailed Design and Supervision								25%	25%	25%	25%								
	Services									30%	40%	30%								
	Administration							20%	20%	20%	20%	20%								
	Administration							- 379			2070	2070								
	maintenance Routine														-					
	Maintenance Overlay per 5 Years															1				
						-														
	Land Acquisition and Compensatio	47,906						9,581	19,162	19,162										
	Detailed Design and Supervision S	19,595							4,899	4,899	4,899	4,899								
	Construction	279,929						1.120	1.100	83,979	111,972	83,979								
	Administration Maintenance Routine	2,508						1,120	1,120	1,120	1,120	1,120	314	314	314	314	314	314	314	314
	Maintenance Overlay per 5 Years	6,271															6,271			
	Total	361,807						10,701	25,181	109,159	117,990	89,997	314	314	314	314	6,585	314	314	314
		100%						3.0%	7.0%	30.2%	32.6%	24.9%	0.1%	0.1%	0.1%	0.1%	1.8%	0.1%	0.1%	0.1%
	Maros-KIMA Access (Middle	North)																		
		7.6 km																		
	Land Acquisition and Compensation															20%	40%	40%		
	Detailed Design and Supervision																25%	25%	25%	25%
	Construction				-										-			30%	40%	30%
	Administration															20%	20%	20%	20%	20%
	Maintananaa Boutina																			
	Wannenance Kouune																			
	Maintenance Overlay per 5 Years																			
																	_			
	Land Acquisition and	15 160														3.03/	6.069	6.069		
	Compensation Detailed Design and Supervision	15,109														5,054	5,008	3,008		
	Services	6,330															1,582	1,582	1,582	1,582
	Construction	90,425														2/2	262	27,128	36,170	27,128
	Maintenance Routine	1,809														362	.562	562	362	562
	Maintenance Overlay per 5 Years																			
		113.733														3,396	8,012	35,139	38,114	29,072
	Total	100%														3.0%	7.0%	30.9%	33.5%	25.6%
	Jl. Malino- South Section (Jl.	Tj.Bunga) (So	uth)																	
		16.7 km																		
	Land Acquisition and													20%	40%	40%				
	Compensation														170/	170	170/	170/	170	170/
	Services														1/%	1/%	1 / %	1 / %	1 / %	1 / %
	Construction															20%	20%	20%	20%	20%
L_	Administraition													14%	14%	14%	14%	14%	14%	14%
	Maintenance Routine																			
	Maintenance Overlay per 5 Years																			
<u> </u>						I	l													
	Land Acquisition and Compensation	9,274												1,855	3,710	3,710		_		
	Detailed Design and Supervision	17.487			-										2.915	2.915	2,915	2.915	2.915	2,915
	Services Construction	249 810													_,,,,	49 964	49.96/	49.964	49 964	49.964
	Administration	4,996												714	714	714	714	714	714	714
	Maintenance Routine																			
	Maintenance Overlay per 5 Years																			
	Total	281,576				1								2,569	7,338	57,302	53,592	53,592	53,592	53,592
	10181	100%				1				1				0.9%	2.6%	20.4%	19.0%	19.0%	19.0%	19.0%

# Table 9.1 Cost Distribution for Mamminasa Bypass Implementation

# 2) Trans-Sulawesi Mamminasata Road

The three (3) evaluation scenarios (cases) as in Figure 9.3 were prepared for economic and financial evaluation for the Trans-Sulawesi Mamminasata Road. Case 1 is non-toll road and Case 2 is toll road. The cost estimate was made for each case to meet these scenarios.



# Figure 9.3 Economic Evaluation Scenarios for Trans-Sulawesi Mamminasata Road

# Sub-case 1-1 (Alternative A)

The road is constructed as a non-toll road. The full length of project is implemented in one time. The project cost and its disbursement were estimated as given in the following table.

								0		•								
Item	Estimated Amount (M Rp.)	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
Section A, B, C & D	47.1km																	
Land Acquisition and Compensation		5.0%	30.0%	30.0%	35.0%													
Detailed Design and				40.0%	20.0%	20.0%	20.0%											
Supervision Services																		
Construction					35.0%	35.0%	30.0%											
Administraition				25.0%	25.0%	25.0%	25.0%											
Maintenance																		
Section A, B, C & D																		
Land Acquisition and Compensation	260,338	13,017	78,101	78,101	91,118	0	0	0	0	0	0	0	0	0	0	0	0	0
Detailed Design and Supervision Services	58,789	0	0	23,515	11,758	11,758	11,758	0	0	0	0	0	0	0	0	0	0	0
Construction	839,838	0	0	0	293,943	293,943	251,951	0	0	0	0	0	0	0	0	0	0	0
Administraition	16,797	0	0	4,199	4,199	4,199	4,199	0	0	0	0	0	0	0	0	0	0	0
Routine Maintenance	99,902							9,082	9,082	9,082	9,082	9,082	9,082	9,082	9,082	9,082	9,082	9,082
Periodic Maintenance	60,294											30,147					30,147	
	1.335.958	13.017	78,101	105.816	401.019	309,900	267,908	9.082	9.082	9.082	9.082	39,229	9.082	9.082	9.082	9,082	39,229	9.082
Total	(100%)	(1.0%)	(5.8%)	(7.9%)	(30.0%)	(23.2%)	(20.1%)	(0.7%)	(0.7%)	(0.7%)	(0.7%)	(2.9%)	(0.7%)	(0.7%)	(0.7%)	(0.7%)	(2.9%)	(0.7%)
Source: JICA Study T	eam																	

 Table 9.2
 Cost Distribution according to Implementation Plan for Alternative A

# Sub-case 1-2 (Alternative B)

The road is constructed as a non-toll road. The project is implemented in two phases. Phase I covers Section B (the Middle Ring Road) and Section C (Southern extension of the Middle Ring Road). Phase II covers Section A (Maros – Jl. Ir. Sutami IC) and Section D (Sungguminasa (Boka IC) – Takalar). The project cost and its disbursement were estimated as given in the following tables.

•.	Estimated			••••														
Item	Amount (M. Bn.)	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
Phase I																		
Section B & C	15.9km																	
Land Acquisition and	15.781	5.0%	30.0%	30.0%	35.0%													
Compensation																		
Detailed Design and				40.0%	20.0%	20.0%	20.0%											
Supervision Services					35.0%	35.0%	30.0%											
Construction				25.00	25.0%	25.06	25.00											
Administraition				23.0%	23.0%	23.0%	23.0%											
Maintenance																		
Phase II																		
Section A & D	31.2km																	
Land Acquisition and					25.0%	25.0%	25.0%	25.0%										
Compensation Detailed Design and						8.0%	32.0%	20.0%	20.0%	20.0%								
Supervision Services																		
Construction								33.3%	33.3%	33.3%								
Administraition						11.1%	22.2%	22.2%	22.2%	22.2%								
Maintenance																		
*	1																	
Phase I																		
Section B & C																		
Land Acquisition and	127,130	6,357	38,139	38,139	44,496	0	0	0	0	0	0	0	0	0	0	0	0	0
Detailed Design and																		
Supervision Services	32,286	0	0	12,914	6,457	6,457	6,457	0	0	0	0	0	0	0	0	0	0	0
Construction	461,224	0	0	0	161,428	161,428	138,367	0	0	0	0	0	0	0	0	0	0	0
Administraition	9,224	0	0	2,306	2,306	2,306	2,306	0	0	0	0	0	0	0	0	0	0	0
Routine Maintenance	29,506							2,682	2,682	2,682	2,682	2,682	2,682	2,682	2,682	2,682	2,682	2,682
Periodic Maintenance	17,090											8,545					8,545	
Total	676,460	6,357	38,139	53,359	214,687	170,192	147,130	2,682	2,682	2,682	2,682	11,227	2,682	2,682	2,682	2,682	11,227	2,682
Totai	(100%)	(0.9%)	(5.6%)	(7.9%)	(31.7%)	(25.2%)	(21.8%)	(0.4%)	(0.4%)	(0.4%)	(0.4%)	(1.7%)	(0.4%)	(0.4%)	(0.4%)	(0.4%)	(1.7%)	(0.4%)
Phase II																		
Section A & D																		
Land Acquisition and	133 208	0	0	0	33 302	33 302	33 302	33 302	0	0	0	0	0	0	0	0	0	0
Compensation	155,200	0	0	0	55,502	55,502	55,562	55,502	0	Ů	0	0	0	0	Ŭ	Ű	0	0
Detailed Design and Supervision Services	26,503	0	0	0	0	2,120	8,481	5,301	5,301	5,301	0	0	0	0	0	0	0	0
Construction	378.614	0	0	0	0	0	0	126.205	126.205	126,205	0	0	0	0	0	0	0	0
Administraition	7,572	0	0	0	0	841	1,683	1,683	1,683	1,683	0	0	0	0	0	0	0	0
Routine Maintenance	51,197			-		-	,	,	,	,	6,400	6,400	6,400	6,400	6,400	6,400	6,400	6,400
Periodic Maintenance	21,602								-			.,	.,	.,	21,602	.,	.,	.,
	618,696	0	0	0	33,302	36,264	43,466	166,490	133,188	133,188	6,400	6,400	6,400	6,400	28,002	6,400	6,400	6,400
Total	(100%)	(0.0%)	(0.0%)	(0.0%)	(5.4%)	(5.9%)	(7.0%)	(26.9%)	(21.5%)	(21.5%)	(1.0%)	(1.0%)	(1.0%)	(1.0%)	(4.5%)	(1.0%)	(1.0%)	(1.0%)
0.10.1	1,295,157	6,357	38,139	53,359	247,989	206,455	190,596	169,172	135,870	135,870	9,082	17,627	9,082	9,082	30,684	9,082	17,627	9,082
Grand Total	(100%)	(0.5%)	(2.9%)	(4.1%)	(19.1%)	(15.9%)	(14.7%)	(13.1%)	(10.5%)	(10.5%)	(0.7%)	(1.4%)	(0.7%)	(0.7%)	(2.4%)	(0.7%)	(1.4%)	(0.7%)
	(100/0)	(010 / 0)	()	(	(1) 1 (0)	(10.0 /0)	(1.1.7,0)	(1011 /0)	(1010 /0)	(1010 /0)	(0,0)	(1.1.70)	(017 /0)	(017 /0)	()	(01.70)	(1.1.70)	(0., ,0)

Table 9.3Cost Distribution according to Implementation Plan for Alternative B

Source: JICA Study Team

# Case-2

Alternative C is the plan in which Section B (the Middle Ring Road section) and Section C (Southern extension of the Middle Ring Road) would be constructed as an express toll road with frontage roads along Section B in the period of Phase I. Section A (Maros - Jl. Ir. Sutami IC) and Section D (Sungguminasa (Boka IC) - Takalar) would be undertaken in Phase II. The project cost and its disbursement were estimated as given in the following tables.

Table	9.4	С	ost D	istri	butio	n ac	cordi	ing to	o Imj	olem	entat	ion l	Plan i	for A	lterr	nativo	e C	
	Estimated																	

	Estimated																	
Item	Amount	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
ni 7	(M Rp.)															_		
Phase I																		
Section B & C (Toll Road	15.9km	5.0%	30.0%	30.0%	35.0%													
Compensation	127,130																	
Detailed Design and	25 514			40.0%	20.0%	20.0%	20.0%											
Supervision Services	35,514						-											
Construction	507,346				35.0%	35.0%	30.0%											
Administraition	10,147			25.0%	25.0%	25.0%	25.0%											
Maintenance																		
Section B (Frontage Road	7.1km																	
Land Acquisition and	0	5.0%	30.0%	30.0%	35.0%													
Compensation Detailed Design and				40.0%	20.0%	20.0%	20.0%											
Supervision Services	11,411			40.0.0														
Construction	163 010				35.0%	35.0%	30.0%											
Administration	3 260			25.0%	25.0%	25.0%	25.0%											
Maintenance	5,200																	
Phase II																		
Section A & D	31.2km																	
Land Acquisition and	122 208				25.0%	25.0%	25.0%	25.0%										
Getanetr Désign and	26 502					8.0%	32.0%	20.0%	20.0%	20.0%								
Cunarvisian Carviage	20,305							33.3%	33.3%	33.3%								
Construction	3/8,014					11.4%	22.2%	22.2%	22.2%	22.2%								
Administration	1,572																	
Maintenance																		
Phase I																		
Section B & C (Toll Road	)																	
Land Acquisition and	127 120	6 357	28 120	28 120	44 496	0	0	0	0	0	0	0	0	0	0	0	0	0
Compensation	127,150	0,557	36,139	56,159	44,490	0	0	0	0	0	0	0	0	0	0	0	0	0
Detailed Design and	35,514	0	0	14,206	7,103	7,103	7,103	0	0	0	0	0	0	0	0	0	0	0
Supervision Services	507 346	0	0	0	177 571	177 571	152 204	0	0	0	0	0	0	0	0	0	0	0
Administration	10 147	0	0	2 527	2 527	2 527	2 527	0	0	0	0	0	0	0	0	0	0	0
Autimistration Douting Maintenance	101.460	0	0	2,337	2,337	2,331	2,337	0.224	0.224	0.224	0.224	0.224	0.224	0.224	0.224	0.224	0.224	0.224
Routile Maintenance	55 247							9,224	9,224	9,224	9,224	9,224	9,224	9,224	9,224	9,224	9,224	9,224
renouic maintenance	926.054	( 257	20.120	54 001	221 704	107 211	1/1 042	0.224	0.224	0.224	0.224	27,073	0.224	0.224	0.224	0.224	27,075	0.224
Total	(1000()	(0,00/)	30,139	34,001	231,700	(22, 49())	(10.20())	9,224	9,224	9,224	9,224	30,090	9,224	9,224	9,224	9,224	(4 40()	9,224
Section P. (Eventers Dec	(100%) d)	(0.0%)	(4.0%)	(0.0%)	(27.7%)	(22.470)	(19.3%)	(1.1%)	(1.170)	(1.1%)	(1.170)	(4.470)	(1.170)	(1.1%)	(1.170)	(1.170)	(4.4%)	(1.1%)
Land Acquisition and	u)						-	-		-								
Compensation	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Detailed Design and	11.411	0	0	1 561	2 202	2 202	2 202	0	0	0	0	0	0	0	0	0	0	0
Supervision Services	11,411	0	0	4,304	2,282	2,282	2,282	0	0	0	0	0	0	0	0	0	0	0
Construction	163,010	0	0	0	57,054	57,054	48,903	0	0	0	0	0	0	0	0	0	0	0
Administraition	3,260	0	0	815	815	815	815	0	0	0	0	0	0	0	0	0	0	0
Routine Maintenance	16,301							1,482	1,482	1,482	1,482	1,482	1,482	1,482	1,482	1,482	1,482	1,482
Periodic Maintenance	14,819											7,410					7,410	
Total	208,801	0	0	5,379	60,151	60,151	52,000	1,482	1,482	1,482	1,482	8,891	1,482	1,482	1,482	1,482	8,891	1,482
Totai	(100%)	(0.0%)	(0.0%)	(2.6%)	(28.8%)	(28.8%)	(24.9%)	(0.7%)	(0.7%)	(0.7%)	(0.7%)	(4.3%)	(0.7%)	(0.7%)	(0.7%)	(0.7%)	(4.3%)	(0.7%)
Phase II																		
Section A & D																		
Land Acquisition and	133.208	0	0	0	33,302	33,302	33,302	33,302	0	0	0	0	0	0	0	0	0	0
Compensation																		
Detailed Design and	26,503	0	0	0	0	2,120	8,481	5,301	5,301	5,301	0	0	0	0	0	0	0	0
Construction	378.614	0	0	0	0	0	0	126.205	126.205	126.205	0	0	0	0	0	0	0	0
Administration	7 572	0	0	0	0	841	1 682	1 682	1 682	1 682	0	0	0	0	0	0	0	0
Routine Maintenance	22 193		0	0	0	041	1,005	1,005	1,005	1,005	2 774	2 774	2 774	2 774	2 774	2 774	2 774	2 774
Periodic Maintenance	13 870										2,774	2,774	2,774	2,774	13 870	2,774	2,774	2,774
i eriodie ividinendiee	581 041	•	•	•	33 302	36 264	13 164	166 400	133 199	133 199	2 774	2 774	2 774	2 774	16.645	2 774	2 774	2 774
Total	(100%)			(0.0%)	(5 79/)	(6 29/)	(7 59/)	(28.69/)	(22.00/)	(22.09/)	(0.5%)	(0.5%)	2,774 (0.5%)	(0.59/)	(2.0%)	2,774 (0.5%)	2,774 (0.59/)	(0.59/)
	(100%)	6 357	38 130	(0.0%)	325 150	283 425	(7.5%)	(20.0%)	143 004	(22.9%)	(0.5%)	(0.5%)	13 490	(0.5%)	(2.9%)	(0.5%)	(0.5%)	(0.5%)
Grand Total	(100%)	(0.49/)	(2 30/)	(3.79/)	(20.09/)	203,025	(15 89/)	(10.09/)	(8 80/)	(8 89/)	13,460	40,503	(0.89/)	(0.89/)	(1.79/)	(0.80/)	(3.09/)	13,460
Source: IICA Study Tee	(100%)	(0.4 /0)	(4.370)	(3.1 /0)	(20.0 /0)	(1/.4/0)	(13.0 /0)	(10.7 /0)	(0.0 /0)	(0.0 /0)	(0.0 /6)	(3.0 /0)	(0.0 /0)	(0.0 /0)	(1.7 /0)	(0.0 /0)	(3.0 /6)	(0.0 /0)

# 3) Hertasning Road

The project cost and its disbursement were estimated as given in the following Table 9.5.

Table 9.5	Cost Distribution for Implementation Plan of Hertasning Road
-----------	--

	Item	Amount	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
		(M. Rp.)		1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
3. H	ertasning Road	4.9 km																		
	Land Acquisition and Compensation		40%	50%	10%															
	Detailed Design and Supervision Services			10%	30%	30%	30%													
	Construction				30%	40%	30%													
	Administration			25%	25%	25%	25%													
	Maintenance Routine																			
	Maintenance Overlay per 5 Years																			
	Land Acquisition and Compensation	9,833	3,933	4,917	983															
	Detailed Design and Supervision Services	4,269		427	1,281	1,281	1,281													
	Construction	60,989			18,297	24,396	18,297													
	Administraition	1,220		305	305	305	305													
	Maintenance Routine	2,627						202	202	202	202	202	202	202	202	202	202	202	202	202
	Maintenance Overlay per 5 Years	8,082										4,041					4,041			
	Total	87,019 100%	3,933 4.5%	5,648 6.5%	20,866 24.0%	25,981 29.9%	19,882 22.8%	202 0.2%	202 0.2%	202 0.2%	202 0.2%	4,243 4.9%	202 0.2%	202 0.2%	202 0.2%	202 0.2%	4,243 4.9%	202 0.2%	202 0.2%	202 0.2%

Source: JICA Study Team estimation

#### 4) Abdullah Daeng Sirua Road

The project cost and its disbursement were estimated as given in the following Table 9.6.

		Amount	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
	Item	(M. Rp.)		1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
4. A	bdullah Daeng Sirua Road	15.3 km																		
	Makassar Section (West)	7.0 km																		
	Land Acquisition and Compensa				50%	50%														
	Detailed Design and Supervision					33%	33%	33%												
	Construction						50%	50%												
	Administraition			1	25%	25%	25%	25%												
	Maintenance Routine																			
	Maintenance Overlay per 5 Year																			
	Makassar Section (West)																			
	Land Acquisition and Compensa	31,451			15,725	15,725														
	Detailed Design and Supervision	6,386				2,129	2,129	2,129												
	Construction	91,230					45,615	45,615												
	Administraition	1,825			456	456	456	456												
	Maintenance Routine	2,965							247	247	247	247	247	247	247	247	247	247	247	247
	Maintenance Overlay per 5 Year	9,884											4,942					4,942		
	Sub-Total	143,741 100%			16,181 11.3%	18,310 12.7%	48,200 33.5%	48,200 33.5%	247 0.2%	247 0.2%	247 0.2%	247 0.2%	5,189 3.6%	247 0.2%	247 0.2%	247 0.2%	247 0.2%	5,189 3.6%	247 0.2%	247 0.2%
	Maros/Gowa Section (East)	8.3 km																		
	Land Acquisition and Compensa						20%	40%	40%											
	Detailed Design and Supervision							20%	20%	20%	20%	20%								
	Construction								25%	25%	25%	25%								
	Administraition						17%	17%	17%	17%	17%	17%								
	Maintenance Routine																			
	Maintenance Overlay per 5 Year																			
	Maros/Gowa Section (East)																			
	Land Acquisition and Compensa	5,424					1,085	2,170	2,170											
	Detailed Design and Supervision	8,694						1,739	1,739	1,739	1,739	1,739								
	Construction	124,199							31,050	31,050	31,050	31,050								
	Administraition	2,484					414	414	414	414	414	414								
	Maintenance Routine	2,785											348	348	348	348	348	348	348	348
	Maintenance Overlay per 5 Year	6,963															6,963			
	Sub-Total	150,549					1,499	4,322	35,372	33,203	33,203	33,203	348	348	348	348	7,311	348	348	348
L		100%			14.163	10.21-	1.0%	2.9%	23.5%	22.1%	22.1%	22.1%	0.2%	0.2%	0.2%	0.2%	4.9%	0.2%	0.2%	0.2%
	Total	150,549			16,181	18,310	49,699	52,522	35,619	33,450	33,450	33,450	5,537	595	595	595	7,558	5,537	595	595
		100%					1.0%	2.9%	43.5%	44.1%	44.1%	44.1%	0.2%	0.2%	0.2%	0.2%	4.9%	0.2%	0.2%	0.2%

 Table 9.6
 Cost Distribution for Implementation Schedule of Abdullah Daeng Sirua Road

#### 9.2 **Economic Evaluation**

#### (1) Economic Costs

Economic evaluation for the 4 (four) target roads was carried out based on the comparison between economic project costs and economic benefits. The economic costs of target roads are shown as below:

Target Road	Length	Economic Cost
	(km)	(Rp. Million)
R1: Mamminasa Bypass	48.6	854,521
R2: Trans-Sulawesi Mamminasata	47.3	
- Non-Toll		1,175,761
<ul> <li>Toll Expressway</li> </ul>		1,382,835
R3: Hertasning Road	4.9	76,310
R4: Abd. Daeng Sirua Road	14.6	271,692
Source: IICA Study Team		

Table 9.7 Economic Cost (Rp. Million, at 2006 Price)

Source: JICA Study Team

The following three (3) evaluation scenarios were prepared for the Trans-Sulawesi Mamminasata Road:

Case 1:	Non-Toll	
	Sub-Case 1-1: Sub-Case 1-2	Non-Toll and Full construction (all sections open by 2013) Non-Toll and Phases construction. Phase 1: opens by 2013 Phase 2: opens at the end of 2015
Case 2	Full access contr	rolled Toll Expressway (Middle section) opens by 2013

#### (2) Economic Benefit

Quantified economic benefits in the Study are:

- 1) Savings in Vehicle Operating Costs (VOC Savings)
- 2) Savings in Passenger Travel Time Costs (TTC Savings)

Basic data and parameters of unit costs of VOC and TTC were obtained from the "Indonesian Road Management System (IRMS) 2006".

#### (3) Economic Evaluation

Economic evaluation was carried out based on the following preconditions:

- Price level	: Constant 2006 prices
- Evaluation period	: 30 years after first opening to traffic
- Residual Value	: No residual values were counted
- Opportunity Cost of Capital	: 15% (and 12% for reference)

# (4) Evaluation Results

Evaluation indicators (Economic Internal Rate of Return: EIRR, Net Present Value: NPV, and Benefit/ Cost Ratio: B/C) were calculated based on the Discount Cash Flow method as shown below:

Target Roads		<b>Evaluation Indicators</b>	
	EIRR	NPV (Rp. million) (*)	B/C (*)
R1: Mamminasa Bypass	22.4%	171,550	1.97
R2: Trans-Sulawesi Mamminasata Road			
-(Non-Toll) 2013 simultaneous open	28.5%	768,273	2.30
-(Non-Toll) Phasing	30.2%	721,063	2.45
-(Toll Expressway)	26.7%	648,842	2.07
R3: Hertasning Road	33.8%	122,258	3.51
R4: Abd. Daeng Sirua Road	31.0%	110,466	1.96

Table 9.2.6Results of Economic Evaluation

Source: JICA Study Team

(\*) Discount Rate = 15%

() *Discount faute* = 1570

The above results show that the implementation of all target roads will be economically feasible and justified from the view point of national economy. Among the all target roads, Trans-Sulawesi Mamminasata Road (non-toll and phasing construction case), <u>Abdullah Daeng Sirua Road and Hertasning Road indicate the higher EIRR of 30.7%</u>, 31.0% and 33.8% respectively. NPV for the Trans-Sulawesi Mamminasata Road is the highest among FS roads.

# 9.3 Financial Evaluation

# (1) **Purpose of Evaluation**

It is recommended that the Trans-Sulawesi Mamminasata Road should be implemented as a non-toll road based on the results of economic analysis shown above. On the other hand, Bina Marga conducted a freeway/toll road study for Sulawesi Island in 2006 and recommended implementing the Trans-Sulawesi Mamminasata Middle Section with PPP project. Under the circumstance, it is necessary to re-investigate the financial viability under the PPP scheme and to check the government burden in this JICA Study.

# (2) Target Toll Road Sections for Financial Evaluation

Toll Expressway (fully access-controlled with ramps/interchanges) is assumed to be introduces at the section of the Middle Ring and its southern access road with a 15.9 km length as shown in the figure below:



Figure 9.4 Target Road Sections for Fully Access Controlled Toll Expressway

# (3) Financial Return on Investment and Government Burden

A comparison of toll revenue and project cost of the toll expressway shows that Financial Internal Rate of Return (FIRR) will be at 6.5% without any subsidies or other financial support from the Government. In general, a toll road project with such a low financial return should be implemented under the conventional public investment (see the following table).

			Economic Feasibility							
			Good	Marginal	Bad					
			EIRR>18%	12% - 18%	EIRR< 12%					
	Good FIRR>20%		BOT*	BOT*	-					
Financial	Marginal	10%-20%	PPP**	PPP**	-					
Viability	Pod		Public	Public						
	Dag	FIKK<10%	Finance	Finance	-					

Table 9.9Financial Viability and Category of Financing Scheme

Note: As FIRR of the project was estimated at 6.5%, it is categorized into Public Finance.

In order to attract a private sector to investment, it is necessary to achieve the minimum 20% of FIRR through the government subsidy on the initial investment. However, the necessary Government subsidy is estimated at 72.0% (Rp. 523,078 Million) of the total investment cost including the Land Acquisition. This percentage of government subsidy is too high comparing with the normal PPP schemes. Therefore, the project is recommended to be implemented under public finance.

# 9.4 Role of Mamminasata Metropolitan Area in the Sulawesi and Eastern Indonesia Regional Development

The national spatial plan defines three transport corridors throughout Indonesia. These are the Northern, Middle and Southern corridors, as shown in **Figure 9.5**. Sulawesi occupies a strategic location that could link the three development belts including the neighboring ASEAN countries.



Source: JICA Study Team



To promote industrial development, industrial centers should be enhanced in a manner that the investment environment for FDI and DDI are improved. To carry out regional development, which is "effective economic growth on the basis of the existing economic linkage," following development plans are proposed on the basis of Economic Linkage between South Sulawesi Province and Southeast Sulawesi Province.

The development on the basis of economic linkage between Makassar-Kendari is most important in the connection, utilization, and further promotion of concentrated populations and industries. Success of this development will contribute to the



# Figure 9.6 Development Plan on the basis of Economic Linkage between Makassar - Kendari

total economic growth of the island. Makassar will continuously function as the gateway for inter-island linkages. Both the neighboring Kalimantan energy base, Java Island and eastern Indonesia will be tightly linked with the Makassar and Parepare priority areas through the distribution and transportation of commodities and passengers.

# 9.5 Logistic Support for Trade and Investment Promotion

Within the Mamminasata Metropolitan Area, freight traffic is concentrated at present in the Makassar Industrial Estate (PT Kawasan Industri Makassar – KIMA). KIMA is located in the suburbs of Makassar City along Ir. Sutami Toll road, 15 km north of the Makassar Port and around 10 minutes drive from the Hasanuddin International Airport.

The comparative advantage of Sulawesi and Makassar in particular lies on their geographical location. However, this comparative advantage has not been realized well in business as well as in investment especially with the international market and foreign direct investment unless the following conditions are met:

- i) Transport infrastructure combined with road, seaport and airport in an integrated way is available.
- ii) Other infrastructures such as power supply, water supply, wastewater treatment, telecommunication, etc. are provided in complete set for modern industrial estates between the international seaport and airport.
- iii) Containerization proceeds at a certain degree or more than 40% of goods produced and exported can be containerized.

The development of the F/S roads would enhance industrial development in South Sulawesi and in Mamminasata Metropolitan Areas in particular. The Trans-Sulawesi Mamminasata Road will function as a major land transport infrastructure for sourcing and collection of raw materials for manufacturing and processing of various kinds of industrial products at closest and proper location to the international seaport and airport.

# 10 IMPLEMENTATION PLAN

# 10.1 Overall Implementation Plan for Major Road Development in Mamminasata Metropolitan Area

The major on-going and future road developments in the Mamminasata Metropolitan Area is approximately twenty (20) links including the four F/S roads and one Pre-F/S road undertaken by the Study Team. These are part of the secondary arterial road network system in the Mamminasata Metropolitan Area and envisaged to implement by the year 2023.

The average amount of development investment required for 2007-2023 period is estimated at Rp 190-200 billion per year. As the budget being able to allocate for the road infrastructure development would be limited, the implementation schedule of those road infrastructures should be carefully planned to bring the maximum benefits for nation, region, local economy and communities.

# **10.2** Implementation Plan for the FS Roads

# (1) Trans-Sulawesi Mamminasata Road

The investment required for the Trans-Sulawesi Road Project is estimated at approximately Rp 1,651-1,757 billion in total including civil works, consultancy services, ROW acquisition, administration and tax (VAT). If Japanese ODA facility (JBIC Loan) is used, 100% of civil works and consultancy service costs can be covered by a soft loan.

However, GOI needs to provide own finance for land acquisition, resettlement, administration and tax (VAT), which are not eligible for external loan. Land acquisition and resettlement costs for the Trans-Sulawesi Mamminasata Road are estimated at Rp 310 billion including inflation. The central and regional governments share the cost, allocate budget and complete the land acquisition and resettlement by commencement of the construction. As allocation of sufficient budget for the land acquisition and resettlement in period will be difficult, the Study Team made alternative implementation plans A and B.

Alternative A is implementation of the full length in one time and Alternative B is implementation in two phases. Phase 1 covers the Middle Ring Road and its south extension as these two sections are more urgently required in terms of traffic demand while less resettlement is required. Phase 2 covers the Maros-Jl.Ir.Sutami IC and Sungguminasa (Boka IC) - Takalar sections. **Table 10.1** shows basic concept of the alternative plans.

Alternative	Concept	Section	Length	Construction	Estimated Project
Plans				Period	Cost
А	Non-phased	Sections A,	47.1 km	36 months	Rp 1,625 billion
	Implementation	B, C and D		(2010-2012)	
В	Phased	Phase 1:	16.0 km	36 months	Rp 886 billion
	Implementation	Sections B		(2010-2012)	
		and C			
		Phase 2:	31.1 km	36 months	Rp 842 billion
		Sections A		(2013-2015)	
		and D			

Table 10.1Alternative Implementation Plans

Approximately Rp 99 billion will be required from 2008 to 2010 for the land acquisition and resettlement in the case of Alternative A. Annual budget requirement could be reduced to approximately Rp 55 billion from 2007 to 2013 as illustrated in **Figure 10.1** for Alternative B. It seems that Alternative B is more practicable and, therefore, it is recommended.





There are many houses to be moved for the existing road widening along the project road, especially at Mandai in Kab.Maros (Section A) and Limbung in Kab.Gowa (Section D) and it needs considerable time for resettlement negotiations and arrangement. On the other hand, the ROW acquisition is in progress for the Middle Ring Road (Section B) and there are not so many houses to be moved for Section C. It is expected that land acquisition and resettlement for Sections A and D can be progressed and completed during the construction of Sections B and C.

# (2) Mamminasa Bypass, Hertasning Road and Abdullah Daeng Sirua Road

# 1) Mamminasa Bypass

Four ring roads were planned for the Mamminasata Metropolitan Area namely the inner ring (JI A.P.Pettarani/ JI Tol Reformasi), middle ring, outer ring and outer-outer ring (Mamminasa Bypass). A general order of development requirement is from the inner ring to outside. However, as anticipated role and function of the Mamminasa Bypass are to induce/promote the creation of a new satellite town at the foot of Mt. Moncongloe (approximately 15 km east of the Makassar City center), the middle part of the bypass road, which is an arterial road for the new town, should be constructed earlier than the northern and southern sections.

# 2) Hertasning Road

The Hertasning Road (4-lane road) is under construction by the South Sulawesi Provincial Government. It is anticipated that the Provincial Government will continue the construction and complete this road by the end of 2010 using APBD I (provincial budget).

If budget availability is tight, staged implementation could be applied for Section D, 4.5 km long from the new campus of the State Islamic University to the intersection of the Kabupaten road. The  $1^{st}$  stage consists of widening the existing 4.5 m road to 7 m road, and the  $2^{nd}$  stage consists of further widening it to 4-lane road in the future.

3) Abdullah Daeng Sirua Road

A part of the Abdullah Daeng Sirua Road (Section B) is under construction by Makassar City (APBD II) and this should be continued up to the Makassar / Maros boarder.

The Maros / Gowa Regency section is a direct access from the Makassar City center to a planned new satellite town at the foot of Mt. Moncongloe (15 km east of the Makassar City center) and KIWA. The section should be constructed together with the middle section of Mamminasa Bypass.

# **10.3** Executing Agency

The execution agency for national roads shall be DGH. That for provincial roads is Praswil of South Sulawesi Province and that for the city roads are Makassar City. The executing agency of the F/S road project will be as given in the following table.

Project	Sub-Section	Administrative	Executing Agency
		Status of Road	
Trans-Sulawesi	-	National	DGH/MPW
Mamminasata Road			
Mamminasa Bypass	North Section	Provincial	Praswil, South Sulawesi Province
	Middle Section	Provincial	Praswil, South Sulawesi Province
	South Section	Provincial	Praswil, South Sulawesi Province
Hertasning Road	Section D	Provincial	Praswil, South Sulawesi Province
Abdullah Daeng	Makassar	Makassar City	PU, Makassar City
Sirua Road	Section		
	Maros / Gowa	Provincial	Praswil, South Sulawesi Province
	Section		

Table 10.2	Executing	Agency

# **10.4** Contract Packaging

# (1) Trans-Sulawesi Mamminasata Road

The project should be implemented with appropriate contract packages to be determined taking into consideration the size of contracts (amount and quantity), characteristics of the section, technical difficulty, construction period, funding source and competition in bidding. **Figure 10.2** shows the packaging and scope of work for alternative implementation plans A and B.



#### Source: JICA Study Team

# Figure 10.2 Implementation Plan B and Contract Packaging for Trans-Sulawesi Mamminasata Road

#### (2) Mamminasa Bypass, Hertasning Road, A.D. Sirua Road

#### 1) Mamminasa Bypass

The Mamminasa Bypass was divided into four (4) sections as indicated in **Table 10.3** taking the appropriate construction timing into consideration.

Section	Section Name	Road	Major Bridge	Construction	Estimated
No.*		Length	Length	Period	Construction Cost
1-A	Maros Bypass	5.7 km	Maros Bridge	24 months	Rp 88 billion
	Section		(126m)	(2016-2017)	
1-C	Middle Section	6.9 km		36 months	Rp 90 billion
	(KIMA Access –			(2013-2015)	
	Jl Malino)				
1-B	Maros-KIMA	19.7 km		36 months	Rp 280 billion
	Access			(2021-2023)	
1-D	Jl Malino –	16.7 km	Jeneberang	60 months	Rp 250 bullion
	South Section (Jl		Bridge (154m)	2019-2023	
	Tj Bunga)				
Total		49.1 km	280m		Rp 708 billion

Table 10.3	Implementation	Section of	f Mamminasa	Bypass
I HOIC I UIC	Implementation	Dection of	1 I I I I I I I I I I I I I I I I I I I	Dypubb

Note: Order of sections from the north (Matos) to the south Source: JICA Study Team

Of the above, it is assumed that an external soft loan would be applied for Section B, Middle Section (KIMA Access – Jl Malino), as this section should be constructed earlier than other sections according to the strategy of inducing the creation of a new satellite town along this road section. The construction should be carried out in one or two contract packages taking the estimated project cost and work characteristics into account.

2) Hertasning Road

The JICA Study Team studied only Section D (4.9 km) of the Hertasning Road. Application of a single contract package would be appropriate for the construction of this road section.

3) Abdullah Daeng Sirua Road

Section B of the Abdullah Daeng Sirua Road is under construction and, therefore, Sections C and D within the territory of Makassar City should be implemented with appropriate contract packaging determined by Dinas PU. For the construction of Sections E and F in the territory of Kabupaten Maros and Gowa, it is recommended to use an external soft loan as these sections should be connected to the Mamminasa Bypass to induce the new satellite town. Considering the estimated project cost, application of one or two contract packages would be appropriate for the

-														
Section	Section Section Name		Long Bridge	Construction	Estimated									
No.		Length	Length	Period	Construction Cost									
4-A, 4-C	Makassar City	7.0km		48 months	Rp 91 billion									
and 4-D	Section			(2010-2013)										
4-E and	Kabupaten Maros	8.3km	Tallo Bridge	36 months	Rp 124 billion									
4-F	& Gowa Section		(60m)	(2013-2015)										
Total		15.3km			Rp 315 billion									

construction of these sections.

 Table 10.4
 Implementation Section of Abdullah Daeng Sirua Road

Source: JICA Study Team

# **10.5** Implementation Schedule

# (1) Trans-Sulawesi Mamminasata Road

# 1) Pre-construction Schedule and Action Plan

A joint financing by GOI and an external source (either Japanese ODA scheme or other donor agency) will be appropriate for implementation of the project. **Figure 10.3** shows planned schedule (implementation plan for Phase 1 project of Alternative Implementation Plan B) and action plan for the use of the Japanese ODA facility for earliest project implementation. Similar procedures will be required in the case of using other external funding. The phase 2 project also should be implemented in the same way as the phase 1.

The DGH needs to make internal project screening and submit the project proposal to Bappenas through MOW for Blue Book listing. Financial arrangements of GOI (APBN/ABPD) are also necessary for the cost not covered by the external loan like land acquisition, resettlement and administration costs.

AMDAL (EIA) for the project was approved by the Governor of South Sulawesi Province in September 2007. The LARAP policy frame required for project appraisal was also prepared by the JICA Study Team.

	Item / Action		Period	2006		20	07			20	80		20	09	20	10	20	11	20	12	20	13
1.	Feasibility Study (	Interim Report)		-		_																
2.	Screeing and Fina	ancial (Loan) Procedures																				
З.	Procurement of C	onsultant																				
4.	Detailed Engineer	ing Design																				
5.	Bidding and Contr	ract												-								
6.	Construction		2009-2012																			
7.	Maintenance																					
		Feasibility Study	Up to Jene 2007			_																
	dy																					
	Stu	Assist in EIA (AMDAL)					-															
	¥ (۲	Assist in LARAP																				
Ś	ar	Framework																				
ů.	C Ĕ	Preparation of Project	Jun 2007																			
,g	A C	Digest				- 7																
u u	ЫĻ	Assist in Implementaion	Jun 2007																			
oa		Program Preparation																				
1		Eact Findings	Aug - Sep 2007																			
of		Project Appraisal	Oct-Nov 2007			-				-												
S	č	Pledge	Eeb 2008			_				-	-	-							_	-		
	18	Exchange of Notes	Mar 2008			_						-										
	,	Loan Agreement	Mar 2008			-				_												
	Project Monitoring		11101 2000			-				_												
		r toject Monitoring				_																_
	Bina Marga		Lin to Jun 2007																			
	Dina Marga		00 10 0011 2001																			
	Banedal-Da	Public Consultation																				
	Dapedal Da				(TOI	R) (E	IA) (	LAR	AP F	ram	work	)										
	Bapedal-Da	Assessment and Approval	Up to Sep 2007																			
	Bapoaa. Ba	of AMDAL	op to oop.2001																			
de	Bina Marga	Implementation Program	Up to Jun.2007																			
Si	Bina Marga	Screening and Proposal of	Nov 2007				-															
an	Dina maiga	Project to Bappenas																				
ŝŝi	MOF	Request to GOJ	Feb.2007					<b>^</b>														
ů,	Bina Marga	Request for Blue Book	Up to Dec.2007					1														
ğ	Bina	Budget consultation /																				
1	Marga/MOF/Regi	negotiation																				
	onal Goverment																					
	Bina	Budget allocation for land		_																		
	Marga/MOF/Regi	acquisition and										_										
	onal Goverment	resettlement																				
	Dinas PU/ Kota/	Land acquisition /																				
	Kabupaten	Resettlement					[ <sup>-</sup> ]								Г							
Noto	* a case for use o	f Jananese ODA facilities ( II	BIC Loan)			E/C	Ron	ort f	for T	rane	Sul	214/0	ci Ma		inac	oto F	2020	1710	no 2	007	<u> </u>	

# Figure 10.3 Implementation Schedule and Action Plan for Trans-Sulawesi Mamminasata Road Project (Case of Japanese ODA Facility)

#### 2) Construction Stage

The construction period is estimated to be 36 months. The required period for the roadway and bridge construction is estimated based on the work quantities in Section 9.1, daily productivity, number of work-units, and seasonal working days.

3) Post-construction Stage

Maintenance of for warranty period (one year) is the responsibility of the contractors. After that, the project road will be maintained by DGH. If operation and maintenance works are contracted out, they are under the responsibility of operator/contractors. The project execution will be continually monitored by the executing agency.

# (2) Mamminasa Bypass, Hertasning Road, A.D. Sirua Road

The implementation schedule of the Mamminasa Bypass, Hertasning Road and Abdullah Daeng Sirua Road would differ by financing source and availability. The anticipated or assumed financial source and implementation schedule are as shown in **Figure 10.4**.

Road	Length*	Financial	Period	2006-2010 2011-2015			2016-2020				2021-2023										
	(km)	Source*		2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
<ul> <li>Mamminasa Bypass</li> </ul>																					
- Maros Bypass Section	5.0	APBN	2016-2017																		
- Maros-KIMA Access	7.6	APBN/ APBD I	2021-2023																		
- Middle Section (KIMA	19.4	External	2013-2015																		
- Jl. Malino- South Section	16.7	Loan or Private Investor APBN/	2019-2023																		
(JI.Tj.Bunga)		APBD I																			
<ul> <li>Hertasning Road</li> </ul>																					
- Secions C	3.4	APBD I	Up to 2008																		
- Secions D	4.9	APBD I	2008-2010			_															
Abdullah Daeng Sirua Road - Makassar Section	2.5	APBD II	Up to 2009																		
- Makassar Section	7.4	APBD II	2010-2011																		
(Sections A, C, D) - Maros/Gowa Section	7.2	External	2012-2015																		
(Section E and F)		Loan or Privato																			
		Investor																			
Source: JICA Study Team					•					•										•	

# Figure 10.4 Construction Schedule of Mamminasa Bypass, Hertasning Road and Abdullah Daeng Sirua Road

# **10.6** Operation and Maintenance Plan

#### (1) Key Maintenance Issues and Financing Sources

Sustainability of the road facilities after development is the most important issue. The asset management approach should be applied.

The road maintenance work consists of routine maintenance and periodic maintenance. The management, planning and execution of the maintenance work for national roads are under the responsibility of DGH. The routine maintenance is conducted by force account of provincial or regency governments using APBN allocated by DGH. The periodic maintenance is contracted out.

The planning and execution of the maintenance work for provincial roads is under the responsibility of Praswil of South Sulawesi Province using APBD I, while for city or Kabupaten roads they are under the responsibility of Dinas PU of city or regency governments using by APBD II.

The key issue for the maintenance is the lack of financial and budgetary sustainability and/or insufficient budget allocation. A stable funding source should be established for maintenance financing. There are two approaches: budget approach and road fund approach. In the first approach, the road costs are considered as public expenditures to be covered by national or provincial budget. The revenue from fuel taxes, vehicle registration fees and others levies is used to cover such road costs. In the second approach, road users pay for the road costs. The former is the current practice in Indonesia and the establishment of road fund is one of the future challenges.

#### (2) Trans-Sulawesi Mamminasata Road

The operation and maintenance cost required for the Trans-Sulawesi Mamminasata Road is estimated to be Rp 9,000 million per year for routine maintenance. Periodic maintenance is also required at a certain interval. In order to secure the sustainability of the Trans-Sulawesi Mamminasata Road after construction, a funding mechanism to finance operation and maintenance cost should be instituted. There will be three methods: the operation and maintenance by force account of DGH; by contractors under supervision of DGH (Balai Besar VI); and by participation of the private sector. The former two involve public financing and the last one involves financing by the private sector.

The Study Team recommended to collect low user charges at the toll gates installed at access points, Tallo River Bridge and Jeneberang River Bridges, to Makassar City indicated in **Figure 10.5** could raise a sufficient fund for covering the maintenance costs required for the TSMR.



Figure 10.5 Location of Toll Gates for O&M Cost Recovery

#### (3) Mamminasa Bypass, Hertasning Road and Abdullah Daeng Sirua Road

The road maintenance work for the Mamminasa Bypass, Hertasning Road, Abdullah Daeng Sirua Road consists of routine maintenance and periodic maintenance. The management, planning and execution of the maintenance work for these roads are under

the responsibility of Praswil of South Sulawesi Province using APBD I or Dinas PU of Makassar City using APBD II.

As the central section of the Mamminasa Bypass and the Maros/Gowa section of Abdullah Daeng Sirua Road are for the service of a new satellite town, the maintenance obligation might be transferred to the private investors who participate in the new town development.

# **10.7** Financing Plan and Annual Fund Requirements

#### (1) Trans-Sulawesi Mamminasata Road Project

Figure 10.6 summarizes the general financing methods studied for the Trans-Sulawesi Mamminasata Road Project.



Source: JICA Study Team

#### Figure 10.6 Financing Methods for Trans-Sulawesi Mamminasata Road Project

There will be two financing methods for implementation of the project. One is financing by the public sector and the other is co-financing with the private sector (Public Private Partnership). In both methods it is possible to use a soft loan facility either from Japan or other sources. However, PPP will be difficult to apply as the Project's FIRR is too low. Hence, public finance was recommended.

**Table 10.5** indicate the financing plan for the project in the case of amplification of Japanese ODA facility (JBIC soft loan) by alternative implementation plan with assumptions that:

- \* 100% of the costs of civil works, consulting services and contingencies are financed by an external soft loan
- \* GOI finances the land acquisition/resettlement, administration cost and tax (VAT), which are not eligible for the JBIC loan
- \* The assumed the currency exchange rate is of US\$ 1.00=¥120=Rp.9,322 (as of May 2007).

The total project cost is estimated at Rp 888 billion and Rp 869 billion for Phase 1 and Phase 2 of Alternative B, respectively. The loan amount for the project, which is the total of the civil works, the consulting services and contingencies, is estimated to be US\$ 72.7 million for Phase 1 and US\$ 67.7 million for Phase 2. The rest of the project cost will be financed by the local budget (APBN and APBD). The loan cover 71% - 75% of the project cost.

		Α	Iternative E	3	Actual
	Alternative A	Phase 1	Phase 2	Total	Implementaion
					for Phase 1*
External Soft Loan (US	6 million)				
- Civil Works	112.7	61.9	57.6	119.5	61.9
- Consulting Services	8.4	4.6	4.3	8.9	5.7
- Contingencies	11.3	6.2	5.8	11.9	6.2
Total	132.3	72.7	67.7	140.4	73.8
GOI APBN / APBD (Rp b	illion)				
- Land Acquisition	283.8	148.9	156.6	305.5	148.9
- Administration Cost	16.8	9.2	7.6	16.8	9.2
- Tax (VAT)	121.7	66.8	62.2	129.0	67.8
Total	422.3	224.9	226.3	451.3	225.9
Grand Total (Rp billion)	1,625.4	885.7	841.6	1,727.2	896.7

 Table 10.5
 Project Cost and Loan Amount by Alternative Implementation Plan

Note: \* The detailed design for Phase 2 will be carried out during the Phase 1 work. Source: JICA Study Team

# (2) Mamminasa Bypass Project, Hertasning Road Project and Abdullah Daeng Sirua Road Project

The Mamminasata Bypass, the Hertasning Road and Maros/Gowa section of the Abdullah Daeng Sirua Road will be developed as a provincial roads, the construction and consultancy services will be financed by APBD I (the provincial budget) in principle and possibly by APBN as these are arterial road links in the Mamminasata Metropolitan Area. External soft loan may be used for the development of the Mamminasa Bypass Project possibly covering a substantial part on a granting basis from the central government. Maintenance will be financed by APBD I since the roads are provincial roads.

There are following potential funding sources which could be utilized for the development of regional roads:

i) **Funding from the Line Ministry (APBN):** The national budget of Bina Marga for the road

sector (APBN) is allocated mainly for the development of national roads, but sometimes it is allocated for the development of provincial roads.

- ii) External Loan/Grant via the same route as above (APBN): The Ministry of Finance has already prepared the decrees on both case of granting external loan from the GOI to regional governments (PMK 52 /2006: Peraturan Menteri Keuangan, Nomor 52/PMK 010 /2006) and lending external loan (PMK 53 /2006). However, due to the limited financial capacity of the regional governments, only the external loan granting practice has been adopted so far. External loan granting may be extended to both provincial and Kabupaten/Kota governments. The ERITP II project is implemented on the On-granting basis with 30% 90% of the project cost being provided by the central government.
- DAK (Special Allocation Fund: APBD): DAK is one category of balancing fund from GOI to regional governments. DAK has been allocated to cover the road sector expenditures of Kabupaten/Kota governments in the last two years based on the proposal from these governments. However, DAK allocated to the road sector should be used in accordance with PU's instruction (Peraturan Menteri Pekerjaan Umum Nomor: 39 /PRT/M/2006), that is 70% for the maintenance and 30% for the improvement/construction.
- iii) General Regional Budget (APBD I: Province and APBD II: Kabupaten/Kota): The General Regional Budget (APBD I and APBD II) is although limited the major funding source for both the development/improvement and maintenance of regional roads. APBD I and APDB II are financed by own regional tax/levy revenue and the balancing fund from GOI such as the Revenue Sharing, the General Allocation Fund (DAU) and the Special Allocation Fund (DAK).
- iv) **Mamminasata Metropolitan Area:** Strategic and priority infrastructures in the Mamminasata Metropolitan Area might be financed by the national budget in future.

**Figure 10.7** shows the optional financing methods applicable for the Mamminasa Bypass, Hertasning Road and Abdullah Daeng Sirua Road projects. If preferable incentives and conditions are given and secured, private investors may participate in some part of the road development.

It may be possible to introduce an external soft loan for the central section of Mamminasa Bypass and the Kabupaten Maros/Gowa section of Abdullah Daeng Sirua Road as those are for inducing a new satellite town in accordance with the Mamminasata Spatial Plan.

March 2008





Note: Excluding VAT and Administration cost Source: JICA Study Team

# Figure 10.7 Optional Financing Methods for Mamminasa Bypass, Hertasning Road and Abdullah Daeng Sirua Road Project

# 11 CONCLUSIONS AND RECOMMENDATIONS

## **11.1** Conclusions on F/S Roads

#### (1) Trans-Sulawesi Mamminasata Road

- 1) The Study Team identified that the Trans-Sulawesi Mamminasata Road (TSMR) is the highest priority road link among the four F/S roads. It will directly contribute to the development of the Mamminasata Metropolitan Area by:
  - improving the present urban road network;
  - coping with the increasing traffic demand;
  - > enhancing regional development; and
  - supporting logistic flow for inducing trade, investment and industrial development.

It also will indirectly contribute to:

- > expanding development to the whole eastern regions of Indonesia; and
- > reducing poverty and regional development gaps.
- 2) The feasibility study for the TSMR has shown that the Project is highly viable in both technical and economic aspects (EIRR: 28.5-30.2%). Therefore, it is recommended that the Project be implemented at an earliest date for the benefit of national and regional economy.
- 3) As to the construction plan, a full access-controlled express highway for the Middle Ring Road section under PPP (Public Private Partnership) scheme is judged not feasible because its FIRR is only 6.5%. Thus this project should better be implemented in the category of public financing (Government) projects.
- 4) Collection of low user charges at the toll gates installed at access points (Tallo River Bridge and Jeneberang River Bridges) to Makassar City could raise a sufficient fund for covering the maintenance costs required for the TSMR.
- 5) The current progress of ROW acquisition for the Middle Ring Road (Section B) is approximately 60-70%.
- 6) EIA (AMDAL) report on the TSMR Project was approved by the Governor of South Sulawesi Province in September 2007.

## (2) Mamminasa Bypass

- 1) The Study Team identified that the Mamminasa Bypass is the second highest priority road link among the four F/S roads.
- 2) The Mamminasa Bypass should be constructed as a new road. The appropriate route is that passing through appropriate topography and location where a new satellite town can be developed. The north section of the Mamminasa Bypass should be planned as a bypass for Maros Town while avoiding a planned flood retarding basin of the Maros River. The southern route should be connected to Jl.Tj.Metro Bunga where many development projects are in progress or under planning.
- 3) It will directly contribute to the development of the Mamminasata Metropolitan Area by:
  - inducing a new satellite town at the east of Makassar City and the west foot of Mt. Moncongloe, where flood free 4,000 ha of land could be available for regulated urban development; and
  - enhancing regional development, especially contributing to the development of KIWA (planned new industrial area of Gowa Regency).
- 4) The feasibility study for the Mamminasa Bypass has shown that the Project is viable on both technical and economic aspects (EIRR: 22.4%). Therefore, it is recommended that the Project be implemented at an earliest date for the benefit of national and regional economy.
- 5) As the middle section of the Mamminasa Bypass and the Maros/Gowa Regency section of the Abdullah Daeng Sirua Road are intended to serve directly the planned new satellite town, they might be constructed with cooperation of private investors who will participate in the new satellite town development.
- 6) EIA (AMDAL) report on the Mamminasa Bypass Project needs to be approved by the Governor of South Sulawesi Province.

#### (3) Hertasning Road

- 1) The Study Team identified that the Hertasning Road is an important arterial road link for the Mamminasata Metropolitan Area.
- 2) The Hertasning Road construction project is an ongoing development project under South Sulawesi Government. It is divided into four sections: Sections A, B, C and D. Section A has already been completed and Section B is under construction. The detailed design for Section C has been completed. Therefore, only Section D was subject to F/S.

- 3) The Hertasning Road has the following functions:
  - Direct access road from the east suburbs to the Makassar City center as one of the radial roads.
  - A main access road to TPA (new final waste disposal area planned at Pattallassang in Gowa Regency).
  - Enhancement of regional development, especially contributing to the development of KIWA (new industrial area of Gowa Regency).
  - A short cut route for the Bili-bili Dam and Malino.
- 4) The feasibility study for the Hertasning Road has shown that the Project is viable on both technical and economic aspects (EIRR: 33.8%) and it will contribute to national and regional economy.

# (4) Abdullah Daeng Sirua Road

- 1) The Study Team identified that the Abdullah Daeng Sirua Road is one of the important arterial road links for the Mamminasata Metropolitan Area.
- 2) The Abdullah Daeng Sirua Road construction project is an ongoing development project under Makassar City. It is divided into six sections: Sections A, B, C, D, E and F, and Section B is under construction. Sections E and F are in the Maros/Gowa Regency
- 3) It will directly contribute to the development of the Mamminasata Metropolitan Area by:
  - inducing a new satellite town at the east of Makassar City and the west foot of Mt. Moncongloe, where flood free 4,000 ha of land could be available for regulated urban development;
  - providing direct access for the residents staying in the east suburbs of Makassar City; and
  - enhancing regional development, especially contributing to the development of KIWA (new industrial area of Gowa Regency).
- 4) The feasibility study for the Abdullah Daeng Sirua Road has shown that the Project is viable on both technical and economic aspects (EIRR: 31.0%). Therefore, it is recommended that the Project be continued for the benefit of national and regional economy.
- 5) As the Maros and Gowa Regency sections are intended to serve directly the planned new satellite town, they might be constructed with cooperation of private investors who will participate in the new satellite town development.

### **11.2** Recommendations on F/S Roads

#### (1) Trans-Sulawesi Mamminasata Road

- 1) The Trans-Sulawesi Mamminasata Road Project (the TSMRP) should be implemented as a national strategic road link since it is a part of the Trans-Sulawesi West Corridor and an arterial road for the Mamminasata Metropolitan Area.
- 2) The TSMRP should be implemented in two phases: Phase 1 for Sections B and C (Middle Ring Road and its southern extension), and Phase 2 for Section A (Maros-Jl.Tol.Ir.Sutami IC) and Section D (Sungguminasa Takalar).
- 3) The Directorate General of Highways (DGH) should request Bappenas to list the TSMRP in the Blue Book for foreign funding assistance.
- 4) DGH should conduct an appropriate project evaluation process and propose, preferably to the Government of Japan, for extension of a soft loan for the implementation of the TSMRP, through PU, Bappenas and MOF as soon as possible.
- 5) The central and regional governments should negotiate and allocate sufficient budget required for ROW acquisition and resettlement for the project preparation. The ROW acquisition for the Middle Ring Road should be continued.
- 6) DGH should make environmental management and monitoring in accordance with the environmental management and monitoring plans established in the EIA Report in cooperation with the agencies concerned.

#### (2) Mamminasa Bypass

- 1) The Mamminasa Bypass Project (the MBP) should be implemented as a provincial strategic road or a national strategic road since it is an arterial road for inducing the creation of a new satellite town for the Mamminasata Metropolitan Area.
- 2) The MBP should be implemented in four phases. The middle part of the Mamminasa Bypass should be constructed in the first phase since it is an arterial road for the planned new satellite town.
- 3) An external funding would be necessary and, therefore, South Sulawesi Government should request Bappenas to list the MBP in the Blue Book.
- 4) A separate study should be conducted for establishment of a satellite town development plan. The private sector should be encouraged to participate in the required infrastructure construction, including access road for the new satellite town development.
- 5) The regional governments should control housing and other development on the route of

the Mamminasa Bypass and the planned new town area to secure the land for these developments.

6) The regional governments should make environmental management and monitoring in accordance with the environmental management and monitoring plans established in the EIA Report in cooperation with the agencies concerned.

# (3) Hertasning Road

- Implementation of the Hertasning Road Project (the HRP) should be continued by South Sulawesi Province as a provincial strategic road since it is an arterial road of the Mamminasata Metropolitan Area.
- 2) The remaining sections of the HRP (Sections C and D) might be implemental as an access road for TPA (new final waste disposal area planned at Pattallassang in Gowa Regency).
- 3) A stage construction approach might be applied for Sections C and D of HRP taking tight budget required for both ROW acquisition and construction into consideration. The 1<sup>st</sup> Stage is widening of the existing 4.5m travelway (carriageway) to a 7.0 m standard road. The 2<sup>nd</sup> stage is further widening from 2 lanes to 4 lanes with a median.
- 4) The regional governments should control housing and other developments within the planned ROW.
- 5) The regional governments should make environmental management and monitoring in accordance with the environmental management and monitoring plans etablished in the EIA Report in cooperation with the agencies concerned.

#### (4) Abdullah Daeng Sirua Road

- 1) Makassar City Section
  - Implementation of the Abdullah Daeng Sirua Road Project (the ADSRP) should be continued by Makassar City up to the border of Makassar City and Gowa Regency as a strategic road.
  - ii) Financial assistance by both provincial and central governments should be made since this is an arterial road of the Mamminasata Metropolitan Area.
  - iii) As ROW acquisition is difficult for the beginning section of the ADSRP (Section A) which is located in a densely populated urban area, one-way traffic control should be applied rather than widening it to a 4-lane road, considering the environmental aspect.
  - iv) The construction of the road sections in the semi-urban and residential area should be made by utilizing the ROW of PDAM as much as possible. However, the PDAM canal

should be kept open as much as possible for securing a green and water front environment.

- v) The regional governments should make environmental management and monitoring in accordance with the environmental management and monitoring plans established in the EIA Report in cooperation with the agencies concerned.
- 2) Maros/Gowa Regency Section
  - The ADSRP in the Maros/Gowa Regency section should be implemented as a provincial strategic road or a national strategic road since it is an arterial road for inducing the creation of a new satellite town for the Mamminasata Metropolitan Area.
  - An external funding would be necessary for the Maros/Gowa Regency section and, therefore, South Sulawesi Government should request Bappenas to list up the ADSRP on the Blue Book, as a package with the middle part of the Mamminasa Bypass.
  - iii) The regional governments should control housing and other developments within the planned ROW.
  - iv) The regional governments should make environmental management and monitoring in accordance with the environmental management and monitoring plans established in the EIA Report in cooperation with the agencies concerned.

# **11.3** Conclusion and Recommendations on Other Roads

#### (1) Outer Ring Road

- 1) The Outer Ring Road is one of the important links in the Mamminasata Metropolitan Area arterial road network and its expected functions are as follows:
  - > Ring road to contribute to harmonizing urban development;
  - Logistic route for the coming in and out traffic from/to the southern area of South Sulawesi Province to/from KIMA, Makassar Port, new industrial areas along Jl.Tol.Ir.Sutami; and
  - > Connection between the north educational center and the south educational center.
- 2) The Outer Ring Road consists of three parts. The north section is the part accessing to KIMA, Jl.Tol.Ir.Sutami and Makassar Port. The middle section runs along the Tallo River and the south section is a connection to the Sungguminasa and Mamminasa Bypass. The Outer Ring Road and the Mamminasa Bypass share the same road at their southern part to connect to the Tj. Bunga Development Area.
- 3) The northern section between Jl.Tol.Ir.Sutami and Jl. Perintis Kemerdekaan through the New Industrial Area (Kawasan Pergudangan dan Industri Parangloe Indah) is under

construction by a private investor and will be completed as planned.

- 4) Intersections for Jl.Tol.Ir.Sutami and the Outer Ring Road should be constructed under the on-going BOT project.
- 5) A 500-700 m buffer zone should be provided between the route of the on-going north section and the Tallo River to avoid negative effects to the river environment.
- 6) As the project is vital on both technical and economic aspects (EIRR: 27%), it is recommended to conduct a feasibility study including EIA for its implementation.

# (2) Tj.Bunga – Takalar Road (Jalan Lintas Barat Makassar - Takalar)

- As floods do not occur at the Jeneberang River estuary after the Bili-bili dam construction, many development projects have been implemented. Since the completion of a bridge at the mouth of the Jeneberang River in 2005, development has expanded to the south. An earliest improvement of the Tj.Bunga - Takalar Road (Lintas Barat) is recommended to regulate the sprawled urban development in the area.
- 2) This road link constitutes one of the radial roads (south radial road) in the Mamminasata Urban Arterial Road Network System and it connects the Galesong Port in Takalar. It is recommended to upgrade this road status from Kabupaten road to provincial road as it connects Makassar City to Takalar (Capital of Takalar Regency) along the west coast.
- 3) This road will be an alternative route of the Trans-Sulawesi Road from/to Makassar City to/from the southern part of South Sulawesi Province and contribute to reducing the traffic jam at Sungguminasa.
- 4) As the economic analysis has shown a very high EIRR of 41.4%, it is recommended that the Project be implemented for the benefit of national and regional economy
- 5) Financing for the project implementation should be made by both provincial and central governments since this is an arterial road of the Mamminasata Metropolitan Area.

# 11.4 Recommendation on Establishment of Coordination Committee for Project Implementation of the F/S Roads

The Study Team understands that good cooperation and coordination between the central governments (Bappenas, MOF and MPW) and regional governments (South Sulawesi Province, Makassar City and Regencies of Maros, Gowa and Takalar) are very important for implementation of the F/S road projects as these are part of the arterial road network for the Mamminasata Metropolitan Area.

The Study Team recommends establishment of a "Project Implementation Committee for Arterial Road Network Development for the Mamminasata Metropolitan Area". The committee, comprised of the representatives of concerned central and regional governments, holds periodic meetings for monitoring progress of the project implementation, discusses on problems and measures to solve and takes required actions for smooth implementation of the projects.