



BR-34 EMANG BRIDGE







1 ELEVATION
SCALE 1:100




2 PLAN
SCALE 1:100



3 KEY PLAN
SCALE 1:100




4 SECTION @ S1, P1 & S2
SCALE 1:50




5 SECTION @ C1-C6
SCALE 1:50

	DIRECTORATE GENERAL OF HIGHWAY MINISTRY OF PUBLIC WORKS THE REPUBLIC OF INDONESIA		JAPAN INTERNATIONAL COOPERATION AGENCY		THE BASIC DESIGN STUDY ON THE PROJECT FOR CONSTRUCTION OF BRIDGES IN THE PROVINCE OF NUSA TENGGARA BARAT PHASE 2 IN THE REPUBLIC OF INDONESIA	TITLE: BR-34 EMANG BRIDGE GEN. DIM. OF SUPERSTRUCTURE	SCALE: AS SHOWN	DRAWING No: 14-3	Rev.
--	---	--	--	--	--	---	--------------------	---------------------	------




1 PLAN
SCALE 1:500


§ OF ROADWAY



2 ELEVATION
SCALE 1:500




3 ELEVATION
SCALE 1:500




4 ELEVATION
SCALE 1:500


	DIRECTORATE GENERAL OF HIGHWAY PUBLIC WORKS THE REPUBLIC OF INDONESIA	JAPAN INTERNATIONAL COOPERATION AGENCY	KATAHIRA & ENGINEERS INTERNATIONAL	THE BASIC DESIGN STUDY ON THE PROJECT FOR CONSTRUCTION OF BRIDGES IN THE PROVINCE OF NUSA TENGGARA BARAT PHASE-2 IN THE REPUBLIC OF INDONESIA	TITLE: BR-34 EMANG BRIDGE SUBSTRUCTURE STRUCTURAL DIMENSION (ABUTMENT A1 & A2)	SCALE: AS SHOWN	DRAWING NO: 14-4	Rev.
--	---	--	---------------------------------------	--	--	--------------------	---------------------	------




1 PLAN
SCALE 1:50
C OF ROADWAY



2 ELEVATION
SCALE 1:50




3 ELEVATION
SCALE 1:50



4 ELEVATION
SCALE 1:50

	DIRECTORATE GENERAL OF HIGHWAY MINISTRY OF PUBLIC WORKS THE REPUBLIC OF INDONESIA		JAPAN INTERNATIONAL COOPERATION AGENCY		KATAHIRA & ENGINEERS INTERNATIONAL	TITLE: 20 BR-34 EMANG BRIDGE SUBSTRUCTURE STRUCTURAL DIMENSION (PIER P1) SCALE: AS SHOWN DRAWING No: 14-5 Rev.
--	---	--	--	--	---------------------------------------	---



DIRECTORATE GENERAL OF HIGHWAY
 MINISTRY OF PUBLIC WORKS
 THE REPUBLIC OF INDONESIA



JAPAN INTERNATIONAL COOPERATION AGENCY



KATAHIRA & ENGINEERS
 INTERNATIONAL

THE BASIC DESIGN STUDY ON THE PROJECT FOR
 CONSTRUCTION OF BRIDGES IN THE PROVINCE
 OF NUSANTARA BARAT, PHASE-2
 IN THE REPUBLIC OF INDONESIA


TITLE:
 EMANG BRIDGE
 APPROACH ROAD CROSS SECTIONS


SCALE:
 1:400

DRAWING No:
 14-7


Rev.

BR-35 KALBIR BRIDGE







1 ELEVATION
SCALE 1:100




2 PLAN
SCALE 1:100



3 KEY PLAN
SCALE 1:100



4 SECTION @ S1 & S2
SCALE 1:50



5 SECTION @ C1-C3
SCALE 1:50



DIRECTORATE GENERAL OF HIGHWAY
MINISTRY OF PUBLIC WORKS
THE REPUBLIC OF INDONESIA



JAPAN INTERNATIONAL COOPERATION AGENCY



KATAHIRA & ENGINEERS
INTERNATIONAL


THE BASIC DESIGN STUDY ON THE PROJECT FOR
CONSTRUCTION OF THE FIRST PROVINCE
OF NUSA TENGGARA BARAT PHASE-2
IN THE REPUBLIC OF INDONESIA


TITLE:
BR-35 KALBIR BRIDGE
GEN. DIM. OF SUPERSTRUCTURE


SCALE:
AS SHOWN

DRAWING No:
15-3


Rev.














DETAILS OF STANDARD STRUCTURES













1 GROUTED RIPRAP SLOPE PROTECTION
SCALE 1:100




3 GABION MATTRESS
SCALE NOT TO SCALE


SCHEDULE OF REINFORCEMENT				
BAR NO.	BAR SIZE	QTY.	UNIT WT. PER BAR	TOTAL WT.
1	16	1,432	2.09	2,992.88
2	16	0.523	2.09	1.093.07
3	16	43.42	6	260.52
				TOTAL = 25,415kg



2 STONE MASONRY DITCH
SCALE 1:20



5A ELEVATION
SCALE 1:50



5B SECTION
SCALE 1:10


5 GUIDE POST
SCALE AS SHOWN

QUANTITY PER GUIDE POST	
CONCRETE CLASS "A"	0.038 m ³
BAR # 10	28.5 kg
BAR # 8	11.2 kg


NOTE: THE GUIDE POST SHALL BE INSTALLED AT INTERVALS INDICATED IN THE SITE DEVELOPMENT PLANS

NOTE: THE GABION MESH AND BOLLERS SHALL COMPLY WITH THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS FOR GABION MATTRESS AND CYLINDRICAL GABION SHALL BE PLACED ON GEOTEXTILE FABRIC.


	DIRECTORATE GENERAL OF HIGHWAY MINISTRY OF PUBLIC WORKS THE REPUBLIC OF INDONESIA	JICA JAPAN INTERNATIONAL COOPERATION AGENCY	K&E KATAHIRA & ENGINEERS INTERNATIONAL	TITLE: STANDARD DRAWINGS RIPRAP PROTECTION, GABION STONE MASONRY DITCH & GUIDE POST	SCALE: AS SHOWN	DRAWING No: 16-6	Rev.
--	---	--	--	--	--------------------	---------------------	------



3 TYPICAL PLAN OF BRIDGE APPROACH
SCALE 1:100




4 TYPICAL SECTION OF BRIDGE APPROACH
SCALE 1:100



MACADAM PAVEMENT SECTION

1 APPROACH ROAD TYPICAL SECTION
SCALE 1:100



AGGREGATE SURFACE SECTION

2 APPROACH ROAD TYPICAL SECTION
SCALE 1:100

DIRECTORATE GENERAL OF HIGHWAY
MINISTRY OF PUBLIC WORKS
THE REPUBLIC OF INDONESIA

JICA
JAPAN INTERNATIONAL COOPERATION AGENCY

KATAHIRA & ENGINEERS
INTERNATIONAL


THE BASIC DESIGN STUDY ON THE PROJECT FOR
CONSTRUCTION OF BRIDGES IN THE PROVINCE
OF NUSA TENGGARA BARAT, PHASE 2
IN THE REPUBLIC OF INDONESIA

TITLE:
STANDARD DRAWINGS
TYPICAL APPROACH ROAD SECTION


SCALE:
1 : 100

DRAWING NO:
16-7


Rev.



1. LONGITUDINAL SECTION - TONGUE & GROOVE TYPE
SCALE: TO NOT



A. TWO LINES OF CIRCULAR REINFORCEMENT
SCALE: TO NOT




B. ONE LINE OF CIRCULAR REINFORCEMENT
SCALE: TO NOT


STANDARD STRENGTH REINFORCED CONCRETE CULVERT											
CONCRETE 3,500 PSI (24.1 MPa)						CONCRETE 4,500 PSI (31.0 MPa)					
SIZE WALL THICKNESS	TONGUE	GROOVE	MINIMUM REINFORCEMENT PER LINEAR M. OF PIPE BARREL	WALL THICKNESS	TONGUE	GROOVE	MIN. REIN. PER LINEAR M. OF PIPE BARREL	WALL THICKNESS	TONGUE	GROOVE	THREE-EDGE BEARING METHOD
I.D.	A	B	C	E	P	W	A	B	C	E	P
810	77	873	527	885	689	45	1 LINE 350	1 LINE 350	1 LINE 350	1 LINE 424	4473
910	102	1064	527	1011	1035	84	2 LINES 381	2 LINES 381	2 LINES 448	2 LINES 448	6939

THE DISTANCE FROM THE CENTER LINE OF THE REINFORCEMENT TO THE NEAREST SURFACE OF THE CONCRETE IS ASSUMED AS 32mm. FOR PIPES WITH SHELL THICKNESS OF 84mm. OR MORE TEST-LOAD FOR SAND BEARING TEST SHALL BE ONE AND A HALF TIMES THOSE SPECIFIED IN THIS TABLE FOR THREE-EDGE-BEARING TEST.


STANDARD CONCRETE PIPE COLLAR	
PIPE DIAMETER (mm)	REBAR (kg)
810	0.656
910	1.056
	12.5




2a. PIPE COLLAR AT BEND DETAILS
SCALE: TO NOT



2b. SECTION
SCALE: TO NOT




TONGUE END
GROOVE END



3. TRENCHING AND BEDDING DETAILS
SCALE: TO NOT


TYPICAL DETAIL DESIGN (STEEL BRIDGE)





NOTES:


1. ALL MATERIALS SHALL BE SH400A UNLESS OTHERWISE NOTED.
2. SCALLOP NOT MENTIONED SPECIALLY IS ASSUMED TO BE R35
3. THE SIGN SHOWS HIGH TENSILE STRENGTH BOLT M22(RBT)
4. A DETAILED EACH PART MUST REFER TO "GIRDER DETAIL"


 DIRECTORATE GENERAL OF HIGHWAY MINISTRY OF PUBLIC WORKS THE REPUBLIC OF INDONESIA	 JAPAN INTERNATIONAL COOPERATION AGENCY	 KATAHIRA & ENGINEERS INTERNATIONAL	TITLE: BR-16 TELONGANG I BRIDGE INTERM. CROSS BEAM DETAILS (1 of 2)		SCALE: AS SHOWN	DRAWING NO: 17-3	Rev.
			THE BASIC DESIGN STUDY ON THE PROJECT FOR CONSTRUCTION OF BRIDGES IN THE PROVINCE OF NUSA TENGGARA BARAT, PHASE-2 IN THE REPUBLIC OF INDONESIA				












DIRECTORATE GENERAL OF HIGHWAY
MINISTRY OF PUBLIC WORKS
THE REPUBLIC OF INDONESIA



JAPAN INTERNATIONAL COOPERATION AGENCY




KATAHIRA & ENGINEERS
INTERNATIONAL

TITLE:
THE BASIC DESIGN STUDY ON THE PROJECT
FOR THE IMPROVEMENT OF BRIDGES IN NIAS ISLAND
IN THE REPUBLIC OF INDONESIA


SCALE:
AS SHOWN

DRAWING No:
17-8


Rev.



7 SECTION
SCALE 1:50



8 SECTION
SCALE 1:50




9 SECTION
SCALE 1:50

1 ABUTMENT DETAIL
SCALE 1:50




W2-1 9-#16 x 5348




W3-2 1-#16 x 5348



W4-1 9-#16 x 5348



W5-2 1-#16 x 5348



W6-2 1-#16 x 5348



W7-10-#13 x 2189


W8-10-#13 x 2189




W9-23-#19 x 5400



W14-9-#16 x 3652



W15-9-#16 x 3787



W19-9-#16 x 3852

W23-9-#16 x 3852

W29-9-#16 x 3852

W33-9-#16 x 3852

W37-9-#16 x 3852

W41-9-#16 x 3852

W45-9-#16 x 3852

W49-9-#16 x 3852

W53-9-#16 x 3852

W57-9-#16 x 3852

W61-9-#16 x 3852

W65-9-#16 x 3852

W69-9-#16 x 3852

W73-9-#16 x 3852

W77-9-#16 x 3852

W81-9-#16 x 3852

W85-9-#16 x 3852

W89-9-#16 x 3852

W93-9-#16 x 3852

W97-9-#16 x 3852

W101-9-#16 x 3852

W105-9-#16 x 3852

W109-9-#16 x 3852

W113-9-#16 x 3852

W117-9-#16 x 3852

W121-9-#16 x 3852

W125-9-#16 x 3852

W129-9-#16 x 3852

W133-9-#16 x 3852

W137-9-#16 x 3852

W141-9-#16 x 3852

W145-9-#16 x 3852

W149-9-#16 x 3852

W153-9-#16 x 3852

W157-9-#16 x 3852

W161-9-#16 x 3852

W165-9-#16 x 3852

W169-9-#16 x 3852

W173-9-#16 x 3852

W177-9-#16 x 3852

W181-9-#16 x 3852

W185-9-#16 x 3852

W189-9-#16 x 3852

W193-9-#16 x 3852

W197-9-#16 x 3852

W201-9-#16 x 3852

W205-9-#16 x 3852

W209-9-#16 x 3852

W213-9-#16 x 3852

W217-9-#16 x 3852

W221-9-#16 x 3852

W225-9-#16 x 3852

W229-9-#16 x 3852

W233-9-#16 x 3852

W237-9-#16 x 3852

W241-9-#16 x 3852

W245-9-#16 x 3852

W249-9-#16 x 3852

W253-9-#16 x 3852

W257-9-#16 x 3852

W261-9-#16 x 3852

W265-9-#16 x 3852

W269-9-#16 x 3852

W273-9-#16 x 3852

W277-9-#16 x 3852

W281-9-#16 x 3852

W285-9-#16 x 3852

W289-9-#16 x 3852

W293-9-#16 x 3852

W297-9-#16 x 3852

W301-9-#16 x 3852

W305-9-#16 x 3852

W309-9-#16 x 3852

W313-9-#16 x 3852

W317-9-#16 x 3852

W321-9-#16 x 3852

W325-9-#16 x 3852

W329-9-#16 x 3852

W333-9-#16 x 3852

W337-9-#16 x 3852

W341-9-#16 x 3852

W345-9-#16 x 3852

W349-9-#16 x 3852


W353-9-#16 x 3852

W357-9-#16 x 3852

W361-9-#16 x 3852

W365-9-#16 x 3852

W369-9-#16 x 3852



DIRECTORATE GENERAL OF HIGHWAY
MINISTRY OF PUBLIC WORKS
THE REPUBLIC OF INDONESIA



JAPAN INTERNATIONAL COOPERATION AGENCY




KATAHIRA & ENGINEERS
INTERNATIONAL

TITLE:
BR-16 TELONANG I BRIDGE
PIER P1 REINFORCEMENT DETAILS (1 of 3)

SCALE:
AS SHOWN

DRAWING No:
17-10

Rev.



DIRECTORATE GENERAL OF HIGHWAY
ENGINEERING
THE REPUBLIC OF INDONESIA



JAPAN INTERNATIONAL COOPERATION AGENCY



KATAHIRA & ENGINEERS
INTERNATIONAL


THE BASIC DESIGN STUDY ON THE PROJECT FOR
CONSTRUCTION OF BRIDGES IN THE PROVINCE
OF NUSA TENGGARA BARAT, PHASE-2
IN THE REPUBLIC OF INDONESIA

TITLE :
BR-16 TELONGANG I BRIDGE
PIER P1 REINFORCEMENT DETAILS (2 of 3)


SCALE :
AS SHOWN


DRAWING NO :
17-11


Rev.




TYPICAL DETAIL DESIGN (RC BRIDGE)








Rev.	18-3	AS SHOWN	SCALE:	DRAWING NO:
JICA	DIRECTORATE GENERAL OF HIGHWAY MINISTRY OF PUBLIC WORKS THE REPUBLIC OF INDONESIA	JAPAN INTERNATIONAL COOPERATION AGENCY	KATAHIRA & ENGINEERS INTERNATIONAL	TITLE:
				BR-32 PETAIN II BRIDGE GIRDER ELEVATION, BOTTOM BAR LAYOUT & SECTION (1 of 2)




1A ELEVATION
SCALE 1:30




1B SECTION
SCALE 1:10


1 INTERMEDIATE DIAPHRAGM DETAIL
SCALE AS SHOWN




(D1) 2-#29 x 8150



(D3) 8-#16 x 5820



(D2) 2-#29 x 8092



(D4) 28-#12 x 2810

SCHEDULE OF REINFORCEMENT					
BAR MARK	BAR SIZE	BAR LENGTH	QTY.	UNIT WT. PER BAR	TOTAL WT.
D1	D-29	8.150	2	5.165	42.254
D2	D-29	8.092	2	5.165	41.953
D3	D-16	5.820	8	1.578	9.185
D4	D-12	2.810	28	0.888	2.484
SD-40 TOTAL=					311.74kg

QUANTITIES FOR 1 WINDOW ONLY



DIRECTORATE GENERAL OF HIGHWAY
MINISTRY OF PUBLIC WORKS
THE REPUBLIC OF INDONESIA



JAPAN INTERNATIONAL COOPERATION AGENCY



KATAHIRA & ENGINEERS
INTERNATIONAL


THE BASIC DESIGN STUDY ON THE PROJECT FOR
CONSTRUCTION OF BRIDGE AT PHASE-2
OF NUSA TENGGARA BARAT PROVINCE
IN THE REPUBLIC OF INDONESIA


TITLE:
BR-32 PETAIN III BRIDGE
DIAPHRAGM DETAILS

SCALE:
AS SHOWN

DRAWING No:
18-5

Rev.





SCHEDULE OF REINFORCEMENT

BAR MARK	BAR SIZE	LENGTH BAR	QTY.	UNIT	WT. BAR	TOTAL WT.
A1a	D-25	7.067	59	3.853	27.23	1606.52
A1b	D-22	5.750	59	2.884	17.16	1012.32
A1c	D-19	5.646	10	2.226	12.57	125.68
A2	D-16	9.272	54	1.578	14.63	780.02
A3	D-16	2.428	80	1.578	3.83	344.72
A4	D-16	1.100	28	1.578	1.74	48.72
A5	D-16	7.400	4	1.578	11.68	46.72
A6	D-16	1.650	28	1.578	2.60	72.80
F1	D-25	5.650	59	3.853	21.77	1284.43
F2	D-19	5.780	59	2.226	12.87	759.33
F3	D-16	8.650	21	1.578	13.05	286.65
F4	D-16	8.650	21	1.578	13.05	286.65
F5	D-19	7.772	4	2.226	21.53	86.20
F6	D-16	5.760	4	2.226	17.30	51.48
F7a	D-16	1.524	28	1.578	2.40	67.20
F7b	D-16	1.274	30	1.578	2.01	60.30
SD-40 TOTAL = 6912.72 Kg.						

QUANTITIES ARE FOR 1 ABUTMENT ONLY



DIRECTORATE GENERAL OF HIGHWAY
MINISTRY OF PUBLIC WORKS
THE REPUBLIC OF INDONESIA



JAPAN INTERNATIONAL COOPERATION AGENCY




THE BASIC DESIGN STUDY ON THE PROJECT FOR
CONSTRUCTION OF BRIDGES IN THE PROVINCE
OF NUSA TENGGARA BARAT, PHASE-2
IN THE REPUBLIC OF INDONESIA

TITLE:
BR-32 PETAIN III BRIDGE
ABUT. A1 & A2 REINF. DETAILS (2 of 2)

SCALE:
AS SHOWN

DRAWING NO:
18-7

Rev.



2.2.4 Implementation Plan

2.2.4.1 Implementation Policy

(1) Basic Condition of the Project Implementation

The basic conditions for the project implementation are as follows:

- This project, if approved, will be implemented in accordance with the Japan's grant scheme after the signing of the Exchange of Notes between the Government of Japan and the Government of Indonesia.
- The Directorate General of highway of the Ministry of Public Works is responsible for implementing the Project.
- The detailed design, assistance in tendering and construction supervision of the project will be undertaken by a Japanese consulting firm in accordance with a contract between the Ministry of Public Works and the consulting firm.
- The construction will be undertaken by a successful Japanese tenderer who wins the contract with the Ministry of Public Works.

(2) Implementation Policy

Implementation Schedule

- The project will be implemented in two stages. The construction of the 4 bridges located in the road section between Tongoloka (the west side as the starting point of the Project road) and Sta. 17 km of the Project road is scheduled to be implemented in the earlier stage (Phase 2) since the Ministry of Public Works jointly with the Provincial Government of Nusa Tenggara Barat are executing the improvement work of this 17 km road section. And the work has been scheduled to be completed in December 2008. The construction of the remaining 11 bridges located in the Project road section from Sta. 17 km to Lunyuk (the end point of the Project road) is scheduled to be implemented in the latter stage (Phase 3) since the improvement work of this road section has been scheduled to be completed in December 2010. The Phase 3 will be implemented in accordance with the progress of the road improvement to be undertaken by the Indonesian side. (The schedule of the project road improvement by the Indonesian side is shown in Appendix-4)

Construction Planning

- Construction methods and schedules are planned with consideration of local natural conditions such as climate, topography, geology and hydrology.
- Common methods which do not require special equipment and technique are planned.
- Constructability and safety are considered in the construction planning.
- Full attention is paid to the environmental preservation during the construction.
- Temporary detours are provided if necessary for public traffic.

Construction supervision planning

- Appropriate technical specifications and quality control requirements are established and included in the contract documents.
- Organization of construction management by a contractor and construction supervision by a consultant are planned to meet the standardized construction management requirements.
- Counter-measures for preventing accidents are secured.

Material procurement planning

- All materials, equipments and laborers required for the project are procured from Indonesia.
- The materials and equipment for the Project are planned in transportable size and specifications since the transportation route condition is bad and trailer truck is not possible to transport them.
- Cost efficiency is considered in selection of materials and equipment and construction planning.

2.2.4.2 Implementation Condition

(1) Safety Measure

Safety measures should be established to prevent accident in the construction.

Accidents prone to happen in bridge construction

- Falling down of girder : Breaking of hangers, overturning of crane are major cause
- Scaffolding / support collapse: Inadequate support or soil strength is major cause
- Excavation slope failure: lack of support, inadequate strength of support are major cause
- Falling down of worker: Lack or ignorance of using safety device is major cause

Safety measure in construction site

- Safety officers are deployed
- Construction plan including temporary works is submitted and checked.
- Works are checked whether they are compliant with the construction plan.
- Construction plan is informed to all related persons.
- Action should be taken when failure and accident happen.

Safety measure in transportation

- Safety seminars are given to drivers.
- Driving at night should be avoided.
- Transportation plans are submitted and checked.

(2) Transportation Condition

Transportable construction equipment

The Project road passes through steep mountains and there are many road sections steeper than 15% and sharp curves with radius less than 15 m. Semi-trailer may not pass through such substandard road sections. As the result, crawler type equipments are not available for the Project since only semi-trailer can carry such equipment. Only small-sized construction equipments transportable by trucks or self-propelled equipment are possible to be procured.

Transportation through sea route

Padas Port in Sumbawa Besar has enough capacity for landing large-sized goods. However, there are mountainous road sections between the port and the Project site that makes transportation of large-sized materials and equipment by semi-trailer difficult. Instead, a landing craft is available, as it was used in Phase 1 project, for transportation of large-sized materials such as reinforcing bars, steel girders and large construction equipments from Jakarta to a beach close to the Project site.

(3) Construction Sequence of Integral Type Bridges

Integral type bridges should be constructed with the sequences similar to what was assumed in the design analysis and constructed symmetrically. Additionally the concrete pouring sequences should be planned so as to avoid cracking due to deformation caused by the weight of subsequent concrete pouring. The construction sequences should be clearly instructed in the construction plans and the construction should be executed in accordance with the instructions.

(4) Pile Driving Method

Usually steel tubular piles are driven by a diesel hammer held by a crawler crane. Since crawler crane is difficult to procure for this project, rafterrain crane (self-propelled wheel type crane) is scheduled to be used for the pile driving, instead. Vibratory hammer is used for around 7 m preliminary pile driving until the piles stand stably on the ground.

(5) Temporary Detour Road

Temporary detour roads for public traffic and for construction vehicles are planned for the bridges which are planned to be constructed on the existing road. The temporary detour roads plan is shown in Appendix 9.

(6) Observance of UKL & UPL

UKL & UPL approved by BEPEDALDA and the Recommendation from BAPEDALDA should be observed in the construction of the project bridges. And periodical monitoring reports should be prepared and submitted to the concerned agencies. The major contents of the UKL & UPL are as shown in Table 2.2-9.

Table 2.2-9 Major Contents of UKL&UPL

The major items of environmental impact management to be taken in the construction of project bridges are as follows.	
1. Land acquisition	The forest land owned by regency can be used for the project without compensation. However, private land and trees should be compensated based on the deliberated rate in accordance with laws and regulations.
2. Employment opportunity creation	Local manpower should be maximum utilized. Wage should referred to regency minimum wage. Training is given to laborers to improve their skills.
3. Air and noise pollution mitigation	To water routinely on the dusty roads, install dust-collector of plant if necessary, secur distance of base camp from residential area, regulate vehicle speed slower than 40 km/hr and ban overtime work. To clear and vegitate the area where camps were.
4. Riverwater pollution prevention	To treat polluted water properly, discharge muddy water after clearing, install septic tanks for every camps and treat rubbish properly but not to dump directly.
5. Soil pollution prevention	To store fuel and oil in a storage, collect waste oil then send to oil treatment plant, collect spilled oil immediately before it discharges to the river by rainwater and treat toxic and hazardous substances in accordance with law and regulation.
6. Traffic control and safety	To install flag man for transporting heavy equipments, hold safety campaign for students, install warning signs and traffic safety signs and regulate max driving speed to be 40 km/hr.
7. Accident prevention	To let workers wear safety devices (helmet, musk, earplug, safety shoe, goggle, etc.)
8. Health control	To manitain camp sanitary and prevent malaria and hemorrhagic fever by covering breeding spots and fill water ponds.
9. Road damage	To limit the size and weigh of heavy equipments which are to use the road and repair the road immediately when damaged.
10. Disruption of utility	To relocate power poles, coordinate with regency government and Sumbawa Electric Enterprise (PLN).
11. Gravel quarring	To ban quarring river gravel within 500m from any bridge.
12. Preservation of forest	To ban fire, cut trees, hunting animals in the forest, and install sign boards of these information.
13. Post construction environmental management	To ban construcion buildings close to bridges and control traffic operation.

2.2.4.3 Scope of Works

Responsibilities of both Japanese and Indonesian governments are shown on Table 2.2-10.

Table 2.2-10 Responsibilities of Both Governments

Items	Contents	Undertaken by		Remarks
		Japan	Indonesia	
Procurement of materials and equipment	Procurement and delivery	○		
Preparation work	Improvement of Project road		○	
	Construction of bridges excluded from Japan's grant		○	
	Acquisition of lots for construction		○	
	Leasing temporary work areas		○	For detour, camp, work yards
	Securing borrow pit and disposal area		○	
	Relocation/removal of construction obstacles		○	
	Other preparation work	○		
Construction works	Bridge construction	○		

2.2.4.4 Construction Supervision Plan

A Japanese consultant will carry out the detailed design, assistance in tendering and construction supervision in accordance with the contract between the Ministry of Public Works and the consultant.

(1) Detailed Design

Major works in the detailed design to be carried out by the consultant are as follows:

Detailed Design

- Commencement meeting with the Directorate General of Highways and site survey
- Detailed design and preparation of drawings
- Quantity calculation and cost estimate

The time required for the detailed design is estimated 3 months for Phase 2 and 1.5 months for Phase 3.

(2) Assistance in Tendering

Major items of the services in the assistance in tendering are as follows:

- Preparation of tender documents (conducted simultaneously with the detailed design)

- Tender publication
- Pre-qualification
- Assistance in tendering
- Tender evaluation
- Contract facilitation

The time required for the assistance in tendering is estimated 3.5 months for Phase 2 and 3 months for Phase 3.

(3) Construction Supervision

The consultant will carry out the supervision of the construction works executed by the contractor. Major items of the construction supervision are as follows:

- Inspection and approval of site survey
- Inspection and approval of construction plan
- Quality control
- Progress control
- Measurement of work
- Inspection of safety aspects
- Management of environmental UKL&UPL
- Final inspection and hand-over

The required construction period is estimated 15 months for Phase 2 and 20.5 months for Phase 3.

For the construction supervision, a Japanese-national engineer is required to be stationed on the site. Additionally, an Indonesian engineer is planned to be stationed on the site.

2.2.4.5 Quality Control Plan

Quality control plan for concrete work, earthwork and pavement work and plate girder fabrication work are shown on Table 2.2-11 to Table 2.2-13, respectively.

Table 2.2-11 Quality Control Plan for Concrete Work

Item	Test	Test Method (Specification)	Frequency of Test
Cement	Physical property test	AASHTO M85	Once before trial mix. Thereafter, once every 500 m ³ concreting or when the material brand is changed.
Fine aggregate	Physical property test	AASHTO M6	Once before trial mix. Thereafter, once every 500m ³ concreting or when supplying place is changed (with confirmation of the supplier's data).
	Sieve analysis	AASHTO T27	Once a month.
Coarse aggregate	Physical property test	AASHTO M80	Once before trial mix. Thereafter, once every 500m ³ concreting or when the material source is changed (with confirmation of the supplier's data).
	Sieve analysis	AASHTO T27	Once a month.
Water	Quality test	AASHTO T26	Once before trial mix.
Concrete	Slump test	AASHTO T119	Twice a day
	Air content test	AASHTO T121	Twice a day
	Compressive strength test	AASHTO T22	6 specimens per placement or 6 specimens per 75 m ³ when concrete volume in one placement is big (3 specimens for 7 days strength test and 3 specimens for 28 days strength test).
	Temperature	—	Twice a day
	Salinity test	—	Twice a day

Table 2.2-12 Quality Control Plan for Earthwork and Pavement Work

Item	Test	Test Method (Specification)	Frequency of Test
Embankment	Density test (compaction test)	AASHTO T191	Once every 500 m ³
Base course	Site density test (compaction test)	AASHTO T191	Once every 1,000 m ³
	Sieve analysis	AASHTO T27	Once every 500m ³
Asphalt pavement	Temperature of asphalt mixture	-	5 times a day.
	Abrasion	AASHTO T96	Once every 1,500m ³ or when the material source is changed (with confirmation of the supplier's data).

Table 2.2-13 Quality Control Plan for Plate Girder Fabrication Work

Item	Test	Test Method (Specification)	Frequency of Test
Steel plate	Mill sheet quality test	JISG3101	Before work
High tensile bolt	Mill sheet quality test	JISB0205/Z2201	Before work
Galvanizing	Weighing test	JISH0401	Every work
Welding	X-ray radio graphic flaw detection, Liquid penetration test	JISG3106	Every work
Shop assembly	Japanese Road Association Specifications	JISG3101	Every bridge
Fabrication factory	ISO 9001 Certified Factory		

2.2.4.6 Procurement Plan

All construction materials and equipments necessary for the Project are available in Indonesia. Equipments owned by local contractors will be rented for the project. The material and equipment procurement plan is shown on Table 2.2-14.

Table 2.2-14 Material and Equipment Procurement Plan

Item	Procured from			Remarks
	Indonesia	Japan	Third Country	
<u>Construction Materials</u>				
Crushed stone	○			
Cement	○			
Sand	○			
Boulder	○			
Aggregate	○			
Asphalt	○			
Reinforcing bar	○			
Concrete additives	○			
Steel girder	○			
Gabion	○			
Steel tubular pile	○			
Guardrail	○			
Timber	○			
Plywood	○			
Timber support	○			
Fuel, oil	○			
<u>Equipments</u>	○			
Bulldozer	○			
Backhoe	○			
Hydraulic clamshell	○			
Dump truck	○			
Crane mounted truck	○			
Loader	○			
Diesel hammer	○			
Vibratory hammer	○			
Breaker	○			
Motor grader	○			
Road roller	○			
Tire roller	○			
Vibratory roller	○			
Tamper	○			
Concrete mixing plant	○			
Truck mixer	○			
Asphalt kettle	○			
Water tanker	○			

2.2.4.7 Implementation Schedule

The implementation schedule of the Project is shown on Table 2.2-15.

Table 2.2-15 Implementation Schedule

Stage	Item	Month	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23
Phase 2	Design	Detailed desing				(Total 3 months)																			
		Tendering								(Total 3.5 months)															
	Construction	Preparation																							
		BR-1 Air Keruh I																							
		BR-2 Air Keruh II																							
		BR-3 Negene I																							
		BR-8 Tatar Loka																							
	Demobilization																								
Phase 3	Design	Detailed desing				(Total 1.5 months)																			
		Tendering								(Total 3 months)															
	Construction	Preparation																							
		BR-13 Mone I																							
		BR-16 Telonang I																							
		BR-19 Sepang																							
		BR-20 Bontong																							
		BR-22 Blengkon																							
		BR-27 Lamar																							
		BR-29 Liang Bagik																							
		BR-32 Petain III																							
		BR-33 Molong																							
		BR-34 Emang																							
		BR-35 Kalbir																							
	Demobilization																								