

**MINISTRY OF AGRICULTURE
PALESTINIAN WATER AUTHORITY
PALESTINIAN NATIONAL AUTHORITY**

**THE FEASIBILITY STUDY
ON
WATER RESOURCES DEVELOPMENT AND MANAGEMENT
IN
THE JORDAN RIVER RIFT VALLEY**

FINAL REPORT

**VOLUME-I
MAIN REPORT**

DECEMBER 2008

JAPAN INTERNATIONAL COOPERATION AGENCY

NIPPON KOEI CO., LTD.

**THE FEASIBILITY STUDY
ON
WATER RESOURCES DEVELOPMENT AND MANAGEMENT
IN
THE JORDAN RIVER RIFT VALLEY**

FINAL REPORT

LIST OF VOLUMES

VOLUME-I MAIN REPORT

VOLUME-II ANNEXES-A

ANNEX 1	HYDROLOGY
ANNEX 2	HYDROGEOLOGY
ANNEX 3	STORM WATER HARVESTING

VOLUME-III ANNEXES-B

ANNEX 4	SPRINGS
ANNEX 5	AGRICULTURAL WELLS

VOLUME-IV ANNEXES-C

ANNEX 6	PILOT PROJECTS
ANNEX 7	SOCIO-ECONOMY
ANNEX 8	ON-FARM WATER MANAGEMENT
ANNEX 9	ENVIRONMENTAL ASSESSMENT
ANNEX 10	GIS DATABASE
ANNEX 11	PROJECT EVALUATION

PREFACE

In response to the request from the Palestinian National Authority (PNA), the Government of Japan decided to conduct the Feasibility Study on Water Resources Development and Management in the Jordan River Rift Valley and entrusted the study to the Japan International Cooperation Agency (JICA).

JICA selected and dispatched a study team headed by Mr. Kunio GOTO of Nippon Koei Co., Ltd. during the period from March 2007 to December 2008.

The team conducted the study with the counterpart agencies and held a series of discussions with the officials concerned of PNA. Upon returning to Japan, the team conducted further studies and prepared this final report.

I hope that this report will contribute to the promotion of the project for water resources development project and to the realization of the concept of “Corridor for Peace and Prosperity”.

Finally, I wish to express my sincere appreciation to the officials concerned of PNA for their close cooperation extended to the study.

December 2008

Ariyuki MATSUMOTO

Vice President

Japan International Cooperation Agency

December 2008

Mr. Ariyuki MATSUMOTO
Vice President
Japan International Cooperation Agency
Tokyo, JAPAN

LETTER OF TRANSMITTAL

Dear Sir,

We are pleased to submit herewith the Final Report of the Feasibility Study on Water Resources Development and Management in the Jordan River Rift Valley. The Final Report was prepared based on the results of the Study conducted during the period from March 2007 to December 2008.

The objectives of the Study are to: i) formulate a basic plan for efficient utilization of water for agriculture in the Jordan River Rift Valley; ii) formulate a basic plan for water resources development in the Jordan River Rift Valley; and iii) carry out technology transfer to Palestinian counterpart personnel through on-the-job training during the course the Study.

In the Phase 1 from March 2007 to December 2007, the basic plans for improvement of spring water conveyance system and rehabilitation and integrated management of agricultural wells were formulated for efficient utilization of water for agriculture in the Study Area. And the prospective plan for storm water harvesting was proposed for water resources development.

Two types of pilot projects, namely the rehabilitation and integrated management of agricultural wells and the improvement of spring water conveyance system, were implemented during the Phase 2 from January 2008 to December 2008 to verify efficiency and effectiveness of the basic plans. Major lessons learned from the pilot projects were reflected upon the basic plans. The Feasibility Study was conducted for the priority schemes selected in the basic plans.


The Study was performed based on continual partnership of the Ministry of Agriculture and the Palestinian Water Authority as well as the Ministry of Planning, the Environment Quality Authority, farmers and other stakeholders. Their opinions and intentions were, therefore, incorporated in the plans.

We hope that the report would contribute to efficient utilization of water for agriculture and the water resources development and management in the Study Area.

We would like to express our deep appreciation a sincere gratitude to all the officials who extended their extensive assistance and cooperation to the JICA Study Team, in particular the Ministry of Agriculture and the Palestinian Water Authority. We also acknowledge the officials of your agency and Embassy of Japan in Israel for their support and valuable advices in the course of the Study.

Very truly yours,

Kunio GOTO
Team Leader of the JICA Study Team for
the Feasibility Study on Water Resources
Development and Management in the
Jordan River Rift Valley



LOCATION MAP

PHOTOGRAPHS



**Jordan River Rift Valley
(View from Mt. Temptation)**



**Agricultural Products
(Morning Bazaar in the Jericho City)**



**Steering Committee Meeting
(April 3rd, 2007)**



**Seminar on Water Resources Development and
Management (May 28th, 2008)**



**Formation of WUA
(Rehabilitation of Agricultural Wells)**



**On-farm Water Management Training
(Rehabilitation of Agricultural Wells)**

PHOTOGRAPHS



Cleaning and Deepening
(19-17/047, Frush bet dajan)



Installation of Pump Equipment
(19-19/005A, Ein Al Byhda)



Before Rehabilitation
(19-17/054, Jiftlik)



After Rehabilitation
(19-17/054, Jiftlik)



Before Rehabilitation
(19-17/055, Jiftlik)



After Rehabilitation
(19-17/055, Jiftlik)

PHOTOGRAPHS



**Leakage from Open Canal
(Al 'Auja Spring)**



**Water Source
(Al Dyuk Spring)**



**Before Improvement of Open Canal
(Al Nwai'mah Spring)**



**Under Construction of Pipeline
(Al Nwai'mah Spring)**



**Before Improvement of Settling Basin
(Al Nwai'mah Spring)**



**After Improvement of Settling Basin
(Al Nwai'mah Spring)**

PHOTOGRAPHS



**Dry Season
(Wadi Qilt)**



**Rainy Season
(Wadi Qilt)**



**Dry Season
(Wadi Qilt)**



**Rainy Season
(Wadi Qilt)**



**Memorial Board of Pilot Project
(Al Nwai'mah Spring)**



**Memorial Board of Pilot Project
(Rehabilitation of Agricultural Wells)**

FINAL REPORT

EXECUTIVE SUMMARY

1. Introduction

1.1 Authority

This Final Report has been prepared in accordance with the Scope of Work (S/W) for the Feasibility Study on Water Resources Development and Management in the Jordan River Rift Valley, agreed upon between the concerned authorities of Palestinian National Authority (PNA) and the Japan International Cooperation Agency (JICA) on February 27, 2007. The report presents all the results of the Study throughout the defined period.

1.2 Background

Inefficient use of water resources is a vital issue to Palestine. The problem is mainly caused by i) an excessive water consumption due to the time-based distribution, ii) water conveyance losses in open canal irrigation network, iii) damaged agricultural wells, and iv) limited use of surface water. Since water demand is expected to increase in the future, efficient use of the existing water resources as well as development of new water resources is essential.

A study on Jericho Regional Development was conducted by JICA during the period of October 2005 to September 2006 to formulate a Regional Development Plan for the Jericho and the Jordan River Rift Valley area, and also to enhance the capacity for formulation and implementation of a regional development program. Said program was comprised of a Social and Community Development Program, Agriculture and Agribusiness Development Program and Tourism and Urban Environment Program.

The Feasibility Study on Water Resources Development and Management in the Jordan River Rift Valley is conducted as a sub-program of the Agriculture and Agribusiness Development Program under the concept of “Corridor for Peace and Prosperity”.

1.3 Objectives of the Study

The objectives of the Study are as follows:

- (1) To formulate a basic plan for efficient utilization of water for agriculture in the Jordan River Rift Valley;
- (2) To formulate a basic plan for water resources development in the Jordan River Rift Valley; and
- (3) To carry out technology transfer to Palestinian counterpart personnel through on-the-job training during the course of the Study.

1.4 The Study Area

The Study Area, as presented in the location map, is located in the West Bank of the Jordan River Rift Valley, which includes the watershed areas of Wadi Qilt, Wadi Auja and Wadi Far'a.

1.5 Work Schedule

The Study was carried out over a period of 22 months, from March 2007 to December 2008, consisting of the following two phases:

Phase 1: March 2007 ~ December 2007 (Formulating basic plans on efficient utilization of water for agriculture and water resources development)

Phase 2: January 2008 ~ December 2008 (Conducting feasibility studies on selected water resources management schemes for water resources development and for efficient utilization of water agriculture, including implementation of small scale pilot projects)

Activity	Phase-1						Phase-2															
	1st Year						2nd Year						3rd Year									
	FY2007						FY2008															
	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22
Work in Palestine	■						■												■			
Work in Japan	□												□						□			
Report	▲ IC/R		▲ PR1				▲ It/R						▲ DF/R						▲ F/R			

Source: JICA Study Team

Figure 1 Work Schedule of the Study

2. Activities

The Study Team conducted the following works throughout the study period:

- (1) Home Office Preparatory Work (March 2007)
- (2) First Field Work (March 2007 to August 2007)
- (3) Second Field Work (1) (October 2007 to March 2008)
- (4) First Home Office Work (March 2008 to April 2008)
- (5) Second Field Work (2) (May 2008 to August 2008)
- (6) Second Home Office Work (September 2008)
- (7) Third Field Work (November 2008)
- (8) Third Home Office Work (December 2008)

3. The Study Area

3.1 General Conditions

- (1) Topography and Landscapes
 - 1) Mountainous area is located in the upstream of Wadi Far'a. The elevation reaches up to 600 m above sea level.
 - 2) Most of all Study Areas are covered by foothills with steep slopes. The elevation of the foothills range from 0 to 200 m above sea level.

3) Flat area, which is lower than the sea level and has relatively high agricultural resources, lies along the Jordan River. The length and width of the area is about 10 km and 1 to 2 km, respectively.

(2) Climate

1) Rainfall

Rainfall ranges from 80 - 200 mm/year along the flat area, to 200 - 350 mm/year in the mountainous area.

2) Temperature

Mean monthly temperature in Jericho and Wadi Far'a ranges between a minimum of 13.1°C in December to a maximum of 32.4°C in August.

3) Evaporation

Evaporation rate is high due to high temperature, intensive sunshine and low humidity, particularly during the period of May through September. Annual average evaporation in Jericho reaches around 2,100 mm.

Genial climate enables cultivation of the vegetable crops throughout the year. It is expected to secure the sufficient water for the advantages of agriculture in the Study Area.

(3) Geology and Hydrogeology

Generally, the Jordan Valley area is part of the Eastern Basin in the West Bank. The existing aquifer systems within the Study Area consist of the following main aquifers:

- (i) The Holocene Aquifer;
- (ii) The Pleistocene Gravel Aquifer (Samra Formation);
- (iii) The Neogene (Miocene – Pliocene) Aquifer (Beida Formation);
- (iv) The Eocene Aquifer (Jenin sub series);
- (v) The Upper Cretaceous Aquifer (Jerusalem, Bethlehem, and Hebron Formations); and
- (vi) The Lower Cretaceous Aquifer (Yatta, Upper Beit Kahil and Lower Beit Kahil Formations).

3.2 Present Land Use of the Study Area

The land use distribution is summarized as follows:

Table 1 Present Land Use of the Study Area

Land Cover	Area A	Area B	Area C	Unit: km ²
				Total
Agricultural Areas	86	36	219	342
Palestinian Communities	16	2	47	65
Israeli Settlement	0	0	17	17
Military Base	13	3	67	84
Others	32	16	537	586
Total	148 (13.5%)	58 (5.3%)	887 (81.2%)	1,093 (100.0%)

Area A: under control of PNA both for administration and security

Area B: under control of PNA for administration, and Israeli Government for security

Area C: under control of Israeli Government both for administration and security

Source: MoP(2005)

3.3 Socio-Economic Condition

(1) Administration

The Study Area covers three administrative districts; these are Jericho governorate, Tubas governorate and a part of Nablus governorate. Under these governorates, there are 29 Local Government Units (LGUs) consisting of two municipalities and 27 village councils. Although the municipalities have comparatively well-organized administrative structure and sufficient number of staff, the administrative capacity and financial management of the village councils remain very weak.

(2) Demography

Total population of Palestinian was 3,762,005 in 2005. Among these, 2,372,216 reside in the West Bank, while 97,373 live within the Study Areas, Jericho and Tubas. The annual population growth rate of Palestinian from 1997 to 2005 was 3.3%, while that of Jericho and Tubas were 3.8% and 3.6% respectively. Accordingly, the population growth rate in the Study Area is rather higher than the regional average of Palestine.

(3) Employment

Labor force in the Jordan River Rift Valley area, consisting of Jericho and Tubas, is 24,100 persons. Unemployment rates of Jericho and Tubas are 14.0% and 23.2%, respectively.

(4) Economic Trends

Gross Domestic Product (GDP) in Palestinian Territory had steadily increased during 1994 -1999. For three years between 2000 and 2002, GDP has dropped 21% since 1999. GDP recovered gradually afterwards.

(5) Local Financial System

Access to credit is quite limited to farmers, particularly to small scale farmers, in the Study Area. Lack of collateral and high market risks for the agricultural sector unable farmers to access commercial and financial institutions. Agricultural and rural credits are currently provided for informal channels, such as family, relative, middleman, wholesaler, etc.

(6) Education

The current education system is relatively improved, and works effectively. According to the socioeconomic survey, only about 43.5% of the heads of surveyed households have either no education or are drop-outs from primary education.

(7) Health

Public health conditions of Palestine are similar to those of lower, middle-income countries. Infant mortality rate of Jericho Governorate was lower than the average as per WB, during 2000-2004. Life expectancy of Jericho Governorate has also improved. The latest figure indicates a higher life expectancy of 72.4 years in 2000-2005, as compared to 56.6 years in 1970-1975. The Ministry of Health, the United Nations

Relief and Works Agency (UNRWA) and NGOs are the main service providers in the Study Area.

(8) Poverty

A high incident of poverty is observed in the agricultural sector of the Study Area. The deep poverty rate and the poverty rate of the agricultural sector are 29.7 % and 50.4 %, respectively.

(9) Gender Issue

Socio-economic survey results conducted by the Study Team indicated that job opportunities for females, as compared to males, are relatively limited, except in the agricultural industry in the Study Area.

3.4 Agriculture

(1) Farm Households and Land Tenure Systems

Number of farm households, inclusive of agriculture and livestock, is about 2,200. It is estimated that about 32,000 persons in the Study Area are engaged in agriculture.

(2) Land Tenure Systems

Three main forms of land tenure, consisting of (i) Ownership system, (ii) Sharecropping system, and (iii) Rental system, are observed in the irrigated regions of the Study Area, and to a lesser extent, a fourth mixed form is adopted in some other included regions.

(3) Agricultural Land Use

The agricultural land in the Study Area is categorized into two land units, namely, the "Rainfed Land" and the "Irrigated Land". The irrigated land covers about 61,000 dunum, which is over 90% of the total agricultural land use in the Study Area.

(4) Agricultural Production

The total production of the field crops and forages in the Study Area is 25,539 tons, which is 12.5% of the total production in the West Bank.

Production of major vegetables include: eggplant (31,930 tons or 74% of production in the West Bank); tomato (35,137 tons or 35%); cucumber (17,779 tons or 19%); squash (20,003 tons or 63%); and maize (5,849 tons or 95%). The total production of vegetables in the Study Area is 132,781 tons, which contributes to 39% of the total production in the West Bank.

Fruit trees in the Study Area are planted over 22,000 dunum, which is equivalent to 20% of the area for fruit tree planting in the West Bank. In the West Bank, bananas (9,800 tons or 3,305 dunum) and dates (1,274 tons or 1,988 dunum) are planted only in Jericho because of its suitable climate conditions.

(5) Livestock

The livestock productions in the Study Area include production of milk (goats, sheep and cattle), meat (broiler, goats, sheep and cows), eggs and honey. Most of the Bedouins,

who live within the Study Area, engage in the livestock sector. The livestock production rate in the Study Area is relatively low in comparison with the other areas.

(6) Marketing

Most of the agricultural products produced in the Study Area are cash crops. Main destinations of the products are other areas in the West Bank and Israel.

3.5 Water Resources Management

(1) Wadi Watershed

In the Study Area, there are a number of wadis, which are broadly demarcated into nine major wadi basins as shown in the table below. Flood water is currently not utilized, since there is no intake facility installed in the wadis.

Table 2 Major Wadi Basins in the Study Area

No.	Name of Wadi	Catchment Area (km ²)
1.	Wadi Hahal Milah	276.1
2.	Wadi Abu Sidra	120.8
3.	Wadi Far'a	336.9
4.	Wadi Al 'Ahmer	180.1
5.	Wadi Auja	291.4
6.	Wadi Nueima	152.5
7.	Wadi Qilt	172.4
8.	Wadi Marar	102.4
9.	Wadi Mukallak	140.5

Source: PWA Database

(2) Agricultural Wells

The working agricultural wells in the Jordan River Rift Valley are 88, out of the total 184 wells. The remaining wells are non-pumping and are abandoned.

Table 3 Agricultural Wells in the Study Area

No.	Locality	Number of wells (Working, Non-pumping)
1	Al 'Auja	10 (7, 3)
2	Al Jiftlik	27 (21, 6)
3	An Nabi Musa	1 (0, 1)
4	Az Zubeidat	4 (2, 2)
5	Bardala	8 (1, 7)
6	Deir Hajleh	2 (0, 2)
7	Fasayil	1 (0, 1)
8	Furush Beit Dajan	8 (5, 3)
9	Jericho (Ariha)	92 (29, 63)
10	Marj Na'ja	13 (7, 6)
11	Wadi Al Far'a	18 (16, 2)
	Total	184 (88, 96)

Source: PWA Database as of March 2007

(3) Spring Water

A group of 24 springs is located in the Study Area as listed below, together with the average discharge data for each. Most of the springs function less due to the damage of the conveyance system and improper management of water distribution.

Table 4 Spring in the Study Area

No.	Name	Code	Average Discharge (MCM/yr)
1	Fasayil	AC/054	0.66
2	Al Dyuk	AC/060	4.86
3	Al Nwai'mah	AC/060A	2.60
4	Al Shusah	AC/060B	0.61
5	Al Sultan	AC/061	5.54
6	Shibli	AQ/022	0.85
7	Abu Saleh	AQ/024	0.19
8	Meskah	AQ/025	1.29
9	Al Far'ah	AQ/030	5.31
10	Al Dlaib	AQ/032	1.20
11	Sedrah	AQ/036	1.46
12	Hamad & Baidah	AQ/037A	0.88
13	Qdairah	AQ/037B	1.19
14	Jeser	AQ/038	0.14
15	Tabban	AQ/039	1.29
16	Al Subyan	AQ/040	0.19
17	Balata	AQ/043	0.18
18	Dafna	AQ/044	0.13
19	Al 'Auja	AR/020	9.55
20	Al Qilt & Al Fawwar	AS/020	6.55
21	Al Fawwar	AS/021	4.48
22	Far'a	AS/022	0.70
23	Al Jummaizah	AS/022A	0.30
24	Al Ru'yan	AS/022B	0.36

Source: PWA Database

Note: The average discharge volumes of each spring are calculated from the raw data with the unit of L/s measured in 1960-2006.

(4) On-Farm Facilities and Management

Various methods of water application are used in irrigation systems. The three basic methods prevailing in Palestine are surface irrigation, sprinkler irrigation, and drip irrigation.

3.6 Constraints on Water Resources Development and Management

(1) Socio-Economic Conditions

Political issues such as Israeli control between Palestine and her neighboring countries sometimes interrupt the economic development. Restriction on the movement of goods and people within Palestine aggravated the quality of public services and deprived the

economic activities. Consequently, human resource development as well as institutional strengthening is essential to achieve a sustainable socio-economic development in the region.

(2) Existing Water Resources

The constraints on agricultural wells and spring water uses are pointed out below:

Agricultural Well

- 1) Most of the wells were drilled from 1950 to 1966, and then its capacity decreased;
- 2) Limitation of well extraction;
- 3) Drop of groundwater level;
- 4) Electricity deficit in many areas;
- 5) Escalating costs of equipment, spare parts and maintenance works;
- 6) Lack of local cooperative organization for maintenance of wells;
- 7) Lack of efficient and qualified local drilling companies; and
- 8) Political Issues such as Israeli control to be settled between Palestine and Israel on the water resources development and management including agricultural development

Spring Water

- 1) Inefficient use of water due mainly to seepage, leakage in the main conveyance canals or natural conveyance systems and insufficient capacities of those conveyance facilities;
- 2) Excessive water consumption caused by time-based water distribution;
- 3) Lack of water users association;
- 4) Lack of capacity on operation and maintenance (O&M) of water conveyance facilities;
- 5) Contamination by untreated wastewater inflow in the wadis;
- 6) Unstable water supply due to the seasonal fluctuation; and
- 7) Political Issues such as Israeli control to be settled between Palestine and Israel on the water resources development and management including agricultural development

4. Hydrology and Hydro-geology

4.1 Hydrological Analysis

Hydrological analysis was conducted on major wadis in the Study Area, namely, Wadi Qilt and Wadi Far'a.

(1) Available Data

- 1) Temperature, Rainfall, Evaporation (1953/1954 – 2005/2006) provided by PWA, MoT, PHG;
- 2) Hourly rainfall on Wadi Far'a Basin (2003/2004 – 2004/2005) and runoff on Wadi Far'a (2003/2004 – 2004/2005) provided by Najah University;
- 3) Runoff on Wadi Qilt (1967 – 1983) provided by Israel Water Committee; and
- 4) Runoff on Wadi Qilt and Wadi Far'a (spot data in 1971 – 2005) provided by PWA.

(2) Hydrological Analysis

The hydrological analysis on Wadi Qilt was performed by applying the daily rainfall data to the simulation model called the “Tank Model,” under a very limited flood runoff data. The mean annual runoff volume in the Wadi Qilt between 1953/1954 and 2005/2006 was derived as 1.67 MCM.

Meanwhile, the hydrological analysis on Wadi Far’a is being carried out by the EU Engineer and Najah University. The annual runoff volumes of Wadi Far’a sub-catchment was derived as 1.76 MCM, based on the observed data of 2003 to 2005.

(3) Sedimentation

Although no sediment data on wadis of Palestine is available, the study team has estimated the sedimentation of Wadi Far’a at 0.75 mm/year, and that of Wadi Qilt at 0.625 mm/year, based on the study result of the Kafrein Dam in Jordan.

(4) Assessment of Availability of Hydrological Data for Feasibility Study of Storm water Harvesting Project

The available hydrological data on Wadi Qilt is still insufficient to carry out a feasibility study on storm water harvesting project in the Wadi Qilt basin. It is recommended that the feasibility study and subsequent detailed design be performed when the hydrological data, including the sediment data (preferably the 5-years’ data) are adequately available.

4.2 Hydro-Geological Environment of Study Area

(1) Hydrogeology and Aquifer System

The geological stratigraphy of the Study Area is as follows:

- 1) Quaternary Aquifer
- 2) Neogene Aquifer
- 3) Eocene Aquifer
- 4) Upper Cretaceous Aquifer
- 5) Lower Cretaceous Aquifer

Groundwater basin in the Study Area is divided into Eastern Basin and North Eastern Basin with anticline syncline structure. This means that the basin of surface water and that of groundwater are different.

(2) Groundwater Environment of the Study Area

The results of existing data analysis and field survey are summarized below:

- 1) In the Eastern Basin, the secular decreasing tendency of groundwater level of Quaternary, Eocene and Upper Cretaceous Aquifer is remarkable;
- 2) The chloride ion concentration of Quaternary Aquifer is very high, and its tendency to increase is observed;
- 3) As for the spring water originated in Cenomanian Aquifer of the Eastern Basin, the tendency to decrease is not observed. However, the tendency of chloride and nitrate ion to increase is possible to a part of the spring water due to its contamination with waste water;

- 4) A remarkable change is not seen in the groundwater level of the North Eastern Basin. In recent years, the groundwater use of Cretaceous Aquifer has progressed. Thus, the monitoring of the groundwater level and pumping rate are necessary; and
- 5) The chloride ion concentration of the wells in the North Eastern Basin is not significant. The increase tendency of chloride and nitrate ion is observed due to mixing of waste water.

5. Comprehensive Water Resources Management and Development

5.1 Water Resources in the Study Area

(1) Present Water Resources

The present water resources in the four sub-regions are estimated on the basis of available data in 2005, as summarized in the following table:

Table 5 Present Water Resources in 2005

Area	Spring (MCM/yr)	Well (MCM/yr)	Mekorot * (MCM/yr)	Total (MCM/yr)
Jericho/Al 'Auja	22.22	3.83	1.09	27.14
Lower Al Far'a	1.50	4.20	0.17	5.87
West Tubas	8.38	2.88	0.02	11.28
North Tubas	0.00	0.38	4.10	4.48
Total	32.10	11.29	5.38	48.77

Note: Excluding assumed losses.

**: purchase from Mekorot (Israel water company)*

Source: PWA database (2005)

(2) Present Water Demand

Water resources in the Study Area are mainly allocated for agricultural, domestic and industrial uses. Those demands are shown in the following tables:

Table 6 Present Agricultural Water Demand in 2004/2005

Area	Irrigated Area (Dunum)	Agricultural Water Demand (MCM/yr)				Total
		Field Crop	Protected Plants	Open Field Vegetable	Fruit	
Jericho/Al 'Auja	26,079	0.88	0.60	12.66	15.03	29.17
Lower Al Far'a	20,289	2.05	0.61	9.76	2.84	15.26
West Tubas	5,837	0.53	0.66	0.82	2.13	4.14
North Tubas	8,772	0.17	2.93	2.72	0.23	6.05
Total	60,977	3.63	4.80	25.96	20.23	54.62

Source: Agricultural Statistics, PCBS, 2004/05, Water resources and Irrigated Agriculture, Applied Research Institute, March 1998, and JICA Study Team estimate

Table 7 Present Municipal and Industrial Water Demand in 2005

Area	Population	Municipal & Industrial Demand (MCM/yr)					
		Dom.	Tour	Public	Livstck	Indst.	Total
			200 lpc	3%	10%	15%	
2005							
Jericho/Al 'Auja	35,514	1.72	0.20	0.08	0.27	0.40	2.67
Lower Al Far'a	7,982	0.35	0.00	0.01	0.05	0.07	0.48
West Tubas	50,023	0.88	0.00	0.04	0.12	0.18	1.22
North Tubas	3,143	0.06	0.00	0.00	0.01	0.01	0.08
Others	711	0.01	0.00	0.00	0.00	0.00	0.02
Total	97,373	3.02	0.20	0.13	0.45	0.66	4.47

Note:

- It is assumed that the number of tourists will be 400,000 in a year and that each tourist will stay for 2.5 nights in the Jericho/Al 'Auja area only.
- Public water demand is assumed to be 3% of M&I demand.
- Livestock water demand is assumed to be 10% of M&I demand.
- Industrial water demand is assumed to be 15% of M&I demand.
- Domestic water demand is assumed under the target water supply level set by PWA.

Source: JICA Study Team estimate

(3) Present Water Balance

The characteristics of sub-region on water balance in the Study Area are summarized in the table below.

Table 8 Characteristics of Sub-region Areas in the Study Area

Sub-region	Population	Water resource (MCM/yr)	Water Resources	Water Demands
Jericho/Al 'Auja	35,589	27.14	<ul style="list-style-type: none"> • Spring water is abundant. • Spring has a seasonal fluctuation. • Wells water is brackish. • Precipitation is very low. 	<ul style="list-style-type: none"> • Growth rate of population is relatively high. • Agricultural water use is high. • Irrigated area is widely spread. • Rainfed agriculture is not practiced.
Lower Al Far'a	7,982	5.87	<ul style="list-style-type: none"> • Wells water is brackish. • There are wells, which are not operated. • Precipitation is very low. 	<ul style="list-style-type: none"> • Irrigated area is widely spread. • Rainfed agriculture is not practiced.
West Tubas	50,659	11.28	<ul style="list-style-type: none"> • Spring water is abundant • There are some wells. • Precipitation is relatively high. 	<ul style="list-style-type: none"> • Rainfed agriculture is practiced.
North Tubas	3,143	4.48	<ul style="list-style-type: none"> • Pumping potential from wells is relatively high. • There are wells which are not operated. • Water is supplied from Mekorot. 	<ul style="list-style-type: none"> • All the area lies in Area C.

Source: JICA Study Team

(4) New Water Resources in the Study Area

In the Study Area, following new water resources could be made available. These are:

- 1) Floodwater in wadi basins; and
- 2) Recycled water from wastewater treatments plants in major cities/towns.

(5) Constraint on Water Resources Development and Management

The following constraints on the water resources development and management in the Study Area are pointed out:

- 1) Limited Water Resource;
- 2) Inefficient Water Utilization due to Deteriorated Conveyance System;
- 3) Existence of Non-functioning Wells;
- 4) Ineffective Use of Storm Water Resource; and
- 5) Political Issues to be settled for the water resources development and management (e.g. delay issue of permits from Israeli side).

5.2 Strategy for Water Resources Development and Management

Saving water is the most essential issue in the Study Area. Based on the above situations, the following measures are proposed for the water resources development and management in the Study Area.

- 1) Improvement of Spring Water Conveyance System
- 2) Rehabilitation and Integrated Management of Agricultural Wells
- 3) Development of Storm Water Harvesting
- 4) Formulation of Management System

5.3 Potential Water Resources

The future water potential after accomplishing the above strategies is estimated as follows:

Table 9 Future Potential Water Volume in the Study Area

Water Resource	Available Water Volume				
	Existing (2005)	Pilot Term 2007-2009 (3 years)	Short Term 2010-2012 (3 years)	Mid Term 2013-2015 (3 years)	Long Term (After 2016)
	(MCM/yr)	(MCM/yr)	(MCM/yr)	(MCM/yr)	(MCM/yr)
(1) Existing Water Resources					
· Existing Springs	32.10	32.10	32.10	32.10	32.10
· Existing Wells	11.29	11.29	11.29	11.29	11.29
· Mekorot*	5.38	5.38	5.38	5.38	5.38
Sub-total (1)	48.77	48.77	48.77	48.77	48.77
(2) Future Potential Water Resources					
· Spring Canal Improvement			2.39	4.26	11.47
· Well Rehabilitation		0.47	3.35	6.69	10.25
· New Well Development		0.76	0.76	0.76	0.76
· Storm Water Harvesting**			0.50	0.50	10.00
· Wastewater Reuse		0.63	1.33	2.13	12.50
Sub-total (2)		1.86 (+1.86)	8.33 (+6.47)	14.34 (+6.00)	44.98 (+30.64)

Water Resource	Available Water Volume				
	Existing (2005)	Pilot Term 2007-2009 (3 years)	Short Term 2010-2012 (3 years)	Mid Term 2013-2015 (3 years)	Long Term (After 2016)
	(MCM/yr)	(MCM/yr)	(MCM/yr)	(MCM/yr)	(MCM/yr)
(3) Palestinian Historical Water Rights***					
· Fashkha Springs Group		20.00	30.00	40.00	70.00
· Jordan River****		-	-	250.00	250.00
Sub-total (3)		20.00	30.00	290.00	320.00
Grand-total (1)+(2) (excluding (3))	48.77	50.63	57.10	63.11	93.75

Source: PWA Database, JICA Study Team estimate

Note: *: Management will be transferred to Palestinian institution depending on peace process

**: Further studies on storm water harvesting are required after collecting sufficient data for analysis.

***: Quantity of water volume should be estimated as a result of peace process.

****: Based on Johnston Plan

6. Basic Plan for Water Resources Development and Management

6.1 Rehabilitation and Integrated Management of Agricultural Wells

(1) Basic Plan for Rehabilitation and Integrated Management of Agricultural Wells

Out of 184 wells in the Jordan River Rift Valley around 88 wells are working while the rest are none pumping and are abandoned. Most of these wells were drilled before 1967, and their conditions are deteriorating due to electromechanical, hydro-geological and economic reasons. Basic plan for the rehabilitation of agricultural wells is envisaged for all the above wells.

For the formulation of basic plan for the rehabilitation of agricultural wells, the following points are mainly considered as the basic concept of the study:

1) Process of JWC approval

The first priority for rehabilitation is given to the wells which are in the process of obtaining JWC approval, or will be subjected to processing approval soon.

2) Sustainability of groundwater resources

Sustainability of groundwater resource should be considered in the rehabilitation plan. Downward tendency of groundwater level is alerted due to depletion of groundwater resources, especially in the southeastern part of the Study Area, including Jericho, Al 'Auja and its surrounding areas. Northern part of the Study Area is assumed to have more capacity to supply water than the present volume of abstraction.

3) Licensed volume of abstraction

The licensed volume is regarded as the maximum volume of abstraction.


4) Combination of hardware component and software component

Hardware component (wells' rehabilitation including installation of pumping equipment) and software component (operation and management of rehabilitated wells by water users' association, and water-saving irrigation system applied in the field level) are required taking into consideration the basic plan formulation.

(2) Selection of the First Priority Agricultural Wells for Rehabilitation

Nineteen wells as shown in the following figure have been selected as the priority schemes for rehabilitation, based on the technical and socioeconomic factors.

No.	Code	Name of Well
1	18-18/016	Mustafa Abu Khayzaran
2	18-18/019	Abdul Kareem Salem
3	18-18/027A	Ibrahem Dyab
4	18-18/036	Khaleel 'Abed Al Hadi
5	19-14/058B	Yunes 'Abdu
6	19-14/062	Sa'eed 'Ala' Al Deen
7	19-15/008	'Abed Al Kareem Njum
8	19-15/028A	Al 'Auja
9	19-16/005	'Abed Al'azeez Lubbad Sarrees
10	19-17/012	Marj Na'ja C5
11	19-17/027	Hasan Al Sumadi
12	19-17/033	Deya' Saleh 'Abdu
13	19-17/034	Rajy Al Skakah
14	19-17/047	Hasan 'Abed Al Jaleel
15	19-17/054	Ma'rouf Abu Samrah
16	19-17/055	Jawad Al Masri
17	19-19/005A	Rafeeq Al Zua'bi
18	19-20/001A	Khursheed Mbaslat
19	20-17/022	Sulayman Saleh




Source: JICA Study Team

Figure 2 Priority Schemes for Rehabilitation of Agricultural Wells

(3) Process of Further Rehabilitation of Remaining Agricultural Wells

Recommended process for the prioritization of further rehabilitation of remaining agricultural wells is illustrated in the following figure.



Source: JICA Study Team

Figure 3 Recommended Process to Prioritize Agricultural Wells for Rehabilitation

(4) Technical and Social Criteria for the Prioritization

The criteria to be considered for the prioritization in the above process are shown in table below.

Table 10 Recommended Criteria for the Prioritization of Agricultural Wells

Criteria		Description
Technical	Extraction license	When the licensed volume of extraction exceeds the actual volume of extraction in a well, the well should be given the higher priority.
	Water quality	Higher priority should be given to better quality of water for agriculture. If the water quality data is not available, the northern and western area of the Jordan River Rift Valley should be given higher priority because the southeastern area shows tendency of deteriorating water quality.
	Status of pumping equipment	Higher priority should be given to the worse status of pumping equipment. In case of a non-pumping well, mechanical or economical reasons why pumping stopped should be accorded more priority over hydro-geological reasons such as bad water quality and low groundwater table.
	Needs for rehabilitation	In case of hydro-geological reasons for pumping stoppage, the highest priority should be given to the wells which need to be developed, excluding deepening. The second highest priority should be given to the wells which require both development and deepening. The substitute wells should be given lower priority

Criteria		Description
		<p>since necessity of rehabilitation is lesser.</p> <p>In case of electromechanical reason, installation of motors and pumps should be given higher priority than the maintenance of existing pumping equipment in terms of the necessity for governmental support. Electrification of power source has advantage in the rehabilitation. The lowest priority should be given to the economical reason in terms of the necessity of governmental support as well.</p>
Socio-economic	Availability of alternative water source	Some of the wells have alternative water source, such as spring water channel near the cultivated area. Priority of these wells should be lower than the others.
	Irrigated area	The technical criteria are limited to a bore hole and pumping equipment. Therefore, the water distribution system is not included. Even though the well would be rehabilitated, sometimes expansion of cultivation area can not be expected due to the farmers' difficult economic condition. Since a wider cultivation area is assumed to show more cost-benefit performance, a well, which serves a wider irrigated area, should be given higher priority.
	Irrigable area	A well, which serves more irrigable land as compared to the actual irrigated area, is expected to possibly expand its irrigation network in future. Such wells should be given higher priority than others.
	Water users	<p>The criterion on the water user has two levels. One is the combination of water users, such as an absent landowner, owner farmer and tenant farmer. Another level is the number of total water users.</p> <p>To avoid limiting the benefits of rehabilitation to the land and well owners and their families only, a well, of which the water users are just the owner and his family, should be given the lowest priority.</p> <p>In terms of O&M, the owners obviously have an important role, and they should be actively involved in this aspect. Consequently, a well, which is utilized by both owner farmers and tenant farmers, should be given the highest priority. Meanwhile, a well, which is used only by tenant farmers, should be the second priority.</p> <p>Furthermore, the number of total water users should be taken into consideration for the prioritization. A larger number of total water users (beneficiaries) should be given higher priority.</p>

Source: JICA Study Team

(5) Tentative Implementation Schedule for Rehabilitation of Agricultural Wells

Tentative Implementation schedule for rehabilitation of agricultural wells is as shown below.

Work item	2006	2007-2009 (3 years)	2010-2012 (3 years)	2013-2015 (3 years)	After 2016
Pilot projects (8 wells)					
Preliminary research		■			
Preparation of priority list		■			
JWC approval	■	■			
Rehabilitation of agricultural wells		■			
Formation of WUAs and related trainings		■			
Monitoring&Evaluation		■	■	■	
1st priority projects (13 wells) excluding rehabilitation of 20 wells supported by FAO and Arabfund					
Approval of relevant institutions			■		
Rehabilitation of agricultural wells			■		
Formation of WUAs and related trainings			■		
Monitoring&Evaluation			■	■	■
2nd priority projects (30 wells)					
Preliminary research			■		
Initial Environmental Evaluation			■		
Assessment of priority list			■		
Approval of relevant institutions			■	■	
Rehabilitation of agricultural wells			■	■	
Formation of WUAs and related trainings			■	■	
Monitoring&Evaluation			■	■	■
3rd priority projects (30 wells including drilling new wells)					
Preliminary research				■	
Initial Environmental Evaluation				■	
Assessment of priority list				■	
Approval of relevant institutions				■	
Rehabilitation of agricultural wells				■	■
Formation of WUAs and related trainings				■	■
Monitoring&Evaluation				■	■

Source: JICA Study Team

Figure 4 Tentative Implementation Schedule for Rehabilitation of Agricultural Wells

(6) Basic Plan for Integrated Management of Wells

For rehabilitation of wells, following basic conditions are fulfilled prior to the rehabilitation. All well owners and beneficiaries have to agree these conditions before rehabilitation.

- 1) The well is officially registered and licensed.
- 2) Cooperation to water management at regional and national level
- 3) Contribution to the rehabilitation in cash or in kind (if a donor requests)
- 4) Establishment of Water Users' Association (WUA)
- 5) Establishment of a tariff system (water fee for water users)
- 6) Long term contract between owners and existing water users
- 7) Disclosure of information on management

6.2 Improvement of Spring Water Conveyance System

(1) Basic Plan for Improvement of Spring Water Conveyance System

The concept of the basic plan for improvement of spring conveyance systems for agriculture is set up as follows, in order to establish and enhance the spring water management system.

- 1) Improvement of conveyance system
 - (i) Reduction of physical losses
 - (ii) Prevention of water against contamination
 - (iii) Introduction of fair water distribution system under water right
 - (iv) Introduction of water distribution monitoring system
- 2) Improvement of water use and O&M systems and activities

- (i) Establishment and strengthening of O&M organization
- (ii) Training on on-farm water management

Upon the above concept, basic plan for improvement of spring water conveyance system is prepared under the following regional wise development:

- 1) Wadi Far'a Area (Badhan, Al Far'a and Ain Shibli Spring Groups)
 - (i) Rehabilitation of the intake facilities of Al Dlaib, Hammad & Beidha, Qudairah, Sedrah, Jeser, Subyn and Meskeh springs
 - (ii) Development of pipeline system for main and sub-main conveyance lines of Al Fa'ra, Al Dlaib, Hammad & Baidah, Qudairah, Tabban, Sedrah, Jeser, Subyan and Meskeh springs
 - (iii) Development of trunk pipelines to convey water from Al Badhan and Al Far'a Spring Groups to the down stream villages, connecting to the Al Far'a Irrigation Project
 - (iv) Development of sub-main pipelines to convey water to the downstream areas such as An Nassariya, Al' Aqrabaniya, Frush Beit Dajan and Al Jiftlik.
 - (v) Establishment of O&M bodies including a coordination committee
 - (vi) Strengthening of O&M bodies and a coordination committee
 - (vii) Awareness promotion for effective water use for irrigation
 - 2) Al 'Auja Spring
 - (i) Rehabilitation of existing intake weir
 - (ii) Development of pipeline system for main and sub-main conveyance lines
 - (iii) Establishment and enhancement of O&M body
 - (iv) Awareness promotion for effective water use for irrigation
 - 3) Jericho and Dyuk Spring Group
 - (i) Development of pipeline system for main and sub-main conveyance lines
 - (ii) Rehabilitation of existing open canals for main, secondary and tertiary conveyance lines
 - (iii) Establishment and enhancement of O&M body
 - (iv) Awareness promotion for effective water use for irrigation
- (2) Priority Scheme for Improvement of Spring Water Conveyance System


Based on the concept of basic plan, the criteria for selection of priority schemes was set as shown in the following, from the viewpoint of the characteristics of water sources and water use situation and its improvement needs:

- 1) The spring should have continuous discharge through the years. This means that any dried-up springs or seasonal springs should be removed from the shortlist;
- 2) The spring water should be used for agricultural purposes;
- 3) The spring should be used for to benefit the public. This means that the spring water and facilities should not be owned and used by only a particular family;
- 4) The utilization of spring should be limited to a particular locality. This means that the spring with users and stakeholders from plural localities should be excluded from the shortlist to avoid any friction or conflict as a result of the improvement in the pilot project; and

5) The improvement requirements identified for the spring should include rehabilitation of its mainline, to meet the concept of the basic plan.

The following sites presented in the figure below are prioritized in the basic plan, through the baseline survey, technical survey and analysis.

- (i) Al 'Auja Spring
- (ii) Al Dyuk Spring
- (iii) Al Nwai'mah Spring



Source: JICA Study Team

Figure 5 Location of Priority Schemes for Improvement of Spring

(3) Proposed Implementation Plan for Improvement of Spring Water Conveyance System

The following schedule for the implementation of spring water conveyance system is tentatively proposed.

Work Item	2007-2009 (3 years)	2010-2012 (3 years)	2013-2015 (3 years)	After 2016
Pilot Project				
Design Study				
JWC Approval	▲			
Tnederung & Implementation Works	■			
Priority Project for Al 'Auja Spring				
Approval of Relevant Institutions	▲			
Basic Design Study		■		
Detailed Design Study			■	
Tnederung & Implementation Works			■	
Priority Project for Al Dyuk and Al Nwai'mah Spring				
Approval of Relevant Institutions	▲			
Basic Design Study			■	
Detailed Design Study				■
Tnederung & Implementation Works			■	
Project for Non-prioritized Spring Site				
Preliminary Study & Feasibility Study				■
Approval of Relevant Institutions				▲
Basic & Detailed Design Study				■
Tnederung & Implementation Works				■

Source: JICA Study Team

Figure 6 Proposed Implementation Schedule of Basic Plan for Improvement of Spring Water Conveyance System

(4) Basic Plan for Integrated Management of Springs

The basic concepts for integrated management of springs are as follows:

- Establishment of a coordination committee or a similar body, which manages the spring water conveyance system at local government level.
- Compliance to a tariff system, which will be set by the coordination committee

6.3 Prospective Plan for Storm Water Harvesting

(1) Potential for Development of Storm Water Harvesting

Following plans are pointed out for the development of the storm water harvesting in the Study Area:

- 1) Storage-type dam
- 2) Recharge dam or underground dam
- 3) Reservoir located outside the area of wadi riverbed

Potential plans for the storm water harvesting on the major wadis, namely Wadi Qilt, Wadi Auja and Wadi Far'a are as follows:

- 1) Wadi Qilt
 - (i) Storage-type dam at the end of the mountain region
 - (ii) Recharge facility or underground dam at the location around the existing Parshall flume
 - (iii) Storage facility of the storm water at the area outside the wadi riverbed around the downstream of the garbage dumping site
- 2) Wadi Auja
 - (i) Recharge facility or underground dam around the downstream end of the alluvial fan
 - (ii) Regulating reservoir for the systematic water supply surplus spring water along

the headrace located in the wide flat plain area

3) Wadi Far'a

- (i) Storage type dam around the confluence between Nablus Basin and Tubas Basin

The location of potential sites and plans are presented in Chapter 6.

(2) Prospective Plan for Storm Water Harvesting

Hydrological and geological data was insufficient to conduct the feasibility study for the storm water harvesting plan. Moreover, installation of hydrological station and geological investigation could not be executed due to the delay issue of permits from Israel. However, three prospective plans among the above potentials were prepared with conditions on geological and hydrological aspects. The rest of the potential plans were not considered for further studies, judging from the available data as well as the result of the field investigations.

Prospective plans of storm water harvesting are:

- 1) Recharge facility or underground dam at the location around the existing Parshall flume on Wadi Qilt;
- 2) Storage facility of the storm water at the area outside the wadi riverbed around downstream area of the garbage dumping site on Wadi Qilt; and
- 3) Regulating reservoir for the systematic water supply surplus spring water along the headrace located in the wide flat plain area.

(3) Measures Taken prior to the Execution of the Feasibility Study

In order to proceed to the next step which is the execution of feasibility study for storm water harvesting, the following measures were considered in this study.

- 1) Preparation of Installation Plan for Hydrological Stations
- 2) Preparation of Pilot Project Plan for Storm Water Harvesting

6.4 On-farm Water Management

As well as rehabilitation and improvement of main irrigation facilities, enhancement of on-farm application efficiency is essential to realize the efficient water use in the field of irrigation. Following measures are proposed:

- 1) Improvement of techniques and O&M for water saving irrigation;
- 2) Replacement of old facilities for water saving irrigation; and
- 3) Awareness promotion on efficient water use.

To accomplish the proposed water saving irrigation, the following activities were implemented during the course of the study:

- 1) Initiate pilot project on improvement of spring water conveyance system and rehabilitation of agricultural well (to enhance water conveyance efficiency)
- 2) Conduct training courses for on-farm water management (to enhance on-farm application efficiency)

6.5 Implementation Program for Water Resources Development

The water resources development in the Study Area mentioned in the previous sections will be implemented under short, medium, and long term plans. Urgency, scale, political risks for executing the construction works, and other factors are also taken into consideration in the plans.

Table 11 Implementation Program for Water Resources Development


Plan	Short Term (2010-2012)	Medium Term (2013-2015)	Long Term (After 2016)
Improvement of Spring Water Conveyance System	Al 'Auja Spring	Al Nwai'mah and Al Dyuk Spring	16 springs
Rehabilitation of Agricultural Wells	11 wells (excluding 8 wells from 19 priority wells which was executed as the pilot project)	30 wells	30 wells
Development of Storm Water Harvesting	Collection and analysis of relevant data and information for the preparation of storm water harvesting plan		Major wadis such as Wadi Qilt, Wadi Auja and Wadi Far'a
	Implementation of Pilot Projects		

Source: JICA Study Team

7. Pilot Project

7.1 Objective of Pilot Project

Two types of pilot projects, namely the rehabilitation of agricultural wells and improvement of spring water conveyance system, were implemented during the second field work. The objective of implementation of the pilot project was to verify efficiency and effectiveness of the development plans, which was drafted in the interim period of the study. Based on lessons learned from the implementation, the development plans were revised. The figure below shows the function of pilot projects in the implementation.



Source: JICA Study Team

Figure 7 Function of Pilot Project to the Feasibility Study

7.2 Selection of Pilot Project

The following sites have been selected as the pilot projects during the first field work period (from March 2007 to August 2007), considering the selection criteria. These have been approved by the Steering Committee.

- (1) *Rehabilitation and Integrated Management of Agricultural Wells: 8 wells with the high order of priority among 19 wells as mentioned in 6.1*
- (2) *Improvement of Spring Water Conveyance System: Upper parts of Nwai'mah Spring Conveyance System*

Work items and cost for the pilot project are as follows:

Table 12 Work Item and Cost for Well Rehabilitation of Pilot Projects

	Code	Name	Location	Area			Condition		Needs		Remarks
				A	B	C	Bad	Not pumping	Cleaning	Deepening	
1	19-15/008	'Abed Al Kareem Njum	Auja	*				*	*		Cleaning up to 58 m, Installation was cancelled due to water quality through pump test.
2	19-17/047	Hasan 'Abed Al Jaleel	Frush bet dajan			*	*			*	Deepening more than 20 m, Vertical pump (80 m ³ /hr, Head 200m), motor(125 HP)
3	19-17/034	Rajy Al Skakah	Frush bet dajan			*	*		*		Vertical pump (50 m ³ /hr, Head 180m), motor(75 HP)
4	19-17/027	Hasan Al Sumadi	Jiftlik			*	*				Vertical pump (65 m ³ /hr, Head 80m), motor(75 HP)
5	19-17/054	Ma'rouf Abu Samrah	Jiftlik			*	*				Submergible pump (30 m ³ /hr, Head 70m)
6	19-17/055	Jawad Al Masri	Jiftlik			*	*				Vertical pump (90m ³ /hr, Head 120m), motor(75 HP)
7	19-19/005A	Rafeeq Al Zua'bi	Ein Al Byhda			*	*				Vertical pump (110m ³ /hr, Head 50m), motor(50 HP)
8	18-18/036	Khaleel 'Abed Al Hadi	Far'a		*		*				Vertical pump (90m ³ /hr, Head 60m), motor(50 HP)
										Total direct cost : USD500,000 (including the software component)	

Source: JICA Study Team

Table 13 Work Item and Cost of Nwai'mah Spring Pilot Project


Work Item
(1) Rehabilitation of the first part of main open canal (approx. 30m)
(2) Construction of a settling basin (16m ³ , concrete structure) with bypass pipes (Approx. 40, HDPE pipe)
(3) Installation of closed pipeline (underground) replacing the second part of main open canal (approx. 1.0km, HDPE pipe with dia.14 inch)
Total cost : USD320,000 (including the software component)

Source: JICA Study Team

7.3 Supporting System for Water Resources Management

Apart from the improvement and rehabilitation works, supporting system for the water resources management, such as formation and training of water users association and capacity building for related organization, is carried out at the pilot project sites, in order to accomplish the project target and to build integrated management for the wells.

The supporting activities to be taken throughout the pilot projects are as follows:




Source: JICA Study Team

Figure 8 Flow of Supporting System


7.3 Implementation Schedule of Pilot Projects

Implementation schedule and actual progress of the pilot projects for rehabilitation of agricultural wells and improvement of spring water conveyance system are shown in the following figure.



Source: JICA Study Team

Figure 9 Implementation Schedule of Pilot Project (Agricultural Wells)



Source: JICA Study Team

Figure 10 Implementation Schedule of Pilot Project (Nwai'mah Spring)

Supporting system was commenced in the middle of November 2007 as per the following schedule.

- 1) Pre-rehabilitation stage (formation of WUA and water management section): (3 months)
- 2) Rehabilitation stage (technical training): (5 months)
- 3) Post-rehabilitation stage (follow-up training, monitoring, and reporting): (3 months)

7.4 Monitoring and Evaluation of Pilot Project

(1) Monitoring and Evaluation Indexes

Monitoring and evaluation of pilot projects were carried out based on Project Design Matrix (PDM) and implementation plan. PDMs for each pilot project are presented in Table 7.6.1 and Table 7.6.2 of the main text.

(2) Monitoring and Evaluation of Pilot Project

Project purpose and outputs were evaluated by indicators described in PDMs. Results are shown in the evaluation grid table below.

Table 14 Evaluation Grid based on PDM for Rehabilitation of Agriculture Wells

PDM code	Indicators	Source/ Method	Result
<u>Project Purpose</u> Efficient and effective development plan of the priority scheme for rehabilitation of agricultural wells is formulated.	<u>Indicator 1</u> Work component, implementation schedule and management unit	Final report of the JICA Study	Development plan for the priority schemes was formulated based on the result of the pilot project. Lessons from the future monitoring activities to be conducted by MoA and PWA should be reflected on the implementation.
	<u>Indicator 2</u> B/C and IRR of Feasibility Study on rehabilitation of agricultural wells	Final report of the JICA Study	The financial and economic evaluation for the priority schemes was finalized based on the result of the pilot project.
<u>Output 1-1</u> Wells' extraction capacity is recovered up to the licensed level.	<u>Indicator</u> Volume of extraction	- Record of water extraction kept by WUA - Field survey on water extraction capacity conducted by JICA Study Team	Since full operation has not been started, actual extraction volume cannot be recorded. However, the result of pumping test indicated that extraction volume per hour was increased more than 30% in average. Actual effect shall be confirmed through monitoring by MoA and PWA after commencement of full operation.
<u>Output 1-2</u> O&M cost for the selected wells becomes cheaper.	<u>Indicator</u> Unit cost of pumped water	- Record of water extraction and account book kept by WUA - Result of interview survey to WUA	Since full operation has not been started, actual O&M cost yet to be seen. However, the result of pumping test indicated that unit fuel cost for m ³ was decreased more than 30% in average.
<u>Output 2</u> The management unit of rehabilitated wells is established to operate and manage appropriately.	<u>Indicator 1</u> Organization chart of the WUA for O&M of the rehabilitated wells	- Internal rule of the WUA - Interview survey to the WUA - List and contents of records to be kept by WUA	Regulation of WUA was developed and issued in all WUA, and training on O&M was completed. Continuous monitoring by MoA and PWA is required.

PDM code	Indicators	Source/ Method	Result
	<u>Indicator 2</u> Records kept by the WUA	- Internal rule of the WUA - Training report - Interview survey to the WUA - List and contents of records to be kept by WUA	Training of O&M and record keeping was completed in participation of well owners, operators and record keepers. Continuous awareness raising activities and timely/appropriate guidance by MoA and PWA are required.
	<u>Indicator 3</u> Expected financial balance of WUA	- Interview survey to WUA - List and contents of records to be kept by WUA	The tariff system was proposed to make the financial balance sound, but it was not applied because full operation of pumping equipment is not started yet. Continuous awareness raising activities and timely/appropriate guidance by MoA and PWA are required.
Output 3 Farmers' understanding on efficient use of agricultural water is deepened.	<u>Indicator</u> No. of farmers participating the training and their understandings on water saving agriculture	- Interview survey to the participants - Record of water extraction kept by WUA - Field survey on water extraction capacity conducted by JICA Study Team	124 trainees, who include 80% of the farmers, participated in the training course. 96.3% of trainees intend to change their irrigation practice based on the training course they received. Continuous awareness raising activities and timely/appropriate guidance by MoA and PWA are required.
Output 4 Procedure, implementation schedule, cost and desired management system are clarified through all activities.	<u>Indicator</u> Lessons learned from the pilot project	- Interview survey to the well owners, WUA and farmers - Study report of the JICA Study	Many practical lessons learned were obtained through the process of the pilot project activities. Regarding the post project period, continuous monitoring is needed for evaluation.

Source: JICA Study Team

Table 15 Evaluation Grid based on PDM for Improvement of Spring Water Conveyance System

PDM code	Indicators	Source/ Method	Result
Project Purpose Efficient and effective development plan of the priority scheme for improvement of spring water conveyance system is formulated.	<u>Indicator 1</u> Work component, implementation schedule and management unit	- Final report of the JICA Study	Development plan for the priority schemes was formulated based on the result of the pilot project. Lessons from the future monitoring activities to be conducted by MoA and PWA should be reflected on the implementation.
	<u>Indicator 2</u> B/C and IRR of Feasibility Study on improvement of spring water conveyance system	- Final report of the JICA Study	The financial and economic evaluation for the priority schemes was finalized based on the result of the pilot project.

PDM code	Indicators	Source/ Method	Result
Output 1 Conveyance loss of spring water is decreased.	<u>Indicator</u> Volume of conveyed water and leakage	- Discharge record - Field survey on water leakage	The water loss in the target conveyance line was 38.5% before the project. The result of water flow monitoring shows that it was improved to be 9.9% after the project.
Output 2-1 Spring water is allocated effectively and efficiently.	<u>Indicator</u> Expected condition of water allocation	- Discharge record - Field survey on water leakage	It can be conceivable that the water volume conveyed to the users is increased to be another 0.7 million m ³ /year from the result of water flow monitoring mentioned above.
Output 2-2 A management unit of spring water conveyance system is established to operate and manage appropriately.	<u>Indicator 1</u> Organization chart of the management unit for O&M of the improved conveyance system	- Water allocation plan - Interview survey to the village council	Stakeholders decided that two existing water management bodies be merged to promote efficient management. An organization structure of merged management committee was proposed, but not yet started. In order to get ready for the improvement works for the entire conveyance system, awareness raising activities by MoA and PWA are required continuously.
	<u>Indicator 2</u> Records kept by the management unit	- Scope of work of the management unit - Training report - Interview survey to the village council and farmers - List and contents of records to be kept by the management unit	No. of training participants was 7, who were nominated as candidates for the committee members. They were explained on the proposed scope of works for O&M. Continuous awareness raising activities and timely/appropriate guidance by MoA and PWA are required.
	<u>Indicator 3</u> Expected financial balance of the village council on water	- Interview survey to the village council - List and contents of records to be kept by the village council	The tariff system was proposed to make the financial balance sound, but it will not be applied until the entire conveyance system is improved. Continuous awareness activities by MoA and PWA are required.
Output 3 Procedure, implementation schedule, cost and desired management system are clarified through all activities.	<u>Indicator</u> Lessons learned from the pilot project	- Interview survey to the village council - Study report of the JICA Study	Many practical lessons learned were obtained through the process of the pilot project activities. Regarding the post project period, continuous monitoring is needed for evaluation.

Source: JICA Study Team

(4) Lessons Learned from the Activities of the Pilot Project

Through the activities of the pilot projects, the following lessons were realized, and reflected in the preparation of the plan for the priority schemes.

1) General

- Close communication and confirmation among all water users is essential to prepare the proper planning, and to avoid design modifications during the construction period.
- Any field investigation especially in the natural reserve area should be reported to the Civil Administration, prior to the execution of the works.
- Regarding implementation, apart from obtaining JWC approval, Civil Administration permission is also required for any field activities including movement of contractor's staff, equipment, materials etc.
- The applications for the activities mentioned in the above are required not only for Area C but also for Areas A and B.

2) Rehabilitation of Agricultural Wells

- Among selected eight agricultural wells, installation of pump equipment for well No. 19-15/008 in Al 'Auja was abandoned because that water quality of the well with a high electric conductivity of about 4,000 to 6,000 $\mu\text{s}/\text{cm}$ was observed through 1st stage works. It causes restriction of the cropping in the area.
- For the prioritization of the proposed wells, score setting on each criterion should be considered, so that difference among wells can be clearly appeared.
- Any activities requiring farmers' participation should not be planned from June to August (agricultural off-season), since they are not available on site during this period.
- Orientation or introduction of the project activity requires longer time and patience. In particular, owners of absentee-owned wells tend to misunderstand about ownership of their well and water rights.
- For the facilitation of WUA establishment, a period for rapport building among stakeholders and facilitators varies depending on the condition of the well. Experiences in the pilot project indicate that at least six months need to be allotted.
- For smooth movement of the staff tasked to perform field works, identification card should be issued by the project or Palestinian Authority.
- If a target well is absentee-owned or owner managed, its proposed rehabilitation should be approved first by the well owners, as well as establishment of WUA. This obtained approval shall be confirmed in a written document in order to avoid any problems during the implementation works.
- Renewal of extraction license should be monitored by PWA as part of the routine works in order to avoid any delay of implementation.
- Establishment of WUA has to be scheduled before the procurement of equipment. This

is intended to more possibly execute the collective works for the formation of WUA.

- Approval of well rehabilitation by JWC requires many procedures and takes time. Approval of JWC on wells that need rehabilitation, should be obtained prior to submission of the rehabilitation proposal to the donors.
- Most of the target wells in pilot project are located in Area C, thus requires approvals from concerned Israeli authorities, who are in charge of security in the project site. These authorities have to be properly informed about the project in order to avoid any obstacles concerning the movement of staff and equipment.
- Most of well equipment has to be imported from outside of Palestine through the Israeli port. Delivery schedule may be delayed due to official procedures in the port. Hence, three months should be allotted for the procurement of equipment
- An electric motor as power source is preferable in terms of lowering the operation cost. This is consistent with the policy of PWA. Possibility of considering the electric motor in the detailed design should to be carefully examined in any area.
- If a target well produces saline water, well owners have to be adequately informed about the quality of water, options for water use in agriculture and other purposes.

3) Improvement of Spring Water Conveyance System

- During the design stage, it is necessary to initiate a workshop to discuss the outline of proposed facilities and O&M methods with the O&M bodies and water rights holder, and consequently obtain a consensus.
- It is preferable to maintain the traditional distribution methods and structures of the distribution line. This is ideal to obtain project consensus with the users, taking into consideration the current or traditional operating methods even in cases where the conveyance system is replaced with closed pipelines.
- The user connection component should be user-friendly
- The construction plan should be designed considering user's water demand period.
- In case a conveyance system is rehabilitated partially, the O&M plan for the proposed projects should include a work item for the O&M of the whole system.
- If there are existing groups, which are involved in any O&M activity in the system, utilization of these groups for O&M of improved system should be considered rather than new one to establish.

8. Feasibility Study on Priority Schemes


8.1 Development Plan for Rehabilitation of Agricultural Wells

(1) Site Location of Priority Schemes

The first priority agricultural wells for rehabilitation were selected in the basic plan, as presented in Chapter 6 of the main text. . Among these 19 wells, eight were selected as the pilot project while the remaining 11 were included in the priority schemes for the

rehabilitation of agricultural wells. Locations of the priority schemes are illustrated in the following figure.

No.	Code	Name	Location	Area	Status
1	18-18/016	Mustafa Abu Khayzaran	Far'a	A	Bad condition
2	18-18/019	Abdul Kareem Salem	Far'a	B	Bad condition
3	18-18/027A	Ibrahem Dyab	Far'a	B	Not pumping
4	19-14/058B	Yunes 'Abdu	Jericho	A	Not pumping
5	19-14/062	Sa'eed 'Ala' Al Deen	Jericho	A	Fair condition
6	19-15/028A	Al 'Auja	Auja	A	Not pumping
7	19-16/005	'Abed Al'azeez Lubbad Sarrees	Jiftlik	C	Bad condition
8	19-17/012	Marj Na'ja C5	Marji Ghazal	C	Not pumping
9	19-17/033	Deya' Saleh 'Abdu	Jiftlik	C	Not pumping
10	19-20/001A	Khursheed Mbaslat	Bardalla	C	Not pumping
11	20-17/022	Sulayman Saleh	Marji Naja	C	Not pumping



Source: JICA Study Team

Figure 11 List and Location of Priority Schemes

(2) Development Plan for Priority Scheme

The work components and quantities for the rehabilitation of agricultural wells in each priority site are summarized in the following table.

Table 16 Work Components for the Rehabilitation of Agricultural Wells (Priority Schemes)

		18-18/016	18-18/019	18-18/027A	19-14/058B	19-14/062	19-15/028A	19-16/005	19-17/012	19-17/033	19-20/001A	20-17/022
Hardware component												
1	Preparation of pumping test	○	○	○	○	○	○	○	○	○	○	○
	1) Obtaining agreement on rehabilitation from owners	○	○	○	○	○	○	○	○	○	○	○
	2) Preparation of tender document for pumping test	○	○	○	○	○	○	○	○	○	○	○
	3) Tendering and contract	○	○	○	○	○	○	○	○	○	○	○
2	Pumping test (Contract work)	○	○	○	○	○	○	○	○	○	○	○
	1) Site preparation	○	○	○	○	○	○	○	○	○	○	○
	2) Deepening and drilling new substitute well	-	○	○	○	-	○	-	○	○	○	○
	3) Developing	-	○	○	○	-	○	-	○	○	○	○
	4) Pumping test	○	○	○	○	○	○	○	○	○	○	○
	5) Analysis of pumping test result	○	○	○	○	○	○	○	○	○	○	○
	6) Water quality analysis	-	-	-	○	○	○	○	○	-	○	○
3	Supporting, monitoring and supervision of pumping test	○	○	○	○	○	○	○	○	○	○	○
	1) Receiving access permission from C.A.	○	○	○	○	○	○	○	○	○	○	○
	2) Monitoring and supervision of pumping test	○	○	○	○	○	○	○	○	○	○	○

		18-18/016	18-18/019	18-18/027A	19-14/058B	19-14/062	19-15/028A	19-16/005	19-17/012	19-17/033	19-20/001A	20-17/022
4	Preparation of installation of pumping equipment	○	△	△	△	○	△	○	△	△	△	△
	1) Determination of required specification of pumping equipment	○	△	△	△	○	△	○	△	△	△	△
	2) Preparation of tender document for installation of pumping equipment	○	△	△	△	○	△	○	△	△	△	△
	3) Tendering and contract	○	△	△	△	○	△	○	△	△	△	△
5	Installation of pumping equipment (Contract work)	○	△	△	△	○	△	○	△	△	△	△
	1) Procurement of pumping equipment	○	△	△	△	○	△	○	△	△	△	△
	2) Installation of pumping equipment	○	△	△	△	○	△	○	△	△	△	△
6	Supporting, monitoring and supervision of installation work	○	△	△	△	○	△	○	△	△	△	△
	1) Supporting procurement of pumping equipment	○	△	△	△	○	△	○	△	△	△	△
	2) Receiving access permission from C.A.	○	△	△	△	○	△	○	△	△	△	△
	3) Monitoring and supervision of installation work	○	△	△	△	○	△	○	△	△	△	△
7	Quality inspection	○	△	△	△	○	△	○	△	△	△	△
8	Handing over the rehabilitated equipment	○	△	△	△	○	△	○	△	△	△	△
Software component												
1	Preparation of software component	○	○	○	○	○	○	○	○	○	○	○
	1) Obtaining agreement on rehabilitation from owners and farmers	○	○	○	○	○	○	○	○	○	○	○
	2) Preparation of tender document for software component	○	○	○	○	○	○	○	○	○	○	○
	3) Tendering and contract	○	○	○	○	○	○	○	○	○	○	○
2	Detailed profile survey (Contract work)	○	○	○	○	○	○	○	○	○	○	○
3	Facilitation of establishment of WUA (Contract work)	○	△	△	△	○	△	○	△	△	△	△
	1) Orientation for establishment of WUA	○	△	△	△	○	△	○	△	△	△	△
	2) Clarification of role and responsibility of WUA	○	△	△	△	○	△	○	△	△	△	△
	3) Discussion on water distribution and water tariff	○	△	△	△	○	△	○	△	△	△	△
	4) Election of a leader, board members, administration staff and technical staff	○	△	△	△	○	△	○	△	△	△	△
	5) Registration of WUA	○	△	△	△	○	△	○	△	△	△	△
4	Monitoring and supervision of establishment of WUA	○	△	△	△	○	△	○	△	△	△	△
5	O&M training (Contract work)	○	△	△	△	○	△	○	△	△	△	△
	1) Water distribution planning	○	△	△	△	○	△	○	△	△	△	△
	2) Setting of water tariff	○	△	△	△	○	△	○	△	△	△	△
	3) Maintenance planning of pumping equipment	○	△	△	△	○	△	○	△	△	△	△
	4) Record keeping and accounting	○	△	△	△	○	△	○	△	△	△	△
	5) Follow-up activities for O&M	○	△	△	△	○	△	○	△	△	△	△
6	Monitoring and supervision of O&M training	○	△	△	△	○	△	○	△	△	△	△
7	Training of on-farm water management	○	○	○	○	○	○	○	○	○	○	○
	1) Seasonal cultivating and water requirement planning	○	○	○	○	○	○	○	○	○	○	○
	2) Agriculture input procurement planning	○	○	○	○	○	○	○	○	○	○	○
	3) Management of irrigation facility and equipment	○	○	○	○	○	○	○	○	○	○	○
	4) Water saving irrigation practice	○	○	○	○	○	○	○	○	○	○	○

○: Necessary activities, △: Necessity of activities to be decided in the former activities and to be confirmed in the proceeding study, - : Unnecessary activities

Source: JICA Study Team

Table 17 Work Quantities for Agricultural Wells (Priority Schemes)

Item	Unit	Quantities											
		18-18/016	18-18/019	18-18/027A	19-14/058B	19-14/062	19-15/028A	19-16/005	19-17/012	19-17/033	19-20/001A	20-17/022	
1	Pumping test phase												
	1) Deepening	m	0	50	145	50	0	32	0	30	50	50	30
	2) Developing	L.S.	0	1	1	1	0	1	0	1	1	1	1
	3) Pumping test	L.S.	1	1	1	1	1	1	1	1	1	1	1
	4) Water quality analysis	L.S.	0	0	0	1	1	1	1	1	0	1	1
2	Procurement and installation of pumping equipment phase												
	1) Vertical turbine pump	L.S.	1	1	1	1	1	1	1	1	1	1	1
	- Extraction discharge	m ³ /hour	60	80	100	50	45	50	60	70	70	70	60
	- Head	m	100	120	150	150	150	130	75	120	120	140	130
	2) Lifting pipes (HDPE-6")	m	130	190	190	120	100	110	40	80	97	160	95
	3) Diesel generator	L.S.	0	1	1	0	0	1	1	1	1	1	1
	4) Others*	L.S.	1	1	1	1	1	1	1	1	1	1	1

*Following items are included:

i) Electric motor, ii) non return valve, iii) gate valve, iv) air valve, v) water flow meter, vi) pressure gauge, vii) pressure switch

Source: JICA Study Team

(3) O&M Plan

The list of required activities and responsible unit for O&M are described in the following table.

Table 18 Activity List for Operation and Maintenance Phase


Category	Actions to be taken	Responsibility of the actions	Assisted and monitored by
Pumping equipment	1. To prepare annual water distribution plan and pumping plan 2. To operate pumping equipment based on the plans 3. To maintain pumping equipment 4. To keep records on operation and maintenance cost	WUA	PWA
Groundwater monitoring	1. To keep records on water extraction and distribution	WUA	PWA
	1. To advise WUA about the preparation of the annual water distribution plan and pumping plan 2. To monitor water extraction and distribution based on the records kept by WUA 3. To monitor groundwater level and water quality	PWA	Donors, if necessary
	1. To keep records about WUA activities including collection of water fee and account of WUA. 2. To hold a regular meeting of WUA to monitor the O&M	WUA	PWA
WUA and its financial status	1. To monitor WUA's activities based on the record kept by WUA 2. To provide advice and guidance to WUA	PWA & MoA	Donors, if necessary
	1. To conduct training on on-farm water management	MoA	Donors, if necessary
On-farm water management	1. To conduct efficient on-farm water management based on the training	Farmers	MoA
	1. To monitor the efficient on-farm water management 2. To provide technical advices to the farmers, if necessary	MoA	Donors, if necessary

Source: JICA Study Team

8.2 Development Plan for Spring Water Conveyance System

(1) Site Location of Priority Schemes

The site locations of the priority schemes are shown in the following figure. The Al 'Auja spring source is situated in Area C while the natural reserve area is adjacent to the upper Wadi Al 'Auja. The Al Nwai'mah and Al Dyuk spring sources are at the same location, as well as the Shusah Spring which is one of the private springs.



Source: JICA Study Team

Figure 12 Location of Priority Schemes for Spring Improvement

(2) Development Plan for Priority Scheme

The work components and quantities for the improvement of spring water conveyance system in each priority site are summarized in the following table.

Table 19 Work Components for Spring Improvement (Priority Schemes)

Al 'Auja	Al Dyuk	Al Nwai'mah
1) Installation of conveyance pipelines	1) Installation of conveyance pipelines	1) Installation of conveyance pipelines
2) Construction of settling basin	2) Construction of settling basin	2) Construction of Distribution Box
3) Construction of Distribution Box	3) Construction of Distribution Box	3) Rehabilitation of existing concrete canals
4) Rehabilitation of intake weir	4) Rehabilitation of existing concrete canals	
5) Rehabilitation of existing concrete canals		

Source: JICA Study Team


Table 20 Work Quantity for Spring Improvement (Priority Schemes)

NWA'MAH			DYUK			AUJA		
Item	Unit	Quantity	Item	Unit	Quantity	Item	Unit	Quantity
Pipe Installation	m	4,680	Pipe Installation	m	6,930	Pipe Installation	m	15,010
HDPE-355mm	m	1,720	SP-22"	m	480	SP-26"	m	1,590
HDPE-280mm	m	1,620	SP-18"	m	1,230	SP-22"	m	200
HDPE-225mm	m	1,340	SP-16"	m	760	SP-20"	m	3,720
			SP-12"	m	760	SP-18"	m	4,160
			HDPE-450mm	m	1,080	HDPE-450mm	m	4,280
			HDPE-400mm	m	250	HDPE-400mm	m	1,060
			HDPE-355mm	m	1,420			
			HDPE-280mm	m	950			
Construction			Construction			Construction		
Settling Basin	pcs	0	Settling Basin	pcs	1	Settling Basin	pcs	1
Distribution Box	pcs	8	Distribution Box	pcs	24	Distribution Box	pcs	16
Rehabilitation			Rehabilitation			Rehabilitation		
Intake Rehabilitation	L.S.	0	Intake Rehabilitation	L.S.	0	Intake Rehabilitation	L.S.	1
Canal Rehabilitation	m	2,000	Canal Rehabilitation	m	2,900	Canal Rehabilitation	m	3,750

Source: JICA Study Team

(3) O&M Plan

Roles and responsibility for O&M are illustrated below.



Source: JICA Study Team

Figure 13 Roles and Responsibility for O&M

The activities to be handled for O&M of the spring water conveyance system are shown in the following table:

Table21 Activity List for O&M

Acting Body	Category	Actions to be taken
Village Council	Administration	1. Preparation of annual O&M plan 2. Preparation of financial plan 3. Accounting 4. Maintenance of water right 5. Tariff collection 6. Holding board meetings 7. Monthly and annually reporting on activities
	Monitoring of Water Resources	1. Monitoring of water flow from spring sources by current meter 2. Monitoring of water quality of spring sources by observation

Acting Body	Category	Actions to be taken
	Supervising of Water Conveyance and Distribution	1. Monitoring of water flow in the main and secondary conveyance system by bulk meter or current meter 2. Supervising of farmer's operation activities 3. Monitoring of water quality in the conveyance system by observation 4. Keeping records of monitoring results
	Maintenance of Conveyance System	1. Inspection and patrol of facilities 2. Cleaning of intake, settling basin and pipeline 3. Procurement and replacement of materials deteriorated 4. Rehabilitation of facilities deteriorated 5. Keeping of maintenance records
Water right holders	Operation for Water Distribution	1. Control of gates and valves for distribution 2. Operation of on-farm equipment
	O&M of distribution system	1. Maintenance of distribution pipe and pond 2. Maintenance of on-farm equipment

Source: JICA Study Team

9. Environmental Assessment

Environmental impacts caused by the pilot projects and the priority projects were evaluated through the Initial Environmental Evaluation (IEE), under the JICA Study. At the IEE level, resulting environmental impacts due to these projects were found negligible, except for the project on storm water harvesting. The impacts caused by the storm water harvesting were expected to be serious. However, without the decision on size based on the record of wadis' discharge, detailed environmental study could not be completed. In parallel with the discharge measurement, the other basic information such as geology, concentration of suspended solids in the wadis' discharge, etc. should also be collected in order to conduct the feasibility study on storm water harvesting structures. Therefore, it was concluded that the EIA study be conducted in parallel with the feasibility study on water harvesting structures, after obtaining discharge measurements during at least 5–10 years.


10. Updating and Improvement of GIS Database

(1) Support for Base Map Updating Activities

Base map updating activities started from December 2007 by MoP, in cooperation with the MoA, and through the support of the JICA Study Team. Main work item was the ground truth on land use in the West Bank. The activities were successfully completed and the updated GIS land use data was integrated into the GIS database as mentioned in the following section

(2) Database Development and Enhancement of GIS Capacity

In the course of the study, several types of data were collected. Said data was compiled into the GIS database for water resources development and management in the Jordan River Rift Valley, and the GIS database was handed over to organizations concerned. The final contents of the database are illustrated in the following figure.



Source: JICA Study Team

Figure 14 GIS Database Structure

(3) Support for Consensus Building on Better Data Management

To secure consistency of GIS data in the said GIS database after handing over to the organizations concerned, a meeting on GIS data management was held among responsible personnel of the organizations in August 2008. Finally, tentative GIS committee was established and a consensus on better GIS data management for the future was built.

11. Implementation Plan and Cost Estimates for the Priority Schemes

11.1 Rehabilitation of Agricultural Wells

(1) Implementation Plan for the Rehabilitation of Agricultural Wells

Implementation schedule for the priority schemes for rehabilitation of agricultural wells is as shown in the following figure.

Work item	2010	2011	2012
Hardware component			
1 Preparation for pumping test	■		
2 Pumping test	■	■	
3 Supporting, monitoring and supervision of pumping test	■	■	
4 Preparation for installation of pumping equipment		■	
5 Installation of pumping equipment		■	■
6 Supporting, monitoring and supervision of installation work		■	■
7 Quality inspection			■
8 Handing over the rehabilitated equipments			■
Software component			
1 Preparation of software component	■		
2 Detailed profile survey		■	
3 Supporting, monitoring and supervision of detailed profile survey		■	
4 Facilitation of establishment of WUA		■	■
5 O&M training			■
6 Training of on-farm water management		■	
7 Followup activities for O&M			■

Source: JICA Study Team

Figure 15 Implementation Schedule for Rehabilitation of Agricultural Wells

(2) Cost Estimate for the Rehabilitation of Agricultural Wells

Implementation costs for the rehabilitation of agricultural wells are estimated as shown in the following table.

Table 22 Estimated Costs for Rehabilitation of Agricultural Wells

Item	Total Amount
	(USD)
1. Construction Costs	1,193,687
(1) Pumping Test	445,730
(2) Procurement and Installation of Pumping Equipment	639,440
(3) Administrative Cost 10%	108,517
2. Engineering Costs (Pumping Test & Procurement and Installation of Pumping Equipment)	358,106
3. Software Component Program	434,665
(1) Foreign Expert	150,000
(2) Local Expert	158,800
(3) Transport	70,600
(4) Documentation of Manuals	1,540
(5) Workshop and Training	14,210
(6) Administrative Cost 10%	39,515
4. Contingency 20%	397,292
Total	2,383,750

Source: JICA Study Team

(3) O&M Costs

Costs for O&M of the agricultural wells after the rehabilitation are estimated as shown in the following table.

Table 23 Estimated Annual Total Costs for O&M

	Well ID	Name	O&M costs (USD)	
			Present condition	After electrification
1	18-18/016*	Mustafa Abu Khayzaran	48,575	48,575
2	18-18/019	Abdul Kareem Salem	26,442	15,797
3	18-18/027A	Ibrahem Dyab	8,821	6,383
4	19-14/058B*	Yunes 'Abdu	7,775	7,775
5	19-14/062*	Sa'eed 'Ala' Al Deen	17,915	17,915
6	19-15/028A	Al 'Auja	23,000	13,971
7	19-16/005	'Abed Al'azeez Lubbad Sarrees	19,720	11,685
8	19-17/012	Marj Na'ja C5	22,561	13,532
9	19-17/033	Deya' Saleh 'Abdu	12,482	7,932
10	19-20/001A	Khursheed Mbaslat	5,358	4,058
11	20-17/022	Sulayman Saleh	16,969	10,378
	Total		209,618	158,001

*These wells are supplied electricity under present condition.


Source: JICA Study Team

11.2 Improvement of Spring Water Conveyance System

(1) Implementation Plan for Improvement of Spring Water Conveyance System

Implementation schedule for the priority schemes of improvement of spring water

conveyance system is as shown in the following figure.



Source: JICA Study Team

Figure 16 Implementation Schedule of Priority Scheme

(2) Cost Estimate for the Improvement of Spring Water Conveyance System

Implementation costs for the improvement of spring water conveyance system are estimated as shown in the following table.

Table 24 Estimated Costs for Al 'Auja Improvement Scheme

Item	Total Amount (USD)
[Al 'Auja Spring]	
1. Construction Costs	5,734,900
(1) Direct Construction Costs	5,213,500
- Temporary Works 5%	248,300
- Pipe Installation and Related Works	3,764,200
- Intake Rehabilitation Works	2,100
- Canal Rehabilitation Works	1,198,900
(2) Administrative Cost 10%	521,400
2. Engineering Costs	860,200
(Detailed Design & Construction Supervision)	
3. Software Component Program	533,500
SubTotal	7,128,600
Contingency 20%	1,425,700
Total	8,554,300

Source: JICA Study Team

Table 25 Estimated Costs for Al Nwai'mah and Al Dyuk Improvement Scheme

Item	Total Amount (USD)
[Al Dyuk & Al Nwai'mah Springs]	
1. Construction Costs	4,343,200
(1) Direct Construction Costs	3,948,400
Al Nwai'mah	1,246,100
- Temporary Works 5%	59,300
- Pipe Installation and Related Works	636,900
- Intake Rehabilitation Works	0
- Canal Rehabilitation Works	549,900
Al Dyuk	2,702,300
- Temporary Works 5%	128,700
- Pipe Installation and Related Works	1,764,000
- Intake Rehabilitation Works	0
- Canal Rehabilitation Works	809,600
(2) Administrative Cost 10%	394,800
2. Engineering Costs 15%	592,300
(Detailed Design & Construction Supervision)	
3. Software Component Program	541,100
SubTotal	5,476,600
Contingency 20%	1,095,300
Total	6,571,900

Source: JICA Study Team

(3) O&M Costs

The O&M costs for each spring facility are estimated as shown in the following table.

Table 26 Estimated Annual Total Costs for O&M

(Unit: USD)

Item	Al Nwai'mah	Al Dyuk	Al 'Auja
Depreciation Cost (USD)	49,800	108,100	208,500
Personnel Cost (USD)	30,800	30,800	38,500
Administrative Cost 20%	16,100	27,800	49,400
Total O&M Costs (USD)	96,700	166,700	296,400
Average Discharge for Agr. (Mm ³ /yr)	2.53	4.73	9.55
O&M Costs per m ³ (USD/m ³)	0.038	0.035	0.031

Source: JICA Study Team

12. Project Evaluation

(1) Economic Analysis

Economic internal rate of return (EIRR), net present value (NPV), and benefit – cost ratio (B/C) of each priority scheme are summarized in the following table. The quantitative evaluation results reveal high economic viability.

Table 27 Evaluation Results of the Economic Analysis

	EIRR	NPV@12% (‘000USD)	B/C@12%
Improvement of Spring Conveyance Systems			
Al ‘Auja Spring	23.2%	5,663	1.72
Al Dyuk & Al Nwai’mah Springs	13.5%	472	1.08
Rehabilitation & Management of 11 Agricultural Wells	14.9%	493	1.14

Source: JICA Study Team

(2) Farm Income Analysis

Implementation of the overall priority projects also benefits the farmer’s household income. The farm income analysis has indicated that a typical vegetable-producing farmer’s household would obtain an additional irrigated land of 5.5 dunum, and thereby raising their household income by 35% (equivalent to USD2,700 per annum).

13. Technology Transfer

The technology transfer to the counterpart personnel, conducted mainly while on the job, was carried out by the study team throughout the study period, in accordance with the Technology Transfer Program.

A training course program to Jordan was carried out from June 29 to July 2, 2008, aiming to develop the skills of the Palestinian counterpart personnel on surface water monitoring, which is intended for the development of storm water harvesting. It also aimed to develop skills on ground water monitoring for better ground water resources management.

As a part of technology transfer as well as information disclosure, seminars on water resources development and management in the Jordan River Rift Valley were held twice which were first seminar on May 28, 2008 and second seminar on November 19, 2008. Counterpart agencies for the Study, other relevant agencies in Palestine including local government, donors, NGOs and village council were participated in the seminars.

14. Conclusion and Recommendations

(1) Conclusions

As a result of the feasibility study, it was realized that the implementation of the proposed priority schemes is technically sound and economically viable. From the institutional and organizational, social and natural environmental aspects, it was also found that the schemes are generally sound. Execution of the schemes could accomplish the principal objective of efficient utilization of water, and increase the agricultural production through harmonized implementation of hardware and software components. Thus, it is concluded that the schemes should be implemented in the manner planned in this Study.

(2) Recommendations

- 1) In order to achieve the effective utilization of water resources, water resources development and management plans in the study should be implemented with close

coordination between hardware component (consisting of rehabilitation of agricultural wells and improvement of spring conveyance system as well as development of new water resources) and software components (comprising of establishment of water users association for integrated management of agricultural wells, capacity building of O & M organizations and training of farmers for farming practice on water saving irrigation).

- 2) Water resources development plan has been formulated considering short, medium and long term plans as mentioned in Chapter 6 of the main text. The execution of this study, in fact, experienced shortage of data and information especially required for the preparation of new water resources development in the Study Area. Moreover, required investigations to support the existing data were also difficult to execute due to the issuance of security situation permits. Accordingly, it is recommended that execution of rehabilitation and improvement of the existing irrigation system should proceed ahead since a more accurate data and information will be required for the preparation of new water resources development plan.
- 3) In connection with recommendation 2) above, storm water harvesting plan in this study has been prepared with several limited conditions due to insufficient data available for the preparation of the plan. It is recommended that data such as meteorological and hydrological data be obtained during the short and medium terms of the water resources development. After these data were sufficiently obtained and collected, the storm water harvesting plan (preliminary plan prepared in this study) will be reviewed and revised to confirm its feasibility.
- 4) Any water resources development including rehabilitation and improvement of existing facilities in the Study Area require JWC approval as well as permission from the civil administration of Israel, prior to implementation. It often takes time to obtain such approval and permission. It is expected that this process will be relieved within a few year. However, it is recommended that PWA shall apply to JWC as well as the civil administration at an early stage in accordance with the implementation plan before settlement on this matter.
- 5) After the Study Period, it is recommended that monitoring and evaluation of the pilot project should be continued periodically. In particular, sustainability of WUA activity is the most important element for O&M of water supply facility. Lessons learned from WUA activity would be helpful for formation process in the priority schemes.
- 6) For the rehabilitation of agricultural wells, joint management through WUA by well owners and water users is important for the sustainable water management. In particular, introduction of water tariff system is vital for the future renewal of facility and equipment by the WUA. Clarification of water fee by tariff could help farmers to have motivation to examine and lower the production cost of agriculture produces.
- 7) Since electrification in the Study Area is under development, it is recommended that power sources for future plan such rehabilitation of wells should be examined

depending on progress of the electrification, in order to save O&M cost.

- 8) There is a water resource registration system for wells in the central government, but it is not functioning well. Modification of the system is recommended in order to control and restrict well abstraction according to the license volumes in parallel with establishment of monitoring system of water utilization.
- 9) The central government does not have any registration system for springs although wells registration system exists. It is recommended to establish the registration, monitoring and restriction system of spring water right and its actual utilization as a bylaw.
- 10) It is necessary to hold workshops for explanation of proposed new conveyance and distribution system and its operation and maintenance method and to conduct site investigations with water right holders to determine the new conveyance alignment, distribution boxes and outlets for farmers in the designing stages for the priority schemes.
- 11) In parallel with the implementation of the priority schemes, proper on-farm water management should be extended. In particular, capacity development of extension agents is encouraged.
- 12) Based on the IEE study for the storm water harvesting, it is concluded that the environmental assessment study should be conducted prior to implementation of pilot project for the storm water harvesting.
- 13) Recycled water from wastewater and desalted water are other new water resource for irrigation purposes. The availability of recycled water depends on the progress of development of sewerage network and treatment systems in major cities. Introduction of water recycling from wastewater as well as desalination, in taking into consideration the shortage of absolute water volume in the study area, is recommended, although related details are excluded from this study.
- 14) Other than the water resources development in the basic plan of this study, many micro irrigation facilities in the field exist, such as micro spring, pond and others. It should be realized that these facilities need to be maintained in order to utilize the limited available water effectively.
- 15) All the findings and lessons learned through the implementation of the pilot projects are quite important and precious for the every stakeholder concerned to the water resources development and management in the Jordan River Rift Valley. Those findings and lessons learned are outcomes from what JICA Study Team and Palestinian counterparts have acquired through the implementation of the pilot projects of this study. It is recommended that those precious findings and lessons learned are reviewed either for the implementation of the priority schemes or preparation of other new water resources development and management plans by the related Palestinian authorities.

**THE FEASIBILITY STUDY
ON
WATER RESOURCES DEVELOPMENT AND MANAGEMENT
IN
THE JORDAN RIVER RIFT VALLEY**

FINAL REPORT

VOLUME-I

MAIN REPORT

TABLE OF CONTENTS

PREFACE

LETTER OF TRANSMITTAL

LOCATION MAP

PHOTOGRAPHS

EXECUTIVE SUMMARY

	Page
CHAPTER 1 INTRODUCTION.....	1-1
1.1 Authority	1-1
1.2 Background	1-1
1.3 Objectives of the Study	1-2
1.4 Study Area	1-2
1.5 Work Schedule	1-2
1.6 Counterpart and Steering Committee	1-3
CHAPTER 2 OUTLINE AND ACTIVITIES OF THE STUDY	2-1
2.1 General	2-1
2.2 Outline of the Study	2-1
2.2.1 Home Office Preparatory Work (March 2007)	2-1
2.2.2 First Field Work (March 2007 to August 2007)	2-1
2.2.3 Second Field Work (1) (October 2007 to March 2008)	2-5
2.2.4 First Home Office Work (March 2008 to April 2008)	2-6
2.2.5 Second Field Work (2) (May 2008 to August 2008)	2-6
2.2.6 Second Home Office Work (September 2008).....	2-9
2.2.7 Third Field Work (November 2008)	2-9
2.2.8 Third Home Office Work (December 2008)	2-9

CHAPTER 3	THE STUDY AREA	3-1
3.1	General Conditions of the Study Area.....	3-1
3.1.1	Topography and Landscapes	3-1
3.1.2	Climate	3-1
3.1.3	Geology and Hydrogeology	3-4
3.2	Present Land Use in the Study Area.....	3-8
3.3	Socio-Economic Conditions.....	3-9
3.3.1	Demography	3-9
3.3.2	Administration.....	3-10
3.3.3	Employment	3-10
3.3.4	Economic Trends.....	3-12
3.3.5	Local Financial System	3-15
3.3.6	Education.....	3-16
3.3.7	Health	3-16
3.3.8	Poverty	3-16
3.3.9	Gender Issue.....	3-17
3.4	Agriculture	3-18
3.4.1	Farm Households and Land Tenure Systems	3-18
3.4.2	Agricultural Land Use.....	3-19
3.4.3	Agricultural Production.....	3-20
3.4.4	Livestock	3-24
3.4.5	Marketing	3-24
3.4.6	Agriculture Extension Service	3-25
3.4.7	Constraints on Agricultural Development.....	3-26
3.5	Water Resources Management	3-28
3.5.1	Watersheds.....	3-28
3.5.2	Agricultural Wells	3-29
3.5.3	Spring Water.....	3-32
3.5.4	On-Farm Facilities and Management.....	3-41
3.6	Constraints on Water Resources Development and Management.....	3-44
3.6.1	Socio-Economic Conditions.....	3-44
3.6.2	Existing Water Resources.....	3-44
CHAPTER 4	HYDROLOGY AND HYDROGEOLOGY.....	4-1
4.1	General	4-1
4.2	Hydrological Analysis	4-5
4.2.1	General Climate.....	4-5
4.2.2	Rainfall Analysis	4-8

4.2.3	Discharge Measurements Conducted by PWA on Wadi Qilt and Wadi Far'a	4-12
4.2.4	Flood Runoff Data on Wadi Qilt, Provided by Israel	4-14
4.2.5	Preliminary Runoff Analysis on Wadi Qilt	4-16
4.2.6	Preliminary Runoff Analysis on Wadi Far'a	4-17
4.2.7	Flood Analysis	4-18
4.2.8	Sedimentation	4-19
4.2.9	Assessment of Availability of Hydrological Data for Feasibility Study of Storm Water Harvesting Project	4-19
4.3	Hydro-Geological Environment of Study Area	4-22
4.3.1	Hydrogeology and Aquifer System	4-22
4.3.2	Hydraulic Parameter of Aquifer	4-27
4.3.3	Groundwater Flow	4-29
4.3.4	Groundwater Use	4-33
4.3.5	Spring Water	4-40
4.3.6	Groundwater Quality	4-44
4.3.7	Evaluation of Groundwater Resources	4-54
4.3.8	Analysis of Effective Use of Seasonal Variation of Spring by Groundwater Simulation	4-57
4.4	Potential Water Resources	4-60
4.4.1	General	4-60
4.4.2	Effective Rainfall and Effective Catchment in Each Catchment	4-62
4.4.3	Water Resources Amount by Water Source	4-66
4.4.4	Overall Assessment of Results of Estimated Water Resources Amount in the Study Area	4-66
CHAPTER 5	COMPREHENSIVE WATER RESOURCES MANAGEMENT AND DEVELOPMENT	5-1
5.1	Development Plan in Palestine	5-1
5.1.1	Medium Term Development Plan	5-1
5.1.2	National Water Policy and Strategy	5-2
5.1.3	Agricultural Medium Term Development Plan 2006-2008	5-3
5.1.4	Oslo II Accords	5-4
5.1.5	Organization of Water Resources Development in Palestine	5-4
5.2	Water Resources in the Study Area	5-6
5.2.1	Present Water Resources	5-6
5.2.2	Present Water Demand	5-8
5.2.3	Present Water Balance	5-8
5.2.4	New Water Resources in the Study Area	5-11

5.2.5	Constraints on Water Resources Development and Management	5-11
5.2.6	Strategies for Water Resources Development and Management	5-11
5.3	Future Potential of Water Resources in the Study Area	5-12
5.3.1	Future Potential of Water Resources	5-12
5.3.2	Future Water Balance	5-15
CHAPTER 6	BASIC PLAN FOR WATER RESOURCES DEVELOPMENT AND MANAGEMENT	6-1
6.1	Baseline Survey and Inventory Survey	6-1
6.1.1	Baseline Survey	6-1
6.1.2	Inventory Survey on Agricultural Wells and Springs.....	6-13
6.2	Basic Plan for Rehabilitation and Integrated Management of Agricultural Wells.....	6-17
6.2.1	Basic Consideration for the Rehabilitation of Private Well as a Public Project	6-17
6.2.2	Concept of the Basic Plan for the Rehabilitation of Agricultural Wells	6-17
6.2.3	Selection of the First Priority Agricultural Wells for Rehabilitation	6-18
6.2.4	Recommendation for Further Rehabilitation of Remaining Agricultural Wells	6-22
6.2.5	Basic Plan for Integrated Management of Wells.....	6-25
6.3	Basic Plan for Improvement of Spring Water Conveyance System.....	6-30
6.3.1	Basic Consideration for Improvement of Spring Water Conveyance System	6-30
6.3.2	Concept of Basic Plan for Improvement of Spring Water Conveyance System	6-31
6.3.3	Prioritization of Improvement of Spring Water Conveyance System	6-33
6.3.4	Implementation Plan for Improvement of Spring Conveyance System	6-37
6.3.5	Basic Plan for Integrated Management of Spring Water Conveyance System	6-40
6.4	Basic Plan for Storm Water Harvesting.....	6-43
6.4.1	Basic Concept for Formulation of Basic Plan for Storm Water Harvesting	6-43
6.4.2	Selection of Prospective Storm Water Harvesting Plans.....	6-44

6.4.3	Consideration of Measures against Evaporation and Suspended Load	6-52
6.4.4	Pre-feasibility Study for Storm Water Harvesting.....	6-54
6.4.5	Further Investigation Schedule with List of Information Required	6-71
6.4.6	Installation Plan of Hydrological Station	6-73
6.4.7	Pilot Project for Storm Water Harvesting.....	6-80
6.4.8	Draft TOR for Future Feasibility Study for Storm Water Harvesting	6-87
6.5	On-farm Water Management.....	6-90
6.5.1	Present Status of Irrigation System	6-90
6.5.2	Efficient Water Use for Irrigation.....	6-90
6.5.3	Constraints of On-farm Application Efficiency	6-92
6.5.4	Activity to Cope with Constraints on Water Saving Irrigation ..	6-94
6.5.5	Concept on Water Saving Irrigation	6-95
6.5.6	Training Course for On-farm Water Management	6-95
6.5.7	Water Economical Efficiency and Value-added	6-106
6.5.8	Value-added in Cultivation Phase	6-107
6.5.9	Value-added in Processing Phase	6-113
6.5.10	Concept of Value-added Process	6-113
6.6	Implementation Program for Water Resource Development	6-114
CHAPTER 7	PILOT PROJECT.....	7-1
7.1	Objective of Pilot Project	7-1
7.2	Selection of Pilot Project for Rehabilitation of Agricultural Wells.....	7-2
7.2.1	Selection Criteria.....	7-2
7.2.2	Pilot Project for Rehabilitation and Integrated Management for Agricultural Wells.....	7-4
7.3	Selection of Pilot Project for Improvement of Spring Water Conveyance System.....	7-6
7.3.1	Selection Criteria.....	7-6
7.3.2	Pilot Project for Improvement of Spring Water Conveyance System	7-8
7.4	Supporting System for Water Resources Management.....	7-9
7.4.1	Assistance for Establishment and Capacity Building of WUA for Agricultural Wells.....	7-9
7.4.2	Assistance for Establishment of Coordination Committee and Capacity Building of Village Council for Spring.....	7-12

7.5	Implementation Schedule of Pilot Project.....	7-14
7.5.1	Pilot Project for Rehabilitation of Agricultural Wells.....	7-14
7.5.2	Pilot Project for Improvement of Spring Water Conveyance System	7-15
7.5.3	Supporting System for Water Resources Management.....	7-15
7.6	Monitoring and Evaluation of Pilot Project	7-16
7.6.1	Project Design Matrix (PDM) of Pilot Project.....	7-16
7.6.2	Monitoring Method	7-19
7.6.3	Evaluation Method	7-19
7.6.4	Monitoring and Evaluation of Pilot Project	7-19
7.6.5	Monitoring and Evaluation of the Pilot Project in Post Study Period	7-28
CHAPTER 8	FEASIBILITY STUDY ON PRIORITY SCHEMES	8-1
8.1	Development Plan for the Rehabilitation of Agricultural Wells	8-1
8.1.1	Preparation of Development Plan for the Rehabilitation of Agricultural Wells	8-1
8.1.2	Development Plan for Rehabilitation of Agricultural Wells	8-10
8.1.3	Operation and Maintenance (O&M) Plan	8-10
8.2	Development Plan for Improvement of Spring Water Conveyance System.....	8-11
8.2.1	Site Location of Priority Schemes.....	8-11
8.2.2	Development Plan for Priority Schemes	8-12
8.2.3	Operation and Maintenance (O&M) Plan	8-27
CHAPTER 9	ENVIRONMENTAL ASSESSMENT	9-1
9.1	General	9-1
9.2	Legal Basis on Environmental Assessment.....	9-1
9.2.1	Palestinian Environmental Assessment Policy.....	9-1
9.2.2	Water-related Laws.....	9-3
9.2.3	Land-related Laws.....	9-8
9.2.4	Organizations Concerned with Agricultural Water Use	9-8
9.3	Initial Environmental Evaluation	9-8
9.3.1	Purpose of Initial Environmental Evaluation	9-9
9.3.2	Methodology of IEE.....	9-9
9.3.3	Identification of Conceivable Impacts of Priority Projects for Feasibility Study.....	9-9
9.3.4	Mitigation Measures for Major Environmental and Social Impacts	9-16

9.3.5	Identification of Conceivable Impacts of Pilot Projects.....	9-19
9.3.6	Conclusion of IEE	9-20
9.4	Tentative Environmental Assessment on Storm Water Harvesting	9-21
9.5	Environmental Monitoring and Management Plan	9-25
9.6	Information Disclosure.....	9-30
CHAPTER 10	UPDATING AND IMPROVEMENT OF GIS DATABASE.....	10-1
10.1	Objectives and Approaches to Update and Improve GIS Database.....	10-1
10.2	Review of Present Data Management Structure.....	10-1
10.2.1	Data Management in Ministry of Agriculture (MoA).....	10-1
10.2.2	Data Management in Palestinian Water Authority (PWA).....	10-2
10.2.3	GIS Data Management in Ministry of Planning (MoP)	10-2
10.2.4	GIS Data Management in Environment Quality Authority (EQA).....	10-3
10.3	Problem Identification on GIS Activities	10-3
10.3.1	Review of Collected GIS Data from Technical Aspect.....	10-3
10.3.2	Review of Data Management System from Institutional Aspect.....	10-4
10.3.3	1st Joint Meeting on GIS Data Management	10-5
10.4	Activities for Updating and Improvement of GIS.....	10-7
10.4.1	Support for Base Map Updating Activities	10-7
10.4.2	Database Development and Enhancement of GIS Capacity	10-8
10.4.3	Support for Consensus Building on Better Data Management ..	10-9
10.5	Recommendations for Further Improvement of Data Management	10-11
10.5.1	Issues for Data Management	10-11
10.5.2	Recommended Actions for Improvement of Data Management	10-12
CHAPTER 11	IMPLEMENTATION PLAN AND COST ESTIMATES OF PRIORITY SCHEMES	11-1
11.1	Rehabilitation of Agricultural Wells.....	11-1
11.1.1	Proposed Works for the Rehabilitation of Agricultural Wells....	11-1
11.1.2	Implementation Plan for the Rehabilitation of Agricultural Wells.....	11-2
11.1.3	Cost Estimates for the Rehabilitation of Agricultural Wells	11-3
11.1.4	Costs for Operation and Maintenance (O&M).....	11-4
11.2	Improvement of Spring Water Conveyance System	11-4
11.2.1	Proposed Works for the Improvement of Spring Water Conveyance System	11-4

11.2.2	Implementation Plan for the Improvement of Spring Water Conveyance System	11-5
11.2.3	Cost Estimates for the Improvement of Spring Water Conveyance System	11-9
11.2.4	Costs for Operation and Maintenance (O&M).....	11-11
CHAPTER 12 PROJECT EVALUATION		12-1
12.1	Approach and Methodology of Evaluation	12-1
12.2	Economic Analysis	12-1
12.2.1	Assumptions	12-1
12.2.2	Economic Costs	12-2
12.2.3	Economic Benefits	12-4
12.2.4	Evaluation Results of the Economic Analysis.....	12-8
12.3	Financial Analysis	12-10
CHAPTER 13 TECHNOLOGY TRANSFER		13-1
13.1	General	13-1
13.2	Execution of Technology Transfer	13-1
13.2.1	On the Job Training	13-1
13.2.2	Training Course in Jordan	13-2
13.2.3	Seminar on Water Resources Development and Management...	13-4
CHAPTER 14 CONCLUSION AND RECOMMENDATIONS		14-1
14.1	Conclusion.....	14-1
14.2	Recommendations	14-1

LIST OF ATTACHMENTS

	Page
Attachment-1	Scope of Work (S/W) AT1-1
Attachment-2	Minutes of Meeting on Inception Report AT2-1
Attachment-3	Minutes of Meeting on 2nd Steering Meeting AT3-1
Attachment-4	Minutes of Meeting on 3rd Steering Meeting AT4-1
Attachment-5	Minutes of Meeting on 4th Steering Meeting AT5-1

LIST OF TABLES

	Page
Table 3.2.1	Land Use Distribution of the Study Area 3-8
Table 3.3.1	Population Change between 1997 and 2005 3-9
Table 3.3.2	Area of Governorate, Population and Population Density of the Palestinian Territory by Governorate/ District, 2005..... 3-9
Table 3.3.3	Population Projection of the Study Area 3-10
Table 3.3.4	Labor Force Indicators in the Palestinian Territory by Governorate/District, January- March, 2007..... 3-11
Table 3.3.5	Consumer Price Index and Rate of Change by Major Expenditure Groups, 2003-2005 3-14
Table 3.3.6	Average Daily Wage for Wage Employees by Economic Activity and Place ... 3-14
Table 3.3.7	Palestinian Imports Indicators, 2000-2004..... 3-15
Table 3.3.8	Poverty Rates According to Actual Monthly Consumption Patterns of Households 1998- 2005 3-17
Table 3.3.9	Full or Partial Participation in Activities by Sex..... 3-17
Table 3.4.1	Population and Farm Household Type 3-18
Table 3.4.2	Agricultural Land Use in the Study Area 3-20
Table 3.4.3	Characteristics of Farming by Locality 3-20
Table 3.4.4	Field Cropped Area, Yield and Production of Field Crops and Forages in Jericho and Tubas (2004/05) 3-21
Table 3.4.5	Field Cropped Area, Yield and Production of Vegetables in Jericho and Tubas (2004/05) 3-22
Table 3.4.6	Field Cropped Area, Yield and Production of Fruits in Jericho and Tubas (2004/05)..... 3-23
Table 3.4.7	Livestock Production in Jericho and Tubas (2004/05)..... 3-24
Table 3.5.1	Major Wadi Basins in the Study Area 3-28
Table 3.5.2	Summary of Agricultural Wells..... 3-29
Table 3.5.3	Spring Discharge in West Bank in 2003..... 3-32
Table 3.5.4	Spring Discharge in West Bank in 2003..... 3-33
Table 3.5.5	List of Spring Group in the Study Area..... 3-34

Table 3.5.6	Estimated Spring Water Allocation to Agricultural and Domestic Uses	3-37
Table 3.5.7	Current Situation of Spring Water Use for Agriculture	3-37
Table 3.5.8	O&M and Water Users Organization	3-39
Table 3.5.9	Water Tariff	3-40
Table 3.5.10	Comparison of Irrigation System in Relation to Site and Situational Factors ..	3-44
Table 4.1.1	List of Rainfall Stations in the West Bank (Functional Stations Only).....	4-2
Table 4.2.1	Annual Mean Monthly Air Temperature and Relative Humidity, Monthly Rainfall and Mean Monthly Evaporation at Jericho	4-6
Table 4.2.2	Annual Mean Monthly Air Temperature and Relative Humidity, Monthly Rainfall and Mean Monthly Evaporation at Nablus.....	4-6
Table 4.2.3	List of Rainfall Stations in Drainage Areas of Wadis Covered by this Study ...	4-8
Table 4.2.4	Annual Rainfall Records in and around the Study Area	4-9
Table 4.2.5	Results of Current Metering Carried out by PWA on the Wadi Qilt (Extracted from the 1998 FORMARD Report).....	4-13
Table 4.2.6	Results of Current Metering Carried out by PWA on the Wadi Qilt and Wadi Far'a (Obtained from PWA in This Study)	4-13
Table 4.2.7	Observed Flood Runoff at Station No. 46150 on Wadi Qilt, Provided by Israel.....	4-15
Table 4.2.8	Mean Monthly Discharges of Observed Flow at Al-Badan Stream Gauge.....	4-17
Table 4.2.9	Mean Monthly Discharge of Observed Flow at Al-Far'a Stream Gauge.....	4-17
Table 4.2.10	Probable Floods Estimated for Catchment of the Kafrein Dam in Jordan (CA=161 km ²) and Their Creager's C Values.....	4-18
Table 4.2.11	Estimated Probable Floods for Catchment of Wadi Qilt and Al Badan	4-18
Table 4.3.1	Geological Stratigraphy	4-22
Table 4.3.2	Hydraulic Parameters of Eastern Aquifer.....	4-27
Table 4.3.3 (1)	Pumping Test Data and the Result of Analysis – (19-14/081)	4-28
Table 4.3.3 (2)	Pumping Test Data and the Result of Analysis – (19-14/052)	4-28
Table 4.3.3 (3)	Pumping Test Data and the Result of Analysis – (19-13/015)	4-29
Table 4.3.4	Springs in the Study Area.....	4-41
Table 4.3.5	Summary of Change of Annual Groundwater Balance by Artificial Recharge (1976 – 1999).....	4-58
Table 4.4.1	Surface Water (SW) and Groundwater (GW) Areas of 9 Wadi Basins	4-61
Table 4.4.2	Marginal Ground Elevation and Annual Rainfall	4-63
Table 4.4.3	Catchment Area at 50 m Intervals of Contour Lines in Each Wadi Basin	4-64
Table 4.4.4	Catchment Area at 50 mm Interval of Annual Rainfall in Each Wadi Basin	4-65
Table 4.4.5	Estimated Potential Water Resources in the Study Area	4-67
Table 5.1.1	Water Allocation Recognized under Oslo II Accords	5-4
Table 5.1.2	Existing and Future Institutional Framework of the Water Sector.....	5-5
Table 5.2.1	Present Water Resources in 2005	5-6
Table 5.2.2	Present Agricultural Water Demand in 2004/2005.....	5-8
Table 5.2.3	Present Municipal and Industrial Water Demand in 2005.....	5-8
Table 5.2.4	Characteristics of Sub-regions in the Study Area.....	5-10

Table 5.2.5	Strategies for Water Resources Development and Management of Sub-regions in the Study Area.....	5-12
Table 5.3.1	Future Increased Volume through Improvement of the Spring Water Conveyance System	5-13
Table 5.3.2	Future Increased Volume through Rehabilitation of Existing Wells	5-13
Table 5.3.3	Future Volume to be Increased by Water Recycling System.....	5-14
Table 5.3.4	Future Potential Water Volume in the Study Area.....	5-14
Table 5.3.5	Future Municipal and Industrial Water Demand	5-15
Table 5.3.6	Future M&I Water Demands and Water Available for Agriculture	5-16
Table 6.1.1	Sample Distribution	6-1
Table 6.1.2	Basic Information of Surveyed Households.....	6-2
Table 6.1.3	Average Agricultural Land Area Used and Owned by the Family	6-2
Table 6.1.4	Average Cultivated Area per Family (Field Crops).....	6-5
Table 6.1.5	Average Cultivated Area per Family (Fruits).....	6-5
Table 6.1.6	Average Cultivated Area per Family (Vegetables).....	6-5
Table 6.1.7	Livestock Owned by Family	6-6
Table 6.1.8	Percentage of Respondents Owning Agricultural Equipment and Facilities	6-6
Table 6.1.9	Income Source and Dependence	6-6
Table 6.1.10	Evaluation of Monthly Income in Last 5 years	6-8
Table 6.1.11	Self Evaluation of Living Standard.....	6-8
Table 6.1.12	Ranking of Problems and Respondents.....	6-13
Table 6.1.13	Summary of Inventory for Agricultural Wells	6-15
Table 6.1.14	Summary of Inventory for Springs	6-16
Table 6.2.1	List of High Priority Wells Selected by PWA and MoA	6-20
Table 6.2.2	Recommended Criteria for the Prioritization of Agricultural Wells	6-23
Table 6.2.3	Next Priority Wells Recommended by PWA and MoA.....	6-24
Table 6.3.1	Result of Spring Inventory Survey.....	6-33
Table 6.3.2	First Evaluation for Shortlist of Priority Scheme.....	6-35
Table 6.3.3	Water Resources Availability for Shortlisted Site	6-35
Table 6.3.4	Estimated Water Loss in Conveyance System	6-36
Table 6.3.5	Proposed Long-term Project	6-38
Table 6.3.6	Proposed Work Item for the Future Project.....	6-38
Table 6.3.7	Provisional Cost Estimate for Priority Scheme.....	6-39
Table 6.3.8	Provisional Cost Estimate for Future Project.....	6-39
Table 6.4.1	Basic Concept for Storm Water Harvesting	6-43
Table 6.4.2	Conceivable Types of Storm Water Harvesting Facilities	6-45
Table 6.4.3	Identified Storm Water Harvesting Plans in Three Major Wadi Basins	6-47
Table 6.4.4	Summary of Quantity Calculation	6-56
Table 6.4.5	Summary of Quantity Calculation for Storm Water Harvesting Facility at Wadi Auja.....	6-65
Table 6.4.6	Summary of Tentative Evaluation Result of the Prospective Plans	6-70
Table 6.4.7	Main Field Survey and Investigation Works for the Storm Water Harvesting	6-71

Table 6.4.8	Proposed New Stream Gauges on Wadi Qilt and Wadi Auja	6-77
Table 6.4.9	Water Storage Capacity of Candidate Sites.....	6-82
Table 6.4.10	Sample of a Record Note	6-87
Table 6.5.1	Use of Irrigation Practices in the Jordan River Rift Valley.....	6-90
Table 6.5.2	Agricultural Water Demand	6-92
Table 6.5.3	Constraints and Countermeasures on Irrigation Efficiency	6-94
Table 6.5.4	Outline of Training Components.....	6-96
Table 6.5.5	List of Pilot Project Sites for Well Rehabilitation.....	6-96
Table 6.5.6	Training Program	6-97
Table 6.5.7	Training Participants	6-97
Table 6.5.8	Answerer to the Pre-training Questionnaire.....	6-98
Table 6.5.9	Answerer to the Post-training Questionnaire	6-99
Table 6.5.10	Impact of Training.....	6-105
Table 6.5.11	Palestinian Export of Fresh Fruits and Vegetables by Destination Country/Area, 1999-2005	6-107
Table 6.5.12	Comparison Table of Gross Margin and Profit of Major Crops in the Study Area (2006/2007)	6-107
Table 6.5.13	Comparison Table of Water Efficiency of Major Crops in the Study Area (2006/2007).....	6-109
Table 6.5.14	Comparison Table of Labor Efficiency of Major Crops in the Study Area (2006/2007).....	6-111
Table 6.6.1	Implementation Program for Water Resources Development.....	6-114
Table 7.2.1	Evaluation Marks in the Criteria for Wells from Technical View	7-2
Table 7.2.2	Evaluation Marks in the Criteria of Wells from Socio-economic View.....	7-2
Table 7.2.3	Result of Final Evaluation to Select Pilot Project Sites for Rehabilitation of Agricultural Wells	7-3
Table 7.2.4	Sites and Needs for Well Rehabilitation of Pilot Projects.....	7-4
Table 7.3.1	Evaluation Marks in the Criteria.....	7-7
Table 7.3.2	Result of Final Evaluation for Spring Improvement Pilot Project	7-8
Table 7.3.3	Work Item and Cost of Nwai'mah Pilot Project.....	7-9
Table 7.4.1	Activity of Assistance at Each Stage (Agricultural Wells).....	7-10
Table 7.4.2	Activity of Assistance at Each Stage (Spring Water Conveyance System).....	7-12
Table 7.6.1	PDM: Pilot Project for Well Rehabilitation	7-17
Table 7.6.2	PDM: Pilot Project for Improvement of Spring Water Conveyance System	7-18
Table 7.6.3	Progress of Activities in the Pilot Project for Rehabilitation of Agriculture Wells.....	7-19
Table 7.6.4	Evaluation Grid based on PDM for Rehabilitation of Agriculture Wells.....	7-20
Table 7.6.5	The Results of Pumping Test	7-22
Table 7.6.6	Progress of Activities in the Pilot Project for Improvement of Spring Water Conveyance system.....	7-24
Table 7.6.7	Evaluation Grid based on PDM for Improvement of Spring Water Conveyance System	7-25

Table 8.1.1	Mechanical Condition of the Priority Wells.....	8-2
Table 8.1.2	Hydrogeological Condition of the Priority Wells.....	8-2
Table 8.1.3	Socio-economic Condition around the Priority Wells.....	8-3
Table 8.1.4	Summary of Detailed Survey and Assessment of the Priority Schemes	8-3
Table 8.1.5	Expected Condition of the Priority Wells after Rehabilitation.....	8-8
Table 8.1.6	Work Components and Quantities for Priority Scheme	8-9
Table 8.1.7	Activity List for Operation and Maintenance Phase	8-11
Table 8.2.1	Outline of Priority Site for Spring Improvement	8-12
Table 8.2.2	Average Discharge of Priority Spring	8-13
Table 8.2.3	Outline of Spring Conveyance Facility	8-13
Table 8.2.4	Spring Water Users Category	8-15
Table 8.2.5	Spring Water Right Allocation by Conveyance Blocks	8-16
Table 8.2.6	Design Flow for Al Nwai'mah and Al Dyuk Springs	8-20
Table 8.2.7	Coefficient for Hydraulic Calculation.....	8-21
Table 8.2.8	Design Flow for Al Nwai'mah and Al Dyuk Springs	8-21
Table 8.2.9	Pipe Materials to be Adopted	8-21
Table 8.2.10	Advantage/Disadvantage of Alternatives	8-23
Table 8.2.11	Work Components and Quantities for Priority Scheme	8-26
Table 8.2.12	Proposed Form for List of Water Right Holders	8-29
Table 8.2.13	Number of Water Flow Monitoring Points.....	8-29
Table 8.2.14	Activity List for O&M.....	8-30
Table 8.2.15	Necessary Staff and Tasks of O&M Team in Village Council	8-31
Table 8.2.16	Work Item of Software Component Program.....	8-31
Table 9.2.1	Valued Environmental Components.....	9-2
Table 9.2.2	Environmental Laws and Regulations	9-3
Table 9.2.3	Water-related Laws Introduced to Palestine.....	9-4
Table 9.2.4	Water-related Laws and Regulations.....	9-4
Table 9.2.5	Palestinian Guideline for Drinking Water	9-5
Table 9.2.6	Treated Wastewater Quality by Basic Indicators	9-5
Table 9.2.7	Number of Barriers Required for Different Crops and the Types of Treated Wastewater	9-7
Table 9.2.8	Land-related Laws and Regulations.....	9-8
Table 9.2.9	Organizations Concerned with Agricultural Water Use	9-8
Table 9.3.1	Scoping Matrix for Rehabilitation of Agricultural Wells	9-10
Table 9.3.2	Scoping Matrix for Improvement of Spring Water Conveyance System.....	9-12
Table 9.3.3	Scoping Matrix for Potential Storm Water Harvesting	9-14
Table 9.3.4	Mitigation Measures Taken for Major Environmental and Social Impacts in the Implementation of the Pilot Projects.....	9-19
Table 9.4.1	Scoping Matrix for Pilot Project of Storm Water Harvesting (As of July 2008)	9-23
Table 9.5.1	Environmental Monitoring and Management Plan (Rehabilitation of Agricultural Wells).....	9-26

Table 9.5.2	Environmental Monitoring and Management Plan (Improvement of Spring Water Conveyance System).....	9-28
Table 10.2.1	Roles and Responsibilities on Data Management in MoA	10-1
Table 10.2.2	Roles and Responsibilities on Data Management in PWA	10-2
Table 10.3.1	List of Differences Observed in the Collected GIS Data	10-3
Table 10.4.1	Activities for Updating and Improvement of GIS.....	10-7
Table 10.4.2	Summary of 2nd Joint Meeting on GIS Data Management.....	10-9
Table 11.1.1	Work Items for the Rehabilitation of Agricultural Wells	11-1
Table 11.1.2	Costs for the Rehabilitation of Agricultural Wells	11-4
Table 11.1.3	Estimated Annual Total Costs for O&M.....	11-4
Table 11.2.1	Work Components of Priority Scheme.....	11-5
Table 11.2.2	Quantities of Construction Material for Priority Scheme	11-5
Table 11.2.3	Estimated Costs for AI ‘Auja Improvement Scheme	11-10
Table 11.2.4	Estimated Costs for AI Nwai’mah and AI Dyuk Improvement Scheme	11-10
Table 11.2.5	Estimated Costs for Software Component Program	11-11
Table 11.2.6	Estimated Costs for Basic Design Study for Each Project.....	11-11
Table 11.2.7	Estimated Annual Depreciation Costs.....	11-12
Table 11.2.8	Estimated Personnel Costs for Operation and Maintenance	11-12
Table 11.2.9	Estimated Annual Total Costs for Operation and Maintenance	11-12
Table 12.2.1	Economic Costs of the Improvement of the Priority Springs Conveyance Systems	12-3
Table 12.2.2	Economic Costs of Rehabilitation and Integrated Management of 11 Agricultural Wells	12-4
Table 12.2.3	Expected Water Volume Secured by the Project Implementation.....	12-5
Table 12.2.4	Domestic Water Demand and Economic Benefits	12-6
Table 12.2.5	Incremental Agricultural Water Supply and Economic Benefits by the Improvement of the Spring Conveyance Systems	12-7
Table 12.2.6	Incremental Agricultural Water Supply and Economic Benefits by the Rehabilitation and Integrated Management of Agricultural Wells.....	12-7
Table 12.2.7	Economic Evaluation Results of the Improvement of Spring Conveyance Systems	12-8
Table 12.2.8	Economic Evaluation Results of the Rehabilitation of Agricultural Well Projects.....	12-9
Table 12.2.9	Sensitivity Analysis.....	12-9
Table 12.3.1	Crop Budget (Vegetables)	12-11
Table 12.3.2	EIRR, NPV and B/C for the Improvement of 3 Spring Conveyance Systems	12-12
Table 12.3.3	EIRR, NPV, and B/C of the Rehabilitation of 11 Agricultural Wells.....	12-13

Table 13.2.1	Training Course in Jordan	13-3
Table 13.2.2	Summary of First Seminar	13-4
Table 13.2.3	Summary of Second Seminar	13-5

LIST OF FIGURES

	Page	
Figure 3.1.1	Topographic Map of the Study Area	3-1
Figure 3.1.2	Annual Average Rainfall from Jericho and Tubas Meteorological Stations	3-2
Figure 3.1.3	Long-term Annual Average Rainfall of the Jordan Valley	3-2
Figure 3.1.4	Monthly rainfall from Jericho and Nablus Meteorological Stations in 2004	3-2
Figure 3.1.5	Mean Temperature in WB	3-3
Figure 3.1.6	Mean Monthly Temperature	3-3
Figure 3.1.7	Mean Monthly Evaporation	3-3
Figure 3.1.8	Hydrogeological Map	3-7
Figure 3.2.1	Present Land Use in the Study Area	3-8
Figure 3.3.1	Changes of Unemployment Rate in Palestine during 1995 - 2006	3-11
Figure 3.3.2	Percentage Distribution of Employed Persons Aged +15 in WB by Economic Activity and Sex	3-12
Figure 3.3.3	Gross Domestic Product in Palestine, 1994-2005 (at Constant Price, Base Year 1997)	3-12
Figure 3.3.4	Contribution of Economic Activity to GDP in Palestine in 1997 and 2005	3-13
Figure 3.3.5	Changes of Employment Ratio in Israel and Settlement to Total Employment during 1995 - 2007	3-14
Figure 3.3.6	Credit Source by Monthly Expenditure	3-15
Figure 3.5.1	Major Wadi Basins in the Study Area	3-28
Figure 3.5.2	Location of Spring Group in the Study Area	3-34
Figure 3.5.3	Monthly Average Discharge of Jericho & Dyuk Spring Group	3-35
Figure 3.5.4	Monthly Average Discharge of Al 'Auja and Al Qilt Spring Group	3-35
Figure 3.5.5	Monthly Average Discharge of Al Far'a Spring Group	3-35
Figure 3.5.6	Monthly Average Discharge of Badhan and Shibli Spring Group	3-36
Figure 3.5.7	Historical Discharge of Ain Shibli Spring	3-36
Figure 4.1.1	Location of Functional Rainfall Station in Palestine	4-3
Figure 4.2.1	Isohyetal Map of the Study Area	4-7
Figure 4.2.2	Double Mass Curves between Annual Rainfalls	4-10
Figure 4.2.3	Concept of Extractable Discharge from Wadi Considering Hydrological Data	4-20
Figure 4.3.1	Geological Map of the Study Area	4-23
Figure 4.3.2	Hydrogeological Map and Cross Section of the Study Area	4-24
Figure 4.3.3	Watershed Division of Surface Water and Groundwater	4-26

Figure 4.3.4	Groundwater Level Cotour Map around Jericho City.....	4-30
Figure 4.3.5	Annual and Seasonal Change of Groundwater Level	4-32
Figure 4.3.6	Annual and Seasonal Changes of Groundwater Use (Eastern Basin)	4-33
Figure 4.3.7	Annual and Seasonal Change of Groundwater Use (Eastern Basin)	4-34
Figure 4.3.8	Annual and Seasonal Changes of Groundwater Use (North Eastern Basin)	4-34
Figure 4.3.9	Annual Changes of Groundwater Use (North Eastern Basin)	4-35
Figure 4.3.10	Annual and Seasonal Change of Groundwater Use (Mesh Data)	4-36
Figure 4.3.11(1)	Operation of the Agriculture Wells – Jericho Area	4-37
Figure 4.3.11(2)	Operation of the Agriculture Wells – Jiftlik Area.....	4-38
Figure 4.3.11(3)	Operation of the Agriculture Wells – Far’a Area	4-39
Figure 4.3.12	Location Map of Springs in the Study Area.....	4-40
Figure 4.3.13	Annual and Seasonal Change of Spring Discharge.....	4-43
Figure 4.3.14(1)	Secular Change of Chloride (Cl) Ion -Wells	4-46
Figure 4.3.14(2)	Secular Change of Nitrate (NO ₃) Ion -Wells.....	4-47
Figure 4.3.14(3)	Secular Change of Chloride (Cl) and Nitrate (NO ₃) Ion -Springs.....	4-48
Figure 4.3.15(1)	Tri-linear Diagram and Hexa Diagram -Wells	4-50
Figure 4.3.15(2)	Tri-linear Diagram and Hexa Diagram -Springs.....	4-51
Figure 4.3.16	Diagram for Classification of Irrigation Water	4-52
Figure 4.3.17	Suitability for Irrigation Water	4-53
Figure 4.3.18	Annual and Seasonal Change of Groundwater Use (Eastern Basin)	4-54
Figure 4.3.19	Annual Change of Groundwater Level (Eastern Basin).....	4-54
Figure 4.3.20	Annual Change of Chloride Ion (Eastern Basin - Wells)	4-54
Figure 4.3.21	Operation of the Agricultural Wells	4-55
Figure 4.3.22	Annual Change of Spring Discharge – Shbli Spring (Eocene Aquifer)	4-56
Figure 4.3.23	Annual Change of Groundwater Use (North Eastern Basin)	4-56
Figure 4.3.24	Annual Change of Groundwater Level (North Eastern Basin)	4-56
Figure 4.3.25	Annual Change of Chloride and Nitrate Ion (North Eastern Basin - Wells)	4-57
Figure 4.3.26	Analytical Area of Groundwater Simulation.....	4-58
Figure 4.4.1	Boundaries of Surface Water and Groundwater of 9 Wadi Basins.....	4-61
Figure 4.4.2	Relation between Ground Elevation and Annual Evaporation Depth.....	4-62
Figure 4.4.3	Relation between Annual Rainfall and Ground Elevation	4-63
Figure 5.1.1	Organizational Structure of the PWA.....	5-5
Figure 5.1.2	Organizational Structure of the MoA.....	5-6
Figure 5.2.1	Present Water Resources in each Sub-region.....	5-7
Figure 5.2.2	Present Water Balance in each Sub-region.....	5-9
Figure 6.1.1	Cultivated Area and Own Land.....	6-3
Figure 6.1.2	Land Owned by Family.....	6-3
Figure 6.1.3	Irrigation Practices	6-4
Figure 6.1.4	Cultivated Area by Crop.....	6-4

Figure 6.1.5	Average Monthly Income and Expenditure (2006).....	6-7
Figure 6.1.6	Degree of Income Dependence on Agriculture by Income Level.....	6-7
Figure 6.1.7	Distribution of Income and Expenditure of Household with Irrigated Area.....	6-8
Figure 6.1.8	Main Water Sources for Agriculture.....	6-9
Figure 6.1.9	Usage of Own Well for Agriculture by Income Level.....	6-10
Figure 6.1.10	Agriculture Water from Mekorot by Village.....	6-11
Figure 6.1.11	Quantity and Quality of Water Sources for Agriculture.....	6-11
Figure 6.1.12	Dissatisfaction on Quantity and Quality by Water Source.....	6-12
Figure 6.2.1	First Priority Agricultural Wells for Rehabilitation.....	6-21
Figure 6.2.2	Recommended Process to Prioritize Agricultural Wells for Rehabilitation.....	6-22
Figure 6.2.3	Tentative Implementation Schedule for Rehabilitation of Agricultural Wells..	6-25
Figure 6.3.1	Location Map of Priority Schemes (Spring).....	6-36
Figure 6.3.2	Proposed Implementation Schedule of Basic Plan for Improvement of Spring Water Conveyance System.....	6-40
Figure 6.4.1	Potential Storm Water Harvesting Plan on Wadi Qilt.....	6-49
Figure 6.4.2	Potential Storm Water Harvesting Plan on Wadi Auja.....	6-50
Figure 6.4.3	Potential Storm Water Harvesting Plan on Wadi Far'a.....	6-50
Figure 6.4.4	Proposed Site for Storage Facility at Downstream Area of Wadi Qilt.....	6-57
Figure 6.4.5	Layout Plan of Reservoir, Intake Facilities and Concrete Weir with Gate.....	6-58
Figure 6.4.6	Basic Concept of Concrete Weir with Gate.....	6-59
Figure 6.4.7	Proposed Site for Recharge Facility at Upstream Area of Wadi Qilt.....	6-63
Figure 6.4.8	Geology of Proposed Site for Underground Dam at Wadi Auja.....	6-66
Figure 6.4.9	Geological Sections of Proposed Site for Underground Dam at Wadi Auja.....	6-67
Figure 6.4.10	Proposed Site for Regulating Reservoir at Wadi Auja.....	6-69
Figure 6.4.11	Investigation Schedule for Construction of Storm Water Harvesting Facilities.....	6-72
Figure 6.4.12	Location of New Stream Gauges on Wadi Qilt and Wadi Auja.....	6-75
Figure 6.4.13	Location Map of Candidate Sites.....	6-83
Figure 6.4.14	Plan of Pilot Project at PP2.....	6-84
Figure 6.4.15	Standard Cross-section and Profile for Pilot Project at PP2.....	6-85
Figure 6.4.16	Implementation Schedule of Pilot Project.....	6-87
Figure 6.4.17	Expected Schedule for the Future Feasibility Study.....	6-89
Figure 6.5.1	Concept on Water Saving Irrigation.....	6-95
Figure 6.5.2	Determination of Irrigation Timing.....	6-98
Figure 6.5.3	Need of Training in Irrigation Field.....	6-98
Figure 6.5.4	Receiving Training on Irrigation Techniques.....	6-99
Figure 6.5.5	Training Subjects Needed by Farmers.....	6-99
Figure 6.5.6	Place of Training.....	6-100
Figure 6.5.7	Sufficiency of Training Duration.....	6-100
Figure 6.5.8	Suitability of Training Time.....	6-100
Figure 6.5.9	Timing of Training.....	6-101
Figure 6.5.10	Nature of Training.....	6-101
Figure 6.5.11	Qualification of Trainers.....	6-101
Figure 6.5.12	Qualification of Trainers.....	6-102
Figure 6.5.13	Use of Training Means.....	6-103

Figure 6.5.14	Responses from the Trainee	6-104
Figure 6.5.15	Gross Margin and Profit of Vegetables in the Study Area.....	6-108
Figure 6.5.16	Gross Margin and Profit of Fruits in the Study Area	6-108
Figure 6.5.17	Gross Margin and Profit per Water Unit Required by Vegetables in the Study Area (NIS/m ³)	6-110
Figure 6.5.18	Gross Margin and Profit per Water Unit Required by Fruits in the Study Area (NIS/m ³)	6-111
Figure 6.5.19	Gross Margin and Profit per Labor Unit Required by Vegetables in the Study Area (NIS/hour)	6-112
Figure 6.5.20	Gross Margin and Profit per Labor Unit Required by Fruits in the Study Area (NIS/hour)	6-112
Figure 6.5.21	Concept of Value-added Process	6-113
Figure 7.1.1	Function of Pilot Project to the Feasibility Study	7-1
Figure 7.2.1	Location Map of Pilot Project (Agricultural Wells).....	7-5
Figure 7.2.2	Work Item and Conceptual Image of Well Rehabilitation Pilot Project.....	7-6
Figure 7.3.1	Conceptual Image of Nwai'mah Pilot Project.....	7-9
Figure 7.4.1	Flow Chart of the Supporting System	7-14
Figure 7.5.1	Implementation Schedule of Pilot Project (Agricultural Wells).....	7-15
Figure 7.5.2	Implementation Schedule of the Pilot Project (Nwai'mah Spring).....	7-15
Figure 8.1.1	List and Location of Priority Schemes.....	8-1
Figure 8.1.2	Typical Layout of Pumping Equipment	8-8
Figure 8.2.1	Location of Priority Schemes for Spring Improvement	8-12
Figure 8.2.2	Existing Spring Conveyance System (Al Nwai'mah).....	8-14
Figure 8.2.3	Existing Spring Conveyance System (Al Dyuk).....	8-14
Figure 8.2.4	Existing Spring Conveyance System (Al 'Auja).....	8-15
Figure 8.2.5	Irrigation Water Balance of Al 'Auja Spring.....	8-17
Figure 8.2.6	Outline of Existing Spring Water Conveyance System.....	8-18
Figure 8.2.7	Monthly Spring Discharge and Design Flow of Al 'Auja Spring	8-20
Figure 8.2.8	Alternatives of Spring Water Conveyance/Distribution System	8-23
Figure 8.2.9	Image of Changing Spring Conveyance System.....	8-24
Figure 8.2.10	Proposed Distribution Box Alternatives.....	8-25
Figure 8.2.11	Proposed Canal Construction and Rehabilitation.....	8-25
Figure 8.2.12	Proposed Conveyance System (Al Nwai'mah).....	8-26
Figure 8.2.13	Proposed Conveyance System (Al Dyuk).....	8-26
Figure 8.2.14	Proposed Conveyance System (Al 'Auja).....	8-27
Figure 8.2.15	Roles and Responsibility for O&M.....	8-28
Figure 8.2.16	Image of Proposed Distribution Blocks	8-28
Figure 8.2.17	Water Flow Monitoring Point	8-29
Figure 9.2.1	Flowchart of Environmental Assessment Procedures	9-2

Figure 9.2.2	Typical Procedure of Land Expropriation.....	9-8
Figure 10.3.1	Problem Trees on GIS Activities.....	10-6
Figure 10.4.1	Schedule of Ground Truth for Base Map Updating	10-8
Figure 10.4.2	GIS Database Structure	10-8
Figure 10.5.1	Sample of Recommended Questionnaire Sheet for Monitoring of Agricultural Wells	10-14
Figure 11.1.1	Implementation Schedule for the Rehabilitation of Agricultural Well.....	11-3
Figure 11.2.1	Implementation Schedule of Priority Scheme.....	11-6
Figure 11.2.2	Typical Works Schedule for Software Component Program.....	11-8
Figure 11.2.3	Proposed Implementing Organization Structure	11-9

ABBREVIATIONS

ACDI/VOCA	Agricultural Cooperative Development International / Volunteers in Overseas Cooperative Assistance
ANERA	American Near East Refugee Aid
ASAP	The Project for Strengthening Support System Focusing on Sustainable Agriculture in the Jordan River Rift Valley
CAGR	Compound Annual Growth Rate
CEP	Center for Engineering and Planning
COGAT	Coordinate of Government Activities in the Territories
DCL	District Coordination Liaison
DF/R	Draft Final Report
EIA	Environmental Impact Assessment
EIS	Environmental Impact Systems
EQA	Environment Quality Authority
EIRR	Economic Internal Rate of Return
EP	Evaporation
ESC	Eastern Surface Catchment
EU	European Union
FAO	Food and Agriculture Organization
FFWSs	Flood Forecasting and Warning Systems
F/S	Feasibility Study
GDP	Gross Domestic Product
GIS	Geographic Information System
GTZ	German Agency for Technical Cooperation
HWE	House of Water and Environment
IC/R	Inception Report
ICRC	International Committee of the Red Cross
IDF	Israeli Defense Force
IEC	Information Education Communication
IEE	Initial Environmental Evaluation
IFAD	International Fund for Agricultural Development
IMR	Infant Mortality Rate
JCspd	Joint Council for services, planning and development
JDECO	Jerusalem District Electric Company
JICA	Japan International Cooperation Agency
JRRV	Jordan River Rift Valley
JVA	Jordan Valley Authority
JWC	Joint Water Committee

LGUs	Local Government Units
MAP	Mapping Agency Palestine
MD	Palestine Meteorological Department
MEnA	Ministry of Environmental Affairs
Mekorot	Israel Water Company
MoA	Ministry of Agriculture
MoEHE	Ministry of Education and Higher Education
MoH	Ministry of Health
MoI	Ministry of Interior
MoLG	Ministry of Local Government
MoP	Ministry of Planning
MoPIC	Ministry of Planning and International Cooperation
MoT	Ministry of Transportation
MTDP	Medium Term Development Plan
NARC	National Agriculture Research Center
NEAP	National Environmental Action Plan
NER	Net Enrolment Rate
NGO	Non-Governmental Organization
NPV	Net Present Value
O&M	Operation and Maintenance
ODA	Official Development Assistance
PARC	Palestinian Agricultural Relief Committees
PCBS	Palestinian Central Bureau of Statistics
PES	Preparation of an Environmental Strategy
PHG	Palestinian Hydrology Group
PIEFZA	Palestinian Industrial Estates & Free Zones Authority
PMD	Palestinian Meteorological Department
PNA	Palestinian National Authority
PWA	Palestinian Water Authority
S/W	Scope of Work
SAR	Sodium Absorption Ratio
SCF	Standard Conversion Factor
SCUs	School, College and Universities
SODEPAZ	SOLIDARIDAD, DESARROLLO Y PAZ
SS	Suspended Solids
TCTP	Third Country Training Program
TOR	Terms of Reference
UAE	United Arab Emirates

UN	United Nations
UNDP	United Nations Development Programme
UNIDO	United Nations Industrial Development Organization
Unesco-IHE	United Nations Educational, Scientific and Cultural Organization - Institute for Water Education
UNRWA	United Nations Relief and Works Agency for Palestine Refugees in the Near East
USAID	United States Agency for International Development
VAT	Value Added Tax
WB	West Bank
WBGS	West Bank and Gaza Strip
WBWD	West Bank Water Department
WHO	World Health Organization
WRDM	Water Resources Development and Management
WUA	Water Users' Association

MEASUREMENT UNITS

Extent

cm² = Square-centimeters (1.0 cm x 1.0 cm)

m² = Square-meters (1.0 m x 1.0 m)

km² = Square-kilometers (1.0 km x 1.0 km)

dunum = Dunum (0.1 ha)

ha = Hectares (10,000 m²)

ac = Acres (4,046.8 m² or 0.40468 ha.)

Volume

cm³ = Cubic-centimeters

(1.0 cm x 1.0 cm x 1.0 cm
or 1.0 m-lit.)

m³ CM = Cubic-meters

(1.0 m x 1.0 m x 1.0 m
or 1.0 k-lit.)

lit l = Liter (1,000 cm³)

Length

mm = Millimeters

cm = Centimeters (cm = 10 mm)

m = Meters (m = 100 cm)

km = Kilometers (km = 1,000 m)

Weight

gr = Grams

µg = Micrograms (0.000001 gr.)

mg = Miligrams (0.001 gr.)

kg = Kilograms (1,000 gr.)

ton = Metric ton (1,000 kg)

Time

sec. = Second

min. = Minutes (60 sec.)

hr. = Hours (60 min.)

yr. = Year

Others

°C = degree Celsius

R = Right angle

kPa = Kilopascal (1,000 Pa)

Currency

USD = United States Dollar

NIS = New Israeli Shekel

JPY = Japanese Yen

JD = Jordanian Dinar

Exchange Rate

USD1.00 = NIS3.5= JPY107

as of August 2008

(unless otherwise specified)

CHAPTER 1 INTRODUCTION

1.1 Authority

This Final Report has been prepared in accordance with the Scope of Work (S/W) for the Feasibility Study on Water Resources Development and Management in the Jordan River Rift Valley, agreed upon between the concerned authorities of Palestinian National Authority (PNA) and the Japan International Cooperation Agency (JICA) on February 27, 2007. The report presents all the results of the Study throughout the defined period.

1.2 Background


The Study Area is located in the eastern part of the West Bank of the Jordan River Rift Valley, and has a population of about 100,000 at present. The climate in the Study Area is categorized as arid to semi-arid zone, with annual average rainfall ranging from less than 100 mm to 400 mm. Required water in the area is presently sourced from spring water and groundwater.

Although water is mainly utilized for irrigation and livestock in the Study Area, water resources are currently being utilized inefficiently. The problem is due mainly to: i) improper water distribution based on time; ii) water conveyance losses from insufficient irrigation facilities; iii) damaged agricultural wells; and iv) lack of development of surface water. Since water demand is expected to increase in the future, efficient utilization of the existing water resources, as well as development of new water resources is essential in the Study Area.

A study on Jericho Regional Development was conducted by JICA during the period of October 2005 to September 2006, to formulate a Regional Development Plan for the Jericho and the Jordan River Rift Valley area, and to enhance the capacity for formulation and implementation of a regional development program. The program is comprised of a Social and Community Development Program, Agriculture and Agribusiness Development Program and Tourism and Urban Environment Program. Agriculture and Agribusiness Program (Agricultural Sector) is further divided into Water Resources Management, Industry & Trade Promotion and Agriculture Development.

In July 2006, the Government of Japan held discussions with Palestine, Israel and Jordan and recommended the concept of "Corridor for Peace and Prosperity," aiming the realization of a permanent peace process in the region. For this concept, a Four-Party Consultative Unit was established, with Japan expressing its intentions to grant an Official Development Assistance (ODA) in order to accelerate the confidence building among the concerned countries, through the regional development.

Regional and Sector Development



Under these circumstances, the Project Formation Mission for Agriculture and Agribusiness Development Program was dispatched by JICA in November 2006. An exchange of ideas was then held with the PNA and their neighboring countries. In response to the official request of PNA, the S/W for the Feasibility Study on Water Resources Development and Management in the Jordan River Rift Valley was also discussed and agreed upon by both parties in February 2007. The S/W is presented in Attachment-1.

1.3 Objectives of the Study

The objectives of the Study are as follows:

- (i) To formulate a basic plan for efficient utilization of water for agriculture in the Jordan River Rift Valley;
- (ii) To formulate a basic plan for water resources development in the Jordan River Rift Valley; and
- (iii) To carry out technology transfer to Palestinian counterpart personnel through on-the-job training during the course of the Study.

1.4 Study Area

As presented in the location map, the Study Area is located in the West Bank of the Jordan River Rift Valley, which includes the watershed areas of Wadi Qilt, Wadi Auja and Wadi Far'a.

1.5 Work Schedule

The Study was carried out over a period of 22 months, from March 2007 to December 2008, consisting of the following two phases:

Phase 1: March 2007 ~ December 2007 (Formulate basic plans on efficient utilization of water for agriculture and water resources development)

Phase 2: January 2008 ~ December 2008 (Conduct feasibility studies on selected water

resources management schemes for water resources development and for efficient utilization of water agriculture including implementation of small scale pilot projects)

Activity	Phase-1						Phase-2															
	1st Year						2nd Year						3rd Year									
	FY2007						FY2008															
	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22
Work in Palestine													■									
Work in Japan	□						□						□									
Report	▲ IC/R		▲ PR1				▲ It/R						▲ DF/R		▲ F/R							

1.6 Counterpart and Steering Committee

The counterpart personnel assigned for the Study are as follows:

Counterpart Personnel Assigned

JICA Study Team		Palestinian Counterpart	
Name	Position	Name	Organization
Kunio GOTO	Team Leader/ Water Resource Management	Issam Nofal ^{1/}	MoA
		Deeb Abdel Ghafoor ^{1/}	PWA
Toshio KATAYAMA	Hydrological Analysis/ Water Harvesting	Mohannad Hej Hussein	MoA
		Almotaz A. Abadi	PWA
Toshiyuki WADA	Groundwater Analysis / Hydrogeology & Water Quality	Imad Ghanma	MoA
		Deeb Abdel Ghafoor	PWA
		Majida Almaneh	PWA
Masahiko TANIGUCHI	Satellite Image/GIS Database	Yagoub Zaid	MoA
		Waleed Abu Muhsin	PWA
		Khaled Salem	EQA
Jun HORIMOTO	Plan & Design for Spring Water Conveyance System	Mohannad Hej Hussein	MoA
Abbas Zuhair KALBOUNEH	Plan & Design for Agricultural Well	Omar Zayed	PWA
		Farah Sawuftah	MoA
Yuji MURASE	Plan & Design for Storm Water Harvesting	Khairi	PWA
		Issam Nofal	MoA
Akio YAMASHITA	Water Management	Omar Zayed	PWA
		Ibtisam Abu Haija	MoA
Yasunobu KUDO	Organization of Water Management/Social Environment	Hanai Qasem	PWA
		Issam Nofal	MoA
		Ayman Jarrar	PWA
		Abdel Aziz Rayyan	EQA

JICA Study Team		Palestinian Counterpart	
Name	Position	Name	Organization
Abbas Zuhair KALBOUNEH	Supervision of Pilot Project	Mohannad Hej Hussein	MoA
		Khairi	PWA
		Omar Zayed	PWA
Honorato G. PALIS	Environmental Impact Assessment	Thaer Al-Rabi	MoA
		Sbui Samhan	PWA
		Mahmoud Abushanab	EQA
Koji OTSUKA	Financial Analysis/Project Evaluation	Raed Al-Aghber	MoA
		Kamal Issa	PWA
		Ibrahim Abdelrahim	MoP

^{1/} : *Chief Counterpart Personnel*

MoA: Ministry of Agriculture

PWA: Palestinian Water Authority

EQA: Environment Quality Authority

MoP: Ministry of Planning

For the smooth execution of the Study, a Steering Committee composed of the following major members was organized:

- (i) Palestinian Water Authority (PWA);
- (ii) Ministry of Agriculture (MoA);
- (iii) Ministry of Planning (MoP);
- (iv) Environment Quality Authority (EQA);
- (v) Resident Representative of JICA Palestine Office;
- (vi) Leader of the Study Team; and
- (vii) Others appointed by the Chairperson.

CHAPTER 2 OUTLINE AND ACTIVITIES OF THE STUDY

2.1 General

As explained in Section 1.5, the Study has been conducted from March 2007 to December 2008 in a series of works divided into two phases.

Phase-1 consists of: (i) Home Office Preparatory Work; (ii) First Field Work; and (iii) Second Field Work (1), while Phase-2 comprises: (iv) First Home Office Work; (v) Second Field Work (2); (vi) Second Home Office Work; (vii) Third Field Work; and (viii) Third Home Office Work.

The proceeding sections explain the outline of activities throughout the study period.

2.2 Outline of the Study

2.2.1 Home Office Preparatory Work (March 2007)

(1) Collection and Analysis of Relevant Data and Information

The existing relevant data, which includes agricultural development, agricultural product processing and marketing programs proposed in the Jericho Regional Development Study Project in Palestine, were reviewed and analyzed in order to identify major items and constraints for smooth execution of the First Field Work as an initial stage.

(2) Examination of Study Methodology and Preparation of Implementation Programs

The study plan and methodology, capacity development plan for the counterpart personnel etc., were examined. Subsequently, the implementation program for the Study was prepared.

(3) Preparation of the Inception Report

On the basis of the preliminary examination mentioned above, the Inception Report was prepared, containing: (i) Background of the Study; (ii) Objectives of the Study; (iii) Basic Approach to the Study; (iv) Contents and Methodology of the Study; (v) Work plan (flowchart of the work schedule, itineraries, sub-contracted works); (vi) Organization of the Study Team (assignment schedule and work period); (vii) Organization of Implementation of the Study (organization of counterpart and backup support of the home office; (viii) Reports to be submitted; (ix) Required Data for the Study; (x) Undertakings of PNA; and (xi) Policy and Plan for Capacity Development of the Palestinian Officials.

2.2.2 First Field Work (March 2007 to August 2007)

(1) First Steering Committee Meeting

The First Steering Committee Meeting was held in April 3, 2007 to discuss the Inception Report. The staff of JICA Headquarters also joined the meeting. After the explanation of report contents by the Study Team, related discussions were held among attendees, in order to obtain the committee's joint acceptance of the report. The minutes of said meeting are included in this report as Attachment-2.

(2) Collection and Analysis of Relevant Data and Information

Existing relevant data, which includes agricultural development, agricultural product processing and marketing programs proposed in the Jericho Regional Development Study Project in Palestine, were collected, reviewed and analyzed in order to define the present situation and clarify the issues related to water utilization.

(3) Survey for Rural Society, Irrigated Agriculture and Water Resources

The following items were surveyed to determine the potentials and constraints of the water resources development in the Jordan River Rift Valley:

- (i) Rural Society: (a) Natural condition, (b) Socio-economy, (c) Administrative institutions, and (d) Gender in rural society;
- (ii) Irrigated Agriculture: (a) Farming, (b) Farmers' organization, and (c) Irrigation methods and water management; and
- (iii) Water Resources Development: (a) Water utilization, (b) Water volume and quality, (c) Irrigation facilities, and (d) Laws, regulations and customs for water utilization.

(4) Preparation of Inventory for Water Resources

Based on the results of data and information collected in 2.2.2-(2) above and the results of survey conducted in 2.2.2-(3) above, an inventory was prepared concerning the water resources in the Study Area.

(5) Improvement and Updating of Existing GIS Database

Improvement and updating of the existing GIS database were conducted based on the results of the survey and inventory discussed above. Capacity development of counterpart personnel and enhancement of organizations for the proper utilization of the GIS database were carried out, in order to produce unified information and to train the Palestinian personnel in periodically updating the data after the study period.

(6) Discussions with Other Donor Agencies

The Study Team discussed the contents of the Study with the other donors in-charge of the water resources development, as well as with the concerned agencies of neighboring countries. Information related to similar projects was also collected from these agencies.

(7) Preparation of Technology Transfer Program

The Technology Transfer Program in the study period was prepared for the respective counterpart personnel based on the responsibilities of each technical field. The program carried out throughout the study includes on-the-job trainings, meetings and seminars.

(8) Preparation of Basic Plan for Improvement of Spring Water Conveyance Systems

Basic plan for improvement of spring water conveyance systems was prepared through the detailed investigation and analysis of data.

1) Detailed Investigations

Spring water was investigated by means of field observations and interview surveys, which cover the following subjects:

- (i) Laws and regulations concerning utilization of spring water; and
- (ii) Condition of spring water conveyance systems (Discharge, facilities, water leakage, water quality etc.).

2) Analysis and Evaluation of Present Condition and Potential for Improvement

The existing springs were classified based on the investigation results and possibility of improvement was examined, e.g. improvement of conveyance facilities. Prioritization for the spring water conveyance systems was performed based on the examination results, with due consideration of the technical, economic, social and legal aspects.

3) Preparation of Basic Plan for Improvement of Spring Water Conveyance System

Basic plan for improvement of spring water conveyance systems was prepared based on the analysis and evaluation of their present conditions.

4) Selection of Priority Schemes for the Feasibility Study

The priority schemes for improvement of spring water conveyance system were selected from the above Basic Plan, considering viability, as well as the economic, social and legal aspects.

(9) Preparation of Basic Plan for Rehabilitation and Integrated Management of Agricultural Wells

Basic plan for rehabilitation and integrated management of agricultural wells was also prepared through the detailed investigation and analysis of data.

1) Detailed Investigation

Agricultural wells were investigated through field observations and surveys interviews, which cover the following topics:

- (i) Laws and regulations related to the utilization of agricultural wells;
- (ii) Condition of wells (depth, water level, water volume, water quality, hydro-geology, and ownership); and
- (iii) Operation and maintenance (O&M) of wells.

2) Analysis and Evaluation of Present Condition and Potential for Rehabilitation

The existing wells were classified based on their operations, management system, etc, and the possibility of their rehabilitation was examined considering technical and economic aspects.

3) Examination of Social Assessment

A social assessment was carried out to determine if a certain well could be utilized as community well.

4) Preparation of Basic Plan for Rehabilitation and Integrated Management of Agricultural Wells

Basic Plan for rehabilitation of agricultural wells was prepared based on the analysis and evaluation of their present conditions. Moreover, a plan for the institutional arrangements of water users associations for the integrated management of the wells was evaluated.

5) Selection of Priority Schemes for the Feasibility Study

The priority schemes for rehabilitation and integrated management of agricultural wells were selected from the above Basic Plan, considering the viability of the Plan as well as the economic, social and legal aspects.

(10) Execution of Initial Environmental Evaluations (IEE)

IEE of the scheme plans, such as the improvement of spring water conveyance systems and the rehabilitation and integrated management of agricultural wells were carried out. The results were also used as basis for the selection of the priority schemes for the Feasibility Study.

(11) Selection of Pilot Project

Pilot projects were selected in order to verify the suitability and effectiveness of the plans for the improvement of spring water conveyance systems and the rehabilitation and integrated management of agricultural wells as mentioned in the above (8) and (9).

(12) Preparation of Pamphlet

A pamphlet presenting the objectives and contents of the study was prepared in order to introduce the Study to the concerned Palestinian agencies, other donors agencies etc.

(13) Preparation of Progress Report (1)

Progress Report (1) was prepared based on the study results of the First Field Work, which includes following contents:

- (i) Present conditions and issues of the Study Area;
- (ii) Results of rural society, irrigated agriculture and water resources studies;
- (iii) Basic Plan for improvement of spring water conveyance systems;
- (iv) Basic Plan for rehabilitation and integrated management of agricultural wells;
- (v) Basic approach to preparation of storm water harvesting for Wadi watersheds;
- (vi) Selection of pilot projects;
- (vii) Progress of technology transfer program; and
- (viii) Results of IEE.

(14) Second Steering Committee Meeting

A Second Steering Committee Meeting was held in July 23, 2007 to discuss the Basic Plan, Selection of Pilot Project and Schedule of Second Field Work. The resident representative of JICA Palestine joined the meeting. After the Study Team explained the above enumerated contents, related discussions among attendees took place in order to obtain committee's joint acceptance of the proposed Basic Plan, the selected pilot projects

and the schedule of Second Field Work. The minutes of this meeting is included in this report as Attachment-3

2.2.3 Second Field Work (1) (October 2007 to March 2008)

(1) Detailed Survey for Agricultural Water Use

Conditions and information regarding spring water conveyance systems and agricultural wells during the winter season were collected and investigated. Results obtained were reflected on the Basic Plan prepared in (8) and (9) of Section 2.2.2.

(2) Preparation of Basic Plan for Storm Water Harvesting for Wadi Watersheds

1) Examination of Storm Water Harvesting

Hydrological analysis for watersheds was made focusing on surface water. Moreover, groundwater was analyzed by reviewing the water levels in the existing wells. The influences on the surrounding water resources by the development of storm water harvesting were assessed through the analysis.

2) Evaluation of Present Condition and Potential

Possibilities of storm water harvesting in the respective watersheds were examined through the evaluation of the present condition and its potential.

3) Preparation of Basic Plan for Storm Water Harvesting

Basic Plan for storm water harvesting for Wadi Qilt, Wadi Auja and Wadi Far'a watersheds was studied through the above examination.

(3) Supplemental Investigation for Selected Pilot Projects

Supplemental investigations in the selected pilot projects were executed to confirm the condition of the irrigation facilities and farming practices.

(4) Preparation of Implementation Schedule for the Pilot Projects

Implementation plans for the pilot projects were prepared, taking into consideration the farmers' participation in water management, including the following contents:

- (i) Work schedule;
- (ii) Target, outcome, activities, avoidance of expected risk etc.;
- (iii) Monitoring index;
- (iv) Methods and executing organization for monitoring and evaluation; and
- (v) Methods of extension of project outcomes.

(5) Implementation of Pilot Project

Upon approval of the Joint Water Committee (JWC) for the implementation of the pilot projects, rehabilitation of eight agricultural wells and improvement of a spring water conveyance system were commenced from December 2007 and February 2008, respectively, under the supervision of the Study Team.

(6) Feasibility Study for Priority Schemes

The feasibility study for the priority schemes, which have been selected during the First Field Work stage, was conducted based on detailed investigation.

(7) Preparation of Interim Report

An Interim Report was prepared mainly covering the activities and progress up to the interim stage of the study, with the following contents:

- (i) Progress and issues of Pilot Projects;
- (ii) Plan for the improvement of spring water conveyance systems (1st revision);
- (iii) Plan for the rehabilitation and integrated management of agricultural wells (1st revision);
- (iv) Basic Plan for storm water harvesting; and
- (v) Progress of the technology transfer program.

(8) Third Steering Committee Meeting

The Third Steering Committee Meeting was held in February 13, 2008 to discuss the contents of the Interim Report. The Basic Plan for water resources development and management, the activities and progress of the pilot projects, plan of the selected priority schemes as well as the schedule of the subsequent field work were accepted by the committee. The minutes of said meeting is presented in Attachment-4.

2.2.4 First Home Office Work (March 2008 to April 2008)

The Study Team explained the contents of the Interim Report to JICA Headquarters and the Advisory Committee in Japan. Their comments were reflected in the report.

2.2.5 Second Field Work (2) (May 2008 to August 2008)

The pilot projects were executed to confirm the validity and effectiveness of the improvement of spring water conveyance systems and the rehabilitation and integrated management of agricultural wells. The projects include not only the rehabilitation and improvement of facilities, but also the improvement of water management on farm level, and the establishment of an integrated management system for the wells.

Based on the lessons learned from the pilot projects, the Basic Plan for the improvement of spring water conveyance systems and the rehabilitation and integrated management of agricultural wells, formulated in the First Field Work, were revised. Then, the feasibility study for the improvement of spring water conveyance systems and the rehabilitation and integrated management of agricultural wells as well as preparation of preliminary plan for the storm water harvesting were carried out in the Second Field Work (2).

(1) Implementation and Monitoring of Pilot Project

Following the Second Field Work (1), implementation of the pilot projects were continued on a sub-contract basis, in accordance with the schedule approved by the agencies concerned. Monitoring of the pilot projects was conducted parallel with the implementation works.

Among the selected eight wells for the pilot projects, one well was abandoned due to high electric conductivity of its contained water, observed during 1st stage of the works.

(2) Execution of First Seminar

First Seminar was held in May 28 2008 at Ramallah to introduce the outcomes of the study and to promote its understanding. Palestinian agencies concerned, NGOs, donor agencies and other JICA study teams joined the seminar.

(3) Evaluation of Pilot Projects

Based on the monitoring index mentioned in (4) of Section 2.2.3, evaluation of the pilot projects was made and the corresponding lessons learned were reflected in the Basic Plan for the improvement of spring water conveyance systems and the Basic Plan for the rehabilitation and integrated management of agricultural wells.

(4) Feasibility Study for Selected Schemes

The feasibility study for the priority schemes, which have been selected during the First Field Work, was continued including collection of data and information required for the study as well as field investigations.

(5) Preparation of Development Plans (Draft) for Selected Schemes

1) Preparation of Development Plan (Draft)

Development plans (draft) for the selected schemes were prepared, which comprise the improvement of spring water conveyance systems, the rehabilitation and integrated management of agricultural wells and the storm water harvesting. The plans include not only the rehabilitation and improvement of facilities, but also the improvement of water management on farm level and the establishment of an integrated management system for the wells. Moreover, the urgency, development level, and possible financing sources for implementation, including Palestinian own budget and financing by other donors agencies were examined.

2) Economic and Financial Analysis

Economic and financial analysis was conducted based on valid input for cost estimates and benefits.

It is noted that available hydrological data are insufficient for the preparation of the feasibility study on storm harvesting plan. Continuous long-term data is required to prepare an accurate plan. Accordingly, the storm water harvesting plan in this report shall be reviewed and re-examined after accumulation of hydrological data.

(6) Preparation of Plan for Installation of Hydrological Station

It was observed that some of the existing hydrological stations in the study area are not functioning. In connection with (5) above, the plan for the rehabilitation and installation of hydrological observation system was formulated in order to observe continuous hydrological data in the study area.

(7) Preparation of Pilot Project Plan for Storm Water Harvesting

Plan of small scale pilot project was prepared to confirm the validity and effectiveness of

storm water harvesting, which could be implemented in parallel with the observation of long term hydrological data as mentioned in (6) above.

(8) Environmental Evaluation

Environmental impact in the proposed development plan (draft) mentioned in (5) as well as alternative plans to minimize the impact was examined.

(9) Preparation of Implementation Programs for the Selected Schemes

Implementation programs for the selected schemes were prepared, which included the executing body, implementation schedule and financial sources. The program is laid out on a yearly basis.

(10) Recommendations for Efficient Utilization of Water

Recommendations cover efficient utilization of water resources, including waste water and brackish water treatment means, draft rules for water distribution, draft organization of a water management system and methods for maintenance of facilities. Executing bodies, targets, indexes for attainment, implementation schedule, priority of the plan and management were also examined.

(11) Preparation of Draft Final Report

A Draft Final Report was prepared describing the study results throughout the study period including the feasibility study for the selected schemes. Contents of the report are as follows.

- 1) Basic Plan and Its Processes and Analysis:
 - (i) Plan for improvement of spring water conveyance system;
 - (ii) Plan for rehabilitation and integrated management of agricultural wells; and
 - (iii) Plan for storm water harvesting.
- 2) Contents of Pilot Projects and their Evaluation Results
- 3) Results of Feasibility Study:
 - (i) Background for selection of priority schemes;
 - (ii) Development plan for selected schemes;
 - (iii) Operational plan;
 - (iv) Maintenance plan;
 - (v) Implementation program;
 - (vi) Evaluation and conclusions; and
 - (vii) Recommendations.
- 4) Recommendations for Efficient Utilization of Water

(12) Fourth Steering Committee Meeting

The Fourth Steering Committee Meeting was held in August 19, 2008 to discuss about the final outcomes of the Study. The Basic Plan for water resources development and

management, results of the pilot projects, plan of the selected priority schemes including their implementation plan and recommendations to efficient utilization of water were accepted by the Committee. The minutes of said meeting is presented in Attachment-5.

2.2.6 Second Home Office Work (September 2008)

(1) Discussion of Draft Final Report

The Study Team explained the contents of the Draft Final Report to JICA Head Quarter and the Advisory Committee in Japan. Their comments were consequently reflected in the report.

(2) Preparation of Final Report

The Draft Final Report was modified and finalized according to the comments received from PNA, as well as the comments from JICA and the Advisory Committee in Japan.

2.2.7 Third Field Work (November 2008)

(1) Explanation of Final Report to PNA

The Final Report was explained to the Palestinian agencies concerned to obtain consensus for the contents of the report.

(2) Execution of Second Seminar

Second Seminar was held in November 19, 2008 to explain and to obtain the understanding on the outcomes of the Study. Palestinian agencies concerned, NGOs, donor agencies and other JICA study teams joined this seminar.

2.2.8 Third Home Office Work (December 2008)

(1) Submission of Final Report

The Final Report was submitted after obtaining final approval by JICA.