

Supporting Report H

Economic Evaluation

Supporting Report H Economic Evaluation

H.1 Methodology

The objective of economic evaluation is to evaluate the project efficiency from the viewpoint of economics of the Study Area. An economic analysis is carried out using the economic costs and economic benefits from the projects of Master Plan, which is not directly related to the cash flow of the projects. For example, subsidies or taxes, which are internal transfers of cash within the country, are not included in economic analysis.

The economic cost is obtained by deducting the transfer payment from the financial cost. The economic benefit is defined as the impact of flood control measures, which is composed of the flood damage reduction impact and the effect of multipurpose dam.

The economic effects and feasibility of the project are examined by making a comparison between both present values of the economic cost and benefit, by means of the Cost Benefit Ratio (B/C), the Net Present Value (NPV) and the Economic Internal Rate of Return (EIRR).

H.2 Economic Cost

For the economic evaluation, the project cost estimated in financial cost is converted to the economic cost. In order to derive the economic cost from the financial cost, transfer payments such as taxes and price escalation are deducted. In addition to subtracting the transfer payments, a standard conversion factor of 0.9 is applied for converting to the shadow price for all the costs except imported goods.

H.3 Economic Benefit

Benefit of the project is generally defined as an economic difference between “with-project” and “without-project” situation. As for the Study, “With-project” means the condition that the structural measures and non-structural measures for flood damage reduction proposed in this Study are developed completely or gradually, and “Without-project” means the condition without any such measures.

Generally, there are two kinds of benefit, namely tangible benefit and intangible benefit. Further, tangible benefit would be classified into direct benefit and indirect benefit.

The direct/tangible benefits derived from the implementation of countermeasures will be estimated as a reduction in damage to assets such as building, household effects, livestock, crops, infrastructure and other facilities. Indirect/tangible benefit also would be estimated as a reduction in damage, which would be caused by the direct damage of disaster.

H.3.1 Types of Project Benefits

Two types of project benefits are estimated for economic evaluation of the Proposed Plan: 1) flood damage reduction benefit and 2) the benefit of multiple uses of dam.

- 1) Flood damage reduction benefit is characterized as flood damage reduced by implementation of the flood control plan, which includes damage to property, damage to infrastructure and disturbance to economic activities.

- 2) The benefit of multiple uses of dam is characterized as the effect of dam utilization with other objectives except flood control such as power generation and water supply.

H.3.2 Flood Damage Reduction Benefit

The flood damage reduction benefit expected from the flood control project is estimated by the following procedure.

- 1) Selection of evaluation items
- 2) Estimation of unit value of assets
- 3) Estimation of damage by inundation depth
- 4) Estimation of probable flood damage
- 5) Conversion to annual average flood damage

(1) Selection of Evaluation Items

The following items are selected for estimation of the expected flood damage considering the data availability of the Study Area.

(Direct damage)

- House damage
- Household property damage
- Agricultural damage (paddy)
- Public infrastructure damage

(Indirect damage)

- Interruption to business operations

(2) Estimation of Unit Value of Assets

The value of the assets for the study area is determined by review of past study data and additional data collection from publications and related agencies. The details of each item are described below.

1) House and Household Property

According to the Census of Population and Housing 2001, houses in Sri Lanka have been divided into the following three housing types, which are classified based on materials of construction used for wall, floor and roof:

- Improvised: The walls and roof were made of cadjan, palmyrah or other inferior or non-durable material
- Semi-Permanent: A mixture of durable and non-durable materials
- Permanent: Materials used are of the durable type like bricks, cement, tile, asbestos sheets, etc.

The following table shows the basic conditions applied to estimate the value of a house.

Table H.3.1 Estimation of Value of House in June, 2007

Housing Type	Floor Area (m ²) *1	Average Unit Value (Rs/m ²) *2	Average Value of Houses	Depreciation Ratio *1	Residual Value (Rs./unit)
Improvised	36	3,474	125,075	0.5	62,538
Semi-Permanent	92	20,528	1,888,554	0.5	944,277
Permanent	185	20,528	3,797,636	0.5	1,898,818

Note: *1: "The Study on Storm Water Drainage Plan for the Colombo Metropolitan Region", 2003 March, JICA

*2: "The Study on Storm Water Drainage Plan for the Colombo Metropolitan Region", 2003 March, JICA,
and "Bulletin of Construction Statistics", 2007 June, ICTAD

The household property value is also estimated for three groups. The household property value is estimated by a ratio to the average value of the house.

Table H.3.2 Estimation of Value of Household Property in June, 2007

Housing Type	Average Value of House (Rs.)	Ratio of Household Property Value (%) *1	Estimated Household Property (Rs.)
Improvised	62,538	30	18,761
Semi-Permanent	944,277	30	283,283
Permanent	1,898,818	30	569,645

Note: *1: "The Study on Storm Water Drainage Plan for the Colombo Metropolitan Region", 2003 March, JICA

The proportion of housing type is various in districts as shown in the table below. In the analysis, number of damaged house is calculated using this proportion.

Table H.3.3 Number and Percentage of Housing Units by District and Type of Housing Unit

District	Total Housing Units	Permanent		Semi Permanent		Improvised	
		No.	No.	%	No.	%	No.
Colombo	473,045	408,473	86.3%	54,234	11.5%	1,293	0.3%
Gampaha	475,847	380,985	80.1%	83,351	17.5%	5,251	1.1%
Kalutara	245,784	193,973	78.9%	48,347	19.7%	1,094	0.4%
Nuwara Eliya	164,886	106,766	64.8%	54,618	33.1%	300	0.2%
Galle	229,521	166,119	72.4%	60,304	26.3%	1,722	0.8%
Matara	174,712	126,683	72.5%	46,118	26.4%	1,096	0.6%
Hambantota	126,362	75,720	59.9%	49,367	39.1%	590	0.5%
Ratnapura	242,882	148,266	61.0%	92,413	38.0%	406	0.2%
Kegalle	193,578	133,244	68.8%	57,960	29.9%	980	0.5%
Total	2,326,617	1,740,229	74.8%	546,712	23.5%	12,732	0.5%

Source: Census of Population and Housing 2001

2) Paddy

The value of paddy is estimated separately based on the productivity (average yield) and producer price of paddy. The average yield by districts as shown in the table below and Rs.13.34/kg of the all island producer prices of 2005 from Statistical Abstract 2006 by Department of Census and Statistics are applied for estimation of the value of paddy.

Table H.3.4 Average Yield of Paddy by District

District	Average Yield 2006 Total (kg/Hectare)
Colombo	3,206
Gampaha	3,507
Kalutara	2,791
Nuwara Eliya	3,710
Galle	3,299
Matara	3,817
Hambantota	4,798
Ratnapura	3,167
Kegalle	3,686
Sri Lanka	4,137

Source: <http://www.statistics.gov.lk/agriculture/index.htm>
*Web Site of Agriculture and Environment Statistics
Division, Department of Census and Statistics*

(3) Estimation of damage by inundation depth

1) House

The rate of damage caused by inundation to the assets is mainly related to water depth. In this analysis, the relationship between inundation depth and damage rate prepared by the Ministry of Land, Infrastructure and Transport, Japan is utilized for estimation of the house damage by inundation depth.

The above damage rate is defined by the slope of inundation area such as less than 1/1000, 1/1000-1/500 and more than 1/500. Average gradient of the riverbed of each target river is less than 1/1000. Accordingly, damage rate of less than 1/1000 as shown in the table below is applied for flood damage estimation in this Study.

Table H.3.5 Rate of Flood Damage to House

	Water Depth				
	< 50 m	50 – 99cm	100 – 199cm	200 – 299cm	300cm =<
Damage Rate	0.092	0.119	0.266	0.580	0.834

Source: "Manual for Economic Study on Flood Control", Ministry of Land, Infrastructure and Transport, Japan

2) Household Property

The damage rate for household property is shown in the table below, which is also from the manual prepared by the Ministry of Land, Infrastructure and Transport, Japan.

Table H.3.6 Rate of Flood Damage to Assets and Effects

	Water Depth				
	< 50 m	50 – 99cm	100 – 199cm	200 – 299cm	300cm =<
Damage Rate	0.145	0.326	0.508	0.928	0.991

Source: "Manual for Economic Study on Flood Control", Ministry of Land, Infrastructure and Transport, Japan

(4) Estimation of Probable Flood Damage

1) House, Household Property and Paddy Damage

The probable flood damage of house, household property and paddy, is estimated under the various magnitudes of flood events. For the estimation, number of affected damaged house by water depth and inundated area of paddy are analyzed using GIS database and the result of hydraulic analysis.

Detailed analysis using GIS has been done for two flood events with probabilities of 2 and 50 years in each basin.

Conditions of analysis and data used for analysis are as follow;

- Population: 2001 data (GIS data) from UGA
- House and household number: Calculated by dividing the population by 4.2, which is the average size (persons) of household from Census of Population and Housing 2001. According to the Census, number of household and number of house were almost same.
- Proportion of housing type: 2001 data from Census of Population and Housing 2001
- Landuse condition (area of paddy field): 1999 data (GIS data) from Survey Department

Results of the analysis for damage to house and household property, and damage to paddy are shown in Table H.4.2 and the table below, respectively.

Table H.3.7 Damage to Paddy in Basins by Zone

Basin	Zone	Flood Return Period	Inundation Area (km ²)	Damage Amount (Million Rs.)
Kelani	Unprotected Area	2 years	0.02	0.07
		50 years	3.86	16.91
	Other Area	2 years	20.25	90.83
		50 years	36.45	163.05
	Total	2 years	20.27	90.89
		50 years	40.31	179.96
Kalu	Zone A	2 years	4.72	17.57
		50 years	33.47	124.60
	Zone B	2 years	0	0
		50 years	2.44	10.32
	Zone C	2 years	0	0
		50 years	1.27	5.39
	Total	2 years	4.72	17.57
		50 years	37.18	140.30
Gin	Zone A	2 years	2.44	10.74
		50 years	8.34	36.68
	Zone B	2 years	5.77	25.38
		50 years	10.17	44.74
	Total	2 years	8.21	36.12
		50 years	18.50	81.42
Nilwala	Zone A	2 years	0.29	1.47
		50 years	8.86	45.09
	Zone B	2 years	16.50	84.04
		50 years	21.92	111.60
	Total	2 years	16.79	85.51
		50 years	30.77	156.69

Note: Estimated by JICA Study Team

Damages of other flood events with probabilities of 5, 10, 20 and 30 years are calculated using the above result of each two flood events and the result of hydraulic analysis. Table H.4.3 shows the result of calculation.

2) Infrastructure Damage and Interruption to Business Operations

Damage due to interruption to business operations and infrastructure is estimated applying the ratio used in “The Study on Storm Water Drainage Plan for the Colombo Metropolitan Region”, 2003 March, JICA, which was based on the ratio set by the Ministry of Land, Infrastructure and Transport, Japan. The interruption to business operations is estimated at 6% of the sum of house and household property damage, and the damage to infrastructure (roads, bridges) is estimated at 28% of the sum of house and household property damage. Table H.4.3 shows the result of calculation including house, household property and paddy damage for four basins, and the following table is a summarized one.

Table H.3.8 Summary of Probable Flood Damage

(Unit: Million Rs.)

Flood Return Period	Kelani	Kalu	Gin	Nilwala
2 years	5,353.7	652.0	1,355.2	2,925.6
5 years	10,910.7	4,425.2	2,125.5	4,252.9
10 years	14,948.6	7,300.1	2,646.9	5,416.9
20 years	18,637.0	10,243.3	3,413.4	6,003.2
30 years	20,840.7	11,853.5	4,255.0	6,494.9
50 years	23,614.3	14,336.0	5,027.6	7,137.7

Note: Estimated by JICA Study Team

(5) Conversion of Probable Flood Damage to Annual Average Flood Damage

Table H.4.4 shows the annual average flood damage for the four basins and the table below shows the summary of it. The estimated annual average flood damage is considered as a base for the flood reduction benefits. The flood damage reduction benefit is derived from the annual average flood damage and the effect of the flood control measures, which is estimated from the reduced damage by them.

Table H.3.9 Summary of Annual Average Flood Damage

(Unit: Million Rs.)

Flood Return Period	Kelani	Kalu	Gin	Nilwala
2 years	1,338.4	163.0	338.8	731.4
5 years	3,778.1	924.6	860.9	1,808.2
10 years	5,071.1	1,510.9	1,099.5	2,291.7
20 years	5,910.7	1,949.4	1,251.0	2,577.2
30 years	6,239.7	2,133.6	1,314.9	2,681.3
50 years	6,536.1	2,308.2	1,376.8	2,772.2

Note: Estimated by JICA Study Team

H.3.3 Benefit of Multiple Uses of Dam

The benefit of multiple uses of dam is characterized as the effect of dam utilization with other objectives except flood control such as power generation and water supply, since the effect of flood control by dam is already included in the benefit of flood damage reduction. In this analysis, the

function of power generation is counted as other economic benefit from the multipurpose dam. The benefit is calculated by the construction and O&M cost of alternative thermal power generation plant, which has the same capacity and average annual generation as the proposed dam.

The table below shows the unit values for the evaluation of the benefits of multiple uses of dam.

Table H.3.10 Unit Values of Benefit of Multiple Uses of Dam

Type of Alternative Thermal Plants	Construction Cost (US\$/kW)	Fixed O&M Cost (US\$/kW Month)	Variable O&M Cost (USCts/kWh)	Fuel Cost (USCts/kWh)
Steam - Fuel Oil (Capacity: 150 MW)	1304.8	0.802	0.439	5.29

Source: "Long Term Generation Expansion Plan, 2006-2020", December 2005, Ceylon Electricity Board

The following table summarizes the benefit of multiple uses of proposed dams, which is calculated using the above unit values.

Table H.3.11 Benefit of Multiple Uses of Dam

Name of Dam	Basin	Installed Capacity	Constructin Cost of Alternative Thermal Power	Annual Energy Generation	Annual Benefit from Alternative O&M Cost of Thermal Power Plant				Annual Benefit (extracted from the Report concerned)	Source
					Fixed O&M Cost	Variable O&M Cost	Fuel Cost	Total		
					Million Rs.	Million Rs.	Million Rs.	Million Rs.		
Nawata-Parusella	Kelani	44,774 *2	6,491,148	124.87	15.5	60.9	733.9	810.3		*2: DHI 1992
Malwara (Multi-purpose)	Kalu	33,000 *1	4,784,219	111.58 *1	13.8	54.4	655.8	724.1	420 *1	*1: Pre Feasibility Study Assessment of Kalu Ganga Flood Protection with Special Reference to Ratnapura, Drainage & Flood Protection Branch, Irrigation Department, July 2004
Malwara (Flood Control)	Kalu	29,872 *1	4,330,694	94.00 *1	11.6	45.8	552.5	610.0	420 *1	
Jasmin (High)	Gin	20,661 *4	2,995,388	48.73	6.0	23.8	286.4	316.2		*4: ECI 1968
Jasmin (Low)	Gin	9,298 *4	1,347,925	29.59	3.7	14.4	173.9	192.0		*4: ECI 1968
Siyambalagoda (High)	Nilwala	16,164	2,343,353	39.99	4.9	19.5	235.1	259.5		
Siyambalagoda (Low)	Nilwala	11,870	1,720,900	32.76	4.1	16.0	192.6	212.6		

Conditions of Above Calculation

Exchange Rate (US\$ - Rs.)	111.11	Rs.
----------------------------	--------	-----

Unit Value for Construction Cost of Thermal Power Generatio Source: Long Term Generation Expansion Plan, 2006-2005, December 2005, CEB

Plant	Installed Capacity (MW)	Const Period (Years)	Total Construction Cost Including of IDC (US\$/kW)	Economic Life (Years)
Steam - Fuel Oil	150	4	1,305	30

Selected the most highest unit rate of thermal power generation type in the CEB's Report.

Unit Value for O&M Cost of Thermal Power Generation Plant Source: Long Term Generation Expansion Plan, 2006-2005, December 2005, CEB

Plant	Installed Capacit v (MW)	Fixed O&M Cost (US\$/k W)	Variable O&M Cost (USCts/kwh)	Fuel Cost (USCts/kwh)
Steam - Fuel Oil	150	0.802	0.439	5.29

Selected the most highest unit rate of thermal power generation type in the CEB's Report.

H.3.4 Intangible Benefit

In addition to the quantitative benefits discussed and estimated in the previous sections, it should be noted that the proposed project would produce a lot of intangible benefits that cannot be measured quantitatively. The following intangible benefits can be expected through the implementation of the project.

1) Promotion of Landuse Development and Economic Development

The proposed project creates flood free land and the flood free land can be utilized for industry, commercial and residential purposes. Consequently, the economic development of the region is promoted.

2) Hygienic Improvement of the Environment

The flooding causes health hazards such as breeding of mosquitoes, contaminating the water and the spread of intestinal diseases, which are identified as one of the major causes of death among children and elderly. The project will improve the hygienic environment and improve the people's health. It eventually contributes to savings in health care cost.

3) Alleviation of Inconvenience to People's Life

The flooding usually affects the people's life and causes inconvenience such as a decline in the standard of their living due to damage to their assets and public facilities, shortage of goods, steep rise in prices, lowering of administrative and educational activities, etc. As the project aims at reducing flooding in space and time, the people's lives will become much more convenient due to the project.

4) Elimination of the Menace of Flooding

The people living in the lowlands are exposed to the menace of flooding. The project will eliminate the menace of flooding by reducing flooding or protecting the people from flood.

H.4 Economic Evaluation for the Proposed Alternative Projects

H.4.1 Basic Conditions

On the basis of the estimated construction cost, operation and maintenance cost (O&M cost) and estimated economic benefits, the Economic Internal Rate of Return (EIRR), B-C and B/C of proposed alternative projects are calculated based on the following assumptions.

- 1) Project life of 50 years
- 2) Discount rate of 10%
- 3) Project cost of short term is disbursed according to the construction schedule.
- 4) Project cost of medium and long term is disbursed according to the construction schedule.
- 5) The O&M cost is assumed to be disbursed for the entire project lifetime from the year following completion of the project works in each term of short term and medium and long term.
- 6) Benefit is produced over the entire project life from the year following completion of the project works in each term of short term and medium and long term.
- 7) The benefit is expected not to increase.

H.4.2 Economic Evaluation for Proposed Alternative Projects

The flood control benefit for the project is composed of the flood damage reduction benefit and the benefit of multiple uses of dam. The flood damage reduction benefit is calculated based on the annual average flood damage and the impact of the projects measured by the difference between the inundation area with and without the project. The impact of the projects is calculated by the size of reduction of the expected

inundation area with the project. The benefit of multiple uses of dam is calculated based on construction and O&M cost of alternative thermal power generation plant.

H.4.3 Results of the Evaluations

The results of the evaluations for the proposed alternative projects for each basin are expressed in B-C (Rs. million), B/C and EIRR (%). Economic feasibility line of the project is considered to be positive for B-C, one or above for B/C and 10% or higher for EIRR, which is based on the discount rate of 10%. Cost benefit streams of the proposed alternative projects for each basin are shown in Table H.4.5, and results of the evaluations of selected projects in each basin are summarized in the table below:

Table H.4.1 Economic Evaluation for the Selected Proposed Projects

Short-term Plan

Basin	B-C (Million Rs.)	B/C	EIRR (%)
Kelani (5-yr)	8,811	3.2	24.4
Kalu (10-yr)	7,617	2.89	23.5
Gin (10-yr)	1,512	1.23	12.4
Nilwala (10-yr)	6,105	2.00	19.2

Long-term Plan

Basin	B-C (Million Rs.)	B/C	EIRR (%)
Kelani (20-yr)	9,611	2.4	20.7
Kalu (30-yr)	7,438	2.24	20.7
Gin (30-yr)	555	1.07	10.7
Nilwala (30-yr)	5,890	1.85	18.0

Note: Estimated by JICA Study Team

Table H.4.2 (1) Damage to House and Household Property with Inundation Depth in Kelani Basin

Kelani (1/2)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House Number by Housing	16,570	0	0	0	0	16,570
Permanent	14,074	0	0	0	0	14,074
Simi-Permanent	2,387	0	0	0	0	2,387
Improvised	109	0	0	0	0	109
Damage to House (Million Rs.)	2,666.6	0.0	0.0	0.0	0.0	2,666.6
Damage to Household Property (Million Rs.)	1,260.9	0.0	0.0	0.0	0.0	1,260.9
Total Damage (Million Rs.)	3,927.5	0.0	0.0	0.0	0.0	3,927.5

Kelani (1/50)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House Number by Housing	70,710	21	97	243	101	71,171
Permanent	60,627	17	82	206	89	61,022
Simi-Permanent	9,688	4	14	35	12	9,753
Improvised	394	0	1	2	0	397
Damage to House (Million Rs.)	11,435.0	4.3	45.1	245.8	150.4	11,880.6
Damage to Household Property (Million Rs.)	5,406.8	3.5	25.8	118.0	53.6	5,607.7
Total Damage (Million Rs.)	16,841.7	7.8	70.9	363.9	204.0	17,488.3

Table H.4.2 (2) Damage to House and Household Property with Inundation Depth in Kalu Basin

Zone A (1/2)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House Number by Housing	1,555	134	92	0	0	1,781
Permanent	1,239	107	74	0	0	1,419
Semi-Permanent	309	27	18	0	0	354
Improvised	7	1	0	0	0	8
Damage to House (Million Rs.)	243.4	27.1	41.7	0.0	0.0	312.2
Damage to Household Property (Million Rs.)	115.1	22.3	23.9	0.0	0.0	161.3
Total Damage (Million Rs.)	358.4	49.4	65.7	0.0	0.0	473.5

Zone A (1/50)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House Number by Housing	6,070	1,055	2,241	1,229	442	11,037
Permanent	4,835	841	1,783	979	352	8,791
Semi-Permanent	1,207	210	448	245	88	2,197
Improvised	27	5	10	6	2	50
Damage to House (Million Rs.)	949.7	213.6	1,013.3	1,212.4	627.0	4,016.0
Damage to Household Property (Million Rs.)	449.1	175.5	580.6	581.9	223.5	2,010.6
Total Damage (Million Rs.)	1,398.8	389.1	1,593.9	1,794.3	850.5	6,026.5

Zone B (1/2)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House Number by Housing	0	0	0	0	0	0
Permanent	0	0	0	0	0	0
Semi-Permanent	0	0	0	0	0	0
Improvised	0	0	0	0	0	0
Damage to House (Million Rs.)	0.0	0.0	0.0	0.0	0.0	0.0
Damage to Household Property (Million Rs.)	0.0	0.0	0.0	0.0	0.0	0.0
Total Damage (Million Rs.)	0.0	0.0	0.0	0.0	0.0	0.0

Zone B (1/50)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House Number by Housing	631	185	232	149	304	1,500
Permanent	388	113	143	92	187	922
Semi-Permanent	242	71	89	57	116	575
Improvised	1	0	0	0	1	3
Damage to House (Million Rs.)	88.8	33.6	94.5	132.0	387.3	736.2
Damage to Household Property (Million Rs.)	42.0	27.6	54.1	63.4	138.1	325.2
Total Damage (Million Rs.)	130.8	61.2	148.6	195.4	525.4	1,061.4

Zone C (1/2)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House Number by Housing	0	0	0	0	0	0
Permanent	0	0	0	0	0	0
Semi-Permanent	0	0	0	0	0	0
Improvised	0	0	0	0	0	0
Damage to House (Million Rs.)	0.0	0.0	0.0	0.0	0.0	0.0
Damage to Household Property (Million Rs.)	0.0	0.0	0.0	0.0	0.0	0.0
Total Damage (Million Rs.)	0.0	0.0	0.0	0.0	0.0	0.0

Zone C (1/50)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House Number by Housing	1,366	131	71	119	1,720	3,408
Permanent	840	81	44	73	1,058	2,096
Semi-Permanent	524	50	27	46	659	1,306
Improvised	2	0	0	0	3	6
Damage to House (Million Rs.)	192.3	23.8	29.1	105.6	2,194.8	2,545.6
Damage to Household Property (Million Rs.)	90.9	19.6	16.7	50.7	782.4	960.3
Total Damage (Million Rs.)	283.2	43.4	45.7	156.3	2,977.2	3,505.9

Total (1/2)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House Number by Housing	1,555	134	92	0	0	1,781
Permanent	1,239	107	74	0	0	1,419
Semi-Permanent	309	27	18	0	0	354
Improvised	7	1	0	0	0	8
Damage to House (Million Rs.)	243	27	42	0	0	312.2
Damage to Household Property (Million Rs.)	115	22	24	0	0	161.3
Total Damage (Million Rs.)	358.4	49.4	65.7	0.0	0.0	473.5

Total (1/50)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House Number by Housing	8,067	1,371	2,545	1,497	2,466	15,945
Permanent	6,064	1,035	1,970	1,144	1,597	11,809
Semi-Permanent	1,973	330	564	347	864	4,078
Improvised	31	5	11	6	5	58
Damage to House (Million Rs.)	1,231	271	1,137	1,450	3,209	7,297.8
Damage to Household Property (Million Rs.)	582	223	651	696	1,144	3,296.0
Total Damage (Million Rs.)	1,812.8	493.7	1,788.2	2,146.0	4,353.1	10,593.8

Table H.4.2 (3) Damage to House and Household Property with Inundation Depth in Gin Basin

Zone A (1/2)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House	567	52	64	21	27	731
Number by Housing						
Permanent	413	38	47	15	20	532
Semi-Permanent	150	14	17	6	7	193
Improvised	4	0	0	0	0	6
Damage to House (Million Rs.)	85.2	10.1	27.8	19.7	36.5	179.3
Damage to Household Property (Million Rs.)	40.3	8.3	15.9	9.5	13.0	87.0
Total Damage (Million Rs.)	125.4	18.4	43.7	29.2	49.5	266.2

Zone A (1/50)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House	1,060	40	132	121	448	1,801
Number by Housing						
Permanent	771	29	96	88	326	1,311
Semi-Permanent	280	11	35	32	118	476
Improvised	8	0	1	1	3	14
Damage to House (Million Rs.)	159.1	7.8	57.5	114.1	609.9	948.5
Damage to Household Property (Million Rs.)	75.2	6.4	33.0	54.8	217.4	386.8
Total Damage (Million Rs.)	234.4	14.2	90.5	168.9	827.3	1,335.3

Zone B (1/2)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House	699	86	234	180	65	1,265
Number by Housing						
Permanent	509	63	170	131	48	921
Semi-Permanent	185	23	62	48	17	334
Improvised	5	1	2	1	0	10
Damage to House (Million Rs.)	105.1	16.8	101.5	170.5	89.2	482.9
Damage to Household Property (Million Rs.)	49.7	13.8	58.1	81.8	31.8	235.2
Total Damage (Million Rs.)	154.7	30.6	159.6	252.3	120.9	718.2

Zone B (1/50)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House	1,051	60	70	132	1,012	2,324
Number by Housing						
Permanent	765	43	51	96	737	1,692
Semi-Permanent	278	16	18	35	267	614
Improvised	8	0	1	1	8	18
Damage to House (Million Rs.)	157.8	11.6	30.4	125.4	1,377.8	1,703.0
Damage to Household Property (Million Rs.)	74.6	9.5	17.4	60.2	491.2	652.9
Total Damage (Million Rs.)	232.4	21.1	47.8	185.6	1,869.0	2,355.9

Total (1/2)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House	1,266	138	298	201	92	1,996
Number by Housing						
Permanent	922	101	217	146	67	1,453
Semi-Permanent	335	37	79	53	24	527
Improvised	10	1	2	2	1	15
Damage to House (Million Rs.)	190	27	129	190	126	662.2
Damage to Household Property (Million Rs.)	90	22	74	91	45	322.2
Total Damage (Million Rs.)	280.2	49.0	203.3	281.5	170.4	984.4

Total (1/50)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House	2,110	100	202	253	1,460	4,125
Number by Housing						
Permanent	1,536	73	147	184	1,063	3,004
Semi-Permanent	558	26	53	67	386	1,090
Improvised	16	1	2	2	11	31
Damage to House (Million Rs.)	317	19	88	240	1,988	2,651.5
Damage to Household Property (Million Rs.)	150	16	50	115	709	1,039.7
Total Damage (Million Rs.)	466.8	35.3	138.2	354.5	2,696.3	3,691.2

Table H.4.2 (4) Damage to House and Household Property with Inundation Depth in Nilwala Basin

Zone A (1/2)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House Number by Housing	2,220	119	146	6	0	2,491
Permanent	1,617	87	106	4	0	1,815
Semi-Permanent	589	32	39	2	0	661
Improvised	14	1	1	0	0	16
Damage to House (Million Rs.)	333.8	23.1	63.4	5.6	0.0	426.0
Damage to Household Property (Million Rs.)	157.8	19.0	36.3	2.7	0.0	215.9
Total Damage (Million Rs.)	491.6	42.2	99.7	8.3	0.0	641.8

Zone A (1/50)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House Number by Housing	3,417	193	321	190	366	4,488
Permanent	2,489	141	234	139	267	3,270
Semi-Permanent	906	51	85	51	97	1,190
Improvised	22	1	2	1	2	28
Damage to House (Million Rs.)	513.7	37.6	139.7	180.5	498.9	1,370.4
Damage to Household Property (Million Rs.)	242.9	30.9	80.0	86.7	177.8	618.3
Total Damage (Million Rs.)	756.5	68.5	219.8	267.2	676.7	1,988.7

Zone B (1/2)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House Number by Housing	4,726	318	295	83	0	5,423
Permanent	3,443	232	215	61	0	3,950
Semi-Permanent	1,253	84	78	22	0	1,438
Improvised	30	2	2	1	0	34
Damage to House (Million Rs.)	710.5	61.9	128.1	79.0	0.0	979.5
Damage to Household Property (Million Rs.)	336.0	50.9	73.4	37.9	0.0	498.1
Total Damage (Million Rs.)	1,046.5	112.8	201.4	116.9	0.0	1,477.6

Zone B (1/50)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House Number by Housing	4,143	208	625	634	494	6,104
Permanent	3,018	152	455	462	360	4,447
Semi-Permanent	1,099	55	166	168	131	1,619
Improvised	26	1	4	4	3	38
Damage to House (Million Rs.)	622.8	40.5	271.7	600.8	673.3	2,209.1
Damage to Household Property (Million Rs.)	294.5	33.3	155.6	288.4	240.0	1,011.8
Total Damage (Million Rs.)	917.3	73.8	427.3	889.2	913.3	3,221.0

Zone B (1/2)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House Number by Housing	6,946	438	440	89	0	7,914
Permanent	5,060	319	321	65	0	5,765
Semi-Permanent	1,842	116	117	24	0	2,099
Improvised	44	3	3	1	0	50
Damage to House (Million Rs.)	1,044	85	191	85	0	1,405.5
Damage to Household Property (Million Rs.)	494	70	110	41	0	714.0
Total Damage (Million Rs.)	1,538.1	155.0	301.2	125.2	0.0	2,119.5

Zone B (1/50)

Item	Inundation Depth					Total
	<50cm	50-99cm	100-199cm	200-299cm	>=300cm	
Damaged House Number by Housing	7,560	402	946	824	860	10,592
Permanent	5,507	293	689	601	627	7,716
Semi-Permanent	2,005	107	251	219	228	2,809
Improvised	48	3	6	5	5	67
Damage to House (Million Rs.)	1,136	78	411	781	1,172	3,579.5
Damage to Household Property (Million Rs.)	537	64	236	375	418	1,630.2
Total Damage (Million Rs.)	1,673.8	142.3	647.1	1,156.4	1,590.1	5,209.7

Table H.4.3 (1) Probable Flood Damage in Kelani Basin by Zone

Basin	Return Period (Year)	Discharge at Downstream (m3/sec.)	Damage to Households (Million Rs.)	Damage to Household Property (Million Rs.)	Damage to Paddy (Million Rs.)	Disturbance to Business Activities (Million Rs.)	Damage to Infrastructure (Million Rs.)	Total Damage (Million Rs.)
Kelani	2	1,671.6	2,666.6	1,260.9	90.9	235.7	1,099.7	5,353.7
	5	2,803.8	5,470.6	2,583.7	118.0	483.3	2,255.2	10,910.7
	10	3,626.5	7,508.0	3,544.9	137.7	663.2	3,094.8	14,948.6
	20	4,378.0	9,369.1	4,422.9	155.7	827.5	3,861.8	18,637.0
	30	4,827.0	10,481.1	4,947.5	166.4	925.7	4,320.0	20,840.7
	50	5,392.1	11,880.6	5,607.7	180.0	1,049.3	4,896.7	23,614.3

Table H.4.3 (2) Probable Flood Damage in Kalu Basin by Zone

Zone	Return Period (Year)	Discharge at Downstream (m3/sec.)	Damage to Households (Million Rs.)	Damage to Household Property (Million Rs.)	Damage to Paddy (Million Rs.)	Disturbance to Business Activities (Million Rs.)	Damage to Infrastructure (Million Rs.)	Total Damage (Million Rs.)
Zone A	2	711.0	312.2	161.3	17.6	28.4	132.6	652.0
	5	1,244.6	1,321.1	665.0	46.7	119.2	556.1	2,708.0
	10	1,654.7	2,096.4	1,052.1	69.1	188.9	881.6	4,288.2
	20	2,075.0	2,891.1	1,448.9	92.1	260.4	1,215.2	5,907.8
	30	2,286.8	3,291.7	1,648.9	103.7	296.4	1,383.4	6,724.1
	50	2,669.9	4,016.0	2,010.6	124.6	361.6	1,687.4	8,200.1
Zone B	2	504.4	0.0	0.0	0.0	0.0	0.0	0.0
	5	816.1	198.0	87.4	2.8	17.1	79.9	385.3
	10	1,062.4	354.4	156.5	5.0	30.7	143.1	689.7
	20	1,315.2	515.0	227.5	7.2	44.6	207.9	1,002.2
	30	1,468.7	612.5	270.5	8.6	53.0	247.3	1,191.9
	50	1,663.4	736.2	325.2	10.3	63.7	297.2	1,432.6
Zone C	2	443.9	0.0	0.0	0.0	0.0	0.0	0.0
	5	683.5	720.9	271.9	1.5	59.6	278.0	1,331.9
	10	861.7	1,256.9	474.1	2.7	103.9	484.7	2,322.3
	20	1,043.7	1,804.2	680.6	3.8	149.1	695.7	3,333.3
	30	1,152.4	2,131.1	803.9	4.5	176.1	821.8	3,937.5
	50	1,290.2	2,545.6	960.3	5.4	210.4	981.6	4,703.3
Kalu Basin Total	2	—	312.2	161.3	17.6	28.4	132.6	652.0
	5	—	2,239.9	1,024.4	51.0	195.9	914.0	4,425.2
	10	—	3,707.8	1,682.8	76.8	323.4	1,509.4	7,300.1
	20	—	5,210.3	2,357.0	103.1	454.0	2,118.9	10,243.3
	30	—	6,035.4	2,723.4	116.8	525.5	2,452.5	11,853.5
	50	—	7,297.8	3,296.0	140.3	635.6	2,966.3	14,336.0

Table H.4.3 (3) Probable Flood Damage in Gin Basin by Zone

Zone	Return Period (Year)	Discharge at Downstream (m3/sec.)	Damage to Households (Million Rs.)	Damage to Household Property (Million Rs.)	Damage to Paddy (Million Rs.)	Disturbance to Business Activities (Million Rs.)	Damage to Infrastructure (Million Rs.)	Total Damage (Million Rs.)
Zone A	2	634.2	179.3	87.0	10.7	16.0	74.5	367.5
	5	1,026.9	417.2	179.7	18.8	35.8	167.1	818.7
	10	1,293.7	579.0	242.8	24.2	49.3	230.1	1,125.3
	20	1,554.4	736.9	304.4	29.5	62.5	291.6	1,424.9
	30	1,702.9	826.9	339.4	32.6	70.0	326.6	1,595.5
	50	1,903.5	948.5	386.8	36.7	80.1	373.9	1,826.0
Zone B	2	543.2	482.9	235.2	25.4	43.1	201.1	987.7
	5	900.5	658.8	295.4	28.2	57.3	267.2	1,306.8
	10	1,140.9	777.1	335.9	30.0	66.8	311.7	1,521.5
	20	1,663.8	1,034.5	424.0	34.1	87.5	408.4	1,988.6
	30	2,414.9	1,404.2	550.6	40.0	117.3	547.4	2,659.5
	50	3,021.9	1,703.0	652.9	44.7	141.4	659.6	3,201.6
Gin Basin Total	2	—	662.2	322.2	36.1	59.1	275.6	1,355.2
	5	—	1,076.0	475.1	46.9	93.1	434.3	2,125.5
	10	—	1,356.1	578.7	54.3	116.1	541.7	2,646.9
	20	—	1,771.4	728.4	63.7	150.0	700.0	3,413.4
	30	—	2,231.2	890.0	72.6	187.3	873.9	4,255.0
	50	—	2,651.5	1,039.7	81.4	221.5	1,033.5	5,027.6

Table H.4.3 (4) Probable Flood Damage in Nilwala Basin by Zone

Zone	Return Period (Year)	Discharge at Downstream (m ³ /sec.)	Damage to Households (Million Rs.)	Damage to Household Property (Million Rs.)	Damage to Paddy (Million Rs.)	Disturbance to Business Activities (Million Rs.)	Damage to Infrastructure (Million Rs.)	Total Damage (Million Rs.)
Zone A	2	637.0	426.0	215.9	1.5	38.5	179.7	861.5
	5	1,214.4	720.7	341.5	15.1	63.7	297.4	1,438.3
	10	1,878.5	1,059.6	485.9	30.7	92.7	432.7	2,101.6
	20	1,983.5	1,113.2	508.7	33.2	97.3	454.1	2,206.6
	30	2,198.7	1,223.0	555.5	38.3	106.7	498.0	2,421.5
	50	2,487.5	1,370.4	618.3	45.1	119.3	556.8	2,710.0
Zone B	2	544.7	979.5	498.1	84.0	88.7	413.7	2,064.1
	5	1,051.1	1,369.9	661.2	92.8	121.9	568.7	2,814.6
	10	1,388.9	1,630.4	770.1	98.6	144.0	672.1	3,315.2
	20	1,713.7	1,880.8	874.7	104.2	165.3	771.5	3,796.6
	30	1,900.5	2,024.8	934.8	107.5	177.6	828.7	4,073.4
	50	2,139.6	2,209.1	1,011.8	111.6	193.3	901.9	4,427.7
Nilwala Basin Total	2	—	1,405.5	714.0	85.5	127.2	593.5	2,925.6
	5	—	2,090.6	1,002.7	107.9	185.6	866.1	4,252.9
	10	—	2,690.0	1,255.9	129.4	236.8	1,104.9	5,416.9
	20	—	2,994.0	1,383.4	137.4	262.6	1,225.7	6,003.2
	30	—	3,247.8	1,490.4	145.7	284.3	1,326.7	6,494.9
	50	—	3,579.5	1,630.2	156.7	312.6	1,458.7	7,137.7

Table H.4.4 (1) Annual Average Flood Damage in Kelani Basin by Zone

Basin	Return Period (Year)	Exceedance	Difference of Exceedance	Damage (Rs. Million)		Annual Damage (Rs. Million)	
				Amount	Average	Segment	Cumulative
Kelani	2	1.00	0.50	5,353.7	2,676.9	1,338.4	1,338.4
	5	0.50	0.30	10,910.7	8,132.2	2,439.7	3,778.1
	10	0.20	0.10	14,948.6	12,929.6	1,293.0	5,071.1
	20	0.10	0.05	18,637.0	16,792.8	839.6	5,910.7
	30	0.05	0.02	20,840.7	19,738.9	329.0	6,239.7
	50	0.02	0.01	23,614.3	22,227.5	296.4	6,536.1

Table H.4.4 (2) Annual Average Flood Damage in Kalu Basin by Zone

Zone	Return Period (Year)	Exceedance	Difference of Exceedance	Damage (Rs. Million)		Annual Damage (Rs. Million)	
				Amount	Average	Segment	Cumulative
Zone A	2	1.00	0.50	652.0	326.0	163.0	163
	5	0.50	0.30	2,708.0	1,680.0	504.0	667
	10	0.20	0.10	4,288.2	3,498.1	349.8	1,017
	20	0.10	0.05	5,907.8	5,098.0	254.9	1,272
	30	0.05	0.02	6,724.1	6,315.9	105.3	1,377
	50	0.02	0.01	8,200.1	7,462.1	99.5	1,476
Zone B	2	1.00	0.50	0.0	0.0	0.0	0.0
	5	0.50	0.30	385.3	192.6	57.8	57.8
	10	0.20	0.10	689.7	537.5	53.7	111.5
	20	0.10	0.05	1,002.2	845.9	42.3	153.8
	30	0.05	0.02	1,191.9	1,097.1	18.3	172.1
	50	0.02	0.01	1,432.6	1,312.3	17.5	189.6
Zone C	2	1.00	0.50	0.0	0.0	0.0	0.0
	5	0.50	0.30	1,331.9	666.0	199.8	199.8
	10	0.20	0.10	2,322.3	1,827.1	182.7	382.5
	20	0.10	0.05	3,333.3	2,827.8	141.4	523.9
	30	0.05	0.02	3,937.5	3,635.4	60.6	584.5
	50	0.02	0.01	4,703.3	4,320.4	57.6	642.1
Total	2	1.00	0.50	652.0	326.0	163.0	163.0
	5	0.50	0.30	4,425.2	2,538.6	761.6	924.6
	10	0.20	0.10	7,300.1	5,862.7	586.3	1,510.9
	20	0.10	0.05	10,243.3	8,771.7	438.6	1,949.4
	30	0.05	0.02	11,853.5	11,048.4	184.1	2,133.6
	50	0.02	0.01	14,336.0	13,094.7	174.6	2,308.2

Table H.4.4 (3) Annual Average Flood Damage in Gin Basin by Zone

Zone	Return Period (Year)	Exceedance	Difference of Exceedance	Damage (Rs. Million)		Annual Damage (Rs. Million)	
				Amount	Average	Segment	Cumulative
Zone A		1.00					
		2	0.50	0.50	367.5	183.8	91.9
		5	0.20	0.30	818.7	593.1	177.9
		10	0.10	0.10	1,125.3	972.0	97.2
		20	0.05	0.05	1,424.9	1,275.1	63.8
		30	0.03	0.02	1,595.5	1,510.2	25.2
Zone B		50	0.02	0.01	1,826.0	1,710.8	22.8
		1.00					
		2	0.50	0.50	987.7	493.9	246.9
		5	0.20	0.30	1,306.8	1,147.2	344.2
		10	0.10	0.10	1,521.5	1,414.2	141.4
		20	0.05	0.05	1,988.6	1,755.1	87.8
Total		30	0.03	0.02	2,659.5	2,324.0	38.7
		50	0.02	0.01	3,201.6	2,930.5	39.1
		1.00				0	
		2	0.50	0.50	1,355.2	677.6	338.8
		5	0.20	0.30	2,125.5	1,740.3	522.1
		10	0.10	0.10	2,646.9	2,386.2	238.6
		20	0.05	0.05	3,413.4	3,030.2	151.5
		30	0.03	0.02	4,255.0	3,834.2	63.9
		50	0.02	0.01	5,027.6	4,641.3	61.9
		1.00					
		2	0.50	0.50	338.8	338.8	
		5	0.20	0.30	860.9	860.9	
		10	0.10	0.10	1,099.5	1,099.5	
		20	0.05	0.05	1,251.0	1,251.0	
		30	0.03	0.02	1,314.9	1,314.9	
		50	0.02	0.01	1,376.8	1,376.8	

Table H.4.4 (4) Annual Average Flood Damage in Nilwala Basin by Zone

Zone	Return Period (Year)	Exceedance	Difference of Exceedance	Damage (Rs. Million)		Annual Damage (Rs. Million)	
				Amount	Average	Segment	Cumulative
Zone A		1.00					
		2	0.50	0.50	861.5	430.8	215.4
		5	0.20	0.30	1,438.3	1,149.9	345.0
		10	0.10	0.10	2,101.6	1,770.0	177.0
		20	0.05	0.05	2,206.6	2,154.1	107.7
		30	0.03	0.02	2,421.5	2,314.1	38.6
Zone B		50	0.02	0.01	2,710.0	2,565.8	34.2
		1.00					
		2	0.50	0.50	2,064.1	1,032.0	516.0
		5	0.20	0.30	2,814.6	2,439.3	731.8
		10	0.10	0.10	3,315.2	3,064.9	306.5
		20	0.05	0.05	3,796.6	3,555.9	177.8
Total		30	0.03	0.02	4,073.4	3,935.0	65.6
		50	0.02	0.01	4,427.7	4,250.5	56.7
		1.00				0	
		2	0.50	0.50	2,925.6	1,462.8	731.4
		5	0.20	0.30	4,252.9	3,589.3	1,076.8
		10	0.10	0.10	5,416.9	4,834.9	483.5
		20	0.05	0.05	6,003.2	5,710.0	285.5
		30	0.03	0.02	6,494.9	6,249.0	104.2
		50	0.02	0.01	7,137.7	6,816.3	90.9
		1.00					
		2	0.50	0.50	731.4	731.4	
		5	0.20	0.30	1,808.2	1,808.2	
		10	0.10	0.10	2,291.7	2,291.7	
		20	0.05	0.05	2,577.2	2,577.2	
		30	0.03	0.02	2,681.3	2,681.3	
		50	0.02	0.01	2,772.2	2,772.2	

Table H.4.5 (1) Cost Benefit Stream of Alternative Plan of Case 1 in Kelani River Basin

River:	Kelani	Overall										
Case:	1											
Year	Cost			NPV			Benefit			(Unit: Million Rs.)		
	Short Term	Long Term	Total	Grand Total	Short Term	Long Term	Total	Short Term	Long Term	Grand Total	NPV	B-C (NPV)
1	1,041	945	1,041	945	0	1,041	946	0	0	0	0	-1041
2	945	1,540	1,540	0	0	945	781	0	0	0	0	-945
3	1,540	1,137	1,137	0	0	1,540	1,157	0	0	0	0	-1540
4	1,137	736	736	0	0	1,137	736	0	0	0	0	-1137
5	736	3,765	54	54	0	736	457	0	0	0	0	-736
6	3,765	3,082	54	54	0	3,765	2,156	0	0	0	0	-3,765
7	3,082	2,558	54	54	0	3,082	1,609	0	0	0	0	-3,082
8	2,558	1,615	54	54	0	2,558	1,219	0	0	0	0	-2,558
9	1,615	458	54	54	0	1,615	708	0	0	0	0	-1,615
10	458	458	54	54	0	458	512	0	0	0	0	-458
11	496	496	54	54	0	496	550	0	0	0	0	-496
12	538	538	54	54	0	538	592	0	0	0	0	-538
13	585	585	54	54	0	585	639	0	0	0	0	-585
14	483	537	54	54	0	483	537	0	0	0	0	-483
15	187	187	54	54	0	187	241	0	0	0	0	-187
16	0	138	54	54	0	138	192	42	0	0	0	-138
17	0	138	54	54	0	138	192	38	0	0	0	-138
18	0	138	54	54	0	138	192	34	0	0	0	-138
19	0	138	54	54	0	138	192	31	0	0	0	-138
20	0	138	54	54	0	138	192	28	0	0	0	-138
21	0	138	54	54	0	138	192	26	0	0	0	-138
22	0	138	54	54	0	138	192	24	0	0	0	-138
23	0	138	54	54	0	138	192	21	0	0	0	-138
24	0	138	54	54	0	138	192	19	0	0	0	-138
25	0	138	54	54	0	138	192	18	0	0	0	-138
26	0	138	54	54	0	138	192	16	0	0	0	-138
27	0	138	54	54	0	138	192	15	0	0	0	-138
28	0	138	54	54	0	138	192	13	0	0	0	-138
29	0	138	54	54	0	138	192	12	0	0	0	-138
30	0	138	54	54	0	138	192	11	0	0	0	-138
31	0	138	54	54	0	138	192	10	0	0	0	-138
32	0	138	54	54	0	138	192	9	0	0	0	-138
33	0	138	54	54	0	138	192	8	0	0	0	-138
34	0	138	54	54	0	138	192	8	0	0	0	-138
35	0	138	54	54	0	138	192	7	0	0	0	-138
36	0	138	54	54	0	138	192	6	0	0	0	-138
37	0	138	54	54	0	138	192	5	0	0	0	-138
38	0	138	54	54	0	138	192	5	0	0	0	-138
39	0	138	54	54	0	138	192	4	0	0	0	-138
40	0	138	54	54	0	138	192	4	0	0	0	-138
41	0	138	54	54	0	138	192	3	0	0	0	-138
42	0	138	54	54	0	138	192	3	0	0	0	-138
43	0	138	54	54	0	138	192	3	0	0	0	-138
44	0	138	54	54	0	138	192	3	0	0	0	-138
45	0	138	54	54	0	138	192	2	0	0	0	-138
46	0	138	54	54	0	138	192	2	0	0	0	-138
47	0	138	54	54	0	138	192	2	0	0	0	-138
48	0	138	54	54	0	138	192	2	0	0	0	-138
49	0	138	54	54	0	138	192	2	0	0	0	-138
50	0	138	54	54	0	138	192	2	0	0	0	-138
	5,398	13,765	0	54	26,410	11,213	0	0	0	0	0	9,086
												9,085
												-0.75
												13.76%
												1.37

Table H.4.5 (2) Cost Benefit Stream of Alternative Plan of Case 1 in Kelani River Basin

River: Kelani
Case: Short
1

Year	Construction Cost			Cost O&M			Flood Control			Benefit			(Unit: Million Rs.)
	Short Term	Long Term	Total	Short Term	Long Term	Total	Grand Total	Short Term	Long Term	Total	Grand Total	NPV	B-C (NPV)
1	1,041	945	1,041	945	1715	946	1,041	945	1,041	946	1,041	0	-946
2	945	1540	2,485	1539	842	2,481	0	945	781	0	0	0	-781
3	1540	1137	2,677	1137	1,078	2,675	0	1,540	1,157	0	0	0	-1,157
4	1137	736	1,883	735	5332	1,888	0	1,137	777	0	0	0	-1,137
5	736	0	736	54	30	2,078	0	736	457	0	0	0	-736
6	0	54	54	54	28	2,078	0	0	0	0	0	0	0
7	0	54	54	54	25	2,078	0	0	0	0	0	0	0
8	0	54	54	54	23	2,078	0	0	0	0	0	0	0
9	0	54	54	54	21	2,078	0	0	0	0	0	0	0
10	0	54	54	54	19	2,078	0	0	0	0	0	0	0
11	0	54	54	54	17	2,078	0	0	0	0	0	0	0
12	0	54	54	54	16	2,078	0	0	0	0	0	0	0
13	0	54	54	54	14	2,078	0	0	0	0	0	0	0
14	0	54	54	54	13	2,078	0	0	0	0	0	0	0
15	0	54	54	54	12	2,078	0	0	0	0	0	0	0
16	0	54	54	54	11	2,078	0	0	0	0	0	0	0
17	0	54	54	54	10	2,078	0	0	0	0	0	0	0
18	0	54	54	54	9	2,078	0	0	0	0	0	0	0
19	0	54	54	54	8	2,078	0	0	0	0	0	0	0
20	0	54	54	54	7	2,078	0	0	0	0	0	0	0
21	0	54	54	54	6	2,078	0	0	0	0	0	0	0
22	0	54	54	54	5	2,078	0	0	0	0	0	0	0
23	0	54	54	54	4	2,078	0	0	0	0	0	0	0
24	0	54	54	54	3	2,078	0	0	0	0	0	0	0
25	0	54	54	54	2	2,078	0	0	0	0	0	0	0
26	0	54	54	54	1	2,078	0	0	0	0	0	0	0
27	0	54	54	54	0	2,078	0	0	0	0	0	0	0
28	0	54	54	54	0	2,078	0	0	0	0	0	0	0
29	0	54	54	54	0	2,078	0	0	0	0	0	0	0
30	0	54	54	54	0	2,078	0	0	0	0	0	0	0
31	0	54	54	54	0	2,078	0	0	0	0	0	0	0
32	0	54	54	54	0	2,078	0	0	0	0	0	0	0
33	0	54	54	54	0	2,078	0	0	0	0	0	0	0
34	0	54	54	54	0	2,078	0	0	0	0	0	0	0
35	0	54	54	54	0	2,078	0	0	0	0	0	0	0
36	0	54	54	54	0	2,078	0	0	0	0	0	0	0
37	0	54	54	54	0	2,078	0	0	0	0	0	0	0
38	0	54	54	54	0	2,078	0	0	0	0	0	0	0
39	0	54	54	54	0	2,078	0	0	0	0	0	0	0
40	0	54	54	54	0	2,078	0	0	0	0	0	0	0
41	0	54	54	54	0	2,078	0	0	0	0	0	0	0
42	0	54	54	54	0	2,078	0	0	0	0	0	0	0
43	0	54	54	54	0	2,078	0	0	0	0	0	0	0
44	0	54	54	54	0	2,078	0	0	0	0	0	0	0
45	0	54	54	54	0	2,078	0	0	0	0	0	0	0
46	0	54	54	54	0	2,078	0	0	0	0	0	0	0
47	0	54	54	54	0	2,078	0	0	0	0	0	0	0
48	0	54	54	54	0	2,078	0	0	0	0	0	0	0
49	0	54	54	54	0	2,078	0	0	0	0	0	0	0
50	0	54	54	54	0	2,078	0	0	0	0	0	0	0
	5,398	0	7,827	4,448								3,115	3,116
												0.83	0.83
												23.35%	23.35%

IRR	2.86
B-C	
B/C	

Table H.4.5 (3) Cost Benefit Stream of Alternative Plan of Case 2 in Kelani River Basin

River:	Kelani	Overall	Case:	2	Cost												Benefit												EIRR	Benefit Net Present Value	Verification
					Construction Cost				O&M				Flood Control				Power Generation				Grand Total				NPV				B-C (NPV)		
Year	Short Term	Long Term	Total	Short Term	Long Term	Total	0	Short Term	Long Term	Total	Short Term	Long Term	Total	0	Short Term	Long Term	Total	0	Short Term	Long Term	Total	0	Short Term	Long Term	Total	0	Short Term	Long Term	Total		
1	919	1,050	919	1,050	1,531	0	0	1,050	868	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-835	823	0	-919	-1,050	-1,531	-1,205	
2	1,050	1,531	2,581	1,050	1,205	0	0	1,531	1,151	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-868	842	0	-1,050	-1,531	-1,205	
3	1,531	2,581	4,112	1,531	896	0	0	1,205	823	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-823	775	0	-1,531	-2,581	-1,205	
4	2,581	4,112	6,662	4,112	896	0	0	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-556	516	0	-2,581	-4,112	-1,205	
5	4,112	6,662	10,774	4,112	896	0	0	4,112	4,742	2,677	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-1,173	1,173	0	-4,112	-6,662	-1,205	
6	6,662	10,774	17,426	6,662	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-6,662	-10,774	-1,205	
7	10,774	17,426	28,199	10,774	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-10,774	-17,426	-1,205	
8	17,426	28,199	45,625	17,426	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-17,426	-28,199	-1,205	
9	28,199	45,625	73,824	28,199	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-28,199	-45,625	-1,205	
10	45,625	73,824	120,449	45,625	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-45,625	-73,824	-1,205	
11	73,824	120,449	194,253	73,824	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-73,824	-120,449	-1,205	
12	120,449	194,253	314,696	120,449	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-120,449	-194,253	-1,205	
13	194,253	314,696	508,950	194,253	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-194,253	-314,696	-1,205	
14	314,696	508,950	823,646	314,696	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-314,696	-508,950	-1,205	
15	508,950	823,646	1332,596	508,950	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-508,950	-823,646	-1,205	
16	823,646	1332,596	2156,242	823,646	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-823,646	-1332,596	-1,205	
17	1332,596	2156,242	3489,838	1332,596	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-1332,596	-2156,242	-1,205	
18	2156,242	3489,838	5646,080	2156,242	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-2156,242	-3489,838	-1,205	
19	3489,838	5646,080	8735,918	3489,838	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-3489,838	-5646,080	-1,205	
20	5646,080	8735,918	12381,998	5646,080	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-5646,080	-8735,918	-1,205	
21	8735,918	12381,998	20717,916	8735,918	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-8735,918	-12381,998	-1,205	
22	12381,998	20717,916	33109,914	12381,998	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-12381,998	-20717,916	-1,205	
23	20717,916	33109,914	53837,830	20717,916	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-20717,916	-33109,914	-1,205	
24	33109,914	53837,830	86957,744	33109,914	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-33109,914	-53837,830	-1,205	
25	53837,830	86957,744	130835,574	53837,830	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-53837,830	-86957,744	-1,205	
26	86957,744	130835,574	217813,318	86957,744	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-86957,744	-130835,574	-1,205	
27	130835,574	217813,318	348648,892	130835,574	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-130835,574	-217813,318	-1,205	
28	217813,318	348648,892	557462,210	217813,318	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-217813,318	-348648,892	-1,205	
29	348648,892	557462,210	806111,102	348648,892	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-348648,892	-557462,210	-1,205	
30	557462,210	806111,102	115357,322	557462,210	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-557462,210	-806111,102	-1,205	
31	806111,102	115357,322	195968,424	806111,102	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-806111,102	-115357,322	-1,205	
32	115357,322	195968,424	311325,746	115357,322	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-115357,322	-195968,424	-1,205	
33	195968,424	311325,746	507334,170	195968,424	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-195968,424	-311325,746	-1,205	
34	311325,746	507334,170	818669,914	311325,746	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-311325,746	-507334,170	-1,205	
35	507334,170	818669,914	122706,084	507334,170	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-507334,170	-818669,914	-1,205	
36	818669,914	122706,084	194472,998	818669,914	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-818669,914	-122706,084	-1,205	
37	122706,084	194472,998	317179,082	122706,084	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-122706,084	-194472,998	-1,205	
38	194472,998	317179,082	531651,074	194472,998	896	56	56	896	556	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-2,078	2,078	0	-194472,998	-317179,082	-1,205	
39	317																														

Table H.4.5 (4) Cost Benefit Stream of Alternative Plan of Case 2 in Kelani River Basin

River:	Kelani	Short
Case:	2	

Year	Cost						Benefit						(Unit: Million Rs.)
	Short Term	Construction Cost	Long Term	Total	Short Term	Long Term	Total	Flood Control	Power Generation	Long Term	Total	Grand Total	NPV
1	919	0	0	919	0	0	0	919	0	0	0	0	-835
2	1,050	1,050	1,050	3,150	0	0	0	868	0	0	0	0	-868
3	1,531	1,531	1,531	4,592	0	0	0	1,531	0	0	0	0	-1,531
4	1,205	1,205	1,205	3,616	0	0	0	1,205	0	0	0	0	-1,205
5	896	896	896	2,692	0	0	0	896	0	0	0	0	-896
6	0	0	0	0	56	56	56	0	0	0	0	0	0
7	0	0	0	0	56	56	56	32	2,078	0	0	0	0
8	0	0	0	0	56	56	56	29	2,078	0	0	0	0
9	0	0	0	0	56	56	56	26	2,078	0	0	0	0
10	0	0	0	0	56	56	56	24	2,078	0	0	0	0
11	0	0	0	0	56	56	56	22	2,078	0	0	0	0
12	0	0	0	0	56	56	56	20	2,078	0	0	0	0
13	0	0	0	0	56	56	56	18	2,078	0	0	0	0
14	0	0	0	0	56	56	56	16	2,078	0	0	0	0
15	0	0	0	0	56	56	56	15	2,078	0	0	0	0
16	0	0	0	0	56	56	56	13	2,078	0	0	0	0
17	0	0	0	0	56	56	56	12	2,078	0	0	0	0
18	0	0	0	0	56	56	56	11	2,078	0	0	0	0
19	0	0	0	0	56	56	56	10	2,078	0	0	0	0
20	0	0	0	0	56	56	56	9	2,078	0	0	0	0
21	0	0	0	0	56	56	56	8	2,078	0	0	0	0
22	0	0	0	0	56	56	56	7	2,078	0	0	0	0
23	0	0	0	0	56	56	56	6	2,078	0	0	0	0
24	0	0	0	0	56	56	56	6	2,078	0	0	0	0
25	0	0	0	0	56	56	56	5	2,078	0	0	0	0
26	0	0	0	0	56	56	56	5	2,078	0	0	0	0
27	0	0	0	0	56	56	56	4	2,078	0	0	0	0
28	0	0	0	0	56	56	56	4	2,078	0	0	0	0
29	0	0	0	0	56	56	56	4	2,078	0	0	0	0
30	0	0	0	0	56	56	56	3	2,078	0	0	0	0
31	0	0	0	0	56	56	56	3	2,078	0	0	0	0
32	0	0	0	0	56	56	56	3	2,078	0	0	0	0
33	0	0	0	0	56	56	56	2	2,078	0	0	0	0
34	0	0	0	0	56	56	56	2	2,078	0	0	0	0
35	0	0	0	0	56	56	56	2	2,078	0	0	0	0
36	0	0	0	0	56	56	56	2	2,078	0	0	0	0
37	0	0	0	0	56	56	56	2	2,078	0	0	0	0
38	0	0	0	0	56	56	56	1	2,078	0	0	0	0
39	0	0	0	0	56	56	56	1	2,078	0	0	0	0
40	0	0	0	0	56	56	56	1	2,078	0	0	0	0
41	0	0	0	0	56	56	56	1	2,078	0	0	0	0
42	0	0	0	0	56	56	56	1	2,078	0	0	0	0
43	0	0	0	0	56	56	56	1	2,078	0	0	0	0
44	0	0	0	0	56	56	56	1	2,078	0	0	0	0
45	0	0	0	0	56	56	56	1	2,078	0	0	0	0
46	0	0	0	0	56	56	56	1	2,078	0	0	0	0
47	0	0	0	0	56	56	56	1	2,078	0	0	0	0
48	0	0	0	0	56	56	56	1	2,078	0	0	0	0
49	0	0	0	0	56	56	56	0	2,078	0	0	0	0
50	0	0	0	0	56	56	56	0	2,078	0	0	0	0
	5,601	0	0	8,121	4,576							93,496	12,724
												3,190	3,148

IRR	23.07%
B-C	8.14%
BIC	2.78

Table H.4.5 (5) Cost Benefit Stream of Alternative Plan of Case 3 in Kelani River Basin

River:	Kelani	Overall
Case:	3	

Year	Construction Cost			Cost			Benefit			B-C			EIRR Verification		
	Short Term	Long Term	Total	Short Term	Long Term	Total	Grand	NPV	Short Term	Long Term	Total	NPV	(NPV)		
1	1,162	1,162	1,046,474	0	1,046	951	0	0	0	0	0	0	-951	-1,046	
2	1,162	1,162	0	1,162	0	0	0	0	0	0	0	0	-960	-1,162	
3	1,588	1,588	0	1,588	0	0	0	0	0	0	0	0	-960	-1,598	
4	1,230	1,230	0	1,230	0	0	0	0	0	0	0	0	-940	-1,230	
5	869	869	0	869	0	0	0	0	0	0	0	0	-840	-869	
6	1,986	1,986	59	1,986	59	1,055	1,160	2,078	0	0	0	0	1,173	23	
7	1,855	1,855	59	1,855	59	1,914	982	2,078	0	0	0	0	84	164	
8	1,545	1,545	59	1,545	59	1,604	748	2,078	0	0	0	0	969	473	
9	1,191	1,191	59	1,191	59	1,251	530	2,078	0	0	0	0	351	827	
10	752	752	59	752	59	812	313	2,078	0	0	0	0	488	1,266	
11	817	817	59	817	59	876	307	2,078	0	0	0	0	421	1,202	
12	888	888	59	965	965	947	302	2,078	0	0	0	0	357	1,131	
13	965	965	59	1,051	1,051	1,025	297	2,078	0	0	0	0	308	1,053	
14	1,051	1,051	59	1,145	1,145	1,110	292	2,078	0	0	0	0	255	968	
15	1,145	1,145	0	122	122	1,204	288	2,078	0	0	0	0	230	873	
16	17	0	59	181	181	39	0	3,586	3,586	3,586	3,586	3,586	17	3,405	
17	59	122	181	36	0	3,586	0	3,586	0	0	0	0	295	3,405	
18	0	59	122	181	33	0	3,586	0	0	0	0	0	255	3,405	
19	59	122	181	30	0	3,586	0	3,586	0	0	0	0	220	3,405	
20	0	59	122	181	27	0	3,586	0	0	0	0	0	190	3,405	
21	59	122	181	24	0	3,586	0	3,586	0	0	0	0	164	3,405	
22	59	122	181	22	0	3,586	0	3,586	0	0	0	0	142	3,405	
23	0	59	122	181	20	0	3,586	0	0	0	0	0	122	3,405	
24	59	122	181	18	0	3,586	0	3,586	0	0	0	0	106	3,405	
25	59	122	181	17	0	3,586	0	3,586	0	0	0	0	91	3,405	
26	59	122	181	15	0	3,586	0	3,586	0	0	0	0	79	3,405	
27	59	122	181	14	0	3,586	0	3,586	0	0	0	0	68	3,405	
28	59	122	181	13	0	3,586	0	3,586	0	0	0	0	59	3,405	
29	59	122	181	11	0	3,586	0	3,586	0	0	0	0	51	3,405	
30	59	122	181	10	0	3,586	0	3,586	0	0	0	0	44	3,405	
31	59	122	181	9	0	3,586	0	3,586	0	0	0	0	38	3,405	
32	59	122	181	8	0	3,586	0	3,586	0	0	0	0	33	3,405	
33	59	122	181	7	0	3,586	0	3,586	0	0	0	0	28	3,405	
34	59	122	181	6	0	3,586	0	3,586	0	0	0	0	24	3,405	
35	59	122	181	5	0	3,586	0	3,586	0	0	0	0	21	3,405	
36	59	122	181	4	0	3,586	0	3,586	0	0	0	0	18	3,405	
37	59	122	181	3	0	3,586	0	3,586	0	0	0	0	16	3,405	
38	59	122	181	2	0	3,586	0	3,586	0	0	0	0	14	3,405	
39	59	122	181	1	0	3,586	0	3,586	0	0	0	0	12	3,405	
40	59	122	181	0	0	3,586	0	3,586	0	0	0	0	10	3,405	
41	59	122	181	42	0	3,586	0	3,586	0	0	0	0	9	3,405	
42	59	122	181	43	0	3,586	0	3,586	0	0	0	0	8	3,405	
43	59	122	181	44	0	3,586	0	3,586	0	0	0	0	6	3,405	
44	59	122	181	45	0	3,586	0	3,586	0	0	0	0	6	3,405	
45	59	122	181	46	0	3,586	0	3,586	0	0	0	0	4	3,405	
46	59	122	181	47	0	3,586	0	3,586	0	0	0	0	3	3,405	
47	59	122	181	48	0	3,586	0	3,586	0	0	0	0	3	3,405	
48	59	122	181	49	0	3,586	0	3,586	0	0	0	0	2	3,405	
49	59	122	181	50	0	3,586	0	3,586	0	0	0	0	0	3,405	
50	5,906	12,207	18,113	25,043	10,131	0	0	0	0	0	0	0	7,340	-0.07	15.82%

EIRR	15.82%
BC	6,075
BC	1,601

Table H.4.5 (6) Cost Benefit Stream of Alternative Plan of Case 3 in Kelani River Basin

River:	Kelani	Short
Case:		3

Year	Construction Cost			Cost			Benefit			(Unit: Million Rs.)		
	Short Term		Long Term	Total	O&M		Total	Power Generation		Grand Total	NPV	B-C (NPV)
	Total	Short Term	Long Term	Total	Grand	NPV	Total	Short Term	Long Term	Total	-951	-951
1	1,046	1,162	1,162	0	1,046	951	0	0	0	0	0	-1,046
2	1,162	1,598	1,598	0	1,162	960	0	0	0	0	0	-1,162
3	1,598	1,230	1,230	0	1,598	1,201	0	0	0	0	0	-1,598
4	1,230	869	869	0	1,230	840	0	0	0	0	0	-1,230
5	869	0	869	0	869	540	0	0	0	0	0	-869
6	0	59	59	59	59	33	2,078	0	2,078	1,173	1,139	2,019
7	0	59	59	59	59	30	2,078	0	2,078	1,066	1,036	2,019
8	0	59	59	59	59	28	2,078	0	2,078	969	942	2,019
9	0	59	59	59	59	25	2,078	0	2,078	881	856	2,019
10	0	59	59	59	59	23	2,078	0	2,078	801	773	2,019
11	0	59	59	59	59	21	2,078	0	2,078	728	708	2,019
12	0	59	59	59	59	19	2,078	0	2,078	662	643	2,019
13	0	59	59	59	59	17	2,078	0	2,078	602	585	2,019
14	0	59	59	59	59	16	2,078	0	2,078	547	532	2,019
15	0	59	59	59	59	14	2,078	0	2,078	497	483	2,019
16	0	59	59	59	59	13	2,078	0	2,078	452	439	2,019
17	0	59	59	59	59	12	2,078	0	2,078	411	399	2,019
18	0	59	59	59	59	11	2,078	0	2,078	374	363	2,019
19	0	59	59	59	59	10	2,078	0	2,078	340	330	2,019
20	0	59	59	59	59	9	2,078	0	2,078	309	300	2,019
21	0	59	59	59	59	8	2,078	0	2,078	281	273	2,019
22	0	59	59	59	59	7	2,078	0	2,078	255	248	2,019
23	0	59	59	59	59	7	2,078	0	2,078	232	225	2,019
24	0	59	59	59	59	6	2,078	0	2,078	211	205	2,019
25	0	59	59	59	59	5	2,078	0	2,078	192	186	2,019
26	0	59	59	59	59	5	2,078	0	2,078	174	169	2,019
27	0	59	59	59	59	4	2,078	0	2,078	158	154	2,019
28	0	59	59	59	59	4	2,078	0	2,078	144	140	2,019
29	0	59	59	59	59	4	2,078	0	2,078	127	121	2,019
30	0	59	59	59	59	3	2,078	0	2,078	119	116	2,019
31	0	59	59	59	59	3	2,078	0	2,078	108	105	2,019
32	0	59	59	59	59	3	2,078	0	2,078	98	96	2,019
33	0	59	59	59	59	3	2,078	0	2,078	89	87	2,019
34	0	59	59	59	59	2	2,078	0	2,078	81	79	2,019
35	0	59	59	59	59	2	2,078	0	2,078	74	72	2,019
36	0	59	59	59	59	2	2,078	0	2,078	67	65	2,019
37	0	59	59	59	59	2	2,078	0	2,078	61	59	2,019
38	0	59	59	59	59	2	2,078	0	2,078	56	54	2,019
39	0	59	59	59	59	1	2,078	0	2,078	50	49	2,019
40	0	59	59	59	59	1	2,078	0	2,078	46	45	2,019
41	0	59	59	59	59	1	2,078	0	2,078	42	41	2,019
42	0	59	59	59	59	1	2,078	0	2,078	37	37	2,019
43	0	59	59	59	59	1	2,078	0	2,078	34	34	2,019
44	0	59	59	59	59	1	2,078	0	2,078	31	30	2,019
45	0	59	59	59	59	1	2,078	0	2,078	29	28	2,019
46	0	59	59	59	59	1	2,078	0	2,078	26	25	2,019
47	0	59	59	59	59	1	2,078	0	2,078	24	23	2,019
48	0	59	59	59	59	1	2,078	0	2,078	21	21	2,019
49	0	59	59	59	59	1	2,078	0	2,078	19	19	2,019
50	0	59	59	59	59	1	2,078	0	2,078	17	0	2,019
	5,906	0			8,564	4,854				93,496	12,724	3,494
	5,906	0								858	781	-0.97
										880	555	2,62

IRR	22.00%
B-C	7.870
B/C	2.62

Table H.4.5 (7) Cost Benefit Stream of Alternative Plan of Case 1 in Kalu River Basin

River:	Kalu	Overall
Case:	1	
Year	Construction Costs	
	Short Term	Long Term
1	1,121	
2	1,133	
3	3,122	
4	2,436	
5	1,848	
6		349
7		187
8		938
9		1,024
10		1,118
11		1,222
12		1,337
13		1,464
14		1,166
15		314
16		
17		
18		
19		
20		
21		
22		
23		
24		
25		
26		
27		
28		
29		
30		
31		
32		
33		
34		
35		
36		
37		
38		
39		
40		
41		
42		
43		
44		
45		
46		
47		
48		
49		
50		
	9,660	9,119
		18,779

EIRR	9.46%
B-C	-533
B/C	0.95

Table H.4.5 (8) Cost Benefit Stream of Alternative Plan of Case 1 in Kalu River Basin

River:	Kalu	Short
Case:	1	

Year	Construction Cost			Cost O&M			Benefit Power Generation			Benefit Flood Control			(Unit: Million Rs.)		
	Short Term		Long Term	Total		Grand Total	NPV		Short Term		Long Term	Total		B-C (NPV)	
	Short Term	Long Term	Total	Short Term	Long Term	Total	Short Term	Long Term	Total	Short Term	Long Term	Total	Grand Total	Total	-1,019
1	1,121	1,121	0	1,121	1,019	0	0	0	0	0	0	0	0	0	-936
2	1,133	1,133	0	1,133	936	0	0	0	0	0	0	0	0	0	-1,133
3	3,122	3,122	0	3,122	2,346	0	0	0	0	0	0	0	0	0	-3,122
4	2,436	2,436	0	2,436	1,664	0	0	0	0	0	0	0	0	0	-2,436
5	1,848	1,848	0	1,848	1,147	0	0	0	0	0	0	0	0	0	-1,848
6	97	97	55	1,601	0	1,601	0	0	0	0	0	0	0	0	0
7	97	97	50	1,601	0	1,601	0	0	0	0	0	0	0	0	0
8	97	97	45	1,601	0	1,601	0	0	0	0	0	0	0	0	0
9	97	97	41	1,601	0	1,601	0	0	0	0	0	0	0	0	0
10	97	97	37	1,601	0	1,601	0	0	0	0	0	0	0	0	0
11	97	97	34	1,601	0	1,601	0	0	0	0	0	0	0	0	0
12	97	97	31	1,601	0	1,601	0	0	0	0	0	0	0	0	0
13	97	97	28	1,601	0	1,601	0	0	0	0	0	0	0	0	0
14	97	97	25	1,601	0	1,601	0	0	0	0	0	0	0	0	0
15	97	97	23	1,601	0	1,601	0	0	0	0	0	0	0	0	0
16	97	97	21	1,601	0	1,601	0	0	0	0	0	0	0	0	0
17	97	97	19	1,601	0	1,601	0	0	0	0	0	0	0	0	0
18	97	97	17	1,601	0	1,601	0	0	0	0	0	0	0	0	0
19	97	97	16	1,601	0	1,601	0	0	0	0	0	0	0	0	0
20	97	97	14	1,601	0	1,601	0	0	0	0	0	0	0	0	0
21	97	97	13	1,601	0	1,601	0	0	0	0	0	0	0	0	0
22	97	97	12	1,601	0	1,601	0	0	0	0	0	0	0	0	0
23	97	97	11	1,601	0	1,601	0	0	0	0	0	0	0	0	0
24	97	97	10	1,601	0	1,601	0	0	0	0	0	0	0	0	0
25	97	97	9	1,601	0	1,601	0	0	0	0	0	0	0	0	0
26	97	97	8	1,601	0	1,601	0	0	0	0	0	0	0	0	0
27	97	97	7	1,601	0	1,601	0	0	0	0	0	0	0	0	0
28	97	97	7	1,601	0	1,601	0	0	0	0	0	0	0	0	0
29	97	97	6	1,601	0	1,601	0	0	0	0	0	0	0	0	0
30	97	97	5	1,601	0	1,601	0	0	0	0	0	0	0	0	0
31	97	97	5	1,601	0	1,601	0	0	0	0	0	0	0	0	0
32	97	97	4	1,601	0	1,601	0	0	0	0	0	0	0	0	0
33	97	97	4	1,601	0	1,601	0	0	0	0	0	0	0	0	0
34	97	97	4	1,601	0	1,601	0	0	0	0	0	0	0	0	0
35	97	97	3	1,601	0	1,601	0	0	0	0	0	0	0	0	0
36	97	97	3	1,601	0	1,601	0	0	0	0	0	0	0	0	0
37	97	97	3	1,601	0	1,601	0	0	0	0	0	0	0	0	0
38	97	97	3	1,601	0	1,601	0	0	0	0	0	0	0	0	0
39	97	97	2	1,601	0	1,601	0	0	0	0	0	0	0	0	0
40	97	97	2	1,601	0	1,601	0	0	0	0	0	0	0	0	0
41	97	97	2	1,601	0	1,601	0	0	0	0	0	0	0	0	0
42	97	97	2	1,601	0	1,601	0	0	0	0	0	0	0	0	0
43	97	97	2	1,601	0	1,601	0	0	0	0	0	0	0	0	0
44	97	97	1	1,601	0	1,601	0	0	0	0	0	0	0	0	0
45	97	97	1	1,601	0	1,601	0	0	0	0	0	0	0	0	0
46	97	97	1	1,601	0	1,601	0	0	0	0	0	0	0	0	0
47	97	97	1	1,601	0	1,601	0	0	0	0	0	0	0	0	0
48	97	97	1	1,601	0	1,601	0	0	0	0	0	0	0	0	0
49	97	97	1	1,601	0	1,601	0	0	0	0	0	0	0	0	0
50	97	97	1	1,601	0	1,601	0	0	0	0	0	0	0	0	0
				14,007	7,704									7,051	9,806
				9,660	0									7,051	9,806
				9,660	0									7,051	9,806

EIRR	12.53%
B-C	2,102
B/C	1.22

Table H.4.5 (9) Cost Benefit Stream of Alternative Plan of Case 2 in Kalu River Basin

River:	Kalu	Overall
Case:	2	

Year	Construction Cost			Cost			Benefit			(Unit: Million Rs.)				
	Short Term		Long Term	Short Term		Long Term	Grand Total		Flood Control	Power Generation		Grand Total	NPV	B-C (NPV)
	Total	Total	Total	Total	Total	Total	NPV	Short Term	Long Term	Total	Short Term	Long Term	Short Term	Long Term
1	1,291	1,291	0	1,291	0	0	1,291	0	1,74	0	0	0	0	-1,291
2	1,723	1,723	0	1,723	0	0	1,723	0	1,424	0	0	0	0	-1,723
3	3,255	3,255	0	3,255	0	0	3,255	0	2,446	0	0	0	0	-3,255
4	2,641	2,641	0	2,641	0	0	2,641	0	2,641	0	0	0	0	-2,641
5	2,127	2,127	0	2,127	0	0	2,127	0	1,321	0	0	0	0	-2,127
6	1,287	1,287	110	110	110	0	1,397	789	1,399	0	0	0	0	2
7	736	736	110	110	110	0	846	434	1,399	0	0	0	0	553
8	2,451	2,451	110	110	110	0	2,561	1,195	1,399	0	0	0	0	-1,162
9	2,604	2,604	110	110	110	0	2,714	1,151	1,399	0	0	0	0	-1,315
10	2,765	2,765	110	110	110	0	2,875	1,109	1,399	0	0	0	0	-1,476
11	3,021	3,021	110	110	110	0	3,131	1,098	1,399	0	0	0	0	-1,732
12	3,303	3,303	110	110	110	0	3,413	1,088	1,399	0	0	0	0	-2,014
13	3,613	3,613	110	110	110	0	3,723	1,079	1,399	0	0	0	0	-2,324
14	2,934	2,934	110	110	110	0	3,044	802	1,399	0	0	0	0	-1,645
15	963	963	110	110	110	0	1,073	257	1,399	0	0	0	0	326
16	0	110	237	347	76	0	1,962	1,962	1,962	427	351	185	1,043	1,614
17	0	110	237	347	69	0	1,962	1,962	1,962	388	319	177	1,002	1,614
18	0	110	237	347	62	0	1,962	1,962	1,962	353	290	171	964	1,614
19	0	110	237	347	57	0	1,962	1,962	1,962	321	264	164	926	1,614
20	0	110	237	347	52	0	1,962	1,962	1,962	232	240	158	890	1,614
21	0	110	237	347	47	0	1,962	1,962	1,962	265	218	151	856	1,614
22	0	110	237	347	43	0	1,962	1,962	1,962	241	198	146	823	1,614
23	0	110	237	347	39	0	1,962	1,962	1,962	219	180	140	791	1,614
24	0	110	237	347	35	0	1,962	1,962	1,962	199	164	135	760	1,614
25	0	110	237	347	32	0	1,962	1,962	1,962	181	149	129	731	1,614
26	0	110	237	347	29	0	1,962	1,962	1,962	165	135	124	703	1,614
27	0	110	237	347	26	0	1,962	1,962	1,962	150	123	120	675	1,614
28	0	110	237	347	24	0	1,962	1,962	1,962	136	112	115	649	1,614
29	0	110	237	347	22	0	1,962	1,962	1,962	124	102	110	624	1,614
30	0	110	237	347	20	0	1,962	1,962	1,962	112	93	106	600	1,614
31	0	110	237	347	18	0	1,962	1,962	1,962	102	84	97	577	1,614
32	0	110	237	347	16	0	1,962	1,962	1,962	93	76	98	554	1,614
33	0	110	237	347	15	0	1,962	1,962	1,962	84	70	94	533	1,614
34	0	110	237	347	14	0	1,962	1,962	1,962	77	63	91	512	1,614
35	0	110	237	347	12	0	1,962	1,962	1,962	70	57	87	492	1,614
36	0	110	237	347	11	0	1,962	1,962	1,962	63	52	84	473	1,614
37	0	110	237	347	10	0	1,962	1,962	1,962	58	47	81	455	1,614
38	0	110	237	347	9	0	1,962	1,962	1,962	52	43	77	437	1,614
39	0	110	237	347	8	0	1,962	1,962	1,962	48	39	74	420	1,614
40	0	110	237	347	8	0	1,962	1,962	1,962	43	36	56	319	1,614
41	0	110	237	347	7	0	1,962	1,962	1,962	39	32	69	389	1,614
42	0	110	237	347	6	0	1,962	1,962	1,962	36	29	66	374	1,614
43	0	110	237	347	6	0	1,962	1,962	1,962	33	27	64	359	1,614
44	0	110	237	347	5	0	1,962	1,962	1,962	30	24	61	345	1,614
45	0	110	237	347	5	0	1,962	1,962	1,962	27	22	59	332	1,614
46	0	110	237	347	4	0	1,962	1,962	1,962	24	20	56	319	1,614
47	0	110	237	347	4	0	1,962	1,962	1,962	22	18	54	307	1,614
48	0	110	237	347	3	0	1,962	1,962	1,962	20	17	52	295	1,614
49	0	110	237	347	3	0	1,962	1,962	1,962	18	15	50	283	1,614
50	0	110	237	347	3	0	1,962	1,962	1,962	17	14	48	272	1,614
	11,037	23,676	0	47,967	17,969					0	0	0	29,474	0.08
		34,714								0	0	0	29,474	0.08

4.03%

EIRR	4.03%
B-C	-8.102
B/C	0.55

Table H.4.5 (10) Cost Benefit Stream of Alternative Plan of Case 2 in Kalu River Basin

River:	Kalu	Short	Cost:	Case:	2
Year	Construction Cost	O&M	Cost	Benefit	(Unit: Million Rs.)
	Short Term Long Term	Total	Short Term Long Term	Total	Grand Total
1	1,291		0	1,291	1,291
2	1,723	1,723	0	1,723	1,723
3	3,255	3,255	0	3,255	3,255
4	2,641	2,641	0	2,641	2,641
5	2,127	2,127	0	2,127	2,127
6	0	0	110	110	110
7	0	0	110	110	110
8	0	0	110	110	110
9	0	0	110	110	110
10	0	0	110	110	110
11	0	0	110	110	110
12	0	0	110	110	110
13	0	0	110	110	110
14	0	0	110	110	110
15	0	0	110	110	110
16	0	0	110	110	110
17	0	0	110	110	110
18	0	0	110	110	110
19	0	0	110	110	110
20	0	0	110	110	110
21	0	0	110	110	110
22	0	0	110	110	110
23	0	0	110	110	110
24	0	0	110	110	110
25	0	0	110	110	110
26	0	0	110	110	110
27	0	0	110	110	110
28	0	0	110	110	110
29	0	0	110	110	110
30	0	0	110	110	110
31	0	0	110	110	110
32	0	0	110	110	110
33	0	0	110	110	110
34	0	0	110	110	110
35	0	0	110	110	110
36	0	0	110	110	110
37	0	0	110	110	110
38	0	0	110	110	110
39	0	0	110	110	110
40	0	0	110	110	110
41	0	0	110	110	110
42	0	0	110	110	110
43	0	0	110	110	110
44	0	0	110	110	110
45	0	0	110	110	110
46	0	0	110	110	110
47	0	0	110	110	110
48	0	0	110	110	110
49	0	0	110	110	110
50	0	0	110	110	110
	11,037	0	16,004	8,844	
	11,037	0	16,004	8,844	

EIRR	9.70%
B-C	-274
B/C	0.97

Year	Cost	Benefit
	Net Present Value	Net Present Value
1	1,177	0
2	1,432	-1,723
3	55	-3,255
4	667	-2,446
5	568	-2,641
6	44	-1,804
7	33	-1,321
8	28	0
9	349	0
10	25	0
11	16	555
12	40	1,289
13	36	0
14	411	0
15	373	0
16	342	0
17	21	0
18	241	0
19	19	0
20	220	0
21	17	0
22	200	0
23	16	0
24	183	0
25	166	0
26	152	0
27	138	0
28	110	0
29	106	0
30	81	0
31	77	0
32	67	0
33	6	0
34	46	0
35	3	0
36	38	0
37	34	0
38	3	0
39	38	0
40	2	0
41	2	0
42	2	0
43	2	0
44	2	0
45	2	0
46	2	0
47	1	0
48	1	0
49	1	0
50	1	0
	8,943	9.70%
	8,943	-274
	8,943	0.97

Table H.4.5 (11) Cost Benefit Stream of Alternative Plan of Case 3 in Kalu River Basin

River:	Kalu	Overall
Case:	3	

Year	Construction Cost			Cost O&M			Benefit Power Generation			B-C (NPV)			Cost Net Present Value	Benefit Net Present Value	
	Short Term		Long Term	Short Term		Long Term	Short Term		Long Term	Short Term		Long Term			
	Grand Total	NPV	Grand Total	NPV	Grand Total	NPV	Grand Total	NPV	Grand Total	NPV	Grand Total	NPV			
1	1,168	1,062	0	0	0	0	0	0	0	0	0	0	-1,062	-1,168	
2	1,427	1,427	0	0	0	0	0	0	0	0	0	0	-1,179	-1,427	
3	3,121	3,121	0	0	0	0	0	0	0	0	0	0	-2,345	-3,121	
4	2,501	2,501	0	0	0	0	0	0	0	0	0	0	-2,501	-2,501	
5	1,980	1,980	0	0	0	0	0	0	0	0	0	0	-1,980	-1,980	
6	2,332	2,332	102	102	1,434	1,374	1,399	0	1,399	0	790	-584	-1,035	-1,035	
7	1,699	1,699	102	102	1,801	924	1,399	0	1,399	0	718	-206	1,172	-402	
8	4,735	4,735	102	102	4,837	2,256	1,399	0	1,399	0	653	-1,604	3,951	-438	
9	4,671	4,671	102	102	4,773	2,024	1,399	0	1,399	0	593	-1,431	3,612	-3374	
10	4,549	4,549	102	102	4,651	1,793	1,399	0	1,399	0	539	-1,254	3,854	-3,252	
11	4,988	4,988	102	102	5,090	1,784	1,399	0	1,399	0	490	-1,294	3,854	-3,691	
12	5,471	5,471	102	102	5,573	1,776	1,399	0	1,399	0	446	-1,330	4,115	-4,174	
13	6,003	6,003	102	102	6,105	1,768	1,399	0	1,399	0	405	-1,363	4,395	-4,706	
14	6,588	6,588	102	102	6,690	1,762	1,399	0	1,399	0	368	-1,393	4,686	-5,291	
15	7,231	7,231	102	102	7,333	1,755	1,399	0	1,399	0	335	-1,420	5,019	-5,934	
16	0	0	102	483	585	127	0	2,858	2,858	622	495	390	958	2,273	2,273
17	0	0	102	483	585	116	0	2,858	2,858	565	450	380	1,859	2,273	2,273
18	0	0	102	483	585	105	0	2,858	2,858	514	409	371	1,813	2,273	2,273
19	0	0	102	483	585	96	0	2,858	2,858	467	372	362	1,788	2,273	2,273
20	0	0	102	483	585	87	0	2,858	2,858	425	338	353	1,724	2,273	2,273
21	0	0	102	483	585	79	0	2,858	2,858	386	307	344	1,680	2,273	2,273
22	0	0	102	483	585	72	0	2,858	2,858	351	279	335	1,639	2,273	2,273
23	0	0	102	483	585	65	0	2,858	2,858	319	254	327	1,598	2,273	2,273
24	0	0	102	483	585	59	0	2,858	2,858	290	231	319	1,558	2,273	2,273
25	0	0	102	483	585	54	0	2,858	2,858	264	210	311	1,519	2,273	2,273
26	0	0	102	483	585	49	0	2,858	2,858	240	191	303	1,481	2,273	2,273
27	0	0	102	483	585	45	0	2,858	2,858	218	173	295	1,444	2,273	2,273
28	0	0	102	483	585	41	0	2,858	2,858	198	158	288	1,408	2,273	2,273
29	0	0	102	483	585	37	0	2,858	2,858	180	143	281	1,373	2,273	2,273
30	0	0	102	483	585	34	0	2,858	2,858	164	130	274	1,338	2,273	2,273
31	0	0	102	483	585	30	0	2,858	2,858	149	108	267	1,305	2,273	2,273
32	0	0	102	483	585	28	0	2,858	2,858	135	98	260	1,272	2,273	2,273
33	0	0	102	483	585	25	0	2,858	2,858	123	89	254	1,241	2,273	2,273
34	0	0	102	483	585	23	0	2,858	2,858	112	89	247	1,210	2,273	2,273
35	0	0	102	483	585	21	0	2,858	2,858	102	81	241	1,180	2,273	2,273
36	0	0	102	483	585	19	0	2,858	2,858	92	74	235	1,150	2,273	2,273
37	0	0	102	483	585	17	0	2,858	2,858	84	67	229	1,121	2,273	2,273
38	0	0	102	483	585	16	0	2,858	2,858	76	61	224	1,093	2,273	2,273
39	0	0	102	483	585	14	0	2,858	2,858	69	55	218	1,066	2,273	2,273
40	0	0	102	483	585	13	0	2,858	2,858	63	50	213	1,039	2,273	2,273
41	0	0	102	483	585	12	0	2,858	2,858	57	46	207	1,014	2,273	2,273
42	0	0	102	483	585	11	0	2,858	2,858	52	42	198	988	2,273	2,273
43	0	0	102	483	585	10	0	2,858	2,858	47	38	197	964	2,273	2,273
44	0	0	102	483	585	9	0	2,858	2,858	43	34	192	939	2,273	2,273
45	0	0	102	483	585	8	0	2,858	2,858	39	31	187	916	2,273	2,273
46	0	0	102	483	585	7	0	2,858	2,858	36	28	183	893	2,273	2,273
47	0	0	102	483	585	6	0	2,858	2,858	32	26	178	871	2,273	2,273
48	0	0	102	483	585	5	0	2,858	2,858	27	21	169	849	2,273	2,273
49	0	0	102	483	585	5	0	2,858	2,858	24	19	165	828	2,273	2,273
50	0	0	102	483	585	5	0	2,858	2,858	0	0	165	807	2,273	2,273
	10,197	48,267			79,946	26,091					114,013	11,936	-14,154	2,56%	
												55,613	55,613	0.00	2,56%

58,464

EIRR	2.56%
B-C	-14,154
B/C	0.46

Table H.4.5 (12) Cost Benefit Stream of Alternative Plan of Case 3 in Kalu River Basin

River:	Kalu	Short
Case:	3	

Year	Construction Cost			Cost			Benefit			(Unit: Million Rs.)			
	Short Term		Long Term	Short Term		Long Term	Short Term		Long Term	Power Generation		Grand Total	NPV
	Grand Total	NPV	Short Term	Flood Control	Long Term	Total	Short Term	Long Term	Total	Short Term	Long Term	Total	B-C (NPV)
1	1,168	1,168					0	1,168	0	0	0	0	-1,062
2	1,427	1,427					0	1,427	0	0	0	0	-1,179
3	3,121	3,121					0	3,121	0	0	0	0	-2,345
4	2,501	2,501					0	2,501	0	0	0	0	-2,708
5	1,980	1,980					0	1,980	0	0	0	0	-1,229
6	0	0	102	102	58	1,399	0	0	0	0	0	0	0
7	0	0	102	102	52	1,399	0	0	0	0	0	0	0
8	0	0	102	102	48	1,399	0	0	0	0	0	0	0
9	0	0	102	102	43	1,399	0	0	0	0	0	0	0
10	0	0	102	102	39	1,399	0	0	0	0	0	0	0
11	0	0	102	102	36	1,399	0	0	0	0	0	0	0
12	0	0	102	102	32	1,399	0	0	0	0	0	0	0
13	0	0	102	102	30	1,399	0	0	0	0	0	0	0
14	0	0	102	102	27	1,399	0	0	0	0	0	0	0
15	0	0	102	102	24	1,399	0	0	0	0	0	0	0
16	0	0	102	102	22	1,399	0	0	0	0	0	0	0
17	0	0	102	102	20	1,399	0	0	0	0	0	0	0
18	0	0	102	102	18	1,399	0	0	0	0	0	0	0
19	0	0	102	102	17	1,399	0	0	0	0	0	0	0
20	0	0	102	102	15	1,399	0	0	0	0	0	0	0
21	0	0	102	102	14	1,399	0	0	0	0	0	0	0
22	0	0	102	102	13	1,399	0	0	0	0	0	0	0
23	0	0	102	102	11	1,399	0	0	0	0	0	0	0
24	0	0	102	102	10	1,399	0	0	0	0	0	0	0
25	0	0	102	102	9	1,399	0	0	0	0	0	0	0
26	0	0	102	102	8	1,399	0	0	0	0	0	0	0
27	0	0	102	102	7	1,399	0	0	0	0	0	0	0
28	0	0	102	102	6	1,399	0	0	0	0	0	0	0
29	0	0	102	102	5	1,399	0	0	0	0	0	0	0
30	0	0	102	102	5	1,399	0	0	0	0	0	0	0
31	0	0	102	102	5	1,399	0	0	0	0	0	0	0
32	0	0	102	102	5	1,399	0	0	0	0	0	0	0
33	0	0	102	102	4	1,399	0	0	0	0	0	0	0
34	0	0	102	102	4	1,399	0	0	0	0	0	0	0
35	0	0	102	102	4	1,399	0	0	0	0	0	0	0
36	0	0	102	102	3	1,399	0	0	0	0	0	0	0
37	0	0	102	102	3	1,399	0	0	0	0	0	0	0
38	0	0	102	102	3	1,399	0	0	0	0	0	0	0
39	0	0	102	102	2	1,399	0	0	0	0	0	0	0
40	0	0	102	102	2	1,399	0	0	0	0	0	0	0
41	0	0	102	102	2	1,399	0	0	0	0	0	0	0
42	0	0	102	102	2	1,399	0	0	0	0	0	0	0
43	0	0	102	102	2	1,399	0	0	0	0	0	0	0
44	0	0	102	102	1	1,399	0	0	0	0	0	0	0
45	0	0	102	102	1	1,399	0	0	0	0	0	0	0
46	0	0	102	102	1	1,399	0	0	0	0	0	0	0
47	0	0	102	102	1	1,399	0	0	0	0	0	0	0
48	0	0	102	102	1	1,399	0	0	0	0	0	0	0
49	0	0	102	102	1	1,399	0	0	0	0	0	0	0
50	0	0	102	102	0	1,399	0	0	0	0	0	0	0
	10,197	0				14,786	8,148						

10,197

EIRR	10.50%
B-C	421
B/C	1.05

Table H.4.5 (13) Cost Benefit Stream of Alternative Plan of Case 4 in Kalu River Basin

River:	Kalu	Overall
Case:	4	

Year	Construction Cost			Cost O&M			Benefit Power Generation			Benefit Flood Control			B-C (NPV)			EIRR Verification
	Short Term		Long Term	Short Term		Long Term	Short Term		Long Term	Short Term		Long Term	Grand Total		NPV	
	Cost	Benefit	Net Present Value	Cost	Benefit	Net Present Value	Cost	Benefit	Net Present Value	Cost	Benefit	Net Present Value	Cost	Benefit	Net Present Value	
1	326	0	0	326	296	0	0	0	0	0	0	0	-296	314	0	-326
2	605	605	0	605	500	0	0	0	0	0	0	0	-500	561	0	-605
3	829	829	0	829	828	0	0	0	0	0	0	0	-829	740	0	-829
4	722	722	0	722	493	0	0	0	0	0	0	0	-722	620	0	-722
5	645	645	0	645	400	0	0	0	0	0	0	0	-645	533	0	-645
6	2,119	2,119	31	2,150	1,214	0	1,017	0	0	0	0	0	-1,133	1,712	809	-1,133
7	1,583	1,583	31	1,614	828	0	1,017	0	0	0	0	0	-597	1,237	779	-597
8	4,328	4,328	31	4,359	2,034	0	1,017	0	0	0	0	0	-3,342	3,216	750	-3,342
9	4,228	4,228	31	4,259	1,806	0	1,017	0	0	0	0	0	-3,242	3,025	722	-3,242
10	4,096	4,096	31	4,097	1,580	0	1,017	0	0	0	0	0	-3,080	2,801	695	-3,080
11	4,462	4,462	31	4,493	1,575	0	1,017	0	0	0	0	0	-3,476	2,867	669	-3,476
12	4,898	4,898	31	4,929	1,571	0	1,017	0	0	0	0	0	-3,912	3,123	644	-3,912
13	5,377	5,377	31	5,408	1,567	0	1,017	0	0	0	0	0	-4,391	3,299	620	-4,391
14	5,904	5,904	31	5,935	1,563	0	1,017	0	0	0	0	0	-4,918	3,485	597	-4,918
15	6,483	6,483	31	6,514	1,559	0	1,017	0	0	0	0	0	-5,497	3,682	575	-5,497
16	0	0	31	434	466	101	0	2,744	0	0	0	0	2,278	253	1,493	2,278
17	0	0	31	434	466	92	0	2,744	0	0	0	0	2,278	244	1,437	2,278
18	0	0	31	434	466	84	0	2,744	0	0	0	0	2,278	235	1,384	2,278
19	0	0	31	434	466	76	0	2,744	0	0	0	0	2,278	226	1,332	2,278
20	0	0	31	434	466	69	0	2,744	0	0	0	0	2,278	218	1,282	2,278
21	0	0	31	434	466	63	0	2,744	0	0	0	0	2,278	210	1,235	2,278
22	0	0	31	434	466	57	0	2,744	0	0	0	0	2,278	202	1,188	2,278
23	0	0	31	434	466	52	0	2,744	0	0	0	0	2,278	194	1,144	2,278
24	0	0	31	434	466	46	0	2,744	0	0	0	0	2,278	187	1,101	2,278
25	0	0	31	434	466	40	0	2,744	0	0	0	0	2,278	180	1,060	2,278
26	0	0	31	434	466	39	0	2,744	0	0	0	0	2,278	191	1,021	2,278
27	0	0	31	434	466	36	0	2,744	0	0	0	0	2,278	174	983	2,278
28	0	0	31	434	466	32	0	2,744	0	0	0	0	2,278	158	946	2,278
29	0	0	31	434	466	29	0	2,744	0	0	0	0	2,278	144	911	2,278
30	0	0	31	434	466	27	0	2,744	0	0	0	0	2,278	131	877	2,278
31	0	0	31	434	466	24	0	2,744	0	0	0	0	2,278	119	844	2,278
32	0	0	31	434	466	22	0	2,744	0	0	0	0	2,278	108	813	2,278
33	0	0	31	434	466	20	0	2,744	0	0	0	0	2,278	133	782	2,278
34	0	0	31	434	466	18	0	2,744	0	0	0	0	2,278	107	89	128
35	0	0	31	434	466	17	0	2,744	0	0	0	0	2,278	98	81	123
36	0	0	31	434	466	15	0	2,744	0	0	0	0	2,278	89	74	118
37	0	0	31	434	466	14	0	2,744	0	0	0	0	2,278	81	67	114
38	0	0	31	434	466	12	0	2,744	0	0	0	0	2,278	73	61	110
39	0	0	31	434	466	11	0	2,744	0	0	0	0	2,278	55	106	123
40	0	0	31	434	466	10	0	2,744	0	0	0	0	2,278	50	102	99
41	0	0	31	434	466	9	0	2,744	0	0	0	0	2,278	46	98	57
42	0	0	31	434	466	8	0	2,744	0	0	0	0	2,278	42	94	556
43	0	0	31	434	466	7	0	2,744	0	0	0	0	2,278	38	91	535
44	0	0	31	434	466	6	0	2,744	0	0	0	0	2,278	34	87	515
45	0	0	31	434	466	6	0	2,744	0	0	0	0	2,278	31	84	496
46	0	0	31	434	466	5	0	2,744	0	0	0	0	2,278	28	81	477
47	0	0	31	434	466	4	0	2,744	0	0	0	0	2,278	26	78	459
48	0	0	31	434	466	4	0	2,744	0	0	0	0	2,278	21	75	442
49	0	0	31	434	466	4	0	2,744	0	0	0	0	2,278	20	72	426
50	0	0	31	434	466	4	0	2,744	0	0	0	0	2,278	19	70	410
	3,127	43,448			63,189	18,684							36,303	36,303	0.02	3,88%
	46,575															

EIRR	3.88%
B-C	-8.471
B/C	0.55

Table H.4.5 (14) Cost Benefit Stream of Alternative Plan of Case 4 in Kalu River Basin

River:	Kalu	Short
Case:	4	

Year	Construction Cost			Cost			Benefit			(Unit: Million Rs.)							
	Short Term	Long Term	Total	Short Term	Long Term	Total	Grand Total	NPV	Flood Control	Short Term	Long Term	Total	Power Generation	Grand Total	NPV	B-C (NPV)	
1	326	326	652	326	296	605	326	0	0	0	0	0	0	0	-296	0	
2	605	605	829	605	500	829	605	0	0	0	0	0	0	0	-605	0	
3	829	829	722	829	623	722	829	0	0	0	0	0	0	0	-829	0	
4	722	722	645	722	493	645	722	0	0	0	0	0	0	0	-722	0	
5	645	645	0	645	400	645	645	0	0	0	0	0	0	0	-645	0	
6	0	0	31	31	18	31	31	1,017	0	1,017	0	0	0	0	0	314	
7	0	0	31	31	18	31	31	1,017	0	1,017	0	0	0	0	0	258	
8	0	0	31	31	15	31	31	1,017	0	1,017	0	0	0	0	0	212	
9	0	0	31	31	13	31	31	1,017	0	1,017	0	0	0	0	0	174	
10	0	0	31	31	12	31	31	1,017	0	1,017	0	0	0	0	0	143	
11	0	0	31	31	11	31	31	1,017	0	1,017	0	0	0	0	0	986	
12	0	0	31	31	10	31	31	1,017	0	1,017	0	0	0	0	0	118	
13	0	0	31	31	9	31	31	1,017	0	1,017	0	0	0	0	0	97	
14	0	0	31	31	8	31	31	1,017	0	1,017	0	0	0	0	0	80	
15	0	0	31	31	7	31	31	1,017	0	1,017	0	0	0	0	0	65	
16	0	0	31	31	6	31	31	1,017	0	1,017	0	0	0	0	0	54	
17	0	0	31	31	5	31	31	1,017	0	1,017	0	0	0	0	0	44	
18	0	0	31	31	4	31	31	1,017	0	1,017	0	0	0	0	0	36	
19	0	0	31	31	3	31	31	1,017	0	1,017	0	0	0	0	0	30	
20	0	0	31	31	2	31	31	1,017	0	1,017	0	0	0	0	0	25	
21	0	0	31	31	1	31	31	1,017	0	1,017	0	0	0	0	0	20	
22	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	17	
23	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	14	
24	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	11	
25	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	9	
26	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	8	
27	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	6	
28	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	5	
29	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	4	
30	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	3	
31	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	3	
32	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	2	
33	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	2	
34	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	1	
35	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	1	
36	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	0	
37	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	0	
38	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	0	
39	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	0	
40	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	0	
41	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	0	
42	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	0	
43	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	0	
44	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	0	
45	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	0	
46	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	0	
47	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	0	
48	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	0	
49	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	0	
50	0	0	31	31	0	31	31	1,017	0	1,017	0	0	0	0	0	0	
	3,127	0		4,534	2,504										45,756	6,227	3,723
															1,764	0.00	21,64%
																	EIRR
																	B-C
																	2,49

EIRR	21.64%
B-C	3,723
B/C	2.49

Table H.4.5 (15) Cost Benefit Stream of Alternative Plan of Case 1 in Gin River Basin

Year	Construction Cost			Cost O&M			Flood Control			Benefit Power Generation			Grand Total		NPV	B-C (NPV)	(Unit: Million Rs.)
	Short Term	Long Term	Total	Short Term	Long Term	Total	Short Term	Long Term	Total	Short Term	Long Term	Total	Total	Total			
1	437	437	0	437	397	0	0	0	0	0	0	0	0	0	-397	-397	
2	778	778	0	778	643	0	0	0	0	0	0	0	0	0	-643	-778	
3	2,794	2,794	0	2,794	2,089	0	0	0	0	0	0	0	0	0	-2,089	-2,794	
4	2,938	2,938	0	2,938	2,007	0	0	0	0	0	0	0	0	0	-2,007	-2,938	
5	3,170	3,170	0	3,170	1,968	0	0	0	0	0	0	0	0	0	-1,968	-3,170	
6	4,976	4,976	101	5,077	2,866	220	0	220	0	220	0	220	0	0	216	4,938	
7	6,112	6,112	101	6,213	3,188	220	0	220	0	220	0	220	0	0	216	5,944	
8	5,415	5,415	101	5,516	2,573	220	0	220	0	220	0	220	0	0	215	5,297	
9	4,520	4,520	101	4,621	1,960	220	0	220	0	220	0	220	0	0	215	4,401	
10	3,392	3,392	101	3,493	1,347	220	0	220	0	220	0	220	0	0	214	3,274	
11	3,716	3,716	101	3,817	1,338	220	0	220	0	220	0	220	0	0	214	3,597	
12	4,072	4,072	101	4,173	1,330	220	0	220	0	220	0	220	0	0	213	3,953	
13	3,162	3,162	101	3,263	945	220	0	220	0	220	0	220	0	0	213	3,044	
14	601	601	101	702	185	220	0	220	0	220	0	220	0	0	212	483	
15	646	646	101	747	179	220	0	220	0	220	0	220	0	0	212	527	
16	0	101	366	467	102	0	1,851	1,851	0	1,851	403	301	0	449	1,779		
17	0	101	366	467	92	0	1,851	1,851	0	1,851	366	274	0	448	1,775		
18	0	101	366	467	84	0	1,851	1,851	0	1,851	333	249	0	447	1,770		
19	0	101	366	467	76	0	1,851	1,851	0	1,851	303	226	0	446	1,766		
20	0	101	366	467	69	0	1,851	1,851	0	1,851	275	206	0	445	1,762		
21	0	101	366	467	63	0	1,851	1,851	0	1,851	250	187	0	444	1,757		
22	0	101	366	467	57	0	1,851	1,851	0	1,851	227	170	0	443	1,753		
23	0	101	366	467	52	0	1,851	1,851	0	1,851	207	154	0	442	1,749		
24	0	101	366	467	47	0	1,851	1,851	0	1,851	188	140	0	440	1,745		
25	0	101	366	467	43	0	1,851	1,851	0	1,851	171	128	0	439	1,740		
26	0	101	366	467	39	0	1,851	1,851	0	1,851	155	116	0	438	1,736		
27	0	101	366	467	36	0	1,851	1,851	0	1,851	141	106	0	437	1,732		
28	0	101	366	467	32	0	1,851	1,851	0	1,851	128	96	0	436	1,727		
29	0	101	366	467	29	0	1,851	1,851	0	1,851	117	87	0	435	1,723		
30	0	101	366	467	27	0	1,851	1,851	0	1,851	106	79	0	434	1,719		
31	0	101	366	467	24	0	1,851	1,851	0	1,851	96	72	0	433	1,715		
32	0	101	366	467	22	0	1,851	1,851	0	1,851	88	66	0	432	1,711		
33	0	101	366	467	20	0	1,851	1,851	0	1,851	80	60	0	431	1,706		
34	0	101	366	467	18	0	1,851	1,851	0	1,851	72	54	0	430	1,702		
35	0	101	366	467	17	0	1,851	1,851	0	1,851	67	54	0	429	1,698		
36	0	101	366	467	15	0	1,851	1,851	0	1,851	66	49	0	429	1,698		
37	0	101	366	467	14	0	1,851	1,851	0	1,851	65	45	0	428	1,694		
38	0	101	366	467	12	0	1,851	1,851	0	1,851	54	41	0	427	1,690		
39	0	101	366	467	11	0	1,851	1,851	0	1,851	49	37	0	426	1,686		
40	0	101	366	467	10	0	1,851	1,851	0	1,851	45	34	0	425	1,681		
41	0	101	366	467	9	0	1,851	1,851	0	1,851	41	31	0	424	1,677		
42	0	101	366	467	8	0	1,851	1,851	0	1,851	37	28	0	422	1,673		
43	0	101	366	467	7	0	1,851	1,851	0	1,851	34	25	0	421	1,669		
44	0	101	366	467	6	0	1,851	1,851	0	1,851	31	23	0	420	1,665		
45	0	101	366	467	5	0	1,851	1,851	0	1,851	28	21	0	419	1,661		
46	0	101	366	467	4	0	1,851	1,851	0	1,851	25	19	0	418	1,657		
47	0	101	366	467	3	0	1,851	1,851	0	1,851	23	17	0	417	1,653		
48	0	101	366	467	2	0	1,851	1,851	0	1,851	21	16	0	416	1,649		
49	0	101	366	467	1	0	1,851	1,851	0	1,851	17	14	0	415	1,645		
50	0	101	366	467	0	0	1,851	1,851	0	1,851	13	12	0	413	1,637		
	10,116	36,612			64,094	24,103					66,966	5,110	-18,993	61,880	0,14	0,25%	

EIRR	0.25%
BC	-18,993
BC	0.2%

Table H.4.5 (16) Cost Benefit Stream of Alternative Plan of Case 1 in Gin River Basin

River:	GIN	Short
Case:	1	

Year	Construction Cost			Cost O&M			Benefit			(Unit: Million Rs.)		
	Short Term	Long Term	Total	Short Term	Long Term	Total	Flood Control	Short Term	Long Term	Total	Power Generation	Total
1	437	397	834	0	0	0	0	0	0	0	-397	-437
2	778	778	1556	0	0	0	0	0	0	0	-643	-778
3	2,794	2,794	5,588	0	0	0	0	0	0	0	-2,099	-2,794
4	2,938	2,938	5,876	0	0	0	0	0	0	0	-2,007	-2,938
5	3,170	3,170	6,340	0	0	0	0	0	0	0	-1,968	-3,170
6				101	101	202	0	0	0	0	124	117
7				101	101	202	0	0	0	0	61	260
8				101	101	202	0	0	0	0	113	102
9				101	101	202	0	0	0	0	55	267
10				101	101	202	0	0	0	0	50	273
11				101	101	202	0	0	0	0	46	129
12				101	101	202	0	0	0	0	280	118
13				101	101	202	0	0	0	0	132	287
14				101	101	202	0	0	0	0	136	118
15				101	101	202	0	0	0	0	309	118
16				101	101	202	0	0	0	0	142	118
17				101	101	202	0	0	0	0	317	118
18				101	101	202	0	0	0	0	324	118
19				101	101	202	0	0	0	0	332	118
20				101	101	202	0	0	0	0	153	118
21				101	101	202	0	0	0	0	341	118
22				101	101	202	0	0	0	0	161	349
23				101	101	202	0	0	0	0	165	118
24				101	101	202	0	0	0	0	169	367
25				101	101	202	0	0	0	0	173	118
26				101	101	202	0	0	0	0	376	118
27				101	101	202	0	0	0	0	177	385
28				101	101	202	0	0	0	0	182	118
29				101	101	202	0	0	0	0	394	118
30				101	101	202	0	0	0	0	404	118
31				101	101	202	0	0	0	0	191	414
32				101	101	202	0	0	0	0	196	424
33				101	101	202	0	0	0	0	200	435
34				101	101	202	0	0	0	0	205	118
35				101	101	202	0	0	0	0	446	118
36				101	101	202	0	0	0	0	457	118
37				101	101	202	0	0	0	0	186	468
38				101	101	202	0	0	0	0	221	118
39				101	101	202	0	0	0	0	226	491
40				101	101	202	0	0	0	0	232	118
41				101	101	202	0	0	0	0	238	516
42				101	101	202	0	0	0	0	244	118
43				101	101	202	0	0	0	0	250	542
44				101	101	202	0	0	0	0	256	118
45				101	101	202	0	0	0	0	262	569
46				101	101	202	0	0	0	0	269	583
47				101	101	202	0	0	0	0	275	118
48				101	101	202	0	0	0	0	282	612
49				101	101	202	0	0	0	0	289	627
50				101	101	202	0	0	0	0	296	643
											304	659
											311	675
											319	692
											327	709
											335	726
											343	744
											20,573	0.88
												-2.41%
												-6.389
												0.17

Table H.4.5 (17) Cost Benefit Stream of Alternative Plan of Case 2 in Gin River Basin

Year	Construction Cost			Cost O&M			Benefit			(Unit: Million Rs.)							
	Short Term	Long Term	Total	Short Term	Long Term	Total	Grand Total	Flood Control	Short Term	Long Term	Total	Grand Total	NPV	B-C (NPV)	Net Present Value	Benefit	
1	363	628	991	363	628	991	363	330	0	0	0	0	0	-330	0	EIRR Verification	
2	628	3,202	3,830	628	3,202	3,830	628	628	0	0	0	0	0	-519	584	-363	
3	3,202	3,375	6,577	0	0	0	3,202	2,406	0	0	0	0	0	-2,406	2,869	-628	
4	3,375	3,654	6,739	0	0	0	3,375	2,305	0	0	0	0	0	-2,305	2,915	-3,202	
5	3,654	3,124	10,863	112	112	226	3,654	2,269	0	0	0	0	0	-2,269	3,043	-3,375	
6	3,124	4,863	8,000	112	112	2,553	112	1,827	1,319	0	0	0	0	0	-1,917	2,915	-3,654
7	4,863	4,559	9,422	112	112	4,975	112	2,553	1,319	0	0	0	0	0	-1,917	3,043	0
8	4,559	2,712	7,271	112	112	4,671	112	2,179	1,319	0	0	0	0	0	-1,917	3,195	0
9	2,712	2,029	4,741	112	112	2,824	112	1,198	1,319	0	0	0	0	0	-1,917	3,269	0
10	2,029	378	2,407	112	112	2,141	112	826	1,319	0	0	0	0	0	-1,917	3,343	0
11	378	490	868	112	112	490	172	1,319	0	0	0	0	0	-1,917	3,417	0	
12	490	404	894	112	112	516	164	1,319	0	0	0	0	0	-1,917	3,491	0	
13	433	433	866	112	112	545	158	1,319	0	0	0	0	0	-1,917	3,565	0	
14	464	464	930	112	112	576	152	1,319	0	0	0	0	0	-1,917	3,639	0	
15	499	499	998	112	112	611	146	1,319	0	0	0	0	0	-1,917	3,713	0	
16	0	112	195	307	307	67	1,726	1,726	0	0	0	0	0	-1,917	3,787	0	
17	0	112	195	307	307	61	0	1,726	1,726	0	0	0	0	0	-1,917	3,861	0
18	0	112	195	307	307	55	0	1,726	1,726	0	0	0	0	0	-1,917	3,935	0
19	0	112	195	307	307	50	0	1,726	1,726	0	0	0	0	0	-1,917	4,009	0
20	0	112	195	307	307	46	0	1,726	1,726	0	0	0	0	0	-1,917	4,083	0
21	0	112	195	307	307	41	0	1,726	1,726	0	0	0	0	0	-1,917	4,157	0
22	0	112	195	307	307	38	0	1,726	1,726	0	0	0	0	0	-1,917	4,231	0
23	0	112	195	307	307	34	0	1,726	1,726	0	0	0	0	0	-1,917	4,305	0
24	0	112	195	307	307	31	0	1,726	1,726	0	0	0	0	0	-1,917	4,379	0
25	0	112	195	307	307	28	0	1,726	1,726	0	0	0	0	0	-1,917	4,453	0
26	0	112	195	307	307	26	0	1,726	1,726	0	0	0	0	0	-1,917	4,527	0
27	0	112	195	307	307	23	0	1,726	1,726	0	0	0	0	0	-1,917	4,601	0
28	0	112	195	307	307	21	0	1,726	1,726	0	0	0	0	0	-1,917	4,675	0
29	0	112	195	307	307	19	0	1,726	1,726	0	0	0	0	0	-1,917	4,749	0
30	0	112	195	307	307	18	0	1,726	1,726	0	0	0	0	0	-1,917	4,823	0
31	0	112	195	307	307	16	0	1,726	1,726	0	0	0	0	0	-1,917	4,897	0
32	0	112	195	307	307	15	0	1,726	1,726	0	0	0	0	0	-1,917	4,971	0
33	0	112	195	307	307	13	0	1,726	1,726	0	0	0	0	0	-1,917	5,045	0
34	0	112	195	307	307	12	0	1,726	1,726	0	0	0	0	0	-1,917	5,119	0
35	0	112	195	307	307	11	0	1,726	1,726	0	0	0	0	0	-1,917	5,193	0
36	0	112	195	307	307	10	0	1,726	1,726	0	0	0	0	0	-1,917	5,267	0
37	0	112	195	307	307	9	0	1,726	1,726	0	0	0	0	0	-1,917	5,341	0
38	0	112	195	307	307	8	0	1,726	1,726	0	0	0	0	0	-1,917	5,415	0
39	0	112	195	307	307	7	0	1,726	1,726	0	0	0	0	0	-1,917	5,489	0
40	0	112	195	307	307	6	0	1,726	1,726	0	0	0	0	0	-1,917	5,563	0
41	0	112	195	307	307	5	0	1,726	1,726	0	0	0	0	0	-1,917	5,637	0
42	0	112	195	307	307	4	0	1,726	1,726	0	0	0	0	0	-1,917	5,711	0
43	0	112	195	307	307	3	0	1,726	1,726	0	0	0	0	0	-1,917	5,785	0
44	0	112	195	307	307	2	0	1,726	1,726	0	0	0	0	0	-1,917	5,859	0
45	0	112	195	307	307	1	0	1,726	1,726	0	0	0	0	0	-1,917	5,933	0
46	0	112	195	307	307	0	0	1,726	1,726	0	0	0	0	0	-1,917	5,907	0
47	0	112	195	307	307	3	0	1,726	1,726	0	0	0	0	0	-1,917	5,981	0
48	0	112	195	307	307	2	0	1,726	1,726	0	0	0	0	0	-1,917	5,955	0
49	0	112	195	307	307	1	0	1,726	1,726	0	0	0	0	0	-1,917	5,929	0
50	0	112	195	307	307	0	0	1,726	1,726	0	0	0	0	0	-1,917	5,903	0
	11,222	19,465	30,687		42,550	17,912								28,340	28,340	3,73%	
														28,340	28,340	-8,894	
																EIRR	
																B-C	
																B/C	
																0.50	

Table H.4.5 (18) Cost Benefit Stream of Alternative Plan of Case 2 in Gin River Basin

River:	GIN	Short
Case:	2	

Year	Construction Cost			Cost			Benefit			(Unit: Million Rs.)			B-C (NPV)	
	Short Term	Long Term	Total	Short Term	Long Term	Total	Grand Total	NPV	Flood Control	Short Term	Long Term	Total	NPV	
1	363	628	991	363	628	991	363	330	0	0	0	0	0	-330
2	628	3,202	3,830	628	3,202	3,830	628	628	519	0	0	0	0	-519
3	3,202	3,375	6,577	3,202	3,375	6,577	3,202	2,406	0	0	0	0	0	-2,406
4	3,375	3,654	7,031	3,375	3,654	7,031	3,375	2,305	0	0	0	0	0	-2,305
5	3,654	0	3,654	3,654	0	3,654	3,654	2,269	0	0	0	0	0	-2,269
6	0	112	112	112	112	112	112	63	1,319	0	0	0	0	0
7	112	112	224	112	112	224	112	58	1,319	0	0	0	0	0
8	0	112	112	112	112	112	112	52	1,319	0	0	0	0	0
9	0	112	112	112	112	112	112	48	1,319	0	0	0	0	0
10	0	112	112	112	112	112	112	43	1,319	0	0	0	0	0
11	0	112	112	112	112	112	112	39	1,319	0	0	0	0	0
12	0	112	112	112	112	112	112	36	1,319	0	0	0	0	0
13	0	112	112	112	112	112	112	33	1,319	0	0	0	0	0
14	0	112	112	112	112	112	112	30	1,319	0	0	0	0	0
15	0	112	112	112	112	112	112	27	1,319	0	0	0	0	0
16	0	112	112	112	112	112	112	24	1,319	0	0	0	0	0
17	0	112	112	112	112	112	112	22	1,319	0	0	0	0	0
18	0	112	112	112	112	112	112	20	1,319	0	0	0	0	0
19	0	112	112	112	112	112	112	18	1,319	0	0	0	0	0
20	0	112	112	112	112	112	112	17	1,319	0	0	0	0	0
21	0	112	112	112	112	112	112	15	1,319	0	0	0	0	0
22	0	112	112	112	112	112	112	14	1,319	0	0	0	0	0
23	0	112	112	112	112	112	112	13	1,319	0	0	0	0	0
24	0	112	112	112	112	112	112	11	1,319	0	0	0	0	0
25	0	112	112	112	112	112	112	10	1,319	0	0	0	0	0
26	0	112	112	112	112	112	112	9	1,319	0	0	0	0	0
27	0	112	112	112	112	112	112	9	1,319	0	0	0	0	0
28	0	112	112	112	112	112	112	8	1,319	0	0	0	0	0
29	0	112	112	112	112	112	112	7	1,319	0	0	0	0	0
30	0	112	112	112	112	112	112	6	1,319	0	0	0	0	0
31	0	112	112	112	112	112	112	5	1,319	0	0	0	0	0
32	0	112	112	112	112	112	112	5	1,319	0	0	0	0	0
33	0	112	112	112	112	112	112	5	1,319	0	0	0	0	0
34	0	112	112	112	112	112	112	4	1,319	0	0	0	0	0
35	0	112	112	112	112	112	112	4	1,319	0	0	0	0	0
36	0	112	112	112	112	112	112	4	1,319	0	0	0	0	0
37	0	112	112	112	112	112	112	3	1,319	0	0	0	0	0
38	0	112	112	112	112	112	112	3	1,319	0	0	0	0	0
39	0	112	112	112	112	112	112	3	1,319	0	0	0	0	0
40	0	112	112	112	112	112	112	2	1,319	0	0	0	0	0
41	0	112	112	112	112	112	112	2	1,319	0	0	0	0	0
42	0	112	112	112	112	112	112	2	1,319	0	0	0	0	0
43	0	112	112	112	112	112	112	2	1,319	0	0	0	0	0
44	0	112	112	112	112	112	112	2	1,319	0	0	0	0	0
45	0	112	112	112	112	112	112	2	1,319	0	0	0	0	0
46	0	112	112	112	112	112	112	1	1,319	0	0	0	0	0
47	0	112	112	112	112	112	112	1	1,319	0	0	0	0	0
48	0	112	112	112	112	112	112	1	1,319	0	0	0	0	0
49	0	112	112	112	112	112	112	1	1,319	0	0	0	0	0
50	0	112	112	112	112	112	112	0	1,319	0	0	0	0	0
	11,222	0	11,222	0	16,272	8,516	16,272	0	0	59,355	8,078	59,355	8,713	8,713
													438	0.00
														9,47%
														9,47%
														438
														0.95

11,222

EIRR	9.47%
B-C	-438
B/C	0.95

Table H.4.5 (19) Cost Benefit Stream of Alternative Plan of Case 3 in Gin River Basin

River:	GIN	Overall
Case:	3	

Year	Cost						Benefit						(Unit: Million Rs.)	
	Construction Cost		O&M		Flood Control		Power Generation		Grand Total		NPV			
	Short Term	Long Term	Total	Short Term	Long Term	Total	Short Term	Long Term	Total	Short Term	Long Term	Total	NPV	B-C (NPV)
1	180	180	0	180	164	0	0	0	0	0	0	0	-164	-180
2	396	396	0	396	327	0	0	0	0	0	0	0	-327	-396
3	2,565	2,565	0	2,565	2,565	0	0	0	0	0	0	0	-2,565	-2,565
4	2,729	2,729	0	2,729	1,927	0	0	0	0	0	0	0	-1,927	-2,729
5	2,986	2,986	0	2,986	1,864	0	0	0	0	0	0	0	-1,864	-2,986
6	564	564	89	89	1,854	0	0	0	0	0	0	0	-1,854	-66
7	1,577	1,577	89	89	653	368	587	0	587	0	0	0	-554	-1,079
8	1,677	1,677	89	89	1,666	855	587	0	587	0	0	0	-550	-1,179
9	1,782	1,782	89	89	1,766	824	587	0	587	0	0	0	-545	-1,284
10	1,893	1,893	89	89	1,871	793	587	0	587	0	0	0	-538	-1,395
11	262	262	89	89	1,982	764	587	0	587	0	0	0	-532	-236
12	282	282	89	89	351	123	587	0	587	0	0	0	-526	-216
13	303	303	89	89	392	113	587	0	587	0	0	0	-520	-195
14	326	326	89	89	415	109	587	0	587	0	0	0	-513	-172
15	352	352	89	89	441	105	587	0	587	0	0	0	-506	-146
16	0	89	90	90	90	99	179	35	0	1,534	0	0	-295	-79
17	0	89	90	90	179	35	0	1,534	0	0	0	0	-268	-75
18	0	89	90	90	179	32	0	1,534	0	0	0	0	-244	-71
19	0	89	90	90	179	29	0	1,534	0	0	0	0	-222	-68
20	0	89	90	90	179	27	0	1,534	0	0	0	0	-228	-64
21	0	89	90	90	179	24	0	1,534	0	0	0	0	-207	-61
22	0	89	90	90	179	22	0	1,534	0	0	0	0	-167	-58
23	0	89	90	90	179	20	0	1,534	0	0	0	0	-151	-55
24	0	89	90	90	179	18	0	1,534	0	0	0	0	-151	-55
25	0	89	90	90	179	16	0	1,534	0	0	0	0	-142	-52
26	0	89	90	90	179	15	0	1,534	0	0	0	0	-125	-50
27	0	89	90	90	179	14	0	1,534	0	0	0	0	-114	-47
28	0	89	90	90	179	12	0	1,534	0	0	0	0	-103	-45
29	0	89	90	90	179	11	0	1,534	0	0	0	0	-94	-43
30	0	89	90	90	179	10	0	1,534	0	0	0	0	-97	-41
31	0	89	90	90	179	9	0	1,534	0	0	0	0	-88	-39
32	0	89	90	90	179	8	0	1,534	0	0	0	0	-80	-37
33	0	89	90	90	179	8	0	1,534	0	0	0	0	-73	-35
34	0	89	90	90	179	7	0	1,534	0	0	0	0	-66	-33
35	0	89	90	90	179	6	0	1,534	0	0	0	0	-53	-31
36	0	89	90	90	179	6	0	1,534	0	0	0	0	-55	-30
37	0	89	90	90	179	5	0	1,534	0	0	0	0	-45	-28
38	0	89	90	90	179	5	0	1,534	0	0	0	0	-41	-27
39	0	89	90	90	179	4	0	1,534	0	0	0	0	-37	-23
40	0	89	90	90	179	4	0	1,534	0	0	0	0	-34	-20
41	0	89	90	90	179	4	0	1,534	0	0	0	0	-31	-20
42	0	89	90	90	179	3	0	1,534	0	0	0	0	-27	-19
43	0	89	90	90	179	3	0	1,534	0	0	0	0	-25	-21
44	0	89	90	90	179	2	0	1,534	0	0	0	0	-20	-17
45	0	89	90	90	179	2	0	1,534	0	0	0	0	-19	-16
46	0	89	90	90	179	2	0	1,534	0	0	0	0	-18	-15
47	0	89	90	90	179	2	0	1,534	0	0	0	0	-17	-14
48	0	89	90	90	179	2	0	1,534	0	0	0	0	-15	-13
49	0	89	90	90	179	2	0	1,534	0	0	0	0	-14	-12
50	8,856	9,018	0	8,856	10,722	25,016	17,874	59,569	5,780	14,778	0.01	5,25%	14,778	14,778

EIRR	5.25%
B-C	-4,941
BC	0.54

Table H.4.5 (20) Cost Benefit Stream of Alternative Plan of Case 3 in Gin River Basin

Year	Cost			Benefit			(Unit: Million Rs.)
	Short Term	Long Term	Total	Short Term	Long Term	Total	
1	180	180	360	180	164	344	-164
2	396	396	792	396	327	723	-396
3	2,565	2,565	5,130	2,565	1,927	4,492	-2,565
4	2,729	2,729	5,458	2,729	0	2,729	-2,729
5	2,986	2,986	5,974	2,986	1,864	4,840	-2,986
6	0	0	0	0	0	0	0
7	89	89	178	89	50	139	0
8	89	89	178	89	45	134	0
9	89	89	178	89	41	133	0
10	89	89	178	89	38	131	0
11	89	89	178	89	34	127	0
12	89	89	178	89	31	124	0
13	89	89	178	89	28	121	0
14	89	89	178	89	26	119	0
15	89	89	178	89	23	116	0
16	89	89	178	89	21	114	0
17	89	89	178	89	19	112	0
18	89	89	178	89	18	111	0
19	89	89	178	89	16	109	0
20	89	89	178	89	14	107	0
21	89	89	178	89	13	106	0
22	89	89	178	89	12	105	0
23	89	89	178	89	11	104	0
24	89	89	178	89	10	103	0
25	89	89	178	89	9	102	0
26	89	89	178	89	8	101	0
27	89	89	178	89	7	100	0
28	89	89	178	89	6	99	0
29	89	89	178	89	6	98	0
30	89	89	178	89	5	97	0
31	89	89	178	89	5	96	0
32	89	89	178	89	4	95	0
33	89	89	178	89	4	94	0
34	89	89	178	89	3	93	0
35	89	89	178	89	3	92	0
36	89	89	178	89	3	91	0
37	89	89	178	89	3	90	0
38	89	89	178	89	2	89	0
39	89	89	178	89	2	88	0
40	89	89	178	89	2	87	0
41	89	89	178	89	2	86	0
42	89	89	178	89	2	85	0
43	89	89	178	89	1	84	0
44	89	89	178	89	1	83	0
45	89	89	178	89	1	82	0
46	89	89	178	89	1	81	0
47	89	89	178	89	1	80	0
48	89	89	178	89	1	79	0
49	89	89	178	89	1	78	0
50	89	89	178	89	1	77	0
							8,746
							8,746
							0
							0
							4,65%
							EIRR
							B-C
							B/C

River:	GIN	Overall Case:	4
--------	-----	---------------	---

Table H.4.5 (21) Cost Benefit Stream of Alternative Plan of Case 4 in Gin River Basin

Year	Construction Cost			Cost O&M			Flood Control			Benefit Power Generation			Net Present Value		Benefit	
	Short Term	Long Term	Total	Short Term	Long Term	Total	NPV	Short Term	Long Term	Total	Short Term	Long Term	Total	NPV		
1	282	282	282	0	282	0	256	0	0	0	0	0	0	-256	-282	
2	478	478	478	0	478	0	395	0	0	0	0	0	0	-395	-478	
3	3,059	3,059	3,059	0	3,059	0	2,298	0	0	0	0	0	0	-2,298	-3,059	
4	3,224	3,224	3,224	0	3,224	0	2,202	0	0	0	0	0	0	-2,202	-3,224	
5	3,493	3,493	3,493	0	3,493	0	2,169	0	0	0	0	0	0	-2,169	-3,493	
6	396	396	396	105	105	105	501	105	105	0	1,319	0	0	0	0	
7	950	950	950	105	105	105	542	105	105	0	1,319	0	0	0	0	
8	1,037	1,037	1,037	105	105	105	533	105	105	0	1,319	0	0	0	0	
9	1,134	1,134	1,134	105	105	105	526	105	105	0	1,319	0	0	0	0	
10	1,240	1,240	1,240	105	105	105	519	105	105	0	1,319	0	0	0	0	
11	261	261	261	105	105	105	386	128	128	0	1,319	0	0	0	0	
12	280	280	280	105	105	105	385	123	123	0	1,319	0	0	0	0	
13	301	301	301	105	105	105	406	118	118	0	1,319	0	0	0	0	
14	324	324	324	105	105	105	429	113	113	0	1,319	0	0	0	0	
15	350	350	350	105	105	105	455	109	109	0	1,319	0	0	0	0	
16	0	0	0	105	105	105	168	37	0	1,534	0	0	0	0	0	
17	63	63	63	168	168	168	33	0	0	1,534	0	0	0	0	0	
18	0	0	0	105	105	105	63	168	30	0	1,534	0	0	0	0	
19	0	0	0	105	105	105	63	168	25	0	1,534	0	0	0	0	
20	0	0	0	105	105	105	63	168	168	0	1,534	0	0	0	0	
21	0	0	0	105	105	105	63	168	23	0	1,534	0	0	0	0	
22	0	0	0	105	105	105	63	168	21	0	1,534	0	0	0	0	
23	0	0	0	105	105	105	63	168	19	0	1,534	0	0	0	0	
24	0	0	0	105	105	105	63	168	17	0	1,534	0	0	0	0	
25	0	0	0	105	105	105	63	168	16	0	1,534	0	0	0	0	
26	0	0	0	105	105	105	63	168	14	0	1,534	0	0	0	0	
27	0	0	0	105	105	105	63	168	13	0	1,534	0	0	0	0	
28	0	0	0	105	105	105	63	168	12	0	1,534	0	0	0	0	
29	0	0	0	105	105	105	63	168	11	0	1,534	0	0	0	0	
30	0	0	0	105	105	105	63	168	10	0	1,534	0	0	0	0	
31	0	0	0	105	105	105	63	168	9	0	1,534	0	0	0	0	
32	0	0	0	105	105	105	63	168	8	0	1,534	0	0	0	0	
33	0	0	0	105	105	105	63	168	7	0	1,534	0	0	0	0	
34	0	0	0	105	105	105	63	168	6	0	1,534	0	0	0	0	
35	0	0	0	105	105	105	63	168	5	0	1,534	0	0	0	0	
36	0	0	0	105	105	105	63	168	5	0	1,534	0	0	0	0	
37	0	0	0	105	105	105	63	168	4	0	1,534	0	0	0	0	
38	0	0	0	105	105	105	63	168	4	0	1,534	0	0	0	0	
39	0	0	0	105	105	105	63	168	2	0	1,534	0	0	0	0	
40	0	0	0	105	105	105	63	168	2	0	1,534	0	0	0	0	
41	0	0	0	105	105	105	63	168	3	0	1,534	0	0	0	0	
42	0	0	0	105	105	105	63	168	3	0	1,534	0	0	0	0	
43	0	0	0	105	105	105	63	168	2	0	1,534	0	0	0	0	
44	0	0	0	105	105	105	63	168	2	0	1,534	0	0	0	0	
45	0	0	0	105	105	105	63	168	1	0	1,534	0	0	0	0	
46	0	0	0	105	105	105	63	168	1	0	1,534	0	0	0	0	
47	0	0	0	105	105	105	63	168	1	0	1,534	0	0	0	0	
48	0	0	0	105	105	105	63	168	2	0	1,534	0	0	0	0	
49	0	0	0	105	105	105	63	168	2	0	1,534	0	0	0	0	
50	0	0	0	105	105	105	63	168	1	0	1,534	0	0	0	0	
	10,536	6,273	16,809	23,746	10,701									66,894	8,575	2,127
																12,212
																0.00
																7,72%
																2,127
																0.80

Table H.4.5 (22) Cost Benefit Stream of Alternative Plan of Case 4 in Gin River Basin

River:	GIN	Short
Case:	4	

Year	Cost						Benefit						(Unit: Million Rs.)
	Construction Cost		O&M		NPV		Flood Control		Power Generation		Grand Total		
	Short Term	Long Term	Total	Short Term	Long Term	Total	Short Term	Long Term	Total	Short Term	Long Term	Total	
1	282	282	564	0	0	282	256	0	0	0	0	0	-282
2	478	478	956	0	0	478	395	0	0	0	0	0	-478
3	3,059	3,059	6,118	0	0	3,059	2,288	0	0	0	0	0	-3,059
4	3,224	3,224	6,448	0	0	3,224	2,202	0	0	0	0	0	-3,224
5	3,493	3,493	6,986	0	0	3,493	2,169	0	0	0	0	0	-3,493
6	0	105	105	59	1,319	0	1,319	0	0	0	0	0	0
7	0	105	105	54	1,319	0	1,319	0	0	0	0	0	0
8	0	105	105	49	1,319	0	1,319	0	0	0	0	0	0
9	0	105	105	45	1,319	0	1,319	0	0	0	0	0	0
10	0	105	105	41	1,319	0	1,319	0	0	0	0	0	0
11	0	105	105	37	1,319	0	1,319	0	0	0	0	0	0
12	0	105	105	34	1,319	0	1,319	0	0	0	0	0	0
13	0	105	105	31	1,319	0	1,319	0	0	0	0	0	0
14	0	105	105	28	1,319	0	1,319	0	0	0	0	0	0
15	0	105	105	25	1,319	0	1,319	0	0	0	0	0	0
16	0	105	105	23	1,319	0	1,319	0	0	0	0	0	0
17	0	105	105	21	1,319	0	1,319	0	0	0	0	0	0
18	0	105	105	19	1,319	0	1,319	0	0	0	0	0	0
19	0	105	105	17	1,319	0	1,319	0	0	0	0	0	0
20	0	105	105	16	1,319	0	1,319	0	0	0	0	0	0
21	0	105	105	14	1,319	0	1,319	0	0	0	0	0	0
22	0	105	105	13	1,319	0	1,319	0	0	0	0	0	0
23	0	105	105	12	1,319	0	1,319	0	0	0	0	0	0
24	0	105	105	11	1,319	0	1,319	0	0	0	0	0	0
25	0	105	105	10	1,319	0	1,319	0	0	0	0	0	0
26	0	105	105	9	1,319	0	1,319	0	0	0	0	0	0
27	0	105	105	8	1,319	0	1,319	0	0	0	0	0	0
28	0	105	105	7	1,319	0	1,319	0	0	0	0	0	0
29	0	105	105	6	1,319	0	1,319	0	0	0	0	0	0
30	0	105	105	5	1,319	0	1,319	0	0	0	0	0	0
31	0	105	105	5	1,319	0	1,319	0	0	0	0	0	0
32	0	105	105	5	1,319	0	1,319	0	0	0	0	0	0
33	0	105	105	5	1,319	0	1,319	0	0	0	0	0	0
34	0	105	105	4	1,319	0	1,319	0	0	0	0	0	0
35	0	105	105	4	1,319	0	1,319	0	0	0	0	0	0
36	0	105	105	3	1,319	0	1,319	0	0	0	0	0	0
37	0	105	105	3	1,319	0	1,319	0	0	0	0	0	0
38	0	105	105	3	1,319	0	1,319	0	0	0	0	0	0
39	0	105	105	3	1,319	0	1,319	0	0	0	0	0	0
40	0	105	105	2	1,319	0	1,319	0	0	0	0	0	0
41	0	105	105	2	1,319	0	1,319	0	0	0	0	0	0
42	0	105	105	2	1,319	0	1,319	0	0	0	0	0	0
43	0	105	105	2	1,319	0	1,319	0	0	0	0	0	0
44	0	105	105	2	1,319	0	1,319	0	0	0	0	0	0
45	0	105	105	1	1,319	0	1,319	0	0	0	0	0	0
46	0	105	105	1	1,319	0	1,319	0	0	0	0	0	0
47	0	105	105	1	1,319	0	1,319	0	0	0	0	0	0
48	0	105	105	1	1,319	0	1,319	0	0	0	0	0	0
49	0	105	105	1	1,319	0	1,319	0	0	0	0	0	0
50	0	105	105	0	1,319	0	1,319	0	0	0	0	0	0
	10,536	0		15,277	7,966								7,917
	10,536	0											0.01

Year	Cost						Benefit						EIRR Verification
	Construction Cost		O&M		NPV		Flood Control		Power Generation		Grand Total		
	Short Term	Long Term	Total	Short Term	Long Term	Total	Short Term	Long Term	Total	Short Term	Long Term	Total	
1	0	0	0	0	0	0	0	0	0	0	0	0	-256
2	478	478	956	0	0	0	0	0	0	0	0	0	-394
3	3,059	3,059	6,118	0	0	0	0	0	0	0	0	0	-2,288
4	3,224	3,224	6,448	0	0	0	0	0	0	0	0	0	-2,191
5	3,493	3,493	6,986	0	0	0	0	0	0	0	0	0	-2,169
6	0	105	105	59	1,319	0	1,319	0	0	0	0	0	0
7	0	105	105	54	1,319	0	1,319	0	0	0	0	0	0
8	0	105	105	49	1,319	0	1,319	0	0	0	0	0	0
9	0	105	105	45	1,319	0	1,319	0	0	0	0	0	0
10	0	105	105	41	1,319	0	1,319	0	0	0	0	0	0
11	0	105	105	37	1,319	0	1,319	0	0	0	0	0	0
12	0	105	105	34	1,319	0	1,319	0	0	0	0	0	0
13	0	105	105	31	1,319	0	1,319	0	0	0	0	0	0
14	0	105	105	28	1,319	0	1,319	0	0	0	0	0	0
15	0	105	105	25	1,319	0	1,319	0	0	0	0	0	0
16	0	105	105	23	1,319	0	1,319	0	0	0	0	0	0
17	0	105	105	21	1,319	0	1,319	0	0	0	0	0	0
18	0	105	105	19	1,319	0	1,319	0	0	0	0	0	0
19	0	105	105	17	1,319	0	1,319	0	0	0	0	0	0
20	0	105	105	16	1,319	0	1,319	0	0	0	0	0	0
21	0	105	105	14	1,319	0	1,319	0	0	0	0	0	0
22	0	105	105	12	1,319	0	1,319	0	0	0	0	0	0
23	0	105	105	11	1,319	0	1,319	0	0	0	0	0	0
24	0	105	105	10	1,319	0	1,319	0	0	0	0	0	0
25	0	105	105	9	1,319	0	1,319	0	0	0	0	0	0
26	0	105	105	8	1,319	0	1,319	0	0	0	0	0	0
27	0	105	105	7	1,319	0	1,319	0	0	0	0	0	0
28	0	105	105	6	1,319	0	1,319	0	0	0	0	0	0
29	0	105	105	5	1,319	0	1,319	0	0	0	0	0	0
30	0	105	105	5	1,319	0	1,319	0	0	0	0	0	0
31	0	105	105	5	1,319	0	1,319	0	0	0	0	0	0
32	0	105	105	5	1,319	0	1,319	0	0	0	0	0	0
33	0	105	105	5	1,319	0	1,319	0	0	0	0	0	0
34	0	105	105	4	1,319	0	1,319	0	0	0	0	0	0
35	0	105	105	4	1,319	0	1,319	0	0	0	0	0	0
36	0	105	105	3	1,319	0	1,319	0	0	0	0	0	0
37	0	105	105	3	1,319	0	1,319	0	0	0	0	0	0
38	0	105	105	3	1,319	0	1,319	0	0	0	0	0	0
39	0	105	105	3	1,319	0	1,319	0	0	0	0	0	0
40	0												

Table H.4.5 (23) Cost Benefit Stream of Alternative Plan of Case 1 in Nilwala River Basin

River:	NILWALA	Overall
Case:	1	1

Year	Cost						Benefit						(Unit: Million Rs.)	
	Construction Cost			O&M			Flood Control			Power Generation				
	Short Term	Long Term	Total	Short Term	Long Term	Total	Short Term	Long Term	Total	Short Term	Long Term	Total		
1	434	434	434	0	434	395	0	0	0	0	0	0	-395	
2	550	550	550	0	550	455	0	0	0	0	0	0	-455	
3	2,760	2,760	2,760	0	2,760	2,074	0	0	0	0	0	0	-550	
4	2,848	2,848	2,848	0	2,848	1,945	0	0	0	0	0	0	-2,760	
5	3,014	3,014	3,014	0	3,014	1,871	0	0	0	0	0	0	-2,848	
6	311	311	96	96	407	230	1,980	0	1,980	0	0	0	-3,014	
7	583	583	96	96	679	348	1,980	0	1,980	0	0	0	-1,871	
8	621	621	96	96	717	335	1,980	0	1,980	0	0	0	-1,871	
9	678	678	96	96	774	328	1,980	0	1,980	0	0	0	-1,871	
10	194	194	96	96	290	112	1,980	0	1,980	0	0	0	-1,871	
11	208	208	96	96	304	107	1,980	0	1,980	0	0	0	-1,871	
12	223	223	96	96	319	102	1,980	0	1,980	0	0	0	-1,871	
13	239	239	96	96	335	97	1,980	0	1,980	0	0	0	-1,871	
14	257	257	96	96	353	93	1,980	0	1,980	0	0	0	-1,871	
15	277	277	96	96	373	89	1,980	0	1,980	0	0	0	-1,871	
16	0	0	96	96	36	132	132	29	0	2,223	0	2,223	455	
17	0	0	96	96	36	132	132	26	0	2,223	0	2,223	455	
18	0	0	96	96	36	132	132	24	0	2,223	0	2,223	455	
19	0	0	96	96	36	132	132	22	0	2,223	0	2,223	455	
20	0	0	96	96	36	132	132	20	0	2,223	0	2,223	455	
21	0	0	96	96	36	132	132	18	0	2,223	0	2,223	455	
22	0	0	96	96	36	132	132	16	0	2,223	0	2,223	455	
23	0	0	96	96	36	132	132	15	0	2,223	0	2,223	455	
24	0	0	96	96	36	132	132	13	0	2,223	0	2,223	455	
25	0	0	96	96	36	132	132	12	0	2,223	0	2,223	455	
26	0	0	96	96	36	132	132	11	0	2,223	0	2,223	455	
27	0	0	96	96	36	132	132	10	0	2,223	0	2,223	455	
28	0	0	96	96	36	132	132	9	0	2,223	0	2,223	455	
29	0	0	96	96	36	132	132	8	0	2,223	0	2,223	455	
30	0	0	96	96	36	132	132	7	0	2,223	0	2,223	455	
31	0	0	96	96	36	132	132	6	0	2,223	0	2,223	455	
32	0	0	96	96	36	132	132	5	0	2,223	0	2,223	455	
33	0	0	96	96	36	132	132	4	0	2,223	0	2,223	455	
34	0	0	96	96	36	132	132	3	0	2,223	0	2,223	455	
35	0	0	96	96	36	132	132	2	0	2,223	0	2,223	455	
36	0	0	96	96	36	132	132	1	0	2,223	0	2,223	455	
37	0	0	96	96	36	132	132	0	0	2,223	0	2,223	455	
38	0	0	96	96	36	132	132	0	0	2,223	0	2,223	455	
39	0	0	96	96	36	132	132	0	0	2,223	0	2,223	455	
40	0	0	96	96	36	132	132	0	0	2,223	0	2,223	455	
41	0	0	96	96	36	132	132	0	0	2,223	0	2,223	455	
42	0	0	96	96	36	132	132	0	0	2,223	0	2,223	455	
43	0	0	96	96	36	132	132	0	0	2,223	0	2,223	455	
44	0	0	96	96	36	132	132	0	0	2,223	0	2,223	455	
45	0	0	96	96	36	132	132	0	0	2,223	0	2,223	455	
46	0	0	96	96	36	132	132	0	0	2,223	0	2,223	455	
47	0	0	96	96	36	132	132	0	0	2,223	0	2,223	455	
48	0	0	96	96	36	132	132	0	0	2,223	0	2,223	455	
49	0	0	96	96	36	132	132	0	0	2,223	0	2,223	455	
50	0	0	96	96	36	132	132	0	0	2,223	0	2,223	455	
	9,606	3,591	0	13,197			18,777	8,885			97,596	12,684	3,800	
												7,276	7,276	

13,197

Year	Cost						Benefit						Cost Verification
	Net Present Value	Present Value											
1	380	0	0	0	0	0	0	0	0	0	0	0	-434
2	421	0	0	0	0	0	0	0	0	0	0	0	-550
3	1,667	0	0	0	0	0	0	0	0	0	0	0	-2,760
4	1,543	0	0	0	0	0	0	0	0	0	0	0	-2,848
5	0	0	0	0	0	0	0	0	0	0	0	0	-3,014
6	886	0	0	0	0	0	0	0	0	0	0	0	-1,572
7	266	0	0	0	0	0	0	0	0	0	0	0	-1,300
8	246	0	0	0	0	0	0	0	0	0	0	0	-1,292
9	593	0	0	0	0	0	0	0	0	0	0	0	-1,205
10	232	0	0	0	0	0	0	0	0	0	0	0	-1,689
11	519	0	0	0	0	0	0	0	0	0	0	0	-1,675
12	454	0	0	0	0	0	0	0	0	0	0	0	-1,660
13	397	0	0	0	0	0	0	0	0	0	0	0	-1,644
14	347	0	0	0	0	0	0	0	0	0	0	0	-1,626
15	303	0	0	0	0	0	0	0	0	0	0	0	-1,606
16	265	0	0	0	0	0	0	0	0	0	0	0	-2,091
17	261	0	0	0	0	0	0	0	0	0	0	0	-2,091
18	228	0	0	0	0	0	0	0	0	0	0	0	-2,091
19	199	0	0	0	0	0	0	0	0	0	0	0	-2,091
20	174	0	0	0	0	0	0	0	0	0	0	0	-2,091
21	153	0	0	0	0	0	0	0	0	0	0	0	-2,091
22	8	0	0	0	0	0	0	0	0	0	0	0	-2,091
23	133	0	0	0	0	0	0	0	0	0	0	0	-2,091
24	7	0	0	0	0	0	0	0	0	0	0	0	-2,091
25	117	0	0	0	0	0	0	0	0	0	0	0	-2,091
26	127	0	0	0	0	0	0	0	0	0	0	0	-2,091
27	35	0	0	0	0	0	0	0	0	0	0	0	-2,091
28	48	0	0	0	0	0	0	0	0	0	0	0	-2,091
29	52	0	0	0	0	0	0	0	0	0	0	0	-2,091
30	3	0	0	0	0	0	0	0	0	0	0	0	-2,091
31	27	0	0	0	0	0	0	0	0	0	0	0	-2,091
32	1	0	0	0	0	0	0	0	0	0	0	0	-2,091
33	12	0	0	0	0	0	0	0	0	0	0	0	-2,091
34	14	0	0	0	0	0	0	0	0	0	0	0	-2,091
35	18	0	0	0	0	0	0	0	0	0	0	0	-2,091
36	8	0	0	0	0	0	0	0	0	0	0	0	-2,091
37	0	0	0	0	0	0	0	0	0	0	0	0	-2,091
38	7	0	0	0	0	0	0	0	0	0	0	0	-2,091
39	14	0	0	0	0	0	0	0	0	0	0	0	-2,091
40	16	0	0	0	0	0	0	0	0	0	0	0	-2,091
41	18	0	0	0	0	0	0	0	0	0	0	0	-2,091
42	0	0	0	0	0								

Table H.4.5 (24) Cost Benefit Stream of Alternative Plan of Case 1 in Nilwala River Basin

River:	NILWALA	Short
Case:	1	

Year	Construction Cost			Cost O&M			Flood Control			Benefit Power Generation			Grand Total			B-C (NPV)		
	Short Term	Long Term	Total	Short Term	Long Term	Total	Short Term	Long Term	Total	Short Term	Long Term	Total	Present Value	Net Present Value	Benefit	Cost	EIRR Verification	
1	434	434	868	434	395	829	0	0	0	0	0	0	-395	0	-434	-434		
2	550	550	1,100	550	455	1,005	0	0	0	0	0	0	-455	408	0	-550		
3	2,760	2,760	5,520	2,760	2,074	4,834	0	0	0	0	0	0	-2,074	1,764	0	-2,760		
4	2,848	2,848	5,696	2,848	1,945	4,803	0	0	0	0	0	0	-1,945	1,568	0	-2,848		
5	3,014	3,014	6,028	3,014	1,871	54	1,980	0	0	0	0	0	-1,871	1,429	0	-3,014		
6	96	96	192	96	49	1,980	0	0	0	0	0	0	0	0	0	0		
7	96	96	192	96	49	1,980	0	0	0	0	0	0	0	0	0	0		
8	96	96	192	96	45	1,980	0	0	0	0	0	0	0	0	0	0		
9	96	96	192	96	41	1,980	0	0	0	0	0	0	0	0	0	0		
10	96	96	192	96	37	1,980	0	0	0	0	0	0	0	0	0	0		
11	96	96	192	96	34	1,980	0	0	0	0	0	0	0	0	0	0		
12	96	96	192	96	31	1,980	0	0	0	0	0	0	0	0	0	0		
13	96	96	192	96	28	1,980	0	0	0	0	0	0	0	0	0	0		
14	96	96	192	96	25	1,980	0	0	0	0	0	0	0	0	0	0		
15	96	96	192	96	23	1,980	0	0	0	0	0	0	0	0	0	0		
16	96	96	192	96	21	1,980	0	0	0	0	0	0	0	0	0	0		
17	96	96	192	96	19	1,980	0	0	0	0	0	0	0	0	0	0		
18	96	96	192	96	17	1,980	0	0	0	0	0	0	0	0	0	0		
19	96	96	192	96	16	1,980	0	0	0	0	0	0	0	0	0	0		
20	96	96	192	96	14	1,980	0	0	0	0	0	0	0	0	0	0		
21	96	96	192	96	13	1,980	0	0	0	0	0	0	0	0	0	0		
22	96	96	192	96	12	1,980	0	0	0	0	0	0	0	0	0	0		
23	96	96	192	96	11	1,980	0	0	0	0	0	0	0	0	0	0		
24	96	96	192	96	10	1,980	0	0	0	0	0	0	0	0	0	0		
25	96	96	192	96	9	1,980	0	0	0	0	0	0	0	0	0	0		
26	96	96	192	96	8	1,980	0	0	0	0	0	0	0	0	0	0		
27	96	96	192	96	7	1,980	0	0	0	0	0	0	0	0	0	0		
28	96	96	192	96	6	1,980	0	0	0	0	0	0	0	0	0	0		
29	96	96	192	96	5	1,980	0	0	0	0	0	0	0	0	0	0		
30	96	96	192	96	4	1,980	0	0	0	0	0	0	0	0	0	0		
31	96	96	192	96	3	1,980	0	0	0	0	0	0	0	0	0	0		
32	96	96	192	96	2	1,980	0	0	0	0	0	0	0	0	0	0		
33	96	96	192	96	1	1,980	0	0	0	0	0	0	0	0	0	0		
34	96	96	192	96	0	1,980	0	0	0	0	0	0	0	0	0	0		
35	96	96	192	96	0	1,980	0	0	0	0	0	0	0	0	0	0		
36	96	96	192	96	0	1,980	0	0	0	0	0	0	0	0	0	0		
37	96	96	192	96	0	1,980	0	0	0	0	0	0	0	0	0	0		
38	96	96	192	96	0	1,980	0	0	0	0	0	0	0	0	0	0		
39	96	96	192	96	0	1,980	0	0	0	0	0	0	0	0	0	0		
40	96	96	192	96	0	1,980	0	0	0	0	0	0	0	0	0	0		
41	96	96	192	96	0	1,980	0	0	0	0	0	0	0	0	0	0		
42	96	96	192	96	0	1,980	0	0	0	0	0	0	0	0	0	0		
43	96	96	192	96	0	1,980	0	0	0	0	0	0	0	0	0	0		
44	96	96	192	96	0	1,980	0	0	0	0	0	0	0	0	0	0		
45	96	96	192	96	0	1,980	0	0	0	0	0	0	0	0	0	0		
46	96	96	192	96	0	1,980	0	0	0	0	0	0	0	0	0	0		
47	96	96	192	96	0	1,980	0	0	0	0	0	0	0	0	0	0		
48	96	96	192	96	0	1,980	0	0	0	0	0	0	0	0	0	0		
49	96	96	192	96	0	1,980	0	0	0	0	0	0	0	0	0	0		
50	96	96	192	96	0	1,980	0	0	0	0	0	0	0	0	0	0		
	9,606	9,606	0	13,929	7,328	0	0	0	0	0	0	0	0	89,078	12,123	4,795		
	9,606	9,606	0	0	0	0	0	0	0	0	0	0	0	0	5,826	5,826	-0.01	16.09%

EIRR	4.795
B-C	1.65
B/C	

Table H.4.5 (25) Cost Benefit Stream of Alternative Plan of Case 2 in Nilwala River Basin

River:	NilWALA	Overall
Case:	2	

Year	Construction Cost			Cost O&M			Flood Control			Benefit Power Generation			Grand Total			NPV	B-C (NPV)	Verification
	Short Term	Long Term	Total	Short Term	Long Term	Total	Short Term	Long Term	Total	Short Term	Long Term	Total	Grand Total	Total	Total			
1	447	447	593	2,779	2,871	3,040	0	0	0	447	406	490	0	0	0	-406	-447	
2	593	2,779	3,040	503	503	503	97	97	97	593	2,779	2,088	0	0	0	-490	-593	
3	2,779	2,871	3,040	1,391	1,391	1,391	97	97	97	600	1,488	1,980	0	0	0	-2,088	-2,779	
4	2,871	3,040	3,040	1,445	1,445	1,445	97	97	97	764	1,542	719	0	0	0	-1,980	-2,871	
5	3,040	3,040	3,040	1,536	1,536	1,536	97	97	97	693	1,633	693	0	0	0	-1,980	-3,040	
6				227	227	227	97	97	97	324	125	1,980	0	0	0	-1,980	-1,980	
7				243	243	243	97	97	97	340	119	1,980	0	0	0	-1,980	-1,980	
8				260	260	260	97	97	97	357	114	1,980	0	0	0	-1,980	-1,980	
9				280	280	280	97	97	97	377	109	1,980	0	0	0	-1,980	-280	
10				301	301	301	97	97	97	398	105	1,980	0	0	0	-1,980	-301	
11				324	324	324	97	97	97	421	101	1,980	0	0	0	-1,980	-324	
12				0	0	0	97	97	97	65	162	162	32	0	0	-2,223	-65	
13				0	0	0	97	97	97	97	162	162	29	0	0	-2,223	-97	
14				0	0	0	97	97	97	97	162	162	27	0	0	-2,223	-97	
15				0	0	0	97	97	97	97	162	162	24	0	0	-2,223	-97	
16				0	0	0	97	97	97	97	162	162	22	0	0	-2,223	-97	
17				0	0	0	97	97	97	97	162	162	20	0	0	-2,223	-97	
18				0	0	0	97	97	97	97	162	162	18	0	0	-2,223	-97	
19				0	0	0	97	97	97	97	162	162	16	0	0	-2,223	-97	
20				0	0	0	97	97	97	97	162	162	14	0	0	-2,223	-97	
21				0	0	0	97	97	97	97	162	162	12	0	0	-2,223	-97	
22				0	0	0	97	97	97	97	162	162	11	0	0	-2,223	-97	
23				0	0	0	97	97	97	97	162	162	10	0	0	-2,223	-97	
24				0	0	0	97	97	97	97	162	162	9	0	0	-2,223	-97	
25				0	0	0	97	97	97	97	162	162	15	0	0	-2,223	-97	
26				0	0	0	97	97	97	97	162	162	14	0	0	-2,223	-97	
27				0	0	0	97	97	97	97	162	162	12	0	0	-2,223	-97	
28				0	0	0	97	97	97	97	162	162	11	0	0	-2,223	-97	
29				0	0	0	97	97	97	97	162	162	10	0	0	-2,223	-97	
30				0	0	0	97	97	97	97	162	162	9	0	0	-2,223	-97	
31				0	0	0	97	97	97	97	162	162	8	0	0	-2,223	-97	
32				0	0	0	97	97	97	97	162	162	7	0	0	-2,223	-97	
33				0	0	0	97	97	97	97	162	162	6	0	0	-2,223	-97	
34				0	0	0	97	97	97	97	162	162	6	0	0	-2,223	-97	
35				0	0	0	97	97	97	97	162	162	6	0	0	-2,223	-97	
36				0	0	0	97	97	97	97	162	162	5	0	0	-2,223	-97	
37				0	0	0	97	97	97	97	162	162	4	0	0	-2,223	-97	
38				0	0	0	97	97	97	97	162	162	4	0	0	-2,223	-97	
39				0	0	0	97	97	97	97	162	162	4	0	0	-2,223	-97	
40				0	0	0	97	97	97	97	162	162	4	0	0	-2,223	-97	
41				0	0	0	97	97	97	97	162	162	3	0	0	-2,223	-97	
42				0	0	0	97	97	97	97	162	162	3	0	0	-2,223	-97	
43				0	0	0	97	97	97	97	162	162	3	0	0	-2,223	-97	
44				0	0	0	97	97	97	97	162	162	2	0	0	-2,223	-97	
45				0	0	0	97	97	97	97	162	162	2	0	0	-2,223	-97	
46				0	0	0	97	97	97	97	162	162	2	0	0	-2,223	-97	
47				0	0	0	97	97	97	97	162	162	2	0	0	-2,223	-97	
48				0	0	0	97	97	97	97	162	162	2	0	0	-2,223	-97	
49				0	0	0	97	97	97	97	162	162	1	0	0	-2,223	-97	
50				0	0	0	97	97	97	97	162	162	1	0	0	-2,223	-97	
	9,730	6,510	16,240				22,897	10,396								97,596	12,684	2,289
																9,186	9,186	12,40%

EIRR	2289
B-C	1,22

Table H.4.5 (26) Cost Benefit Stream of Alternative Plan of Case 2 in Nilwala River Basin

River:	NILWALA	Short
Case:	2	

Year	Construction Cost			Cost O&M			Benefit Power Generation			B-C (NPV)			EIRR Verification	
	Short Term	Long Term	Total	Short Term	Long Term	Total	Grand Total	NPV	Short Term	Long Term	Total	Grand Total	NPV	
1	447	447	593	2,779	2,871	3,070	0	447	406	0	0	0	-447	-447
2	533	2,779	3,070	0	0	0	593	490	0	0	0	0	0	-533
3	0	0	0	2,779	1,961	3,070	0	2,779	2,088	0	0	0	0	-2,779
4	0	0	0	2,871	1,961	3,070	0	2,871	1,961	0	0	0	0	-2,871
5	0	0	0	3,070	1,961	3,070	0	3,070	1,961	0	0	0	0	-3,070
6	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
7	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
8	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
9	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
10	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
11	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
12	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
13	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
14	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
15	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
16	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
17	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
18	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
19	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
20	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
21	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
22	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
23	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
24	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
25	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
26	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
27	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
28	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
29	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
30	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
31	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
32	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
33	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
34	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
35	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
36	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
37	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
38	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
39	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
40	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
41	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
42	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
43	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
44	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
45	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
46	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
47	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
48	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
49	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
50	98	98	98	98	98	98	98	98	98	98	98	98	98	1,882
	9,760	9,760	0	14,152	7,449									5,974
														5,974
														15.85%
														EIRR
														4.673
														B-C
														1.63

Table H.4.5 (27) Cost Benefit Stream of Alternative Plan of Case 3 in Nilwala River Basin

River:	NILWALA	Overall
Case:	3	

Year	Construction Cost			Cost O&M			Flood Control			Benefit Power Generation			B-C (NPV)			EIRR Verification
	Short Term	Long Term	Total	Short Term	Long Term	Total	Grand Total	NPV	Short Term	Long Term	Total	Short Term	Long Term	Total	NPV	
1	577	577	989	2,879	2,992	5,871	577	525	0	0	0	0	0	0	0	-577
2	989	0	989	2,992	0	2,992	0	0	0	0	0	0	0	0	0	-989
3	2,879	0	2,879	0	0	0	0	0	0	0	0	0	0	0	0	-2,879
4	2,992	0	2,992	0	0	0	0	0	0	0	0	0	0	0	0	-2,992
5	3,185	0	3,185	1,580	106	1,686	952	1,673	0	0	0	0	0	0	0	-3,185
6	0	1,580	1,580	106	106	1,673	1,673	0	0	0	0	0	0	0	0	-1,580
7	3,163	0	3,163	5,566	106	3,269	1,678	1,673	0	0	0	0	0	0	0	-3,163
8	5,566	0	5,566	5,858	106	5,672	2,646	1,673	0	0	0	0	0	0	0	-5,566
9	5,858	0	5,858	106	106	5,964	2,529	1,673	0	0	0	0	0	0	0	-5,858
10	3,334	0	3,334	106	106	3,440	1,326	1,673	0	0	0	0	0	0	0	-3,334
11	3,653	0	3,653	106	106	3,759	1,318	1,673	0	0	0	0	0	0	0	-3,653
12	4,003	0	4,003	106	106	4,109	1,309	1,673	0	0	0	0	0	0	0	-4,003
13	4,388	0	4,388	106	106	4,494	1,302	1,673	0	0	0	0	0	0	0	-4,388
14	4,812	0	4,812	106	106	4,918	1,295	1,673	0	0	0	0	0	0	0	-4,812
15	739	0	739	106	106	845	202	1,673	0	0	0	0	0	0	0	-739
16	0	106	106	371	477	477	104	1,673	0	0	0	0	0	0	0	-0
17	0	0	106	371	477	477	94	0	0	0	0	0	0	0	0	-0
18	0	106	371	477	477	477	86	0	0	0	0	0	0	0	0	-0
19	0	106	371	477	477	477	78	0	0	0	0	0	0	0	0	-0
20	0	106	371	477	477	477	71	0	0	0	0	0	0	0	0	-0
21	0	106	371	477	477	477	64	0	0	0	0	0	0	0	0	-0
22	0	106	371	477	477	477	59	0	0	0	0	0	0	0	0	-0
23	0	106	371	477	477	477	53	0	0	0	0	0	0	0	0	-0
24	0	106	371	477	477	477	48	0	0	0	0	0	0	0	0	-0
25	0	106	371	477	477	477	44	0	0	0	0	0	0	0	0	-0
26	0	106	371	477	477	477	40	0	0	0	0	0	0	0	0	-0
27	0	106	371	477	477	477	36	0	0	0	0	0	0	0	0	-0
28	0	106	371	477	477	477	33	0	0	0	0	0	0	0	0	-0
29	0	106	371	477	477	477	30	0	0	0	0	0	0	0	0	-0
30	0	106	371	477	477	477	27	0	0	0	0	0	0	0	0	-0
31	0	106	371	477	477	477	25	0	0	0	0	0	0	0	0	-0
32	0	106	371	477	477	477	23	0	0	0	0	0	0	0	0	-0
33	0	106	371	477	477	477	21	0	0	0	0	0	0	0	0	-0
34	0	106	371	477	477	477	19	0	0	0	0	0	0	0	0	-0
35	0	106	371	477	477	477	17	0	0	0	0	0	0	0	0	-0
36	0	106	371	477	477	477	15	0	0	0	0	0	0	0	0	-0
37	0	106	371	477	477	477	14	0	0	0	0	0	0	0	0	-0
38	0	106	371	477	477	477	13	0	0	0	0	0	0	0	0	-0
39	0	106	371	477	477	477	12	0	0	0	0	0	0	0	0	-0
40	0	106	371	477	477	477	11	0	0	0	0	0	0	0	0	-0
41	0	106	371	477	477	477	10	0	0	0	0	0	0	0	0	-0
42	0	106	371	477	477	477	9	0	0	0	0	0	0	0	0	-0
43	0	106	371	477	477	477	8	0	0	0	0	0	0	0	0	-0
44	0	106	371	477	477	477	7	0	0	0	0	0	0	0	0	-0
45	0	106	371	477	477	477	6	0	0	0	0	0	0	0	0	-0
46	0	106	371	477	477	477	5	0	0	0	0	0	0	0	0	-0
47	0	106	371	477	477	477	4	0	0	0	0	0	0	0	0	-0
48	0	106	371	477	477	477	3	0	0	0	0	0	0	0	0	-0
49	0	106	371	477	477	477	2	0	0	0	0	0	0	0	0	-0
50	0	106	371	477	477	477	1	0	0	0	0	0	0	0	0	-0
	10,622	37,096		65,482	23,185										14,154	-9,031
															35,115	5,19%
																47,718

EIRR	B-C	B/C
		-9,031

0.61

Table H.4.5 (28) Cost Benefit Stream of Alternative Plan of Case 3 in Nilwala River Basin

River:	Nilwala	Short
Case:	3	

Year	Construction Cost			Cost O&M			Flood Control			Benefit Power Generation			B-C (NPV)			EIRR Verification
	Short Term	Long Term	Total	Short Term	Long Term	Total	Grand Total	NPV	Short Term	Long Term	Total	Grand Total	NPV	Total	Net Present Value	
1	577	577	989	2,879	2,992	3,185	0	577	525	0	0	0	0	-525	-577	
2	989	2,879	3,185	2,992	3,185	0	989	817	0	0	0	0	0	-817	0	-989
3	2,879	2,992	0	2,992	0	0	2,879	2,163	0	0	0	0	0	-2,163	0	-2,879
4	2,992	3,185	0	3,185	0	0	2,992	2,044	0	0	0	0	0	-2,044	0	-2,992
5	3,185	0	0	0	0	0	3,185	1,978	0	0	0	0	0	-1,978	0	-3,185
6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
7	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
8	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
9	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
10	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
11	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
12	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
13	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
14	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
15	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
16	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
17	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
18	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
19	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
20	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
21	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
22	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
23	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
24	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
25	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
26	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
27	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
28	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
29	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
30	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
31	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
32	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
33	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
34	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
35	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
36	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
37	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
38	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
39	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
40	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
41	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
42	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
43	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
44	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
45	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
46	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
47	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
48	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
49	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
50	106	106	106	106	106	106	106	106	106	106	106	106	106	0	0	0
	10,622	10,622	0				15,402	8,177						7,434	7,434	
	10,622	10,622	0											0.00	12.45%	

EIRR	12.45%
B-C	2,069
B/C	1.25

Table H.4.5 (29) Cost Benefit Stream of Alternative Plan of Case 4 in Nilwala River Basin

River:	Nilwala Overall	
Case:	4	

Year	Construction Cost			Cost O&M			Flood Control			Benefit Power Generation			B-C (NPV)		
	Short Term	Long Term	Total	Short Term	Long Term	Total	Grand Total	NPV	Short Term	Long Term	Total	Grand Total	NPV	Total	
1	560	560	0	916	916	0	560	509	0	0	0	0	-509	-560	
2	916	2,923	3,839	2,923	3,033	0	916	757	0	0	0	0	-757	-916	
3	3,033	3,033	0	3,033	3,033	0	2,923	2,196	0	0	0	0	-2,196	-2,923	
4	3,224	3,224	0	3,224	3,224	0	3,224	2,002	0	0	0	0	-2,002	-3,224	
5	1,332	1,332	0	107	107	0	1,332	1,439	812	1,980	0	0	0	0	
6	3,460	3,460	0	107	107	0	3,460	1,830	1,980	0	1,980	1,117	979	1,348	
7	4,561	4,561	0	107	107	0	4,561	2,177	1,980	0	1,980	1,016	2,277	2,412	
8	4,805	4,805	0	107	107	0	4,805	2,083	1,980	0	1,980	923	2,795	2,347	
9	3,903	3,903	0	107	107	0	3,903	1,546	1,980	0	1,980	840	2,759	2,347	
10	4,010	4,010	0	107	107	0	4,010	1,537	1,980	0	1,980	763	2,113	2,347	
11	4,280	4,280	0	107	107	0	4,280	1,537	1,980	0	1,980	694	2,168	2,347	
12	4,695	4,695	0	107	107	0	4,695	1,530	1,980	0	1,980	631	-899	-2,002	
13	564	564	0	107	107	0	564	194	1,980	0	1,980	573	379	2,225	
14	607	607	0	107	107	0	607	174	1,980	0	1,980	521	333	2,225	
15	654	654	0	107	107	0	654	182	1,980	0	1,980	474	292	2,225	
16	0	0	0	107	289	395	395	86	0	3,173	691	605	142	1,338	
17	289	395	395	107	289	0	395	78	0	3,173	628	550	133	1,067	
18	0	0	0	107	289	395	395	71	0	3,173	571	500	125	2,778	
19	0	0	0	107	289	395	395	65	0	3,173	519	454	117	939	
20	0	0	0	107	289	395	395	59	0	3,173	472	413	110	881	
21	0	0	0	107	289	395	395	53	0	3,173	429	375	103	826	
22	0	0	0	107	289	395	395	49	0	3,173	390	341	97	775	
23	0	0	0	107	289	395	395	44	0	3,173	354	310	91	727	
24	0	0	0	107	289	395	395	40	0	3,173	322	282	85	682	
25	0	0	0	107	289	395	395	36	0	3,173	293	256	80	639	
26	0	0	0	107	289	395	395	33	0	3,173	266	233	75	600	
27	0	0	0	107	289	395	395	30	0	3,173	242	212	70	562	
28	0	0	0	107	289	395	395	27	0	3,173	220	193	66	528	
29	0	0	0	107	289	395	395	25	0	3,173	200	175	62	495	
30	0	0	0	107	289	395	395	23	0	3,173	182	159	58	464	
31	0	0	0	107	289	395	395	21	0	3,173	165	145	54	435	
32	0	0	0	107	289	395	395	19	0	3,173	150	132	51	408	
33	0	0	0	107	289	395	395	17	0	3,173	137	120	48	383	
34	0	0	0	107	289	395	395	15	0	3,173	124	109	35	359	
35	0	0	0	107	289	395	395	14	0	3,173	109	99	42	337	
36	0	0	0	107	289	395	395	13	0	3,173	103	90	39	316	
37	0	0	0	107	289	395	395	12	0	3,173	93	82	37	296	
38	0	0	0	107	289	395	395	11	0	3,173	85	74	35	278	
39	0	0	0	107	289	395	395	10	0	3,173	77	68	32	261	
40	0	0	0	107	289	395	395	9	0	3,173	70	61	30	244	
41	0	0	0	107	289	395	395	8	0	3,173	64	56	29	229	
42	0	0	0	107	289	395	395	7	0	3,173	58	51	27	215	
43	0	0	0	107	289	395	395	6	0	3,173	53	46	25	202	
44	0	0	0	107	289	395	395	5	0	3,173	48	42	24	189	
45	0	0	0	107	289	395	395	5	0	3,173	44	38	22	177	
46	0	0	0	107	289	395	395	4	0	3,173	40	35	21	166	
47	0	0	0	107	289	395	395	3	0	3,173	36	31	19	156	
48	0	0	0	107	289	395	395	4	0	3,173	33	29	18	146	
49	0	0	0	107	289	395	395	3	0	3,173	30	26	17	137	
50	0	0	0	107	289	395	395	3	0	3,173	27	24	16	129	
	10,656	28,861			54,414	20,528					130,847	14,878	-5,650	26,662	
													0.00	6.62%	

EIRR	6.62%
B-C	-5,650
B/C	0.72

Supporting Report I

Established Systems in Pilot Project

Supporting Report I Established Systems in Pilot Project

I.1 Hydrological Information System

Systems established in Pilot Project are mainly composed of Hydrological Information System and Intra-Governmental Network.




Figure I.1.1 Relation of Hydrological Information System and Intra-Governmental Network

I.1.1 General

The Hydrological Information System is consisted of the following two systems: 1) Monitoring Equipment and Data Collecting System, and 2) Database and Data Display System.




Figure I.1.2 System Diagram of Hydrological Information System

I.1.2 Monitoring Equipment and Data Collecting System

The pilot project automated the following observation stations in Kelani and Kalu river basin and the observed data at some of the most important stations are transferred to the hydrology division by telemeter system.

Table I.1.1 Selected Gauging Stations

River Basin	Name of gauging station	Rain gauge	Water level gauge	Telemeter
Kelani	Nagalagam St.	—	○	○
	Hanwella	○	○	○
	Glencourse	△	○	—
	Kitulgala	○	△	—
	Dompe	○	—	—
	Meegoda	○	—	○
	Holombuwa	○	○	○
	Deraniyagala	○*	○	○
Kalu	Putupaula	—	○	○
	Ellagawa	—	○	○
	Ratnapura	—	△	○
	Dela	—	○	—
	Malwala	—	○	—
	Hapugastenna	○	—	○

○: installed by Pilot Project, △: existing, —: not installed, *: will be installed (location is not decided)




Figure I.1.3 Location of Observation Stations

(1) Nagalagam st.



(2) Hanwella




(3) Glencourse




(4) Kitulgala




(5) Dompe




(6) Meegoda




(7) Holombuwa





(8) Deraniyagala



(9) Putupaula




(10) Ellagawa




(11) Ratnapura



(12) Dela



(13) Malwala



(14) Hapugastenna



I.1.3 Database and Data Display System

In the pilot project, collected data by telemeter system is saved in the database, and tables and graphs are created and shown on the screen. The tables and graphs are also shown on the wide screen so that all the officers in the hydrology division can monitor the current situation.



Figure I.1.4 Installed Equipments at Hydrology Division, DOI



Figure I.1.5 Monitoring Screen of Hydrological Information System

I.2 Intra-Governmental Network

I.2.1 Summary of Intra-Governmental Network

Intra-Governmental Network was installed to connect relevant 14 organizations through a dedicated line so that government officers of the concerned organizations can easily communicate whenever necessary. The connected organizations are; DMC, DOI, DOM, NBRO, Police, Media (SLBC and SLRC),and DDMCU (Colombo, Gampaha, Kegalle, Ratnapura, Kalutara, Galle and Matara).





Figure I.2.1 System Diagram of Intra-Governmental Network

Each organization was provided a personal computer, telephone and fax to be linked to this network. Normal communication using telephone and fax, and information sharing through a web server at the DMC is made possible by this network. Commercial dedicated communication line by radio system called “Wimax” was selected for Intra-Governmental Network.



Organization	Telephone	Fax
DMC	101,102,103	201
DOI	201	202
DOM	301	302
NBRO	401	402
Police	501	502
SLRC	601	602
SLBC	701	702
DDMCU Colombo	801	802
DDMCU Gampaha	901	902
DDMCU Kegalle	931	932
DDMCU Ratnapura	941	942
DDMCU Kalutara	921	922
DDMCU Galle	951	952
DDMCU Matara	911	912

Figure I.2.2 Location Map and Telephone/Fax Number

(1) DMC



(2) DOI




(3) DOM



(4) NBRO




(5) SLRC



(6) SLBC



(7) DDMCU Colombo



(8) DDMCU Gampaha



(9) DDMCU Kegalle




(10) DDMCU Ratnapura



(11) DDMCU Kalutara



(12) DDMCU Galle



(13) DDMCU Matara



(14) Police (Taking photo is not allowed)

I.2.2 Utilization of Intra-Governmental Network

It is possible to communicate each other during emergency period without congestion because of dedicated line. This is the best advantage of Intra-Governmental Network. Another advantage is that because of the fixed price contract with communication company, stable budget planning is possible. And information can be shared easily among related organizations by utilizing “notice board” or “share folder”. If warning message or evacuation instruction is uploaded to the notice board, this message can be shared by all the organizations at once. Large size files such as photo of disaster or inundation condition can be shared smoothly and easily by utilizing share folder.

The screenshot displays the JICA Disaster Management Notice Board interface. At the top, it shows the logo 'jica' and the title 'DISASTER MANAGEMENT NOTICE BOARD'. The date and time are listed as 'Wednesday, December 24, 2008 3:08:17 PM'. Below the header, there are navigation links for 'Home', 'My Notices', 'All Notices', 'Administration', and 'Archive'. A 'Logout' link is also present. The main content area is divided into two sections: 'Early Warning' and 'Situational Report'. The 'Early Warning' section contains several entries, each with a subject, date, and a brief description. The 'Situational Report' section includes a photograph of a damaged building and a text reminder about a disaster management exercise.

Figure I.2.3 First Page of Notice Board

And, Hydrological Information System can be monitored through Intra-Governmental Network. It serves many uses for provision of information by each organization.

I.3 Recommendation of Methods to Disseminate Information to People

I.3.1 Information Dissemination by Internet

Anybody can monitor the data by uploading the Hydrological Information System to web site. PC and ADSL line were provided to DS office to monitor the system through internet. Because DS office has an important role to disseminate information to GN and people.




Figure I.3.1 System Diagram of Information Transfer through Internet

PC and ADSL line were provided to 3 DS offices such as Kollonawa and Biyagama (Kelani river basin), and Ratnapura (Kalu river basin).




Figure I.3.2 Location Map of Selected DS Office

I.3.2 Information Dissemination by Car Mount Type Loud Speaker

DS office has a role to disseminate information, that is obtained through DDMCU or Internet, to people through GN. In addition to this, car mount type loud speaker is provided as a tool to disseminate information directly to people.

I.3.3 Photos at DS Offices

(1) Kolonnawa DS



(2) Biyagama DS



(3) Ratnapura DS



Supporting Report J

Warning Criteria and Warning Message

Supporting Report J Warning Criteria and Content of Warning Message

J.1 General

In the main report, the methods to define the warning criteria for slow flood, fast flood and landslide are briefly explained. Concrete methods to define the warning criteria for flood in Kelani as the example of slow flood and for flood in Ratnapura as the example of fast flood are explained as follows. Explanation of method for sediment disaster is also shown.

Regarding the contents of warning message, although the necessary items are shown in the main report, sample messages for flood, landslide and tsunami are shown in this chapter.

J.2 Warning Criteria for Downstream of Kelani River

J.2.1 General

It is considered necessary that the technical benchmark for alert, warning and evacuation instruction should be objective and understandable. In particular, the technical benchmark for evacuation instruction should be easily understood by the local government officers as well as local residents since they have the responsibility for the issuance of evacuation instruction. There are many cases in Japan that the local government hesitates to issue evacuation instruction in advance or issues it after disaster happens, because the local government is afraid of making a mistake. This is because the benchmark is not clear.

Based on the “Standing Order” in Kelani River, when a 24-hour rainfall exceeds 125mm, DOI discusses the possibility of minor flood by checking the water level in the basin. And in case the DOI is convinced of the imminent minor flood situation, warning is issued to the people living in the low-lying areas immediately, with the least possible delay, through the media, police and local government. Although it may be possible to respond in time since the flood concentration time is long in Kelani river, it is very important to set up several technical benchmarks and to define the activities depending on the benchmarks from the point of risk management. In this report, the Study Team has studied what kind of the warning level can be defined for Kelani River.

J.2.2 Correlation Analysis

(1) Target Water Level

Location of main monitoring stations in Kelani is shown below. The correlation analysis of three monitoring stations, Glencourse, Hanwella and Nagalagam St., those are at the downstream of confluence of main river and two tributaries, was conducted. The target water level for flood forecasting is the water level by that level the inundation occurs around Colombo at first. This water level is 5 feet at Nagalagam St. gauging station. (Regarding the water level 5 feet, there is a report saying that inundation occurs below this water level in the actual situation. Therefore, target water level can be modified according to further study.)




Figure J.2.1 Location of Gauging Stations in Kelani River Basin

(2) Correlation Analysis

The table below shows the annual maximum water level after 1985. No major flood occurred except for the devastating flooding in 1989, with recorded water level of 9.20 feet at Nagalagam St. gauging station, while minor flooding were recorded seven times.

These 8 floods are selected as representative floods to compare the hourly water level at Glencourse, Hanwella and Nagalagam St. gauging stations.

Table J.2.1 Annual Maximum Water Level

Year.Month	Waterlevel at Nagalagam st. (feet)	Flood Level	Year.Month	Waterlevel at Nagalagam st. (feet)	Flood Level
1985.6	4.60		1996.9	5.00	Minor
1986.4	2.60		1997.9	5.50	Minor
1987.6	3.10		1998.7	4.90	
1988.9	4.10		1999.4	6.60	Minor
1989.6	9.20	Dangerous	2000.9	5.00	Minor
1990.5	3.90		2001.6	3.90	
1991.6	4.90		2002.6	4.05	
1992.6	5.10	Minor	2003.7	3.95	
1993.10	5.00	Minor	2004.11	5.00	Minor
1994.5	4.60		2005.9	4.75	
1995.5	4.20				

The example of peak water level comparison is shown in the following Figure.




Figure J.2.2 Example of Comparison of Peak Water Level

To carry out the correlation analysis of the water level at three gauging stations, water levels of 8 representative floods observed at 3 gauging stations are compared. Since the number of representative floods are small and not enough for correlation analysis if only peak water levels are compared, other water level combinations which correspond to the water level among three gauging stations are identified by applying the method shown below.

Other water level combinations are selected by assuming that upstream water level at t_1 is corresponding to downstream water level at t_3 , where $(t_3-t_1) = (t_4-t_2)$, it means $\Delta t_a = \Delta t_b$.






Figure J.2.3 Procedure for Finding Corresponding Water Levels

Five different Δt_a was set for all eight representative floods to get the corresponding water levels, and correlation analysis was carried out using all water level combinations. Result of correlation analysis is shown below.



Correlation Analysis of Glencourse and Nagalagam St.



Correlation Analysis of Hanwella and Nagalagam St.

Figure J.2.4 Result of Correlation Analysis

Water level at Glencourse gauging station is about 52.0 ft., corresponding to 5.0 ft. at Nagalagam St. gauging station according to the correlation analysis. This represents that if the water level reaches 52.0 ft. at Glencourse, there is a possibility that the water level at Nagalagam St. will reach to minor flood level of 5.0 ft. after certain hours. Regarding the time lag (flood travel time) between Glencourse and Nagalagam St., there is at least 10 hours, although there seems no correlation between the water level of Glencourse and travel time to Nagalagam St. Therefore, the warning that can be issued is as follows: “There is a possibility of Minor Flood after 10 hours in case the water level at Glencourse reaches 52.0 ft.”

In the same way, based on the result of the correlation analysis, the warning that can be issued may be as follows: “There is a possibility of Minor Flood after three hours in case the water level at Hanwella reaches 4.5 m.”

(3) Warning Criteria

Based on the analysis, there are two opportunities to issue the warning in terms of time frame. One is 10 hours and the other one is 3 hours before the flood comes. The warning can be understandable if the meaning is given by describing the activities to be taken at 10 hours and three hours before flooding.

Three hours before flooding, the residents can afford to plan their action. They have time to assess whether it would be better to move their furniture upstairs or to move everything out, depending on

the forecast by DOI or evacuation instruction by GA before evacuation. Therefore, the warning issued at three hours before flooding is the “Warning” which means that people should evacuate smoothly after preparation. GA shall issue “Evacuation Instruction” based on the discussion of district level DM committee meeting after receiving warning from DOI.

DOI is trying to give a more accurate forecast by checking the rainfall amount around the basin and the water level of upstream at 10 hours before flooding. The “Standing Order” says the Flood Committee is convened in case of the Minor Flood, but it is recommended to have a meeting or to coordinate closely with related organizations by using intra-governmental network to prepare for the coming flood at 10 hours before flooding. For local people, it is also a time to watch for signs of the coming flood. Therefore, the warning issued at 10 hours before flooding is the “Alert” that makes people and the related organizations recognize the coming flood.

Warning Criteria to forecast Minor Flood (5 feet at Nagalagam St.) in downstream of Kelani River can be defined as follows.

Table J.2.2 Warning Criteria for Minor Flood in Kelani River

Level	Station	Water Level	Available Time
Advisory	Glencourse	52 feet	10 hours
Warning	Hanwella	4.5 m	3 hours

Although the above study is only for the Minor Flood, the same method can be used for higher flood level by checking the water level at the upstream and modifying the water level forecasting at the downstream.

(4) Comparison with Actual Events

Validity of above warning criteria was studied using the data of actual flood on April/May flood and May/June flood.

Regarding April/May flood, the duration from the time when the water level of Glencourse exceeds its warning level 52 feet to the time when the water level of Nagalagam St. exceeds 5 feet, and the duration from the time when the water level of Hanwella exceeds its warning level 4.5 m to the time when the water level of Nagalagam St. exceeds 5 feet, are shown below. It is found that there are 10 hours from Glencourse to Nagalagam St., and 7 hours from Hanwella to Nagalagam St.




Figure J.2.5 Travel Time (April / May Flood)

Regarding May/June flood, it is found that there are 14 hours from Glencourse to Nagalagam St., and 11 hours from Hanwella to Nagalagam St.




Figure J.2.6 Travel Time (May / June Flood)

If DOI issues flood warning according to the above defined warning criteria, related organization can have enough time for taking their actions in the case for two floods in 2008. Therefore, it can be said that the defined warning criteria is appropriate.


(5) Comparison with Simulation Result

Hydraulic Simulation was conducted by using the MIKE11 model prepared in Component 1 against the result of correlation analysis of three water level gauging stations. The condition of the model was used for this simulation that was calibrated to fit to the actual flood to reflect the present geographical conditions and storage effect etc. of the flood basin in the component 1. Actual hydrograph of 1989 flood and 1990 flood was given to Glencourse as the boundary condition, and simulation result at Hanwella and Nagalagam St. was compared to actual hydrograph in the calibration. In this simulation, actual hydrograph of 1989 flood and 1990 flood was scaled to seven different cases in addition to actual two cases, and total nine case hydrographs were given to Glencourse and correlation of peak water level at three stations and its time lag were analyzed. Boundary condition of nine cases of simulation is shown below.


Table J.2.3 Case of Simulation

Case	Boundary Condition at Glencourse
1	1990 actual hydrograph
2	$1.2 * 1990$ actual hydrograph
3	$1.4 * 1990$ actual hydrograph
4	$2.0 * 1990$ actual hydrograph
5	$3.0 * 1990$ actual hydrograph
6	1989 actual hydrograph
7	$0.85 * 1989$ actual hydrograph
8	$0.75 * 1989$ actual hydrograph
9	$0.50 * 1989$ actual hydrograph

The result of simulation plotted on Figure J.2.7 is shown below. And correlation of peak water level of three stations and its time lag of April/May flood and May/June flood are also shown on the same figure for reference.



Correlation Analysis of Glencourse and Nagalagam St.



Correlation Analysis of Hanwella and Nagalagam St.

▲ Simulation Result ■ Floods in 2008

Figure J.2.7 Comparison with Simulation Result

Correlation of peak water level at Glencourse and Nagalagam St. are far above approximated line. One reason is that the storage effect of flood plain is not estimated properly (there is a possibility of overrated.), and inflow from the river basin at downstream of Glencourse is not counted. Correlation of peak water level at Hanwella and Nagalagam St. are also above approximated line, but difference is not so much. It can be said that this is because the distance between two stations is short and the effect of storage and inflow is small.

Although there is an advantage for the simulation to be able to conduct various kind of calculation easily, reliability of the simulation result will be low without preparing the simulation model based on the detailed topographical data, cross section data, and enough hydrological data, etc. If the warning criteria is defined based on the above simulation result, water level at downstream will be underestimated, and this is dangerous. Since a lot of analysis like correlation analysis can be done by using actual data, continuous monitoring of hydrological data is important. Accumulation of monitored data will also help improving the accuracy of simulation model.

J.3 Warning Criteria for Ratnapura

J.3.1 General

Flood in Ratnapura shall be forecasted by correlating the rainfall amount at upstream and water level at downstream. There are several methods for forecasting such flood like in Ratnapura such as using daily rainfall, hourly rainfall, and simulation. Methods shall be selected according to the availability of data.

Warning criteria shall be defined as the rainfall amount at upstream station to forecast the target water level at downstream. And the water level can be also defined as the warning criteria by studying rate of rising of water level.

Location of Ratnapura gauging station and main rainfall stations at upstream of Kalu river basin is shown below. Target water level is Minor Flood level 6m (about 19 feet) at Ratnapura gauging station. (Regarding the water level 6m, there is a report saying that inundation occurs below this water level in the actual situation. Therefore, target water level can be modified according to further study.)




Figure J.3.1 Location of Monitoring Stations at Upstream of Ratnapura

J.3.2 Method by Daily Rainfall

Water level data at Ratnapura gauging station were collected to study warning criteria for Ratnapura. The following Table shows the annual maximum water level from 1981 to 2005. Hourly water level data and daily rainfall data for 17 floods that exceed the water level 6m (19 feet) were collected.

Table J.3.1 Annual Maximum Water Level at Ratnapura gauging station

Year/Month		Water Level (feet)	Year/Month		Water Level (feet)	Year/Month		Water Level (feet)
1981	9	22.0	1991	7	18.8	2001	9	14.3
1982	6	28.3	1992	6	22.0	2002	6	19.8
1983	6	14.0	1993	10	27.8	2003	5	33.2
1984	7	24.9	1994	5	15.6	2004	5	17.8
1985	6	23.3	1995	10	23.5	2005	9	22.6
1986	10	20.0	1996	6	23.0			
1987	6	12.9	1997	8	22.8			
1988	6	26.5	1998	9	20.8			
1989	5	37.0	1999	4	27.0			
1990	5	24.2	2000	6	16.4			


Target rainfall gauging stations are five stations such as Hapugastenna, Lellopitiya, Alupolla, Ratnapura, and Wellandura at the upstream of Ratnapura. One day rainfall amount and two days rainfall amount that will affect the peak water level at Ratnapura for selected 17 floods are shown in the Table below.

Table J.3.2 1 day and 2 days rainfall amount at selected stations


Year	Month	Maximum Waterlevel (feet)	Hapugastenna		Lellopitiya		Alupolla		Ratnapura		Wellandura	
			1day Rainfall	2days Rainfall								
1989	5	37.0	242.6	437.7	119.0	349.0	149.0	457.0	29.1	126.7	59.9	145.5
1989	5	28.0	182.3	298.9	137.0	207.5	140.0	236.0	220.1	323.1	0.0	66.6
2003	5	33.2	156.0	302.5	68.0	257.0	102.0	288.2	99.6	444.8	77.2	343.9
1982	6	20.0	173.0	202.2	120.8	163.9	92.7	158.5	128.8	160.3	—	—
1982	6	28.3	59.7	292.1	56.4	231.1	31.0	205.2	38.3	189.3	—	—
1993	10	27.8	140.7	288.0	68.3	248.3	78.8	182.7	61.2	238.8	59.2	118.1
1999	4	27.0	145.3	244.9	152.5	258.5	94.1	195.3	232.3	353.0	33.5	110.9
1988	6	22.3	181.6	238.5	110.0	228.0	175.0	234.0	34.8	92.0	—	—
1988	6	26.5	165.9	312.7	7.8	11.2	148.0	275.0	243.6	312.5	—	—
1984	7	24.9	185.9	239.0	82.0	132.5	88.4	106.2	91.8	130.2	—	—
1990	5	24.2	7.1	253.7	67.0	248.6	7.2	193.5	23.6	91.5	12.2	79.5
1995	10	23.5	124.5	257.3	91.6	169.6	87.5	175.2	124.5	186.5	18.1	113.4
1985	5	23.3	39.4	184.9	46.8	174.8	15.7	83.8	62.5	177.1	—	—
1985	6	20.9	120.7	181.7	26.5	67.0	52.1	102.9	96.1	135.9	—	—
1996	6	23.0	3.3	3.3	0.0	152.4	1.5	86.9	3.1	395.6	0.0	51.8
1997	8	22.8	12.7	102.9	18.5	48.0	16.1	29.2	2.1	25.8	—	—
2005	9	22.6	59.0	313.0	79.0	180.9	56.0	171.0	64.5	119.1	9.3	52.2
1981	9	22.0	129.5	171.6	141.2	166.6	121.9	153.4	108.5	133.1	—	—
1992	6	22.0	194.3	207.5	133.0	167.1	104.0	119.1	141.8	153.2	61.2	65.3
1998	9	20.8	9.7	50.3	43.1	99.1	26.2	113.2	22.5	69.4	26.7	47.3
1986	10	20.0	105.7	176.3	108.9	168.9	100.8	177.0	95.2	157.8	—	—

The correlation between one day rainfall and two days rainfall, and peak water level at Ratnapura is shown in the figure below.


Hapugastenna



Lellopitiya



Alupolla



Rathnapura




Figure J.3.2 Relation of Rainfall Amount and Water Level in Ratnapura

In case of one day rainfall, the correlation with the water level is not high at any stations. On the other hand, in case of two days rainfall, correlation with the water level is relatively high especially at Hapugastenna station. Three floods that show the low correlation can be eliminated as the exceptional cases. One flood among three is that 400mm/day rainfall amount is monitored at Ratnapura station. The data for other two floods have lack credibility.

According to the result of above study, it can be said as the flood forecasting;

“There is a possibility of Minor Flood (more than 6 m) when the rainfall amount for 2 days exceeds 170mm at Hapugastenna rainfall gauging station.”

And it is also possible to predict the water level from rainfall amount by using approximated line even though the accuracy is not high.

The following Table shows the number of rainfall event that exceed the rainfall amount 170 mm /2 days at Hapugastenna.

Table J.3.3 Number of Rainfall event that exceed the rainfall amount 170 mm/2 days

Year	Number of Event	Year	Number of Event	Year	Number of Event
1981	3	1991	0	2001	1
1982	11	1992	8	2002	3
1983	1	1993	10	2003	3
1984	7	1994	1	2004	0
1985	8	1995	4	2005	2
1986	1	1996	0		
1987	0	1997	3	average	3.88
1988	9	1998	3		
1989	9	1999	5		
1990	4	2000	1		

The number of rainfall event that exceed 170 mm/2 days is about 4times/year. This number is appropriate for issuance of early warning. Therefore, warning level by daily rainfall data is defined as follows.

Table J.3.4 Warning Level for Flood in Ratnapura (based on daily rainfall)

Monitoring	Warning Level	Available Time
Rainfall	170 mm / 2 days at Hapugastenna Station	—

J.3.3 Method by Rate of Rising of Hourly Water Level

Next table shows the rate of rising at each stage such as 3 to 6 m (10 to 19 feet), 6 to 8 m (19 to 24 feet), and 8 to 12 m (24 to 36 feet). DOI starts close monitoring at 3m. 6m is the minor flood level, 8m is the medium flood level and 12m is the major flood level. It is shown that it takes at least four hours from 3 to 6 m, three hours from 6 to 8 m, and 11 hours from 8 to 12 m from the actual data for past 25 years.

According to the result of this study, it takes minimum four hours and average 10 hours from 3 to 6 m .

Table J.3.5 Rate of Rising

Year	Month	Maximum Waterlevel (feet)	Rate of Rising														
			10–19feet					19–24feet					24–36feet				
			a ft	b ft	c hrs	d ft/hr	e hrs	a ft	b ft	c hrs	d ft/hr	e hrs	a ft	b ft	c hrs	d ft/hr	e hrs
1989	5	37.0	10.6	19.4	13	0.7	13	19.4	24.2	4	1.2	4	24.2	36.0	16	0.7	16
1989	5	28.0	11.1	19.9	12	0.7	12	19.9	24.7	4	1.2	4	24.7	28.0	3	1.1	11
2003	5	33.2	10.5	19.0	7	1.2	7	19.0	24.7	10	0.6	9	24.7	32.5	24	0.3	37
1982	6	28.3	10.2	19.5	7	1.3	7	—	—	—	—	—	—	—	—	—	—
1993	10	27.8	10.1	19.5	13	0.7	12	19.5	24.0	13	0.3	14	24.0	27.8	14	0.3	44
1999	4	27.0	10.1	19.8	8	1.2	7	19.8	24.7	5	1.0	5	24.7	27.0	5	0.5	26
1988	6	26.5	10.0	19.3	9	1.0	9	19.3	22.3	12	0.2	20	—	—	—	—	—
1984	7	24.9	10.8	16.6	5	1.2	8	20.0	24.0	7	0.6	9	—	—	—	—	—
1990	5	24.2	13.8	19.8	4	1.5	6	19.8	24.2	6	0.7	7	—	—	—	—	—
1995	10	13.4	10.7	13.4	6	0.5	20	19.1	23.5	19	0.2	22	—	—	—	—	—
1995	10	23.5	11.8	19.1	18	0.4	22	19.1	23.5	19	0.2	22	—	—	—	—	—
1985	6	23.3	10.8	19.5	9	1.0	9	19.5	23.3	9	0.4	12	—	—	—	—	—
1996	6	23.0	12.1	19.3	3	2.4	4	19.3	23.0	6	0.6	8	—	—	—	—	—
1997	8	22.8	10.3	19.3	6	1.5	6	19.3	22.8	3	1.2	4	—	—	—	—	—
2005	9	22.6	10.0	19.2	18	0.5	18	19.2	22.6	6	0.6	9	—	—	—	—	—
1981	9	22.0	10.5	19.6	6	1.5	6	—	—	—	—	—	—	—	—	—	—
1992	6	22.0	10.2	19.5	7	1.3	7	19.5	22.0	5	0.5	10	—	—	—	—	—
1998	9	20.8	10.3	19.3	8	1.1	8	19.3	20.8	1	1.5	3	—	—	—	—	—
1986	10	20.0	10.7	18.2	7	1.1	8	—	—	—	—	—	—	—	—	—	—

a: water level from, b: water level to, c: actual duration from a to b, d: rate of rising, e: calculated duration

: minimum time

Therefore, warning level by rate of rising of water level is defined as follows.

Table J.3.6 Warning Level for Flood in Ratnapura (based on rate of rising)

Monitoring	Warning Level	Available Time
Water level	3.0m at Ratnapura Station	4 – 10 hours

J.3.4 Method by Hourly Rainfall

In the case for April/May flood in 2008, rainfall amount at Asoka Estate for two hours from 7:00am to 9:00am recorded 116 mm and the water level at Ratnapura increased from 2.9 m at 8:00am to 6.0 m at 10:00am. It took only two hours from 3 to 6 m and this is the minimum time in past 28 years. Manual monitoring of daily rainfall is conducted at every morning once a day, and daily rainfall means the 24 hours rainfall from 9:00am to 9:00am next day. (8:30am to 8:30am for DOM) Therefore, if such a torrential rainfall occurs during midnight, this rainfall event can not be known and flood can not be forecasted.

At present, there are only two rainfall gauge stations at the upstream of Ratnapura where the hourly rainfall is monitored, Ratnpaura station operated by DOM and Asoka Estate station consigned by DOI. Relation of cumulative rainfall and water level is analyzed in the following Figure. “24 hours” is selected as the duration for accumulation, because the flood in Ratnapura is depending on the rainfall amount for about 24 hours according to the size of watershed of upstream of Ratnapura.

Horizontal line shows the 24 hours cumulative rainfall amount at Ratnapura and Asoka Estate that changes every hour, and vertical line shows the water level at Ratnapura.




Figure J.3.3 Result of Simulation

24 hours cumulative rainfall when the water level at Ratnapura gauging station reached 6 m is summarized below.

Table J.3.7 24 Hours Cumulative Rainfall at Flood Time

Flood	24 hours cumulative rainfall (mm)	
	Ratnapura	Asoka Estate
April to May	100 mm	200 mm
May to June	200 mm	200 mm
July	170 mm	175 mm

100 mm rainfall for 24 hours at Ratnapura station seems small compared from other rainfall amounts, therefore the warning level by the analysis of the hourly rainfall is defined two levels as follows. However the accuracy will not be high since the number of samples is not enough.

Table J.3.8 Warning Level for Flood in Ratnapura (based on hourly rainfall)

Monitoring	Warning Level	Available Time
Rainfall	Advisory level: 100 mm / 24 hours at any station	—
Rainfall	Warning level: 170 mm / 24 hours at any station	—

J.3.5 Method by Simulation

24 hours rainfall amount by which the water level at Ratnapura station will exceed 6m was analyzed by using MIKE 11 run-off simulation model prepared in component 1.

24 hours rainfall amount at Hapugastenna station, where automatic rainfall gauge with telemeter system was installed by pilot project, was changed from 100 to 200 mm (five cases per 25 mm), and averaged rainfall amount in the upstream basin of Ratnapura is calculated. The water level at Ratnapura was calculated from this averaged rainfall amount. Result is shown below.




Figure J.3.4 Result of Simulation

It can be said that if 24 hours rainfall amount exceeds 170mm at Hapugatstenna station, water level at Ratnapura will exceed 6 m.

Additionally, regarding the case for 24 hours rainfall amount: 175 mm, the difference of rate of rising of water level was analyzed between the case if it rains 17.5mm for 24 hours uniformly, and the case if it rains 175 mm in three hours.




Figure J.3.5 Comparison of Rate of Rising

Therefore, warning level by simulation is defined as follows.

Table J.3.9 Warning Level for Flood in Ratnapura (based on simulation)

Monitoring	Warning Level	Available Time
Rainfall	170mm / 24hours at Hapugastenna station	2 – 6 hours

J.3.6 Warning Criteria for Flood in Ratnapura

Warning criteria shall be defined by taking the above results into consideration in a comprehensive manner. Here, 24 hours cumulative rainfall amount: 150 mm at any stations in upstream basin of Ratnapura is defined as the warning criteria for flood in Ratnapura. This is because 170 mm/24 hours is too critical to issue warning from the experience of 2008 flood. And, since the water level at Ratnapura increases from 3m to 6m in two hours by the simulation as well as in the April /May flood, warning issuance is necessary when the water level reaches 3m, despite of cumulative rainfall amount.

Therefore, “Advisory” shall be issued when the 24 hours cumulative rainfall amount exceeds 100 mm at any stations, and “Warning” shall be issued when the water level reaches 3 m, or the 24 hours cumulative rainfall amount exceeds 150 mm at any stations.

Table J.3.10 Warning Criteria for Minor Flood at Ratnapura

Level	Criteria
Advisory	Rainfall amount is 100 mm within 24 hours at any stations
Warning	Rainfall amount is 150 mm within 24 hours at any stations or Water Level is 3.0 m at Ratnapura gauging station

If these warning criteria are applied to the three actual floods in 2008, timing of issuing warning will be estimated as follows.

Table J.3.11 Timing of Issuing Flood Warning based on Warning Criteria
and the Time of Minor Flood Occurrence

Level	April/May	May/June	July
Advisory	8:00am	23:00pm	19:00pm
Warning (water level)	9:00am	2:00am	20:00pm
Warning (rainfall)	9:00am	4:00am	20:00pm
Occurrence of Flood	10:00am	18:00pm	23:00pm

It can be said that all three floods can be forecasted by using proposed warning criteria. However only one hour is available for the case of April/May flood, therefore more collection of hourly rainfall data and analysis on the relation between the hourly rainfall and water level at Ratnapura is necessary to upgrade the warning criteria.

J.4 Warning Criteria for Sediment Disaster

In Japan there are several methods to determine the critical rainfall for sediment disaster at present. Among them, Guideline Method called Method “A” is the most simple method based on the past disaster records and rainfall amount at the time of disaster. Basically, the method “A” is applied only for the debris flow, since the landslide can not be forecasted only by the rainfall amount. However, only rainfall amount can be the bench mark for forecasting landslide in Sri Lanka at present, and local people can manage this method

by themselves if properly instructed, the method “A” can be utilized for defining one of the warning criteria for landslide in Sri Lanka.

The following Figure is a schematic image of the critical line. The rainfall index is expressed by a combination of the rainfall intensity and the total rainfall (cumulative rainfall). As shown in the figure, the rainfall intensity is shown in the ordinate (Y-axis) and the total rainfall in the abscissa (X-axis). Debris flow causing rainfall and non-causing rainfall are plotted in the figure by the different symbols. Then, those two rainfall groups are separated with a linear line or a curved line descending to the right. This boundary line is called the Critical Line (CL) which distinguishes the occurrence and non-occurrence of a debris flow. The lower left side of this line is the safe zone where a debris flow may not be caused. The upper right side of this line is the unsafe zone where a debris flow may be caused. The definitions of plotted rainfall values are explained in the Table below.




Figure J.4.1 Concept of Critical Line

Table J.4.1 Definitions of Rainfall Indexes

	X axis (abscissa)	Y axis (ordinate)
Causing Rainfall	Cumulative rainfall up to 1 hour before the occurrence of debris flow	1 hour rainfall immediately before the occurrence of debris flow
Non-causing Rainfall	Cumulative rainfall up to before the start of a maximum hourly rainfall	Maximum hourly rainfall in a series of rain

Methods for setting the rainfall criteria for issuing warning and evacuation instruction are explained below. The line indicating the rainfall criteria for warning is called “Warning Line (WL)” and the line indicating the rainfall criteria for evacuation is called “Evacuation Line (EL)”.

Before setting the WL and the EL, it is necessary to determine the timing to give warning and evacuation instruction. It means that how many hours before the forecasted occurrence time warning or evacuation instruction should be given, so that people as well as the related organizations can take necessary actions for safety. After that the WL and EL are set in consideration of an estimated rainfall during the leading time. Table shown below shows the conditions used in the “Method A” in Japan.

Table J.4.2 Definitions of Timing for Warning and Evacuation

	Timing	Forecasted Rainfall during leading time
Warning Issuance	2 hours before reaching the CL	Past maximum 2 hours rainfall (R_{H2M})
Evacuation Instruction	1 hours before reaching the CL	Past maximum 1 hour rainfall (R_{H1M})




Figure J.4.2 Concept of Warning Level and Evacuation Level

J.5 Samples of Warning Message

Regarding the contents of warning message, the timing of issuance and necessary contents are recommended in the Main Report as follows.

Table J.5.1 Timing of Issuance and Contents of Warning (Flood)

Category	Timing of Issuance	Necessary Contents
Advisory	- Issued by DOI when rainfall amount or water level exceeds the warning criteria (advisory)	- List of Areas to be inundated, estimated time and inundation depth - "wait for next information"
Warning	- Issued by DOI when rainfall amount or water level exceeds the warning criteria (warning) - Warning shall be updated according to new information	- List of Areas to be inundated, estimated time and inundation depth - "follow the instruction by GA"
Evacuation Instruction / Order	- Issued by GA based on the result of District DM Committee Meeting.	- List of Areas to be inundated, estimated time and inundation depth - Evacuation instruction / order
Cancellation of warning	- Issued by DOI when the water level decreases below flood level and water level of upstream decreases below warning criteria.	- Cancellation of warning
Cancellation of evacuation instruction / order	- Issued by GA based on the result of District DM Committee Meeting.	- Cancellation of evacuation instruction / order

Table J.5.2 Timing of Issuance and Contents of Warning (Landslide)

Category	Timing of Issuance	Necessary Contents
Advisory	- Issued by NBRO when rainfall amount exceeds 100mm/24hours	- List of DS covered by rain gauge station exceeds warning criteria - "wait for next information"
Warning	- Issued by NBRO when rainfall amount exceeds 150mm/24hours - Warning shall be updated according to new information	- List of DS covered by rain gauge station exceeds warning criteria - "follow the instruction by GA"
Evacuation Instruction / Order	- Issued by GA based on the result of District DM Committee Meeting.	- List of DS and GN covered by rain gauge station exceeds warning criteria - Evacuation instruction / order
Cancellation of warning	- Issued by NBRO when the rainfall stopped for certain time.	- Cancellation of warning
Cancellation of evacuation instruction / order	- Issued by GA based on the result of District DM Committee Meeting.	- Cancellation of evacuation instruction / order

Table J.5.3 Timing of Issuance and Contents of Warning (Tsunami)

Category	Timing of Issuance	Necessary Contents
Advisory	- Issued by DOM when earthquake occurs which can generate Tsunami	- Time, place and magnitude of earthquake - "wait for next information"
Warning	- Issued by DOM when coast of Sri Lanka is forecasted to be affected by tsunami - Warning shall be updated according to new information such as actual monitoring of tsunami at other countries	- Estimated arrival time of tsunami - "follow the instruction by GA"
Evacuation Instruction / Order	- Issued by GA when "Tsunami Warning" is issued by DOM	- Estimated arrival time of tsunami - Evacuation instruction / order
Cancellation of warning, evacuation instruction / order	- Issued by DOM and GA when PTWC and JMA cancelled their warnings	- Cancellation of warning, evacuation instruction / order

In this Chapter, the samples of warning message for each disaster are shown below. The message shall be simple and easily understandable for people to avoid any misunderstanding. Necessary actions shall be also indicated. The message shall be prepared by Sinahara and Tamil.

Flood Warning for Kelani River														
Issued by DOI at 17:15 on April 28 th														
1. Present Water Level at 17:00 on April 28 th														
<table border="1"> <thead> <tr> <th>Station</th> <th>Water level</th> <th>Situation</th> </tr> </thead> <tbody> <tr> <td>Glencourse</td> <td>54.9 ft</td> <td>below minor flood but increasing</td> </tr> <tr> <td>Hanwella</td> <td>4.7m</td> <td>below minor flood but increasing</td> </tr> <tr> <td>Nagalagam St.</td> <td>4.1ft</td> <td>below minor flood but increasing</td> </tr> </tbody> </table>			Station	Water level	Situation	Glencourse	54.9 ft	below minor flood but increasing	Hanwella	4.7m	below minor flood but increasing	Nagalagam St.	4.1ft	below minor flood but increasing
Station	Water level	Situation												
Glencourse	54.9 ft	below minor flood but increasing												
Hanwella	4.7m	below minor flood but increasing												
Nagalagam St.	4.1ft	below minor flood but increasing												
2. Flood Forecasting														
Minor Flood at Nagalagam St. (5.0ft) is expected at 20:00 on April 28 th .														
3. Expected Inundation Area														
Warning: Biyagama DS, Hanwella DS														
Alert: Colombo DS, Kolonnawa DS, Kelaniya DS														
4. Instruction														
Warning: Please follow the instruction by GA.														
Alert: Please wait for next information														

Figure J.5.1 Sample of Message (Flood Warning)

Landslide Warning														
Issued by NBRO at 9:30 on April 29 th														
1. Present Rainfall Amount at 9:00 on April 29 th														
<table border="1"> <thead> <tr> <th>Station</th> <th>27th</th> <th>28th</th> </tr> </thead> <tbody> <tr> <td>Kitulgala</td> <td>102.2mm</td> <td>160.1mm</td> </tr> <tr> <td>Ratnapura</td> <td>71.8mm</td> <td>159.9mm</td> </tr> <tr> <td>Hapugastenna</td> <td>147.0mm</td> <td>182.0mm</td> </tr> </tbody> </table>			Station	27 th	28 th	Kitulgala	102.2mm	160.1mm	Ratnapura	71.8mm	159.9mm	Hapugastenna	147.0mm	182.0mm
Station	27 th	28 th												
Kitulgala	102.2mm	160.1mm												
Ratnapura	71.8mm	159.9mm												
Hapugastenna	147.0mm	182.0mm												
2. Weather Forecasting														
More rainfall is expected around Sabaragamuwa Province next several hours according to DOM.														
3. Vulnerable Area for Landslide														
Warning: Aaaa DS, Bbbb DS, Cccc DS														
Alert: Dddd DS, Eeee DS, Ffff DS														
4. Instruction														
Warning: Please follow the instruction by GA.														
Rainfall amount for Aaaa DS is exceeding critical level														
Alert: Please wait for next information														

Figure J.5.2 Sample of Message (Landslide Warning)

Tsunami Warning

Issued by DOM at 17:00 on September 12th

1. Information from PTWC at 16:45 on September 12th

- Earthquake occurred at 16:40 at South Sumatra, Indonesia
- Magnitude is 8.2
- Tsunami can be generated
- Estimated tsunami arrival time is as follows.

Dondra Head 20:17

Trincomalee 20:32

Colombo 20:45

Jaffna 21:55

2. Instruction

There is enough time for evacuation. Please follow the instruction by GA.

Figure J.5.3 Sample of Message (Tsunami Warning)

Supporting Report K

Result of Interview Survey

Supporting Report K Results of Interview Survey

K.1 General

An actual “Tsunami warning” was issued due to earthquake at Indonesia and an actual flood disaster occurred due to heavy rainfall during this Study. These actual events were reviewed from the point of EWE system and issues and lessons were raised for system development in the main report. To obtain data for the review of the activities conducted by local people, interview surveys for both events were conducted. The results of these interview surveys are discussed in this chapter.

K.2 Tsunami Warning on 12th and 13th September 2007

K.2.1 Background

Due to an earthquake occurred in South Sumatra, Indonesia, the tsunami warning was issued in Sri Lanka on September 12 and 13, 2007. The questionnaire survey was designed and conducted to understand the information dissemination process from the government level to the people’s level after this occasion.

Timeline of Tsunami Warning

Information related to tsunami watch was issued by PTWC (Pacific Tsunami Warning Center) and the information was informed to DOM. Based on this information, DOM issued Tsunami Warning/Evacuation Instruction in Sri Lanka.

On September 12, the earthquake of M.8.2 occurred in South Sumatra, Indonesia at 16:40¹⁾. PTWC issued the tsunami watch at 16:45, estimated there is a possibility of tsunami in Sri Lanka around 20:00 to 21:00 (at 20:17 in Dondra Head in Matara, 20:32 in Trincomalee, 20:45 in Colombo and 21:55 in Jaffna). Based on the tsunami watch, DOM issued the tsunami warning at 17:20 and evacuation instruction at 18:30. Before issuing the tsunami warning officially by DOM, the local media broadcasted the tsunami information based on the PTWC’s tsunami watch. DMC and Police officially received the evacuation instruction by Fax at 18:38. At 20:30, DOM cancelled evacuation instruction and DMC and police received a cancellation of tsunami warning at 20:40.

On September 13, an earthquake of M.7.8 occurred in South Sumatra, Indonesia at 05:19. DOM issued the tsunami warning at 06:10 and police received a Fax at 06:11. DOM cancelled tsunami warning at 9:00 and police received a cancellation of tsunami warning at 09:50. There was no media broadcasting regarding tsunami information.

Table K.2.1 shows the situation of tsunami warning in chronological order, which was issued from the occurrence of earthquake to cancellation of tsunami warning.

Table K.2.1 Information Related to Tsunami Warning on 12th and 13th September

Time	Situation
12th Sep. 16:40	Occurrence of Earthquake in South Sumatra, Indonesia (M8.2)
16:54	PTWC issued Tsunami Watch (Tsunami Bulletin No.1)
17:01	DOM received Tsunami Bulletin No.1 from PTWC by e-mail, FAX, and GTS
17:09	DOM informed to MDMHR and DMC by telephone and made discussion for next action

¹⁾ : All the time mentioned in this section are local time in Sri Lanka.

Time	Situation
17:20	DOM issued Tsunami Warning
17:21	DMC and Police Command Centre received Tsunami Warning by Fax. Police started to take actions assuming the Tsunami Warning as Evacuation Instruction
18:30	DOM issued Evacuation Instruction
18:38	DMC and Police Command Centre received Evacuation Instruction by FAX
20:30	DOM cancelled Evacuation Instruction
20:35	Tsunami Bulletin Final by PTWC: Tsunami Watch was cancelled
20:41	DMC and Police Command Centre received the cancellation of Evacuation Instruction by FAX. But Evacuated people had started to return home before this issuance
13th Sep. 5:19	Occurrence of Earthquake in South Sumatra, Indonesia (M7.8)
5:31	PTWC issued Tsunami Watch. Sri Lanka is out of the issued area
6:10	DOM issued Tsunami Warning
6:11	Police received FAX
8:32	Tsunami Bulletin Final by PTWC: Cancellation of Tsunami Watch
9:00	DOM cancelled Tsunami Warning
9:50	Police received FAX

K.2.2 Questionnaire Survey on Tsunami Warning

(1) Survey Method

Questionnaire sheet was distributed to DDMCU in 5 districts (Galle, Hambantotha Kalthara, Mathara and Ampara) through Mrs. Inburana of DMC. Each district was asked to select total of 40 persons from two divisions (20 person from each division) to answer the questionnaire.

Total number of samples collected was 150. Ampara district did not return any questionnaire. Among 150 samples, there were two questionnaires sheets without name of division. Since the analysis is based on the district level, these questionnaire sheets are counted as a part of total samples in belonging district.

The officers in district conducted the questionnaire using face-to-face interview method.

(2) Survey Duration

The survey was conducted from 28th September to 31st December 2007.

(3) Location and Sample Number

The details of sampling location and number are shown below.

Table K.2.2 Location and Number of Samples Collected in Each District

District/ Total Sample	Galle	40	Hambantotha	40	Kalthara	20	Mathara	50
Division (Sample No.)	Deweta	8	Hambantotha	18	Beruwala	9	Gandara- Devinuwara	23
	Hikkaduwa	20	Hambantotha-E	2	Kalthara	10	Paburana	2
	Katugoda	8	Kudawella-S	7			Paramulla	4
	Siybalagohawaththa	1	Kudawella-W	7			Thotamana	21
	Vijitharama	1	Madaketiya	6				
	No answer	1			No answer	1		

E=Eastern, S=Southern, W=Western

(1) Contents of Questionnaire

The questionnaire has seven sections with 50 questions in which consists of multiple choices and write in type questions. Major questionnaire items are shown below. The original text of questionnaire is attached in the end of the text.

1. General Information of Interviewee Sex, age, occupation, address	5. Hazard Map and Evacuation Exercise Recognition of hazard map Usefulness of hazard map Participation to evacuation exercise Usefulness of hazard map
2. Tsunami Warning on September 12 Time of tsunami warning, Source of Tsunami warning Contents of tsunami warning	6. Other Information about Tsunami Warning Number of tsunami warning received Time and information source of tsunami warning Reaction to tsunami warning
3. Evacuation Location of evacuation Means of transportation Information about evacuation place Reason of evacuation	7. Other Line availability of mobile phone Confusion in evacuation
4. Cancellation of Tsunami Warning Time of cancellation of tsunami warning Source of cancellation of tsunami warning Contents of cancellation of tsunami warning	

K.2.3 Result of Questionnaire Survey

(1) Basic information about interviewee

Among the total of 150 samples, gender distribution was “male (85 samples)”, “female (50 samples)” and “no answer (15 samples)”.

About age distribution, interviewees age was concentrated in “30s (27 samples)”, “40s (41 samples)”, “50s (30 samples)” with small number of “below 20s (3 samples)”, “20s (14 samples)”, “60s (11 samples)” and “no answer (24 samples)”.

Current occupation of interviewees were “fishery (37 samples)”, “housewife (26 samples)”, “merchant (24 samples)”, “company employee (14 samples)” and “civil officer (8 samples)” are the major answer.

The distance from the coastal line to current residence was asked. Among 150 samples, interviewees answered that about 43% live in “0 to 100 m” and 46% live in “100-500 m” (Q1.6). This result shows that about 90% of interviewees live in less than 500 m from the coastal line at present. Many interviewees live in close to coastal line after the tsunami experience in 2004.




Figure K.2.1 Distance from Coastal Line to House

Among 150 samples, about 93% (138 samples) of interviewees were affected by the tsunami in 2004 (Q1.7). Among those who were affected, the house damage was “totally destroyed (39%)”, “half destroyed (36%)”, “partially destroyed (9%)” as shown in Figure (continue Q1.7).

(2) Time and Tools of Tsunami Warning on September 12, 2007

PTWC issued 1st tsunami watch at 16:54 and DOM at 17:20. All the interviewees received tsunami warning and 87% of interviewees received tsunami warning before 18:00, about 60 minutes after the tsunami watch by PTWC and 30 to 40 minutes after DOM’s tsunami warning. On the other hand, 13% of interviewees answered that they received the information after 18:00.




Figure K.2.2 Time of Receiving the Tsunami Warning

Since the expected time of tsunami arrival in the coast of Sri Lanka is around 20:00 to 21:00, it is considered that people in the community had enough time to evacuate with current situation.

The source of tsunami warning was asked in Q 2.2 and interviewees could give multiple answers, and the result is shown below.

Table K.2.3 Source of Tsunami Warning

Item	Answer	Percentage
TV	102	68%
Radio	65	43%
Speaker	42	28%
Neighbors	40	27%
Family	28	19%
Friends	28	19%
Community Leader	22	15%
Police	20	13%
Telephone	18	12%
Internet	2	1%
Others	14	9%

This result shows that many interviewees received tsunami warning by TV or/and Radio. In addition to the media information, they received tsunami information from public such as “Speaker” or “Police” and from family or community but their answers were limited to about 10 to 20%.

According to the comments on the interview sheets, most of interviewees trusted information provided by the media rather than government. However, many of interviewees received information

from speaker and/or other public sources, therefore, several methods have to be established to disseminate warnings.

When this result was analyzed by district level, no clear differences between districts are observed. However, interviewees in Mathatara and Hambantotha received information from various sources while interviewees in Kalutara answered that they received information only from media. The reason should be analyzed further but level of understandings and quality of interviewer might influence the result.

(3) Contents and Sources of Tsunami Warning on September 12, 2007

The contents of tsunami warning message (information received) could be divided into three levels (Q2.5):

- 1) Earthquake information and instruction to evacuation (85 answers)
- 2) Instruct to be aware of possible tsunami (3 answers)
- 3) Earthquake information in Indonesia (15 answers)

From this result, most of interviewee received earthquake information together with instruction to evacuate to the safe place.

(4) Evacuation Condition after the Tsunami Warning

Among total of 150 samples, 92 % (138 answers) actually evacuated to the safe place. Among who answered that they evacuated, 89% (82 % of total samples) evacuated soon after receiving the tsunami warning (Q3.1).

Among nine interviewees who answered that they did not evacuate soon was asked their reasons. The interviewees answered that “they thought tsunami is not coming soon (4 answers)”.

According to the Q2.1, most of the interviewees replied that they received the information before 18:00, and this means that the information they received was not the evacuation instruction because the instruction was issued at 18:30 by DOM. In Q3.1, more than 80% of the interviewee evacuated soon after they received information. This shows that people in community mostly did not understand the meaning of the information/warning properly.

In Q3.4, place of evacuation was asked. About 40 % answered those public spaces or infrastructures such as school and temple that might be strong or it was the evacuation place in past experience. Also about 23% answered “Small hill”.




Figure K.2.3 Place of Evacuation

The location of schools and temples were not identified in this questionnaire. Major answer of “Other” was “friend or relatives house” which consist of 20% of total sample. From this question, it can be said that people were able to evacuate to safer place because of previous tsunami experience or/and evacuation drill that identified the evacuation place.

Means of evacuation transportation were mostly “On foot” (Q3.5). Figure K.2.4 shows the place of evacuation and means of transportation at the time of tsunami.




Figure K.2.4 Means of Evacuation Transportation

Question was asked about their knowledge of evacuation place prior to tsunami warning with multiple answers (Q3.8). Almost all (95%) of interviewees knew the evacuation place in advance by “Evacuation drill (81%)”. Those who did not know the location of evacuation place answered that “they followed others” or “evacuated to the place based on previous experiences”. From this question, evacuation drill was effective for responding to the actual situation of tsunami warning and for increasing the awareness of the people. Figure K.2.5 shows the reason of knowing about evacuation place.




Figure K.2.5 Knowledge about Evacuation Place

(2) Cancellation of Tsunami Warning

Among total of 139 samples, 96 % (134 answers) returned their house because they received information of “evacuation cancellation” (Q4.2). From this result, it can be said that the most of interviewees received cancellation of tsunami warning. Only less than 3 % of interviewees left the evacuation place before the cancellation of tsunami warning (Q4.1 and Q4.2). The cancellation of

tsunami warning was issued at 20:30 and most of interviewees left the evacuation place around 21:00 to 22:00 after hearing the cancellation of the tsunami warning. Figure K.2.6 shows the time of leaving the evacuation place.




Figure K.2.6 Time of Leaving Evacuation Place

The source of cancellation of tsunami warning was asked with multiple answers in Q 4.4. The major answer was TV. This result shows that all the interviewees received cancellation of tsunami warning mainly from the media but also with several ways that can confirm that disaster information or warning is appropriately transferred and disseminated to people in the community in evacuation place. However, this result shows that the source of information is heavily depended on the media rather than instruction by the organization or verbal communication. Table K.2.4 shows the source of cancellation of tsunami warning.

Table K.2.4 Source of Cancellation of Tsunami Warning

Item	Answer	Percentage
TV	127	86%
Radio	78	53%
Speaker	27	18%
Friends	21	14%
Neighbors	20	14%
Family	19	13%
Community Leader	18	12%
Police	11	7%
Telephone	7	5%
Internet	2	1%
Others	14	9%

In Q4.5, the content of tsunami warning cancellation was asked. The result of message contents could be divided into two levels:

- 1) Inform that emergency situation is over and tsunami will not come to Sri Lanka (76 answers)
- 2) Inform that emergency situation is over and instruct to go home (44 answers)

From this result, most of interviewee received information on “cancellation of tsunami warning” and “end of emergency situation”. Also the result shows that one third (1/3) of interviewees received an instruction to go home together with cancellation of tsunami warning.

(3) Hazard Map and Evacuation Drill

About 60 % of interviewees knew hazard map and among those who knew hazard map saw the hazard map during the evacuation drill (94%) (Q5.2 and Q5.3). Figure K.2.7 shows the knowledge and usefulness of hazard map.




Figure K.2.7 Knowledge and Usefulness of Hazard Map

73% of interviewees had experience of participating the tsunami evacuation drill before (Q5.4). Among those who already knew the evacuation place reached about 91% (cross checked with Q3.7 and Q3.8). Based on this result, it can be said that almost all the participants who attended the evacuation drill could recognize the evacuation place appropriately and hazard map helped them to recognize the geological location of evacuation route and place. Also, All the interviewees who participated in the tsunami evacuation drill answered that “the evacuation drill was useful (100%)”. On the other hand, the main reason of not participating to the evacuation drill was “did not know the drill (56%)” (Q5.6). It can be said that evacuation drill need to be widely informed in the community and the drill is useful for people during the actual evacuation of the disaster.

(4) Tsunami Information and Warning on September 13, 2007

About 82% of interviewees received the tsunami warning issued in the morning of September 13. Compare with the 100% on September 12, 18 points decreased (Q6.3). Also on 12th, 99% of the interviewees received information some kind within about one hour, however, on 13th, only 69% of interviewees received information within one hour. The earthquake was occurred in the early morning on 13th, it might cause delay in disseminating the information, however, in both cases, people had enough time to evacuate based on the estimation of the tsunami arrival. The source of information and tool that used for the information transfer were mostly same in 12th and 13th September.

About 84% of interviewees who heard the 2nd tsunami warning took some kind of action but only 21% actually evacuated even evacuation instruction was not issued by DOM or other government authorities, which is reduced about 71 points from 1st evacuation of about 92% actually evacuated (Q6.4). The reasons need to be further analyzed but the time (early morning), level of warning and 1st day experience might influence the result.

About 53% of interviewees answered that they had some changes of mind from 1st warning to 2nd warning (Q6.5) and said that about 70% of interviewees had negative impression about tsunami

warning answered that “it seems not necessary to evacuate (38%)” followed by “tsunami does not seem to occur (31%)”.

(5) Others/ Comments

Reliable Information Source

The most reliable information source regarding the information transfer and evacuation was asked with multiple answers and about 72% answered “TV” followed by “Radio (59%)” and “Government (43%)” (Q7.2). This result shows that interviewees relied on media rather than government or police. Figure K.2.8 shows the reliable source of information for community people.




Figure K.2.8 Reliable Source of Information

Also, about 80% of interviewees said that there was some confusion. One of major reason of confusion was caused because “information received was different from the actual situation (52%)” (Q7.5). Therefore, people in the community are hoping to receive tsunami or other disaster related information/warning from reliable information source for responding and evacuating from their place.

Telephone Communication

The mobile phone (93%) and landline telephone (82%) was not able to use during the course of tsunami warning (Q7.3 and Q7.4).

Means of Information Dissemination

Many interviewees requested the installation of a siren or a speaker to inform the disaster warning which could be useful at the night. Also many thought that evacuation drill was useful and hoped to continue the practice in the future.

Some interviewees suggested using the bell in the temple, mobile phone at night, and also to make some arrangement to evacuate elders and heavy people.

(6) Summary of the questionnaire survey

Another tsunami was occurred after three years of the Indian Ocean Tsunami in December 2004. The complete system of information transfer and dissemination of tsunami warning to the community was not established yet at that time, however, this survey illustrated that 99% of interviewees received tsunami information/warning and evacuation instruction, and evacuated to the safer place. Almost all

interviewees evacuated to the safe place shows that people's awareness has increased because of the 2004 tsunami experience and some of activities in community such as evacuation drill and hazard mapping which were conducted during these three years.

However, the result also shows that about 50% of people changed their mind from 1st warning and 2nd warning and over 70% had negative impression about tsunami warning. Even though the time and warning level had some influence to their mind and behavior, it is necessary to inform the people that tsunami warning is based on an estimation of possible tsunami and not always tsunami occur, but it is important to take an appropriate action based on the tsunami warning.

K.3 Flood Disaster on April / May and May / June in 2008

K.3.1 Background

Southwestern part of Sri Lanka experienced flood three times in 2008 in the end of April to May (April/May flood), and the end of May to beginning of June (May/June Flood) and the middle of July, and the scale of floods were severe as 2003 flood. This questionnaire survey was designed and conducted to understand the local condition and psychology of the local people at the time of evacuation.

Damage by Flood in April/May and May/June Floods

April/May and May/June Floods caused severe damages such as death and many affected people in the seven districts namely, Colombo, Kalutara, Galle, Kegalle, Gampaha, Ratnapura and Matara. The details of damage by the flood in each district are shown below.

Table K.3.1 Location and Number of Affect People by May/June Floods

Number/District	Colombo	Galle	Gampaha	Kegalle	Mathara	Ratnapura
Affected GN*	11	96	79	3	-	31
Affected Family*	8,164	4,373	8,646	450	1,100	6,685
Affected People*	42,402	-	41,114	1,500	5,600	25,200
Death*	0	1	-	1	1	-

Source: *Daily Mirror (Sri Lanka Newspaper), -No information

K.3.2 Questionnaire Survey on Flood Disaster

(1) Survey Method

Questionnaire sheet was distributed to DDMCU in seven (7) districts (Colombo, Galle, Gampaha, Kalutara, Kegalle, Mathara and Ratnapura.) where were affected by the flood through DMC. Each district was asked to select total of 20 persons from several flood affected area to answer the questionnaire. Not all the DDMCU conducted 20 questionnaires but less. Total number of samples collected was 106 samples.

The officers in district conducted the questionnaire using face-to-face interview method.

(2) Survey Duration

The survey was conducted from July to September 2008.

(3) Location and Sample Number

The details of sampling location and number are shown below.

Table K.3.2 Location and Number of Samples Collected in Each District

No.	District	Sample collected
1	Colombo	24
2	Galle	24
3	Gampaha	13
4	Kalthara	6
5	Kegalle	19
6	Mathara	15
7	Ratunapura	5
	TOTAL	106

(4) Contents of Questionnaire

The questionnaire has seven sections with 50 questions in which consists of multiple choices and write in type questions. Major questionnaire items are shown below.

<p>1. General Information of Interviewee - Sex, age, occupation, distance from river</p> <p>2. The details about flood in May/June - Duration, height, maximum height, damage and frequency of flood, preparedness for flood</p> <p>3. Regarding response before the flood situation - Psychological condition, activity and preparation activity of one day before the flood</p> <p>4. Evacuation Activity - Decision making and psychological condition at the time of evacuation - height of flood and evacuation location</p>	<p>5. Flood Information - Time, contents and information source of flood information and evacuation address - Height of flood at the time of receiving information</p> <p>6. Future Activity - Request for government - Willingness for participating early warning activity</p> <p>7. Proposal for mitigating flood damage</p> <p>8. Other - Comments</p>
---	--

K.3.3 Result of Questionnaire Survey

(1) Basic information about interviewee

Among the total of 106 samples, gender distribution was “male (58%)” and “female (33%).

Interviewee’s age distribution was concentrated in “40s (30%)” and “30s (23%)”.

Current occupation of interviewees were “housewife (19%)”, “merchant (13%)”, “agriculture (11%)” and “unemployed (11%)”.

Their structure of house was also asked to understand their living condition (Q1.5). Majority of interviewees live in “one story house (76%)” and 20% live in “2nd story house”.




Figure K.3.1 House Structure

(2) Flood Condition of April/May and May/June Flood

The highest level of flood experienced either in April/May or May/June was asked. Most of interviewees experienced inundation and over 80% experienced maximum level of flood over “knee” to even “higher than their house” by these floods (Q2.1). Many interviewees experienced flood level of “knee (20%)”, “waist (19%)” and “breast (17%)”.

This result shows how severe these floods were and people actually experienced high level of flood which might put them in danger.




Figure K.3.2 Highest Level of Flood Experienced

The damages by the flood varied but many answered “damaged to furniture (16%)”, “shortage of food and water (13%)” and “damage to food (10%)” (Q2.3). Since majority of people lives in one story house, the flood directly affects their property.

Table K.3.3 Damages by the Flood

Damage	No. of Answer	Percentage
No any damage	9	3%
Family member injured	3	1%
House was totally destroyed	4	1%
House was half destroyed	24	8%
House was partially destroyed	10	3%
Damage to house and shop equipment and facility	13	4%
Damage to commercial products/goods	16	5%

Damage	No. of Answer	Percentage
Damaged to furniture	49	16%
Damage to food	31	10%
No house damage but flooded the floor	19	6%
Work/business was not possible	19	6%
Could not live in the house	19	6%
Furniture was not usable	17	6%
Shortage of food and water	40	13%
Road was flooded and could not move	18	6%
Nothing particularly	2	1%
Other	19	6%
No answer	4	1%
TOTAL	300	

Did they take any preparation measures since people in Sri Lanka faces flood every year? (Q2.6).

About 50% of interviewees answered that they did not take any preparation measures before the flood. Some people participated in several activities like “community workshop (18%)”, “formulation of Disaster Management Committee (14%)”, or/and “community activities (10%)” which include monitoring the rain, preparing a hazard map and/or participating evacuation drill.




Figure K.3.3 Preparation Activities for Flood

(3) Response of People before the Flood

There was a situation that it was raining some days before flood occurred. Questions were asked to understand how people were assessing/assuming their situation and how they felt before the flood.

Question was asked “Did you think that flood is going to happen one day before the flood?” (Q3.2) Over 70% of interviewees thought that there would be a possibility of flood one day before the flood.

Also, over 50% of interviewees felt “very worried” when their feeling about one day before the flood was asked (Q3.3). On the other hand, about 20 % of interviewees were not so much worried about the flood.




Figure K.3.4 Understanding of Situation and Feeling at One Day Before the Flood

The reason of not worry about flood was asked (Q3.4). Although this question was for person who answered “not worry” or “not worry at all”, almost all the interviewees answered this question (Q3.3). This means many interviewees understood this question as a new question but relation to Q3.3 and instruction of questionnaire was not appropriate. Since this question and answer is consider to be important, this question is considered as a separate question and answer from Q3.3. Many interviewees answered that they “thought it wouldn’t be so serious even thought it becomes flood (33%)”, “thought it was a usual rain (20%)” and “thought water would not come until my house (18%)”.

This result shows that people did not worry or did not think flood would occur based on their assumption. Also, people tend to think and judge the situation for their convenience.




Figure K.3.5 Reasons for Not Worry about Flood

(4) Evacuation Activity

About 60% of interviewees evacuated to the safe place at the time of flood (Q4.1). About 20 % of interviewees evacuated when flood level was low like ankle or not inundated. However, over 40% of interviewees evacuated when water level was already at “knee (21%)”, “waist (11%)” and “breast (10%)” or higher (Q4.3).




Figure K.3.6 Evacuation to Safe Place and Height of Water Level at the time of Evacuation

The reason to decide evacuating from their house was asked, “What made you to decide to evacuate?” (Q4.4). The result shows that about 20% of interviewees decided to evacuate because it was already flooded. On the other hand, about 30% evacuated before the flood because they thought that they are going to be in danger (“thought myself and family are in danger (24%)” and “thought house would be flooded (11%)”). Also, some people decided to evacuate because their family or neighbors recommended them to evacuate. In addition, some people heard flood warning or instruction by police and DS officers to evacuate.




Figure K.3.7 Decision Making at the Time of Evacuation

Over 50% of interviewees evacuated to their “family and relative house (69%)”. Others evacuated to “school” or “hill and higher place”. The reason of deciding the evacuation place was mostly based on their “past experience (40%)”, and 25% of people decided based on the community activities.




Figure K.3.8 Evacuation Place and The Reason for Deciding the Evacuation Place

The feelings at the time of evacuation was “worried about children and elderly (16%)”, “Worried about my poverty and belongings at home (15%)” and “felt a fear because it was hard to see the street at night (14%)” (Q4.9). This result shows that many people worried about their family and the vulnerable, at the same time, they worried about their property and belongings at home.




Figure K.3.9 Reception and Contents Flood Information

(5) Flood Information

Questions were asked how flood information was disseminated to people in the community.

About 40% of interviewees received flood information and 20% did not receive flood information (Q5.1).

The content of flood information was about “the river water level will increase (39%)”, “there is a danger of flooding (34%)” and “there is a heavy rain (24%)”.




Figure K.3.10 Reception and Contents Flood Information

About 80% of interviewees received flood information verbally. They also received flood information by other means like “TV”, “Radio”, “phone” or “speakers” but the percentage is low as about 20%. In Colombo, Gampaha and Kaluthara, many people selected “TV” or “radio” as a means of receiving flood information but percentage is about 20% in each district.

About 40% received flood information through “neighbors”, followed by “family (19%)” and “friend (18%)”. Also some people answered “police (9%)” and “government officer (85%)” (Q5.1b).




Figure K.3.11 How and from Who to Get Flood Information

The source of flood information varied and several organizations were listed. Among several organizations, “AGA (18%)” and “police (18%)” had high recognition followed by “meteorology department (14%)”, “DMC (11%)” and “GN (11%)” (Q5.1c).

The height of water level at the time of receiving flood information was “not inundated (39%)” and “water level of river had increased (23%)” followed by “ankle (18%)” and “knee (15%)”.

This result shows that flood information was disseminated when the height of water level is still low or below knee level.




Figure K.3.12 Source of Flood Information and Height of Water Level at the time of Flood Information

Their feeling and thinking at the time of receiving flood information was asked (Q5.1e). Some people were optimistic like “There won’t be a flood risk (22%)” and “nothing special but it is usual rain (11%)” even though they received flood information. On the other hand, some people felt that “there will be a flood risk (17%)” and thinking about next step like “better to evacuate (17%)” or “better to check the neighboring situation (21%)”.




Figure K.3.13 Feeling/Thinking at the time of Receiving Flood Information

(6) Other

Evaluation for Government's Response

People's evaluation of government's response to this flood was asked (Q6.1). About 22% of interviewees answered "there was no or not enough boat (22%)" and "did not receive evacuation instruction (15%)" or "did not receive flood information (12%)".

This result shows that there is a shortage of boats for their evacuation. Also, people wants government to provide food information or evacuation instruction and some also wish to receive information/evacuation instruction earlier.




Figure K.3.14 Evaluation of Government's Response

Ideal Type of Information ,Timing and Informant for Flood Evacuation

A question of "With what kind of information, will you evacuate before flooding? (Q6.2)" was asked. People wants to receive information of "expected river water level (50%)" followed by "predicted amount of rainfall (31%)" and "became flood or not (26%).

About 45% of interviewees want flood information "one day before" and 30% want "6 hours before".

This result shows that people wants to receive flood information at early stage and they want to judge based on estimated or predicted river water level or rainfall in their area.




Figure K.3.15 Type of Information and Timing of Flood Information People Request

About 55% of interviewees think that “GN (55%)” is an appropriate person to give flood information followed by “neighbor (42%)”, “family and relatives (42%)”, “TV (35%)” and “police (32%)”.




Figure K.3.16 From Who People Wants to Receive Flood Information

Proposal of Flood Mitigating Measures

People’s willingness for participating the community based flood mitigation activity was asked (Q6.4). Over 80% of interviewees want to receive early warning information even though flood might not occur.

Also, about 70% of interviewees were willing to participate in community based flood forecasting activity.




Figure K.3.17 Willingness to Receive Flood Information and Participate in Community based Flood Forecasting

Their proposal for mitigating the future disaster was asked. About 50% of interviewees selected “proper instruction of disaster preparedness” for proposed measures for flood mitigation, followed by “supporting service for evacuation (42%)”, “early warning (41%)” and “construction/reinforcement of flood management structures (32%)”.




Figure K.3.18 Proposed Measure for Flood Mitigation

(7) Summary of the questionnaire survey

The two floods in April/May and May/June affected many divisions in Sri Lanka. Many people experienced high level of flooding over knee level to even higher than house level, and had damages to their furniture, food and water and their businesses.

Even though people experience flood almost every year, not many people did prepare for flood and take actions when they were in the situation of flooding or in danger. Many were optimistic about their situation and they assumed that flood would not be very serious or would not come to my house. However, this questionnaire illustrated that over half of interviewees have some kind of recognition/assumption that flood condition would occur one day before the flood and they worried about it.

During April/May and May/June floods, about a little more than half of interviewees received flood information through verbal communication through neighbors or family and friends when flood condition was not serious or not even inundated. In some area, GN or police instructed them to evacuate, therefore, there was an early warning and evacuation system in place in some area. However, the early warning and evacuation needs improvement to disseminate appropriate information to all the people in the community and actually address people to take actions..

For future flood situation, people are expecting the government to give early warning information many hours or one day before the flood for making their decision to evacuate before the flood. On the other hand, people in the community are willing to have some kind of community based measures like observing rainfall or river water level to obtain flood information before the flood.