

HOLDING COMPANY FOR WATER AND WASTEWATER  
(HCWW)  
SHARKIA POTABLE WATER AND SANITATION COMPANY  
(SHAPWASCO)

**THE PROJECT  
FOR  
IMPROVEMENT OF MANAGEMENT CAPACITY  
OF  
OPERATION AND MAINTENANCE FOR SHAPWASCO  
IN THE ARAB REPUBLIC OF EGYPT**

**PROJECT FINAL REPORT  
(MAIN REPORT)**

**NOVEMBER 2009**

**JAPAN INTERNATIONAL COOPERATION AGENCY**

---

**YACHIYO ENGINEERING CO., LTD.**

**GED**

**JR**

**09- 122**

HOLDING COMPANY FOR WATER AND WASTEWATER  
(HCWW)  
SHARKIA POTABLE WATER AND SANITATION COMPANY  
(SHAPWASCO)

**THE PROJECT  
FOR  
IMPROVEMENT OF MANAGEMENT CAPACITY  
OF  
OPERATION AND MAINTENANCE FOR SHAPWASCO  
IN THE ARAB REPUBLIC OF EGYPT**

**PROJECT FINAL REPORT**  
**(MAIN REPORT)**

**NOVEMBER 2009**

**JAPAN INTERNATIONAL COOPERATION AGENCY**

---

**YACHIYO ENGINEERING CO., LTD.**


**Exchange Rate applied in this Report**

*As of November 2009*


US\$ 1.00 = LE 5.43

US\$ 1.00 = JY90.87

LE 1.00 = JPY16.723



**Pilot Project Area for UFW Reduction Activities**



### Model Facilities for SOP Activities

**M & E : Mechanical & Electrical**  
**M : Mechanical only**  
**E : Electrical only**

## Open Seminar



Chairman of HWCC and SHAPWASCO make a speech for opening ceremony at Grand Hyatt Hotel in Cairo.(1<sup>st</sup> Open seminar)  
(Date: Jun. 10, 2007)



Chairman of SHAPWASCO facilitates the 1<sup>st</sup> open seminar.  
(Date: Jun. 10, 2007)



The head of UFW Reduction Team makes a presentation at 1<sup>st</sup> Open seminar.  
(Date : Jun. 10, 2007)



The head of SOP Team makes a presentation at 1<sup>st</sup> Open seminar.  
(Date: Jun. 10, 2007)



The head of UFW reduction team makes a presentation for final achievement and evaluation at 3<sup>rd</sup> Open seminar.  
(Date : Oct. 27, 2009)



The head of SOP team makes a presentation for final achievement at 3<sup>rd</sup> Open and evaluation seminar.  
(Date : Oct. 27, 2009)



## Open Workshop



Presentation by counter part at Military club in Zagazig. (1<sup>st</sup> Open workshop)  
(Date: Nov. 25.26, 2007)



Presentation by counter part at Military club in Zagazig. (1<sup>st</sup> Open workshop)  
(Date: Nov. 25.26, 2007)



The situation of listening to presentation by counterpart. (1<sup>st</sup> Open workshop)  
(Date: Nov. 25.26, 2007)



Discussion with attendance at Military club in Zagazig. (1<sup>st</sup> Open workshop)  
(Date: Nov. 25.26, 2007)



Counterpart makes a presentation of result for water saving campaign at Sharkia Governorate in Zagazig. (2<sup>nd</sup> Open workshop)  
(Date: Dec. 16, 2008)



Attendance asks question of counterpart about UFW reduction activity presentation. (2<sup>nd</sup> Open workshop)  
(Date: Dec. 16, 2008)

## Internal Workshop for UFW



Explanation of project objectives for UFW reduction activity. (Date: Feb. 24, 2007)



Explanation by Egyptian expert for UFW reduction activity. (Date: Feb. 24, 2007)



Presentation by a counterpart (UFW team member) for UFW reduction activity. (Date: Feb. 24, 2007)



Explanation for water meter reading by specialist of Zagazig City in training room. (Date: Jul. 1, 2007)



Presentation of the investigated result in Zagazig City East by head of Zagazig team. (Date: Sep. 11, 2007)



Counterpart takes Japanese Expert's advice at onsite workshop in Zagazig East City. (Date: Sep. 11, 2007)



## Internal Workshop for SOP



Explanation of project objectives for SOP activity.  
(Date: Feb. 26, 2007)



Explanation by Egyptian expert for SOP activity.  
(Date: Feb. 26, 2007)



Presentation by a counterpart for SOP activity.  
(Date: Feb. 27, 2007)



Counterpart explains the importance of coordination between facility operation and water quality control in Abbasa W.T.P.  
(Date: Jun. 25, 2007)



Presentation for well monitoring by head of well monitoring team in training room.  
(Date: Jun. 26, 2007)



Presentation for water quality & process control in training room.  
(Date: Oct. 27, 2007)

## Water Conservation Campaign



Expert and counter part team visit to primary school in Hihya Markaz. (Date: Oct. 24, 2007)



Students at primary school in Hihya Markaz visit to Hihya Water Treatment Plant. (Date: Oct. 28, 2007)



Students answer a questionnaire at junior high school in Ibrahimia Markaz. (Date: Nov. 14, 2007)



Students at junior high school in Ibrahimia Markaz visit to Hihya Water Treatment Plant. (Date: Nov. 19, 2007)

## Joint Coordination Committee



Discussion with member of 1<sup>st</sup> Joint Coordination Committee. (Date: July. 10, 2008)



Signing of completion for project at 6<sup>th</sup> Joint Coordination Committee. (Date : Oct. 27, 2009)



## UFW Reduction Activity(1/3)



The situation of training for C/P at Mostorod Training Center. (Action U1).  
(Date: May.7, 2007)



Minimum night flow survey in Zagazig City East. (Action U2) (Date: Jun. 7, 2007)



Installation of portable flow meter on MNF survey in Zagazig Markaz. (Action U2).  
(Date: Jun. 30, 2007)



Training for GIS operation with Expert at GIS center. (Action U3). (Date: May. 14, 2007)



Exchange of opinions with Jordan UFW Team. (Action U5). (Date: Jul. 14, 2007)



Investigation of meter error in Zagazig City East. (Action U7&8). (Date: Nov. 10, 2007)

## UFW Reduction Activity(2/3)



SHAPWASCO replace to new water meter in Zagazig City East. (Action U7&8).  
(Date: Nov. 12, 2007)



Counter part makes a search for the leak by water leak detector with Head of Hihya UFW team in Hihya Markaz. (Action U11).  
(Date: Nov. 26, 2007)



Counter part makes a search for the leak by acoustic rod in Hihya Markaz. (Action U11)  
(Date: Nov. 29, 2007)



Head of Hihya Team and UFW team investigate at midnight in Hihya Markaz. (Action U11)  
(Date: Dec. 5, 2007)



Counter part makes a hole at suspected leakage point by drill hummer in Hihya Markaz. (Action U11).  
(Date: Dec. 8, 2007)



Counter parts investigate the pipe and cable under the ground by locator in Hihya Markaz. (Action U11).  
(Date: Dec. 13, 2007)



### UFW Reduction Activity(3/3)



Excavation of leakage point found by counterpart team in Hyhya Markaz. (Action U12)  
(Date: Dec. 13, 2007)



Leakage point found by counterpart team in Hyhya Markaz. (Action U12).  
(Date: Dec. 13, 2007)



Repairing leakage point in Ibrahimiya. (Action U12).  
(Date: Jul. 24, 2008)



Training and evaluation for equipment in Zagazig West .  
(Date: Jul. 6, 2008)



Training and evaluation for equipment at New Training Yard in Hihya (1) (Date: Feb. 5, 2009)



Training and evaluation for equipment at New Training Yard in Hihya (2) (Date: Feb. 5, 2009)



### SOP Activity(1/3)



Investigation for preparation of P&ID and SOP in Abbasa W.T.P (Action S1.2.4).  
(Date: May. 31, 2007)



Counter parts prepare the draft P&ID in Abbasa W.T.P (Action S1).  
(Date: Jun.6, 2007)



Discussion for preparation of P&ID and SOP in Abbasa W.T.P (Action S1.4) (Date: Jun.9, 2007)



Discussion for preparation of P&ID and SOP in Abbasa W.T.P (Action S1.4) (Date: Jun.11, 2007)



Discussion for preparation of P&ID and SOP in Kafr Farag (Action S1.4) (Date: Jun.16, 2007)



Counter parts record the vibration of motor at before maintenance and after maintenance in Abbasa W.T.P. (Action S2.4.6)  
(Date: Sep.5, 2007)

### SOP Activity(2/3)



Counter parts apply a SOP to pump maintenance in Abbasa W.T.P. (Action S4.6)  
(Date: Sep.5, 2007)



Counter part measures and records the water pressure in Zagazig W.T.P. (Action S2.6)  
(Date: Feb.20, 2007)



Counter part uses the SOP documents and makes an entry to unified form in Zagazig W.T.P. (Action S2.6)  
(Date: Feb.20, 2007)



Counter parts learn about the hydraulic analysis from expert in headquarter office. (Action S5-2)  
(Date: Aug.21, 2007)



Current survey and discussion about water quality control in New Faqus W.T.P. (Action S9)  
(Date: May.28, 2007)



Counter part measures the water level by teaching from expert in Abu Kabier Markaz. (Action S10)  
(Date: May.15, 2007)



### SOP Activity(3/3)



Measurement for well production by portable flow meter in Diarb Nigm Markaz. (Action S10)  
(Date: Jun.24, 2007)



OJT of filter refreshment in Zagazig W.T.P (Action S6).  
(Date: June. 24, 2008)



OJT of chlorine control in Abbasa W.T.P (Action S6).  
(Date: July.17, 2008)



Training of installation of data roger, data reading and data transportation in Abbssa W.T.P (Action S3.5).  
(Date: July.14, 2008)



Preparation of control procedures for residual chlorine.(Action S4.6) (Date: Oct.12, 2008)



OJT of control procedures for residual chlorine by H/Q counterpart in Abbasa W.T.P (Action S6.7)  
(Date: Oct.28, 2008)

**THE PROJECT FOR  
IMPROVEMENT OF MANAGEMENT CAPACITY OF  
OPERATION AND MAINTENANCE FOR SHAPWASCO  
IN THE ARAB REPUBLIC OF EGYPT**

**Project Final Report  
(Main Report)**

**Table of Contents**

Project Area

Photographs

Table of Contents

List of Tables and Figures

Abbreviations

**SUMMARY** ..... S-1

**CHAPTER 1 GENERAL** ..... 1-1

1.1 Preface ..... 1-1

1.2 Objectives of the Project ..... 1-2

1.3 Project Area ..... 1-2

1.4 Structure for Project Implementation ..... 1-3

**CHAPTER 2 DEVELOPMENT OF PDM** ..... 2-1

**CHAPTER 3 PROJECT ACHIEVEMENT** ..... 3-1

3.1 Achievement for Overall Goal ..... 3-1

3.2 Achievement for Project Purpose ..... 3-1

3.3 Achievement for Outputs ..... 3-1

3.4 Setting Performance Indicators for Overall Goal ..... 3-5

**CHAPTER 4 TECHNICAL COOPERATION OUTPUTS** ..... 4-1

4.1 UFW Reduction Activities ..... 4-1

4.1.1 Basic Policy ..... 4-1

4.1.2 Action Plan ..... 4-3

4.1.3 Common Actions (Actions U1 to U5) ..... 4-6

4.1.4 Implementation of Pilot Project (Action U6 - U14) ..... 4-18

4.1.5 Formulating Long-Term Pipe Replacement Plan for Preventive Works ..... 4-28

4.1.6 Formulating a Plan for Expanding UFW Reduction Activity to the whole  
Governorate ..... 4-31

4.1.7 Internal Workshop for UFW Reduction Activities ..... 4-32

|  |   |            |
|--|---|------------|
| 4.2  | SOP Activities.....   | 4-34       |
| 4.2.1  | Basic Policy.....   | 4-34       |
| 4.2.2  | Action Plan.....  | 4-38       |
| 4.2.3  | Each SOP Action.....  | 4-39       |
| 4.2.4  | Internal Workshop for SOP Activities.....                         | 4-68       |
| 4.3  | Other Activities.....   | 4-78       |
| 4.3.1  | Water Conservation Campaign.....                                  | 4-78       |
| 4.3.2  | Public Relation Activities.....                                   | 4-82       |
| 4.3.3  | Coordination with Other Donor and Organizations.....              | 4-83       |
| <b>CHAPTER 5 ACTUAL IMPLEMENTATION SCHEDULE.....</b>                             |   | <b>5-1</b> |
| 5.1  | Actual Implementation Schedule for UFW Reduction Activity.....    | 5-1        |
| 5.2  | Actual Implementation Schedule for SOP Activity.....              | 5-3        |
| <b>CHAPTER 6 ACTUAL OUTPUTS.....</b>   |   | <b>6-1</b> |
| 6.1  | Inputs by Japanese Side.....                                      | 6-1        |
| 6.1.1  | JICA Expert Team.....   | 6-1        |
| 6.1.2  | Counterpart Training in Japan.....                                | 6-2        |
| 6.1.3  | Provision of Equipment.....                                       | 6-9        |
| 6.1.4  | Expenses of Project Implementation.....                           | 6-13       |
| 6.2  | Input by Egyptian Side.....                                       | 6-14       |
| 6.2.1  | Counterpart Team.....   | 6-14       |
| 6.2.2  | Budget Allocation in Egyptian side.....                           | 6-17       |
| <b>CHAPTER 7 DEVICE AND LESSON ON PROJECT MANAGEMENT AND IMPLEMENTATION.....</b> |   | <b>7-1</b> |
| <b>CHAPTER 8 EVALUATION OF THE PROJECT.....</b>                                  |   | <b>8-1</b> |
| 8.1  | Mid-Term Monitoring Study.....                                    | 8-1        |
| 8.1.1  | Objective of Mid-term Monitoring Study.....                       | 8-1        |
| 8.1.2  | Comments by Mid-term Monitoring Study Team.....                   | 8-1        |
| 8.1.3  | Feedback of Comments made by Mid-term Monitoring Study Team.....  | 8-1        |
| 8.2  | Terminal Evaluation.....  | 8-2        |
| 8.2.1  | Objectives of Terminal Evaluation.....                            | 8-2        |
| 8.2.2  | Results of Terminal Evaluation.....                               | 8-2        |
| 8.2.3  | Feedback of Recommendations made by Terminal Evaluation Team..... | 8-5        |
| 8.3  | Cost Benefit Analysis for UFW Reduction Activity.....             | 8-5        |
| <b>CHAPTER 9 HOLDING OF VARIOUS MEETINGS.....</b>                                |   | <b>9-1</b> |
| 9.1  | Joint Coordinating Committee (JCC) Meeting.....                   | 9-1        |
| 9.2  | Technical Committee (TC) Meeting.....                             | 9-1        |
| 9.3  | Project Team Meeting (PTM).....                                   | 9-1        |



|       |                                   |     |
|-------|-----------------------------------|-----|
| 9.4   | Open Seminar .....                | 9-1 |
| 9.4.1 | 1st Open Seminar (Phase-2) .....  | 9-1 |
| 9.4.2 | 2nd Open Seminar (Phase-2).....   | 9-2 |
| 9.4.3 | 3rd Open Seminar (Phase-4) .....  | 9-3 |
| 9.5   | Open Workshop .....               | 9-3 |
| 9.5.1 | 1st Open Workshop (Phase-2) ..... | 9-3 |
| 9.5.2 | 2nd Open Workshop (Phase-3).....  | 9-5 |
| 9.5.3 | 3rd Open Workshop (Phase-3) ..... | 9-6 |

|                   |                                      |             |
|-------------------|--------------------------------------|-------------|
| <b>CHAPTER 10</b> | <b>TASK AND RECOMMENDATION .....</b> | <b>10-1</b> |
| 10.1              | Task .....                           | 10-1        |
| 10.2              | Recommendation.....                  | 10-1        |
| 10.2.1            | UFW Reduction Activities .....       | 10-1        |
| 10.2.2            | SOP Activities .....                 | 10-3        |

#### **ATTACHMENT**

|     |   |       |
|-----|---|-------|
| 1.  | Minutes of Meeting of 1 <sup>st</sup> JCC Meeting.....        | A1-1  |
| 2.  | Minutes of Meeting of 2 <sup>nd</sup> JCC Meeting.....        | A2-1  |
| 3.  | Minutes of Meeting of 3 <sup>rd</sup> JCC Meeting .....       | A3-1  |
| 4.  | Minutes of Meeting of 4 <sup>th</sup> JCC Meeting .....       | A4-1  |
| 5.  | Minutes of Meeting of 5 <sup>th</sup> JCC Meeting .....       | A5-1  |
| 6.  | Minutes of Meeting of 6 <sup>th</sup> JCC Meeting .....       | A6-1  |
| 7.  | Minutes of Meeting of Project Team Meetings for Phase-1 ..... | A7-1  |
| 8.  | Minutes of Meeting of Project Team Meetings for Phase-2 ..... | A8-1  |
| 9.  | Minutes of Meeting of Project Team Meetings for Phase-3 ..... | A9-1  |
| 10. | Minutes of Meeting of Project Team Meetings for Phase-4 ..... | A10-1 |

## **List of Tables and Figures**

### **Summary**

|            |   |     |
|------------|---|-----|
| Table S-1  | Summary of UFW Reduction Activities for the Project ..... | S-4 |
| Table S-2  | Summary of SOP Activities for the Project .....           | S-5 |
| Figure S-1 | Overall Schedule and Main Activities .....                | S-1 |

### **Chapter 1**

|            |  |      |
|------------|--|------|
| Table 1-1  | Roles of Committees and Teams for the Project..... | 1-3  |
| Table 1-2  | Member of Joint Coordinating Committee (JCC).....  | 1-4  |
| Table 1-3  | Member of Technical Committee(TC).....             | 1-5  |
| Table 1-4  | Member of Project Team.....                        | 1-5  |
| Table 1-5  | Member of UFW Teams.....                           | 1-6  |
| Table 1-6  | Member of SOP Teams .....                          | 1-7  |
| Table 1-7  | JICA Expert Team.....                              | 1-10 |
| Figure 1-1 | Structure for Project Implementation.....          | 1-4  |

### **Chapter 2**

|           |   |      |
|-----------|---|------|
| Table 2-1 | Development of PDM and PO .....         | 2-1  |
| Table 2-2 | PDM0(Original at the time of R/D) ..... | 2-2  |
| Table 2-3 | PDM1(1 <sup>st</sup> Revision) .....    | 2-4  |
| Table 2-4 | PDM2(2 <sup>nd</sup> Revision) .....    | 2-8  |
| Table 2-5 | PDM3(3 <sup>rd</sup> Revision).....     | 2-12 |

### **Chapter 3**

|           |  |      |
|-----------|--|------|
| Table 3-1 | Project Indicators and Achievement Levels.....                                       | 3-2  |
| Table 3-2 | PI for UFW Reduction Activity .....  | 3-5  |
| Table 3-3 | Long-Term Targets of UFW Ratios for SHAPWASCO.....                                   | 3-6  |
| Table 3-4 | PI for SOP Activities.....   | 3-7  |
| Table 3-5 | Result of PI for Power Consumption per Unit Water Production Volume in 2009 .....    | 3-8  |
| Table 3-6 | Target of PI for Power Consumption .....   | 3-8  |
| Table 3-7 | Result of PI for Chlorine Consumption per Unit Water Production Volume in 2009 ..... | 3-9  |
| Table 3-8 | Target of PI for Chlorine Consumption .....  | 3-9  |
| Table 3-9 | Result of PI for Alum Consumption per Unit Water Production Volume in 2009 .....     | 3-10 |

|                  |   |      |
|------------------|---|------|
| Table 3-10       | Target of PI for Alum Consumption.....  | 3-10 |
| Table 3-11       | Ratio of Water Production Volume and Water Intake Volume in 2009 .....                      | 3-11 |
| Table 3-12       | Target of PI for Efficiency of Water Production .....                                       | 3-11 |
| <b>Chapter 4</b> |   |      |
| Table 4.1-1      | Methodology for Three Countermeasures against UFW Reduction.....                            | 4-2  |
| Table 4.1-2      | Action Plan of UFW reduction activity .....   | 4-4  |
| Table 4.1-3      | Schedule and Program of Training at Mostrod Training Center .....                           | 4-6  |
| Table 4.1-4      | Schedule and Program of Training at SHAPWASCO Training Yard.....                            | 4-7  |
| Table 4.1-5      | List of Nominated Candidate Areas for Pilot Project Sites.....                              | 4-9  |
| Table 4.1-6      | Results of MNF Survey for Candidate Areas for the Pilot Project .....                       | 4-10 |
| Table 4.1-7      | Selected Pilot Project Sites .....  | 4-11 |
| Table 4.1-8      | Results of Leakage Survey for Selected Pilot Project Sites.....                             | 4-12 |
| Table 4.1-9      | Training Schedule of GIS Staff by JICA GIS Expert.....                                      | 4-13 |
| Table 4.1-10     | GIS Base Maps for Sharkia Governorate.....  | 4-14 |
| Table 4.1-11     | List of GIS Network Drawings Prepared.....  | 4-15 |
| Table 4.1-12     | Participants in Action U5 .....   | 4-16 |
| Table 4.1-13     | Schedule for Action U5.....   | 4-16 |
| Table 4.1-14     | Water Balance Analysis Sheet taking into account Water Supply Service<br>by SHAPAWSCO ..... | 4-21 |
| Table 4.1-15     | Results of UFW and Leakage ratio in each Pilot Project area .....                           | 4-25 |
| Table 4.1-16     | Information in each Pilot Project area.....   | 4-27 |
| Table 4.1-17     | Results of leakage survey in each Pilot Project area.....                                   | 4-28 |
| Table 4.1-18     | Internal Workshop for UFW Reduction Activities Done .....                                   | 4-32 |
| Figure 4.1-1     | Relation among Three Countermeasures for UFW Reduction Activity .....                       | 4-1  |
| Figure 4.1-2     | Position of the Project in the Whole UFW Reduction Activity .....                           | 4-2  |
| Figure 4.1-3     | Benefits of Reducing UFW.....   | 4-3  |
| Figure 4.1-4     | Flow of Actions for UFW Reduction Activity .....  | 4-5  |
| Figure 4.1-5     | Method of Measuring Metering Error.....   | 4-19 |
| Figure 4.1-6     | Flow Meter Installation for Tree Shape Network .....  | 4-19 |
| Figure 4.1-7     | Flow Meter Installation for Network in Highly-Populated District.....                       | 4-20 |
| Figure 4.1-8     | Ultrasonic Flow Meter .....   | 4-20 |
| Figure 4.1-9     | Water Pressure Recorder.....  | 4-20 |
| Figure 4.1-10    | Detecting by Acoustic Rod or Digital Sound Detector .....                                   | 4-22 |

|               |   |      |
|---------------|---|------|
| Figure 4.1-11 | Work by Leak Detector .....   | 4-22 |
| Figure 4.1-12 | Mechanism of Detecting Leaking Point.....   | 4-22 |
| Figure 4.1-13 | Typical Leak Detector .....   | 4-23 |
| Figure 4.1-14 | Leak Sound Correlator.....  | 4-23 |
| Figure 4.1-15 | Method of Detecting Leakage by Leak Sound Correlator .....  | 4-23 |
| Figure 4.1-16 | Method of Confirming Exact Location of Leak Point .....   | 4-24 |
| Figure 4.1-17 | Pipe & Cable Locator.....   | 4-24 |
| Figure 4.1-18 | Metal Locator.....  | 4-24 |
| Figure 4.1-19 | Pipelines in High Mobarak 1 area in Zagazig City-East.....  | 4-30 |
| Figure 4.1-20 | Location of Broken Pipes in Zagazig City-East.....  | 4-31 |
|               |   |      |
| Table 4.2-1   | Typical Changes in Present and New Potable Water Standards.....   | 4-35 |
| Table 4.2-2   | Objectively Verifiable Indicators and Achievements .....  | 4-38 |
| Table 4.2-3   | Basic Drawings prepared for Abbasa WTP .....  | 4-39 |
| Table 4.2-4   | Location for Flow Meters at Seven (7) WTPs .....  | 4-42 |
| Table 4.2-5   | Total Number of SOPs prepared through Phase-3 .....   | 4-44 |
| Table 4.2-6   | Modification Example of run time for filter washing after applying OJT of filter refreshment in Zagazig Water Treatment Plant ..... | 4-54 |
| Table 4.2-7   | Specification of 4 Monitoring Wells .....   | 4-63 |
| Table 4.2-8   | Internal Workshop for SOP Activities.....   | 4-68 |
|               |   |      |
| Figure 4.2-1  | Implementation Flow .....   | 4-37 |
| Figure 4.2-2  | Situation of Qenayat FMRP.....  | 4-39 |
| Figure 4.2-3  | P&ID and Graphs for to calculate the quantity of chemicals for Qenayat FMRP.....  | 4-39 |
| Figure 4.2-4  | Installation Situation of Bulk Flow Meter in Abbasa WTP .....   | 4-41 |
| Figure 4.2-5  | Typical Composition of SOP Documents .....  | 4-45 |
| Figure 4.2-6  | Example for SOP Documents in Arabic(SOP Package) .....  | 4-45 |
| Figure 4.2-7  | Data Analysis in Hihya .....  | 4-47 |
| Figure 4.2-8  | Lecture and study on filter refreshment to the plant managers.....  | 4-51 |
| Figure 4.2-9  | Site Situation of Qenayat Fe/Mn.....  | 4-52 |
| Figure 4.2-10 | Basic Idea and Function of Chlorine Dose Control in Qenayat Fe/Mn .....   | 4-52 |
| Figure 4.2-11 | Filter Before Refreshment.....  | 4-54 |
| Figure 4.2-12 | Filter After Refreshment .....  | 4-54 |
| Figure 4.2-13 | Typical Composition of Well Inventory and Well List .....   | 4-62 |

|                      |   |      |
|----------------------|---|------|
| Figure 4.2-14        | Well Inventory and Contour Map for Groundwater Level.....                                 | 4-65 |
| Table 4.3-1          | Methodology of Water Saving Campaign.....   | 4-78 |
| Table 4.3-2          | Questionnaire to Students in Pre-questionnaire Survey.....                                | 4-80 |
| Table 4.3-3          | Schedule of the Campaign .....  | 4-81 |
| Table 4.3-4          | Meeting with Other Donor and Organizations.....   | 4-83 |
| Figure 4.3-1         | Result of Pre-Questionnaire.....  | 4-82 |
| Figure 4.3-2         | Result of Post-Questionnaire .....  | 4-82 |
| Figure 4.3-3         | Opening part of Newsletter.....   | 4-82 |
| Figure 4.3-4         | Public Information Video CD .....   | 4-82 |
| <br><b>Chapter 5</b> |   |      |
| Figure 5-1           | Actual Implementation Schedule for UFW Reduction Activities.....                          | 5-2  |
| Figure 5-2           | Actual Implementation Schedule for SOP Activities.....                                    | 5-4  |
| <br><b>Chapter 6</b> |   |      |
| Table 6-1            | Dispatch of experts (Phase-1) .....   | 6-1  |
| Table 6-2            | Dispatch of experts (Phase-2) .....   | 6-1  |
| Table 6-3            | Dispatch of experts (Phase-3) .....   | 6-2  |
| Table 6-4            | Dispatch of experts (Phase-4) .....   | 6-2  |
| Table 6-5            | Summary of Counterpart Training in Japan.....   | 6-3  |
| Table 6-6            | Training Schedule in Japan for Phase-1.....   | 6-4  |
| Table 6-7            | Training Schedule in Japan for Phase-2.....   | 6-5  |
| Table 6-8            | Training Schedule and Program in Japan for UFW for Phase-3.....                           | 6-7  |
| Table 6-9            | Training Schedule and Program in Japan for SOP for Phase-3 .....                          | 6-8  |
| Table 6-10           | Equipment for UFW and SOP Activities procured .....                                       | 6-10 |
| Table 6-11           | Equipment for Common Activities procured .....  | 6-12 |
| Table 6-12           | Equipment Status .....  | 6-12 |
| Table 6-13           | Expense of Project Implementation .....   | 6-13 |
| Table 6-14           | Transition of Counterpart Team .....  | 6-14 |
| Table 6-15           | Budget Allocation in Egyptian Side.....   | 6-17 |
| <br><b>Chapter 8</b> |   |      |
| Table 8-1            | Comments made by Mid-term Monitoring Study Team .....                                     | 8-1  |
| Table 8-2            | Feedback of Comments made by Mid-term Monitoring Study Team.....                          | 8-2  |
| Table 8-3            | Results and Conclusion of Evaluation according to JICA' Five Evaluation<br>Criteria ..... | 8-3  |



|                       |   |      |
|-----------------------|---|------|
| Table 8-4             | Feedback of Recommendations made by Terminal Evaluation Team .....                  | 8-5  |
| Table 8-5             | Cost Breakdown of Cost Incurred in 3 Years for UFW Reduction Activities ..          | 8-6  |
| Table 8-6             | Cost-Benefit Analysis for UFW Reduction Activities (For 1 Year in Each Branch)..... | 8-7  |
| Table 8-7             | Production Cost of SHAPWASCO (FY2007) .....   | 8-7  |
| Table 8-8             | Selling Price of SHAPWASCO (FY2007) .....   | 8-7  |
| <br><b>Chapter 9</b>  |   |      |
| Table 9-1             | List of Joint Coordinating Committee .....  | 9-1  |
| <br><b>Chapter 10</b> |   |      |
| Table 10-1            | Work Assignment and Number of Staff for SOP Activities .....                        | 10-3 |
| Figure 10-1           | Practicable Approach for UFW Reduction by Establishment of DMA .....                | 10-2 |

## **Abbreviations**

|           |   |
|-----------|---|
| C/P       | Counterpart   |
| DT        | Distribution Tank   |
| DAPWASCO  | Dakahlia Potable Water and Sanitation Company                 |
| FY        | Fiscal Year   |
| FDWSC     | Fayoum Drinking Water and Sanitation Company                  |
| GIS       | Geographic Information System                                 |
| HCWW      | Holding Company for Water and Wastewater                      |
| HQ        | Headquarters  |
| IC/R      | Inception Report  |
| IWA       | International Water Association                               |
| JCC       | Joint Coordinating Committee                                  |
| JICA      | Japan International Cooperation Agency                        |
| LE        | Egyptian Pound  |
| L/s       | Liter per second  |
| MCM       | Million Cubic Meter   |
| M/M       | Minutes of Meeting  |
| MNF       | Minimum Night Flow  |
| NOPWASD   | National Organization for Potable Water and Sanitary Drainage |
| NRW       | Non Revenue Water   |
| O&M       | Operation and Maintenance                                     |
| PDM       | Project Design Matrix   |
| PO        | Plan of Operation   |
| PTM       | Project Team Meeting  |
| PVC       | Polyvinyl Chloride  |
| RW        | Revenue Water   |
| SHAPWASCO | Sharkia Potable Water and Sanitation Company                  |
| SOP       | Standard Operational Procedures                               |
| TC        | Technical Committed   |
| TPS       | Transmission Pump Station                                     |
| UFW       | Unaccounted-for Water   |
| USAID     | U.S. Agency for International Development                     |
| WTP       | Water Treatment Plant   |

## SUMMARY

### 1. Overall Schedule and Main Activities

The Project Final Report has been prepared for compiling all the activities and the achievements of for the Project. The Project has been implemented in four (4) phases from November 2006 to October 2009. Overall schedule and main activities are described in Figure S-1 below:




Figure S-1 Overall Schedule and Main Activities

### 2. Action Plans

The Project consisted of two (2) main activities: UFW reduction activity and SOP (Standard Operational Procedures) activity. Action Plans for these activities were formulated in Phase-1 and approved at Technical Committee (TC) held in March 2007. Contents of actions for each activity are as follows:

#### UFW Reduction Activity

- Action-U1** Conducting training of C/P staff at Mostrod Training Center
- Action-U2** Conducting leakage (minimum night flow: MNF) survey for candidate areas
- Action-U3** Determining nine (9) pilot project areas
- Action-U4** Preparing GIS drawings
- Action-U5** Learning experiences of Jordan UFW reduction project
- Action-U6** Making field survey of distribution network
- Action-U7** Surveying working conditions of water meters and conducting meter readings
- Action-U8** Measuring metering error for working meters and water wastage in the house
- Action-U9** Conducting MNF survey
- Action-U10** Making water balance analysis before repair works
- Action-U11** Conducting leakage detection survey
- Action-U12** Repairing leaking parts

**Action-U13** Conducting MNF survey (including meter readings) after repair works

**Action-U14** Making water balance analysis after repair works and its evaluation

### **SOP Activity**

**Action-S1** Preparing basic system drawings

**Action-S2** Preparing unified forms of O&M records and reports

**Action-S3** Measuring intake/production water volume at seven (7) WTPs

**Action-S4** Developing SOPs for Model Facilities

**Action-S5** Examining water distribution control in the network

**S5-1** Pilot project for distribution control in small areas

**S5-2** Hydraulic analysis of water supply and distribution network

**Action-S6** Applying SOPs in O&M

**Action-S7** Developing SOPs for the Remaining Facilities

**Action-S8** Formulating O&M Plans

**Action-S9** Developing water quality control program

**Action-S10** Developing well inventory forms and monitoring wells

### **3. Milestones of the Activities**

The milestones of each activity for the Project are mentioned below:

#### **(1) General**

- Dec. 2006 1<sup>st</sup> JCC was held and the inception report of the Project was approved.
- Mar. 2007 1<sup>st</sup> TC was held and Action Plans were approved.
- Jun. 2007 2<sup>nd</sup> JCC was held where PDM1 and PO1 were approved and 1st seminar was held in Cairo.
- Mar. 2008 3<sup>rd</sup> JCC was held where PDM2 and PO2 were approved and 2<sup>nd</sup> open seminar was held in Cairo.
- Jul. 2008 4<sup>th</sup> JCC was held where PDM3 and PO3 were approved.
- Feb. 2009 Terminal evaluation coordination meeting and 5<sup>th</sup> JCC were held where minutes on joint evaluation report on Japanese technical cooperation for the Project and 5<sup>th</sup> JCC were signed.
- Oct. 2009 6<sup>th</sup> JCC was held to confirm the completion of activities in Egypt and submission of the Project Final Report to the Egyptian side in November 2009

#### **(2) UFW Reduction Activity**

- Dec. 2006 UFW/HQ team was organized at SHAPWASCO headquarters.
- Jan. 2007 Existing conditions survey of UFW was completed.
- Feb. 2007 UFW teams of the whole governorate were organized and training of UFW/HQ team leader was conducted in Japan.
- Mar. 2007 Action plan for UFW reduction activity was formulated and approved.

- Apr. 2007 Action U1 and U4 started.
- May 2007 Action U2 started.
- Jun. 2007 Action U5 was conducted.
- Jul. 2007 Pilot Project-1 started in Zagazig City-East
- Aug. 2007 Action U11 and U12 of Pilot Project-1 started.
- Sept. 2007 Internal workshop for training leakage detection technique was held.
- Oct. 2007 Water conservation campaigns started for primary school students and junior high school students at Hihya WTP.
- Nov. 2007 1<sup>st</sup> open workshop for achievements of UFW reduction activity was held in Zagazig.
- Nov. 2008 Five (5) pilot projects at Zagazig City (East), Zagazig City (West), Hihya Markaz, Zagazig Markaz and Ibrahimiya Markaz were completed.
- Dec. 2008 2<sup>nd</sup> open workshop for achievements of UFW reduction activity was held in Zagazig.
- Jan. 2009 Construction of SHAPAWASCO training yard for leakage survey was completed at Central Well Station in Hihya City.
- Feb. 2009 3<sup>rd</sup> open workshop for latest achievements of UFW reduction activity was held in Cairo. In this workshop, UFW activity in Jordan was introduced by the representative of Water Authority of Jordan.
- Sept. to Oct. 2009 All the pilot projects were completed and long-term UFW targets as performance indicator were set based on the results of the pilot projects.
- Oct. 2009 3<sup>rd</sup> open seminar was held and the achievements in UFW reduction activities were presented.

## **(2) SOP Activity**

- Dec. 2006 SOP/HQ team was organized in SHAPWASCO headquarters.
- Jan. 2007 Existing conditions survey for water supply facilities were completed and list of the existing water supply facilities for SHAPWASCO was compiled.
- Feb. 2007 SOP/HQ team leader was trained in Japan.
- Mar. 2007 Action Plan for SOP activity was formulated and approved.
- Apr. 2007 Action S1 started.
- May 2007 Actions S2, S3, S5, S9 and S10 started.
- Aug. 2007 Activity for development of SOP started and internal workshop was conducted.
- Nov. 2007 1<sup>st</sup> open workshop for SOP activity was held and discussions were done for sample of SOP.



- Feb. 2008 OJT started using SOPs at Abbasa WTP.
- Mar. 2008 Measurement of distribution volume by ultra-sonic flow meter started at Abbasa WTP.
- Jun. 2008 OJT started using SOP at Kafr Farag Fe/Mn removal plant and applying filter refreshment started at Zagazig WTP.
- Nov. 2008 Revision of SOP was started at Abbasa WTP by SHAPWASCO.
- Dec. 2008 OJT started using SOP at Bilbais booster pump station.
- Dec. 2008 2<sup>nd</sup> open workshop for achievements of SOP activity was held.
- Feb. 2009 3<sup>rd</sup> open workshop for latest achievements of SOP activity was held in Cairo.
- Mar. to Oct. 2009 Monitoring data of flow rate and consumption of electricity, chlorine and alum was done. Performance indicators for SOP activities were set based on the monitoring results.
- Oct. 2009 3<sup>rd</sup> open seminar was held and the achievements in SOP activities were presented.

#### 4. Summary of Activities for the Project

##### 4-1. UFW Reduction Activity

UFW reduction activities for the Project are summarized for each action below:

**Table S-1 Summary of UFW Reduction Activities for the Project**

| No. | Pilot Project Site              | UFW Ratio            |                     |                      |
|-----|---------------------------------|----------------------|---------------------|----------------------|
|     |                                 | Before Repair<br>(%) | After Repair<br>(%) | Reduction<br>(point) |
| 1   | Zagazig City-East               | 40.8                 | 20.8                | 20.0                 |
| 2   | Hihya Markaz                    | 27.5                 | 16.6                | 10.9                 |
| 3   | Zagazig City-West               | 35.4                 | 19.4                | 16.0                 |
| 4   | Zagazig Markaz-1                | 39.2                 | 14.1                | 25.1                 |
| 5   | Ibrahimiya Markaz-1             | 30.0                 | 14.0                | 16.0                 |
| 6   | Diarb Nigm Markaz               | 26.2                 | 18.6                | 7.6                  |
| 7   | Abu Hamad Markaz                | 39.2                 | 29.7                | 9.5                  |
| 8   | Bilbais Markaz                  | 21.3                 | 12.8                | 8.5                  |
| 9   | Menia Alqamah M.                | 29.2                 | 23.4                | 5.8                  |
| 10  | Zagazig Markaz-2 (Expansion)    | 30.7                 | 23.0                | 7.7                  |
| 11  | Ibrahimiya Markaz-2 (Expansion) | 19.9                 | 12.8                | 7.1                  |
|     | Average (Except Area 10,11)     | <b>31.3</b>          | <b>18.0</b>         | <b>12.4</b>          |
|     | Average(All eleven Areas)       | <b>31.0</b>          | <b>18.8</b>         | <b>12.2</b>          |
|     | Target                          |                      |                     | <b>13</b>            |

\* Average is weighted average considering water distribution volume

## 4.2 SOP Activity

SOP activities for the Project are summarized for each action below:

**Table S-2 Summary of SOP Activities for the Project**

| Activity                                    |   | Achievement   |   | Facilities Applied         |
|---|---|---|---|----------------------------|
| Preparation of documents for SOP activities | <ul style="list-style-type: none"> <li>➤ Basic system drawings</li> <li>➤ SOP</li> <li>➤ P&amp;ID and others</li> </ul> | Capacity Development of preparing/modification document                                 | Capacity Development of O&M   | 4WTP, 3FMRP, 1BPS and 2WPS |
|   | Unified recording sheet   | Capacity Development of preparing/modification document                                 | Capacity Development of O&M   | 1WTP, 1FMRP, 1BPS and 1WPS |
| Applying SOP to O&M by OJT                  | O&M of filter   | Reduction of water use for filter washing   | <ul style="list-style-type: none"> <li>➤ Improvement of performance indicator</li> </ul>                                    | 3WTP and 2FMRP             |
|   | Control of chemical consumption   | Reduction of chemical consumption   | <ul style="list-style-type: none"> <li>➤ Improvement of water facilities</li> <li>➤ Improvement of water quality</li> </ul> | 3WTP and 2FMRP             |
|   | Control of operation number of main pumps   | Improvement of stability for water supply and reduction of power consumption            | Improvement of water supply service   | 2WTP, 1BPS and 1WPS        |
| Other Activities                            | Well Monitoring   | Development for well inventory, Enhancement of well monitoring                          |   | All WPS                    |
|   | Water Quality Control   | To become routine work of auditing system, Development of water quality control program |   | 2 WTP                      |

Note:

WTP: Water Treatment Plant, FMRP: Iron and Manganese Removal Plant  
 BPS: Booster Pump Station, WPS: Well Pump Station  
 P&ID: Piping & Instrument Diagram O&M: Operation and Maintenance

## **CHAPTER 1 GENERAL**

### **1.1 Preface**

Egypt has been experiencing sector reform in the water supply and sanitation sector since late 90s.

In the Sharkia Governorate, the third largest governorate with approximately five million people, the public water supply and sewerage corporation (SHEGAWASD) took over the management of all the water supply and sewerage services in the governorate from the local government in 1995 (in 2004, SHEGAWASD renamed itself as SHAPWASCO).

SHAPWASCO, like other public corporations and firms, is in the red because of low incomes arising from low fare receipts; excessive labor cost due to overstaffing; high cost of inefficient operation of the facilities; high unaccounted-for water (UFW) ratio; low ratio of water charge collection; and insufficient management ability due to incapability of obtaining management information (concerning production, water supply management, and customers).

Under such circumstances, in 2003, the Egyptian Government requested the Japanese government to implement a technical cooperation project to assist SHAPWASCO improve its operation and maintenance capacity.

In the Governorate of Sharkia, a new water purification plant was constructed under Japan's grant aid cooperation project in 2007, "the Project for Water Supply Development in Northwest Part of Sharqiya Governorate, so that this project is positioned as a collaborating project for the grant aid cooperation in progress.

Following the request as stated above, JICA discussed the issue with the Egyptian side in May-June 2006, confirmed the relevance and the nature of the request; mutually signed minutes of meeting with the Egyptian side concerning the specific outline of the project; signed Records of Discussions on 20<sup>th</sup> September 2006; and the JICA expert team commenced their work in Egypt from 29<sup>th</sup> November 2006.

The 1<sup>st</sup> Joint Coordinating Committee (JCC) was held on 3<sup>rd</sup> December 2006. In the 1<sup>st</sup> JCC, the Inception Report of the Project was explained by the expert team and approved by the members of JCC.

During the Project, PDM (Project Design Matrix) and PO (Plan of Operation) were revised from PDM0 and PO0 to PDM3 and PO3 respectively. In the 2<sup>nd</sup> to 4<sup>th</sup> JCC, those revisions of PDM and PO were approved.

The JICA expert team and the counterpart (C/P) team conducted UFW (unaccounted-for water) reduction activities, SOP (standard operational procedures) activities and public campaign for water saving according to PDM and PO and the comments made by the mid-term monitoring study team on 4<sup>th</sup> March 2008 and the terminal evaluation team on 23<sup>rd</sup> February 2009.

It was confirmed in the 6<sup>th</sup> JCC that the activities in Egypt are completed at the end of October 2009 and the final report of the Project will be submitted to the Egyptian side in November 2009.

## 1.2 Objectives of the Project

The objectives of the Project are summarized as follows:

**[Overall Goal]** Management capacity of operation and maintenance of water supply facilities is improved in Sharkia Governorate.

**[Project Purpose]** Management capacity of operation and maintenance of water supply facilities is improved in target areas (Project Area-1 and 2 mentioned in section 1.3 below).

The following outputs are expected to be gained from the Project:

**[Outputs]**

- Unaccounted-for water (UFW) ratio is reduced in the pilot project areas.
- Operation and maintenance capacity of water supply facilities is strengthened.

Activities in the Project are focused on the following:

**[Activities]**

- Activity for reduction of unaccounted-for water (UFW)
- Activity for Improvement of operation and maintenance capacity of water supply facilities (SOP : Standard Operational Procedures)

The Project Design Matrix (PDM) and Plan of Operation (PO) were reviewed in Phase-2 (the 2<sup>nd</sup> Year: from April 2007 to March 2008). During Phase-2, original PDM0 and PO0 have been revised into PDM3 and PO3 by the approval in the JCC meeting.

## 1.3 Project Area

The Project Sites are categorized according to the activities as follows:

### <For UFW Reduction Activity>

- Project Area-1 : Zagazig City and Zagazig Markaz
- Project Area-2 : Hihya Markaz, Diarb Nigm Markaz and Ibrahimiya Markaz
- Project Area-3 : Abu Hamad Markaz, Bilbais Markaz and Menia Alqamah Markaz

### <For SOP Activity>

- Water supply facilities (water treatment plant, pumping station, iron/manganese removal plant, well) in the whole Governorate as follows:
  - Water treatment plant
  - Booster pumping station
  - Iron/manganese removal plant
  - Well

## 1.4 Structure for Project Implementation

The Project was conducted under the following implementation structure:

### (1) Formation for Project Implementation

The chairman of Holding Company for Water and Wastewater (HCWW) was assigned to the Project Director and the Chairman of the Joint Coordination Committee (JCC). The Project Manager was played by the chairman of SHAPWASCO. The JCC members included the representative of the NOPWASD, the Governor of Sharkia, Japanese experts and the representatives of JICA Egypt office.

An Unaccounted-For Water reduction team (UFW team) and Standard Operation Procedure for operation and maintenance team (SOP team) was organized at the SHAPWASCO headquarters, both of which performed their activities by closely communicating with personnel in charge in the areas they cover. In addition, since it is essential to cooperate and coordinate with the USAID, the headquarter team constructed a system for regular information exchanges.

Figure 1-1 illustrates the project implementation organization. Since the implementation organization agreed upon in the M/M has a limited frequency of JCC meetings, it was proposed to set up a Technical Committee as a forum for preliminary discussion on technical matters prior to discussion at the JCC that involves the central government. The Technical Committee consisted of SHAPWASCO, HCWW, and UFW and SOP teams from the Sharkia Governorate and JICA-related parties.

The functions of each committee or meeting, in conjunction with the implementation of the Project, are as listed in Table 1-1 below.

**Table 1-1 Roles of Committees and Teams for the Project**

| Project agency                     | Roles  | Frequency           |
|------------------------------------|--|---------------------|
| Joint Coordination Committee (JCC) | Approval of the project annual plan, monitoring/evaluation of the project and annual plan, discussion and advice on the main issues of the project, coordination between Egyptian side and Japanese side | 1~2 times a year    |
| Technical Committee (TC)           | Prior consultation with JCC for the project main issues and report of the progress of the project, as required   | As required         |
| Project Team Meeting (PTM)         | Committee chaired by SHAPWASCO Chairman consisting of JICA expert team and the counterpart team established in Headquarters of SHAPWASCO for supervising the Project                                     | Weekly in principle |




Figure 1-1 Structure for Project Implementation

(2) Joint Coordinating Committee (JCC)

Joint Coordinating Committee (JCC) was formed on 20<sup>th</sup> September 2006. Chairman of Holding Company for Water and Wastewater (HCWW) has been nominated as the Project Director. The members of JCC are as follows:

Table 1-2 Member of Joint Coordinating Committee (JCC)

| Role                       | Member   |
|----------------------------|--|
| - Chairman                 | ➤ Chairman, HCWW   |
| - Members on Egyptian Side | ➤ Chairman, SHAPWASCO  |
|                            | ➤ Representative(s), SHAPWASCO                                     |
|                            | ➤ Representative, NOPWASD  |
|                            | ➤ Representative, Sharkia Governorate                              |
|                            | ➤ Others appointed by the Committee                                |
| - Members on Japanese side | ➤ Chief Advisor  |
|                            | ➤ Experts  |
|                            | ➤ Representatives of JICA Egypt Office                             |
|                            | ➤ Other personnel concerned to be dispatched by JICA, if necessary |

Note: Official(s) of the Embassy of Japan may attend the Joint Coordinating Committee as observer(s).

### (3) Technical Committee (TC)

Establishment of the Technical Committee (TC) was proposed by the expert team in the 1<sup>st</sup> JCC meeting on 3<sup>rd</sup> December 2007 and approved by JCC members. TC is supposed to be held prior to JCC to discuss or coordinate technical matters or particularities of project activities.

However, TC was held only once during the Project because all the matters were discussed in detail at the project team meeting and the Project Manager (SHAPWASCO Chairman) explained the results of the discussions in PTM to the committee members at JCC. The members of TC are as follows:

**Table 1-3 Member of Technical Committee (TC)**

| Role       | Member                                       |
|------------|--|
| - Chairman | ➤ Chairman, SHAPWASCO                        |
| - Member   | ➤ Representative, HCWW                       |
|            | ➤ Representative, NOPWASD                    |
|            | ➤ Head of UFW team at SHAPWASCO headquarters |
|            | ➤ Head of UFW team at SHAPWASCO headquarters |
|            | ➤ Japanese Experts                           |
|            | ➤ Representative(s) of JICA Egypt Office     |

### (4) Project Team

The Project Team has been organized among C/P team and JICA expert team prior to the commencement of the Project. It consists of the following members:

**Table 1-4 Member of Project Team**

| Role              | Member                |
|-------------------|-----------------------|
| - Project Manager | ➤ Chairman, SHAPWASCO |
| - Member          | ➤ UFW/HQ team member  |
|                   | ➤ SOP/HQ team member  |
|                   | ➤ Facilitator         |
|                   | ➤ JICA experts        |

### (5) Counterparts (SHAPWASCO)

In December 2006, UFW team and SOP team at headquarters of SHAPWASCO were organized. In February 2007, UFW teams for Zagazig City-East, Zagazig City-West and each Markaz were organized. For SOP team, task force for Action Plan formulation was organized in February 2007.

#### [UFW Team]

UFW team except for headquarters of SHAPWASCO consists of one (1) engineer, three (3) supervisors and 2 workers. The members are listed below:



**Table 1-5 Member of UFW Teams**

| UFW Team in City/Markaz | Name   |
|-------------------------|--|
| Head of UFW/HQ team     | Mr. Alae El Din Mohamed (E)<br>Miss. Wala Mohamed Ali (E)<br>Miss. Wala Hamdi (E)<br>Mr. Alaa Abd El Raheem (S)                                  |
| Zagazig City - East     | Mr. Salama Mahmoud Abd El Aal (E)<br>Mr. Mohamed Mohamed Bakr (S)<br>Mr. Medhat Moneir Mahmoud (S)<br>Mr. Mohamed Hafez Lotfy (S)                |
| Zagazig City - West     | Mr. Samir Mahmoud Abd El Hameed (E)<br>Mr. Mahmoud Mohamed El Hariry (S)<br>Mr. Nabil Fathy El Sayed (S)<br>Mr. Gorge Abd El Maseeh (S)          |
| Zagazig Markaz          | Mr. Mohamed Mohamed Sabry (S)<br>Mr. Ibrahim Bayoumi Mohamed (S)<br>Mr. Ahmed Younis Metwaly (S)<br>Mr. Esam Afifi (S)                           |
| Hihya Markaz            | Mr. Mahdy Fathy Ahmed (E)<br>Mr. Gamal Mohamed Hussein (S)<br>Mr. El Hady Ahmed El Taher (S)   |
| Ibrahimiya Markaz       | Mr. Ramadan Abd Allah (S)<br>Mr. Khairi Abd El Rahman (S)<br>Mr. Mahmoud Mohamed Asar (S)<br>Mr. Abdu Fatehy Mohaned (S)                         |
| Diarb Nigm Markaz       | Mr. Mohamed El Sayed El Killany (S)<br>Mr. Mohamed Megahed Abd El Aziz (S)<br>Mr. Khairi Eid Talaat (S)<br>Mr. Hamdi El Sayed Abd El Fatah (S)   |
| Awlad Saqr Markaz       | Mr. Emad Ahmed Abd El Kader (E)<br>Mr. Bendary Hassan Bendarhy (S)<br>Mr. Hegazy El Sayed Ali (S)<br>Mr. Saeed Abd El Salam Ahmed (S)            |
| Kafr Saqr Markaz        | Mr. Fahmy Mohamed Khalaf Allah (E)<br>Mr. Mohamed Ibrahim Mohamed (S)<br>Mr. Mahmoud Awad Abd Alah (S)<br>Mr. Osman mansour Mohamed (S)          |
| Menia Al Qamah Markaz   | Mr. Mohamed Abd El Wahab (E)<br>Mr. Adel Saleh (S)<br>Mr. Ibrahim Fathy El Sadany (S)<br>Mr. El Sayed Abd El Habet Ghamry (S)                    |
| Mashtool El Sooq Markaz | Mr. Saeed Abd El Rahman Hefny (E)<br>Mr. Mohamed Ahmed Ali Hozayen (S)<br>Mr. Abd El Baset Mostafa Mohamed (S)<br>Mr. Soliman Hassan Soliman (S) |
| Bilbais Markaz          | Mr. Reda Abd El Hameed Abd Allah (S)<br>Mr. Salah Mohamed Kamel (S)<br>Mr. Mahmoud Salem Ibrahim (S)<br>Mr. Mostafa Ali ElSayed (S)              |

| UFW Team in City/Markaz                                    | Name   |
|--|--|
| Faqus Markaz   | Mr. Sebaey Mohamed Rabee (E)<br>Mr. Mostafa Mohamed Sobeeh (S)<br>Mr. El Sayed Abd El Aziz Soliman (S)<br>Mr. Salah El Dien Abbas Farah (S)  |
| Abu Kabier Markaz  | Mr. El Saied Abd El Reheem (E)<br>Mr. Abd El Wahab Mohamed Ali (S)<br>Mr. Mahrour Gergis Romees (S)<br>Mr. Mahmoud Mohamed Gebaly (S)  |
| Abu Hamad Markaz   | Mr. Taher Mansour Metwalli (E)<br>Mr. Sayed Nasser (S)<br>Mr. Mohamed Mahmoud Radwan (S)<br>Mr. Youssry Abd El Monem Hassan (S)  |
| El Huseinia Markaz   | Mr. Salah Abd El Haq (E)<br>Mr. Mohamed Abd El Monem (S)<br>Mr. El Sayed Ibrahim Ali (S)<br>Mr. Mohamed Abd El Aal Mohamed (S)   |
| El Salehia Sector (New Sector Established in January 2008) | Mr. Mohamed Saleem Abd El Salam (E)<br>Mr. Mohamed Mohamed Gomaa (S)<br>Mr. Ibrahim Ali Attia (S)<br>Mr. Abd Alaziz Khalil Mahmoud (S)   |
| GIS center   | Mr. Abdel Halim Mahdy<br>Mr. Tarek Yousef<br>Ms. Aliaa El Saeed<br>Ms. Hend Ali<br>Mr. Mohamed Saeed<br>Ms. Nour Abbas<br>Ms. Samar Sameer<br>Ms. Marwa Ahmed<br>Ms. Basma Ibrahim |
| Water conservation campaign                                | Ms. Mariam Wageih  |

**[SOP Team]**

SOP team at SHAPWASCO headquarters (SOP/HQ team) and the teams at the related water supply facilities for SOP activity are as follows:

**Table 1-6 Member of SOP Teams**

| Activity     | Name   | Position  |
|--------------|--|---|
| SOP Activity | <b><u>SOP/HQ team</u></b><br>1- Eng. Abdel Shafi Abdel Aziz<br>2- Eng. Ibrahim Shaheen<br>3- Eng. Gamal Abd El Hameed<br>4- Mr. Mohamed Ali<br>5- Ms. Heba Mahmoud Mohamed<br>6- Mr. Abd Allah Sayed | Head of SOP/HQ Team<br>Electrical Engineer<br>Geologist – Well Depart.<br>Chemist<br>Assistant<br>Assistant |
|              | <b><u>Members of Task Force of SOP Activity:</u></b><br>1- Mr. Abdel Shafi Abdel Aziz<br>2- Mr. Nagi Labib Abd El Sayed<br>3- Mr. Bahaa Abd Allah Badran<br>4- Mr. Samir Gharieb                     | Head of SOP/HQ Team<br>Hihya WTP manager<br>Kafr Saqr WTP manager<br>Abbasa WTP manager                     |

| Activity | Name  | Position  |
|----------|---|---|
|          | 5- Mr. Mohamed Ali<br>6- Mr. Aly El Mosalemy<br>7- Mr. Emam Abd El Mawgoud<br>10- Mr. Gamal Abd El Hameed Morsi<br>11- Mr. Mohamed El Sayed Abd El Hameed<br>12- Ms. Naglaa Fatehy  | Head Quarter<br>Water Department Manger<br>Menia Al Qamah FMR plant<br>Well Stations Department<br>Bilbais BPs<br>Data Base- Head Quarter   |
|          | <b><u>SOP team for Abbasa WTP</u></b><br>1- Eng. Samir Mohamed Ghareib<br>2- Tech. Hosni Abd El Rahman Hosni<br>3- Tech. Abd El Hakeem Mohamed<br>4- Tech. Ashour Ali Ashour<br>5- Tech. Ismaiel Abd El Hameed<br>6- Labor. Adel Gamal Mohamed<br>7- Chemist. Mansour Mohamed Nasaar<br>8- Chemist. Fayza Mohmed Ghamri<br><b><u>Representative from other facilities:</u></b><br>1- Eng. Mohamed Faried  | Abbasa WTP manager<br>Abbasa WTP<br>Abbasa WTP<br>Abbasa WTP<br>Abbasa WTP<br>Abbasa WTP<br>Abbasa WTP<br>Abbasa WTP<br>Zagazig WTP manager   |
|          | <b><u>SOP team for Zagazig WTP</u></b><br>1- Mohamed El Sayed Farid<br>2- Tech. Abd Allah Mohamed Yousef<br>3- Tech. Zakaria Mamoud El Sayed<br>4- Tech. Mohamed Hassan Mohamed<br>5- Tech. El Sayed Mohamed Hassan<br>6- Tech. Hani Zaki Fahmy<br>7- Tech. El Sayed Mohamed Abd El Rahman<br>8- Chemist: Ahmed Abd El Mohsen<br>9- Chemist: Mona Abd Alah Mokhtar  | Zagazig WTP manger<br>Zagazig WTP<br>Zagazig WTP<br>Zagazig WTP<br>Zagazig WTP<br>Zagazig WTP<br>Zagazig WTP<br>Zagazig WTP<br>Head of Laboratory<br>Chemist  |
|          | <b><u>SOP team for New Faqus WTP</u></b><br>1- Eng. Ahmed Mohamed El Ghateit<br>2- Tech. Helal Morsi Mansour<br>3- Tech. Ashraf Mohamed Basiouni<br>4- Tech. Samir Ahmed Youssef<br>5- Chemist. Saad El Dien Abd El Monem<br>6- Tech. Youssry Mohamed Abd El Rehim<br><b><u>Representative from other facilities:</u></b><br>1- Eng. Bahaa Ramadan<br>2- Eng. Nagi Labib  | New Faqus WTP manager<br>New Faqus WTP<br>New Faqus WTP<br>New Faqus WTP<br>New Faqus WTP<br>New Faqus WTP<br>Sangaha (Kafr Saqr) WTP manager<br>Hihya WTP manager  |
|          | <b><u>SOP team for Kafr Farag FMRP</u></b><br>1- Tech. Imam Abd El Mawgood<br>2- Tech. Samir El Sayied Hassan<br>3- Tech. El Sayied Abd El Fatah El Saied<br>4- Chemist. Abd El Hadi Ali Bassiouni<br><b><u>Representative from other facilities:</u></b><br>1- Tech. Adel Abu El Yazid Mohamed<br>2- Tech. Mohamed Fouad Ali Mostafa<br>3- Tech. El Saied El Shahat El Menshawi<br>4- Tech. Ahmed Mahmoud Ahmed Nagi<br>6- Tech. Zareif Saber Mohamed El Saied | Kafr Farag FMRP manager<br>Kafr Farag FMRP<br>Kafr Farag FMRP<br>Kafr Farag FMRP<br>Qenayat FMRP<br>Mashtool El Sooq FMRP<br>El Adlia FMRP<br>Melamis FMRP in Menia Al Qamah<br>Abu Metanna in Diarb Nigm |
|          | <b><u>SOP team for Bilbaise BPS</u></b><br>1- Tech. Mohamed El Sayied<br>2- Tech. Gamal Gaad Ahmed Ibrahim  | Bilbais BPS manager<br>Bilbais BPS  |

| Activity                   | Name   | Position  |
|----------------------------|--|---|
|                            | 3- Tech. Gamal Salem Mohamed<br>4- Chemist. Saad El Dien Abd El Monem<br>5- Abd El Hakeem Nabawi<br><u>Representative from other facilities</u><br>1- Tech. Emad El Dien Abd El Hadi<br>2- Tech. Abd El Aliem Ahmed Mohamed          | Bilbais BPS<br>Bilbais BPS<br>Bilbais BPS<br><br>Faqus BPS<br>Zagazig BP  |
|                            | <b><u>SOP team for Zeraa well station</u></b><br>1- Eng. Ali El Mosalmi<br>2- Tech. Ibrahim Mohey<br>3- Tech. Mohamed Abd El Aziz<br>4- Tech. Attia Bayoumi<br>5- Tech. Sami Bahi Abd El Gawad<br>6- Chemist. Gamal Abd El Hameed    | Zeraa well station<br>Zeraa well station<br>Zeraa well station<br>Zeraa well station<br>Zeraa well station<br>Head Quarter                    |
|                            | <b><u>SOP team for El Asloughi well station</u></b><br>1- Tech. Abd El Aleem Mohamed Ahmed<br>2- Tech. Salah El Din Afifi Khatab<br>3- Tech. Abd El Hameed Ibrahim<br>4- Tech. Ahmed Mohamed Metwaly                                 | Manger of Water Plants<br>Manger of El Asloughi Station<br>El Asloughi well station<br>El Asloughi well station                               |
|                            | <b><u>SOP team for Qenayat FMRP (Additional)</u></b><br>1- Tech. Adel Abu El Yazid Mohamed<br>2- Tech. Saleem Abd Alah<br>3- Tech. El Sayied Ibrahim<br>4- Chemist. Attia Goda El Sayed  | Plant Manger of Qenayat FMRP<br>Technician of Qenayat FMRP<br>Technician of Qenayat FMRP<br>Chemist   |
|                            | <b><u>SOP team for Abu Metana FMRP (Additional)</u></b><br>1- Tech. Adel Abu El Mohamed Abu Warda<br>2- Tech. Hosam El Din Mohamed<br>3- Tech. Alaa Ahmed El Badawi<br>4- Ahmed Ali Abd El Maksoud<br>4- Chemist. Adly Abd El Mageed | Plant Manger of Abu Metana FMRP<br>Technician of Abu Metana FMRP<br>Technician of Abu Metana FMRP<br>Technician of Abu Metana FMRP<br>Chemist |
| 3. Hydraulic Analysis Team | 1- Mr. Mahdi Ahmed<br>2- Ms. Heba Mahmoud  | Hihya Branch<br>Head Quarter  |
| 4. Well Monitoring         | 1- Mr. Gamal Abd El Hameed Morsi   | Head Quarter  |
| 5. Water Quality Control   | 1- Mr. Mohamed Ali   | Head Quarter  |
| 6. Auto CAD Operator       | 1- Ms. Heba Mahmoud<br>2- Ms. Nour Abbas   | Head Quarter  |

**(5) JICA Expert Team**

JICA Expert Team consists of the Japanese Team and Egyptian Team as follows:

**Table 1-7 JICA Expert Team**

| Expert  | Name                    |
|---|-------------------------|
| [Japanese Team]                                   |                         |
| - Chief Advisor/Water Supply Planning             | Mr. Masahiro Takeuchi   |
| - Expert/UFW Reduction                            | Mr. Masatoshi Seno      |
| - Leak Detection                                  | Mr. Akihiko Okazaki     |
| - Expert/SOP Activity for Water Supply Facilities | Mr. Noboru Saeki        |
| - Expert/SOP Activity for Water Supply Facilities | Mr. Keizo Kimura        |
| - Coordinator/Hydraulic Analysis Network          | Mr. Mitsuhiro Omori     |
| - Electrical Equipment                            | Dr. Ashraf Ahamed       |
| - Hydrogeology                                    | Mr. Nobuyuki Iijima     |
| - Water Quality Control                           | Mr. Takashi Hara        |
| [Egyptian Team]                                   |                         |
| - Project Facilitator                             | Mr. Mohamed Nagi        |
| - Senior Engineer for UFW Reduction Activity      | Dr. Mohamed Sobhy       |
| - Senior Engineer for UFW Reduction Activity      | Mr. Mostafa Moawed      |
| - Senior Engineer for SOP Activity                | Mr. Mahmoud Khalaf      |
| - Senior Engineer for SOP Activity                | Mr. Mahmoud Abu El Naga |

## CHAPTER 2 DEVELOPMENT OF PDM

PDM (Project Design Matrix) and PO (Plan of Operation) had been revised during the Project and approved at JCC. Contents of the revisions of PDM are as shown in Table 2-1.

**Table 2-1 Development of PDM and PO**

| PDM & PO   | Version                  | Revision Date                 | Approved at         | Contents   |
|------------|--------------------------|-------------------------------|---------------------|--|
| PDM0 & PO0 | Original Version         | 3 <sup>rd</sup> December 2006 | 1 <sup>st</sup> JCC | PDM0 and PO0 was confirmed between the Egyptian side and the Japanese side at the record of discussions (R/D) and approved at 1 <sup>st</sup> JCC. |
| PDM1 & PO1 | 1 <sup>st</sup> Revision | 10 <sup>th</sup> June 2007    | 2 <sup>nd</sup> JCC | Revisions were made taking into account the action plans for UFW reduction activity and SOP activity   |
| PDM2 & PO2 | 2 <sup>nd</sup> Revision | 4 <sup>th</sup> March 2008    | 3 <sup>rd</sup> JCC | Revisions were made after the mid-term monitoring survey and by setting targets of UFW and leakage ratios.   |
| PDM3 & PO3 | 3 <sup>rd</sup> Revision | 10 <sup>th</sup> July 2008    | 4 <sup>th</sup> JCC | Revisions were made for the targets of UFW and leakage ratios taking into account the actual results in UFW reduction activity                     |

PDM0 to PDM3 are shown in Table 2-2 to 2-5 respectively. PO is applied in the implementation plan and shall be referred to Figure 5-1, 5-2 in Chapter 5.

**Table 2-2 PDM0 (Original at the time of R/D)**

**Project Design Matrix (PDM0)**

**Project Title: The Project for Improvement of Management Capacity of Operation and Maintenance for SHAPWASCO**

**Target Area : Sharkia Governorate, Egypt**

**Target Group : Staff of SHAPWASCO**

**Duration : FY2006 – FY2009**

**Final Beneficiaries : People in Sharkia Governorate**

**Date : June 13, 2006**

| Narrative Summary   | Objectively Verifiable Indicators   | Means of Verification   | Important Assumption   |
|---|---|---|--|
| <b>Overall Goal</b>   |   |   |  |
| Management capacity of operation and maintenance of water supply facilities is improved in Sharkia Governorate.         | 1 Performance indicators in the field of management capacity of operation and maintenance are improved for all branches in the Governorate.   | SHAPWASCO quarterly report submitted to HCWW  |  |
| <b>Project Purpose</b>  |   |   |  |
| Management capacity of operation and maintenance of water supply facilities is improved in target areas. <sup>(1)</sup> | 1 Performance indicators in the field of management capacity of operation and maintenance are improved in target areas. <sup>(2)</sup><br><br>2. Activities on UFW and SOPs are incorporated into the routine work. | SHAPWASCO quarterly report submitted to HCWW<br><br>Organogram of SHAPWASCO, Questionnaire survey, interviews | Sector policy of the Egyptian government will not drastically change on management of water supply services.   |
| <b>Outputs</b>  |   |   |  |
| 1. Unaccounted-for water (UFW) ratio is reduced in the pilot project areas.   | 1-1 Volume of unaccounted-for water can be properly measured.<br><br>1-2 Unaccounted-for water ratio is reduced compared with the baseline data obtained at the beginning of the Project.                           | Project records<br><br>Project records  | Any change of development assistant policy by other donors to improve the management of water supply service will not adversely affect the Project implementation. |
| 2. Operation and maintenance capacity of water supply facilities is strengthened.                                       | 2-1 Manuals for management of O&M are developed and updated.  | Project records   |  |
|   | 2-2 The plan for the management of O&M is developed.  | Project records   |  |
|   | 2-3 Level of applying knowledge and skills acquired through OJT   | Questionnaire survey, interviews  |  |

Note (1) Target areas for output 1 are the pilot project areas specified by the Project in Zagazig City, Zagazig Markaz, Hihya Markaz, Diarb Nigm Markaz and Ibrahimiya Markaz, respectively.

(2) Specific indicators are selected from those in quarterly report to HCWW, such as the percentage of metered connections, the percentage of working meters, etc.



| Activities   | Inputs  |   | Important Assumption  |
|--|---|---|---|
|  | Japanese Side   | Egyptian Side   |   |
| <p><b>1 Unaccounted-for water (UFW) ratio is reduced in the pilot project areas.</b></p> <p>1-1 Analyze the current situation on UFW and prepare plan for UFW reduction</p> <p>1-2 Select pilot project areas</p> <p>1-3 Organize UFW reduction teams</p> <p>1-4 Prepare pipe network drawings of the pilot project area</p> <p>1-5 Survey actual conditions of UFW, analyze contents of UFW and measure UFW ratio in the pilot project area</p> <p>1-6 Conduct on-the-job training for SHAPWASCO staff on leakage detection</p> <p>1-7 Implement pipe repairing and commercial loss reduction programs</p> <p>1-8 Conduct public awareness campaign for water saving</p> <p>1-9 Conduct post-evaluation of UFW ratio.</p> <p><b>2 Operation and maintenance capacity of water supply facilities is strengthened.</b></p> <p>2-1 Survey current conditions of water supply facilities</p> <p>2-2 Conduct monitoring of wells</p> <p>2-3 Organize standard operational procedures (SOP) team</p> <p>2-4 Establish the system for water quality control</p> <p>2-5 Establish the system to measure the quality of water production and transmission</p> <p>2-6 Study on optimum water distribution main with network hydraulic analysis and plan district-metering-zone (DMZ)</p> <p>2-7 Prepare SOPs for WTP, Fe/Mn removal plants and pumping stations</p> <p>2-8 Prepare textbooks for SOPs training</p> <p>2-9 Conduct on-the-job training for SHAPWASCO on SOPs</p> <p>2-10 Conduct workshop/seminars for SOPs</p> <p>2-11 Monitor the performance indicator regarding operation and maintenance and achievement level of staff performance</p> | <p>1. Experts</p> <ul style="list-style-type: none"> <li>● Chief Advisor</li> <li>● UFW reduction specialist</li> <li>● Leakage detection trainer</li> <li>● Water treatment specialist</li> <li>● Hydraulic engineer for network analysis</li> <li>● Electrical engineer</li> <li>● Mechanical engineer</li> <li>● Hydro-geologist</li> <li>● Water quality control specialist</li> </ul> <p>2. Equipment and materials</p> <p>3. Trainings</p> <p>4. Local cost</p> | <p>1. Counterparts</p> <p>2. Office space and facilities for experts</p> <p>3. Equipment</p> <p>4. Necessary information</p> <p>5. Local cost</p> | <p>Employees who received trainings by the Project will continuously work for SHAPWASCO.</p> <p>Personnel transfer of executive management will not affect the implementation of the Project.</p> <p>Funds from NOPWASD and Sharkia Governorate in related to the Project will be allocated as planned.</p> |
|  |   |   | <b>Pre-Conditions</b>   |
|  |   |   | The Hihya Water Treatment Plant (WTP) is successfully constructed as scheduled.   |



Table 2-3 PDM1 (1<sup>st</sup> Revision)

## Project Design Matrix-1 (PDM1)

Project Title: The Project for Improvement of Management Capacity of Operation and Maintenance for SHAPWASCO

Target Area : Sharkia Governorate, Egypt

Target Group : Staff of SHAPWASCO

Duration : FY2006 – FY2009

Final Beneficiaries : People in Sharkia Governorate

Date : June 10, 2007

| Narrative Summary   | Objectively Verifiable Indicators   | Means of Verification   | Important Assumption   |
|---|---|---|--|
| <b>[Overall Goal]</b><br>Management capacity of operation and maintenance of water supply facilities is improved in Sharkia Governorate.            | 1. Performance indicators in the field of management capacity of operation and maintenance are improved for all branches in the Governorate.  | SHAPWASCO quarterly report submitted to HCWW  |  |
| <b>[Project Purpose]</b><br>Management capacity of operation and maintenance of water supply facilities is improved in target areas. <sup>(1)</sup> | 1. Performance indicators in the field of management capacity of operation and maintenance are improved in target areas. <sup>(2)</sup><br><br>2. Activities on UFW and SOPs are incorporated into the routine work.  | SHAPWASCO quarterly report submitted to HCWW<br><br>Project Progress Report<br>Questionnaire survey<br>Organization chart   | Sector policy of the Egyptian government will not drastically change on management of water supply services. |
| <b>[Outputs]</b><br>1. Unaccounted-for water (UFW) ratio is reduced in the pilot project areas.   | 1-1 Water balance analysis can be conducted properly for the pilot project areas.<br><br>1-2 UFW ratio is reduced from xx% to xx% in the pilot project areas. (UFW ratio will be set by August 2007)<br><br>1-3 Leakage (real loss) ratio is reduced from xx% to xx% in the pilot project areas. (Leakage ratio will be set by August 2007)<br><br>1-4 At least three (3) members each of UFW team of Zagazig City and Hihya Markaz acquire leakage detection survey technique.<br><br>1-5 At least one (1) member each of UFW team of other Markazes related to the pilot project areas acquires leakage detection survey technique. | Project Progress Report<br><br>Project Progress Report<br><br>Project Progress Report<br><br>Test by JICA Expert<br>Project Progress Report<br><br>Test by JICA Expert<br>Project Progress Report |  |

| Narrative Summary   | Objectively Verifiable Indicators  | Means of Verification                          | Important Assumption   |
|---|--|--|--|
| 2. Operation and maintenance capacity of water supply facilities is strengthened. | 2-1 Basic system drawings of the facilities are prepared and updated at five (5) model facilities (2 WTPs, 1 FMRP, 1 BPS and 1 well station) which represent the facilities of SHAPWASCO.  | Project Progress Report                        | New Faqus WTP is handed over from NOPWASD to SHAPWASCO in due course.<br><br>New Faqus WTP is handed over from NOPWASD to SHAPWASCO in due course. |
|   | 2-2 Manuals for management of O&M are developed and updated as SOPs by the following SOP packages for plant components and for three activity categories, i.e. Operation, Maintenance and Water Quality Control for each model facilities.<br>- Not less than twenty (20) SOP packages at WTP<br>- Not less than five (5) SOP packages at FMRP, BPS and well stations. | Project Progress Report                        |  |
|   | 2-3 For the application of SOPs to the field operation, class room training and OJT to operators are conducted at all the five (5) model facilities.   | Project Progress Report                        |  |
|   | 2-4 Not less than eighty (80) percent of SOP/HQ and SOP/MF members acquire the ability to apply knowledge and skills of SOP.   | Test by JICA Expert<br>Project Progress Report |  |
|   | 2-5 O&M Plan is developed at not less than one (1) model WTP.  | Project Progress Report                        |  |
|   | 2-6 Water quality control system applying the new HCWW regulation is prepared.   | Project Progress Report                        |  |
|   | 2-7 Well inventory is prepared with a standard form and the first round of investigation is conducted for all the SHAPWASCO well stations.   | Project Progress Report                        |  |
|   | 2-8 Hydraulic analysis is done for not less than two pilot project areas.  | Project Progress Report                        |  |

Note (1) Target areas for output 1 are the pilot project areas specified by the Project in Zagazig City, Zagazig Markaz, Hihya Markaz, Diarb Nigm Markaz and Ibrahimiya Markaz, respectively.  
Target areas for output 2 are all the water supply facilities except compact units.

(2) Following PI has been selected as a specific indicator.

- Percentage of measured water production (%), etc.

Volume of measured production water / total volume of produced water

Volume of measured production water : means total volume of measured produced water in stations equipped with meters working in cubic meter



| Activities  | Inputs  |   | Important Assumption   |
|---|---|---|--|
|   | Japanese Side   | Egyptian Side   |  |
| <b>1 Unaccounted-for water (UFW) ratio is reduced in the pilot project areas.</b><br><b>1-1 General</b><br>(1) Analyzing the current situation on UFW<br>(2) Selecting candidate areas for pilot project areas<br>(3) Organizing UFW reduction teams<br>(4) Formulating an action plan for UFW reduction<br>(5) Conducting water conservation campaign<br>(6) Formulating long-term pipe replacement plan for preventive works<br>(7) Holding workshops and seminars<br><b>1-2 Actions</b><br>U1 Conducting training of C/P staff at Mostrod Training Center<br>U2 Conducting leakage (minimum night flow : MNF) survey for candidate areas<br>U3 Determining six (6) pilot project areas<br>U4 Preparing GIS drawings<br>U5 Learning experiences of Jordan UFW reduction project<br>U6 Making field survey of distribution network<br>U7 Surveying installation conditions of water meters and conducting meter readings<br>U8 Measuring metering error for working meters and water wastage in the house<br>U9 Conducting MNF survey<br>U10 Making water balance analysis before repair works<br>U11 Conducting leakage detection survey<br>U12 Repairing leaking parts<br>U13 Conducting MNF survey (including meter readings) after repair works<br>U14 Making water balance analysis after repair works and its evaluation | <b>1. Experts</b><br>- Chief Advisor<br>- UFW reduction specialist<br>- Leakage detection trainer<br>- Water treatment specialist<br>- Hydraulic engineer for network analysis<br>- Electrical engineer<br>- Mechanical engineer<br>- Hydro-geologist<br>- Water quality control specialist<br><br><b>2. Equipment and materials</b><br><br><b>3. Trainings</b><br><br><b>4. Local cost</b> | <b>1. Counterparts</b><br>- Project director<br>- Project manager<br>- UFW teams<br>- SOP teams<br><br><b>2. Office space and facilities for experts</b><br><br><b>3. Equipment</b><br><br><b>4. Necessary information</b><br><br><b>5. Local cost</b><br>All the cost for repairing leakage in distribution network of the pilot project areas | Employees who received trainings by the Project will continuously work for SHAPWASCO.<br><br>Personnel transfer of executive management will not affect the implementation of the Project.<br><br>Funds from NOPWASD and SHAPWASCO in related to the Project will be allocated as planned. |

| Activities   | Inputs        |   | Important Assumption  |
|--|---------------|---|-----------------------|
|  | Japanese Side | Egyptian Side   |                       |
| <b>2 Operation and maintenance capacity of water supply facilities is strengthened</b> |               | 6. Others   |                       |
| <b>2-1 General</b>   |               | - Civil works, electrical works and other necessary works for the installation of flow meters |                       |
| (1) Surveying current conditions of water supply facilities                            |               | - Measurement of flow rate by the flow meters   |                       |
| (2) Selecting Model Facilities (MF)  |               | - Monitoring of wells   |                       |
| (3) Organizing SOP/MF teams  |               | - MNF survey and countermeasure works for other areas than the pilot project areas            |                       |
| (4) Holding workshops and seminars   |               |   |                       |
| <b>2-2 Actions</b>   |               |   |                       |
| S1 Preparing basic system drawings   |               |   |                       |
| S2 Preparing unified forms of O&M records and reports                                  |               |   |                       |
| S3 Measuring intake / production water volume at 7 WTPs                                |               |   |                       |
| S4 Developing SOPs for model facilities  |               |   |                       |
| S5 Examining water distribution control practice in the network                        |               |   |                       |
| S5-1 Pilot project for distribution control in small areas                             |               |   |                       |
| S5-2 Hydraulic analysis of water supply and distribution                               |               |   | <b>Pre-Conditions</b> |
| S6 Applying SOPs in O&M  |               |   |                       |
| S7 Developing SOPs for the remaining facilities  |               |   |                       |
| S8 Formulating O&M plans   |               |   |                       |
| S9 Developing water quality control program  |               |   |                       |
| S10 Developing well inventory forms and monitoring well stations                       |               |   |                       |
| <b>2-3 Monitoring achievement of SOP</b>   |               |   |                       |

Abbreviations:

|  |                            |
|--|----------------------------|
| O&M : Maintenance and operation                          | FMRP : Fe/Mn removal plant |
| BPS : Booster pumping station                            | MF : Model facilities      |
| HCWW : Holding Company for Water and Wastewater          |                            |
| SHAPWASCO : Sharkia Potable Water and Sanitation Company |                            |

|   |                                      |
|---|--------------------------------------|
| WTP : Water treatment plant   | OJT : On-the-job training            |
| HQ : Headquarters   | SOP : Standard Operational Procedure |
| NOPWASD : National Organization for Potable Water and Sanitary Drainage |                                      |



Table 2-4 PDM2 (2<sup>nd</sup> Revision)

## Project Design Matrix-2 (PDM2)

Project Title: The Project for Improvement of Management Capacity of Operation and Maintenance for SHAPWASCO

Target Area : Sharkia Governorate, Egypt

Target Group : Staff of SHAPWASCO

Duration : FY2006 – FY2009

Final Beneficiaries : People in Sharkia Governorate

Date : March 4, 2008

| Narrative Summary  | Objectively Verifiable Indicators  | Means of Verification  | Important Assumption   |
|--|--|--|--|
| <b>[Overall Goal]</b><br>Management capacity of operation and maintenance of water supply facilities is improved in Sharkia Governorate. | 1. Performance indicators in the field of management capacity of operation and maintenance are improved for all branches in the Governorate.   | SHAPWASCO quarterly report submitted to HCWW   |  |
| <b>[Project Purpose]</b><br>Management capacity of operation and maintenance of water supply facilities is improved in target areas.     | 1. Performance indicators in the field of management capacity of operation and maintenance are improved in target areas.<br>2. Setting indicators for optimum electricity and chemical consumption and manpower standard working hours is conducted at model facilities for SOP activity.<br>3. Activities on UFW and SOPs are incorporated into the routine work.<br>- Activities on UFW reduction are expanded to other sites than the pilot project sites.<br>- Activities on SOPs are expanded to other facilities than the model facilities.                        | SHAPWASCO quarterly report submitted to HCWW<br><br>Monthly Report for O&M Project Progress Report<br><br>Monthly Report for O&M Project Progress Report<br>Questionnaire survey<br>Organization chart | Sector policy of the Egyptian government will not drastically change on management of water supply services. |
| <b>[Outputs]</b><br>1. Unaccounted-for water (UFW) ratio is reduced in the pilot project sites.  | 1-1 Water balance analysis can be conducted properly for the pilot project sites.<br>1-2 An average UFW ratio (initial) is reduced from 35% to 20% in the pilot project sites.<br>1-3 An average leakage (real loss) ratio (initial) is reduced from 30% to 15% in the pilot project sites.<br>1-4 At least three (3) members of each UFW team of Zagazig City and Hihya Markaz acquire leakage detection survey technique.<br>1-5 At least one (1) member of each UFW team of other Markazes related to the pilot projects acquires leakage detection survey technique. | Project Progress Report<br><br>Project Progress Report<br><br>Project Progress Report<br><br>Test by JICA Expert<br>Project Progress Report<br><br>Test by JICA Expert<br>Project Progress Report      |  |

| Narrative Summary   | Objectively Verifiable Indicators  | Means of Verification                          | Important Assumption |
|---|--|--|----------------------|
| 2. Operation and maintenance capacity of water supply facilities is strengthened. | 2-1 Basic system drawings of the facilities are prepared and updated at five (5) model facilities (2 WTPs, 1 FMRP, 1 BPS and 1 well station) which represent the facilities of SHAPWASCO.  | Project Progress Report                        |                      |
|   | 2-2 Manuals for management of O&M are developed and updated as SOPs by the following SOP packages for plant components and for three activity categories, i.e. Operation, Maintenance and Water Quality Control for each model facility.<br>- Not less than twenty (20) SOP packages at WTP<br>- Not less than five (5) SOP packages at FMRP, BPS and well stations. | Project Progress Report                        |                      |
|   | 2-3 For the application of SOPs to the field operation, class room training and OJT to operators are conducted at all the five (5) model facilities.   | Project Progress Report                        |                      |
|   | 2-4 Not less than eighty (80) percent of SOP/HQ and SOP/MF members acquire the ability to apply knowledge and skills of SOP.   | Test by JICA Expert<br>Project Progress Report |                      |
|   | 2-5 O&M Plan is developed at not less than one (1) WTP.  | Project Progress Report                        |                      |
|   | 2-6 Water quality control program applying the new HCWW regulation is prepared.  | Project Progress Report                        |                      |
|   | 2-7 Well inventory is prepared with a standard form and the first round of investigation is conducted for all the SHAPWASCO well stations.   | Project Progress Report                        |                      |
|   | 2-8 Hydraulic analysis is done for not less than two pilot project areas.  | Project Progress Report                        |                      |

Note (1) Following PI has been selected as a specific indicator.

- Percentage of measured water production (%), etc.

Volume of measured production water / total volume of produced water

Volume of measured production water: means total volume of measured produced water in stations equipped with meters working in cubic meter



| Activities   | Inputs  |   | Important Assumption  |
|--|---|---|---|
|  | Japanese Side   | Egyptian Side   |   |
| <p><b>1 Unaccounted-for water (UFW) ratio is reduced in the pilot project sites.</b></p> <p><b>1-1 General</b></p> <p>(1) Analyzing the current situation on UFW</p> <p>(2) Organizing UFW reduction teams</p> <p>(3) Selecting candidate areas for pilot project sites</p> <p>(4) Formulating an action plan for UFW reduction activity</p> <p>(5) Conducting water conservation campaign</p> <p>(6) Formulating long-term pipe replacement plan for preventive works</p> <p>(7) Formulating a plan for expanding UFW reduction activity to the other Markazes than the pilot project areas</p> <p>(8) Holding workshops and seminars</p> <p><b>1-2 Actions</b></p> <p>U1 Conducting training of C/P staff at Mostrod Training Center</p> <p>U2 Conducting leakage (minimum night flow : MNF) survey for candidate areas</p> <p>U3 Determining six (6) pilot project sites</p> <p>U4 Preparing GIS drawings</p> <p>U5 Learning experiences of Jordan UFW reduction project</p> <p>U6 Making field survey of distribution network</p> <p>U7 Surveying working conditions of water meters and conducting meter readings</p> <p>U8 Measuring metering error for working meters and water wastage in the house</p> <p>U9 Conducting MNF survey</p> <p>U10 Making water balance analysis before repair works</p> <p>U11 Conducting leakage detection survey</p> <p>U12 Repairing leaking parts</p> <p>U13 Conducting MNF survey (including meter readings) after repair works</p> <p>U14 Making water balance analysis after repair works and its evaluation</p> | <p>1. Experts</p> <ul style="list-style-type: none"> <li>- Chief Advisor</li> <li>- UFW reduction specialist</li> <li>- Leakage detection trainer</li> <li>- Water treatment specialist</li> <li>- Hydraulic engineer for network analysis</li> <li>- Electrical engineer</li> <li>- Mechanical engineer</li> <li>- Hydro-geologist</li> <li>- Water quality control specialist</li> </ul> <p>2. Equipment and materials</p> <p>3. Trainings</p> <p>4. Local cost</p> | <p>1. Counterparts</p> <ul style="list-style-type: none"> <li>- Project director</li> <li>- Project manager</li> <li>- UFW teams</li> </ul> <p>2. Office space and facilities for experts</p> <p>3. Equipment</p> <p>4. Necessary information</p> <p>5. Local cost<br/>All the cost for repairing leakage in distribution network of the pilot project areas</p> <p>6. Others</p> <ul style="list-style-type: none"> <li>- Civil works, electrical works and other necessary works for the installation of flow meters</li> <li>- Measurement of flow rate by the flow meters</li> <li>- Monitoring of wells</li> <li>- MNF survey and countermeasure works for other areas than the pilot project areas</li> </ul> | <p>Employees who received trainings by the Project will continuously work for SHAPWASCO.</p> <p>Personnel transfer of executive management will not affect the implementation of the Project.</p> <p>Funds from NOPWASD and SHAPWASCO in related to the Project will be allocated as planned.</p> |

| Activities  | Inputs        |               | Important Assumption  |
|---|---------------|---------------|-----------------------|
|   | Japanese Side | Egyptian Side |                       |
| <b>2 Operation and maintenance capacity of water supply facilities is strengthened</b><br><b>2-1 General</b><br>(1) Surveying current conditions of water supply facilities<br>(2) Selecting Model Facilities (MF)<br>(3) Organizing SOP/MF teams<br>(4) Formulating an action plan for SOP activity<br>(5) Holding workshops and seminars<br><b>2-2 Actions</b><br>S1 Preparing basic system drawings<br>S2 Preparing unified forms of O&M records and reports<br>S3 Measuring intake / production water volume at seven (7) WTPs<br>S4 Developing SOPs for model facilities<br>S5 Examining water distribution control practice in the network<br>S5-1 Pilot project for distribution control in small areas<br>S5-2 Hydraulic analysis of water supply and distribution<br>S6 Applying SOPs in O&M<br>S7 Developing SOPs for the remaining facilities<br>S8 Formulating O&M plans<br>S9 Developing water quality control program<br>S10 Developing well inventory forms and monitoring wells<br><b>2-3 Monitoring achievement of SOP</b> |               |               |                       |
|   |               |               | <b>Pre-Conditions</b> |

Abbreviations:

O&amp;M : Maintenance and operation

FMRP : Fe/Mn removal plant

WTP : Water treatment plant

OJT : On-the-job training

BPS : Booster pumping station

MF : Model facilities

HQ : Headquarters

SOP : Standard Operational Procedure

HCWW : Holding Company for Water and Wastewater

NOPWASD : National Organization for Potable Water and Sanitary Drainage

SHAPWASCO : Sharkia Potable Water and Sanitation Company



Table 2-5 PDM3 (3<sup>rd</sup> Revision)

## Project Design Matrix-3 (PDM3)

Project Title: The Project for Improvement of Management Capacity of Operation and Maintenance for SHAPWASCO

Target Area : Sharkia Governorate, Egypt

Target Group : Staff of SHAPWASCO

Duration : FY2006 – FY2009

Final Beneficiaries : People in Sharkia Governorate

Date : 9<sup>th</sup> July 2008

| Narrative Summary  | Objectively Verifiable Indicators  | Means of Verification  | Important Assumption   |
|--|--|--|--|
| <b>[Overall Goal]</b><br>Management capacity of operation and maintenance of water supply facilities is improved in Sharkia Governorate. | 1. Performance indicators in the field of management capacity of operation and maintenance are improved for all branches in the Governorate.   | SHAPWASCO quarterly report submitted to HCWW   |  |
| <b>[Project Purpose]</b><br>Management capacity of operation and maintenance of water supply facilities is improved in target areas.     | 1. Performance indicators in the field of management capacity of operation and maintenance are improved in target areas.<br>2. Setting indicators for optimum electricity and chemical consumption and manpower standard working hours is conducted at model facilities for SOP activity.<br>3. Activities on UFW and SOPs are incorporated into the routine work.<br>- Activities on UFW reduction are expanded to other sites than the pilot project sites.<br>- Activities on SOPs are expanded to other facilities than the model facilities.                  | SHAPWASCO quarterly report submitted to HCWW<br><br>Monthly Report for O&M<br>Project Progress Report<br><br>Monthly Report for O&M<br>Project Progress Report<br>Questionnaire survey<br>Organization chart | Sector policy of the Egyptian government will not drastically change on management of water supply services. |
| <b>[Outputs]</b><br>1. Unaccounted-for water (UFW) ratio is reduced in the pilot project sites.  | 1-1 Water balance analysis can be conducted properly for the pilot project sites.<br>1-2 An average UFW ratio (initial) is reduced by 13 points in the pilot project sites.<br>1-3 An average leakage (real loss) ratio (initial) is reduced by 13 points in the pilot project sites.<br>1-4 At least three (3) members of each UFW team of Zagazig City and Hihya Markaz acquire leakage detection survey technique.<br>1-5 At least one (1) member of each UFW team of other Markazes related to the pilot projects acquires leakage detection survey technique. | Project Progress Report<br><br>Project Progress Report<br><br>Project Progress Report<br><br>Test by JICA Expert<br>Project Progress Report<br><br>Test by JICA Expert<br>Project Progress Report            |  |

| Narrative Summary   | Objectively Verifiable Indicators  | Means of Verification                          | Important Assumption |
|---|--|--|----------------------|
| 2. Operation and maintenance capacity of water supply facilities is strengthened. | 2-1 Basic system drawings of the facilities are prepared and updated at five (5) model facilities (2 WTPs, 1 FMRP, 1 BPS and 1 well station) which represent the facilities of SHAPWASCO.  | Project Progress Report                        |                      |
|   | 2-2 Manuals for management of O&M are developed and updated as SOPs by the following SOP packages for plant components and for three activity categories, i.e. Operation, Maintenance and Water Quality Control for each model facility.<br>- Not less than twenty (20) SOP packages at WTP<br>- Not less than five (5) SOP packages at FMRP, BPS and well stations. | Project Progress Report                        |                      |
|   | 2-3 For the application of SOPs to the field operation, class room training and OJT to operators are conducted at all the five (5) model facilities.   | Project Progress Report                        |                      |
|   | 2-4 Not less than eighty (80) percent of SOP/HQ and SOP/MF members acquire the ability to apply knowledge and skills of SOP.   | Test by JICA Expert<br>Project Progress Report |                      |
|   | 2-5 O&M Plan is developed at not less than one (1) WTP.  | Project Progress Report                        |                      |
|   | 2-6 Water quality control program applying the new HCWW regulation is prepared.  | Project Progress Report                        |                      |
|   | 2-7 Well inventory is prepared with a standard form and the first round of investigation is conducted for all the SHAPWASCO well stations.   | Project Progress Report                        |                      |
|   | 2-8 Hydraulic analysis is done for not less than two pilot project areas.  | Project Progress Report                        |                      |

Note (1) Following PI has been selected as a specific indicator.

- Percentage of measured water production (%), etc.

Volume of measured production water / total volume of produced water

Volume of measured production water: means total volume of measured produced water in stations equipped with meters working in cubic meter



| Activities  | Inputs  |  | Important Assumption  |
|---|---|--|---|
|   | Japanese Side   | Egyptian Side  |   |
| <p><b>1 Unaccounted-for water (UFW) ratio is reduced in the pilot project sites.</b></p> <p><b>1-1 General</b></p> <p>(1) Analyzing the current situation on UFW</p> <p>(2) Organizing UFW reduction teams</p> <p>(3) Selecting candidate areas for pilot project sites</p> <p>(4) Formulating an action plan for UFW reduction activity</p> <p>(5) Conducting water conservation campaign</p> <p>(6) Formulating long-term pipe replacement plan for preventive works</p> <p>(7) Formulating a plan for expanding UFW reduction activity to the other Markazes than the pilot project areas</p> <p>(8) Holding workshops and seminars</p> <p><b>1-2 Actions</b></p> <p>U1 Conducting training of C/P staff at Mostrod Training Center</p> <p>U2 Conducting leakage (minimum night flow : MNF) survey for candidate sites</p> <p>U3 Determining nine (9) pilot project sites</p> <p>U4 Preparing GIS drawings</p> <p>U5 Learning experiences of Jordan UFW reduction project</p> <p>U6 Making field survey of distribution network</p> <p>U7 Surveying working conditions of water meters and conducting meter readings</p> <p>U8 Measuring metering error for working meters and water wastage in the house</p> <p>U9 Conducting MNF survey</p> <p>U10 Making water balance analysis before repair works</p> <p>U11 Conducting leakage detection survey</p> <p>U12 Repairing leaking parts</p> <p>U13 Conducting MNF survey (including meter readings) after repair works</p> <p>U14 Making water balance analysis after repair works and its evaluation</p> | <p>1. Experts</p> <ul style="list-style-type: none"> <li>- Chief Advisor</li> <li>- UFW reduction specialist</li> <li>- Leakage detection trainer</li> <li>- Water treatment specialist</li> <li>- Hydraulic engineer for network analysis</li> <li>- Electrical engineer</li> <li>- Mechanical engineer</li> <li>- Hydro-geologist</li> <li>- Water quality control specialist</li> </ul> <p>2. Equipment and materials</p> <p>3. Trainings</p> <p>4. Local cost</p> | <p>1. Counterparts</p> <ul style="list-style-type: none"> <li>- Project director</li> <li>- Project manager</li> <li>- UFW teams</li> <li>- SOP teams</li> </ul> <p>2. Office space and facilities for experts</p> <p>3. Equipment</p> <p>4. Necessary information</p> <p>5. Local cost<br/>All the cost for repairing leakage in distribution network of the pilot project areas</p> <p>6. Others</p> <ul style="list-style-type: none"> <li>- Civil works, electrical works and other necessary works for the installation of flow meters</li> <li>- Measurement of flow rate by the flow meters</li> <li>- Monitoring of wells</li> <li>- MNF survey and countermeasure works for other areas than the pilot project areas</li> </ul> | <p>Employees who received trainings by the Project will continuously work for SHAPWASCO.</p> <p>Personnel transfer of executive management will not affect the implementation of the Project.</p> <p>Funds from NOPWASD and SHAPWASCO in related to the Project will be allocated as planned.</p> |

## **CHAPTER 3 PROJECT ACHIEVEMENT**

### **3.1 Achievement for Over Goal**

The project achievement for the Over Goal for the Project is described in Table 3-1. They are compared with PDM3 as shown in Table 2-5.

### **3.2 Achievement for Project Purpose**

The project achievement for the Project Purpose for the Project is described in Table 3-1. They are compared with PDM3 as shown in Table 2-5.

### **3.3 Achievement for Outputs**

The project achievement for the Outputs for the Project is described in Table 3-1. They are compared with PDM3 as shown in Table 2-5.

Table 3-1 Project Indicators and Achievement Levels

| Narrative Summary  | Objectively Verifiable Indicators  | Achievement  |
|--|--|--|
| <p><b>[Overall Goal]</b><br/>Management capacity of operation and maintenance of water supply facilities is improved in Sharkia Governorate.</p> | <p>1. Performance indicators in the field of management capacity of operation and maintenance are improved for all branches in the Governorate.</p>  | <p>In this project, following PIs have been set for Overall Goal (refer to section 3.4 for the details):</p> <ol style="list-style-type: none"> <li>1) Long-term UFW ratio for the year of 2015 to 2030</li> <li>2) Power consumption per unit production water volume</li> <li>3) Chlorine consumption per unit production water volume</li> <li>4) Alum consumption per unit production water volume</li> <li>5) Ratio of production water volume to intake water volume</li> </ol>  |
| <p><b>[Project Purpose]</b><br/>Management capacity of operation and maintenance of water supply facilities is improved in target areas.</p>     | <p>1. Performance indicators in the field of management capacity of operation and maintenance are improved in target areas.</p> <p>2. Setting indicators for optimum electricity and chemical consumption and manpower standard working hours is conducted at model facilities for SOP activity</p> <p>3. Activities on UFW and SOPs are incorporated into the routine work.</p> <ul style="list-style-type: none"> <li>➤ Activities on UFW reduction are expanded to other sites than the pilot project sites.</li> </ul> | <p>PI was set at percentage of the measured production to the total estimated production of water treatment plants. PI was improved from 0% to 54% at the end of the Project.</p> <p>Measurements of water flows and supply have been undertaken and recorded at two model WTPs at Abbasa and Zagazig. As a result, SHAPWASCO was able to obtain sufficient data to set indicators for electricity and chemical consumption.</p> <p>For Zagazig WTP, they were set at 0.28kWh/m<sup>3</sup> for electricity, 26.7mg/m<sup>3</sup> for aluminum sulfate and 5.37mg/m<sup>3</sup> for chlorine respectively. These indicators were then compared to those of the Hihya WTP that was constructed under the Japanese Grant Aid for identification of areas of improvement and setting of optimum indicators.</p> <p>As the indicator related to manpower standard working hours, PI as unit production water volume per person were set. Also, number and category of required staff in each facility was incorporated in SOP document.</p> <p>As for UFW reduction activity, in addition to the three (3) pilot project areas in Abu Hamad Markaz, Menia Alqamah Markaz and Bilbais Markaz that were added at the time of mid-term monitoring, two (2) more pilot projects in Zagazig Markaz and Ibrahimiya Markaz have been conducted during the project period. Expansion of UFW activity is being fostered in the following:</p> <ol style="list-style-type: none"> <li>1) Flow meter installation chambers were constructed with concrete in all candidate sites of the pilot project site in one city and seven Markaz and ready for starting activities</li> <li>2) Data on leakages in all target areas are being collected and have been put into the database which could be used as a tool to develop pipe</li> </ol> |



| Narrative Summary  | Objectively Verifiable Indicators  | Achievement  |
|--|--|--|
|  | <ul style="list-style-type: none"> <li>- Activities on SOPs are expanded to other facilities than the model facilities.</li> </ul>   | <p>replacement plan</p> <p>3) All 12 members of core UFW team at HQ, Zagazig East and Hihya Markaz have equipped with sufficient expertise to train other SHAPWASCO staff members</p> <p>4) Construction of a leakage detection training yard at Hihya Central Station has been initiated by SHAPWASCO and is expected to provide platform of further training not only for all other staff members at target areas but in all over the Governorate.</p> <p>Incorporation of SOP activities into work routine and their expansion to other facilities have been confirmed by:</p> <p>1) Filter washing method has already been incorporated into routine work at two model WTPs and has been started its application at another WTP in Kafr Saqr</p> <p>2) Monitoring on chemical consumption has been undertaken and data is being regularly collected. Based on the collected data, improvement activity for reduction is started.</p> <p>3) Monitoring on flow data and the data is being regularly collected at all WTPs except WTPs under rehabilitation.</p> <p>4) OJT on chlorine usage control was conducted and SOPs were then developed at Qenayat Fe/Mn removal plant. Moreover, HCWW has already distributed a draft copy of SOPs to other water companies which are expected to be used as a reference for preparing O&amp;M manual throughout the country.</p> |
| <p><b>[Outputs]</b></p> <p>1. Unaccounted-for water (UFW) ratio is reduced in the pilot project areas.</p> | <p>1-1 Water balance analysis can be conducted properly for the pilot project sites.</p> <p>1-2 An average UFW ratio (initial) is reduced by 13 points in the pilot project sites.</p> <p>1-3 An average leakage (real loss) ratio (initial) is reduced by 13 points in the pilot project sites.</p> <p>1-4 At least three (3) members of each UFW team of Zagazig City and Hihya Markaz acquire leakage detection survey technique.</p> <p>1-5 At least one (1) member each of UFW team of other Markazes related to the pilot project areas acquires leakage detection survey technique.</p> | <p>Water balance analysis has been done properly for nine (9) pilot project sites and two (2) sites for the expansion activity.</p> <p>UFW ratio is reduced by 12.2 points in average for nine (9) pilot project sites and two (2) sites for the expansion activity.</p> <p>Leakage ratio is reduced by 12.1 points in average for nine (9) pilot project sites and two (2) sites for the expansion activity.</p> <p>Following members have acquired the technique.</p> <ul style="list-style-type: none"> <li>- UFW/HQ team: 4</li> <li>- Zagazig City UFW team: 3 (Zagazig East)</li> <li>- Hihya Markaz: 3</li> </ul> <p>Following members have acquired the technique.</p> <ul style="list-style-type: none"> <li>- Zagazig West: 3</li> <li>- Zagazig Markaz: 1</li> <li>- Ibrahimiya Markaz: 2</li> <li>- Diarb Nigm Markaz: 2</li> </ul>  |

| Narrative Summary   | Objectively Verifiable Indicators  | Achievement  |
|---|--|--|
| 2. Operation and maintenance capacity of water supply facilities is strengthened. | 2-1 Basic system drawings of the facilities are prepared and updated at five (5) model facilities (2 WTPs, 1 FMRP, 1 BPS and 1 well station) which represent the facilities of SHAPWASCO.  | <ul style="list-style-type: none"> <li>- Abu Hamad Markaz: 1</li> <li>- Bilbais Markaz: 1 and Menia Alqamah Markaz: 1</li> </ul> Basic system drawings of the facilities have been prepared and updated at five (5) model facilities (2 WTPs, 1 FMRP, 1 BPS and 1 well station).   |
|   | 2-2 Manuals for management of O&M are developed and updated as SOPs by the following SOP packages for plant components and for three activity categories, i.e. Operation, Maintenance and Water Quality Control for each model facilities.<br><ul style="list-style-type: none"> <li>- Not less than twenty (20) SOP packages at WTP</li> <li>- Not less than five (5) SOP packages at FMRP, BPS and well stations.</li> </ul> | SOPs have been developed in the form of the following SOP packages for plant components and for three activity categories. <ul style="list-style-type: none"> <li>- Thirty-five (34) SOP packages at WTP</li> <li>- Twelve (20) SOP packages at FMRP</li> <li>- Nine (9) SOP packages at BPS</li> <li>- Eight (8) SOP packages at WPS</li> </ul> |
|   | 2-3 For the application of SOPs to the field operation, class room training and OJT to operators are conducted at all the five (5) model facilities.   | SOPs have been applied as follows: <ul style="list-style-type: none"> <li>- Abbasa WTP and Zagazig WTP</li> <li>- Kafr Farag and Qenayat Fe/Mn removal plants</li> <li>- Bilbais booster pump station</li> <li>- Asloughi well station</li> </ul>  |
|   | 2-4 Not less than eighty (80) percent of SOP/HQ and SOP/MF members acquire the ability to apply knowledge and skills of SOP.   | Out of 3 staff for SOP/HQ team: 3 staff has acquired the ability.<br>Out of 8 staff for SOP/MF team: To be tested in Phase-4   |
|   | 2-5 O&M Plan is developed at not less than one (1) model WTP.  | O&M plan has been prepared in Abbasa WTP.  |
|   | 2-6 Water quality control system applying the new HCWW regulation is prepared.   | Water quality control program has been prepared for Abbasa WTP and Zagazig WTP. Auditing system for laboratory quality control has been prepared and applied to Abbasa WTP and Zagazig WTP.  |
|   | 2-7 Well inventory is prepared with a standard form and the first round of investigation is conducted for all the SHAPWASCO well stations.   | Well inventory has been prepared and second round of well monitoring is being conducted.   |
|   | 2-8 Hydraulic analysis is done for not less than two pilot project areas.  | Hydraulic analysis has been done for the pilot project areas of Hihya Markaz and Zagazig East.   |

### 3.4 Setting Performance Indicators for Overall Goal

#### 3.4.1 UFW Reduction Activity

Performance indicator for UFW reduction activity is set as UFW ratio. The UFW ratios for evaluating improvement of O&M capacity of SHAPWASCO have been set for the years of 2015, 2020, 2025 and 2030 according to the results of the pilot projects as follows:

**Table 3-2 PI for UFW Reduction Activity**

| Year | UFW Ratio (%) |
|------|---------------|
| 2015 | 27.0          |
| 2020 | 23.5          |
| 2025 | 21.0          |
| 2030 | 19.0          |

Conditions for setting PIs related to UFW reduction activities are as follows:

- It is assumed that 15 branches of SHAPWASCO conduct annually starting from 2012 UFW reduction activity at four districts which have similar house connections to the pilot project of the Project. In other words, UFW teams of SHAPWASCO will conduct activity annually at 60 districts (4 districts x 15 branches). By the activity at this pace, the first round of UFW reduction activity will be completed by the year 2030 in the whole SHAPWASCO service area. The second round will start from 2031.
- Service population at each district is set as 7,200 based on the result of the pilot project.
- Annual population growth is set as 2% which is applied by SHAPWASCO and distributed water volume is also set as 2.0%.
- Distributed water volume to each district is calculated as follows:  
(Distributed water volume in the whole governorate ÷ Population for the whole governorate) x service population in the district
- Initial UFW ratio at each district before conducting UFW reduction activity is set as 31.0%.
- UFW reduction point after UFW reduction activity by each UFW team is set as 12.2 points (or 0.122).
- UFW volume to be reduced is calculated as follows:  
Reduction volume of UFW = [Service Pop. at each district] x [Annual distributed water per capita] x [UFW Reduction point: 0.122]
- UFW ratio for each year is calculated as follows:  
UFW Ratio in each year = [UFW Ratio before activity : 31.0%] – [Total UFW volume up to the year ÷ Total distribution volume for SHAPAWASCO in the year]
- For the targets of UFW ratio from 2015 to 2030, calculated figures are rounded up to 0 or 5 after the decimal fractions.
- Taking into account the recurrence of leakage (increase of leakage after UFW reduction activity), each UFW team is required to review the target figure of UFW every 5 years by checking UFW ratio through minimum night flow survey at the districts (4 districts x 5 years = 20 districts) where leakage survey has been finished.

Table 3-3 shows the UFW ratios from 2009 to 2030 which have been calculated according to the above conditions.

**Table 3-3 Long-Term Targets of UFW Ratios for SHAPWASCO**

| Year | UFW Team | No. of UFW Reduction Activity Site | Service Population in Activity Site | Total Service Population in Activity Site (cumulative) | Total Population in Sharkia Gov. | Total Distributed Water for SHAPWASCO (m3/yr) | Water distributed per person per year (m3/cap./yr) | Distributed Water in Activity Site (m3/yr) | Reduction of UFW by volume (m3/yr) | Accumulation of UFW Reduction (m3/yr) | UFW after Activity (%) | Long Term Target (%) |
|------|----------|------------------------------------|-------------------------------------|--|----------------------------------|---|--|--|------------------------------------|---------------------------------------|------------------------|----------------------|
| 2009 | 3        | 12                                 | 86,400                              | 86,400   | 5,700,000                        | 246,000,000                                   | 43.158   | 3,728,842                                  | 454,919                            | 454,919                               | 30.82                  |                      |
| 2010 | 5        | 20                                 | 144,000                             | 230,400  | 5,814,000                        | 250,920,000                                   | 43.158   | 6,214,737                                  | 758,198                            | 1,213,117                             | 30.52                  |                      |
| 2011 | 10       | 40                                 | 288,000                             | 518,400  | 5,930,280                        | 255,938,400                                   | 43.158   | 12,429,474                                 | 1,516,396                          | 2,729,512                             | 29.93                  |                      |
| 2012 | 15       | 60                                 | 432,000                             | 950,400  | 6,048,886                        | 261,057,168                                   | 43.158   | 18,644,211                                 | 2,274,594                          | 5,004,106                             | 29.08                  |                      |
| 2013 | 15       | 60                                 | 432,000                             | 1,382,400  | 6,169,863                        | 266,278,311                                   | 43.158   | 18,644,211                                 | 2,274,594                          | 7,278,700                             | 28.27                  |                      |
| 2014 | 15       | 60                                 | 432,000                             | 1,814,400  | 6,293,261                        | 271,603,878                                   | 43.158   | 18,644,211                                 | 2,274,594                          | 9,553,293                             | 27.48                  |                      |
| 2015 | 15       | 60                                 | 432,000                             | 2,246,400  | 6,419,126                        | 277,035,955                                   | 43.158   | 18,644,211                                 | 2,274,594                          | 11,827,887                            | 26.73                  | <b>27.0</b>          |
| 2016 | 15       | 60                                 | 432,000                             | 2,678,400  | 6,547,508                        | 282,576,674                                   | 43.158   | 18,644,211                                 | 2,274,594                          | 14,102,481                            | 26.01                  |                      |
| 2017 | 15       | 60                                 | 432,000                             | 3,110,400  | 6,678,458                        | 288,228,208                                   | 43.158   | 18,644,211                                 | 2,274,594                          | 16,377,075                            | 25.32                  |                      |
| 2018 | 15       | 60                                 | 432,000                             | 3,542,400  | 6,812,028                        | 293,992,772                                   | 43.158   | 18,644,211                                 | 2,274,594                          | 18,651,668                            | 24.66                  |                      |
| 2019 | 15       | 60                                 | 432,000                             | 3,974,400  | 6,948,268                        | 299,872,627                                   | 43.158   | 18,644,211                                 | 2,274,594                          | 20,926,262                            | 24.02                  |                      |
| 2020 | 15       | 60                                 | 432,000                             | 4,406,400  | 7,087,234                        | 305,870,080                                   | 43.158   | 18,644,211                                 | 2,274,594                          | 23,200,856                            | 23.41                  | <b>23.5</b>          |
| 2021 | 15       | 60                                 | 432,000                             | 4,838,400  | 7,228,978                        | 311,987,481                                   | 43.158   | 18,644,211                                 | 2,274,594                          | 25,475,449                            | 22.83                  |                      |
| 2022 | 15       | 60                                 | 432,000                             | 5,270,400  | 7,373,558                        | 318,227,231                                   | 43.158   | 18,644,211                                 | 2,274,594                          | 27,750,043                            | 22.28                  |                      |
| 2023 | 15       | 60                                 | 432,000                             | 5,702,400  | 7,521,029                        | 324,591,776                                   | 43.158   | 18,644,211                                 | 2,274,594                          | 30,024,637                            | 21.75                  |                      |
| 2024 | 15       | 60                                 | 432,000                             | 6,134,400  | 7,671,450                        | 331,083,611                                   | 43.158   | 18,644,211                                 | 2,274,594                          | 32,299,230                            | 21.24                  |                      |
| 2025 | 15       | 60                                 | 432,000                             | 6,566,400  | 7,824,879                        | 337,705,283                                   | 43.158   | 18,644,211                                 | 2,274,594                          | 34,573,824                            | 20.76                  | <b>21.0</b>          |
| 2026 | 15       | 60                                 | 432,000                             | 6,998,400  | 7,981,376                        | 344,459,389                                   | 43.158   | 18,644,211                                 | 2,274,594                          | 36,848,418                            | 20.30                  |                      |
| 2027 | 15       | 60                                 | 432,000                             | 7,430,400  | 8,141,004                        | 351,348,577                                   | 43.158   | 18,644,211                                 | 2,274,594                          | 39,123,011                            | 19.86                  |                      |
| 2028 | 15       | 60                                 | 432,000                             | 7,862,400  | 8,303,824                        | 358,375,548                                   | 43.158   | 18,644,211                                 | 2,274,594                          | 41,397,605                            | 19.45                  |                      |
| 2029 | 15       | 60                                 | 432,000                             | 8,294,400  | 8,469,900                        | 365,543,059                                   | 43.158   | 18,644,211                                 | 2,274,594                          | 43,672,199                            | 19.05                  |                      |
| 2030 | 15       | 60                                 | 432,000                             | 8,726,400  | 8,639,298                        | 372,853,921                                   | 43.158   | 18,644,211                                 | 2,274,594                          | 45,946,792                            | 18.68                  | <b>19.0</b>          |
| 2031 | 15       | 60                                 | 432,000                             | 9,158,400  | 8,812,084                        | 380,310,999                                   | 43.158   | 18,644,211                                 | 2,274,594                          | 48,221,386                            | 18.32                  |                      |

### 3.4.2 SOP Activity

Among the water supply facilities for SHAPWASCO such as water treatment plants (WTP), iron/manganese removal plants, booster pump stations and well stations, the facilities in service at which flow meter is installed and working are as follows:

- Hihya WTP
- Zagazig WTP
- New Faqus WTP
- Kafr Saqr WTP
- Huseinia WTP
- Abbasa WTP

Since the accurate water production volume can be measured only at the above-mentioned WTPs, it is not possible to set performance indicator (PI) for assessment of the whole management of SHAPWASCO to be submitted to HCWW quarterly for the year.

Therefore, in this Project, PIs shall be set for improvement of O&M in 2010 using the monitored data for flow rate, electricity consumption, chlorine consumption and alum consumption. For PIs after the year 2011, monitored data for the previous year shall be applied for setting PIs of the following year for O&M improvement.

PIs have been set for the following:

**Table 3-4 PI for SOP Activities**

| No. | Performance Indicator   | Unit               |
|-----|---|--------------------|
| 1   | Power consumption per unit production water volume (PI-PW)      | kWh/m <sup>3</sup> |
| 2   | Chlorine consumption per unit production water volume (PI-CL)   | g/m <sup>3</sup>   |
| 3   | Alum consumption per unit production water volume (PI-AL)       | g/m <sup>3</sup>   |
| 4   | Ratio of production water volume to intake water volume (PI-EF) | ---                |

#### (1) Power Consumption per Unit Production Water Volume (PI-PW)

Annual target of PI as power consumption per unit water production volume was set for each WTP using the data from January to September 2009.

The results of PI at each plant for the period from January to September 2009 are as follows:



**Table 3-5 Result of PI for Power Consumption per Unit Water Production Volume in 2009**

| WTP       | PI-PW (kWh/m <sup>3</sup> ) |         |         | Difference from Average |         |
|-----------|-----------------------------|---------|---------|-------------------------|---------|
|           | Maximum                     | Minimum | Average | Maximum                 | Minimum |
| Hihya     | 0.327                       | 0.305   | 0.315   | 0.012                   | 0.010   |
| Zagazig   | 0.322                       | 0.287   | 0.300   | 0.022                   | 0.013   |
| NewFaqus  | 0.369                       | 0.247   | 0.289   | 0.080                   | 0.042   |
| Kafr Saqr | 0.359                       | 0.009   | 0.246   | 0.113                   | 0.237   |
| Huseinia  | 0.533                       | 0.277   | 0.439   | 0.094                   | 0.162   |
| Abbasa    | 0.485                       | 0.295   | 0.341   | 0.144                   | 0.046   |
| Average   | 0.399                       | 0.237   | 0.322   | ---                     | ---     |

Note: Huseinia WTP is operated under special condition on power supplying. Wattmeter is installed at the place near by water intake facility located 25km away from WTP. Power supply loss arises while supplying electric power for WTP.

Electric power is consumed mainly by main pumps, such as intake pumps and transmission pumps, at water treatment plants in SHAPWASCO. Therefore, operation and maintenance activities for main pumps shall be focused on for improvement of PI-PW value.

**Action to reduce power consumption at WTP**

Operation number of transmission pumps to maintain an adequate water pressure in the network shall be controlled.

Through the above action to reduce the electric power, annual target of PI as power consumption per unit water production volume is set for each WTP as shown in Table 3-6.

**Table 3-6 Target of PI for Power Consumption**

| WTP       | Annual Target                        |
|-----------|--------------------------------------|
| Hihya     | Not more than 0.30kWh/m <sup>3</sup> |
| Zagazig   | Not more than 0.30kWh/m <sup>3</sup> |
| New Faqus | Not more than 0.25kWh/m <sup>3</sup> |
| Kafr Saqr | Not more than 0.25kWh/m <sup>3</sup> |
| Huseinia  | Not more than 0.42kWh/m <sup>3</sup> |
| Abbasa    | Not more than 0.30kWh/m <sup>3</sup> |

## (2) Chlorine Consumption per Unit Production Water Volume (PI-CL)

Annual target of PI as chlorine consumption per unit water production volume was set for each WTP for the period from January to September 2009. The results of PI at each plant for the period from January to September 2009 are as follows:

**Table 3-7 Result of PI for Chlorine Consumption per Unit Water Production Volume in 2009**

| WTP       | PI-CL (g/m <sup>3</sup> ) |         |         | Difference from Average |         |
|-----------|---------------------------|---------|---------|-------------------------|---------|
|           | Maximum                   | Minimum | Average | Maximum                 | Minimum |
| Hihya     | 6.68                      | 4.68    | 5.43    | 1.25                    | 0.75    |
| Zagazig   | 5.01                      | 4.75    | 4.88    | 0.13                    | 0.13    |
| New Faqus | 8.53                      | 4.35    | 6.49    | 2.04                    | 2.14    |
| Kafr Saqr | 7.32                      | 5.37    | 6.16    | 1.16                    | 0.79    |
| Huseinia  | 5.07                      | 4.66    | 5.05    | 0.02                    | 0.39    |
| Abbasa    | 5.96                      | 4.08    | 4.74    | 1.22                    | 0.66    |
| Average   | 6.43                      | 4.65    | 5.46    | ---                     | ---     |

Chlorine consumption will be changed depending on raw water quality such as break point. Therefore, target of PI can not be set up as the value common to all the water treatment plant.

### Actions to reduce chlorine consumption

- Residual chlorine control procedures shall be continued after completion of this project.
- Periodical monitoring and review for pre and post chlorine dosing rate and free residual chlorine of treated water shall be done at end of the process.
- Adequate dosing flow rate of chlorine shall be maintained based on chlorine dosing rate and raw water flow rate.

Through the above actions, averaged annual target and monthly target of PI as chlorine consumption per unit water production volume is set for each WTP as shown in Table 3-8.

**Table 3-8 Target of PI for Chlorine Consumption**

| WTP       | Averaged Annual Target             | Monthly Target                            |
|-----------|------------------------------------|---|
| Hihya     | Not more than 4.5 g/m <sup>3</sup> | 4.5g/m <sup>3</sup> ± 0.5g/m <sup>3</sup> |
| Zagazig   | Not more than 4.5 g/m <sup>3</sup> | 4.5g/m <sup>3</sup> ± 0.5g/m <sup>3</sup> |
| New Faqus | Not more than 5.0 g/m <sup>3</sup> | 5.0g/m <sup>3</sup> ± 0.5g/m <sup>3</sup> |
| Kafr Saqr | Not more than 5.0 g/m <sup>3</sup> | 5.0g/m <sup>3</sup> ± 0.5g/m <sup>3</sup> |
| Huseinia  | Not more than 4.5 g/m <sup>3</sup> | 4.5g/m <sup>3</sup> ± 0.5g/m <sup>3</sup> |
| Abbasa    | Not more than 4.5 g/m <sup>3</sup> | 4.5g/m <sup>3</sup> ± 0.5g/m <sup>3</sup> |

## (3) Alum Consumption per Unit Water Production Volume (PI-AL)

Annual target of PI as alum consumption per unit water production volume was set for each WTP for the period from January to September 2009.

The results of PI at each plant for the period from January to September 2009 are as follows:

**Table 3-9 Result of PI for Alum Consumption per Unit Water Production Volume in 2009**

| WTP       | PI-AL(g/m <sup>3</sup> ) |         |         | Difference from Average |         |
|-----------|--------------------------|---------|---------|-------------------------|---------|
|           | Maximum                  | Minimum | Average | Maximum                 | Minimum |
| Hihya     | 26.1                     | 16.2    | 21.7    | 4.4                     | 5.5     |
| Zagazig   | 29.6                     | 22.8    | 25.1    | 4.5                     | 2.3     |
| New Faqus | 24.6                     | 18.8    | 22.0    | 2.6                     | 3.2     |
| Kafr Saqr | 22.1                     | 18.9    | 21.3    | 0.8                     | 2.4     |
| Huseinia  | 18.3                     | 12.4    | 14.4    | 3.9                     | 2.0     |
| Abbasa    | 52.2                     | 38.0    | 41.0    | 11.2                    | 3.0     |
|           | 27.8                     | 20.3    | 21.9    | 6.0                     | 1.6     |
| Total     | 24.8                     | 21.9    | 24.3    | ---                     | ---     |

Alum consumption will be changed depending on raw water quality such as turbidity, pH, algae accounts etc. Therefore, target of PI can not be set up as the value common to all the water treatment plant.

**Actions to reduce alum consumption**

- Alum dosing control procedures shall be continued after completion of this project.
- Periodical monitoring and review for alum dosing rate and turbidity of treated water shall be done at end of the process.
- Adequate dosing flow rate of alum shall be maintained based on alum dosing rate and raw water flow rate.
- Concentration of alum solution shall be adjusted according to adequate procedures for making alum solution.

Through the above actions, averaged annual target and monthly target of PI as alum consumption per unit water production volume is set for each WTP as shown in Table 3-10.

**Table 3-10 Target of PI for Alum Consumption**

| WTP       | Average d Annual Target          | Monthly Target                         |
|-----------|----------------------------------|--|
| Hihya     | Not more than 20g/m <sup>3</sup> | 20g/m <sup>3</sup> ± 2g/m <sup>3</sup> |
| Zagazig   | Not more than 23g/m <sup>3</sup> | 23g/m <sup>3</sup> ± 2g/m <sup>3</sup> |
| New Faqus | Not more than 20g/m <sup>3</sup> | 20g/m <sup>3</sup> ± 2g/m <sup>3</sup> |
| Kafr Saqr | Not more than 20g/m <sup>3</sup> | 20g/m <sup>3</sup> ± 2g/m <sup>3</sup> |
| Huseinia  | Not more than 15g/m <sup>3</sup> | 15g/m <sup>3</sup> ± 2g/m <sup>3</sup> |
| Abbasa    | Not more than 38g/m <sup>3</sup> | 38g/m <sup>3</sup> ± 2g/m <sup>3</sup> |

**(4) Ratio of Water Production Volume to Water Intake Volume (PI-EF)**

Annual target of PI as efficiency of water production was set for each WTP for the period from

January to September 2009.

The results of PI at each plant for the period from January to September 2009 are as follows:

**Table 3-11 Ratio of Water Production Volume and Water Intake Volume in 2009**

| WTP       | PI-EF (-) |         | Average |
|-----------|-----------|---------|---------|
|           | Maximum   | Minimum |         |
| Hihya     | 0.999     | 0.710   | 0.951   |
| Zagazig   | 0.933     | 0.853   | 0.898   |
| New Faqus | 0.963     | 0.628   | 0.846   |
| Kafr Saqr | 0.951     | 0.895   | 0.918   |
| Huseinia  | 0.930     | 0.853   | 0.913   |
| Abbasa    | 0.977     | 0.882   | 0.940   |
| Total     | 0.959     | 0.804   | 0.911   |

In view of recycling water from drainage facilities, Hihya WTP differs from other WTPs for SHAPWASCO. Water from drainage facilities returns to receiving well as recycled water at Hihya WTP.

Therefore, water intake volume can be reduced by the amount of recycled water.

**Actions to improve the ratio of water production volume and water intake volume**

- a) Backwashing regime and filtration time shall be reviewed by making assessment of filter media.
- b) Filtering load to the filter shall be reduced as much as possible by setting target of clarified water turbidity and residual chlorine.
- c) Periodical inspection of filter media shall be done and filter washing condition and water quality of clarified water shall be monitored.
- d) Leakage from concrete structures, pipes and valves of water treatment facilities such as sedimentation basin, filters, etc., shall be checked and repaired.

Through the above actions, averaged annual target of PI as ratio of water production volume to water intake volume is set for each WTP as shown in Table 3-12.

**Table 3-12 Target of PI for Efficiency of Water Production**

| WTP       | Averaged Annual Target |
|-----------|------------------------|
| Hihya     | Not less than 0.98     |
| Zagazig   | Not less than 0.93     |
| New Faqus | Not less than 0.93     |
| Kafr Saqr | Not less than 0.93     |
| Huseinia  | Not less than 0.93     |
| Abbasa    | Not less than 0.95     |

| Activities  | Inputs        |               | Important Assumption  |
|---|---------------|---------------|-----------------------|
|   | Japanese Side | Egyptian Side |                       |
| <b>2 Operation and maintenance capacity of water supply facilities is strengthened</b><br><b>2-1 General</b><br>(1) Surveying current conditions of water supply facilities<br>(2) Selecting Model Facilities (MF)<br>(3) Organizing SOP/MF teams<br>(4) Formulating an action plan for SOP activity<br>(5) Holding workshops and seminars<br><b>2-2 Actions</b><br>S1 Preparing basic system drawings<br>S2 Preparing unified forms of O&M records and reports<br>S3 Measuring intake / production water volume at seven (7) WTPs<br>S4 Developing SOPs for model facilities<br>S5 Examining water distribution control practice in the network<br>S5-1 Pilot project for distribution control in small areas<br>S5-2 Hydraulic analysis of water supply and distribution<br>S6 Applying SOPs in O&M<br>S7 Developing SOPs for the remaining facilities<br>S8 Formulating O&M plans<br>S9 Developing water quality control program<br>S10 Developing well inventory forms and monitoring wells<br><b>2-3 Monitoring achievement of SOP</b> |               |               |                       |
|   |               |               | <b>Pre-Conditions</b> |

Abbreviations:

O&M : Maintenance and operation

BPS : Booster pumping station

HCWW : Holding Company for Water and Wastewater

SHAPWASCO : Sharkia Potable Water and Sanitation Company

FMRP : Fe/Mn removal plant

MF : Model facilities

WTP : Water treatment plant

HQ : Headquarters

NOPWASD : National Organization for Potable Water and Sanitary Drainage

OJT : On-the-job training

SOP : Standard Operational Procedure