

A1.5 Traffic Control Assistance

1) Service Requirements and Use Cases

(1) 1st Stage

- (i) Notification to the road operation vehicles immediately after receiving the information of incident,
- (ii) Arrival of the road operation vehicles at the site by 1 hour at the latest from the incident occurrence,
- (iii) Decision/implementation of traffic restriction immediately after arrival of the road operation vehicles,
- (iv) Incident/restriction information dissemination to the drivers en-route on adjacent section immediately after the decision of restriction, and prevention of the secondary incidents,
- (v) Prompt incident/restriction information dissemination to the drivers en-route for reducing vehicles to the concerned section,
- (vi) Traffic congestion information dissemination to the drivers en-route on adjacent section immediately after grasping the congestion for prevention of the collision from behind,
- (vii) Decision/implementation of the restriction of incoming traffic at the interchange as needed,
- (viii) Prompt restriction information dissemination to the drivers en-route,
- (ix) Information update every 15 minutes for dissemination.

(2) 2nd Stage


- (i) Travel-time/weather information dissemination to the drivers en-route.

(3) 3rd Stage

- (i) Congestion forecast information dissemination to the drivers en-route.

The following five alternative use cases are to be considered in the discussion.

Figure A1.5.1 Use Case Diagram of Traffic Control Assistance



Source: VITRANSS 2 Study Team

2) Message Sequence Diagram

The message sequence diagram (MSD) of the use cases above are shown in the following pages.

Figure A1.5-(a).MSD Traffic Control Assistance by Monitoring at Roadside




Figure A1.5-(b).MSD Traffic Control Assistance by Image Recognition




Figure A1.5-(c).MSD Traffic Control Assistance by Vehicle Detection




Figure A1.5-(d).MSD Traffic Control Assistance by DSRC Probe






Figure A1.5-(e).MSD Traffic Control Assistance by GPS/WL Probe



3) Collaboration Diagram with Functions/Installation

The collaboration diagrams (CD) are derived respectively from the message sequence diagrams aforementioned.


Figure A1.5-(a).CD Traffic Control Assistance by Monitoring at Roadside (Graded as “Useful as a Complement”)



Functions & Installation: 5-(a) by Monitoring on Roadside		
Function	Equipment	Installation
CCTV monitoring	Console	Traffic information/control center **
	Computer	Traffic information/control center **
Event data management	Console	Traffic information/control center **
	Computer	Traffic information/control center **
VMS indication (→ See Table 9.3.2)	Console	Traffic information/control center **
	Computer	Traffic information/control center **
	VMS	Roadside (1 st ~ : short of exit diverging point, entrance point, tollgate, relevant spot)
	SGM	Roadside (3 rd : short of junction)

Note, **: Three main centers shall be constructed in the 1st stage (→ See Section 8.4). Management offices shall be implemented every 50–80 km in the 1st–2nd stages keeping pace with the road construction (→ See Figure 8.3.2).


Figure A1.5-(b).CD Traffic Control Assistance by Image Recognition (Graded as “Necessary”)



Functions & Installation: 5-(b) by Image Recognition		
Function	Equipment	Installation
CCTV monitoring	Console	Traffic information/control center **
	Computer	Traffic information/control center **
Image recognition	Computer	Traffic information/control center **
Event data management	Console	Traffic information/control center **
	Computer	Traffic information/control center **
VMS indication (→ See Table 9.3.2)	Console	Traffic information/control center **
	Computer	Traffic information/control center **
	VMS	Roadside (1 st ~ : short of exit diverging point, entrance point, tollgate, relevant spot))
	SGM	Roadside (3 rd : short of junction)

Note, **: Three main centers shall be constructed in the 1st stage (→ See Section 8.4). Management offices shall be implemented every 50–80 km in the 1st–2nd stages keeping pace with the road construction (→ See Figure 8.3.2).


Figure A1.5-(c).CD Traffic Control Assistance by Vehicle Detection (Graded as “Necessary”)



Functions & Installation: 5-(c) by Vehicle Detection		
Function	Equipment	Installation
Event data management	Console	Traffic information/control center **
	Computer	Traffic information/control center **
VMS indication (→ See Table 9.3.2)	Console	Traffic information/control center **
	Computer	Traffic information/control center **
	VMS	Roadside (1 st ~ : short of exit diverging point, entrance point, tollgate, relevant spot)
	SGM	Roadside (3 rd : short of junction)

Note, **: Three main centers shall be constructed in the 1st stage (→ See Section 8.4). Management offices shall be implemented every 50–80 km in the 1st–2nd stages keeping pace with the road construction (→ See Figure 8.3.2).


Figure A1.5-(d).CD Traffic Control Assistance by DSRC Probe (Graded as “Necessary”)



Functions & Installation: 5-(d) by DSRC Probe		
Function	Equipment	Installation
DSRC probe	Computer	Probe information management center (2 nd ~)
	Computer	Toll Management Center (1 st ~)
Event data management	Console	Traffic information/control center **
	Computer	Traffic information/control center **
VMS indication (→ See Table 9.3.2)	Console	Traffic information/control center **
	Computer	Traffic information/control center **
	VMS	Roadside (1 st ~ : short of exit diverging point, entrance point, tollgate, relevant spot)
	SGM	Roadside (3 rd : short of junction)

Note, **: Three main centers shall be constructed in the 1st stage (→ See Section 8.4). Management offices shall be implemented every 50–80 km in the 1st–2nd stages keeping pace with the road construction (→ See Figure 8.3.2).

Figure A1.5-(e).CD Traffic Control Assistance by GPS/WL Probe (Graded as “Useful as a Complement”)



Functions & Installation: 5-(e) by GPS/WL Probe		
Function	Equipment	Installation
GPS probe	Computer	Probe information management center (2 nd ~)
	Sensor	In-vehicle (2 nd ~)
Event data management	Console	Traffic information/control center **
	Computer	Traffic information/control center **
VMS indication (→ See Table 9.3.2)	Console	Traffic information/control center **
	Computer	Traffic information/control center **
	VMS	Roadside (1 st ~ : short of exit diverging point, entrance point, tollgate, relevant spot)
	SGM	Roadside (3 rd : short of junction)

Note, **: Three main centers shall be constructed in the 1st stage (→ See Section 8.4). Management offices shall be implemented every 50–80 km in the 1st–2nd stages keeping pace with the road construction (→ See Figure 8.3.2).