

Appendix K-3

Presentation on Third Stake Holder Meeting



The Republic of Uganda
Project for Master Plan Study on
Hydropower Development

Presentation to Stake Holders
at
IMPERIAL ROYAL HOTEL

Presented by: Jimmy Collins Omona & Moses Otim
Hydro Power Development Unit (UEGCL)



SESSION-1

HYDROPOWER MASTER PLAN

Presentation on Third Stake Holder Meeting

2

Contents

1. Demand Forecast
2. System Analysis
3. Alternative Energy Sources
4. Selection of Prospective Site
5. Power Development Plan

Presentation on Third Stake Holder Meeting

3


1. Demand Forecast 1.1 Actual Record of Gross Domestic Product and Domestic Energy Sales

Year	Gross Domestic Product (GDP)		Domestic Energy Sales		Elasticity (Energy/GDP)
	Current currency (billion US\$)	Growth Rate (%)	(GWh)	Growth Rate (%)	
2002	10,709	8.73	1,356		
2003	11,403	6.47	1,433	5.65	0.88
2004	12,179	6.81	1,614	12.65	1.86
2005	12,950	6.33	1,767	9.47	1.50
2006	14,347	10.78	1,554	-12.05	-1.12
2007	15,254	6.41	1,819	17.03	2.02
2008	16,908	8.71	1,993	9.53	1.09
2009	18,103	7.06	2,276	14.32	2.03
Average 2002-2009		7.79		7.69	0.99

Presentation on Third Stake Holder Meeting

4

1.2 Actual Record of Gross Domestic Product and Domestic Energy Sales



Presentation on Third Stake Holder Meeting

5

1.3 Comparison of Growth Rate

(Domestic Energy Demand Forecast in GDP2009 and Gross Domestic Product)


Year	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2009-23
A: Growth Rate of Domestic Energy Demand in GDP 2009 (%)	5.86	6.04	6.39	5.93	7.64	7.52	7.63	9.94	10.2	8.37	8.53	8.30	8.43	8.93	9.16	8.06
B: Growth Rate of Gross Domestic Product by DMF (%)	7.06	5.59	6.40	7.00	7.20	7.40	7.50	7.50	7.50	7.50	7.50	7.50	7.50	7.50	7.50	7.22
Elasticity (A/B)	0.73	0.81	0.83	0.77	1.03	1.02	1.03	1.34	1.37	1.13	1.15	1.12	1.14	1.21	1.24	1.12

Presentation on Third Stake Holder Meeting

6

1.4 Comparison of Growth Rate

(Domestic Energy Demand Forecast in GDP2009 and Gross Domestic Product)



Presentation on Third Stake Holder Meeting

7


1.5 Result of Domestic Energy Demand Forecast (GWh)

Year	2009	2010	2011	2012	2013	2014	2015	2016	
GDP2009	Medium	2,171	2,302	2,449	2,595	2,793	3,000	3,232	3,554
	Medium	2,371	2,346	2,535	2,740	2,961	3,199	3,457	3,736
	High	2,171	2,368	2,582	2,816	3,072	3,350	3,654	3,985
	Low	2,171	2,324	2,489	2,664	2,852	3,054	3,270	3,500
GDP2009	Medium	3,815	4,242	4,804	4,986	5,406	5,889	6,428	
	Medium	4,037	4,363	4,714	5,094	5,505	5,949	6,428	
	High	4,346	4,740	5,169	5,637	6,140	6,706	7,313	
	Low	3,748	4,012	4,296	4,599	4,924	5,272	5,644	

Presentation on Third Stake Holder Meeting

8

1.6 Result of Domestic Energy Demand Forecast (GWh)




1.7 Result of Domestic Power Demand Forecast (MW)

Year	2009	2010	2011	2012	2013	2014	2015	2016
GDP2009	375	398	424	449	483	519	559	615
JICA	Medium	375	406	439	474	512	553	598
	High	375	410	447	487	531	579	632
	Low	375	402	436	461	493	528	566
Year	2017	2018	2019	2020	2021	2022	2023	
GDP2009	677	769	834	903	980	1,034	1,129	
JICA	Medium	698	755	815	881	952	1,029	1,112
	High	732	820	894	975	1,063	1,160	1,263
	Low	648	694	743	795	852	912	976

Presentation on Third Stake Holder Meeting 10

1.8 Result of Domestic Power Demand Forecast (MW)




1.9 Result of Power Demand Forecast incl. Export (MW)

Year	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
Domestic (JICA)	375	406	439	474	512	553	598	646	698	755	815	881	952	1029	1112
Domestic (GDP2009)	375	398	424	449	483	519	559	615	677	769	834	903	980	1034	1129
Export (Kenya)	1	1	10	10	10	20	20	20	30	50	100	100	100	100	100
Export (Tanzania)	10	10	13	12	13	20	20	20	20	20	20	20	20	20	20
Export (Rwanda)	1	1	1	1	1	10	10	20	20	20	20	20	20	20	20
Export (Congo)					1	2	3	20	20	30	30	30	30	30	30
Export (Sudan)										0	20	30	30	30	30
Total (JICA)	387	418	462	499	539	623	698	796	796	870	1035	1131	1222	1329	1432
Total (GDP2009)	387	410	447	474	510	589	676	765	771	889	1074	1153	1250	1354	1449

Presentation on Third Stake Holder Meeting 12

1.10 Result of Power Demand Forecast incl. Export (MW)



2. System

2.1 Condition

- Network to be Simulated
- Based on GDP2009
 - 220kV Kawanda—Mutundwe is added to solve overload problem in Kampala Area

2.2 Network Analysis



2.3 Power Flow Analysis Result in 2023

- Network to be Simulated
- Based on GDP2009
 - 220kV Kawanda—Mutundwe is added to solve overload problem in Kampala area

Maximum power flow

	Line	Max. P. Flow	Comments
400kV	Karuma-Kafu	748MW	Sufficient transmitting capacity is necessary
220kV	Kawanda-Mutundwe	267MW	Listing the line in GDP is necessary

Presentation on Third Stake Holder Meeting 16

3. Alternative Energy Source

3.1 Economic and Technical Consideration

Evaluation items	Hydro	Geothermal	Diesel Engine (Heavy Oil)	Wind Power	Biomass Thermal Cogeneration	Solar Thermal	Nuclear	Energy import
Development cost(USD/kW)	C	C	A	E	E	E	A	
Operation & Maintenance cost (USD/kW/yr)	A	C	C	A	C	A	A	
Use cost of power generation (USD/MWh)	A	A	E	A	C	E	A	
Existing potential (MW)	A	C	C	E	B	D	D	
Technically feasible potential at present (MW)	A	C	D	E	B	C	E	
Availability of Energy Source	B	A	D	-	D	C	E	
Survey maturity	B	C	A	-	A	A	E	
Lead time for construction(years)	C	D	A	-	B	B	E	
Initial Starting Time	A	C	B	-	C	C	D	
Energy stability	B	A	A	-	C	E	A	
Power supply stability	B	A	C	-	D	E	D	
Life span (Year)	A	B	C	B	B	B	A	
Contribution to national economy*	A	A	E	C	A	C	A	

Presentation on Third Stake Holder Meeting

17

3.2 Environmental Consideration

Evaluation items	Hydro	Geothermal	Diesel Engine (Heavy Oil)	Wind Power	Biomass Thermal Cogeneration	Solar Thermal	Nuclear	Energy import
Air pollution	A	A	E	B	D	B	A	
Water pollution	C	D	C	A	C	B	D	
Consumption of natural resource*	A	B	E	A	C	A	C	
CO2 emission	A	B	E	C	C	D	A	
Waste	B	C	C	A	D	A	E	
Water right/ water resource*	D	B	C	A	B	B	C	
Impact on natural ecology**	E	C	D	B	C	A	C	

Presentation on Third Stake Holder Meeting

18


3.3 Social Consideration

Evaluation items	Hydro	Geothermal	Diesel Engine (Heavy Oil)	Wind Power	Biomass Thermal Cogeneration	Solar Thermal	Nuclear	Energy import
Impact on Agriculture	D	A	A	C	E	B	A	
Resettlement	D	A	A	C	E	A	B	
Impact on fishery	E	C	D	A	D	A	D	
Impact on tourism	E	B	A	D	A	C	C	
Legal aspects	A	C	A	A	A	E	A	
Human health hazard+	D	D	D	B	D	A	D	
Risk of accident	D	B	E	A	B	A	D	

Presentation on Third Stake Holder Meeting

19

3.4 Summary (Multi Criteria Decision)



Presentation on Third Stake Holder Meeting

20

4. Selection of Prospective Site


4.1 Plan



Presentation on Third Stake Holder Meeting

21


4.2 Profile of Nile River



Presentation on Third Stake Holder Meeting

22

4.3 Feature of Nile River - Abundant Water resources and Stable Flow -



Presentation on Third Stake Holder Meeting

23

5. Power Development Plan

5.1 Scenarios of Development Plan


	Demand Forecast	Data Source
Scenario I	Middle Case	Study Team
Scenario II	High Case	Study Team
Scenario III	Low Case	Study Team
Scenario IV	Middle + Export to Kenya	Study Team
Scenario V	Vision 2035	PSIP Draft Report Dec.8.2009

(Source: Study Team)

Presentation on Third Stake Holder Meeting


24

5.2 Scenario I : Energy demand and Supply Balance




Presentation on Third Stakeholder Meeting

5.3 Scenario II : Power demand and Supply Balance




Presentation on Third Stakeholder Meeting

5.4 Scenario II : Energy demand and Supply Balance




Presentation on Third Stakeholder Meeting

5.5 Scenario III : Power demand and Supply Balance




Presentation on Third Stakeholder Meeting

5.6 Scenario IV : Energy demand and Supply Balance




Presentation on Third Stakeholder Meeting

5.7 Scenario V : Power demand and Supply Balance



Presentation on Third Stakeholder Meeting

5.8 Scenario V : Energy demand and Supply Balance



Presentation on Third Stakeholder Meeting

• END OF PRESENTATION

Presentation on Third Stakeholder Meeting

SESSION-2

PRE-FEASIBILITY STUDIES FOR THE AYAGO PROJECT

Presentation on Third Stake Holder Meeting

33

Contents

1. Hydrology
2. Topography and Geology
3. Optimum Scale of Ayago project
4. Design
5. Construction Planning
6. Cost Estimates
7. Economic and Financial Evaluation
8. Project Execution Plan

Presentation on Third Stake Holder Meeting

34

1. Hydrology

1.1 Introduction

- 1) The Nile River Network
- 2) Historical Record of Water Level of L. Victoria
- 3) Water Balance of Lake Victoria and Lake Kyoga
- 4) Flow Duration of Lake Victoria and Lake Kyoga
- 5) Flood Analysis

Presentation on Third Stake Holder Meeting

35

1.2 The Nile River Network



1. The Nile River is originated from Lake Victoria. It flows through Lake Kyoga and Lake Albert, and down to Sudan.
2. The runoff from the Lake Victoria is solely regulated at Owen Falls Dam.


Basic Features of Lake Victoria, Lake Kyoga and Lake Albert

Lakes	Total Area (km ²)	Area in Uganda (km ²)	Mean Elevation (m)	Max. Depth (m)
Victoria	68,457	28,663	1,134	82
Albert	5,335	2,913	621	31
Kyoga and Kwana	2,047	2,047	1,033	7

Presentation on Third Stake Holder Meeting

36

1.3 Historical Record of Water Level at Lake Victoria




Water Level of Lake Victoria (yr 1896 - yr 2009)

1. The water level of Lake Victoria varied from EL1134.5m to 1133.41m between year 1896 to year 1960.
2. The water level suddenly rose by 2 meters due to heavy rains in 1961-1964. Since 1964, the lake level gradually continued to fall until 2006 when it reached its lowest level and the benefit of high lake level seemed to have been exhausted.
4. The agreement between Uganda and the downstream riparian countries of Sudan and Egypt prescribes the rule curve for releases from the Owen Falls Dam. The rule curve requires the releases to keep the natural flow regime of the river and O.F.P.S generally complies the rule.

Presentation on Third Stake Holder Meeting

37

1.4 Flow Duration of Lake Victoria and Lake Kyoga



Flow Duration Curve of Lake Victoria and Lake Kyoga

- Runoff from Lake Victoria flows into Lake Kyoga which is 120 km downstream from Lake Victoria.
- In the draught season, the evaporation exceeds total inflow in the Lake Kyoga. Therefore the flow is lower than the Victoria runoff in the draught season.
- In general, the flow duration of Lake Kyoga and Lake Victoria is similar.
- Discharges at 95% exceedance probability are 499 m³/s for the Lake Victoria and 414 m³/s for the Lake Kyoga.

Presentation on Third Stake Holder Meeting

38

1.5 Flood Analysis



1. Flood analysis is carried out at intake and outlet location for the planned Ayago site.
2. Return period of 100 years, 200 years, and 1000 years are examined.
3. Flood discharge is derived by combination of the Nile and tributary flood.

Probable Flood Discharge

Return Period	100 year	200 year	1,000 year
Ayago Intake	3,800 m ³ /s	3,700 m ³ /s	4,300 m ³ /s
Ayago Outlet	3,000 m ³ /s	3,000 m ³ /s	4,000 m ³ /s


1. Tributary Flood
Flood duration = Several days
 2. Nile River Flood
Flood duration = Several months to years
- Concept of Combination of Floods

Presentation on Third Stake Holder Meeting

39

2. Topography and Geology

2.1 General




Base map: 1:1,500,000 Geological Map, Department of Geological Survey and Mines, Uganda, 1966

Presentation on Third Stake Holder Meeting

40

2.2 Topographic Survey




Survey Items and Quantity

- Topographic maps covering the whole project area, scale 1:10,000 (5m contour interval)
- Topographic maps for main structures such as inlet weir, power station and outlet, scale 1:1,000 (1 m contour interval)
- Cross-section survey

Presentation on Third Stakeholder Meeting

41

2.3 Geological Investigation




Survey Items and Quantities

- Ground Mapping: 36 km²
- Aerial Photograph Interpretation: 100 km²
- Core Drilling: 8 holes, total 350m in length
- Permeability tests: 46 nos.
- Laboratory tests and Construction Material Survey

Presentation on Third Stakeholder Meeting

42

2.4 Core Boring and Laboratory Test Results



Presentation on Third Stakeholder Meeting

43

2.5 Results of Geological Investigation


- Ayago site is underlain mainly by hard gneiss rocks, which will be suitable in terms of strength and water tightness.
- No serious problems were found in rock foundations of the structures such as intake weir, underground powerhouse and tunnels.
- A NE-SW lineament near the outlet site indicates a weak zone. Rock condition seems to be more preferable by shifting the layout of the outlet slightly to the upstream.
- Development of quarry site is essential for construction material. Use of rock materials obtained by tunnel excavation will be preferable from the viewpoint of nature conservation.
- Additional geological investigations including core drilling with testing are necessary during the F/S to confirm the distribution of sound rock and availability of construction material source.

Presentation on Third Stakeholder Meeting

44

3. Optimum Scale of Ayago Project


3.1 Power Discharge and Energy Production



Presentation on Third Stakeholder Meeting

45

3.2 Selection of Optimum Size



Presentation on Third Stakeholder Meeting

46

4. Design

4.1 Layout Options




Presentation on Third Stakeholder Meeting

47

4.2 General Evaluation of Optimal Layout

- Current evaluation shows that Left Bank Route has relatively higher score than the other layouts for Even Case, Environment Weighting Case, and Economic & Technical Weighting Case.




Presentation on Third Stakeholder Meeting

48

4.3 General Layout of Intake and Powerhouse

- The intake and powerhouse structures were divided into two ridges due to limitation of the ridge area.
- Two powerhouses are connected by one access tunnel and one cable connection tunnel. Two powerhouses
- The high voltage cable will be led out from the GIS room to the transmission line via cable shaft. The transmission line will be connected to the steel tower located on the ground surface.




Layout Plan from Intake to Powerhouse

Presentation on Third Stakeholder Meeting

49

4.4 Powerhouse Layout

- A 50 MW generating unit capacity was adopted so as to avoid damage of the power grid system in Uganda.
- There are six numbers of turbines and generators, which unit capacity is 50 MW, in each powerhouse cavern.
- Two erection bays were planned to be located at both sides of the powerhouse machine bay, so as to shorten the installation period.
- Transformer and GIS caverns were proposed to be located at the immediate vicinity of the powerhouse cavern.




No.1 Powerhouse Layout (Unit Capacity : 50MW)

Presentation on Third Stakeholder Meeting

50

4.5 Case Study for Unit Capacity

- In case the grid system will be developed to more than expected, 100 MW unit capacity can be adopted for the Project.
- A reduction of 15% in the volume of excavation for the cavern and a 50% decrease in the quantity of the generating units can be achieved by adopting a 100 MW unit capacity



Alternative Layout of No.2 Powerhouse (Unit Capacity : 100MW)

Presentation on Third Stakeholder Meeting

51

4.6 Electrical Equipment

Appropriate Unit Capacity


Condition

- Peak load 900MW
- Off-peak load 440MW
- Constant characteristics 5%
- Minimum frequency 48.5Hz
- No connection to Kenya

Presentation on Third Stakeholder Meeting

52

4.7 Transmission Line Route



Presentation on Third Stakeholder Meeting

53

5. Construction Planning

5.1 Access Road




- Project site: South of Nile River
- Length: approx. 75km(south), 40km(north), 20km(site)
- Use of existing path to minimize environmental impact

Presentation on Third Stakeholder Meeting

54

5.2 Spoil Bank



No.	Estimated Area (m ²)	Estimated Volume (m ³)
(A)	318,000	5,088,000
(B)	52,000	258,000
(C)	61,000	536,000
Total	431,000	5,902,000

- (A) Exit of tailrace work adit
- (B) Exit of powerhouse access tunnel
- (C) Downstream of weir

- Volume: over 5mil m³ except concrete aggregate
- Consider accessibility and less environmental impact
- Detailed survey and environmental evaluation are required

Presentation on Third Stakeholder Meeting

55

5.3 Temporary Facility Area



No.	Expected Area (m ²)	Purpose for
(A)	2,000	Weir Intake
(B)	3,500	Headrace Penstock
(C)	3,300	Powerhouse Tailrace
(D)	3,200	Tailrace
(E)	3,200	Tailrace Outlet
(F)	11,000	Concrete Facility
(G)	45,000	Building Camp

- Temporary facilities will be demolished later
- Building and camp will be remained for operation

Presentation on Third Stakeholder Meeting

56

5.4 Weir and Intake




Weir
Excavation: 11,000m³
Concrete: 83,000m³

- Weir location is determined in consideration of river diversion
- Easy to divert river flow utilizing 2 small islands in the river
- Closure work is conducted in 3 stages

Presentation on Third Stakeholder Meeting

57

5.5 Underground Powerhouse





- Arch excavation
- Cavern excavation
- Foundation concrete
- Installation of Draft tube
- Reinforcing bar and Concrete Casting
- Installation of the electrical equipment

Excavation: 15 month
Concrete & Electromechanical : 27 month
Others : 10 month

Presentation on Third Stakeholder Meeting

58

5.6 Tailrace Tunnel



- 6 lines with 8.4m dia. 7500m long
- Blasting method
- Excavation: 80m/monthx24month
- Concrete: 110m/monthx18month
- Driven simultaneously from 4 tunnel faces

Presentation on Third Stakeholder Meeting

59

6. Cost Estimates


6.1 Total Cost for 600MW

Items	Cost (x10 ⁷ US\$)	Note
1. Preparative and Land acquisition	36,030	
(1) Access road	13,500	(100x10 ⁷ US\$) x 0.135 km
(2) Compensation & Resettlement	5,000	
(3) Camp & Facilities	13,500	(1.5 x Civil works) x 7%
2. Environmental mitigation cost	43,827	(1.5 x Civil works) x 7%
3. Civil work	876,494	
(1) Weir	28,813	
(2) Intake	19,535	
(3) Headrace	31,023	
(4) Penstock	5,000	
(5) Access tunnel	13,018	
(6) Powerhouse	78,526	
(7) Draft Tunnel	25,712	
(8) Tailrace tunnel	401,883	
(9) Outlet	5,444	
(10) Miscellaneous	76,083	
4. Hydraulic equipment	38,858	
5. Electro-mechanical equipment	255,200	Installed Capacity: 610 MW
6. Transmission line	28,000	Atago-Ramona: 30 km
7. Transportation cost	1,279,434	Direct cost
8. Administration and Engineering service	191,915	Direct cost = 15%
9. Contingency	127,943	Direct cost = 10%
Total cost	3,899,293	

Presentation on Third Stakeholder Meeting

60

6.2 Disbursement Schedule



- Disburse schedule is based on the stage development
- First 100MW starts construction in 2015 and operates in 2020
- Second 100MW starts construction in 2020 and operates in 2023
- Third 100MW starts construction in 2021 and operates in 2024

Presentation on Third Stakeholder Meeting

61

7. Economic & Financial Evaluation

7.1 Power Purchase Composition



Source: UETCL Annual Report 2008

UGX390,051 million (US\$200 million) for 2,095 GWh

(for simplicity the exchange rate: US\$1=UGX2000)

Average purchase cost: US 9.3 ¢/kWh

Eskom: US 1.2 ¢/kWh

Aggreko: US 22.7 ¢/kWh

Jacobsen: US 29.4 ¢/kWh

KPLC: US 23.8 ¢/kWh

Presentation on Third Stakeholder Meeting

62

7.2. Result of Economic Evaluation (Scenario I)

Scenario I on Base Case
The construction cost of Ayago hydropower=100%
The construction cost of the alternative thermal power=100%
The fuel price=US\$50 cents/liter
Discount rate=10%

Criteria	Evaluation	Index	Judgment
EIRR	24.36%	> 10%	Passed
NPV	US\$ 1.134 million	> 0	Passed
B/C	2.58	> 1	Passed

Scenario I on Severer Case
The construction cost of Ayago hydropower=100%
The construction cost of the alternative thermal power=50%
The fuel price=US\$25 cents/liter
Discount rate=10%

Criteria	Evaluation	Index	Judgment
EIRR	10.65%	> 10%	Passed
NPV	US\$ 6million	> 0	Passed
B/C	1.07	> 1	Passed

Presentation on Third Stakeholder Meeting

63

7.3. Result of Economic Evaluation (Scenario IV)

Scenario IV on Base Case
The construction cost of Ayago hydropower=100%
The construction cost of the alternative thermal power=100%
The fuel price=US\$25 cents/liter
Export tariff=US\$11 Scents/kWh
Discount rate=10%

Criteria	Evaluation	Index	Judgment
EIRR	24.44%	> 10%	Passed
NPV	US\$ 1.136 million	> 0	Passed
B/C	2.88	> 1	Passed

Scenario IV on Severer Case
The construction cost of Ayago hydropower=100%
The construction cost of the alternative thermal power=50%
The fuel price=US\$25 cents/liter
Export tariff=US\$6cents/kWh
Discount rate=10%

Criteria	Evaluation	Index	Judgment
EIRR	10.19%	> 10%	Passed
NPV	US\$ 1million	> 0	Passed
B/C	1.02	> 1	Passed

Presentation on Third Stakeholder Meeting

64

7.4 Result of Financial Evaluation (Scenario I)

Scenario I on Base Case
The construction cost of Ayago hydropower=100%
The power price=US\$6 cents/kWh
Discount rate=10%

Criteria	Evaluation	Index	Judgment
FIRR	12.83%	> 10%	Passed
NPV	US\$ 192 million	> 0	Passed
B/C	1.33	> 1	Passed

Scenario I on Severer Case
The construction cost of Ayago hydropower=120%
The power price=US\$5.5 cents/kWh
Discount rate=10%

Criteria	Evaluation	Index	Judgment
FIRR	10.18%	> 10%	Passed
NPV	US\$ 14million	> 0	Passed
B/C	1.02	> 1	Passed

Presentation on Third Stake Holder Meeting

65

7.5 Result of Financial Evaluation (Scenario IV)

Scenario IV on Base Case
The construction cost of Ayago hydropower=100%
The power price=US\$6 cents/kWh
Export tariff=US\$11.5 cents/kWh
Discount rate=10%

Criteria	Evaluation	Index	Judgment
FIRR	18.46%	> 10%	Passed
NPV	US\$ 639 million	> 0	Passed
B/C	2.04	> 1	Passed

Scenario IV on Severer Case
The construction cost of Ayago hydropower=120%
The power price=US\$4.5 cents/kWh
Export tariff=US\$6 cents/kWh
Discount rate=10%

Criteria	Evaluation	Index	Judgment
FIRR	10.19%	> 10%	Passed
NPV	US\$ 15million	> 0	Passed
B/C	1.02	> 1	Passed

Presentation on Third Stake Holder Meeting

66

7.6 Result of Cashflow Analysis (Scenario I)

Scenario I on Base Case
The construction cost of Ayago hydropower=100%
The power price=US\$6 cents/kWh
Interest rate=7%

Criteria	Evaluation	Index	Judgment
IRR on Project	9.41%	> 7%	Passed
IRR on Equity	12.32%	> 7%	Passed
LLCR	2.95	> 1.5	Passed
DSCR Average	4.19	> 1.5	Passed
DSCR Minimum	2.68	> 1.0	Passed

Scenario I on Severer Case
The construction cost of Ayago hydropower=120%
The power price=US\$5.5 cents/kWh
Interest rate=10%

Criteria	Evaluation	Index	Judgment
IRR on Project	7.34%	> 7%	Passed
IRR on Equity	8.63%	> 7%	Passed
LLCR	1.72	> 1.5	Passed
DSCR Average	2.84	> 1.5	Passed
DSCR Minimum	1.71	> 1.0	Passed

Presentation on Third Stake Holder Meeting

67

7.7 Result of Cashflow Analysis (Scenario IV)

Scenario IV on Base Case
The construction cost of Ayago hydropower=100%
The power price=US\$6 cents/kWh
Export tariff=US\$11.5 cents/kWh
Interest rate=7%

Criteria	Evaluation	Index	Judgment
IRR on Project	13.26%	> 7%	Passed
IRR on Equity	18.64%	> 7%	Passed
LLCR	4.22	> 1.5	Passed
DSCR Average	5.95	> 1.5	Passed
DSCR Minimum	3.75	> 1.0	Passed


Scenario IV on Severer Case
The construction cost of Ayago hydropower=120%
The power price=US\$4.5 cents/kWh
Export tariff=US\$6 cents/kWh
Interest rate=10%

Criteria	Evaluation	Index	Judgment
IRR on Project	7.19%	> 7%	Passed
IRR on Equity	7.50%	> 7%	Passed
LLCR	1.64	> 1.5	Passed
DSCR Average	2.67	> 1.5	Passed
DSCR Minimum	1.61	> 1.0	Passed

Presentation on Third Stake Holder Meeting

68


8. Project Execution Plan 8.1 Scheme of Implementation (IPP/PPP with government equity participation)



Presentation on Third Stake Holder Meeting

69

8.2 Scheme of Implementation (Public works as government project)



Presentation on Third Stake Holder Meeting

70

8.3 Mode of Implementation

Viewed from the government	Advantages	Disadvantages
IPP/PPP with government equity participation	<ul style="list-style-type: none"> Possible to utilize funds and knowhow of the private sector Possible to reduce financial burden on the government Possible to reduce input of human resources of the government 	<ul style="list-style-type: none"> Complicated financial/contractual scheme Time consuming for coordination between a numerous parties concerned Uncertain about the timing of financial close Required to provide government guarantees as conditions for private sector participation (contingent liabilities) Less management transparency Less likely to accumulate project management capability
Public works as government project	<ul style="list-style-type: none"> Possible shortening of development period Possible to accumulate project management capability Enhanced management transparency 	<ul style="list-style-type: none"> Full funding responsibility on the government Necessary to secure project management staff Vulnerable to government intervention in autonomy as power utility

Presentation on Third Stake Holder Meeting

71


8.4 Type of Execution

Viewed from the government	Advantages	Disadvantages
EPC	<ul style="list-style-type: none"> Being called as fast track, possible to reduce the period of detail design and construction Responsibility for design and construction solely on EPC contractor Possible to reduce input of human resources of the government 	<ul style="list-style-type: none"> Higher markup on the contract price for risk hedge Fast track may not be kept if differing conditions from tendering conditions set at the level of F/S are encountered Necessary to have the ability to properly prepare EPC tender documents and evaluate the submitted tenders Necessary to have the ability to check the quality and the quantity of the works performed
CM at risk	<ul style="list-style-type: none"> Construction quality, cost and time guaranteed by CM consultant Possible to reduce input of human resources of the government Design responsibility on CM consultant if they make detail design 	<ul style="list-style-type: none"> Consultant's fee raised for risk hedge against guarantee of quality, cost and time Less likely to be able to accumulate experience in project management
Joint JV	<ul style="list-style-type: none"> Possible to make impartial judgment on allocation of responsibility Reasonable consultant fee Possible to accumulate project management capability Design responsibility on CM consultant if they make detail design 	<ul style="list-style-type: none"> Construction quality, cost and time not guaranteed by JV consultant

Presentation on Third Stake Holder Meeting

72

8.5 Schedule of Implementation



Presentation on Third Stakeholder Meeting

73

• END OF PRESENTATION

Presentation on Third Stakeholder Meeting

74

Discussion

Presentation on Third Stakeholder Meeting

75


Conclusions

- **Hydropower M/P**
 - Ayago Site selected as Prospective Site
 - Stage Development plan of Ayago Project
- **Pre F/S**
 - Salient Feature of Ayago Project
 - Installed Capacity: 50MW X 12 units
 - Suitable Layout for Stage Development by 100MW
 - Feasible Project in terms of Economic and financial

Presentation on Third Stakeholder Meeting

76

Thank you for your attention



SESSION-3

HYDROPOWER MASTER PLAN STUDY

Items of Session-3

1. Result of Strategic Environmental Assessment study
 - Stage 1: Dec. 2009 – Jan. 2010
 - Stage 2: Dec. 2009 – Feb. 2010
 - Stage 3: Jul. – Oct. 2010
2. Mitigation Strategy and Next Study

Presentation on Third Stakeholder Meeting

79

Three Strategic Environmental Assessments

Alternatives	Methods
1 st Stage: Hydropower, Geothermal, Diesel Engine, Solar thermal, Wind Power, Biomass Cogeneration, Nuclear, Energy Import	Literature Survey
2 nd stage: Kalagara, Isimba, Karuma, Oriang, Ayago, Kiba, and Murchison	Literature Survey
3 rd stage: Dam option, Left bank option, Right bank option	Site Survey

Presentation on Third Stakeholder Meeting

80

1. Result of Strategic Environmental Assessment study



1. Result of Strategic Environmental Assessment study

1.1 Stage 1



1.1 Stage 1 General Rating



Hydro	High impact on natural Ecology Low unit cost high availability of energy	A
Geothermal	Totally better, but survey maturity is necessary	B
Diesel Engine (Heavy Oil)	High unit cost High impact on air pollution and global warming	C
Wind Power	Low impact on environment Low potential	C
Biomass Thermal Cogeneration	Totally good Availability of energy is low	C
Solar Thermal	Low impact on Environment High development cost	B
Nuclear	Long initial starting time	C
Energy import	Uncertainty of supply High risk of accident	C

Presentation on Third Stake Holder Meeting

83

1.1 Stage 1 Conclusion



- High Score Sources are Hydro, Geothermal, and Solar.
- Geothermal has low survey maturity.
- Energy potential of solar is low.
- Hydro would be the most suitable energy source to fulfill the demand until 2023.

Presentation on Third Stake Holder Meeting

84

1. Result of Strategic Environmental Assessment study

1.2 Stage 2



1.2 Stage 2 Economic



Evaluation Items		Kalagala	Isimba	Karuma	Orang	Ayago	Kiba	Murchison
Cost**	Construction Cost (MUSD)	A	A	C	C	C	D	B
	Generation Cost (cent/kWh)	A	D	B	C	A	E	B
Effectiveness*	Maximum Power (MW)	C	E	B	C	A	D	A
	Construction time (year)	A	A	B	B	B	B	A
	Head (m)	E	E	B	C	A	D	A
	Distance to load center or existing grid(km)	B	D	A	C	D	D	E
	Length of Waterway	A	A	D	D	C	F	B
	Geological Condition	B	B	C	C	C	C	C
	Excavation Volume	B	A	D	C	C	E	B
	Construction material (availability)	A	A	B	B	B	C	A
	Accessibility	A	A	A	B	C	D	B
	Loss of transmission	A	A	A	B	A	B	B
Development progress	Lead Time	D	D	A	C	B	C	C
	Financial Negotiation and close	E	C	C	C	C	C	E

Presentation on Third Stake Holder Meeting

86

1.2 Stage 2 Environment



Evaluation items	Kalagala	Isimba	Karuma	Orang	Ayago	Murchison
Length of water recession (km)	A	A	D	D	C	B
Rate of recession (%)	A	A	D	D	D	D
Impact on Protected area	C	C	B	D	D	E
Impact on wetland	A	A	C	A	A	A
Impact on protected species	A	A	E	E	E	E
Degradation of underground water	A	A	D	D	C	A
CO2 emission from the reservoir	D	E	A	A	A	C

Presentation on Third Stake Holder Meeting

87


1.2 Stage 2 Social



Evaluation items	Kalagala	Isimba	Karuma	Orang	Ayago	Kiba	Murchison
Land acquisition	E	E	B	C	C	C	D
Flooding area*	D	E	A	A	A	A	C
Number of affected people	D	E	D	A	A	A	A
Impact on ethnic minority and indigenous people	C	C	D	B	B	B	B
Impact on fish breeding and/or fishing	A	A	B	A	A	A	A
Impact on Agriculture	C	D	D	A	A	A	A
Impact on cultural property	E	A	D	A	A	A	C
Impact on potential tourism	E	B	C	D	D	D	E
Impact on current tourism	E	A	B	B	B	B	E
Impact on existing infrastructure	C	C	D	A	A	A	B
Impact on landscape	E	A	D	C	C	C	E
Human health hazard	C	C	D	A	A	A	A

Presentation on Third Stake Holder Meeting

88



1.2 Stage 2 Cumulative Impact Assessment

Items	Impacts	Significance
Length of Recession	50.2 km	Serious
Impact Area	1,075 km ²	Middle
Impact on protected area	6.0 % of total protected area in the country	Serious
Impact on Hippopotamus	34.2 % of the total Hippopotamus population in the country	Serious
Poaching and Encroachment	Expansion of the poaching is anxious	Middle
Impact on tourism	Impact will be long and seriously.	Serious

Presentation on Third Stake Holder Meeting 90

1. Result of Strategic Environmental Assessment study



1.2 Stage 3

Presentation on Third Stake Holder Meeting 91

- ### 1.3 Stage 3 Survey Items (Site Survey Period)
- Topography (6/1-12/20)
 - Geology (6/1-10/13)
 - Flora (7/29-8/2)
 - Terrestrial Fauna (8/9-15)
 - Fish (9/21-24, 10/12-15)
 - Social (6/22-23, 7/12-17)
 - Archeology (7/12-17, 7/26-8/3)
- Presentation on Third Stake Holder Meeting 92

- ### 1.3 Stage 3 EIA process
- 19 March 2010: MEMD submitted "Project Brief of Pre-Feasibility Study of Ayago Hydro Electric Power Project" to NEMA.
 - 11 May 2010: NEMA issued Approval to proceed the Pre-Feasibility Study. (No need IEE/EIA)
- Presentation on Third Stake Holder Meeting 93

- ### 1.3 Stage 3 - Survey Results 1 Flora and Vegetation
- 244 vascular plant species were recorded.
 - IUCN redlisted (VU)
 - *Milicia excelsa*
 - *Khaya anthotheca*
 - Vegetations:
 - Riverine vegetation
 - Combretum dominated grassland,
 - Acacia dominated wooded grassland
 - Piliostigma-Acacia wooded grassland
- Presentation on Third Stake Holder Meeting 94



1.3 Stage 3 - Survey Results 2 Mammals

- 26 mammals are recorded.
- 4 IUCN red list species are recorded.
 - Hippopotamus (VU-Vulnerable)
 - Leopard (NT-Near Threatened)
 - Spotted Hyena (NT)
 - African Elephant (NT)

Presentation on Third Stakeholder Meeting

97


1.3 Stage 3 - Survey Results 1 Photos of Mammal vestige




Presentation on Third Stakeholder Meeting

98


1.3 Stage 3 - Survey Results 2 Mammals - Hippopotamus




1.3 Stage 3 - Survey Results 2 Mammals - Elephant




1.3 Stage 3 - Survey Results 2 Mammals - Giraffe



1.3 Stage 3 - Survey Results 2 Mammals - Buffalo



1.3 Stage 3 - Survey Results 2 Mammals - Waterbuck



1.3 Stage 3 - Survey Results 3 Birds

- 119 species are recorded.
- 9 conservation concern species are recorded.
 - Purple Heron LC
 - Brown Snake Eagle LC
 - Western Banded Snake Eagle LC
 - Swallow-tailed Bee-eater LC
 - Ring-necked Francolin NT
 - Rock Pratincole LC
 - Spot-flanked Barbet LC
 - White-headed Saw-wing LC
 - Sharpe's Starling LC



Presentation on Third Stakeholder Meeting

104

1.3 Stage 3 - Survey results 4 Amphibians and Reptiles

- 12 amphibian species are recorded.
 - Ametophrynus maculatus* LC
 - Ametophrynus regularis* LC
 - Ametophrynus vittatus* DD
 - Afraxalus osorioi* LC
 - Hyperolius viridiflavus* LC
 - Kassina senegalensis* LC
 - Amietia angolensis* LC
 - Phrynobatrachus acridoides* LC
 - Phrynobatrachus natalensis* LC
 - Psychadena anchietae* LC
 - Psychadena chrysogaster* LC
 - Psychadena mascareniensis* LC
- 16 reptiles species are recorded.
 - Crocodylus niloticus* LC

Presented on Third Stakeholder Meeting

1.3 Stage 3 - Survey Results 5 Butterflies

- 66 species of butterflies are confirmed at the site survey.
- None of them are listed in the IUCN red list.

Presented on Third Stakeholder Meeting

1.3 Stage 3 - Survey Results 6 Fish

- 5 kinds of fishes are confirmed.
 - Lates niloticus* LC
 - Barbus altianalis* LC
 - Mormyrus kannume* LC
 - Bagrus docmac* LC
 - Oreochromis niloticus* LC

Presented on Third Stakeholder Meeting

1.3 Stage 3 - Survey results 7 Administrative Boundaries near Survey Areas

Project for Master Plan Study on Hydropower Development in the Republic of Uganda (2010, JICA)

1.3 Stage 3 - Survey Results 8 Land Use

Project for Master Plan Study on Hydropower Development in the Republic of Uganda (2010, JICA)

1.3 Stage 3 - Survey Results 9 Population by gender, 2010

Sub-county	Male	Female	Total
Aber	33,000	35,100	68,100
Anaka	7,600	8,100	15,700
Purongo	4,100	4,200	8,300
Mutunda	35,200	36,900	72,100
Myene/Minakulu	26,700	26,900	53,600
Koch Goma	5,500	5,100	10,600

Source: Sub National Projections Report Northern, Western Region 2008-2012

Presented on Third Stakeholder Meeting

1.3 Stage 3 - Survey Results 10 Ethnic Groups

Presented on Third Stakeholder Meeting

1.3 Stage 3 - Survey Results 11 Internally Displaced Persons

Project for Master Plan Study on Hydropower Development in the Republic of Uganda (2010, JICA)

1.3 Stage 3 - Survey Results 11 Internally Displaced Persons




Typical grass thatched houses in IDP camp

A typical IDP satellite camp setting in Koch Goma Sub-county

Presentation on Third Stakeholder Meeting


113

1.3 Stage 3 - Survey Results 12 Educational Institutions




Project for Master Plan Study on Hydropower Development in the Republic of Uganda (2010, JICA) 14

1.3 Stage 3 - Survey Results 13 Health Facilities




Project for Master Plan Study on Hydropower Development in the Republic of Uganda (2010, JICA) 115

1.3 Stage 3 - Survey Results 14 Water Source



Project for Master Plan Study on Hydropower Development in the Republic of Uganda (2010, JICA) 116


1.3 Stage 3 - Survey Results 15 Tourism - Number of Tourists to MFNP



Presentation on Third Stakeholder Meeting

117

1.3 Stage 3 - Survey results 16 Tourism - Management Zones of MFNP



Project for Master Plan Study on Hydropower Development in the Republic of Uganda (2010, JICA)


1.3 Stage 3: Survey Results 17 MFNP and the Community

- UWA has promoted collaborative management with local community.
- 20% of the revenue has been shared with communities for development project.
- Based on MoU with UWA, communities are allowed to access park resources such as grass, firewood and local herbs.

Presentation on Third Stakeholder Meeting


119

1.3 Stage 3: Survey results 18 Poaching



Project for Master Plan Study on Hydropower Development in the Republic of Uganda (2010, JICA) 20

1.3 Stage 3: Survey Results 19 Historical/ Cultural site




1.3 Stage 3: Survey Results 19 Historical/ Cultural site



Presentation on Third Stakeholder Meeting

1.3 Stage 3: Survey Results 20 Archeological Site





1.3 Stage 3: Survey Results 20 Archeological Site





Presentation on Third Stakeholder Meeting

1.3 Stage 3: Alternatives 1 - Dam Option





Presentation on Third Stakeholder Meeting

1.3 Stage 3: Alternative 2 – Left Bank Option



Presentation on Third Stakeholder Meeting

1.3 Stage 3: Alternatives 3 – Right Bank Option



1.3 Stage 3: Impact Assessment 1 Economic and technical Aspects

	Dam Option	Left Bank Option	Right Bank Option
Construction Cost (100 x 10 ³ USD)	1,704,071 C	1,599,293 A	1,973,557 E
Disposal Volume (m ³)	5,102,136 A	6,140,682 C	7,579,766 E
Concrete Aggregate Volume (m ³)	170,000 E	Negligible A	Negligible A
Rock Classification Rate	E	A	C
Peak Power Generation Control	Available A	Not Available E	Not Available E
Construction Term (Month)	70 A	70 A	70 A
Construction Risk (Tunnel Length: mline)	6,100 A	7,900 B	9,900 C

1.3 Stage 3: Impact Assessment 2 Natural Aspects

	Dam Option	Left Bank option	Right Bank option
Flora and vegetation	C	A	B
Middle and large mammals	C	B	C
Birds	C	B	B
Amphibians and reptiles	C	B	B
Butterflies	C	B	B
Fishes	C	B	B

A: Smaller impact B: Middle impact C: Bigger impact

1.3 Stage 3: Impact Assessment 3 Social Aspects

	Dam Option	Left Bank option	Right Bank option
Land acquisition	B	C	B
Flooding area	C	B	B
Number of resettlement/ affected people	B	C	B
Impact on agriculture	B	A	C
Impact on historical/cultural property	C	B	A
Impact on poaching activities	B	C	B
Impact on tourism	C	B	B

1.3 Stage 3: Impact Assessment 4 General Evaluation

	Dam Option	Left Bank option	Right Bank option
Even Case	161	218	188
Environment weighting case	152	215	188
Economic Weighting Case	172	218	187

2. Mitigation Strategy and Next Study

2.1 Mitigation Strategy 1

- Facility siting
 - Enlarge underground facilities (Control room, management room)
 - Minimize aboveground facilities (Stock yard, Intake, maintenance road, Rock Disposal)
 - Minimize temporarily Facilities (Crasher plant, Butcher plant, Temporarily Roads)

2.2 Mitigation Strategy 2

- Access roads planning
 - Minimum vegetation cut
 - Route selection for minimum road kill
 - Animal crossing bridge or tunnel
 - Minimum impact on safari (transport and landscape)
 - Minimize noise, vibration, dust

Presentation on Third Stake Holder Meeting

137

2.3 Mitigation Strategy 3

- Water use planning
 - Keep environmental flow
- Barrage designing
 - Fit for Natural Landscape
 - Corridor for wildlife
- Transmission line planning
 - Minimize impact on landscape

Presentation on Third Stake Holder Meeting

138

2.4 Mitigation Strategy 4

- Support UWA's park management
 - Vegetation control (wild fire, invasion plants)
 - Patrol for illegal activities (poaching, encroachment)
 - Wildlife monitoring (survey system, training, sample management)
 - Coexistence of the development project with tourism

Presentation on Third Stake Holder Meeting

139

2.5 Scoping for EIA 1

Items	Impact	Task in EIA		
		Survey	Impact Assessment	Mitigation
Air pollution	C: Exhaust gas by trucks	-	Need	Need
Water pollution	C: Turbid water during construction	Need	Need	Need
Soil pollution	C: Small risk of contamination by oil	-	-	Need
Waste	A: Rock disposal	Need	Need	Need
Noise and vibrations	A: Noise from blasting, construction machines and trucks	Need	Need	Need
Ground subsidence	-	-	-	-
Offensive odors	C: Small risk from garbage	-	-	Need

A: Bigger impact B: Medium impact C: Smaller impact
Presentation on Third Stake Holder Meeting

140

2.6 Scoping for EIA 2

Items	Impact	Task in EIA		
		Survey	Impact Assessment	Mitigation
Bottom sediment	-	-	-	-
Biota and ecosystems	A: Habitat loss, human disturbance,	Need	Need	Need
Water usage	B: During construction and operation	Need	Need	Need
Accidents	A: Car accident, Blasting etc.	Need	Need	Need
Global warming	-	-	-	-
Involuntary resettlement	C: It might happen near transmission line	Need	Need	Need

Presentation on Third Stake Holder Meeting

141

2.7 Scoping for EIA 3

Items	Impact	Task in EIA		
		Survey	Impact Assessment	Mitigation
Land use and utilization of local resources	C: Private land or farm land might be acquired for transmission line	Need	Need	Need
Social institutions such as social infrastructure and local decision-making institutions	-	Need	Need	Need
Existing social infrastructures and services	C: Community usage of MFNP might be affected.	-	-	-
Poor, indigenous, or ethnic people	C: They might be affected by land acquisition.	Need	Need	Need
Misdistribution of benefits and damages	B: Benefits for whole Usandan and damage for the neighbors	Need	Need	Need

Presentation on Third Stake Holder Meeting

142

2.8 Scoping for EIA 4

Items	Impact	Task in EIA		
		Survey	Impact Assessment	Mitigation
Local conflicts of interest	A: Conflicts with hunting and tourism	Need	Need	Need
Limitation of accessibility to information, meetings, etc. for a specific person or group	B: Their mother language is not English and some of them are illiterate.	-	-	Need
Gender	C: Information disclosure should be considered.	-	-	Need
Children's rights	-	-	-	-

Presentation on Third Stake Holder Meeting

143

2.9 Scoping for EIA 5

Items	Impact	Task in EIA		
		Survey	Impact Assessment	Mitigation
Cultural heritage	B: Some cultural assets might be found in the project site.	Need	Need	Need
Infectious diseases such as HIV/AIDS	A: Infectious diseases might be spread by workers.	-	-	Need
Cultural and spiritual believes	B: Spirit sites might be affected.	Need	Need	Need

Presentation on Third Stake Holder Meeting

144

Reviews of Session 3



1. Result of Strategic Environmental Assessment study
 - Stage 1: Dec. 2009 – Jan. 2010
 - Stage 2: Dec. 2009 – Feb. 2010
 - Stage 3: Jul. – Oct. 2010
2. Mitigation Strategy and Next Study

Presentation on Third Stakeholder Meeting

145

End of the session 3

