

APPENDICES

| | |
|-------------|--|
| Appendix 1 | Member List of the Study Team |
| Appendix 2 | Study Schedule |
| Appendix 3 | List of Parties Concerned in the Recipient Country |
| Appendix 4 | Minutes of Discussions (November 24 th , 2010, October 27 th , 2011) |
| Appendix 5 | Technical Notes (November 11 th , 2010, March 21 st , 2011) |
| Appendix 6 | Geotechnical Survey Results |
| Appendix 7 | Seismic Design Data |
| Appendix 8 | Hydrological Study Results |
| Appendix 9 | Soundness Survey Results of Existing Juba Bridge |
| Appendix 10 | Traffic Data/Information |
| Appendix 11 | Stakeholders Meeting Records |
| Appendix 12 | Preparatory Design Drawings |

Appendix 1

Member List of the Study Team

Members of the Survey Team

| Name | Role | Position |
|----------------------|---|--|
| Mr. Hayashi Hiroyuki | Team Leader (First Field Survey) | Director, Urban and Regional Dev't Division 1, Urban and Regional Dev't Group Economic Infrastructure Dept., JICA |
| Mr. Suzuki Masahiko | Team Leader (Explanation and Conference about Preparatory Design Summary) | JICA Senior Advisor |
| Mr. Itoyama Hiroshi | Planning Management (First Field Survey) | Transportation and ICT Division 2, Transportation and ICT Group, Economic Infrastructure Dept., JICA |
| Mr. Fukuzawa Daisuke | Planning Management (Explanation and Conference about Preparatory Design Summary) | Transportation and ICT Division 2, Transportation and ICT Group, Economic Infrastructure Dept., JICA |
| Mr. Gose Shingo | Chief Engineer/ Bridge Planner | CTI Engineering International Co., Ltd. |
| Mr. Mizota Yuzo | Asst. Chief Engineer/ Bridge Designer II/ Topographic-Geotechnical Survey | CTI Engineering International Co., Ltd. |
| Dr. Jovito C.Santos | Bridge Designer I | CTI Engineering International Co., Ltd. |
| Mr. Izawa Tetsuro | Highway Planner/ Highway Designer | Eight-Japan Engineering Consultants, Inc. |
| Mr. Mori Shuichi | Hydrologist | CTI Engineering International Co., Ltd. |
| Mr. Shoji Takeo | Social-Environmental | CTI Engineering International Co., Ltd. |
| Ms. Umiguchi Mitsue | Environmental | Eight-Japan Engineering Consultants, Inc. |
| Mr. Nishi Shuichi | Construction Planner/ Cost Estimator | CTI Engineering International Co., Ltd. |
| Mr. Watanabe Ryohei | Construction Planner/ Cost Estimator | CTI Engineering International Co., Ltd. |

Appendix 2

Study Schedule

Study Schedule

(1) First Field Study (19th October, 2010 to 17th November)

| Date | | Team Leader | Cooperation Planning | Chief Engineer/Bridge Planning | Bridge Design I | Social Consideration | Environmental Consideration |
|------|--------|------------------|--|--|------------------------|--|---|
| No. | Date | Hayashi Hiroyuki | Itoyama Taishi | Gose Shingo | Jovito C. Santos | Shoji Takeo | Umiguchi Mitsue |
| 1 | 19 Tue | | Move Tokyo(QR803/Dep 10:50)→ | | | | |
| 2 | 20 Wed | | →Doha (QR522/ Dep 7:15) →Khartum (Arr 10:55), JICA courtesy visit (13:00) | | | | |
| 3 | 21 Thu | | Khartum → Juba (Arr. 11:00) | | | | Data Sorting |
| 4 | 22 Fri | | 10:00 MRC courtesy visit, 11:30 MD meeting (MTR), 16:00 USAid Interview Survey | | | | Khartum → Juba |
| 5 | 23 Sat | | 9:00 MOPI Interview Survey, 10:00 Field Survey | | | | |
| 6 | 24 Sun | | Study Team Meeting, Data Sorting | | | | |
| 7 | 25 Mon | | 10:00 MD Meeting, MTR | | | Field Study | Meeting with MTR |
| 8 | 26 Tue | | Signature of MD MTR, MRC, MoFEP | | | Field Study | Meeting with MOPI, MTR, MOE |
| 9 | 27 Wed | | Juba → Khartum (Not fixed time) | Meeting with JICA | | Field Study | Hearing to UNEP, Meeting with MOE |
| 10 | 28 Thu | | Report to JICA and EOJ, Khartum (Dep 21:00) → Doha(QR521/Dep 00:15) | Field Study | | Field Study | Field Study of MOPI, MTR, MOE, MoAF |
| 11 | 29 Fri | | → Tokyo (Arr 19:30) | Field Study | | Field Study | Meeting with MOPI, MTR, MOE |
| 12 | 30 Sat | | | Data Sorting | | | |
| 13 | 31 Sun | | | Data Sorting | | | |
| 14 | 1 Tue | | | Making Papers for Conference | | Field Study | Conference with WB |
| 15 | 2 Wed | | | Making Papers for Conference | | Meeting with MOE | Meeting with MoAF, Conference with MOE |
| 16 | 3 Thu | | | Meeting with MOPI | | Meeting with MOPI | Tree Survey with MoAF |
| 17 | 4 Fri | | | Making Technical Notes | Making Technical Notes | Meeting with UNHCR | Meeting with UNHCR |
| 18 | 5 Sat | | | Meeting with Directorate of River Transport | | Making Report | Meeting with MoAF, Conference with MOE |
| 19 | 6 Sun | | | Making Papers for Conference | | Data Sorting | Data Sorting |
| 20 | 7 Mon | | | Data Sorting | | | |
| 21 | 8 Tue | | | The First Conference between Stakeholders; Technical Notes – MTR | | | |
| 22 | 9 Wed | | | Conference of Technical Notes – MOPI; Dir. Of Land Survey | | Making Report | Hearing to Ministry of Wild Animal Protection and MOE |
| 23 | 10 Thu | | | Conference of Technical Notes (MOE) | | Making Report | Meeting with MOE about TN |
| 24 | 11 Fri | | | Signature to Technical Notes (MOPI, MOE, MTR) | | Meeting with Payam Administrator and Community Chief | Meeting with MOPI, MTR, MOE |
| 25 | 12 Sat | | | Making Report, Field Survey | | Making Report | Data Collecting of WB |
| 26 | 13 Sun | | | Making Report | | | |
| 27 | 14 Mon | | | Data Sorting | | | |
| 28 | 15 Tue | | | Making Report; Reporting for JICA (18:00) | | | |
| 29 | 16 Wed | | | Juba (11:00) → Khartum(13:00) → Khartum(Dep 21:00) → Doha (QR521/ Dep 00:15) → | | | |
| 30 | 17 Thu | | | → Tokyo (Arr 19:30) | | | → Kanku (Arr 16:30) |

JICA: Japan International Cooperation Agency

MTR: Ministry of Transport and Roads under GOSS (Government of Southern Sudan)

MOPI: Ministry of Physical Infrastructure under CES (Central Equatoria State)


(2) Second Field Study (10th December 2010 to 25th December)

| Day/Date | | | | Social Consideration |
|----------|----------|----|-----|---|
| | | | | Shoji Takeo |
| 1 | December | 10 | Fri | Move Narita(QR0803/Dep.20:50)→ |
| 2 | | 11 | Sat | →Doha (QR0532/Dep.07:10)→Nairobi (Arr.12:30) Meeting with Local Consultants, Surveying |
| 3 | | 12 | Sun | Nairobi (JO831/Dep.8:30)→Juba (Arr.10:15) |
| 4 | | 13 | Mon | Meeting with JICA |
| 5 | | 14 | Tue | Early Baseline Study in Lologo Village |
| 6 | | 15 | Wed | Meeting with MOE(Approval of TOR) |
| 7 | | 16 | Thu | Making Papers for Public Meeting |
| 8 | | 17 | Fri | Early Baseline Study in Gumba Village |
| 9 | | 18 | Sat | Public Meeting |
| 10 | | 19 | Sun | Data Sorting |
| 11 | | 20 | Mon | Making Minutes of Public Meeting |
| 12 | | 21 | Tue | Meeting with MOE, Vice president of Luluggo Village, Ministry of Agriculture and Forestry, Ministry of Urban Infrastructure (About the member of price assessment committee) |
| 13 | | 22 | Wed | Meeting with JICA, Meeting with MTR |
| 14 | | 23 | Thu | Juba (JO836/Dep.16:30) →Nairobi (Arr.18:15) |
| 15 | | 24 | Fri | Nairobi (QR533/Dep.14:15)→Doha (Arr.19:10) |
| 16 | | 25 | Sat | Doha (QR0802/Dep.01:00) →Narita (Arr.19:05) |

(3) Third Field Survey (15th February 2011 to 31st March)

| Date | | Chief Consultant/ Bridge Planning | Bridge Design I | Asst. Chief Engineer/ Bridge Design II/ Environmental Condition | Road Planning/ Road Design | Hydrological Study | Social Consideration | Environmental Consideration | Construction Planning/ Cost Estimation | Construction Planning/ Cost Estimation |
|------|--------|---|--|---|--|---|---|---|--|--|
| No. | Date | Gose Shingo | Jovito C. Santos | Mizota Yuzo | Izawa Tetsuro | Mori Shuichi | Shoji Takeo | Umiguchi Mitsue | Nishi Shuichi | Watanabe Ryohei |
| 1 | 15 Tue | | Field Survey | Tokyo(EK6251 Dep20:45)⇒ | | | Tokyo(EK6251 Dep20:45)⇒ | | Tokyo(EK6251 Dep20:45)⇒ | |
| 2 | 16 Wed | | Field Survey | ⇒Nairobi(EK719 Arr14:55) | | | ⇒Nairobi(EK719 Arr14:55) | | ⇒Nairobi(EK719 Arr14:55) | |
| 3 | 17 Thu | | Visiting JICA Juba Office | Nairobi⇒Juba, MTR, Visiting JICA Juba office | | | Nairobi⇒Juba, MTR, Visiting JICA Juba Office | | Nairobi⇒Juba, MTR, Visiting JICA Juba Office | |
| 4 | 18 Fri | Tokyo(EK6251 Dep20:45)⇒ | Consideration of Bridge type(Superstructure) | Considering of Measurement and Soil Survey | | | Directions for Local Consultants | | Surveying Supply Situation | |
| 5 | 19 Sat | ⇒Nairobi(EK719 Arr14:55) | Consideration of Bridge type(Superstructure) | Considering of Measurement and Soil Survey | | | Directions for Local Consultants | | Surveying Supply Situation | |
| 6 | 20 Sun | Nairobi⇒Juba, MTR, JICA Juba Office | Data Sorting | Data Sorting | Tokyo⇒ | Tokyo⇒ | Data Sorting | | Data Sorting | |
| 7 | 21 Mon | Considering Project effect and evaluation | Consideration of Bridge type(Superstructure) | Considering of Measurement and Soil Survey | ⇒Nairobi | ⇒Nairobi | Checking Compensation Rate and Resettlement Site | | Surveying Supply Situation | |
| 8 | 22 Tue | Considering Project effect and evaluation | Consideration of Bridge type(Superstructure) | Considering of Measurement and Soil Survey | Nairobi⇒Juba, Safety briefing | Nairobi⇒Juba, Safety briefing | Checking Compensation Rate and Resettlement Site | | Surveying Supply Situation, Safety Briefing | |
| 9 | 23 Wed | Considering Project effect and evaluation | Consideration of Bridge type(Superstructure) | Considering of Traffic Survey | Considering of the Optimal Road Line | Hydrological Study | Checking Compensation Rate and Resettlement Site | | Surveying Supply Situation | |
| 10 | 24 Thu | Meeting with Concerned Organizations | Consideration of Bridge type(Superstructure) | Conference of Stakeholders | Considering of the Optimal Road Line | Hydrological Study | Conference of Stakeholders | | Surveying Supply Situation | |
| 11 | 25 Fri | Meeting with Concerned Organizations | Consideration of Bridge type(Superstructure) | Considering of Measurement and Soil Survey | Considering of the Optimal Road Line | Hydrological Study | Conference of Stakeholders | | Surveying Supply Situation | |
| 12 | 26 Sat | Meeting with Concerned Organizations | Consideration of Bridge type(Superstructure) | Considering of Measurement and Soil Survey | Considering of the Optimal Road Line | Hydrological Study | Supervising Local Consultants | | Surveying Supply Situation | |
| 13 | 27 Sun | Conference of Stakeholders | Conference of Stakeholders | Conference of Stakeholders | Data Sorting | Data Sorting | Conference of Stakeholders | | Juba → Nairobi | |
| 14 | 28 Mon | Considering of the Optimal Road Type | Consideration of Bridge type(Superstructure) | Consideration of Bridge type(Understructure) | Considering of the Optimal Road Line | Hydrological Analysis | Checking Compensation Rate and Resettlement Site | | Surveying Supply Situation | |
| 15 | 1 Tue | Considering of the Optimal Road Type | Consideration of Bridge type(Superstructure) | Consideration of Bridge type(Understructure) | Considering of the Optimal Road Line | Hydrological Analysis | Checking Compensation Rate and Resettlement Site | Nairobi⇒Juba | Surveying Supply Situation | |
| 16 | 2 Wed | Considering of the Optimal Road Type | Consideration of Bridge type(Superstructure) | Consideration of Bridge type(Understructure) | Considering of the Optimal Road Line | Hydrological Analysis | Site Visiting | Site Visiting | Surveying Supply Situation | |
| 17 | 3 Thu | Considering of the Optimal Road Type | Consideration of Bridge type(Superstructure) | Consideration of Bridge type(Understructure) | Considering of the Optimal Road Line | Hydrological Analysis | Site Visiting | Site Visiting | Surveying Supply Situation | |
| 18 | 4 Fri | Considering of the Optimal Road Type | Consideration of Bridge type(Superstructure) | Consideration of Bridge type(Understructure) | Considering of the Optimal Road Line | Hydrological Analysis | Site Visiting | Site Visiting | Nairobi → Juba | |
| 19 | 5 Sat | Site Visiting | Site Visiting | Site Visiting | Site Visiting | Site Visiting | Site Visiting | Site Visiting | Site visiting | |
| 20 | 6 Sun | Data Sorting | Data Sorting | Data Sorting | Data Sorting | Data Sorting | Data Sorting | Data Sorting | Data Sorting | |
| 21 | 7 Mon | Generalizing the Condition of Road Design | Considering the Condition of Road Design | Considering the Condition of Road Design | Considering the Condition of Road Design | Studying the Hydrological Condition for Bridge Design | Checking of Census and Draft of Compensation Rate | Studying of Plants and Animals (for Compensation) | Considering the Condition of Cost Estimation | |
| 22 | 8 Tue | Generalizing the Condition of Road Design | Considering the Condition of Road Design | Considering the Condition of Road Design | Considering the Condition of Road Design | Studying the Hydrological Condition for Bridge Design | Checking of Census and Draft of Compensation Rate | Studying of Plants and Animals (for Compensation) | Considering the Condition of Cost Estimation | |
| 23 | 9 Wed | Generalizing the Condition of Road Design | Considering the Condition of Road Design | Considering the Condition of Road Design | Considering the Condition of Road Design | Studying the Hydrological Condition for Bridge Design | Checking of Census and Draft of Compensation Rate | Studying of Plants and Animals (for Compensation) | Considering the Condition of Cost Estimation | |
| 24 | 10 Thu | Considering of Bridge Planning | Bridge Design (Superstructure) | Bridge Design (Understructure) | Road Designing | Studying the Hydrological Condition for Bridge Design | Checking of Census and Draft of Compensation Rate | Studying of Plants and Animals (for Compensation) | Considering the Estimation and Construction Planning | |
| 25 | 11 Fri | Considering of Bridge Planning | Bridge Design (Superstructure) | Bridge Design (Understructure) | Road Designing | Studying the Hydrological Condition for Bridge Design | Checking the Intention of Residents | Studying of Plants and Animals (for Compensation) | Considering the Estimation and Construction Planning | |
| 26 | 12 Sat | Considering of Bridge Planning | Bridge Design (Superstructure) | Bridge Design (Understructure) | Road Designing | Studying the Hydrological Condition for Bridge Design | Checking the Intention of Residents | Studying of Plants and Animals (for Compensation) | Considering the Estimation and Construction Planning | |
| 27 | 13 Sun | Data Sorting | Data Sorting | Data Sorting | Data Sorting | Data Sorting | Data Sorting | Data Sorting | Data Sorting | |
| 28 | 14 Mon | Considering the draft of G/P and Maintenance Planning | Bridge Design (Superstructure) | Bridge Design (Understructure) | Road Designing | Considering the Result of Hydrological Study | Checking the draft of EIA/RAP | Checking the draft of EIA/RAP | Considering the Estimation and Construction Planning | |
| 29 | 15 Tue | Considering the draft of G/P and Maintenance Planning | Bridge Design (Superstructure) | Bridge Design (Understructure) | Road Designing | Considering the Result of Hydrological Study | Checking the draft of EIA/RAP | Checking the draft of EIA/RAP | Considering the Estimation and Construction Planning | |
| 30 | 16 Wed | Considering the draft of G/P and Maintenance Planning | Bridge Design (Superstructure) | Bridge Design (Understructure) | Road Designing | Considering the Result of Hydrological Study | Checking the draft of EIA/RAP | Checking the draft of EIA/RAP | Considering the Estimation and Construction Planning | Nairobi⇒Juba |
| 31 | 17 Thu | Conference of Stakeholders | Conference of Stakeholders | Conference of Stakeholders | Road Designing | Considering the Result of Hydrological Study | Conference of Stakeholders | Conference of Stakeholders | Considering the Estimation and Construction Planning | Considering the Estimation and Construction Planning |
| 32 | 18 Fri | Making the Report | Bridge Design (Superstructure) | Bridge Design (Understructure) | Road Designing | Considering the Result of Hydrological Study | Checking and Revising the draft of EIA/RAP | Checking and Revising the draft of EIA/RAP | Nairobi⇒Juba | Considering the Estimation and Construction Planning |
| 33 | 19 Sat | Technical Notes Conference | Technical Notes Conference | Technical Notes Conference | Road Designing | Considering the Result of Hydrological Study | Supervising Local Consultants | Checking and Revising the draft of EIA/RAP | | Considering the Estimation and Construction Planning |
| 34 | 20 Sun | Data Sorting | Data Sorting | Data Sorting | Data Sorting | Data Sorting | Data Sorting | Data Sorting | | Data Sorting |
| 35 | 21 Mon | Technical Notes Signing (MOPI, MOE, MTR) | | | | Generalizing the Environmental Condition Study | Checking and Revising the draft of EIA/RAP | Checking and Revising the draft of EIA/RAP | | Collecting the Information for Detail Estimation |
| 36 | 22 Tue | Juba(11:00)→Khartum(13:00) | Making Report | Juba(11:00)→Khartum(13:00) | Making Report | Generalizing the Environmental Condition Study | Checking and Revising the draft of EIA/RAP | Checking and Revising the draft of EIA/RAP | | Collecting the Information for Detail Estimation |
| 37 | 23 Wed | Reporting for JICA, EnJ, Khartum→Juba | Making Report | Reporting for JICA, EnJ, Khartum→Juba | Making Report | Generalizing the Environmental Condition Study | Checking and Revising the draft of EIA/RAP | Checking and Revising the draft of EIA/RAP | | Collecting the Information for Detail Estimation |
| 38 | 24 Thu | Conference of Stakeholders | Conference of Stakeholders | Conference of Stakeholders | Making Report | Generalizing the Environmental Condition Study | Conference of Stakeholders | Conference of Stakeholders | | Collecting the Information for Detail Estimation |
| 39 | 25 Fri | Making the Report | Making Report | Making Report | Making Report | Generalizing the Environmental Condition Study | Making Report | Making Report | | Making Report |
| 40 | 26 Sat | Making the Report | Making Report | Making Report | Making Report | Making Report | Supervising Local Consultants | Making Report | | Making Report |
| 41 | 27 Sun | Data Sorting | Data Sorting | Data Sorting | Data Sorting | Data Sorting | Data Sorting | Data Sorting | | Data Sorting |
| 42 | 28 Mon | Making the Report | Making Report | Making Report | Making Report | Making Report | Making Report | Juba→Nairobi | | Making Report |
| 43 | 29 Tue | Juba→Nairobi | Juba→Nairobi | Juba→Nairobi | Juba→Nairobi | Juba→Nairobi | Juba→Nairobi | Nairobi→Dubai | | Juba→Nairobi |
| 44 | 30 Wed | Nairobi (EK720 Dep16:40) →Dubai (Arr 22:40) | | | | | Nairobi→Dubai | →Tokyo(EK318 Arr17:35) | | Nairobi→Dubai |
| 45 | 31 Thu | Dubai (EK318 Dep02:50)→Tokyo (EK318 Arr17:35) | | | | | →Tokyo(EK318 Arr17:35) | | | →Tokyo(EK318 Arr17:35) |

Khartum
Juba
Trip



JICA: Japan International Cooperation Agency
MTR: Ministry of Transport and Roads under GOSS (Government of Southern Sudan)
MOPI: Ministry of Physical Infrastructure under CES (Central Equatoria State)
Meeting with JICA Sudan Office or Embassy of Japan will be done as it need.

(4) Explanation and Conference of Draft Outline Design (15th October 2011 to 30th October)

| Date | | | | Team Leader | Planning Management | Chief Engineer/ Bridge Planning | Bridge Design I |
|------|---------|----|-----|---------------------------------|---------------------------------|--|--|
| No. | Date | | | Suzuki Masahiko | Fukuzawa Daisuke | Gose Shingo | Jovito C. Santos |
| 1 | October | 15 | Sat | | | | Tokyo(QR803 Dep 20:50)→ |
| 2 | | 16 | Sun | | | | →Nairobi(QR803 Arr 12:45) |
| 3 | | 17 | Mon | | | | Nairobi⇒Juba(KQ352 Arr 14:25) |
| 4 | | 18 | Tue | | | Tokyo(QR803 Dep 20:50)→ | Explanation DOD to MOPI |
| 5 | | 19 | Wed | | | →Nairobi(QR803 Arr 12:45) | Explanation DOD to MTR |
| 6 | | 20 | Thu | | | Nairobi⇒Juba(KQ352 Arr 14:25) | Explanation of EIA and RAP to MOE |
| 7 | | 21 | Fri | Tokyo(QR803 Dep 20:50)→ | Tokyo(QR803 Dep 20:50)→ | Meeting with JICA | Meeting with JICA |
| 8 | | 22 | Sat | →Nairobi(QR803 Arr 12:45) | →Nairobi(QR803 Arr 12:45) | Meeting with MRB | Meeting with MRB |
| 9 | | 23 | Sun | Nairobi⇒Juba(KQ352 Arr 14:25) | Nairobi⇒Juba(KQ352 Arr 14:25) | Study Team Meeting, Data Sorting | Study Team Meeting, Data Sorting |
| 10 | | 24 | Mon | | | Explanation of EIA and RAP to MOE, Meeting with JICA | Explanation of EIA and RAP to MOE, Meeting with JICA |
| 11 | | 25 | Tue | MM Conference at MOPI, MRB, MOE | MM Conference at MOPI, MRB, MOE | MM Conference at MOPI, MRB, MOE | MM Conference at MOPI, MRB, MOE |
| 12 | | 26 | Wed | Field Study, Meeting with IBRD | Field Study, Meeting with IBRD | Field Study, Meeting with IBRD | Field Study, Meeting with IBRD |
| 13 | | 27 | Thu | Signature of MM | Signature of MM | Signature of MM | Signature of MM |
| 14 | | 28 | Fri | SHM | SHM | SHM | SHM |
| 15 | | 1 | Sat | Departing from Juba | Departing from Juba | Juba(KQ351 Dep 10:15)→Nairobi→ | Juba(KQ351 Dep 10:15)→Nairobi→ |
| 16 | | 2 | Sun | | | →Tokyo(QR533 Arr 19:05) | →Tokyo(QR533 Arr 19:05) |

| | |
|--|--------------------|
| | Site (South Sudan) |
| | on Travle |

(5) Supporting for Compensation and Land Acquisition

(13th December 2011 to 26th December and 12th January 2012 to 1st February)

| Date | | | | Asst. Chief Engineer/ Bridge Design II/ Environmental Condition Survey | Bridge Design I |
|------|----------|----|-----|---|---|
| No. | Date | | | Mizota Yuzo | Jovito C. Santos |
| 1 | December | 13 | Tue | Checking of Resettlement Compensation | |
| 2 | | 14 | Wed | Checking of Resettlement Compensation | |
| 3 | | 15 | Thu | Checking of Resettlement Compensation | |
| 4 | | 16 | Fri | Checking of Resettlement Compensation | |
| 5 | | 17 | Sat | Checking of Resettlement Compensation | |
| 6 | | 18 | Sun | Checking of Resettlement Compensation | |
| 7 | | 19 | Mon | Checking of Resettlement Compensation | |
| 8 | | 20 | Tue | Conference about Compensation Condition among Ministries Committee | |
| 9 | | 21 | Wed | Checking of MRB Budget of Resettlement Compensation | |
| 10 | | 22 | Thu | Conference about Compensation Condition among Ministries Committee | |
| 11 | | 23 | Fri | Checking of MRB Budget of Resettlement Compensation | |
| 12 | | 24 | Sat | Meeting with MRB Juba(EK319 22:00)→Nairobi | |
| 13 | | 25 | Sun | Nairobi→ | |
| 14 | | 26 | Mon | →Tokyo(QR533 Arr 19:05) | |
| 15 | January | 12 | Thu | | Tokyo(Juba(EK319 22:00))→ |
| 16 | | 13 | Fri | | →Nairobi(EK719 Arr 14:55) |
| 17 | | 14 | Sat | | Nairobi→Juba(KQ350 Arr 9:20) |
| 18 | | 15 | Sun | | Review of IMC Activities |
| 19 | | 16 | Mon | | Meeting with MRB & MOPI on Relocation Site |
| 20 | | 17 | Tue | | Checking Site Condition/Road Alignment |
| 21 | | 18 | Wed | | Checking IMC Proposal on Compensation of Affected Persons |
| 22 | | 19 | Thu | | MRB & JICA Meeting on Relocation and Compensation |
| 23 | | 20 | Fri | | Checking the Condition of Resettlement Compensation |
| 24 | | 21 | Sat | | Meeting with MRB & Community about Compensation |
| 25 | | 22 | Sun | | Reporting |
| 26 | | 23 | Mon | | Meeting with MRB on Compensation of Affected Assets |
| 27 | | 24 | Tue | | Checking Road Alignment and Affected Persons |
| 28 | | 25 | Wed | | Meeting with MRB, MOPI & Payam on Resettlement Site |
| 29 | | 26 | Thu | | Meeting with MRB on RAP Schedule and Plan |
| 30 | | 27 | Fri | | Verification of Affected Persons/Marking |
| 31 | | 28 | Sat | | Checking Gorom Relocation Site |
| 32 | | 29 | Sun | | Reproting/Summary |
| 33 | | 30 | Mon | | Meeting with MRB on Next Schedule; Meeting with JICA |
| 34 | | 31 | Tue | | Juba(KQ351 Dep 10:15)→Nairobi→ |
| 35 | Feb | 1 | Wed | | →Tokyo(EK318 Arr 17:20) |

| | |
|--|----------------------|
| | - Site (South Sudan) |
| | - on Travel |

Appendix 3

List of Parties Concerned in the Recipient Country

List of Parties Concerned in the Recipient Country

Ministry of Roads and Bridges : MRB

| | |
|-------------------------|------------------|
| Mr. Gier Chuang Aluong | Minister |
| Mr. Simon Majok Majak | Deputy Minister |
| Mr. Jacob Marial Maker | Undersecretary |
| Mr. Gabriel Makur Amour | Director General |
| Mr. Otim Bong Mike | Deputy Director |

Ministry of Physical Infrastructure : MOPI

| | |
|-----------------------|------------------------|
| Mr. John Lado Tombe | Minister |
| Mr. Lewis Gore George | First Director General |

Ministry of Environment : MOE

| | |
|------------------------|-----------------|
| Mr. Alfred Ladu Gore | Minister |
| Mr. Philip Palet Gadin | Deputy Minister |
| Mr. Kuol Alor Kuol | Undersecretary |

Ministry of Finance and Economic Planning : MOFEP

| | |
|--------------------------------|----------------|
| Mr. Salvatore Garang Mabiordit | Undersecretary |
|--------------------------------|----------------|

Ministry of Foreign Affairs : MOFAIC

| | |
|---------------------------|-----------------|
| Mr. Elias Nymlell Wakoson | Deputy Minister |
|---------------------------|-----------------|

World Bank

| | |
|--------------------|-----------------------|
| Mr. Emmanuel Taban | Civil Engineer, AFTTR |
|--------------------|-----------------------|

Embassy of Japan in Sudan

| | |
|---------------------|--|
| Mr. Akinori Wada | Ambassador Extraordinary and Plenipotentiary |
| Mr. Yoichi Nakajima | Counselor |

JICA South Sudan Office

| | |
|----------------------|----------------------------------|
| Mr. Kenichi Shishido | Vice Resident Representative |
| Mr. Hanaoka Atsushi | Resident Representative |
| Mr. Yasuhiko Wada | Deputy Resident Representative |
| Mr. Kiyotaka Tamari | Vice Project Formulation Advisor |
| Ms. Makiko Kimura | Project Formulation Advisor |

Appendix 4 (1)

Minutes of Discussions (November 24th, 2010)

**Minutes of Discussions
On the Preparatory Survey
On the Project for Construction of Nile River Bridge
in the Republic of the Sudan
(The first site survey)**

In response to a request from the Government of Southern Sudan (hereinafter referred to as "GOSS") and Central Equatoria State (hereinafter referred to as "CES"), the Government of Japan decided to conduct a Preparatory Survey (hereinafter referred to as "the Survey") on the Project for Construction of Nile River Bridge in Southern Sudan (hereinafter referred to as "the Project"), and entrusted the study to Japan International Cooperation Agency (hereinafter referred to as "JICA").

JICA sent the Preparatory Survey Team (hereinafter referred to as "the Team") to Sudan, headed by Mr. Hiroyuki HAYASHI, Director, Urban and Regional Development Div I, Economic Infrastructure Dept., JICA, and is scheduled to stay in the country from October 20th to November 16th, 2010.

The Team held discussions with the officials concerned of GOSS and CES, and conducted a field survey in the project area.


In the course of discussions and field surveys, both sides confirmed the main items described in the attached sheets.

Juba, October 26, 2010




Hiroyuki HAYASHI
Leader
Preparatory Survey Team
Japan International Cooperation Agency
Japan

witness




Mr. Maurice REHAN
Acting Undersecretary
Ministry of Transport and Road
Government of Southern Sudan

witness


 26.10.2010

Mr. Aggrey Tisa Sabuni
Undersecretary
Ministry of Finance and Economic Planning
Government of Southern Sudan

witness

 26.10.2010

Mr. Baak Valentino A. Wol
Acting Undersecretary
Ministry of Regional Cooperation
Government of Southern Sudan



Mr. Lewis Gore George
First Director General
Ministry of Physical Infrastructure
Central Equatoria State

ATTACHMENT

1. Objective of the Project

The objective of the Project is to construct, in close collaboration with GOSS, a new Nile River Bridge and its approach roads to divert and distribute the traffic within and around all the city areas without concentrating at the central part of Juba.

2. Project Site

The Project site is located in City of Juba, as shown in Appendix-1.

3. Responsible and Implementing Organizations

3-1. The responsible and implementing organization is Ministry of Transport and Roads, GOSS (MTR).

3-2. The organization chart of MTR is as shown in Appendix-2

4. Items Requested by GOSS

The requested components are shown below. The requested items and their scale and size will be examined by the Team in the course of the Survey.

(1) Construction of Nile River Bridge (2 lanes)

(2) Construction of the part of the Circumferential Road "C3" (2 lanes)

JICA will assess the appropriateness of the above-mentioned components through the Preparatory Survey and will report the findings to the Government of Japan. Based on the results of the Survey, the Scope of the Outline Design Study for the Project will be determined by the Japanese side.

5. Japan's Grant Aid Scheme

5-1. The Southern Sudanese side understands the Japan's Grant Aid scheme explained by the Team, as described in Appendix-3 and 4.

5-2. The Southern Sudanese side will take the necessary measures to facilitate the smooth implementation of the Project, if the Japan's Grant Aid is implemented, as a condition for the Japanese Grand Aid to be implemented.

6. Environmental and Social Considerations

6-1. The Team explained the outline of JICA Guidelines for Environmental and Social Considerations (hereinafter referred to as "the JICA Guidelines") to the Southern Sudanese side. The Southern Sudanese side understood the concept of the JICA Guideline and agreed on reviewing Initial Environment Examination (IEE) and carrying out Environment Impact Assessment (EIA) in accordance with the Sudanese laws and regulations by the end of July, 2011.

Regarding the Project Affected Persons (PAPs) within the Project sites, the Southern Sudanese side agreed to secure the appropriate budget to be allocated before implementation of the Project. In this regard a Resettlement Action Plan (RAP) will be prepared by the end of September, 2011.

6-2. The implementing organization for EIA and RAP is Ministry of Physical Infrastructure, CES (MoPI).

(88)

B. W. A. I.

John

Help Dept.

7. Further Schedule of the Survey

- 7-1. The Team will continue further studies in Sudan until 16th November, 2010.
- 7-2. If the Project is deemed feasible as a result of the first site survey, the Government of Japan may decide to proceed and conduct the second site survey (Social Conditions Study stage ; December, 2010) and the third Site Survey (the Outline Design Study stage ; middle of February, 2011).

8. Other Relevant Issues

- 8-1. The Southern Sudanese side will submit answers to the Questionnaire, which the Team had handed to the Southern Sudanese side by November 12th, 2010.
- 8-2. The Southern Sudanese side shall provide security to all concerned members working for the Project, if deemed necessary.
- 8-3. The Southern Sudanese side shall allocate the necessary budget and counterpart personnel for executing the Project including operation and maintenance cost, especially to relocate power cable, telecommunications, water and sewage.
- 8-4. The Southern Sudanese side promised that they will utilize the JICA Guidelines so that for PAPs to maintain at least their current living conditions in their relocated place and will not be forcibly removed from their current resident place.
- 8-5. As for 5 2) of Appendix – 4, both side agreed that detailed will be discussed and confirmed in the Technical Notes, which will be signed between MTR and the Team.

Appendix 1: Project site

Appendix 2: Organization chart of MTR

Appendix 3: Japan's Grant Aid Scheme

Appendix 4: Necessary measures taken by the Southern Sudanese side



(FF)

B. W. I

17/11/10

AL

Dr. A. H. M.




Location Map

Handwritten signature/initials.

Handwritten signature/initials.

Handwritten signature/initials.

Handwritten signature/initials.



Note : Each division is headed by Deputy Director in principle

Organization of Ministry of Transport and Roads

Japan's Grant Aid

The Grant Aid scheme provides a recipient country with non-reimbursable funds to procure the facilities, equipment and services (engineering services and transportation of the products, etc.) for economic and social development of the country under the principles in accordance with the relevant laws and regulations of Japan. The Grant Aid, as such, is not supplied through the donation of materials.

1. Grant Aid Procedures

Japan's Grant Aid scheme is executed through the following procedures.

| | |
|---------------------------------|--|
| Application | (Request made by a recipient country) |
| Survey/Study | (Preliminary/Basic Design Study conducted by JICA) |
| Appraisal & Approval | (Appraisal by the Government of Japan and Approval by the Cabinet) |
| Determination of Implementation | (The Notes exchanged between the Governments of Japan and the recipient country) |

Firstly, the application or request for a Grant Aid Project submitted by a recipient country is examined by the Government of Japan (the Ministry of Foreign Affairs) to determine whether or not it is eligible for the Grant Aid. If the request is deemed appropriate, the Government of Japan assigns JICA (Japan International Cooperation Agency) to conduct a survey/study on the request.

Secondly, JICA conducts the survey/study (Preliminary/Basic Design Study), using (a) Japanese consulting firm(s).

Thirdly, the Government of Japan appraises the project to see whether or not it is suitable for Japan's Grant Aid Scheme, based on the Preliminary/Basic Design Study Report prepared by JICA, and the results are then submitted to the Cabinet for approval.

Fourthly, the project, once approved by the Cabinet, becomes official with the Exchange of Notes (E/N) signed by the Governments of Japan and the recipient country.

Finally, for the smooth implementation of the project, JICA assists the recipient country in such matters as preparing tenders, contracts and so on.

2. Preliminary/Basic Design Study

1) Contents of the Study

The aim of the Preliminary/Basic Design Study (hereafter referred to as "the Study"), conducted by JICA on a requested project (hereafter referred to as "the Project") is to provide a basic document necessary for the appraisal of the Project by the Government of Japan. The contents of the Study are as follows:

- Confirmation of the background, objectives, and benefits of the requested Project and also the institutional capacity of agencies concerned of the recipient country necessary for the Project's implementation.
- Evaluation of the appropriateness of the Project to be implemented under the Grant Aid Scheme from a technical, social and economic point of view.
- Confirmation of items agreed upon by both parties concerning the basic concept of the Project.
- Preparation of a Preliminary/Basic Design of the Project
- Estimation of cost of the Project

The contents of the original request are not necessarily approved in their initial form to be the contents of the Grant Aid project. The Preliminary/Basic Design of the Project is confirmed considering the Guidelines of Japan's Grant Aid Scheme.

The Government of Japan requests the Government of the recipient country to take whatever measures are necessary to ensure its self-reliance in the implementation of the Project. Such measures must be guaranteed even though they may fall outside of the jurisdiction of the organization actually implementing the Project in the recipient country. Therefore, the implementation of the Project is confirmed by all relevant organizations of the recipient country through the Minutes of Discussions.

2) Selection of Consultants

For smooth implementation of the Study, JICA uses (a) registered consulting firm(s). JICA selects (a) firm(s) based on proposals submitted by interested firms. The firm(s) selected carry(ies) out a Preliminary/Basic Design Study and write(s) a report, based upon terms of reference set by JICA.

The consulting firm(s) used for the Study is (are) recommended by JICA to the recipient country to also work on the Project's implementation after the Exchange of Notes, in order to maintain technical consistency.

3. Japan's Grant Aid Scheme

1) Exchange of Notes (E/N)

Japan's Grant Aid is extended in accordance with the Notes exchanged by the two Governments concerned, in which the objectives of the Project, period of execution, conditions and amount of the Grant Aid, etc., are confirmed.

2) "The period of the Grant Aid" means the fiscal year which the Cabinet approves the Project for. Within the fiscal year, all procedures such as exchanging of the Notes, concluding contracts with (a) consulting firm(s) and (a) contractor(s) and the final payment to them must be completed.

However, in case of delays in delivery, installation or construction due to unforeseen factors such as natural

disaster, the period of the Grant Aid can be further extended for a maximum of one fiscal year at most by mutual agreement between the two Governments.

3) Under the Grant Aid, in principle, Japanese products and services including transport or those of the recipient country are to be purchased.

When the two Governments deem it necessary, the Grant Aid may be used for the purchase of the products or services of a third country.

However, the prime contractors, namely, consulting constructing and procurement firms, are limited to "Japanese nationals". (The term "Japanese nationals" means persons of Japanese nationality or Japanese corporations controlled by persons of Japanese nationality.)

4) Necessity of "Verification"

The Government of the recipient country or its designated authority will conclude contracts denominated in Japanese Yen with Japanese nationals. Those contracts shall be verified by the Government of Japan. This "Verification" is deemed necessary to secure accountability to Japanese taxpayers.

5) Undertakings required to the Government of the Recipient Country

In the implementation of the Grant Aid Projects, the recipient country is required to undertake such necessary measures as the following:

- ① To secure land necessary for the sites of the Project and to clear, level and reclaim the land prior to commencement of the construction,
- ② To provide facilities for the distribution of electricity, water supply and drainage and other incidental facilities in and around the sites,
- ③ To secure buildings prior to the procurement in case the installation of the equipment,
- ④ To ensure all the expenses and prompt execution for unloading, customs clearance at the port of disembarkation and internal transportation of the products purchased under the Grant Aid,
- ⑤ To exempt all concerned members working for the Project from customs duties, internal taxes and other fiscal levies that will be imposed in the recipient country with respect to the supply of the products and services under the Verified Contracts,
- ⑥ To accord all concerned members working for the Project, whose services may be required in connection with the supply of the products and services under the Verified contracts, such facilities as may be necessary for their entry into the recipient country and stay therein for the performance of their work.

6) "Proper Use"

The recipient country is required to operate and maintain the facilities constructed and equipment purchased under the Grant Aid properly and effectively and to assign staff necessary for this operation and

(JB)

B. wal

2017

depth

maintenance as well as to bear all the expenses other than those covered by the Grant Aid.

7) "Re-export:"

The products purchased under the Grant Aid should not be re-exported from the recipient country.

8) Banking Arrangements (B/A)

- a) The Government of the recipient country or its designated authority should open an account in the name of the Government of the recipient country in a bank in Japan (hereinafter referred to as "the Bank"). The Government of Japan will execute the Grant Aid by making payments in Japanese yen to cover the obligations incurred by the Government of the recipient country or its designated authority under the Verified Contracts.
- b) The payments will be made when payment requests are presented by the Bank to the Government of Japan under an Authorization to Pay (A/P) issued by the Government of the recipient country or its designated authority.

9) Authorization to Pay (A/P)


The Government of the recipient country should bear an advising commission of an Authorization to Pay and payment commissions to the Bank.

JE

B. WOI

Don *He* *Deft*

Flow Chart of Japan's Grant Aid Procedures



55

B. wal

[Handwritten signature]

[Handwritten signature]

Major Tasks to be Undertaken by Each Government

| No. | Items | To be covered by Grant Aid | To be covered by the Recipient Side |
|-----|---|----------------------------|-------------------------------------|
| 1 | To secure land for the project, including resettlement sites for project affected persons | | ● |
| 2 | To clear, level and reclaim the project site when needed | | ● |
| 3 | To construct gates and fences in and around the project site | | ● |
| 4 | To bear the following commissions to the Japanese bank for banking services based upon the B/A | | |
| | 1) Advising commission of A/P | | ● |
| | 2) Payment commission | | ● |
| 5 | To ensure unloading and customs clearance at port of disembarkation in recipient country | | |
| | 1) Marine/Air/Land transportation of the products from Japan to the recipient country | ● | |
| | 2) Tax exemption and customs clearance of the products at the port of disembarkation | (●) | (●) |
| | 3) Internal transportation from the port of disembarkation to the project site | (●) | (●) |
| 6 | To accord Japanese nationals, whose service may be required in connection with the supply of the products and the services under the Verified Contract, such facilities as may be necessary for their entry into the recipient country and stay therein for the performance of their work | | ● |
| 7 | To exempt Japanese nationals from customs duties, internal taxes and other fiscal levies which may be imposed in the recipient country with respect to the supply of the products and services under the Verified Contracts | | ● |
| 8 | To maintain and use properly and effectively the facilities contracted and equipment provided under the Grant Aid | | ● |
| 9 | To bear all the expenses, other than those to be borne by the Grant Aid, necessary for construction of the facilities as well as for the transportation and installation of the equipment | | ● |

(B/A : Banking Arrangement, A/P : Authorization to Pay)

B. W. J.

Appendix 4 (2)

Minutes of Discussions
(October 27th, 2011)

**Minutes of Discussions
on the Preparatory Survey
on the Project for Construction of Nile River Bridge
in the Republic of South Sudan
(Explanation on Draft Final Report)**


In October 2010, the Japan International Cooperation Agency (hereinafter referred to as "JICA") dispatched the Preparatory Survey Teams on the Project for Construction of Nile River Bridge to the Government of Southern Sudan, and through discussions, field surveys and technical examination of the results in Japan, JICA prepared a Draft Final Report of the study.

In order to explain and to consult with the concerned officials of the Government of the Republic of South Sudan (hereinafter referred to as RSS) on the contents of the Draft Final Report, JICA sent to RSS the Preparatory Survey Team (hereinafter referred to as "the Team"), for explaining the Draft Final Report. The team is headed by Mr. Masahiko Suzuki, Senior Transport Sector Advisor, JICA and is scheduled to stay from October 17 to October 29, 2011.


As a result of the discussions, both sides confirmed the main item described in the attached sheets.

Juba, October 27, 2011



Mr. Masahiko Suzuki
Leader, Preparatory Survey Team
Japan International Cooperation Agency


Hon. Simon Majok Majak
Deputy Minister,
Ministry of Road and Bridges


Witness


Mr. Lewis Gore George
First Director General,
Ministry of Physical Infrastructure
Central Equatoria State


Witness



Mr. Salvatore Garang Mabiordit
Under Secretary,
Ministry of Finance and Economic Planning

Witness


Amb. Kuol Alor Kuol
Undersecretary,
Ministry of Environment

Witness


Prof. Elias Nyamlell Wakoson
Deputy Minister,
Ministry of Foreign Affairs and International
Cooperation



ATTACHMENT

1. Project Component

After the explanation of the contents of the Draft Final Report by the Team, RSS side agreed in principle to the project contents.

2. Responsible Organizations

Because of the reorganization of government ministries, the responsible organization has become Ministry of Road and Bridges (MRB) instead of Ministry of Transport and Road (MTR).

3. Cost Estimation

3-1. Both sides agreed that the Project Cost Estimation as attached in Annex-1 should never be duplicated or disclosed to any third parties before the signing of all the contract(s) with contractor(s) for the Project.

3-2. The Team explained to RSS side that the rough estimate of the Project Cost described in Annex-1 includes the contingency, however, the final Project Cost including the contingency described in E/N would be appraised by the Government of Japan. The contingency would cover the additional cost due to natural disaster, unexpected natural conditions, etc.

4. Japan's Grant Aid Scheme

RSS side understood the Japan's Grant Aid scheme and the necessary measures to be taken by the recipient country as explained by the Team and described in Annex-3 and Annex-4 of the Minutes of Discussions signed on October 26, 2010.

5. Schedule of the Study

JICA will complete the final report in accordance with the confirmed items and send it to RSS side around March, 2012.

6. Environmental and Social Considerations

6-1. RSS side assured to undertake Environmental and Social Considerations in conformity with EIA (Environmental Impact Assessment) and RAP (Resettlement Action Plan) report prepared. Further, it agreed to complete the EIA certification process and inform the result to JICA South Sudan office by the end of October, 2011.


6-2. RSS side agreed to protect the approach road embankment slope with sodding or other slope protection means and to undertake planting (including trees) to improve the natural environment and landscape.

6-3. Both sides agreed the contents of the Environmental Checklist as shown in Annex-2.

6-4. RSS side agreed that monitoring for Environmental and Social considerations should be conducted by MRB through contractor(s) in accordance with the Monitoring Plan for the Project described in the Preparatory Survey Report and EIA report.

The results of monitoring will be provided to JICA by filling in the Monitoring Form attached as Annex-3, during the pre- construction phase, construction phase, and after completion of the Project.

6-5. RSS side agreed that JICA will disclose the results of monitoring conducted by MRB on JICA's website and report the results of monitoring to the Advisory Committee for Environmental and Social Considerations established by JICA on a periodic basis.



7. Other Relevant Issues

7-1. Both sides confirmed that the following undertakings should be taken by RSS side at RSS expenses under the Project. The expected schedule is shown in Annex-4 and the responsible organization for each undertaking is shown in Annex-5.

- (1) Removal/Relocation of existing buildings, trees and other obstacles within the Project site in accordance with the RAP report and to inform the result to JICA South Sudan office.
 - i) Budget estimation for compensation by the end of November, 2011.
 - ii) Decision of the relocation site by the end of December, 2011.
 - iii) To start payment of compensation by the end of January, 2012.
 - iv) Completion of Relocation and Compensation by the end of June, 2012.
- (2) Securing and clearance of the temporary yard for the Project.
- (3) Securing site for borrowing pit, quarry and disposal area.
- (4) Necessary arrangement for tax exemption and custom clearance for project related equipments, materials and facilities.

7-2. Both sides agreed that the pavement structure of the approach road (approximately 3.5km) will be completed by RSS side before the target completion date of the Project. The Japanese consultant(s) and Japanese contractor(s) that are engaged in the Project, shall not be responsible for any future defects of the approach roads, and will be exempted from warranty against defect in the contract.

7-3. RSS side agreed that the completion of relocation and compensation for all utilities and PAPs is a condition of the commencement of pre-qualification under the contractor tendering procedure.

7-4. The Team explained that MRB may update the EIA and RAP report according to the comments of the Advisory Committee in Japan. RSS side agreed that any modification will be examined and the certification will be updated if necessary.

7-5. RSS side shall bear the banking commissions as a condition for the Japan's Grant Aid to be implemented, and secure the sufficient budget to cover the following cost.

- (1) The commissions for the banking services based upon Banking Arrangement (B/A)
- (2) The advising commission of the Authorization to Pay (A/P)

7-6. RSS side shall secure enough budget and personnel necessary for the operation and maintenance of the facilities constructed by the Project and conduct the periodical maintenance work after the completion of the Project.




Annex-1 Project Cost Estimation

Annex-2 Environmental Checklist

Annex-3 Monitoring Form

Annex-4 Schedule of Undertakings of RSS

Annex-5 Responsibility Matrix

AM.  S. S. M.  

Project Cost Summary

The total cost of the project which will be implemented under the financial assistance of Japanese Grant Aid and contribution from the Government of South Sudan is about _____ Yen. Cost breakdown based on the division of work between the two countries is presented below. This figure however is provisional and does not necessarily mean the upper limit for the grant referred to in the Exchange of Notes (E/N) and will be further examined when the implementation of the requested Japanese assistance is examined in a concrete manner.

(1) Japanese Contribution

The table below shows the breakdown of costs of Japanese contribution.

Cost Summary of Japanese Contribution

| Cost Summary of Japanese Contribution | | | Project Cost (Million Yen) |
|--|--------------|-----------------------------------|----------------------------|
| Facility | Bridge Works | Substructure | |
| | | Superstructure | |
| | | Ancillary works and approach road | |
| | | Temporary works | |
| | | Other indirect costs | |
| Detailed Design and Construction Supervision | | | |
| Contingency | | | |
| Total | | | |

(2) South Sudan Contribution

Cost Summary of South Sudan Contribution

| Item | Amount US\$ |
|--|-------------|
| 1. Advising Commission (Bank Charges) | 146,551 |
| 2. Land acquisition and relocation of house | 750,626 |
| 3. Pavement and drainage work of approach road | 9,085,010 |
| Total | 9,982,187 |

(3) Condition of Estimation

- ① Estimation Month/Year : March 2011
- ② Foreign Exchange Rate : US\$ 1.00 = 83.93 Yen (Exchange rate of Japanese Yen against American dollar)
 : US\$ 1.00 = 2.44 SDG (Exchange rate of American Dollar against South Sudan Pound)
 : Yen 1.00 = 0.0313 SDG (Exchange rate of Japanese Yen against South Sudan Pound)
- ③ Construction Period : Schedule of detailed design and construction supervision is shown in the schedule of implementation
- ④ Others : The project is to be carried out based on the Japanese Government's grant aid scheme.

[Handwritten signatures and initials: KAK, Jm, S. S. M., MA, ERW]

Environmental Check Lists for Roads/Bridges

| Category | Environmental Item | Main Check Items | Yes: Y No: N | Confirmation of Environmental Considerations (Reasons, Mitigation Measures) |
|----------------------------------|---|--|----------------------------------|---|
| 1. Permits and Explanation | (1) EIA and Environmental Permits | (a) Have EIA reports been already prepared in official process? (b) Have EIA reports been approved by authorities of the host country's government? (c) Have EIA reports been unconditionally approved? If conditions are imposed on the approval of EIA reports, are the conditions satisfied? (d) In addition to the above approvals, have other required environmental permits been obtained from the appropriate regulatory authorities of the host country's government? | (a) N (b) N (c) N (d) Y | (a) Preparing and to be submitted in October to MOE (b) - (c) - (d) Waste is dumped at authorized site. Soil/rock are to be bought from licensed quarry operators. As for river water sampling, the proponent will get necessary approval. |
| | (2) Explanation to the Local Stakeholders | (a) Have contents of the project and the potential impacts been adequately explained to the Local stakeholders based on appropriate procedures, including information disclosure? Is understanding obtained from the Local stakeholders? (b) Have the comment from the stakeholders (such as local residents) been reflected to the project design? | (a) Y (b) Y | (a) More than 5 times of public meetings and door to door interviews of 200 households were implemented from 2010 and project consent was obtained. (b) The proponent agreed with requests from illegal residents for the provision of cheap land, house compensation and transportation of private effects although such compensations are not specified in the law. |
| | (3) Examination of Alternatives | (a) Have alternative plans of the project been examined with social and environmental considerations? | (a) Y | (a) The site is the area where development is most urgently required and, within that area, the most technically, socially and economically feasible route has been chosen. |
| 2. Pollution Control | (1) Air Quality | (a) Is there a possibility that air pollutants emitted from the project related sources, such as vehicles traffic will affect ambient air quality? Does ambient air quality comply with the country's air quality standards? Are any mitigating measures taken? (b) Where industrial areas already exist near the route, is there a possibility that the project will make air pollution worse? | (a) Y (b) N | (a) Air quality will be improved in the vicinity of the existing bridge and although air pollution level complies with the international standards in 2015, it doesn't in 2025 unless the road network is improved. Before 2025, the urban road network will be improved and traffic congestion will be relieved with less emission. (b) No industrial area in Juba that can affect air quality |
| | (2) Water Quality | (a) Is there a possibility that soil runoff from the bare lands resulting from earthmoving activities, such as cutting and filling will cause water quality degradation in downstream water areas? (b) Is there a possibility that surface runoff from roads will contaminate water sources, such as groundwater? | (a) Y (b) N (c) Y | (a) There is no cut portion. Fill near the river is protected from erosion. Muddy water is once pooled in sediment ponds/tank before being discharged to the river. (b) Groundwater can be contaminated by inflow of muddy water through outcropped rock, into ground. However there no well at the out crop area. (c) Liquid waste from workers camp is dumped at the official dumping site. |
| | | (c) Do effluents from various facilities, such as parking areas/service areas comply with the country's effluent standards and ambient water quality standards? Is there a possibility that the effluents will cause areas not to comply with the country's ambient water quality standards? | | |

- : Not Applicable

| Category | Environmental Item | Main Check Items | Yes: Y No: N | Confirmation of Environmental Considerations (Reasons, Mitigation Measures) |
|------------------------------|-------------------------|---|--|---|
| 3. Natural Environment | (3) Wastes | (a) Are wastes generated from the project facilities, such as parking areas/service areas, properly treated and disposed of in accordance with the country's regulations? | (a) Y | (a) Solid waste is generated from the workers camp and is properly dumped at the official dumping site |
| | (4) Noise and Vibration | (a) Do noise and vibrations from the vehicle and train traffic comply with the country's standards? | (a) Y | (a) It may become greater than standard during construction in the area facing the road. Monitoring will be implemented and noise prevention barrier is installed if necessary. |
| | (1) Protected Areas | (a) Is the project site located in protected areas designated by the country's laws or international treaties and conventions? Is there a possibility that the project will affect the protected areas? | (a) N | (a) - |
| | (2) Ecosystem | (a) Does the project site encompass primeval forests, tropical rain forests, ecologically valuable habitats (e.g., coral reefs, mangroves, or tidal flats)? (b) Does the project site encompass the protected habitats of endangered species designated by the country's laws or international treaties and conventions? (c) If significant ecological impacts are anticipated, are adequate protection measures taken to reduce the impacts on the ecosystem? (d) Are adequate protection measures taken to prevent impacts, such as disruption of migration routes, habitat fragmentation, and traffic accident of wildlife and livestock? (e) Is there a possibility that installation of roads and bridges will cause impacts, such as destruction of forest, poaching, desertification, reduction in wetland areas, and disturbance of ecosystems due to introduction of exotic (nonnative invasive) species and pests? Are adequate measures for preventing such impacts considered? (f) In cases the project site is located at undeveloped areas, is there a possibility that the new development will result in extensive loss of natural environments? | (a) N (b) N (c) N (d) N (e) N (f) N | (a) - (b) - (c) - (d) - (e) - (f) - |
| | (3) Hydrology | (a) Is there a possibility that alteration of topographic features and installation of structures, such as tunnels will adversely affect surface water and groundwater flows? | (a) N | (a) - |

KAK.

Jm

S.H.M. J

MA

E.H.V

| Category | Environmental Item | Main Check Items | Yes: Y No: N | Confirmation of Environmental Considerations (Reasons, Mitigation Measures) |
|-----------------------------|----------------------------|--|---|---|
| | (4) Topography and Geology | <p>(a) Is there any soft ground on the route that may cause slope failures or landslides? Are adequate measures considered to prevent slope failures or landslides, where needed?</p> <p>(b) Is there a possibility that civil works, such as cutting and filling will cause slope failures or landslides? Are adequate measures considered to prevent slope failures or landslides?</p> <p>(c) Is there a possibility that soil runoff will result from cut and fill areas, waste soil disposal sites, and borrow sites? Are adequate measures taken to prevent soil runoff?</p> | <p>(a) N</p> <p>(b) N</p> <p>(c) N</p> | <p>(a) Based on the results of boring, the ground is confirmed to be generally firm. There is no possibility of collapse in fill since proper slope angles and depths are considered.</p> <p>(b) Excavation in the river will be made using be steel pipe sheet pile cofferdam.</p> <p>(c) -</p> |
| 4. Social Environment | (1) Resettlement | <p>(a) Is involuntary resettlement caused by project implementation? If involuntary resettlement is caused, are efforts made to minimize the impacts caused by the resettlement?</p> <p>(b) Is adequate explanation on compensation and resettlement assistance given to affected people prior to resettlement?</p> <p>(c) Is the resettlement plan, including compensation with full replacement costs, restoration of livelihoods and living standards developed based on socioeconomic studies on resettlement?</p> <p>(d) Are the compensations going to be paid prior to the resettlement?</p> <p>(e) Are the compensation policies prepared in document?</p> <p>(f) Does the resettlement plan pay particular attention to vulnerable groups or people, including women, children, the elderly, people below the poverty line, ethnic minorities, and indigenous peoples?</p> <p>(g) Are agreements with the affected people obtained prior to resettlement?</p> <p>(h) Is the organizational framework established to properly implement resettlement? Are the capacity and budget secured to implement the plan?</p> <p>(i) Are any plans developed to monitor the impacts of resettlement?</p> <p>(j) Is the grievance redress mechanism established?</p> | <p>(a) Y</p> <p>(b) Y</p> <p>(c) Y</p> <p>(d) Y</p> <p>(e) Y</p> <p>(f) Y</p> <p>(g) Y</p> <p>(h) Y</p> <p>(i) Y</p> <p>(j) Y</p> | <p>Replies to questions (a) through (j) are detailed in RAP. The followings outlines the replies:</p> <p>(a) The route is chosen with the least number of households affected which is the most technically and economically feasible.</p> <p>(b) It will be explained when the compensation policies have been finalized.</p> <p>(c) Value Assessment, Compensation and Resettlement Committee (VACRC) is established and census, assets survey, market price survey will be implemented.</p> <p>(d) Payment is scheduled before relocation.</p> <p>(e) They are indicated in the entitlement matrix.</p> <p>(f) Food and medical care cost (1 month income) is provided for vulnerable group.</p> <p>(g) Presently one household is reluctant for relocation, but persuasion is continued.</p> <p>(h) New committees will be established and the proponent will secure enough budget for compensation.</p> <p>(i) Both internal and external monitoring will be implemented.</p> <p>(j) Grievance committee which includes the representative of affected tribes will be established.</p> |
| | (2) Living and Livelihood | <p>(a) Where bridges and access roads are newly installed, is there a possibility that the project will affect the existing means of transportation and the associated workers? Is there a possibility that the project will cause significant impacts, such as extensive alteration of existing land uses, changes in sources of livelihood, or unemployment? Are adequate measures considered for preventing these impacts?</p> <p>(b) Is there any possibility that the project will adversely affect the living conditions of the inhabitants other than the target population? Are adequate measures considered to reduce the</p> | <p>(a) Y</p> <p>(b) Y</p> <p>(c) Y</p> <p>(d) N</p> <p>(e) N</p> <p>(f) N</p> | <p>(a) Shop keeper who loses shop is provided with shop loss allowance. Farmers, who lost farm are provided alternative farm lands or replacement cost.</p> <p>(b) Residents who may lose their job are employed at the construction site with priority.</p> <p>(c) Provision of safety measures, goods and prevention campaigns are planned.</p> <p>(d) The objective of the road project is to improve the road network and therefore improve the traffic flow in the surrounding areas. Intersections will properly consider traffic movement and</p> |

| Category | Environmental Item | Main Check Items | Yes: Y No: N | Confirmation of Environmental Considerations (Reasons, Mitigation Measures) |
|-----------------------------|--|--|---|---|
| 4. Social Environment | | <p>impacts, if necessary?</p> <p>(c) Is there any possibility that diseases, including infectious diseases, such as HIV will be brought due to immigration of workers associated with the project? Are adequate considerations given to public health, if necessary?</p> <p>(d) Is there any possibility that the project will adversely affect road traffic in the surrounding areas (e.g., increase of traffic congestion and traffic accidents)?</p> <p>(e) Is there any possibility that roads will impede the movement of inhabitants?</p> <p>(f) Is there any possibility that structures associated with roads (such as bridges) will cause a sun shading and radio interference?</p> | | <p>safety facilities installed along the road.</p> <p>(e) Intersections are properly designed to allow safe motorized and non-motorized movements. Shoulders and sidewalks are provided for safe movement of non-motorized transport, including pedestrians.</p> <p>(f) Only the section directly below the approach bridge deck will experience sun shading but it is within the project right-of-way.</p> |
| | (3) Heritage | (a) Is there a possibility that the project will damage the local archeological, historical, cultural, and religious heritage? Are adequate measures considered to protect these sites in accordance with the country's laws? | (a) N | (a) - |
| | (4) Landscape | (a) Is there a possibility that the project will adversely affect the local landscape? Are necessary measures taken? | (a) N | (a) The bridge form will add value to the existing landscape and will become symbolic to Juba. |
| | (5) Ethnic Minorities and Indigenous Peoples | <p>(a) Are considerations given to reduce impacts on the culture and lifestyle of ethnic minorities and indigenous peoples?</p> <p>(b) Are all of the rights of ethnic minorities and indigenous peoples in relation to land and resources to be respected?</p> | <p>(a) Y</p> <p>(b) Y</p> | <p>(a) Integration of host community and relocated community is planned.</p> <p>(b) Alternative relocation sites of similar environment and cultural background are identified for project affected persons. Affected cemetery will be relocated in accordance with local ceremony.</p> |
| | (6) Working Environment | <p>(a) Is the project proponent not violating any laws and ordinances associated with the working conditions of the country which the project proponent should observe in the project?</p> <p>(b) Are tangible safety considerations in place for individuals involved in the project, such as the installation of safety equipment which prevents industrial accidents, and management of hazardous materials?</p> <p>(c) Are intangible measures being planned and implemented for individuals involved in the project, such as the establishment of a safety and health program, and safety training (including traffic safety and public health) for workers etc.?</p> <p>(d) Are appropriate measures being taken to ensure that security guards involved in the project not to violate safety of other individuals involved, or local residents?</p> | <p>(a) Y</p> <p>(b) Y</p> <p>(c) Y</p> <p>(d) Y</p> | <p>(a) Compliance with the law is the first priority policy of EMP.</p> <p>(b) Health and safety plan for employees and residents are planned properly and secured.</p> <p>(c) Safety education, including how to use safety materials, equipment and facilities and how to behave in emergency case, are to be implemented.</p> <p>(d) Security guard is chosen after his background and experience is sufficiently checked.</p> |
| | | | | |

| Category | Environmental Item | Main Check Items | Yes: Y No: N | Confirmation of Environmental Considerations (Reasons, Mitigation Measures) |
|-----------|---|--|----------------------------------|--|
| 5. Others | (1) Impacts during Construction | (a) Are adequate measures considered to reduce impacts during construction (e.g., noise, vibrations, turbid water, dust, exhaust gases, and wastes)? (b) If construction activities adversely affect the natural environment (ecosystem), are adequate measures considered to reduce impacts? (c) If construction activities adversely affect the social environment, are adequate measures considered to reduce impacts? | (a) Y (b) N (c) N | (a) Monthly meeting will be held to monitor the complains about construction. Based on the meeting, mitigation measures are taken when necessary. (b) Impact to ecosystem is negligible and, for improvement of landscape, the vegetation/sodding on the embankment slope and river bank is promoted (c) Impact can be considered to be mitigated and public meeting is continued. |
| | (2) Monitoring | (a) Does the proponent develop and implement monitoring program for the environmental items that are considered to have potential impacts? (b) What are the items, methods and frequencies of the monitoring program? (c) Does the proponent establish an adequate monitoring framework (organization, personnel, equipment, and adequate budget to sustain the monitoring framework)? (d) Are any regulatory requirements pertaining to the monitoring report system identified, such as the format and frequency of reports from the proponent to the regulatory authorities? | (a) Y (b) Y (c) N (d) Y | (a) The contractor implements monitoring under the supervision of proponent. (b) Scheduled before, during and after construction for air pollution, noise and vibration, water pollution and social conditions of affected people as indicated in the monitoring plan in EIA. (c) Only one specialist is available and without any equipment. However, proponent is going to request enough budget from the government to fulfill the requirement of JICA Environmental and Social Considerations Guidelines as much possible. (d) The monitoring report, as discussed in the EIA, will be submitted to JICA every month. |
| | Reference to Checklist of Other Sectors | (a) Where necessary, pertinent items described in the Forestry Projects checklist should also be checked (e.g., projects including large areas of deforestation). (b) Where necessary, pertinent items described in the Power Transmission and Distribution Lines checklist should also be checked (e.g., projects including installation of power transmission lines and/or electric distribution facilities). | (a) N (b) N | (a) No forest at the site (b) - |
| 6. Note | Note on Using Environmental Checklist | (a) If necessary, the impacts to transboundary or global issues should be confirmed, if necessary (e.g., the project includes factors that may cause problems, such as transboundary waste treatment, acid rain, destruction of the ozone layer, or global warming). | (a) Y | Prediction of emission of CO2 were implemented in 2015 and 2025 respectively and results was found as the emission amounts will be halved by the implementation of the project in 2015 and 2025 respectively |

1) Regarding the term "Country's Standards" mentioned in the above table, in the event that environmental standards in the country where the project is located differ significantly from international standards, appropriate environmental considerations are required to be made. In cases where local environmental regulations are yet to be established in some areas, considerations should be made based on comparisons with appropriate standards of other countries (including Japan's experience).

2) Environmental checklist provides general environmental items to be checked. It may be necessary to add or delete an item taking into account the characteristics of the project and the particular circumstances of the country and locality in which it is located.

Monitoring Form

1. Permission and Public Meeting

| Items | Contents |
|---|--------------------------------------|
| The proponent will obtain the permission for river water sampling | Date of approval |
| Public meeting | Date, participants, subject, opinion |

2. Pollutions

| — Ambient Air Pollution Around the Site, 2 times per year between 2012-2018 Item | Unit | Nile Bridge Road | | Juba Bridge Road | | Tentative standards |
|--|-------------------|------------------|------------------|------------------|------------------|---|
| | | Beside road * | 200m behind road | Beside road * | 200m behind road | |
| Sulphur dioxides SO ₂ | µg/m ³ | | | | | WHO 20-125 (daily) 500 (10min) |
| Nitrogen dioxides NO ₂ | µg/m ³ | | | | | WHO 40 (yearly) 200(hourly) |
| Carbon monoxide CO | µg/m ³ | | | | | Japan 2000(8hours) |
| Suspended Particulate Matter SPM | µg/m ³ | | | | | Japan 100(daily) 200(hourly) |
| Dust | µg/m ³ | | | | | Japan 600 |
| Noise | dB | | | | | Japan 70 (Daytime) 65 (Nighttime) |
| Vibration | dB | | | | | Japan 70 (Daytime) 65 (Nighttime) |
| Traffic volume | No./hour | | | | | - |

*: Boundary between private and public/road areas

For sensitive areas (school, hospital and church), the limits shall be 60dB in daytime and 55 dB in nighttime for noise and vibration respectively.

— Maintenance of Equipment by Exhaust Gas Detector During Construction

| Item | Equipment 1 | Equipment 2 | | Standards |
|------|-------------|-------------|--|-----------|
| NO x | | | | |
| CO | | | | |

— Dust Suppression Plan During Construction

| Item | Confirmation | Standards |
|------|--------------|-----------|
|------|--------------|-----------|

Handwritten signature

Handwritten signature

Handwritten signature
A4(2)-10

Handwritten signature

Handwritten signature

Handwritten signature

| | | |
|-------------------------|--|---|
| Accesses | | Spray of water 5 times daily in dry season |
| Stock piles | | Water spray/covering with |
| Earth transport lorries | | Covering with tarpaulin and prohibiting overloading |

— Water Quality (Environmental Water Around the Site During Construction)

| Item | | Unit | 200m downstream from Nile Bridge | 200m upstream of Nile Bridge | Well at the site | Standards |
|--|--------------------------|-------------------|----------------------------------|------------------------------|------------------|--|
| Hand held type simple monitoring every month during construction | pH | - | | | | 6.5-8.5 |
| | Turbidity | NTU | | | | <5 NTU |
| | Electric Conductivity Ec | μS/cm | | | | <2000 (Environmental Protection Agency, USA) |
| | Dissolved oxygen DO | mg/L | | | | >2 (Japan) |
| Sampling and laboratory analysis 2 times before and during construction and 3 years after construction | SS | mg/m ³ | | | | <50 or <100 (Japan) |
| | Coliform | group/100mL | | | | Not detected |
| | Oil | mg/L | | | | 0.5mg/L (Japan) |

— Control of Muddy Water/Excavated River Bed Material During Construction

| Item | Situation |
|--|-----------|
| Installation of sediment ponds/tanks | |
| Approximate volumes of liquids brought in ponds/tank | |
| Sedimentation control | |

— Waste Management During Construction







| Item | Situation |
|---|-----------|
| Date of collection, types of waste (solid/liquid), volume/weight, | |

— Vegetation of the Embankment Slope During Construction

| Item | Situation |
|---|-----------|
| Date of seeding, area, growth condition | |
| Area covered | |

3. Health and Safety During Construction

| Item | Situation |
|---|-----------|
| Records of safety/health activities, accident reports | |
| Record of clinic activities and number of patients | |


4. Social Environment

— Involuntary Resettlement

| Item | Situation |
|---|-----------|
| Sample interviews about resettlement activities implemented (census, asset inventory, contract, payment, relocation site preparation, private assets transportation) per every three months, 4 times in total in 2012 | |

— Life and Livelihood Levels

| Item | Situation |
|---|-----------|
| Sample interviews about occupation, income, education and integration with surrounding communities one time in 2013, 2014 and 2015 respectively | |



Undertaking of South Sudan

1. Resettlement Activity

Resettlement activities to be conducted by South Sudan Government is described as following table:

| Activity | Responsible Agency | 2011 | | | | | | | | 2012 | | | | | | | |
|--|----------------------------|------|----|----|----|---|---|---|---|------|---|---|---|---|----|----|----|
| | | 9 | 10 | 11 | 12 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 |
| 1. Approval of RAP | MOE | | • | | | | | | | | | | | | | | |
| 2. Detailed Asset Survey and Compensation Estimation | IMC - VACRC | | • | • | | | | | | | | | | | | | |
| 3. RAP Budget - Submission - Approval | MRB | | • | | • | | | | | | | | | | | | |
| 4. Decision of Relocation Site | MRB | | | | • | | | | | | | | | | | | |
| 5. For Legal Residents (Formal) - Contracting for Compensation - Compensation Payment - Site Preparation (Demarcation) - Relocation of Residents | MRB MRB MOPI MOPI | | | | • | • | • | • | | | | | | | | | |
| 6. For Illegal Residents (Informal) - Contracting for Compensation - Compensation Payment - Identify Relocation Site - Relocation of Residents | MRB MRB MOPI MOPI | | | | • | • | • | • | | | | | | | | | |
| 7. Completion of Relocation | MRB | | | | | | | | | | • | | | | | | |
| 8. Grievance Redressing | IMC-GRC | | | • | • | • | • | • | • | • | • | • | | | | | |
| 9. Site Clearing for Alignment ROW | MOPI/MRB | | | | | | | | | | | • | • | | | | |
| 10. Possible Bidding Date | - | | | | | | | | | | | | | • | | | |
| 11. Possible Start of Construction | - | | | | | | | | | | | | | | • | | |

Notes: 1. Abbreviations:


- MOE - Ministry of Environment
- IMC - Inter-Ministry Committee for Nile River Bridge Construction Project, RSS
- VACRC - Value Assessment, Compensation and Resettlement Committee
- MRB - Ministry of Roads and Bridges, RSS
- MOPI - Ministry of Physical Infrastructure, CES
- GRC - Grievance and Redressing Committee
- JICA - Japan International Cooperation Agency

2. JICA will provide technical support for the RAP Activities.

2. Pavement Works

Pavement works for approach road to the proposed Nile river bridge shown in the following table is to be completed by South Sudan Government with road drainage works.

| Approach Road Works | Distance | Contents |
|---------------------|----------|---|
| Pavement | 3.565 km | Sub-base course, base course and surface pavement |
| Drainage | 7.23 km | Concrete ditch |




Project for Construction of Nile River Bridge in the Republic of South Sudan

Responsibility Matrix

| Items | Target Date | Responsible Agency | | | | | | |
|--|---|--|------|-----|------|-----|------------|-----|
| | | GOJ | RoSS | MRB | MOPI | MOE | Communi-ty | IMC |
| 1. Project Scope | • 560m two-lane Bridge | End of 2015 | ⊙ | | | | | |
| | • 2x50m PCCP Approach Road (1) | End of 2015 | ⊙ | | | | | |
| | • 3.6km Access Road (for Construction) | End of 2015 | ⊙ | | | | | |
| | • 3.6km AC Approach Road (2) | End of 2015 | | ○ | ⊙ | | | |
| | • Road Drainage | End of 2015 | | ○ | ⊙ | | | |
| 2. Project ROW and Permits/ Clearances | • Secure Budget for ROW & RAP | Dec 2011 | | ○ | ⊙ | | | |
| | • Project ROW Acquisition (30m wide route corridor) | End of June 2012 | | | ⊙ | ○ | | ○ |
| | • Project Site Preparation and Clearance (removal of existing buildings, trees, obstacles, removal/relocation of utilities, etc.) | End of July 2012 | | | ⊙ | ⊙ | | ○ |
| | • Clearance for Temporary Construction Yard | Before Construction | | | ⊙ | ○ | | ○ |
| | • Permits for Borrow Pit, Quarry, River Water Usage, Disposal Area, etc. | Before Construction | | | ⊙ | ○ | ○ | |
| 3. RAP | • RAP Approval | Oct 2011 | | | ○ | | ⊙ | |
| | • Detailed Asset Survey and Compensation Estimation | Nov 2011 | | | ○ | ○ | | ⊙ |
| | • RAP Budget (Preparation & Approval) | Dec 2011 | | ○ | ⊙ | | | |
| | • Compensation Agreement with PAPs | Dec 2011 | | | ○ | ○ | | ⊙ |
| | • Payment of Compensation | Jan-Mar 2012 | | | ⊙ | | | ○ |
| | • Relocation Site Preparation | Feb-Mar 2012 | | | ○ | ⊙ | | ○ |
| | • Relocation of PAPs | Mar-Jun 2012 | | | ○ | ⊙ | | ○ |
| 4. EIA | • RAP Monitoring | During RAP activities until after Resettlement | | | ⊙ | | ○ | ⊙ |
| | • EIA Approval | Oct 2011 | | | ○ | | ⊙ | |
| | • Monitoring for Environmental and Social Consideration | Before, During and After Construction | | | ⊙ | | ○ | ○ |
| 5. Bank Arrangement | • Bank Account and Bank Charges for Grant (Commission for Banking Arrangement and Authorization to Pay) | Before and during Construction | | ⊙ | ○ | | | |
| 6. Tax Exemption and Clearances | • Customs clearance and tax exemption for imported items related to project | During Construction | | ⊙ | ○ | | | |
| | • Tax exemption of Japanese nationals from customs duties, internal taxes and other fiscal levies for the supply of products and services | During Construction | | ⊙ | ○ | | | |

Notes:

- ⊙ - Major role/responsibility
- - Secondary role/responsibility
- GOJ - Government of Japan
- RoSS - Republic of South Sudan
- MRB - Ministry of Roads and Bridges, RoSS
- MOPI - Ministry of Physical Infrastructure, CES
- MOE - Ministry of Environment, RoSS
- IMC - Inter-Ministry Committee for Nile Bridge Construction



Appendix 5 (1)

Technical Notes

(November 11th, 2010)

Technical Notes
(The First Site Survey)

The JICA Study Team for the Preparatory Survey (the Study Team) and the representative of the Ministry of Transport and Roads (MTR) which is the responsible and implementing organization for the Project for Construction of Nile River Bridge (the Project) have agreed upon the items described in the attached Technical Notes, with witnesses of representatives of concerned Ministries. Based on the Technical Notes, the Study Team will analyze and discuss the First Site Survey results with authorities concerned in Japan to justify the Project and determine its scope.

November 11, 2010 in Juba



Dr. Shingo GOSE
Chief Consultant
JICA Study Team



Mr. Jacob Marial Maker
Director General
Ministry of Transport and Roads
Government of Southern Sudan

Witness



Mr. Lewis Gore George
First Director General
Ministry of Physical Infrastructure
Central Equatoria State

Witness



Mr. Victor Wurda LoTombe
Director General of Environmental Affairs
Ministry of Environment
Government of Southern Sudan

Witness



Mr. Otim Bong Mike
Deputy Director
Ministry of Transport and Roads
Government of Southern Sudan

Technical Notes for the First Site Survey

1. Engineering Aspects

1.1 Cross Sections

- The cross-section elements for the bridge component and the road component of the project are to be the ones shown in the Figures in **Annex-1**.
- The GOSS will complete the approach roads as shown in Figure1-1 of Annex-1 by utilizing the temporary construction access roads as shown in Figure1-2 of Annex-1.
- The temporary construction access roads during construction will be developed with gravel roads.
- The bridge cross section is shown in Figure 1-3 of Annex-1.

1.2 Bridge Location and Approach Road Route Alternatives

- Candidate bridge locations and approach road routes are shown in **Annex-2**.
- Based on the discussions with the concerned agencies of GOSS and analysis of the survey results, the most appropriate alternative will be recommended through discussions with JICA in Japan.

1.3 Navigation/Vertical Clearances

- There is no navigation clearance requirement in the proposed site location of the bridge.
- The vertical clearance, which is between the girder soffit and the highest water level in fifty years, stipulated in "Bridge Design Manual, 2006" (MTR) is to be used as the basis for the design.

2. Related Projects

2.1 Road Development Projects

- The GOSS side understood the importance of road development projects related to the Nile River Bridge Construction and presented the programs including those implementation schedules as shown in **Annex-3**.

2.2 Land Development Projects

- The proposed C-3 approach road on the west side will be incorporated into the present land demarcation and development program of the Central Equatoria State Ministry of Physical Infrastructure, as shown in **Annex-4**.

3. Environmental and Social Considerations (ESC) Aspects

- The GOSS side promised to take necessary measures for Environmental and Social



Considerations following the process and its time frame shown in **Annex-5**.

- A Value Assessment Committee (VAC) will be formed by the time shown in **Annex-5** in order to consult together and determine appropriate compensation prices. The VAC shall be composed of the representatives from the Ministry of Transport and Roads (MTR, GOSS), the Ministry of Environment (MOE, GOSS), the Southern Sudan Land Commission (SSLL, GOSS), the Ministry of Physical Infrastructure (MOPI, CES), the Ministry of Agriculture and Forest (MOAF, CES), Southern Sudan Center for Census, Statistics and Evaluation (SSCCSE), Ministry of Finance (MOF), NGOs and the concerned Communities.
- The GOSS side understood the recommendation of the Study Team that the Inter-Ministerial Monitoring Committee (IMMC) is to be established in order to undertake and monitor the legal framework of ROW acquisition, the RAP and Resettlement activities, and the implementation program of the road development projects related to the Nile River Bridge construction.

4. Application of Stage ROW Acquisition

- To enhance project cost effectiveness and reduce budgetary requirements from initial project costs, the ROW acquisition including compensation shall be undertaken by phasing following the process shown in **Annex-6**.






Figure 1-1 Approach Road




Figure 1-2 Temporary Construction Access Road




Figure 1-3 Bridge Section

Road and Bridge Cross-Section

36


36

3

36

36

36



Status of Road Development Projects Related to Nile River Bridge Construction


| Projects (refer to Appendix-1) | | Descriptions | Expected Funds | Planned Schedule |
|---|-------------|--|-------------------------------------|---------------------|
| 1. Nile River Bridge Approach Road (A-B and C-D Sections) | | <ul style="list-style-type: none"> Asphalt pavement for 2-lane road utilizing the temporary access roads for Nile River Bridge Construction. Improvement of side ditches. | GOSS (Temp. access road – Japan) | Refer to Appendix-2 |
| 2. C-3 Road Improvement (D-E Section) | | <ul style="list-style-type: none"> Gravel road is almost completed. Remaining works are asphalt pavement, installment of a bridge and side ditches improvement. | Sudan ^{*1)} | |
| 3. Lologo Street Improvement (H-I Section) | | <ul style="list-style-type: none"> Widening, grading and resurfacing including alignment improvement Asphalt pavement | GOSS | |
| 4. C-2 Road Improvement (F-G Section) | | <ul style="list-style-type: none"> Widening, grading and resurfacing including alignment improvement Asphalt pavement | GOSS | |
| 5. Nyakuron Street Construction (F-J Section) | | <ul style="list-style-type: none"> 2-Lane road construction | GOSS | |
| 6. Collector/Market Street Improvement (K-O Section & M-N Section) | | <ul style="list-style-type: none"> 4-Lane gravel road is almost completed. Installation of a 2-cell box culvert Partial 2-lane asphalt road completed Asphalt pavement | Sudan ^{*1)} | |
| 7. C-3 – R-1 Road Improvement | E-M Section | <ul style="list-style-type: none"> 4-Lane gravel road is completed. 2-lane asphalt pavement completed Remaining 2-lane asphalt pavement | Sudan ^{*1)} | |
| | M-P Section | <ul style="list-style-type: none"> 4-lane asphalt pavement completed for Section O-P RC Pipe drainage works 4-lane asphalt road construction for Section M-O | Sudan ^{*1)} | |
| 8. R6 Juba-Nimule Road Project (A to Nimule Section) | | <ul style="list-style-type: none"> 2-lane asphalt pavement (192kms). On-going. 8 bridges completed. | USAID | |
| 9. Juba Urgent Road Improvement Project | | <ul style="list-style-type: none"> 50kms of asphalt pavement completed (total length = 65kms). On-going. | GOSS | |
| 10. R-1 Road Improvement (E to Kaya Section) | | <ul style="list-style-type: none"> 2-lane asphalt pavement (245kms). F/S & D/D on-going | World Bank/ MDTF | |

*1) Forms part of the 20kms Sudan Government Road Project.

5



Status of Road Development Projects Related to Nile River Bridge Construction



Land Demarcation and Development Plan for Lologo 4th Class Residential Area

32

Im

8

Don't

Shant Job


Items and Time Frame on ESC^{*1)} to be undertaken by GOSS

| | Items to be undertaken by GOSS | Time Frame | Support by Japan Side |
|----|--|---|--|
| 1 | Establishment of Value Assessment Committee (VAC) | Before JICA Study Team arrival for the 3 rd Site Survey (around the middle of February, 2011) | Advice for candidate authorities/agencies and parties for the committee |
| 2 | Preparation of Environmental Impact Assessment (EIA) and Resettlement Action Plan (RAP) | <ul style="list-style-type: none"> • EIA Report preparation other than RAP <ul style="list-style-type: none"> - From December, 2010 to July, 2011 • RAP Report preparation <ul style="list-style-type: none"> - From December, 2010 to August, 2011 | <ul style="list-style-type: none"> • Support/Advice for technical issues • Procurement of consultant firm for EIA and RAP preparation • Providing Relevant Basic Design drawings and documents, if required |
| 3 | Declaration of Initial Cut-Off Date (prohibiting new development and housing within the Provisional ROW Limits) ^{*2)} | Within December, 2010 | Providing provisional ROW limits (100m) on a satellite map |
| 4 | Declaration of Final Cut-Off Date (Staking along the ROW limits) ^{*2)} | Early June, 2011 | Providing ROW limits (60m) on a topographic map |
| 5 | Issue of Environmental License (EL) for EIA and RAP by the Ministry of Environment (MOE) | By the end of September, 2011 | Providing relevant Basic Design drawings and documents, if required |
| 6 | Appraisal by Inter-Ministerial Appraisal Committee (IMAC) | By the middle of October, 2011 | Providing drawings and documents necessary for the appraisal |
| 7 | Compensation Agreement with Affected Persons | By the end of December, 2011 | Providing necessary information |
| 8 | ROW Acquisition including Compensation Payment | From early January to the end of June, 2012 | |
| 9 | Phase-I ROW Acquisition including Relocation of Affected Persons and Clearance of ROW Limits (30m) ^{*2)} | Before bidding date for the construction | |
| 10 | RAP Monitoring | From ROW acquisition until completion of the Project and at appropriate time of after completion of the Project | Advice for the monitoring. |
| 11 | EIA Monitoring | Duration of the project implementation and at appropriate time after completion of the Project | |

*1) ESC : Environmental and Social Considerations

*2) With respect to the meaning of these items, refer to **Annex-6** of the Technical Notes.

9



ROW Acquisition by Phasing

Appendix 5 (2)

Technical Notes

(March 21st, 2011)


Technical Notes (The Third Site Survey)

The JICA Survey Team for the Preparatory Survey (the Survey Team) and the representatives of the Ministry of Transport and Roads (MTR) which is the responsible and implementing organization for the Project for Construction of Nile River Bridge in Southern Sudan (the Project) have agreed upon the items described in the attached Technical Notes. Based on these Technical Notes, the Survey Team will carry out the basic design for the Project including the project cost estimate through analysis of the Third Site Survey findings and discussions with concerned authorities in Japan.

The results of the analysis and basic design will be presented and explained in October, 2011.

March 21, 2011

Juba, Southern Sudan



五瀬 伸吾

Dr. Shingo GOSE
Chief Consultant
JICA Study Team

Mr. Gabriel Makur Amour
Acting Director General,
Ministry of Transport and Roads
Government of Southern Sudan

 21/03/11

Mr. Otum Bong Mike
Deputy Director, Urban Roads
Ministry of Transport and Roads
Government of Southern Sudan



Mr. Emmanuel Matayo Wani
Director General, Housing & Construction
Ministry of Physical Infrastructure
Central Equatoria State



Mr. Victor Wurda LoTombe
Director General of Environmental Affairs
Ministry of Environment
Government of Southern Sudan



Technical Notes for the Third Site Survey/Basic Design

1. Application of Design Guideline

Reference shall be made to following manuals and standard specifications for the basic design requirements of roads and bridges:

- Geometric Design Manual, Ministry of Transport and Roads (MTR), GOSS, 2006.
- Bridge Design Manual, Ministry of Transport and Roads (MTR), GOSS, 2006.
- Drainage Design Manual, Ministry of Transport and Roads (MTR), GOSS, 2006

In addition to the above guidelines when other aspects of design are not covered or when a safer and more efficient requirement is indicated, the design of the New Nile Bridge shall refer to other standards, including:

- AASHTO Policy on Geometric Design of Highways and Streets, 2004
- AASHTO LRFD Bridge Design Specifications, 2007
- Specifications for Highway Bridges, Japan Road Association (JRA), 2002
- Specification for River Facilities, Japan River Association (JRA), 1998
- AASHTO Standard Specifications for Highway Bridges, 17th Ed., 2002

2. Right-of-Way (ROW) and Stage Construction

- The proposed New Nile River Bridge falls under the road functional category of International/Interstate Road (Principal Arterial).
- A 60m right-of-way (ROW) is recommended for this road based on the Road Network Master Plan of the Juba Urban Transport Infrastructure and Capacity Development Study (JICA 2010).
- However, considering the initial investment cost for the road and bridge, a stage construction with a 2-lane road and bridge in the initial stage is proposed for this project.
- Moreover, with the present budget constraint within GOSS, it is recommended that the right-of-way acquisition be conducted in two phases with the initial phase covering only 30m wide ROW which is sufficient to accommodate the initial stage 2-lane road.

3. Composition of Bridge and Approach Road Cross Sections

- The cross-section elements for the initial stage 2-lane bridge and road are shown in **Annex-1**.
- **Bridge Cross-Section.** The recommended bridge cross-section, as shown in **Annex-2**, consists of:

2 – lanes 3.6m wide traveledway satisfying the requirements of MTR for vehicular travel lanes.

- 2.5m wide sidewalk located on the left side or downstream side considering future 2-lane widening of similar cross-section on the upstream side.
 - 2 – 0.75m combined shoulder and gutter.
- **Approach Road Cross-Section.** The recommended cross-section for the approach road in the initial stage, shown in **Annex-2**, consists of:
- 2 – lanes 3.6 m wide traveledway satisfying the requirements of MTR for vehicular travel lanes.
 - 2 – 3.0m combined shoulder and sidewalk on both sides of the traveledway
 - A 50m long paved section with asphalt or concrete pavement will be provided on each end of the bridge to allow a smooth transition from the standard road section to the bridge section.
 - The rest of the road section shall be initially gravel paved with temporary wearing course (base course material) to be utilized as the access road during construction.
 - The MTR (GOSS) shall complete the pavement structure and the drainage facilities of the remaining section of the approach road before completion of the bridge.

4. Bridge Type Alternatives (Annex 3)

- Three (3) alternative types of bridges (as illustrated in **Annex 3**),
 - the Steel Tied Arch (Alternative – 1)
 - the Steel Box-Girder (Alternative – 2) and
 - the Prestressed Concrete Box Girder (Alternative – 3).will be compared from the viewpoints of structural system (performance/durability/maintenance), construction (method/cost/duration/ materials), river hydraulics, and aesthetic & environment.
- The MTR basically agreed with the three candidate alternative options for bridge type. However, selection of the most appropriate type shall be finalized in Japan, after analyzing the data gathered during the third site survey, considering economy, cost-effectiveness and construction reliability.

5. Approach Road Alignment Alternatives (Annex 4)

- Two (2) alternative approach road alignments,
 - the Downstream-side (Alternative-1) and
 - the Upstream-side (Alternative-2)options are presented in **Annex 4**.

Both options consider the technical aspect such as geometric and cross-section requirements for the roads, the road length, the social impact, the natural environmental impact and future widening.

- The Downstream-side (Alternative-1) alignment option is recommended considering the least social impact and the initial phase 30m ROW acquisition.

6. Design Requirements

- Road Functional Classification – Interstate Road (Urban/Peri-Urban).
- Design Standard - DS 2 according to the MTR Design Manual. The major geometric design conditions and elements are presented in **Annex 5**.
- Design Speed - 60km/hr as recommended in the JICA Road Network Master Plan in 2010. This proposal satisfies the standard design speed of Urban/Peri-Urban Class DS2.
- Design Flood Frequency and Freeboard – 1.50m freeboard for a 100-yr flood, in accordance with the MTR Design Manual.
- Pavement Design Life – 10 years in consideration of availability of existing reliable data. Pavement design will be made with full composition of pavement layers (including tarmac layers). However, the Scope of Work in the civil work contract under this project will cover layers up to subgrade/gravel base level only, with the pavement structure under GOSS responsibility.
- Utilities on Bridge – the design for bridge structure shall not cover any utilities as future attachment to the bridge.
- Street Lighting – the bridge design will consider provisions for street lighting of the bridge (in terms of locations of light pole base) but will not be part of the scope of works. Street lighting facilities shall be under GOSS responsibility.
- Others – all other design parameters shall follow the recommendations of MTR Manuals and Standards, as mentioned in Item 1. Deviations/exceptions from the standard shall be accompanied with reasonable clarifications.

7. Construction Planning

- Aggregate/Soil Borrow Site. Possible locations of borrow sites are shown in **Annex 6**. When necessary, the MTR shall obtain permissions for mining of aggregate/soil from the community, Ministry of Industry and Mining, CES and/or private firms or individuals concerned.
- Dumping of Discarded Soil. Possible location of disposal area is likewise shown in **Annex 6**. When necessary, the MTR shall obtain permissions for dumping of discarded soil from the community, Ministry of Environment, CES and/or private firms or individuals concerned.
- Construction Yard. The MTR shall procure the construction yard on the east and west areas of the Nile River, to be used during the construction period through negotiation with the community and to execute an agreement of lease prior to the approval of tender documents. Possible locations of construction yards of around 3.5 hectares are shown in **Annex-6**.


- Tax Exemption Related to Construction. The GOSS side shall issue exemption certificates for all concerned members working for the Project from Customs duties, internal taxes and other fiscal levies that may be imposed in Southern Sudan with respect to the supply of products and services, including the exemption certificate from the Central Equatoria State.
- Utility Diversion. The MTR shall relocate overhead electricity lines and electrical poles on the Nimule Road and other areas affected by the project prior to the approval of tender documents.
- River Water Use. Any permit/s necessary (including river water Abstraction Permit, Navigation Permit, etc.) for the use of the river and water during construction of the bridge shall be secured by MTR.

8. Related Projects

- The status and proposed implementation plan of road development projects related to the Nile River Bridge Construction Project in Juba City are presented in **Annex 7**.

9. Environmental License for Environmental Impact Assessment (EIA) and Resettlement Action Plan (RAP)

- EIA. The GOSS side (MTR, MOE, CES, etc.) has agreed on the items and time frame of the Environmental Impact Assessment (EIA) as shown in **Annex 8-1**.
- RAP. The GOSS side (MTR, MOE, CES, etc.) has agreed on the procedures of the Resettlement Action Plan (RAP) as shown in **Annex 8-2**.



Technical Notes (March 2011) - 4


Bridge Deck Cross-Section Elements

| Items | Applied Road Section | Bridge Section | | Remarks |
|---|--|---|---------------------------------------|--|
| | | GOSS Standard | Applied to Nile Bridge | |
| Road Class/Function | Interstate Road ¹⁾ / Primary Arterial ²⁾ | | | - Connects Juba-Nimule and Juba-Kaya Roads |
| Design Speed (km/hr) | 60 | 50 (Urban) ¹⁾ , 60 ²⁾ | 60 | |
| Lane Width (m) | 3.60 | 3.65 ¹⁾ | 3.60 | - GOSS minimum for 2-lane road is 7.30m in rural areas |
| Bridge Width (m) | - | 10.30 ²⁾ (min, including shoulder/sidewalk for urban areas) | 11.2 (including shoulder/sidewalk) | - Initial stage is a 2-lane bridge under this project - Applied curb-to-curb width is 8.7m plus 2.5m sidewalk |
| Shoulder (m) | 3.5 (combined use) | 2x1.5 ²⁾ (combined shoulder/sidewalk) | 0.75 (0.5m shoulder + 0.25 gutter) | - GOSS requirement is for combined shoulder and sidewalk |
| Sidewalk (m) | | 2.5 (min, on urban roads) | 2.5 | - GOSS minimum requirement for urban interstate road is 2.5m |
| Pavement Cross-fall (%) | 2.5 | 2 ²⁾ | 2.5 | |
| Freeboard from Design Flood Level (m) | n.a. | 1.5 ²⁾ | 1.5 | - Existing Juba Bridge freeboard from design flood is 0.85m |
| Min. Span Length for Main Bridge, S (m) | n.a. | - | 45 ⁴⁾ | - $S = 20 + 0.005Q$ ³⁾ $Q = 5,000 \text{ m}^3/\text{s}$ (100 yr discharge) |
| Design Vehicle | Semi-Trailer (W=2.6, L=16.7, H=4.1) | HS-25/HL-93 ²⁾ | HL-93 | |


Notes:

¹⁾ Geometric Design Manual, Ministry of Transport and Roads, GOSS, 2006²⁾ Bridge Design Manual, Ministry of Transport and Roads, GOSS, 2006³⁾ Drainage Design Manual, Ministry of Transport and Roads, GOSS, 2006⁴⁾ Specification for River Facilities, Japan River Association, 1998⁵⁾ Juba Urban Transport Infrastructure and Capacity Development Study in Southern Sudan, Road Network Master Plan, 2010


ANNEX 2



(1) Typical Bridge Deck Section




(2) Typical Approach Road Section



(3) 50m Paved Section at Approach Road




ANNEX 3-2




ALTERNATIVE 2 5-Span Steel Box Girder Bridge

ANNEX 3-2




ALTERNATIVE 3 5-Span Prestressed Concrete Box Girder Bridge




Geometric Design Criteria for Roads

| Parameters | Unit | Applied | AASHTO | SATCC | Southern Sudan | Remarks |
|--|------|--|---------------------------------------|---|--|---|
| Design Speed | Km/h | 60 | 60 | 60 | 60 | |
| Design Vehicle | M | Semi trailer combination large* W=2.6 L=16.7 H=4.1 | WB-15 W=2.6 L=17.0, H=4.1 | WB-15 (Semi-Trailer) W=2.5, L=17, H=4.1 | DV4 Semi trailer combination large* W=2.6 L=16.7 H=4.1 | |
| Lane Width | m | 3.6 | 3.6 | 3.1~3.7 (3.4) | 3.65 ¹⁾ 3.5 ²⁾ 3.35 ³⁾ | Less relationship to the design speed |
| Shoulder | m | 3.0 (Combined Use) | 1.2 (Combined Use) | 1.5, 2.0, 2.5 3.0 ⁴⁾ | Town Section 3.5 (Parking) Terrain : Flat 3.0 ¹⁾ 2.0 ²⁾ 2.5 ³⁾ | *1: DS1&DS2 *2: DS3 *3: DS4 *4: Highest Operation Speed and Heavy Traffic |
| Min. R. of Horizontal Curve | m | 150(2.5%) | Crossfall | | | |
| | | | 4% | 6% | 8% | |
| | | | 150 | 135 | 125 | |
| Min. Curve Length | m | Not Applicable | Not specified | 300 (absolute 150) | 5* or 300 | |
| Min. R. of Curve for omitting Transition | m | 500 ⁵⁾ | Not Specified | Not Specified | Transition curve is required to having design speed greater than 80km/hr | *5 R< (Design Speed) ⁶⁾ /432: Rounded |
| Stopping Sight Distance | m | 85 | 85 | 80 | 85 | |
| Max. Grade | % | 6.0 | 7.0(Level) | 6.0 (Flat) | 3.0 ⁶⁾ 6.0 ⁷⁾ | Flat/Absolute *6: DS1 to DS3 *7: DS4 to DS5 |
| K-Value at Crest Point | - | 180 | 195 | - | 180 | Passing Sight Distance |
| K-Value at Sag Point | - | Not Applicable | Not Specified | - | 180 | Passing Sight Distance |
| K-Value at Crest Point | - | Not Applicable | 11 | 16 | 18 | Stopping Sight Distance |
| K-Value at Sag Point | - | 18 | 18 | 16 | 18 | Stopping Sight Distance |
| Pavement Crossfall | % | 2.5 | 1.5~2 ⁸⁾ 2~6 ⁹⁾ | 2.0-3.0 | 2.5 | *8 :High Surface *9 Low Surface |
| Height Clearance | M | 5.0 | 4.3 | 5.1 | 5.0 | |
| Right of Way | M | 60(30) | More than Required Road Width | Not Specified | 60 | |

ANNEX 6



(1) Possible Locations of Borrow Pit, Quarry and Disposal Areas




(2) Possible Locations of Construction Yard

ANNEX 7-1**Status of Road Development Projects Related to Nile River Bridge Construction**

| Projects (refer to Annex 7-2, 7-3) | Road Section | Project Description and Status | Expected Funds | Planned Schedule |
|---|-----------------|---|--|--|
| 1. Nile River Bridge Approach Road | • A-B and C-D | <ul style="list-style-type: none"> Asphalt pavement for 2-lane road utilizing the temporary access roads for Nile River Bridge Construction. Construction of drainage/side ditches. Basic design on-going. | GOSS (Temp. access road – Japan) | Refer to Annex 7-4 |
| 2. C-3 Road Improvement | • D-E | <ul style="list-style-type: none"> Gravel road is almost completed. Remaining works are asphalt pavement, installment of a bridge and drainage/side ditches Project on-hold | North Sudan ^{*1)} (on-hold) | |
| 3. Lologo Street Improvement | • H-I | <ul style="list-style-type: none"> Widening, grading and resurfacing including alignment improvement Asphalt pavement Project planning | GOSS | |
| 4. C-2 Road Improvement | • F-G | <ul style="list-style-type: none"> Widening, grading and resurfacing including alignment improvement Asphalt pavement Project planning | GOSS | |
| 5. Nyakuron Street Construction | • F-J | <ul style="list-style-type: none"> 2-Lane road construction Project planning | GOSS | |
| 6. Collector/Market Street Improvement | • K-O & M-N | <ul style="list-style-type: none"> 4-Lane gravel road is almost completed. Installation of concrete box culverts Partial 2-lane asphalt road completed Asphalt pavement Project on-hold | North Sudan ^{*1)} (on-hold) | |
| 7. C-3 – R-1 Road Improvement | • E-M | <ul style="list-style-type: none"> 4-Lane gravel road is completed. 2-lane asphalt pavement completed Remaining 2-lane asphalt pavement on-hold | North Sudan ^{*1)} (on-hold) | |
| | • M-P | <ul style="list-style-type: none"> 4-lane asphalt pavement completed for Section O-P by GOSS 4-lane asphalt road construction for Section M-O^{*1)} Project on-hold | GOSS/ North Sudan ^{*1)} (on-hold) | |
| 8. R6 Juba-Nimule Road Project | • A to Nimule | <ul style="list-style-type: none"> 2-lane DBST pavement (192kms) 8 bridges completed On-going (Target: Feb. 2012) | USAID | |
| 9. Juba Urgent Road Improvement Project | • | <ul style="list-style-type: none"> 50kms of asphalt pavement completed (total length = 65kms). On-going (Project scope increasing) | GOSS | Started in 2006 – no definite target |
| 10. R-1 Juba-Yei-Kaya Road Project | • E to Kaya | <ul style="list-style-type: none"> 2-lane asphalt pavement (245kms, US\$310 million). D/D on final stage Awaiting funding for construction | World Bank/ MDTF (D/D) | Not Decided (Seeking funds for construction) |
| 11. Juba-Torit-Nadapal Road Project | • Juba to Kenya | <ul style="list-style-type: none"> 2-lane asphalt pavement (360kms, US\$333 million). D/D completed Awaiting funding for construction | World Bank/ MDTF (D/D) | Not Decided (Seeking funds for construction) |

Note: ^{*1)} Forms part of the 20kms North Sudan Government Road Project.


ANNEX 7-2




Road Development Projects Related to Nile River Bridge Construction Project



(1) International Road Projects Within South Sudan



(2) Related International Road Projects in Neighboring Countries

ANNEX 7-4
Implementation Schedule of Road Development Projects Related to Nile River Bridge Construction


Technical Notes (March 2011) - 16

ANNEX 8-1**Items and Time Frame on the Environmental Impact Assessment (EIA)
by GOSS and Japan**

| | Items to be undertaken by GOSS | Items to be undertaken by Japan | Time Frame |
|---|---|--|--------------------------------|
| 1 | Preparation and Review of EIA Report including RAP by MTR | Support of preparation for EIA report | By the end of July, 2011 |
| 2 | Submission of EIA Report to MOE by MTR | - | By the end of July, 2011 |
| 3 | Review of EIA Report by MOE | - | By the end of August, 2011 |
| 4 | Issue of Environmental License by MOE to MTR | - | By the end of September, 2011 |
| 5 | - | Submission and Explanation of Draft Basic Design (B/D) Report to MTR | By the middle of October, 2011 |
| 6 | Submission of Environmental License (EL) to Japan Side | Submission of B/D Report to Japanese Government | By the end of October, 2011 |



Approval of Japanese Cabinet (EL & B/D Report Essential)




- ◆ Implementation of D/D by Japan side
- ◆ Monitoring of EIA (RAP: Compensation, Site Clearance, etc.) by GOSS side



- ◆ Implementation of Bridge Construction by Japanese side
- ◆ Monitoring of EIA (Water Quality, Air Quality, Vibration/Noise, etc.) by GOSS side

Note: Details of RAP Procedures are described in Annex 8-2.

ANNEX 8-2**Procedures for the Resettlement of Action Plan (RAP)****Members of Compensation Committee ***

| Member | Remarks |
|--|-------------|
| 1st DG, MOPI | Chairman |
| DIR, Housing and Construction, MOPI, CES | Secretariat |
| D.D, Urban Roads, Roads & Bridges, MTR, GOSS | Member |
| Representative of Juba County | Member |
| Administrator of Payam Rejaf | Member |
| Chairman of Lologo Committee | Member |
| Chairman of Gumbo Community | Member |

Member of VAC Committee**

| VAC Member | Remarks |
|--|-------------|
| 1st DG, MOPI | Chairman |
| DIR, Housing and Construction, MOPI, CES | Secretariat |
| D.D, Urban Roads, Roads & Bridges, MTR, GOSS | Member |
| DIR, Land and Town Planning, MOPI, CES | Member |
| DIR, Department of Afforestation, MOAF, CES | Member |
| DIR, Department of Agriculture, MOAF, CES | Member |
| Chairman of Lologo Committee | Member |
| Chairman of Gumbo Community | Member |

Members of Mediator***

| Mediator | Area of Dispute |
|---|-------------------------|
| Payam Land Office | Government/Private Land |
| Traditional Authority (Community Chief) | Community Land |

Legend:

D.D: Deputy Director; DIR: Directorate; DG: Director-General; MTR: Ministry of Transport and Roads; MOPI: Ministry of Physical Infrastructure; MOAF: Ministry of Agriculture and Forestry; CES: Central Equatoria State; VAC: Value Assessment Committee.