## 2-2-3 Outline Design Drawing

 Table 2-2-23 shows the list of outline design drawings:

| No.   | Drawing No.   | Drawing Title   |  |  |
|-------|---------------|---|--|--|
| 1     | GE-GLP-001    | General Layout Plan   |  |  |
| 2     | WIF-LP-001    | Water Intake Facility General Layout Plan   |  |  |
| 3     | WIF-PFD-001   | Water Intake Facility Process Flow Diagram  |  |  |
| 4     | WIF-IW-001    | Water Intake Facility Weir Plan and Section   |  |  |
| 5     | WIF-PR-001    | Water Intake Facility Grit Chamber and Pump Room Layout Plan and Section            |  |  |
| 6     | WIF-GER-001   | Water Intake Facility Generator/ Electrical Room Plan, Section and Elevation        |  |  |
| 7     | WIF-E-001     | Water Intake Facility Single Line Diagram   |  |  |
| 8     | WIF-E-002     | Water Intake Facility LV Distribution Panel and Local Control Panel Outline Diagram |  |  |
| 9     | WTP-LP-001    | Proposed North WTP Layout Plan  |  |  |
| 10    | WTP-HP-001    | Proposed North WTP Hydraulic Profile  |  |  |
| 11    | WTP-PFD-001   | Proposed North WTP Process Flow Diagram   |  |  |
| 12    | WTP-IFD-001   | Proposed North WTP Instrumentation Flow Diagram                                     |  |  |
| 13    | WTP-RW-001    | Proposed North WTP Receiving Well Plan and Section                                  |  |  |
| 14    | WTP-ST-001    | Proposed North WTP Sedimentation Tank Plan  |  |  |
| 15    | WTP-ST-002    | Proposed North WTP Sedimentation Tank Section                                       |  |  |
| 16    | WTP-RSF-001   | Proposed North WTP Rapid Filter Plan  |  |  |
| 17    | WTP-RSF-002   | Proposed North WTP Rapid Filter Section   |  |  |
| 18    | WTP-CWR-001   | Proposed North WTP Clear Water Reservoir Plan                                       |  |  |
| 19    | WTP-CWR-002   | Proposed North WTP Clear Water Reservoir Section                                    |  |  |
| 20    | WTP-EWT-001   | Proposed North WTP Elevated Backwash Water Tank Plan and Section                    |  |  |
| 21    | WTP-SDB-001   | Proposed North WTP Drying Bed Plan and Section                                      |  |  |
| 22    | WTP-DP-001    | Proposed North WTP Drainage Pond Plan and Section                                   |  |  |
| 23    | WTP-ADB-001   | Proposed North WTP Operation Building Plan and Section                              |  |  |
| 24    | WTP-CR-001    | Proposed North WTP Chemical House Plan and Section                                  |  |  |
| 25    | WTP-CR-002    | Proposed North WTP Chemical House Elevation   |  |  |
| 26    | WTP-GER-001   | Proposed North WTP Generator and Electrical House Plan, Section and Elevation       |  |  |
| 27    | WTP-E-001     | Proposed North WTP Single Line Diagram  |  |  |
| 28    | WTP-E-002     | Proposed North WTP LV Distribution Panel and Local Control Panel Outline Diagram    |  |  |
| 29    | WTP-GH-001    | Proposed North WTP Guard House Plan, Section and Elevation                          |  |  |
| 30    | WTP-Reh-001   | Existing Central WTP General Layout Plan  |  |  |
| 31    | WTP-Reh-002   | Existing Central WTP Chemical House Plan, Section and Elevation                     |  |  |
| 32    | EDT-Reh-001   | Existing Reservoir Outline Plan and Painting Area                                   |  |  |
| 33    | PI-RM-001     | Raw Water Transmission Pipe Plan and Profile  |  |  |
| 34    | PI-RM-002     | Raw Water Transmission Pipe Plan and Profile  |  |  |
| 35    | PI-TM-001     | Clear Water Transmission Pipe Layout Plan   |  |  |
| 36~43 | PI-DP-001~008 | Distribution Pipe, Distribution Main Plan and Profile                               |  |  |
| 44    | PI-WPB-001    | Water Pipe Bridge Plan and Profile  |  |  |
| 45~50 | PI-SP-001~006 | Distribution Branch Pipe Plan   |  |  |

 Table 2-2-23
 List of Outline Design Drawings



























































2-69









| Name              | Height H(m) | Dia. B(m) | Volume (m³) | Structure                     |
|-------------------|-------------|-----------|-------------|-------------------------------|
| G.K.TANK          | 1.9         | 8.5       | 105         | Surfsce Type Circular Masonry |
| FTC TANK          | 1.9         | 8.5       | 105         | Surfsce Type Circular Masonry |
| Total Estate TANK | 2.3         | 7.8       | 100         | Surfsce Type Circular Masonry |
| Majengo TANK      | 2.4         | 7.9       | 100         | Surfsce Type Circular Masonry |
| Mwamba TANK       | 4.0         | 6.9       | 150         | Surfsce Type Circular Masonry |
| Oletipis TANK     | 4.0         | 8.5       | 225         | Surfsce Type Circular Masonry |
| Fanaka TANK       | 4.0         | 12.6      | 500         | Surfsce Type Circular Masonry |

| Name              | Contents of Repair Work |  |
|-------------------|-------------------------|--|
| G.K.TANK          | Painting & Water Proof  |  |
| FTC TANK          | Painting & Water Proof  |  |
| Total Estate TANK | Painting & Water Proof  |  |
| Majengo TANK      | Painting & Water Proof  |  |
| Mwamba TANK       | Painting & Water Proof  |  |
| Oletipis TANK     | Painting & Water Proof  |  |
| Fanaka TANK       | Painting & Water Proof  |  |

| Project Name   |                     |  |  |  |  |  |
|--|---------------------|--|--|--|--|--|
| The Preparatory Survey on The Project for                  | Augmentation of     |  |  |  |  |  |
| Water Supply System in Narok Town in The Republic of Kenya |                     |  |  |  |  |  |
| ケニア国ナロック給水拡張計画準備   | 調査                  |  |  |  |  |  |
| Drawrg Tile  | No.                 |  |  |  |  |  |
| Existing Distribution Reservoir (Renabilitation)           | Incare. INON        |  |  |  |  |  |
| Outline and Painting Area<br>既設配水池 概略図及び塗装面積               | Drawing EDT-Reh-001 |  |  |  |  |  |





Preparatory Survey on The Project for Augmentation of Water Supply System in NAROK Town in The Republic of KENYA Chapter2 Contents of the Project










Preparatory Survey on The Project for Augmentation of Water Supply System in NAROK Town in The Republic of KENYA Chapter2 Contents of the Project



























## 2-2-4 Implementation Plan

### 2-2-4-1 Implementation Policy

Actual water supply projects are implemented by NARWASSCO through trust contract with RV-WSB. Project execution structure is shown in **Figure 2-2-13**. From detailed design stage, this project will be consistently led by the project team specially established in RV-WSB and NARWASSCO. The roles of the project team are as follows:

- a. Represent the RV-WSB and NARWASSCO for this project
- b. Communicate with related Kenyan agencies
- c. Communicate with related external agencies
- d. Coordinate system design and tender procedure as counterpart of the consultant
- e. Coordinate additional survey and investigation

For smooth project implementation, the consultant carries out the detailed design, tender procedures and construction supervision within the planned work period. To achieve this, the consultant shall dispatch a resident construction supervision engineer to manage whole construction works on behalf of RV-WSB and shall also assign experts in specific fields of civil, pipeline, mechanical and electrical depending on the progress of works.

As major portion of this project is civil works, pipe laying and installation of mechanical/electrical equipment, and the assignment of Japanese contractor who has broad experience in similar works abroad is necessary. The selection of the contractor shall be done by general open tendering. Required contractors' qualifications and contractor selection criteria shall be examined and confirmed during the tender preparation stage, in with consultation with RV-WSB.

Upon the implementation of construction work, the resident engineer assigned by the contractor will manage the works. As Kenyan construction firms have been developed, local contractors can be employed as sub-contractors but will be supervised for strict work quality and safety management.

There are security restrictions on storage yard for pipes and fittings and these should be properly secured by guards. Furthermore, uPVC pipes are vulnerable to sunlight. Thus, their site delivery schedule shall be carefully planned according to work progress.

Unification of pipe specifications, careful arrangement on flange specifications of valves, fittings and joint parts and on locally available diameter of these are required. For timely site delivery, work plan and actual work progress shall always be monitored properly.



Figure 2-2-13 Project Execution Structure

#### 2-2-4-2 Implementation Conditions

The planned construction works are comprised of the construction of water intake facility and water treatment plant, the rehabilitation of the existing Central WTP and reservoirs and the installation of raw water transmission pipes, clear water transmission pipes and distribution pipes. Site office and material storage yard have already been acquired by NATWASSCO and are located near the construction site of the proposed North WTP, secured with adequate space.

As eligible local contractors are available, part of the works can be executed by them with strict management on construction materials and heavy machinery. Important points on construction work are summarized as follows.

#### (1) General

- a. It shall be noted that Muslims take several days off after Ramadan, aside from public holiday and national holiday in Kenya. Religious composition in Kenya is Protestant 47.7%, Roman Catholic 23.5%, Islam 11.2%, Transitional 1.7% and others 16.0%.
- b. Narok Town is located in African Rift Valley and is 140km away from national capital Nairobi in West. Since Narok Town is also located at the entrance of world famous Masaimara National Park and serves as a key entry point to major cities of Nairobi, Nakuru, Kissii and Kisumu, industrial and tourism development is expected. Such circumstances shall be considered in labor procurement and material/equipment transportation.
- c. Land transportation is mostly by vehicles since the railway has not yet reached to Narok Town.
- d. Annual rainfall in Narok Town has a wide range. Average rainfall during years of 2001 to 2010 was 736mm, 390mm in 2005 and 1,065mm in 2002. Temperature in 2011 ranged from

9°C to 27°C and average is 20°C. Average monthly rainfall is spread from 11.0mm to

113.8mm with total annual rainfall at 762.4mm. Rainy seasons can be divided into long-term rainy season from March to May, short-term rainy season from November to December and dry season from January to February, from June to October. Rainfall during rainy seasons fluctuates year on year. Intense rain comes with thunder mainly in nighttime during long-term rainy season, while temperate rain comes in the evening during short-term rainy season. In general, expected impact on construction work caused by rainfall is minimal although heavy rain should be expected. So, work efficiency can decrease during work days with rainfall greater than 10mm/day

- e. Water intake facility construction work and raw water transmission pipe installation work shall be executed during the dry season excluding months of November to May.
- f. During earthwork, rock excavation is anticipated especially in the construction of the water intake facility and raw water transmission pipe laying. Compared with in Embu and Kapsabet, there is a bigger possibility of rock excavation thus, heavy breakers are needed.
- g. Since pipe laying along the paved road of main road B3, Mai Mahiu-Narok section is prohibited, pipe shall be installed in the open space secured outside of drainage gutter. If pipe is planned in private land, RV-WSB and NARWASSCO shall obtain land use allowance and deal with necessary compensation.
- h. Complying with regulations of Road Authority, pipes shall be protected at the crossing points of the National Road or major town roads, if required.
- i. As the National Road B3 is trunk road for Kenyan inland transportation, pipe installation work plan shall be prepared that avoids road blockades.
- j. No stable commercial suppliers of ready mixed concrete are available in nearby cities including Nairobi. Thus, selection of a concrete batcher plant site is definitely needed.

Strict quality management shall be in place.

- k. Current water supply amount is insufficient, so water for construction work shall be secured by water tanker or storage pond.
- 1. Japanese experts shall be dispatched and works shall be carried out under their strict supervision for specific works such as pump placing work/test operation, welding works and so on.
- m. Heavy vehicles pass frequently during work period and thus, traffic congestion and impact by earth/gravel hauling is anticipated. To manage the dust problem, watering and spreading of gravel to un-paved roads shall be done.
- n. Comprehensive work plan is needed for rehabilitation works of the existing Central WTP, including filter material replacement and chemical dosage equipment installation to avoid adverse operational impacts on water treatment process.
- o. VAT on imported products and imported tax can be exempted by routine procedures. As to domestic procurements, refund process is generally done.
- p. The contractor will pay the custom bond to the insurance company or the bank when imported products which arrived at the port will be received. And, at that time, the contractor must pay the issue commission to the insurance company or the bank. The Kenyan side must pay the contractor in case the contractor submits the receipt for issue commission.
- q. Construction work implementation plan with full consideration of the surrounding environmental condition shall be prepared. As stipulated in NEMA regulation, countermeasures for environment related issues such as restoration of material storage yard, dust, noise and turbid water and surplus soil disposal shall be examined.
- r. Since local infrastructure is fragile and power failure occurs frequently, generators shall be utilized when needed.
- s. Price increases occur in the Kenyan market. According IMF estimates, price escalation of 11.3% is considered from cost estimation month to scheduled tendering month.

#### (2) Safety Control

Local safety related information shall be collected from JICA Kenya Office and the Embassy of Japan to prepare the safest measures with attention on the following items:

- a. Presidential election is scheduled on March 2013. According to the past experiences, security in Nairobi and other major local cities worsen in times of election, and thus safety measures shall be strengthened during the election period.
- b. Get timely advice from Kenyan counterpart agencies for safe and smooth work implementation.
- c. Keep close contact with donor agencies working in Narok to share security-related information.
- d. Generally, security in Narok Town and its surroundings is satisfactory and there are no problems in daily life. However, living in single detached housing is not favorable. Accommodation shall be in secured hotels or in several large housings units that provide communal living.
- e. Security incidents such as kidnapping have occurred in the past. Maximum care shall be taken when in major cities and facilities with many foreigners.

- f. Recently, Kenyan security has been deteriorating, including Nairobi City. Murders and robberies have become frequent. In the past, the site office of a Japanese contractor was attacked by robbers in Tanzania and Zambia. In this project, the project team shall consider contracting security with a security service provider in water supply facilities, site office and lodging areas. Guards with firearms shall be allocated, if needed.
- g. Logo marks shall be pasted on the work vehicles and the machineries to show that they are engaged in Japan-assisted project.
- h. Basic Operating Guideline (BOG) shall be publicized to related staff and workers to enable them to cope with unexpected security contingencies.

#### (3) Procurement Plan

#### a. Cement

Cement for ready-mixed concrete used for general concrete structure is manufactured in several factories of Banburi Cement Company in Mombasa, Blue Triangle Company and Rhino Cement Company in Nairobi. Raw material of cement is imported and landed at Monbasa port and transported to each factory by land. Total of cement price in Mombasa and transportation cost to site and cement price in Nairobi are almost the same. In case of the Embu project, cement is procured from Banburi Cement Company in Mombasa. In this project, procurement source shall be compared on the perspective of price and quality based on factory survey results.

b. Reinforcement bars

Though the price of reinforcement bars rapidly escalated in the years of 2010 and 2011 affected by World-cup Football Game, the price is stabilizing and fluctuates around peak level during run up years. Local products are available and only those manufactured based on British Standard (hereafter BS) quality control shall be procured.

c. Formwork

Domestic products are available but qualified formwork shall be supplied.

d. Gravel (coarse aggregate) and Sand (fine aggregate)

In Kenya, dust generated during gravel shaping is circulated in market as fine aggregate. Since dust contains fine powder, grain size distribution shall be confirmed upon application. Said aggregates are available at a quarry located an hour's drive from the site. There are two stores selling gravel and sand, one is on the way to Kisumu and another is on the way to Nairobi. However, when the construction work starts, this shall be re-confirmed.

e. Distribution Pipe Materials

As DI pipe is not currently manufactured in Kenya, this shall be imported from Japan or third countries. GI pipe, steel pipe with internal and external coating, uPVC pipe and HDPE pipe are manufactured in Nairobi factories and are domestically available. Spiral steel pipe is manufactured by only one company, called ASP Company situated in Nairobi. The minimum order length is 100m. As water leakage usually occurs in the butt welding joint, a simple steel plate socket is inserted at joint portion and is welded to pipe body by fillet welding.

Kenyan standard on uPVC pipe was revised in 2009 to comply with ISO1452-2 and pipe quality rapidly improved in recent years. Some companies have also been aggressively introducing foreign technologies, importing high quality raw materials and conducting water pressure test three times a day, taking samples every eight hours. Strict quality control should be practiced.



Low quality uPVC pipe

As some impurity might be contained, surface finishing and color are not homogeneous and pipe thickness is uneven. (Brown: for sewer and drainage, Grey: for water supply)



High quality uPVC pipe (Eslon Company)

Raw pipe materials are imported by mediation of Japanese company. Surface finishing and color are homogeneous and shiny. Pipe thickness is constant. (Brown : for sewer and drainage, Grey : for water supply)

Photo 2-2-2 uPVC Products

To secure a certain quality and durability, local pipe products that comply with BS and ISO specifications should be employed. Furthermore, pipes shall be procured from manufacturers which conduct voluntary quality test to produce high quality products.

f. Transportation Cost

Fuel costs have increased along with general price escalation. As fuel cost escalation directly affects in-land transportation cost, transportation cost shall be carefully estimated.

g. Exchange rate Fluctuation

Recently, there have been movements on the exchange rate between Japanese yen (hereafter JPY) and Kenya shilling (Kshs). Exchange rate fluctuations shall be carefully monitored.

#### 2-2-4-3 Scope of Works

**Table 2-2-24** and **Table 2-2-25** summarize work obligation and major undertakings of Japanese and Kenyan side.

| Work Items                           | Work Contents          | Kenyan Side | Japanese Side |
|--------------------------------------|------------------------|-------------|---------------|
| Water intake facilities construction | Procurement            |             | 0             |
| and raw water transmission pipe      | Construction works     |             | 0             |
| laying                               |                        |             |               |
| North WTP construction and           | Procurement            |             | 0             |
| clear water transmission pipe laying | Construction works     |             | 0             |
|                                      | Equipment installation |             | 0             |

Table 2-2-24Work Demarcation

| Work Items                         | Work Contents               | Kenyan Side | Japanese Side |
|------------------------------------|-----------------------------|-------------|---------------|
|                                    | Land acquisition            | 0           |               |
|                                    | Gate and Fence              | 0           |               |
|                                    | Distribution line           | 0           |               |
| Rehabilitation of existing Central | Procurement                 |             | 0             |
| WTP and reservoirs                 | Construction works          |             | 0             |
|                                    | Equipment installation      |             | 0             |
| Distribution Pipe                  | Procurement                 | 0           | 0             |
|                                    | Construction works          | 0           | 0             |
| Common                             | Temporary work road         |             | 0             |
|                                    | Permit approval acquisition | 0           |               |

### Table 2-2-25 Major Undertakings to be taken by each Government (General)

| No. | Undertakings   | Japan<br>(Grant) | Kenya |
|-----|--|------------------|-------|
| 1   | Secure land  |                  |       |
| 2   | Clear, level and reclaim the site when needed  |                  |       |
| 3   | Construct gates and fences in and arround the site   |                  |       |
| 4   | Access road  |                  | •     |
| 4   | In-site work road  | ۲                |       |
| 5   | Constrct water intake facility, raw water transmission pipe, North WTP and clear water transmission pipe | •                |       |
|     | Reghabilitation of the existing Central WTP and reservoirs   | $\bullet$        |       |
|     | Distribution pipe, $L = 80$ km, $\varphi 50 \sim 300$ mm   | $\bullet$        |       |
|     | Distribution pipe, $L = 20$ km, $\varphi$ 50mm   |                  | •     |
| 7   | Provide facilities for power supply, water supply, storm drainage and other incidental facilities        |                  |       |
|     | 1) Power Supply  |                  |       |
|     | a. Distribution line to the site   |                  | •     |
|     | b. Main circuit breakre and transformer  |                  | •     |
|     | c. Wiring within the site  |                  |       |
|     | 2) Water Supply (in site)  | •                |       |
|     | 3) Storm Drainage (in site)  | •                |       |
|     | 4) Telephone   | -                |       |
|     | a. Telephone trunk line from site office to main distribution panel                                      |                  | •     |
|     | b. Office cable  |                  |       |
|     | 5) Furniture and Equipment   |                  |       |
|     | a. General furniture   |                  | •     |
|     | b. Project equipment   |                  |       |
| 0   | Bear the following commissions to Japanese Bank for banking service based on the B/A                     |                  |       |
| 8   | 1) Advising Commision of A/P   |                  | •     |
|     | 2) Payment commission  |                  |       |
| 9   | Ensure unloading and customs clearance at port of disembarkation in recipient country                    |                  |       |
|     | 1) Marine (Air) transportaion of the products from Japan to the recipient country                        |                  |       |
|     | 2) Tax exemption and custom clearance of the products at the port of disembarkation                      |                  |       |
|     | 3) International transportation from the port of disembarkation to the project site                      |                  |       |
|     | Accord Japanese nationals, whose service may be required in connection with the supply                   |                  |       |
| 10  | of the products and the service under the verified contract, such facilities as may be                   |                  |       |
|     | of their work  |                  |       |
|     | Exempt Japanese nationals from custom duties, internal taxes and other fiscal levies                     |                  |       |
| 11  | which may be imposed on the recipient country with respect to the supply of the products                 |                  | •     |
|     | and services under the verified contracts  |                  |       |
| 12  | Bear all expenses needed to maintain, use properly and effectively the materials and                     |                  | •     |

| No. | Undertakings  | Japan<br>(Grant) | Kenya      |
|-----|---|------------------|------------|
|     | equipment provided under the Grant                                    |                  |            |
| 13  | Bear all installation cost for equipment not provided under the Grant |                  |            |
|     | (B/A: Bank Arrangenet, A  | P: Authrizati    | on to Pay) |

2-2-4-4 Consultant Supervision

After completion of the preparatory survey, cabinet approval of GoJ is executed. The proposed project will commence with the "Signing on Exchange of Note (E/N) related to grant aid assistance on this project".

#### (1) Detailed Design

If GoJ decides the grant aid assisted implementation based on the preparatory survey results, signing of E/N shall be carried out between GoJ and GoK. The consultant will then prepare the contract with RV-WSB and start the detailed design after certification by GoJ. The consultant shall conduct detailed field survey including topographic survey and carry out facilities design, cost estimation and preparation of tender documents.

#### (2) Tendering Procedures

All tender documents shall be approved by RV-WSB and after approval, move into tendering procedure immediately.

- a. Receive tender participation application from tenderers within one week after tender announcement.
- b. Evaluate tenderers' qualification with the least delay after receiving the applications
- c. Distribute tender documents to the eligible tenderers. After 1.5 months of preparation period, hold tender meeting with participation of persons involved.
- d. Tenderer that offers the lowest tender price is recommended to RV-WSB as successful tenderer and arrange for construction work contract.

#### (3) Construction Supervision

Site work consists of a wide-range of works such as, civil work, architectural work, pipe work, mechanical/electrical work. Engineers dispatched from Japan shall be one civil engineer to conduct resident supervision, structural and pipeline civil engineers, mechanical and electrical engineers. These engineers will be dispatched several times to carry out spot supervision according to the progress of major facility construction works. An assistant resident civil (local) engineer shall also be employed. Supervisory work shall be conducted with comprehensive meetings between the RV-WSB and the Japanese contractor.

Progress reports shall be submitted to MWI, RV-WSB, NARWASSCO, JICA Kenya office and JICA headquarters on schedule. Reports, contacts and meetings with relevant persons shall be carried out with undue delay.

## 2-2-4-5 Quality Control Plan

The Consultant shall require the Contractor to conduct the following tests shown in **Table 2-2-26** and reflect them to quality control plan.

| Test Items                          | Control Items  | Test Methods   | Standard/Remarks  |
|-------------------------------------|--|--|---|
| Pipe Materials                      | Strength/Dimensions<br>Appearance/Dimensions                                 | Confirm factory inspection report<br>Visual inspection/dimension measurement<br>Gauge  | Japanese Standard   |
| Pipe Installation                   | Torque<br>Leakage<br>Coating   | Torque wrench<br>Water pressure test<br>Coating thickness meter/visual inspection  | Japanese Standard   |
| Ground Foundation                   | Ground bearing capacity  | Plate loading test   | Japanese Standard   |
| Concrete<br>Reinforcement Bar       | Aggregate/Cement<br>Water<br>Fresh Concrete<br>Concrete Strength<br>Strength | Physical test/chemical test<br>Grain size test<br>Slump/air content/chloride content<br>Compressive strength test<br>Tensile strength test<br>Reinforcement bar arrangement inspection | Japanese Standard<br>BS<br>ISO<br>Japanese Standard<br>$440 \sim 600 \text{N/mm}^2$ |
|                                     |  |  | $545 \sim 595 \text{N/mm}^2$  |
| Structure Appearance                | Structure dimension  | Dimension measurement  | Japanese Standard   |
| Water-proof Work                    | Material quality<br>Paint thickness/ adhesion<br>Finishing status<br>Leakage | Confirmation of warranty<br>Thickness test/tensile test<br>Visual inspection<br>Water filling test   | Japanese Standard   |
| Mechanical /Electrical<br>Equipment | Installation precision<br>Functions  | Installation location measurement<br>Loading operation test  | Japanese Standard   |

Table 2-2-26Test Methods for Quality Control

## 2-2-4-6 Procurement Plan

#### (1) Source of Materials and Equipment

Eligible sources of materials and equipment to be procured by grant assistance project are basically Japan and recipient country. As much as possible, materials and equipment shall be procured in Kenya. However, for goods are not available in the local market, or stable supply cannot be ensured, or if cost is prohibitive, then these can be imported from Japan, considering cost benefit performance and O&M efficiency. Middle-south African countries, south Asian countries and EU countries are regarded as eligible third countries.

a. Civil materials

Among major civil and architectural materials, general ones such as cement, gravel, sand, brick, timber, petrol and oil shall be procured in the domestic market. However, measures to procure quality goods that comply with specifications shall also be examined.

b. Piping materials

Steel pipe with internal and external coating and uPVC pipe are manufactured in Nairobi factories and are available.

In the past years, domestic DI pipes were also manufactured but these are not currently circulated in the domestic market. Since no products have complied with the specifications, DI pipe shall be

imported from Japan or overseas factory of a Japanese manufacturer.

c. Mechanical/electrical equipment

The quality of equipment in water treatment plants is important and cannot be compromised. The advantage of third country procurement may be resorted to, but reliable Japanese products may also be procured.

d. Filter materials

High specifications such as grain size, specific gravity and grain size distribution are required for filter sand. Based on field survey results, domestic filter sand can be procured but strict quality control is needed.

e. Construction machineries

Though local construction machinery lease market is insufficient in terms of the number of available/operational machine units, so procurement of such general machineries employed in this project is permissible. Table 2-2-27 shows material/equipment procurement demarcation.

| Construction M                    | Procurement Source     |       |       |               |  |  |
|-----------------------------------|------------------------|-------|-------|---------------|--|--|
| Classifications                   | Items                  | Kenya | Japan | Third Country |  |  |
|                                   | Cement                 | 0     |       |               |  |  |
|                                   | Reinforcement bar      | 0     |       |               |  |  |
| Civil Materials                   | Formwork               | 0     |       |               |  |  |
|                                   | Sand, Gravel, Brick    | 0     |       |               |  |  |
|                                   | Light oil, Petrol      | 0     |       |               |  |  |
|                                   | DI Pipe                |       | 0     | (())          |  |  |
| Pipe Materials                    | GI Pipe, Steel Pipe    | 0     |       |               |  |  |
|                                   | uPVC Pipe              | 0     |       |               |  |  |
|                                   | Pumps                  |       | 0     |               |  |  |
| Mechanical/Electrical             | Chemical dosing device |       | 0     |               |  |  |
| Equipment                         | Filter sand            | 0     |       |               |  |  |
| Construction Equipment<br>(Lease) | Construction Equipment | 0     |       |               |  |  |
| Common Temporary<br>Works         | Concrete Plant         | 0     |       |               |  |  |

 Table 2-2-27
 Material/Equipment Procurement Demarcation

(): Provided the supply of products from overseas factory of Japanese Manufacturer

#### (2) Site Delivery and Storage Yard

Basically, the delivery site of procured material/equipment shall be the storage yard in Narok Town which shall be designated by NARWASSCO within or near the proposed North WTP site. Security shall be maintained at all times to prevent theft. Therefore, huge volume delivery is unfavorable especially in case of bulky pipe materials, and deliveries will have to be made in several batches according to the progress of work.

#### 2-2-4-7 Operational Guidance Plan

Upon facility completion, test operation shall be scheduled before the final turn-over of the facilities to confirm the function and operation of the installed equipment such as, generator, intake pump, transmission pump, chemical dosing equipment and so on. During the test operation, the initial operational training shall be conducted by the technical staff by the contractor before NARWASSCO O&M personnel to demonstrate the proper operation of each equipment. The contents of initial operational guideline are shown in **Table 2-2-28**.

| Facilities  | Major Guidance  | Remarks   |
|---|---|---|
| North WTP/<br>Clear Water Reservoir   | Surface washing function : Confirm functioning status, ON-OFF<br>operation, water amount setting, inspection method<br>Pumping function : Confirm functioning status, ON-OFF operation,<br>water amount setting, inspection method, emergency stop procedure<br>Sludging devices : Sludge operation<br>Chemical dosing devices : Dosage amount setting, agitator operation,<br>inspection method<br>Electrical equipment : Confirm functioning status, inspection method<br>Generating equipment : Confirm functioning status, operation<br>method, inspection method | Including operation<br>guidance to the<br>existing Central<br>WTP, especially<br>chemical dosage<br>equipment |
| Rehabilitation of the existing Central WTP  | Water level setting : Confirm functioning status, inspection method   | Rehabilitation of<br>the existing seven<br>(7) reservoirs   |
| Raw Water Transmission<br>Pipe, Clear Water<br>Transmission Pipe and<br>Distribution Pipe | Valves : Confirm functioning status, open-close operation, inspection method  |   |
| Raw Water Transmission<br>Equipment   | Transmission function : Confirm functioning status, ON-OFF<br>operation, North WTP receiving well water level setting, inspection<br>method, emergency stop procedure<br>Generator : Confirm functioning status, open-close operation,<br>inspection method   |   |
| Water Intake Equipment  | Valves and Gates : Confirm functioning status, open-close operation,<br>desludging method, inspection method<br>Screen : Inspection and cleaning method   |   |

 Table 2-2-28
 Initial Operational Guidance

#### 2-2-4-8 Soft Component Plan (Technical Assistance) Plan

The objective of "Project for Augmentation of Water Supply System in Narok Town" is to improve current unreliable water supply condition caused by deterioration of existing facilities and resulting to inadequate of water supply capacity which is to be implemented through Japanese Grant Aid assistance. These are: (1) Facility construction composed of (i) Rehabilitation of the existing Central WTP and reservoirs, (ii) Construction of new North WTP, water intake facility and a clear water reservoir, (iii) Installation of raw water transmission pipe, clear water transmission pipe and distribution pipe, and (2) Material/equipment procurement, composed of (i) Chemical dosage equipment and water quality analysis equipment, and (ii) Distribution pipe/house connection pipe/water meter.

NARWASSCO has to develop its capacity in managing the implementation of an improvement project

of this size, as well as operating and maintaining the system after construction. Thus, a soft component is planned to enhance the organizational capacity of NARWASSCO and of those who will be tasked with operation and maintenance. This will ensure that the project benefits are sustained. In preparing the soft component plan, these three separate activities shall be undertaken: 1) Capacity building on facility operation and maintenance of the entire water supply system, from the intake facility up to house connection. 2) Capacity upgrading on customer service management, particularly pipeline installation, water tariff billing and collection, finance and accounting work. 3) Capacity improvement and strengthening in over-all water utility management.

These three separate capacity development activities will become the core for the scope of work for soft component, as detailed in **Appendix 5**.

- ① O&M of Water Supply Facility
- 2 Upgrading Supervising Capacity of Pipe Installation
- ③ Strengthening Managerial Capacity of Water Supply Undertaking

#### 2-2-4-9 Implementation Schedule



 Table 2-2-29
 Implementation Schedule

# 2-3 Obligations of Recipient Country

The activities undertaken by GoK and NARWASSCO are described in "2-2-4-3 Scope of Works" and are tabulated in Table 2-3-1.

| No. | Work Items  | Description   | Quantity | Unit |
|-----|---|---|----------|------|
| 1   | New North WTP   | Gate  | 1        | set  |
| 1   | New Notur W 11  | Fence   | 880      | m    |
| 2   | Intake Facility   | Gate  | 1        | set  |
|     | intake i denity   | Fence   | 85       | m    |
| 3   | Access road to intake facility<br>(work road is undertaken by Grant<br>Aid) | Pavement cost is also borne by Kenyan side  | 1,500    | m    |
| 4   | Power receiving   | WTP   | 30       | m    |
|     | (distribution line+main breaker + transformer)                              | Intake facility   | 1,500    | m    |
| 5   | Distribution Pipe   | Lay $\varphi$ 50mm pipe with pipe materials and labor borne by Kenyan side  | 20,000   | m    |
| 6   | House Connection Pipe - 1   | φ13mm, Installation of Procured Pipe  | 16,000   | m    |
| 7   | House Connection Pipe - 2   | φ13mm, Procured and Installation of Pipe  | 16,000   | m    |
| 8   | Water Mater - 1   | Placing of provided meter   | 1,600    | pcs  |
| 9   | Water Mater - 2   | Procured and placing water meter  | 2,000    | pcs  |
| 10  | Land Acquisition  | Land acquisition for North WTP, raw water<br>transmission pipe and access road. As they are<br>governmental land, land acquisition cost is free | 5.5      | ha   |
| 11  | Land Rental   | Contractors Camp, stock yard and so on, 2 years   | 1.5      | ha   |
| 12  | Furniture for Administration Building                                       | If needed   | 1        | set  |
| 13  | Bank Commission   | 0.05% of total construction cost + 20,000Kshs   | 1        | set  |
| 14  | Disposal Site for Sludge (RV-WSB)   | Secure of disposal site for dry sludge contains<br>Fluorine   | 1        | set  |
| 15  | Commission Fee for Custom Bond  |   | 1        | set  |

Table 2-3-1 Undertaking by GoK and NARWASSCO

The abovementioned works are all important, especially for No.5, the laying of distribution pipe which is critical to achieve the project objectives. Out of the total distribution pipelines, with length of 80km priority pipes will be installed by the Japanese side. Distribution branch pipes of 20km shall be covered by NARWASSCO, including pipe material and installation costs.

Work schedule conducted by Kenyan side is shown in **Figure 2-3-1**. Most of the works except pipe work will be completed by the end of this project, and the rest of pipe works shall be completed within 5 years after this project.

|    | W/   | Decemination  | Work Schedule (Year)                     |                         |                        |            |                          |                           |                |   |         |   |
|----|--|---|--|-------------------------|------------------------|------------|--------------------------|---------------------------|----------------|---|---------|---|
|    | work items   | Description   | Details                                  |                         | 1                      | 2          | 3                        | 4                         | 5              | 6 | 6 7<br> | 8 |
|    |  |   | conducted b                              | Construct<br>by Japan's | ion Work<br>Side Start | Cons<br>by | truction V<br>Japan's Si | •<br>Work con<br>de Compl | ducted<br>eted |   |         |   |
| 1  | Installation of Distribution Pipe  | φ50mm, Total Length 20km  | L = 5km $L = 5km$ $L = 5km$ $L = 5km$    |                         |                        |            |                          |                           |                |   |         |   |
| 2  | Installation of House Connections<br>(Pipe Material to be provided under the | φ13mm (1/2"), Total Length 16km                                       | L = 8km<br>L = 8km                       |                         |                        |            |                          |                           |                |   |         |   |
| 3  | Installation of House Connection<br>(Pipe Material provided by Kenyan side)  | φ13mm (1/2"), Total Length 16kn                                       | L = 4km $L = 4km$ $L = 4km$ $L = 4km$    |                         |                        |            |                          |                           |                |   |         |   |
| 4  | Installation of Water Meters<br>(Water Meters to be provided under the       | Total 1,600 pcs   | 800 pcs<br>800 pcs                       |                         |                        |            |                          |                           |                |   |         |   |
| 5  | Installation of Water Meters<br>(Water Meters provided by Kenyan side)       | Total 2,000 pcs   | 500 pcs<br>500 pcs<br>500 pcs<br>500 pcs |                         |                        |            |                          |                           |                |   |         |   |
| 6  | Tree Felling & Leveling  | for Temporary Work Road at Raw<br>Water Transmission Pipe             |  |                         | -                      |            |                          |                           |                |   |         |   |
| 7  | Construction of Access Road  | from Intake to North WTP  |  |                         |                        |            | _                        |                           |                |   |         |   |
| 8  | Installation of Gate & Fence at Intake                                       | Gate: 1 set, Fence 85m  |  |                         |                        | -          |                          |                           |                |   |         |   |
| 9  | Installation of Gate & Fence at North WT                                     | Gate: 1 set, Fence 880m   |  |                         |                        | •          |                          |                           |                |   |         |   |
| 10 | Preparation of Power Receiving   | Distribution Line, Main Breaker,<br>Transformer at Intake & North WTP |  |                         |                        |            |                          |                           |                |   |         |   |
| 11 | Furniture for Administration Building at W                                   | /TP   |  |                         |                        |            |                          |                           |                |   |         |   |

Figure 2-3-1 Work Schedule conducted by Kenyan Side

A 5km/year distribution branch pipe laying shall be conducted by NARWASSCO. The on-going pipe laying work in Embu is performed by EWASCO with progress rate of 10km/month. NARWASSCO does not have working department at present, but it must develop a supervision capacity equivalent to 10% of EWASCO's.

Work capacity of contractors who have pipe laying work experiences in Narok Town is shown in **Tabele 2-3-2**. Work progress rate can be increased by manpower input, but the current NARWASSCO's work quality inspection is quite inadequate necessitating training by the soft component.

| Items   | STROIKA                                      | ENTAWUO   | ERETO                              |
|---|--|---|------------------------------------|
| Number of workers (persons)                         | 10 (Regular)                                 | 8 (Regular)   | 50 (Regular/Part-time)             |
| Pipe laying capacity<br>(Interview survey)          | 5 km/month<br>(Employing additional workers) | 3 to 5 km/month<br>(Employing additional workers)             | 1km/month                          |
| Experiences in<br>Plumbing works                    | 15 years                                     | 5 years   | 15 years                           |
| Experiences in<br>Construction works                | 15 years                                     | Not Available   | 15 years                           |
| Experiences in<br>Pipe laying works                 | 8 years                                      | 6 years   | _                                  |
| No. of projects<br>undertaken<br>(Interview survey) | 8 to 10 projects/year                        | 15 pipe laying works<br>More than 100 material<br>procurement | More than 50 large-scaled projects |

 Table 2-3-2
 Local Contractors in Narok Town

If Kenyan side works are executed smoothly, the planned distribution branch and house connection pipes are going to be completed within target year of 2020. This will enable achievement of the water service rate.

# 2-4 Project Operation Plan

#### (1) **O&M Structure**

The current NARWASSCO O&M structure is headed by a manager director, assisted by a commercial and sales department, a technical department and an administration and human resource department. The number of total staff is 23. At present no manager and staff are allocated to the administration and human resource department. With this project, the current water supply amount of 2,000m<sup>3</sup>/day will double to 5,000m<sup>3</sup>/day and so with the number of WTP from one to two. The current number of house connections of 2,000 HH is projected to exceed 5,000 HH. Therefore, personnel increase in the commercial and sales department, as well as the technical department is necessary. Furthermore, computer system will be needed to ensure efficient water tariff billing and accounting work. **Table 2-4-1** shows the work assignment, work contents, current staff number and proposed staff number for target year 2020.

|   |   | Staff Number as  | Proposed Staff |
|---|---|------------------|----------------|
| Line of Work                                | Description   | End of February  | Number in      |
|   |   | 2012             | 2020           |
| Managing Director                           | Generalization of Project Operation                           | 1                | 1              |
| Commercial & Sales Manager                  | Generalization of Commercial &<br>Sales                       | 1                | 1              |
| Technical Manager                           | Chief in charge of Design Techniques                          | 1                | 1              |
| Administration & Human Resource<br>Manager  | Chief in charge of Administration &<br>Human Resource Matters | —                | 1              |
| Sub Total                                   |   | 3                | 4              |
| Commercial & Sales                          |   |                  |                |
| Assistant Account & IT officer              | Accounting and computer operation                             | —                | 1              |
| Meter readers                               | Water meter reading   | 2                | 5              |
| Billing clerk & revenue collection<br>clerk | Bill issue and charge collection                              | 2                | 3              |
| Customer care officer & receptionist        | Q&A for customers   | 1                | 2              |
| Disconnection assistant                     | Valve disconnection for customers in arrears                  | 1                | 2              |
| Driver                                      |   | 2                | 4              |
| Sub Total                                   |   | 8                | 17             |
| Technical operations                        |   |                  |                |
| Water supply operator                       | Chief of WTP  | 1                | 2              |
| Artisan I (Water supply)                    |   | 3                | 8              |
| Artisan II (Masson Artisan)                 |   | 1                | 1              |
| Lab. Technologist                           | Water quality analysis  | 1                | 1              |
| Pump operators                              | O&M of intake facility, WTP and raw water transmission pump   | 1                | 2              |
| UFW & Reconnection officers                 | UFW handling and private faucet reconnection                  | 5* <sup>1)</sup> | 8              |
| Sub Total                                   |   | 12               | 22             |
| Audit Officer                               |   | —                |                |
| Human Resources                             |   |                  |                |
| Grand Total                                 |   | 23               | 43             |

Table 2-4-1 Composition of NARWASSCO Staff

\*1) : Though they are assigned as UFW & reconnection officer, they also engaged in other works due to man power shortage. They shall be exclusive officers for assigned work and other works shall be covered by personnel increase

Aside from the increase in personnel, proper maintenance of transport such as vehicles, motor bikes

and working trucks will be required. There will also be a need to have ties with local contractors to whom O&M work can be outsourced. New water meters must be installed to allow for easy meter reading, unlike the existing manner where meters are difficult to verify access and read.

#### (2) Required Number of Staff from Work Commencement Year to Target Year

Yearly personnel increase and allocation by work assignment is shown in **Table 2-4-2**. Since the organization structure has already been established, the increases in personnel by each department will be systematic.

As scheduled work commences on November 2013 up to work completion year, two water supply engineers will be required to personnel increase of two water supply engineers is needed to acquire O&M technology through soft component and OJT at the proposed North WTP.

On work completion year scheduled on October 2015, personnel increase is planned in WTP operation staff and in commercial and sales department to deal with house connection and customer increase. This arrangement is quite important for smooth progress of routine works and to upgrade customer service. Meter reader personnel shall be increased arbitrarily according to water meter placing plan and actual progress.

|   | 2012          | 2014 | 2015 | 2016                             | 2017 | 2018 | 2019 | 2020           |
|---|---------------|------|------|----------------------------------|------|------|------|----------------|
| Line of Work                                | At<br>present |      |      | Work Completion/<br>Commisioning |      |      |      | Target<br>Year |
| Managing Director                           | 1             | 1    | 1    | 1                                | 1    | 1    | 1    | 1              |
| Commercial & Sales Manager                  | 1             | 1    | 1    | 1                                | 1    | 1    | 1    | 1              |
| Technical Manager                           | 1             | 1    | 1    | 1                                | 1    | 1    | 1    | 1              |
| Administration & Human Resource<br>Manager  | _             | _    | _    | 1                                | 1    | 1    | 1    | 1              |
| Sub Total                                   | 3             | 3    | 3    | 4                                | 4    | 4    | 4    | 4              |
| Commercial & Sales                          |               |      |      |                                  |      |      |      |                |
| Assistant Account & IT officer              | _             | _    | 1    | 1                                | 1    | 1    | 1    | 1              |
| Meter readers                               | 2             | 2    | 2    | 3                                | 4    | 4    | 5    | 5              |
| Billing clerk & revenue collection<br>clerk | 2             | 2    | 2    | 3                                | 3    | 3    | 3    | 3              |
| Customer care officer & receptionist        | 1             | 1    | 1    | 2                                | 2    | 2    | 2    | 2              |
| Disconnection assistant                     | 1             | 1    | 1    | 2                                | 2    | 2    | 2    | 2              |
| Driver                                      | 2             | 2    | 2    | 3                                | 3    | 4    | 4    | 4              |
| Sub Total                                   | 8             | 8    | 9    | 14                               | 15   | 16   | 17   | 17             |
| Technical operations                        |               |      |      |                                  |      |      |      |                |
| Water supply operator                       | 1             | 1    | 1    | 2                                | 2    | 2    | 2    | 2              |
| Artisan I (Water supply)                    | 3             | 3    | 5    | 8                                | 8    | 8    | 8    | 8              |
| Artisan III                                 | 1             | 1    | 1    | 1                                | 1    | 1    | 1    | 1              |
| Lab. Technologist                           | 1             | 1    | 1    | 1                                | 1    | 1    | 1    | 1              |
| Pump operators                              | 1             | 1    | 1    | 2                                | 2    | 2    | 2    | 2              |
| UFW & Reconnection officers                 | 5             | 5    | 5    | 8                                | 8    | 8    | 8    | 8              |
| Sub Total                                   | 12            | 12   | 14   | 22                               | 22   | 22   | 22   | 22             |
| Grand Total                                 | 23            | 23   | 26   | 40                               | 41   | 42   | 43   | 43             |

Table 2-4-2 Required Number of Staff from Work Commencement Year to Target Year

## 2-5 Project Cost Estimation

#### 2-5-1 Initial Cost Estimation

#### (1) Cost to be Borne by the Kenyan Side

| No | Work Items  | Description  | Quantity | Unit | Unit Cost                             | Cost<br>(Kshs) |
|----|---|--|----------|------|---------------------------------------|----------------|
| 1  | New North WTP<br>(NARWASSCO)  | Gate   | 1        | set  | 150,000                               | 150,000        |
|    |   | Fence  | 880      | m    | 1,900                                 | 1,672,000      |
| 2  | Intake Facility<br>(NARWASSCO)  | Gate   | 1        | set  | 150,000                               | 150,000        |
|    |   | Fence  | 85       | m    | 1,900                                 | 161,500        |
| 3  | Access road to intake<br>facility (road work is<br>undertaken by Japan<br>Grant Aid)<br>(NARWASSCO) | Pavement cost is also borne<br>by Kenyan side  | 1,500    | m    | 34,000                                | 5,100,000      |
| 4  | Power receiving<br>(distribution line+main  | WTP  | 30       | m    | · · · · · · · · · · · · · · · · · · · |                |
| -  | breaker + transformer)<br>(NARWASSCO)   | Intake facility  | 1,500    | m    | -                                     | 11,000,000     |
| 5  | Distribution Pipe<br>(NARWASSCO)  | Lay φ50mm pipe with pipe<br>materials and labor borne by<br>Kenyan side  | 20,000   | m    | 1,000                                 | 20,000,000     |
| 6  | House Connection Pipe<br>(NARWASSCO)  | φ13mm, Installation of procured pipe   | 16,000   | m    | 600                                   | 9,600,000      |
| 7  | House Connection Pipe<br>(NARWASSCO)  | φ13mm, Procured and installation of pipe   | 16,000   | m    | 700                                   | 11,200,000     |
| 8  | Water mater<br>(NARWASSCO)  | Placing of provided water meters   | 1,600    | pcs  | 300                                   | 1,110,000      |
| 9  | Water mater<br>(NARWASSCO)  | Procured and placing water meters  | 2,000    | pcs  | 4,300                                 | 8,600,000      |
| 10 | Land Acquisition (NARWASSCO)  | Land acquisition for WTP,<br>raw water transmission pipe<br>and access road. As they are<br>governmental land, land<br>acquisition cost is free. | 5.5      | ha   | -                                     | 0              |
| 11 | Land Rental<br>(NARWASSCO)  | Contractors Camp, stock yard<br>and so on, 2 years   | 1.5      | ha   | 1,250,000                             | 0              |
| 12 | Furniture for<br>Administration Building<br>(NARWASSCO)   | If needed  | 1        | set  | 200,000                               | 200,000        |
| 13 | Bank Commission<br>(RV-WSB)   | 0.05% of total construction<br>cost + 20,000Kshs   | 1        | set  | 580,000                               | 580,000        |
| 14 | Disposal Site for Sludge<br>(RV-WSB)  | Secure of disposal site for dry sludge contains Fluorine   | 1        | set  | -                                     | -              |
| 15 | Commission Fee for<br>Custom Bond   |  | 1        | set  | 3,000,000                             | 3,000,000      |
|    | Grand Total   |  |          |      |                                       | 72,523,500     |

Distribution pipe (pipe materials + installation) conducted by NARWASSCO with length of 20km will be installed 4 years from 2015. GoK budget for Iimplementation of Water Project is about 600 to 700 million Kshs, 2011/2012 budget is 670 million Kshs. Therefore, construction cost borne by Kenyan side (72.5 million Kshs) considering implemented in 5 years is estimated (72.5 million Kshs / 5 years) / 670 million Kshs  $\times 100\% = 2.2\%$ . It is conceivable that Kenyan side can bear this cost sufficiently.

#### 2-5-2 Operation and Maintenance Cost

#### (1) O&M Cost

The estimated O&M cost in the target year of 2020 is shown in **Table 2-5-2**. Price escalation of 4% is utilized for cost estimation purposes. Refer to Kenyan major indices view, April 2012, JICA. As a result, the projected O&M cost in 2020 is 84.3 million Kshs/year. Compared with actual performance in 2011 of 30.9 million Kshs/year, O&M cost is projected to be 2.7 times in 2020.

|   |   | O&M Cost   | (Kshs/Year)               |
|---|---|------------|---------------------------|
| Cost Items  | Calculation (at year of 2020)   | 2020       | 2011Actual<br>Performance |
| Private Cost  | <ul> <li>Total 43 persons</li> <li>40,000Kshs Ave./person • month×12 months×43preson</li> <li>= 20,640,000Kshs/year</li> </ul>  | 20,640,000 | 7,700,000                 |
| Chemical Cost   | <ul> <li>Existing Central WTP</li> <li>Aluminum Sulfate (Average dosing rate 80ppm)<br/>50Kshs/kg×84kg/day×365 day = 1,533,000Kshs/year</li> <li>Lime (Average dosing rate 10ppm)<br/>70Kshs/kg×10.5kg/day×365 day = 268,000Kshs/year</li> <li>Calcium hypochlorite (Average dosing rate as effective chlorine 2ppm)<br/>240Kshs/kg×3.2kg/day×365 day = 280,000Kshs/year</li> <li>New North WTP</li> <li>Aluminum Sulfate (Average dosing rate 80ppm)<br/>50Kshs/kg×344kg/day×365 day = 6,278,000Kshs/year</li> <li>Lime (Average dosing rate 10ppm)<br/>70Kshs/kg×43kg/day×365 day = 1,099,000Kshs/year</li> <li>Calcium hypochlorite (Average dosing rate as effective chlorine 2ppm)<br/>240Kshs/kg×13.2kg/day×365 day = 1,099,000Kshs/year</li> </ul> | 10,614,000 | 2,891,000                 |
| Electricity   | Water Intake Facility         2,203kWh/day×365 day×24Kshs /kWh* = 19,298,000Kshs/year         Existing Central WTP         1,173kWh/day×365 day×24Kshs /kWh* = 10,275,000Kshs/year         New North WTP         257kWh/day×365 day×24Kshs /kWh* = 2,251,000Kshs/year         *Average unit cost per KWh calculated based on KPLC regulations   | 31,824,000 | 8,645,000                 |
| Sludge<br>Hauling/Disposal<br>Cost                                  | <ul> <li>Generated amount of dried sludge : 53 ton/30 days</li> <li>Dump truck (4 ton loading) : 53t / 4t = 13 units, 5,000Kshs/time</li> <li>5,000 Kshs/time×13 units×12 time/year= 780,000Kshs/year</li> </ul>  | 780,000    | -                         |
| Equipment Repair<br>Cost  | Providing 4% of mechanical/electrical equipment cost<br>235,000,000Kshs×0.04/year = 9,400,000Kshs/year  | 9,400,000  | 5,332,000                 |
| Office Expense,<br>Communication<br>Expenses and<br>Consumable Cost | Calculate on15% of total of abovementioned costs<br>73,258,000Kshs/year×0.15=11,000,000Kshs/year  | 11,000,000 | 6,332,000                 |
| Total   |   | 84,258,000 | 30,900,000                |

| Table 2-5-2 | Expected O&M | <b>Cost in Target Year</b> |
|-------------|--------------|----------------------------|
|-------------|--------------|----------------------------|

#### (2) Estimation of Water Tariff Income

The projected water tariff income in 2020 is shown below. Water tariff income is calculated as 49.6 million Kshs/year if applying the current water tariff.

① Water supply amount : 3,730m<sup>3</sup>/day (Effective amount out of design water supply amount 5,000m<sup>3</sup>/day)

- ② Served population : 49,980 persons
- ③ Served household number : 10,000HH (5 persons per HH) Estimated [High-middle income class 7,500HH, Low income class 2,500HH]
- ④ Breakdown of water consumption :
  - a. High middle income group 2,450m<sup>3</sup>/day (included shops and offices)

 $\Rightarrow$  per HH average consumption 9.8m<sup>3</sup>/month

 $(2,450m^{3}/day \times 30 days \div 7,500HH = 9.8m^{3}/month \cdot HH)$ 

- b. Low income group 500 m<sup>3</sup>/day
  - $\Rightarrow$  per HH average consumption 6 m<sup>3</sup>/month
  - $(500m^{3}/day \times 30 days \div 2,500 HH = 6.0m^{3}/month \cdot HH)$
- c. Boarding school, collage 780 m<sup>3</sup>/day
  - $\Rightarrow$  23,400m<sup>3</sup>/month (780m<sup>3</sup>/day× 30 days = 23,400m<sup>3</sup>/month)
- (5) Water tariff (applied current water tariff)
  - a. High middle income group : 390Kshs/month×7,500HH×12 months = 35,100,000 Kshs/year
  - b. Low income group : 200Kshs/month×2,500HH×12 months =6,000,000 Kshs/year
  - c. Boarding school, collage : 50Kshs/  $m^3 \times 23,400m^3$ /month×12 months = 14,040,000 Kshs/year

#### (3) Income and Expenditure Projection based on Water Tariff Income

**Table 2-5-3** shows a comparison of O&M cost and water tariff income in the future. If current water tariff is continuously applied, a deficit of 34.7 million Kshs/year is expected.

 Table 2-5-3
 Comparison between O&M Cost and Water Tariff Income

| Cost Item                   | O&M Cost            | Water Tariff Income | Balance             |
|-----------------------------|---------------------|---------------------|---------------------|
|                             | (Million Kshs/year) | (Million Kshs/year) | (Million Kshs/year) |
| Estimated Amount<br>at 2020 | 84.3                | 49.6                | ▲ 34.7              |

Since GoK will subsidize the project, there are no serious restrictions on the project's implementation. However, since expenditures shall be covered by income from water tariff in the future, tariff may need to be adjusted by around 70% (84.3/49.6=1.70).

If the 70% water tariff increase is then executed, the new water tariff becomes 660 Kshs/month for the high to middle income group and 340 Kshs/month for low-income group. According to the results of social survey, the average household income is 22,000 Kshs/month, thus new water tariff is well within 3 to 5% of the average income, which is affordable. Furthermore, the new water tariff is lower than the average willingness to pay amount of 1,050 Kshs/month. Coupled with increases in household incomes in the future, the proposed water tariff increase is judged to be feasible from viewpoint of affordability-to-pay and willingness-to-pay by the average household, and will be considered to cover the O&M cost for water supply facilities.

The implementation of the new water tariff increase in the future shall also necessitate the revision of water tariff discounts to the low income group which already utilizes government subsidy. The water tariff income shall have to be augmented by vigorously promoting new house connection and a strong metering program to improve the financial standing of the water authority. Soft component performed by this project will support O&M and water tariff.

#### (4) Facility Renewal and Equipment Replacement Period

According to durable period prescription using Kenyan design standards, the captioned period is set as follows:

- Structure : 50 years
- Pipeline : 50 years (Main) , 30 years (Branch)
- Mechanical and Electrical Equipment : 15 year

# <u>Chapter 3</u> Project Evaluation
# **Chapter 3 Project Evaluation**

# **3-1** Preconditions

The preconditions for project implementation are follows:

- (a) Secure the budget on the activities to be undertaken by the Kenyan side. Disbursements shall depend on the work schedule. The contents of the activities are construction of the fence, gate and access road for the water intake facility and the proposed North WTP, power transmission, installation of a part of distribution pipelines, water meters and house connections.
- (b) Progress on the land transaction authentication procedure application addressed to the Narok Town council to get official land transaction approval from Ministry of Land and National Land Authority.
- (c) Progress on the water right authentication procedure application addressed to WRMA to get official water right.
- (d) Get the necessary approval and license needed regarding the facility construction works in advance to avoid delays in project implementation schedule.
- (e) Get the approval of EIA from NEMA.

# **3-2** Necessary Inputs by Recipient Country

The followings are items to be undertaken by Kenyan side:

- (a) Organize the project team, allocate necessary personnel, and secure the required budget. This activity shall be performed during project implementation and after facility completion.
- (b) Establish project team during detailed design study to comprehend project contents and to master techniques.
- (c) Actively participate in the soft component and apply acquired techniques for proper project operation and O&M.
- (d) Until target year of 2020, install distribution pipe with length of 20km using the budget allocated from the Kenyan side.
- (e) Connect house connection pipe to distribution pipe (installed by Japanese side) and install water meter by using the materials produced by Japanese side.
- (f) Collect proper water tariff in a timely manner to sustain project operation.

## **3-3** Important Assumptions

 Important assumptions on project implementation is construction and reinforcement works for the water supply facility utilizing subsidy issued carrying out by NARWASSCO under supports from Water Service Trust Fund and RV-WSB. While the work scale of the subsidized project will not seriously affect the contents of this augmentation project, careful consideration shall be given to former.

### **3-4** Project Evaluation

#### 3-4-1 Relevance

The existing Central WTP capacity is inadequate to supply water to the growing population of the central area of Narok Town. It is also overloaded, thus treated water cannot be assured to match of the service area such as schools, hospitals, households and so on. This is aggravated by numerous leaks in the old pipelines. Furthermore, the town has pockets of unserved areas.

Since significant project benefits on water supply service in Narok Town is expected and this project broadly contributes to residents' BHN upgrading, project implementation through Japanese Grant Aid scheme is judged as appropriate for the following reasons:

- Narok Town is located very close to the world famous Masaimara National Park, therefore industry and tourism is expected to grow. It has also been nominated as one of 15 cities prioritized for water supply system development in Vision 2030.
- ii) In 2008, national road B3 was connected to Masaimara National Park. The construction of housing units has been rapidly on-going, with the attendant increase in population in the area.
- iii) Currently, there is not 24 hours water supply service, and water supply hours are uncertain.
- iv) Fetching of water is mainly performed by women and children, and has become a huge burden, since water service area is limited, even if there is water supplied by KIOSKs.
- v) The existing Central WTP produces water beyond its capacity, so the water quality of treated water is compromised.
- vi) Advancing Narok universities and some schools in Narok Town remarkably.
- vii) Since the existing Central WTP and reservoirs are still available, a full package water supply system is not required, thereby reducing and construction cost.
- viii) Since schools, hospitals and houses are concentrated in the centre of Narok Town, the

length of distribution pipelines for the project is reduced, leading to substantial savings.

- There is no foreseen technical problem because target water supply facilities are of the same type and same method with that applied in the local water supply system.
   Furthermore, procured materials and equipment are indispensable to achieve the target water service ratio.
- x) Only the cost needed for O&M is covered by water tariff income and thus, this project will not be a big burden to water consumers.
- xi) Minimum environmental impact is foreseen during construction works and system operation.
- xii) Smooth project implementation through Japanese Grant Aid scheme is feasible.

### 3-4-2 Effectiveness

The following quantitative and qualitative project effectiveness is anticipated:

#### (1) Quantitative Effectiveness

Quantitative project effectiveness indices are shown in Table 3-4-1.

| Indices           | At Present (2012)                       | Target Year (2020)       |
|-------------------|---|--------------------------|
| Served Population | 18,000 person *1)                       | 49,980 person            |
| Supply Amount     | 2,000m <sup>3</sup> /day <sup>*2)</sup> | 5,000m <sup>3</sup> /day |

 Table 3-4-1
 Quantitative Project Effectiveness

\*1): Current served population. But water supply is unstable and water service time is not regularly.

\*2): Current water supply amount. But water is treated beyond its design capacity, resulting to water quality that does not conform to standards

#### (2) Qualitative Effectiveness

The following qualitative project effectiveness as shown in **Table 3-4-2** is expected to Narok Town water supply service and residents.

| Table 3-4-2 | Qualitative Project Effectiveness |
|-------------|-----------------------------------|
|-------------|-----------------------------------|

| Current Status and Issues | Countermeasures to be<br>implemented by this Project | Project Effects |
|---------------------------|--|-----------------|
| A: Direct Effects         |  |                 |
| (1) Water supply capacity |  |                 |

|  | <i>a</i>  |  |
|--|---|--|
| Current Status and Issues  | Countermeasures to be implemented by this Project   | Project Effects  |
| • Water supply capacity is<br>extremely deficient compared<br>with water demand  | <ul> <li>Construction of the proposed<br/>North WTP</li> <li>Construction of the new clear<br/>water reservoir (2,000m<sup>3</sup>) within<br/>North WTP premises as clear<br/>water reservoir</li> <li>Installation of distribution pipe<br/>(80km)</li> </ul> | • Water amount equivalent to<br>water demand can be supplied<br>by distribution pipe<br>installation   |
| <ul> <li>(2) Stable water supply</li> <li>Currently, 24 hours water supply<br/>is not performed and water<br/>supply hours are uncertain</li> </ul>  | <ul> <li>Construction of new WTP with<br/>sufficient capacity</li> <li>Construction of reservoir and<br/>distribution pipe to system<br/>augmentation</li> </ul>  | <ul> <li>24 hours water supply is<br/>available.</li> </ul>  |
| <ul> <li>(3) Water quality</li> <li>Operation of the existing Central WTP in overloaded, treated water quality is below potable water standard</li> <li>Proper water quality control has not been practiced</li> </ul>   | <ul> <li>Construction of new WTP where adequate water treatment is possible</li> <li>Construct the chemical house and procure chemical dosage equipment for the existing Central WTP</li> <li>O&amp;M upgrading through Soft Component</li> </ul>               | <ul> <li>Supplied water quality is to be<br/>improved by construction of<br/>new WTP and repair/ and<br/>O&amp;M capacity upgrading of<br/>the existing Central WTP</li> </ul>                                 |
| <ul> <li>(4) NRW measure / water charge collection</li> <li>According to current water service, registered house connections number 2,131 but water charge is collected from only 1,175 which have negatively affected financial health of the water system.</li> <li>NRW rate is high. Improvement shall be required</li> </ul> | <ul> <li>Procurement of water meters<br/>and house connection pipes</li> <li>NRW rate is to be reduced by<br/>laying of new distribution pipes</li> </ul>   | <ul> <li>Increasing water income and<br/>amount</li> <li>NRW reduction, proper water<br/>charge billing/collection by<br/>water meter installation<br/>stabilize managerial status of<br/>NARWASSCO</li> </ul> |
| B: Indirect Effects  |   |  |
| <ul> <li>(1) Water-borne diseases</li> <li>Safe and sanitary potable water<br/>supply has not been secured or<br/>is insufficient and this causes<br/>high morbidity due to<br/>water-borne diseases</li> </ul>  | —   | <ul> <li>Stable supply of safe and<br/>sanitary potable water supply<br/>will contribute to the<br/>reduction of water-borne<br/>diseases morbidity, such as<br/>Diarrhea, Typhoid and<br/>Cholera</li> </ul>  |
| <ul> <li>(2) Water fetching labor</li> <li>Water fetching labor is mainly<br/>performed by women and<br/>children and this becomes a<br/>huge burden</li> </ul>  | —   | Water fetching labor will be<br>mitigated by house<br>connection   |

| Current Status and Issues  | Countermeasures to be<br>implemented by this Project | Project Effects  |
|--|--|--|
| <ul> <li>(3) Effect of global warming</li> <li>Intensity of rainfall<br/>fluctuation, drought might<br/>increase by climate change<br/>caused by global warming</li> </ul> | _  | <ul> <li>By completion of this<br/>project, safe and stable water<br/>supply is realized and social<br/>adaptability against climate<br/>change is improved</li> </ul> |