

**Ministry of Agriculture
Republic of Peru**

**THE PREPARATORY STUDY
ON
PROJECT OF THE PROTECTION OF
FLOOD PLAIN AND VULNERABLE RURAL
POPULATION AGAINST FLOOD IN THE
REPUBLIC OF PERU**

**FINAL REPORT
PRE-FEASIBILITY STUDY REPORT
II-6 PROJECT REPORT (YAUCA RIVER)
(TEMPORARY VERSION)**

March 2013

**JAPAN INTERNATIONAL COOPERATION AGENCY
(JICA)**

**YACHIYO ENGINEERING CO., LTD.
NIPPON KOEI CO., LTD.
NIPPON KOEI LATIN AMERICA –
CARIBBEAN Co., LTD.**

Composition of Final Report

I. Feasibility Study Report

I-1 Program Report

I-2 Project Report (Cañete River)

I-3 Project Report (Chincha River)

I-4 Project Report (Pisco River)

I-5 Project Report (Majes-Camana River)

I-6 Supporting Report

Annex – 1 Metrology /Hydrology /Run-off Analysis

Annex – 2 Inundation Analysis

Annex – 3 River Bed Fluctuation Analysis

Annex – 4 Flood Control Plan

Annex – 5 Forecasting and Warning System in Chira River

Annex – 6 Sediment Control

Annex – 7 Afforestation and Vegetation Recovery Plan

Annex – 8 Plan and Design of Facilities

Annex – 9 Construction Planning and Cost Estimate

Annex – 10 Socio-economy and Economic Evaluation

Annex – 11 Environmental and Social Considerations/ Gender

Annex – 12 Technical Assistance

Annex – 13 Stakeholders Meetings

Annex – 14 Implementation Program of Japanese Yen Loan Project

Annex – 15 Drawings

I-7 Data Book

II. Pre- Feasibility Study Report

II-1 Program Report

II-2 Project Report (Chira River)


II-3 Project Report (Cañete River)

II-4 Project Report (Chincha River)


II-5 Project Report (Pisco River)

II-6 Project Report (Yauca River) (This Report)

II-7 Project Report (Majes-Camana River)



Location Map



Abbreviation

| Abbreviation | Official Name or meaning |
|--------------|---|
| ANA | Water National Authority (Autoridad Nacional del Agua) |
| ALA | Water Local Authority (Autoridad Local del Agua) |
| C/B | Cost-Benefit relation (Cost-Benefit Ratio) |
| GDP | PBI (Producto Bruto Interno) (Gross Domestic Product) |
| GIS | Sistema de información geográfica (Geographic Information System) |
| DGAA | Dirección General de Asuntos Ambientales (Environmental Affairs General Direction) |
| DGFFS | Dirección General de Forestal y de Fauna Silvestre (Forestry and Fauna General Direction) |
| DGIH | Dirección General de Infraestructura Hidráulica (Hydraulic Infrastructure General Direction) |
| DGPM | Dirección General de Programación Multianual del Sector Público (Public Sector Multiannual Program General Direction) |
| DNEP | Dirección Nacional de Endeudamiento Público (Public Indebtedness National Direction) |
| DRA | Dirección Regional de Agricultura (Agriculture Regional Direction) |
| EIA | Estudio de impacto ambiental (Environmental Impact Assessment - EIA) |
| FAO | Organización de las Naciones Unidas para la Agricultura y la Alimentación (Food and Agriculture Organization of the United Nations) |
| F/S | Estudio de Factibilidad (Feasibility Study) |
| GORE | Gobiernos Regionales (Regional Governments) |
| HEC-HMS | Sistema de Modelado Hidrológico del Centro de Ingeniería Hidrológica (Hydrologic Model System from the Hydrology Engineer Center) |
| HEC-RAS | Sistema de Análisis de Ríos del Centro de Ingeniería Hidrológica (Hydrologic Engineering Centers River Analysis System) |
| IGN | Instituto Geográfico Nacional (National Geographic Institute) |
| IGV | Impuesto General a Ventas (TAX) |
| INDECI | Instituto Nacional de Defensa Civil (Civil defense National Institute) |
| INEI | Instituto Nacional de Estadística (Statistics National Institute) |
| INGEMMET | Instituto Nacional Geológico Minero Metalúrgico (Metallurgic Mining Geologic National Institute) |
| INRENA | Instituto Nacional de Recursos Naturales (Natural Resources National Institute) |
| IRR | Tasa Interna de Retorno (Internal Rate of Return - IRR) |
| JICA | Agencia de Cooperación Internacional del Japón (Japan International Cooperation Agency) |
| JNUDRP | Junta Nacional de Usuarios de los Distritos de Riego del Perú (Peruvian Irrigation District Users National Board) |
| L/A | Acuerdo de Préstamo (Loan Agreement) |
| MEF | Ministerio de Economía y Finanzas (Economy and Finance Ministry) |
| MINAG | Ministerio de Agricultura (Agriculture Ministry) |
| M/M | Minuta de Discusiones (Minutes of Meeting) |

| | |
|-------------|--|
| NPV | VAN (Valor Actual Neto) (NET PRESENT VALUE) |
| O&M | Operación y mantenimiento (Operation and maintenance) |
| OGA | Oficina General de Administración (Administration General Office) |
| ONERRN | Oficina Nacional de Evaluación de Recursos Naturales (Natural Resources Assessment National Office) |
| OPI | Oficina de Programación e Inversiones (Programming and Investment Office) |
| PE | Proyecto Especial Chira-Piura (Chira-Piura Special Project) |
| PES | PSA (Pago por Servicios ambientales) (Payment for Environmental Services) |
| PERFIL | Estudio del Perfil (Profile Study) |
| Pre F/S | Estudio de prefactibilidad (Pre-feasibility Study) |
| PERPEC | Programa de Encauzamiento de Ríos y protección de Estructura de Captación (River Channeling and Protection of Collection Structures Program) |
| PRONAMACHIS | Programa Nacional de Manejo de Cuencas Hidrográficas y Conservación de Suelos (Water Basins Management and Soil Conservation National Program) |
| PSI | Programa Sub Sectorial de irrigaciones (Sub-Sectorial Irrigation Program) |
| SCF | Factor de conversión estándar (Standard Conversion Factor) |
| SENAMHI | Servicio Nacional de Meteorología y Hidrología (Meteorology and Hydrology National Service) |
| SNIP | Sistema Nacional de Inversión Pública (Public Investment National System) |
| UF | Unidades Formuladoras (Formulator Units) |
| VALLE | Llanura aluvial, llanura de valle (Alluvial Plain, Valley Plain) |
| VAT | Impuesto al valor agregado (Value added tax) |

THE PREPARATORY STUDY
ON
PROJECT OF THE PROTECTION OF FLOOD PLAIN AND VULNERABLE RURAL
POPULATION AGAINST FLOODS IN THE REPUBLIC OF PERU
FINAL REPORT
PRE-FEASIBILITY STUDY REPORT
II-6 PROJECT REPORT
(YAUCA RIVER)
(TEMPORARY VERSION)

Table of Contents

Location Map

Abbreviation

| | |
|--|------------|
| 1. EXECUTIVE SUMMARY | 1-1 |
| 1.1 Project Name..... | 1-1 |
| 1.2 Project's Objective | 1-1 |
| 1.3 Supply and Demand Balance | 1-1 |
| 1.4 Structural Measures | 1-2 |
| 1.5 Non-structural measures | 1-4 |
| 1.6 Technical support | 1-5 |
| 1.7 Costs..... | 1-5 |
| 1.8 Social Assessment..... | 1-5 |
| 1.9 Sustainability Analysis..... | 1-7 |
| 1.10 Environmental Impact..... | 1-8 |
| 1.11 Execution plan | 1-10 |
| 1.12 Institutions and management | 1-10 |
| 1.13 Logical Framework..... | 1-11 |
| 1.14 Middle and Long Term Plans..... | 1-13 |

| | | |
|-----------|---|------------|
| 2. | GENERAL ASPECTS | 2-1 |
| 2.1 | Name of the Project | 2-1 |
| 2.2 | Formulator and Executor Units..... | 2-1 |
| 2.3 | Involved entities and Beneficiaries Participation..... | 2-1 |
| 2.4 | Framework | 2-4 |
| 3. | IDENTIFICATION..... | 3-1 |
| 3.1 | Diagnosis of the current situation | 3-1 |
| 3.2 | Definition of Problem and Causes | 3-44 |
| 3.3 | Objective of the Project | 3-47 |
| 4. | FORMULATION AND EVALUATION | 4-1 |
| 4.1 | Definition of the Assessment Horizon of the Project | 4-1 |
| 4.2 | Supply and Demand Analysis | 4-1 |
| 4.3 | Technical Planning..... | 4-4 |
| 4.4 | Costs..... | 4-23 |
| 4.5 | Social Assessment..... | 4-24 |
| 4.6 | Sensitivity Analysis..... | 4-32 |
| 4.7 | Sustainability Analysis..... | 4-34 |
| 4.8 | Environmental Impact..... | 4-35 |
| 4.9 | Execution Plan | 4-47 |
| 4.10 | Institutions and Administration | 4-50 |
| 4.11 | Logical framework of the eventually selected option | 4-54 |
| 4.12 | Middle and long term Plan..... | 4-56 |
| 5. | CONCLUSIONS | 5-1 |

1. EXECUTIVE SUMMARY

1.1 Project Name

“Protection program for valleys and rural communities vulnerable to floods Implementation of prevention measures to control overflows and floods of Yauca River, Arequipa Department.”

1.2 Project’s Objective

The ultimate impact that the project is design to achieve is to alleviate the vulnerability of valleys and the local community to flooding and boost local socioeconomic development.

1.3 Supply and Demand Balance

It has been calculated the theoretical water level in case of flow design flood based on the transversal lifting data of the river with an interval of 500m, in the Yauca river watershed, assuming a design flood flow equal to the flood flow with a return period of 50 years. Then, we determined the dike height as the sum of the design water level plus the dike’s free board.

This is the required height of the dike to control the damages caused by design floods and is the indicator of the demand of the local community.

The height of the existing dike or current terrain height is the required height to control the current flood damages, and is the indicator of the current offer.

The difference between the dike design height (demand) and the height of the dam or current field is the difference or gap between demand and supply.

Table 4.2-2 shows the average water levels floods, calculated with a return period of 50 years, of the required height of the dike (demand) to control the flow by adding the design water level plus the free board of the dike; from dike height or current ground (supply), and the difference between these two (difference between demand and supply) of the river. Then, in Table 1.3-1 the values at each point are shown. The current height of the dike or the current field is greater than the required height of the dike, at certain points. In these, the difference between supply and demand is considered null.

Table 1.3-1 Demand and supply analysis

| Watershed | Dike Height / current land (supply) | | Theoretical water level with a return period of 50 years | Dike Freeboard | Required dike's heigth (demand) | Diff. demand/supply | |
|-----------|--|------------|--|-------------------|---------------------------------------|---------------------|------------|
| | Left bank | Right bank | | | | Left bank | Right bank |
| | ① | ② | | | | ③ | ④ |
| Yauca | 187.54 | 183.01 | 179.03 | 0.80 | 179.83 | 0.21 | 0.40 |

1.4 Structural Measures

Structural measures are a subject that must be analyzed in the flood control plan covering the entire watershed. The analysis results are presented in section 4.12 “medium and long term plan” This plan proposes the construction of dikes for flood control throughout the watershed. However, the case of Yauca River requires a large project investing at a extremely high cost, far beyond the budget for this Project, which makes this proposal it impractical. Therefore, assuming that the dikes to control floods throughout the whole basin will be constructed progressively over a medium and long term period. Here is where this study focused on the most urgent works, priority for flood control.

(1) Design flood flow

The Methodological Guide for Protection Projects and / or Flood Control in Agricultural or Urban Areas prepared by the Public sector multi annual programming general direction (DGPM) of the Ministry of Economy and Finance (MEF) recommends a comparative analysis of different return periods: 25, 50 and 100 years for the urban area and 10, 25 and 50 years for rural and agricultural land.

Considering that the present project is aimed at protecting the rural and agricultural land, the design flood flow was determined in the set value for floods with a return period of 50 years in the mentioned Guide.

The maximum discharge observed in the past in Yauca river is considerably less than the flood discharge with return period of 50 years, and the same class of floods occurred three times in the past.

In Peru the flood protection works in the basins are developed almost nil, therefore it is not necessary to adopt the design discharge more than the past maximum discharge. However, the large disasters occurred in the past so that the design flood discharge with return period of 50 years, which is larger than the past maximum, is to be adopted as design flood as in safe side.

The relation among flood discharge with different return period, damage caused by the floods and inundation areas is analyzed in the basin. The results are that the more the return periods of flood increase the more inundation area and damage amount increase in the basin, however the increase tendency of damage with project is more gentle compared with former two items, and the reduction of damage with project reaches to maximum in the case of the flood with return period of 50 years within the cases of flood with less return period of 50 years.

As described above, the adopted design flood discharge with return period of 50 years is bigger than the past maximum discharge and damage reduction amount in the adopted case becomes more than that of the flood discharges with less return period. However the Project in Yauca river is to be cancelled due to low economic viability studied in the section 4.5 Social Evaluation

(2) Selection of prioritized flood control works

We applied the following five criteria for the selection of priority flood control works.

- Demand from the local community (based on historical flood damage)
- Lack of discharge capacity (including the sections affected by the excavation)
- Conditions of the adjacent area (conditions in urban areas, farmland, etc.).
- Flood conditions (extent of overflowed water according to the results of flood analysis)
- Social and environmental conditions (important local infrastructures)

Based on the river survey, field investigation, discharge capacity analysis of river channel, inundation analysis, and interviews to the local community (irrigation committee needs, local governments, historical flood damage, etc...) a comprehensive evaluation was made applying the five evaluation criteria listed above. After that we selected a total of six (6) critical points (with the highest score in the assessment) that require flood protection measures.

Concretely, since the river cross sectional survey was carried out every 500m interval and discharge capacity analysis and inundation analysis were performed based on the survey results, the integral assessment was also done for sections of 500 meters. This sections have been assessed in scales of 1 to 3 (0 point, 1 point and 2 points) and the sections of which score is more than 6 were selected as prioritized areas. The lowest limit (6 points) has been determined also taking into account the budget available for the Project in general

1.5 Non-structural measures

1.5.1 Reforestation and vegetation recovery

(1) Basic Policies

The reforestation plan and vegetation recovery that meets the objective of this project can be divided into: i) reforestation along river structures, and ii) reforestation in the upper watershed. The first has a direct effect on flood prevention expressing its impact in a short time, while the second one requires high cost and a long period for its implementation, as indicated later in the section 4.12 “Medium and long term Plan”, and also it is impractical to be implemented within the framework of this project. Therefore, this study focused on the first alternative.

(2) Regarding reforestation along river structures

This alternative proposes planting trees along the river structures, including dikes and bank protection works.

- Objective: Reduce the impact of flooding of the river when an unexpected flood or narrowing of the river by the presence of obstacles, using vegetation strips between the river and the elements to be protected.
- Methodology: Create vegetation stripes of a certain width between the river and river structures.
- Execution of works: Plant vegetation on a portion of the river structures (dikes, etc.).
- Maintenance after reforestation: Maintenance will be taken by irrigation committees under their own initiative.

The width, length and area of reforestation along river structures are 11m, 4.4km y 4.9ha respectively.

1.5.2 Sediment Control Plan

The sediment control plan must be analyzed within the general plan of the watershed. The results of the analysis are presented in section 4.12 “Medium and long term plan”. To sum up, the sediment control plan for the entire watershed requires a high investment cost, which goes far beyond the budget of this project, which makes it impractical to adopt.

Regarding sediment control of the lower watershed, the bed variation analysis has shown that

the volume of sediments that are entering and the bed variation volume are not so much so that the urgent sediment control actions are not required at present although the monitoring the riverbed variation and the maintenance of river channel depending on the monitoring results will be required.

1.6 Technical support

Based on the technical proposals of structural and nonstructural measures, it is also intends to incorporate in this project technical assistance to strengthen the measures.

The objective of the technical assistance is to “improve the capacity and technical level of the local community, to manage risk to reduce flood damage in selected valleys.”

Technical assistance will cover the Yauca river watershed.

Aiming to train characteristics of the watershed, courses for one will be prepared. The beneficiaries are the representatives of the committees and irrigation groups from each watershed, governments employees (provincial and district), local community representatives, local people etc.

Qualified as participants in the training, people with ability to replicate and disseminate lessons learned in the courses to other community members, through meetings of the organizations to which they belong.

In order to carry out the technical assistance goal, the three activities propose the following:

- Bank protection activity and knowledge enhancement on agriculture and natural environment
- Community disaster prevention planning for flood damages
- Watershed (slope) management against fluvial sedimentation

1.7 Costs

In the Table 1.7-1 the costs of this Project in Yauca watershed is shown. The cost of the watersheds is around 20.9 million soles.

Table 1.7-1 Project Cost

1.8 Social Assessment

(1) Benefits

The benefits of flood control are the reduction of losses caused by floods which would be achieved by the implementation of the project and is determined by the difference between the loss amount without project and with project. Specifically, to determine the benefits, first the

amount of losses by floods is calculated from different return periods (between 2 and 50 years), assuming that flood control works will last 50 years, and then the average annual reduction loss amount is determined from the reduction of losses from different return periods. In Tables 1.8-1 and 1.8-2 show the average annual amount of reduction loss that would be achieved by implementing this project, expressed in costs at private prices and costs at social prices.

Table 1.8-1 Annual average damage reduction amount (at private prices)

s/1000

| Watershed | 流量規模 Return Period | 超過確率 Probability | 被害額 (Total Damages - thousand S/.) | | | 区間平均被害 額 ④ Damages Average | 区間確率 ⑤ Probability Incremental value | 年平均被害額 ④×⑤ Damages Flow Average Value | 年平均被害額の 累計=年平均被 害軽減期待額 Annual Medial Damage |
|-----------|--------------------------|---------------------|------------------------------------|-------------------|-------------------------------|--|--|--|---|
| | | | 事業を実施し ない場合① | 事業を実施し た場合② | 軽減額 ③=①-② | | | | |
| | | | With Project ① | With Project ② | Mitigated damages ③=①-② | | | | |
| YAUCA | 1 | 1.000 | 0 | 0 | 0 | | 0 | 0 | |
| | 2 | 0.500 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | 5 | 0.200 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | 10 | 0.100 | 1,695 | 7 | 1,688 | 844 | 0.100 | 84 | 84 |
| | 25 | 0.040 | 2,569 | 1,005 | 1,564 | 1,626 | 0.060 | 98 | 182 |
| | 50 | 0.020 | 11,497 | 2,028 | 9,469 | 5,517 | 0.020 | 110 | 292 |

Table 1.8-2 Annual average damage reduction amount (at social prices)

s/1000

| Watershed | 流量規模 Return Period | 超過確率 Probability | 被害額 (Total Damages - thousand S/.) | | | 区間平均被害 額 ④ Damages Average | 区間確率 ⑤ Probability Incremental value | 年平均被害額 ④×⑤ Damages Flow Average Value | 年平均被害額の 累計=年平均被 害軽減期待額 Annual Medial Damage |
|-----------|--------------------------|---------------------|------------------------------------|-------------------|-------------------------------|--|--|--|---|
| | | | 事業を実施し ない場合① | 事業を実施し た場合② | 軽減額 ③=①-② | | | | |
| | | | With Project ① | With Project ② | Mitigated damages ③=①-② | | | | |
| YAUCA | 1 | 1.000 | 0 | 0 | 0 | | 0 | 0 | |
| | 2 | 0.500 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | 5 | 0.200 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | 10 | 0.100 | 2,150 | 9 | 2,141 | 1,071 | 0.100 | 107 | 107 |
| | 25 | 0.040 | 3,313 | 1,341 | 1,972 | 2,057 | 0.060 | 123 | 230 |
| | 50 | 0.020 | 12,092 | 2,653 | 9,439 | 5,706 | 0.020 | 114 | 345 |

(2) Social assessment results

The objective of the social assessment in this study is to evaluate the efficiency of investments in the structural measures using the method of cost-benefit relation (C/B) from the point of view of national economy. To do this, we determined the economic evaluation indicators (C/B relation, Net Present Value-NPV, and Internal return rate - IRR).

The benefits of the evaluation period were estimated, from the first 15 years since the start of the project. Because, from these 15 years, two are from the work execution period, the evaluation was conducted for the 13 years following the completion of works.

In Tables 1.8-3 and 1.8-4 the costs at private prices and at social prices resulting from this project assessment are shown. It is noted that the project will have extremely low economic effect.

Table 1.8-3 Social Assessment (private prices)

Table 1.8-4 Social Assessment (social prices)

Social assessment showed that the Yauca river watershed project will not give a palpable economic impact in social prices costs terms. Below are the positive effects of the Project that are difficult to quantify in economic values.

- ① Contribution to local economic development to alleviate the fear to economic activities suspension and damages
- ② Contribution to increase local employment opportunities thanks to the local construction project
- ③ Strengthening the awareness of local people regarding damages from floods and other disasters
- ④ Contribution to increase from stable agricultural production income, relieving flood damage
- ⑤ Rise in farmland prices

From the results of the economic evaluation presented above, it is difficult to implement this Project, even if there is the positive effects of the Project that are difficult to quantify in economic values.

1.9 Sustainability Analysis

This project will be co-managed by the central government (through the DGIH), irrigation committees and regional governments, and the project cost will be covered with the respective contributions of the three parties. Usually the central government (in this case, the DGIH) assumes 80%, the irrigation commissions 10% and regional governments 10%. However, the percentages of the contributions of these last two are decided through discussions between both parties. On the other hand, the operation and maintenance (O & M) of completed works is taken by the irrigation committees. Therefore, the sustainability of the project is depends on the profitability of the project and the ability of O & M of irrigation committees.

In Table 1.9-1 data of the irrigation commission's budget of the Yauca River in the last years is shown.

Table 1.9-1 Irrigation commission Project's Budget

| River | Annual Budget | | | (In soles) |
|-------|---------------|------------|------------|----------------|
| | 2006 | 2007 | 2008 | 3 year average |
| Yauca | 114,482.12 | 111,102.69 | 130,575.40 | 118,720 |

(1) Profitability

We have seen that Yauca river watershed is not sufficiently profitable, so it is not viable. The amount of investment required is estimated at million soles (cost at private prices), the C/B relation is 0.13, IRR = null and NPV = S/. – 13.0 millions. These figures are showing the economic low efficiency of the project.

(2) Operation and maintenance costs

The annual cost of operation and maintenance required for the project, having as base year 2008 is estimated at soles, which corresponds to % of the construction cost of the project in the Yauca river watershed. On the other hand, the operating expenses average in the last four years of irrigation committees is 118,720.

When considering that the annual cost of operation and maintenance represents 75.9% of the annual irrigation budget, the project would not be sustainable because of the financial capacity of these committees to maintain and operate the constructed works.

As conclusion, the project is economically less effective; also, it is hardly that irrigation commissions may pay maintenance costs. So, this project is almost not viable.

1.10 Environmental Impact

(1) Procedure of Environmental Impact Assessment

Projects are categorized in three scales, based on the significance level of the negative and positive impacts, and each sector has an independent competence on this categorization. The Project holder should submit the Environmental Impact Statement (DIA, in Spanish) for all Projects under Category I. The project holder should prepare an EIA-sd or an EIA-d if the Project is categorized under Category II or III, respectively, to be granted the Environmental Certification from the relevant Ministry Directorate.

First, the Project holder applies for the Project classification, by submitting the Preliminary Environmental Assessment (PEA). The relevant sector assesses and categorizes the Project.

The Project's PEA that is categorized under Category I becomes an EID, and those Projects categorized under Category II or III should prepare an EIA-sd or EIA-d, as applicable.

The preliminary environmental assessment (EAP) for Yauca river was carried out between December 2010 and January 2011 and by a consulting firm registered in the Ministry of Agriculture (CIDES Ingenieros S.A.). EAP for Yauca was submitted to DGIH January 25, 2011 by JICA Study Team and from DGIH to DGAA July 19, 2011.

DGAA examined EAP and issued approval letter of Category I. Therefore, no further environmental impact assessment is required for Yauca river.

(2) Results of Environmental Impact Assessment

The procedures to review and evaluate the impact of the natural and social environment of the Project are the following. First, we reviewed the implementation schedule of the construction of river structures, and proceeded to develop the Leopold matrix.

The impact at environmental level (natural, biological and social environment) was evaluated and at Project level (construction and maintenance stage). The quantitative levels were determined by quantifying the environmental impact in terms of impact to nature, manifestation possibility, magnitude (intensity, reach, duration and reversibility).

The EAP showed that the environmental impact would be manifested by the implementation of this project in the construction and maintenance stages, mostly, it is not very noticeable, and if it were, it can be prevented or mitigated by appropriately implementing the management plan environmental impact.

On the other hand, the positive impact is very noticeable in the maintenance stage, which manifests at socioeconomic and environmental level, specifically, in greater security and reduced vulnerability, improved life quality and land use.

1.11 Execution plan

Table 1.11-1 presents the Project execution plan.

Table 1.11-1 Execution plan

| ITEMS | 2010 | | | 2011 | | | 2012 | | | 2013 | | | 2014 | | | 2015 | | | 2016 | | | | |
|--|-------|-------|---|------|------------|------------|------|--------------------------|---|------|------------------|----|------|---|---|------|---|---|------|----|---|---|---|
| | 3 | 6 | 9 | 12 | 3 | 6 | 9 | 12 | 3 | 6 | 9 | 12 | 3 | 6 | 9 | 12 | 3 | 6 | 9 | 12 | 3 | 6 | 9 |
| 1 PROFILE STUDY / SNIP ASSESSMENT | STUDY | | | | EVALUATION | | | | | | | | | | | | | | | | | | |
| 2 FEASIBILITY STUDY / SNIP ASSESSMENT | | STUDY | | | | EVALUATION | | | | | | | | | | | | | | | | | |
| 3 YEN CREDIT NEGOTIATION | | | | | | | | | | | | | | | | | | | | | | | |
| 4 CONSULTANT SELECTION | | | | | | | | | | | | | | | | | | | | | | | |
| 5 CONSULTANT SERVICE (DETAILED DESIGN, LAWFUL DOCUMENTS PREPARATION) | | | | | | | | DESIGN / LAWFUL DOCUMENT | | | WORK SUPERVISION | | | | | | | | | | | | |
| 6 BUILDER SELECTION | | | | | | | | | | | | | | | | | | | | | | | |
| 7 WORK EXECUTION | | | | | | | | | | | | | | | | | | | | | | | |
| 1) STRUCTURES BUILDING | | | | | | | | | | | | | | | | | | | | | | | |
| 2) REFORESTATION | | | | | | | | | | | | | | | | | | | | | | | |
| 3) EARLY ALERT SYSTEM | | | | | | | | | | | | | | | | | | | | | | | |
| 4) DISASTER PREVENTIVE TRAINING | | | | | | | | | | | | | | | | | | | | | | | |
| 8 FINISH WORK / DELIVERY TO USERS BOARDS | | | | | | | | | | | | | | | | | | | | | | | |

1.12 Institutions and management

The institutions and its administration in the investment stage and in the operation and maintenance stage after the investment, shown in the figures 1.12-1 and 1.12-2.




Figure 1.12-1 Institutions related to the Project (investment stage)




Figure 1.12-2 Institutions related to the project (operation and maintenance stage)

1.13 Logical Framework

Table 1.13-1 presents the logical framework of the final selected alternative.

Table 1.13-1 Logical framework of the final selected alternative

| Narrative Summary | Verifying Indicators | Verifying Indicators Media | Preliminary Conditions |
|--|---|--|--|
| Superior Goal | | | |
| Promote socioeconomic local development and contribute in communities' social welfare. | Improve local productivity, generate more jobs, increase population's income and reduce poverty index | Published statistic data | Scio-economic and policy stability |
| Objectives | | | |
| Relief the high vulnerability of valleys and local continuity to floods | Types, quantity and distribution of flood control works, population and beneficiaries areas | Monitoring annual calendar works and financial plan, budget execution control | Ensure the necessary budget, active intervention from central and regional governments, municipalities, irrigation communities, local population, etc. |
| Expected results | | | |
| Reduction of areas and flooded areas, functional improvement of intakes, road destruction prevention, irrigation channels protection, bank erosion control and Poechos dike safety | Number of areas and flooded areas, water intake flow variation, road destruction frequency, bank erosion progress and watershed's downstream erosion. | Site visits, review of the flood control plan and flood control works reports and periodic monitoring of local inhabitants | Maintenance monitoring by regional governments, municipalities and local community, provide timely information to the superior organisms |
| Activities | | | |
| Component A: Structural Measures | Dikes rehabilitation, intake and bank protection works, road damages prevention, construction of 28 works, including dike's safety | Detailed design review, works reports, executed expenses | Ensure the works budget, detailed design/works execution/good quality works supervision |
| Component B: Non-Structural Measures | | | |
| B-1 Reforestation and vegetation recovery | Reforested area, coastal forest area | Works advance reports, periodic monitor by local community | Consultants support, NGO's, local community, gathering and cooperation of lower watershed community |
| Component C: Disaster prevention and capabilities development education | Number of seminars, trainings, workshops, etc | Progress reports, local governments and community monitoring | Predisposition of the parties to participate, consultants and NGO's assessments |
| Project's execution management | | | |

| | | | |
|----------------------|---|--|---|
| Project's management | Detailed design, work start order, work operation and maintenance supervision | Design plans, work's execution plans, costs estimation, works specifications, works management reports and maintenance manuals | High level consultants and contractors selection, beneficiaries population participation in operation and maintenance |
|----------------------|---|--|---|

1.14 Middle and Long Term Plans

While it is true that due to the limited budget available for the Project, this study is focused mainly on the flood control measures analysis that must be implemented urgently. It is considered necessary to timely implement other necessary measures within a long term. In this section we will discuss the medium and long term plans.

(1) Flood Control General Plan

There are several ways to control floods in the entire watershed, for example, the building of dams, retarding basin, dikes or a combination of these. The options to build dams or retarding basin are not viable because in order to answer to a flood flow with a return period of 50 years, enormous works would be necessary to be built. So, the study was focused here on dikes' construction because it was the most viable option.

Flood water level was calculated in the watershed adopting a designed flood flow with a return period of 50 years. At this water level, freeboard was added in order to determine the required dikes height. After, sections of the rivers where the dikes or ground did not reach the required height were identified. These sections, altogether, add up to approx.3km. Also, from maintaining these works, annually a dragged of the rivers has to be done in the sections where, according to the bed fluctuation analysis the sediment gathering is elevating the bed's height. The volume of sediments that shall be eliminated annually was determined in approximately 1,200 m³.

In Tables 1.14-1 and 1.14-2 the flood control general plan project cost is shown as well as the social assessment results in terms of private and social costs.

Table 1.14-1 Social Assessment (private prices)

| 流域名 | 年平均被害軽減額 Annual Average Damage Reduction | 評価期間被害 軽減額(15年) Damage Reduction in Evaluation Period(15years) | 事業費 Project Cost | 維持管理費 O&M Cost | B/C Cost Benefit Ration | NPV Net Present Value | IRR(%) Internal Return of Rate |
|-------|--|--|---------------------|-------------------|-------------------------------|-----------------------------|--------------------------------------|
| Yauca | 4,592,758 | 2,073,999 | 9,920,549 | 894,671 | 0.23 | -7,014,101 | - |

Table 1.14-2 Social Assessment (prices costs)

| 流域名 | 年平均被害軽減額 Annual Average Damage Reduction | 評価期間被害 軽減額(15年) Damage Reduction in Evaluation Period(15years) | 事業費 Project Cost | 維持管理費 O&M Cost | B/C Cost Benefit Ration | NPV Net Present Value | IRR(%) Internal Return of Rate |
|-------|--|--|---------------------|-------------------|-------------------------------|-----------------------------|--------------------------------------|
| Yauca | 5,531,228 | 2,497,793 | 7,976,121 | 719,315 | 0.34 | -4,809,039 | - |

In case of executing flood control works in the watershed, the works is not economically viable at both private price and social price, and the Projects' cost would elevate to 9.9 million soles, which is a huge amount for this project, so that this project could not be implemented.

(2) Reforestation Plan and Vegetation Recovery

The forestry option was analyzed, in a long term basis, to cover every area that requires being covered with vegetation in the upper watershed. The objective is improving this areas' infiltration capacity, reduce of surface water and increase semi-underground and underground water. So, the flood maximum flow will be decreased, also it could be possible to increase the water reserve in the mountain areas and prevent and soothe floods. The areas to be reforested will be the afforested areas or where the forest mass in the water infiltration areas has been lost.

In Table 1.14-3 the area to be afforested and the project's cost for the watershed is shown. These were calculated based on forestry plan of Chincha River. The total surface would be approximately 68,000hectares and in order to forest them the required time would be from 22 years and 184.3 million soles. To sum up, the Project has to cover an extensive area, with an investment of much time and at a high cost.

Table 1.14-3 General Plan for forestry on upper stream watersheds

| Watershed | Forestry Area (ha) A | Required Period for the project (years) B | Required Budget (soles) C |
|-----------|-------------------------|--|---------------------------------|
| Yauca | 68.296 | 22 | 184.340,033 |

(3) Sediment Control Plan

As long term sediment control plan, it is recommended to perform necessary works on the upper watershed. These works will mainly consist of dams and bank protection. In Table 1.14-4 the estimate work cost is shown. There are two costs, one for executing works in the entire watershed and another one for executing works only in prioritized areas.

All the chosen watersheds for this Project are big. So, if bank protection works and sediment control dams want to be built, not only the works' cost would elevate but also a very long period of investment would have to be done in the watershed. This means that its positive impact will be seen

in a long time.

Table 1.14-4 Projects Costs of Sediment Control

| Watersheds | Areas | Margin Protection | | Bands | | Dams | | Works direct cost (total) | Project Cost (in millions de s/.) |
|------------|-------------------|-------------------|----------------------------------|-----------|----------------------------------|-----------|----------------------------------|---------------------------|-----------------------------------|
| | | Qty. (km) | Works direct costs (million s/.) | Qty. (km) | Works direct costs (million s/.) | Qty. (km) | Works direct costs (million s/.) | | |
| Yauca | Totally | 565 | S/.604 | 57 | S/.2 | 97 | S/.144 | S/.750 | S/.1,412 |
| | Prioritized areas | 565 | S/.604 | 57 | S/.2 | 37 | S/.54 | S/.660 | S/.1,242 |

2. GENERAL ASPECTS

2.1 Name of the Project

“Protection program for valleys and rural communities vulnerable to floods Implementation of prevention measures to control overflows and floods of Yauca River, Arequipa Department”

2.2 Formulator and Executor Units

(1) Formulator Unit

Name: Hydraulic Infrastructure General Direction, Agriculture Ministry

Responsible: Orlando Chirinos Hernan Trujillo

General Director of the Water Infrastructure General Direction

Address: Av. Benavides N° 395 Miraflores, Lima 12 - Peru

Phone: (511) 4455457 / 6148154

Email: ochirinos@minag.gob.pe

(2) Executor Unit

Name: Sub-sectorial Irrigation Program, Agriculture Ministry

Manager: Jorge Zúñiga Morgan

Executive Director

Address: Jr. Emilio Fernandez N° 130 Santa Beatriz, Lima-Peru

Phone: (511) 4244488

Email: postmast@psi.gob.pe

2.3 Involved entities and Beneficiaries Participation

Here are the institutions and entities involved in this project, as well as beneficiaries.

(1) Agriculture Ministry (MINAG)

MINAG, as manager of natural resources of watersheds promotes agricultural development in each of them and is responsible of maintaining the economical, social and environmental to benefit agricultural development.

To accomplish effectively and efficiently this objective, the MINAG has been working since 1999 in the River Channeling and Collection Structures Protection Program (PERPEC). The river disaster prevention programs that are been carried out by regional governments are funded with PERPEC resources.

1) Administration Office (OA)

- Manages and executes the program's budget

- Establishes the preparation of management guides and financial affairs
- 2) Hydraulic Infrastructure general Direction (DGIH)
 - Performs the study, control and implementation of the investment program
 - Develops general guidelines of the program together with OPI
- 3) Planning and Investment Office (OPI)
 - Conducts the preliminary assessment of the investment program
 - Assumes the program's management and the execution of the program's budget
 - Plans the preparation of management guides and financial affairs
- 4) Irrigation Sub-Sectorial Program (PSI)
 - Carries-out the investment program approved by OPI and DGPM

(2) Economy and Finance Ministry (MEF)

Public Sector's Multiannual Programming General Direction (DGPM)

Is in charge of approving public investment works according to procedures under the Public Investment National System (SNIP) to assess the relevance and feasibility of processing the disbursement request of the national budget and the loan from JICA.

(3) Japan's International Cooperation Agency (JICA)

It is a Japanese government institution with the objective of contributing in the socioeconomic development of developing countries through international cooperation. JICA has extended financial assistance to carry out pre-feasibility and feasibility studies of this Project.

(4) Regional Governments (GORE)

Regional governments assume the promotion of integrated and sustainable regional development following the national and regional plans and programs, trying to increase public and private investment, generating employment opportunities, protecting citizens rights and ensuring equal opportunities.

The regional governments' participation with their possible financial support is a very important factor to ensure the Project's sustainability.

The Special Project Chira-Piura, Regional Government of Piura implemented by the regional government of Piura also includes Chira River which is the area of this Study.

(5) Irrigation Commission

Currently there are 3 irrigation commissions in the Yauca River Watershed. These have expressed a strong desire for the starting of works because these will help constructing dikes, protecting margins, repairing water intakes, etc. These commissions are currently suffering major damages due to rivers flooding. Next, a brief overview of the Yauca River Watershed is described (for more details, see Section 3.1.3). Currently, the operation and maintenance of dikes, margin protection works,

irrigation intakes and channels linked to agricultural land and irrigation systems in the Watershed, are mainly made by irrigation commissions and their members, with the assistance of local governments.

| | |
|-----------------------------------|-----------------|
| Number of irrigation blocks: | 3 |
| Number of Irrigation Commissions: | 3 |
| Irrigated Area: | 1, 614 ha |
| Beneficiaries: | 557 productores |

(6) Meteorology and Hydrology National Service (SENAMHI)

It is an agency from the Environment Ministry responsible for all activities related to meteorology, hydrology, environment and agricultural meteorology. Take part in global level monitoring, contributing to sustainable development, security and national welfare, and gathering information and data from meteorological stations and hydrological observation.

(7) Civil Defense National Institute (INDECI)

INDECI is the main agency and coordinator of the Civil Defense National System. It is responsible for organizing and coordinating the community, elaborating plans and developing disaster risk's management processes. Its objective is to prevent or alleviate human life loss due to natural and human disasters and prevent destruction of property and the environment.

(8) Water National Authority (ANA)

It is the highest technical regulating authority in charge of promoting, monitoring and controlling politics, plans, programs and regulations regarding sustainable use of water resources nationwide.

Its functions include sustainable management of these resources, as well as improving the technical and legal framework on monitoring and assessment of water supply operations in each region.

Along with maintaining and promoting a sustainable use of water resources, it is also responsible for conducting the necessary studies and developing main maintenance plans, national and international economic and technical cooperation programs.

(9) Agriculture Regional Directorates (DRA's)

Agricultural regional addresses fulfill the following functions under the respective regional government:

- 1) Develop, approve, assess, implement, control and manage national agriculture policies, sectorial plans as well as regional plans and policies proposed by municipalities
- 2) Control agriculture activities and services fitting them to related policies and regulations, as well as on the regional potential
- 3) Participate in the sustainable management of water resources agreeing with the watershed's general framework, as well as the policies of the Water National Authority (ANA)
- 4) Promote the restructure of areas, market development, export and agricultural and agro-industrial products consumption
- 5) Promote the management of: irrigation, construction and irrigation repair programs, as well as the proper management and water resources and soil conservation

2.4 Framework

2.4.1 Background

(1) Study Background

The Republic of Peru (hereinafter “Peru”) is a country with high risk of natural disasters such as earthquakes, Tsunamis, etc. Among these natural disasters there are also floods. In particular, El Niño takes place with an interval of several years and has caused major flood of rivers and landslides in different parts of the country. The most serious disaster in recent years due to El Niño occurred in the rainy season of 1982-1983 and 1997-1998. In particular, the period of 1997-1998, the floods, landslides, among others left loss of 3,500 million of dollars nationwide. The latest floods in late January 2010, nearby Machupicchu World Heritage Site, due to heavy rains interrupted railway and roads traffic, leaving almost 2,000 people isolated.

In this context, the central government has implemented El Niño phenomenon I and II contingency plans in 1997-1998, throughout the Agriculture and Livestock Ministry (MINAG) in order to rebuild water infrastructures devastated by this phenomenon. Next, the Hydraulic Infrastructure General Direction (DGIH) of the Agriculture Ministry (MINAG) began in 1999 the River Channeling and Collection Structures Protection Program (PERPEC) in order to protect villages, farmlands, agricultural infrastructure, etc located within flood risk areas. The program consisted of financial support for regional government to carry out works of margin protection. In the multiyear PERPEC plan between 2007-2009 it had been intended to execute a total of 206 margin protection works nationwide. These projects were designed to withstand floods with a return period of 50 years, but all the works have been small and punctual, without giving a full and integral solution to control floods. So, every time floods occur in different places, damages are still happening.

MINAG developed a “Valley and Rural Populations Vulnerable to Floods Protection Project” for nine watersheds of the five regions. However, due to the limited availability of experiences, technical and

financial resources to implement a pre-investment study for a flood control project of such magnitude, MINAG requested JICA's help to implement this study. In response to this request, JICA and MINAG held discussions under the premise of implementing it in the preparatory study scheme to formulate a loan draft from AOD of JICA, about the content and scope of the study, the implementation's schedule, obligations and commitments of both parties, etc. expressing the conclusions in the Discussions Minutes (hereinafter "M/D") that were signed on January 21 and April 16, 2010. This study was implemented on this M/D.

(2) Progress of Study

The Profile Study Report for this Project at Program's level for nine watersheds of five regions has been elaborated by DGIH and sent to the Planning and Investment Office (OPI) on December 23, 2009, and approved on the 30th of the same month. Afterwards, DGIH presented the report to the Public Sector Multiannual Programming General Direction (DGPM) of the Economy and Finance Ministry (MEF) on January 18, 2010. On March 19th, DGPM informed DGIH about the results of the review and the correspondent comments.

The JICA Study Team began the study in Peru on September 5th, 2010. At the beginning, nine watersheds were going to be included in the study. One, the Ica River was excluded of the Peruvian proposal leaving eight watersheds. The eight watersheds were divided into two groups: Group A with five watersheds and Group B with three watersheds. The study for the first group was assigned to JICA and the second to DGIH. Group A includes Chira, Cañete, Chincha, Pisco and Yauca Rivers' Watersheds and Group B includes the Cumbaza, Majes and Camana Rivers' Watersheds.

The JICA Study Team conducted the profile study of the five watersheds of Group A, with an accurate pre-feasibility level and handed DGIH the Program Report of group A and the reports of the five watershed projects by late June 2011. Also, the feasibility study has already started, omitting the pre-feasibility study.

For the watersheds of Group B which study corresponded to DGIH, this profile study took place between mid-February and early March 2011 (and not with a pre-feasibility level, as established in the Meetings Minutes), where Cumbaza River Watershed was excluded because it was evident that it would not have an economic effect. The report on the Majes and Camana rivers watersheds were delivered to OPI, and OPI official comments were received through DGIH on April 26th, indicating that the performed study for these two watersheds did not meet the accuracy level required and it was necessary to study them again. Also, it was indicated to perform a single study for both rivers because they belong to a single watershed (Majes-Camana).

On the other hand, due to the austerity policy announced on March 31st, prior to the new government assumption by new president on July 28th, it has been noted that it is extremely difficult to obtain new budget, DGIH has requested JICA on May 6th to perform the prefeasibility and feasibility studies of the Majes-Camana Watershed.

JICA accepted this request and decided to perform the mentioned watershed study modifying for the second time the Meeting Minutes (refer to Meetings Minutes Second Amendment about the Initial Report, Lima, July 22nd, 2011)

So, the JICA Study Team began in August the prefeasibility study for the watershed above mentioned, which was completed in late November.

This report corresponds with the pre-feasibility study of the Yauca watershed project, of a five watershed Group A. The feasibility study of Majes - Camana watershed wants to be finished by mid-January 2012, and the feasibility study for all selected watersheds around the same dates.

Remember that DGIH processed on July 21st, the SNIP registration of four of the five watersheds from JICA (except Yauca), based on projects reports at pre-feasibility level (according to the watersheds). DHIG decided to discard Yauca River due to its low impact in economy.

2.4.2 Laws, regulations, policies and guidelines related to the Program

This program has been elaborated following the mentioned laws and regulations, policies and guidelines:

(1) Water Resources Law N° 29338

Article 75 .- Protection of water

The National Authority, in view of the Watershed Council, must ensure for the protection of water, including conservation and protection of their sources, ecosystems and natural assets related to it in the regulation framework and other laws applicable. For this purpose, coordination with relevant government institutions and different users must be done.

The National Authority, throughout the proper Watershed Council, executes supervision and control functions in order to prevent and fight the effects of pollution in the oceans, rivers and lakes. It can also coordinate for that purpose with public administration, regional governments and local governments sectors.

The State recognizes as environmentally vulnerable areas the headwater watersheds where the waters originate. The National Authority, with the opinion of the Environment Ministry, may declare protected areas the ones not granted by any right of use, disposition or water dumping.

Article 119 .- Programs flood control and flood disasters

The National Authority, together with respective Watershed Board, promotes integral programs for flood control, natural or manmade disasters and prevention of flood damages or other water impacts and its related assets. This promotes the coordination of structural, institutional and necessary operational measures.

Within the water planning, the development of infrastructure projects for multi-sectorial advantage is promoted. This is considered as flood control, flood protection and other preventive measures.

(2) Water Resources Law Regulation N° 29338

Article 118 .- From the maintenance programs of the marginal strip

The Water Administrative Authority, in coordination with the Agriculture Ministry , regional governments, local governments and water user organizations will promote the development of programs and projects of marginal strips forestry protection from water erosive action.

Article 259 ° .- Obligation to defend margins

All users have as duty to defend river margins against natural phenomenon effects, throughout all areas that can be influenced by an intake, whether it is located on owned land or third parties' land. For this matter, the correspondent projects will be submitted to be reviewed and approved by the Water National Authority.

(3) Water Regulation

Article 49. Preventive measures investments for crop protection are less than the recovery and rehabilitation cost measures. It is important to give higher priority to these protective measures which are more economic and beneficial for the country, and also contribute to public expenses savings.

Article 50. In case the cost of dikes and irrigation channels protection measures is in charge of family production units or it exceeds the payment capacity of users, the Government may pay part of this cost.

(4) Multi-Annual Sectorial Strategic Plan of the Agriculture Ministry for the period 2007-2011 (RM N° 0821-2008-AG)

Promotes the construction and repair of irrigation infrastructure works with the premise of having enough water resources and their proper use.

(5) Organic Law of the Agriculture Ministry, N° 26821

In Article 3, it is stipulated that the agricultural sector is responsible for executing river works and agricultural water management. This means that river works and water management for agricultural purposes shall be paid by the sector.

(6) Guidelines for Peruvian Agricultural Policy - 2002, by the Policy Office of MINAG

Title 10 - Sectorial Policies

“Agriculture is a high risk productive activity due to its vulnerability to climate events, which can be anticipated and mitigated... The damage cost to infrastructure, crops and livestock can be an obstacle for the development of agriculture, and as consequence, in the deterioration of local, regional and national levels.”

(7) River Channeling and Collection Structures Protection Program, PERPEC

The MINAG's DGIH started in 1999 the River Channeling and Collection Structures Protection Program (PERPEC) in order to protect communities, agricultural lands and facilities and other elements of the region from floods damages, extending financial support to margin protection works carried out by regional governments.

3. IDENTIFICATION

3.1 Diagnosis of the current situation

3.1.1 Nature

(1) Location

Figure 3.1.1-1 shows the location map of the Yauca River.



Figure 3.1.1-1 Objective River for the Study

(2) Watershed overall description

The Yauca River runs 460km to the south of the Capital of Lima and it is the river closer to the south within the five rivers chosen in this city. It belongs to the Arequipa Region. Its area covers 4.300 km². It's characterized because its width increases as getting closer to the upper watershed. Altitudes above 4.000 mosl only represent a 10% of the total and 60% is constituted by 2000 and 4000 mosl altitudes. In its lower watershed, is where the river has a slope approximately of 1/100 with a 200 meters width.

Annual rainfalls are approximately 500mm at altitudes between 2000 and 3000 mosl. But this data is not well confirmed because there is no complete monitoring of the details. The middle flow is the most reduced among the 5 rivers, due to which we are deducing that precipitations themselves are pretty low.

As to vegetation, upper watersheds are covered with grassland, bushes in the middle watershed and deserts in the middle and lower watersheds. Agriculture lands are only 1% of the watershed. The main product is olive, which production occupies almost the entire agricultural lands in this area .

3.1.2 Socio-economic conditions of the Study Area

(1) Administrative Division and Surface

The Yauca River is located in the provinces of Caraveli in the Arequipa Region.

Table 3.1.2-1 shows the main districts surrounding this river, with their corresponding surface.

Table 3.1.2-1 Districts surrounding the Yauca River with areas

| Region | Province | District | Area (km ²) |
|----------|----------|----------|-------------------------|
| Arequipa | Caravelí | Yauca | 556.30 |
| | | Jaquí | 424.73 |

(2) Population and number of households

The following Table 3.1.2-2 shows how population varied within the period 1993-2007. From 1,708 inhabitants in 2007, 84% (2,844 inhabitants) lived in urban areas while 16% (549 inhabitants) lived in rural areas.

Yauca population has not varied. However, a reduction of rural population is observed. In Jaqui district, both populations, rural and urban, have decreased.

Table 3.1.2-2 Variation of the urban and rural population

| District | Total Population 2007 | | | | | Total Population 1993 | | | | | Variation (%) | |
|--------------|-----------------------|-------------|------------|-------------|--------------|-----------------------|-------------|------------|-------------|--------------|---------------|---------------|
| | Urban | % | Rural | % | Total | Urban | % | Rural | % | Total | Urban | Rural |
| Yauca | 1.442 | 84 % | 266 | 16 % | 1.708 | 1.370 | 81 % | 321 | 19 % | 1.691 | 0,4 % | -1,3 % |
| Jaqui | 1.402 | 83 % | 283 | 17 % | 1.685 | 2.016 | 81 % | 482 | 19 % | 2.498 | -2,6 % | -3,7 % |
| Total | 2.844 | 84 % | 549 | 16 % | 3.393 | 3.386 | 81 % | 803 | 19 % | 4.189 | -1,2 % | -2,7 % |

Source: Prepared by JICA Study Team, Statistics National Institute- INEI, 2007 and 1993 Population and Housing Census.

Table 3.1.2-3 shows the number of households and members per home. The number of members per household has been 3.5 in average in Yauca and 3.7 in Jaqui. The number of members per family in Yauca is 3.4 and 3.5 in Jaqui.

Table 3.1.2-3 Number of households and families

| Variables | Distrito | |
|-------------------------------------|----------|-------|
| | Yauca | Jaqui |
| Population (inhabitants) | 1,708 | 1,685 |
| Number of households | 492 | 461 |
| Number of families | 499 | 483 |
| Members per household (person/home) | 3.47 | 3.66 |
| Members per family (person/family) | 3.42 | 3.49 |

(3) Occupation

Table 3.1.2-4, shows occupation lists of local inhabitants itemized by sector. In Yauca, primary sector is 39% of labor; meanwhile tertiary sector is 51%, being the second one predominant. In Jaqui, primary sector is 55% of labor and the tertiary sector is 35%, being the first one predominant

Table 3.1.2-5 Occupation

| | Distrito | | | |
|------------------|----------|------|-------|------|
| | Yauca | | Jaqui | |
| | 人 | % | 人 | % |
| EAP | 688 | 100 | 604 | 100 |
| Primary Sector | 269 | 39.1 | 334 | 55.3 |
| Secondary Sector | 68 | 9.9 | 56 | 9.3 |
| Tertiary Sector | 351 | 51.0 | 214 | 35.4 |

* Sector primario: agricultura, ganadería, forestal y pesca; secundario: minería, construcción, manufactura; terciario servicios y otros

(4) Poverty index

Table 3.1.2-5, shows the poverty index. 28.2% of the districts' population (956 inhabitants) belongs to the poor segment, and 4.4% (150 inhabitants) belong to extreme poverty.

Table 3.1.2-7 Poverty index

| | District | | | | | |
|---------------------|--------------|------|---------------|------|-------|------|
| | Chincha Alta | | Tambo de Mora | | | |
| | People | % | People | % | Total | % |
| Regional Population | 1,708 | 100 | 1,685 | 100 | 3,393 | 100 |
| In poverty | 449 | 26.3 | 507 | 30.1 | 956 | 28.2 |
| In extreme poverty | 71 | 4.2 | 79 | 4.7 | 150 | 4.4 |

(5) Type of housing

The walls of the houses are made 55% of bricks or cement, and 24% of adobe and mud. The floor is made 95% of earth or cement.

The public drinking water service covers approximately 66% in Yauca and 68% in Jaqui, while the sewage service is 63% in Yauca and 22% in Jaqui (Jaqui is a little far behind in this topic). Electrification reaches 78% in average.

Table 3.1.2-9 Type of housing

| Variable/Indicator | Districts | | | |
|---------------------------------|------------|------------|------------|------------|
| | Yauca | | Jaqui | |
| | Households | % | Households | % |
| Name of housings | | | | |
| Common residents housing | 492 | 59,3 | 461 | 79,2 |
| Walls materials | | | | |
| Bricks or cement | 262 | 53,3 | 265 | 57,5 |
| Adobe and mud | 133 | 27 | 100 | 21,7 |
| Bamboo + mud or wood | 44 | 8,9 | 68 | 14,8 |
| Others | 53 | 10,8 | 28 | 6,1 |
| Floor Materials | | | | |
| Soil | 136 | 27,6 | 160 | 34,7 |
| Cement | 315 | 64 | 290 | 62,9 |
| Ceramics, parquet, quality wood | 38 | 7,7 | 10 | 2,2 |
| Others | 3 | 0,6 | 1 | 0,2 |
| Running water system | | | | |
| Public network within household | 325 | 66,1 | 313 | 67,9 |
| Public network within building | 27 | 5,5 | 49 | 10,6 |
| public use | 4 | 0,8 | | |
| Sewage | | | | |
| Public sewage within household | 308 | 62,6 | 99 | 21,5 |
| Public sewage within building | 19 | 3,9 | 27 | 5,9 |
| Septic Tank | 23 | 4,7 | 147 | 31,9 |
| Electricity | | | | |
| Public electric service | 422 | 85,8 | 321 | 69,6 |
| Member quantity | | | | |
| Common residents housing | 499 | 100 | 483 | 100 |
| Appliances | | | | |
| More than three | 198 | 39,7 | 136 | 28,2 |
| Communication Services | | | | |
| Phones and mobiles | 241 | 48,3 | 7 | 1,4 |

Source: Prepared by JICA Study Team, Statistics National Institute- INEI, 2007 Population and Housing Census.

(6) GDP

Peru's GDP in 2009 was S./392,565,000,000.

The growth rate in the same year was of + 0.9 % compared with the previous year with the poorest level within 11 years.

Itemized by regions, Ica registered a growth of 3.8 %, Piura 2.0 %, Lima 0.4 % and Arequipa 0.2 %. Particularly Ica and Piura regions registered Figures that were beyond the national average.





Figure 3.1.2-1 Growth rate of GDP per region (2009/2008)

The Figure 3.1.2-2 shows the contribution of each region to the GDP. Lima Region represents almost half of the total, that is to say 44.8%. Arequipa contributed with 5.3 %, Piura 4.6 % and Ica 2.9 %. Taxes and duties contributed with 7.2 % and 0.4 %, respectively.




INEI Source – National Accounts National Direction

Figure 3.1.2-2 Region contribution to GDP

The GDP per capita in 2009 was of S/.13,475.

The Table below shows data per region: Lima S/.17,800, Arequipa S/.17,200, Ica S/.15,600 and Piura S/.10,200. The first three regions exceeded the national average, with exception of Piura.



INEI Source – National Accounts National Direction

Figure 3.1.2-3 GDP per capita (2009)

Table 3.1.2-7 shows the variation along the years of the GDP per capita per region, during the last 9 years (2001-2009).

The GDP national average increased in 44% within nine years from 2001 until 2009. The Figures per region are: +83.9 % for Ica, +54.2 % for Arequipa, +48.3 % for Piura and 2.9 % for Lima.

Figures in Table 3.1.2-7 were established taking 1994 as base year.

Table 3.1.2-7 Variation of the GDP per capita (2001-2009)

(1994 Base year, S/.)

| Departament | 2001 | 2002 | 2003 | 2004 | 2005 | 2006 | 2007P/ | 2008P/ | 2009E/ | Accumulated Growth 2001-2009 (%) |
|---------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|----------------------------------|
| Cusco | 2 194 | 2 086 | 2 195 | 2 565 | 2 768 | 3 071 | 3 340 | 3 554 | 3 685 | 67,9 |
| Ica | 4 055 | 4 259 | 4 343 | 4 663 | 5 214 | 5 582 | 6 025 | 7 265 | 7 457 | 83,9 |
| La Libertad | 3 162 | 3 316 | 3 483 | 3 410 | 3 697 | 4 216 | 4 586 | 4 874 | 4 895 | 54,8 |
| Ucayali | 3 063 | 3 149 | 3 203 | 3 411 | 3 584 | 3 754 | 3 846 | 4 007 | 4 039 | 31,9 |
| Moquegua | 10 405 | 11 967 | 12 670 | 13 455 | 13 882 | 13 794 | 13 606 | 14 201 | 13 865 | 33,3 |
| Arequipa | 5 387 | 5 766 | 5 895 | 6 143 | 6 488 | 6 807 | 7 786 | 8 379 | 8 308 | 54,2 |
| Apurimac | 1 216 | 1 278 | 1 334 | 1 400 | 1 494 | 1 619 | 1 653 | 1 691 | 1 770 | 45,5 |
| Piura | 2 733 | 2 780 | 2 847 | 3 049 | 3 192 | 3 472 | 3 780 | 4 007 | 4 052 | 48,3 |
| San Martin | 2 026 | 2 059 | 2 094 | 2 232 | 2 393 | 2 476 | 2 655 | 2 870 | 2 928 | 44,5 |
| Ayacucho | 1 788 | 1 870 | 1 942 | 1 900 | 2 045 | 2 207 | 2 448 | 2 640 | 2 896 | 61,9 |
| Amazonas | 1 835 | 1 910 | 1 996 | 2 081 | 2 212 | 2 349 | 2 510 | 2 684 | 2 761 | 50,5 |
| Madre de Dios | 4 441 | 4 708 | 4 550 | 4 846 | 5 171 | 5 215 | 5 617 | 5 878 | 5 564 | 25,3 |
| Cajamarca | 2 493 | 2 731 | 2 947 | 2 968 | 3 165 | 3 113 | 2 864 | 3 094 | 3 295 | 32,2 |
| Ancash | 4 037 | 4 703 | 4 772 | 4 876 | 4 999 | 5 089 | 5 408 | 5 852 | 5 827 | 44,3 |
| Tumbes | 2 744 | 2 802 | 2 873 | 3 018 | 3 385 | 3 212 | 3 427 | 3 594 | 3 611 | 31,6 |
| Lima | 6 451 | 6 579 | 6 700 | 6 925 | 7 284 | 7 817 | 8 520 | 9 314 | 9 220 | 42,9 |
| Puno | 2 105 | 2 236 | 2 234 | 2 270 | 2 365 | 2 460 | 2 617 | 2 731 | 2 800 | 33,0 |
| Lambayeque | 2 941 | 3 046 | 3 132 | 2 959 | 3 164 | 3 300 | 3 615 | 3 882 | 3 963 | 34,8 |
| Junin | 3 245 | 3 311 | 3 350 | 3 527 | 3 505 | 3 856 | 4 072 | 4 379 | 4 248 | 30,9 |
| Loreto | 2 827 | 2 917 | 2 936 | 2 995 | 3 079 | 3 192 | 3 287 | 3 402 | 3 429 | 21,3 |
| Huánuco | 1 678 | 1 694 | 1 833 | 1 866 | 1 890 | 1 915 | 1 942 | 2 050 | 2 044 | 21,8 |
| Pasco | 5 137 | 5 552 | 5 481 | 5 634 | 5 644 | 6 062 | 6 711 | 6 729 | 6 349 | 23,6 |
| Tacna | 6 004 | 6 124 | 6 382 | 6 643 | 6 782 | 6 941 | 7 256 | 7 458 | 7 253 | 20,8 |
| Huancavelica | 2 700 | 2 632 | 2 683 | 2 697 | 2 864 | 3 014 | 2 903 | 2 959 | 3 039 | 12,5 |
| GDP | 4 601 | 4 765 | 4 890 | 5 067 | 5 345 | 5 689 | 6 121 | 6 643 | 6 625 | 44,0 |

INEI Source – National Accounts National Direction

3.1.3 Agriculture

Next is a summarized report on the current situation of agriculture in each Watershed, including irrigation commissions, crops, planted area, performance, sales, etc.

(1) Irrigation Sectors

Table 3.1.3-1 shows basic data on the irrigation commissions. In the Yauca River Watershed there are 3 irrigation sectors, 3 irrigation commissions with 557 beneficiaries. The surface managed by these sectors reach a total of 1,614 hectares.

Table 3.1.3-1 Basic data of the irrigation commissions

| Irrigation Sectors | Irrigation Commissions | Areas under irrigation | | N° of Beneficiaries (People) | River |
|--------------------|------------------------|------------------------|------------|------------------------------|-------|
| | | ha | % | | |
| Yauca | Yauca | 523 | 32 | 350 | Yauca |
| Mochica | Mochica | 456 | 28 | 57 | |
| Jaqui | Jaqui | 635 | 39 | 150 | |
| Total | | 1,614 | 100 | 557 | |

Source: Prepared by JICA Study Team, Users Board of Yauca, October 2010

(2) Main crops

Table 3.1.3-2 shows the variation between 2004 and 2009 of the planted surface and the performance of main crops.

In the Yauca River Watershed, olive represents 70% of the planted area and between 80 to 90% of the profit, being the key product of this area.

The profits of 2007-2008 were a total of S/.24,808,192, duplicating compared to former years calculations, thanks to the increase of olives production.

Table 3.1.3-3 Sowing and sales of main crops

| | Variables | 2004-2005 | 2005-2006 | 2006-2007 | 2007-2008 | 2008-2009 |
|------------------|--------------------------|------------|------------|------------|------------|------------|
| Olive | Planted Area (ha) | 1,002 | 1,002 | 1,002 | 1,162 | SD |
| | Unit Performance (kg/Ha) | 6,009 | 4,846 | 3,604 | 11,635 | SD |
| | Harvest (Kg) | 6,021,018 | 4,855,692 | 3,611,208 | 13,519,870 | |
| | Unit Price (S/./kg) | 1.41 | 1.75 | 1.90 | 1.70 | 1.90 |
| | Sales (S/.) | 8,489,635 | 8,497,461 | 6,861,295 | 22,983,779 | |
| Alfalfa | Planted Area (ha) | 328 | 347 | 309 | 290 | 257 |
| | Unit Performance (kg/Ha) | 31,160 | 28,096 | 33,074 | 32,480 | 28,674 |
| | Harvest (Kg) | 10,220,480 | 9,749,312 | 10,219,866 | 9,419,200 | 7,369,218 |
| | Unit Price (S/./kg) | 0.09 | 0.10 | 0.10 | 0.10 | 0.10 |
| | Sales (S/.) | 919,843 | 974,931 | 1,021,987 | 941,920 | 736,922 |
| Cotton | Planted Area (ha) | 56 | 53 | 85 | 77 | 85 |
| | Unit Performance (kg/Ha) | 2,035 | 1,990 | 2,693 | 3,297 | 2,760 |
| | Harvest (Kg) | 113,960 | 105,470 | 228,905 | 253,869 | 234,600 |
| | Unit Price (S/./kg) | 2.20 | 2.00 | 2.70 | 2.54 | 1.82 |
| | Sales (S/.) | 250,712 | 210,940 | 618,044 | 644,827 | 426,972 |
| Corn (yellow) | Planted Area (ha) | 20 | 163 | 110 | 33 | 13 |
| | Unit Performance (kg/Ha) | 6,633 | 7,752 | 6,719 | 7,202 | 8,005 |
| | Harvest (Kg) | 132,660 | 1,263,576 | 739,090 | 237,666 | 104,065 |
| | Unit Price (S/./kg) | 0.52 | 0.50 | 0.70 | 1.00 | 0.70 |
| | Sales (S/.) | 68,983 | 631,788 | 517,363 | 237,666 | 72,846 |
| Sweet potatoe | Planted Area (ha) | 10 | 16 | 22 | 23 | 11 |
| | Unit Performance (kg/Ha) | 7,583 | 7,792 | 7,710 | 7,611 | 10,127 |
| | Harvest (Kg) | 75,830 | 124,672 | 169,620 | 175,053 | 111,397 |
| | Unit Price (S/./kg) | 0.59 | 0.60 | 0.75 | 0.83 | 0.92 |
| | Sales (S/.) | 44,740 | 74,803 | 127,215 | 145,294 | 102,485 |
| Others | Planted Area (ha) | 27 | 147 | 46 | 29 | 95 |
| Total | Planted Area (ha) | 2,522 | 3,189 | 3,037 | 2,864 | |
| | Harvest (Kg) | 49,052,450 | 47,090,300 | 47,103,115 | 56,176,725 | 41,216,009 |
| | Sales (S/.) | 42,792,095 | 41,282,962 | 47,588,416 | 66,174,879 | 35,998,549 |




Figure 3.1.3-1 Planted Surface




Figure 3.1.3-2 Harvest




Figure 3.1.3-3 Sales

3.1.4 Infrastructure

(1) Irrigation Infrastructures

In Yauca River there are a total of 48 intakes, from which 2 are permanent. Derivation channels of first, second and third order add up to 191.96km, from which 24.14km (12.6%) are lagged.

Table 3.1.4-1 Existing Irrigation Channels

| JUNTA USUARIO | COMISION DE REGANTES | BOCATOMA | | | CANAL DE DERIVACION | | | CANAL DE PRIMER ORDEN | | | CANAL SEGUNDO ORDEN | | | CANAL TERCER ORDEN | | | TOTAL DEL SISTEMA | | | | | | |
|-----------------------------|----------------------|-----------------|-----------|----------------|---------------------|---------------------|---------------|-----------------------|--------------------|---------------------|---------------------|----------------|--------------------|---------------------|--------------|----------------|--------------------|---------------------|--------------|-------------|---------------|---------------|---------------|
| | | TIPO (cantidad) | Nº | Revestido (km) | sin Revestido (km) | Longitud Total (km) | Nº | Revestido (km) | sin Revestido (km) | Longitud Total (km) | Nº | Revestido (km) | sin Revestido (km) | Longitud Total (km) | Nº | Revestido (km) | sin Revestido (km) | Longitud Total (km) | | | | | |
| Sub Distrito de Riego Acari | Chaviña | 1 | 1 | 1 | 2.708 | 1.372 | 4.080 | 1 | 0.000 | 1.336 | 1.336 | | | 0.00 | | | 0.000 | 2 | 2.71 | 2.71 | 5.42 | | |
| | Acari Bajo | 10 | 1 | 9 | 4.882 | 10.673 | 15.555 | 5 | 4.562 | 6.324 | 10.886 | 1 | 0.00 | 2.50 | 2.50 | | 0.000 | 16 | 9.44 | 19.50 | 28.94 | | |
| | Acari Pueblo | 1 | 0 | 1 | 2.540 | 0.000 | 2.540 | 1 | 4.000 | 0.000 | 4.000 | 7 | 2.48 | 14.49 | 16.97 | 2 | 0.000 | 0.842 | 0.842 | 11 | 9.02 | 15.33 | 24.34 |
| | Chocavente | 2 | 2 | 2 | 0.250 | 1.850 | 2.100 | 2 | 4.500 | 6.000 | 10.500 | | | 0.00 | | | 0.000 | 4 | 4.75 | 7.85 | 12.60 | | |
| | Molino | 3 | 1 | 2 | 3 | 6.360 | 1.125 | 7.485 | 2 | 3.300 | 3.200 | 6.500 | 1 | 0.00 | 0.60 | 0.60 | | 0.000 | 6 | 9.66 | 4.92 | 14.58 | |
| | Quarato Amato | | | 8 | 8 | 1.800 | 15.847 | 17.647 | | | 0.000 | | | 0.00 | | | 0.000 | 8 | 1.80 | 15.85 | 17.65 | | |
| | Visija | | | 2 | 2 | 3.000 | 2.350 | 5.350 | 2 | 0.000 | 1.500 | 1.500 | | 0.00 | | 0.000 | 4 | 3.00 | 3.85 | 6.85 | | | |
| | Huanca | 3 | 3 | 3 | 2.700 | 11.827 | 14.527 | | | 0.000 | | | | 0.00 | | 0.000 | 3 | 2.70 | 11.83 | 14.53 | | | |
| | Lisahuacho | 12 | 12 | 12 | 0.000 | 36.430 | 36.430 | | | 0.000 | | | | 0.00 | | 0.000 | 12 | 0.00 | 36.43 | 36.43 | | | |
| SUBTOTAL | 42 | 4 | 38 | 42 | 24.24 | 81.47 | 105.71 | 13 | 16.36 | 18.36 | 34.72 | 9 | 2.48 | 17.58 | 20.06 | 2 | 0.00 | 0.84 | 0.84 | 66 | 43.08 | 118.25 | 161.34 |
| Bella Unión | Lateral 1 | 1 | 1 | 1 | 17.75 | 2.053 | 19.803 | | | | | | | | | | | 1 | 17.75 | 2.05 | 19.80 | | |
| | Lateral 2 | 1 | 1 | 1 | | | 0 | 1 | 5.584 | 3.216 | 8.8 | 5 | 2.476 | 5.497 | 7.973 | | | 0 | 6 | 8.06 | 8.71 | 16.77 | |
| | Lateral 3 | 1 | 1 | 1 | | | 0 | 1 | 2.35 | 6.35 | 8.7 | 4 | 1.25 | 4.79 | 6.04 | | | 0 | 5 | 3.60 | 11.14 | 14.74 | |
| | SUBTOTAL | 4 | 4 | 0 | 1 | 17.75 | 2.05 | 19.803 | 0 | 16.76 | 9.57 | 26.33 | 13.00 | 5.18 | 16.99 | 22.10 | 0.00 | 0.00 | 0.00 | 0.00 | 17 | 39.69 | 28.61 |
| Sub Distrito de Riego Yauca | Yauca | 9 | 2 | 7 | 9 | 5.75 | 15.55 | 21.30 | 9 | 1 | 7.96 | 8.96 | 3 | 0.65 | 3.91 | 4.56 | | | 21 | 7.40 | 27.42 | 34.82 | |
| | Mochica | 1 | 0 | 1 | 1 | 2.50 | 11.00 | 13.50 | 0 | 0 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | | | 1 | 2.50 | 11.00 | 13.50 | |
| | Paqui | 13 | 0 | 13 | 13 | 14.24 | 27.72 | 41.96 | 5 | 0 | 4.35 | 4.35 | 0 | 0.00 | 0.00 | 0.00 | | | 18 | 14.24 | 32.07 | 46.31 | |
| | San Luis Palca | 0 | 11 | 11 | 11 | 0.00 | 35.80 | 35.80 | 0 | 0 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | | | 11 | 0.00 | 35.80 | 35.80 | |
| | Lampalla | 12 | 0 | 12 | 12 | 0.00 | 48.82 | 48.82 | 0 | 0 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | | | 12 | 0.00 | 48.82 | 48.82 | |
| | Cuesta Chacui | 2 | 2 | 2 | 2 | 0.00 | 12.70 | 12.70 | 0 | 0 | 0 | 0 | 0 | 0.00 | 0.00 | 0.00 | | | 2 | 0.00 | 12.70 | 12.70 | |
| SUBTOTAL | 48 | 2 | 46 | 48 | 22.49 | 151.59 | 174.08 | 14 | 1 | 12.31 | 13.31 | 3 | 0.65 | 3.91 | 4.56 | 0 | 0 | 0 | 0 | 65 | 24.14 | 167.81 | 191.95 |
| TOTAL | 94 | 10 | 84 | 91 | 64.48 | 235.17 | 299.59 | 730 | 34.12 | 40.23 | 74.35 | 25 | 8.302 | 38.47 | 46.71 | 2 | 0 | 0.842 | 0.842 | 148 | 106.91 | 314.61 | 421.5 |

(2) PERPEC

No PERPEC project has been implemented in Yauca River between 2006 and 2009.

3.1.5 Real flood damages

(1) Damages on a nationwide scale

Table 3.1.5-1 shows the present situation of flood damages during the last five years (2003-2007) in the whole country. As observed, there are annually dozens to hundreds of thousands of flood affected inhabitants.

Table 3.1.5-1 Situation of flood damages

| | | Total | 2003 | 2004 | 2005 | 2006 | 2007 |
|----------------------------|--------|---------|---------|--------|--------|---------|--------|
| Disasters | Cases | 1,458 | 470 | 234 | 134 | 348 | 272 |
| Víctims | people | 373,459 | 118,433 | 53,370 | 21,473 | 115,648 | 64,535 |
| Housing loss victims | people | 50,767 | 29,433 | 8,041 | 2,448 | 6,328 | 4,517 |
| Decesased individuals | people | 46 | 24 | 7 | 2 | 9 | 4 |
| Partially destroyed houses | Houses | 50,156 | 17,928 | 8,847 | 2,572 | 12,501 | 8,308 |
| Totally destroyed houses | Houses | 7,951 | 3,757 | 1,560 | 471 | 1,315 | 848 |

Source : SINADECI Statistical Compendium

Peru has been hit by big torrential rain disasters caused by the El Niño Phenomenon. Table 3.1.5-2 shows damages suffered during the years 1982-1983 and 1997-1998 with extremely serious effects. Victims were approximately 6.000.000 inhabitants with an economic loss of about US\$ 1.000.000.000 in 1982-1983. Likewise, victims number in 1997-1998 reached approximately 502.461 inhabitants with economic loss of US\$ 1.800.000.000. Damages in 1982-1983 were so serious that they caused a decrease of 12 % of the Gross National Product.

Table 3.1.5-2 Damages

| Damages | 1982-1983 | 1997-1998 |
|--|---------------|---------------|
| Persons who lost their homes | 1.267.720 | — |
| Victims | 6.000.000 | 502.461 |
| Injured | — | 1.040 |
| Deceased | 512 | 366 |
| Missing persons | — | 163 |
| Partially destroyed houses | — | 93.691 |
| Totally destroyed houses | 209.000 | 47.409 |
| Partially destroyed schools | — | 740 |
| Totally destroyed schools | — | 216 |
| Hospitals and health centers partially destroyed | — | 511 |
| Hospitals and health centers totally destroyed | — | 69 |
| Damaged arable lands (ha) | 635.448 | 131.000 |
| Head of cattle loss | 2.600.000 | 10.540 |
| Bridges | — | 344 |
| Roads (km) | — | 944 |
| Economic loss (\$) | 1.000.000.000 | 1.800.000.000 |

“—”: No data

(2) Disasters in the watersheds object of this study

Table 3.1.5-3 summarizes damages occurred in the Arequipa region, to which this study belongs to.

Table 3.1.5-3 Disasters in Arequipa Region

| Years | 1995 | 1996 | 1997 | 1998 | 1999 | 2000 | 2001 | 2002 | 2003 | 2004 | 2005 | 2006 | 2007 | 2008 | 2009 | 2010 | Total | Media |
|--------------------------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|-------|-------|
| LANDSLIP | | | | | | | | | | | | | | | | 1 | 1 | |
| FLOOD | | | | | | | | | | | 5 | | | | | | 5 | |
| COLLAPSE | | | | | | 1 | 1 | 1 | | | | | | | | 1 | 4 | |
| LANDSLIDE | | 1 | | 1 | 1 | 2 | 1 | 1 | 4 | 3 | 4 | 2 | | | 1 | 2 | 23 | |
| AVALANCHE | 6 | 1 | 7 | 14 | 3 | 2 | 4 | | | | 2 | 2 | 1 | | 9 | 3 | 54 | |
| TOTAL SEDIMENT DISASTERS | 6 | 2 | 7 | 15 | 4 | 5 | 6 | 2 | 4 | 3 | 11 | 4 | 1 | 0 | 10 | 7 | 87 | 5 |
| TOTAL FLOODING | 3 | 1 | 42 | 6 | 44 | 2 | 15 | 3 | 1 | 2 | 2 | 3 | 0 | 1 | 3 | 3 | 131 | 8 |

3.1.6 Results on the visits to Study Sites

JICA Study Team made some technical visits to the selected watersheds and identified some challenges on flood control through visits and interviews to regional government authorities and irrigation associations on damages suffered in the past and the problems each watershed is currently facing.

(1) Interviews

Lowest watershed's bridge

- Main crop is olive
- 400 olives, approximately of 100 years were overthrown by the river's overflow a couple of years ago
- The river's bed elevated due to El Niño floods in 1998
- The maximum water level was reached during 1983 el Niño, which water raised up to the upper section of the bridge on Panamericana Highway

○ San Francisco

- Small olives trees are seen downstream this area, this was the affected area by last year's floods
- Olives may be harvested 8 years after the trees are planted. Trees with more than 20 to 30 years have more to harvest. There are trees of 100 to 500 years
- From one tree you can obtain a harvest of approx 200 to 250 kg/year. There are 100 trees per hectare. The cost of 1 kg is about 3.5 soles
- The lower watershed sector has an approx extension of 400 hectares

○ Mochica Intake

- 1700L/s are taken
- There are 580 hectares of olives in the middle watershed

- The harvest volume is 80kg/year per tree (max 200kg). In an abundant harvest year, a hectare may pay up to 10.000kg
- There is a Dam in Ayacucho, upstream, where water is discharged for a month between August and September
- The total capacity of this dam is $23 \times 10^6 \text{ m}^3$
- This dam has been built 120 years ago, it has cracks and water leaks. This dam had been used in Yauca and another community until 2006, then another community was added, but it cannot supply more communities any longer
- MINAG determines the water discharge period from the dam
- It is hoped to give the maximum use to the water. It is better to control the water from the river's bed
- The fluvial terrace is used without authorization for agriculture production, which is an issue
- The bed continues to raise
- Bridge in the narrow section (last bridge on the Yauca River upper watershed)
 - From this point upwards is Jaqui sector
 - There are 490 hectares of olives and 14 intakes
 - Floods destroy intakes leaving them out of service
- Intakes
 - Flood water reaches olives
 - The channel upstream the intake is destroyed due to floods
 - Water volume has been decreasing in the past 15 years, so much that producers have been planting olives even near the river bed
 - Every Jaqui channels are made of masonry and are destroyed every time a flood occurs. All 14 channels have been destroyed with the same frequency (it does not happen that some of them are destroyed and some are left ok)
- Drinking water Intake
 - It was finished building last year
- Purification Plant
 - It was finished recently
 - Currently, chemical treatment is not being done
 - Water is used for human consumption in Jaqui, downstream

(2) Description of the visit to the study sites

Figure 3.1.6-1 shows pictures of main sites visited.



Figure 3.1.6-1 Visit to the Study Site (Yauca River)

(3) Challenges and measures

The following table shows challenges and possible solution measures for flood control considered at this moment, based on the results of technical visits.

1) Challenge 1: Floodplain area (km 7.0 downstream)

| | |
|----------------------------------|--|
| Current situation and challenges | <ul style="list-style-type: none"> • Main product is olive • Urban area is relatively in a high elevation so direct risk of floods and overflowing is reduced. The elements to be protected are the trees and hydraulic installations • A dike is built empirically and partially, but banks are eroded and flood may affect the olives |
| Main elements to be conserved | <ul style="list-style-type: none"> • Agricultural lands (main product: olive) |
| Basic measures | <ul style="list-style-type: none"> • Repair existing dike • Execute bank protection Works (banks erosion control) • Build retarding reservoirs |



Figure 3.1.6-2 Local conditions related with Challenge 1 (Yauca River)

2) Challenge 2: Water intake point in the middle watershed (km 25.0)

| | |
|----------------------------------|---|
| Current situation and challenges | <ul style="list-style-type: none"> • The fluvial terrace of the opposite bank began to be cultivated recently, so, overflows will be on the right bank • As main problem that has to be solved, the flood impact on the intake is mentioned, also the right bank's erosion were the highway passes is mentioned too |
| Main elements to be conserved | <ul style="list-style-type: none"> • Olives (from this area and from the lower watershed) |
| Basic measures | <ul style="list-style-type: none"> • Reinforce the intake • Execute bank protection works (right bank erosion control) • Built retarding reservoirs (buying lands from the opposite bank) |





Figure 3.1.6-3 Local conditions related with Challenge 2 (Yauca River)

3) Challenge 3: Upper watershed intake point (km 27.0 upper watershed)

| | |
|----------------------------------|--|
| Current situation and challenges | <ul style="list-style-type: none"> ▪ There are several relatively simple intakes ▪ Some of these intakes are destroyed and require to be repaired every time a flood takes place |
| Main elements to be conserved | <ul style="list-style-type: none"> ▪ Olives (from this area and from the lower watershed) |
| Basic measures | <ul style="list-style-type: none"> ▪ Built retarding reservoirs (to reduce floods peak stream) ▪ Built an intake (to integrate the existing small works) |




Figure 3.1.6-4 Local conditions related with Challenge 3 (Yauca River)

3.1.7 Current situation of vegetation and reforestation

(1) Current Vegetation

Pursuant to the 1995 Forest Map and its explanations, the Cañete, Chinchá, Pisco and Yauca watersheds extends from the coast to the Andean mountains; usually, they feature different vegetal coverage according to the altitude. From coast up to the 2,500m.a.s.l (Cu, Dc) have scarce vegetation. Some meters above in altitude, there are only scarce bushes disseminated in the area due to the rains. Although, in zones close to the rivers, high trees are mainly develop (4 meters approximately), even in arid zones.

Table 3.1.7-1 List of representative vegetable forming in the Yauca watersheds

| Symbol | Life Zone | Distribution of Altitude | Rainfall | Representative Vegetation |
|--------|----------------------|---|--|--|
| 1)Cu | Coast Crop Lands | Coast | Almost none. | Coastal crops |
| 2)Dc | Coast Desert | 0~1,500 m.a.s.l | Almost none, there are mist zones. | Almost none, there are vegetation slopes |
| 3)Ms | Dry Thicket | 1,500~3,900 m.a.s.l | 120~220mm | Cactus and grass |
| 4)Msh | Subhumid Forest | North-center: 2,900~3,500 m.a.s.l Inter Andean 2,000~3,700 m.a.s.l | 220~1,000mm | Perennial bushes, less than 4m high |
| 5)Mh | Humid Forest | North: 2,500~3,400 m.a.s.l South 3,000~3,900 m.a.s.l | 500~2,000mm | Perennial bushes, less than 4m high |
| 6)Cp | Puna grass | Approx 3,800 m.a.s.l | No description | Gramineae |
| 7)Pj | Scrubland | 3,200~3,300 m.a.s.l Center-South up to 3,800 m.a.s.l | South zone with low rainfall: less than 125mm East springs: higher than 4,000mm | Gramineae |
| 8)N | Ice-capped mountains | | — | — |

Source: Prepared by the JICA Team based on the Forest Map. 1995

(2) Area and distribution of vegetation

The present study was determined by the surface percentage that each vegetation formation occupies on the total watershed's surface, overcoming the INRENA study results of 1995 to the GIS (see Tables 3.1.7-2 and Figures 3.7.2-1). Then, the addition of each ecologic life zone's surface, outstanding the coastal desert (Cu, Pj), dry grass (Ms), bushes (Msh, Mh) and puna grass (Cp, Pj). Table 3.1.7-3 shows the percentage of each ecologic area. It is observed that the desert occupies 20% of the total area, 10% of dried grass and puna grass 50%. Bushes occupy between 10 to 20%. They are distributed on areas with unfavorable conditions for the development of dense forests, due to which the surface of these bushes is not wide. So, natural conditions of the four watersheds, Cañete, Chinchá, Pisco and Yauca are set. In particular, the low precipitations, the almost non-fertile soil and accentuated slopes are the limiting factors for the vegetation growth, especially on high size species.

Table 3.1.7-2 Vegetation formation surface of the watershed's surface(Yauca River)

| Watershed | Vegetation Cover | | | | | | | | |
|---------------------|------------------|----------|--------|--------|--------|--------|--------|------|----------|
| | Cu | Dc | Ms | Msh | Mh | Cp | Pj | N | Total |
| (Surface: hectares) | | | | | | | | | |
| Yauca River | 69,48 | 1.433,26 | 990,99 | 730,67 | 234,49 | 428,64 | 435,04 | 0,00 | 4,322,57 |
| (Percentage: %) | | | | | | | | | |
| Yauca River | 1,6 | 33,2 | 22,9 | 16,9 | 5,4 | 9,9 | 10,1 | 0,0 | 100,0 |

Source: Prepared by the JICA Team based on the INRENA1995 Forest Map

Table 3.1.7-3 Ecologic Life Areas Percentage (Yauca River)

| Watershed | Ecologic life areas | | | | | Total |
|-----------------|-----------------------|----------------|-----------------|-----------------|-----------|-------|
| | Desert, etc. (Cu, Dc) | Dry grass (Ms) | Grass (Msh, Mh) | Bushes (Cp, Pj) | Snowy (N) | |
| (Percentage: %) | | | | | | |
| Yauca | 34.8 | 22.9 | 22.3 | 20.0 | 0.0 | 100.0 |

Source: Prepared by the JICA Team based on the INRENA1995 Forest Map

(3) Forest area variation

Although a detailed study on the variation of the forest area in Peru has not been performed yet, the National Reforestation Plan Peru 2005-2024, Annex 2 of INRENA shows the areas deforested per department until 2005. These areas subject matter of this study are included in the regions of Arequipa, Ayacucho, Huancavelica, Ica, Lima and Piura, but they only belong to these regions partially. Table 3.1.7-4 shows the Figures accumulated areas deforested in these regions. However, in relation to the Arequipa Region, data is not available.

Table 3.1.7-4 Area Deforested Until 2005

| Department | Area (ha) | Area deforested accumulated (ha) and the percentage of such area in the department area (%) | Post-Felling Situation | |
|------------|-----------|---|------------------------|---------------|
| | | | Non used Area (ha) | Used area(ha) |
| Arequipa | 6.286.456 | - | - | - |

Source: National Reforestation Plan, INRENA, 2005

The variation of the distribution of vegetation was analyzed per watershed, comparing data from the FAO study performed in 2005 (prepared based on satellite figures from 2000) and the results of the 1995 INRENA study (prepared base on satellite figures from 1995). (See Table 3.1.7-5).

Analyzing the variation of the surface of each vegetation formation, it is observed that the vegetation has reduced in the arid zones (desert and cactus: Cu, DC and Ms) and bushes (Cp, Pj) but have increased in the arid area (desert DC) and scrub area (Msh, Mh).

Table 3.1.7-5 Changes in the areas of distribution of vegetation from 1995 to 2000

| Watershed | Vegetation Formation | | | | | | | | |
|--|----------------------|----------|--------|--------|--------|--------|--------|------|----------|
| | Cu | | Cu | | Cu | | Cu | | Cu |
| (Surface of the vegetation cover: hectare) | | | | | | | | | |
| Yauca (a) | -20,22 | 33,63 | -10,87 | 34,13 | 21,15 | -42,62 | -15,20 | — | 4.322,57 |
| Current Surface (b) | 69,48 | 1,433,26 | 990,99 | 730,67 | 234,49 | 428,64 | 435,04 | 0,00 | 4.322,57 |
| Percentage of current surface (a/b) % | -29,1 | +2,3 | -1,1 | +4,7 | +9,0 | -9,9 | -3,5 | - | |

Source: Prepared by the JICA Study Team based on the studies performed by the INRENA 1995 and FAO 2005

(4) Current situation of forestation

As indicated before, the climate conditions of Yauca River watershed do not improve high trees species development, so natural vegetation is not distributed; this only happens in the banks where the freatic water table is near the surface.

So, due to the difficult situation of finding a good spot to grow trees is why reforestation great projects have not happened in this area. There is no reforest project known with commercial aims.

In the lower and medium watersheds, trees are planted mainly for three objectives: i) reforest along the river to prevent disasters; ii) for agricultural lands protection from wind and sand; and iii) as perimeter for housings. In any case, the surface is much reduced. The most planted specie is Eucalyptus and is followed by *Casuarinaceae*. The use of native species is not very common. On the other hand, in the Mountain region, reforestation is done for logging, crops protection (against cold and livestock entrance) and to protect the recharge water areas. There are mostly eucalyptus and pines. Many reforest projects in the Mountain region have been executed following PRONAMACHS (currently, AGRORURAL). Such program gives throughout AGRORURAL seedlings to the community, which are planted and monitored by producers. There is also a reforest program implemented by the regional government, but in a much reduced way. In this case, the program establishes the needs to achieve consensus from the community to choose the areas to be reforested. However, in general, mostly all farmers want to have greater crop lands and achieving consensus always takes more time. Another limiting factor is the cold weather on altitudes greater than 3.800m.a.s.l. In general, no information has been able to be collected on reforestation projects to date, because these files were not available.

The National Reforestation Plan (INRENA, 2005) registers forestation per department from 1994 to 2003, from which the history data corresponding to the environment of this study was searched (See Table 3.1.7-6). It is observed that the reforested area increased in 1994, drastically decreasing later. Arequipa, Ica and Lima are departments located in the coast zone with scarce rainfall, thus the forestation possibility is limited, besides the scarce forest demand.

Table 3.1.7-6 History registry of forestation 1994-2003

(Units: ha)

| Department | 1994 | 1995 | 1996 | 1997 | 1998 | 1999 | 2000 | 2001 | 2002 | 2003 | Total |
|------------|-------|------|------|-------|------|------|------|------|------|------|-------|
| Arequipa | 3.758 | 435 | 528 | 1.018 | 560 | 632 | nr | 37 | 282 | 158 | 7.408 |

Source: National Reforestation Plan, INRENA, 2005




Figure 3.1.7-1 Forestry map of Yauca River Watershed

3.1.8 Current situation of the soil erosion

(1)Information gathering and basic data preparation

1) Information Gathering

During this study the data and information indicated in Table 3.1.8-1 was collected in other to know the current situation of the sediment production behind the Study Area.

Table 3.1.8-1 List of collected information

| | Forms | Prepared by: |
|-----------------------------------|--------------------|-------------------------------|
| Topographic map (Scale 1/50.000) | Shp | INSTITUTO GEOGRAFICO NACIONAL |
| Topographic map (Scale 1/100.000) | Shp,dxf | INSTITUTO GEOGRAFICO NACIONAL |
| Topographic map (Scale 1/250.000) | SHP | Geologic data systems |
| Topographic map (Scale 1/100.000) | Shock Wave | INGEMMET |
| 30 m grid data | Text | NASA |
| River data | SHP | ANA |
| Watershed data | SHP | ANA |
| Erosion potential risk map | SHP | ANA |
| Soils map | SHP | INRENA |
| Vegetal coverage map | SHP2000 PDF1995 | DGFFS |
| Rainfall data | Text | Senami |

2) Preparation of basic data

The following data was prepared using the collected material. Details appear in Annex 6.

- Hydrographic watershed map (zoning by third order valleys)
- Slope map
- Geological Map
- Erosion and slope map
- Erosion and valley order map
- Soil map
- Isohyets map

(2)Analysis of the causes of soil erosion

1) Topographic characteristics

- i) Surface pursuant to altitudes

Table 3.1.8-2 and Figure 3.1.8-1 show the percentage of surface according to altitudes

Table 3.1.8-2 Surface according to altitude

| Altitude (m.a.s.l) | Area (km ²) |
|--------------------|-------------------------|
| | Yauca |
| 0 – 1000 | 332,79 |
| 1000 – 2000 | 575,82 |
| 2000 – 3000 | 1302,58 |
| 3000 – 4000 | 1504,8 |
| 4000 – 5000 | 602 |
| 5000 – More | 0,55 |
| TOTAL | 4318,54 |
| Maximum Altitude | 5060,00 |

Source: Prepared by the JICA Study Team based on the 30 m grid data




Figure 3.1.8-1 Surface according to altitude

ii) Zoning according to slopes

Table 3.1.8-3 and Figure 3.1.8-2 show the slopes in each watershed.

Table 3.1.8-3 Slopes and surface

| Watershed slope (%) | Yauca | |
|-----------------------|-------------------------|------------|
| | Área (km ²) | Percentage |
| 0 - 2 | 79,01 | 2% |
| 2 - 15 | 1190,19 | 28% |
| 15 - 35 | 1591,21 | 37% |
| More than 35 | 1458,13 | 34% |
| TOTAL | 4318,54 | 100% |




Figure 3.1.8-2 Slopes and surface

iii) River-bed slope

Table 3.1.8-4 and Figure 3.1.8-3 show the slope in every river and the length of streams including tributaries. Figure 3.1.8-4 shows the general relation of the movement of sediments and the river-bed slope. Supposedly, sections with more than 33,3 % of slope tend to produce higher amount of sediments, and hillsides with slopes between 3,33 % and 16,7 %, accumulate sediments easier.

Table 3.1.8-4 River-bed Slope and total length of stream

| River-bed slope (%) | Yauca |
|---------------------|----------------|
| 0,00 - 1,00 | 39,13 |
| 1,00 - 3,33 | 312,82 |
| 3,33 - 16,67 | 1687,19 |
| 16,67 - 25,00 | 352,42 |
| 25,00 - 33,33 | 185,78 |
| 33,33 - More | 226,92 |
| TOTAL | 2804,26 |




Figure 3.1.8-3 River-bed Slope and total length of streams





Figure 3.1.8-4 River-bed slope and sediment movement pattern

3) Rainfall

On the Pacific coast there is an arid area of 30 to 50km width and approx 3.000km long. This region belongs to a climate zone called Chala, where the middle annual temperature is about 20 °C and almost it does not rain along the year.

Altitudes between 2500 and 3000 m.a.s.l. belong to the Quechua zone, where annual precipitation exist between 200 and 300mm. On altitudes from 3500 and 4500m.a.s.l there is another region, called Suni, characterized by its sterility. Precipitations in this region occur annually with 700mm of rain.

Figure 3.1.8-5 shows the isohyets map (annual rainfall) of the watershed.



Source: Prepared by the JICA Study Team based on the SENAMHI data

Figure 3.1.8-5 Isohyet Map of the Yauca river watershed

Annual precipitations in the flood analysis area fluctuate between 0 and 25mm. The average annual precipitation in the northern area of 4000 m.a.s.l is between 500 and 750 m.a.s.l.

4) Erosion

The characteristics of erosion of the watershed in general are presented below. This is divided in three large natural regions: Coast, Mountain/Suni and Puna. Figure 3.1.8-6 shows the corresponding weather and the rainfalls. It is observed that the area most sensitive to erosion is Mountain/Suni where the pronounced topography without vegetal coverage predominates.




Figure 3.1.8-6 Relation between the erosion volume and the different causes

(3) Identification of the zones more vulnerable to erosion

The erosion map prepared by ANA considers the geology, hill sloping and rainfalls. Supposedly, the erosion depth depends on the hillside slope, and in such sense the erosion map and the slope map are consistent. Thus, it is deduced that the zones more vulnerable to erosion according to the erosion map are those where most frequently erosion happens within the corresponding watershed. Next, the tendencies regarding the watershed are described.

Between 1000 and 3000 m.a.s.l are located on slopes with more than 35 degrees. It is observed that this watershed's topography is less accentuated than the Cañete, Chinchá and Pisco watersheds. In particular, between 1000 and 2000m.a.s.l, 76% of slopes are more than 35° and are deduced to be more susceptible to erosion.

Table 3.1.8-5 Slopes according to altitudes of the Yauca river watershed

| Altitude | SLOPES | | | | Total |
|-------------|--------|---------|---------|--------------|---------|
| | 0-2 | 2 - 15 | 15 - 35 | More than 35 | |
| 0 - 1000 | 21.13 | 106.81 | 86.07 | 118.78 | 332.79 |
| Ratio | 6% | 32% | 26% | 36% | 100% |
| 1000 - 2000 | 1.48 | 40.14 | 94.66 | 439.54 | 575.82 |
| Ratio | 0% | 7% | 16% | 76% | 100% |
| 2000 - 3000 | 14.72 | 350.89 | 399.92 | 538.08 | 1303.61 |
| Ratio | 1% | 27% | 31% | 41% | 100% |
| 3000 - 4000 | 25.07 | 498.75 | 686.54 | 295.34 | 1505.7 |
| Ratio | 2% | 33% | 46% | 20% | 100% |
| 4000 - 5000 | 17.56 | 194.38 | 324.82 | 67.24 | 604 |
| Ratio | 3% | 32% | 54% | 11% | 100% |
| 5000 - More | 0.15 | 0.22 | 0.1 | 0.18 | 0.65 |
| Ratio | 23% | 34% | 15% | 28% | 100% |
| Total | 80.11 | 1191.19 | 1592.11 | 1459.16 | 4322.57 |
| Ratio | 2% | 28% | 37% | 34% | 100% |




Figure 3.1.8-7 Slopes according to altitudes of Yauca River

(4) Production of sediments

1) Results of the geological study

The study was performed on the upper watersheds of Pisco and Cañete Rivers. It is considered that the conditions for Yauca River are similar. The results are described below.

- On mountain slopes there are formations of clastic deposits leaved by collapses or wind erosion
- Production patterns are differentiated according to the foundation rock geology. If this foundation is andesitic or basaltic, the mechanisms consists mainly in great gravel falling (see Figure 3.1.8-8 and 3.1.8-9)
- There is no rooted vegetation (Figure 3.1.8-10) due to the sediment in ordinary time. On the joints of the andesitic rock layer where few sediment movements occur, algae and cactus have developed

- In almost every stream lower terrace formation was observed. In these places, sediments dragged from slopes do not enter directly to the stream, but they stay as deposits on the terraces. Due to this, most of the sediments that enter the river probably are part of the deposits of the erosion terraces or accumulated sediments due to the bed's alteration (see Figure 3.1.8-11)
- On the upper watershed there are less terraces and the dragged sediments of slopes enter directly to the river, even though its amount is very little



Figure 3.1.8-8 Andesitic and Basaltic lands collapse



Figure 3.1.8-9 Sediment production of the sedimentary rocks



Figure 3.1.8-10 Cactus Invasion




Figure 3.1.8-11 Movement of the sediment in the stream


2) Sediments movement (in the stream)

In ravines terraces are developed. The base of these terraces is directly contacted with channels and from these places the sediments will be dragged and transported with an ordinary stream (including small and medium overflows in rainy season).

3) Production forecast and sediments entrainment

It is expected that the amount of sediment production and entrainment will vary depending of the dimension of factors such as rainfall, volume of flow, etc.

Since a quantitative sequential survey has not been performed, nor a comparative study, here we show some qualitative observations for an ordinary year, a year with a rainfall similar to that of El Niño and one year with extraordinary overflow. The scope of this Study is focused on a rainfall with 50 year return period, as indicated in the Figure below, which is equivalent to the rainfall producing the sediment flow from the tributaries.



(i) An ordinary year

- Almost no sediments are produced from the hillsides
- Sediments are produced by the encounter of water current with the sediment deposit detached from the hillsides and deposited at the bottom of terraces
- It is considered that the entrainment is produced by this mechanism: the sediments accumulated in the sand banks within the bed are pushed and transported downstream by the bed change during low overflows (see Figure 3.1.8-12)




Figure 3.1.8-12 Production and entrainment of sediments in an ordinary year

(ii) When torrential rains with magnitude similar to that of the El Niño happen (50 years return period)

Pursuant to the interviews performed in the locality, every time El Niño phenomenon occurs the tributary sediment flow occurs. However, since the bed has enough capacity to regulate sediments, the influence on the lower watershed is reduced.

- The amount of sediments entrained varies depending on the amount of water running by the hillsides
- The sediment flow from the tributaries reaches to enter to the main river
- Since the bed has enough capacity to regulate the sediments, the influence in the watershed is reduced




Figure 3.1.8-13 Production and entrainment of sediments during the torrential rainfall of magnitude similar to that of El Niño (1:50 year return period)

(iii) Large magnitude overflows (which may cause the formation of terraces similar to those existing now), with a 1:10.000 year return period

In the coast, daily rainfall with 100 years of probability are approximately 50 mm, so land slides entrained by water scarcely occur currently. However, precisely since there are few rains, when torrential rainfall occurs, there is a high potential of water sediment entrainment.

If we suppose that rainfall occurs with extremely low possibilities, for example, 1:10.000 years, we estimate that the following situation would happen (see Figure 3.1.8-14).

- Sediment entrainment from hillsides, by the amount congruent with water amount
- Exceeding sediment entrainment from the bank and bottom of hillsides by the amount congruent with the water amount, provoking landslides which may close streams or beds
- Destruction of the natural embankments of beds closed by the sediments, sediment flow by the destruction of sand banks
- Formation of terraces and increase of sediments in the beds of lower watershed due to the large amount of sediments
- Overflowing in section between alluvial cone and critical sections, which may change the bed.




Figure 3.1.8-21 Production of sediments in large overflowing (geologic scale)

3.1.2 Run off analysis

(1) Rainfall data

1) Current rainfall monitoring system

The current rainfall data collection system used for the discharge analysis was reviewed; besides, the necessary rainfall data was collected and processed for such analysis. Rainfall data was obtained from SENAMHI and ELECT.PERU.

Tables 3.1.9-1~2 and Figure 3.1.9-1 indicate the rainfall monitoring points and the data collected according to the period.

In Yauca river watershed rainfall monitoring is performed in 7 stations (including those currently non-operative), for a maximum period of 47 years since 1964 until 2010.

Table 3.1.9-1 List of rainfall monitoring stations (Yauca river watershed)

| NAME | CODE of STATION | LENGTH [° ' ''] | LATITUDE [° ' ''] | HEIGHT [m.a.s.l] | PERIOD |
|--------------|-----------------|------------------|--------------------|------------------|--|
| YAUCA | 000743 | 74°31'01.0" | 15°40'01.0" | | 1964-1976,1979-1982 |
| CARHUANILLAS | 157220 | 73°44'01.0" | 15°08'01.0" | 3,000 | 1967-1968,1971-1987 |
| CHAVIÑA | 000742 | 73°50'01.0" | 14°59'01.0" | 3,310 | 1964-1982 |
| CORA CORA | 000743 | 73°47'01.0" | 15°01'01.0" | 3,172 | 1964, 1966-1984, 1987-1988,1991, 1993-2010 |
| SANCOS | 000740 | 73°57'01.0" | 15°04'01.0" | 2,800 | 1964-1980 |
| TARCO | 157216 | 73°45'01.0" | 15°18'01.0" | 3,300 | 1967-1969, 1971-1973 |

In the Yauca River Watershed is observed that the considerable variation of the annual rainfall depending on the zones, with a minimum of 25mm and a maximum of 750 mm approximately. The rainfall is lower on the lower watershed and it increases as the altitudes gets near the upper watershed, increasing the altitudes.

The annual rainfall in the low watershed, subject to the control of floods, is reduced ranging from 25 to 50 mm.




Figure 3.1.9-2 Isohyet Map (Yauca River watershed)

(2) Rainfall analysis

1) Methodology

The statistic hydrologic calculation was made using the rainfall data collected from several stations, to determine the rainfall with 24 hour return period in every station.

Several models of distribution of return periods were tested and the most adequate one was adopted. Thus, the precipitation with 24 hours return period was determined with this model.

The statistic hydrologic models were:

- Normal o Gaussian distribution
- Log-Normal of 3 parameters distribution
- Log-Normal of 2-parameters distribution
- Gamma distribution of 2 or 3 parameters
- Log Pearson Type III distribution
- Gumbel distribution
- General distribution of extreme value

2) Results of the rainfall analysis of return period– t

The rainfall of several stations are shown below and the reference point of each watershed, according to return periods.

Rain observed in Yauca River stations has been greater than 40mm with a maximum of 84mm.

Table 3.1.9-3 shows the monitoring points and the rainfall with 24 hour return period in each station. Figure 3.1.9-3 shows the map of isohyets of rainfall with 50 year return period.

**Table 3.1.9-3 Rainfall with 24 hour return period
(Yauca river watershed)**

| Station Name | Return Period T [YEARS] | | | | | | |
|--------------|-------------------------|------|-------|-------|-------|--------|--------|
| | PT_2 | PT_5 | PT_10 | PT_25 | PT_50 | PT_100 | PT_200 |
| CARHUANILLAS | 26.0 | 42.0 | 54.0 | 70.0 | 84.0 | 98.0 | 114.0 |
| CHAVIÑA | 32.0 | 42.0 | 48.0 | 54.0 | 59.0 | 62.0 | 66.0 |
| CORA CORA | 28.0 | 36.0 | 41.0 | 46.0 | 49.0 | 52.0 | 54.0 |
| SANCOS | 34.0 | 48.0 | 57.0 | 67.0 | 74.0 | 80.0 | 86.0 |
| TARCO | 20.0 | 32.0 | 41.0 | 54.0 | 65.0 | 77.0 | 91.0 |

**Table 3.1.9-4 Rain of 24 hours for the different return periods
(Reference Point: San Francisco Alto Station)**

| Return Period (years) | Maximum Precipitation in 24 hours (mm) |
|-----------------------|--|
| 5 | 28 |
| 10 | 33 |
| 25 | 39 |
| 50 | 45 |
| 100 | 50 |




Figure 3.1.9-3 Map of isohyets of a 50 years period rainfall (Yauca river watershed)

Table 3.1.9-5 Pluviograph of the different return periods

| Years | Hours | | | | | | | | | | Total Precipitation (mm) |
|-------|-------|---|---|---|---|---|---|---|---|----|--------------------------------|
| | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | |
| 5 | 1 | 2 | 3 | 4 | 3 | 3 | 2 | 2 | 1 | 1 | 22 |
| 10 | 1 | 2 | 3 | 5 | 4 | 3 | 3 | 2 | 2 | 1 | 26.5 |
| 25 | 2 | 3 | 4 | 6 | 4 | 4 | 3 | 3 | 2 | 1 | 31.3 |
| 50 | 2 | 3 | 5 | 7 | 5 | 4 | 4 | 3 | 2 | 1 | 36.2 |
| 100 | 2 | 4 | 5 | 8 | 6 | 5 | 4 | 3 | 2 | 2 | 40.2 |

(3) Run off analysis

1) Flow monitoring

The current flow data collection system used in the discharge analysis was reviewed, and the necessary flow monitoring data were collected and processed for such analysis. The flow data have been obtained mainly from the DGIH, irrigation commissions, Water National Authority (ANA) and the Chira-Piura Special Project.

2) Run off analysis

The statistic hydrological calculation was made using the data of the maximum annual discharge collected and processed in the reference points, to determine the flow with different probabilities. Table 3.1.9-6 shows the probable flow with return periods between 2 and 100 years.

Table 3.1.9-4 Probable flow in control points

| Rivers | Return periods | | | | | |
|-----------------------------------|----------------|---------|----------|----------|----------|-----------|
| | 2 years | 5 years | 10 years | 25 years | 60 years | 100 years |
| Yauca River San Francisco Alto | 41 | 81 | 116 | 171 | 219 | 273 |

(m³/s)

3) Analysis of flooding flow with t-years return periods

(a) Methodology

The probable flooding flow was analysed using the HEC-HMS model, with which the hyetograph or return periods was prepared, and the peak flow was calculated.

For the rainfall used in the analysis, the hyetograph of several periods prepared in the rainfall analysis was used.

(b) Analysis results

Table 3.1.9-7 shows the flow of floodings with return periods between 2 and 100 years of the Yauca river watershed.

Likewise, Figure 3.1.9-4 shows the hydrographical map of probable flood in the Yauca river watershed. It can be noticed that the numbers in Tables 3.1.9-6 and 3.1.9-7 are similar. So, for the following flood analysis the figures of Table 3.1.9-7 were decided to be used because they match the hydrograph.

Table 3.1.9-6 Flood flow according to the return periods

(Peak flow: Reference point)

| Rivers | Return period | | | | | |
|-----------------------------------|---------------|---------|----------|----------|----------|-----------|
| | 2 years | 5 years | 10 years | 25 years | 50 years | 100 years |
| Yauca River San Francisco Alto | 24 | 37 | 90 | 167 | 263 | 400 |

(m³/s)




Figure 3.1.9-4 Hydrogram of Yauca river

3.1.10 Analysis of inundation

(1) River surveys

Prior to the flood analysis, the transversal survey of Yauca river was performed as well as the longitudinal survey of dikes. Table 3.1.10-1 shows the results of the surveys in the five rivers subject of this Study.

In order to obtain the topographic data for the analysis of the flooding zones, the results of the true measurement results indicated in Table 3.1.10-1 were used as a complement, using the satellite figures data.

Table 3.1.10-1 Basic data of the river surveys

| Survey | Unit | Quantity | Notes |
|-----------------------------|------|----------|------------------------------|
| 1. Control points survey | | | |
| Yauca river | No. | 5 | |
| 2. Dikes transversal survey | | | 250m Interval, only one bank |
| Yauca river | km | 45 | |
| 3. River transversal survey | | | 500m Interval |
| Yauca river | km | 31.9 | 91 lines x 0.35km |
| 4. Benchmarks | | | |
| Type A | No. | 5 | Every control point |
| Type B | No. | 25 | 25km x one point/km |

(1) Inundation analysis methods

Since the DGIH carried out the flood analysis of the profile study at a program level using the HEC-RAS model, for this Study, we decided to use this method, and review and modify it, if necessary.

1) Analysis basis

Normally, for the flooding analysis the following three methods are used.

- ① Varied flow unidimensional model
- ② Tank model
- ③ Varied flow horizontal bidimensional model







Figure 3.1.10-1 Idea of unidimensional model

The time and cost required by each method vary considerably, so only the most efficient method will be chosen, which guarantees the necessary accurateness degree for the preparation of the floodable zone maps.

Table 3.1.10-2 shows the characteristics of each analysis method. From the results of the simulation performed by DGIH, it is known that the rivers have a slope between 1/100 and 1/300, so initially the varied flow one-dimensional model was chosen assuming that the floods were serious. However, we considered the possibility that the overflowed water extends within the watershed in the lower watershed, so for this study the variable regimen horizontal bi-dimensional model was used to obtain more accurate results

Table 3.1.10-2 Methodology of flooding analysis

| Analysis methods | Vary flow unidimensional model | Tank model | Varied flow bi-dimensional horizontal model |
|--|--|--|---|
| Basic concept of the flood zone definition | In this method, the flood zone is considered to be included in the river bed, and the flood zone is determined by calculating the water level of the bed in relation to the maximum flooding flow | This method manages the flood zone and bed separately, and considers the flooding zone as a closed body. This closed water body is called <i>pond</i> where the water level is uniform. The flood zone is determined in relation to the relationship between the overflowed water from the river and entered to the flood zone, and the topographic characteristics of such zone (water level– capacity– surface). | This method manages the flood zones and the bed separately, and the flood zone is determined by analyzing the bidimensional flow of the behaviour of water entered to the flood zone. |
| Approach |  |  |  |
| Characteristics | It is applicable to the floods where the overflowed water runs by the flood zone by gravity; that means, current type floods. This method must manage the analysis area as a protected area (without dikes). | Applicable to blocked type floods where the overflowed water does not extend due to the presence of mountains, hills, embankments, etc. The water level within this closed body is uniform, without flow slope or speed. In case there are several embankments within the same flood zone, it may be necessary to apply the pond model in series distinguishing the internal region. | Basically, it is applicable to any kind of flood. Beside the flood maximum area and the water level, this method allows reproducing the flow speed and its temporary variation. It is considered as an accurate method compared with other methods, and as such, it is frequently applied in the preparation of flood irrigation maps. However, due to its nature, the analysis precision is subject to the size of the analysis model grids. |

2) Overflow analysis method

Figure 3.1.10-2 shows the conceptual scheme of the variable regimen horizontal bi-dimensional model.




Figure 3.1.10-2 Conceptual scheme of the overflow analysis model

(2) Discharge capacity analysis

The current discharge capacity of the beds was estimated based on the results of the river survey and applying the HEC-RAS method, which results appear in Figure 3.1.10-3. This Figure also shows the flooding flows of different return periods, which allow evaluating in what points of the Yauca river watershed flood may happen and what magnitude of flood flow may they have.




Figure 3.1.10-3(1) Current discharge capacity of Yauca River

(4) Inundation area

As a reference, Figures 3.1.10-4 show the results of the inundation area calculation in the Yauca river watershed compared to the flooding flow with a 50 year return period.




Figure 3.1.10-4 Inundation area of Yauca river (50 year period floods)

3.2 Definition of Problem and Causes

3.2.1 Problems of flood control measures in the Study Area

Based on the results of the Yauca River, the main problem on flood control was identified, as well as the structures to be protected, which results are summarized in Table 3.2.1-1.

Table 3.2.1-1 Problems and conservation measures of flood control works

| Problems | | Overflowing | | | Dike erosion | Banks erosion | Non-working intake | Non-working derivation works |
|----------------------------|---------------------|---------------|-----------------|---------------|--------------|---------------|--------------------|------------------------------|
| | | Without dikes | Sediment in bed | Lack of width | | | | |
| Structures to be protected | Agricultural lands | ○ | ○ | ○ | ○ | ○ | ○ | ○ |
| | Irrigation channels | | | | | ○ | ○ | |
| | Urban area | ○ | | ○ | | | | ○ |
| | Roads | | | | | ○ | | |
| | Bridges | | ○ | | | | | |

3.2.2 Problem causes

Next, the main problem and its direct and indirect causes for flood control in the Study Area are described:

(1) Main Problem

Valleys and local communities highly vulnerable to floods

(2) Direct and indirect causes

Table 3.2.2-2 shows the direct and indirect causes of the main problem

Table 3.2.2-2 Direct and indirect causes of the main problem

| | | | | |
|-----------------|--|--|--|--|
| Direct cause | 1. Excessive flood flow | 2. Overflowing | 3. Insufficient maintenance of control works | 4. Insufficient communitarian activities for flood control |
| Indirect causes | 1.1 Frequent occurrence of extraordinary weather (El Niño, etc..) | 2. Lack of flood control works | 3.1 Lack of maintenance knowledge and skills | 4.1 Lack of knowledge and flood prevention techniques |
| | 1.2 Extraordinary rains in the middle and upper basins | 2.2 Lack of resources for the construction of works | 3.2 Lack of training in maintenance | 4.2 Lack of training in flood prevention |
| | 1.3 Vegetation cover almost zero in the middle and upper basins | 2.3 Lack of plans for flood control in basins | 3.3 Lack of dikes and banks repair | 4.3 Lack of early warning system |
| | 1.4 Excessive sediment dragging from the upper and middle river levee | 2.4 Lack of dikes | 3.4 Lack of repair works and referral making | 4.4 Lack of monitoring and collection of hydrological data |
| | 1.5 Reduction of discharge capacity of rivers by altering slopes, etc. | 2.5 Lack of bed channel width | 3.5 Use of illegal bed for agricultural purposes | |
| | | 2.6 Accumulation of sediments in beds | 3.6 Lack of maintenance budget | |
| | | 2.7 Lack of width at the point of the bridge construction | | |
| | | 2.8 Elevation of the bed at the point of the bridge construction | | |
| | | 2.9 Erosion of dikes and banks | | |
| | | 2.10 Lack of capacity for the design of the works | | |

3.2.3 Problem Effects

(1) Main Problem

Valleys and local communities highly vulnerable to floods

(2) Direct and indirect effects

Table 3.2.3-1 shows the direct and indirect effects of the main problem

Table 3.2.3-1 Direct and indirect effects of the main problem

| Direct Effects | 1. Agriculture Damages | 2. Direct damages to the community | 3. Social infrastructure damages | 4. Other economical damages |
|------------------|--------------------------------------|---------------------------------------|--|---|
| Indirect Effects | 1.1 Agriculture and livestock damage | 2.1 Private property and housing loss | 3.1 Roads destruction | 4.1 Traffic interruption |
| | 1.2 Agricultural lands loss | 2.2 Industries and facilities loss | 3.2 Bridges loss | 4.2 Flood and evacuations prevention costs |
| | 1.3 Irrigation channels destruction | 2.3 Human life loss and accidents | 3.3 Running water, electricity, gas and communication infrastructures' damages | 4.3 Reconstruction costs and emergency measures |
| | 1.4 Work destruction and derivation | 2.4 Commercial loss | | 4.4 Work loss by local inhabitants |
| | 1.5 Dikes and banks erosion | | | 4.5 Communities income reduction |
| | | | | 4.6 Life quality degradation |
| | | | | 4.7 Loss of economical dynamism |

(3) Final effect

The main problem final effect is the community socio-economic impediment development of the affected area.

3.2.4 Causes and effects diagram

Figure 3.2.4-1 shows the causes and effects diagram done based on the above analysis results.




Figure 3.2.4-1 Causes and effects diagram

3.3 Objective of the Project

The final impact that the Project wants to achieve is to alleviate the vulnerability of valleys and local community to flooding and promote local economic development.

3.3.1 Solving measures for the main problem

(1) Main objective

Soothe the valleys and local community to flooding vulnerability.

(2) Direct and indirect measures

In table 3.3.1-1, direct and indirect solutions measures for the problem are shown.

Table 3.3.1-1 Direct and indirect solution measures to the problem

| | | | | |
|-------------------|--|--|--|---|
| Direct measures | 1. Analyze and relieve excessive flood flow | 2. Prevent overflow | 3. Full compliance with maintenance of flood control works | 4. Encourage community flood prevention |
| Indirect measures | 1.1 Analyze extraordinary weather (El Niño, etc..) | 2.1 Construct flood control works | 3.1 Strengthen maintenance knowledge and skills | 4.1 Strengthen knowledge and skills to prevent flooding |
| | 1.2 Analyze extraordinary rainfall in the upper and middle basins | 2.2 Provide resources for the works construction | 3.2 Reinforce training maintenance | 4.2 Running flood prevention training |
| | 1.3 Planting vegetation on the upper and middle basins | 2.3 Develop plans for flood control basins | 3.3 Maintain and repair dikes and banks | 4.3 Creating early warning system |
| | 1.4 Relieve Excessive sediment entrainment from the upper and middle river dikes | 2.4 Build dikes | 3.4 Repair intake and derivation works | 4.4 Strengthen monitoring and water data collection |
| | 1.5 Take steps to alleviate the reduction in discharge capacity of rivers by altering slopes, etc. | 2.5 Extends the width of the channel | 3.5 Control the illegal use of bed for agricultural purposes | |
| | | 2.6 Excavation of bed | 3.6 Increase the maintenance budget | |
| | | 2.7 Extending the river at the bridge's construction | | |
| | | 2.8 Dredging at the point of the bridge construction | | |
| | | 2.9 Control dikes and banks erosion | | |
| | | 2.10 Strengthen the capacity for works design | | |

3.3.2 Expected impacts for the main's objective fulfillment

(1) Final Impact

The final impact that the Project wants to achieve is to alleviate the vulnerability of the valleys and the local community to floods and promoting local socio-economic development.

(2) Direct and indirect impacts

In table 3.3.2-1 direct and indirect impacts expected to fulfill the main objective to achieve the final impact are shown.

Table 3.3.2-1 Direct and indirect impacts

| | | | | |
|------------------|--|--|---|---|
| Direct Impacts | 1. Agricultural damage relief | 2. Relief of direct harm to the community | 3. Relief of social infrastructure damage | 4. Relief of other economic damage |
| Indirect Impacts | 1.1 Relief to crops and livestock damage | 2.1 Housing and private properties loss prevention | 3.1 Road destruction prevention | 4.1 Traffic interruption prevention |
| | 1.2 Relief for farmland loss | 2.2 Prevention of Industries and facilities establishments | 3.2 Prevention of bridges loss | 4.2 Reducing costs of flood prevention and evacuation |
| | 1.3 Prevention of the destruction of irrigation channels | 2.3 Prevention of accidents and human life loss | 3.3 Running water, electricity, gas and communication infrastructures' relief | 4.3 Cost reduction of the reconstruction and emergency measures |
| | 1.4 Prevention of destruction works of intake and derivation | 2.4 Commercial loss relief | | 4.4 Increase of local community hiring |
| | 1.5 Dikes and banks erosion relief | | | 4.5 Community income increase |
| | | | | 4.6 Life quality improvement |
| | | | | 4.7 Economic activities development |

3.3.3 Measures - objectives – impacts Diagram

In Figure 3.3.3-1 the measures - objectives – impacts diagram is shown.




Figure 3.3.3-1 Measures - objectives – impacts diagram

4. FORMULATION AND EVALUATION

4.1 Definition of the Assessment Horizon of the Project

The Project's assessment horizon will be of 15 years, same as the one applied on the Program Profile Report. The Annex-10 of SNIP regulation stipulates that the assessment horizon should be basically 10 years; however the period can be changed in case that the project formulator (DGIH in this Project) admits the necessity of change. DGIH adopted 15 years in the Program Profile Report and OPI and DGPM approved it in March 19, 2010. In JICA's development study it should be generally 50 years, so the JICA Study Team inquired on the appropriate period to DGIH and OPI, they directed JICA Study Team to adopt 15 years. And the social evaluation in case of 50 years assessment horizon is described in Annex-14 Implementation Program of Japanese Yen Loan Project.

4.2 Supply and Demand Analysis

The theoretical water level was calculated considering flowing design flood discharge based on river cross sectional survey executed with a 500m interval, in each Watershed, considering a flood discharge with a return period of 50 years. Afterwards, the dike height was determined as the sum of the design water level plus the freeboard of dike.

This is the dike height required to prevent damages caused by design floods and represents the local community demand indicator.

The height of the existing dike or the height of the present ground is that required to prevent present flood damages, and represents the present supply indicator.

The difference between the design dike (demand) and the height of the present dike or ground represents the difference or gap between demand and supply.

Table 4.2-1 shows the averages of flood water level calculated with a return period of 50 years in "3.1.9 Run-off Analysis"; of the required dike height (demand) to control the discharge adding the design water level plus the freeboard dike; the dike height or that of the present ground (supply), and the difference between these last two (difference between demand-supply) of the river. Then, Table 4.2-2 shows the values of each point in Yauca river. The dike height or that of the present ground is greater than the required dike height, at certain points. In these, the difference between supply and demand was considered null.

Table 4.2-1 Watershed Demand and Supply

| Watershed | Dike Height / current land (supply) | | Theoretical water level with a return period of 50 years | Dike Freeboard | Required dike's height (demand) | Diff. demand/supply | |
|-----------|-------------------------------------|------------|--|----------------|---------------------------------|---------------------|------------|
| | Left bank | Right bank | | | | Left bank | Right bank |
| | ① | ② | | | | ③ | ④ |
| Yauca | 187.54 | 183.01 | 179.03 | 0.80 | 179.83 | 0.21 | 0.40 |

Preparatory study on the protection program for
valleys and rural communities vulnerable to floods in Peru
Profile Study Report (Pre-feasibility level), Yauca River

Table 4.2-2 Demand and Supply according to calculation (Yauca River)

(m)

| Distance (km) | Dike Height / current land (supply) | | Theoretical water level with a return period of 50 years ③ | Dike Freeboard ④ | Required dike's height (demand) ⑤=③+④ | Diff. demand/supply | |
|---------------|-------------------------------------|-----------------|---|---------------------|--|---------------------|---------------------|
| | Left bank ① | Right bank ② | | | | Left bank ⑥=⑤-① | Right bank ⑦=⑤-② |
| 0.0 | 4.97 | 2.94 | 2.11 | 0.80 | 2.91 | 0.00 | 0.00 |
| 0.5 | 3.27 | 1.76 | 2.37 | 0.80 | 3.17 | 0.00 | 1.41 |
| 1.0 | 10.87 | 3.64 | 3.10 | 0.80 | 3.90 | 0.00 | 0.26 |
| 1.5 | 4.97 | 4.97 | 4.10 | 0.80 | 4.90 | 0.00 | 0.00 |
| 2.0 | 5.80 | 7.83 | 4.90 | 0.80 | 5.70 | 0.00 | 0.00 |
| 2.5 | 7.47 | 7.31 | 6.96 | 0.80 | 7.76 | 0.30 | 0.45 |
| 3.0 | 14.25 | 8.72 | 8.61 | 0.80 | 9.41 | 0.00 | 0.69 |
| 3.5 | 37.20 | 10.24 | 10.62 | 0.80 | 11.42 | 0.00 | 1.17 |
| 4.0 | 27.20 | 14.89 | 13.45 | 0.80 | 14.25 | 0.00 | 0.00 |
| 4.5 | 41.61 | 16.73 | 15.01 | 0.80 | 15.81 | 0.00 | 0.00 |
| 5.0 | 48.40 | 18.05 | 17.08 | 0.80 | 17.88 | 0.00 | 0.00 |
| 5.5 | 49.60 | 21.82 | 20.69 | 0.80 | 21.49 | 0.00 | 0.00 |
| 6.0 | 66.64 | 22.59 | 22.57 | 0.80 | 23.37 | 0.00 | 0.78 |
| 6.5 | 26.15 | 27.58 | 26.44 | 0.80 | 27.24 | 1.10 | 0.00 |
| 7.0 | 31.56 | 30.44 | 29.54 | 0.80 | 30.34 | 0.00 | 0.00 |
| 7.5 | 35.06 | 33.45 | 33.74 | 0.80 | 34.54 | 0.00 | 1.09 |
| 8.0 | 55.64 | 36.76 | 36.54 | 0.80 | 37.34 | 0.00 | 0.58 |
| 8.5 | 92.42 | 42.03 | 40.95 | 0.80 | 41.75 | 0.00 | 0.00 |
| 9.0 | 47.78 | 51.89 | 43.97 | 0.80 | 44.77 | 0.00 | 0.00 |
| 9.5 | 46.33 | 47.03 | 47.70 | 0.80 | 48.50 | 2.16 | 1.47 |
| 10.0 | 63.63 | 57.95 | 50.05 | 0.80 | 50.85 | 0.00 | 0.00 |
| 10.5 | 54.18 | 54.90 | 54.33 | 0.80 | 55.13 | 0.95 | 0.23 |
| 11.0 | 58.49 | 57.64 | 58.23 | 0.80 | 59.03 | 0.55 | 1.39 |
| 11.5 | 67.51 | 65.23 | 62.01 | 0.80 | 62.81 | 0.00 | 0.00 |
| 12.0 | 78.41 | 69.53 | 64.45 | 0.80 | 65.25 | 0.00 | 0.00 |
| 12.5 | 80.32 | 87.31 | 68.29 | 0.80 | 69.09 | 0.00 | 0.00 |
| 13.0 | 71.34 | 71.52 | 71.17 | 0.80 | 71.97 | 0.63 | 0.45 |
| 13.5 | 83.84 | 83.32 | 75.46 | 0.80 | 76.26 | 0.00 | 0.00 |
| 14.0 | 79.35 | 78.03 | 78.67 | 0.80 | 79.47 | 0.12 | 1.45 |
| 14.5 | 94.44 | 83.42 | 83.15 | 0.80 | 83.95 | 0.00 | 0.53 |
| 15.0 | 103.94 | 85.08 | 86.11 | 0.80 | 86.91 | 0.00 | 1.83 |
| 15.5 | 91.45 | 93.23 | 90.89 | 0.80 | 91.69 | 0.24 | 0.00 |
| 16.0 | 103.13 | 94.80 | 95.66 | 0.80 | 96.46 | 0.00 | 1.66 |
| 16.5 | 101.27 | 99.13 | 99.45 | 0.80 | 100.25 | 0.00 | 1.12 |
| 17.0 | 105.25 | 104.77 | 105.16 | 0.80 | 105.96 | 0.71 | 1.19 |
| 17.5 | 117.49 | 114.65 | 109.53 | 0.80 | 110.33 | 0.00 | 0.00 |
| 18.0 | 115.48 | 124.95 | 112.85 | 0.80 | 113.65 | 0.00 | 0.00 |
| 18.5 | 120.59 | 118.49 | 117.47 | 0.80 | 118.27 | 0.00 | 0.00 |
| 19.0 | 122.18 | 122.34 | 121.71 | 0.80 | 122.51 | 0.32 | 0.17 |
| 19.5 | 128.61 | 130.38 | 127.62 | 0.80 | 128.42 | 0.00 | 0.00 |
| 20.0 | 132.85 | 134.29 | 132.42 | 0.80 | 133.22 | 0.37 | 0.00 |
| 20.5 | 136.79 | 141.05 | 137.34 | 0.80 | 138.14 | 1.34 | 0.00 |
| 21.0 | 146.87 | 158.06 | 141.99 | 0.80 | 142.79 | 0.00 | 0.00 |
| 21.5 | 152.18 | 167.34 | 147.07 | 0.80 | 147.87 | 0.00 | 0.00 |

Preparatory study on the protection program for
valleys and rural communities vulnerable to floods in Peru
Profile Study Report (Pre-feasibility level), Yauca River

| | | | | | | | |
|---------|--------|--------|--------|------|--------|------|------|
| 22.0 | 166.56 | 166.11 | 151.74 | 0.80 | 152.54 | 0.00 | 0.00 |
| 22.5 | 167.23 | 176.01 | 157.30 | 0.80 | 158.10 | 0.00 | 0.00 |
| 23.0 | 200.98 | 174.62 | 162.00 | 0.80 | 162.80 | 0.00 | 0.00 |
| 23.5 | 179.36 | 168.30 | 167.46 | 0.80 | 168.26 | 0.00 | 0.00 |
| 24.0 | 192.88 | 172.51 | 172.67 | 0.80 | 173.47 | 0.00 | 0.96 |
| 24.5 | 177.96 | 190.53 | 177.87 | 0.80 | 178.67 | 0.71 | 0.00 |
| 25.0 | 207.59 | 202.14 | 183.38 | 0.80 | 184.18 | 0.00 | 0.00 |
| 25.5 | 207.43 | 215.11 | 188.96 | 0.80 | 189.76 | 0.00 | 0.00 |
| 26.0 | 238.50 | 207.55 | 193.98 | 0.80 | 194.78 | 0.00 | 0.00 |
| 26.5 | 208.54 | 208.50 | 201.43 | 0.80 | 202.23 | 0.00 | 0.00 |
| 27.0 | 217.45 | 208.19 | 208.06 | 0.80 | 208.86 | 0.00 | 0.68 |
| 27.5 | 222.97 | 215.11 | 213.55 | 0.80 | 214.35 | 0.00 | 0.00 |
| 28.0 | 231.57 | 220.68 | 219.73 | 0.80 | 220.53 | 0.00 | 0.00 |
| 28.5 | 237.11 | 230.00 | 226.05 | 0.80 | 226.85 | 0.00 | 0.00 |
| 29.0 | 233.54 | 236.00 | 233.35 | 0.80 | 234.15 | 0.61 | 0.00 |
| 29.5 | 243.36 | 239.69 | 239.11 | 0.80 | 239.91 | 0.00 | 0.22 |
| 30.0 | 247.66 | 246.30 | 246.24 | 0.80 | 247.04 | 0.00 | 0.74 |
| 30.5 | 254.22 | 253.31 | 252.58 | 0.80 | 253.38 | 0.00 | 0.07 |
| 31.0 | 262.98 | 262.55 | 258.54 | 0.80 | 259.34 | 0.00 | 0.00 |
| 31.5 | 268.93 | 264.18 | 264.74 | 0.80 | 265.54 | 0.00 | 1.37 |
| 32.0 | 271.56 | 271.80 | 270.59 | 0.80 | 271.39 | 0.00 | 0.00 |
| 32.5 | 294.15 | 281.23 | 277.73 | 0.80 | 278.53 | 0.00 | 0.00 |
| 33.0 | 289.54 | 285.00 | 283.63 | 0.80 | 284.43 | 0.00 | 0.00 |
| 33.5 | 314.58 | 292.43 | 291.29 | 0.80 | 292.09 | 0.00 | 0.00 |
| 34.0 | 301.91 | 300.00 | 298.40 | 0.80 | 299.20 | 0.00 | 0.00 |
| 34.5 | 309.96 | 303.26 | 304.17 | 0.80 | 304.97 | 0.00 | 1.71 |
| 35.0 | 309.63 | 308.91 | 309.80 | 0.80 | 310.60 | 0.97 | 1.69 |
| 35.5 | 316.12 | 315.88 | 316.26 | 0.80 | 317.06 | 0.94 | 1.18 |
| 36.0 | 321.67 | 322.81 | 321.73 | 0.80 | 322.53 | 0.86 | 0.00 |
| 36.5 | 327.48 | 342.42 | 326.88 | 0.80 | 327.68 | 0.20 | 0.00 |
| 37.0 | 333.64 | 332.74 | 333.85 | 0.80 | 334.65 | 1.01 | 1.90 |
| 37.5 | 340.40 | 339.28 | 339.41 | 0.80 | 340.21 | 0.00 | 0.93 |
| 38.0 | 350.09 | 345.56 | 345.70 | 0.80 | 346.50 | 0.00 | 0.93 |
| 38.5 | 351.81 | 352.28 | 352.26 | 0.80 | 353.06 | 1.25 | 0.78 |
| 39.0 | 386.18 | 358.72 | 357.64 | 0.80 | 358.44 | 0.00 | 0.00 |
| 39.5 | 364.24 | 363.43 | 364.22 | 0.80 | 365.02 | 0.78 | 1.59 |
| 40.0 | 371.86 | 370.50 | 369.82 | 0.80 | 370.62 | 0.00 | 0.12 |
| 40.5 | 376.35 | 375.80 | 375.71 | 0.80 | 376.51 | 0.16 | 0.71 |
| 41.0 | 384.23 | 399.63 | 381.90 | 0.80 | 382.70 | 0.00 | 0.00 |
| 41.5 | 395.43 | 406.83 | 388.05 | 0.80 | 388.85 | 0.00 | 0.00 |
| 42.0 | 406.80 | 394.91 | 393.12 | 0.80 | 393.92 | 0.00 | 0.00 |
| 42.5 | 410.39 | 408.45 | 399.38 | 0.80 | 400.18 | 0.00 | 0.00 |
| 43.0 | 405.33 | 418.83 | 404.79 | 0.80 | 405.59 | 0.26 | 0.00 |
| 43.5 | 410.55 | 423.82 | 410.54 | 0.80 | 411.34 | 0.78 | 0.00 |
| 44.0 | 417.99 | 417.91 | 418.22 | 0.80 | 419.02 | 1.04 | 1.11 |
| 44.5 | 438.95 | 424.57 | 424.52 | 0.80 | 425.32 | 0.00 | 0.75 |
| 45.0 | 431.48 | 431.34 | 431.86 | 0.80 | 432.66 | 1.18 | 1.32 |
| 45.5 | 438.56 | 438.49 | 438.89 | 0.80 | 439.69 | 1.12 | 1.20 |
| 46.0 | 447.75 | 446.76 | 446.80 | 0.80 | 447.60 | 0.00 | 0.84 |
| Average | 187.54 | 183.01 | 179.03 | 0.80 | 179.83 | 0.21 | 0.40 |

4.3 Technical Planning

4.3.1 Structural Measures

As structural measures it was necessary to prepare a flood control plan for the whole Watershed. The later section 4.12 “Medium and Long Term Plan” and 4.12.1 “General Flood Control Plan” details results on the analysis. This plan proposes the construction of dikes for flood control in the entire Watershed. However, in the case of the Watershed of the Yauca River, a big project needs to be set up investing very high costs, far beyond those considered in the budget of the present Project, what makes it difficult to take this proposal. Therefore, supposing the flood control dikes in the whole Watershed are built progressively within a medium and long term plan, they would be focused on the study of more urgent and priority works for flood control.

(1) Design flood discharge

1) Guideline for flood control in Peru

The Methodological Guide for Projects on Protection and/or Flood Control in Agricultural or Urban Areas prepared by the Public Sector Multiannual Programming General Direction (DGPM) of the Economy and Finance Ministry (MEF) recommends to carry out the comparative analysis of different return periods: 25 years, 50 years and 100 years for the urban area, and 10 years, 25 years and 50 years for rural area and agricultural lands.

Considering that the present Project is focused on the protection of rural and agricultural areas, the design flood discharge should be the discharge with return period of 10year to 50-year.

2) Maximum discharge in the past and design flood discharge

The yearly maximum discharge in the watershed is as shown in Figure-4.3.1-1. Based on the figure, the maximum discharge in the past can be extracted as shown in the Table- 4.3.1-1 together with the flood discharges with different return periods.

The maximum discharge observed in the past in Yauca river is considerably less than the flood discharge with return period of 50 years, and the same class of floods occurred three times in the past.

In Peru the flood protection works in the basins are developed almost nil, therefore it is not necessary to adopt the design discharge more than the past maximum discharge. However, the large disasters occurred in the past so that the design flood discharge with return period of 50 years, which is larger than the past maximum, is to be adopted as design flood as in safe side.

The relation among flood discharge with different return period, damage caused by the floods and inundation areas is analyzed in the basin. The results are that the more the return periods of flood increase the more inundation area and damage amount increase in the basin, however the increase tendency of damage with project is more gentle compared with former two items, and the reduction of damage with project reaches to maximum in the case of the flood with return period of 50 years within the cases of flood with less return period of 50 years.

Table - 4.3.1-1 Flood discharge with different return period(m³/sec)

| Watershed | 2-year | 10-year | 25-year | 50-year | 100-year | Max.in Past |
|-----------|--------|---------|---------|---------|----------|-------------|
| Yauca | 24 | 90 | 167 | 263 | 400 | 211 |




Figure- 4.3.1-1 Yearly Max. Discharge (Yauca)


3) Relation among probable flood, Damage and inundation area

The relation among probable flood, Damage and inundation area in the watershed are shown in the Figure-4.3.1-2.

Based on the figure the following facts can be expressed.

- ① The more increase probable flood discharge, the more increase inundation area (green line in the figure).
- ② The more increase probable flood discharge, the more increase damage (red line in the figure).
- ③ According to increase of probable flood discharge, the damage with project increase gently (blue line in the figure).
- ④ According to increase of probable flood discharge, damage reduction (difference between red line and blue line) increase steadily, and it reaches maximum at the probable flood of 50- year within the scope of study.

As described above, the adopted design flood discharge with return period of 50 years is bigger than the past maximum discharge and damage reduction amount in the adopted case becomes more than that of the flood discharges with less return period. However the Project in Yauca river is to be cancelled due to low economic viability studied in the section 4.5 Social Evaluation.



Figure— 4.3.1-2 Probable Flood Discharge, Damage Amount and Inundation Area (Yauca river)

(2) Topographical Uplift

The topographical survey was carried out in selected places for the execution of structural measurements (Table 4.3.1-1). The preliminary design of control works was based on these topographical survey results.

Table 4.3.1-1 Summary of Topographical Survey

| River | Location (No.) | Installations | Topo lift. | Transversal Lifting (S=1/200) | | |
|--------------|----------------|-------------------|-------------|-------------------------------|-------------------|------------------|
| | | | (ha) | Line No. | Middle length (m) | Total length (m) |
| Yauca | Ya-1 | Dike | 5.0 | 11 | 50.0 | 550 |
| | Ya-2 | Dike & excavation | 10.0 | 6 | 200.0 | 1,200 |
| | Ya-3 | Dike | 12.5 | 26 | 50.0 | 1,300 |
| | Ya-4 | Reservoir | 10.0 | 6 | 200.0 | 1,200 |
| | Ya-5 | Dike | 2.5 | 6 | 50.0 | 300 |
| | Ya-6 | Dike | 2.0 | 5 | 50.0 | 250 |
| Total | | | 42.0 | 60 | | 4,800 |

(3) Selection of control works against priority floods

1) Basic Guidelines

For the selection of priority flood protection works, the following elements were considered:

- Demand from the local community (based on historical flood damage)
- Lack of discharge capacity of river channel (including the sections affected by the scouring)
- Conditions of the adjacent area (conditions in urban areas, farmland, etc.).
- Conditions and area of inundation (type and extent of inundation according to inundation analysis)
- Social and environmental conditions (important local infrastructures)

Based on the river survey, field investigation, discharge capacity analysis of river channel, inundation analysis, and interviews to the local community (irrigation committee needs, local governments, historical flood damage, etc...) a comprehensive evaluation was made applying the five evaluation criteria listed above. After that we selected a total of six (6) critical points (with the highest score in the assessment) that require flood protection measures.

Concretely, since the river cross sectional survey was carried out every 500m interval and discharge capacity analysis and inundation analysis were performed based on the survey results, the integral assessment was also done for sections of 500 meters. This sections have been assessed in scales of 1 to 3 (0 point, 1 point and 2 points) and the sections of which score is more than 6 were selected as prioritized areas. The lowest limit (6 points) has been determined also taking into account the budget available for the Project in general

Table 4.3.1-3 details evaluated aspects and assessment criteria.

Table 4.3.1-3 Assessment Aspects and Criteria

| Assessment Aspects | Description | Assessment Criteria |
|---|---|---|
| Demand of local population | <ul style="list-style-type: none"> ● Flood damages in the past ● Demand of local population and producers | <ul style="list-style-type: none"> • Flooding area with big floods in the past and with great demand from local community (2 points) • Demand of local population (1 point) |
| Lack of discharge capacity (bank scouring) | <ul style="list-style-type: none"> ● Possibility of river overflow given the lack of discharge capacity ● Possibility of dike and bank collapse due to scouring | <ul style="list-style-type: none"> • Extremely low discharge capacity (discharge capacity with return period of 10 years or less) (2 points) • Low discharge capacity (with return period of less than 25 years) (1 point) |
| Conditions of surrounding areas | <ul style="list-style-type: none"> ● Large arable lands, etc. ● Urban area, etc. ● Assessment of lands and infrastructure close to the river. | <ul style="list-style-type: none"> • Area with large arable lands (2 points) • Area with arable lands mixed with towns, or big urban area (2 points) • Same configuration as the previous one, with shorter scale (1 point) |
| Inundation conditions | <ul style="list-style-type: none"> ● Inundation magnitude | <ul style="list-style-type: none"> • Where overflow extends on vast surfaces (2 points) • Where overflow is limited to a determined area (1 point) |
| Socio-environmental conditions (important structures) | <ul style="list-style-type: none"> ● Intake of the irrigation system, drinking water, etc. ● Bridges and main roads (Carretera Panamericana, etc.) | <ul style="list-style-type: none"> • Where there are important infrastructures for the area (2 points) <p>Where there are important infrastructures (but less than the first ones) for the area (regional roads, little intakes, etc.) (1 point)</p> |

2) Selection results

Figure 4.3.1-3 details assessment results of each the river, as well as the selection results of flood protection priority works.

Yauca river is characterized due to its overflowing tendency at km 7 downwards the intake, flooding right bank crops. Therefore the flood prevention works are to be inundation prevention work for farmland in the section downstream of 7km and conservation works for intake and regional road eroded by scouring with high priority.

Table 4.3.1-8 Selected sections bases to execute works (Yauca River)

| No | Location | Basis of Selection |
|----|-------------------------------|--|
| ① | | <p>The existing dikes in this section may be destroyed due to the erosion caused during floods; so, repair and bank protection works must be executed</p> <p>[Characteristics of the section]</p> <ul style="list-style-type: none"> ●The overflow water from the lower section swept away the olives ●Section in which the existing dike has to be repaired <p>[Elements to Protect]</p> <ul style="list-style-type: none"> ○Agricultural lands of the right bank <p>[Method of Protection]</p> <p>In this section the conservation of olive field which is special product in this region is main target. The bank protection is to be executed utilizing the existing dike eroded by the past flood with same scale of the flood with return period of 50-years.</p> |
| ② | 3.5km ~ 7.5km (right bank) | <p>Inundation occurred at km 7 downstream from river mouth, spreading farm land of the right bank. Excavation of the riverbed has to be carried out to maintain the necessary discharge capacity at the road bridge</p> <p>[Characteristics of the section]</p> <ul style="list-style-type: none"> ●Narrow section (where the road bridge is) in which the discharge capacity is reduced ●Section on which sediments have deposited due to damming up caused by the narrowness ●Section in which the water level can be reduced due to the riverbed excavation <p>[Elements to Protect]</p> <ul style="list-style-type: none"> ○ Agricultural lands of the right bank in the section (olive field of regional special product) <p>[Method of Protection]</p> <p>The riverbed excavation is to be executed considering the balance of upstream and downstream flood protection works as well as aiming at lowering the water level in the upstream section.</p> |
| ③ | | <p>Inundation occurred at km 7 downstream from river mouth, spreading farm land of the right bank. The existing dike in this section may be destroyed due to the erosion caused during floods; so, repair and bank protection works must be executed</p> <p>[Characteristics of the section]</p> <ul style="list-style-type: none"> ●Both sides of dikes are partially constructed. Sand and gravel material is embanked there empirically and annually ●Floods swept away part of the olives ●The existing dikes have to be repaired to prevent inundation on right bank <p>[Elements to Protect]</p> <ul style="list-style-type: none"> ○ Agricultural lands of the right bank <p>[Method of Protection]</p> |

| | | |
|---|------------------------------|---|
| | | In this section the conservation of olive field which is special product in this region is main target. The bank protection is to be executed utilizing the existing dike eroded by the past flood with same scale of the flood with return period of 50-years. |
| ④ | 25.0km~25.7km (total) | In this section the intake is constructed, however it is not working properly due to the enlarged private property of the left bank to the river, and floods flow into the intake directly, sediment deposit and destruction of intake, therefore the appropriate river section is to be secured considering comprehensive flow condition in this section . [Characteristics of the section] ●Section in which it is important to protect the intakes functioning ●Section in which it is important to maintain the river's section delimitating it from the left bank [Elements to Protect] ○Intake [Method of Protection] ▼The most important intake in this river. In case that the function of it is damaged, the influence to the region will be serious, therefore the protection work is to be implemented not to cause the damage in the past flood of 210m ³ /sec which is almost equal the flood with return period of 50-year. ▼It is difficult to take water due to sediment deposit, and the private property enlarges at the left bank to the river causing direct inflow to the intake in flooding, therefore the appropriate layout of river is to be planned considering comprehensive flow condition in this section . |
| ⑤ | | This section formulates bending and quick flow at the right bank, which is causing bank erosion. If no adequate measure is taken, the eroded bank may disturb the regional road located on the upper section of the right bank resulting in stop of traffic. So, it is necessary to take erosion control actions, such as bank protection works for conservation of the road. [Characteristics of the section] ●Right bank's progressive erosion (the main road is located on the upper section) ●Section in which bank erosion control together with regional road conservation should be performed [Elements to Protect] ○Regional road of the right bank [Method of Protection] ▼In case that the regional main road is destroyed , the influence to the region will be serious, therefore the protection work is to be implemented not to cause the damage in the past flood of 210m ³ /sec which is almost equal the flood with return period of 50-year. ▼If it is left as it is, the bank will be eroded resulting in destruction of road, therefore the erosion protection work such as groin is to be implemented. |
| ⑥ | 40.9km~41.3km (left bank) | The intake located on the upper watershed of the Yauca River is an important facility to ensure drinking water for local population. However, erosion still affects the upstream left bank of the intake, also affecting regional road located on the upper part of the left bank. So, it is urgent to take action on the erosion control of this section. [Characteristics of the section] |

| | | |
|--|--|--|
| | | <ul style="list-style-type: none"> ● Section in which the base of the road that runs upstream and downstream the intake is eroded. ● Section in which bank erosion control works as well as regional road conservation should be performed. <p>[Elements to Protect]</p> <ul style="list-style-type: none"> ○ Intake ○ Regional road of the left bank <p>[Method of Protection]</p> <ul style="list-style-type: none"> ▼ The intake is the most important facility in this river. In case that the function of the facility is lost, the influence to the region will be serious, therefore the protection work is to be implemented not to cause the damage in the past flood of 210m³/sec which is almost equal the flood with return period of 50-year. ▼ If the erosion to the important intake for securing drinking water and regional main road will progress, there is possibility to hinder intake of drinking water and destruction of regional main road, therefore the erosion protection work is to be executed. |
|--|--|--|

(4) Location of priority works on flood control

In Figure 4.3.1-4 the location of prioritized flood control works is indicated in the watershed and in the Table- 4.3.1-5 the summary of flood control works is indicated..




Figure 4.3.1-4 Prioritized flood control works in Yauca River

Table 4.3.1-5 Summary of Facilities

| Basin | Location | | Preservation Object | Counter Measure | Summary of Facility | Objective Section | |
|-------|----------|----------|---------------------|-------------------|--------------------------|----------------------------|--|
| Yauca | 1 | 4.5k下流 | Inundation | Crop land (olive) | Rehabilitation of dike | 3.5km~7.5km(total) | |
| | 2 | 4.1km | Narrow Section | | Riverbed excavation | | Ex. width: 100m Ex. depth: 1.0m L: 500m |
| | 3 | 4.5~7.0k | Inundation | | Rehabilitation of dike | | Top W: 4.0m H: 2.0m Slope: 1:3 L: 2,500m |
| | 4 | 25.0k | Intake | Crop land (olive) | Rehabilitation of intake | 25.0km~25.7km(total) | |
| | 5 | 25.0k | Intake | | Revetment | | H: 2.0m Slope: 1:2 L: 500m |
| | 6 | 41km | Intake | Road | Revetment | H: 2.0m Slope: 1:2 L: 400m | 40.9~41.3km(left bank) |

(5) Standard section of the dike

1) Width of the crown

The width of the dike crown was defined in 4 meters, considering the dike stability when facing design overflows, width of the existing dike, and width of the access road or that of local communication.

2) Dike structure

The dike structure has been designed empirically, taking into account historic disasters, soil condition, condition of surrounding areas, etc.

Dikes are made of soil in all the Watersheds. Although there is a difference in its structure varying from area to area, this can be summarized as follows, based on the information given by the administrators interviewed:

- ① The gradient of the slope is mainly 1:2 (vertical: horizontal relationship); the form may vary depending on rivers and areas.
- ② Dike materials are obtained from the river bed in the area. Generally these are made of sand/gravel ~sandy soil with gravel, of reduced plasticity. As to the resistance of the materials, we cannot expect cohesiveness.
- ③ The Watershed of the Cañete River is made of loamy soil with varied pebble, relatively compacted.
- ④ The lower stretch of the Sullana weir of the Chira River is made of sandy soil mixed with silt. Dikes have been designed with a “zonal-type” structure where material with low permeability is placed on the riverside of the dike and the river; material with high permeability is placed on landside of the dike. However, given the difficulty to obtain material with low permeability, it has been noticed that there is lack of rigorous control of grain size distribution in supervision of construction.
- ⑤ When studying the damaged sections, significant differences were not found in dike material or in the soil between broken and unbroken dike. Therefore, the main cause of destruction has been water overflow.
- ⑥ There are groins in the Chira and Cañete rivers, and many of them are destroyed. These are made of big rocks, with filler material of sand and soil in some cases, what may suggest that destruction must be caused by loss of filler material.
- ⑦ There are protection works of banks made of big rocks in the mouth of the Pisco River. This structure is extremely resistant according to the administrator. Material has been obtained from quarries, 10 km. away from the site.

Therefore, the dike should have the following structure.

- ① Dikes will be made of material available in the zone (river bed or banks). In this case, the material would be sand and gravel or sandy soil with gravel, of high permeability. The stability problems forecasted in this case are as follows.
 - i) Infiltrate destruction caused by piping due to washing away fine material
 - ii) Sliding destruction of slope due to infiltrate pressure

In order to secure the stability of dike the appropriate standard section should be determined by infiltration analysis and stability analysis for sliding based on unit weight, strength and permeability of embankment material.

- ② The gradient of the slope of the dike will be between $30^\circ \sim 35^\circ$ (angle of internal friction) if the material to be used is sandy soil with low cohesiveness. The stable gradient of the slope of an embankment executed with material with low cohesiveness is determined as: $\tan\theta = \tan\phi/n$ (where “ θ ” is gradient of the slope; “ ϕ ” is angle of internal friction and “ n ” is 1.5 ,safety factor).

The stable slope required for an angle of internal friction of 30° is determined as: V:H=1:2.6 ($\tan\theta=0.385$).

Taking into consideration this theoretical value, a gradient of the slope of 1:3.0 was considered, with more gentle inclination than the existing dikes, considering the results of the discharge analysis, the prolonged time of the design flood discharge (more than 24 hours), the fact that most of the dikes with slope of 1:2 have been destroyed, and the relative resistance in case of overflow due to unusual flooding.

The infiltration analysis and stability analysis of dike based on the soil investigation and martial tests are not performed in this Study so that the slope is determined by simple stability analysis assuming the strength factors of dike material estimated by field survey of material and by adding some safety allowance.

And the slope of dike in Japan is generally 1:2.0 in minimum, however the average slope will be more than 1:3.0 because the dike has several steps in every interval of 2m~3m of height.

- ③ The dike slope by the riverside must be protected for it must support a fast water flow given the quite steep slope of the riverbed. This protection will be executed using big stones or big rocks easily to get in the area, given that it is difficult to get connected concrete blocks.

The size of the material was determined between 30cm and 1m of diameter, with a minimum protection thickness of 1m, although these values will be determined based on flow speed of each river.

3) Freeboard of the dike

The dike is made of soil material, and as such, it generally turns to be a weak structure when facing overflow. Therefore, it is necessary to prevent water overflow, to a lower water rise than the design discharge. So it is necessary to keep a determined freeboard when facing a possible increase in water level caused by the waves by the wind during water rise, tidal, hydraulic jump, etc. Likewise, it is necessary that the dikes have sufficient height to guarantee safety in surveillance activities and flood protection work , removal of logs and other carryback material, etc.

Table 4.3.1-6 shows guidelines applied in Japan regarding freeboard. Although in Peru there is

a norm on freeboard, it has been decided to apply the norms applied in Japan, considering that rivers in both countries are alike.

Table-4.3.1-6 Design discharge and freeboard

| Design discharge | Freeboard |
|---|-----------|
| Less than 200 m ³ /s | 0.6m |
| More than 200 m ³ /s, less than 500 m ³ /s | 0.8m |
| More than 500 m ³ /s, less than 2,000 m ³ /s | 1.0 m |
| More than 2,000 m ³ /s, less than 5,000 m ³ /s | 1.2 m |
| More than 5,000 m ³ /s, less than 10,000 m ³ /s | 1.5 m |
| More than 10,000 m ³ /s | 2.0 m |




Figure 4.3.1-5 Standard dike section

4.3.2 Nonstructural measures

4.3.2.1 Reforestation and vegetation recovery

(1) Basic policies

The Reforestation and Vegetation Recovery Plan satisfying the goal of the present Project can be classified in: i) reforestation along fluvial works; and ii) reforestation in the high Watershed. The first one contributes directly to flood control and expresses its effect in short time. The second one demands a huge investment and an extended time, as detailed in the later section 4.12 “Medium and long term Plan”, 4.12.2 “Reforestation Plan and Vegetation Recovery”, what makes not feasible to implement it in the present Project. Therefore, the analysis is here focused only in option i).

(2) Reforestation plan along fluvial structures

This proposal consists in planting trees along fluvial structures such as protection works of banks, dikes, etc.

- a) Objective: Reduce impact of river overflow when water rise occurs or when river narrowing is produced by the presence of obstacles, by means of vegetation borders between the river and the elements to be protected.
- b) Methodology: Create vegetation borders of a certain width between fluvial structures and the river.
- c) Work execution: Plant vegetation at a side of the fluvial structures (dikes, etc.)
- d) Maintenance post reforestation: The maintenance will be assumed by irrigator commissions by own initiative.





Figure 4.3.2.1-1 Conceptual Diagram Forestry in the Riverside structures (A Type)
 (Source: JICA Study Team)

(3) Reforestation Plan Measure

1) Structure (forestry location)

In Peru the most common location for forestry is with equilateral triangles. This project also uses this model by planting trees with 3-meter intervals. If this method is used, it is expected that trees will act to stop and cushion even 1-meter diameter rocks, for what rows will be quadrupled, thus increasing their effectiveness. However, the main goal is to avoid overflow surpass the limit; in case floods strike directly with plants sowed, good results might be expected.



(Source: JICA Study Team)

Figure 4.3.2.1-3 Location of the forestry design plan in the riverside structure

2) Species to be forested

Species to be planted along the river were selected applying the following criteria and submitted to an overall assessment.

- ① Species with adequate properties to grow and develop in the riverside (preferably native)
- ② Possibility of growing in plant nurseries
- ③ Possibility of wood and fruit use
- ④ Demand of local population
- ⑤ Native species (preferably)

After making a land survey, a list of planted or indigenous species of each zone was firstly made. Then, a list of species whose plants would grow in seedbeds, according to interviews made to plant growers, was prepared.

Priority was given to the aptitude of local conditions and to plant production precedents, leaving

as second priority its usefulness and demand or if they were native species or not. Table 4.3.2.1-1 shows the assessment criterion.

Table 4.3.2.1-1 Assessment criterion for forest species selection

| | | Assessment Criterion | | | | |
|-------------------|---|--|-------------------------------------|--|---|-----------------|
| | | 1 | 2 | 3 | 4 | 5 |
| Assessment points | A | In situ testing (natural or reforested growth) | Major production | Possible use as wood or for fruit production | Water demand by the Users Committee, among others | Local specie |
| | B | Growth has not been checked in situ, however it adapts in the zone | Sporadic production | Possible use as wood or for fruit production | There is NO water demand by the Users Committee | No local specie |
| | C | None of the above | Possible reproduction but not usual | No use as wood nor fruit | — | — |
| | D | Unknown | Not produced | Unknown | — | — |

(Source: JICA Study Team)

Table-4.3.2.1-2 shows a list of selected species applying this assessment criterion. © marks main species, ○ are those species that would be planted with a proportion of 30% to 50%. This proportion is considered to avoid irreversible damages such as plagues that can kill all the trees.

Table 4.3.2.1-2 Selection of forest species

| Watershed | Forest species |
|-----------|--|
| Yauca | Eucalipto (©), Huarango (○), Casuarina (○) |

In the Cañete Watershed the main forestry specie is Eucalyptus. This specie adapts very well in this area, it adapts to the zone and has high demand by the Water User's Committees. Huarango (*Prosopis limensis*: is how this plant is known in the northern region of Peru, comes from another seed) is a native specie from the southern region of Peru. It is planted along the Panamericana Highway. Casuarinas specie has been planted in this area to protect from wind and sand, moreover for the lands near farms.

3) Volume of the Reforestation Plan

The forestry plan has been selected as it is mentioned in the location and type of species plan, in the dikes and rockfill, sedimentation wells along the riverside. The width of the forest is 11 meters; and within sand reservoir, tree will be planted excepting on the normal water route.

Following Table 4.3.2.1-3 shows the construction estimating for the Forestry and Recovery of Vegetation Cover Plan for Yauca Watershed.

**Table 4.3.2.1-3 Construction estimating for the forestry and vegetation cover recovery plan
(Along the river)**

| N° | Location (bank) | Length (m) | Width (m) | Area (ha) | Quantity (unit) | Distribution according to the specie (units) | | | |
|-------------|-----------------|------------|-----------|-----------|-----------------|--|----------|-----------|--------|
| | | | | | | Eucalyptus | Huarango | Casuarina | (m) |
| Ya-1 | General | 1.000 | 11 | 1,1 | 3.256 | 1.628 | 977 | 651 | 3.256 |
| Ya-2 | General | | | 0,0 | 0 | — | — | — | — |
| Ya-3 | General | 2.500 | 11 | 2,8 | 8.288 | 4.144 | 2.486 | 1.658 | 8.288 |
| Ya-4 | | 0 | 11 | 0,0 | 0 | — | — | — | — |
| Ya-5 | Right | 500 | 11 | 0,6 | 1.776 | 888 | 533 | 355 | 1.776 |
| Ya-6 | Right | 400 | 11 | 0,4 | 1.184 | 592 | 355 | 237 | 1.184 |
| Yauca Total | | 4.400 | | 4,9 | 14.504 | 7.252 | 4.351 | 2.901 | 14.504 |

(Source: JICA Study Team)

4) Areas subject to the Reforestation and Vegetation Recovery Plan

In areas subject to the Reforestation/Vegetation Recovery Plan along fluvial works, the structure arrangement is similar everywhere. See section 4.5.1.3(2).

5) Execution costs of the Reforestation and Vegetation Recovery Plan

Execution costs of works for the Reforestation and Vegetation Recovery Plan were estimated as follows:

- Planting unitary cost (planting unitary cost + transportation)
- Labor cost

Planting providers may include i) AGRORURAL or ii) private providers. For reforestation along rivers private providers will be requested.

For labor unitary cost estimation, common labor unitary cost is proposed to be applied for riverside reforestation.

i) Planting unitary cost

Planting unitary cost was defined as detailed in Table 4.3.2.1-4, based on information obtained through interviews to private providers. Given that planting prices and transportation cost varies per provider, an average was applied.

Table 4.3.2.1-4 Unitary cost of plants

ii) Labor cost

iii) Reforestation execution cost

Work costs for the forestry and vegetation cover recovery plan in the riverside structures are detailed in Table 4.3.2.1-5.

Table 4.3.2.1-5 Forestry work cost

6) Implementation process plan

The Process Plan of forestry works in riverbanks is part of the coastal structure, thus the same will be considered for the Construction Plan of the Coastal Structure. Forestry works should generally start at the beginning of the rainy season or just before, and must end approximately one month before the season finishes. However, there is scarce rain in the coastal area; therefore there is no effect of dry and rainy seasons. For the sake of forestry, it is most convenient is to take advantage of water rise, but according to the Construction Process Plan of the coastal structure there are no major forestry issues in seasons where water level is low, if the execution schedule of water structures require so. The gravity irrigation system can only be used to irrigate just planted plants during approximately the first 3 months until water level rises. This irrigation is performed using perforated horse which is a field technique actually carried out in Poechos dam area.

4.3.2.2 Sediment Control Plan

(1) Importance of the Sediment Control Plan

Below flood control issues in selected Watersheds are listed. Some of them relate to sediment control. In the present Project an overall flood control plan covering both the high and the low

Watershed is prepared. The study for the preparation of the Sediment Control Plan comprised the whole Watershed.

- Water rise causes overflow and floods.
- Rivers have a steep slope of 1/30 to 1/300. The flow speed is high, as well as the sediment transport capacity.
- The accumulation of large quantities of dragged sediment and the consequent elevation of the river bed aggravate flood damages.
- There is a great quantity of sediment accumulated on the river bed forming a double sandbank. The water route and the spot of greater water impact are unstable, causing route change and consequently, change of spot of greater water impact.
- Riverside is highly erodible, causing a decrease of adjacent farming lands, destruction of regional roads, etc., for what they should be duly protected.
- Big stones and rocks cause damages and destruction of water intakes.

(2) Sediment Control Plan (structural measures)

The sediment control plan suitable for the present sediment movement pattern was analyzed. Table 4.3.2.2-1 details basic guidelines.

Table 4.3.2.2-1 Basic guidelines of the Sediment Control Plan

| Conditions | Typical year | Precipitations with 50-year return period |
|-------------------|---|---|
| Sediment dragging | Bank erosion and river bed change | Bank erosion and river bed change Sediment flow from ravines |
| Measures | Erosion control → Bank protection Control of riverbed variation → compaction of ground, bands (compaction of ground in the alluvial cone, bands) | Erosion control → bank protection Riverbed variation control → compaction of ground, bands (compaction of ground in the alluvial cone, bands) Sediment flow → protection of slopes, sediment control dams |




Figure 4.3.2.2-1 Sediment control works

1) Sediment control plan in the upper Watershed

The next section 4.12 “Medium and long term Plan” 4.12.3 “Sediment Control Plan” details

the sediment control plan covering the whole Upper Watershed. This plan will require an extremely long time with huge costs, what makes it quite not feasible. Therefore, it must be executed progressively within the medium and long term.

2) Sediment control plan in the low Watershed

The riverbed fluctuation analysis is as shown below. The average bed height has been increasing in the river, so basically it is concluded that this is the general trend. The total variation volume of the bed and sediment transport is not so much in Yauca river,

| | |
|--|-------|
| Total volume of dragged sediment (in thousands of m ³) | 1,192 |
| Annual average of dragged sediment (in thousands of m ³) | 23.8 |
| Total volume of riverbed variation (in thousands of m ³) | 685 |
| Annual average of variation of riverbed height (m) | 0.1 |

While the variation of the bed (volume of sediment) is great too, looking at the average height of the bed, only 0.1 meters has changed in 50 years, and is therefore considered that the entry of sediments won't affect much the river downstream. Therefore, it is considered that the urgent sediment control actions are not required at present although the monitoring the riverbed variation and the maintenance of river channel depending on the monitoring results will be required.

4.3.3 Technical Assistance

Based on the proposals on flood control measures, a component on technical assistance is proposed in order to strengthen risk management capabilities in the Program.

(1) **Component objective**

The component objective in the Program is the "Adequate capability of local population and professionals in risk management application to reduce flood damages in Watersheds".

(2) **Target area**

The target area for the implementation of the present component is the Yauca watershed.

In the execution stage, the implementation has to be coordinated with local authorities in the watershed. However, each authority has to execute those activities related with the characteristics of the watershed to carry out an adequate implementation.

(3) **Target population**

Target populations will represent irrigator associations and other community groups, provincial, district and local community governments and local people in the watershed, considering the limited capacity to receive beneficiaries of this component.

Participants are those with skills to widespread technical assistance contents of local populations in the watershed.

Besides, the participation of women has to be considered because currently only few ones participate in technical assistance opportunities.

(4) **Activities**

In order to achieve the above purpose, the following 3 components of study and training is to be carried out.

Component 1: Knowledge on River Bank Protection Actions in consideration of Agriculture and Natural Environment

| | |
|--------------|--|
| Course | a) River Bank Operation and Maintenance b) River Bank Plant Management c) Erosion Prevention and Mitigation Natural Resource Management |
| Objectives | a) In this project, local populations learn suitable technology to operate and give maintenance to constructions and works from prior projects. b) Local populations learn suitable technology on river bank plants and vegetation for flooding control purposes. c) Local populations learn suitable technology on erosion and natural resources for flooding control purposes. |
| Participants | a) Engineers and / or technicians from local Governments b-c) Engineers and / or technicians from local Governments and Water Users Associations, Community representatives |
| Times | a) 12 times in all (every six (6) hours) b) 12 times in all (every five (5) hours) c) 26 times in all (every three (3) hours) |
| Lecturers | a) Contractors of constructions and works, Engineers from MINAG and / or the Regional Government b-c) Engineers from MINAG and / or the Regional Government, College professors (From universities, institutes, NGOs, etc.) |
| Contents | a-1) Suitable operation and maintenance technology for constructions and works from prior projects a-2) Suitable operation and maintenance technology for constructions and works in this project b-1) River bank protection with the use of plants b-2) The importance of river bank vegetation in flooding control b-3) Types of river bank plants and their characteristics c-1) Evaluation of the erosion conditions c-2) Evaluation of natural resource conditions c-3) Erosion approach for flooding control c-4) Natural resource approach for flooding control c-5) Environmental consideration approach c-6) Use of water resources c-7) Alternatives for suitable farming crops |

Component 2: Preparation of Community Disaster Management Plan for Flood Control

| | |
|--------------|--|
| Course | a) Risk management Plan Formulation b) Detailed Risk management Plan Formulation |
| Objectives | a) Local populations gain knowledge and learn technology to prepare a flooding control plan b) Ditto |
| Participants | a-c) Engineers and / or technicians from local Governments and Water Users Associations, Community representatives |
| Times | a) 19 times in all (every four (4) hours) b) 34 times in all (every five (5) hours) c) 24 times in all (every five (5) hours) |
| Lecturers | a-c) Engineers from MINAG and / or the Regional Government, Community Development Expert, Facilitator (local participation) |
| Contents | a-1) Flooding control plan preparation manuals a-2) Current condition analyses for flooding control a-3) Community development alternatives by means of local participation a-4) Workshop for flooding control plan preparation b-1) Community activity planning in consideration of ecological zoning b-2) Risk management b-3) Resource management |

| | |
|--|--|
| | c-1) Preparation of community disaster management plan c-2) Joint activity with local governments, users' association, etc. |
|--|--|

Component 3: Basin Management for Anti – River Sedimentation Measures

| | |
|--------------|--|
| Courses | a) Hillside Conservation Techniques b) Forest Seedling Production c) Forest Seedling Planting d) Forest Resource Management and Conservation |
| Objectives | a) Local populations learn suitable technology on hillside conservation for flooding control purposes b) Local populations learn suitable technology on forest seedling production c) Local populations learn suitable technology on forest seedling planting d) Local populations learn suitable technology on forest resource management and conservation |
| Participants | a-d) Engineers and / or technicians from local Governments and Water Users Associations, Community representatives and Local People |
| Times | a) 12 times in all (every five (5) hours) b-d) 40 times in all for three (3) “Courses on Basin Management for Anti - River Sedimentation Measures” (every five (5) hours) |
| Lecturers | a-d) Engineers from MINAG and / or the Regional Government, College professors (From universities, institutes, NGOs, etc.) |
| Contents | a-1) Soil characteristics and conservation on hillsides a-2) Hillside agroforestry system a-3) Animal herding system on hillsides a-4) Reforestation with traditional vegetation and plants a-5) Hillside conservation and alleviation alternatives b-1) A selection of plants that are suitable to the local characteristics b-2) Forest seedling production technology b-3) Control carried out by the local population's involvement c-1) Candidate areas for forestation c-2) Forest plantation control technology c-3) Forest plantation soil technology c-4) Control carried out by the local population's involvement d-1) Forestation for flooding control purposes d-2) Forest plantation control technology d-3) Forest plantation output technology d-4) Control carried out by the local population's involvement |

(5) Direct cost and period

The direct cost for the above activities is as shown in the Table 4.3.3-1. The total cost for the objective basin is estimated as soles, and the brake down of the unit cost is as shown in the Annex-12, Appendix No.5. And the period required for study and training is assumed to be as same as the construction period of 2 years.

Table 4.3.3-1 Contents of technical assistance and direct cost

(6) Implementation Plan

The Hydraulic Infrastructure General Direction (DGIH-MINAG) executes this

component as the executing unity in cooperation with the Agriculture Regional Direction (DRA), the Board of Users and related Institutions. In order to execute the activities efficiently the following has to be considered:

- For the implementation of the present component, the DGIH-MINAG will coordinate actions with the Central Management Unit responsible for each Watershed, as well as with Regional Managements of Agriculture (DRA).
- For the Project administration and management, the DGIH-MINAG will coordinate actions with PSI-MINAG (Sub-sector Irrigation Program with extensive experience in similar projects).
- Considering there are some local governments that have initiated the preparation of a similar crisis management plan through the corresponding civil defense committee, under the advice of the National Institute of Civil Defense (INDECI) and local governments, the DGIH-MINAG must coordinate so that these plans be consistent with those existing in each Watershed.
- Training courses will be managed and administered by irrigator associations (particularly the unit of skills development and communications) with the support of local governments in each Watershed, to support timely development in each town.
- Experts in disaster management departments in each provincial government, ANA, AGRORURAL, INDECI, etc., as well as (international and local) consultants will be in charge of course instruction and facilitation.

4.4 Costs

4.4.1 Cost Estimate (at private prices)

(1) Project Costs Components

Project costs include the following:

① Work direct costs = total number of works by type × unit price

② Common provisional works = ① × 10%

③ Construction cost -1 = ① + ②

④ Miscellaneous = ③ × 15%

⑤ Benefits = ③ × 10%

⑥ Construction cost -2 = ③ + ④ + ⑤

⑦ Tax = ⑥ × 18% (IGV)

⑧ Construction cost = ⑥ + ⑦

⑨ Environmental measures cost = ⑧ × 1%

⑩ Detailed design cost = ⑧ × 5%

⑪ Works supervision cost = ⑧ × 10%

⑫ Project Cost = ⑧ + ⑨ + ⑩ + ⑪

(2) Work direct costs

On table 4.4.1-1 a summary table of direct costs for structural measures is presented for the Yauca River Watershed.

(3) Project Costs

The project cost is estimated in 20.9 million of soles as shown in Table 4.4.1-2. It includes reforestation and vegetation recovery costs, construction of early warning system and technical assistance. The annual operation and maintenance cost of completed works is approximately 0.5% of the project's cost.

Table 4.4.1-1 Summary Table of the work's direct cost (at private prices)

Table 4.4.1-2 Construction cost (at private prices)

4.4.2 Cost Estimate (at social prices)

(1) Work direct costs

In Table 4.4.2-1 a summary table of direct costs for structural measures is presented for the Yauca River watershed. The works' direct cost at private prices was turned into social prices applying the conversion factor.

(2) Project Costs

The project cost is estimated in 16,8 million of soles as shown in Table 4.4.2-2. It includes reforestation and vegetation recovery costs, construction of early warning system and technical assistance, before converting from private prices.

Table 4.4.2-1 Summary Table of the work's direct cost (at social prices)

Table 4.4.2-2 Construction cost at (social prices)

4.5 Social Assessment

4.5.1 Private prices costs

(1) Benefits

Flood control benefits are flood loss reduction that would be achieved by the implementation of the Project and is determined by the difference between the amount of loss with and without Project. Specifically, in order to determine the benefits that will be achieved by the works' construction. First, the flood amount per flood loss of the different return periods (between 2 to 50 years) is calculated; assuming that the flood control works have a useful life of 50 years. To finish, determine the annual average amount of the loss reduction from the loss amount of different return periods. The Methodological Guideline for Protection and/or Flood Control Projects in agricultural or urban areas, 4.1.2p-105) establishes similar procedures.

Above find the description of the procedures to determine concrete benefits

- Determine the flood loss amount in the flood area by analyzing the magnitude of overflow that occurs without the Project for each return period (between 2 and 50 years)
- After, determine the amount of flood loss in the flood area by analyzing the magnitude of overflow that occurs when flood control priority works are built (Yauca 1 to 6).
- Determine the difference between ① and ②. Add the benefits of other works different than dikes (intakes, roads and dams protection, etc.) in order to determine the total profits

“Benefits of the Project” are considered as the sum of direct loss amount caused by overflow and indirect loss caused by the destruction of structures in vulnerable sections (farmland loss, interruption of traffic, etc.)

1) Method of loss amount calculation

In this study, the amount of loss from direct and indirect damages to the variables listed in Table 4.5.1-1 was determined.

Table 4.5.1-1 Flood loss amount calculation variables

| Loss | Variables | Description |
|--------------|--------------------------|---|
| (1) Direct | ① Crops | <ul style="list-style-type: none"> • Crops in flooding season The amount of crop loss by flooding is determined by multiplying the damage % regarding water depth and the number of days flooded • Agricultural land and infrastructure (channels, etc.) • Crop loss amount is determined by multiplying the damage % regarding water depth and the number of days flooded |
| | ② Hydraulic Works | <ul style="list-style-type: none"> • Loss amount due to hydraulic structures destruction (intakes, channels, etc.). |
| | ③ Road Infrastructures | <ul style="list-style-type: none"> • Flood damage related to road infrastructure is determined by the damage in transport sector |
| | ④ Housing | <ul style="list-style-type: none"> • Residential and industrial buildings It is calculated applying the loss coefficient depending on the flood depth Housing: residential and industrial buildings; household goods: furniture, household appliances, clothing, vehicles, etc. Flood damages in housing, commercial buildings, assets and inventories (buildings and assets) is determined applying the loss coefficient according to the flood depth |
| | ⑤ Public Infrastructures | <ul style="list-style-type: none"> • Determine the loss amount in roads, bridges, sewers, urban infrastructures, schools, churches and other public facilities • Determine the loss amount in public works by applying the correspondent coefficient to the general assets loss amount |
| | ⑥ Public Services | <ul style="list-style-type: none"> • Electricity, gas, water, rail, telephone, etc. |
| (2) Indirect | ① Agriculture | <ul style="list-style-type: none"> • Estimate the loss caused by irrigation water interruption due to the damage of hydraulic structures • Determine the construction and repair costs of hydraulic structures such as direct year costs |
| | ② Traffic Interruption | <ul style="list-style-type: none"> • Estimate the loss lead by traffic interruption due to damages on flooded roads • Determine road’s repair and construction costs as damage direct cost |

A. Direct loss

Direct loss is determined by multiplying the damage coefficient according to the flood depth as the asset value.

B. Indirect Loss

Indirect loss is determined taking into account the impact of intakes and damaged roads. Below, calculation procedures are described.

a. Dams damage

The loss amount due to dam damage is calculated by adding the direct loss (dam's rehabilitation and construction) and the indirect loss amount (harvest loss due to the interruption of irrigation water supply)

① Calculating the infrastructure cost

Works Cost = construction cost per water unit taken × size (flow, work length)

Unit cost of the work: for intakes and channels, it is required to gather information on the water intake volume of the existing work and the works' execution cost (construction or repair). The unit cost is calculated by analyzing the correlation among them both.

It was estimated that the work will be completely destroyed by the flow with a return period of 10 years.

② Crop loss

Annual earnings are determined according to the crops grown in the correspondent irrigation district.

Annual Profit = (crops selling - cost) × frequency of annual harvest

Crop Sale = planted area (ha) × yield (kg/ha) × transaction unit price

Cost = unit cost (s/ha) × planted area (ha)

b. Road infrastructure damage

Determine the loss due to traffic interruption.

Amount of loss = direct loss + indirect loss

Direct loss: road construction cost (construction, rehabilitation)

Indirect Loss: opportunity loss cost due to road damage (vehicle depreciation + staff expenses loss)

Then, a 5 days period takes place of non-trafficability (usually in Peru it takes five days to complete the rehabilitation of a temporary road)

2) Loss estimated amount according to disasters in different return periods

In table 4.5.1-2 the amounts of loss with and without Project are shown. These are estimated for disasters of different return periods in the Yauca River.

Table 4.5.1-2 Loss Estimated Value (at private prices)

s./ 1,000

| Case | t | Yauca |
|-----------------|--------------|---------------|
| Without Project | 2 | 0 |
| | 5 | 0 |
| | 10 | 1,695 |
| | 25 | 2,569 |
| | 50 | 11,497 |
| | Total | 15,761 |
| With Project | 2 | 0 |
| | 5 | 0 |
| | 10 | 7 |
| | 25 | 1,005 |
| | 50 | 2,028 |
| | Total | 3,040 |

3) Loss amount (annual average) expected to be reduced by the Project

The annual average loss amount that is expected to be reduced by the Project by the total annual average loss amount occurred as flow multiplying the amount of loss reduction occurred as flow for the corresponding flood probabilities.

Considering that floods happen probabilistically, the annual benefit is determined as the annual average amount of loss reduction. Next find the procedures of calculation.

Table 4.5.1-3 Loss reduction annual average amount

| Probabilities | Loss Amount | | | Average path's loss | Paths' Probabilities | Loss reduction annual average amount |
|--|-----------------|--------------|-------------------------|---|----------------------------|--------------------------------------|
| | Without Project | With Project | Loss Reduction | | | |
| 1/1 | | | $D_0 = 0$ | | | |
| 1/2 | L_1 | L_2 | $D_1 = L_1 - L_2$ | $(D_0 + D_1)/2$ | $1 - (1/2) = 0,500$ | $d_1 = (D_0 + D_1)/2 \times 0,67$ |
| 1/5 | L_3 | L_4 | $D_2 = L_3 - L_4$ | $(D_1 + D_2)/2$ | $(1/2) - (1/5) = 0,300$ | $d_2 = (D_1 + D_2)/2 \times 0,300$ |
| 1/10 | L_5 | L_6 | $D_3 = L_5 - L_6$ | $(D_2 + D_3)/2$ | $(1/5) - (1/10) = 0,100$ | $d_3 = (D_2 + D_3)/2 \times 0,100$ |
| 1/20 | L_7 | L_8 | $D_4 = L_7 - L_8$ | $(D_3 + D_4)/2$ | $(1/10) - (1/20) = 0,050$ | $d_4 = (D_3 + D_4)/2 \times 0,050$ |
| 1/30 | L_9 | L_{10} | $D_5 = L_9 - L_{10}$ | $(D_4 + D_5)/2$ | $(1/20) - (1/30) = 0,017$ | $d_5 = (D_4 + D_5)/2 \times 0,017$ |
| 1/50 | L_{11} | L_{12} | $D_6 = L_{11} - L_{12}$ | $(D_5 + D_6)/2$ | $(1/30) - (1/50) = 0,013$ | $d_6 = (D_5 + D_6)/2 \times 0,013$ |
| 1/100 | L_{13} | L_{14} | $D_7 = L_{13} - L_{14}$ | $(D_6 + D_7)/2$ | $(1/50) - (1/100) = 0,010$ | $d_7 = (D_6 + D_7)/2 \times 0,010$ |
| Foreseen average annual amount of loss reduction | | | | $d_1 + d_2 + d_3 + d_4 + d_5 + d_6 + d_7$ | | |

In Table 4.5.1-4 Results of loss amount calculus are presented (annual average), which are expected to be reduced when implementing the Project in the Yauca River Watershed.

Table 4.5.1-4 Annual average damage reduction amount (at private prices)

s/1000

| 流域 Watershed | 流量規模 Return Period | 超過確率 Probability | 被害額 (Total damage - thousands of S/.) | | | 区間平均被害 額 ④ Damage Average | 区間確率 ⑤ Probability incremental value | 年平均被害額 ④×⑤ Average value of the damages flow | 年平均被害額の 累計=年平均被 害軽減期待額 Annual Medial Damage |
|-----------------|--------------------------|---------------------|---------------------------------------|----------------|-------------------------------|---------------------------------------|--|--|---|
| | | | 事業を実施し ない場合① | 事業を実施し た場合② | 軽減額 ③=①-② | | | | |
| | | | Without Project ① | With Project | Mitigated damages ③=①-② | | | | |
| YAUCA | 1 | 1.000 | 0 | 0 | 0 | | | 0 | 0 |
| | 2 | 0.500 | 0 | 0 | 0 | 0 | 0.500 | 0 | 0 |
| | 5 | 0.200 | 0 | 0 | 0 | 0 | 0.300 | 0 | 0 |
| | 10 | 0.100 | 1,695 | 7 | 1,688 | 844 | 0.100 | 84 | 84 |
| | 25 | 0.040 | 2,569 | 1,005 | 1,564 | 1,626 | 0.060 | 98 | 182 |
| | 50 | 0.020 | 11,497 | 2,028 | 9,469 | 5,517 | 0.020 | 110 | 292 |

(2) Social Assessment

1) Assessment's objective and indicators

The social assessment's objective in this Study is to evaluate investment's efficiency in structural measures using the analysis method of cost-benefit (C/B) from the national economy point of view. For this, economic assessment indicators were determined (relation C/B, Net Present Value - NPV and IRR). The internal return rate (IRR) is an indicator that denotes the efficiency of the project's investment. It is the discount rate to match the current value of the project's generated cost regarding the benefit's current value. It is the discount rate necessary so the Net Present Value (NPV) equals zero and the relation C/B equals one. It also indicates the percentage of benefits generated by such investment. The internal return rate used in the economic assessment is called "economical internal return rate (EIRR)". The market price is turned into the economical price (costs at social prices) eliminating the impact of market distortion.

The IRR, C/B relation and NPV are determined applying mathematical expressions shown in the Table below. When IRR is greater than the social discount rate, the relation C/B is greater than one and NPV is greater than zero, it is considered that the project is efficient from the national economic growth point of view.

Table 4.5.1-5 Analysis assessment indicators of cost-benefit relation and its characteristics

| Indicators | Definition | Characteristics |
|--|---|--|
| Net Present Value (NPV) | $NPV = \sum_{i=1}^n \frac{B_i}{(1+r)^i} - \sum_{i=1}^n \frac{C_i}{(1+r)^i}$ | <ul style="list-style-type: none"> - Allows comparing net benefit magnitude performed by the project - It varies depending on the social discount rate |
| Cost-Benefit Relation (C/B) | $B/C = \sum_{i=1}^n \frac{B_i}{(1+r)^i} / \sum_{i=1}^n \frac{C_i}{(1+r)^i}$ | <ul style="list-style-type: none"> - Allows comparing the investment efficiency by the magnitude of benefit per investment unit - Varies depending on the social discount rate |
| Economical Internal Return Rate (EIRR) | $\sum_{i=1}^n \frac{B_i}{(1+r)^i} = \sum_{i=1}^n \frac{C_i}{(1+r)^i}$ | <ul style="list-style-type: none"> - Allows knowing the investment efficiency comparing it to the social discount rate - Does not vary depending on the social discount rate |
| Where Bi: benefit per "i" year / Ci: cost per "i" year / r: social discount rate (11 %) / n: years of assessment | | |

2) Assumptions

Next, find the assumptions of every indicator used from the economical assessment

i) Assessment Period

The assessment period is set between 2013 and 2027 (15 years after construction works started). This Project implementing schedule is the following:

- 2012: Detailed Design
- 2013-2014: Construction
- 2013-2027: Assessment Period

ii) Standard Conversion Factor (SCF)

The standard conversion factor (SCF) is the relationship between socioeconomic prices established along the border and national private prices of all goods in a country's economy. It is used to convert goods and services prices purchased in the local market at affordable prices. In this Study the following SCF values were used:

- Dams 0.804
- Gabions 0.863
- Intakes 0.863

TAX (Peruvians use IGV) is not taken into account in the conversion of market prices to socioeconomic prices.

iii) Other preliminary conditions

- Price level: 2011
- Social discount rate: 10%

Annual maintenance cost: 0.5% of construction cost

3) Cost-benefit relation analysis (C/B)

A comparison of the total cost and total benefit of flood control works converted to present values applying the social discount rate was performed. In this case, the total cost is the addition of construction, operation and maintenance costs. The total benefit is the loss amount that was reduced due to the works. For this, a base year was established for the conversion into the current value at the moment of the assessment, and the assessment period was set for the next 15 years from the beginning of the Project. The total cost was determined adding-up the construction, operation and maintenance costs of the works converted into present values; and the total benefit adding-up the annual average loss amount turned into current values.

In table 4.5.1-6 results of calculations C/B, NPV and IRR to private prices is shown.

Table 4.5.1-6 Social Assessment (C/B, NPV, IRR) (at private prices)

4.5.2 Costs at social prices

(1) Benefits

1) Estimated loss amount according to different return periods

In table 4.5.2-1 the amounts of loss with and without Project are shown. These are estimated for disaster of different return periods in the Yauca River Watershed.

Table 4.5.2-1 Estimated loss amount (at social prices)

| 千ソールレス | | |
|-----------------------------------|----------|---------|
| Case ケース | t 確率年 | Cañete |
| Without Project 事業を実施 しない場合 | 2 | 2,582 |
| | 5 | 10,558 |
| | 10 | 105,137 |
| | 25 | 144,972 |
| | 50 | 213,134 |
| | Total | 476,384 |
| With Project 事業を実施 した場合 | 2 | 272 |
| | 5 | 1,024 |
| | 10 | 9,908 |
| | 25 | 14,260 |
| | 50 | 20,117 |
| | Total | 45,580 |

2) Loss amount (annual average) is expected to be reduced with the Project

In table 4.5.2-2 results of loss amount calculation (annual average) that are expected to reduce to implement the Project in the Yauca River are shown.

Table 4.5.2-2 Annual average damage reduction amount (at social prices)

s/1000

| 流域 Watershed | 流量規模 Return Period | 超過確率 Probability | 被害額 (Total damage - thousands of S/.) | | | 区間平均被害 額 ④ Damage Avergare | 区間確率 ⑤ Probability incremental value | 年平均被害額 ④×⑤ Average value of the damages flow | 年平均被害額の 累計=年平均被 害軽減期待額 Annual Medial Damage |
|-----------------|--------------------------|---------------------|---------------------------------------|----------------|-------------------------------|--|--|--|---|
| | | | 事業を実施し ない場合① | 事業を実施し た場合② | 軽減額 ③=①-② | | | | |
| | | | Without Project ① | With Project | Mitigated damages ③=①-② | | | | |
| YAUCA | 1 | 1.000 | 0 | 0 | 0 | | 0 | 0 | |
| | 2 | 0.500 | 0 | 0 | 0 | 0.500 | 0 | 0 | |
| | 5 | 0.200 | 0 | 0 | 0 | 0.300 | 0 | 0 | |
| | 10 | 0.100 | 2,150 | 9 | 2,141 | 1,071 | 0.100 | 107 | 107 |
| | 25 | 0.040 | 3,313 | 1,341 | 1,972 | 2,057 | 0.060 | 123 | 230 |
| | 50 | 0.020 | 12,092 | 2,653 | 9,439 | 5,706 | 0.020 | 114 | 345 |

(2) Social Assessment

In table 4.5.2-3 results of the calculation C/B, NPV and IRR at social prices are shown.

Table 4.5.2-3 Social Assessment (C/B, NPV, IRR) (at social prices)

4.5.3 Social assessment conclusions

The social assessment shows that the Project in Yauca River watershed has extremely low economic impact on private and social prices. However, the following economical non-quantifiable positive impacts are shown:

- Contribution to local economic development when soothing the fear due to economic activities suspension and damage
- Contribution by increasing local employment opportunities for the construction of the project
- Strengthening the local population's awareness for floods damage and other disasters
- Income increase contributions due to an stable agricultural production because flood damages are soothed
- Increase of agricultural land price

From the results of the economic evaluation presented above, it is difficult to implement this

Project, even if there is the positive effects of the Project that are difficult to quantify in economic values.

4.6 Sensitivity Analysis

(1) Objective

A sensitivity analysis was made in order to clarify the uncertainty due to possible changes in the future of the socioeconomic conditions. For the cost-benefit analysis it is required to foresee the cost and benefit variation of the project, subject to assessment, to the future. However, it is not easy to perform an adequate projection of a public project, since this is characterized for the long period required from planning to the beginning of operations. Also because of the long useful life of works already in operation and the intervention of a number of uncertainties that affect the future cost and benefit of the project. So, analysis results are obtained frequently and these are discordant to reality when the preconditions or assumptions used do not agree with reality. Therefore, for the uncertainty compensation of the cost-benefit analysis it should be better to reserve a wide tolerance-bank, avoiding an absolute and unique result. The sensitivity analysis is a response to this situation.

The objective of the sensitivity analysis is to provide the cost-benefit analysis results a determined bank that will allow a proper managing of the project's implementation, give numbers to the population and achieve greater accuracy and reliability of the project's assessment results.

(2) Sensitivity Analysis

1) General description of the sensitivity analysis

There are three methods of the sensitivity analysis, as indicated in Table 4.6-1.

Table 4.6-1 Sensitivity Analysis Methods

| Methods | Description | Products |
|--------------------------------|--|---|
| Variables sensitivity analysis | It consists in changing only one predetermined variable (precondition or hypothesis), to assess how the analysis result is affected | Bank values from the analysis when a precondition or hypothesis varies |
| Better and worst alternatives | It consists in defining the cases in which the analysis results are improved or worsen when changing the main pre-established preconditions or hypothesis to assess the analysis result bank | Bank values from the analysis when the main precondition or hypothesis vary |
| Monte Carlo | It consists in knowing the probability distribution of the analysis results by simulating random numbers of Monte Carlo simulation of pre-established preconditions and hypothesis | Probable results distribution when all main precondition or hypothesis vary |

2) Description of the sensitivity analysis

In this project the sensitivity analysis method of the variables usually used in public works investments was adopted. Next, the scenarios and economic indicators used in the sensitivity analysis are shown.

Table 4.6-2 Cases subjected to the sensitivity analysis and economic indicators

| Indicators | Variation bank according to factors | Economic indicators to be evaluated |
|----------------------|---|-------------------------------------|
| Construction cost | In case the construction cost increases in 5 % and 10 % | IRR, NPV, C/B |
| Benefit | In case of reducing the benefit in 5 % and 10 % | IRR, NPV, C/B |
| Social discount rate | In case of increase and reduction of the discount social rate in 5 % respectively | NPV, C/B |

3) Results of the sensitivity analysis

In table 4.6-3 the results of the sensitivity analysis of each assessed case to private and social prices is shown.

Table 4.6-3 Results of the sensitivity analysis of IRR, C/B and NPV

| | Watershed | Variables | Base Case | Case 1 | Case 2 | Case 3 | Case 4 | Case 5 | Case 6 |
|----------------|-----------|-----------|--------------|------------------|-------------------|----------------------|-----------------------|---------------------------|----------------------------|
| | | | | Cost increase 5% | Cost increase 10% | Benefit reduction 5% | Benefit reduction 10% | Discount rate increase 5% | Discount rate increase 10% |
| Private prices | YAUCA | IRR (%) | - | - | - | - | - | - | - |
| | | B/C | 0.09 | 0.09 | 0.08 | 0.09 | 0.08 | 0.07 | 0.12 |
| | | NPV(s) | (17,059,601) | (17,998,368) | (18,937,135) | (17,145,388) | (17,231,175) | (16,296,088) | (17,760,074) |
| Social prices | YAUCA | IRR (%) | - | - | - | - | - | - | - |
| | | B/C | 0.13 | 0.13 | 0.12 | 0.13 | 0.12 | 0.10 | 0.18 |
| | | NPV(s) | (13,083,633) | (13,838,957) | (14,594,281) | (13,184,775) | (13,285,917) | (12,649,776) | (13,357,212) |

(3) Assessment of the sensitivity analysis

The impact of socioeconomic conditions changes to the Project, has shown that the variation of economic effect indicators are small, however the indicators of base case itself show very low viability of this Project.

4.7 Sustainability Analysis

This project will be co-managed by the central government (through the DGIH), irrigation committees and regional governments. Also, the project cost will be covered with the respective contributions of the three parties. Usually the central government (in this case, the DGIH) takes the 80%, irrigation commissions 10% and regional governments 10%. However, the percentages of the contributions of these last two are decided through discussions between both parties. On the other hand, the operation and maintenance (O & M) of the completed works is assumed by the irrigation committee. So, the sustainability of the project depends on the profitability of the Project and the ability of the irrigation committees for O & M.

Table 4.7-1 presents the data of the budget for irrigation committees of Yauca River Watershed in recent years.

Table 4.7-1 Project Budget of the irrigation commissions

| River | Annual Budget | | | |
|-------|---------------|------------|------------|---------|
| | 2006 | 2007 | 2008 | Average |
| Yauca | 114,482.12 | 111,102.69 | 130,575.40 | 118,720 |

(1) Profitability

The project in Yauca river Watershed is insufficiently profitable and sustainable. The investment amount in this watershed is estimated in million soles at private prices. However, the C/B relation is 0.13, the NPV is estimated in – 13.0 million soles and the internal return rate is almost nil at social prices. These Figures show that the project's economic efficiency is very low.

(2) Cost of operation and maintenance

The annual cost of operation and maintenance required for the project, having as a base year 2008 is estimated at soles, corresponding to % of the project construction cost. On the other hand, the average operating expenses for the last 3 years of the irrigation commissions was 118,700 soles.

When considering that the annual operation and maintenance cost represents 75.9% of the annual irrigation commissions budget, the project would not be sustainable according to the financial capacity of these committees to maintain and operate the constructed works.

4.8 Environmental Impact

4.8.1 Procedure of Environmental Impact Assessment


Projects are categorized in three scales, based on the significance level of the negative and positive impacts, and each sector has an independent competence on this categorization. The following table shows the environmental management instruments that are required for each category. The Project holder should submit the Environmental Impact Statement (DIA, in Spanish) for all Projects under Category I. The project holder should prepare an EIA-sd or an EIA-d if the Project is categorized under Category II or III, respectively, to be granted the Environmental Certification from the relevant Ministry Directorate.

Table 4.8.1-1 Project Categorization and Environmental Management Instruments

| | Description | Required Environmental Management Instrument |
|--------------|--|---|
| Category I | It includes those Projects that when carried out, they cause no significant negative environmental impacts whatsoever. | PEA that is considered a DIA after the assessment for this category |
| Category II | It includes those Projects that when carried out, they can cause moderate environmental impacts, and their negative effects can be removed or minimized through the adoption of easily applicable measures. | Semi-Detailed Environmental Impact Assessment (EIA-sd) |
| Category III | It includes those Projects than can cause significant quantitative or qualitative negative environmental impacts because of their characteristics, magnitude and/or location. Therefore, a deep analysis is required to revise those impacts and set out a relevant environmental management strategy. | Detailed Environmental Impact Assessment (EIA-d) |

Source: Prepared by the JICA Study Team based on the SEIA Law (2001)

The next graph shows the Environmental Document's Classification, the Environmental Document's Assessment, and the Environmental Certification.



Source: Prepared by the JICA Study Team based on the SEIA Regulations (2009)

Figure 4.8.1-1 Process to Obtain the Environmental Certification

First, the Project holder applies for the Project classification, by submitting the Preliminary Environmental Assessment (PEA). The relevant sector assesses and categorizes the Project within the next 30 working days after the document's submission. The Project's PEA that is categorized under Category I becomes an EID, and those Projects categorized under Category II or III should prepare an EIA-sd or EIA-d, as applicable. There are cases in which the relevant sector prepares the Terms of Reference for these two studies, and submits them to the holder. There are other cases in which the holder prepares the Terms of Reference and these are approved by the relevant sector, based on the interview with DGAA. Number of working days required for EIA-sd revision and approval is 90, and number of working days required for EIS-d is 120; however, these maximum deadlines may be extended.

The progress of the environmental impact study is as shown below.

The JICA Study Team subcontracted a local Consultant (CIDE Ingenieros S.A.), and a Preliminary Environmental Assessment (PEA) was carried out, from December 2010 to January 2011 for Yauca river.

EAP for the Yauca river was submitted to DGIH from JICA on January 25, 2011. DGIH submitted the EAP to DGAA on July 19, 2011.

EAP for Yauca river was examined by DGAA, and DGAA issued their comments on EAP to DGIH. JICA Study Team revised EAP upon the comments and submitted it to DGAA on September 21, 2011. DGAA completed examination on the revised EAP and issued approval letter on Yauca river in which DGAA classified Yauca river into Category I. Therefore the additional environmental impact analysis for Yauca river is not required.

The positive and negative environmental impact associated with the implementation of this project was confirmed and evaluated, and the plan for prevention and mitigation measures are prepared by EAP results, field investigation and hearing by JICA Study Team.

The proposed works in this project include: the reparation of existing dikes, construction of new dikes, riverbed excavation, bank protection works, repair and improvement of the derivation and intakes works, and also river expansion. Table 4.8.1-2 describes “working sites” to be considered in the Environmental Impact section for Pisco river.

Table 4.8.1-2 Works Description

| Basin | Location | | Preservation Object | Counter Measure | Summary of Facility | Objective Section | |
|-------|----------|----------|---------------------|------------------------|--|------------------------------|-----------------------|
| Yauca | 1 | 4.5k下流 | Inundation | Rehabilitation of dike | Top W; 4.0m H; 2.0m Slope; 1:3 L; 1,000m | 3.5km~7.5km (total) | |
| | 2 | 4.1km | Narrow Section | Riverbed excavation | Ex. width; 100m Ex. depth; 1.0m L; 500m | | |
| | 3 | 4.5~7.0k | Inundation | Rehabilitation of dike | Top W; 4.0m H; 2.0m Slope; 1:3 L; 2,500m | | |
| | 4 | 25.0k | Intake | Crop land (olive) | Rehabilitation of intake | Weir W; 100m H; 3.0m T; 2.0m | 25.0km~25.7km (total) |
| | 5 | 25.0k | Intake | Crop land (olive) | Revetment | H; 2.0m Slope; 1:2 L; 500m | |
| | 6 | 41km | Intake | Road | Revetment | H; 2.0m Slope; 1:2 L; 400m | |
| | | | | | | 40.9~41.3km(left bank) | |

Source: JICA Study Team

4.8.2 Methodology

In order to identify environmental impacts of the works to be executed in the different watersheds, we developed identification impact matrixes for watershed.

First, the operation and activities for each project based on typical activities of “hydraulic works” construction were determined. Afterwards, the concrete activities type was determined which will be executed for each work that will be developed in the watersheds. Then, to evaluate Socio-environmental impacts the Leopold matrix was used.

Table 4.8.2-1 Evaluation Criterion - Leopold Matrix

| Index | | Description | Valuation |
|----------------------------------|---------------------|---|--------------------------------|
| "Na" nature | | It defines whether change in each action on the means is positive or negative | Positive (+) : beneficial |
| | | | Negative (-): harmful |
| Probability of Occurrence "P.O." | | It includes the probability of occurrence of the impact on the component | High (>50 %) = 1.0 |
| | | | Medium (10 – 50 %) = 0.5 |
| | | | Low (1 – 10 %) = 0.2 |
| Magnitude | Intensity (In) | It indicates the magnitude of change in the environmental factor. It reflects the degree of disturbance | Negligible (2) |
| | | | Moderate intensity (5) |
| | | | Extreme Disturbance (10) |
| | Extension "Ex" | It indicates the affected surface by the project actions or the global scope on the environmental factor. | Area of indirect influence: 10 |
| | | | Area of direct influence: 5 |
| | | | Area used up by the works: 2 |
| | Duration "Du" | It refers to the period of time when environmental changes prevail | > 10 years: 10 |
| | | | 5 – 10 years : 5 |
| | | | 1 – 5 years: 2 |
| | Reversibility "Rev" | It refers to the system's capacity to return to a similar, or an equivalent to the initial balance. | Irreversible: 10 |
| | | | Partial return: 5 |
| | | | Reversible: 2 |

Source: Prepared based on PEAs of 6 Basins

Table 4.8.2-2 Impact Significance Degrees

| SIA | Extent of Significance |
|-----------|------------------------|
| ≤ 15 | Of little significance |
| 15.1 - 28 | Significant |
| ≥ 28 | Very significant |

Source: Prepared based on PEAs of 6 Basins

4.8.3 Identification, Description and Social Environmental Assessment

(1) Identification of social environmental impacts

In the following matrix (construction/operation stages) in the watershed, elaborated based on the report analysis of the Preliminary Environmental Assessment.

Table 4.8.3-1 Impact Identification Matrix (Construction and Operation Stage) – Yauca River

| Construction Stage | | | Work | 1-6 | 1-6 | 1-6 | 1-6 | 4-6 | 1,2,3 | 1,3,4,5,6 | 1-6 | 1-6 | 1-6 | 1-6 | 1-6 | Total Negative | Total Positive |
|--|--------------|------------------------------|----------|-------------------|--|------------------------------------|------------------------------|-----------------------------------|-----------------------------------|-------------------------|--|----------|----------------|-----------------|--|----------------|----------------|
| Environment | Component | Environmental Factors | Activity | Labor Recruitment | Site preparation work (Clearing, land grading, Levelled) | Diversion of riverbed (Cofferdams) | Digging and movement of Land | Digging and refilling in riverbed | Digging and refilling in riverbed | Civil Work (Concreting) | I&O of stone pits and material production plants | DME I&O | Camps work I&O | Carrriage Staff | Transportation of machinery, equipment, materials and supplies | | |
| Physique | Air | PM-10 (Particulate matter) | | N | N | N | N | N | N | N | N | N | N | N | N | 9 | 0 |
| | | Gas emissions | | N | N | N | N | N | N | N | N | N | N | N | N | 10 | 0 |
| | Noise | Noise | | N | N | N | N | N | N | N | N | N | N | N | N | 11 | 0 |
| | | Soil fertility | | N | | | | | | | | N | N | | | 3 | 0 |
| | Soil | Land Use | | N | | | | | | | N | N | | | 3 | 0 | |
| | | Calidad del agua superficial | | | N | | | N | N | | N | | | | | 5 | 0 |
| | Water | Cantidad de agua superficial | | | | | | | | N | | | N | | | 2 | 0 |
| | | Morfología fluvial | | | N | | | N | N | | N | | | | | 4 | 0 |
| | Physiography | Morfología terrestre | | | N | | N | | | | | N | | | | 3 | 0 |
| | | Terrestrial flora | | | N | | | | | | | N | | | | 2 | 0 |
| Biotic | Flora | Aquatic flora | | | | | | | N | | N | | | | 2 | 0 | |
| | | Terrestrial fauna | | N | | | | | | | N | | | | 2 | 0 | |
| | Fauna | Aquatic fauna | | | N | | | N | N | | N | | | | 4 | 0 | |
| | | Visual landscape | | | | | | | | | N | N | | | | 2 | 0 |
| Socio-economic | Social | Quality of life | P | | | | | | | | | N | N | N | 3 | 1 | |
| | | Vulnerability - Security | | | | | | | | | | | | | | 0 | 0 |
| | Economic | PEA | P | | | | | | | | | | | | | 0 | 1 |
| Current land use | | | | | | | | | | | | | | | 0 | 0 | |
| Total | | | | 2 | 8 | 6 | 4 | 6 | 7 | 4 | 10 | 9 | 3 | 4 | 4 | 65 | 2 |
| Percentage of positive and negative | | | | | | | | | | | | | | | | 97 % | 3 % |

| Operation Stage | | | Works | Repaired Dike Point 1 | Riverbed without Silling Point 2 | Repaired Dike Point 3 | Intake Point 4 | Protection Point 5 | Protection - Left Side Point 6 | Total Negative | Total Positive |
|--|--------------|------------------------------|----------|-----------------------|----------------------------------|-----------------------|----------------|--------------------|--------------------------------|----------------|----------------|
| Physique | Air | PM-10 (Particulate matter) | | | | | | | | 0 | 0 |
| | | Gas emissions | | | | | | | | 0 | 0 |
| | Noise | Noise | | | | | | | | 0 | 0 |
| | | Soil fertility | | | | | P | P | | 0 | 2 |
| | Soil | Land Use | | | | | | | | 0 | 0 |
| | | Calidad del agua superficial | | | | P | P | P | | 0 | 3 |
| | Water | Cantidad de agua superficial | P | P | P | P | | | | 0 | 4 |
| | | Morfología fluvial | N | N | N | | | | | 3 | 0 |
| | Physiography | Morfología terrestre | | | | | | | | 0 | 0 |
| | | Terrestrial flora | | | | | | | | 0 | 0 |
| Biotic | Flora | Aquatic flora | | | | | | | 0 | 0 | |
| | | Terrestrial fauna | | | | | | | 0 | 0 | |
| | Fauna | Aquatic fauna | N | N | N | | | | | 3 | 0 |
| | | Visual landscape | P | P | P | | P | P | | 0 | 5 |
| Socio-economic | Social | Quality of life | P | P | P | P | P | P | 0 | 6 | |
| | | Vulnerability - Security | P | P | P | P | P | P | | 0 | 6 |
| | Economic | PEA | P | P | P | P | P | P | | 0 | 6 |
| Current land use | | | | | | | | | 0 | 0 | |
| Total | | | 7 | 7 | 7 | 5 | 6 | 6 | 6 | 32 | |
| Percentage of positive and negative | | | | | | | | | 16 % | 84 % | |

N: Negative, P:Positive

Source: Prepared by the JICA Study Team

On the Yauca River basin, based on the impact identification results for the construction stage, a total number of 67 interactions have been found. 65 of these interactions (97 %) correspond to impacts that will be perceived as negative, and 2 (3 %) correspond to impacts that will be perceived as positive. In addition, 38 interactions have been found for the operation stage; 6 of these interactions (16 %) correspond to impacts that will be perceived as negative, and 32 (84 %) correspond to impacts that will be perceived as positive.

(2) Environmental and Social Impact Assessments

Environmental and social impacts are assessed with the methodology that was explained in 4.8.2 Methodology. The following tables show the environmental and social assessment results for the basin, during the construction and operation stages.

Table 4.8.3-2 Environmental Impact Assessment Matrix – Yauca River

| | | | The Yauca River Basin | | | | | | | | | | | | | | | | |
|----------------|--------------|------------------------------|-----------------------|--|-----------------------------------|------------------------------------|-----------------------------------|-------------------------|--|---------|----------------|---------------|--|-----------------|-------|-------|------|------|------|
| Medio | Componente | Acciones del proyecto | Construction Stage | | | | | | | | | | | Operation Stage | | | | | |
| | | | Labor Recruitment | Site preparation work (Clearing, land grading, Levelled) | Diversion of riverbed (Coferdams) | Digging and refilling in riverside | Digging and refilling in riverbed | Civil Work (Concreting) | I&O of stone pits and material production plants | DME I&O | Camps work I&O | Carnage Staff | Transportation of machinery, equipment, materials and supplies | Ya1 | Ya2 | Ya3 | Ya4 | Ya5 | Ya6 |
| | | | | | | | | | | | | | | | | | | | |
| Physique | Air | PM-10 (Particulate matter) | 0.0 | -15.0 | -11.5 | -12.0 | -12.0 | 0.0 | -18.0 | -18.0 | 0.0 | -12.0 | -12.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | | Gas emissions | 0.0 | -11.5 | -11.5 | -11.5 | -11.5 | -11.5 | -15.0 | -11.5 | 0.0 | -11.5 | -11.5 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | Noise | Noise | 0.0 | -12.0 | -15.0 | -15.0 | -15.0 | -15.0 | -15.0 | -15.0 | -15.0 | -15.0 | -15.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | | Soil | Soil fertility | 0.0 | -14.5 | 0.0 | 0.0 | 0.0 | 0.0 | -14.2 | -14.2 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 31.0 | 31.0 |
| | Water | Land Use | 0.0 | -14.2 | 0.0 | 0.0 | 0.0 | 0.0 | -15.0 | -15.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| | | Calidad del agua superficial | 0.0 | 0.0 | -17.5 | -15.0 | -23.0 | -14.5 | -15.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 28.0 | 31.0 | 31.0 |
| | Physiography | Cantidad de agua superficial | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | -9.0 | 0.0 | 0.0 | -15.0 | 0.0 | 0.0 | 26.0 | 31.0 | 26.0 | 26.0 | 0.0 | 0.0 |
| | | Morfología fluvial | 0.0 | 0.0 | -12.0 | -26.0 | -31.0 | 0.0 | -23.0 | 0.0 | 0.0 | 0.0 | 0.0 | -25.5 | -30.5 | -25.5 | 0.0 | 0.0 | 0.0 |
| | | Morfología terrestre | 0.0 | -33.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | -28.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | | Flora | Terrestrial flora | 0.0 | -24.5 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | -22.5 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Biotic | Fauna | Aquatic flora | 0.0 | 0.0 | 0.0 | 0.0 | -14.5 | 0.0 | -14.5 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| | | Terrestrial fauna | 0.0 | -24.2 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | -22.5 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | Economic | Aquatic fauna | 0.0 | 0.0 | -12.0 | -11.5 | -17.5 | 0.0 | -14.5 | 0.0 | 0.0 | 0.0 | 0.0 | -25.5 | -30.5 | -25.5 | 0.0 | 0.0 | 0.0 |
| | | Visual landscape | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | -12.0 | -12.0 | 0.0 | 0.0 | 0.0 | 36.0 | 36.0 | 36.0 | 0.0 | 36.0 | 36.0 |
| Socio-economic | Social | Quality of life | 20.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | -14.5 | -17.5 | 36.0 | 36.0 | 36.0 | 31.0 | 36.0 | 36.0 | |
| | | Vulnerability- Security | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 36.0 | 36.0 | 36.0 | 31.0 | 36.0 | 36.0 |
| | Economic | PEA | 20.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | | Current land use | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 36.0 | 36.0 | 36.0 | 36.0 | 36.0 | 36.0 |



Source: Prepared based on PEAs of 6 Basins

It must be pointed out that in the Yauca River basin only 14 out of a total of 65 negative impacts have been quantified as significant, and 2 have been quantified as very significant, during the construction stage. Meanwhile, out of a total of 6 negative impacts, only 4 have been quantified as significant, and 2 have been quantified as very significant, during the operation stage.

During the construction stage, the works site preparation component and the DME installation and operation component will significantly affect the land morphology. At the same time, the Riverbed Excavation and Filling component will affect the “Ya1”, “Ya2”, and “Ya3” points. During the operation stage, river morphology and aquatic fauna will be significantly affected at the “Ya2” points, where the river basin will be excavated.

During the construction stage, actions that will generate most significant negative impacts along the basin include: “Site Works Preparation and Clearance”, “Riverbed Excavation and Filling”, and “Surplus Material Deposits Operation (DME, in Spanish).” “Site works Preparation and Clearance” will bring about a significant modification to the land morphology, whereas “Riverbed Excavation and Filling” will bring about a significant modification to river morphology.

During the operation stage, hydraulic infrastructure works that will bring about most significant negative environmental impacts include “Riverbed excavation and embankment” that will cause a modification to the river morphology and subsequently, decreased river habitability conditions that will directly impact the aquatic fauna.

Most significant positive impacts are related to all works to be constructed along the river basins, and are directly related to improve the quality of the lives of the population around the area of influence, improve the “Current Use of land / soil”, improve the security conditions, and reduce vulnerability at social and environmental levels.

4.8.4 Socio-Environmental Management Plans

The objective of the Socio-Environmental Plans is to internalize both positive and negative significant and very significant environmental impacts that are related to the Project’s construction and operation stages, so that prevention and/or mitigation of significant and very significant negative impacts, preservation of environmental heritage, and Project sustainability are ensured.

During the construction stage, Project of Pisco river has set out the following measures: “Local Hiring Program”, “Works Sites Management and Control Program”, “Riverbed Diversion Program”, “Riverbank Excavation and Filling Management”, “Riverbed Excavations and Filling Management”, “Quarry Management”, “DME Management”, “Camp and Site Residence Standards”, and “Transportation Activity Management.” During the operation stages, Project for the basin has considered the development of activities with regard to “Riverbed and Aquatic Fauna Management”. These activities should develop riverbed conditioning downstream the intervention points, for erosion probabilities to be reduced, and habitability conditions to be provided for aquatic fauna species. The following are measures related to those negative impacts to be mitigated or those positive impacts to be potentiated. Overall measures have been established for the basin, based on the impacts.

Table 4.9.4-1 Environmental Impact and Prevention/Mitigation Measures

| Item | Impact | Counter Measures | Period |
|---|--|--|---------------------|
| Natural environment | Water quality of surface water | Management of river diversion and coffering | Construction period |
| | | Management of bank excavation and banking | |
| | | Management of riverbed excavation and back filling | |
| | River topography | Management of bank excavation and banking | |
| | | Management of riverbed excavation and back filling | |
| | | Management of quarry site | |
| | Other topography | Management of construction site | |
| | | Management of large amount of excavated or dredged material | |
| Dust | Management of construction site | | |
| | Management of large amount of excavated and dredged material | | |
| Biological environment | Aquatic fauna | Management of riverbed excavation and back filling | O/M period |
| | Terrestrial fauna | Management of construction site | Construction period |
| | | Management of large amount of excavated and dredged material | |
| | Terrestrial flora | Management of construction site | |
| | | Management of large amount of excavated and dredged material | |
| | Social environment | Quality of life | |
| Management of traffic of construction vehicle | | | |
| Employment plan of local people | | | |
| Population of economic activity | | Employment plan of local people | |

Source: JICA Study Team

4.8.5 Monitoring and Control Plan

(1) Follow up and monitoring plan

The follow-up plan has to implement firmly the management of environmental plan. The monitoring plan is to be carried out to confirm that the construction activity fulfill the environmental standard such as Environmental Quality Standards (EQS) either or Maximum Permissible Limits (MPL). And the monitoring and control must be carried out under the responsibility of the project's owner or a third party under the supervision of the owner.

· Construction stage

During the construction period of the projects to be done in the watershed, the Monitoring and Control Plan will be directed to the verification of the fulfillment measures designed as part of the environmental monitoring plan and the verification of the fulfillment of laws and regulation of the Peruvian Legislation. The following aspects will also be monitored:

Water Quality and Biological Parameters:

Water quality and biodiversity parameters control shall be performed at downstream of these works must be monitored. In the following table the profile of this plan is shown.

Table 4.8.5-1 Monitoring to Water Quality and Biological Parameters

| Item | Unit | Measured Value (Mean) | Measured Value (Max.) | Country's Standards |
|---|------|-----------------------|-----------------------|---|
| pH | pH | | | "National Standard for Water Quality" D.S. No. 002-2009 MINAM |
| TSS | mg/l | | | |
| BOD/COD | mg/l | | | |
| DO | mg/l | | | |
| Total Nitrogen | mg/l | | | |
| Heavy Metals | mg/l | | | |
| Temperature | °C | | | |
| Biological Diversity indices: Shannon; Pielou; richness and abundance | | | | |

[Measurement Points]

-50 meters upstream the intervention points

-50 meters downstream the intervention points

-100 meters downstream the intervention points

[Frequency]

Quarterly

[Person in charge of Implementation]

DGIH-MINAG, or a third party under the project holder's supervision

Source: JICA Study Team

Air Quality:

During impact analysis, in the projects to be developed in the watershed no significant impacts will be seen in the activities related to hydraulic infrastructure works. However, the generation of dust and atmospheric contaminant emissions always affects the working area and the workers and inhabitants health. So, it is recommended to monitor air quality.

Table 4.8.5-2 Monitoring to Air Quality

| Item | Unit | Measured Value (Mean) | Measured Value (Max.) | Peruvian Standards (D.S. No 074-2001-PCM) | Referred International Standards |
|-----------------|------|-----------------------|-----------------------|--|--|
| SO ² | | | | "National Standard for Air Quality" D.S. No.074-2001-PCM | National Ambient Air Quality Standards (NAAQS) (Updated in 2008) |
| NO ² | | | | | |
| CO | | | | | |
| O ³ | | | | | |
| PM-10 | | | | | |
| PM-2.5 | | | | | |

[Measurement Points]

*02 stations per monitoring point: Windward and downwind (upwind and against the wind direction)

-1 point at the working zones

-1 point at a quarry, away from the river (the largest and / or the closest point to a populated area)

-1 point at a D.M.E. (the largest and / or the closest point to a populated area)

[Frequency]

Quarterly

[Person in charge of the Implementation]

DGIH-MINAG, or a third party under the project holder's supervision

Source: JICA Study Team

Noise Quality

Likewise, it is proposed to perform a noise monitoring at the potential receptors located near the noise emission spots towards the working sites, in the next table 4.8.5-3, the terms are described.

Table 4.8.5-3 Monitoring to Noise Quality

| Item | Unit | Measured Value (Mean) | Measured Value (Max.) | Country's Standards | Referred International Standards |
|-------------|---------------|-----------------------|-----------------------|---|---|
| Noise level | LAeqT (dB(A)) | | | National Environmental Quality Standards for noise (EQS) - S.N. N° 085-2003-PCM | -IEC 651/804 – International -IEC 61672- New Law: Replaces IECs 651/804 -ANSI S 1.4 – America |

[Measurement Point]

Monitoring to acoustic contamination levels will be carried out at the potential receivers that are located around the noise emission points per work front.

01 point per potential receiver will be monitored.

[Frequency]

Every two months during construction phase

[Person in charge of the Implementation]

DGIH-MINAG, or a third party under the project holder's supervision

Source: JICA Study Team

· Operation Stages

Regarding works impact of all projects, it is mainly recommended to monitor biologic parameters and water quality as river topography and the habitat of aquatic life.

Table 4.8.5-4 Monitoring to Water Quality (Operation Stage)

| Item | Unit | Measured Value (Mean) | Measured Value (Max.) | Country's Standards |
|---|------|-----------------------|-----------------------|---|
| pH | pH | | | "National Standard for Water Quality" D.S. No. 002-2009 MINAM |
| TSS | mg/l | | | |
| BOD/COD | mg/l | | | |
| DO | mg/l | | | |
| Total Nitrogen | mg/l | | | |
| Heavy Metals | mg/l | | | |
| Temperature | °C | | | |
| Biological Diversity indices: Shannon; Pielou; richness and abundance | | | | |

[Measurement Points]

- 50 meters upstream the intervention points
- 50 meters downstream the intervention points
- 100 meters downstream the intervention points

[Frequency]

Quarterly in first two years of operation phase

[Person in charge of Implementation]

DGIH-MINAG, or a third party under the project holder's supervision

Source: JICA Study Team

(2) Closure or Abandon Plan

Closure or abandon plans have been made for each watershed. These will be executed at the end of construction activities and involves the removal of all temporary works and restoration of intervened and/or affected areas as a result of the works execution. The restoration includes the removal of contaminated soil, disposal of waste material, restoration of soil morphology and restoration with vegetation of intervened sites.

(3) Citizen Participation

Citizen participation plans have been made for each watershed, which must be executed before and during construction and when the works are completed. The recommended activities are:

- Before works: Organize workshops in the surrounding community's area near the project and let them know what benefits they will have. Informative materials in communities, which will explain the profile, lapse, objectives, benefits, etc. of the Project
- During works execution: Give out information on the construction progress. Responding complaints generated from the local community during works execution. For this, a consensus

wants to be previously achieved with the community in order to determine how claims will be met

- When works are completed: Organize workshops to inform about works completion. Works delivery to the local community inviting local authorities for the transfer of goods, which means the work finished.

4.8.6 Cost for the environmental impact management

The direct costs of previously mentioned measures to mitigate environmental impacts in the Pisco River Watershed is as shown in the Table 4.8.6-1. In any case, it is necessary to determine in detail these measures' budget for each watershed in the detailed design stage.

Table 4.8.6-1 Direct costs of measures to manage environmental impact

4.8.7 Conclusions and Recommendations

(1) Conclusions

According to the Preliminary Environmental Appraisals to Yauca basin, most impacts identified during the construction and operation stages were found out to be of little significance. Significant and very significant negative impacts can be controlled or mitigated, as long as suitable Environmental Management Plans are carried out. In addition, the Project will be implemented in the short term, as environmental conditions will be quickly restored. However, the execution of a follow – up and monitoring plan is important, and in the event that unexpected impacts are generated, immediate mitigation measures must be taken.

In addition, significant positive impacts are also present, especially during the operation stage. These positive impacts include: An enhanced security / safety and a decreased vulnerability at social and environmental levels; an improved quality of life among the population in the area of influence, and an improved “Current use of land / soil”.

(2) Recommendations

1) We mainly recommend that the beginning of the construction activities coincides with the beginning of the dry seasons in the region (May to November) when the level of water is very low or the river dries up. The river characteristics / features should be taken into account, that the Yauca River is seasonal rivers. At the same time, the crop season cycle in the areas of direct influence should be taken into account, so that traffic jams caused by the large trucks and farming machinery is prevented.

2) It is recommended that the Project holder (DGIH) should define the limit of river area during detailed design stage, and identify the people who live within the river area illegally.

Continually the DGIH should carry on the process of land acquisition based on the Land Acquisition Law, which are; Emission of Resolution for land acquisition by the State, Proposition of land cost and compensation for land owner, Agreement of the State and land owner, Payment, archaeological assessment certification.

3) DGIH has to promote the process to obtain the CIRA in the detail design stage. The process to be taken is i) Application form, ii) Copies of the location drawings and outline drawings, iii) voucher, iv) Archaeological Assessment Certificate.

4) The participation of the women in the workshops can be promoted through the existing women group such as Vaso de Leche.

Finally, the DGAA submitted the resolutions (Environmental Permissions) for Yauca basin. The project has been categorized as “Category I”, which means that the project is not required to carry out neither EIA-sd nor EIA-d.

4.9 Execution Plan

The Project’s Execution Plan will review the preliminary schedule, which includes the following components. For pre-investment stage: ① full execution of pre-feasibility and feasibility studies to obtain SNIP’s approval in the pre-investment stage; for the investment stage: ② signing of loans (L/A), ③ consultant selection, ④ consulting services (detailed design and elaboration of technical specifications), ⑤ constructor selection and ⑥ work execution. For the post-investment stage: ⑦ Works’ completion and delivery to water users associations and beginning of the operation and maintenance stage.


(1) Review by the Public Investment National System (SNIP)

In Peru, the Public Investment National System (SNIP hereinafter) is under operation. This reviews the rationality and feasibility of public investment projects, and will be applied to this Project.

In SNIP, among previous studies to an investigation, it will be conducted in 3 stages: profile study (study on the project’s summary), pre-feasibility and feasibility. SNIP was created under Regulation N° 27293 (published on June 28, 2000) in order to achieve efficient use of public resources for public investment. It establishes principles, procedures, methods and technical regulations to be fulfilled by central/regional governments in public investment scheme plans and executed by them.

SNIP, as described below, is all public works projects which are forced to perform a 3-stage pre-investment study: profile study, pre-feasibility and feasibility, and have them approved.

However, following the Regulation amendment in April 2011, the execution of pre-feasibility study of the intermediate stage was considered unnecessary; but in return, a study based on primary data during the profile study is requested. The required precision degree throughout all stages of the study has hardly changed before and after this modification.




(Source: DGPM HP)

Figure 4.9-1 SNIP Cycle Project

In order to carry out this Project, which is a project composed by several programs, pre-investment studies at investments' programs level are required to be performed and also have them approved.

Although the procedure is quite different in each stage, in SNIP procedures, the project's training unit (UF) conducts studies of each stage, the Planning and Investment Office (OPI) assesses and approves the UF's presented studies and requests Public Sector Multi-Annual Programming General Direction (hereinafter referred DGPM) to approve feasibility studies and initiation of following studies. Finally DPGM evaluates, determines and approves the public investment's justification.



(See Regulation No.001-2009-EF/68.01.)

Figure 4.9-2 Related Institutions to SNIP

Due to the comments of examining authorities (OPI and DGPM) to FU, it will be necessary to prepare correspondent responses and improve the studies. Since these authorities officially admit applications after obtaining definitive answers, there are many cases in which they take several months from the completion of the study report until the completion of the study.

(2) Yen loan contract

Once the feasibility studies reports are submitted and examined in SNIP, discussions on the loan in yen will begin. It is estimated to be a period of 6 months for procedures.

(3) Procedure of the project's execution

After the documents are assessed by SNIP and a loan agreement between Japan (JICA) and the Peruvian counterpart is signed, a consultant will be selected. The consulting service includes the development of detailed design and technical specifications, the contractors' selection and the work's supervision. Table 4.9-1 presents the Project's overall schedule.

1) Consultant selection: 3 months, builder selection: 3 months

2) Develop detailed design and technical specifications of the work's period

① River and re-forestation works along these works

Detailed design and technical specifications elaboration: 6 months

Working Period: 2 years

② Capacity Building

It will be executed on the same work period of river facilities.

Detailed design and technical specifications elaboration: 6 months

Working Period: 2 years

Table 4.9-1 Implementation Plan

| ITEMS | 2010 | | | 2011 | | | 2012 | | | 2013 | | | 2014 | | | 2015 | | | 2016 | | | | |
|--|-------|---|---|------------|---|---|--------------------------|----|---|------|---|----|------------------|---|---|------|---|---|------|----|---|---|---|
| | 3 | 6 | 9 | 12 | 3 | 6 | 9 | 12 | 3 | 6 | 9 | 12 | 3 | 6 | 9 | 12 | 3 | 6 | 9 | 12 | 3 | 6 | 9 |
| 1 PROFILE STUDY / SNIP ASSESSMENT | STUDY | | | EVALUATION | | | | | | | | | | | | | | | | | | | |
| 2 FEASIBILITY STUDY / SNIP ASSESSMENT | | | | STUDY | | | EVALUATION | | | | | | | | | | | | | | | | |
| 3 YEN CREDIT NEGOTIATION | | | | | | | | | | | | | | | | | | | | | | | |
| 4 CONSULTANT SELECTION | | | | | | | | | | | | | | | | | | | | | | | |
| 5 CONSULTANT SERVICE (DETAILED DESIGN, LAWFUL DOCUMENTS PREPARATION) | | | | | | | DESIGN / LAWFUL DOCUMENT | | | | | | WORK SUPERVISION | | | | | | | | | | |
| 6 BUILDER SELECTION | | | | | | | | | | | | | | | | | | | | | | | |
| 7 WORK EXECUTION | | | | | | | | | | | | | | | | | | | | | | | |
| 1) STRUCTURES BUILDING | | | | | | | | | | | | | | | | | | | | | | | |
| 2) REFORESTATION | | | | | | | | | | | | | | | | | | | | | | | |
| 3) EARLY ALERT SYSTEM | | | | | | | | | | | | | | | | | | | | | | | |
| 4) DISASTER PREVENTIVE TRAINING | | | | | | | | | | | | | | | | | | | | | | | |
| 8 FINISH WORK / DELIVERY TO USERS BOARDS | | | | | | | | | | | | | | | | | | | | | | | |

4.10 Institutions and Administration

Peruvian institutions regarding the Project’s execution and administration are the Agriculture Ministry, Economy and Finance Ministry and Irrigation Commission, with the following roles for each institution:

Ministry of Agriculture (MINAG)

- * The Ministry of Agriculture (MINAG) is responsible for implementing programs and the Hydraulic Infrastructure General Direction (DGIH) is responsible for the technical administration of the programs. The Hydraulic Infrastructure General Direction (DGIH) is dedicated to the coordination, administration and supervision of investment programs.
- * In investment stage, the PSI(Programa Subsectorial de Irrigaciones, Ministerio de Agricultura) is dedicated to calculate project costs, detail design and supervision of the works execution.
- * The Planning and Investment Office (OPI) from the Agriculture Ministry is the one responsible for pre-feasibility and feasibility studies in the pre-investment stage of DGIH projects and requests approval of DGPI from the Economy and Finance Ministry (MEF).
- * The General Administration Office of the Agriculture Ministry (OGA-MINAG) along with the Public Debt National Direction (DNEP) of the Economy and Finance Ministry is dedicated to financial management. It also manages the budget for procurement, commissioning works, contracting, etc. from the Agriculture Ministry.
- * The Environmental Affairs General Direction (DGAA) is responsible for reviewing and approving the environmental impact assessment in the investment stage.

Economy and Finance Ministry (MEF)

- * The DGPI approves feasibility studies. It also confirms and approves the conditions of

loan contracts in yen. In the investment stage, it gives technical comments prior to the project execution.

- * Financial management is in charge of DNEP from the Economy and Finance Ministry and OGA-MINAG.
- * The Public Debt National Direction (DNEP) of the Economy and Finance Ministry administers expenses in the investment stage and post-investment operation.

Irrigation Commission

- * Responsible for the operation and maintenance of facilities at the post-investment operation stage.

The relationship between the involved institutions in the Project's execution is shown in Figures 4.10-1 and 4.10-2.

In this Project, the investment stage (Project execution) corresponds to PSI from MINA. The PSI is currently performing JBIC projects, etc. and in case of beginning a new project, it forms the correspondent Project Management Unit (UGP), who is responsible of choosing the consulting firm, hire construction services, works supervision, etc. The following figure describes the structure of the different entities involved in the Project's execution stage.





Figure 4.10-1 Related institutions to the Project's execution (investment stage)

The main operations in the post-investment stage consist of operation and maintenance of the built works and the loan reimbursement. The O & M of the works will be assumed by the respective irrigation commission. Likewise, they should pay the construction costs in credits mode. Next, the relationship of different organizations involved in post-project implementation stage is detailed.



**Figure 4.10-2 institutions related to the Project
(Post-investment operation and maintenance stage)**

(1) DGIH

1) Role and Functions

The Hydraulic Infrastructure General Direction is in charge of proposing public policies, strategies and plans aimed to promoting water infrastructure development, according with the Water Resources National Policy and the Environmental National Policy.

Water Infrastructure development includes studies, works, operation, maintenance and construction risk management, fit-out, improve and expand dams, intakes, river beds, irrigation channels, drains, meters, outlets, groundwater wells and modernize plot irrigation.

2) Main functions

- a. Coordinate with the planning and budget office to develop water infrastructure and propose sectorial and management policies on infrastructure development. Monitor and assess the implementation of sectorial policies related to hydraulic infrastructure development
- b. Propose government, region and provinces intervention regulations, as part of sectorial policies
- c. Verify and prioritize hydraulic infrastructure needs

- d. Promote and develop public investment projects at the hydraulic infrastructure profile level
- e. Elaborate technical regulations to implement hydraulic infrastructure projects
- f. Promote technological development of hydraulic infrastructure
- g. Elaborate operation and maintenance technical standards for hydraulic infrastructure

(2) PSI

1) Function

The Irrigation Sub-sectorial Program (PSI) is responsible of executing investment projects. A respective management unit is formed for each project.

2) Main functions

- a. Irrigation Sub-sectorial Program - PSI, under the Agriculture Ministry, is a body with administrative and financial autonomy. It assumes the responsibility of coordinating, managing and administering involved institutions in projects in order to meet goals and objectives proposed in investment projects
- b. Also, it coordinates the disbursements of foreign cooperation agencies financing, such as JICA.
- c. The Planning, Budget and Monitoring Office of PSI is responsible for hiring services, elaborating investment programs, as well as project execution plans. These Project preparation works are executed by hiring “in-house” consultants
- d. Likewise, it gathers contractors, makes a lease, executes works and implements supply projects, etc.
- e. Contract management is leaded by the Planning, Budget and Monitoring Office

3) Budget

In Table 4.10-1 the PSI budget for 2011 is shown.

Table 4.10-1 PSI Budget (2011)

| Programs / Projects / Activities | PIM (S/.) |
|---|-------------------|
| JBIC Program (Loan Agreement EP-P31) | 69.417.953 |
| Program - PSI Sierra (Loan Agreement 7878-PE) | 7.756.000 |
| Direct management works | 1.730.793 |
| Southern Reconstruction Fund (FORSUR) | 228.077 |
| Crop Conversion Project (ARTRA) | 132.866 |
| Technified Irrigation Program (PRT) | 1.851.330 |
| Activity- 1.113819 small farmers... | 783.000 |
| PSI Management Program (Other expenses) | 7.280.005 |
| TOTAL | 89.180.024 |


4) Organization

PSI is conformed by 235 employees, from which 14 are assigned for JBIC Projects and 29 technicians and assistants are working under them.

Table 4.10-2 PSI Payroll

| Central Level | Data from May 31, 2011 | | |
|-----------------------|------------------------|----------------------|------------|
| | CAS | Servic. and Consult. | TOTAL |
| Main Office | 61 | 43 | 104 |
| Zonal Office LIMA | 12 | 24 | 36 |
| Zonal Office AREQUIPA | 14 | 12 | 26 |
| Zonal Office CHICLAYO | 17 | 13 | 30 |
| Zonal Office TRUJILLO | 13 | 26 | 39 |
| TOTAL | 117 | 118 | 235 |

In Figure 4.10-3, PSI flow table is detailed:



4.11 Logical framework of the eventually selected option

In Table 4.11-1 the logical framework of the definite selected option is shown.

Table 4.11-1 Logical framework of the definite selected option

| Narrative Summary | Verifying Indicators | Verifying Indicators Media | Preliminary Conditions |
|--|---|--|--|
| Superior Goal | | | |
| Promote socioeconomic local development and contribute in communities' social welfare. | Improve local productivity, generate more jobs, increase population's income and reduce poverty index | Published statistic data | Scio-economic and policy stability |
| Objectives | | | |
| Relief the high vulnerability of valleys and local continuity to floods | Types, quantity and distribution of flood control works, population and beneficiaries areas | Monitoring annual calendar works and financial plan, budget execution control | Ensure the necessary budget, active intervention from central and regional governments, municipalities, irrigation communities, local population, etc. |
| Expected results | | | |
| Reduction of areas and flooded areas, functional improvement of intakes, road destruction prevention, irrigation channels protection, bank erosion control and Poechos dike safety | Number of areas and flooded areas, water intake flow variation, road destruction frequency, bank erosion progress and watershed's downstream erosion. | Site visits, review of the flood control plan and flood control works reports and periodic monitoring of local inhabitants | Maintenance monitoring by regional governments, municipalities and local community, provide timely information to the superior organisms |
| Activities | | | |
| Component A: Structural Measures | Dikes rehabilitation, intake and bank protection works, road damages prevention, construction of 28 works, including dike's safety | Detailed design review, works reports, executed expenses | Ensure the works budget, detailed design/works execution/good quality works supervision |
| Component B: Non-Structural Measures | | | |
| B-1 Reforestation and vegetation recovery | Reforested area, coastal forest area | Works advance reports, periodic monitor by local community | Consultants support, NGO's, local community, gathering and cooperation of lower watershed community |
| Component C: Disaster prevention and capabilities development education | Number of seminars, trainings, workshops, etc | Progress reports, local governments and community monitoring | Predisposition of the parties to participate, consultants and NGO's assessments |
| Project's execution management | | | |
| Project's management | Detailed design, work start order, work operation and maintenance supervision | Design plans, work's execution plans, costs estimation, works specifications, works management reports and maintenance manuals | High level consultants and contractors selection, beneficiaries population participation in operation and maintenance |

4.12 Middle and long term Plan

Up to this point, only flood control measures have been proposed and these must be executed most urgently, due to the limitations on the available budget for this Project. However, there are other measures that must be performed in the long term framework. In this section we will be talking about the middle and long term flood control plan.

4.12.1 Flood Control General Plan

There are several ways to control floods in the entire watershed, for example building dams, reservoirs, dikes or a combination of these.

In case of building a dam, assuming that this will reduce the flood peak (maximum flow) with a 50 year return period reaching an equivalent flow of 10 return years. It will be necessary to build a dam with a 3.7 million m³ capacity, which is quite an oversized number. Usually upstream of an alluvial area, there is a rough topography, and in order to build a dam with enough capacity, a very high dam need to be built, which implies investing a large amount (more than thousand millions of soles). Also, it would take between three to five years to identify the dam site, perform geological survey, material assessment and conceptual design. The impact on the local environment is huge. So, it is considered inappropriate to include the dam analysis option in this Study.

Likewise, the option of building a retarding basin would be not viable for the same reasons already given for the dam, because it would be necessary to build a great capacity of retarding basin and it is difficult to find a suitable location because most of the flat lands along the river's downstream are being used for agricultural purposes. So, its analysis has been removed from this Study.

Therefore, we will focus our study in the construction of dams because it is the most viable option.

(1) Plan of the river

1) Discharge capacity

An estimation was done on the discharge capacity of the current river's flow based on longitudinal and transversal river survey, which results are shown in the section 3.1.10, Figure 3.1.10-3.

2) Inundation characteristics

Inundation analysis of the Pisco River was performed. In the section 3.1.10, Figure 3.1.10-4 the inundation condition for flood with probabilities of 50 years is shown. In the Pisco River

watershed there are several sections where discharge capacity is not enough, causing floods for example on the left bank around km 7 upwards and downwards.

3) Design flood level and dike's standard section

The design flood level was determined in the flood water level with a return period of 50 years, and the dike's standard section will be determined as already mentioned in section 4.3.1, 5), 1). In 4.2, Table 4.2-2 the theoretical design flood level and the required height of the dike's crown is shown.

4) Dikes' Alignment

Considering the current conditions of existing dikes the alignment of the new dikes was defined. Basically, the broader possible river width was adopted to increase the discharge capacity and the retard effect. In Figure 4.12.1-1 the current channel and the setting alignment method of a section where the current channel has more width is explained schematically. In a normal section, the dike's crown has the same height to the flood water level with a return period of 50 years plus free board, while in the sections where the river has greater width, double dikes be constructed with inner consistent dike alignment and continuous with normal sections upstream and downstream. The crown height is equal to the flood water level with a return period of 50 years. The external dike's crown height is equal to flood water level with a return period of 50 years, so in case the river overflows the internal dike, the open gap between the two dikes will serve to store sediments and slow water.




Figure 4.12.1-1 Definition of dike alignment

5) Plan and River section

In Figures 4.12.1-2 and -4.12.1-3 the plan and longitudinal section of the Yauca River are shown.




Figure 4.12.1-2 Plan of Yauca River




Figure 4.12.1-3 Yauca River Longitudinal Profile

6) Dike's construction plan

Next, basic policies for the dike's construction plan on the Yauca River are shown:

- Build dikes that allow flood flow safe passage with a return period of 50 years
- The dikes will be constructed in areas where overflowing water will enter the dike, according to the flood simulation
- The dikes will be placed in the sections above mentioned, where the design water level exceeds the existing dike's height or the ground level within the dike
- The dike's height is defined in the flood water level with a return period of 50 years plus the free board

Table 4.12.1-1 and Figure 4.12.1-4 show the dike's construction plan on the Yauca River

Table 4.12.1-1 Dike's Construction Plan

| River | Sections to be improved | | Dike missing height average (m) | Dike proposed size | Dike length (km) |
|-------|-------------------------|-----------|---------------------------------|---|------------------|
| Yauca | Left margin | - | - | Dikes' height = 1,5m Margin protection works height = 3,0m | - |
| | Right margin | 0,5k-8,0k | 0,46 | | 3,0 |
| | Total | | 0,46 | | 3,0 |





Figure 4.12.1-4 Yauca River dike construction works approach

7) Project Cost

In Tables 4.12.1-2 and 4.12.1-4 works' direct costs in private prices and the Project's cost are shown. Also, the cost of the project in social prices is presented in Table 4.12.1-5.

Table 4.12.1-2 Direct works' cost (at private prices)

| Dike construction | | | | Coastal defense | | | |
|-------------------|-----|------|------|-----------------|------|-----|------|
| B1 | H1 | B2 | A | B1 | H2 | B2 | A |
| 3.0 | 1.0 | 8.5 | 5.8 | 1.0 | 1.0 | 2.4 | 10.8 |
| 3.0 | 2.0 | 14.0 | 17.0 | 1.0 | 2.0 | 2.9 | 13.4 |
| 3.0 | 3.0 | 19.5 | 33.8 | 1.0 | 3.0 | 3.4 | 16.5 |
| 3.0 | 4.0 | 25.0 | 56.0 | 1.0 | 4.0 | 3.9 | 20.1 |
| 3.0 | 5.0 | 30.5 | 83.8 | 1.0 | 5.0 | 4.4 | 24.3 |
| 3.0 | 1.5 | 11.3 | 10.7 | 1.0 | 6.0 | 4.9 | 28.9 |
| | | | | 1.0 | 1.5 | 2.6 | 12.0 |
| | | | | 1.0 | 10.0 | 6.9 | 52.4 |



| Water shed | Works | Amount | Unit | Unitary Price | Work direct cost/m | Work direct cost/km | Dike length | Work direct cost |
|------------|-------------------|--------|----------------|---------------|--------------------|---------------------|-------------|------------------|
| Yauca | Dikes | 10.7 | m ³ | 10.0 | 107.0 | 107.0 | 3.0 | 321.0 |
| | Margin protection | 16.5 | m ³ | 100.0 | 1,650.0 | 1,650.0 | | 4,950.0 |
| Total | | | | | 1,820.0 | 1,820.0 | | 55,510.0 |

Table 4.12.1-3 Projects' Cost (at private prices)

| Watershed | Direct Cost | Temporary works cost | Works Cost | Operative Expenses | Utility | Total Cost of Infrastructure | TAX | Total work cost | Environmental Impact | Technical File | Supervision | Total Cost |
|-----------|-------------|----------------------|-----------------|--------------------|-----------------|------------------------------|------------------|-----------------|----------------------|-------------------|------------------|--------------------------|
| 流域名 | 直接工事費計 | 共通仮設費 | 工事費 | 諸経費 | 利益 | 構造物工事費 | 税金 | 建設費 | 環境影響 | 詳細設計 | 施工管理費 | 事業費 |
| | (1) | (2) = 0.1 x (1) | (3) = (1) + (2) | (4) = 0.15 x (3) | (5) = 0.1 x (3) | (6) = (3)+(4)+(5) | (7) = 0.18 x (6) | (8) = (6)+(7) | (9)=0.01 x (8) | (10) = 0.05 x (8) | (11) = 0.1 x (8) | (12) = (8)+(9)+(10)+(11) |
| YAUCA | 5,271,000 | 527,100 | 5,798,100 | 869,715 | 579,810 | 7,247,625 | 1,304,573 | 8,552,198 | 85,522 | 427,610 | 855,220 | 9,920,549 |

Table 4.12.1-4 Projects' Cost (at social prices)

| Watershed | Direct Cost | Temporary works cost | Works Cost | Operative Expenses | Utility | Total Cost of Infrastructure | TAX | Total work cost | Environmental Impact | Technical File | Supervision | Total Cost |
|-----------|-------------|----------------------|-----------------|--------------------|-----------------|------------------------------|------------------|-----------------|----------------------|-------------------|------------------|--------------------------|
| 流域名 | 直接工事費計 | 共通仮設費 | 工事費 | 諸経費 | 利益 | 構造物工事費 | 税金 | 建設費 | 環境影響 | 詳細設計 | 施工管理費 | 事業費 |
| | (1) | (2) = 0.1 x (1) | (3) = (1) + (2) | (4) = 0.15 x (3) | (5) = 0.1 x (3) | (6) = (3)+(4)+(5) | (7) = 0.18 x (6) | (8) = (6)+(7) | (9)=0.01 x (8) | (10) = 0.05 x (8) | (11) = 0.1 x (8) | (12) = (8)+(9)+(10)+(11) |
| YAUCA | 4,237,884 | 423,788 | 4,661,672 | 699,251 | 466,167 | 5,827,091 | 1,048,876 | 6,875,967 | 68,760 | 343,798 | 687,597 | 7,976,121 |

2) Operation and Maintenance Plan

The operation and maintenance cost was calculated identifying the trend of the sedimentation and erosion bed based on the one-dimensional analysis results of the bed variation, and a long-term operation and maintenance plan was created.

The current river course has some narrow sections where there are bridges, farming works (intakes, etc.) and there is a tendency of sediment gathering upstream of these sections. Therefore, in this project there is a suggestion to increase the discharge capacity of these narrow sections in order to avoid as possible upstream and in the bed (main part) sedimentation, together with gathering sediments as much as possible when floods over a return period of 50 years occur.

1) Bed variation analysis

Figure 4.12.1-5 shows the results of the Bed variation analysis of the Pisco River for the next fifty years. From this figure a projection of the bed's sedimentation and erosion trend and its respective volume can be made.

2) Sections that need maintenance

In table 4.12.1-5 possible sections that require a process of long-term maintenance in the Pisco River watershed is shown.

3) Operation and maintenance cost

Next the direct work cost at private prices for maintenance (bed excavation) required for each watershed in the next 50 years is shown.

Direct Work Cost

At private prices: $60,000 \text{ m}^3 \times 10 \text{ soles} = 600,000 \text{ soles}$

Tables 4.12.1-6 and 4.12.1-7 show a 50 year Project cost at private and social prices.

Table 4.12.1-5 Sections which bed must be excavated in a programmed way

| River Name | Excavation Area | | Method of Maintenance Works |
|-------------|-----------------|--|--|
| Yauca River | Place 1 | Target Section : 25.5km-26.5km Target Volume : $60,000\text{m}^3$ | The section locates in the direct upstream of an existing intake weir. In order to keep the function of the weir, the periodical excavation maintenance should be carried out. |

※Design sediment volume: Sediment volume deposited in 50 years




Figure 4.12.1-5 Section that requires maintenance (Cañete River)

Table 4.12.1-6 Excavation Works cost for a 50 year bed (at private prices)

| Watershed | Direct Cost 直接工事費計 (1) | Temporary works cost 共通仮設費 (2) = 0.1 x (1) | Works Cost 工事費 (3) = (1) + (2) | Operative Expenses 諸経費 (4) = 0.15 x (3) | Utility 利益 (5) = 0.1 x (3) | Total Cost of Infrastructure 構築物工事費 (6) = (3)+(4)+(5) | TAX 税金 (7) = 0.18 x (6) | Total work cost 建設費 (8) = (6)+(7) | Environmental Impact 環境影響 (9) = 0.01 x (8) | Technical File 詳細設計 (10) = 0.05 x (8) | Supervision 施工管理費 (11) = 0.1 x (8) | Total Cost 事業費 (12) = (8)+(9)+(10)+(11) |
|-----------|------------------------------|--|--------------------------------------|---|----------------------------------|---|-------------------------------|---|--|---|--|---|
| YAUCA | 600 | 60 | 660 | 99 | 66 | 825 | 149 | 974 | 10 | 49 | 97 | 1,129 |

Table 4.12.1-7 Excavation Works cost for a 50 year bed (at social prices)

| Watershed | Direct Cost 直接工事費計 (1) | Temporary works cost 共通仮設費 (2) = 0.1 x (1) | Works Cost 工事費 (3) = (1) + (2) | Operative Expenses 諸経費 (4) = 0.15 x (3) | Utility 利益 (5) = 0.1 x (3) | Total Cost of Infrastructure 構築物工事費 (6) = (3)+(4)+(5) | TAX 税金 (7) = 0.18 x (6) | Total work cost 建設費 (8) = (6)+(7) | Correction Factor cf | Total work cost 建設費 (9) = cf*(8) | Environmental Impact 環境影響 (9) = 0.01 x (8) | Technical File 詳細設計 (10) = 0.05 x (8) | Supervision 施工管理費 (11) = 0.1 x (8) | Total Cost 事業費 (12) = (8)+(9)+(10)+(11) |
|-----------|------------------------------|--|--------------------------------------|---|----------------------------------|---|-------------------------------|---|-------------------------|--|--|---|--|---|
| YAUCA | 600 | 60 | 660 | 99 | 66 | 825 | 149 | 974 | 0.804 | 783 | 8 | 39 | 78 | 96 |

(3) Social Assessment

1) Private prices cost

i) Damage amount

Table 4.12.1-8 shows the damage amount calculated analyzing the overflow caused by floods in the Cañete River with return periods between 2 and 50 years.

Table 4.12.1-8 Amount of damage of different return periods (at private prices)

| Damage Amount (1,000 soles). 被害額(千ソール) | |
|---|--------|
| year | Yauca |
| 2 | 0 |
| 5 | 0 |
| 10 | 1,695 |
| 25 | 2,569 |
| 50 | 11,497 |

ii) Damage reduction annual average

Table 4.12.1-9 shows the damage reduction annual average of the watershed calculated with the data of Table 4.12.1-8.

iii) Project's Cost and the operation and maintenance cost

Table 4.12.1-3 shows the projects' cost. Also, the annual operation and maintenance (O & M) cost for dikes and bank protection works can be observed in the table. This is calculated from the 0.5% of the construction cost plus the bed excavation annual average cost indicated in Table 4.12.1-6.

iv) Economic evaluation

In Table 4.12.1-10 the results of economic assessment are shown.

Table 4.12.1-9 Damage Reduction Annual Average

s/1000

| 民間価格：流域全体 (Private Prices for ALL watersheds) | | | | | | | | | |
|---|--------------------------|---------------------|------------------------------------|-------------------|-------------------------------|--|--|--|--|
| 流域 Watershed | 流量規模 Return Period | 超過確率 Probability | 被害額 (Total damages - thousand S/.) | | | 区間平均被害 額 ④ Damages Average | 区間確率 ⑤ Probability incremental value | 年平均被害額 ④×⑤ Average value of damages flow | 年平均被害額の 累計=年平均被害 軽減期待額 Annual medial damages |
| | | | 事業を実施し ない場合① | 事業を実施し た場合② | 軽減額 ③=①-② | | | | |
| | | | Without Project ① | With Project ② | Mitigated damages ③=①-② | | | | |
| YAUCA | 1 | 1.000 | 0 | 0 | 0 | | | 0 | 0 |
| | 2 | 0.500 | 0 | 0 | 0 | 0 | 0.500 | 0 | 0 |
| | 5 | 0.200 | 0 | 0 | 0 | 0 | 0.300 | 0 | 0 |
| | 10 | 0.100 | 1,695 | 0 | 1,695 | 847 | 0.100 | 85 | 85 |
| | 25 | 0.040 | 2,569 | 0 | 2,569 | 2,132 | 0.060 | 128 | 213 |
| | 50 | 0.020 | 11,497 | 0 | 11,497 | 7,033 | 0.020 | 141 | 353 |

Table 4.12.1-10 Economic assessment results (private prices costs)

| 流域名 | 年平均被害軽減額 Accumulated Average Annual Benefit | 評価期間被害 軽減額(15年) Accumulated Average Annual Benefit (in 15 years) | 事業費 Project's Cost | 維持管理費 O&M Cost | C/B Cost/Benefit Relation | Net Present Value (NPV) NPV | Internal Rate of Return (IRR) IRR |
|-------|---|--|-----------------------|-------------------|---------------------------------|-----------------------------------|---|
| Yauca | 4,592,758 | 2,073,999 | 9,920,549 | 894,671 | 0.23 | (7,014,101) | - |

2) Social prices cost

i) Damage amount

Table 4.12.1-11 shows the damage amount calculated analyzing the overflow caused by floods in the Majes-Camana River with return periods between 2 and 50 years in each watershed.

Table 4.12.1-11 Amount of damage of different return periods (at social prices)

| Damage Amount (1,000 soles). 被害額(千ソールレス) | |
|--|--------|
| year | Yauca |
| 2 | 0 |
| 5 | 0 |
| 10 | 2,150 |
| 25 | 3,313 |
| 50 | 12,092 |

ii) Damage reduction annual average

Table 4.12.1-12 shows the damage reduction annual average of each watershed calculated with the data of Table 4.12.1-11.

iii) Project's Cost and the operation and maintenance cost

Table 4.12.1-4 shows the projects' cost. Also, the annual operation and maintenance (O & M) cost for dikes and bank protection works can be observed in the table. This is calculated from the 0.5% of the construction cost, as well as the bed excavation annual average cost indicated in Table 4.12.1-7.

iv) Economic evaluation

In Table 4.12.1-13 the results of economic assessment are shown.

Table 4.12.1-12 Damage Reduction Annual Average

s/1000

| 社会価格:流域全体 | | | | | | | | | |
|-----------------|--------------------------|---------------------|------------------------------------|-------------------|-------------------------------|--|--|--|--|
| 流域 Watershed | 流量規模 Return Period | 超過確率 Probability | 被害額 (Total damages - thousand S/.) | | | 区間平均被害 額 ④ Damages Average | 区間確率 ⑤ Probability incremental value | 年平均被害額 ④×⑤ Average value of damages flow | 年平均被害額の 累計=年平均被 害軽減期待額 Annual medial damages |
| | | | 事業を実施し ない場合① | 事業を実施し た場合② | 軽減額 ③=①-② | | | | |
| | | | Without Project ① | With Project ② | Mitigated damages ③=①-② | | | | |
| YAUCA | 1 | 1.000 | 0 | 0 | 0 | | 0 | 0 | |
| | 2 | 0.500 | 0 | 0 | 0 | 0.500 | 0 | 0 | |
| | 5 | 0.200 | 0 | 0 | 0 | 0.300 | 0 | 0 | |
| | 10 | 0.100 | 2,150 | 0 | 2,150 | 1,075 | 108 | 108 | |
| | 25 | 0.040 | 3,313 | 0 | 3,313 | 2,732 | 164 | 271 | |
| | 50 | 0.020 | 12,092 | 0 | 12,092 | 7,702 | 154 | 425 | |

Table 4.12.1-10 Economic assessment results (social prices costs)

| 流域名 | 年平均被害軽減額 Accumulated Average Annual Benefit | 評価期間被害 軽減額(15年) Accumulated Average Annual Benefit (in 15 years) | 事業費 Project's Cost | 維持管理費 O&M Cost | C/B Cost/Benefit Relation | Net Present Value (NPV) NPV | Internal Rate of Return (IRR) IRR |
|-------|---|--|-----------------------|-------------------|---------------------------------|-----------------------------------|---|
| Yauca | 5,531,228 | 2,497,793 | 7,976,121 | 719,315 | 0.34 | (4,809,039) | - |

(4) Conclusions

The economic assessment result shows that the Project has no positive economic impact in terms of cost on both private and social prices, and the required cost is extremely high (9.9 million of soles, so, this Project is less viable to be adopted.

4.12.2 Reforestation and Recovery of Vegetation Plan

(1) Reforestation of the upper watershed

Long-term reforestation in all areas considered to be critical of the upper watershed is recommended. So, a detail analysis of this alternative will be explained next.

1) Basic Policies

Objectives: Improve the water source area's infiltration capacity, reduce surface soils water flow and at the same time, increase water flow in intermediate soils and ground-water level. Because of the above mentioned, water flow is interrupted in high flood season, this increases water resources in mountain areas, reduces and prevents floods increasing with it the amount and greater flow of ground-water level, reducing and preventing floods

Forestry area: means forestry in areas with planting possibilities around watersheds with water sources or in areas where forest area has decreased.

Forestry method: local people plantations. Maintenance is done by promoters, supervision and advisory is leaded by NGOs.

Maintenance after forestry: Maintenance is performed by the sow responsible in the community. For this, a payment system (Payment for Environmental Services) will be created by downstream beneficiaries

Observations: After each thinning the area will have to be reforested, keeping and preserving it in a long-term sustainable way. An incentive for community people living upstream of the watershed shall be designed.

The forest is preserved after keeping and reforesting it after thinning, this also helps in the support and prevention of floods. For this, it is necessary that local people are aware, encourage people downstream, promote and spread the importance of forests in Peru during the project's execution.

2) Selection of forestry area

As mentioned in 1) Forestry on upper watershed is performed with the support of the community. In this case, the local inhabitants will participate in the upper watersheds during their spare time. However, take into account that the community mostly lives in the highlands where inhabitants live performing their farming and cattle activities in harsh natural conditions. Therefore, it is difficult to tell if they have the availability to perform forestry. So, finding comprehension and consensus of the inhabitants will take a long time.

3) Time required for the reforestation project

Since it is a small population, the workforce availability is reduced. So, the work that can be carried out during the day is limited, and the work efficiency would be very low. The JICA Study Team estimated the time required to reforest the entire area throughout the population in

the areas within the reforestation plan, plant quantity, work efficiency, etc. According to this estimate, it will take 14 years to reforest approximately 40,000 hectares from the Chincha River Watershed. When estimating the required time for other watersheds, by simply applying this rate to the respective watershed area, we obtained that reforestation in Yauca River Watershed will take 22 years.

4) Total reforestation volume in the upper watershed and project's period and cost

It has been estimated that the surface needed to be reforested in the Yauca River Watershed, as well as the execution cost, having as reference Chincha River Watershed project reforestation data. According to this estimate, the area to be reforested is approximately a total of 68,000 hectares. The required period is 22 years, and the cost is calculated in 184.3 million soles. In other words, investing a great amount of time and money is required to reforest.

Table 4.12.2-1 Upstream Watershed Forest General Plan

| Watershed | Forestry Area (ha) A | Required period for the project (years) B | Required budget (soles) C |
|-----------|-------------------------|--|---------------------------------|
| Yauca | 68,296 | 22 | 184,340,033 |

(Source: JICA Study Team)

5) Conclusions

The objective of this project is to execute the most urgent works and give such a long period for reforestation which has an indirect effect with an impact that takes a long time to appear would not be consistent with the proposed objective for the Project. Considering that 22 years and invested 184 million soles are required, we can say that it is impractical to implement this alternative in this project and that it shall be timely executed within the framework of a long-term plan after finishing this project.

4.12.3 Sediment control plan


For the long-term sediment control plan, it is recommended to execute the necessary works in the upper watershed.

The Sediment Control Plan in the upper watershed will mainly consist in construction of sediment control dikes and bank protection works. In Figure 4.12.3-1 the sediment control works disposition proposed to be executed throughout the watershed is shown. The cost of Yauca River works was estimated focusing on: a) covers the entire watershed, and b) covers only the priority areas, analyzing the disposition of works for each case. The results are shown in Table 4.12.3-1.

Due to the Yauca River extension, the construction cost for every alternative would be too high in case of carrying-out the bank protection works, erosion control dikes, etc., apart from requiring a considerably long time. This implies that the project will take a long time to show positive results. So, it is decided that it is impractical to execute this alternative within this project and should be timely executed within the framework of a long-term plan, after finishing this project.

Table 4.12.3-1 Upper watershed sediment control works execution estimated costs

| Watershed | Approach | Margin Protection | | Strip | | Sediment control dike | | Total works direct cost | Project Cost (Millions S/.) |
|-----------|---------------------|-------------------|---------------------------|--------------|---------------------------|-----------------------|---------------------------|-------------------------|-----------------------------|
| | | Vol. (km) | Direct Cost (Million S/.) | Vol. (units) | Direct Cost (Million S/.) | Vol. (units) | Direct Cost (Million S/.) | | |
| Yauca | All Watershed | 565 | S/.604 | 57 | S/.2 | 97 | S/.144 | S/.750 | S/.1.412 |
| | Prioritized Section | 565 | S/.604 | 57 | S/.2 | 37 | S/.54 | S/.660 | S/.1.242 |



4.12.3-1 Sediment control works location Cañete River Watershed

5. CONCLUSIONS

The selected alternative for flood control in this Study is structurally safe, and the environmental impact is small, however the social evaluation shows extremely low economic effect so that it is difficult to implement this Project.

**Ministry of Agriculture
Republic of Peru**

**THE PREPARATORY STUDY
ON
PROJECT OF THE PROTECTION OF
FLOOD PLAIN AND VULNERABLE RURAL
POPULATION AGAINST FLOOD IN THE
REPUBLIC OF PERU**

**FINAL REPORT
PRE-FEASIBILITY STUDY REPORT
II-7 PROJECT REPORT
(MAJES-CAMANA RIVER)
(TEMPORARY VERSION)**

March 2013

**JAPAN INTERNATIONAL COOPERATION AGENCY
(JICA)**

**YACHIYO ENGINEERING CO., LTD.
NIPPON KOEI CO., LTD.
NIPPON KOEI LATIN AMERICA –
CARIBBEAN Co., LTD.**

Composition of Final Report

I. Feasibility Study Report

I-1 Program Report

I-2 Project Report (Cañete River)

I-3 Project Report (Chincha River)

I-4 Project Report (Pisco River)

I-5 Project Report (Majes-Camana River)

I-6 Supporting Report

Annex – 1 Metrology /Hydrology /Run-off Analysis

Annex – 2 Inundation Analysis

Annex – 3 River Bed Fluctuation Analysis

Annex – 4 Flood Control Plan

Annex – 5 Forecasting and Warning System in Chira River

Annex – 6 Sediment Control

Annex – 7 Afforestation and Vegetation Recovery Plan

Annex – 8 Plan and Design of Facilities

Annex – 9 Construction Planning and Cost Estimate

Annex – 10 Socio-economy and Economic Evaluation

Annex – 11 Environmental and Social Considerations/ Gender

Annex – 12 Technical Assistance

Annex – 13 Stakeholders Meetings

Annex – 14 Implementation Program of Japanese Yen Loan Project

Annex – 15 Drawings

I-7 Data Book

II. Pre- Feasibility Study Report

II-1 Program Report

II-2 Project Report (Chira River)

II-3 Project Report (Cañete River)

II-4 Project Report (Chincha River)


II-5 Project Report (Pisco River)

II-6 Project Report (Yauca River)

II-7 Project Report (Majes-Camana River) (This Report)



Location Map



Abbreviation

| Abbreviation | Official Name or meaning |
|--------------|---|
| ANA | Water National Authority (Autoridad Nacional del Agua) |
| ALA | Water Local Authority (Autoridad Local del Agua) |
| C/B | Cost-Benefit relation (Cost-Benefit Ratio) |
| GDP | PBI (Producto Bruto Interno) (Gross Domestic Product) |
| GIS | Sistema de información geográfica (Geographic Information System) |
| DGAA | Dirección General de Asuntos Ambientales (Environmental Affairs General Direction) |
| DGFFS | Dirección General de Forestal y de Fauna Silvestre (Forestry and Fauna General Direction) |
| DGIH | Dirección General de Infraestructura Hidráulica (Hydraulic Infrastructure General Direction) |
| DGPM | Dirección General de Programación Multianual del Sector Público (Public Sector Multiannual Program General Direction) |
| DNEP | Dirección Nacional de Endeudamiento Público (Public Indebtedness National Direction) |
| DRA | Dirección Regional de Agricultura (Agriculture Regional Direction) |
| EIA | Estudio de impacto ambiental (Environmental Impact Assessment - EIA) |
| FAO | Organización de las Naciones Unidas para la Agricultura y la Alimentación (Food and Agriculture Organization of the United Nations) |
| F/S | Estudio de Factibilidad (Feasibility Study) |
| GORE | Gobiernos Regionales (Regional Governments) |
| HEC-HMS | Sistema de Modelado Hidrológico del Centro de Ingeniería Hidrológica (Hydrologic Model System from the Hydrology Engineer Center) |
| HEC-RAS | Sistema de Análisis de Ríos del Centro de Ingeniería Hidrológica (Hydrologic Engineering Centers River Analysis System) |
| IGN | Instituto Geográfico Nacional (National Geographic Institute) |
| IGV | Impuesto General a Ventas (TAX) |
| INDECI | Instituto Nacional de Defensa Civil (Civil defense National Institute) |
| INEI | Instituto Nacional de Estadística (Statistics National Institute) |
| INGEMMET | Instituto Nacional Geológico Minero Metalúrgico (Metallurgic Mining Geologic National Institute) |
| INRENA | Instituto Nacional de Recursos Naturales (Natural Resources National Institute) |
| IRR | Tasa Interna de Retorno (Internal Rate of Return - IRR) |
| JICA | Agencia de Cooperación Internacional del Japón (Japan International Cooperation Agency) |
| JNUDRP | Junta Nacional de Usuarios de los Distritos de Riego del Perú (Peruvian Irrigation District Users National Board) |
| L/A | Acuerdo de Préstamo (Loan Agreement) |
| MEF | Ministerio de Economía y Finanzas (Economy and Finance Ministry) |
| MINAG | Ministerio de Agricultura (Agriculture Ministry) |
| M/M | Minuta de Discusiones (Minutes of Meeting) |

| | |
|-------------|--|
| NPV | VAN (Valor Actual Neto) (NET PRESENT VALUE) |
| O&M | Operación y mantenimiento (Operation and maintenance) |
| OGA | Oficina General de Administración (Administration General Office) |
| ONERRN | Oficina Nacional de Evaluación de Recursos Naturales (Natural Resources Assessment National Office) |
| OPI | Oficina de Programación e Inversiones (Programming and Investment Office) |
| PE | Proyecto Especial Chira-Piura (Chira-Piura Special Project) |
| PES | PSA (Pago por Servicios ambientales) (Payment for Environmental Services) |
| PERFIL | Estudio del Perfil (Profile Study) |
| Pre F/S | Estudio de prefactibilidad (Pre-feasibility Study) |
| PERPEC | Programa de Encauzamiento de Ríos y protección de Estructura de Captación (River Channeling and Protection of Collection Structures Program) |
| PRONAMACHIS | Programa Nacional de Manejo de Cuencas Hidrográficas y Conservación de Suelos (Water Basins Management and Soil Conservation National Program) |
| PSI | Programa Sub Sectorial de irrigaciones (Sub-Sectorial Irrigation Program) |
| SCF | Factor de conversión estándar (Standard Conversion Factor) |
| SENAMHI | Servicio Nacional de Meteorología y Hidrología (Meteorology and Hydrology National Service) |
| SNIP | Sistema Nacional de Inversión Pública (Public Investment National System) |
| UF | Unidades Formuladoras (Formulator Units) |
| VALLE | Llanura aluvial, llanura de valle (Alluvial Plain, Valley Plain) |
| VAT | Impuesto al valor agregado (Value added tax) |

THE PREPARATORY STUDY
ON
PROJECT OF THE PROTECTION OF FLOOD PLAIN AND VULNERABLE RURAL
POPULATION AGAINST FLOODS IN THE REPUBLIC OF PERU
FINAL REPORT
PRE-FEASIBILITY STUDY REPORT
II-7 PROJECT REPORT
(MAJES-CAMANA RIVER)
(TEMPORARY VERSION)

Table of Contents

Location Map

Abbreviation

| | |
|--|------------|
| 1. EXECUTIVE SUMMARY | 1-1 |
| 1.1 Project Name..... | 1-1 |
| 1.2 Project's Objective | 1-1 |
| 1.3 Supply and Demand Balance | 1-1 |
| 1.4 Structural Measures | 1-2 |
| 1.5 Non-structural measures | 1-4 |
| 1.6 Technical support | 1-5 |
| 1.7 Costs..... | 1-5 |
| 1.8 Social Assessment..... | 1-5 |
| 1.9 Sustainability Analysis..... | 1-7 |
| 1.10 Environmental Impact..... | 1-8 |
| 1.11 Execution plan | 1-10 |
| 1.12 Institutions and management | 1-10 |
| 1.13 Logical Framework..... | 1-12 |
| 1.14 Middle and Long Term Plans..... | 1-13 |

| | | |
|-----------|---|------------|
| 2. | GENERAL ASPECTS | 2-1 |
| 2.1 | Name of the Project | 2-1 |
| 2.2 | Formulator and Executor Units..... | 2-1 |
| 2.3 | Involved entities and Beneficiaries Participation..... | 2-1 |
| 2.4 | Framework | 2-4 |
| 3. | IDENTIFICATION..... | 3-1 |
| 3.1 | Diagnosis of the current situation | 3-1 |
| 3.2 | Definition of Problem and Causes | 3-65 |
| 3.3 | Objective of the Project | 3-69 |
| 4. | FORMULATION AND EVALUATION | 4-1 |
| 4.1 | Definition of the Assessment Horizon of the Project | 4-1 |
| 4.2 | Supply and Demand Analysis | 4-1 |
| 4.3 | Technical Planning..... | 4-6 |
| 4.4 | Costs..... | 4-29 |
| 4.5 | Social Assessment..... | 4-30 |
| 4.6 | Sensitivity Analysis..... | 4-38 |
| 4.7 | Sustainability Analysis..... | 4-40 |
| 4.8 | Environmental Impact..... | 4-41 |
| 4.9 | Execution Plan | 4-53 |
| 4.10 | Institutions and Administration | 4-56 |
| 4.11 | Logical framework of the eventually selected option | 4-61 |
| 4.12 | Middle and long term Plan..... | 4-62 |
| 5. | CONCLUSIONS | 5-1 |

1. EXECUTIVE SUMMARY

1.1 Project Name

“Protection program for valleys and rural communities vulnerable to floods
Implementation of prevention measures to control overflows and floods of Majes-
Camana River, Arequipa department.”

1.2 Project’s Objective

The ultimate impact that the project is design to achieve is to alleviate the vulnerability of
valleys and the local community to flooding and boost local socioeconomic development.

1.3 Supply and Demand Balance

It has been calculated the theoretical water level in case of flow design flood based on the
transversal lifting data of the river with an interval of 500m, in the Majes-Camana river
watershed, assuming a design flood flow equal to the flood flow with a return period of
50 years. Then, we determined the dike height as the sum of the design water level plus
the dike’s free board.

This is the required height of the dike to control the damages caused by design floods and
is the indicator of the demand of the local community.

The height of the existing dike or current ground height is the required height to control
the current flood damages, and is the indicator of the current offer.

The difference between the dike design height (demand) and the height of the
embankment or ground at present (supply) is the difference or gap between demand and
supply.

Table 1.3-1 shows the average water levels floods, calculated with a return period of 50
years, of the required height of the dike (demand) to control the flow by adding the
design water level plus the free board of the dike; of dike height or current ground height
(supply), and the difference between these two (difference between demand and supply)
of the river. Then, in Table 4.2-2 the values at each point are shown. The current height
of the dike or the current ground height is greater than the required height of the dike, at
certain points. In these, the difference between supply and demand is considered null.

Table 1.3-1 Demand and supply analysis

| Watershed | Dike Height / current land (supply) | | Theoretical water level with a return period of 50 years | Dike Freeboard | Required dike's height (demand) | Diff. demand/supply | |
|--------------|-------------------------------------|------------|--|----------------|---------------------------------|---------------------|------------|
| | Left bank | Right bank | | | | Left bank | Right bank |
| | ① | ② | | | | ③ | ④ |
| Majes-Camaná | 401.90 | 405.19 | 399.43 | 1.20 | 400.63 | 1.21 | 0.88 |

1.4 Structural Measures

Structural measures are a subject that must be analyzed in the flood control plan covering the entire watershed. The analysis results are presented in section 4.12 “medium and long term plan” This plan proposes the construction of dikes for flood control throughout the watershed. However, the case of Majes-Camana River requires a large project investing at a extremely high cost, far beyond the budget for this Project, which makes this proposal it impractical. Therefore, assuming that the dikes to control floods throughout the whole basin will be constructed progressively over a medium and long term period. Here is where this study focused on the most urgent works, priority for flood control.

(1) Design flood flow

The Methodological Guide for Protection Projects and/or Flood Control in Agricultural or Urban Areas (Guia Metodologica para Proyectos de Proteccion y/o Control de Inundaciones en Áreas Agrícolas o Urbanas, 3.1.1 Horizonte de Proyectos) prepared by the Public Sector Multi Annual Programming General Direction (DGPM) of the Ministry of Economy and Finance (MEF) recommends a comparative analysis of different return periods: 25, 50 and 100 years for the urban area and 10, 25 and 50 years for rural and agricultural land.

Considering that the present Project is aimed at protecting the rural and agricultural land, the design flood flow is to be determined in a return period of 10 years to 50 years in the mentioned Guide.

The maximum discharge in the past in Majes-Camana watershed is less than the flood discharge with return period of 50-year. However it seems that the flood discharge with return period of 50-year caused large damages.

Since the flood control facilities in Peru not well developed, it is true that the past floods caused much disaster so that the facilities should be safe for the same scale of flood with return period of 50 years, therefore the design flood discharge in this Project is to be the discharge with return period of 50-year.

The relation among flood discharge with different return period, damage caused by the floods and inundation areas is analyzed in the basin. The results are that the more the return periods of flood increase the more inundation area and damage amount increase in the basin, however the increase tendency of damage with project is more gentle compared with former two items, and the reduction of damage with project reaches to maximum in the case of the flood with return period of 50 years within the cases of flood with less return period of 50 years.

As shown in the above section, the design flood discharge with return period of 50-year is more than the maximum flood in the past, and absolute damage reduction amount in the design discharge is largest among the probable flood discharge less than with return period of 50-year, and economic viability of the design flood is confirmed.

(2) Selection of prioritized flood prevention works

We applied the following five criteria for the selection of priority flood control works.

- Demand from the local community (based on historical flood damage)
- Lack of discharge capacity of river channel (including the sections affected by the scouring)
- Conditions of the adjacent area (conditions in urban areas, farmland, etc.).
- Conditions and area of inundation (type and extent of inundation according to inundation analysis)
- Social and environmental conditions (important local infrastructures)

Based on the river survey, field investigation, discharge capacity analysis of river channel, inundation analysis, and interviews to the local community (irrigation committee needs, local governments, historical flood damage, etc...) a comprehensive evaluation was made applying the five evaluation criteria listed above. After that we selected a total of seven (7) critical points (with the highest score in the assessment) that require flood protection measures.

Concretely, since the river cross sectional survey was carried out every 500m interval and discharge capacity analysis and inundation analysis were performed based on the survey results, the integral assessment was also done for sections of 500 meters. This sections have been assessed in scales of 1 to 3 (0 point, 1 point and 2 points) and the sections of which score is more than 6 were selected as prioritized areas. The lowest limit (6 points) has been determined also taking into account the budget available for the Project in general

1.5 Non-structural measures

1.5.1 Reforestation and vegetation recovery

(1) Basic Policies

The reforestation plan and vegetation recovery that meets the objective of this project can be divided into: i) reforestation along river structures, and ii) reforestation in the upper watershed. The first has a direct effect on flood prevention expressing its impact in a short time, while the second one requires high cost and a long period for its implementation, as indicated later in the section “1.12 (2) Reforestation Plan and vegetation recovery”, and also it is impractical to be implemented within the framework of this project. Therefore, this study focused on the first alternative.

(2) Regarding reforestation along river structures

This alternative proposes planting trees along the river structures, including dikes and bank protection works.

- Objective: Reduce the impact of flooding of the river when an unexpected flood or narrowing of the river by the presence of obstacles, using vegetation strips between the river and the elements to be protected.
- Methodology: Create vegetation stripes of a certain width between the river and river structures.
- Execution of works: Plant vegetation on a portion of the river structures (dikes, etc.).
- Maintenance after reforestation: Maintenance will be taken by irrigation committees under their own initiative.

The width, length and area of reforestation along river structures are 11m, 29.0 km and 18.3 ha respectively.

1.5.2 Sediment control plan

The sediment control plan must be analyzed within the general plan of the watershed. The results of the analysis are presented in section 1.12 “Medium and long term plan (3)”. To sum up, the sediment control plan for the entire watershed requires a high investment cost, which goes far beyond the budget of this project, which makes it impractical to adopt.

The bed variation analysis has shown that the volume of sediment dragged in the Majes-Camana river watershed is high, and therefore the bed variation (sediment volume) is also large. However, seeing the average height of the bed, there has only been a variation of approximately 0.2 m in 50 years, and the entry of sediments seem to have almost no impact on the downstream bed. So, we conclude that it is necessary to take special measures to control sediment.

1.6 Technical support

Based on the technical proposals of structural and nonstructural measures, it is also intends to incorporate in this project technical assistance to strengthen the measures.

The objective of the technical assistance is to “improve the capacity and technical level of the local community, to manage risk to reduce flood damage in selected valleys.”

Technical assistance will cover the Majes-Camana river watershed.

Aiming to train characteristics of the watershed, courses for one will be prepared. The beneficiaries are the representatives of the committees and irrigation groups from each watershed, governments employees (provincial and district), local community representatives, local people etc.

Qualified as participants in the training, people with ability to replicate and disseminate lessons learned in the courses to other community members, through meetings of the organizations to which they belong.

In order to carry out the technical assistance goal, the three activities propose the following:

- Bank protection activity and knowledge enhancement on agriculture and natural environment
- Community disaster prevention planning for flood damages
- Watershed (slope) management against fluvial sedimentation

1.7 Costs

In the Table 1.7-1 the costs of this Project in Majes-Camana watershed is shown. The cost of the watersheds is around 97.2 million soles.

Table 1.7-1 Project Cost

1.8 Social Assessment

(1) Benefits

The benefits of flood control are the reduction of losses caused by floods which would be achieved by the implementation of the project and is determined by the difference between the loss amount without project and with project. Specifically, to determine the benefits, first the amount of losses by floods is calculated from different return periods

(between 2 and 50 years), assuming that flood control works will last 50 years, and then the average annual reduction loss amount is determined from the reduction of losses from different return periods. In Tables 1.8-1 and 1.8-2 show the average annual amount of reduction loss that would be achieved by implementing this project, expressed in costs at private prices and costs at social prices.

Table 1.8-1 Annual average damage reduction amount (at private prices)

s/1000

| 流域 Basin | 流量規模 Return period | 超過確率 Probability | 被害額 (Total damage - miles de S/.) | | | 区間平均被害額 ④ Average damage | 区間確率 ⑤ Section probability | 年平均被害額 ④×⑤ Annual average damage ⑥ | Accumulation of ⑥ = Annual average damage reduction |
|--------------|-----------------------|---------------------|-----------------------------------|----------------|---------------------------|--------------------------------|----------------------------------|--|--|
| | | | 事業を実施しない場合① | 事業を実施した場合② | 軽減額 ③=①-② | | | | |
| | | | Without Project ① | With project ② | Damage reduction ③=①-② | | | | |
| MAJES-CAMANA | 1 | 1.000 | 0 | 0 | 0 | | 0 | 0 | |
| | 2 | 0.500 | 0 | 0 | 0 | 0 | 0.500 | 0 | |
| | 5 | 0.200 | 47,669 | 10,021 | 37,648 | 18,824 | 0.300 | 5,647 | 5,647 |
| | 10 | 0.100 | 76,278 | 21,316 | 54,962 | 46,305 | 0.100 | 4,631 | 10,278 |
| | 25 | 0.040 | 111,113 | 34,254 | 76,859 | 65,911 | 0.060 | 3,955 | 14,232 |
| | 50 | 0.020 | 190,662 | 63,532 | 127,130 | 101,994 | 0.020 | 2,040 | 16,272 |
| | | | | | | | | | |

Table 1.8-2 Annual average damage reduction amount (at social prices)

s/1000

| 流域 Basin | 流量規模 Return period | 超過確率 Probability | 被害額 (Total damage - miles de S/.) | | | 区間平均被害額 ④ Average damage | 区間確率 ⑤ Section probability | 年平均被害額 ④×⑤ Annual average damage ⑥ | Accumulation of ⑥ = Annual average damage reduction |
|--------------|-----------------------|---------------------|-----------------------------------|----------------|---------------------------|--------------------------------|----------------------------------|--|--|
| | | | 事業を実施しない場合① | 事業を実施した場合② | 軽減額 ③=①-② | | | | |
| | | | Without Project ① | With project ② | Damage reduction ③=①-② | | | | |
| MAJES-CAMANA | 1 | 1.000 | 0 | 0 | 0 | | 0 | 0 | |
| | 2 | 0.500 | 0 | 0 | 0 | 0 | 0.500 | 0 | |
| | 5 | 0.200 | 48,468 | 10,435 | 38,033 | 19,016 | 0.300 | 5,705 | 5,705 |
| | 10 | 0.100 | 78,194 | 21,738 | 56,456 | 47,244 | 0.100 | 4,724 | 10,429 |
| | 25 | 0.040 | 116,730 | 36,455 | 80,275 | 68,366 | 0.060 | 4,102 | 14,531 |
| | 50 | 0.020 | 206,459 | 70,838 | 135,621 | 107,948 | 0.020 | 2,159 | 16,690 |
| | | | | | | | | | |

(2) Social assessment results

The objective of the social assessment in this study is to evaluate the efficiency of investments in the structural measures using the method of cost-benefit relation (C/B) from the point of view of national economy. To do this, we determined the economic evaluation indicators (C/B relation, Net Present Value-NPV, and Internal return rate - IRR).

The benefits of the evaluation period were estimated, from the first 15 years since the start of the project. Because, from these 15 years, two are from the work execution period, the evaluation was conducted for the 13 years following the completion of works.

In Tables 1.8-3 and 1.8-4 the costs at private prices and at social prices resulting from this project assessment are shown. It is noted that the project will have enough economic effect.

Table 1.8-3 Social Assessment (costs at private prices)

Table 1.8-4 Social Assessment (costs at social prices)

Below are the positive effects of the Project that are difficult to quantify in economic values.

- ① Contribution to local economic development to alleviate the fear to economic activities suspension and damages
- ② Contribution to increase local employment opportunities thanks to the local construction project
- ③ Strengthening the awareness of local people regarding damages from floods and other disasters
- ④ Contribution to increase from stable agricultural production income, relieving flood damage
- ⑤ Rise in farmland prices

From the results of the economic evaluation presented above, it is considered that this project will substantially contribute to the development of the local economy.

1.9 Sustainability Analysis

This project will be co-managed by the central government (through the DGIH), irrigation committees and regional governments, and the project cost will be covered with the respective contributions of the three parties. Usually the central government (in this case, the DGIH) assumes 80%, the irrigation commissions 10% and regional governments 10%. However, the percentages of the contributions of these last two are decided through discussions between both parties. On the other hand, the operation and maintenance (O & M) of completed works is taken by the irrigation committees. Therefore, the sustainability of the project is depends on the profitability of the project and the ability of O & M of irrigation committees.

(1) Profitability

We have seen that Majes-Camana river watershed is sufficiently profitable and sustainable. The amount of investment required is estimated at million soles (cost at private prices). It is a cost-effective project with a C/B relation of 1.35, a relatively high IRR of approximately 16% and NPV of S/.25. 4millones soles.

(2) Operation and maintenance costs

The annual cost of operation and maintenance required for the project, having as base year 2008 is estimated at soles, which corresponds to % of the construction cost of the project (83,228,000 soles) in the Majes-Camana river watershed. On the other hand, the operating expenses average in the last two years of irrigation committees is 1,911,708.

When considering that the annual cost of operation and maintenance represents 22% of the annual irrigation budget, the project would be sustainable enough because of the financial capacity of these committees to maintain and operate the constructed works.

Table 1.9-1 presents the budget of the irrigation committees in the Majes-Camana river watershed in recent years.

Table 1.9-1 Irrigation committee’s budget

| Rivers | Annual Budget (Unit/ S) | | | | |
|--------------|-------------------------|------|------|--------------|--------------|
| | 2006 | 2007 | 2008 | 2009 | 2010 |
| Majes-Camana | | | | 1.959.302,60 | 1.864.113,30 |

1.10 Environmental Impact

(1) Procedure of Environmental Impact Assessment

Projects are categorized in three scales, based on the significance level of the negative and positive impacts, and each sector has an independent competence on this categorization. The Project holder should submit the Environmental Impact Statement (DIA, in Spanish) for all Projects under Category I. The project holder should prepare an EIA-sd or an EIA-d if the Project is categorized under Category II or III, respectively, to be granted the Environmental Certification from the relevant Ministry Directorate.

First, the Project holder applies for the Project classification, by submitting the Preliminary Environmental Assessment (PEA). The relevant sector assesses and categorizes the Project. The Project’s PEA that is categorized under Category I

becomes an EID, and those Projects categorized under Category II or III should prepare an EIA-sd or EIA-d, as applicable.

The preliminary environmental assessment (EAP) for Majes-Camana river was carried out between September 2011 and November 2011 and by a consulting firm registered in the Ministry of Agriculture (CIDES Ingenieros S.A.). EAP for Majes-Camana was submitted to DGIH December 20, 2011 by JICA Study Team and from DGIH to DGAA January 4, 2012. DGAA is still under assessment on Majes-Camana watershed,

(2) Results of Environmental Impact Assessment

The procedures to review and evaluate the impact of the natural and social environment of the Project are the following. First, we reviewed the implementation schedule of the construction of river structures, and proceeded to develop the Leopold matrix.

The impact at environmental level (natural, biological and social environment) was evaluated and at Project level (construction and maintenance stage). The quantitative levels were determined by quantifying the environmental impact in terms of impact to nature, manifestation possibility, magnitude (intensity, reach, duration and reversibility).

The EAP showed that the environmental impact would be manifested by the implementation of this project in the construction and maintenance stages, mostly, it is not very noticeable, and if it were, it can be prevented or mitigated by appropriately implementing the management plan environmental impact.

On the other hand, the positive impact is very noticeable in the maintenance stage, which manifests at socioeconomic and environmental level, specifically, in greater security and reduced vulnerability, improved life quality and land use.

1.11 Execution plan

Table 1.11-1 presents the Project execution plan.

Table 1.11-1 Execution plan

| ITEMS | 2010 | | | 2011 | | | 2012 | | | 2013 | | | 2014 | | | 2015 | | | 2016 | | | | |
|--|-------|---|---|--------------------------|---|---|------------------|----|---|------|---|----|------|---|---|------|---|---|------|----|---|---|---|
| | 3 | 6 | 9 | 12 | 3 | 6 | 9 | 12 | 3 | 6 | 9 | 12 | 3 | 6 | 9 | 12 | 3 | 6 | 9 | 12 | 3 | 6 | 9 |
| 1 PROFILE STUDY / SNIP ASSESSMENT | STUDY | | | EVALUATION | | | | | | | | | | | | | | | | | | | |
| 2 FEASIBILITY STUDY / SNIP ASSESSMENT | STUDY | | | EVALUATION | | | | | | | | | | | | | | | | | | | |
| 3 YEN CREDIT NEGOTIATION | | | | | | | | | | | | | | | | | | | | | | | |
| 4 CONSULTANT SELECTION | | | | | | | | | | | | | | | | | | | | | | | |
| 5 CONSULTANT SERVICE (DETAILED DESIGN, LAWFUL DOCUMENTS PREPARATION) | | | | DESIGN / LAWFUL DOCUMENT | | | WORK SUPERVISION | | | | | | | | | | | | | | | | |
| 6 BUILDER SELECTION | | | | | | | | | | | | | | | | | | | | | | | |
| 7 WORK EXECUTION | | | | | | | | | | | | | | | | | | | | | | | |
| 1) STRUCTURES BUILDING | | | | | | | | | | | | | | | | | | | | | | | |
| 2) REFORESTATION | | | | | | | | | | | | | | | | | | | | | | | |
| 3) EARLY ALERT SYSTEM | | | | | | | | | | | | | | | | | | | | | | | |
| 4) DISASTER PREVENTIVE TRAINING | | | | | | | | | | | | | | | | | | | | | | | |
| 8 FINISH WORK / DELIVERY TO USERS BOARDS | | | | | | | | | | | | | | | | | | | | | | | |

1.12 Institutions and management

The institutions and its administration in the investment stage and in the operation and maintenance stage after the investment shown in the Figures 1.12-1 and 1.12-2.




Figure 1.12-1 institutions related to the implementation of the project (investment stage)




Figure 1.12-2 institutions related to the implementation of the project (operation and maintenance phase of post-investment)

1.13 Logical Framework

Table 1.13-1 presents the logical framework of the final selected alternative.

Table 1.13-1 Logical framework of the final selected alternative

| Narrative Summary | Verifying Indicators | Verifying Indicators Media | Preliminary Conditions |
|--|---|--|--|
| Superior Goal | | | |
| Promote socioeconomic local development and contribute in communities' social welfare. | Improve local productivity, generate more jobs, increase population's income and reduce poverty index | Published statistic data | Scio-economic and policy stability |
| Objectives | | | |
| Relief the high vulnerability of valleys and local continuity to floods | Types, quantity and distribution of flood control works, population and beneficiaries areas | Monitoring annual calendar works and financial plan, budget execution control | Ensure the necessary budget, active intervention from central and regional governments, municipalities, irrigation communities, local population, etc. |
| Expected results | | | |
| Reduction of areas and flooded areas, functional improvement of intakes, road destruction prevention, irrigation channels protection, bank erosion control and Poechos dike safety | Number of areas and flooded areas, water intake flow variation, road destruction frequency, bank erosion progress and watershed's downstream erosion. | Site visits, review of the flood control plan and flood control works reports and periodic monitoring of local inhabitants | Maintenance monitoring by regional governments, municipalities and local community, provide timely information to the superior organisms |
| Activities | | | |
| Component A: Structural Measures | Dikes rehabilitation, intake and bank protection works, road damages prevention, construction of 28 works, including dike's safety | Detailed design review, works reports, executed expenses | Ensure the works budget, detailed design/works execution/good quality works supervision |
| Component B: Non-Structural Measures | | | |

| | | | |
|---|---|--|---|
| B-1 Reforestation and vegetation recovery | Reforested area, coastal forest area | Works advance reports, periodic monitor by local community | Consultants support, NGO's, local community, gathering and cooperation of lower watershed community |
| Component C: Disaster prevention and capabilities development education | Number of seminars, trainings, workshops, etc | Progress reports, local governments and community monitoring | Predisposition of the parties to participate, consultants and NGO's assessments |
| Project's execution management | | | |
| Project's management | Detailed design, work start order, work operation and maintenance supervision | Design plans, work's execution plans, costs estimation, works specifications, works management reports and maintenance manuals | High level consultants and contractors selection, beneficiaries population participation in operation and maintenance |

1.14 Middle and Long Term Plans

While it is true that due to the limited budget available for the Project, this study is focused mainly on the flood control measures analysis that must be implemented urgently. It is considered necessary to timely implement other necessary measures within a long term. In this section we will discuss the medium and long term plans.

(1) Flood Control General Plan

There are several ways to control floods in the entire watershed, for example, the building of dams, retarding basin, dikes or a combination of these. The options to build dams or retarding basin are not viable because in order to answer to a flood flow with a return period of 50 years, enormous works would be necessary to be built. So, the study was focused here on dikes' construction because it was the most viable option.

Flood water level was calculated in the watershed adopting a designed flood flow with a return period of 50 years. At this water level, freeboard was added in order to determine the required dikes height. After, sections of the rivers where the dikes or ground did not reach the required height were identified. These sections, altogether, add up to approx.136km. Also, from maintaining these works, annually a dragged of the rivers has to be done in the sections where, according to the bed fluctuation analysis the sediment gathering is elevating the bed's height. The volume of sediments that shall be eliminated annually was determined in approximately 11,000 m³.

In Tables 1.14-1 and 1.14-2 the flood control general plan project cost is shown as well as the social assessment results in terms of private and social costs.

**Table 1.14-1 Project Cost and Social Assessment of the general flood control plan
(private prices costs)**

| | 年平均被害軽減額 Annual Average Damage Reduction | 評価期間被害 軽減額(15年) Damage Reduction in Evaluation Period(15years) | 事業費 Project Cost | 維持管理費 O&M Cost | B/C Cost Benefit Ration | NPV Net Present Value | IRR(%) Internal Return of Rate |
|--------------|--|--|---------------------|-------------------|-------------------------------|-----------------------------|--------------------------------------|
| Majes-Camana | 285,833,001 | 129,076,518 | 465,857,392 | 29,096,617 | 0.31 | -291,140,628 | - |

**Table 1.14-2 Project Cost and Social Assessment of the general flood control plan
(social prices costs)**

| | 年平均被害軽減額 Annual Average Damage Reduction | 評価期間被害 軽減額(15年) Damage Reduction in Evaluation Period(15years) | 事業費 Project Cost | 維持管理費 O&M Cost | B/C Cost Benefit Ration | NPV Net Present Value | IRR(%) Internal Return of Rate |
|--------------|--|--|---------------------|-------------------|-------------------------------|-----------------------------|--------------------------------------|
| Majes-Camana | 294,878,168 | 133,161,136 | 374,549,343 | 23,393,680 | 0.39 | -204,693,450 | - |

In case of executing flood control works in the watershed, the works is not viable economically, and the Projects' cost would elevate to 465.9 million soles, which is a huge amount for this project..

(2) Reforestation Plan and Vegetation Recovery

The forestry option was analyzed, in a long term basis, to cover every area that requires being covered with vegetation in the upper watershed. The objective is improving this areas' infiltration capacity, reduce of surface water and increase semi-underground and underground water. So, the flood maximum flow will be decreased, also it could be possible to increase the water reserve in the mountain areas and prevent and soothe floods. The areas to be reforested will be the afforested areas or where the forest mass in the water infiltration areas has been lost.

In Table 1.14-3 the area to be afforested and the project's cost for the watershed is shown. These were calculated based on forestry plan of Chincha River. The total surface would be approximately 307,000hectares and in order to forest them the required time would be from 98 years and 829.2 million soles. To sum up, the Project has to cover an extensive area, with an investment of much time and at a high cost.

Table 1.14-3 General Plan for forestry on upper stream watersheds

| Watershed | Forestry Area (ha) A | Required Period for the project (years) B | Required Budget (1,000soles) C |
|---------------|----------------------------|--|--------------------------------------|
| Majes- Camana | 307,210 | 98 | 829,201 |

(3) Sediment Control Plan

As long term sediment control plan, it is recommended to perform necessary works on the upper watershed. These works will mainly consist of dams and bank protection. In Table 1.14-4 the estimate work cost is shown. There are two costs, one for executing works in the entire watershed and another one for executing works only in prioritized areas.

All the chosen watersheds for this Project are big. So, if bank protection works and sediment control dams want to be built, not only the works' cost would elevate but also a very long period of investment would have to be done in the watershed. This means that its positive impact will be seen in a long time.

**Table 1.14-4 Projects' General Costs of the Sediment Control Installations
Upstream the Watershed**

| Watersheds | Areas | Bank Protection | | Bands | | Dams | | Works direct cost (total) | Project Cost (in millions de s/.) |
|--------------|-------------------|-----------------|----------------------------------|------------|----------------------------------|------------|----------------------------------|---------------------------|-----------------------------------|
| | | Qty. (km) | Works direct costs (million s/.) | Qty. (No.) | Works direct costs (million s/.) | Qty. (No.) | Works direct costs (million s/.) | | |
| Majes-Camana | Totally | 264 | S/.282 | 26 | S/.1 | 123 | S/.165 | S/.448 | S/.843 |
| | Prioritized areas | 264 | S/.282 | 26 | S/.1 | 81 | S/.105 | S/.388 | S/.730 |

2. GENERAL ASPECTS

2.1 Name of the Project

“Protection program for valleys and rural communities vulnerable to floods Implementation of prevention measures to control overflows and floods of Majes-Camana River, Arequipa department”

2.2 Formulator and Executor Units

(1) Formulator Unit

Name: Hydraulic Infrastructure General Direction, Agriculture Ministry

Responsible: Orlando Chirinos Hernan Trujillo

General Director of the Water Infrastructure General Direction

Address: Av. Benavides N° 395 Miraflores, Lima 12 - Peru

Phone: (511) 4455457 / 6148154

Email: ochirinos@minag.gob.pe

(2) Executor Unit

Name: Sub-sectorial Irrigation Program, Agriculture Ministry

Manager: Jorge Zúñiga Morgan

Executive Director

Address: Jr. Emilio Fernandez N° 130 Santa Beatriz, Lima-Peru

Phone: (511) 4244488

Email: postmast@psi.gob.pe

2.3 Involved entities and Beneficiaries Participation

Here are the institutions and entities involved in this project, as well as beneficiaries.

(1) Agriculture Ministry (MINAG)

MINAG, as manager of natural resources of watersheds promotes agricultural development in each of them and is responsible of maintaining the economical, social and environmental to benefit agricultural development.

To accomplish effectively and efficiently this objective, the MINAG has been working since 1999 in the River Channeling and Collection Structures Protection Program (PERPEC). The river disaster prevention programs that are been carried out by regional governments are funded with PERPEC resources.

1) Administration Office (OA)

- Manages and executes the program's budget

- Establishes the preparation of management guides and financial affairs

2) Hydraulic Infrastructure general Direction (DGIH)

- Performs the study, control and implementation of the investment program
- Develops general guidelines of the program together with OPI

3) Planning and Investment Office (OPI)

- Conducts the preliminary assessment of the investment program
- Assumes the program's management and the execution of the program's budget
- Plans the preparation of management guides and financial affairs

4) Irrigation Sub-Sectorial Program (PSI)

- Carries-out the investment program approved by OPI and DGPM

(2) Economy and Finance Ministry (MEF)

Public Sector's Multiannual Programming General Direction (DGPM)

Is in charge of approving public investment works according to procedures under the Public Investment National System (SNIP) to assess the relevance and feasibility of processing the disbursement request of the national budget and the loan from JICA.

(3) Japan's International Cooperation Agency (JICA)

It is a Japanese government institution with the objective of contributing in the socioeconomic development of developing countries through international cooperation. JICA has extended financial assistance to carry out pre-feasibility and feasibility studies of this Project.

(4) Regional Governments (GORE)

Regional governments assume the promotion of integrated and sustainable regional development following the national and regional plans and programs, trying to increase public and private investment, generating employment opportunities, protecting citizens rights and ensuring equal opportunities.

The regional governments' participation with their possible financial support is a very important factor to ensure the Project's sustainability.

(5) Irrigation Commission

Currently there are 42 irrigation commissions in the Majes-Camana River Watershed. These have expressed a strong desire for the starting of works because these will help constructing dikes, protecting margins, repairing water intakes, etc. These commissions are currently suffering major damages due to rivers flooding. Next, a brief overview of the Majes-Camana River Watershed is described (for more details, see Section 3.1.3). Currently, the operation and maintenance of dikes, margin protection works, irrigation intakes and channels linked to agricultural land and irrigation systems in the Watershed, are mainly made by irrigation commissions and their members, with the assistance of local governments.

| | Majes River Watershed | Camana Watershed | River |
|--------------------------------------|-----------------------|---------------------|-------|
| Number of irrigation blocks: | 17 | 17 | |
| Number of Irrigation Commissions: | 45 | 38 | |
| Irrigated Area: | 7,505 ha | 6,796ha | |
| Beneficiaries: | 2.519 producers | 3,388 producers | |

(6) Meteorology and Hydrology National Service (SENAMHI)

It is an agency from the Environment Ministry responsible for all activities related to meteorology, hydrology, environment and agricultural meteorology. Take part in global level monitoring, contributing to sustainable development, security and national welfare, and gathering information and data from meteorological stations and hydrological observation.

(7) Civil Defense National Institute (INDECI)

INDECI is the main agency and coordinator of the Civil Defense National System. It is responsible for organizing and coordinating the community, elaborating plans and developing disaster risk's management processes. Its objective is to prevent or alleviate human life loss due to natural and human disasters and prevent destruction of property and the environment.

(8) Water National Authority (ANA)

It is the highest technical regulating authority in charge of promoting, monitoring and controlling politics, plans, programs and regulations regarding sustainable use of water resources nationwide.

Its functions include sustainable management of these resources, as well as improving the technical and legal framework on monitoring and assessment of water supply operations in each region.

Along with maintaining and promoting a sustainable use of water resources, it is also responsible for conducting the necessary studies and developing main maintenance plans, national and international economic and technical cooperation programs.

(9) Agriculture Regional Directorates (DRA's)

Agricultural regional addresses fulfill the following functions under the respective regional government:

- 1) Develop, approve, assess, implement, control and manage national agriculture policies, sectorial plans as well as regional plans and policies proposed by municipalities
- 2) Control agriculture activities and services fitting them to related policies and regulations, as well as on the regional potential
- 3) Participate in the sustainable management of water resources agreeing with the watershed's general

framework, as well as the policies of the Water National Authority (ANA)

4) Promote the restructure of areas, market development, export and agricultural and agro-industrial products consumption

5) Promote the management of: irrigation, construction and irrigation repair programs, as well as the proper management and water resources and soil conservation

2.4 Framework

2.4.1 Background

(1) Study Background

The Republic of Peru (hereinafter “Peru”) is a country with high risk of natural disasters such as earthquakes, Tsunamis, etc. Among these natural disasters there are also floods. In particular, El Niño takes place with an interval of several years and has caused major flood of rivers and landslides in different parts of the country. The most serious disaster in recent years due to El Niño occurred in the rainy season of 1982-1983 and 1997-1998. In particular, the period of 1997-1998, the floods, landslides, among others left loss of 3,500 million of dollars nationwide. The latest floods in late January 2010, nearby Machupicchu World Heritage Site, due to heavy rains interrupted railway and roads traffic, leaving almost 2,000 people isolated.

In this context, the central government has implemented El Niño phenomenon I and II contingency plans in 1997-1998, throughout the Agriculture and Livestock Ministry (MINAG) in order to rebuild water infrastructures devastated by this phenomenon. Next, the Hydraulic Infrastructure General Direction (DGIH) of the Agriculture Ministry (MINAG) began in 1999 the River Channeling and Collection Structures Protection Program (PERPEC) in order to protect villages, farmlands, agricultural infrastructure, etc located within flood risk areas. The program consisted of financial support for regional government to carry out works of margin protection. In the multiyear PERPEC plan between 2007-2009 it had been intended to execute a total of 206 margin protection works nationwide. These projects were designed to withstand floods with a return period of 50 years, but all the works have been small and punctual, without giving a full and integral solution to control floods. So, every time floods occur in different places, damages are still happening.

MINAG developed a “Valley and Rural Populations Vulnerable to Floods Protection Project” for nine watersheds of the five regions. However, due to the limited availability of experiences, technical and financial resources to implement a pre-investment study for a flood control project of such magnitude, MINAG requested JICA’s help to implementation this study. In response to this request, JICA and MINAG held discussions under the premise of implementing it in the preparatory study scheme to formulate a loan draft from AOD of JICA, about the content and scope of the study, the implementation’s schedule, obligations and commitments of both parties, etc. expressing the conclusions in the Discussions Minutes (hereinafter “M/D”) that were signed on January 21 and April

16, 2010. This study was implemented on this M/D.

(2) Progress of Study

The Profile Study Report for this Project at Program's level for nine watersheds of five regions has been elaborated by DGIH and sent to the Planning and Investment Office (OPI) on December 23, 2009, and approved on the 30th of the same month. Afterwards, DGIH presented the report to the Public Sector Multiannual Programming General Direction (DGPM) of the Economy and Finance Ministry (MEF) on January 18, 2010. On March 19th, DGPM informed DGIH about the results of the review and the correspondent comments.

The JICA Study Team began the study in Peru on September 5th, 2010. At the beginning, nine watersheds were going to be included in the study. One, the Ica River was excluded of the Peruvian proposal leaving eight watersheds. The eight watersheds were divided into two groups: Group A with five watersheds and Group B with three watersheds. The study for the first group was assigned to JICA and the second to DGIH. Group A includes Chira, Cañete, Chincha, Pisco and Yauca Rivers' Watersheds and Group B includes the Cumbaza, Majes and Camana Rivers' Watersheds.

The JICA Study Team conducted the profile study of the five watersheds of Group A, with an accurate pre-feasibility level and handed DGIH the Program Report of group A and the reports of the five watershed projects by late June 2011. Also, the feasibility study has already started, omitting the pre-feasibility study.

For the watersheds of Group B which study corresponded to DGIH, this profile study took place between mid-February and early March 2011 (and not with a pre-feasibility level, as established in the Meetings Minutes), where Cumbaza River Watershed was excluded because it was evident that it would not have an economic effect. The report on the Majes and Camana rivers watersheds were delivered to OPI, and OPI official comments were received through DGIH on April 26th, indicating that the performed study for these two watersheds did not meet the accuracy level required and it was necessary to study them again. Also, it was indicated to perform a single study for both rivers because they belong to a single watershed (Majes-Camana).

On the other hand, due to the austerity policy announced on March 31st, prior to the new government assumption by new president on July 28th, it has been noted that it is extremely difficult to obtain new budget, DGIH has requested JICA on May 6th to perform the prefeasibility and feasibility studies of the Majes-Camana Watershed.

JICA accepted this request and decided to perform the mentioned watershed study modifying for the second time the Meeting Minutes (refer to Meetings Minutes Second Amendment about the Initial

Report, Lima, July 22nd, 2011)

So, the JICA Study Team began in August the prefeasibility study for the watershed above mentioned, which was completed in late November.

This report corresponds with the pre-feasibility study of the Majes-Camana watershed project, of Group B. The feasibility study wants to be finished by mid-January 2012, and the feasibility study for all selected watersheds around the same dates.

Remember that DGIH processed on July 21st, the SNIP registration of four of the five watersheds from JICA (except Yauca), based on projects reports at pre-feasibility level (according to the watersheds). DHIG decided to discard Yauca River due to its low impact in economy.

2.4.2 Laws, regulations, policies and guidelines related to the Program

This program has been elaborated following the mentioned laws and regulations, policies and guidelines:

(1) Water Resources Law N° 29338

Article 75 .- Protection of water

The National Authority, in view of the Watershed Council, must ensure for the protection of water, including conservation and protection of their sources, ecosystems and natural assets related to it in the regulation framework and other laws applicable. For this purpose, coordination with relevant government institutions and different users must be done.

The National Authority, throughout the proper Watershed Council, executes supervision and control functions in order to prevent and fight the effects of pollution in the oceans, rivers and lakes. It can also coordinate for that purpose with public administration, regional governments and local governments sectors.

The State recognizes as environmentally vulnerable areas the headwater watersheds where the waters originate. The National Authority, with the opinion of the Environment Ministry, may declare protected areas the ones not granted by any right of use, disposition or water dumping.

Article 119 .- Programs flood control and flood disasters

The National Authority, together with respective Watershed Board, promotes integral programs for flood control, natural or manmade disasters and prevention of flood damages or other water impacts and its related assets. This promotes the coordination of structural, institutional and necessary operational measures.

Within the water planning, the development of infrastructure projects for multi-sectorial advantage is promoted. This is considered as flood control, flood protection and other preventive measures.

(2) Water Resources Law Regulation N° 29338

Article 118 .- From the maintenance programs of the marginal strip

The Water Administrative Authority, in coordination with the Agriculture Ministry , regional governments, local governments and water user organizations will promote the development of programs and projects of marginal strips forestry protection from water erosive action.

Article 259 ° .- Obligation to defend margins

All users have as duty to defend river margins against natural phenomenon effects, throughout all areas that can be influenced by an intake, whether it is located on owned land or third parties' land. For this matter, the correspondent projects will be submitted to be reviewed and approved by the Water National Authority.

(3) Water Regulation

Article 49. Preventive measures investments for crop protection are less than the recovery and rehabilitation cost measures. It is important to give higher priority to these protective measures which are more economic and beneficial for the country, and also contribute to public expenses savings.

Article 50. In case the cost of dikes and irrigation channels protection measures is in charge of family production units or it exceeds the payment capacity of users, the Government may pay part of this cost.

(4) Multi-Annual Sectorial Strategic Plan of the Agriculture Ministry for the period 2007-2011 (RM N° 0821-2008-AG)

Promotes the construction and repair of irrigation infrastructure works with the premise of having enough water resources and their proper use.

(5) Organic Law of the Agriculture Ministry, N° 26821

In Article 3, it is stipulated that the agricultural sector is responsible for executing river works and agricultural water management. This means that river works and water management for agricultural purposes shall be paid by the sector.

(6) Guidelines for Peruvian Agricultural Policy - 2002, by the Policy Office of MINAG

Title 10 - Sectorial Policies

“Agriculture is a high risk productive activity due to its vulnerability to climate events, which can be anticipated and mitigated... The damage cost to infrastructure, crops and livestock can be an obstacle for the development of agriculture, and as consequence, in the deterioration of local, regional and national levels.”

(7) River Channeling and Collection Structures Protection Program, PERPEC

The MINAG's DGIH started in 1999 the River Channeling and Collection Structures Protection Program (PERPEC) in order to protect communities, agricultural lands and facilities and other elements of the region from floods damages, extending financial support to margin protection works carried out by regional governments.

3. IDENTIFICATION

3.1 Diagnosis of the current situation

3.1.1 Nature

(1) Location

Figure 3.1.1-1 shows the location map of the Majes – Camana River



Base 800745 (B01044) 4-91

Figure 3.1.1-1 Objective River for the Study

(2) Watershed overall description

The Majes – Camana River runs 700 m to the south of the Capital of Lima. It is the river running at the most southern point of all the rivers object of the present Study and belongs to the Arequipa Region. The watershed surface is of 17,000 km² approximately and 60% of it is located above 4,000 m.a.s.l. The area object of the Project is approximately 100km from the river mouth, which is below 2,000 m.a.s.l, representing 20% of the total surface of the watershed.

The limit between Majes and Camana is located approximately 40 km from the rivers' mouth. From this point downstream the river is called “Camana” and “Majes” from this limit upstream. The slope of the riverbed is approximately 1/200 in Camana and 1/100 in Majes. Its width varies between 100 and 200 meters in Camana and between 200 and 500 meters in Majes. The river is wider in the upper part because, while in the lower part (Camana) the water course has been stabilized with dikes built by the irrigation commission, in the upper watershed (Majes) there are no sufficient dikes constructed.

Annual rainfalls show a clear tendency to increase in upper areas. This trend is such that they are of approximately 50 mm below 1,000 m.a.s.l and more than 500 mm above 4,000 m.a.s.l. The flow is abundant and the superficial water (fluvial) does not run out even in dried seasons.

As to vegetation, upper areas of more than 4,000 m.a.s.l represent 60% of the total area are covered by wetlands, while the lower areas below 2,000 m.a.s.l are desert. Flat lands along the river are being used, mostly for agriculture, particularly for irrigated rice crops.

3.1.2 Socio-economic conditions of the Study Area

(1) Administrative Division and Surface

The Majes – Camana River is located in the provinces of Castilla and Camana in the Arequipa Region. Table 3.1.2-1 shows the main districts surrounding this river, with their corresponding surface.

Table 3.1.2-1 Districts surrounding the Majes – Camana River with areas

| Region | Province | District | Area (Km ²) |
|----------|----------|--------------------|-------------------------|
| Arequipa | Castilla | Uraca | 713.83 |
| | | Aplao | 640.04 |
| | | Huancarqui | 803.65 |
| | Camana | Camana | 11.67 |
| | | Nicolas de Pierola | 391.84 |
| | | Mariscal Caceres | 579.31 |
| | | Samuel Pastor | 113.4 |
| | | Jose Maria Quimper | 16.72 |

(2) Population and number of households

The following Table 3.1.2-2 shows how population varied within the period 1993-2007. In 2007, from 44,175 inhabitants, 91% (40,322 inhabitants) lived in urban areas while 9% (3,853 inhabitants) lived in rural areas.

Population is increasing in all districts. However, while the urban area registers an annual medium increase of 2.8% to 3.4%, exceeding the national average, the rural area experiments a decrease of -1.3% to -6.6%.

Table 3.1.2-2 Variation of the urban and rural population

| Province | District | 2007 Total Population | | | | | 1993 Total Population | | | | | Variation (%) | |
|--------------|--------------------|-----------------------|---------------|--------------|---------------|---------------|-----------------------|------------|---------------|------------|---------------|---------------|---------------|
| | | Urban | % | Rural | % | Total | Urban | % | Rural | % | Total | Urban | Rural |
| Castilla | Uraca | 2,664 | 37% | 4,518 | 63% | 7,182 | 1,953 | 29% | 4,698 | 71% | 6,651 | 2.20% | -0.30% |
| | Aplao | 4,847 | 45% | 4,004 | 55% | 8,851 | 2,928 | 35% | 5,334 | 65% | 8,262 | 3.70% | -2.00% |
| | Huancarqui | 1,191 | 18% | 254 | 82% | 1,445 | 1,047 | 65% | 555 | 35% | 1,602 | 0.90% | -5.40% |
| Total | | 8,702 | 49.80% | 8,776 | 50.20% | 17,478 | 5,928 | 36% | 10,587 | 64% | 16,515 | 2.80% | -1.30% |
| Camana | Camana | 14,642 | 1% | 116 | 99% | 14,758 | 13,284 | 94% | 809 | 6% | 14,093 | 0.70% | -13.00% |
| | Nicolas de Pierola | 5,362 | 88% | 703 | 12% | 6,065 | 4,688 | 88% | 613 | 12% | 5,301 | 1.00% | 1.00% |
| | Mariscal Caceres | 4,705 | 86% | 758 | 14% | 5,463 | 2,562 | 67% | 1,253 | 33% | 3,815 | 4.40% | -3.50% |
| | Samuel Pastor | 12,004 | 91% | 1,138 | 9% | 13,142 | 2,285 | 26% | 6,501 | 74% | 8,786 | 12.60% | -11.70% |
| | Jose Maria Quimper | 3,609 | 76% | 1,138 | 24% | 4,747 | 2,426 | 74% | 870 | 26% | 3,296 | 2.90% | 1.90% |
| Total | | 40,322 | 91.30% | 3,853 | 8.70% | 44,175 | 25,245 | 72% | 10,046 | 28% | 35,291 | 3.40% | -6.60% |

Source: Prepared by JICA Study Team, Statistics National Institute- INEI, 2007 and 1993 Population and Housing Census.

Table 3.1.2-3 -4 shows the number of households and members per home in 2007. Apparently Huancarqui has fewer members per household (3.36 persons) while Jose Maria Quimper has a greater number with 4.4; remaining districts vary between 3,6 and 4,1 persons.

The number of members per family is around 4,1 persons, with exception of Nuevo Imperial, with a lower Figure of 3.77.

Table 3.1.2-3 Number of households and families in Castilla

| Variables | District | | |
|---|----------|-------|------------|
| | Uraca | Aplao | Huancarqui |
| Population (inhabitants) | 7,182 | 8,851 | 1,445 |
| Number of households | 1,760 | 2,333 | 430 |
| Number of families | 1,887 | 2,416 | 434 |
| Members per household (persons/household) | 4.08 | 3.79 | 3.36 |
| Members per family (persons/family) | 3.81 | 3.66 | 3.33 |

Table 3.1.2-4 Number of households and families in Camana

| Variables | District | | | | |
|---|----------|--------------------|------------------|---------------|--------------------|
| | Camana | Nicolas de Pierola | Mariscal Caceres | Samuel Pastor | Jose Maria Quimper |
| Population (inhabitants) | 14,758 | 6,065 | 5,463 | 13,142 | 4,747 |
| Number of households | 3,845 | 1,680 | 1,394 | 3,426 | 1,078 |
| Number of families | 4,066 | 1,738 | 1,448 | 3,554 | 1,108 |
| Members per household (persons/household) | 3.84 | 3.61 | 3.92 | 3.84 | 4.4 |
| Members per family (persons/family) | 3.63 | 3.49 | 3.77 | 3.7 | 4.28 |

(3) Occupation

Table 3.1.2-5, shows occupation lists of local inhabitants itemized by sector.

It highlights the primary sector in all districts representing between 23 and 65% of the economically active population (EAP).

Table 3.1.2-5 Occupation in Castilla

| EAP | Uraca | | Aplao | | Huancarqui | |
|--|---------|-------|---------|-------|------------|-------|
| | persons | % | Persons | % | Persons | % |
| Economically Active Pop. ^{1/} | 3,343 | 100 | 3,618 | 100 | 649 | 100 |
| a) Primary sector | 2,174 | 65.03 | 1,966 | 54.34 | 413 | 63.64 |
| b) Secondary sector | 160 | 4.79 | 251 | 6.94 | 40 | 6.16 |
| c) Tertiary sector | 1,009 | 30.18 | 1,401 | 38.72 | 196 | 30.2 |

Source: National Institute of Statistics - INEI, 2007 Population and Housing Census.

^{1/} Primary sector: agriculture, livestock, forest and fishery; secondary: mining, construction, manufacturing; tertiary: services and others

Table 3.1.2-6 Occupation in Camana

| PEA | District | | | | | | | | | |
|--|---------------|-----|---------|-----|--------------------|-----|------------------|-----|--------------------|-----|
| | Samuel Pastor | | Camana | | Jose Maria Quimper | | Mariscal Cáceres | | Nicolas de Pierola | |
| | persons | % | persons | % | persons | % | persons | % | persons | % |
| Economically Active Pop. ^{1/} | 5,237 | 100 | 6,292 | 100 | 1,463 | 100 | 1,888 | 100 | 2,348 | 100 |
| a) Primary sector | 1,749 | 33 | 1,469 | 23 | 548 | 37 | 1,181 | 63 | 1,125 | 48 |
| b) Secondary sector | 624 | 12 | 473 | 8 | 127 | 9 | 88 | 5 | 167 | 7 |
| c) Tertiary sector | 2,864 | 55 | 4,350 | 69 | 788 | 54 | 619 | 33 | 1,056 | 45 |

Source: National Institute of Statistics - INEI, 2007 Population and Housing.

^{1/} Primary sector: agriculture, livestock, forest and fishery; secondary: mining, construction, manufacturing; tertiary: services and others

(4) Poverty index

Table 3.1.2-7, -8 shows the poverty index. 25 % to 27 % of the districts' population belongs to the poor segment, and 3.8% to 4.4% belong to extreme poverty. Particularly, the Huancarqui district stands out for its high poverty percentage with 33.1%, and 6,9% of extreme poverty.

Table 3.1.2-7 Poverty index in Castilla

| Variable /Indicator | District (Castilla) | | | | | | | |
|----------------------------------|---------------------|------|------------|------|---------|------|-----------|-----|
| | Aplao | | Huancarqui | | Uraca | | Total | |
| | Persons | % | Persons | % | Persons | % | Persons | % |
| Total Population (inhab.) | 8,851 | | 1,445 | | 7,182 | | 17,478.00 | 100 |
| Poor | 2,153 | 24.3 | 480 | 33.1 | 1,731 | 24.1 | 4,364 | 25 |
| Extreme Poverty | 358 | 4.1 | 98 | 6.9 | 305 | 4.3 | 761 | 4.4 |

Table 3.1.2-8 Poverty index in Camana

| Variable /Indicator | District (Canana) | | | | | | | | | | | |
|--------------------------|-------------------|------|---------------|------|--------------------|------|--------------------|------|-----------|------|-----------|------|
| | Mariscal Caceres | | Samuel pastor | | Nicolas de Pierola | | Jose Maria Quimper | | Camana | | Total | |
| | Persons | % | Persons | % | Persons | % | Persons | % | Persons | % | Persons | % |
| Total Population (inhab) | 5,463 | | 13,142 | | 6,065.00 | | 4,747.00 | | 14,758.00 | | 44,175.00 | 100 |
| Poor | 1,927 | 35.2 | 4,410.00 | 33.5 | 1,494.00 | 24.6 | 979 | 24.9 | 3,013.00 | 20.4 | 11,823 | 26.8 |
| Extreme Poverty | 391 | 7.4 | 629 | 4.9 | 221 | 3.8 | 140 | 3.7 | 303 | 2.1 | 1,684 | 3.8 |

(5) Type of housing

Tables 3-1.2-9 and 3-1.2-10 show data on Castilla and Camana housing. The walls of the houses in Castilla are made 46% of bricks or cement, and 43% of adobe and mud. The floor is made 96% of earth or cement. The public drinking water service covers 50%, while the sewage service is scarcely 45.5% in Huancarqui. The average electrification rate is 86%.

In Camana, walls are made 65% bricks or cement, and 4% with adobe and mud. The floor is made of 98% earth or cement. The public drinking water service covers more than 50% while the sewage service is less than 50%, with exception of Camana. The average electrification rate is 84%.

Table 3.1.2-9 Type of housing in Castilla

| Variable/Indicator | Districts | | | | | |
|---|------------|------|------------|------|------------|------|
| | Uraca | | Aplao | | Huancarqui | |
| | Households | % | Households | % | Households | % |
| Number of Households | | | | | | |
| Common houses with residents | 1,760 | 86 | 2,333 | 75.3 | 430 | 63 |
| Wall material | | | | | | |
| Brick or cement | 999 | 56.8 | 820 | 35.1 | 106 | 24.7 |
| Adobe and mud | 195 | 11.1 | 1,067 | 45.7 | 237 | 55.1 |
| With walls of quincha and wood | 521 | 29.6 | 332 | 14.2 | 78 | 18.1 |
| Other | 45 | 2.6 | 114 | 4.9 | 9 | 2.1 |
| Floor material | | | | | | |
| Earth | 687 | 39 | 831 | 35.6 | 195 | 45.3 |
| Cement | 996 | 56.6 | 1,381 | 59.2 | 226 | 52.6 |
| Tile, terrazzo tile, parquet or polished wood, wood, boards | 71 | 4 | 106 | 4.5 | 7 | 1.6 |
| Other | 6 | 0.3 | 15 | 0.6 | 2 | 0.5 |
| Drinking water system | | | | | | |
| Public service in the house | 1,216 | 69.1 | 1,483 | 63.6 | 255 | 59.3 |
| Public service out of the house but within the building | 86 | 4.9 | 228 | 9.8 | 20 | 4.7 |
| Public sink | 115 | 6.5 | 34 | 1.5 | | |
| Sewage and latrine service | | | | | | |
| Public sewage service in the house | 472 | 26.8 | 705 | 30.2 | 193 | 44.9 |
| Public sewage service within the building | 26 | 1.5 | 58 | 2.5 | 4 | 0.9 |
| Cesspit/ latrine | 753 | 42.8 | 875 | 37.5 | 153 | 35.6 |
| Houses with lighting system | | | | | | |
| Public network | 1,505 | 85.5 | 1,790 | 76.7 | 340 | 79.1 |
| HOUSEHOLD | | | | | | |
| Households in special houses with present occupants | 1,887 | 100 | 2,416 | 100 | 434 | 100 |
| Head of household | | | | | | |
| Man | 1,477 | 78.3 | 1,839 | 76.1 | 335 | 77.2 |
| Woman | 410 | 21.7 | 577 | 23.9 | 99 | 22.8 |
| Home appliances | | | | | | |
| Has three or more home appliances or equipment | 541 | 28.7 | 683 | 28.3 | 113 | 26 |
| Information and communication service | | | | | | |
| Has landline telephone or mobile | 1,353 | 71.7 | 1,301 | 53.8 | 242 | 55.8 |

Source: Prepared by JICA Study Team, Statistics National Institute- INEI, 2007 Population and Housing Census.

Table 3.1.2-10 Type of housing in Camana

| Variable/Indicador | Samuel Pastor | | Camana | | Jose Maria Quimper | | Mariscal Caceres | | Nicolas d |
|---|---------------|------------|--------------|------------|--------------------|------------|------------------|------------|--------------|
| | Households | % | Households | % | Households | % | Households | % | Households |
| Number of Households | | | | | | | | | |
| Common houses with residents | 3,426 | 69.7 | 3,845 | 90.7 | 1,078 | 74.7 | 1,394 | 70 | 1,680 |
| Wall material | | | | | | | | | |
| Brick or cement | 1,956 | 57.1 | 2,942 | 76.5 | 674 | 62.5 | 664 | 47.6 | 986 |
| Adobe and mud | 66 | 1.9 | 175 | 4.6 | 20 | 1.9 | 28 | 2 | 78 |
| With walls of quincha and wood | 716 | 20.9 | 427 | 11.1 | 226 | 21 | 172 | 12.3 | 419 |
| Other | 688 | 20.1 | 301 | 7.8 | 158 | 14.7 | 530 | 38 | 197 |
| Floor material | | | | | | | | | |
| Earth | 1,780 | 52 | 961 | 25 | 487 | 45.2 | 841 | 60.3 | 792 |
| Cement | 1,432 | 41.8 | 2,335 | 60.7 | 547 | 50.7 | 530 | 38 | 806 |
| Tile, terrazzo tile, parquet or polished wood, wood, boards | 154 | 4.5 | 514 | 13.4 | 38 | 3.5 | 16 | 1.1 | 70 |
| Other | 60 | 1.8 | 35 | 0.9 | 6 | 0.6 | 7 | 0.5 | 12 |
| Drinking water system | | | | | | | | | |
| Public service in the house | 1,987 | 58 | 3,028 | 78.8 | 732 | 67.9 | 774 | 55.5 | 957 |
| Public service out of the house but within the building | 231 | 6.7 | 236 | 6.1 | 108 | 10 | 160 | 11.5 | 323 |
| Public sink | 851 | 24.8 | 164 | 4.3 | 13 | 1.2 | 9 | 0.6 | 57 |
| Sewage and latrine service | | | | | | | | | |
| Public sewage service in the house | 1,466 | 42.8 | 2,816 | 73.2 | 181 | 16.8 | 243 | 17.4 | 778 |
| Public sewage service within the building | 104 | 3 | 246 | 6.4 | 24 | 2.2 | 5 | 0.4 | 208 |
| Cesspit/latrine | 1,144 | 33.4 | 360 | 9.4 | 526 | 48.8 | 763 | 54.7 | 463 |
| Houses with lighting system | | | | | | | | | |
| Public network | 2,734 | 79.8 | 3,556 | 92.5 | 935 | 86.7 | 1,017 | 73 | 1,284 |
| HOUSEHOLD | | | | | | | | | |
| Households in special houses with present occupants | 3,554 | 100 | 4,066 | 100 | 1,108 | 100 | 1,448 | 100 | 1,738 |
| Home appliances | | | | | | | | | |
| Has three or more home appliances or equipment | 997 | 28.1 | 1,902 | 46.8 | 360 | 32.5 | 304 | 21 | 524 |
| Information and communication service | | | | | | | | | |
| Has landline telephone or mobile | 2,297 | 64.6 | 3,586 | 88.2 | 790 | 71.3 | 654 | 45.2 | 1,073 |

Source: Prepared by JICA Study Team, Statistics National Institute–INEI, 2007 Population and Housing Census.

(6) GDP

Peru's GDP in 2009 was S./392,565,000,000.

The growth rate in the same year was of + 0.9 % compared with the previous year with the poorest level within 11 years.

Itemized by regions, Ica registered a growth of 3,8 %, Piura 2.0 %, Lima 0.4 % and Arequipa 0.2 %. Particularly Ica and Piura regions registered Figures that were beyond the national average.





Figure 3.1.2-1 Growth rate of GDP per region (2009/2008)

The table below shows the contribution of each region to the GDP. Lima Region represents almost half of the total, that is to say 44.8%. Arequipa contributed with 5.3 %, Piura 4.6 % and Ica 2.9 %. Taxes and duties contributed with 7.2 % and 0.4 %, respectively.




INEI Source – National Accounts National Direction

Figure 3.1.2-2 Region contribution to GDP

The GDP per capita in 2009 was of S/.13,475.

The Table below shows data per region: Lima S/.17,800, Arequipa S/.17,200, Ica S/.15,600 and Piura S/.10,200. The first three regions exceeded the national average, with exception of Piura.



INEI Source – National Accounts National Direction

Figure 3.1.2-3 GDP per capita (2009)

Table 3.1.2-7 shows the variation along the years of the GDP per capita per region, during the last 9 years (2001-2009).

The GDP national average increased in 44% within nine years from 2001 until 2009. The Figures per region are: +83.9 % for Ica, +54.2 % for Arequipa, +48.3 % for Piura y +42.9 % for Lima.

Figures in Table 3.1.2-11 were established taking 1994 as base year.

Table 3.1.2-11 Variation of the GDP per capita (2001-2009)

(1994 Base year, S/.)

| Departament | 2001 | 2002 | 2003 | 2004 | 2005 | 2006 | 2007P/ | 2008P/ | 2009E/ | Accumulated Growth 2001-2009 (%) |
|---------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|----------------------------------|
| Cusco | 2 194 | 2 086 | 2 195 | 2 565 | 2 768 | 3 071 | 3 340 | 3 554 | 3 685 | 67,9 |
| Ica | 4 055 | 4 259 | 4 343 | 4 663 | 5 214 | 5 582 | 6 025 | 7 265 | 7 457 | 83,9 |
| La Libertad | 3 162 | 3 316 | 3 483 | 3 410 | 3 697 | 4 216 | 4 586 | 4 874 | 4 895 | 54,8 |
| Ucayali | 3 063 | 3 149 | 3 203 | 3 411 | 3 584 | 3 754 | 3 846 | 4 007 | 4 039 | 31,9 |
| Moquegua | 10 405 | 11 967 | 12 670 | 13 455 | 13 882 | 13 794 | 13 606 | 14 201 | 13 865 | 33,3 |
| Arequipa | 5 387 | 5 766 | 5 895 | 6 143 | 6 488 | 6 807 | 7 786 | 8 379 | 8 308 | 54,2 |
| Apurimac | 1 216 | 1 278 | 1 334 | 1 400 | 1 494 | 1 619 | 1 653 | 1 691 | 1 770 | 45,5 |
| Piura | 2 733 | 2 780 | 2 847 | 3 049 | 3 192 | 3 472 | 3 780 | 4 007 | 4 052 | 48,3 |
| San Martín | 2 026 | 2 059 | 2 094 | 2 232 | 2 393 | 2 476 | 2 655 | 2 870 | 2 928 | 44,5 |
| Ayacucho | 1 788 | 1 870 | 1 942 | 1 900 | 2 045 | 2 207 | 2 448 | 2 640 | 2 896 | 61,9 |
| Amazonas | 1 835 | 1 910 | 1 996 | 2 081 | 2 212 | 2 349 | 2 510 | 2 684 | 2 761 | 50,5 |
| Madre de Dios | 4 441 | 4 708 | 4 550 | 4 846 | 5 171 | 5 215 | 5 617 | 5 878 | 5 564 | 25,3 |
| Cajamarca | 2 493 | 2 731 | 2 947 | 2 968 | 3 165 | 3 113 | 2 864 | 3 094 | 3 295 | 32,2 |
| Ancash | 4 037 | 4 703 | 4 772 | 4 876 | 4 999 | 5 089 | 5 408 | 5 852 | 5 827 | 44,3 |
| Tumbes | 2 744 | 2 802 | 2 873 | 3 018 | 3 385 | 3 212 | 3 427 | 3 594 | 3 611 | 31,6 |
| Lima | 6 451 | 6 579 | 6 700 | 6 925 | 7 284 | 7 817 | 8 520 | 9 314 | 9 220 | 42,9 |
| Puno | 2 105 | 2 236 | 2 234 | 2 270 | 2 365 | 2 460 | 2 617 | 2 731 | 2 800 | 33,0 |
| Lambayeque | 2 941 | 3 046 | 3 132 | 2 959 | 3 164 | 3 300 | 3 615 | 3 882 | 3 963 | 34,8 |
| Junín | 3 245 | 3 311 | 3 350 | 3 527 | 3 505 | 3 856 | 4 072 | 4 379 | 4 248 | 30,9 |
| Loreto | 2 827 | 2 917 | 2 936 | 2 995 | 3 079 | 3 192 | 3 287 | 3 402 | 3 429 | 21,3 |
| Huánuco | 1 678 | 1 694 | 1 833 | 1 866 | 1 890 | 1 915 | 1 942 | 2 050 | 2 044 | 21,8 |
| Passo | 5 137 | 5 552 | 5 481 | 5 634 | 5 644 | 6 062 | 6 711 | 6 729 | 6 349 | 23,6 |
| Tacna | 6 004 | 6 124 | 6 382 | 6 643 | 6 782 | 6 941 | 7 256 | 7 458 | 7 253 | 20,8 |
| Huancavelica | 2 700 | 2 632 | 2 683 | 2 697 | 2 864 | 3 014 | 2 903 | 2 959 | 3 039 | 12,5 |
| GDP | 4 601 | 4 765 | 4 890 | 5 067 | 5 345 | 5 689 | 6 121 | 6 643 | 6 625 | 44,0 |

INEI Source – National Accounts National Direction

3.1.3 Agriculture

Next is a summarized report on the current situation of agriculture in the Watershed of the Majes – Camana River, including irrigation commissions, crops, planted area, performance, sales, etc.

(1) Irrigation Sectors

Table 3.1.3-1 and 3.1.3-2 shows basic data on the irrigation commissions of the Majes River and the Camana River, respectively. In the first one there are 45 irrigation sectors, 17 irrigation commissions with 2,519 beneficiaries. The surface managed by these sectors reach a total of 7,505 hectares.

In the watershed of the Camana River there are 38 irrigation sectors, 17 irrigation commissions with 3,388 beneficiaries. The surface managed by these sectors amounts 6,796 hectares.

Table 3.1.3-1 Basic data of the irrigation commissions in the Majes River

| Irrigation Commissions | Irrigation sectors | Irrigated areas | | N° de Beneficiaries | River |
|------------------------|------------------------|-----------------|-------------|---------------------|-------|
| | | ha | % | (Person) | |
| Ongoro | Las Joyitas Las Palmas | 8.08 | 0.11% | 4 | Majes |
| | Andamayo | 94.35 | 1.26% | 25 | |
| | Luchea | 35.26 | 0.47% | 24 | |
| | Ongoro | 368.13 | 4.91% | 65 | |
| | Huatiapilla | 367.26 | 4.89% | 75 | |
| | La Central | 406.57 | 5.42% | 66 | |
| | El Castillo | 623.05 | 8.30% | 73 | |
| | La Banda | 4.15 | 0.06% | 3 | |
| | Jaran | 3.52 | 0.05% | 6 | |
| Ongoro Bajo | Huanco Iquiapaza | 4.46 | 0.06% | 11 | |
| | Huatiapilla Baja | 103.62 | 1.38% | 23 | |
| | Alto Huatiapa | 44.47 | 0.59% | 20 | |
| | Bajo Huatiapa | 19.11 | 0.25% | 8 | |
| | Quiscay | 17.84 | 0.24% | 1 | |
| Beringa | San Isidro | 10.53 | 0.14% | 3 | |
| | Beringa | 109.07 | 1.45% | 80 | |
| Huancarqui | La Collpa | 14.93 | 0.20% | 14 | |
| | Huancarqui | 342.56 | 4.56% | 211 | |
| Cosos | Cosos | 125.43 | 1.67% | 92 | |
| Aplao | Aplao | 232.26 | 3.09% | 145 | |
| | Bajos Aplao | 11.50 | 0.15% | 5 | |
| La Real | Caspani | 20.54 | 0.27% | 18 | |
| | La Real | 172.07 | 2.29% | 125 | |
| Monte los Apuros | Monte los Apuros | 370.86 | 4.94% | 160 | |
| Querulpa | Alto Maran Trapiche | 131.78 | 1.76% | 53 | |
| | La Revilla Valcarcel | 151.01 | 2.01% | 50 | |
| Tomaca | Tomaca | 296.32 | 3.95% | 54 | |
| | El Rescate | 92.34 | 1.23% | 41 | |
| Uraca | Uraca | 688.81 | 9.18% | 239 | |
| Cantas Pedregal | Alto Cantas | 162.87 | 2.17% | 74 | |
| | Bajo Cantas | 147.09 | 1.96% | 47 | |
| Sogiata | Sogiata | 522.66 | 6.96% | 154 | |
| San Vicente | San Vicente | 230.68 | 3.07% | 100 | |
| | Caceres | 57.31 | 0.76% | 12 | |
| Pitis | Pitis | 93.10 | 1.24% | 53 | |
| | Escalerillas | 155.61 | 2.07% | 74 | |
| Sarcas Toran | Sarcas Toran | 777.69 | 10.36% | 195 | |
| | Hinojosa Pacheco | 1.00 | 0.01% | 2 | |
| | Medrano | 12.29 | 0.16% | 7 | |
| | La Cueva | 6.24 | 0.08% | 6 | |
| | Callan Jaraba | 37.91 | 0.51% | 10 | |
| | Sahuani | 58.47 | 0.78% | 17 | |
| | Paycan | 24.44 | 0.33% | 6 | |
| | Vertiente | 2.29 | 0.03% | 3 | |
| El Granado | El Granado | 345.45 | 4.60% | 65 | |
| Total | | 7,504.98 | 100% | 2,519 | |

Source: Prepared by JICA Study Team, Users Board of Camana-Majes, September 2011

Table 3.1.3-2 Basic data of irrigation commissions in the Camana River

| Irrigation Commission | Irrigation Sectors | Irrigated areas | | N° de Beneficiaries | River |
|-----------------------|-------------------------|-----------------|-------------|---------------------|--------|
| | | ha | % | (Person) | |
| Socso-Sillan | Huambo | 28.23 | 0.42% | 8 | Camana |
| | Puccor | 13.30 | 0.20% | 2 | |
| | Pillistay | 13.91 | 0.20% | 6 | |
| | Nueva Esperanza | 27.31 | 0.40% | 19 | |
| | Socso | 52.97 | 0.78% | 15 | |
| | Socso Medio | 21.27 | 0.31% | 12 | |
| | Casias-Sillan | 45.32 | 0.67% | 20 | |
| Sonay | Sonay | 110.48 | 1.63% | 34 | |
| Pisques | Pisques | 86.82 | 1.28% | 39 | |
| Characta | Soto | 16.29 | 0.24% | 4 | |
| | Characta | 174.35 | 2.57% | 54 | |
| Pampata | Naspas-Pampata | 130.31 | 1.92% | 21 | |
| | Pampata-Baja | 164.77 | 2.42% | 27 | |
| La Bombon | Tirita | 15.67 | 0.23% | 12 | |
| | Montes Nuevos | 49.41 | 0.73% | 26 | |
| | La Bombon | 402.38 | 5.92% | 265 | |
| | Gordillo | 8.14 | 0.12% | 9 | |
| | La Era | 1.44 | 0.02% | 4 | |
| | La Rama Era I | 45.53 | 0.67% | 37 | |
| | Toma Davila | 58.20 | 0.86% | 11 | |
| El Alto | El Alto | 314.57 | 4.63% | 128 | |
| Los Molinos | Los Molinos | 435.97 | 6.41% | 295 | |
| El Medio | El Medio | 477.98 | 7.03% | 231 | |
| | Los Castillos | 44.36 | 0.65% | 48 | |
| | Flores | 4.73 | 0.07% | 5 | |
| La Valdivia | El Desague | 45.56 | 0.67% | 55 | |
| | La Lurin | 17.35 | 0.26% | 11 | |
| | La Chingana | 51.27 | 0.75% | 33 | |
| | La Valdivia | 323.86 | 4.77% | 196 | |
| La Deheza | La Deheza | 336.71 | 4.95% | 228 | |
| La Gamero | La Gamero | 356.04 | 5.24% | 257 | |
| El Molino | El Molino | 370.29 | 5.45% | 302 | |
| El Cuzco | El Cuzco | 290.02 | 4.27% | 261 | |
| Montes Nuevos | Montes Nuevos | 192.46 | 2.83% | 123 | |
| Huacapuy | Huacapuy | 23.12 | 0.34% | 21 | |
| Pucchun | Mal Paso-Sta. Elizabeth | 1070.90 | 15.76% | 296 | |
| | 1er y 2do Canal Aereo | 872.79 | 12.84% | 202 | |
| | Jahuay | 102.11 | 1.50% | 71 | |
| Total | | 6,796.19 | 100% | 3,388 | |

Source: Prepared by JICA Study Team, Users Board of Camana-Majes, September 2011

(2) Main crops

Table 3.1.3-3 shows the variation between 2004 and 2009 of the planted surface and the

performance of main crops.

In the Majes – Camana River Watershed, in 2004 the planted area, performance and sales decreased, but later increased so that during the period 2008-2009 profits were of S/.188,596,716. Main crops in this watershed were represented by: rice, beans, onions, corn and pumpkins.

Table 3.1.3-3 Sowing and sales of main crops

| | Variables | 2004-2005 | 2005-2006 | 2006-2007 | 2007-2008 | 2008-2009 |
|-------------|--------------------------|-------------|-------------|-------------|-------------|-------------|
| Paddy Rice | Sown surface (ha) | 6,216 | 6,246 | 6,211 | 6,212 | 6,224 |
| | Unit performance (kg/Ha) | 12,041 | 13,227 | 12,841 | 13,370 | 13,823 |
| | Harvest (Kg) | 74,844,450 | 82,617,571 | 79,753,422 | 83,057,334 | 86,032,532 |
| | Unit price (S/./kg) | 0.92 | 0.65 | 0.80 | 1.10 | 0.70 |
| | Sales (S/.) | 68,868,814 | 53,701,421 | 63,802,738 | 91,354,778 | 60,222,772 |
| Dried beans | Sown surface (ha) | 4,458 | 4,433 | 3,947 | 4,045 | 3,886 |
| | Unit performance (kg/Ha) | 1,630 | 1,660 | 1,745 | 1,743 | 1,920 |
| | Harvest (Kg) | 7,264,349 | 7,359,607 | 6,888,684 | 7,051,876 | 7,460,849 |
| | Unit price (S/./kg) | 2.93 | 2.44 | 3.03 | 4.12 | 3.85 |
| | Sales (S/.) | 21,304,797 | 17,970,689 | 20,888,054 | 29,058,175 | 28,746,981 |
| Onion | Sown surface (ha) | 2,063 | 1,958 | 2,168 | 2,331 | 1,886 |
| | Unit performance (kg/Ha) | 40,552 | 32,073 | 41,231 | 46,034 | 35,840 |
| | Harvest (Kg) | 83,659,519 | 62,798,588 | 89,388,731 | 107,304,225 | 67,594,277 |
| | Unit price (S/./kg) | 0.58 | 0.38 | 0.71 | 0.43 | 1.37 |
| | Sales (S/.) | 48,800,305 | 24,067,447 | 63,582,270 | 46,002,256 | 92,290,918 |
| Corn | Sown surface (ha) | 50 | 30 | 34 | 618 | 558 |
| | Unit performance (kg/Ha) | 4,192 | 3,500 | 3,680 | 5,670 | 4,580 |
| | Harvest (Kg) | 209,600 | 105,000 | 125,120 | 3,503,916 | 2,555,501 |
| | Unit price (S/./kg) | 0.85 | 0.80 | 1.00 | 0.90 | 0.75 |
| | Sales (S/.) | 178,160 | 84,000 | 125,120 | 3,153,524 | 1,918,916 |
| Pumpkin | Sown surface (ha) | 193 | 223 | 217 | 129 | 159 |
| | Unit performance (kg/Ha) | 29,341 | 34,419 | 32,869 | 40,346 | 42,789 |
| | Harvest (Kg) | 5,662,900 | 7,675,350 | 7,132,607 | 5,204,624 | 6,803,456 |
| | Unit price (S/./kg) | 0.36 | 0.30 | 0.30 | 0.41 | 0.26 |
| | Sales (S/.) | 2,056,542 | 2,295,721 | 2,123,348 | 2,154,472 | 1,786,014 |
| Chala Corn | Sown surface (ha) | 55 | 35 | 38 | 29 | 44 |
| | Unit performance (kg/Ha) | 60,800 | 59,435 | 59,962 | 60,675 | 58,332 |
| | Harvest (Kg) | 3,344,000 | 2,080,242 | 2,278,540 | 1,759,566 | 2,566,613 |
| | Unit price (S/./kg) | 0.08 | 0.10 | 0.10 | 0.10 | 0.25 |
| | Sales (S/.) | 267,520 | 208,024 | 227,854 | 175,957 | 633,487 |
| Sweet Corn | Sown surface (ha) | 51 | 40 | 27 | 19 | 51 |
| | Unit performance (kg/Ha) | 16,980 | 17,694 | 18,053 | 18,201 | 18,223 |
| | Harvest (Kg) | 865,998 | 707,742 | 487,426 | 345,824 | 929,377 |
| | Unit price (S/./kg) | 0.30 | 0.40 | 0.61 | 0.32 | 0.58 |
| | Sales (S/.) | 259,799 | 283,097 | 296,066 | 111,028 | 536,123 |
| Potato | Sown surface (ha) | 39 | 38 | 22 | 22 | 65 |
| | Unit performance (kg/Ha) | 31,538 | 26,368 | 27,866 | 27,524 | 32,091 |
| | Harvest (Kg) | 1,230,000 | 1,002,000 | 613,045 | 605,531 | 2,085,916 |
| | Unit price (S/./kg) | 0.50 | 0.50 | 0.46 | 0.83 | 0.63 |
| | Sales (S/.) | 615,000 | 501,000 | 281,443 | 500,939 | 1,310,597 |
| Tomato | Sown surface (ha) | 5 | 45 | 36 | 11 | 48 |
| | Unit performance (kg/Ha) | 29,000 | 38,951 | 30,584 | 34,963 | 36,310 |
| | Harvest (Kg) | 145,000 | 1,752,790 | 1,101,025 | 384,597 | 1,742,875 |
| | Unit price (S/./kg) | 0.50 | 0.38 | 0.73 | 0.45 | 0.41 |
| | Sales (S/.) | 72,500 | 662,165 | 804,360 | 173,418 | 714,942 |
| Watermelon | Sown surface (ha) | 29 | 30 | 13 | 14 | 40 |
| | Unit performance (kg/Ha) | 9,862 | 17,265 | 12,920 | 13,087 | 13,718 |
| | Harvest (Kg) | 286,000 | 517,938 | 167,960 | 183,218 | 548,708 |
| | Unit price (S/./kg) | 0.30 | 0.40 | 0.40 | 0.47 | 0.80 |
| | Sales (S/.) | 85,800 | 207,175 | 67,184 | 86,112 | 438,966 |
| Otros | Sown surface (ha) | 95 | 153 | 204 | 190 | 116 |
| Total | Sown surface (ha) | 13,254 | 13,231 | 12,917 | 13,620 | 13,077 |
| | Harvest (Kg) | 177,511,816 | 166,616,828 | 187,936,560 | 209,400,711 | 178,320,104 |
| | Sales (S/.) | 142,509,238 | 99,980,740 | 152,198,437 | 172,770,659 | 188,599,716 |




Figure 3.1.3-1 Planted Surface




Figure 3.1.3-2 Harvest




Figure 3.1.3-3 Sales

3.1.4 Infrastructure

(1) Road Infrastructures

Table 3.1.4-1 shows road infrastructures in the watershed of the Majes River. In total there are 981.291 km of roads, 282.904 km of them (28.8 %) are national roads, 208.163 km (21.2 %) regional roads, and 490.223 km (50.0 %) municipal roads.

Table 3.1.4-2 shows road infrastructures in the watershed of the Camana River. In total there are 574,039 km of roads, 143.608 km of them (25.0 %) area national roads, 365.940 km (63.8 %) regional roads, and 64.491 km (11.2 %) municipal roads.

Table 3.1.4-1 Basic data of road infrastructure in the Majes River

| Roads | Total Length (Km) | | Paving (Km) | | | |
|-----------------|-------------------|---------|-------------|------------|-------------|---------|
| | | | Asphalted | Trail Road | Gravel Road | Path |
| National Road | 282.904 | 28.83% | 64.400 | 173.842 | | 44.662 |
| Regional roads | 208.164 | 21.21% | | | 2.727 | 205.437 |
| Municipal roads | 490.223 | 49.96% | | 10.321 | | 479.902 |
| Total | 981.291 | 100.00% | 64.400 | 184.163 | 2.727 | 685.339 |

Table 3.1.4-2 Basic data of road infrastructure in the Camana River

| Roads | Total Length (Km) | | Paving (Km) | | | |
|-----------------|-------------------|---------|-------------|------------|-------------|---------|
| | | | Asphalted | Trail Road | Gravel Road | Path |
| National Road | 143.608 | 25.02% | 114.748 | 28.860 | | |
| Regional roads | 365.940 | 63.75% | 16.100 | 82.610 | | 267.230 |
| Municipal roads | 64.491 | 11.23% | 1.040 | 6.677 | | 56.774 |
| Total | 574.039 | 100.00% | 131.888 | 118.147 | | 324.004 |

(2) Irrigation systems

Table 3.1.4-3 shows data on existing irrigation systems in watershed of the Majes - Camana River. There are 58 water inlets and 79 water direct inlets. Besides, there are 58 main channels, 128 primary ones, 54 secondary and 5 tertiary. Main channels have an accumulated length of 167.24 km. Lagged channels amount 3.498 km, while 334.019 km have no lagging.

(3) PERPEC

Table 3.1.4-4 shows implemented projects by PERPEC between 2006 and 2009.

Table 3.1.4-3 Present conditions of irrigation channels

| IRRIGATION COMMISSION | Number of Water Inlets | Number of Direct Water Inlets | N° of Intakes and sluiceways at CD level | | | | | | Number of channels | | | | Long de C.D. (Kms.) | Total System Length | |
|-----------------------|------------------------|-------------------------------|--|------------------|----------------|------------------|------|------|--------------------|------|---------------|---------------|---------------------|---------------------|--|
| | | | Housing inlets | N° of sluiceways | Lateral inlets | N° of sluiceways | C.D. | 1er. | 2do. | 3er. | Lagged (Kms.) | Rustic (Kms.) | | | |
| | | | | | | | | | | | | | | Total System Length | |
| ONGORO | 5 | 5 | 63 | 35 | 25 | 25 | 0 | 5 | 25 | 6 | 0 | 30.064 | 0.363 | 69.600 | |
| ONGORO BAJO | 3 | 6 | 49 | 0 | 4 | 4 | 0 | 3 | 4 | 1 | 0 | 9.841 | 0.600 | 11.586 | |
| BERINGA | 2 | 0 | 29 | 0 | 2 | 2 | 0 | 2 | 2 | 0 | 0 | 5.530 | 0.000 | 7.880 | |
| COSOS | 1 | 2 | 37 | 0 | 4 | 4 | 0 | 1 | 4 | 3 | 0 | 3.976 | 0.000 | 9.140 | |
| APLAO | 2 | 0 | 47 | 2 | 6 | 6 | 2 | 1 | 6 | 1 | 0 | 5.933 | 0.000 | 9.660 | |
| HUANCARQUI | 3 | 0 | 39 | 1 | 10 | 10 | 1 | 2 | 10 | 3 | 0 | 7.401 | 0.000 | 20.483 | |
| TOMACA | 3 | 0 | 36 | 0 | 10 | 10 | 0 | 3 | 10 | 12 | 2 | 7.653 | 0.000 | 29.180 | |
| LA REAL | 2 | 0 | 47 | 0 | 1 | 1 | 0 | 3 | 1 | 0 | 0 | 6.664 | 0.000 | 7.604 | |
| MONTE LOS PUROS | 0 | 4 | 71 | 0 | 9 | 9 | 0 | 2 | 9 | 3 | 1 | 6.508 | 0.360 | 12.884 | |
| QUERULPA | 4 | 2 | 66 | 2 | 7 | 7 | 1 | 1 | 7 | 5 | 1 | 4.941 | 0.000 | 16.766 | |
| URACA | 8 | 23 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0.000 | 0.000 | 0.000 | |
| SOGIATA | 1 | 0 | 78 | 2 | 4 | 4 | 0 | 5 | 4 | 0 | 0 | 7.439 | 0.000 | 10.457 | |
| SAN VICENTE | 2 | 0 | 71 | 0 | 3 | 3 | 0 | 4 | 3 | 0 | 0 | 5.225 | 0.000 | 6.944 | |
| CANTAS PEDREGAL | 2 | 0 | 34 | 9 | 3 | 3 | 1 | 1 | 3 | 7 | 1 | 7.930 | 0.090 | 20.886 | |
| PITIS | 1 | 1 | 48 | 0 | 1 | 1 | 0 | 8 | 1 | 1 | 0 | 8.011 | 0.000 | 8.616 | |
| SARCAS - TORAN | 6 | 2 | 42 | 0 | 8 | 8 | 0 | 1 | 8 | 2 | 0 | 7.650 | 0.000 | 16.920 | |
| EL GRANADO | 1 | 11 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0.000 | 0.000 | 0.000 | |
| TOTAL | 58 | 79 | 1,043 | 57 | 126 | 126 | 34 | 58 | 126 | 54 | 5 | 167.240 | 3.498 | 334.019 | |

Table 3.1.4-4 Projects implemented by PERPEC

| Nº | YEAR | Work | Location | | | Description | Total Cost (\$/.) |
|----|------|--|------------|----------|---------------------------|--------------------------|-------------------|
| | | | Department | Province | District | | |
| 1 | 2006 | Construction of a Rockfill Dike - Huantay Sector | Arequipa | Camana | Ocona | Huantay | 150,000.00 |
| 2 | 2006 | Construction of breakwaters and rockfill dikes in the Majes Valley | Arequipa | Castilla | Aplao y Uraza | El Granado | 607,186.00 |
| 3 | 2006 | Construction of Coastal Defense - Quilca Valley Sector | Arequipa | Camana | Quilca | El Platanal | 81,305.00 |
| 4 | 2006 | Majes River Coastal Defense - Montes Sector | Arequipa | Castilla | Aplao | El Monte | 96,000.00 |
| 5 | 2006 | Construction of Coastal Defense - Ocona Valley, Jayhuiche Sector | Arequipa | Camana | Mariano Nicolas Valcarcel | Jayhuiche | 149,992.00 |
| 6 | 2006 | Construction of rockfill dike - Zurita Sector | Arequipa | Camana | Ocona | Zurita | 151,484.00 |
| 7 | 2006 | Construction of Coastal Defense - Ocona Valley, Santa Rita Sector | Arequipa | Camana | Ocona | Santa Rita | 149,487.00 |
| 8 | 2007 | Construction of coastal defense - Querulpa Tomaca Sectors | Arequipa | Castilla | Aplao, Huancarqui | Querulpa Tomaca | 380,233.00 |
| 9 | 2007 | Construction of dike with breakwaters - El Platanal Sector, Quilca District, Province of Camana - Arequipa | Arequipa | Camana | Quilca | El Platanal | 259,174.00 |
| 10 | 2008 | Construction of Provisional Coastal Defense Construction in the Majes River - Los Puros Sector, Aplao District, Province of Castilla - Arequipa (Contingency) | Arequipa | Castilla | Aplao | Los Puros | 117,215.00 |
| 11 | 2008 | Construction of Provisional Coastal Defense in the Ocona River - Santa Rita Sector, Ocona District, Province of Camana - Arequipa (Contingency) | Arequipa | Camana | Ocona | Santa Rita | 97,066.00 |
| 12 | 2008 | Construction of Provisional Coastal Defense in the Majes River - San Vicente and Sacramento Sectors, Uraza District, Province of Castilla - Arequipa (Contingency) | Arequipa | Castilla | Uraza | San Vicente y Sacramento | 124,952.00 |
| 13 | 2008 | Construction of rockfill dike - Sonay Sector (Prevention) | Arequipa | Camana | Nicolas de Pierola | Sonay | 230,058.00 |
| 14 | 2008 | Construction of coastal defense - Anchalo Huacan Sector - Ocona Valley (Prevention) | Arequipa | Camana | Ocona | Huacan | 123,352.00 |
| 15 | 2008 | Construction of Rockfill Dike - Huantay Sector - Ocona Valley (Prevention) | Arequipa | Camana | Ocona | Huantay | 117,348.00 |

3.1.5 Real flood damages

(1) Damages on a nationwide scale

Table 3.1.5-1 shows the present situation of flood damages during the last five years (2003-2007) in the whole country. As observed, there are annually dozens to hundreds of thousands of flood affected inhabitants.

Table 3.1.5-1 Situation of flood damages

| | | Total | 2003 | 2004 | 2005 | 2006 | 2007 |
|----------------------------|---------|---------|---------|--------|--------|---------|--------|
| Disasters | Cases | 1,458 | 470 | 234 | 134 | 348 | 272 |
| Víctims | persons | 373,459 | 118,433 | 53,370 | 21,473 | 115,648 | 64,535 |
| Housing loss victims | persons | 50,767 | 29,433 | 8,041 | 2,448 | 6,328 | 4,517 |
| Decesated individuals | persons | 46 | 24 | 7 | 2 | 9 | 4 |
| Partially destroyed houses | Houses | 50,156 | 17,928 | 8,847 | 2,572 | 12,501 | 8,308 |
| Totally destroyed | Houses | 7,951 | 3,757 | 1,560 | 471 | 1,315 | 848 |

Source : SINADECI Statistical Compendium

Peru has been hit by big torrential rain disasters caused by the El Niño Phenomenon. Table 3.1.5-2 shows damages suffered during the years 1982-1983 and 1997-1998 with extremely serious effects. Victims were approximately 6,000,000 inhabitants with an economic loss of about US\$ 1,000,000,000 in 1982-1983. Likewise, victims number in 1997-1998 reached approximately 502,461 inhabitants with economic loss of US\$ 1,800,000,000. Damages in 1982-1983 were so serious that they caused a decrease of 12 % of the Gross National Product.

Table 3.1.5-2 Damages

| Damages | 1982-1983 | 1997-1998 |
|--|---------------|---------------|
| Persons who lost their homes | 1.267.720 | — |
| Victims | 6.000.000 | 502.461 |
| Injured | — | 1.040 |
| Deceased | 512 | 366 |
| Missing persons | — | 163 |
| Partially destroyed houses | — | 93.691 |
| Totally destroyed houses | 209.000 | 47.409 |
| Partially destroyed schools | — | 740 |
| Totally destroyed schools | — | 216 |
| Hospitals and health centers partially destroyed | — | 511 |
| Hospitals and health centers totally destroyed | — | 69 |
| Damaged arable lands (ha) | 635.448 | 131.000 |
| Head of cattle loss | 2.600.000 | 10.540 |
| Bridges | — | 344 |
| Roads (km) | — | 944 |
| Economic loss (\$) | 1.000.000.000 | 1.800.000.000 |

“—”: No data

(2) Disasters in the watersheds object of this study

Table 3.1.5-3 summarizes damages occurred in the Arequipa region.

Table 3.1.5-3 Disasters in the Arequipa Region

| Years | 1995 | 1996 | 1997 | 1998 | 1999 | 2000 | 2001 | 2002 | 2003 | 2004 | 2005 | 2006 | 2007 | 2008 | 2009 | 2010 | Total | Media |
|-------------------------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|-------|-------|
| LANDSLIP | | | | | | | | | | | | | | | | 1 | 1 | |
| FLOOD | | | | | | | | | | | 5 | | | | | | 5 | |
| COLLAPSE | | | | | | 1 | 1 | 1 | | | | | | | | 1 | 4 | |
| LANDSLIDE | | 1 | | 1 | 1 | 2 | 1 | 1 | 4 | 3 | 4 | 2 | | | 1 | 2 | 23 | |
| AVALANCHE | 6 | 1 | 7 | 14 | 3 | 2 | 4 | | | | 2 | 2 | 1 | | 9 | 3 | 54 | |
| TOTAL SEDIMENT DISASTER | 6 | 2 | 7 | 15 | 4 | 5 | 6 | 2 | 4 | 3 | 11 | 4 | 1 | 0 | 10 | 7 | 87 | 5 |
| TOTAL FLOOD | 3 | 1 | 42 | 6 | 44 | 2 | 15 | 3 | 1 | 2 | 2 | 3 | 0 | 1 | 3 | 3 | 131 | 8 |

3.1.6 Results on the visits to Study Sites

JICA Study Team made some technical visits to the selected watersheds and identified some challenges on flood control through visits and interviews to regional government authorities and irrigation associations on damages suffered in the past and the problems each watershed is currently facing.

(1) Interviews

1) Camana River

(General conditions of the watershed)

- The jurisdiction area of Camana covers from the river mouth to 39 km upstream
- The dike was constructed thirty years ago by the irrigation commission, but there are various eroded parts
- 99% of rice crops are commercialized in Lima's market
- Flow is measured once a day. The maximum historical flow was from 1.200 to 1.500 m³/s. Floods last almost a week
- There are some colonial ruins in the upper area at the left riverbank between km 2 and 6

(On critical points)

○ Obstruction of the river mouth

- The formation of the gravel bank in the river mouth caused by beach waves obstructs water flow in the river mouth (obstruction in the river mouth). The construction of a longitudinal dike along the sea side has been considered in order to control this situation. The gravel bank disappeared with floods and reappeared between June and December
- The path km 2,5 – km 4,5 burst its banks the same year El Niño Phenomenon hit, 1998. The right bank also did burst in the past
- Riverbed elevation

- Path with lower dike (left bank between km 6 and km 7,5).
 - The dike at the left bank is particularly low between km 6 – 7,5 (LA BOMBOM)
 - There are arable lands between the dike at the left bank and the river downstream in the Camana Bridge that can eventually be removed for being illegal. As to the arable lands outside the dike, the negotiation might be complicated
 - The riverbed has elevated more than a meter
- Erosion in the riverbank around the channel (left bank between km 12– 13)
 - There is an arm water inlet for Camana's drinking water by km 13
 - There is a channel that goes from the water inlet along the river. The river's left bank is seriously eroded at km12, endangering the adjacent channel
- Scour of bridge piers (by km 26)
 - There is a local community at the right bank of the river, by km 26 (SONAI) with 40 households. There is a suspension bridge constructed a year ago with semi-eroded piers because of floods, presenting collapse risks with following floods
- Other parts presenting problems
 - The left bank dike at km 3 is eroded and has been provisionally repaired
 - There is an unprotected part at km 14,2
 - There is a path whose left bank is being eroded at km 19 (CHARACTA)
 - The left bank dike at km 26,5 is eroded
 - A left bank dike at km 28 needs to be constructed
 - Arable lands at km 29 of the left bank are eroded (CULATA DE SIYAN)
 - The left bank at km 30 is being eroded and needs protection (FUNDO CASIAS)
 - A dike at km 33,5 needs to be constructed given that annually the water inlet and the irrigation channels get flooded
 - A 1km dike needs to be constructed at the right bank of km 34
 - A 2km dike needs to be constructed at km 37,5 downstream in order to protect the water inlet and adjacent arable lands (80 ha) of the left bank (HUAMBOY)
 - A 1km dike needs to be constructed at km 39 downstream in order to protect the water inlet and adjacent arable lands (80 ha) of the right bank (HUAMBOY)

2) Majes River

(Critical points)

- Areas overflowing (right bank at km 104)
 - A 500m dike needs to be constructed at the right bank
 - Elements to be protected: arable lands (ONGORO BAJO)
 - Landslide occurred on 1977 left arable lands buried at river banks. Accumulated sediment in the river course was dragged downstream by river level rise
- Fluvial erosion (right river bank, km 101)
 - Arable lands were eroded by 1997 floods

- The elements to be conserved are arable lands (HUATIAPILLA BAJA)
- The current dike (600 m) at the right river bank needs to be extended between 500 and 800 m
- Fluvial erosion (right river bank, km 88,5)
 - River banks have been eroded by the floods in February 2011 dragging also part of a house (which is still being occupied)
 - The elements to be conserved are arable lands and houses (BERINGA)
 - The existing dike (1 km) as well as protection works at the right river bank need to be prolonged 600 m
- Dike erosion (right river bank, km 84,5)
 - The dike at the right river bank is being progressively eroded year by year, and if measures are not taken, this could affect the adjacent bridge (Huancarqui Bridge)
 - The dike has been repaired in an improvised way, but it needs a pertinent measure as river bank protection, etc
 - The elements to be conserved are arable lands and the bridge (APLAO)
 - The town of Aplao, the biggest city hall in Majes, has 18 thousand inhabitants, and Huancarqui at the other side of the river, crossing the bridge, has 5 thousand inhabitants
- Unprotected stretch (right river bank, between km 70,5 and km 71)
 - Currently an 800m dike is being constructed financed by the regional government. However, other 1,3 km are considered to be built in order to protect approximately 30 houses located in lower lands of the lower watershed
 - Last August 2010, the area was flooded after eight years
 - The elements to be conserved are arable lands and private houses (EL DEQUE)
 - There is an irrigation channel upstream, conducting water to arable lands (700 ha) downstream. The water inlet is being eventually repaired, to be finished in 15 days
 - Big rocks for river bank protection are extracted and transported from a quarry in Aplao
- Overflowed stretch (both river banks, between km 60 and km 62)
 - It is necessary to construct 2km dikes at the left river bank and 1,5 dikes at the right river bank
 - Elements to be conserved are arable lands (Pitis at the left river bank and San Vicente at the right river bank)
- Overflowed stretch (left river bank, between km 58 and km 58.5k)
 - A dike needs to be constructed at the left river bank
 - The elements to be conserved are arable lands (ESCALERILLAS)
- Fluvial erosion (left river bank between km 55 and km 56.5k)
 - Agriculture lands are being progressively eroded year by year by floods
 - Elements to be conserved are arable lands (SARCAS)

- Part of the area has been flooded in 1998 by 1.500 m³/s floods, forcing three small communities to move from lower lands to upper ones
- The river overflowed in February 2011 by floods of 800 m³/s
- Other parts presenting problems
 - A dike is looked to be built at the left river bank, between km 81,5 and km 82 (HUANCARUQUI)
 - A dike is looked to be built at the right river bank, between km 81,5 and km 82 (CASPANI)
 - Parts between km 75–km 75,5k and km 71–km 71,5 are unprotected at the left river bank (TOMACA)
 - The stretch km 73,5 – km 74 is unprotected at the right river bank (QUERULPA)
 - A dike is looked to be built at the left river bank, between km 49 and km 51,5 (PAMPA BLANCA)

(2) Description of the visit to the study sites

Figure 3.1.6-1 shows pictures of main sites visited.




Figure -3.1.6-1 Visit to the Study Site (Camana River)




Figure 3.1.6-2 Visit to the Study Site (Majes River)