

## 添付資料 2 改訂した ADN マニュアル(テトン語版)



**AGÊNCIA DE DESENVOLVIMENTO NACIONAL  
REPÚBLICA DEMOCRÁTICA DE TIMOR-LESTE**



**JAPAN INTERNATIONAL COOPERATION AGENCY (JICA)**

# **MANUAL ADN (Política, Prosessu & Prosedimentu, Produutu)**

**Outubru de 2012**

**Mr. Aleixo Amaral do Carmo (FI)**

**Mr. Demistocles G. X. F. Cabral (PDID)**

**Mr. Miguel M. M. de Jesus (ELÉKTRIKA)**

**Mr. Januario Maia Guterres (LM)**

**AGÊNCIA DE DENSEVOLVIMENTO  
NACIONAL (ADN)**

## **Lia-Dahuluk**

ADN Establesidu iha Março de 2011 husi Dekretu-Lei No.11/2011. Desde Nia inaugurasaun ADN involvidu ona iha dezentovimentu infraestruturá, prinsipalmente iha prosessu sira husi verifikasaun ba dokumentus tenderizasaun no inspesaun ba pedidu pagamentu. Manual ADN ne'e mak formuladu liu husi arranja prosedimentu obra atual no aumenta várius melhorias ba implementasaun ne'ebé di'ak husi prosessu hirak iha leten. Nia aponta atu ajuda laos de'it ba funsionáriu ADN maibé mos funsionáriu Liña Ministérial (LM) ne'ebé tenke hala'o obra iha prosessu hirak ne'e.

Esbosu Manual ADN mak preparadu no introduz ona iha Semináriu Internal loron 25 Outubru 2012, no Manual ADN mós korrijidu no introduz tiha ona iha Workshop kona-ba Kontrolu Kualidade através Servisu ADN nian iha loron 20 Setembru 2013.

Manual ida ne'e mak kompostu husi sesaun tolu : Jeneralidade, avaliasaun projetu molok ajudikasaun kontratu; no, inspesaun projetu no rekomendasaun ba pagamentu. Manual ne'e kobre kategoria hat katak projetus sira ne'ebé husi Fundus Infraestruturá, PDID, Programa Eléktrifikasaun Nasional (PEN) no Fundu LM. Entretantu, kada kategoria mak representadu husi seitor espesifiku ida. Haktuir ba Lista-revista (Checklist) Téknika, Fundu Infraestruturá toma-konta ho seitor estrada & ponte, PDID ho Fornesementu Be-mos, Programa Eletrifikasaun Nasional ho Eletrisidade no Fundu LM ho Edifisiu. Hirak ne'ebé husi Projetu Espesial iha ADN nia okos no Fundu Emerjênsia, Sefope, and ADDT mak la inkluidu iha ne'e.

Komponentes chave ida husi manual ne'e mak atu fornese Lista-Verifikasaun(Checklist) no Formatu(Forms). Lista-Verifikasaun(checklist) mak atu halo servisu ADN nian sai klaru no Formatu(Forms) mak atu halo komunikasaun klaru entre ADN no LM, basá atu klarifika sira nia papel no responsabilidades. Sira na'in rua hamutuk mak projetada atu halo prosessu hirak ne'e lidera sai própriu no furak liu.

Manual ADN husik hela assuntus téknika núdar Padraun no espesifikasaun ba kada LM's(Liña Ministérialis). Manual ne'e sei bele halo revizaun hodi akomoda melhoramentu ruma husi kolaborasaun servisu entre ADN no LM.

### Abreviatura

AASHTO	American Association of State Highway and Transportation Officials
ADB	Asian Development Bank / Banco Desenvolvimento Asiático
ADN	Agencia de Desenvolvimento Nacional
APORTIL	Port Administration of Timor-Leste / Autoridade Porto Marítima de Timor Leste
AS	Australian Standard (for Building) / Padraun Australianu ba Konstrusaun Edifisiu
AS/NZS	Australian / New Zealand Standard (for Building) / Padraun Australianu/Nova Zelândia ba Konstrusaun Edifisiu
BCA	Building Code of Australia/Kódigu Edifisiu Australianu
BOQ	Bill of Quantities / Lista Kuantidades
CAFI	Conselho de Administração do Fundo das Infra-estruturas
CKP	Charles Kendal & Partners
DC	District Committee/Comissão Distrital
DNSA	National Directorate of Water Supply/ Direcção Nacional das Águas e Saneamento (Organizasaun Tu'an)
DNSAS	National Directorate of Water and Sanitation/Direcção Nacional dos serviços de Água e Saneamento
DRBFC	National Directorate of Road, Bridge and Flood Control/Direcção Nacional dos Estradas, Pontes e Controlo de Cheia
EDTL	Electricity of East Timor/Eletricidade de Timor Leste
ESTATAL	Ministry of State Administration and Territorial Management (MAEOT)
FAQ	Frequently Asked Question/Nafatin; Frequentemente Husu perguntas
FI	Infrastructure Fund/Fundo das Infraestruturas
JICA	Japan International Cooperation Agency
KDD	Development District Commission/Komissaun Dezenvolvimentu Distrital
LM	Line Ministry/Linha Ministéris
MAEOT	Ministry of State Administration and Territorial Management (ESTATAL)
MDG	Millennium Development Goal/Meta do Desenvolvimento Milénio
MOF	Ministry of Finance/Ministério das Finanças
MOI	Former Ministry of Infrastructure/Ministério das Infra-estruturas
MPS	Major Project Secretariat
MPW	Ministry of Public Works/Ministério das Obras Públicas
NPC	National Procurement Commission/Comissão de Aproveitamento Nacional
PDD I	Package of Decentralized Development I/Pakote dezenvolvimentu nasional I
PDD II	Package of Decentralized Development II/ Pakote dezenvolvimentu nasional II
PDIDS	Integrated Development Project in Suco/Projeto Integrado Distrital em Suco
PDL	Programa de Desenvolvimento Local
PEN	Programa da Eletrificação Nacional



PO	Purchase Order/ Ordem Compra(Procura)
RDTL	The independent Democratic Republic of Timor-Leste/República Democrática de Timor Leste
RWS	Rural Water Supply/Fornesementu Be-mos Rural
SDP	Timor-Leste Strategic Development Plan 2011-2030/Plano Estratégico de desenvolvimento Nacional
SGP	Secretariat of Large Project
SNI	Serviços Nacional de Inteligência
Suco	Village in Timor-Leste
TPO	Treasury Payment Order/Ordem Pagamento do Tesouro
UNDP	United Nations Development Program/Programa Desenvolvimento Nação Unidas
WB	World Bank/Banco Mundial
W/C	Water Cement Ratio/Rasio we'e no sementu
BPA	Banking & Payments Authority/Autoridade Bankária & Pagamentu

# MANUAL ADN (Política, Prosesu & Prosedimentu, Produktu)

## INDÍSIU

	Pájina
Jeneralidade .....	1
<b>1. Projetu Fundu da Infra-esrutura(FI) .....</b>	<b>7</b>
<b>1.1. Avaliasaun Projetu molok Ajudikasaun kontratu .....</b>	<b>7</b>
1.1.1. Fluxograma .....	7
1.1.2. Oráriu husi Obra .....	8
1.1.3. Konfirmasaun ba Dokumentus ne'ebé submete ona .....	8
1.1.4. Verifikasaun ba Kondisoens Pagamentu .....	9
1.1.5. Verifikasaun Téknika Utiliza Lista-Verifikasaun(Checklist).....	9
1.1.6. Rona husi LM .....	14
1.1.7. Oráriu Verifikasaun .....	14
1.1.8. Remédiu/Reparasaun .....	15
1.1.9. FAQ (Frequentamente/Nafatin Husu Perguntas).....	15
<b>1.2. Inspesaun Projetu &amp; Rekomendasaun ba Pagamentu .....</b>	<b>16</b>
1.2.1 Fluxograma .....	16
1.2.2 Oráriu husi Obra .....	17
1.2.3 Inspesaun Dokumentus .....	17
1.2.4 Inspesaun Terrenu.....	18
1.2.5 Notifikasaun husi Julgamentu Kona-ba Pagamentu.....	19
1.2.6 FAQ (Frequentamente/Nafatin husu Perguntas).....	19
<b>Anexu-1 (Fundu da Infra-estrutura (FI))</b>	
Formatu-A (Rezumu/outline projetu ba Ponte).....	20
Formatu -A2 (Rezumu/outline projetu ba Estrada).....	21
Formatu -B (Pedidu Preparasaun ba Inspesaun Terrenu).....	22
Formatu -C (Relatóriu Inspesaun no Rekomendasaun ba Pagamentu).....	23
Checklist -A (Dokumentus ne'ebé Submetidu ba Dokumentus Tender).....	24
Checklist-B (Kondisoens Pagamentu).....	26
Checklist-C (Verifikasaun Téknika) .....	27
Checklist-D (Dokumentus ne'ebé Submetidu ba Pedidu Pagamentu).....	29
Checklist-E (Kontrolu Kualidade) .....	31
Checklist-F (Medisaun/Masurement) .....	32
Anexu A (Dadus passadu husi Kondisaun Kontratu) .....	33
Anexu B (Livru FAQ).....	34

<b>2. Projetu PDID .....</b>	<b>37</b>
<b>2.1. Avaliasaun Projetu molok Ajudikasaun kontratu .....</b>	<b>37</b>
2.1.1. Fluxograma .....	37
2.1.2. Oráriu husi Obra .....	38
2.1.3. Konfirmasaun ba Dokumentus ne'ebé submete ona .....	39
2.1.4. Verifikasaun ba Kondisaun Pagamentu.....	39
2.1.5. Verifikasaun Téknika Utiliza Lista-Revista .....	39
2.1.6. Rona husi LM .....	39
2.1.7. Oráriu Verifikasaun .....	40
2.1.8. Remédiu/Reparasaun .....	40
2.1.9. FAQ (Frequentamente/Nafatin Husu Perguntas).....	40
<b>2.2. Inspesaun Projetu &amp; Rekomendasaun ba Pagamentu .....</b>	<b>41</b>
2.2.1. Fluxograma .....	41
2.2.2. Oráriu Obra .....	42
2.2.3. Inspesaun Dokumentus .....	42
2.2.4. Inspesaun Terrenu.....	43
2.2.5. Notifikasaun husi Jsulgamentu kona-ba Pagamentu .....	44
2.2.6. FAQ (Frequentamente/Nafatin Husu Perguntas).....	44
<b>Anexu (PDID)</b>	
Formatu-A (Delinear/Rezumu Projetu husi LM/KDD).....	45
Formatu-B (Relatóriu Inspesaun no Rekomendasaun ba Pagamentu).....	46
Checklist -A (Dokumentus ne'ebé sei Submete) .....	47
Checklist-C (Verifikasaun Téknika).....	48
Checklist-B (Kondisoens Pagamentu) .....	54
Checklist-D (Kontrolu Kualidade).....	58
Checklist-E (Meditaun/Measurement ba Obra Komleta ona).....	60
<b>3. Programa Eléktrifikasaun Nasional .....</b>	<b>77</b>
<b>3.1. Avaliasaun Projetu molok Ajudikasaun kontratu .....</b>	<b>77</b>
3.1.1. Jeneralidade .....	77
3.1.2. Fluxu prosedimentu ba Sertifikasaun Kualidade.....	78
3.1.3. Oráriu Publikasaun ba Sertifikasaun Kualidade.....	79
3.1.4. Verifikasaun ba Sertifikasaun Kualidade.....	80
<b>3.2. Inspesaun Projetu &amp; Rekomendasaun ba Pagamentu .....</b>	<b>82</b>
3.2.1. Fluxu Prosedimentu ba Pagamentu.....	82
3.2.2. Oráriu Verifikasaun ba Pagamentu.....	83
3.2.3. Dokumentus Nesessáriu sei submete husi Komissaun.....	84
3.2.4. Dokumentu Inspesaun.....	85
3.2.5. Inspesaun Terenu.....	87
3.2.6. Evaliasaun no Relatóriu .....	88

<b>Anexu- 3 (Program Elétrifikasaun Nasional)</b>	
Formatu A (Pedidu Verifikasaun Dokumentu husi Komissaun PEN) .....	90
Formatu B (Rekomendasaun ba Remédiu iha Provisional Handover) .....	92
Formatu C (Relatóriu Inspeksaun no Rekomendasaun ba Pagamentu).....	93
Formatu D (Rekomendasaun ba Remédiu).....	94
Checklist-A (Dokumentus ne'ebé submete) .....	97
Checklist B (Inspesaun ba Pagamentu) .....	98
Checklist C (Padraun Inspesaun Téknika ba Liña Distribusaun) .....	102
<b>4. Liña Ministeriais.....</b>	<b>136</b>
<b>4.1. Avaliasaun Projetu molok Ajudikasaun kontratu.....</b>	<b>136</b>
4.1.1. Fluxograma .....	136
4.1.2. Oráriu Obra .....	137
4.1.3. Konfirmasaun ba Dokumentus ne'ebé submete ona .....	137
4.1.4. Verifikasaun ba Kondisoens Pagamentu .....	137
4.1.5. Verifikasaun Téknika Utiliza Lista Verifikasaun.....	138
4.1.6. Rona husi LM .....	140
4.1.7. Oráriu Verifikasaun .....	140
4.1.8. Remédiu/Reparasaun .....	141
4.1.9. (Frequentamente/Nafatin Husu Perguntas) .....	141
<b>4.2. Inspesaun Projetu &amp; Rekomendasaun ba Pagamentu .....</b>	<b>142</b>
4.2.1. Fluxograma .....	142
4.2.2. Oráriu Obra .....	143
4.2.3. Dokumentus Inspesaun .....	143
4.2.4. Inspesaun Terrenu.....	144
4.2.5. Notifika iha Julgamentu Kona-ba Pagamentu.....	145
4.2.6. FAQ (Frequentamente/Nafatin husu Perguntas).....	145
<b>Anexu-4 (Liña Ministéris)</b>	
Formatu-A (Karta Pedidu Verifikasaun ba Dokumentus Tender).....	146
Formatu-B (Delinear Projetu preparadu husi LM) .....	147
Formatu-C (Karta Pedidu Inspesaun husi LM hato'o ba ADN).....	148
Formatu-D (Relatóriu Inspeksaun no Rekomendasaun ba Pagamentu).....	149
Formatu-E (Pedidu ba Preparasaun Inspesaun Terenu).....	152
Checklist-A (Dokumentus ne'ebé submetidu).....	153
Checklist-B (Kondisaun Pagamentu).....	155
Checklist-C (Verifikasaun Téknika) .....	156
Checklist-D (Dokumentus ne'ebé submetidu).....	157
Checklist-E (Kontrolu Kualidade) .....	159

## **Jeneralidade**

### **(Antesedentes)**

ADN estabeleceu husi Dekretu-Lci No.11/ 2011 nu'udar iniciativa ida husi governu atu estabelese reformaun no hametin estrutura organizasional husi administrasaun pública.

ADN mak responsabiliza ba revizaun estrita husi projetus kapital dezenvolvimentu hanesan tuir mai:

- Avalia méritu/valor no viabilidade husi projetus kapital dezenvolvimentu;
- Superviziona, inspeiona no sertifika projetus kapital dezenvolvimentu;
- Jere projetus konstrusaun iha PDDII nia okos; no
- Fornese apoiu ba programa MDG Sucos.

### **(Âmbitu)**

Manual ADN aponta ba ADN atu hala'o nia knar ho propriamente no efisientemente mandatu hirak-ne'ebé mak espesifikadu iha Dekretu-Lci. Manual ne'e mós aponta ba LMs (Liña Ministeriais) no organizaun seluk ké involvidu hodi suporta korretamente sira nia papel no responsabilidade durante aprovizionamentu ba projetus kapital dezenvolvimentu.

Manual ne'e espesialmente fokaliza iha prosesu hirak tuir mai durante sira okupadu teb-tebes hala'o knar iha tempu agora daudaun.

- Verifikasaun ba Dokumentus Tenderizasaun
- Inspesasaun ba Pedidu Pagamentu

### **(Kategoria husi Projetus/Fundus)**

Kategoria projetu iha ADN mak hatudu iha Tabela 1, Categoria Projetu iha ADN hanesan husi 2012, Tabela 2, Categoria Projetu iha ADN hanesan husi 2013, no Tabela 3, Categoria Projetu iha ADN hanesan husi 2014.

Manual ne'e separadamente formuladu bazea ba kategoria husi projetus iha konsiderasaun ba prosedimentu diferente no iha favorese ba Uza-na'in (Uzuáriu) sira.

Manual ne'e mós toma-konta ho Projetu Fundu da Infra-estrutura, Projetu Fundu Liña Ministeriais, Projetu Fundu PDID, no Programa Eletrifikasaun Nasional (PEN). Manual ne'e la toma-konta ba Emerjênsia, Adisional, SEFOPE, MDG, no Projetu Espesial iha ADN nia mahon.

Tabela 1. Categoria Projeto iha ADN hanesan husi 2012

Klassifikasaun husi Projektu	Fundu Infra-estrutura	Liña Ministeriais	PDD I & II	PDID	PDL	MDG	Fundu Emerjensia	Programa Elektrifikas Nasiona (PEN)	Fundu Kontinjensia	Projektus Especial iha ADN nia okos
Notifikasaun				[TBC]	Aprovizionamentu ne'ebé inteiramente iha Distritu	Uma Edifisiu	Só-de'it iha kazu emerjensia	Dekretu Lei No: 40/2012	Apenas uja ba projektus la previstu iha orsamentu	Hafoin de instrusaun no aprovađu husi PM
Fonte Financiamentu	Fundu Infra-estrutura	Orsamentu Liña Ministeriais	PDD I – MAEOT PDD II - ADN	[TBC]	MAEOT 1) no Administraσαun Distritu	ADN	Fundu Emerjensia jere husi MoF	Fundu Infra-estrutura	Fundu Kontinjensia jere husi MoF	Fundus alokađu ba ADN
Variedade Orsamentu	Bo'ot Liu-husi US\$1.000.000	US\$500.000 to'õ US\$1.000.000	PDD I to'õ ba 150.000 PDD II 150.001 to'õ ba 500.000	[TBC]	1 to'õ US\$100.000	Laiha Limitasaun	US\$100.000 to'õ US\$150.000	US\$100.000 to'õ US\$4.500.000	Máximu 2.000.000 (Prátika Normal)	Até 10.000.000

1) MAEOT: Ministério das Administração Estatal e Ordenamento Território

Tabela 2. Categoria Projetu iha ADN hanesan husi 2013

Klassifikasaun husi Projetu	Fundu da Infra-estruturais	Liña Ministeriais	PDD I & II	PDID	PDL	MDG	SEFOPE	Fundu Emerjensia	Programa Elektrifikasaun Nasional (PEN) (PEN)	Adisional	Projetus Especial iha ADN nia okos
Notifikasaun					Aprovizionamentu ne'ebé inteiramente iha Distritu	Uma Edifisiu	Dekretu Lei LM	Só-de'it iha kazu emerjensia	Dekretu Lei No: 40/2012	Apenas uja ba projetus la previstu iha orsamentu	Hafoin instrusaun no aprovadu husi PM
Fonte Finansiamentu	Fundu Infra-estruturais	Orsamentu Liña Ministeriais	PDD I – MAEOT PDD II ADN	ADN	MAEOT (no Administrasaun Distritu)	ADN	SEFOPE	Fundu Emerjensia jere husi MoF	Fundu Infra-estruturais	Fundu Kontinjensia jere husi MoF	Fundus alokadu ba ADN
Variedade Orsamentu	Bo'tot Liusi US\$1.000.000	US\$500.000 to'o US\$1.000.000	PDD I to'oba 150.000 PDD II 150.001 to'oba 500.000	PDD I to'oba 150.000 PDD II 150.001 to'oba 500.000	1 to'o US\$100.000	Laiha Limitasaun	Laiha Limitasaun	US\$100.000 to'o US\$150.000	US\$100.000 to'o US\$4.500.000	Máximu 2.000.000 (Prátika Normal)	Até 10.000.000

Tabela 3. Categoria Projeto Antisipada iha ADN hanesan husi 2014

Klassifikasaun husi Projeto	Fundu da Infra-estrutura	Liña Ministeriais	PDID	MDG	SEFOPE	Fundu Emerjensia	Programa Elektrifika saun Nasional (PEN)	Adisional	Projetus Especial iha ADN nia okos
Notifikasaun				Uma Edifisiu	Dekretu Lei LM	Só-dé-it iha kazu emergjensia	Dekretu Lei No: 40/2012	Apenas uja ba projetus la previstu iha orsamentu	Hafoin instrusaun no aprovaadu husi PM
Fonte Finansiamentu	Fundu Infra-estrutura	Orsamentu Liña Ministeriais	ADN	ADN	SEFOPE	US\$100.000 to'o US\$150.000	Fundu Infra-estrutura	Fundu Kontinjensia jere husi MoF	Fundus alokadu ba ADN
Variedade Orsamentu	Bo'ot Liu-husi US\$1.000.000	US\$500.000 to'o US\$1.000.000	PDD I to'o ba 150.000 PDD II 150.001 to'o ba 500.000	Laiha Limitasaun	Laiha Limitasaun	00 to'o US\$150.000	US\$100.000 to'o US\$4.500.000	Máximu 2.000.000 (Prátika Normal)	Até 10.000.000



### **(Papel no Responsabilidade)**

Manual ne'e iha espektativa prinsipal relasionadu ba organizasaun relevante sira atu toma responsabilidade hanesan:

- ADN tenke verifica no inspesiona ba dokumentus haktuir mensiona iha leten ne'ebé submetidu husi LM (Iha ne'e refere hanesan LM)/Projetu Na'in. ADN bele solisita LM/Projetu Na'in atu fornese dokumentus adisionais no apresenta esplikasaun detalhadu, karik nesesáriu, durante verifikasaun no inspesaun;
- LM/Projetu Na'in, tenke produz dokumentus reklamadu para verifikasaun no/ka inspesaun iha nia responsabilidade. LM/Projetu Na'in sei submete dokumentu ba ADN ho karta ida katak nia konfirma ona dokumentus hirak-ne'e hanesan na'in ba projetu. Nune'e mós aplika ba dokumentus adisionais ne'ebé solisitadu husi ADN; no
- Kontraktor/empresariu tenke submete dokumentus reklamadu ba LM/Projetu Na'in bazea ba kontratu.

### **(Variedade husi Aplikasaun ba Kada Seitor)**

Haktuir seitor sira, manual ne'e inklui Lista-Verifikasaun(Checklist) téknika ba Estrada & Ponte iha Fundu da Infra-estrutura, Fornesementu Be-mos iha PDID, no Eletridade iha PEN. Checklist téknika sei bele atu uza parsialmente ba kategoria seluk.

Favor notifika hanesan tuir-mai, wainhira aplikasaun iha kategoria seluk.

- Haktuir ba Estrada & Ponte, checklist téknika aponta hodi verifica dokumentus tenderizasaun no atu inspesiona ba pagamentu, utiliza teknolojia parte-sentral kona-ba sira ne'e.

Checklist la inklui Projetu Espesial. Projetu Espesial persija checklist téknika sobre dezeñu detallu, supervizaun ba obra konstrusaun. Projetu PDID iha obra reparasaun wa'in. Checklist la inklui reparasaun dezeñu/obra.

- Relata ba Fornesementu/abastesimentu Be-mos, checklist téknika aponta atu verifica dokumentus tenderizasaun no atu inspesiona ba pagamentu sobre Projetus

Abastimentu Be-mos Rural, Checklist téknika ne'e mak prinsipalmente aplikável ba kategoria husi PDID no MDG kona-ba Fornesementu Be-mos Rural husi ESTATAL.

Checklist téknika ne'e mak la aplikável ba kategoria husi FI no LM kona-ba

Abastesimentu Be-mos Urbana husi DNSA. Checklist ida ne'e inklui dezeñu husi kadoras(pipeline). Checklist ne'e la inklui reparasaun ou hadi'a dezeñu/obra (Obras operasaun & manutensaun).

- Haktuir Eletridade, checklist téknika aponta hodi verifica tenderizasaun no atu inspesiona ba pagamentu sobre PEN, ida-ne'ebé mak projetu distribuissau ba


eletricidade. Checklist t knika ne'e la aplik vel ba projetu jersaun (generation project) hanesan FI & LM, projetu transmissaun(transmission project) hanesan FI & LM, no projetu koneksaun ba uma (home connection project) hanesan MDG.

## 1. Projeitu Fundu da Infra-estrutura (FI)

### 1.1. Avaliasaun Projeitu molok Adjudikasaun Kontratu

#### 1.1.1. Fluxograma

Figura 1-1. Fluxograma Projeitus Fundu da Infra-estrutura



- (1) LM/Konsultan Dezeñu  
LM fornese TOR ba Konsultan ida atu dezeña hatuir ba programa hanesan projeitu Ponte ká Estrada.  
Konsultan Dezeñu kompleta Dokumentus Tender no submete ba ADN.
- (2) MPS (Sekretaria Grande Projeitu)  
LM passa dokumentus hirak ne'e ba MPS atu verifika viabilidade husi projeitu.
- (3) ADN  
ADN verifika dokumentus hotu-hotu, espesialmente sobre kustu nomós konstrusaun. Wainhira verifikasaun kompleta hafoin ADN sei passa ba NPC + CKP. Ida-ne'ebé NPC nudar Komissaun Aprozionamentu Nasional, no CKP mak Charles Kendal & Partners.
- (4) NPC + CKP  
NPC, hamutuk ho CKP sei halo Tender.
- (5) CAFi > 5,000,000, CoM < 5,000,000  
CAFi sei foti desizaun, sé maka sei manan projeitu ne'e.
- (6) LM, MPS, ADN  
LM, MPS, ADN ne'ebé responsabiliza ba projeitu ne'e enkuantu projeitu mak sei-iha prosesu implementasaun.

### 1.1.2. Oráriu husi Obra

- (1) Rekerementu Tempu ba Verifikasaun iha ADN  
ADN kompleta verifikasaun ba dokumentus tender iha loron sanulu (10) kalendáriu nia laran depois de simu oficialmente dokumentus rekeridu husi ADN.
- (2) Tempu ba submissaun adisional, resubmissaun ká responde ba perguntas ADN LM tenke submete, resubmete ká responde ba ADN saida mak reklama ona husi ADN durante loron sanulu (10) kalendáriu nia laran depois de simu notifikasaun husi rekerimentu informasoens adianta-liu tan.
- (3) Iha assuntu husi sub-klauza (2) iha leten, tempu ba ADN atu kompleta verifikasaun tenke ser atrazada tamba iha tempu hanesan wainhira LM gasta tempu ba submissaun adisional, resubmissaun ká responde.

### 1.1.3. Konfirmasaun ba dokumentus ne'ebé submete ona:

ADN sei verifika karik dokumentus reklamadu hotu-hotu manda tiha ona. Iha kazu buat ruma mak falta, ADN sei informa ba LM kona-ba ida ne'e no informa LM atu submete iha tempu espisifikadu nia laran.

- (1) Karta Pedidu ba Verifikasaun Dokumentus Tender
- (2) Rezumu projetu prepara husi LM; **Formatu – A**
- (3) Dokumentus Tender : ADN sei konfirma rekerementu dokumentus ne'ebé submete ona, utiliza **Lista-Verifikasaun(Checklist) – A**.

### 1.1.4. Verifikasaun ba kondisaun pagamentu

ADN sei verifika kondisaun pagamentu ne'ebé adekua, utiliza **Lista-Verifikasaun /checklist– B** hanesan mensiona iha okos.

- (1) Tempu Kompleta/ Períodu Konstrusaun  
ADN sei verifika Tempu Kompleta ká Períodu Konstrusaun iha maneira ruma,
  - 1) Verifika oráriu konstrusaun detallada fornese husi LM,
  - 2) Hetan esplikasaun husi LM oinsá sira deside tempu ká periodu,
  - 3) Kompara tempu kompleta ho obra seluk ne'ebé hanesan.  
*Notifikasaun: Dadus passadu husi kondisaun kontratu hanesan tempu ba kompleta obra nian mak hatudu iha **Anexu(Attachment) A** anexada iha ne'e.*
- (2) Períodu Manutensaun/Períodu Notifikasaun ba Estragu /Períodu Responsabilidade Estragu
  - 1) Hetan esplikasaun husi LM oinsá sira deside tempu ká period,
  - 2) Kompara tempu Kompleta ho obra seluk ké hanesan.

- (3) Lei Governu nian  
Lei Governu mak lei husi Demokrátika Repúblika de Timor Leste.
- (4) Regulamentu Língua  
Regulamentu Língua mak Inglês.
- (5) Garantia ba Exekusaun/ Garantia ba Exekusaun Diak  
Montante Mínimu husi Garantia Exekusaun Diak mak persentajen husi Montante Kontratu hanesan ho dadus passadu ké hatudu iha **Anexu (Attachment) A** ne'ebé anexada iha ne'e.
- (6) Atraza estragus ba obra / Multas  
Liquidasaun Estragus/multas ba obras tomak mak 0.1% husi Presu Kontratu final kada loron, nu'udar hatudu iha dadus passadu iha **Anexu/Attachment A** ké anexada iha ne'e,
- (7) Montante Máximu ba Atraza Estragus  
Montante Máximu ba Atraza Estragus / Multas ba projetu pasadu mak hatudu iha **Anexu (Attachment) A** ne'ebé anexada iha ne'e.
- (8) Montante Provizóriu  
Montante Provizóriu ba projetu pasadu mak hatudu iha **Anexu (Attachment) A** ne'ebé anexada iha ne'e.
- (9) Total Pagamentu Adiantadu  
Total Pagamentu Adiantadu ba projetu pasadu mak hatudu iha **Anexu (Attachment) A** ne'ebé anexada iha ne'e.
- (10) Prosentajen ba Retensaun  
Prosentajen husi Retensaun ba projetu pasadu mak hatudu iha **Anexu (Attachment) A** ne'ebé anexada iha ne'e.
- (11) Limitasaun Husi Orsamentu Retensaun  
Limitasaun Husi Orsamentu Retensaun ba projetu pasadu mak hatudu iha **Anexu (Attachment) A** ne'ebé anexada iha ne'e.  
[Ezemplu A] Ponte Baer: 10% husi Montante Kontratu Aseita  
[Ezemplu B] Projetu Reabilitasaun Estrada ADB: 10% husi Montante Kontratu Aseita
- (12) Montante mínimu husi Sertifikasaun Pagamentu Provizóriu  
Montante mínimu husi Sertifikasaun Pagamentu Provizóriu ba projetus pasadu mak hatudu iha **Anexu (Attachment) A** ne'ebé anexada iha ne'e.  
[Ezemplu A] Ponte Baer: 5% Montante Kontratu Aseita  
[Ezemplu B] Projetu Reabilitasaun Estrada ADB: La Aplikável

### 1.1.5. Verifikasaun Téknika utiliza lista-verifikasaun/Checklist

ADN sei verifika teknikamente dokumentu hirak ne'e hanesan BOQ, dezeńu no spesifikasaun, utiliza **Lista-verifikasaun/Checklist C**.

**Lista Verifikasaun/checklist C1** ma uza ba projetu pontes no **C2** ba projetu estradas.

#### 1.1.5.1. Projetu Ponte (*Lista verifikasaun- C 1*)

(1) Klassifikasaun Estrada

Konfirma klasse husi estrada ké konekta ho ponte;

- 1) Estrada National,
- 2) Estrada Distritu ká
- 3) Estrada Rural

(2) Karga Direta/ Beban Langsung

Konfirma katak Kategoriya Karga Direta utiliza iha dezeńu ne'ebé adekuaadu ba klasse estrada.

Iha assuntu estrada nasional nian, pontes mak preferivel dezeńada Klase A husi Indonézia “Kódigu Dezeńu Pontes MBS” hatudu iha tabela tuir mai;

Klasse Estrada	Luan (m)			Karga Direta
	Trotoar/La'oa ain fatin iha Liman Karuk	Estrada lolon	Trotoar/la'oa ain fatin iha Liman Loos	
Klasse A	1.0	7.0	1.0	BM-100
Klasse B	0.5	6.0	0.5	BM-100
Klasse C	0.5	4.5	0.5	BM-70

*Notifikasaun; Luan ké hatudu iha-leten ne'ebé Minimu.*

(3) Ponte nia Luan

Ne'e Preferivel ba dezeńu iha konkordânsia ho tabela iha leten.

(4) Limitasaun kontra Planu Ponte

1) Fiu Aéreo (Kabel Udara)

Karik iha fiu sira ne'ebé bele impede konstrusaun ponte ká tráfikku depois de kompleta, confirma ba LM katak fiu sira ne'e bele hasai ká muda fatin tiha,

2) Fiu / Pipa Hakoi

Karik iha pipa be'e/komunikasaun ida-ne'ebé bele efeita durante ká depois de kompleta, confirma ba LM katak pipa sira ne'e bele hasai ká muda fatin tiha.

3) Akquizasaun Rai

Konfirma ba LM katak la iha rai privadu ne'ebé bele efeita ba konstrusaun.

(5) Levantamentu Jeotékniku no Topógrafu

1) Levantamentu Jeotékniku

ADN sei confirma katak levantamentu Geográfiku kompletada tiha ona no rezultadu refletada ba dezeńu detalladu.

2) Levantamentu Topógrafu

ADN sei confirma that levantamentu Topógrafu kompletada tiha ona no rezultadu refletada ba dezeńu detalladu.

(6) Materiais

(1) Estrutura Konkretu

Refere ba espesifikasaun iha-okos ká espesifikasaun seluk ruma ne'ebé utilizada jeralmente;

- i. ITEM 506-Estrutura Konkretu, “Standard Specifications, Roads, Bridges and Airport, MTCPW, 2005”

- ii. Sesaun 7.1 Konkretu & Sesaun 7.2 Prestressed Concrete, “General Specifications, August 2010, Projetu Melloramentu Estrada Nasional Indonesia Leste”
- (2) Besi-Reforsamentu/Reinforcement Steel  
 Refere ba espesifikasaun iha-okos ká espesifikasaun seluk ruma ne’ebé utilizada jeralmente;
- i. ITEM 505-Reinforcing Steel, “Standard Specifications, Roads, Bridges and Airport, MTCPW, 2005”
  - ii. Sesaun 7.3 Reinforcing Steel, “General Specifications, August 2010, “Projetu Melloramentu Estrada Nasional Indonesia Leste”
- (7) Rezolvementu Kontra Susulin Mota
- 1) Protesaun ba Sasatan;abutment/Pilar;pier.  
 Husu ba LM oinsá sasatan no pilares mak adekuaudu protejidu.
  - 2) Liña-livre/Freeboard  
 Husu ba LM katak barak ká lae liña-livre/Freeboard, apuramentu/clearance entre nivel bee-ass no padiera/soffit husi ponte. Depende ba diskarga husi mota; maibe nia tenke ser liu husi 1.0m kontra inundasaun.
- (8) Dezeñu
- 1) Dimensaun Maioria  
 Verifika dimensaun maioria hanesan ponte no espasu/span nia naruk, seksaun-kruzada/cross – section no kuaru ulun vertikal livre/vertical free head room hanesan iha-okos;
    - Ponte and Espasu/Span Nia Naruk  
 Sé relasaun entre ponte nia naruk no espasu/span nia naruk loloos?
    - Seksaun-kruzada/ cross –section  
 Sé luan husi trotoar/footway no Estrada-lolon/roadway tebes-duni ba klasse Estrada?
    - Kuaru Ulun Vertikal/Vertical Head Room  
 Iha assuntu através ponte hanesan ponte warren truss, tenke iha fatin ne’ebé nataton ba veikulu sira passajen iha ponte ne’e. Baibain preferivel hodi iha apuramentu/clearance vertikal liu husi 5.0m iha laletek husi pavimentu/pavement.

Klasse Estrada	Luan (m)		
	La’o Ain nia Fatin/trotoar Liman Karuk	Estrada Lolon	La’o Ain nia Fatin/trotoar iha Liman Loos
Klasse A	1.0	7.0	1.0
Klasse B	0.5	6.0	0.5
Klasse C	0.5	4.5	0.5

*Notifikasaun; Luan ké hatudu iha-leten ne’ebé Minimu.*

- 2) Konteúdu husi Dezeñu  
 Jeralmente estruktura ponte nia dezeñu iha konteúdu hanesan tuir-mai:

- Vizaun Jeral
- Mapa Lokalizaun
- Detallu husi Superestrutur
- Detallu husi Junta Expansaun
- Detallu husi Aguenta (Bearings)
- Detallu husi Sistema Drenajen
- Detallu husi subestrutur (Abutments; sasatan/Piers; pilares)
- Detallu husi Fundasaun
- Detallu husi Banku Protesaun, Revestimentu (revetment),
- Detallu husi Assessu Estrada.

3) Notifikasaun

Toma atensaun kona-ba “Notifikasaun” hatudu tiha ona iha dezeńu no verifika sira ne’e, wainhira hetan deskrisaun bei-beik:

- Grau Konkretu,
- Konteúdu sementi mínimu
- Rasio W/C Máxima
- Sasan husi Besi-betaun (Rebar)
- Kobertura Konkretu Mos
- Standard/padraun Naruk husi Rebar/besi-betaun.

(9) Lista kuantidades (BOQ)

Jeralmente Lista Kuantidade (BOQ) konsiste husi item sira iha-okos:

- 1) Rekerementu Jeral
- 2) Obra Atteru
- 3) Nanahe Superfisie Aspal
- 4) Fundasaun-Okos no Fundasaun Superfisie-Leten
- 5) Konstrusaun Ponte
- 6) Drenajen no Protesaun Deklive; Hali’is (Slope)
- 7) Estrutura de Diversos
- 8) Servisu Lor-loron
  - Fora husi item sira ne’e, hili item maioria balun no husu LM oinsá sira hare kuantidades, presu unidade no montantes.

(10) Padraun Dezeńu

Husu LM padraun dezeńu ne’ebé mak utiliza ba dezeńu,

- AASHTO Code” Standard Specifications for Highway Bridges”, Edisaun 16<sup>o</sup>, 1996,
- Sistema Jestaun Ponte – Kódigu Dezeńu Pontes (Indonesia), ká
- Padraun Seluk

(11) Espesifikasaun Téknika

Husu LM Espesifikasaun Téknika ne’ebé mak utiliza ba konstrusaun,

- Ministériu das Obras Públiku “Standard Specifications, for Roads, Bridges and Airport, 2005”, ká
- Espesifikasaun Seluk



### 1.1.5.2 Projeitu Estrada (Lista-Verifikasaun/Checklist C2)

(1) Klasifikasaun Estrada

Verifika Klasse estrada ho nia luan. Liuliu Klasse A korresponde ba Estrada, Klasse B

ba Estrada Nasional, Klasse B ba Estrada distritu, no Klasse C ba Estrada rural.

Klasse Estrada	Luan (m)			
	Kabas	Estrada-lolon	Kabas	Total
Klasse A	1.0	7.0	1.0	9.0
Klasse B	1.0	6.0	1.0	8.0
Klasse C	1.0	4.5	1.0	6.5

*Notifikasaun; Luan ké hatudu iha-leten ne'ebé Mínimu.*

(2) Dezeña Karga

Sé karga roda ne'ebé mak utiliza ba dezeña própria? Husu LM oinsá sira deside karga ne'e.

(3) Oráriu Konstrusaun

Iha Dokumentus Tender, tenke iha deskrisaun ida husi Períodu Konstrusaun.

Husu LM atu hatudu oráriu konstrusaun sobre Períodu

Konstrusaun ida-ne'ebé deside tiha ona, no konfirma katak konsiderada ba tempu udan.

(4) Ámbitu husi Obra

Verifika iha pontu hahú nian, pontu remata no distánsia total.

(5) Dezeñu Jeométriku

1) Kurvature(lengkungan) Mínimu

Sé kurvature mínimu nataton ba Projeitu nia objetivu?

Husu ba LM ida-ne'ebé iha Padraun Dezeñu Geométriku ké desidi ona kurvature.

Refere ba “Road Geometry Design Standard, MOI, Jullu 2010”.

2) Rai-lolon Subida Teb-tebes(Steepest Gradient)

Sé rai-lolon subida nataton ba Projeitu nia objetivu?

Husu LM ida-ne'ebé iha Padraun Dezeñu ba Subida ké desidi tiha ona.

Refere ba “Road Geometry Design Standard”, MOI, Jullu 2010.

(6) Sistema Drenajen

Verifika katak tipu, dimensaun, no arranju husi sistema drenajen mak Dezeñada própria ona.

(7) Moru Protesaun

Verifika katak Moru Protesaun ho tipu próprio no dimensaun mak arranjadu iha lokalizasaun adequadu.

(8) Baleta Rai-okos(Culvert)

1) Konfirma katak rai taka tomak baleta rai-okos(culvert) mak suficiente.

2) Konfirma katak tipu no dimensaun husi culvert mak próprio ona.

(9) Estrada Alternativa

Konfirma oinsá atu tráfikú passa durante servisu iha assuntu husi rehabilitasaun ba estrada existe-hele, ká existe estradas alternativas.

(10) Akquizasaun Rai

Konfirma katak hetan rai hotu ké presija ba obra.

(11) Kondisaun Jeolojika

Konfirma katak laiha Kondisaun Jeolójika mak desfavorável. Kuandu iha problema ruma hanesan bele rezulta ba rai-halai ká rai-mamar, husu LM kontramedida/rezolvementu saida mak sira konsidera.

(12) Dezeñu

Verifika katak dimensaun maioria hanesan naruk husi Estrada-lolon, luan husi estrada-lolon no nia kabaas haktuir ho klasse estrada no dokumentu tender sira seluk. Nomós konfirma katak iha konteúdu dezeñu suficiente atu konstrui ponte?.

(13) Lista Kuantidades (BoQ)

Verifika kuantidades, presu unidade sira no montante husi item maioria sira. Ida-ne'e rekomenda katak kustu unidade per kilómetru konstrusaun husi kada obra konstrusaun estrada mak rejista ona ba Evaluasaun grossu projetu iha futuru husi projetu estrada ké hanesan.

#### 1.1.6. Rona husi LM

ADN sei rona husi LM oinsá sira atenzi solusaun final ida-ne'e, iha lia fuan seluk, karik sira prepara ona ho alternativus seluk.

Ida-ne'e difisil tebes atu Verifika Dokumentus barak-liu ké simu iha loraon oitoande'it. Nune'e maka rekomenda teb-tebes ba Enjeñeiru Foin-sa'e ADN sira atu estuda dokumentus tender no prepara perguntas iha akordânsia ho utilizaun manual ida-ne'e uja lista-verifikasaun ne'ebé anexada iha-ne'e antespadamente husi nia-an rasik, hodi bolu Enjeñeiru LM no Konsultan dezeñu mai iha ADN, no husu perguntas no adjudika.

Ne'e sei ajuda Enjeñeiru ADN sira atu salva tempu ba verifikasaun, no hasa'e sira nia kapasidade.

#### 1.1.7. Oráriu Verifikasaun:

ADN sei prepara oráriu, iha-ne'ebé disponivel ba funsionáriu ADN hodi kompleta verifikasaun obra iha tempu mak termina.

Oráriu Verifikasaun ba Dokumentus Tender mak apertada tebes, iha loraon 10 kalendáriu deit hafoin simu dokumentus ne'ebé sei fó.

Ne'e rekomenda hodi prepara oráriu ba verifikasaun, mós haktuir oráriu, kontinua tuir ida ba ida, loraon ba loraon.

Ezemplu husi Oráriu Verifikasaun mak hatudu iha-okos ba operasaun loraon 10.

#### [Loraon 1 to'o 3)

(1) Verifika sé-karik dokumentus rekeridu hotu-hotu mak hatama utiliza **Lista-verifikasaun/checklist A**.

Karik lae, informa ba LM katak dokumentus la suficiente, no verifikasaun sei

- hahú husi loron tuir-mai bainhira simu dokumentus adekuaudu.
- (2)Wainhira dokumentus hotu-hotu mak submete ona, hahú verifika Kondisaun Pagamentu/apêndise ba Tender/ Kondisaun partikular, iha akordânsia ho Manual ne'e utiliza **Lista-Verifikasaun/Checklist B**.
  - (3)Prepara perguntas hatuir ba Manual ida-ne'e utiliza **Lista-Verifikasaun/checklist C, C1** ba Projetu Pontes, **C2** ba Projetu Estrada.
  - (4)Arranja entrevista ho LM no nia Konsultan hodi husu perguntas téknika iha Loron Segundu.

**[Loron 4 to'o 6]**

- (1)Husu perguntas sobre assunto téknika ne'ebé ita-bo'ot prepara ona.
- (2)Karik sira nia resposta mak la satisfatóriu ká k responde mak la klaru tamba dadus Ké falta, afirma ba sira atu prepara dadus suficiente hodi esplika, hafoin arranja entrevista tuir-mai. Loron tuir-mai husi entrevista ikus-mai mak Loron Segundu husi verifikasaun.
- (3)Husu LM atu kompleta korreksaun hotu-hotu, no submete fila-fali.

**[Loron 7 to'o 10]**

- (1)Verifika de'it parte korrije ona, no manda dokumentu sira ba NPC, wainhira dokumentus korrijidu nian mak submete ona.
- (2)Iha kazu katak korreksaun mak la satisfatóriu, halo hanesan pontu (3) iha leten.

**1.1.8. Remédiu/Reparasaun**

Iha kazu katak problema ruma mak hetan tiha ona hanesan rezultadu ida husi verifika Dokumentus Tender, ADN sei informa problem ne'e ba LM no oinsá atu hadi'a.

Obra verification sei demora husi lakon tempu ba resubmissaun.

**1.1.9. FAQ (Frequetemente/Nafatin Husu Perguntas)**


Iha kursu husi verifikasaun dokumentus tender, Enjeñeiru ADN sira sei iha perguntas no problema oi-oin, no rezolve problema hirak ne'e ho ajudu husi sira nia Enjeñeiru senior sira. Ida-ne'e rekomenda ba Enjeñeiru sira, sé-mak sei rezolve problemas sira ne'e, mantein inskrisaun iha "Livru FAQ".

Livru FAQ ne'e, nu'udar ezemplu ida ne'ebé anexada iha-ne'e hanesan "**Anexu/attachment B**", bele ajuda enjeñeiru sira seluk ké hasoru problema hanesan.

## 1.2. Inspesaun Projetu & Rekomendasaun ba Pagamentu

### 1.2.1. Fluxograma

Figura 1-2. Fluxograma husi Dokumentus Tederizasaun



- (1) Kontraktor  
Kontraktor prepara dokumentus ne'ebé presiza ba pagamentu, no haruka dokumentus hirak nee ba Konsultan Supervizaun.
- (2) Konsultan Supervizaun  
Supervizaun Konsultan reve dokumentus, emite/hasai Sertifikadu ida ba Pagamentu wainhira nia simu dokumentus sira ne'e, no haruka nia ho dokumentus pagamentu seluk ba LM/Projetu Na'in.
- (3) LM/Projetu Na'in  
LM/Projetu Na'in reve dokumentus, aprova Pagamentu wainhira nia simu dokumentus sira ne'e, no haruka orijinal ida no kopia tolu husi dokumentus pagamentu sira hotu ba ADN.
- (4) ADN  
ADN nia papel mak atu inspesiona projetus bazea ba dokumentus no situasaun iha terrenu.
- (5) MPS  
MPS emite enkarseramentu, Bilete Sertifikadu Pagamentu (CPV) no Ordem de Compra/Purchase Order (PO) no haruka ba Tezouru.
- (6) TEZOURU  
Tezouru ordena ba Banku Sentral (BPA) hodi selu ba Kontraktor.
- (7) BANKU SENTRAL  
Banku Sentral selu montante ba Kontraktor nia Konta Bankária iha-okos.
- (8) Kontraktor nia Konta Bankária  
Kontraktor simu pagamentu iha nia Konta Bankária.

### 1.2.2. Oráriu husi Obra

- (1) Rekerementu Tempu ba verifikasaun iha ADN  
ADN tenke kompleta inspesaun ba pedidu pagamentu iha  
Loron (10) sanulu kalendáriu nia laran hafoin simu ofisialmente dokumentus  
ké rekere husi ADN.
- (2) Tempu submissaun adisional, resubmissaun ká responde baperguntas ADN nia  
LM tenke submete, resubmete ká responde ba ADN saida mak rekere ona husi  
ADN iha loran 10 kalendáriu nia laran hafoin simu notifikasaun husi  
rekerementu informasaun adianta liu-tan.
- (3) Enkuantu husi sub-klauza (2) iha leten, tempu ba ADN atu kompleta  
Inspesaun tenke ser demora wainhira LM halo hela submissaun adisional,  
resubmissaun ká responde iha tempu hanesan.

### 1.2.3. Inspesaun Dokumentus

- (1) Konfirmasaun ba Dokumentus ké submete ona: ADN sei simu dokumentus  
pagamentu original ida no kopia tolu husi LM/Projetu Na'in, no verifika karik  
dokumentus rekeridu hotu-hotu mak entrega tiha ona ké hatudu iha-okos  
utiliza **Lista-Verifikasaun/checklist D**. Iha kazu buat ruma falta, ADN sei  
informa LM kona ba ida-ne'e no informa LM atu submete dokumentus iha  
tempu espesifikadu nia laran.
  - 1) Karta Pedidu Orijinal (Invoice) husi Kompañia
  - 2) Submete Sertifikadu Pagamentu Orijinal ida-ne'ebé aprova ona husi  
Ministru ká Sekretáriu Estadu husi Liña Ministeriais
  - 3) Hatama kopia dokumentu husi Kontratu ké válidu hela no kompleta ho  
nia anexu
  - 4) Hatama kopia tolu husi Relatóriu Progressu Fíziku ne'ebé aprova ona  
husi Projetu Na'in
  - 5) No. TIN (Identificação do contribuite Registo Imposto)
  - 6) Kopia Númeru husi Konta Bankária husi Kompañia
  - 7) Submete "Sertidaun Dívidas" Kompañia nian ké válidu no tenke ser  
legalizada
  - 8) Hatama "Lisensa de Atividades Kommérsiu" ké válidu no tenke ser  
legalizada
  - 9) Submete "Para Quem Interessado" ne'ebé válidu
  - 10) Karik, Pagamentu ba progressu fisiku 100%, tenke hatama karta "Termo  
Pre-HandOver/Entrega (PHO)
  - 11) Karik, Pagamentu ba Retensaun, tenke anexa "Termo de Entrega  
Final/Final HandOver (FHO)
  - 12) Lista Kuantidades ( BoQ).
- (2) Konfirmasaun ba Kondisaun Pagamentu hanesan pagamentu adiantadu no  
retensaun: Inspetór ADN halo serteza ba kondisaun pagamentu para  
kalkulasaun montante ne'ebé atu selu mak tebes haktuir ba deskrisaun husi  
dokumentu kontratu.

- (3) Kalkulasaun iha folha lisitasaun  
Uluk-nana'in, inspetór ADN refere ba BoQ iha dokumentus ne'ebé entrega ona husi LM, no mós prosentajen husi obra completa ona iha períodu ida-ne'e, exijidu husi kontraktor iha Pedidu/invoice. No mós nia halo dadus-apoiu/ backup data haktuir ba medida/sasukat ké nia halo ona iha ninian inspesaun terrenu, no hafoin kalkula kuantidade husi kada item. Nia formulasaun mak  $\text{Progresu} \times \text{Total Valor Kontratu}$ .
- (4) Konfirmasaun ba obra ké completa ona iha BoQ laran  
Inspetór ADN kompara montante exijidu husi pedidu/invoice ho montante kalkualadu ona husi nia bazea ba inspesaun terrenu. Iha kazu katak montante Kalkuladu differênsia hosi ne'ebé mak husi invoice, ADN sei kontakta kontraktor hodi hatudu rezultadu Kalkuladu no fó ba nia oportunidade ida atu esplika tamba-sá nia hasai konkluzoan ida-ne'e to'o halo desizaun final.
- (5) Konfirmasaun ba oráriu obra  
Inspetór ADN verifika Relatóriu Menssal Konsultan nian no kompara progresu husi oráriu planeadu tiha ona ho oráriu atual.

#### 1.2.4. Inspeasaun Terrenu

- (1) Preparasaun  
ADN manda Pedidu Preparasaun Inspeasaun Terrenu ba LM utiliza **Formatu/Form B**, lora 7 iha lora servisu molok Inspeasaun.
  - 1) Assistente  
LM sei konvida ema sira iha-okos iha inspeasaun terrenu.
    - Inspetór hosi ADN
    - Enjiñeiru hosi Liña Ministériaais
    - Konsultan Supervizaun
    - Kontraktor
  - 2) Preparasaun  
LM sei arranja buat-hirak iha-kraik iha inspeasaun terrenu.
    - Inskrisaun kona-ba Kontrola Kualidade
    - Dezeñu
    - Detalha husi Bill of Quantities (BoQ)
    - Ekipamentu Medisaun/sukat
    - Assistente ba Sukat/Medisaun
- (2) Oráriu Verifikasaun  
Inspetór ADN verifika progresu atual haktuir ba Relatóriu Progresu Menssal/ Monthly Progress Report.
- (3) Kontrolu Kualidade/Quality Control  
Inskrisaun husi kontrola kualidade ne'ebé avalia ona husi Inspetór ADN utiliza **Lista-Verifikasaun/checklist E**.  
Item Verifikasaun iha checklist nu'udar ezemplu deit, nune'e item apropiadu tenke ser aumenta depende ba situaasaun.

(4) Medisaun ba obra Kompletá ona

Objetivu husi medisaun mak atu konfirma katak kuantidade atual husi item ké kompletá mak igual hanesan ho kuantidade exigidu iha invoice.

Kuantidade husi item obra ké kompletá ona mak sukat utiliza **Lista Verifikasaun/checklist F**.

Item iha checklist no esplikasaun hirak ne'e nu'udar ezemplu deit, no sira sei bele truka no/ká depende ba item sira iha tempu inspesaun.

(5) Remédiu/reparasaun(Hadi'a)

Bainhira ADN hetan buat ruma la konfirmadu ká obra la satisfeitu, ADN tenke ordena/haruka remédiu.

**1.2.5. Notifikasaun husi Julgamentu kona-ba Pagamentu**

Finalmente ADN julga montante pagamentu adekuaadu,, notifika rezultadus no rekomendasaun pagamentu ba MPS, utiliza **Formatu/form C**.

ADN manda orijinal ida no kopia rua husi dokumentus pagamentu ba MPS, no mantein kopia ida iha eskritóriu ADN.

**1.2.6. FAQ (Frequetemente/Nafatin Husu Perguntas)**

Iha kursu husi inspesaun ba pagamentu, enjiñeiru ADN sei iha perguntas no problema oi-oin, no rezolve sira ne'e ho apoiu husi sira nia senior enjineiru sira. Ida-ne'e rekomenda tebes ba enjiñeiru sira, ba sé mak sei rezolve problema hirak ne'e, atu mantein inskrisaun iha "Livru FAQ".

Livru FAQ ne'e, nu'udar ezemplu ida ne'ebé anexada iha-ne'e hanesan "**Anexu/attachment B**", bele ajuda enjeñeiru sira seluk ké hasoru problema hanesan.

## FORMATU-A1 (Rezumu Projetu ba Projetu Pontes)

Data Submissaun/hatama						
Naran husi Projetu						
Ajensia Implementador			Kontaktu Pessoai			
Konsultan Dezeńu			Kontaktu Pessoai			
Lokalizasaun/Fatin Projetu						
Mota						
Kategoria husi Fundu						
Kategoria husi Estrada		Estrada Nasional	Estrada Distritu	Estrada Rural		
Akquizasaun Rai/Pembebasan tanah						
Levantamentu kondisaun natural/ Natural Conditions Survey		Survei Topografia		Survei Jeoteknika		
Karga Direta/ Beban Langsung/Live Load						
Tipu Superstrutura/Type of Superstructure						
Tipu Substrutura/Type of Substructure						
Tipu Fundasaun/Type of Foundation						
Especifikasaun Técnica						
Padraun Dezeńu/Design Standards						
Nivel altura beeha Lina-Livre nia leten /Freeboard above High Water Level		m				
Orariu Projetu ne'e be hein-hela		Hahu	Ramata		Periódú Konstrusaun	Loron
Total montante husi Folin estimativa						
Ponte nia Dimensaun/Dimension of Bridge		Ponte nia Naruk	m	Espasu/Span	m	Luan

Nota: 1) LM tenke enxe formatu ne'e, no anexa Dokumentu Tender para verifikasaun husi ADN.  
 2) Formatu ida ne'e aplikavel ba projetus ponte iha kategori seluk hanesan Projetus Fundus Lina Ministeriais.



**FORMATU A2 (Rezumu Projektu ba Projektu Estrada)**

Data Submissaun/natama								
Naran Projektu								
Ajensia Implementador					Kontaktu Pesoi			
Konsultan Dezeru					Kontaktu Pesoi			
Lokalizasaun Projektu								
Fundunha Kategoria	Fundu Infraestrutur							
Estradunha Kategoria	Estrada Nasional	Estrada Distrital	Estrada Rural					
Tipu husi Pavimentu/Pavement								
Distansia Mi./Mileage	Hahu	Ramata				Total Distansia		km
Espesifikasaun Teknika								
Padraun/standart Dezeru								
Padraun Dezeru Jeometrika								
Laletek subida maka as/Steepest Gradient		%						
Kurvatura minimu		m						
Orgru ne ebe hakarak ba projetu	Hahu		Ramata			Periodu Konstrusaun		Loron
Total Montante husi estimasaun presu								

*Nota 1) LM tenke enxe Formatu nee, no anaxa ba Dokumentus Tender para verifikasaun husi ADN  
2)Formatu ida ne'e aplikovel ba projektus ponte seluk, iha kategoria seluk hanesan Projektus Fundu Ii'na Ministeriois*

Formatu B (Pedidu Preparasaun ba  
Inspesun terrenu)



**REPÚBLICA DEMOCRÁTICA DE TIMOR-LESTE  
GABINETE DO PREMIÉIRO MINISTRO  
AGÊNCIA DE DESENVOLVIMENTO NAÇIONAL**

DATA

(Hato'ó ba Sé)

LM

(ASSUNTU) PEDIDU PREPARASAUN BA INSPESAUN TERRENU

Nu'udar responde ba pedidu pagamentu ké submete ba ADN, ADN informa katak ..... ADN rekere ba LM atu prepara hirak-tuir-mai para hala'ó inspesaun terrenu ho própriu no haktuir-orden.

1. Naran husi Projetu
2. Data husi Inspesaun Terrenu
3. Rekere prezensa husi
  - 1) Supervisor no Enjiñeiru(s) responsabelizada hosi LM
  - 2) Konsultan Supervizaun
  - 3) Jerente Terrenu hosi Kontraktor.
4. Preparasaun iha terrenu arranjada husi LM
  - 1) Inskrisaun/Records kona-ba Kontrolu Kualidade
  - 2) Drawings with completed construction included
  - 3) Detaillu husi BOQ
  - 4) Ekipamentu sukat, karik persija Teste Destrutivu/harahun( Destructive Testing)
  - 5) Assistente ba Medisaun/sukat(Measurement)

Husi ADN

CC.

Ba organizaun relevante karik iha.

FORM C



**REPÚBLICA DEMOCRÁTICA DE TIMOR LESTE**  
**GABINETE DO PRIMEIRO MINISTRO**  
**AGÊNCIA DESENVOLVIMENTO NACIONAL**

No	RELATORIO	INSPECSAUN	NO	RECOMENDASAUN	BA	PAGAMENTO
1	Projecto nia Naran	Sculpturing and installation of statues for santa cruz, Memorial Monument and King Dom Boaventura				
2	Ministerio/Dono de Projecto	Agencia Dezenvolvimento Nacional				
3	Fontes de Fundos : ( PDD I, PDD II,PDL,FI,Emergencia,MDG Suco,etc)					
4	Contractor	PT. Siluet Nyoman Nuarta				
5	Numero PO (Purchase Order)					
6		a. Distrito : Dili b.Sub distrito : c.Suco/Aldeia :				
a	Valor Contracto	a	\$	738,888.00		
b	Progreso fisico iha fulan kotuk	b		0.00%		
c	Progreso fisico ate agora	c		50.00%		
d	Valor Pagamento foer ate agora (gross)	(c-b)*a	\$	369,444.00		
e	Osan adiantamento nebe simu ona ....%	....%*a	\$	-		
f	Deducsaun adiantado ba pagamento ida ne'e ..%	(c-b)*e	\$	-		
g	Deducsaun retensaun ba pagamento ida ne'e 10%	0.1*d	\$	36,944.40		
h	Net pagamento depois de deducsaun ba retensaun	d-g	\$	332,499.60		
i	Net pagamento nebe atu selu ba pagamento ida ne'e	h-f	\$	332,499.60		
j	Total Net pagamento ate agora		\$	332,499.60		
k	Balansu depois de pagamento ida ne'e	(100%-c)*a	\$	369,444.00		
7	Observasaun ou komentario seluk :					
8	Recomendasaun ba MPS-MdF/Tezouro-MdF/Ministerio/Agencia Tutela Selu ho Montante (USD)			332,499.60		
9	Observasaun :		SIM	Komentarios Ruma	LAE	
a	Tuir Dezenho ?					
b	Tuir BOQ ?					
c	Tuir Espesifikasaun ?					
d	Tuir Schedule curva S ?					
e	Tuir Termos de Contracto ?					
10	Data Inspeksaun		Data:	Fulan:	Tinan:	
11	Enginheiro Nebe Halo Inspeksaun :	Assinatura:				Data :
	1. Naran : Eng. Jaquelina da Costa Sales					
	2.Naran :	Assinatura:				Data :
12	Verifikado Hosi :	Assinatura:				Data :
	Eng. Aleixo A. do Carmo					
13	Q.A	Assinatura:				Data :
	Ir. Eron St. Henuk MM, MPU					
14	Approvado Hosi :	Assinatura:				Data :
	Sr. Samuel Marçal Directur Geral - ADN.					

# Checklist A



## REPÚBLICA DEMOCRÁTICA DE TIMOR LESTE GABINETE DO PRIMEIRO MINISTRO AGÊNCIA DE DESENVOLVIMENTO NACIONAL

### Checklist husi Verifikasaun Dokumentu ba Dezeñu no BOQ

Naran husi Projetu :  
Projetu Na'in :  
Número Kontratu :  
Data Simu dokumentu :

1. Karta Akumpañamentu.....
2. Dezeñu tenke ser kompleta no hetan assinatura husi Obras Pública.....
3. BOQ no Estimasaun Kustu hetan assinatura husi Obras Pública .....
4. Análiza Presu Unidade/Unit Price Analysis.....
5. Soft copy husi dokumentus ida-ne'ebé mensiona iha-leten.....
6. Espesifikasaun Técnica .....
7. Ida-ne'e tenke iha mós Análiza Kalkulasaun Estrutura no Hidrolójia, nomós dados Topografía.....

***Notifikasaun: Checklist ida-ne'e utiliza hodi konfirma katak dokumentus rekeridu hotu-hotu submetidu ona para verifikasaun dokumentu husi Projetu Fundu da Infra-estrutura ba Estrada, Ponte, Portu & Irrigasaun.***

**Checklist A**



**REPÚBLICA DEMOCRÁTICA DE TIMOR LESTE  
GABINETE DO PRIMEIRO MINISTRO  
AGÊNCIA DE DESENVOLVIMENTO NACIONAL**

---

**CHECKLIST DOKUMENTU TENDER BA PROJETUS KONSTRUSAUN  
EDIFÍSIU & MORU HALE'U ESKRITÓRIU**

1. Dezeñu tenke ser aprovalu husi Obras Públika \_\_\_\_\_
2. Bill of Quantity ( BoQ) tenke ser aprovalu husi Obras Públika \_\_\_\_\_
3. Estimasaun Kustu tenke ser aprovalu husi Obras Públika \_\_\_\_\_
4. Espesifikasaun Téknika tenke ser hetan husi Obras Públika \_\_\_\_\_
5. Submete file elektrónika ne'ebe salva iha CD laran \_\_\_\_\_
6. Karik Edifisiu mak nia ass mak liu andar 2, tenke ser anexada Estudu Viabilidade husi Rai ká rezultadus invertigasaun rai \_\_\_\_\_
7. Karik Edifisiu nia ass mak liu andar 2, tenke ser anexada Análiza Kalkulasaun Estrutura \_\_\_\_\_

***Notifikasaun: Checklist ida-ne'e utiliza hodi konfirma katak dokumentus rekeridu hotu-hotu submetidu ona para verifikasaun dokumentu husi Projeitu Fundu da Infra-estrutura ba Edifisiu.***

Fundu Infrastructural			Checklist B (Kondisaun ba Pagamentu)		Verifika husi	Aprova husi
Tipu Projetu	Jerál	Klasse Obra	Kondisaun husi Kontratu			

No. Kontratu Naran Projetu Ajénsia Implementasaun		Data entrega Nivel	Verifikasaun ba Dokumentus Tenderizasaun			
Lista Material	Pontus Verifikasaun	Data Verifikasaun	Marka Verifikasaun	Observasaun		
	Ida nee atu konfirma katak dokumentus hotu-hotu entrega ona husi LM			Dadus Passadu Bai bain		
1	Tempu ba kompletu/ periondu konstrusaun (Time for completion/Construction Period)			Orariu tempu detail lirona husi LM		
2	Periondu Manutensaun/Periondu Notifikasaun Estragu (Maintenance Period/Defect Notification Period)			Rona dadus passadu LM nian		
3	Lei Governu/Governing Law			Lei husi RDTL		
4	Regulamentu Lingua / Ruling Language			Ingles		
5	Garantia Exekusaun/ Garantia Exekusaun Diak (Performance Security/Performance Bond)			5-10% husi montante kontratu		
6	Demora estragu ba obra/Multas (Maximum amount of delay damages)			0.1%/loron		
7	Montante Máximu Ba Demora Estragu (Maximum amount of delay damages)			5-10% husi montante kontratu		
8	Montante Provizóriu /Provisional Sum			15% husi kontratu		
9	Total Pagamentu Adiantadu (Total Advance Payment )			10-20% husi kontratu		
10	Persentajen ba Retensaun (Percentage of Retention)			5-10% husi kontratu		
11	Limitada ba Orsamentu Retensaun/Limit of Retention Money			5-10% husi kontratu		
12	Kuantidade mínimu husi Sertifikadu Pagamentu Provizóriu/ Minimum Amount of Interim Payment Certificates			1-5%		

Notifikasaun: Dadus passadu ba kondisaun kontratu bele uja hanesan referensia ba Projetu Fundu da Infra-estrutura seluk alein estrada & Ponte.

A	B	C	D	E	F	G	H	I	J
1									
2	<b>Fundu Infrastruktura</b>	<b>Checklist C1 (Checklist Téknika ba Ponte)</b>							
3									
4	<b>Tipu Projetu</b>	Ponte	Objetivu	Verifikasaun Tékniku ba ponte					
5									
6	No. Kontratu								
7	Naran Projetu								
8	Ajénsia Implementador								
9	Item Avaliasaun	Pontus Verifika							
10							Marka Verifikasaun	Obserbasaun	
11	Klassifikasaun Estrada/Road Classification	Klassifikasaun estrada Konfirma ona ka lae?							
12	Karga Direta/ Beban Langsung/Live Load	Sé-karik karga direta adekuadu ba klassifikasaun karga?							
13	Ponte nia Luan/Bridge Width	Sé-karik viatura nia luan no numeru husi pista -trafiku(Lane) adekuadu?							
14		Sé-karik Passeiu(footway) nia luan apropiadu?							
15	Limitasaun kontra Planu	Sé-konfirma katak laiha fiu eletrisidade/kabel komunikasaun iha ponte nia leten?							
16	Ponte/ Constraints against bridge plan	Sé-konfirma katak laiha fiu ká kanu hako iha rai okos?							
17		Sé-konfirma katak laiha problema akvizizasaun rai?							
18	Levantamentu Jeotékniku & Topográfiku (Geotechnical & Topographical Survey)	Sé-karik levantamentu topográfiku hali'ona, presiza dezeñu detai lladu?							
19		Sé-karik levantamentu Jeotékniku, hali'ona, presiza dezeñu detai lladu?							
20	Materiais/Materials	Sé-karik betau konkretu nia forsa adekuadu? Sé-karik forsa husi besi aniha homan reforsementu adekuadu/reinforcement steel bar?							
21	Rezolvimentu hasoru Mota nia Suli /Countermeasures against River Flow	Sé-karik Proteasaun ba Sasatan(Abutment)/pillar (Pier)konsiderada própriu?							
22		Sé-karik lina-livre (Freeboard), apuramentu (clearance)ponte okos ba nivei altura husi bee, natoon?							
23		Verifika dimensaun bo'ot-liu							
24	Dezeñu/Drawings	Sé iha konteúdu nataton husi dezeñu atu konstrui ponte? sé apuramentu (clearance) vertikál entre plataforma/deck no estrutura kruzada ida-leten liu natooh ba víkulu entantu ba tipu-plataforma ponte-							
25		Verifika kuantidades, presu unidade no montante husi item bo'ot-liu ruma?							
26	Lista kuantidades/ BoQ								
27	Padraun Dezeñu /Design Standards	Verifika Padraun Dezeñu ida-ne'ebé mak uza/adopta?							
28	Espesifikasaun Téknika /technical Specification	Verifika Espesifikasaun Téknika ida-ne'ebé mak uza/adopta?							
29	<b>Notifikasaun: Checklist ida-ne'e bele uja hanesan referensia ba Projetu Fundu da Infra-estrutura seluk alein estrada &amp; Ponte.</b>								
30									

Fundu Infraestrutura			Checklist C2 (Teknika Verifikasaun ba Estrada)			Verifika husi	Aprova husi
Tipu projetu	Estrada	Objectivu	Verifikasaun Téknika ba Estrada				
No Kontratu			Data Submete		, 2012		
Naran Projetu			Faze		Verifikasaun Dokumentu Tenderizasaun		
Ajénsia Implementador							

Item Verifika	Pontu Verifika	Data Verifika	Marka Verifika	Referénsia
1	Klassifikasaun Estrada	Klasse saida mak husi estrada ne'e?		Rona husi LM
2	Dezeñu Karga	Karga Dezeñu saida mak uza ba Dezeñu estrada ne'e?		Rona husi LM
3	Oráriu Konstrusaun	Sé-karik periode konstrusaun apropriau?		Rona husi LM
4	Ámbitu husi obra	Konfirma original nian, Estrada nia rohan no naruk.		Oráriu Tempu Detaillu
5	Dezeñu Jeométrika	Sé-karik volta kurvature/lengkungan belok mínimu própriu? Sé-karik subida rai-lolon makas( steepest gradient) própriu?		Rona husi LM Refere ba Lissaun aula-laran kona-ba ponte (7)
6	Sistema Drenajen(drainage)	Karik sistema drenajen(drainage system) di'ak ona?		Rona husi LM
7	Moru Retesaun	Karik lokalizasaun, tipu, altura husi moru retesaun di'ak ona?		Rona husi LM Dezeñu
8	Baleta rai-okos/perit(Culvert)	Karik rai taka tomak baleta -rai-okos( culvert) ká lae? Karik tipu no dimensaun husi baleta-rai-okos(culvert) di'ak ona?		Rona husi LM Dezeñu Rona husi LM Dezeñu
9	Estrada Alternativa	Entantu rehabilitasaun ba estrada ke existe-hela, Iha ká lae dalan alternativu ida?		Rona husi LM Dezeñu
10	Akquizasaun Rai	Karik hetan ona rai ne'ebe persija?		Rona husi LM
11	Kondisaun Jeolójika	Karik konsidera ona rai-mamar no rai-halalai? <b>Verifika dimensaun maioria/bo'ot</b>		Rona husi LM Dezeñu
12	Dezeñu	Karik iha konteudu husi deseñu atu harii ponte?		Dezeñu
13	Lista Kuantidades/ BoQ	Verifika kuantidade, presu unidade no montante husi item maioria/bo'ot balun?		Dezeñu,BoQ Rona husi LM

**Notifikasaun: Checklist ida-ne'e bele uja nu'udar referensia ba projetu estrada iha kategoria seluk hanesan Projetu Fundu Ministeriais.**



## Checklist D



# REPÚBLICA DEMOCRÁTICA DE TIMOR LESTE GABINETE DO PRIMEIRO MINISTRO AGÊNCIA DE DESENVOLVIMENTO NACIONAL

### Checklist Pagamentu ba Dokumentu husi Konsultan Supervizaun

Projetu nia Naran :  
Na'in husi Projetu :  
Número husi Kontratu :  
Data Simu dokumentu :

1. Invoice iha Orijinal hatama husi Konsultan.....
2. Sertifikadu Pagamentu iha Orijinal ne'ebé hetan aprovasaun husi Ministru ká Sekretáriu Estadu.....
3. Submete kopia kompleta husi Kontratu Válidu ho nia anexu.....
4. Hatama Relatóriu Menssal ne'ebé hetan aprovasaun husi Projetu Na'in.....
5. Submete No. TIN (Identificação do Contribuente Registo Imposto).....
6. Número husi Konta Bankária.....
7. Submete Sertidaun Dividas ne'ebé válidu no tenke ser legalizadu.....
8. Submete Licença Actividades de Comercio e Económico ne'ebé válidu no legalizada.....
9. Submite Para Quem Interessado ne'ebé válidu .....

***Notifikasaun: Checklist ida-ne'e utiliza hodi konfirma katak dokumentus rekeridu hotu-hotu submetidu ona para dokumentu pagamentu husi Projetu Fundu da Infra-estrutura ba Estrada, Ponte, Portus & Irigasaun***

**Checklist D**

**REPÚBLICA DEMOCRÁTICA DE TIMOR-LESTE**  
**GABINETE DO PRIMEIRO MINISTRO**  
**AGÊNCIA DE DESENVOLVIMENTO NACIONAL**  
**CHECKLIST FUNDU DA INFRA-ESTRUTURA BA PAGAMENTU**

**Naran husi Projetu** :  
**Naran husi Kompañia** :  
**Númeru Kontratu** :  
**Valor husi Kontratu** : US\$  
**Valor husi Invoice/Pedidu** : US\$

No	Dokumentus ne'ebé submetidu iha Invoice laran	Resultadu		OBS
		Sim	Lac	
1	Kontratu sei moris hela (mais menus fulan ida antes data prazu hotu/ expired date). Valor kontratu mak liu husi >500,000 tenke ser sujeitada hodi hetan Karta Justifikasaun husi Tribunal das Contas, Tribunal Superior das Administrativas de Timor Leste.			
2	Submete Sertidaun Dívidas ne'ebé válido no tenke ser legalizadu			
3	Submete No. TIN (Identificação do Contribuente Registo Imposto)			
4	Submete Para Quem Interessado ne'ebé válido			
5	Submete Licença Actividades de Comercio e Económico ne'ebé válido no legalizada			
6	Submete Invoice Orijinal 1 (kopia 5) no hetan aprovasaun husi Tékniku LM			
7	Pedidu husi Karta Pagamentu			
8	Sertifikadu Pagamentu aprovada husi Liñe Ministriais			
9	Númeru Conta Banária husi Kompañia			
10	Recommendasaun Pagamentu hosi ADN			
11	Garantia ba Exekusaun di'ak tenke ser rai iha banku nu'udar garantia, ida-ne'e hanesan ho Valor Adiantadu ká bazea Termos husi Kontratu			
12	Invoice tenke ser anexada ho Relatóriu Progressu Mensal			
13	Kompañia Internacional tenke anexa sertifikadu hosi Organizasaun Padraun Internacional (ISO)			

***Notifikasaun: Checklist ida-ne'e utiliza hodi konfirma katak dokumentus rekeridu hotu-hotu submetidu ona para dokumentu pagamentu husi Projetu Fundu da Infra-estrutura ba Edifisiu, Estrada, Ponte, Portu, Irigasaun, etc.***

Checklist E (Kontrolu Kualidade)				Verifika husi	Aprova husi
Fundu Infraestrutura	Estrada & Pontes	Objetivu	Kontrolu Kualidade		
Tipu Projetu					
No. Kontratu	Data Submete		Inspesaun ba Pedidu Pagamentu		
Naran Projetu	Faze				
Ajensia Implementador					
Item Verifika	Pontos Verifikasaun	Data Verifika	Marka Verifika	Referensia	
1	Forsa Kompresivu/to'os iha loron 28			506.4.1 Tabela 506.2 MEAN, MTCPW, 2005	LIVRU
2	Lakon Frakeza/Siump Loss			506.4.1 Tabela 506.2 MEAN, MTCPW, 2005	LIVRU
3	Medida/ukuran deseñada ba massa grossu/Coarse aggregate			506.4.1 Tabela 506.2 MEAN, MTCPW, 2005	LIVRU
4	Baibain silu besi-betaun/rebar ba reforsementu konkretu ké utiliza iha relasaun ho AASHTO M 31 (Grau 400)			911.1 LIVRU MEAN, MTCPW, 2005	
5	Wweep holes/lubang berongga-frongga (Weep Holes)			606.3.7 LIVRU MEAN, MTCPW, 2005	
6	Cement/ Sementi			901.1 LIVRU MEAN, MTCPW, 2005	
7	Pilling/Pilar			ITEM 501, LIVRU MEAN, MTCPW, 2005	
8	Superfisie-okos/Subgrade			206.3.2 LIVRU MEAN, MTCPW, 2005	
9	Fundasaun-okos/Subbase			302.2 LIVRU MEAN, MTCPW, 2005	
				302.3.5 LIVRU MEAN, MTCPW, 2005	
10	Nanahe superfisie aspa/Base Course			401 LIVRU MEAN, MTCPW, 2005	
				405 LIVRU MEAN, MTCPW, 2005	
				406 LIVRU MEAN, MTCPW, 2005	
				407 LIVRU MEAN, MTCPW, 2005	

**Notifikasaun: 1) Wainhira Utilizasaun Checklist ne'e, ne'e mos refere ba materiais husi Lisaun Sala-laran Ponte (5).**

**2) Checklist ida-ne'e bele uja nu'udar referensia ba projetu ponte iha kategoria seluk hanesan projetus Lina Ministeriais.**

Fundu Infraestrutúra		Checklist F (Medisaun/Sukat)		Verifika husi	Aprova husi
Tipu Projetu		Estrada & Pontes	Objetivu	Medisaun/Sukat	
No. Kontratu					
Naran husi Projetu					
Ajénsia Implementasaun					
				Data Submete Faze	Inspesaun ba Pedidu Pagamentu
Item Verifika	Pontus Verifikasaun	Data Verifika	Marka Verifika	Referánsia	
1 Fundasaun Superfisie Lolon/Leten(Base Course)	Sukat naruk no luan husi obra remata ona iha periódu ida ne'e. Kalkula volume base course utiliza deseñu nia mahar husi baze.			Desenu & Lista kuantidade (BoQ)	
2 Pavimentu(Pavement)	Sukat naruk no luan husi obra remata ona iha periódu ida ne'e. Kalkula area pavimentu(pavement)			Desenu & Lista kuantidade (BoQ)	
3 Drenajen Limpa(Drainage Cleaning)	Sukat naruk no luan husi obra drenajen Limpa ne'ebé remata ona iha periódu ida ne'e			Desenu & Lista kuantidade (BoQ)	
4 Plester Fatuk Baleta sorin(StoneMasonry Side Ditch)	Sukat naruk neseráriu husi kada sorin no nia luan. Kalkula volume obra remata ona iha periódu ne'e.			Desenu & Lista kuantidade (BoQ)	
5 Lutu seguransa iha estrada ninin(Railing)	Sukat total naruk no número/jumlah husi Postu Giarmatadalan			Desenu & Lista kuantidade (BoQ)	
6 Markasaun estrada (Road Marking)	Sukat total naruk			Desenu & Lista kuantidade (BoQ)	
7 Sinál estrada (Road Sign)	Sura número/jumlah husi sinál estrada			Desenu & Lista kuantidade (BoQ)	
8 Moru Satan Anin (Wing Wall)	Sura dimensaun no kompara ho deseñu			Desenu & Lista kuantidade (BoQ)	
9 Balok plataforma/lantai (Deck Slab)	Sura dimensaun no kompara ho deseñu			Desenu & Lista kuantidade (BoQ)	
10 Balok Aproximafhakbesik (Approach Slab)	Sura dimensaun no kompara ho deseñu			Desenu & Lista kuantidade (BoQ)	

Notifikasan: Checklist ida ne'e bele uja hanesan referensia ba projetus estrada no ponte iha kategoria seluk hanesan Projetu Liña Ministeriais.

Naran husi Projetu	Eskema Irrigasaun Tono	Projetu Altu Estrada Suai-Beaço	Ponte Comoro 2	Ponte Baer	Projetu ADB	Projetu Irrigasaun Caraulun	Alkansamentu Kómun ita Projetu Passadu
Ajénsia Implementador	Ministériu de Agrikultura	Ministériu das Obras Públikas	ADN	Ministériu das Obras Públikas			
Tempu para Kompleta	-	-	Loron 270	Loron 480			
Períodu Manutensaun	Loron 90	Loron 365	Loron 90	Loron 540	Loron 365		90-540
Lei Governu nian	Lei husi Timor Leste	Lei husi Timor Leste	Lei husi Timor Leste	Lei husi Timor Leste	Lei husi Timor Leste		Lei husi Timor Leste
Regulamentu Língua	Inglês	Inglês	Inglês	Inglês	Inglês		Inglês
Garantia ba Exekusaun	10%	5%	5%	10%	5%	7.50%	5-10%
Demora hadi'a estragu	0.1%/Loron	0.1%/Loron		0.1%/Loron	0.1%/Loron	0.1%/Loron	0.1%/Loron
Montante Máximu husi Demora hadi'a Estragu	10%	5%		10%	10%		5-10%
Montante Klausula/ Provisional Sum				15%	15%		15%
Total Pagamentu Adiantadu/Advance Payment		15%	20%	10%	15%		10-20%
Porsentajen husi Retensaun		5%	5%	10%	10%		5-10%
Limitasaun husi Orsamentu Retensaun		5%		10%	10%		5-10%
Montante Mínimu ba Pagamentu Provizóriu		1%		5%			1-5%

Notifikasaun: Data passadu hirak-ne e husi kondisaun kontratu bele mos uja nu'udar referensia ba projetus Fundu da Infra-estrutura seluk alein estrada & Ponte.

## Anexu B1, Livru FAQ

### Livru FAQ

Sé mak hasoru problema ká perguntas, no hetan ona solusaun/respostas tenki tau rejistus hodi ajuda kolega sira ne'ebé bele hasoru problema hanesan iha futuru.

Naran husi Projetu		Ponte Tono		
<input type="checkbox"/> Estrada	<input checked="" type="checkbox"/> Ponte	<input type="checkbox"/> Irigasaun	<input type="checkbox"/> Portu	<input type="checkbox"/> Sira seluk
Verifikasaun ba DokumentusTender		<input type="checkbox"/> Insesaun ba Pagamentu Provizóriu		
Naran	XXX	Data	04 Sept. 2013	
<b>Problemas ká Perguntas ne'ebé hasoru</b>				
<b>Problem/Question</b> Dezeñu husi ponte hatudu katak ponte nia naruk maka metrus 360, maibé iha parte luan husi mota hakur ba haré hela-oitoan metrus 500. Oinsá tenke ser desidi ponte nia naruk?				
<b>Solusaun ká resposta ne'ebé hetan</b>				
<b>Solusaun/Resposta</b> Baibain ne'e mak magnétiku katak ponte mak igual ba ká naruk-liu duké mota nia luan, Maibé tau iha konsiderasaun faktu katak harí ponte naruk ne'e karun, forte no asegura protesaun mota-ninin dalaruma bele razoável. Antes desidi ponte nia naruk, iha alternativu rua, ponte naruk-liu ká asegura protesaun mota-ninin, tenke ser kompara.				
Naran husi Enjiñeiru Senior ne'ebé konsulta ba			Mr. YYY	

## Anexu B2, Livru FAQ

### Livru FAQ

Sé mak hasoru problema ká perguntas, no hetan ona solusaun/respostas tenki tau rejistus hodi ajuda kolega sira ne'ebé bele hasoru problema hanesan iha futuru.

Naran husi Projetu		Ponte XXX		
<input type="checkbox"/> Estrada	<input checked="" type="checkbox"/> Ponte	<input type="checkbox"/> Irigasaun	<input type="checkbox"/> Portu	<input type="checkbox"/> Sira seluk
Verifikasaun ba Dokumentus Tender		<input type="checkbox"/> Insesaun ba Pagamentu Provizóriu		
Naran	XXX	Data	04 Sept. 2013	
<b>Problemas ká Perguntas ne'ebé hasoru</b>				
<b>Problema/Pergunta</b> Iha Dezeñu husi ponte, elevasaun ba estrada leten ne'ebé hatudu. Oinsá ita tenke verifika elevasaun ne'ebé razoável?				
<b>Solusaun ká resposta ne'ebé hetan ona</b>				
<b>Solusaun/Resposta</b> Mais-menus pontu tolu mensiona iha-okos tenke ser verifika; 1) Kurva Vertikal ba elevasaun Estrada iha ponte lolon tenke konekta kabir ho assesu estrada? 2) Elevasaun husi Estrada lolon iha ponte altura/aas nataton duké ba assesu estrada. Kazu-kontráriu, dalaruma bele iha bee-nalibun iha Estrada klaran husi ponte hafoin udan. 3) Baze husi estrutura ponte tenke ser mais-menus metru ida altura/aas-liu duké altura nivel bee husi mota.				
Naran husi Enjiñeiru Senior ne'ebé konsulta ba		Mr. YYY		

## Anexu B3, Livru FAQ

### Livru FAQ

Sé mak hasoru problema ká perguntas, no hetan ona solusaun/respostas tenki tau rejistus hodi ajuda kolega sira ne'ebé bele hasoru problema hanesan iha futuru.

Naran husi Projetu		Ponte Tono		
<input type="checkbox"/> Estrada	<input checked="" type="checkbox"/> Ponte	<input type="checkbox"/> Irigasaun	<input type="checkbox"/> Portu	<input type="checkbox"/> sira seluk
Verifikasaun ba Dokumentus Tender		<input type="checkbox"/> Inspesasaun ba Pagamentu Provizóriu		
Naran	XXX	Data	04 Sept. 2013	
<b>Problemas ká Perguntas ne'ebé hasoru</b>				
<b>Problema/Perguntas</b>				
Sé iha métodu di'ak ruma ba revista besik-liu kustu konstrusaun husi ponte ida ne'ebé haruka tiha ona ba ADN hosi LM para verifikasaun ba Dokumentus Tenderizasaun?				
<b>Solusaun ká resposta ne'ebé hetan ona</b>				
<b>Solusaun/Resposta</b>				
Presu Unidade, total kustu konstrusaun desidi ba area Estrada lolon husi ponte, ba ponte Comoro fo'un mak liu duké \$8000 kada metru eskuadradu husi area Estrada lolon. Ne'e hare-hanesan karun hosi experiensia uluk nian.				
Ida-ne'e rekomenda katak ADN sei kolekta kustu unidade husi ponte sira, ho kustu unidade ida-ne'ebé husi ponte fo'un ida mak kompara ba no verifika karik ne'e la do'ok liu hosi dadus ne'ebé akumulá ona.				
Naran husi Enjiñeiru Senior ne'ebé konsulta ba			Mr. YYY	



## 2. Projeitu PDID

### 2.1 Evaluasaun Projeitu antes adjudikasaun Kontratu

#### 2.1.1 Fluxugrama




Figura 2-1. Fluxugrama ba Evaluasaun projeitu antes adjudikasaun kontratu

- (1) Identifikasaun projetu husi ESTATAL atu submete ba MoF  
Komunidade fo proposta ba ESTATAL halo identifikasaun ba projetu PDID. Depois de identifikasaun ESTATAL submete ba MoF (Divizaun planu orsamentu) atu tau hamutuk iha lista prijetu PDID.
- (2) Approvasaun Parliamentu  
MoF, (Divizaun Planu e Orsamentu) prepara hotu lista Projeitu no sei submete ba iha Parliamentu atu halo aprovasaun ba Projetu PDID II hodi implementa iha Distrito.
- (3) Verifikasaun Dezeñu no BoQ husi KDD  
KDD ho Konsultant Prepara dezeñu no BoQ hafoin submete mai ADN para halo verifikasaun ba volume, kustu no dezeñu. Verifikasaun hotu ADN submete direta ba iha KDD hodi prepara prosesu ba adjudikasaun
- (4) Rezultadu Verifikasaun.  
Rezultadu verifikasaun submete ba KDD ( Komisaun Dezenvolvimentu Distritu) ne'be atu prepara dokumentu kontratu no kontinua tuir adjudikasaun kontratu ho kontrator ba inisiu projetu.
- (5) Verifikasaun Dokumentus Kontratus husi ADN  
ADN (Eng. ADN iha Distritu) sei Verifika dokumentus kontratus no informa ba AND Nasional atu bele prepara CPV( pagamentu de kompromisu vale) hodi prosesu ba pagamentu adiantamentu 25 %.
- (6) ADN no MoF  
ADN prepara hotu CPV no PO ( orden kompara) atu submete ba MoF (Treasury) atu sira hare no MoF sei haruka ba BC (Bankun Central), BC halo pagamentu ba iha konta Bankaria kontrator nian ida-idak iha Banku.
- (7) Kontrator no AND  
Kontrator simu tiha orsamentu Adiantamentu husi banko sei hala'o konstrusaun tuir tempu nebe determina ona iha kontratu no ADN sei halo monitorizasaun no supervisaun ba Projetu PDD II.

### 2.1.2 Orario husi Obra

- (1) Presiza tempu ba verifikasaun iha ADN  
ADN tenke kompletu verifikasaun dokumentu ba pedidu pagamentu iha lora tolu 3 depois simu oficialmente husi KDD.
- (2) Tempu ba submisaun adisiona, halo submisaun fila fali ka resposta ba AND pergunta, KDD sei submete, submete fila fali ka resposta ba ADN iha semana ida (1) depois emisaun notisia husi ADN ne'ebé husu informasaun kontinuidade.
- (3) Iha kazu pontu (2) iha leten, tempu ba ADN atu halo kompletu verifikasaun sei ajusta ho KDD ne'ebé foti submisaun adisiona, halo submisaun fila fali ka resposta.

**2.1.3 Konfirmasaun ba Dokumentus ne'ebé submete ona:** ( aplikavel forneseменту bee mos ba area rurais )ADN sei verifika se dokumentus hotu ne'ebé presiza simu tiha ona. Karik iha buat falta, ADN sei informa KDD kona bá ne'e no intruza KDD atu submete iha tempu espesífika ona.

(1) Ezbosa Projetu prepara husi KDD

Ne'e informasaun baziku nebe nesesariu ba ADN nia verifikasaun.KDD sei prepara esbosu projetu, iha formatu -A no Formatu –B.

(2) Ezbosu Dokumentus Kontratu: ADN sei konfirma dokumentus hotu ne'ebé submete *ona, uza* Lista Verifikasaun-A

- 1) Projetu Adverstimentu
- 2) Kondisaun Kontratu
- 3) Dadus Kontratu
- 4) Kuantidade Projetudelei
- 5) Espesifikasaun Técnica
- 6) Dezeñu
- 7) Buat seluk ne'ebé se presiza

**2.1.4 Verifikasaun Técnica Utiliza Lista verifikasaun:** ( aplikavel ba setor forneseменту bee mos ba area rural)

AND sei verifika teknikamente dokumentus hotu BOQ, dezenu no espesifikasaun sira, usa lista verifikasaun B1 to B3 ba setor fonesementu bee moos ba rural.

Lista verifikasaun B1 no B3, prepara ona atu hare fila fali no kontrola konteudu espesifikasaun téknikau no BOQ repetivamente, husi pontu de vista enjeñeiru nian.

Nuudar orientasaun revizaun tuir padraun espesifiku tékniku nian, BOQ no dezeñu husi RWS (Fornese bee moos ba rural) atualmente iha DNSA nia mahon. lista verifikasaun ida ne'e sei hare fali bainhira kompletu ona.

Lista verifikasaun B3-1 to'o B3-2 relasiona ho aspetu planu no dezenu RWS.

Lista verifikasaun B3-1 Espesifikamente ba RWS depende ba tempu udan bee mota nian sai bee matan, enkuantu B3-2 ba sira nebe depende ba bomba liman ka posu nebe ke'e ho liman.

**2.1.5 Rona husi KDD**

ADN sei rona husi KDD oinsa atu foti solusaun ikus, iha liafuan seluk mesmu sira kompara ho alternativu seluk. Data no informasaun nebe presiza ba verifikasaun ezbosu dokumentu kontratu espesifika ona iha tablele formatu no lista verifikasaun iha leten.

### **2.1.6 Orario verifikasaun**

ADN sei verifika ezbosu dokumentus kontratu nian iha loron tolu (3) nia laran (3) loron servisu nian uza formatu A ba B no lista verifikasaun A ba C. Iha kazu ne'e se dokumentu submete la kompletu ka la tuir manual ADN nian, ADN sei foti prosedimentu nesesariu ba klarifikasaun inklui emisaun husi karta klarifikasaun, ka planu enkonrtu ida atu bele halo konfirmasaun ho KDD.

### **2.1.7 Remédiu/Reparasaun**

Iha kazu ne'e se hetan problema iha ezbosu dokumentus kontratus, ADN tenke informa ba KDD kona ba problema refere no oinsa hadi'ak. Prosesu sei atraza konforme verifikasaun nee

### **2.1.8 FAQ (Frequentamente/nafatin Husu perguntas)**

Iha kursu verifikasaun ezbosu dokumentu, enjiñeiru ADN sei hetan varius perguntas no problema sira. Perguntas no problema ne'e sei supera ho ajuda husi enjiñeiru senior sira. Ne'e dezejavel atu manten nafatin rejistu iha " Livru FAQ " husi enjiñeiru sira. Livru FAQ bele ajuda enjiñeiru seluk ne'ebe karik hetan problema hanesan.

## 2.2 Project Inspesaun ba pagamentu & Recomendasaun ba pagamentu

### 2.2.1 Fluxograma (Flow Chart)




Figure 2-2. Fluxograma ba pagamentu

#### (1) Pedidu Pagamentu Progresu Husi Kontrator

Kontrator halo pedidu pagamentu ba progresu liu husi KDD nebe sei submete ba ADN.

#### (2) ADN Halo Monitorizasaun

Kontrator husu pedidu pagamentu progresu ba KDD ne'ebe sei transfere ba ADN. Simu husi ADN, Enjiñeiru ADN monitór no inspesaun ba progresu servisu iha terrenu, no sei prepara verifica sertifikadu pagamentu ba progresu, bainhira verifikasaun razoavel ona no halo rekomendasaun ba ADN (finansas) atu prosesu pagamentu.

#### (3) ADN (Finansas ADN) Prepara CPV no Submete ba MoF

Engeñeiru ADN iha distritu submete karta rekomendasaun pagamentu progresu ba ADN Nasional, ADN (Finansas ADN) prepara CPV bazeia ba rekomendasaun husi ADN engeñeiru distritu no submete ba MoF (treasury).

#### (4) MoF Halo Pagamentu

MoF simu dokumentus husi ADN (Finansas ADN) bazeia ba pedidu Progresu husi kompañia no relatoriu husi enjeñeiru ADN iha distritu, MoF sei submete ba BPA no BPA sei selu ba kompañia tuir konta bankaria nebe kompañia iha.

#### (5) Kontinuasaun obra husi kontraaktor

Kontraaktor simu progresu pagamentu hosi Banku, ba kontuasaun husi obra. Durante periodu konstrusaun, ADN & KDD copera atu monitoriza no

superviziona ba obra.

(6) Submisaun ba pedido pagamentu progresu final husi kontraktor

Karik progresu fiziku husi konstrusaun atinzi to'o 100%,kontraktor sulisita pagamentu progresu final ba AND liu husi KDD enjeñeiruADN hala'o inspesaun terrenu ba verifikaasaun no rekomendasaun ba AND(finansa), ida-nebe sei perpara COV para prosesu pagamentu final.

(7) ADN & MoF

Bazeia ba pedidu husi kontraktor no rekomendasaun husi enjeñeiru ADN(Finansas ADN) prepara CPV submete ba MoF (Treasury) no prosesu ba Pagamentu final.

(8) Hand Over (Entrega Final)

Wainhira Konstrusaun atinji ona 100% no progresu pagamentu mós atinji ba 100%, maka facilidade tomak profesionalmente entrega ba projetu na'in (Owner).

(9) Retensaun

Karik iha defekta ka falyansu ruma nebe lahetan iha period nia laran husi fulan 3-6 depois konstrusaun entrega ba projetu na'in (Owner), kontraktor bele halo pedidu pagamentu retensaun ba KDD no KDD submete ba ADN hodi halo inspesaun ba tempu retensaun nian. Enjeñeiru AND prepara rekomendasaun ba pagamentu retensaun no submete ba AND(finansa).

(10) ADN Nasional Prepara CPV

Bazeia ba rekomendasaun husi enjeñeiru ADN iha distritu maka ADN Nasional (Finansas ADN) prepara CPV no submete ba MoF (Treasury) atu prosesu pagamentu retensaun ba kontraktor.

(11) Operasaun no Manutensaun

Projetu na'in(Owner) sei halo operasaun no manutensaun ba konstrusaun nebe kontrator entrega ona ba projetu na'in (Owner).

### 2.2.2 Oráriu Obra

(1) Presiza tempu ba verifikasaun iha AND

ADN sei halo kompletu verifikasaun dokumentu ba pedidu pagamentu iha loron sanulu (10), loron serbisu nian depois simu oficialmente dokumentus.

(2) Tempu ba submisaun adisiona, halo submisaun fila fali ka resposta ba ADN nia perguntas,KDD sei submete, submete fila fali ka resposta ba ADN iha loron sanulu(10), loron serbisu nian depois emisaun notísia husi ADN ne'ebé husu informasaun kontinuidade.

(3) Iha kazu pontu (2) iha leten, tempu ba ADN atu halo kompletu verifikasaun sei ajusta ho KDD ne'ebé foti submisaun adisiona, halo submisaun fila fali ka resposta.

### 2.2.3 Inspeasaun Dokumentus (Aplika ba setor Bee Moss iha Rural)

(1) Konfirmasaun ba Dokumentu sira nebe entrega ona: ADN sei verifika dokumentus hotu ne'ebé presiza simu tiha ona, uza lista verifikasaun-C. Karik iha buat falta, ADN sei informa KDD kona bá ne'e no intruza KDD atu entrega iha tempu nebe espesífika ona.

1)Karta pedidu pagamentu husi kontrator

- 2) karta pedidu verifikasaun husi KDD ba AND
  - 3) Parte dokumentus kontratu nian, hatudu montante kontratu no kondisun pagamentu
  - 4) Kuantidade Projetelelei hatudu unidade presu no kuantidade
  - 5) Relatoriu progresu hatudu progresu no planu servisu aktul no variasaun, progresu fotografia no dokumentus legal kontrator nian.
  - 6) Relatoriu inspesaun terenu husi KDD
  - 7) Sertifikadu lisensa ba negosiasaun no dividendu
  - 8) Dadus dijital husi BOQ nian
- (2) Konfirmasaun pagamentu kondisionál ba pagamentu avansadu no retensaun:  
 Inspetór ADN sei halo klaru kondisaun pagamentu uza ba kalkulasaun montante nebe atu selu konformidade ho deskrisaun dokumentu kontratu nian.
- (3) Kálkulu iha surat tahan fatura projetelelei.  
 Inspetór ADN refere ba BOQ iha dokumentus sira nebe entrega husi ESTATAL, no mos porsentu servisu kompletu nian iha periode ida nee. ezijensia husi kontrator iha fatura. No nia mos halo arkibu data bazeia ba medidas nebe iha ona no ninia inpesaun terenu, no kalkua kuantidade item ida-idak. Formula mak progresu x Total valor kontratu.
- (4) Konfirmasaun obra kompletu iha BOQ, dezeńu no figura  
 Inpetor ADN iha kooperasaun ho enjiñeiru KDD kompara fatura pedidu montante ne'ebe nia kalkula tiha ona iha inspesaun terenu. Iha kazu ne'e kalkulasaun montante la hanesan ho ida ne'ebe iha fatura laran, ADN sei bolu kontrator atu hatudu sezultadu kalkulasaun no fo ba nia oportunidade atu esplika tanbasa nia halo konkluzun ne'e too foti desizaun final.
- (5) Konfirmasaun orariu servisu  
 Inspetór ADN verifika relatoriu fulan kontrator nian no kompara progresu orariu planeada tiha ona ho oráriu aktual.

#### 2.2.4 Inspeasaun terenu (aplikável ba setor forneseamentu bee moos iha iha area rural)

- (1) Preparasaun
  - 1) Asisténsia  
 KDD sei konvida sira hotu tuir mai nee iha Inspeasaun terenu.
    - Inspetór husi ADN
    - Enjeñeiru husi KDD
    - Kontraktor
  - 2) Preparasaun  
 KDD sei konvida sira hotu tuir mai nee iha Inspeasaun terenu.
    - Rejistu Kualidade Kontrola
    - Dezeńu
    - Detalla Kuantidade Projetelelei
    - Medida Aparellu.
    - Asisténsia ba Medida
- (2) Kualidade Kontrolu  
 Rejistu Kualidade Kontrolu mak husi ADN atu hare fila fali uza *Lista Verifikasaun- D*. Verifika item, iha lista verifikasaun mostra ezemplu item

ne'ebe adekuadu depende ba situasaun.

(3) Medida Obra Kompletu

Objetivu ba medida mak atu konfirma kuantidade aktual ba kada item, kompletu hanesan ho kuantidade eziste fatura. Kuantidade servisu material, kompletu ho nia medidas, uza lista *verifikasaun-E*, item ne'ebe iha lista verifikasaun ezemplu deit, no sira sei troka ka depende ba item, iha tempu inspesaun nian.

(4) Rona husi enjeñeiru KDD

ADN sei rona husi KDD se bainhira presiza

(5) Remédiu

Karik iha kazu ruma ne'ebé ADN hetan nu'udár obra nia defeitu ka la satisfeito, ADN bele intruza atu remédiu.

(6) Relatóriu Inspesaun no Rekomendasaun

ADN sei prepara Relatóriu Inspesaun no Rekomendasaun  
Pagamentu ba MoF: *Formatu B*

### 2.2.5 Notifika iha Julgamentu kona-ba Pagamentu

Ikus liu ADN sei julga ba kuantidade pagamentu. Bazeia iha AND nia rekomendasaun, enjeñeiru ADN ( finansa) hasai notísia (CPV) ba MOF atu kompromisu ba fundu.

### 2.2.6 FAQ (Nafatin Husu Perguntas)

Iha kursu verifikasaun ezbosu dokumentu, enjeñeiru ADN sei hetan varius perguntas no problema sira. Perguntas no problema ne'e sei supera ho ajuda husi enjeñeiru senior sira. Ne'e dezejavel atu manten nafatin rejistu iha " Livru FAQ " husi enjeñeiru sira. Livru FAQ bele ajuda enjeñeiru seluk ne'ebe karik hetan problema hanesan.



Anex 2. (PDID)

Formatu-A (Rezumu Projeitu prepara husi LM)

<b>PDID</b>		<b>FIXA A</b>		Verifika Husi	Aprova Husi
Tipu Projeitu	Bee Moos	Objetivu	Hases/outline husi liru projeitu		
No. Kontratu/Projeitu			Data submisaun	_____, 201__	
Naran Projeitu/Fatin Konsultan			Etapa	Verification of Draft Contract Documents	
			Implementing Agency		
(Kondisaun Eziste)					
Númeru Uma Kain:					
Bee Matan Prinsipál:					
Fonte Rendimentu Prinsipál:					
Kondisaun Saúde:					
Karakteristika Markante seluk:					
(Planu Fornesimentu Bee)					
Tarjetu tinan:					
Bee Matan:					
Produsaun:					
Númeru Uma kain ne'ebe uza:					
Modelu Fornesimentu(Konesaun Uma no/Torneira Públiku):					
Unidade Konsuma Bee:					
Ezijénsia Bee iha Futuru:					
Modu de Konsume:					
Numeru Tanke.BTPs, Rezervat óriu ne'ebe Konstrui ona:					
Tranzmisaun Prinsipál nia naruk:					
Redi Distribuissau nia naruk:					
Númeru torneira públiku					
			(Óriariu Konstrusaun)		
Supervizór Husi:					
Kustu Projeitu:					
Períodu Konstrusaun:					
Exetua Data Hahu:					
Exetua data Kompletu :					
			(Kondisaun Kontratu)		
Exetua Data Anúnsiu					
Pagamentu Avansa (%):	_____%				
Retensaun (%):	_____%				
Ezamina Dokumentus husiADN:	Iha loron tolu (3) nia laran				
Resposta ka submisaun fila fall husi KDD/LM depois pedidu ofisiál:	Iha Semana ida(1)nia laran				
Verifika saun husi ADN depois resibu pagamentu:	Iha loron sanulu (10) loron serbisu nian				
Reply or resubmission by KDD/LM after receipt of official request:	Iha loron sanulu (10) loron serbisu nian				
(Ezbosu Projeitu)					

# Formatu -B (Relatoriu Inspesaun no Recomendasaun ba Pagamentu)



FIXA B

REPÚBLICA DEMOCRÁTICA DE TIMOR LESTE  
GABINETE DO PRIMEIRO MINISTRO  
AGENCIA DESENVOLVIMENTO NACIONAL

NO	RELATÓRIO	INSPECSAUN	NO	RECOMENDASAUN	BA	PAGAMENTO
1	Projecto	nia Naran				
2	Ministerio/Dono de Projecto					
3	Fontes de Fundos					
4	Contractor					
5	Numero PO (Purchase Order)				ÓÓ	
6	Localizasaun Projecto :	a. Distrito	:	Covalima		
		b. Sub distrito	:	Fatumea		
		c. Suco/Aldeia	:	Belulic Leten		
a	Valor Contracto		a	\$		180.000.00
b	Progreso fisico iha fulan kotuk		b			83.00%
c	Progreso fisico ate agora		c			90.00%
d	Valor Pagamento foer ate agora (gross)		(c-b)*a	\$		12,600.00
e	Osan adiantamento nebe simu ona .....%		...%*a	\$		-
f	Deducsaun adiantado ba pagamento tomak		e	\$		-
g	Deducsaun retensaun ba pagamento ida ne'e 10%		0.1*d			
h	Net pagamento depois de deducsaun ba retensaun		d-g	\$		12,600.00
i	Net pagamento nebe atu selu ba pagamento ida ne'e		h-f	\$		12,600.00
j	Total Net pagamento ate agora			\$		162.000.00
k	Balansu depois de pagamento ida ne'e		(100%-c)*a	\$		18,000.00
7	Observasaun ou komentario seluk : Bazeia ba inspesaun nebe ekipa ADN halo ba Projeito Konstrusaun Aqua potavel ho sistema solar panel Fatumea katak agora Projeito ne'e atinji ona 95 % ne duni ami rekomenda atu halo pagamento ba progresso fisiku 90 % nian.					
8	Recomendasaun ba Tezouro-MdF/Ministerio/Agencia Tutela Selu ho Montante (USD)					12,600.00
9	Observasaun :		SIM	Komentarios Ruma		LAE
a	Tuir Dezenho ?		✓			
b	Tuir BOQ ?		✓			
c	Tuir Espesifikasaun ?		✓			
d	Tuir Schedule curva S ?		✓			
e	Tuir Termos de Contracto ?		✓			
10	Data Inspeksaun		Data:	Fulan:		Tinan:
11	Engenheiro Nebe Halo Inspeksaun :	Assinatura:				Data :
	1. Naran : Lourdes Pereira	Assinatura:				Data :
	2. Naran : Manuel Martins					
	Verifikado Hosi :	Assinatura:				Data :
	Sônia Freitas Moreira					
12	Q.A	Assinatura:				Data :
	Esron St. Henuk					
13	Approvado Hosi :	Assinatura:				Data :
	Sr. Samuel Marçal Director Geral - ADN.					
14	Annexo :	Fotografias Ruma Hosi Terreno				

Lista Verifikasaun-A (Dokumentus Submetidu)

<b>PDID</b>		<b>LISTA VERIFIKASAUN A</b>		Verifika Husi	Aprova husi
Tipu Projetu	Bee Moos	Obejetivu	Dokumentus prezisa atu entrega		
No. Kontratu/ Projetu			Data submisaun	_____, 201____	
Naran Projetu			Etapa	Verifikasaun ba esbozu dokumentus kontratu	
<b>Ajénsia Implementasaun</b>					
Lista Material	Pontus Verifikasaun	Data verifikasaun	Marka	Informasaun	
	Ida nee atu konfirma katak dokumentus hotu entrega husi KDD			Razaun la entrega	
1	Anúnsiu Projetu				
2	Kondisaun kontratu				
3	Dadus Kontratu				
4	Kuantidade Projetudelei				
5	Espesifikasaun sira				
6	Dezeñu				
7	Buat seluk ne'ebé se prezisa				

Verifikasaun-B1to'o B3 ( Verifikasaun Téknika)

<b>LISTA VERIFIKASAUN B1</b>			Verifika Husi	Aprova Husi
<b>PDID</b>	Bee Moos			
Tipu Projetu	Objetivu	Especifikasaun Téniku		
No. Kontratu/Projetu		Data submissaun	_____, 201____	
Naran Projetu		<b>Etapa</b>	Verifikasaun ba esbozu dokumentus kontratu	
<b>Ajénsia implementasaun</b>				
<b>Lista Material</b>	<b>Pontus verifikasaun</b>			
<b>Finalidade no uza</b>	Espezifikasaun Projetu tenke kobretaka aspetu hotu serbisu sivi neebe nesesáriu ba implementasaun projetu .		Marka	Informasaun
<b>Kódigu no Padraun</b>	Padraun no Kódigu prátika neebe uza iha espefikasaun mak ida ne'ebe aseita internasionalmente ho ninia estadu fontes referensia ne'ebe klaru.			
<b>Naran no Abreviatura</b>	Naran no abreviatura husi ajénsia relevante, Komisaun sira, organizasaun no/ padraun neebe estipula iha espefikasaun téniku tenke atualiza atu bele resente nafatin (hafoun bei-beik).			
<b>Rezultadu peskija , Medidas no Teste</b>	Rezultadu husi peskija iha terenu, medidas no teste ezekusaun iha kursu dezeńu projetu, tenke aneksa iha dokumentus, atu kumpri ho garantia kualidade no kontrolu rekizitu neebe espefifika iha kondisaun géral kontratu nian.			
<b>Seguransa</b>	Serbisu hotu sei ezekuta ho di'ak atu bele kumpre rekizitu seguransa ne'ebe hakerek iha kontratu no regras espésifiku seguransa ne'ebe iha.			
<b>Asesu</b>	Asesu ba estrada tempórariu nee tão husi projetu fatin.			
<b>Kuadru Sinal</b>	Kuadru sinal sei fornese no hari tiha ona husi Kontratór, Kuadru sinal ida ne'e tenke adisional ba seguransa neebe deit no sai sinal avza.			
<b>Figura no Tabela</b>	Figura no tabela ne'ebe hatudu espefikasaun tékniku, tenke aneksa iha testu ka hatudu klaru sira nia fontes.			
<b>Rekizitu Ambiental</b>	Serbisu hotu tenke ezekuta atu bele kumpre rekizitu ambiental ne'ebe hakerek tiha ona iha rekizitu espefikasaun ambiental nian.			

<b>PDID</b>	<b>Lista Verifikasaun B2</b>			Verifika Husi	Aprova Husi
	<b>Tipu Projetu</b>	<b>Bee Mos</b>	<b>Objetivu</b>	Kuantidade selu nian(Bill of Quantity )	

<b>No. Kontratu/Projetu</b>		<b>Data submisaun</b>	_____, 201____		
<b>Naran Projetu</b>		<b>Etapu</b>	Verifikasaun ba esbozu dokumentus kontratu		
<b>Ajensia Implementasaun</b>					
<b>Lista material</b>	<b>Pontus Verifikasaun</b>	<b>Data Verifikasaun</b>	<b>Marka Verifikasaun</b>	<b>Informasaun</b>	
<b>Materiál servisu</b>	Iha BoQ nia laran halista material hirak nebee konaba konstrusaun Sivil no/ka materials nebee preziza hodi fasilita konstrusaun projetu nee, inklui mos mobilizasaun, preparasaun servisu , operasaun teste ho demolisaun(demolition)				
	Materia servisu tomak/refere kualidade ba klase espesifika materials nee, haforsa estandar/standards no conforme ba exigencias nee hatur iha espesifikasaun tekniku ka?				
<b>Kuantidade</b>	Nee kualidade Konstrusaun sivil nian, no materials bazeia iha dezeńu, sasukat no resultadu nian foo husi kontrator sira.				
<b>Presu Unidade</b>	Nee kualidade Konstrusaun sivil nian, no materials bazeia iha dezeńu, sasukat no resultadu nian foo husi kontrator sira.				

<b>PDID</b>			<b>LISTA VERIFIKASAUN B3-1</b>		Verifika husi	Aprova husi
Tipu projetu	Fornese bee -bee matan moris rasik/leio fluvial	Objetivu	Planu no Dezeñu			

<b>NO.kontratu/projetu</b>		<b>Date of Submission</b>	_____, 201____			
<b>Naran projetu</b>		<b>Stage</b>	Verifikasaun ba esbozu dokumentus kontratu			
<b>Ajénsia Implementasaun</b>						
<b>Lista Materai</b>	<b>Pontus verifikasaun</b>					
<b>Konseptu projetu</b>	Iha proposal projetu akordu nian laran ho estratejia Governu (rural no urban estratejia desenvolvimentu fornese bee)					
<b>Koordenasaun</b>	Halo koordenasaun tomak entre Ajénsias relevantes. data/informasaun avelabe(available), inklui: <input type="checkbox"/> presentí populasaun no uma kain, <input type="checkbox"/> fonte rendimentu, <input type="checkbox"/> historia desenvolvimentu konaba suku/sidade, <input type="checkbox"/> udan been?					
<b>Projetu Areal</b>	Hanesan iha areal sira afektu beibeik husi desaster naturalis. <input type="checkbox"/> bee sae ka <input type="checkbox"/> rai monu?					
<b>Projetu tarjet</b>	Tarjet ba tinan: _____ Número uma kain hodi servi ba: _____ Hanesan data avelabe(available)iha : <input type="checkbox"/> Saida mak bee matan agora da-dauk ba ema sira uza moris lor-loron nian? <input type="checkbox"/> Saida mak problema boot liu ba sira ( <input type="checkbox"/> kualidade, <input type="checkbox"/> kualidade, <input type="checkbox"/> distansia)? <input type="checkbox"/> Kondisaun saude ba ema sira nee mak saida? ( media(rate)mortalidade moras tanba bee)					
<b>kondisaun eziste</b>	Bee matan sufisienti iha kuantidade no kualidade? Kuantidade: _____ L/sec. Kualidade: <input type="checkbox"/> bee foe(turbid), <input type="checkbox"/> Bee la/foer(not turbid)					
<b>Planu bee matan</b>	Liu husi tinan-tinan produsaun estabel ? <input type="checkbox"/> los, <input type="checkbox"/> lae Nee aplika sistema graviti bee suli sai konaba transmisaun bee? <input type="checkbox"/> los, <input type="checkbox"/> lae Iha catchment area bee hu'un/matan sufisienti?: <input type="checkbox"/> los, <input type="checkbox"/> lae					
			Marka	Informasaun		
				Anexu: Projetu tarjet No.1		
				Anexu: Planu bee matan No.1 Planu bee matan No.2		
				Anexu: Planu bee matan No.3 Annex: Planu bee matan No.4		

<b>PDID</b>		<b>LISTA VERIFIKASAUN B3-1</b>		Verifika husi	Aprova husi
Tipu projetu	Fornese bee -bee matan moris rasik/leio fluyial	Objetivu	Planu no Dezeñu		

<b>N0.kontratu/projetu</b>	<b>Date of Submission</b>	_____, 201 ____			
<b>Naran projetu</b>	<b>Stage</b>	Verifikasaun ba esbozu dokumentus kontratu			
<b>Ajénsia Implementasaun</b>					
<b>Lista Materal</b>	<b>Pontus verifikasaun</b>	<b>Data verifikasaun</b>	<b>Marka</b>	<b>Informasaun</b>	
<b>Futuru bee mos</b>	<p>Fornese bee konaba via ema sira nia <input type="checkbox"/> torneira uma nian ka <input type="checkbox"/> torneirapubliku?</p> <p>Dezeñu valor komsumi bee per kapita kada loron : _____ L/c/d</p> <p>Kalkulasaun konaba bee mos ba futuru husi servi ba populasaun halo ka lae ? <input type="checkbox"/> los, <input type="checkbox"/> lae</p>			<p>AneXu: Bee mos ba futuru No.1</p> <p>AneXu: Bee mos ba futuru No.2</p> <p>AneXu: Bee mos ba futuru No.3</p>	
<b>Dezeñu kadoras</b>	<p>Kanu/kadoras bee sulji sai estimasaun ninian diametru uza formula no variabe( variables) ba distánsia, todan ho média sasuli <input type="checkbox"/> los, <input type="checkbox"/> lae</p> <p>Dezeñu bazeia ba survei iha terenu hydraulic profile aneXu. <input type="checkbox"/> los, <input type="checkbox"/> lae</p> <p>Hanesan kadoras asesores(accessories)balbu odamatan, balbu anin nian, dezeniu pr ó pria fase bee fakar sai(wash-outs) <input type="checkbox"/> los, <input type="checkbox"/> lae</p>			<p>AneXu: Dezeñu kadoras No.1</p> <p>AneXu: Dezeñu kadoras No.2</p> <p>AneXu: Dezeñu kadoras No.3</p>	
<b>Dezeñu reservador hodi servi</b>	<p>Materiál reservador ho <input type="checkbox"/> balbu inlet, <input type="checkbox"/> balbu outlet, <input type="checkbox"/> kanu dreinajen, <input type="checkbox"/> kanu bee suljisai (overflow) , <input type="checkbox"/> Anin kuak.</p> <p>Nele konkretu estruktura(structure) ho dezeñu simples bar reinformentu(reinforcement) : <input type="checkbox"/> los, <input type="checkbox"/> lae</p>			<p>AneXu: Dezeñu reservador hodi servi</p>	
<b>Torneira publiku</b>	<p>N úmeru konaba torneira materiál ba torneira: _____ torneira</p> <p>Numeru uma kain ne'ebe servi husi torneira ida: _____ uma kain</p> <p>Dezeñu própria hanesan apron konkretu apron : <input type="checkbox"/> los, <input type="checkbox"/> lae</p> <p>Materiál hanesann kanu bee i hodi halo dreinajen ba konkretu apron: <input type="checkbox"/> los, <input type="checkbox"/> lae</p>			<p>AneXu: Torneira publiku No.1</p>	

<b>PDID</b>			<b>LISTA VERIFIKASAUN B3-1</b>		Verifika husi	Aprova husi
Tipu projetu	Formese bee -bee matan moris rasik/leio fluvial	Objetivu	Planu no Dezeñu			

NO.kontratu/projetu	Date of Submission	Stage	Marka	Informasaun
<b>Naran projetu</b>	_____, 201____			
<b>Ajénsia Implemენტasaun</b>	Verifikasaun ba esbozu dokumentus kontratu			
<b>Lista Material</b>	<b>Pontus verifikasaun</b>			
<b>Operasaun &amp; manutensaun depois konstrusaun</b>	Ne'e planu komisaun uza bee hodi organiza iha suku/sidade: <input type="checkbox"/> los, <input type="checkbox"/> lae			
	Ne'e planu operasaun (hamos, kontrua balbu, etc.) prepara: <input type="checkbox"/> los, <input type="checkbox"/> lae			
	Sei hadia montante konaba osan selu bee nian ba O&M ne'ebe kolekta (collected) husi uma kain sira: US\$ _____ /fulan ida/uma kain			
<b>Ema sira nia konsiénsia</b>	Ema sira ne'e mos iha konsiénsia atu selu taxa konaba O&M: <input type="checkbox"/> los, <input type="checkbox"/> lae			
	Ema sira ne'e iha laran kaman hodi servisu: _____ sai uman kain ba _____ uma kain			



<b>PDID</b>	<b>LISTA VERIFIKASAUN B3-2</b>		Verifika husi	Aprova husi
Tipu Projetu	Fornese bee - bomba liman ka bee posu uza bomba liman	Objetivu	Planu no Dezerñu	

No. Kontratu/Projetu		Data submissaun	_____, 201____
Naran Projetu		<b>Etapa</b>	Inspesaun regular konaba pagamentu
<b>Ajénsia Implementasaun</b>			
<b>Lista material</b>	<b>Pontus verifikaun</b>	Marka verifikaun	<b>Informasaun</b>
<b>Konseptu projetu</b>	Iha proposal projetu akordu nian laran ho estratejia Governu (rural no urban estratejia desenvolvimento fornese bee)		
<b>koordinasaun</b>	Halo koordinasaun tomak entre Ajénsias relevantes.		
<b>Projetu areal</b>	data/informasaun avelabel(available), inklui: <input type="checkbox"/> presentí populasaun no uma kain, <input type="checkbox"/> fonte rendimentu, <input type="checkbox"/> historia desenvolvimento konaba suku/sidade, <input type="checkbox"/> udan been?		
<b>Projetu targetu</b>	Hanesan iha areal sira afektu beibeik husi desaster naturais. <input type="checkbox"/> bee sae ka <input type="checkbox"/> rai monu? Número uma kain hodi servi ba: _____		
<b>kondisaun eziste</b>	Hanesan data avelabel( available)iha : <input type="checkbox"/> Saida mak bee matan agora da-dauk ba ema sira uza moris lor-loron nian? <input type="checkbox"/> Saida mak problema boot liu ba sira ( <input type="checkbox"/> kuantidade, <input type="checkbox"/> kualidade, <input type="checkbox"/> distansia)? <input type="checkbox"/> Kondisaun saúde ba ema sira nee mak saida? ( media(rate)mortalidade moras tanba bee) <input type="checkbox"/> Iha areal, fasilidades sanitáriu, sentru saúde, ka klinik ne'ebe avelabel(available)? Dala ruma bomba liman bee posu ka konstrusaun fura bee planu besik iha projetu fatin. <input type="checkbox"/> yes, <input type="checkbox"/> no		
<b>Planu bee matan</b>	Karik data ne'e avelabel(available), produsaun sira nian mos estabel duranti tina-tinan? <input type="checkbox"/> los, <input type="checkbox"/> lae karik la'avelabel( available).Kondisaun topographical haleukonsidera mos katak diak konaba konstrusaun fura bee: <input type="checkbox"/> los, <input type="checkbox"/> lae bomba liman hanesan ba tipu: _____, halo iha: _____.		
<b>Operaun &amp; manuntesaun depois konstrusaun</b>	Nee planu komisaun uza bee hodi organiza iha suku/sidade: <input type="checkbox"/> los, <input type="checkbox"/> lae sei hadia montante konaba osan selu bee nian O&M ne'ebe kolekta( collected) husi uma kain sira: US\$ _____/fulan/uma kain		
<b>Ema sira nia konsiénsia</b>	Ema sira ne'e mos iha konsiénsia atu selu taxa konaba O&M: <input type="checkbox"/> los, <input type="checkbox"/> lae Ema sira ne'e iha laran kaman hodi servi/selu: _____ sai uman kain ba _____ uma kain		

Verifikasaun-C (Kondisaun pagamentu)



**REPÚBLICA DEMOCRÁTICA DE TIMOR LESTE**  
**GABINETE DO PRIMEIRO MINISTRO**  
**AGÊNCIA DE DESENVOLVIMENTO NACIONAL**  
**CHECKLIST FUNDU DA INFRA-ESTRUTURA BA PAGAMENTU**

**Naran husi Projetu** :  
**Naran husi Kompañia** :  
**Númeru Kontratu** :  
**Valor husi Kontratu** : US\$  
**Valor husi Invoice/Pedidu** : US\$

No	Dokumentus ne'ebé submetidu iha Invoice laran	Resultadu		OBS
		Sim	Lae	
1	Kontratu sei moris hela (mais menus fulan ida antes data prazu hotu/ expired date). Valor kontratu mak liu husi >500,000 tenke ser sujeitada hodi hetan Karta Justifikasaun husi Tribunal das Contas, Tribunal Superior das Administrativas de Timor Leste.			
2	Submete Sertidaun Dívidas ne'ebé válido no tenke ser legalizadu			
3	Submete No. TIN (Identificação do Contribuente Registo Imposto)			
4	Submite Para Quem Interessado ne'ebé válido			
5	Submete Licença Actividades de Comercio e Económico ne'ebé válido no legalizada			
6	Submete Invoice Orijinal 1 (kopia 5) no hetan aprovasaun husi Tékniku LM			
7	Pedidu husi Karta Pagamentu			
8	Sertifikadu Pagamentu aprovada husi Liñe Ministriais			
9	Númeru Konta Banária husi Kompañia			
10	Garantia ba Exekusaun di'ak tenke ser rai iha banku nu'udar garantia, ida-ne'e hanesan ho Valor Adiantadu ká bazea Termos husi Kontratu			
11	Invoice tenke ser anexada ho Relatóriu Progressu Mensal			
12	Kompañia Internacional tenke anexa sertifikadu hosi Organizaçao Padraun Internacional (ISO)			



REPÚBLICA DEMOCRÁTICA DE TIMOR LESTE

GABINETE DO PRIMEIRO MINISTRO

AGÊNCIA DE DESENVOLVIMENTO NACIONAL

CHECK LIST PAGUMENTU PDID

PAGUMENTU ADIANTAMENTU

N o.	Dokumentu Nia Naran	Kondisaun						Rema rks
		Iha	L a I h a	Kompl etu	La Kompletu	Los	La Los	
1	Pedidu Pagamentu husi kompanhia ba KDD(Original)							
2	Karta Emkamniamentu husi koordenador KDD (Original)							
3	Dokumentu Kontratu (Original)							
4	Foto copy dokumentu Licenca Para Actividade Economicas nabe sei moris, minimu to'o fulan 1 husi data hatama Pedidu Pagamentu (Legalizadu)							
5	Foto copy dokumentu Certidão de Dívidas nebe sei moris, minimu to'o fulan 1 fusi data hatama Pedidu Pagamentu (Legalizadu).							
6	Foto copy dokumentu TIN.							
7	Foto copy dokumentu Para Quem é Interdssado							
8	Foto copy Konta Bankaria kompanhia							
9	Foto copy Kartaun Eleitoral director kompanhia							



**REPÚBLICA DEMOCRÁTICA DE TIMOR-LESTE**  
**GABINETE DO PRIMEIRO MINISTRO**  
**AGÊNCIA DE DESENVOLVIMENTO NACIONAL**

CHECKLIST PAGAMENTU PDL/PDD/PDID

**PAGAMENTU RETENSAUN (10 %)**

N o	Dokumentu Nia Naran	Kondisaun						Remarks
		Iha	Ia Iha	Kompletu	Ia Kompletu	Lo s	Ia Lo s	
1	Pedidu Pagamentu husi kompanhia ba KDD (Original)							
2	Karta Enkarnihamentu husi koordenador KDD (Original)							
3	Foto copy Dokumentu kontratu/ sekarak projetu entrega wainhira kontratu mate ona, tangke aneksa ho dokumentu original ka foto copy emenda kontratu nebe validu minimu ate data entrega projetu .							
4	Certifikadu Pagamentu nebe preparadu husi Gastor Obras Publiku/ Tekniku KDD, Verifikadu husi ADN Distritu no aprovalu husi Koordenador KDD(original) – <b>ba pagamentu Projetu PDDII2012 no PDID deit</b>							
5	Termo Entregue de Projecto Final(original)							
6	Final Inspection Sheet ba retensaun(original)							
7	Foto copy Termo Entregue de Projecto Provisional/Primeiru							
8	Foto copy dokumentu Licenca Para Actividade Economicas nebe sei moris, minimu to’o fulan 1 husi data hatama Pedidu Pagamentu(Legalizadu)- <b>la aplika ba KIK</b>							
9	Foto copy dokumentu Certidão de Dívidas nebe sei moris, minimu to’o fulan 1 husi data hatama Pedidu Pagamentu (Legalizadu)- <b>la aplika ba KIK</b>							

1 0	Foto copy dokumentu Tin- <b>la aplika ba KIK</b>							
1 1	Foto copy dokumentu Para Quem é Interessado - <b>la aplika ba KIK</b>							
1 2	Foto copy konta Bankaria kompanhia							
1 3	Foto copy Kartaun Eleitoral director kompanhia							
1 4	Dokumentasaun (Fotografia tuir progressu fiziki)							
1 5	As built Drawing/Dezenho bazea ba rezultadu implementasaun <b>ba pagamentu Projetu PDID deit</b>							
1 6	Foto copy Dezenho no BOQ nebe aprova <b>-ba projetu PDD 2012 deit</b>							

Verifikasaun -D (Kontrolu Kualidade)

PDID		LISTA VERIFIKASAUN D		Verifika husi		Aprova husi	
				Formese bee	Objetivu	Kontrola kualidade	
NO. Kontratu/Projetu		Data submissaun		_____ , 201_____			
Naran projetu		Stage		Inspeksaun Regular konaba Pagamentu			
Naran Kontraktór		Ajénsia implementasaun					
Lista materiál		Pontus verifikasaun		Marka		Informasaun	
Technical dimensions		Are technical dimensions of all project facilities including tanks, reservoir, BPT, equipment, pipelines, fittings, etc. are in accordance with the technical specification and drawings?					
Materials		Are all materials new and of the kinds and qualities described in the Contract?					
Concrete		Is good quality cement used? Is stored cement randomly reweighed to check the quality?				Annex: Concrete No.1	
		Is best quality sand that contains no organic materials and less fine materials (dust) procured? Isn't sea beach sand used?				Annex: Concrete No.2	
		Does the aggregate (gravel) have no organic material in it? Isn't sea aggregate used? Is maximum allowable aggregate size 25mm?					
		Is slump test carried out? Is the slump between 70 to 90mm (Guideline CWSS)?				Annex: Concrete No.3	
		Is Hammer test conducted at representative parts of all concrete structure to confirm its strength in accordance with the Contract?					
Reinforcement Bars		Is steel for reinforcement of concrete a hot rolled deformed bar in accordance with internationally accepted standards? Are copies of test certificate provided to the Engineer?					
		Are all bars supplied in the straight form from the manufacturing plant?					
		Free of loose mill scale, rust, oil grease, mud or other materials.				Annex: Reinforcement bars No.1	

<b>PDID</b>	<b>LISTA VERIFIKASAUN D</b>			Verifika husi	Aprova husi
Tipu projetu	Fornese bee	Objetivu	Kontrola kualidade		

NO. Kontratu/Projetu	Naran Kontraktór	Pontus verifikasaun	Data submisaun	Marka	Informasaun
			Stage		
Naran Kontraktór		Ajénsia implementasaun			
Lista material					
Pipa/kanu no kadeli koneksaun nian( Fittings)		Hanesan material Kanu ne'ebe fo'o tuir akordu exigéncia espesifika ne'ebe iha kontratu laran? Kopia abrikantes sertifikadus fo'o Enjineiru hodi aprova ?			
		Kanu sira hotu tenke kompletu ho válvula komparta/ekluza, válvula kontrolu, válvula ár, fase liur, blokus konkretu tuir akordu ne'ebe iha kontratu?			Anexu: Kanu no kadeli koneksaun(Fittings) No. 1,
		Instelesaun hotu tiha , hanesan kanu hirak ne'e kokok(tested) presaun nian, detekta keta iha kuak ruma ba reparasaun ne'e no ( re-tested) kokok hikas kadoras			
Tanke sira		Hanesan Tanki sira hotu inklui reservador, BPTs, sedimentasaun tanki sira nian seluk-seluk tan, teste konaba kuak depois de konstrusaun?			
		Kanu inlet & válvula, kanu outlet & válvula, kanu bee suli sai liu, kanu ba dreinajén & vávula, anin kuak no kuak prinsipal nebe hanesan instelesaun lolos nian.			Anexu: Tanke sira No.1
Avental(Aprons) & dreinajén		Avental iha posu, tanke komunidadade no fontanárius la bele nakfera. Bee suli liu husi avental no suli tun ba ezgotu/kanu fo'er/baleta?			Anexu: Aventál(Apron) & dreinajén No.1

## Verifikasaun-E (Medisaun/sukat ba Obra Kompleta ona)

<b>PDID</b>				<b>Verifika Husi</b>	<b>Aprova Husi</b>
<b>LISTA VERIFIKASAUN E</b>					
Tipu Projetu	Bee Moos	Objetivu	Sasukat kona ba servisu kompletu		
<b>No. Kontratu/Projetu</b>			<b>Data submissaun</b>	_____, 201____	
<b>Naran Projetu</b>			<b>Etapa</b>	Inspesasaun konnaba pagamentu regular	
<b>Naran Kontrator</b>			<b>Ajensia Implementasaun</b>		
<b>Lista Material</b>		<b>Pontus Verifikasaun</b>	<b>Data Verifikasaun</b>	<b>Marka Verifikasaun</b>	<b>Informasaun</b>
<b>Tanke</b>	Tanke nia Medidas, Rezervatoriu no STPN, atu bele konfirma nia númeru, luan, naruk no aas				
<b>Kadoras</b>	Medida kanu nia naruk, husi fotorafia no medida ho roda				
<b>Kontrétu</b>	Númeru Saku Semente tenke bazeia ba dadus lójistika				
<b>Besi Reforsamentu</b>	Númeru bór reforsamentu bazeia ba dadus lójistika				




# 【Attachment1】 Aneksu ba Verifikasaun

Tarjetu ba projetu No.1

Tarjetu ba tinan: \_\_\_\_\_

## Tarjetu ba tinan(DEZEYNA PERIODO)

Iha komersial utiliza ho modelu, dezeyna normal ba periodo espasu naruk involve dekada(dasawarsa) ho nunez hahu ho modal/orsamentu nebe sai ho susesu atu habelar ho hetan rehabilitasaun rasional duni. Kona-ba atu utiliza bee uitoan , inkluindu mos ba nain sira husi governo lokal, nunez la haluan/hirak nee la prepara ho la'hetan iha kontestu husi populasaun rural ninia kapasidade atu selu. Ba razaun sira nee,dezeynu periodo ka horizontal ihaManual laran hakerek ona ba tinan 5 ka 10 . Iha faktu, dezeynu periodo hirak nee deside permanente husi agrementu nebe forte entre, implementasaun Agensia. Dezeynu periodo iha ona, planu finansial tenke hatama ba iha rekenin termus paket ho potensial ba kosumedores sirra' cakapabilidade ho pruntu presiza atu entre atu suporta selu hukas fali.(WB Manual)



TLRWSG by DENSA

Dezeyna periodo:tinan 10 (Minimum requirementus) , tinan 20 (Recommenda estandar)

	Vantagen	Desvantagen
<b>Tinan 5- dezeyna periodo</b>	Hahu selu nencik ona.	Presiza hafoun selu ba gastu dpois tinan (5) ba kapasidade atu hadi'an.
<b>tinan-sanulu dezeyna periodo</b>	Fasilidades sistema bee nec kapabilidade kona-ba ezezensia bee suli sai ba periodo naruk.	Hahu selu kustu nebe as.s.

Planu ba bee matan No.1

Bee matan suficiente quantidade ho qualidade?  
Quantidade: \_\_\_\_\_ L/sec,

## Sasukat quantidade kona-ba bee

Check kuantidade klimatiku tempu udan ho klimatiku tempu bai loron

### 1. Metodu Volumetrika

Determina yield(terbentur) kona-ba uza methodu volumetrika ba bee posu

#### Data:

- Volume of oil drum used : 200 liters
- Number of drums used : 1
- Time to fill the drum : 30 seconds

Required: Well yield


1. Calculate the total volume of water collected, V

$$V = \text{Volume of container used} = 200 \text{ liters}$$

2. Calculate the yield of well, Q

$$Q = \frac{\text{Volume of water collected}}{\text{time in seconds}} = \frac{200 \text{ l}}{30 \text{ s}} = 6.67 \text{ lps}$$

## 2. V-Indentasaun(takik) repreza



**Planu ba bee matan No.2**

**Nee bee matan suficiente in quantidade ho qualidade?**

**Qualidade:**  la'dun mos/keruh,  la'os la'dunmos

**Kualidade bee: Prioridade As (critical) Parametros**

Parametros
1. Microbiological : (Total Coliform, Fecal Coliform )
2. Bee foer/kekeruhan
3.Kor
4. pH
5.Besi
6. Manganese
7. Chloride
8. Arsenic
9. Cadmium/sejenis logam yang putih
10. Nitrate/sejenis garam
11. Sulfate/sulfat(garam asam belerang)
12.Total kahu'ur Solido (TDS)

TLRWSG husi DENSA

Kualidade bee ho pontu kelesaun bee nian

(Rekerementu Minimum)

La abu-abu, la iis, koko ka koris.

Bee tenke nono molok atu hemu.

Peskiza ba Sanitasaun nian halo kompletu ona nomos minimiza risiko balun.


(Standarte be Rekomendasaun)

Hasoru mos WHO hodi hetan orientasaun hanesa indikador husi governu

**Planu ba bee matan No.3**

**Nee graviti sistema aplika bee kon-ba transmisaun bee?**

sim,  não



**Planu ba bee matan No.4**

**Nee waduk areal suficiente kona-ba bee matan?**

sim,  não

**Baliza dataran pemisah(areal waduk)**



**Sa ida mak dataran pemisah?**

Ba definesaun, areal ida nebe iha dataran pemisah udan tau be-beik kolekta iha fatin neba hanesan bain-bain.Hanesan iha fatin bain-bain korente bee nian, debu, mota, etc.

Bee ulun kona-ba kona-ba mota uluk mak halo korente arus aliran air . Ba dataran pemisah haruka kona-ba korente aliran bee la'at tu'un tama ba kra'ik tanba primeiro mak bee bee korente nia suli diretamente.Bele mos bee origen rasik duni tu'un husi udan ben ka hanesan bee rai okoos bee posu bsa leten haktuir bee iha rai leten. Ba rai, tipe vegetasaun, tipe rai, rai lolon, microorganismes, pH, DO ( ka'ur Oxygen), ho temperatura hirak nee afeta bee iha dataran pemisah

As elevasi = kuntut garis bentuk 1800 ba bee Matan A, B and C.



**Areal waduk: B > C > A**

**Ezezensia bee mos nia future, No.1**


**Fornese bee mos ba komunidad liu husi via**

Tornera Uma kain ka tornera publik?

**Public tap or House connection**



**Domestic Water Quantity and Health**



**PONTO NEBE PERSIZA HANOIN:**

Iha kestaun ida katak tornera publiku sei konsumi husi vizinyu balun nebe lori husi tornera publiku ba iha sira nian uma,kestaun ne'e tenki halo husi ema ida. Husi se ? I to'o bain hira

**Ezezensia bee mos nia futuru No.2**

**Dezenya ba unidade bee nebe konsumedores sira uza per kapita ba loron ida nian: \_\_\_\_\_ L/c/d**

TLRWSG husi DENSA

Kuantidade bee	Rekerementu Minimum	Estandarti rekomenda nian
Umakain nia persiza:		
Hemu	2 litres per day	Litru 5 ba loron ida
Te'in	5 litres per day	15
fase	10 litres per day	20 litres per day
Haris	13 litres per day	20 litres per day
Total	Litru30 ba loron ida	Litru 60 ba loron ida

Individuals: 15-20 L.pcd (sustentabel ba fulan badak)  
 Hodi hemu 3-4 L.pcd  
 Perparasaun ba hahan, Hamos ka fase 2-3 L.pcd  
 Hygene personalidade nian 6-7 L.pcd  
 Fase ropa nian 4-6 L.pcd  
 Animal hakiak no agrikultura nian  
 Karau, kuda, kuda buru 20-30 kada litru  
 Bibi Timur, Bibi malae, fahi 10-20 kada litru  
 Manu, 10-20 kada litru 100  
 To'os hodi halo kantreru. 3-6 litres kada kuadradu.

Husi "Minimum Kuantidade bee nebe persiza ba iha umakan hodi uza"

WHO Regional Office for South-East Asia


**Ezezensia bee mos nia futuru No.3**

**Kalkulasaun ezezensia bee nia futuru halo husi populasaun sira ka lae?**  
 Los,  Lac

**Water Demand = Per capita water consumption × Population + NRW**

**Water Demand Projections = Water Demand at Targeted year**

example: Targeted year = after 10 years



**Water Demand for Design of Facilities**

Example: Community A

Households (HHs) = 100, average 1 HH = 6 persons

Total served Population = 100 × 6 = 600

Average Water demand = 600 × 50 lpcd = 30,000 l/d

NRW (Leakage ratio) = 15 %

Distributed amount including Leakage

= 30,000 l/d / (1 - 0.15) / 86400 sec/d = 0.41 l/sec

Maximum Water demand

= Average Water demand (including NRW) × 1.30


= 0.41 l/sec × 1.30 = 0.53 l/sec

**Dezenya instalasaun pipa No.1**

**Nee diametru estimasaun uza formula pipa bee suli ho varidade kona-ba distansia , as ho media bee suli ka?**  
 Los,  Lac

Pipa diametru tenki uza estimasaun formula pipa bee suli (hanesan Formula Hazen-Williamsho varidade kona-ba distansia, as ho media bee suli. Nunee,atu halo kalkulasan ba resultadu tenki ho nia ezemplo anexu, oinsa atu deside pipa diametru(D)kona-ba seksaun id-idak wainhira ba zeia ba beeulun(A iha nec), GL ba nodos, bee uitoan nebee suli sai husi nodus (konsume), pipa kle'an(L), koeffisiente ho bee suli(C<sub>HW</sub>) nebee fo. Ba razaun instalasaun pipa hydraulic-gradient (h/L) tenki asume..

Uza 'PIPECAL' ou 'EPANET'.




Nee exemplu kona-ba kalkulasaun ba resultadu

Node	GL(m)	Q(m³/sec)	W Head	Pipe size	d(mm)	L(m)	C	Qlow	HO(D)	WSS(m)
A	10	-	30.00	-	-	-	-	-	-	-
Node-1	10	25	26.0	A-N1	343.0	5000	110	95	4	4.0
Node-2	12	30	20.8	N1-N2	307.6	800	110	70	4	3.2
Node-3	8	20	22.8	N2-N3	248.7	500	110	40	4	2.0
Node-4	7	10	21.4	N3-N4	193.3	600	110	20	4	2.4
Node-5	5	5	20.6	N4-N5	146.9	700	110	10	4	2.8
To Down	-	5	-	N5-	-	-	-	5	-	-

Dezenya instalasaun pipa No.2


Dezenu hirak nec ba hydraulic bazeia profile iha kampu de trabalho anexu ka ?

Sim,  Não



Dezenya instalasaun pipa No.3

Hirak nec acesoris pipa hanesanas odan matan balvu, balvu anin, dezeyna ba prope duni ka fase soc sai ?  Sim,  Não




- A = Konstrusaun Intake
- B = Reservador
- C = kadoras
- D = Valvula hois anin sai
- E = Balvu ajuda anin

- HDL = Hydraulic fatuk musan
- G = Estatistika leten
- H = Sidade rural ou Suku
- I = Fabe balvu (id-idak 1.5 km)

Dezenya servi ba reservador No.1

Hirak nee acesoris pipa hanesan odan matan balvu, balvu anin, dezeyna ba prope duni ka fase soc sai?  Sim,  Não





Pontu revista

- a. Pipa bee tama  
Valvula odan matan nian
- b. Pipa bee sai  
Valvula odan matan nian
- c. Pipa bee resin/ suli sai  
ligasaun ho pipa baleta nian
- d. Pipa baleta  
Balbu odan matan nian, baleta/ saluran
- e. Anin fatin  
Screen Insetus
- f. ku'ak prinsipal  
g. Indikador level ba bee nian

Torneira publika No.1

Numeru kona-ba torneira ulun kompletu ho loke taka:  
Loke-taka

Numeru husi Uma kain nebe uza husi torneira ida.  
Uma kain



TLRWSG husi DENSA

Minimum requirements

200 metrus / mais ou minus 5 minutos

Por volta tempu be la'o.

Standarti Rekomenda nian

100 metrus



Maximum numeru servi ba populasaun

Kolekta pontus

requeremento maximun

populasaun 100

Rekomenda estandar

populasaun 50




**Torneira Publiku No.2**

Hirak nee propio duni ho dizaanya baiha konkreto nahe nian/ celemek?:

Los,  Lac

Bee dalan/drainpipe kompleta duni ho konkreta nahe nian:

Los,  Lac



**Konkreto No.1**

Semente nebe atu uza ne'e ho kulidade? Semente nebe rai,halo ona testu ba iha kulidade?

**Saku semeti ka Storing Bagged Cement**

1. Simenti iha saku laran nebe hatama iha karon nia laran tenke rai iha armazen,hodi prevene anin ka bokon nebe halo estraga sementi ,falun ho lona/terpal hodi hamenus sirkulasaun anin nian no is bokon nian husi bee matan.
2. Sementi nebe hatama ona iha saku laran tenki rai iha armazen, karik laiha armazen ,bele uza ai dalas hodi rai sementi no falun halo diak ho lona atu prevene bee ka udan been labale kona ba iha sementi
3. Hodi nune saku sementi nebe rai husi okasionalidade “ Pakote Armazen “kondisaun no rezultadu huis saku sementi ki'ik/klot. Retains husi semente se menti nian nee,kulidade no nebe normalmente halo no bele roling saku ninian nee iha rai leten.

**Konkretu No.2**

Semente nebe atu uza ne'e ho kulidade? Semente nebe rai,halo ona testu ba iha kulidade?


**Hetan hun/abut Aggregates ka Raihenek - Hasai ou haketak husi rai no tahu**

1. Rai no tahu mosu maka,as liu bele prova detekta husi tuir mai ne,e : Ense bee iha botir (1.14ru lit)erlenmeyer iha rai henek to'o nia klean 5.0cm(2 ince);
2. Aumenta bee iha botir ka termos to'o  $\frac{3}{4}$  no halo nakonu;
3. Doko botir ne'e durante menu tu ida ho ninia getaran to'o pontu nebe didika;
4. Mantein hela stik no pozisaun hari, to'o menu tu 30;
- 5 Observe ba iha raihenek ne'e karik liu husi 3,2mm ba ninia lapisan sedimental nian, hodi hetan raihenek ia simpel laran katak ne,e labele uza iha servisu konstrusaun nian, maibe Agregat hirak ne,e bele uza wainhira fase halo momos husi fo,er hirak nebe lao tuir iha rai henek laran.

**Konkretu No.3**

Hala'o ona kemerostan ou lae? Kemerostan nee entre 70 to 90mm (husi Guideline CWSS)?

*Notifikasaun minus liu husi frakeza katak nee liu husi waterproof wainhira halo ninia mistura.*



- Kahur nian nee tenke halo maran ba frakeza nian husi 0 – 25 mm hodi halo dalan/ konstrusaun dalan
- Abilidade servisu nian nebe kahur ba frakeza nian husi 10 – 40 mm nebe uja ba fundasi kaman iha reinforcement
- Mediu ba workability nian sei kahur tuir frakeza nian husi 50 – 90 mm nebe uja iha beton bertulag biasa
- Kakahur ba workability nia as ba frakeza nian ho getaran liu husi 100 mm.



**Bar Reinforcement nian No.1**


Livre husi eskalasaun nebe dulas hodi naklosu, ferujen, oli massa, tahu ka material sira seluk.

**Molok no durante fabrication of rebar's, Tenke inspesaun tuir:**

1. Mudah ka halakon ba feruziu hirak nee nebe relasaun ho materials. Iha feruziu balun ho skalasaun katak hamenus buat hirak nee wainhira parti bar nia nakleuk ou halos ho martelu no tenke hasai.
2. Karik feruziu makas liu iha bar nia hun, persiza atu husik iha fali ou lalika kontinua If the rust is firmly attached to the bar, it is recommended to leave it intact. This may improve the holding capacity of the bar and increase the bar-concrete bond.
3. Karik feruziu mosu makas liu tenke hamenus no liu husi area cross-sectional nian sikonfika katak bele redus no halo rezeta.
4. Hamenus/ halakon objeksionalidade hirak nee hodi ko'a hanesan/hamenu oli, bomba massa, hamaran tahu hodi didika ba besi tranka nian nebe nahe iha konkretu nia leten tanba bele indika ba iha konkretu nia leten hanesan bainbain.

**Pipa no Fitting No.1**

Material pipeline nian monta hamutuk ho sluice valvula, kontrola valvula, anin valvula, pusa sai anain/wash-outs, no blok nebe hada nee mentin tuir dadus dizaenya no kontratu?



NO.	DESCRIPTION	RECOMMENDED TYPES	NO.	DESCRIPTION	RECOMMENDED TYPES
1	Pump Discharge	Air/Vacuum for Pumps	9	Decrease Downslope	No Valve Required
2	Incr. Downslope	Combination	10	Low Point	No Valve Required
3	Low Point	No Valve Required	11	Long Ascent	Air/Vac or Combination
4	Increase Upslope	No Valve Required	12	Increase Upslope	No Valve Required
5	Decrease Upslope	Air/Vac or Combination	13	Decrease Upslope	Air/Vac or Combination
6	Beginning Horizontal	Combination	14	High Point	Combination
7	Horizontal	Air/Rel or Combination	15	Long Descent	Air Release or Combination
8	End Horizontal	Combination	16	Decrease Upslope	Air/Vac or Combination


## Lokasaun Valvula Anin iha pipa nia naruk

Valvula anin instala iha linya pipa nian atu eskuta anin no prevene ba iha vacuum nia kondisaun no hodi haforsa. Ba AWWA Steel Pipe nia manual hodi halo rekommenda, Valvula Anin tenke tuir pontu linya pipa nian.

1. **As pontu nian:** Kombinasau ho Valvula Anin
2. **Naruk Horizontal nian hodi Halai:** Hasai Anini ka Kombinasau Valvula iha 380 to 760 m ba ninia intervalu.
3. **Hamenus ninia Desentus:** Kombinasau Valvula iha 380 to 760 m ba ninia intervalu.
4. **Ascents nia naruk:** Anin/Vacuum Valvula iha 380 to 760 m ba ninia intervalau.
5. **Sasulin nia As:** Anin/Vacuum Valvula
6. **Sasulin nia minus:** Kombinasau ho valvula Anin

Husi "Theoria, Aplikasaun, no medida iha Valvula anin"  
(Val-Matic Valve and Manufacturing Corporation)


## Hametin kaixa Block & Anchors



THRUST BLOCKS and ANCHORS

**Tanki No.1**


Pipa Inlet & valvula, pipa outlet & valvula, pipa overflow , valeta & valvula, anin ventilasaun no tampaun matan/manhole hirak nee insatala diak .?



- (1) Inlet Pipe & Valve
- (2) Outlet Pipe & Valve
- (3) Overflow Pipe
- (4) Drain Pipe & Valve
- (5) Air Vent
- (6) Manhole
- (7) Water Level Indicator

**Apron & valeta bee dalan.1**


Kondisaun Apron dian diak, tanki komuidade no pipa hari la iha sinal ruma? Sasulin bee nia husi apron ne la'o tuir valeta?



**【Attachment 2】 Aneksu Verifikasaun**


**PDID EVALUASAUN Projetu Antes AjudikasaunKontratu**

**(1/5)**




## PDID Orario husi ba Verifikasaun

(2/5)




PDID Rekomendasaun ba Pagamentu ho Inpesaun ba pagamentu (1)

(3/5)




## PDID Rekomendasaun ba Pagamentu & Rekomendasaun ba pagamentu (2)

(4/5)



# PDID Horario ba Verifiasaan

(5/5)





### 3. Programa Eletrifikasaun Nasional

#### 3.1 Avaliasaun Projetu molok Adjudikasaun Kontratu

##### 3.1.1 Jeneralidade

Programa Eletrifikasaun Nasional maka hanaran (PEN) programa idane'e hanesan promosaun disséminasaun ba eletrifikasaun rurál ho méus estensaun distribusaun liña sira (20kV no 380V) ba nasional Timor Leste nian.

Dekretu-Lei Nú: 40/2012 5 Setembru<sup>1</sup> hatutan katak;

Dezenvolvimentu lokál no maioria aumenta kompañia iha distritu sira nebe promove ona liuhosi servisu ne'ebé sei rehabilita no instala distribuisaun liña sira hosi enerjia elétriku ho koñesementu no responsabilidade.

Programa Eletrifikasaun Nasional mak asaun ida urjente no essensiál hodi hasa'e ekonómiku, atu kria servisu no mós hasa'e kapasidade kompañia lokal sira nian. Aleindisu, implementasaun hosi programa sira hanesan iha tinan kotuk sei kapasita efetivu liután implementasaun husi Lei ida-ne'e.

“Artigu 1. Objetu” preeskreve katak;

1. Lei ida-ne'e regula prosedimentu espesiál ba adjudikasaun obra rehabilitasaun no instalasaun foun hosi distribuisaun liña sira hosi valór elétriku hosi U.S. \$ 100,000 to'o U.S. \$ 4, 500,000, maka hanaran Programa Electrificação Nacional (PEN).
2. Konsellu administrasaun nian hosi fundu infra-estrutura iha responsabilidade másimu ba PEN, no bele delega responsabilidade kon-ba administrasaun iha área eletrisidade nian no implementasaun hosi PEN ba membru governu nian ida.
3. Ajensia Dezenvolvimetu Nasional, (National Development Agency, ADN), ne'ebé iha koordenasaun diak ho Governu, nebe responsabiliza iha área elétriku nian hodi hala'o kontrolu no supervizaun implementasaun nian hosi PEN.

“Artigu 6. Komisaun Jestaun no Implementasaun” preeskreve katak;

Komisaun Jestaun no Implementasaun (depois hanaran “Komisaun

---

<sup>1</sup> Dekretu-Lei ida-ne'e deskrebe deit iha lian-Português no tradús tuir projetu JICA.

PEN”) konsiste husi:

1. Xefe ida husi Komisaun nebe hili husi membru Guvernu nian responsabiliza kona-ba área eletrisidade nian;
2. Representativu ida husi Komisaun Aprovizionamentu Nasionál, hanesan Sekretáridu;
3. Representativu ida husi Administrasaun Ministériu das Infra-estrutura;
4. Representativu ida husi MPS (Major Project Secretariat);
5. Representativu ida husi Departementu Prokuramentu EDTL;
6. Enjiñeru eletrisidade nain rua husi Guvernu rensponsabiliza ba área eletrisidade nian;
7. Representativu ida husi Departementu Finanzas EDTL nian;
8. Representativu ida husi sub-distritu iha ne’ebé projetu konsentra;

Responsabilidade no aktividade sira husi Komisaun PEN nebe hatudu iha baze husi Dekretu-Lei Nú. 40/20/2012 hanesan tuir mai ne’e.

1. Komisaun PEN aranza lista projetu sira nian hodi realizada
2. Komisaun PEN formula projetu no projetu publika atravesa jornal públiku
3. Komisaun PEN, no MPS hala’o engkontru hodi halo selesaun ba Kompañia. Komisaun PEN halo selesiona Kompañia ba projetu.
4. Komisaun PEN hala’o enkontru ho Kompañia selesionadu tuir orden atu hetan akordu ba termu husi kontratu.
5. Pedidu pagamentu sei submete ba Komisaun PEN.
6. Komisaun PEN no ADN hala’o verifikasaun ba progresu obra nian, no submete pedidu pagamentu ba MPS.

### 3.1.2 Fluxu Prosedimentu kona-ba Kualidade Sertifikasaun hosi dokumentus kontratu

Iha Dekretu-Lei Nú. 40/2012, Kualidade Sertifikasaun hosi dokumentus kontratu hosi ADN nebe spesífika hanesan parte ida hosi prosedimentu kona-ba selesaun hosi kompañia sira.

Fluxu Prosedimentu hodi atinje Kualidade Sertifikasaun molok asina kontratu nebe hatudu iha figura 3-1




Figure 0-1 Fluxu Prosedimentu ba Kualidade Sertifikasaun hosi Dokumentus Kontratu

### 3.1.3 Oráriu ba Emite Sertifikasaun Kualidade

#### (1) Oráriu baziku

Atinje Kualidades Sertifikasaun (rezultadu verifikasaun nian hosi dokumentus kontratu) antes asina kontratu tenke kompleta iha loron 10 nia laran depois de simu dokumentus suficiente maka hanesan iha fluxugrama iha Figura 3-2. (Kontratu tenke asina iha loron 8 nia laran depois atinje Kualidade Sertifikasaun).

#### (2) Konfirmasaun hosi dokumentus nesasáriu ba verifikasaun

Iha loron 4 depois de simu dokumentus husi Komisaun PEN, ADN tenke istrui ba Komisaun PEN atu submete dukumentus nebe falta iha karta no husu pergunta ba Komisaun PEN, karik iha.

#### (3) Verifikasaun ba dokumentus kontratu

Iha loron 10 depois husi simu dokumentus suficiente no responde ba ADN-nia perguntas husi Komisaun PEN, ADN tenke submete rezultadu verifikasaun nian iha hakerek. Karik rezultadu verifikasaun nian maka aprova, dukumen nebe submete hosi ADN sei konsidera hanesan atinje kualidade sertifikasaun hosi ADN.




Figura 0-2 Oráriu Atinje ba Kualidade Sertifikasaun

### 3.1.4 Verifikasaun ba Kualidade Sertifikasaun

#### (1) Dokumentus Nesesáriu atu submete ba Kualidade Sertifikasaun

ADN tenke izame dokumentus nebe konsentra ba verifikasaun and atinje Kualidade Sertifikasun. Dokumentus nesesáriu atu submete husi Komisaun PEN ba ADN hatudu iha kraik no ninia ponturevista hatudu iha anexa -3 hanesan “Checklist A”. Karik dokumentus husi Komisaun PEN la natoon, AND tenke instrui ba Komisaun PEN atu submete dokumentus natoon hodi uza “Formatu A-1”.

##### 1) Lista Projetu

- Prioridade kona-ba Implementasaun Projetu
- Informasaun kona-ba Sucos non eletrifikadu
- Informasaun kona-ba planu no liñas eziste

##### 2) Formulasau Projetu

- Justifikasaun kona-ba projetu
- Área obra nian
- Ezbosu husi Sucos nebe presiza eletridade
- Ezbosu husi Projetu

- Aproximadamente. Naruk husi distribuisaun liñas hosi 20kv no 380v
- Prospetiva loron komesa hala’o projetu
- Publisidade Projetu

### 3) Seleksaun Kompañia

- Justifikasaun Kompañia
- Minutu enkontru kona-ba selesaun
- Impostu Kompañia
- Lista kona-ba esperénsia obras nian hanesan ho uluk
- Lista enjiñerus nian iha Kompañia kona-ba obras

### 4) Dokumentus Kontratu

- Akordou Kontratu
- Kondisoins Jerál ho Dadus Kontratu
- Espesífikasaun tékniku
- Padraun Konstruksaun
- Dezeñu Projetu
- BoQ

## (2) Atinje Kualidade Sertifikasaun

Asina Kontratu tenke hala’o depois atinje Kualidade Sertifikasan husi ADN tuir Dikretu-Lei Nú.40/2012.

ADN tenke verifika items hirak ne’e ho inisiativu husi ezaminasaun ba dokumentus nesesáriu atu submete husi Komisaun PEN hodi uza anexa “Checklist A”.

The ADN tenke atenji resultadu husi verifikasaun dokumentus ba Komisaun PEN uza “Form A-2”.

## 3.2 Inspesaun Projetu & Rekomendasaun ba Pagamentu

### 3.2.1 Fluxu Prosedimentu ba Pagamentu

Fluxu Pagamentu husi PEN maka hatudu iha Figura 3-3 hanesan fluxugrama ida bazéia ba Dekritu-Lei Nú.40/2012.

Dekritu-Lei preeskreve katak;

Pedidu pagamentu husi conpanha submete ba Komisaun PEN. Depois de verifikasaun husi Komisaun PEN, ADN hala'o verifikasaun ba progressu obras no submete pedidu rekomendasaun ba pagamentu ba MPS.




Figura 3-3 Fluxu Pagamentu ba PEN

### 3.2.2 Oráriu Verifikasaun ba Pagamentu

#### (1) Oráriu Baziku

Verifikasaun ba Pagamentu tenke kompleta iha loron 10 nia laran depois simu dokumentus sufsiente hanesan hatudu iha fluxograma iha Figura 3-4 iha kraik ne'e. Durasaun ba loron hatudu iha data deadline nian.




Figure 3-4 Oráriu Verifikasaun ba Pagamentu

#### (2) Kofirmasaun hosi dokumentus nesesáriu ba verifikasaun

Iha loron 4 nia laran depois simu Sertifikadu ba Pagamentu husi Komisaun PEN, ADN tenke instrui ba Komisaun PEN atu submete dokumentus nebe mak falta iha hakerek no husu pergunta ba Komisaun PEN, karik iha.

#### (3) Dokumentu inspesaun no fatin inspesaun

Iha loron 7 depois simu dokumentus sufsiente no resposta husi

Komisaun PEN, ADN tenke tún ba fatin Inspesaun, karik nesesáriu, ho koodenasaun loron ba vizita terrenu ho Komisaun PEN iha orden atu rona tuir no fó instrusaun.

#### (4) Atinje rekomendasaun pagamentu

Iha loron 10 nia laran depois simu dokumentus suficiente no resposta ba ADN-nia pergunta husi Komisaun PEN, ADN tenke atinje rekomendasaun pagamentu kona-ba verifikasaun ba MPS iha MOF.

#### 3.2.3 Dokumentus Nesesáriu atu submete husi Komisaun PEN

Relatoriu inspesaun husi Komisaun PEN tenke submete ba ADN depois de verifikasaun husi Komisaun PEN ba pagamentu.

Relatoriu ba pedidu pagamentu interim pagamentu tenke inklui tuirmai ne'e:

- “Sumariu Verifikasaun ba Pedidu Pagamentu husi Komisaun PEN”
- ”Dokumentus kompañia nian ho Asinatura Hakerek fila fali husi Komisaun PEN iha Kada Pajina”
- “Resultadu ba supervisaun husi Komisaun PEN”

Relatoriu ba Pedidu Pagamentu husi Provizional Handover tenke inklui adesaun tuirmai.

- “Resultadu Teste Funsional ho kriteria”

Relatoriu pedidu ba Pagamentu Final Handover tenke inklui adesaun tuirmai.

- “Relatoriu ba operasaun no manutensaun”

ADN tenke prova katak relatoriu inspesaun husi Komisaun PEN inklui itens suficiente ba verifikasaun. Formatu ba sumariu relatoriu inspesaun nian husi Komisaun PEN nebe hatudu iha Anexa-3 hanesan “Formatu B” no no nesesáriu itens iha relatoriu ne'e hatudu iha Anexa-3 hanesan “Checklist B-1~3”.



### 3.2.4 Dokumentu Inspeksaun

#### (1) Jeneralidade

Komisaun PEN tenke submete sira-nia relatoriu hanesan sira-nia rezultadu ba verifikasaun. Relatoriu ida-ne'e tenke inklui Kompañia-nia relatoriu ho asinatura hakerek husi Komisaun PEN.

Verifikasaun husi ADN tenke hahu husi inspesaun dokumentu bainhira relatoriu husi Komisaun PEN ho nesesáriu items to'o iha ADN.

#### (2) Inspesaun ba Pagamentu Interim

Verifikasaun ba pedidu pagamentu interim dala ruma hala'o deit ba Dokumentu Inspesaun karik iha markante problemas nebe deskoñesidu. Iha tempu inspeksaun terrenu ba pagamentu interim hala'o, tenke iha razaun loloos no mensiona iha relatoriu inspesaun.

Verifikasaun Items ho razaun atu implementa ba inspesaun terrenu ba pagamentu interim maka hanesan tuir mai ne'e.

1. Valor nebe bo'ot (karik liu husi 100,000 USD) husi fatura kada pagamentu interim
2. Relatoriu husi Komisaun PEN sei la suficiente atu verifka kuantidades.

Verifikasaun ba pedidu pagamentu interim tenke ezame importante ba kalkulasiun husi fatura ho kondisoens pagamentu no kuantidades aproximadamente husi kompletasaun ba obras.

Ezaminasaun tenke fukus ba importante tékniku items nebe route ba liña tenke koresponde dezeńu ka tipu fundasaun ba ai-rin tenke hasoru rekerementu ba spesifikasaun tékniku nst

Items nesesáriu ba verifkasaun tenke inklui iha relatoriu Komisaun PEN nian maka hanesan tuirmai no checklist nebe hatudu iha anexada-3 hanesan "ChecklistB-1".

3. Rezumu verifikasaun ba pedidu pagamentu husi Komisaun PEN
4. Revizaun ba Obras no investigasaun detalla relasiona jeográfika no aspetu jeolójika
5. Dokumentus Kompañia nian ho asinatura hakerek husi Komisaun PEN iha kada pájina
6. Resultadu ba supervisaun husi Komisaun
7. Dadus digitál husi fatura iha pedidu pagamentu

### (3) Inspeksaun pagamentu ba Provisional Handover

Nesesáriu items ba verifikasaun tenke inklui iha relatoriu husi Komisaun PEN hanesan tuirmai ne'e. Checklist ba verifikasaun anexa-3 hanesan "Checklist B-2" no checklist ba inspeksaun tékniku nebe hatudu iha "Checklist C" ho inklui "Guideline of Technical Inspection for Distribution Line".

Inspesaun tenke fokus ba dokumentus husi Komisaun PEN atu nune'e kompleta servisu obra no mós ba remediun ba defeitus.

8. Rezumu husi verifikasaun ba pedidu pagamentu husi Komisaun PEN
9. Revizaun ba obras no investigasaun detalla relasiona jeográfika no aspetu jeolójika
10. Dokumentus kompañia nian tenke hetan asinatura hakerek husi Komisaun PEN iha kada pájina
11. Rezultadu ba Supervisaun husi Komisaun PEN
12. Rezultadu Funsionál Teste no sukat ho kriteria
13. Dadus digital husi fatura iha pedidu pagamentu

### (4) Inspesaun ba Pagamentu Final Handover

Items nesesáriu para verifika tenke inklui iha relatoriu Komisaun PEN hanesan tuirmai ne'e. Checklist ba verifikasaun nebe hatudu iha Anexa-3 hanesan "Checklist B-3" no checklist ba inspesaun tékniku nebe hatudu iha "Checklist C" ho "Guideline of Technical Inspection for Distribution Line".

Inspeksaun tenke fokus ba dokumentus husi Komisaun PEN kona-ba obra kompletu no mós ba remediun ba defetus.

- a. Rezumu verifikasaun ba pedidu pagamentu husi Komisaun PEN
- b. Revizaun ba obra no investigasaun detalla relasiona jeográfika no aspektu jeolójika
- c. Dokumentus kompañia ho asinatura hakerek husi Komisaun PEN iha kada pájina
- d. Relatoriu husi operasaun no manutensaun
- e. Dadus digital husi fatura iha pedidu pagamentu

### 3.2.5 Inspeksaun terrenu

#### (1) Jeneralidade

Verifikasaun ba pedidu pagamentu ba Provizionál no Final Handover tenke hala'o iha ispesaun terrenu depois inspesaun ba dokumentus.

Implementasaun koreta no efisien husi inspesaun tékniku iha konkluziun fiziku husi obra, Provizionál no Final Handover, tenke realizada bazcia ba “Checklist C” nebe hatudu iha Anexa-3 “Guideline of Technical Inspection for Distribution Line”.

#### (2) Preparasaun

Verifika Items hanesan tuir mai ne'e.

- a. Preparasaun ba tempu oráriu kona-ba fatin vizita
- b. Koordensaun ho Komisaun PEN-nia atendentu iha fatin vizita
- c. Husu xefe Komisaun PEN atraveza karta hakerek cc ba MPS, karik laiha atendentu husi Komisaun PEN
- d. Selesaun ba investigasaun items/komponentes iha BoQ, hanesan komponentes importante atu funksiona no no kuantidade items nebe mak boot

#### (3) Atividades iha terrenu

Verifika Items ba atividades iha terrenu para inspesaun hanesan hatudu tuirmai ne'e.

- a. Outline husi komponentes kompletu
- b. Kuantidades kompletu husi mediasaun lokál
  - Diferente entre valór kompletu loloos no hirak ne'e iha BoQ
- c. Kualidade materiais no instalasoens
  - Referesia ba “Checklist C” no “Guideline of Technical Inspection for Distribution Line”
  - Resultadu Teste husi Komisaun PEN tuir kriteria
- d. Aspectu seluk tan
  - Oráriu husi Obras
  - Atividades Konstrusaun
  - Situasaun husi Benifisiarius
  - Problemas entre viziñus, etc.

### 3.2.6 Evaliasaun no Relatóriu

Depois implementasaun hosi inspesaun no evaluasaun ba obras kompletu, “rekomendasaun ba pagamentu” no “rekomendasaun ba remediu” ba defeitus husi obras nian, karik iha, tenke hato’o liuhosi karta ba MPS ho lais.

Prosedimentu husi submisaun ba relatoriu hanesan hatudu tuirmai ne’e.

- 1) Inspetur husi ADN tenke verifika Pedidu Pagamentu relasiona ba dokumentus no inspesaun ba terrenu. Rekomendasaun ba pagamentu nebe hato’o utiliza “**Formatu C**” nebe hatudu iha Anexa-3.
- 2) Karik ADN la simu dokumentus suficiente no resposta husi Komissaun iha loraon razuavel nia laran (karik semana 1) AND tenke hato’o verifikasaun defetivu husi Komisaun PEN ba MPS.
- 3) Karik iha defeitus ruman husi obras nebe observa hela, rekomendasaun ba remediu tenke instrui ba Komisaun PEN no Kompañia ho hakerek. ADN tenke hetan asinatura husi parte rua iha anexa “**Formatu D-1**”, “**Formatu D -2**” no “**Formatu D-3**”.

Rekomendasaun ba pagamentu ne’ebé inklui redusaun ba pedidu pagamentu ka pending ba loraon pagamentu atu bele hein ba koresaun ba defeitus husi kompañia, tenke hato’o ba iha MPS.

### Anexa-3 (Programa Eletrifikasaun Nasionál)

Iha Anexa ida-ne'e, formatus no checklists nebe uza iha obra deskrebe iha'3. Programa Eletrifikasaun Nasionál' nebe hatudu.

Relasaun entre formatus/checklists no tempu uza sira hatudu iha tabela tuirmai.

Tabela Anexa-3-1 formatus/checklists no sira-nia tempu utilizaun

Formatus/Checklist	Tempu Utilizaun	Utilizadór
Formatu A-1	Atinje rezultadu konfirmasaun dokumentus ba kualidade verifikasaun hosi kontratu	ADN
Formatu A-2	Atinje rezultadu verifikasaun ba kualidade sertifikasaun hosi kontratu	ADN
Formatu B	Atinje Sertifikadu ba Pagamentu	PEN/C
Formatu C	Atinje rekomendasaun ba pagamentu	ADN
Formatu D-1	Atinje rekomendasaun ba pagamentu interim	ADN
Formatu D-2	Atinje rekomendasaun ba pagamentu provisional	ADN
Formatu D-3	Atinje rekomendasaun ba pagamentu final	ADN
Checklist A	- Konfirmasaun dokumentus ba kualidade verifikasaun hosi kontratu - Verifikasaun ba kualidade sertifikasaun hosi kontratu	ADN
Checklist B-1	Atinje sertifikadu ba pagamentu interim	PEN/C
Checklist B-2	Atinje sertifikadu ba pagamentu provisional	PEN/C
Checklist B-3	Atinje sertifikadu ba pagamentu final	PEN/C
Checklist C	Fatin inspesaun / Inspeasaun terrenu	ADN

PEN/C : Komisaun PEN

Anexada, 'Guideline of Technical Inspection for Distribution Line' ne'e ba utilizaun inspesaun tékniku 'Checklist C'.

Formatu A-1 (Konfirmasaun ba Pedidu Pagamentu husi Komissaun PEN)



REPUBLICA DEMOCRATICA DE TIMOR LESTE  
GABINETE DO PRIMEIRO MINISTRO  
AGÊNCIA DE DESENVOLVIMENTO NACIONAL

Formatu A-1

Data : 25 de Outubro, 2012

Hato'o Ba : Sr. Kassius Klei  
                  Chefe Komisaun Jestaun no Implementasaun - PEN  
Hosi : Sr. Samuel Marcal  
                  Diretor Geral da Agencia de Desenvolvimento Nacional  
CC : S.E. Januario da Costa Pereira  
                  Secretario de Estado da Electricidade  
Ref : \_\_\_\_\_RDTL/GPM/ADN/X/2012

**Assunto : Nessesariu Dokumentus atu Submete husi Komisaun PEN**

Ho Respeitu,

Bazeia ba Decretu lei Agência Desenvolvementu Nacional (ADN) No. 11/2011 nomos Decretu Lei No. 40/2012 Programa Eletrificação Nacional (PEN) nebe fo papel ba ADN nudar quality control & auditing ba projetu hotu-hotu nebe financia husi osamento estado. Ho nune ekipa halao tiha ona prosesu Komfirmasaun ba dokumentus hirak nebe ita submete husi Comissao de Gestao e Implementacao ba ADN

Resultadu ba komfirmasaun ba nessesariu dokumentus atu submete hatudu tuir mai ne'e ho resultadu husi Checklist A (Aneksu):

Naran Projetu : \_\_\_\_\_  
Fatin Projetu : \_\_\_\_\_  
Naran Companha : \_\_\_\_\_  
Tipu Verifikasaun : 1. Lista Projetu   
                          2. Formulasaun Projetu   
                          3. Seleksaun Companha   
                          4. Documentus Contratu

Resultado komfirmasaun Documentus : APROVA/APROVA HO NOTA/PENDENTE/REZEITA

<b><u>RECOMENDASAUN ADN</u></b>
---------------------------------

Mak ne'e deit ba ita boot nia atensaun no kolaborasaun diak ami hatu'o Obrigado Wain.

Formatu A-2 (Verifikasaun ba Pedidu Pagamentu husi Komisaun PEN)



REPUBLICA DEMOCRATICA DE TIMOR LESTE  
GABINETE DO PRIMEIRO MINISTRO  
AGÊNCIA DE DESENVOLVIMENTO NACIONAL

Formatu A-2

Data : 25 de Outubro, 2012

Hato'o Ba : Sr. Kassius Klei  
                  Chefe Komisaun Jestaun no Implementasaun - PEN  
Hosi : Sr. Samuel Marcal  
          Diretor Geral da Agencia de Desenvolvimento Nacional  
CC : S.E. Januario da Costa Pereira  
          Secretario de Estado da Electricidade  
Ref : \_\_\_\_\_RDTL/GPM/ADN/X/2012

**Assunto : Resultado Verifikasaun Dokumentus Projetu PEN**

Ho Respeitu,

Bazeia ba Decretu lei Agência Desenvolvementu Nacional (ADN) No. 11/2011 nomos Decretu Lei No. 40/2012 Programa Eletrificação Nacional (PEN) nebe fo papel ba ADN nudar quality control & auditing ba projetu hotu-hotu nebe financia husi osamento estado. Ho nune ekipa halao tiha ona prosesu verifikasaun ba dokumentus hirak nebe ita submete husi Comissao de Gestao e Implementacao ba ADN Resultado verifikasaun ba dokumentus mak tuirmai ne'e ho resultado iha Checklist 1 (Aneksu):

Naran Projetu : \_\_\_\_\_  
Fatin Projetu : \_\_\_\_\_  
Naran Companha : \_\_\_\_\_  
Tipu Verifikasaun : 1. Lista Projetu   
                          2. Formulasaun Projetu   
                          3. Seleksaun Companha   
                          4. Documentus Contratu

Resultado Verifikasaun Documentus : APROVA/APROVA HO NOTA/PENDENTE/REZEITA

<b><u>RECOMENDASAUN ADN</u></b>
---------------------------------

Mak ne'e deit ba ita boot nia atensaun no kolaborasaun diak ami hato'o Obrigado Wain.

## Formatu-B (Rekomendasaun ba Pagamentu hosi Komisaun PEN)

### Verifikasaun ba Pedidu Pagamentu husi Comisaun

Formatu B

1	Naran Projeitu		
2	Tipu Prejetu <i>Programa Eletrifikasaun Nacional</i>		
3	Numeru PO (Purchase Order)		
4	Naran Kontratour		
5	Tipu Pedidu Pagamentu <i>Pagamentu Interem (First, Second, Third), Provisional Handover, Final Handover</i>		
6	Orariu husi Obra <i>Loron Hahu: Intended Completion day Delet Library Period</i>		
7	Kondisoins Pagamentu <i>Pagamentu Adiantadu ( %), Retensaan ( %), Prapagu ba retensaan ( % iha loron Kompletasaun), etc.</i>		
8	Fatin Projeitu	District & Sub-district Village/Hamlet	
9	Valor husi Kontratu		\$ 1,000,000.00
10	Brutu Pagamentu to agora		\$ 500,000.00
11	Fatura iha invoice husi Kontratour		\$ 200,000.00
12	Fatura Verifikadu husi Inspetour		\$ 100,000.00
13	Pagamentu adiantadu : ( 10 % ) husi valor Kontratu	$(9) \times 10\%$	\$ 100,000.00
14	Redusaun ba Pagamentu adiantadu	$(13) \times (12) / (9)$	\$ 10,000.00
15	Redusaun ba Retensaan ( 10 % )	$(12) \times 10\%$	\$ 10,000.00
16	Pagamentu depois husi Redusaun	$(12) - (14) - (15)$	\$
17	Release ba Retensaan anterior		\$
18	Pagamentu ba fulan ida ne'e	$(14) + (15)$	#VALUE!
19	Balanse depois husi Pagamentu	$(9) - (10) - (18)$	#VALUE!
20	Progressu ba Pagamentu anterior (%)	$(10) / (9)$	50%
21	Progress for this payment (%)	$(12) / (9)$	10%
22	Inspesau ba Dokumentus	Dokumentus	Problemas ruman & Comentariu
a	Dokumentus Kontratu	Sim/Nao	
b	BOQ husi Kuantidades Kompletu	Sim/Nao	
c	As-built Drawing iha Handover	Sim/Nao	
d	Programa Orariu husi Obra	Sim/Nao	
e	Resultadu testu ba handover	Sim/Nao	
f	Relatoriu Inspesau	Sim/Nao	
g	Fotografia husi obra kompletu/protu	Sim/Nao	
24	Resultadu Inspesau husi EBYL		
	[ Resultadu husi Inspesau Dokumentus ]		
	[ Resultadu husi Inspesau iha Terrenu ]		
	[ Julgamentu ba Pagamentu ]		
25	Proposta Pedidu Pagamentu husi Kontratour		
26	Rekomendasaun ba Pagamentu #VALUE!		
27	Loron Inspesau ba Terrenu	Data:	Fulan: Tinan:
28	Inspetour	Asinatura:	Data:
		Asinatura:	Data:
29	Verifika husi	Asinatura:	Data:
30	Approva husi	Asinatura:	Data:



## Formatu-C (Relatoriu Inspesaun no Rekomendasaun ba Pagamentu)



AGÊNCIA DE DESENVOLVIMENTO NACIONAL  
GABINETE DO PRIMEIRO MINISTRO  
REPÚBLICA DEMOCRÁTICA DE TIMOR-LESTE

Formatu C

RELATORIU INSPESAUN NO REKOMENDASAUN BA PAGAMENTU				
1	Naran Prozetu			
2	Tipu Prozetu	Programa Elektrifikasaun Nasional		
3	Numeru PO (Purchase Order)			
4	Naran Kontratour			
5	Tipu Pedidu Pagamentu	Pagamentu Interim (First, Second, Third), Provisional Handover, Final Handover		
6	Orariu husi Obra	Loron Komesa:	Pretendidu loron Kompletu	Defect Library Period:
7	Kondisoins Pagamentu	Advance payment ( %), Retention ( %), Repay of Retention ( % at Completion day), etc.		
8	Fatin Prozetu	Distritu & Sub-distritu		
		Suco/Aldeia		
9	Presu Kontratu			\$ 1,000,000.00
10	Pagamentu Brutu to agora			\$ 500,000.00
11	Fatura iha Invoice husi Kontratour			\$ 200,000.00
12	Fatura ne'be verifika ona husi inspetur			\$ 100,000.00
13	Pagamentu Adiantadu: ( 10 %) Valor Kontratu		$(9) \times 10\%$	\$ 100,000.00
14	Redusaun ba Pagamentu Adiantadu		$(13) \times ((12) / (9))$	\$ 10,000.00
15	Redusaun ba Retensaun ( 10 %)		$(12) \times 10\%$	\$ 10,000.00
16	Pagamentu depois de redusaun		$(12) - (14) - (15)$	\$ 80,000.00
17	Release ba Retensaun anterior			\$ -
18	Pagamentu ba fulan ida ne		$(14) + (15)$	\$ 80,000.00
19	Balansa depois de pagamentu ida ne'e		$(9) - (10) - (18)$	\$ 420,000.00
20	Progresu ba Pagamentu anterior (%)		$(10) / (9)$	50%
21	Progresu ba Pagamentu ida ne'e (%)		$(12) / (9)$	10%
22	Inspesaun ba Dokumentus	Dokumentus	Problemas ruman & Kommentarius	
	a) Dokumentus Kontratu	Sim/Nao		
	b) BOQ Kompletu ho Kuantidade	Sim/Nao		
	c) As-build Drawing iha Handover	Sim/Nao		
	d) Programa Orariu ba Obra	Sim/Nao		
	e) Resultadu Teste ba handover	Sim/Nao		
	f) Relatoriu Inspesaun	Sim/Nao		
	g) Fotografia ba servisu kompletu/Prontu	Sim/Nao		
21	<p><b>Resultadu husi Inspesaun</b></p> <p>{ Resultadu husi Dokumentus Inspesaun }</p> <p>Verifika items refere: * Dokumentus ba invoice preparadu ho korektu? * pedidu pagamentu ida ne hasoru kondisoins pagamentu hanesan retensaun no taxa? * Kalkulasaun ba fatura ne'e korektu? * Manteng nafatin loron kompletasaun? * Ordem remediou ruman husi Comisaun? * Resultadu teste hasoru kriteria?</p> <p>{ Resultadu Inspesaun ba Terrenu }</p> <p>Verifika items refere: * Comisaun atende iha terrenu no fo isplikasaun? * Komponentes importante ba funsaun no valor bo'ot husi kuantidades iha BoQ laran verifikadu? * Problemas ruman iha kuantidades ( qualidade ladun diak husi materiais no instalaoins, etc. )? * Problemas ruman iha kuantidades ( Diferenti entre atuais no BoQ nia laran )?</p> <p>{ Julgamentu ba Pagamentu }</p> <p>Resultadu ba verifikasaun: APPROVA/ APPROVA ho NOTA /REDUSAUN/PENDENTE</p>			
22	Proposta Pagamentu iha Invoice husi Kontratour (USD)			
23	Rekomendasaun Pagamentu ba MPS-MoF (USD)			80,000.00
24	Loron Inspesaun ba Terrenu	Data	Fulan	Tinan:
25	Inspetur	Asinatura:		Data :
	1. Maximos dos Santos			
	2. Ana Maria Guterres			Data :
	Verifika husi :	Asinatura:		Data :
	Miguel Marques Monteiro de Jesus			
26	Q.C.	Asinatura:		Data :
	Esrn ST. Henuk			
27	Approva husi :	Signature:		Date :
	Sr. Samuel Marçal			
28	Diretour Geral - ADN.			
27	Annex : Employer			

Formatu D-1 (Rekomendasaun ba Remediu)



REPÚBLICA DEMOCRÁTICA DE TIMOR-LESTE  
GABINETE PRIMEIRO MINISTRO  
AGENCIA DESENVOLVIMENTO NACIONAL

Formatu D-1

**RECOMMENDATION FOR REMEDY IN INTELIM PAYMENT**

Data : \_\_\_\_\_  
Kompanha : \_\_\_\_\_  
Fatin Projetu : \_\_\_\_\_  
Naran Projetu : \_\_\_\_\_

Bazeia ba inspeksaun nebe ekipa ADN ho Supervisor Kompanha halao, mak ekipa ADN hatoo ba kompanha rezultado rekomendasaun tuir mai :

**1 Medium Voltage**

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**2 Low Voltage**

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**3 Home Connection**

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Rekomendasaun hirak ne'ebe mensiona iha leten tuir duni realidade iha terenu e Kompanha pronto kolabora ou follow up rekomendasaun husi ekipa ADN,

Ekipa ADN

( \_\_\_\_\_ )

Supervisor EDTL

( \_\_\_\_\_ )

NB:

1. Orijinal depois asinadu tenke entrega ba AND
2. Fotokopia tahan ida ba EDTL no Kompanha

Supervisor Kompanha

( \_\_\_\_\_ )

Formatu D-2 (Rekomendasaun ba Remediu)



REPÚBLICA DEMOCRÁTICA DE TIMOR-LESTE  
GABINETE PRIMEIRO MINISTRO  
AGENCIA DESENVOLVIMENTO NACIONAL

Formatu D-2

**RECOMMENDATION FOR REMEDY IN PROVISIONAL HANDOVER**

Data : \_\_\_\_\_  
Kompanha : \_\_\_\_\_  
Fatin Projetu : \_\_\_\_\_  
Naran Projetu : \_\_\_\_\_

Bazeia ba inspeksaun nebe ekipa ADN ho Supervisor Kompanha halao, mak ekipa ADN hatoo ba companha rezultado rekomendasaun tuir mai :

**1 Medium Voltage**

.....  
.....  
.....  
.....

**2 Low Voltage**

.....  
.....  
.....  
.....

**3 Home Connection**

.....  
.....  
.....  
.....

Rekomendasaun hirak ne'ebe mensiona iha leten tuir duni realidade iha terenu e Kompanha pronto kolabora ou follow up rekomendasaun husi ekipa ADN,

Ekipa ADN

(\_\_\_\_\_)

Supervisor EDTL

(\_\_\_\_\_)

NB:

1. Drijinal depojs asinadu tenke entrega ba AND
2. Fotokopia tahan ida ba EDTL no Companha

Supervisor Companha

(\_\_\_\_\_)

Formatu D-3 (Rekomendasaun ba Remediu)



REPÚBLICA DEMOCRÁTICA DE TIMOR-LESTE  
GABINETE PRIMEIRO MINISTRO  
AGENCIA DESENVOLVIMENTO NACIONAL

Formatu D-3

**RECOMMENDATION FOR REMEDY IN FINAL HANDOVER**

Data : \_\_\_\_\_  
Kompanha : \_\_\_\_\_  
Fatin Projetu : \_\_\_\_\_  
Naran Projetu : \_\_\_\_\_

Bazeia ba inspeksaun nebe ekipa ADN ho Supervisor Kompanha halao, mak ekipa ADN hatoo ba kompanha rezultado rekomendasaun tuir mai :

**1 Medium Voltage**

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**2 Low Voltage**

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**3 Home Connection**

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Rekomendasaun hirak ne' ebe mensiona iha leten tuir duni realidade iha terenu e Kompanha pronto kolabora ou follow up rekomendasaun husi ekipa ADN,

Ekipa ADN

( \_\_\_\_\_ )

Supervisor EDTL

( \_\_\_\_\_ )

NB:

1. Orjinal depois asinadu tenke entrega ba AND
2. Fotokopia tahan ida ba EDTL no Kompanha

Supervisor Kompanha

( \_\_\_\_\_ )



Checklist A(Dokumentu Submetidu)

Checklist A

Ngaran Projeitu		Inspetikan husi	Apurina husi
<p>Class</p> <p>Emittir Seretifikado Kualidade antes saina Kontratu</p> <p>Fundo</p> <p>Fundo Infrastruktur</p> <p>Fase Projeitu</p> <p>Sub Distrito</p>			
<p>Porto Verifikasur</p>			
<p>Verifika Konfirmasur ba dokumentu s</p>		Verifika (Sim/Nao)	Remedio & Komentario
<p>1. Lista Projeitu</p>			
1	1. Lokasur husi Mapa no Diagrama husi linia	Sim/Nao	
	2. Diagrama ba planu no distribusur linia 20kv maka existe	Sim/Nao	
	3. Foto husi lusa s zere hetan elektifikasur	Sim/Nao	
	4. Foto husi populasur no lusa s zere hetan elektifikasur	Sim/Nao	
	5. Kriteria prioridadi ba sarakasur	Sim/Nao	
<p>2. Formulasion Projeitu</p>			
1	1) Justifikasur projeitu	Sim/Nao	
	2) Lokasur mapa	Sim/Nao	
	3) Outline husi lusa s zere hetan elektifikasur	Sim/Nao	
	4) Sairit e futuru ba ojeitu	Sim/Nao	
<p>3. Seresur ba kompania</p>			
1	1) Publikidade ba projeitu	Sim/Nao	
	2) Justifikasur projeitu	Sim/Nao	
	3) Imnda de renisar pasa lusa s zere hetan	Sim/Nao	
	4) Imposu kompania	Sim/Nao	
	5) Lista sairit esperensa antieru	Sim/Nao	
	6) Lista engineros ba projeitu	Sim/Nao	
<p>4. Dokumentu Kontratu</p>			
1	1) Sairit e futuru ba Projeitu	Sim/Nao	
	2) Amdo Kontratu serein antieru	Sim/Nao	
	3) Kondisus geral husi kontratu	Sim/Nao	
	4) Sairit e futuru ba Projeitu	Sim/Nao	
	5) Standar serein antieru	Sim/Nao	
	6) Disain Drainase	Sim/Nao	
	7) BOQ	Sim/Nao	

Nota: Numeru ho siraAula haidi katali, referementu marna ba dokumentu submetidu husi Komisar, atu verifika husi ADN



Checklist B-1 (Inspesaun ba pagamentu)



REPÚBLICA DEMOCRÁTICA DE TIMOR-LESTE  
 GABINETE PRIMEIRO MINISTRO  
 AGÊNCIA DE DESENVOLVIMENTO NACIONAL

Naran Projeitu		Checklist para Necesários Items Iha Relatorio Inspesaun husi Comissau		Inspesaun husi	Approva husi
Etapa	Verification for Interim Payment Request (1st and 2nd Pagamento)	Data Inspesaun husi ADN			
Fundu	Fundo Infraestrutura	Programa Electrifikasaun Nasional	Agencia Implementar	EDTL	
Fatin Projeitu	a) Distrito	b) Sub distrito	c) Suco/Aldeia		
Verifika Item	Porito inspesaun	Verifika (Sim/Nao)	Comentarios ba Items ne b'e maka la iha		
1 Resume verifikasaun ba Pedido Pagamentu husi Comissau			utiliza "Format 1"		
1 Outline ba Projeitu no pedido pagamento	Kategoria pagamentu hanesan interim, provisional no final handover	Sim/Nao			
2 Kalkulasaun Pagamentu	Kalkulasaun pagamentu ho kondisoinis pagamentu	Sim/Nao			
3 Letter with signature for verification	Assinatura husi Supervisor no chefe da comissao	Sim/Nao			
2 Revisaun ba obra no investigasaun detalha acordadu ba geografica no aspeto geologica					
1 Revisaun ba route lalhanan, so kark, ibe	Razaun husi revisaun	Sim/Nao			
2 narak husi linha 20 kv and 220v	Resultado detalha husi investigasaun	Sim/Nao			
3 Numero uma kain ne'be halo konesasaun	Resultado detalha husi investigasaun	Sim/Nao			
4 Numero husi transformer	Resultado detalha husi investigasaun	Sim/Nao			
5 Approva revisaun husi Comissau		Sim/Nao	ho inspector nia naran		
3 Documentos companha nian ho assinatura husi Comissau iha kada pagina					
1 Fatura	Kalkulasaun pagamentu ho kondisoinis pagamentu	Sim/Nao			
2 BOQ	Kompletado kuantidade ne b'e bele refere ba drawings	Sim/Nao			
3 D zenitu	Marka ho kor mean ba servisu ne'be maka komplete ona	Sim/Nao	Obra kompletu pruntu teske coresponde ho kuantidades iha BOQ		
4 Programa	Incluir orarun husi kurva S planu no kompletasaun obra	Sim/Nao			
5 Fotografias	Hatudu katak servisu completo ona prouto	Sim/Nao			
4 Resultadu ba supervisaun husi Comissau					
1 Instruksaun ba companha	Instruksaun remedio ba defectos obras husi Comissao	Sim/Nao			
2 Emitir certificado	Certifikasaun obra nia kompletu husi Companha kona ba remedio	Sim/Nao			
5 Dados digital iha fatura ba pedido pagamentu		Sim/Nao			



REPÚBLICA DEMOCRÁTICA DE TIMOR-LESTE  
GABINETE PRIMEIRO MINISTRO  
AGÊNCIA DE DESENVOLVIMENTO NACIONAL

Checklist B-2


Checklist para Necessários Items iha Relatorio Inspeksaun husi Comisaun				Inspeksaun husi	Approva husi
Naran Projectu					
Etapas	Verifikasaun ba Pedido Pagamento iha Provisional Handover			Data Inspeksaun husi ADN	
Fundu	Fundu Infraestrutura	Tipo Projectu	Programa Electrifikasaun Nasional	Agencia Implementar	EDTL
Fatin Projectu	a) Distrito:		b) Sub distrito:	c) Suco/Aldia :	
Verifika Item	Ponto inspesaun		Verifika (Sim/Nao)	Problemas / Defectos & Remedio	
1	Resumo ba verifikasaun husi pedido pagamento husi Comisaun			utiliza "Format 1"	
1	Outlino husi projectu no pedidu pagamentu	Kategoria ba pagamento hanesan interim, provisional no final handover	Sim/Nao		
2	Kalkulasaun ba Pagamentu	Kalculasaun pagamento ho condicoins pagamento	Sim/Nao		
3	Karta ho assinatura para halo verifikasaun	Assinatura husi Supervisor no chefe da commissao	Sim/Nao		
2	Revisaun ba obra no investigasaun detalha accordo ba geografica no aspeto geologica				
	Revisaun ba rute linha nia, se kank itia	Razaun husi revisaun	Sim/Nao		
	Naruk husi linha 20 kv and 220v	resultado husi detalh investigasaun	Sim/Nao		
	Numero husi transformer	resultado husi detalh investigasaun	Sim/Nao		
	Numero uma kank ne be halo koreksaun	resultado husi detalh investigasaun	Sim/Nao		
	Approva ba revisaun husi Comisaun		Sim/Nao	ho Inspector nia naran	
3	Dokumentos companha nian ho assinatura husi Comisaun iha kada pagina				
1	Fatura	Calculasaun ba pagamento	Sim/Nao		
2	BOQ	Completo ho quantidades atravesa medidaun resultado obras	Sim/Nao		
3	As-build Drawings	Obras completo	Sim/Nao		
4	Programa*	indul orano curve \$ ba palanu no kompletasaun obra	Sim/Nao		
5	Fotografia	Hatudu katak servisu completo ona/ pronto	Sim/Nao		
4	Relatorio supervisaun husi Comisaun				
1	Instruksaun ba companha	Instruksaun remedio ba defeitus obras husi Comissao	Sim/Nao		
2	Emitir certificado	Sertificasaun obras nia kompletu husi Companha kona ba remedio	Sim/Nao		
5	Resultado ka funcional teste no medidaun ho kriteria		Sim/Nao	Referencia lista verifikasaun 3"	
6	Dados digital iha fatura ba pedido pagamento		Sim/Nao		

Checklist B-3

Checklist para Necessários Items Iha Relatorio Inspeksaun husi Comisaun				Inspeksaun husi	Approva husi	
Naran Projeitu						
Etapa	Verifikasaun ba Pedido Pagamento Iha Final Handover					
Fúndu	Fúndu Infraestrutura	Tipo Projeitu	Programa Electrifikasaun Nasional	Data Inspeksaun husi ADN		
Fatin Projeitu	a) Distrito:		b) Sub distrito:	Agencia Implementar	EDTL	
		c) Suco/Aldeia :				
Verifika Item		Ponto inspesaun		Verifika (Sim/Nao)	Problemas / Defectos & Remedio	
1	Resume ba verifikasaun husi pedido pagamento husi Comisaun					utiliza "Format 1"
1	Outline husi projeitu no pedido pagamento	Categoria ba pagamento hanesan interim, provisional no final handover			Sim/Nao	
2	Kalkulasaun ba Pagamentu	Kalkulasaun pagamento ho kondisoini pagamento			Sim/Nao	
3	Karta Iho assinatura para Ihalo verifikasaun	Assinatura husi Supervisor no chefe da comissao			Sim/Nao	
2	Revisaun ba obra no investigasaun detalha accordo ba geografica no aspeto geologica	karik Iha mudansa				
	Revisaun ba rute linha nia, se karik Iha	Razaun husi revisaun			Sim/Nao	
	Narak husi linha 20 kv and 220v	Resultado husi detalh investigasaun			Sim/Nao	
	Numero husi transformer	Resultado husi detalh investigasaun			Sim/Nao	
	Numero husi unta ne'ho Ihalo koneksaun	Resultado husi detalh investigasaun			Sim/Nao	
	Approva ba revisaun husi Comisaun				Sim/Nao	
3	Dokumentos companha nian ho assinatura husi Comisaun Iha kada pagina, karik Iha mudansa depois de Provisional Handover					
1	Fatura, karik Iha mudansa	Kalkulasaun ba pagamento			Sim/Nao	
2	BOQ, karik Iha mudansa	Kompletus ho quantidades atravesa medisaun resultado obras			Sim/Nao	
3	As-build Drawings, karik Iha mudansa	Obras kompleto			Sim/Nao	
4	"Programa", karik Iha mudansa	Inclui oratu husi Kurva S ba planu no Kompletasaun obra			Sim/Nao	
5	Photographs, karik Iha mudansa	Hatudu katak servisu completo ona, pronto			Sim/Nao	
4	Relatorio ba supervisaun husi Comisaun, karik Iha servisu ruman					
1	Instruksaun ba companha	Instruksaun remedi ba defectos obras husi Comissao			Sim/Nao	
2	Emittir certificado	Certifikasaun obras nia kompletu husi Companha kona ba remedi			Sim/Nao	
5	Relatorio ba operasaun no manutensaun					
6	Dados digital Iha fatura ba pedido pagamentu					
				Sim/Nao	Difficuldades ruman no Problemas ho Remedio	



# Checklist C (Inspeksaun Tékniku ha Distribuisaun Liña)



Checklist ba Nessesariu Items ba Técnico Inspeksaun					Inspeksaun husi	Approva husi
Naran Projeitu						
Etapa	Verifikasaun ba Pagamentu	Tipo Projeitu	Programa Electrifikasaun Nasional	Data Inspeksaun husi: ADN		
Fundu	Fundu Infrastruktura	a) Distrito	b) Sub distrito:	Agencia Implementar	EDTL	
Fatin Projeitu				c) Suco/Aldia:		
Verifika Dokumentus				Ponto Verifikasaun	Verifika (Sim/Nao)	Problemas / Defectos & Remedio
1	Verifika Exame eksternal ita terrenu					
1	Stabilidade husi airing	Tipu fundasaun, ba rai no fatuk				
		Klean ita rai nia okos				
		Supurta ba kritikal airing, Guy/Shaft support				
2	Pinta ba airing	Dalas ba pinta				
3	Conductor/Kondotur	Folga				
4	Insulator	Meruk husi MV/LV Circuits				
5	Transformer/Travo					
6	As husi linha ita leten					
7	Folga entre Linhas Aéreas (Overhead Lines) no Objetus					
8	Linha korta husi Linhas despezajiral	Distansi ba Linhas				
2	Verifika Dokumentus husi standar tebniku					
1	Resisténsia trasaun husi kondutores no fia rai-okos	Resisténsia trasaun depois koneksaun				
2	Kondotur	Koneksaun husi Kondotur				
3	Insulator/Isolador	Kapasidade izolamentu depende ba voltage				
4	Sistema Elektrika Rai-okos	Valor husi rai okos				
5	Despositivus Proteksaun	Korrente Mak'as Iiu no Falhansu Rai-Okos Sirkuitu Kebrabores				
6	Standar tansaun	Iapará Sobretensaun				
3	Verifika Dokumentus no Medisaun ita terreno					
1	Resisténsia Ligasaun-Fiai	Sistema Ligasaun-Rai ba substasaun				
		Protectivo Ligasaun-Rai ba transformers				
		Iapará Sobretensaun Earthing				
2	Izolamentu Resisténsia	Iiha voltage 20kV				
		Transformer				
		Iapará rai-lakan				
4	Sekutun					
1	Sertifikado husi suppliers/fabrikas	III Certifikado ba materiais				
		Performa Sertifikadu ba Komponentes				

## {Anexu}

### Matadalan husi Inspesaun Téknika ba Liña Distribuisaun

#### 1. Objektivu

“Padraun husi Inspesaun Téknika ba Liña Distribuisaun” ne’e mak establesidu hodi fasilita no implementasaun efisiente ba inspesaun téknika durante konkluziun fiziku husi konstrusaun liña distribuisaun elektrisidade

#### 2. Âmbitu

Padraun ne’e mak alista item prinsipal balun no criteria hirak ne’e atu aplika ba aspektu téknika ba inspesaun iha handover/Entrega.

#### 3. Objektu husi inspesaun handover/Entrega

Inspesaun téknika tenke ser hala’o hodi verifika karik instalasoens distribuisaun elektrisidade mak haktuir konstrusaun korretamente iha akordansia ho volume dezeñu no espesifikasaun téknika iha kontratu. Reparasaun/Remedy ba defeitus tenke ser esklarese nu’udar baze husi inspesaun.

#### 5. Auto-inspesaun husi Contractor/Emprezáriu

Contractor/Emprezáriu tenke ser submete relatóriu auto-inspesaun ba LM liu-husi hato’o auto-inspesaun depois de konkluziun husi obras. As-built Drawing/Haktuir Dezeña, BOQ husi obra ne’ebé kompleta ona no fotografía projetu tenke ser anexa.

#### 6. Inspesaun husi LM

LM tenke prepara no submete relatóriu inspesaun ba ADN liu-husi hala’o inspesaun depois de simu relatóriu inspesaun husi emprezáriu.

#### 7. Inspesaun Handover/Entrega

##### 7-1 Exame Dokumentáriu

Rezultadu inspesaun husi Contractor/Emprezáriu no LM tenke ser examina. Karik konteúdu husi inspesaun hirak ne’e mak la adequadu, ADN tenke informa sira atu hala’o inspesaun adisional ka remedy/reparasaun ba defeitus.

##### 7-2 Métudu no Kritériu Inspesaun

Kondisoens Instalasaun iha terrenu tenke hasoru padraun téknika ne’ebé bai-bain utiliza hanesan Padraun PLN Indonésia.

Sasukat hirak iha okos tenke ser hala’o ba Instalasoens hotu-hotu.

- (1) Verifikasaun liu-husi exame Externu
- (2) Verifikasaun liu-husi padraun Téknika/Technical Standard
- (3) Verifikasaun ba medisaun/Measurement

## **Lista Verifikasaun ba Aspektu Téniku iha Inspesaun Terrenu**

### **(1) Verifikasaun liu-husi exame Externu**

- Estabilidade husi Ai-rin/Pole
  - Profundidade/Depth iha underground/Rai-okos
  - Guy/kara
- Conductor/kondutor
  - Clearance/folga
  - Length/Nanaruk husi MV/LV Circuits (sirkuitus)
- Insulator/Izolador
- Transformer/Transformador
- Height/Altura husi Liñas Overhead/despezas jerais
  - Estrada ka seluk-seluk
- Clearance/Folga entre Liñas Overhead/despezas jerais no Objektus Ai-hun; liu husi 5m ba liñas foun overhead/despezas jerais
- Crossing/Atravessa liu-husi Liñas Overhead/despezas jerais
  - Distánsia husi liñas

### **(2) Verifikasaun liu-husi padraun Téknika/Technical Standard**

- Tensile Strength/Resisténsia trasaun husi Conductors/kondutores no Fiu rai-okos/Ground Wires
  - Fator Seguransa/Safety factor
  - Tensile Strength/Resisténsia trasaun depois de koneksaun
- Conductor/Kondutor
  - Koneksaun husi Kondutor
  - Kapasidade izolasaun/Insulation Capacity depende ba tensaun
- Power System Grounding/sistema elétrico rai-okos
  - Valor tenke labele liu husi 10 ohms.
- Protective Devices/ Dispositivos Protesaun
  - Over Current Circuit Breakers/Sirkuitu Kebradores Korrente Superior
  - Ground Fault Circuit Breakers/Sirkuitu Kebradores Falhansu Rai-okos
  - Surge Arresters/ Hapará Sobretensaun
- Sertifikadu Aquizisaun husi fornecedores/fábrica
  - Sertifikadu Mill ba materiais
  - Sertifikadu verifikasaun dezempeñu/Performance ba Komponentes
- Standard Voltage/Padraun Tensaun

### **(3) Verifikasaun ba medisaun/Measurement**



- Earthing Resistance/Resisténsia Ligasaun Rai (pilas)
  - System Earthing/sistema Ligasaun-Rai ba subestasaun/substations
  - Protective Earthing/protesaun ligasaun-Rai ba transformador/transformers
  - Surge Arrester/ Hapará Sobretensaun ba Earthing/ligasaun-rai
- Insulation Resistance/Resisténsia Izolasaun
  - Liña Tensaun 20kV
  - Transformador
  - Lightning/Rai-lakan(pilas) arrester/Hapará

## 1 VERIFIKASAUN liu-husi EXAME EXTERNU

### 1.1 Pole/Ai-rin

Item	Métodu Inspesaun	Kritériu
Tipu	Inspesaun Visual ba material, medida	Konstrui haktuir hanesan kontratu
Ajusta Profundidade (klean)	Verifika liu-husi marka ba profundidade/depth(klean) Verifika liu-husi fotográfia	Konstrui haktuir hanesan Kontratu Depth/klean 2m ba pole/ai-rin 12m iha fundasi rai Depth/klean 1.5m ba pole/ai-rin 9m iha fundasi rai
Inklinasaun (enkosta)	Inspesaun Visual	Laletek husi Ai-rin/pole tenke labele sai husi liña liu husi 2ft.
Pintura	Inspesaun Visual	Pelu menus, Kamadas/layer rua tenke ser pinta Kamada baze/Base layer husi pintura tenke labele mosu/aparese iha partes ruma husi estrutura

[exemplu husi inklinaun/enkosta]


Kazu Di'ak	Kazu A'at
	
Inklinasaun mak menus husi 2ft.	Inklinasaun mak liu husi 2ft iha laletek.

**Guy/kara**

Item	Métodu Inspesaun	Kritériu
Julga ba adopsaun	Inspesaun Visual	Liña rua iha pole iha mais 5 graus husi ângulo/sudut
Instalasaun	Inspesaun Visual	Instaladu iha pole/ai-rin korrektamente
Fondasi	Inspesaun Visual	Instaladu firmemente para nia bele suporta adequadu ba karga tensaun
Globu inzolador	Inspesaun Visual	Inserida iha parte a'as-liu/superior husi guy

Construsaun Ai-rin Suporta

Tipu 1. Fiu Guy/kara




Keterangan : • Konstruksi topang tarik ( Guy Wire ) jika komponen no 3 di pakai, tidak perlu memakai komponen no. 6

NO	NOMOR SAP	NAMA MATERIAL	SATUAN	JUMLAH	
				TM	TR
1		Guy Wire Band + Bolt & Nut M16 X 50	Set	1	1
2		Terminating Thimble	Pcs	1	-
3		Preformed Grit 22/35/70	Pcs	4	2
4		Guy Insulator	Pcs	1	-
5		Galv Steel Stranded Wire 22/35/70 Sqmm	Mtr	X	X
6		Wire Clip	Pcs	1	1
7		Plpa Pelindung 3/4"-2Mtr	Pcs	1	1
		-	Pcs	-	-
8		Guy Rod ( 2.5 / 1.8 ) Mtr	Pcs	1	1
9		U Bolt & Nut M16	Pcs	1	1
10		Anchor Block 400 X 400 mm/Epending Anchor	Pcs	1	1
11		Turn Buckle 5/8"	Pcs	-	1
12		Turn Buckle 3/4"	Pcs	1	-

ADN	<b>KONSTRUKSI TOPANG TARIK / GUY WIRE PADA TIANG BETON BULAT</b>		FOTO
	STANDAR KONSTRUKSI JARINGAN DISTRIBUSI		
DIGAMBAR PPST UI	No. GAMBAR JTM/SUTM/08		
DISETUJUI : DIV. DISTRIBUSI IT, IB, JB	EDISI 1	2010 112	

## Konstrusaun Ai-rin suporta

### Tipu 1. Kontramast




Keterangan : •Konstruksi topang tarik khusus ( supported Guy Wire - kontramast )

NO	NOMOR SAP	NAMA MATERIAL	SATUAN	JUMLAH	
				TM	TR
1		Guy Wire Band + Bolt & Nut M16 X 50	Set	1	1
2		Terminating Thimble	Pcs	1	-
3		Preformed Grip 22/35/70	Pcs	4	2
4		Guy Insulator	Pcs	1	-
5		Galv Steel Stranded Wire 22/35 Sqmm	Mtr	X	X
6		Wire Clip	Pcs	1	1
7		Pipa Pelindung 3/4"-2Mtr	Pcs	1	1
8		Guy Rod ( 2,5 / 1,8 ) Mtr	Pcs	-	-
9		U Bolt & Nut M16	Pcs	1	1
10		Anchor Block 400 X 400 mm	Pcs	1	1
11		Expanding Anchor	Pcs	1	1
12		Turn Buckle 5/8" atau 3/4"	Pcs	-	1

ADN	KONSTRUKSI TOPANG TARIK KONTRAMAST		No. GAMBAR : JTM/SUTM/67	FOTO
DISETUJUI : DIV. DISTRIBUSI IT, IB, JB		EDISI 1	111	

Konstrusaun Ai-rin Suporta

Tipu 1. Ai-rin suporta




NO	NOMOR SAP	NAMA MATERIAL	SATUAN	JUMLAH			
1		Single Arm Band & Nut M16 + Washer	Set	1			
2		Strut Arm UNP. 8 x 300	Pcs	1			
3		Strut Tie 1200 s/d 1500	Pcs	1			
4		Double Pole Band + Bolt & Nut M 16 X 50	Set	4			
5		Bolt & Nut M 16 X 140 + 16 X50	Set	11			
NO	TYPE TIANG BESI		SATUAN DALAM METER				
	UTAMA	STRUT POLE	A	B	C	D	E
1	13	11	8,4	10	5,42	1,83	1
2	11	9	7,7	8,4	3,3	1,83	0,6
3	9	9	6,75	8	4,2	1,5	1
4	7	7	5,3	6,5	3,7	1,16	0,5

ADN	KONSTRUKSI PENOPANG TIANG ( STRUT POLE )		FOTO
	STANDAR KONSTRUKSI JARINGAN DISTRIBUSI		
DIGAMBAR PPST UI	No. GAMBAR : JTM/SUTM/05		
DISETUJUI : DIV. DISTRIBUSI IT. IB. JB	EDISI : 1	2010	
		109	



## 1.2 Kondutor



### PVC LOW VOLTAGE CABLE

#### TECHNICAL DATA

Spec	Specification : SPLN 43 -1 : 1994, IEC 60502 - 1 : 1997	Cu	Conductor Shape : re = Circular rm = Circular
AFL	Used for indoor in ducts installation or for laying in the ground where not sustain mechanical damage	DCV	DC Test Voltage : 8,5 kV for 5



#### DIMENSIONAL DATA

**5** CORES

SIZE	No. of wire and Shaped Of Conductor		Nominal Thickness		Approximately		Min. Bending Diameter	Std. Length per reel
			Insulation	Outer Sheath	Overall Diameter	Net. Weight		
mm <sup>2</sup>	pcs	shape	mm	mm	mm	kg/km	mm	m
1.5	1	re	0.8		12.8	255	230	1000
	7	rm			13.3	268	239	
2.5	1	re			14	329	252	
	7	rm			14.6	352	263	
4	1	re	1	1.8	16.3	470	293	
	7	rm			17.1	505	308	
6	1	re			17.7	602	319	
	7	rm			18.6	650	335	
10	7	rm	1.2		21	912	378	
16	7	rm			23.8	1279	428	
25	7	rm	1.2		28.3	1914	509	
35	7	rm			31.5	2505	567	
50	19	rm	1.4	1.9	36.4	3273	655	

Item	Métodu Inspesaun	Kritériu
Tipu	Inspesaun Visual iha pontu konektadu no instalasaun husi izolador	Konstrui haktuir hanesan Kontratu
Pontu Konektadu	Inspesaun Visual	Laiha Pontu Konektadu entre ai-rin ida ho ai-rin tuir mai
Dip (Sag)	Inspesaun Visual	Sedauk iha extraordináriu folgas ka aperta
Clearance/Folga	Inspesaun Visual no medisaun husi clearance/folga	Tenke ser kumpri ba Padraun/standard Téknika
Nanaruk husi MV/LV Circuits	Inspesaun Visual ba Medisaun Nanaruk husi meius kilometrazen viajen kareta nian etc.	Konstrui la liu husi radius 500m husi subestasaun.

[exemplu husi Instalasaun Global]

Kazu Di'ak	Kazu A'at
	
Fiu Jumper mak konektadu husi Konektor.	Fiu Jumper mak konekta folga, la aperta.

[exemplu husi clearance/folga]

Kazu Di'ak	Kazu A'at
	
Iha folga/clearance sufisiente entre HV no LV.	Laiha folga/clearance (0.6m de'it) entre HV no LV, nomos laiha guarda fiu/guard wires.

### 1.3 Insulator/Izolador

Tipu izolador ne'ebé uja iha liña transmisaun mak parceling/tipu vidro.

Klasifikasaun izolador maka:

- a. cotter pin insulator/ isolator jenis pasak.
- b. pos-transmission isolator /isolator tipu pos-transmisaun.
- c. hang isolator/ isolator gantung.

Izolaor tipu cotter pin no izolador tipu pos-transmisaun mak utiliza ba transmisaun ho servisu relativu baixa tensaun (mais-menus husi 22-33 kV), enquanto hang/ isolator gantung bele okupladu/ digandeng sai nu'udar suite izolador mak-ne'ebé número bele ajusta haktuir ba nesesidade.

Iha tipu izolador rua ne'ebé bele uja komforme ba nia funsoens :

1. Liña Izolador iha variedade em termos: Liña post Izolador/ line post insulator, post insulator, insulator pin. Izolador ne'e utiliza ba apoiu hodi kondukta forsa mékanikal ba izolador ida ne'e hodi realiza tahan todan karga iha ai-rin.
2. Izolador suspensaun ( Suspension isolator), iha tipu 2 mak : izolador despeza (Umbrella Insulator) no long rod insulator.

### Karakteristika Izolador



No	karakteristika	Tipu Izolador		
		Line Post	Pin Post	Pin
1	Servisu Tensaun Máximu	24 kv	24 kv	22 kv
2	Tensaun suportável/Withstand voltage (bokon)	65 kv	65 kv	75 kv
3	Tensaun Impolso supertável/Impulse withstand Voltage	125 kv	125 kv	125 kv
4	Forsa mékanika/Mechanical Strenght	1250 daN	1250 kv	850 daN
5	Distansia fuga/Creepage distance	480 mm	534 mm	583 mm
6	Todan	8,34 kg	10 kg	6,4 kg

Ba 1 nu'udar tipu suspensaun konsiste husi pedasuk 2/bikan 2 entantu tipu long rod pedasuk 1. Karga/todan izolador mékanika ne'e mak karga mékanika hanesan haktuir ba ai-rin izolador nia ulun / ai-rin hahu nian.

Item	Métodu Inspesaun	Kritériu
Tipu, Voltage/Tensaun	Inspesaun Visual ba tipu	Korresponde ba liña Tensaun
Instalasaun Global	Inspesaun Visual ba instalasaun global husi izoladores	Laiha mak la haktuir bain-bain hanesan rahun/retak

## 1.4 Transformer/transformatador

Jeralmente konfigurasaun husi ai-rin transformador ne'ebé enerjia husi SUTM mak T section ho ekipamentu seguransa Cut-Out (FCO) hanesan koneksaun seguransa badak ba transformador ho element fuser/harahun (fuzau/harahun tipu link expulsaun) no hapara pilas/*Lightning Arrester* (LA) hanesan ekipamentu hodi prevene tensaun maka'as iha transformador kauza husi rai-lakan/pilas.




**Tabel 2.1. Vektor Group dan Daya Transformator**

NO	Vektor Group	Daya (kVA)	Keterangan
1	Yzn5	50 100 160	Untuk sistem 3 kawat
2	Dyn5	200 250 315 400 500 630	Untuk sistem 3 kawat
3	Ynyn0	50 100 160 200 250 315 400 500 630	Untuk sistem 4 kawat

## Distansia Seguru husi rede

No.	Uraian	Jarak Aman
1.	Terhadap permukaan jalan raya	≥ 6 meter
2.	Balkon rumah	≥ 2,5 meter
3.	Atap rumah	≥ 2 meter
4.	Dinding Bangunan	≥ 2,5 meter
5.	Antena TV/ radio, menara	≥ 2,5 meter
6.	Pohon	≥ 2,5 meter
7.	Lintasan kereta api	≥ 2 meter dari atap kereta
8.	Underbuilt TM – TM	≥ 1 meter
9.	Underbuilt TM – TR	≥ 1 meter

Item	Métodu Inspesaun	Kritériu
Tipu, Kapasidade	Inspesaun Visual ba tipu no kapasidade husi transformador	Konstrui haktuir hanesan Kontratu
Konneksaun	Inspesaun Visual ba konneksaun	Konnekta hanesan rekerementu
Fiasaun Subestasaun	Inspesaun Visual	Laiha Pontus konnektidu iha kondutores
Instalasaun transformador	Inspesaun Visual ba instalasaun	Laiha mak la bai-bain
Instalasaun ba dispozitivus protesaun	Inspesaun Visual ba instalasaun	Persija dispozitivus/perangkat protesaun tenke ser instala iha parte dahuluk husi transformador
Instalasaun Ligasaun rai/Earthing wire	Inspesaun Visual ba instalasaun global husi ligasaun rai/earthing wire	Laiha mak la bai-bain




**PENJELASAN**

- S1 : Panjang andongan (sag) jaringan tegangan rendah tidak kurang dari 60 Cm
- S2 : Jarak saluran udara tegangan rendah dengan kabel optik telekomunikasi tidak kurang dari 1000 Cm
- H : Jarak aman kabel optik terhadap permukaan jalan
  - Jalan umum tidak kurang dari 6 meter
  - Jalan lingkungan tidak kurang dari 5 meter
  - Tanah pekarangan pribadi tidak kurang dari 4 meter

<b>ADN</b>	<b>SALURAN UDARA TEGANGAN RENDAH JARAK AMAN</b>	
	DIGAMBAR PPST LI	No. GAMBAR : JTR/SUTR/25
DISETJUIH DIV. DISTRIBUSI IT, IB, JB	<b>STANDAR KONSTRUKSI JARINGAN DISTRIBUSI</b>	EDISI : 1
		2010 54

<b>Títulu</b>	Folga/Clearance entre liña despezada jéral/Overhead Line no Ai-hun
---------------	--



(Unidade: m)


Folga/Clearance Mínimu

<b><i>Médu &amp; Baixa-tensaun</i></b>	<b><i>Alta-tensaun</i></b>
Tenke labele kontakta diretamente	Menus husi 0.9m

Folga/clearance tenke ser liu husi 5m ho liña overhead foun.

<b>Observasoens</b>	<b>Revizoens</b>	





**PENJELASAN :**


- Perlintasan kabel telekomunikasi dengan saluran tenaga listrik dengan jarak -D
- Dengan saluran udara dengan tegangan menengah tidak kurang dari 250 Cm
- Dengan saluran udara dengan tegangan rendah tidak kurang dari 100 Cm
- Dengan saluran udara dengan tegangan menengah tidak kurang dari 250 Cm
- Jarak aman H tidak kurang dari 600 Cm

ADN	<b>KONSTRUKSI PERLINTASAN DENGAN KABEL TELEKOMUNIKASI</b>		
	DIGAMBAR PPST UII	<b>STANDAR KONSTRUKSI JARINGAN DISTRIBUSI</b>	NO. GAMBAR JTR/SUTR/24
DISETUJUI : DIV. DISTRIBUSI (T, IB, JB)	1	2010	63

FOLGA/CLEARANCE IHA UTILIZASAUN PARTE IDA BA IDA NO UTILIZASAUN JUNTA LIÑA

**Clearance on Side by Side Use and Joint Use of Lines**

The minimum clearance of each lines at a supporting structure is give by the following fig and table. The clearance is dicided taking working space into consideration.




(Unit: m)

**Recommended Minimum Clearance**

A	High-Voltage Line	Medium /Low-Voltage Line	0.9m

Remarks	Revisions

Títulu: Ajusta Kle'an/Setting Depth ba estrutura suporta/Supporting Structure



**KETERANGAN**

L Tinggi Tiang (m)	UKURAN	Beban Rencana (daN)	Top (bag atas) (mm)		Bottom (bag bawah) (mm)		Ukuran (mm)			
			a	b	A	B	c	d	e	f
9	Ø	200	165	110	315	235	18	55	52	72
Ø	Ø	500								


ADN

**TIANG BETON TYPE - H**

DIGAMBAR PPST UI	STANDAR KONSTRUKSI JARINGAN DISTRIBUSI	No. GAMBAR JTR/SUTR-SKUTR/02
DISETUJUI : DIV DISTRIBUSI (F. IB, JB)		EDISI 1
		2010 103

<b>Títulu</b>	Ajusta Klean/profundidade ba estrutura suporta
---------------	--


Ajusta Klean/profundidade ba estrutura suporta define ona iha Artigu No.X-X husi Standard /PadraunTécnika mak tui-mai;



\* Valor husi B mak deside bazeia ba kalkulasaun konsidera ba situasaun pior husi kada kondisaun.

Observasoens	Revizoens	


## Foundasaun



**KETERANGAN :**

- Pondasi Tipe-C = pemakaian untuk tanah berpasir, tanah liat
- Campuran beton = 1 semen + 3 pasir + 5 koral

ADN	REKOMENDASI PONDASI TIANG TIPE C		
	<b>STANDAR KONSTRUKSI JARINGAN DISTRIBUSI</b>		No. GAMBAR : JTR/SUTR45
DISELUAR : DIV. DISTRIBUSI IT, © . . .	EDISI 1	2019	93



- a= 15cm
- b= tiang 350 daN = 50cm
- tiang 500 daN =
- tiang 200 daN =
- c= 250mm
- $d = \frac{1}{6} \times \text{panjang tiang}$
- e= 2 x diameter tiang bagian bawah

t= 40 cm  
1:2:3


Type foundation In rock

**KETERANGAN :**

- o Pondasi Tipe-d = pemakaian pada tanah lunak, endapan lumpur
- o Campuran beton = 1 semen + 3 pasir + 5 koral

ADN	REKOMENDASI PONDASI TIANG TIPE D		
	PST 03	No GAMBAR	JTR/SUTR/45A
DISETUJUI DIV. DISTRIBUSI IT, IB, JB	<b>STANDAR KONSTRUKSI JARINGAN DISTRIBUSI</b>		EDISI 1
			2010 94

## 1.4 Transformer/transformador

<b>Títulu</b>	Kondisoens Instalasaun husi Transformadores HV(alta) / MV(Médiu) & LV(baixa)	
<p>Transformadores HV(alta) / MV(Médiu) &amp; LV(baixa) tenke ser instala iha maneira ruma husi métodu tuir-mai karik sira la instaladu no savi iha kabina eksklusivu.</p> <p><b>Instalasaun ba ai-rin/pole iha altura husi 5.0m ka liu</b></p> <div style="display: flex; align-items: center;">  </div>		
<b>Observasoens</b>	<b>Revizoens</b>	

## 2 VERIFIKASAUN ba PADRAUN / STANDARD TÉKNIKA

### 2.1 Altura husi Liñas Despeza Jéral/Overhead

Altura husi Liñas distribusaun despeza jéral/overhead tenke ser la menus husi valores iha tabela tuir-mai;

	Médiu & Baixa tensaun	Altura Tensaun
Atravessa estrada	5.4m(18ft)	5.7m(19ft)
Atravessa Dalan kombioneta	7.5m(25ft)	7.5m(25ft)
Seluk-seluk	4.8m(16ft)	5.1m(17ft)

### 2.2 Folga/Clearance entre Liñas Overhead no Objektus seluk

Liñas despeza jéral/Overhead tenke atravessa mais objektus ho folga/clearance ne'ebé nesessáriu. Folga Mínimu entre liña ida ho objektus sira seluk tenke ser valorize iha tabela tuir-mai;

(Unidade: m)

				Médiu ka baixa tensaun	Alta tensaun
Estrutura husi Konstrusaun	Laletek Adjasênsia /Kbesik	Ho possibilidade ba ema atu sa'e ba	Bare/fiu-molik Kondutor	2.5m	3m
			Kondutor Inzoladu	2m	2.5m
			Cable/fiu	1m	1.2m
		Seluk-seluk	Bare/fiu-molik Kondutor	2m	3m
			Kondutor Inzoladu	1.2m	1.5m
			Cable/fiu	0.4m	0.5m
	Lateral no desvantajem Adjasênsia/Kbesik	Bare/fiu-molik Kondutor	2m	3m	
		Kondutor Inzoladu	1.2m	1.5m	
		Cable/fiu	0.4m	0.5m	
Ai-horis	Bare/fiu-molik Kondutor		5m iha konstrusaun fo'un	Hensan ho karuk	
	Kondutor Inzoladu		Tenke labele kontakta diretamente		
	Cable/fiu		Tenke labele kontakta diretamente		



### **2.3 Resisténsia Trasaun husi Kondutores no Fiu Rai-okos**

Hanesan ba tensile strength/ Resisténsia trasaun husi kondutores /conductors no Fiu rai-okos/Ground Wires ba liñas eléktrika despeza jéral/overhead la inklui ho fiu/cables, Fator seguransa/safety factor tenke ser labele menus husi 2.5.

### **2.4 Resisténsia Trasaun depois de Koneksaun**

(1) Métopu Koneksaun husi Kondutores despeza jéral/Overhead Conductors

Resisténsia trasaun/tensile strength husi kondutores tenke ser labele reduz husi 20% ka liu, wainhira kondutores eléktrika konekta hela.

(2) Sanak(Branching) husi Liñas despeza jéral(Overhead Lines)

Sanak/Branching Liñas despeza jéral/Overhead Lines tenke ser halo ba pontu suporta husi Liñas.

### **2.5 Kapasidade Izolamentu**

Fiu sira no kondutores izoladu tenke iha kapasidade izolamentu (insulation capacity) sufisiente apropriadu ba kondisoens husi tensaun aplikadu (applied voltage).

### **2.6 Koneksaun husi Kondutores**

Kondutores tenke ser konekta hanesan métodu tui-mai;

1. Kondutores tenke ser konekta firmemente atu evita aumenta iha resisténsia.
2. Kapasidade izoladu husi fiu/cables no kondutor izoladu tenke ser labele hatun.
3. Elektrokimia korosi(electrochemical corrosion) tenke labele akuntese konekta kondutores ba diferente tipu husi materiais.

### **2.7 Grounding/Fiu Rai-okos**

1. Grounding ka sasukat apropriadu seluk tenke ser fornese ba ekipamentu eléktriku prevene husi choke eléktriku, perigu ba ema nia isin lolon, ahi, no seluk-seluk tan.
2. Grounding ba ekipamentu eléktriku tenke ser instala para halo fluxu korrente(current flow) salva no seguru tama ba rai.

### **2.8 Sistema Eléktrika Rai-okos (Power System Grounding)**

Sistema Eléktrika Rai-okos tenke ser aplika ba transformador katak konekta liña distribusaun alta-tensaun no médiu/baixa-tensaun atu prevene asidente ruma, ne'ebé bele akuntese tamba kontakta sala. Valor husi grounding/rai-okos tenke ser labele liu husi 10 ohms.

## **2.9 Proteksaun kontra Korrente mais superior (Over-current)**

Ekipamentu Proteksaun kontra korrente mais superior/maka'as liu (over-current) tenke ser instala iha fatin apropriadu husi sirkuitus eléktrikus (electrical circuits) atu prevene ekipamentu eléktriku husi Manas-liu (over-heating) tamba korrente ne'ebé mais superior(maka'as liu) no la hamosu ahi-han.

## **2.10 Proteksaun kontra Falhansu Rai-okos (Ground Faults)**

Ekipamentu Proteksaun kontra falhansu rai-okos(ground faults) ka sasukat apropriadu seluk tenke ser fornese hodi prevene estragu husi ekipamentu eléktriku, choke eléktriku no ahi-han.

## **2.11 Instalasaun ba Despozitivus Proteksaun(Protective Devices)**

### **(1) Sirkuitu Kebradores (Circuit Breakers) Korrente Maka'as liu (Over Current)**

1. Iha liñas alta-tensaun, sirkuitu kebradores (circuit breaker)Korrente maka'as liu tenke ser instala iha pontu korrente sai (outgoing point) husi subestasaun ka fatin hanesan ruma no iha parte dahuluk husi transformador (transformer).
2. Katak kebradores sirkuitu maka'as liu (over current breakers) tenke iha abilidade atu kebra/hapara korrente sirkuitu badak (short circuit current) ne'ebé atravessa husi kebradores (breakers).

### **(2) Sirkuitu Kebradores (Circuit Breakers) Falhansu Rai-Okos (Ground Fault)**

Sirkuitu Kebrador falhansu rai-okos tenke ser instala iha pontu korrente sai (outgoing point) husi subestasaun ka fatin hanesan. Katak sirkuitu kebra/hapara (breaks circuit) automatikamente wainhira falhansu rai-okos akuntese iha liñas.

### **(3) Hapará Sobretensaun (Surge Arresters)**

Atu prevene ekipamentu eléktrika ne'ebé estragu hela husi rai-lakan(pilas), Hapará Sobretensaun (surge arresters) tenke ser instala iha fatin kritical sira husi liñas hanesan tuir mai;

1. Lidera ba liña despeza jéral (overhead) husi subestasaun.
2. Pontu koneksaun husi despeza jéral (overhead) liñas alta-tensaun ba transformador prinsipal.

## **2.12 Transformadores Distribusaun**

Transformadores Distribusaun tenke ser instala laos deit iha fatin perigu kontra choke elétrika iha métodu hirak tuir mai.

1. Transformadores Distribusaun tenke ser instala iha Altura husi 5.0m ka a'as liu rai para nune'e ema labele bo'ok sira ho fasil.
2. Lutu Apropriadu tenke ser halo hale'u fatin Transformadores Distribusaun. Mancira seluk, partes kobradu husi transformadores distribusaun labele nakloke para prevene husi bo'ok.

## 2.13 Standar Tensaun (Standard Voltage)

Standar Tensaun tenke ser mantein mínimu entre 94% no máximu 106% husi Tensaun nominal.

Liña 150kV tenke ser mantein entre 141kV no 159kV.

Liña 20kV tenke ser mantein entre 18.8kV to'o 21.2kV.

Liña 220V tenke ser mantein entre 216.2V to'o 243.8V.

## 3 VERIFIKASAUN Iiu-husi MEDISAUN (MEASUREMENT)

### 3.1 Resistênsia Ligasaun-Rai (Earthing Resistance)

#### KONSEITU BAZE BA LIGASAUN-RAI

Objetivu Ligasaun-Rai iha sistema tensaun eléktrika jeralmente mak :

1. Fornese proteasaun perigu ba ema ne'ebé uza eléktrik no ambiente.
2. Hetan distribusaun konfiabilidade iha sistema diak husi termus de qualidade, konfiabilidade no continuidade distribuisaun enerjia eléktrika.
3. Limita aumenta tensaun ba fasa/Ligasaun-Rai ne'ebé laiha ligasaun ba rai no válor mínimu tensaun servisu.

Iha rede distribusaun enerjia eléktrika iha pontus númeru Ligasaun rai diak ba médiu tensaun no ba parte baixa tensaun mak:

1. Ligasaun-Rai ba konstrusaun rede distribusaun
  - a.Ligasaun-Rai pontu neutral transformador iha sentral transformador
  - b.Ligasaun-Rai pontu neutral transformador iha parte baixa tensaun(sekundariu) iha distribusaun transformador
  - c.Ligasaun-Rai kondutor neutral iha parte médiu tensaun no baixa tensaun
  - d. Ligasaun-Rai ba kondutor rai-laran (*shield wire*) iha parte baixa tensaun
  - e.Kamada protetora Ligasaun-Rai hanesan cobre/tembaga, aço/baja iha fiu rai-okos
2. Ekipamentu protetora Ligasaun-Rai no Medisaun
  - a. Ligasaun-Rai *Lightning Arrester*
  - b. Ligasaun-Rai CT/PT
3. Ligasaun-Rai iha parte kondutor nakloke no Ekstra (BKT and BKE)

- a. Ligasaun-Rai isin (panel) PHB-TM, PHB-TR, Kabel Tray/Rak Kabel
- b. Ligasaun-Rai kruz (*cross arm/travers*)
- c. Ligasaun-Rai parte husi metal ne'ebé laos parte instalasaun  
exemplu odamatan transformador, lutu besi.

## LIGASAUN-RAI PONTU NEUTRAL PARTE SEKUNDÁRIU HUSI TRANSFORMADOR FORSA IHA TRANSFORMADOR PRINSIPAL KA GENERADOR

Enrolamentu transformador eléktrika iha transformador principal ka gerador parte sekunder (20 kV) iha forma pontu sirkuitu estrela. Pontu estrela mak liga ho maneira :

1. Liu husi resisténsia :
  - a. Resisténsia baixa 12 Ohm, 40 Ohm
  - b. Resisténsia baixa liu (Ligasaun dereta /solid grounded)
  - c. Resisténsia alta 500 Ohm
2. La liga ba rai(Ligasaun-rai flutuante),exemplu ba rede médiu tensaun iha PLTD ki'ik

Valor Ligasaun-rai inklui várius tipus konstrusaun rede,sistema protesaun no aproximasaun ba servisu rede distribuisaun.

**Ligasaun-Rai ho valor baixa resisténsia 12 Ohm no 40 Ohm**

Ligasaun-Rai ho valor baixa resisténsia mak utiliza iha transformador prinsipal/subestasaun iha sistema :

1. Resisténsia 12 Ohm ba transformador ne'ebé serve rede fiu rai-okos.  
Valor sirkuitu korrente máximu rai-okos 1000 Ampere.
2. Resisténsia 40 Ohm ba transformador ne'ebé especialmente serve b  
aliña aero médiu tensaun. Valor korrente máximu ba sistema  
tensaun 20 kV mak máximu 300 Ampere.

Valor korrente bo'ot sirkuitu husi Ligasaun-Rai fasilita protesaun obra atraza no permite protesaun atraza obra ho relativu baratu. Valor korrente sirkuitu la suficiente atu hakotu fuse cut out karik iha kazu parte mak badak ba sirkuitu rai-okos iha parte ne'ebé protezidu.

Ligasaun-Rai ho valor resisténsia 12 Ohm especialmente utiliza transformador eléktrika mak-ne'ebé fornese enerjia eléktrisidade ba iha fiu rai-okos iha area PLN/EDTL.

### 10.2.2 Ligasaun-rai ho valor resisténsia ne'ebé ki'ik liu (solid grounded)

Iha parte sistema valor Ligasaun-rai 20 kV husi transformador principal konekta direktamente ba rai okos. Sistema ne'e fornese benefisiu ba rede distribusaun mak :

1. Korrente falhansu ne'ebé luan tebes, nune'e fasil para koordena retransmiti. *Fuse cut-out* (FCO) utilize hanesan seguransa rede fasa rai okos ne'ebe bele servisu ho efektivu.
2. Koveransa rede distribusaun ne'ebé extensivu.
3. Ho sistema multigrounded common neutral iha rede MT/TM, possibilidade ba sistema fasa-1 iha rede MT/TM atu enerjia areia remotu ho kustu investimentu ne'ebé barratu.

Sistema Liagasaun-Rai ne'e utilizada iha areia distribusaun PT. PLN Persero central Jawa no Jogjakarta. Nune'e atu utiliza sistema *multi-grounded common neutral*, konstrusaun iha rede laran husi kada sistema konstrusaun mak diferente oitoan iha fatin balun que spesial ba rede liña aero husi médiu tensaun, espesifikasaun transformador no sistema liña aero ba baixa tensaun. Korrente falhansu rai-okos mak maka'as tebes, haktuir ba parte ki'ik husi disorder impedementu. Ai-rin no parte kondutor hotu-hotu nakloke iha rede ne'ebé konnekta ona ho hamutuk kondutor neutral ne'ebé iha kada ai-rin ne'ebé konnekta ba rai laran. Valor máximu husi Ligasaun-rai mak máximu 5 Ohm.

#### Ligasaun-Rai ho valor resisténsia a'as

Iha sistema ne'e valor resisténsia ligasaun-rai iha sikun 20 kV transformador enerjia iha transformer prinsipal ka gerador máximu 500 Ohm.

Ligasaun-Rai ho valor resisténsia a'as hodi nune'e impede dizorden tama iha rai-laran maka relativu ki'ik oan, valor maximu mak 25 Ampere. Valor korrente hanesan ne'e sei fornese tensaun maximu 125 Volt karik akuntese kotu ba liña rede aero iha médiu tensaun no kona rede baixa tensaun nune'e seguransa jeral maka seguru liu.

#### Ligasaun-Rai Flutuante

Ligasaun-rai flutuante agora dadaun iha PLN uza de'it hodi enerjia ba sistema eléktrisidade area rural nu'udar fonte eneja, no laiha ligasaun-rai ba transformador 20 kV, maibé iha ligasaun-rai existe ba

*lightning arrester* (LA) iha parte transformador sekundáriu no iha parte husi rede kondutor ne'ebé nakloke/molik. Ligasaun-Rai ba rede baixa tensaun utiliza sistema TN-C, maibé só iha de'it ba ai-rin 1(ida) antes ai-rin feeder prinsipal no kondutor ne'eb'e bo'ot liu.

#### LIGASAUN-RAI PONTUS NEUTRAL HUSI TRANSFORMADOR DISTRIBUSAUN

- Pontus neutral husi transformador parte husi baixa tensaun hakoi tiha ho kondutor cobre ne'ebé ho medida hanesan ho kondutor neutral husi fiu transformador hatama ba PHB-TR9(baixa tensaun). Karik akuntese rede fasa ida de'it la bele hasa'e tensaun ba fasa sira seluk.
- Valor resisténsia elektorada Ligasaun-rai la bele liu husi 1 Ohm  
Pontus Ligasaun-rai neutral iha betaun transformador neutral bele utiliza dalan rua:
  - a. Kondutor Pontus Neutral husi transformador hakoi tiha iha liur husi instalasaun transformador Liagasaun-rai ne'ebé bele iha ai-rin primeiru husi dalan aero baixa tensaun ka iha primeiru husi PHB husi fiu ligasaun-rai ba baixa tensaun iha kondutor neutral. Massa trafo no panel PHB hakoi separadu tiha.
  - b. Kondutor Pontus neutral husi transformador hakoi tiha iha ekipamentu sirkuitu ba baixa tensaun. Ligasaun-rai utiliza kondutores cobre/tembaga ho cross section mai menus 50 mm<sup>2</sup> no konekta hamutuk ho ligasaun-rai konduktivu ne'ebé nakloke/molik (massa trafo, kubikel/panel dll )

#### LIGASAUN-RAI BA REDE DISTRIBUSAUN BAIXA TENSAUN

1. Ligasaun-rai proteje ba rede baixa tensaun utiliza padraun TN-C. Rede kondutor neutral hakoi tiha iha kada ai-rin 5 (+/- 200 meter) ho pontus ligasaun-rai primeiru iha ai-rin segundu husi ai-rin ne'ebé háhu no ai-rin 1 (ida) antes ai-rin final/ikus-liu.
2. Valor bo'ot ba Ligasaun-rai elektroda máximu ida 10 Ohm. Resisténsia total ba ba transformador no JTR máximu 5 Ohm
3. Iha sistema *multi grounded common neutral* ba sistema kondutor neutral husi médiu tensaun mos sai nu'udar sistema husi kondutor

neutral ba médiu tensaun. Provizaun husi standar konstrusaun iha PLN distribusaun sentral Jawa ba kada ai-rin, kondutor mak konekta ho terminal husi ai-rin ligasaun-rai nian, maibe koneksaun ho elektroda ligasaun-rai konstrui/harii iha kada ai-rin 5(lima).

#### LIGASAUN-RAI BA TRANSFORMADOR DISTRIBUSAUN

Parte sira ne'ebé hakoi iha transformador distribusaun mak:

1. Parte kondutor hotu-hotu ne'ebé nakloke/molik (BKT) no parte husi kondutor Ekstra (BKE) exemplu mak odamatan transformador, panel kubikel.
2. Terminal neutral iha parte husi transformer distribusaun ba baixa tensaun
3. Kamada protektivu fiu eléktika husi médiu tensaun iha parte husi kubikel
4. *Lightning Arrester* iha portal husi transformador

Keta hakoi ketak-ketak ba kada parte sira ne'e, além husi Ligasaun-rai ba lightning arrester/hapara rai-lakan. Partes husi kondutor ligasaun-rai sei bele konekta ba sesaun kondutor rai-lakan mak ligasaun ho ekipotensial hamutuk ida, ikus-mai ligasaun ekipotensial hakoi tia , nune'e gradiente tensaun sa'e hasoru rai tamba distrubansia iha parte hotu husi instalasaun ba magnitude ne'ebé hanesan.

Valor resisténsia Ligasaun-rai la bo'ot liu husi 1 Ohm (1,7 Ohm iha livru padraun konstrusaun DJBB).

#### LIGASUN-RAI KONDUTOR RAI (*SHIELD WIRE/EARTH WIRE*)

Jeneralidade kondutor rai ka *earth wire/shield wire* mak la uja ida.

Kondutor ne'e monta iha rede SUTM(Liña aero ba médiu tensaun) nia leten iha area husi akuntese frequentemente rai-lakan ka area ne'ebé nakloke no direktamente konekta no hakoi iha ai-rin. Utilizasaun husi kondutor rai tenke ser diak iha iha revista hanesan nivel existe hela. Monta iha area husi edifisiu/ai-hun mak-ne'ebé a'as liu husi rede ne'ebé ladun efektivu.

#### HAPARA RAI-LAKAN/LIGHTNING ARRESTER HUSI LIGASAUN-RAI

*Lightning Arrester* (LA) hakoi ketak-ketak tiha ho elektroda . Iha tipu portal husi transformador distribusaun, ligasaun-rai pontu neutral husi transformador mak ketak-ketak ho elektroda ligasaun-rai husi

### *Lightning Arrester.*

Nune'e atu hetan tensaun hanesan ho gradient tensaun iha rai, kondutor ligasaun-rai husi *Lightning arrester* ho parte husi pontu neutral iha baixa tensaun transformador distribusaun mak mekanikamente konekta (iha ligasaun) iha rai-okos.

Ba transformador (portal) no transformador (eskápulu) kondutor ligasaun-rai husi *lightning arrester* sai ida de'it ho transformador nia isin-lolon no hafoin hakoi tiha.

Resisténsia Ligasaun-rai tenke ser sukat liu-husi métodu inspesaun ne'ebé mak hatudu iha okos haktuir ba sistema ligasaun-rai/ earthing system (hakerek iha IEC 60364-5-54). Ida ne'e la persija atu sukat ligasaun-rai hotu-hotu, maibe amostra/sample medisaun tenke ser realizadu/hatudu.

Item	Métodu Inspesaun	Kritériu
Sistema Ligasaun-rai iha parte sekundáriu husi transformador/subestasaun ligasaun-rai klasse _ B	Measurement by earth Metru resisténsia	10 $\Omega$ ka menus
Ligasaun-rai protektiva ba equipamentu HV inklui transformadores Ligasaun-rai klasse _ A	Ditto	10 $\Omega$ ka menus
Surge Arrester Earthing/Hapara pilas	Ditto	10 $\Omega$ ka menus



### 3.2 Resistência Isolamentu

#### OVERHEAD TRANSMISSION LINE ALUMINIUM ALLOY CONDUCTOR AND XLPE SHEATHED

Type of Cable : AAAC-S

SPECIFICATION : SPLN 41-10  
SPLN 41-8

#### CONSTRUCTION

Size of Cable	Number / Diameter of Wire	Nominal Thickness of Sheath	Approx. Overall Diameter	Approx. Weight of Cable	Standard Length per Drum
mm <sup>2</sup>	n / mm	mm	mm	kg/km	m
35	7 / 1.50	3.0	13.9	204	2,000
50	19 / 1.75	3.0	15.2	244	2,000
70	19 / 2.25	3.0	17.7	353	2,000
95	19 / 2.50	3.0	18.9	415	2,000
120	19 / 2.75	3.0	20.2	483	2,000
150	19 / 3.23	3.0	22.6	528	1,000
150	37 / 2.25	3.0	22.2	594	1,000
185	37 / 2.50	3.0	23.9	707	1,000
240	61 / 2.25	3.0	26.7	900	1,000


#### CHARACTERISTICS

Size of Cable	Maximum DC Conductor Resistance at 20 °C	Maximum Current Carrying Capacity		Calculated Breaking Load of Conductor	AC Voltage Test
		at 30°C	at 40°C		
mm <sup>2</sup>	ohm/km	A		N	kV / 5 min.
35	0.958	167	150	9,615	13
50	0.724	200	180	12,750	13
70	0.438	275	240	11,090	13
95	0.355	315	282	16,095	13
120	0.293	356	319	31,590	13
150	0.210	423	378	44,045	13
150	0.225	423	378	41,105	13
185	0.183	484	431	50,755	13
240	0.139	586	523	67,785	13

Medisoens resistênsia Izolamentu konfirma ba adequasaun husi liña distribusaun.

Item	Métodu Inspesaun	Kritériu
Liña tensaun 20kV	Resistênsia Izolamentu mak sukat haktuir tester resistênsia izolamentu 1,000V. Valor medisaun tenke ser adopta ba valor 1-min. Karik indikasaun mak la stabel tamba-de'it kapasidade karrega bo'ot husi medisaun sirkuitu, valor medisaun tenke ser adopta hafoin valor sai stabel. (Ne'e la persija atu mantein medisaun bo'ot liu husi 3min.)	Izolamentu husi fazes-Rai okos no faze-faze tenke ser adequadu  (2,000M $\Omega$ ka liu)
Ekipamentu tensaun 20kV	Ditto	Ditto
Subestasaun	Ditto	Ditto


[exemplu husi medisaun liña tensaun 20kV]

	Sukat Fatin	
Fiu ba Rai	Measure the insulation resistance between wire to earth which is connected to a transformer, a lightning arrester, or a switch.	(Agora laiha fotografía.)
Fiu ba fiu faze seluk	Sukat resistênsia izolamentu entre fiu ida ho fiu faze seluk antes trasformadores konekta ba liña sira ne'e.	

[exemplu husi medisaun transformador]

	Fatin Sukat	
Fiu Primeiru ba transformador Rai nian	Sukat resistênsia izolamentu husi fiu primeiru ba transformador Rai nian, husi fiu segundu ba fiu transformador nian, no husi fiu primeiru ba fiu segundu.	(Agora laiha fotografía.)
Fiu Segundu ba fiu transformador nian		
Fiu Primeiru ba fiu segundu		

[exemplu husi medisaun hapará rai-lakan/pilas (lightning arrester)]

	Fatin Sukat	
Fiu Primeiru ba Hapará Rai-lakan nian (lightning arrester's earth)	Sukat resistênsia izolamentu husi fiu primeiru ba ekipamentu rai nian mak-ne'ebé konekta transformador, hapará rai-lakan ( lightning arrester), ka switch.	<p>Laiha Hapará rai-lakan rua ( lightning arresters) iha fotografía ida-ne'e. Karik iha Hapará Rai-lakan tolu (lightning arresters), Ita-bo'ot tenke sukat sira ne'e hotu.</p> 

## 4. Liña Ministéris

### 4.1 Avaliasaun Projetu molok Adjudikasaun Kontratu

#### 4.1.1 Fluxograma




Figura 1. Projetus Liña Ministéris

#### (1) LM (Liñas Ministéris)

LM prepara kontratu ba Konsultor ruma mak seleksiona hodi halo Dezeñu projetu ne'ebé detalhu. LM mak fundamental sai Na'in ba projetu.

#### (2) Consultant Design (Konsultor Dezeñu)

Konsultor hala'o servisu bazeia ba TOR ne'ebé estabelese ona. Depois de remata dezeñu projetu, Konsultor refere sei entrega ba LM hodi submete fila fali mai iha ADN.

#### (3) ADN (Agência Desenvolvimento Nacional)

Iha biban ne'e, ADN sei verifica dokumentus tender ne'ebé entrega husi LM karik dokumentus ne'ebé entrega completa ona. Hafoin verifica saun completa, ADN sei entrega hikas ba LM hodi loke prosesu tender iha Ministério ka Secretário de Estado.

#### (4) LM (Liñas Ministéris)

LM mak responsabiliza ba projetu.

#### (5) LM, ADN

LM sei resubmete, karik dokumentus ne'ebé entrega ona seidakompleta. Hotu tiha, ADN sei verifica ba dokumentu.

#### 4.1.2 Oráriu Obra

(1). Tempu Reklamadu ba verifikasaun iha ADN

ADN sei kompleta verifikasaun ba dokumentus konkursu/tender durante loron sanulu (10 ) nia laran (loron servisu) após simu ofisialmente dokumentus reklamadus husi LM. Karik dokumentus ne'ebé entrega sedauk kompleta, ADN ho esforsu tomak hodi kontakta LM atu kompleta liu tan dokumentu hirak ne'e.

(2). Tempu ba submisaun adisional, resubmisaun ka responde ba perguntas ADN, LM tenke submete, resubmete ka responde ba ADN saida mak reklama husi ADN durante semana (2) após simu notifikasaun husi rekerementu para informasoens seluk-seluk tan depende ba tipu husi projetu.

(3). Iha kazu husi sub-klauza (2) iha leten, tempu ba ADN atu kompleta verifikasaun tenke ser atraza iha tempu ne'ebé hanesan haktuir implementasaun husi LM ba submisaun adisional, resubmisaun ka responde.

#### 4.1.3 Konfirmasaun ba dokumentu ne'ebé submete ona:

ADN sei revista karik rekerementu dokumentus hotu-hotu entrega tiha ona. Karik iha kazu buat ruma ne'ebé falta, ADN sei informa ba LM kona-ba ne'e no instrui LM hodi submete iha tempu espesifiku nia laran.

(1) Karta pedidu verifikasaun ba dokumentus tender : **formatu-A**

(2) Project Outline/delinear projetu preparadu husi LM; **formatu B**

(3) Dokumentus Konkursu : ADN sei konfirma rekerementu dokumentus ne'ebé submete tiha ona, utiliza **Lista Verifikasaun-A**

- 1) Konvite ba Lisitasaun/tender
- 2) Instrusaun ba Lisitatante sira
- 3) Formatu husi lisitasaun no Dadus Kualifikasaun
- 4) Kondisoens Kontratu
- 5) Dadus Kontratu
- 6) Lista Kuantidade/BOQ
- 7) Formatu husi Seguransa
- 8) Espesifikasoens
- 9) Dezeñu/drawings
- 10) Seluk-seluk tan, karik nessesáriu

#### 4.1.4 Verifikasaun ba kondisoens pagamentu: ADN sei verifika kondisoens pagamentu ne'ebé adekua, utiliza Lista Verifikasaun-B.

(1) Tempu para kompleta/Periódú konstrusaun

ADN sei verifika kona ba tempu ne'ebé hodi kompleta ká periodu ba konstrusaun hanesan maneira,

- 1) Verifika oráriu konstrusaun detallu fornese husi LM,
  - 2) Iha esplikasaun husi LM kona-ba oinsá sira desidi tempu ká periodu
  - 3) Kompara ho tempu kompleta obra seluk ké hanesan.
- (2) Períodu Manutensaun/ Períodu Notifikasaun ba Estragu/Períodu Responsabilidade Estragu
- 1) Iha esplikasaun husi LM konaba oinsá sira desidi tempu ká periodu,
  - 2) Kompara ho tempu kompleta obra seluk ké hanesan
- (3) Lei Governu nian (Ukun-fuan Fovernu nian)  
Lei Governu mak Lei Repúblika Demokrátika de Timor Leste.
- (4) Regulamentu língua  
Regulamentu língua mak Inglês
- (5) Exekusaun Di'ak/ Guaranti ba Exekusaun Di'ak  
Montante Mínimu Guaranti ba Exekusaun Di'ak mak hanesan prosentajen ba montante kontratu hanesan dadus passadu hatudu 10% to'o 20% bazea ba total pagamentu adiantadu.
- (6) Demora estragus ba obra/ Multas  
Multas ba obra tomak mak 0,1% ba Presu kontratu final kada loron.
- (7) Montante Mínimu ba demora estragus.  
Montante Mínimu husi demora estragus/Multas ba projetus passadu mak 10% husi montante kontratu
- (8) Montante Provizóriu(Provisional sum)  
Montante Provizóriu ba projetu passadu mak 5% to'o 15%
- (9) Total Pagamentu Adiantadu  
Total Pagamentu Adiantadu ba projetu passadu mak 10% to'o 20%
- (10) Prosentajen Retensaun  
Prosentajen Retensaun ba projetu projetu passadu mak 10%
- (11) Limitasaun ba Orsamentu Retensaun  
Limitasaun ba Orsamentu Retensaun ba projetu passadu mak 10% husi montante kontratu ne'ebé aseita.
- (12) Montante Mínimu ba Sertifikadu Pagamentu Provizóriu  
Montante Mínimu ba Sertifikadu Pagamentu Provizóriu mak entre 25%, 50%, 75%, ká 100% husi montante kontratu bazea ba kontratu orijinal.

4.1.5 Verifikasaun Téknika utiliza lista verifikasaun(Checklist): ADN sei verifika

téknikamente dokumentus ruma hanesan BOQ, dezeńu no spesifikasaun sira, utiliza lista verifikasaun- C.

Uza lista verifikasaun-C kona ba projetu Uma nian

Projetu Uma nian (Lista verifikasaun C)

(1) Antecedentes(background)

Verika antecedentes husi projetu no planu viabilidade. Konfirma adekuadamente entre projetu no antecedentes.

(2) Objetivus

Konfirma adekuasaun ba projetu, konsidera ba efikâsia no potênsia ekonómia no efisiênsia.

(3) Âmbitu husi Obra

Konfirma âmbito hotu-hotu husi obra iha dokumentu tenderizasaun.

(4) Relatóriu no Oráriu Tempu

Konfirma razoabilidade kona-ba oráriu tempu, konsidera tempu mobilizasaun, tempu inundasaun, etc

(5) Espesifikasaun

Espesifikasaun téknika tenke tuir padraun(standard)/kódigu, “ne’ebé ekuivalente ká qualidade aas-liu” duké spesifikasaun baibain?

(6) Padraun(standard) ká Kódigu

Laiha lei edifísiu/uma, kódigu & padraun(standard) iha Timor Leste.

Konfirma kódigu edifísiu/uma” Australia (AS) no Australia/Nova Zelandia (AS/NXS)” ká “ Padraun Edifísiu Indonésia (SNI 2002)”.

(7) Qualidade

Haktuir spesifikasaun/kódigu tékniku etc.

Amostra(sample) spesifikasaun material

1) Spesifikasaun Konkretu (haktuir ba NP EN 206-1,2007;

Klassifikasaun Inspesaun 2; Durasaun-vida(lifetime) tinan 50)

2) Besi-betaun(rebar steel) NP ENV 13670-1)

(8) Lista Kuantidades/BoQ

Verifika Lista kuantidades, unidade presu no montantes husi item bo’ot ruma, evita sala/erru ne’ebe fásil. Konfirma lolos entre dezeńu iha dezeńu arsitektura, dezeńu estruktural, no estabelesimentu dezeńu iha mekániku,elétriku, no dezeńus Hidráuliku.

(9) Dezeńu

Veifika spesifikasaun detailla no kódigu iha dezeńus.

#### (10) Âmbitu husi konstrusaun

Verifika a âmbito husi konstrusaun indika iha dezeńu no espezifikaun sira.

**4.1.6 Rona husi LM:** ADN sei rona husi LM oinsá sira bele atinji solusaun ikus nian, iha lia fuan seluk, karik kompara ona ho alternativus seluk.

Ne'e defisil tebes atu verifika Dokumentus tender barak tebes ké simu horseik iha lora hirak nia laran. Ne'e bele rekomenda tebes ba enjineiru ADN foin sae sira hodi estuda Dokumentus tender no prepara antesipadamente perguntas ba nia-an rasik iha akordu ho manual ne'e utiliza lista-verifikaun (checklist) anexada iha-ne'e, hodi bolu enjineiru LM no konsultan dezeńu mai ADN, no husu perguntas no tesi-lia.

Ida-ne'e sei ajuda enjineiru ADN sira guarda tempu ba verifikaun, no hasa'e sira nia kapasidade.

**4.1.7 Oráriu Verifikaun:** ADN sei prepara oráriu, iha-ne'ebé ne'e permiti funsionáriu ADN atu kompleta verifikaun obra durante iha tempu ne'ebé defini ona.

Oráriu Verifikaun Dokumentus tenderizasaun ne'ebé aperta tebes , iha kalendáriu lora 10 deit, hafoin simu dokumentus ne'ebé entrega.

Ne'e Rekomenda hodi prepara oráriu ba verifikaun, no tuir oráriu, prosesu hosi ida ba ida, hosi lora ba lora.

Exemplu oráriu verifikaun ne'ebé hatudu iha okos ba lora 3 operasaun [lora 1 to'o lora 3].

(1) Verika karik dokumentus submetidu ne'ebé utiliza lista-verifikaun/checklist A.

Karik lae, informa ba LM katak dokumentus la suficiente, no verifikaun sei komesa iha lora tuir-mai husi simu dokumentus adekua.

(2) Wainhira dokumentus reklamadu sira ne'e hotu entrega ona, komesa verifika kondisaun pagamentu /anexa ba tenderizasaun/kondisaun partikular, iha konkordansia ho manual ne'e utiliza lista-verifikaun B.

(3) Prepara perguntas iha akordu ho manual ne'e utiliza lista-verifikaun C, ba projetu Uma nian.



(4) Arranja Entrevista ho LM no nia konsultan ba perguntas tékniku iha loron segundu.

[loron 4 to'o loron 6].

(5) Husu pergunta kona ba kestaun tékniku ne'ebe ita boot prepara.

(6) Karik sira nia resposta la satisfeito ka resposta la'dun klaru tamba menus dados, hato'o ba sira atu prepara data suficiente para explika, hafoin arranja entrevista tuir-mai. Loron ikus kona ba entrevista tuir-mai mak loron segundu husi verifikasaun.

(7) Hatete LM hodi kompleta dokumentus korreksaun hotu-hotu, hatama hikas fali

[loron 7 to'o loron 10]

(8) Verifika deit porsaun koriji ona, no manda sira ba LM, wainhira dokumentus korrijidu ne'ebé entrega ona.

(9) Entantu katak koreksaun mak la satisfeito, halo hanesan pontu (3) iha leten.

**4.1.8 Remédiu/reparasaun:** iha kazu problemas ruma ne'ebé rezulta dokumentus verifikasaun, ADN sei informa ba LM kona ba problemas no oinsá atu resolve.

Obra Verifikasaun sei demora husi lakon tempu ba resubmissaun.


#### **4.1.9 FAQ (Frekuentamente/Nafatin husu perguntas )**

Iha kursu verifikasaun dokumentus tender, enjiñeiru ADN sei iha perguntas no problemas oin-oin, no rezolve problemas ho ajudu husi enjiñeiru senior sira to'o sira toman atu kompleta sira nia servisu. Ne'e rekomenda ba enjiñeiru sira sé-mak atu rezolve problemas sira ne'e rai inskrisaun iha "Livru FAQ".

Livru FAQ bele ajuda enjiñeiru seluk ne'ebé hasoru problema hanesan.

## 4. 2: Inspesaun Regular ba Pagamentu & Rekomendasaun ba Pagamentu

### 4.2.1 Fluxograma



#### (1) Empreza Kontratante

Hatama Invoice ba iha LM haktuir ba progressu fiziku obra nian iha terrenu maibé relatóriu progressu tenke hetan aprovasaun husi Konsultor supervisaun.

#### (2) LM (linã Ministeriais) no (Empreza Kontratante fiskalizador)

LM simu Invoice husi Empreza Kontratante/kontraktor bazea ba relatóriu progressu ne'ebé hetan tiha ona revista ba-mai/cross-check husi kompañia supervizaun no hetan aprovasaun husi Secretário do Estado ká Ministro/a hodi prepara Sertifikadu Pagamentu no Sertifikadu refere hetan autorizasaun husi Secretário do Estado ká Ministro/a. Hafoin LM submete Karta Pedidu ba ADN, anexa mós dokumentus relevante kompletu.

#### (3) ADN

Simu dokumentus pedidu ba Inspesaun ida-ne'ebé anexada dokumentus Pagamentu hodi realiza inspesaun. Depois inspesaun hotu, ADN sei prepara Relatóriu Inspesaun no Rekomendasaun Pagamentu entrega ba LM , atu nunc'e LM bele submete ba Tezouru hodi hetan TPO (Orden pagamentu husi Tezouru/Treasury Payment Order).

#### (4) Tezouru

Tezouru sei prepara TPO (Orden pagamentu husi Tezouru/Treasury Payment Order)

hafoin TPO ne'e manda ba Banku Sentral (BPA).

**(5) BPA/Banku Sentral**

Halo pagamentu ba Konta Bankária Kompañia nian.

**(6) Konta Bankária Kompañia**

Kompania sei simu osan ne'ebé transfere iha sira nia Konta Bankária rasik.

#### 4.2.2 Oráriu Obra

**(1) Rekere tempu ba verifikasaun iha ADN**

ADN tenke kompleta dokumentus inspesaun ba pedidu pagamentu durante semana rua (2) nia laran depois de simu oficialmente dokumentus rekerementu husi ADN.

**(2) Tempu ba submisaun adisional, resubmisaun ka responde ba**

perguntas ADN nian, LM tenke submete, resubmete ka respode ba ADN saida mak rekere husi ADN durante semana rua(2) ni laran depois de simu notifikasaun husi rekerementu mais informasaun detalhu.

**(3) Iha kazu husi sub-kauza rua (2) iha leten, tempu ba ADN atu**

kompleta verifikasaun tenke ser atraza iha tempu hanesan ho tempu ne'ebé LM foti ba adisional submisaun, resubmisaun ka responde ba Dokumentus inspesaun.

#### 4.2.3 Dokumentu Inspesaun

**(1) Konfirmasaun ba dokumentus submetidu: ADN sei revista karik dokumentus rekerementu hotu-hotu hatudu iha okos entrega tiha ona utiliza lista verifikasaun-D. Iha kazu buat ruma mak falta, ADN sei informa ba LM kona ba ne'e no instrui/haruka LM hodi submete/entrega iha tempu espesífiku nia laran.**

1) Karta pedidu inspesaun husi LM hato'o ba ADN : **formatu –C**

2) Partes husi dokumentu kontratu, hatudu montante kontratu no kondisoens pagamentu.

3) Lista Kuantidade/BOQ hatudu presu unidades no kuantidades

4) Deskrisaun husi mudansa, alterasaun ka variasaun, karik iha

5) Relatóriu inspesaun Terrenu husi LM

## 6) Dadus Dijital husi BOQ

- (2) Konfirmasaun husi kondisoens pagamentu hanesan pagamentu adiantadu no retensaun:

ADN tenke halo serteza kondisoens pagamentu hirak ne'e mak tuir los-los deskrisaun husi dokumentu kontratu.

- (1) Kalkulasaun iha folha faturamentu
- (2) Konfirmasaun husi remata obra iha BOQ, dezeńu no fotografía
- (3) Konfirmasaun ba oráriu obra
- (4) Konfirmasaun ba rezulta inspesaun husi LM
- (5) Emite relatóriu inspesaun no rekomendasaun ba pagamentu :  
formatu-D

### 4.2.4 Inspesaun Terrenu

- (1) Preparasaun

ADN manda Pedidu Preparasaun husi Inspesaun Terrenu ba ADN uja formatu-E iha loron hitu (7) molok inspesaun.

- 1) Atendentes

LM tenke konvida sira hotu iha kra'ik ne'e ba inspesaun terrenu.

- Inspetór husi ADN
- Enjeñeiru husi Liña Ministériu
- Konsultan Supervizaun
- Emprezáriu/Kontraktor

- 2) Preparasaun

LM tenke organiza buat hotu iha kra'ik ne'e iha inspesaun terrenu

- Arkivu/inskrisaun husi kontrolu kualidade
- Dezeńu
- Lista Kuantidade/BOQ Detaillu
- Ekipamentu Medisaun/sukat
- Asisténte para sukat/medisaun

- (2) Kontrolu kualidade

Arkivu ba kontrolu kualidade sei avalia husi ADN utiliza *Lista-verifikasaun/checklist E*.

Item verifika sira iha checklist ne'e hanesan amostra de'it, nune'e item própriu tenke ser aumenta depende ba situasaun.

(3) Medisaun/Sukat ba Obra ké kompletu ona

Obra ké Kompletu ona tenke ser sukat. Objektivu husi sukat/medisaun mak atu konfirma katak kuantidade atual husi kada item ké kompletu ona hanesan ho kuantidade husi pedidu iha Invoice laran.

(4) Rona husi enjeñeiru LM nian

ADN tenke rona husi enjeñeiru LM karik iha perguntas.

(5) Remédiu/Reparasaun(Remedy)

Wainhira ADN hetan buat ruma sala/non-conformant ká la satisfatóriu ba obra, ADN tenke haruka remédiu/hadi'a.

#### 4.2.5 Notifikasaun husi Julgamentu kona-ba pagamentu

Finalmente ADN tenke julga montante pagamentu sufisiente, notifika no rekomenda pagamentu ba LM, utiliza **Formatu C**. ADN manda orijinal ida no kopia rua husi dokumentus pagamentu ba LM, no rai kopia ida iha eskritóriu ADN.

#### 4.2.6 FAQ (Frekuetemente/Nafatin husu Perguntas)

Ne'e rekomenda maka'as tebes atu halibur no hakerek perguntas no resposta ne'ebé mosu hela de'it iha ADN relasiona ba pedidu husi inspesaun ba pagamentu.

Anexu -4. (Liña Ministéris)

Formatu-A (Karta Pedidu Verifikasaun ba dokumentus tender

Karta ulun/Kop husi Liña Ministéris

Data : \_\_\_\_\_ Fulan \_\_\_\_\_ Tinan

Número : Ministério/ Infra Unit/ \_\_\_\_\_ (númeru surat)  
Hato'o ba : Ex<sup>mo</sup>. Senhor Samuel Marçal  
Director ADN  
Iha Dili  
Assuntu : Pedidu Verifikasaun  
Projetu Fundo Liña Ministérial (Tipu husi projetu)  
Lokalizaun ( Fatin Projetu)

Atu responde ba pedidu verifikasaun ne'ebé regula iha regra legal ba prosesu tender, Ami (LM) informa katak sei hala'o prosesu tender ba projetu.....(projetu naran) ho No.Kontratu: RDTL.....  
Ho biban ne'e mos, ami submete mos kampania lisitante sira no sira nia profile ne'ebé anexa iha okos atu nune'e ADN bele halo verifikasaun no selekta kampania ne'ebé mak sei manan.

Ikus Liu, Ami hato'o agradese wa'in ba Ita nia kooperasaun.

Chefe de projeto

(.....)

Aprova husi Ministro/SOS

(.....)

Anexu

1. Períodu implementasaun (Konkluzau ba projetu)
2. Súmariu Projetu
2. Lista K uantidade (BOQ)
3. Dezeñu (Drawings)
4. Espesifikasaun téknika detalhadu
5. Medisaun (Measurement)
6. Lista no profile kampania Lisitante sira
7. Seluk-seluk tan, karik persija



## Formatu-C (Karta Pedidu Inspesaun husi LM hato'o ba ADN)

### Karta ulun/Kop husi Liña Ministéris

Data : \_\_\_\_\_ Fulan \_\_\_\_\_ Tinan

Número : Ministério/ Infra Unit/ \_\_\_\_\_ (númeru surat)  
Hato'o ba : Ex<sup>mo</sup>. Senhor Samuel Marçal  
Director ADN  
Iha Dili  
Assuntu : Pedidu Inspesaun  
Projetu Fundo Liña Ministérial (Tipu husi projetu)  
Lokalizaun ( Fatin Projetu)

Atu responde ba pedidu pagamentu ne'ebé submete ona husi kompania \_\_\_\_\_ (naran kompania), Ami (LM) informa katak sei hala'o inspesaun ba projetu \_\_\_\_\_ (projetu naran) ho No.Kontratu: RDTL \_\_\_\_\_, iha Loron \_\_\_\_\_ (data husi inspesaun). Ho biban ne'e mos, ami submete mos Invoice kampania nian no Relatóriu Progressu ne'ebé anexa iha okos atu nune'e ADN bele halo inspesaun no prepara relatóriu inspesaun no rekomendasaun ba pagamentu.

Ikus Liu, Ami hato'o agradese wa'in ba Ita nia kooperasaun.

Chefe de projeto

(.....)

Aprova husi Ministro/SOS

(.....)

#### Anexu

1. Períodu implementasaun (Konkluzo ba projetu)
2. Súmariu Projetu
2. Lista Kuantidade (BOQ)
3. Dezeñu (Drawings)
4. Espesifikasaun Téknika detalhadu
5. Medisaun (Measurement)
6. Invoice no relatóriu progressu husi kompania
7. Seluk-seluk tan, karik persija





**REPÚBLICA DEMOCRÁTICA DE TIMOR-LESTE**  
**GABINETE DO PRIMEIRO MINISTRO**  
**AGÊNCIA DESENVOLVIMENTO NACIONAL**

---

Data : \_\_\_\_\_, Fulan, Tinan

Hato'o ba : Director of Major Project Secretary (MPS)

Husi : Samuel Marçal (Karimbu no asina husi ADN)  
Director Geral ADN

Ref : \_\_\_\_\_ RDTL/ GPM /ADN / III / 20 \_\_\_\_\_

Assuntu : Pedidu Pagamentu

---

Relasiona ho Pedidu Pagamento  
No. \_\_\_\_\_ (No. Pedidu) husi  
companhia \_\_\_\_\_ (Naran companhia) ba  
projetu \_\_\_\_\_ (naran  
projetu) iha \_\_\_\_\_ (distrito)

(sub distrito) \_\_\_\_\_ (Suco). Ekipa Tékniku ADN ne'ebé hala'o ona  
inspesaun ba projetu refere rekomena bele halo pagamentu ba progressu ne'ebé iha.  
Nune'e Ami Husu ba Secretário de Grandes Projetos ( MPS ) wainhira atu exakuta  
prosesu pagamentu persija verifika fali pagamentu anterior.

Mak ne'e deit, ba Ita bo'ot nia kolaborasaun diak ami hato'o obrigado wa'in

Formatu ne'ebé exite hela



REPUBLICA DEMOCRATICA DE TIMOR LESTE  
GABINETE DO PRIMEIRO MINISTRO  
AGENCIA DESENVOLVIMENTO NACIONAL

No	RELATORIO	INSPECSAUN	NO	RECOMENDASAUN	BA	PAGAMENTO
A	Projecto nia Naran					
B	Ministerio/Dono de Projecto					LM
C	Fontes de Fundos : ( PDD I, PDD II,PDL,FI,Emergencia,MDG Suco,etc)					
D	Contractor					
E	Numero PO (Purchase Order)					
F	Localizasaun Projecto :			B.Distrito :		
				b.Sub distrito :		
				c.Suco/Aldeia :		
G	Valor Contracto					
H	Progreso fisico iha fulan kotuk					
I	Progreso fisico ate agora					
J	Valor Pagamento foer ate agora (gross)			(9-8)*7		
K	Osan adiantamento nebe simu ona ...%			(...%*7)		
L	Deducsaun adiantado ba pagamento ida ne'e 10%			(9-8)*11		
M	Deducsaun retensaun ba pagamento ida ne'e			(10%*10)		
N	Valor pagamento depois de deducsaun ba retensaun			(10-13)		
O	Valor pagamento nebe atu selu ba pagamento ida ne'e			(14-12)		
P	Balansu depois de pagamento ida ne'e			7-(9*7)		
Q	Observasaun ou komentario:					
R	Recomendasaun ba MPS-MdF/Tezouro-MdF/Ministerio/Agencia Tutela Selu ho Montante (USD)					
S	Observasaun :			SIM	Komentarios	LAE
a	Tuir Dezenho ?			LAE		
b	Tuir BOQ ?			SIM		
c	Tuir Especificasaun ?			LAE		
d	Tuir Schedule curva S ?			SIM		
e	Tuir Termos de Contracto ?			SIM		
T	Data Inspeksaun			Data: 03-0	Fulan: 07	Tinan:2012
U	Engenheiro Nebe Halo Inspeksaun :			Assinatura:		Data :
	1. Maximos dos Santos			Assinatura:		Data :
	2. Camilio de Jesus			Assinatura:		Data :
				Assinatura:		Data :
V	Verifikado Hosi :			Assinatura:		Data :
	Miguel Marques Monteiro de Jesus			Assinatura:		Data :
W	Q.C.			Assinatura:		Data :
	Esron ST. Henuk			Assinatura:		Data :
X	Aprovado Hosi :			Assinatura:		Data :
	Sr. Samuel Marçal			Assinatura:		Data :
	Directur Geral - ADN.			Assinatura:		Data :
Y	Anexo :			Fotografias Ruma Hosi Terreno		

Propoin Folla Foun

No	RELATORIU INSPEKSAUN NO REKOMENDASAUN BA PAGAMENTU		
1	Projeito nia Naran		
2	Ministerio/Dono de projeto		
3	Fonte de fundos ( PDD I, PDD II ,MP, Emergencia, etc)		
4	Contractor		
5	Numero PO (Purchase Order)		
6	Localizasaun Projeto :	a) Distrito :	
		b) Sub distrito :	
		c) Suco/Aldeia :	
7	Valor Contracto		
8	Valor pagamento foer ate agora (gross)		
9	Billing(faturamentu) ih invoice husi emprezariu		
10	Billing(faturamentu) verifikadu husi Inspector		
11	Osan adiantamento nebe simu ona ....%	(7)*10%	
12	Deducsaun adiantado ba pagamento ida ne'e 10%	(11)*((10)/(7))	
13	Deducsaun retensaun ba pagamento ida ne'e	(10)*10%	
14	Valor pagamento depois de deducsaun ba retensaun	(10)-(12)-(13)	
15	Liberasaun ba iha retensaun anterior (50%)		
16	Valor pagamento nebe atu selu ba pagamento ida ne'e	(14)+(15)	
17	Balansu depois de pagamento ida ne'e	(7)-(8)-(16)	
18	Progreso fisico iha fulan kotuk %	(8)/(7)	
19	Progreso fisico ate agora %	(10)/(7)	
20	Documentos husi Inspeksaun	Dokumentos	Problema & Comentario ruma
a	Tuir Termos de Contracto ?	Yes/No	
b	Tuir BOQ ?	Yes/No	
c	Tuir Especificasaun ?	Yes/No	
d	Tuir Dezenho ?	Yes/No	
e	Tuir Schedule curva S ?	Yes/No	
f	Relatoriu inspeksaun husi Dono de Projeitu(EDTL ka distritu)	Yes/No	
g	Rezultadu teste ba Termu-Entrega	Yes/No	
h	Dezenha ba faturamentu ne'e	Yes/No	
21	<b>Rezultadu Husi Inspeksaun</b> { Rezultadu husi Dokumentu Inspeksaun nian } Revista item hirak nu'udar referencia: * Dokumentus ba invoice preparadu lo-los ? * Invoice ida ne'e atinji ba kondisaun pagamentu hanesan pagamentu adiantadu no retensaun ? * Kalkulasaun lo-los husi faturamentu(billing)? * Sei mantein loron completa nian? * Rezultadu husi teste (Teste de exekusaun) ba Termo-Entrega tuir kriteria? * Karik laiha inspeksaun terenu, Tenki ser mensiona razaun saida, exemplu; Montante ki'ik ba pagamentu interkalar, implementasaun husi vizita terenu liu-ba, Foto sufisiente ba verifikasaun qualidade, etc.  { Rezultadu husi Inspeksaun Terenu } Revista item hirak nu'udar referencia: * Dono de projeto (EDTL ka seluk ) mak atende mos iha terenu ka fo explikasaun iha edefisiu? * Komponentes importante ba funsaun no komponentes volume bo'ot iha BoQ revista tiha ona ? * Problema ruma iha qualidade ( Qualidade ladiak husi material no instalasaun, rezultadu teste alem de criteria, etc.)? * Problema ruma iha quantidade ( Diferenti entre figuras aktual no BoQ) ?  {Ajustamentu ba iha pagamentu } Revista item hirak nu'udar referencia: * Rekomendasaun pagamentu haktuir invoice ka lae ? * Karik Lae, Razaun husi avaliasaun ba redusaun ? * Rekomendasaun hadia(konsertu) saida mak kontra(hasoru) defeitu(estragu) ?		
22	Proposta pagamentu ih invoice husi emprezariu		
23	Recomendasaun ba MPS-MdF/Tezouro-MdF/Ministerio/Agencia Tutela Selu ho Montante (USD)		
24	Loron Inspeksaun terenu	Data:	Fulan: Tinan:
25	Inspector	Assinatura:	Data :
	1. Maximos dos Santos		
	2. Ana Maria Guterres	Assinatura:	Data :
	Verifikadu husi :	Assinatura:	Data :
	Miguel Marques Monteiro de Jesus		
26	Q.C.	Assinatura:	Data :
	Esron ST. Henuk		
27	Aprovadu husi :	Assinatura:	Data :
	Sr. Samuel Marçal		
28	Direitor Geral - ADN.		
29	Annexu : Sertifikadu husi dono de projeto & dokumentu adicional		

## Formatu E (Pedidu ba Preparasaun Inspesaun Terrenu)

### KARTA ULUN/KOP

---

DATA

(HATO'O BA SÉ)

LM

#### (ASSUNTU) PEDIDU BA PREPARASAUN INSPESAUN TERRENU

Atu responde ba pedidu pagamentu ne'ebé submetidu ba ADN, ADN informa katak ..... ADN hato'o pedidu ba LM atu prepara tuir-mai hodi realiza inspesaun terrenu ne'ebé korretamente no ordenada.

1. Naran Projetu
2. Data Inspesaun terrenu
3. Atendentes/Lista Prezensa ne'ebé nesessáriu
  - 1) Supervisor ka Engenheiro(s) responsável husi LM
  - 2) Konsultor(s) supervizaun
  - 3) Jerrente projetu no Chefe Engenheiro husi Empreza
4. Preparasaun iha Terrenu aranjadu husi LM
  - 1) Records/Notafikasaun sobre Kontrolu Qualidade
  - 2) Drawings/dezeñu homos inkluidu konstrusaun kompleta
  - 3) Detailhus husi BOQ
  - 4) Dispositivu Medisaun/Measuring Devices, karik Teste Destructivu nesessáriu
  - 5) Assistentes ba Measurement/medida

Husi ADN

CC.

ba Organizaun Relevante karik iha

## Checklist A



**REPÚBLICA DEMOCRÁTICA DE TIMOR LESTE  
GABINETE DO PRIMEIRO MINISTRO  
AGÊNCIA DE DESENVOLVIMENTO NACIONAL**

---

**Checklist husi Verifikasaun Dokumentu ba Dezeñu no BOQ**

Naran husi Projetu :  
Projetu Na'in :  
Número Kontratu :  
Data Simu dokumentu :

1. Karta Akumpañamentu.....
2. Dezeñu tenke ser kompleta no hetan assinatura husi Enjiñeiru husi LM.....
3. BOQ no Estimasaun Kustu hetan assinatura husi Obras Pública .....
4. Análiza Presu Unidade/Unit Price Analysis.....
5. Soft copy husi dokumentus ida-ne'ebé mensiona iha-leten.....
6. Espesifikasaun Técnica .....
7. Ida-ne'e tenke iha mós Análiza Kalkulasaun Estrutura no Hidrolójia, nomós dados Topográfia.....

***Notifikasaun: Checklist ida-ne'e utiliza hodi konfirma katak dokumentus rekeridu hotu-hotu submetidu ona para verifikasaun dokumentu husi Projetu Fundu da Infra-estrutura ba Estrada, Ponte, Portu & Irrigasaun***

Checklist A



**REPÚBLICA DEMOCRÁTICA DE TIMOR LESTE  
GABINETE DO PRIMEIRO MINISTRO  
AGÊNCIA DE DESENVOLVIMENTO NACIONAL**

---

**CHECKLIST DOKUMENTU TENDER BA PROJETUS KONSTRUSAUN  
EDIFÍSIU & MORU HALE'U ESKRITÓRIU**

8. Dezeñu tenke ser aprovalu husi Obras Públika \_\_\_\_\_
9. Bill of Quantity ( BoQ) tenke ser aprovalu husi Obras Públika \_\_\_\_\_
10. Estimasaun Kustu tenke ser aprovalu husi Obras Públika \_\_\_\_\_
11. Espesifikasaun Téknika tenke ser hetan husi Obras Públika \_\_\_\_\_
12. Submete file elektrónika ne'ebe salva iha CD laran \_\_\_\_\_
13. Karik Edifisiu mak nia ass mak liu andar 2, tenke ser anexada Estudu Viabilidade husi Rai ká rezultadus invertigasaun rai \_\_\_\_\_
14. Karik Edifisiu nia ass mak liu andar 2, tenke ser anexada Análiza Kalkulasaun Estrutura \_\_\_\_\_

***Notifikasaun: Checklist ida-ne'e utiliza hodi konfirma katak dokumentus rekeridu hotu-hotu submetidu ona para verifikasaun dokumentu husi Projetu Fundu da Infra-estrutura ba Edifisiu.***

Lista Verifikasaun-B (Kondisaun Pagamentu)

Linha Ministeriais		CHECKLIST-B (Lista Verifikasaun)			Verifika husi	Aprova husi
Tipu husi Projету	Edifisiu	Objetivu	Kondisaun Pagamentu			
Atrazu Estragu ba obra/Liquidadu estragu				Loron submete	Verifikasaun husi dokumentus konkursu/tender	
Naran Projету				Etapas		
Aliensia Implementador						
Item verifika	Pontu Inspeasaun		Loron verifika		Marka verifika	Observasaun
1	Ne' e Se konfirmadu karik buat-hirak iha-okos mak razoavei ka lae?	Se karik iha orariu detalhadu? Ne' e karik Diak/OK kompara nia ho dadus passadu?				Karik Lae, realiza rona husi LM
2	Períodu manutensaun/Períodu Notifikasaun Defeitu	Ne' e karik diak/ok kompara nia ho dadus passadu?				
3	Lei Administrativa	Karik iha Lei husi Republica Democrática de Timor Leste?				
4	Regulamentu Lingua	Karik iha Ingles?				ICB Utiliza Ingles iha Timor-Leste
5	Dezempneu Seguransa/Garantia exakusaun diak	Ne' e karik diak/ok kompara nia ho dadus passadu?				
6	Estragu Atraza ba obra/Liquidadu estragu	Ne' e karik diak/ok kompara nia ho dadus passadu?				
7	Montante maximu ba estragu atraza	Ne' e karik diak/ok kompara nia ho dadus passadu?				
8	Montante Provisional	Ne' e karik diak/ok kompara nia ho dadus passadu?				
9	Total pagamentu adiantamentu	Ne' e karik diak/ok kompara nia ho dadus passadu?				
10	Porcentajen husi Retensaun	Ne' e karik diak/ok kompara nia ho dadus passadu?				
11	Limitasaun husi orsan Retensaun	Ne' e karik diak/ok kompara nia ho dadus passadu?				
12	Montante minimu husi sertifikadus pagamentu interinu	Ne' e karik diak/ok kompara nia ho dadus passadu?				

Lista Verifikasaun-C (Verifikasaun Téknika)

Linha Ministeriais		CHECKLIST-C (Lista Verifikasaun)				Verifika husi	Aprova husi
Tipu husi projetu	Edifisiu	Objetivu	Verifikasaun teknika				
No. Kontratu	Loron submete		Verifikasaun husi dokumentus/konkursu/tender				
Naran Projetu	Etapa						
Ajensia implementador		Pontu inspesaun		Loron verifika		Marka verifika	
Item verifika						Observasaun	
1	Background/Fundo	Karik ne' e klaru entre projetu no Fundo?					Dadus Referidu
2	Objetivu	Karik ne' e projetu ne' ebe adequadu, konsidera efektivus, potencia ekonomia no efisiensia?					
3	Eskopu husi servisu	Karik ne' e klaru ba dokumentus konkursu/tender?					
4	Relatorius no Orariu	Karik ne' e klaru ba Relatoriu? Karik ne' e razoavel ho Orariu?					Konsidera tempu mobilizasaun, tempu idundasaun, etc
5	Espesifikasaun	Karik ne' e klaru ba kodigu edificiu & standard/padraun?					
6	Padraun ka Kodigus	Karik kodigu edificiu Australianu (AS) no Australianu/New Zealand(AS/NXS) ka Padraun Edifisiu Indonesia(SNI 2002)?					Laiha Lei, kodigu & standard/padarun ba Edifisiu iha Timor Leste
7	Kualidade	Karik Ne' e haktuir padraun/kodigu? Karik ne' e utiliza equivalente ka kualidade a' as-jiu duke spesifikasaun?					
8	BQQ	Karik ne' e korekta/los?					
9	Drawings/Dezenu	Oinsa ne' e hatudu deta lhu ba spesifikasaun no kodigu?					
10	Eskopu husi konstrusaun	Oinsa eskopu husi konstrusaun indika iha dezena no spesifikasaun?					



## Checklist D



# REPÚBLICA DEMOCRÁTICA DE TIMOR LESTE GABINETE DO PRIMEIRO MINISTRO AGÊNCIA DE DESENVOLVIMENTO NACIONAL

### Checklist Pagamentu ba Dokumentu husi Konsultan Supervizaun

Projetu nia Naran :  
Na'in husi Projetu :  
Número husi Kontratu :  
Data Simu dokumentu :

10. Invoice iha Orijinal hatama husi Konsultan.....
11. Sertifikadu Pagamentu iha Orijinal ne'ebé hetan aprovasaun husi Ministru ká Sekretáriu Estadu.....
12. Submete kopia kompleta husi Kontratu Válidu ho nia anexu.....
13. Hatama Relatóriu Menssal ne'ebé hetan aprovasaun husi Projetu Na'in.....
14. Submete No. TIN (Identificação do Contribuente Registo Imposto).....
15. Número husi Konta Bankária.....
16. Submete Sertidaun Dividas ne'ebé válidu no tenke ser legalizadu.....
17. Submete Licença Actividades de Comercio e Económico ne'ebé válidu no legalizada.....
18. Submite Para Quem Interessado ne'ebé válidu .....

***Notifikasaun: Checklist ida-ne'e utiliza hodi konfirma katak dokumentus rekeridu hotu-hotu submetidu ona para dokumentu pagamentu husi Projetu Fundu da Infra-estrutura ba Estrada, Ponte, Portus & Irigasaun***

**Checklist D**

**REPÚBLICA DEMOCRÁTICA DE TIMOR LESTE  
GABINETE DO PRIMEIRO MINISTRO  
AGÊNCIA DE DESENVOLVIMENTO NACIONAL  
CHECKLIST FUNDU DA INFRA-ESTRUCTURA BA  
PAGAMENTU**

**Naran husi Projetu** :  
**Naran husi Kompañia** :  
**Númeru Kontratu** :  
**Valor husi Kontratu** : US\$  
**Valor husi Invoice/Pedidu** : US\$

No	Dokumentus ne'ebé submetidu iha Invoice laran	Resultadu		OBS
		Sim	Lae	
1	Kontratu sei moris hela (mais menus fulan ida antes data prazu hotu/ expired date). Valor kontratu mak liu husi >500,000 tenke ser sujeitada hodi hetan Karta Justifikasaun husi Tribunal das Contas, Tribunal Superior das Administrativas de Timor Leste.			
2	Submete Sertidaun Dívidas ne'ebé válidu no tenke ser legalizadu			
3	Submete No. TIN (Identificação do Contribuente Registo Imposto)			
4	Submite Para Quem Interessado ne'ebé válidu			
5	Submete Licença Actividades de Comercio e Económico ne'ebé válidu no legalizada			
6	Submete Invoice Orijinal I (kopia 5) no hetan aprovasaun husi Tékniku LM			
7	Pedidu husi Karta Pagamentu			
8	Sertifikadu Pagamentu aprovada husi Liñe Ministriais			
9	Númeru Conta Banária husi Kompañia			
10	Garantia ba Exekusaun di'ak tenke ser rai iha banku nu'udar garantia, ida-ne'e hanesan ho Valor Adiantadu ká bazea Termos husi Kontratu			
11	Invoice tenke ser anexada ho Relatório Progressu Mensal			
12	Kompañia Intemasional tenke anexa sertifikadu hosi Organizasaun Padraun Intemasional (ISO)			

**Notifikasaun:** Checklist ida-ne'e utiliza hodi konfirma katak dokumentus rekeridu hotu-hotu submetidu ona para dokumentu pagamentu husi Projetu Fundu da Infra-estrutura ba Edifisiu, Estrada, Ponte, Portu, Irigasaun, etc.

CHECKLIST- E (Lista Verifikasaun)				Verifika husi	Aprova husi
Linha Ministeriais	Edifisiu	Objetivu	Kontroliu Kualidade		
Tipu husi projetu					
No. Kontratu	Loron submete		Inspeasaun no Rekomendasaun ba Pagamentu		
Naran Projetu	Etapa				
Ajensia implementador					
Item verifika	Pontu Inspeasaun		Loron verifika		
Finalidade no Utilizasaun	Karik Espesifikasaun konstrusaun obedese ba rekerementus husi kontratu?		Marka verifika		
Kodigus no Padraun	Karik Padraun no kodigus hotu-hotu husi Praktika utilizada ih espezifikaun konstrusaun aktuais haktuir loran manan konkursu/tender nian?		Wainhira Lae. aponta Rona husi LM.		
Inspeasaun, amostrajen /Sampling no Teste	Karik Inspeasaun, sampling no teste exekuta hodi kumpru tuir assegura kualidade no kontroliu rekerementus espezifikaun iha Rekerementu Jeral?		Hanesan iha leten		
Seguransa	Oinsa ho Obra hotu-hotu exekuta hodi kumpru tuir rekerementus seguransa ne'ebe estabeselese iha Kontratu no rekerementus seguransa espezifiku ruma?		Hanesan iha leten		
Asessu	Oinsa ho Emprezaariu responsabilidade hodi fornese asessu dalan temporaria ba no husi terrenu?		Hanesan iha leten		
Signboard/Plakas	Karik Signboard forneseidu no montadu husi Emprezaariu? Nusa signboard hirak ne'e iha adisaun ba seguransa no sinais avisu ruma?		Hanesan iha leten		
Rekerementus Ambiental	Tamba sa mak Obra hotu-hotu exekuta hodi kumpru ba rekerementus ambiental ne'ebe estabeselese iha rekerementus ambiental espezifiku ruma?		Hanesan iha leten		
Demostrasaun	Karik ne'e mak Planu adequadu?		Hanesan iha leten		

## 添付資料 3 人材育成計画

**DEMOCRATIC REPUBLIC OF TIMOR-LESTE**

**ADN**

**EXPERT FOR STRENGTHENING  
INSTITUTIONAL CAPACITY OF  
NATIONAL DEVELOPMENT AGENCY**

**HUMAN RESOURCE DEVELOPMENT  
PLAN**

**OCTOBER 2013**

**JAPAN INTERNATIONAL COOPERATION AGENCY  
(JICA)**

**DAINICHI CONSULTANT INC.  
TOKYO WATERWORKS INTERNATIONAL CO.LTD  
GEOPLAN CO.,LTD  
NEWJEC INC.**

EXPERT FOR STRENGTHENING INSTITUTIONAL CAPACITY OF  
NATIONAL DEVELOPMENT AGENCY (ADN)  
IN DEMOCRATIC REPUBLIC OF TIMOR-LESTE  
  
HUMAN RESOURCE DEVELOPMENT PLAN

**Table of Content**

	<b>Page</b>
<b>1. Background .....</b>	<b>1</b>
<b>2. General Plan .....</b>	<b>2</b>
<b>2.1 Outline of Plan .....</b>	<b>2</b>
<b>2.2 Methodology.....</b>	<b>2</b>
<b>2.3 Program.....</b>	<b>3</b>
<b>2.4 Time Schedule.....</b>	<b>6</b>
<b>3. Plan of Each Sector .....</b>	<b>7</b>
<b>3.1 Plan of Bridge/ Road Sector .....</b>	<b>7</b>
<b>3.1.1 Engineering Field necessary for Bridge/Road Engineerings in ADN .....</b>	<b>7</b>
<b>3.1.2 Targeted Engineeris to be Developed and Objectives .....</b>	<b>8</b>
<b>3.1.3 Methods of Human Resource Development .....</b>	<b>9</b>
<b>3.2 Plan of Power Sector .....</b>	<b>12</b>
<b>3.2.1 Engineering Field necessary for Power Engineers in ADN .....</b>	<b>12</b>
<b>3.2.2 Targeted Engineeris to be Developed and Objectives .....</b>	<b>12</b>
<b>3.2.3 Methods of Human Resource Development .....</b>	<b>13</b>
<b>3.3 Plan of Water Supply Sector .....</b>	<b>15</b>
<b>3.3.1 Engineering Field necessary for Water Supply Engineers in ADN .....</b>	<b>15</b>
<b>3.3.2 Targeted Engineeris to be Developed and Objectives .....</b>	<b>15</b>
<b>3.3.3 Methods of Human Resource Development .....</b>	<b>16</b>

## **1. Background**

The low quality of infrastructure in Timor-Leste is one of the most serious social issues that Timor-Leste faces. As part of this, effective quality control of infrastructure is a nationwide issue that remains to be addressed.

The National Development Agency (ADN) is responsible for quality control of infrastructure especially through design verification and construction inspection. However, ADN is a young organization whose institutional framework is still in the process of stabilization. In addition, ADN's staff is almost fully composed of junior engineers and most of them do not have sufficient experiences or knowledge that is required to fulfill their mission.

The Japanese Technical Assistance Project, "Strengthening Institutional Capacity of the National Development Agency of the Democratic Republic of Timor-Leste" was carried out in 2012 (Phase I) and 2013 (Phase II) under these conditions. The Japanese International Cooperation Agency (JICA) proposed to develop a capacity building strategy through the creation of a manual and the "ADN Manual" was made by a JICA-ADN team in 2012. During Phase II it was planned that the capacity of ADN's staff would be strengthened through the use of the ADN Manual and the provision of classroom based lessons and one the job trainings (OTJ) to ADN engineers.

As it is still necessary to continue to develop human resources capability beyond the end of Phase 2 of the JICA-ADN Project, this Human Resource Development Plan has been developed taking into account the results of the activities of the JICA-ADN team. The plan consists of two parts; part one explains the scheme of the general plan and part two describes the specific sections of the plan, namely, Bridge, Power and Water Supply.

## **2. General Plan**

### **2.1 Outline of the Plan**

#### **a. Goal**

A more effective human resource development management system is in place and quality is assured through ADN's supervision of projects.

#### **b. Objective**

A human resource development system as required for management will be established and human resources will be developed through better coordination with International Advisors.

#### **c. Targeted Staff**

All ADN engineers

#### **d. Time Frame**

Two years from 2013 to 2015.

### **2.2 Methodology**

Generally, personnel's skills are expected to improve through continued practical work activities, and their development will be assisted by the personnel management and training system.

#### (1) Personnel management system

- a. Recruitment
- b. Job rotation
- c. Management System for voluntary capacity development.

#### (2) Training system

- a. Off-the-job training (Off JT)
- b. On-the-job training (OJT)
- c. Self-development support

Practical work activities, self-help efforts, and classroom lesson are factors that will contribute to human resource development in governmental organizations and private companies. However the ADN or Government of Timor-Leste have specific characteristics that makes them difficult:

- ♦ ADN engineer's knowledge at recruitment is insufficient.
- ♦ ADN is mostly composed of junior engineers.


It is expected that human resource development will be accelerated against above difficulties.

Existing level of ADN engineers is divided into 1) Team Leader level, 2) assistant engineer level



and 3) new recruit level.

Considering these particular situations, this human resource development plan of new recruit level mainly focuses on Classroom Lessons. New recruit level should start from the start line as illustrated in Fig.2-1.



**Fig.2-1: Means and level of contribution to of human resource development**

## 2.3 Program

### 2.3.1 Targeted Engineering Levels

The level of ADN engineers on general plan is defined in Table 2-1.

**Table 2-1 Definition of Level of ADN engineers**

Level I	New recruit level.
Level II	Assistant engineer level (can handle ADN work with Team Leader's support )
Level III	Team Leader level,(can handle ADN work)

ADN's engineers are required to attain the following abilities:

- a. To check the design documents and identify any errors in the design, and
- b. To check the construction works, any mistakes and to instruct the contractor rework to remedy such works correctly.

To supervise project adequately, ADN's engineers need to acquire the specific knowledge to be obtained through practical work activities. But, as it takes time to accumulate experience, it is difficult for ADN's engineers to obtain such knowledge within a short period of time. Therefore, it is proposed that;

- ♦ First step (Level-I): Fundamental knowledge on civil engineering shall be acquired through classroom lessons,
- ♦ Second step (Level-II): The practical knowledge to be applied depending on the

various situations in the different project sites shall be acquired through practical work and OJT, and

- ♦ Third step (Level-III): A special program shall be necessary. Refer to 2.3.5.

### **2.3.2 Off-the-job training for Level-I**

The attainment to Level-I, which is the general start line or a little bit above it, shall be made through classroom lessons. The Level-I Training Course, which may be set on Saturdays, should be prepared in order that as many engineers as possible can attend the classes. E-learning systems should also be constructed and made available for engineers based in the Districts. Whenever possible, simultaneous TV-classes will be the option to favor.

#### **(1) Classroom lessons**

The preparation of the classroom lessons shall follow the procedures below:

1. Determination of Curriculum and Syllabus
2. Preparation of texts
3. Preparation of training materials (Power Point Slides)
4. Recruitment of Instructor (International Adviser)

It is expected that the preparation of the training mentioned above is carried out by a team headed by an international adviser(s).

#### **(2) E-learning (Electronic learning)**

The contents of the e-learning system should be the same with classroom lesson and the function of evaluation such as “test and record of the test result” will be necessary. The e-learning system should be constructed by IT engineers.

### **2.3.3 Practical Work Activities & On-the-job training for Level-II**

The attainment of Level-II, which is the ability to identify most of the engineering issues to be addressed in a project cycle and to solve them, shall be done through practical work activities and OJT.

#### **(1) Practical work activities**

Acquisition of knowledge/skills through practical work activities are deeply related to time, job rotation and the number of jobs undertaken.

#### **(2) OJT**

Practical technical transfer of design verification and supervision, monitoring and inspection of construction works shall be done through OJT. OJT activities should be carried out with a leader, senior engineer or international adviser, who is able to give instruction and advice to junior

engineers.

#### **2.3.4 Small group activities/Self-development for Level-II**

Additional measures such as “QC group activities” may be necessary to expedite the human resource development.

##### **(1) QC circle activities**

A QC Circle is a small group of frontline employees who meet regularly to try to improve the quality of their work. QC Circle activities are at the core of Total Quality Management (TQM). QC Circles normally take a problem-based approach to improve the quality of their work. They identify problems in their workplace, usually related to product quality and referred to as ‘themes’, and together they set about to find solutions for these problems. They use quality control concepts and techniques, and try to be creative in seeking solutions.

The QC Circle leaders will be the driving force behind the activities. The selected individuals will be able to show leadership to get members to cooperate during meetings, gather ideas, and create an atmosphere where everyone will feel free to express their opinions.

##### **(2) Voluntary study circle**

Voluntary study circles consist of members of a small group meeting regularly to pursue a common theme of study. It may take the form of reading a book and discussing it chapter by chapter. Even when the cost is not subsidized, it is necessary to provide at least meeting facilities.

#### **2.3.5 Special program for Level-III**

If the ADN needs section/sector expert(s), they would be in charge of developing the following activities. The ADN must prepare a special program beginning with the recruitment of Level-III or these expert(s).

- ♦ National Development Planning
- ♦ Planning of city or district master plans
- ♦ Attending international conferences such as the MDGs conferences
- ♦ Introduction of advanced technologies to their sectors

The ADN will have to recruit several postgraduate students and prepare courses of study or training abroad for them.

#### **2.3.6 Others**

**(1). Guidance for newly recruited engineers**

Guidance should be provided for newly recruited engineers to ensure their full understanding of the outline of ADN jobs. The ADN Manual which describes the whole work area of ADN will be very useful for this purpose.

**(2) Handbook by Sector**

The JICA-ADN team produced “Technical Checklists” as a part of the ADN Manual. In the near future the contents of these checklists will be enriched by international advisers and ADN staff. Ultimately, it would be better to complete a second, “Technical Handbook” by ADN staff, which would be very useful for their work and for self-study.

**2.4 Time Schedule**

The time schedule of the plan is shown in Table 2-2 below.

**Table 2-2 Time Schedule**

Activities	Year	2013				2014				2015			
		Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3
Annual training plan		▨		▨								▨	
Classroom lessons		▨	▨	▨	▨								
E-learning		▨	▨	▨	▨	▨	▨	▨	▨	▨	▨	▨	▨
OJT		▨	▨	▨	▨	▨	▨	▨	▨	▨	▨	▨	▨
Small group activities		▨	▨	▨	▨	▨	▨	▨	▨	▨	▨	▨	▨
Guidance for new personnel				■								■	
Sectoral handbook		▨	▨	▨	▨	▨	▨	▨	▨	▨	▨	▨	▨

▨ : Preparation

■ : Implementation, ■ ■ ■ : Intermittent implementation

### **3. Plan of each sector**

Regarding Human Resource Development Plan of ADN, Chapter 2 explains common belief. There are a lot of different conditions among ADN Sector Team, so Chapter 3 focus on Plan of Each Sector, considering existing assignment, personal distribution and time frame of two years.

#### **3.1 Plan for the Road/Bridge Sector**

##### **3.1.1 Engineering Field knowledge necessary for ADN Bridge Engineers**

Most of the work for the ADN bridge engineers working in the Infrastructure Fund Project (FI Project) consists of the verification of tender documents and inspection for payment. Bridge projects in other budget categories such as PDID are technically similar to FI Project or less difficult.

ADN is the organization in charge of evaluating before a contract is signed as to whether a project is feasible and reasonable, and also ADN must judge whether the payment amount requested by a contractor is reasonable. In other words, ADN is generally not an implementing agency. As a result, the range of engineering fields necessary for the engineers is thus limited. The bridge engineers are not required to plan a project, nor make a detailed design or to supervise and manage bridge works directly on site.

Required knowledge and technology for the engineers to accomplish their responsibilities of verification of tender documents and inspection of payment requests are;

###### **[Verification of Tender Documents]**

- 1) Knowledge regarding which documents are required for the verification,
- 2) Knowledge regarding the conditions of contract, especially payment conditions such as delay damages, provisional sum, advance payment, percentage of retention, minimum amount of interim payment and so on,
- 3) General but broad knowledge regarding bridge technology including planning, detailed design, construction, design standards and quality control on technical specifications to evaluate the project shown in the drawings, and
- 4) Knowledge on BOQ, constitution of BOQ, unit price.

###### **[Inspection for Payment Request]**

- 1) Knowledge regarding which documents are required for the inspection,
- 2) Knowledge of payment conditions such as contract amounts, advance payments, performance bond, retention, delay damage and so on,

- 3) Knowledge and technology on BOQ. The engineer has to know how the BOQ document is composed, and how to calculate and verify the percentage of completed work claimed by a contractor at certain times,
- 4) Knowledge on time schedule. The engineer has to check how the construction work has progressed according to the schedule,
- 5) Knowledge and technology on quality control. The engineer has to verify if the works done so far conform to the quality specifications. Thus he has to be familiar with the quality control on technical specifications.
- 6) Knowledge on how to measure and calculate quantities. Some items are calculated by length, linear meter and others by area or volume. The engineers must know how to use these measuring units and how to measure and calculate quantities in order to verify the quantities on which the payment amount requested is based.

Regarding special improvement points identified by JICA-ADN Team, required knowledge and technology for the engineers to accomplish their responsibilities on Bridge, Road & Flood Control sector are;

- 1) Knowledge of durability assessment of Bridge, Road & Flood Control
- 2) Knowledge of countermeasure of Bridge, Road & Flood Control against natural disaster
- 3) Knowledge of safety control of construction and traffic
- 4) Knowledge of maintenance & operation of Bridge, Road & Flood Control

### **3.1.2 Targeted Engineers to be Developed and Objectives**

There are two kinds of engineers targeted for human resource development. (1) One are the junior engineers, who have just graduated from school, and were recruited and dispatched to district offices; hereinafter they are referred to as “**Junior Engineers**”. (2) The other are engineers equivalent to sub-team leaders, who have worked for several years in the industry or at ADN and who aspire to be senior bridge engineers; hereinafter they are referred to as “**Would-be senior Engineers**”. Table 3-1 shows Relationship between Level of Road/Bridge Sector and Level of General Plan.

**Table 3-1. Relationship between Level of Road/Bridge Sector and Level of General Plan**

Level of Road/Bridge Sector	Level of General Plan
Junior Engineers	Level I
Would-be Senior Engineers	Level II or Level III
Senior Engineers	Level III

“The Junior Engineers” seldom have knowledge and experience on bridge, even though they are graduated from a faculty of civil engineering. Japanese civil engineers are classified into specialized areas depending on the specialization that they choose during their university studies. By contrast, as mentioned by an Indonesian adviser, Timorese as well as Indonesian civil engineers get their specialization after graduation through experience gained in the industry with time.

“Would-be Senior Engineers” may have some experience in the bridge sector but usually they have not exclusively worked in this field, but also in other fields such as irrigation or water supply. Thus even the Would-be senior Engineers do not have sufficient knowledge and technological skills to be considered as bridge specialists. They still need to ask advice from Indonesian advisers when they have to make an important judgment.

- (1) The purpose of the human resource development plan for the Junior Engineers is to give them very basic and general knowledge on bridges as a part of the general scope of work in order to raise the level and/or accuracy of the on-site inspection of bridges and of the relevant documents. Finally after one or two years of capacity development the junior engineer will be able to work as a “Generalist” in a district, with the ability to inspect a bridge not only on site but through the examination of documents also as a part of his scope of work.
- (2) The purpose of the human resource development plan for Would-be Senior Engineers is to give them deeper knowledge on bridges through which they can inspect a bridge and also verify tender documents themselves. Even after getting a deeper knowledge on bridges, they will need at least 5 years experiences by working exclusively on bridges. Finally they will be expected to become bridge specialists, able to give advice and instructions to junior engineers.

### **3.1.3 Methods of Human Resource Development**

Two human resource development methods are introduced to Junior Engineers and Would-be Senior Engineers; lectures and OJT.

#### **(1) Verification of Tender Documents**

Tender documents are verified mainly at the Head Office by Senior Engineers and Would-be Senior Engineer. Would-be Senior Engineers have to know about the tender document itself, especially contract conditions and also technical matters such as verification of drawings and BOQ. Junior Engineers do not need to gain this knowledge for the time being as it is too difficult for them to verify documents. Instead they must focus on the inspection of bridges at

district level. So only Would-be Senior Engineers will benefit from the trainings mentioned below;

**[Lectures to Would-be Senior Engineers]**

Knowledge on verification of contract, unit price analysis and drawings

**[OJT to Would-be Senior Engineers]**

Technology on verification of contract, unit price analysis and drawings

**(2) Inspection for Payment**

Junior Engineers, stationed at the district level, work on bridge inspection with the help of Senior Engineers and international advisers. They will gain the necessary knowledge through lectures, and practical technical skills through actual inspections.

Would-be Senior Engineers will have to replace Senior Engineers in the near future, so they have to gain full knowledge and technical skills required for effective inspections.

**[Lectures to Junior Engineers]**

As Junior Engineers work on bridges consists of inspection for payments, they need lectures by international advisers on subjects such as;

- 1) Knowledge on the required documents for inspection for payment  
Refer to the “ADN Manual” and materials for Classroom Lessons prepared by JICA-ADN Team
- 2) Knowledge on payment conditions  
Refer to “ADN Manual” and materials for Classroom Lessons prepared by JICA-ADN Team
- 3) Knowledge and technology on BOQ  
Refer to the materials for Classroom Lessons prepared by JICA-ADN Team
- 4) Knowledge on time schedule
- 5) Knowledge on quality control  
Refer to the materials for classroom lessons prepared by JICA-ADN Team  
Even after taking lectures on quality control, it is still hard for the junior engineer to actually understand the quality control system or each clause of the specifications. They need experience in actual situations related to specified quality specifications and instruction from senior engineers.
- 6) Knowledge on how to measure and calculate the quantities  
Refer to materials for classroom lessons prepared by JICA-ADN Team

**[OJT to Junior Engineers]**

- 1) Quality control techniques  
Capability on quality control consists of understanding technical specifications and judging



the actually achieved results. To fully understand the specifications and judge the results is a long term process. Junior Engineers need to learn this material step by step under the instruction of Senior Engineers and advisers.

2) Quantity measurement techniques

Junior Engineers will practice what they study through the lectures, that is, measure and calculate the work completed so far under instruction from the Senior Engineers or advisers.

**[Lectures to Would-be senior Engineers]**

1) With regards to 4), and 6), Would-be Senior Engineers usually have considerable knowledge about these subjects in principle, thus no lecture is necessary.

2) Knowledge on quality control

Most specifications are written in English with many technical terms. Some would-be Senior Engineers have a good understanding of English, but the majority are weak in reading English. This is one reason why engineers are reluctant to looking into specifications.

Lectures will teach would be senior engineers how to use and how to find out proper clauses of the specifications for specific quality control activities.

**[OJT to Would-be Senior Engineers]**

1) Quality control techniques

International advisers will teach Would be Senior Engineers how to make a comparison between the specified quality level and the actually achieved quality as well as on how to make an on the job quality evaluation.

## **3.2 Plan of Power Sector**

### **3.2.1 Engineering Field necessary for Power Engineers in ADN**

Power Sector Development Projects in Timor-Leste are divided roughly into two categories, the 'Construction Supervision Services of the Nationwide Electrical Power Grid and Power Plants and its Facilities' project and the 'Installation Middle Voltage and Low Voltage line, House Connection and Home Installation (Hereinafter, it is referred to as The Power Distribution Line Extension)' project.

The former consists of the construction of two diesel power stations, the construction of high voltage (150kV) transmission lines (700km in full length), and the construction of nine distribution substations. The construction has been mostly completed as of September, 2013. Meanwhile, the latter project is still in the middle of development.

Required knowledge and techniques for the engineers to accomplish their responsibilities in the Power sector are;

- 1) Knowledge of the verification of inventory/ master plan of implementation project list
- 2) Knowledge of the verification of project development pronouncing the infrastructure plan
- 3) Knowledge of the verification on the selection of contractors and award of contract
- 4) Knowledge of the verification of contracts (payment condition, control of costs and quality)
- 5) Knowledge on the Inspection of Power Stations (Mainly Diesel Power Station)
- 6) Knowledge of the Inspection of Power Substation
- 7) Knowledge of the Inspection on Transmission and Distribution System
- 8) Knowledge of the Inspection on Renewable Energy (Photovoltaic Power)
- 9) Knowledge required of others on electrical engineers

Regarding special improvement points found by JICA-ADN Team, required knowledge and technology for the engineers to accomplish their responsibilities on Power sector are;

- 1) All the domains, which are generation, transmission, transformation, and distribution.
- 2) The establishment of a continuous education system which can acquire the knowledge of each domain and can understand the relevance between each domain is recommended.
- 3) Effective use of Classroom Materials
- 4) Training in PLN (electric power company of Indonesia) University

### **3.2.2 Targeted Engineers to be Developed and Objectives**

One definition of the level of engineers is shown in the IEA Technical Report, Structure of

Operation and Maintenance Training Programmes (May 2000). The level of competence has been classified into five categories applicable to a shift charge-engineer, the control room technician and the plant operator of the hydro power plant.

Table 3-2 shows Level of Competence.

**Table 3-2 Level of Competence on Power (Defined in IEA Technical Report)**

LEVEL	COMPETENCE
5	Can perform the task/competence with better than acceptable speed and quality and with initiative and adaptability. Can lead others in performing the task.
4	Can perform the task/competence with better than acceptable speed and quality and with initiative and adaptability to special problems and situations.
3	Can perform the task/competence without assistance and supervision with better than acceptable speed and quality of work.
2	Can perform this task/competence without assistance and supervision.
1	Can perform the task/competence satisfactorily, but requires periodic supervision and some assistance.

Table 3-3 shows Relationship between Level of Power Sector and Level of General Plan.

**Table 3-3. Relationship between Level of Power Sector and Level of General Plan**

Level of Power Sector	Level of General Plan
Level 5	Level III
Level 4	Level II or Level III
Level 3	Level II
Level 2	Level II
Level 1	Level I

### 3.2.3 Methods of Human Resource Development

Training is divided into two sections, one of which is theory and the other, practice.

Regarding theory, it is necessary to use the classroom lessons materials effectively.

Table3-4 shows the classroom syllabus

**Table3-4 Syllabus of Classroom on Power**

No	Contents
1	Introduction
2	Power Station (Diesel)
3	Substation
4	Transmission and Distribution System
5	Power System Study
6	Power Flow Analysis
7	Power System Stability
8	An Example of Power System Analysis (Using PSS/E)

9	How to Use the Result of Power System Analysis
10	Renewable Energy (Photovoltaic Power)

It is also useful to use the course of PLN University. Table 3-5 shows course of PLN University.

**Table 3-5 Course of PLN University**

Level	subject of educational training
Basic	Operation of LV line and LV connection service
Bas/spe	Operation of MV Line
Bas/spe	Operation of distribution substation
Bas/spe	Operation of cubicle 20KV
Basic	Instalation and sealing APP (measuring and limiting tools)
Bas/spe	Wiring and APP (measuring and limiting tools) LV testing
Bas/spe	Testing of CT- PT distribution
Bas/spe	Wiring and testing APP – MV
Bas/spe	Electronic meter reading and AMR
Basic	Inspection of distribution network
Basic	LV line maintenance
Basic	MV line maintenance
Bas/spe	Maintenance of distribution transformer
Bas/spe	Maintenance of cubicle 20KV
Bas/spe	Connecting and terminating ground cable 20KV
Spe/sys	Construction plan of medium voltage distribution network
Sys/opt	Distribution plan management
Sys/opt	Operation management and distribution maintenance
Bas/spe	Controlling of power consumption
Bas/spe	Introducing automatic meter reading

Junior engineers in Electrical Team will categorized into level, from Level 1 to Level 3, as shown in Table 3-2 & Table 3-3. Table 3-6 shows a case model for the development of competence.

**Table 3-6 Model Case for Development of Competence**

LEVEL	Position	NO. of Syllabus	OJT	PLN University
1	-	1~4	accompany with inspection	arbitrarily
2~3	-	5~9	Inspection with level 4	
4	Sub Leader	-	Experiences are acquired	
5	Leader	-		

### **3.3 Plan of Water Supply Sector**

#### **3.3.1 Engineering Field necessary for Water Supply Engineers in ADN**

Required knowledge/skills in water supply section are as follows:

1. Knowledge for verification of design documents
  - ♦ Basic knowledge on rural water supply systems
  - ♦ Basic knowledge on the design of rural water supply system
  - ♦ Practical knowledge on the outlining and design of rural water supply system
  - ♦ Basic knowledge on basic hydraulics of pipelines
  - ♦ Practical knowledge on hydraulics calculation of simple pipelines using EPANET or PIPECAL
  - ♦ Knowledge on profile of pipeline and air release valve
  - ♦ Practical knowledge on drawing profile using Google Earth
2. Knowledge for inspection of construction works
  - ♦ Basic knowledge on inspection procedures
  - ♦ Basic knowledge on the inspection of water source facilities
  - ♦ Basic knowledge on the inspection of concrete storage tanks
  - ♦ Basic knowledge on the inspection of transmission and distribution pipelines
  - ♦ Basic knowledge on the inspection of public taps

Regarding special improvement points identified by JICA-ADN Team, required knowledge and technology for the engineers to accomplish their responsibilities on Water Supply sector are;

- 1) Knowledge of adoption of good sample drawings for design
- 2) Knowledge of information from Google earth and preparation of pipeline profile.
- 3) Knowledge of air valves and sand valves on pipeline
- 4) Knowledge of countermeasure of leakage from tank and pipeline

#### **3.3.2 Targeted Engineers**

The proportion of time that ADN spends on water supply projects is not large. Therefore, it will require a significant timeframe for water engineers to gain OJT experience. Also, ADN does not have a specialized section to deal with water supply. As a result the creation of a mechanism to increase the capacity of ADN engineers in the area of water supply is difficult. Due to the short period of time spent by the ADN engineers investigating water supply issues it may be inefficient itself to retain in the ADN personnel a water supply specialist. Thus it might be better

to carry out periodical training to all ADN engineers by international adviser(s).

Table 3-7 shows Relationship between Level of Water Supply Sector and Level of General Plan.

**Table 3-7. Relationship between Level of Water Supply Sector and Level of General Plan**

Level of Water Supply Sector	Level of General Plan
Level III	Level III
Level II	Level II
Level I	Level I

### 3.3.3 Method of Human Resource Development

Table 3-8 shows Level I Plan on Water Supply.

**Table 3-8 Level I Plan on Water Supply**

Name	General Program of Water Supply
Objects	To acquire basic knowledge on rural water supply
Methodology	Classroom Lecture and e-Learning
Preparation	1. Curriculum and Syllabus 2. Preparation of Text (refer to WB's Manual of Rural Water Supply) 3. Preparation of Training materials (Power Point Slides) 4. Instructor (International Adviser) Preparation of training mentioned above shall be carried out by an International Adviser lead team.

Table 3-9 shows the Level II Plan on Water Supply.

**Table 3-9 Plan for Level-II on Water Supply**

Name	Senior Engineer Program of Water Supply
Objects	To acquire practical and specific knowledge on rural water supply so that he/she can identify technical problems on water supply projects and solve them.
Methodology	Experiences, OJT, and QC circle activity
QC Circle Activity	A QC Circle is a small group of frontline employees who meet regularly to try to improve the quality of their work. QC Circle activities are at the core of Total Quality Management (TQM). QC Circles normally take a problem-based approach in order to improve the quality of their work. They identify problems in their workplace, usually related to product quality and referred to as 'themes', and together they set about finding a solution. They use quality control concepts and techniques, and try to be creative in seeking solutions.  The QC Circle leaders will be the driving force behind the activities. Select people, who can show leadership, get members to cooperate in meetings, can gather ideas, and can create an atmosphere where everyone will feel free to express their opinion.

Table 3-10 shows Level III Plan on Water Supply.

**Table 3-10 Level III Plan on Water Supply**

Name	Expert program of Water Supply
Objects	To acquire total water supply knowledge as followings: <ul style="list-style-type: none"> <li>• Water Supply Policy (National Plan, Tariff, Sustainable water supply)</li> <li>• Water supply and Hygiene</li> <li>• MDG</li> <li>• Urban Water supply System</li> <li>• Advanced Technology and Appropriate Technology</li> <li>• Planning of Master Plan</li> </ul>
Methodology	Special training (Master course, e-Learning of special program, Study or Training Abroad)

A reference handbook should be prepared to use as needed. Concerning the Handbook, it is recommended that the Rural Water Supply Manuals published by WB Manila Office, which should be edited in accordance with the actual situation of this country and in the spoken language of Timor-Leste.

## 添付資料 4 セミナー配布資料(英語版)





AGÊNCIA DE DESENVOLVIMENTO NACIONAL  
REPÚBLICA DEMOCRÁTICA DE TIMOR-LESTE

# **Workshop on Quality Control through ADN Work**

## **Handout of Presenter**

**20th September 2013**

## Table of Content

	<b>Page</b>
1. Activities of JICA-ADN Team .....	<b>1</b>
2. Quality Control and Use of ADN Manual on Infrastructure Fund Projects .....	<b>21</b>
3. Rapid Assessment of ADN: ADN's Role in the infrastructure Development Process .....	<b>32</b>
4. Presentation ADN Manual for Line Ministry Project.....	<b>38</b>
5. Power Quality & Utilization ADN Manual Book .....	<b>46</b>
6. The Presentation of ADN Manual Regarding PDID Project .....	<b>57</b>
7. Overview of JICA Assistance to ADN and Way Forward .....	<b>64</b>

## ACTIVITIES OF JICA-ADN TEAM



Presented  
by  
Mr. Hideo MATSUSHIMA  
JICA-ADN TEAM

1

### Project Title / Overall Goal / Purpose of JICA-ADN Team

PROJECT TITLE	JAPANESE TECHNICAL ASSISTANCE ON STRENGTHENING INSTITUTIONAL CAPACITY OF NATIONAL DEVELOPMENT AGENCY (ADN)
OVERALL GOAL	More effective management of Infrastructure Development is carried out and quality is assured through ADN
PROJECT PURPOSE	Human resource of ADN is developed on fundamental knowledge & experience of evaluation, monitoring and inspection of infrastructure project as following fields. 1) Road/Bridge/Flood Control (Use of Infrastructure Fund on ADN Manual) 2) Power (Use of National Electrification Program: PEN on ADN Manual) 3) Water (Use of PDD I & II on ADN Manual)

2

## Project Activities of JICA-ADN Team (Phase-1)

- JICA provided JICA-ADN Team (Phase-1) for **OJT** of project monitoring/ inspections for infrastructure and **development of ADN manual**. JICA-ADN Team (Phase-1) dispatched from Jun 2012 to Nov 2012.

Mr. Hideo MATSUSHIMA (Road & Bridges #1)  
Mr. Jiro KOYAMA (Road & Bridges #2)  
Mr. Shimpei TOMITA (Power)  
Mr. Hiroyasu YODA (Water)  
Mr. Hiroki Oe (ITC) (Assistant)  
Mr. Osamu KUNITA (Port & Aviation)

3

## Project Activities of JICA-ADN Team (Phase-2)

- JICA provides JICA-ADN Team (Phase-2) for **wide use of ADN Manual** and **basic skill training** for project inspection, review and monitoring. JICA-ADN Team (Phase-2) dispatched from Apr 2013 to Sep 2013.



Road & Bridges expert #1  
Mr. Hideo MATSUSHIMA



Road & Bridges expert #2  
Mr. Jiro KOYAMA



Water expert #1  
Mr. Hideo HIGUCHI



Water expert #1 (Assistant)  
Mr. Takeo SAKAMOTO



Water expert #2  
Mr. Hiroyasu YODA



Power expert  
Mr. Koichi UCHIDA

4

## Outputs resulted from JICA-ADN Team

[1] **The Revised ADN Manual** ---pp6-10

JICA-ADN Team/ADN engineers revised ADN Manual.

[2] **Core technologies** on evaluation, monitoring and inspection of infrastructure projects. ---pp11-14

**ADN engineers acquire the core technologies by use of ADN Manual.**

[3] **Fundamental knowledge** on evaluation, monitoring and inspection of infrastructure projects. ---pp15-19

**ADN engineers acquire the fundamental knowledge by classroom lessons.**

[4] **Coordination** with relevant Ministries/Agencies---pp20-22

[5] Suggestion on Human resource development plan ---p23

[6] Finding & Achievements ---pp24-38

[7] Workshop --- p39

5


## [1] The Revised ADN Manual

- ADN engineers revised the Checklists/Forms resulting from actual use.
- JICA-ADN Team and ADN engineers revised the Checklists/Forms according to the discussion results.

### **(Achievement)**

- **Revised ADN Manual**

6



## Brief Summary of Revised ADN Manual

(Scope)

- ADN Manual aims at ADN to carry out properly and efficiently its duties which are specified in the Decree-Law. The manual also aims at LMs and other organizations concerned to play properly their roles and responsibilities during provision of the capital development project.
- The manual focuses specifically on the following processes since they are most busily handled at present.
- -Verification of Tender Documents
- -Inspection for Payment Request

### **(Category of Projects/Funds)**

- The manual is separately formulated based on the category of projects in consideration of different procedure and in favor of the users.
- The manual deals with **Infrastructure Fund** Project, **Line Ministries** Fund Project, **PDID** Fund Project, and National Electrification Program (**PEN**).
- The manual does not deal with **Emergency**, **Additional**, **SEFOPE**, **MDG**, and **Special Project** under ADN.

9

### **(Range of Application of Each Sector)**

- Regarding Sectors, the manual includes technical checklist for **Road & Bridge on Infrastructure Fund**, **Water Supply on PDID**, and **Electric Power on PEN**. The technical checklist will be able to use for other category partially.
- Please note the explanation of page 5 on ADN Manual, when application on other category.

10

[2] **Core technologies** on evaluation, monitoring and inspection of infrastructure projects.

- Regarding Inspection, JICA-ADN Team supported how to use ADN Manual at District Office and at site.
- Regarding Verification, JICA-ADN Team supported how to use ADN Manual at Head Office and at site.

**(Achievement)**


- **ADN engineers acquire the Core technologies by use of ADN Manual. As a result, the work flow is visual and uniform, and procedure is more efficient than before. The system is improved.**

11



12





[3] **Fundamental knowledge** on evaluation, monitoring and inspection of infrastructure projects.

JICA-ADN Team had a lot of Lectures in classroom on Saturday at ADN head office.

**(Achievement)**

**ADN engineers acquire the Fundamental knowledge by class room lessons. As a result, the quality of verification and inspection is improved.**



## Class Room Lesson by JICA-ADN Team

### (1) Bridge

No.	Contents	Date	Entry
1	Flow of Bridge Work & Site Investigation	5/11	19
2	Bridge Plan (Superstructure)	5/18	10
3	Bridge Plan (Substructure, Foundation and Accessories)	6/1	3
4	Detail Design & How to Read Bridge Drawings	6/8	4
5	Construction method & Tender Documents (Bidding Documents)	6/29	25
6	Review of above No.1 & No.2	7/6	17
7	Review of above No.3 & No.4	7/13	14
8	Use of ADN Manual	7/27	14
9	Specification	8/3	2

### (2) Road

No.	Contents	Date	Entry
1	Pavement	5/11	19
2	Road Width & Landslide Slope Stability Analysis	5/18	10
3	Design Speed, Plan & Profile	6/1	3
4	Soil Condition, Design of Retaining Wall, Box Culvert, Landslide	6/8	4
5	Construction of Road, Pavement	6/29	25
6	Review of above No.1 & No.2	7/6	17
7	Review of above No.3 & No.4	7/13	14
8	Comment on Comoro Bridge, and so on	7/27	14
9	Comment on Pavement materials in Oecussi, Cold Mix and so on	8/3	2

17

### (3) Flood Control

No.	Contents	Date	Entry
1	Countermeasure of Flood Control	5/11	19
2	Topographic Data, Hydrologic Data, Design Discharge	5/18	10
3	Channel Characteristic, Revetment, Foot Protection	6/1	3
4	Construction of Dike, Revetment	6/8	4
5	Construction of Spur Dike, Weir	6/29	25
6	Review of above No.1 & No.2	7/6	17
7	Review of above No.3 & No.4	7/13	14
8	Comment on Loea River, and so on	7/27	14
9	Comment on Tono River, and so on	8/3	2

### (4) Electric Power

No.	Contents	Date	Entry
1	Introduction, Power Engineering, Transmission & Distribution	5/25	7
2	Power Station (Mainly Diesel Power Station)	6/29	7

18

### (5) Water Supply

No.	Contents	Date	Entry
1	How to Use EPANET with Practice (1/6)	4/29	3
2	How to Use EPANET with Practice (2/6)	4/30	10
3	How to Use EPANET with Practice (3/6)	5/3	6
4	How to Use EPANET with Practice (4/6)	5/6	5
5	How to Use EPANET with Practice (5/6)	5/8	12
6	How to Use EPANET with Practice (6/6)	3/9	6
7	Design of Rural Water Supply System (Case Study) (1/5)	5/13	7
8	Design of Rural Water Supply System (Case Study) (2/5)	5/14	8
9	Design of Rural Water Supply System (Case Study) (3/5)	5/16	5
10	Design of Rural Water Supply System (Case Study) (4/5)	5/23	5
11	Design of Rural Water Supply System (Case Study) (5/5)	5/28	4
12	How to Use EPANET & How to Use PIPECAL (1/1)	5/25	16
13	Design of Rural Water Supply System (Introduction, Water Demand)	6/1	3
14	Design of Rural Water Supply System (Water Source)	6/8	4
15	Outline of Rural Water Supply System	7/6	17
16	Diagnosis of Rural Water Supply System	7/13	14
17	Design of Rural Water Supply System (Transmission and Distribution)	7/27	14
18	One point lesson on air release valve	8/3	2

19

## [4] Coordination with relevant Ministries/Agencies

- JICA-ADN Team explained the ADN Manual to relevant Ministries/Agencies stressing use of the forms, and checklists.
- JICA-ADN Team confirmed “Schedules of the Work” specified in the ADN Manual with relevant Ministries/Agencies.
- JICA-ADN Team discussed with relevant Ministries/Agencies how to facilitate verification and inspection of the procedures.

20





## Recommendation & Achievement

### (Issues)

Request of Verification and inspection come to ADN from LM suddenly. LM also receive them from Contractor suddenly. It is hard to make efficient and effective schedule.

### (Recommendation)

LM instructs Contractor to submit Monthly & Weekly Schedule of Verification and Inspection, so that LM and ADN will share schedule at same time.

### (Achievement)

**Relationship between ADN and relevant LM is smoother than phase 1.**

## [5] Suggestion on Human resource development plan

- New organization was discussed at Dare Retreat on July 2013.



The sub-team leaders and junior engineers developed through the lessons & OJT, but still they need help of the advisers to make serious decision. Based on activities of this project, JICA-ADN Team submitted Human Resource Development Plan of ADN.

**(Achievement)**

**Human Resource Development Plan**

23

**[6] Finding & Achievement**  
through evaluation, monitoring and  
inspection of infrastructure projects

24

## **1. Road/Bridge/Flood Control (Infrastructure Fund Projects)**

### **1) Findings of FI projects on Road/ Bridge/ Flood Control**

- Team Leader, Sub Team Leader, Staffs and Indonesia Advisor carry out the verification of tender documents and inspection for payment request.
- Increase of verification of feasibility study and/or preliminary phase.
- Donor and/or MPW have complaints of 1) uncertainty of process of ADN, 2) unclear template of submit form, and 3) closed procedure system of ADN.

25

### **2) Achievements on Road/Bridge/Flood Control**

#### **(a) Upgrading human resource of FI projects on Road/Bridge/Flood Control**

- Sub-team leader is leveled up to Team Leader class and young engineers is Sub-team leader class, with use of ADN Manual and material of class room lessons of English version and Tetum version , and with OJT by Indonesia/ JICA-ADN Team.

26

### (b) Wide Use of Revised ADN Manual

- ADN engineers know it is necessary to use 1) the form & checklist, 2) the technical checklist using class room lesson's material.


### (c) Showings by JICA-ADN Team

- They were saved in ADN share folder, which are 1) materials of class room lesson, 2) short reports on site training, 3) material of MPW guidelines, 4) Revised ADN Manual.

27

## Finding No.1 of FI project


- Comparative study is necessary. The damage of abutment and revetment occurs due to local scour.





## Finding No.2 of FI project

- It is necessary to specify the area of Landslide. It is required to make safety & flexible stability structure like gabion.



## 2. Power (National Electrification Program: PEN)

### 1) Findings of PEN projects on Electric

- Team Leader and electric team carry out the verification of tender documents and inspection for payment request based on PEN Decree-Law No.40/2012.
- There are no district engineers on power, so that electric team covers all of Timor-Leste
- PEN Decree-Law requires evaluation of the plan/ design/ construction/ tender of distribution system by ADN engineers. Regarding power, there is no Indonesia Advisor in ADN.

## **2) Achievements on Power**

### **(a) Upgrading human resource of PEN projects on Electric**

- Sub-team leader is leveled up to Team Leader class and young engineers is Sub-team leader class, with use of ADN Manual, material of class room lessons of English version and Tetum version, and with OJT by JICA-ADN Team of Electric.

31

### **(b) Wide Use of Revised ADN Manual**

- ADN engineers know it is necessary to use 1) the form & checklist, 2) the technical checklist together with class room lesson's material.

### **(c) Showings by JICA-ADN Team**

- They were saved in ADN share folder, which are 1) materials of class room lesson, 2) short reports on site training, 3) material of EDTL guidelines, 4) Revised ADN Manual.

32

### 3. Water (PDID)

- **1) Findings of PDID projects on Water**
- There are lots of projects of PDID in ADN, which sectors are building, road, ditch, river development, irrigation, water supply. There are a few numbers of projects on water supply.
- ADN checklist is not efficient under the present situation such as the design drawings are far different from the site.
- ADN's inspectors must judge the facilities from the viewpoints of the function, not complying the design drawings at the inspection of some rural water supply projects.

33

- Mobile Team started to train contractors and consultants of each district for PDID projects.
- Contractors (design & construction) of PDID projects would have little technical knowledge/ experience, so that it is necessary for ADN engineers not only to verify the projects but also to coach the contractors on the plan, design, tender document and construction.
- Regarding water supply, there is no Indonesia Advisor in ADN.
- One of the main problems in rural water supply projects is lack of technical knowledge/ experience on pipeline hydraulics/calculation and pipeline profile.

34

## **2) Achievements on Water**

### **(a) Upgrading of human resource of PDID projects on Water**

Some of young engineers acquired fundamental knowledge through class room lessons, and OJT at inspection site by JICA-ADN Team of Water Supply

35

### **(b) Wide Use of Revised ADN Manual**

- Fundamental technical knowledge is required to use ADN Manual (technical checklist). Therefore technical notes were attached with existing checklist.
- As a result, ADN engineers can use technical checklist more effectively.

### **(c) Showings by JICA-ADN Team**

- They were saved in ADN share folder, which are 1) materials of class room lesson, 2) short reports on site training, 3) Revised ADN Manual, and 4) technical references such as EPANET software with the user manual and World Bank's Rural Water Supply Manual.

36

#### **4. ICT work in ADN (Outside the scope of JICA-ADN Team)**

- Donor and/or MPW have complaints of 1) uncertainty of process of ADN, 2) unclear template of submit form, and 3) closed procedure system of ADN.
- ICT Advisor starts the bellow countermeasures of information system in ADN.
- **(a) Project Monitoring System**
- ICT Team prepares the project monitoring system, which can monitor the progress of each project, sorting in sequence from oldest.

37

- **(b) Down load of Template, ADN Manual** on website of <http://adn.gov.tl>
- ICT Team will prepare the template and ADN Manual data on website.
- **(c) Project Mapping System**
- ICT Team will prepare project mapping system.
- The above information system is to cooperate between ADN and Line Ministries.

38

## [7] Workshop

- Each presenter explain **Issues** During ADN performance verification for tender documents and conduct inspection at project. They also make a suggestion about them.
- Each presenter explain process & procedure of ADN work.
- Each presenter explain sample of bad quality control work/ good quality control work.
- Please listen them and **use ADN Manual for systematic way** of process & procedure of infrastructure projects.

39

# END

- Thank you very much for your cooperation with JICA-ADN Team.


40

# Quality Control and Use of ADN Manual on Infrastructure Fund Projects

By Aleixo Amaral do Carmo

1


## FLOW CHART IN VERIFICATION OF TENDER DOCUMENTS



Contact to Administration Unit of ADN for inquiry on progress of Tender Document

2

## FLOW CHART IN INSPECTION FOR PAYMENT



Contact to Administration Unit of ADN for inquiry on progress of Inspection for Payment

3

## CHECKLIST OF VERIFICATION DOCUMENT FOR DESIGN AND BOQ (ROAD, BRIDGE, PORT & IRRIGATION)

Checklist A



**DEMOCRATIC REPUBLIC OF TIMOR LESTE  
CABINET OF PRIME MINISTER  
NATIONAL DEVELOPMENT AGENCY**

### Checklist of Verification Document for Design and BOQ

- |                      |   |  |
|----------------------|---|--|
| Name of Project      | : |  |
| Owner of the Project | : |  |
| Number of Contract   | : |  |
| Date of Receipt      | : |  |
- 
1. The Letter of Inclusion .....
  2. Design should be completed and obtained the signature by LM's Engineers .....
  3. BOQ and Estimation Cost should be gotten the signature by Public Works .....
  4. Unit Price Analysis .....
  5. Soft copy of documents which mentioned above .....
  6. Technical Specification .....
  7. It should also have the Structure and Hydrologic Calculation Analysis, and Topography data .....

*Note: This checklist is used to confirm that all the required documents are submitted for Verification Document of Infrastructure Fund project of Road, Bridge, Port, Irrigation*

4



## TENDER DOCUMENT CHECKLIST OF CONSTRUCTION FOR BUILDING & OFFICE FENCING WALLPROJECTS

**CHECKLIST A**



**DEMOCRATIC REPUBLIC OF TIMOR LESTE  
CABINET OF PRIME MINISTER  
NATIONAL DEVELOPMENT AGENCY**

**TENDER DOCUMENT CHECKLIST OF CONSTRUCTION FOR  
BUILDINGS & OFFICE FENCING WALL PROJECTS**

1. The Drawings should be approved by Public Works \_\_\_\_\_
2. Bill of Quantity ( BoQ) should be approved by Public Works \_\_\_\_\_
3. Cost Estimation should be approved by Public Works \_\_\_\_\_
4. Technical Specification should be ascertainable by Public Works \_\_\_\_\_
5. Submit the Electronic files which saved inside CD \_\_\_\_\_
6. If the buildings is more than 2 stairs, it should be attached the feasibility study of Soil or soil investigation results \_\_\_\_\_
7. If the buildings is more than 2 stairs, it should be attached the Structure Calculation analysis \_\_\_\_\_

*Note: This checklist is used to confirm that all the required documents are submitted for Verification Document of Infrastructure Fund project of Building*

## CHECKLIST OF PAYMENT DOCUMENT FOR THE SUPERVISING CONSULTANT

**Checklist D**



**DEMOCRATIC REPUBLIC OF TIMOR LESTE  
CABINET OF PRIME MINISTER  
NATIONAL DEVELOPMENT AGENCY**

**Checklist of Payment Document for the Supervising Consultant**

Name of Project : \_\_\_\_\_  
 Owner of Project : \_\_\_\_\_  
 Number of Contract : \_\_\_\_\_  
 Date of Receipt : \_\_\_\_\_

1. The Invoice in Original submitted by Consultant.....
2. The Payment Certificate in Original which obtained approval by Minister or Secretary of State.....
3. Submit the completed copy of the Valid Contract with attachment.....
4. Submit the Monthly Report which obtained approval by Project Owner.....
5. Submit No. TIN (Identification of the Taxpayer contributions Number).....
6. Number of Bank Account.....
7. Submit the valid of the Company Birth Certificate and should be legalized.....
8. Submit the Valid Economic Activity License and should be legalized .....
9. Submit the Valid of Company Ownership License.....

*Note: This checklist is used to confirm that all the required documents are submitted for Payment Document of Infrastructure Fund project of Road, Bridge, Port & Irrigation*

## INFRASTRUCTURE FUND CHECKLIST OF PAYMENT (Submitted by Contractor)

Checklist D



**DEMOCRATIC REPUBLIC OF TIMOR LESTE  
CABINET OF PRIME MINISTER  
NATIONAL DEVELOPMENT AGENCY**

### INFRASTRUCTURE FUND CHECKLIST OF PAYMENT

Name of Project :  
Name of Company :  
Contract Number :  
The Value of Contract : US\$  
The Value of Invoice/Request : US\$

No	Documents to be submitted at the Invoice	Results		Remarks
		Yes	No	
1	The contract is still valid (at least one month before expired date). The contract Value is more than 5 hundreds thousands must be subjected to get Justification Letter from the chamber of Account in the Superior Administrative Court of Timor Leste.			
2	Submit the valid of the Company Birth Certificate and should be legalized			
3	No TIN (Identification of the Taxpayer contributions Number)			
4	Submit the Valid of Company Ownership License			
5	Submit the Valid Economic Activity License and should be legalized			
6	Submit 1 Original Invoice (5 copies) and obtained approval by the LM's Techniques			
7	Request of Payment Letter			
8	The Payment Certificate approved by Line Ministries			
9	Bank Account Number of company			
10	Performance Bond should be saved in the bank as guarantee, it is a similar with the Advance Value or based on the Terms of contract			
11	The Invoice should be attached with the Monthly Progress Report			
12	International Company should attach the certificates from International Standard Organization (ISO)			

*Note: This checklist is used to confirm that all the required documents are submitted for Payment Document of Infrastructure Fund project of Building, Road, Bridge, Port & Irrigation and others.*

7


## PROBLEMS AND RECOMMENDATIONS

**PROBLEM 1.** Sometimes MPW and related LM, Consultant and Contractor do not attend the site inspection.

**RECOMMENDATION 1.** ADN will inform when the inspection is carried out.

**RECOMMENDATION 2.** In accordance with ADN Manual, MPW and Related Ministries will prepare for the inspection

8




**PROBLEM 3.** Consultant who designs a work has sometimes no appropriate background and qualification.

**RECOMMENDATION 3.** Project owners, relevant ministries or agencies, have to employ good enough consultants to work on the project.

**PROBLEM 4.** We find out contractor's activities on site that do not follow the specification.

**RECOMMENDATION 4.** Both parties, project owner and contractor should follow not only specifications but all the contract documents.

9



**PROBLEM 5.** It is specified in the ADN Manual that ADN has to complete inspection for payment within 10 days after receiving complete set of documents, but sometimes it takes more than 10 days.

**RECOMMENDATION 5.** ADN staff in charge of the inspection has to complete the document and site inspection, and then send recommendation for the payment to MPS within the specified time. But on the other hand, the project owner has to send all the required documents, specified in the ADN Manual, within the specified time and cooperate with AND on the inspection .

10

**PROBLEM 6.** Contractors complain to ADN regarding deduction of money.

**RECOMMENDATION 6.** ADN makes inspection for payment in accordance with the ADN Manual. When quality of the works is less than specified, then remedy against the defectives are issued. When quantities invoiced is more than the quantities actually completed at the time of inspection, the amount the contractor receives may be deducted from the invoiced amount.

11

## The Quality of the Construction

### Doing Construction

**Must be based on designs and technical specification:**

- Type of materials
- Quantities
- Qualities
- Dimensions
- Mixtures
- Construction Methods
- Miscellaneous(Colors, Indoors, outdoors)

12

## **Doing Construction**

**Dimensions must be based on Designs :**

- Its Length
- Its Width
- Its Height
- Its Depth
- Its Thickness
- Radius

**THE WORKS HAVE BEEN SUCCESSFUL AND CORRECTED, WHEN :**

- In accordance with the terminated time of contract
- Corrected quality based on technical specification and other technical methods.
- Corrected quantities is based on technical specification and other technical methods.
- Corrected Dimensions is based on designs, technical specification and other technical methods.
- Based on administrative matters.

13

**Some Documentations of  
Construction has been  
uncorrected/not corrected  
yet**

14






Do not used mixed concrete bar stone gravel,  
stone large diameter and should not be used  
round mixed



17


**Bad way**  
So many hollow  
holes, each  
stones must be  
mixed well with  
cement  
aggregates




**Bad way**  
So many hollow  
holes, each  
stones must be  
mixed well  
with cement  
aggregates

18









Thank You So Much  
Obrigado Wa'in  
Terima Kasih Banyak

# Rapid Assessment of ADN ADN's Role in the Infrastructure Development Process

Carolyn Peterken  
Consultant to AusAID/ADN

## Rapid Assessment – Purpose

- ▶ Propose a way forward for ADN that will enable it to better meet its current mandate
- ▶ Consider the potential transition of ADN to EPIA

## ADN's Strengths

- ▶ Has already led to significant cost savings for GovTL
- ▶ Strong sense of shared values across ADN
- ▶ Some strong HR policies, and a commitment to L&D
- ▶ Checklists to guide administrative processes
- ▶ Strong district presence
- ▶ Strong relationship with Office of the PM, and good personal relationship with other government stakeholders
- ▶ Positive internal management style


3

## Recommendations re. Internal Operations

- ▶ Articulate and maintain a **positive culture** that supports good relationships with its stakeholders
- ▶ Strengthen **capabilities**, not only technical, but also in communication, negotiation, community engagement, leadership and management...
- ▶ Add certain areas of **professional expertise**, such as legal and contract management
- ▶ Establish and communicate **standard operating procedures** on the basis of which recommendations are made
- ▶ Establish an **internal structure** with clearly identified coordinators who take a leadership role with respect to their team
- ▶ Maintain good **internal channels of communication** and information sharing as the Agency establishes a more formal organisational structure

## Framework for Learning and Development at ADN


- Annual Agency Learning and Development Plan
- Annual individual Learning and Development plans



## Draft Skills Framework for ADN

General skills/knowledge	Core engineering skills/knowledge	Working with stakeholders
<p><i>All staff</i> need an understanding of the following:</p> <ul style="list-style-type: none"> <li>•Role, structure and processes of government</li> <li>•Role, structure and processes of ADN</li> <li>•General administration</li> <li>•Portuguese language</li> <li>•English language</li> </ul>	<p><i>All technical staff</i> need a qualification and breadth of knowledge in one of the following:</p> <ul style="list-style-type: none"> <li>•Civil Engineering</li> <li>•Architecture</li> <li>•Electrical Engineering</li> <li>•IT and communications</li> <li>•Project management</li> </ul>	<p><i>All technical staff</i> need skills in the following:</p> <ul style="list-style-type: none"> <li>•Communication with stakeholders</li> <li>•Negotiation</li> </ul>
Specialised corporate/professional skills	Specialised engineering skills/knowledge	Management and leadership skills
<p><i>Some corporate staff</i> need specialised knowledge in one of the following:</p> <ul style="list-style-type: none"> <li>•Finance/FMIS</li> <li>•Procurement</li> <li>•HR management</li> </ul> <p><b>Other professional capabilities</b></p> <p><i>Some staff</i> need professional qualifications/experience in the following</p> <ul style="list-style-type: none"> <li>•Economics*</li> <li>•Social planning*</li> <li>•Environment*</li> <li>•Contract management</li> <li>•Legal</li> </ul>	<p><i>Some technical staff</i> need to specialised knowledge in one of the following areas of engineering</p> <ul style="list-style-type: none"> <li>•Roads</li> <li>•Bridges</li> <li>•Construction/buildings</li> <li>•Geotechnical</li> <li>•Water and sanitation</li> <li>•Irrigation</li> <li>•Electricity transmission and distribution</li> <li>•Renewable energy</li> <li>•Ports</li> </ul>	<p><i>Some staff</i> need to develop skills in the following:</p> <ul style="list-style-type: none"> <li>•Team management</li> <li>•Leadership</li> <li>•Communicaty engagement</li> </ul>

## Organisations potentially involved in monitoring/inspection process



7

## Challenges in infrastructure process as identified by ADN

- Different contracts used by Line Ministries
- Incomplete documents and late submissions
- Poor communications between state institutions
- Many projects have no project manger

8

## Challenges identified through Rapid Assessment process

- ▶ Lack of certainty regarding future intentions for ADN/ EPIA
- ▶ Overlap of roles ADN/MPS
  - Evaluation of projects prior to procurement
  - Processing of payments
- ▶ Overlapping mandates between ministries (or overlap in their implementation)
- ▶ Lack of clarity around project owner and project accountability, and inconsistencies between authority/ accountability
- ▶ Inefficient process leading to significant delays in both project approvals and in payments
- ▶ Lack of clarity around basis on which ADN makes its decisions/recommendations

9

## Recommendations

- ▶ Clearly define words commonly used around quality control process (“project owner”, “accountability”, “monitor”, “evaluate”, “supervise”, “inspect”, “quality control”, “certify”...)
- ▶ Produce a single document that summarises the roles of different players at each step of the infrastructure development process, their roles, authorities and accountabilities, and work through this with the respective stakeholders.
- ▶ Establish a program of regular meetings between ADN and key stakeholders at various organisational levels.
- ▶ Once finalised, share ADN’s standard operating procedures with stakeholders.
- ▶ Where possible conduct joint inspections with ADN and other stakeholders.

10

**Questions/Comments?**

**Thank You!**

## PRESENTATION ADN MANUAL FOR LINE MINISTRY PROJECT



Presented  
by  
Januario Maia Guterres

ADN was established by Decree-Law No.11/ 2011 as one of the government take initiatives to establish reform and strengthen an organizational structure of the public administration.

ADN is responsible for strict reviewing of capital development projects as follows:

- assessing merit and feasibility of capital development projects;
- supervising, inspecting and certifying capital development projects;
- managing construction projects under PDDII; and
- providing support to MDG program for Sucos.



During ADN performance of verification for tender documents and conduct of inspection at project, many issues were met as follows:

**Issues**

- Many drawings were submitted without detailed drawings.
- Regarding many designs/drawings, they were uncompleted.
- The design/drawing compared with the condition at site were very different.
- Due to a lot of BoQ, analyzing the unit price were uncompleted.
- Regarding many Payment of Document, they were uncompleted.
- Payments for the other Company were delayed because the long process to complete the document for the inspection.
- Many payments of the other Company were delayed because an administrative system does not flow.

It is effective and efficient work, that ADN has support from JICA to make ADN Manual. This Manual was helpful for the ADN to perform the job appropriately and to follow Decree-Law efficiently. So that, also this Manual have supported to LM and other relevant Institutes for supporting the responsible papers during procurement and implementation of projects at capital development.

This Manual specially explained about the process and flow chart :


- Verification of Documents for tender.
- Inspection for payment recommendation

The Manual was separate base on Category. One is forms where the fund indicated in the following table and second is to have a considerate and different procedure.


Table 3. Anticipated Category on ADN as of 2014

Class of Project	Infrastructure	Line Ministries	PDID	MDG	SEFOPE	Emergency Fund	National Electrification Programa (PEN)	Additional	Special Projects under ADN
Note				Building house	Decree Law LM	Only in emergency cases	Decree Law No: 40/2012	Only used for projects not foreseen in the budget	Upon instruction and approval by PM
Funding Source	Infrastructure Fund	Line ministries Budget	ADN	ADN	SEFOPE	Emergency Fund Managed by MoF	Infrastructure Fund	Contingency Fund managed by MoF	Funds allocated to ADN
Budget Range	Over US\$1,000,000	US\$500,000 to US\$1,000,000	(PDDI) Up to 150,000 (PDDII) 130,001 Up to 300,000	No limit	No Limit	US\$100,000 to US\$150,000	US\$ 1,000.00 to US\$ 4,500.00	Maximum 2,000,000 (Normal practice)	Upon to 10,000,000

Project Evaluation before Contract Award



### Check List of Tender Document


  
**DEMOCRATIC REPUBLIC OF TIMOR LESTE**  
**CABINET OF PRIME MINISTER**  
**NATIONAL DEVELOPMENT AGENCY**

---


**TENDER DOCUMENT CHECKLIST OF CONSTRUCTION FOR BUILDINGS & OFFICE FENCING WALL PROJECTS**

1. The Drawings should be approved by Public Works \_\_\_\_\_
2. Bill of Quantity ( BoQ) should be approved by Public Works \_\_\_\_\_
3. Cost Estimation should be approved by Public Works \_\_\_\_\_
4. Technical Specification should be ascertainable by Public Works \_\_\_\_\_
5. Submit the Electronic files which saved inside CD \_\_\_\_\_
6. If the buildings is more than 2 stairs, it should be attached the feasibility study of Soil or soil investigation results \_\_\_\_\_
7. If the buildings is more than 2 stairs, it should be attached the Structure Calculation analysis \_\_\_\_\_

### Project Inspection & Recommendation for Payment



## Check List of Payment



**DEMOCRATIC REPUBLIC OF TIMOR LESTE  
CABINET OF PRIME MINISTER  
NATIONAL DEVELOPMENT AGENCY**

**CHECKLIST OF DOCUMENT FOR THE PAYMENT OF BUILDINGS & FENCING WALL PROJECTS**

1. The Original Invoice submitted by Company _____	<input type="checkbox"/>
2. Submit the Original Payment Certificates which approved by Minister or State Secretary of Line Ministries _____	<input type="checkbox"/>
3. Submit the Copied document of the valid Contract and completed with its annex _____	<input type="checkbox"/>
4. Submit the three copies of Phisical Progress Report which approved by the Owner of Project _____	<input type="checkbox"/>
5. No.TIN (Identification of the Taxpayer contributions Number) _____	<input type="checkbox"/>
6. Bank Account Number of company _____	<input type="checkbox"/>
7. Submit the valid of the Company Birth Certificate and should be legalized _____	<input type="checkbox"/>
8. Submit the Valid Economic Activity License and should be legalized _____	<input type="checkbox"/>
9. Submit the Valid of Company Ownership License _____	<input type="checkbox"/>
10. If, the payment for 100% of phisical progress, it should attach the Term of Pre-Handover Letter (PHO) _____	<input type="checkbox"/>
11. If, the Payment of retention, it should attach the Term of Final HandOver Letter for deduction of retention money (FHO) _____	<input type="checkbox"/>

## Letter Head of Line Ministries

Date : \_\_\_\_\_ Month \_\_\_\_\_ Year

Núnumber : Ministry/ Infra Unit/ \_\_\_\_\_ (number of Letter)

To : Excellency Mr. Samuel Marçal  
Director of ADN  
In Dili

Subject : Request of Inspection  
Project of Line Ministries Fund (Type of project)  
Localization (place of project)

In response to the request of payment which submitted by company \_\_\_\_\_ (name of company). We (LM) inform that will be done the inspection for the project o \_\_\_\_\_ (name of project) with the contract number: RIDTL \_\_\_\_\_, at \_\_\_\_\_ (date of inspection). In this case, we also submitted the Invoice of companies and progress report which attached below in order to ADN could inspect and prepare the inspection report and the recommendation for payment.

Finally, we would express appreciation for your cooperation.

Chief of project \_\_\_\_\_ Approved by Minister/SOS  
(.....) (.....)

Attachment:  
1. Implementation period (Completion for the project)  
2. Summary of Project  
2. List of Quantity (BOQ)  
3. Drawings  
4. Detailed technical specification  
5. Measurement  
6. Invoice and progress report of company  
7. Others, if required



**REPUBLICA DEMOCRATICA DE TIMOR LESTE**  
**GABINETE DO PRIMEIRO MINISTRO**  
**AGENCIA DESENVOLVIMENTO NACIONAL**

Inspection Result and Recommendation for Payment	
<b>A</b> Name of Project	
<b>B</b> Ministry/Project Owner	Line Ministry
<b>C</b> Sources of Funds : ( PDD I, PDD II, PDL, H, Emergency, MDG Suco, etc)	
<b>D</b> Contractor	
<b>E</b> PO number (Purchase Order)	
<b>F</b> Project site :	<b>H</b> District : <b>b</b> Sub district : <b>c</b> Village/Hamlet :
<b>G</b> Contract Value	
<b>H</b> Previous physical progress	
<b>I</b> Physical progress up to date	
<b>J</b> Gross payment value up to date (gross)	(9.8) * 7
<b>K</b> Advance payment which paid ...%	(...56) * 7
<b>L</b> Deduction for advance payment 10%	(9.8) * 11
<b>M</b> Deduction for retention payment	(10%) * 10
<b>N</b> Value payment after deduction for retention	(10.13)
<b>O</b> Value for this payment	(14.12)
<b>P</b> Balance after this payment	7 (9 * 7)
<b>Q</b> Observation or others Commands:	
<b>R</b> Recommendation for payment to MPS/MoP/Treasurer MoP/Ministry/other relevant agency with amount (USD)	
<b>S</b> Observation	Yes    Comments    No
<b>a</b> Based on Design ?	
<b>b</b> Based on BCQ ?	
<b>c</b> Based on specification ?	
<b>d</b> Based on schedule curve S ?	
<b>e</b> Based on Terms of Contract ?	
<b>T</b> Inspection date	Date:    Month:    Year:
<b>U</b> Inspector	Signature:    Date:
<b>1</b>	Signature:    Date:
<b>Z</b>	Signature:    Date:
<b>V</b> Verified by:	Signature:    Date:
Miguel Marques Monteiro de Jesus	
<b>W</b> O.C.	Signature:    Date:
Esron St. Elmuk	
<b>X</b> Approved by:	Signature:    Date:
Dr. Samuel Marçal	
Director Geral - ADN	
<b>Y</b> Annex :	FILE PICTURE



**REPUBLICA DEMOCRATICA DE TIMOR LESTE**  
**GABINETE DO PRIMEIRO MINISTRO**  
**AGENCIA DESENVOLVIMENTO NACIONAL**

Date : \_\_\_\_ Month Year  
 To : Director of Major Project Secretary (MPS)  
 From : Samuel Marçal (Stamp and signed by Director of ADN)  
 General Director of ADN  
 Ref : \_\_\_\_\_ RDTL/ GPM /ADN / III / 20 \_\_\_\_  
 Subject : Payment Request  
 On regarding to the Payment Request No. \_\_\_\_\_ (Number of Request) by the company  
 \_\_\_\_\_ (Name of company) on the project  
 for \_\_\_\_\_ (name of project)  
 in \_\_\_\_\_ (district) \_\_\_\_\_ (sub district) \_\_\_\_\_ (Village). ADN's Technical Team which done the inspection for works referred recommends to be able making payment for existed progress. So we would ask to Major Project Secretary (MPS) when executing the payment process has to verify again the previous payment.  
 Finally. Thank You Very Much for Your collaboration .

Do not use gravel of large diameter, and follow the size of specification of contract



**Making the wrong mortar  
(excavator instead of a tool for stirring)**





- Thank you very much






# SEMINAR

Power Quality & Utilization ADN Manual Book

Presentation By  
Mechanical & Electrical Team





**PLANNING**

**SOLUTION**

**PROBLEM**

**Double Line = High Cost**

**Revoke**

Emergency Project 2010-2011

Should be Revoked ...

PEN - 2013


**PLANNING**


**SOLUTION**

**PROBLEM**


**Inefficiency = High Cost**

**Efficiency = Low Cost**









**KWH calculation of loss due to the illegal installation**

1. The number of consumers with illegal Connection	258 Houses
2. The number of consumers (KWH COMBO/Conventional)	550 Houses
3. The number of Ex. Illegal	39 Houses
4. The number of not installed /house closed	269 Houses
<b>Total</b>	<b>1.116 Houses</b>

total  $5.251 - 1.116 = 4.135$

Load per/house = 6 Ampere (1300 VA)

Number of Load 1116 Houses =  $1300 \times 1116 \times 0.8 = 1160.64$  Kwh

Kwh /day =  $24 \times 1160.64 = 27,855.36$  Kwh



\$ /Kwh = \$ 0.12 cen



❖ Loss \$/Day =  $27,855.36 \times 0.12 = \$ 3,342.64$

❖ Loss \$/Month =  $\$ 3,342.64 \times 30 \text{ Days} = \$ 100,279.20$

❖ Loss \$/Year =  $\$ 100,279.20 \times 12 \text{ Month} = \$ 1,203,350.40$


**ORDERLY**










Flow of Procedure for Quality Certification of the contract documents




Schedules of issuing Quality Certification







### Checklist A(Document to be submitted)




**AGÊNCIA DE DESENVOLVIMENTO NACIONAL**  
**GABINETE DO PRIMEIRO MINISTRO**  
**REPÚBLICA DEMOCRÁTICA DE TIMOR-LESTE**

Checklist A

Checklist for Necessary Documents from the Committee and Verification				Inspected by	Approved by
Project Name					
Stage	<b>Issue of Quality Certification before signing Contract</b>			Date of Inspection of ADN	
Project Type	Infrastructure Fund	Type of Project	National Electrification Program (PEN)	Projecting Agency	EDF
Project Site	a) District	b) Sub-district	c) Village Name:		
Check of Confirmation of Documents		Check Post for Verification		Checking	Remarks & Remarks
<b>A List of Projects</b>					
1	Location map and diagrams of lines	Maps for projects Diagrams of planned and existing 20kv overhead on lines	Yes/No		
2	Sheet of the list of projects	Name and address, population of each non electrified village for each project. The approximate length of new lines of 20kv for each project. Rate of the population and length of the line for the effect and cost.	Yes/No Yes/No Yes/No		
3	Order of priority for the selection	Order of priority for the implementation of projects	Yes/No		
4	Formulation of the Project	Reason for putting the order of priority.	Yes/No		
5	The justification of the project	Reason of priority of the project in the district and subdistrict Summary of cost and benefit (effect)	Yes/No Yes/No		
6	The location map	The maps with the area of the works and existing lines	Yes/No		
7	Outline of villages to be electrified	The name, numbers of household, population and income issues	Yes/No		
8	So. ent. futures of the Project	Location, name of sub-district & district, length of 20kv & 380v lines, numbers of houses, budget, name of company, etc.	Yes/No		
<b>3 Selection of the Company</b>					
1	Publicity of the project	The documents related to publicity through the public newspaper	Yes/No		
2	Justification of the Company	Including evaluation of the selection with criteria by the Committee	Yes/No		
3	The minute of meeting for selection	Record of minute of the district and MPS as well as their attendance	Yes/No		
4	Eligibility of Company	The proof of tax payment in the last quarter and certification of registration	Yes/No		
5	The list of similar previous experiences	Name, contract price, type of the works, year of implementation, etc.	Yes/No		
6	The list of engineers for the project	Civil electrical & civil engineers and minimum requirements with name, years and list of experiences	Yes/No		
7	Information on involvement of Veteran	Involved or not and if any what kind involvement?	Yes/No		
<b>4 The Contract Documents</b>					
1	So. ent. futures of the Project	Location, name of sub-district & district, length of 20kv & 380v lines, numbers of houses, budget, name of company, etc.	Yes/No		
2	Contract Agreement (without signing)	Contract price, start day and intended completion day	Yes/No		
3	General Condition with Contract Data	Payment conditions such as advance payment, retention bank security	Yes/No		
4	Technical Specifications	Prescription of quality of materials & components listed in the BOO	Yes/No		
5	Standard Construction	Construction method for main components	Yes/No		
6	Design Drawings	Description of main elements of BOO in the drawings	Yes/No		
7	BOO	Estimated quantities and unit price	Yes/No		

Note: The circle numbers show minimum requirement of documents submitted by the Commission for verification by the ADN

### Confirmation of Payment Request by the PEN Commission



**REPÚBLICA DEMOCRÁTICA DE TIMOR-LESTE**  
**GABINETE DO PRIMEIRO MINISTRO**  
**AGÊNCIA DE DESENVOLVIMENTO NACIONAL**

Form A-1

Date : 25 October, 2012

To : Sr. Kassiuis Klei  
 Head of the Management and Implementation Commission of PEN

From : Sr. Samuel Marçal  
 General Director of the Agencia de Desenvolvimento Nacional

CC : S.E. Januario da Costa Pereira  
 Secretary of State of the Electricity

Ref : \_\_\_\_\_ RDTI/GPM/ADN/X/2012

**Subject : Necessary Documents Submitted by the Commission of PEN**

With respect,  
 Based on Decree Law No. 11/2011: Agência Desenvolvimento Nacional (ADN) and Decree Law No. 40/2012: Programa Eletrificação Nacional (PEN) which gives role to the ADN as Quality Control & Auditing to the all Project funded by government budget, the Team has carried out confirmation of the documents which is submitted by the Management and Implementation Commission to the ADN.  
 Result of confirmation of the necessary documents to be submitted is shown as follows with the result of Checklist A (Attachment):

Project Name : \_\_\_\_\_

Project Site : \_\_\_\_\_


Company Name : \_\_\_\_\_

Type of Verification : 1. List of Project   
 2. Formulation of the Project   
 3. Selection of the company   
 4. Contract Document

Result of Confirmation of the Document: **APPROVES/ APPROVES with NOTE /PENDING/REJECT**

RECOMMENDATION BY ADN

Thank you for your attention and collaboration.



**REPÚBLICA DEMOCRÁTICA DE TIMOR-LESTE**  
**GABINETE DO PRIMEIRO MINISTRO**  
**AGÊNCIA DE DESENVOLVIMENTO NACIONAL**

Form A-2

Date : 25 October, 2012

To : Sr. Kassiuis Klei  
 Head of the Management and Implementation Commission of PEN

From : Sr. Samuel Marçal  
 General Director of the Agencia de Desenvolvimento Nacional

CC : S.E. Januario da Costa Pereira  
 Secretary of State of the Electricity

Ref : \_\_\_\_\_ RDTI/GPM/ADN/X/2012

**Subject : Result of Verification of Documents of the Project of PEN**

With respect,  
 Based on Decree Law No. 11/2011: Agência Desenvolvimento Nacional (ADN) and Decree Law No. 40/2012: Programa Eletrificação Nacional (PEN) which gives role to the ADN as Quality Control & Auditing to the all Project funded by government budget, the Team has carried out verification of the documents which is submitted by the Management and Implementation Commission to the ADN.  
 Result of Verification of the documents is shown as follows with the result of Checklist A (Attachment):

Project Name : \_\_\_\_\_

Project Site : \_\_\_\_\_

Company Name : \_\_\_\_\_

Type of Verification : 1. List of Project   
 2. Formulation of the Project   
 3. Selection of the company   
 4. Contract Document

Result of Verification of the Document: **APPROVES/ APPROVES with NOTE /PENDING/REJECT**

RECOMMENDATION BY ADN

Thank you for your attention and collaboration.


INSPECTION REPORT AND RECOMMENDATION FOR PAYMENT			
1	Name of Project		
2	Type of Project	National Reconstruction Program	
3	PO Number (Purchase Order)		
4	Name of Contractor		
5	Type of Payment Request	Interim Payment (First, Second, Third), Provisional Handover, Final Handover	
6	Schedule to the Work	Start day	Intended Completion day
7	Payment conditions	Advance payment ( %), Retention ( %), Repay of Retention ( % at Completion day), etc.	
8	Project site	District & Sub-district	Village/Samurai
9	Contract Price		1,000,000.00
10	Gross Payment until now		000,000.00
11	Billing in this invoice from the Contractor		000,000.00
12	Billing verified by the Inspector		000,000.00
13	Advance payment ( 10 % of Contract Value)	(13) = 10%	100,000.00
14	Reduction for advance payment	(13) - (12) (a)	0.00
15	Reduction for retention ( 10 %)	(12) * 10%	0.00
16	Payment after reduction	(12) - (14) - (15)	0.00
17	Retainage for previous retention		0.00
18	Payment for this month	(14) - (15)	0.00
19	Balance after this payment	(9) - (10) - (16)	0.00
20	Progress for previous payment (%)	(10) / (9)	0%
21	Progress for this payment (%)	(10) / (9)	0%
22	Inspection of Documents	Documents	Any Problems & Comments
	B. COPIES Documents	Yes/No	
	B.100 of completed quantities	Yes/No	
	A3. BUILD Drawing at Handover	Yes/No	
	Program Schedule of the Work	Yes/No	
	Testing Result for the Work	Yes/No	
	Inspection Report	Yes/No	
	Records of Completed Work	Yes/No	
23	Result of inspection (Result of Document Inspection) Check items as reference: "Documents for invoice are prepared correctly?" "The payment request meets payment conditions under the contract?" "Completion of work is correct?" "Any remarks are made by the Committee?" "Testing result meets the criteria?" Result of the inspection: Check items as reference: "The Committee is satisfied at the site and gives satisfaction?" "The important components for function and the size of quantities in the Bill are checked?" "Any problems in quality of work quality of material and installation, etc.?" "Any problems in quantity (Difference between actual and that in Bill)?" Judgment for payment: Check items as reference: "The recommended payment is the same as the invoice of bill?" "Is the reason of severe reduction?" "Any other recommendation of remedy is made?"		
24	Proposed payment in the invoice from the Contractor (USD)		000,000.00
25	Recommendation for payment to MPS/MoF (USD)		
26	Site inspection day	Day	Month
27	Inspector	Signature	Date
	J. Maximus dos Santos	Signature	Date
	J. Ana Maria Gutierrez	Signature	Date
28	Verified by	Signature	Date
	Miguel Marques Monteiro de Saes	Signature	Date
29	Approved by	Signature	Date
	Dr. Samuel Marçal	Signature	Date
30	Director General - ADN		
31	Agency Employer		




# THE PRESENTATION OF ADN MANUAL REGARDING PDID PROJECT

BY  
Demistocles Cabral

## FLOW CHART PDID PROCESS INSPECTION AND PAYMENT



## FLOW CHART PDID PROCESS OF PROJECT WORK



## PROBLEM AND RECOMMENDATION

### Problem

- Without Line coordinated with Ministry and other District
- Design Document and BOQ submitted delay will be impacted to implementation process
- Many failure were found in implementation because the design not to reflect the actual site condition.

### Recommendation

- To make coordinated with other Ministry (LM)
- Requested to all Ministry to submitted Design and BOQ base on schedule were determinate.
- Requested to all Ministry to controlling their Consultant and avoided to have reserve fund.

# PAYMENT FORMAT OF CHECK LIST



REPÚBLICA DEMOCRÁTICA DE TIMOR LESTE  
GABINETE DO PRIMEIRO MINISTRO  
AGENCIA DESENVOLVIMENTO NACIONAL

## Format: Payment

INSPECTION REPORT AND RECOMMENDATION FOR PAYMENT			
1	Name of Project		
2	Ministry/Project Owner		
3	Sources of funds		
4	Contractor		
5	PO Number (Purchase Order)		
6	Project site :	a. District : Manufahi	
		b. Sub District : Same	
		c. Villag/Hamlet : Letefoho	
a	Contract Value	a	\$ 125,398.59
b	Progress for previous payment	b	80.00%
c	Progress for this payment	c	100.00%
d	Gross Payment until now	(c-b)*a	\$ 25,079.71
e	Advance payment: (10%) of Contract Value	...%*a	\$
f	Reduction for advance payment	e	\$
g	Reduction for retention	0.1*d	
h	Payment after reduction for retention	d-g	\$ 25,079.71
i	Release for (50%) previous retention	h-f	\$ 25,075.71
j	Total Net Payment until now		\$ 112,858.70
k	Balance after this payment	(100%-c)*a	\$
7	Observation or comment : ADN team, based on inspection of the potable water supply project in Fatumea that relies its power source on the solar panel system, verifies that the project has been reached to 95%, and therefore we ensure to take necessary procedures for the payment of the 90% physical progress.		

8	Recommendation for payment to Treasurer-MoF/Ministry/Agency Tutela (USD)		12,600.00
9	Observation :	YES	Any comments
		NO	
a	Drawings	✓	
b	BOQ	✓	
c	Technical specification	✓	
d	Schedule of S shape curve	✓	
e	Payment conditions in the contract	✓	
10	Inspection date	Date:	Month: Year:
11	Inspector :	Signature:	Date :
	1. Lourdes Pereira		
	2. Manuel Martins		
	Verified by :	Signature:	Date :
	Sônia Freitas Moreira		
12	Q.A	Signature:	Date :
	Esron St. Henuk		
13	Approved by :	Assinatura:	Date :
	Sr. Samuel Marçal		
	General Director - ADN.		
14	Annex :	Some photographys of Site inspection	





Format : Check List

REPÚBLICA DEMOCRÁTICA DE TIMOR LESTE  
GABINETE DO PRIMEIRO MINISTRO  
AGÊNCIA DESENVOLVIMENTO NACIONAL

No.	Name of Document	Condition						Remark
		Yes	No	Completed	Uncompleted	Yes	No	
1	Requested payment from Company to KDD (Original)							
2	Inclusion letter from KDD Coordinator (Original)							
3	Copy Contract document if the project is handed over while the contract is expired, it should attach with a Original document or copy of valid contract at minimum until the first date of provisional hand over of the project .							
4	The payment certificate which prepared by manager of Public Works/ KDD technique, verified by District ADN engineer and approved by KDD Coordinator (Original) - <b>for payment of II PDD Project at 2012 and PDID only.</b>							
5	Term of Hand over of final project (Original)							
6	Final Inspection Sheet for retention							
7	Copy the Term of first/provisional Hand over of the Project							

8	Copy the document of the Valid Economic Activity License, minimum until one month from submission date of payment request (legalized), it is <b>not applied for KIK (Communitarian Project)</b>							
9	Copy document of the Valid Company Birth Certificate, minimum until one month from submission date of payment request (legalized)- it is <b>not applied to KIK(Communitarian Project)</b>							
10	Copy document of TIN(Identification of the Taxpayer contributions) it is <b>not applied to KIK(Communitarian Project)</b>							
11	Copy document of Company Ownership License – it is <b>not applied to KIK(Community Project)</b>							
12	Copy Bank Account Number of Company							
13	Copy Electoral Card of Director Company							
14	Documentation (Picture based physical progress.							
15	As Built Drawing Based on result of implementation - <b>only for payment of PDID Project.</b>							
16	Copy Design and BoQ which already approved – <b>for PDD project at 2012 only.</b>							



## Another Example: Bad Design to Bad Result

There is no monitoring tank in the design.



To built a monitoring tank.

## Issues 2: Inspection

Inspection is to ensure that the contractor's work is carried out in accordance with contract documents including design drawings and specifications of the project. The inspection is impossible theoretically when the drawings do not reflect the actual site condition.

**The construction works has finished, but water cannot flow in the pipeline.  
Should the contract payment be paid?**





## Payment

In a case that water cannot flow

	Design	Construction	Payment
Case 1	Bad	Not carried out in accordance with contract documents	x
Case 2	Bad	Carried out in accordance with contract documents	?
Case 3	Good	Not carried out in accordance with contract documents	x

**Thank You!!!**  
**Obrigado Barak!!!**

# Overview of JICA Assistance to ADN and Way Forward

AND seminar on September 20, 2013

Southeast Asia and Pacific Department  
Japan International Cooperation Agency (JICA)

## Tasks of JICA Assistance to ADN

- Task #1) Facilitate efficient work flow of ADN and provide basic skill trainings for project inspection, review and monitoring (along with its Organic Law)
- Task #2) Clarify the role of ADN among Ministries; especially between ADN and MOF/MPS (development planning coordination), ADN and Line Ministries, such as MPW (technical operational coordination)

## Overview of JICA Assistance (Initial Stage)

INPUTS	2011	2012				2013				2014
		I	II	III	IV	I	II	III	IV	
Dispatch of Short Term Experts		→								
- Expert on Road & Bridges		●	●							
- Expert on Ports		●								
- Water Sanitation				●						

**Key Achievements:** Developed training programs on basic skill development for major infra. project inspection, review, and monitoring, etc.

## Overview of JICA Assistance (Basic Capacity Development)

INPUTS	2011	2012				2013				2014
		I	II	III	IV	I	II	III	IV	
Dispatch of JICA-ADN Expert Team			→ Phase I			→ Phase II				
- Expert on Road & Bridges #1			→			→				
- Expert on Road & Bridges #2			→			→				
- Expert on Power			→			→				
- Expert on Water			→			→				
- Expert on Port & Aviation			→							
Infrastructure Advisors (to supervise the team)			●	●	●	●	●	●		

**Key Achievements:** [Phase I: Jun - Nov, 2012] Development of ADN work manuals & check lists and OJT, etc / [Phase II: April - September, 2013] Harmonize ADN work manual & check lists with ADN daily work including updating them and OJT, etc

## Overview of JICA Assistance (Planning for the Future)

INPUTS	2013				2014				2015			
	I	II	III	IV	I	II	III	IV	I	II	III	IV
Development Administration Advisor / Advisor to DG of ADN (Mr. Todoroki)												

**Key Tasks: Assist in contract management / Assist in quality control of administrative works of ADN / Assist DG in designing organizational structure of ADN / Provide policy recommendations on establishment of EPIA based on PM's instruction/ Coordinate ADN with other JICA related assistance**

## Other Relevant Cooperation (Training Programs and Japan or Third Countries)

2011

- Training Program for Young Leaders for Timor-Leste/Urban Environmental Management Course

2012

- Economic Development Policies in Japan
- Maintenance of Mountain Road in Japan
- Road Administration in Japan
- Project Management Training in Philippines
- Study Visit to BAPPENAS, BAPPEDA, and NEDA

2013 (In Process)

- National Government Administration for Senior Officials in Japan
- Environmental Planning for Sustainable Tourism in Singapore

## Other Relevant Cooperation

- Road Policy Advisor to MPW (~2014)
- Advisor on Improvement of Water Supply System to DNSA (~2014)
- Dili Urban Master Plan (~2014)
- Port Management Advisor (~2015)
- Aid Coordination Advisor to MOF (~2014)

## Way Forward :JICA's future cooperation

- Identifying Concrete Roles of ADN in TL Government
  - 【Task 1】 Defining the scope of works of ADN
- Designing Organizational Structure
  - 【Task 2】 Well designing organizational structure in accordance with the defined scope of works



**Development Administration  
Advisor could support**

## Way Forward :JICA's future cooperation

- Strengthening Coordination Mechanism with Line Ministries

【Task 3】 Establishing coordination task forces and meeting bodies with line ministries

JICA-ADN Team is supporting the effort / relevant Advisors to line ministries, such as MPW, could support in facilitating coordination with the line ministries



## Way Forward :JICA's future cooperation

- Continuing Improvement of Basic Skills in Engineering and Evaluation

【Task 4】 Promoting Self-study

JICA-ADN Team prepared educational materials, which will be useful for daily works, through the class room lectures / Opportunity of JICA's Long Term Training in Economics and Public Administration



## Way Forward :JICA's future cooperation

- Strengthening Development Planning Capacity  
【Task 5】 Capacity Development in socio-economic analysis, development planning and budgeting, etc.



Development Administration  
Advisor could support / Opportunity  
of JICA's Long term training / New  
Technical Cooperation Project for  
capacity development once PM's  
decision is made

# Thank you!