

資料編

【資料編】

資料－１ 調査団員・氏名

資料－２ 調査行程

資料－３ 関係者（面談者）リスト

資料－４ 討議議事録(M/D)

資料 4.1 現地調査時（2013年3月18日）

資料 4.2 概要説明時（2013年11月15日）

資料－５ 参考資料

資料 5.1 Technical Notes（T/N）

資料－６ その他の資料・情報

資料 6.1 ボーリング調査結果（各地点の粒径加積分曲線）

資料 6.2 波浪解析

資料 6.3 ホニアラ港周辺道路の交通量調査

資料一1 調査団員・氏名

(1) 現地調査

現地調査の調査団員の構成は、以下のとおりである。

氏名	担当	所属
勝田 穂積	総括	国際協力機構 国際協力専門員
福原 さおり	調査計画管理	国際協力機構 経済基盤開発部 平和構築・都市・地域開発グループ 平和構築・都市・地域開発第一課
越智 裕	業務主任／港湾計画	株式会社エコー
山本 雄平	自然条件調査	株式会社エコー
山田 俊夫	港湾施設計画	株式会社ドラムエンジニアリング
酒井 修二	施工計画／積算	株式会社エコー
畠山 祐二	環境社会配慮	有限会社プロジェクト環境
一之瀬 政男	組織運営管理	一般財団法人国際臨海開発研究センター

(2) 概要説明調査

概要説明現地調査の調査団員の構成は、以下のとおりである。

氏名	担当	所属
勝田 穂積	総括	国際協力機構 国際協力専門員
越智 裕	業務主任／港湾計画	株式会社エコー
山田 俊夫	港湾施設計画	株式会社ドラムエンジニアリング
一之瀬 政男	組織運営管理	一般財団法人国際臨海開発研究センター

資料-2 調査行程

(1) 現地調査

日 順	月 日	JICA 団員		コンサルタント団員							
		勝田穂積	福原さおり	越智 裕	山田俊夫	一之瀬政男	島山祐二	山本建平	酒井修二		
		(a)総括	(b)計画管理	(e)業務主任/港湾計画	(c)港湾施設設計	(f)組織運営管理	(e)環境社会配慮	(b)自然条件調査	(d)施工計画/積算		
1	3/7	木				成田-シンガポール シンガポール					
2	3/8	金				→プリズベン プリズベン-ホニアラ					
3	3/9	土				港湾活動及び施設状況視察					
4	3/10	日				国内会議、港湾活動及び施設状況視察					
5	3/11	月				SPA表敬及びインセプション・レポート説明					
6	3/12	火				JICAソロモン表敬及びインセプション・レポート説明、港湾施設踏査（国際埠頭、国内埠頭）、背後主要道路視察					
7	3/13	水				現地調査及び資料収集					再委託業者との契約、打合せ（測量範囲の現地確認）
8	3/14	木									
9	3/15	金				プリズベン-ホニアラ					
11	3/16	土									
11	3/17	日				コンテナ船見学・船長ヒアリング					資料整理
											資料整理
											資料整理
12	3/18	月				SFA 全体会議及びミニッツ協議、インフラ開発省表敬及びミニッツ協議					
						ミニッツ最終調整					コンテナ船見学・船長ヒアリング
13	3/19	火				ドナー関係者への説明（ADB、AusAID、PIAC他）					
						ミニッツ協議・署名、日本大使館表敬・報告					
14	3/20	水				報告資料作成等					コンテナヤード 荷役状況調査
15	3/21	木				ホニアラ-プリズベン					
											再委託調査調整 自然条件関連資料収集
16	3/22	金									
17	3/23	土									
18	3/24	日									
19	3/25	月									
20	3/26	火									
21	3/27	水									
22	3/28	木									
23	3/29	金									
24	3/30	土									
25	3/31	日									
26	4/1	月									
27	4/2	火									
28	4/3	水									
29	4/4	木									
30	4/5	金									
31	4/6	土									
32	4/7	日									
33	4/8	月									
34	4/9	火									
35	4/10	水									
36	4/11	木									
37	4/12	金									
38	4/13	土									
39	4/14	日									
40	4/15	月									
41	4/16	火									
42	4/17	水									
43	4/18	木									
44	4/19	金									
45	4/20	土									
46	4/21	日									
47	4/22	月									
48	4/23	火									
49	4/24	水									
50	4/25	木									
51	4/26	金									

(2) 概要説明調査

日 順	月 日		JICA 団員	コンサルタント 団員		
			勝田穂積	越智 裕	山田俊夫	一之瀬政男
			(a) 総 括	(a) 業務主任/港湾計画	(c) 港湾施設設計	(f) 組織運営管理
1	10/1	火	成田→シンガポール シンガポール→			
2	10/2	水	→プリズベン プリズベン→ホニアラ JICAソロモン表敬及び準備調査報告書(案)説明			
3	10/3	木	SIPA表敬、準備調査報告書(案)説明・協議			
4	10/4	金	財務省次官及びインフラ開発省次官表敬及び準備調査報告書(案)説明・協議 団内打合せ			
5	10/5	土	団内打合せ、現地踏査			
6	10/6	日	ホニアラ→プリズベン プリズベン→	団内会議、資料作成		
7	10/7	月	→シンガポール シンガポール→成田	現地踏査、テクニカルノート(T/N)協議、資料作成		
8	10/8	火	/	SIPAへの準備調査報告書(案)の詳細説明・協議、T/N協議		
9	10/9	水		日本大使館表敬・報告、JICAソロモン報告 現地コンサルタントヒアリング、T/N署名、資料作成		
10	10/10	木		資料作成 ホニアラ→プリズベン プリズベン→		
11	10/11	金		→シンガポール シンガポール→成田		

資料－3 関係者（面談者）リスト

(1) ソロモン諸島国官公庁

1) Ministry of Infrastructure Development (MID)

Mr. Moses Soajonga Virivolomo Permanent Secretary

Mr. Jimmy Nuake Director, Civil Engineering

2) Ministry of Finance and Treasury

Mr. Shadrach Fanega Permanent Secretary

3) Solomon Islands Port Authority (SIPA)

Mr. Glyn Joshua General Manager (AG), Director, Corporate Service"

Mr. Ronald Ivupitu Director Engineering

Ms. Bridget Wafuni Management Accountant

Mr. Leonald Bava Operation Manager (AG)

Mr. Ashley Hangio Chief Security

Mr. Hugo John Bugoro Operation Manager

Mr. Romeo Vilaka Property Officer

Mr. Santus Siota Project Engineer

Capt. Judah Kulabule Harbour Master

Capt. Vitale Tangisi Harbour Pilot

Mr. Reginald Alatala Workshop Manager

Mr. George Rausi Director Finance

Mr. Benny Legua ICT Manager

Mr. Dean Pitu Statistic Officer

Mr. Ken Grossmith Member of Board

Mr. William Berile CEO

4) Ministry of Natural Resource

Mr. Alison K. P. Principal Seismology Officer, Seismology Section

5) National Disaster Management Office

Mr. Jonathan T. F. Deputy Director

6) Environmental and Conservation Division, Ministry of Environment, Climate Change, Disaster Management and Meteorology (MECDM)

Mr. Tia Masolo Deputy Director of Environment

Mr. Edward Jonathan Danitofea Senior Environment Officer

7) Solomon Water

Mr. Silas Talosui Team Leader, Network Maintenance

- 8) Honiara City Council
- | | |
|-------------------------|------------------------------|
| Mr. George Titiulu | Principal Health Inspector |
| Ms. Christine Ouahikeri | Health Inspector |
| Ms. Mercy Iilv Nunva | Environmental Health Officer |

(2) 国際機関

1) Asian Development Bank (ADB)

Mr. Paula Baleilevuka	Director
-----------------------	----------

2) Australian Agency for International Development (AusAID)

Mr. Scott McNamara	Senior Development Program Specialist
--------------------	---------------------------------------

3) Pacific Infrastructure Advisory Centre (PIAC)

Mr. John Austin	
Mr. Jan Willen Overbeek	

4) World Fish Center (WFC)

Dr. Anne-Maree Schwarz	Scientist
Mr. Waghon Lalao	Business Manager, Corporate Service Division

5) World Wide Fund for Nature (WWF)

Mr. Duddley Marau	Finance manager
-------------------	-----------------

(3) 民間会社

1) iBusiness

Ms. Grace NG	CEO
Mr. Jonathan Foong	Consultant

2) iPacific Frontieers Limited

Dr. Deogratias Harorimana	CEO & Chairman
Mr. Salome Kwaiga	Chief Operating Officer

3) Beca

Mr. Graeme Roberts	Technical Director
Mr. John Youdale	Project Director
Mr. Alex Wong	Civil Engineer
Ms. Deborah Robertson	Senior Planner

4) Greater Bali Hai

Mr. Alfred Chan, Capt.	Ship Master, Coral Islander
Mr. Gideon P. Avengoza, Capt.	Ship Master, Tropical Islander

- 5) Swire Shipping
 Capt. Nigel R. S. Prosser Ship Master, High Land Chief
 Capt. Jeff Liew K. F. Ship Master, Kwangsi
- 6) Tradco
 Mr. Gerald Stenzel Managing Director
- 7) Kitano Construction
 Mr. Fujii Yasushi Project Manager
- 8) Solomon Kitano Mendana Hotel
 Mr. Masao Yamagata General Manager
- 9) Solomon Sheet Steel Ltd.
 Mr. Jason Lee Managing Director
- 10) DALGRO (SI) L td.
 Mr. Keith Douglas General Director
 Mr. Reginald Douglas Managing Director
 Mr. Armando Marco Site Manager
- 11) Nofokava Construction Ltd.
 Mr. Francis Nori Nofokava Managing Director
- 12) Hatanga Limited
 Mr. Jeremy Barlett Manager
- (4) 日本国関係者
- 1) 在ソロモン日本国大使館
 中嶋 敏 大使
 岩撫 明 前大使
 小幡ひとみ 専門調査員
- 2) JICA ソロモン諸島支所
 臼井太二 支所長
 瀧下良信 前支所長
 ラカ直子 企画調査員

資料一4 討議議事録(M/D)

(1) 現地調査 (2013年3月18日)

**Minutes of Meetings
on the Second Preparatory Survey for Outline Design
on
the Project for Improvement of Honiara Port Facilities
in Solomon Islands**

**Agreed upon
Between the Government of Solomon Islands
And Japan International Cooperation Agency**

Referring to the result of Preparatory Survey in September 2011, the Government of Japan (hereinafter referred to as "the GOJ") decided to conduct a Second Preparatory Survey for Outline Design on the Project for Improvement of Honiara Port Facilities in the Solomon Islands (hereinafter referred to as "the Project") and entrusted the survey to the Japan International Cooperation Agency (hereinafter referred to as "JICA")

JICA dispatched the Second Preparatory Survey Team for the Project (hereinafter referred to as "the Team") to the Solomon Islands, headed by Mr. Hozumi Katsuta, Advisor, JICA, and conducted the survey from March 14 to March 21, 2013.


The Team held a series of discussions with the officials concerned of the Government of Solomon Islands (hereinafter referred to as "the SIG") and conducted a field survey in the Project area.

As a result of the discussions and field survey, both sides have confirmed the main items described in the attached sheets. It should be noted that implementation of the Second Preparatory Survey does not imply any decision or commitment by JICA to extend its grant for the Project at this stage.

Honiara, 18 March, 2013




Moses Virivolomo
Permanent Secretary
Ministry of Infrastructure Development
Solomon Islands




Hozumi Katsuta
Leader
Second Preparatory Survey Team
Japan International Cooperation Agency

(Witness by)



Glyn Joshua
Acting General Manager
Solomon Island Ports Authority
Solomon Islands



Shadrach Fanega
Permanent Secretary
Ministry of Finance and Treasury
Solomon Islands

ATTACHMENT

1. Objective of the Project

The objective of the Project is to improve the Honiara Port facilities.

2. The Proposed Project Site

Honiara Port in Point Cruz, as shown in Annex 1.

3. Responsible and Implementing Organizations

3-1. The responsible organization is the Ministry of Infrastructure Development

3-2. The implementing organization is the Solomon Island Ports Authority (SIPA)

3-3. The organization chart of SIPA is as shown in Annex 2

4. Items Requested by the SIG

4-1. The components of the Project requested by the SIG for Improvement of Honiara Port Facilities

No.	Items	Description	Quantity
1	International Wharf		
(1)	Sea Wall	Steel sheet pile wall with re-concrete superstructure	150 m
(2)	End Revetment	Steel sheet pile wall and rubble mound revetment	125 m
(3)	Dredging and Filling	-1 m and fill for container yard	17,000 m ³
(4)	Mooring Dolphin	Steel pile and grating catwalk	2 nos.
(5)	Removal of Existing Dolphin		1 ls
2	Container Yard		
(1)	Yard Pavement	Concrete pavement with storm drainage	10,500 m ²
3	Accessories		
(1)	Water Supply and Fire Fighting	Water supply piping underground with F/F hydrants along the wharf	1 ls
(2)	Lighting for the Wharf	Outdoor lighting pole	1 ls
(3)	Boundary Security Fence	H2.5m L300m with security gate	1 ls
(4)	Mobile Crane	Capacity 45 t	1 ls

4-2. JICA will assess the necessity, relevancy and degree of urgency of the requested components through the survey and will report the findings to the GOJ. Implementation and components of the Project will be decided by the GOJ.

4-3. Through the site survey and a series of discussion, both sides agreed upon the priority of the Project components, in the following order:

Handwritten signatures and initials:
H/K

D

No.	Component	Priority	Remarks
1.	International Wharf		
(1)	Seawall	First	
(2)	End Revetment	First	
(3)	Dredging and Filling	First	
(4)	Mooring Dolphin	First	
(5)	Removal of Existing Dolphin	-	No Significant Obstacle for the Project
2.	Container Yard		
(1)	Yard Pavement	Second	
3.	Accessories		
(1)	Water Supply to the wharf	Second	
(2)	Fire Fighting at the wharf	-	Procured by SIPA
(3)	Lighting for the Wharf	Second	
(4)	Boundary Security Fence	-	Security Fence already installed along the Port Boundary
(5)	Mobile Crane	-	All Container Ships calling to Honiara Port equip ship's gear. And SIPA owns small size crane and the rental is possible.

Both sides agreed that the Project components to be constructed by Japan's Grant Aid Scheme be the first and second prioritized.

5. Japan's Grant Aid Scheme

- 5-1. The SIG understands the Japan's Grant Aid scheme explained by the Team, as described in Annex 3 and 4.
- 5-2. the SIG will take the necessary measures, as described in Annex 5, to facilitate the smooth implementation of the Project, if the Japan's Grant Aid is implemented, as a condition for the Japanese Grant Aid to be implemented.

6. Environmental and Social Considerations

- 6-1. The Team explained the outline of JICA Guidelines for Environmental and Social Considerations (hereinafter referred to as "the JICA Guidelines") to the SIG. The SIG understood the concept of the JICA Guidelines and confirmed to conduct the necessary procedure.
- 6-2. The responsible organization for environmental and social considerations of the Project is SIPA under the direction of Ministry of Environment, Climate Change, Disaster Management and Meteorology.
- 6-3. The Team explained EIA/IEE (Development Consent) had to be approved by Ministry of Environment, Climate Change, Disaster Management and Meteorology before the

[Handwritten signatures and initials]

Exchange of Notes to be signed between both governments for the implementation of the Project.

7. Schedule of the Study

7-1. The consultants will proceed to further studies in Honiara until April 25, 2013.

7-2. JICA will prepare the draft report and dispatch a mission in order to explain its contents around September, 2013.

8. Undertakings of the SIG

The SIG shall act as a counterpart agency to the survey team and also as a coordinating body with other organizations concerned for the smooth implementation of the Second Preparatory Survey.

The SIG shall, at its own expense, provide the survey team with the following items in cooperation with other organizations concerned:

- (1) security-related information as well as measures to ensure the safety of the survey team;
- (2) information as well as support in obtaining medical service;
- (3) data and information related to the Second Preparatory Survey;
- (4) counterpart personnel;
- (5) suitable office space with necessary equipment and secretarial service;
- (6) credentials or identification cards;
- (7) entry permits necessary for the survey team members to conduct field surveys;
- (8) support in making transportation arrangements;
- (9) support in obtaining other privileges and benefits if necessary;
- (10) the SIG shall assist the team in custom clearance, exempt from any duties with respect to equipment, instruments, tools and other articles to be brought into and out of Solomon Islands in connection with the implementation of the survey. For the equipment for boring works, in particular, the SIG shall proceed necessary procedure of tax exemption for importation of it as soon as possible, and
- (11) the SIG shall bear claims, if any arises, against the members of the survey team resulting from, occurring in the course of, or otherwise connected with the discharge of their duties in implementation of the Second Preparatory Survey, except when such claim arise from gross negligence or willful misconduct on the part of the member of the survey team.

9. Other Relevant Issues

(1) Responsibility of SIPA

- The Survey report will be prepared through the full consultation with SIPA.

- Primary accountability about the Project rests with the SIG.

(2) Management structure of SIPA

The SIG confirmed that basic stance of the SIG to implement the Project would not be changed even after the assignment of new General Manager.

(3) Financial condition of SIPA


SIPA explained that financial condition of SIPA was sound and it had accumulated debt amounting up to approximately 1.061US\$ (One Million and sixty one Thousand United State Dollar, as of November, 2012) which is in the trend of decrease because of increase of income raised by cargo volume increase.

(4) Separation of cargo operation function

The Team informed that the possibility of separation of cargo operation function from SIPA, as one option of SIPA's restructuring, will be studied because it would be a good opportunity for SIPA to consider the outsourcing scheme of the operation when the new international wharf would be developed. The SIG agreed to consider the study result with the involvement of SIPA in the course of the study.

(5) Wave calmness in front of the new international wharf

The Team explained that the operation rate of the new international wharf would be less than that of the existing international wharf because of less favorable sea condition.

(6) Master Plan Study

SIPA expressed the urgency of the Project and explained that the Master Plan Study is under way to prepare an action plan for the rest of facilities.

(7) Road issues

Ministry of Infrastructure Development and SIPA are mindful of road problem/traffic congestion that might be generated partially from the port.

Annex 1: The Proposed Project site

Annex 2: Organization chart of SIPA

Annex 3: Japan's Grant Aid Scheme

Annex 4: Flow chart of Japan's Grant Aid Procedures

Annex 5: Major Undertakings to be taken by Each Government



Annex 6: List of Attendants

Handwritten mark

Handwritten signatures


Annex 1

Honiara Port in Point Cruz



Handwritten signatures and initials:
MHA
#6
[Signature]

Annex 2



Handwritten initials

Handwritten signatures

Annex 3

JAPAN'S GRANT AID

The Government of Japan (hereinafter referred to as "the GOJ") is implementing the organizational reforms to improve the quality of ODA operations, and as a part of this realignment, a new JICA law was entered into effect on October 1, 2008. Based on this law and the decision of the GOJ, JICA has become the executing agency of the Grant Aid for General Projects, for Fisheries and for Cultural Cooperation, etc.

The Grant Aid is non-reimbursable fund provided to a recipient country to procure the facilities, equipment and services (engineering services and transportation of the products, etc.) for its economic and social development in accordance with the relevant laws and regulations of Japan. The Grant Aid is not supplied through the donation of materials as such.

1. Grant Aid Procedures

The Japanese Grant Aid is supplied through following procedures:

- Preparatory Survey
 - The Survey conducted by JICA
- Appraisal & Approval
 - Appraisal by the GOJ and JICA, and Approval by the Japanese Cabinet
- Authority for Determining Implementation
 - The Notes exchanged between the GOJ and a recipient country
- Grant Agreement (hereinafter referred to as "the G/A")
 - Agreement concluded between JICA and a recipient country
- Implementation
 - Implementation of the Project on the basis of the G/A

2. Preparatory Survey

(1) Contents of the Survey

The aim of the preparatory Survey is to provide a basic document necessary for the appraisal of the Project made by the GOJ and JICA. The contents of the Survey are as follows:

- Confirmation of the background, objectives, and benefits of the Project and also institutional capacity of relevant agencies of the recipient country necessary for the implementation of the Project.

MSK



- Evaluation of the appropriateness of the Project to be implemented under the Grant Aid Scheme from a technical, financial, social and economic point of view.
- Confirmation of items agreed between both parties concerning the basic concept of the Project.
- Preparation of a outline design of the Project.
- Estimation of costs of the Project.

The contents of the original request by the recipient country are not necessarily approved in their initial form as the contents of the Grant Aid project. The Outline Design of the Project is confirmed based on the guidelines of the Japan's Grant Aid scheme.

JICA requests the Government of the recipient country to take whatever measures necessary to achieve its self-reliance in the implementation of the Project. Such measures must be guaranteed even though they may fall outside of the jurisdiction of the organization of the recipient country which actually implements the Project. Therefore, the implementation of the Project is confirmed by all relevant organizations of the recipient country based on the Minutes of Discussions.

(2) Selection of Consultants

For smooth implementation of the Survey, JICA employs (a) registered consulting firm(s). JICA selects (a) firm(s) based on proposals submitted by interested firms.

(3) Result of the Survey

JICA reviews the Report on the results of the Survey and recommends the GOJ to appraise the implementation of the Project after confirming the appropriateness of the Project.

3. Japan's Grant Aid Scheme

(1) The E/N and the G/A

After the Project is approved by the Cabinet of Japan, the Exchange of Notes (hereinafter referred to as "the E/N") will be signed between the GOJ and the Government of the recipient country to make a pledge for assistance, which is followed by the conclusion of the G/A between JICA and the Government of the recipient country to define the necessary articles to implement the Project, such as payment conditions, responsibilities of the Government of the recipient country, and procurement conditions.

(2) Selection of Consultants

In order to maintain technical consistency, the consulting firm(s) which conducted the Survey will be recommended by JICA to the recipient country to continue to work on the Project's implementation after the E/N and G/A.

(3) Eligible source country

Under the Japanese Grant Aid, in principle, Japanese products and services including transport or those of the recipient country are to be purchased. When JICA and the Government of the recipient country or its designated authority deem it necessary, the Grant Aid may be used for the purchase of the products or services of a third country. However, the prime contractors, namely, constructing and procurement firms, and the prime consulting firm are limited to "Japanese nationals".

(4) Necessity of "Verification"

The Government of the recipient country or its designated authority will conclude contracts denominated in Japanese yen with Japanese nationals. Those contracts shall be verified by JICA. This "Verification" is deemed necessary to fulfill accountability to Japanese taxpayers.

(5) Major undertakings to be taken by the Government of the Recipient Country

In the implementation of the Grant Aid Project, the recipient country is required to undertake such necessary measures as Annex.

(6) "Proper Use"

The Government of the recipient country is required to maintain and use properly and effectively the facilities constructed and the equipment purchased under the Grant Aid, to assign staff necessary for this operation and maintenance and to bear all the expenses other than those covered by the Grant Aid.

(7) "Export and Re-export"

The products purchased under the Grant Aid should not be exported or re-exported from the recipient country.

(8) Banking Arrangements (B/A)

a) The Government of the recipient country or its designated authority should open an account under the name of the Government of the recipient country in a bank in Japan (hereinafter referred to as "the Bank"). JICA will execute



the Grant Aid by making payments in Japanese yen to cover the obligations incurred by the Government of the recipient country or its designated authority under the Verified Contracts.

b) The payments will be made when payment requests are presented by the Bank to JICA under an Authorization to Pay (A/P) issued by the Government of the recipient country or its designated authority.

(9) Authorization to Pay (A/P)

The Government of the recipient country should bear an advising commission of an Authorization to Pay and payment commissions paid to the Bank.

(10) Social and Environmental Considerations


A recipient country must carefully consider social and environmental impacts by the Project and must comply with the environmental regulations of the recipient country and JICA socio-environmental guidelines.

Handwritten mark

Handwritten signature

Annex 4

FLOW CHART OF JAPAN'S GRANT AID PROCEDURES



Handwritten signatures and initials, including the letters "H", "D", and "C".

Annex 5

Major Undertakings to be taken by Each Government

No.	Items	To be covered by Grant Aid	To be covered by Recipient Side
1	To secure a lot of land necessary for the implementation of the Project and to clear the site sites;		●
2	To ensure prompt unloading and customs clearance of the products at ports of disembarkation in the recipient country and to assist internal transportation of the products		
	1) Marine (Air) transportation of the Products from Japan to the recipient country	●	
	2) Tax exemption and customs clearance of the Products at the port of disembarkation		●
	3) Internal transportation from the port of disembarkation to the project site	(●)	(●)
3	To ensure that customs duties, internal taxes and other fiscal levies which may be imposed in the recipient country with respect to the purchase of the products and the services be exempted		●
4	To accord Japanese nationals and nationals of third countries whose services may be required in connection with the supply of the products and the services such facilities as may be necessary for their entry into the recipient country and stay there in for the performance of their work		●
5	To ensure that the Facilities and the products be maintained and used properly and effectively for the implementation of the Project		●
6	To bear all the expenses, other than those covered by the Grant, necessary for the implementation of the Project		●
7	To bear the following commissions paid to the Japanese bank for banking services based upon the B/A		
	1) Advising commission of A/P		●
	2) Payment commission		●
8	To give due environmental and social consideration in the implementation of the Project.		●

(B/A : Banking Arrangement, A/P : Authorization to pay)

MK

Annex 6

SIG Side:

Mr. Shadrach Fanega, Permanent Secretary, Ministry of Finance and Treasury
Mr. Moses Virivolomo, Permanent Secretary, Ministry of Infrastructure Development
Mr. Glyn Joshua, Acting General Manager, Solomon Island Ports Authority
Mr. Ronald Ivapitu, Director, Engineering, Solomon Island Ports Authority
Ms. Bridget WAFUNI, Management accountant, Solomon Island Ports Authority
Mr. Reginald Alatala, Workshop Manager, Solomon Island Ports Authority
Mr. Hugo John Bugoro, Acting Operations Manager, Solomon Island Ports Authority
Captain Judah KULABULE, Harbourmaster, Solomon Island Ports Authority
Captain Vitale TANGISI, Harbour Pilot, Solomon Island Ports Authority
Mr. Santus SIOTA, Project Engineer, Solomon Island Ports Authority

Japanese Side:

Mr. Hozumi Katsuta, Leader, Second Preparatory Study Team, JICA
Ms. Saori Fukuhara, Member, Second Preparatory Study Team, JICA
Mr. Yutaka Ochi, Consultant, Second Preparatory Study Team, JICA
Mr. Yuhei Yamamoto, Consultant, Second Preparatory Study Team, JICA
Mr. Toshio Yamada, Consultant, Second Preparatory Study Team, JICA
Mr. Yuji Hatakeyama, Consultant, Second Preparatory Study Team, JICA
Mr. Masao Ichinose, Consultant, Second Preparatory Study Team, JICA
Mr. Yoshinobu Takishita, Representative, Solomon Islands Office, JICA
Ms. Naoko Laka, Project Formulation Adviser, Solomon Islands Office, JICA

14/11



(2) 概要説明時 (2013年11月15日)


**Minutes of Discussions
on the Second Preparatory Survey for Outline Design
on
the Project for Improvement of Honiara Port Facilities
in the Solomon Islands**

In March 2013, the Japan International Cooperation Agency (hereinafter referred to as "JICA") dispatched a Second Preparatory Survey Team for "the Project for Improvement of Honiara Port Facilities in the Solomon Islands" (hereinafter referred to as "the Project") to Solomon Islands. The Second Preparatory Survey Team held a series of discussions with the concerned officials of the Solomon Islands Government (hereinafter referred to as "SIG") and conducted field surveys. After returning back to Japan, based on the discussions, field survey results and technical examination, JICA prepared a draft report of the survey.

In order to explain and discuss with the SIG on the contents of the draft report, JICA sent to the Solomon Islands, the Explanation Team for the Draft Outline Design Report of the Second Preparatory Survey (hereinafter referred to as "the Team"), which is headed by Mr. Hozumi KATSUTA, Advisor, JICA, from October 1st to 11th, 2013.

As a result of the discussion through the Explanation Team and the Resident Representative of JICA Solomon Islands Office with SIG side, both sides confirmed the main items described in the attached sheets.


Honiara, November 15, 2013



Seth Gukuma
Hon. Minister
Ministry of Infrastructure Development
Solomon Islands



Taiji Usui
Resident Representative
Solomon Islands office
Japan International Cooperation Agency



Rick Nelson Houenipwela
Hon. Minister
Ministry of Finance and Treasury
Solomon Islands

ATTACHMENT

1. Components of the Draft Outline Design Report

SIG agreed and accepted in principle the contents of the Draft Outline Design Report of the Preparatory Survey as a Technical Notes signed by both sides on October 9th, 2013.

2. Japan's Grant Aid Scheme

SIG reconfirmed the Japan's Grant Aid scheme. SIG reassured to take the necessary measurements as explained by the Second Preparatory Survey Team and described in the Annex-5 of the Minutes of Discussions signed by both sides on March 18th, 2013. SIG agreed to undertake all necessary works written in Annex-1 (2).

3. Schedule of the Study

JICA will complete the Final Outline Design Report of the Second Preparatory Survey in English, in accordance with the confirmed items and send the report to the SIG through JICA Solomon Office by the end of December, 2013.

4. Cost Estimation

Both sides agreed that in order to secure a fair and equitable procurement, the Project Cost Estimation attached in Annex-1 should never be duplicated or released to any third parties before the signing of all the Contract(s) for the Project.

5. Other Relevant Issues

JICA insists on immediate settling of uncertainties surrounding the management and governance of SIPA for smooth implementation of the Project.

Annex1 Cost Estimation

81

△ T.V.

CONFIDENTIAL

Project Cost to be Borne by Japan's Grant Aid

「施工・調達業者計約認証まで非公表」

SA

△ 200

資料—5 参考資料

資料 5.1 Technical Notes (T/N)

(1) 現地調査 (2013 年 4 月 12 日)


**Technical Notes
on the Second Preparatory Survey for Outline Design
on the Project for Improvement of Honiara Port Facilities
in Solomon Islands**

Referring to the result of Preparatory Survey in September 2011, the Government of Japan (hereinafter referred to as “the GOJ”) decided to conduct a Second Preparatory Survey for Outline Design on the Project for Improvement of Honiara Port Facilities in the Solomon Islands (hereinafter referred to as “the Project”) and entrusted the survey to the Japan International Cooperation Agency (hereinafter referred to as “JICA”)


JICA dispatched the Second Preparatory Survey Team for the Project (hereinafter referred to as “the Team”) to the Solomon Islands, headed by Mr. Hozumi Katsuta, Advisor, JICA, and conducted the survey from March 14 to March 21, 2013.

The Consultant members of the Team continued field survey in the study area and carried out a preliminary analysis of collected data and information. In the course of the discussions and field survey, both sides have confirmed the main items described in the attached sheets.

Honiara, April 12, 2013



Mr. Yutaka Ochi
Chief Consultant
Second Preparatory Survey Team
Japan International Cooperation Agency



Mr. Glyn Joshua
Acting General Manager
Solomon Island Ports Authority
Solomon Islands

ATTACHMENT

1. Beacons of Ancillary Facility of Berth

Beacons installed at both end of the new berth are necessary as a basic ancillary of the new international wharf for night time navigation safety.

2. Structural Type of Berthing Facility

Regarding the berthing facility, a steel pile wall type structure, which is a part of the existing international wharf, is preferable through discussion with the JICA study team.

3. Application of Construction Permit Issued by Honiara City Council

Applications of Development Permit necessary for the project implementation stage will be undertaken by Solomon Islands Ports Authority (hereinafter referred to as "SIPA") to Honiara City Council.

4. Design Standard of Port Structures

Japanese design standard for the port structures, which is internationally recognized, will be adopted.

5. Temporary Construction Yard

Temporary construction yards required for the construction works of the Project will be allocated in the area of Honiara Port.

6. Pavement of Existing Container Yard

Pavement works of unpaved area next to the existing container yard will be carried out by SIPA to cater for increase of container volume.

7 Drainage Relocation

Drainage system to discharge rain water to sea where outlets are located behind the Project site will be relocated by SIPA.

8. Extension of Electricity and Water Supply Line

Internal extension of electricity and water supply line within the existing port area will be carried out by SIPA to the point adjacent to the Project site.

Over

Handwritten signature and initials in black ink, appearing to be 'Chi' followed by a stylized 'D' or 'O'.

(2) 概要説明調査 (2013年10月9日)

Technical Notes
on the Second Preparatory Survey for Outline Design
on the Project for Improvement of Honiara Port Facilities
in Solomon Islands
(Explanation of the Draft Outline Design Report)

In March 2013, the Japan International Cooperation Agency (hereinafter referred to as "JICA") dispatched a Second Preparatory Survey Team for "Improvement of Honiara Port Facilities in Solomon Islands (hereinafter referred to as "the Project") to Solomon Islands. The Second Preparatory Survey Team held a series of discussions with the officials concerned in the Solomon Islands Government (hereinafter referred to as "SIG") and conducted field surveys. Based on the discussion, field survey results and technical examination, JICA prepared a draft report of the survey in Japan.


In order to explain to and discuss with SIG the contents of the draft report, JICA sent to Solomon Islands, the Explanation Team for the Draft Outline Design Report of the Second Preparatory Survey (hereinafter referred to as "the Team"), headed by Mr. Hozumi KATSUTA, Advisor, JICA from October 1st to 7th, 2013.

The Consultant members of the Team remained and continued the field survey and discussion with Solomon Islands Port Authority (hereinafter referred to as "SIPA") to finalise the technical matters in the Draft Report. As the results of the discussions and field survey, both sides have confirmed the main items described in the attached sheet.

Honiara
October 9, 2013



Mr. Yutaka Ochi
Chief Consultant
Second Preparatory Survey Team
Japan International Cooperation Agency



Mr. Ronald Ivupitu
Director Engineering
Solomon Island Ports Authority
Solomon Islands

ATTACHMENT

1. Components of the Draft Outline Report

SIPA, the implementing agency of the Project agreed and accepted in principle the Draft Outline Report of the Preparatory Survey.

2. EIA Procedure

EIA procedure of the Project is currently on finalization stage as scheduled. The final stakeholder meeting and publicity is scheduled to be held in November, 2013. The environmental license is expected to be issued around December, 2013.

3. Planning Approval and Building Permit

Planning approval is expected to be issued around January, 2014 by Honiara City Council. Similarly building permit from Honiara City Council is expected to be issued around August, 2014. Any fees associated with obtaining planning approval and building permit will be borne by SIPA.

4. The Master Plan Study of Honiara Port under SIPA

The Master Plan Study of Honiara Port carried out by SIPA is currently under way to prepare an action plan for port facility development. The port facility layout plan of the master plan will incorporate the layout plan of the Project.

5. Other Relevant Issues

- 5-1 Particulars of the project facilities described in the draft report are agreed in principle.
- 5-2 Extension point of electricity and water line to the Project Site is confirmed to be near the existing bank adjacent to the north access road of the new international wharf.
- 5-3 Site clearance and preparation of the temporary construction yard are confirmed to be carried out by SIPA.

Over

資料-6 その他の資料・情報


資料 6.1 ボーリング調査結果（各地点の粒径加積曲線）

ボーリング調査において得られた各地点の粒径加積曲線は、以下に示すとおりである。

（ボーリング調査地点は、2-2-3 章を参照。）

(1) BH-1 地点

DL-11.05~-11.60m




Solid Density: 2.40 t/m³, Unit Weight: 1.68 t/m³

Sieve (mm)	Total % Passing
75.0	---
63.0	---
53.0	---
37.5	---
26.5	100
19.0	96
13.20	90
9.50	87
6.70	82
4.75	79

Sieve (mm)	Total % Passing
3.35	76
2.00	70
1.180	61
0.600	47
0.425	39
0.300	29
0.212	20
0.150	14
0.090	9
0.063	8

DL-15.05~-15.60m




Solid Density: 2.45 t/m³, Unit Weight: 1.79 t/m³

Sieve (mm)	Total % Passing
75.0	100
63.0	83
53.0	83
37.5	83
26.5	77
19.0	72
13.20	63
9.50	50
6.70	37
4.75	29

Sieve (mm)	Total % Passing
3.35	23
2.00	17
1.180	13
0.600	8
0.425	7
0.300	5
0.212	3
0.150	2
0.090	2
0.063	1

DL-22.05~-22.60m




Solid Density: 2.42 t/m³, Unit Weight: 1.70 t/m³

Sieve (mm)	Total % Passing
75.0	---
63.0	---
53.0	---
37.5	100
26.5	96
19.0	95
13.20	92
9.50	88
6.70	83
4.75	80

Sieve (mm)	Total % Passing
3.35	77
2.00	71
1.180	64
0.600	51
0.425	43
0.300	35
0.212	28
0.150	21
0.090	15
0.063	13

(2) BH-2 地点

DL-10.25~10.80m




Solid Density: 2.43 t/m³, Unit Weight: 1.65 t/m³

Sieve (mm)	Total % Passing
63.0	---
53.0	---
37.5	100
26.5	94
19.0	89
13.2	82
9.50	76
6.70	69
4.75	64
3.35	59

Sieve (mm)	Total % Passing
2.00	53
1.18	46
0.600	38
0.425	34
0.300	31
0.212	28
0.150	25
0.090	20
0.063	16

DL-17.25~17.80m




Solid Density: 2.40 t/m³, Unit Weight: 1.62 t/m³

Sieve (mm)	Total % Passing
63.0	---
53.0	---
37.5	---
26.5	100
19.0	94
13.2	87
9.50	80
6.70	75
4.75	70
3.35	67

Sieve (mm)	Total % Passing
2.00	64
1.18	61
0.600	57
0.425	55
0.300	51
0.212	47
0.150	41
0.090	33
0.063	25

DL-24.25~-24.60m




Solid Density: 2.51 t/m³, Unit Weight: 1.79 t/m³

Sieve (mm)	Total % Passing
63.0	---
53.0	100
37.5	96
26.5	93
19.0	81
13.2	72
9.50	66
6.70	61
4.75	56
3.35	52

Sieve (mm)	Total % Passing
2.00	47
1.18	41
0.600	32
0.425	28
0.300	24
0.212	21
0.150	18
0.090	15
0.063	12

(3) BH-3 地点

DL-11.65~12.00m




Solid Density: 2.59 t/m³, Unit Weight: 1.63 t/m³

Sieve (mm)	Total % Passing
63.0	---
53.0	---
37.5	100
26.5	96
19.0	92
13.2	85
9.50	76
6.70	70
4.75	65
3.35	62

Sieve (mm)	Total % Passing
2.00	56
1.18	51
0.600	41
0.425	36
0.300	30
0.212	24
0.150	19
0.090	14
0.063	11

DL-15.80~-16.20m




Solid Density: 2.55 t/m³, Unit Weight: 1.63 t/m³

Sieve (mm)	Total % Passing
63.0	---
53.0	---
37.5	100
26.5	95
19.0	91
13.2	86
9.50	78
6.70	73
4.75	68
3.35	64

Sieve (mm)	Total % Passing
2.00	60
1.18	56
0.600	49
0.425	46
0.300	42
0.212	37
0.150	31
0.090	24
0.063	19

DL-22.65~-23.00m




Solid Density: 2.52 t/m³, Unit Weight: 1.73 t/m³

Sieve (mm)	Total % Passing
63.0	---
53.0	---
37.5	---
26.5	100
19.0	97
13.2	92
9.50	86
6.70	80
4.75	74
3.35	70

Sieve (mm)	Total % Passing
2.00	64
1.18	58
0.600	49
0.425	45
0.300	40
0.212	35
0.150	31
0.090	25
0.063	21

(4) BH-4 地点

DL-10.55~-11.10m




Solid Density: 2.40 t/m³, Unit Weight: 1.81 t/m³

Sieve (mm)	Total % Passing
75.0	---
63.0	100
53.0	82
37.5	82
26.5	77
19.0	71
13.20	66
9.50	61
6.70	56
4.75	52

Sieve (mm)	Total % Passing
3.35	48
2.00	41
1.180	35
0.600	28
0.425	25
0.300	23
0.212	20
0.150	18
0.090	16
0.063	14

DL-21.55~-22.10m




Solid Density: 2.45 t/m³, Unit Weight: 1.63 t/m³

Sieve (mm)	Total % Passing
75.0	---
63.0	---
53.0	---
37.5	100
26.5	99
19.0	94
13.20	88
9.50	84
6.70	78
4.75	72

Sieve (mm)	Total % Passing
3.35	68
2.00	62
1.180	57
0.600	49
0.425	45
0.300	40
0.212	36
0.150	31
0.090	25
0.063	20

DL-27.55~-28.10m




Solid Density: 2.42 t/m³, Unit Weight: 1.87 t/m³

Sieve (mm)	Total % Passing
63.0	---
53.0	100
37.5	94
26.5	94
19.0	91
13.2	86
9.50	80
6.70	74
4.75	71
3.35	66

Sieve (mm)	Total % Passing
2.00	60
1.18	53
0.600	43
0.425	38
0.300	32
0.212	25
0.150	20
0.090	15
0.063	11

(5) BH-5 地点

DL-7.45~-8.00m




Solid Density: 2.52 t/m³, Unit Weight: 1.63 t/m³

Sieve (mm)	Total % Passing
63.0	---
53.0	---
37.5	100
26.5	96
19.0	95
13.2	91
9.50	87
6.70	81
4.75	76
3.35	73

Sieve (mm)	Total % Passing
2.00	67
1.18	60
0.600	46
0.425	37
0.300	27
0.212	19
0.150	13
0.090	8
0.063	6

DL-12.45~-13.00m




Solid Density: 2.55 t/m³, Unit Weight: 1.79 t/m³

Sieve (mm)	Total % Passing
63.0	---
53.0	---
37.5	100
26.5	99
19.0	95
13.2	90
9.50	83
6.70	77
4.75	73
3.35	70

Sieve (mm)	Total % Passing
2.00	66
1.18	60
0.600	49
0.425	41
0.300	32
0.212	23
0.150	17
0.090	12
0.063	9

DL-16.45~-17.00m




Solid Density: 2.54 t/m³, Unit Weight: 1.75 t/m³

Sieve (mm)	Total % Passing
63.0	---
53.0	---
37.5	100
26.5	96
19.0	89
13.2	81
9.50	74
6.70	69
4.75	64
3.35	60

Sieve (mm)	Total % Passing
2.00	54
1.18	48
0.600	39
0.425	34
0.300	27
0.212	20
0.150	15
0.090	11
0.063	8

(6) BH-6 地点

DL-5.65~-6.20m




Solid Density: 2.50 t/m³, Unit Weight: 1.76 t/m³

Sieve (mm)	Total % Passing
63.0	---
53.0	---
37.5	100
26.5	96
19.0	91
13.2	84
9.50	76
6.70	71
4.75	67
3.35	64

Sieve (mm)	Total % Passing
2.00	59
1.18	54
0.600	44
0.425	38
0.300	32
0.212	25
0.150	20
0.090	14
0.063	11

DL-9.65~-10.20m




Solid Density: 2.52 t/m³, Unit Weight: 1.67 t/m³

Sieve (mm)	Total % Passing
63.0	---
53.0	---
37.5	100
26.5	96
19.0	91
13.2	88
9.50	83
6.70	78
4.75	74
3.35	71

Sieve (mm)	Total % Passing
2.00	66
1.18	59
0.600	49
0.425	42
0.300	34
0.212	26
0.150	20
0.090	15
0.063	11

DL-19.20~-20.20m



Solid Density: 2.63 t/m³, Unit Weight: 2.00 t/m³


Sieve (mm)	Total % Passing
63.0	---
53.0	---
37.5	100
26.5	93
19.0	85
13.2	79
9.50	73
6.70	67
4.75	61
3.35	57

Sieve (mm)	Total % Passing
2.00	52
1.18	46
0.600	37
0.425	32
0.300	28
0.212	24
0.150	20
0.090	16
0.063	12

(7) BH-7 地点

DL-8.55~9.10m

Solid Density: 2.51 t/m³, Unit Weight: 1.81 t/m³




Sieve (mm)	Total % Passing
63.0	---
53.0	---
37.5	---
26.5	100
19.0	98
13.2	95
9.50	93
6.70	90
4.75	88
3.35	84

Sieve (mm)	Total % Passing
2.00	77
1.18	68
0.600	49
0.425	39
0.300	29
0.212	21
0.150	16
0.090	12
0.063	10

DL-12.55~13.10m

Solid Density: 2.55 t/m³, Unit Weight: 1.84 t/m³




Sieve (mm)	Total % Passing
63.0	---
53.0	100
37.5	96
26.5	88
19.0	80
13.2	71
9.50	67
6.70	62
4.75	58
3.35	55

Sieve (mm)	Total % Passing
2.00	51
1.18	47
0.600	42
0.425	40
0.300	37
0.212	34
0.150	31
0.090	26
0.063	21

DL-19.55~-20.10m

Solid Density: 2.62 t/m³, Unit Weight: 1.86 t/m³




Sieve (mm)	Total % Passing
63.0	---
53.0	---
37.5	100
26.5	99
19.0	97
13.2	95
9.50	91
6.70	85
4.75	79
3.35	75

Sieve (mm)	Total % Passing
2.00	69
1.18	62
0.600	51
0.425	44
0.300	37
0.212	31
0.150	25
0.090	19
0.063	13

(8) BH-8 地点

DL-7.45~-8.00m


Solid Density: 2.48 t/m³, Unit Weight: 1.71 t/m³



Sieve (mm)	Total % Passing
63.0	---
53.0	---
37.5	---
26.5	100
19.0	98
13.2	95
9.50	93
6.70	90
4.75	87
3.35	83

Sieve (mm)	Total % Passing
2.00	78
1.18	66
0.600	49
0.425	39
0.300	31
0.212	23
0.150	17
0.090	11
0.063	9

DL-11.45~-11.90m




Solid Density: 2.37 t/m³, Unit Weight: 1.65 t/m³

Sieve (mm)	Total % Passing
63.0	---
53.0	---
37.5	100
26.5	96
19.0	88
13.2	77
9.50	72
6.70	69
4.75	66
3.35	64

Sieve (mm)	Total % Passing
2.00	61
1.18	58
0.600	55
0.425	53
0.300	50
0.212	46
0.150	41
0.090	34
0.063	27

DL-21.45~-22.00m




Solid Density: 2.46 t/m³, Unit Weight: 1.75 t/m³

Sieve (mm)	Total % Passing
63.0	---
53.0	---
37.5	100
26.5	96
19.0	92
13.2	90
9.50	85
6.70	79
4.75	75
3.35	70

Sieve (mm)	Total % Passing
2.00	63
1.18	57
0.600	49
0.425	45
0.300	40
0.212	36
0.150	31
0.090	27
0.063	23

(9) BH-9 地点

DL-2.15~-2.70m




Solid Density: 2.53 t/m³, Unit Weight: 1.73 t/m³

Sieve (mm)	Total % Passing
63.0	100
53.0	92
37.5	89
26.5	84
19.0	76
13.2	70
9.50	64
6.70	59
4.75	55
3.35	52

Sieve (mm)	Total % Passing
2.00	47
1.18	42
0.600	31
0.425	25
0.300	19
0.212	16
0.150	13
0.090	10
0.063	9

DL-9.15~-9.70m




Solid Density: 2.50 t/m³, Unit Weight: 1.68 t/m³

Sieve (mm)	Total % Passing
63.0	---
53.0	100
37.5	96
26.5	89
19.0	83
13.2	75
9.50	69
6.70	62
4.75	57
3.35	52

Sieve (mm)	Total % Passing
2.00	47
1.18	42
0.600	35
0.425	32
0.300	28
0.212	25
0.150	21
0.090	16
0.063	13

DL-14.15~14.70m




Solid Density: 2.60 t/m³, Unit Weight: 1.75 t/m³

Sieve (mm)	Total % Passing
63.0	---
53.0	100
37.5	95
26.5	93
19.0	88
13.2	78
9.50	68
6.70	60
4.75	53
3.35	48

Sieve (mm)	Total % Passing
2.00	43
1.18	38
0.600	34
0.425	32
0.300	30
0.212	27
0.150	23
0.090	18
0.063	14

(10) BH-10 地点

DL-2.15~3.30m




Solid Density: 2.46 t/m³, Unit Weight: 1.86 t/m³

Sieve (mm)	Total % Passing
63.0	---
53.0	100
37.5	84
26.5	76
19.0	72
13.2	62
9.50	57
6.70	51
4.75	46
3.35	43

Sieve (mm)	Total % Passing
2.00	38
1.18	33
0.600	26
0.425	22
0.300	19
0.212	16
0.150	13
0.090	10
0.063	7

DL-6.15~6.70m




Solid Density: 2.36 t/m³, Unit Weight: 1.70 t/m³

Sieve (mm)	Total % Passing
63.0	---
53.0	100
37.5	93
26.5	85
19.0	77
13.2	71
9.50	69
6.70	67
4.75	65
3.35	62

Sieve (mm)	Total % Passing
2.00	55
1.18	49
0.600	41
0.425	36
0.300	30
0.212	25
0.150	20
0.090	14
0.063	10

DL-13.30~13.70m



Solid Density: 2.34 t/m³, Unit Weight: 1.67 t/m³

Sieve (mm)	Total % Passing
63.0	---
53.0	100
37.5	97
26.5	96
19.0	90
13.2	83
9.50	78
6.70	73
4.75	68
3.35	65

Sieve (mm)	Total % Passing
2.00	59
1.18	55
0.600	49
0.425	46
0.300	43
0.212	39
0.150	35
0.090	29
0.063	23

資料 6.2 波浪解析

(1) 波浪解析手法

対象地点に来襲する波浪は、図 A6.2-1 に示すように、1) 南太平洋で発生する波浪と、2) New Georgia Sound 内で発生する波浪に分類できる。南太平洋で発生する波浪は、Santa Isabel 島と Malaita 島との Indispensable Strait から侵入し、Florida 諸島による遮蔽の影響を受けつつ、対象地点（ホニアラ港沖合）に到達する。一方、New Georgia Sound で発生する波浪は、対象地点に直接到達する。これら 2 種類の波浪を合成し、ホニアラ港沖合に到達する波浪を求めた。本件では、この手法により、通常時と異常時（設計波）について、それぞれ解析を行った。図 A6.2-2 に解析フローを示す。




図 A6.2-1 対象地点の波浪発生海域




図 A6.2-2 対象地点での波浪解析フロー

南太平洋で発生する波浪は、「1点スペクトル法」を用いて推算した。この方法は、風波及びうねりの発生・発達・伝搬において波浪の不規則性を取り入れながら、推算対象地点から放射状に伸びる計算格子点上で、波浪を推算する手法である。図 A6.2-3 は、「1点スペクトル法」に用いる推算対象点と波浪推算格子点の位置を示したものである。




図 A6.2-3 推算対象点及び推算格子点位置図

一方、New Georgia Sound 内で発生する波浪については、「SMB 法」を用いて波浪推算を行った。この方法は、風向、風速データと対象風向毎の吹送距離のデータから波浪諸元を求める手法である。吹送距離については、風向の変化や風域の幅を考慮し、有効吹送距離を算定して用いた。図 A6.2-4 は、New Georgia Sound 内発生波の推算に用いた有効吹送距離の計算例(図の場合は、波向 NW)、表 A6.2-1 は有効吹送距離の一覧を示したものである。New Georgia Sound 内発生波の有効吹送距離の最大値は、NNW 方向の 103km である。




図 A6.2-4 有効吹送距離の計算例 (風向 NW)

表 A6.2-1 有効吹送距離 (New Georgia Sound 内発生波)

風 向	WNW	NW	NNW	N	NNE	NE	ENE	E
有効吹送距離 (km)	73.9	97.7	103.3	70.7	50.1	52.5	59.5	53.6

(2) 通常時波浪の推算結果（ホニアラ港沖）

1) 南太平洋で発生する波浪

南太平洋の風の平面データ（気象庁資料）から、「1点スペクトル法」を用いて、南太平洋内で発生する波浪の推算を行った。推算期間は2002～2006年の5年間である。計算結果より、Indispensable Strait 沖の波浪頻度表を表 A6.2-3, 4 に示す。

風向の出現率が高い ESE の波浪が卓越し、全体の 56%程度を占め、続いて NNE、NE の順になっている。波高は最大で 3.5m 程度である。また周期は 4～10 秒程度に分布しているが、最も出現率が高いのは 6～9 秒である。通年において、波高 1m、2m、3m 以上となる出現率はそれぞれ 38.6%、4.3%、0.2% である。

この波浪について、Indispensable Strait 内に侵入する波浪の変形計算を、エネルギー平衡方程式を解く方法を用いて行った。変形計算結果例を図 A6.2-5 に示す。波浪変形計算における波浪の周期は、推算された波浪の頻度表から、8 秒に設定した。計算結果より、ホニアラ港沖での波高比及び入射波向を表 A6.2-2 に示す。

表 A6.2-2 波浪変形計算結果（Indispensable Strait 内侵入波）

沖波波向	NW	NNW	N	NNE	NE	ENE	E	ESE
波高比	0.35	0.33	0.37	0.36	0.28	0.13	0.13	0.07
入射波向	NW	NNE	NNE	NNE	NNE	ENE	ENE	ENE

2) New Georgia Sound 内で発生する波浪

対象地点における、風の時系列データ（気象庁資料）から、「SMB 法」を用いて、New Georgia Sound 内で発生しホニアラ港沖合に到達する波浪を推算した。推算結果は表 A6.2-5, 6 に示すとおりである。波向は WNW～N～E に広く分布している。ESE～S～W については、風の出現率が高いものの、対岸距離が短いため、高波浪の出減率は小さくなっている。周期は 0～5 秒程度まで分布しており、南太平洋発生波と較べると短周期である。通年において、波高 1m、1.5m、2m 以上となる出現率はそれぞれ 3.3%、0.9%、0.3% である。

3) 南太平洋で発生する波浪と New Georgia Sound 内で発生する波浪の合成

波高はエネルギー合成法、周期は谷本・木村の方法（港研報告 Vol.25, No.2）を用いて、波浪の合成を行った。合成波の波向は、合成する 2 つの波浪のうち、波高の大きいものの波向を採用した。計算結果より、波浪の頻度表を表 A6.2-7, 8 に、波向分布図を図 A6.2-6 に示す。

波向は WNW～N～E に広く分布しているが、出現率が高いのは、ENE 及び NNE である。これは、南太平洋で発生し海峡内へ侵入した波浪の影響と考えられ、波高は比較的小さい。一方、波向 WNW から NNW の波浪は、New Georgia Sound 内で発生した波浪と考えられ、出現率は合計で 11.6%程度であるが、比較的高波の出現率が高く、最大 3.2m 程度に達している。周期は、幅広く分布しているが、波高 0.5m を超える波浪の周期は、3～10 秒程度、波高 1.0m を超える波浪の周期は、3～7 秒程度である。通年において、波高 0.5m、1m、1.5m、2m 以上となる出現率はそれぞれ、14.2%、4.0%、1.1%、0.5% である。また、季節的にみると、12～5 月に高波浪の出現する割合が多くなっている。

表 A6.2-3 波向別波高階級別頻度表 (Indispensable Strait 沖、通年、2002~2006 年)

WAVE DIRECTION	U. K.	N	NNE	NE	ENE	E	ESE	SE	SSE	S	SSW	SW	WSW	W	WNW	NW	NNW	TOTAL
WAVE HEIGHT (M)																		
CALM	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0
0.00 - 0.50	0 .0	1038 2.4	2564 5.9	1507 3.4	77 .2	138 .3	3294 7.5	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	250 .6	486 1.1	9354 21.3
0.50 - 1.00	0 .0	1200 2.7	3256 7.4	1899 4.3	178 .4	526 1.2	9344 21.3	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	736 1.7	487 1.1	17626 40.2
1.00 - 1.50	0 .0	637 1.5	1260 2.9	497 1.1	232 .5	204 .5	7083 16.2	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	598 1.4	379 .9	10890 24.9
1.50 - 2.00	0 .0	171 .4	111 .3	16 .0	7 .0	69 .2	3399 7.8	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	302 .7	22 .1	4097 9.4
2.00 - 2.50	0 .0	31 .1	4 .0	0 .0	0 .0	39 .1	1213 2.8	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	134 .3	8 .0	1429 3.3
2.50 - 3.00	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	257 .6	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	76 .2	13 .0	346 .8
3.00 - 3.50	0 .0	2 .0	0 .0	0 .0	0 .0	0 .0	59 .1	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	7 .0	1 .0	69 .2
3.50 - 4.00	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	6 .0	0 .0	6 .0
4.00 - 5.00	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0
5.00 - 6.00	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0
6.00 - 7.00	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0
7.00 -	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0
TOTAL	0 .0	3079 7.0	7195 16.4	3919 8.9	494 1.1	976 2.2	24649 56.3	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	2109 4.8	1396 3.2	43817 100.0

表 A6.2-4 波高・周期階級別頻度表 (Indispensable Strait 沖、通年、2002~2006 年)

WAVE PERIOD (S)	CALM	0-1	1-2	2-3	3-4	4-5	5-6	6-7	7-8	8-9	9-10	10-11	11-12	12-13	13-14	14-	TOTAL
WAVE HEIGHT (M)																	
CALM	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0
0.00 - 0.50	0 .0	0 .0	0 .0	0 .0	0 .0	27 .1	260 .6	1004 2.3	4293 9.8	3529 8.1	216 .5	25 .1	0 .0	0 .0	0 .0	0 .0	9354 21.3
0.50 - 1.00	0 .0	0 .0	0 .0	0 .0	0 .0	357 .1	2258 5.2	3400 7.8	4617 10.5	5231 11.9	1690 3.9	72 .2	1 .0	0 .0	0 .0	0 .0	17626 40.2
1.00 - 1.50	0 .0	0 .0	0 .0	0 .0	0 .0	58 .1	2320 5.3	3473 7.9	1951 4.5	1462 3.3	1360 3.1	243 .6	16 .0	7 .0	0 .0	0 .0	10890 24.9
1.50 - 2.00	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	460 1.0	2017 4.6	1024 2.3	377 .9	132 .3	46 .1	28 .1	13 .0	0 .0	0 .0	4097 9.4
2.00 - 2.50	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	11 .0	708 1.6	558 1.3	107 .2	35 .1	10 .0	0 .0	0 .0	0 .0	0 .0	1429 3.3
2.50 - 3.00	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	125 .3	186 .4	35 .1	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	346 .8
3.00 - 3.50	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	1 .0	67 .2	1 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	69 .2
3.50 - 4.00	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	6 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	6 .0
4.00 - 5.00	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0
5.00 - 6.00	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0
6.00 - 7.00	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0
7.00 -	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0
TOTAL	0 .0	0 .0	0 .0	0 .0	0 .0	442 1.0	5309 12.1	10728 24.5	12702 29.0	10742 24.5	3433 7.8	396 .9	45 .1	20 .0	0 .0	0 .0	43817 100.0

表 A6.2-5 波向別波高階級別頻度表 (New Georgia Sound 発生波ホニアラ港沖、通年、2002~2006 年)

WAVE DIRECTION	U. K.	N	NNE	NE	ENE	E	ESE	SE	SSE	S	SSW	SW	WSW	W	WNW	NW	NNW	TOTAL
WAVE HEIGHT (M)																		
CALM	7 .0	33 .1	8 .0	14 .0	12 .0	6 .0	862 2.0	34 .1	45 .1	59 .1	19 .0	30 .1	31 .1	27 .1	8 .0	12 .0	4 .0	1211 2.8
0.00 - 0.24	0 .0	645 1.5	579 1.3	659 1.5	968 2.2	587 1.3	12361 28.2	7084 16.2	2728 6.2	1123 2.6	759 1.7	832 1.9	1417 3.2	2364 5.4	686 1.6	540 1.2	504 1.2	33836 77.2
0.25 - 0.49	0 .0	279 .6	238 .5	430 1.0	847 1.9	678 1.5	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	489 1.1	305 .7	315 .7	3581 8.2
0.50 - 0.74	0 .0	173 .4	121 .3	221 .5	498 1.1	518 1.2	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	325 .7	256 .6	148 .3	2260 5.2
0.75 - 0.99	0 .0	124 .3	91 .2	72 .2	278 .6	360 .8	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	269 .6	177 .4	99 .2	1470 3.4
1.00 - 1.24	0 .0	33 .1	27 .1	16 .0	98 .2	88 .2	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	281 .6	150 .3	64 .1	757 1.7
1.25 - 1.49	0 .0	12 .0	7 .0	0 .0	4 .0	19 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	194 .4	47 .1	9 .0	292 .7
1.50 - 1.74	0 .0	4 .0	0 .0	0 .0	0 .0	8 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	88 .2	69 .2	4 .0	173 .4
1.75 - 1.99	0 .0	0 .0	0 .0	0 .0	0 .0	2 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	61 .1	31 .1	4 .0	98 .2
2.00 - 2.24	0 .0	0 .0	0 .0	0 .0	0 .0	1 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	41 .1	47 .1	4 .0	93 .2
2.25 - 2.49	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	4 .0	30 .1	10 .0	44 .1
2.50 - 2.74	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	3 .0	4 .0	0 .0	7 .0
2.75 - 3.00	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	2 .0	0 .0	2 .0
3.00 -	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0
TOTAL	7 .0	1303 3.0	1071 2.4	1412 3.2	2705 6.2	2267 5.2	13223 30.2	7118 16.2	2773 6.3	1182 2.7	778 1.8	862 2.0	1448 3.3	2391 5.5	2449 5.6	1670 3.8	1165 2.7	43824 100.0

表 A6.2-6 波高・周期階級別頻度表 (New Georgia Sound 発生波ホニアラ港沖、通年、2002~2006 年)

WAVE PERIOD (S)	CALM	0- 1	1- 2	2- 3	3- 4	4- 5	5- 6	6- 7	7- 8	8- 9	9-10	10-11	11-12	12-13	13-14	14-	TOTAL
WAVE HEIGHT (M)																	
CALM	7 .0	995 2.3	209 .5	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	1211 2.8
0.00 - 0.24	0 .0	18781 42.9	3575 8.2	4554 10.4	5876 13.4	1045 2.4	5 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	33836 77.2
0.25 - 0.49	0 .0	0 .0	153 .3	3428 7.8	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	3581 8.2
0.50 - 0.74	0 .0	0 .0	0 .0	689 1.6	1571 3.6	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	2260 5.2
0.75 - 0.99	0 .0	0 .0	0 .0	0 .0	1457 3.3	13 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	1470 3.4
1.00 - 1.24	0 .0	0 .0	0 .0	0 .0	234 .5	523 1.2	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	757 1.7
1.25 - 1.49	0 .0	0 .0	0 .0	0 .0	0 .0	292 .7	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	292 .7
1.50 - 1.74	0 .0	0 .0	0 .0	0 .0	0 .0	162 .4	11 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	173 .4
1.75 - 1.99	0 .0	0 .0	0 .0	0 .0	0 .0	5 .0	93 .2	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	98 .2
2.00 - 2.24	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	93 .2	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	93 .2
2.25 - 2.49	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	44 .1	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	44 .1
2.50 - 2.74	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	2 .0	5 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	7 .0
2.75 - 3.00	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	2 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	2 .0
3.00 -	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0
TOTAL	7 .0	19776 45.1	3937 9.0	8671 19.8	9138 20.9	2040 4.7	248 .6	7 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	0 .0	43824 100.0

表 A6.2-7 波向別波高階級別頻度表 (ホニアラ港沖、通年、2002~2006 年)

WAVE DIRECTION	U.K.	N	NNE	NE	ENE	E	ESE	SE	SSE	S	SSW	SW	WSW	W	WNW	NW	NNW	TOTAL
WAVE HEIGHT (M)																		
CALM	0	0	0	0	8	0	0	0	0	0	0	0	0	0	0	0	0	8
0.00 - 0.24	0	223	6522	302	20515	289	22	689	420	219	61	28	37	58	201	511	134	30231
0.25 - 0.49	0	249	3721	386	876	634	0	0	0	0	0	0	0	392	825	274	7357	
0.50 - 0.74	0	180	510	263	519	551	0	0	0	0	0	0	0	326	425	173	2947	
0.75 - 0.99	0	127	129	79	301	362	0	0	0	0	0	0	0	239	175	101	1513	
1.00 - 1.24	0	47	49	33	116	103	0	0	0	0	0	0	0	306	179	75	908	
1.25 - 1.49	0	22	11	0	7	19	0	0	0	0	0	0	0	234	52	23	368	
1.50 - 1.74	0	7	4	0	0	7	0	0	0	0	0	0	0	86	69	4	177	
1.75 - 1.99	0	0	0	0	0	3	0	0	0	0	0	0	0	58	29	2	92	
2.00 - 2.24	0	0	0	0	0	1	0	0	0	0	0	0	0	55	39	5	100	
2.25 - 2.49	0	0	0	0	0	0	0	0	0	0	0	0	0	29	39	4	72	
2.50 - 2.74	0	0	0	0	0	0	0	0	0	0	0	0	0	4	21	9	34	
2.75 - 3.00	0	0	0	0	0	0	0	0	0	0	0	0	0	2	6	0	8	
3.00 -	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2	
TOTAL	0	855	10946	1063	22342	1969	22	689	420	219	61	28	37	58	1932	2372	804	43817

表 A6.2-8 波高・周期階級別頻度表 (ホニアラ港沖、通年、2002~2006 年)

WAVE PERIOD (S)	CALM	0-1	1-2	2-3	3-4	4-5	5-6	6-7	7-8	8-9	9-10	10-11	11-12	12-13	13-14	14-	TOTAL
WAVE HEIGHT (M)																	
CALM	0	0	0	0	0	0	0	8	0	0	0	0	0	0	0	0	8
0.00 - 0.24	0	559	8068	3925	1388	2394	4742	4175	2882	1464	350	156	60	44	11	13	30231
0.25 - 0.49	0	0	31	2899	599	423	646	730	611	558	454	149	79	41	26	111	7357
0.50 - 0.74	0	0	0	348	2004	152	60	121	100	70	32	10	20	10	6	14	2947
0.75 - 0.99	0	0	0	0	1368	114	0	0	13	18	0	0	0	0	0	0	1513
1.00 - 1.24	0	0	0	0	179	729	0	0	0	0	0	0	0	0	0	0	908
1.25 - 1.49	0	0	0	0	0	368	0	0	0	0	0	0	0	0	0	0	368
1.50 - 1.74	0	0	0	0	0	138	39	0	0	0	0	0	0	0	0	0	177
1.75 - 1.99	0	0	0	0	0	0	5	87	0	0	0	0	0	0	0	0	92
2.00 - 2.24	0	0	0	0	0	0	100	0	0	0	0	0	0	0	0	0	100
2.25 - 2.49	0	0	0	0	0	0	72	0	0	0	0	0	0	0	0	0	72
2.50 - 2.74	0	0	0	0	0	0	31	3	0	0	0	0	0	0	0	0	34
2.75 - 3.00	0	0	0	0	0	0	0	8	0	0	0	0	0	0	0	0	8
3.00 -	0	0	0	0	0	0	0	2	0	0	0	0	0	0	0	0	2
TOTAL	0	559	8099	7172	5538	4323	5777	5047	3606	2110	836	315	159	95	43	138	43817




図 A6.2-5 波浪変形計算結果例 (New Georgia Sound 内侵入波、波向 : N、周期 : 8 秒)




図 A6.2-6 波向分布図（ホニアラ港沖、通年、2002～2006 年）

(3) 異常時波浪（設計波）の推算

対象地点は、南太平洋で発生するサイクロンによる波浪の影響を受ける。ここでは、通常時の波浪解析で用いたのと同じ手法を用いて、サイクロン来襲時の波浪を検討した。

図 A6.2-7 は、1945 年～2011 年の間に「ソ」国周辺を通過したサイクロンのなかで、対象地点への影響が大きいと考えられるサイクロンを抽出して、その経路を示したものである。サイクロンは南緯 5° 以南の海域で発生・発達し、主として南側に向かって進行する。「ソ」国は南緯 8～10° 付近に位置しているが、この付近の海域では、サイクロンは発達途上であり、波浪が十分に発達する前の段階にあるものと考えられる。また、サイクロンのあるものは SW 方向に、あるものは SE～E 方向に進行するというように、その進行経路にはバラツキが多い。

1) 南太平洋で発生する波浪

「1 点スペクトル法」を用いて、Indispensable Strait に来襲する波浪を推算した。図 A6.2-7 に示したサイクロンのうち、対象に地点に対する影響が大きいと考えられる、1972 年 5～6 月のサイクロン（サイクロン番号 7231）、及び 1996 年 11 月のサイクロン（サイクロン番号 9606）、を選定し波浪推算を行った。図 A6.2-8, 9 に推算結果を示す。最大波高は 5.53m、周期は 9.68 秒、波向は NNW であった。また、この間の対象地点周辺の風況は、風向 N～NNW、風速 25m/s 程度であり、吹送時間は 3 時間程度と推算された。

2) New Georgia Sound 内で発生する波浪

これらのサイクロンから、New Georgia Sound 内での波浪を推算した。上記サイクロン時の最大風速の風向は N~NW であり、対象地点であるホニアラ港沖から New Georgia Sound の方向は WNW~NW である。ここでは、危険側を考慮して、New Georgia Sound 方向と上記サイクロン時の風向が一致するものとした。New Georgia Sound の最大吹送距離は約 400km である。サイクロン時の最大風速は 25m/s、その最大継続時間は 3 時間である。これらの結果から、サイクロン時の最大波浪を SMB 法により求めると、波高 3.18m、周期 6.02s となる。

3) 南太平洋で発生する波浪と New Georgia Sound 内で発生する波浪の合成

通常時波浪の場合と同様に、南太平洋内発生波の Indispensable Strait 内侵入波と、New Georgia Sound 内発生波を合成すると、表 A6.2-9 のとおりとなる。これらを整理し、ホニアラ港沖の設計波浪を示したものが表 A6.2-10 である。波向については、サイクロンの経路や、New Georgia Sound 内の対岸距離、フロリダ島と対象地点との位置関係などを考慮し、NW~N と設定した。




図 A6.2-7 サイクロン経路 (1945~2011 年)




図 A6.2-8 波浪推算結果 (サイクロン 7231、1972 年 5~6 月)




図 A6.2-9 波浪推算結果 (サイクロン 9606、1996 年 11 月)

表 A6.2-9 ホニアラ港沖の波浪（サイクロン来襲時）

諸元	南太平洋発生波	波高比 (海峡内侵入波)	南太平洋発生波の侵入波	New Georgia Sound 内発生波	合成波 (ホニアラ港沖)
波高 (H)	5.53m	0.33	1.82m	3.18m	3.66m
周期 (T)	9.68		10s	6.02s	6.7s
波向	NNW		NNE	NW	NW

表 A6.2-10 ホニアラ港の設計波浪（沖波諸元）

波高 (H)	3.66m
周期 (T)	6.7s
波向	NW~N

4) 岸壁前面における設計波の算定

表 A6.2-10 の波浪に対し、浅海域における波浪変形計算を実施し、ホニアラ港コンテナヤード岸壁前面の設計波浪を求めた。波浪変形計算は、エネルギー平衡方程式を解く方法を用いた。この計算方法は、防波堤や島などを陸地としてエネルギーを吸収させることにより、不規則波の回折現象も擬似的に取り入れた計算方法である。計算結果から計算対象領域の各格子点における、波高比、入射浪向などの緒元が求められる。

図 A6.2-10 は、変形計算の計算対象領域を示したものである。このように、計算領域は、東西、南北ともに約 2.5km で格子間隔は何れも 50m である。例として、波向 N による計算結果を図 A6.2-11 に示す。また、岸壁前面での波浪緒元（換算沖波波高、入射浪向）を整理した結果を表 A6.2-11 に示す。換算沖波波高は、沖波浪向 N の場合が最も大きく、2.78m、入射浪向は N25.4° E（岸壁への入射角は約 65°）となる。

表 A6.2-11 換算沖波波浪緒元

沖波波浪			岸壁前面での波浪緒元		
波向	波高	周期	屈折係数	換算沖波波高(m)	入射波向
NW	3.66m	6.7s	0.53	1.94	N3.3°E
NNW	〃	〃	0.67	2.45	N13.3°E
N	〃	〃	0.76	2.78	N25.4°E





図 A6.2-10 計算領域図



屈折係数

入射波向	N
周期	6.7 s
方向集中度 Smax	25



波 向

入射波向	N
周期	6.7 s
方向集中度 Smax	25

図 A6.2-11 波浪変形計算結果例（設計波、波向 N）

資料 6.3 ホニアラ港周辺道路の交通量調査

(1) 交通量調査の概要

ホニアラ港の関連車両は、市街地の中心である Point Cruz 地区を東西に結ぶ幹線道路市内である Mendana Avenue から、Commonwealth Street などのアクセス道路を利用している。本交通量調査は、ホニアラ港国際埠頭に関連した交通量が Mendana Avenue の交通量にしめる割合について把握するために実施した。

調査は、現地調査期間中の 2013 年 3 月 25 日（月）から 3 月 31 日（日）の 1 週間で、交通量の多い昼間の 07:00～19:00 の 12 時間について実施した。なお、3 月 28 日（金）～4 月 1 日（月）の 4 日間は、復活祭のため休日である。

調査地点及び道路諸元は、図 A6.3-1、2 に示すとおりである。それぞれの調査地点における交通量の測定結果は、つぎに示すとおりである。



図 A6.3-1 交通量調査の調査点（A～C 地点）




図 A6.3-2 Mendana Avenue の標準道路断面

(2) 調査地点 A の調査結果

1) 調査地点 A における流入交通量

表 A6.3-1 調査地点 A における流入交通量の測定結果

Period	March 25 (Mon)			March 26 (Tue)			March 27 (Wed)			March 28 (Thu)			March 29 (Fri)			March 30 (Sat)			March 31 (Sun)			Grand Total		
	From	Truck	General Sub T.	Truck	General Sub T.	Truck	General Sub T.	Truck	General Sub T.	Truck	General Sub T.	Truck	General Sub T.	Truck	General Sub T.	Truck	General Sub T.	Truck	General Sub T.	Truck	General Sub T.	Truck	General Sub T.	
0700	0	23	23	5	23	28	19	15	4	15	19	3	6	9	0	0	1	8	9	19	104	123		
0800	13	68	81	20	60	80	82	60	22	60	82	2	8	10	3	14	3	4	7	77	266	343		
0900	32	110	142	35	82	117	107	80	27	80	107	6	12	18	10	39	4	10	14	149	405	554		
1000	29	152	181	24	92	116	119	87	32	87	119	2	10	12	12	24	5	7	12	129	449	578		
1100	21	187	208	19	55	74	127	98	29	98	127	2	11	13	19	44	3	6	9	116	489	605		
1200	15	196	211	20	47	67	119	59	18	59	119	2	7	9	14	29	43	7	14	92	399	491		
1300	34	287	321	39	89	128	138	81	30	108	138	2	13	15	9	19	28	3	9	12	156	606	762	
1400	33	293	326	27	93	120	113	87	26	87	113	3	14	17	5	23	6	10	16	134	598	732		
1500	16	351	367	26	59	85	103	67	23	80	103	3	8	11	5	13	8	7	15	100	566	666		
1600	9	337	346	11	21	32	42	34	8	34	42	3	11	14	6	21	5	6	11	57	475	532		
1700	12	369	381	8	10	18	22	7	25	32	27	1	7	8	5	9	14	2	6	8	41	442	483	
1800	5	348	353	2	11	13	13	5	8	13	13	1	6	7	1	7	8	3	4	7	22	402	424	
Total	219	2,721	2,940	236	642	878	972	741	231	741	972	30	113	143	242	331	50	84	134	1,092	5,201	6,293		
% of Truck	7.4%			26.9%			23.8%			21.0%			26.9%			37.3%			17.4%					




図 A6.3-3 調査地点 A における流入交通量の曜日別分布




図 A6.3-4 調査地点 A における流入交通量の時間別分布

2) 調査地点 A における流出交通量

表 A6.3-2 調査地点 A における流出交通量の測定結果

Period	March 25 (Mon)		March 26 (Tue)		March 27 (Wed)		March 28 (Thu)		March 29 (Fri)		March 30 (Sat)		March 31 (Sun)		Grand Total	
	Truck	General	Truck	General	Truck	General	Truck	General	Truck	General	Truck	General	Truck	General	Truck	General
From	0	4	2	6	3	14	17	4	15	2	5	7	0	0	1	5
0700	4	4	8	59	11	39	50	13	31	3	9	12	3	7	6	6
0800	10	51	17	42	11	24	58	25	65	3	11	14	10	31	41	5
0900	26	79	27	68	24	58	82	25	65	3	11	14	10	31	41	5
1000	31	135	24	86	28	71	99	30	88	2	1	3	6	19	25	4
1100	37	183	22	81	28	118	146	46	115	4	13	17	19	40	59	4
1200	10	279	16	51	11	53	64	11	66	3	4	7	17	39	56	6
1300	30	159	28	61	35	68	103	20	83	0	10	10	10	30	40	4
1400	34	365	38	77	31	80	111	25	71	1	14	15	6	22	28	6
1500	24	247	35	81	28	58	86	22	97	2	12	14	5	12	17	8
1600	10	418	17	32	17	66	83	16	49	5	8	13	7	22	29	5
1700	9	272	7	15	22	13	25	3	23	1	5	6	4	10	14	2
1800	10	432	3	11	4	20	24	5	14	2	11	13	1	8	9	2
1900	231	2,624	236	611	232	658	890	220	717	28	103	131	88	240	328	46
Sub-total	231	2,624	236	611	232	658	890	220	717	28	103	131	88	240	328	46
% of Truck	8.1%		27.9%		26.1%		23.5%		21.4%		26.8%		37.1%		17.7%	




図 A6.3-5 調査地点 A における流出交通量の曜日別分布




図 A6.3-6 調査地点 A における流出交通量の時間別分布

(3) 調査地点 B の調査結果

1) 調査地点 B における東方向交通量

表 A6.3-3 調査地点 B における東方向交通量の測定結果

Period	March 25 (Mon)		March 26 (Tue)		March 27 (Wed)		March 28 (Thu)		March 29 (Fri)		March 30 (Sat)		March 31 (Sun)		Grand Total			
	From	To	Truck	General	Sub T.	Truck	General	Sub T.	Truck	General	Sub T.	Truck	General	Sub T.	Truck	General	Sub T.	
0700	125	615	740	165	590	755	174	616	790	560	727	401	73	337	410	91	384	475
0800	55	762	817	166	734	900	149	718	867	111	442	553	122	554	676	85	444	529
0900	42	826	868	175	729	904	174	828	1,002	103	402	505	114	546	660	89	437	526
1000	40	887	927	170	758	928	149	607	756	110	472	582	72	285	357	89	415	504
1100	96	832	928	196	853	1,049	157	522	679	79	529	608	58	175	233	101	449	550
1200	231	1,122	1,353	147	633	780	125	530	655	95	528	623	54	169	223	86	466	552
1300	89	418	507	199	799	998	184	537	721	87	466	553	126	404	530	104	506	610
1400	180	773	953	166	678	844	66	306	372	78	491	569	84	410	494	135	298	433
1500	131	634	765	196	687	883	80	225	305	73	567	640	110	461	571	67	386	453
1600	147	657	804	145	688	833	96	250	346	93	496	589	95	587	682	107	503	610
1700	130	549	679	160	705	865	81	234	315	73	298	375	298	673	114	550	664	
1800	100	458	558	110	645	755	108	382	490	87	424	511	93	520	613	107	455	562
Sub-total	1,366	8,533	9,899	1,995	8,499	10,494	1,561	5,607	7,168	1,107	5,655	6,762	1,376	4,746	6,122	1,175	5,293	6,468
% of Truck	13.8%		19.0%		21.8%		19.9%		16.4%		22.5%		18.2%		18.5%			




図 A6.3-7 調査地点 B における東方向交通量の曜日別分布




図 A6.3-8 調査地点 B における東方向交通量の時間別分布

2) 調査地点 C における西方向交通量

表 A6.3-6 調査地点 C における西方向交通量の測定結果

Period	March 25 (Mon)		March 26 (Tue)		March 27 (Wed)		March 28 (Thu)		March 29 (Fri)		March 30 (Sat)		March 31 (Sun)		Grand Total	
	Truck	Sub T.	Truck	Sub T.	Truck	Sub T.	Truck	Sub T.	Truck	Sub T.	Truck	Sub T.	Truck	Sub T.	Truck	Sub T.
From 0700	64	676	72	1,000	82	920	72	748	44	615	51	469	31	589	416	5,017
0800	145	1,288	139	1,259	119	1,116	95	1,173	31	525	58	811	31	719	618	6,891
0900	166	1,362	111	1,953	151	1,132	129	1,283	36	467	96	943	39	750	728	7,890
1000	139	1,135	165	1,300	152	1,061	127	1,058	57	827	92	1,005	49	612	781	6,998
1100	132	1,152	128	1,164	146	1,062	132	1,119	42	868	97	905	37	755	714	7,025
1200	112	1,197	115	1,199	111	1,087	115	1,062	75	859	95	848	51	773	674	7,025
1300	140	1,150	119	1,194	131	1,107	86	1,039	48	755	116	1,102	48	714	688	7,061
1400	153	1,147	136	1,016	130	1,013	74	858	62	836	68	747	51	701	674	6,244
1500	120	1,095	156	1,133	121	988	108	1,006	38	839	84	1,213	39	649	666	6,923
1600	103	1,039	110	967	100	920	97	960	35	700	66	905	40	601	551	6,092
1700	114	939	127	1,119	127	928	101	908	41	737	98	952	31	575	606	6,158
1800	37	408	62	962	56	807	72	702	40	732	63	850	39	620	369	5,081
Sub-total	1,425	12,588	1,440	14,266	1,426	12,141	1,208	11,842	549	8,760	984	10,750	486	8,058	7,518	78,405
% of Truck	10.2%		9.2%		10.5%		9.3%		5.9%		8.4%		5.7%		8.7%	




図 A6.3-13 調査地点 C における西方向交通量の曜日別分布




図 A6.3-14 調査地点 C における西方向交通量の時間別分布

