

**MINISTRY OF PUBLIC WORKS AND TRANSPORT(MPWT)
THE ROYAL GOVERNMENT OF THE KINGDOM OF CAMBODIA**

**PREPARATORY SURVEY ON
NATIONAL ROAD NO. 5
IMPROVEMENT PROJECT
(THLEA MA'AM-BATTAMBANG SECTION
AND SRI SOPHORN-POIPET SECTION)
IN THE KINGDOM OF CAMBODIA**

**FINAL REPORT
(VOLUME II APPENDIX)**

OCTOBER 2014

**JAPAN INTERNATIONAL COOPERATION AGENCY
KATAHIRA & ENGINEERS INTERNATIONAL**

EI
CR (3)
14-177 (2)

NATIONAL ROAD NO. 5 IMPROVEMENT PROJECT
(THLEA MA'AM–BATTAMBANG SECTION
AND SRI SOPHORN–POIPET SECTION)
FINAL REPORT
LIST OF APPENDICES

APPENDIX	1-1	MINUTES OF STEERING COMMITTEE MEETING
APPENDIX	2-1	GEOLOGICAL MAP
APPENDIX	4-1	STRAIGHT LINE DIAGRAM
APPENDIX	6-1	INVENTORY SURVEY OF BOX CULVERT
APPENDIX	6-2	INVENTORY SURVEY OF BRIDGE
APPENDIX	6-3	INVENTORY SURVEY OF PIPE CULVERT
APPENDIX	6-4	INQUIRING SURVEY FOR INFORMATION OF FLOODING CONDITIONS 20 th May to 29 th May 2013
APPENDIX	6-5	SKETCHES OF TEST PITS ON THE MIDDLE SECTION
APPENDIX	6-6	SKETCHES OF TEST PITS ON THE SRI SOPHORN–POIPET SECTION
APPENDIX	6-7	SUMMARY OF CBR TESTS FOR THE MIDDLE SECTION
APPENDIX	6-8	SUMMARY OF CBR TESTS FOR THE SRI SOPHORN–POIPET SECTION
APPENDIX	6-9	LOCATION MAP OF BOREHOLES ON THE MIDDLE SECTION
APPENDIX	6-10	BOREHOLE LOG ON THE MIDDLE SECTION
APPENDIX	6-11	SUMMARY OF LABORATORY TEST OF BOREHOLE ON THE MIDDLE SECTION
APPENDIX	6-12	CALCULATED SOIL PARAMETER ON THE MIDDLE SECTION
APPENDIX	8-1	KEY PLAN OF NATIONAL ROAD NO.5 ON THE MIDDLE SECTION
APPENDIX	8-2	KEY PLAN OF NATIONAL ROAD NO.5 ON THE SRI SOPHORN–POIPET SECTION
APPENDIX	8-3	PLAN AND PROFILE OF PURSAT BYPASS
APPENDIX	9-1	BRIDGE DESIGN
APPENDIX	15-1	LIST OF FLORA
APPENDIX	15-2	LIST OF FAUNA
APPENDIX	15-3	RESULT OF NOISE AND VIBRATION SURVEY
APPENDIX	15-4	PREDICTION METHOD AND MODEL
APPENDIX	16-1	PROJECT INFORMATION BOOKLET (ENGLISH DRAFT VERSION)
APPENDIX	16-2	TERMS OF REFERENCE FOR EXTERNAL MONITORING AGENCY
APPENDIX	16-3	TERMS OF REFERENCE FOR INCOME RESTORATION PROGRAMS
APPENDIX	16-4	INVENTORY OF LOSS AND SOCIO-ECONOMIC SURVEY QUESTIONNAIRE FORM

APPENDIX 1-1

MINUTES OF

STEERING COMMITTEE MEETING

MINUTES OF DISCUSSION
Between the Steering Committee and the JICA Survey Team
on
The Inception Report of
The Preparatory Survey for National Road No. 5 Improvement Project
(Middle Section: Thlea Ma'am – Battambang)

Japan International Cooperation Agency (hereinafter referred to as 'JICA') organized a Survey Team for the Preparatory Survey for National Road No. 5 Improvement Project (Middle Section: Thlea Ma'am – Battambang) (hereinafter referred to as 'the Survey').

The First Steering Committee meeting was held on 8 May 2013, and the Inception Report was presented by the Survey Team. The list of the attendants is attached as Attachment 1.


After a series of discussion on the Inception Report, the followings were agreed upon between the Steering Committee and the Survey Team:

- (1) The Survey Team officially submitted the Inception Report to the Steering Committee and made presentation with particular focus on the plan of the Survey.
- (2) The Steering Committee agreed in principle to the contents of the Inception Report.
- (3) The Steering Committee agreed to extend the support to the JICA Survey Team as stated in the Inception Report.
- (4) The Steering Committee requested that the survey on the Sri Sophorn – Poipet Section be added to the survey on the Middle Section and the results of the two surveys be united into one report. JICA answered that JICA will add the survey on the Sri Sophorn – Poipet Section to the contract with the Survey Team (Katahira & Engineers International) upon receipt of a request letter from MPWT before the end of May 2013.
- (5) The Steering Committee commented the following and the Survey Team agreed to incorporate them in the Survey
 - (i) Necessity and route of the Pursat Bypass should be studied.
 - (ii) Measures against flood/inundation need to be diligently studied.
 - (iii) Survey on the Middle Section should be completed in as short period as possible, so that the process of loan appraisal of the Middle Section can be started with minimum time lag from that of the South Section.
 - (iv) The Survey Team should maintain good coordination with MEF/IRC and MOE in preparing RAP and EIA report.
 - (v) Attention should be paid to the rapid increase of traffic volume which is


occurring in the recent years due to increase in vehicle ownership. Attention should be also paid to the planned increase of quota of trucks in the Cross Border Transport Agreement between Cambodia and Thailand.

- (6) The Japanese side requested the Cambodian side that MPWT coordinate with the line ministries to expedite the process of approval of EIA report and finalizing RAP.

Phnom Penh, 8 May 2013



H.E. Tauch Chankosal
Chairperson, Steering Committee
(Secretary of State, MPWT)



Mr. Tatsuyuki Sakurai
Team Leader, JICA Survey Team

Preparatory Survey for National Road No.5 Improvement Project
(Middle Section: Thlea Ma'am - Battambang)

1st Steering Committee, 08 May 2013

The Attendant List

Date: 08 May 2013

Time: 3:00 PM

Place: MPWT

AI-3

Organization	Position	Name	Tel. Number	Signature		
MPWT	Secretary of State	H.E Tauch Chancosal	Personal information, Not disclosed			
	Director General	H.E Kem Borey				
	Director of ICD	Chhim Phalla				
	Deputy Director General	MOM NADA				
Embassy of Japan						
JICA	JICA Expert for JIPWT	SHIMADA Takashi		Personal information, Not disclosed		
	Representative	Egami Masahiko				
	Officer	Say Bora				
Ministry of Economy & Finance	Deputy chief of bid.	Mr. Ream Widan			Personal information, Not disclosed	
	Deputy chief of Prol.	Mr Pich Sodranta				
	K.D	Mr SUONG RUM				
	Director General of ICD	Mr OUK SIM				
Ministry of Environment	Dep. Dir. of Reg. & Licensing	Mr LIM VANN A	Personal information, Not disclosed			

A

Preparatory Survey for National Road No.5 Improvement Project
(Middle Section: Thlea Ma'am - Battambang)

1st Steering Committee, 08 May 2013

The Attendant List

Date: 08 May 2013

Time: 3:00 PM

Place: MPWT

Organization	Position	Name	Tel. Number	Signature
Battambang Province			Personal information, Not disclosed	
Pursat Province		Heran ANI		
	Deputy Director of Dept	Chinh Keornar		
JICA Survey Team	Tatsuyuki SAKURAI	Team Leader		
	Deputy Team Leader	Tomohiko Nakamura		
	Hydrological & Hydraulic Survey Specialist	Himasa Aoki		
	Resettlement	YAMASHITA Akira		
Others	Project Coordination / Assistant Engineer	Masateru Tachibana		
MPWT	Deputy Director KSP	Som Sathira		

A14



Preparatory Survey for National Road No.5 Improvement Project

(Middle Section: Thlea Ma'am - Battambang)

1st Steering Committee, 08 May 2013

The Attendant List

Date: 08 May 2013

Time: 3:00 PM

Place: MPWT

A1-5

Organization	Position	Name	Tel. Number	Signature		
MPWT	Secretary of State	H.E Tauch Chancosal	Personal information, Not disclosed			
	Director General	H.E Kem Borey				
	Director of ICD	Chhim Phalla				
	Deputy Director General	MOM MADA				
Embassy of Japan						
JICA	JICA Export for MPWT Representative	SHIMADA Takashi		Personal information, Not disclosed		
	Officer	Egami Masahiko				
		Say Bora				
Ministry of Economy & Finance	Deputy chief of Bd.	Mr. Ream Udom			Personal information, Not disclosed	
	Deputy chief of Bd.	Mr Pich Socheata				
	K.D	Mr SUONG RUM				
	Director General of the	Mr OUK-DIM				
Ministry of Environment	Dep. W.F. Reg. - Battambang	Mr PHIM VANN A	Personal information, Not disclosed			

Preparatory Survey for National Road No.5 Improvement Project

(Middle Section: Thlea Ma'am - Battambang)








1st Steering Committee, 08 May 2013

The Attendant List

Date: 08 May 2013

Time: 3:00 PM

Place: MPWT

Organization	Position	Name	Tel. Number	Signature	
Battambang Province			Personal information, Not disclosed		
Pursat Province		Heav An			
	Deputy Director of DPWT	Chin Kheom			
JICA Survey Team	Tatsuyuki SAKURAI	Team Leader			P. Sakurai
		Deputy Team Leader		Tomohiko Nakamura	
		Hydrological & Hydraulic Survey Specialist		Hirayasa Aoki	
		Resettlement		YAMASHITA AKIRA	
		Project Coordination / Assistant Engineer		Masateru Tachibana	
Others					
DPWT	Deputy Director Ksp.	SOM. Sothea		SOM Sothea	
Heav An		KHANH Sothea			

AI-6

Preparatory Survey for National Road No.5 Improvement Project

Middle Section: Thlea Ma'am - Battambang

1 st Steering Committee Meeting, 08 May 2013

The Attendant List

Date: 08 May 2013

Time: 3:00 PM

Place: MPWT

Organization	Position	Name	Tel. Number	Signature
MPWT	Secretary of State	H.E Tauch Chankosal	Personal information, Not disclosed	
	Director General	H.E Kem Borey		
	Director of ICD	Chhim Phalla		
	Deputy Director General	Mom Nada		
	Deputy Director KSP (DPWT)	Som Sothea		
JICA	JICA Expert for MPWT	Shimada Takashi		
	Representative	Masahiko Egami		
	Officer	Say Bora		
Ministry of Economy & Finance	Deputy Chief Bilateral	Ream Utdom		
	Deputy Chief Bilateral	Pich Socheata		
Kandal Province	Kandal	Suong Run		
	Kandal	Khan Sokha		
Kampong Chhnang Province	Director General Affairs	Ouk Dim		
	Deputy Director	Yim Vanna		
Pursat Province	Deputy Director	Chinh Kourng		
	Director Inter-field	Hun An		

L-17

Preparatory Survey for National Road No.5 Improvement Project

Middle Section: Thlea Ma'am - Battambang

1 st Steering Committee Meeting, 08 May 2013

The Attendant List

Date: 08 May 2013

Time: 3:00 PM

Place: MPWT

Organization	Position	Name	Tel. Number	Signature
JICA Survey Team	Team Leader	Sakurai Tatsuyuki	Personal information, Not disclosed	
	Deputy Team Leader	Tomohiko Nakamura		
	Hidrological &Hydraulic Survey Speicalist	Heromasa Aoki		
	Resettlement	Yamashita Akira		
	Project Coordination/Assistance Engineer	Masateru Tochinaka		

8-1V
A1-8

MINUTES OF DISCUSSION (Draft 2.9.2013)
Between the Steering Committee and the JICA Survey Team
on
The Progress Report of
The Preparatory Survey for National Road No. 5 Improvement Project
(Middle Section: Thlea Ma'am – Battambang)

Japan International Cooperation Agency (hereinafter referred to as 'JICA') organized a Survey Team for the Preparatory Survey for National Road No. 5 Improvement Project (Middle Section: Thlea Ma'am – Battambang) (hereinafter referred to as 'the Survey').

The Second Steering Committee meeting was held on 30 August 2013, and the Progress Report was presented by the Survey Team. The list of the attendants is attached as Attachment 1.

After a series of discussion on the Progress Report, the followings were agreed upon between the Steering Committee and the Survey Team:

- (1) The Survey Team officially submitted the Progress Report to the Steering Committee and made presentation.
- (2) The Steering Committee agreed in principle to the contents of the Progress Report.
- (3) The Steering Committee commented the following and the Survey Team agreed to incorporate them in the Survey
 - Due attention should be paid to the structure/type of median division from viewpoint of traffic safety, amenity and landscape.

Phnom Penh, 30 August 2013

H.E. Tauch Chankosal
Chairperson, Steering Committee
(Secretary of State, MPWT)

Mr. Tatsuyuki Sakurai
Team Leader, JICA Survey Team

MINUTES OF DISCUSSION

Between the Steering Committee and the JICA Survey Team on
The Interim Report of
The Preparatory Survey for National Road No. 5 Improvement Project
(Middle Section: Thlea Ma'am – Battambang)

Japan International Cooperation Agency (hereinafter referred to as 'JICA') organized a Survey Team for the Preparatory Survey for National Road No. 5 Improvement Project (Middle Section: Thlea Ma'am – Battambang) (hereinafter referred to as 'the Survey').

The third Steering Committee meeting was held on 9 December 2013, and the Interim Report was presented by the Survey Team. The list of the attendants is attached as Attachment 1.


After a series of discussion on the Interim Report, the followings were agreed upon between the Steering Committee and the Survey Team:

- (1) The Survey Team officially submitted the Interim Report to the Steering Committee and made presentation.
- (2) The Steering Committee agreed in principle to the contents of the Interim Report.
- (3) The Steering Committee commented the following and the Survey Team agreed to incorporate them in the Survey
 - The structure of pavement of the Sri Sophorn – Poipet Section should be proposed with alternatives.
 - MPWT should arrange the site visit of the proposed Pursat bypass route with MEF and relevant organizations in January 2014.
 - Comparative Study of the route of Pursat bypass should additionally include more detailed information such as schedule of relocation of houses and land acquisition.
 - The preliminary design shall be further discussed between MEF, MPWT, JICA and the Survey Team before the Draft Final Report is prepared.
- (4) It was agreed that the Cambodian side review the Interim Report and send comments, if there is any, to the Survey Team by the end of January 2013.



Mr. Chhim Phalla
Acting Chairperson, Steering Committee
(Director of International Cooperation
Department, MPWT)

Phnom Penh, 9 December 2013



Mr. Tomohiko Nakamura
Deputy Team Leader,
JICA Survey Team

Preparatory Survey for National Road No.5 Improvement Project

(Middle Section: Thlea Ma'am - Battambang)

3rd Steering Committee, 09 December 2013

The Attendant List

Date: 09 December 2013

Time: 9:00 AM

Place: MPWT

A1-11

Organization	Name	Position	Tel. Number	Signature	
MPWT	H.E Tauch Chancosal	Secretary of State	Personal information, Not disclosed		
	H.E Kem Borey	Director General			
	Chhim Phalla	Director of ICD		<i>[Signature]</i>	
	<i>Kith Chandarith</i>	Deputy Director of ICD		<i>Kith</i>	
	<i>Tapash SHIMBDA</i>	JICA Expert		<i>[Signature]</i>	
Embassy of Japan					
JICA	EGAMI Masahiko	Representative JICA Cambodia			<i>[Signature]</i>
	<i>Nhep Tinal</i>	officer			<i>[Signature]</i>
Ministry of Economic & Finance	<i>Sim Samnang</i>	Deputy RD Director			<i>[Signature]</i>
	<i>Ngay LAYMITHUNAL</i>	TECHNICAL OFFICIAL		<i>[Signature]</i>	
	<i>Sun Sokny</i>	Chief of Office No.2		<i>[Signature]</i>	
	<i>Chheang Chhakin</i>	Deputy Chief of RD office		<i>[Signature]</i>	

Preparatory Survey for National Road No.5 Improvement Project

(Middle Section: Thlea Ma'am - Battambang)

3rd Steering Committee, 09 December 2013

The Attendant List

Date: 09 December 2013

Time: 9:00 AM

Place: MPWT

A1-12

Organization	Name	Position	Tel. Number	Signature
Ministry of Environment			Personal information, Not disclosed	
Pursat Province	HEUN AN	Assistant Director		
	Chinh Kourner	Deputy Director		
Battambang Province				
	Sal Sotat	MPWT BB		
Banteay Meanchey	YIN Vath	Deputy Director		
JICA Survey Team	Yamashita akira	Consultant		
	Tomohiko Nakama	Dep. Team leader		
	Tochinaka Masatear	JICA Survey Team		
Others				
Kg. Chhnang	CAASYLENPA EN	deputy director		
- a -	OKR SIM	Kg. Chhnang PROV		

Preparatory Survey for National Road No.5 Improvement Project

(Middle Section: Thlea Ma'am - Battambang)

3rd Steering Committee, 09 December 2013

The Attendant List

Date: 09 December 2013

Time: 9:00 AM

Place: MPWT

Organization	Name	Position	Tel. Number	Signature

A1-13

MINUTES OF DISCUSSION
Between the Steering Committee and the JICA Survey Team
on
The Draft Final Report of
The Preparatory Survey for National Road No. 5 Improvement Project
(Middle Section: Thlea Ma'am – Battambang and Sri Sophorn – Poipet Section)

Japan International Cooperation Agency (hereinafter referred to as 'JICA') organized a Survey Team for the Preparatory Survey for National Road No. 5 Improvement Project (Middle Section: Thlea Ma'am – Battambang and Sri Sophorn – Poipet Section) (hereinafter referred to as 'the Survey').

The Fourth Steering Committee meeting was held on 13 August 2014, and the Draft Final Report was presented by the Survey Team. The list of the attendants is attached as Attachment 1.

After a series of discussion on the Draft Final Report, the followings were agreed upon between the Steering Committee and the Survey Team:

- (1) The Survey Team officially submitted the Draft Final Report to the Steering Committee and made presentation of the result of the Survey, with particular focus on preliminary design, countermeasures for inundation/flood, and cost estimation.
- (2) The Steering Committee agreed in principle to the contents of the Draft Final Report.
- (3) The Survey Team requested Steering Committee that comments on the Draft Final Report be sent to the Survey Team by the end of August 2014 and the Steering Committee agreed to it.
- (4) The Steering Committee commented the following and the Survey Team agreed to incorporate them in the Survey
 - (i) Future increase of traffic volume should be taken into account.
 - (ii) The Survey Team and MPWT shall have further consultation on the plan of the interchange with the access road to the new border facility.
 - (iii) Cost of weigh station need to be considered.
 - (iv) The Survey Team will confirm the cost of EMP be included in the cost of Consultant Services for the Project.
 - (v) The representative of Ministry of Environment queried the dead line for approval of EIA report and representative of JICA replied that approval by the end of September is acceptable.
 - (vi) MPWT should issue a letter to Pursat Province instructing issuance of a letter on freezing of land transactions along the route of Pursat Bypass.

Phnom Penh, 13 August 2014


















H.E. Tauch Chankosal
Chairperson, Steering Committee
(Secretary of State, MPWT)



Mr. Tatsuyuki Sakurai
Team Leader, JICA Survey Team

National Road No. 5 (Middle Section and Sri Sophorn – Poipet Section) Improvement Project
Attendant List of 4th Steering Committee (13 August 2014)

Organization	Position	Name	Signature	Remarks
MPWT	Secretary of State	H.E. Tauch Chankosal		Chair Person
Ministry of Economy & Finance	Deputy Chief of Resettlement office	Chheang Chhavin		
	offered	NGY CAMHITANA		
		CHUONG CHANTHY		ការទេត្តា គ្រប់គ្រង
Ministry of Environment	Deputy Director	DUONG SAM KEAT		
Pursat Province	Assistant Director	HUN AN		
	Deputy Director - PNT Pursat	Chinh Kournr		
Battambang Province	Deputy Director	SOL SOKET		
Banteay Meanchey Province	Deputy Director	SOK CHANTHA		

Ministry of Public Works & Transport	Director General of Public Work	H.E. Kem Borey		
	Director of Intern'l Cooperation	Mr. Chhin Phalla		
	Deputy Director ICD	KITH Chandararith		
	JICA Expert			
Embassy of Japan	1 st Secretary	Mr. Tomohiro IIZUKA		
JICA Cambodia Office	Senior Representative	Mr. Takashi ITO		
	Representative	Mr. Masahiko EGAMI		
	officer	Nhep Tinat		


MEF	Deputy chief of DBC1	Mr. Ream Utdom	3	DCDM/GDB
JICA Survey Team	Team Leader	Tatsuyuki SAKURAI		


APPENDIX 2-1


GEOLOGICAL MAP


APPENDIX 4-1


STRAIGHT LINE DIAGRAM















APPENDIX 6-1

INVENTORY SURVEY OF BOX CULVERT

KP: **171+800**

No.: **Bc54**


Date: **20-May-2013**



KP: **179+100**

No.: **Bc55**

Date: **20-May-2013**




Note: BC means Box Culvert, W=Total Width, W₁/W₂/W_i =Net Width, H=Total Height, H₁/H₂/H_i =Net Height, L=Total Length, h=Water Depth, tc=Height of Soil over Top, River means Tonle Sap River

KP: **179+500**

No.: **Bc56**

Date:

20-May-2013



2-BC

W	=	6.25	(m)
W ₁ , W ₂	=	2.85	(m)
H	=	2.25	(m)
H ₁ , H ₂	=	1.90	(m)
L	=	13.60	(m)
h	=	0.20	(m)
tc	=	0.62	(m)


Lake Side (Outlet)

KP: **179+800**

No.: **Bc57**

Date:

20-May-2013



3-BC

W	=	9.60	(m)
W ₁ , W ₃	=	2.85	(m)
W ₂	=	3.00	(m)
H	=	2.20	(m)
H ₁ , H ₃	=	1.65	(m)
H ₂	=	1.80	(m)
L	=	12.20	(m)
h	=	0.40	(m)
tc ₁ , tc ₃	=	0.73	(m)
tc ₂	=	0.48	(m)


Lake Side (Outlet)

Note: BC means Box Culvert, W=Total Width, W₁/W₂/W₃=Net Width, H=Total Height, H₁/H₂/H₃ =Net Height, L=Total Length, h=Water Depth, tc₁/tc₂/tc₃=Height of Soil over Top, River means the Tonle Sap River

KP: **182+200**

No.: **Bc58**

Date: **20-May-2013**



1-BC


W	=	2.90	(m)
W _i	=	2.80	(m)
H	=	2.15	(m)
H _i	=	1.75	(m)
L	=	13.60	(m)
h	=	0.20	(m)
tc	=	0.65	(m)

Lake Side (Outlet)

KP: **196+500**

No.: **Bc59**

Date: **21-May-2013**



1-BC

W	=	3.10	(m)
W _i	=	3.00	(m)
H	=	2.20	(m)
H _i	=	1.60	(m)
L	=	14.00	(m)
h	=	0.10	(m)
tc	=	0.80	(m)

Lake Side (Outlet)


Note: BC means Box Culvert, W=Total Width, W_i=Net Width, H=Total Height, H_i= Net Height, L=Total Length, h=Water Depth, tc=Height of Soil over Top, River means the Tonle Sap River

KP: **199+300**

No.: **Bc60**

Date:

21-May-2013



1-BC

W	=	3.10	(m)
W _i	=	3.00	(m)
H	=	1.90	(m)
H _i	=	1.45	(m)
L	=	13.80	(m)
h	=	0.10	(m)
tc	=	0.75	(m)


Lake Side (Outlet)

KP: **214+100**

No.: **Bc61**

Date:

22-May-2013



3-BC

W	=	9.45	(m)
W ₁ , W ₃	=	2.80	(m)
W ₂	=	2.95	(m)
H	=	2.40	(m)
H ₁ , H ₃	=	1.75	(m)
H ₂	=	2.00	(m)
L	=	13.70	(m)
h	=	0.00	(m)
tc ₁ , tc ₃	=	0.97	(m)
tc ₂	=	0.72	(m)

Lake Side (Outlet)


Note: BC means Box Culvert, W=Total Width, W₁/W₂/W₃=Net Width, H=Total Height, H₁/H₂/H₃=Net Height, L=Total Length, h=Water

Depth, tc₁/tc₂/tc₃=Height of Soil over Top, River means the Tonle Sap River

KP: **218+800**

No.: **Bc62**


Date: **22-May-2013**



KP: **218+900**

No.: **Bc63**

Date: **22-May-2013**




Note: BC means Box Culvert, W=Total Width, W_i=Net Width, H=Total Height, H_i=Net Height, L=Total Length, h=Water Depth, tc=Height of Soil over Top. River means the Tonle Sap River

KP: **221+400**

No.: **Bc64**

Date:

22-May-2013



2-BC

W	=	4.10	(m)
W ₁ , W ₂	=	1.80	(m)
H	=	2.40	(m)
H ₁ , H ₂	=	2.00	(m)
L	=	13.70	(m)
h	=	0.00	(m)
tc	=	0.80	(m)


Lake Side (Outlet)

KP: **221+700**

No.: **Bc65**

Date:

22-May-2013



2-BC

W	=	6.30	(m)
W ₁ , W ₂	=	3.00	(m)
H	=	2.25	(m)
H ₁ , H ₂	=	1.80	(m)
L	=	16.02	(m)
h	=	0.00	(m)
tc	=	1.25	(m)

Lake Side (Outlet)

Note: BC means Box Culvert, W=Total Width, W₁/W₂=Net Width, H=Total Height, H₁/H₂=Net Height, L=Total Length, h=Water Depth,,


tc=Height of Soil over Top, River means the Tonle Sap River

KP: **230+400**

No.: **Bc66**

Date:

22-May-2013



2-BC

W	=	6.30	(m)
W ₁ , W ₂	=	3.00	(m)
H	=	2.20	(m)
H ₁ , H ₂	=	1.80	(m)
L	=	13.70	(m)
h	=	0.00	(m)
tc	=	0.65	(m)


Lake Side (Outlet)

KP: **232+800**

No.: **Bc67**

Date:

23-May-2013



1-BC

W	=	3.20	(m)
W _i	=	3.10	(m)
H	=	1.85	(m)
H _i	=	1.45	(m)
L	=	13.70	(m)
h	=	0.00	(m)
tc	=	0.75	(m)


Lake Side (Outlet)

Note: BC means Box Culvert, W=Total Width, W₁/W₂/W_i =Net Width, H=Total Height, H₁/H₂/H_i =Net Height, L=Total Length, h=Water Depth, tc=Height of Soil over Top,

KP: **237+400**

No.: **Bc68**

Date: **23-May-2013**



1-BC


W	=	3.10	(m)
W _i	=	3.00	(m)
H	=	1.95	(m)
H _i	=	1.55	(m)
L	=	13.70	(m)
h	=	0.00	(m)
tc	=	0.80	(m)

Lake Side (Outlet)

KP: **238+200**

No.: **Bc69**

Date: **23-May-2013**



1-BC

W	=	3.10	(m)
W _i	=	3.00	(m)
H	=	2.30	(m)
H _i	=	1.90	(m)
L	=	13.70	(m)
h	=	0.10	(m)
tc	=	0.62	(m)


Lake Side (Outlet)

Note: BC means Box Culvert, W=Total Width, W_i=Net Width, H=Total Height, H_i=Net Height, L=Total Length, h=Water Depth, tc=Height of Soil over Top.

KP: **240+000**

No.: **Bc70**

Date: **23-May-2013**



3-BC


W	=	6.65	(m)
W ₁ , W ₃	=	2.80	(m)
W ₂	=	3.00	(m)
H	=	2.50	(m)
H ₁ , H ₃	=	1.85	(m)
H ₂	=	2.10	(m)
L	=	13.70	(m)
h	=	0.00	(m)
tc ₁ , tc ₃	=	0.75	(m)
tc ₂	=	0.50	(m)

Lake Side (Outlet)

KP: **245+400**

No.: **Bc71**

Date: **23-May-2013**



3-BC

W	=	7.50	(m)
W ₁ , W ₃	=	2.80	(m)
W ₂	=	3.00	(m)
H	=	2.45	(m)
H ₁ , H ₃	=	1.80	(m)
H ₂	=	2.05	(m)
L	=	13.80	(m)
h	=	1.40	(m)
tc ₁ , tc ₃	=	1.30	(m)
tc ₂	=	1.05	(m)

Lake Side (Outlet)


Note: BC means Box Culvert, W=Total Width, W₁/W₂/W₃=Net Width, H=Total Height, H₁/H₂/H₃=Net Height, L=Total Length, h=Water Depth, tc₁/tc₂/tc₃=Height of Soil over Top, River means the Tonle Sap River

KP: **248+500**

No.: **Bc72**

Date:

23-May-2013



2-BC

W	=	6.35	(m)
W ₁ , W ₂	=	2.85	(m)
H	=	2.45	(m)
H ₁ , H ₂	=	2.00	(m)
L	=	13.70	(m)
h	=	0.00	(m)
tc	=	0.45	(m)


Lake Side (Outlet)

KP: **249+000**

No.: **Bc73**

Date:

23-May-2013



1-BC

W	=	3.10	(m)
W _i	=	3.00	(m)
H	=	2.45	(m)
H _i	=	2.05	(m)
L	=	13.80	(m)
h	=	0.00	(m)
tc	=	0.65	(m)

Lake Side (Outlet)

Note: BC means Box Culvert, W=Total Width, W₁/W₂/W_i =Net Width, H=Total Height, H₁/H₂/H_i =Net Height, L=Total Length, h=Water


Depth, tc=Height of Soil over Top, River means the Tonle Sap River

KP: 251+000

No.: Bc74

Date:

23-May-2013



3-BC

W	=	9.70	(m)
W ₁ , W ₃	=	2.85	(m)
W ₂	=	3.00	(m)
H	=	2.60	(m)
H ₁ , H ₃	=	2.00	(m)
H ₂	=	2.20	(m)
L	=	13.70	(m)
h	=	0.00	(m)
tc ₁ , tc ₃	=	0.72	(m)
tc ₂	=	0.52	(m)


Lake Side (Outlet)

KP: 252+400

No.: Bc75

Date:

23-May-2013



3-BC

W	=	9.50	(m)
W ₁ , W ₃	=	2.85	(m)
W ₂	=	3.00	(m)
H	=	1.35	(m)
H ₁ , H ₃	=	0.75	(m)
H ₂	=	1.00	(m)
L	=	13.70	(m)
h	=	0.30	(m)
tc ₁ , tc ₃	=	1.20	(m)
tc ₂	=	0.95	(m)

Lake Side (Outlet)


Note: BC means Box Culvert, W=Total Width, W₁/W₂/W₃=Net Width, H=Total Height, H₁/H₂/H₃=Net Height, L=Total Length, h=Water Depth, tc₁/tc₂/tc₃=Height of Soil over Top, River means the Tonle Sap River

KP: 254+700

NO.: Bc76

Date:

23-May-2013




KP: 255+900

No.: Bc77

Date:

23-May-2013




Note: BC means Box Culvert, W=Total Width, W₁/W₂=Net Width, H=Total Height, H₁/H₂=Net Height, L=Total Length, h=Water Depth, tc=Height of Soil over Top,

KP: **259+100**

No.: **Bc78**

Date:

23-May-2013



2-BC

W	=	6.20	(m)
W ₁	=	2.75	(m)
W ₂	=	2.85	(m)
H	=	2.30	(m)
H ₁ , H ₂	=	1.90	(m)
L	=	13.70	(m)
h	=	0.00	(m)
tc	=	0.75	(m)


Lake Side (Outlet)

KP: **261+400**

No.: **Bc79**

Date:

23-May-2013



2-BC

W	=	8.60	(m)
W ₁ , W ₂	=	4.15	(m)
H	=	2.35	(m)
H ₁ , H ₂	=	1.90	(m)
L	=	13.70	(m)
h	=	0.00	(m)
tc	=	1.05	(m)


Lake Side (Outlet)

Note: BC means Box Culvert, W=Total Width, W₁/W₂=Net Width, H=Total Height, H₁/H₂=Net Height, L=Total Length, h=Water Depth, tc=Height of Soil over Top.

KP: **262+300**

No.: **Bc80**

Date: **24-May-2013**



2-BC


W	=	6.30	(m)
W_1, W_2	=	2.85	(m)
H	=	2.40	(m)
H_1, H_2	=	2.00	(m)
L	=	13.70	(m)
h	=	0.00	(m)
tc	=	0.45	(m)

Lake Side (Outlet)

KP: **264+100**

No.: **Bc81**

Date: **24-May-2013**



2-BC

W	=	6.20	(m)
W_1, W_2	=	2.85	(m)
H	=	2.20	(m)
H_1, H_2	=	1.80	(m)
L	=	13.70	(m)
h	=	0.00	(m)
tc	=	0.55	(m)

Lake Side (Outlet)


Note: BC means Box Culvert, W =Total Width, W_1/W_2 =Net Width, H =Total Height, H_1/H_2 =Net Height, L =Total Length, h =Water Depth,

tc =Height of Soil over Top,

KP: 267+000

No.: Bc82

Date: 24-May-2013



3-BC


W	=	9.60	(m)
W ₁ , W ₃	=	2.85	(m)
W ₂	=	3.00	(m)
H	=	2.60	(m)
H ₁ , H ₃	=	1.95	(m)
H ₂	=	2.20	(m)
L	=	13.70	(m)
h	=	0.00	(m)
tc ₁ , tc ₃	=	0.75	(m)
tc ₂	=	0.50	(m)

Lake Side (Outlet)

KP: 269+700

No.: Bc83

Date: 24-May-2013



2-BC

W	=	6.30	(m)
W ₁ , W ₂	=	3.00	(m)
H	=	2.40	(m)
H ₁ , H ₂	=	2.00	(m)
L	=	13.00	(m)
h	=	0.00	(m)
tc	=	0.55	(m)


Lake Side (Outlet)

Note: BC means Box Culvert, W=Total Width, W₁/W₂/W₃=Net Width, H=Total Height, H₁/H₂/H₃=Net Height, L=Total Length, h=Water Depth, tc₁/tc₂/tc₃=Height of Soil over Top, River means the Tonle Sap River

KP: 270+400

No.: Bc84

Date: 24-May-2013



2-BC


W	=	6.30	(m)
W ₁ , W ₂	=	3.00	(m)
H	=	2.25	(m)
H ₁ , H ₂	=	1.90	(m)
L	=	13.10	(m)
h	=	0.00	(m)
tc	=	0.60	(m)

Lake Side (Outlet)

KP: 274+200

No.: Bc85

Date: 26-May-2013



1-BC

W	=	2.90	(m)
W _i	=	2.85	(m)
H	=	2.05	(m)
H _i	=	1.65	(m)
L	=	13.70	(m)
h	=	0.00	(m)
tc	=	0.55	(m)


Lake Side (Outlet)

Note: BC means Box Culvert, W=Total Width, W₁/W₂/W_i =Net Width, H=Total Height, H₁/H₂/H_i =Net Height, L=Total Length, h=Water Depth, tc=Height of Soil over Top,

KP: **276+100**

No.: **Bc86**

Date: **26-May-2013**



1-BC


W	=	2.90	(m)
W _i	=	2.85	(m)
H	=	2.35	(m)
H _i	=	1.95	(m)
L	=	13.70	(m)
h	=	0.00	(m)
tc	=	0.55	(m)

Lake Side (Outlet)

KP: **280+700**

No.: **Bc87**

Date: **26-May-2013**



1-BC

W	=	3.10	(m)
W _i	=	3.00	(m)
H	=	2.20	(m)
H _i	=	1.80	(m)
L	=	13.70	(m)
h	=	0.00	(m)
tc	=	0.65	(m)


Lake Side (Outlet)

Note: BC means Box Culvert, W=Total Width, W_i=Net Width, H=Total Height, H_i=Net Height, L=Total Length, h=Water Depth, tc=Height of Soil over Top, River means the Tonle Sap River

KP: **281+700**

No.: **Bc88**

Date: **26-May-2013**



3-BC


W	=	9.50	(m)
W ₁ , W ₃	=	2.85	(m)
W ₂	=	3.00	(m)
H	=	2.60	(m)
H ₁ , H ₃	=	1.95	(m)
H ₂	=	2.20	(m)
L	=	13.70	(m)
h	=	0.00	(m)
tc ₁ , tc ₃	=	1.05	(m)
tc ₂	=	0.80	(m)

Lake Side (Outlet)

KP: **283+700**

No.: **Bc89**

Date: **27-May-2013**



3-BC

W	=	9.55	(m)
W ₁ , W ₃	=	2.85	(m)
W ₂	=	3.00	(m)
H	=	2.60	(m)
H ₁ , H ₃	=	1.95	(m)
H ₂	=	2.20	(m)
L	=	26.70	(m)
h	=	0.00	(m)
tc ₁ , tc ₃	=	3.15	(m)
tc ₂	=	2.90	(m)

Lake Side (Outlet)


Note: BC means Box Culvert, W=Total Width, W₁/W₂/W₃=Net Width, H=Total Height, H₁/H₂/H₃=Net Height, L=Total Length, h=Water Depth, tc₁/tc₂/tc₃=Height of Soil over Top, River means the Tonle Sap River

KP: **285+100**

No.: **Bc90**

Date:

27-May-2013



1-BC

W	=	2.00	(m)
W _i	=	1.90	(m)
H	=	2.35	(m)
H _i	=	2.00	(m)
L	=	14.40	(m)
h	=	0.00	(m)
tc	=	0.85	(m)


Lake Side (Outlet)

KP: **294+000**

No.: **Bc91**

Date:

27-May-2013



2-BC

W	=	6.30	(m)
W ₁ , W ₂	=	2.85	(m)
H	=	2.30	(m)
H ₁ , H ₂	=	1.85	(m)
L	=	23.20	(m)
h	=	0.80	(m)
tc	=	0.80	(m)


Lake Side (Outlet)

Note: BC means Box Culvert, W=Total Width, W₁/W₂/W_i =Net Width, H=Total Height, H₁/H₂/H_i =Net Height, L=Total Length, h=Water Depth, tc=Height of Soil over Top,

KP: 295+000

No.: Bc92

Date: 27-May-2013



3-BC


W	=	9.35	(m)
W ₁ ,	=	2.85	(m)
W ₂	=	2.90	(m)
W ₃	=	2.75	(m)
H	=	2.65	(m)
H ₁ , H ₂ , H ₃	=	2.00	(m)
L	=	23.10	(m)
h	=	1.60	(m)
tc ₁ , tc ₂ , tc ₃	=	0.65	(m)

Lake Side (Outlet)

KP: 297+500

No.: Bc93

Date: 27-May-2013



2-BC

W	=	6.20	(m)
W ₁ , W ₂	=	2.85	(m)
H	=	1.90	(m)
H ₁ , H ₂	=	1.50	(m)
L	=	13.70	(m)
h	=	0.00	(m)
tc	=	0.55	(m)


Lake Side (Outlet)

Note: BC means Box Culvert, W=Total Width, W₁/W₂/W₃=Net Width, H=Total Height, H₁/H₂/H₃=Net Height, L=Total Length, h=Water Depth, tc₁/tc₂/tc₃=Height of Soil over Top,

KP: 302+300

No.: Bc94


Date: 28-May-2013



KP: 303+600

No.: Bc95

Date: 28-May-2013




Note: BC means Box Culvert, W=Total Width, W₁/W₂=Net Width, H=Total Height, H₁/H₂=Net Height, L=Total Length, h=Water Depth,
tc=Height of Soil over Top,

KP: **306+400**

No.: **Bc96**

Date: **28-May-2013**



2-BC


W	=	6.25	(m)
W ₁ , W ₂	=	2.85	(m)
H	=	1.95	(m)
H ₁ , H ₂	=	1.55	(m)
L	=	12.30	(m)
h	=	0.00	(m)
tc	=	0.56	(m)

Lake Side (Outlet)

KP: **309+100**

No.: **Bc97**

Date: **28-May-2013**



3-BC

W	=	9.60	(m)
W ₁ , W ₃	=	2.85	(m)
W ₂	=	3.00	(m)
H	=	2.55	(m)
H ₁ , H ₃	=	1.90	(m)
H ₂	=	2.15	(m)
L	=	13.70	(m)
h	=	0.10	(m)
tc ₁ , tc ₃	=	0.85	(m)
tc ₂	=	0.60	(m)


Lake Side (Outlet)

Note: BC means Box Culvert, W=Total Width, W₁/W₂/W₃=Net Width, H=Total Height, H₁/H₂/H₃=Net Height, L=Total Length, h=Water Depth, tc₁/tc₂/tc₃=Height of Soil over Top,

KP: **310+400**

No.: **Bc98**

Date: **28-May-2013**



3-BC


W	=	9.60	(m)
W ₁ , W ₃	=	2.85	(m)
W ₂	=	3.00	(m)
H	=	2.40	(m)
H ₁ , H ₃	=	1.75	(m)
H ₂	=	2.00	(m)
L	=	13.70	(m)
h	=	0.00	(m)
tc ₁ , tc ₃	=	0.77	(m)
tc ₂	=	0.52	(m)

Lake Side (Outlet)

KP: **311+300**

No.: **Bc99**

Date: **28-May-2013**



3-BC

W	=	9.60	(m)
W ₁ , W ₃	=	2.85	(m)
W ₂	=	3.00	(m)
H	=	2.60	(m)
H ₁ , H ₃	=	1.95	(m)
H ₂	=	2.20	(m)
L	=	13.70	(m)
h	=	0.00	(m)
tc ₁ , tc ₃	=	0.75	(m)
tc ₂	=	0.50	(m)

Lake Side (Outlet)

Note: BC means Box Culvert, W=Total Width, W₁/W₂/W₃=Net Width, H=Total Height, H₁/H₂/H₃=Net Height, L=Total Length, h=Water Depth, tc₁/tc₂/tc₃=Height of Soil over Top, Lake means the Tonle Sap Lake


APPENDIX 6-2

INVENTORY SURVEY OF BRIDGE

KP: **177+200**

No.: **Br40**

Date: **May 20, 2013**



1-Br


W	=	23.1	(m)
W _i	=	23.1	(m)
H	=	5.5	(m)
H _i	=	4.3	(m)
L	=	9.6	(m)
B	=	12.2	(m)
t	=	1.2	(m)
P _i	=	N/A	(m)

Lake Side (down stream)

KP: **178+500**

No.: **Br41**

Date: **May 20, 2013**



1-Br

W	=	19.8	(m)
W _i	=	19.8	(m)
H	=	4.4	(m)
H _i	=	2.8	(m)
L	=	10.0	(m)
B	=	11.0	(m)
t	=	1.6	(m)
P _i	=	N/A	(m)

Lake Side (down stream)


Note: Br means Bridge, W=Total Width, W_i=Net Width, H=Total Height, H_i=Net Height, L=Total Length, B=River bed Width, t=Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: **181+800**

No.: **Br42**

Date:

May 20, 2013



4-Br

W	=	19.2	(m)
W ₁ , W ₂ , W ₃ , W ₄	=	4.8	(m)
H	=	2.2	(m)
H _i	=	1.4	(m)
L	=	9.1	(m)
B	=	14.8	(m)
t	=	0.8	(m)
Pi	=	0.8	(m)


Lake Side (down stream)

KP: **182+800**

No.: **Br43**

Date:

May 20, 2013



2-Br

W	=	42.6	(m)
W ₁ , W ₂	=	21.3	(m)
H	=	3.5	(m)
H _i	=	2.9	(m)
L	=	10.0	(m)
B	=	35.7	(m)
t	=	0.55	(m)
Pi	=	0.9	(m)

Lake Side (down stream)


Note: Br means Bridge, W=Total Width, W_i=Net Width, H=Total Height, H_i=Net Height, L=Total Length, B=River bed Width, t=Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: **183+300**

No.: **Br44**

Date:

May 20, 2013



3-Br

W	=	45.3	(m)
W_1, W_2, W_3	=	15.1	(m)
H	=	4.9	(m)
H_i	=	3.6	(m)
L	=	9.0	(m)
B	=	35.6	(m)
t	=	1.25	(m)
Pi	=	1.5	(m)


Lake Side (down stream)

KP: **183+900**

No.: **Br45**

Date:

May 21, 2013



2-Br

W	=	42.5	(m)
W_1, W_2	=	21.25	(m)
H	=	6.0	(m)
H_i	=	5.3	(m)
L	=	10.0	(m)
B	=	30.6	(m)
t	=	0.65	(m)
Pi	=	0.6	(m)


Lake Side (down stream)

Note: Br means Bridge, W=Total Width, W_i =Net Width, H=Total Height, H_i =Net Height, L=Total Length, B=River bed Width, t=Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: **184+100**

No.: **Br46**

Date: **May 21, 2013**



1-Br

W	=	26.5	(m)
W _i	=	26.5	(m)
H	=	3.2	(m)
H _i	=	2.5	(m)
L	=	10.1	(m)
B	=	20.2	(m)
t	=	0.65	(m)
Pi	=	N/A	(m)

Lake Side (down stream)

KP: **185+700**

No.: **Br47** ✕

Date: **May 21, 2013**

1-Br

W	=		(m)
W _i	=		(m)
H	=		(m)
H _i	=		(m)
L	=		(m)
B	=		(m)
t	=		(m)
Pi	=		(m)

Lake Side (down stream)


Note: Br means Bridge, W=Total Width, W_i=Net Width, H=Total Height, H_i=Net Height, L=Total Length, B=River bed Width, t=Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: **187+400**

No.: **Br48**

Date:

May 21, 2013



2-Br

W	=	39.1	(m)
W ₁ , W ₂	=	19.55	(m)
H	=	6.1	(m)
H _i	=	4.5	(m)
L	=	8.8	(m)
B	=	39.1	(m)
t	=	1.6	(m)
Pi	=	1.6	(m)


Lake Side (down stream)

KP: **187+700**

No.: **Br49**

Date:

May 21, 2013



2-Br

W	=	30.5	(m)
W ₁ , W ₂	=	15.25	(m)
H	=	3.4	(m)
H _i	=	2.5	(m)
L	=	10.0	(m)
B	=	23.8	(m)
t	=	0.9	(m)
Pi	=	0.7	(m)


Lake Side (down stream)

Note: Br means Bridge, W=Total Width, W_i=Net Width, H=Total Height, H_i=Net Height, L=Total Length, B=River bed Width, t=Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: **188+100**

No.: **Br50**

Date: **May 21, 2013**



3-Br


W	=	61.0	(m)
W_1	=	18.0	(m)
W_2, W_3	=	21.5	(m)
H	=	2.5	(m)
H_i	=	1.9	(m)
L	=	10.0	(m)
B	=	56.0	(m)
t	=	0.65	(m)
P_i	=	0.9	(m)

Lake Side (down stream)

KP: **188+250**

No.: **Br51**

Date: **May 21, 2013**



3-Br

W	=	51.5	(m)
W_1	=	15.0	(m)
W_2, W_3	=	18.25	(m)
H	=	2.9	(m)
H_i	=	2.2	(m)
L	=	10.0	(m)
B	=	45.8	(m)
t	=	0.65	(m)
P_i	=	0.9	(m)


Lake Side (down stream)

Note: Br means Bridge, W =Total Width, W_i =Net Width, H =Total Height, H_i =Net Height, L =Total Length, B =River bed Width, t =Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: **189+250**

No.: **Br52**

Date: **May 21, 2013**



4-Br


W	=	36.5	(m)
W_1, W_2	=	18.25	(m)
H	=	3.6	(m)
H_i	=	3.0	(m)
L	=	10.0	(m)
B	=	29.4	(m)
t	=	0.6	(m)
P_i	=	0.9	(m)

Lake Side (down stream)

KP: **189+900**

No.: **Br53**

Date: **May 21, 2013**



1-Br

W	=	24.5	(m)
W_i	=	24.5	(m)
H	=	2.1	(m)
H_i	=	2.5	(m)
L	=	10.0	(m)
B	=	20.3	(m)
t	=	0.6	(m)
P_i	=	N/A	(m)

Lake Side (down stream)


Note: Br means Bridge, W =Total Width, W_i =Net Width, H =Total Height, H_i =Net Height, L =Total Length, B =River bed Width, t =Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: **190+150**

No.: **Br54**

Date:

May 21, 2013



1-Br

W	=	24.5	(m)
W _i	=	24.5	(m)
H	=	1.9	(m)
H _i	=	1.3	(m)
L	=	10.0	(m)
B	=	20.8	(m)
t	=	0.55	(m)
Pi	=	N/A	(m)


Lake Side (down stream)

KP: **191+100**

No.: **Br55**

Date:

May 21, 2013



2-Br

W	=	36.4	(m)
W ₁ , W ₂	=	18.2	(m)
H	=	4.9	(m)
H _i	=	4.3	(m)
L	=	10.0	(m)
B	=	26.7	(m)
t	=	0.55	(m)
Pi	=	0.4	(m)


Lake Side (down stream)

Note: Br means Bridge, W=Total Width, W_i=Net Width, H=Total Height, H_i=Net Height, L=Total Length, B=River bed Width, t=Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: **201+800**

No.: **Br56**


Date: **May 21, 2013**



KP: **208+500**

No.: **Br57** ✕

Date: **May 21, 2013**



Note: Br means Bridge, W=Total Width, W_i =Net Width, H=Total Height, H_i =Net Height, L=Total Length, B=River bed Width, t=Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: **215+750**

No.: **Br58** ✕

Date: **May 22, 2013**

3-Br			
W	=		(m)
W ₁	=		(m)
W ₂ , W ₃	=		(m)
H	=		(m)
H _i	=		(m)
L	=		(m)
B	=		(m)
t	=		(m)
Pi	=		(m)
Lake Side (down stream)			

KP: **219+600**

No.: **Br59** ✕

Date: **May 22, 2013**

3-Br			
W	=		(m)
W ₁	=		(m)
W ₂	=		(m)
W ₃	=		(m)
H	=		(m)
H _i	=		(m)
L	=		(m)
B	=		(m)
t	=		(m)
Pi	=		(m)
Lake Side (down stream)			


Note: Br means Bridge, W=Total Width, W_i=Net Width, H=Total Height, H_i=Net Height, L=Total Length, B=River bed Width, t=Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: **220+800**

No.: **Br60**

Date:

May 22, 2013



2-Br

W	=	30.4	(m)
W ₁ , W ₂	=	15.2	(m)
H	=	4.2	(m)
H _i	=	3.8	(m)
L	=	10.0	(m)
B	=	22.1	(m)
t	=	0.4	(m)
Pi	=	0.4	(m)


Lake Side (down stream)

KP: **222+650**

No.: **Br61**

Date:

May 22, 2013



1-Br

W	=	18.5	(m)
W _i	=	18.5	(m)
H	=	2.9	(m)
H _i	=	2.5	(m)
L	=	10.0	(m)
B	=	12.7	(m)
t	=	0.4	(m)
Pi	=	N/A	(m)


Lake Side (down stream)

Note: Br means Bridge, W=Total Width, W_i=Net Width, H=Total Height, H_i=Net Height, L=Total Length, B=River bed Width, t=Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: **223+650**

No.: **Br62**

Date: **May 22, 2013**



1-Br


W	=	18.5	(m)
W_i	=	18.5	(m)
H	=	3.0	(m)
H_i	=	2.6	(m)
L	=	10.0	(m)
B	=	12.5	(m)
t	=	0.4	(m)
Pi	=	N/A	(m)

Lake Side (down stream)

KP: **242+850**

No.: **Br63**

Date: **May 23, 2013**



1-Br

W	=	24.5	(m)
W_i	=	24.5	(m)
H	=	3.0	(m)
H_i	=	2.4	(m)
L	=	10.0	(m)
B	=	18.6	(m)
t	=	0.6	(m)
Pi	=	N/A	(m)


Lake Side (down stream)

Note: Br means Bridge, W=Total Width, W_i =Net Width, H=Total Height, H_i =Net Height, L=Total Length, B=River bed Width, t=Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: **243+600**

No.: **Br64**

Date: **May 23, 2013**



2-Br

W	=	37.0	(m)
W ₁ , W ₂	=	18.5	(m)
H	=	3.1	(m)
H _i	=	2.6	(m)
L	=	10.0	(m)
B	=	30.9	(m)
t	=	0.5	(m)
Pi	=	0.4	(m)

Lake Side (down stream)

KP: **244+400**

No.: **Br65** ✕

Date: **May 23, 2013**

3-Br

W	=		(m)
W ₁	=		(m)
H	=		(m)
H _i	=		(m)
L	=		(m)
B	=		(m)
t	=		(m)
Pi	=		(m)

Lake Side (down stream)


Note: Br means Bridge, W=Total Width, W_i=Net Width, H=Total Height, H_i=Net Height, L=Total Length, B=River bed Width, t=Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: **245+900**

No.: **Br66**

Date:

May 23, 2013



2-Br

W	=	15.8	(m)
W_1, W_2	=	7.9	(m)
H	=	2.4	(m)
H_i	=	1.9	(m)
L	=	9.1	(m)
B	=	15.8	(m)
t	=	0.5	(m)
Pi	=	0.8	(m)


Lake Side (down stream)

KP: **255+250**

No.: **Br67**

Date:

May 23, 2013



1-Br

W	=	21.5	(m)
W_i	=	21.5	(m)
H	=	2.4	(m)
H_i	=	1.9	(m)
L	=	10.0	(m)
B	=	16.7	(m)
t	=	0.5	(m)
Pi	=	N/A	(m)

Lake Side (down stream)


Note: Br means Bridge, W=Total Width, W_i =Net Width, H=Total Height, H_i =Net Height, L=Total Length, B=River bed Width, t=Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: **255+600**

No.: **Br68**

Date:

May 23, 2013



2-Br

W	=	30.5	(m)
W ₁ , W ₂	=	15.25	(m)
H	=	2.3	(m)
H _i	=	1.9	(m)
L	=	10.0	(m)
B	=	25.9	(m)
t	=	0.4	(m)
Pi	=	0.4	(m)


Lake Side (down stream)

KP: **256+550**

No.: **Br69**

Date:

May 23, 2013



1-Br

W	=	21.5	(m)
W _i	=	21.5	(m)
H	=	2.5	(m)
H _i	=	2.0	(m)
L	=	10.0	(m)
B	=	16.5	(m)
t	=	0.5	(m)
Pi	=	N/A	(m)

Lake Side (down stream)


Note: Br means Bridge, W=Total Width, W_i=Net Width, H=Total Height, H_i=Net Height, L=Total Length, B=River bed Width, t=Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: 257+900

No.: Br70

Date:

May 23, 2013



1-Br

W	=	18.5	(m)
W _i	=	18.5	(m)
H	=	3.0	(m)
H _i	=	2.5	(m)
L	=	10.0	(m)
B	=	12.6	(m)
t	=	0.45	(m)
Pi	=	N/A	(m)


Lake Side (down stream)

KP: 265+348

No.: Br71

Date:

May 24, 2013



1-Br

W	=	18.5	(m)
W _i	=	18.5	(m)
H	=	2.9	(m)
H _i	=	2.4	(m)
L	=	18.5	(m)
B	=	12.8	(m)
t	=	0.45	(m)
Pi	=	N/A	(m)


Lake Side (down stream)

Note: Br means Bridge, W=Total Width, W_i=Net Width, H=Total Height, H_i=Net Height, L=Total Length, B=River bed Width, t=Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: **270+900**

No.: **Br72**


Date: **May 24, 2013**



KP: **271+700**

No.: **Br73**

Date: **May 24, 2013**




Note: Br means Bridge, W=Total Width, W_i=Net Width, H=Total Height, H_i=Net Height, L=Total Length, B=River bed Width, t=Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: **272+650**

No.: **Br74**

Date:

May 24, 2013




KP: **273+300**

No.: **Br75**

Date:

May 24, 2013




Note: Br means Bridge, W=Total Width, W_i=Net Width, H=Total Height, H_i=Net Height, L=Total Length, B=River bed Width, t=Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: 275+650

No.: Br76

Date:

May 26, 2013



1-Br

W	=	18.5	(m)
W _i	=	18.5	(m)
H	=	2.5	(m)
H _i	=	2.1	(m)
L	=	10.0	(m)
B	=	13.5	(m)
t	=	0.45	(m)
Pi	=	N/A	(m)


Lake Side (down stream)

KP: 276+550

No.: Br77

Date:

May 26, 2013



1-Br

W	=	18.5	(m)
W _i	=	18.5	(m)
H	=	2.4	(m)
H _i	=	2.0	(m)
L	=	10.0	(m)
B	=	13.7	(m)
t	=	0.45	(m)
Pi	=	N/A	(m)


Lake Side (down stream)

Note: Br means Bridge, W=Total Width, W_i=Net Width, H=Total Height, H_i=Net Height, L=Total Length, B=River bed Width, t=Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: **292+000**

No.: **Br78**

Date: **May 27, 2013**



3-Br


W	=	130.8	(m)
W ₁ , W ₂ , W ₃	=	43.6	(m)
H	=	12.6	(m)
H _i	=	12.6	(m)
L	=	6.6	(m)
B	=	12.6	(m)
t	=	N/A	(m)
Pi	=	N/A	(m)

Lake Side (down stream)

KP: **303+400**

No.: **Br79**

Date: **May 28, 2013**



1-Br

W	=	13.7	(m)
W _i	=	13.65	(m)
H	=	5.1	(m)
H _i	=	3.8	(m)
L	=	7.0	(m)
B	=	3.8	(m)
t	=	1.35	(m)
Pi	=	N/A	(m)

Lake Side (down stream)


Note: Br means Bridge, W=Total Width, W_i=Net Width, H=Total Height, H_i=Net Height, L=Total Length, B=River bed Width, t=Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: **305+800**

No.: **Br80**

Date:

May 28, 2013



1-Br

W	=	26.3	(m)
W_i	=	26.25	(m)
H	=	3.4	(m)
H_i	=	2.8	(m)
L	=	10.0	(m)
B	=	2.8	(m)
t	=	0.6	(m)
P_i	=	N/A	(m)


Lake Side (down stream)

KP: **307+200**

No.: **Br81**

Date:

May 28, 2013



1-Br

W	=	26.3	(m)
W_i	=	26.25	(m)
H	=	2.5	(m)
H_i	=	1.8	(m)
L	=	10.0	(m)
B	=	1.8	(m)
t	=	0.65	(m)
P_i	=	N/A	(m)

Lake Side (down stream)


Note: Br means Bridge, W =Total Width, W_i =Net Width, H =Total Height, H_i =Net Height, L =Total Length, B =River bed Width, t =Girder thickness, N/A means data not available. Lake means Tonle Sap Lake

KP: **312+000**

No.: **Br82**

Date:

May 28, 2013



Note: Br means Bridge, W=Total Width, W_i =Net Width, H=Total Height, H_i =Net Height, L=Total Length, B=River bed Width, t=Girder thickness, N/A means data not available. Lake means Tonle Sap Lake