


***CHAPTER 2***

***REVIEW OF EXISTING INFORMATION AND EXPLORATION***

## 2.1-1 Sfax Port

2.1-1



***CHAPTER 4***

***WATER SUPPLY PLAN FOR GREATER SFAX***

4.1-1 Presentation Material for International Donors Conference in Marseille, France



REPUBLIQUE TUNISIENNE  
MINISTRE DE L'AGRICULTURE  
SOCIETE NATIONALE D'EXPLOITATION ET DE DISTRIBUTION DES EAUX




---

## Marseille, 4 et 5 Février 2014

### Projet National d'investissement de Renforcement et de Sécurisation de l'Alimentation d'Eau Potable

Présenté par : Adnan BOUBAKER  
DIRECTEUR CENTRAL DES ETUDES



## Construction du barrage réservoir Saida (1/4)

**RESPONSABLE DE MISE EN OEUVRE** : DGBGTH

**EXPLOITANT** : SONEDE ou DGBGTH

**OBJET** : Construction d'un barrage réservoir à Saida dans la région de Béjaoua (à l'Ouest du Grand Tunis) pour stocker une eau prélevée du canal Medjerda Cap y compris l'infrastructure d'alimentation

**POPULATION CONCERNEE**: 5.5 million d'habitants

**OBJECTIFS** :

- Régulation saisonnière pour combler le déficit en ressources en période estivale.
- Sécurisation de l'approvisionnement en eau potable en cas de problème au niveau du canal Medjerda Cap Bon.

35

## Construction du barrage réservoir Saida (2/4)

**CONSISTANCE DES TRAVAUX** :

- 1/ Construction d'un barrage réservoir à Saida (45 Mm<sup>3</sup>),
- 2/ Réalisation d'adduction d'alimentation,
- 3 / Construction de stations de pompage.
- 4/ Construction d'un réservoir de mise en charge
- 5/ Raccordement au réseau électrique MT de la STEG.

**COÛT ESTIMATIF** : 121.3 MDT HT (54.0 million €)

| Sous composante                             | Coût (MDT)   |
|---|--------------|
| Retenue de régulation (45 Mm <sup>3</sup> ) | 81.4         |
| Adductions                                  | 22.1         |
| Pompage                                     | 13.3         |
| Réservoir                                   | 4.1          |
| Electrification                             | 0.5          |
| <b>TOTAL</b>                                | <b>121.3</b> |

36

## Construction du barrage réservoir Saida (3/4)

### ETAT D'AVANCEMENT DES ETUDES :

- APD achevé en 1999 par VODNIIFORMPROEKT Mouscou.
- Les TDR de l'Etude d'impact sur l'environnement, sont en cours de préparation par la DGBGTH.

### PLANNING DE REALISATION : (2016-2018)

37

## Construction du barrage réservoir Saida (4/4)



38

## Système de transfert des eaux brutes de Saida vers Belli (1/3)

**RESPONSABLE DE MISE EN OEUVRE : SONEDE**

**EXPLOITANT : SONEDE ou SECADENORD**

**OBJET : Transférer pendant la période de faible demande en eau les eaux brutes depuis le barrage réservoir à réaliser à Saida vers la station de pompage El Kouine au pied du complexe Belli**

**POPULATION CONCERNEE: 3.0 million d'habitants**

**OBJECTIFS :**

Satisfaire les besoins en eau potable pour les régions du Grand Tunis et de Sahel.

**CONSISTANCE DES TRAVAUX :**

- 1/ Pose de conduites de transfert.
- 2/ Construction de stations de pompage.

39

## Système de transfert des eaux brutes de Saida vers Belli (2/3)

**COÛT ESTIMATIF : 90 MDT HT (40.0 million €)**

| Désignation            | Coût (MDT)  |
|------------------------|-------------|
| Adductions             | 78.1        |
| Pompage                | 8.7         |
| Acquisition de terrain | 3.4         |
| <b>TOTAL</b>           | <b>90.2</b> |

**ETAT D'AVANCEMENT DES ETUDES :**

- Etude de faisabilité SOGREAH-STUDI –IDEA CONSULT, 2005.
- Etude stratégique, SONEDE 2013.
- Etudes d'exécution et DAO en cours par SONEDE

**PLANNING DE REALISATION :**  
(2016-2018)

40

### Système de transfert des eaux brutes de Saida vers Belli (3/3)



41

### Construction du barrage réservoir Sahel (1/3)

**RESPONSABLE DE MISE EN OEUVRE : DGBGTH**

**EXPLOITANT : SONEDE**

**OBJET : Construction d'un barrage réservoir dans la région de Kalaa Kébira pour stocker une eau prélevée du système de transfert des eaux du Nord**

**POPULATION CONCERNEE: 2.3 million d'habitants**

**OBJECTIFS :**

- Stocker des quantités d'eaux importantes et de les restituer au réseau après traitement en période de forte demande.
- Sécurisation de l'approvisionnement en eau potable de la région du Sahel et en partie de Sfax en cas de problème au niveau du canal Medjerda, d'interruption accidentelle de la production dans la station de traitement de Belli ou incident sur l'adduction des Eaux du Nord

42



## Construction du barrage réservoir Sahel (2/3)

### CONSISTANCE DES TRAVAUX :

- 1/ Construction d'un barrage réservoir (26 Mm<sup>3</sup>),
- 2/ Réalisation d'adduction d'alimentation et une station de pompage

COUT ESTIMATIF : 113.6 MDT HT (50.5 million €)

| Désignation                                 | Coût (MDT)   |
|---|--------------|
| Retenue de régulation (26 Mm <sup>3</sup> ) | 88.2         |
| Adductions                                  | 21.1         |
| Pompage                                     | 4.3          |
| <b>TOTAL</b>                                | <b>113.6</b> |


### ETAT D'AVANCEMENT DES ETUDES :

- Etude de faisabilité SOGREA-STUDI –IDEACONSULT, 2005.
- Etude d'avant projet sommaire, groupement STUKY – CONCEPT, 2011
- Etude d'impact sur l'environnement, groupement STUKY – CONCEPT, transmis à l'ANPE depuis le 26 mars 2013.
- Etude d'avant projet détaillé en cours, groupement STUKY – CONCEPT.

PLANNING DE REALISATION :  
(2016-2018)

43

## Construction du barrage réservoir Sahel (3/3)



44

## Renforcement des réseaux et capacité de réserve des eaux du Nord pour les régions de Sahel et Sfax (1/2)

**RESPONSABLE DE MISE EN OEUVRE : SONEDE**

**EXPLOITANT : SONEDE**

**OBJET** : Transférer les eaux brutes pendant la période de faible demande en eau depuis la station de pompage El Khouine située au pied du complexe Belli vers un barrage réservoir à réaliser dans la région du Sahel

**POPULATION CONCERNEE**: 2.3 million d'habitants

**OBJECTIFS** :

Satisfaire les besoins en eau potable pour les régions du Cap Bon, Sahel et Sfax jusqu'à l'horizon 2030

**CONSISTANCE DES TRAVAUX** :

- 1/ Renforcement réseaux, capacités de pompage et réserves à Belli
- 2 / Séparation des deux conduites des eaux du Nord (traitée et brutes)

45

## Renforcement des réseaux et capacité de réserve des eaux du Nord pour les régions de Sahel et Sfax (2/2)

**COÛT ESTIMATIF** : 38.3 MDT HT (17.0 million €)

| Désignation  | Sous composante | Coût (MDT) |             |
|--|-----------------|------------|-------------|
| Renforcement des réseaux et capacités de pompage et des réserves au complexe Belli   | Adductions      | 7.8        | 30.9        |
|  | Pompage         | 17.7       |             |
|  | Réservoirs      | 5.4        |             |
| Infrastructure de séparation des deux conduites des eaux du Nord (traitée et brutes) | Adductions      | 4.7        | 7.4         |
|  | Réservoirs      | 2.7        |             |
| <b>TOTAL</b>   |                 |            | <b>38.2</b> |

**ETAT D'AVANCEMENT DES ETUDES** :

- Etude de faisabilité SOGREAH-STUDI –IDEACONSULT, 2005
- Etude stratégique, SONEDE 2013.
- Etudes d'exécution et DAO en cours par SONEDE

**PLANNING DE REALISATION** :  
(2016-2018)

46

## Construction de la station de traitement de Sahel (1/3)

**RESPONSABLE DE MISE EN OEUVRE : SONEDE**

**EXPLOITANT : SONEDE**

**OBJET** : Construction d'une station de traitement des eaux brutes et son raccordement au système de transfert des eaux du Nord au niveau de la région de Sahel

**POPULATION CONCERNEE**: 2.3 million d'habitants

**OBJECTIFS** :

Satisfaire les besoins en eau potable pour la région de Sahel et Sfax

**CONSISTANCE DES TRAVAUX** :

- 1/ Construction d'une station de traitement des eaux brutes de capacité 4 m<sup>3</sup>/s
- 2/ Réalisation d'adduction de raccordement au système de transfert des eaux du Nord,
- 3/ Construction d'une station de pompage

47

## Construction de la station de traitement de Sahel (2/3)

**COÛT ESTIMATIF** : 69.2 MDT HT (31.0 million €)

| Désignation                                 | Coût (MDT)  |
|---|-------------|
| Station de traitement (4 m <sup>3</sup> /s) | 35.3        |
| Adductions                                  | 21.1        |
| Pompage                                     | 6.0         |
| Foncier                                     | 6.8         |
| <b>TOTAL</b>                                | <b>69.2</b> |


**ETAT D'AVANCEMENT DES ETUDES** :

- Etude de faisabilité faite par la SONEDE en 2013.
- Etudes d'exécution et DAO en cours par SONEDE


**PLANNING DE REALISATION** :  
(2016-2018)

48

### Construction de la station de traitement de Sahel (3/3)



49



## 4.3-1 Existing Water Supply Facilities in Greater Sfax

### Table of Contents

|                           |       |
|---------------------------|-------|
| 1. Outline -----          | 4.3-2 |
| 2. Groundwater -----      | 4.3-2 |
| 3. Pumping Station -----  | 4.3-3 |
| 4. Service Reservoir----- | 4.3-3 |

### **4.3-1 Existing Water Supply Facilities in Greater Sfax**

#### **1. Outline**

There are three water sources for water supply in Greater Sfax as follows:

- Treated water transferred by pumping through the North Water Transfer System for about 200 km, from Belli water treatment plant with the water resource originated in Medjerda River.
- Groundwater transferred from Jelma and Sbeitla, and
- Groundwater pumped up in Sfax

The transferred water and groundwater are stored at distribution reservoirs located inland of Sfax and distributed to two water distribution districts, i.e. high and low distribution districts, from respective reservoirs by gravity. Water from each reservoir is distributed to high or low distribution districts. Further subdivision is not introduced.

#### **2. Groundwater**

##### **(1) Groundwater Well**

In recent years, water demand in upstream areas of the North Water Transfer System and the Jelma-Sbeitla Groundwater Transfer System has been increased, and consequently available water volume is decreased in Greater Sfax where no large water source exists, and then serious continuous water interruption happened. To cope with the situation in Sfax, SONEDE drilled wells at its reservoir sites as emergency measures though groundwater pumped up through those wells has high salinity. Groundwater pumped up in Sfax is distributed after mixing with the water transferred from the north water transfer system and Jelma-Sbeitla Groundwater transfer system. SONEDE evaluated its available water volume from those groundwater sources in Sfax at 491  $\ell$ /second or about 42,400 $m^3$ /day.

##### **(2) Groundwater treatment facility**

###### **1) Purpose of the installation and capacity**

Recently, on purpose to reinforce the supply capacity of water services, a well and groundwater treatment facility was installed in the plot of the PK10. The water yield is a fairly large quantity of 60 $\ell$ /s (216  $m^3$ /h), and the facility is operated 200-250 days a year. In Sfax region, there are totally 5 similar groundwater treatment facilities installed in the other service reservoirs and so on.

###### **2) Outline of the facility**

The treatment facility is for iron removal of groundwater composed of the aeration tower and sand filter. The aeration tower is for oxidation of iron in the water by the air-liquid contact technique; the raw groundwater falls down from the top and the air blows from the bottom in up-flow direction promoting the contact between

the air and water.

The aerated water is pumped through the sand filter and oxidized suspended iron is removed at the filter. The sand filter is pressure system in the horizontal tank. The accumulated iron at the filter layer is washed by periodical backwashing and discharged to the out of filter. The series of the operation such as filtration and backwash are all automatic.




Photo 1 Aeration tower



Photo 2 Sand filter

### 3. Pumping Station

The Sfax service areas are divided into two zones: one is the lower zone lying along the coast at the lower elevations, and the other, the upper zone located inland at the higher elevations. Each service area receives water supply from a couple of service reservoirs by gravity. Accordingly the Greater Sfax has no pump stations for transmission and distribution.

### 4. Service Reservoir

SONEDE installed service reservoirs in various parts of the Greater Sfax area, among which those in service to the city zone are listed in Table 1 including those now under repair and in planning.

**Table 1 Principal Reservoirs**

| Name of Reservoir     | Volume (m <sup>3</sup> ) | Service Zone | HWL (m) | LWL (m) | Remarks                          |
|-----------------------|--------------------------|--------------|---------|---------|----------------------------------|
| Bou Merra             | 500                      | Higher       | 84.0    | 79.0    | Bou Merra_N +1,500m <sup>3</sup> |
| PK11                  | 22,000                   | Lower        | 59.0    | 53.0    | 5000m <sup>3</sup> x4+1000x2     |
| PK14                  | 10,000                   | Higher       | 78.8    | 73.0    | 5000m <sup>3</sup> x2            |
| PK10                  | 20,000                   | Lower        | 58.0    | 52.0    | 5000m <sup>3</sup> x4            |
| Sidi Salah_Haut       | 2,500                    | Higher       | 79.0    | 73.0    |                                  |
| Sidi Salah_Bas (plan) | -                        | Lower        | 59.0    | 53.0    | Plan+5000m <sup>3</sup>          |

Source: SONEDE

One of the major reservoirs, PK10, was examined under this study for its operation and maintenance, as follows:

#### (1) Water source and quality

The water sources of PK10 are the surface water in the north transmitted to and purified at Belli Treatment Plant, the groundwater from Jelma and Sbeitla in the west, and the groundwater pumped up from the well inside the plot as described later.

The water from those three water sources is blended and equalized in quality in the mixing basin, reserved in the four (4) distribution basins, and then distributed to each distribution areas in lower service zone.

The salinity (TDS) of the water sources are; the surface water 1.3-1.4 g/l, groundwater 3.5-4 g/l, and the blended water of the PK10, 2 to 2.1 g/l which is under the drinking water standard of 2.5g/l.



**Photo 3 Mixing basin (right)**



**Photo 4 Inside of the mixing basin**

## (2) Specifications of the distribution basin

Each distribution basin is constructed above ground, shape of cylindrical and reinforced-concrete made.

For the prevention of temperature rise of the wall, upper slab and reserved water of the basin, the wall and upper slab are covered by soil protecting the concrete from the direct sunlight. Also grasses are planned on the protecting soil which presents a fine spectacle.

The above specifications of the distribution basin are the standard design of SONEDE.



**Photo 5 Distribution Basins**



***CHAPTER 5***

***STUDY ON SEA WATER DESALINATION PLANT***

**5.2-1 Selection of Site for Sea Water Desalination Plant, and Route for Transmission Pipeline**

**Table of Contents**

1. Candidate Sites for Sea Water Desalination Plant -----5.2-2

2. Topography and Water Quality of the Sea in Front of Candidate Sites -----5.2-2

3. Method of Site Selection -----5.2-7

4. Candidate Site Comparison and Evaluation Result----- 5.2-11

## 5.2-1 Selection of Sea Water Desalination Plant Construction Site

### 1. Candidate sites for seawater desalination plant

Before starting this survey, SONEDE has picked up candidate sites by their own idea, mainly from viewpoints of distance from city of Sfax (Refer to Site 1 – Site4 in Table 1 and Figure 1). Candidate sites were evaluated in accordance with agreed “Selection Criteria” with SONEDE. Further 3 sites (Refer to Site 4 – Site7 in Table 1 and Figure 1) were added from viewpoints of accessibility to intake/discharge points.

Firstly, these sites were evaluated from viewpoints of general situation of site location, and after selection of four (4) sites, actual “Construction cost” and “Electric cost for product water transmission pump operation” for each candidate sites were evaluated. Finally two (2) candidate sites are selected. This is the Phase 1, and final selection was studied in Phase 2 afterward.

**Table.1 Candidate sites for seawater desalination plant**

| No.    | Loation      | Governorte | North Latitude | East Longitude |
|--------|--------------|------------|----------------|----------------|
| SITE 1 | El Amra Nord | Sfax       | 34.921381      | 10.921379      |
| SITE 2 | El Amra Sud  | Sfax       | 34.847586      | 10.885692      |
| SITE 3 | Agareb       | Sfax       | 34.617982      | 10.624981      |
| SITE 4 | Chebba Sud   | Mahdia     | 35.189466      | 11.097065      |
| SITE 5 | Nakta        | Sfax       | 34.554409      | 10.594427      |
| SITE 6 | Chebba Nord  | Mahdia     | 35.258148      | 11.112843      |
| SITE 7 | Mahres       | Sfax       | 34.506152      | 10.446425      |

Note: Latitude and longitude are based on GPS data

Source: JICA Survey Team


### 2. Topography and water quality of the sea in front of candidate sites

The 10m deep contour line in the sea is show on Figure 1. Depth of 10m is considered to be suitable for direct intake method, which is recommendable for the project because of volume of intake. Topography f seabed in front of Sfax is shallow to a considerable distance from the shore. There are no sea deeper than 10m in the area of northern are of Sfax (around Site 1, 2 and 4).

Topography of the sea at each candidate site are presented in Annexed Figures 1 o 4.

#### (2) Water Quality

Due to pollution of coastal areas, and consequently a possibility of elution of heavy metals from deposited pollution sediment, it is necessary to check the water quality for planned seawater desalination facility construction projects. Since it is necessary to secure a depth of 8m to 10m for installation of intake facility, and intake point will be located at approximately 5m in depth, the sampling points are selected at the location of approximately 10m depth near the seawater desalination facility candidate sites. Samples were taken from 5m depth at each point. It was also decided to check the water quality of a position of 50cm above seabed. Selected sampling points are shown in Figure 2. Table 2 presents the position information of each sampling points. Five sampling points were selected in total. For candidate sites 4 and 6, sampling point No. 1 was selected, and for candidate sites Nos. 1 and 2, sampling point No. 2 was selected, while sampling points Nos. 3, 4 and 5 corresponds to candidate sites Nos. 3, 5 and 7 respectively. Analytical results of water quality in each place are shown in Table 2. The minimum requirement to select the desalination plants site analyzed in this Phase 1 Survey. Detailed analysis of heavy metals and other items, etc. on the selected site will be conducted in Phase 2.



Source: JICA Survey Team


**Figure1 Location of Candidate Sites**

Considering the water quality analysis results of Table.2, noteworthy analysis results are not shown except TDS. TDS had been estimated to be 33,000 mg/l to 38,000 mg/l in this area, but results showed 43,000 mg/l to 50,000 mg/l in each data collection point.

**Table.2 Sampling Points and Sea Water Quality**

| Analysis items              | Point 1                       | Point 2                       | Point 3                       | Point 4                       | Point5                        |        |          |          |          |        |          |
|-----------------------------|-------------------------------|-------------------------------|-------------------------------|-------------------------------|-------------------------------|--------|----------|----------|----------|--------|----------|
| Location data<br>(by GPS)   | N:35.2648413<br>E:011.1184828 | N:34.8085109<br>E:010.9516900 | N:34.5836229<br>E:010.6553259 | N:34.5362839<br>E:010.6054000 | N:34.4905769<br>E:010.4849709 |        |          |          |          |        |          |
| Seawater samples            |                               |                               |                               |                               |                               |        |          |          |          |        |          |
| Analysis items              | Unit                          | Depth                         |                               | Depth                         |                               | Depth  |          | Depth    |          | Depth  |          |
|                             |                               | 5m                            | ~10m                          | 5m                            | ~10m                          | 5m     | ~10m     | 5m       | ~10m     | 5m     | ~10m     |
| Temperature                 | °C                            | 25                            | 25                            | 26                            | 26                            | 25     | 24.8     | 25       | 24.4     | 24.9   | 25       |
| pH                          | -                             | 7.7                           | 7.7                           | 7.8                           | 7.8                           | 7.8    | 7.8      | 7.8      | 7.8      | 7.8    | 7.7      |
| EC (Electric Conductivity)  | S/cm                          | 47.3                          | 47.6                          | 48.2                          | 48.4                          | 47.7   | 48.5     | 47.9     | 47.4     | 47.7   | 47.2     |
| TDS (Total Dissolved Solid) | mg/ℓ                          | 43,282                        | 43,430                        | 43,364                        | 43,547                        | 56,579 | 45,938   | 45,471   | 44,057   | 50,613 | 43,092   |
| Turbidity                   | NTU                           | 0                             | 0                             | 0                             | 0                             | 0      | 0        | 0        | 0        | 0      | 0        |
| SS (Suspended Solid)        | mg/ℓ                          | 29                            | 75.5                          | 70                            | 77.5                          | 85.5   | 78.5     | 20.5     | 74.5     | 67     | 76.5     |
| Na <sup>+</sup> (Sodium)    | mg/ℓ                          | 12,901.5                      | 12,394.5                      | 13,072                        | 12,326.5                      | 13,278 | 13,140.5 | 12,582   | 15,386.5 | 14,433 | 12,717   |
| Cl <sup>-</sup> (Chloride)  | mg/ℓ                          | 22,680.5                      | 21,650                        | 21,717                        | 21,446                        | 22,661 | 21,929   | 2,1405.5 | 25,986   | 25,057 | 21,685.5 |
| SiO <sub>2</sub> (Silica)   | mg/ℓ                          | 0.563                         | 0.570                         | 0.313                         | 0.671                         | 0.404  | 0.301    | 0.508    | 0.528    | 0.755  | 0.563    |
| B (Boron)                   | mg/ℓ                          | 0.157                         | 0.529                         | 0.165                         | 0.236                         | 0.987  | 0.469    | 0.381    | 0.315    | 0.602  | 0.236    |
| TOC (Total Organic Carbon)  | mg/ℓ                          | 0.43                          | 0.77                          | <0.1                          | <0.1                          | 0.88   | 0.48     | 0.34     | 0.28     | 0.4    | 0.14     |

Source : JICA Survey Team



Source : JICA Survey Team

Figure 2 Locations of Sampling Points

### (3) Analysis of Sediments

There is a possibility that the sediment deposited on the seabed is contaminated by heavy metals. Upon water quality sampling, seabed mud samples were simultaneously collected from sampling point, which were analyzed for radioactive materials and heavy metals. Results are shown in Table 3. Except the seawater sampling point No.4, the lead concentration of each candidate site were slightly above that of the reference. It shall be noted that there is a possibility sediments is rolled up when the ocean is rough.

**Table 3 Analysis of Sediment**

| Analysis item               | unit  | Point 1 | Point 2 | Point 3 | Point 4 | Point 5 | Referential data of comparison * |
|-----------------------------|-------|---------|---------|---------|---------|---------|----------------------------------|
| Cu <sup>++</sup> (Copper)   | mg/kg | 2.28    | 5.36    | 6.07    | 2.78    | 6.51    | ≤ 60                             |
| Pb <sup>++</sup> (Lead)     | mg/kg | 208.79  | 154.77  | 127.63  | 53.28   | 234.54  | ≤ 110                            |
| Zn <sup>++</sup> (Zinc)     | mg/kg | 23.22   | 20.11   | 28.92   | 16.31   | 46.11   | ≤ 365                            |
| Cd <sup>++</sup> (Cadmium)  | mg/kg | 0.04    | 0.08    | 0.06    | 0.06    | 0.06    | ≤ 4                              |
| Ni <sup>++</sup> (Nickel)   | mg/kg | 17.51   | 30.56   | 29.63   | 10.76   | 41.23   | ≤ 45                             |
| Cr <sup>++</sup> (Chromium) | mg/kg | 7.96    | 5.05    | 12.14   | 11.58   | 23.36   | ≤ 120                            |
| Radioactivity               | Bq/s  | 0       | 0       | 0       | 0.198   | 0.395   | ≤ 100                            |
| Uranium                     | Bq/s  | ND      | ND      | ND      | ND      | ND      | ≤ 0.183                          |

※ : Limits of Acceptability for sediment discharge into the sea in Tunisia.

Source: JICA Survey Team

### (4) Benthic Plant

It is seaweed [posidonia] is a kind of famous submarine plants in Ibiza which is registered as a world heritage in Spain Country Balearic Islands in Sfax coastal waters. It inhabit near Kerkennah Island especially. In addition it inhabits in Sfax coastline. We had confirmation of this fact on each site survey of seabed mud sample. (refer to Figures 2 and 3). And thus concentrated water discharge pipe and raw water intake pipe is construction on the seabed. It will be affected by digging of pipeline for intake line and discharge line. But, I considered it have a low impact on the posidonia with the course of time after construction work. Further investigation is needed about this problem.



Source : SONEDE

**Figure 3**  
**Posidonia Glowing**  
**Location**

### 3. Method of Site Selection

Upon discussions with SONEDE, the method for site selection was decided as follows;

#### (1) Selection Policy

##### 1) Basic Prerequisite for the study

Intake process is preliminary studied from the data of similar plant, and concluded as follows.

Direct intake process with pipeline shall be adopted for this project because of its required quantity.

There are two types of direct intake. i.e. Surface seawater intake and Deep sea water intake with pipeline transmission. In case of surface intake, intake area near the coast should be dredged around 10meter depth for preventing from absorption of sand and/or sediment on the seabed. When considering the construction cost and future maintenance cost for this Surface intake, Deep sea intake may be cheaper than dredging the seabed. Therefore Deep sea water intake method is selected for this project.

##### 2) Selection Criteria

###### (i) Authorization procedure

Draft of Selection Criteria was prepared by the JICA Survey Team and discussed with SONEDE. The key points for the Criteria are as follows.

- a) Each check items have different evaluation points of view, and different importance. Therefore different score was allocated to each check item.
- b) By this different scoring allocation, candidate sites were evaluated with different points. Score/Points for each item are shown in Figure 1.

###### (ii) Evaluation items

Sites are reviewed and evaluated from following viewpoints.




- a) Accessibility to reliable seawater source
  - Stable obtaining of high quality sea water
- b) Easy land acquisition
  - Public land or Private land
- c) Accessibility to adequate Energy sources
  - Enough electricity is available near the sites
- d) Minimize environ impacts
  - Brine discharge
  - Impact to ecosystem
- e) Easy access to water distribution
  - Distance to reservoir for water distribution network for consumer

### 3) Scoring criteria in each evaluation items

Evaluation items of #11 (distance from intake and discharging point), #31 (distance from electric grid), and #51 (distance for reservoirs) are important for the site selection.


Therefore scoring criteria for these important evaluation items are separately studied. Item #11 and #31 are evaluated by its distance, and #51 is evaluated by the estimated construction cost for pipeline to reservoirs. Refer to Figure 5 and Figure 6.

Especially #11 is further confirmed any differences by giving different scoring point as per Figure 5. As the result, not so big difference was obtained by different scoring system, which means some site always gets high score and some site gets low score. From this fact, scoring case one (1) is applied to this #11.




Source: JICA Survey team

**Figure 4 Selection Criteria**




Source: JICA Survey team

**Figure 5 #11- Distance from Intake Point vs. Scoring Point**



Source: JICA Survey team

**Figure 6 #31- Distance from Grid vs. Scoring Point**



Source: JICA Survey team

**Figure 7 #51- Cost for Pipeline to Reservoirs vs. Scoring Point**

#### 4. Candidate Site Comparison and Evaluation Result

Site space requires not only for 200,000 m<sup>3</sup>/d desalination plant, but also, seawater receiving pit, product water tank, electric power receiving equipment, stock house for chemicals and necessary materials for operation, general administration building and parking space, etc. Actual space will be studied in next Phase 2, but based on the data from other similar desalination plant, around 200,000m<sup>2</sup> are estimated to be necessary for this project.

Seven (7) sites in Figure 1 were evaluated in accordance with the selection method.

##### (1) 1st Evaluation

Firstly, based on three (3) cases shown in Figure 5, scoring sensitivity for #11 are studied. Result is shown in the Graph in Table 4. From this result, not big difference is obtained. i.e. Site 1, 2 and 4 are always in low score. Total score, based on case 1 for #11, is shown in Table 5

As the conclusion, site 3, 5, 6 and 7 have passed this 1st evaluation, and these are further studied from view point of construction cost as 2nd evaluation.

**Table5 Result of 1st Evaluation**


| Site No | Site name           | Score (Case 1 in #11)<br>65 point perfect | Propriety  | Reference                     |
|---------|---------------------|---|------------|-------------------------------|
| 1       | El Amra Nord (Sfax) | 37  | disqualify |                               |
| 2       | El Amra Sud (Sfax)  | 41  | disqualify |                               |
| 3       | Agareb (Sfax)       | 51  |            | To 2 <sup>nd</sup> evaluation |
| 4       | Chebba Sud (Mahdia) | 29  | disqualify |                               |
| 5       | Nakta (Sfax)        | 53  |            | To 2 <sup>nd</sup> evaluation |
| 6       | Chebba Nord(Mahdia) | 47  |            | To 2 <sup>nd</sup> evaluation |
| 7       | Mahres(Sfax)        | 48  |            | To 2 <sup>nd</sup> evaluation |

Source: JICA Survey team

**Table 4 Evaluation Result in Each Site**

| Ref No    | Site No.  | Point  | 1            | Point Case1                                | Case2/Case3 | 2   | Point Case1 | Case2/Case3 | 3   | Point Case1 | Case2/Case3 | 4                                       | Point Case1 | Case2/Case3 | 5                                       | Point Case1 | Case2/Case3 | 6                                       | Point Case1 | Case2/Case3 | 7                                       | Point Case1 | Case2/Case3 | Scoring standard   |
|-----------|---|--|--------------|--|-------------|---|-------------|-------------|---|-------------|-------------|---|-------------|-------------|---|-------------|-------------|---|-------------|-------------|---|-------------|-------------|--|
|           | Name  |  | El Amra Nord |  |             | El Amra Sud   |             |             | Agareb  |             |             | Chebba Sud                              |             |             | Nakta                                   |             |             | Chebba Nord                             |             |             | Mahres                                  |             |             |  |
|           | Governerates  |  | SFAX         |  |             | SFAX  |             |             | SFAX  |             |             | MAHDIA                                  |             |             | SFAX                                    |             |             | MAHDIA                                  |             |             | SFAX                                    |             |             |  |
| 0         | Distance from Center of SFAX (Straight)                   |  | 25km         |  |             | 17km  |             |             | 18km  |             |             | 60km                                    |             |             | 25km                                    |             |             | 67km                                    |             |             | 40km                                    |             |             |  |
| 11        | Depth of Intake/Discharge Point                           | 10 meter depth point                                   | 15           | 13km                                       | 0 0 3       | 8km   | 1 0 8       |             | 5km   | 11 3 11     |             | 9 km                                    | 0 0 7       |             | 3km                                     | 13 9 13     |             | 1km                                     | 15 15 15    |             | 4km                                     | 12 6 12     |             | Refer to Fig 5.2-2   |
| 12        | Ship route  | Ferry  | 4            | Care                                       | 3           | Care  | 3           |             | OK  | 4           |             | OK                                      | 4           |             | OK                                      | 4           |             | OK                                      | 4           |             | OK                                      | 4           |             | OK: P4, Care: P3   |
|           |   | Fishing boat   | 1            | Care                                       | 0           | Care  | 0           |             | Care  | 0           |             | Care                                    | 0           |             | OK                                      | 1           |             | Care                                    | 0           |             | OK                                      | 1           |             | OK: P1, Care: P0   |
| 13        | Seawater Quality  | TDS  | 2            |  | 2           |   | 2           |             | 2   |             | 2           |   | 2           |             | 2                                       |             | 2           |   | 2           |             | 2                                       |             | 2           |  |
|           |   | Contamination of industrial waste water, city sewerage | 6            | No Possibility? (Close to SFAX city area.) | 5           | No Possibility? (Close to SFAX city and industrial area.) | 4           |             | No Possibility? (Close to SFAX city and industrial area.) | 4           |             | No Possibility                          | 6           |             | No Possibility                          | 6           |             | No Possibility                          | 6           |             | No Possibility                          | 6           |             | Far from Big City : P6, Near Big City: P5, Near Big City & Industrial area: P4 |
|           |   | Sediment at seabed                                     | 2            | (Far from phosphorous industrial area.)    | 2           | (Far from phosphorous industrial area.)                   | 2           |             | (Close to phosphorous industrial area.)                   | 1           |             | (Far from phosphorous industrial area.) | 2           |             | (Far from phosphorous industrial area.) | 2           |             | (Far from phosphorous industrial area.) | 2           |             | (Far from phosphorous industrial area.) | 2           |             | Far: P2, Near: P1  |
| 1bis      | Possibility of Beach Well                                 |  | ?            |  |             | ?   |             |             | ?   |             |             | ?                                       |             |             | ?                                       |             |             | ?                                       |             |             | ?                                       |             |             |  |
| 21        | Land acquisition  | Desalination plant (Land ownership)                    | 8            | Public                                     | 8           | Public  | 8           |             | Public  | 8           |             | Public (to be confirmed)                | 7           |             | Public                                  | 8           |             | Public                                  | 8           |             | Public                                  | 8           |             | Public: P8, Public (to be confirmed): P7, Public/Private mix: P6, Private: P3  |
|           | Soil condition  | Height from sealevel (meter)                           | 2            | 1-2m                                       | 1           | 1-2m  | 1           |             | 1-2m  | 1           |             | 1-2m                                    | 1           |             | 1-2m                                    | 1           |             | 1-2m                                    | 1           |             | 1-2m                                    | 1           |             | 1-5m: P1, 5m<: P2  |
|           |   | Soil condition   | ?            |  |             | ?   |             |             | ?   |             |             | ?                                       |             |             | ?                                       |             |             | ?                                       |             |             | ?                                       |             |             |  |
| 31        | Energy  | Electricity supply                                     | 5            | 15km                                       | 4           | 7.5km   | 5           |             | 15.5km  | 3           |             | 32km                                    | 0           |             | 23km                                    | 2           |             | 27km                                    | 1           |             | 35.3km                                  | 0           |             | Refer to Fig 5.2-3   |
| 41        | Environment aspects                                       | Historical Remains                                     |              | Nothing                                    |             | Nothing   |             |             | Nothing   |             |             | Nothing                                 |             |             | Nothing                                 |             |             | Nothing                                 |             |             | Nothing                                 |             |             |  |
|           |   | Wood, Animal, Bird                                     |              | No impact                                  |             | No impact   |             |             | No impact   |             |             | No impact                               |             |             | No impact                               |             |             | No impact                               |             |             | No impact                               |             |             |  |
|           |   | Sea bed plant, Fish...                                 | 8            | Middle impact (Posidonia)                  | 4           | Middle impact (Posidonia)                                 | 4           |             | No impact   | 8           |             | Middle impact (Posidonia)               | 4           |             | Small impact (Posidonia)                | 6           |             | Small impact (Tuna)                     | 6           |             | No impact                               | 8           |             | No: P8, Small: P6, Middle: P4, Impact: P0                                      |
|           |   | Sediment pollution                                     |              | Small impact                               | 0           | Small impact  | 0           |             | Small-Middle impact                                       | ▲ 1         |             | Small impact                            | 0           |             | Small impact                            | 0           |             | Small impact                            | 0           |             | Small impact                            | 0           |             | Small: P0, Small-Medium: P(-1)   |
|           | Human aspects impact, during marine facility construction | Fishing industry                                       | 2            | Middle                                     | 1           | Middle  | 1           |             | Few   | 2           |             | Middle-Large                            | 1           |             | Few                                     | 2           |             | Middle                                  | 1           |             | Few                                     | 2           |             | OK: P2, If any suspicious: P1, Big problem: P0                                 |
|           |   | Tourism industry                                       |              | None                                       |             | None  |             |             | None  |             |             | None                                    |             |             | Few                                     |             |             | Few                                     |             |             | None                                    |             |             |  |
| 51        | Access to distribution system                             | Cost   | 8            | Middle                                     | 5           | Normal  | 8           |             | Normal  | 6           |             | High                                    | 0           |             | Middle                                  | 4           |             | High                                    | 0           |             | High                                    | 0           |             | Refer to Fig 5.2-4   |
|           |   | Obstacle, at Pipeline route                            | 2            |  | 2           |   | 2           |             |   | 2           |             |   | 2           |             |   | 2           |             |   | 2           |             |   | 2           |             | If nothing: P2, If serious: P0   |
| Sub Total | Case 1  | Full score   | 65           |  |             |   | 41          |             |   | 51          |             |   | 29          |             |   | 53          |             |   | 48          |             |   | 48          |             |  |
|           | Case 2  | Full score   | 65           |  | 37          |   |             | 40          |   |             | 43          |   |             | 29          |   |             | 49          |   |             | 48          |   |             | 42          |  |
|           | Case 3  | Full score   | 65           |  |             | 40  |             |             | 48  |             |             | 51                                      |             |             | 36                                      |             |             | 53                                      |             |             | 48                                      |             | 48          |  |

note: Figure in red is more than point 45.



Source: JICA Survey team

## (2) 2nd Evaluation

Site 3, 5, 6 and 7 which passed 1st evaluation are further studied from following costs viewpoints.

### a) Marine construction cost

- Intake quantity: 500,000m<sup>3</sup>/d
- Discharge quantity: 300,000m<sup>3</sup>/d
- Both pipelines will be laid in same line from land and separated at end of pipe. Intake and discharge tower will be installed at different point.

### b) Seawater Desalination plant

- Desalination process with RO membrane will be adopted.
- Product water: 200,000m<sup>3</sup>/d,
- Recovery: 40%

### c) Electric Receiving Equipment

- From STEG grid of 150KV
- Necessary electric power: 40MW capacity

### d) Product water transmission pipeline

- Transmission of 200,000m<sup>3</sup>/d water to existing 5 reservoirs
- Transmission route shall be decided by the discussion with SONEDE

### e) Transmission pump

- 200,000m<sup>3</sup>/d

### f) Transmission pump operation Cost

- Electric consumption cost for project life (20 years) is compared

Estimated cost for each sites are shown in Table 6. It should be noted that these cost is only for comparison among candidate site, and not based on detail specification, and may be changed after progress of Feasibility Study. Also should be noted that land acquisition and/or reclamation cost, Environment Impact Assessment fee, etc. Consultant service fee for the period of project implementation are not included.

**Table 6 Cost Comparison among Candidate Site**

| Candidate Site No.                       |                                | 3       | 5      | 6           | 7      |        |
|--|--------------------------------|---------|--------|-------------|--------|--------|
| Location Name                            |                                | Agareb  | Nakta  | Chebba Nord | Mahres |        |
| Governorates                             |                                | SFAX    | SFAX   | MAHDIA      | SFAX   |        |
| Distance from Center of SFAX (Straight)  |                                | 18 km   | 25 km  | 67 km       | 40 km  |        |
| Distance to 10m deep offshore point      |                                | 5 km    | 3 km   | 1 km        | 4 km   |        |
| CAPEX:<br>Construction Cost<br>(mio JPY) | Intake/Discharge               | Intake  | 6,500  | 3,000       | 1,000  | 4,800  |
|  |                                | Outfall | 4,000  | 2,000       | 600    | 3,000  |
|  | Desalination Plant             |         | 25,000 | 24,000      | 24,000 | 24,000 |
|  | Electricity Service Connection |         | 2,870  | 4,250       | 4,990  | 6,470  |
|  | Transmission Pump              |         | 1,050  | 1,070       | 1,080  | 1,070  |
|  | Pipeline                       |         | 5,510  | 7,030       | 13,330 | 8,980  |
| Sub Total                                |                                | 44,930  | 41,350 | 45,000      | 48,320 |        |
| ratio                                    |                                | 100%    | 92%    | 100%        | 108%   |        |

Source: JICA Survey Team

According to above cost comparison in Table 6, cost at site 5 is minimum and 93% of site 3. Site 6 and site 7 are 100% and 108% of site 3 respectively.

Further, electric consumption cost by transmission pump, which are different in each site due to the difference of transmission distance, are studied in the following assumption. This study in this section is only confirming whether the difference of initial project cost is reversed by 20 years operation cost or not, therefore, this operation cost is not converted to Net Present Value.

a) Operation period: 12 months /years

Desalination plant is expected to be operated at the peak demand only, and not in 100%, which means transmission pump is not operated in 100% for whole year. But in this study, 100% operation is assumed.

b) Project life: 20 years for study, which is generally used in feasibility studies

Result is shown in Table 7. From this result, the difference in initial construction cost is not reversed by the electric consumption cost.

**Table 7 Initial Construction Cost and Electric Consumption Cost for Transmission Pump**

| Candidate Site No.                                     | 3      | 5      | 6      | 7      |
|--|--------|--------|--------|--------|
| CAPEX (Plant construction cost)                        | 44,930 | 41,350 | 45,000 | 48,320 |
| Pump Electric cost x 12months/year x 20years (mio JYE) | 4,300  | 4,570  | 5,530  | 4,940  |
| CAPEX + Electric cost for transmission pump            | 49,230 | 45,920 | 50,530 | 53,260 |
| ratio  | 100%   | 93%    | 103%   | 108%   |

Source: JICA Survey team

Evaluation results for four (4) candidate sites are summarized as per Table 8.

**Table 8 Evaluation Result**

| Candidate Site No.                      | 3         | 5         | 6           | 7         |
|---|-----------|-----------|-------------|-----------|
| Location Name                           | Agareb    | Nakta     | Chebba Nord | Mahres    |
| Governorates                            | SFAX      | SFAX      | MAHDIA      | SFAX      |
| Distance from Center of SFAX (Straight) | 18 km     | 25 km     | 67 km       | 40 km     |
| Distance to 10m deep offshore point     | 5 km      | 3 km      | 1 km        | 4 km      |
| Land Ownership                          | Public    | Public    | Public      | Public    |
| Height above Sea Level                  | around 2m | around 2m | around 2m   | around 2m |
| Construction Cost (in %)                | 100%      | 92%       | 100%        | 108%      |
| Total Evaluation Rank                   | 2         | 1         | 3           | 4         |

Source: JICA Survey team

From above Table 8, it is concluded that;

- 1) Site #5 is the best candidate site.
- 2) From costing view point, #3 and #6 follow #5.
- 3) Due that land owner for #6 is not yet confirmed, and also belong to Mahdia governorate, the JICA Survey Team recommends #3 as 2nd best candidate site

Since sites #3 and #5 are located in the "Public Maritime Domain", approval of APAL is necessary for development in those area.

### (3) Conclusion

During Phase I of the Survey, the conclusion stated in above (2) was obtained without consultation with related authorities because implementation of the project was not yet decided. As a result of Phase 1 Survey, necessity of the project was confirmed, consequently several examinations about #3 and #5 were conducted with related authorities at the beginning of Phase 2 of the Survey.


APAL expressed their opinion that Site #5 cannot be approved because of frangibility of coastal features. While, APAL approved Site # 3 for development. After that, the area located south of initial site # 3 was indicated for use (refer to Figure 8). The JICA survey team started the study based on the site shown on Figure 8 as the project site. Official approval of APAL for use of the site will be provided upon approval of EIA by ANPE.






Source : APAL/SONEDE/JICA Survey Team

**Figure 8 Site approved by APAL**




| ID               | Location    | Latitude     | Longitude     |
|------------------|-------------|--------------|---------------|
| Site 4           | Chebba Sud  | N:35.189466  | E:011.097065  |
| Site 6           | Chebba Nord | N:35.258148  | E:011.112843  |
| Sampling Point 1 | -           | N:35.2648413 | E:011.1184828 |

**Annexed Figure 1 Sea Water Desalination Plants Candidate Site and Sampling Points (1)**




| ID               | Location     | Latitude      | Longitude      |
|------------------|--------------|---------------|----------------|
| Site 1           | El Amra Nord | N: 34.921381  | E: 010.921379  |
| Site 2           | El Amra Sud  | N: 34.847586  | E: 010.885692  |
| Sampling Point 2 | -            | N: 34.8085109 | E: 010.9516900 |

Annexed Figure 2 Sea Water Desalination Plants Candidate Site and Sampling Points (2)




| ID               | Location | Latitude     | Longitude     |
|------------------|----------|--------------|---------------|
| Site 3           | Agareb   | N: 34.617982 | E: 010.624981 |
| Sampling Point 3 | -        | N:34.5836229 | E:010.6553259 |

Annexed Figure 3 Sea Water Desalination Plants Candidate Site and Sampling Points (3)




**Annexed Figure 4 Seawater Desalination Plants Candidate Site and Sampling Points (4)**



— Pipeline Route from Site 1 and Site 2

P1 Pumping Station

Annexed Figure 5 Transmission Pipeline Route from Respective Site by Case (1)



— Pipeline Route for Site 3, 5 and 7 (Case 1)  
P1 Pumping Station

Annexed Figure 6 Transmission Pipeline Route from Respective Site by Case (2)



- Pipeline Route for Sites 3, 5 and 7 (Case 2)
- P1 Pumping Station

**Annexed Figure 7 Transmission Pipeline Route from Respective Site by Case (3)**





— Pipekine Route for Site 4 and 6 (Case 1)  
P1 Pumping Station

Annexed Figure 8 Transmission Pipeline Route from Respective Site by Case (4)



— Pipeline Route for Site 4 and 6 (Case 2)  
P1 Pumping Station

**Annexed Figure 9 Transmission Pipeline Route from Respective Site by Case (5)**

**Annexed Table 1 Rough Cost Estimates of Transmission Pipeline from Respective Site by Case**


| <b>Pumpig Stations &amp; Pipeline for Each Site (1)</b> |        |        |      |                   |      |     |       |           |       |         |                |              |           |                       |
|---|--------|--------|------|-------------------|------|-----|-------|-----------|-------|---------|----------------|--------------|-----------|-----------------------|
| <b>Site 1</b>   |        |        |      |                   |      |     |       |           |       |         |                |              |           |                       |
|   |        | km     | mm   | m <sup>3</sup> /d | m/s  | H-W | 0/00  | m         |       | TND/m   | 1000TND        |              | Elevation | Q (m <sup>3</sup> /d) |
|   | P. St. | Length | Dia. | Q                 | V    | C   | Grade | Head Loss |       | Unit C. | Amount         |              |           |                       |
| Site – Main Road  | 1      | 9.0    | 1600 | 200,000           | 1.15 | 136 | 0.58  | 5.19      |       | 2,721   | 24,489         | Sidi Salah H | 79m       | 16,000                |
| Main R.   |        | 17.8   | 1600 | 200,000           | 1.15 | 136 | 0.58  | 10.27     |       | 2,721   | 48,434         | Sidi Salah B | 59m       | 37,000                |
| Main R. – S. Salah B                                    |        | 4.0    | 800  | 53,000            | 1.22 | 136 | 1.45  | 5.79      | 21.25 | 879     | 3,516          | PK14         | 79m       | 32,000                |
| S. Salah B – S. Salah H                                 | 2      | 2.3    | 500  | 16,000            | 0.94 | 136 | 1.56  | 3.58      | 3.58  | 429     | 987            | PK10         | 58m       | 55,000                |
| Mai. R.   |        | 7.8    | 1400 | 147,000           | 1.11 | 136 | 0.63  | 4.88      |       | 2,193   | 17,105         | Bou Merra    | 84m       | 16,000                |
| Mai R. – PK10   |        | 0.1    | 1000 | 87,000            | 1.28 | 136 | 1.22  | 0.12      | 20.47 | 1,229   | 123            | PK11         | 59m       | 44,000                |
| PK10 – PK14   | 3      | 4.3    | 800  | 32,000            | 0.74 | 136 | 0.57  | 2.45      | 2.45  | 879     | 3,780          |              |           | 200,000               |
| Mai. R.   |        | 4.5    | 1000 | 60,000            | 0.88 | 136 | 0.61  | 2.76      |       | 1,229   | 5,531          | Pump St.1    | 200,000   | 83m                   |
| Mai R. – PK11   |        | 1.2    | 1000 | 60,000            | 0.88 | 136 | 0.61  | 0.74      | 23.84 | 1,229   | 1,475          | Pump St.2    | 16,000    | 29m                   |
| PK11 – Bou Merra  | 4      | 3.0    | 500  | 16,000            | 0.94 | 136 | 1.56  | 4.67      | 4.67  | 429     | 1,287          | Pump St.3    | 32,000    | 29m                   |
|   |        | 54.0   |      |                   |      |     |       |           |       |         | <b>106,726</b> | Pump St.4    | 16,000    | 35m                   |
| <b>Site 2</b>   |        |        |      |                   |      |     |       |           |       |         |                |              |           |                       |
|   | P. St. | Length | Dia. | Q                 | V    | C   | Grade | Head Loss |       | Unit C. | Amount         |              | Elevation | Q (m <sup>3</sup> /d) |
| Site – Main Road  | 1      | 5.8    | 1600 | 200,000           | 1.15 | 136 | 0.58  | 3.35      |       | 2,721   | 15,782         | Sidi Salah H | 79m       | 16,000                |
| Main R.   |        | 9.3    | 1600 | 200,000           | 1.15 | 136 | 0.58  | 5.37      |       | 2,721   | 25,305         | Sidi Salah B | 59m       | 37,000                |
| Main R. – S. Salah B                                    |        | 4.0    | 800  | 53,000            | 1.22 | 136 | 1.45  | 5.79      | 14.50 | 879     | 3,516          | PK14         | 79m       | 32,000                |
| S. Salah B – S. Salah H                                 | 2      | 2.3    | 500  | 16,000            | 0.94 | 136 | 1.56  | 3.58      | 3.58  | 429     | 987            | PK10         | 58m       | 55,000                |
| Mai. R.   |        | 7.8    | 1400 | 147,000           | 1.11 | 136 | 0.63  | 4.88      |       | 2,193   | 17,105         | Bou Merra    | 84m       | 16,000                |
| Mai R. – PK10   |        | 0.1    | 1000 | 87,000            | 1.28 | 136 | 1.22  | 0.12      | 13.72 | 1,229   | 123            | PK11         | 59m       | 44,000                |
| PK10 – PK14   | 3      | 4.3    | 800  | 32,000            | 0.74 | 136 | 0.57  | 2.45      | 2.45  | 879     | 3,780          |              |           | 200,000               |
| Mai. R.   |        | 4.5    | 1000 | 60,000            | 0.88 | 136 | 0.61  | 2.76      |       | 1,229   | 5,531          | Pump St.1    | 200,000   | 77m                   |
| Mai R. – PK11   |        | 1.2    | 1000 | 60,000            | 0.88 | 136 | 0.61  | 0.74      | 17.09 | 1,229   | 1,475          | Pump St.2    | 16,000    | 29m                   |
| PK11 – Bou Merra  | 4      | 3.0    | 500  | 16,000            | 0.94 | 136 | 1.56  | 4.67      | 4.67  | 429     | 1,287          | Pump St.3    | 32,000    | 29m                   |
|   |        | 42.3   |      |                   |      |     |       |           |       |         | <b>74,890</b>  | Pump St.4    | 16,000    | 35m                   |
| <b>Site 3 Case 1</b>                                    |        |        |      |                   |      |     |       |           |       |         |                |              |           |                       |
|   | P. St. | Length | Dia. | Q                 | V    | C   | Grade | Head Loss |       | Unit C. | Amount         |              | Elevation | Q (m <sup>3</sup> /d) |
| Site – Main Road  | 1      | 0.0    | 1600 | 200,000           | 1.15 | 136 | -     | 0.00      |       | 2,721   | 0              | Sidi Salah H | 79m       | 16,000                |
| Main R.   |        | 21.6   | 1600 | 200,000           | 1.15 | 136 | 0.58  | 12.45     |       | 2,721   | 58,692         | Sidi Salah B | 59m       | 37,000                |
| Main R. – PK11  |        | 1.2    | 800  | 60,000            | 1.38 | 136 | 1.82  | 2.18      | 14.63 | 879     | 1,055          | PK14         | 79m       | 32,000                |
| PK11 – Bou Merra  | 2      | 3.0    | 500  | 16,000            | 0.94 | 136 | 1.56  | 4.67      | 4.67  | 429     | 1,287          | PK10         | 58m       | 55,000                |
| Main R.   |        | 4.5    | 1400 | 147,000           | 1.11 | 136 | 0.63  | 2.82      |       | 2,193   | 9,869          | Bou Merra    | 84m       | 16,000                |
| Main R. – PK10  |        | 0.1    | 1000 | 87,000            | 1.28 | 136 | 1.22  | 0.12      | 15.39 | 1,229   | 123            | PK11         | 59m       | 44,000                |
| PK10 – PK14   | 3      | 4.3    | 800  | 32,000            | 0.74 | 136 | 0.57  | 2.45      | 2.45  | 879     | 3,780          |              |           | 200,000               |
| Mai. R.   |        | 7.8    | 1000 | 53,000            | 0.78 | 136 | 0.49  | 3.81      |       | 1,229   | 9,586          | Pump St.1    | 200,000   | 80m                   |
| Main R. – S. Salah B                                    |        | 4.0    | 1000 | 53,000            | 0.78 | 136 | 0.49  | 1.95      | 21.02 | 1,229   | 4,916          | Pump St.2    | 16,000    | 35m                   |
| S. Salah B – S. Salah H                                 | 4      | 2.3    | 500  | 16,000            | 0.94 | 136 | 1.56  | 3.58      | 3.58  | 429     | 987            | Pump St.3    | 32,000    | 29m                   |
|   |        | 48.8   |      |                   |      |     |       |           |       |         | <b>90,294</b>  | Pump St.4    | 16,000    | 29m                   |

| Pumpig Stations & Pipeline for Each Site (2) |        |        |      |                   |      |     |       |           |       |         |         |              |                       |  |
|--|--------|--------|------|-------------------|------|-----|-------|-----------|-------|---------|---------|--------------|-----------------------|--|
| Site 3 Case 2                                |        |        |      |                   |      |     |       |           |       |         |         |              |                       |  |
|  |        | km     | mm   | m <sup>3</sup> /d | m/s  | H-W | 0/00  | m         |       | TND/m   | 1000TND |              |                       |  |
|  | P. St. | Length | Dia. | Q                 | V    | C   | Grade | Head Loss |       | Unit C. | Amount  | Elevation    | Q (m <sup>3</sup> /d) |  |
| Site - Main Road                             | 1      | 0.0    | 1600 | 200,000           | 1.15 | 136 | -     | 0.00      |       | 2,721   | 0       | Sidi Salah H | 79m                   | 16,000   |
| Main R.                                      |        | 21.6   | 1600 | 200,000           | 1.15 | 136 | 0.58  | 12.45     |       | 2,721   | 58,692  | Sidi Salah B |                       | 37,000   |
| Main R. - PK11                               |        | 1.2    | 1600 | 200,000           | 1.15 | 136 | 0.58  | 0.69      | 13.14 | 2,721   | 3,265   | PK14         | 79m                   | 32,000   |
| PK11 - Bou Merra                             | 2      | 3.0    | 1400 | 156,000           | 1.17 | 137 | 0.69  | 2.07      |       | 2,193   | 6,579   | PK10         |                       | 55,000   |
| Bou Merra - PK14 jct                         |        | 6.2    | 1400 | 140,000           | 1.05 | 138 | 0.56  | 3.45      |       | 2,193   | 13,597  | Bou Merra    | 84m                   | 16,000   |
| PK14 jct - PK14                              |        | 0.5    | 1000 | 87,000            | 1.28 | 139 | 1.17  | 0.59      |       | 1,229   | 615     | PK11         | 59m                   | 44,000   |
| PK14 jct - Sidi Salah Hault                  |        | 9.9    | 1000 | 53,000            | 0.78 | 136 | 0.49  | 4.83      | 10.35 | 1,229   | 12,167  |              |                       | 200,000  |
|  |        | 42.4   |      |                   |      |     |       |           |       |         | 94,914  | Pump St.1    | 200,000               | 73m  |
|  |        |        |      |                   |      |     |       |           |       |         |         | Pump St.2    | 156,000               | 36m  |
| Site 4 Case 1                                |        |        |      |                   |      |     |       |           |       |         |         |              |                       |  |
|  |        | km     | mm   | m <sup>3</sup> /d | m/s  | H-W | 0/00  | m         |       | TND/m   | 1000TND |              |                       |  |
|  | P. St. | Length | Dia. | Q                 | V    | C   | Grade | Head Loss |       | Unit C. | Amount  | Elevation    | Q (m <sup>3</sup> /d) |  |
| Site - Main R.1                              | 1      | 1.0    | 1600 | 200,000           | 1.15 | 136 | 0.58  | 0.58      |       | 2,721   | 2,721   | Mahrouga     | 132m                  | 200,000  |
| Main R.1                                     |        | 5.7    | 1600 | 200,000           | 1.15 | 136 | 0.58  | 3.29      |       | 2,721   | 15,510  | Sidi Salah H | 79m                   | 16,000   |
| Main R.2                                     |        | 24.7   | 1600 | 200,000           | 1.15 | 136 | 0.58  | 14.25     |       | 2,721   | 67,209  | PK14         | 79m                   | 32,000   |
| Main R.3 Jebeniana (40m)                     |        | 1.0    | 1600 | 200,000           | 1.15 | 136 | 0.58  | 0.58      | 18.70 | 2,721   | 2,721   | Bou Merra    | 84m                   | 16,000   |
| Jebeniana Mahrouga (132m)                    |        | 14.5   | 1600 | 200,000           | 1.15 | 137 | 0.57  | 8.26      | 8.26  | 2,721   | 39,455  |              |                       | 264,000  |
| Mahrouga - S.Salah H                         |        | 13.5   | 1000 | 103,300           | 1.52 | 136 | 1.68  | 22.64     | 22.64 | 1,229   | 16,592  |              | Q (m <sup>3</sup> /d) | Head   |
| S.Salah H - S.Salah B                        |        | 2.3    | 500  | 35,000            | 2.06 | 137 | 6.53  | 15.02     | 37.66 | 429     | 987     | Pump St.1    | 200,000               | 160  |
| S.Salah H - PK14 jct                         |        | 9.9    | 1000 | 74,700            | 1.10 | 138 | 0.90  | 8.87      |       | 1,229   | 12,167  |              |                       |  |
| PK14 jct - PK14                              |        | 0.2    | 500  | 44,000            | 2.59 | 139 | 9.71  | 1.94      | 33.45 | 429     | 86      |              |                       |  |
| PK14 jct - Bou Merra                         |        | 6.2    | 1000 | 61,300            | 0.90 | 140 | 0.61  | 3.75      | 35.26 | 1,229   | 7,620   |              |                       |  |
|  |        | 79.0   |      |                   |      |     |       |           |       |         | 165,066 |              |                       |  |
|  |        |        |      |                   |      |     |       |           |       |         |         |              |                       | This is not recommendable because 15km long land acquisition for pipeline installation is needed, and very high pump head. |
| Site 4 Case 2                                |        |        |      |                   |      |     |       |           |       |         |         |              |                       |  |
|  |        | km     | mm   | m <sup>3</sup> /d | m/s  | H-W | 0/00  | m         |       | TND/m   | 1000TND |              |                       |  |
|  | P. St. | Length | Dia. | Q                 | V    | C   | Grade | Head Loss |       | Unit C. | Amount  | Elevation    | Q (m <sup>3</sup> /d) |  |
| Site - Main R.1                              | 1      | 1.0    | 1600 | 200,000           | 1.15 | 136 | 0.58  | 0.58      |       | 2,721   | 2,721   | Sidi Salah H | 79m                   | 16,000   |
| Main R.1                                     |        | 5.7    | 1600 | 200,000           | 1.15 | 136 | 0.58  | 3.29      |       | 2,721   | 15,510  | Sidi Salah B | 59m                   | 37,000   |
| Main R.2                                     |        | 24.7   | 1600 | 200,000           | 1.15 | 136 | 0.58  | 14.25     |       | 2,721   | 67,209  | PK14         | 79m                   | 32,000   |
| Main R.3                                     |        | 22.2   | 1600 | 200,000           | 1.15 | 136 | 0.58  | 12.81     |       | 2,721   | 60,406  | PK10         | 58m                   | 55,000   |
| Main R.4                                     |        | 7.1    | 1600 | 200,000           | 1.15 | 136 | 0.58  | 4.10      |       | 2,721   | 19,319  | Bou Merra    | 84m                   | 16,000   |
| Main R. - S. Salah B                         |        | 4.0    | 800  | 53,000            | 1.22 | 136 | 1.45  | 5.79      | 40.81 | 879     | 3,516   | PK11         | 59m                   | 44,000   |
| S. Salah B - S. Salah H                      | 2      | 2.3    | 500  | 16,000            | 0.94 | 136 | 1.56  | 3.58      | 3.58  | 429     | 987     |              |                       | 200,000  |
| Mai. R.                                      |        | 7.8    | 1400 | 147,000           | 1.11 | 136 | 0.63  | 4.88      |       | 2,193   | 17,105  |              | Q (m <sup>3</sup> /d) | Head   |
| Mai R. - PK10                                |        | 0.1    | 1000 | 87,000            | 1.28 | 136 | 1.22  | 0.12      | 40.03 | 1,229   | 123     | Pump St.1    | 200,000               | 103m   |
| PK10 - PK14                                  | 3      | 4.3    | 800  | 32,000            | 0.74 | 136 | 0.57  | 2.45      | 2.45  | 879     | 3,780   | Pump St.2    | 16,000                | 29m  |
| Mai. R.                                      |        | 4.5    | 1000 | 60,000            | 0.88 | 136 | 0.61  | 2.76      |       | 1,229   | 5,531   | Pump St.3    | 32,000                | 29m  |
| Mai R. - PK11                                |        | 1.2    | 1000 | 60,000            | 0.88 | 136 | 0.61  | 0.74      | 43.41 | 1,229   | 1,475   | Pump St.4    | 16,000                | 35m  |
| PK11 - Bou Merra                             | 4      | 3.0    | 500  | 16,000            | 0.94 | 136 | 1.56  | 4.67      | 4.67  | 429     | 1,287   |              |                       |  |
|  |        | 87.9   |      |                   |      |     |       |           |       |         | 198,968 |              |                       |  |

| Pumpig Stations & Pipeline for Each Site (3) |        |        |      |         |      |     |       |           |         |         |                                       |          |         |
|--|--------|--------|------|---------|------|-----|-------|-----------|---------|---------|---------------------------------------|----------|---------|
| Site 5 Case 1                                |        |        |      |         |      |     |       |           |         |         |                                       |          |         |
|  | P. St. | Length | Dia. | Q       | V    | C   | Grade | Head Loss | Unit C. | Amount  | Elevation                             | Q (m3/d) |         |
| Site - Main Road                             | 1      | 3.1    | 1600 | 200,000 | 1.15 | 136 | 0.58  | 1.79      | 2,721   | 8,435   | Sidi Salah H                          | 79m      | 16,000  |
| Main R.                                      |        | 27.7   | 1600 | 200,000 | 1.15 | 136 | 0.58  | 15.97     | 2,721   | 75,290  | Sidi Salah B                          | 59m      | 37,000  |
| Main R - PK11                                |        | 1.2    | 800  | 60,000  | 1.38 | 136 | 1.82  | 2.18      | 19.94   | 879     | PK14                                  | 79m      | 32,000  |
| PK11 - Bou Merra                             | 2      | 3.0    | 500  | 16,000  | 0.94 | 136 | 1.56  | 4.67      | 4.67    | 429     | PK10                                  | 58m      | 55,000  |
| Main R.                                      |        | 4.5    | 1400 | 147,000 | 1.11 | 136 | 0.63  | 2.82      |         | 2,193   | Bou Merra                             | 84m      | 16,000  |
| Main R - PK10                                |        | 0.1    | 1000 | 87,000  | 1.28 | 136 | 1.22  | 0.12      | 20.69   | 1,229   | PK11                                  | 59m      | 44,000  |
| PK10 - PK14                                  | 3      | 4.3    | 800  | 32,000  | 0.74 | 136 | 0.57  | 2.45      | 2.45    | 879     |                                       |          | 200,000 |
| Mai. R.                                      |        | 7.8    | 1000 | 53,000  | 0.78 | 136 | 0.49  | 3.81      |         | 1,229   | Pump St.1                             | 200,000  | 86m     |
| Main R - S. Salah B                          |        | 4.0    | 1000 | 53,000  | 0.78 | 136 | 0.49  | 1.95      | 26.33   | 1,229   | Pump St.2                             | 16,000   | 35m     |
| S. Salah B - S. Salah H                      | 4      | 2.3    | 500  | 16,000  | 0.94 | 136 | 1.56  | 3.58      | 3.58    | 429     | Pump St.3                             | 32,000   | 29m     |
|  |        | 58.0   |      |         |      |     |       |           |         | 115,327 | Pump St.4                             | 16,000   | 29m     |
| Site 5 Case 2                                |        |        |      |         |      |     |       |           |         |         |                                       |          |         |
|  | P. St. | Length | Dia. | Q       | V    | C   | Grade | Head Loss | Unit C. | Amount  | Elevation                             | Q (m3/d) |         |
| Site - Main Road                             | 1      | 3.1    | 1600 | 200,000 | 1.15 | 136 | 0.58  | 1.79      | 2,721   | 8,435   | Sidi Salah H                          | 79m      | 16,000  |
| Main R.                                      |        | 27.7   | 1600 | 200,000 | 1.15 | 136 | 0.58  | 15.97     |         | 2,721   | Sidi Salah B                          |          | 37,000  |
| Main R - PK11                                |        | 1.2    | 1600 | 200,000 | 1.15 | 136 | 0.58  | 0.69      | 18.45   | 2,721   | PK14                                  | 79m      | 32,000  |
| PK11 - Bou Merra                             | 2      | 3.0    | 1400 | 156,000 | 1.17 | 137 | 0.69  | 2.07      |         | 2,193   | PK10                                  |          | 55,000  |
| Bou Merra - PK14 jct                         |        | 6.2    | 1400 | 140,000 | 1.05 | 138 | 0.56  | 3.45      |         | 2,193   | Bou Merra                             | 84m      | 16,000  |
| PK14 jct - PK14                              |        | 0.5    | 1000 | 87,000  | 1.28 | 139 | 1.17  | 0.59      |         | 1,229   | PK11                                  | 59m      | 44,000  |
| PK14 jct - Sidi Salah Hault                  |        | 9.9    | 1000 | 53,000  | 0.78 | 136 | 0.49  | 4.83      | 10.35   | 1,229   |                                       |          | 200,000 |
|  |        | 51.6   |      |         |      |     |       |           |         | 119,948 | Pump St.1                             | 200,000  | 78m     |
|  |        |        |      |         |      |     |       |           |         |         | Pump St.2                             | 156,000  | 36m     |
| Site 6 Case 1                                |        |        |      |         |      |     |       |           |         |         |                                       |          |         |
|  | P. St. | Length | Dia. | Q       | V    | C   | Grade | Head Loss | Unit C. | Amount  | Elevation                             | Q (m3/d) |         |
| Site - Main R.1                              | 1      | 8.2    | 1600 | 200,000 | 1.15 | 136 | 0.58  | 4.73      |         | 2,721   | Mahrouga                              | 132m     | 200,000 |
| Main R.1                                     |        | 5.7    | 1600 | 200,000 | 1.15 | 136 | 0.58  | 3.29      |         | 2,721   | Sidi Salah H                          | 79m      | 16,000  |
| Main R2                                      |        | 24.7   | 1600 | 200,000 | 1.15 | 136 | 0.58  | 14.25     |         | 2,721   | PK14                                  | 79m      | 32,000  |
| Main R3 Jebeniana (40m)                      |        | 1.0    | 1600 | 200,000 | 1.15 | 136 | 0.58  | 0.58      | 22.85   | 2,721   | Bou Merra                             | 84m      | 16,000  |
| Jebeniana Mahrouga (132m)                    |        | 14.5   | 1600 | 200,000 | 1.15 | 137 | 0.57  | 8.26      | 8.26    | 2,721   |                                       |          | 264,000 |
| Mahrouga - S.Salah H                         |        | 13.5   | 1000 | 103,300 | 1.52 | 136 | 1.68  | 22.64     | 22.64   | 1,229   |                                       | Q (m3/d) | Head    |
| S.Salah H - S.Salah B                        |        | 2.3    | 500  | 35,000  | 2.06 | 137 | 6.53  | 15.02     | 37.66   | 429     | Pump St.1                             | 200,000  | 160m    |
| S.Salah H - PK14 jct                         |        | 9.9    | 1000 | 74,700  | 1.10 | 138 | 0.90  | 8.87      |         | 1,229   | This is not recommendable because     |          |         |
| PK14 jct - PK14                              |        | 0.2    | 500  | 44,000  | 2.59 | 139 | 9.71  | 1.94      | 33.45   | 429     | 15km of land acquisition for pipeline |          |         |
| PK14 jct - Bou Merra                         |        | 6.2    | 1000 | 61,300  | 0.90 | 140 | 0.61  | 3.75      | 35.26   | 1,229   | inst. is needed, and very high head.  |          |         |
|  |        | 86.2   |      |         |      |     |       |           |         | 184,657 |                                       |          |         |





| Pumpig Stations & Pipeline for Each Site (4) |        |      |      |                   |      |       |           |         |        |         |                |           |                            |        |
|--|--------|------|------|-------------------|------|-------|-----------|---------|--------|---------|----------------|-----------|----------------------------|--------|
| Site 6 Case 2                                |        | km   | mm   | m <sup>3</sup> /d | m/s  | H-W   | 0/00      | m       | TND/m  | 1000TND |                | Elevation | Q (m <sup>3</sup> /d)      |        |
| P. St.                                       | Length | Dia. | Q    | V                 | C    | Grade | Head Loss | Unit C. | Amount |         |                |           |                            |        |
| Site - Main R.1                              | 1      | 8.2  | 1600 | 200,000           | 1.15 | 136   | 0.58      | 4.73    | 2,721  | 22,312  | Sidi Salah H   | 79m       | 16,000                     |        |
| Main R.1                                     |        | 5.7  | 1600 | 200,000           | 1.15 | 136   | 0.58      | 3.29    | 2,721  | 15,510  | Sidi Salah B   | 59m       | 37,000                     |        |
| Main R2                                      |        | 24.7 | 1600 | 200,000           | 1.15 | 136   | 0.58      | 14.25   | 2,721  | 67,209  | PK14           | 79m       | 32,000                     |        |
| Main R3                                      |        | 22.2 | 1600 | 200,000           | 1.15 | 136   | 0.58      | 12.81   | 2,721  | 60,406  | PK10           | 58m       | 55,000                     |        |
| Main R4                                      |        | 7.1  | 1600 | 200,000           | 1.15 | 136   | 0.58      | 4.10    | 2,721  | 19,319  | Bou Merra      | 84m       | 16,000                     |        |
| Main R. - S. Salah B                         |        | 4.0  | 800  | 53,000            | 1.22 | 136   | 1.45      | 5.79    | 44.97  | 879     | 3,516          | PK11      | 59m                        | 44,000 |
| S. Salah B - S. Salah H                      | 2      | 2.3  | 500  | 16,000            | 0.94 | 136   | 1.56      | 3.58    | 3.58   | 429     | 987            |           | 200,000                    |        |
| Mai. R.                                      |        | 7.8  | 1400 | 147,000           | 1.11 | 136   | 0.63      | 4.88    |        | 2,193   | 17,105         |           | Q (m <sup>3</sup> /d) Head |        |
| Mai R. - PK10                                |        | 0.1  | 1000 | 87,000            | 1.28 | 136   | 1.22      | 0.12    | 44.19  | 1,229   | 123            | Pump St.1 | 200,000                    | 107m   |
| PK10 - PK14                                  | 3      | 4.3  | 800  | 32,000            | 0.74 | 136   | 0.57      | 2.45    | 2.45   | 879     | 3,780          | Pump St.2 | 16,000                     | 29m    |
| Mai. R.                                      |        | 4.5  | 1000 | 60,000            | 0.88 | 136   | 0.61      | 2.76    |        | 1,229   | 5,531          | Pump St.3 | 32,000                     | 29m    |
| Mai R. - PK11                                |        | 1.2  | 1000 | 60,000            | 0.88 | 136   | 0.61      | 0.74    | 47.56  | 1,229   | 1,475          | Pump St.4 | 16,000                     | 35m    |
| PK11 - Bou Merra                             | 4      | 3.0  | 500  | 16,000            | 0.94 | 136   | 1.56      | 4.67    | 4.67   | 429     | 1,287          |           |                            |        |
|  |        | 95.1 |      |                   |      |       |           |         |        |         | <b>218,559</b> |           |                            |        |
| Site 7 Case 1                                |        | km   | mm   | m <sup>3</sup> /d | m/s  | H-W   | 0/00      | m       | TND/m  | 1000TND |                | Elevation | Q (m <sup>3</sup> /d)      |        |
| P. St.                                       | Length | Dia. | Q    | V                 | C    | Grade | Head Loss | Unit C. | Amount |         |                |           |                            |        |
| Site - Main Road                             | 1      | 0.0  | 1600 | 200,000           | 1.15 | 136   | 0.00      | 0.00    | 2,721  | 0       | Sidi Salah H   | 79m       | 16,000                     |        |
| Main R.                                      |        | 42.5 | 1600 | 200,000           | 1.15 | 136   | 0.58      | 24.51   | 2,721  | 115,561 | Sidi Salah B   | 59m       | 37,000                     |        |
| Main R. - PK11                               |        | 1.2  | 800  | 60,000            | 1.38 | 136   | 1.82      | 2.18    | 26.69  | 879     | 1,055          | PK14      | 79m                        | 32,000 |
| PK11 - Bou Merra                             | 2      | 3.0  | 500  | 16,000            | 0.94 | 136   | 1.56      | 4.67    | 4.67   | 429     | 1,287          | PK10      | 58m                        | 55,000 |
| Main R.                                      |        | 4.5  | 1400 | 147,000           | 1.11 | 136   | 0.63      | 2.82    |        | 2,193   | 9,869          | Bou Merra | 84m                        | 16,000 |
| Main R. - PK10                               |        | 0.1  | 1000 | 87,000            | 1.28 | 136   | 1.22      | 0.12    | 27.45  | 1,229   | 123            | PK11      | 59m                        | 44,000 |
| PK10 - PK14                                  | 3      | 4.3  | 800  | 32,000            | 0.74 | 136   | 0.57      | 2.45    | 2.45   | 879     | 3,780          |           | 200,000                    |        |
| Mai. R.                                      |        | 7.8  | 1000 | 53,000            | 0.78 | 136   | 0.49      | 3.81    |        | 1,229   | 9,586          | Pump St.1 | 200,000                    | 86m    |
| Main R. - S. Salah B                         |        | 4.0  | 1000 | 53,000            | 0.78 | 136   | 0.49      | 1.95    | 33.08  | 1,229   | 4,916          | Pump St.2 | 16,000                     | 35m    |
| S. Salah B - S. Salah H                      | 4      | 2.3  | 500  | 16,000            | 0.94 | 136   | 1.56      | 3.58    | 3.58   | 429     | 987            | Pump St.3 | 32,000                     | 29m    |
|  |        | 69.7 |      |                   |      |       |           |         |        |         | <b>147,163</b> | Pump St.4 | 16,000                     | 29m    |
| Site 7 Case 2                                |        | km   | mm   | m <sup>3</sup> /d | m/s  | H-W   | 0/00      | m       | TND/m  | 1000TND |                | Elevation | Q (m <sup>3</sup> /d)      |        |
| P. St.                                       | Length | Dia. | Q    | V                 | C    | Grade | Head Loss | Unit C. | Amount |         |                |           |                            |        |
| Site - Main Road                             | 1      | 0.0  | 1600 | 200,000           | 1.15 | 136   | 0.00      | 0.00    | 2,721  | 0       | Sidi Salah H   | 79m       | 16,000                     |        |
| Main R.                                      |        | 42.5 | 1600 | 200,000           | 1.15 | 136   | 0.58      | 24.51   | 2,721  | 115,561 | Sidi Salah B   |           | 37,000                     |        |
| Main R. - PK11                               |        | 1.2  | 1600 | 200,000           | 1.15 | 136   | 0.58      | 0.69    | 25.20  | 2,721   | 3,265          | PK14      | 79m                        | 32,000 |
| PK11 - Bou Merra                             | 2      | 3.0  | 1400 | 156,000           | 1.17 | 137   | 0.69      | 2.07    | 2,193  | 6,579   | PK10           |           | 55,000                     |        |
| Bou Merra - PK14 jct                         |        | 6.2  | 1400 | 140,000           | 1.05 | 138   | 0.56      | 3.45    | 2,193  | 13,597  | Bou Merra      | 84m       | 16,000                     |        |
| PK14 jct - PK14                              |        | 0.5  | 1000 | 87,000            | 1.28 | 139   | 1.17      | 0.59    |        | 1,229   | 615            | PK11      | 59m                        | 44,000 |
| PK14 jct - Sidi Salah Hault                  |        | 9.9  | 1000 | 53,000            | 0.78 | 136   | 0.49      | 4.83    | 10.35  | 1,229   | 12,167         |           | 200,000                    |        |
|  |        | 63.3 |      |                   |      |       |           |         |        |         | 151,783        | Pump St.1 | 200,000                    | 85m    |
|  |        |      |      |                   |      |       |           |         |        |         |                | Pump St.2 | 156,000                    | 36m    |

### 5.3-1 Geotechnical Investigation in Seabed



Source: JICA Survey Team

### Boring Point for Geotechnical Investigation in Seabed



Source: JICA Survey Team

### Result of Geotechnical Investigation on Seabed



### 5.3-2 Calculation for Diameter of Intake and Discharge Pipes

#### Calculation for diameter of HDPE

**Project name: Tunisia, Sfax desalination plant project**  
**Calculation: Headloss**

| Intake                      |                                       | HDPE x 2                           |      | HDPE x 1                           |      |
|-----------------------------|---------------------------------------|------------------------------------|------|------------------------------------|------|
|                             |                                       | Allowable head loss: Less than 2mH |      | Allowable head loss: Less than 2mH |      |
| Total flow rate             | Q= 444.445 m3/day= 5.144 m3/sec       |                                    |      | 444.445 m3/day= 5.144 m3/sec       |      |
| Pipeline No.                | Pn= 2                                 | Capacity                           | 100% | Capacity                           | 100% |
| Design flow rate/line       | Qp= 2.572 m3/sec                      |                                    |      | 5.144 m3/sec                       |      |
| Roughness coefficient       | n= 0.016                              |                                    |      | 0.016                              |      |
| Additional thickness        | ld= 0 mm                              |                                    |      | 0 mm                               |      |
| Specific weight of seawater | yw= 10.1 kN/m3                        |                                    |      | 10.1 kN/m3                         |      |
| Anode No.                   | An= pcs                               |                                    |      | pcs                                |      |
| Anode section area          | Aa= m2                                |                                    |      | m2                                 |      |
| Chlori pipe support No.     | Cn= pcs (Assumed setting interval 2m) |                                    |      | pcs (Assumed setting interval 2m)  |      |
| Chlori pipe OD              | Dc= mm (4inch)                        |                                    |      | mm (4inch)                         |      |
| Chlori pipe section area    | Ac= m2                                |                                    |      | m2                                 |      |
| Chlori support section area | As= m2                                |                                    |      | m2                                 |      |

| Brine Discharge             |                                 | HDPE x 1                           |      |
|-----------------------------|---------------------------------|------------------------------------|------|
|                             |                                 | Allowable head loss: Less than 3mH |      |
| Total flow rate             | Q= 244.445 m3/day= 2.829 m3/sec |                                    |      |
| Pipeline No.                | Pn= 1                           | Capacity                           | 100% |
| Design flow rate/line       | Qp= 2.829 m3/sec                |                                    |      |
| Roughness coefficient       | n= 0.012                        |                                    |      |
| Additional thickness        | ld= 0 mm                        |                                    |      |
| Specific weight of seawater | yw= 10.1 kN/m3                  |                                    |      |
| Anode No.                   | An= pcs                         |                                    |      |
| Anode section area          | Aa= m2                          |                                    |      |
| Nozzle no.                  | Nn= 4 nozzles                   |                                    |      |
| Nozzle dia                  | Dn= 0.55 m                      |                                    |      |
| Flow rate per one nozzle    | Qn= 0.707 m3/sec                |                                    |      |
| 放水流速                        | Vn= 3 m/sec                     |                                    |      |

|                                    | PipeLife         | KWH   |        | PipeLife | PipeLife | KWH    |        |        |        |
|------------------------------------|------------------|-------|--------|----------|----------|--------|--------|--------|--------|
|                                    |                  | 2,020 | 2,240  |          |          | Max    | 2,690  | 2,804  | 2,920  |
| Pipe ND (mm)                       | D=               | 2,100 | 1,800  | 2,000    | 2,300    | 2,500  | 2,400  | 2,500  | 2,600  |
| SDR                                |                  | 17    | --     | --       | 17       | 17     | --     | --     | --     |
| Pipe thickness(mm)                 | t=               | 123.5 | 110    | 120      | 135.3    | 147.1  | 145    | 152    | 160    |
| Pipe Inner Diameter (mm)           | Dc=              | 1,853 | 1,800  | 2,000    | 2,029    | 2,206  | 2,400  | 2,500  | 2,600  |
| Pipe section area(m <sup>2</sup> ) | Ap=              | 2.697 | 2.545  | 3.142    | 3.235    | 3.821  | 4.524  | 4.909  | 5.309  |
| Flow section area(m <sup>2</sup> ) | Acp=             | 2.697 | 2.545  | 3.142    | 3.235    | 3.821  | 4.524  | 4.909  | 5.309  |
| Flow velocity(m/sec)               | V=               | 0.954 | 1.011  | 0.819    | 0.795    | 0.673  | 1.137  | 1.048  | 0.969  |
| Wetted perimeter(m)                | S=               | 5.821 | 5.655  | 6.283    | 6.376    | 6.93   | 7.54   | 7.854  | 8.168  |
| Hydraulic radius(m)                | R=               | 0.463 | 0.45   | 0.5      | 0.507    | 0.551  | 0.6    | 0.625  | 0.65   |
| Pipeline length(m)                 | L=               | 3,600 | 3,600  | 3,600    | 3,600    | 3,600  | 3,600  | 3,600  | 3,600  |
| Inlet headloss(m)                  | h <sub>i</sub> = | 0.046 | 0.052  | 0.034    | 0.032    | 0.023  | 0.066  | 0.056  | 0.048  |
| Coefficient of friction            |                  | 50.43 | 52.382 | 45.517   | 44.681   | 39.988 | 35.694 | 33.803 | 32.081 |
| Friction headloss(m)               | h <sub>f</sub> = | 2.342 | 2.732  | 1.558    | 1.441    | 0.924  | 2.354  | 1.894  | 1.537  |
| Coefficient of anode               |                  | 0     | 0      | 0        | 0        | 0      | 0      | 0      | 0      |
| Anode headloss(m)                  | h <sub>a</sub> = | 0     | 0      | 0        | 0        | 0      | 0      | 0      | 0      |
| Bend pipe headloss(m)              | h <sub>b</sub> = | 0     | 0      | 0        | 0        | 0      | 0      | 0      | 0      |
| Coefficient of chlori support      |                  | 0     | 0      | 0        | 0        | 0      | 0      | 0      | 0      |
| Chlori support headloss(m)         | h <sub>c</sub> = | 0     | 0      | 0        | 0        | 0      | 0      | 0      | 0      |
| Outlet headloss(m)                 | h <sub>o</sub> = | 0.046 | 0.052  | 0.034    | 0.032    | 0.023  | 0.066  | 0.056  | 0.048  |
| <b>Total headloss(m)</b>           | <b>H=</b>        | 2.434 | 2.836  | 1.626    | 1.505    | 0.97   | 2.486  | 2.006  | 1.633  |

|                                    | PipeLife         | PipeLife | KWH    |        |        |
|------------------------------------|------------------|----------|--------|--------|--------|
|                                    |                  |          | 2,020  | 2,240  |        |
| Pipe ND (mm)                       | D=               | 2,000    | 2,100  | 1,800  | 2,000  |
| SDR                                |                  | 17       | 17     | --     | --     |
| Pipe thickness(mm)                 | t=               | 117.6    | 123.5  | 110    | 120    |
| Pipe ID (mm)                       | Dc=              | 1,765    | 1,853  | 1,800  | 2,000  |
| Pipe section area(m <sup>2</sup> ) | Ap=              | 2.446    | 2.697  | 2.545  | 3.142  |
| Flow section area(m <sup>2</sup> ) | Acp=             | 2.446    | 2.697  | 2.545  | 3.142  |
| Flow velocity(m/sec)               | V=               | 1.157    | 1.049  | 1.112  | 0.9    |
| Wetted perimeter(m)                | S=               | 5.544    | 5.821  | 5.655  | 6.283  |
| Hydraulic radius(m)                | R=               | 0.441    | 0.463  | 0.45   | 0.5    |
| Pipeline length(m)                 | L=               | 4,400    | 4,400  | 4,400  | 4,400  |
| Inlet headloss(m)                  | h <sub>i</sub> = | 0.068    | 0.056  | 0.063  | 0.041  |
| Coefficient of friction            |                  | 36.996   | 34.671 | 36.013 | 31.293 |
| Friction headloss(m)               | h <sub>f</sub> = | 2.527    | 1.947  | 2.272  | 1.293  |
| Bend pipe headloss(m)              | h <sub>b</sub> = | 0        | 0      | 0      | 0      |
| Coefficient of anode               |                  | 0        | 0      | 0      | 0      |
| Anode headloss(m)                  | h <sub>a</sub> = | 0        | 0      | 0      | 0      |
| Nozzle outlet headloss(m)          | h <sub>n</sub> = | 0.689    | 0.689  | 0.689  | 0.689  |
| Discharge head headloss(m)         | h <sub>d</sub> = | 0.068    | 0.056  | 0.063  | 0.041  |
| <b>Total headloss(m)</b>           | <b>H=</b>        | 3.352    | 2.748  | 3.087  | 2.064  |

5.3-3

Source: JICA Survey Team

## Calculation for diameter of steel pipe

**Project name: Tunisia, Sfax desalination plant project**  
**Calculation: Headloss**

| Intake                                |  |
|---------------------------------------|--|
| Coated steel with cathodic protection |  |
| Allowable head loss : Less than 2mH   |  |

| Brine Discharge                       |  |
|---------------------------------------|--|
| Coated steel with cathodic protection |  |
| Allowable head loss : Less than 3 mH  |  |

|                       |                                 |
|-----------------------|---------------------------------|
| Total flow rate       | Q= 444,445 m3/day= 5.144 m3/sec |
| Pipeline No.          | Pn= 1                           |
| Design flow rate/line | Q p = 5.144 m3/sec              |

|                       |                                 |
|-----------------------|---------------------------------|
| Total flow rate       | Q= 244,445 m3/day= 2.829 m3/sec |
| Pipeline No.          | Pn= 1                           |
| Design flow rate/line | Q p = 2.829 m3/sec              |

|                             |                |                                |
|-----------------------------|----------------|--------------------------------|
| Roughness coefficient       | n= 0.016       |                                |
| Additional thickness        | ld= 0 mm       |                                |
| Specific weight of seawater | γw= 10.1 kN/m3 |                                |
| Anode No.                   | An= 450 pcs    | Design life 10years            |
| Anode section area          | Aa= 0.0204 m2  |                                |
| Chlori pipe support No.     | Cn= 1,800 pcs  | (Assumed setting interval 2m ) |
| Chlori pipe OD              | Dc= 114 mm     | (4inch)                        |
| Chlori pipe section area    | Ac= 0.0103 m2  |                                |
| Chlori support section area | As= 0.033 m2   |                                |

|                             |                  |                     |
|-----------------------------|------------------|---------------------|
| Roughness coefficient       | n= 0.012         |                     |
| Additional thickness        | ld= 0 mm         |                     |
| Specific weight of seawater | γw= 10.1 kN/m3   |                     |
| Anode No.                   | An= 550 pcs      | Design life 10years |
| Anode section area          | Aa= 0.0204 m2    |                     |
| Nozzle no.                  | Nn= 4 nozzles    |                     |
| Nozzle dia                  | Dn= 0.55 m       |                     |
| Flow rate per one nozzle    | Qn= 0.707 m3/sec |                     |
| 放水流速                        | Vn= 3 m/sec      |                     |

|                                    |                  |              |              |
|------------------------------------|------------------|--------------|--------------|
|                                    | Outer diameter   | 2,828        |              |
|                                    | wall thickness   | 14.0         |              |
| Pipe ND (mm)                       | D=               | 2,700        | 2,900        |
| Pipe Inner Diameter (mm)           | Dc=              | 2,700        | 2,900        |
| Pipe section area(m <sup>2</sup> ) | Ap=              | 5.726        | 6.605        |
| Flow section area(m <sup>2</sup> ) | Acp=             | 5.716        | 6.595        |
| Flow velocity(m/sec)               | V=               | 0.9          | 0.78         |
| Wetted perimeter(m)                | S=               | 8.84         | 9.469        |
| Hydraulic radius(m)                | R=               | 0.647        | 0.696        |
| Pipeline length(m)                 | L=               | 3,600        | 3,600        |
| Inlet headloss(m)                  | h <sub>a</sub> = | 0.041        | 0.031        |
| Coefficient of friction            |                  | 32.279       | 29.286       |
| Friction headloss(m)               | h <sub>f</sub> = | 1.334        | 0.909        |
| Coefficient of anode               |                  | 12.24        | 14.123       |
| Anode headloss(m)                  | h <sub>c</sub> = | 0.506        | 0.438        |
| Bend pipe headloss(m)              | h <sub>b</sub> = | 0            | 0            |
| Coefficient of chlori support      |                  | 10.392       | 9.007        |
| Chlori support headloss(m)         | h <sub>s</sub> = | 0.429        | 0.28         |
| Outlet headloss(m)                 | h <sub>s</sub> = | 0.041        | 0.031        |
| <b>Total headloss(m)</b>           | <b>H=</b>        | <b>2.351</b> | <b>1.689</b> |

|                                    |                  |              |              |
|------------------------------------|------------------|--------------|--------------|
|                                    | Outer diameter   | 1,920        |              |
|                                    | wall thickness   | 10.0         |              |
| Pipe ND (mm)                       | D=               | 1,800        | 2,000        |
| Pipe Inner Diameter (mm)           | Dc=              | 1,800        | 2,000        |
| Pipe section area(m <sup>2</sup> ) | Ap=              | 2.5447       | 3.142        |
| Flow section area(m <sup>2</sup> ) | Acp=             | 2.5447       | 3.142        |
| Flow velocity(m/sec)               | V=               | 1.112        | 0.9          |
| Wetted perimeter(m)                | S=               | 5.655        | 6.283        |
| Hydraulic radius(m)                | R=               | 0.45         | 0.5          |
| Pipeline length(m)                 | L=               | 4,400        | 4,400        |
| Inlet headloss(m)                  | h <sub>a</sub> = | 0.063        | 0.041        |
| Coefficient of friction            |                  | 36.013       | 31.293       |
| Friction headloss(m)               | h <sub>f</sub> = | 2.272        | 1.293        |
| Bend pipe headloss(m)              | h <sub>b</sub> = | 0            | 0            |
| Coefficient of anode               |                  | 12.106       | 14.96        |
| Anode headloss(m)                  | h <sub>c</sub> = | 0.764        | 0.618        |
| Nozzle outlet headloss(m)          | h <sub>n</sub> = | 0.689        | 0.689        |
| Discharge head headloss(m)         | h <sub>s</sub> = | 0.063        | 0.041        |
| <b>Total headloss(m)</b>           | <b>H=</b>        | <b>3.851</b> | <b>2.682</b> |

Relation between intake pipe diameter and head loss

| Summary of intake pipe specification                                 |                    |                  |                   |                   |                  |                    |              |
|--|--------------------|------------------|-------------------|-------------------|------------------|--------------------|--------------|
| Material   |                    |                  | HDPE              |                   |                  | Steel              |              |
| Manufacturer   |                    |                  | Uponor            | PipeLife          | Agru             | Many               |              |
| Head Quarter   |                    |                  | Finland           | Norway            | Austria          | many               |              |
| Application  | Targeted head loss | Adjusted at,     |                   | Inner dia         | Outer dia        | Outer dia          |              |
| Intake   | 2.0 mH             | Number of pipes  |                   | 1                 | 1                | 1                  |              |
|  |                    | Outer Dia        | mm                | 2,804             | (Max2,500)       |                    | 2,828        |
|  |                    | Wall thickness   | mm                | 152               | --               |                    | 14           |
|  |                    | Inner Dia        | mm                | <b>2,500</b>      | --               |                    | <b>2,800</b> |
|  |                    | Expected delta H | mH                | 2.01              | --               |                    | 1.98         |
|  |                    | Number of pipes  |                   | 2                 | 2                | 2                  |              |
|  |                    | Outer Dia        | mm                | 2,240             | <b>2,300</b>     | <b>(Max 2,250)</b> |              |
|  |                    | Wall thickness   | mm                | 120               | 135.3            |                    |              |
|  |                    | Inner Dia        | mm                | <b>2,000</b>      | 2,029            |                    |              |
|  |                    | Expected delta H | mH                | 1.63              | 1.51             |                    |              |
| Note:<br>Specification of products is based on their catalogue, etc. |                    |                  | Stabdard Products | Adjusted at Inner | Ajusted at Outer | Ajusted at Outer   |              |
|  |                    |                  |                   | 1,600             | 1,600            |                    |              |
|  |                    |                  |                   | 1,800             | 1,800            |                    |              |
|  |                    |                  |                   | 2,000             | 2,000            |                    |              |
|  |                    |                  |                   |                   | 2,100            |                    |              |
|  |                    |                  |                   | 2,200             |                  | 2,250              |              |
|  |                    |                  |                   |                   | 2,300            | (MAX)              |              |
|  |                    |                  |                   | 2,400             |                  |                    |              |
|  |                    |                  |                   |                   | 2,500            |                    |              |
|  |                    |                  |                   | 2,600             | (MAX)            |                    |              |
|  | 2,800              |                  |                   |                   |                  |                    |              |
|  | 3,000              |                  |                   |                   |                  |                    |              |
|  | (MAX)              |                  |                   |                   |                  |                    |              |

Source: JICA Survey Team

Relation between internal diameter of discharge pipe and head loss

| Summary of discharge pipe specification                              |                    |                   |                   |                  |                  |           |              |
|--|--------------------|-------------------|-------------------|------------------|------------------|-----------|--------------|
| Material   |                    |                   |                   | HDPE             |                  |           | Steel        |
| Manufacturer   |                    |                   |                   | Uponor           | PipeLife         | Agru      | Many         |
| Head Quarter   |                    |                   |                   | Finland          | Norway           | Austria   | many         |
| Application  | Targeted head loss | Adjusted at,      |                   | Inner dia        | Outer dia        | Outer dia | Inner dia    |
| Brine discharge  | 3.0 mH             | Number of pipes   |                   | 1                | 1                | 1         | 1            |
|  |                    | Outer Dia         | mm                | 2,020            | <b>2,100</b>     | Available | 1,920        |
|  |                    | Wall thickness    | mm                | 110              | 123.5            |           | 10.0         |
|  |                    | Inner Dia         | mm                | <b>1,800</b>     | 1,853            |           | <b>1,900</b> |
|  |                    | Expected delta H  | mH                | 3.09             | 2.75             | 3.18      |              |
| Note:<br>Specification of products is based on their catalogue, etc. |                    | Stabdard Products | Adjusted at Inner | Ajusted at Outer | Ajusted at Outer |           |              |
|  |                    |                   | 1,600             | 1,600            |                  |           |              |
|  |                    |                   | 1,800             | 1,800            |                  |           |              |
|  |                    |                   | 2,000             | 2,000            |                  |           |              |
|  |                    |                   |                   | 2,100            |                  |           |              |
|  |                    |                   | 2,200             |                  | 2,250            |           |              |
|  |                    |                   | 2,400             | 2,300            | (MAX)            |           |              |
|  |                    |                   |                   | 2,500            |                  |           |              |
|  |                    |                   | 2,600             | (MAX)            |                  |           |              |
|  |                    |                   | 2,800             |                  |                  |           |              |
|  |                    |                   | 3,000             |                  |                  |           |              |
|  |                    |                   | (MAX)             |                  |                  |           |              |

Source: JICA Survey Team

**Calculation for Diameter of Sodium Hypochlorite Injection Pipe Diameter**

**Condition:**

**Injection Rate:** Sodium Hypochlorite 2 mg/L

**Flow Rate:** Sodium Hypochlorite Solution (concentration 5,000mg/L)

Sodium Hypochlorite to be Injected 0.88889m<sup>3</sup>/day (=Intake volume 444,445m<sup>3</sup>/day x 2mg/L /1,000,000)

Sodium Hypochlorite Injection Solution 0.0021m<sup>3</sup>/sec (=0.88889m<sup>3</sup>/day/ (5,000/1,000,000)mg/L = 177.8m<sup>3</sup>/day)

**Pipe Materials:** PVC or HDPE (Injection Nozzle at the Intake head is PVC with FRP reinforcement)

**Roughness Coefficient:** Friction headloss by Hazen-Williams formula. C=120 for plastic pipe for long term use.

$$h_f = \frac{10.67 L Q^{1.85}}{C^{1.85} d^{4.87}}$$

$$d^{4.87} = (10.67 \times L \times Q^{1.85}) / (C^{1.85} \times h_f)$$

where:

hf: Headloss for pipe length (L) (m) 8

L: Pipe length (m) 3600

Q: Flow quantity (m<sup>3</sup>/s) 0.0021

C: Croughness cosfficeient for Hazen-Williams Formula 120

d: Internal diameter of Pipe (m)

$$d^{4.87} = 0.0000076$$

$$d = 89 \text{ mm } \quad 4" \text{ pipe I.D. about } 100\text{mm}$$

***CHAPTER 6***

***PLAN OF WATER SUPPLY FACILITIES***

## 6.1-1 TDS Concentrations of Existing Reservoirs and Water Sources

|           |           | (1) TDS Concentraion by Reservoir (Upper: date, Lower:TDS concentration mg/L) |      |      |      |      |      |      |      |      |      |      |      |            |           |
|-----------|-----------|---|------|------|------|------|------|------|------|------|------|------|------|------------|-----------|
| Reservoir |           | PK10  |      |      |      | PK11 |      |      |      | PK14 |      |      |      | Sidi Salah | Bou Merra |
| 2010      | January   |   |      |      |      |      |      |      |      |      |      |      |      |            |           |
|           | February  |   |      |      |      |      |      |      |      |      |      |      |      |            |           |
|           | March     |   |      |      |      |      |      |      |      |      |      |      |      |            |           |
|           | April     | 1   |      |      |      | 1    |      |      |      | 1    |      |      |      |            |           |
|           | May       | 1364  |      |      |      | 1416 |      |      |      | 1400 |      |      |      |            |           |
|           | June      |   |      |      |      |      |      |      |      |      |      |      |      |            |           |
|           | July      | 6   |      |      |      | 6    |      |      |      | 6    |      |      |      |            |           |
|           | August    | 1716  |      |      |      | 1694 |      |      |      | 1518 |      |      |      |            |           |
|           | September | 21  | 28   |      |      | 21   | 28   |      |      | 21   | 28   |      |      |            |           |
|           | October   | 1410  | 1504 |      |      | 1970 | 1710 |      |      | 1462 | 1602 |      |      |            |           |
|           | November  | 8   | 12   | 19   |      | 8    | 12   | 19   |      | 8    | 12   | 19   |      |            |           |
|           | December  | 1150  | 1250 | 1434 |      | 1450 | 1500 | 1522 |      | 1350 | 1250 | 1636 |      |            |           |
|           | Average   |   |      |      |      | 1404 |      |      |      | 1609 |      |      |      | 1460       |           |
| 2011      | January   | 4   | 20   | 25   |      | 4    | 20   | 25   |      | 4    | 20   | 25   |      |            |           |
|           | February  | 1430  | -    | 1070 |      | 1324 | 1368 | 1402 |      | 1461 | -    | 1069 |      |            |           |
|           | March     | 1   | 8    | 17   | 23   | 1    | 8    | 17   | 23   | 1    | 8    | 17   | 23   | 28         |           |
|           | April     | 1763  | 1980 | 1497 | 1456 | 1588 | 1588 | 1626 | 1613 | 1439 | 1190 | 1417 | 1378 | 23         | 17        |
|           | May       | 1387  | 1216 | 1414 | 1418 | 1588 | 1588 | 1626 | 1613 | 1439 | 1190 | 1417 | 1378 | 23         | 17        |
|           | June      | 5   | 12   | 19   | 26   | 5    | 12   | 19   | 26   | 5    | 12   | 19   | 26   |            |           |
|           | July      | 1432  | 1480 | 1688 | 1615 | 1738 | 1878 | 1864 | 1614 | 1487 | 1490 | 1677 | 1661 |            |           |
|           | August    | 11  | 17   | 24   | 31   | 11   | 17   | 24   | 31   | 11   | 17   | 24   | 31   | 30         |           |
|           | September | 1349  | 1548 | 1262 | 1435 | 1581 | 1438 | 1422 | 1608 | 1391 | 1533 | 1240 | 1485 | 1932       |           |
|           | October   | 21  | 28   |      |      | 21   | 28   |      |      | 21   | 28   |      |      | 28         | 14        |
|           | November  | 1488  | 1624 |      |      | 1860 | 1792 |      |      | 1611 | 1561 |      |      | 1820       | 1452      |
|           | December  | 12  | 19   | 26   |      | 12   | 19   | 26   |      | 12   | 19   | 26   |      |            | 25        |
|           | Average   | 1718  | 1663 | 1646 |      | 1769 | 1642 | 1636 |      | 1542 | 1634 | 1526 |      |            | 1390      |
| 2012      | January   | 3   | 13   | 24   |      | 3    | 13   | 24   |      | 3    | 13   | 24   |      |            |           |
|           | February  | 1640  | 2240 | 2150 |      | 1780 | 2270 | 2190 |      | 1654 | 2070 | 1991 |      |            |           |
|           | March     | 7   | 15   | 22   |      | 7    | 15   | 22   |      | 7    | 15   | 22   |      | 27         |           |
|           | April     | 1028  | 1636 | 1408 |      | 1620 | 2090 | 2000 |      | 1120 | 1869 | 1436 |      | 1606       |           |
|           | May       | 6   | 21   | 29   |      | 6    | 21   | 29   |      | 6    | 21   | 29   |      |            |           |
|           | June      | 1041  | 1253 | 1261 |      | 2050 | 1401 | 1955 |      | 1268 | 1398 | 1392 |      |            |           |
|           | July      | 17  | 30   |      |      | 17   | 30   |      |      | 17   | 30   |      |      |            | 16        |
|           | August    | 1641  | 1556 |      |      | 2050 | 2000 |      |      | 1753 | 1771 |      |      |            | 1490      |
|           | September | 11  | 24   |      |      | 11   | 24   |      |      | 11   | 24   |      |      | 17         |           |
|           | October   | 1975  | 1987 |      |      | 2180 | 2040 |      |      | 2160 | 2040 |      |      | 1880       |           |
|           | November  | 5   | 19   |      |      | 5    | 19   |      |      | 5    | 19   |      |      |            |           |
|           | December  | 1901  | 1900 |      |      | 2030 | 2210 |      |      | 1795 | 1630 |      |      |            |           |
|           | Average   | 3   | 12   | 20   | 30   | 5    | 18   | 25   | 31   | 4    | 18   | 25   | 31   |            |           |
| 2013      | January   | 3   | 13   | 24   |      | 3    | 13   | 24   |      | 3    | 13   | 24   |      |            |           |
|           | February  | 1947  | 1900 | 2030 | 2060 |      |      |      |      | 3    |      |      |      | 3          |           |
|           | March     | 5   | 15   | 21   | 29   |      |      |      |      | 1874 |      |      |      | 2188       |           |
|           | April     | 1913  | 1742 | 1769 | 2090 |      |      |      |      |      |      |      |      |            |           |
|           | May       | 3   | 11   | 20   | 31   | 19   |      |      |      |      |      |      |      |            | 4         |
|           | June      | 2420  | 1866 | 1481 | 1780 | 1868 |      |      |      |      |      |      |      |            | 1936      |
|           | July      | 5   | 12   | 20   | 30   |      |      |      |      |      |      |      |      |            |           |
|           | August    | 1877  | 1734 | 1880 | 1734 |      |      |      |      |      |      |      |      | 12         |           |
|           | September | 8   | 15   | 21   | 28   |      |      |      |      | 17   |      |      |      | 5          | 18        |
|           | October   | 1533  | 1530 | 1557 | 2000 |      |      |      |      | 1714 |      |      |      | 2014       | 1738      |
|           | November  |   |      |      |      |      |      |      |      |      |      |      |      |            |           |
|           | December  |   |      |      |      |      |      |      |      |      |      |      |      |            |           |
|           | Average   |   |      |      |      | 1779 |      |      |      | 1974 |      |      |      | 1702       | 1939      |
| 2014      | January   | 9   | 16   | 25   | 31   | 17   |      |      |      |      |      |      |      |            |           |
|           | February  | 1450  | 1800 | 2002 | 2500 | 1690 |      |      |      |      |      |      |      |            |           |
|           | March     | 4   | 9    | 16   | 25   |      |      |      |      |      |      |      |      | 14         |           |
|           | April     | 2400  | 1600 | 820  | 1915 |      |      |      |      |      |      |      |      | 1146       |           |
|           | May       | 4   | 9    | 18   | 29   |      |      |      |      | 7    |      |      |      | 7          | 2302      |
|           | June      | 2150  | 1760 | 1990 | 2300 |      |      |      |      | 1666 |      |      |      | 8          | 1776      |
|           | July      | 11  | 23   | 29   |      | 11   | 23   | 29   |      | 11   | 23   | 29   |      |            |           |
|           | August    | 2100  | 2500 | 2400 |      | 2200 | 2300 | 2400 |      | 2100 | 2300 | 2300 |      |            |           |
|           | September | 17  | 21   | 28   |      | 17   | 21   | 28   |      | 17   | 21   | 28   |      | 27         |           |
|           | October   | 2200  | 2150 | 2300 |      | 2400 | 2500 | 2300 |      | 2200 | 2000 | 2200 |      | 2336       |           |
|           | November  | 4   | 20   | 29   |      | 4    | 20   | 29   |      | 4    | 20   | 29   |      |            | 10        |
|           | December  | 2100  | 2400 | 2300 |      | 2400 | 2450 | 2300 |      | 2000 | 2400 | 2450 |      |            | 1630      |
|           | Average   | 9   | 16   | 24   | 30   | 9    | 16   | 24   | 30   | 9    | 16   | 24   | 30   |            |           |
| 2015      | January   | 2400  | 2150 | 2200 | 2200 | 2200 |      |      | 2200 | 2500 | 2150 | 2300 | 2200 |            |           |
|           | February  | 6   | 15   | 21   |      | 6    | 15   | 21   |      | 6    | 15   | 21   |      | 23         | 22        |
|           | March     | 2050  | 2000 | 2110 |      | 2150 | 2100 | 2380 |      | 2350 | 2200 | 2400 |      | 1850       | 1582      |
|           | April     | 17  | 24   |      |      | 17   | 24   |      |      | 17   | 24   |      |      |            |           |
|           | May       | 2300  | 2370 |      |      | 2300 | 2480 |      |      | 2630 | 2410 |      |      |            |           |
|           | June      | 8   | 29   |      |      | 8    | 29   |      |      | 8    | 29   |      |      | 2          |           |
|           | July      | 2130  | 2520 |      |      | 2320 | 2300 |      |      | 2270 | 2630 |      |      |            | 1732      |
|           | August    | 19  | 26   |      |      | 19   | 26   |      |      | 19   | 26   |      |      | 22         |           |
|           | September | 2330  | 2170 |      |      | 2060 | 2250 |      |      | 2140 | 2150 |      |      | 2106       |           |
|           | October   | 3   | 10   | 30   |      | 3    | 10   | 30   |      | 3    | 10   | 30   |      |            | 2         |
|           | November  | 2180  | 2390 | 2290 |      | 2230 | 2380 | 2020 |      | 2050 | 2440 | 2210 |      |            | 2092      |
|           | December  |   |      |      |      |      |      |      |      |      |      |      |      |            |           |
|           | Average   |   |      |      |      | 2133 |      |      |      | 2257 |      |      |      | 2256       | 1860      |
| 2016      | January   | 7   | 17   | 22   |      | 7    | 17   | 22   |      | 7    | 17   | 22   |      |            |           |
|           | February  | 2270  | 2210 | 2740 |      | 2060 | 1924 | 2050 |      | 2450 | 2350 | 2650 |      |            |           |
|           | March     | 4   | 11   | 18   | 25   | 4    | 11   | 18   | 25   | 4    | 11   | 18   | 25   |            |           |
|           | April     | 2120  | 2060 | 2510 | 2410 | 1883 | 1883 | 2100 | 2040 | 1913 | 2080 | 2300 | 2280 |            |           |
|           | Average   | 11  | 18   | 24   | 31   | 11   | 18   | 24   | 31   | 11   | 18   | 24   | 31   |            |           |
| 2017      | January   | 2390  | 2260 | 1795 | 1810 | 2170 | 2180 | 1892 | 2070 | 2220 | 2200 | 1935 | 1790 |            |           |
|           | February  | 8   | 22   | 29   |      | 8    | 22   | 29   |      | 8    | 22   | 29   |      |            |           |
|           | March     | 8   | 22   | 29   |      | 8    | 22   | 29   |      | 8    | 22   | 29   |      |            |           |
|           | April     | 1976  | 2170 | 2140 |      | 2130 | 2060 | 2120 |      | 1858 | 2340 | 2380 |      |            |           |
|           | Average   |   |      |      |      | 2204 |      |      |      | 2040 |      |      |      | 2196       |           |
| Reservoir |           |   |      |      |      |      |      |      |      |      |      |      |      |            |           |
|           |           |   |      |      |      |      |      |      |      |      |      |      |      |            |           |

Source : SONEDE

**(2) TDS Concentration by Water Source (Upper: date, Lower:TDS concentration mg/L)**


| Dsitric |                           | D32             |                   |            |            | D33                     |                  |                     |                    |                          | D34                        |                                      |            |
|---------|---------------------------|-----------------|-------------------|------------|------------|-------------------------|------------------|---------------------|--------------------|--------------------------|----------------------------|--------------------------------------|------------|
| Site    | Arrivé<br>Eaux du<br>Nord | Arrivé<br>Jelma | Arrivé<br>Sbeitla | PK13       | PK15       | Forage<br>Sidi<br>Saleh | Forage<br>Heicha | Forage<br>Jebeniana | Forage<br>Mahrouga | Forage<br>Saint<br>Louis | Forage<br>Sidi<br>Boukthir | Forage<br>Sidi<br>Allouch<br>Aguereb |            |
| 2012    | January                   | 30<br>1130      | 30<br>1540        | 30<br>1536 |            |                         |                  |                     |                    |                          |                            |                                      |            |
|         | February                  |                 |                   |            |            |                         |                  |                     |                    |                          |                            |                                      |            |
|         | March                     |                 |                   |            | 5<br>2988  |                         | 1<br>3154        | 1<br>3460           |                    |                          |                            |                                      |            |
|         | April                     |                 |                   |            |            |                         |                  |                     |                    |                          | 5<br>3978                  |                                      |            |
|         | May                       |                 |                   |            |            |                         | 14<br>3138       |                     |                    |                          |                            |                                      |            |
|         | June                      |                 |                   |            |            |                         |                  |                     |                    |                          |                            |                                      |            |
|         | July                      | 10<br>1430      | 10<br>1502        |            |            |                         |                  |                     |                    |                          |                            |                                      |            |
|         | August                    | 3<br>1110       |                   |            | 9<br>3142  |                         | 3<br>3101        | 7<br>3104           | 7<br>3476          |                          |                            | 6<br>3908                            |            |
|         | September                 |                 |                   |            |            |                         |                  |                     |                    |                          |                            |                                      |            |
|         | October                   | 4<br>1900       |                   |            |            |                         |                  |                     |                    |                          |                            |                                      |            |
|         | November                  |                 |                   |            |            |                         | 19<br>3176       |                     |                    |                          |                            |                                      |            |
|         | December                  |                 |                   |            |            |                         |                  |                     |                    |                          |                            |                                      |            |
| Average | 1393                      | 1521            | 1536              |            |            | 3138                    | 3129             | 3468                |                    |                          | 3943                       |                                      |            |
| 2013    | January                   | 23<br>1290      | 23<br>1430        | 23<br>1772 |            |                         |                  |                     |                    |                          |                            |                                      |            |
|         | February                  |                 |                   |            | 19<br>3092 | 14<br>3162              | 18<br>3588       | 18<br>3486          |                    |                          |                            |                                      |            |
|         | March                     |                 |                   |            |            |                         |                  |                     | 11<br>3846         |                          | 11<br>4054                 |                                      |            |
|         | April                     | 8<br>1828       | 8<br>1524         | 10<br>1848 |            |                         |                  |                     |                    |                          |                            |                                      |            |
|         | May                       |                 |                   |            |            | 13<br>3110              | 27<br>3156       |                     |                    |                          |                            |                                      |            |
|         | June                      |                 |                   |            |            |                         |                  |                     |                    |                          |                            |                                      |            |
|         | July                      | 16<br>1582      | 16<br>1676        | 16<br>1944 |            |                         |                  |                     |                    |                          |                            |                                      |            |
|         | August                    |                 |                   |            |            |                         | 23<br>3172       | 26<br>3634          | 29<br>3514         | 26<br>3842               | 29<br>3660                 |                                      | 29<br>2950 |
|         | September                 |                 |                   |            | 5<br>3198  | 5<br>3202               |                  |                     |                    |                          |                            |                                      |            |
|         | October                   | 4<br>1668       | 4<br>1644         | 4<br>1918  |            |                         |                  |                     |                    |                          |                            |                                      |            |
|         | November                  |                 |                   |            |            |                         | 22<br>3152       |                     |                    |                          |                            |                                      |            |
|         | December                  |                 |                   |            |            |                         |                  |                     |                    |                          |                            |                                      |            |
| Average | 1592                      | 1569            | 1871              | 3145       | 3156       | 3161                    | 3611             | 3500                | 3844               | 3660                     | 4054                       | 2950                                 |            |
| 2014    | January                   |                 |                   |            |            |                         |                  |                     |                    |                          |                            |                                      |            |
|         | February                  | 4<br>1928       | 4<br>1616         | 4<br>1856  |            |                         |                  | 17<br>3610          | 17<br>3598         |                          |                            |                                      |            |
|         | March                     |                 |                   |            |            |                         |                  |                     |                    |                          |                            |                                      |            |
|         | April                     | 8<br>1296       | 8<br>1600         | 10<br>1790 | 19<br>3088 |                         | 4<br>3208        |                     |                    |                          |                            |                                      |            |
|         | Average                   | 1612            | 1608              | 1823       | 3088       |                         | 3208             | 3610                | 3598               |                          |                            |                                      |            |
|         | North                     | Jelma Sbeitla   |                   | Well       |            |                         |                  |                     |                    |                          |                            |                                      |            |
|         | Moyenne                   | Moyenne         |                   | Moyenne    |            | 3154                    |                  |                     |                    |                          |                            |                                      |            |
|         | say                       | 1599            | 31Mm3             | 16.1Mm3    |            | say                     | 3160             |                     |                    |                          |                            |                                      |            |
|         |                           | 1600            | 1582              | 1855       |            |                         |                  |                     |                    |                          |                            |                                      |            |
|         |                           |                 | 1675              |            |            |                         |                  |                     |                    |                          |                            |                                      |            |
|         |                           |                 | say               | 1680       |            |                         |                  |                     |                    |                          |                            |                                      |            |

Source : SONEDE




## 6.1-2 Schematic Diagram of Transmission Flow of Each Option


### (1) Option 1



## (2) Option 2



### (3) Option 3



## 6.1-3 Distribution Flow and TDS Concentration of Each Reservoir in Option 1 and Option 2

Allocation of Water Source and TDS Concentrations by Reservoir (Option 1: Groundwater; maximum reduction, Jelma-Sbeitla & North; possible reduction)

| Phase  | Actual |      |      |      | Pre-Construction |      |      |      |      |      |      |      | Phase 1 |      |      |      | Phase 2 |      |      |      |      |      |      |      |      |      |      |
|--|--------|------|------|------|------------------|------|------|------|------|------|------|------|---------|------|------|------|---------|------|------|------|------|------|------|------|------|------|------|
|  | Year   | 2010 | 2011 | 2012 | 2013             | 2014 | 2015 | 2016 | 2017 | 2018 | 2019 | 2020 | 2021    | 2022 | 2023 | 2024 | 2025    | 2026 | 2027 | 2028 | 2029 | 2030 | 2031 | 2032 | 2033 | 2034 | 2035 |
| <b>Available Quantity from Water Sources</b> |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| <b>North Water Transmission System</b>       |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Jelma-Sbeitla Groundwater Trans. System      |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Groundwater in Greater Sfax                  |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| <b>Total Distribution Volume (m³/d)</b>      |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| <b>PK11 (distribution flow*)</b>             |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Wells  |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| North Water                                  |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Jelma-Sbeitla Water                          |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Sfax Desalination                            |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| <b>Mixed Water Transmission</b>              |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Total  |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| TDS (mg/l)                                   |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| <b>Bou Merra (max. dist. flow*)</b>          |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Wells  |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| North Water                                  |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Jelma-Sbeitla Water                          |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| <b>Mixed Water</b>                           |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Total  |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| TDS (mg/l)                                   |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| <b>PK10 (max. distribution flow*)</b>        |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Wells  |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| North Water                                  |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Jelma-Sbeitla Water                          |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| <b>Mixed Water</b>                           |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Total  |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| TDS (mg/l)                                   |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| <b>PK14 (max. distribution flow*)</b>        |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Wells  |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| North Water                                  |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Jelma-Sbeitla Water                          |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| <b>Mixed Water Transmission</b>              |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Total  |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| TDS (mg/l)                                   |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| <b>Sidi Salah EH (max. dist. flow*)</b>      |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Wells  |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| North Water                                  |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Jelma-Sbeitla Water                          |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| <b>Mixed Water</b>                           |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Total  |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| TDS (mg/l)                                   |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| <b>Sidi Salah EB (max. dist. flow*)</b>      |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Wells  |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| North Water                                  |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Jelma-Sbeitla Water                          |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| <b>Mixed Water (thru SS EH)</b>              |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| Total  |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |
| TDS (mg/l)                                   |        |      |      |      |                  |      |      |      |      |      |      |      |         |      |      |      |         |      |      |      |      |      |      |      |      |      |      |



## Planned TDS Concentration : Option 1

### Allocation of Water Source and TDS Concentrations by Reservoir (Option 1: Groundwater; maximum reduction, Jelma-Sbeitla & North; possible reduction)

#### TDS Concentration of Each Reservoir

| TDS(mg/l)      | Phase 1 |       |              |         |         |         |         |
|----------------|---------|-------|--------------|---------|---------|---------|---------|
| Reservoir      | 2020    | 2021  | 2022         | 2023    | 2024    | 2025    |         |
| PK11           | 1,800   | 1,861 | 784          | 935     | 901     | 933     |         |
| Bou Merra      | 2,293   | 2,243 | 784          | 1,188   | 901     | 933     |         |
| PK10           | 1,888   | 1,906 | 1,048        | 1,131   | 940     | 969     |         |
| PK14           | 1,822   | 1,820 | 1,141        | 1,204   | 1,046   | 1,066   |         |
| Sidi Salah EH  | 1,835   | 1,810 | 1,215        | 1,204   | 1,151   | 1,161   |         |
| Sidi Salah EB  | 1,835   | 1,810 | 1,215        | 1,204   | 1,151   | 1,161   |         |
| Highest TDS    | 2,293   | 2,243 | <b>1,215</b> | 1,204   | 1,151   | 1,161   | < 1,215 |
| Lowest TDS     | 1,800   | 1,810 | 784          | 935     | 901     | 933     |         |
| Highest/Lowest | 127%    | 124%  | <b>155%</b>  | 129%    | 128%    | 124%    | < 155%  |
| Desalination Q | 0       | 0     | 90,000       | 100,000 | 100,000 | 100,000 |         |

| TDS(mg/l)      | Phase 2-1  |             |         |         |         |        |
|----------------|------------|-------------|---------|---------|---------|--------|
| Reservoir      | 2026       | 2027        | 2028    | 2029    | 2030    |        |
| PK11           | 755        | 698         | 633     | 637     | 645     |        |
| Bou Merra      | 755        | 698         | 633     | 637     | 645     |        |
| PK10           | 797        | 741         | 633     | 637     | 685     |        |
| PK14           | 899        | 847         | 633     | 721     | 762     |        |
| Sidi Salah EH  | 958        | 907         | 684     | 800     | 834     |        |
| Sidi Salah EB  | 958        | 907         | 684     | 800     | 834     |        |
| Highest TDS    | <b>958</b> | 907         | 684     | 800     | 834     | < 958  |
| Lowest TDS     | 755        | 698         | 633     | 637     | 645     |        |
| Highest/Lowest | 127%       | <b>130%</b> | 108%    | 126%    | 129%    | < 130% |
| Desalination Q | 135,000    | 150,000     | 180,000 | 180,000 | 180,000 |        |

| TDS(mg/l)      | Phase 2-2   |         |            |         |         |        |
|----------------|-------------|---------|------------|---------|---------|--------|
| Reservoir      | 2031        | 2032    | 2033       | 2034    | 2035    |        |
| PK11           | 653         | 686     | 723        | 662     | 697     |        |
| Bou Merra      | 653         | 686     | 723        | 662     | 697     |        |
| PK10           | 693         | 723     | 757        | 697     | 735     |        |
| PK14           | 829         | 852     | 875        | 819     | 847     |        |
| Sidi Salah EH  | 892         | 934     | 952        | 897     | 920     |        |
| Sidi Salah EB  | 892         | 934     | 952        | 897     | 920     |        |
| Highest TDS    | 892         | 934     | <b>952</b> | 897     | 920     | < 952  |
| Lowest TDS     | 653         | 686     | 723        | 662     | 697     |        |
| Highest/Lowest | <b>137%</b> | 136%    | 132%       | 136%    | 132%    | < 137% |
| Desalination Q | 180,000     | 180,000 | 180,000    | 200,000 | 200,000 |        |

## Planned TDS Concentration : Option 2

### Allocation of Water Source and TDS Concentrations by Reservoir (Option 2: Groundwater; 20% Reduction, Jelma-Sbeitla; GW 100% Reduction)

#### TDS Concentration of Each Reservoir

| TDS(mg/l)      | Phase 1 |       |             |              |         |         |         |
|----------------|---------|-------|-------------|--------------|---------|---------|---------|
| Reservoir      | 2020    | 2021  | 2022        | 2023         | 2024    | 2025    |         |
| PK11           | 1,800   | 1,861 | 729         | 888          | 866     | 898     |         |
| Bou Merra      | 2,293   | 2,243 | 1,286       | 1,464        | 1,344   | 1,347   |         |
| PK10           | 1,888   | 1,906 | 1,213       | 1,109        | 1,097   | 1,116   |         |
| PK14           | 1,822   | 1,820 | 1,395       | 1,283        | 1,294   | 1,301   |         |
| Sidi Salah EH  | 1,835   | 1,810 | 1,457       | 1,487        | 1,379   | 1,379   |         |
| Sidi Salah EB  | 1,835   | 1,810 | 1,457       | 1,487        | 1,379   | 1,379   |         |
| Highest TDS    | 2,293   | 2,243 | 1,457       | <b>1,487</b> | 1,379   | 1,379   | < 1,487 |
| Lowest TDS     | 1,800   | 1,810 | 729         | 888          | 866     | 898     |         |
| Highest/Lowest | 127%    | 124%  | <b>200%</b> | 168%         | 159%    | 154%    | < 200%  |
| Desalination Q | 0       | 0     | 90,000      | 100,000      | 100,000 | 100,000 |         |

| TDS(mg/l)      | Phase 2-1    |             |         |         |         |         |
|----------------|--------------|-------------|---------|---------|---------|---------|
| Reservoir      | 2026         | 2027        | 2028    | 2029    | 2030    |         |
| PK11           | 709          | 647         | 596     | 585     | 594     |         |
| Bou Merra      | 1,171        | 1,101       | 1,038   | 1,012   | 1,001   |         |
| PK10           | 932          | 867         | 752     | 747     | 792     |         |
| PK14           | 1,126        | 1,066       | 860     | 929     | 962     |         |
| Sidi Salah EH  | 1,192        | 1,134       | 926     | 1,014   | 1,041   |         |
| Sidi Salah EB  | 1,192        | 1,134       | 926     | 1,014   | 1,041   |         |
| Highest TDS    | <b>1,192</b> | 1,134       | 1,038   | 1,014   | 1,041   | < 1,192 |
| Lowest TDS     | 709          | 647         | 596     | 585     | 594     |         |
| Highest/Lowest | 168%         | <b>175%</b> | 174%    | 173%    | 175%    | < 175%  |
| Desalination Q | 135,000      | 150,000     | 180,000 | 180,000 | 180,000 |         |

| TDS(mg/l)      | Phase 2-2   |         |              |         |         |         |
|----------------|-------------|---------|--------------|---------|---------|---------|
| Reservoir      | 2031        | 2032    | 2033         | 2034    | 2035    |         |
| PK11           | 606         | 642     | 683          | 622     | 661     |         |
| Bou Merra      | 995         | 1,008   | 1,030        | 964     | 985     |         |
| PK10           | 803         | 829     | 858          | 796     | 830     |         |
| PK14           | 1,020       | 1,036   | 1,051        | 992     | 1,012   |         |
| Sidi Salah EH  | 1,089       | 1,118   | 1,128        | 1,072   | 1,087   |         |
| Sidi Salah EB  | 1,089       | 1,118   | 1,128        | 1,072   | 1,087   |         |
| Highest TDS    | 1,089       | 1,118   | <b>1,128</b> | 1,072   | 1,087   | < 1,128 |
| Lowest TDS     | 606         | 642     | 683          | 622     | 661     |         |
| Highest/Lowest | <b>180%</b> | 174%    | 165%         | 172%    | 165%    | < 180%  |
| Desalination Q | 180,000     | 180,000 | 180,000      | 200,000 | 200,000 |         |

***CHAPTER 8***

***SOCIO-ENVIRONMENTAL CONSIDERATIONS***



### 8.7-1 Environmental Checklist

| Category                  | Environmental Item                        | Main Check Items   | Yes: Y<br>No: N                  | Confirmation of Environmental Considerations<br>(Reasons, Mitigation Measures)  |
|---------------------------|---|--|----------------------------------|---|
| 1 Permits and Explanation | (1) EIA and Environmental Permits         | (a) Have EIA reports been already prepared in official process?<br>(b) Have EIA reports been approved by authorities of the host country's government?<br>(c) Have EIA reports been unconditionally approved? If conditions are imposed on the approval of EIA reports, are the conditions satisfied?<br>(d) In addition to the above approvals, have other required environmental permits been obtained from the appropriate regulatory authorities of the host country's government? | (a) N<br>(b) N<br>(c) -<br>(d) N | (a) The EIA including the one for power distribution line will be implemented by SONEDE from February to September 2015.<br>(b) The EIA report shall be approved by ANPE(National Environment Agency) until December 2015. The TOR of the EIA are already approved by ANPE.<br>(c) Not applicable.<br>(d) The concession decree for the use of the maritime domain is scheduled for September 2016. また、The project will be implemented by SONEDE. Tunisian Electricity and Gas Supply Corporation (STEG), however, will construct the power distribution line. Since construction cost of it will be shouldered by SONEDE, necessary procedures have been started between SONEDE and STEG, and cost estimates offered by STEG is counted in the project cost. |
|                           | (2) Explanation to the Local Stakeholders | (a) Have contents of the project and the potential impacts been adequately explained to the Local stakeholders based on appropriate procedures, including information disclosure? Is understanding obtained from the Local stakeholders?<br>(b) Have the comment from the stakeholders (such as local residents) been reflected to the project design?   | (a) Y<br>(b) Y                   | (a) The first stakeholder meeting has been hold on the 22nd of May 2014. Considering the scope of the project, additional meetings will be scheduled during the EIA in 2015. STEG will prepare the plan of power distribution line. Based on it, SONEDE will make documents to explain the outline of the plan and collect opinions of residents from representatives of related areas, and then those opinions will be reflected in the plan of power distribution line.<br>(b) The comments from the citizens have been reflected on the compensation policy.   |
|                           | (3) Examination of Alternatives           | (a) Have alternative plans of the project been examined with social and environmental considerations?  | (a) Y                            | (a) A comparison analysis, taking into account environmental items, considering different sites and processes, including the zero option, has been implemented.   |
| 2 Pollution Control       | (1) Air Quality                           | (a) Is there a possibility that chlorine from chlorine storage facilities and chlorine injection facilities will cause air pollution? Are any mitigating measures taken?<br>(b) Do chlorine concentrations within the working environments comply with the country's occupational health and safety standards?   | (a) N<br>(b) Y                   | (a) Liquid chlorine solutions are used so no air pollution is anticipated.<br>(b) The plant will be built according to Tunisian specifications complying with applicable standards.   |
|                           | (2) Water Quality -1                      | (a) Do pollutants, such as SS, BOD, COD contained in effluents discharged by the facility operations comply with the country's effluent standards?<br>(b) Does untreated water contain heavy metals?   | (a) Y<br>(b) N                   | (a) The brine discharge into the sea is complying with the Tunisian standard NT 106-002.<br>(b) Almost all of heavy metals contained in brine discharged from the desalination plant originate in sea water, and is condensed to 100/45=2.22times. It, however, conforms to effluent quality standard. (for example: Zn++ in sea water = 38ug/l × 2.22 = 85ug/L; discharge <10,000ug/L; NT106-002).   |

### 8.7-1 Environmental Checklist

| Category              | Environmental Item      | Main Check Items   | Yes: Y<br>No: N   | Confirmation of Environmental Considerations<br>(Reasons, Mitigation Measures)  |
|-----------------------|-------------------------|--|---|---|
| 2 Pollution Control   | (2) Water Quality -2    | (c) Is there a possibility that soil runoff from the bare lands resulting from earthmoving activities, such as cutting and filling will cause water quality degradation in downstream water areas? If water quality degradation is anticipated, are adequate measures considered?  | (c) N   | (c) Plan of power distribution line is made by STEG. It is assumed that the line is led from 150kV national grid by aerial line, and tower interval is around 400m. Since it will be constructed on the flat olive field, large earth work and wood cutting are not necessary. Therefore, no impact on water quality and hydrology is anticipated.  |
|                       | (3) Wastes              | (a) Are wastes, such as sludge generated by the facility operations properly treated and disposed in accordance with the country's regulations?  | (a) Y   | (a) The membrane use is evaluated to 200m <sup>3</sup> /year, and these are considered as usual burnable wastes.  |
|                       | (4) Noise and Vibration | (a) Do noise and vibrations generated from the facilities, such as pumping stations comply with the country's standards?   | (a) Y   | (a) The pumping facilities will be located within the existing reservoir facilities, so no noise nor vibrations are anticipated.  |
|                       | (5) Subsidence          | (a) In the case of extraction of a large volume of groundwater, is there a possibility that the extraction of groundwater will cause subsidence?   | (a) N   | (a) Sea water will be the only feed water used, so there is no risk of subsidence.  |
| 3 Natural Environment | (1) Protected Areas     | (a) Is the project site or discharge area located in protected areas designated by the country's laws or international treaties and conventions? Is there a possibility that the project will affect the protected areas?  | (a) N   | (a) The project area is not including any RAMSAR area.  |
|                       | (2) Ecosystem           | (a) Does the project site encompass primeval forests, tropical rain forests, ecologically valuable habitats (e.g., coral reefs, mangroves, or tidal flats)?<br>(b) Does the project site or discharge area encompass the protected habitats of endangered species designated by the country's laws or international treaties and conventions?<br>(c) If significant ecological impacts are anticipated, are adequate protection measures taken to reduce the impacts on the ecosystem?<br>(d) Is there a possibility that the amount of water used (e.g., surface water, groundwater) by project will adversely affect aquatic environments, such as rivers? Are adequate measures taken to reduce the impacts on aquatic environments, such as aquatic organisms?<br>(e) Are adequate measures taken to prevent disruption of migration routes and habitat fragmentation of wildlife, and livestock?<br>(f) Is there a possibility that improved access by the project will cause impacts, such as destruction of forest, poaching, desertification, reduction in wetland areas, and disturbance of ecosystem due to introduction of exotic (non-native invasive) species and pests? Are adequate measures for preventing such impacts considered?<br>(g) In cases where the project site is located in undeveloped areas, is there a possibility that the new development will result in extensive loss of natural environments? | (a) Y<br>(b) Y<br>(c) Y<br>(d) N<br>(e) N<br>(f) N<br>(g) N | (a) The intake and discharge head are planned within a sea area including sea-grass meadows. The brine discharge will be done in an area with sea-grass meadows.<br>(b) The sea-grass "posidonia oceanica" is considered a species to be protected under the Barcelona conference,<br>(c) No significant impact on sea-grass meadows are anticipated, furthermore the discharge head allow for an efficient dilution of the brine, and offset mitigation measures are planned.<br>(d) The intake head is planned within a depth of 8m, and is designed to take water at 2 to 3m height from the bottom, within a speed of max 0.2m/s, so that no fish nor organisms should be sucked up.<br>(e) Plan of power distribution line is made by STEG. It is assumed that the line is led from 150kV national grid by aerial cable, tower interval is around 400m. No intercept of moving route of animals and livestock.<br>(f) Since it will be constructed on the flat olive farming field, large earth work and wood cutting are not necessary. Therefore, no impact on ecosystem is anticipated.<br>(g) Power distribution line will be constructed through developed environment, i.e. olive field. |
|                       | (3) Hydrology           | (a) Is there a possibility that the amount of water used (e.g., surface water, groundwater) by the project will adversely affect surface water and groundwater flows?  | (a) N   | (a) Sea water will be the only feed water used, so there will be no affection on surface water nor on groundwater flow.   |

### 8.7-1 Environmental Checklist

| Category              | Environmental Item         | Main Check Items   | Yes: Y<br>No: N  | Confirmation of Environmental Considerations<br>(Reasons, Mitigation Measures)   |
|-----------------------|----------------------------|--|--|--|
| 3 Natural Environment | (4) Topography and Geology | <p>(a) Is there a soft ground on the route of power transmission lines that may cause slope failures or landslides? Are adequate measures considered to prevent slope failures or landslides, where needed?</p> <p>(b) Is there a possibility that civil works, such as cutting and filling will cause slope failures or landslides? Are adequate measures considered to prevent slope failures or landslides?</p> <p>(c) Is there a possibility that soil runoff will result from cut and fill areas, waste soil disposal sites, and borrow sites? Are adequate measures taken to prevent soil runoff?</p>  | (a,b,c)<br>N   | (a,b,c) The route of power distribution line is not decided yet by STEG as of December 2014. The area within a radius of 15.5km has gentle slope of 0.6% from 5m to 100m in elevation. No fear of landslide and no large scale earth work is needed for aerial power distribution line.  |
| 4 Social Environment  | (1) Resettlement           | <p>(a) Is involuntary resettlement caused by project implementation? If involuntary resettlement is caused, are efforts made to minimize the impacts caused by the resettlement?</p> <p>(b) Is adequate explanation on compensation and resettlement assistance given to affected people prior to resettlement?</p> <p>(c) Is the resettlement plan, including compensation with full replacement costs, restoration of livelihoods and living standards developed based on socioeconomic studies on resettlement?</p> <p>(d) Is the compensations going to be paid prior to the resettlement?</p> <p>(e) Is the compensation policies prepared in document?</p> <p>(f) Does the resettlement plan pay particular attention to vulnerable groups or people, including women, children, the elderly, people below the poverty line, ethnic minorities, and indigenous peoples?</p> <p>(g) Are agreements with the affected people obtained prior to resettlement?</p> <p>(h) Is the organizational framework established to properly implement resettlement? Are the capacity and budget secured to implement the plan?</p> <p>(i) Are any plans developed to monitor the impacts of resettlement?</p> <p>(j) Is the grievance redress mechanism established?</p> | (a) N<br>(b) Y<br>(c) Y<br>(d) Y<br>(e) Y<br>(f) -<br>(g) -<br>(h) Y<br>(i) Y<br>(j) Y | <p>(a) The desalination plant is located with the public maritime domain, so no resettlement is anticipated. Also the pumping stations, reservoirs are planned within the existing reservoirs areas, so no resettlement is anticipated. Finally the distribution line route is planned along existing roads, so no resettlement is anticipated but some land acquisitions are required (ex: surge tanks).</p> <p>(b) No resettlement is anticipated but a stakeholder meeting has already been implemented with the purpose to explain about the project. Additional stakeholder meetings will be hold during the EIA.</p> <p>(c) No resettlement is anticipated but the compensation concept of the Tunisian law about expropriation is complying with the full replacement cost policy and a compensation procedure is established.</p> <p>(d) The payment of a compensation is a condition for expropriation according to Tunisian law.</p> <p>(e) The procedure for expropriation and land acquisition is described in the report of the preparatory survey for this project.</p> <p>(f) No resettlement is anticipated, so not applicable.</p> <p>(g) No resettlement is anticipated, so not applicable.</p> <p>(h) The land acquisition will be implemented by the land affairs department at SONEDE, the organisation is also including the participation of civil affairs court. In order to prepare an appropriate budget, the land acquisition scope has been estimated and is given in the report of the preparatory survey.</p> <p>(i) A monitoring plan (organization and monitoring form) including the state and progress of land acquisition has been established.</p> <p>(j) A complain management mechanism is established under the Tunisian law.</p> |

### 8.7-1 Environmental Checklist

| Category             | Environmental Item                           | Main Check Items   | Yes: Y<br>No: N  | Confirmation of Environmental Considerations<br>(Reasons, Mitigation Measures)  |
|----------------------|--|--|--|---|
| 4 Social Environment | (2) Living and Livelihood                    | <p>(a) Is there a possibility that the project will adversely affect the living conditions of inhabitants? Are adequate measures considered to reduce the impacts, if necessary?</p> <p>(b) Is there a possibility that the amount of water used (e.g., surface water, groundwater) by the project will adversely affect the existing water uses and water area uses?</p> <p>(c) Is there a possibility that diseases, including communicable diseases, such as HIV will be introduced due to immigration of workers associated with the project? Are adequate considerations given to public health, if necessary?</p> <p>(d) Is there a possibility that installation of structures, such as power line towers will cause a radio interference? If significant radio interference is anticipated, are adequate measures considered?</p> <p>(e) Is compensation for construction of transmission line, such like compensation for underline executed in accordance with domestic law.</p> | <p>(a) Y</p> <p>(b) N</p> <p>(c) N</p> <p>(d) N</p> <p>(e) Y</p> | <p>(a) The construction of the intake and discharge pipe will affect the fishing activities. A compensation plan based on the activity time loss is established.</p> <p>(b) Sea water will be the only feed water used, so there will be no impact on current water uses.</p> <p>(c) Since Sfax is developed as the second largest population city in Tunisia, and rapid immigration of population is not anticipated. It will be developed in accordance with the population increase. Therefore, occurrence of disease caused by immigration will not be anticipated.</p> <p>(d) There are existing power lines in the project area. Therefore, new facilities will not affect on the present situation of radio.</p> <p>(e) The power distribution line is constructed by STEG, and land acquisition and underline compensation will be conducted in accordance with the law of Tunisia.</p> |
|                      | (3) Heritage                                 | <p>(a) Is there a possibility that the project will damage the local archaeological, historical, cultural, and religious heritage? Are adequate measures considered to protect these sites in accordance with the country's laws?</p>  | <p>(a) N</p>   | <p>(a) The project area is not including the Thyna archaeological park. Registered archeologic ruins are not located in the project site.</p>   |
|                      | (4) Landscape                                | <p>(a) Is there a possibility that the project will adversely affect the local landscape? Are necessary measures taken?</p>  | <p>(a) N</p>   | <p>(a) The project is not located within a touristic area and existing high tension power line exists. Therefore, impact on landscape by the facilities is small.</p>   |
|                      | (5) Ethnic Minorities and Indigenous Peoples | <p>(a) Are considerations given to reduce impacts on the culture and lifestyle of ethnic minorities and indigenous peoples?</p> <p>(b) Are all of the rights of ethnic minorities and indigenous peoples in relation to land and resources respected?</p>  | <p>(a) -</p> <p>(b) -</p>  | <p>(a) There is no ethnic minorities within the project area.</p> <p>(b) Not applicable.</p>  |
|                      | (6) Working Conditions                       | <p>(a) Is the project proponent not violating any laws and ordinances associated with the working conditions of the country which the project proponent should observe in the project?</p> <p>(b) Are tangible safety considerations in place for individuals involved in the project, such as the installation of safety equipment which prevents industrial accidents, and management of hazardous materials?</p> <p>(c) Are intangible measures being planned and implemented for individuals involved in the project, such as the establishment of a safety and health program, and safety training (including traffic safety and public health) for workers etc.?</p> <p>(d) Are appropriate measures taken to ensure that security guards involved in the project not to violate safety of other individuals involved, or local residents?</p>   | <p>(a) Y</p> <p>(b) Y</p> <p>(c) Y</p> <p>(d) Y</p>              | <p>(a) The project will be implemented by SONEDE (public water supply company) and STEG (public power and gas supply company), so the Tunisian laws regarding working conditions will be enforced.</p> <p>(b) The project has been established considering present experience of SONEDE in the management of desalination facilities, and the project is not including any hazardous facility.</p> <p>(c) Upon completion of desalination plant, the plant maker will train the staff of SONEDE to the operation and maintenance of facilities.</p> <p>(d) The security guards will work from within the enclosed area of the facility and basically be at the guard post at the entrance of the plant. They will have to lay down their defence equipment into deposit at the guard post before leaving work.</p>  |

### 8.7-1 Environmental Checklist

| Category | Environmental Item                      | Main Check Items   | Yes: Y<br>No: N                  | Confirmation of Environmental Considerations<br>(Reasons, Mitigation Measures)   |
|----------|---|--|----------------------------------|--|
| 5 Others | (1) Impacts during Construction         | (a) Are adequate measures considered to reduce impacts during construction (e.g., noise, vibrations, turbid water, dust, exhaust gases, and wastes)?<br>(b) If construction activities adversely affect the natural environment (ecosystem), are adequate measures considered to reduce impacts?<br>(c) If construction activities adversely affect the social environment, are adequate measures considered to reduce impacts?<br>(d) If the construction activities might cause traffic congestion, are adequate measures considered to reduce such impacts?                           | (a) Y<br>(b) Y<br>(c) Y<br>(d) N | (a) Measures to reduce turbidity during construction of intake and discharge pipes, are planned.<br>(b) The living sea grass meadows will be destroyed by the construction of intake and discharge pipes. The development of artificial reefs is planned as a mitigation measure.<br>(c) As the fishing activities will be affected by the construction of intake and discharge pipes, a compensation plan based on activity time loss, has been established.<br>(d) The distribution line is planned along the existing roads, but the construction space will not include the pavement section, so no particular impact on traffic is anticipated. |
|          | (2) Monitoring                          | (a) Does the proponent develop and implement monitoring program for the environmental items that are considered to have potential impacts?<br>(b) What are the items, methods and frequencies of the monitoring program?<br>(c) Does the proponent establish an adequate monitoring framework (organization, personnel, equipment, and adequate budget to sustain the monitoring framework)?<br>(d) Are any regulatory requirements pertaining to the monitoring report system identified, such as the format and frequency of reports from the proponent to the regulatory authorities? | (a) Y<br>(b) Y<br>(c) Y<br>(d) Y | (a) A monitoring plan of the water quality and sea grass meadows during construction and operation, will be implemented.<br>(b) The items and methods of the monitoring program have been established according to Tunisian law on water quality and according to the expertise of the INSTM for the sea-grass, the frequencies have been set to monitor impacts during construction and operation.<br>(c) The monitoring organization is established around SONEDE, including the ANPE, the INSTM, and the UTAP.<br>(d) A monitoring form, easily usable by the PIU in SONEDE and defining format and frequency of reports, has been established.   |
| 6 Note   | Reference to Checklist of Other Sectors | (a) Where necessary, pertinent items described in the Dam and River Projects checklist should also be checked.   | (a) N                            | (a) This checklist is made based on JICA's forms of checklists for water supply, and power transmission and distribution lines.  |
|          | Note on Using Environmental Checklist   | (a) If necessary, the impacts to trans-boundary or global issues should be confirmed (e.g., the project includes factors that may cause problems, such as trans-boundary waste treatment, acid rain, destruction of the ozone layer, or global warming).   | (a) N                            | (a) There is no trans-boundary or global issues related to the project.  |

8.7-5

1) Regarding the term "Country's Standards" mentioned in the above table, in the event that environmental standards in the country where the project is located diverge significantly from international standards, appropriate environmental considerations are required to be made.

In cases where local environmental regulations are yet to be established in some areas, considerations should be made based on comparisons with appropriate standards of other countries (including Japan's experience).

2) Environmental checklist provides general environmental items to be checked. It may be necessary to add or delete an item taking into account the characteristics of the project and the particular circumstances of the country and locality in which the project is located.

***CHAPTER 9***

***LAND ACQUISITION AND RESETTLEMENT***

## **9.10-1 Documents delivered to Residents for Explanation about Power Transmission Line**

Letter from SONEDE to Sfax Governor : 2014/12/12

Original letter in Arabic,

Page 9.10-2

English translation,

Page 9.10-3

Appendices 1, 2, and 3 (English translation)

Page 9.10-4

Answer FAX of Sfax Governor to SONEDE : 2015/02/04

Page 9.10-8



تونس في 12 ديسمبر 2014

إلى السيد والي صفاقس

29036

**الموضوع:** - مشروع إنجاز محطة تحلية مياه البحر بسعة 200 ألف متر مكعب في اليوم بصفاقس الكبرى  
- حول ربط المحطة بالكهرباء

**المصاحب:** - ملحق عدد 1 حول المسار الأولي لخط الجهد العالي،

- ملحق عدد 2 حول وثيقة استشارة (الملاحظات و التساؤلات حول المشروع)

- ملحق عدد 3 حول العناصر الأساسية للمشروع،

تحية طيبة وبعد،

في إطار تدعيم تزويد صفاقس الكبرى بالماء الصالح للشرب، كما تعلمون برمجت الشركة الوطنية لاستغلال وتوزيع المياه إنجاز محطة لتحلية مياه البحر بسعة 100 ألف متر مكعب في اليوم كمرحلة أولى. وتبعا لذلك ستقوم الشركة التونسية للكهرباء و الغاز بجلب الطاقة الكهربائية اللازمة لكافة المنشآت التابعة للمشروع عن طريق مد خط كهربائي جهد عالي.

كما نفيد سيدتكم علما بأن الشركة التونسية للكهرباء و الغاز تقوم حاليا بإعداد الدراسات الضرورية لتحديد مسار خط الجهد العالي لربط محطة التحلية بالكهرباء. وعند الانتهاء من هذه الدراسة و تحديد المسار النهائي، سيتم إنجاز دراسة المؤثرات البيئية التي ستشمل منشآت محطة التحلية وخط الكهرباء ذات الجهد العالي من قبل مكتب دراسات مختص. وخلال الدراسة البيئية سيتم تنظيم يوم إعلامي للعموم قصد شرح كل تفاصيل المشروع و خاصة الجزء المتعلق بربط المحطة بالكهرباء.

وبهدف الإعلام المسبق للسكان المعنيين بهذا المشروع، تجدون هذا ملخصا للعناصر الأساسية للمشروع (ملحق عدد 3). كما نطلب من سيادتكم مدنا بملاحظاتكم و تساؤلاتكم بخصوص عناصر المشروع وذلك طبقا لوثيقة الاستشارة المصاحبة (ملحق عدد 2).

وحتى تتمكن من إدراج ملاحظاتكم في الدراسة البيئية للمشروع، الرجاء موافاتنا بإجاباتكم في أقرب الآجال. تقبلوا سيدي الوالي فائق عبارات التقدير و الاحترام.



شارع سليمان بن سليمان  
المطار II - تونس، 2092  
Av. Slimane Ben Slimane  
El Manar II - Tunis 2092

Tel : 79 33 10 00  
الخطوط الهاتفية  
Fax : 79 33 10 00  
E-mail : sonede@sonede.com.tn

البيتر التجاري: 83 83  
R.C. : 11892008  
Matrique Fiscal : 4455 J/A/M/000  
البريد الإلكتروني



Tunis, December 12, 2014.

To the attention of the Governor of Sfax

**Subject** : - Seawater desalination plant construction project with a capacity of 200,000 m<sup>3</sup>/d in the Grand Sfax.

- Connection of the desalination station to the HV power network of STEG

**PJ** : -Annex N°1 : Preliminary outline of the high voltage power line,

-Annex N°2: Survey form (comments and questions),

-Annex N°3: Project's key components.

Greetings,

In the framework of reinforcing the drinking water supply throughout the Grand Sfax, SONEDE has planned a construction project of a seawater desalination station with a capacity of 100,000 m<sup>3</sup>/d for the first phase. Electrical power required for the Project's different components will be transferred by means of a high voltage electrical line that will be built by STEG.

We would like to inform you that STEG is currently preparing all studies required for the choice of the high voltage power line's outline, which will feed power to the desalination station. Once all details are determined, an impact study covering the desalination plant and the high voltage line will be conducted by a specialized Consultant. In the course of this impact study, an open-to-the public information day will be held to explain the project's details and mainly the part related to the connection of the desalination plant to the HV power network.

Nevertheless, in order to provide preliminary information to concerned populations, we are summarizing below the project's key components (Annex 3) and we ask you to please share with us your comments or possible questions about these components, according to the Survey Form attached herewith (Annex 2).

In order to reflect all different statements and opinions about the Project and those that will be collected during the impact study, we hope to receive your answer in the near future.

Please accept Mr. Governor our best regards.

**Studies Central Manager**

**Adnen BOUBAKER**

(Attached 1) STEG Transmission line



Source: STEG

**Annex 2 Comments and questions concerning the Desalination Plant in Sfax**

Recipient: Sfax Agency, SONEDE

To the kind attention of Mr. Youssef Shel (email: [y.shel@sonede.com.tn](mailto:y.shel@sonede.com.tn), fax: 74297335)

Or Mr. Charfeddine Sliti (email: [c.sliti@sonede.com.tn](mailto:c.sliti@sonede.com.tn), fax: 71494185)

My comments about the Project of the Plant and the construction of the high voltage transmission line are the following:

I have the following comment:

.....

.....

.....

I don't have any comment

I have the following question:

.....

.....

.....

I have no question

Date: December ..., 2014

Name : M /Ms.....

Function/Title :.....

Delegation :.....

Occupation/Employment:.....

Tel:.....Fax:.....

Email:.....@.....

**Annex 3**  
**Seawater Desalination Plant Construction Project of Sfax**  
**Key Components:**

**1 Desalination Installations**

1.1 Components

- Seawater Desalination Plant
- Transmission pipelines (from the plant to water tanks)

1.2 Desalination Plant

- Ultimate Capacity: 200,000m<sup>3</sup>/day (phase I , 100,000m<sup>3</sup>/day)
- Location: Sfax Governorate, Delegation of Agareb, on the shore across from British Gas

1.3 Expected Results

- Increase the quantity of drinking water
- Improve the quality of drinking water

1.4 Expected operation date

- In the course of 2020

**2 Power Installations**

2.1 Required power: 40MW (phase I , 20MW)

2.2 Supply method (under study)

- The required power will be transmitted up to the Plant by means of a high voltage line from STEG's existing electrical lines (existing 150 kV line starting from Sfax towards the West)

**3 - Impacts induced by the high voltage line and compensation method**

3.1 Expected impacts

- The outline of the high voltage line has not been determined yet ; however the line will likely be oriented towards the North on an approximate distance of 16 km to join existing lines. The line will be mainly crossing olive groves, and no significant impact on buildings is expected (the temporary outline is shown in the Annex).

### 3.2 Compensation method

- Nearly 40 electrical towers will be required for the line construction. The acquisition of lands required for the installation of electrical towers will be carried out by STEG.
- Compensations for the acquisition of lands will be carried out according to the Tunisian Law which is in compliance with the Donor's guidelines in this regard.

## 4 Comments on this document

4.1 Please fill in the attached Annex 2 to share your possible comments and questions. If you have no comment and no question, please fill in the attached Annex 2 with the statements: "No Comments, No questions".

4.2 Recipient: SONEDE, Sfax Regional Department or Desalination and Environment Department.

4.3 Deadline: December 31, 2014

Annex 2 related to comments may be filled in by the regional and local authorities (Delegation, Equipment, telecoms, ONAS ...) or any other person that is likely to be affected by the passage of the high voltage power line.

Answer FAX of Sfax Governor to SONEDE  
(Check at No question on the matter.)

04-02-2015 17:49

GOUVERNORAT DE Sfax  
Tél. NO. 218 71 494185

74 403 625 P.01/01  
04 Feb. 2015 11:37 P 3

Annexe 2 : Commentaires et questions à propos du projet de la station de dessalement de Sfax

Destinataire: Direction régionale de Sfax ou Direction de dessalement et d'environnement (SONEDE) (www.sonede.com.tn, fax: 74297335)  
Ou M. Charfeddine Siliti (email : [c.siliti@sonede.com.tn](mailto:c.siliti@sonede.com.tn) fax : 71494185)

Mes commentaires à propos du projet de la centrale et de la construction de la ligne à haute tension sont les suivants:

J'ai le commentaire suivant:

.....

.....

.....

Je n'ai pas de commentaire

J'ai la question suivante:

.....

.....

.....

Je n'ai pas de question

Date: le ..... décembre 2014  
Nom : M /Mme.....  
Fonction/Titre : .....

Délégation : .....

Occupation/Emploi : .....

Tel: ..... Fax: .....

Email: .....@.....

الوالي  
محمد شابي



***CHAPTER 10***  
***IMPLEMENTATION PLAN***

## **10.3-1 TOR for Consulting Service (draft)**

### **Sfax Sea Water Desalination Plant Construction Project in the Republic of Tunisia Terms of Reference on Consulting Service**

#### **1. Background**

One half of Tunisia belongs to semi-dry climate. The annual average of the rainfall is about a little less than 500mm. Consequently, groundwater contributes to about 40% of water intake. The water supply system in Tunisia has been developed in accordance with an economic growth of 4% in average during the last 15 years. The service area of water supply covers 97.8% in total, i.e. 100% of urban areas, 93.4% of rural areas (SONEDE, 2012). In Tunisia, the Ministry of Agriculture defines the water sector policy. Water supply in rural area is based on the communal faucet method and is operated by the Ministry of Agriculture. SONEDE (Société Nationale d'Exploitation et de Distribution des Eaux) is responsible for water supply in urban areas and in some rural areas using individual supply systems including water supply for domestic use and development, and the maintenance of conveyance and transmission systems.

Greater Sfax is the second largest city in Tunisia with an approximate population of about 621000. Water supply volume amounts to about 190,000m<sup>3</sup>/day for SONEDE's coverage area with a served population of about 810,000 in 2012. Because of rapid increase in population at 1.37% per annum over the last ten years, it is projected that serious water shortage will happen in 2018, and the development of a new water source is requested. Greater Sfax currently relies on groundwater in the central-western region for its water supply. However, it is projected that water supply from the region will be decreased in order to spare groundwater resources in the central-western regions and the increase of demand in the region. In order to cope with this situation, it is requested to develop water resource only for Sfax governorate and to provide related infrastructure. SONEDE studied the construction of a sea water desalination plant in Sfax in the feasibility study for water supply in south regions conducted in 2005.

SONEDE also prepared the Strategic Plan in 2013 to enhance water supply capacity and to improve water quality by 2030. In the plan, the Sfax Desalination Plant Construction Project was planned. In this framework, the preparatory survey was conducted with JICA funding. Based on the survey, this project was formulated.

#### **2. Objectives of Consulting Services**

The objective of the consulting services is to provide design, evaluation of bids, and construction supervision ensuring the design and the construction quality and fairness, and achieving the efficient project implementation.

#### **3. Scope of Consulting Services**

The scope of consulting services on Sfax Sea Water Desalination Plant Construction Project in the Republic of Tunisia cover designing, tender assistance, and management of construction services for 7



lots and eight (08) contracts. Each lot is explained below followed by a description of services to provide:

(1) Project Component

The project consists of 7 lots. Each lot is explained as follows:

i) Lot 1: Construction of the Seawater Desalination Plant

(a) Sea Water Desalination Plant

- a1) Land Acquisition: Approximately 20ha
- a2) Desalination Method: Reverse Osmosis Membrane Method (RO)
- a3) Treated Water: 100,000m<sup>3</sup>/d
- a4) RO Units: 25,000m<sup>3</sup>/day × 4 units
- a5) Transmission Pump Facility 100,000m<sup>3</sup>/d
- a6) Required Electricity: Approximately 20MVA

(b) Sea Water Intake Pipe

- b1) Intake Volume: 222,200m<sup>3</sup>/d (capable of flowing 444,400 m<sup>3</sup>/d for Phase 2)
- b2) Pipe Material: HDPE
- b3) φ2000mm x 2 (HDPE), L=3.6km (Buried Pipe: 3.2 km offshore, and 0.4 km onshore))
- b4) Transmission pump facility 100,000 m<sup>3</sup>/d
- b5) Submerged Water Intake Tower 2 units

(c) Brine Effluent Pipe

- c1) Effluent Volume: 122,000m<sup>3</sup>/d (capable of flowing 244,000 m<sup>3</sup>/d for Phase 2)
- c2) Pipe Material: HDPE
- c3) φ1800mm, L=4.4km (Buried Pipe: 4.0 km offshore, 0.4 km onshore))
- c4) Submerged Water Effluent Tower 1 unit

ii) Lot 2: Procurement of Pipes

(a) Procurement of Pipe for Transmission to be installed for Lot 4

- a1) Pipe Material: Ductile Cast Iron Pipe
- a2) φ1400mm: L=26.1km (Desalination Plant - PK11 Reservoir)
- a3) φ1000mm: L=6.1km (PK10 Reservoir)
- a4) φ800mm: L=4.8km (PK10 Reservoir—PK14 Reservoir)
- a5) φ800mm: L=9.4km (PK14 Reservoir—Sidi Salah EH Reservoir)
- a6) φ400mm: L=2.9km (PK11 Reservoir—Bou Merra Reservoir)

This lot can be subject of two contracts (sub-lot 2.1 and sub-lot 2.2)

iii) Lot 3: Procurement of Valves and Other Equipment

(a) Procurement of valves and other equipment to be installed for Lot 4

iv) Lot 4: Installation of Pipeline including valves and other equipment

- (a) Construction of Transmission Pipeline and valves whose materials are procured through Lot 2 and Lot 3.
  - (b) Construction of One-Way Surge Tanks or other anti-water-hammer equipment
    - b1) Desalination Plant Site - PK11 Reservoir  
Tank dimension: diameter 10m x height 15m, site: 20m x 30m x 2 locations
- v) Lot 5: Construction of Reservoir
- (a) Construction of Reservoir
    - a1) Capacity of 5,000m<sup>3</sup> existing precinct of Bou Merra Reservoir
  - (b) Construction of Receiving and Mixing Chambers
    - b1) PK11: 9.0 W x 15.0 L x 5.0 D
    - b2) Bou Merra: 4.0W x 3.0L x 5.0D
    - b3) PK10: 7.0W x 10.0L x 5.0D
    - b4) PK14: 7.0W x 7.0L x 5.0D
    - b5) Sidi Salah EH: 6.0W x 5.0L x 5.0D

(internal dimension; W: width, L: length, D: water depth; unit: m)
- vi) Lot 6: Construction of Pumping Stations
- (a) Pumping Station
    - a1) Relay Pumping Station: 3 (in PK10, PK11, and PK14 Reservoir Sites)
- vii) Lot 7: Power Transmission Construction and Power Connection Works(Executed by STEG)
- (a) Construction of electrical power supply facility necessary for the Sea Water Desalination Plant
    - a1) power line
    - a2) power line tower
    - a3) facility for transformation of energy
    - a4) other necessary facilities
  - (b) Electrical power connection work (pumping stations of Pk10, Pk11 and Pk14)
  - (c) Assistance for the installation of Sea Water Desalination Plant electrical facility

The Consultants shall include the following items as subjects in their engineering works required for the facilities stipulated in (1) Project Component:

- (a) Associated reservoirs, all piping, valves, special parts, pumping mains, overflow pipeline, scour pipes etc. in construction of pumping stations;
- (b) Associated inlet chamber, over flow pipeline, pumping main and other ancillary structures in construction of pumping stations;
- (c) Roads and other networks, street lighting, water supply, sanitation, fencing compound wall, etc., within the premises of the water treatment plant and reservoirs; and
- (d) River/Canal crossings, pipe supports, cradle support, thrust and anchor blocks, valve chambers, road crossings, fabrication of manholes, expansion joints, and installation of valves along the outline.

(2) Detailed description of the consulting services

Design and preparation of bidding documents

- 1) The Consultant shall perform the duties for designing and preparation of the bidding documents according to contracts to be signed between SONEDE and the Consultant. The conceptual design for Lots 1 and 6, and the detailed design for Lots 2 to 5 and Lot 7 shall be performed by the responsibility of the Consultant. Standard Bidding Documents of JICA shall be applied for International Competitive Bidding. The Consultant shall function with the authorities and responsibilities of the Engineer in case it is provided in this Project's Contract Documents. In this context, the Consultant shall;
  - a) Prepare hydraulic, structural, mechanical and electrical systems designs;
  - b) Prepare specifications for civil works, mechanical and electrical equipment, including instrumentation, control and regulation systems;
  - c) Prepare tender drawings for civil work;
  - d) Prepare general arrangement drawings incorporating equipment layout, piping layout and instrumentation and control schemes for tender purpose;
  - e) Prepare technical specifications for electrical drawings such as single line diagrams, equipment layout, cable networks layout, and lighting networks layout;
  - f) Prepare cost estimate for civil works and mechanical and electrical equipment and works;
  - g) Prepare process flow sheets, process design, process criteria, hydraulic diagram and design; civil and structural design criteria, mechanical and electrical and instrumentation system requirements;
  - h) Conduct surge suppression studies and recommend appropriate surge protection system; and
  - i) Design arrival hydraulic structures and calculation of needs.
  
- 2) The Consultant shall carry out process design and engineering studies for Lot 1 including the following:
  - a) Prepare conceptual design (i.e. process, hydraulic, mechanical and electrical equipment designs);
  - b) Prepare specifications;
  - c) Prepare sea water desalination plant flow chart with its different levels;
  - d) Prepare sea water desalination plant preliminary hydraulics with control levels;
  - e) Prepare sea water desalination plant implantation plans; and
  - f) Prepare process and hydraulic designs, parameters, structural design criteria, mechanical and electrical system requirements.
  
- 3) The Consultants shall provide assistance in Pre-Qualification (PQ) for Lot 1 (based on the JICA's standard document related to prequalification). The Consultant shall assist SONEDE to;
  - a) Define technical and financial requirements, capacity and/or experience for PQ criteria taking into consideration technical features of the Project;
  - b) Prepare PQ documents in accordance with the Standard Prequalification Documents under

- Japanese ODA Loans;
- c) Carry out PQ announcement, addendum/corrigendum, and clarifications to bidders' queries;
  - d) Evaluate PQ applications in accordance with the criteria set forth in PQ documents; and
  - e) Prepare a PQ evaluation report for approval by the competent committee.
- 4) The Consultants shall provide assistance in preparation of bidding documents. The Consultant shall assist SONEDE to;
- a) Prepare bidding documents in accordance with the latest version of Standard Bidding Documents under Japanese ODA Loans for Procurement ("PLANT" for Lots 1 and 6, "GOODS" for Lot 2, "WORKS" for Lots 4 and 7), together with all relevant technical document such as specifications, drawings and other documents, which are prepared during the detailed design period; and
  - b) Prepare bidding documents which include i) the clauses that the Contractors is to comply with the requirement of the Environmental Management Plan (EMP) and JICA Guidelines for environmental and social considerations (April 2010) (JICA Environmental Guidelines), ii) the specification clearly stipulating the safety requirements in accordance with the laws and regulations in Tunisia, relevant international standards (including guidelines of international organization), if any, and also in consideration of "the Guidance for the Management of Safety for Construction Works in Japanese ODA Projects of JICA," iii) the requirement to furnish a safety plan to meet the safety requirements, iv) the requirement for the personnel for key positions to include an accident prevention officer, and v) the requirement to submit method statements of safety to SONEDE and the consultant at the construction stage.

#### Tendering Assistance

The Consultants shall provide assistance to the tendering procedure listed below in accordance with the JICA Guidelines for Procurement under Japanese ODA Loans (April 2012). The Consultant shall assist SONEDE to;

- a) Carry out issuing bid advertising, conducting pre-bid conferences, issuing codicils, and clarifications to bidders' inquiries;
- b) Evaluate bids in accordance with the criteria set forth in the bidding documents. In such evaluation, the Consultant shall carefully confirm that bidders' submissions in their technical proposal including, but not limited to, site organization, mobilization schedule, method statement, construction schedule, safety plan, and EMP have been prepared in harmony each other and will meet such requirements set forth in applicable laws and regulations, specifications and other parts of the bidding documents;
- c) Prepare bid evaluation reports for approval of the competent committee;
- d) Carry out contract negotiation by preparing agenda and facilitating negotiations including preparation of minutes of negotiation meeting; and
- e) Prepare a draft and final contract agreement.

### Construction Supervision

#### 1) Lots 1 and 6

The Consultant shall perform his duties during the implementation period of the contracts to be executed by SONEDE and the Contractors (Lots 1 and 6). In this context, the Consultant shall;

- a) Act as SONEDE's Representative to execute construction supervision and contract administration services in accordance with the power and authority to be delegated by SONEDE;
- b) Provide assistance to SONEDE concerning variations and claims which are to be ordered/issued at the initiative of SONEDE;
- c) Advise SONEDE on resolution of any dispute with the Contractors;
- d) Issue instructions, approvals and notices as appropriate;
- e) Provide recommendations to SONEDE for acceptance of the Contractor's performance security, advance payment security and required insurances;
- f) Assess adequacy of all inputs such as materials, labor and equipment provided by the Contractors;
- g) Check and approve the Contractors' method of work, including site organization, program of performance, quality assurance system, safety plan and environmental monitoring plan so that the requirements set forth in the applicable laws and regulations, the specifications or other parts of the contract are to be duly respected;
- h) Monitor as appropriate physical and financial progress, and take appropriate action to expedite progress if necessary, so that the time for completion set forth in the contract will be duly respected;
- i) Explain and/or adjust ambiguities and/or discrepancies in the Contract Documents and issue any necessary clarifications or instructions;
- j) Review and approve the Contractor's design for the works to be constructed, working drawings, shop drawings and drawings for temporary works;
- k) Liaise with the appropriate authorities to ensure that all the affected utility services are promptly relocated;
- l) Carry out field inspections on the Contractor's setting out of the works in relation to original points, lines and levels of reference specified in the contract;
- m) Organize, as necessary, management meetings with the Contractors to review the arrangements for future work. Prepare and deliver minutes of such meetings to SONEDE and the Contractors;
- n) Supervise the works so that all the contractual requirements are met by the Contractor, including those in relation to i) quality of the works, ii) safety and iii) protection of the environment. Confirm that an accident prevention officer proposed by the Contractor is duly assigned at the project site;
- o) Supervise field tests, sampling and laboratory test to be carried out by the Contractors;
- p) Inspect construction methods, equipment to be used, workmanship at the site, and attend factory inspection and manufacturing tests in accordance with SONEDE's Requirements;
- q) Verify payment applications submitted by the Contractor;
- r) Coordinate the works among different contractors employed for the Project;

- s) Modify the Employer's Requirements as may be necessary in accordance with the actual site conditions, and issue variation orders with the approval of SONEDE (including necessary actions in relation to the works performed by other contractors working for other projects or other facility operators, if any);
- t) Carry out timely reporting to SONEDE for any inconsistency in executing the works and suggesting appropriate corrective measures to be applied;
- u) Inspect, verify and comment on claims issued by the Contractors;
- v) Supervise Pre-commissioning carried out by the Contractors, check and comment on the Contractor's Pre-commissioning report, and suggest the Completion Certificate as specified in the contract;
- w) Supervise Commissioning and Guarantee Test carried out by the Contractors, check and comment on the Contractor's report on the Commissioning and Guarantee Test, and suggest the Operational Acceptance Certificate as specified in the Contract;
- x) Provide periodic inspection services during defect liability period and if any defects are noted, instruct first SONEDE and second the Contractors to rectify;
- y) Check and suggest the approval of as-built drawings prepared by the Contractors; and
- z) Check and suggest the approval of the operation and maintenance manual prepared by the Contractor.

2) Lots 4 and 5

The Consultant shall perform his duties during the contract implementation period of the contracts to be executed by SONEDE and the Contractors (Lots 4 and 5). In this context, the Consultant shall;

- a) Act as SONEDE's Representative to execute construction supervision and contract administration services in accordance with the power and authority delegated by SONEDE;
- b) Provide assistance to SONEDE concerning variations and claims which are to be ordered/issued at the initiative of SONEDE;
- c) Advise SONEDE on resolution of any dispute with the Contractor;
- d) Issue instructions and notices, and suggest approvals as appropriate;
- e) Provide recommendation to SONEDE for acceptance of the Contractors' safety plan, performance security, advance payment security and required insurances;
- f) Evaluate compliance of all inputs such as equipment, working staff, and materials provided by the Contractors;
- g) Provide commencement order to the Contractors;
- h) Check and approve the Contractors' method of work, including site organization, program of performance, quality assurance system, safety plan, method statement of safety and environmental monitoring plan so that the requirements set forth in the applicable laws and regulations, the specifications or other parts of the contract are to be duly respected;
- i) Regularly monitor physical and financial progress, and take appropriate action to expedite progress if necessary, so that the time for completion set forth in the contract will be duly respected by the Contractor;
- j) Explain and/or adjust ambiguities and/or discrepancies in the Contract Documents and issue

any necessary clarifications or instructions. Issue further drawings and give instructions to the Contractors for any works which may not be sufficiently detailed in the contract documents, if any;

- k) Review and approve the Contractor's working drawings, shop drawings and drawings for temporary works;
- l) Liaise with the appropriate authorities to ensure that all the affected utility services are promptly relocated;
- m) Carry out field inspections on the Contractor's setting out of the works in relation to original points, lines and levels of reference specified in the contract;
- n) Organize, as necessary, management meetings with the Contractors to review the arrangements for future work. Prepare and deliver minutes of such meetings to SONEDE and the Contractors;
- o) Supervise the works so that all the contractual requirements are met by the Contractors, including those in relation to i) quality of the works, ii) safety and iii) protection of the environment. Confirm that an accident prevention officer proposed by the Contractors is duly assigned at the project site. Require the contractors to take appropriate remedies if any questions are recognized regarding the safety measures;
- p) Supervise field tests, sampling and laboratory test to be carried out by the Contractors;
- q) Inspect the construction method, equipment to be used, workmanship at the site, and attend shop inspection and manufacturing tests in accordance with the specifications;
- r) Survey and measure the work output performed by the Contractors verify statements submitted by the Contractor and issue payment certificates such as interim payment certificates and final payment certificate as specified in the contract;
- s) Coordinate the works among different contractors employed for the Project;
- t) Modify the designs, technical specifications and drawings, relevant calculations and cost estimates as may be necessary in accordance with the actual site conditions, and issue variation orders (including necessary actions in relation to the works performed by other contractors working for other projects, if any);
- u) Carry out timely reporting to SONEDE for any inconsistency in executing the works and suggesting appropriate corrective measures to be applied;
- v) Inspect, verify and approve or disapprove claims issued by the parties to the contract (i.e. SONEDE and Contractors) in accordance with the civil works contract;
- w) Perform the inspection of the works, including Test on Completion, and to issue certificates such as the Taking-Over Certificate, Performance Certificate as specified in the contract;
- x) Supervise the preliminary operation conducted by the Contractors, check and approve the initial operation report issued by the Contractors and issue the completion report as specified in the Contract;
- y) Supervise commissioning and carry out tests during the commissioning, if applicable;
- z) Provide periodic and/or continuous inspection services during defects notification period and if any defects are noted, instruct the Contractors to rectify;
- aa) Prepare as-build drawings for the parts of the works constructed in accordance with the design provided by SONEDE;
- ab) Check and certify as-built drawings for the parts of the works designed by the Contractors, if

any; and

ac) Prepare an operation and maintenance manual for the works constructed in the Project.

3) Lot 7

The Consultant shall perform the following tasks throughout the execution of the Contract between SONEDE and STEG (Lot 7). In this regard, the Consultant shall;

- a) Monitor the progress of works carried out by STEG; and
- b) Coordination with STEG.

Safety measures

The Consultants shall;

- a) Review the safety plans submitted by the contractors securing the safety during the construction. (Refer to Paragraph (2), Section 4.02 Scope of the Project and of the Consulting Services of the Guidelines for the Employment of Consultants under Japanese ODA Loans, March 2009), and require them to submit the revision if necessary; and
- b) Confirm that an accident prevention officer proposed by the contractor is duly assigned at the project site during the supervision of the construction works and ensure the work is carried out according to the safety plan as well as the safety measures prescribed in the Program. If Consultants recognize any questions regarding the safety measures in general including the ones mentioned above, the Consultants shall requires the contractors to make appropriate improvements.

Facilitation of implementation of Environmental Management Plan (EMP) and Environmental Monitoring Plan (EMoP)

The Consultant shall;

- a) Update EMP as appropriate;
- b) Assist SONEDE in dissemination and explanation of additionally confirmed and identified environmental issues to public including holding public consultations;
- c) During the preparation of bidding documents, clearly identify environmental responsibilities as explained in the EIA and EMP;
- d) Assist SONEDE to review the Construction Contractor's Environmental Program to be prepared by the contractor in accordance with EMP, relevant plans and JICA Environmental Guidelines and to make recommendations to SONEDE regarding any necessary amendments for its approval;
- e) Assist SONEDE to implement the measures identified in the EMP;
- f) Monitor the effectiveness of EMP and negative impacts on environment caused by the construction works and provide technical advice, including a feasible solution, so that SONEDE can improve situation when necessary;
- g) Assist SONEDE in monitoring the compliance with conditions stated in the Environmental Permit Certification (EPC) and the requirements under EMP and JICA Environmental Guidelines;
- h) Assist SONEDE in the capacity building of SONEDE staff on environmental management



through on-the-job training on environmental assessment techniques, mitigation measure planning, supervision and monitoring, and reporting.

#### Technology transfer

The Consultant shall carry out the technology transfer as an important aspect in design and supervision works. The Consultant shall provide the opportunity to SONEDE officers and staffs to be involved in the working team of the Consultant during the designing, contract administration and supervision works for their capacity building wherever possible. If requested by SONEDE, the Consultant shall brief and demonstrate the survey and design procedure, the construction supervision and contract management process and procedures. The consultant shall assist SONEDE and its staff to build their capacity as a part of on the job training under the Project.

#### **4. Man-Month Schedule and Expected Time Schedule**

The consultants will be engaged over 87 months as a consulting service period. The team shall comprise Foreign and Local Professional Staff with man-month presented below.

| No   | Position   | Man-Month        |                  |                  |              |
|--|--|------------------|------------------|------------------|--------------|
|  |  | DD <sup>1)</sup> | TA <sup>2)</sup> | CS <sup>3)</sup> | Total        |
| <b>Foreign Professional Staff</b>                          |  |                  |                  |                  |              |
| 1  | Team Leader  | 12.0             | 10.0             | 35.5             | 57.5         |
| 2  | Desalination Plant Process Engineer                | 9.0              | 4.0              | 18.5             | 31.5         |
| 3  | Civil Engineer                                     | 12.0             | 4.0              | 33.0             | 49.0         |
| 4  | Pipeline Engineer                                  | 12.0             | 1.5              | 28.0             | 41.5         |
| 5  | Mechanical Engineer (Desalination Plant)           | 4.0              | 3.5              | 9.5              | 17.0         |
| 6  | Mechanical Engineer (Transmission Pumps)           | 3.0              | 2.0              | 7.0              | 12.0         |
| 7  | Electrical Engineer                                | 3.0              | 3.5              | 9.0              | 15.5         |
| 8  | Instrumentation Engineer                           | 3.0              | 2.0              | 9.0              | 14.0         |
| 9  | Structural Engineer                                | 6.0              | 0.0              | 2.0              | 8.0          |
| 10   | Contract Specialist                                | 5.0              | 5.5              | 5.0              | 15.5         |
| 11   | Quantity Surveyor                                  | 4.0              | 0.0              | 34.0             | 38.0         |
| 12   | Specification specialist                           | 4.0              | 0.0              | 0.0              | 4.0          |
| <b>Subtotal: Foreign Professional Staff</b>                |  | <b>77.0</b>      | <b>36.0</b>      | <b>190.5</b>     | <b>303.5</b> |
| <b>Local Professional Staff</b>                            |  |                  |                  |                  |              |
| 1  | Deputy Team Leader                                 | 13.0             | 14.0             | 36.5             | 63.5         |
| 2  | Environmental Specialist                           | 2.0              | 1.0              | 38.0             | 41.0         |
| 3  | Geo-technical Engineer                             | 3.0              | 0.0              | 3.0              | 6.0          |
| <b>Lot 1. Construction of Sea Water Desalination Plant</b> |  |                  |                  |                  |              |
| 4  | Resident Engineer 1 / Civil Engineer (1) for Lot 1 | 9.0              | 0.0              | 48.0             | 57.0         |
| 5  | Civil Engineer (2) for Lot 1                       | 0.0              | 0.0              | 29.0             | 29.0         |
| 6  | Mechanical Engineer for Lot 1, 6                   | 4.0              | 0.0              | 9.0              | 13.0         |
| 7  | Electrical Engineer for Lot 1, 6, 7                | 3.0              | 0.0              | 9.0              | 12.0         |
| 8  | Structural Engineer for Lot 1, 4, 5, 6             | 4.0              | 0.0              | 3.0              | 7.0          |

|  |  |       |       |        |        |
|--|--|-------|-------|--------|--------|
| 9  | Architect  | 4.0   | 0.0   | 4.0    | 8.0    |
| 10   | Building Utilities Engineer                              | 3.0   | 0.0   | 4.0    | 7.0    |
| 11   | Quantity Surveyor for Lot 1                              | 0.0   | 0.0   | 33.0   | 33.0   |
| Lot 2 & 3 Procurement of Pipes / Valves and Other Equipment<br>Lot 4. Construction of Pipeline |  |       |       |        |        |
| 12   | Resident Engineer 2 / Civil Engineer (1) for Lot 2, 3, 4 | 12.0  | 0.0   | 33.0   | 45.0   |
| 13   | Civil Engineer (2) for Lot 2, 3, 4                       | 10.0  | 0.0   | 32.0   | 42.0   |
| 14   | Procurement Specialist                                   | 4.0   | 0.0   | 0.0    | 4.0    |
| 15   | Quantity Surveyor for Lot 2, 3, 4                        | 0.0   | 0.0   | 32.0   | 32.0   |
| Lot 5 & 6. Reservoirs/Pump Facility Construction   |  |       |       |        |        |
| 16   | Resident Engineer 3 / Civil Engineer (1) for Lot 5, 6    | 8.0   | 0.0   | 33.0   | 41.0   |
| 17   | Civil Engineer (2) for Lot 5, 6                          | 6.0   | 0.0   | 30.0   | 36.0   |
| 18   | Quantity Surveyor for Lot 5, 6                           | 0.0   | 0.0   | 30.0   | 30.0   |
| <b>Subtotal: Local Professional Staff</b>  |  | 85.0  | 15.0  | 406.5  | 506.5  |
| Local support staff  |  |       |       |        |        |
| 1  | Assistant Engineer                                       | 13.0  | 14.0  | 69.0   | 96.0   |
| 2  | Inspector/Surveyor                                       | 0.0   | 0.0   | 156.0  | 156.0  |
| 3  | CAD Operator   | 60.0  | 0.0   | 36.0   | 96.0   |
| 4  | Interpreter/Translator                                   | 29.0  | 16.0  | 86.0   | 131.0  |
| 5  | Office Manager   | 13.0  | 14.0  | 36.0   | 63.0   |
| 6  | Accountant   | 12.0  | 0.0   | 36.0   | 48.0   |
| 7  | Clerk  | 12.0  | 0.0   | 36.0   | 48.0   |
| 8  | Office Boy   | 13.0  | 14.0  | 36.0   | 63.0   |
| <b>Subtotal: Local Support Staff</b>   |  | 152.0 | 58.0  | 491.0  | 701.0  |
| <b>Total Technical and support staff</b>   |  | 314.0 | 109.0 | 1088.0 | 1511.0 |

- 1) Conceptual Design and Detailed Design
- 2) Tendering Assistance
- 3) Construction Supervision

All technical and support staff required for the mission must be provided by the Consultant and includes the following profiles.

It is envisaged that the Consultant will provide adequate Technical and Administrative supporting staff. It is the Consultant's responsibility to select the optimum team and to propose the professionals which are believed to the best meets and needs of SONEDE without exceeding total man-month proposed for each category.

## 5. Basic professional requirements of key expert

The key expert requirements with qualification and experience for each position are given in the table below.

### (1) Foreign Professional Staff

| Position                                 | Minimum requirement  |
|--|--|
| Team Leader                              | <u>Education</u><br>Master Degree in civil engineering or construction management, or a national-registered professional engineer in his country.<br><u>Professional Experience</u><br>At least 20 years professional experience including 18 years at least in infrastructure. Experience of team leader for 5 or more projects in the field of water and sewerage, each of which is amounted at a project cost of more than 30 million US dollars. |
| Desalination Plant Process Engineer      | <u>Education</u><br>Master Degree in civil engineering or a national-registered professional engineer in his country.<br><u>Professional Experience</u><br>At least 10 years professional experience including at least 8 years as a plant process engineer. Experience on desalination plant for 2 or more projects.  |
| Civil Engineer                           | <u>Education</u><br>Master Degree in civil engineering or a national-registered professional engineer in his country.<br><u>Professional Experience</u><br>At least 10 years' professional experience including at least 8 years in development. Experience during construction period for 3 or more projects in the field of water and sewerage.  |
| Pipeline Engineer                        | <u>Education</u><br>E Bachelor's Degree in civil engineering or mechanical engineering..<br><u>Professional Experience</u><br>At least 10 years professional experience including at least 8 years in the field of pipeline design/construction. Experience during construction period of pipeline for 3 or more projects with a total period of 3 or more years.  |
| Mechanical Engineer (Desalination Plant) | <u>Education</u><br>Bachelor's Degree in civil engineering or mechanical engineering.<br><u>Professional Experience</u><br>At least 10 years professional experience including at least 8 years of experience in the design and/or construction of water treatment plants. Experience on desalination plant for 2 or more projects.  |
| Mechanical Engineer (Transmission Pumps) | <u>Education</u><br>Bachelor's Degree in mechanical engineering.<br><u>Professional Experience</u><br>At least 10 years professional experience including at least 8 years in the design and/or construction of pumping stations. Experience during construction period of pumping station for 3 or more projects with a total period of 3 or more years.  |
| Electrical Engineer                      | <u>Education</u><br>Bachelor's Degree in electrical engineering.<br><u>Professional Experience</u><br>At least 10 years professional experience including at least 8 years in the design and/or construction of desalination plants and pumping station. Experience during construction period of desalination plant and pumping station for 5 or more projects with a total period of 3 or more years.  |
| Instrumentation Engineer                 | <u>Education</u><br>Bachelor's Degree in electrical engineering.<br><u>Professional Experience</u>   |

|                          |  |
|--------------------------|--|
|                          | At least 10 years professional experience including at least 8 years in instrumentation engineering for any plant. Experience in the operation of desalination plant on 3 or more years.   |
| Structural Engineer      | <u>Education</u><br>Master Degree in civil engineering or a national-registered professional engineer in his country.<br><u>Professional Experience</u><br>At least 10 years professional experience including at least 8 years in the design and/or construction of desalination plant and pumping stations. Experience during construction period of desalination plants and pumping stations for 5 or more projects with a total period of 3 or more years. |
| Contract Specialist      | <u>Education</u><br>Bachelor's Degree in engineering or related field.<br><u>Professional Experience</u><br>At least 10 years professional experience including at least 8 years as a contract specialist for any type of plants or infrastructure development. At least 5 or more projects as a contract specialist.  |
| Quantity Surveyor        | <u>Education</u><br>Bachelor's Degree in engineering or related field.<br><u>Professional Experience</u><br>At least 10 years professional experience including at least 8 years as a quantity surveyor or relevant specialist for any type of plants or infrastructure development. At least 5 or more projects for surveying quantity.   |
| Specification Specialist | <u>Education</u><br>Bachelor's Degree in engineering or related field.<br><u>Professional Experience</u><br>Preferably more than 10 years, at least 8 years' professional experience as a specification specialist or engineer for any type of plants or infrastructure development. At least 5 or more projects as a specification specialist.  |

(2) Local Professional Staff

| Position                   | Minimum requirement   |
|----------------------------|---|
| (responsible for all lots) |   |
| Deputy Team Leader         | <u>Education</u><br>Master Degree in civil engineering or construction management, or a national-registered professional engineer in his country.<br><u>Professional Experience</u><br>At least 20 years professional experience of infrastructure development. Experience of team leader for 5 or more projects in the field of water and sewerage.                                |
| Environmental Specialist   | <u>Education</u><br>Master Degree in civil/environmental engineering or related fields, or a national-registered professional engineer in his country.<br><u>Professional Experience</u><br>At least 20 years professional experience of environmental infrastructure development. Experience during construction period for 5 or more projects in the field of water and sewerage. |
| Geo-technical Engineer     | <u>Education</u><br>Bachelor's Degree in civil engineering or related fields.<br><u>Professional Experience</u>   |

|   |  |
|---|--|
|   | At least 10 years professional experience of geo-technical engineering.  |
| (responsible for Lot 1. Desalination Plant)<br>(Additional responsibility to Mechanical Engineer for Lot 6, and Electrical Engineer for Lots 6 and 7) |  |
| Resident Engineer 1 /<br>Civil Engineer (1) for<br>Lot 1  | <u>Education</u><br>Master Degree in civil engineering or a national-registered professional engineer in his country.<br><u>Professional Experience</u><br>At least 15 years professional experience of civil engineering work. Preferably 5 years experience in the field of water supply during construction period.   |
| Civil Engineer (2) for<br>Lot 1   | <u>Education</u><br>Bachelor's Degree in civil engineering.<br><u>Professional Experience</u><br>At least 10 years professional experience of civil engineering work. Preferably 5 years experience in the field of water supply during construction period.   |
| Mechanical Engineer for<br>Lot 1, 6   | <u>Education</u><br>Bachelor's Degree in mechanical engineering.<br><u>Professional Experience</u><br>At least 5 years professional experience related to design and/or construction of pumping stations. Experience during construction period of pumping station for 3 or more projects with a total period of 3 or more years.  |
| Electrical Engineer for<br>Lot 1, 6, 7  | <u>Education</u><br>Bachelor's Degree in electrical engineering.<br><u>Professional Experience</u><br>At least 5 years professional experience related to the design and/or construction of desalination plants and pumping stations. Experience during construction period of desalination plant and pumping station for 3 or more projects with a total period of 3 or more years. |
| Structural Engineer   | <u>Education</u><br>Bachelor's Degree in civil engineering.<br><u>Professional Experience</u><br>At least 10 years' professional experience related to design and/or construction of desalination plants and pumping stations. Experience during construction period of desalination plant and pumping station for 5 or more projects with a total period of 3 or more years.        |
| Architect   | <u>Education</u><br>Bachelor's Degree in architecture.<br><u>Professional Experience</u><br>At least 10 years' professional experience related to the construction design of any plant and pumping station. Preferably experience on 5 or more projects with a total period of 3 or more years.  |
| Building Utilities<br>Engineer  | <u>Education</u><br>Bachelor's Degree in any engineering or related fields.<br><u>Professional Experience</u><br>At least 5 years' professional experience related to design and construction management of building utilities at any plant and pumping station. Preferably experience on 3 or more projects with a total period of 3 or more years.                                 |
| Quantity Surveyor for<br>Lot 1  | <u>Education</u><br>Bachelor's Degree in civil engineering or relevant.<br><u>Professional Experience</u>  |

|   |   |
|---|---|
|   | At least 10 years' professional experience of infrastructure development. Experience during construction period for 5 or more projects in the field of water and sewerage.  |
| (responsible for Lot 4. Pipeline Installation, and Lots 2 and 3)        |   |
| Resident Engineer 2 / Civil Engineer (1) for Lot 2, 3, 4                | <u>Education</u><br>Bachelor's Degree in civil engineering.<br><u>Professional Experience</u><br>At least 15 years' professional experience of civil engineering work. Preferably 5 years' experience in the field of water supply during construction period.                            |
| Civil Engineer (2) for Lot 2, 3, 4                                      | <u>Education</u><br>Bachelor's Degree in civil engineering.<br><u>Professional Experience</u><br>At least 10 years' professional experience of civil engineering work. Preferably 5 years' experience in the field of water supply during construction period.                            |
| Procurement Expert  | <u>Education</u><br>Bachelor's Degree in civil engineering.<br><u>Professional Experience</u><br>At least 10 years' professional experience including 8 years at least in civil engineering work. Preferably 5 years' experience in the field of water supply during construction period. |
| Quantity Surveyor for Lot 2, 3, 4                                       | <u>Education</u><br>Bachelor's Degree in civil engineering or relevant.<br><u>Professional Experience</u><br>At least 10 years' professional experience of infrastructure development. Experience during construction period for 5 or more projects in the field of water and sewerage.   |
| (responsible for Lots 5 and 6. Reservoirs / Pump Facility Construction) |   |
| Resident Engineer 3 / Civil Engineer (1) for Lot 5, 6                   | <u>Education</u><br>Bachelor's Degree in civil engineering.<br><u>Professional Experience</u><br>At least 15 years' professional experience of civil engineering work. Preferably 5 years' experience in the field of water supply during construction period.                            |
| Civil Engineer (2) for Lot 5, 6   | <u>Education</u><br>Bachelor's Degree in civil engineering.<br><u>Professional Experience</u><br>At least 10 years' professional experience of civil engineering work. Preferably 5 years' experience in the field of water supply during construction period.                            |
| Quantity Surveyor for Lot 5, 6  | <u>Education</u><br>Bachelor's Degree in civil engineering or relevant.<br><u>Professional Experience</u><br>At least 10 years professional experience of infrastructure development. Experience during construction period for 5 or more projects in the field of water and sewerage.    |

## 6. Task of Professional Staff

### (1) Foreign Professional Staff

## 1) Team Leader

- a) Shall take the overall responsibility, and shall represent the project Consultant's Team in all matters relating to the performance of services, coordinating with all other consultant's staff to deliver excellent product during the stipulated time schedule;
- b) Shall oversee, and supervise the Consultant's services;
- c) Assume direct responsibility for day-to-day consulting services including day-to-day management of all consultants' staff and co-ordination among and with them;
- d) Review existing studies / documents and other resources available and formulate the best implementation approach including programmatic project schedule;
- e) Develop and implement quality assurance program;
- f) Recommend contract payments;
- g) Review, analyze and make recommendations to SONEDE concerning variations and claims which are to be ordered/issued by SONEDE;
- h) Recommend to issue the commencement order to the Contractors;
- i) Evaluation of time extension claims and make recommendations;
- j) Provide recommendation to SONEDE for acceptance of the Contractor Performance security, advance payment security and required insurances;
- k) Explain and/or adjust ambiguities and/or discrepancies in the Contract Documents and recommend issuing any necessary clarifications or instructions;
- l) Review, verify and further detail the design of the works, recommend to approve the Contractors' working drawings and if necessary, issue further drawings and/or give instructions to the Contractor;
- m) Review and recommend to approve the proposals submitted by the Contractors;
- n) Make necessary design changes and amendments at site;
- o) Provide guidance for unforeseen matters;
- p) Progress reporting;
- q) Prepare institutional arrangement and training program for O&M;
- r) Certify all the drawings, BOQs, cost estimates and specifications;
- s) Ensure the safety conditions at work sites;
- t) Supervise commissioning, and carry out testing during commissioning;
- u) Review O&M manuals; and
- v) Develop a course module on project management including project coordination, contract administration, over-all supervision over the implementation of the project and conduct 3 days Project Management Training Course for SONEDE's project staff.

## 2) Desalination Plant Process Engineer

- a) Prepare conceptual design of the desalination process including the flow chart with levels;
- b) Prepare the specifications of the desalination process;
- c) Evaluate the proposed unit of the desalination plant;
- d) Supervise the installation procedure of the unit; and
- e) Assist the commissioning and guarantee test of the desalination plant, and evaluate the performance of the plant's equipment.

### 3) Civil Engineer

- a) Direct civil engineers assigned as national professional staff for any his/her responsible work;
- b) Prepare specifications of civil engineering works;
- c) Evaluate the proposed desalination plant, pipe installation, and reservoir work;
- d) Supervise civil work for desalination plant, pipe installation, and reservoir work;
- e) Assess the applicability of products proposed by the contractors;
- f) Attend the test operation of mechanical and electrical equipment;
- g) Evaluate the performance of the water transmission system; and
- h) Support training on O&M on facility related to facilities and civil engineering works.

### 4) Pipeline Engineer

- a) Direct the civil engineer for Lot 1 assigned as national professional staff regarding his/her responsible work;
- b) Prepare specifications related to pipes;
- c) Evaluate the proposed pipe materials and installation;
- d) Supervise pipeline installation work;
- e) Assess the applicability of products proposed by the contractors;
- f) Attend the test and commencement of pipeline operation; and
- g) Support training on O&M on pipeline facility.

### 5) Mechanical Engineer (Desalination Plant)

- a) Direct the mechanical engineer assigned as national professional staff for any his/her responsible work;
- b) Assist Team Leader for preparing O&M manuals on desalination plant;
- c) Prepare specifications of mechanical equipment and works;
- d) Evaluate the proposed mechanical facilities at the desalination plant;
- e) Assess the applicability of product proposed by the contractors related to desalination plant;
- f) Supervise the installation works of mechanical equipment for desalination plant;
- g) Attend the commissioning and guarantee test of mechanical equipment for desalination plant; and
- h) Support training on O&M on mechanical equipment for desalination plant.

### 6) Mechanical Engineer (Transmission Pumps)

- a) Direct the mechanical engineer assigned as national professional staff for any his/her responsible work;
- b) Assist Team Leader for preparing O&M manuals on transmission pumps;
- c) Prepare specifications of mechanical equipment and works;
- d) Evaluate the proposed mechanical facilities of transmission pumps;
- e) Assess the applicability of product proposed by the contractors related to transmission pumps;
- f) Supervise the installation works of mechanical equipment for transmission pumps;
- g) Attend the test operation of mechanical equipment for transmission pumps; and
- h) Support training on O&M on mechanical equipment for transmission pumps.



7) Electrical Engineer

- a) Direct the electrical engineer assigned as national professional staff for any his/her responsible work;
- b) Assist Team Leader for preparing O&M manuals related to electrical equipment;
- c) Prepare a specification of electrical equipment and works;
- d) Evaluate the proposed electrical equipment at desalination plant and of transmission pumps;
- e) Assess the applicability of product proposed by the contractors;
- f) Supervise the installation works of electrical equipment;
- g) Attend the test operation and guarantee test of electrical equipment; and
- h) Support training on O&M on electrical equipment.

8) Instrumentation Engineer

- a) Conduct conceptual design on instrumentation system of desalination plant and transmission pumps;
- b) Prepare technical specifications of instrumentation systems;
- c) Evaluate the proposed instrumentation system for the desalination plant and transmission pumps; and
- d) Attend the commissioning and guarantee test of the desalination plant and transmission pumps, and evaluate the performance of the instrumentation system.

9) Structural Engineer

- a) Conduct structural design on desalination plant and transmission pumps for a contract of design - build construction;
- b) Prepare specifications related to the structural design;
- c) Identify the necessary soil investigations required for the structural design and administer that work; and
- d) Provide necessary advice to implement all construction works in order to comply with the design code.

10) Specification / Contract Specialist

- a) Prepare bidding documents including prequalification documents;
- b) Evaluate the bidders' proposals;
- c) Carry out activities described in and/or that follows from the activities described in the scope of work related to procurement and contract management; and those assigned by Team Leader;
- d) Review Guidelines for preparation of Bid documents, and contracts for all lots of the project; and
- e) Proactively anticipate and carry out any other activity as per the scope of work.

11) Cost Estimation / Quantity Surveyor

- a) Estimate cost for each lot;
- b) Evaluate financial proposals;
- c) Review BOQs according to Guideline of SONEDE;
- d) Prepare work standards and material / day work schedules;
- e) Evaluate relevant documents for contractors' claims and variations; and

- f) Evaluate and report to Team Leader on the progress of the works and periodical payment requested by Contractors.

**(2) Local Professional Staff  
(responsible for all lots)**

1) Deputy Team Leader

- a) Support Team Leader;
- b) Inform data/report from national professional staff to Team Leader; and
- c) Supervise all National Professional Staff.

2) Environmental Specialist

- a) Review conceptual design based on the result of EIA;
- b) Update Environmental Management Plan (EMP) if necessary;
- c) Assist SONEDE to implement the measure identified in EMP;
- d) Monitor the works on the view point of the EMP and negative impacts on environment caused by the construction works;
- e) Assist SONEDE in monitoring the compliance with the requirements under the EMP, JICA Environmental Guidelines and the Tunisian Regulations; and
- f) Prepare report for environment and social environment and submit it to SONEDE.

3) Geo-technical Engineer

- a) Prepare a document for geo-technical conditions on site based on the existing data;
- b) Evaluate the foundation design of facilities; and
- c) Review geo-technical conditions on site, and foundation design of facilities.

**(responsible for Lot 1. Desalination Plant)**

4) Resident Engineer 1 / Civil Engineer (1) for Lot 1

- a) Conduct conceptual design of civil works for sea water desalination plant;
- b) Supervise civil work for Intake/Discharge at the level of the Desalination Plant;
- c) Assess the applicability of product proposed by the contractors;
- d) Attend the test operation, commissioning and guarantee test of desalination plant;
- e) Evaluate the performance of the desalination system; and
- f) Support training on O&M of facilities related to civil engineering work.

5) Civil Engineer (2) for Lot 1

- a) Conduct conceptual design of civil works for intake and brine effluent pipe;
- b) Assess the applicability of product proposed by the contractors;
- c) Attend the test operation of the desalination system;
- d) Evaluate the performance of the desalination system; and
- e) Support training for O&M on facility related to civil engineering work.

6) Mechanical Engineer (for Lots 1, 6)

- a) Conduct conceptual design of mechanical engineering works for Lot 1 and 6;
- b) Direct the mechanical engineer assigned as national professional staff for any his/her responsible work;
- c) Assist Team Leader for preparing O&M manuals on mechanical equipment;
- d) Assess the applicability of products proposed by the contractors related to mechanical equipment;
- e) Supervise the installation works of mechanical equipment;
- f) Attend the test operation of mechanical equipment;
- g) Evaluate the performance of the mechanical equipment; and
- h) Support training for O&M on mechanical equipment.

7) Electrical Engineer (for Lots 1, 6, 7)

- a) Conduct conceptual design of mechanical engineering works for Lot 1, 6 and 7;
- b) Assist Team Leader for preparing O&M manuals related to electrical equipment;
- c) Assess the applicability of product proposed by the contractors;
- d) Supervise the installation works of electrical equipment;
- e) Attend the test operation of electrical equipment;
- f) Evaluate the performance of the electrical equipment; and
- g) Support training for O&M on electrical equipment.

8) Structural Engineer

- a) Conduct conceptual design of structural engineering works;
- b) Identify the necessary soil investigations required for the structural design and administer that work; and
- c) Provide necessary advice to implement all construction works in order to comply with the design code.

9) Architect

- a) Conduct conceptual design of architect works;
- b) Review building design in consideration of energy efficiency and operational environment;
- c) Supervise building construction ensuring safety condition; and
- d) Evaluate and approve the applicability of the building.

10) Building Utilities Engineer

- a) Conduct conceptual design of building utilities in consideration of energy efficiency and operational environment;
- b) Supervise building utility construction ensuring safety condition; and
- c) Attend the building utility tests, and report to Team Leader.

11) Quantity Surveyor for Lot 1

- a) Review BOQs according to Guideline of SONEDE;
- b) Preparation of work standards and material / day work schedules;

- c) Evaluate relevant documents for contractors' claims and variations; and
- d) Evaluate and report to Team Leader for the progress of the works and periodical payment requested by Contractors.

**(responsible for Lots 2, 3, 4. Pipeline Installation)**

12) Resident Engineer 2 / Civil Engineer (1) for Lots 2, 3, 4

- a) Prepare a design for civil engineering works of Lot 4;
- b) Calculate the work volume and estimate costs;
- c) Assess the applicability of product proposed by the contractors;
- d) Attend the test operation of the transmission system;
- e) Evaluate the performance of the transmission system; and
- f) Support training on O&M on facility related to civil engineering work.

13) Civil Engineer (2) for Lots 2, 3, 4

- a) Prepare a design for civil engineering works of Lot 4;
- b) Calculate the work volume and estimate costs;
- c) Assess the applicability of product proposed by the contractors;
- d) Attend the test operation of the transmission system;
- e) Evaluate the performance of the transmission system; and
- f) Support training on O&M on facility related to civil engineering work.

14) Procurement Specialist for Lots 2, 3, 4

- a) Prepare detailed design, specifications and BoQ for transmission pipelines.

15) Quantity Surveyor for Lots 2, 3, 4

- a) Review BOQs according to SONEDE's guidelines;
- b) Preparation of work standards and material / day work schedules;
- c) Evaluate relevant documents for contractors' claims and variations; and
- d) Evaluate and report to Team Leader for the progress of the works and periodical payment requested by Contractors.

**(responsible for Lots 5, 6. Reservoirs / Pump Facility Construction)**

16) Resident Engineer 3 / Civil Engineer (1) for Lots 5, 6

- a) Conduct conceptual design of civil works for Lot 6;
- b) Supervise civil work for reservoir and pump facilities;
- c) Assess the applicability of product proposed by the contractors;
- d) Attend the test operation of mechanical and electrical equipment;
- e) Evaluate the performance of the transmission system; and
- f) Support training for O&M on facility related to civil engineering work,

17) Civil Engineer (2) for Lots 5, 6

- a) Conduct conceptual design of civil works for Lot 6;

- b) Assess the applicability of product proposed by the contractors;
- c) Attend the test operation of mechanical and electrical equipment;
- d) Evaluate the performance of the transmission system; and
- e) Support training on O&M on facility related to civil engineering work.

18) Quantity Surveyor for Lots 5, 6

- a) Review BOQs according to Guideline of SONEDE;
- b) Preparation of work standards and material / day work schedules;
- c) Evaluate relevant documents for contractors' claims and variations; and
- d) Evaluate and report to Team Leader for the progress of the works and periodical payment requested by Contractors.

## 7. Reporting

Within the scope of consulting services, the Consultant shall prepare and submit reports and documents to SONEDE as shown below. The Consultant shall provide electronic copy of each of these reports.

*(Example)*

| Category                         | Type of Report                                       | Timing  | No. of Copies |
|----------------------------------|--|---|---------------|
| Consultancy Services             | Inception Report                                     | Within 1 month after commencement of the services             | 10            |
|                                  | Monthly Progress Report                              | Every month   | 10            |
|                                  | Quarterly Progress Report                            | Every quarter   | 10            |
|                                  | Project Completion Report (for submission to JICA)   | At the end of Services  | 10            |
| Tender Assistance                | Bid Evaluation Report (Technical & Price)            | After evaluation of Bids                                      | 15 each       |
| Construction Supervision         | Quality Control Report                               | Every month   | 10            |
|                                  | Completion Report (and As-built Drawings, if any)    | At the end of the Project                                     | 5             |
| Training                         | Training Plan  | At appropriate timing in accordance with the Inception Report | 10            |
|                                  | Training Execution and Evaluation Report             | Within 1 month after training                                 | 10            |
| Environment and Social Safeguard | Environmental Monitoring Report                      | Every quarter   | 10            |
|                                  | Land Acquisition Monitoring Report                   | Every month   | 10            |
|                                  | Environmental and Social Safeguard Evaluation Report | At the end of the Project                                     | 20            |
| Other Report                     | Technical Report                                     | As required or upon request                                   | As required   |

Contents to be included in each report are as follows:

*(Monthly Progress report and Inception report)*

- a) Monthly Progress Report: Describes briefly and concisely all activities and progress for the

previous month by the 10th day of each month. Problems encountered or anticipated will be clearly stated, together with actions to be taken or recommendations on remedial measures for correction. Also indicates the work to be performed during the coming month.

- b) Inception Report: To be submitted within 1 month after the commencement of the services, presenting the methodologies, schedule, organization, etc.

*(Detailed Design/ Conceptual Design)*

- a) Project Definition Report (20 copies), to be submitted in the 3<sup>rd</sup> month after the commencement of services, presenting the design criteria and standards.
- b) Draft Detailed Design/ Conceptual Design Report (20 copies), to be submitted in the 8<sup>th</sup> month for Lot 1 and the 11<sup>th</sup> month for Lots 2 to 6, after the commencement of services, presenting detailed engineering design and conceptual design.
- c) Cost Estimate Report (20 copies), to be submitted in the 9<sup>th</sup> month for Lot 1, and the 12<sup>th</sup> month for Lots 2 to 6, after the commencement of services, presenting detailed cost estimates.
- d) Final Detailed Design/ Conceptual Design Report (20 copies), to be submitted in the 9<sup>th</sup> month for Lot 1, and the 11<sup>th</sup> month for Lots 2 to 6 after the commencement of services, compiling all the items carried out during services.
- e) Final Design Report (20 copies), to be submitted in the 12th month after the commencement of services, finalizing detailed design, cost estimate, bid plan, bid evaluation criteria, technical evaluation criteria and bidding documents through the incorporation of comments on the Draft Design Report, provided by SONEDE
- f) Pre-qualification Document Report (20 copies), to be submitted in the 3<sup>rd</sup> month after the commencement of the services, presenting the pre-qualification documents for Lot 1 and its evaluation criteria.
- g) Pre-qualification Evaluation Report (15 copies) to present the results of the evaluation and to select the qualified applicants.
- h) Bidding Document Report (20 copies), to be submitted in the 9<sup>th</sup> month for Lot 1, and the 12<sup>th</sup> month for Lots 2 to 6, after the commencement of the services, presenting the bidding documents and bid evaluation criteria.

*(Tender Assistance)*

- a) Bid Evaluation Report (Technical) (15 copies) to present the results of technical evaluation and to recommend the qualified applicants.
- b) Bid Evaluation Report (Financial) (15 copies) to present the results of the tenders to select the qualified applicants with lowest evaluated price bid .

*(Assistance in Environment Monitoring)*

- a) Environmental Monitoring Report (10 copies), to be submitted at every three (3) months after the commencement of the services, presenting the environmental impacts and implementation of environmental mitigation measures during and [at the completion of / after] the construction stage. Environmental monitoring forms attached as Appendix # will be filled and attached to the Report.
- b) Land Acquisition Report (10 copies), to be submitted at every month during land acquisition period.
- c) Environmental and Social Safeguard Evaluation Report (20 copies), to be submitted by the end of the consulting services, presenting the EMP and EMoP prepared.

*(Construction Supervision)*

- a) Quarterly Progress Report (15 copies), to be submitted at every three (3) months during construction, presenting the progress status of the Project.
- b) Operation and Maintenance Manual (20 copies) containing technical procedures for the appropriate operation and maintenance of all project facilities.
- c) Construction Completion Report (20 copies), to be submitted within three (3) month after completion of construction, which comprises a full size of as-built drawings for all the structures and facilities completed, and the final details of the construction completed together with all data, records, material tests results, field books.

## **10.3-2 TOR for Consulting Service (draft) Tendering Assistance and Construction Supervision**

### **Sfax Sea Water Desalination Plant Construction Project in the Republic of Tunisia Terms of Reference on Consulting Service**

#### **1. Background**

One half of Tunisia belongs to semi-dry climate. The annual average of the rainfall is about a little less than 500mm. Consequently, groundwater contributes to about 40% of water intake. The water supply system in Tunisia has been developed in accordance with an economic growth of 4% in average during the last 15 years. The service area of water supply covers 97.8% in total, i.e. 100% of urban areas, 93.4% of rural areas (SONEDE, 2012). In Tunisia, the Ministry of Agriculture defines the water sector policy. Water supply in rural area is based on the communal faucet method and is operated by the Ministry of Agriculture. SONEDE (Société Nationale d'Exploitation et de Distribution des Eaux) is responsible for water supply in urban areas and in some rural areas using individual supply systems including water supply for domestic use and development, and the maintenance of conveyance and transmission systems.

Greater Sfax is the second largest city in Tunisia with an approximate population of about 621000. Water supply volume amounts to about 190,000m<sup>3</sup>/day for SONEDE's coverage area with a served population of about 810,000 in 2012. Because of rapid increase in population at 1.37% per annum over the last ten years, it is projected that serious water shortage will happen in 2018, and the development of a new water source is requested. Greater Sfax currently relies on groundwater in the central-western region for its water supply. However, it is projected that water supply from the region will be decreased in order to spare groundwater resources in the central-western regions and the increase of demand in the region. In order to cope with this situation, it is requested to develop water resource only for Sfax governorate and to provide related infrastructure. SONEDE studied the construction of a sea water desalination plant in Sfax in the feasibility study for water supply in south regions conducted in 2005.

SONEDE also prepared the Strategic Plan in 2013 to enhance water supply capacity and to improve water quality by 2030. In the plan, the Sfax Desalination Plant Construction Project was planned. In this framework, the preparatory survey was conducted with JICA funding. Based on the survey, this project was formulated.

#### **2. Objectives of Consulting Services**

The objective of the consulting services is to provide assistance to the bidding process and construction supervision ensuring the design and the construction quality and fairness, and achieving the efficient project implementation.

#### **3. Scope of Consulting Services**

The scope of consulting services on Sfax Sea Water Desalination Plant Construction Project in the



Republic of Tunisia cover tender assistance, and management of construction services for 7 lots and eight (08) contracts. Each lot is explained below followed by a description of services to provide:

(1) Project Component

The project consists of 7 lots. Each lot is explained as follows:

i) Lot 1: Construction of the Seawater Desalination Plant

(a) Sea Water Desalination Plant

- a1) Land Acquisition: Approximately 20ha
- a2) Desalination Method: Reverse Osmosis Membrane Method (RO)
- a3) Treated Water: 100,000m<sup>3</sup>/d
- a4) RO Units: 25,000m<sup>3</sup>/day × 4 units
- a5) Transmission Pump Facility 100,000m<sup>3</sup>/d
- a6) Required Electricity: Approximately 20MVA

(b) Sea Water Intake Pipe

- b1) Intake Volume: 222,200m<sup>3</sup>/d (capable of flowing 444,400 m<sup>3</sup>/d for Phase 2)
- b2) Pipe Material: HDPE
- b3) φ2000mm x 2 (HDPE), L=3.6km (Buried Pipe: 3.2 km offshore, and 0.4 km onshore))
- b4) Transmission pump facility 100,000 m<sup>3</sup>/d
- b5) Submerged Water Intake Tower 2 units

(c) Brine Effluent Pipe

- c1) Effluent Volume: 122,000m<sup>3</sup>/d (capable of flowing 244,000 m<sup>3</sup>/d for Phase 2)
- c2) Pipe Material: HDPE
- c3) φ1800mm, L=4.4km (Buried Pipe: 4.0 km offshore, 0.4 km onshore))
- c4) Submerged Water Effluent Tower 1 unit

ii) Lot 2: Procurement of Pipes

(a) Procurement of Pipe for Transmission to be installed for Lot 4

- a1) Pipe Material: Ductile Cast Iron Pipe
- a2) φ1400mm: L=26.1km (Desalination Plant - PK11 Reservoir)
- a3) φ1000mm: L=6.1km (PK10 Reservoir)
- a4) φ800mm: L=4.8km (PK10 Reservoir—PK14 Reservoir)
- a5) φ800mm: L=9.4km (PK14 Reservoir—Sidi Salah EH Reservoir)
- a6) φ400mm: L=2.9km (PK11 Reservoir—Bou Merra Reservoir)

This lot can be subject of two contracts (sub-lot 2.1 and sub-lot 2.2)

iii) Lot 3: Procurement of Valves and Other Equipment

(a) Procurement of valves and other equipment to be installed for Lot 4

iv) Lot 4: Installation of Pipeline including valves and other equipment

- (a) Construction of Transmission Pipeline and valves whose materials are procured through Lot 2 and Lot 3.
- (b) Construction of One-Way Surge Tanks or other anti-water-hammer equipment
  - b1) Desalination Plant Site - PK11 Reservoir  
Tank dimension: diameter 10m x height 15m, site: 20m x 30m x 2 locations
- v) Lot 5: Construction of Reservoir
  - (a) Construction of Reservoir
    - a1) Capacity of 5,000m<sup>3</sup> existing precinct of Bou Merra Reservoir
  - (b) Construction of Receiving and Mixing Chambers
    - b1) PK11: 9.0 W x 15.0 L x 5.0 D
    - b2) Bou Merra: 4.0W x 3.0L x 5.0D
    - b3) PK10: 7.0W x 10.0L x 5.0D
    - b4) PK14: 7.0W x 7.0L x 5.0D
    - b5) Sidi Salah EH: 6.0W x 5.0L x 5.0D

(internal dimension; W: width, L: length, D: water depth; unit: m)
- vi) Lot 6: Construction of Pumping Stations
  - (a) Pumping Station
    - a1) Relay Pumping Station: 3 (in PK10, PK11, and PK14 Reservoir Sites)
- vii) Lot 7: Power Transmission Construction and Power Connection Works (Executed by STEG)
  - (a) Construction of electrical power supply facility necessary for the Sea Water Desalination Plant
    - a1) power line
    - a2) power line tower
    - a3) facility for transformation of energy
    - a4) other necessary facilities
  - (b) Electrical power connection work (pumping stations of Pk10, Pk11 and Pk14)
  - (c) Assistance for the installation of Sea Water Desalination Plant electrical facility
- (2) Detailed description of the consulting services

Tendering Assistance

The Consultants shall provide assistance to the tendering procedure listed below in accordance with the JICA Guidelines for Procurement under Japanese ODA Loans (April 2012). The Consultant shall assist SONEDE to;

- a) Evaluate bids in accordance with the criteria set forth in the bidding documents. In such evaluation, the Consultant shall carefully confirm that bidders' submissions in their technical proposal including, but not limited to, site organization, mobilization schedule, method statement, construction schedule, safety plan, and EMP have been prepared in harmony each other and will meet such requirements set forth in applicable laws and regulations, specifications and other parts of the bidding documents;

- b) Prepare bid evaluation reports for approval of the competent committee;
- c) Assist SONEDE in contract negotiation by preparing agenda and facilitating negotiations including preparation of minutes of negotiation meeting; and
- d) Prepare a draft and final contract agreement.

### Construction Supervision

#### 1) Lots 1 and 6

The Consultant shall perform his duties during the implementation period of the contracts to be executed by SONEDE and the Contractors (Lots 1 and 6). In this context, the Consultant shall;

- a) Act as SONEDE's Representative to execute construction supervision and contract administration services in accordance with the power and authority to be delegated by SONEDE;
- b) Provide assistance to SONEDE concerning variations and claims which are to be ordered/issued at the initiative of SONEDE;
- c) Advise SONEDE on resolution of any dispute with the Contractors;
- d) Issue instructions, approvals and notices as appropriate;
- e) Provide recommendations to SONEDE for acceptance of the Contractor's performance security, advance payment security and required insurances;
- f) Assess adequacy of all inputs such as materials, labor and equipment provided by the Contractors;
- g) Check and approve the Contractors' method of work, including site organization, program of performance, quality assurance system, safety plan and environmental monitoring plan so that the requirements set forth in the applicable laws and regulations, the specifications or other parts of the contract are to be duly respected;
- h) Monitor as appropriate physical and financial progress, and take appropriate action to expedite progress if necessary, so that the time for completion set forth in the contract will be duly respected;
- i) Explain and/or adjust ambiguities and/or discrepancies in the Contract Documents and issue any necessary clarifications or instructions;
- j) Review and approve the Contractor's design for the works to be constructed, working drawings, shop drawings and drawings for temporary works;
- k) Liaise with the appropriate authorities to ensure that all the affected utility services are promptly relocated;
- l) Carry out field inspections on the Contractor's setting out of the works in relation to original points, lines and levels of reference specified in the contract;
- m) Organize, as necessary, management meetings with the Contractors to review the arrangements for future work. Prepare and deliver minutes of such meetings to SONEDE and the Contractors;
- n) Supervise the works so that all the contractual requirements are met by the Contractor, including those in relation to i) quality of the works, ii) safety and iii) protection of the environment. Confirm that an accident prevention officer proposed by the Contractor is duly assigned at the project site;

- o) Supervise field tests, sampling and laboratory test to be carried out by the Contractors;
- p) Inspect construction methods, equipment to be used, workmanship at the site, and attend factory inspection and manufacturing tests in accordance with SONEDE's Requirements;
- q) Verify payment applications submitted by the Contractor;
- r) Coordinate the works among different contractors employed for the Project;
- s) Modify the Employer's Requirements as may be necessary in accordance with the actual site conditions, and issue variation orders with the approval of SONEDE (including necessary actions in relation to the works performed by other contractors working for other projects or other facility operators, if any);
- t) Carry out timely reporting to SONEDE for any inconsistency in executing the works and suggesting appropriate corrective measures to be applied;
- u) Inspect, verify and comment on claims issued by the Contractors;
- v) Supervise Pre-commissioning carried out by the Contractors, check and comment on the Contractor's Pre-commissioning report, and suggest the Completion Certificate as specified in the contract;
- w) Supervise Commissioning and Guarantee Test carried out by the Contractors, check and comment on the Contractor's report on the Commissioning and Guarantee Test, and suggest the Operational Acceptance Certificate as specified in the Contract;
- x) Provide periodic inspection services during defect liability period and if any defects are noted, instruct first SONEDE and second the Contractors to rectify;
- y) Check and suggest the approval of as-built drawings prepared by the Contractors; and
- z) Check and suggest the approval of the operation and maintenance manual prepared by the Contractor.

2) Lots 4 and 5

The Consultant shall perform his duties during the contract implementation period of the contracts to be executed by SONEDE and the Contractors (Lots 4 and 5). In this context, the Consultant shall;

- a) Act as SONEDE's Representative to execute construction supervision and contract administration services in accordance with the power and authority delegated by SONEDE;
- b) Provide assistance to SONEDE concerning variations and claims which are to be ordered/issued at the initiative of SONEDE;
- c) Advise SONEDE on resolution of any dispute with the Contractor;
- d) Issue instructions and notices, and suggest approvals as appropriate;
- e) Provide recommendation to SONEDE for acceptance of the Contractors' safety plan, performance security, advance payment security and required insurances;
- f) Evaluate compliance of all inputs such as equipment, working staff, and materials provided by the Contractors;
- g) Provide commencement order to the Contractors;
- h) Check and approve the Contractors' method of work, including site organization, program of performance, quality assurance system, safety plan, method statement of safety and environmental monitoring plan so that the requirements set forth in the applicable laws and

- regulations, the specifications or other parts of the contract are to be duly respected;
- i) Regularly monitor physical and financial progress, and take appropriate action to expedite progress if necessary, so that the time for completion set forth in the contract will be duly respected by the Contractor;
  - j) Explain and/or adjust ambiguities and/or discrepancies in the Contract Documents and issue any necessary clarifications or instructions. Issue further drawings and give instructions to the Contractors for any works which may not be sufficiently detailed in the contract documents, if any;
  - k) Review and approve the Contractor's working drawings, shop drawings and drawings for temporary works;
  - l) Liaise with the appropriate authorities to ensure that all the affected utility services are promptly relocated;
  - m) Carry out field inspections on the Contractor's setting out of the works in relation to original points, lines and levels of reference specified in the contract;
  - n) Organize, as necessary, management meetings with the Contractors to review the arrangements for future work. Prepare and deliver minutes of such meetings to SONEDE and the Contractors;
  - o) Supervise the works so that all the contractual requirements are met by the Contractors, including those in relation to i) quality of the works, ii) safety and iii) protection of the environment. Confirm that an accident prevention officer proposed by the Contractors is duly assigned at the project site. Require the contractors to take appropriate remedies if any questions are recognized regarding the safety measures;
  - p) Supervise field tests, sampling and laboratory test to be carried out by the Contractors;
  - q) Inspect the construction method, equipment to be used, workmanship at the site, and attend shop inspection and manufacturing tests in accordance with the specifications;
  - r) Survey and measure the work output performed by the Contractors verify statements submitted by the Contractor and issue payment certificates such as interim payment certificates and final payment certificate as specified in the contract;
  - s) Coordinate the works among different contractors employed for the Project;
  - t) Modify the designs, technical specifications and drawings, relevant calculations and cost estimates as may be necessary in accordance with the actual site conditions, and issue variation orders (including necessary actions in relation to the works performed by other contractors working for other projects, if any);
  - u) Carry out timely reporting to SONEDE for any inconsistency in executing the works and suggesting appropriate corrective measures to be applied;
  - v) Inspect, verify and approve or disapprove claims issued by the parties to the contract (i.e. SONEDE and Contractors) in accordance with the civil works contract;
  - w) Perform the inspection of the works, including Test on Completion, and to issue certificates such as the Taking-Over Certificate, Performance Certificate as specified in the contract;
  - x) Supervise the preliminary operation conducted by the Contractors, check and approve the initial operation report issued by the Contractors and issue the completion report as specified in the Contract;
  - y) Supervise commissioning and carry out tests during the commissioning, if applicable;

- z) Provide periodic and/or continuous inspection services during defects notification period and if any defects are noted, instruct the Contractors to rectify;
  - aa) Prepare as-built drawings for the parts of the works constructed in accordance with the design provided by SONEDE;
  - ab) Check and certify as-built drawings for the parts of the works designed by the Contractors, if any; and
  - ac) Prepare an operation and maintenance manual for the works constructed in the Project.
- 3) Lot 7
- The Consultant shall perform the following tasks throughout the execution of the Contract between SONEDE and STEG (Lot 7). In this regard, the Consultant shall;
- a) Monitor the progress of works carried out by STEG; and
  - b) Coordination with STEG.

Safety measures

The Consultants shall;

- a) Review the safety plans submitted by the contractors securing the safety during the construction. (Refer to Paragraph (2), Section 4.02 Scope of the Project and of the Consulting Services of the Guidelines for the Employment of Consultants under Japanese ODA Loans, March 2009), and require them to submit the revision if necessary; and
- b) Confirm that an accident prevention officer proposed by the contractor is duly assigned at the project site during the supervision of the construction works and ensure the work is carried out according to the safety plan as well as the safety measures prescribed in the Program. If Consultants recognize any questions regarding the safety measures in general including the ones mentioned above, the Consultants shall requires the contractors to make appropriate improvements.

Facilitation of implementation of Environmental Management Plan (EMP) and Environmental Monitoring Plan (EMoP)

The Consultant shall;

- a) Update EMP as appropriate;
- b) Assist SONEDE in dissemination and explanation of additionally confirmed and identified environmental issues to public including holding public consultations;
- c) During the preparation of bidding documents, clearly identify environmental responsibilities as explained in the EIA and EMP;
- d) Assist SONEDE to review the Construction Contractor's Environmental Program to be prepared by the contractor in accordance with EMP, relevant plans and JICA Environmental Guidelines and to make recommendations to SONEDE regarding any necessary amendments for its approval;
- e) Assist SONEDE to implement the measures identified in the EMP;
- f) Monitor the effectiveness of EMP and negative impacts on environment caused by the construction works and provide technical advice, including a feasible solution, so that

SONEDE can improve situation when necessary;

- g) Assist SONEDE in monitoring the compliance with conditions stated in the Environmental Permit Certification (EPC) and the requirements under EMP and JICA Environmental Guidelines;
- h) Assist SONEDE in the capacity building of SONEDE staff on environmental management through on-the-job training on environmental assessment techniques, mitigation measure planning, supervision and monitoring, and reporting.

#### Technology transfer

The Consultant shall carry out the technology transfer as an important aspect in design and supervision works. The Consultant shall provide the opportunity to SONEDE officers and staffs to be involved in the working team of the Consultant during the designing, contract administration and supervision works for their capacity building wherever possible. If requested by SONEDE, the Consultant shall brief and demonstrate the survey and design procedure, the construction supervision and contract management process and procedures. The consultant shall assist SONEDE and its staff to build their capacity as a part of on the job training under the Project.

#### **4. Man-Month Schedule and Expected Time Schedule**

The consultants will be engaged over 74 months as a consulting service period. The team shall comprise Foreign and Local Professional Staff with man-month presented below.

| No  | Position   | Man-Month        |                  |                  |       |
|---|--|------------------|------------------|------------------|-------|
|   |  | DD <sup>1)</sup> | TA <sup>2)</sup> | CS <sup>3)</sup> | Total |
| <b>Foreign Professional Staff</b>                   |  |                  |                  |                  |       |
| 1   | Team Leader  | -                | 10.0             | 35.5             | 45.5  |
| 2   | Desalination Plant Process Engineer                | -                | 4.0              | 18.5             | 22.5  |
| 3   | Civil Engineer                                     | -                | 4.0              | 33.0             | 37.0  |
| 4   | Pipeline Engineer                                  | -                | 1.5              | 28.0             | 29.5  |
| 5   | Mechanical Engineer (Desalination Plant)           | -                | 3.5              | 9.5              | 13.0  |
| 6   | Mechanical Engineer (Transmission Pumps)           | -                | 2.0              | 7.0              | 9.0   |
| 7   | Electrical Engineer                                | -                | 3.5              | 9.0              | 12.5  |
| 8   | Instrumentation Engineer                           | -                | 2.0              | 9.0              | 11.0  |
| 9   | Structural Engineer                                | -                | 0.0              | 2.0              | 2.0   |
| 10  | Contract Specialist                                | -                | 5.5              | 5.0              | 10.5  |
| 11  | Quantity Surveyor                                  | -                | 0.0              | 34.0             | 34.0  |
| <b>Subtotal: Foreign Professional Staff</b>         |  | -                | 36.0             | 190.5            | 226.5 |
| <b>Local Professional Staff</b>                     |  |                  |                  |                  |       |
| 1   | Deputy Team Leader                                 | -                | 14.0             | 36.5             | 50.5  |
| 2   | Environmental Specialist                           | -                | 1.0              | 38.0             | 39.0  |
| 3   | Geo-technical Engineer                             | -                | 0.0              | 3.0              | 3.0   |
| Lot 1. Construction of Sea Water Desalination Plant |  |                  |                  |                  |       |
| 4   | Resident Engineer 1 / Civil Engineer (1) for Lot 1 | -                | 0.0              | 48.0             | 48.0  |

|  |  |   |       |        |        |
|--|--|---|-------|--------|--------|
| 5  | Civil Engineer (2) for Lot 1                             | - | 0.0   | 29.0   | 29.0   |
| 6  | Mechanical Engineer for Lot 1, 6                         | - | 0.0   | 9.0    | 9.0    |
| 7  | Electrical Engineer for Lot 1, 6, 7                      | - | 0.0   | 9.0    | 9.0    |
| 8  | Structural Engineer for Lot 1, 4, 5, 6                   | - | 0.0   | 3.0    | 3.0    |
| 9  | Architect  | - | 0.0   | 4.0    | 4.0    |
| 10   | Building Utilities Engineer                              | - | 0.0   | 4.0    | 4.0    |
| 11   | Quantity Surveyor for Lot 1                              | - | 0.0   | 33.0   | 33.0   |
| Lot 2 & 3 Procurement of Pipes / Valves and Other Equipment<br>Lot 4. Construction of Pipeline |  |   |       |        |        |
| 12   | Resident Engineer 2 / Civil Engineer (1) for Lot 2, 3, 4 | - | 0.0   | 33.0   | 33.0   |
| 13   | Civil Engineer (2) for Lot 2, 3, 4                       | - | 0.0   | 32.0   | 32.0   |
| 14   | Quantity Surveyor for Lot 2, 3, 4                        | - | 0.0   | 32.0   | 32.0   |
| Lot 5 & 6. Reservoirs/Pump Facility Construction   |  |   |       |        |        |
| 15   | Resident Engineer 3 / Civil Engineer (1) for Lot 5, 6    | - | 0.0   | 33.0   | 33.0   |
| 16   | Civil Engineer (2) for Lot 5, 6                          | - | 0.0   | 30.0   | 30.0   |
| 17   | Quantity Surveyor for Lot 5, 6                           | - | 0.0   | 30.0   | 30.0   |
| <b>Subtotal: Local Professional Staff</b>  |  | - | 15.0  | 406.5  | 421.5  |
| Local support staff  |  |   |       |        |        |
| 1  | Assistant Engineer                                       | - | 14.0  | 69.0   | 83.0   |
| 2  | Inspector/Surveyor                                       | - | 0.0   | 156.0  | 156.0  |
| 3  | CAD Operator   | - | 0.0   | 36.0   | 36.0   |
| 4  | Interpreter/Translator                                   | - | 13.0  | 69.0   | 82.0   |
| 5  | Office Manager   | - | 14.0  | 36.0   | 50.0   |
| 6  | Accountant   | - | 0.0   | 36.0   | 36.0   |
| 7  | Clerk  | - | 0.0   | 36.0   | 36.0   |
| 8  | Office Boy   | - | 14.0  | 36.0   | 50.0   |
| <b>Subtotal: Local Support Staff</b>   |  | - | 55.0  | 474.0  | 529.0  |
| <b>Total Technical and support staff</b>   |  | - | 106.0 | 1071.0 | 1177.0 |

- 1) Conceptual Design/Detailed Design: to be conducted by SONEDE
- 2) Tendering Assistance
- 3) Construction Supervision

All technical and support staff required for the mission must be provided by the Consultant and includes the following profiles.

It is envisaged that the Consultant will provide adequate Technical and Administrative supporting staff. It is the Consultant's responsibility to select the optimum team and to propose the professionals which are believed to the best meets and needs of SONEDE without exceeding total man-month proposed for each category.

## 5. Basic professional requirements of key expert

The key expert requirements with qualification and experience for each position are given in the table



below.

(1) Foreign Professional Staff

| Position                                 | Minimum requirement   |
|--|---|
| Team Leader                              | <p><u>Education</u><br/>Master Degree in civil engineering or construction management, or a national-registered professional engineer in his country.</p> <p><u>Professional Experience</u><br/>At least 20 years professional experience including 18 years at least in infrastructure. Experience of team leader for 5 or more projects in the field of water and sewerage, each of which is amounted at a project cost of more than 30 million US dollars.</p> |
| Desalination Plant Process Engineer      | <p><u>Education</u><br/>Master Degree in civil engineering or a national-registered professional engineer in his country.</p> <p><u>Professional Experience</u><br/>At least 10 years professional experience including at least 8 years as a plant process engineer. Experience on desalination plant for 2 or more projects.</p>  |
| Civil Engineer                           | <p><u>Education</u><br/>Master Degree in civil engineering or a national-registered professional engineer in his country.</p> <p><u>Professional Experience</u><br/>At least 10 years' professional experience including at least 8 years in development. Experience during construction period for 3 or more projects in the field of water and sewerage.</p>  |
| Pipeline Engineer                        | <p><u>Education</u><br/>E Bachelor's Degree in civil engineering or mechanical engineering..</p> <p><u>Professional Experience</u><br/>At least 10 years professional experience including at least 8 years in the field of pipeline design/construction. Experience during construction period of pipeline for 3 or more projects with a total period of 3 or more years.</p>  |
| Mechanical Engineer (Desalination Plant) | <p><u>Education</u><br/>Bachelor's Degree in civil engineering or mechanical engineering.</p> <p><u>Professional Experience</u><br/>At least 10 years professional experience including at least 8 years of experience in the design and/or construction of water treatment plants. Experience of desalination plant for 2 or more projects.</p>  |
| Mechanical Engineer (Transmission Pumps) | <p><u>Education</u><br/>Bachelor's Degree in mechanical engineering.</p> <p><u>Professional Experience</u><br/>At least 10 years professional experience including at least 8 years in the design and/or construction of pumping stations. Experience during construction period of pumping station for 3 or more projects with a total period of 3 or more years.</p>  |
| Electrical Engineer                      | <p><u>Education</u><br/>Bachelor's Degree in electrical engineering.</p> <p><u>Professional Experience</u><br/>At least 10 years professional experience including at least 8 years in the design and/or construction of desalination plants and pumping station. Experience during construction period of desalination plant and pumping</p>   |

|                          |  |
|--------------------------|--|
|                          | station for 5 or more projects with a total period of 3 or more years.   |
| Instrumentation Engineer | <u>Education</u><br>Bachelor's Degree in electrical engineering.<br><u>Professional Experience</u><br>At least 10 years professional experience including at least 8 years in instrumentation engineering for any plant. Experience in the operation of desalination plant on 3 or more years.   |
| Structural Engineer      | <u>Education</u><br>Master Degree in civil engineering or a national-registered professional engineer in his country.<br><u>Professional Experience</u><br>At least 10 years professional experience including at least 8 years in the design and/or construction of desalination plant and pumping stations. Experience during construction period of desalination plants and pumping stations for 5 or more projects with a total period of 3 or more years. |
| Contract Specialist      | <u>Education</u><br>Bachelor's Degree in engineering or related field.<br><u>Professional Experience</u><br>At least 10 years professional experience including at least 8 years as a contract specialist for any type of plants or infrastructure development. At least 5 or more projects as a contract specialist.  |
| Quantity Surveyor        | <u>Education</u><br>Bachelor's Degree in engineering or related field.<br><u>Professional Experience</u><br>At least 10 years professional experience including at least 8 years as a quantity surveyor or relevant specialist for any type of plants or infrastructure development. At least 5 or more projects for surveying quantity.   |

(2) Local Professional Staff

| Position                                    | Minimum requirement   |
|---|---|
| (responsible for all lots)                  |   |
| Deputy Team Leader                          | <u>Education</u><br>Master Degree in civil engineering or construction management, or a national-registered professional engineer in his country.<br><u>Professional Experience</u><br>At least 20 years professional experience of infrastructure development. Experience of team leader for 5 or more projects in the field of water and sewerage.                                |
| Environmental Specialist                    | <u>Education</u><br>Master Degree in civil/environmental engineering or related fields, or a national-registered professional engineer in his country.<br><u>Professional Experience</u><br>At least 20 years professional experience of environmental infrastructure development. Experience during construction period for 5 or more projects in the field of water and sewerage. |
| Geo-technical Engineer                      | <u>Education</u><br>Bachelor's Degree in civil engineering or related fields.<br><u>Professional Experience</u><br>At least 10 years professional experience of geo-technical engineering.  |
| (responsible for Lot 1. Desalination Plant) |   |

| (Additional responsibility to Mechanical Engineer for Lot 6, and Electrical Engineer for Lots 6 and 7) |   |
|--|---|
| Resident Engineer 1 / Civil Engineer (1) for Lot 1   | <p><u>Education</u><br/>Master Degree in civil engineering or a national-registered professional engineer in his country.</p> <p><u>Professional Experience</u><br/>At least 15 years professional experience of civil engineering work. Preferably 5 years experience in the field of water supply during construction period.</p>   |
| Civil Engineer (2) for Lot 1   | <p><u>Education</u><br/>Bachelor's Degree in civil engineering.</p> <p><u>Professional Experience</u><br/>At least 10 years professional experience of civil engineering work. Preferably 5 years experience in the field of water supply during construction period.</p>   |
| Mechanical Engineer for Lot 1, 6   | <p><u>Education</u><br/>Bachelor's Degree in mechanical engineering.</p> <p><u>Professional Experience</u><br/>At least 5 years professional experience related to design and/or construction of pumping stations. Experience during construction period of pumping station for 3 or more projects with a total period of 3 or more years.</p>  |
| Electrical Engineer for Lot 1, 6, 7  | <p><u>Education</u><br/>Bachelor's Degree in electrical engineering.</p> <p><u>Professional Experience</u><br/>At least 5 years professional experience related to the design and/or construction of desalination plants and pumping stations. Experience during construction period of desalination plant and pumping station for 3 or more projects with a total period of 3 or more years.</p> |
| Structural Engineer  | <p><u>Education</u><br/>Bachelor's Degree in civil engineering.</p> <p><u>Professional Experience</u><br/>At least 10 years' professional experience related to design and/or construction of desalination plants and pumping stations. Experience during construction period of desalination plant and pumping station for 5 or more projects with a total period of 3 or more years.</p>        |
| Architect  | <p><u>Education</u><br/>Bachelor's Degree in architecture.</p> <p><u>Professional Experience</u><br/>At least 10 years' professional experience related to the construction design of any plant and pumping station. Preferably experience on 5 or more projects with a total period of 3 or more years.</p>  |
| Building Utilities Engineer  | <p><u>Education</u><br/>Bachelor's Degree in any engineering or related fields.</p> <p><u>Professional Experience</u><br/>At least 5 years' professional experience related to design and construction management of building utilities at any plant and pumping station. Preferably experience on 3 or more projects with a total period of 3 or more years.</p>                                 |
| Quantity Surveyor for Lot 1  | <p><u>Education</u><br/>Bachelor's Degree in civil engineering or relevant.</p> <p><u>Professional Experience</u><br/>At least 10 years' professional experience of infrastructure development. Experience during construction period for 5 or more projects in the field of</p>  |

|   |  |
|---|--|
|   | water and sewerage.  |
| (responsible for Lot 4. Pipeline Installation, and Lots 2 and 3)        |  |
| Resident Engineer 2 /<br>Civil Engineer (1) for<br>Lot 2, 3, 4          | <u>Education</u><br>Bachelor's Degree in civil engineering.<br><u>Professional Experience</u><br>At least 15 years' professional experience of civil engineering work.<br>Preferably 5 years' experience in the field of water supply during construction period.                          |
| Civil Engineer (2) for<br>Lot 2, 3, 4                                   | <u>Education</u><br>Bachelor's Degree in civil engineering.<br><u>Professional Experience</u><br>At least 10 years' professional experience of civil engineering work.<br>Preferably 5 years' experience in the field of water supply during construction period.                          |
| Quantity Surveyor for<br>Lot 2, 3, 4                                    | <u>Education</u><br>Bachelor's Degree in civil engineering or relevant.<br><u>Professional Experience</u><br>At least 10 years' professional experience of infrastructure development.<br>Experience during construction period for 5 or more projects in the field of water and sewerage. |
| (responsible for Lots 5 and 6. Reservoirs / Pump Facility Construction) |  |
| Resident Engineer 3 /<br>Civil Engineer (1) for<br>Lot 5, 6             | <u>Education</u><br>Bachelor's Degree in civil engineering.<br><u>Professional Experience</u><br>At least 15 years' professional experience of civil engineering work.<br>Preferably 5 years' experience in the field of water supply during construction period.                          |
| Civil Engineer (2) for<br>Lot 5, 6                                      | <u>Education</u><br>Bachelor's Degree in civil engineering.<br><u>Professional Experience</u><br>At least 10 years' professional experience of civil engineering work.<br>Preferably 5 years' experience in the field of water supply during construction period.                          |
| Quantity Surveyor for<br>Lot 5, 6                                       | <u>Education</u><br>Bachelor's Degree in civil engineering or relevant.<br><u>Professional Experience</u><br>At least 10 years professional experience of infrastructure development.<br>Experience during construction period for 5 or more projects in the field of water and sewerage.  |

## 6. Task of Professional Staff

### (1) Foreign Professional Staff

#### 1) Team Leader

- a) Shall take the overall responsibility, and shall represent the project Consultant's Team in all matters relating to the performance of services, coordinating with all other consultant's staff to deliver excellent product during the stipulated time schedule;
- b) Shall oversee, and supervise the Consultant's services;
- c) Assume direct responsibility for day-to-day consulting services including day-to-day

management of all consultants' staff and co-ordination among and with them;

- d) Review existing studies / documents and other resources available and formulate the best implementation approach including programmatic project schedule;
- e) Develop and implement quality assurance program;
- f) Recommend contract payments;
- g) Review, analyze and make recommendations to SONEDE concerning variations and claims which are to be ordered/issued by SONEDE;
- h) Recommend to issue the commencement order to the Contractors;
- i) Evaluation of time extension claims and make recommendations;
- j) Provide recommendation to SONEDE for acceptance of the Contractor Performance security, advance payment security and required insurances;
- k) Explain and/or adjust ambiguities and/or discrepancies in the Contract Documents and recommend issuing any necessary clarifications or instructions;
- l) Review, verify and further detail the design of the works, recommend to approve the Contractors' working drawings and if necessary, issue further drawings and/or give instructions to the Contractor;
- m) Review and recommend to approve the proposals submitted by the Contractors;
- n) Make necessary design changes and amendments at site;
- o) Provide guidance for unforeseen matters;
- p) Progress reporting;
- q) Prepare institutional arrangement and training program for O&M;
- r) Certify all the drawings, BOQs, cost estimates and specifications;
- s) Ensure the safety conditions at work sites;
- t) Supervise commissioning, and carry out testing during commissioning;
- u) Review O&M manuals; and
- v) Develop a course module on project management including project coordination, contract administration, over-all supervision over the implementation of the project and conduct 3 days Project Management Training Course for SONEDE's project staff.

## 2) Desalination Plant Process Engineer

- a) Evaluate the proposed unit of the desalination plant;
- b) Supervise the installation procedure of the unit; and
- c) Assist the commissioning and guarantee test of the desalination plant, and evaluate the performance of the plant's equipment.

## 3) Civil Engineer

- a) Direct civil engineers assigned as national professional staff for any his/her responsible work;
- b) Evaluate the proposed desalination plant, pipe installation, and reservoir work;
- c) Supervise civil work for desalination plant, pipe installation, and reservoir work;
- d) Assess the applicability of products proposed by the contractors;
- e) Attend the test operation of mechanical and electrical equipment;
- f) Evaluate the performance of the water transmission system; and
- g) Support training on O&M on facility related to facilities and civil engineering works.

#### 4) Pipeline Engineer

- a) Direct the civil engineer for Lot 1 assigned as national professional staff regarding his/her responsible work;
- b) Evaluate the proposed pipe materials and installation;
- c) Supervise pipeline installation work;
- d) Assess the applicability of products proposed by the contractors;
- e) Attend the test and commencement of pipeline operation; and
- f) Support training on O&M on pipeline facility.

#### 5) Mechanical Engineer (Desalination Plant)

- a) Direct the mechanical engineer assigned as national professional staff for any his/her responsible work;
- b) Assist Team Leader for preparing O&M manuals on desalination plant;
- c) Evaluate the proposed mechanical facilities at the desalination plant;
- d) Assess the applicability of product proposed by the contractors related to desalination plant;
- e) Supervise the installation works of mechanical equipment for desalination plant;
- f) Attend the commissioning and guarantee test of mechanical equipment for desalination plant; and
- g) Support training on O&M on mechanical equipment for desalination plant.

#### 6) Mechanical Engineer (Transmission Pumps)

- a) Direct the mechanical engineer assigned as national professional staff for any his/her responsible work;
- b) Assist Team Leader for preparing O&M manuals on transmission pumps;
- c) Evaluate the proposed mechanical facilities of transmission pumps;
- d) Assess the applicability of product proposed by the contractors related to transmission pumps;
- e) Supervise the installation works of mechanical equipment for transmission pumps;
- f) Attend the test operation of mechanical equipment for transmission pumps; and
- g) Support training on O&M on mechanical equipment for transmission pumps.

#### 7) Electrical Engineer

- a) Direct the electrical engineer assigned as national professional staff for any his/her responsible work;
- b) Assist Team Leader for preparing O&M manuals related to electrical equipment;
- c) Evaluate the proposed electrical equipment at desalination plant and of transmission pumps;
- d) Assess the applicability of product proposed by the contractors;
- e) Supervise the installation works of electrical equipment;
- f) Attend the test operation and guarantee test of electrical equipment; and
- g) Support training on O&M on electrical equipment.

#### 8) Instrumentation Engineer

- a) Evaluate the proposed instrumentation system for the desalination plant and transmission pumps;

and

- b) Attend the commissioning and guarantee test of the desalination plant and transmission pumps, and evaluate the performance of the instrumentation system.

9) Structural Engineer

- a) Provide necessary advice to implement all construction works in order to comply with the design code.

10) Contract Specialist

- a) Evaluate the bidders' proposals;
- b) Carry out activities described in and/or that follows from the activities described in the scope of work related to procurement and contract management; and those assigned by Team Leader; and
- c) Proactively anticipate and carry out any other activity as per the scope of work.

11) Cost Estimation / Quantity Surveyor

- a) Evaluate financial proposals;
- b) Review BOQs according to Guideline of SONEDE;
- c) Prepare work standards and material / day work schedules;
- d) Evaluate relevant documents for contractors' claims and variations; and
- e) Evaluate and report to Team Leader on the progress of the works and periodical payment requested by Contractors.

**(2) Local Professional Staff**

**(responsible for all lots)**

1) Deputy Team Leader

- a) Support Team Leader;
- b) Inform data/report from national professional staff to Team Leader; and
- c) Supervise all National Professional Staff.

2) Environmental Specialist

- a) Review conception design based on the result of EIA;
- b) Update Environmental Management Plan (EMP) if necessary;
- c) Assist SONEDE to implement the measure identified in EMP;
- d) Monitor the works on the view point of the EMP and negative impacts on environment caused by the construction works;
- e) Assist SONEDE in monitoring the compliance with the requirements under the EMP, JICA Environmental Guidelines and the Tunisian Regulations; and
- f) Prepare report for environment and social environment and submit it to SONEDE.

3) Geo-technical Engineer

- a) Evaluate the foundation design of facilities; and
- b) Review geo-technical conditions on site, and foundation design of facilities.

**(responsible for Lot 1. Desalination Plant)**

4) Resident Engineer 1 / Civil Engineer (1) for Lot 1

- a) Supervise civil work for Intake/Discharge at the level of the Desalination Plant;
- b) Assess the applicability of product proposed by the contractors;
- c) Attend the test operation, commissioning and guarantee test of desalination plant;
- d) Evaluate the performance of the desalination system; and
- e) Support training on O&M of facilities related to civil engineering work.

5) Civil Engineer (2) for Lot 1

- a) Assess the applicability of product proposed by the contractors;
- b) Attend the test operation of the desalination system;
- c) Evaluate the performance of the desalination system; and
- d) Support training for O&M on facility related to civil engineering work.

6) Mechanical Engineer (for Lot 1, 6)

- a) Direct the mechanical engineer assigned as national professional staff for any his/her responsible work;
- b) Assist Team Leader for preparing O&M manuals on mechanical equipment;
- c) Assess the applicability of products proposed by the contractors related to mechanical equipment;
- d) Supervise the installation works of mechanical equipment;
- e) Attend the test operation of mechanical equipment;
- f) Evaluate the performance of the mechanical equipment; and
- g) Support training for O&M on mechanical equipment.

7) Electrical Engineer (for Lot 1, 6, 7)

- a) Assist Team Leader for preparing O&M manuals related to electrical equipment;
- b) Assess the applicability of product proposed by the contractors;
- c) Supervise the installation works of electrical equipment;
- d) Attend the test operation of electrical equipment;
- e) Evaluate the performance of the electrical equipment; and
- f) Support training for O&M on electrical equipment.

8) Structural Engineer

- a) Identify the necessary soil investigations required for the structural design and administer that work; and
- b) Provide necessary advice to implement all construction works in order to comply with the design code.

9) Architect

- a) Review building design in consideration of energy efficiency and operational environment;



- b) Supervise building construction ensuring safety condition; and
- c) Evaluate and approve the applicability of the building.

10) Building Utilities Engineer

- a) Supervise building utility construction ensuring safety condition; and
- b) Attend the building utility tests, and report to Team Leader.

11) Quantity Surveyor for Lot 1

- a) Evaluate relevant documents for contractors' claims and variations; and
- b) Evaluate and report to Team Leader for the progress of the works and periodical payment requested by Contractors.

**(responsible for Lots 2, 3, 4. Pipeline Installation)**

12) Resident Engineer 2 / Civil Engineer (1) for Lot 2, 3, 4

- a) Assess the applicability of product proposed by the contractors;
- b) Attend the test operation of the transmission system;
- c) Evaluate the performance of the transmission system; and
- d) Support training on O&M on facility related to civil engineering work.

13) Civil Engineer (2) for Lot 2, 3, 4

- a) Assess the applicability of product proposed by the contractors;
- b) Attend the test operation of the transmission system;
- c) Evaluate the performance of the transmission system; and
- d) Support training on O&M on facility related to civil engineering work.

14) Quantity Surveyor for Lot 2, 3, 4

- a) Evaluate relevant documents for contractors' claims and variations; and
- b) Evaluate and report to Team Leader for the progress of the works and periodical payment requested by Contractors.

**(responsible for Lot 5, 6. Reservoirs / Pump Facility Construction)**

15) Resident Engineer 3 / Civil Engineer (1) for Lot 5, 6

- a) Supervise civil work for reservoir and pump facilities;
- b) Assess the applicability of product proposed by the contractors;
- c) Attend the test operation of mechanical and electrical equipment;
- d) Evaluate the performance of the transmission system; and
- e) Support training for O&M on facility related to civil engineering work,

16) Civil Engineer (2) for Lot 5, 6

- a) Assess the applicability of product proposed by the contractors;
- b) Attend the test operation of mechanical and electrical equipment;
- c) Evaluate the performance of the transmission system; and

- d) Support training on O&M on facility related to civil engineering work.

17) Quantity Surveyor for Lot 5, 6

- a) Evaluate relevant documents for contractors' claims and variations; and  
 b) Evaluate and report to Team Leader for the progress of the works and periodical payment requested by Contractors.

**7. Reporting**

Within the scope of consulting services, the Consultant shall prepare and submit reports and documents to SONEDE as shown below. The Consultant shall provide electronic copy of each of these reports.

*(Example)*

| Category                         | Type of Report                                       | Timing  | No. of Copies |
|----------------------------------|--|---|---------------|
| Consultancy Services             | Inception Report                                     | Within 1 month after commencement of the services             | 10            |
|                                  | Monthly Progress Report                              | Every month   | 10            |
|                                  | Quarterly Progress Report                            | Every quarter   | 10            |
|                                  | Project Completion Report (for submission to JICA)   | At the end of Services  | 10            |
| Tender Assistance                | Bid Evaluation Report (Technical & Price)            | After evaluation of Bids                                      | 15 each       |
| Construction Supervision         | Quality Control Report                               | Every month   | 10            |
|                                  | Completion Report (and As-built Drawings, if any)    | At the end of the Project                                     | 5             |
| Training                         | Training Plan  | At appropriate timing in accordance with the Inception Report | 10            |
|                                  | Training Execution and Evaluation Report             | Within 1 month after training                                 | 10            |
| Environment and Social Safeguard | Environmental Monitoring Report                      | Every quarter   | 10            |
|                                  | Land Acquisition Monitoring Report                   | Every month   | 10            |
|                                  | Environmental and Social Safeguard Evaluation Report | At the end of the Project                                     | 20            |
| Other Report                     | Technical Report                                     | As required or upon request                                   | As required   |

Contents to be included in each report are as follows:

*(Monthly Progress report and Inception report)*

- a) Monthly Progress Report: Describes briefly and concisely all activities and progress for the previous month by the 10th day of each month. Problems encountered or anticipated will be clearly stated, together with actions to be taken or recommendations on remedial measures for

correction. Also indicates the work to be performed during the coming month.

- b) Inception Report: To be submitted within 1 month after the commencement of the services, presenting the methodologies, schedule, organization, etc.

*(Tender Assistance)*

- a) Bid Evaluation Report (technical) (15 copies) to present the results of technical evaluation and to recommend the qualified applicants.
- b) Bid Evaluation Report (price) (15 copies) to present the results of the tender to select the qualified applicants with lowest evaluated price bid.

*(Assistance in Environment Monitoring)*

- a) Environmental Monitoring Report (10 copies), to be submitted at every three (3) months after the commencement of the services, presenting the environmental impacts and implementation of environmental mitigation measures during and [at the completion of / after] the construction stage. Environmental monitoring forms attached as Appendix # will be filled and attached to the Report.
- b) Land Acquisition Monitoring Report (10 copies), to be submitted at every month during land acquisition period.
- c) Environmental and Social Safeguard Evaluation Report (20 copies), to be submitted by the end of the consulting services, presenting the EMP and EMoP prepared.

*(Construction Supervision)*

- a) Quarterly Progress Report (15 copies), to be submitted at every three (3) months during construction, presenting the progress status of the Project.
- b) Operation and Maintenance Manual (20 copies) containing technical procedures for the appropriate operation and maintenance of all project facilities.
- c) Construction Completion Report (20 copies), to be submitted within three (3) month after completion of construction, which comprises a full size of as-built drawings for all the structures and facilities completed, and the final details of the construction completed together with all data, records, material tests results, field books.

## 10.5-1 Project Cost Estimates

|      |   |         |
|------|---|---------|
| T1   | Total-----  | 10.5-2  |
| L1   | Constrtion of Seawater Desalination Plant-----                    | 10.5-5  |
| L2-1 | Procurement of Transmission Pipes (Diameters 1400mm – 1000mm)     | 10.5-34 |
| L2-2 | Procurement of Transmission Pipes (Diameters less than 1000mm) -- | 10.5-35 |
| L3   | Procurement of Valves and Others for Transmission Pipelines ----- | 10.5-36 |
| L4   | Construction of Transmission Pipelines -----                      | 10.5-37 |
| L5   | Construction of Resrvoirs -----                                   | 10.5-44 |
| L6   | Construction of Pumping Stations -----                            | 10.5-51 |
| L7   | Construction of Power Distribution Lines -----                    | 10.5-71 |

**T1 Cost Estimates Total**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items   | Specification              | Unit | Qt'ty | FC Portion (JPY) |                       | LC Portion (TND) |                    | Total                 |                    | Reference |
|---|----------------------------|------|-------|------------------|-----------------------|------------------|--------------------|-----------------------|--------------------|-----------|
|   |                            |      |       | Unit Price       | Amount                | Unit Price       | Amount             | (JPY)                 | (equiv. TND)       |           |
| <b>Lot 1 Desalination Plant (ICB)</b>                 | including intake/discharge |      |       |                  |                       |                  |                    |                       |                    |           |
| Intake & Discharge Facilities                         |                            | Ls   | 1     |                  | 4,420,968,000         |                  | 74,815,000         | 8,986,179,000         | 147,266,000        | L1-1      |
| Desalination Plant                                    |                            | Ls   | 1     |                  | 8,785,042,000         |                  | 84,084,000         | 13,915,848,000        | 228,054,000        | L1-2      |
| Transmission Pump Facility                            |                            | Ls   | 1     |                  | 738,940,000           |                  | 5,327,000          | 1,063,994,000         | 17,437,000         | L1-3      |
| Guarantee Test  |                            | Ls   | 1     |                  | 218,003,000           |                  | 26,916,000         | 1,860,417,000         | 30,489,000         | L1-4      |
| <b>Lot 1 Sub-Total</b>                                |                            |      |       |                  | <b>14,162,953,000</b> |                  | <b>191,142,000</b> | <b>25,826,438,000</b> | <b>423,245,000</b> |           |
|   | FCP:LCP                    |      |       |                  | 55%                   |                  | 45%                |                       |                    |           |
| <b>Lot 2-1 Pipe Procurement (ICB) 1000 &amp; 1400</b> |                            |      |       |                  |                       |                  |                    |                       |                    |           |
| Transmission Pipe Material                            |                            | Ls   | 1     |                  | 2,189,020,000         |                  | 3,986,000          | 2,432,246,000         | 39,860,000         | L2-1      |
| <b>Lot 2-1 Sub-Total</b>                              |                            |      |       |                  | <b>2,189,020,000</b>  |                  | <b>3,986,000</b>   | <b>2,432,245,720</b>  | <b>39,860,000</b>  |           |
|   | FCP:LCP                    |      |       |                  | 90%                   |                  | 10%                |                       |                    |           |
| <b>Lot 2-2 Pipe Procurement (ICB) less than 1000</b>  |                            |      |       |                  |                       |                  |                    |                       |                    |           |
| Transmission Pipe Material                            |                            | Ls   | 1     |                  | 435,557,000           |                  | 793,000            | 483,945,860           | 7,931,000          | L2-2      |
| <b>Lot 2-2 Sub-Total</b>                              |                            |      |       |                  | <b>435,557,000</b>    |                  | <b>793,000</b>     | <b>483,945,860</b>    | <b>7,931,000</b>   |           |
|   | FCP:LCP                    |      |       |                  | 90%                   |                  | 10%                |                       |                    |           |
| <b>Lot 2 Sub-Total</b>                                |                            |      |       |                  | <b>2,624,577,000</b>  |                  | <b>4,779,000</b>   | <b>2,916,191,580</b>  | <b>47,791,000</b>  |           |
|   | FCP:LCP                    |      |       |                  | 90%                   |                  | 10%                |                       |                    |           |

**T1 Cost Estimates Total**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items  | Specification     | Unit | Qt'ly | FC Portion (JPY) |                    | LC Portion (TND) |                   | Total                |                   | Reference |
|--|-------------------|------|-------|------------------|--------------------|------------------|-------------------|----------------------|-------------------|-----------|
|  |                   |      |       | Unit Price       | Amount             | Unit Price       | Amount            | (JPY)                | (equiv. TND)      |           |
| <b>Lot 3 Valve and Other Equipment Procurement (LCB)</b> |                   |      |       |                  |                    |                  |                   |                      |                   |           |
| Valve Material   |                   | Ls   | 1     |                  | 510,792,000        |                  | 930,000           | 567,540,600          | 9,301,000         | L3        |
| <b>Lot 3 Sub-Total</b>                                   |                   |      |       |                  | <b>510,792,000</b> |                  | <b>930,000</b>    | <b>567,540,600</b>   | <b>9,301,000</b>  |           |
|  | FCP:LCP           |      |       |                  | 90%                |                  | 10%               |                      |                   |           |
| <b>Lot 4 Pipe Installation (ICB)</b>                     |                   |      |       |                  |                    |                  |                   |                      |                   |           |
| Transmission Pipe Installatiom                           |                   | Ls   | 1     |                  | 0                  |                  | 40,270,000        | 2,457,275,400        | 40,270,000        | L4-1      |
| Valve Installation                                       |                   | Ls   | 1     |                  | 0                  |                  | 615,000           | 37,527,300           | 615,000           | L4-2      |
| Pipe Jacking   |                   | Ls   | 1     |                  | 0                  |                  | 4,369,000         | 266,596,380          | 4,369,000         | L4-3      |
| Surge Tank   | 10mx15mx2         | Ls   | 1     |                  | 40,430,000         |                  | 2,262,000         | 178,457,240          | 2,925,000         | L4-4      |
| <b>Lot 4 Sub-Total</b>                                   |                   |      |       |                  | <b>40,430,000</b>  |                  | <b>47,516,000</b> | <b>2,939,856,320</b> | <b>48,179,000</b> |           |
|  | FCP:LCP           |      |       |                  | 1%                 |                  | 99%               |                      |                   |           |
| <b>Lot 5 Reservoirs Construction (LCB)</b>               |                   |      |       |                  |                    |                  |                   |                      |                   |           |
| Mixing Chmber  | PK11              | Ls   | 1     |                  | 0                  |                  | 1,501,000         | 91,591,020           | 1,501,000         | L5-1      |
| Mixing Chmber  | Bou Merra         | Ls   | 1     |                  | 0                  |                  | 281,000           | 17,146,620           | 281,000           | L5-2      |
| Mixing Chmber  | PK10              | Ls   | 1     |                  | 0                  |                  | 560,000           | 34,171,200           | 560,000           | L5-3      |
| Mixing Chmber  | PK14              | Ls   | 1     |                  | 0                  |                  | 472,000           | 28,801,440           | 472,000           | L5-4      |
| Mixing Chmber  | Sidi Salah EH     | Ls   | 1     |                  | 0                  |                  | 319,000           | 19,465,000           | 319,000           | L5-5      |
| Reservoir  | Bou Merra 5 000m3 | Ls   | 1     |                  | 0                  |                  | 1,890,000         | 115,327,800          | 1,890,000         | L5-6      |
| <b>Lot 5 Sub-Total</b>                                   |                   |      |       |                  | <b>0</b>           |                  | <b>5,023,000</b>  | <b>306,503,460</b>   | <b>5,023,000</b>  |           |
|  | FCP:LCP           |      |       |                  | 0%                 |                  | 100%              |                      |                   |           |

**T1 Cost Estimates Total**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items   | Specification | Unit | Qt'ly | FC Portion (JPY) |                       | LC Portion (TND) |                    | Total                 |                    | Reference |
|---|---------------|------|-------|------------------|-----------------------|------------------|--------------------|-----------------------|--------------------|-----------|
|   |               |      |       | Unit Price       | Amount                | Unit Price       | Amount             | (JPY)                 | (equiv. TND)       |           |
| <b>Lot 6 Pump Facilities Construction (ICB)</b> |               |      |       |                  |                       |                  |                    |                       |                    |           |
| PK11 (for PK10 & Bou Merrra)                    |               | Ls   | 1     |                  | 789,808,000           |                  | 6,059,000          | 1,159,528,000         | 19,002,000         | L6-1      |
| PK10 (for PK14)                                 |               | Ls   | 1     |                  | 469,333,000           |                  | 4,543,000          | 746,546,860           | 12,234,000         | L6-2      |
| Pk14 (for Sidi Salah EH)                        |               | Ls   | 1     |                  | 306,074,000           |                  | 3,167,000          | 499,324,340           | 8,183,000          | L6-3      |
| <b>Lot 6 Sub-Total</b>                          |               |      |       |                  | <b>1,565,215,000</b>  |                  | <b>13,769,000</b>  | <b>2,405,399,380</b>  | <b>39,420,000</b>  |           |
|   | FCP:LCP       |      |       |                  | 65%                   |                  | 35%                |                       |                    |           |
| <b>Lot 7 Power Supply Line (by STEG)</b>        |               |      |       |                  |                       |                  |                    |                       |                    |           |
| Power Supply Line Construction                  | 150kV - 15km  | Ls   | 1     |                  | 0                     |                  | 4,350,000          | 265,437,000           | 4,350,000          | L7-1      |
| Travées   |               | Ls   | 1     |                  | 0                     |                  | 2,400,000          | 146,448,000           | 2,400,000          | L7-2      |
| Assistance                                      |               | Ls   | 1     |                  | 0                     |                  | 533,000            | 32,523,660            | 533,000            | L7-3      |
| <b>Lot 7 Sub-Total</b>                          |               |      |       |                  | <b>0</b>              |                  | <b>7,283,000</b>   | <b>444,408,660</b>    | <b>7,283,000</b>   |           |
|   | FCP:LCP       |      |       |                  | 0%                    |                  | 100%               |                       |                    |           |
| Total Cost                                      |               |      |       |                  | 18,903,967,000        |                  | 270,442,000        | 35,406,337,840        | 580,242,000        |           |
| <b>Total Cost (rounded)</b>                     |               |      |       |                  | <b>18,903,967,000</b> |                  | <b>270,442,000</b> | <b>35,406,338,000</b> | <b>580,242,000</b> |           |
|   | FCP:LCP       |      |       |                  | 53%                   |                  | 47%                |                       |                    |           |

**L1 Desalination Plant**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                                   | Specification | Unit | Qt'ty | FC Portion (JPY) |                       | LC Portion (TND) |                    | Total                 |                    | Reference        |
|---|---------------|------|-------|------------------|-----------------------|------------------|--------------------|-----------------------|--------------------|------------------|
|   |               |      |       | Unit Price       | Amount                | Unit Price       | Amount             | (JPY)                 | (equiv. TND)       |                  |
| Intake & Discharge Facilities           |               | Ls   | 1     |                  | 4,420,968,000         |                  | 74,815,000         | 8,986,179,000         | 147,266,000        | L1-1             |
| Desalination Plant                      |               | Ls   | 1     |                  | 8,785,042,000         |                  | 84,084,000         | 13,915,848,000        | 228,054,000        | L1-2             |
| Transmission Pump Facility              |               | Ls   | 1     |                  | 738,940,000           |                  | 5,327,000          | 1,063,994,000         | 17,437,000         | L1-3             |
| Guarantee Test (for Desalination Plant) |               | Ls   | 1     |                  | 218,003,000           |                  | 26,916,000         | 1,860,417,000         | 30,489,000         | L1-4<br>12months |
|   |               |      |       |                  |                       |                  |                    |                       |                    |                  |
|   |               |      |       |                  |                       |                  |                    |                       |                    |                  |
|   |               |      |       |                  |                       |                  |                    |                       |                    |                  |
|   |               |      |       |                  |                       |                  |                    |                       |                    |                  |
|   |               |      |       |                  |                       |                  |                    |                       |                    |                  |
|   |               |      |       |                  |                       |                  |                    |                       |                    |                  |
|   |               |      |       |                  |                       |                  |                    |                       |                    |                  |
|   |               |      |       |                  |                       |                  |                    |                       |                    |                  |
|   |               |      |       |                  |                       |                  |                    |                       |                    |                  |
|   |               |      |       |                  |                       |                  |                    |                       |                    |                  |
|   |               |      |       |                  |                       |                  |                    |                       |                    |                  |
| Total                                   |               |      |       |                  | 14,162,953,000        |                  | 191,142,000        |                       |                    |                  |
| <b>Total Cost (rounded)</b>             | <b>to T1</b>  |      |       |                  | <b>14,162,953,000</b> |                  | <b>191,142,000</b> | <b>25,826,438,000</b> | <b>423,245,000</b> | <b>L1</b>        |
|   | FCP:LCP       |      |       |                  |                       | 55%              | 45%                |                       |                    |                  |

10.5-5



### L1-1 Intake & Discharge Facilities

Exchange Rate: 1.00US\$= 119.60JPY    1.000TND= 61.02JPY

| Items                        | Specification   | Unit | Qt'ty | FC Portion (JPY)     | LC Portion (TND)  | Total                |                    | Reference        |
|------------------------------|-----------------|------|-------|----------------------|-------------------|----------------------|--------------------|------------------|
|                              |                 |      |       |                      |                   | (JPY)                | (equiv. TND)       |                  |
|                              |                 |      |       |                      |                   |                      |                    |                  |
| Intake & Discharge Pipelines | HDPE 2000mm x 2 | Ls   | 1     | 4,420,968,000        | 67,193,000        | 8,521,085,000        | 139,644,000        | L1-1-1           |
| Intake Pit                   | 42x20x8.3m      | Ls   | 1     | 0                    | 6,037,000         | 368,378,000          | 6,037,000          | L1-1-2      Work |
| Outfall Pit                  | 22x7.8x11m      | Ls   | 1     | 0                    | 1,585,000         | 96,717,000           | 1,585,000          | L1-1-3      Work |
|                              |                 |      |       |                      |                   |                      |                    |                  |
|                              |                 |      |       |                      |                   |                      |                    |                  |
|                              |                 |      |       |                      |                   |                      |                    |                  |
|                              |                 |      |       |                      |                   |                      |                    |                  |
|                              |                 |      |       |                      |                   |                      |                    |                  |
|                              |                 |      |       |                      |                   |                      |                    |                  |
|                              |                 |      |       |                      |                   |                      |                    |                  |
|                              |                 |      |       |                      |                   |                      |                    |                  |
|                              |                 |      |       |                      |                   |                      |                    |                  |
| <b>Total</b>                 |                 |      |       | 4,420,968,000        | 74,815,000        |                      |                    |                  |
| <b>Total Cost (Rounded)</b>  | <b>to L1</b>    |      |       | <b>4,420,968,000</b> | <b>74,815,000</b> | <b>8,986,179,000</b> | <b>147,266,000</b> | <b>L1-1</b>      |
|                              | FCP:LCP         |      |       | 49%                  | 51%               |                      |                    |                  |

### L1-1-1 Intake & Discharge Pipelines

Exchange Rate: 1.00US\$= 119.60JPY    1.000TND= 61.02JPY

| Items                       | Specification          | Unit | Qt'ty | FC Portion (JPY)     | LC Portion (TND)  | Total                |                    | Reference             |
|-----------------------------|------------------------|------|-------|----------------------|-------------------|----------------------|--------------------|-----------------------|
|                             |                        |      |       |                      |                   | (JPY)                | (equiv. TND)       |                       |
| Pipe material               |                        |      |       |                      |                   |                      |                    |                       |
| Intake HDPE φ2000mm (ID)    | 3600m×2lines           | Ls   | 1     | 2,782,676,160        | 0                 | 2,782,676,160        | 45,602,690         | ID: Internal Diameter |
| Discharge HDPE φ1800mm (ID) | 4400m                  | Ls   | 1     | 1,458,292,000        | 0                 | 1,458,292,000        | 23,898,591         | ID: Internal Diameter |
| Intake head                 | Type TK-2000 x 2 heads | Ls   | 1     | 0                    | 3,528,000         | 215,278,560          | 3,528,000          | cost                  |
| Discharge head              | Multi Nozzle 1800      | Ls   | 1     | 0                    | 1,960,000         | 119,599,200          | 1,960,000          | cost                  |
| Intake Pipe Assembly        | 3600m×2                | Ls   | 1     | 0                    | 4,403,000         | 268,671,060          | 4,403,000          |                       |
| Discharge Pipe Assembly     | 4400m                  | Ls   | 1     | 0                    | 2,285,000         | 139,430,700          | 2,285,000          |                       |
| Pipe Material sub-total     |                        |      |       | 4,240,968,160        | 12,176,000        | 4,983,947,680        | 81,677,281         |                       |
| Pipe Installation           |                        |      |       |                      |                   |                      |                    |                       |
| Intake Pipe                 | ID2000x3600x2          | Ls   | 1     | 0                    | 5,179,000         | 316,022,580          | 5,179,000          |                       |
| Discharge Pipe              | ID1800x4400x1          | Ls   | 1     | 0                    | 3,105,000         | 189,467,100          | 3,105,000          |                       |
| Intake head                 | Type TK-2000 x 2       | Ls   | 1     | 0                    | 94,000            | 5,735,880            | 94,000             |                       |
| Discharge head              | Multi Nozzle 1800      | Ls   | 1     | 0                    | 47,000            | 2,867,940            | 47,000             |                       |
| Pipe Installation sub-total |                        |      |       | 0                    | 8,425,000         | 514,093,500          | 8,425,000          | Work                  |
| On-shore part civil work    | & backfilling          | Ls   | 1     | 0                    | 7,559,000         | 461,250,000          | 7,559,000          | L1-1-1-1    Work      |
| Off-shore part civil work   | & backfilling          | Ls   | 1     | 180,000,000          | 31,857,000        | 2,123,914,000        | 34,807,000         | L1-1-1-2    Work      |
| Other Miscellaneous. Work   | 15% of Work            | Ls   | 1     | 0                    | 7,176,150         | 437,888,673          | 7,176,150          | 2                     |
|                             |                        |      |       |                      |                   |                      |                    |                       |
| Total                       |                        |      |       | 4,420,968,160        | 67,193,150        |                      |                    |                       |
| <b>Total Cost (Rounded)</b> | <b>to L1-1</b>         |      |       | <b>4,420,968,000</b> | <b>67,193,000</b> | <b>8,521,085,000</b> | <b>139,644,000</b> | <b>L1-1-1</b>         |
|                             | FCP:LCP                |      |       | 52%                  | 48%               |                      |                    |                       |

**L1-1-1 On-shore Pipeline Civil Work**

49000

Exchange Rate: 1.00US\$= 119.60JPY 1.000TND= 61.02JPY

| Items                       | Specification    | Unit           | Qt'ty  | FC Portion (JPY) |          | LC Portion (TND) |                  | Total              |                  | Reference                       |
|-----------------------------|------------------|----------------|--------|------------------|----------|------------------|------------------|--------------------|------------------|---------------------------------|
|                             |                  |                |        | Unit Price       | Amount   | Unit Price       | Amount           | (JPY)              | (equiv. TND)     |                                 |
| Excavation                  | sandy soil       | m <sup>3</sup> | 23,500 | 0                | 0        | 16.500           | 387,750          | 23,660,505         | 387,750          |                                 |
| Backfilling                 | excavated soil   | m <sup>3</sup> | 16,700 | 0                | 0        | 11.000           | 183,700          | 11,209,374         | 183,700          |                                 |
| Surplus Soil Transport      |                  | m <sup>3</sup> | 6,800  | 0                | 0        | 23.100           | 157,080          | 9,585,022          | 157,080          |                                 |
| Foundation                  | Gravel           | m <sup>3</sup> | 2,900  | 0                | 0        | 74.800           | 216,920          | 13,236,458         | 216,920          | Material,<br>Placing,           |
| Sheet Pile                  | IV Type L=17m    | ton            | 2,717  | 0                | 0        | 1760.000         | 4,781,920        | 291,792,758        | 4,781,920        | purchase x 80% (scrap<br>20%) x |
| Sheet Pile Driving          |                  | pcs            | 2,100  | 0                | 0        | 280.500          | 589,050          | 35,943,831         | 589,050          |                                 |
| Sheet Pile Removal          |                  | pcs            | 2,100  | 0                | 0        | 56.100           | 117,810          | 7,188,766          | 117,810          | 20% of driving                  |
| Tie-rod, waling and H pile  |                  | ton            | 475    | 0                | 0        | 1536.700         | 729,933          | 44,540,512         | 729,933          | purchase x 80% (scrap<br>20%)   |
| Anchor Pile Driving         | H300 L=12m       | pcs            | 420    | 0                | 0        | 230.000          | 96,600           | 5,894,532          | 96,600           |                                 |
| Anchor Pile Removal         |                  | pcs            | 420    | 0                | 0        | 46.000           | 19,320           | 1,178,906          | 19,320           | 20% of driving                  |
| Tie-rod & waling Setting    |                  | ton            | 119    | 0                | 0        | 1560.000         | 185,640          | 11,327,753         | 185,640          |                                 |
| Tie-rod & waling Removal    |                  | ton            | 119    | 0                | 0        | 780.000          | 92,820           | 5,663,876          | 92,820           | 50% of driving                  |
|                             |                  |                |        |                  |          |                  |                  |                    |                  |                                 |
| Total                       |                  |                |        |                  | 0        |                  | 7,558,543        |                    |                  |                                 |
| <b>Total Cost (Rounded)</b> | <b>to L1-1-1</b> |                |        |                  | <b>0</b> |                  | <b>7,559,000</b> | <b>461,250,000</b> | <b>7,559,000</b> | <b>L1-1-1-1</b>                 |
|                             | FCP:LCP          |                |        |                  | 0%       |                  | 100%             |                    |                  |                                 |

10.5-8

**L1-1-1-2 Off-shore Pipeline Civil Work**

Exchange Rate: 1.00US\$= 119.60JPY 1.000TND= 61.02JPY

| Items                           | Specification          | Unit           | Qt'y    | FC Portion (JPY) |                    | LC Portion (TND) |                   | Total                |                   | Reference       |
|---------------------------------|------------------------|----------------|---------|------------------|--------------------|------------------|-------------------|----------------------|-------------------|-----------------|
|                                 |                        |                |         | Unit Price       | Amount             | Unit Price       | Amount            | (JPY)                | (equiv. TND)      |                 |
| Excavation                      | sandy soil             | m <sup>3</sup> | 389,600 | 0                | 0                  | 27.400           | 10,675,040        | 651,390,941          | 10,675,040        |                 |
| Backfilling                     | excavated soil         | m <sup>3</sup> | 288,000 | 0                | 0                  | 27.400           | 7,891,200         | 481,521,024          | 7,891,200         |                 |
| Surplus Soil Transport          |                        | m <sup>3</sup> | 101,600 | 0                | 0                  | 9.800            | 995,680           | 60,756,394           | 995,680           |                 |
| Foundation Material & Placing   | Gravel                 | m <sup>3</sup> | 28,300  | 0                | 0                  | 96.000           | 2,716,800         | 165,779,136          | 2,716,800         |                 |
| Foundation Levelling            | Gravel                 | m <sup>2</sup> | 40,400  | 0                | 0                  | 92.100           | 3,720,840         | 227,045,657          | 3,720,840         |                 |
| Armour Stone                    | Rubble Stone           | m <sup>3</sup> | 55,600  | 0                | 0                  | 94.100           | 5,231,960         | 319,254,199          | 5,231,960         |                 |
| Turbid Water Protection Barrier | floating silt curtains | lot            | 1       | 180,000,000      | 180,000,000        | 327,761.390      | 327,761           | 200,000,000          | 3,277,614         |                 |
| Artificial Reef                 | Concrete Blocks        | lot            | 1       | 0                | 0                  | 297,922.000      | 297,922           | 18,179,200           | 297,922           |                 |
|                                 |                        |                |         |                  |                    |                  |                   |                      |                   |                 |
|                                 |                        |                |         |                  |                    |                  |                   |                      |                   |                 |
|                                 |                        |                |         |                  |                    |                  |                   |                      |                   |                 |
|                                 |                        |                |         |                  |                    |                  |                   |                      |                   |                 |
|                                 |                        |                |         |                  |                    |                  |                   |                      |                   |                 |
|                                 |                        |                |         |                  |                    |                  |                   |                      |                   |                 |
|                                 |                        |                |         |                  |                    |                  |                   |                      |                   |                 |
| <b>Total</b>                    |                        |                |         |                  | 180,000,000        |                  | 31,857,203        |                      |                   |                 |
| <b>Total Cost (Rounded)</b>     | <b>to L1-1-1</b>       |                |         |                  | <b>180,000,000</b> |                  | <b>31,857,000</b> | <b>2,123,914,000</b> | <b>34,807,000</b> | <b>L1-1-1-2</b> |
|                                 | FCP:LCP                |                |         |                  | 8%                 |                  | 92%               |                      |                   |                 |

**L1-1-2 Intake Pit**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

10-5-10

| Items                          | Specification                           | Unit           | Qt'ty  | FC Portion (JPY) |          | LC Portion (TND) |                  | Total              |                  | Reference   |
|--------------------------------|---|----------------|--------|------------------|----------|------------------|------------------|--------------------|------------------|---|
|                                |   |                |        | Unit Price       | Amount   | Unit Price       | Amount           | (JPY)              | (equiv. TND)     |   |
| Pile driving work              | 300x300, L = 10m<br>Including Materials | m              | 740    | 0                | 0        | 77.000           | 56,980           | 3,476,920          | 56,980           | 74pcs x 10m   |
| Pile Head Treatment            | 300x300                                 | pcs            | 74     | 0                | 0        | 4.400            | 326              | 19,893             | 326              |   |
| Excavation                     |   | m <sup>3</sup> | 10,660 | 0                | 0        | 16.500           | 175,890          | 10,732,808         | 175,890          |   |
| Backfilling                    |   | m <sup>3</sup> | 3,065  | 0                | 0        | 11.000           | 33,715           | 2,057,289          | 33,715           |   |
| Surplus Soil Transport         |   | m <sup>3</sup> | 7,595  | 0                | 0        | 23.100           | 175,445          | 10,705,654         | 175,445          |   |
| Gravel                         |   | m <sup>3</sup> | 171    | 0                | 0        | 74.800           | 12,791           | 780,507            | 12,791           |   |
| Lean Concrete                  |   | m <sup>3</sup> | 86     | 0                | 0        | 440.000          | 37,840           | 2,308,997          | 37,840           |   |
| Reinforced Concrete            |   | m <sup>3</sup> | 3,070  | 0                | 0        | 935.000          | 2,870,450        | 175,154,859        | 2,870,450        |   |
| Formwork                       |   | m <sup>2</sup> | 4,063  | 0                | 0        | 62.700           | 254,750          | 15,544,845         | 254,750          |   |
| Rebar Fabrication and Assembly |   | ton            | 614    | 0                | 0        | 1,320.000        | 810,480          | 49,455,490         | 810,480          | 200kg/m3  |
| Sheet Pile Driving             | Type IV 17m                             | pcs            | 340    | 0                | 0        | 280.500          | 95,370           | 5,819,477          | 95,370           |   |
| Sheet Pile removing            | Type IV 17m                             | pcs            | 340    | 0                | 0        | 56.100           | 19,074           | 1,163,895          | 19,074           | 20% of driving  |
| Sheet Pile                     | Type IV 17m                             | ton            | 440    | 0                | 0        | 0.000            | 0                | 0                  | 0                | reuse of sheet pile used for on-shore pipe civil work |
| Waling and Strut Installation  | H300*300*10*15                          | ton            | 118    | 0                | 0        | 1,430.000        | 168,740          | 10,296,515         | 168,740          |   |
| Waling and Strut Removal       | H300*300*10*15                          | ton            | 118    | 0                | 0        | 715.000          | 84,370           | 5,148,257          | 84,370           |   |
| Waling & Strut                 | H300*300*10*15                          | ton            | 118    | 0                | 0        | 286.000          | 33,748           | 2,059,303          | 33,748           | purchase x 20%  |
| Other Miscellaneous Work       | 25% of Structure Work                   | Ls             | 1      |                  | 0        |                  | 1,207,492        | 73,681,162         | 1,207,492        |   |
| Total                          |   |                |        |                  | 0        |                  | 6,037,461        |                    |                  |   |
| <b>Total Cost (Rounded)</b>    | <b>to L1-1</b>                          |                |        |                  | <b>0</b> |                  | <b>6,037,000</b> | <b>368,378,000</b> | <b>6,037,000</b> | <b>L1-1-2</b>   |
|                                | FCP:LCP                                 |                |        |                  | 0%       |                  | 100%             |                    |                  |   |

**L1-1-3 Outfall Pit**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

10-5-11

| Items                          | Specification                           | Unit           | Qt'ty | FC Portion (JPY) |          | LC Portion (TND) |                  | Total             |                  | Reference   |
|--------------------------------|---|----------------|-------|------------------|----------|------------------|------------------|-------------------|------------------|---|
|                                |   |                |       | Unit Price       | Amount   | Unit Price       | Amount           | (JPY)             | (equiv. TND)     |   |
| Pile driving work              | 300x300, L = 10m<br>Including Materials | m              | 180   | 0                | 0        | 77.000           | 13,860           | 845,737           | 13,860           | 18pcs x 10m   |
| Pile Head Treatment            | 300x300                                 | pcs            | 18    | 0                | 0        | 4.400            | 79               | 4,821             | 79               |   |
| Excavation                     |   | m <sup>3</sup> | 2,853 | 0                | 0        | 16.500           | 47,075           | 2,872,517         | 47,075           |   |
| Backfilling                    |   | m <sup>3</sup> | 1,237 | 0                | 0        | 11.000           | 13,607           | 830,299           | 13,607           |   |
| Surplus Soil Transport         |   | m <sup>3</sup> | 1,616 | 0                | 0        | 23.100           | 37,330           | 2,277,877         | 37,330           |   |
| Gravel                         |   | m <sup>3</sup> | 41    | 0                | 0        | 74.800           | 3,067            | 187,148           | 3,067            |   |
| Lean Concrete                  |   | m <sup>3</sup> | 20    | 0                | 0        | 440.000          | 8,800            | 536,976           | 8,800            |   |
| Reinforced Concrete            |   | m <sup>3</sup> | 778   | 0                | 0        | 935.000          | 727,430          | 44,387,779        | 727,430          |   |
| Formwork                       |   | m <sup>2</sup> | 1,265 | 0                | 0        | 62.700           | 79,316           | 4,839,862         | 79,316           |   |
| Rebar Fabrication and Assembly |   | ton            | 156   | 0                | 0        | 1,320.000        | 205,920          | 12,565,238        | 205,920          | 200kg/m3  |
| Sheet Pile Driving             | Type IV 17m                             | pcs            | 189   | 0                | 0        | 280.500          | 53,015           | 3,234,975         | 53,015           |   |
| Sheet Pile removing            | Type IV 17m                             | pcs            | 189   | 0                | 0        | 56.100           | 10,603           | 646,995           | 10,603           | 20% of driving  |
| Sheet Pile                     | Type IV 17m                             | ton            | 245   | 0                | 0        | 0.000            | 0                | 0                 | 0                | reuse of sheet pile used for on-shore pipe civil work |
| Waling and Strut Installation  | H300*300*10*15                          | ton            | 28    | 0                | 0        | 1,430.000        | 40,040           | 2,443,241         | 40,040           |   |
| Waling and Strut Removal       | H300*300*10*15                          | ton            | 28    | 0                | 0        | 715.000          | 20,020           | 1,221,620         | 20,020           |   |
| Waling & Strut                 | H300*300*10*15                          | ton            | 28    | 0                | 0        | 286.000          | 8,008            | 488,648           | 8,008            | purchase x 20%  |
| Other Miscellaneous Work       | 25% of Structure Work                   | Ls             | 1     |                  | 0        |                  | 317,043          | 19,345,964        | 317,043          |   |
| Total                          |   |                |       |                  | 0        |                  | 1,585,213        |                   |                  |   |
| <b>Total Cost (Rounded)</b>    | <b>to L1-1</b>                          |                |       |                  | <b>0</b> |                  | <b>1,585,000</b> | <b>96,717,000</b> | <b>1,585,000</b> | <b>L1-1-3</b>   |
|                                | FCP:LCP                                 |                |       |                  | 0%       |                  | 100%             |                   |                  |   |

**L1-2 Desalination Plant**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                       | Specification | Unit | Qt'ty | FC Portion (JPY) |                      | LC Portion (TND) |                   | Total                 |                    | Reference   |
|-----------------------------|---------------|------|-------|------------------|----------------------|------------------|-------------------|-----------------------|--------------------|-------------|
|                             |               |      |       | Unit Price       | Amount               | Unit Price       | Amount            | (JPY)                 | (equiv. TND)       |             |
| Foundation                  |               | Ls   | 1     |                  | 0                    |                  | 4,817,000         | 293,933,000           | 4,817,000          | L1-2-1      |
| Buildings                   |               | Ls   | 1     |                  | 774,904,000          |                  | 39,576,000        | 3,189,832,000         | 52,275,000         | L1-2-2      |
| Desalination Plant          |               | Ls   | 1     |                  | 6,661,213,000        |                  | 18,819,000        | 7,809,548,000         | 127,983,000        | L1-2-3      |
| Filtered Water Tank         | 15mx50mx5mH   | Ls   | 1     |                  | 0                    |                  | 1,737,000         | 105,992,000           | 1,737,000          | L1-2-4      |
| Drain Tank                  | 15m38mx5mH    | Ls   | 1     |                  | 0                    |                  | 1,316,000         | 80,302,000            | 1,316,000          | L1-2-5      |
| Brine Tank                  | 12mx40mx5mH   | Ls   | 1     |                  | 0                    |                  | 1,132,000         | 69,075,000            | 1,132,000          | L1-2-6      |
| Water Reservoir             | V=5,000m3 x 5 | Ls   | 1     |                  | 0                    |                  | 10,640,000        | 649,253,000           | 10,640,000         | L1-2-7      |
| In-yard Pipe                |               | Ls   | 1     |                  | 0                    |                  | 2,145,000         | 130,888,000           | 2,145,000          | L1-2-8      |
| Electrical Facilities       |               | Ls   | 1     |                  | 1,348,925,000        |                  | 3,902,000         | 1,587,025,000         | 26,008,000         | L1-2-9      |
|                             |               |      |       |                  |                      |                  |                   |                       |                    |             |
|                             |               |      |       |                  |                      |                  |                   |                       |                    |             |
|                             |               |      |       |                  |                      |                  |                   |                       |                    |             |
|                             |               |      |       |                  |                      |                  |                   |                       |                    |             |
| <b>Total</b>                |               |      |       |                  | 8,785,042,000        |                  | 84,084,000        |                       |                    |             |
| <b>Total Cost (Rounded)</b> | <b>to L1</b>  |      |       |                  | <b>8,785,042,000</b> |                  | <b>84,084,000</b> | <b>13,915,848,000</b> | <b>228,054,000</b> | <b>L1-2</b> |
|                             | FCP:LCP       |      |       |                  | 63%                  |                  | 37%               |                       |                    |             |

10.5-12

**L1-2-1 Foundation for Equipment**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                          | Specification                           | Unit           | Qt'y    | FC Portion (JPY) |          | LC Portion (TND) |                  | Total              |                  | Reference                 |
|--------------------------------|---|----------------|---------|------------------|----------|------------------|------------------|--------------------|------------------|---------------------------|
|                                |   |                |         | Unit Price       | Amount   | Unit Price       | Amount           | (JPY)              | (equiv. TND)     |                           |
| <b>Foundation</b>              |   |                |         |                  |          |                  |                  |                    |                  |                           |
| Dual Media & Polishing Filter  | 18x70x0.3m height                       |                | 4       |                  |          |                  |                  |                    |                  |                           |
| Pile Driving Work              | 500x500, L = 10m<br>Including Materials | m              | 2,500   | 0                | 0        | 110.000          | 275,000          | 16,780,500         | 275,000          | L=250pcs×10m              |
| Pile Head Treatment            | 500x500                                 | pcs            | 250     | 0                | 0        | 6.600            | 1,650            | 100,683            | 1,650            |                           |
| Reinforced Concrete            |   | m <sup>3</sup> | 1,512   | 0                | 0        | 935.000          | 1,413,720        | 86,265,194         | 1,413,720        |                           |
| Formwork                       |   | m <sup>2</sup> | 53      | 0                | 0        | 62.700           | 3,323            | 202,776            | 3,323            |                           |
| Rebar Fabrication and Assembly |   | ton            | 257     | 0                | 0        | 1,320.000        | 339,293          | 20,703,647         | 339,293          | Rebar/Concrete = 170kg/m3 |
| Cartridge Filter               | 3x6x0.3m height                         |                | 4       |                  |          |                  |                  |                    |                  |                           |
| Reinforced Concrete            |   | m <sup>3</sup> | 22      | 0                | 0        | 935.000          | 20,570           | 1,255,181          | 20,570           |                           |
| Formwork                       |   | m <sup>2</sup> | 6       | 0                | 0        | 62.700           | 376              | 22,956             | 376              |                           |
| Rebar Fabrication and Assembly |   | ton            | 4       | 0                | 0        | 1,320.000        | 4,937            | 301,244            | 4,937            | Rebar/Concrete = 170kg/m3 |
| High Pressure Pump             | 3x8x0.3m height                         |                | 4       |                  |          |                  |                  |                    |                  |                           |
| Reinforced Concrete            |   | m <sup>3</sup> | 29      | 0                | 0        | 935.000          | 27,115           | 1,654,557          | 27,115           |                           |
| Formwork                       |   | m <sup>2</sup> | 7       | 0                | 0        | 62.700           | 439              | 26,782             | 439              |                           |
| Rebar Fabrication and Assembly |   | ton            | 5       | 0                | 0        | 1,320.000        | 6,508            | 397,094            | 6,508            | Rebar/Concrete = 170kg/m3 |
| RO system                      | 6x10x0.3m height                        |                | 4       |                  |          |                  |                  |                    |                  |                           |
| Reinforced Concrete            |   | m <sup>3</sup> | 72      | 0                | 0        | 935.000          | 67,320           | 4,107,866          | 67,320           |                           |
| Formwork                       |   | m <sup>2</sup> | 10      | 0                | 0        | 62.700           | 627              | 38,260             | 627              |                           |
| Rebar Fabrication and Assembly |   | ton            | 12      | 0                | 0        | 1,320.000        | 16,157           | 985,888            | 16,157           | Rebar/Concrete = 170kg/m3 |
| <b>Ground levelling</b>        |   | m <sup>3</sup> | 200,000 | 0                | 0        | 13.200           | 2,640,000        | 161,092,800        | 2,640,000        |                           |
| Total                          |   |                |         |                  | 0        |                  | 4,817,034        |                    |                  |                           |
| <b>Total Cost (Rounded)</b>    | <b>to L1-2</b>                          |                |         |                  | <b>0</b> |                  | <b>4,817,000</b> | <b>293,933,000</b> | <b>4,817,000</b> | <b>L1-2-1</b>             |
|                                | FCP:LCP                                 |                |         |                  | 0%       |                  | 100%             |                    |                  |                           |

10.5-13



**L1-2-2 Building (Desalination Plant)**

Exchange Rate: 1.00US\$= 119.60JPY 1.000TND= 61.02JPY

| Items                                | Specification                           | Unit           | Qt'ty  | FC Portion (JPY) |                    | LC Portion (TND) |                   | Total                |                   | Reference       |
|--------------------------------------|---|----------------|--------|------------------|--------------------|------------------|-------------------|----------------------|-------------------|-----------------|
|                                      |   |                |        | Unit Price       | Amount             | Unit Price       | Amount            | (JPY)                | (equiv. TND)      |                 |
| <b>Pre-treatment system Building</b> |   |                |        |                  |                    |                  |                   |                      |                   |                 |
| Structure                            | 130x80x7.5m height                      | m <sup>2</sup> | 10,400 | 24,667           | 256,536,800        | 1155.000         | 12,012,000        | 989,509,040          | 16,216,143        | Structure       |
| overhead crane& misc. work           |   | Ls             | 1      |                  | 128,268,400        |                  | 6,006,000         | 494,754,520          | 8,108,071         | Structure x 50% |
| waterproofing                        |   | m <sup>2</sup> | 10,400 | 0                | 0                  | 42.900           | 446,160           | 27,224,683           | 446,160           |                 |
| Pile Driving Work                    | 500x500, L = 20m<br>Including Materials | m              | 11,560 | 0                | 0                  | 110.000          | 1,271,600         | 77,593,032           | 1,271,600         | L=578pcs×20m    |
| Pile Head Treatment                  | 500x500                                 | pcs            | 578    | 0                | 0                  | 6.600            | 3,815             | 232,779              | 3,815             |                 |
| <b>sub-total</b>                     |   |                |        |                  | <b>384,805,200</b> |                  | <b>19,739,575</b> | <b>1,589,314,054</b> | <b>26,045,789</b> |                 |
| <b>RO system Building</b>            |   |                |        |                  |                    |                  |                   |                      |                   |                 |
| Structure                            | 630x86x12m height                       | m <sup>2</sup> | 5,418  | 24,667           | 133,645,806        | 1155.000         | 6,257,790         | 515,496,152          | 8,447,987         | Structure       |
| overhead crane& misc. work           |   | Ls             | 1      |                  | 66,822,903         |                  | 3,128,895         | 257,748,076          | 4,223,993         | Structure x 50% |
| waterproofing                        |   | m <sup>2</sup> | 5,418  | 0                | 0                  | 42.900           | 232,432           | 14,183,013           | 232,432           |                 |
| Pile Driving Work                    | 500x500, L = 20m<br>Including Materials | m              | 6,020  | 0                | 0                  | 110.000          | 662,200           | 40,407,444           | 662,200           | L=301pcs×20m    |
| Pile Head Treatment                  | 500x500                                 | pcs            | 301    | 0                | 0                  | 6.600            | 1,987             | 121,222              | 1,987             |                 |
| <b>sub-total</b>                     |   |                |        |                  | <b>200,468,709</b> |                  | <b>10,283,304</b> | <b>827,955,907</b>   | <b>13,568,599</b> |                 |

10.5-14

**L1-2-2 Building (Desalination Plant)**

Exchange Rate: 1.00US\$= 119.60JPY 1.000TND= 61.02JPY

| Items                           | Specification                           | Unit           | Qt'ty | FC Portion (JPY) |                   | LC Portion (TND) |                  | Total              |                  | Reference          |
|---------------------------------|---|----------------|-------|------------------|-------------------|------------------|------------------|--------------------|------------------|--------------------|
|                                 |   |                |       | Unit Price       | Amount            | Unit Price       | Amount           | (JPY)              | (equiv. TND)     |                    |
| <b>Administration Building</b>  |   |                |       |                  |                   |                  |                  |                    |                  |                    |
| Structure                       | 16x40x8m height                         | m <sup>2</sup> | 1,800 | 49,335           | 88,803,000        | 2310.000         | 4,158,000        | 342,524,160        | 5,613,310        | three stories 200% |
| Pile Driving Work               | 500×500, L = 20m<br>Including Materials | m              | 840   | 0                | 0                 | 110.000          | 92,400           | 5,638,248          | 92,400           | L=42pcs×20m        |
| Pile Head Treatment             | 500×500                                 | pcs            | 42    | 0                | 0                 | 6.600            | 277              | 16,915             | 277              |                    |
| <b>sub-total</b>                |   |                |       |                  | <b>88,803,000</b> |                  | <b>4,250,677</b> | <b>348,179,323</b> | <b>5,705,987</b> |                    |
| <b>Warehouse Building</b>       |   |                |       |                  |                   |                  |                  |                    |                  |                    |
| Structure                       | 50x20x5m height                         | m <sup>2</sup> | 1,000 | 19,981           | 19,981,000        | 990.000          | 990,000          | 80,390,800         | 1,317,450        | Structure          |
| overhead crane& misc. work      |   | Ls             | 1     |                  | 9,990,500         |                  | 495,000          | 40,195,400         | 658,725          | Structure x 50%    |
| ground improvement              | 1m x 100kg/m3                           | m <sup>3</sup> | 1,000 | 0                | 0                 | 41.000           | 41,000           | 2,501,820          | 41,000           |                    |
| <b>sub-total</b>                |   |                |       |                  | <b>29,971,500</b> |                  | <b>1,526,000</b> | <b>123,088,020</b> | <b>2,017,175</b> |                    |
| <b>GIS Sub-station Building</b> |   |                |       |                  |                   |                  |                  |                    |                  |                    |
| Structure-1                     | 15x11x7.5m height                       | m <sup>2</sup> | 165   | 24,667           | 4,070,055         | 1155.000         | 190,575          | 15,698,942         | 257,275          | Structure          |
| overhead crane& misc. work      | for Structure 1                         | Ls             | 1     |                  | 2,035,028         |                  | 95,288           | 7,849,471          | 128,638          | Structure x 50%    |
| Structure-2                     | (15x20+7x20)x5m height                  | m <sup>2</sup> | 440   | 24,667           | 10,853,480        | 1155.000         | 508,200          | 41,863,844         | 686,068          |                    |
| waterproofing                   |   | m <sup>2</sup> | 605   | 0                | 0                 | 42.900           | 25,955           | 1,583,744          | 25,955           |                    |
| Pile Driving Work               | 500×500, L = 20m<br>Including Materials | m              | 680   | 0                | 0                 | 110.000          | 74,800           | 4,564,296          | 74,800           | L=34pcs×20m        |
| Pile Head Treatment             | 500×500                                 | pcs            | 34    | 0                | 0                 | 6.600            | 224              | 13,693             | 224              |                    |
| <b>sub-total</b>                |   |                |       |                  | <b>16,958,563</b> |                  | <b>895,041</b>   | <b>71,573,989</b>  | <b>1,172,960</b> |                    |

10.5-15

**L1-2-2 Building (Desalination Plant)**

Exchange Rate: 1.00US\$= 119.60JPY      1.000TND= 61.02JPY

| Items                              | Specification                           | Unit                 | Qt'ty     | FC Portion (JPY) |                    | LC Portion (TND) |                   | Total                |                   | Reference     |
|------------------------------------|---|----------------------|-----------|------------------|--------------------|------------------|-------------------|----------------------|-------------------|---------------|
|                                    |   |                      |           | Unit Price       | Amount             | Unit Price       | Amount            | (JPY)                | (equiv. TND)      |               |
| <b>Intake Sub-station Building</b> |   |                      |           |                  |                    |                  |                   |                      |                   |               |
| Structure                          | 36x24x5m height                         | m <sup>2</sup>       | 864       | 24,667           | 21,312,288         | 1155.000         | 997,920           | 82,205,366           | 1,347,187         |               |
| waterproofing                      |   | m <sup>2</sup>       | 864       | 0                | 0                  | 42.900           | 37,066            | 2,261,743            | 37,066            |               |
| Pile Driving Work                  | 500×500, L = 20m<br>Including Materials | m                    | 960       | 0                | 0                  | 110.000          | 105,600           | 6,443,712            | 105,600           | L=48pcs×20m   |
| Pile Head Treatment                | 500×500                                 | pcs                  | 48        | 0                | 0                  | 6.600            | 317               | 19,331               | 317               |               |
| <b>sub-total</b>                   |   |                      |           |                  | <b>21,312,288</b>  |                  | <b>1,140,902</b>  | <b>90,930,152</b>    | <b>1,490,170</b>  |               |
| <b>RO Sub-station Building</b>     |   |                      |           |                  |                    |                  |                   |                      |                   |               |
| Structure                          | 54x24x5m height                         | m <sup>2</sup>       | 1,296     | 24,667           | 31,968,432         | 1155.000         | 1,496,880         | 123,308,050          | 2,020,781         |               |
| waterproofing                      |   | m <sup>2</sup>       | 1,296     | 0                | 0                  | 42.900           | 55,598            | 3,392,614            | 55,598            |               |
| Pile Driving Work                  | 500×500, L = 20m<br>Including Materials | m                    | 1,440     | 0                | 0                  | 110.000          | 158,400           | 9,665,568            | 158,400           | L=72pcs×20m   |
| Pile Head Treatment                | 500×500                                 | pcs                  | 72        | 0                | 0                  | 6.600            | 475               | 28,997               | 475               |               |
| <b>sub-total</b>                   |   |                      |           |                  | <b>31,968,432</b>  |                  | <b>1,711,354</b>  | <b>136,395,229</b>   | <b>2,235,254</b>  |               |
| <b>Gate Keeper House</b>           | <b>5x5x4m height</b>                    | <b>m<sup>2</sup></b> | <b>25</b> | <b>24,667</b>    | <b>616,675</b>     | <b>1155.000</b>  | <b>28,875</b>     | <b>2,378,628</b>     | <b>38,981</b>     |               |
| Total                              |   |                      |           |                  | 774,904,367        |                  | 39,575,728        |                      |                   |               |
| <b>Total Cost (Rounded)</b>        | <b>to L1-2</b>                          |                      |           |                  | <b>774,904,000</b> |                  | <b>39,576,000</b> | <b>3,189,832,000</b> | <b>52,275,000</b> | <b>L1-2-2</b> |
|                                    | FCP:LCP                                 |                      |           |                  | 24%                |                  | 76%               |                      |                   |               |

10.5-16

**L1-2-3 Desalination Plant**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= #####

| Items                       | Specification | Unit  | Qt'ty | FC Portion<br>(JPY)  | LC Portion<br>(TND) | Total                |                   | Reference |
|-----------------------------|---------------|-------|-------|----------------------|---------------------|----------------------|-------------------|-----------|
|                             |               |       |       |                      |                     | (JPY)                | (equiv. TND)      |           |
| <b>Pre-treatment system</b> |               |       |       |                      |                     |                      |                   |           |
| Feed Pump                   |               | units | 5     | 142,500,000          | 122,900             | 149,999,358          | 2,458,200         |           |
| Backwash Pump               |               | units | 3     | 26,600,000           | 22,900              | 27,997,358           | 458,823           |           |
| Air wash Blower             |               | units | 3     | 4,800,000            | 4,100               | 5,050,182            | 82,763            |           |
| Drain Pump                  |               | units | 2     | 142,500,000          | 122,900             | 149,999,358          | 2,458,200         |           |
| Dual media Filter           |               | units | 24    | 931,000,000          | 803,000             | 979,999,060          | 16,060,293        |           |
| Polishing Filter            |               | units | 16    | 617,500,000          | 532,600             | 649,999,252          | 10,652,233        |           |
| Valves                      |               | Ls    | 1     | 216,600,000          | 186,800             | 227,998,536          | 3,736,456         |           |
| Pipes                       |               | Ls    | 1     | 456,000,000          | 393,300             | 479,999,166          | 7,866,260         |           |
| <b>sub-total</b>            |               |       |       | <b>2,537,500,000</b> | <b>2,188,500</b>    | <b>2,671,042,270</b> | <b>43,773,228</b> |           |
| <b>RO system</b>            |               |       |       |                      |                     |                      |                   |           |
| RO Feed Pump                |               | units | 5     | 142,500,000          | 122,900             | 149,999,358          | 2,458,200         |           |
| Cartridge Filter            |               | units | 10    | 78,000,000           | 67,300              | 82,106,646           | 1,345,569         |           |
| Booster Pump                |               | units | 6     | 110,200,000          | 95,100              | 116,003,002          | 1,901,065         |           |
| High Pressure Pump          |               | units | 5     | 456,000,000          | 393,300             | 479,999,166          | 7,866,260         |           |
| Pressure Exchanger Unit     |               | units | 4     | 330,600,000          | 285,200             | 348,002,904          | 5,703,096         |           |

**L1-2-3 Desalination Plant**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= #####

| Items                                    | Specification | Unit  | Qt'ty | FC Portion (JPY)     | LC Portion (TND) | Total                |                   | Reference    |
|--|---------------|-------|-------|----------------------|------------------|----------------------|-------------------|--------------|
|  |               |       |       |                      |                  | (JPY)                | (equiv. TND)      |              |
| RO Unit                                  |               | Ls    | 1     | 1,121,000,000        | 966,900          | 1,180,000,238        | 19,337,926        |              |
| Chemical dosing system (Pre-treatment)   |               | Ls    | 1     | 15,500,000           | 13,400           | 16,317,668           | 267,415           | NaClO, FeCl3 |
| Chemical dosing system (After-treatment) |               | Ls    | 1     | 17,800,000           | 15,400           | 18,739,708           | 307,108           |              |
| Cleaning Pump                            |               | units | 2     | 19,000,000           | 16,400           | 20,000,728           | 327,773           |              |
| Valves                                   |               | Ls    | 1     | 173,000,000          | 149,200          | 182,104,184          | 2,984,336         |              |
| Pipes                                    |               | Ls    | 1     | 332,500,000          | 286,800          | 350,000,536          | 5,735,833         |              |
| Stages                                   |               | Ls    | 1     | 97,000,000           | 83,700           | 102,107,374          | 1,673,343         |              |
| <b>sub-total</b>                         |               |       |       | <b>2,893,100,000</b> | <b>2,495,600</b> | <b>3,045,381,512</b> | <b>49,907,924</b> |              |
|  |               |       |       |                      |                  |                      |                   |              |
| <b>Electrical system</b>                 |               |       |       |                      |                  |                      |                   |              |
| Panels for pre-treatment                 |               | Ls    | 1     | 86,000,000           | 74,200           | 90,527,684           | 1,483,574         |              |
| Panels for RO                            |               | Ls    | 1     | 340,000,000          | 293,300          | 357,897,166          | 5,865,244         |              |
| Panels for others                        |               | Ls    | 1     | 140,000,000          | 120,800          | 147,371,216          | 2,415,130         |              |
| Instruments                              |               | Ls    | 1     | 232,500,000          | 200,500          | 244,734,510          | 4,010,726         |              |
| <b>sub-total</b>                         |               |       |       | <b>798,500,000</b>   | <b>688,800</b>   | <b>840,530,576</b>   | <b>13,774,674</b> |              |
|  |               |       |       |                      |                  |                      |                   |              |

**L1-2-3 Desalination Plant**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= #####

| Items                        | Specification  | Unit | Qt'ty | FC Portion (JPY)     | LC Portion (TND)  | Total                |                    | Reference                   |
|------------------------------|----------------|------|-------|----------------------|-------------------|----------------------|--------------------|-----------------------------|
|                              |                |      |       |                      |                   | (JPY)                | (equiv. TND)       |                             |
| <b>Engineering Work</b>      |                |      |       |                      |                   |                      |                    |                             |
| Mechanical design            |                | Ls   | 1     | 137,000,000          | 0                 | 137,000,000          | 2,245,166          |                             |
| Electrical design            |                | Ls   | 1     | 90,000,000           | 0                 | 90,000,000           | 1,474,926          |                             |
| <b>sub-total</b>             |                |      |       | <b>227,000,000</b>   | <b>0</b>          | <b>227,000,000</b>   | <b>3,720,092</b>   |                             |
| <b>Installation</b>          |                |      |       |                      |                   |                      |                    |                             |
| Mechanical for pre-treatment |                | Ls   | 1     | 80,131,000           | 5,252,800         | 400,656,856          | 6,565,992          | 15% of Pre-treatment system |
| Mechanical for RO            |                | Ls   | 1     | 91,361,000           | 5,989,000         | 456,809,780          | 7,486,230          | 15% of RO system            |
| Electrical installation      |                | Ls   | 1     | 33,621,000           | 2,203,900         | 168,102,978          | 2,754,883          | 20% of RO system            |
| <b>sub-total</b>             |                |      |       | <b>205,113,000</b>   | <b>13,445,700</b> | <b>1,025,569,614</b> | <b>16,807,105</b>  |                             |
| Total                        |                |      |       | 6,661,213,000        | 18,818,600        |                      |                    |                             |
| <b>Total Cost (Rounded)</b>  | <b>to L1-2</b> |      |       | <b>6,661,213,000</b> | <b>18,819,000</b> | <b>7,809,548,000</b> | <b>127,983,000</b> | <b>L1-2-3</b>               |
|                              | FCP:LCP        |      |       | 85%                  | 15%               |                      |                    |                             |

**L1-2-4 Break Tank 15mx50mx5mH (V=3,000m3)**

Exchange Rate: 1.00US\$= 119.60JPY 1.000TND= 61.02JPY

| Items                          | Specification                           | Unit           | Qt'ty | FC Portion (JPY) |          | LC Portion (TND) |                  | Total              |                  | Reference                   |
|--------------------------------|---|----------------|-------|------------------|----------|------------------|------------------|--------------------|------------------|-----------------------------|
|                                |   |                |       | Unit Price       | Amount   | Unit Price       | Amount           | (JPY)              | (equiv. TND)     |                             |
| Pile Driving Work              | 500×500, L = 30m<br>Including Materials | m              | 1,080 | 0                | 0        | 110.000          | 118,800          | 7,249,176          | 118,800          | L=36pcs×30m                 |
| Pile Head Treatment            | 500×500                                 | pcs            | 36    | 0                | 0        | 6.600            | 238              | 14,498             | 238              |                             |
| Excavation                     |   | m <sup>3</sup> | 530   | 0                | 0        | 16.500           | 8,745            | 533,620            | 8,745            |                             |
| Backfilling                    |   | m <sup>3</sup> | 80    | 0                | 0        | 11.000           | 880              | 53,698             | 880              |                             |
| Surplus Soil Transportation    |   | m <sup>3</sup> | 450   | 0                | 0        | 23.100           | 10,395           | 634,303            | 10,395           |                             |
| Gravel                         |   | m <sup>3</sup> | 75    | 0                | 0        | 74.700           | 5,603            | 341,865            | 5,603            |                             |
| Concrete                       |   | m <sup>3</sup> | 75    | 0                | 0        | 440.000          | 33,000           | 2,013,660          | 33,000           | 1                           |
| Reinforced Concrete            |   | m <sup>3</sup> | 889   | 0                | 0        | 935.000          | 831,215          | 50,720,739         | 831,215          | 2                           |
| Formwork                       |   | m <sup>2</sup> | 2,230 | 0                | 0        | 62.700           | 139,821          | 8,531,877          | 139,821          | 3                           |
| Rebar Fabrication and Assembly |   | ton            | 151   | 0                | 0        | 1,320.000        | 199,492          | 12,172,977         | 199,492          | 4 Rebar/Concrete = 170kg/m3 |
| Waterproofing                  |   | m <sup>2</sup> | 1,400 | 0                | 0        | 42.900           | 60,060           | 3,664,861          | 60,060           |                             |
| Scaffolding                    |   | m <sup>2</sup> | 260   | 0                | 0        | 107.800          | 28,028           | 1,710,269          | 28,028           |                             |
| Other Miscellaneous works      |   | Ls             | 1     |                  | 0        |                  | 300,882          | 18,359,814         | 300,882          | sum of (1~4) x 25%          |
| Total                          |   |                |       |                  | 0        |                  | 1,737,158        |                    |                  |                             |
| <b>Total Cost (Rounded)</b>    | <b>to L1-2</b>                          |                |       |                  | <b>0</b> |                  | <b>1,737,000</b> | <b>105,992,000</b> | <b>1,737,000</b> | <b>L1-2-4</b>               |
|                                | FCP:LCP                                 |                |       |                  | 0%       |                  | 100%             |                    |                  |                             |

10.5-20

**L1-2-5 Drain Tank 15mx38mx5mH**

Exchange Rate: 1.00US\$= 119.60JPY 1.000TND= 61.02JPY

10.5-21

| Items                          | Specification                           | Unit           | Qt'ty | FC Portion (JPY) |          | LC Portion (TND) |                  | Total             |                  | Reference                   |
|--------------------------------|---|----------------|-------|------------------|----------|------------------|------------------|-------------------|------------------|-----------------------------|
|                                |   |                |       | Unit Price       | Amount   | Unit Price       | Amount           | (JPY)             | (equiv. TND)     |                             |
| Pile Driving Work              | 500×500, L = 30m<br>Including Materials | m              | 780   | 0                | 0        | 110.000          | 85,800           | 5,235,516         | 85,800           | L=26pcs×30m                 |
| Pile Head Treatment            | 500×500                                 | pcs            | 26    | 0                | 0        | 6.600            | 172              | 10,471            | 172              |                             |
| Excavation                     |   | m <sup>3</sup> | 408   | 0                | 0        | 16.500           | 6,732            | 410,787           | 6,732            |                             |
| Backfilling                    |   | m <sup>3</sup> | 66    | 0                | 0        | 11.000           | 726              | 44,301            | 726              |                             |
| Surplus Soil Transportation    |   | m <sup>3</sup> | 342   | 0                | 0        | 23.100           | 7,900            | 482,070           | 7,900            |                             |
| Gravel                         |   | m <sup>3</sup> | 57    | 0                | 0        | 74.700           | 4,258            | 259,817           | 4,258            |                             |
| Concrete                       |   | m <sup>3</sup> | 57    | 0                | 0        | 440.000          | 25,080           | 1,530,382         | 25,080           | 1                           |
| Reinforced Concrete            |   | m <sup>3</sup> | 668   | 0                | 0        | 935.000          | 624,580          | 38,111,872        | 624,580          | 2                           |
| Formwork                       |   | m <sup>2</sup> | 1,790 | 0                | 0        | 62.700           | 112,233          | 6,848,458         | 112,233          | 3                           |
| Rebar Fabrication and Assembly |   | ton            | 114   | 0                | 0        | 1320.000         | 149,899          | 9,146,849         | 149,899          | 4 Rebar/Concrete = 170kg/m3 |
| Waterproofing                  |   | m <sup>2</sup> | 1,100 | 0                | 0        | 42.900           | 47,190           | 2,879,534         | 47,190           |                             |
| Scaffolding                    |   | m <sup>2</sup> | 220   | 0                | 0        | 107.800          | 23,716           | 1,447,150         | 23,716           |                             |
| Other Miscellaneous Works      |   | Ls             | 1     |                  | 0        |                  | 227,948          | 13,909,390        | 227,948          | sum of (1~4) x 25%          |
|                                |   |                |       |                  |          |                  |                  |                   |                  |                             |
| Total                          |   |                |       |                  | 0        |                  | 1,316,234        |                   |                  |                             |
| <b>Total Cost (Rounded)</b>    | <b>to L1-2</b>                          |                |       |                  | <b>0</b> |                  | <b>1,316,000</b> | <b>80,302,000</b> | <b>1,316,000</b> | <b>L1-2-5</b>               |
|                                | FCP:LCP                                 |                |       |                  | 0%       |                  | 100%             |                   |                  |                             |



**L1-2-6 Brine Tank 12mx40mx5mH**

Exchange Rate: 1.00US\$= 119.60JPY 1.000TND= 61.02JPY

| Items                          | Specification                           | Unit           | Qt'ty | FC Portion (JPY) |          | LC Portion (TND) |                  | Total             |                  | Reference                   |
|--------------------------------|---|----------------|-------|------------------|----------|------------------|------------------|-------------------|------------------|-----------------------------|
|                                |   |                |       | Unit Price       | Amount   | Unit Price       | Amount           | (JPY)             | (equiv. TND)     |                             |
| Pile Driving Work              | 500×500, L = 30m<br>Including Materials | m              | 540   | 0                | 0        | 110.000          | 59,400           | 3,624,588         | 59,400           | L=18pcs×30m                 |
| Pile Head Treatment            | 500×500                                 | pcs            | 18    | 0                | 0        | 6.600            | 119              | 7,249             | 119              |                             |
| Excavation                     |   | m <sup>3</sup> | 353   | 0                | 0        | 16.500           | 5,825            | 355,411           | 5,825            |                             |
| Backfilling                    |   | m <sup>3</sup> | 65    | 0                | 0        | 11.000           | 715              | 43,629            | 715              |                             |
| Surplus Soil Transportation    |   | m <sup>3</sup> | 288   | 0                | 0        | 23.100           | 6,653            | 405,954           | 6,653            |                             |
| Gravel                         |   | m <sup>3</sup> | 48    | 0                | 0        | 74.700           | 3,586            | 218,793           | 3,586            |                             |
| Concrete                       |   | m <sup>3</sup> | 48    | 0                | 0        | 440.000          | 21,120           | 1,288,742         | 21,120           | 1                           |
| Reinforced Concrete            |   | m <sup>3</sup> | 576   | 0                | 0        | 935.000          | 538,560          | 32,862,931        | 538,560          | 2                           |
| Formwork                       |   | m <sup>2</sup> | 1,640 | 0                | 0        | 62.700           | 102,828          | 6,274,565         | 102,828          | 3                           |
| Rebar Fabrication and Assembly |   | ton            | 98    | 0                | 0        | 1,320.000        | 129,254          | 7,887,103         | 129,254          | 4 Rebar/Concrete = 170kg/m3 |
| Waterproofing                  |   | m <sup>2</sup> | 1,000 | 0                | 0        | 42.900           | 42,900           | 2,617,758         | 42,900           |                             |
| Scaffolding                    |   | m <sup>2</sup> | 210   | 0                | 0        | 107.800          | 22,638           | 1,381,371         | 22,638           |                             |
| Other Miscellaneous Works      |   | Ls             | 1     |                  | 0        |                  | 197,941          | 12,078,335        | 197,941          | sum of (1~4) x 25%          |
|                                |   |                |       |                  |          |                  |                  |                   |                  |                             |
| Total                          |   |                |       |                  | 0        |                  | 1,131,538        |                   |                  |                             |
| <b>Total Cost (Rounded)</b>    | <b>to L1-2</b>                          |                |       |                  | <b>0</b> |                  | <b>1,132,000</b> | <b>69,075,000</b> | <b>1,132,000</b> | <b>L1-2-6</b>               |
|                                | FCP:LCP                                 |                |       |                  | 0%       |                  | 100%             |                   |                  |                             |

10.5-22

**L1-2-7 Product Water Tank (V=5,000m<sup>3</sup> x 5)**

Exchange Rate: 1.00US\$= 119.60JPY      1.000TND= 61.02JPY

| Items                          | Specification                         | Unit           | Qt'ty | FC Portion (JPY) |          | LC Portion (TND) |                   | Total              |                   | Reference                               |
|--------------------------------|---------------------------------------|----------------|-------|------------------|----------|------------------|-------------------|--------------------|-------------------|---|
|                                |                                       |                |       | Unit Price       | Amoun    | Unit Price       | Amount            | (JPY)              | (equiv.)          |   |
| Pile Driving Work              | φ 500, L = 30m<br>Including Materials | m              | 2,160 | 0                | 0        | 110.000          | 237,600           | 14,498,352         | 237,600           | L=72pcs×30m                             |
| Pile Head Treatment            | φ 500                                 | pcs            | 72    | 0                | 0        | 6.600            | 475               | 28,997             | 475               |   |
| Excavation                     |                                       | m <sup>3</sup> | 2,036 | 0                | 0        | 16.500           | 33,594            | 2,049,906          | 33,594            |   |
| Backfilling                    |                                       | m <sup>3</sup> | 428   | 0                | 0        | 11.000           | 4,708             | 287,282            | 4,708             |   |
| Surplus Soil Transportation    |                                       | m <sup>3</sup> | 1,608 | 0                | 0        | 23.100           | 37,145            | 2,266,576          | 37,145            |   |
| Gravel                         |                                       | m <sup>3</sup> | 241   | 0                | 0        | 74.700           | 18,003            | 1,098,525          | 18,003            |   |
| Concrete                       |                                       | m <sup>3</sup> | 161   | 0                | 0        | 440.000          | 70,840            | 4,322,657          | 70,840            | 1                                       |
| Reinforced Concrete            |                                       | m <sup>3</sup> | 930   | 0                | 0        | 935.000          | 869,550           | 53,059,941         | 869,550           | 2                                       |
| Formwork                       |                                       | m <sup>2</sup> | 3,500 | 0                | 0        | 62.700           | 219,450           | 13,390,839         | 219,450           | 3                                       |
| Rebar Fabrication and Assembly |                                       | ton            | 158   | 0                | 0        | 1,320.000        | 208,692           | 12,734,386         | 208,692           | 4 Rebar/Concrete = 170kg/m <sup>3</sup> |
| Waterproofing                  |                                       | m <sup>2</sup> | 1,500 | 0                | 0        | 42.900           | 64,350            | 3,926,637          | 64,350            |   |
| Scaffolding                    |                                       | m <sup>2</sup> | 200   | 0                | 0        | 107.800          | 21,560            | 1,315,591          | 21,560            |   |
| Other Miscellaneous Works      |                                       | Ls             | 1     |                  | 0        |                  | 342,133           | 20,876,956         | 342,133           | sum of (1~4) x      25%                 |
| Total Cost/1unit               |                                       |                |       |                  | 0        |                  | 2,128,100         |                    |                   |   |
| Total Cost/5units              |                                       |                |       |                  | 0        |                  | 10,640,499        |                    |                   |   |
| <b>Total Cost (Rounded)</b>    | <b>to L1-2</b>                        |                |       |                  | <b>0</b> |                  | <b>10,640,000</b> | <b>649,253,000</b> | <b>10,640,000</b> | <b>L1-2-7 for 5 units</b>               |
|                                | FCP:LCP                               |                |       |                  | 0%       |                  | 100%              |                    |                   |   |

10.5-23

**L1-2-8 In-Yard Pipelines**

Exchange Rate: 1.00US\$= 119.60JPY 1.000TND= 61.02JPY

| Diameter(mm)                  | Specification | Unit | Qt'ty | FC Portion (JPY) |          | LC Portion (TND) |                  | Total              |                  | Reference     |
|-------------------------------|---------------|------|-------|------------------|----------|------------------|------------------|--------------------|------------------|---------------|
|                               |               |      |       | Unit Price       | Amount   | Unit Price       | Amount           | (JPY)              | (equiv. TND)     |               |
| 1200                          | HDPE          | m    | 250   | 0                | 0        | 1,481            | 370,250          | 22,592,655         | 370,250          | Local Market  |
| 1400                          | HDPE          | m    | 420   | 0                | 0        | 1,906            | 800,688          | 48,857,982         | 800,688          | Local Market  |
| 1800                          | HDPE          | m    | 320   | 0                | 0        | 3,045            | 974,400          | 59,457,888         | 974,400          | Local Market  |
| including materials and works |               |      |       |                  |          |                  |                  |                    |                  |               |
|                               |               |      |       |                  |          |                  |                  |                    |                  |               |
|                               |               |      |       |                  |          |                  |                  |                    |                  |               |
|                               |               |      |       |                  |          |                  |                  |                    |                  |               |
|                               |               |      |       |                  |          |                  |                  |                    |                  |               |
|                               |               |      |       |                  |          |                  |                  |                    |                  |               |
|                               |               |      |       |                  |          |                  |                  |                    |                  |               |
|                               |               |      |       |                  |          |                  |                  |                    |                  |               |
|                               |               |      |       |                  |          |                  |                  |                    |                  |               |
|                               |               |      |       |                  |          |                  |                  |                    |                  |               |
|                               |               |      |       |                  |          |                  |                  |                    |                  |               |
|                               |               |      |       |                  |          |                  |                  |                    |                  |               |
| Total                         |               |      |       |                  | 0        |                  | 2,145,338        |                    |                  |               |
| <b>Total Cost (Rounded)</b>   | to L1-2       |      |       |                  | <b>0</b> |                  | <b>2,145,000</b> | <b>130,888,000</b> | <b>2,145,000</b> | <b>L1-2-8</b> |
|                               | FCP:LCP       |      |       |                  | 0%       |                  | 100%             |                    |                  |               |

**L1-2-9 Electrical Facility for Desalination Plant**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items  | Specification    | Unit      | Qt'y     | FC Portion (JPY) |                    | LC Portion (TND) |                  | Total              |                   | Reference  |
|--|------------------|-----------|----------|------------------|--------------------|------------------|------------------|--------------------|-------------------|--|
|  |                  |           |          | Unit Price       | Amount             | Unit Price       | Amount           | (JPY)              | (equiv. TND)      |  |
| <b>150kV GIS Sub-station and Power Supply Facilities</b>         |                  |           |          |                  |                    |                  |                  |                    |                   |  |
|  |                  |           |          |                  |                    |                  |                  |                    |                   | GIS:<br>Gas Insulated Switchgear                   |
| 150kV Gas Insulated Switchgear                                   |                  | lot       | 1        | 136,000,000      | 136,000,000        | 393,000          | 393,000          | 160,000,000        | 2,622,091         | 1  |
| Power Transformer  | oil type 40MVAx2 | lot       | 1        | 255,000,000      | 255,000,000        | 737,000          | 737,000          | 300,000,000        | 4,916,421         | 2  |
| 30kV Switchgear  |                  | lot       | 1        | 42,500,000       | 42,500,000         | 123,000          | 123,000          | 50,000,000         | 819,403           | 3  |
| Power Cable  |                  | lot       | 1        | 127,500,000      | 127,500,000        | 369,000          | 369,000          | 150,000,000        | 2,458,210         | 4  |
| Earthing System  |                  | lot       | 1        | 8,500,000        | 8,500,000          | 25,000           | 25,000           | 10,000,000         | 163,881           | 5  |
| Control & Protection   |                  | lot       | 1        | 170,000,000      | 170,000,000        | 492,000          | 492,000          | 200,000,000        | 3,277,614         | 6  |
| Other Miscellaneous Works  |                  | lot       | 1        |                  | 73,950,000         |                  | 214,000          | 87,008,280         | 1,425,898         | 7.<br>Sum of (1~6) x 10%                           |
| <b>150kV Sub-station total</b>                                   | <b>to Total</b>  |           |          |                  | <b>813,450,000</b> |                  | <b>2,353,000</b> | <b>957,030,000</b> | <b>15,683,874</b> | <b>a. sum of (1~7)</b>                             |
|  | FCP:LCP          |           |          |                  | 85%                |                  | 15%              |                    |                   |  |
| <b>Intake Facilities Sub-station and Power Supply Facilities</b> |                  |           |          |                  |                    |                  |                  |                    |                   |  |
| <b>30kV Switchgear</b>   |                  | <b>Ls</b> | <b>1</b> |                  | <b>36,720,000</b>  |                  | <b>105,895</b>   | <b>43,200,000</b>  | <b>707,965</b>    | <b>8</b>   |
| 30kV DS, LA Panel  |                  | set       | 1        | 4,250,000        | 4,250,000          | 12,000           | 12,000           | 5,000,000          | 81,940            | DS: Disconnecting Switch<br>LA: Lightning Arrester |
| 30kV VT Panel  |                  | set       | 1        | 4,250,000        | 4,250,000          | 12,000           | 12,000           | 5,000,000          | 81,940            | VT:<br>Voltage Transformer                         |
| 30kV VCB Panel   |                  | set       | 1        | 7,225,000        | 7,225,000          | 20,895           | 20,895           | 8,500,000          | 139,299           | VCB:<br>Vacuum Circuit Breaker                     |
| 30kV/6kV Transformer   | oil type 4MVA    | set       | 1        | 20,995,000       | 20,995,000         | 61,000           | 61,000           | 24,700,000         | 404,785           |  |
| <b>6kV &amp; LV Switchgear</b>                                   |                  | <b>Ls</b> | <b>1</b> |                  | <b>128,945,000</b> |                  | <b>372,327</b>   | <b>151,700,000</b> | <b>2,486,070</b>  | <b>9 LV: Low Voltage</b>                           |
| 6kV VCB Panel  |                  | set       | 8        | 4,845,000        | 38,760,000         | 14,000           | 112,000          | 45,600,000         | 747,296           |  |
| 6kV VT Panel   |                  | set       | 1        | 3,825,000        | 3,825,000          | 11,000           | 11,000           | 4,500,000          | 73,746            |  |
| Intake Pump Panel  | 6kV VFD 240kW    | set       | 5        | 10,200,000       | 51,000,000         | 29,400           | 147,000          | 60,000,000         | 983,284           | VFD:<br>Variable Frequency Drive                   |
| LV Transformer   | dry type 500kVA  | set       | 1        | 7,225,000        | 7,225,000          | 21,000           | 21,000           | 8,500,000          | 139,299           |  |
| LV Main Switchgear   | 5 units          | set       | 1        | 11,050,000       | 11,050,000         | 31,957           | 31,957           | 13,000,000         | 213,045           |  |

10.5-25

**L1-2-9 Electrical Facility for Desalination Plant**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items  | Specification                           | Unit      | Qt'ly    | FC Portion (JPY) |                    | LC Portion (TND) |                | Total              |                  | Reference                               |
|--|---|-----------|----------|------------------|--------------------|------------------|----------------|--------------------|------------------|---|
|  |   |           |          | Unit Price       | Amount             | Unit Price       | Amount         | (JPY)              | (equiv. TND)     |   |
| MCC for Intake-1   | 5 units                                 | set       | 1        | 14,535,000       | 14,535,000         | 42,000           | 42,000         | 17,100,000         | 280,236          | MCC:<br>Motor Control Centre            |
| Local Panel  |   | set       | 10       | 255,000          | 2,550,000          | 737              | 7,370          | 3,000,000          | 49,164           |   |
| <b>Instrumentation &amp; Monitoring</b>                      |   | <b>Ls</b> | <b>1</b> |                  | <b>62,985,000</b>  |                  | <b>182,636</b> | <b>74,100,000</b>  | <b>1,214,356</b> | <b>10</b>                               |
| Intake Flow -1   | electro-magnetic 2000mm                 | set       | 2        | 11,305,000       | 22,610,000         | 32,694           | 65,388         | 26,600,000         | 435,923          |   |
| Brine Discharge Flow -1                                      | electro-magnetic 1800mm                 | set       | 1        | 10,115,000       | 10,115,000         | 29,253           | 29,253         | 11,900,000         | 195,018          |   |
| Water Level  | Ultrasonic                              | set       | 2        | 680,000          | 1,360,000          | 1,967            | 3,934          | 1,600,000          | 26,221           |   |
| Water Quality  | Turbidity, pH,<br>Electric Conductivity | set       | 3        | 1,275,000        | 3,825,000          | 3,687            | 11,061         | 4,500,000          | 73,746           |   |
| Instrumentation Panel  |   | set       | 1        | 2,550,000        | 2,550,000          | 7,000            | 7,000          | 3,000,000          | 49,164           |   |
| PLC Panel  |   | set       | 2        | 6,375,000        | 12,750,000         | 18,500           | 37,000         | 15,000,000         | 245,821          | PLC:<br>Programmable Logic Controller   |
| Remote SCADA   |   | set       | 1        | 8,500,000        | 8,500,000          | 25,000           | 25,000         | 10,000,000         | 163,881          |   |
| UPS  | 10kVA                                   | set       | 1        | 1,275,000        | 1,275,000          | 4,000            | 4,000          | 1,500,000          | 24,582           | UPS:<br>Uninterruptive Power Supply     |
| <b>Other Miscellaneous Works</b>                             |   | <b>Ls</b> | <b>1</b> |                  | <b>22,865,000</b>  |                  | <b>66,000</b>  | <b>26,892,320</b>  | <b>440,713</b>   | <b>11</b><br>Sum of (8-10) x <b>10%</b> |
| <b>Intake Sub-station total</b>                              | <b>to Total</b>                         |           |          |                  | <b>251,515,000</b> |                  | <b>726,858</b> | <b>295,868,000</b> | <b>4,848,705</b> | <b>b. sum of (8-11)</b>                 |
|  | FCP:LCP                                 |           |          |                  | 85%                |                  | 15%            |                    |                  |   |
| <b>RO Facilities Sub-station and Power Supply Facilities</b> |   |           |          |                  |                    |                  |                |                    |                  |   |
| <b>30kV Switchgear</b>                                       |   | <b>Ls</b> | <b>1</b> |                  | <b>124,950,000</b> |                  | <b>361,790</b> | <b>147,000,000</b> | <b>2,409,046</b> | <b>12</b>                               |
| 30kV DS, LA Panel  |   | set       | 2        | 4,250,000        | 8,500,000          | 12,500           | 25,000         | 10,000,000         | 163,881          |   |
| 30kV VT Panel  |   | set       | 2        | 4,250,000        | 8,500,000          | 12,500           | 25,000         | 10,000,000         | 163,881          |   |
| 30kV VCB Panel   |   | set       | 2        | 7,225,000        | 14,450,000         | 20,895           | 41,790         | 17,000,000         | 278,597          |   |
| 30kV/6kV Transformer   | oil type 15MVA                          | set       | 2        | 46,750,000       | 93,500,000         | 135,000          | 270,000        | 110,000,000        | 1,802,688        |   |
| <b>6kV &amp; LV Switchgear</b>                               |   | <b>Ls</b> | <b>1</b> |                  | <b>80,495,000</b>  |                  | <b>232,957</b> | <b>94,700,000</b>  | <b>1,551,950</b> | <b>13</b>                               |
| 6kV VCB Panel  |   | set       | 11       | 4,845,000        | 53,295,000         | 14,000           | 154,000        | 62,700,000         | 1,027,532        |   |

10.5-26

**L1-2-9 Electrical Facility for Desalination Plant**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                                  | Specification   | Unit      | Qt'y     | FC Portion (JPY) |                      | LC Portion (TND) |                  | Total                |                   | Reference                          |
|--|-----------------|-----------|----------|------------------|----------------------|------------------|------------------|----------------------|-------------------|------------------------------------|
|  |                 |           |          | Unit Price       | Amount               | Unit Price       | Amount           | (JPY)                | (equiv. TND)      |                                    |
| 6kV VT Panel                           |                 | set       | 2        | 3,825,000        | 7,650,000            | 11,000           | 22,000           | 9,000,000            | 147,493           |                                    |
| LV Transformer                         | dry type 250kVA | set       | 2        | 4,250,000        | 8,500,000            | 12,500           | 25,000           | 10,000,000           | 163,881           |                                    |
| LV Main Switchgear                     | 5 units         | set       | 1        | 11,050,000       | 11,050,000           | 31,957           | 31,957           | 13,000,000           | 213,045           |                                    |
| <b>Other Miscellaneous Works</b>       |                 | <b>Ls</b> | <b>1</b> |                  | <b>20,545,000</b>    |                  | <b>59,000</b>    | <b>24,145,180</b>    | <b>395,693</b>    | <sup>14</sup> Sum of (12,13) x 10% |
| <b>RO Facilities Sub-station total</b> | <b>to Total</b> | <b>Ls</b> | <b>1</b> |                  | <b>225,990,000</b>   |                  | <b>653,747</b>   | <b>265,881,642</b>   | <b>4,357,287</b>  | <b>c. sum of (12-14)</b>           |
|  | FCP:LCP         |           |          |                  | 85%                  |                  | 15%              |                      |                   |                                    |
| <b>SCADA System</b>                    |                 |           |          |                  |                      |                  |                  |                      |                   |                                    |
| Central SCADA                          |                 | lot       | 1        | 29,750,000       | 29,750,000           | 86,000           | 86,000           | 35,000,000           | 573,582           | 15                                 |
| PLC for RO                             |                 | lot       | 1        | 12,750,000       | 12,750,000           | 37,000           | 37,000           | 15,000,000           | 245,821           | 16                                 |
| Remote SCADA for RO                    |                 | lot       | 1        | 8,500,000        | 8,500,000            | 25,000           | 25,000           | 10,000,000           | 163,881           | 17                                 |
| UPS                                    | 20kVA           | set       | 1        | 1,700,000        | 1,700,000            | 5,000            | 5,000            | 2,000,000            | 32,776            | 18                                 |
| Other Miscellaneous Works              |                 | Ls        | 1        |                  | 5,270,000            |                  | 15,000           | 6,185,300            | 101,365           | <sup>19</sup> Sum of (15-18) x 10% |
| <b>SCADA System total</b>              | <b>to Total</b> | <b>Ls</b> | <b>1</b> |                  | <b>57,970,000</b>    |                  | <b>168,000</b>   | <b>68,221,360</b>    | <b>1,118,016</b>  | <b>d. sum of (15-19)</b>           |
|  | FCP:LCP         |           |          |                  | 85%                  |                  | 15%              |                      |                   |                                    |
| Total                                  |                 |           |          |                  | 1,348,925,000        |                  | 3,901,605        |                      |                   | sum of (a,b,c,d)                   |
| <b>Total Cost (Rounded)</b>            | <b>to L1-2</b>  |           |          |                  | <b>1,348,925,000</b> |                  | <b>3,902,000</b> | <b>1,587,025,000</b> | <b>26,008,000</b> | <b>L1-2-9</b>                      |
|  | FCP:LCP         |           |          |                  | 85%                  |                  | 15%              |                      |                   |                                    |

10.5-27

**L1-3 Transmission Pump Facility**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                       | Specification | Unit | Qt'ty | FC Portion (JPY) |                    | LC Portion (TND) |                  | Total                |                   | Reference   |
|-----------------------------|---------------|------|-------|------------------|--------------------|------------------|------------------|----------------------|-------------------|-------------|
|                             |               |      |       | Unit Price       | Amount             | Unit Price       | Amount           | (JPY)                | (equiv. TND)      |             |
| Buildings                   |               | Ls   | 1     |                  | 64,234,000         |                  | 3,378,000        | 270,360,000          | 4,431,000         | L1-3-1      |
| Mechanical Facilities       |               | Ls   | 1     |                  | 269,897,000        |                  | 780,000          | 317,493,000          | 5,203,000         | L1-3-2      |
| Electrical Facilities       |               | Ls   | 1     |                  | 404,809,000        |                  | 1,169,000        | 476,141,000          | 7,803,000         | L1-3-3      |
|                             |               |      |       |                  |                    |                  |                  |                      |                   |             |
|                             |               |      |       |                  |                    |                  |                  |                      |                   |             |
|                             |               |      |       |                  |                    |                  |                  |                      |                   |             |
|                             |               |      |       |                  |                    |                  |                  |                      |                   |             |
|                             |               |      |       |                  |                    |                  |                  |                      |                   |             |
|                             |               |      |       |                  |                    |                  |                  |                      |                   |             |
|                             |               |      |       |                  |                    |                  |                  |                      |                   |             |
|                             |               |      |       |                  |                    |                  |                  |                      |                   |             |
|                             |               |      |       |                  |                    |                  |                  |                      |                   |             |
| Total                       |               |      |       |                  | 738,940,000        |                  | 5,327,000        |                      |                   |             |
| <b>Total Cost (Rounded)</b> | <b>to L1</b>  |      |       |                  | <b>738,940,000</b> |                  | <b>5,327,000</b> | <b>1,063,994,000</b> | <b>17,437,000</b> | <b>L1-3</b> |
|                             | FCP:LCP       |      |       |                  | 69%                |                  | 31%              |                      |                   |             |

**L1-3-1 Building (Transmission Pump House)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                                    | Specification                           | Unit           | Qt'ty | FC Portion (JPY) |                   | LC Portion (TND) |                  | Total              |                  | Reference       |
|--|---|----------------|-------|------------------|-------------------|------------------|------------------|--------------------|------------------|-----------------|
|  |   |                |       | Unit Price       | Amount            | Unit Price       | Amount           | (JPY)              | (equiv. TND)     |                 |
| <b>Transmission Pump House</b>           |   |                |       |                  |                   |                  |                  |                    |                  |                 |
| Structure                                | 51.8x19.2x5.8m height                   | m <sup>2</sup> | 995   | 24,667           | 24,543,998        | 1155.000         | 1,149,225        | 94,669,708         | 1,551,454        | Structure       |
| Miscellaneous work                       |   | Ls             | 1     |                  | 4,908,800         |                  | 229,845          | 18,933,942         | 310,291          | Structure x 20% |
| waterproofing                            |   | m <sup>2</sup> | 995   | 0                | 0                 | 42.900           | 42,686           | 2,604,669          | 42,686           |                 |
| Pile Driving Work                        | 500x500, L = 20m<br>Including Materials | m              | 1,120 | 0                | 0                 | 110.000          | 123,200          | 7,517,664          | 123,200          | L=56pcsx20m     |
| Pile Head Treatment                      | 500x500                                 | pcs            | 56    | 0                | 0                 | 6.600            | 370              | 22,553             | 370              |                 |
| <b>sub-total</b>                         |   |                |       | <b>0</b>         | <b>29,452,798</b> |                  | <b>1,545,325</b> | <b>123,748,536</b> | <b>2,028,001</b> |                 |
| <b>Transmission Sub-station Building</b> |   |                |       |                  |                   |                  |                  |                    |                  |                 |
| Structure                                | 36x24x5m height                         | m <sup>2</sup> | 864   | 24,667           | 21,312,577        | 1155.000         | 997,920          | 82,205,656         | 1,347,192        |                 |
| waterproofing                            |   | m <sup>2</sup> | 864   | 0                | 0                 | 42.900           | 37,066           | 2,261,743          | 37,066           |                 |
| Pile Driving Work                        | 500x500, L = 20m<br>Including Materials | m              | 960   | 0                | 0                 | 110.000          | 105,600          | 6,443,712          | 105,600          | L=48pcsx20m     |
| Pile Head Treatment                      | 500x500                                 | pcs            | 48    | 0                | 0                 | 6.600            | 317              | 19,331             | 317              |                 |
| <b>sub-total</b>                         |   |                |       |                  | <b>21,312,577</b> |                  | <b>1,140,586</b> | <b>90,911,111</b>  | <b>1,489,858</b> |                 |
| <b>Generator Building</b>                |   |                |       |                  |                   |                  |                  |                    |                  |                 |
| Structure                                |   | m <sup>2</sup> | 364   | 24,667           | 8,978,910         | 1155.000         | 420,420          | 34,632,938         | 567,567          | Structure       |
| over head crane& misc.                   |   | Ls             | 1     |                  | 4,489,455         |                  | 210,210          | 17,316,469         | 283,784          | Structure x 50% |
| waterproofing                            |   | m <sup>2</sup> | 364   | 0                | 0                 | 42.900           | 15,616           | 952,864            | 15,616           |                 |
| Pile Driving Work                        | 500x500, L = 20m<br>Including Materials | m              | 420   | 0                | 0                 | 110.000          | 46,200           | 2,819,124          | 46,200           | L=21pcsx20m     |
| Pile Head Treatment                      | 500x500                                 | pcs            | 21    | 0                | 0                 | 6.600            | 139              | 8,457              | 139              |                 |
| <b>sub-total</b>                         |   |                |       |                  | <b>13,468,365</b> |                  | <b>692,584</b>   | <b>55,729,853</b>  | <b>913,306</b>   |                 |
| Total                                    |   |                |       |                  | 64,233,740        |                  | 3,378,495        |                    |                  |                 |
| <b>Total Cost (Rounded)</b>              | <b>to L1-3</b>                          |                |       |                  | <b>64,234,000</b> |                  | <b>3,378,000</b> | <b>270,360,000</b> | <b>4,431,000</b> | <b>L1-3-1</b>   |
|  | FCP:LCP                                 |                |       |                  | 24%               |                  | 76%              |                    |                  |                 |



**L1-3-2 Mechanical Facility for Transmission Pump (100,000 m3/d)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= #####

| Items                            | Specification            | Unit | Qt'ly | FC Portion (JPY) |                    | LC Portion (TND) |                | Total              |                  | Reference       |
|----------------------------------|--------------------------|------|-------|------------------|--------------------|------------------|----------------|--------------------|------------------|-----------------|
|                                  |                          |      |       | Unit Price       | Amount             | Unit Price       | Amount         | (JPY)              | (equiv. TND)     |                 |
| <b>Transmission pump station</b> | <b>Plant Site - PK11</b> |      |       |                  |                    |                  |                |                    |                  |                 |
| Transmission Pump                | 34.8m3/min x 95m         | set  | 3     | 57,962,000       | 173,886,000        | 167,600          | 502,800        | 204,566,856        | 3,352,456        |                 |
| Suction Valve                    | Dia. 500mm               | set  | 3     | 1,845,000        | 5,535,000          | 5,300            | 15,900         | 6,505,218          | 106,608          |                 |
| Check Valve                      | Dia. 500mm               | set  | 3     | 2,769,000        | 8,307,000          | 8,000            | 24,000         | 9,771,480          | 160,136          |                 |
| Discharge Valve                  | Dia. 500mm               | set  | 3     | 3,668,000        | 11,004,000         | 10,600           | 31,800         | 12,944,436         | 212,134          | Motorized       |
| Maintenance Valve                | Dia. 500mm               | set  | 3     | 1,845,000        | 5,535,000          | 5,300            | 15,900         | 6,505,218          | 106,608          |                 |
| Maintenance Valve                | Dia. 1400 mm             | set  | 2     | 5,477,000        | 10,954,000         | 15,800           | 31,600         | 12,882,232         | 211,115          | Butterfly Valve |
| Pump Lifting Equipment           | suspension crane: 5 ton  | set  | 1     | 19,472,000       | 19,472,000         | 56,300           | 56,300         | 22,907,426         | 375,408          |                 |
| Pipes                            |                          | lot  | 1     | 35,204,000       | 35,204,000         | 101,800          | 101,800        | 41,415,836         | 678,726          |                 |
|                                  |                          |      |       |                  |                    |                  |                |                    |                  |                 |
|                                  |                          |      |       |                  |                    |                  |                |                    |                  |                 |
|                                  |                          |      |       |                  |                    |                  |                |                    |                  |                 |
|                                  |                          |      |       |                  |                    |                  |                |                    |                  |                 |
| Total                            |                          |      |       |                  | 269,897,000        |                  | 780,100        |                    |                  |                 |
| <b>Total Cost (Rounded)</b>      | <b>to L1-3</b>           |      |       |                  | <b>269,897,000</b> |                  | <b>780,000</b> | <b>317,493,000</b> | <b>5,203,000</b> | <b>L1-3-2</b>   |
|                                  | FCP:LCP                  |      |       |                  | 85%                |                  | 15%            |                    |                  |                 |

### L1-3-3 Electrical Facility for Transmission Pump

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items   | Specification                   | Unit      | Qt'ly    | FC Portion (JPY) |                    | LC Portion (TND) |                | Total              |                  | Reference  |
|---|---------------------------------|-----------|----------|------------------|--------------------|------------------|----------------|--------------------|------------------|--|
|   |                                 |           |          | Unit Price       | Amount             | Unit Price       | Amount         | (JPY)              | (equiv. TND)     |  |
| <b>Transmission Sub-station and Power Supply Facilities</b> |                                 |           |          |                  |                    |                  |                |                    |                  |  |
| <b>30kV Switchgear</b>                                      |                                 | <b>Ls</b> | <b>1</b> |                  | <b>49,725,000</b>  |                  | <b>142,895</b> | <b>58,500,000</b>  | <b>958,702</b>   | <b>1</b>   |
| 30kV DS, LA Panel   |                                 | set       | 1        | 4,250,000        | 4,250,000          | 12,000           | 12,000         | 5,000,000          | 81,940           | DS: Disconnecting Switch<br>LA: Lightning Arrester |
| 30kV VT Panel   |                                 | set       | 1        | 4,250,000        | 4,250,000          | 12,000           | 12,000         | 5,000,000          | 81,940           | VT:<br>Voltage Transformer                         |
| 30kV VCB Panel  |                                 | set       | 1        | 7,225,000        | 7,225,000          | 20,895           | 20,895         | 8,500,000          | 139,299          | VCB:<br>Vacuum Circuit Breaker                     |
| 30kV/6kV Transformer  | oil type 10MVA                  | set       | 1        | 34,000,000       | 34,000,000         | 98,000           | 98,000         | 40,000,000         | 655,523          |  |
| <b>6kV &amp; LV Switchgear</b>                              |                                 | <b>Ls</b> | <b>1</b> |                  | <b>142,587,500</b> |                  | <b>412,327</b> | <b>167,750,000</b> | <b>2,150,115</b> | <b>2</b> LV: Low Voltage                           |
| 6kV VCB Panel   |                                 | set       | 6        | 4,845,000        | 29,070,000         | 14,000           | 84,000         | 34,200,000         | 560,472          |  |
| 6kV VT Panel  |                                 | set       | 1        | 3,825,000        | 3,825,000          | 11,000           | 11,000         | 4,500,000          | 73,746           |  |
| Transmission Pump Panel                                     |                                 | set       | 3        | 23,800,000       | 71,400,000         | 68,667           | 206,000        | 84,000,000         | 1,376,598        | VFD:<br>Variable Frequency Drive                   |
| LV Transformer  | dry type 500kVA                 | set       | 1        | 7,225,000        | 7,225,000          | 21,000           | 21,000         | 8,500,000          | 139,299          |  |
| LV Main Switchgear  | 5 units                         | set       | 1        | 11,050,000       | 11,050,000         | 31,957           | 31,957         | 13,000,000         | 213,045          |  |
| MCC for Transmission-1                                      | 6 units                         | set       | 1        | 17,467,500       | 17,467,500         | 51,000           | 51,000         | 20,550,000         | 336,775          | MCC:<br>Motor Control Centre                       |
| Local Panel   |                                 | set       | 10       | 255,000          | 2,550,000          | 737              | 7,370          | 3,000,000          | 49,164           |  |
| <b>Instrumentation &amp; Monitoring</b>                     |                                 | <b>Ls</b> | <b>1</b> |                  | <b>41,395,000</b>  |                  | <b>119,717</b> | <b>48,700,000</b>  | <b>363,814</b>   | <b>3</b>   |
| Transmission Flow   | electro-magnetic<br>1400mm      | set       | 1        | 7,820,000        | 7,820,000          | 22,616           | 22,616         | 9,200,000          | 150,770          |  |
| Water Level   | Ultrasonic                      | set       | 5        | 680,000          | 3,400,000          | 1,967            | 9,835          | 4,000,000          | 65,552           |  |
| Water Quality   | Turbidity, pH, Res.<br>Chlorine | set       | 4        | 1,275,000        | 5,100,000          | 3,687            | 14,748         | 6,000,000          | 98,328           |  |
| Instrumentation Panel                                       |                                 | set       | 1        | 2,550,000        | 2,550,000          | 7,375            | 7,375          | 3,000,000          | 49,164           |  |
| PLC Panel   |                                 | set       | 2        | 6,375,000        | 12,750,000         | 18,437           | 36,874         | 15,000,000         | 245,821          | Programmable Logic<br>Controller                   |

**L1-3-3 Electrical Facility for Transmission Pump**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                                   | Specification         | Unit       | Qt'ty    | FC Portion (JPY) |                    | LC Portion (TND) |                  | Total              |                  | Reference                             |
|---|-----------------------|------------|----------|------------------|--------------------|------------------|------------------|--------------------|------------------|---------------------------------------|
|   |                       |            |          | Unit Price       | Amount             | Unit Price       | Amount           | (JPY)              | (equiv. TND)     |                                       |
| <i>Remote SCADA</i>                     |                       | <i>set</i> | <i>1</i> | 8,500,000        | 8,500,000          | 24,582           | 24,582           | 10,000,000         | 163,881          |                                       |
| <i>UPS</i>                              | <i>10kVA</i>          | <i>set</i> | <i>1</i> | 1,275,000        | 1,275,000          | 3,687            | 3,687            | 1,500,000          | 24,582           | UPS:<br>Uninterruptive Power          |
| <b>Other Miscellaneous Works</b>        |                       | <b>Ls</b>  | <b>1</b> |                  | <b>23,371,000</b>  |                  | <b>67,000</b>    | <b>27,459,340</b>  | <b>450,006</b>   | <b>4</b><br>Sum of (1~3) x <b>10%</b> |
| <b>Transmission Sub-station total</b>   | <b>to Total</b>       | <b>Ls</b>  | <b>1</b> |                  | <b>257,078,500</b> |                  | <b>741,939</b>   | <b>302,351,618</b> | <b>4,954,959</b> | <b>a. sum of (1~4)</b>                |
|   | FCP:LCP               |            |          |                  | 85%                |                  | 15%              |                    |                  |                                       |
| <b>Emergency Power Facilities</b>       |                       |            |          |                  |                    |                  |                  |                    |                  |                                       |
| <i>Stand-by Generator</i>               | <i>Diesel 2000kVA</i> | <i>set</i> | <i>1</i> | 129,200,000      | 129,200,000        | 374,000          | 374,000          | 152,000,000        | 2,490,987        | 5                                     |
| <i>DC Power</i>                         |                       | <i>set</i> | <i>2</i> | 1,275,000        | 2,550,000          | 3,500            | 7,000            | 3,000,000          | 49,164           | 6                                     |
| <i>UPS</i>                              | <i>10kVA</i>          | <i>set</i> | <i>2</i> | 1,275,000        | 2,550,000          | 3,500            | 7,000            | 3,000,000          | 49,164           | 7                                     |
| <i>Other Miscellaneous Works</i>        |                       | <i>Ls</i>  | <i>1</i> | 13,430,000       | 13,430,000         | 39,000           | 39,000           | 15,809,780         | 259,092          | 8<br>Sum of (5~7) x <b>10%</b>        |
| <b>Emergency Power Facilities total</b> | <b>to Total</b>       | <b>Ls</b>  | <b>1</b> |                  | <b>147,730,000</b> |                  | <b>427,000</b>   | <b>173,785,540</b> | <b>2,848,010</b> | <b>b. sum of (5~8)</b>                |
|   | FCP:LCP               |            |          |                  | 85%                |                  | 15%              |                    |                  |                                       |
| Total                                   |                       |            |          |                  | 404,808,500        |                  | 1,168,939        |                    |                  | a+b                                   |
| <b>Total Cost (Rounded)</b>             | <b>to L1-3</b>        |            |          |                  | <b>404,809,000</b> |                  | <b>1,169,000</b> | <b>476,141,000</b> | <b>7,803,000</b> | <b>L1-3-3</b>                         |
|   | FCP:LCP               |            |          |                  | 85%                |                  | 15%              |                    |                  |                                       |

10.5-32

**L1-4 Guarantee Test (for Desalination Plant for 12 Months)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items  | Specification      | Unit         | Qt'y      | FC Portion (JPY) |                    | LC Portion (TND) |                   | Total                |                   | Reference  |
|--|--------------------|--------------|-----------|------------------|--------------------|------------------|-------------------|----------------------|-------------------|--|
|  |                    |              |           | Unit Price       | Amount             | Unit Price       | Amount            | (JPY)                | (equiv. TND)      |  |
| <b>Power Cost</b>                            | <b>provisional</b> | <b>month</b> | <b>12</b> | 0                | <b>0</b>           | 1,885,380        | <b>22,625,000</b> | <b>1,380,578,000</b> | <b>22,625,008</b> | (Demand+Consumption)<br>for 90,000m3/day in average        |
| <b>Chemicals</b>                             | <b>provisional</b> | <b>month</b> | <b>12</b> | 11,843,982       | <b>142,128,000</b> | 0                | <b>0</b>          | <b>142,128,000</b>   | <b>2,329,204</b>  | for 90,000m3/day in average                                |
| NaClO, FeCl3, Na2S2O5, Antiscalant, NaOH     |                    |              |           |                  |                    |                  |                   |                      |                   |  |
| <b>RO Membrane Unit Replacement</b>          |                    | Ls           | -         | 0                | <b>0</b>           | 0                | <b>0</b>          | <b>0</b>             | <b>0</b>          | No charged replacement<br>because of 3 years guarantee     |
| <b>Remuneration</b>                          |                    |              |           |                  |                    |                  |                   |                      |                   |  |
| Foreign Engineer                             | 5 persons          | MM           | 30        | 2,412,500        | 72,375,000         | 0                | 0                 | 72,375,000           | 1,186,087         | Manager 12, Plant 12, Mech 2,<br>Elec 2, Instrument 2      |
| Local Engineer                               | 2 persons          | MM           | 24        | 0                | 0                  | 13,500           | 324,000           | 19,770,480           | 324,000           | Mechanical , Electrical                                    |
| Support/Administrative Staff                 | 30 persons         | MM           | 360       | 0                | 0                  | 10,000           | 3,600,000         | 219,672,000          | 3,600,000         | 8, guards 4, ope.supervisor 4,<br>operator 8               |
| <b>sub-total</b>                             |                    |              |           |                  | <b>72,375,000</b>  |                  | <b>3,924,000</b>  | <b>311,817,480</b>   | <b>5,110,087</b>  |  |
| <b>Direct Cost</b>                           |                    |              |           |                  |                    |                  |                   |                      |                   | Accommodation and per diem,<br>Travel for Foreign Engineer |
| International Travel                         |                    | trip         | 5         | 700,000          | 3,500,000          | 0                | 0                 | 3,500,000            | 57,358            |  |
| Accommodation & Per Diem of Foreign Engineer |                    | MM           | 30        | 0                | 0                  | 8,000            | 240,000           | 14,644,800           | 240,000           |  |
| Accommodation & Per Diem of Local Engineer   |                    | MM           | 24        | 0                | 0                  | 4,800            | 115,200           | 7,029,504            | 115,200           |  |
| Communication                                |                    | M            | 12        | 0                | 0                  | 1,000            | 12,000            | 732,240              | 12,000            |  |
| <b>sub-total</b>                             |                    |              |           |                  | <b>3,500,000</b>   |                  | <b>367,200</b>    | <b>25,906,544</b>    | <b>424,558</b>    |  |
| Total  |                    |              |           |                  | 218,003,000        |                  | 26,916,200        |                      |                   |  |
| <b>Total Cost (Rounded)</b>                  | <b>to L1</b>       |              |           |                  | <b>218,003,000</b> |                  | <b>26,916,000</b> | <b>1,860,417,000</b> | <b>30,489,000</b> | <b>L1-4</b>  |
|  | FCP:LCP            |              |           |                  | 12%                |                  | 88%               |                      |                   |  |

**L2-1 Transmission Pipe Material (1000mm & 1400mm) (ICB)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                  | Specification  | Unit | Qt'ly  | FC Portion (JPY) |                      | LC Portion (TND) |                  | Total                |                   | Reference            |
|------------------------|----------------|------|--------|------------------|----------------------|------------------|------------------|----------------------|-------------------|----------------------|
|                        |                |      |        | Unit Price       | Amount               | Unit Price       | Amount           | (JPY)                | (equiv. TND)      |                      |
| Pipe Material          | Dia 1000mm DIP | m    | 6,070  | 32,041           | 194,491,043          | 58.344           | 354,148          | 216,101,158          | 3,541,481         | 1. PK11 - PK10       |
| Pipe Material          | Dia 1400mm DIP | m    | 26,280 | 56,673           | 1,489,370,430        | 103.196          | 2,711,990        | 1,654,856,033        | 27,119,896        | 2. Plant - PK11      |
| Pipe Fittings Material |                | Ls   | 1      |                  | 505,158,442          |                  | 919,841          | 561,287,157          | 9,198,413         | Sum of (1 & 2) x 30% |
|                        |                |      |        |                  |                      |                  |                  |                      |                   |                      |
|                        |                |      |        |                  |                      |                  |                  |                      |                   |                      |
|                        |                |      |        |                  |                      |                  |                  |                      |                   |                      |
|                        |                |      |        |                  |                      |                  |                  |                      |                   |                      |
|                        |                |      |        |                  |                      |                  |                  |                      |                   |                      |
|                        |                |      |        |                  |                      |                  |                  |                      |                   |                      |
|                        |                |      |        |                  |                      |                  |                  |                      |                   |                      |
|                        |                |      |        |                  |                      |                  |                  |                      |                   |                      |
|                        |                |      |        |                  |                      |                  |                  |                      |                   |                      |
|                        |                |      |        |                  |                      |                  |                  |                      |                   |                      |
| <b>Total</b>           |                |      |        |                  | 2,189,019,914        |                  | 3,985,979        |                      |                   |                      |
| <b>Total (Rounded)</b> | <b>to T1</b>   |      |        |                  | <b>2,189,020,000</b> |                  | <b>3,986,000</b> | <b>2,432,246,000</b> | <b>39,860,000</b> | <b>L2-1</b>          |
|                        | FCP:LCP        |      |        |                  | 90%                  |                  | 10%              |                      |                   |                      |

**L2-2 Transmission Pipe Material (Less than 1000mm) (ICB)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                  | Specification | Unit | Qt'ty | FC Portion (JPY) |                    | LC Portion (TND) |                | Total              |                  | Reference               |
|------------------------|---------------|------|-------|------------------|--------------------|------------------|----------------|--------------------|------------------|-------------------------|
|                        |               |      |       | Unit Price       | Amount             | Unit Price       | Amount         | (JPY)              | (equiv. TND)     |                         |
| Pipe Material          | Dia 400mm DIP | m    | 2,860 | 7,677            | 21,955,005         | 13.978           | 39,978         | 24,394,451         | 399,778          | 1. PK11- Bou Merra      |
| Pipe Material          | Dia 800mm DIP | m    | 9,360 | 22,095           | 206,810,945        | 40.233           | 376,581        | 229,789,939        | 3,765,813        | 2. PK14 - Sidi Salah EH |
| Pipe Material          | Dia 800mm DIP | m    | 4,810 | 22,095           | 106,277,847        | 40.233           | 193,521        | 118,086,496        | 1,935,210        | 3. PK10 - PK14          |
| Pipe Fittings Material |               | Ls   | 1     |                  | 100,513,139        |                  | 183,024        | 111,681,266        | 1,830,240        | Sum of (1~3) x 30%      |
|                        |               |      |       |                  |                    |                  |                |                    |                  |                         |
|                        |               |      |       |                  |                    |                  |                |                    |                  |                         |
|                        |               |      |       |                  |                    |                  |                |                    |                  |                         |
|                        |               |      |       |                  |                    |                  |                |                    |                  |                         |
|                        |               |      |       |                  |                    |                  |                |                    |                  |                         |
|                        |               |      |       |                  |                    |                  |                |                    |                  |                         |
|                        |               |      |       |                  |                    |                  |                |                    |                  |                         |
|                        |               |      |       |                  |                    |                  |                |                    |                  |                         |
|                        |               |      |       |                  |                    |                  |                |                    |                  |                         |
| Total                  |               |      |       |                  | 435,556,936        |                  | 793,104        |                    |                  |                         |
| <b>Total (Rounded)</b> | <b>to T1</b>  |      |       |                  | <b>435,557,000</b> |                  | <b>793,000</b> | <b>483,946,000</b> | <b>7,931,000</b> | <b>L2-2</b>             |
|                        | FCP:LCP       |      |       |                  | 90%                |                  | 10%            |                    |                  |                         |

10.5-35

**L3 Valves Material (LCB)**

Exchange Rate: 1.00US\$= 119.60JPY      1.000TND= 61.02JPY

| Items                    | Specification | Unit | Qt'ty | FC Portion (JPY) |                    | LC Portion (TND) |                | Total              |                  | Reference     |
|--------------------------|---------------|------|-------|------------------|--------------------|------------------|----------------|--------------------|------------------|---------------|
|                          |               |      |       | Unit Price       | Amount             | Unit Price       | Amount         | (JPY)              | (equiv. TND)     |               |
| Air Valve Material       | Dia 100mm     | pcs  | 6     | 82,039           | 492,235            | 149.385          | 896            | 546,928            | 8,963            |               |
| Air Valve Material       | Dia 150mm     | pcs  | 29    | 193,116          | 5,600,362          | 351.644          | 10,198         | 6,222,625          | 101,977          |               |
| Air Valve Material       | Dia 200mm     | pcs  | 64    | 471,609          | 30,182,959         | 858.751          | 54,960         | 33,536,621         | 549,600          |               |
| Butterfly Valve Material | Dia 400mm     | pcs  | 3     | 1,063,373        | 3,190,118          | 1,936.292        | 5,809          | 3,544,575          | 58,089           | 2,860m/1,000m |
| Butterfly Valve Material | Dia 800mm     | pcs  | 10    | 2,585,604        | 25,856,041         | 4,708.118        | 47,081         | 28,728,934         | 470,812          | 9,360m/1,000m |
| Butterfly Valve Material | Dia 800mm     | pcs  | 5     | 2,585,604        | 12,928,020         | 4,708.118        | 23,541         | 14,364,467         | 235,406          | 4,810m/1,000m |
| Butterfly Valve Material | Dia 1000mm    | pcs  | 12    | 4,113,777        | 49,365,319         | 7,490.762        | 89,889         | 54,850,355         | 898,891          | 6,070m/500m   |
| Butterfly Valve Material | Dia 1400mm    | pcs  | 53    | 6,842,165        | 362,634,744        | 12,458.875       | 660,320        | 402,927,493        | 6,603,204        | 26,280m/500m  |
| Gate Valve Material      | Dia 75mm      | pcs  | 6     | 42,455           | 254,729            | 77.306           | 464            | 283,032            | 4,638            |               |
| Gate Valve Material      | Dia 150mm     | pcs  | 29    | 96,591           | 2,801,149          | 175.883          | 5,101          | 3,112,388          | 51,006           |               |
| Gate Valve Material      | Dia 300mm     | pcs  | 64    | 273,219          | 17,486,037         | 497.504          | 31,840         | 19,428,930         | 318,403          |               |
|                          |               |      |       |                  |                    |                  |                |                    |                  |               |
|                          |               |      |       |                  |                    |                  |                |                    |                  |               |
| <b>Total</b>             |               |      |       |                  | 510,791,713        |                  | 930,099        |                    |                  |               |
| <b>Total (Rounded)</b>   | <b>to T1</b>  |      |       |                  | <b>510,792,000</b> |                  | <b>930,000</b> | <b>567,541,000</b> | <b>9,301,000</b> | <b>L3</b>     |
|                          | FCP:LCP       |      |       |                  | 90%                |                  | 10%            |                    |                  |               |

10.5-36

**L4 Pipe Installation (ICB)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                          | Specification | Unit | Qt'ty | FC Portion (JPY) |                   | LC Portion (TND) |                   | Total                |                   | Reference |
|--------------------------------|---------------|------|-------|------------------|-------------------|------------------|-------------------|----------------------|-------------------|-----------|
|                                |               |      |       | Unit Price       | Amount            | Unit Price       | Amount            | (JPY)                | (equiv. TND)      |           |
| Transmission Pipe Installatiom |               | Ls   | 1     |                  | 0                 |                  | 40,270,000        | 2,457,275,400        | 40,270,000        | L4-1      |
| Valve Installation             |               | Ls   | 1     |                  | 0                 |                  | 615,000           | 37,527,300           | 615,000           | L4-2      |
| Pipe Jacking                   |               | Ls   | 1     |                  | 0                 |                  | 4,369,000         | 266,596,380          | 4,369,000         | L4-3      |
| Surge Tank                     | 10mx15mx2     | Ls   | 1     |                  | 40,430,000        |                  | 2,262,000         | 178,457,240          | 2,924,570         | L4-4      |
|                                |               |      |       |                  |                   |                  |                   |                      |                   |           |
|                                |               |      |       |                  |                   |                  |                   |                      |                   |           |
|                                |               |      |       |                  |                   |                  |                   |                      |                   |           |
|                                |               |      |       |                  |                   |                  |                   |                      |                   |           |
|                                |               |      |       |                  |                   |                  |                   |                      |                   |           |
|                                |               |      |       |                  |                   |                  |                   |                      |                   |           |
|                                |               |      |       |                  |                   |                  |                   |                      |                   |           |
|                                |               |      |       |                  |                   |                  |                   |                      |                   |           |
|                                |               |      |       |                  |                   |                  |                   |                      |                   |           |
| <b>Total</b>                   |               |      |       |                  | 40,430,000        |                  | 47,516,000        |                      |                   |           |
| <b>Total (Rounded)</b>         | <b>to T1</b>  |      |       |                  | <b>40,430,000</b> |                  | <b>47,516,000</b> | <b>2,939,856,000</b> | <b>48,179,000</b> | <b>L4</b> |
|                                | FCP:LCP       |      |       |                  | 1%                |                  | 99%               |                      |                   |           |

10.5-37



### L4-1 Transmission Pipe Installation

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                      | Specification  | Unit  | Qt'ty  | FC Portion (JPY) |          | LC Portion (TND) |                   | Total                |                   | Reference                |
|----------------------------|----------------|-------|--------|------------------|----------|------------------|-------------------|----------------------|-------------------|--------------------------|
|                            |                |       |        | Unit Price       | Amount   | Unit Price       | Amount            | (JPY)                | (equiv. TND)      |                          |
| Pipe Installation          | Dia 400mm DIP  | m     | 2,860  | 0                | 0        | 121.780          | 348,291           | 21,252,705           | 348,291           | 1.PK11- Bou Merrra       |
| Pipe Installation          | Dia 800mm DIP  | m     | 9,360  | 0                | 0        | 436.360          | 4,084,330         | 249,225,792          | 4,084,330         | 2.PK14 - Sidi Salah EH   |
| Pipe Installation          | Dia 800mm DIP  | m     | 4,810  | 0                | 0        | 436.360          | 2,098,892         | 128,074,365          | 2,098,892         | 3.PK10 - PK14            |
| Pipe Installation          | Dia 1000mm DIP | m     | 6,070  | 0                | 0        | 549.140          | 3,333,280         | 203,396,733          | 3,333,280         | 4.PK11 - PK10            |
| Pipe Installation          | Dia 1400mm DIP | m     | 26,280 | 0                | 0        | 821.440          | 21,587,443        | 1,317,265,784        | 21,587,443        | 5.Plant - PK11           |
| Pipe Fittings Installation |                | Ls    | 1      |                  | 0        |                  | 1,572,612         | 95,960,769           | 1,572,612         | Sum of (1~5) x 5%        |
| Pipe Connecting            | Dia 400mm DIP  | joint | 477    | 0                | 0        | 110.000          | 52,470            | 3,201,719            | 52,470            | 2,860m/6m                |
| Pipe Connecting            | Dia 800mm DIP  | joint | 1,560  | 0                | 0        | 264.000          | 411,840           | 25,130,477           | 411,840           | 9,360m/6m                |
| Pipe Connecting            | Dia 800mm DIP  | joint | 802    | 0                | 0        | 264.000          | 211,728           | 12,919,643           | 211,728           | 4,810m6m                 |
| Pipe Connecting            | Dia 1000mm DIP | joint | 1,012  | 0                | 0        | 330.000          | 333,960           | 20,378,239           | 333,960           | 6,070m6m                 |
| Pipe Connecting            | Dia 1400mm DIP | joint | 4,380  | 0                | 0        | 660.000          | 2,890,800         | 176,396,616          | 2,890,800         | 26,280m/6m               |
| Miscellaneous Works        |                | Ls    | 1      |                  | 0        |                  | 3,692,564         | 225,320,284          | 3,692,564         | Sum of other items x 10% |
|                            |                |       |        |                  |          |                  |                   |                      |                   |                          |
| Total                      |                |       |        |                  | 0        |                  | 40,269,918        |                      |                   |                          |
| <b>Total (Rounded)</b>     | <b>to L4</b>   |       |        |                  | <b>0</b> |                  | <b>40,270,000</b> | <b>2,457,275,000</b> | <b>40,270,000</b> | <b>L4-1</b>              |
|                            | FCP:LCP        |       |        |                  | 0%       |                  | 100%              |                      |                   |                          |

## L4-2 Valves Installation

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                        | Specification | Unit | Qt'ly | FC Portion (JPY) |          | LC Portion (TND) |                | Total             |                | Reference                |
|------------------------------|---------------|------|-------|------------------|----------|------------------|----------------|-------------------|----------------|--------------------------|
|                              |               |      |       | Unit Price       | Amount   | Unit Price       | Amount         | (JPY)             | (equiv. TND)   |                          |
| Air Valve Installation       | Dia 100mm     | pcs  | 6     | 0                | 0        | 550.000          | 3,300          | 201,366           | 3,300          | 2,860m/500m              |
| Air Valve Installation       | Dia 150mm     | pcs  | 29    | 0                | 0        | 660.000          | 19,140         | 1,167,923         | 19,140         | (9,360m+4810m)/500m      |
| Air Valve Installation       | Dia 200mm     | pcs  | 64    | 0                | 0        | 770.000          | 49,280         | 3,007,066         | 49,280         | (6,070m+26,280m)/500m    |
| Butterfly Valve Installation | Dia 400mm     | pcs  | 3     | 0                | 0        | 1,100.000        | 3,300          | 201,366           | 3,300          | 2,860m/1,000m            |
| Butterfly Valve Installation | Dia 800mm     | pcs  | 10    | 0                | 0        | 2,420.000        | 24,200         | 1,476,684         | 24,200         | 9,360m/1,000m            |
| Butterfly Valve Installation | Dia 800mm     | pcs  | 5     | 0                | 0        | 2,420.000        | 12,100         | 738,342           | 12,100         | 4,810m/1,000m            |
| Butterfly Valve Installation | Dia 1000mm    | pcs  | 12    | 0                | 0        | 2,970.000        | 35,640         | 2,174,753         | 35,640         | 6,070m/500m              |
| Butterfly Valve Installation | Dia 1400mm    | pcs  | 53    | 0                | 0        | 3,520.000        | 186,560        | 11,383,891        | 186,560        | 26,280m/500m             |
| Gate Valve Installation      | Dia 75mm      | pcs  | 6     | 0                | 0        | 550.000          | 3,300          | 201,366           | 3,300          |                          |
| Gate Valve Installation      | Dia 150mm     | pcs  | 29    | 0                | 0        | 660.000          | 19,140         | 1,167,923         | 19,140         |                          |
| Gate Valve Installation      | Dia 300mm     | pcs  | 64    | 0                | 0        | 880.000          | 56,320         | 3,436,646         | 56,320         |                          |
| MiscellaneousWorks           |               | Ls   | 1     |                  | 0        |                  | 206,140        | 12,578,663        | 206,140        | Sum of other items x 50% |
|                              |               |      |       |                  |          |                  |                |                   |                |                          |
| Total                        |               |      |       |                  | 0        |                  | 615,120        |                   |                |                          |
| <b>Total (Rounded)</b>       | <b>to L4</b>  |      |       |                  | <b>0</b> |                  | <b>615,000</b> | <b>37,527,000</b> | <b>615,000</b> | <b>L4-2</b>              |
|                              | FCP:LCP       |      |       |                  | 0%       |                  | 100%           |                   |                |                          |

**L4-3 Pipe Jacking**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                  | Specification | Unit | Qt'ty | FC Portion (JPY) |          | LC Portion (TND) |                  | Total              |                  | Reference                                |
|------------------------|---------------|------|-------|------------------|----------|------------------|------------------|--------------------|------------------|--|
|                        |               |      |       | Unit Price       | Amount   | Unit Price       | Amount           | (JPY)              | (equiv. TND)     |  |
| Pipe Jacking           | Dia 400mm     | lot  | 1     | 0                | 0        | 1,100.000        | 55,000           | 3,356,100          | 55,000           | unit price x 50m/lot<br>PK11 - Bou Merra |
| Pipe Jacking           | Dia 800mm     | lot  | 5     | 0                | 0        | 2,420.000        | 605,000          | 36,917,100         | 605,000          | unit price x 50m/lot<br>PK14 - SSEH      |
| Pipe Jacking           | Dia 800mm     | lot  | 1     | 0                | 0        | 2,420.000        | 121,000          | 7,383,420          | 121,000          | unit price x 50m/lot<br>PK10 - PK14      |
| Pipe Jacking           | Dia 1000mm    | lot  | 5     | 0                | 0        | 2,970.000        | 742,500          | 45,307,350         | 742,500          | unit price x 50m/lot<br>PK11 - PK10      |
| Pipe Jacking           | Dia 1400mm    | lot  | 11    | 0                | 0        | 3,850.000        | 2,117,500        | 129,209,850        | 2,117,500        | unit price x 50m/lot<br>Plant - PK11     |
| Other Works            |               | Ls   | 1     |                  | 0        |                  | 728,200          | 44,434,764         | 728,200          | Sum of Other Items x 20%                 |
|                        |               |      |       |                  |          |                  |                  |                    |                  |  |
|                        |               |      |       |                  |          |                  |                  |                    |                  |  |
|                        |               |      |       |                  |          |                  |                  |                    |                  |  |
|                        |               |      |       |                  |          |                  |                  |                    |                  |  |
|                        |               |      |       |                  |          |                  |                  |                    |                  |  |
|                        |               |      |       |                  |          |                  |                  |                    |                  |  |
|                        |               |      |       |                  |          |                  |                  |                    |                  |  |
|                        |               |      |       |                  |          |                  |                  |                    |                  |  |
| Total                  |               |      |       |                  | 0        |                  | 4,369,200        |                    |                  |  |
| <b>Total (Rounded)</b> | <b>to L4</b>  |      |       |                  | <b>0</b> |                  | <b>4,369,000</b> | <b>266,596,000</b> | <b>4,369,000</b> | <b>L4-3</b>                              |
|                        | FCP:LCP       |      |       |                  | 0%       |                  | 100%             |                    |                  |  |

**L4-4 Surge Tank**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                            | Specification                | Unit | Qty | FC Portion (JPY) |                   | LC Portion (TND) |                  | Total              |                  | Reference    |
|----------------------------------|------------------------------|------|-----|------------------|-------------------|------------------|------------------|--------------------|------------------|--------------|
|                                  |                              |      |     | Unit Price       | Amount            | Unit Price       | Amount           | (JPY)              | (equiv. TND)     |              |
| <b>1200 m3 (10m dia x 15m H)</b> | <b>1200m3/Tank x 2 tanks</b> |      |     |                  |                   |                  |                  |                    |                  | Plant - PK11 |
| Structure                        | <b>2 tanks</b>               | tank | 2   | 0                | 0                 | 1,031,000        | 2,062,000        | 125,823,240        | 2,062,000        | L4-4-1       |
| Piping                           | <b>for 2 tanks</b>           | lot  | 2   | 20,215,000       | 40,430,000        | 100,000          | 200,000          | 52,634,000         | 862,570          | L4-4-2       |
|                                  |                              |      |     |                  |                   |                  |                  |                    |                  |              |
|                                  |                              |      |     |                  |                   |                  |                  |                    |                  |              |
|                                  |                              |      |     |                  |                   |                  |                  |                    |                  |              |
|                                  |                              |      |     |                  |                   |                  |                  |                    |                  |              |
|                                  |                              |      |     |                  |                   |                  |                  |                    |                  |              |
|                                  |                              |      |     |                  |                   |                  |                  |                    |                  |              |
|                                  |                              |      |     |                  |                   |                  |                  |                    |                  |              |
|                                  |                              |      |     |                  |                   |                  |                  |                    |                  |              |
|                                  |                              |      |     |                  |                   |                  |                  |                    |                  |              |
|                                  |                              |      |     |                  |                   |                  |                  |                    |                  |              |
| Total                            |                              |      |     |                  | 40,430,000        |                  | 2,262,000        |                    |                  |              |
| <b>Total (Rounded)</b>           | <b>to L4</b>                 |      |     |                  | <b>40,430,000</b> |                  | <b>2,262,000</b> | <b>178,457,000</b> | <b>2,925,000</b> | <b>L4-4</b>  |
|                                  | FCP:LCP                      |      |     |                  | 23%               |                  | 77%              |                    |                  |              |

**L4-4-1 Structure of Surge Tank**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                     | Specification  | Unit           | Qty   | FC Portion (JPY) |          | LC Portion (TND) |                  | Total             |                  | Reference                |
|---------------------------|----------------|----------------|-------|------------------|----------|------------------|------------------|-------------------|------------------|--------------------------|
|                           |                |                |       | Unit Price       | Amount   | Unit Price       | Amount           | (JPY)             | (equiv. TND)     |                          |
| 1200 m3 (10m dia x 15m H) |                |                |       |                  |          |                  |                  |                   |                  |                          |
| Excavation                |                | m <sup>3</sup> | 937   | 0                | 0        | 16.500           | 15,461           | 943,430           | 15,461           |                          |
| Backfilling/Filling       |                | m <sup>3</sup> | 408   | 0                | 0        | 11.000           | 4,488            | 273,858           | 4,488            |                          |
| Waste Soil Removal        |                | m <sup>3</sup> | 529   | 0                | 0        | 23.100           | 12,220           | 745,664           | 12,220           |                          |
| Gravel                    |                | m <sup>3</sup> | 35    | 0                | 0        | 74.800           | 2,618            | 159,750           | 2,618            |                          |
| Waterproofing             |                | m <sup>2</sup> | 110   | 0                | 0        | 42.900           | 4,719            | 287,953           | 4,719            |                          |
| Formwork                  |                | m <sup>2</sup> | 1,758 | 0                | 0        | 62.700           | 110,227          | 6,726,052         | 110,227          |                          |
| Lean Concrete             |                | m <sup>3</sup> | 17    | 0                | 0        | 440.000          | 7,480            | 456,430           | 7,480            |                          |
| Reinforced Concrete       |                | m <sup>3</sup> | 686   | 0                | 0        | 935.000          | 641,410          | 39,138,838        | 641,410          |                          |
| Scaffolding               |                | m <sup>2</sup> | 1,289 | 0                | 0        | 107.800          | 138,954          | 8,478,973         | 138,954          |                          |
| Other Miscellaneous Works | incl. Rebar    | Ls             | 1     |                  | 0        |                  | 93,758           | 5,721,095         | 93,758           | Sum of above items x 10% |
|                           |                |                |       |                  |          |                  |                  |                   |                  |                          |
|                           |                |                |       |                  |          |                  |                  |                   |                  |                          |
| <b>Total</b>              | 1200 m3        |                |       |                  | 0        |                  | 1,031,335        |                   |                  | for 1200m3               |
| <b>Total (Rounded)</b>    | <b>to L4-4</b> |                |       |                  | <b>0</b> |                  | <b>1,031,000</b> | <b>62,912,000</b> | <b>1,031,000</b> | <b>L4-4-1 per tank</b>   |
|                           | FCP:LCP        |                |       |                  | 0%       |                  | 100%             |                   |                  |                          |

**L4-4-2 Piping for Surge Tank φ10x15m**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                                 | Specification  | Unit  | Qty | FC Portion (JPY) |                   | LC Portion (TND) |                | Total             |                | Reference              |
|---------------------------------------|----------------|-------|-----|------------------|-------------------|------------------|----------------|-------------------|----------------|------------------------|
|                                       |                |       |     | Unit Price       | Amount            | Unit Price       | Amount         | (JPY)             | (equiv. TND)   |                        |
| piping for φ10x15m One-way Surge Tank |                |       |     |                  |                   |                  |                |                   |                |                        |
| Butterfly Valve Materials             | Dia. 800mm     | set   | 4   | 2,585,604        | 10,342,416        | 4,708.118        | 18,832         | 11,491,545        | 188,324        |                        |
| Check Valve Materials                 | Dia. 800mm     | set   | 2   | 2,585,604        | 5,171,208         | 4,708.118        | 9,416          | 5,745,772         | 94,162         |                        |
| Pipe Materials                        | Dia. 800mm     | m     | 30  | 22,095           | 662,856           | 40.233           | 1,207          | 736,507           | 12,070         |                        |
| Pipe Materails                        | Dia. 600mm     | m     | 100 | 14,018           | 1,401,809         | 25.526           | 2,553          | 1,557,593         | 25,526         |                        |
| Butterfly Valve Installation          | Dia. 800mm     | set   | 4   | 0                | 0                 | 2,420.000        | 9,680          | 590,674           | 9,680          |                        |
| Check Valve Installation              | Dia. 800mm     | set   | 2   | 0                | 0                 | 2,420.000        | 4,840          | 295,337           | 4,840          |                        |
| Pipe Installation                     | Dia. 800mm     | m     | 30  | 0                | 0                 | 436.360          | 13,091         | 798,813           | 13,091         |                        |
| Joint Connection                      | Dia. 800mm     | joint | 5   | 0                | 0                 | 440.000          | 2,200          | 134,244           | 2,200          |                        |
| Pipe Installation                     | Dia. 600mm     | m     | 100 | 0                | 0                 | 193.090          | 19,309         | 1,178,235         | 19,309         |                        |
| Joint Connection                      | Dia. 600mm     | joint | 17  | 0                | 0                 | 330.000          | 5,610          | 342,322           | 5,610          |                        |
| Other Miscellaneous Works             | 15%            | lot   | 1   |                  | 2,636,743         |                  | 13,011         | 3,430,656         | 56,222         | 15% of above total     |
|                                       |                |       |     |                  |                   |                  |                |                   |                |                        |
| Total                                 |                |       |     |                  | 20,215,032        |                  | 99,749         |                   |                |                        |
| <b>Total (Rounded)</b>                | <b>to L4-4</b> |       |     |                  | <b>20,215,000</b> |                  | <b>100,000</b> | <b>26,317,000</b> | <b>431,000</b> | <b>L4-4-2 per Tank</b> |
|                                       | FCP:LCP        |       |     |                  | 77%               |                  | 23%            |                   |                |                        |

**L5 Reservoirs Construction**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items  | Specification | Unit | Qty | FC Portion (JPY) |          | LC Portion (TND) |                  | Total              |                  | Reference |
|--|---------------|------|-----|------------------|----------|------------------|------------------|--------------------|------------------|-----------|
|  |               |      |     | Unit Price       | Amount   | Unit Price       | Amount           | (JPY)              | (equiv. TND)     |           |
| Mixing Chamber (PK11)                          |               | Ls   | 1   |                  | 0        |                  | 1,501,000        | 91,591,020         | 1,501,000        | L5-1      |
| Mixing Chamber (Bou Merra)                     |               | Ls   | 1   |                  | 0        |                  | 281,000          | 17,146,620         | 281,000          | L5-2      |
| Mixing Chamber (PK10)                          |               | Ls   | 1   |                  | 0        |                  | 560,000          | 34,171,200         | 560,000          | L5-3      |
| Mixing Chamber (PK14)                          |               | Ls   | 1   |                  | 0        |                  | 472,000          | 28,801,440         | 472,000          | L5-4      |
| Mixing Chamber (Sidi Salah EH)                 |               | Ls   | 1   |                  | 0        |                  | 319,000          | 19,465,380         | 319,000          | L5-5      |
| Distribution Reservoir (Bou Merra, V=5,000 m3) |               | Ls   | 1   |                  | 0        |                  | 1,890,000        | 115,327,800        | 1,890,000        | L5-6      |
|  |               |      |     |                  |          |                  |                  |                    |                  |           |
|  |               |      |     |                  |          |                  |                  |                    |                  |           |
|  |               |      |     |                  |          |                  |                  |                    |                  |           |
|  |               |      |     |                  |          |                  |                  |                    |                  |           |
|  |               |      |     |                  |          |                  |                  |                    |                  |           |
|  |               |      |     |                  |          |                  |                  |                    |                  |           |
|  |               |      |     |                  |          |                  |                  |                    |                  |           |
|  |               |      |     |                  |          |                  |                  |                    |                  |           |
| <b>Total</b>                                   |               |      |     |                  | 0        |                  | 5,023,000        |                    |                  |           |
| <b>Total Cost (Rounded)</b>                    | <b>to T1</b>  |      |     |                  | <b>0</b> |                  | <b>5,023,000</b> | <b>306,503,000</b> | <b>5,023,000</b> | <b>L5</b> |
|  | FCP:LCP       |      |     |                  | 0%       |                  | 100%             |                    |                  |           |

**L5-1 Mixing Chamber (PK11)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items   | Specification | Unit           | Qt'ty | FC Portion (JPY) |          | LC Portion (TND) |                  | Total             |                  | Reference            |
|---|---------------|----------------|-------|------------------|----------|------------------|------------------|-------------------|------------------|----------------------|
|   |               |                |       | Unit Price       | Amount   | Unit Price       | Amount           | (JPY)             | (equiv. TND)     |                      |
| Excavation  |               | m <sup>3</sup> | 280   | 0                | 0        | 16.500           | 4,620            | 281,912           | 4,620            |                      |
| Backfilling/Filling                               |               | m <sup>3</sup> | 5048  | 0                | 0        | 11.000           | 55,528           | 3,388,319         | 55,528           |                      |
| Waste Soil Removal                                |               | m <sup>3</sup> | 230   | 0                | 0        | 23.100           | 5,313            | 324,199           | 5,313            |                      |
| Gravel  |               | m <sup>3</sup> | 59    | 0                | 0        | 74.800           | 4,413            | 269,281           | 4,413            |                      |
| Waterproofing                                     |               | m <sup>2</sup> | 582   | 0                | 0        | 42.900           | 24,968           | 1,523,547         | 24,968           |                      |
| Formwork  |               | m <sup>2</sup> | 2280  | 0                | 0        | 62.700           | 142,956          | 8,723,175         | 142,956          |                      |
| Lean Concrete                                     |               | m <sup>3</sup> | 29    | 0                | 0        | 440.000          | 12,760           | 778,615           | 12,760           |                      |
| Reinforced Concrete                               |               | m <sup>3</sup> | 970   | 0                | 0        | 935.000          | 906,950          | 55,342,089        | 906,950          |                      |
| Reinforcement Bar                                 |               | ton            | 97.0  | 0                | 0        | 1320.000         | 128,040          | 7,813,001         | 128,040          | 100kg/m3             |
| Scaffolding                                       |               | m <sup>2</sup> | 729   | 0                | 0        | 107.800          | 78,586           | 4,795,318         | 78,586           |                      |
| Other Miscellaneous Works                         |               | Ls             | 1     |                  | 0        |                  | 136,413          | 8,323,946         | 136,413          | above items<br>x 10% |
| Above quantities includes those for Valve Chamber |               |                |       |                  |          |                  |                  |                   |                  |                      |
|   |               |                |       |                  |          |                  |                  |                   |                  |                      |
| Total   |               |                |       |                  | 0        |                  | 1,500,547        |                   |                  |                      |
| <b>Total Cost (Rounded)</b>                       | <b>to L5</b>  |                |       |                  | <b>0</b> |                  | <b>1,501,000</b> | <b>91,591,000</b> | <b>1,501,000</b> | <b>L5-1</b>          |
|   | FCP:LCP       |                |       |                  | 0%       |                  | 100%             |                   |                  |                      |

10.5-45



**L5-2 Mixing Chamber (Bou Merra)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items   | Specification | Unit           | Qt'ty | FC Portion (JPY) |          | LC Portion (TND) |                | Total             |                | Reference              |
|---|---------------|----------------|-------|------------------|----------|------------------|----------------|-------------------|----------------|------------------------|
|   |               |                |       | Unit Price       | Amount   | Unit Price       | Amount         | (JPY)             | (equiv. TND)   |                        |
| Excavation  |               | m <sup>3</sup> | 183   | 0                | 0        | 16.500           | 3,020          | 184,280           | 3,020          |                        |
| Backfilling/Filling                               |               | m <sup>3</sup> | 48    | 0                | 0        | 11.000           | 528            | 32,219            | 528            |                        |
| Waste Soil Removal                                |               | m <sup>3</sup> | 136   | 0                | 0        | 23.100           | 3,142          | 191,725           | 3,142          |                        |
| Gravel  |               | m <sup>3</sup> | 15    | 0                | 0        | 74.800           | 1,122          | 68,464            | 1,122          |                        |
| Waterproofing                                     |               | m <sup>2</sup> | 165   | 0                | 0        | 42.900           | 7,079          | 431,961           | 7,079          |                        |
| Formwork  |               | m <sup>2</sup> | 670   | 0                | 0        | 62.700           | 42,009         | 2,563,389         | 42,009         |                        |
| Lean Concrete                                     |               | m <sup>3</sup> | 7     | 0                | 0        | 440.000          | 3,080          | 187,942           | 3,080          |                        |
| Reinforced Concrete                               |               | m <sup>3</sup> | 159   | 0                | 0        | 935.000          | 148,665        | 9,071,538         | 148,665        |                        |
| Reinforcement Bar                                 |               | ton            | 15.9  | 0                | 0        | 1320.000         | 20,988         | 1,280,688         | 20,988         | 100kg/m3               |
| Scaffolding                                       |               | m <sup>2</sup> | 243   | 0                | 0        | 107.800          | 26,195         | 1,598,419         | 26,195         |                        |
| Other Miscellaneous Works                         |               | Ls             | 1     |                  | 0        |                  | 25,583         | 1,561,062         | 25,583         | Sum of above items 10% |
| Above quantities includes those for Valve Chamber |               |                |       |                  |          |                  |                |                   |                |                        |
|   |               |                |       |                  |          |                  |                |                   |                |                        |
|   |               |                |       |                  |          |                  |                |                   |                |                        |
| Total   |               |                |       |                  | 0        |                  | 281,411        |                   |                |                        |
| <b>Total Cost (Rounded)</b>                       | <b>to L5</b>  |                |       |                  | <b>0</b> |                  | <b>281,000</b> | <b>17,147,000</b> | <b>281,000</b> | <b>L5-2</b>            |
|   | FCP:LCP       |                |       |                  | 0%       |                  | 100%           |                   |                |                        |

10.5-46

**L5-3 Mixing Chamber (PK10)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items   | Specification | Unit           | Qt'ty | FC Portion (JPY) |          | LC Portion (TND) |                | Total             |                | Reference                |
|---|---------------|----------------|-------|------------------|----------|------------------|----------------|-------------------|----------------|--------------------------|
|   |               |                |       | Unit Price       | Amount   | Unit Price       | Amount         | (JPY)             | (equiv. TND)   |                          |
| Excavation  |               | m <sup>3</sup> | 93    | 0                | 0        | 16.500           | 1,535          | 93,666            | 1,535          |                          |
| Backfilling/Filling                               |               | m <sup>3</sup> | 393   | 0                | 0        | 11.000           | 4,323          | 263,789           | 4,323          |                          |
| Waste Soil Removal                                |               | m <sup>3</sup> | 72    | 0                | 0        | 23.100           | 1,663          | 101,476           | 1,663          |                          |
| Gravel  |               | m <sup>3</sup> | 31    | 0                | 0        | 74.800           | 2,319          | 141,505           | 2,319          |                          |
| Waterproofing                                     |               | m <sup>2</sup> | 339   | 0                | 0        | 42.900           | 14,543         | 887,414           | 14,543         |                          |
| Formwork  |               | m <sup>2</sup> | 1,122 | 0                | 0        | 62.700           | 70,349         | 4,292,696         | 70,349         |                          |
| Lean Concrete                                     |               | m <sup>3</sup> | 16    | 0                | 0        | 440.000          | 7,040          | 429,581           | 7,040          |                          |
| Reinforced Concrete                               |               | m <sup>3</sup> | 343   | 0                | 0        | 935.000          | 320,705        | 19,569,419        | 320,705        |                          |
| Reinforcement Bar                                 |               | ton            | 34.3  | 0                | 0        | 1320.000         | 45,276         | 2,762,742         | 45,276         | 100kg/m3                 |
| Scaffolding                                       |               | m <sup>2</sup> | 387   | 0                | 0        | 107.800          | 41,719         | 2,545,693         | 41,719         |                          |
| Other Miscellaneous Works                         |               | Ls             | 1     |                  | 0        |                  | 50,947         | 3,108,798         | 50,947         | Sum of above items x 10% |
| Above quantities includes those for Valve Chamber |               |                |       |                  |          |                  |                |                   |                |                          |
|   |               |                |       |                  |          |                  |                |                   |                |                          |
| Total   |               |                |       |                  | 0        |                  | 560,419        |                   |                |                          |
| <b>Total Cost (Rounded)</b>                       | <b>to L5</b>  |                |       |                  | <b>0</b> |                  | <b>560,000</b> | <b>34,171,000</b> | <b>560,000</b> | <b>L5-3</b>              |
|   | FCP:LCP       |                |       |                  | 0%       |                  | 100%           |                   |                |                          |

10.5-47

**L5-4 Mixing Chamber (PK14)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items   | Specification | Unit           | Qt'ty | FC Portion (JPY) |          | LC Portion (TND) |                | Total             |                | Reference                |
|---|---------------|----------------|-------|------------------|----------|------------------|----------------|-------------------|----------------|--------------------------|
|   |               |                |       | Unit Price       | Amount   | Unit Price       | Amount         | (JPY)             | (equiv. TND)   |                          |
| Excavation  |               | m <sup>3</sup> | 93    | 0                | 0        | 16.500           | 1,535          | 93,666            | 1,535          |                          |
| Backfilling/Filling                               |               | m <sup>3</sup> | 465   | 0                | 0        | 11.000           | 5,115          | 312,117           | 5,115          |                          |
| Waste Soil Removal                                |               | m <sup>3</sup> | 72    | 0                | 0        | 23.100           | 1,663          | 101,476           | 1,663          |                          |
| Gravel  |               | m <sup>3</sup> | 26    | 0                | 0        | 74.800           | 1,945          | 118,684           | 1,945          |                          |
| Waterproofing                                     |               | m <sup>2</sup> | 272   | 0                | 0        | 42.900           | 11,669         | 712,042           | 11,669         |                          |
| Formwork  |               | m <sup>2</sup> | 962   | 0                | 0        | 62.700           | 60,317         | 3,680,543         | 60,317         |                          |
| Lean Concrete                                     |               | m <sup>3</sup> | 13    | 0                | 0        | 440.000          | 5,720          | 349,034           | 5,720          |                          |
| Reinforced Concrete                               |               | m <sup>3</sup> | 285   | 0                | 0        | 935.000          | 266,475        | 16,260,305        | 266,475        |                          |
| Reinforcement Bar                                 |               | ton            | 28.5  | 0                | 0        | 1320.000         | 37,620         | 2,295,572         | 37,620         | 100kg/m3                 |
| Scaffolding                                       |               | m <sup>2</sup> | 342   | 0                | 0        | 107.800          | 36,868         | 2,249,685         | 36,868         |                          |
| Other Miscellaneous Works                         |               | Ls             | 1     |                  | 0        |                  | 42,893         | 2,617,313         | 42,893         | Sum of above items x 10% |
| Above quantities includes those for Valve Chamber |               |                |       |                  |          |                  |                |                   |                |                          |
|   |               |                |       |                  |          |                  |                |                   |                |                          |
| Total   |               |                |       |                  | 0        |                  | 471,820        |                   |                |                          |
| <b>Total Cost (Rounded)</b>                       | <b>to L5</b>  |                |       |                  | <b>0</b> |                  | <b>472,000</b> | <b>28,801,000</b> | <b>472,000</b> | <b>L5-4</b>              |
|   | FCP:LCP       |                |       |                  | 0%       |                  | 100%           |                   |                |                          |

10.5-48

**L5-5 Mixing Chamber (Sidi Salah EH)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items   | Specification | Unit           | Qt'ty | FC Portion (JPY) |          | LC Portion (TND) |                | Total             |                | Reference                |
|---|---------------|----------------|-------|------------------|----------|------------------|----------------|-------------------|----------------|--------------------------|
|   |               |                |       | Unit Price       | Amount   | Unit Price       | Amount         | (JPY)             | (equiv. TND)   |                          |
| Excavation  |               | m <sup>3</sup> | 248   | 0                | 0        | 16.500           | 4,092          | 249,694           | 4,092          |                          |
| Backfilling/Filling                               |               | m <sup>3</sup> | 48    | 0                | 0        | 11.000           | 528            | 32,219            | 528            |                          |
| Waste Soil Removal                                |               | m <sup>3</sup> | 200   | 0                | 0        | 23.100           | 4,620          | 281,912           | 4,620          |                          |
| Gravel  |               | m <sup>3</sup> | 19    | 0                | 0        | 74.800           | 1,421          | 86,709            | 1,421          |                          |
| Waterproofing                                     |               | m <sup>2</sup> | 196   | 0                | 0        | 42.900           | 8,408          | 513,056           | 8,408          |                          |
| Formwork  |               | m <sup>2</sup> | 754   | 0                | 0        | 62.700           | 47,276         | 2,884,782         | 47,276         |                          |
| Lean Concrete                                     |               | m <sup>3</sup> | 10    | 0                | 0        | 440.000          | 4,400          | 268,488           | 4,400          |                          |
| Reinforced Concrete                               |               | m <sup>3</sup> | 178   | 0                | 0        | 935.000          | 166,430        | 10,155,559        | 166,430        |                          |
| Reinforcement Bar                                 |               | t              | 18    | 0                | 0        | 1320.000         | 23,496         | 1,433,726         | 23,496         | 100kg/m3                 |
| Scaffolding                                       |               | m <sup>2</sup> | 275   | 0                | 0        | 107.800          | 29,645         | 1,808,938         | 29,645         |                          |
| Other Miscellaneous Works                         | incl. Rebar   | Ls             | 1     |                  | 0        |                  | 29,032         | 1,771,508         | 29,032         | Sum of above items x 10% |
| Above quantities includes those for Valve Chamber |               |                |       |                  |          |                  |                |                   |                |                          |
|   |               |                |       |                  |          |                  |                |                   |                |                          |
| Total   |               |                |       |                  | 0        |                  | 319,348        |                   |                |                          |
| <b>Total Cost (Rounded)</b>                       | <b>to L5</b>  |                |       |                  | <b>0</b> |                  | <b>319,000</b> | <b>19,465,000</b> | <b>319,000</b> | <b>L5-5</b>              |
|   | FCP:LCP       |                |       |                  | 0%       |                  | 100%           |                   |                |                          |

10.5-49

**L5-6 Distribution Reservoir (Bou Merra, V=5,000m3)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                          | Specification | Unit           | Qty   | FC Portion (JPY) |          | LC Portion (TND) |                  | Total              |                  | Reference                    |
|--------------------------------|---------------|----------------|-------|------------------|----------|------------------|------------------|--------------------|------------------|------------------------------|
|                                |               |                |       | Unit Price       | Amount   | Unit Price       | Amount           | (JPY)              | (equiv. TND)     |                              |
| Pile Driving Work              |               | m              | 0     | 0                | 0        | 110.000          | 0                | 0                  | 0                |                              |
| Pile Head Treatment            |               | pcs            | 0     | 0                | 0        | 6.600            | 0                | 0                  | 0                |                              |
| Excavation                     |               | m <sup>3</sup> | 2,036 | 0                | 0        | 16.500           | 33,594           | 2,049,906          | 33,594           |                              |
| Backfilling                    |               | m <sup>3</sup> | 428   | 0                | 0        | 11.000           | 4,708            | 287,282            | 4,708            |                              |
| Surplus Soil Transport         |               | m <sup>3</sup> | 1,608 | 0                | 0        | 23.100           | 37,145           | 2,266,576          | 37,145           |                              |
| Gravel                         |               | m <sup>3</sup> | 241   | 0                | 0        | 74.800           | 18,027           | 1,099,995          | 18,027           |                              |
| Concrete                       |               | m <sup>3</sup> | 161   | 0                | 0        | 440.000          | 70,840           | 4,322,657          | 70,840           | structure                    |
| Reinforced Concrete            |               | m <sup>3</sup> | 930   | 0                | 0        | 935.000          | 869,550          | 53,059,941         | 869,550          | structure                    |
| Formwork                       |               | m <sup>2</sup> | 3,500 | 0                | 0        | 62.700           | 219,450          | 13,390,839         | 219,450          | structure                    |
| Rebar Fabrication and Assembly |               | t              | 158   | 0                | 0        | 1320.000         | 208,692          | 12,734,386         | 208,692          | Rebar/Concrete<br>= 170kg/m3 |
| Waterproofing                  |               | m <sup>2</sup> | 1,500 | 0                | 0        | 42.900           | 64,350           | 3,926,637          | 64,350           |                              |
| Scaffolding                    |               | m <sup>2</sup> | 200   | 0                | 0        | 107.800          | 21,560           | 1,315,591          | 21,560           |                              |
| Other Miscellaneous Works      |               | Ls             | 1     |                  |          |                  | 342,133          | 20,876,956         | 342,133          | Structure x 25%              |
|                                |               |                |       |                  |          |                  |                  |                    |                  |                              |
| Total                          |               |                |       |                  | 0        |                  | 1,890,049        |                    |                  |                              |
| <b>Total Cost (Rounded)</b>    | <b>to L5</b>  |                |       |                  | <b>0</b> |                  | <b>1,890,000</b> | <b>115,328,000</b> | <b>1,890,000</b> | <b>L5-6</b>                  |
|                                | FCP:LCP       |                |       |                  | 0%       |                  | 100%             |                    |                  |                              |

10.5-50

**Lot 6 Pump Facilities Construction (ICB)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                       | Specification | Unit | Qty | FC Portion (JPY) |                      | LC Portion (TND) |                   | Total                |                   | Reference |
|-----------------------------|---------------|------|-----|------------------|----------------------|------------------|-------------------|----------------------|-------------------|-----------|
|                             |               |      |     | Unit Price       | Amount               | Unit Price       | Amount            | (JPY)                | (equiv. TND)      |           |
| PK11 (for PK10 & Bou Merra) |               | Ls   | 1   |                  | 789,808,000          |                  | 6,059,000         | 1,159,528,180        | 19,002,428        | L6-1      |
| PK10 (for PK14)             |               | Ls   | 1   |                  | 469,333,000          |                  | 4,543,000         | 746,546,860          | 12,234,462        | L6-2      |
| Pk14 (for Sidi Salah EH)    |               | Ls   | 1   |                  | 306,074,000          |                  | 3,167,000         | 499,324,340          | 8,182,962         | L6-3      |
|                             |               |      |     |                  |                      |                  |                   |                      |                   |           |
|                             |               |      |     |                  |                      |                  |                   |                      |                   |           |
|                             |               |      |     |                  |                      |                  |                   |                      |                   |           |
|                             |               |      |     |                  |                      |                  |                   |                      |                   |           |
|                             |               |      |     |                  |                      |                  |                   |                      |                   |           |
|                             |               |      |     |                  |                      |                  |                   |                      |                   |           |
|                             |               |      |     |                  |                      |                  |                   |                      |                   |           |
|                             |               |      |     |                  |                      |                  |                   |                      |                   |           |
|                             |               |      |     |                  |                      |                  |                   |                      |                   |           |
|                             |               |      |     |                  |                      |                  |                   |                      |                   |           |
|                             |               |      |     |                  |                      |                  |                   |                      |                   |           |
| <b>Total</b>                |               |      |     |                  | 1,565,215,000        |                  | 13,769,000        |                      |                   |           |
| <b>Total Cost (Rounded)</b> | <b>to T1</b>  |      |     |                  | <b>1,565,215,000</b> |                  | <b>13,769,000</b> | <b>2,405,399,000</b> | <b>39,420,000</b> | <b>L6</b> |
|                             | FCP:LCP       |      |     |                  | 65%                  |                  | 35%               |                      |                   |           |

**L6-1 Pumping Facilities (PK11)**

Exchange Rate: 1.00US\$= 119.60JPY      1.000TND= 61.02JPY

| Items                               | Specification | Unit | Qty | FC Portion (JPY) |                    | LC Portion (TND) |                  | Total                |                   | Reference   |
|-------------------------------------|---------------|------|-----|------------------|--------------------|------------------|------------------|----------------------|-------------------|-------------|
|                                     |               |      |     | Unit Price       | Amount             | Unit Price       | Amount           | (JPY)                | (equiv. TND)      |             |
| Pumping Station                     |               | Ls   | 1   |                  | 0                  |                  | 3,070,000        | 187,331,400          | 3,070,000         | L6-1-1      |
| Sub-Station                         |               | Ls   | 1   |                  | 0                  |                  | 706,000          | 43,080,120           | 706,000           | L6-1-2      |
| Mechanical Work (incl. Air Chamber) |               | Ls   | 1   |                  | 423,054,000        |                  | 1,223,000        | 497,681,460          | 8,156,038         | L6-1-3      |
| Electrical Work                     |               | Ls   | 1   |                  | 366,754,000        |                  | 1,060,000        | 431,435,200          | 7,070,390         | L6-1-4      |
|                                     |               |      |     |                  |                    |                  |                  |                      |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                      |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                      |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                      |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                      |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                      |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                      |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                      |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                      |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                      |                   |             |
| Total                               |               |      |     |                  | 789,808,000        |                  | 6,059,000        |                      |                   |             |
| <b>Total Cost (Rounded)</b>         | <b>to L6</b>  |      |     |                  | <b>789,808,000</b> |                  | <b>6,059,000</b> | <b>1,159,528,000</b> | <b>19,002,000</b> | <b>L6-1</b> |
|                                     | FCP:LCP       |      |     |                  | 68%                |                  | 32%              |                      |                   |             |

10.5-52

**L6-1-1 Pump Station (PK11)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                      | Specification  | Unit           | Qty   | FC Portion (JPY) |          | LC Portion (TND) |                  | Total              |                  | Reference                |
|----------------------------|----------------|----------------|-------|------------------|----------|------------------|------------------|--------------------|------------------|--------------------------|
|                            |                |                |       | Unit Price       | Amount   | Unit Price       | Amount           | (JPY)              | (equiv. TND)     |                          |
| Excavation                 |                | m <sup>3</sup> | 5,928 | 0                | 0        | 16.500           | 97,812           | 5,968,488          | 97,812           |                          |
| Backfilling/Filling        |                | m <sup>3</sup> | 2,862 | 0                | 0        | 11.000           | 31,482           | 1,921,032          | 31,482           |                          |
| Waste Soil Removal         |                | m <sup>3</sup> | 3,066 | 0                | 0        | 23.100           | 70,825           | 4,321,742          | 70,825           |                          |
| Gravel                     |                | m <sup>3</sup> | 180   | 0                | 0        | 74.800           | 13,464           | 821,573            | 13,464           |                          |
| Waterproofing              |                | m <sup>2</sup> | 726   | 0                | 0        | 42.900           | 31,145           | 1,900,468          | 31,145           |                          |
| Formwork                   |                | m <sup>2</sup> | 5,702 | 0                | 0        | 62.700           | 357,515          | 21,815,565         | 357,515          |                          |
| Lean Concrete              |                | m <sup>3</sup> | 266   | 0                | 0        | 440.000          | 117,040          | 7,141,781          | 117,040          |                          |
| Reinforced Concrete        |                | m <sup>3</sup> | 1,665 | 0                | 0        | 935.000          | 1,556,775        | 94,994,411         | 1,556,775        |                          |
| Scaffolding                |                | m <sup>2</sup> | 3,540 | 0                | 0        | 107.800          | 381,612          | 23,285,964         | 381,612          |                          |
| Other Miscellaneous Works  | incl. Rebar    | Ls             | 1     |                  | 0        |                  | 265,767          | 16,217,102         | 265,767          | Sum of above items x 10% |
| Engineering Cost           |                | Ls             | 1     |                  | 0        |                  | 146,172          | 8,919,406          | 146,172          | Sum of other items x 5%  |
|                            |                |                |       |                  |          |                  |                  |                    |                  |                          |
|                            |                |                |       |                  |          |                  |                  |                    |                  |                          |
| <b>Total</b>               |                |                |       |                  | 0        |                  | 3,069,609        |                    |                  |                          |
| <b>Sub-Total (rounded)</b> | <b>to L6-1</b> |                |       |                  | <b>0</b> |                  | <b>3,070,000</b> | <b>187,331,000</b> | <b>3,070,000</b> | <b>L6-1-1</b>            |
|                            | FCP:LCP        |                |       |                  | 0%       |                  | 100%             |                    |                  |                          |

10.5-53



**L6-1-2 Sub-station (PK11)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                       | Specification  | Unit           | Qty   | FC Portion (JPY) |          | LC Portion (TND) |                | Total             |                | Reference                |
|-----------------------------|----------------|----------------|-------|------------------|----------|------------------|----------------|-------------------|----------------|--------------------------|
|                             |                |                |       | Unit Price       | Amount   | Unit Price       | Amount         | (JPY)             | (equiv. TND)   |                          |
| Excavation                  |                | m <sup>3</sup> | 248   | 0                | 0        | 16.500           | 4,092          | 249,694           | 4,092          |                          |
| Backfilling/Filling         |                | m <sup>3</sup> | 57    | 0                | 0        | 11.000           | 627            | 38,260            | 627            |                          |
| Waste Soil Removal          |                | m <sup>3</sup> | 191   | 0                | 0        | 23.100           | 4,412          | 269,220           | 4,412          |                          |
| Gravel                      |                | m <sup>3</sup> | 66    | 0                | 0        | 74.800           | 4,937          | 301,256           | 4,937          |                          |
| Waterproofing               |                | m <sup>2</sup> | 366   | 0                | 0        | 42.900           | 15,701         | 958,075           | 15,701         |                          |
| Formwork                    |                | m <sup>2</sup> | 1,627 | 0                | 0        | 62.700           | 102,013        | 6,224,833         | 102,013        |                          |
| Lean Concrete               |                | m <sup>3</sup> | 121   | 0                | 0        | 440.000          | 53,240         | 3,248,705         | 53,240         |                          |
| Reinforced Concrete         |                | m <sup>3</sup> | 323   | 0                | 0        | 935.000          | 302,005        | 18,428,345        | 302,005        |                          |
| Scaffolding                 |                | m <sup>2</sup> | 1,156 | 0                | 0        | 107.800          | 124,617        | 7,604,129         | 124,617        |                          |
| Other Miscellaneous Works   | incl. Rebar    | Ls             | 1     |                  | 0        |                  | 61,164         | 3,732,252         | 61,164         | Sum of above items x 10% |
| Engineering Cost            |                | Ls             | 1     |                  | 0        |                  | 33,640         | 2,052,738         | 33,640         | Sum of other items x 5%  |
|                             |                |                |       |                  |          |                  |                |                   |                |                          |
|                             |                |                |       |                  |          |                  |                |                   |                |                          |
| Total                       |                |                |       |                  | 0        |                  | 706,449        |                   |                |                          |
| <b>Total Cost (Rounded)</b> | <b>to L6-1</b> |                |       |                  | <b>0</b> |                  | <b>706,000</b> | <b>43,080,000</b> | <b>706,000</b> | <b>L6-1-2</b>            |
|                             | FCP:LCP        |                |       |                  | 0%       |                  | 100%           |                   |                |                          |

10.5-54

**L6-1-3 Mechanical Facility for PK11 Pump Station**

Foreign Portion: 85%, Local Portion: 15% (Installation)

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items   | Specification                          | Unit       | Qt'ty    | FC Portion (JPY) |                    | LC Portion (TND) |                | Total              |                  | Reference       |
|---|--|------------|----------|------------------|--------------------|------------------|----------------|--------------------|------------------|-----------------|
|   |  |            |          | Unit Price       | Amount             | Unit Price       | Amount         | (JPY)              | (equiv. TND)     |                 |
| <b>Intermediate transmission pump station</b> |  |            |          |                  |                    |                  |                |                    |                  |                 |
| <b>PK11-1</b>                                 | PK11-B,Merra                           |            |          |                  |                    |                  |                |                    |                  |                 |
| Transmission Pump                             | 6.7m3/min x 61m                        | set        | 3        | 37,095,000       | 111,285,000        | 107,000          | 321,000        | 130,872,000        | 2,144,739        |                 |
| Inlet Valve                                   | Dia. 300mm                             | set        | 3        | 910,000          | 2,730,000          | 3,000            | 9,000          | 3,279,000          | 53,736           |                 |
| Check Valve                                   | Dia. 200 mm                            | set        | 3        | 224,000          | 672,000            | 1,000            | 3,000          | 855,000            | 14,012           |                 |
| Discharge Valve                               | Dia. 200 mm                            | set        | 3        | 2,142,000        | 6,426,000          | 6,000            | 18,000         | 7,524,000          | 123,304          | Motorized       |
| Maintenance Valve                             | Dia. 200 mm                            | set        | 3        | 570,000          | 1,710,000          | 1,600            | 4,800          | 2,003,000          | 32,825           |                 |
| Maintenance Valve                             | Dia. 400 mm                            | set        | 2        | 1,420,000        | 2,840,000          | 4,000            | 8,000          | 3,328,000          | 54,539           | Butterfly Valve |
| Pipes   |  | lot        | 1        | 18,849,000       | 18,849,000         | 55,000           | 55,000         | 22,205,000         | 363,897          |                 |
| <b>sub-total</b>                              |  |            |          |                  | <b>144,512,000</b> |                  | <b>418,800</b> | <b>170,066,000</b> | <b>2,787,053</b> |                 |
| <b>Air Chamber (Mechanical)</b>               | <b>approx. 3m3<br/>( φ 1.5 x 1.7m)</b> | <b>lot</b> | <b>1</b> |                  | <b>3,213,000</b>   |                  | <b>9,292</b>   | <b>3,780,000</b>   | <b>61,947</b>    |                 |

10.5-55

**L6-1-3 Mechanical Facility for PK11 Pump Station**

Foreign Portion: 85%, Local Portion: 15% (Installation)

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                  | Specification             | Unit | Qt'ty | FC Portion (JPY) |                    | LC Portion (TND) |                  | Total              |                  | Reference       |
|------------------------|---------------------------|------|-------|------------------|--------------------|------------------|------------------|--------------------|------------------|-----------------|
|                        |                           |      |       | Unit Price       | Amount             | Unit Price       | Amount           | (JPY)              | (equiv. TND)     |                 |
| <b>PK11-2</b>          | PK11-PK10                 |      |       |                  |                    |                  |                  |                    |                  |                 |
| Transmission Pump      | 37.1m3/min x 38m          | set  | 4     | 46,369,000       | 185,476,000        | 134,000          | 536,000          | 218,183,000        | 3,575,598        |                 |
| Inlet Valve            | Dia. 500 mm               | set  | 4     | 1,845,000        | 7,380,000          | 5,000            | 20,000           | 8,600,000          | 140,937          |                 |
| Check Valve            | Dia. 500 mm               | set  | 4     | 2,769,000        | 11,076,000         | 8,000            | 32,000           | 13,029,000         | 213,520          |                 |
| Discharge Valve        | Dia. 500 mm               | set  | 4     | 3,668,000        | 14,672,000         | 11,000           | 44,000           | 17,357,000         | 284,448          | Motorized       |
| Maintenance Valve      | Dia. 500 mm               | set  | 4     | 1,845,000        | 7,380,000          | 5,000            | 20,000           | 8,600,000          | 140,937          |                 |
| Maintenance Valve      | Dia. 1000 mm              | set  | 2     | 5,900,000        | 11,800,000         | 17,000           | 34,000           | 13,875,000         | 227,384          | Butterfly Valve |
| Pump Lifting Equipment | Suspension crane : 3.2ton | set  | 1     | 1,632,000        | 1,632,000          | 5,000            | 5,000            | 1,937,000          | 31,744           |                 |
| Pipes                  |                           | lot  | 1     | 35,913,000       | 35,913,000         | 104,000          | 104,000          | 42,259,000         | 692,543          |                 |
| <b>sub-total</b>       |                           |      |       |                  | <b>275,329,000</b> |                  | <b>795,000</b>   | <b>323,840,000</b> | <b>5,307,112</b> |                 |
| Total                  |                           |      |       |                  | 423,054,000        |                  | 1,223,092        |                    |                  |                 |
| <b>Total (Rounded)</b> | <b>to L6-1</b>            |      |       |                  | <b>423,054,000</b> |                  | <b>1,223,000</b> | <b>497,681,000</b> | <b>8,156,000</b> | <b>L6-1-3</b>   |
|                        | FCP:LCP                   |      |       |                  | 85%                |                  | 15%              |                    |                  |                 |

10.5-56

**L6-1-4 Electrical Facility for PK11 Pump Station**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                                   | Specification   | Unit      | Qt'ty    | FC Portion (JPY) |                   | LC Portion (TND) |                | Total             |                  | Reference  |
|---|---|-----------|----------|------------------|-------------------|------------------|----------------|-------------------|------------------|--|
|   |   |           |          | Unit Price       | Amount            | Unit Price       | Amount         | (JPY)             | (equiv. TND)     |  |
| <b>PK-11</b>                            |   |           |          |                  |                   |                  |                |                   |                  |  |
| <b>30kV Switchgear</b>                  |   | <b>Ls</b> | <b>1</b> |                  | <b>32,640,000</b> |                  | <b>94,396</b>  | <b>38,400,000</b> | <b>629,302</b>   | <b>a.</b>  |
| 30kV DS, LA Panel                       |   | set       | 1        | 4,250,000        | 4,250,000         | 12,291           | 12,291         | 5,000,000         | 81,940           | DS: Disconnecting Switch<br>LA: Lightning Arrester |
| 30kV VT Panel                           |   | set       | 1        | 4,250,000        | 4,250,000         | 12,291           | 12,291         | 5,000,000         | 81,940           | VT: Voltage Transformer                            |
| 30kV VCB Panel                          |   | set       | 2        | 7,225,000        | 14,450,000        | 20,895           | 41,790         | 17,000,000        | 278,597          | VCB:<br>Vacuum Circuit Breaker                     |
| 30kV/400V Transformer                   | oil type 2MVA   | set       | 1        | 9,690,000        | 9,690,000         | 28,024           | 28,024         | 11,400,000        | 186,824          |  |
|   |   |           |          |                  |                   |                  |                |                   |                  |  |
| <b>LV Switchgear</b>                    |   | <b>Ls</b> | <b>1</b> |                  | <b>71,527,500</b> |                  | <b>206,857</b> | <b>84,150,000</b> | <b>1,379,056</b> | <b>b.</b>  |
| LV Main Switchgear                      | 5 units   | set       | 1        | 11,050,000       | 11,050,000        | 31,957           | 31,957         | 13,000,000        | 213,045          | LV: Low Voltage                                    |
| Transmission Pump for Bou Merra         | 400V VFD 132kW  | set       | 3        | 3,060,000        | 9,180,000         | 8,850            | 26,550         | 10,800,000        | 176,991          | VFD:<br>Variable Frequency Drive                   |
| Transmission Pump for PK-10             | 400V VFD 355kW  | set       | 4        | 7,820,000        | 31,280,000        | 22,616           | 90,464         | 36,800,000        | 603,081          |  |
| MCC for Transmission-1                  | 6 units   | set       | 1        | 17,467,500       | 17,467,500        | 50,516           | 50,516         | 20,550,000        | 336,775          | MCC:<br>Motor Control Centre                       |
| Local Panel                             |   | set       | 10       | 255,000          | 2,550,000         | 737              | 7,370          | 3,000,000         | 49,164           |  |
|   |   |           |          |                  |                   |                  |                |                   |                  |  |
| <b>Instrumentation &amp; Monitoring</b> |   | <b>Ls</b> | <b>1</b> |                  | <b>67,745,000</b> |                  | <b>195,922</b> | <b>79,700,000</b> | <b>1,306,129</b> | <b>c.</b>  |
| Transmission Flow                       | electro-magnetic 1400mm                               | set       | 1        | 7,820,000        | 7,820,000         | 22,616           | 22,616         | 9,200,000         | 150,770          |  |
| Transmission Flow                       | electro-magnetic 1000mm                               | set       | 1        | 5,270,000        | 5,270,000         | 15,241           | 15,241         | 6,200,000         | 101,606          |  |
| Transmission Flow                       | electro-magnetic 400mm                                | set       | 1        | 2,125,000        | 2,125,000         | 6,146            | 6,146          | 2,500,000         | 40,970           |  |
| Water Level                             | Ultrasonic  | set       | 6        | 680,000          | 4,080,000         | 1,967            | 11,802         | 4,800,000         | 78,663           |  |
| Water Quality                           | Turbidity, pH, Res. Chlorine<br>Electric Conductivity | set       | 9        | 1,275,000        | 11,475,000        | 3,687            | 33,183         | 13,500,000        | 221,239          | Inflow: TDS x 5, Outflow:                          |
| Instrumentation Panel                   |   | set       | 1        | 2,550,000        | 2,550,000         | 7,375            | 7,375          | 3,000,000         | 49,164           |  |
| PLC Panel                               |   | lot       | 2        | 6,375,000        | 12,750,000        | 18,437           | 36,874         | 15,000,000        | 245,821          | PLC:<br>Programmable Logic Controller              |
| Telemetry System                        | Plant-PK11, PK11-PK10,<br>PK11-Bou Merra              | lot       | 3        | 6,800,000        | 20,400,000        | 19,666           | 58,998         | 24,000,000        | 393,314          |  |

10.5-57

**L6-1-4 Electrical Facility for PK11 Pump Station**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                             | Specification         | Unit       | Qt'ty    | FC Portion (JPY)   |                    | LC Portion (TND) |                  | Total              |                  | Reference                           |
|-----------------------------------|-----------------------|------------|----------|--------------------|--------------------|------------------|------------------|--------------------|------------------|-------------------------------------|
|                                   |                       |            |          | Unit Price         | Amount             | Unit Price       | Amount           | (JPY)              | (equiv. TND)     |                                     |
| <i>UPS</i>                        | <i>10kVA</i>          | <i>set</i> | <i>1</i> | <i>1,275,000</i>   | <i>1,275,000</i>   | <i>3,687</i>     | <i>3,687</i>     | <i>1,500,000</i>   | <i>24,582</i>    | UPS:<br>Uninterruptive Power Supply |
| <b>Emergency Power Facilities</b> |                       | <b>Ls</b>  | <b>1</b> |                    | <b>161,500,000</b> |                  | <b>467,060</b>   | <b>190,000,000</b> | <b>3,113,733</b> | <b>d.</b>                           |
| <i>Stand-by Generator</i>         | <i>Diesel 2500kVA</i> | <i>set</i> | <i>1</i> | <i>161,500,000</i> | <i>161,500,000</i> | <i>467,060</i>   | <i>467,060</i>   | <i>190,000,000</i> | <i>3,113,733</i> |                                     |
| <b>Other Miscellaneous Works</b>  |                       | <b>Ls</b>  | <b>1</b> |                    | <b>33,341,000</b>  |                  | <b>96,000</b>    | <b>39,199,000</b>  | <b>642,396</b>   | Sum of (a~d) x 10%                  |
|                                   |                       |            |          |                    |                    |                  |                  |                    |                  |                                     |
|                                   |                       |            |          |                    |                    |                  |                  |                    |                  |                                     |
|                                   |                       |            |          |                    |                    |                  |                  |                    |                  |                                     |
|                                   |                       |            |          |                    |                    |                  |                  |                    |                  |                                     |
|                                   |                       |            |          |                    |                    |                  |                  |                    |                  |                                     |
|                                   |                       |            |          |                    |                    |                  |                  |                    |                  |                                     |
|                                   |                       |            |          |                    |                    |                  |                  |                    |                  |                                     |
|                                   |                       |            |          |                    |                    |                  |                  |                    |                  |                                     |
| <b>Total</b>                      |                       |            |          |                    | 366,753,500        |                  | 1,060,235        |                    |                  |                                     |
| <b>Total (Rounded)</b>            | <b>to L6-1</b>        |            |          |                    | <b>366,754,000</b> |                  | <b>1,060,000</b> | <b>431,435,000</b> | <b>7,070,000</b> | <b>L6-1-4</b>                       |
|                                   | FCP:LCP               |            |          |                    | 85%                |                  | 15%              |                    |                  |                                     |

10.5-58

**L6-2 Pumping Facilities (PK10)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                               | Specification | Unit | Qty | FC Portion (JPY) |                    | LC Portion (TND) |                  | Total              |                   | Reference   |
|-------------------------------------|---------------|------|-----|------------------|--------------------|------------------|------------------|--------------------|-------------------|-------------|
|                                     |               |      |     | Unit Price       | Amount             | Unit Price       | Amount           | (JPY)              | (equiv. TND)      |             |
| Pumping Station                     |               | Ls   | 1   |                  | 0                  |                  | 1,580,000        | 96,411,600         | 1,580,000         | L6-2-1      |
| Sub-Station                         |               | Ls   | 1   |                  | 0                  |                  | 706,000          | 43,080,120         | 706,000           | L6-2-2      |
| Mechanical Work (incl. Air Chamber) |               | Ls   | 1   |                  | 228,523,000        |                  | 663,000          | 268,979,000        | 4,408,047         | L6-2-3      |
| Electrical Work                     |               | Ls   | 1   |                  | 240,810,000        |                  | 1,594,000        | 338,075,880        | 5,540,411         | L6-2-4      |
|                                     |               |      |     |                  |                    |                  |                  |                    |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                   |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                   |             |
| Total                               |               |      |     |                  | 469,333,000        |                  | 4,543,000        |                    |                   |             |
| <b>Total Cost (Rounded)</b>         | <b>to L6</b>  |      |     |                  | <b>469,333,000</b> |                  | <b>4,543,000</b> | <b>746,547,000</b> | <b>12,234,000</b> | <b>L6-2</b> |
|                                     | FCP:LCP       |      |     |                  | 63%                |                  | 37%              |                    |                   |             |

10.5-59

**L6-2-1 Pump Station (PK10)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                      | Specification  | Unit           | Qty   | FC Portion (JPY) |          | LC Portion (TND) |                  | Total             |                  | Reference                |
|----------------------------|----------------|----------------|-------|------------------|----------|------------------|------------------|-------------------|------------------|--------------------------|
|                            |                |                |       | Unit Price       | Amount   | Unit Price       | Amount           | (JPY)             | (equiv. TND)     |                          |
| Excavation                 |                | m <sup>3</sup> | 2,874 | 0                | 0        | 16.500           | 47,421           | 2,893,629         | 47,421           |                          |
| Backfilling/Filling        |                | m <sup>3</sup> | 1,477 | 0                | 0        | 11.000           | 16,247           | 991,392           | 16,247           |                          |
| Waste Soil Removal         |                | m <sup>3</sup> | 1,398 | 0                | 0        | 23.100           | 32,294           | 1,970,580         | 32,294           |                          |
| Gravel                     |                | m <sup>3</sup> | 80    | 0                | 0        | 74.800           | 5,984            | 365,144           | 5,984            |                          |
| Waterproofing              |                | m <sup>2</sup> | 462   | 0                | 0        | 42.900           | 19,820           | 1,209,416         | 19,820           |                          |
| Formwork                   |                | m <sup>2</sup> | 3,056 | 0                | 0        | 62.700           | 191,611          | 11,692,103        | 191,611          |                          |
| Lean Concrete              |                | m <sup>3</sup> | 119   | 0                | 0        | 440.000          | 52,360           | 3,195,007         | 52,360           |                          |
| Reinforced Concrete        |                | m <sup>3</sup> | 828   | 0                | 0        | 935.000          | 774,180          | 47,240,464        | 774,180          |                          |
| Scaffolding                |                | m <sup>2</sup> | 2,115 | 0                | 0        | 107.800          | 227,997          | 13,912,377        | 227,997          |                          |
| Other Miscellaneous Works  | incl. Rebar    | Ls             | 1     |                  | 0        |                  | 136,791          | 8,347,011         | 136,791          | Sum of above items x 10% |
| Engineering Cost           |                | Ls             | 1     |                  | 0        |                  | 75,235           | 4,590,856         | 75,235           | Sum of other items x 5%  |
|                            |                |                |       |                  |          |                  |                  |                   |                  |                          |
|                            |                |                |       |                  |          |                  |                  |                   |                  |                          |
| Total                      |                |                |       |                  | 0        |                  | 1,579,941        |                   |                  |                          |
| <b>Sub-Total (rounded)</b> | <b>to L6-2</b> |                |       |                  | <b>0</b> |                  | <b>1,580,000</b> | <b>96,412,000</b> | <b>1,580,000</b> | <b>L6-2-1</b>            |
|                            | FCP:LCP        |                |       |                  | 0%       |                  | 100%             |                   |                  |                          |

10.5-60

**L6-2-2 Sub-station (PK10)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                       | Specification  | Unit           | Qty   | FC Portion (JPY) |          | LC Portion (TND) |                | Total             |                | Reference               |
|-----------------------------|----------------|----------------|-------|------------------|----------|------------------|----------------|-------------------|----------------|-------------------------|
|                             |                |                |       | Unit Price       | Amount   | Unit Price       | Amount         | (JPY)             | (equiv. TND)   |                         |
| Excavation                  |                | m <sup>3</sup> | 248   | 0                | 0        | 16.500           | 4,092          | 249,694           | 4,092          |                         |
| Backfilling/Filling         |                | m <sup>3</sup> | 57    | 0                | 0        | 11.000           | 627            | 38,260            | 627            |                         |
| Waste Soil Removal          |                | m <sup>3</sup> | 191   | 0                | 0        | 23.100           | 4,412          | 269,220           | 4,412          |                         |
| Gravel                      |                | m <sup>3</sup> | 66    | 0                | 0        | 74.800           | 4,937          | 301,256           | 4,937          |                         |
| Waterproofing               |                | m <sup>2</sup> | 366   | 0                | 0        | 42.900           | 15,701         | 958,075           | 15,701         |                         |
| Formwork                    |                | m <sup>2</sup> | 1,627 | 0                | 0        | 62.700           | 102,013        | 6,224,833         | 102,013        |                         |
| Lean Concrete               |                | m <sup>3</sup> | 121   | 0                | 0        | 440.000          | 53,240         | 3,248,705         | 53,240         |                         |
| Reinforced Concrete         |                | m <sup>3</sup> | 323   | 0                | 0        | 935.000          | 302,005        | 18,428,345        | 302,005        |                         |
| Scaffolding                 |                | m <sup>2</sup> | 1,156 | 0                | 0        | 107.800          | 124,617        | 7,604,129         | 124,617        |                         |
| Other Miscellaneous Works   | incl. Rebar    | Ls             | 1     |                  | 0        |                  | 61,164         | 3,732,252         | 61,164         | Sum of above items 10%  |
| Engineering Cost            |                | Ls             | 1     |                  | 0        |                  | 33,640         | 2,052,738         | 33,640         | Sum of other items x 5% |
|                             |                |                |       |                  |          |                  |                |                   |                |                         |
|                             |                |                |       |                  |          |                  |                |                   |                |                         |
| Total                       |                |                |       |                  | 0        |                  | 706,449        |                   |                |                         |
| <b>Total Cost (Rounded)</b> | <b>to L6-2</b> |                |       |                  | <b>0</b> |                  | <b>706,000</b> | <b>43,080,000</b> | <b>706,000</b> | <b>L6-2-2</b>           |
|                             | FCP:LCP        |                |       |                  | 0%       |                  | 100%           |                   |                |                         |

10.5-61



**L6-2-3 Mechanical Facility for PK10 Pump Station** Foreign Portion: 85%, Local Portion: 15% (Installation) Exchange Rate: 1.00US\$= 119.60JPY .000TND= 61.02JPY

| Items   | Specification             | Unit | Qt'ly | FC Portion (JPY) |                    | LC Portion (TND) |                | Total              |                  | Reference       |
|---|---------------------------|------|-------|------------------|--------------------|------------------|----------------|--------------------|------------------|-----------------|
|   |                           |      |       | Unit Price       | Amount             | Unit Price       | Amount         | (JPY)              | (equiv. TND)     |                 |
| <b>Intermediate transmission pump station</b> |                           |      |       |                  |                    |                  |                |                    |                  |                 |
| <b>PK10</b>                                   | PK10 - PK14               |      |       |                  |                    |                  |                |                    |                  |                 |
| Transmission Pump                             | 32.9m3/min x 53m          | set  | 3     | 52,165,000       | 156,495,000        | 151,000          | 453,000        | 184,137,000        | 3,017,650        |                 |
| Inlet Valve                                   | Dia. 450mm                | set  | 3     | 1,704,000        | 5,112,000          | 5,000            | 15,000         | 6,027,000          | 98,771           |                 |
| Check Valve                                   | Dia. 300mm                | set  | 3     | 347,000          | 1,041,000          | 1,000            | 3,000          | 1,224,000          | 20,059           |                 |
| Discharge Valve                               | Dia. 300mm                | set  | 3     | 2,380,000        | 7,140,000          | 7,000            | 21,000         | 8,421,000          | 138,004          | Motorized       |
| Maintenance Valve                             | Dia. 300mm                | set  | 3     | 612,000          | 1,836,000          | 2,000            | 6,000          | 2,202,000          | 36,087           |                 |
| Maintenance Valve                             | Dia. 600 mm               | set  | 2     | 2,367,000        | 4,734,000          | 7,000            | 14,000         | 5,588,000          | 91,577           | Butterfly Valve |
| Maintenance Valve                             | Dia. 800 mm               | set  | 1     | 3,551,000        | 3,551,000          | 10,000           | 10,000         | 4,161,000          | 68,191           | Butterfly Valve |
| Pump Lifting Equipment                        | Suspension crane : 5.0ton | set  | 1     | 19,270,000       | 19,270,000         | 56,000           | 56,000         | 22,687,000         | 371,796          |                 |
| Pipes   |                           | lot  | 1     | 29,344,000       | 29,344,000         | 85,000           | 85,000         | 34,531,000         | 565,896          |                 |
|   |                           |      |       |                  |                    |                  |                |                    |                  |                 |
|   |                           |      |       |                  |                    |                  |                |                    |                  |                 |
|   |                           |      |       |                  |                    |                  |                |                    |                  |                 |
| Total   |                           |      |       |                  | 228,523,000        |                  | 663,000        |                    |                  |                 |
| <b>Total (Rounded)</b>                        | <b>to L6-2</b>            |      |       |                  | <b>228,523,000</b> |                  | <b>663,000</b> | <b>268,979,000</b> | <b>4,408,000</b> | <b>L6-2-3</b>   |
|   | FCP:LCP                   |      |       |                  | 85%                |                  | 15%            |                    |                  |                 |

10.5-62

**L6-2-4 Electrical Facility for PK10 Pump Station**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                                   | Specification   | Unit      | Qt'y     | FC Portion (JPY) |                   | LC Portion (TND) |                | Total              |                  | Reference  |
|---|---|-----------|----------|------------------|-------------------|------------------|----------------|--------------------|------------------|--|
|   |   |           |          | Unit Price       | Amount            | Unit Price       | Amount         | (JPY)              | (equiv. TND)     |  |
| <b>PK-10</b>                            |   |           |          |                  |                   |                  |                |                    |                  |  |
| <b>30kV Switchgear</b>                  |   | <b>Ls</b> | <b>1</b> |                  | <b>32,640,000</b> |                  | <b>94,396</b>  | <b>38,400,000</b>  | <b>629,302</b>   | <b>a.</b>  |
| 30kV DS, LA Panel                       |   | set       | 1        | 4,250,000        | 4,250,000         | 12,291           | 12,291         | 5,000,000          | 81,940           | DS: Disconnecting Switch<br>LA: Lightning Arrester |
| 30kV VT Panel                           |   | set       | 1        | 4,250,000        | 4,250,000         | 12,291           | 12,291         | 5,000,000          | 81,940           | VT:<br>Voltage Transformer                         |
| 30kV VCB Panel                          |   | set       | 2        | 7,225,000        | 14,450,000        | 20,895           | 41,790         | 17,000,000         | 278,597          | VCB:<br>Vacuum Circuit Breaker                     |
| 30kV/400V Transformer                   | oil type 2MVA   | set       | 1        | 9,690,000        | 9,690,000         | 28,024           | 28,024         | 11,400,000         | 186,824          |  |
|   |   |           |          |                  |                   |                  |                |                    |                  |  |
| <b>LV Switchgear</b>                    |   | <b>Ls</b> | <b>1</b> |                  | <b>61,412,500</b> |                  | <b>993,975</b> | <b>122,065,000</b> | <b>2,000,410</b> | <b>b.</b>  |
| LV Main Switchgear                      | 5 units   | set       | 1        | 11,050,000       | 11,050,000        | 31,957           | 31,957         | 13,000,000         | 213,045          | LV: Low Voltage                                    |
| Transmission Pump for PK-14             | 400V VFD 450kW  | set       | 3        | 10,455,000       | 31,365,000        | 302,360          | 907,080        | 86,715,000         | 1,421,091        | VFD:<br>Variable Frequency Drive                   |
| MCC for Transmission-1                  | 6 units   | set       | 1        | 17,467,500       | 17,467,500        | 50,516           | 50,516         | 20,550,000         | 336,775          | MCC:<br>Motor Control Centre                       |
| Local Panel                             |   | set       | 6        | 255,000          | 1,530,000         | 737              | 4,422          | 1,800,000          | 29,499           |  |
|   |   |           |          |                  |                   |                  |                |                    |                  |  |
| <b>Instrumentation &amp; Monitoring</b> |   | <b>Ls</b> | <b>1</b> |                  | <b>35,615,000</b> |                  | <b>102,999</b> | <b>41,900,000</b>  | <b>686,660</b>   | <b>c.</b>  |
| Transmission Flow                       | electro-magnetic 1000mm                               | set       | 1        | 5,270,000        | 5,270,000         | 15,241           | 15,241         | 6,200,000          | 101,606          |  |
| Transmission Flow                       | electro-magnetic 800mm                                | set       | 1        | 4,335,000        | 4,335,000         | 12,537           | 12,537         | 5,100,000          | 83,579           |  |
| Water Level                             | Ultrasonic  | set       | 2        | 680,000          | 1,360,000         | 1,967            | 3,934          | 1,600,000          | 26,221           |  |
| Water Quality                           | Turbidity, pH, Res. Chlorine<br>Electric Conductivity | set       | 6        | 1,275,000        | 7,650,000         | 3,687            | 22,122         | 9,000,000          | 147,493          | Inflow: TDS x 2, Outflow: 4                        |
| Instrumentation Panel                   |   | set       | 1        | 2,550,000        | 2,550,000         | 7,375            | 7,375          | 3,000,000          | 49,164           |  |
| PLC Panel                               |   | lot       | 1        | 6,375,000        | 6,375,000         | 18,437           | 18,437         | 7,500,000          | 122,911          | PLC:<br>Programmable Logic                         |
| Telemetry System                        | PK10-PK14   | lot       | 1        | 6,800,000        | 6,800,000         | 19,666           | 19,666         | 8,000,000          | 131,105          |  |
| UPS                                     | 10kVA   | set       | 1        | 1,275,000        | 1,275,000         | 3,687            | 3,687          | 1,500,000          | 24,582           | UPS:<br>Uninterruptive Power Supply                |

**L6-2-4 Electrical Facility for PK10 Pump Station**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                             | Specification  | Unit      | Qt'ty    | FC Portion (JPY) |                    | LC Portion (TND) |                  | Total              |                  | Reference          |
|-----------------------------------|----------------|-----------|----------|------------------|--------------------|------------------|------------------|--------------------|------------------|--------------------|
|                                   |                |           |          | Unit Price       | Amount             | Unit Price       | Amount           | (JPY)              | (equiv. TND)     |                    |
| <b>Emergency Power Facilities</b> |                | <b>Ls</b> | <b>1</b> |                  | <b>89,250,000</b>  |                  | <b>258,112</b>   | <b>105,000,000</b> | <b>1,720,747</b> |                    |
| Stand-by Generator                | Diesel 1250kVA | set       | 1        | 89,250,000       | 89,250,000         | 258,112          | 258,112          | 105,000,000        | 1,720,747        |                    |
| <b>Other Miscellaneous Works</b>  |                | <b>Ls</b> | <b>1</b> |                  | <b>21,892,000</b>  |                  | <b>145,000</b>   | <b>30,740,000</b>  | <b>503,769</b>   | Sum of (a~d) x 10% |
|                                   |                |           |          |                  |                    |                  |                  |                    |                  |                    |
|                                   |                |           |          |                  |                    |                  |                  |                    |                  |                    |
|                                   |                |           |          |                  |                    |                  |                  |                    |                  |                    |
|                                   |                |           |          |                  |                    |                  |                  |                    |                  |                    |
|                                   |                |           |          |                  |                    |                  |                  |                    |                  |                    |
|                                   |                |           |          |                  |                    |                  |                  |                    |                  |                    |
|                                   |                |           |          |                  |                    |                  |                  |                    |                  |                    |
|                                   |                |           |          |                  |                    |                  |                  |                    |                  |                    |
|                                   |                |           |          |                  |                    |                  |                  |                    |                  |                    |
|                                   |                |           |          |                  |                    |                  |                  |                    |                  |                    |
|                                   |                |           |          |                  |                    |                  |                  |                    |                  |                    |
|                                   |                |           |          |                  |                    |                  |                  |                    |                  |                    |
|                                   |                |           |          |                  |                    |                  |                  |                    |                  |                    |
|                                   |                |           |          |                  |                    |                  |                  |                    |                  |                    |
|                                   |                |           |          |                  |                    |                  |                  |                    |                  |                    |
|                                   |                |           |          |                  |                    |                  |                  |                    |                  |                    |
|                                   |                |           |          |                  |                    |                  |                  |                    |                  |                    |
|                                   |                |           |          |                  |                    |                  |                  |                    |                  |                    |
|                                   |                |           |          |                  |                    |                  |                  |                    |                  |                    |
| <b>Total</b>                      |                |           |          |                  | 240,809,500        |                  | 1,594,482        |                    |                  |                    |
| <b>Total (Rounded)</b>            | <b>to L6-2</b> |           |          |                  | <b>240,810,000</b> |                  | <b>1,594,000</b> | <b>338,076,000</b> | <b>5,540,000</b> | <b>L6-2-4</b>      |
|                                   | FCP:LCP        |           |          |                  | 71%                |                  | 29%              |                    |                  |                    |

**L6-3 Pumping Facilities (PK14)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                               | Specification | Unit | Qty | FC Portion (JPY) |                    | LC Portion (TND) |                  | Total              |                  | Reference   |
|-------------------------------------|---------------|------|-----|------------------|--------------------|------------------|------------------|--------------------|------------------|-------------|
|                                     |               |      |     | Unit Price       | Amount             | Unit Price       | Amount           | (JPY)              | (equiv. TND)     |             |
| Pumping Station                     |               | Ls   | 1   |                  | 0                  |                  | 1,580,000        | 96,411,600         | 1,580,000        | L6-3-1      |
| Sub-Station                         |               | Ls   | 1   |                  | 0                  |                  | 706,000          | 43,080,120         | 706,000          | L6-3-2      |
| Mechanical Work (incl. Air Chamber) |               | Ls   | 1   |                  | 106,124,000        |                  | 303,000          | 124,613,060        | 2,042,167        | L6-3-3      |
| Electrical Work                     |               | Ls   | 1   |                  | 199,950,000        |                  | 578,000          | 235,219,560        | 3,854,794        | L6-3-4      |
|                                     |               |      |     |                  |                    |                  |                  |                    |                  |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                  |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                  |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                  |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                  |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                  |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                  |             |
|                                     |               |      |     |                  |                    |                  |                  |                    |                  |             |
| <b>Total</b>                        |               |      |     |                  | 306,074,000        |                  | 3,167,000        |                    |                  |             |
| <b>Total Cost (Rounded)</b>         | <b>to L6</b>  |      |     |                  | <b>306,074,000</b> |                  | <b>3,167,000</b> | <b>499,324,000</b> | <b>8,183,000</b> | <b>L6-3</b> |
|                                     | FCP:LCP       |      |     |                  | 61%                |                  | 39%              |                    |                  |             |

**L6-3-1 Pump Station (PK14)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                      | Specification  | Unit           | Qty   | FC Portion (JPY) |          | LC Portion (TND) |                  | Total             |                  | Reference                |
|----------------------------|----------------|----------------|-------|------------------|----------|------------------|------------------|-------------------|------------------|--------------------------|
|                            |                |                |       | Unit Price       | Amount   | Unit Price       | Amount           | (JPY)             | (equiv. TND)     |                          |
| Excavation                 |                | m <sup>3</sup> | 2,874 | 0                | 0        | 16.500           | 47,421           | 2,893,629         | 47,421           |                          |
| Backfilling/Filling        |                | m <sup>3</sup> | 1,477 | 0                | 0        | 11.000           | 16,247           | 991,392           | 16,247           |                          |
| Waste Soil Removal         |                | m <sup>3</sup> | 1,398 | 0                | 0        | 23.100           | 32,294           | 1,970,580         | 32,294           |                          |
| Gravel                     |                | m <sup>3</sup> | 80    | 0                | 0        | 74.800           | 5,984            | 365,144           | 5,984            |                          |
| Waterproofing              |                | m <sup>2</sup> | 462   | 0                | 0        | 42.900           | 19,820           | 1,209,416         | 19,820           |                          |
| Formwork                   |                | m <sup>2</sup> | 3,056 | 0                | 0        | 62.700           | 191,611          | 11,692,103        | 191,611          |                          |
| Lean Concrete              |                | m <sup>3</sup> | 119   | 0                | 0        | 440.000          | 52,360           | 3,195,007         | 52,360           |                          |
| Reinforced Concrete        |                | m <sup>3</sup> | 828   | 0                | 0        | 935.000          | 774,180          | 47,240,464        | 774,180          |                          |
| Scaffolding                |                | m <sup>2</sup> | 2,115 | 0                | 0        | 107.800          | 227,997          | 13,912,377        | 227,997          |                          |
| Other Miscellaneous Works  | incl. Rebar    | Ls             | 1     |                  | 0        |                  | 136,791          | 8,347,011         | 136,791          | Sum of above items x 10% |
| Engineering Cost           |                | Ls             | 1     |                  | 0        |                  | 75,235           | 4,590,856         | 75,235           | Sum of other items x 5%  |
|                            |                |                |       |                  |          |                  |                  |                   |                  |                          |
|                            |                |                |       |                  |          |                  |                  |                   |                  |                          |
| <b>Total</b>               |                |                |       |                  | 0        |                  | 1,579,941        |                   |                  |                          |
| <b>Sub-Total (rounded)</b> | <b>to L6-3</b> |                |       |                  | <b>0</b> |                  | <b>1,580,000</b> | <b>96,412,000</b> | <b>1,580,000</b> | <b>L6-3-1</b>            |
|                            | FCP:LCP        |                |       |                  | 0%       |                  | 100%             |                   |                  |                          |

10.5-66

**L6-3-2 Sub-station (PK14)**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                       | Specification  | Unit           | Qty   | FC Portion (JPY) |          | LC Portion (TND) |                | Total             |                | Reference                |
|-----------------------------|----------------|----------------|-------|------------------|----------|------------------|----------------|-------------------|----------------|--------------------------|
|                             |                |                |       | Unit Price       | Amount   | Unit Price       | Amount         | (JPY)             | (equiv. TND)   |                          |
| Excavation                  |                | m <sup>3</sup> | 248   | 0                | 0        | 16.500           | 4,092          | 249,694           | 4,092          |                          |
| Backfilling/Filling         |                | m <sup>3</sup> | 57    | 0                | 0        | 11.000           | 627            | 38,260            | 627            |                          |
| Waste Soil Removal          |                | m <sup>3</sup> | 191   | 0                | 0        | 23.100           | 4,412          | 269,220           | 4,412          |                          |
| Gravel                      |                | m <sup>3</sup> | 66    | 0                | 0        | 74.800           | 4,937          | 301,256           | 4,937          |                          |
| Waterproofing               |                | m <sup>2</sup> | 366   | 0                | 0        | 42.900           | 15,701         | 958,075           | 15,701         |                          |
| Formwork                    |                | m <sup>2</sup> | 1,627 | 0                | 0        | 62.700           | 102,013        | 6,224,833         | 102,013        |                          |
| Lean Concrete               |                | m <sup>3</sup> | 121   | 0                | 0        | 440.000          | 53,240         | 3,248,705         | 53,240         |                          |
| Reinforced Concrete         |                | m <sup>3</sup> | 323   | 0                | 0        | 935.000          | 302,005        | 18,428,345        | 302,005        |                          |
| Scaffolding                 |                | m <sup>2</sup> | 1,156 | 0                | 0        | 107.800          | 124,617        | 7,604,129         | 124,617        |                          |
| Other Miscellaneous Works   | incl. Rebar    | Ls             | 1     |                  | 0        |                  | 61,164         | 3,732,252         | 61,164         | Sum of above items x 10% |
| Engineering Cost            |                | Ls             | 1     |                  | 0        |                  | 33,640         | 2,052,738         | 33,640         | Sum of other items x 5%  |
|                             |                |                |       |                  |          |                  |                |                   |                |                          |
|                             |                |                |       |                  |          |                  |                |                   |                |                          |
| <b>Total</b>                |                |                |       |                  | 0        |                  | 706,449        |                   |                |                          |
| <b>Total Cost (Rounded)</b> | <b>to L6-3</b> |                |       |                  | <b>0</b> |                  | <b>706,000</b> | <b>43,080,000</b> | <b>706,000</b> | <b>L6-3-2</b>            |
|                             | FCP:LCP        |                |       |                  | 0%       |                  | 100%           |                   |                |                          |

10.5-67

**L6-3-3 Mechanical Facility for PK14 Pump Station**

Exchange Rate: 1.00US\$= 119.60JPY .000TND= 61.02JPY

| Items   | Specification             | Unit | Qt'y | FC Portion (JPY) |                    | LC Portion (TND) |                | Total              |                  | Reference       |
|---|---------------------------|------|------|------------------|--------------------|------------------|----------------|--------------------|------------------|-----------------|
|   |                           |      |      | Unit Price       | Amount             | Unit Price       | Amount         | (JPY)              | (equiv. TND)     |                 |
| <b>Intermediate transmission pump station</b> |                           |      |      |                  |                    |                  |                |                    |                  |                 |
| <b>PK14</b>                                   | PK14-S,Salah H            |      |      |                  |                    |                  |                |                    |                  |                 |
| Transmission Pump                             | 22.8m3/min x 38m          | set  | 3    | 16,529,000       | 49,587,000         | 48,000           | 144,000        | 58,374,000         | 956,637          |                 |
| Inlet Valve                                   | Dia. 450mm                | set  | 3    | 1,420,000        | 4,260,000          | 4,000            | 12,000         | 4,992,000          | 81,809           |                 |
| Check Valve                                   | Dia. 300mm                | set  | 3    | 1,188,000        | 3,564,000          | 3,000            | 9,000          | 4,113,000          | 67,404           |                 |
| Discharge Valve                               | Dia. 300mm                | set  | 3    | 2,881,000        | 8,643,000          | 8,000            | 24,000         | 10,107,000         | 165,634          | Motorized       |
| Maintenance Valve                             | Dia. 300mm                | set  | 3    | 1,204,000        | 3,612,000          | 3,000            | 9,000          | 4,161,000          | 68,191           |                 |
| Maintenance Valve                             | Dia. 500 mm               | set  | 2    | 2,367,000        | 4,734,000          | 7,000            | 14,000         | 5,588,000          | 91,577           | Butterfly Valve |
| Maintenance Valve                             | Dia. 700 mm               | set  | 1    | 2,841,000        | 2,841,000          | 8,000            | 8,000          | 3,329,000          | 54,556           | Butterfly Valve |
| Pump Lifting Equipment                        | Suspension crane : 3.2ton | lot  | 1    | 15,720,000       | 15,720,000         | 45,000           | 45,000         | 18,466,000         | 302,622          |                 |
| Pipes   |                           | set  | 1    | 13,163,000       | 13,163,000         | 38,000           | 38,000         | 15,482,000         | 253,720          |                 |
|   |                           |      |      |                  |                    |                  |                |                    |                  |                 |
|   |                           |      |      |                  |                    |                  |                |                    |                  |                 |
| Total   |                           |      |      |                  | 106,124,000        |                  | 303,000        |                    |                  |                 |
| <b>Total (Rounded)</b>                        | <b>to L6-3</b>            |      |      |                  | <b>106,124,000</b> |                  | <b>303,000</b> | <b>124,613,000</b> | <b>2,042,000</b> | <b>L6-3-3</b>   |
|   | FCP:LCP                   |      |      |                  | 85%                |                  | 15%            |                    |                  |                 |

10.5-68

**L6-3-4 Electrical Facility for PK14 Pump Station**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                                   | Specification                | Unit      | Qt'y     | FC Portion (JPY) |                   | LC Portion (TND) |                | Total             |                | Reference  |
|---|------------------------------|-----------|----------|------------------|-------------------|------------------|----------------|-------------------|----------------|--|
|   |                              |           |          | Unit Price       | Amount            | Unit Price       | Amount         | (JPY)             | (equiv. TND)   |  |
| PK-14                                   |                              |           |          |                  |                   |                  |                |                   |                |  |
| <b>30kV Switchgear</b>                  |                              | <b>Ls</b> | <b>1</b> |                  | <b>25,925,000</b> |                  | <b>74,976</b>  | <b>30,500,000</b> | <b>499,836</b> | <b>a.</b>  |
| 30kV DS, LA Panel                       |                              | set       | 1        | 4,250,000        | 4,250,000         | 12,291           | 12,291         | 5,000,000         | 81,940         | DS: Disconnecting Switch<br>LA: Lightning Arrester |
| 30kV VT Panel                           |                              | set       | 1        | 4,250,000        | 4,250,000         | 12,291           | 12,291         | 5,000,000         | 81,940         | VT:<br>Voltage Transformer                         |
| 30kV VCB Panel                          |                              | set       | 2        | 7,225,000        | 14,450,000        | 20,895           | 41,790         | 17,000,000        | 278,597        | VCB:<br>Vacuum Circuit Breaker                     |
| 30kV/400V Transformer                   | oil type 0.5MVA              | set       | 1        | 2,975,000        | 2,975,000         | 8,604            | 8,604          | 3,500,000         | 57,358         |  |
|   |                              |           |          |                  |                   |                  |                |                   |                |  |
| <b>LV Switchgear</b>                    |                              | <b>Ls</b> | <b>1</b> |                  | <b>44,837,500</b> |                  | <b>129,668</b> | <b>52,750,000</b> | <b>864,471</b> | <b>b.</b>  |
| LV Main Switchgear                      | 3 units                      | set       | 1        | 8,500,000        | 8,500,000         | 24,582           | 24,582         | 10,000,000        | 163,881        | LV: Low Voltage                                    |
| Transmission Pump for Sidi Salah EH     | 400V VFD 250kW               | set       | 3        | 5,780,000        | 17,340,000        | 16,716           | 50,148         | 20,400,000        | 334,317        | VFD:<br>Variable Frequency Drive                   |
| MCC for Transmission-1                  | 6 units                      | set       | 1        | 17,467,500       | 17,467,500        | 50,516           | 50,516         | 20,550,000        | 336,775        | MCC:<br>Motor Control Centre                       |
| Local Panel                             |                              | set       | 6        | 255,000          | 1,530,000         | 737              | 4,422          | 1,800,000         | 29,499         |  |
|   |                              |           |          |                  |                   |                  |                |                   |                |  |
| <b>Instrumentation &amp; Monitoring</b> |                              | <b>Ls</b> | <b>1</b> |                  | <b>47,260,000</b> |                  | <b>136,678</b> | <b>55,600,000</b> | <b>911,177</b> | <b>c.</b>  |
| Transmission Flow                       | electro-magnetic 800mm       | set       | 1        | 4,335,000        | 4,335,000         | 12,537           | 12,537         | 5,100,000         | 83,579         |  |
| Transmission Flow                       | electro-magnetic 800mm       | set       | 1        | 4,335,000        | 4,335,000         | 12,537           | 12,537         | 5,100,000         | 83,579         |  |
| Water Level                             | Ultrasonic                   | set       | 3        | 680,000          | 2,040,000         | 1,967            | 5,901          | 2,400,000         | 39,331         |  |
| Water Quality                           | Turbidity, pH, Res. Chlorine | set       | 6        | 1,275,000        | 7,650,000         | 3,687            | 22,122         | 9,000,000         | 147,493        | Inflow: TDS x 2, Outflow: 4                        |
| Instrumentation Panel                   |                              | set       | 3        | 2,550,000        | 7,650,000         | 7,375            | 22,125         | 9,000,000         | 147,493        |  |
| PLC Panel                               |                              | lot       | 1        | 6,375,000        | 6,375,000         | 18,437           | 18,437         | 7,500,000         | 122,911        | PLC:<br>Programmable Logic                         |



**L6-3-4 Electrical Facility for PK14 Pump Station**

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                             | Specification         | Unit       | Qt'ty    | FC Portion (JPY)  |                    | LC Portion (TND) |                | Total              |                  | Reference                           |
|-----------------------------------|-----------------------|------------|----------|-------------------|--------------------|------------------|----------------|--------------------|------------------|-------------------------------------|
|                                   |                       |            |          | Unit Price        | Amount             | Unit Price       | Amount         | (JPY)              | (equiv. TND)     |                                     |
| <i>Telemetry System</i>           | <i>PK14-SS. EH/EB</i> | <i>lot</i> | <i>2</i> | <i>6,800,000</i>  | <i>13,600,000</i>  | <i>19,666</i>    | <i>39,332</i>  | <i>16,000,000</i>  | <i>262,209</i>   |                                     |
| <i>UPS</i>                        | <i>10kVA</i>          | <i>set</i> | <i>1</i> | <i>1,275,000</i>  | <i>1,275,000</i>   | <i>3,687</i>     | <i>3,687</i>   | <i>1,500,000</i>   | <i>24,582</i>    | UPS:<br>Uninterruptive Power Supply |
|                                   |                       |            |          |                   |                    |                  |                |                    |                  |                                     |
| <b>Emergency Power Facilities</b> |                       | <b>Ls</b>  | <b>1</b> |                   | <b>63,750,000</b>  |                  | <b>184,366</b> | <b>75,000,000</b>  | <b>1,229,105</b> | <b>d.</b>                           |
| <i>Stand-by Generator</i>         | <i>Diesel 750kVA</i>  | <i>set</i> | <i>1</i> | <i>63,750,000</i> | <i>63,750,000</i>  | <i>184,366</i>   | <i>184,366</i> | <i>75,000,000</i>  | <i>1,229,105</i> |                                     |
|                                   |                       |            |          |                   |                    |                  |                |                    |                  |                                     |
| <b>Other Miscellaneous Works</b>  |                       | <b>Ls</b>  | <b>1</b> |                   | <b>18,177,250</b>  |                  | <b>52,569</b>  | <b>21,384,998</b>  | <b>350,459</b>   | Sum of (a~d) x 10%                  |
|                                   |                       |            |          |                   |                    |                  |                |                    |                  |                                     |
|                                   |                       |            |          |                   |                    |                  |                |                    |                  |                                     |
|                                   |                       |            |          |                   |                    |                  |                |                    |                  |                                     |
|                                   |                       |            |          |                   |                    |                  |                |                    |                  |                                     |
|                                   |                       |            |          |                   |                    |                  |                |                    |                  |                                     |
|                                   |                       |            |          |                   |                    |                  |                |                    |                  |                                     |
|                                   |                       |            |          |                   |                    |                  |                |                    |                  |                                     |
|                                   |                       |            |          |                   |                    |                  |                |                    |                  |                                     |
|                                   |                       |            |          |                   |                    |                  |                |                    |                  |                                     |
|                                   |                       |            |          |                   |                    |                  |                |                    |                  |                                     |
|                                   |                       |            |          |                   |                    |                  |                |                    |                  |                                     |
| <b>Total</b>                      |                       |            |          |                   | <b>199,949,750</b> |                  | <b>578,257</b> |                    |                  |                                     |
| <b>Total (Rounded)</b>            | <b>to L6-3</b>        |            |          |                   | <b>199,950,000</b> |                  | <b>578,000</b> | <b>235,220,000</b> | <b>3,855,000</b> | <b>L6-3-4</b>                       |
|                                   | FCP:LCP               |            |          |                   | 85%                |                  | 15%            |                    |                  |                                     |

### L7 Power Supply Line (by STEG)

Exchange Rate: 1.00US\$= 119.60JPY

1.000TND= 61.02JPY

| Items                                  | Specification | Unit | Qt'ty | FC Portion (JPY) |          | LC Portion (TND) |                  | Total              |                  | Reference |
|--|---------------|------|-------|------------------|----------|------------------|------------------|--------------------|------------------|-----------|
|  |               |      |       | Unit Price       | Amount   | Unit Price       | Amount           | (JPY)              | (equiv. TND)     |           |
| Power Supply Line Construction by STEG |               | Ls   | 1     |                  | 0        |                  | 4,350,000        | 265,437,000        | 4,350,000        |           |
| 150kV x 15km                           |               |      |       |                  |          |                  |                  |                    |                  |           |
| Travées                                | 150kV         | Ls   | 2     |                  | 0        |                  | 2,400,000        | 146,448,000        | 2,400,000        |           |
| Assistance                             |               | Ls   | 1     |                  | 0        |                  | 532,500          | 32,493,150         | 532,500          |           |
|  |               |      |       |                  |          |                  |                  |                    |                  |           |
|  |               |      |       |                  |          |                  |                  |                    |                  |           |
|  |               |      |       |                  |          |                  |                  |                    |                  |           |
|  |               |      |       |                  |          |                  |                  |                    |                  |           |
|  |               |      |       |                  |          |                  |                  |                    |                  |           |
|  |               |      |       |                  |          |                  |                  |                    |                  |           |
|  |               |      |       |                  |          |                  |                  |                    |                  |           |
|  |               |      |       |                  |          |                  |                  |                    |                  |           |
|  |               |      |       |                  |          |                  |                  |                    |                  |           |
|  |               |      |       |                  |          |                  |                  |                    |                  |           |
|  |               |      |       |                  |          |                  |                  |                    |                  |           |
|  |               |      |       |                  |          |                  |                  |                    |                  |           |
| Total                                  |               |      |       |                  | 0        |                  | 7,282,500        |                    |                  |           |
| <b>Total (Rounded)</b>                 | <b>to T1</b>  |      |       |                  | <b>0</b> |                  | <b>7,283,000</b> | <b>444,409,000</b> | <b>7,283,000</b> | <b>L7</b> |
|  | FCP:LCP       |      |       |                  | 0%       |                  | 100%             |                    |                  |           |

## 10.12-1 Cash Flows of FIRR Calculation

(1) FIRR with Present Water Rate at 0.382TND/m<sup>3</sup>

| 0.382                   | YEAR | 1TND= 61.02    |  | JPY                          |                | UNIT:JPY               |                           |
|-------------------------|------|----------------|--|------------------------------|----------------|------------------------|---------------------------|
|                         |      | Project Cost   | Non-eligible Cost to be financed by SONEDE | Operation & Maintenance Cost | Revenue        | Net Benefit With CAPEX | Net Benefit Without CAPEX |
|                         |      | a              | b (included in a)                          | c                            | d              | d-a-c                  | d-b-c                     |
| Construction            | 2015 | 0              | 0  | 0                            | 0              | 0                      | 0                         |
|                         | 2016 | 0              | 0  | 0                            | 0              | 0                      | 0                         |
|                         | 2017 | 701,738,436    | 111,086,679                                | 0                            | 0              | -701,738,436           | -111,086,679              |
|                         | 2018 | 346,429,763    | 76,845,491                                 | 0                            | 0              | -346,429,763           | -76,845,491               |
|                         | 2019 | 5,752,699,567  | 540,549,751                                | 0                            | 0              | -5,752,699,567         | -540,549,751              |
|                         | 2020 | 9,892,306,518  | 1,065,375,471                              | 0                            | 0              | -9,892,306,518         | -1,065,375,471            |
|                         | 2021 | 9,403,934,920  | 983,924,237                                | 0                            | 0              | -9,403,934,920         | -983,924,237              |
|                         | 2022 | 8,516,748,025  | 901,726,138                                | 0                            | 136,736,013    | -8,380,012,012         | -764,990,125              |
| Operation & Maintenance | 2023 | 7,888,928,826  | 805,443,700                                | 391,979,012                  | 562,136,943    | -7,718,770,895         | -635,285,769              |
|                         | 2024 | 1,820,589,502  | 182,022,124                                | 1,676,743,126                | 607,715,614    | -2,889,617,013         | -1,251,049,636            |
|                         | 2025 | 144,100,349    | 13,587,337                                 | 1,676,743,126                | 607,715,614    | -1,213,127,861         | -1,082,614,849            |
|                         | 2026 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2027 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2028 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2029 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2030 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2031 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2032 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2033 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2034 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2035 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2036 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2037 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2038 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2039 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2040 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2041 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2042 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2043 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2044 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2045 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2046 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
|                         | 2047 | 0              | 0  | 1,676,743,126                | 607,715,614    | -1,069,027,512         | -1,069,027,512            |
| 2048                    | 0    | 0              | 1,676,743,126                              | 607,715,614                  | -1,069,027,512 | -1,069,027,512         |                           |
| 2049                    | 0    | 0              | 1,676,743,126                              | 607,715,614                  | -1,069,027,512 | -1,069,027,512         |                           |
| 2050                    | 0    | 0              | 1,676,743,126                              | 607,715,614                  | -1,069,027,512 | -1,069,027,512         |                           |
| 2051                    | 0    | 0              | 1,676,743,126                              | 607,715,614                  | -1,069,027,512 | -1,069,027,512         |                           |
| 2052                    | 0    | 0              | 1,676,743,126                              | 607,715,614                  | -1,069,027,512 | -1,069,027,512         |                           |
| TOTAL                   |      | 44,467,475,906 | 4,680,560,928                              | 49,017,529,664               | 18,322,625,771 | -75,162,379,800        | -35,375,464,822           |
| FIRR                    |      |                |  |                              |                | -                      | -                         |

(2) FIRR with Water Rate at 1.154TND/m<sup>3</sup>

TND.1.0 = JPY61.02

| 1.154                    | YEAR | Project Cost   | Non-eligible Cost to be financed by SONEDE | Operartion & Maintenance Cost | Revenue        | Net Benefit With CAPEX | Net Benefit Without CAPEX |
|--------------------------|------|----------------|--|-------------------------------|----------------|------------------------|---------------------------|
|                          |      | a              | b (included in a)                          | c                             | d              | d-a-c                  | d-b-c                     |
| Construction             | 2015 | 0              | 0  | 0                             | 0              | 0                      | 0                         |
|                          | 2016 | 0              | 0  | 0                             | 0              | 0                      | 0                         |
|                          | 2017 | 701,738,436    | 111,086,679                                | 0                             | 0              | -701,738,436           | -111,086,679              |
|                          | 2018 | 346,429,763    | 76,845,491                                 | 0                             | 0              | -346,429,763           | -76,845,491               |
|                          | 2019 | 5,752,699,567  | 540,549,751                                | 0                             | 0              | -5,752,699,567         | -540,549,751              |
|                          | 2020 | 9,892,306,518  | 1,065,375,471                              | 0                             | 0              | -9,892,306,518         | -1,065,375,471            |
|                          | 2021 | 9,403,934,920  | 983,924,237                                | 0                             | 0              | -9,403,934,920         | -983,924,237              |
|                          | 2022 | 8,516,748,025  | 901,726,138                                | 0                             | 192,003,135    | -8,324,744,890         | -709,723,003              |
| Operartion & Maintenance | 2023 | 7,888,928,826  | 805,443,700                                | 391,979,012                   | 1,016,555,498  | -7,264,352,340         | -180,867,214              |
|                          | 2024 | 1,820,589,502  | 182,022,124                                | 1,676,743,126                 | 1,344,610,569  | -2,152,722,059         | -514,154,682              |
|                          | 2025 | 144,100,349    | 13,587,337                                 | 1,676,743,126                 | 1,590,242,220  | -230,601,255           | -100,088,243              |
|                          | 2026 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2027 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2028 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2029 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2030 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2031 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2032 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2033 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2034 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2035 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2036 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2037 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2038 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2039 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2040 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2041 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2042 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2043 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2044 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2045 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2046 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
|                          | 2047 | 0              | 0  | 1,676,743,126                 | 1,835,873,871  | 159,130,745            | 159,130,745               |
| 2048                     | 0    | 0              | 1,676,743,126                              | 1,835,873,871                 | 159,130,745    | 159,130,745            |                           |
| 2049                     | 0    | 0              | 1,676,743,126                              | 1,835,873,871                 | 159,130,745    | 159,130,745            |                           |
| 2050                     | 0    | 0              | 1,676,743,126                              | 1,835,873,871                 | 159,130,745    | 159,130,745            |                           |
| 2051                     | 0    | 0              | 1,676,743,126                              | 1,835,873,871                 | 159,130,745    | 159,130,745            |                           |
| 2052                     | 0    | 0              | 1,676,743,126                              | 1,835,873,871                 | 159,130,745    | 159,130,745            |                           |
| TOTAL                    |      | 44,467,475,906 | 4,680,560,928                              | 49,017,529,664                | 53,712,005,950 | -39,772,999,620        | 13,915,358                |
| FIRR                     |      |                |  |                               |                | -10.54%                | 0.02%                     |

(3) FIRR with Water Rate at 1.258TND/m<sup>3</sup>

TND.1.0 = JPY61.02

| 1.258                    | YEAR | Project Cost   | Non-eligible Cost to be financed by SONEDE | Operartion & Maintenance Cost | Revenue        | Net Benefit With CAPEX | Net Benefit Without CAPEX |
|--------------------------|------|----------------|--|-------------------------------|----------------|------------------------|---------------------------|
|                          |      | a              | b (included in a)                          | c                             | d              | d-a-c                  | d-b-c                     |
| Construction             | 2015 | 0              | 0  | 0                             | 0              | 0                      | 0                         |
|                          | 2016 | 0              | 0  | 0                             | 0              | 0                      | 0                         |
|                          | 2017 | 701,738,436    | 111,086,679                                | 0                             | 0              | -701,738,436           | -111,086,679              |
|                          | 2018 | 346,429,763    | 76,845,491                                 | 0                             | 0              | -346,429,763           | -76,845,491               |
|                          | 2019 | 5,752,699,567  | 540,549,751                                | 0                             | 0              | -5,752,699,567         | -540,549,751              |
|                          | 2020 | 9,892,306,518  | 1,065,375,471                              | 0                             | 0              | -9,892,306,518         | -1,065,375,471            |
|                          | 2021 | 9,403,934,920  | 983,924,237                                | 0                             | 0              | -9,403,934,920         | -983,924,237              |
|                          | 2022 | 8,516,748,025  | 901,726,138                                | 0                             | 199,448,447    | -8,317,299,578         | -702,277,692              |
| Operartion & Maintenance | 2023 | 7,888,928,826  | 805,443,700                                | 391,979,012                   | 1,077,772,506  | -7,203,135,332         | -119,650,206              |
|                          | 2024 | 1,820,589,502  | 182,022,124                                | 1,676,743,126                 | 1,443,881,391  | -2,053,451,236         | -414,883,859              |
|                          | 2025 | 144,100,349    | 13,587,337                                 | 1,676,743,126                 | 1,722,603,317  | -98,240,158            | 32,272,854                |
|                          | 2026 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2027 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2028 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2029 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2030 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2031 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2032 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2033 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2034 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2035 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2036 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2037 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2038 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2039 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2040 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2041 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2042 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2043 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2044 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2045 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2046 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
|                          | 2047 | 0              | 0  | 1,676,743,126                 | 2,001,325,243  | 324,582,117            | 324,582,117               |
| 2048                     | 0    | 0              | 1,676,743,126                              | 2,001,325,243                 | 324,582,117    | 324,582,117            |                           |
| 2049                     | 0    | 0              | 1,676,743,126                              | 2,001,325,243                 | 324,582,117    | 324,582,117            |                           |
| 2050                     | 0    | 0              | 1,676,743,126                              | 2,001,325,243                 | 324,582,117    | 324,582,117            |                           |
| 2051                     | 0    | 0              | 1,676,743,126                              | 2,001,325,243                 | 324,582,117    | 324,582,117            |                           |
| 2052                     | 0    | 0              | 1,676,743,126                              | 2,001,325,243                 | 324,582,117    | 324,582,117            |                           |
| TOTAL                    |      | 44,467,475,906 | 4,680,560,928                              | 49,017,529,664                | 58,479,487,218 | -35,005,518,352        | 4,781,396,625             |
| FIRR                     |      |                |  |                               |                | -7.67%                 | 4.79%                     |

(4) FIRR with Water Rate at 2.022TND/m<sup>3</sup>

TND.1.0 = JPY61.02

| 2.022                   | YEAR | Project Cost   | Non-eligible Cost to be financed by SONEDE | Operartion & Maintenance Cost | Revenue        | Net Benefit With CAPEX | Net Benefit Without CAPEX |
|-------------------------|------|----------------|--|-------------------------------|----------------|------------------------|---------------------------|
|                         |      | a              | b (included in a)                          | c                             | d              | d-a-c                  | d-b-c                     |
| Construction            | 2015 | 0              | 0  | 0                             | 0              | 0                      | 0                         |
|                         | 2016 | 0              | 0  | 0                             | 0              | 0                      | 0                         |
|                         | 2017 | 701,738,436    | 111,086,679                                | 0                             | 0              | -701,738,436           | -111,086,679              |
|                         | 2018 | 346,429,763    | 76,845,491                                 | 0                             | 0              | -346,429,763           | -76,845,491               |
|                         | 2019 | 5,752,699,567  | 540,549,751                                | 0                             | 0              | -5,752,699,567         | -540,549,751              |
|                         | 2020 | 9,892,306,518  | 1,065,375,471                              | 0                             | 0              | -9,892,306,518         | -1,065,375,471            |
|                         | 2021 | 9,403,934,920  | 983,924,237                                | 0                             | 0              | -9,403,934,920         | -983,924,237              |
|                         | 2022 | 8,516,748,025  | 901,726,138                                | 0                             | 254,142,852    | -8,262,605,173         | -647,583,286              |
| Operation & Maintenance | 2023 | 7,888,928,826  | 805,443,700                                | 391,979,012                   | 1,527,482,060  | -6,753,425,778         | 330,059,348               |
|                         | 2024 | 1,820,589,502  | 182,022,124                                | 1,676,743,126                 | 2,173,140,129  | -1,324,192,499         | 314,374,878               |
|                         | 2025 | 144,100,349    | 13,587,337                                 | 1,676,743,126                 | 2,694,948,300  | 874,104,825            | 1,004,617,837             |
|                         | 2026 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2027 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2028 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2029 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2030 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2031 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2032 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2033 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2034 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2035 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2036 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2037 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2038 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2039 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2040 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2041 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2042 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2043 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2044 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2045 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2046 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
|                         | 2047 | 0              | 0  | 1,676,743,126                 | 3,216,756,471  | 1,540,013,345          | 1,540,013,345             |
| 2048                    | 0    | 0              | 1,676,743,126                              | 3,216,756,471                 | 1,540,013,345  | 1,540,013,345          |                           |
| 2049                    | 0    | 0              | 1,676,743,126                              | 3,216,756,471                 | 1,540,013,345  | 1,540,013,345          |                           |
| 2050                    | 0    | 0              | 1,676,743,126                              | 3,216,756,471                 | 1,540,013,345  | 1,540,013,345          |                           |
| 2051                    | 0    | 0              | 1,676,743,126                              | 3,216,756,471                 | 1,540,013,345  | 1,540,013,345          |                           |
| 2052                    | 0    | 0              | 1,676,743,126                              | 3,216,756,471                 | 1,540,013,345  | 1,540,013,345          |                           |
| TOTAL                   |      | 44,467,475,906 | 4,680,560,928                              | 49,017,529,664                | 93,502,138,069 | 17,132,499             | 39,804,047,477            |
| FIRR                    |      |                |  |                               |                | 0.00%                  | 21.96%                    |

(5) FIRR with Water Rate at 3.035TND/m<sup>3</sup>

TND.1.0 = JPY61.02



| 3.035                    | YEAR | Project Cost   | Non-eligible Cost to be financed by SONEDE | Operartion & Maintenance Cost | Revenue         | Net Benefit With CAPEX | Net Benefit Without CAPEX |
|--------------------------|------|----------------|--|-------------------------------|-----------------|------------------------|---------------------------|
|                          |      | a              | b (included in a)                          | c                             | d               | d-a-c                  | d-b-c                     |
| Construction             | 2015 | 0              | 0  | 0                             | 0               | 0                      | 0                         |
|                          | 2016 | 0              | 0  | 0                             | 0               | 0                      | 0                         |
|                          | 2017 | 701,738,436    | 111,086,679                                | 0                             | 0               | -701,738,436           | -111,086,679              |
|                          | 2018 | 346,429,763    | 76,845,491                                 | 0                             | 0               | -346,429,763           | -76,845,491               |
|                          | 2019 | 5,752,699,567  | 540,549,751                                | 0                             | 0               | -5,752,699,567         | -540,549,751              |
|                          | 2020 | 9,892,306,518  | 1,065,375,471                              | 0                             | 0               | -9,892,306,518         | -1,065,375,471            |
|                          | 2021 | 9,403,934,920  | 983,924,237                                | 0                             | 0               | -9,403,934,920         | -983,924,237              |
|                          | 2022 | 8,516,748,025  | 901,726,138                                | 0                             | 326,663,051     | -8,190,084,973         | -575,063,087              |
| Operartion & Maintenance | 2023 | 7,888,928,826  | 805,443,700                                | 391,979,012                   | 2,123,759,258   | -6,157,148,580         | 926,336,546               |
|                          | 2024 | 1,820,589,502  | 182,022,124                                | 1,676,743,126                 | 3,140,076,124   | -357,256,503           | 1,281,310,874             |
|                          | 2025 | 144,100,349    | 13,587,337                                 | 1,676,743,126                 | 3,984,196,294   | 2,163,352,819          | 2,293,865,831             |
|                          | 2026 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2027 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2028 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2029 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2030 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2031 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2032 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2033 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2034 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2035 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2036 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2037 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2038 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2039 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2040 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2041 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2042 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2043 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2044 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2045 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2046 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
|                          | 2047 | 0              | 0  | 1,676,743,126                 | 4,828,316,464   | 3,151,573,338          | 3,151,573,338             |
| 2048                     | 0    | 0              | 1,676,743,126                              | 4,828,316,464                 | 3,151,573,338   | 3,151,573,338          |                           |
| 2049                     | 0    | 0              | 1,676,743,126                              | 4,828,316,464                 | 3,151,573,338   | 3,151,573,338          |                           |
| 2050                     | 0    | 0              | 1,676,743,126                              | 4,828,316,464                 | 3,151,573,338   | 3,151,573,338          |                           |
| 2051                     | 0    | 0              | 1,676,743,126                              | 4,828,316,464                 | 3,151,573,338   | 3,151,573,338          |                           |
| 2052                     | 0    | 0              | 1,676,743,126                              | 4,828,316,464                 | 3,151,573,338   | 3,151,573,338          |                           |
| TOTAL                    |      | 44,467,475,906 | 4,680,560,928                              | 49,017,529,664                | 139,939,239,263 | 46,454,233,693         | 86,241,148,671            |
| FIRR                     |      |                |  |                               |                 | 4.77%                  | 35.16%                    |

***CHAPTER 11***

***CONFIRMATION OF VIABILITY AND RISK ANALYSIS***



11.3-1 Request Letter to STEG from SONEDE regarding Power Provision of 40MW  
(issued on May 28, 2013)

**الشركة الوطنية للاستغلال وتوزيع المياه**  
**SOCIÉTÉ NATIONALE D'EXPLOITATION ET DE DISTRIBUTION DES EAUX**

تونس في 28 ماي 2013

إلى  
السيد المدير العام للشركة التونسية للكهرباء والغاز 26170

الموضوع: مشروع إنجاز محطة لتغطية مياه البحر بصفاقس

تحية طيبة و بعد،


في إطار مشروع إنجاز محطة لتغطية مياه البحر بصفاقس و ربطها بشبكة التوزيع، قام وفد من الوكالة اليابانية للتعاون الدولي بزيارة إلى البلاد التونسية خلال الفترة الممتدة من 13 إلى 17 ماي 2013 قصد التحضير لإعداد دراسة أولية للمشروع الذي سيتم تمويله من طرف الجانب الياباني، وقد طالب الفريق الياباني بمدد بعض المعطيات المتعلقة بتوريد ولاية صفاقس بالطاقة الكهربائية التالية:

- إجمالي وتفصيل حجم الطاقة الكهربائية بولاية صفاقس،
- الزيادة المتوقعة من إمدادات الطاقة الكهربائية في السنوات القليلة القادمة بولاية صفاقس.

نالرجاء مآذنا بالمعطيات المطلوبة في أقرب الآجال لتيسر انطلاق دراسة للمشروع علما و أن الطاقة الضرورية لتشغيل المحطة المزعم إنجازها تقارب 40 ميجاوات.

تقبلا فائق عبارات التقدير و السلام.

الرئيس المدير العام  
الهادي بالحاج

  
ARRIVÉE : 28 MAI 2013

شارع سلطان بن علي  
الهادي - II - تونس 2092  
P. Slimane Ben Slimane  
M. Slimane II - Tunis 2092

الهاتف : 71.887.000  
فاكس : 71.871.000  
E-mail : sonede@sonede.com.tn

السجل التجاري : 0111592608  
Matri-cule Fiscal : 1455 /A/24/000  
البريد : 2071

## 11.3-2 Translation of 11.3-1 in English

# SONEDE

Tunis, May 28, 2013

To the kind attention of the General Manager of STEG, Tunisian Power Company

Subject: Construction project of the sea water desalination project in Sfax

Greetings,

In the framework of the sea water desalination plant construction project and its subsequent connection to the distribution network, a delegation representing the Japan International Cooperation Agency visited Tunisia on May 13-17, 2013 to set the framework for a preliminary study of a project that will be funded by the Japanese part, and the Japanese team requested some information concerning power supply to the Sfax Governorate as follows:

- Total and detailed power supply to the Governorate of Sfax;
- Possible increase of electrical power supply in the few next years in the Sfax Governorate;

Therefore, we would appreciate you providing us with these data in the best possible time to ensure smooth beginning of the project, knowing that power required for the operation of the planned station would be about 40 MW.

Please accept my best regards

General Manager

Hedi Belhaj

11.3-3 Answer from STEG to SONEDE regarding Request Letter on May 28, 2013  
(issued on August 22, 2013)

**Société Tunisienne de l'Electricité et du Gaz**  **الشركة التونسية للكهرباء والغاز**

1962-2012  
STEG 50

الشركة التونسية للكهرباء والغاز  
الإدارة العمومية للتوزيع بصفاقس  
خريف سبور منصور كاد 3 صفاقس 4012  
هاتف : 255 236 74 - الفاكس : 043 236 74

السيد الرئيس المدير العام للشركة  
الوطنية لاستغلال و توزيع المياه  
شارع سليمان بن سليمان  
المنار II 2092 تونس

22 أوت 2013

00581

المرجع : مراسلة ع-26170-دد بتاريخ 2013/05/28  
الموضوع : مشروع إنجاز محطة لتحلية مياه البحر بصفاقس

سيدي الرئيس المدير العام ،

أما بعد فتبعا للمراسلة المذكورة بالمرجع أعلاه و المتعلقة بمشروع إنجاز محطة لتحلية مياه البحر بصفاقس بقوة كهربائية قدرت ب 40 ميغاواط نعلمكم بأن تنوير هذا المشروع يتطلب تركيب محطة تحويل كهربائية جهد عالي/ جهد متوسط خاصة بهذه المحطة و يقع ربطها بشبكة الجهد العالي على حسابكم. و لدراسة هذا الأمر فإننا نرجو منكم مدنا بالمعطيات التالية :

- الموقع الجغرافي للمشروع و الإحداثيات الرقمية للموقع باستخدام نظام تحديد المواقع العالمي (GPS)
- تاريخ تشغيل المحطة و بيان قوة الطاقة الكهربائية المطلوبة في كل سنة
- طريقة ربط المحطة (simple alimentation ou double alimentation)

و نتمنى على امتداد للمزيد من الارشادات في هذا الموضوع.  
تقبلوا سيدي المدير فائق احترامتنا وتقديرنا.

  
محمد فخر الدين  
مدير التوزيع بصفاقس

R.C. : B 121461997

الطريق الإخلماسي : 88، نهج كمال أجازونك صرب 1000-1000 تونس سديس - CEDEX  
Site Web : www.steg.com.tn Courriel : dpsc@steg.com.tn ☎ (216) 71 341 311 📠 (216) 71 341 401 / 71 340 101 / 71 350 174

**11.3-4 Translation of 11.3-3 in English**

# STEG

August 22, 2013

To the kind attention of the Director General of SONEDE

Reference: Letter n. 26170 dated May 28, 2013

Subject: Construction project of the sea water desalination project in Sfax

Mr. Director General:

Further to your letter referenced above concerning the sea water desalination construction project in Sfax with a total power of 40 MW, we inform you that this project will require the construction of a high voltage/middle voltage power transformation station that will be connected to the high voltage station at your expense. In order to further study this subject, we kindly ask you to provide us with the following information:

- Geographic location of the project and the digital coordinates based on GPS;
- Date of project operation and electrical power required per year;
- Connection pattern of the station: simple supply or double supply.

We remain prepared to provide you with additional information.

Please accept our best regards.

Sfax Regional Distribution Director

Mohamed Ketata

11.3-5 Answer of STEG about Power Supply Cost and Method (2013/11/20)

21-NOV-2013 THU 10:11

SONEDE. DTTS

FAX NO. 216 74 223303

P. 01/02

Société Tunisienne  
de l'Electricité et du Gaz



الشركة التونسية  
لل كهرباء والغاز

à l'attention de  
M<sup>x</sup> A. Boussoffara

Le Chef Service  
Travaux Equipements  
M.F MAALEJ

**STEG**  
Direction Régionale  
Distribution de Sfax  
Route de Manouba Km 3 - Sfax 302  
Tél. : 216 74 223 303 Fax : 216 74 223 303

**SONEDE**  
Division Equipement Sud  
Rue Ibn Badis 3029 Sfax

20 NOV 2013

№ 00846

OBJET : Raccordement de la station de dessalement projetée à Sfax.  
Réf : Votre note du 04/11/2013

Monsieur

Suite à votre note du 04/11/2013 relative au raccordement de la station de dessalement projetée à Sfax et en réponse à l'enquête avancée par l'équipe japonaise chargé de l'étude de la dite station nous vous transmettons ci-après les éléments de réponse relatifs à cette enquête.

- 1) Les coupures sur le réseau 150 kV sont minimales du fait que le réseau HTB est maillé. Cependant la puissance demandée par le projet est disponible actuellement en termes de production.
- 2) La puissance maximale du transformateur qui peut être raccordé sur le réseau 150 kV est de 40 MVA.
- 3) La distance et le coût actuel d'extension de la ligne électrique dépendent de l'emplacement du site. Le calcul du coût s'est fait sur la base d'un câble souterrain. Le tableau suivant résume ces différentes quantités.

| Site N° | Distance  | Coût d'extension (DT HTVA) |
|---------|-----------|----------------------------|
| 1       | 2x3.6 km  | 11 million                 |
| 2       | 2x5.6 km  | 17 million                 |
| 3.1     | 2x11.1 km | 34 million                 |
| 3.2     | 2x15.5 km | 47 million                 |
| 3.3     | 2x18.2 km | 55 million                 |
| 5       | 2x26 km   | 78 million                 |
| 6       | 2x35.3 km | 106 million                |

3  
0121111111

- 4) L'alimentation sera en double ligne (entrée sortie) à partir du point le plus proche du réseau 150 kV. Il n'y aura pas de ligne spécialisé ni d'alimentation duplex à partir d'une autre station. Cependant il est possible que la ligne soit en partie en souterrain et en partie en aérien.



*Le Directeur Régional de la  
Distribution de Sfax*

*Mohammed KETATA*

**11.3-6 Translation of 11.3-5 in English**

**From: STEG Regional Distribution Department, SFAX**

**To: SONEDE Equipment Division – SOUTH**

**20 November, 2013**

**Subject: Connection of the Sfax desalination station project**

**Reference: Your note dated November 4, 2013**

Dear Sir,

Further to your note dated November 4, 2013 related to connection of the Sfax Desalination Station and in response to the survey questions raised by the Japanese team in charge of the study of subject station, please find below answers related to questions raised:

- 1- Power cutoffs on the 150 kV network are scarce as the HTB (High Voltage) network is meshed. And capacity currently requested by the project is available.
- 2- The maximal power of the transformer that can be connected to the 150 kV network is 40 MVA.
- 3- The distance and the current extension cost of the electrical line depend on the project location. The cost calculation is made based on an underground cable. The following table summarizes the different quantities:

| <u>Site n.</u> | <u>Distance</u> | <u>Extension Cost</u> |
|----------------|-----------------|-----------------------|
| 1              | 2 x 306 km      | 11 million            |
| 3.1            | 2 x 11.1 km     | 34 million            |
| 3.2            | 2 x 15.5 km     | 47 million            |
| 3.3            | 2 x 18.2 km     | 55 million            |
| 5              | 2 x 26 km       | 78 million            |
| 6              | 2 x 35.3 km     | 106 million           |

- 4- Supply will be in double line (incoming/outgoing) from the closest point of the 150 kV network. There will be neither specialized line nor dual supply from a different power plant. However, the line may be partly buried and partly airborne.

**Mohamed Ketata**

**Regional Director**