



Detailed Power Flow around the Sampoor Substation in 2020

Grid condition : 2020 Year
 Generator condition : Thermal maximum
 Load condition : Night peak





Detailed Power Flow around the Sampoor Substation in 2020

Grid condition : 2020 Year
 Generator condition : Thermal maximum
 Load condition : Day peak





Detailed Power Flow around the Sampoor Substation in 2020

Grid condition : 2020 Year
 Generator condition : Hydro maximum
 Load condition : Night peak





Detailed Power Flow around the Sampoor Substation in 2020

Grid condition : 2020 Year
 Generator condition : Hydro maximum
 Load condition : Day peak




Detailed Power Flow around the Sampoor Substation in 2020

Grid condition : 2020 Year
 Generator condition : -----
 Load condition : Off peak




Detailed Power Flow around the Sampoor Substation in 2022

Grid condition : 2022 Year
 Generator condition : Thermal maximum
 Load condition : Night peak




Detailed Power Flow around the Sampoor Substation in 2022

Grid condition : 2022 Year
 Generator condition : Thermal maximum
 Load condition : Day peak




Detailed Power Flow around the Sampoor Substation in 2022

Grid condition : 2022 Year
 Generator condition : Hydro maximum
 Load condition : Night peak




Detailed Power Flow around the Sampoor Substation in 2022

Grid condition : 2022 Year
 Generator condition : Hydro maximum
 Load condition : Day peak




Detailed Power Flow around the Sampoor Substation in 2022

Grid condition : 2022 Year
 Generator condition : -----
 Load condition : Off peak




Detailed Power Flow around the Sampoor Substation in 2024

Grid condition : 2024 Year
 Generator condition : Thermal maximum
 Load condition : Night peak




Detailed Power Flow around the Sampoor Substation in 2024

Grid condition : 2024 Year
 Generator condition : Thermal maximum
 Load condition : Day peak




Detailed Power Flow around the Sampoor Substation in 2024

Grid condition : 2024 Year
 Generator condition : Hydro maximum
 Load condition : Night peak




Detailed Power Flow around the Sampoor Substation in 2024

Grid condition : 2024 Year
 Generator condition : Hydro maximum
 Load condition : Day peak



Detailed Power Flow around the Sampoor Substation in 2024

Grid condition : 2024 Year
 Generator condition : -----
 Load condition : Off peak





Lanka Hydraulic Institute Ltd

*Natural Condition Survey for 400kV Sampur –
Habarana Transmission Line Project*



Final Report

March 2015

Tokyo Electric Power Services Co., Ltd.

| | | | | | |
|--|--|--|---------|-------------|------|
| Client Tokyo Electric Power Services Co., Ltd. | | Client's Representative Mr. Fumiyasu MINAGAWA | | | |
| Project Natural Condition Survey for 400kV Sampur – Habarana Transmission Line Project | | Project No. 1502 | | | |
| Authors Dr. D. P. C. Laknath Mr. K. B. A. Silva Mr. K. Maiyourathan Ms. S. Hewavidana | | Date March 2015 | | | |
| | | Approved by Mr. H. N. R. Perera Dr. K. Raveenthiran | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| Revision | | By | Checked | Approved | Date |
| Key words Meteorological Survey Ground level Survey Hydrological Survey Numerical Simulation | | Classification <input type="checkbox"/> Open <input type="checkbox"/> Internal <input checked="" type="checkbox"/> Proprietary | | | |
| Distribution Tokyo Electric Power Services Co., Ltd. 1-7-12, Shinonome, Koto-ku, Tokyo 135-0062, Japan | | No. of Copies: | | | |
| | | Soft | | Hard | |
| | | 01 | | 03 | |



Lanka Hydraulic Institute Ltd

177, John Rodrigo Mawatha, Katubedda, Moratuwa, Sri Lanka.
Tel. Nos. 2650409 / 2650471 / 2650472-3, Fax No. 2650470 - Email: lhi@lhi.lk

TABLE OF CONTENTS

Chapter 1: INTRODUCTION

| | |
|--------------------------------------|---|
| 1.1. Project Synopsis..... | 1 |
| 1.2. Scope of Service | 1 |
| 1.3. Organization of the Report..... | 2 |

Chapter 2: METEOROLOGICAL SURVEY

| | |
|----------------------------------|----|
| 2.1. Study Area..... | 3 |
| 2.2. Meteorological Survey | 3 |
| 2.3. Wind..... | 5 |
| 2.4. Ambient Temperature..... | 9 |
| 2.5. Relative Humidity..... | 12 |
| 2.6. Rainfall | 15 |
| 2.7. Solar Radiation..... | 17 |
| 2.8. Thunder Days..... | 20 |

Chapter 3: HYDROLOGICAL SURVEY AND INVESTIGATIONS

| | |
|---|----|
| 3.1. Measurement of Elevations at Points LP1- LP11..... | 22 |
| 3.2. Investigation of OHWL and MHWL | 24 |

| | |
|--------------------------------|-----------|
| <i>References</i> | 32 |
|--------------------------------|-----------|

APPENDIX

| | |
|---|----|
| <i>Appendix - 1: Wind Hazard Susceptible Map of Sri Lanka</i> | 33 |
| <i>Appendix - 2: Site Condition during 12th -15th February 2015</i> | 35 |
| <i>Appendix - 3: Control Point Established by Surveying Department</i> | 36 |
| <i>Appendix - 4: Control Points Established by LHI Survey Team</i> | 37 |
| <i>Appendix - 5: Points LP1 – LP11</i> | 40 |

List of Figures

| | |
|---|----|
| Figure 2.1: The Proposed Transmission Line - Route Map | 3 |
| Figure 2.2: Wind Measurements – Weather Stations | 5 |
| Figure 2.3: Wind Rose Diagrams for 2010 – 2014 Period | 9 |
| Figure 2.4: Ambient Temperature Measurements – Weather Stations | 10 |
| Figure 2.5: Relative Humidity Measurements – Weather Stations | 12 |
| Figure 2.6: Rainfall Measurements – Gauging Stations | 15 |
| Figure 2.7: Solar Radiation Measurements – Polonnaruwa Weather Station | 18 |
| Figure 2.8: Thunder Day Measurements – Weather Station | 20 |
| Figure 3.1: Measurement Points (L1 – L11) | 22 |
| Figure 3.2: LB and RB Areas of River along the Transmission Line | 24 |
| Figure 3.3: Natural Features of River Banks along the Transmission Line | 26 |
| Figure 3.4: River Cross Section along the Transmission Line | 27 |
| Figure 3.5: Bathymetry of the River Reach used for 2D Simulations | 28 |
| Figure 3.6: Schematic Diagram Used for MIKE 21 HD Model..... | 29 |
| Figure 3.7: Water Level Variation in Study Area – MIKE21 HD Output | 30 |

List of Tables

| | | |
|------------|--|----|
| Table 2.1 | Expected Details of Meteorological Parameters..... | 4 |
| Table 2.2 | Wind Data Measurements Duration and Availability | 5 |
| Table 2.3 | Annual Maximum, Minimum and Mean Wind Speed..... | 6 |
| Table 2.4 | Temperature Data Measurements Duration and Availability | 10 |
| Table 2.5 | Annual Maximum, Minimum and Mean Temperatures | 11 |
| Table 2.6 | Relative Humidity Measurements Duration and Availability | 12 |
| Table 2.7 | Maximum Relative Humidity at Polonnaruwa in 2014 | 13 |
| Table 2.8 | Maximum Relative Humidity at Trincomalee in 2014 | 14 |
| Table 2.9 | Rainfall Data Measurements Duration and Availability..... | 16 |
| Table 2.10 | Monthly and Annual Total Rainfall Values at 6 Gauging Stations | 16 |
| Table 2.11 | Solar Radiation Data Measurements Duration and Availability | 18 |
| Table 2.12 | Monthly/Daily Total Maximum and Minimum Solar Radiation | 19 |
| Table 2.13 | Hourly Maximum Total and Average Solar Radiation..... | 19 |
| Table 2.14 | Monthly Thunder Days | 21 |
| Table 3.1 | Coordinates of Measurement Points (L1 – L11)..... | 22 |
| Table 3.2 | Water Levels at Point P1 for Different Return Period | 31 |

CHAPTER 1 INTRODUCTION

1.1. Project Synopsis

The Tokyo Electric Power Services Co Ltd. (TEPSCO) is the Consultant for Japan International Cooperation Agency (JICA) for the *Preparatory Study on National Transmission and Distribution Network Development and Efficiency Improvement Project (II)*. In line with the project objectives, Lanka Hydraulic Institute Ltd. (LHI) was awarded consultancy services for “*Natural Condition Survey for 400kV Sampur - Habarana Transmission Line Project*” by TEPSCO on 30th January 2015.

1.2. Scope of Service

The Scope of Service of this project mainly focuses on (1) *Meteorological Survey* (2) *Hydrological Survey and Investigation*.

Meteorological Survey:

Objective: The objective of this task is to collect and analyse of meteorological data, such as wind speed and direction, ambient temperature, humidity, precipitation, solar radiation and thunder days.

Activities:

- Collect wind data at Trincomalee and Polonnaruwa stations for as long as possible period and analyse wind speed for maximum, minimum and mean.
- Collect wind data at Trincomalee and Polonnaruwa stations for a period of three year and analyse wind direction.
- Collect ambient temperature data at Trincomalee and Polonnaruwa stations for as long as possible period and analyse for maximum, minimum and mean of ambient temperature.
- Collect humidity data at Trincomalee and Polonnaruwa stations for a period of one year and analyse for maximum humidity.
- Collect precipitation data at Trincomalee, Polonnaruwa, Palampodaru/Alai Tank, Kantale, Habarana and Kaudulla Wewa stations for a period of five years and analyse for annual precipitation.
- Collect solar radiation data at Trincomalee and Polonnaruwa stations for a period of three years and analyse for maximum solar radiation.
- Collect thunder days data at Trincomalee and Polonnaruwa stations for a period of three years and analyse for mean thunder days.

Output: The analysed data is presented in tabular and graphical formats in this report.

Hydrological Survey and Investigation:

Objective: The objective of this task is to survey the levels at specified points (i.e. LP1 to LP11 points along the transmission line), and investigate the Ordinary High Water Level (OHWL) and Maximum High Water Level (MHWL), where the transmission line crosses the Mahaweli River. LP1 to LP11 locations along the transmission line are explained and illustrated in *Chapter 3*.

Activities: The following activities were carried out under this task;

- Survey the levels of LP1 to LP11 by using DGPS, Auto Level and Total Station.
- Investigate the OHWL and MHWL by using numerical model simulation (*DHI MIKE21 software* was used).

Output: The survey and modelling results are given in tabular and graphical forms.

Under the Scope of Service of LHI, following deliverables are expected to submit to TEPSCO.

- Draft Final Report
- Final Report

The Draft Final Report was submitted to client on 11th March 2015.

1.3. Organization of the Report

The brief descriptions about the content of each chapter of this “*Final Report*” are summarized as follows:

Chapter 1 includes project synopsis, the scope of services and organization of the report.

Chapter 2 explains about the study area, details about meteorological stations and meteorological data. Further, analysis results of each meteorological parameter are also included in this chapter.

Chapter 3 explains about survey results and investigations about HWLs on the basis of numerical simulation and field investigations.

CHAPTER 2 METEOROLOGICAL SURVEY

2.1. Study Area

The project site is located between Sampur in Trincomalee district to Habarana district. The 400kV Sampur – Habarana transmission line starts from Sampur GS, through north of Polonnaruwa district, and ends up at Habarana GS. This transmission line will be aligned in order to connect Sampur GS and Habarana GS. The approximate distance between Sampur GS and Habarana GS is 95 km. The proposed alignment map of the transmission line is shown in *Figure 2.1*.



Figure 2.1: The Proposed Transmission Line - Route Map

2.2. Meteorological Survey

2.2.1. Data Requirement by Client

As explained in the *Scope of Service (i.e. Section 1.2)*, expected details of meteorological parameters around the proposed transmission line with expected durations are tabulated in *Table 2.1*. Data recorded intervals, available periods and percentage availability at corresponding gauging stations are explained separately under each meteorological parameter (*i.e. from 2.3 – 2.8 Sections*).

Table 2.1 Expected Details of Meteorological Parameters

| Item | Data | Minimum Data Collection Period |
|--------------------------------|---|--------------------------------|
| <i>Wind speed</i> | Yearly wind data that based on hourly recorded wind data at a height of 10m at meteorological stations and/or point near transmission line | As long as possible |
| <i>Wind direction</i> | Yearly wind data that based on hourly recorded wind data at a height of 10m at meteorological stations and/or point near transmission line | 3 years |
| <i>Ambient temperature</i> | Yearly ambient temperature data that based on hourly recorded temperature data at meteorological stations and/or point near transmission line | As long as possible |
| <i>Humidity</i> | Yearly humidity data that based on hourly recorded humidity data at meteorological stations and/or point near transmission line | 1 years |
| <i>Amount of precipitation</i> | Yearly precipitation data that were recorded at meteorological stations and/or point near transmission line | 5 years |
| Solar radiation | Yearly solar radiation data that were recorded at meteorological stations and/or point near transmission line | 3 years |
| <i>Thunder days</i> | Yearly thunder days data that were recorded at meteorological stations and/or point near transmission line | 3 years |

2.3. Wind

2.3.1. Stations and Data Availability

Wind speed and directions were measured at Polonnaruwa [7.87^o, 81.05^o] and Trincomalee [8.58^o, 81.25^o] weather stations (see *Figure 2.2*). Even it is expected to collect hourly recorded wind data under the scope, wind speed and directions were recorded only at 8.30 am and 5.30 pm during each day at each station. Further, at each station, average daily wind speed was calculated and given as *Daily Average Wind Run*. Wind data available duration and percentage availability at Polonnaruwa and Trincomalee stations are given in *Table 2.2*.




Figure 2.2: Wind Measurements – Weather Stations

Table 2.2 Wind Data Measurements Duration and Availability

| Met. Parameter | Daily Measurements | Data Availability (Period & Percentage) | | | |
|----------------|---------------------------------|---|------|----------------------|------|
| | | Polonnaruwa | | Trincomalee | |
| | | Period | % | Period | % |
| Wind Speed | 8.30 am, 5.30 pm, Avg. wind Run | (5 Yrs.) 2010 -2014 | 96.2 | (20 Yrs.) 1994 -2014 | 78.7 |
| Wind Direction | 8.30 am, 5.30 pm, Avg. wind Run | (5 Yrs.) 2010 -2014 | 96.2 | (20 Yrs.) 1994 -2014 | 88.1 |
| | | | | (5 Yrs.) 2010 -2014 | 78.3 |

Wind data explained in *Table 2.2* is given with enclosed CDROM in digital format (*i.e. 1.Wind.xlsx*)

2.3.2. Wind Speed

Maximum, minimum and average wind speed of each year at Polonnaruwa and Trincomalee weather stations are given in *Table 2.3*.

Table 2.3 Annual Maximum, Minimum and Mean Wind Speed at (a) Polonnaruwa and (b).Trincomalee Weather Stations

(a) Polonnaruwa

| Year | Speed (m/s) (Annual) | | |
|----------------|----------------------|------------|------------|
| | Average | Maximum | Minimum |
| 2010 | 1.3 | 6.4 | 0.0 |
| 2011 | 1.2 | 6.9 | 0.0 |
| 2012 | 1.4 | 8.4 | 0.0 |
| 2013 | 1.6 | 7.8 | 0.0 |
| 2014 | 1.6 | 8.9 | 0.0 |
| Average | 1.4 | 7.7 | 0.0 |

(b).Trincomalee

| Year | Speed (m/s) (Annual) | | |
|----------------|----------------------|------------|------------|
| | Average | Maximum | Minimum |
| 1994 | 1.0 | 3.5 | 0.0 |
| 1995 | 0.7 | 3.6 | 0.0 |
| 1996 | 1.1 | 9.0 | 0.0 |
| 1997 | 0.4 | 4.8 | 0.0 |
| 1998 | 0.8 | 7.3 | 0.0 |
| 1999 | 2.5 | 8.3 | 0.0 |
| 2000 | 1.8 | 9.6 | 0.0 |
| 2001 | 1.6 | 7.0 | 0.0 |
| 2002 | 2.2 | 7.2 | 0.0 |
| 2003 | 2.3 | 8.7 | 0.0 |
| 2004 | 2.1 | 7.6 | 0.0 |
| 2005 | 2.2 | 8.1 | 0.0 |
| 2006 | 2.1 | 8.5 | 0.0 |
| 2007 | 2.3 | 10.3 | 0.0 |
| 2008 | 2.0 | 6.2 | 0.0 |
| 2009 | 2.4 | 9.3 | 0.0 |
| 2010 | 1.8 | 4.6 | 0.0 |
| 2011 | NA | NA | NA |
| 2012 | 2.7 | 8.2 | 0.5 |
| 2013 | 2.3 | 6.3 | 0.0 |
| 2014 | 2.4 | 7.2 | 0.0 |
| Average | 1.8 | 7.3 | 0.0 |


NA = Not Available


Maximum wind speed at Polonnaruwa and Trincomalee weather stations for the considered period are 8.9 m/s and 10.3 m/s respectively (*please note that wind data is not available at Trincomalee weather station for year 2011*). According to average and maximum values of wind hazard susceptible map of Sri Lanka prepared by Disaster Management Center of Sri Lanka, average wind speed in Polonnaruwa varies between 8.2 m/s – 10.3 m/s. Further, for the same area, maximum wind speed varies between 12.7 m/s – 18.0 m/s (*see Appendix 1*). This analysis was carried out by “Weather Research and Forecasting (WRF)” model using NCEP/NCAR re-analysis data. The spatial resolution of the model is 10 X 10 km. Data between 1958 – 2009 period has been considered for the analysis. Comparing measured wind speeds and simulated wind speed, simulated values are higher than measured values. In case of measured wind data (by Meteorological Department in Sri Lanka), wind speed was recorded only at 8.30 am and 5.30 pm during each day. Our analysis includes only above values. So there is a possibility of not recording actual maximum wind speed of each day. Further, for the provided hazard map by *Disaster Management Center of Sri Lanka*, they have considered data from 1958 – 2009 period. However, for our analysis we have only considered 2010 – 2014 period considering the measured data availability in Polonnaruwa weather station. These reasons could cause the discrepancy between Meteorological Department recorded and WRF simulated values.

2.3.3. Wind Direction

Wind directions at Polonnaruwa and Trincomalee weather stations for the period of 2010 – 2014 are illustrated by wind rose diagrams (*Figure 2.3*). A wind rose is a graphic tool used by meteorologists to give a succinct view of how wind speed and direction are typically distributed at a particular location.


(a). Polonnaruwa





As seen in *Figure 2.3 (a)*, it is clear that wind direction is dominant between 210⁰ N – 240⁰ N directions at Polonnaruwa weather station. Additionally, there is a considerable amount of wind has blown from 0⁰ N – 30⁰ N directions.

(b).Trincomalee



Data - Not Available

2011




Figure 2.3: Wind Rose Diagrams for 2010 - 2014 Period at (a). Polonnaruwa (b). Trincomalee Weather Stations

As seen in *Figure 2.3 (b)*, we can see that wind has blown from various directions at Trincomalee weather station. High percentage of wind has blown between 210° N – 300° N directions. Further, wind has come from 0° N – 150° N direction at Trincomalee weather station in each year. This could be resulted due to the effect of wind coming from sea side.

2.4. Ambient Temperature

2.4.1. Stations and Data Availability

Daily maximum and minimum temperature values were measured at Polonnaruwa [7.87° , 81.05°] and Trincomalee [8.58° , 81.25°] weather stations (see *Figure 2.4*). At each station, maximum and minimum temperature values were recorded during each day. Mean temperature was calculated by averaging maximum and minimum temperature values. Temperature data available duration and percentage availability at Polonnaruwa and Trincomalee stations are given in *Table 2.4*.

Table 2.4 Temperature Data Measurements Duration and Availability

| Met. Parameter | Interval | Data Availability (Period & Percentage) | | | |
|----------------------------|----------|---|------|----------------------|------|
| | | Polonnaruwa | | Trincomalee | |
| | | Period | % | Period | % |
| Ambient Temperature (Max.) | Daily | (6 Yrs.) 2009 -2014 | 98.6 | (21 Yrs.) 1994 -2014 | 95.0 |
| Ambient Temperature (Min.) | Daily | (6Yrs.) 2009 -2014 | 98.5 | (21 Yrs.) 1994 -2014 | 95.6 |



Figure 2.4: Ambient Temperature Measurements – Weather Stations

Temperature data explained in *Table 2.4* is given with enclosed CDROM in digital format (*i.e. 2.Temperature.xlsx*)

Annual maximum, minimum and mean temperature values for the available periods at Polonnaruwa and Trincomalee weather stations are given in *Table 2.5*.

Table 2.5 Annual Maximum, Minimum and Mean Temperatures at (a) Polonnaruwa and (b).Trincomalee Weather Stations

(a). Polonnaruwa

| Polonnaruwa | | | |
|----------------|----------------|----------------|---------------|
| Year | Max. Temp (°C) | Min. Temp (°C) | Avg.Temp (°C) |
| 2009 | 38.5 | 14.4 | 28.5 |
| 2010 | 37.3 | 17.9 | 28.1 |
| 2011 | 38.3 | 16.5 | 28.3 |
| 2012 | 39.0 | 18.0 | 28.8 |
| 2013 | 38.2 | 18.2 | 28.6 |
| 2014 | 38.5 | 16.4 | 28.6 |
| Average | 38.3 | 16.9 | 28.5 |

(b).Trincomalee

| Trincomalee | | | |
|----------------|----------------|----------------|---------------|
| Year | Max. Temp (°C) | Min. Temp (°C) | Avg.Temp (°C) |
| 1994 | 38.2 | 21.6 | 28.7 |
| 1995 | 37.8 | 22.1 | 28.9 |
| 1996 | 39.6 | 21.2 | 28.7 |
| 1997 | 39.0 | 20.1 | 28.2 |
| 1998 | 39.3 | 22.4 | 29.4 |
| 1999 | 39.3 | 20.8 | 28.7 |
| 2000 | 38.2 | 22.0 | 28.9 |
| 2001 | 39.0 | 20.7 | 28.9 |
| 2002 | 39.1 | 21.6 | 29.2 |
| 2003 | 38.4 | 21.9 | 29.0 |
| 2004 | 39.2 | 20.9 | 28.7 |
| 2005 | 38.2 | 20.0 | 28.9 |
| 2006 | 38.3 | 20.7 | 29.1 |
| 2007 | 38.2 | 19.0 | 28.7 |
| 2008 | 38.7 | 21.1 | 28.6 |
| 2009 | 38.4 | 19.6 | 28.9 |
| 2010 | 38.6 | 19.0 | 29.2 |
| 2011 | 37.4 | 23.4 | 30.0 |
| 2012 | 39.5 | 21.2 | 29.1 |
| 2013 | 38.3 | 20.6 | 28.5 |
| 2014 | 39.1 | 20.0 | 28.8 |
| Average | 38.7 | 20.9 | 28.9 |

From above analysis, it can be identified that maximum temperature at both stations has reached to 39°C for the considered period. Also, it clear that minimum temperature at Trincomalee is higher than Polonnaruwa weather stations for the considered common period (*i.e.* 2009 – 2014).

2.5. Relative Humidity

2.5.1. Stations and Data Availability

Daily maximum relative humidity values were measured at Polonnaruwa [7.87°, 81.05°] and Trincomalee [8.58°, 81.25°] weather stations for year 2014 (see Figure 2.5). At each station, maximum and minimum relative humidity values were recorded during each day. Hourly recorded relative humidity data is not available at both stations. In line with the Scope of the Service, maximum values of relative humidity data were considered for the analysis. Relative humidity data available duration and percentage availability at Polonnaruwa and Trincomalee stations are given in Table 2.6.



Figure 2.5: Relative Humidity Measurements – Weather Stations

Table 2.6 Relative Humidity Measurements Duration and Availability

| Met. Parameter | Interval | Data Availability (Period & Percentage) | | | |
|--------------------------|----------|---|------|---------------|------|
| | | Polonnaruwa | | Trincomalee | |
| | | Period | % | Period | % |
| Relative Humidity (Max.) | Daily | (1 Yrs.) 2014 | 83.3 | (1 Yrs.) 2014 | 66.3 |

Relative humidity data explained in Table 2.6 is given with enclosed CDROM in digital format (i.e. 3.Relative Humidity.xlsx). Daily maximum relative humidity values for year 2014 at Polonnaruwa and Trincomalee weather stations are given in Table 2.7 and Table 2.8 respectively.

Table 2.7 Maximum Relative Humidity at Polonnaruwa in 2014

| Year | Day | Daily Maximum Relative Humidity | | | | | | | | | | | |
|----------------|-----|---------------------------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| | | January | February | March | April | May | June | July | August | September | October | November | December |
| 2014 | 1 | 96 | 91 | 96 | 92 | 97 | 84 | 67 | 68 | NA | 96 | 87 | NA |
| 2014 | 2 | 93 | 97 | 96 | 92 | 97 | 76 | 69 | 64 | NA | 96 | 88 | NA |
| 2014 | 3 | 92 | 96 | 94 | 93 | 95 | 82 | 68 | 64 | NA | 93 | 92 | NA |
| 2014 | 4 | 86 | 98 | 95 | 86 | 97 | 69 | 68 | 64 | NA | 95 | 92 | NA |
| 2014 | 5 | 92 | 97 | 95 | 89 | 92 | 71 | 65 | 64 | NA | 94 | 93 | NA |
| 2014 | 6 | 98 | 96 | 95 | 93 | 95 | 66 | 65 | 65 | NA | 75 | 93 | NA |
| 2014 | 7 | 94 | 97 | 95 | 90 | 89 | 66 | 67 | 81 | NA | 69 | 94 | NA |
| 2014 | 8 | 94 | 97 | 94 | 91 | 96 | 68 | 67 | 59 | NA | 89 | 95 | NA |
| 2014 | 9 | 93 | 95 | 96 | 88 | 96 | 64 | 66 | 64 | NA | 77 | 96 | NA |
| 2014 | 10 | 97 | 96 | 96 | 89 | 91 | 64 | 65 | 63 | NA | 59 | 96 | NA |
| 2014 | 11 | 96 | 95 | 96 | 90 | 92 | 68 | 64 | 65 | NA | 62 | 95 | NA |
| 2014 | 12 | 94 | 95 | 96 | 90 | 91 | 67 | 65 | 63 | NA | 61 | 98 | NA |
| 2014 | 13 | 97 | 97 | 97 | 91 | 88 | 67 | 64 | 63 | NA | 93 | 98 | NA |
| 2014 | 14 | 97 | 96 | 93 | 93 | 77 | 66 | 59 | 57 | NA | 92 | 97 | NA |
| 2014 | 15 | 100 | 93 | 97 | 90 | 81 | 72 | 63 | 79 | NA | 94 | 94 | NA |
| 2014 | 16 | 99 | 93 | 94 | 87 | 78 | 65 | 71 | 84 | NA | 96 | 97 | NA |
| 2014 | 17 | 96 | 97 | 94 | 92 | 85 | 70 | 64 | 94 | NA | 97 | 98 | NA |
| 2014 | 18 | 97 | 97 | 94 | 92 | 90 | 64 | 64 | 96 | NA | 98 | 97 | NA |
| 2014 | 19 | 98 | 95 | 97 | 90 | 90 | 68 | 63 | 96 | NA | 98 | 99 | NA |
| 2014 | 20 | 97 | 96 | 96 | 92 | 93 | 67 | 67 | 92 | NA | 99 | 99 | NA |
| 2014 | 21 | 96 | 94 | 96 | 93 | 68 | 68 | 65 | 96 | NA | 96 | 88 | NA |
| 2014 | 22 | 97 | 96 | 93 | 93 | 60 | 62 | 65 | 75 | NA | 95 | 99 | NA |
| 2014 | 23 | 98 | 97 | 96 | 94 | 72 | 65 | 67 | 72 | NA | 97 | 99 | NA |
| 2014 | 24 | 97 | 94 | 94 | 92 | 72 | 64 | 67 | 90 | NA | 98 | 98 | NA |
| 2014 | 25 | 95 | 94 | 97 | 87 | 89 | 66 | 68 | 89 | NA | 95 | 97 | NA |
| 2014 | 26 | 96 | 99 | 93 | 87 | 78 | 68 | 66 | 67 | NA | 96 | 99 | NA |
| 2014 | 27 | 96 | 100 | 95 | 88 | 97 | 79 | 67 | 79 | NA | 96 | 99 | NA |
| 2014 | 28 | 99 | 96 | 95 | 95 | 98 | 65 | 64 | 68 | NA | 95 | 95 | NA |
| 2014 | 29 | 99 | | 96 | 97 | 96 | 64 | 68 | 67 | NA | 96 | 91 | NA |
| 2014 | 30 | 97 | | 94 | 98 | 74 | 67 | 63 | 66 | NA | 95 | 98 | NA |
| 2014 | 31 | 97 | | 90 | | 75 | | 64 | 66 | | 92 | | NA |
| Average | | 96 | 96 | 95 | 91 | 87 | 68 | 66 | 74 | NA | 90 | 95 | NA |

NA = Not Available

Yearly Average = 86

Table 2.8 Maximum Relative Humidity at Trincomalee in 2014

| Year | Day | Daily Maximum Relative Humidity | | | | | | | | | | | |
|----------------|-----|---------------------------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| | | January | February | March | April | May | June | July | August | September | October | November | December |
| 2014 | 1 | 82 | 85 | 85 | 88 | 89 | 87 | NA | NA | 77 | 91 | NA | NA |
| 2014 | 2 | 88 | 84 | 86 | 91 | 90 | 81 | NA | NA | 73 | 97 | NA | NA |
| 2014 | 3 | 95 | 78 | 84 | 87 | 92 | 80 | NA | NA | 76 | 79 | NA | NA |
| 2014 | 4 | 97 | 76 | 83 | 86 | 96 | 80 | NA | NA | 81 | 0 | NA | NA |
| 2014 | 5 | 98 | 75 | 84 | 88 | 86 | 77 | NA | NA | 71 | 95 | NA | NA |
| 2014 | 6 | 98 | 73 | 84 | 86 | 87 | 77 | NA | NA | 0 | 80 | NA | NA |
| 2014 | 7 | 96 | 72 | 84 | 85 | 94 | 73 | NA | NA | 82 | 83 | NA | NA |
| 2014 | 8 | 95 | 72 | 79 | 86 | 93 | 73 | NA | NA | 74 | 83 | NA | NA |
| 2014 | 9 | 84 | 71 | 78 | 85 | 94 | 74 | NA | NA | 73 | 88 | NA | NA |
| 2014 | 10 | 88 | 81 | 75 | 86 | 86 | 75 | NA | NA | 73 | 64 | NA | NA |
| 2014 | 11 | 89 | 77 | 74 | 87 | 86 | 75 | NA | NA | 92 | 0 | NA | NA |
| 2014 | 12 | 92 | 89 | 78 | 88 | 88 | 75 | NA | NA | 97 | 87 | NA | NA |
| 2014 | 13 | 95 | 83 | 66 | 87 | 83 | 79 | NA | NA | 0 | 87 | NA | NA |
| 2014 | 14 | 93 | 86 | 72 | 86 | 84 | 78 | NA | NA | 83 | 89 | NA | NA |
| 2014 | 15 | 93 | 85 | 78 | 88 | 82 | 79 | NA | NA | 77 | 93 | NA | NA |
| 2014 | 16 | 89 | 89 | 82 | 81 | 76 | 75 | NA | NA | 70 | 94 | NA | NA |
| 2014 | 17 | 77 | 83 | 82 | 83 | 72 | 77 | NA | NA | 72 | 98 | NA | NA |
| 2014 | 18 | 92 | 84 | 88 | 88 | 79 | 76 | NA | NA | 73 | 0 | NA | NA |
| 2014 | 19 | 84 | 79 | 93 | 89 | 80 | 80 | NA | NA | 64 | 97 | NA | NA |
| 2014 | 20 | 87 | 74 | 90 | 87 | 83 | 78 | NA | NA | 0 | 94 | NA | NA |
| 2014 | 21 | 82 | 80 | 92 | 87 | 79 | 78 | NA | NA | 93 | 91 | NA | NA |
| 2014 | 22 | 88 | 84 | 89 | 90 | 74 | 78 | NA | NA | 86 | 91 | NA | NA |
| 2014 | 23 | 83 | 89 | 90 | 84 | 80 | 77 | NA | NA | 85 | 95 | NA | NA |
| 2014 | 24 | 76 | 86 | 89 | 83 | 83 | 76 | NA | NA | 85 | 87 | NA | NA |
| 2014 | 25 | 72 | 79 | 81 | 83 | 81 | 76 | NA | NA | 96 | 0 | NA | NA |
| 2014 | 26 | 75 | 97 | 82 | 86 | 78 | 73 | NA | NA | 98 | 93 | NA | NA |
| 2014 | 27 | 81 | 91 | 81 | 85 | 85 | 79 | NA | NA | 0 | 89 | NA | NA |
| 2014 | 28 | 86 | 76 | 90 | 89 | 88 | 79 | NA | NA | 98 | 94 | NA | NA |
| 2014 | 29 | 93 | | 88 | 94 | 81 | 77 | NA | NA | 91 | 95 | NA | NA |
| 2014 | 30 | 95 | | 88 | 90 | 82 | 80 | NA | NA | 92 | 93 | NA | NA |
| 2014 | 31 | 90 | | 86 | | 84 | | NA | NA | | 90 | | NA |
| Average | | 88 | 81 | 83 | 87 | 84 | 77 | NA | NA | 71 | 78 | NA | NA |

NA = Not Available

Yearly Average = 81

As seen in *Table 2.7* and *Table 2.8*, maximum relative humidity at Polonnaruwa and Trincomalee weather stations were recorded as 100 and 98 respectively. Also, yearly average value at Polonnaruwa and Trincomalee weather stations were calculated as 86 and 81 respectively. Generally, relative humidity at Polonnaruwa is higher than Trincomalee weather station.

2.6. Rainfall

2.6.1. Stations and Data Availability

Rainfall data at 6 gauging stations in the vicinity of the proposed transmission line were collected. Coordinates of selected Polonnaruwa, Trincomalee Habarana, Kaudulla, Kanthale and Palampoddar gauging stations are $[7.87^{\circ}, 81.05^{\circ}]$, $[8.58^{\circ}, 81.25^{\circ}]$, $[8.03^{\circ}, 80.75^{\circ}]$, $[8.13^{\circ}, 80.93^{\circ}]$, $[8.35^{\circ}, 80.98^{\circ}]$ and $[8.55^{\circ}, 81.07^{\circ}]$ respectively (see *Figure 2.6*). At each station, daily rainfall was recorded. Rainfall data available duration and percentage availability at 6 gauging stations are given in *Table 2.9*.



Figure 2.6: Rainfall Measurements – Gauging Stations

Table 2.9 Rainfall Data Measurements Duration and Availability

| Met. Parameter | Interval | Data Availability (Period & Percentage) | | |
|----------------|----------|---|---------------------|-------|
| | | Station NM | Period | % |
| Rainfall | Daily | Polonnaruwa | (6 Yrs.) 2009 -2014 | 98.6 |
| | Daily | Trincomalee | (5 Yrs.) 2010 -2014 | 100.0 |
| | Daily | Palampoddiar RFGS | (5 Yrs.) 2010 -2014 | 91.7 |
| | Daily | Kanthale RFGS | (5 Yrs.) 2010 -2014 | 95.0 |
| | Daily | Kaudulla RFGS | (5 Yrs.) 2010 -2014 | 89.9 |
| | Daily | Habarana RFGS | (5 Yrs.) 2010 -2014 | 95.0 |

Rainfall data explained in *Table 2.9* is given with enclosed CDROM in digital format (*i.e. 4.Rainfall.xlsx*). Monthly and annual total rainfall values for the considered periods at 6 gauging stations are tabulated in *Table 2.10*.

Table 2.10 Monthly and Annual Total Rainfall Values at 6 Gauging Stations**(a). Polonnaruwa**

| Year | Polonnaruwa-Rainfall (mm) | | | | | | | | | | | | |
|----------------|---------------------------|------------|-----------|------------|-----------|----------|-----------|-----------|-----------|------------|------------|------------|-------------|
| | Jan. | Feb. | Mar. | Apr. | May | Jun. | Jul. | Aug. | Sep. | Oct. | Nov. | Dec. | Annual Tot. |
| 2009 | - | 1 | 161 | 247 | 21 | 0 | 35 | 80 | 20 | 105 | 301 | 544 | 1515 |
| 2010 | 123 | 29 | 103 | 247 | 242 | 0 | 91 | 92 | 245 | 183 | 334 | 81 | 1770 |
| 2011 | 663 | 560 | 45 | 151 | 2 | 0 | 39 | 81 | 7 | 735 | 519 | 360 | 3160 |
| 2012 | 7 | 239 | 24 | 63 | 0 | 0 | 67 | 4 | 32 | 550 | 249 | 661 | 1896 |
| 2013 | 390 | 162 | 207 | 44 | 108 | 0 | 12 | 68 | 12 | 39 | 143 | 228 | 1414 |
| 2014 | 270 | 62 | 5 | 58 | 138 | 0 | 0 | 51 | 101 | 319 | 508 | 1130 | 2642 |
| Average | 291 | 175 | 91 | 135 | 85 | 0 | 41 | 62 | 70 | 322 | 343 | 500 | 2066 |

(b). Trincomalee

| Year | Trincomalee-Rainfall (mm) | | | | | | | | | | | | |
|----------------|---------------------------|------------|-----------|-----------|-----------|----------|-----------|-----------|------------|------------|------------|------------|-------------|
| | Jan. | Feb. | Mar. | Apr. | May | Jun. | Jul. | Aug. | Sep. | Oct. | Nov. | Dec. | Ann. Tot. |
| 2010 | 48 | 4 | 3 | 2 | 42 | 19 | 23 | 96 | 197 | 71 | 292 | 622 | 1419 |
| 2011 | 817 | 481 | 44 | 197 | 1 | 1 | 34 | 80 | 32 | 548 | 352 | 320 | 2907 |
| 2012 | 13 | 156 | 21 | 13 | 1 | 0 | 16 | 4 | 231 | 597 | 181 | 590 | 1823 |
| 2013 | 200 | 355 | 239 | 3 | 132 | 1 | 65 | 93 | 2 | 35 | 177 | 190 | 1493 |
| 2014 | 164 | 83 | 5 | 2 | 57 | 5 | 25 | 120 | 108 | 160 | 430 | 532 | 1691 |
| Average | 249 | 216 | 62 | 43 | 47 | 5 | 33 | 79 | 114 | 282 | 286 | 451 | 1867 |

(c). Habarana

| Year | Habarana-Rainfall (mm) | | | | | | | | | | | | |
|----------------|------------------------|------------|-----------|------------|-----------|----------|-----------|-----------|-----------|------------|------------|------------|-------------|
| | Jan. | Feb. | Mar. | Apr. | May | Jun. | Jul. | Aug. | Sep. | Oct. | Nov. | Dec. | Annual Tot. |
| 2010 | 45 | 65 | 44 | 89 | 72 | 0 | 19 | 74 | 171 | 62 | 350 | 355 | 1346 |
| 2011 | 617 | 441 | 132 | 162 | 0 | 0 | 6 | 10 | 8 | 400 | 470 | 303 | 2548 |
| 2012 | - | 179 | 58 | 99 | 4 | 11 | 0 | 2 | 3 | 509 | 133 | 550 | - |
| 2013 | 275 | 154 | 130 | 89 | 74 | 0 | 79 | 90 | 26 | 83 | 122 | 124 | 1245 |
| 2014 | 248 | 20 | 0 | 140 | 79 | 0 | 0 | 15 | 261 | 379 | - | - | - |
| Average | 296 | 172 | 73 | 116 | 46 | 2 | 21 | 38 | 94 | 286 | 269 | 333 | 1713 |

(d). Kaudulla

| Year | Kaudulla-Rainfall (mm) | | | | | | | | | | | | |
|----------------|------------------------|------------|-----------|-----------|-----------|----------|-----------|-----------|-----------|------------|------------|------------|-------------|
| | Jan. | Feb. | Mar. | Apr. | May | Jun. | Jul. | Aug. | Sep. | Oct. | Nov. | Dec. | Annual Tot. |
| 2010 | 7 | 47 | 34 | 126 | 107 | 0 | 70 | 100 | 165 | 224 | 339 | 418 | 1637 |
| 2011 | 671 | 437 | 66 | 81 | 0 | 0 | 86 | 0 | 0 | 621 | 451 | | - |
| 2012 | - | 99 | 8 | 125 | 0 | 0 | 0 | 0 | 8 | 672 | 132 | 625 | - |
| 2013 | 413 | 177 | 166 | 58 | 146 | 25 | 25 | 14 | 0 | 246 | 57 | 114 | 1440 |
| 2014 | 140 | 69 | - | 102 | 113 | 0 | 0 | 24 | 201 | - | - | - | - |
| Average | 308 | 166 | 68 | 98 | 73 | 5 | 36 | 28 | 75 | 441 | 245 | 386 | 1539 |

(e). Kanthale

| Year | Kanthale-Rainfall (mm) | | | | | | | | | | | | |
|----------------|------------------------|------------|-----------|------------|------------|----------|-----------|-----------|-----------|------------|------------|------------|-------------|
| | Jan. | Feb. | Mar. | Apr. | May | Jun. | Jul. | Aug. | Sep. | Oct. | Nov. | Dec. | Annual Tot. |
| 2010 | 19 | 24 | 3 | 58 | 124 | 0 | 137 | 164 | 155 | 123 | 474 | 540 | 1820 |
| 2011 | 661 | 607 | 119 | 106 | 15 | 0 | 67 | 57 | 37 | 722 | 510 | 280 | 3181 |
| 2012 | 11 | 145 | 28 | 299 | 39 | 0 | 20 | 0 | - | 682 | 168 | 767 | - |
| 2013 | 239 | 288 | 221 | 111 | 154 | 0 | 5 | 34 | 0 | 104 | 190 | 158 | 1503 |
| 2014 | 225 | 63 | 0 | 29 | 267 | 0 | 0 | 118 | 140 | 385 | - | - | - |
| Average | 231 | 226 | 74 | 120 | 120 | 0 | 46 | 75 | 83 | 403 | 335 | 437 | 2168 |

(f). Palampoddiar

| Year | Palampoddiar-Rainfall (mm) | | | | | | | | | | | | |
|----------------|----------------------------|------------|-----------|-----------|-----------|----------|-----------|-----------|------------|------------|------------|------------|-------------|
| | Jan. | Feb. | Mar. | Apr. | May | Jun. | Jul. | Aug. | Sep. | Oct. | Nov. | Dec. | Annual Tot. |
| 2010 | 44 | 32 | 70 | - | 202 | 13 | 87 | 196 | 334 | 118 | 462 | 804 | - |
| 2011 | 531 | 484 | 0 | 56 | 0 | 0 | 70 | 121 | 47 | 969 | 722 | 469 | 3469 |
| 2012 | 12 | 145 | 12 | 243 | 15 | - | 55 | 0 | 112 | 554 | 255 | 764 | - |
| 2013 | 201 | 369 | 196 | 28 | 107 | - | 1 | 21 | 1 | 53 | 154 | 187 | - |
| 2014 | 158 | 75 | 16 | 39 | 90 | 0 | 1 | 103 | 89 | 314 | - | - | - |
| Average | 189 | 221 | 59 | 92 | 83 | 4 | 43 | 88 | 116 | 402 | 398 | 556 | 3469 |

It is clear that highest rainfall has occurred during October to February period at all stations. This could be resulted due to the north-east and inter monsoon effects. Rainfall amount during June and July months are identified as lower than other months. Out of all stations, rainfall at Polonnaruwa and Kanthale stations are higher than other stations (*NB: Palampoddiar GS was excluded considering non data availability*). In 2011, comparatively high rainfall has occurred at all stations.

2.7. Solar Radiation

2.7.1. Stations and Data Availability

Solar radiation is radiant energy emitted by the sun. The solar radiation is expressed in watts per square meter (W/m^2) and the total amount of solar radiation is expressed in joules per square meter (J/m^2). Solar radiation values are available only at Polonnaruwa weather stations [7.87^0 , 81.05^0] in the vicinity of the proposed transmission line (see *Figure 2.7*). For the period of July 2011 – September 2012, total solar radiation (e.g. hourly, monthly) was

recorded by Meteorological Department. Solar radiation data available duration and percentage availability at Polonnaruwa station are given in *Table 2.11*.



Figure 2.7: Solar Radiation Measurements – Polonnaruwa Weather Station

Table 2.11 Solar Radiation Data Measurements Duration and Availability

| Met. Parameter | Interval | Data Availability (Period & Percentage) at Polonnaruwa | |
|------------------------------------|----------------|--|------|
| | | Period | % |
| Solar Radiation Total/Max./Min. | Monthly/hourly | (1 Yrs.) 2011/7 - 2012/9 | 93.3 |

Solar radiation data explained in *Table 2.11* is given with enclosed CDROM in digital format (i.e. *5.Solar Radiation.xlsx*).

Total solar radiation values for the considered periods at Polonnaruwa weather stations are given in *Table 2.12*. Generally, Meteorological Department records total solar radiation values (i.e. not an instantaneously values). In each hour, Meteorological Department records total solar radiation. Considering total of each day of each month, maximum and minimum daily total solar radiation is identified. Further, total monthly solar radiation is calculated (*Table 2.12*). Thus, considering the daily total, maximum solar radiation was identified as 27 MJ/m² for the considered period.

Table 2.12 Monthly/Daily Total Maximum and Minimum Solar Radiation

| Year and Month | Solar Radiation(MJ/m ²) | | |
|----------------|-------------------------------------|------------------------------------|------------------------------------|
| | Total (Monthly total) ¹ | Maximum (Daily total) ² | Minimum (Daily total) ² |
| 2011-07 | 553 | 25 | 0 |
| 2011-08 | 708 | 26 | 14 |
| 2011-09 | 680 | 26 | 13 |
| 2011-10 | 561 | 24 | 8 |
| 2011-11 | 430 | 21 | 3 |
| 2011-12 | NA | NA | NA |
| 2012-01 | 563 | 22 | 14 |
| 2012-02 | 476 | 23 | 4 |
| 2012-03 | 680 | 26 | 16 |
| 2012-04 | 612 | 27 | 14 |
| 2012-05 | 679 | 27 | 16 |
| 2012-06 | 648 | 25 | 13 |
| 2012-07 | 691 | 26 | 12 |
| 2012-08 | 710 | 26 | 16 |
| 2012-09 | 642 | 26 | 16 |
| Average | 617 | 25 | 11 |

Table 2.13 Hourly Maximum Total and Average Solar Radiation

| Date | Hour of the Maximum Solar Radiation Received | Solar Radiation | |
|----------------|--|-------------------------------------|------------------|
| | | (MJ/m ²) (Hourly Total) | W/m ² |
| 7/20/2011 | 12-13hrs | 3.45 | 958 |
| 8/23/2011 | 12-13hrs | 3.54 | 983 |
| 9/17/2011 | 12-13hrs | 3.60 | 1000 |
| 10/17/2011 | 11-12hrs | 3.44 | 956 |
| 11/13/2011 | 10-11hrs | 3.06 | 850 |
| 2011-12 | NA | NA | NA |
| 1/1/2012 | 12-13hrs | 3.22 | 894 |
| 2/11/2012 | 11-12hrs | 3.56 | 989 |
| 3/24/2012 | 12-13hrs | 3.54 | 983 |
| 4/5/2012 | 12-13hrs | 3.67 | 1019 |
| 5/3/2012 | 11-12hrs | 3.62 | 1006 |
| 6/23/2012 | 11-12hrs | 3.28 | 911 |
| 7/30/2012 | 11-12hrs | 3.47 | 964 |
| 8/12/2012 | 12-13hrs | 3.49 | 969 |
| 9/2/2012 | 12-13hrs | 3.48 | 967 |
| Average | | 3.46 | 961 |

In Table 2.12, MJ (Mega Joules) values refer to “Energy”. To calculate solar radiation in W (Watt), referring “Power”, it can be approximated by dividing MJ/m² values by corresponding time period. For this purpose, maximum “hourly” total solar radiation of each month in MJ/m² was used. Assuming constant solar radiation throughout the considered one hour of period, solar radiation was calculated in W/m², dividing MJ/m² by hour of time (*i.e.* 60 x 60 Seconds) (See Table 2.13).

2.8. Thunder Days

2.8.1. Stations and Data Availability

Thunder days were measured at Polonnaruwa [7.87^o, 81.05^o] and Trincomalee [8.58^o, 81.25^o] weather stations for 2011 – 2013 periods (see Figure 2.8). Thunder (or lightning) is counted during 24 hours of each day. If 1 or more thunder (or lightning) occurs during a day, that day is considered as a “Thunder Day”. Thus, thunder days of each month was counted. Thunder days data available duration and percentage availability at Polonnaruwa and Trincomalee stations are given in Table 2.13.

Table 2.13 Thunder Day Data Measurements Duration and Availability

| Met. Parameter | Interval | Data Availability (Period & Percentage) | | | |
|----------------|-------------------------------|---|-------|----------------------|-------|
| | | Polonnaruwa | | Trincomalee | |
| | | Period | % | Period | % |
| Thunder Days | Availability: Monthly only | (3 Yrs.) 2011 - 2013 | 100.0 | (3 Yrs.) 2011 - 2013 | 100.0 |



Figure 2.8: Thunder Day Measurements – Weather Station

Thunder days data explained in Table 2.13 is given with enclosed CDROM in digital format (6.Thunder days.xlsx). Monthly thunder day values for 2011 - 2013 periods at Polonnaruwa and Trincomalee stations are given in Table 2.14. Except 2011, yearly average thunder days at both stations were calculated as 5. Further, number of thunder days at Polonnaruwa and Trincomalee during April and October months are higher than other months for 2011 – 2013 periods.

Table 2.14 Monthly Thunder Days at (a) Polonnaruwa and (b).Trincomalee Weather Stations

(a). Polonnaruwa

| Month | Year | | | Monthly Average |
|----------------|----------|----------|----------|-----------------|
| | 2011 | 2012 | 2013 | |
| January | 5 | 0 | 4 | 3 |
| February | 1 | 4 | 2 | 2 |
| March | 6 | 2 | 9 | 6 |
| April | 12 | 15 | 16 | 14 |
| May | 3 | 1 | 3 | 2 |
| June | 0 | 0 | 0 | 0 |
| July | 2 | 5 | 1 | 3 |
| August | 2 | 2 | 3 | 2 |
| September | 1 | 5 | 3 | 3 |
| October | 19 | 15 | 9 | 14 |
| November | 9 | 3 | 7 | 6 |
| December | 4 | 6 | 0 | 3 |
| Average | 5 | 5 | 5 | 5 |

(b). Trincomalee

| Month | Year | | | Monthly Average |
|----------------|----------|----------|----------|-----------------|
| | 2011 | 2012 | 2013 | |
| January | NA | 2 | 1 | 2 |
| February | 6 | 8 | 0 | 5 |
| March | 2 | 3 | 0 | 2 |
| April | 24 | 8 | 5 | 12 |
| May | 3 | 8 | 10 | 7 |
| June | 0 | 0 | 0 | 0 |
| July | 8 | 4 | 5 | 6 |
| August | 4 | 10 | 10 | 8 |
| September | 12 | 3 | 7 | 7 |
| October | 19 | 6 | 9 | 11 |
| November | 3 | 7 | 7 | 6 |
| December | 10 | 1 | 1 | 4 |
| Average | 8 | 5 | 5 | 6 |

NA = Not Available

CHAPTER 3

HYDROLOGICAL SURVEY AND INVESTIGATIONS

3.1. Measurement of Elevations at Points LP1- LP11

3.1.1. Details of Points

Details of the expected measurement points (i.e. LP1 – LP 11) are given in *Figure 3.1* and *Table 3.1*.




Figure 3.1: Measurement Points (L1 – L11)

Table 3.1 Coordinates of Measurement Points (L1 – L11)

| Point | Coordinate(UTM) | | Note |
|-------|-----------------|---------------|------|
| LP1 | 522446.43 m E | 931697.93 m N | AP38 |
| LP2 | 522836.37 m E | 931475.79 m N | |
| LP3 | 523226.75 m E | 931252.33 m N | |
| LP4 | 523809.56 m E | 930918.48 m N | |
| LP5 | 524347.96 m E | 930611.15 m N | AP39 |
| LP6 | 524768.70 m E | 930456.42 m N | |
| LP7 | 525190.93 m E | 930300.70 m N | |
| LP8 | 525612.87 m E | 930144.29 m N | |
| LP9 | 526033.98 m E | 929987.60 m N | |
| LP10 | 526455.24 m E | 929832.80 m N | |
| LP11 | 526982.92 m E | 929639.64 m N | AP4 |

3.1.2. Surveying Elevations at Points LP1 - LP11

During 12th - 15th February in 2015, LHI survey team went to the site to measure elevations of specified points (*i.e. LP1 to LP11*). However, due to the flooding condition in study area (*i.e. around Mahaweli River*), it was difficult to reach to exact locations (*see Appendix 2 for site condition during 12th -15th of February in 2015*). During this period, LHI survey team used a control point established by Surveying Department (*i.e. SLGI02 = [531862.75 m E, 936608.09 m N]*) (*see Appendix 3*) for the present survey. Based on this control point, control points were established in site (*i.e. LHI 01 = [525532.00 m E, 930054.00 m N], and LHI 02 = [523214.00 m E, 931136.00 m N]*) (*see Appendix 4*) to measure elevations of specified points.

During 13th - 15th March in 2015, LHI survey team measured elevations at specified location (*i.e. LP1 to LP11*). This task was carried out by using DGPS, Auto Level and Total Station. To measure elevation points LP1 – LP6 and LP7 – LP11, previously established LHI 02 and LHI 01 control point were used respectively. Pictures of LP1 – LP11 points are shown in *Appendix 5*. Measured elevations are presented in *Table 3.2*.

Table 3.2 Elevation of LP1 – LP11 Points

| Point | Coordinate(UTM) | | Ground Level (above MSL in m) |
|-------|-----------------|---------------|-------------------------------|
| LP1 | 522446.43 m E | 931697.93 m N | 2.515 |
| LP2 | 522836.37 m E | 931475.79 m N | 2.999 |
| LP3 | 523226.75 m E | 931252.33 m N | 2.923 |
| LP4 | 523809.56 m E | 930918.48 m N | 3.115 |
| LP5 | 524347.96 m E | 930611.15 m N | 2.505 |
| LP6 | 524768.70 m E | 930456.42 m N | 2.969 |
| LP7 | 525190.93 m E | 930300.70 m N | 2.408 |
| LP8 | 525612.87 m E | 930144.29 m N | 2.072 |
| LP9 | 526033.98 m E | 929987.60 m N | 2.229 |
| LP10 | 526455.24 m E | 929832.80 m N | 2.131 |
| LP11 | 526982.92 m E | 929639.64 m N | 2.023 |

3.2. Investigation of OHWL and MHWL

The ordinary high water level (*OHWL*) is a line on the bank or shore to which the high water ordinarily rises each year. It is the water ward limit of upland vegetation and soil. This line is not established based on the level to which the water rises during major floods. It is generally recognizable by a visible change in the soil and vegetation. *OHWL* is used to define the boundary of in-water work. Any work below the *OHWL* is considered to be in-water work and special measures must be taken to protect the water way. To investigate Ordinary High Water Level (*OHWL*) and Maximum High Water Level (*MHWL*), attempts were made with two approaches as follows.

3.2.1. Field Investigation to Identify High Water Levels

On 14th of March in 2015, field investigation was carried out in left and right banks of the Mahaweli River where transmission line crosses the river. As seen in *Figure 3.2*, natural features nearby river along LP3 – LP4 was considered.




Figure 3.2: LB and RB Areas of River along the Transmission Line

Vegetation patterns and natural feature of points 1 – 4 along LP3 – LP4 line is further illustrated in *Figure 3.3*. As seen in Figure No. 1, erosion has occurred in left bank area. As a result, nearly vertical slope has formed in the collapsed left bank. Therefore, vegetation pattern in the left bank area is barely helpful to identify high water levels. Similarly, as seen in Figure No. 2 and 3, clay has deposited in the right bank side up to 2.67 m MSL. Hence, only considering vegetation pattern in right bank side, it is difficult to identify high water levels.





Figure 3.3: Natural Features of River Banks along the Transmission Line

River cross section survey was carried out along the transmission line during the same survey period. River cross section along the transmission line is shown in *Figure 3.4* (NB: *Vertical and horizontal scale are different*).




Figure 3.4: River Cross Section along the Transmission Line (On 14th of March in 2015)

According to *John Scherek and Glen Yakel (1993)*, the OHWL is the elevation of the top of the bank of the channel for watercourses such as river. As seen in Figure No. 1 and Figure 3.4, the top level of collapsed river left bank is 3.30 m MSL. However, flooding level could be higher than 3.30 m MSL during the flooding time.

To further investigate about high water levels, numerical simulation was carried out.

3.2.2. Numerical Simulation to Identify High Water Levels

To identify high water levels, numerical model simulation was conducted by using MIKE 21 Hydrodynamic Model (*HD*). Hydrological characteristics required for the model was obtained from calibrated rainfall - runoff (*RR*) model of MIKE 11 modelling system.

MIKE 21 Hydrodynamic (HD) Model System

MIKE 21 HD is a modelling system for 2D free-surface flows and applicable to the simulation of hydraulic and environmental phenomena in lakes, estuaries, bays, coastal areas and seas in response to a variety of forcing functions including tide, wind, wave and river flow. It provides the hydrodynamic basis for the computations performed in the environmental hydraulics and sediment transport modules. MIKE 21 HD Model has the capability to simulate changes of depth (water level) and discharge along and across the river reaches with time. Further, computation of flow velocities and flow patterns are other important capabilities of the same model. Thus, water level at interested point was predicted by using the MIKE 21 HD model.

Model Set-up

The MIKE 21 HD (Flexible Mesh) was selected for the proposed study. By using flexible mesh, it is easy to model small areas with different grid resolutions. Thus, interested area can be defined with a high resolution. Further, model boundaries can be set up smoothly with flexible mesh of this model.

Bathymetry

Bathymetry was created in 2D plane to include the flood inundation areas. Since the flood plain spreads over few kilometers from the river, wider bathymetry was prepared rather than having only a narrow river path. Surveyed river cross sectional data, 1:50,000 topographic maps and Google Earth images were used for the preparation of bathymetry. *Figure 3.5* shows the bathymetry of the project area prepared for the model with flexible mesh.




Figure 3.5: Bathymetry of the River Reach used for 2D Simulations

Boundary Conditions

Discharge and sea levels were used as upstream and downstream boundaries respectively. By using calibrated rainfall-runoff (RR) model, upstream boundary condition was provided for HD model. These flow values are corresponded to the selected return periods to simulate different flood situations. Constant water level boundary was applied for the downstream boundary (see *Figure 3.6* for Schematic diagram of the established model).




Figure 3.6: Schematic Diagram Used for MIKE 21 HD Model

Model Calibration

The hydrodynamic model was calibrated using measured discharges. The bed roughness was used as the calibration parameter and Manning's coefficient of 0.029 was identified as suitable value for river bed roughness when calibrating the model.

Model Simulation

By using MIKE21 HD model simulation, high flow analysis was conducted by taking different discharges for the upstream boundary of the model. For this purpose, extreme analysis was done for the discharge obtained from the calibrated RR model. Accordingly, *Gumbel* distribution was used to estimate discharges correspond to different return periods (i.e. 2, 5, 10, 25, 50 and 100 year). On the basis of discharges for different return periods, HWL identification was done at interested point (P1) by using simulated water level at point P1. 2D plot for the water level variation in the vicinity of LP3 – LP4 area for return period of 10 years is given in Figure 3.7.




Figure 3.7. Water Level Variation in Study Area – MIKE21 HD Output ($T_r = 10$ Years)

Table 3.2 shows water level at point P1 for different return periods obtained by HD model.

Table 3.2 Water Levels at Point P1 for Different Return Period

| Return Period (Tr) | Water Level m MSL | Remarks |
|--------------------|-------------------|-----------------------|
| 2 | 2.92 | |
| 5 | 3.13 | <i>Suggested OHWL</i> |
| 10 | 3.26 | |
| 25 | 3.38 | |
| 50 | 3.45 | |
| 100 | 3.52 | <i>Suggested MHWL</i> |

According to *Robert and Shawn (2008)*, 5 - year flood elevation was approximated as the OHWL for their project works. Thus, on the basis of numerical simulation results and above approximation, 3.13 m MSL can be suggested as OHWL. As mentioned in *Section 3.2.1*, field investigated OHWL is approximated to 3.30 m MSL. Therefore, appropriate OHWL is required to select considering the type of construction work in the study area.

In case of MHWL, 3.52 m MSL is suggested by assuming 100 years of return period. However, considering the design life of proposed construction, most suitable MHWL can be selected from Table 3.2.

References

J. Scherek and G. Yakel, 1993, Guidelines for Ordinary High Water Level (OHWL) Determinations, Minnesota Department of Natural Resources Waters.

Lichvar, Robert W. and McColley, Shawn M., 2008, A Field Guide to the Identification of the Ordinary High Water Mark (OHWM) in the Arid West Region of the Western United States, A delineation Manual; U.S. Army Corps of Engineers; p43.

<http://www.santabarbaraca.gov/civicax/filebank/blobdload.aspx?BlobID=18319>

DHI MIKE11 User Manual

DHI MIKE21 User Manual

APPENDIX - 1: WIND HAZARD SUSCEPTIBLE MAP OF SRI LANKA




Figure A1-1: Average Values of Wind Hazard Susceptible Map of Sri Lanka
 (Source: (http://www.dmc.gov.lk/hazard/hazard/Tropical_Cyclones.html))




Figure A1-2: Maximum Values of Wind Hazard Susceptible Map of Sri Lanka
 (Source: (http://www.dmc.gov.lk/hazard/hazard/Tropical_Cyclones.html))

APPENDIX - 2: SITE CONDITION DURING 12TH -15TH FEBRUARY 2015



Figure A2 - 1: Site Condition during 12th - 15th of February in 2015

APPENDIX - 3: CONTROL POINT ESTABLISHED BY SURVEYING DEPARTMENT



Figure A3 - 1: Control Point “SLGI02” Established by Surveying Department



Figure A3 - 2: GPS Observations at “SLGI02”

APPENDIX - 4: CONTROL POINTS ESTABLISHED BY LHI SURVEY TEAM



Figure A4 - 1: Control Point “LHI01” Established by LHI



Figure A4 - 2: Establishment of Control Point “LHI01”



Figure A4 - 3: Establishment of Control Point “LHI01”



Figure A4 - 4: Control Point “LHI02”



Figure A4 - 5: Establishment of Control Point “LHI02”



Figure A4 - 6: Mark nearby Control Point “LHI2”

APPENDIX - 5: POINTS LP1 – LP11



Figure A5 - 1: Point LP1



Figure A5 - 2: Point LP2



Figure A5 - 3: Point LP3



Figure A5 - 4: Point LP4



Figure A5 - 5: Point LP5 and nearby CEB Mark



Figure A5 - 6: Point LP6



Figure A5 - 7: Point LP7



Figure A5 - 8: Point LP8



Figure A5 - 9: Point LP9



Figure A5 - 10: Point LP10



Figure A5 - 11: Point LP11

Insulator Pollution Details for the Sampoor Area (Lat 8.508923°, Lon 81.193291°)**Insulator Type - Glass, Standard Type, 120kN**Pollution Data with one month IntervalTop Surface

| # | Month | ESDD (mg/cm ²) | NSDD (mg/cm ²) | Pollution Level |
|----|-----------|-------------------------------|-------------------------------|--------------------|
| 1 | October | 0.0204 | NA | - |
| 2 | November | 0.0054 | NA | - |
| 3 | December | 0.0134 | NA | - |
| 4 | January | 0.0108 | NA | - |
| 5 | February | 0.0025 | NA | - |
| 6 | March | 0.0025 | 0.0208 | Very Light |
| 7 | April | 0.0078 | 0.0813 | Light |
| 8 | May | 0.0082 | 0.0521 | Light |
| 9 | June | 0.0360 | 0.1167 | Medium |
| 10 | July | 0.0313 | 0.1313 | Medium |
| 11 | August | 0.0025 | 0.0271 | Very Light |
| 12 | September | 0.0026 | 0.0854 | Very Light |
| 13 | October | 0.0053 | 0.0042 | Very Light |
| 14 | November | 0.0000 | 0.0042 | Very Light |

Bottom Surface

| # | Month | ESDD (mg/cm ²) | NSDD (mg/cm ²) | Pollution Level |
|----|-----------|-------------------------------|-------------------------------|--------------------|
| 1 | October | 0.0081 | NA | - |
| 2 | November | 0.0019 | NA | - |
| 3 | December | 0.0336 | NA | - |
| 4 | January | 0.0320 | NA | - |
| 5 | February | 0.0046 | NA | - |
| 6 | March | 0.0092 | 0.0094 | Very Light |
| 7 | April | 0.0075 | 0.0174 | Very Light |
| 8 | May | 0.0109 | 0.0334 | Very Light |
| 9 | June | 0.0738 | 0.2092 | Medium |
| 10 | July | 0.0593 | 0.1627 | Medium |
| 11 | August | 0.0027 | 0.0276 | Very Light |
| 12 | September | 0.0078 | 0.0523 | Light |
| 13 | October | 0.0028 | 0.0073 | Very Light |
| 14 | November | 0.0019 | 0.0276 | Very Light |

Data with 3 months interval

| # | Month | ESDD (mg/cm ²) | NSDD (mg/cm ²) | Pollution Level |
|---|-----------|-------------------------------|-------------------------------|--------------------|
| 1 | December | 0.0134 | NA | - |
| 2 | March | 0.0025 | 0.0208 | Very Light |
| 3 | June | 0.0347 | 0.1229 | Medium |
| 4 | September | 0.0025 | 0.0521 | Very Light |

| # | Month | ESDD (mg/cm ²) | NSDD (mg/cm ²) | Pollution Level |
|---|-----------|-------------------------------|-------------------------------|--------------------|
| 1 | December | 0.0337 | NA | - |
| 2 | March | 0.0121 | 0.0283 | Very Light |
| 3 | June | 0.0711 | 0.2367 | Medium |
| 4 | September | 0.0066 | 0.0712 | Light |

Data with 6 month interval

| # | Month | ESDD (mg/cm ²) | NSDD (mg/cm ²) | Pollution Level |
|---|-----------|-------------------------------|-------------------------------|--------------------|
| 1 | March | 0.0051 | 0.0417 | Very Light |
| 2 | September | 0.0051 | 0.0688 | Light |

| # | Month | ESDD (mg/cm ²) | NSDD (mg/cm ²) | Pollution Level |
|---|----------|-------------------------------|-------------------------------|--------------------|
| 1 | December | 0.0123 | 0.0370 | Medium |
| 2 | March | 0.0056 | 0.0733 | Light |

Data with 12 month (yearly) interval

| # | Month | ESDD | NSDD | Pollution |
|---|-------|------|------|-----------|
|---|-------|------|------|-----------|

| # | Month | ESDD | NSDD | Pollution |
|---|-------|------|------|-----------|
|---|-------|------|------|-----------|

| | | (mg/cm ²) | (mg/cm ²) | Level |
|---|-----------|-----------------------|-----------------------|-------|
| 1 | September | 0.0052 | 0.0771 | Light |

| | | (mg/cm ²) | (mg/cm ²) | Level |
|---|----------|-----------------------|-----------------------|-------|
| 1 | December | 0.0047 | 0.0763 | Light |

Insulator Type - Porcelain, Fog Type, 120kN

Pollution Data with one month Interval

Top Surface

| # | Month | ESDD (mg/cm ²) | NSDD (mg/cm ²) | Pollution Level |
|---|-----------|-------------------------------|-------------------------------|--------------------|
| 1 | August | 0.0012 | 0.0227 | Very Light |
| 2 | September | 0.0013 | 0.0247 | Very Light |
| 3 | October | 0.0135 | 0.0021 | Very Light |
| 4 | November | 0.0012 | 0.0309 | Very Light |

Bottom Surface

| # | Month | ESDD (mg/cm ²) | NSDD (mg/cm ²) | Pollution Level |
|---|-----------|-------------------------------|-------------------------------|--------------------|
| 1 | August | 0.0024 | 0.0114 | Very Light |
| 2 | September | 0.0057 | 0.0328 | Very Light |
| 3 | October | 0.0117 | 0.0082 | Very Light |
| 4 | November | 0.0032 | 0.0170 | Very Light |

Data with 3 months interval

Top Surface

| # | Month | ESDD (mg/cm ²) | NSDD (mg/cm ²) | Pollution Level |
|---|---------|-------------------------------|-------------------------------|--------------------|
| 1 | October | 0.0135 | 0.0062 | Light |

Bottom Surface

| # | Month | ESDD (mg/cm ²) | NSDD (mg/cm ²) | Pollution Level |
|---|---------|-------------------------------|-------------------------------|--------------------|
| 1 | October | 0.0160 | 0.0265 | Light |

No six month data and yearly data are available

Insulator Type - Composite (Hybrid), Standard, 120kN

Pollution Data with one month Interval

Top Surface

| # | Month | ESDD (mg/cm ²) | NSDD (mg/cm ²) | Pollution Level |
|---|-----------|-------------------------------|-------------------------------|--------------------|
| 1 | April | 0.0100 | 0.0579 | Light |
| 2 | May | 0.0055 | 0.0377 | Very Light |
| 3 | June | 0.0298 | 0.1005 | Medium |
| 4 | July | 0.0223 | 0.0809 | Medium |
| 5 | August | 0.0009 | 0.0195 | Very Light |
| 6 | September | 0.0026 | 0.0433 | Very Light |
| 7 | October | 0.0028 | 0.0098 | Very Light |
| 8 | November | 0.0009 | 0.0181 | Very Light |

Bottom Surface

| # | Month | ESDD (mg/cm ²) | NSDD (mg/cm ²) | Pollution Level |
|---|-----------|-------------------------------|-------------------------------|--------------------|
| 1 | April | 0.0081 | 0.0707 | Light |
| 2 | May | 0.0113 | 0.0464 | Light |
| 3 | June | 0.0625 | 0.1933 | Medium |
| 4 | July | 0.0524 | 0.1737 | Light |
| 5 | August | 0.0020 | 0.1737 | Very Light |
| 6 | September | 0.0101 | 0.0794 | Light |
| 7 | October | 0.0064 | 0.0212 | Very Light |
| 8 | November | 0.0061 | 0.0259 | Very Light |

Data with 3 months interval

Top Surface

| # | Month | ESDD (mg/cm ²) | NSDD (mg/cm ²) | Pollution Level |
|---|-----------|-------------------------------|-------------------------------|--------------------|
| 1 | June | 0.0287 | 0.1403 | Medium |
| 2 | September | 0.0035 | 0.0670 | Very Light |

Bottom Surface

| # | Month | ESDD (mg/cm ²) | NSDD (mg/cm ²) | Pollution Level |
|---|-----------|-------------------------------|-------------------------------|--------------------|
| 1 | June | 0.0602 | 0.2169 | Medium |
| 2 | September | 0.0101 | 0.1367 | Light |

Top Surface

| # | Month | ESDD (mg/cm ²) | NSDD (mg/cm ²) | Pollution Level |
|---|-----------|-------------------------------|-------------------------------|--------------------|
| 1 | September | 0.0044 | 0.0800 | Light |

Bottom Surface

| # | Month | ESDD (mg/cm ²) | NSDD (mg/cm ²) | Pollution Level |
|---|-----------|-------------------------------|-------------------------------|--------------------|
| 1 | September | 0.0112 | 0.145 | Light |

No yearly data are available



Geotechnical Engineering Division

Quality is Our Trademark

GEOTECHNICAL INVESTIGATION REPORT

ELS SI 3592

PROJECT

Geotechnical Investigation for National Transmission and Distribution Network Development and Efficiency Improvement Project (II)

CLIENT

Tokyo Electric Power Services Co. Ltd.

February 02, 2015.

ENGINEERING & LABORATORY SERVICES [PVT.] LTD.

62/3, Neelammahara Road | Katuwawala | Boraesgamuwa

Sri Lanka. Tel: +94 114 309 494 | Fax: +94 112 509 806

Email: soil@elslanka.com | Web: www.elslanka.com



CONCRETE PIPES

CEMENT BLOCKS



CONTENTS

| | | |
|-----|--|---|
| 1.0 | Introduction..... | 1 |
| 2.0 | Site Description..... | 1 |
| 3.0 | Field Investigation | 3 |
| 4.0 | Subsurface Conditions | 3 |
| 4.1 | Subsurface conditions across the borehole TT-01 | 3 |
| 4.2 | Subsurface conditions across the borehole AP-09 | 4 |
| 4.3 | Subsurface conditions across the borehole AP-17 | 4 |
| 4.4 | Subsurface conditions across the borehole AP-20 | 4 |
| 4.5 | Subsurface conditions across the borehole AP-32 | 4 |
| 4.6 | Subsurface conditions across the borehole AP-36A | 5 |
| 4.7 | Subsurface conditions across the borehole AP-38 | 5 |
| 4.8 | Subsurface conditions across the borehole AP-39 | 5 |
| 4.9 | Subsurface conditions across the borehole AP-44 | 6 |
| 4.7 | Subsurface conditions across the borehole TT-02 | 6 |

TABLES

| | |
|--|---|
| Table 1: Locations of the boreholes..... | 1 |
|--|---|

FIGURES

| | |
|--|----|
| Figure 1: Proposed tower locations..... | 2 |
| Figure 2(a): Sub Surface Profile at TT-01 | 7 |
| Figure 2(b): Sub Surface Profile at AP-09..... | 8 |
| Figure 2(c): Sub Surface Profile at AP-17..... | 9 |
| Figure 2(d): Sub Surface Profile at AP-20..... | 10 |
| Figure 2(e): Sub Surface Profile at AP-32..... | 11 |
| Figure 2(f): Sub Surface Profile at AP-36A | 12 |
| Figure 2(g): Sub Surface Profile at AP-38..... | 13 |



| | |
|--|----|
| Figure 2(h): Sub Surface Profile at AP-39..... | 14 |
| Figure 2(i): Sub Surface Profile at AP-44..... | 15 |
| Figure 2(j): Sub Surface Profile at TT-01..... | 16 |

ANNEXURE

Annexure I: Borehole Logs

Annexure II: Field Photographs

Annexure III: Locations of Boreholes



**GEOTECHNICAL INVESTIGATION FOR NATIONAL TRANSMISSION AND
DISTRIBUTION NETWORK DEVELOPMENT AND EFFICIENCY IMPROVEMENT
PROJECT (II)**

1.0 Introduction

Tokyo Electric Power Services Co. Ltd. (TEPSCO) is a Tokyo based engineering/ consulting company. And will perform Japanese International Cooperation Agency's (JICA) preparatory study on National Transmission and Distribution Network Development and Efficiency Improvement Project (II) in Sri Lanka as JICA study team under JICA. Under the above project 400kV electricity transmission line is proposed from Sampoor, where a coal power project is proposed, to Habarana (95km). Geotechnical Investigation was carried out for some tower locating along above tower line in order to assess the geological conditions at required tower positions.

M/s. Engineering and Laboratory Services (Pvt) Ltd. was authorized by **M/s. Tokyo Electric Power Services Co. Ltd. (TEPSCO)**, to carry out the soil investigation at the above site and prepare the soil investigation report with recommendations for foundation design.

2.0 Site Description

The boreholes were done along the proposed transmission line.

Table 1: Locations of the boreholes

| Location | Coordinate (UTM) | |
|----------|------------------|-------------|
| | Northing (m) | Easting (m) |
| TT-01 | 889756.50 | 469925.99 |
| AP-09 | 894523.58 | 477707.07 |
| AP-17 | 910993.46 | 489980.66 |
| AP-20 | 916390.60 | 492864.38 |
| AP-32 | 924330.82 | 504853.51 |
| AP-36A | 932097.78 | 513311.74 |
| AP-38 | 931688.98 | 522443.44 |
| AP-39 | 930607.46 | 524349.76 |
| AP-44 | 934586.00 | 533906.00 |
| TT-02 | 936689.06 | 534721.00 |





Figure 1: Proposed tower locations



3.0 Field Investigation

The field investigation was consisted of advancing 10 boreholes at the location marked as in Figure 1.

The boreholes were advanced by means of a rotary - drilling machine. The drilling was carried out with overburden cutting tools, and the wash boring process was adopted to remove the cuttings from the bottom of the borehole.

Standard Penetration Test (SPT) was carried out in regular intervals in the overburden. This test was carried out as specified in BS 1377.

Disturbed samples of soil were collected both from the SPT tube and the cuttings were collected from the washings.

Groundwater Level (GWL) was determined as the depth at which the water level stabilized inside the borehole.

The field investigation was commenced on 02nd January 2015 and completed on 31st January 2015.

4.0 Subsurface Conditions

The results of the borehole investigation are given in Annexure I.

The bed rock level at the area is generally varies 3.5m-10m depth from the surface level except AP-39 (near to river). Generally the water level along investigated line was noted as 0.6-2m depth from the surface level.

Using this, profiles of subsurface conditions across the boreholes have been constructed and these are shown in Figure 2(a) to 2(j).

4.1 Subsurface conditions across the borehole TT-01

The results indicate that,

- (i) The groundwater level (GWL) was encountered at the depth of 0.25m at the time of investigation.
- (ii) A medium dense to dense clayey sand layer was found up to the depth of 4.20m at the borehole TT-01



- (iii) A completely weathered rock layer was encountered up to the rock level at the depth of 10.30m and borehole was terminated at that level

4.2 Subsurface conditions across the borehole AP-09

The results indicate that,

- (i) The groundwater level (GWL) was not encountered at the time of investigation.
- (ii) A sand layer was found up to the depth of 1.00m at the borehole AP-09.
- (iii) A completely weathered rock layer was encountered up to the rock level at the depth of 4.40m and borehole was terminated at that level.

4.3 Subsurface conditions across the borehole AP-17

The results indicate that,

- (i) The groundwater level (GWL) was encountered at the depth of 3.00m at the time of investigation.
- (ii) Gravels layer was found up to the depth of 1.00m at the borehole AP-17.
- (iii) Then completely weathered rock layer was encountered up to the rock level at the depth of 4.80m and borehole was terminated at that level.

4.4 Subsurface conditions across the borehole AP-20

The results indicate that,

- (i) The groundwater level (GWL) was encountered at the depth of 1.10m at the time of investigation.
- (ii) A sandy clay layer was found up to the depth of 0.80m at the borehole AP-20.
- (iii) Then completely weathered rock layer was encountered up to the rock level at the depth of 8.85m and borehole was terminated at that level.

4.5 Subsurface conditions across the borehole AP-32

The results indicate that,

- (i) The groundwater level (GWL) was encountered at the depth of 1.15m at the time of investigation.
- (ii) A clayey sand layer was found up to the depth of 0.80m at the borehole AP-32.
- (iii) Then firm to very stiff sandy clay layer was encountered up to the rock level at the depth of 7.30m and borehole was terminated at that level.



4.6 Subsurface conditions across the borehole AP-36A

The results indicate that,

- (i) The groundwater level (GWL) was encountered at the depth of 0.60m at the time of investigation.
- (ii) A loose sand layer was found up to the depth of 3.50m (the rock level) and borehole was terminated at that level.

4.7 Subsurface conditions across the borehole AP-38

The results indicate that,

- (i) The groundwater level (GWL) was encountered at the depth of 1.40m at the time of investigation.
- (ii) A stiff sandy clay layer was found up to the depth of 2.00m at the borehole AP-39.
- (iii) Then medium dense sand layer was found up to the depth of 4.50m.
- (iv) Very soft organic clay layer was found up to the depth of 7.50m.
- (v) Then completely weathered rock layer was encountered up to the rock level at the depth of 8.80m and borehole was terminated at that level.

4.8 Subsurface conditions across the borehole AP-39

The results indicate that,

- (i) The groundwater level (GWL) was encountered at the depth of 1.60m at the time of investigation.
- (ii) A stiff sandy clay layer was found up to the depth of 2.00m at the borehole AP-39.
- (iii) Then medium dense to loose sand layer was found up to the depth of 6.00m.
- (iv) Very soft organic clay layer was found up to the depth of 9.00m.
- (v) Then very loose clayey organic sand layer was found up to the depth of 10.50m.
- (vi) Loose sand with organic clay layer was found up to the depth of 13.50m.
- (vii) Firm to very soft organic clay/organic sandy clay layer was noticed up to the depth of 25.00m.
- (viii) Loose clayey sand layer was found up to the depth 30.00m.
- (ix) Then dense clayey sand layer was found up to the depth of 32.00m
- (x) Then very dense to dense sand layer was encountered up to the rock level at the depth of 40.00m and borehole was terminated at that level.



4.9 Subsurface conditions across the borehole AP-44

The results indicate that,


- (iii) The groundwater level (GWL) was encountered at the depth of 1.30m at the time of investigation.
- (iv) A completely weathered rock was found up to the rock level at the depth of 2.80m and borehole was terminated at that level.

4.7 Subsurface conditions across the borehole TT-02

The results indicate that,


- (vi) The groundwater level (GWL) was not encountered at the time of investigation.
- (vii) A completely weathered rock layer was encountered up to the rock level at the depth of 2.60m and borehole was terminated at that level.

TT-01



| | | |
|---|---|-----------------------------|
| <p>Figure 2(a): Possible Soil Profile at the borehole, BH-TT-01</p> | <p>Project: Geotechnical Investigation for National Transmission and Distribution Network Development and Efficiency Improvement Project (II)</p> | <p>Vertical scale 1:130</p> |
|---|---|-----------------------------|


Note: Profile is plotted only according to the data obtained from the borehole locations and actual soil profile may vary from this profile



| | | |
|--|--|----------------------|
| Figure 2(b): Possible Soil Profile at the borehole,AP-09 | Project: Geotechnical Investigation for National Transmission and Distribution Network Development and Efficiency Improvement Project (II) | Vertical scale 1:130 |
|--|--|----------------------|

Note: Profile is plotted only according to the data obtained from the borehole locations and actual soil profile may vary from this profile

AP-17



| | | |
|--|---|-----------------------------|
| <p>Figure 2(c): Possible Soil Profile at the borehole, AP-17</p> | <p>Project: Geotechnical Investigation for National Transmission and Distribution Network Development and Efficiency Improvement Project (II)</p> | <p>Vertical scale 1:130</p> |
|--|---|-----------------------------|

Note: Profile is plotted only according to the data obtained from the borehole locations and actual soil profile may vary from this profile

AP-20





Figure 2(d): Possible Soil Profile at the borehole, AP-20

Project: Geotechnical Investigation for National Transmission and Distribution Network Development and Efficiency Improvement Project (II)

Vertical scale 1:130

Note: Profile is plotted only according to the data obtained from the borehole locations and actual soil profile may vary from this profile


AP-32



| | | |
|--|---|-----------------------------|
| <p>Figure 2(e): Possible Soil Profile at the borehole, AP-32</p> | <p>Project: Geotechnical Investigation for National Transmission and Distribution Network Development and Efficiency Improvement Project (II)</p> | <p>Vertical scale 1:130</p> |
|--|---|-----------------------------|

Note: Profile is plotted only according to the data obtained from the borehole locations and actual soil profile may vary from this profile


AP-36A



| | | |
|---|---|-----------------------------|
| <p>Figure 2(f): Possible Soil Profile at the borehole, AP-36A</p> | <p>Project: Geotechnical Investigation for National Transmission and Distribution Network Development and Efficiency Improvement Project (II)</p> | <p>Vertical scale 1:130</p> |
|---|---|-----------------------------|

Note: Profile is plotted only according to the data obtained from the borehole locations and actual soil profile may vary from this profile


AP-38



| | | |
|--|---|-----------------------------|
| <p>Figure 2(g): Possible Soil Profile at the borehole, AP-38</p> | <p>Project: Geotechnical Investigation for National Transmission and Distribution Network Development and Efficiency Improvement Project (II)</p> | <p>Vertical scale 1:130</p> |
|--|---|-----------------------------|

Note: Profile is plotted only according to the data obtained from the borehole locations and actual soil profile may vary from this profile

AP-39



| | | |
|--|---|-----------------------------|
| <p>Figure 2(h): Possible Soil Profile at the borehole, AP-39</p> | <p>Project: Geotechnical Investigation for National Transmission and Distribution Network Development and Efficiency Improvement Project (II)</p> | <p>Vertical scale 1:165</p> |
|--|---|-----------------------------|

Note: Profile is plotted only according to the data obtained from the borehole locations and actual soil profile may vary from this profile





Figure 2(i): Possible Soil Profile at the borehole, AP-44

Project: Geotechnical Investigation for National Transmission and Distribution Network Development and Efficiency Improvement Project (II)

Vertical scale 1:130

Note: Profile is plotted only according to the data obtained from the borehole locations and actual soil profile may vary from this profile

TT-02




| | | |
|---|--|----------------------|
| Figure 2(j): Possible Soil Profile at the borehole, TT-02 | Project: Geotechnical Investigation for National Transmission and Distribution Network Development and Efficiency Improvement Project (II) | Vertical scale 1:130 |
|---|--|----------------------|

Note: Profile is plotted only according to the data obtained from the borehole locations and actual soil profile may vary from this profile




Annexure I: Borehole Logs

| | | | |
|-------------------------|---|--------------------|----------------------------------|
| Project | Geotechnical Investigation for National Transmission and Distribution Network Development and Efficiency Improvement Project (II) | Borehole No | AP-32 |
| Client | M/s. Tokyo Electric Power Services Co. Ltd | Sheet | 1 of 1 |
| Location | Sampoor | Rig | Joy |
| Date of Started | 16.01.2015 | Core Diameter | 54mm |
| Date of Finished | | Drilling Method | Wash |
| | | Casing depth | 6.0m |
| | | Casing Diameter | 76mm |
| | | Elevation (m) | |
| | | Ground Water level | 1.15m |
| | | Coordinates | 8° 21' 45.98"N 81° 2' 38.72"E |



| Sample Key / Test Key | | | | Remarks | Logged By : |
|-----------------------|---|----------------------------------|------------------------------|--|---|
| SPT | Where full 0.3m penetration has not been achieved the number of blows for the quoted penetration is given (not N-value) | D - Disturbed Sample | N - Natural Moisture Content | Existing ground level considered as the zero level | S.M.D..Samantha Drilled By: W.L.Nimal |
| GWL | : Ground Water Level observed inside the Borehole, after the saturation | SS -SPT Sample | L - Atterberg Limit Test | | |
| NE | Not Encountered | W - Water Sample | G - Grain Size Analysis | | |
| HB | -Hammer Bounce | WS-Wgrey Sample | SG -Specific Gravity Test | | |
| FD | - Free Down | UD- Undisturbed Sample | B - Bulk Density | | |
| | | CS- Core Sample | V - Vane Shear Test | | |
| | | Cr - Core Recovery (%) | | | |
| | | RQD-Rock Quality Designation (%) | | | |
| | Made Ground | | Silt | | Completely Weathered Rock |
| | Clay | | Sand | | Highly Weathered Rock |
| | Gravel | | Organic Matter | | Laterite Nodules |
| | Silty Sand | | Fresh Rock | | |


| | | | |
|------------------|---|--------------------|----------------------------------|
| Project | Geotechnical Investigation for National Transmission and Distribution Network Development and Efficiency Improvement Project (II) | Borehole No | AP-36A |
| Client | M/s. Tokyo Electric Power Services Co. Ltd | Sheet | 1 of 1 |
| Location | Sampoor | Rig | Joy |
| Date of Started | 25.01.2013 | Core Diameter | 54mm |
| Date of Finished | 25.01.2013 | Drilling Method | Wash |
| | | Casing depth | 3.50m |
| | | Casing Diameter | 76mm |
| | | Elevation (m) | |
| | | Ground Water level | 0.60m |
| | | Coordinates | 8° 25' 58.86"N 81° 6.49' 46"E |



| Sample Key / Test Key | | | | Remarks | Logged By : |
|-----------------------|---|------------------------------------|------------------------------|--|---------------------------|
| SPT | Where full 0.3m penetration has not been achieved the number of blows for the quoted penetration is given (not N-value) | D - Disturbed Sample | N - Natural Moisture Content | Existing ground level considered as the zero level | Nishantha |
| | | SS - SPT Sample | L - Atterberg Limit Test | | Supervised By: |
| | | W - Water Sample | G - Grain Size Analysis | | Lahiru |
| | | WS - Wgrey Sample | SG - Specific Gravity Test | | Drilled By: |
| | GWL : Ground Water Level observed inside the Borehole, after the saturation | UD - Undisturbed Sample | B - Bulk Density | | Suranga |
| | NE - Not Encountered | CS - Core Sample | V - Vane Shear Test | | |
| | HB - Hammer Bounce | Cr - Core Recovery (%) | | | |
| | FD - Free Down | RQD - Rock Quality Designation (%) | | | |
| | Made Ground | | Silt | | Completely Weathered Rock |
| | Clay | | Sand | | Highly Weathered Rock |
| | Gravel | | Organic Matter | | Laterite Nodules |
| | Silty Sand | | Fresh Rock | | |



| | | | | | | | |
|------------------|--|-----------------|------|---------------|-------------|--------------------|-----------------|
| Project | Geotechnical Investigation for National Transmission and Distribution Network Development and Efficiency Improvement Project (II) | | | | Borehole No | AP-38 | |
| Client | M/s. Tokyo Electric Power Services Co. Ltd | | | | Sheet | 1 of 1 | |
| Location | Sampoor | Rig | TD | Core Diameter | 54mm | Ground Water level | 1.40m |
| Date of Started | 23.01.2015 | Drilling Method | Wash | Casing depth | 7.50m | Coordinates | 8° 25' 43.01"N |
| Date of Finished | 14.01.2015 | Casing Diameter | 76mm | Elevation (m) | | | 81° 12' 13.96"E |



| Sample Key / Test Key | | | | Remarks | Logged By : |
|-----------------------|---|----------------------------------|------------------------------|--|---------------------------|
| SPT | Where full 0.3m penetration has not been achieved the number of blows for the quoted penetration is given (not N-value) | D - Disturbed Sample | N - Natural Moisture Content | Existing ground level considered as the zero level | N.A.C Nishshanka |
| GWL | : Ground Water Level observed inside the Borehole, after the saturation | SS -SPT Sample | L - Atterberg Limit Test | | R.M.B.Sandarawan |
| NE | Not Encountered | W - Water Sample | G - Grain Size Analysis | | Drilled By: |
| HB | -Hammer Bounce | WS-Wgrey Sample | SG -Specific Gravity Test | | Sumathipala |
| FD | - Free Down | UD- Undisturbed Sample | B - Bulk Density | | |
| | | CS- Core Sample | V - Vane Shear Test | | |
| | | Cr - Core Recovery (%) | | | |
| | | RQD-Rock Quality Designation (%) | | | |
| | Made Ground | | Silt | | Completely Weathered Rock |
| | Clay | | Sand | | Highly Weathered Rock |
| | Gravel | | Organic Matter | | Fresh Rock |
| | Laterite Nodules | | Silty Sand | | |




| | | | | | | |
|------------------|--|-----------------|------|---------------|-------------|---|
| Project | Geotechnical Investigation for National Transmission and Distribution Network Development and Efficiency Improvement Project (II) | | | | Borehole No | BH-39 |
| Client | M/s. Tokyo Electric Power Services Co. Ltd | | | | Sheet | 2 of 4 |
| Location | Sampoor | Rig | Joy | Core Diameter | 54mm | Ground Water level |
| Date of Started | 16.01.2015 | Drilling Method | Wash | Casing depth | 40.00m | Coordinates 8° 25' 7.77"N 81° 13' 49.1627"E |
| Date of Finished | 22.01.2015 | Casing Diameter | 76mm | Elevation (m) | | |

| Depth (m) | Sa. Cond | Sa. NO. | Sa. Type | Reduced level | Depth (m) | Legend | Soil Description | Field Records (SPT) | | | | Moisture Content - % | | Undrained Shear Strength - t/m ² | | SPT Resistance - Blows/ft | |
|-----------|----------|---------|----------|---------------|-----------|--------|---|---------------------|------|------|---|----------------------|--|---|--|---------------------------|--|
| | | | | | | | | 15cm | 15cm | 15cm | N | | | | | | |
| 10.00 | | | | | | | Continue from Page 1 | | | | | | | | | | |
| 11.00 | D9 | | SS | | 10.50 | | Same as previous description | 1 | 2 | 2 | 4 | | | | | | |
| 12.00 | | | WS | | | | Loose, black, fine to coarse SAND with small amount of ORGANIC CLAY | | | | | | | | | | |
| 13.00 | D10 | | SS | | | | | 1 | 1 | 2 | 3 | | | | | | |
| 14.00 | | | WS | | | | Firm, black, amorphous ORGANIC fine SANDY CLAY | | | | | | | | | | |
| 15.00 | D11 | | SS | | 13.50 | | | 2 | 3 | 4 | 7 | | | | | | |
| 16.00 | | | WS | | | | Firm, black, amorphous ORGANIC CLAY | | | | | | | | | | |
| 17.00 | D12 | | SS | | | | | 3 | 3 | 5 | 8 | | | | | | |
| 18.00 | | | WS | | | | Firm, black, amorphous ORGANIC CLAY | | | | | | | | | | |
| 19.00 | D13 | | SS | | 17.00 | | | 2 | 3 | 3 | 6 | | | | | | |
| 20.00 | | | WS | | | | Firm, black, amorphous ORGANIC CLAY with some fine sand | | | | | | | | | | |
| | D14 | | SS | | 19.00 | | | 3 | 2 | 3 | 5 | | | | | | |

| Sample Key / Test Key | | | | Remarks | Logged By |
|-----------------------|---|---|--|--|--|
| SPT | Where full 0.3m penetration has not been achieved the number of blows for the quoted penetration is given (not N-value) | D - Disturbed Sample SS - SPT Sample W - Water Sample WS - Wgrey Sample UD - Undisturbed Sample CS - Core Sample Cr - Core Recovery (%) RQD - Rock Quality Designation (%) | N - Natural Moisture Content L - Atterberg Limit Test G - Grain Size Analysis SG - Specific Gravity Test B - Bulk Density V - Vane Shear Test | C - Consolidation UCT - Unconfined Compression CU - Consolidated Undrained UU - Unconsolidated Undrained pH - Chemical O - Organic content SO ₄ ²⁻ - Sulphate Content CF - Chloride Content | Existing ground level considered as the zero level |
| GWL | Ground Water Level observed inside the Borehole, after the saturation | | | | Nishantha Supervised By: |
| NE | Not Encountered | | | | Indunil Drilled By: |
| HB | -Hammer Bounce | | | | Sumathipala |
| FD | - Free Down | | | | |
| | Made Ground | | Silt | | Gravel |
| | Clay | | Sand | | Organic Matter |
| | | | Laterite Nodules | | Silty Sand |
| | | | Completely Weathered Rock | | Highly Weathered Rock |
| | | | Fresh Rock | | |



| | | | | | | |
|-------------------------|--|------------------------|------|----------------------|--------------------|---------------------------|
| Project | Geotechnical Investigation for National Transmission and Distribution Network Development and Efficiency Improvement Project (II) | | | | Borehole No | BH-39 |
| Client | M/s. Tokyo Electric Power Services Co. Ltd | | | | Sheet | 3 of 4 |
| Location | Sampoor | Rig | Joy | Core Diameter | 54mm | Ground Water level |
| Date of Started | 16.01.2015 | Drilling Method | Wash | Casing depth | 40.00m | Coordinates |
| Date of Finished | 22.01.2015 | Casing Diameter | 76mm | Elevation (m) | | |



| Sample Key / Test Key | | | | Remarks | Logged By: | |
|-----------------------|---|------------------------------------|------------------------------|--|---------------------------|-------------|
| SPT | Where full 0.3m penetration has not been achieved the number of blows for the quoted penetration is given (not N-value) | D - Disturbed Sample | N - Natural Moisture Content | Existing ground level considered as the zero level | Nishantha | |
| GWL | : Ground Water Level observed inside the Borehole, after the saturation | SS - SPT Sample | L - Atterberg Limit Test | | Supervised By: | Indunil |
| NE | Not Encountered | W - Water Sample | G - Grain Size Analysis | | Drilled By: | Sumathipala |
| HB | -Hammer Bounce | WS - Wgrey Sample | SG - Specific Gravity Test | | | |
| FD | - Free Down | UD - Undisturbed Sample | B - Bulk Density | | | |
| | | CS - Core Sample | V - Vane Shear Test | | | |
| | | Cr - Core Recovery (%) | | | | |
| | | RQD - Rock Quality Designation (%) | | | | |
| | Made Ground | | Silt | | Completely Weathered Rock | |
| | Clay | | Sand | | Silty Sand | |
| | Gravel | | Organic Matter | | Laterite Nodules | |
| | Fresh Rock | | Highly Weathered Rock | | Fresh Rock | |



| | | | | | | |
|------------------|--|-----------------|------|---------------|-------------|------------------------------------|
| Project | Geotechnical Investigation for National Transmission and Distribution Network Development and Efficiency Improvement Project (II) | | | | Borehole No | BH-39 |
| Client | M/s. Tokyo Electric Power Services Co. Ltd | | | | Sheet | 4 of 4 |
| Location | Sampoor | Rig | Joy | Core Diameter | 54mm | Ground Water level |
| Date of Started | 16.01.2015 | Drilling Method | Wash | Casing depth | 40.00m | Coordinates |
| Date of Finished | 22.01.2015 | Casing Diameter | 76mm | Elevation (m) | | 8° 25' 7.77"N 81° 13' 49.1627"E |

| Depth (m) | Sa. Cond | Sa. NO. | Sa. Type | Reduced level | Depth (m) | Legend | Soil Description | Field Records (SPT) | | | | Moisture Content - % | | |
|-----------|----------|---------|----------|---------------|-----------|--------|--|---------------------|------|------|-----|----------------------|----------------|-----|
| | | | | | | | | 15cm | 15cm | 15cm | N | U | U ₂ | |
| 30.00 | | | | | | | Continue from Page 1 | | | | | | | |
| 31.00 | | | WS | | | | Dense, yellowish brown, fine to medium CLAYEY SAND | 12 | 17 | 22 | 39 | | | 39 |
| 32.00 | | | WS | | | | Very dense, yellowish brown, gray, fine to coarse SAND | 18 | 22 | 29 | >50 | | | >50 |
| 34.00 | | | WS | | | | Washed sample changed to; | 16 | 23 | 25 | 48 | | | 48 |
| 36.00 | | | WS | | | | Dense, brown, gray, fine to medium sand with mica traces | 12 | 19 | 25 | 44 | | | 44 |
| 38.00 | | | WS | | | | END OF THE BOREHOLE AT 40.00m DEPTH | 24 | 28 | 24 | 52 | | | 52 |

| Sample Key / Test Key | | | | Remarks | Logged By: |
|-----------------------|---|--|--|--|----------------------------|
| SPT | Where full 0.3m penetration has not been achieved the number of blows for the quoted penetration is given (not N-value) | D - Disturbed Sample SS - SPT Sample W - Water Sample WS - Wash Sample UD - Undisturbed Sample CS - Core Sample Cr - Core Recovery (%) RQD - Rock Quality Designation (%) | N - Natural Moisture Content L - Atterberg Limit Test G - Grain Size Analysis SG - Specific Gravity Test B - Bulk Density V - Vane Shear Test | C - Consolidation UCT - Unconfined Compression CU - Consolidated Undrained UU - Unconsolidated Undrained pH - Chemical O - Organic content SO ₄ ²⁻ - Sulphate Content Cl - Chloride Content | Nishantha |
| GWL | Ground Water Level observed inside the Borehole, after the saturation | | | Existing ground level considered as the zero level | Supervised By: Indunil |
| NE | Not Encountered | | | | Drilled By: Sumathipala |
| HB | -Hammer Bounce | | | | |
| FD | - Free Down | | | | |
| | Made Ground | | Silt | | Gravel |
| | Clay | | Sand | | Organic Matter |
| | Laterite Nodules | | Silty Sand | | Completely Weathered Rock |
| | Highly Weathered Rock | | Fresh Rock | | |



Annexure II: Field Photographs

GEOTECHNICAL INVESTIGATION FOR NATIONAL TRANSMISSION AND DISTRIBUTION NETWORK DEVELOPMENT AND EFFICIENCY IMPROVEMENT PROJECT (II)

Client: Tokyo Electric Power Services Co. Ltd. (TEPSCO)




Engineering & Laboratory Services (Pvt) Ltd.



Annexure III: Borehole Locations

GEOTECHNICAL INVESTIGATION FOR NATIONAL TRANSMISSION AND DISTRIBUTION NETWORK DEVELOPMENT AND EFFICIENCY IMPROVEMENT PROJECT (II)

Client: Tokyo Electric Power Services Co. Ltd. (TEPSCO)



Engineering & Laboratory Services (Pvt) Ltd.

GEOTECHNICAL INVESTIGATION FOR NATIONAL TRANSMISSION AND DISTRIBUTION NETWORK DEVELOPMENT AND EFFICIENCY IMPROVEMENT PROJECT (II)


Client: Tokyo Electric Power Services Co. Ltd. (TEPSCO)



Engineering & Laboratory Services (Pvt) Ltd.

GEOTECHNICAL INVESTIGATION FOR NATIONAL TRANSMISSION AND DISTRIBUTION NETWORK DEVELOPMENT AND EFFICIENCY IMPROVEMENT PROJECT (II)


Client: Tokyo Electric Power Services Co. Ltd. (TEPSCO)



Engineering & Laboratory Services (Pvt) Ltd.

GEOTECHNICAL INVESTIGATION FOR NATIONAL TRANSMISSION AND DISTRIBUTION NETWORK DEVELOPMENT AND EFFICIENCY IMPROVEMENT PROJECT (II)


Client: Tokyo Electric Power Services Co. Ltd. (TEPSCO)



Engineering & Laboratory Services (Pvt) Ltd.

GEOTECHNICAL INVESTIGATION FOR NATIONAL TRANSMISSION AND DISTRIBUTION NETWORK DEVELOPMENT AND EFFICIENCY IMPROVEMENT PROJECT (II)

Client: Tokyo Electric Power Services Co. Ltd. (TEPSCO)



Engineering & Laboratory Services (Pvt) Ltd.

GEOTECHNICAL INVESTIGATION FOR NATIONAL TRANSMISSION AND DISTRIBUTION NETWORK DEVELOPMENT AND EFFICIENCY IMPROVEMENT PROJECT (II)


Client: Tokyo Electric Power Services Co. Ltd. (TEPSCO)



Engineering & Laboratory Services (Pvt) Ltd.

GEOTECHNICAL INVESTIGATION FOR NATIONAL TRANSMISSION AND DISTRIBUTION NETWORK DEVELOPMENT AND EFFICIENCY IMPROVEMENT PROJECT (II)


Client: Tokyo Electric Power Services Co. Ltd. (TEPSCO)



Engineering & Laboratory Services (Pvt) Ltd.

GEOTECHNICAL INVESTIGATION FOR NATIONAL TRANSMISSION AND DISTRIBUTION NETWORK DEVELOPMENT AND EFFICIENCY IMPROVEMENT PROJECT (II)

Client: Tokyo Electric Power Services Co. Ltd. (TEPSCO)



Engineering & Laboratory Services (Pvt) Ltd.

Loss Reduction Calculation of the 400kV Sampoor - New Habarana T/L


| | | |
|----------------------|--------------------------|---|
| Power factor | 0.85 | Construction cost of 400kV Sampoor - New Habarana |
| Load factor of 220kV | 0.582 | -ACSR Zebra 9284 M Rs |
| Conductor Resistance | | -LL-ACSR/AW 550 10029 M Rs |
| - ACSR Zebra | 0.0814 Ohm/km at 63 deg. | -Cost Difference 745 M Rs |
| - LL-ACSR/AC 550 | 0.0621 Ohm/km at 61 deg. | |
| Bundle | 4 bundle | Rate 0.87 LKR/yen |
| Length of S-H T/L | 91.2 km | |

| Year | Generation at Sampoor (GWh) | Operation Voltage of S-H T/L (kV) | Load of Kapparlai (MW) | Energy to S-K T/L (GWh) | Energy to S-H T/L (GWh) | Sending per 1cct of S-H T/L (MW) | Load factor of S-H T/L | Load Loss Factor of S-H T/L | Current per conductor (A) | Annual losses on Zebra per cct (MWh/km) | Annual losses on LL per cct (MWh/km) | Annual loss reduction per cct (MWh/km) | Annual loss reduction (MWh) | Tariff (kWh/Y) | Loss reduction benefits equivalent Sales Amounts (M JPY) | Sum of Annual Benefit Amounts (M JPY) |
|------|-----------------------------|-----------------------------------|------------------------|-------------------------|-------------------------|----------------------------------|------------------------|-----------------------------|---------------------------|---|--------------------------------------|--|-----------------------------|----------------|--|---------------------------------------|
| 1 | 2017 | | | | | | | | | | | | | | | |
| 2 | 2018 | | | | | | | | | | | | | | | |
| 3 | 2019 | | | | | | | | | | | | | | | |
| 4 | 2020 | 3360 | 220 | 85.2 | 434.4 | 2925.6 | 194.3 | 0.8594 | 0.7628 | 149.97 | 146.8 | 112.0 | 34.8 | 6348.8 | 99.17 | 99.17 |
| 5 | 2021 | 3381 | 220 | 85.2 | 434.4 | 2946.6 | 194.3 | 0.8656 | 0.7725 | 149.97 | 148.7 | 113.4 | 35.3 | 6429.9 | 15.62 | 100.44 |
| 6 | 2022 | 6621 | 400 | 88 | 448.7 | 6172.3 | 452.9 | 0.7779 | 0.6397 | 192.27 | 202.3 | 154.4 | 48.0 | 8750.3 | 15.62 | 136.68 |
| 7 | 2023 | 8053 | 400 | 88 | 448.7 | 7604.3 | 452.9 | 0.9584 | 0.9264 | 192.27 | 293.0 | 223.6 | 69.5 | 12673.1 | 15.62 | 197.95 |
| 8 | 2024 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 9 | 2025 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 10 | 2026 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 11 | 2027 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 12 | 2028 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 13 | 2029 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 14 | 2030 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 15 | 2031 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 16 | 2032 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 17 | 2033 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 18 | 2034 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 19 | 2035 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 20 | 2036 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 21 | 2037 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 22 | 2038 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 23 | 2039 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 24 | 2040 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 25 | 2041 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 26 | 2042 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 27 | 2043 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 28 | 2044 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 29 | 2045 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 30 | 2046 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 31 | 2047 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 32 | 2048 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 33 | 2049 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 34 | 2050 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 35 | 2051 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 36 | 2052 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 37 | 2053 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 38 | 2054 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 39 | 2055 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 40 | 2056 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 41 | 2057 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 42 | 2058 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 43 | 2059 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 44 | 2060 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 45 | 2061 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 46 | 2062 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 47 | 2063 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 48 | 2064 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 49 | 2065 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |
| 50 | 2066 | 9343 | 400 | 114 | 581.2 | 8761.8 | 709.8 | 0.7046 | 0.5380 | 301.33 | 418.0 | 318.9 | 99.1 | 18078.4 | 15.62 | 282.38 |


Loss Reduction Calculation of the 220kV Sampoor - Kappalturai T/L


| | | | | |
|----------------------|--------------------------|------------------------|------------------|------------------|
| Power factor | 0.85 | Conductor cost | | |
| Load factor of 220kV | 0.582 | - ACSR Zebra | 770 JPY/m | 670 LKR/m |
| Conductor Resistance | | - LL-ACSR/AC 550 | 1,079 JPY/m | 939 LKR/m |
| - ACSR Zebra | 0.0814 Ohm/km at 63 deg. | Cost Difference per km | 3,708,000 JPY/km | 3,225,960 LKR/km |
| - LL-ACSR/AC 550 | 0.0621 Ohm/km at 61 deg. | Rate | 0.87 LKR/yen | |
| Bundle | 2 bundle | | | |
| Length of S-H T/L | 45 km | | | |

| | Year | Generation at Sampoor (GWh) | Operation Voltage of S-H T/L (kV) | Sending per 1cct of S-K T/L (MW) | Load Loss Factor of S-K T/L | Current per conductor (A) | Annual losses on Zebra per cct (MWh/km) | Annual losses on LL per cct (MWh/km) | Annual Loss reduction per cct (MWh/km) | Annual Loss reduction (MWh/km) | Annual Loss reduction (MWh) | Tariff (kWh/Y) | Loss reduction benefits equivalent Sales Amounts (JPY/km) | Sum of Annual Benefit Amounts (JPY/km) |
|----|------|-----------------------------|-----------------------------------|----------------------------------|-----------------------------|---------------------------|---|--------------------------------------|--|--------------------------------|-----------------------------|----------------|---|--|
| 1 | 2017 | | | | | | | | | | | | | |
| 2 | 2018 | | | | | | | | | | | | | |
| 3 | 2019 | | | | | | | | | | | | | |
| 4 | 2020 | 3360 | 220 | 39.3 | 0.3874 | 60.67 | 6.1 | 4.7 | 1.4 | 2.9 | 130.2 | 15.62 | 45,184 | 45,184 |
| 5 | 2021 | 3381 | 220 | 39.3 | 0.3874 | 60.67 | 6.1 | 4.7 | 1.4 | 2.9 | 130.2 | 15.62 | 45,184 | 90,368 |
| 6 | 2022 | 6621 | 220 | 44.1 | 0.3874 | 68.08 | 7.7 | 5.9 | 1.8 | 3.6 | 163.9 | 15.62 | 56,895 | 147,263 |
| 7 | 2023 | 8053 | 220 | 44.1 | 0.3874 | 68.08 | 7.7 | 5.9 | 1.8 | 3.6 | 163.9 | 15.62 | 56,895 | 204,158 |
| 8 | 2024 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 299,540 |
| 9 | 2025 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 394,922 |
| 10 | 2026 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 490,304 |
| 11 | 2027 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 585,686 |
| 12 | 2028 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 681,068 |
| 13 | 2029 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 776,450 |
| 14 | 2030 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 871,832 |
| 15 | 2031 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 967,214 |
| 16 | 2032 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 1,062,596 |
| 17 | 2033 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 1,157,978 |
| 18 | 2034 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 1,253,360 |
| 19 | 2035 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 1,348,742 |
| 20 | 2036 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 1,444,124 |
| 21 | 2037 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 1,539,506 |
| 22 | 2038 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 1,634,888 |
| 23 | 2039 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 1,730,270 |
| 24 | 2040 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 1,825,652 |
| 25 | 2041 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 1,921,034 |
| 26 | 2042 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 2,016,416 |
| 27 | 2043 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 2,111,798 |
| 28 | 2044 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 2,207,180 |
| 29 | 2045 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 2,302,562 |
| 30 | 2046 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 2,397,944 |
| 31 | 2047 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 2,493,326 |
| 32 | 2048 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 2,588,708 |
| 33 | 2049 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 2,684,090 |
| 34 | 2050 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 2,779,472 |
| 35 | 2051 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 2,874,854 |
| 36 | 2052 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 2,970,236 |
| 37 | 2053 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 3,065,618 |
| 38 | 2054 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 3,161,000 |
| 39 | 2055 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 3,256,382 |
| 40 | 2056 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 3,351,764 |
| 41 | 2057 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 3,447,146 |
| 42 | 2058 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 3,542,528 |
| 43 | 2059 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 3,637,910 |
| 44 | 2060 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 3,733,292 |
| 45 | 2061 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 3,828,674 |
| 46 | 2062 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 3,924,056 |
| 47 | 2063 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 4,019,438 |
| 48 | 2064 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 4,114,820 |
| 49 | 2065 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 4,210,202 |
| 50 | 2066 | 9343 | 220 | 57.1 | 0.3874 | 88.15 | 12.9 | 9.8 | 3.1 | 6.1 | 274.8 | 15.62 | 95,382 | 4,305,584 |




SL-SP SS-LY-001 : Layout Drawing for the Sampoor 220 kV Switching Station






GROUND FLOOR PLAN
SCALE A


| No. | Equipment |
|-----|---|
| ① | 220 kV GIS (1+1/2 Circuit Breaker Scheme) |
| ② | Local Control Board |
| ③ | Communication Equipment |
| ④ | 220 kV Protection Panel |
| ⑤ | 33 kV Distribution Board |
| ⑥ | Control Equipment (Micro SCADA) |




UPPER FLOOR PLAN
SCALE A




SECTION A-A
SCALE B




SECTION X-X
SCALE B




SECTION Y-Y
SCALE B







Phase 1 :
 Layout for the Sampoor 220 kV Switching Station




Phase 2 :
 Preceding Construction for the 400 kV Substation



Phase 3 :
 Layout for Sampoor the 220 kV Switching Station
 and 400 kV Substation (1 cct)



Phase 4 :
Layout for Sampoor the 400 kV Substation (2 cct)



Phase 5 :
 Layout for the Sampoor 400 kV Substation (2 cct)
 Final Phase

220 KV OVERHEAD T/L (2 CCT)
TO SAMPOOR SS

FROM PALUGASWEWA

PUBLIC ROAD

TO HABARANA

SECURITY FENCE

220 kV BUSBAR

ACCESS ROAD

NEW HABARANA
220 / 132 / 33 kV
SUBSTATION

220 / 132 / 33 kV
Transformer

Land for the New Habarana 400 kV Substation

315 m

450.0 m


Phase 1 :
Layout for the New Habarana 220 KV Grid Substation

220 KV OVERHEAD T/L (2 CCT)
TO SAMPOOR SS

FROM PALUGASWEWA

PUBLIC ROAD

TO HABARANA




Phase 2 :
Preceding Construction for the 400 kV Grid Substation

400 KV and 220kV OVERHEAD T/L
TO SAMPOOR SS


FROM PALUGASWEWA

PUBLIC ROAD

TO HABARANA



Phase 3 :
Layout for the New Habarana 220 KV Grid Substation (1 cct)
Layout for the 400 kV Grid Substation (1 cct)




Phase 4 :
Layout for the New Habarana 400 KV Grid Substation (2 cct)

400 KV OVERHEAD T/L (2 CCT)
TO SAMPOOR SS

FROM PALUGASWEWA

PUBLIC ROAD

TO HABARANA



Phase 5 :
Layout for the New Habarana 400 KV Grid Substation (2 cct)
Final Phase

**Terms of Reference for Supervision Consultant for the works under
National Transmission and Distribution Network Development and
Efficiency Improvement Project (II)
in
Democratic Socialist Republic of Sri Lanka
(Draft)**

Chapter 1. Background

- (1) Sri Lanka has 2,970 MW electric power supply capability (2012) and 2,146 MW electricity peak demand (2012), and its power system is stable comparing with other South Asian countries. However, the economy has had the annual average growth rate of 7%, and the economic growth has caused electricity demand increase at the annual average rate of 5-6% in recent years. Therefore, Government of Sri Lanka promotes the construction of large-scale coal-fired power plants based on the long term generation expansion plan in order to meet the rapid expansion of electricity demand and decrease the generation cost. On the other hand, transmission and distribution system loss rate is improved year by year (12.0% as of 2012). However, it is necessary to reduce the transmission and distribution system loss rate more and more by the introduction of high voltage transmission system, low-loss conductor, etc. in order to meet the power demand expansion. Ministry of Power and Energy (MOPE) published the electrical policy for steady power supply and energy efficiency as one of the important policies in national energy policy (2006), and considered to introduce high voltage transmission systems which had enough transmission capacity in parallel with the construction of the large-scale power station. In addition, introduction of low-loss conductor is promoted from the point of view of transmission loss reduction simultaneously. Component of “National Transmission and Distribution Network Development and Efficiency Improvement Project (II) (hereinafter referred to as ‘the Project’)” is to construct transmission lines from Sampoor coal-fired power plant (250 MW x 2) to New Habarana Substation (which locates between Sampoor coal-fired power plant and Colombo area) and Kappalturai substation in order to evacuate the electric power from Sampoor coal-fired power plant constructed by Trincomalee Power Company Limited (TPCL: special-purpose company by the co-funding of National Thermal Power Corporation (NTPC) in India and Ceylon Electricity Board (CEB)). In addition, related switching station/ substation are also included in the Project for the stable power supply. Another purpose of the Project is energy efficiency by the introduction of extra high voltage (400 kV) transmission facilities for the first time and low-loss conductor.
- (2) Based on the above background, the Government of Sri Lanka requested to receive a loan from the Japan International Cooperation Agency (hereinafter referred to as “JICA”) to

finance the National Transmission and Distribution Network Development and Efficiency Improvement Project (II) which is to enhance transmission network system in Sri Lanka.

(3) The Project consists of the following components:

- a) Construction of 400 kV designed Sampoor – New Habarana TL (220 kV operation)
- b) Construction of 220 kV Sampoor – Kappalturai TL
- c) Construction of 220 kV GIS at Sampoor SS

(4) The Government of Sri Lanka intends to use part of the proceeds of the loan for eligible payments for consulting services for which this ToR is issued.

(5) The Project is expected to be completed by the end of 2018.

(6) Location of the Project: See (3) of this Chapter

(7) Executing Agency: CEB (Ceylon Electricity Board)

Chapter 2. Objectives of Consulting Services

The consulting services shall be provided by an international consulting firm (or any other relevant entity) (hereinafter referred to as “the Consultant”) selected in compliance with Guidelines for the Employment of Consultants under Japanese ODA Loans, April 2012.

The services to be rendered by the Consultant will cover construction supervision partially. Expected consulting services period is approximately 14 months.

Chapter 3. Scope of Consulting Services

3.1 Project Implementation Stage

The Consultant shall perform his duties during the construction period in accordance with the contracts to be executed between the Employer and the Contractors. FIDIC Plant and Design Build First Edition (1999) will be applied to the works of the Project.

The Consultant is requested to be (behave) “advisor”.

In addition to roles of “Engineer” above, the Consultant shall also carry out the followings:

- To assist in review of the detailed design documents of 400 kV transmission line and 220 kV GIS prepared by the Contractors
- To assist in carrying out construction supervision of 400 kV transmission line and 220 kV GIS in view of quality control and scheduling control
- To assist in inspection of manufacturing and fabrications of 400 kV transmission line and 220 kV GIS at the site
- To assist in review and approval for testing procedure prepared by Contractors.
- To witness the testing and commissioning at site as well as factory acceptance tests.
- To check the as-built drawings and operation & maintenance manuals prepared by the Contractors.

3.2 Co-ordination

The Consultant will assist CEB to maintain proper co-ordination and communication between CEB/JICA and CEB/Contractors.

Chapter 4. Expected Time Schedule

The total duration of consulting services will be 24 months. The implementation schedule expected is as shown in Table 1.

Table 1: Implementation Schedule Tentative

| Key activities | Data (FY) | Expected Duration in Months |
|------------------------------------|---------------|-----------------------------|
| Commencement of construction | January 2017 | 24 |
| End of construction | December 2018 | |
| Termination of Consulting Services | December 2018 | 24 |

Chapter 5. Staffing

Refer to the page **.

2 of Professional (A) consultants will be engaged, over 24 month's duration of consulting services, for a total of 40.0 man-months for Professional (A).

A detailed schedule of consulting services of person-months is shown in Attachment xx.

The qualification of key Team Members is shown in Table 2.

Table 2: Qualification of Key Team Members

| Designation | Qualification |
|-----------------------------------|---|
| International Consultants (Pro-A) | |
| Transmission Line Engineer | <p><u>Education:</u></p> <ul style="list-style-type: none">• Graduate in Electrical Engineering <p><u>Experience:</u></p> <ul style="list-style-type: none">• In the power transmission system related field: 15 years or more• In design and/or construction supervision for transmission line projects: 10 years or more• In design and/or supervision of installation works for transmission line projects: 2 projects or more |
| Substation Engineer | <p><u>Education:</u></p> <ul style="list-style-type: none">• Graduate in Electrical Engineering <p><u>Experience:</u></p> <ul style="list-style-type: none">• In the power transmission system related field: 15 years or more• In design and/or construction supervision for substation (including GIS) projects: 10 years or more• In design and/or supervision of installation works for substation projects: 2 projects or more |

Chapter 6. Meager Tasks and Duties of Team members

6.1 Transmission Line Engineer

- Assist in review of the detailed design documents of 400 kV transmission line prepared by the Contractors.
- Assist in carrying out construction supervision of 400 kV transmission line in view of quality control and scheduling control.
- Assist in inspection of manufacturing and fabrications of 400 kV transmission line at the site.
- Assist in review and approval for testing procedure prepared by Contractors.
- Witness the testing and commissioning at site as well as factory acceptance tests.
- Check the as-built drawings and operation & maintenance manuals prepared by the Contractors.

6.2 Substation Engineer

- Assist in review of the detailed design documents of 220 kV GIS prepared by the Contractors
- Assist in carrying out construction supervision of 220 kV GIS in view of quality control and scheduling control
- Assist in inspection of manufacturing and fabrications of GIS at the site
- Assist in review and approval for testing procedure prepared by Contractors.
- Witness the testing and commissioning at site as well as factory acceptance tests.
- Check the as-built drawings and operation & maintenance manuals prepared by the Contractors.

Chapter 7. Reports to be prepared by the Consultant

The Consultant shall prepare and submit to the Owner for the following reports:

- Site Work Report

Chapter 8. Obligation of the Executing Agency

The followings are assumed to be provided from the Executing Agency for the consulting services:

- To provide to the Consultants in an expeditious manner access to and copies of studies, plans, specifications, maps, drawings, criteria, and other information related to the Project, if available to CEB and necessary for the Consultants to perform the Services, at no expense to the Consultants.
- To assist the Consultants in obtaining customs clearance for materials or equipment brought into Sri Lanka for performance of the Services by the Consultants. CEB and/or

government of Sri Lanka shall directly pay the customs duties associated with materials or equipment reimbursable hereunder brought for the jobsite office only, which at completion of the Project will be delivered to CEB as CEB's property.

- To assist the Consultants, if required, in obtaining clearances, visas, and extensions; resident work permits; and any other documents relating to Expatriates of the Consultant, their accompanying dependents, and their personal effects assigned to perform the Services and shall use its best efforts to assist the Consultant, its Sub-consultants, and employees to obtain the benefit of all privileges, exemptions, and other favorable treatment, which are or may become lawfully available under any decisions, laws, regulations, or rules of Sri Lanka.
- To provide overall management, direction, and control of the Project. In addition, CEB intends to provide a dedicated CEB's team for the Project to coordinate with the Consultants' project team.
- To facilitate and expedite the Services, CEB shall approve or object to the Consultants' replies and/or recommendations within two weeks after receipt of such replies/recommendations made during the Project's implementation period and in accordance with the Project's milestone schedule. For the purposes of assuring continuity in the performance of the Consultants' Services, in the event approval or objection is not made within such two weeks period, the replies/recommendations shall be deemed approved unless otherwise agreed for a longer period.

Annex 10.2-1 Assumed Construction Cost of Transmission Lines

1. Assumed Construction Cost of 400 kV Sampoor - New Habarana Transmission Line

Rate= 130.2 LKR / USD

| Item | Specification | Unit Wt[t] | No. of Tower | Tot. Wt[t] | Sampoor - New Habarana | | | | | |
|---|------------------------|------------|----------------|-----------------|------------------------|----------|----------------------|-------------------|----------|-------------------|
| | | | | | FC [LKR] | LC [LKR] | Total [LKR] | FC [USD] | LC [USD] | Total [USD] |
| | | | | | 230,040 LKR/t | 0 LKR/t | | | | |
| Towers | | | | | | | | | | |
| Suspension Tower (TDL) | Body extension +0m | 49.1 | 22 | 1,080.2 | 248,489,208 | 0 | 248,489,208 | 1,908,519 | 0 | 1,908,519 |
| Suspension Tower (TDL) | Body extension +3m | 55.4 | 143 | 7,922.2 | 1,822,422,888 | 0 | 1,822,422,888 | 13,997,104 | 0 | 13,997,104 |
| Suspension Tower (TDL) | Body extension +6m | 94.4 | 3 | 283.2 | 65,147,328 | 0 | 65,147,328 | 500,364 | 0 | 500,364 |
| Suspension Tower (TDL) | Body extension +9m | 61.8 | 1 | 61.8 | 14,216,472 | 0 | 14,216,472 | 109,190 | 0 | 109,190 |
| Tension Tower 0-10 (TD1) | Body extension +0m | 45.5 | 6 | 273.2 | 62,851,989 | 0 | 62,851,989 | 482,734 | 0 | 482,734 |
| Tension Tower 0-10 (TD1) | Body extension +3m | 47.6 | 2 | 95.2 | 21,888,767 | 0 | 21,888,767 | 168,117 | 0 | 168,117 |
| Tension Tower 0-10 (TD1) | Body extension +6m | 54.3 | 2 | 108.6 | 24,990,166 | 0 | 24,990,166 | 191,937 | 0 | 191,937 |
| Tension Tower 0-10 (TD1) | Body extension +9m | 60.1 | 0 | 0.0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Tension Tower 10-30 (TD3) | Body extension +0m | 56.2 | 17 | 954.7 | 219,619,879 | 0 | 219,619,879 | 1,686,789 | 0 | 1,686,789 |
| Tension Tower 10-30 (TD3) | Body extension +3m | 58.8 | 3 | 176.5 | 40,612,872 | 0 | 40,612,872 | 311,927 | 0 | 311,927 |
| Tension Tower 10-30 (TD3) | Body extension +6m | 64.8 | 2 | 129.5 | 29,794,321 | 0 | 29,794,321 | 228,835 | 0 | 228,835 |
| Tension Tower 10-30 (TD3) | Body extension +9m | 72.2 | 0 | 0.0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Tension Tower 30-60 (TD6) | Body extension +0m | 67.7 | 10 | 677.3 | 155,812,994 | 0 | 155,812,994 | 1,196,720 | 0 | 1,196,720 |
| Tension Tower 30-60 (TD6) | Body extension +3m | 71.0 | 5 | 354.9 | 81,636,596 | 0 | 81,636,596 | 627,009 | 0 | 627,009 |
| Tension Tower 30-60 (TD6) | Body extension +6m | 77.7 | 2 | 155.4 | 35,738,555 | 0 | 35,738,555 | 274,490 | 0 | 274,490 |
| Tension Tower 30-60 (TD6) | Body extension +9m | 85.6 | 0 | 0.0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Terminal Tower (TDT) | Body extension +0m | 151.9 | 1 | 151.9 | 34,935,485 | 0 | 34,935,485 | 268,322 | 0 | 268,322 |
| Terminal Tower (TDT) | Body extension +3m | 167.3 | 5 | 836.4 | 192,406,607 | 0 | 192,406,607 | 1,477,777 | 0 | 1,477,777 |
| Terminal Tower (TDT) | Body extension +6m | 184.3 | 0 | 0.0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Terminal Tower (TDT) | Body extension +9m | 194.4 | 0 | 0.0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Total Tower | | | 224 | 13,261.0 | 3,050,564,127 | 0 | 3,050,564,127 | 23,429,832 | 0 | 23,429,832 |
| Conductors | | | | | | | | | | |
| | | [Unit] | Qty | Unit Price | FC [LKR] | LC [LKR] | Total [LKR] | FC [USD] | LC [USD] | Total [USD] |
| LL-ACSR eq Zebra | | [km] | 0.0 | 1,079,000 | 0 | 0 | 0 | 0 | 0 | 0 |
| Zebra/AS | | [km] | 2,188.8 | 770,000 | 1,685,376,000 | 0 | 1,685,376,000 | 12,944,516 | 0 | 12,944,516 |
| Total Conductor | | | 2,188.8 | | 1,685,376,000 | 0 | 1,685,376,000 | 12,944,516 | 0 | 12,944,516 |
| Earth Wires | | | | | | | | | | |
| AS 110 | | [km] | 91.2 | 243,000 | 22,161,600 | 0 | 22,161,600 | 170,212 | 0 | 170,212 |
| OPGW 120 | | [km] | 91.2 | 611,000 | 55,698,760 | 0 | 55,698,760 | 427,794 | 0 | 427,794 |
| Total Earth wire | | | 182.4 | | 77,860,360 | 0 | 77,860,360 | 598,006 | 0 | 598,006 |
| Insulators | | | | | | | | | | |
| U160 BS | Suspension tower | [Nos.] | 38,976 | 4,900 | 190,982,400 | 0 | 190,982,400 | 1,466,839 | 0 | 1,466,839 |
| U160 BS | Tension tower | [Nos.] | 54,432 | 4,900 | 266,716,800 | 0 | 266,716,800 | 2,048,516 | 0 | 2,048,516 |
| U160 BLP (Anti-fog) | Suspension tower | [Nos.] | 13,356 | 7,600 | 101,505,600 | 0 | 101,505,600 | 779,613 | 0 | 779,613 |
| U160 BLP (Anti-fog) | Tension tower | [Nos.] | 11,592 | 7,600 | 88,099,200 | 0 | 88,099,200 | 676,645 | 0 | 676,645 |
| U70BL | | [Nos.] | 1,008 | 2,400 | 2,419,200 | 0 | 2,419,200 | 18,581 | 0 | 18,581 |
| U70BLP (Anti-fog) | | [Nos.] | 252 | 4,700 | 1,184,400 | 0 | 1,184,400 | 9,097 | 0 | 9,097 |
| Total Insulators | | | 119,616 | | 650,907,600 | 0 | 650,907,600 | 4,999,290 | 0 | 4,999,290 |
| Spacer dumpers | | | | | | | | | | |
| 4 bundle spacer | LL-ACSR eq Zebra | [Nos.] | 10,944 | 2,400 | 26,265,600 | 0 | 26,265,600 | 201,733 | 0 | 201,733 |
| 4-bundle jumper spacer | LL-ACSR eq Zebra | [Nos.] | 330 | 2,400 | 792,000 | 0 | 792,000 | 6,083 | 0 | 6,083 |
| Total Spacer dumpers | | | 11,274 | | 27,057,600 | 0 | 27,057,600 | 207,816 | 0 | 207,816 |
| Insulator set | | | | | | | | | | |
| Normal suspension insulator set double-strings | | [Sets] | 696 | 140,000 | 97,440,000 | 0 | 97,440,000 | 748,387 | 0 | 748,387 |
| Anti-fog suspension insulator set double-strings | | [Sets] | 318 | 300,000 | 95,400,000 | 0 | 95,400,000 | 732,719 | 0 | 732,719 |
| Normal tension insulator set quad-strings | | [Sets] | 486 | 350,000 | 170,100,000 | 0 | 170,100,000 | 1,306,452 | 0 | 1,306,452 |
| Anti-fog tension insulator set quad-strings | | [Sets] | 138 | 800,000 | 110,400,000 | 0 | 110,400,000 | 847,926 | 0 | 847,926 |
| Jumper suspension insulator set single-string including | | [Sets] | 0 | 120,000 | 0 | 0 | 0 | 0 | 0 | 0 |
| Anti-fog Jumper suspension insulator set single-string | | [Sets] | 0 | 300,000 | 0 | 0 | 0 | 0 | 0 | 0 |
| Inverted type tension insulator set quad-strings | | [Sets] | 0 | 300,000 | 0 | 0 | 0 | 0 | 0 | 0 |
| Inverted type anti-fog tension insulator set quad-strings | | [Sets] | 0 | 800,000 | 0 | 0 | 0 | 0 | 0 | 0 |
| Light duty tension insulator set single-string | | [Sets] | 36 | 150,000 | 5,400,000 | 0 | 5,400,000 | 41,475 | 0 | 41,475 |
| Light duty anti-fog tension insulator set | | [Sets] | 12 | 320,000 | 3,840,000 | 0 | 3,840,000 | 29,493 | 0 | 29,493 |
| Suspension sets for earth wire AS 110 | | [Sets] | 169 | 5,000 | 845,000 | 0 | 845,000 | 6,490 | 0 | 6,490 |
| Suspension sets for earth wire OPGW 120 | | [Sets] | 169 | 6,400 | 1,081,600 | 0 | 1,081,600 | 8,307 | 0 | 8,307 |
| Tension sets for earth wire AS 110 | | [Sets] | 112 | 4,100 | 459,200 | 0 | 459,200 | 3,527 | 0 | 3,527 |
| Tension sets for earth wire OPGW 120 | | [Sets] | 112 | 6,000 | 672,000 | 0 | 672,000 | 5,161 | 0 | 5,161 |
| Preformed amor rod Zebra eq | | [Sets] | 4,056 | 3,600 | 14,601,600 | 0 | 14,601,600 | 112,147 | 0 | 112,147 |
| Total Insulator set | | | | | 500,239,400 | 0 | 500,239,400 | 3,842,085 | 0 | 3,842,085 |
| Other supply | | | | | | | | | | |
| Other supply | 6% of total cost above | | 1 | 359,520,305 | 359,520,305 | 0 | 359,520,305 | 2,761,293 | 0 | 2,761,293 |
| A. Total Supply | | | | | 6,351,525,392 | 0 | 6,351,525,392 | 48,782,837 | 0 | 48,782,837 |

| Item | [Unit] | Qty | Unit Price | FC [LKR] | LC [LKR] | Total [LKR] | FC [USD] | LC [USD] | Total [USD] |
|---|--------|------|------------|----------|-------------------|-------------------|----------|----------------|----------------|
| Design and Drawings | | | | | | | | | |
| Design and liaison of works | [km] | 91.2 | 180,000 | 0 | 16,416,000 | 16,416,000 | 0 | 126,083 | 126,083 |
| Drawings and Documentation required for works | [km] | 91.2 | 180,000 | 0 | 16,416,000 | 16,416,000 | 0 | 126,083 | 126,083 |
| B. Total Design and Drawings | | | | 0 | 32,832,000 | 32,832,000 | 0 | 252,166 | 252,166 |

| Item | Specification | [Unit] | Qty | Unit Price | FC [LKR] | LC [LKR] | Total [LKR] | FC [USD] | LC [USD] | Total [USD] |
|------------------------------|------------------------------------|---------|------|-------------|----------|----------------------|----------------------|----------|-------------------|-------------------|
| Foundation Work | | | | | | | | | | |
| TDL Tower foundation | Pad and chimney | [Units] | 162 | 6,471,000 | 0 | 1,048,302,000 | 1,048,302,000 | 0 | 8,051,475 | 8,051,475 |
| TD1 Tower foundation | Pad and chimney | [Units] | 10 | 6,886,000 | 0 | 68,860,000 | 68,860,000 | 0 | 528,879 | 528,879 |
| TD3 Tower foundation | Pad and chimney | [Units] | 22 | 7,566,000 | 0 | 166,452,000 | 166,452,000 | 0 | 1,278,433 | 1,278,433 |
| TD6 Tower foundation | Pad and chimney | [Units] | 17 | 17,853,000 | 0 | 303,501,000 | 303,501,000 | 0 | 2,331,037 | 2,331,037 |
| TDT Tower foundation | Pad and chimney | [Units] | 6 | 31,437,000 | 0 | 188,622,000 | 188,622,000 | 0 | 1,448,710 | 1,448,710 |
| TDL Tower foundation | pile foundation | [Units] | 7 | 12,942,000 | 0 | 90,594,000 | 90,594,000 | 0 | 695,806 | 695,806 |
| TD1 Tower foundation | pile foundation | [Units] | 0 | 13,772,000 | 0 | 0 | 0 | 0 | 0 | 0 |
| TD3 Tower foundation | pile foundation | [Units] | 0 | 15,132,000 | 0 | 0 | 0 | 0 | 0 | 0 |
| TD6 Tower foundation | pile foundation | [Units] | 0 | 35,706,000 | 0 | 0 | 0 | 0 | 0 | 0 |
| TDT Tower foundation | pile foundation | [Units] | 0 | 62,874,000 | 0 | 0 | 0 | 0 | 0 | 0 |
| Total Foundation Work | | | | | | 1,866,331,000 | 1,866,331,000 | 0 | 14,334,340 | 14,334,340 |
| Tower Erection | | | | | | | | | | |
| Suspension Tower (TDL) | Body extension +0m | [Unit] | 22 | 1,136,000 | 0 | 24,992,000 | 24,992,000 | 0 | 191,951 | 191,951 |
| Suspension Tower (TDL) | Body extension +3m | [Unit] | 143 | 1,281,000 | 0 | 183,183,000 | 183,183,000 | 0 | 1,406,935 | 1,406,935 |
| Suspension Tower (TDL) | Body extension +6m | [Unit] | 3 | 1,429,000 | 0 | 4,287,000 | 4,287,000 | 0 | 32,926 | 32,926 |
| Suspension Tower (TDL) | Body extension +9m | [Unit] | 1 | 2,183,000 | 0 | 2,183,000 | 2,183,000 | 0 | 16,767 | 16,767 |
| Tension Tower 0-10 (TD1) | Body extension +0m | [Unit] | 6 | 1,053,000 | 0 | 6,318,000 | 6,318,000 | 0 | 48,525 | 48,525 |
| Tension Tower 0-10 (TD1) | Body extension +3m | [Unit] | 2 | 1,101,000 | 0 | 2,202,000 | 2,202,000 | 0 | 16,912 | 16,912 |
| Tension Tower 0-10 (TD1) | Body extension +6m | [Unit] | 2 | 1,256,000 | 0 | 2,512,000 | 2,512,000 | 0 | 19,293 | 19,293 |
| Tension Tower 0-10 (TD1) | Body extension +9m | [Unit] | 0 | 1,391,000 | 0 | 0 | 0 | 0 | 0 | 0 |
| Tension Tower 10-30 (TD3) | Body extension +0m | [Unit] | 17 | 1,299,000 | 0 | 22,083,000 | 22,083,000 | 0 | 169,608 | 169,608 |
| Tension Tower 10-30 (TD3) | Body extension +3m | [Unit] | 3 | 1,361,000 | 0 | 4,083,000 | 4,083,000 | 0 | 31,359 | 31,359 |
| Tension Tower 10-30 (TD3) | Body extension +6m | [Unit] | 2 | 1,498,000 | 0 | 2,996,000 | 2,996,000 | 0 | 23,011 | 23,011 |
| Tension Tower 10-30 (TD3) | Body extension +9m | [Unit] | 0 | 1,669,000 | 0 | 0 | 0 | 0 | 0 | 0 |
| Tension Tower 30-60 (TD6) | Body extension +0m | [Unit] | 10 | 1,567,000 | 0 | 15,670,000 | 15,670,000 | 0 | 120,353 | 120,353 |
| Tension Tower 30-60 (TD6) | Body extension +3m | [Unit] | 5 | 1,642,000 | 0 | 8,210,000 | 8,210,000 | 0 | 63,057 | 63,057 |
| Tension Tower 30-60 (TD6) | Body extension +6m | [Unit] | 2 | 1,797,000 | 0 | 3,594,000 | 3,594,000 | 0 | 27,604 | 27,604 |
| Tension Tower 30-60 (TD6) | Body extension +9m | [Unit] | 0 | 1,979,000 | 0 | 0 | 0 | 0 | 0 | 0 |
| Terminal Tower (TDT) | Body extension +0m | [Unit] | 1 | 3,512,000 | 0 | 3,512,000 | 3,512,000 | 0 | 26,974 | 26,974 |
| Terminal Tower (TDT) | Body extension +3m | [Unit] | 5 | 3,868,000 | 0 | 19,340,000 | 19,340,000 | 0 | 148,541 | 148,541 |
| Terminal Tower (TDT) | Body extension +6m | [Unit] | 0 | 4,262,000 | 0 | 0 | 0 | 0 | 0 | 0 |
| Terminal Tower (TDT) | Body extension +9m | [Unit] | 0 | 4,495,000 | 0 | 0 | 0 | 0 | 0 | 0 |
| Total Tower Erection | | | | | | 305,165,000 | 305,165,000 | 0 | 2,343,817 | 2,343,817 |
| Stringing | | | | | | | | | | |
| Stringing | includes installation of insulator | [km] | 91.2 | 1,530,000 | 0 | 139,536,000 | 139,536,000 | 0 | 1,071,705 | 1,071,705 |
| Total String | | | | | | 139,536,000 | 139,536,000 | 0 | 1,071,705 | 1,071,705 |
| Other work | | | | | | | | | | |
| Other work | 10% of total cost above | | 1.0 | 231,103,200 | 0 | 231,103,200 | 231,103,200 | 0 | 1,774,986 | 1,774,986 |
| C. Civil work | | | | | | 2,542,135,200 | 2,542,135,200 | 0 | 19,524,848 | 19,524,848 |

| Item | [Unit] | Qty | Unit Price | FC [LKR] | LC [LKR] | Total [LKR] | FC [USD] | LC [USD] | Total [USD] | |
|--------------------------------|------------------------|-----|-------------|----------|-------------|--------------------|--------------------|-----------|------------------|------------------|
| Other services | | | | | | | | | | |
| Other services | 4% of total other cost | 1.0 | 357,059,704 | 0 | 357,059,704 | 357,059,704 | 0 | 2,742,394 | 2,742,394 | |
| D. Total Other services | | | | | | 357,059,704 | 357,059,704 | 0 | 2,742,394 | 2,742,394 |

Cost estimate for 400kV Sanpoor - New Habarana Transmission Lin

| Item | FC [LKR] | LC [LKR] | Total [LKR] | FC [USD] | LC [USD] | Total [USD] |
|----------------------------|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|
| A. Supply cost | 6,351,525,392 | 0 | 6,351,525,392 | 48,782,837.30 | 0.00 | 48,782,837.30 |
| B. Design and Drawing cost | 0 | 32,832,000 | 32,832,000 | 0.00 | 252,165.90 | 252,165.90 |
| C. Civil work cost | 0 | 2,542,135,200 | 2,542,135,200 | 0.00 | 19,524,848.03 | 19,524,848.03 |
| D. Other services cost | 0 | 357,059,704 | 357,059,704 | 0.00 | 2,742,394.04 | 2,742,394.04 |
| Total | 6,351,525,392 | 2,932,026,904 | 9,283,552,296 | 48,782,837.30 | 22,519,407.97 | 71,302,245.27 |
| Unit Price | 69,643,919 | 32,149,418 | 101,793,337 LKR/km | | | 781,822.86 USD/km |

| Item | Rate |
|--------------|---|
| | 0.823 Yen/LKR |
| Total in Yen | FC [Yen] 5,227,305,398 LC [Yen] 2,413,058,142 Total [Yen] 7,640,363,540 |
| Unit Price | 57,316,945 26,458,971 83,775,917 Yen/km |

| | | | |
|--------------------------------|-------------------|------------|--|
| Length of Transmission Line | | 91.2 km | |
| Nos. of Tower | Suspension tower | 169 towers | |
| | Tension tower | 49 towers | |
| | Terminal Tower | 6 towers | |
| | Substation gantry | 2 gantrys | Sanpoor S/S, New Habarana G/S |
| Anti-fog insulator using Tower | Suspension tower | 53 towers | Anti-fog insulator will use the tower that are within 10km from coast line |
| | Tension tower | 11 towers | (No.160 to No.224 Towers will use anti-fog insulator) |
| | Terminal Tower | 1 towers | |
| | Substation gantry | 1 gantry | |

2. Assumed Construction Cost of 220 kV Sanpoor - Kappalutrai Transmission Line

Escaretion rate

Foreign = 0.02 Local = 0.038 Rate: 0.823 Yen/LKR

| Year | Length (km) | Unit cost | | Total cost | | Unit cost | | Total cost |
|------|-------------|------------|------------|------------|------------|-----------|---------|------------|
| | | FC (MLKRs) | LC (MLKRs) | FC (MLKRs) | LC (MLKRs) | M Yen/km | M Yen | |
| 2013 | 45 | 39.10 | 15.72 | 1759.50 | 707.4 | 45.12 | 2030.26 | |
| 2014 | 45 | 39.88 | 16.32 | 1794.60 | 734.4 | 46.25 | 2081.37 | |

CEB data base for construction cost in 201:

| Transmission Line / Cable | Per km Cost (MLKR) | |
|-----------------------------|--------------------|-------|
| | FC | LC |
| 220kV 2xZebra double cct TL | 39.10 | 15.72 |
| 400kV 4xZebra double cct TL | 105.64 | 23.79 |
| 220kV Cu(XLPE) 1600mm2 cab | 289.80 | 32.20 |

(Source:CEB database)

Cost Estimate for Dispute Board (Standing)

Construction Period 24 Months
 Warranty Period 12 Months

Cost estimate for the regular Site visits is shown below:

| Cost Category | For 1 DB member for calculation purpose | | | 1-Person DB |
|---|---|--|------------------------------|----------------------|
| Monthly Retainer Fee | Fee 3,000 USD | Const Period x 24 Months | = | USD 72,000 |
| Monthly Retainer during DNP | Fee 2,000 USD | Const Period x 12 Months | = | USD 24,000 |
| Daily fee for Site Visits (3 days for Site visit, 1 day x 2 for travel) | Fee 3,000 USD | Const Period x 5 Days (3+2) | x 6 Times (1Nos/4 months) | USD 90,000 |
| Site Visit Expenses (Air tickets, accommodation, etc.) | Fee 1,000 USD | Const Period x 6 Times (1Nos/4 months) | = | USD 6,000 |
| Sub-Total (1) | | | | 192,000 |

Cost estimate for the referrals is shown below:

| Cost Category | For 1 DB member for calculation purpose | | | 1-Person DB |
|--|---|-----------------------------------|-----------|---------------|
| Additional Daily Fee at Regular Site Visits | Fee 3,000 USD | Const Period x 1 Days | x 2 Times | USD 6,000 |
| Reviewing Submission and Drafting Decision | Fee 3,000 USD | Const Period x 6 Days (3+3) | x 2 Times | USD 36,000 |
| Sub-Total (2) | | | | 42,000 |

| | | | | |
|--------------|--|--|--|----------------|
| Total | | | | 234,000 |
|--------------|--|--|--|----------------|

Cost Estimate for Dispute Board (Ad hoc)

Construction Period 24 Months
 Warranty Period 12 Months

Cost estimate for the referrals is shown below:

| Cost Category | For 1 DB member for calculation purpose | | | 1-Person DB |
|--|---|-------------------|-------------|---------------|
| Daily Fee at Regular Site Visits | Fee 3,000 USD | x 1 Days | x 2 Times = | USD 6,000 |
| Reviewing Submission and Drafting Decision | Fee 3,000 USD | x 6 Days (3+3) | x 2 Times = | USD 36,000 |
| Total | | | | 42,000 |

Cost Breakdown for 220 kV Sampoor Switching Station

US\$ 1 = 107.10 JPY

US\$ 1 = 130.2 LKR

LKR 1 = 0.823 JPY

(1) Cost breakdown for "One-and-half circuit breaker line bay 220 kV for GIS"

| Items | Unit | Qty. | Unit Price | | Foreign Portion (JPY) | Local Portion (LKR) | Total (JPY) | Total (USD) |
|-------------------------------------|-------|------|-------------|------------|--------------------------|------------------------|--------------------|------------------|
| | | | FC (JPY) | LC (LKR) | | | | |
| 1 GIS & Local control panel/cabinet | [bay] | 1 | 230,000,000 | 12,980,000 | 230,000,000 | 12,980,000 | 240,682,540 | 2,247,269 |
| 2 Supervisory service | [bay] | 1 | 5,000,000 | 0 | 5,000,000 | 0 | 5,000,000 | 46,685 |
| 3 Special tools | [bay] | 1 | 15,000,000 | 0 | 15,000,000 | 0 | 15,000,000 | 140,056 |
| Total | | | | | 250,000,000 | 12,980,000 | 260,682,540 | 2,434,011 |

(2) Cost Breakdown for "Common Items - GIS"

| Items | Unit | Qty. | Unit Price | | Foreign Portion (JPY) | Local Portion (LKR) | Total (JPY) | Total (USD) |
|---|---------|------|-------------|-------------|--------------------------|------------------------|--------------------|------------------|
| | | | FC (JPY) | LC (LKR) | | | | |
| 1 LVAC - 400 V Panel | [panel] | 4 | 2,698,938 | 151,650 | 10,795,752 | 606,600 | 11,294,984 | 105,462 |
| 2 Battery Charger and Distribution Boards | [panel] | 2 | 10,535,590 | 530,780 | 21,071,180 | 1,061,560 | 21,944,844 | 204,901 |
| 3 Lightning Arrester (Outdoor) | [unit] | 12 | 499,182 | 78,020 | 5,990,184 | 936,240 | 6,760,710 | 63,125 |
| 4 Fiber Optic/SCADA | [unit] | 1 | 17,932,920 | 606,610 | 17,932,920 | 606,610 | 18,432,160 | 172,102 |
| 5 Substation earthing | [lot] | 1 | 10,904,059 | 1,516,520 | 10,904,059 | 1,516,520 | 12,152,155 | 113,465 |
| 6 Transformers (33/0.4-0.23 kV, 200 kVA) | [unit] | 2 | 1,347,536 | 27,500 | 2,695,072 | 55,000 | 2,740,337 | 25,587 |
| 7 Cables and sealing ends | [lot] | 1 | 122,655,260 | 14,739,660 | 122,655,260 | 14,739,660 | 134,786,000 | 1,258,506 |
| 8 Civil works | [lot] | 1 | 18,143,015 | 212,549,014 | 18,143,015 | 212,549,014 | 193,070,853 | 1,802,716 |
| 9 Diesel Generator | [unit] | 1 | 3,736,025 | 303,300 | 3,736,025 | 303,300 | 3,985,641 | 37,214 |
| 10 Digital Disturbance Recorder | [unit] | 1 | 15,691,305 | 1,668,170 | 15,691,305 | 1,668,170 | 17,064,209 | 159,330 |
| Total | | | | | 229,614,772 | 234,042,674 | 422,231,892 | 3,942,408 |
| Total (Round) | | | | | 229,610,000 | 234,040,000 | 422,230,000 | 3,940,000 |

Note:

Cost Breakdown of Common Items were calculated as the following rules:

- 1) The original data as at 2013 was received by CEB.
- 2) The original data was modified the one as of 2015 in consideration with price escalation.
- 3) The price of "4 Cables and sealing ends" was reviewed and modified in accordance with the length of cable estimated by basic drawings as follows:
- 4) Total price for "4 Cables and sealing ends" calculated in 3) is distributed by the original ratio of FC and LC.

A) Detail Breakdown for Cable price (incl. construction cost)

| | Section | Unit | Qty. | Cable size | Unit Price (JPY) | Total Price (JPY) | Remarks |
|--------------|---|------|------|------------|---------------------|----------------------|--------------|
| 1 | 220 kV GIS to Gantry structure for Kappalthurei G/S | [m] | 60 | 800 sq | 33,600 | 12,096,000 | 2cct, 3phase |
| 2 | 220 kV GIS to Gantry structure for Sampoor CFPP | [m] | 50 | 2000 sq | 65,300 | 19,590,000 | 2cct, 3phase |
| 3 | 220 kV GIS to Gantry structure for New Habarana G/S | [m] | 200 | 1600 sq | 60,800 | 72,960,000 | 2cct, 3phase |
| Total | | | | | | 104,646,000 | |

B) Detail Breakdown for Cable sealing end (incl. construction cost)

| | Section | Unit | Qty. | Cable size | Unit Price (JPY) | Total Price (JPY) | Remarks |
|----------------------------------|---|-------|------|------------|---------------------|----------------------|------------|
| Cable Sealing End for AIS | | | | | | | |
| 1 | 220 kV GIS to Gantry structure for Kappalthurei G/S | [set] | 2 | 800 sq | 1,960,000 | 3,920,000 | 2cct |
| 2 | 220 kV GIS to Gantry structure for Sampoor CFPP | [set] | 2 | 2000 sq | 3,330,000 | 6,660,000 | 2cct |
| 3 | 220 kV GIS to Gantry structure for New Habarana G/S | [set] | 2 | 1600 sq | 3,330,000 | 6,660,000 | 2cct |
| Cable Sealing End for GIS | | | | | | | |
| 1 | 220 kV GIS to Gantry structure for Kappalthurei G/S | [set] | 2 | 800 sq | 1,510,000 | 3,020,000 | 2cct |
| 2 | 220 kV GIS to Gantry structure for Sampoor CFPP | [set] | 2 | 2000 sq | 2,470,000 | 4,940,000 | 2cct |
| 3 | 220 kV GIS to Gantry structure for New Habarana G/S | [set] | 2 | 1600 sq | 2,470,000 | 4,940,000 | 2cct |
| Total | | | | | | 30,140,000 | |
| A+B | | | | | | 134,786,000 | JPY |

(3) Cost Breakdown of "5 Civil Works"

| Items | Unit | Qty. | Unit Price | | Foreign Portion (JPY) | Local Portion (LKR) | Total (JPY) | Total (USD) |
|---|--------|---------|------------|------------|--------------------------|------------------------|--------------------|------------------|
| | | | FC (JPY) | LC (LKR) | | | | |
| 1 Preliminary work | [lot] | 1 | 145,227 | 61,037 | 145,227 | 610,368 | 647,560 | 6,046 |
| 2 Site Cleaning | [m2] | 59,150 | 51 | 30 | 3,019,376 | 1,766,272 | 4,473,018 | 41,765 |
| 3 Site formation & up keeping | [m2] | 59,150 | 0 | 387 | 0 | 22,891,050 | 18,839,334 | 175,904 |
| 4 Cable trenches duct | [m] | 310 | 0 | 21,062 | 0 | 6,529,220 | 5,373,548 | 50,173 |
| 5 Galvanized steel structures | [unit] | 6 | 1,552,265 | 880,182 | 9,313,591 | 5,281,092 | 13,659,930 | 127,544 |
| 6 Foundations for switchgear & take-off structure | [lot] | 1 | 0 | 12,468,735 | 0 | 12,468,735 | 10,261,769 | 95,815 |
| 7 Lightning protection system | [lot] | 1 | 871,361 | 366,221 | 871,361 | 366,221 | 1,172,761 | 10,950 |
| 8 Miscellaneous work | | | | | | | | |
| 8-1 Room for diesel generator | [lot] | 1 | 0 | 1,460,303 | 0 | 1,460,303 | 1,201,829 | 11,222 |
| 8-2 Shed for car parking | [unit] | 2 | 0 | 1,002,954 | 0 | 2,005,908 | 1,650,862 | 15,414 |
| 8-3 Guard room and watch tower | [lot] | 1 | 0 | 4,156,866 | 0 | 4,156,866 | 3,421,101 | 31,943 |
| 9 Water supply and drainage | [lot] | 1 | 0 | 3,811,228 | 0 | 3,811,228 | 3,136,641 | 29,287 |
| 10 Construction & maintenance road | | | | | | | | |
| 10-1 Approach road | [m] | 169 | 0 | 50,452 | 0 | 8,526,388 | 7,017,217 | 65,520 |
| 10-2 Structures for approach road | [m] | 169 | 0 | 18,329 | 0 | 3,097,601 | 2,549,326 | 23,803 |
| 10-3 Access roads & structures | [m] | 1070 | 0 | 10,666 | 0 | 11,412,620 | 9,392,586 | 87,699 |
| 11 Fence | [m] | 843 | 0 | 13,172 | 0 | 11,103,996 | 9,138,589 | 85,328 |
| 12 Miscellaneous work | [lot] | 1 | 455,944 | 1,916,272 | 455,944 | 1,916,272 | 2,033,036 | 18,983 |
| 13 Substation building | | | | | | | | |
| 13-1 Sub-structures | [m2] | 1361.25 | 0 | 23,383 | 0 | 31,830,109 | 26,196,180 | 244,596 |
| 13-2 Super structures | [m2] | 1361.25 | 0 | 35,111 | 0 | 47,794,849 | 39,335,161 | 367,275 |
| 13-3 Door & windows | [unit] | 24 | 0 | 109,197 | 0 | 2,620,728 | 2,156,859 | 20,139 |
| 13-4 Roof & ceiling | [lot] | 1 | 0 | 9,461,153 | 0 | 9,461,153 | 7,786,529 | 72,703 |
| 13-5 Floor & trenches | [m2] | 1739.25 | 0 | 5,852 | 0 | 10,178,091 | 8,376,569 | 78,213 |
| 13-6 Finishes & fittings | [lot] | 1 | 0 | 8,774,622 | 0 | 8,774,622 | 7,221,514 | 67,428 |
| 13-7 Curtaining & furniture | [lot] | 1 | 0 | 1,448,954 | 0 | 1,448,954 | 1,192,489 | 11,134 |
| 13-8 Supplying & erection crane | [unit] | 1 | 4,337,516 | 2,635,186 | 4,337,516 | 2,635,186 | 6,506,274 | 60,750 |
| 13-9 Miscellaneous building works | [lot] | 1 | 0 | 401,182 | 0 | 401,182 | 330,173 | 3,083 |
| 14 Supplying & installation services | | | | | | | | |
| 14-1 A/C ventilation system | [lot] | 1 | 3,131,968 | 890,624 | 3,131,968 | 890,624 | 3,864,952 | 36,087 |
| 14-2 Fire protection & detecting system | [lot] | 1 | 1,049,772 | 5,349,093 | 1,049,772 | 5,349,093 | 5,452,076 | 50,906 |
| 14-3 Lighting & small poert supply work | [lot] | 1 | 8,337,376 | 8,014,813 | 8,337,376 | 8,014,813 | 14,933,567 | 139,436 |
| Total | | | | | 18,143,015 | 212,549,014 | 193,070,853 | 1,802,716 |

Cost Breakdown for the Consulting Services

USD = JPY 107.1
LKR = JPY 0.823

| | Unit | Qty. | Foreign Portion | | Local Portion | | Combined Total (‘000) JPY |
|----------------------------------|-------|------|-----------------|------------------|---------------|------------------|---------------------------------|
| | | | (JPY) | | LKR | | |
| | | | Rate | Amount (‘000) | Rate | Amount (‘000) | |
| A Remuneration | | | | | | | |
| 1 Professional (A) | M/M | 40 | 2,895,000 | 115,800 | 0 | 0 | 115,800 |
| 2 Professional (B) | M/M | 0 | 0 | 0 | 0 | 0 | 0 |
| 3 Supporting Staffs | M/M | 24 | 0 | 0 | 118,000 | 2,832 | 2,331 |
| Subtotal of A | | | | 115,800 | | 2,832 | 118,131 |
| B Direct Cost | | | | | | | |
| 1 International Airfare | | 7 | 510,000 | 3,570 | | 0 | 3,570 |
| 2 Domestic Airfare | | 0 | | 0 | | 0 | 0 |
| 3 Domestic Travel | | 0 | | 0 | | 0 | 0 |
| 3 Accommodation Allowance (A) | Month | 40 | 600,000 | 24,000 | | 0 | 24,000 |
| Accommodation Allowance (B) | Month | 0 | | 0 | 100,000 | 0 | 0 |
| Accommodation Allowance (SS) | Month | 24 | | 0 | | 0 | 0 |
| 4 Vehicle Rental | Month | 40 | | 0 | 280,000 | 11,200 | 9,218 |
| 5 Office Rental | M/M | 0 | | 0 | | 0 | 0 |
| 6 International Communications | M/M | 40 | 10,000 | 400 | | 0 | 400 |
| 7 Domestic Communications | M/M | 40 | | 0 | 10,000 | 400 | 329 |
| 8 Office Supply | Set | 1 | | 0 | 100,000 | 100 | 82 |
| 9 Office Furniture and Equipment | M/M | 0 | | 0 | | 0 | 0 |
| 10 Report Preparation | Set | 1 | | | 20,000 | 20 | 16 |
| Subtotal of B | | | | 27,970 | | 11,720 | 37,616 |
| Total | | | | 143,770 | | 14,552 | 155,746 |

Annual Fund Requirement

Base Year for Cost Estimation:

Apr, 2015

FC & Total: million JPY

Exchange Rates

LKR = JPY 0.823

LC : million LKR

Price Escalation:

FC: 2.0% LC: 3.8%

Physical Contingency

5%

Physical Contingency for Consultant

5%

| Item | Total | | | 2015 | | | 2016 | | | 2017 | | | 2018 | | |
|--|---------------|--------------|---------------|-----------|-----------|-----------|----------|------------|------------|--------------|--------------|--------------|--------------|--------------|--------------|
| | FC | LC | Total | FC | LC | Total | FC | LC | Total | FC | LC | Total | FC | LC | Total |
| A. ELIGIBLE PORTION | | | | | | | | | | | | | | | |
| I) Procurement / Construction | 9,761 | 4,770 | 13,687 | 0 | 0 | 0 | 0 | 0 | 0 | 4,832 | 2,341 | 6,758 | 4,929 | 2,429 | 6,928 |
| Package 01: Construction of Transmission Line | 7,747 | 3,847 | 10,913 | 0 | 0 | 0 | 0 | 0 | 0 | 3,873 | 1,923 | 5,456 | 3,873 | 1,923 | 5,456 |
| Package 02: Construction of Switching Station | 1,100 | 291 | 1,339 | 0 | 0 | 0 | 0 | 0 | 0 | 550 | 145 | 670 | 550 | 145 | 670 |
| Base cost for JICA financing | 8,847 | 4,138 | 12,252 | 0 | 0 | 0 | 0 | 0 | 0 | 4,423 | 2,069 | 6,126 | 4,423 | 2,069 | 6,126 |
| Price escalation | 449 | 405 | 783 | 0 | 0 | 0 | 0 | 0 | 0 | 179 | 160 | 311 | 271 | 245 | 472 |
| Physical contingency | 465 | 227 | 652 | 0 | 0 | 0 | 0 | 0 | 0 | 230 | 111 | 322 | 235 | 116 | 330 |
| II) Consulting services | 159 | 17 | 173 | 0 | 0 | 0 | 0 | 0 | 0 | 75 | 8 | 81 | 84 | 9 | 91 |
| Base cost | 144 | 15 | 156 | 0 | 0 | 0 | 0 | 0 | 0 | 68 | 7 | 74 | 75 | 8 | 82 |
| Price escalation | 7 | 1 | 9 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 1 | 3 | 5 | 1 | 5 |
| Physical contingency | 8 | 1 | 8 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 4 | 4 | 0 | 4 |
| Total (I + II) | 9,920 | 4,787 | 13,859 | 0 | 0 | 0 | 0 | 0 | 0 | 4,907 | 2,348 | 6,839 | 5,013 | 2,438 | 7,020 |
| B. NON ELIGIBLE PORTION | | | | | | | | | | | | | | | |
| a Procurement / Construction | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Base cost for JICA financing | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Price escalation | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Physical contingency | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b Land Acquisition | 0 | 428 | 352 | 0 | 27 | 23 | 0 | 341 | 281 | 0 | 59 | 49 | 0 | 0 | 0 |
| Base cost | 0 | 391 | 322 | 0 | 26 | 21 | 0 | 313 | 258 | 0 | 52 | 43 | 0 | 0 | 0 |
| Price escalation | 0 | 16 | 13 | 0 | 0 | 0 | 0 | 12 | 10 | 0 | 4 | 3 | 0 | 0 | 0 |
| Physical contingency | 0 | 20 | 17 | 0 | 1 | 1 | 0 | 16 | 13 | 0 | 3 | 2 | 0 | 0 | 0 |
| c Administration cost | 0 | 863 | 711 | 0 | 1 | 1 | 0 | 17 | 14 | 0 | 418 | 344 | 0 | 426 | 351 |
| d VAT | 0 | 2,021 | 1,663 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 997 | 821 | 0 | 1,024 | 842 |
| e Import Tax | 0 | 844 | 694 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 417 | 343 | 0 | 426 | 351 |
| Total (a+b+c+d+e) | 0 | 4,155 | 3,420 | 0 | 29 | 24 | 0 | 358 | 295 | 0 | 1,892 | 1,557 | 0 | 1,876 | 1,544 |
| TOTAL (A+B) | 9,920 | 8,942 | 17,279 | 0 | 29 | 24 | 0 | 358 | 295 | 4,907 | 4,241 | 8,397 | 5,013 | 4,315 | 8,564 |
| C. Interest during Construction | 61 | 0 | 61 | 0 | 0 | 0 | 0 | 0 | 0 | 20 | 0 | 20 | 41 | 0 | 41 |
| Interest during Construction(Const.) | 61 | 0 | 61 | 0 | 0 | 0 | 0 | 0 | 0 | 20 | 0 | 20 | 41 | 0 | 41 |
| Interest during Construction (Consul.) | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| D. Front End Fee | 28 | 0 | 28 | 28 | 0 | 28 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| GRAND TOTAL (A+B+C+D) | 10,009 | 8,942 | 17,368 | 28 | 29 | 51 | 0 | 358 | 295 | 4,927 | 4,241 | 8,417 | 5,054 | 4,315 | 8,605 |
| E. JICA finance portion incl. IDC (A + C + D) | 10,009 | 4,787 | 13,948 | 28 | 0 | 28 | 0 | 0 | 0 | 4,927 | 2,348 | 6,860 | 5,054 | 2,438 | 7,061 |

Administration Cost = 5%
 VAT= 12% of the expenditure in local currency of the eligible portion
 Import Tax= 7%