

Chapter 3 Project Evaluation

3-1 Preconditions

The preconditions for project implementation are as follows;

(1) Conditions Related to Environment

- The land acquisition and resettlement are not expected for the bridge construction.

(2) Conditions Related to Construction

- MTRB completes the removal of the obstructions before the bidding.
- MTRB obtains the permission relating to the use of borrow pit and construction yard before the bidding.
- If the water of the Nile River is needed for the project, MTRB gets the permission of its use.

3-2 Necessary Inputs by Recipient Country

After project completion, road maintenance is necessary to prolong the life of the structure and the road. Maintenance work that includes daily or routine maintenance, removal of obstacles, cleaning, etc. Periodic inspection shall be carried out and if damage is observed to structures and pavements, essential repairs will be undertaken appropriately.

It is, therefore, necessary to secure an annual maintenance budget to maintain and repair the facilities (Bridges and Approach Roads; U.S.\$ 17,142/year). As noted in the earlier section, the allocation of operation and maintenance budget in South Sudan is considered possible.

3-3 Important Assumption

In order to express and prolong the effect of the project, the budget should be ensured the maintenance costs of the bridge and the approach road. It becomes the important assumption.

3-4 Project Evaluation

Based on the overall picture of the project, the Relevance and the Effectiveness of the project (quantitative effect and qualitative effect) are shown as follows ;

3-4-1 Relevance

Relevance of the Project is shown in Table 3-4-1.

Table 3-4-1 Relevance of the Project (Small Scale Bridges)

View Point	Relevance
Consistent with the development plan	<ul style="list-style-type: none"> • The national plan of post-independence " South Sudan Development Plan 2011-2013 " is now extended to 2016 and it is the pillar of the development. The plan focuses " Governance " , " Economic development " , " Social and human development " , and " Conflict prevention and security " as the four pillars of development. It is possible to develop the safe, efficient and sustainable road network of Juba city by this project. Thereby supporting the development of the RSS, the economic growth in the region of Juba city, domestic and international logistics, investment promotion , consolidation of

View Point	Relevance
	peace and even contribution to poverty reduction . The aforementioned corresponds to "Economic development" and "Social and human development" and "Conflict prevention and security" and therefore the project is consistent with the development plan.
Consistency of aid policy and policies	<ul style="list-style-type: none"> The basic policy of Japan's ODA to the RSS is shown as follows. These points follow the history of South Sudan gaining independence in July 2011 after experiencing 2 civil wars since 1955 and JICA supports nation building based on the South Sudan Development Plan. <ol style="list-style-type: none"> 1) Basic economic and social infrastructure upgrading, 2) Alternative industrial development , 3) Basic life and livelihood improvement , 4) Support in accordance with the governance and security capacity building, 5) Continued humanitarian assistance to internally displaced persons All 5 points are to provide assistance to support the consolidation of peace in the country. Therefore, this project is line with the policy of " Basic economic and social infrastructure upgrading. And there is a necessity and advantages of using Japanese bridge construction technologies. In addition, it is possible to implement the project under the system of Japan's Grant Aid.
Construction Techniques	<ul style="list-style-type: none"> The construction of the bridge with required quality is difficult for the local contractors in South Sudan due to lack of experience.

3-4-2 Effectiveness

3-4-2-1 Quantitative Effects

The design traffic volume is set for the predicted traffic after 10 years in service. The predicted traffic volume at each bridge is indicated in the Table 3-4 2.

The service starts at the time of the completion of the project (2020 year), The service of the 10 years later (2030 year) enables bridges to correspond to the increase of the predicted traffic.

In addition, the running speed improvement and the increase of passable vehicle weights contribute to the mitigation of the traffic congestion Juba city.

Table3-4-2 Effectiveness/Quantitative Effects

Bridge Number.	Actual Traffic Volume(pcu/day)*	Predicted Traffic Volume (pcu/day)**	Predicted Traffic Volume (pcu/day)***
	Current Situation	Start of Service	10 years after start of service
	2013	2020	2030
No.1	11,677	24,225	38,946
No.4	5,480	9,096	14,623
No.7	6,450	13,296	21,376
No.10	10,454	16,400	26,366
Average Speed(km/h)	10	50	50
Passable Vehicle Weight	10 ton (one bridge 20 ton)	25 ton	25 ton

*Actual Traffic Volume Counted on April 2013

**Predicted Traffic Volume calculated by JICA Strada

*** Predicted Traffic Volume calculated 6.5% as increasing ratio from 2020 and 3.25% from 2025

3-4-2-2 Qualitative Effects

Table 3-4-3 Effectiveness/Qualitative Effects

View Point	Effectiveness/Qualitative Effect
Urgency	<ul style="list-style-type: none"> • The slab floor of the bridge No.1 partly collapsed under the existing traffic load and it was repaired in 2011 by the GOSS. However, since the quality of the construction was poor, deterioration of concrete or the exposure of rebars were already found and there is a possibility to recurrent collapse very soon. Reconstruction of the bridges is able to avoid this risk at an earlier stage. • The structural strengths of other bridges have been greatly reduced due to ageing. All requested bridges become traffic bottlenecks due to narrower widths to approach roads. In addition, accidents such as vehicles falling off a bridge have occurred at the bottlenecked location. Reconstruction of the bridges is able to avoid this risk at an earlier stage.
Benefit	<ul style="list-style-type: none"> • Bridges No.1, 4, 7 and10 are located on the main roads of Juba city, has become a bottleneck of the traffic flow in the city center. Since the road of Juba city has been developed prior to the radiation road and the city center place, the city traffic suffers the congestion without dispersion of traffic flow. By widening the bridge width from a two-lane or single lane to a four-lane, improvement of traffic flow is anticipated contributing to mitigation of traffic congestion in Juba city. • Bridges promote the ring road network development and also contribute to reduce the exhaust gas and noise and to improve the environment. • In the 2008 census, the population of Juba city was 400 thousand people. The population growth expected by the South Sudan National Bureau of Statistics assumes that it may be about 50 million people in2015. The entire population is able to be benefited. • The cargo is transported to various places through the Juba city where is located in the node of the international corridor and the major domestic trunk lines. The mitigation of the congestion in Juba city will serve benefits not only to Juba city traffic flow but also for facilitation of international and domestic logistics. • The traffic to Juba city from neighboring community residents is promoted after the bridge reconstruction. • This project is intended to continue to the city development following the development of 6 bridges under the peace-building program and the Nile bridges construction under the Japan's Grant Aid. Implementation of this project will contribute to the trust -building between the two countries.

Appendix

- | | |
|------------|---|
| Appendix 1 | Member List of the Study Team |
| Appendix 2 | Study Schedule |
| Appendix 3 | List of Parties Concerned
in the Recipient Country |
| Appendix 4 | Minutes of Discussion |
| Appendix 5 | List of Documents |
| Appendix 6 | Preparatory Design Drawings |

Appendix 1 Member List of Study Team

1. Member List of Study Team

Outline Survey (O/D)

Name	Position	Organization
Mr. ISHIGURO Jitsuya	Team Leader	Acting Director Team 1, Transportation and ICT Group Infrastructure and Peacebuilding Department Japan International Cooperation Agency
Mr. SAKABE Hidetaka	Team Leader (Third Field Survey)	Deputy Director Team 1, Transportation and ICT Group Infrastructure and Peacebuilding Department Japan International Cooperation Agency
Mr. MIZOTA Yuzo	Chief Engineer / Highway Planner	CTI Engineering International Co., Ltd.
Mr. WATANABE Masatoshi	Bridge Designer	CTI Engineering International Co., Ltd
Mr. HEIMA Hiroyuki	Construction Planner / Cost Estimator	CTI Engineering International Co., Ltd

Appendix 2 Study Schedule

2. Study Schedule

Study Schedule

Date	Team Leader	Chief Engineer/Highway Planner	Asst. Chief Engineer/ Bridge Planner/ Bridge Designer I	Highway Designer	Bridge Designer II	Hydrologist	Social-Environmental	Construction Planner/ Cost Estimator	Project Coordinator	
No	Date	Jitsuya ISHIGURO	Yuzo MIZOTA	Takashi NAKAJIMA	Ryohai WATANABE	Koshiro YASUOKA	Shuichi MORI	Mitsue UMIGUCHI	Hiroimitsu OGATA	Masatoshi WATANABE
1	15 Fri	Tokyo(TG677 Dep 17h30)→	Tokyo(TG677 Dep 17h30)→	Tokyo(TG677 Dep 17h30)→		Tokyo(TG677 Dep 17h30)→	Tokyo(TG677 Dep 17h30)→BKK(22h20)		Study	
2	16 Sat	BKK(KQ877 00h40)→	Nairobi(09h10), Nairobi	BKK(KQ877 00h40)→		BKK(KQ877 00h40)→Nairobi(09h10), Nairobi(KQ350.07h45)→Juba(09h20)	BKK(KQ877 00h40)→Nairobi(09h10), Nairobi(KQ350.07h45)→Juba(09h20)		Study	
3	17 Sun		study preparation	study preparation		Site visit (No18.19, Lologo)	Census		Study	
4	18 Mon		Catey Call JICA SS, MOPI, MRB	Catey Call JICA SS, MOPI, MRB		MOPI	Census		Study	
5	19 Tue		Discussion	Discussion		Study	Study		Study	
6	20 Wed	Tokyo(TG677 Dep17.30)→	Site visit	Site visit		Study	Study		Study	
7	21 Thu	⇒Juba(KQ350 Arr9.20)	MRB Minister	MRB Minister		Study	Study		Study	
8	22 Fri	MRB-MoPI Discussion	MOPI Minister	MOPI Minister		Study	Study		Study	
9	23 Sat	Site visit	Site visit	Site visit		Study	Study		Study	
10	24 Sun	Site visit	Site visit	Site visit		Study	Study		Study	
11	25 Mon	MM Discussion	MM Discussion	MM Discussion		Study	Study		Study	
12	26 Tue	MM signing	MM signing	MM signing		Study	Study		Study	
13	27 Wed	Juba(KQ353 Dep15.15)	Site visit	Site visit		Study	Study		Study	
14	28 Thu	⇒Tokyo(TG660 Arr22.30)	1st Stakeholder Meeting	1st Stakeholder Meeting		Study	Study		Study	
15	29 Fri		Site visit Juba Yei Road	Site visit Juba Yei Road		Site visit Juba Yei Road	Study		Study	Juba (KQ353.15h25)→
16	30 Sat		Site visit Juba Yei Road	Site visit Juba Yei Road		Site visit Juba Yei Road	Study		Study	Nairobi(7h10)→BKK(13h15,KQ886), BKK(22h10,TG640)→
17	31 Sun		Site visit Juba Yei Road	Site visit Juba Yei Road		Site visit Juba Yei Road	Study		Study	→Narita (06h20)
18	1 Mon		Juba(KQ353.15h25)→	Preparation		Juba(KQ353.15h25)→Nairobi(17h10), Nairobi(KQ886.13h15)→	Study			
19	2 Tue		→BKK(13h15,KQ886), BKK(22h10,TG640)→	Study on Bridge design		→BKK(13h15,KQ886), BKK(22h10,TG640)→	Study			
20	3 Wed		→Narita (06h20)	Study on Road design		→Narita (06h20)	Study			
21	4 Thu			Discussion with SHs	Tokyo(IL5095 Dep 22.00)⇒		Study			
22	5 Fri			2nd Stakeholder Meeting	⇒Nairobi(EK719 Arr 14.45)		Study			
23	6 Sat			Study	⇒Juba(KQ352 Arr 14.35)		Study			
24	7 Sun			Study			Study			
25	8 Mon			Report to JICA	JICA office		Reporting			
26	9 Tue			Discussion with SHs	Discussion with SHs		Reporting			
27	10 Wed			Site visit	Site survey		Reporting			
28	11 Thu			Juba(KQ353.15h25)→	Site survey		Juba(KQ353.15h25)→Nairobi(17h10), Nairobi(KQ886.13h15)→			
29	12 Fri			→BKK(13h15,KQ886), BKK(22h10,TG640)→	Site survey		→BKK(13h15,KQ886), BKK(22h10,TG640)→			
30	13 Sat			→Narita (06h20)	Site survey		→Narita (07h00)			
31	14 Sun				Site survey					
32	15 Mon				Site survey					
33	16 Tue				Site survey					
34	17 Wed				Site survey					
35	18 Thu				Site survey					
36	19 Fri				Site survey					
37	20 Sat				Site survey					
38	21 Sun				Site survey					
39	22 Mon				Site survey					
40	23 Tue				Site survey					
41	24 Wed				Site survey					
42	25 Thu				Site survey					
43	26 Fri				Site survey					
44	27 Sat				Site survey					
45	28 Sun				Reporting					
46	29 Mon				Reporting					
47	30 Tue				Reporting					
48	1 Wed				Reporting	Orake(IL5099.23h40)→				
49	2 Thu				Juba⇒Narita(KQ351 Arr 13.00)⇒	Dubai(05h10)				
50	3 Fri				Dubai(EK720 Arr 22.40)	Dubai(EK719.10h45)→				
51	4 Sat				Dubai⇒Narita(IL5096 Arr 17.35)	Nairobi(KQ352.13h30)→Juba(14h35)				
52	5 Sun					Site survey				
53	6 Mon					Site survey				
54	7 Tue					Site survey				
55	8 Wed					Site survey				

Study Schedule

Date		Team Leader	Chief Engineer/Highway Planner	Asst. Chief Engineer/ Bridge Planner/ Bridge Designer I	Highway Designer	Bridge Designer II	Hydrologist	Social-Environmentalist	Construction Planner/ Cost Estimator	Project Coordinator
No.	Date	Jitsuya ISHIGURO	Yuzo MIZOTA	Takashi NAKAJIMA	Ryobei WATANABE	Koshito YASUOKA	Shuichi MORI	Mitsue UMIGUCHI	Hiromitu OGATA	Masatoshi WATANABE
56	9 Thu					Site survey				
57	10 Fri					Site survey				
58	11 Sat					Site survey				
59	12 Sun					Site survey				
60	13 Mon					Site survey				
61	14 Tue					Site survey				
62	15 Wed					Site survey				
63	16 Thu					Site survey				
64	17 Fri					Site survey				
65	18 Sat					Site survey				
66	19 Sun					Site survey				
67	20 Mon					Site survey				
68	21 Tue					Site survey				
69	22 Wed					Site survey				
70	23 Thu					Site survey				
71	24 Fri					Site survey				
72	25 Sat					Site survey				
73	26 Sun					Site survey				
74	27 Mon					Site survey				
75	28 Tue					Site survey				
76	29 Wed					Juba (KQ351,10h15)→ Nairobi(12h00)				
77	30 Thu					Dubai(JL5090,03h00)→ Osaka(17h10)				
78	31 Fri									
79	1 Sat								Tokyo(JL5095 Dep 22:00)⇒	
80	2 Sun								⇒Nairobi(EK719 Arr 14:45)	
81	3 Mon								⇒Juba(KQ352 Arr 14:35)	
82	4 Tue								Study	
83	5 Wed								Study	
84	6 Thu								Study	
85	7 Fri								Study	
86	8 Sat								Study	
87	9 Sun								Study	
88	10 Mon								Study	
89	11 Tue			Study				Osaka(JL5099 23:40)→Dubai	Study	
90	12 Wed			Study				Dubai(EK719 10:45)→Nairobi	Study	
91	13 Thu			Study				Nairobi(KQ352 12:50)→Juba	Study	
92	14 Fri			Study				Census and reporting	Study	
93	15 Sat			Study				Census and reporting	Study	
94	16 Sun			Study				Census and reporting	Study	
95	17 Mon			Study				Census and reporting	Study	
96	18 Tue			Study				Census and reporting	Study	
97	19 Wed			Study				Census and reporting	Study	
98	20 Thu			Study				Census and reporting	Study	
99	21 Fri			Study				Census and reporting	Study	
100	22 Sat			Study				Census and reporting	Study	
101	23 Sun			Study				Census and reporting	Study	
102	24 Mon			Study				Census and reporting	Study	
103	25 Tue			Study				Census and reporting	Study	
104	26 Wed			Study				Census and reporting	Study	
105	27 Thu			3rd Stakeholders Meeting				Census and reporting	Study	
106	28 Fri			Reporting				Census and reporting	Study	
107	29 Sat			Juba⇒Nairobi(KQ351 Arr 12:00)⇒ Dubai(EK720 Arr 22:40)				Juba⇒Nairobi(KQ351 Arr 12:00)⇒ Dubai(EK720 Arr 22:40)	Juba⇒Nairobi(KQ351 Arr 12:00)⇒ Dubai(EK720 Arr 22:40)	
108	30 Sun			Dubai⇒Nairobi(EK318 Arr 17:35)				Dubai⇒Nairobi(EK318 Arr 17:35)	Dubai⇒Nairobi(EK318 Arr 17:35)	

Juba
Trip

			Chief Engineer/Road Planner	Construction & Procurement Planer/ Cost Estimator Project Coordinator
			Mr. MIZOTA Yuzo	Mr. HEIMA Hiroyuki
1	9/16	Wed		Departure from Haneda Arrival at Nairobi
2	9/17	Thu		Departure from Nairobi Arrival at Juba Meeting with JICA
3	9/18	Fri		Meeting with supporting members and check of schedule and preparation
4	9/19	Sat		Road/bridge condition survey of six bridges
5	9/20	Sun		Internal work for preparation of survey drawing for Obstruction location
6	9/21	Mon		Topographic survey for six bridges to check Obstructions(No.1&No.4
7	9/22	Tue		Topographic survey for six bridges to check Obstructions(No.7&No.10
8	9/23	Wed	Departure from Narita	Topographic survey for six bridges to check Obstructions(No.18&No.19
9	9/24	Thu	Arrival at Nairobi Departure from Nairobi	Internal work for preparation of drawing of Obstruction location as result
10	9/25	Fri	Departure from Nairobi Arrival at Juba Road/bridge condition survey of six bridges	Road/bridge condition survey of six bridges Internal Meeting for Result of Obstruction Situation
11	9/26	Sat	Road/bridge condition survey of six bridges	Preparation of Report for Obstructions Rain water discharge condition check in each bridge
12	9/27	Sun	Internal meeting on grant aid project	Preparation of Report for Obstructions
13	9/28	Mon	Meeting with MOPI and Site visit Meeting with JICA South Sudan Office	Meeting with MOPI and Site visit Meeting with JICA South Sudan Office
14	9/29	Tue	Meeting with Juba Mayor Road/bridge condition survey of six bridges	Preparation for BM and Reference points in No.1&4 bridges Road/bridge condition survey of six bridges
15	9/30	Wed	Road/bridge condition survey of six bridges	Preparation for BM and Reference points in No.7&10 bridges
16	10/1	Thu	Meeting with EOJ Meeting with MTRB	Meeting with EOJ Meeting with MTRB Preparation for BM and Reference points in No.18&19 bridges
17	10/2	Fri	Meeting with EOJ Meeting with JICA Departure from Juba	Meeting with EOJ Meeting with JICA Explanation of Obstruction Area to MOPI in the site
18	10/3	Sat		Road/Bridge condition survey of six bridges Confirmation of all obstruction areas that Surveyor marked before
19	10/4	Sun		Internal work for preparation of Survey Report
20	10/5	Mon		Meeting with MTRB Explanation of Obstruction Area to MOPI in the site Departure from Juba
21	10/6	Tue		Arrival at Haneda

			Chief Engineer/Road Planner	Construction & Procurement Planer/ Cost Estimator Project Coordinator
			Mr. MIZOTA Yuzo	Mr. HEIMA Hirovuki
1	10/13	Tue		Departure from Haneda Arrival at Nairobi
2	10/14	Wed		Stay at Nairobi
3	10/15	Thu		Departure from Nairobi Arrival at Juba
4	10/16	Fri		Meeting with Mr.Otim/Director of MTRM to inform the purpose of our study. Meeting with Local contractor to request the cost estimations and hearing some information.
5	10/17	Sat		Site Survey for the Construction Area of Bridge No.7 and found its much difference from the drawing of its location in actual and ask to the head quarter of Japan about drawing data.
6	10/18	Sun		Internal work for preparation of cost estimation company to have meetings with them.
7	10/19	Mon		Site investigation for the rock line to check the possibility of the Footing Level at No.4 Bridge.
8	10/20	Tue		Meeting with Local contractors to request the cost estimations and hearing some information.
9	10/21	Wed		Site Survey for the Construction Area of Bridge No.4 for outline of the construction area.
10	10/22	Thu		Meeting with Local contractors to request the cost estimations and hearing about some information.
11	10/23	Fri		Topographic Survey of Right of Way along the Hotel side to clear its boundry with the Approach Road of No.7 Bridge. Received document of copy of approval for Car Basement Construction with stamps of MOPI from Anseba Hotel.
12	10/24	Sat		Meeting with the Engineer of Consultant for Hotel Construction to check their approval document to make cler the problem and site check with this document
13	10/25	Sun		Preparation of Report for the Hotel Construction Area Occupation in the Right of Way of Approach Road of Bridge No.7
14	10/26	Mon		Meeting with JICA South Sudan Office for Occupation of Right of Way of No.7 Bridge Construction by New Hotel Construction Area. Preparation for Concrete Stakes of Right of Way along the Hotel side to clear its boundry (No.7 Bridge).
15	10/27	Tue		Meeting among MTRB, MOPI, Anseba Hotel and CTII at Site of No.7 Bridge to investigate the Right of Way and discussion among them to decide the solution Preparation for BM and Reference points in the Bridge No.7.
16	10/28	Wed		Preparation for the Agreement of Right of Way to remove the Hotel Construction Area outside of the Right of Way. Preparation for BM and Reference points in the Bridge No.7.
17	10/29	Thu		Agreement signs among MTRB, MOPI and Anseba Hotel Reprntative for Removal of the Hotel Construction Area from the Ridht of Way of the Bridge No.7.
18	10/30	Fri		Meeting with JICA of South Sudan to explain the Solution of above solution. Preparation for BM and Reference points in each Bridges No.10.
19	10/31	Sat		Preparation for BM and Reference points in each Bridges No.10.
20	11/1	Sun		Internal work for preparation of Technical Notes
21	11/2	Mon		Preparation for Final Obstruction Drawing. No.7 Bridge/ Arrange the design for Hotel Entrance Level& Location Preparation for BM and Reference points in each Bridges No.4.
22	11/3	Tue		Meeting with MOPI to confirm the Construction Yard and final Obstruction Area Preparation for BM and Reference points for Right of Way in Bridges No.4.
23	11/4	Wed		Meeting with MTRB on Technical Notes to sign by Mr.Gabriel Makur, Undersecretary and Mr.Otim Bong, Acting Director Meeting with MOPI on Technical Notes to sign By Mr. John Bullen, Director General Preparation for BM and Reference points in each Bridges No.1.
24	11/5	Thu		Meeting with Mr.Kondo of Consultant TEC International on the Project for the Improvement of Water Sply System of Juba in South Suda to explain him the bridge construction area and to avoid the future problem. Preparation for BM and Reference points in each Bridges No.1.
25	11/6	Fri		Site Vist with MOPI to show them final Obstructions to be removed and Concreate stakes with rebar/nail to indicate the Right of Way to reserve these area
26	11/7	Sat		Internal work for preparation of Survey Report
27	11/8	Sun		Internal work for preparation of Survey Report
28	11/9	Mon		Meeting with Jica to report the work result of Study Team
29	11/10	Tue		Departure from Juba to Nairobi and Nairobi to Dubai
30	11/11	Wed		From Dubai to Narita

			総括 Team Leader 坂部 英孝 Mr. SAKABE Hidetaka	業務主任/交通計画 Chief Consultant/ Highway Planner 溝田 祐造 Mr. MIZOTA Yuzo
1	3/12	Sat		22:00 Departure from Tokyo (EK319)
2	3/13	Sun		05:00 Arrival at Dubai (EK319) 10:35 Departure from Dubai (EK719) 14:45 Arrival at Nairobi (EK719)
3	3/14	Mon	19:45 Departure from Tokyo (ET673) 07:20 Arrival at Addis Ababa (ET673) 9:27 Departure from Addis Ababa (ET356) 11:27 Arrival at Juba (ET356)	08:35 Departure from Nairobi (KQ350) 10:20 Arrival at Juba (KQ350) 16:00 Meeting with JICA Office
4	3/15	Tue		9:00 to 11:00 Explanation of the summary of draft final report and M/D to MTRB 14:00 to 17:00 Site reconnaissance of project bridges
5	3/16	Wed		9:00 Explanation of the summary of draft final report to MTRB 15:00 to 17:00 Discussion and signing of MD with MTRB 17:00 to 18:00 Courtesy call to Japanese Embassy
				11:00 to 12:00 Explanation of the results of MD to JICA Office
			16:10 Departure from Juba(ET357) 18:10 Arrival at Addis Ababa (ET357) 22:20 Departure from Addis Ababa (ET672)	15:00 to 17:00 Site visit to confirm the bench mark at Bridge No.7
7	3/18	Fri	18:45 Arrival at Tokyo (ET672)	10:00 to 12:00 Explanation of draft final report to MTRB 13:00 to 17:00 Site visit to confirm the drawings and obstructions with MOPI
8	3/19	Sat		Site visit to confirm the drawings with MOPI
9	3/20	Sun		Site survey to adopt ramp type footpath instead of steps
10	3/21	Mon		11:00 to 12:00 Meeting with South Sudan Roads Authority 14:00 to 15:00 Site visit to confirm drawings with MOPI
11	3/22	Tue		10:00 to 12:00 Explanation of drawings to MTRB 14:30 to 15:30 Meeting with Bank of South Sudan
12	3/23	Wed		8:00 to 12:00 Site survey to adopt ramp type footpath 14:00 to 17:00 Site visit to confirm drawings
		Thu		10:00 to 12:00 Explanation of drawings to MTRB and MOPI 15:00 to 16:00 Meeting with JICA office
14	3/25	Fri		11:10 Departure from Juba 12:50 Arrival at Nairobi (KQ351) 16:40 Departure from Nairobi 22:40 Arrival at Dubai (EK720)
15	3/26	Sat		02:55 Departure from Dubai (EK318) 17:20 Arrival at Tokyo (EK318)

Appendix 3 List of Parties Concerned
in the Recipient Country

3. List of Parties Concerned in the Recipient Country

I Government of South Sudan	
Ministry of Transport, Roads and Bridges	
Mr. Kuong Danhier Gatluak Mr. Simon Mijok Mijak Mr. Gabriel Makur Amour Mr. Jermiah Turic Bairiak Mr. Otim Bong Mike Mr. Duku George Mr. Philip Thon Mr. Aduot Madil	Minister Deputy Minister Undersecretary Director General Acting Director of Transport, Roads and Bridges Acting Director for Bridges (Department for Roads and Bridges) Senior Inspector for Roads (Department for Roads and Bridges) Road Engineer (project management team)
II Government of Central Equatoria State	
Ministry of Physical Infrastructure	
Mr. John Bullen Mr. Emmanuel Wani Matayo Mr. Roman Marghani Lukak Mr. Dominic Pitia Mr. Peter Laku Loro Mr. Anthony Peter	Director General, MOPI Former Director General, MOPI Director of Roads and Bridges Juba, MOPI Acting Director General for MOPI Acting Director for Roads and Bridges Divisional Engineer and Acting Director of Housing
III South Sudan Road Authority	
Mr. Kenyatta Warille Mr. Edwin Rokani Ikudri Mr. John Deng Diar	Executive Director Director for Maintenance Director for Projects
IV Bank of South Sudan	
Mr. Albino Dak Othow	Director General for Currency and Banking Operation
V Embassy of Japan	
Masahiko KIYA Yasuo MATSUNAMI	Ambassador Extraordinary and Plenipotentiary First Secretary
VI JICA South Sudan Office	
Mitsuaki FURUKAWA Masayoshi KAWAI	Representative Project Officer

Appendix 4 Minutes of Discussion (M/D)

Appendix 4-1 Minutes of Discussion (M/D) March 2013

Appendix 4-2 Technical Notes June 2013

Appendix 4-3 EIA License October 2013

Appendix 4-4 Technical Notes October 2015

Appendix 4-5 Technical Notes November 2015

Appendix 4-6 Minutes of Discussion March 2016

Appendix 4-7 Technical Notes March 2016

4. Minutes of Discussions (M/D)

4-1 Minutes of Discussions (M/D) March 2013.....	A-4-1
1. Object of the Project.....	A-4-2
2. Project Sites.....	A-4-2
3. Responsible and Implementing Organizations.....	A-4-2
4. Items requested by the Government of South Sudan.....	A-4-2
5. Japan’s Grant Aid Scheme.....	A-4-2
6. Environmental and Social Considerations.....	A-4-2
7. Schedule of the Study.....	A-4-3
8. Other Relevant Issues.....	A-4-3
4-2 Technical Notes June 2013.....	A-4-13
1. Plan and Design.....	A-4-15
2. Construction Plan.....	A-4-18
3. Environmental and Social Consideration.....	A-4-19
4. Underground Utilities.....	A-4-19
5. Undertakings by Republic of South Sudan.....	A-4-20
4-3 EIA License October 2013.....	A-4-31
4-4 Technical Notes October 2015.....	A-4-32
1. Priority of Bridges.....	A-4-34
2. Bridge Designs.....	A-4-34
3. Undertakings by Republic of South Sudan.....	A-4-34
4. Annex-1 Drawings for Removal of the Obstructions.....	A-4-36
4-5 Technical Note November 2015.....	A-4-43
1. Priority of Bridges.....	A-4-45
2. Road Design.....	A-4-45
3. Bridge Designs.....	A-4-45
4. Undertakings by Republic of South Sudan.....	A-4-46
Annex-1 Road Drainage Design Change.....	A-4-48
Annex-2 Drawings for Removal of the Obstructions.....	A-4-50
Annex-3 Construction Condition of Anseba Hotel.....	A-4-55
Annex-4 Guarantee Area for New Bridge Construction.....	A-4-59
Annex-5 Construction Yard, Borrow Pit Area and Jebel Disposal Area.....	A-4-64
4-6 Minutes of Discussion (M/O) March 2016.....	A-4-66
4-7 Technical Note November 2015.....	A-4-93


**MINUTES OF DISCUSSIONS
ON THE PREPARATORY SURVEY (OUTLINE DESIGN STUDY)
ON THE PROJECT FOR CONSTRUCTION LOLOGO BYPASS AND BRIDGES
IN JUBA CITY IN THE REPUBLIC OF SOUTH SUDAN**

In response to a request from the Government of the Republic of South Sudan (hereinafter referred to as "RSS"), the Government of Japan decided to conduct a Preparatory Survey for Outline Design (hereinafter referred to as "the Survey") on the Project for Construction of the Lologo Bypass and Bridges in Juba City (hereinafter referred to as "the Project"), and entrusted the study to Japan International Cooperation Agency (hereinafter referred to as "JICA").


JICA sent the Preparatory Survey Team for Outline Design (hereinafter referred to as "the Team") to South Sudan. The Team is headed by Mr. Jitsuya Ishiguro, Advisor, Transportation and ICT Division 2, Economic Infrastructure Department, JICA and is scheduled to stay in the country from 21 to 27 March 2013.

The Team held a series of discussions with the officials of the Government of RSS and conducted a field survey at the Project area. In the course of the discussions, both sides have confirmed the main items described in the attached sheets. The Team will proceed to further works and prepare the Preparatory Survey Report.


Juba, 26 March 2013




Jitsuya Ishiguro
Leader
Preparatory Survey Team
Japan International Cooperation Agency



Eng. Jeremiah Turic Bairiak
Director General
Ministry of Roads and Bridges

Witness:  26/03/13
Otim Bong
Acting Director for Roads and Bridges
Ministry of Roads and Bridges



Emmanuel Wani Matayo
First Director General
Ministry of Physical Infrastructure
Central Equatoria State

ATTACHMENT

1. Objective of the Project

The objective of the Project is to mitigate congestions and facilitate urban passenger and goods transportation in Juba, thereby contributing to economic and social development of South Sudan.

2. Project Sites

The Project sites are in Juba as shown in Annex-1.

3. Responsible and Implementing Organizations

The responsible agency of the Project is the Ministry of Roads and Bridges (hereinafter referred to as "MRB"). The implementing agency of the Project is the Ministry of Physical Infrastructure, the Government of Central Equatoria State (hereinafter referred to as "MOPI"). The organization charts are shown in Annex 2.

4. Items requested by the Government of South Sudan

4-1. As a result of discussions, the requested components were confirmed as follows.

- (1) Construction of Lologo bypass
- (2) Construction of bridges and/or culverts in Juba city

4-2. JICA will assess the appropriateness of the request through the Survey and will report the findings to the Government of Japan. Implementation of the Project will be decided by the Government of Japan.

5. Japan's Grant Aid Scheme

5-1. The South Sudan side has shown a full understanding to the Japan's Grant Aid Scheme explained by the Team, as described in Annex 4 and 5.

5-2. The South Sudan side will take the necessary measures, as described in Annex-6, for smooth implementation of the Project.

6. Environmental and Social Considerations

6-1. The Team explained that during the course of the Survey information on environmental and social considerations including major impacts and relevant mitigation measures will be summarized in the Environmental Checklist attached as Attachment

6-2. Both sides confirmed that JICA will help MRB and MOPI conduct necessary procedures concerning the environmental assessment (including stakeholder

meetings, EIA, RAP etc.) and MRB and MOPI will take necessary actions to obtain official approval from the responsible authorities.

6-3. The South Sudan side agreed to arrange the budget allocation for land acquisition, resettlement and compensation for the Project Affected Persons (PAPs) and to take necessary measures for PAPs and secure the land.

7. Schedule of the Study

7-1. The Team will proceed with further studies in South Sudan until June 2013.

7-2. JICA will prepare a draft final report in English and dispatch a mission to South Sudan in order to explain its contents around December 2013.

7-3. When the contents of the report is accepted in principle by the Government of South Sudan, JICA will complete the final report in English and send it to the Government of South Sudan around February 2014.




8. Other Relevant Issues

8-1. The South Sudan side confirmed that the following undertakings should be taken by the South Sudan side at the South Sudan expenses under the Project.

- (1) To provide tax exemption for construction materials and equipment for the Project
- (2) To provide land necessary for the Project including detour, camp yard and temporary construction yard
- (3) To remove existing obstacles
- (4) To arrange necessary traffic control at necessary sections
- (5) To secure site for borrow pit and disposal area

8-2. The South Sudan side shall secure enough budget and personnel necessary for the operation and maintenance of the road and bridges constructed by the Project, including the routine and periodical maintenance work after the completion of the Project.


- Annex-1 Project Site
- Annex-2 Organization Chart of MRB
- Annex-3 Organization Chart of MOPI
- Annex-4 Japan's Grant Aid
- Annex-5 Flow Chart of Japan's Grant Aid Procedures
- Annex-6 Major Undertakings to be taken by Each Government




Legend

- : International Road
- : Existing Road (un-paved)
- : Existing Road (paved)
- : Plan Road
- : Project Bridge (bridge structure)
- : Lologo Bypass (Project Road)
- C1~C3 : Circumferential Road
- R1~R6 : Radial Road

Location Map





MoPI (Directorate of Roads and Bridges) Organization Structure (Draft)

A-4-6

Annex-3

JAPAN'S GRANT AID

The Government of Japan (hereinafter referred to as “the GOJ”) is implementing the organizational reforms to improve the quality of ODA operations, and as a part of this realignment, a new JICA law was entered into effect on October 1, 2008. Based on this law and the decision of the GOJ, JICA has become the executing agency of the Grant Aid for General Projects, for Fisheries and for Cultural Cooperation, etc.

The Grant Aid is non-reimbursable fund provided to a recipient country to procure the facilities, equipment and services (engineering services and transportation of the products, etc.) for its economic and social development in accordance with the relevant laws and regulations of Japan. The Grant Aid is not supplied through the donation of materials as such.

1. Grant Aid Procedures

The Japanese Grant Aid is supplied through following procedures :

- Preparatory Survey
 - The Survey conducted by JICA
- Appraisal & Approval
 - Appraisal by the GOJ and JICA, and Approval by the Japanese Cabinet
- Authority for Determining Implementation
 - The Notes exchanged between the GOJ and a recipient country
- Grant Agreement (hereinafter referred to as “the G/A”)
 - Agreement concluded between JICA and a recipient country
- Implementation
 - Implementation of the Project on the basis of the G/A

2. Preparatory Survey

(1) Contents of the Survey

The aim of the preparatory Survey is to provide a basic document necessary for the appraisal of the Project made by the GOJ and JICA. The contents of the Survey are as follows:

- Confirmation of the background, objectives, and benefits of the Project and also institutional capacity of relevant agencies of the recipient country necessary for the implementation of the Project.
- Evaluation of the appropriateness of the Project to be implemented under the Grant Aid Scheme from a technical, financial, social and economic point of view.
- Confirmation of items agreed between both parties concerning the basic concept of the Project.
- Preparation of a outline design of the Project.
- Estimation of costs of the Project.

The contents of the original request by the recipient country are not necessarily approved in their initial form as the contents of the Grant Aid project. The Outline Design of the Project is confirmed based on the guidelines of the Japan's Grant Aid scheme.

JICA requests the Government of the recipient country to take whatever measures necessary to achieve its self-reliance in the implementation of the Project. Such measures must be guaranteed even though they may fall outside of the jurisdiction of the organization of the recipient country which actually implements the Project. Therefore, the implementation of the Project is confirmed by all relevant organizations of the recipient country based on the Minutes of Discussions.

(2) Selection of Consultants

For smooth implementation of the Survey, JICA employs (a) registered consulting firm(s). JICA selects (a) firm(s) based on proposals submitted by interested firms.

(3) Result of the Survey

JICA reviews the Report on the results of the Survey and recommends the GOJ to appraise the implementation of the Project after confirming the appropriateness of the Project.

3. Japan's Grant Aid Scheme

(1) The E/N and the G/A

After the Project is approved by the Cabinet of Japan, the Exchange of Notes(hereinafter referred to as "the E/N") will be signed between the GOJ and the Government of the recipient country to make a pledge for assistance, which is followed by the conclusion of the G/A between JICA and the Government of the recipient country to define the necessary articles to implement the Project, such as payment conditions, responsibilities of the Government of the recipient country, and procurement conditions.

(2) Selection of Consultants

In order to maintain technical consistency, the consulting firm(s) which conducted the Survey will be recommended by JICA to the recipient country to continue to work on the Project's implementation after the E/N and G/A.

(3) Eligible source country

Under the Japanese Grant Aid, in principle, Japanese products and services including transport or those of the recipient country are to be purchased. When JICA and the Government of the recipient country or its designated authority deem it necessary, the Grant Aid may be used for the purchase of the products or services of a third country. However, the prime contractors, namely, constructing and procurement firms, and the prime consulting firm are limited to "Japanese nationals".

(4) Necessity of "Verification"

The Government of the recipient country or its designated authority will conclude contracts denominated in Japanese yen with Japanese nationals. Those contracts shall be verified by JICA. This "Verification" is deemed necessary to fulfill accountability to Japanese taxpayers.

(5) Major undertakings to be taken by the Government of the Recipient Country

In the implementation of the Grant Aid Project, the recipient country is required to undertake such necessary measures as Annex.

(6) "Proper Use"

The Government of the recipient country is required to maintain and use properly and effectively the facilities constructed and the equipment purchased under the Grant Aid, to assign staff necessary for this operation and maintenance and to bear all the expenses other than those covered by the Grant Aid.

(7) "Export and Re-export"

The products purchased under the Grant Aid should not be exported or re-exported from the recipient country.

(8) Banking Arrangements (B/A)

- a) The Government of the recipient country or its designated authority should open an account under the name of the Government of the recipient country in a bank in Japan (hereinafter referred to as "the Bank"). JICA will execute the Grant Aid by making payments in Japanese yen to cover the obligations incurred by the Government of the recipient country or its designated authority under the Verified Contracts.
- b) The payments will be made when payment requests are presented by the Bank to JICA under an Authorization to Pay (A/P) issued by the Government of the recipient country or its designated authority.


(9) Authorization to Pay (A/P)

The Government of the recipient country should bear an advising commission of an Authorization to Pay and payment commissions paid to the Bank.

(10) Social and Environmental Considerations

A recipient country must carefully consider social and environmental impacts by the Project and must comply with the environmental regulations of the recipient country and JICA guidelines for environmental and social considerations.

FLOW CHART OF JAPAN'S GRANT AID PROCEDURES



Major Tasks to be Undertaken by Each Government










No.	Items	To be covered by Grant Aid	To be covered by the Recipient Side
1	To secure land		●
2	To clear, level and reclaim the site when needed		●
3	To construct gates and fences in and around the site		●
4	To bear the following commissions to the Japanese bank for banking services based upon the B/A		
	1) Advising commission of A/P		●
	2) Payment commission		●
5	To ensure unloading and customs clearance at port of disembarkation in recipient country		
	1) Marine/Air/Land transportation of the products from Japan to the recipient country	●	
	2) Tax exemption and customs clearance of the products at the port of disembarkation		●
	3) Internal transportation from the port of disembarkation to the project site	●	
6	To accord Japanese nationals, whose service may be required in connection with the supply of the products and the services under the Verified Contract, such facilities as may be necessary for their entry into the recipient country and stay therein for the performance of their work		●
7	To exempt Japanese nationals from customs duties, internal taxes and other fiscal levies which may be imposed in the recipient country with respect to the supply of the products and services under the Verified Contracts		●
8	To maintain and use properly and effectively the facilities contracted and equipment provided under the Grant Aid		●
9	To bear all the expenses, other than those to be borne by the Grant Aid, necessary for construction of the facilities as well as for the transportation and installation of the equipment		●

(B/A : Banking Arrangement, A/P : Authorization to Pay)

Attendant List

Subject: M/M Signing Meeting

Date: 26 March 2013

No	Name	Organization	Contact	Signature
1	EMUKHANI	MLOPI		
2	LEWIS GORE	MOP1		
3	Jitshya Ishiguro	JICA		
4	PHILIP WATAHI	MRB		
5	Jeremiah	MRB		
6	OTIM BONG	MRB		
7	Makiko Kiura	JICA		
8	Kame Mamyai	MRB		
9	TAKASHI WAKANA	CTI / JICA		
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				

4-2 Technical Notes

Ministry of Roads and Bridges
Republic of South Sudan

Ministry of Physical Infrastructure, Central Equatoria
Republic of South Sudan

PREPARATORY SURVEY
ON
THE PROJECT FOR CONSTRUCTION
OF
THE LOLOGO BYPASS AND BRIDGES IN JUBA CITY
IN THE REPUBLIC OF SOUTH SUDAN

TECHNICAL NOTES

JUNE 2013

JAPAN INTERNATIONAL COOPERATION AGENCY

CTI ENGINEERING INTERNATIONAL CO., LTD.

د 195



Preparatory Survey on the Project for Construction of
the Lologo Bypass and Bridges in Juba City
in the Republic of South Sudan

Technical Notes

JICA Survey Team for the Preparatory Survey (the Survey Team) has confirmed the items described in the attached Technical Notes concluded by the representative of the Ministry of Roads and Bridges (MRB) which is the responsible and implementing organization on the Project for Construction of the Lologo Bypass (as PART I) and Bridges (as PART II) in Juba City in the Republic of South Sudan (the Project), with representatives of concerned Ministries as the witnesses. Based on the Technical Notes, the Survey Team plans to conduct the basic design for the Project including the project cost estimate through analysis of the site survey findings after obtaining the approval from Japan International Cooperation Agency (JICA).

The results of the analysis and basic design are planned to be presented and explained in December, 2013.

Juba City, Republic of South Sudan
June, 2013

For 

YUZO MIZOTA
Chief Consultant
JICA Survey Team
Date: 28 Jun 2013
Signature: 


JOHN BULLEN
Director General
Ministry of Physical Infrastructure
Central Equatoria State
(Witness)


GABRIEL MAKUR
Undersecretary
Ministry of Roads and Bridges
Republic of South Sudan


OTIM BONG MIKE
Acting Director
Ministry of Roads and Bridges
Republic of South Sudan
(Witness)

PART II BRIDGES

1. Plan and Design

1.1 Design Standard to Apply

Reference shall be made to following manuals and standard specifications for the basic design requirement of roads and bridges;

- 1) Geometric Design Manual, Ministry of Transport and Roads, GOSS, 2006.
- 2) Bridge Design Manual, Ministry of Transport and Roads, GOSS, 2006.
- 3) Drainage Design Manual, Ministry of Transport and Roads, GOSS, 2006

In addition to the above guidelines when other aspects of design are not covered or when a safer and more efficient requirement is indicated, the design shall refer to other standards including;

- 4) AASHTO Policy on Geometric Design Highway and Streets, 2004
- 5) AASHTO LRFD Bridge Design Specifications, 4th Ed., 2007
- 6) AASHTO Standard Specifications for Highway Bridges, 17th Ed., 2002
- 7) Road Design Ordinances, Japan, 2004
- 8) Specifications for Highway Bridges, Japan Road Association, 2002
- 9) Specification for River Facilities, Japan River Association, 1998.

1.2 Bridge Plan

(1) Bridges Under Japan's Grant Aid

The bridges selected for the Japan's Grant Aid are six (6) as evaluated as "A rank" in total as shown in Table 2.1-1.

The location is shown in **Annex-1**.

Table 2.1-1 Evaluation Result

No.	Bridge Name	River	Payam	Evaluation Rank
1	Shuhada	Lobuliet	Kator	A
3	Salam	Lobuliet	Kator	C
4	Albino	Lobuliet	Kator	A
7	Salakana	Korbou	Juba	A
10	Kokora	Korbou	Juba	A
11	Lukabadi	Korbou	Juba	C
17	Lodoro	Lodoro	Juba	C
18	Korweliang 1	Weliang	Rajaf	A
19	Korweliang 2	Weliang	Rajaf	A
20	Korweliang 3	Weliang	Kator	C
21	Korweliang 4	Weliang	Kator	C
22	Saledo	Saledo	Juba	B
23	Lantor	Saledo	Mundki	B

A: High Urgency (the current problem is due to the bridge (missing link, traffic congestion, flood, structural soundness etc..))

B: Middle Urgency (the problem is partly due to the bridge but requires other actions to take before construction of the bridge (ROW, road rehabilitation, flood mitigation etc..))

C: Low Urgency (no existing road to the proposed bridge, very small traffic volume, existing of alternate road etc..)

PART II BRIDGES

(2) Road Typical Cross Section

The road typical cross section shall follow the existing road plan in principal.
The typical road cross section is shown in Annex-2.

(3) Bridge Design Condition

The bridge design condition is shown in Annex-3.

1.3 Road Design

(1) Design Speed

The project bridge and approach roads are located in the center of Juba City. The design speed shall selected 50km/hr of Urban/Peri-Urban from South Sudan’s design guideline.
However, in order to accommodate the road and bridges within present ROW the design speed might be reduced in order to avoid increase of affected structure and compensation.

(2) Road Alignment (Horizontal and Profile)

The design of the road alignment shall be followed by the South Sudan’s design standard, AASHTO or Japan’s Road Design Ordinances according the design speed.

(3) Pavement Design

The Asphalt Pavement shall be applied. The design axle load shall be ten (10) ton which is agreed as EAC(Eastern African Community) standard. Pavement Design Life shall be ten (10) years in consideration of availability of existing reliable data by the design method of AASHTO Guideline. Pavement configuration and design specification shall be as shown in Table 1.3-1.

Table 1.3-1 Pavement configuration and design specification

Location	Pavement	Design Specification
Carriage Way	Sub-base Course	More than CBR30
	Base Course	More than CBR80
	Wearing Course	Asphalt Concrete
Walk Way	Sub-base Course	More than CBR30
	Base Course	More than CBR80
	Wearing Course	Block Type

(4) Road Drainage Design

The design of road drainage facilities shall be referred to the design return period shown in Table1.4-1.

Table 1.4-1 Return Period for the Road Drainage Design

Structure Type	Return Period (Yrs)	Remark
Gutter and Inlets	2	
Bridge and Culverts	50	

Handwritten signature in green ink.

Handwritten signature in black ink.



Handwritten signature in black ink.

PART II BRIDGES

(5) Crossing Roads

1) Maximum Slope and Pavement

The crossing road shall be smoothly adjusted to the Lologo Bypass at maximum slope of 7%. The crossing road shall be paved approximately 3m from the Lologo Bypass.

2) Pavement Structure of Crossing Road

Pavement structure of the crossing road shall be;
Base Course 15cm, Asphalt Pavement 3cm

1.4 Bridge Design

(1) Superstructure

RC girder type shall be applied due to economical efficiency. The comparative study result is shown in **Annex-4**.

(2) Substructure (Foundation Type)

The Substructure type is selected according to the soil investigation result as shown in Table 1.4-1.

Table 1.4-1 Selection of Foundation Type

Bridge No	Type
Bridge No.1	Pile Foundation
Bridge No.4	Spread Foundation
Bridge No.7	Pile Foundation
Bridge No.10	Spread Foundation
Bridge No.18	Pile Foundation
Bridge No.19	Pile Foundation

(3) Bridge Pavement

Bridge shall be designed with the asphalt pavement of 5cm thickness. The walkway shall be block type.

(4) Bridge Railing Type

The concrete type shall be applied for the advantage of maintenance and cost. The comparative study result is shown in **Annex-5**.

(5) Joint

Expansion Joint type will be applied steel type joint, because of excellence for durability, maintenance, and economic efficiency.

(6) Approach Cushion Slab

Approach cushion slab will be installed behind abutment to prevent subsidence of embankment behind abutment.

7-
di
2

27



PART II BRIDGES

1.5 Crossing Road

(7) Maximum Slope and Pavement

The crossing road shall be smoothly adjusted to the Lologo Bypass at maximum slope of 7%. The crossing road shall be paved approximately 3m from the Lologo Bypass.

(8) Pavement Structure of Crossing Road

Pavement structure of the crossing road shall be;
Base Course 15cm, Asphalt Pavement 3cm

1.6 Road Facilities

(1) Lane Marking

Center Line : To be included
Carriageway Line : To be included
Shoulder Line : Not applied (no shoulder)

(2) Street Lighting

The project is for rehabilitation of bridge and approach road only. The street lighting shall not be included.

(3) Guard Rail

Guard rail shall be installed at the portion where embankment or wall height is more than 2m.

2. Construction Plan

2.1 Size and Location of Construction Yard

The construction requires the temporary construction yard of 2ha(200mx100m). (The construction yard is supposed to be the same as Lologo Bypass.) The possible construction yard location is shown in Annex-6.

2.2 Borrow Pit, Quarry Sites and Disposal Sites

The possible location of borrow pit, quarry sites and disposal sites are shown in Annex-6.

2.3 Traffic Control

(1) Bridge No.1,4,7,10

These four (4) bridges shall be in the center of Juba City on the busy road. It is agreed to divert the traffic to the existing road during the construction. Temporary diversion for the pedestrians shall be considered in the design. The traffic diversion plan is shown in Annex-7. The stage construction of the bridges shall be considered in the design in order to mitigate traffic safety, congestion and pedestrians inconveniences.

ص 111

6

28



7

PART II BRIDGES

(2) Bridge No.18,19

The major traffic is trucks and trailers from the factory along C3 at present condition. The No.18 shall be constructed earlier than No.19 so that Bridge No.18 can be used as diversion of the traffic. In this way it is not required any specific diversion to other road. Traffic diversion plan is shown in Annex-8.

3. Environmental and Social Consideration

3.1 ESIA

The environmental and social impact is limited because the project shall be on the existing ROW. It is confirmed the ESIA (Environmental and Social Impact Assessment) is sufficient to obtain required license.

4. Underground Utilities

4.1 Relocation required

The list of the underground utilities that require relocation is shown in Table 4.1-1.

Table 4.1-1 Utility Condition of each bridges

Bridge	Name	Water Supply	Electricity	Communication
Br.1	Shuhada	No	Overhead	There is communication line but it is already abandoned.
Br.4	Albino	No	Overhead	No
Br.7	Salakana	No	No	There is communication line but it is already abandoned.
Br.10	Kokora	There are ϕ 6inch pipeon the approach road. It is not passing the existing river.	No	No
Br.18	Weliang 1	No	No	No
Br.19	Weliang 2	No	No	No

4.2 Coordination for utility relocation

Based on the above mentioned facilities, MRB will coordinate with relevant authorities for relocation.

29



PART II BRIDGES

5. Undertakings by Republic of South Sudan

5.1 Major Tasks to be Undertaken by Each Government

The major tasks to be undertaken by each government has been confirmed in the Minutes of Discussions dated on 26, March 2013 (**Annex-9**).

5.2 Tax Exemption Related to Construction

The RSS side shall issue exemption certificates for all concerned members working for the Project from Customs duties, internal taxes and other fiscal levies that may be imposed in Southern Sudan with respect to the supply of products and services, including the exemption certificate from the Central Equatoria State.

5.3 Secure of the Land

The RSS sides shall secure the land required for the construction.

The Table 5.3-1 shows required actions to be taken.

Table 5.3-1 Required actions to be taken for the bridge construction

Bridge	Land etc.,	Remark
No.1	Removal of excising bill board	The existing bill board is very close to the exaction of the foundation.
No.4	Part of existing restaurant	Only affected during the foundation excavation
No.7	Part of Concrete Block Wall	Only affected during the foundation excavation
No.10	Part of masonry wall (under construction)	Only affected during the foundation excavation
No.18 No.19	Justification of the wire fence installed at the site by law. To secure the land required for the bridge and future river improvement.	The existing fence might be illegal.

5.4 Permission for Aggregate/Soil Borrow Site

The RSS side shall obtain permissions for mining of aggregate/soil from the concerned authority and/or the private firm concerned for the possible locations of borrow site. The possible location is shown in 2.1.

5.5 Permission for Dumping Discarded Soil

The RSS side shall obtain permission of use of disposal area including discarded soil from the concerned authority and/or the private firm concerned for the possible locations for dumping discarded soil. The possible location is shown in 2.1.

Handwritten signature in green ink.

Handwritten signature in black ink.

30



PART II BRIDGES

5.6 Acquisition of Construction Yard

The RSS side shall procure the construction yard to be used during the construction period through negotiation with the community and to execute an agreement of lease prior to the approval of tender documents. The possible location is shown in 2.1.

5.7 River Water Usage

The RSS side shall obtain exemption from the Nile River abstraction and permission for construction usage during the entire construction period from the Ministry of Water Resource Management and Irrigation.

5.8 Coordination with Traffic Control Concerned Authorities

The RSS shall take required coordination with traffic control concerned authorities to facilitate the construction work and ensure traffic safety near the project area.

5.9 Environmental License

The RSS shall apply for the environmental license required for implementation of the project in accordance with the environmental and social impact study result and resettlement plan.

5.10 Coordination with other project and authorities

The RSS shall take required monitoring and coordination with other project and authorities along the road to prevent any encroachment and increase of the compensation. Especially, the road where Bridge No.18 and No.19 are located might be rehabilitated by RSS budget. The horizontal alignment, profile, typical cross section etc., need to be adjust the plan of Japan's Grant Aid.

5.11 Coordination on Underground Utilities

The MRB shall coordinate with SSUWC in regards to underground water pipe at Bridge No.10. The result of the coordination shall be informed to Japan side by 31 July 2013.

5.12 Others


MRB shall obtain required license or official approval for implementation of the project. MRB shall support for the engineers involved in the project for travel and stay in Republic of South Sudan.

Handwritten initials in green ink.

Handwritten signature in black ink.



31



Annex-1 Location Map of the Bridges


Bridge	BridgeNo.1 (Road C1)	BridgeNo.4 (Road Q)
Road Typical Cross Section		
Road H<2m		
Road H>2m		
Bridge		

Annex 2.1(1/3) Bridge Typical Cross Section

A-4-23



PART II BRIDGES



Annex 2.1(2/3) Bridge Typical Cross Section

A-4-24



PART II BRIDGES

Bridge	BridgeNo.18	BridgeNo.19 (Road 2)
Road Typical Cross Section	<p>SAWA'S PLAN IN 2008</p>	<p>SAWA'S PLAN IN 2008</p>
Road H<2m	<p>ABMC PROPOSAL</p>	<p>ABMC PROPOSAL</p>
Road H>2m	<p>RECOMMENDATION (C3)</p>	<p>RECOMMENDATION ROAD 2</p>
Bridge	<p>RECOMMENDATION (C3) Bridge 18</p>	<p>RECOMMENDATION (C3) Bridge 19</p>

Annex 2.1(3/3) Bridge Typical Cross Section

A-4-25



Annex 3 Bridge Design Condition

Design Item		Criteria / Value	
1.0 General	Design Reference	<ul style="list-style-type: none"> • Bridge Design Manual, Ministry of Transport and Roads, GOSS, 2006 • Geometric Design Manual, Ministry of Transport and Roads, GOSS, 2006 • Drainage Design Manual, Ministry of Transport and Roads, GOSS, 2006 • AASHTO LRFD Bridge Design Specifications, 5th Edition, 2012 • Specifications for Highway Bridges, Part I-V, Japan Road Association, 2012 	
	Road/Bridge Class	• Interstate Trunk Road (DS1)/Primary Arterial	
	Bridge Section Length (m)	Refer Table-2	
	Span Configuration (m)	Refer Table-2	
	Design Speed (km/hr)	50	
2.0 Geometry	Min. Horizontal Curve Radius (m)	150 (2.5%)	
	Max. Gradient (%)	6	
	Travel Lane Width (m)	2.5 – 3.5	
	Sidewalk (m)	1.5 – 1.9	
	Pavement Crossfall (%)	2.5	
	Vertical Clearance on Roadway (m)	5.3 (GOSS BDM 2.4.5 for light structures)	
	Vertical Clearance on Design Flood Level (m)	0.9 (GOSS BDM, DDM)	
	Elevation of Design Flood Level (m)	Riverbed Level + 2.0m	
3.0 Design Load	Live Load	HL-93 (AASHTO)	
	Pedestrian Load (kPa)	4.0 (GOSS BDM 3.12)	
	Flood Velocity (m/s)	1.8	
	Base Wind Velocity, V_B (m/s)	45 (Open Country)	
	Peak Ground Acceleration Coefficient	0.2	
	Temperature	T_{max} (°C)	50
		T_{min} (°C)	15
4.0 Materials	Concrete Strength	Footing/Pile Cap (MPa)	24
		Bored Piles (MPa)	30
		Pier/Abutment/Retaining Wall (MPa)	24
		Slab/Railing (MPa)	24
		Slope Protection (MPa)	21
		Lean Concrete (MPa)	16
	Reinforcing Bars	Yield Strength, f_y (MPa)	415 (Over D16)
		Yield Strength, f_y (MPa)	276 (Less than D13)
Others		BDM, AASHTO, JARA	



Table-2 List of Bridge Length and Span Length


Bridge No.	Bridge Length (m)	Span Length(m)
1	15.0	14.0
4	11.5	10.5
7	9.0	8.0
10	13.0	12.0
18	11.0	10.0
19	11.0	10.0
A	15.0	14.0

Annex-4 Comparative Study of Superstructure

	Option-1 RC Girder	Option-2 Steel Girder (H beam)
Typical Cross Section		
Structural feature	<ul style="list-style-type: none"> • Dead load is heavier than steel girder. (△) • Low maintenance (⊙) 	<ul style="list-style-type: none"> • Dead load is lighter than RC girder (○) • Need periodical maintenance (Repaint) (△)
Workability	<ul style="list-style-type: none"> • Almost materials can be procured in Juba. (○) • All staging method is applied as construction method, so need to consider the period of flood season. (△) 	<ul style="list-style-type: none"> • Need to procure of materials from other countries. (△) • Crane erection method can be applied as construction method, so it is possible to work the erection during flood season. (○)
Construction Cost	1.0 (⊙)	1.2 (△)
Construction Period	<ul style="list-style-type: none"> • Need to avoid the flooded season. (△) • Construction period is almost as same as Steel girder. (○) 	<ul style="list-style-type: none"> • Need to avoid the flooded season. (△) • Construction period is almost as same as RC girder. (○)
Landscape and Environment	<ul style="list-style-type: none"> • It looks heavy compared to the steel girder because the girder height becomes higher than steel girder. (△) 	<ul style="list-style-type: none"> • It can be given the impression of stylish because it is possible to keep low girder height as compared RC girder. (○)
Evaluation	○ RC girder is recommended since it is economic. And, it also is same as a request of the South Sudan government.	△

Annex-5 Bridge Railing Comparison

Option	(1) Concrete Wall Type	(2) Steel Post Type
Image View		
Characteristic	<ul style="list-style-type: none"> • This railing is made of whole concrete. • Heavier than steel post type. • Pedestrian feel a feeling of pressure. • Dirt is conspicuous. 	<ul style="list-style-type: none"> • This railing is made of steel. • Lighter than concrete wall type. • There is a feeling of opening compared with concrete. • Dirt is not conspicuous.
Construction Cost	230 USD/m (23,000 JPY / m)	370USD/m (37,000 JPY / m)
Evaluation	○	△
Comment	The steel post type is not favorable in terms of maintenance including replacement in case any heavy accident occurs. The concrete type shall be selected for maintenance and cost.	




Annex-6 Location of Borrow Pit and Disposal Sites

جواد

Job


Handwritten signature

Handwritten signature



- Legend**
- : Diversion Route
 - : Limit of the Traffic During Construction
 - : Sign Board


Annex-7 Traffic Diversion Plan for No.1, No.4, No.7, No.10 Bridge



Annex-8 Traffic Diversion Plan for No.18, No.19 Bridge

31
0

[Handwritten signature]



Major Tasks to be Undertaken by Each Government

No.	Items	To be covered by Grant Aid	To be covered by the Recipient Side
1	To secure land		●
2	To clear, level and reclaim the site when needed		●
3	To construct gates and fences in and around the site		●
4	To bear the following commissions to the Japanese bank for banking services based upon the B/A		
	1) Advising commission of A/P		●
	2) Payment commission		●
5	To ensure unloading and customs clearance at port of disembarkation in recipient country		
	1) Marine/Air/Land transportation of the products from Japan to the recipient country	●	
	2) Tax exemption and customs clearance of the products at the port of disembarkation		●
	3) Internal transportation from the port of disembarkation to the project site	●	
6	To accord Japanese nationals, whose service may be required in connection with the supply of the products and the services under the Verified Contract, such facilities as may be necessary for their entry into the recipient country and stay therein for the performance of their work		●
7	To exempt Japanese nationals from customs duties, internal taxes and other fiscal levies which may be imposed in the recipient country with respect to the supply of the products and services under the Verified Contracts		●
8	To maintain and use properly and effectively the facilities contracted and equipment provided under the Grant Aid		●
9	To bear all the expenses, other than those to be borne by the Grant Aid, necessary for construction of the facilities as well as for the transportation and installation of the equipment		●

(B/A : Banking Arrangement, A/P : Authorization to Pay)

✓
✓

✍

40





REPUBLIC OF SOUTH SUDAN
MINISTRY OF ENVIRONMENT

Office of the Under Secretary

Ref: RSS/MoEnv/J/14/17

02/10/2013


Undersecretary
Ministry of Roads and Bridges
Republic of South Sudan, Juba

Subject: Environmental Authorization for implementation of bridges rehabilitation Project

Reference is hereby made to your letter without number and dated August 19th, 2013 requesting the Ministry of Environment, RSS, Juba to issue an approval to undertake implementation of the project for rehabilitation of six bridges in Juba City, Republic of South Sudan.

Based on the review of the Environmental and Social Impact Assessment study report for the proposed rehabilitation project in accordance with the EIA requirements, the Ministry has granted an approval authorizing the Ministry of Road and Bridges to undertake implementation of the proposed project whose objective is rehabilitation of six small scale bridges of Shuhada, Albino, Salakana, Kokora, Weliang 1 and Weliang 2, all in Juba City subject to the following conditions to ensure environmentally sustainable development:

1. The proponent shall ensure compliance with the environmental management plan (EMP) (or Environmental and social management plan in Tables 25 & 26, pages 62 - 65) during the project cycle;
2. The project proponent shall ensure adherence to the occupational health and safety requirements for the workforce;
3. The proponent shall, during the construction phase, manage all potential impacts with standard procedures of good engineering practices pertaining to road maintenance project;
4. The proponent shall ensure that there must be control of pollution, traffic disruptions and nuisance;
5. The project proponent shall submit an environmental audit report in the first year of its operation to confirm compliance with best practices.


Victor Wurda LoTombe
Ag/Under Secretary
Ministry of Environment
RSS, Juba



CC:JICA, South Sudan, Juba

Ministry of Transport, Roads and Bridges
Republic of South Sudan

PREPARATORY SURVEY
ON
THE PROJECT FOR CONSTRUCTION
OF
THE BRIDGES IN JUBA CITY
IN THE REPUBLIC OF SOUTH SUDAN

TECHNICAL NOTES

OCTOBER 2015

JAPAN INTERNATIONAL COOPERATION AGENCY

CTI ENGINEERING INTERNATIONAL CO., LTD.

M

[Handwritten signatures]

Preparatory Survey on the Project for Construction of the Bridges in Juba City
in the Republic of South Sudan


Technical Notes


JICA Survey Team for the Preparatory Survey (the Survey Team) has confirmed the items described in the attached Technical Notes concluded by the representative of the Ministry of Transport, Roads and Bridges (MTRB) which is the responsible and implementing organization on the Project for Construction of the Bridges in Juba City in the Republic of South Sudan (the Project). Based on the Technical Notes, the Survey Team plans to conduct the basic design for the Project including the project cost estimate through analysis of the site survey findings after obtaining the approval from Japan International Cooperation Agency (JICA).

Juba City, Republic of South Sudan
October, 2015

For 平馬博之

YUZO, MIZOTA
Chief Consultant
JICA Survey Team


GABRIEL MAKUR
Undersecretary
Ministry of Transport,
Roads and Bridges
Republic of South Sudan


OTIM BONG MIKE
Acting Director General
Ministry of Transport,
Roads and Bridges
Republic of South Sudan
(Witness)



1 . Priority of Bridges

The priority of six (6) bridges to be constructed is divided into following two (2) groups due to the traffic volume and city activity convenience :

Priority of Bridge Construction	Bridge Number	Remarks
First Priority	Bridge No.1, Bridge No.4, Bridge No.7, Bridge No.10	High traffic volume and convenience in the city center
Second Priority	Bridge No.18, Bridge No.19	Low traffic volume along/near outer ring road

First Priority Bridges are targeted to be constructed under the Project.

Second Priority Bridges are not included under the Project.

2 . Bridge Designs

(1) Bridge Pavement

Bridge shall be designed with the concrete pavement and concrete pavement shall be incorporated in the deck slab of the bridge.

(2) Joint

Expansion Joint type will be applied rubber type joint, because of excellence for durability, maintenance, and economic efficiency as actual experience.

3 . Undertakings by Republic of South Sudan

The major tasks to be undertaken by the Republic of South Sudan(RSS) has been confirmed in the technical note dated on 28, June 2013. The following issues to be undertaken by Republic of South Sudan were additionally confirmed in this technical note after conducting site survey from 16th of September 16 to 5th of October, 2015.

(1) Pavement of Approach Roads to the Bridges

Pavement of Approach Roads to the Bridges is constructed by the RSS with his own finance, while the embankment will be constructed under the Project.

(2) Secure of the Land and Relocation of the Utilities

The RSS sides shall secure the land and the relocation of the utilities required for the construction. **The Table 1 shows Requirements of the RSS for the Construction of the Bridges in Juba City** to be taken.

And the drawing of the locations for the obstructions are shown in **Annex-1**.

The fund, 1,500,000 SSP, for the **Requirements of the same** already has been allocated by MTRB.

Table-1 Requirements of the RSS for the Construction of the Bridges in Juba City

Bridge Name	Items	Obstruction(Land, Fence, Masonry Wall, e.t.c.)	Quantity of Obstruction
No.1	①	Removal of existing Bamboo Fence	26m
	②	Removal of existing Barbed Wire Fence	16m
	③	Removal of existing Scrapped Cars	6 cars
	④	Removal of existing Electric Wire and Pole	110m
	⑤	Removal of existing Bill Board 1.3mx2.4m	1 unit
	⑥	Removal of existing Bamboo Fence	21m
No.4	①	Removal of part of existing Restaurant	27m ²
	②	Removal of existing Electric Wire and Pole	120m
	③	Removal of existing Bamboo Fence	30m
No.7	①	Removal of existing Corrugated Plate Galvanized Fence	72m
	②	Removal of existing Masonry Wall	12m
	③	Removal of existing Bamboo Fence	40m
	④	Removal of existing Corrugated Plate Galvanized Fence	32m
	⑤	Removal of existing Sign Board 3mx2m	1 unit
No.10	①	Removal of Brick and Masonry Wall	8m
	②	Demolition of existing Concrete Box (1.9mx4.8m)	9.2m ²
	③	Removal of existing Bamboo Fence	16m
	④	Removal of existing Bamboo Fence	25m
No.18	①	Removal of existing Barbed Wire Fence	176m
	②	New Wire Mesh Fence Constructed	-
	③	Removal of New Cultivated Yard	1520m ²
No.19	①	Removal of existing Barbed Wire Fence	217m
	②	Occupation of this Area	-

u

(Signature)

(Signature)

ANNEX-1


Drawings for Removal of the Obstructions

M

3

(Signature)


(Signature)



A-4-38


m

Handwritten signature and initials



 REPUBLIC OF SOUTH SUDAN	Approved by Project Manager	THE PROJECT FOR CONSTRUCTION OF THE LOLOGO BYPASS AND BRIDGES IN JUBA CITY IN THE REPUBLIC OF SOUTH SUDAN	 JAPAN INTERNATIONAL COOPERATION AGENCY CTI ENGINEERING INTERNATIONAL CO., LTD.	Designed	TITLE: SITE DEVELOPMENT PLAN (BRIDGE NO. 4)	SCALE	DWG. NO. DATE SHT. NO. CB - 15
				Checked		1:600	
				Approved			

m
23
107




 REPUBLIC OF SOUTH SUDAN	Approved by	THE PROJECT FOR CONSTRUCTION OF THE LOLOGO BYPASS AND BRIDGES IN JUBA CITY IN THE REPUBLIC OF SOUTH SUDAN	 JAPAN INTERNATIONAL COOPERATION AGENCY CTI ENGINEERING INTERNATIONAL CO., LTD.	Designed	TITLE: SITE DEVELOPMENT PLAN (BRIDGE NO.7)	SCALE	DWG. NO. CB - 26
	Project Manager			Checked		DATE	
				Approved		SHT. NO.	

A-4-40

m


SM-30



<p>REPUBLIC OF SOUTH SUDAN</p>	Approved by	<p>THE PROJECT FOR CONSTRUCTION OF THE LOLOGO BYPASS AND BRIDGES IN JUBA CITY IN THE REPUBLIC OF SOUTH SUDAN</p> <p>JAPAN INTERNATIONAL COOPERATION AGENCY</p> <p>CTI ENGINEERING INTERNATIONAL CO., LTD.</p>	Designed	<p>TITLE:</p> <p>SITE DEVELOPMENT PLAN (BRIDGE NO. 10)</p>	SCALE	<p>DWG. NO.</p> <p>1:500</p> <p>DATE</p> <p>SHT. NO.</p> <p>CB-37</p>
	Project Manager		Checked			
			Approved			

A-4-41


m
AS



 REPUBLIC OF SOUTH SUDAN	Approved by	THE PROJECT FOR CONSTRUCTION OF THE LOLOGO BYPASS AND BRIDGES IN JUBA CITY IN THE REPUBLIC OF SOUTH SUDAN	 JAPAN INTERNATIONAL COOPERATION AGENCY CTI ENGINEERING INTERNATIONAL CO., LTD.	Designed	TITLE: SITE DEVELOPMENT PLAN BRIDGE NO. 18	SCALE	DWG. NO. 1:1,000 DATE SHT. NO. CB - 48
	Project Manager			Checked		1:1,000	
				Approved		DATE	

m

Handwritten signature



 <p>REPUBLIC OF SOUTH SUDAN</p>	Approved by	<p>THE PROJECT FOR CONSTRUCTION OF THE LOLOGO BYPASS AND BRIDGES IN JUBA CITY IN THE REPUBLIC OF SOUTH SUDAN</p>	 <p>JAPAN INTERNATIONAL COOPERATION AGENCY CTI ENGINEERING INTERNATIONAL CO., LTD.</p>	Designed	<p>TITLE:</p> <p>SITE DEVELOPMENT PLAN BRIDGE NO. 19</p>	SCALE	<p>1:1,000</p>
	Project Manager			Checked		DATE	
				Approved		SHT. NO.	

Ministry of Transport, Roads and Bridges
Republic of South Sudan

Ministry of Physical Infrastructure, Central Equatoria
Republic of South Sudan

PREPARATORY SURVEY
ON
THE PROJECT FOR CONSTRUCTION
OF
THE BRIDGES IN JUBA CITY
IN THE REPUBLIC OF SOUTH SUDAN

TECHNICAL NOTES

NOVEMBER 2015

JAPAN INTERNATIONAL COOPERATION AGENCY
CTI ENGINEERING INTERNATIONAL CO., LTD.



Preparatory Survey on the Project for Construction of the Bridges in Juba City
in the Republic of South Sudan

Technical Notes

JICA Survey Team for the Preparatory Survey (the Survey Team) has confirmed the items described in the attached Technical Notes concluded by the representative of the Ministry of Transport, Roads and Bridges (MTRB) which is the responsible and implementing organization on the Project for Construction of the Bridges in Juba City in the Republic of South Sudan (the Project). Based on the Technical Notes, the Survey Team plans to conduct the basic design for the Project including the project cost estimate through analysis of the site survey findings after obtaining the approval from Japan International Cooperation Agency (JICA).

Juba City, Republic of South Sudan
November, 2015

for 平馬博之

YUZO, MIZOTA
Chief Consultant
JICA Survey Team



JOHN BULLEN
Director General
Ministry of Physical Infrastructure
Central Equatoria State



GABRIEL MAKUR
Undersecretary
Ministry of Transport,
Roads and Bridges
Republic of South Sudan

OTIM BONG MIKE
Acting Director General
Ministry of Transport,
Roads and Bridges
Republic of South Sudan
(Witness)

1. Priority of Bridges

The priority of six (6) bridges to be constructed is divided into following two (2) groups due to the traffic volume and city activity convenience :

Priority of Bridge Construction	Bridge Number	Remarks
First Priority	Bridge No.1, Bridge No.4, Bridge No.7, Bridge No.10	High traffic volume and convenience in the city center
Second Priority	Bridge No.18, Bridge No.19	Low traffic volume along/near outer ring road

First Priority Bridges are targeted to be constructed under the Project.

Second Priority Bridges are not included under the Project.

2. Road Design

(1) Pavement Design

Concrete pavement is adopted for the pavement of bridges and approach roads in the view of economic aspects because of no availability to utilize the asphalt plant under the Project without Lologo Bypass.

(2) Road Drainage Design (Refer to Annex-1)

The design of road drainage facilities of No.1 Bridge (Right side from 0+60m to 1+00m) shall be changed its location and configuration of ditch due to new house constructed and its location is out of Right of Way.

And its configuration shall be changed from Masonry ditch (3300x2000x1300) to U-1000 ditch and shall be located along the outside of the retaining wall and gravity wall similar to other ditch.

Masonry ditch length remains only 5m length near the River.

3. Bridge Designs

(1) Bridge Pavement

Bridge shall be designed with the concrete pavement and concrete pavement shall be incorporated in the deck slab of the bridge.

(2) Joint

Expansion Joint type will be applied rubber type joint, because of excellence for durability, maintenance, and economic efficiency as actual experience.

(3) Bridge accessories

In future plan, there will be no bridge accessories such as water pipe lines.

4. Undertakings by Republic of South Sudan

The major tasks to be undertaken by the Republic of South Sudan (RSS) has been confirmed in the technical notes dated on 28, June 2013. The following issues to be undertaken by Republic of South Sudan were additionally confirmed in this technical notes after conducting site survey from 17th of September, 2015 to 10th of November, 2015.

(1) Pavement of Approach Roads to the Bridges

Pavement of Approach Roads to the Bridges is basically constructed by the RSS.

(2) Secure of the Land and Relocation required

The RSS sides shall secure the land and the relocation of the utilities required for the bridge construction under the Project.

- ① The Table-1 shows Requirements of the RSS for the Construction of the Bridges in Juba City to be taken. And the drawing of the locations for the obstructions are shown in Annex-2.
- ② The fund, 1,500,000 SSP, for the Requirements of the RSS already has been allocated by MTRB.
- ③ The problem of the occupation by Anseba Hotel at the No.7 Bridge Right of Way area was solved among MTRB, MOPI and Anseba Hotel with the agreement shown in Annex-3.
- ④ The RSS should reserve the Right of Way for Bridges Construction as shown in Annex-4.

Table-1 Requirements of the RSS for the Construction of the Bridges in Juba City

Bridge Name	Items	Removal of Obstruction (Land, Fence, Masonry Wall, e.t.c.)	Quantity of Obstruction
No.1	①	Removal of existing Bamboo Fence	26m
	②	Removal of existing Barbed Wire Fence	16m
	③	Removal of existing Scrapped Cars	6 cars
	④	Removal of existing Electric Wire and Pole	110m
	⑤	Removal of existing Bill Board 1.3mx2.4m	1 unit
	⑥	Removal of existing Bamboo Fence	15m

No.4	①	Removal of part of existing Restaurant *	5m ²
	②	Removal of existing Electric Wire and Pole	120m
No.7	①	Removal of Anseba Hotel Area from Right-of-Way	done
	②	Removal of existing Masonry Wall	16m
	③	Removal of existing Bamboo Fence	40m
	④	Removal of existing Sign Board 3m x 2m	1 unit
No.10	①	Removal of Brick and Masonry Wall	7m
	②	Demolition of existing Concrete Box (1.9m x 4.8m)	9.2m ²
	③	Removal of existing Bamboo Fence	16m

*This item should be removed under construction period due to the future bridge structure design change.

(3) Size and Location of Construction Yard

The construction requires the temporary construction yard of 2ha (200m x 100m).

The possible construction yard location is shown in Annex-5.

(4) Borrow Pit, Quarry Sites and Disposal Sites

The possible location of borrow pit and disposal sites are shown in Annex-5.

ANNEX-1

Road Drainage Design Change


Kof M

4

0.15 - 10'

Job M

Q 2005
M



ANNEX- 2


Drawings for Removal of the Obstructions

[Handwritten signature]

[Handwritten signature]

Ref
M

Done
M



A-4-51



REPUBLIC OF SOUTH SUDAN

Approved by
Project Manager

THE PROJECT FOR CONSTRUCTION OF
THE BRIDGES IN JUBA CITY
IN THE REPUBLIC OF SOUTH SUDAN




JAPAN INTERNATIONAL COOPERATION AGENCY
CTI ENGINEERING INTERNATIONAL CO., LTD.

Designed
Checked
Approved

TITLE:
SITE DEVELOPMENT PLAN
(BRIDGE NO.1)

SCALE: DWG. NO.
DATE: SHEET NO.
08/08

cat
mu




A-4-52

Handwritten notes and signatures in the bottom left corner, including a signature and some illegible text.

 <p>REPUBLIC OF SOUTH SUDAN</p>	<p>Approved by</p> <p>Project Manager</p>	<p>THE PROJECT FOR CONSTRUCTION OF THE BRIDGES IN JUBA CITY IN THE REPUBLIC OF SOUTH SUDAN</p>	 <p>JAPAN INTERNATIONAL COOPERATION AGENCY CTI ENGINEERING INTERNATIONAL CO., LTD.</p>	<p>Designed</p>	<p>TITLE:</p> <p>SITE DEVELOPMENT PLAN (BRIDGE NO. 4)</p>	<p>SCALE:</p> <p>1:500</p>	<p>DWG. NO.</p>
	<p>Checked</p>			<p>Approved</p>		<p>SHEET NO.</p> <p>03 - 08</p>	

Lot 5
N



REPUBLIC OF SOUTH SUDAN

Approved by
Project Manager

THE PROJECT FOR CONSTRUCTION OF
THE BRIDGES IN JUBA CITY
IN THE REPUBLIC OF SOUTH SUDAN



JAPAN INTERNATIONAL COOPERATION AGENCY
CTI ENGINEERING INTERNATIONAL CO., LTD.


Designer
Checker
Approver

TITLE
SITE DEVELOPMENT PLAN
(BRIDGE NO.7)

SCALE	DATE	DRG. NO.
1:500	19/11/2011	BR-07

A-4-53

cat
M



A-4-54

10
11

ANNEX- 3

Construction Condition of Anseba Hotel

206 M

6

0 111 111



Minutes of Meeting

Reference : The Project for Construction of Bridges in Juba City in the Republic of South Sudan

Subject : Construction Condition of Anseba Hotel Near to Salakana Bridge (Bridge No.7) Approach Road

Based on the previous field investigation and discussions held among parties such as Ministry of Transport, Roads, and Bridges (MTRB) of Republic of South Sudan, Ministry of Physical Infrastructure (MOPI) of Central Equatoria State Government and Hotel representative of Anseba Company LTD, the Parties have agreed that the land and facilities of Anseba Company Ltd fall within the Right-of-Way of the approach road to Salakana Bridge (Bridge No. 7), therefore, Anseba Company Ltd should relocate them outside of the Right-of-Way of Salakana Bridge (Bridge No.7) as shown in the enclosed layout drawings of Salakana Bridge (Bridge No.7) and its approach road. The attached documents include the following information:


- a. Approach road layout plan of Salakana bridge (Attachment-1)
- b. Survey coordinates of Right-of-Way for approach road of Salakana bridge (Attachment-1)
- c. Possible hotel land area near to Salakana bridge and approach road (Attachment-1)
- d. Salakana bridge layout plan (Attachment-1)
- e. Location of Salakana bridge in Juba City (Attachment-2)

For and on behalf of the MTRB
SIGNED BY: 
Eng. Otin Bang Mike
Acting Director for Roads and Bridges
Ministry of Transport, Roads and Bridges
Republic of South Sudan

For and on behalf of the Anseba Hotel


SIGNED BY: 
Mr. Merhawi Mesfun
Managing Director
Anseba Company Limited

For and on behalf of the MOPI:

SIGNED BY: 
Mr. Roman Marghani
Acting Director General, Roads and Bridges
Ministry of Physical Infrastructure
Central Equatoria State Government
Republic of South Sudan



A-4-57



Attachment-2

LOCATION MAP



A-4-58


ANNEX- 4

Guarantee Area for New Bridge Construction

Job No


7

DATE




Lot 3 M


Q



Let's see

Guarantee Area for
New Bridge Construction
No. 7 Bridge





Annex-5


Construction Yard, Borrow Pit Area and Jebel Disposal Area

Handwritten signature

8

Handwritten signature

Annex-5 Construction Yard, Borrow Pit Area and Jebel Disposal Area



Appendix 4-6 Minutes of Discussion (M/D) March 2016

資料一 議事録 (M/D)

MINUTES OF DISCUSSIONS
ON
THE PREPARATORY SURVEY
FOR
THE PROJECT FOR CONSTRUCTION OF BRIDGES IN JUBA
IN
THE REPUBLIC OF SOUTH SUDAN
(Explanation of Draft Outline Design Report)

On the basis of the preparatory survey started in March 2013, the Japan International Cooperation Agency (hereinafter referred to as "JICA") prepared a Draft Outline Design Report (hereinafter referred to as "the Report") on the Project for Construction of Bridges in Juba (hereinafter referred to as "the Project").

The Preparatory Survey Team, headed by Mr. Hidetaka Sakabe, Deputy Director, Team 1, Transport and ICT Group, Infrastructure and Peacebuilding Department, JICA, explained to and consulted with the concerned officials of the Government of the Republic of South Sudan (hereinafter referred to as "RSS") on the contents of the Report. As a result of discussions, both sides confirmed the main items described in the attached sheets.

Juba, March 16, 2016



Hidetaka Sakabe
Leader
Preparatory Survey Team
Japan International Cooperation
Agency



Gabriel Makur
Undersecretary
Ministry of Transport, Roads and
Bridges
Republic of South Sudan



Otim Dong Mike
Acting Director General
Ministry of Transport, Roads and
Bridges
Republic of South Sudan
(Witness)

ATTACHMENT

1. Components of the Draft Outline Design Report

- 1.1. The Ministry of Transport, Roads and Bridges (hereinafter referred to as MTRB) agreed and accepted in principle the contents of the Report explained by the Team. Main components of the Project consist of the following.
- a) Bridge No.1 (L=15.0m, 4 lanes), Approach Road (L=88.0m, 4 lanes)
 - b) Bridge No.4 (L=17.3m, 4 lanes), Approach Road (L=198.5m, 4 lanes)
 - c) Bridge No.7 (L=10.0m, 4 lanes), Approach Road (L=173.0m, 4 lanes)
 - d) Bridge No.10 (L=13.0m, 4 lanes), Approach Road (L=122.0m, 4 lanes)
- 1.2. The Team requested and the South Sudanese side agreed to confirm the components of the Project and submit comments if any for the Report by 15 April 2016.

2. Cost Estimation for the Project

- 2.1. The Japanese side explained to the South Sudanese side the rough estimate of the Project Cost described in Annex-1; however, the final Project Cost described in the Exchange of Note (hereinafter referred to as "E/N") would be appraised by the Government of Japan (hereinafter referred to as "GOJ").
- 2.2. Both Sides further confirmed that the Project Cost in Annex-1, and details of the construction works in the Report should never be duplicated and/or disclosed to any third parties until all the contracts for the Project are concluded.

3. Project Implementation Schedule

The Team explained to the South Sudanese side that the expected implementation schedule is as attached in Annex-2.

4. Indicators for Expected Outcomes

Both sides agreed that key indicators for expected outcomes are as follows. The South Sudanese side has responsibility to monitor the progress of the indicators.

[Quantitative Effect]

Indicator: Traffic Volume (PCU/day)	Base year 2013	Target year 2020 (Project completion)
Bridge No.1	11,600	24,220
Bridge No.4	5,480	9,090
Bridge No.7	6,450	13,290
Bridge No.10	10,450	16,400

[Qualitative Effect]

- Improved punctuality of passenger and freight traffic
- Enhanced convenience of the road network
- Improved safety for pedestrians and vehicles

5. Undertaking by South Sudanese Side

Both sides confirmed the undertakings described in Annex-3. The South Sudanese side assured that the necessary measures and coordination including allocation of the necessary budget are taken. It was understood that the costs are indicative, i.e. at Outline Design level. More accurate costs will be calculated at the Detailed Design stage. The Contents of Annex-3 will be updated as the Detailed Design progresses, and will finally be used in the contract document.

3-1. The construction yard will be prepared by MTRB as in Annex-4.

3-2. The Team recommended that the South Sudanese side explain to the residents the Project (necessity and significance, construction period, sites, impact etc.), so that consensus support can be obtained from them for the smooth operation of the Project.

6. Monitoring during the Implementation

The Project will be monitored and reported quarterly by MTRB and using the Project Monitoring Report (PMR) attached in Annex-5.

7. Ex-Post Evaluation

JICA will conduct ex-post evaluation three (3) years after the project completion with respect to five evaluation criteria (Relevance, Effectiveness, Efficiency, Impact, Sustainability) of the Project. Result of the evaluation will be publicized. The South Sudanese side is required to provide necessary support for them.

8. Schedule of the Study

JICA will complete the Final Report of the Preparatory Survey in accordance with the confirmed items and send it to the South Sudanese side around May 2016.

9. Environmental and Social Considerations

10-1 Environmental Checklist

The environmental and social considerations including major impacts and mitigation measures for the Project are summarized in the Environmental Checklist attached as Annex-6. Both sides confirmed that in case of major modification of the content of the Environmental Checklist, the South Sudanese side shall submit the modified version to JICA in a timely manner.



12-2 Environmental Monitoring Plan

Both sides agreed that the South Sudanese side will submit results of environmental monitoring to JICA by using the monitoring form attached as Annex-7.

10. Other Relevant Issues

13-1. Operation and Maintenance of the Facilities

The team explained the importance of operation and maintenance of the facilities constructed by the Project considering that proper asset management impacts greatly on life-span of the facilities and its maintenance cost. Ministry of Physical Infrastructure, Central Equatoria Stateshall secure enough staff and budgets necessary for appropriate operation and maintenance of the facilities.

13-2. Disclosure of Information

Both sides confirmed that the study results excluding the Project cost will be disclosed to the public after completion of the Preparatory Survey. All the study results including the project cost will be disclosed to the public after all the contracts for the Project are concluded.

13-3. Creation of the South Sudan Roads Authority (SSRA)

The South Sudanese side explained that the Bill for the creation of South Sudan Roads Authority (SSRA) was enacted in January 2011, but the authority is not fully functional. The MTRB assured that it continues to assume its responsibilities as the implementing agency upto the project completion. After the completion MoPI shall be in charge of maintenance of the four bridges.

Annex-1 Project Cost Estimation

Annex-2 Project Implementation Schedule

Annex-3 Major Undertakings to be taken by Each Government

Annex-4 Construction yard

Annex-5 Project Monitoring Report

Annex-6 Environmental Checklist

Annex-7 Environmental Monitoring Form



Annex-1: Project Cost Estimation

CONFIDENTIAL

(1) Cost Borne by the Government of Japan

Total: million JPY

- Civil Work: million JPY
- Detailed Design and Construction Supervisory Service: million JPY
- Contingency: million JPY

(2) Cost Borne by the Government of South Sudan

- Removal of obstructions, bank charges etc.: 12 million JPY

(3) Conditions of Cost Estimation

- Estimated timing: August 2015
- Exchange rates: 1.00 USD = 122.20 JPY
1.00 USD = 2.95 SSP
- Others: The project is implemented in accordance with the system of Japan's Grant Aid. The above cost estimation does not assure the ceiling cost on the E/N and shall be reviewed by GOJ before signing of the E/N between the two Governments.



Annex-2: Project Implementation Schedule

Year	2016				2017				2018				2019				2020			
Month	1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4
Cabinet Approval in Japan	✓																			
Exchange of Notes (EN) and Grant Agreement (GA)	✓																			
Consultant Contract and Approval																				
Decided Design																				
Tender Works																				
Construction																				

[Handwritten signature]

[Handwritten signature]

[Handwritten signature]

Annex-3 Major Undertakings to be taken by Each Government

Major Undertakings to be taken by Recipient Government

1. Before the Tender

NO	Items	Deadline	In charge	Cost	Ref.
1	To approve ESIA	within 1 month after G/A	Ministry of Environment	-	approved in Oct 2013
2	To implement ESIA	before start of the construction	MTRB	-	ESIA submitted to MOE in Aug 2013
3	To open Bank Account (Banking Arrangement (B/A))	within 1 month after G/A	MTRB	-	
4	To secure lands 1) temporary construction yard and stock yard near the Project area 2) borrow pit and disposal site near the Project area	before notice of the tender document	MTRB	-	
5	To obtain the planning, zoning, building permit, when needed.	before notice of the tender document	MTRB	-	
6	To clear, level and reclaim when needed	before notice of the tender document	MTRB	-	

2. During the Project Implementation

NO	Items	Deadline	In charge	Cost	Ref.
1	To bear the following commissions to a bank of Japan for the banking services based upon the B/A 1) Advising commission for B/A: 0.1 % of total project cost 2) Payment commission for B/A: 0.12% of every payment *15,000 Yen x 5 times	within 1 month after the signing of the contract every payment	MTRB	US\$20,200 US\$24,900	
2	To ensure prompt unloading and customs clearance at the port of disembarkation in recipient country 1) Tax exemption and customs clearance of the products at the port of disembarkation 2) Internal transportation from the port of disembarkation to the project site	during the Project during the Project	MTRB	-	None
3	To accord Japanese nationals whose services may be required in connection with the supply of the products and the services under the verified contract such facilities as may be necessary for their entry into the recipient country and stay therein for the performance of their work.	during the Project	MTRB	-	
4	To ensure that customs duties, internal taxes and other fiscal levies which may be imposed in the country of the Recipient with respect to the purchase of the Products and/or the Services be exempted. Such customs duties, internal taxes and other fiscal levies mentioned above include VAT, commercial tax, income tax and corporate tax of Japanese nationals, resident tax, fuel tax, but not limited, which may be imposed in the recipient country with respect to the supply of the products and services under the verified contract.	during the Project	MTRB	-	

4	To bear all the expenses, other than those to be borne by the Grant Aid, necessary for construction of the facilities as well as for the transportation and installation of the equipment.	during the Project	MTRH	-	
6	Relocation of Utilities (installation of water pipe, electric cable and telecommunication cable)		MTRH	US\$5,000	Removal of Utility post
7	Removal of obstruction in the construction site		MTRH	US\$15,000	Removal of trees, etc.
8	To submit environmental monitoring report to JICA South Sudan Office	during the Project	MTRH	-	

3. After the Project

NO	Items	Deadline	Exchange	Cost	Ref.
1	To maintain and use properly and effectively the facilities constructed and equipment provided under the Grant Aid 1) Allocation of maintenance cost 2) Operation and maintenance structure 3) Routine/Periodic inspection	After completion of the construction	MTRH	US\$16,100 per year	

Costs to be covered by the Grant Aid

No	Items	Deadline	Cost Estimated (Million Japanese Yen)
1	Civil Work		
2	To implement detailed design, tender support and construction supervision (Consultant)		
3	Contingencies		
	Total		

S

Lot

10

Annex-4: Construction Yard

Candidate of the temporary construction yard was proposed to MTRB by the Team. It will be decided by MOP.



[Handwritten signature]

[Handwritten signature]

[Handwritten signature]

添 1-9

Annex-5 Project Monitoring Report

<p>Project Monitoring Report</p> <p>on</p> <p>Project Name</p> <p>Grant Agreement No. <u>XXXXXXXX</u></p> <p>20XX, Month</p>
--

Organization Information

Authority (Signer of the G/A)	<p>Person in Charge _____</p> <p>(Division) _____</p> <p>Contacts Address: _____</p> <p>Phone/FAX: _____</p> <p>Email: _____</p>
Executing Agency	<p>Person in Charge _____</p> <p>(Division) _____</p> <p>Contacts Address: _____</p> <p>Phone/FAX: _____</p> <p>Email: _____</p>
Line Agency	<p>Person in Charge _____</p> <p>(Division) _____</p> <p>Contacts Address: _____</p> <p>Phone/FAX: _____</p> <p>Email: _____</p>

Outline of Grant Agreement:

Source of Finance	Government of Japan: Not exceeding JPY _____ mil, Government of (): _____
--------------------------	---

Project Title	
E/N	Signed date: Duration:
G/A	Signed date: Duration:

10



添 1-11

A-4-76

1: Project Description

1-1 Project Objective

--

1-2 Necessity and Priority of the Project

- Consistency with development policy, sector plan, national/regional development plans and demand of target group and the recipient country.

--

1-3 Effectiveness and the indicators

- Effectiveness by the project

Quantitative Effect (Operation and Effect indicators)		
Indicators	Original (Yr)	Target (Yr)
Qualitative Effect		

2: Project Implementation

2-1 Project Scope

Table 2-1-1a: Comparison of Original and Actual Location

Location	Original: (M/D)	Actual: (PMR)
	Attachment(s):Map	Attachment(s):Map

Table 2-1-1b: Comparison of Original and Actual Scope

Items	Original	Actual
(M/D)	(M/D)	(PMR)

8

of

10

'Soft component' shall be included in 'Items'.	Please state not only the most updated schedule but also other past revisions chronologically. All change of design shall be recorded regardless of its degree.
--	--

(Sample)Table 2-1-1b: Comparison of Original and Actual Scope

Items	Original	Actual
1. Bridges (No.1, 4, 7, 10)		
2. Approach Road		

2-1-2 Reason(s) for the modification if there have been any.

<i>(PMR)</i>

2-2 Implementation Schedule

2-2-1 Implementation Schedule

Table 2-2-1: Comparison of Original and Actual Schedule

Items	Original		Actual
	DOD	G/A	
<i>(M/D)</i> 'Soft component' shall be stated in the column of 'Items'. Project Completion Date*	<i>(M/D)</i>		<i>(PMR)</i> As of (Date of Revision) Please state not only the most updated schedule but also other past revisions chronologically.

*Project Completion was defined as at the time of G/A.

(Sample)Table 2-2-1: Comparison of Original and Actual Schedule

Items	Original		Actual
	DOD	G/A	
Cabinet Approval			

E/N			
G/A			
Detailed Design			
Tender Notice			
Tender			
(Lot1) Construction			
Period			
(Lot2) Installation of			
Equipment			
Project Completion Date			
Defect Liability Period			

*Project Completion was defined as Check-out of Construction work at the time of G/A.

2-2-2 Reasons for any changes of the schedule, and their effects on the project.

2-3 Undertakings by each Government

2-3-1 Major Undertakings
See Attachment *.

2-3-2 Activities
See Attachment *.

2-3-3 Report on RD
See Attachment *.

2-4 Project Cost

2-4-1 Project Cost

Table 2-4-1a Comparison of Original and Actual Cost by the Government of Japan

(Confidential until the Tender)

	Items		Cost (Million Yen)	
	Original	Actual	Original	Actual
Construction Facilities	'Soft component' shall be included in 'Items'.			Please state not only the most

S

26

101

(or Equipment)				updated schedule but also other past revisions chronologically.
Consulting Services	- Detailed design - Procurement Management - Construction Supervision			
Total				

Note: 1) Date of estimation:
2) Exchange rate: 1 US Dollar = Yen

Table 2-4-1b Comparison of Original and Actual Cost by the Government of XX

Items			Cost (Million USD)	
	Original	Actual	Original	Actual
				Please state not only the most updated schedule but also other past revisions chronologically.
Total				

Note: 1) Date of estimation:
2) Exchange rate: 1 US Dollar = (local currency)

(Sample) Table 2-4-1a Comparison of Original and Actual Cost by the Government of Japan
(Confidential until the Tender)

Items	Cost
-------	------

		(Million Yen)		
	Original	Actual	Original ^{1,2)}	Actual
Construction Facilities	I.			
Equipment				
Consulting Services				
Total				

Note: 1) Date of estimation: Month, Year
 2) Exchange rate: 1 US Dollar = ** Yen

(Sample)Table 2-4-1b Comparison of Original and Actual Cost by the Government of RSS

Items		Cost (SSP)		
	Original	Actual	Original ^{1,2)}	Actual
Total				

Note: 1) Date of estimation: Month, Year
 2) Exchange rate: 1 US Dollar = ** Yen (local currency)

2-4-2 Reason(s) for the wide gap between the original and actual, if there have been any, the remedies you have taken, and their results.

(PMR)

2-5 Organizations for Implementation
 2-5-1 Executing Agency:

S *of* *10*

- Organization's role, financial position, capacity, cost recovery etc.,
- Organization Chart including the unit in charge of the implementation and number of employees.

Original: (M/D)
Actual, if changed: (PMR)

2-6 Environmental and Social Impacts

- The results of environmental monitoring as attached in Attachment * in accordance with Schedule * of the Grant Agreement.
- The results of social monitoring as attached in Attachment * in accordance with Schedule 4 of the Grant Agreement.
- Information on the disclosed results of environmental and social monitoring to local stakeholders, whenever applicable.

3: Operation and Maintenance (O&M)

3-1 O&M and Management

- Organization chart of O&M
- Operational and maintenance system (structure and the number, qualification and skill of staff or other conditions necessary to maintain the outputs and benefits of the project soundly, such as manuals, facilities and equipment for maintenance, and spare part stocks etc.)

Original: (M/D)

Actual: (PMR)

3-2 O&M Cost and Budget
 - The actual annual O&M cost for the duration of the project up to today, as well as the annual O&M budget.

Original: (M/D)

4: Precautions (Risk Management)

- Risks and issues, if any, which may affect the project implementation, outcome, sustainability and planned countermeasures to be adapted are below.

Original Issues and Countermeasure(s): (M/D)	
Potential Project Risks	Assessment
1.	Probability: H/M/L
(Description of Risk)	Impact: H/M/L
	Analysis of Probability and Impact:
	Mitigation Measures:
	Action during the Implementation:
	Contingency Plan (if applicable):
2.	Probability: H/M/L
(Description of Risk)	Impact: H/M/L
	Analysis of Probability and Impact:

	Mitigation Measures:
	Action during the Implementation:
	Contingency Plan (if applicable):
3.	Probability: H/M/L
(Description of Risk)	Impact: H/M/L
	Analysis of Probability and Impact:
	Mitigation Measures:
	Action during the Implementation:
	Contingency Plan (if applicable):
Actual issues and Countermeasure(s) (PMR)	

5: Evaluation at Project Completion and Monitoring Plan

5-1 Overall evaluation

Please describe your overall evaluation on the project.

5-2 Lessons Learnt and Recommendations

Please raise any lessons learned from the project experience, which might be valuable for the future assistance or similar type of projects, as well as any recommendations, which might be beneficial for better realization of the project effect, impact and assurance of sustainability.

5-3 Monitoring Plan for the Indicators for Post-Evaluation

Please describe monitoring methods, section(s)/department(s) in charge of monitoring, frequency, the term to monitor the indicators stipulated in 1-3.



Attachment

1. Project Location Map
2. Undertakings to be taken by each Government
3. Monthly Report
4. Report on RD
5. Environmental Monitoring Form / Social Monitoring Form
6. Monitoring sheet on price of specified materials (Quarterly)
7. Report on Proportion of Procurement (Recipient Country, Japan and Third Countries)
(Final Report Only)



Annex-6 Environmental Checklist

Category	Environmental Item	Major items to be checked	Yes: Y No: N	Confirmation of Environmental Consideration
1. Permit and Explanation	(1) EIA and Environmental Permit	(a) Have EIA reports been already prepared in official process? (b) Have EIA reports been approved by authorities of the host country's government? (c) Have EIA reports been unconditionally approved? If conditions are imposed on the approval of EIA reports, are the conditions satisfied? (d) In addition to the above approvals, have other required environmental permits been obtained from the appropriate regulatory authorities of the host country's government?	(a) Y (b) Y (c) Y (d) N	(a) EIA reports have been already prepared in official process. (b) EIA reports were approved in October 2013 by authorities of the host country's government, MOE. (c) EIA reports been unconditionally approved. (d) Nothing.
	(2) Explanation to the Local Stakeholders	(a) Have contents of the project and the potential impacts been adequately explained to the Local stakeholders based on appropriate procedures, including information disclosure? Is understanding obtained from the Local stakeholders? (b) Have the comment from the stakeholders (such as local residents) been reflected to the project design?	(a) Y (b) N	(a) Stake Holder Meetings were held on 28 th March, 2013, 5 th April, 2013 and 27 th June, 2013. (b) The stakeholders have no comment on proceeding the project.
	(3) Alternatives	(a) Have alternative plans of the project been examined with social and environmental considerations?	(a) Y	(a) One alternative plan without the project was examined. Without the project, sufficient width of the bridge will not be obtained and the bridge will always be a bottleneck. Hence, heavy traffic jam is expected at each bridge. In addition, it is expected that there will be increase in traffic accidents/road crashes, and air pollution and serious soil erosion in rainy season.
2. Pollution Control	(1) Air Quality	(a) Is there observation that air pollution emitted from traveling vehicles affects ambient air quality? Does ambient air quality comply with the country's air quality standards? Are any mitigating measures taken? (b) Will project make air quality worsen in case the existing air quality exceeds the air quality standard? Are any mitigating measures taken?	(a) Y (b) N	(a) The urban network will be improved and traffic congestion will be relieved with less emission. (b) Current air quality which is the monitoring data at Juba downtown near Juba port is less than the reference values in Japanese air quality standards.
	(2) Water Quality	(a) Is there a possibility that soil runoff from the bare lands resulting from earthmoving activities, such as cutting and filling will cause water quality degradation in downstream water areas? (b) Is there a possibility that surface runoff from roads will contaminate water sources, such as groundwater? (c) Do effluents from various facilities, such as parking areas/service areas comply with the country's effluent standards and ambient water	(a) Y (b) N (c) Y	(a) River banks near the bridges are to be protected from erosion. (b) There is no well near the project area. (c) Liquid waste from workers' camp is dumped at the official dumping site.

		quality standards? Is there a possibility that the effluents will cause areas not to comply with the country's ambient water quality standards?		
	(3)Waste	(a) Are wastes generated from the project facilities, such as parking areas/service areas, properly treated and disposed of in accordance with the country's regulations?	(a) Y	(a) Solid waste generated from the workers camp is properly dumped at the official dumping site.
	(4)Noise and Vibration	(a) Do noise and vibrations from the vehicle and train traffic comply with the country's standards?	(a) Y	(a) It could become greater than standard during construction in the area facing the road. Monitoring will be implemented and noise prevention sheet is installed if necessary.
3. Natural Environment	(1)Protected Areas	(a) Is the project site located in protected areas designated by the country's laws or international treaties and conventions? Is there a possibility that the project will affect the protected areas?	(a) N	(a) Nature of project site is city area.
	(2)Ecosystem	(a) Does the project site encompass primeval forests, tropical rain forests, ecologically valuable habitats (e.g., coral reefs, mangroves, or tidal flats)?	(a) N	(a) Nature of project site is city area. Ecosystem is far from this area.
	(3)Hydrology	(a) Is there a possibility that alterations of topographic features and installation of structures, such as tunnels will adversely affect surface water and groundwater flows?	(a) N	(a) The project does not requires land modification due to reconstruction of bridges and roads.
4. Social Environment	(1)Resettlement	(a) Is involuntary resettlement caused by project implementation? If involuntary resettlement is caused, are efforts made to minimize the impacts caused by the resettlement?	(a) N	(a) No involuntary resettlement is expected.
	(2)Living and livelihood	(a) Where roads are newly installed, is there a possibility that the project will affect the existing means of transportation and the associated workers? Is there a possibility that the project will cause significant impacts, such as extensive alteration of existing land uses, changes in sources of livelihood, or unemployment? Are adequate measures considered for preventing these impacts? (b) Is there any possibility that the project will adversely affect the living conditions of the inhabitants other than the target population? Are adequate measures considered to reduce the impacts, if necessary? (c) Is there any possibility that diseases, including infectious diseases, such as HIV will be brought due to immigration of workers associated with the project? Are adequate considerations given to public health, if necessary? (d) Is there any possibility that the project will adversely affect road traffic in the surrounding areas (e.g., increase of traffic congestion and traffic accidents)? (e) Is there any possibility that roads will impede the movement of inhabitants? (f) Is there any possibility that structures associated with roads (such as bridges) will cause a sun shading and radio interference?	(a) N (b) Y (c) Y (d) Y (e) N (f) N	(a) Contents of the project is the bridge reconstruction and improvement of existing roads of both sides of bridge will be given within existing ROW which does not make significant environment change. (b) Special consideration and arrangement such as diversion is required for the pedestrian during the project as the number of pedestrian is large. (c) Provision of safety measures and prevention campaigns are planned. (d) In order to mitigate the traffic congestion, simultaneous construction of four bridges is planned to be avoided. (e) Due to the widening the road in 4 lanes and installation of sidewalks the movement of inhabitants will be more free. (f) There will be hardly radio interference during the project due to small size of bridge construction area which will be very limited and momentary.

	(3) Heritage	(a) Is there a possibility that the project will damage the local archaeological, historical, cultural, and religious heritage? Are adequate measures considered to protect these sites in accordance with the country's laws?	(a) N	(a) No cultural heritage exists within the project site.
	(4) Landscape	(a) Is there a possibility that the project will adversely affect the local landscape? Are necessary measures taken?	(a) N	(a) There will be negative impact on landscape which will however be limited and momentary during the project.
	(5) Ethnic Minorities and Indigenous People	(a) Are considerations given to reduce impacts on the culture and lifestyle of ethnic minorities and indigenous peoples?	(a) N	(a) There are no ethnic minorities and indigenous peoples within the project site.
5. Working Environment	(6) Working Environment	(a) Is the project proponent not violating any laws and ordinances associated with the working conditions of the country which the project proponent should observe in the project? (b) Are tangible safety considerations in place for individuals involved in the project, such as the installation of safety equipment which prevents industrial accidents, and management of hazardous materials? (c) Are intangible measures being planned and implemented for individuals involved in the project, such as the establishment of a safety and health program, and safety training (including traffic safety and public health) for workers etc.? (d) Are appropriate measures being taken to ensure that security guards involved in the project not to violate safety of other individuals involved, or local residents?	(a) Y (b) Y (c) Y (d) Y	(a) Compliance with the law is first prioritized policy in Environmental Monitoring Plan. (b) Health and safety for employees and residents are planned properly and secured. Safety Board for workers and pedestrians should be installed to keep safety. Provision of adequate sanitary facilities e.g. washroom and clean water should be installed. (c) Safety education, including how to use safety accessories and how to behave in emergency case, are to be implemented. (d) The safety control person should employed to supervise the safety control and safety guideline.
6. Others	(1) Impacts during construction	(a) Are adequate measures considered to reduce impacts during construction (e.g., noise, vibrations, turbid water, dust, exhaust gases, and wastes)? (b) If construction activities adversely affect the natural environment (ecosystem), are adequate measures considered to reduce impacts? (c) If construction activities adversely affect the social environment, are adequate measures considered to reduce impacts?	(a) Y (b) N (c) N	The following appropriate countermeasures are expected to reduce impacts during construction: - Air pollution: to apply sprinkle water for dust prevention. - Water pollution: to treat a turbid water. - Waste: to dispose construction wastes in the specified disposal site. - Noise: to prevent noise using sound-proof construction equipment. Monthly meeting will be held to monitor the complaints about construction. Based on the meeting, mitigation measures are taken when necessary. (a) Impact to ecosystem is negligible due to the bridge reconstruction and reconstruction of approach roads. (b) Impact can be considered to be

				mitigated and public meeting is continued.
	(2) Monitoring	<p>(a) Does the proponent develop and implement monitoring program for the environmental items that are considered to have potential impacts?</p> <p>(b) What are the items, methods and frequencies of the monitoring program?</p> <p>(c) Does the proponent establish an adequate monitoring framework (organization, personnel, equipment, and adequate budget to sustain the monitoring framework)?</p> <p>(d) Are any regulatory requirements pertaining to the monitoring report system identified, such as the format and frequency of reports from the proponent to the regulatory authorities?</p>	<p>(a) Y</p> <p>(b) Y</p> <p>(c) N</p> <p>(d) Y</p>	<p>(a) The contractor implements monitoring under the supervision of the proponent.</p> <p>(b) Scheduled before, during and after construction for air pollution, noise and vibration, water pollution and social conditions of affected people as indicated in the Environmental Monitoring Plan.</p> <p>(c) Only one specialist is available but without any equipment. However proponent is going to request enough budget to fulfil the requirement of JICA Environmental and Social Considerations Guidelines as much as possible.</p> <p>(d) The contractor shall report the results of monitoring to Ministry of Environment and the Ministry will manage them. Every month the monitoring report is submitted to JICA.</p>

Annex-7: Environmental Monitoring Form

1. Permit and Explanation

Monitoring Items	Actions to be taken
<ul style="list-style-type: none"> ESIA and proposed monitoring plan need to be submitted: Approval from MOE Monitoring shall be carried out according to approved plan 	<ul style="list-style-type: none"> Monitoring result: The result needs to be reported to MOE.

2. Pollution Control

Air Quality

Items	Sampled Value (Average)	Sampled Value (Maximum)	Standard Value	Referred Standard	Sampling Point, Time, Method
Sulphur Dioxides : SO ₂			20-125 (daily)	WHO	<ul style="list-style-type: none"> No. of Sampling: 1 point per bridge Sampling Items: SO₂, NO₂, CO, SPM. Sampling Times: 2 times per year Others: Traffic Volume, Metrological Data
Nitrogen dioxides : NO ₂			40 (yearly)	WHO, Japan	
Carbon monoxide: CO			200 (8 hours)		
Ozone : O ₃			-		
Suspended Particulate Matter : SPM			100 (daily) 200 (hourly)	Japan	
Dust			600	Japan	Physical Observation

Water Quality

Items	Sampled Value (Average)	Sampled Value (Maximum)	Standard Value	Referred Standard	Sampling Point, Time, Method
pH			6.5-8.5	Japan	<ul style="list-style-type: none"> During & After Construction Sampling Point: 4 Sampling Times: 2 times per year Sampling Items: PH, EC, SS.
Electric Conductivity : EC			< 2000µmS/m	Environmental Protection Agency, USA	
Turbidity			< 5 NTU	Japan	
Dissolved Oxygen : DO			> 2	Japan	
Coliform			Not detected		
Oil			< 0.50mg/L	Japan	
SS			50mg/m ³	Japan	

Waste Material

Monitoring Items	Monitoring Point, Time, Method
<ul style="list-style-type: none"> Physical observation of waste materials during the construction: Construction waste material, Deleterious material, Garbage Physical observation of waste materials after the construction 	<ul style="list-style-type: none"> Monitoring of treatment of waste material and report: Time per month

Noise and Vibration

Items	Sampled Value (Average)	Sampled Value (Maximum)	Standard Value	Referred Standard	Monitoring Point, Time, Method
Noise			Day: 70dB Night: 65dB	Japan	<ul style="list-style-type: none"> During and After Construction Monitoring Points: 2 Monitoring Items: Noise and Vibration : Times per monitoring day Monitoring Times: 4 times per year
Vibration			Day: 70dB Night: 65dB	Japan	

3. Natural Environment
Ecosystem

Monitoring Items	Monitoring Point, Time, Method
1) Hydrometeor Physical observation to storm water during rain Condition of storm water discharge	Monitoring of discharge condition at drainage system; 1 time per month

4. Social Environment
Living and Livelihood

Monitoring Items	Monitoring Point, Time, Method
1) During Construction: Pollution status by Air quality, Noise, Waste material to residents 2) During Construction: Monitoring of Road Users and Residents	During the construction: 1 time per month

Existing Social Infrastructure

Monitoring Items	Monitoring Point, Time, Method
1) During Construction: Pollution status by Air quality, Noise, Waste material to residents 2) During Construction: Monitoring of Road Users and Residents	During the construction: 1 time per month

Road Safety

Monitoring Items	Monitoring Point, Time, Method
1) Grasping situation of intersection crossing by school children	During the construction: 1 time per month

Working Environment

Monitoring Items	Monitoring Point, Time, Method
1) Grasping situation of EH&S during the construction	During the construction: 1 time per week

Traffic Accident

Monitoring Items	Monitoring Point, Time, Method
1) Grasping situation of traffic congestion during the construction 2) Grasping situation of traffic accident during the construction	During the construction: 1 time per week

資料-2 TECHNICAL NOTES

Ministry of Transport, Roads and Bridges
Republic of South Sudan

Ministry of Physical Infrastructure, Central Equatoria
Republic of South Sudan

PREPARATORY SURVEY
ON
THE PROJECT FOR CONSTRUCTION
OF
THE BRIDGES IN JUBA CITY
IN THE REPUBLIC OF SOUTH SUDAN

TECHNICAL NOTES

MARCH 2016

JAPAN INTERNATIONAL COOPERATION AGENCY
CTI ENGINEERING INTERNATIONAL CO., LTD.



添2-1

Preparatory Survey on the Project for Construction of the Bridges in Juba City
in the Republic of South Sudan


Technical Notes


JICA Survey Team for the Preparatory Survey (the Survey Team) has confirmed the items described in the attached Technical Notes concluded by the representative of the Ministry of Transport, Roads and Bridges (MTRB) which is the responsible and implementing organization on the Project for Construction of the Bridges in Juba City in the Republic of South Sudan (the Project). Based on the Technical Notes, the Survey Team plans to conduct the basic design for the Project including the project cost estimate through analysis of the site survey findings after obtaining the approval from Japan International Cooperation Agency (JICA).


Juba City, Republic of South Sudan
March, 2016


YUZO, MIZOTA
Chief Consultant
JICA Survey Team




GABRIEL MAKUR
Undersecretary
Ministry of Transport,
Roads and Bridges
Republic of South Sudan


DOMINIC PITIA
Acting Director General
Ministry of Physical Infrastructure
Central Equatoria State


OTEM BONG MIKE
Acting Director General
Ministry of Transport,
Roads and Bridges
Republic of South Sudan
(Witness)



Footpath Design

(1) Pavement Design


Concrete pavement is adopted for the footpath pavement in the view of high durability and commonly-used footpath pavement type in Juba.

(2) Ramp Type Footpath

The design of step for No.1 Bridge (Left side at 0+25m) shall be changed to ramp type foot path at maximum slope of 8% considering universal design.

206

1



添 2-3

Appendix 5 List of Documents

5. List of Documents

Study Title : Preparatory Survey on the Project for Construction of the Lologo Bypass and Bridges in Juba City in the Republic of South Sudan

No	Title	States	Original/ Copy	Issue by	Year
1	Drainage Design Manual, 2006	Documents	Copy	MTR	2006
2	Bridge Design Manual, 2006	Documents	Copy	MTR	2006
3	Geometric Design Manual, 2006	Documents	Copy	MTR	2006
4	Pavement Design Manual, 2006	Documents	Copy	MTR	2006
5	Site Investigation Manual, July 2006	Documents	Copy	MTR	2006
6	Strategic Plan for Road Sector, July 2006	Documents	Copy	MTR	2006
7	Invitation for Bids, May 2007	Documents	Copy	MTR	2007
8	Monitoring and Evaluation, June 2008	Documents	Copy	MTR	2007
9	Training Needs Analysis Report, July 2007	Documents	Copy	MTR	2007
10	HIV AIDS Gender Strategic Plan, August 2007	Documents	Copy	MTR	2007
11	Training Plan, August 2007	Documents	Copy	MTR	2007
12	Human Resource Development, October 2007	Documents	Copy	MTR	2007
13	Standard Bid Documents-Procurement of Small Works, October 2007	Documents	Copy	MTR	2007
14	Transport Sector Policy (Long), October 2007	Documents	Copy	MTR	2007
15	Transport Policy Sector (Abbreviated)	Documents	Copy	MTR	2007
16	Environmental Guidelines - Roads & Bridges, Nov 2007	Documents	Copy	MTR	2007
17	Environmental Guidelines - Road Transport & Safety, Nov 2007	Documents	Copy	MTR	2007
18	Environmental Guidelines - Air, River and Railways, Nov 2007	Documents	Copy	MTR	2007
19	MTR Standard Technical Specifications	Documents	Copy	MTR	2006
20	Land Act 2009	Documents	Copy	RSS	2009
21	National Environmental Policy	Documents	Copy	MOE	2012/3
22	Draft Land Policy	Documents	Copy	South Sudan Land Commission, RSS	2013/2
23	Landmine/ERW Threat Map, Juba- Kayam Road as of march 2013	Documents	Copy	UNMAS	2013/3
24	Environmental Protection Bill,2011	Documents	Copy	RSS	2010
25	Proposed Fiscal Year 2013/14 Budget, Directorate of Roads and Bridges Ministry of Physical Infrastructure, Directorate of Roads and Bridges, CES/JUBA	Documents	Copy	MOPI	2013
26	MOPI DRB CES Budget Request 2013/14	Documents	Copy	MOPI,,DRB	2013
27	National Budget Plan Financial Year 2012/13	Documents	Copy	MFEP	2012/6
28	Master Plan Lologo North	Documents	Copy	MOPI	2012
29	List of land owner	Documents	Copy	Lologo	2013

Remark :

RSS : Republic of South Sudan

MTR : Ministry of Transport and Road (現在 MRB)

MRB : Ministry of Roads and Bridges

MOPI : Ministry of Physical Infrastructure

CES : Central Equatoria States

Appendix 6 Preparatory Design Drawings



MINISTRY OF TRANSPORT, ROADS AND BRIDGES
REPUBLIC OF SOUTH SUDAN

THE PROJECT FOR CONSTRUCTION OF THE BRIDGES
IN JUBA CITY IN THE REPUBLIC OF SOUTH SUDAN

DRAWINGS

MARCH 2016




JAPAN INTERNATIONAL COOPERATION AGENCY


CTI ENGINEERING INTERNATIONAL CO., LTD.

DRAWING LIST

DRAWING TITLE	SHEET NO.	No. of Sheets	DRAWING TITLE	SHEET NO.	No. of Sheets
GENERAL			BRIDGE NO.7		
1. LOCATION MAP	GN - 01	1	25. PLAN	CB7 - 01	1
2. GENERAL NOTES	GN - 02 ~ 04	3	26. PROFILE	CB7 - 02	1
3. PROJECT SITE DEVELOPMENT PLAN	GN - 05	1	27. TYPICAL CROSS SECTION	CB7 - 03	1
4. HORIZONTAL ALIGNMENT	GN - 06 ~ 07	2	28. CROSS SECTIONS	CB7 - 04 ~ 05	2
BRIDGE NO.1			29. JOINT INSTALLATION LAYOUT	CB7 - 06	1
5. PLAN	CB1 - 01	1	30. FRONT VIEW OF RETAINING WALL	CB7 - 07 ~ 08	2
6. PROFILE	CB1 - 02	1	31. GENERAL VIEW OF BRIDGE	CB7 - 09	1
7. TYPICAL CROSS SECTION	CB1 - 03	1	32. DECK AND GIRDER LAYOUT	CB7 - 10	1
8. CROSS SECTIONS	CB1 - 04	1	33. DETAIL OF ABUTMENT A1	CB7 - 11	1
9. JOINT INSTALLATION LAYOUT	CB1 - 05	1	34. DETAIL OF ABUTMENT A2	CB7 - 12	1
10. FRONT VIEW OF RETAINING WALL	CB1 - 06	1	BRIDGE NO.10		
11. GENERAL VIEW OF BRIDGE	CB1 - 07	1	35. PLAN	CB10 - 01	1
12. DECK AND GIRDER LAYOUT	CB1 - 08 ~ 09	2	36. PROFILE	CB10 - 02	1
13. DETAIL OF ABUTMENT A1	CB1 - 10	1	37. TYPICAL CROSS SECTION	CB10 - 03	1
14. DETAIL OF ABUTMENT A2	CB1 - 11	1	38. CROSS SECTIONS	CB10 - 04 ~ 05	2
BRIDGE NO.4			39. JOINT INSTALLATION LAYOUT	CB10 - 06	1
15. PLAN	CB4 - 01	1	40. FRONT VIEW OF RETAINING WALL	CB10 - 07	1
16. PROFILE	CB4 - 02	1	41. GENERAL VIEW OF BRIDGE	CB10 - 08	1
17. TYPICAL CROSS SECTION	CB4 - 03	1	42. DECK AND GIRDER LAYOUT	CB10 - 09	1
18. CROSS SECTIONS	CB4 - 04 ~ 05	2	43. DETAIL OF ABUTMENT A1	CB10 - 10	1
19. JOINT INSTALLATION LAYOUT	CB4 - 06	1	44. DETAIL OF ABUTMENT A2	CB10 - 11	1
20. FRONT VIEW OF RETAINING WALL	CB4 - 07 ~ 08	2	BRIDGE FROM NO.1 TO NO.10		
21. GENERAL VIEW OF BRIDGE	CB4 - 09	1	45. CONCRETE PAVEMENT	CP - 01 ~ 02	2
22. DECK AND GIRDER LAYOUT	CB4 - 10	1	46. DETAIL OF STRUCTURES	CP - 03 ~ 11	9
23. DETAIL OF ABUTMENT A1	CB4 - 11	1			
24. DETAIL OF ABUTMENT A2	CB4 - 12	1			




 <p>REPUBLIC OF SOUTH SUDAN</p>	Approved by	<p>THE PROJECT FOR CONSTRUCTION OF THE BRIDGES IN JUBA CITY IN THE REPUBLIC OF SOUTH SUDAN</p>  <p>JAPAN INTERNATIONAL COOPERATION AGENCY</p> <p>CTI ENGINEERING INTERNATIONAL CO., LTD.</p>	Designed		TITLE:	SCALE	DWG. NO.
	Project Manager		Checked		PROJECT SITE DEVELOPMENT PLAN	1:20,000	
			Approved			DATE	SHT. NO.



<p>REPUBLIC OF SOUTH SUDAN</p>	Approved by	<p>THE PROJECT FOR CONSTRUCTION OF THE BRIDGES IN JUBA CITY IN THE REPUBLIC OF SOUTH SUDAN</p>	<p>JAPAN INTERNATIONAL COOPERATION AGENCY</p> <p>CTI ENGINEERING INTERNATIONAL CO., LTD.</p>	Designed	<p>TITLE</p> <p>SITE DEVELOPMENT PLAN (BRIDGE NO.1)</p>	SCALE	DWG. NO.	
	Project Manager			Checked		1:500	DATE	SHT. NO.
				Approved			CS1-01	

BRIDGE (NO. 1)




EMBANKMENT SECTION

NOTES : Expansion joints of walkway are installed at 3.0m interval.


	REPUBLIC OF SOUTH SUDAN	Approved by	THE PROJECT FOR CONSTRUCTION OF THE BRIDGES IN JUBA CITY IN THE REPUBLIC OF SOUTH SUDAN	 JAPAN INTERNATIONAL COOPERATION AGENCY CTI ENGINEERING INTERNATIONAL CO., LTD.	Designed	TITLE:	SCALE	DWG NO.
		Project Manager			Checked		1:200	
					Approved		TYPICAL CROSS SECTION BRIDGE NO.1	
								CB1 - 03

GENERAL VIEW OF BRIDGE NO. 1


LONGITUDINAL SECTION S=1:200




Cross Section S=1:100




Front View S=1:100 (A1)



PLAN S=1:200



	MINISTRY OF TRANSPORT, ROADS AND BRIDGES (MTRB) REPUBLIC OF SOUTH SUDAN	Approved by Project Manager	THE PROJECT FOR CONSTRUCTION OF BRIDGES IN JUBA CITY (IN THE REPUBLIC OF SOUTH SUDAN)	JAPAN INTERNATIONAL COOPERATION AGENCY CTI ENGINEERING INTERNATIONAL CO., LTD.	Designer: _____ Checked: _____ Approved: _____	TITLE GENERAL VIEW OF BRIDGE NO.1	SCALE: S=200 DATE: _____ DRAW NO: _____
	GENERAL VIEW OF BRIDGE NO.1						
	S=200 DATE: _____ DRAW NO: _____						



REPUBLIC OF SOUTH SUDAN

Approved by
Project Manager

THE PROJECT FOR CONSTRUCTION OF
THE BRIDGES IN JUBA CITY
IN THE REPUBLIC OF SOUTH SUDAN




JAPAN INTERNATIONAL COOPERATION AGENCY
CTI ENGINEERING INTERNATIONAL CO., LTD.

Designed	
Checked	
Approved	

TITLE	SITE DEVELOPMENT PLAN (BRIDGE NO.4)
-------	--

SCALE	DWG. NO.
1:800	
DATE	SHT. NO.
	084-01

BRIDGE (NO. 4)




EMBANKMENT SECTION

NOTES : Expansion joints of walkway are installed at 3.0m interval.


	REPUBLIC OF SOUTH SUDAN	Approved by	THE PROJECT FOR CONSTRUCTION OF THE BRIDGES IN JUBA CITY IN THE REPUBLIC OF SOUTH SUDAN	 JAPAN INTERNATIONAL COOPERATION AGENCY CTI ENGINEERING INTERNATIONAL CO., LTD.	Designed	TITLE:	SCALE	DWG NO.
		Project Manager			Checked		1:200	
					Approved		DATE	SHT. NO.
						TYPICAL CROSS SECTION BRIDGE NO.4		CB4-03

GENERAL VIEW OF BRIDGE NO. 4


LONGITUDINAL SECTION S=1:200




Cross Section S=1:100



Front View S=1:100 (A1)



PLAN S=1:200



MINISTRY OF TRANSPORT, ROADS
AND BRIDGES (MTRB)
REPUBLIC OF SOUTH SUDAN

Approved by
Project Manager

THE PROJECT FOR CONSTRUCTION
OF BRIDGES IN JUBA CITY
IN THE REPUBLIC OF SOUTH SUDAN




JAPAN INTERNATIONAL COOPERATION AGENCY
CTI ENGINEERING INTERNATIONAL CO., LTD.

Designed
Checked
Approved


TITLE
**GENERAL VIEW OF
BRIDGE NO.4**

SCALE: 1:200
DATE: SHEET NO:
JOB NO.



 <p>REPUBLIC OF SOUTH SUDAN</p>	Approved by Project Manager	<p>THE PROJECT FOR CONSTRUCTION OF THE BRIDGES IN JUBA CITY IN THE REPUBLIC OF SOUTH SUDAN</p>	 <p>JAPAN INTERNATIONAL COOPERATION AGENCY</p> <p>CTI ENGINEERING INTERNATIONAL CO., LTD.</p>	Designed	TITLE	SCALE	DWG. NO.		
					Checked	SITE DEVELOPMENT PLAN (BRIDGE NO.7)	1:500	DATE	SHEET NO.
					Approved				081-01

BRIDGE (NO. 7)




EMBANKMENT SECTION

NOTES : Expansion joints of walkway are installed at 3.0m interval.


	REPUBLIC OF SOUTH SUDAN	Approved by	THE PROJECT FOR CONSTRUCTION OF THE BRIDGES IN JUBA CITY IN THE REPUBLIC OF SOUTH SUDAN	 JAPAN INTERNATIONAL COOPERATION AGENCY CTI ENGINEERING INTERNATIONAL CO., LTD.	Designed	TITLE:	SCALE	DWG NO.
		Project Manager			Checked		1:200	
					Approved		DATE	SHT. NO.
						TYPICAL CROSS SECTION BRIDGE NO.7		CB7-03

GENERAL VIEW OF BRIDGE NO. 7


LONGITUDINAL SECTION S=1:200




Cross Section S=1:100



Front View S=1:100 (A1)



PLAN S=1:200



MINISTRY OF TRANSPORT, ROADS AND BRIDGES (MTRB)
REPUBLIC OF SOUTH SUDAN

Approved by
Project Manager

THE PROJECT FOR CONSTRUCTION OF BRIDGES IN JUBA CITY IN THE REPUBLIC OF SOUTH SUDAN




JAPAN INTERNATIONAL COOPERATION AGENCY
CTI ENGINEERING INTERNATIONAL CO., LTD.

Designed
Checked
Approved


TITLE
GENERAL VIEW OF BRIDGE NO.7

SCALE 1:200	DRAWN BY M.C.
RATE	SHEET NO
	EXP. NO



 REPUBLIC OF SOUTH SUDAN	Approved by:	THE PROJECT FOR CONSTRUCTION OF THE BRIDGES IN JUBA CITY IN THE REPUBLIC OF SOUTH SUDAN	 JAPAN INTERNATIONAL COOPERATION AGENCY CTI ENGINEERING INTERNATIONAL CO., LTD.	Designed:	TITLE: SITE DEVELOPMENT PLAN (BRIDGE NO.10)	SCALE: DWG. NO.
	Project Manager:			Checked:		DATE: SHIT. NO.
				Approved:	CB10-01	CB10-01

BRIDGE (NO. 10)




EMBANKMENT SECTION

NOTES : Expansion joints of walkway are installed at 3.0m interval.


	REPUBLIC OF SOUTH SUDAN	Approved by	THE PROJECT FOR CONSTRUCTION OF THE BRIDGES IN JUBA CITY IN THE REPUBLIC OF SOUTH SUDAN	 JAPAN INTERNATIONAL COOPERATION AGENCY CTI ENGINEERING INTERNATIONAL CO., LTD.	Designed	TITLE:	SCALE	DWG NO.
		Project Manager			Checked		1:200	SHT NO.
					Approved			DATE
						TYPICAL CROSS SECTION BRIDGE NO. 10		

GENERAL VIEW OF BRIDGE NO. 10


LONGITUDINAL SECTION S=1:200




Cross Section S=1:100



Front View S=1:100 (A1)



PLAN S=1:200



A 6 - 15

	MINISTRY OF TRANSPORT, ROADS AND BRIDGES (MTRB) REPUBLIC OF SOUTH SUDAN	Approved by Project Manager	THE PROJECT FOR CONSTRUCTION OF BRIDGES IN JUBA CITY IN THE REPUBLIC OF SOUTH SUDAN		JAPAN INTERNATIONAL COOPERATION AGENCY CTI ENGINEERING INTERNATIONAL CO., LTD.	Designed Checked Approved	TITLE GENERAL VIEW OF BRIDGE NO.10	SCALE: 1:200 DATE 15/09/08	DRAW NO. SHEET NO. 15/09/08
	GENERAL VIEW OF BRIDGE NO.10								