Supporting Report 14

Environmental and Social Conditions

Table of Contents

| CHAPTER 14 ENVIRONMENTAL AND SOCIAL CONDITIONS | 14-1 |
|---|-------|
| 14.5 Scoping | 14-1 |
| 14.7 ESTIMATION OF POTENTIAL IMPACTS AT IEE LEVEL | 14-13 |
| 14.8 RECOMMENDED MITIGATION MEASURES | 14-16 |
| 14.9 | 14-27 |
| 14.9.2 Environmental Monitoring Plan (JICA Environmental Monitoring Form) | 14-28 |

List of Tables

| Table 14.5.1 Scoping Results for Water Supply Project for Stage V Conveyance Pipeline Project 14-1 |
|--|
| Table 14.5.2 Scoping Results for Stage V Transmission Pipeline Project in the City |
| Table 14.5.3 Scoping Results for Water Supply Project for 110 Villages Distribution Pipelines 14-6 |
| Table 14.5.4 Scoping Results for 110 Villages Sewerage Component Project (Lateral and House |
| Connection) 14-8 |
| Table 14.5.5 Scoping Results for UFW Reduction Project |
| Table 14.7.1 Potential Adverse Impacts by Stage V Conveyance Pipeline Project |
| Table 14.7.2 Potential Adverse Impacts by Stage V Transmission Pipeline in the City 14-13 |
| Table 14.7.3 Potential Adverse Impacts by Water Supply Project for 110 Villages |
| Table 14.7.4 Potential Adverse Impacts by 110 Villages Sewerage Component Project 14-15 |
| Table 14.8.1 Recommended Mitigation Measures for Stage V Conveyance Pipeline Project 14-16 |
| Table 14.8.2 Recommended Mitigation Measures for Stage V Transmission Pipeline Project 14-18 |
| Table 14.8.3 Recommended Mitigation Measures for UFW Reduction Project |
| Table 14.8.4 Recommended Mitigation Measures for 110 Villages Sewerage Component Project 14- |
| 22 |
| Table 14.8.5 Recommended Mitigation Measures for UFW Reduction Project |

Chapter 14 Environmental and Social Conditions

14.5 Scoping

(1) Stage V Conveyance Pipeline Project

The scoping results of the project are shown in Table 14.5.1. The project site is the existing BWSSB's facility areas of pipeline roads.

Table 14.5.1 Scoping Results for Water Supply Project for Stage V Conveyance Pipeline Project

| Type No. | NT. | Elements to | Rating | | D 6 D 1 d |
|-----------------------------|-----|--|--------|-------|--|
| | No. | be Assessed | Const. | Oper. | Reason for Evaluation |
| | 1 | Protected Area | D | D | The project site and surrounding area is not located in any national parks or nature reserves. |
| | 2 | Ecosystem | D | D | Most of the project sites are located in the existing developed areas of BWSSB's pipeline road. Only some shrubs and grasses are identified. |
| Natural Environ- ment | 3 | Hydrology | D | D | At construction stage: The proposed pipeline crosses river stream of Hulluhalla and Shimsha rivers. However, the construction will be carried out at dry season when the water level is low and may cause less impact on the river flow. At operation stage: The completed structure will change the river flow locally at the crossing points of the rivers. However, the overall flow regime will be recovered at the downstream. |
| | | Topography / Geology | D | D | The project does not include large scaled excavation works. |
| | 5 | Resettlement / Land Issue | D | D | The project site is the existing BWSSB's facility area of pipeline road where no residential houses exists. |
| | 6 | Poverty | D | D | The project is a part of the construction work of the Stage V water supply scheme and has less direct relation to the future tariff system. |
| | 7 | Ethic Minor- ity | D | D | There are neither ethnic minorities nor indigenous people at the project sites. |
| Social En- | 8 | Employment, sustenance and regional economy | B+ | D | The construction works will contribute to employment local labors which may cause positive impact on local economy. |
| vironment | 9 | Land Use / Regional Re- source | D | D | The construction is carried out within the existing BWSSB's facility area, which may not cause land use change. |
| | 10 | Water Use | D | D | The project is a part of the construction work of the Stage V water supply scheme and has less direct relation to the future tariff system. |
| | 11 | Social Infra- structure / Service | D | D | The proposed pipeline crosses several village roads. However, the current traffic at the project site is small compared to the urban area of BBMP. |
| | 12 | Local society for decision making | D | D | The project is to implement a public works by the government which aim to bring public benefit and will not affect local society. |

| _ | | Elements to | Ratir | ıg | D 6 D 1 6 | |
|-----------|-----|---|--------|-------|---|--|
| Type | No. | be Assessed | Const. | Oper. | Reason for Evaluation | |
| | 13 | Unbalance of damages and benefits | D | D | The project will not bring unbalance damage and benefit. | |
| | 14 | Local Conflicts of Interests | D | D | The project does not supply water to specific people or structure, and it will not bring local conflicts. | |
| | 15 | Heritage or Cultural Assets | D | D | The project is implemented at the existing BWSSB's facility area of pipeline road where no historical and cultural assets exists. | |
| | 16 | Landscape | D | D | The laying of water pipelines will be carried out at existing BWSSB's pipeline road where existing CWSS pipelines are exposed. | |
| | 17 | Gender | D | D | The project does not relate to the issues of gender. | |
| | 18 | Right of Children | D | D | The project is not related to the issue of right of children. Child labor is prohibited for implementation of the project by compliance with national laws or international guidelines. | |
| | 19 | Infectious Diseases (e.g. HIV / AIDS) | D | D | The scale of the construction works is small compared to overall stage V project. | |
| | 20 | Occupational Health and Safety | В- | D | At Construction stage: Appropriate care should be taken for the working environment of the construction workers. At Operation stage: There will be no operation works which increase the risks for operation staffs. | |
| | 21 | Air Pollution | В- | D | The construction vehicles and equipment at construction stage will generate dust. | |
| | 22 | Water Pollu- tion | D | D | At Construction stage: Turbid water will be generated at the crossing points of the rivers by the construction works. However, the construction is temporary and local scale. At Operation stage: The operation works does not generate water pollution. | |
| Pollution | 23 | Waste | В- | D | During Construction stage: Construction debris, excavation soil and the garbage at construction camps will be generated. At Operation stage: The operation works will not generate waste. | |
| | 24 | Soil Contami- nation | D | D | The hazardous matter causing soil contamination will not be generated. | |
| | 25 | Noise / Vibration | D | D | During Construction stage: The construction work is carried out existing public roads where surrounding traffic noise is large. At Operation stage: The operation works will not use equipment which will generate noise. | |
| | 26 | Ground Subsidence | D | D | The project does not extract groundwater. | |

| Type No. | Elements to | Rating | | Reason for Evaluation | |
|----------|-------------|-------------------|-------|-----------------------|--|
| | be Assessed | Const. | Oper. | Reason for Evaluation | |
| | 27 | Odour | D | D | The project does not include the activities which generates odour. |
| | 28 | Sediments | D | D | The construction works is not carried out at rivers. |
| Others | 29 | Accident | В- | D | During Construction: Care should be taken for the accidents which are estimated at the construction works. At Operation: The operation works which cause significant accidents will not be generated. |
| | 30 | Climate Change | D | D | The project does not use equipment which use large amount of electricity or chemical substances of GHGs. |

Notes:

A+/-: Significant positive/negative impact is expected.

B+/-: Positive/negative impact is expected to some extent.

C+/-: Extent of positive/negative impact is unknown. (A further examination is needed, and the impact could be clarified as the study progresses)

D: No impact is expected. Source: JICA Survey Team

(1) Branch Feeding Pipes (Expansion of City Trunk Mains) to Share Water to Core/ULBs The scoping results of the project are shown in Table 14.5.2. The project site is the existing public roads in Core / ULB areas of BBMP.

Table 14.5.2 Scoping Results for Stage V Transmission Pipeline Project in the City

| | | | | | Ι υ | |
|-----------------------------|------|--|--------|-------|---|--|
| Туре | No. | Elements to | Ratin | ıg | Reason for Evaluation | |
| Турс | 110. | be Assessed | Const. | Oper. | Reason for Evaluation | |
| | 1 | Protected Area | D | D | The project site and surrounding area is not located in any national parks or nature reserves. | |
| | 2 | Ecosystem | D | D | Most of the project sites are located in the existing public roads in Core/ULB areas of BBMP. | |
| Natural Environ- ment | 3 | Hydrology | D | D | At construction stage: There are no construction works at crossing points of rivers. At operation stage: There are no construction works at crossing points of rivers. | |
| | 4 | Topography / Geology | D | D | The project does not include large scaled excavation works. | |
| | 5 | Resettlement / Land Issue | D | D | The project site is the existing pubic road areass. | |
| Social En- | 6 | Poverty | D | D | The project is a part of the construction work of the Stage V water supply scheme and has less direct relation to the future tariff system. | |
| vironment | 7 | Ethic Minor- ity | D | D | There are neither ethnic minorities nor indigenous people at the project sites. | |
| | 8 | Employment, sustenance and regional economy | B+ | D | The construction works will contribute to employment local labors which may cause positive impact on local economy. | |

| 9 10 11 | Land Use / Regional Resource Water Use Social Infrastructure / Service Local society for decision | D D B- | Oper. D D | Reason for Evaluation The construction is carried out within the existing public road areas which may not cause land use change. The project is a part of the construction work of the Stage V water supply scheme and has less direct relation to the future tariff system. |
|---------------|--|---|---|--|
| 10 | Regional Resource Water Use Social Infrastructure / Service Local society for decision | D | D | areas which may not cause land use change. The project is a part of the construction work of the Stage V water supply scheme and has less direct relation to the future tariff system. |
| 11 12 | Social Infra- structure / Service Local society for decision | | | water supply scheme and has less direct relation to the future tariff system. |
| 12 | Service Local society for decision | В- | D | 1. C |
| | for decision | | | At Construction stage: The construction works at existing public road areas in Core/ULBs may affect surrounding traffic and underground utilities. |
| 12 | making | D | D | The project is to implement a public works by the government which aim to bring public benefit and will not affect local society. |
| 13 | Unbalance of damages and benefits | D | D | The project will not bring unbalance damage and benefit. |
| 14 | Local Conflicts of Interests | D | D | The project does not supply water to specific people or structure, and it will not bring local conflicts. |
| 15 | Heritage or Cultural Assets | D | D | The project is implemented at the existing public road areas where no historical and cultural assets exists. |
| 16 | Landscape | D | D | The laying of water pipelines will be carried out at existing BWSSB's pipeline road where existing CWSS pipelines are exposed. |
| 17 | Gender | D | D | The project does not relate to the issues of gender. |
| 18 | Right of Children | D | D | The project is not related to the issue of right of children. Child labor is prohibited for implementation of the project by compliance with national laws or international guidelines. |
| 19 | Infectious Diseases (e.g. HIV / AIDS) | D | D | The scale of the construction works is small compared to overall stage V project. |
| 20 | Occupational Health and Safety | В- | D | At Construction stage: Appropriate care should be taken for the working environment of the construction workers. At Operation stage: There will be no operation works which increase the risks for operation staffs. |
| 21 | Air Pollution | В- | D | The construction vehicles and equipment at construction stage will generate dust. |
| 22 | Water Pollution | D | D | At Construction stage: Turbid water will be generated at the crossing points of the rivers by the construction works. However, the construction is temporary and local scale.l At Operation stage: The operation works does not generate water pollution. |
| 2 | 20 | Diseases (e.g. HIV / AIDS) Occupational Health and Safety Air Pollution Water Pollu- | Diseases (e.g. Diseases (e.g. HIV / AIDS) Occupational Health and Safety B- Air Pollution B- | D Diseases (e.g. HIV / AIDS) Occupational Health and Safety Air Pollution B- D Water Pollu- D D |

| Type | No. | Elements to | Ratir | ıg | Reason for Evaluation |
|--------|-----|-------------------------|--------|-------|---|
| Туре | NO. | be Assessed | Const. | Oper. | Keason for Evaluation |
| | 23 | Waste | В- | D | During Construction stage: Construction debris, excavation soil and the garbage at construction camps will be generated. At Operation stage: The operation works will not generate waste. |
| | 24 | Soil Contami- nation | D | D | The hazardous matter causing soil contamination will not be generated. |
| | 25 | Noise / Vibration | D | D | During Construction stage: Noise will be generated temporarily by the construction works. However, there are sparse residential houses around the project site. At Operation stage: The operation works will not use equipment which will generate noise. |
| | 26 | Ground Sub- sidence | D | D | The project does not extract groundwater. |
| | 27 | Odour | D | D | The project does not include the activities which generates odour. |
| | 28 | Sediments | D | D | The scale of the pipe support bridges is not large and will not affect the sediments of the river bed. |
| Others | 29 | Accident | В- | D | During Construction: Care should be taken for the accidents which are estimated at the construction works. At Operation: The operation works which cause significant accidents will not be generated. |
| | 30 | Climate Change | D | D | The project does not use equipment which use large amount of electricity or chemical substances of GHGs. |

Notes:

A+/-: Significant positive/negative impact is expected.

B+/-: Positive/negative impact is expected to some extent.

C+/-: Extent of positive/negative impact is unknown. (A further examination is needed, and the impact could be clarified as the study progresses)

D: No impact is expected. Source: JICA Survey Team

(2) 110 Villages Water Supply Project (Distribution Pipeline and Service Connections; and Feeder Pipes between GLRs and OHTs, OHTs and Pumping facilities)

The scoping results for the 110 villages water supply project (distribution pipeline and service connections) is shown in Table 14.5.3. The environmental and social elements of poverty, social infrastructure / service, infectious diseases, occupational health and safety, air pollution (dust), waste, noise and accident are to be assessed for IEE.

Table 14.5.3 Scoping Results for Water Supply Project for 110 Villages Distribution Pipelines

| Type No. | | Elements to be Assessed | Rating | | D 0 D 1 1 |
|-----------------------------|-----|--|--------|-------|--|
| | No. | | Const. | Oper. | Reason for Evaluation |
| | 1 | Protected Area | D | D | The project site and surrounding area is not located in any national parks or nature reserves. |
| | 2 | Ecosystem | D | D | Most of the project sites are located in the existing built-up area of BBMP |
| Natural Environ- ment | 3 | Hydrology | D | D | At construction stage: The construction works of laying water pipes are implemented at existing public road areas and not at rivers. At operation stage: The future operation works will be implemented at public road areas and not at rivers. |
| | 4 | Topography / Geology | D | D | The project does not include large scaled excavation works. |
| | 5 | Resettlement / Land Issue | D | D | The project sites does not include residential area nor compensation problems since the project sites are all public lands, not private lands. |
| | 6 | Poverty | D | B- | At Operation stage: The increase of water tariff may affect the household economy of low income level. |
| | 7 | Ethic Minor- ity | D | D | There are no ethnic minorities nor indigenous people at the project sites. |
| | 8 | Employment, sustenance and regional economy | B+ | D | At construction stage: An opportunity for employment of local residents is expected by the construction works and may contribute to local economy. |
| | 9 | Land Use / Regional Re- source | D | D | The project sites at existing public road areas and the vacant area in the built-up area will not affect the local land use nor regional resources. |
| | 10 | Water Use | D | D | The project does not relate to water use. |
| Social Environment | 11 | Social Infra- structure / Service | В- | D | At construction stage: The construction works of the water pipelines at road areas may affect the traffic flow and existing underground utilities. At Operation stage: The operation works does not interfere the road areas. |
| | 12 | Local society for decision making | D | D | The project is to implement a public works by the government which aim to bring public benefit and will not affect local society. |
| | 13 | Unbalance of damages and benefits | D | D | The project will not bring unbalance damage and benefit. |
| | 14 | Local Conflicts of Interests | D | D | The project does not supply water to specific people or structure, and it will not bring local conflicts. |
| | 15 | Heritage or Cultural Assets | D | D | The project is implemented at public road areas where the historical and cultural assets are reserved separately from roads. |
| | 16 | Landscape | D | D | The replacement of water pipelines will be laid under existing public road areas. |

| | | Elements to | Rating | | |
|-----------|-----|---|--------|-------|--|
| Type | No. | be Assessed | Const. | Oper. | Reason for Evaluation |
| | 17 | Gender | D | D | The project does not relate to the issues of gender. |
| | 18 | Right of Chil- dren | D | D | The project is not related to the issue of right of children. Child labor is prohibited for implementation of the project by compliance with national laws or international guidelines. |
| | 19 | Infectious Diseases (e.g. HIV / AIDS) | В- | D | The inflow of construction workers may generate or expand infection diseases. |
| | | | | | At Construction stage: |
| | 20 | Occupational Health and Safety | В- | D | Appropriate care should be taken for the working environment of the construction workers. At Operation stage: There will be no operation works which increase the risks for operation staffs. |
| | 21 | Air Pollution | В- | D | The construction vehicles and equipment at construction stage will generate dust. |
| | 22 | Water Pollu- tion | D | D | At Construction stage: Turbid water will not be generated by the generation of underground water at excavation works due to the low table of the groundwater. At Operation stage: |
| | | | | | The operation works does not generate water pollution. |
| | 23 | Waste | В- | D | During Construction stage: Construction debris, excavation soil and the garbage at construction camps will be generated. At Operation stage: The operation works will not generate waste. |
| Pollution | 24 | Soil Contami- nation | D | D | The hazardous matter causing soil contamination will not be generated. |
| | 25 | Noise / Vibra- tion | B- | D | During Construction stage: Noise will be generated by the operation of construction vehicles and equipment. At Operation stage: The operation works will not use equipment which will generate noise. |
| | 26 | Ground Sub- sidence | D | D | The project does not extract groundwater. |
| | 27 | Odour | D | D | The project does not include the activities which generates odour. |
| | 28 | Sediments | D | D | The scale of the pipe support bridges is not large and will not affect the sediments of the river bed. |
| Others | 29 | Accident | В- | D | During Construction: Care should be taken for the accidents which are estimated at the construction works. At Operation: The operation works which cause significant accidents will not be generated. |
| | 30 | Climate Change | D | D | The project does not use equipment which use large amount of electricity or chemical substances of GHGs. |

Notes: A+/-: Significant positive/negative impact is expected.

B+/-: Positive/negative impact is expected to some extent.

C+/-: Extent of positive/negative impact is unknown. (A further examination is needed, and the impact could be clarified as the study progresses)

D: No impact is expected.

Source: JICA Survey Team

(3) 110 Villages Sewerage Component Project (Lateral Sewers and House Connections)

The scoping results for the 110 village sewerage component project for lateral sewers and house connection is shown in Table 14.5.4. The environmental and social elements of poverty, social infrastructure / service, infectious diseases, occupational health and safety, air pollution (dust), waste, noise and accident are to be assessed for IEE.

Table 14.5.4 Scoping Results for 110 Villages Sewerage Component Project (Lateral and House Connection)

| Thurs | NI. | Elements to be Assessed | Rating | | December Fundantion |
|-----------------------------|-----|--|--------|-------|--|
| Туре | No. | | Const. | Oper. | Reason for Evaluation |
| | 1 | Protected Area | D | D | The project site and surrounding area is not located in any national parks or nature reserves. |
| | 2 | Ecosystem | D | D | Most of the project sites are located in the existing built-up area of BBMP |
| Natural Environ- ment | 3 | Hydrology | D | D | At construction stage: The construction works of laying lateral sewers and house connection are implemented at existing public road areas and not at rivers. At operation stage: The future operation works will be implemented at public road areas and not at rivers. |
| | 4 | Topography / Geology | D | D | The project does not include large scaled excavation works. |
| | 5 | Resettlement / Land Issue | D | D | The project sites does not include residential area nor compensation problems since the project sites to will be implemented at public lands, not private lands. |
| | 6 | Poverty | D | В- | At Operation stage: The increase of sewerage tariff may affect the household economy of low income level. |
| Social En- | 7 | Ethic Minor- ity | D | D | There are no ethnic minorities nor indigenous people at the project sites. |
| vironment | 8 | Employment, sustenance and regional economy | B+ | D | At construction stage: An opportunity for employment of local residents is expected by the construction works and may contribute to local economy. |
| | 9 | Land Use / Regional Re- source | D | D | The project sites at the BWSSB's facility areas, public road areas and the vacant area in the built-up area will not affect the local land use nor regional resources. |
| | 10 | Water Use | D | D | The downstream water use and maintenance flow in Cauvery river will be secured. |

| | | Elements 4e | Rating | | Supporting Report |
|-----------|--------------------|---|--------|-----------------------|---|
| Туре | No. Lichients to | Const. | Oper. | Reason for Evaluation | |
| | 11 | Social Infra- structure / Service | В- | D | At construction stage: The construction works of the lateral pipes at road areas may affect the traffic flow and existing underground utilities. At Operation stage: The operation works does not interfere the road areas. |
| | 12 | Local society for decision making | D | D | The project is to implement a public works by the government which aim to bring public benefit and will not affect local society. |
| | 13 | Unbalance of damages and benefits | D | D | The project will not bring unbalance damage and benefit. |
| | 14 | Local Conflicts of Interests | D | D | The project does not supply water to specific people or structure, and it will not bring local conflicts. |
| | 15 | Heritage or Cultural As- sets | D | D | The project is implemented at public road areas where the historical and cultural assets are reserved separately from roads. |
| | 16 | Landscape | D | D | The replacement of water pipelines will be laid under existing public road areas. |
| | 17 | Gender | D | D | The project does not relate to the issues of gender. |
| | 18 | Right of Children | D | D | The project is not related to the issue of right of children. Child labor will be prohibited for implementation of the project by compliance with national laws or international guidelines. |
| | 19 | Infectious Diseases (e.g. HIV / AIDS) | B- | D | The inflow of construction workers may generate or expand infection diseases. |
| | 20 | Occupational Health and Safety | B- | D | At Construction stage: Appropriate care should be taken for the working environment of the construction workers. At Operation stage: There will be no operation works which increase the risks of operation staffs. |
| | 21 | Air Pollution | В- | D | The construction vehicles and equipment at construction stage will generate dust. |
| Pollution | 22 | Water Pollution | D | D | At Construction stage: Turbid water will not be generated by the generation of underground water at excavation works due to the low table of the groundwater. At Operation stage: The operation works does not generate water pollution. |
| | 23 | Waste | В- | D | During Construction stage: Construction debris, excavation soil and the garbage at construction camps will be generated. At Operation stage: The operation works will not generate waste. |
| | 24 | Soil Contami- nation | D | D | The hazardous matter causing soil contamination will not be generated. |

| Trunc | No. | Elements to | Rating | | Reason for Evaluation | |
|--------|-----|-------------------|--------|-------|---|--|
| Type | NO. | be Assessed | Const. | Oper. | Reason for Evaluation | |
| | 25 | Noise / Vibration | В- | D | During Construction stage: Noise will be generated by the operation of construction vehicles and equipment. At Operation stage: The operation works will not use equipment which will generate noise. | |
| | 26 | Ground Subsidence | D | D | The project does not extract groundwater. | |
| | 27 | Odour | D | D | The project does not include the activities which generates odour. | |
| | 28 | Sediments | D | D | The scale of the pipe support bridges is not large and will not affect the sediments of the river bed. | |
| Others | 29 | Accident | В- | D | During Construction: Care should be taken for the accidents at working area or traffic accidents which are estimated at the construction works. At Operation: The operation works which cause significant accidents will not be generated. | |
| | 30 | Climate Change | D | D | The project does not use equipment which use large amount of electricity or chemical substances of GHGs. | |

Notes:

A+/-: Significant positive/negative impact is expected.

B+/-: Positive/negative impact is expected to some extent.

C+/-: Extent of positive/negative impact is unknown. (A further examination is needed, and the impact could be clarified as the study progresses)

D: No impact is expected. Source: JICA Survey Team

(4) UFW Reduction Project

The scoping results for the UFW reduction project are shown in Table 14.5.5. The environmental and social elements of poverty, social infrastructure / service, infectious diseases, occupational health and safety, air pollution (dust), waste, noise and accident are to be assessed for IEE.

Table 14.5.5 Scoping Results for UFW Reduction Project

| Туре | No. | Elements to | Rating | | Reason for Evaluation | |
|-----------------------------|-----|-------------------|--------|--------|--|-----------------------|
| Турс | | be Assessed | | Const. | Oper. | Reason for Evaluation |
| | 1 | Protected Area | D | D | The project site and surrounding area is not located in any national parks or nature reserves. | |
| N | 2 | Ecosystem | D | D | Most of the project sites are located in the existing built-up area of BBMP | |
| Natural Environ- ment | 3 | Hydrology | D | D | At construction stage: The construction works of replacing the existing water pipes are implemented at existing public road areas and not at rivers. At operation stage: The future operation works will be implemented at public road areas and not at rivers. | |

| Elements to Rating | | | | | | |
|--------------------|--|--|--------|-------|---|--|
| Туре | No. | be Assessed | Const. | Oper. | Reason for Evaluation | |
| | 4 | Topography / Geology | D | D | The project does not include large scaled excavation works. | |
| | 5 | Resettlement / Land Issue | D | D | The project sites does not include residential area nor compensation problems since the project sites to be acquired are all public lands, not private lands. | |
| | 6 Poverty | | D | B- | At Operation stage: The increase of water tariff may affect the household economy of low income level. | |
| | 7 | Ethic Minor- ity | D | D | There are no ethnic minorities nor indigenous people at the project sites. | |
| | 8 | Employment, sustenance and regional economy | В+ | D | At construction stage: An opportunity for employment of local residents is expected by the construction works and may contribute to local economy. | |
| | 9 Land Use / Regional Re- source | | D | D | The project sites at public road areas and the vacant area in the built-up area will not affect the local land use nor regional resources. | |
| | 10 | Water Use | D | D | The project replaces existing water pipelines and does not relate to water use. | |
| Social Environment | 11 | Social Infra- structure / Service | В- | B- | At construction stage: The replacing works of the water pipelines at road areas may affect the traffic flow and existing underground utilities. At Operation stage: The leakage detection survey at road areas may interfere the traffic flow. | |
| VIIOIIIICIIC | 12 | Local society for decision making | D | D | The project is to implement a public works by the government which aim to bring public benefit and will not affect local society. | |
| | 13 | Unbalance of damages and benefits | D | D | The project will not bring unbalance damage and benefit. | |
| | 14 | Local Conflicts of Interests | D | D | The project does not supply water to specific people or structure, and it will not bring local conflicts. | |
| | 15 | Heritage or Cultural As- sets | D | D | The project is implemented at public road areas where the historical and cultural assets are reserved separately from roads. | |
| | 16 | Landscape | D | D | The replacement of water pipelines will be laid under existing public road areas without any appearance of structure on the ground. | |
| | 17 | Gender | D | D | The project does not relate to the issues of gender. | |
| | 18 | Right of Children | D | D | The project is not related to the issue of right of children. Child labor will be prohibited for implementation of the project by compliance with national laws or international guidelines. | |
| | 19 | Infectious Diseases (e.g. HIV / AIDS) | В- | D | The inflow of construction workers may generate or expand infection diseases. | |

| | | Elements to | Rating | | | |
|-----------|-----|--------------------------------------|--------|-------|---|--|
| Type | No. | be Assessed | Const. | Oper. | Reason for Evaluation | |
| | | Occupational Health and Safety | B- | D | At Construction stage: Appropriate case should be taken for the working environment of the construction workers. At Operation stage: There will be no operation works which increase the risks of operation staffs. | |
| | 21 | Air Pollution | В- | D | The construction vehicles and equipment at construction stage will generate dust. | |
| | 22 | Water Pollu- tion | D | D | At Construction stage: Turbid water will not be generated by the generation of underground water at excavation works due to the low table of the groundwater. At Operation stage: The operation works does not generate water pollution. | |
| | 23 | Waste | В- | D | During Construction stage: Construction debris, excavation soil and the garbage at construction camps will be generated. At Operation stage: The operation works will not generate waste. | |
| Pollution | 24 | Soil Contami- nation | D | D | The hazardous matter causing soil contamination will not be generated. | |
| | 25 | Noise / Vibration | D | D | During Construction stage: The construction works will be carried out at existing public road areas in Core/ULB areas of BBMP where surrounding traffic noise is large. At Operation stage: The operation works will not use equipment which will generate noise. | |
| | 26 | Ground Subsidence | D | D | The project does not extract groundwater. | |
| | 27 | Odour | D | D | The project does not include the activities which generates odour. | |
| | 28 | Sediments | D | D | The scale of the pipe support bridges is not large and will not affect the sediments of the river bed. | |
| Others | 29 | Accident | В- | B- | During Construction: Care should be taken for the accidents which are estimated at the construction works. At Operation: The leakage detection survey at operation stage will increase the risk of traffic accidents. | |
| Notes: | 30 | Climate Change | D | D | The project does not use equipment which use large amount of electricity or chemical substances of GHGs. | |

Notes:

A+/-: Significant positive/negative impact is expected.

B+/-: Positive/negative impact is expected to some extent.

C+/-: Extent of positive/negative impact is unknown. (A further examination is needed, and the impact could be clarified as the study progresses)

D: No impact is expected. Source: JICA Survey Team

14.7 Estimation of Potential Impacts at IEE Level

(1) Stage V Conveyance Pipeline Project

The potential adverse impacts to be caused by the project are shown in Table 14.7.1.

Table 14.7.1 Potential Adverse Impacts by Stage V Conveyance Pipeline Project

| No. | Environmental and Social Ele- ments | Potential Adverse Impacts |
|-----|---|--|
| 1 | Occupational Health and Safety | At construction phase: During construction stage, the adverse impacts on construction workers, surrounding residents potentially to be caused by the construction works or traffic accidents is estimated. |
| 2 | Air Pollution | At construction phase: At the construction phase, dust will be generated by the operation of construction vehicles and construction equipment at construction sites and surrounding areas. Some adverse impact is estimated. |
| 3 | Waste | At construction phase: The excavation works or demolition works at the construction sites will generate excavated soil and demolition waste. And also, domestic garbage will be generated at the construction camps. |
| 4 | Accident | At construction phase: The increase of vehicles for the construction works may cause some risk of traffic accidents around the construction sites. The vehicles carrying the materials, wastes to and from the construction area may drop spoil or soil on the road surface which cause slippery condition and increases the risk of unsafe traffic. |

Source: JICA Survey Team

(1) Branch Feeding Pipes (Stage V Transmission Pipeline in the City) to Share Water to Core/ULBs The potential adverse impacts to be caused by the project are shown in Table 14.7.2.

Table 14.7.2 Potential Adverse Impacts by Stage V Transmission Pipeline in the City

| No. | Environmental and Social Ele- ments | Potential Adverse Impacts |
|-----|--|--|
| 1 | Social infrastruc- ture / service (At construction phase) | At construction phase: The laying works of water pipes may affect the traffic at major roads because of the temporary use of the road areas. |
| 2 | Occupational Health and Safety | At construction phase: During construction stage, the adverse impacts on construction workers, surrounding residents potentially to be caused by the construction works or traffic accidents is estimated. |
| 3 | Air Pollution | At construction phase: At the construction phase, dust will be generated by the operation of construction vehicles and construction equipment at construction sites and surrounding areas. Some adverse impact is estimated. |

| No. | Environmental and Social Ele- ments | Potential Adverse Impacts |
|-----|---|--|
| 4 | Waste | At construction phase: The excavation or demolition works at the construction sites will generate excavated soil and demolition waste. And also, domestic garbage will be generated at the construction camp The issues of handling or disposal of asbestos should be clarified. |
| 5 | Accident | At construction phase: The increase of vehicles for the construction works may cause traffic congestions on the local road network, and increase the risk of traffic accidents around the construction sites. A part of roads around the project sites may be temporarily blocked and cause traffic congestion at some sections. Traffic may be encroached due to the arrangement of the works such as scaffold, material yard and operation of construction equipment. The vehicles carrying the materials, wastes to and from the construction area may drop spoil or soil on the road surface which cause slippery condition and increases the risk of unsafe traffic. |

(2) 110 Villages Water Supply Project (Distribution Pipeline and Service Connections; and Feeder Pipes between GLRs and OHTs, OHTs and Pumping facilities)

The potential adverse impacts to be caused by the project is shown in Table 14.7.3.

Table 14.7.3 Potential Adverse Impacts by Water Supply Project for 110 Villages

| No. | Environmental and Social Ele- ments | Potential Adverse Impacts |
|-----|--|--|
| 1 | Poverty (At Operation Phase) | At operation phase: At the operation phase after the construction of the pipe laying works and the house connection, the water tariff will be increased to recover the future increase of the operation and maintenance cost. Therefore, future increase of water tariff may affect the household economy of the urban poor. |
| 2 | Social infrastruc- ture / service (At construction phase) | At construction phase: The laying works of water pipes may affect the traffic at major roads because of the temporary use of the road areas. |
| 3 | Infectious Diseases (e.g. HIV / AIDS) | At construction phase: According to National AIDS Control Organization of India, the prevalence of AIDS in India in 2013 was 0.27, while they estimated that 2.39 million people live with HIV/AIDS in India in 2008–09, and the British Medical Journal (2010) estimates the population to be between 1.4–1.6 million people. And also, Karnataka state is one of the states with high HIV prevalence as shown that Manipur (1.40%), Andhra Pradesh (0.90%), Mizoram (0.81%), Nagaland (0.78%), Karnataka (0.63%) and Maharashtra (0.55%). During the construction phase, risk of HIV/AIDS infection may increase among construction workers around construction sites. |
| 4 | Occupational Health and Safety | At construction phase: During construction stage, the adverse impacts on construction workers, surrounding residents potentially to be caused by the construction works or traffic |

| No. | Environmental and Social Ele- ments | Potential Adverse Impacts | | |
|-----|---|--|--|--|
| | | accidents is estimated. | | |
| 5 | Air Pollution | At construction phase: At the construction phase, dust will be generated by the operation of construction vehicles and construction equipment at construction sites and surrounding areas. Some adverse impact is estimated. | | |
| 6 | Waste | At construction phase: The excavation works or demolition works at the construction sites will generate excavated soil and demolition waste. And also, domestic garbage will be generated at the construction camps. | | |
| 7 | Noise / Vibration | At construction phase: The excavation works or demolition works at the construction sites will generate noise and may affect the residents in case that the site is close to residential area. | | |
| 8 | Accident | At construction phase: The increase of vehicles for the construction works may cause traffic congestions on the local road network, and increase the risk of traffic accidents around the construction sites. A part of roads around the project sites may be temporarily blocked and cause traffic congestion at some sections. Traffic may be encroached due to the arrangement of the works such as scaffold, material yard and operation of construction equipment. The vehicles carrying the materials, wastes to and from the construction area may drop spoil or soil on the road surface which cause slippery condition and increases the risk of unsafe traffic. | | |

(3) 110 Villages Sewerage Component Project (Lateral Sewers and House Connection) The potential adverse impacts to be caused by the project are shown in Table 14.7.4.

Table 14.7.4 Potential Adverse Impacts by 110 Villages Sewerage Component Project

| No. | Environmental and Social Ele- ments | Potential Adverse Impacts | | |
|-----|--|--|--|--|
| 1 | Poverty (At Operation Phase) | At operation phase: At the operation phase after the construction of the pipe laying works and the house connection, the sewerage tariff will be increased to recover the future increase of the operation and maintenance cost. Therefore, future increase of sewerage tariff may affect the household economy of the urban poor. | | |
| 2 | Social infrastruc- ture / service (At construction phase) | At construction phase: The laying works of lateral sewers and house connection may affect the traffic at major roads because of the temporary use of the road areas. | | |
| 3 | Infectious Diseases (e.g. HIV / AIDS) | At construction phase: According to National AIDS Control Organization of India, the prevalence of AIDS in India in 2013 was 0.27, while they estimated that 2.39 million people live with HIV/AIDS in India in 2008–09, and the British Medical Journal (2010) estimates the population to be between 1.4–1.6 million people. And also, | | |

| No. | Environmental and Social Ele- ments | Potential Adverse Impacts |
|-----|---|--|
| | | Karnataka state is one of the states with high HIV prevalence as shown that Manipur (1.40%), Andhra Pradesh (0.90%), Mizoram (0.81%), Nagaland (0.78%), Karnataka (0.63%) and Maharashtra (0.55%). |
| | | During the construction phase, risk of HIV/AIDS infection may increase among construction workers around construction sites. |
| 4 | Occupational Health and Safety | At construction phase: During construction stage, the adverse impacts on construction workers, surrounding residents potentially to be caused by the construction works or traffic accidents is estimated. |
| 5 | Air Pollution | At construction phase: At the construction phase, dust will be generated by the operation of construction vehicles and construction equipment at construction sites and surrounding areas. Some adverse impact is estimated. |
| 6 | Waste | At construction phase: The excavation works or demolition works at the construction sites will generate excavated soil and demolition waste. And also, domestic garbage will be generated at the construction camps. |
| 7 | Noise / Vibration | At construction phase: The excavation works or demolition works at the construction sites will generate noise and may affect the residents in case that the site is close to residential area. |
| 8 | Accident | At construction phase: The increase of vehicles for the construction works may cause traffic congestions on the local road network, and increase the risk of traffic accidents around the construction sites. A part of roads around the project sites may be temporarily blocked and cause traffic congestion at some sections. Traffic may be encroached due to the arrangement of the works such as scaffold, material yard and operation of construction equipment. The vehicles carrying the materials, wastes to and from the construction area may drop spoil or soil on the road surface which cause slippery condition and increases the risk of unsafe traffic. |

14.8 Recommended Mitigation Measures

(1) Stage V Conveyance Pipeline Project

The recommended mitigation measures indicating its actor, regulatory authority and budget $/\cos t$ are shown in Table 14.8.1.

Table 14.8.1 Recommended Mitigation Measures for Stage V Conveyance Pipeline Project

At Construction Phase

| No. | Ele- ments | Proposed Mitigation Measures | Actor for Mitigation Measures | Regulatory authority | Budget / Cost |
|-----|---|---|-------------------------------------|------------------------|---|
| 1 | Occu- pa- tional Health and | Preparation of construction plan Training of construction workers Provide construction workers with sufficient personal | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |

| No. | Ele- ments | Proposed Mitigation Measures | Actor for Mitigation Measures | Regulatory authority | Budget / Cost |
|-----|-----------------------|---|---|-----------------------------------|---|
| | Safety | Protection equipment such as hard hats, earpiece, safety shoes, and others; Conduct explanation meetings on safety issues for local communities Install warning signs whereas the potential dangers are expected Erect temporary fence around high risk areas to control public access and light them at night if that is on the regular roads used by the locals; Assign construction staffs on or near places where construction vehicles are crowded to ensure safety. | | | |
| 2 | Air Pollu- tion | Preparation of construction plan for control dust Training of construction workers Provide construction workers with sufficient personal Examination of Contractor's construction plan Monitoring of Contractor's dust control | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |
| 3 | Waste | Preparation of construction plan for excavated soil and demolition waste Examination of Contractor's construction plan Monitoring of Contractor's management of excavated soil, construction debris | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |
| 4 | Acci- dent | Preparation of appropriate construction vehicle operation plan to avoid concentration of machinery and vehicles in limited roads. Allotment of traffic guide for proper control of traffic in order to minimize disruption to traffic flows The construction site should be enclosed with temporary fence to provide a visual barrier between the construction site and adjacent traffic. Contractor's advance notification to communities in case of blocking traffic for transport of heavy equipment the contractor Environmental monitoring | Project Cost / Contract Amount | Project Cost / Contract Amount | Project Cost / Contract Amount |

(2) Stage V Transmission Pipeline in the City to Share Water to Core/ULBs

The recommended mitigation measures indicating its actor, regulatory authority and budget / cost is shown in Table 14.8.2 .

 ${\bf Table~14.8.2~Recommended~Mitigation~Measures~for~Stage~V~Transmission~Pipeline~Project}$

At Construction Phase

| No. | Ele- ments | Proposed Mitigation Measures | Actor for Mitigation Measures | Regulatory authority | Budget / Cost |
|-----|---|--|-------------------------------------|------------------------|---|
| 1 | Social Infra- struc- ture / Service | Prior notice to traffic police before the construction works Placement of traffic guides at each end of construction sections for smooth inducement of traffic Careful examination of construction schedule Setting detouring route if necessary. Sufficient information disclosure such as construction period or work section to media such as television, radio, newspapers, etc. as well as utilization of internet media Socialization activity to local residents including distribution of leaflet or announcement letters, or holding meetings if required. Implementation of underground utility survey for existing water pipes, power lines, telephone lines and gas pipes not to cause damage on these utilities | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |
| 2 | Occu- pa- tional Health and Safety | Preparation of construction plan Training of construction workers Provide construction workers with sufficient personal Protection equipment (PPE) such as hard hats, earpiece, safety shoes, and others; Conduct explanation meetings on safety issues for local communities Install warning signs whereas the potential dangers are expected Erect temporary fence around high risk areas to control public access and light them at night if that is on the regular roads used by the locals; Assign construction staffs on or | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |

| No. | Ele- ments | Proposed Mitigation Measures | Actor for Mitigation Measures | Regulatory authority | Budget / Cost |
|-----|-----------------------|---|---|-----------------------------------|---|
| | | near places where construction vehicles are crowded to ensure safety. | | | |
| 3 | Air Pollu- tion | Preparation of construction plan for control dust Training of construction workers Provide construction workers with sufficient personal Examination of Contractor's construction plan Monitoring of Contractor's dust control | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |
| 4 | Waste | Preparation of construction plan for excavated soil and demolition waste Examination of Contractor's construction plan Monitoring of Contractor's management of excavated soil, construction debris | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |
| 5 | Acci-dent | Preparation of appropriate construction vehicle operation plan to avoid concentration of machinery and vehicles in limited roads. Allotment of traffic guide for proper control of traffic in order to minimize disruption to traffic flows The construction site should be enclosed with temporary fence to provide a visual barrier between the construction site and adjacent traffic. Contractor's advance notification to communities in case of blocking traffic for transport of heavy equipment the contractor Environmental monitoring | Project Cost / Contract Amount | Project Cost / Contract Amount | Project Cost / Contract Amount |

(3) Water Supply Project for 110 Villages

The recommended mitigation measures indicating its actor, regulatory authority and budget / cost is shown in Table 14.8.3.

Table 14.8.3 Recommended Mitigation Measures for UFW Reduction Project

At Construction Phase

| No. | Ele- ments | Proposed Mitigation Measures | Actor for Mitigation Measures | Regulatory authority | Budget / Cost |
|-----|---|--|-------------------------------------|---------------------------|---|
| 1 | Social Infra- struc- ture / Service | Prior notice to traffic police before the construction works Placement of traffic guides at each end of construction sections for smooth inducement of traffic Careful examination of construction schedule Setting detouring route if necessary. Sufficient information disclosure such as construction period or work section to media such as television, radio, newspapers, etc. as well as utilization of internet media Socialization activity to local residents including distribution of leaflet or announcement letters, or holding meetings if required. Implementation of underground utility survey for existing water pipes, power lines, telephone lines and gas pipes not to cause damage on these utilities | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |
| 2 | Infectious Disceases (e.g. HIV / AIDS) | Preparation of appropriate working health plan Training of construction workers | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |
| 3 | Occu- pa- tional Health and Safety | Preparation of construction plan Training of construction workers Provide construction workers with sufficient personal Protection equipment (PPE) such as hard hats, earpiece, safety shoes, and others; Conduct explanation meetings on safety issues for local communities Install warning signs whereas the potential dangers are expected Erect temporary fence around high risk areas to control public access and light them at night if that is on the regular roads used by the locals; Assign construction staffs on or near places where construction vehicles are crowded to ensure safety. | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |
| 4 | Air | Preparation of construction plan for | Contractor | KPCB/BWSSB/C | Project Cost / |

| No. | Ele- ments | Proposed Mitigation Measures | Actor for Mitigation Measures | Regulatory authority | Budget / Cost |
|-----|---------------------------|---|---|-----------------------------------|---|
| | Pollu- tion | control dust Training of construction workers Provide construction workers with sufficient personal Examination of Contractor's construction plan Monitoring of Contractor's dust control | | onsultant | Contract Amount |
| 5 | Waste | Preparation of construction plan for excavated soil and demolition waste Examination of Contractor's construction plan Monitoring of Contractor's management of excavated soil, construction debris | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |
| 6 | Noise / Vibra- tion | Utilization of low-noise type construction machineries if applicable. Temporary enclosure of the site during the construction works if necessary Instructing the contractors to examine low noise/vibration construction methods. Encouragement of idling reduction to the workers. To avoid works at night and early morning at the sites close to residential areas, schools and hospitals Monitoring of noise level at facility boundaries | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |
| 7 | Acci- dent | Preparation of appropriate construction vehicle operation plan to avoid concentration of machinery and vehicles in limited roads. Allotment of traffic guide for proper control of traffic in order to minimize disruption to traffic flows The construction site should be enclosed with temporary fence to provide a visual barrier between the construction site and adjacent traffic. Contractor's advance notification to communities in case of blocking traffic for transport of heavy equipment the contractor Environmental monitoring | Project Cost / Contract Amount | Project Cost / Contract Amount | Project Cost / Contract Amount |

(4) 110 Villages Sewerage Component Project (Lateral Sewers and House Connection)

The recommended mitigation measures indicating its actor, regulatory authority and budget / cost is shown in Table 14.8.4.

Table 14.8.4 Recommended Mitigation Measures for 110 Villages Sewerage Component Project<u>At Construction Phase</u>

| No. | Elements | Proposed Mitigation Measures | Actor for Mitigation Measures | Regulatory authority | Budget / Cost |
|-----|--|--|-------------------------------------|------------------------|--------------------------------------|
| 1 | Social Infrastructure / Service | Prior notice to traffic police before the construction works Placement of traffic guides at each end of construction sections for smooth inducement of traffic Careful examination of construction schedule Setting detouring route if necessary. Sufficient information disclosure such as construction period or work section to media such as television, radio, newspapers, etc. as well as utilization of internet media Socialization activity to local residents including distribution of leaflet or announcement letters, or holding meetings if required. Implementation of underground utility survey for existing water pipes, power lines, telephone lines and gas pipes not to cause damage on these utilities | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |
| 2 | Infectious Diseases (e.g. HIV / AIDS) | Preparation of appropriate working health plan Training of construction workers | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |
| 3 | Occupational Health and Safety | Preparation of construction plan Training of construction workers Provide construction workers with sufficient personal Protection equipment (PPE) such as hard hats, earpiece, safety shoes, and others; | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |

| No. | Elements | Proposed Mitigation Measures | Actor for Mitigation Measures | Regulatory authority | Budget / Cost |
|-----|----------------------|--|-------------------------------------|------------------------|--------------------------------------|
| | | Conduct explanation meetings on safety issues for local communities Install warning signs whereas the potential dangers are expected Erect temporary fence around high risk areas to control public access and light them at night if that is on the regular roads used by the locals; Assign construction staffs on or near places where construction vehicles are crowded to ensure safety. | | | |
| 4 | Air Pollution | Preparation of construction plan for control dust Training of construction workers Provide construction workers with sufficient personal Examination of Contractor's construction plan Monitoring of Contractor's dust control | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |
| 5 | Waste | Preparation of construction plan for excavated soil and demolition waste Examination of Contractor's construction plan Monitoring of Contractor's management of excavated soil, construction debris | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |
| 6 | Noise / Vibration | Utilization of low-noise type construction machineries if applicable. Temporary enclosure of the site during the construction works if necessary Instructing the contractors to examine low noise/vibration construction methods. Encouragement of idling reduction to the workers. To avoid works at night and early morning at the sites close to residential areas, schools and hospitals Monitoring of noise level at | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |

| No. | Elements | Proposed Mitigation Measures | Actor for Mitigation Measures | Regulatory authority | Budget / Cost |
|-----|----------|---|---|-----------------------------------|--------------------------------------|
| | | facility boundaries | | | |
| 7 | Accident | Preparation of appropriate construction vehicle operation plan to avoid concentration of machinery and vehicles in limited roads. Allotment of traffic guide for proper control of traffic in order to minimize disruption to traffic flows The construction site should be enclosed with temporary fence to provide a visual barrier between the construction site and adjacent traffic. Contractor's advance notification to communities in case of blocking traffic for transport of heavy equipment the contractor Environmental monitoring | Project Cost / Contract Amount | Project Cost / Contract Amount | Project Cost / Contract Amount |

At Operation Phase

| No. | Ele- ments | Proposed Mitigation Measures | Actor for Mitigation Measures | Regulatory authority | Budget / Cost |
|-----|---------------|---|-------------------------------------|------------------------|------------------|
| 1 | Poverty | Establishment of tariff collection system for urban poor Implementation of public aware- ness survey | Contractor | KPCB/BWSSB/C onsultant | O & M Cost |

Source: JICA Survey Team

(5) UFW Reduction Project

The recommended mitigation measures indicating its actor, regulatory authority and budget / cost is shown in Table 14.8.5.

Table 14.8.5 Recommended Mitigation Measures for UFW Reduction Project

At Construction Phase

| No. | Ele- ments | Proposed Mitigation Measures | Actor for Mitigation Measures | Regulatory authority | Budget / Cost |
|-----|--|--|-------------------------------------|---------------------------|--------------------------------|
| 1 | Social Infra- structure / Service | Prior notice to traffic police before the construction works Placement of traffic guides at each end of construction sections for | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |

| No. | Ele- ments | Proposed Mitigation Measures | Actor for Mitigation Measures | Regulatory authority | Budget / Cost |
|-----|---------------------------------------|--|-------------------------------------|------------------------|---|
| | | smooth inducement of traffic Careful examination of construction schedule Setting detouring route if necessary. Sufficient information disclosure such as construction period or work section to media such as television, radio, newspapers, etc. as well as utilization of internet media Socialization activity to local residents including distribution of leaflet or announcement letters, or holding meetings if required. Implementation of underground utility survey for existing water pipes, power lines, telephone lines and gas pipes not to cause damage on these | | | |
| 2 | Infectious Diseases (e.g. HIV / AIDS) | Preparation of appropriate working health plan Training of construction workers | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |
| 3 | Occupational Health and Safety | Preparation of construction plan Training of construction workers Provide construction workers with sufficient personal Protection equipment (PPE) such as hard hats, earpiece, safety shoes, and others; Conduct explanation meetings on safety issues for local communities Install warning signs whereas the potential dangers are expected Erect temporary fence around high risk areas to control public access and light them at night if that is on the regular roads used by the locals; Assign construction staffs on or near places where construction vehicles are crowded to ensure safety. | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |
| 4 | Air Pol- lution | Preparation of construction plan for control dust Training of construction workers Provide construction workers with sufficient personal Examination of Contractor's construction plan | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |

| No. | Ele- ments | Proposed Mitigation Measures | Actor for Mitigation Measures | Regulatory authority | Budget / Cost |
|-----|----------------------|---|---|-----------------------------------|---|
| | | Monitoring of Contractor's dust con- trol | | | |
| 5 | Waste | Preparation of construction plan for excavated soil and demolition waste Examination of Contractor's construction plan Monitoring of Contractor's management of excavated soil, construction debris | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |
| 6 | Noise / Vibration | Utilization of low-noise type construction machineries if applicable. Temporary enclosure of the site during the construction works if necessary Instructing the contractors to examine low noise/vibration construction methods. Encouragement of idling reduction to the workers. To avoid works at night and early morning at the sites close to residential areas, schools and hospitals Monitoring of noise level at facility boundaries | Contractor | KPCB/BWSSB/C onsultant | Project Cost / Contract Amount |
| 7 | Accident | Preparation of appropriate construction vehicle operation plan to avoid concentration of machinery and vehicles in limited roads. Allotment of traffic guide for proper control of traffic in order to minimize disruption to traffic flows The construction site should be enclosed with temporary fence to provide a visual barrier between the construction site and adjacent traffic. Contractor's advance notification to communities in case of blocking traffic for transport of heavy equipment the contractor Environmental monitoring | Project Cost / Contract Amount | Project Cost / Contract Amount | Project Cost / Contract Amount |

At Operation Phase

| at operation i hase | | | | | | | | | |
|-------------------------|---------------|--|-------------------------------------|------------------------|------------------|--|--|--|--|
| No. | Ele- ments | Proposed Mitigation Measures | Actor for Mitigation Measures | Regulatory authority | Budget / Cost | | | | |
| 1 | Poverty | • Establishment of tariff collection system for urban poor | Contractor | KPCB/BWSSB/C onsultant | O & M Cost | | | | |

Supporting Report

| | • Implementation of public awareness | | |
|--|--------------------------------------|--|--|
| | survey | | |

Source: JICA Survey Team

14.9.2 Environmental Monitoring Plan (JICA Environmental Monitoring Form)

- (1) Stage V Water Supply Project, Transmission Pipelines to share water to Core Area and Connection pipelines between GLRs and OHTs
- 1) Construction Phase

a) Air Quality (Dust)

| Method | Proposed Location | Frequency | Me | asured | Value | |
|------------------------|---|--|-------------------|--------|-------|---|
| Visual in- spection | Facility boundaries at construction sites | Monthly (Examination of daily or monthly report) | Item | Yes | No | If Yes, Mdeasures Taken (e.g. water sprinkling) |
| | | | Dusts | | | |
| | | | Other (Specify:) | | | |

b) Waste

| Method | | Proposed Location | Frequency | Measured | l Value |
|------------------------|---|---|--|--|---------|
| Visual in- spection | • | Construction sites for excavation works Construction sites for backfill Final disposal site of con- | Monthly (Examination of daily or monthly report) | Item Type of construction debris Amount of construction debris Amount of excavated soil Location of final disposal sites | Amount |
| | | struction debris | | of construction debris Location of final disposal sites of excavated soil | |

c) Noise / Vibration

| Monitoring Item | Measured Value (Mean) | Measured Value (Max.) | Standards | Frequency | Measurement Point |
|--------------------|-----------------------------|-----------------------------|-----------------------|-----------|---|
| Noise Level | | | Indian stand- ard* | Monthly | Facility boundaries at the following facilities; Gottigere GLR Singapura GLR Kingadeeranahalli GLR |

* Indian standard as per Schedule III under the Noise Pollution (Regulation and Control) Rules, 2000 and amendment 2002

| Area Code | Cotogowy of Amoo | Limits in dB (A) | | |
|-----------|------------------|------------------|------------|--|
| Area Code | Category of Area | Day time | Night time | |
| A | Industrial | 75 | 70 | |
| В | Commercial | 65 | 55 | |
| С | Residential | 55 | 45 | |
| D | Silence zone | 50 | 40 | |

Note 1: Daytime is reckoned in between six (6) am to 10 p.m.

Note 2: Night time is reckoned in between 10 p.m. to six (6) a.m.

Note 3: Silence zone is defined as areas up to 100 meters around such premises as hospitals, educational institutions and courts. The silence zones are to be declared by the Competent Authority. Use of vehicular horns, loudspeakers and bursting of crackers shall be banned in these zones.

Note 4: Mixed categories of areas should be declared as one of the four above-mentioned categories by the Competent Authority and the corresponding standards shall apply.

d) Accident

| Item | Monitoring Place | Monitoring Method | Frequency | Monitoring Result |
|---|------------------|--|--|-------------------|
| Adequate safety traffic control manners | Н | Visual inspection Examination of daily / monthly | Monthly (Examination of daily or monthly report) | , |
| | | report | | |

2) Operation Phase

a) Water Quality

| | Parameters | Raw Water | Treated Water | Frequency | Proposed Location |
|----|-------------------------|-----------|---------------|-----------|---|
| 1 | Turbidity | V | V | Daily | WTP at TK Halli (Raw water, |
| 2 | pН | V | V | Daily | treated water) |
| 3 | Alkalinity | V | V | Daily | Vasudevapura GLR (Treated) |
| 4 | Total hardness | V | | Daily | water) Singapura GLR (Treated water) |
| 5 | Total dissolved solids | V | | Daily | Chokkanahalli GLR (Treated) |
| 6 | Electrical conductivity | V | | Daily | water) |
| 7 | Calcium | V | | Daily | Lingadeeranahalli GLR |
| 8 | Iron | V | V | Daily | (Treated water) |
| 9 | Magnesium | V | | Daily | Lingadeeranahalli GLR (Transtad annatan) |
| 10 | Total Coliforms | V | | Daily | (Treated water)Doddakanalli GLR (Treated wa- |
| 11 | Temperature | V | | Daily | ter) |
| 12 | Color | | V | Daily | Kadugodi GLR (Treated water) |
| 13 | Fecal coliforms | | V | Daily | 1 |
| 14 | Residual chlorine | | V | Daily | 1 |

b) Waste

| Method | Proposed Location | Frequency | Measured Value | | |
|------------|-------------------|-------------------|-----------------------------------|--------|--|
| Visual in- | WTP at TK Halli | Monthly (Examina- | Item | Amount | |
| spection | Final Disposal | | Type of construction debris | | |
| | Site | monthly report) | Mount of construction de- bris | | |
| | | | Amount of excavated soil | | |

c) Noise / Vibration

| Monitoring Item | Measured Value (Mean) | Measured Value (Max.) | Standards | Frequency | Measurement Point |
|--------------------|-----------------------------|-----------------------------|-----------------------|-----------|--|
| Noise Level | | | Indian stand- ard* | Monthly | Facility boundaries at the following facilities; TK Halli WTP Haraholi Pumping Station Tataguni Pumping Station |

^{*}Refer to information at "Noise/Vibration", 1) Construction Phase, (1) Stage V Water Supply Project.

d) Accident

| Item | Monitoring Place | Monitoring Method | Frequency | Monitoring Result |
|---|---|---|--|-------------------|
| Adequate safety traffic control manners | The following facilities and surrounding road areas; TK Halli WTP Harohalli Pumping Station Tataguni Pumping Station | Visual inspection Examination of daily / monthly report | Monthly (Examination of daily or monthly report) | |

(2) Sewerage Project for 110 Villages

1) Constriction Phase

a) Air Quality (Dust)

| Method | Proposed Location | Frequency | Me | easured | Value | |
|-------------------|---|--|-------------------|---------|-------|---|
| Visual inspection | Facility boundaries at construction sites | Monthly (Examination of daily or monthly report) | Item | Yes | No | If Yes, Mdeasures Taken (e.g. water sprinkling) |
| | | | Dusts | | | |
| | | | | | | |
| | | | Other (Specify:) | | | |

b) Waste

| Method | | Proposed Location | Frequency | Measured | l Value |
|------------|---|---|---------------------------------------|----------------------------------|---------|
| Visual in- | - | Construction sites for exca- | Monthly (Exami- | Item | Amount |
| spection | | vation works Construction sites for backfill Final disposal site of construction debris | nation of daily or monthly report) | Type of construction debris | |
| | - | | | Mount of construction debris | |
| | _ | | | Amount of excavated soil | |
| | | | | Location of final disposal sites | |
| | | | | of construction debris | |
| | | | | Location of final disposal sites | |
| | | | | of excavated soil | |

c) Noise / Vibration

| Monitoring Item | Measured Value (Mean) | Measured Value (Max.) | Standards | Frequency | Measurement Point |
|--------------------|-----------------------------|-----------------------------|-----------------------|-----------|---|
| Noise Level | | | Indian stand- ard* | Monthly | Facility boundaries at the following facilities; Herohhali STP Hosahalli STP Doddabettahalli STP Chikkabanavara STP |

^{*}Refer to information at "Noise/Vibration", 1) Construction Phase, (1) Stage V Water Supply Project.

d) Accident

| Item | Monitoring Place | Monitoring Method | Frequency | Monitoring Result |
|---|--------------------|---|--|-------------------|
| Adequate safety traffic control manners | Construction sites | Visual inspection Examination of daily / monthly report | Monthly (Examination of daily or monthly report) | |

2) Operation Phase

a) Water Quality (Treated Effluent)

| | Parameters | Measured Value (Mean) | Measured Value (Max.) | Stand- ards* | Freque- ncy | Measurement Point |
|---|------------------|-----------------------------|-----------------------------|-----------------|----------------|--|
| 1 | pН | | | 6.0 - 9.5 | Daily | Jakkur Hemigepura |
| 2 | BOD | | | < 10 | Daily | Yelahankakere Nagasandra |
| 3 | COD | | | < 50 | Daily | Doddabettahalli Karivobanahalli |
| 4 | TSS | | | < 20 | Daily | Bilishivalli Herohalli |
| 5 | NH4-N | | | < 5 | Daily | Varthur Hosahalli Chikkabanavara-2 |
| 6 | T-N | | | < 10 | Daily | Tilagalalalii Talaghattapura |
| 7 | Fecal Coliform** | | | < 100 | Daily | Somapura |

^{*} As per CPCB New Standards dated 27th April 2016, **MPN/100 ml

b) Waste

| Method | Proposed Location | | Proposed Location | | Measured Va | alue |
|------------|---|---|------------------------------|---|-------------------------------------|--------|
| Visual in- | i) The following STPs* | • | Somapura | Monthly (Examination | Item | Amount |
| spection | Jakkur Yelahankakere | • | Hemigepura Nagasandra | of daily or monthly report) | Generation amount of treated sludge | |
| | DoddabettahalliBilishivalli | • | Karivobanahalli Herohalli | | Disposal amount of treated sludge | |
| | Varthur Pillaganahalli Talaghattapura Hosahalli Chikkabanavara-2 ii) Final disposal site | | | Location of final disposal site of treated sludge | | |

c) Noise / Vibration

| Monitoring Item | Measured Value (Mean) | Measured Value (Max.) | Standards | Frequency | Measurement Point |
|--------------------|-----------------------------|-----------------------------|-----------------------|-----------|--|
| Noise Level | | | Indian stand- ard* | Monthly | Facility boundaries at the following STPs; Herohhali STP Hosahalli STP Doddabettahalli STP Chikkabanavara -2 STP |

^{*}Refer to information at "Noise/Vibration", 1) Constriction Phase, (1) Stage V Water Supply Project.

d) Offensive Odor

| Monitoring Item | Measured Value (Mean) | Measured Value (Max.) | Standards* (ppm) | Measurement Point | Frequency |
|-------------------------------------|-----------------------------|-----------------------------|---------------------|---|-----------|
| Ammonia | | | 1.0 | Facility boundaries at the following | Monthly |
| Methyl mercaptan | | | 0.002 | STPs; | |
| Hydrogen Sulfide (H ₂ S) | | | 0.02 | Herohhali STPHosahalli STP | |
| Methyl sulfide | | | 0.01 | Doddabettahalli STP | |
| Styrene | | | 0.4 | Chikkabanavara -2 STP | |

Notes; Japanese Offensive Odour Control Law, Law No. 91 / 1971 or latest amendment by Law No. 71 / 1995

e) Accident

| Item Monitoring Place | | Monitoring Method | Frequency | Monitoring Result |
|---|--|---|--|-------------------|
| Adequate safety traffic control manners | All STP sites and surrounding areas All ISPS sites and surrounding areas | Visual inspection Examination of daily / monthly report | Monthly (Examination of daily or monthly report) | |

Supporting Report 14.12

Stakeholder Meeting

Minutes of Meeting

for

Stakeholders' Meeting

on

CAUVERY WATER SUPPLY AND SEWERAGE PROJECT STAGE V

Date and Time: 11 AM, August 22, 2017 Venue: BWSSB Auditorium, 4th floor

Stakeholders (list attached) and the representatives of Bangalore Water Supply and Sewerage Board (BWSSB) exchanged opinions on the contents of CAUVERY WATER SUPPLY AND SEWERAGE PROJECT STAGE V. The main points discussed are as attached hereto.

Nushar Giri Nath, Chairman, BWSSB

<List of Attachment>

- (1) Invitation letter to attendants
- (2) Attendants list
- (3) Explanation materials
- (4) Minutes of Discussions
- (5) Photos of the Meetings

Phone / Fax: 9 608492344 AbUReport



BANGALORE WATER SUPPLY AND SEWERAGE BOARD Office of the Chief Engineer(K), 5th Floor, Cauvery Bhavan, K.G.Road, Bangalore 560009.

No.BWSSB/CH/CE(K)/ 546 /2017-18

Dated: 16-08-2017

| To, | Commisioner, | Chairman, |
|---|--|--|
| Commissioner, BBMP Hudson Circle, Sampangi Rama Nagar. Bengaluru, Karnataka 560002, India | Bangalore Development Authority, T. Chowdaiah Road, Kumara park West, Bangalore. | Karnataka State Pollution Control Board, "Parisara Bhavan", #49,4th & 5th Floor, Church Street, Bangalore-560001 |
| Chief Executive Officer, Lake Development Authority No.49, 2nd Floor, Parisara Bhavan, Church Street, Bangalore - 560001, Near Mg Road | Metropolitan Commissioner Bangalore Metropolitan Region Development Authority (BMRDA), Bangalorc. , # 1, Ali Askar Road, LRDE Building, Bangalore- 560052. | Managing Director, BESCOM, Corporate Office, K.R.Circle, Bengaluru-560001 |
| MLAs of 110 Villages | Corporators of 110 Villages | |

Sir,

Sub: Stake Holder Meeting on Cauvery Water Supply Scheme (CWSS) V stage to provide drinking water supply and Sewerage facility to 110 Villages of BBMP.

Ref: Japan International Cooperation Agency (JICA), Japan and BWSSB agreed Minutes of Discussion on Project.

Adverting to above, Government of Karnataka (GOK) has taken decision to provide drinking water facility and sanitation for the newly added 110 villages of BBMP on priority. The Detailed Project Report (DPR) is forwarded to JICA, Japan to fund the project in terms of Loan to BWSSB. JICA study team did the feasibility of this project and based on their recommendation JICA is considering loan facilities to the project.

Main components of the Project;

7) Augmenting BWSSB with additional 775 MLD of water from Cauvery Source to 110 Villages and to satisfy the needs of entire Bangalore city (800 Sq KM).

8) 7 Ground level reservoirs on periphery of the city.

9) Providing Sewerage System to cover entire 110 Villages

.....2

- 4) 14 numbers of Sewage treatment Plants (STP's)all round the Bangalore to treat the sewage and make environmentally viable solutions for the water bodies located in 110 villages.
- 5) 7 numbers of Intermediate sewage Pumping Stations (ISPS) to pump the sewage to STP.
- 6) SCADA system for entire system to Control monitoring and all the above works to be executed by BWSSB under the supervision and coordination by International consultants appointed by funding agency based on the guide line prescribed by JICA.

The time frame for this project is 36 months and expected to start by 2019 March.

This project is counter guaranteed by Government of India (GoI) and all the other formalities are under process. As a preconditions to the final approval from JICA towards this project, a Stake Holders meeting is to be conveyed to explain the importance of this project and the necessity of this project to all the agency taking the benefit of this project.

- 1. The underlying principle of stakeholder engagement is to have the opportunity to know about the details of the Project.
- 2. to establish what issues matter most to them
- 3. develop understanding and agree how best to deal with issues of concern
- 4. ensure project sustainability by involving stakeholders in implementation and monitoring
- 5. Through working together, key stakeholders can identify common concerns, develop common goals and reap the benefits of the impact of a Stage V project.
- 6. Making project more effective

In this regard, I request you to attend the Stake Holders meeting to be held on August 2017, Tuesday at 11:00AM in Auditorium, 4th Floor, Cauvery Bhavan, K.G.Road, Bangalore and oblige.

Thanking You.

Chairman BWSSB.

Copy submitted to Additional Chief Secretary, UDD for kind information. Copy to EIC/all CEs for information and necessary action.

·Copy to M/s NJS for information.

Bengaluru Water Supply and Sewerage Project (Stage V)

Bangalore Water Supply & Sewerage Board In Coordination with NJS Consultants Co. Ltd., Japan

| Ag | enda of the Stakeholder Med | eting |
|--------------------------------|---|----------------------|
| Purpose/Objective | Stakeholder Meeting | |
| Meeting Date and Time | 22 nd August 2017 | 11:00 – 13:00 |
| Venue | BWSSB Auditorium, 4 th floor | |
| Registration | i i | |
| Welcome Speech by | Shri Tushar Giri Nath, IAS., Hon'al | ole Chairman, BWSSB |
| Presentation on the P BWSSB | roject by Shri K R Manjunath, Chief | Engineer – Projects, |
| | | |
| Discussion and Sugg | estions from the Stake Holder | |
| | v. | |
| Summary of Worksh | op | 2 |
| 1 | | |
| Vote of Thanks by S | hri Dr. P N Ravindra, Chief Enginee | er - Kaveri |
| Lunch | • | |



Bengaluru Water Supply and Sewerage Project (Stage, W) ting Report

Date: 22-Aug-2017

enue: Cauvery Bhavan 4th Floor Conference Hall

| S/N | Name, vic | Designation/ gorganization | Contact(Details) | Signature: |
|-----|---------------------------|--|------------------|------------|
| 1 | Yoshihiro KIRISHIMA | Sr. Engineer NJS Consultants Co., Ltd | | |
| 2 | RAGHU | Bussb Fee | | B |
| 3 | P.R. Frances | te k-1-2 | | dod |
| 4 | Gamalalestrova on ora, ne | ВВК- Ч | | 2 |
| 5 | Pavan - N | AERK-1.2 | | Não - |
| 6 | Facha Asheaf fi | AE | | ant |
| 7 | Narell B.k | AEE (t-3)2 | | dent |
| 8 | Roghavendra, C.P. | EE (K-3) | | 14 |
| 9 | Chethanky | AEE (K-1)-1 | | Cheffer |
| 10 | Elizabeth | XE (K-1)1 | | Sulv |
| 11 | B.14. Manjunder | AEE(BLOW)M-1 | | (3) |
| 12 | Maneen | BWSSB | | Novinon |
| 13 | SRINATH-S | AE CECH) | | 8 |
| 14 | Kanakaráj | AE(K)Ele-1 | | The last |
| 15 | FIRO2 PALMA | AE CELES | | £., |
| 16 | Svilivas. | Pa to would st, with | | lar. |
| 17 | SURESHUT | APECO(K) COLT | | 3 |
| 18 | T.R. Somvin | 4 BE NW-2 | | Fend |
| 19 | Rames ti Annes teles | AE (K-q) | _ | 881 |
| 20 | Shwitha S | A(5 (K-1) | | Sla |



Bengaluru Water Supply and Sewerage Project (Stage, Noting Report

In coordination with 2 NJS Consultants Co. Ltd.

Date: 22-Aug-2017

enue: Cauvery Bhavan 4th Floor Conference Hall

| S/N | Name | na, (Designation). Scopenibation | Contact Details. (IIel/E-mail) | CONTRACTOR | |
|-----|----------------|-------------------------------------|-----------------------------------|---|---|
| 21 | G-V-NABARAT | A-c. whom D.c.of | | ANG | |
| 22 | Midmohe | Busm | | NX- | |
| 23 | Chamber 5 | NEE BUSER | | Jan. | |
| 24 | KR Ramakvich | EECMG-2/ANGO | | and the | _ |
| 25 | COULASA EKAL | n | | | - |
| 26 | Roveendrates | EE (nowwold) | | Called | |
| 27 | B.C. Gargas | n EE (south) | | 2 | |
| 28 | Mudestosa | AE ONGEDIT | | MU9- | |
| 29 | Nanaymorry | CE Cimc. 3) | | Dr. 1 | |
| 30 | Role Alyadan | CESTPLEN) | | 84 | _ |
| 31 | Hemath Koms | ABELLIELE-2 | | Jarait | |
| 32 | Musulic.p | DE (6)66, 2 | | Marce | |
| 33 | G. Mahadarson | odg EE(DW)-2, | , | 81/3/2 | ` |
| 34 | P. N. Nayak | CE/BOA | | | • |
| 35 | H. M. RAVINDRA | | | A s | |
| 36 | Dorangu. M | ACE (M-2) mag | | Cy | |
| 37 | R.Ram | F-A | | N | |
| 38 | H. Laushman | S.E.O, KSPCUS | | V2-> | < |
| 39 | SUPETAR | EE (Contra) | | Pen | / |
| 40 | Somasholar | 196. 5 Cm | | Sono | |



Bengaluru Water Supply and Sewerage Project (Stage Noting Report

In coordination with 2 NJS Consultants Co. Ltd.

Date: 22-Aug-2017

enue: Cauvery Bhavan 4th Floor Conference Hall

| SNEEDEN SETT | The state of the department of the state of | | | Section of the sectio | |
|--------------|---|------------------------------|------------------|--|-----|
| S/N | Name | Designation/ Organization | Contact Details. | [七][[4][[2][[6][[6][[6][[6][[6][[6][[6][[6][[6 | |
| 41 | DE TENDE | F TO CLESTON | _1(| 4 | |
| 42 | | | | Jon | |
| 43 | AMRUTESHPL | Romwyer word. Row SSB | | 4. | |
| 44 | R.S. Dakued | MWSSM . | _ | JR. | |
| 45 | RANGASUAM | 13. W.S I 13 | | P | |
| 46 | M. Vagheegho | JWICO | | M | |
| 47 | Chandfum | Corporator - word() | | | |
| 48 | Prodey Box | AKEBWILD | | | |
| 49 | B.S. JAYALMA | BUSIB | | dt= | |
| 50 | T- Pullays | r knows ABE | | LA! | |
| 51 | B. Phivoprased | ACE (DOW), BINGET | | P.C. | |
| 52 | A. Ravi | Samon Assistant | | of the | |
| 53 | R. Brecenry | Aer (M)? | | and the same | • |
| 54 | B.m. wagerabaf | who AEK King | | | |
| 55 | Dajeer-7 | EETE-A | | 1 | |
| 56 | An mape | 7 COSROPPAN | | Ausce | -dM |
| 57 | U CO BEADOS | (B) 194 | | | ۲ ۱ |
| 58 | K-580000 | 1055 | | e011 | |
| 59 | Shobbu Goi | when band 97 | | | |
| 60 | Enforal! | DINAN | | | |
| | | | | <u></u> | |



Bengaluru Water Supply and Sewerage Project (Stagepy) ing Report

In coordination with 2 NJS Consultants Co. Ltd.

Date: 22-Aug-2017

enue: Cauvery Bhavan 4th Floor Conference Hall

| S/N | Name / Ax | | ©ontacı Details ∴ (ilel/l≅mail) | |
|-----|-------------------------|--------------------|------------------------------------|---------|
| 61 | Cholinege | E-14 | | 2 |
| 62 | PHANJUNATH | AFE | | |
| 63 | Satham | Corpueper. | | 95 |
| 64 | Slashi | C-H9M | | Bashi- |
| 65 | Maroyana Ra | Dr. CA BOAD | | Dock |
| 66 | all with so | Prec Barran | • | 8 |
| 67 | MANOHAS SINSH | AEr | | Dangler |
| 68 | Moham | Str Ste (NISEN) | | Me |
| 69 | Mizom | SR.77 (NZS) | , | iro |
| 70 | Reme | BBND ' | | |
| 71 | Reme | Design Enix | | less. |
| 72 | Such Visughmay | Mord No. Siturary | | D X 7 |
| 73 | Savetta | Conformation BBMP. | | |
| 74 | Charol partie | BBMP. | | |
| 75 | Ragha Lui | Sha AIC | | R |
| 76 | Ahred CK. | ARR | | Ameel |
| 77 | Zijch hurton | | W | M |
| 78 | Devros. | 13. RM.P. | | Sel |
| 79 | Romananda S.V. Douzh | BEE (E) BWW | | Down |
| 80 | S.V. Daniel | ACE (M-4) | | Deel |



Bengaluru Water Supply and Sewerage Project (Stage, W) ting Report

In coordination with NJS Consultants Co. Ltd.

Date: 22-Aug-2017

enue: Cauvery Bhavan 4th Floor Conference Hall

| SIN | " Name | . Designation/ Organization | Contact Details (Tel/E-mail) | Signa- ture |
|-----|----------------|--------------------------------|---------------------------------|----------------|
| 81 | K-R-Manjuras | Bwiles | | My. |
| 82 | Jagaelcesh k.L | | | 7700 |
| 83 | PN. Rawnah | e CEC/RUSY | | (P) |
| 84 | N. Satish | CE. WWT | <u>-</u> | 000 AO |
| 85 | KEMPARA | RWSN | | tre' |
| 86 | MALAH | | | |
| 87 | Suresh it | WOS BUSSING (Project |) | Le |
| 88 | Lawn- | (N3) Conjoughts. | λ | Ange |
| 89 | Seemakuman | BBMP | | Se . |
| 90 | Muthurpy. | / penfor | (| Rees |
| 91 | Krishremitz | Conjunction | | - Later |
| 92 | Horish Knob | Have A. | | Harin |
| 93 | Rajiv | BWSSO/ EE | | 02m |
| 94 | R.W. ZRINATH | BWSSB/EE | | R.KC-S |
| 95 | Angmi | NISER | | Ac |
| 96 | P. Solves | MILBI | | 7 |
| 97 | Savilla | NTS | | See |
| 98 | Servil | MJS | | 81 |
| 99 | Chand Paste | CC. | | - T |
| 100 | Profible | NJSIZI | | Breekel |



Bengaluru Water Supply and Sewerage Project (Stage, W)ting Report

In coordination with NJS Consultants Co. Ltd.

Date: 22-Aug-2017

enue: Cauvery Bhavan 4th Floor Conference Hall

| ŝ/N | Name | Designation/ Organization | Contact Details | Signa- ture |
|------|----------------------|------------------------------|-----------------|----------------|
| 101 | Rojet Kung. | 224 | | y_ |
| 102 | Kajeh Kung. Madhe | RussB. | | |
| 103 | Bhagyala kshi | NISS | | B |
| 104(| garged hava | ess | | Gent |
| 105 | Vaibhar . | NII | | |
| 106 | Shrekman' | BussB | | 2 |
| 107 | M. Jayamma | PS to CE(F) BN SSB | | AD |
| 108 | Sweld Sich | Dec. Exp. | • | 8> |
| 109 | Yogesh Cokler | NJS | | B |
| 110 | ૪ ૭ | ष्ठेव संवद्येव | | مرا |
| 111 | Rajesh.y | Experate. | | ROCK |
| 112 | 2वी | Busse | | |
| 113 | Rayani | RPTCL | | Qu |
| 114 | Nanolini | coorposate | | ne. |
| 115 | 'Thoshi' | BMSSB | L | 3,/ |
| 116 | Doublina | Corporation | | Ben |
| 117 | Rusil | Bemp | | Rr. |
| 118 | Toupti | Boss | | De. |
| 119 | ನಲಾನ | forluter Bond | | (Str. |
| 120 | Lage Series | MG 505 -722 02 50 | | D.) 55° |



Bengaluru Water Supply and Sewerage Project (Stage, W)ting Report

Date: 22-Aug-2017

enue: Cauvery Bhavan 4th Floor Conference Hall

| S/N | Name | (ADesignation/ Organization :) | © Contact Deaths :: (Tel/Email): | . Signa∋ ture |
|-----|---|--|----------------------------------|------------------|
| 121 | Jayesh. S Pagin S.P Sofeste & . f. Sidoppusum. Jayaprallesh Timnegoude | コ・医・ | | 56 : |
| 122 | Pagi S.P. | ARE 258 31-30 (proporter Driver BBMP BBMP | | M. |
| 123 | ವ್ಯಾಕ್ಟಿತ್ವಂತ್ರ .ಕ್ಕೆ. | 52 gl-zn | | |
| 124 | Soldoppesung. | Compositor Donn | | |
| 125 | Jayaprallesh | BBMP | | 70° |
| 126 | Timmegocala | BRMP | 400 | Tour. |
| 127 | | | | |
| 128 | | | | |
| 129 | | | | |
| 130 | | 1.00 | | |
| 131 | | | | |
| 132 | | | | |
| 133 | | | | |
| 134 | | | | |
| 135 | | | | |
| 136 | | | | |
| 137 | | | | |
| 138 | | | | |
| 139 | | | | |
| 140 | | | | |





Bengaluru Water Supply and Sewerage Project (Stage V) ing Report

Date: 22-Aug-2017

enue: Cauvery Bhavan 4th Floor Conference Hall

| S/N | Name* | Designation/ Organization | ©ontact:Details (Tel/E=mail) | Signá- ture |
|-----|-------|------------------------------|---------------------------------|----------------|
| 141 | | | | |
| 142 | | | | |
| 143 | | | | |
| 144 | | | | |
| 145 | | | | |
| 146 | | | | |
| 147 | | | | |
| 148 | | | | |
| 149 | | | | |
| 150 | | | | |
| 151 | | | | |
| 152 | | | | |
| 153 | | | | |
| 154 | | | | |
| 155 | , | | | |
| 156 | | | | |
| 157 | | | | |
| 158 | | | | |
| 159 | | | | |
| 160 | | | | |





Bengaluru Water Supply and Sewerage Project (Stage V)


General


Bangalore is among the fastest growing cities in Asia and one of India's rapidly developing modern urban centers with quality residential complexes; tree lined street corridors, parks, natural valleys and lakes. In spite of its burgeoning growth the city is still attractive for its open parkland environment with naturally undulating topography and water bodies. It is aptly called the "Garden City". As a result of its moderate climate and cosmopolitan nature, the city has attracted people from all over India including pensioners and young professionals alike. It is also home to some of the most high tech industries of India and many multinational information technology companies and the city is often referred to as "Silicon Valley" of India. As a result of growth of information technology companies in the urban agglomeration the habitation started increasing and the cultivation lands are being converted to residential and industrial layouts.

Objective of the Project


The objective of the Project is to provide residents in BBMP area with safe and stable water supply, and sewerage services to meet increasing water demand and the need of environmental improve-ment and to contribute to the promotion of industry. The location of project area is presented in the location map, which covers the jurisdiction of the BWSSB incuding core, ULBs (Urban Local Bodies) and 110 villages, and pipeline routes from the water intake at Cauvery River to the en-trance of BBMP.

Overall Project Scope






| Proposed GLR Capacities and Locations | | | | | |
|---------------------------------------|-----------------------|--------------------------------|---------------------------|--|--|
| SI No | Name of GLR | Proposed GLR Capacity (MLD) | Location of GLR | | |
| 1 | Gottigere GLR | 112.9 | Gottigere Village | | |
| 2 | Doddakannahalli GLR | 48 | Hadosiddapura Village | | |
| 3 | Kadugodi GLR | 48 | Kadugodi Plantation | | |
| 4 | Chokkanhalli | 128 | Chokkanahalli Village | | |
| 5 | Vasudevapura GLR | 64.8 | Harohalli Village | | |
| 6 | Singapura | 40 | Singapura | | |
| 7 | Lingadeeranahalli GLR | 17.8 | Lingadeeranahalli Village | | |



Scope of 110 Villages Sewerage Systems

| - | | STPs | | ISPSs | Pipe Size | Length |
|---------------|-------|---------------|-------|-------------|-------------|--------|
| Zone | (Nos) | (MLD) | (Nos) | (MLD) | (mm) | (km) |
| Bytrayanapura | 4 | 7+6+7+17=37 | 1 | 0.9 | ф300-ф1,000 | 50.3 |
| Mahadevapura | 1 | 15 | 1 | 15.0 | ф300-ф900 | 44.7 |
| Bommanahalli | 2 | 4+5=9 | 1 | 9.0 | ф300-ф1,200 | 65 |
| RR Nagar | 2 | 8+13=21 | 2 | 1.1+1.6=2.7 | ф300-ф700 | 14.8 |
| Dasarahalli | 5 | 10+3+6+4+9=32 | 2 | 0.5+8.1=8.6 | ф300-ф600 | 27.5 |
| Total | 14 | 114 | 7 | 36.2 | - | 202.3 |



Proposed Location of STPs and ISPSs

| Zone | S | TPs . | ISPSs | | |
|-----------------|----------------------|------------------------------------|-------------------|---------------------------------|--|
| ze Zone | Name | Location | Name | Location | |
| | 1.Jakkur | Adjacent Exsting STP Jakkkur | | | |
| Bytrayana | 2. Yelahankakere | Near Yelahanka Lake | 1.Bellahalli | Near Bellhalli Village | |
| pura | 3. Doddabettahalli | Near Attur Lake | | | |
| | 4. Bilishivalli | Near Rampur Lake | | | |
| Mahadev pura | 5. Varthur | Near Varthur Kodi | 2.Hagadur | Near Sammethanahalli Village | |
| Bommana | 6. Pillaganahalli | Near Bilavardahalli Lake | 3.Naganatha | Near Naganathapura Lake | |
| halli | 7. Talaghattapura | Near Nice Road | pura | | |
| | 8. Somapura | Near Somapura Lake | 4.Arehalli | Areahalli Village | |
| R.R.Nagar | 9. Hemigepura | Near Nice Road | 5.Hemmigep ura | Near Varasandra Lake | |
| | 10. Kariobavanahalli | Near Kariobavanahlli Lake | 6.Herohalli | Herohalli Village | |
| _ | 11. Herohalli | ohalli Near Kodihalli Lake | | | |
| Dasara | 12. Hosahalli | Near Kachohalli Lake | 7.Doddabida | | |
| halli | 13. Chikka | Near Chikkabanavar | rkallu | Near Anchepalya Lake | |
| | banavara-2 | Lake | | | |
| | 14. Nagasandra* | Adjacent Exsting STP Nagasandra | | | |



ಬೆಂಗಳೂರು ನೀರು ಸರಬರಾಜು ಮತ್ತು ಒಳಚರಂಡಿ ಮಂಡಳಿ

BANGALORE WATER SUPPLY AND SEWERAGE BOARD

ಬೆಂಗಳೂರು ನೀರು ಸರಬರಾಜು ಮತ್ತು ಒಳಚರಂಡಿ ಯೋಜನೆ (೫ ನೇ ಹಂತ)

BENGALURU WATER SUPPLY AND SEWERAGE PROJECT (Stage -V)

Stakeholder Meeting 22nd/AUGUST/2017

BWSSB / JICA Survey Team


1


Purpose of this Discussion ಯೋಜನೆಯ ಉದ್ದೇಶ


- (1) Provide Information on the JICA assisted Water Supply and Sewerage Project
- Discuss on the Project and to promote understanding /Cooperation by Stakeholders
- ೧) ಜೈಕಾ ನೆರವಿನೊಂದಿಗೆ ನೀರು ಸರಬರಾಜು ಮತ್ತು ಒಳಚರಂಡಿ ಯೋಜನೆಯ ಬಗ್ಗೆ ಮಾಹಿತಿಯನ್ನು ಒದಗಿಸುವದು.
- 9) ಯೋಜನೆಯ ಬಗ್ಗೆ ಅರಿವು, ಮುಂದುವರಿಯುವಿಕೆ ಮತ್ತು ಪಾಲುದಾರರಗೆ ಸಹಕಾರದ ಬಗ್ಗೆ ಚರ್ಚೆ.

.

| Project Group | Project Component | Facilities |
|-----------------------|------------------------------|---|
| JICA Survey | CWSS Stage V | Water Treatment Plant |
| Project | | Transmission Facilities |
| | | City Trunk Main |
| | | Ground Level Reservoir (GLR) |
| | 110 Villages major Sewerage | Bytrayanapura Zone |
| | Facilities (STP, ISPS, Trunk | Mahadevpura Zone |
| | Sewer) | Bommanahalli Zone |
| | | R.R.Nagar Zone |
| | | Dasarahalli Zone |
| BWSSB | CWSS Stage V | Conveyance pipeline |
| Undertaken Project | | Branch Feeding Pipes in the City to share water to Core /ULB |
| | 110 Villages Water Supply | Distribution pipeline and, House |
| | | connections |
| | | Distribution facilities between GLRs |
| | | and OHTs for permanent systems |
| | 110 Villages Sewerage | Lateral sewer and House connection |








| Existing Sewerage Facilities | es and On-going/ Planned Sewerage |
|------------------------------|-----------------------------------|
| Outline of STP | Projects |

| Outline of STP | | | | | | |
|----------------|------------------------|-----|-----------------------------------|--|--|--|
| | | | | | | |
| 1 | K&C Valley_ | 308 | Activated Sludge Process (ASP) | | | |
| 2 | V Valley | 180 | Trickling Filter (TF) | | | |
| 3 | Hebbal | 60 | ASP | | | |
| 4 | Raja Canal -i | 40 | Extended Aeration | | | |
| | Raja Canal -II | 40 | (EA) | | | |
| 5 | Cubbon Park | 1.5 | Membrane Bio Reactor | | | |
| 6 | Labaugh | 1.5 | EA | | | |
| 7 | Kempbudhi | 1 | EA | | | |
| 8 | (ITI Colony) | | 1 | | | |
| 9 | Mailasandra | 75 | EA | | | |
| 10 | Kadabesanahalli | 50 | EA | | | |
| 11 | Nagasandra-I | 20 | EA | | | |
| | Nagasandra-II | 20 | | | | |
| 12 | K.R. Purum | 20 | UASB | | | |
| 13 | Yelahanka | 10 | ASP+Filtration | | | |
| 14 | Jakkur | 10 | UASB+EA | | | |
| 15 | Chikkabanavar | 5 | SBR | | | |
| 16 | Kadugodi | 6 | SBR | | | |
| 17 | Horamavu | 20 | SBR | | | |
| 18 | Ye!lamallappche tti | 15 | SBR | | | |
| 19 | Doddabele | 20 | SBR | | | |
| 20 | Belanduramanik ere | 90 | ASP | | | |
| 21 | Kengerl | 80 | ASP | | | |

Treated Sewage Discharge Standard

| ilijanaan | | Newstandards desired nameros |
|----------------------------|---------------------------|---------------------------------|
| Нq | 5.5 to 9.00 | 6.5 to 9.00 |
| BODS | Not more than 20 mg/1 | Not more than 10 mg/l |
| COD | Not more than 250 mg/l | Not more than 50 mg/l |
| ss | Not more than 30 mg/l | Not more than 10 mg/l |
| TK-N | Not more than 100 mg/l | Not more than 10 mg/las T-N |
| NH4·N | Not more than 50 mg/l | Not more than 5 mg/1 |
| Nitrate Nitrogen | Not more than 10 mg/l | N.A. |
| Dissolved Phosphate | Not more than 5 mg/l | N.A. |
| PO4-P | N.A. | Not more than 2 mg/l |
| Fecal Coliform | N.A. | 100 MPN/ 100ml |
| Total Residual Chlorine | Not more than 1 mg/1 | N.A. |

N.A.: Not Applicable



Projects Needs and Implementation Arrangements for Proposed **Projects**

ಉದ್ದೇಶಿತ ಯೋಜನೆಯ ಬೇಡಿಕೆ ಮತ್ತು ಚಾಲನೆಗೆ ಸಲಕರಣೆ

- (1) General Project Needs ಯೋಜನೆಗೆ ವಾಡಿಕೆಯ ಅಗತ್ಯ 1) To meet the increasing water demand and need of sanitation improvement ೧) ನೀರು ಮತ್ತು ನಿರ್ಮಲೀಕರಣದ ಬೇಡಿಕ ಮತ್ತು ಅಗತ್ಯತೆಯ ಹೆಚ್ಚುದರಿಯನ್ನು ಸರಿದೂಗಿಸುವದು
 - To use limited groundwater effectively avoiding over exploitation ಅಂತರ್ಜಲವನ್ನು ತುಂಬಾ ಪ್ರಜ್ಞಾಪೂರ್ವಕವಾದ ಬಳಕ ಹಾಗು ದುರ್ಲಾಭವನ್ನು ತಡೆಯುವದು.
- (2) **Specific Project Needs and Benefits**
 - Specific Project Needs and Benefits ಯೋಜನೆಯ ನಿರ್ದಿಷ್ಟ ಉದ್ದೇಶ ಮತ್ತು ಲಾಭ Water demand for the BBMP area can be satisfied up to 2034 in provision of CWSS Stage V Project. Therefore, satisfactory / continuous water supply can be practiced through the cooperation by all stakeholders. Uniform water supply services can be provided for entire BBMP area Profile of the city with environmental soundness can be enhanced. Investment in BBMP area both by domestic and foreign companies will be promoted.

- ೧) ಕಾವೇರಿ ೫ ನೇ ನೇ ಹಂತ ಯೋಜನೆಯಿಂದ ಬಿ ಬಿ ಎಂ ಪಿ ಪ್ರದೇಶಕ್ಕೆ ೨೦೩೪ ಇಸವಿವರೆಗೆ ನೀರಿನ ಬೇಡಿಕೆಯನ್ನು ಪೂರ್ಕೈಸುವುದು. ಇದರಿಂದ ಸಂತೃಪ್ತಿಯಾಗಿ ನಿರಂತರ ನೀರು ಸರಬರಾಜನ್ನು ಪಾಲುದಾರರ ಸಹಾಯದಿಂದ ಮಾಡುವುದು
- ೨) ನೀರು ಸರಬರಾಜನ್ನು ಬಿ ಬಿ ಎಂ ಪಿ ಪ್ರದೇಶಕ್ಕೆ ಸಮನಾಗಿ ಪೂರೈಕೆ
- a) ನಗರದ ಭೌಗೋಳಿಕ ಆದಾರದಂತೆ ಪರಿಸರಕ್ಕೆ ತಕ್ಕಂತೆ ವಿಸ್ತರಿಸುವುದು. ಬಿ ಬಿ ಎಂ ಪಿ ಪ್ರದೇಶಕ್ಕೆ ಸ್ಥಳೀಯ ಮತ್ತು ಹೊರದೇಶದ ಕಂಪನಿಗಳನ್ನು ಆಕರ್ಷಿಸಿ ನಗರವನ್ನು ಮೇಲ್ದರ್ಜೆಗೆ ಕೊಂಡೊಯುವುದು.⁹


Water Demand for 110 villages


(1) Water Supply Water Demand of 110 villages


| Sn | Name of Zone | Area (in population Projected Population Sq.Km.) as per | | lation (Pers | on) | Water Demand (MLD) | | | | | |
|------|-------------------------------|---|-----------------|---------------|-----------|----------------------|-----------|-----------|------|---------|------|
| | | | census | 2019 | 2024 | 2034 | 2049 | 2019 | 2024 | 2034 | 2049 |
| 1 | Bytrayanpura (26 Villages) | 55,0 | 243,210 | 342,710 | 416,991 | 593,904 | 941,116 | 61 | 74 | 106 | 168 |
| 2 | Mahadevpura (23 Villages) | 51.0 | 225,491 | 317,709 | 386,568 | 550,573 | 872,455 | 57 | 69 | 98 | 156 |
| 3 | Bommanahalli (33 Villages) | 64.3 | 285,174 | 401,838 | 488,932 | 696,365 | 1,103,482 | 72 | 87 | 124 | 197 |
| 4 | R.R Nagar (17 Villages) | 31.4 | 165,763 | 313,233 | 379,077 | 529,350 | 824,182 | 56 | 68 | 95 | 147 |
| 5 | Dasarahalli (11 Villages) | 23.5 | 193,656 | 272,877 | 332,030 | 472,882 | 749,344 | 49 | 59 | 84 | 134 |
| | | 225.2 | 1,113,294 | 1,648,367 | 2,003,598 | 2,843,074 | 4,490,579 | 294 | 358 | 508 | 802 |
| | Total | | 1,110,000 | 1,650,000 | 2,000,000 | 2,840,000 | 4,490,000 | 290 | 360 | 510 | 800 |
| Wate | r Source | | HILLIAN IZAN EK | | 41.4. | \$110.000 in 100.000 | | HALL LIES | | \$10000 | |
| | Cauvery | | | 3351 111 15 K | | | | | 775 | 775 | 775 |
| | Ground water | HAMBER LINE | | | | | | | 100 | 100 | 100 |
| | Balance | | | | | | | | 517 | 367 | 73 |
| | | | | | | | | | | | 10 |


ಕಾವೇರಿ ಯೋಜನೆಯ 5 ನೇ ಹಂತದ ಕಾಮಗಾರಿ Scope of Work for CWSS Stage V

- WTP ನೀರು ಸಂಸ್ಕರಣಾ ಘಟಕ
- Pump Stations and CWR's
- ಯಂತ್ರಾಗಾರಗಳು ಮತ್ತು ಕಾವೇರಿ ನೀರು ಶೇಖರಣಾ ತೊಟ್ಟಿಗಳು
- Transmission Pipeline
- ನೀರು ಸಾಗಣೆ ಕೊಳವೆ ಮಾರ್ಗ
- City Trunk Main
- ನಗರದ ಪ್ರಮುಖ ಮುಖ್ಯ ಕೊಳವೆ
- City Reservoirs (GLR)
- ನಗರದಲ್ಲಿರುವ ಜಲಾಶಯಗಳು
- STP's and ISPS in 110 villages ೧೧೦ ಹಳ್ಳಿಗಳ ವ್ಯಾಪ್ತಿಯಲ್ಲಿರುವ ತ್ಯಾಜ್ಯ ನೀರು ಸಂಸ್ಕರಣಾ ಮತ್ತು ಯಂತ್ರಾಗಾರಗರು
- Trunk Sewers in 110 villages
- ೧೧೦ ಹಳ್ಳಿಗಳಲ್ಲಿ ಪ್ರಮುಖ ದೊಡ್ಡ ಗಾತ್ರದ ಒಳಚರಂಡಿ ಕೊಳವೆಗಳು











ಉದ್ದೇಶಿತ ನೆಲಮಟ್ಟದ ಜಲಾಶಯಗಳು ಹಾಗೂ ಸ್ಥಳ Proposed Ground Level Reservoirs(GLR's)

| | Proposed | GLR Capacities and | Locations |
|--|-----------------------|---|---|
| ಕ್ರ ನಂ ಜಲಾಶಯದ ಹೆಸರು SI No Name of GLR | | ಸಾಮರ್ಥ್ಯ Proposed GLR Capacity (ML) | ನೆಲಮಟ್ಟದ ಜಲಾಶಯದ ಸ್ಥಳ Location of GLR |
| 1 | Gottigere GLR | 96.8 | Gottigere Village |
| 2 | Doddakannahalli GLR | 87 | Hadosiddapura Village |
| 3 | Kadugodi GLR | 85 | Kadugodi Plantation |
| 4 | Chokkanhalli | 128 | Chokkanahalli Village |
| 5 | Vasudevapura GLR | 17 | Harohalli Village |
| 6 | Singapura | 24 | Singapura |
| 7 | Lingadeeranahalli GLR | 52 | Lingadeeranahalli Village |







19


3) Plan of Sewage Treatment Plant
Application of EA process with chlorination of effluent is recommended for all 14 STPs. For sludge treatment, thickening and mechanical dewatering process shall be adopted. But, in case of the STPs with less than 10 MLD capacity, thickening process may be omitted depending on types of dewatering machine


| | Naa | Flow (MI D) | Flow (MI D) Treatmen | | Sludge |
|---------------|--|---------------|----------------------|-----------|----------------------------|
| Zone | Name | Flow (MLD) | Sewage | Sludge | Disposat/ Utilization |
| | Jakkur Changed from Kattigenahalli | 7.0 | EA + CHL | (TH) + DW | Fertilizer for farmland |
| Bytrayanapura | 2. Yelahankakere | 6.0 | ditto | ditto | ditto |
| | 3. Doddabettahalfi | 7.0 | ditto | ditto | ditto |
| | 4. Bilishivalli | 17.0 | ditto | TH + DW | ditto |
| Mahadovpura | 5. Varthur | 15.0 | ditto | ditto | ditto |
| | 8-Naganathapura | 9,0 | Changed to ISPS | | |
| Bommanahalli | 7. Pillaganahalli | 4.0 | ditto | (TH) + DW | ditto |
| | 8. Talaghattapura | 5,0 | ditto | ditto | ditto |
| D.D. N | 9. Somapura | 8.0 | ditto | ditto | ditto |
| R.R.Nogar | 10. Hemigepura (&11) | 13.0 (Merged) | ditto | TH + DW | ditto |
| | 13. Kariobavanahalli | 10.0 | ditto | ditto | ditto |
| | 14. Herohalil | 3.0 | ditto | (TH) + DW | dillo |
| Dasarahalli | 15, Hosahalli | 6.0 | ditto | ditto | dillo |
| | 16. Chikkabanavara-2 | 4.0 | dillo | ditto | ditto |
| | 12. Nagasandra* | 9.0 | ditto | ditto | ditto |
| Total | 14 STPs | 114 MLD | EA + CHL | - | - |


Note: EA: Extended Aeration Process, CHL: Chlorination, TH: Thickener, (): Possibility of Cancel, DW: Mechanical Dewatering














Construction Cost for the Project (JICA funded)

Unit: Crore

| No. | Project Budget | | | | | |
|-----|---------------------------|---------------------------------------|--------|--|--|--|
| NO. | | Component | Cost | | | |
| 1 | Water Supply | Component | 31,825 | | | |
| 2 | Sewerage Con | nponent . | 8,819 | | | |
| | Total Base C Excluded) | cost of the Project (Land Acquisition | 40,644 | | | |
| | | | | | | |
| | Funding Patter | · | | | | |
| | ЛСА | - 85 % | | | | |
| | GOK | - 7.5 % | | | | |
| | BWSSB | - 7.5 % | | | | |

Associated Projects of BWSSB

| No | Project | Funding Source | Implementation Period | Detailed information |
|-----|---|----------------------------|--|----------------------|
| 1. | 110 Villages Water Supply | GOK (67%) + BWSSB (33%) | 24 Months | GBWASP funds |
| 2. | UFW Reduction | GOK (67%) + BWSSB (33%) | 36 Months (Construction) + 5 years Maintenance | GBWASP funds |
| 3. | 110 Villages Sewerage: Lateral sewers and House connections | BWSSB | Lateral sewers – 36 months House connections as per requests | BCC funds |
| 4.1 | Stage V Project Conveyance pipeline | BWSSB | 24 Months | Already awarded |
| 4.2 | Stage V Project Branch Feeding Pipes for sharing water from Stage V to Core & ULBs | BWSSB | 36 Months | |

27

ಸಮಾಲೋಚಕರು ಸೇವೆಯ ಗುರಿ **Scope of Consultancy Services**

- The Design and Project Management Consultants will be appointed
- as per the procurement guidelines of JICA ಯೋಜನೆಯ ವಿನ್ನಾ ಸ ಮತ್ತು ಕಾರ್ಯನಿರ್ವಣೆಗೆ ಜೈಕಾ ಮಾರ್ಗದರ್ಶದದ ಆಧಾರದಂತೆ ಸಮಾಲೋಚಕರು ನೇಮಕ ಮಾಡಿ ಕೊಳ್ಳುವುದು
- The Consultants will be responsible for
- ಸಲಹೆಗಾರರ ಹೊಣೆಗಾರಿಕೆಗಳು
 - Design and Engineering
 - ವಿನ್ನ್ಯಾಸ ಮತ್ತು ತಾಂತ್ರಿಕತೆ
 - Tendering assistance for procurement ಖರೀದಿಸಲು ದರ್ಖಾಸ್ತುವಿಗೆ ಸಹಾಯ
 - Project Management ಯೋಜನೆಯ ಕಾರ್ಯನಿರ್ವಹಣಿ
 - Construction supervision and Quality Control ಕಾಮಗಾರಿಯ ವೀಕ್ಷಣೆ ಮತ್ತು ಗುಣಮಟ್ಟ
 - Commissioning and Testing ಪರೀಕ್ಷೆ ಮತ್ತು ಕಮಿಷನಿಂಗ್

ಸಲಹಾ ಸೇವೆಯ ಮಾಹಿತಿ Input of Consultancy Services

- Period of Consultancy Services 70 months
- ಸಲಹಾ ಸೇವೆಯ ಅವಧಿ-೭೦ ತಿಂಗಳು
- Input of Experts ತಜ್ಞರ ಬಳಕೆ
 - International Experts 492 manmonths
 - ಅಂತಾರಾಷ್ಟ್ರೀಯ ತಜ್ಞರು-೪೯೨ ತಿಂಗಳದಿನ
 - National Experts 2515 manmonths
 - ರಾಷ್ಟ್ರೀಯ ತಜ್ಞರು-೨೫೧೫ ತಿಂಗಳದಿನ
 - Supporting Staffs 2112 manmonths
 - ಅಭಿಯಂತರರು -೨೧೧೨ ತಿಂಗಳದಿನ

2

Operation and Maintenance of Water Supply and Sewerage Facilities


ನೀರು ಸರಬರಾಜು ಮತ್ತು ಒಳಚರಂಡಿಯ ಕಾರ್ಯಾಚರಣೆ ಮತ್ತು ನಿರ್ವಹಣಿ


The appointed Contractors will be responsible for 10 years of O&M for the water supply and sewerage facilities

ನಿಯೋಜಿತ ಗುತ್ತಗೆದಾರರಿಗೆ ನೀರಿನ ಮತ್ತು ಒಳಚರಂಡಿಯ ಸೌಲಭ್ಯವನ್ನು ೧೦ ವರ್ಷದವರಗೆ ಕಾರ್ಯಾಚರಣೆ ಮತ್ತು ನಿರ್ವಹಣಿಯ ಜವಾಬ್ದಾರಿಯಾಗಿರುತ್ತದೆ

The distribution systems and sewerage network O&M will be undertaken by BWSSB

ಜಲಮಂಡಳಿಯಿಂದ ವಿತರಣಾ ವ್ಯವಸ್ಥೆ ಮತ್ತು ಒಳಚರಂಡಿ ಜಾಲದ ಕಾರ್ಯಾಚರಣೆ ಮತ್ತು ನಿರ್ವಹಣಿ ಮಾಡಲಾಗುತ್ತದೆ





Environmental and Social Considerations

ಸಾಮಾಜಿಕ ಮತ್ತು ಪರಿಸರದ ಪರಿಗಣನೆ

(1) Baseline Situation ಪ್ರಾರಂಭಿಕ ಸಂದರ್ಭ

- 1) Site Description ಜಾಗದ ವಿವರಣೆ
- WTP / Pump Stations: Existing BWSSB's Facility Areas
 ನೀರು ಸಂಸ್ಕರಣಾ ಘಟಕ / ಯಂತ್ರಾಗಾರಗಳು ಪ್ರಸ್ತುತ ಜಲಮಂಡಳಿಯ ಸೌಲಭ್ಯದ ಪ್ರದೇಶ
- Clear Water Transmission: Existing BWSSB's Pipeline Road ನಿಖರ ನೀರು ಸಾಗಿಸುವಿಕೆ ಕೊಳವೆ ಮಾರ್ಗ - ಪ್ರಸ್ತುತ ಜಲಮಂಡಳಿಯ ಕೊಳವೆ ಮಾರ್ಗ ರಸ್ತ
- City Trunk Main: Public Roads in Built-up Areas ನಗರದ ಪ್ರಮುಖ ಮುಖ್ಯ ಕೊಳವೆ – ಅಭಿವೃದ್ಧಿ ಹೊಂದಿದ ಪ್ರದೇಶದ ರಸ್ತಗಳು
- GURS Vacantiands of Government (Gov BBMP, BDA) Lands in Built-up Areas ನಲಮೆಟ್ಟಿದ ಜಲಾಶಯ: ಸರ್ಕಾರದ ಖಾಲಿ ಜಾಗ (ಬಿ ಬಿ ಎಂ ಪಿ, ಬಿ ಡಿ ಎ) ಅಭಿವೃದ್ಧಿ ಹೊಂದಿದ ಪ್ರದೇಶದ ಖಾಲಿ ಜಾಗ

Sewerage Project for 110 Villages: ೧೧೦ ಹಳ್ಳಿಗಳಲ್ಲಿ ಒಳಚರಂಡಿ ಯೋಜನೆ

- STRS://ISRSs: Vacantillands:of:Government (GoX, BBMP; BDA) Lands in Built-up Areas ಸರ್ಕಾರದ ಖಾಲಿ ಜಾಗ ಅಭಿವೃದ್ಧಿ ಹೊಂದಿದ ಪ್ರದೇಶದ ಖಾಲಿ ಜಾಗ
- Main Sewers: Public Roads and Along the Drain in Built-up Areas ಮುಖ್ಯ ಒಳಚರಂಡಿ ಕೊಳವೆ : ಸಾರ್ವಜನಿಕ ರಸ್ತ ಮತ್ತು ಸಮಾನಂತರ ಚರಂಡಿಯ ಉದ್ದಗಲಕ್ಕೂ.
- 2) EIA Requirement EIA ಅವಶ್ಯಕತೆ
- The projects (CWSS Stage V, Sewerage project for 110 Villages) do not require EIA according to EIA Notification 2006. ಯೋಜನೆಗಳು (ಕಾವೇರಿ ನೀರು ೫ ನೇ ಹಂತ, ಒಳಚರಂಡಿ ಯೋಜನೆ ೧೧೦ ಹಳ್ಳಿಗಳಿಗೆ) EIA ಅಭಿಯೋಜನೆಯ ೨೦೦೬ ರಂತೆ ಅವಶ್ಯಕತೆಯಿರುವುದಿಲ್ಲ

(3) Recommended Mitigation Measures

- Coordination mechanism with Stakeholders
- Appropriate traffic management at pipe laying works
- Incorporation of requirements for mitigation measures into bidding documents, contract documents
- Examination of Contractor's construction plan, O& M plan
- Environmental monitoring (Dust, noise, water quality, odour)
- Climate change: Selection of higher efficient pump units,
- Recommendation of future installation of biogas recovery system (Biogas power generation, incineration, etc.)

(4) Land Acquisition ಭೂಮಿಗಳಿಗೆ


The project sites to require Land Acquisition or Land Transfer: ಯೋಜನಾ ಜಾಗದ ಅಗತ್ಯಗೆ ದರ್ಖಾಸ್ತುವಿಗೆ ಅಥವಾ ವರ್ಗಾವಣೆ

- CWSS Stage V Project: GLRs ಕಾವೇರಿ ೫ ನೇ ಹಂತ ಯೋಜನೆ : ನೆಲಮಟ್ಟದ ಜಲಾಶಯ
- Sewerage Project for 110 Villages: STPs and ISPSs ೧೧೦ ಹಳ್ಳಿಗಳಿಗೆ ಒಳಚರಂಡಿ ಕಾಮಗಾರಿ
- All project sites located on government lands (GoK, BBMP, BDA) ಎಲ್ಲಾ ಒಳಚರಂಡಿ ಯೋಜನೆಯ ಜಾಗವು ಸರ್ಕಾರಿ ಪ್ರದೇಶವಾಗೇರಬೇಕು
- Resettlement is not required.
- Land Transfer of ALL Project Sites to BWSSB is required before implementation of the projects.
- ಯೋಜೆನೆಯ ಪ್ರಾರಂಭಿಕ ಹಂತದಲ್ಲೇ ಎಲ್ಲಾ ನಿವೇಶನಗಳು ಜಲಮಂಡಳಿಗೆ, ವರ್ಗಾವಣೆಯಾಗಬೇಕು

37

Implementation Plan

ಕಾರ್ಯಾಚರಣೆ ರಚನೆ



Institutional Development

ಸಂಸ್ಥೆಯ ಅಭಿವೃದ್ಧಿ

ಪಾಲುದಾರರಿಂದ ಅಪೇಕ್ಷ Expectations from the Key Stakeholders

Revenue Department ಕಂದಾಯ ಇಲಾಖೆ

Govt Land to be Transferred to BWSSB With in Time Frame. ಕಾಲಾವಧಿಯೊಳಗೆ ಸರ್ಕಾರೀ ಜಾಗವನ್ನು ಜಲಮಂಡಳಿ ವರ್ಗಾಯಿಸುವುದು

BDA ಬೆಂಗುಳೂರು ಅಭಿವೃದ್ಧಿ ಪ್ರಾಧಿಕಾರ

BDA Land to be transferred to BWSSB with in Time Frame. ಕಾಲವಾದಿಯೊಳಗೆ ಬಿ ಡಿ ಎ ಯಿಂದ ಜಲಮಂಡಳಿಗೆ ಜಾಗವನ್ನು ವರ್ಗಾಯಿಸುವುದು

Some of the identified land for immediate attention. ಗುರುತಿಸುವ ಜಾಗವನ್ನು ತಕ್ಷಣ ಗಮನ ಹರಿಸುವುದು

- STP Land Near Talaghattapura Survey No.41 of Thalaghattapura Village ತಲಘಟ್ಟಪುರ ಗ್ರಾಮದೊಳಗಿನ ತಲಘಟ್ಟಪುರ ಸರ್ವೇ ನಂ ೪೧ ಜಾಗವನ್ನು ತ್ಯಾಜ್ಯನಿರು ಸಂಸ್ಕರಣೆ ಘಟಕ
- STP Land Near Sompura Lake Survey No 2,3(P) at Somapura Village
- ಸರ್ವೇ ನಂ ೨,೩ (ಪಿ) ನಲ್ಲಿ ಸಂಸ್ಕರಣೆ ಘಟಕ ಸೋಮಪುರ ಗ್ರಾಮ
- ISPS Land Near Varasandra Lake Survey No.25 at Varasandra Village
- ವಾರಸಂದ್ರ ಗ್ರಾಮ ಸರ್ವೇ ನಂ ೨೫ ವಾರಸಂದ್ರ ಕೆರೆ ISPS ಜಾಗ

41

ಪಾಲುದಾರರಿಂದ ಆಪೇಕ್ಷ ಮುಂದುವರಿದಿದೆ Expectations from the Key Stakeholders (Cont..)

Permission to provide Power Supply to STP's ,ISPS, Pumping station at GLR's ವಿದ್ಯುತ್ ಸಂಪರ್ಕದನ್ನು STP ಮತ್ತು ISPS ಯಂತ್ರಾಗಾರಗಳಿಗೆ ಒದಗಿಸಲು ಅನುಮತಿ

- Power Requirement for ISPS / STP: 1,14,884 Kwh / day ವಿದ್ಯುತ್ ಅಗತ್ಯತೆ ISPS ಗೆ ಪ್ರತಿದಿನ 1,14,884 Kwh /day
- Power Requirement for Pumping Station GLR: 329 Kwh / day – ಯಂತ್ರಾಗಾರಕ್ಕೆ ವಿದ್ಯುತ್ ಬೇಡಿಕೆ 329 Kwh ಪ್ರತಿದಿನ

Permission to provide Power Supply to WTP in T K Halli, Pumping station's ಟಿ ಕೆ ಹಳ್ಳಿ ಯಂತ್ರಾಗಾರಕ್ಕೆ ನೀರು ಸಂಸ್ಕರಣೆ ಫಟ್ಟಕ್ಕಕ್ಕೆ ವಿದ್ಯುತ್ ಸರಬರಾಜುವಿಗೆ ಅನುಮತಿ

- Power Requirement for Pumping Station at T K Halli :3,36,346 Kwh/day ಯಂತ್ರಾಗಾರಕ್ಕೆ ವಿದ್ಯುತ್ ಬೇಡಿಕೆ ಟಿ ಕೆ ಹಳ್ಳಿ ಘಟ್ಟಕ್ಕಕ್ಕೆ3,36,346 KWH ಪ್ರತಿದಿನ
- Power Requirement for Pumping Station at Harohalli: 3,93,101 Kwh/day – ಯಂತ್ರಾಗಾರಕ್ಕೆ ವಿದ್ಯುತ್ ಬೇಡಿಕೆ ಹಾರೋಹಳ್ಳಿ ಘಟ್ಟಕ್ಕಕ್ಕೆ3,93,101 Kwh ಪ್ರತಿದಿನ
- Power Requirement for Pumping Station at Tataguni: 3,87,960 kwh/day ಯಂತ್ರಾಗಾರಕ್ಕೆ ವಿದ್ಯುತ್ ಬೇಡಿಕೆ ತಾತಗುಣಿ ಫಟ್ನಕ್ಕಕ್ಕೆ:3,87,960 kwh ಪ್ರತಿದಿನ
- Power Requirement for WTP: 70666 KWH/day ವಿದ್ಯುತ್ ಬೇಡಿಕ ಸಂಸ್ಕರಣೆ ಘಟ್ಟಕ್ಕಕ್ಕೆ 70666 Kwh

ಪಾಲುದಾರರಿಂದ ಆಪೇಕ್ಷ ಮುಂದುವರಿದಿದೆ Expectations from the Key Stakeholders (Cont..)

- Pollution Control Board ಮಾಲಿನ್ಯ ನಿಯಂತ್ರಣ ಮಂಡಳಿ Permission for construction STP's near by lake as per Govt Direction held 11-1-2017 ಕೆರೆಯ ಹತ್ತಿರದಲ್ಲಿ ತ್ಯಾಜ್ಯನಿರು ಸಂಸ್ಕರಣೆ ಘಟ್ರಕ್ಕದ ಕಾಮಗಾರಿ ಮತ್ತು ಕೊಳವೆಮಾರ್ಗ ಅಳವಡಿಸಲು ಸರ್ಕಾರದ ನಿರ್ದೇಶನದಂತೆ ದಿನಾಂಕ 11-1-2017 ರ ಆದಾರದಂತಿರುತ್ತದೆ
- Traffic Police ಟ್ರಾಫಿಕ್ ಪೊಲೀಸ್ Permission for Traffic diversion ಟ್ರಾಫಿಕ್ ಬದಲಾಯಿಸಲು ಅನುಮತಿ
- ಟ್ರಾಫಿಕ್ ಬದಲಾಯಿಸಲು ಅನುಮತಿ

 LCDA
 - Permission to lay the pipe line and construct the STP near by lake as per Govt Direction held 11-1-2017 ಕೆರೆಯ ಹತ್ತಿರದಲ್ಲಿ ತ್ಯಾಜ್ಯನಿರು ಸಂಸ್ಕರಣೆ ಘಟ್ಟಕ್ಕದ ಕಾಮಗಾರಿ ಮತ್ತು ಕೊಳವೆಮಾರ್ಗ ಅಳವಡಿಸಲು ಸರ್ಕಾರದ ನಿರ್ದೇಶನದಂತೆ ದಿನಾಂಕ 11-1-2017 ರ ಆದಾರದಂತಿರುತ್ತದೆ
- Elected Representative's Cooperation for Implementation of the project and make the people aware of the benefits of the project ಚುನಾಯಿತ ಪ್ರತಿನಿಧಿ ಯೋಜನೆಯನ್ನು ಕಾರ್ಯಗತಗೊಳಿಸಲು ಸಾರ್ವ ಜನಿಕರಿಗೆ ಯೋಜನೆಯ ಉಪಯುಕ್ತತೆಯ ಬಗ್ಗೆ ಅರಿವು ಮೂಡಿಸಲು ಸಹಕಾರ ಕೋರಲಾಗಿದೆ

43

ಪಾಲುದಾರರಿಂದ ಅಪೇಕ್ಷೆ ಮುಂದುವರಿದಿದೆ Expectations from the Key Stakeholders (Cont...)

Citizens of the 110 villages area: ೧೧೦ ಹಳ್ಳಿಯ ಪ್ರದೇಶದ ನಾಗರಿಕರು

Co-operation is requested from the Citizens of the 110 villages area who will be the main Stake Holder for this project. The project is going to improve the water and sanitation facilities in the 110 villages area.

೧೧೦ ಹಳ್ಳಿಗಳಲ್ಲಿರುವ ನಾಗರಿಕರು ಪ್ರಮುಖ ಪಾಲುದಾರರಾಗಿದ್ದು ಇವರ ಸಹಕಾರವನ್ನು ಕೋರಲಾಗಿದೆ. ಈ ಯೋಜನೆಯಿಂದ ನೀರಿನ ಮತ್ತು ಒಳಚರಂಡಿ ಸೌಲಭ್ಯವು ೧೧೦ ಹಳ್ಳಿ ಪ್ರದೇಶಕ್ಕೆ ದೊರಕುವುದರಿಂದ ಇದು ಅವರಿಗೆ ತುಂಬ ಉಪಯುಕ್ತವಾಗಿಲಿದೆ

The cooperation of the citizens are critical for the success of the project.

ಈ ಯೋಜನೆಯೇ ಯೆಶಸ್ವಿಗೆ ನಾಗರಿಕರ ಸಹಕಾರ ಪ್ರಮುಖವಾಗಿರುತ್ತದೆ

44

Thank You ದಂದನೆಗಳು

45

ಯೋಜನೆಯದ ವ್ಯತಿರಿಕ್ತ ಪರಿಣಾಮಗಳು

(2) Potential Adverse Impacts by the Projects

Both CWSS Stage V Project and Sewerage Project for 110 <u> Villages : ಕಾವೇರಿ ೫ ನೇ ಹಂತ ಮತ್ತು ೧೧೦ ಹಳ್ಳಿಗೆ ಒಳಚರಂಡಿ</u>

- Social infrastructure / service: Impacts on underground utilities, traffic ಸಾಮಾಜಿಕ ಮೂಲಬೂತ ಸೌಕರ್ಯಗಳು/ಸೇವೆ : ಬೂಮಿಯೊಳಗಿನ ಸೌಕರ್ಯಗಳ ಮೇಲೆ ವರಿದಾಮ ವಾಹನದಟ್ಟಣೆ Occupational health & safety: Impacts on work environment ಉದ್ಯೋಗದಾರರ ಅರೋಗ್ಯ ಮತ್ತು ರಕ್ಷಣೆ : ಕೆಲಸದ
- Water pollution: Water pollution due to malfunction of facilities ನೀರಿನ ಮಾಲಿನ್ನತ ಸೌಲಭ್ಯತಯಿಂದ ನೀರಿನ
- Waste (Excavation soil, treated sludge) ತ್ಯಾಚ್ಚಿ (ಮಣ್ಣಿನ ಆಗತ, ಶುದ್ಧಿಕರಿಸಿದ ತ್ಯಾಚ್ಚಿ) Noise: Noise due to construction equipment, pump operation ಶಬ್ದ ಮಾಲಿನ್ಯ : ಕಾಮಗಾರಿ ಸಾಮಗ್ರಿಗಳಿಂದ ಮತ್ತು ಯಂತ್ರಗಳ ಚಾಲನೆಯಿಂದ
- Accidents: Accidents due to construction and operation ಅಪಘಾತ : ಕಾಮಗಾರಿ ಮತ್ತು ಕಾರ್ಯನಿರ್ವಹಣೆಯಿಂದ
- Climate change (Generation of GHGs): due to consumption of electricity ವಾಹಾವರಣ ಬದಲಾವಣೆ (Generation of GHGs) ವಿದ್ಯುತ್ಮಕ್ತಿ ಬಳಿಕೆಯಿಂದ

Sewerage Project for 110 Villages:

• Odour: due to treatment and transport of sludge ವಾಸನೆ : ಸಂಸ್ಕರಣೆ ಮತ್ತು ಕೆಸರು ಸಾಗಾಣಿಕೆಯಿಂದ

46

Approach to Institutional Development

- Situational Analysis: Review, Feedback, Analysis and validation of "AS IS" situation of BWSSB encompassing its Plans, Policies, Management Systems, Organizational Structure, Human Resources, other resources, Work Environment etc.
- Review of Vision, mission, mandate and plans/targets of BWSSB, emerging external developments, public demand etc.
- · Projection of main attributes of a TO BE State for BWSSB
- Assessment of gaps in present (AS IS) and desired (TO BE) scenario
- · Development of strategies to bridge the gap
- Development of action plans with resource requirements
- Implementation Plan
- · Monitoring, Evaluation, Feedback and Integration Plan

47



Cauvery Water Supply and Sewerage Project (Stage V)

Bangalore Water Supply and Sewerage Board

In Coordination with NJS Consultants Co. Ltd.

| | | Minutes of Discussi | ons | |
|----|--|--|--|--|
| F | Purpose/Objective | Stakeholder Meeting | | |
| | Meeting Date | 22 nd August 2017 | | 11:00 - 13:30 |
| Ī | Venue | BWSSB Auditorium, 4th floor | eporter Name | Mr.Yoshihiro Kirishima |
| | Attendees | Stakeholders (list attached): 125 p | persons | |
| D | ocuments | | | |
| | Meeting Notice | | | |
| | Meeting Agenda | | | |
| | Short Write-up on the | Project | | |
| | Project Presentation | 4 | | |
| | Topics | Actions / | Decisions | |
| 2. | Explanation of the Project | all the participants and provided a Presentation on the Project was BWSSB | - | |
| 3. | Clarification & recommendation on proposed project | Following recommendations are (1) Karnataka State Pollution Control It was suggested to explore with Private Partnership like BBMP area. This is mainly Care should be taken that unalas / Storm Water Drains KSPCB informed that all pathe project (2) Bangalore Development Authoric Engineer It was conveyed that BDA implementation of the Project (3) Corporator, Ward No 196 (110) Welcomed the decision to take Sanitary problem to be attended at the All the road restoration work be taken up on priority. Better coordination is required Departments (4) Corporator, Ward No 1 (110 Villowelcomed the decision to take Piped water Supply to be presented. | the possibility of set the possibility of set and the possibility of set and the possibility of set and the possible support will an and the possible support will assist the possible support will extend all assist the possible support will extend all assist the possible support will extend all assist the project will ages), Mr K Somake up the project in the project will ages), Ms Chandran ake up the project | etting up of STP Courses etc in the ity of land issued not diverted into the extended for ented by Chief estance for smooth mashekhar emplementation to and Government to the course of the extended for smooth and Government to the course of the extended for smooth and Government to the course of the extended for |

- The present water supply is from Bore wells which are not reliable and frequenty under repair. (5) Corporator, Ward No 192 (110 Villages), Mr. Anjanappa Welcomed the decision to take up the project Water problem to be attended on priority Actual start of the works to be intimated in advance Corporator, Ward No 14 (110 villaged), Mr Narasimha Naidu Water supply to be provided on priority. Requested to speed up the project implementation as the borewells are all drying up Coordination with all departments are required for smooth project implementation Corodination meeting with all the coorporators, MLA's during project implementation Borewell maintenance to be taken up on priority It was requested for arranging a visit to the Water Works facility of BWSSB for the Corporators so that they get proper exposure and hence can explain the public accordingly.
- (7) Corporator, Ward No 197 (110 villages), Ms Shobha Narayan
 - Welcomed the decision to take up the project as 60% of the area in 110 villages area is having no water.
 - Pro Rata charges to be collection by disconnection of the sewerage connections.
 - Sanitary issues to be resolved
- (8) Corporator, Ward No 85 (110 villages)
 - Welcomed the decision to take up the project.
 - The project implementation to be expedited
- (9) Corporator, Ward No 26 (110 villages), Ramamurthy Nagar
 - Welcomed the decision to take up the project.
 - The project implementation to be expedited
- Protection of Vulnerable groups in society BWSSB indicated that special provisions will be made for improving the water supply and sanitation facilties for the vulnerable groups in the society (slum dewellers etc).
- Notice methods on the project, cooperation and undertakings by beneficiaries

Internet and newspaper will be used and report periodically every month initially and then every quarterly.

- Plan for the succeeding meeting. As suggested a Coordination Meeting will be taken up on monthly basis during the project implementation period.
- Closing remarks was given by Mr Kemparamaiah, Engineering Chief, 4. Closing Remarks **BWSSB**
- Vote of Thanks was given by Mr Rajiv K N, EE (K-1), BWSSB 5. Vote of Thanks

Meeting Program


| Time schedule | In charge |
|--|------------------------------|
| 10:45 - 11:00 Tea | |
| 11:00 Opening Remarks | Hon'ble Chairman, BWSSB |
| 11:30 - 12:00 Explanation of the Project | Dr. Ravindra (CE-K, BWSSB) |
| 12:00 -13:00 Discussion | All Stakeholders |
| 13:15 Closing Remarks | Mr Kemparamaiah (EIC, BWSSB) |
| 13:25 Vote of Thanks | Mr Rajiv K N (EE-K1, BWSSB) |
| 13:30 - 14:30 Lunch | |



| Photo Title | Venue: Auditorium & Welcome Board |
|-------------|--------------------------------------|
| Description | Welcome Board in front of Autitorium |
| Venue | Auditorium 4th Floor, BWSSB |
| Date Taken | 2017/Aug/22 (Tue) |



| Photo Title | Set of Documents |
|-------------|--------------------------------------|
| Description | Distribution Documents and Materials |
| Venue | Auditorium 4th Floor, BWSSB |
| Date Taken | 2017/Aug/22 (Tue) |



| Photo Title | Set of Documents etc. |
|-------------|--|
| Description | Distribution Documents and Materials (inside the clear file) |
| Venue | Auditorium 4th Floor, BWSSB |
| Date Taken | 2017/Aug/22 (Tue) |



| Photo Title | Reception |
|-------------|---|
| Description | Attendants list was filled at the reception |
| Venue | Auditorium 4th Floor, BWSSB |
| Date Taken | 2017/Aug/22 (Tue) |



| Photo Title | Paticipants |
|-------------|---------------------------------------|
| Description | 126 paticipants including BWSSB staff |
| Venue | Auditorium 4th Floor, BWSSB |
| Date Taken | 2017/Aug/22 (Tue) |




| Photo Title | Paticipants |
|-------------|---|
| Description | 126 paticipants including BWSSB staff (Before starting the meeting) |
| Venue | Auditorium 4th Floor, BWSSB |
| Date Taken | 2017/Aug/22 (Tue) |



| Photo Title | Opening by BWSSB Chairman |
|-------------|--|
| Description | Chairman, BWSSB inagurated the conference and welcomed all |
| Venue | Auditorium 4th Floor, BWSSB |
| Date Taken | 2017/Aug/22 (Tue) |



| Photo Title | Explanation of the Project |
|-------------|--|
| Description | Explanation (PPT) was given by Dr. Ravindra, Chief Engineer (Kaveri), BWSSB |
| Venue | Auditorium 4th Floor, BWSSB |
| Date Taken | 2017/Aug/22 (Tue) |



| Photo Title | Explanation of the Project |
|-------------|---|
| Description | Explanation (PPT) was given by Dr. Ravindra, Chief Engineer (Kaveri), BWSSB |
| Venue | Auditorium 4th Floor, BWSSB |
| Date Taken | 2017/Aug/22 (Tue) |



| Photo Title | Explanation of the Project |
|-------------|---|
| Description | Additional Explanation given by Chairman, BWSSB |
| Venue | Auditorium 4th Floor, BWSSB |
| Date Taken | 2017/Aug/22 (Tue) |



| Photo Title | Paticipants |
|-------------|--|
| Description | 126 paticipants including BWSSB staff (During the meeting) |
| Venue | Auditorium 4th Floor, BWSSB |
| Date Taken | 2017/Aug/22 (Tue) |



| Photo Title | Question from the Stakeholder | |
|-------------|--|--|
| Description | Discussion, question-and-answer session after the presentation | |
| Venue | Auditorium 4th Floor, BWSSB | |
| Date Taken | 2017/Aug/22 (Tue) | |

Supporting Report 15.7.1

Draft TOR for Consulting Services

Terms of Reference (TOR) of the consultancy services

1. Background and Objectives of the Project

(1) Background

Bengaluru, the capital city of Karnataka State with 8,500 thousand population in 2011 is one of the fastest developing Metropolitan cities in India. Bengaluru is an industrial center of South India and is a center for research institutions and high-tech electronic houses. The population of Metro Bengaluru in 2024 are projected to be beyond 11 million with required water demand of 2,355 MLD. However, present water supply for the area is limited to 1,400 MLD. The ever-increasing water demand needs augmentation/improvement of water supply and sewerage services.

Under these conditions, Government of India decided to provide water supply and sewerage facilities for the urban population in its 12th Five Year Plan (from April 2012 to March 2017). The plan policy emphasizes on the water saving through the reduction of unaccounted for water (UFW) and the recycle/ re-use of treated sewage considering limited water sources available.

The Government of India through Bangalore Water Supply and Sewerage Board (hereinafter referred to as BWSSB) utilizing Japanese Government ODA loan proposed "Bengaluru Water Supply and Sewerage Project" in March 2016. In this connection, BWSSB, responsible for implementation of the Project and O&M of the water supply and sewerage facilities, prepared some "Detailed Project Reports (DPR)" to confirm the Project feasibility.

After a series of discussions on the scope and implementation arrangements of the Preparatory Survey between the Japanese and Indian sides, M/M (Minutes of Meetings) was exchanged in March 7th, 2016 to start "the Preparatory Survey on the Bengaluru water Supply and Sewerage Project, Phase III. Then, the survey work for the Project commenced in May 25th, 2016.

(2) Objectives of the Project

The objective of the Project is to provide residents in BBMP (Bruhat Bengaluru Mahanagara Palike) area with safe and stable water supply, and sewerage facilities to meet increasing water demand. The Project is expected to improve sanitary environment in BBMP area and contribute to the promotion of industry.

(3) Location of the Project

The Project area covers the jurisdiction of BWSSB (Bangalore Water Supply and Sewerage Board) for

water supply and sewerage services, located in the State of Karnataka, as shown in Attachment 1, including core area, 8 ULBs and 110 Villages as shown in Table 1.

Table 1: The project area

| Core Area | 245 km^2 |
|---|--------------------|
| 8 ULBs (Yelahanka, K.R. Puram, Mahadevpura, Bommanahalli, | 330 km^2 |
| R.R. Nagar, Kengeri, Dasarahalli, Byatrayanapura) | |
| 110 Villages | 225 km^2 |

2. Outline of the Project

(1) Construction Items

The component of the Project is shown in Attachment 2. The contractors' work for CP-2 to CP-5 for water supply and CP-25 to CP-29 for sewerage will include O&M of facilities for seven years after construction/installation of the facilities.

(2) Procurement packages and procedure

Local Competitive Bidding (LCB) will be applied for CP-1 and CP-14 to CP-23 for water supply and CP-35 to CP-39 for sewerage. On the other hand International Competitive Bidding (ICB) based on Single-Stage Two-Envelope Bidding Procedure with Pre-qualification (P/Q) in compliance with the JICA's Procurement Guideline (Section 2.03, Part II) will be employed for other packages.

Table 2: Procurement Package and Procedure of the Project

| Package | Procurement procedure |
|----------------------------|--|
| CP-1 and CP-14 to CP-23 | Local Competitive Bidding (LCB). Out of Consulting Service |
| CP-30 to CP-39 | Local Competitive Bidding (LCB). With Consulting Service |
| | International Competitive Bid (ICB) with P/Q |
| | Single-Stage Two-Envelope |
| CP-2 to CP-5 and CP-25 to | Design-Build-Operation (DBO) contract |
| CP-29 to CP-3 and CP-23 to | 7 years of O&M after the commissioning |
| CF-29 | JICA's Standard Bidding Document "Design-Build"* |
| | *It is noted that the general conditions of the contract shall be prepared using the |
| | FIDIC Gold book (Edition 2008) |
| | International Competitive Bid (ICB) with P/Q |
| CP-24 | Single-Stage Two-Envelope |
| CF-24 | Design-Build (DB) contract |
| | JICA's Standard Bidding Document "Design-Build"* |
| | International Competitive Bid (ICB) with P/Q |
| Others | Single-Stage Two-Envelope |
| Others | Design-Bid-Build contract |
| | JICA's Standard Bidding Document "Works" |

(3) Funding Source

Funding sources of the Project, including that for the Services, are both Japanese ODA Loan and Government of Karnataka (GoK) own budget.

- CP-2 to CP-10, CP-12 to CP-13 and CP-24 to CP-34 are funded by Japanese ODA Loan
- CP-1, CP-11, CP-14 to CP-23 and CP 35 to CP-39 are funded by GoK own budget/BCC fund
- Consulting Service for all packages excluding CP-1 and CP-19 to CP-23 is funded by Japanese ODA Loan

(4) Executing Agency

The Executing Agency / Implementing Agency of the project is BWSSB.

(5) Technical Information

The final report on the "Preparatory Survey on Bengaluru Water Supply and Sewerage Project Phase 3 as well as the results of topographical surveys, raw water quality and wastewater quality analysis, test pit surveys at the water supply and sewerage facility sites are available at BWSSB.

3. Objective of the Consulting Service

The consulting services shall be provided by an international consulting firm (hereinafter referred to as "the Consultant") in association with national consultants in compliance with Guidelines for the Employment of Consultants under Japanese ODA Loans (April 2012). The objective of the consulting services is to achieve the efficient and proper preparation and implementation of the Project through the following works:

- Conceptual design for DB / DBO packages
- Detailed design
- Bid document preparation
- Tender assistance
- Construction supervision for DB and DBO contract packages
- Construction supervision including defect notification period for other contract packages
- Facilitation of Implementation of Environmental Management Plan (EMP), Environmental Monitoring Plan (EMOP) and Resettlement Action Plan (RAP)
- Management assistance for the construction of all components of the project including supervision during the defect liability period
- NRW reduction management and technology transfer
- Water saving campaign
- Development of recycle and reuse program based on demand assessment and reuse need for effective implementation.
- Facilitation of a platform to discuss surface water pollution abatement in Bengaluru

4. Scope of the Consulting Service

The Consultant shall carry out the Consulting Services through the following work items:

(1) Conceptual Design for DBO packages

The conceptual design will include the following works:

- a) Review of the technical information on the Project and recommend modifications with justifications, if necessary;
- b) Implementation of the land availability survey, soil condition survey and traffic impact survey for conceptual design, as applicable to the project components;
- c) Implementation of the topographic survey, geotechnical surveys, raw water quality analysis, wastewater quality analysis and other related engineering survey, which will be provided as a part of the tender document, as applicable to the project components;
- d) Conceptual design of the DBO contract packages;
- e) Preparation of conceptual design report, which includes a description of all the processes, general layout plan, water and material balance sheet, overall process flow diagram, and instrumentation plan;
- f) Preparation of technical specifications to be included in the bid documents; and
- g) Preparation of "Operation and Maintenance Requirement (including risk allocation, payment method, monitoring and evaluation method etc.) to be included in the bid documents of DBO contract packages.

(2) Detailed design

The detailed design will include the following works:

- a) Review of the technical information on the Project and recommend modifications with justifications, if necessary;
- b) Collect and review topographic data of the BBMP;
- c) Implementation of the land availability survey, soil condition survey and traffic impact survey for detailed design, as applicable to the project components;
- d) Implementation of the topographic survey, geotechnical surveys and other related engineering survey for detailed design, as applicable to the project components;

- e) Preparation of large sectorization plan including hydraulic analyses, namely Distribution Blocking System, for optimization of water distribution, especially for detail design of CP-14 to CP-18;
- f) Hydraulic analyses of the pipelines for final determination of the pump head, countermeasure for water hammer and diameter of pipes;
- g) Detailed design of all facilities including architectural, structural, civil, mechanical and electrical works:
- h) Preparation of the construction plan including design of the temporary works;
- i) Preparation of detailed design drawings; and
- j) Preparation of technical specifications and bill of quantities to be included in the bid documents

(3) Bid document preparation

The bid document preparation will include the following works:

- a) Preparation of the pre-qualification (PQ) document, complying with the following instructions:
 - ✓ The technical and financial requirements for PQ shall take into account the technical feature and the magnitude of the Project;
 - ✓ The PQ part shall be in accordance with the latest version of Standard Prequalification Documents under Japanese ODA Loans;
 - ✓ Assistance to BWSSB in PQ announcement, addendum/corrigendum, and clarifications to the applicants' queries;
 - ✓ PQ evaluation of the applicants in accordance with the criteria set forth; and
 - ✓ Preparation of PQ evaluation report to be submitted to BWSSB.
- b) Preparation of the Bid document, complying with the following instructions:
 - ✓ For procurement of goods and services under CP 2 to 6 and 24 to 29 the latest version of "Standard Bidding Documents under Japanese ODA Loans, Procurement of Electrical and Mechanical Plant, and for Building and Engineering Works, Designed by the Contractor" will be applied, together with all relevant specifications, drawings and other documents. The general conditions of the contract shall be prepared using the FIDIC Gold book (Edition 2008), since the operation work of the DSP will be included in these packages under DBO scheme;
 - ✓ For procurement of goods and services under CP7 to 18 and 30 to 39, the latest version of "Standard Bidding Documents under Japanese ODA Loans, Procurement of Works" will be applied, along with all relevant specifications, drawings, and other documents;

✓ Prepare bidding documents which includes i) clauses stating that the Contractor is to comply with the requirement of the Environmental Management Plan (EMP) and JICA Guidelines for environmental and social considerations (April 2010) (JICA Environmental Guidelines) and to conduct environmental monitoring following the Environmental Monitoring Plan (EMoP), ii) the specification clearly stipulating the safety requirements in accordance with the laws and regulations in the country of the Borrower, relevant international standards (including guidelines of international organization), if any, and also in consideration of "the Guidance for the Management of Safety for Construction Works in Japanese ODA Projects of JICA," iii) the requirement to furnish a safety plan to meet the safety requirements, iv) the requirement for the personnel for key positions to include an accident prevention officer, and v) the requirement to submit method statements of safety to BWSSB and the consultant at the construction stage;

(4) Tender Assistance

The Consultant shall assist BWSSB in the bid by the following works:

- a) Assistance to BWSSB in tender call, addendum/corrigendum, clarifications to the bidders and conducting pre-bid conferences;
- b) Evaluations of the bids in accordance with the criteria set forth in the bidding documents. In such evaluation, the Consultant shall carefully confirm that bidders' submissions in their technical proposal including, but not limited to; site organization, mobilization schedule, method statement, construction schedule, safety plan, and EMP, have been prepared in consistent with each other and meet requirements set forth in applicable laws and regulations, specifications and other parts of the bidding documents;
- c) ,Preparation of bid evaluation reports for approval to be submitted to BWSSB;
- d) Assistance to BWSSB in contract negotiations by preparing agenda and facilitating negotiations including preparation of minutes of negotiation meetings; and
- e) Preparation of draft and final contract agreements.

(5) Construction supervision for DBO contract packages

The Consultant shall perform his duties during the construction period in accordance with the contracts to be executed between BWSSB and the contractors. In this context, the Consultant shall act as the Engineer for DB and DBO packages to execute construction supervision and contract administration services in accordance with the power and authority delegated by BWSSB. Construction supervision by the Consultant will include the following works:

- a) Act as the Engineer to execute construction supervision and contract administration services in accordance with the power and authority to be delegated by the Employer;
- b) Provide assistance to the Employer concerning variations and claims that are to be ordered/issued at the initiative of the Employer. Advise the Employer on resolution of any dispute with the Contractor:
- c) Issue instructions, approvals, and notices as appropriate;
- d) Provide recommendation to the Employer for acceptance of the Contractor's performance security, advance payment security and required insurances;
- e) Provide commencement order to the Contractor;
- f) Assess adequacy of all inputs such as materials, labor, and equipment provided by the Contractor;
- g) Check and approve the Contractor's method of work, including site organization, program of performance, quality assurance system, safety plan, method statements of safety, and environmental monitoring plan so that the requirements set forth in the applicable laws and regulations, the specifications or other parts of the contract are to be duly respected;
- h) Regularly monitor physical and financial progress and take appropriate action to expedite progress, if necessary, so that the time for completion set forth in the contract will be duly respected by the Contractor;
- Explain and/or adjust ambiguities and/or discrepancies in the Contract Documents and issue any necessary clarifications or instructions;
- Review and approve the Contractor's design for the works to be constructed, working drawings, shop drawings and drawings for temporary works;
- k) Liaise with the appropriate authorities to ensure that all the affected utility services are promptly relocated;
- Carry out field inspections on the Contractor's setting out of the works in relation to original points, lines and levels of reference specified in the contract;
- m) Organize, as necessary, management meetings with the Contractor to review the arrangements for future work. Prepare and deliver minutes of such meetings to the Employer and the Contractor;
- n) Supervise the works so that all the contractual requirements are met by the Contractor, including those in relation to i) quality of the works, ii) safety, and iii) protection of the environment. Confirm that an accident prevention officer proposed by the Contractor is duly assigned at the project site. Require the contractors to take appropriate remedies if any questions are recognized regarding the safety measures;

- o) Supervise field tests, sampling, and laboratory test to be carried out by the Contractor;
- p) Inspect the construction method, equipment to be used, and workmanship at the site, and attend shop inspection and manufacturing tests in accordance with the Employer's Requirements;
- q) Verify statements submitted by the Contractor and issue payment certificates such as interim payment certificates and final payment certificate as specified in the contract;
- r) Coordinate the works among different contractors employed for the Project;
- s) Modify the Employer's Requirements as may be necessary in accordance with the actual site conditions and issue variation orders (including necessary actions in relation to the works performed by other contractors working on other projects, if any);
- t) Carry out timely reporting to the Employer for any inconsistency / causes of delay in executing the works and suggesting appropriate corrective measures to be applied;
- u) Inspect, verify and fairly determine claims issued by the parties to the contract (i.e. the Employer and Contractor) in accordance with the contract;
- v) Supervise the Test on Completion carried out by the Contractor and assist the Employer in carrying out the Test after Completion, if applicable;
- w) Perform the inspection of the works and issue certificates such as the Taking-Over Certificate, Performance Certificate as specified in the contract,
- x) Check and certify as-built drawings prepared by the Contractor; and
- y) Check and certify the operation and maintenance manual prepared by the Contractor.

(6) Construction supervision including notification period for other contract packages

The Consultant shall perform his duties during the construction period in accordance with the contracts to be executed between BWSSB and the contractors. In this context, the Consultant shall act as the Engineer for other packages to execute construction supervision and contract administration services in accordance with the power and authority delegated by BWSSB. Construction supervision by the Consultant will include the following works:

- a) Act as the Engineer to execute construction supervision and contract administration services in accordance with the power and authority to be delegated by the Employer;
- b) Provide assistance to the Employer concerning variations and claims that are to be ordered/issued at the initiative of the Employer. Advise the Employer on resolution of any dispute with the Contractor:
- c) Issue instructions, approvals, and notices as appropriate;

- d) Provide recommendation to the Employer for acceptance of the Contractor's performance security, advance payment security and required insurances;
- e) Provide commencement order to the Contractor;
- f) Assess adequacy of all inputs such as materials, labor, and equipment provided by the Contractor;
- g) Check and approve the Contractor's method of work, including site organization, program of performance, quality assurance system, safety plan, method statements of safety, and environmental monitoring plan so that the requirements set forth in the applicable laws and regulations, the specifications or other parts of the contract are to be duly respected;
- h) Regularly monitor physical and financial progress and take appropriate action to expedite progress if necessary, so that the time for completion set forth in the contract will be duly respected by the Contractor;
- i) Explain and/or adjust ambiguities and/or discrepancies in the Contract Documents and issue any necessary clarifications or instructions. Issue further drawings and give instructions to the Contractor for any works that may not be sufficiently detailed in the contract documents, if any;
- Review and approve the Contractor's working drawings, shop drawings, and drawings for temporary works. Also review and approve, if any, designs prepared by the Contractor for any part of the permanent works;
- k) Liaise with the appropriate authorities to ensure that all the affected utility services are promptly relocated:
- l) Carry out field inspections on the Contractor's setting out of the works in relation to original points, lines, and levels of reference specified in the contract;
- m) Organize, as necessary, management meetings with the Contractor to review the arrangements for future work. Prepare and deliver minutes of such meetings to the Employer and the Contractor;
- n) Supervise the works so that all the contractual requirements are met by the Contractor, including those in relation to i) quality of the works, ii) safety and iii) protection of the environment. Confirm that an accident prevention officer proposed by the Contractor is duly assigned at the project site. Require the contractors to take appropriate remedies if any questions are recognized regarding the safety measures;
- o) Supervise field tests, sampling, and laboratory test to be carried out by the Contractor;
- p) Inspect the construction method, equipment to be used, and workmanship at the site, and attend shop inspection and manufacturing tests in accordance with the specifications;

- q) Survey and measure the work output performed by the Contractor. Assist the Employer to verify statements submitted by the Contractor and issue payment certificates such as interim payment certificates and final payment certificate as specified in the contract;
- r) Coordinate the works among different contractors employed for the Project;
- s) Modify the designs, technical specifications and drawings, relevant calculations and cost estimates as may be necessary in accordance with the actual site conditions, and issue variation orders (including necessary actions in relation to the works performed by other contractors working on other projects, if any);
- t) Carry out timely reporting to the Employer for any inconsistency in executing the works and suggesting appropriate corrective measures to be applied;
- Inspect, verify, and provide recommendation to the Employer concerning claims issued by the
 parties to the contract (i.e. the Employer and Contractor) in accordance with the civil works
 contract;
- v) Perform the inspection of the works and issue certificates such as the Taking-Over Certificate, Performance Certificate as specified in the contract;
- w) Supervise commissioning and carry out tests during the commissioning, if applicable;
- x) Provide periodic and/or continuous inspection services during defects notification period, and if any defects are noted, instruct the Contractor to rectify;
- y) Check and certify as-built drawings; and
- z) Check and certify an operation and maintenance manual for the works constructed in the Project.

(7) Facilitation of Implementation of Environmental Management Plan (EMP), Environmental Monitoring Plan (EMOP) and Resettlement Action Plan (RAP)

The Consultant shall assist BWSSB in the environmental management and monitoring through the following works:

- a) Review and update EMP according to the actual site conditions, designs, technical specifications and contract documents:
- b) Review and update EMoP according to the updated EMP;
- c) During the preparation of bidding documents, clearly identify environmental responsibilities as explained in the EIA, Final Report of Preparatory Survey and EMP;

- d) Assist BWSSB to review the Construction Contractor's Environmental Program to be prepared by the contractor in accordance with EMP, relevant plans and JICA Environmental Guidelines and to make recommendations to BWSSB regarding any necessary amendments for its approval
- e) Supervision of EMP implementation and implementation of regular compliance monitoring according to EMoP to ensure that the construction works are implemented in accordance with the EMP:
- f) Assist BWSSB to implement the measures identified in the EMP
- g) Monitor the effectiveness of EMP and negative impacts on environment caused by the construction works and provide technical advice, including a feasible solution, so that BWSSB can improve situation when necessary;
- h) Assist BWSSB in monitoring the compliance with conditions stated in the environmental permit certifications and the requirements under EMP and JICA Environmental Guidelines;
- i) Assist BWSSB in preparation of the answer to the request from JICA's advisory committee for environmental and social considerations if necessary; and
- j) Assistance to BWSSB in the capacity building of BWSSB staff on environmental management through on-the-job training so that the EMoP would be carried out appropriately in the O&M of the seawater desalination plant.

(8) Management assistance for the construction of all components of the project including supervision during the defect liability period

The Consultants shall provide technical assistance and training for the PIU members in the field from design stage to O&M stage. Required control items for the project implementation shall include schedule, quality of facilities and risk avoidance.

The Consultant shall provide the opportunity to the BWSSB officers and staff to be involved in the working team of the Consultant during the design, contract administration and supervision works for their capacity building wherever possible. If requested by BWSSB, the Consultant shall brief and demonstrate the survey and design procedure, the construction supervision and contract management process and procedures. The consultant shall assist BWSSB and its staff to build their capacity as a part of on the job training under the Project.

(9) NRW Deduction Management

The consultants shall assist existing organization established in the BWSSB to promote the reduction of UFW. The management required with reference to field staff shall be studied to reflect in the systematic arrangements including tariff collection. Aside from management improvement,

at least one team for field work shall be established by BWSSB and they shall be trained by Japanese expert team.

(10) Water saving campaign

The Consultant shall assist BWSSB to carry out the campaign for the saving of water. During the campaign, community meeting shall be conducted from administrative chief level to common people level to cover larger areas in the BBMP. Implementation plan for the meeting shall be prepared in the initial stage of consulting services and the meetings shall be implemented periodically in the two years during project implementation period.

(11) Development of recycle and reuse program based on demand assessment and reuse need for effective implementation.

The proposed recycle and reuse program task will be conducted to achieve the following specific objectives:

- a) Identify impact of water demands based on currently planned water supply projects;
- b) Develop and analyze zonal water supply and demand for the entire PMC areas to be served by the water utilities in the future:
- Conduct a GAP analysis Demand and Supply and prepare a survey of potential consumers of recycle water.
- d) Prepare and conduct a willingness survey for use of recycled water based on end use application
 such as agriculture, construction industry, horticulture, washing etc.
- e) Assessment of "what if" scenarios for dynamic streamlining of the reuse water supply to identify projects for the medium term and long term; and
- f) Development and Prioritization of reuse potential projects for their future service areas.

(12) Facilitation of a platform to discuss surface water pollution abatement in Bengaluru

The Consultants shall assist BWSSB to facilitate a platform to discuss surface water pollution abatement in Bengaluru through the following works:

- a) Hold a seminar where the stakeholders, encountering the water pollution problem, such as pollution dischargers, regulators and/or surface water users can understand and discuss the causes and the effects of pollution; and
- b) Arrange inputs of successful experiences on wastewater discharge regulations such as administrative system and monitoring technologies to the seminar stipulated in item a).

(13) Promotion of the construction of sewerage house connections

The Consultants shall assist BWSSB to promote the construction of sewerage house connections through the following works:

- a) Hold information sessions where target residents and business establishments for sewerage services easily understand the sewerage system and the importance of the house connections; and
- b) Make and distribute visual materials to help target residents and business establishments for sewerage services to understand the sewerage system and the importance of the house connections.

5. Expected Time Schedule

The total duration of consulting services will be 87 months including defects notification period. The implementation schedule expected is as shown in Table 3.

Duration in **Duration from Key Activities** Date Months the start, Months Commencement of Consulting Services October 2018 18 18 Completion of Detailed Design October 2018 to March 2020 14 Tender process including Pre-Qualification January 2019 to February 2020 32 48 80 Construction Works January 2021 to December 2024 Completion of the Const. Works December 2024 _ 12 12 Defect Notification Period January 2025 to December 2025 Completion of Consulting Services 31 December 2025 87.5

Table 3: Implementation Schedule Expected

6. Staffing

(1) Staffing and Consulting Input

It is proposed that 9 Professional (A) consultants (Foreign Persons) and 58 Professional (B) consultants (Local Persons) will be engaged for a total of 678 man-months (MM) and 2,233 MM, respectively. Total consulting input is 2,911 MM. In addition to the consultants, supporting staff such as secretaries, CAD operators, GIS operators, office keepers, and inspectors will be necessary, and the total input is estimated at 2,036 MM.

(2) Basic professional requirements of key expert

The qualification of Key Experts is shown in Table 4.

Table 4: Qualification of Key Experts

| Designation | Qualifications |
|-------------------------|---|
| Key International Staff | |
| Team Leader – Design | Should have at least 20 years' experience in urban water supply and wastewater / sewerage |
| (Overall management - | related projects. Should have degree in Civil / Mechanical / Electrical / Chemical |

| Designation | Qualifications |
|---|---|
| Design period) | engineering. He should be well versed with e-governance procedures and handled coordination of a project with similar size. Should have handled at least one comprehensive urban water supply and/or wastewater/sewerage project with capacity of 250MLD involving planning, design, detailed engineering, pre-qualification and Bid document development and contract award. Should have handled at least one Japanese |
| TL - Construction Management (Overall management – Construction Period) | ODA Loan project. Experience in India preferred Should have at least 20 years' experience in urban water supply and wastewater / sewerage related projects. Should have degree in Civil / Mechanical / Electrical / Chemical engineering. He should we well versed with e-governance procedures and handled coordination of a project with similar size. Should have handled at least one comprehensive urban water supply and/or wastewater/sewerage project with capacity of 250MLD during construction phase and commissioning including Defect Liability Period. Should have handled at least one Japanese ODA Loan project. Experience in India preferred |
| Senior Resident Engineer - Water Treatment, pumping and transmission (Overall responsibility of the conveyance, water treatment, and transmission at | Should have at least 15 years' experience in urban water supply related projects. Should have degree in Civil / Mechanical / Electrical / Chemical engineering. Should have handled at least one comprehensive urban water supply project with capacity of 250MLD during planning, detailed engineering, construction phase and commissioning including Defect Liability Period. Should have handled at least one Japanese ODA Loan project. Experience in India preferred |
| construction stage) Senior Resident Engineer - Sewage Conveyance and Sewage Treatment (Overall responsibility of the sewage conveyance and treatment at construction stage) | Should have at least 15 years' experience in urban water supply related projects. Should have degree in Civil / Mechanical / Electrical / Chemical engineering. Should have handled at least one comprehensive urban sewerage and treatment project with combined capacity of 250MLD during planning, detailed engineering, construction phase and commissioning including Defect Liability Period. Should have handled at least one Japanese ODA Loan project. Experience in India preferred |
| Senior Design Engineer (Hydraulics Transmission) | Should be at least bachelor's degree in Civil / Mechanical Electrical / Environmental Engineering with 12 years overall experience, with at least 10 years relevant experience in water transmission hydraulics including modelling, in Water GEMS or equivalent including water hammer. He should be well versed with pumped conveyance system for minimum total head of 100m design of water system. He should be familiar with English Language. Should have handled at least one Japanese ODA Loan project. Experience in India preferred |
| Senior Design Engineer (Sewage Hydraulics) | Should be at least bachelor's degree in Civil / Mechanical Electrical / Environmental Engineering with 12 years overall experience, with at least 10 years relevant experience in sewers and pumping stations including modelling, in Sewer GEMS or equivalent. He should be well versed with sewage conveyance system for minimum total capacity of 100MLD. He should be familiar with English Language. Should have handled at least one Japanese ODA Loan project. Experience in India preferred |
| Senior Design Engineer (Water Supply / Water Treatment Plant) | Should be at least bachelor's degree in Civil / Mechanical Electrical / Chemical Environmental Engineering with 20 years overall experience, with at least 10 years relevant experience in water pumping stations and water treatment plants. He should be familiar with English Language. Should have handled at least one comprehensive urban water supply project involving detailed design, construction supervision and project management consultancy for a project with capacity of 250MLD. Should have handled at least one Japanese ODA Loan project. Experience in India preferred |
| Senior Design Engineer (ISPS / STP) | Should be at least bachelor's degree in Civil / Mechanical Electrical / Chemical Environmental Engineering with 20 years overall experience, with at least 10 years relevant experience in sewage conveyance and sewage treatment. He should be familiar with English Language. Should have handled at least one comprehensive urban sewerage project involving detailed design and construction supervision. Should have handled at |

| Designation | Qualifications |
|--|--|
| | least one Japanese ODA Loan project. Experience in India preferred |
| Senior Design Engineer (Electrical and Instrumental Control and Automation) | Should be at least bachelor's degree in Electrical / Instrumentation Control and Automation with 20 years overall experience, with at least 10 years relevant experience in water supply transmission and sewerage, pumping and treatment. He should be familiar with English Language. Should have handled at least one comprehensive urban water supply / sewerage project involving detailed design, construction supervision and project management consultancy with a total capacity of 100MLD. Should have handled at least one Japanese ODA Loan project. Experience in India preferred |
| Senior Design Engineer (Mechanical) | Should be at least bachelor's degree in Electrical / Instrumentation Control and Automation with 20 years overall experience, with at least 10 years relevant experience in water supply transmission and sewerage, pumping and treatment. He should be familiar with English Language. Should have handled at least one comprehensive urban water supply project / sewerage involving detailed design, construction supervision and project management consultancy. Should have handled at least one Japanese ODA Loan project. Experience in India preferred |
| Key National Staff | |
| DTL (Sewerage, ISPS and STPs) | Should have at least 20 years' experience in urban water supply and wastewater / sewerage related projects. Should have degree in Civil / Mechanical engineering. Should have handled at least one comprehensive urban sewerage / Sewage Treatment project comprising of sewers, sewage pumping stations and sewage treatment plants having area greater than 100sqkm including process design, detailed design, construction supervision, monitoring and commissioning of sewerage project including project management consultancy. Should have handled at least one Japanese ODA Loan project. |
| DTL (Water Conveyance, WTP, Water Pumping Station and Transmission) | Should have at least 20 years' experience in urban water supply and wastewater / sewerage related projects. Should have degree in Civil / Mechanical engineering. Should have handled at least one comprehensive urban water supply / water treatment project comprising of conveyance and transmission, pumping stations and water treatment plants with capacity of 250MLD for more including involving contract award, process, design, detailed design, construction supervision, monitoring and commissioning of sewerage project including project management consultancy. Should have handled at least one Japanese ODA Loan project. |
| Sr. Design Engineer (Instrumentation Control and Automation) | Should be at least bachelor's degree in Electrical / Instrumentation Control and Automation with 15 years overall experience, with at least 10 years relevant experience in Instrumentation Control and Automation in water supply transmission and sewerage, pumping and treatment. Should have completed at least 1 project in India with water treatment / pumping facility capacity of 100MLD or more involving centralized SCADA system for a city comparable to Bangalore. Should have handled at least one Japanese ODA Loan project. Should have international experience. |

Consultant may propose other experts and supporting staff required to accomplish the tasks outlined in the ToR.

(3) Scope of works for the respective personnel

Detailed information on the major tasks and duties to be undertaken by Key Experts of the detailed engineering design team and the construction supervision team is summarized in Table 5.

Table 5: Major Tasks and Duties of Key Expert

| Designation | Responsibilities |
|----------------------|--|
| International Staff | |
| Team Leader – Design | Pre-Construction Stage – Design and package award stage: |

| Designation | Responsibilities |
|---|---|
| (Overall management – Design period) | General coordination Supervises the Consultant's services Review Bidding documents prepared by Contract specialist. Interact with client to provide input in particular conditions of the contract. Assumes direct responsibility for day-to-day consulting services Represents the Consultant's Team in all matters relating to the performance of services |
| | Prepare monthly and quarterly progress reports Interact and liaison with BWSSB, GOK as well as JICA. |
| TL - Construction Management (Overall management – Construction Period) | Construction Stage: General coordination Supervises the Consultant's services during Construction Assumes direct responsibility for day-to-day consulting services and construction activities on all the packages – Coordinate with client and contractors for each package Assist client in resolving construction issues as well as review and assist client in preparing progress charts for financial as well as construction activities. |
| Senior Resident Engineer - Water Treatment, pumping and transmission (Overall responsibility of the conveyance, water treatment, and transmission at construction stage) | Interact and liaison with BWSSB, GOK as well as JICA. Pre-Construction Stage – Design stage Review existing designs and specifications as prepared in study report and DPR Prepare basis of design for all the Water Conveyance / Water Transmission WTP / WPS packages Prepare PQ documents and provide detailed evaluation of PQ and bidder submittals. Prepare Bid document for each package considering selected basis of design and client requirements Prepare cost estimates for comparative Assessment. Assist client in technical evaluation of bids and making recommendations on selection of contractor for each package. Direct local engineers attending the designs Review and make recommendations to STP designs submitted by contractors. Prepare the basic design of civil structures for the WTP / STP / GLRs packages including WPS / ISPS Prepare Bill of Quantities for sewerage and WTP / WPS / STP / ISPS work Direct the local civil engineers attending the designs of civil works for the WTP/ STPs as well as WPS / ISPS facilities Prepare Specifications works Supervise process review during construction Providing assessment and input during operation and maintenance – during Defect liability period. Review and contractors' proposed O&M supervision work program and training programs for Distribution Control System Coordinate the contractor's commissioning works Coordinate the contractor's O&M supervision and training Monitor and assess the effect of training and instruct any improvement of training services if necessary |
| Senior Resident Engineer - Sewage Conveyance and Sewage Treatment (Overall responsibility of the sewage conveyance and treatment at construction stage) | Pre-Construction Stage – Design stage Review existing designs and specifications as prepared in study report and DPR Prepare basis of design for all the Sewage Conveyance / ISPS / STP packages Prepare PQ documents and provide detailed evaluation of PQ and bidder submittals. Prepare Bid document for each package considering selected basis of design and client requirements Prepare cost estimates for comparative Assessment. Assist client in technical evaluation of bids and making recommendations on selection of contractor for each package. |

| Designation | Responsibilities |
|-------------------------------|---|
| | Direct local engineers attending the designs |
| | Review and make recommendations to STP designs submitted by contractors. |
| | • Prepare the basic design of civil structures for the WTP / STP / GLRs packages |
| | including WPS / ISPS |
| | Prepare Bill of Quantities for sewerage and WTP / WPS / STP / ISPS work |
| | • Direct the local civil engineers attending the designs of civil works for the WTP/ |
| | STPs as well as WPS / ISPS facilities |
| | Prepare Specifications works |
| | Supervise process review during construction |
| | Providing assessment and input during operation and maintenance – during Defect |
| | liability period. |
| | • Review and contractors' proposed O&M supervision work program and training |
| | programs for Distribution Control System |
| | Coordinate the contractor's commissioning works |
| | Coordinate the contractor's O&M supervision and training |
| | Monitor and assess the effect of training and instruct any improvement of training arrives if page 2007. |
| Canian Danian Engineer | services if necessary |
| Senior Design Engineer | Pre-construction stageReview existing designs |
| (Hydraulics Transmission) | Review existing designs Prepare the basic design of civil structures for the hydraulic transmission in water |
| Transmission) | conveyance and transmission packages |
| | Direct the local civil engineers attending the designs of civil works for the Water |
| | Conveyance and transmission pipelines |
| | Prepare hydraulic models in Water GEMS of the water transmission pipelines up to |
| | GLRs. |
| Senior Design Engineer | Pre-construction stage |
| (Sewage Hydraulics) | Review existing designs |
| (Sewage 11) draunes) | Prepare the basic hydraulic design of civil structures for sewage conveyance |
| | packages |
| | Direct the local civil engineers attending the designs of civil works for the sewage |
| | conveyance pipelines |
| | Prepare hydraulic models in Sewer GEMS of the sewage conveyance pipelines up to |
| | STPs including sub-mains, mains and trunk mains network |
| Senior Design Engineer | <u>Pre-Construction Stage – Design stage</u> |
| (Water Supply / Water | Review existing designs and specifications as prepared in study report and DPR |
| Treatment Plant) | Prepare basis of design for all the WTP / WPS packages |
| | • Prepare PQ documents and provide detailed evaluation of PQ and bidder submittals. |
| | Prepare Bid document for each package considering selected basis of design and |
| | client requirements |
| | Prepare cost estimates for comparative Assessment. |
| | Assist client in technical evaluation of bids and making recommendations on |
| | selection of contractor for each package. |
| | Direct local engineers attending the designs |
| | Review and make recommendations to WTP designs submitted by contractors. |
| | Supervise process review during construction |
| | Providing assessment and input during operation and maintenance – during Defect The second of the second |
| | liability period. |
| | Review and contractors' proposed O&M supervision work program and training programs for Distribution Control System |
| | programs for Distribution Control System |
| | Coordinate the contractor's commissioning works Coordinate the contractor's O.S.M. supervision and training. |
| | Coordinate the contractor's O&M supervision and training Monitor and assess the effect of training and instruct any improvement of training. |
| 1 | Monitor and assess the effect of training and instruct any improvement of training services if necessary |
| Senior Design Engineer | Review existing designs and specifications as prepared in study report and DPR |
| Senior Design Engineer | Review existing designs and specifications as prepared in study report and DPR |

| Designation | Responsibilities |
|---------------------------|--|
| (ISPS / STP) | Prepare basis of design for all the STP / ISPS packages |
| | Prepare PQ documents and provide detailed evaluation of PQ and bidder submittals. |
| | • Prepare Bid document for each package considering selected basis of design and |
| | client requirements |
| | Prepare cost estimates for comparative Assessment. |
| | Assist client in technical evaluation of bids and making recommendations on |
| | selection of contractor for each package. |
| | Direct local engineers attending the designs |
| | Review and make recommendations to STP designs submitted by contractors. |
| | Supervise process review during construction |
| | Providing assessment and input during operation and maintenance – during Defect |
| | liability period. |
| | Review and contractors' proposed O&M supervision work program and training |
| | programs |
| | Coordinate the contractor's commissioning works |
| | Coordinate the contractor's O&M supervision and training |
| | Monitor and assess the effect of training and instruct any improvement of training |
| | services if necessary |
| Senior Design Engineer | <u>Pre-construction stage</u> |
| (Electrical and | Review existing designs |
| Instrumental Control and | • Prepare the basic design of electrical equipment, SCADA and I&C for the WTP / |
| Automation) | STPs including WPS / ISPS facilities |
| | Direct the local electrical engineers attending the designs electrical, SCADA, I&C of |
| | the WTP / STP and WPS / ISPS facilities |
| | Prepare Specifications for electrical works |
| | Prepare Bill of Quantities for electrical works |
| | • Construction stage |
| | Check the shop drawings submitted by the contractors A second by the substitution of any day to proposed by the contractors. |
| | Assess the substitution of products proposed by the contractors Supervises the installation work of electrical equipment. |
| | Supervise the installation work of electrical equipment Attend the feature inspection to eather with PWSSP engineer if requested. |
| | Attend the factory inspection together with BWSSB engineer, if requested Attend the trial operation of mechanical equipment |
| Senior Design Engineer | |
| (Mechanical) | Pre-construction stage Review existing designs |
| (Mechanical) | Prepare the basic design of mechanical equipment for the WTP / STP packages |
| | including WPS and ISPS |
| | Direct the local mechanical engineers attending the designs of mechanical works for |
| | the WTP / STPs as well as WPS / ISPS facilities |
| | Prepare Specifications for mechanical works |
| | Prepare Bill of Quantities for mechanical works |
| | Construction stage |
| | Check the shop drawings submitted by the contractors |
| | Assess the substitution of products proposed by the contractors |
| | Supervise the installation work of mechanical equipment |
| | Attend the factory inspection together with PMC's engineer, if requested |
| | Attend the trial operation of mechanical equipment |
| Project Director Review | Pre-Construction Stage – Design and package award stage: |
| (Overall review of the | General coordination |
| project and liaison with | Occasional Interact and liaison with BWSSB, GOK as well as JICA. |
| higher levels of JICA and | Assist client in resolving construction issues as well as review and assist client in |
| BWSSB) | preparing progress charts for financial as well as construction activities. |
| DTL (Sewerage, ISPS and | Assist Team Leader in carrying out all tasks and duties of Team Leader |
| STPs) | Represent the Consultant's team during absence of the Team Leader |
| * | Perform specific issues/aspects delegated by Team Leader in Sewage conveyance, |

| Designation | Responsibilities |
|---------------------------|---|
| | pumping and sewage treatment plants |
| DTL (Water Conveyance, | Assist Team Leader in carrying out all tasks and duties of Team Leader |
| WTP, Water Pumping | Represent the Consultant's team during absence of the Team Leader |
| Station and Transmission) | Perform specific issues/aspects delegated by Team Leader in Water conveyance, |
| | pumping and water treatment plants |
| Sr. Design Engineer | Assist the Sr. Design Engineer – International |
| (Water Hydraulics) | Pre-construction stage |
| | Review existing designs |
| | Prepare the basic design of civil structures for the hydraulic transmission in water |
| | conveyance and transmission packages |
| | Direct the local civil engineers attending the designs of civil works for the Water |
| | Conveyance and transmission pipelines |
| | Prepare hydraulic models in Water GEMS of the water transmission pipelines up to |
| | GLRs. |
| Sr. Design Engineer | Assist the Sr. Design Engineer – International |
| (Water Treatment Plant) | Review existing designs and specifications as prepared in study report and DPR |
| | Prepare basis of design for all the WTP / WPS packages |
| | Prepare PQ documents and provide detailed evaluation of PQ and bidder submittals. |
| | Prepare Bid document for each package considering selected basis of design and |
| | client requirements |
| | Prepare cost estimates for comparative Assessment. A print plant in the height production of hide and making appropriation of hide and making appropriation. |
| | Assist client in technical evaluation of bids and making recommendations on selection of contractor for each models. |
| | selection of contractor for each package. • Direct local engineers attending the designs |
| | Review and make recommendations to WTP designs submitted by contractors. |
| | Supervise process review during construction |
| | Providing assessment and input during operation and maintenance – during Defect |
| | liability period. |
| | Review and contractors' proposed O&M supervision work program and training |
| | programs for Distribution Control System |
| | Coordinate the contractor's commissioning works |
| | Coordinate the contractor's O&M supervision and training |
| | Monitor and assess the effect of training and instruct any improvement of training |
| | services if necessary |
| Sr. Design Engineer | Assist the Sr. Design Engineer – International |
| (Sewage Treatment | Review existing designs and specifications as prepared in study report and DPR |
| Plants) | Prepare basis of design for all the STP / ISPS packages |
| | • Prepare PQ documents and provide detailed evaluation of PQ and bidder submittals. |
| | Prepare Bid document for each package considering selected basis of design and |
| | client requirements |
| | Prepare cost estimates for comparative Assessment. |
| | Assist client in technical evaluation of bids and making recommendations on |
| | selection of contractor for each package. |
| | Direct local engineers attending the designs Parious and make recommendations to STR designs submitted by contractors. |
| | Review and make recommendations to STP designs submitted by contractors. Supervise process review during construction. |
| | Supervise process review during construction Providing assessment and input during operation and maintenance – during Defect |
| | liability period. |
| | Review and contractors' proposed O&M supervision work program and training |
| | programs |
| | Coordinate the contractor's commissioning works |
| | Coordinate the contractor's Commissioning works Coordinate the contractor's O&M supervision and training |
| | Monitor and assess the effect of training and instruct any improvement of training |
| | services if necessary |
| | SET LOCK IN INCOMENT |

| Designation | Responsibilities |
|--------------------------|---|
| Sr. Design Engineer | Assist the Sr. Design Engineer – International |
| (Sewerage Hydraulics) | Pre-construction stage |
| | Review existing designs |
| | Prepare the basic hydraulic design of civil structures in sewage conveyance packages |
| | • Direct the local civil engineers attending the designs of civil works for the sewage |
| | conveyance pipelines |
| | • Prepare hydraulic models in Sewer GEMS of the sewage conveyance pipelines up to |
| | STPs including sub-mains, mains and trunk mains network |
| Sr. Design Engineer | Assist the Senior Design Engineer - International |
| (Mechanical) | Review existing designs |
| | • Prepare the basic design of mechanical equipment for the WTP / STP packages |
| | including WPS and ISPS |
| | • Direct the local mechanical engineers attending the designs of mechanical works for |
| | the WTP / STPs as well as WPS / ISPS facilities |
| | Prepare Specifications for mechanical works |
| | Prepare Bill of Quantities for mechanical works |
| | Construction stage |
| | Check the shop drawings submitted by the contractors |
| | Assess the substitution of products proposed by the contractors |
| | Supervise the installation work of mechanical equipment |
| | Attend the factory inspection together with PMC's engineer, if requested |
| | Attend the trial operation of mechanical equipment |
| Sr. Design Engineer | Assist the Senior Design Engineer - International |
| (Electrical) | Review existing designs |
| | Prepare the basic design of electrical equipment, SCADA and I&C for the WTP / STPs including WPS / ISPS facilities |
| | • Direct the local electrical engineers attending the electrical designs of the WTP / STP and WPS / ISPS facilities |
| | Prepare Specifications for electrical works |
| | Prepare Bill of Quantities for electrical works |
| | Construction stage |
| | Check the shop drawings submitted by the contractors |
| | Assess the substitution of products proposed by the contractors |
| | Supervise the installation work of electrical equipment |
| | Attend the factory inspection together with BWSSB engineer, if requested |
| | Attend the trial operation of mechanical equipment |
| Sr. Design Engineer | Assist the Senior Design Engineer - International |
| (Instrumentation Control | Review existing designs |
| and Automation) | Prepare the basic design of SCADA and I&C for the WTP / STPs including WPS / ISPS facilities |
| | Direct the ICA engineers under him attending the designs- SCADA, I&C of the WTP / STP and WPS / ISPS facilities |
| | |
| | Prepare Specifications for instrumentation / SCADA works Prepare Bill of Quantities for instrumentation / SCADA works |
| | Construction stage |
| | Check the shop drawings submitted by the contractors |
| | Assess the substitution of products proposed by the contractors |
| | Supervise the installation work of electrical equipment |
| | Attend the factory inspection together with BWSSB engineer, if requested |
| | Attend the trial operation of mechanical equipment |
| Sr. Design Engineer | Assist the Senior Design Engineer - International |
| (Structural) | Review existing designs |
| (www.m.) | Prepare the basic design of SCADA and I&C for the WTP / STPs including WPS / |
| | ISPS facilities |

| Designation | Responsibilities |
|---|---|
| | Direct the ICA under him engineers attending the designs- SCADA, I&C of the WTP / STP and WPS / ISPS facilities Prepare Specifications for structural works Prepare Bill of Quantities for structural works Construction stage Check the shop drawings submitted by the contractors Assess the substitution of products proposed by the contractors Supervise the installation work of electrical equipment Attend the factory inspection together with BWSSB engineer, if requested |
| Construction Supervision S | Attend the trial operation of mechanical equipment |
| Procurement Engineer (All Components) Senior. Resident Engineer (Water) Senior. Resident Engineer (Sewerage Component) | Assist the Senior Design Engineer – International and national Check the drawings submitted by the contractors Assess the substitution proposed by the contractors Supervise the work of water supply component Attend the factory inspection together with BWSSB engineer, if requested Assist the Senior Design Engineer - International Check the drawings submitted by the contractors |
| Contract Engineer (All Components) | Assess the substitution proposed by the contractors Supervise the work of sewerage component Attend the factory inspection together with BWSSB engineer, if requested Assist the Team Leader Check the drawings submitted by the contractors Assess the substitution proposed by the contractors Supervise the work of sewerage component Attend the factory inspection together with BWSSB engineer, if requested |
| HRD and Institutional | , , , , , , , , , , , , , , , , , , , |

7. Reporting

Within the scope of consulting services, the Consultant shall prepare and submit reports and documents to Project Director/ Project Manager in charge in BWSSB as shown in Table 6. The Consultant shall provide electronic copy of each of these reports.

Table 6: Summary of Reports to be submitted

| Category | Type of Report | Timing | No. of Copies |
|-------------------------|------------------------------|--|------------------|
| Consultancy Services | Inception Report | Within 1 month after commencement of the services | 10 |
| | Monthly Progress Report | Every month | 10 |
| | Quarterly Progress Report | Every quarter | 10 |
| | Project Completion Report | At the end of the services | 10 |
| Detailed Design | Project Definition Report | Within 3 months after commencement of the services | 10 |
| | Draft Design Report | Within 6 months after commencement of the services | |
| | Cost Estimate Report | As per the Project Schedule for each Package | 10 |
| | Final Design Report | As per the Project Schedule for each Package | 10 |
| Tender Assistance | Pre-qualification Document | As per the Project Schedule for each Package | 10 |
| | Bidding Document | As per the Project Schedule for each Package | 10 |
| | Pre-qualification Evaluation | At appropriate timing | 10 |

| Category | Type of Report | Timing | No. of Copies |
|--------------------------------------|---|--|------------------|
| | Report | | |
| | Technical Evaluation Report | At appropriate timing | 10 |
| | Price and Commercial Evaluation Report | At appropriate timing | 10 |
| Assistance in Environment Monitoring | Environmental Monitoring Report | Every quarter after commencement of the services | 10 |
| Construction | Quality Control Report | Every month | 10 |
| Supervision | Construction Completion Report | Within 3 months after completion of construction | 10 |
| Technology Transfer | O&M Manual – review comments based on Contractor's submittal and suggestions for improvements | At appropriate timing in accordance with the Inception Report | 10 |
| | Evaluation Report of Contractors' Training Services | Within 1 month after completion of training | 10 |
| Other Report | Development of Recycle and Reuse Program | Within 6 months after commencement of the services | 10 |
| | NRW Deduction Management Program | Within 1 month after commencement of the services and every year | |
| | Water Saving Campaign Program | Within 1 month after commencement of the services and every year | 10 |
| | Technical Report | As required or upon request | As required |

Contents to be included in each report are as follows:

For Inception Report

Inception Report: presents the methodologies, schedule, organization, etc.

For Monthly and Quarterly Progress Report

Monthly Progress Report: describes briefly and concisely all activities and progress for the previous month by the 10th day of each month. Problems encountered or anticipated will be clearly stated, together with actions to be taken or recommendations on remedial measures for correction. Also indicates the work to be performed during the coming month.

Quarterly Progress Report: presents the progress status of the Project.

For Detailed Design

 $\underline{Project\ Definition\ Report} : presents\ the\ design\ criteria\ and\ standards.$

<u>Draft Design Report:</u> presents detailed engineering design as well as 30% designs for WTP/ WPS / STPs /ISPS.

<u>Cost Estimate Report:</u> presents detailed cost estimate.

Final Design Report: presents final documents of detailed design and cost estimate and bid plan through

the incorporation of comments on the Draft Design Report provided by the Consultant.

For Tender Assistance

Pre-qualification Document: presents the pre-qualification documents and its evaluation criteria.

Bidding Document: presents the bidding documents and bid evaluation criteria.

<u>Pre-qualification Evaluation Report:</u> presents the results of the evaluation with recommendation on the selection of the qualified applicants.

<u>Technical Evaluation Report:</u> presents the results of technical evaluation with recommendation on technically responsive bidders.

<u>Price and Commercial Evaluation Report:</u> presents the results of the tenders with recommendation on the successful bidder for award of contract.

For Construction Supervision

Quarterly Progress Report: presents the progress status of the Project.

<u>Construction Completion Report:</u> comprises outline of all facilities completed and construction records from the commencement through completion, together with key data and records.

For Technology Transfer

<u>O&M Manuals</u>: Comments on O&M Manuals submitted by Contractors and Consultants suggestions on its improvement.

<u>Evaluation Report of Contractors' Training Services</u>: presents the evaluation of contractors training services.

For Other Report

Development of Recycle and Reuse Program:

Summarize present practices on recycle and reuse with issues and problems. Relevant laws and regulations are also to be reviewed and recommend improvement plan.

NRW Reduction Management Program:

Analyze achieved performances on completed UFW reduction projects. Prepare plan for the improvement in NRW Reduction management and develop program for the implementation of the plan.

Water Saving Campaign Program:

Prepare plan with methodology for water saving by different water user together with community development. Required materials for information provision on water supply and sewerage services and improvement of environment will be prepared. Based on the plan, community meetings shall be carried out starting from local government staff up to residents. Strategic annual program shall be prepared to cover as much area as possible in the BBMP during consulting service period.

8. Obligation of Executing Agency

A certain range of arrangements and services will be provided by BWSSB to the Consultant for smooth implementation of the Consulting Services. In this context, PMC will:

(1) Reports and data

Make available to the Consultant existing reports and data related to the Project as required.

(2) Office space

The Consultant's requirement for office space, including necessary equipment, furniture and utilities, shall be clearly stated in the proposal with its rental cost for the case where BWSSB would be unable to provide such facilities;

(3) Cooperation and counterpart staff

Appoint counterpart officials, agent and representative as may be necessary for effective implementation of the Consulting Services. Required arrangements for Community Development shall be made timely;

(4) Assistance and exemption

Use its best efforts to ensure that the assistance and exemption, as described in the Standard Request for Proposal issued by JICA, will be provided to the Consultant, in relation to:

- work permit and such other documents;
- entry and exit visas, residence permits, exchange permits and such other documents
- clearance through customs;
- instructions and information to officials, agent and representatives of the GOI as well as GoK;
- Privilege pursuant to the applicable law in India.

Supporting Report 15.8.1

Preliminary Cost Estimates

Annual Fund Requirement

Base Year for Cost Estimation: Apr, 2017

Exchange Rates INR = JPY 1.7 Price Escalation: FC: 2.0% LC:

Physical Contingency 5% Physical Contingency for Consultant 5%

| I) Pr VV | Item IGIBLE PORTION rocurement / Construction BY-U1 Bytrayanapura BY-U2 Bytrayanapura BY-U3 Bytrayanapura | FC | Total LC 10,153 | Total | Million INR |
|---|--|----------------|-----------------------|--------|--|
| I) Pr VV | rocurement / Construction BY-U1 Bytrayanapura BY-U2 Bytrayanapura BY-U3 Bytrayanapura | FC | | | |
| I) Pr VV | rocurement / Construction BY-U1 Bytrayanapura BY-U2 Bytrayanapura BY-U3 Bytrayanapura | | 10,153 | | |
| V | BY-U1 Bytrayanapura BY-U2 Bytrayanapura BY-U3 Bytrayanapura | | 10,153 | | |
| V V V V V V | BY-U2 Bytrayanapura BY-U3 Bytrayanapura | <u> </u> | | 17,260 | |
| V V V V V | BY-U3 Bytrayanapura | | 912 | 1,551 | |
| V V V V V | BY-U3 Bytrayanapura | | 369 | 628 | |
| V V V V | | . | 853 | 1,450 | |
| V V V | M-U1 Mahadevpura | <u> </u> | 158 | 268 | |
| V V | M-U2 Mahadevpura | | 1,488 | 2,530 | |
| V V | BO-U1 Bommanahalli | <u> </u> | 507 | 862 | |
| V V | BO-U2 Bommanahalli | 1 | 348 | 591 | |
| | BO-U3 Bommanahalli | | 372 | 632 | |
| 17 | BO-U4 Bommanahalli | | 438 | 744 | |
| V | R-U1 R.R.Nagar | | 479 | 813 | |
| | R-U2 R.R.Nagar | | 524 | 891 | |
| | D-U1 Dasarahalli | 1 | 291 | 495 | |
| | D-U2 Dasarahalli | † † | 1,603 | 2,726 | <u> </u> |
| | ase cost for JICA financing | | 8,341 | 14,180 | 8,341 |
| | rice escalation | ·† | 1,328 | 2,258 | 1,328 |
| | hysical contingency | · | 483 | 822 | 483 |
| | Consulting services | 234 | 348 | 826 | |
| | ase cost | 212 | 302 | 726 | 427 |
| | rice escalation | 11 | 29 | 61 | 36 |
| | hysical contingency | 11 | 17 | 39 | 23 |
| | | | | | 23 |
| | | 234 | 10,501 | 18,086 | |
| | N ELIGIBLE PORTION | | | | |
| a Pi | rocurement / Construction | | | | |
| | . C. HOLE | 1 | | | |
| | ase cost for JICA financing | | | | |
| | rice escalation | 1 | | | |
| | hysical contingency | | | | |
| b L | and Acquisition | | | | |
| | ase cost | | | | |
| | rice escalation | | | | |
| | hysical contingency | | | | |
| c A | dministration cost | | 319 | 543 | 319 |
| d V | AT | | 7 | 12 | 7 |
| e In | nport Tax | | 21 | 35 | 21 |
| | Total (a+b+c+d+e) | | 347 | 589 | |
| TOTA | AL (A+B) | 234 | 10,848 | 18,675 | |
| | _ | | | | |
| C. In | terest during Construction | 204 | | 204 | |
| | nterest during Construction(Const.) | 204 | | 204 | 120 |
| | nterest during Construction (Consul.) | 0 | | 0 | 0 |
| | ont End Fee | 37 | | 37 | 22 |
| | GRAND TOTAL (A+B+C+D) | | 10,848 | 18,916 | 11,127 |
| Jawai | 101111 (11111111111) | 475 | 10,010 | 13,710 | 11,127 |
| E 114 | CA finance portion incl. IDC (A + C) | 438 | 10,501 | 18,290 | 10,759 |

Indirect Cost Total (Eligible) 2,418

Indirect Cost Total (Non Eligible) 368

Indirect Cost Total 2,786

Direct Cost Total 8,341

Pre-Conditions for Cost Estimation

1. General Conditions

Exchange Rate

| | | | INR | |
|-----|---------|---------|---------------|----|
| (1) | JPY/USD | USD 1 = | 100 JI | PΥ |
| (2) | LC/USD | USD 1 = | 70 II | ۱R |
| (3) | JPY/INR | INR 1 = | 1.7 JI | PΥ |

Price Escalation

| FC | 2.0% | LC | 3.7% |
|----|------|----|------|
| | | | |


Physical Contingency

| Construction | 5.0% | Consultant | 5.0% |
|--------------|------|------------|------|
|--------------|------|------------|------|

Base Year for Cost Estimation: Schedule

| 2017/04 | Start | 2017/01 | End | 2024/12 |
|---------|-------|---------|-----|---------|
|---------|-------|---------|-----|---------|

Billing Rate of Consultant



2. Others

Rate of Tax

| VAT | 5.0% | Import Tax | 15.0% |
|-----|------|------------|-------|

Rate of Administration Cost

3.0%

Rate of Interest During Construction

| Construction | 0.30% | Consultant | 0.01% |
|--------------|-------|------------|-------|

Rate of Front End Fee

0.2%

| Payment Method for I | nterest during construction | <u>Front End Fee</u> |
|----------------------|-----------------------------|----------------------|
| | loan covered | not loan covered |

Fiscal Year

Apr - Mar

VAT and Import TAX

| Construction/Procurement Works |
|--------------------------------|
| Consultant Services |
| Land Acquisition |

| VAT | | |
|-------|-------|--|
| FC | LC | |
| TRUE | FALSE | |
| TRUE | FALSE | |
| FALSE | FALSE | |

| Import TAX |
|------------|
| FC |
| TRUE |
| TRUE |
| |

Advanced Payment

| | Advanced Payme |
|---------------------|----------------|
| Construction | 30.0% |
| Consultant Services | 30.0% |

| Retention Money | | | |
|------------------|-----------|--|--|
| RM at Completion | After DNP | | |
| 0.0% | 0.0% | | |
| 0.0% | 0.0% | | |

Defect Notification Period(DNP)



Cost Breakdown for Package

USD =JPY 100 INR =JPY 1.7

| item | Local | Total |
|-----------------------|-------|-------|
| Reili | INR | JPY |
| Land Acquisition Cost | 0 | 0 |

VBY-U1 Bytrayanapura Loan Coverage Ratio 100

| DI CI Djulujulupulu | | | | soun coverage reams | 100 | | | |
|---|------|----------|---------|---------------------|---------|-------------|---------------|--|
| | | | Unit I | Unit Price | | Cost | | |
| item | unit | Quantity | Foreign | Local | Foreign | Local | Total | |
| | | | JPY | INR | JPY | INR | JPY | |
| Providing Submain and trunk sewer | Set | 1 | | 289,736,711 | 0 | 289,736,711 | 492,552,408 | |
| Construction of STP | Set | 1 | | 578,000,000 | 0 | 578,000,000 | 982,600,000 | |
| Construction of Wet Well cum pumphouses | Set | 1 | | 9,900,000 | 0 | 9,900,000 | 16,830,000 | |
| Providing D.I.Pumping mains | Set | 1 | | 0 | 0 | 0 | 0 | |
| Restration of Storm Water Drains | Set | 1 | | 3,148,616 | 0 | 3,148,616 | 5,352,648 | |
| Roads restration | Set | 1 | | 31,608,034 | 0 | 31,608,034 | 53,733,658 | |
| Total | | | | | 0 | 912,393,361 | 1,551,068,714 | |

VBY-U2 Bytrayanapura Loan Coverage Ratio 100

| VDI CZ Dytrayanapara | | | | | | soun coverage reams | 100 | |
|--|------|----------|---------|-------------|---------|---------------------|-------------|--|
| | | | Unit I | Unit Price | | Cost | | |
| item | unit | Quantity | Foreign | Local | Foreign | Local | Total | |
| | | | JPY | INR | JPY | INR | JPY | |
| Providing Submain and t runk sewer | Set | 1 | | 71,172,251 | 0 | 71,172,251 | 120,992,827 | |
| Construction of STP | Set | 1 | | 278,000,000 | 0 | 278,000,000 | 472,600,000 | |
| Construction of Wet Well cum pumphouses | Set | 1 | | 0 | 0 | 0 | 0 | |
| Providing D.I.Pumping mains | Set | 1 | | 5,934,000 | 0 | 5,934,000 | 10,087,800 | |
| Restration of Storm Water Drains | Set | 1 | | 1,297,677 | 0 | 1,297,677 | 2,206,051 | |
| Roads restration | Set | 1 | | 13,027,000 | 0 | 13,027,000 | 22,145,901 | |
| Total | | | | | 0 | 369,430,929 | 628,032,579 | |

VBY-U3 Bytrayanapura Loan Coverage Ratio 100

| · = | | | | | | | |
|---|------|----------|------------|-------------|---------|-------------|---------------|
| | | | Unit Price | | C | Total | |
| item | unit | Quantity | Foreign | Local | Foreign | Local | Total |
| | | | JPY | INR | JPY | INR | JPY |
| Providing Submain and t runk sewer | Set | 1 | | 297,511,215 | 0 | 297,511,215 | 505,769,065 |
| Construction of STP | Set | 1 | | 516,000,000 | 0 | 516,000,000 | 877,200,000 |
| Construction of Wet Well cum pumphouses | Set | 1 | | 0 | 0 | 0 | 0 |
| Providing D.I.Pumping mains | Set | 1 | | 0 | 0 | 0 | 0 |
| Restration of Storm Water Drains | Set | 1 | | 3,553,706 | 0 | 3,553,706 | 6,041,301 |
| Roads restration | Set | 1 | | 35,674,613 | 0 | 35,674,613 | 60,646,842 |
| Total | | | | | 0 | 852,739,534 | 1,449,657,209 |

| VM-U1 Mahadevpura | M-U1 Mahadevpura Loan Coverage Ratio | | | | | | | | | | |
|---|--------------------------------------|----------|---------|-------------|---------|-------------|-------------|--|--|--|--|
| | | | Unit I | Price | C | Total | | | | | |
| item | unit | Quantity | Foreign | Local | Foreign | Local | Total | | | | |
| | | | JPY | INR | JPY | INR | JPY | | | | |
| Providing Submain and t runk sewer | Set | 1 | | 143,342,217 | 0 | 143,342,217 | 243,681,769 | | | | |
| Construction of STP | Set | 1 | | 0 | 0 | 0 | 0 | | | | |
| Construction of Wet Well cum pumphouses | Set | 1 | | 0 | 0 | 0 | 0 | | | | |
| Providing D.I.Pumping mains | Set | 1 | | 0 | 0 | 0 | 0 | | | | |
| Restration of Storm Water Drains | Set | 1 | | 1,197,350 | 0 | 1,197,350 | 2,035,494 | | | | |
| Roads restration | Set | 1 | | 13,173,170 | 0 | 13,173,170 | 22,394,389 | | | | |
| Total | | | | | 0 | 157,712,737 | 268,111,652 | | | | |

| VM-U2 Mahadevpura | VM-U2 Mahadevpura Loan Coverage Ratio | | | | | | | | | | |
|---|---------------------------------------|----------|---------|-------------|---------|---------------|---------------|-----|-----|-----|--|
| | | | Unit I | Price | C | ost | Total | | | | |
| item | unit | Quantity | Foreign | Local | Foreign | Local | Total | | | | |
| | | | | | | JPY | INR | JPY | INR | JPY | |
| Providing Submain and trunk sewer | Set | 1 | | 566,987,224 | 0 | 566,987,224 | 963,878,281 | | | | |
| Construction of STP | Set | 1 | | 472,000,000 | 0 | 472,000,000 | 802,400,000 | | | | |
| Construction of Wet Well cum pumphouses | Set | 1 | | 183,400,000 | 0 | 183,400,000 | 311,780,000 | | | | |
| Providing D.I.Pumping mains | Set | 1 | | 196,100,000 | 0 | 196,100,000 | 333,370,000 | | | | |
| Restration of Storm Water Drains | Set | 1 | | 5,802,650 | 0 | 5,802,650 | 9,864,506 | | | | |
| Roads restration | Set | 1 | | 63,840,417 | 0 | 63,840,417 | 108,528,708 | | | | |
| Total | | | | | 0 | 1,488,130,291 | 2,529,821,495 | | | | |

| VBO-U1 Bommanahalli Loan Coverage Ratio | | | | | | | | | | |
|---|------|----------|---------|-------------|---------|-------------|-------------|--|--|--|
| | | | Unit I | Price | C | ost | Total | | | |
| item | unit | Quantity | Foreign | Local | Foreign | Local | Total | | | |
| | | | JPY | INR | JPY | INR | JPY | | | |
| Providing Submain and t runk sewer | Set | 1 | | 218,055,035 | 0 | 218,055,035 | 370,693,559 | | | |
| Construction of STP | Set | 1 | | 253,000,000 | 0 | 253,000,000 | 430,100,000 | | | |
| Construction of Wet Well cum pumphouses | Set | 1 | | 0 | 0 | 0 | 0 | | | |
| Providing D.I.Pumping mains | Set | 1 | | 0 | 0 | 0 | 0 | | | |
| Restration of Storm Water Drains | Set | 1 | | 5,075,747 | 0 | 5,075,747 | 8,628,769 | | | |
| Roads restration | Set | 1 | | 31,042,368 | 0 | 31,042,368 | 52,772,025 | | | |
| Total | | | | | 0 | 507,173,149 | 862,194,354 | | | |

| VBO-U2 Bommanahalli | | | | | I | oan Coverage Ratio | 100 |
|---|------|----------|---------|-------------|---------|--------------------|-------------|
| | | | Unit I | Price | C | ost | Total |
| item | unit | Quantity | Foreign | Local | Foreign | Local | Total |
| | | | JPY | INR | JPY | INR | JPY |
| Providing Submain and t runk sewer | Set | 1 | | 97,645,970 | 0 | 97,645,970 | 165,998,149 |
| Construction of STP | Set | 1 | | 231,000,000 | 0 | 231,000,000 | 392,700,000 |
| Construction of Wet Well cum pumphouses | Set | 1 | | 0 | 0 | 0 | 0 |
| Providing D.I.Pumping mains | Set | 1 | | 0 | 0 | 0 | 0 |
| Restration of Storm Water Drains | Set | 1 | | 2,686,064 | 0 | 2,686,064 | 4,566,309 |
| Roads restration | Set | 1 | | 16,427,493 | 0 | 16,427,493 | 27,926,738 |
| Total | | | | | 0 | 347,759,528 | 591,191,197 |

| VBO-U3 Bommanahalli | /BO-U3 Bommanahalli Loan Coverage Ratio | | | | | | | | | |
|---|---|----------|---------|-------------|---------|-------------|-------------|--|--|--|
| | | | Unit I | Price | C | Total | | | | |
| item | unit | Quantity | Foreign | Local | Foreign | Local | Total | | | |
| | | | JPY | INR | JPY | INR | JPY | | | |
| Providing Submain and t runk sewer | Set | 1 | | 137,236,213 | 0 | 137,236,213 | 233,301,562 | | | |
| Construction of STP | Set | 1 | | 0 | 0 | 0 | 0 | | | |
| Construction of Wet Well cum pumphouses | Set | 1 | | 136,600,000 | 0 | 136,600,000 | 232,220,000 | | | |
| Providing D.I.Pumping mains | Set | 1 | | 73,800,000 | 0 | 73,800,000 | 125,460,000 | | | |
| Restration of Storm Water Drains | Set | 1 | | 3,360,569 | 0 | 3,360,569 | 5,712,967 | | | |
| Roads restration | Set | 1 | | 20,552,646 | 0 | 20,552,646 | 34,939,498 | | | |
| Total | | | | | 0 | 371,549,428 | 631,634,027 | | | |

| VBO-U4 Bommanahalli | VBO-U4 Bommanahalli Loan Coverage Ratio | | | | | | | | | | |
|---|---|----------|---------|-------------|---------|-------------|-------------|--|--|--|--|
| | | | Unit I | Price | Cost | | Total | | | | |
| item | unit | Quantity | Foreign | Local | Foreign | Local | Total | | | | |
| | | | JPY | INR | JPY | INR | JPY | | | | |
| Providing Submain and t runk sewer | Set | 1 | | 388,834,943 | 0 | 388,834,943 | 661,019,403 | | | | |
| Construction of STP | Set | 1 | | 0 | 0 | 0 | 0 | | | | |
| Construction of Wet Well cum pumphouses | Set | 1 | | 0 | 0 | 0 | 0 | | | | |
| Providing D.I.Pumping mains | Set | 1 | | 0 | 0 | 0 | 0 | | | | |
| Restration of Storm Water Drains | Set | 1 | | 6,877,620 | 0 | 6,877,620 | 11,691,954 | | | | |
| Roads restration | Set | 1 | | 42,062,306 | 0 | 42,062,306 | 71,505,921 | | | | |
| Total | | | | | 0 | 437,774,870 | 744,217,278 | | | | |

VR-U1 R.R.Nagar Loan Coverage Ratio 100 Unit Price Cost Total item unit Quantity Foreign Local Foreign Local JPY INR JPY INR JPY Providing Submain 120,064,504 0 120,064,504 204,109,656 Set 1 and trunk sewer Construction of STP Set 1 313,000,000 0 313,000,000 532,100,000 Construction of Wet Well cum Set 1 0 pumphouses Providing D.I.Pumping mains Set 1 20,839,000 0 20,839,000 35,426,300 Restration of Storm Water Set 1 3,359,968 0 3,359,968 5,711,945 Roads restration Set 1 21,247,632 0 21,247,632 36,120,975 Total 478,511,103 813,468,876

| VR-U2 R.R.Nagar | | | | | I | oan Coverage Ratio | 100 |
|---|------|----------|---------|-------------|---------|--------------------|-------------|
| | | | Unit I | Price | C | ost | Total |
| item | unit | Quantity | Foreign | Local | Foreign | Local | Total |
| | | | JPY | INR | JPY | INR | JPY |
| Providing Submain and t runk sewer | Set | 1 | | 28,296,980 | 0 | 28,296,980 | 48,104,867 |
| Construction of STP | Set | 1 | | 439,000,000 | 0 | 439,000,000 | 746,300,000 |
| Construction of Wet Well cum pumphouses | Set | 1 | | 51,900,000 | 0 | 51,900,000 | 88,230,000 |
| Providing D.I.Pumping mains | Set | 1 | | 0 | 0 | 0 | 0 |
| Restration of Storm Water Drains | Set | 1 | | 640,032 | 0 | 640,032 | 1,088,055 |
| Roads restration | Set | 1 | | 4,047,412 | 0 | 4,047,412 | 6,880,600 |
| Total | | | | | 0 | 523,884,425 | 890,603,522 |

17,446,315

494,519,461

VD-U1 Dasarahalli Loan Coverage Ratio 100 Unit Price Total item unit Quantity Foreign Local Foreign Local JPY INR JPY INR JPY Providing Submain 0 50,700,586 86,190,996 Set 50,700,586 and trunk sewer 228,000,000 0 228,000,000 387,600,000 Construction of STP Set 1 Construction of Wet Well cum 0 Set 1 pumphouses 0 0 0 0 Providing D.I.Pumping mains Set 1 Restration of Storm Water 0 1 1,930,676 1,930,676 3,282,149 Set Drains

10,262,539

0

0

10,262,539

290,893,801

Roads restration

Total

Set

1

| VD-U2 Dasarahalli | | | | | I | Loan Coverage Ratio | 100 |
|---|------|----------|---------|---------------|---------|---------------------|---------------|
| | | | Unit I | Price | C | ost | Total |
| item | unit | Quantity | Foreign | Local | Foreign | Local | Total |
| | | | JPY | INR | JPY | INR | JPY |
| Providing Submain and t runk sewer | Set | 1 | | 185,048,967 | 0 | 185,048,967 | 314,583,244 |
| Construction of STP | Set | 1 | | 1,181,000,000 | 0 | 1,181,000,000 | 2,007,700,000 |
| Construction of Wet Well cum pumphouses | Set | 1 | | 138,700,000 | 0 | 138,700,000 | 235,790,000 |
| Providing D.I.Pumping mains | Set | 1 | | 60,320,000 | 0 | 60,320,000 | 102,544,000 |
| Restration of Storm Water Drains | Set | 1 | | 6,069,324 | 0 | 6,069,324 | 10,317,851 |
| Roads restration | Set | 1 | | 32,261,586 | 0 | 32,261,586 | 54,844,696 |
| Total | | | | | 0 | 1,603,399,877 | 2,725,779,790 |

Cost Breakdown for the Consulting Services

USD = JPY 100 INR = JPY 1.7

| | | | | | INR | = JPY | 1.7 |
|----------------------------------|--------|-------|-----------|---------------|------------|------------------|---------------|
| | | | | | | | Combined |
| | | | Foreign | | | Portion | Total |
| | Llevid | / Mr. | (JP | | | NR | COON |
| | Unit | Qty. | Rate | Amount ('000) | Rate | Amount ('000) | ('000) JPY |
| A Remuneration | | | | | | | |
| 1 Professional (A) | M/M | 81 | 2,600,000 | 210,600 | 0 | 0 | 210,600 |
| 2 Professional (B) | M/M | 189 | 0 | 0 | 210,000 | 39,690 | 67,473 |
| 3 Supporting Staffs | M/M | 720 | 0 | 0 | 60,000 | 43,200 | 73,440 |
| Subtotal of A | | | | 210,600 | | 82,890 | 351,513 |
| B Direct Cost | | | | | | | |
| 1 International Airfare | | 6.75 | 250,000 | 1,688 | | 0 | 1,688 |
| 2 Domestic Airfare | | 90 | - | 0 | 18,000 | 1,620 | 2,754 |
| 3 Domestic Travel | | | | 0 | 3,000 | 0 | 0 |
| 3 Accommodation Allowance | Month | 81 | | 0 | 30,000 | 2,430 | 4,131 |
| | Month | 189 | | 0 | 20,000 | 3,780 | 6,426 |
| | Month | 720 | | 0 | 5,000 | 3,600 | 6,120 |
| 4 Vehicle Rental | Month | 90 | | 0 | 47,000 | 4,230 | 7,191 |
| 5 Office Rental | M/M | 990 | | 0 | 165,000 | 163,350 | 277,695 |
| 6 International Communications | M/M | 81 | | 0 | 25,000 | 2,025 | 3,443 |
| 7 Domestic Communications | M/M | 990 | | 0 | 20,000 | 19,800 | 33,660 |
| 8 Office Supply | M/M | 1 | | 0 | 10,000,000 | 10,000 | 17,000 |
| 9 Office Furniture and Equipment | M/M | 1 | | 0 | 3,000,000 | 3,000 | 5,100 |
| 10 Report Preparation | Month | 70 | | 0 | 75,000 | 5,250 | 8,925 |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| Subtotal of B | | | | 1,688 | | 219,085 | 374,132 |
| Total | | | | 212,288 | | 301,975 | 725,645 |
| | | | | | | | |

Summary of Cost for Construction of Main facility of 110 Village's Sewarage

| | Item | | Million I | NR |
|-----|----------------------------|---------------|-----------|--------|
| | | Open cut | 198,944MR | 2,370 |
| 0.1 | Providing Submain | Trenchless | 1,130MR | 218 |
| S-1 | and trunk sewer | Miscellaneous | - | 7 |
| | | Sub-Total | - | 2,595 |
| S-2 | Construction of | STP | 14 NOS | 4,489 |
| S-3 | Construction of pumphouses | Wet Well cum | 7 NOS | 521 |
| S-4 | Providing D.I.P | rumping mains | 15,310MR | 357 |
| S-5 | Restration of St Drains | orm Water | - | 45 |
| S-6 | Roads restration | 1 | 1 (4) | 335 |
| | Direct cost | Total | | 8,341 |
| | Indirect cos | t Total | | 2,786 |
| | Land acqui | sition | | 0 |
| | Grand T | otal | | 11,127 |

| The control of the | | | | | Summary of Dire | Direct | Cost for Construction o | † Main T | ct Cost for Construction of Main facility of 110 Village's Sewarage | arage | | | | - | | Г |
|--|---------------|-----------------|--------------------------------------|-------------------------|-----------------|--------|-------------------------|----------|---|---------|---------------------|-------|------------|---------|------------------------|-----|
| | Zone | | Rem | | Total | | | | | | | | Package-U4 | | | |
| 1 | | | | Open cut | 300~1001 48,598 | MR | DIA 300~60 19,127 | MR | DIA 300~601 7,883 | 50.6 | DIA 300~100(21,588 | 297.1 | | | J | œ |
| | | ā | Providing Submain | Trenchless | | | DIA 400~60 | | DIA 300∼ | 20.4 | | | | | | |
| 1 20 Controlled 20 C | | , | and trunk sewer | Miscellaneous | | | 6.0 | | 0.3 | 0.1 | | 0.4 | | | | |
| 100 | | | | | | 8 | | 281 | | 71.2 | | 297.5 | | | | |
| 1 | Bytrayanapura | | Construction of STF | W-II | 4 NOS | ,5, | | 22 | | 278.0 | - | 216.0 | | | 4 NOS | T |
| 1 | | , V | Providing D.I.Pumpin | mein dum pumpnouses | 202 | | | + | DIA250 ~ 1,380 | 5.9 | | | | | 200 | n |
| | | S-5 | Restration of Storm | Water Drains | | | 8.0 | | | 1.3 | | 3.6 | | | | |
| | | 9-S | Roads restration | | | 3 | 90.3 | 3. | 1.6 | 13.0 | | 35.7 | | | | |
| | | ╽ | Tota | | | | | 4 | | 369.4 | | 852.7 | | | | Ī |
| 1 | | | | Open cut | | | DIA 300~50 7,632 | _ | DIA 300~801 36,988 | _ | | | | | | œ |
| Contentioned PTA Part Pa | | <u>.</u> | Providing Submain | Trenchless | | | 31.9 | | DIA 300~60 | 31.9 | | | | | | |
| 1 1 1 1 1 1 1 1 1 1 | | | | Sub-T-del | | | 60. | 149 | 3.0 | 587.0 | | | | | | T |
| Page Controlled With With With With With With With With | | ĵ | Construction of STP | | SON 1 | | 0.00 | É | | 472.0 | | | | | NOS 1 | T |
| 1 | Mahadevpura | 8-8 | Construction of Wet | Well cum pumphouses | 1 NOS | 182 | 33.4 | | 1 NOS | 183.4 | | | | | | T |
| 1 | | \$-S | Providing D.I.Pumpin | ş mains | ~008 | | 19.1 | | 5,300 | 196.1 | | | | | | Ī |
| 1 | | S-5 | Restration of Storm | Water Drains | | | 7.0 | | | 5.8 | | | | | | |
| | | å | Roads restration | | | • | 0.77 | 7 | 3.2 | 63.8 | | | | | | |
| Provincia classical control | | _ | Tota | | | | | | | 1,488.1 | | | | | | |
| 1 | | | | Open cut | 300~120 | Æ | DIA 300~70 | Σ | DIA 300~60 | 85.1 | DIA 300∼500 12,087 | 104.1 | 24,737 MR | 372.0 | | œ |
| 1 | | S-1 | Providing Submain | Trenchless | | | DIA 500∼60 | | DIA 300∼ | 11.9 | DIA 400∼ | 32.3 | 80 MR | 15.2 | | |
| | | | | Sub-Total | | 84 | 8 17 | 916 | 3.1 | 97.6 | | 137.9 | | 388.8 | | T |
| 2-12 Concentration of the name parabosas 1822 Concentratio | | S-2 | Construction of STP | | 2 NOS | 48 | | 255 | | 231.0 | | ! | | | 3 NOS | T |
| 5-4 Providet District Column 1-12 1- | Bommanahalli | 8-8 | Construction of Wet | Well cum pumphouses | 1 NOS | 122 | | | | | - | 136.6 | | | | |
| 1 1 1 1 1 1 1 1 1 1 | | \$ * | Providing D.I.Pumpin | g mains | ~009 | | 73.8 | | | | 3,000 | 73.8 | | | | |
| 1 | | S-5 | Restration of Storm | Water Drains | | T I | 18.0 | 1 | 5.1 | 2.7 | | 3.4 | | 6.9 | | |
| Particular Par | | ę, | Roads restration | | | = | 10.1 | 3 | 0.1 | 16.4 | | 20.6 | | 42.1 | | |
| Providite Scheme Tracticies Tracticies | | _ | Tota | | | | : | 4 | | 347.8 | | 371.5 | | | | T |
| | | | | Open cut | | | DIA 300~50 | Σ | DIA 300~40i | 28.2 | | | | | | r . |
| | | <u>S</u> | Providing Submain and trunk sewer | Miscellaneous | | | 200 MI | | 13 | 0.1 | | | | | | |
| 9-24 Control C | | | | Sub-Total | | 1 | 18.4 | 120 | 9.1 | 28.3 | | | | | | T |
| | | S-2 | Construction of STP | | 2 NOS | 2 | | 315 | | 439.0 | | | | | 3 NOS | Ī |
| 9-4 Providing DLP mayney makes DIA 200-400 2,200 MR 200 DIA 200-400 200 MR 200 DIA 200-400 200 MR | K.K.Nagar | S-3 | Construction of Wet | Well cum pumphouses | 2 NOS | | 91.9 | | | 51.9 | | | | | 1 NOS | |
| St-6 Resident winter Dailes 4.0 2.2 Resident winter Dailes 4.0 2.2 4.0 Diameter Dailes | | \$ - | Providing D.I.Pumpin | g mains | | | DIA 250~40 | | 0.8 | | | | | | | |
| 5-6 Roadin entironical control contro | | S-2 | Restration of Storm | Water Drains | | | 4.0 | | 3.4 | 9.0 | | | | | | Т |
| Providing Submain Coperator Coperato | | φ | Roads restration | | | 7 8 | 25.3 | 2 1 | 2. | 4.0 | | | | | | |
| 5-1 Providing Submining Transcrises Dia 200-200 H 20 MR 102 Dia 200-200 H 20 MR 102 Dia 200-200 H 20 MR 102 Dia 200-200 H 20 MR 103 Dia 200-200 H 20 MR 104 Dia 200-200 H 20 MR 105 Dia 200- | | ļ | 5 | | | | DIA 300~70 | + | DIA 300~70 | 1 | | l | | | | œ |
| 2-3 Construction of Standards and Tunik ewer Miscellancous 0.6 0.0 0 | | į | Providing Submain | Trenchless | | | DIA 300∼ | | DIA 200∼ | | | L | | | | |
| S-A Construction of STP Sub-Total 5 NOS 1 88.0 4 NOS 1 88.0 5 NOS 1 88.0 1 188.0 1 1 NOS 5 NOS 1 NOS <th< th=""><th></th><th>Ī</th><th>and trunk sewer</th><th>Miscellaneous</th><th></th><th></th><th></th><th></th><th></th><th>0.5</th><th></th><th></th><th></th><th></th><th></th><th></th></th<> | | Ī | and trunk sewer | Miscellaneous | | | | | | 0.5 | | | | | | |
| S-9 Construction of SIP | | | | | | 22 | | æ | | 185.0 | | | | | 1 | Т |
| S−1 Construction of Storm Water Drains DA 200–600 3.400 MR 613 Annual Construction of Storm Water Drains BDA 200–600 3.400 MR 613 Annual Construction of Storm Water Drains BDA 200–600 3.400 MR Construction of Storm Water Drains BDA 200–600 3.400 MR Construction of Storm Water Drains BDA 200–600 3.400 MR Construction of Storm Water Drains BDA 200–600 1.184-35 Construction of Storm Water Drains BDA 200–600 1.180-45 Construction of Storm Water Drains BDA 200–600 1.180-45 Construction of Storm Water Drains BDA 200–600 DDA 200–600 | Dasarahalli | S-2 | Construction of STF | | 5 NOS | ±. | | Ž | | 1,181.0 | | | | | S NOS | |
| S-6 Restration of Storm Meter Drailes 4.25 1.13 6.13 6.13 9.10 | | 2 4 | Providing D I Pumping | Well cum pumphouses | g | | m38.7 | 1 | | 138.7 | | İ | | | 202 | Τ. |
| S-6 Roader restration 42.5 16.2 32.2 Post office Submish 42.5 1.003.4 R.2 1.003.4 R.2 1.003.4 R.2 1.003.4 R.2 R.2 <th></th> <th>9</th> <th>Restration of Storm</th> <th>Water Drains</th> <th></th> <th></th> <th>8.0</th> <th></th> <th>00 007 007</th> <th>9</th> <th></th> <th></th> <th></th> <th></th> <th></th> <th>Τ</th> | | 9 | Restration of Storm | Water Drains | | | 8.0 | | 00 007 007 | 9 | | | | | | Τ |
| S-1 Total Distriction 1,894.3 290.9 1,003.4 In 1,003.4 | | 8-8 | Roads restration | | | • | 12.5 | 11 | 0.3 | 32.3 | | | | | | П |
| Providing Submain Terebless | | | Tota | | | | 34.3 | 290 | 0.0 | 1,603.4 | | | | | | |
| S-1 Providing Solument And Color Soluments Providing Solument And Color Soluments Providing Solument And Color A | | | : | Open cut | | | 89.6 | \ | _ | / | | / | | 4 | DIA 300~120(338,333 M | Œ, |
| S-2 Construction of YRP Mode multiple and a state of | | ŗ, | Providing Submain and trunk sewer | Miscellaneous | | | £/1 | \ | _ | \ | ` | \ | \ | \perp | | r |
| S-2 Construction of STIP 14 NOS 4489D S-4 Provider United in Marker Drains DA 200-800 15310 MR 850 Back of State and S | | | | Sub-Total | | 2,58 | 97 | \ | _ | | \ | | \ | | | T |
| S-4 Providing DLPumphe mains 7 NOS 55.05 S-4 Providing DLPumphe mains DIA 200-800 53.10 MR 357.00 DIA 150-250 S-5 Retaration of Som Water Drains 45.00 Brain Social MR 358.20 Brain Social MR 358.20 S-6 Repertation 358.2 Brain Social MR 358.2 Brain Social MR Brain Social | Total | S-2 | Construction of STP | | 14 NOS | 4,4 | 080 | | <u> </u> | | \ | | \ | | 16 NOS | П |
| Provinging Unitary Proving | | S-9 | Construction of Wet | Well cum pumphouses | S | | | | \ | | \ | | \ | | 'n | ٦, |
| Roads restration Total | | , v | Providing D.L.Pumpin | g mains Water Drains | | + | 150 | | \ | | \ | | \ | | | r |
| | | 9-8 | Roads restration | | | 8 | 16.2 | | \ | | \ | | \ | | | T |
| | | | Tota | | | 8,34 | 114 | | | | | | _ | | | П |

Summary of Direct Cost for Construction of Main sewers and Pumping Mains

| | | | | | Sum | mary | סד ט | | | . tor | Cons | truct | ion o | T Main | sewer | s and | Pump | | | | | | |
|--|---------|------|-----------------|---------|---------|----------|----------|---------|----------|---------|---------|----------|----------|-------------|-------------|-------------|------------|-----------|------------|------------|---------|----------|----------|
| Marchas Marc | Package | | Item | | | | | | | | | | | | | | | | | | | | |
| HereMay 100 100 100 100 100 100 100 100 100 10 | | | | | | 450 Dia | 500 Dia | 600 Dia | 700 Dia | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia | | | 450 Dia | 500 Dia | 600 Dia | 700 Dia | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| Marchang | | | | | 4,249 | | 4,565 | | | | | | | 16,348,800 | 41,215,300 | | | | | | | | |
| | | Opun | | 351 | | | 844 | | | | | | | 10,038,600 | | | 24,636,040 | | | | | | |
| West | | | | 2 010 | | | 5.400 | | | | | | | 22 047 400 | | | 71 100 040 | | | | | | |
| Marchard 18 | VBY-U1 | | Sub Total | 3,919 | 9,431 | | 5,409 | | 127 | | | | | 33,047,400 | 135,077,120 | | 71,199,040 | | 920 | | | | |
| | | | | | | 700 Dia | | | | | | | | | | 700 Dia | | | | | | | |
| 1 | | | Trenchless | 30 | 140 | | | | | | | | | 5,700,000 | 32,200,000 | | | | | | | | |
| 1 | ŀ | | | 250 Dia | 300 Dia | | | 1 | /0 | | | | | 250 Dia | 300 Dia | | 1 | 37,900,0 | 100 | ı | | ı . | Γ |
| March Mar | | D.I. | Pumping mains | | | | | | | | | | | | | | | | | | | | |
| March Mar | | | | | | | | | | | | | | | | | | | | | | | |
| Mathia M | | | | | | | 500 Dia | | 700 Dia | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia | | | | 500 Dia | | 700 Dia | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| Mathieum | | | | | | | | 102 | | | | | | | | | | 010,000 | | | | | |
| | | | Above 4 Up to 6 | 73 | 45 | | | | | | | | | 2,087,800 | 1,291,500 | | | | | | | | |
| | | | Above 6 | 2 702 | 2.005 | 174 | | 100 | | | | | | 00 070 000 | 00 100 700 | 1 577 000 | | E40 000 | | | | | |
| | VBY-U2 | | Sub Total | 3,702 | 3,303 | 174 | | | 383 | | | | | 20,370,200 | 20,132,700 | 1,377,000 | | | 500 | | | | 1 |
| No. Process | | | • | | | | | | | | | | | | | | | | | | | | |
| | | | Trenchless | 120 | | | | 1: | 20 | | | | | 20,400,000 | | | | 20 400 0 | 000 | | | | |
| Part | ŧ | | | 250 Dia | I | | | | Ī | | | | | 250 Dia | | | · | 20,100, | Ī | | | | |
| March Marc | | D.I. | Pumping mains | 1,380 | | | | | | | | | | 5,934,000 | | | | | | | | | |
| May | | | Dth (MD) | 200 Di- | 400 Di- | 450 Di- | E00 Di- | | | 000 Di- | 000 Di- | 1000 Di- | 1000 Di- | 200 Die | 400 Di- | 450 Di- | 500 Di- | | | 000 Di- | 000 Di- | 1000 Di- | 1000 Di- |
| Marchand | | | | | | 430 DIS | | OUV DIS | 700 DIS | ovo Dia | ann Dig | TOOU DIS | 1200 DIS | | | 430 DIS | | OUV DIS | 700 DIS | OUJ DIS | and Dia | TOUR DIS | 1200 DIB |
| March Mar | | Onum | Above 2 Up to 4 | 2,675 | 852 | | 244 | | | | | | | 25,676,160 | 8,262,460 | | 2,488,800 | | | | | | |
| March Mar | | | | 653 | 1,045 | | | | 766 | | | 100 | | 18,678,660 | 29,994,370 | | | | 23,430,420 | | | 401000 | |
| Part | | | | 9,702 | 5,661 | | | | 1,645 | | | | | 69,853,620 | 53,690,460 | | | | 33,630.300 | | | | |
| Part | VBY-U3 | | Sub Total | | | | | | | | | | | | | | | | | | | | |
| Part | | | Trenchioss | | | | | | | | | | | | | \Box | \vdash | | | | | | |
| Note Part | | | Trenchiess | | | | | | | | | | | | | | | | | l | | l | |
| Note Part | | | | | | | | | | | | | | | | | | | | | | | |
| May | | D.I. | Pumping mains | | | | | | | | | | | | لـــــــا | | | | | | | | |
| May | | | Depth (MR) | 300 Dia | 400 Dia | 450 Dia | 500 Dia | 600 Dia | 700 Dia | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia | 300 Dia | 400 Dia | 450 Dia | 500 Dia | 600 Dia | 700 Dia | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| March Marc | | | Up to 2 | 317 | | 169 | 1,036 | | | | | | 2.0 | 1,266,800 | - | 727,990 | 4,764,220 | | | | | | |
| March Marc | | Opun | | | | | | | | | | | | | ——— | | | | | | | | |
| May | | cut | | | | 217 | 50 | | | | | | | | | 6,265,520 | 1,460,000 | | | | | | |
| | | | | 3,648 | | 513 | 1,296 | | | | | | | | | 8,245,860 | 8,371,320 | | | | | | |
| Part | VM-U1 | | 000 1000 | | | | | 7,6 | 332 | | | | | ļ | | | | 143,185, | 080 | 1 | | | |
| Part | | | Trenchless | | | <u> </u> | <u> </u> | | | | | | | | | | - | | | | | | |
| March Marc | | | | | | | | | | | | | | | | | | | l | I | | l | |
| March Marc | | | | | | | | | | | | | | | | | | | | | | | |
| May 1 | | D1. | Pumping mains | | | | | | | | | | | | | | | | | | | | |
| Marco Sale | | | Depth (MR) | 300 Dia | 400 Dia | 450 Dia | 500 Dia | 600 Dia | 700 Dia | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia | 300 Dia | 400 Dia | 450 Dia | 500 Dia | 600 Dia | 700 Dia | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| Note Part | | | | | | | | | | | | | | | | | | | | | | | |
| Make | | | | | 394 | | | | | | | | | | 3,821,800 | | | | | | | | |
| Value Valu | | cut | | | | | | | | | | | | | | | | | | | | | |
| Value Part | | | Sub Total | 14,592 | 978 | 10,836 | 1,400 | | | 1,931 | | | | 172,491,900 | 6,216,200 | 135,674,600 | 25,619,000 | | | 57,781,200 | | | |
| Part | VM-U2 | | | 300 Dia | 600 Dia | | | 36, | 988 | | | | | 300 Dia | 600 Dia | | 1 | 534,325, | 700 | ı | | I | Γ |
| Value Part | | | Trenchless | | | | | | | | | | | | | | | | | | | | |
| Part | | | | | | | | 11 | 70 | | | | | | | | | 31,900,0 | 000 | 1 | | | |
| Value | | DJ | Pumping mains | | | <u> </u> | <u> </u> | | | | | | | | | | - | | | | | | |
| Value Part | | | | | | | | | 300 | | | | | | | | | | | ! | | ! | |
| Marcon M | | | | | | | | | | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia | | | | | | | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| Value | | | | | | | | | | | | | | | | | | | | | | | |
| March Marc | | | | | | | .,_0, | | | | | | | | | -,-30,400 | | | | | | | |
| VBO-14 Sile | | | Above 6 | 0.30 | 0.46- | 70- | 4.05 | 0.54- | 004 | | | | | 00.004.555 | E4 700 | 0.000 | 10.101 | 27.027. | 20 500 15 | | | | |
| Trenchess 500 Da 600 Da | VBO-U1 | | Sub Total | 3,707 | 0,495 | 735 | 1,372 | | | | | | | 20,004,600 | 54,/82,900 | 0,330,100 | 13,484,800 | | | | | | |
| Purposing mains | ļ | | | | | | | | | | | | | | | | | | | | | | |
| Page | | | Trenchless | 100 | 100 | | | - | 00 | | | | | 21,000,000 | 23,000,000 | | | 44 000 7 | 000 | <u> </u> | | | |
| Paper Mark | ŀ | | | | | | | | | | | | | | | | | | | | | | |
| VBO-UE V | | D.I. | Pumping mains | | | | | | | | | | | | | | | | | | | | |
| VBO-UE V | | | Dooth (MD) | 200 01- | 400.00 | 450.00 | 500 Di- | 600 01- | 700 01- | 900 51- | 900 51- | 1000 01 | 1200 D | 200 01- | 400 DI- | 450 01- | 500 Di- | 600 01- | 700 01- | 900 01- | 900 Di- | 1000 D | 1200 D |
| VBO-U2 VBO-U2 VBO-U2 VBO-U2 VBO-U2 VBO-U2 VBO-U2 VBO-U3 VBO-U3 Above 2 Up to 4 49 to 16 6 285 297 1 15 1 15 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | | | | | | 470 DIS | | | 700 018 | oou Dia | out Dia | 1000 Dia | 1200 Dia | | | 4/0 DIS | | | 700 Dia | out Dia | ouu Dia | 1000 Dia | 1200 Dia |
| VBO-U2 VBO-U2 VBO-U3 VBO-U4 Above 4 Da to 1 | | 0 | Above 2 Up to 4 | | 3,333 | 166 | 697 | | | | | | | | 32,330,100 | 1,643,400 | 7,109,400 | | | | | | |
| VBO-U2 Sub Total 2,785 5,018 168 1,511 201 | | cut | | | 285 | | | | \vdash | _ | | | | | 8,179,500 | H | | | | | _ | | |
| VBO-US Sub Cital | | | | 2,765 | 5,018 | 166 | | 201 | | | | | | 15,254,400 | 46,249,600 | 1,643,400 | | 1,821,300 | | | | | |
| VBO-US Trenchless Trenchless To | VBO-U2 | | Sub Total | | | | | | 361 | | | | | | | | | | 00 | | | | |
| VBO-UB D1Pumping mains | | | Tranchioss | | | \vdash | \vdash | | | | | | | | | H | \vdash | | | | | | |
| VBO-US Depth (Mpt) S00 Dis 400 Dis 450 Dis 500 Dis 600 Dis 700 Dis 800 Dis 500 Dis 1000 Dis 1200 Dis 1220 D | | | discines5 | /0 | | | | 7 | 10 | | | | | 11,300,000 | | | | 11,900,0 | 000 | <u> </u> | | | |
| VBO-US Depth (MR) Side | ļ | | | | | | | | | | | | | | | | | | | | | | |
| Up to 2 3.05 2.306 31 | | D.I. | Pumping mains | | | | | L | | | | | | | | | | | L | L | | | L |
| Up to 2 3.05 2.306 31 | | | Depth (MR) | 300 Dia | 400 Dia | 450 Dia | 500 Dia | 600 Dia | 700 Dia | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia | 300 Dia | 400 Dia | 450 Dia | 500 Dia | 600 Dia | 700 Dia | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| VBO-U3 | | Up to 2 | 3,051 | 2,306 | | 31 | | | | | | | 12,204,000 | 9,454,600 | | 142,600 | | | | | | |
| VBO-U3 VBO-U3 VBO-U3 VBO-U3 Above 6 5.72 5.392 5.15 458 15.087 5.072.600 4.488.000 1.08.0 | | | | | | 515 | 427 | | | | | | | | | 5,098,500 | 4,355,400 | | | | | | |
| VBO-US Sub Total 5/12 5/38 5/15 458 5/30 5/ | | | | 6/7 | 233 | | | - | | | | | | 19,362,200 | 0,687,100 | | | | | | | | |
| VBO-US 12,007 104,120,000 Trenchless 170 1 232,300,000 1 104,120,000 Trenchless 170 32,300,000 32,300,000 D1Pumping mains 3,000 1 0 000 is 1 1 | | | | 5,722 | 5,392 | 515 | 458 | | | | | | | 50,708,600 | 43,815,800 | 5,098,500 | 4,498,000 | | | | | | |
| Trenchless 170 32,300,000 32,300, | VBO-U3 | | 1000 | 400 Di- | | | | 12, | 087 | | | | | 400 01- | | | | 104,120, | 900 | | | | |
| 170 32,200,000 | | | Trenchless | | | \vdash | \vdash | | | | | | | | | | | | | | | | |
| D1Pumping mains 3,000 73,800,000 | | | | | | | | 1 | 70 | | | | | | | | | 32,300,0 | 000 | | | | |
| | | | | 600 Dia | | | | | | | | | | | | | | | | 1 | | | |
| | | ۲. | Pumping mai- | 0.00- | | | | | | | | | | | | | | | | | | | |
| | | D.I. | Pumping mains | 3,000 | | | | 9.0 | 000 | | | | | 73,800,000 | | | | 73.800 (| 000 | | | | |

| | | Depth (MR) | 300 Dia | 100 D | 450 Dia | 500 Dia | 600 Dia | 200 D | 000 D | 900 Dia | 1000 Dia | 4000 D | 000 D: | 400 D | 450 D. | 500 Dia | 000 D | 700 0: | 800 Dia | 900 Dia | 1000 Dia | 4000 D |
|--------|---------------------|---|--|---|--|---|---|--|--------------------------------|--------------------------------|----------------------|-------------------------------|---|--|---|---|--|--|--|---|--|-------------------------------------|
| | | Up to 2 | 300 Dia 3.822 | 400 Dia 1.381 | 450 Dia 348 | 500 Dia | 112 | 700 Dia 279 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia | 300 Dia 15.286.400 | 400 Dia 5,662,100 | 450 Dia 1.496.400 | 500 Dia | 600 Dia 593,600 | 700 Dia 1,674,000 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| | | Above 2 Up to 4 | 4,738 | 2,070 | 348 | 93 | 894 | 197 | 211 | 3,430 | 347 | 328 | 45,486,144 | 20,074,538 | 3.663.000 | 943,500 | 9,744,600 | 2,285,200 | 2 637 500 | 54 194 000 | 5,725,500 | 6,297,600 |
| | Opun | | 1,485 | 781 | 102 | 964 | 34 | 197 | 211 | 606 | 753 | 680 | 42,471,000 | 22,425,319 | 2,948,956 | 28,137,996 | 1,016,600 | 2,203,200 | 2,037,300 | 21.088.800 | | 25,976,000 |
| | cut | Above 4 Up to 6 | 126 | 268 | 102 | 904 | 34 | | | 600 | /55 | 319 | 3.943.800 | 8,415,200 | 2,940,930 | 20,137,990 | 1,010,000 | | | 21,000,000 | 20,731,300 | 13,047,100 |
| | | Above 6 | 10,171 | 4,500 | 820 | 1,056 | 1,040 | 476 | 211 | 4,036 | 1,100 | 1,327 | 107,187,344 | 56,577,157 | 8,108,356 | 29,081,496 | 11,354,800 | 3,959,200 | 2,637,500 | 75,282,800 | 20 457 000 | |
| VBO-U4 | | Sub Total | 10,171 | 4,300 | 020 | 1,036 | | 737 | 211 | 4,036 | 1,100 | 1,327 | 107,107,344 | 36,377,137 | 0,100,330 | 29,061,490 | 371,966, | | 2,037,300 | 73,202,000 | 32,437,000 | 45,320,700 |
| .50 5. | | | 400 Dia | 450 Dia | l | | | | l | l | | | 400 Dia | 450 Dia | | | 071,000, | | | | | |
| | | Trenchless | 30 | 50 | | | | | | | | | 5,700,000 | 9.500.000 | | | | | | | | |
| | | | | | L | | | 10 | | | | | 0,700,000 | 5,000,000 | | | 15,200,0 | 000 | | | | |
| | | | | | | | | | | | | | | | | | | | | | | |
| | D.I. | Pumping mains | | | | | | | | | | | | | | | | | | | | |
| | | | | | ! | | | | | | | | | | | | | | | | | |
| | | Depth (MR) | 300 Dia | 400 Dia | 450 Dia | 500 Dia | 600 Dia | 700 Dia | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia | 300 Dia | 400 Dia | 450 Dia | 500 Dia | 600 Dia | 700 Dia | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| | | Up to 2 | 4,241 | 1,437 | 36 | 199 | | | | | | | 16,964,000 | 5,891,700 | 154,800 | 915,400 | | | | | | |
| | Opun | Above 2 Up to 4 | 3,311 | 1,297 | 92 | 382 | | | | | | | 31,785,600 | 12,580,900 | 910,800 | 3,896,400 | | | | | | |
| | cut | Above 4 Up to 6 | 1,206 | 217 | | 29 | | | | | | | 34,491,600 | 6,227,900 | | 846,800 | | | | | | |
| | | Above 6 | | | | | | | | | | | | | | | | | | | | |
| VR-U1 | | Sub Total | 8,758 | 2,951 | 128 | 610 | 10 | 447 | | | | | 83,241,200 | 24,700,500 | 1,065,600 | 5,658,600 | 114,665, | 000 | | | | |
| *K-01 | | | 300 Dia | | г | | 14, | | г | г | | | 300 Dia | | | | 114,000, | - | | | | |
| | | Trenchless | 300 Dia | | | | | | | | | | 5,100,000 | | | | | | | | | |
| | | | | | | | | 10 | | | | | 0,100,000 | | | | 5,100,0 | 00 | | | | |
| | | | 250 Dia | 400 Dia | | | | | | | | | 250 Dia | 400 Dia | | | -,,,, | | | | | |
| | D.I. | Pumping mains | 730 | 1,500 | | | | | | | | | 3,139,000 | 17,700,000 | | | | | | | | |
| | | | | | | | 2,1 | 230 | | | | | | | | | 20,839,0 | 000 | | | | |
| | | Depth (MR) | 300 Dia | 400 Dia | 450 Dia | 500 Dia | 600 Dia | 700 Dia | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia | 300 Dia | 400 Dia | 450 Dia | 500 Dia | 600 Dia | 700 Dia | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| | | Up to 2 | 411 | 569 | | | | | | | | | 1,644,000 | 2,332,900 | | | | | | | | |
| | | Above 2 Up to 4 | 486 | 333 | | | | | | | | | 4,665,600 | 3,230,100 | | | | | | | | |
| | Opun | Above 4 Up to 6 | 489 | 83 | | | | | | | | | 13,985,400 | 2,382,100 | | | | | | | | |
| | | Above 6 | | | | | | | | | | | | | | | | | | | | |
| | | Sub Total | 1,386 | 985 | | | | | | | | | 20,295,000 | 7,945,100 | | | 20.010 | | | | | |
| VR-U2 | | | | | | | 2,: | 371 | | | - | | | | | | 28,240,1 | 00 | | | _ | |
| | | Trenchless | | | | | | | | | | | | | | | | | | | | |
| | | Trenchiess | | | | | | | | | | | | | | | | | | | | |
| } | | | - | | | | | | | | 1 | | | | | | | | | | | |
| | DJ | Pumping mains | | | | | | | | | | | | | | | | | | | | |
| | | | | | l | | | l | l | l | | | | | | | | | | | | |
| | | Depth (MR) | 300 Dia | 400 Dia | 450 Dia | 500 Dia | 600 Dia | 700 Dia | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia | 300 Dia | 400 Dia | 450 Dia | 500 Dia | 600 Dia | 700 Dia | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| | | Up to 2 | 2,929 | 1,056 | | 88 | | 52 | | | | | 11,716,000 | 4,329,600 | | 404,800 | | 312,000 | | | | |
| | | Above 2 Up to 4 | 1,230 | 663 | | | | 185 | | | | | 11,808,000 | 6,431,100 | | | | 2,146,000 | | | | |
| | Opun | Above 4 Up to 6 | | | | | | | | | | | | 1,836,800 | | | | | | | | |
| | cut | Above 4 Up to 6 | 48 | 64 | | | | | | | | | 1,372,800 | 1,030,000 | | | | | | | | |
| | cut | Above 6 | 48 | | | | | | | | | | | | | | | | | | | |
| | cut | | | 1,783 | | 88 | | 237 | | | | | 1,372,800 24,896,800 | 12,597,500 | | 404,800 | | 2,458,000 | | | | |
| VD-U1 | cut | Above 6 | 4,207 | | | 88 | 6,3 | 237 | | | | | 24,896,800 | | | 404,800 | 40,357,1 | | | | | |
| VD-U1 | | Above 6 Sub Total | 48 4,207 300 Dia | | | 88 | 6,: | | | | | | 24,896,800 300 Dia | | | 404,800 | 40,357,1 | | | | | |
| VD-U1 | | Above 6 | 4,207 | | | 88 | | 315 | | | | | 24,896,800 | | | 404,800 | | 00 | | | | |
| VD-U1 | | Above 6 Sub Total | 48 4,207 300 Dia | | | 88 | | | | | | | 24,896,800 300 Dia | | | 404,800 | 40,357,1 10,200,0 | 00 | | | | |
| VD-U1 | | Above 6 Sub Total | 48 4,207 300 Dia | | | 88 | | 315 | | | | | 24,896,800 300 Dia | | | 404,800 | | 00 | | | | |
| VD-U1 | | Above 6 Sub Total Trenchless | 48 4,207 300 Dia | | | 88 | | 315 | | | | | 24,896,800 300 Dia | | | 404,800 | | 00 | | | | |
| VD-U1 | | Above 6 Sub Total Trenchless | 48 4,207 300 Dia | | 450 Dia | 88 88 | | 315 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia | 24,896,800 300 Dia | | 450 Dia | 404,800 500 Dia | | 00 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| VD-U1 | | Above 6 Sub Total Trenchless Pumping mains | 48 4,207 300 Dia 60 | 1,783 | 450 Dia 363 | | (| 315 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia | 24,896,800 300 Dia 10,200,000 | 12,597,500 | 450 Dia 1,560,900 | | 10,200,0 | 000 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| VD-U1 | DI | Above 6 Sub Total Trenchless Pumping mains Depth (MR) Up to 2 Above 2 Up to 4 | 48 4,207 300 Dia 60 300 Dia 6,819 3,496 | 1,783 400 Dia 2,157 2,142 | | 500 Dis 212 701 | 600 Dia 471 835 | 315 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia | 24,896,800 300 Dia 10,200,000 300 Dia 27,276,000 33,561,600 | 12,597,500 400 Dia 8,843,700 20,777,400 | | 500 Dia 975,200 7,150,200 | 10,200,0 600 Dia 2,496,300 9,101,500 | 000 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| VD-U1 | | Above 6 Sub Total Trenchless Pumping mains Depth (MR) Up to 2 Above 2 Up to 4 Above 4 Up to 6 | 48 4,207 300 Dia 60 300 Dia 6,819 3,496 426 | 1,783 400 Dia 2,157 2,142 55 | 363 | 500 Dia 212 | 600 Dia 471 835 587 | 700 Dia | 800 Dia | 900 Dia | 1000 Día | 1200 Dis | 24,896,800 300 Dia 10,200,000 300 Dia 27,276,000 33,561,600 12,183,600 | 12,597,500 400 Dia 8,843,700 20,777,400 1,578,500 | 1,560,900 | 500 Dia 975,200 | 10,200,6 600 Dia 2,496,300 9,101,500 17,551,300 | 00 000 700 Dia | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| VD-U1 | D.I. | Above 6 Sub Total Trenchless Pumping mains Depth (MR) Up to 2 Above 2 Up to 4 | 300 Dia 60 300 Dia 6.819 3.496 426 211 | 1,783 400 Dia 2,157 2,142 55 36 | 363 94 | 500 Dia 212 701 67 | 600 Dia 471 835 587 392 | 700 Dia | 800 Dia | 900 Dia | 1000 Dis | 1200 Dia | 24,896,800 300 Dia 10,200,000 300 Dia 27,276,000 32,183,600 6,604,300 | 12,597,500 400 Dia 8,843,700 20,777,400 1,578,500 1,130,400 | 1,560,900 930,600 | 500 Dia 975,200 7,150,200 1,956,400 | 10,200,6 600 Dia 2,496,300 9,101,500 17,551,300 12,779,200 | 700 Dia 9,140,800 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| | D.I. | Above 6 Sub Total Trenchless Pumping mains Depth (MR) Up to 2 Above 2 Up to 4 Above 4 Up to 6 | 48 4,207 300 Dia 60 300 Dia 6,819 3,496 426 | 1,783 400 Dia 2,157 2,142 55 | 363 | 500 Dis 212 701 | 600 Dia 471 835 587 392 2,285 | 700 Dia 788 | 800 Dia | 900 Dia | 1000 Dis | 1200 Dia | 24,896,800 300 Dia 10,200,000 300 Dia 27,276,000 33,561,600 12,183,600 | 12,597,500 400 Dia 8,843,700 20,777,400 1,578,500 | 1,560,900 | 500 Dia 975,200 7,150,200 | 10,200,0 600 Dia 2,496,300 9,101,500 17,551,300 12,779,200 41,928,300 | 700 Dia 9,140,800 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| VD-U1 | D.I. | Above 6 Sub Total Trenchless Pumping mains Depth (MR) Up to 2 Above 2 Up to 4 Above 4 Up to 6 Above 6 | 48 4,207 300 Dia 60 300 Dia 6,819 3,496 426 211 10,952 | 1,783 400 Dia 2,157 2,142 55 36 | 363 94 | 500 Dia 212 701 67 | 600 Dia 471 835 587 392 2,285 | 700 Dia | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia | 24,896,800 300 Dia 10,200,000 300 Dia 27,276,000 33,561,600 12,183,600 12,183,600 12,183,600 79,625,500 | 12,597,500 400 Dia 8,843,700 20,777,400 1,578,500 1,130,400 | 1,560,900 930,600 | 500 Dia 975,200 7,150,200 1,956,400 | 10,200,6 600 Dia 2,496,300 9,101,500 17,551,300 12,779,200 | 700 Dia 9,140,800 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| | Opun cut | Above 6 Sub Total Trenchless Pumping mains Depth (MR) Up to 2 Above 2 Up to 4 Above 4 Up to 6 Above 6 | 48 4,207 300 Dia 60 300 Dia 6,819 3,496 426 211 10,952 | 1,783 400 Dia 2,157 2,142 55 36 | 363 94 | 500 Dia 212 701 67 | 600 Dia 471 835 587 392 2,285 | 700 Dia 788 | 800 Dia | 900 Dis | 1000 Dia | 1200 Dis | 24,896,800 300 Dia 10,200,000 300 Dia 27,276,000 12,183,600 6,604,300 79,625,500 200 Dia | 12,597,500 400 Dia 8,843,700 20,777,400 1,578,500 1,130,400 | 1,560,900 930,600 | 500 Dia 975,200 7,150,200 1,956,400 | 10,200,0 600 Dia 2,496,300 9,101,500 17,551,300 12,779,200 41,928,300 | 700 Dia 9,140,800 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| | Opun cut | Above 6 Sub Total Trenchless Pumping mains Depth (MR) Up to 2 Above 2 Up to 4 Above 4 Up to 6 Above 6 Sub Total | 48 4,207 300 Dia 60 300 Dia 6,819 3,496 426 211 10,952 | 1,783 400 Dia 2,157 2,142 55 36 | 363 94 | 500 Dia 212 701 67 | 600 Dis 471 835 587 392 2,285 | 700 Dia 788 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia | 24,896,800 300 Dia 10,200,000 300 Dia 27,276,000 33,561,600 12,183,600 12,183,600 12,183,600 79,625,500 | 12,597,500 400 Dia 8,843,700 20,777,400 1,578,500 1,130,400 | 1,560,900 930,600 | 500 Dia 975,200 7,150,200 1,956,400 | 10,200,0 600 Dia 2,496,300 9,101,500 17,551,300 12,779,200 41,928,300 | 700 Dia 9,140,800 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| | Opun cut | Above 6 Sub Total Trenchless Pumping mains Depth (MR) Up to 2 Above 2 Up to 4 Above 4 Up to 6 Above 6 Sub Total | 48 4,207 300 Dia 60 300 Dia 6,819 3,496 426 211 10,952 | 1,783 400 Dia 2,157 2,142 55 36 | 363 94 | 500 Dia 212 701 67 | 600 Dis 471 835 587 392 2,285 | 700 Dia 788 852 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dis | 24,896,800 300 Dia 10,200,000 300 Dia 27,276,000 33,561,600 12,183,600 6,604,300 79,625,500 200 Dia 9,000,000 | 12,597,500 400 Dia 8,843,700 20,777,400 1,578,500 1,130,400 | 1,560,900 930,600 | 500 Dia 975,200 7,150,200 1,956,400 | 10,200,6 600 Dia 2,496,300 9,101,500 17,551,300 12,779,200 41,928,300 175,597, | 700 Dia 9,140,800 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| | D.I. Opun cut | Above 6 Sub Total Trenchless Pumping mains Depth (MR) Up to 2 Above 2 Up to 4 Above 4 Up to 6 Above 6 Sub Total | 48 4,207 300 Dia 60 300 Dia 6,819 3,496 426 211 10,952 200 Dia 60 | 1,783 400 Dia 2,157 2,142 55 36 4,390 | 363 94 | 500 Dia 212 701 67 | 600 Dis 471 835 587 392 2,285 | 700 Dia 788 852 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia | 24,896,800 300 Dia 10,200,000 300 Dia 27,276,000 12,183,600 6,604,300 79,625,500 200 Dia | 400 Dia 8,843,700 20,777,400 1,578,500 1,130,400 32,330,000 | 1,560,900 930,600 | 500 Dia 975,200 7,150,200 1,956,400 | 10,200,6 600 Dia 2,496,300 9,101,500 17,551,300 12,779,200 41,928,300 175,597, | 700 Dia 9,140,800 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| | D.I. Opun cut | Above 6 Sub Total Trenchless Pumping mains Depth (MR) Up to 2 Above 2 Up to 4 Above 4 Up to 6 Above 6 Sub Total Trenchless | 48 4,207 300 Dia 60 300 Dia 6,819 3,496 426 211 10,952 200 Dia 60 200 Dia 200 Dia 200 Dia | 1.783 400 Dia 2.157 2.152 55 36 4.390 | 363 94 | 500 Dia 212 701 67 | 600 Dia 471 835 587 392 2,285 | 700 Dia 788 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia | 24,896,800 300 Dia 10,200,000 300 Dia 300 Dia 22,276,000 33,561,600 12,183,600 6,604,300 79,625,500 200 Dia 9,000,000 | 400 Dia 8,843,700 20,777,400 1,137,400 32,330,000 | 1,560,900 930,600 | 500 Dia 975,200 7,150,200 1,956,400 | 10,200,6 600 Dia 2,496,300 9,101,500 17,551,300 12,779,200 41,928,300 175,597, | 700 Dia 9,140,800 900 | 800 Dia | 900 Dia | 1000 Dis | 1200 Dia |
| | D.I. Opun cut | Above 6 Sub Total Trenchless Pumping mains Depth (MR) Up to 2 Above 2 Up to 4 Above 4 Up to 6 Above 6 Sub Total Trenchless | 48 4,207 300 Dia 60 300 Dia 6,819 3,496 426 211 10,952 200 Dia 60 200 Dia 200 Dia 200 Dia | 1.783 400 Dia 2.157 2.152 55 36 4.390 | 363 94 | 500 Dia 212 701 67 | 600 Dia 471 835 587 392 2,285 | 700 Dia 788 788 852 | 800 Dia | 900 Dia | 1000 Dis | 1200 Dia | 24,896,800 300 Dia 10,200,000 300 Dia 27,276,000 33,561,600 12,183,600 6,604,300 79,625,500 200 Dia 9,000,000 200 Dia 3,740,000 300 Dia | 12,597,500 400 Dia 8,843,700 20,777,400 1,578,500 1,130,400 32,330,000 600 Dia 56,580,000 400 Dia | 1,560,900 930,600 2,491,500 450 Dia | 500 Dia 975,200 7,150,200 1,956,400 | 10,200,0 600 Dia 2.496,300 9.101,500 17,551,300 12,779,200 41,928,300 175,597, | 700 Dia 9,140,800 900 900 700 Dia | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| | D.I. Opun cut | Above 6 Sub Total Trenchless Pumping mains Depth (MR) Up to 2 Above 2 Up to 4 Above 6 Sub Total Trenchless | 48 4.207 300 Dia 60 300 Dia 6,819 3,496 426 211 10,952 200 Dia 60 200 Dia 1,100 300 Dia 43,642 | 1,783 400 Dia 2,157 2,142 55 36 4,390 600 Dia 2,300 400 Dia 2,300 | 363 94 457 450 Dia 3,903 | 500 Dia 212 701 67 980 | 600 Dia 471 835 587 392 2.285 19, | 700 Dia 788 788 852 100 100 100 100 100 100 100 100 100 10 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia | 24.896,800 300 Dia 10.200,000 300 Dia 27.276,000 33.561,600 12.183,600 6.604,300 79,625,500 9,000,000 200 Dia 3,740,000 300 Dia 174,568,000 | 12,597,500 400 Dia 8,843,700 20,777,400 1,130,400 32,330,000 600 Dia 56,580,000 400 Dia 85,879,830 | 1,560,900 930,600 2,491,500 450 Dia 16,784,190 | 500 Dia 97.52.200 1.956.400 10.081.800 | 10,200,0 600 Dia 2.496,300 9.101,500 12,779,200 41,928,300 175,597, 9,000,0 | 700 Dia 9,140,800 9,140,800 900 900 900 900 900 900 | 800 Dia | 900 Dia | 1000 Dia | 1200 Dia |
| | Opun cut | Above 6 Sub Total Trenchless Depth (MR) Up to 2 Above 2 Up to 4 Above 6 Sub Total Trenchless Depth (MR) Up to 1 Above 6 Sub Total Trenchless Depth (MR) Up to 2 Above 2 Up to 4 Above 6 Sub Total | 48 4,207 300 Dia 60 300 Dia 60 300 Dia 6,819 3,496 426 211 10,952 200 Dia 60 1,100 300 Dia 43,642 28,477 | 1,783 400 Dia 2,157 2,142 55 36 4,390 400 Dia 2,300 400 Dia 2,300 400 Dia 2,200 400 Dia 4,200 400 Dia 4,200 400 Dia 4,200 400 Dia 4,200 400 Dia 4,200 400 Dia 4,200 400 Dia 4,200 400 Dia 4,200 400 Dia 4,200 400 Dia 4,200 4 4,200 4 4,200 4 4,200 4 4,200 4 4,200 4 4,200 4 4,200 4 4,200 4 4,200 4 4,200 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 | 363 94 457 457 450 Dia 3.903 7.836 | 500 Dia 212 701 67 980 500 Dia 502 Dia 9,041 | 600 Dia 471 835 587 392 2.285 19, 600 Dia 2.770 4.736 | 700 Dia 788 788 852 100 100 100 Dia 6,708 6,708 | 800 Dia | 900 Dia 3,430 | 1000 Dia | 1200 Dis | 24.896.800 300 Dia 10.200.000 300 Dia 27.276.000 33.561.600 12.183.600 6.604.300 79.625.500 200 Dia 3,740.000 300 Dia 174.556.000 300 Dia | 400 Dia 8.843.700 1.177.600 1.177.600 1.177.600 1.130.400 32.330.000 400 Dia 85.878.830 23.584.000 | 1,560,900 930,600 2,491,500 450 Dia 16,784,190 77,571,450 | 500 Dia 97.150.200 1.956.400 10.081.800 500 Dia 511.411.220 92.218.200 | 10,200,6 600 Dia 2,496,300 9,101,500 17,551,300 17,551,300 175,597, 41,928,300 175,597, 600 Dia 14,681,000 | 700 Dia 9,140,800 9,140,800 900 700 Dia 3,648,000 77,816,280 | 800 Dia 4,962,500 | 900 Dia 54,194,000 | 1000 Dis 5,725,500 | 1200 Dia 6,297,600 |
| VD-U2 | D.I. Opun cut | Above 6 Sub Total Trenchless Depth (MR) Up to 2 Above 2 Up to 4 Above 4 Up to 6 Sub Total Trenchless Depth (MR) Up to 2 Above 2 Up to 4 Above 4 Up to 6 Sub Total | 48 4,207 300 Dia 60 300 Dia 6,819 3,496 426 211 10,952 200 Dia 60 200 Dia 1,100 300 Dia 43,642 28,477 10,125 | 1,783 400 Dia 2,157 2,142 55 36 4,390 600 Dia 2,300 400 Dia 20,346 400 Dia 2,340 400 Dia 2,340 400 Dia 2,431 4,722 | 363 94 457 450 Dia 3,903 7,836 2,383 | 500 Dia 2121 67 980 500 Dia 2,481 2,999 | 600 Dia 471 835 587 392 2,285 19, 600 Dia 2,770 4,736 2,375 | 700 Dia 788 788 788 788 600 700 Dia 608 6.708 1.926 | 800 Dia 397 2,745 | 900 Dia 3,430 774 | 1000 Dia 347 753 | 1200 Dis 328 680 | 24,896,800 300 Dia 10,200,000 300 Dia 272,276,000 33,561,600 12,183,600 6,604,300 79,625,500 200 Dia 3,740,000 300 Dia 174,568,000 273,380,544 2885,721,40 | 400 Dia 8.843,700 20,777.400 1,138,400 1,138,500 600 Dia 56,580,000 400 Dia 85,878,830 235,440,098 225,444,098 | 1,560,900 930,600 2,491,500 450 Dia 16,784,190 77,571,450 68,864,076 | 500 Dia 975.200 7.150.200 1.956.400 10.081.800 500 Dia 11.411.220 92.218.200 92.218.200 | 10,200,6 600 Dia 2,496,300 9,10,5500 117,551,300 12,779,200 41,928,300 175,597, 600 Dia 14,681,000 51,621,310 | 700 Dia 9.140.800 900 700 Dia 700 Dia 3.648.000 77.816.280 | 800 Dia 4.962.500 86.480.100 | 900 Dia 54,194,000 26,931,720 | 1000 Dia 5,725,500 26,731,500 | 1200 Dia 6,297,600 25,976,000 |
| VD-U2 | D.I. Opun cut | Above 6 Sub Total Trenchless Depth (MR) Up to 2 Above 2 Up to 4 Above 6 Sub Total Trenchless Depth (MR) Up to 1 Above 6 Sub Total Trenchless Depth (MR) Up to 2 Above 2 Up to 4 Above 6 Sub Total | 48 48 4207 4207 500 Dis 60 50 50 50 50 50 50 50 50 50 50 50 50 50 | 1,783 400 Dia 2,157 2,142 536 4,390 600 Dia 2,300 400 Dia 2,300 400 Dia 2,300 400 Dia 2,300 | 450 Dia 3,903 7,836 2,383 222 | 500 Dia 2121 67 980 500 Dia 2,481 2,941 2,991 | 600 Dia 471 835 587 392 2,285 19, 600 Dia 2,770 4,736 2,336 1,761 | 700 Dia 788 852 100 100 100 100 100 100 100 100 100 10 | 800 Dia 397 2,745 441 | 900 Dia 3,430 774 789 | 1000 Dia 347 753 129 | 1200 Dia 328 680 319 | 24,896,800 300 Dia 10,200,000 300 Dia 21,276,000 33,561,600 12,183,600 6,604,300 79,625,500 200 Dia 9,000,000 200 Dia 3,740,000 273,380,544 285,572,140 308,0580 | 400 Dia 8,843,700 20,777,400 1,578,500 1,130,400 32,330,000 600 Dia 56,580,000 400 Dia 55,578,030 235,844,008 207,474,309 37,523,000 | 1,560,900 930,600 2,491,500 450 Dia 16,784,190 77,571,450 68,884,076 7,015,200 | 500 Dia 97.50.200 1.956,400 10.081,800 500 Dia 11.411,220 92.218,200 87.580,436 | 10,200,6 600 Dia 2,496,300 9,101,500 11,7551,300 12,779,200 41,928,300 175,597, 600 Dia 14,681,000 51,621,310 71,000,540 57,418,380 | 700 Dia 9,140,800 9,140,800 900 00 00 00 00 00 00 00 00 00 00 00 | 800 Dia 4,962,500 86,480,100 15,071,940 | 900 Dia 54,194,000 24,931,720 29,595,000 | 1000 Dia 5,725,500 26,731,500 4,916,340 | 1200 Dia 6.297.600 25,976.000 |
| VD-U2 | D.I. Opun cut | Above 6 Sub Total Trenchless Depth (MR) Up to 2 Above 2 Up to 4 Above 4 Up to 6 Sub Total Trenchless Depth (MR) Up to 2 Above 2 Up to 4 Above 4 Up to 6 Sub Total | 48 4,207 300 Dia 60 300 Dia 6,819 3,496 426 211 10,952 200 Dia 60 200 Dia 1,100 300 Dia 43,642 28,477 10,125 | 1,783 400 Dia 2,157 2,142 55 36 4,390 600 Dia 2,300 400 Dia 20,346 400 Dia 2,340 400 Dia 2,340 400 Dia 2,431 4,722 | 363 94 457 450 Dia 3,903 7,836 2,383 | 500 Dia 2121 67 980 500 Dia 2,481 2,999 | 600 Dia 471 835 587 392 2.285 19, 600 Dia 2.770 4.736 2.375 11,642 | 700 Dia 788 788 788 788 780 Dia 600 700 Dia 600 6,700 Dia 1,926 700 Dia 100 225 700 Dia 100 22 | 800 Dia 397 2,745 | 900 Dia 3,430 774 | 1000 Dia 347 753 | 1200 Dis 328 680 | 24,896,800 300 Dia 10,200,000 300 Dia 272,276,000 33,561,600 12,183,600 6,604,300 79,625,500 200 Dia 3,740,000 300 Dia 174,568,000 273,380,544 2885,721,40 | 400 Dia 8.843,700 20,777.400 1,138,400 1,138,500 600 Dia 56,580,000 400 Dia 85,878,830 235,440,098 225,444,098 | 1,560,900 930,600 2,491,500 450 Dia 16,784,190 77,571,450 68,864,076 | 500 Dia 975.200 7.150.200 1.956.400 10.081.800 500 Dia 11.411.220 92.218.200 92.218.200 | 600 Dia 2,496,300 17,551,300 12,779,200 41,928,300 175,597, 175,597, 600 Dia 14,681,000,540 51,621,310 71,000,540 194,721,230 | 700 Dia 9,140,800 900 700 Dia 3,646,020 58,926,420 32,733,900 | 800 Dia 4.962.500 86.480.100 | 900 Dia 54,194,000 24,931,720 29,595,000 | 1000 Dia 5,725,500 26,731,500 4,916,340 | 1200 Dia 6,297,600 25,976,000 |
| VD-U2 | D.I. Opun cut | Above 6 Sub Total Trenchless Depth (MR) Up to 2 Above 2 Up to 4 Above 6 Sub Total Trenchless Pumping mains Depth (MR) Up to 2 Above 6 Sub Total Depth (MR) Up to 6 Above 6 Sub Total | 48 48 4207 4207 500 Dis 60 50 50 50 50 50 50 50 50 50 50 50 50 50 | 1,783 400 Dia 2,157 2,142 536 4,390 600 Dia 2,300 400 Dia 2,300 400 Dia 2,300 400 Dia 2,300 | 450 Dia 3,903 7,836 2,383 222 | 500 Dia 2121 67 980 500 Dia 2,481 2,941 2,991 | 600 Dia 471 835 587 392 2,285 19, 600 Dia 2,770 4,736 2,375 1,761 | 700 Dia 788 788 788 788 788 788 788 788 788 78 | 800 Dia 397 2,745 441 | 900 Dia 3,430 774 789 | 1000 Dia 347 753 129 | 1200 Dia 328 680 319 | 24,896,800 300 Dia 10,200,000 300 Dia 21,276,000 33,561,600 12,183,600 6,604,300 79,625,500 200 Dia 9,000,000 200 Dia 3,740,000 273,380,544 285,572,140 308,0580 | 400 Dia 8,843,700 20,777,400 1,578,500 1,130,400 32,330,000 600 Dia 56,580,000 400 Dia 55,578,030 235,844,008 207,474,309 37,523,000 | 1,560,900 930,600 2,491,500 450 Dia 16,784,190 77,571,450 68,884,076 7,015,200 | 500 Dia 97.50.200 1.956,400 10.081,800 500 Dia 11.411,220 92.218,200 87.580,436 | 10,200,0 600 Dia 2,496,300 17,551,300 12,79,200 41,928,300 175,597, 600 Dia 14,681,000 51,621,310 71,000,540 57,418,380 194,721,230 2,389,810 | 700 Dia 9,140,800 900 00 00 00 00 00 00 00 00 00 00 00 | 800 Dia 4,962,500 86,480,100 15,071,940 | 900 Dia 54,194,000 24,931,720 29,595,000 | 1000 Dia 5,725,500 26,731,500 4,916,340 | 1200 Dia 6.297.600 25,976.000 |
| VD-U2 | D.I. Opun cut | Above 6 Sub Total Trenchless Depth (MR) Up to 2 Above 2 Up to 4 Above 4 Up to 6 Sub Total Trenchless Pumping mains Depth (MR) Up to 2 Above 2 Up to 4 Above 4 Up to 6 Above 6 Sub Total | 48 48 4207 4207 500 Dis 60 50 50 50 50 50 50 50 50 50 50 50 50 50 | 1,783 400 Dia 2,157 2,142 536 4,390 600 Dia 2,300 400 Dia 2,300 400 Dia 2,300 400 Dia 2,300 | 450 Dia 3,903 7,836 2,383 222 | 500 Dia 2121 67 980 500 Dia 2,481 2,941 2,991 | 600 Dia 471 885 587 392 2.285 19, 600 Dia 2.2770 4.736 1.761 11.642 1864 1874 1874 1874 1874 1874 1874 1874 187 | 700 Dia 788 788 788 788 780 Dia 600 700 Dia 600 6,700 Dia 1,926 700 Dia 100 225 700 Dia 100 22 | 800 Dia 397 2,745 441 | 900 Dia 3,430 774 789 | 1000 Dia 347 753 129 | 1200 Dia 328 680 319 | 24,896,800 300 Dia 10,200,000 300 Dia 21,276,000 33,561,600 12,183,600 6,604,300 79,625,500 200 Dia 9,000,000 200 Dia 3,740,000 273,380,544 285,572,140 308,0580 | 400 Dia 8,843,700 20,777,400 1,578,500 1,130,400 32,330,000 600 Dia 56,580,000 400 Dia 55,578,030 235,844,008 207,474,309 37,523,000 | 1,560,900 930,600 2,491,500 450 Dia 16,784,190 77,571,450 68,884,076 7,015,200 | 500 Dia 97.50.200 1.956,400 10.081,800 500 Dia 11.411,220 92.218,200 87.580,436 | 600 Dia 2,496,300 17,551,300 12,779,200 41,928,300 175,597, 175,597, 600 Dia 14,681,000,540 51,621,310 71,000,540 194,721,230 | 700 Dia 9,140,800 900 700 Dia 3,646,020 700 Dia 3,646,020 58,925,420 22,733,900 173,124,600 | 800 Dia 4,962,500 86,480,100 15,071,940 | 900 Dia 54,194,000 24,931,720 29,595,000 | 1000 Dia 5,725,500 26,731,500 4,916,340 | 1200 Dia 6.297.600 25,976.000 |

| | Depth (MR) | Dia 300 | Dia 400 | Dia 450 | Dia 500 | Dia 600 | Dia 700 | Dia 800 | Dia 900 | Dia 1,000 | Dia 1,200 |
|----------|-----------------|---------|---------|---------|---------|---------|---------|---------|---------|-----------|-----------|
| | Up to 2 | 4,000 | 4,100 | 4,300 | 4,600 | 5,300 | 6,000 | 6,900 | 10,200 | 10,900 | 13,600 |
| Open cut | Above 2 Up to 4 | 9,600 | 9,700 | 9,900 | 10,200 | 10,900 | 11,600 | 12,500 | 15,800 | 16,500 | 19,200 |
| | Above 4 Up to 6 | 28,600 | 28,700 | 28,900 | 29,200 | 29,900 | 30,600 | 31,500 | 34,800 | 35,500 | 38,200 |
| | Above 6 | 31,300 | 31,400 | 31,600 | 31,900 | 32,600 | 33,300 | 34,200 | 37,500 | 38,200 | 40,900 |

Unit Cost

| | 150 | 2,700 |
|-----------------|-----|--------|
| | 200 | 3,400 |
| | 250 | 4,300 |
| | 300 | 5,400 |
| Pumping Main | 400 | 11,800 |
| | 500 | 18,200 |
| | 600 | 24,600 |
| | 700 | 31,000 |
| | 800 | 37,000 |

| | 200 | 150,000 |
|-------------|-----|---------|
| | 300 | 170,000 |
| | 400 | 190,000 |
| Trenchiless | 500 | 210,000 |
| | 600 | 230,000 |
| | 700 | 250,000 |
| | 800 | 270,000 |
| | | |

Sl. No.

Insterest of construction(1.4%) Front end fee(0.2%)

Miscellaneous & Rounding Off

GRAND TOTAL =

Construction workers welfare cess @ 1% of Total Project Cost.

Consultancy fees for DPR preperation (Reimbursement) On

UGD component 0.75%,Road Restoration Component 0.50% Consultancy fees Including price escaration and tax(0.01%) Project Management Consultants & Material Inspection charges

Work contract Tax @ 4% of Total Project Cost.

Provision of Vehicle and Laptop for Department

Particulars

| | Providing Sewerage System | | Trenchless | | | Trenchless | | | Trenchless | | | Trenchless | | | Trenchless | | | | |
|----|--|--------------|--|------|-------|------------|------|-------|------------------|------|---------------|-----------------------|------|-------------|---|------|--------------|-----------|-------|
| A | Providing Sewerage System | | Other | | 0.09 | Other | | 0.09 | Other | | 0.44 | Other | | 0.04 | Other | | 0.06 | 0.71 | |
| | | | Sub-Total | | 54.6 | Sub-Total | | 62.3 | Sub-Total | | 77.2 | Sub-Total | | 20.7 | Sub-Total | | 42.9 | 258 | 44.2% |
| | | | Kattigenahalli | 14.0 | | Hagadur | 34.0 | | Talaghattapura | 10.0 | | Sompura | 16.0 | | Kariobanahalli | 20.0 | | | |
| | | | Dottabettahalli | 8.0 | | | | | t Pillaganahalli | 6.0 | | Hemigepura-1 | 26.0 | | Herohalli | 6.0 | | | |
| В | Construction of STP | | Yelhankakere | 10.0 | 68.0 | | | 34.0 | Naganathapur | 10.0 | 26.0 | Hemigepura-2 | 22.0 | 64.0 | Chikkabanavara | 10.0 | 66.0 | 258 | 44.3% |
| | | | Billeshivalli | 36.0 | | | | | | | | | | | Doddabidaraukall u | 16.0 | | | |
| | | | | | | | | | | | | | | | Hosahalli | 14.0 | | | |
| С | Construction of Wet Well cum pumphouses, D.G.Set room with office building, Pumping machinery & allied accessories , and KPTCL, BESCOM Deposits. | | Intermediate Sewage Pumping Station - Bellahalli | 1.39 | 1.4 | | | | | | | ISPS (Arehalli -1) | 0.99 | 1.0 | Manhole Pump & Sump (IV. Herohallii- 1477) | 0.62 | 0.6 | 3 | 0.5% |
| D. | Providing D.I.Pumping Mains | | | | | | | | | | | | | | | | | | |
| E | Restoration of Storm Water Drains | | | | 0.8 | | | 0.7 | | | 1.8 | | | 0.4 | | | 0.8 | 4.5 | |
| F | House Service Connection | | | | | | | | | | | | | | | | | | |
| G | Sewer Cleaning Machine (SCM) | | | | | | | 13.9 | | | 160 | | | 50 | | | 0.7 | | |
| Н | Roads Restore | | | | 12.5 | | | 97.0 | | | 16.9 105.0 | | | 5.0 87.1 | | | 8.7 110.4 | 57 526 | |
| | Sub-total(without road restore) | | | | 126.1 | | | | | | | | | | | | | 583 | |
| | Sub-total | | | | 138.6 | | | 110.9 | | | 121.9 | | | 92.1 | | | 119.1 | | |
| | Physical Contingencies @ 3% | 3.0% | | | 4.2 | | | 3.3 | | | 3.7 | | | 2.8 | | | 3.6 | 17 | |
| | Administrative Charges @ 0.5% | 0.5% | | | 0.7 | | | 0.6 | | | 0.6 | | | 0.5 | | | 0.6 | 3 | |
| | Land Acquisition (LP.S/OHT,SUMP,PUMP HOUSE,DG RROOM) | | | | 41.3 | | | 11.3 | | | 15.0 | | | 23.0 | | | 25.3 | 115.9 | |
| | Indirect Costs Total | | | | 34.2 | | | 26.9 | | | 29.8 | | | 22.7 | | | 29.4 | 143 | |
| | Price Escalation at 6% / annum of Total Project Cost for 3 years period | 6.0% 3 years | | | 24.9 | | | 20.0 | | | 21.9 | | | 16.6 | | | 21.4 | 105 | |
| | Price Escalation at 5% SOR Price escalation | | | | | | | | | | | | | | | | | | |
| | Environmental Compliance Cost @ 1% of Total Project Cost. | | | | | | | | | | | | | | | | | | |
| | Technical and Supervisory Staff to be Employed for the specified Works in 110 villages. | | | | | | | | | | | | | | | | | | |
| | Insurance for employees / workers employed by the contractor @ 0.6% per year | | | | | | | | | | | | | | | | | | |
| | Bank Commission on B.G. for Performance security @ 0.2%/annum over 10% of Total Project Cost for for 3 years | | | - | | | | | | | | | | | | | | | |
| | period for UGD & WS only. | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |

1.1

0.8

0.6

4.4

0.0

153.0

1.2

0.9

0.6

4.9

0.3

171.0

0.9

0.7

0.5

3.7

141.0

1.2

0.9

0.6

4.8

0.3

178.0

6

4

3

23

0

2

862

Bommanahalli

Open Cut

R R Nagar Total

Open Cut

Summary of Cost for Construction of 110 Village's Main Facility of Sewerage by DPR (Rate Revised)

1.4

1.0

0.7

5.5

0.7

219.0

0.5% 0.75%

0.5%

4.0%

Open Cut

Mahadevapura

Byatarayanpura

Open Cut

INR (Crore)

Grand Total

Dasarahalli

Open Cut

Direct Cost for Construction of STPs

Sample Data

Cost Function

Construction Cost of STPs

| Unit : Million INF |
|--------------------|
|--------------------|

| Capacity | Item | INR |
|----------|-------------------|-------------|
| | Civi and Archtect | 92,400,000 |
| | Mechanical | 56,100,000 |
| 3MLD | Electrical | 44,800,000 |
| | Total INR | 193,300,000 |
| | Unit cost | 64.4 |
| | Civi and Archtect | 187,200,000 |
| | Mechanical | 100,400,000 |
| 10MLD | Electrical | 70,400,000 |
| | Total INR | 358,000,000 |
| | Unit cost | 35.8 |
| | Civi and Archtect | 241,200,000 |
| | Mechanical | 124,400,000 |
| 15MLD | Electrical | 85,600,000 |
| | Total INR | 451,200,000 |
| | Unit cost | 30.1 |
| | Civi and Archtect | 346,800,000 |
| | Mechanical | 175,500,000 |
| 24MLD | Electrical | 108,700,000 |
| | Total INR | 631,000,000 |
| | Unit cost | 26.3 |

| | | ML | .D | | | | Million INR | |
|---|---|----|----|---|---|---|-------------|--|
| | x | = | 3 | | y | = | 193 | |
| | x | = | 4 | 2 | / | = | 217 | |
| | x | = | 5 | 2 | / | = | 241 | |
| | x | = | 6 | 2 | / | = | 265 | |
| | x | = | 7 | 2 | y | = | 289 | |
| | x | = | 8 | 2 | y | = | 313 | |
| | x | = | 9 | 2 | / | = | 337 | |
| | x | = | 10 | 2 | y | = | 358 | |
| > | x | = | 11 | 2 | y | = | 377 | |
| | x | = | 12 | 2 | / | = | 396 | |
| | x | = | 13 | 2 | y | = | 415 | |
| | х | = | 14 | 2 | / | = | 434 | |
| | x | = | 15 | | y | = | 451 | |
| | x | = | 16 | 2 | y | = | 471 | |
| | х | = | 17 | 2 | / | = | 491 | |
| | x | = | 18 | 2 | y | = | 511 | |
| | x | = | 19 | 2 | / | = | 531 | |
| | х | = | 20 | 2 | y | = | 551 | |
| | х | = | 21 | 2 | y | = | 571 | |
| | x | = | 22 | 2 | / | = | 591 | |
| | x | = | 23 | | y | = | 611 | |
| | x | = | 24 | , | v | = | 631 | |

| | | | | n Flow MLD) | | Cost (Mi | llion INR) | |
|---------------|------------|-------------------|--------|----------------|-------|------------------|----------------------------|-------|
| Zone | Package | STP | ЛСА | | | JICA | Surbey | |
| | | | Surbey | DPR | Basis | Foundation ※1 | Land Filling ※ 2 | Total |
| | VBY-U1 | Doddabettahalli | 7.0 | 4.0 | 289 | | | |
| D | V D I -U I | Jakkur | 7.0 | - | 289 | | | |
| Bytrayanapura | VBY-U2 | Yelahankakere | 6.0 | 5.0 | 265 | 13 | | 1,372 |
| | VBY-U3 | Bilishivalli | 17.0 | 18.0 | 491 | 25 | | |
| | | Kattigenahalli | _ | 7.0 | _ | | | |
| Mahadevpura | VM-U2 | Varthur* | 15.0 | - | 451 | | 21 | 472 |
| Manadevpura | | Hagadur | _ | 17.0 | _ | | | 4/2 |
| | VBO-U1 | Talaghattapura | 5.0 | 5.0 | 241 | 12 | | |
| Bommanahalli | VBO-U2 | Pillaganahalli | 4.0 | _ | 217 | | 14 | 484 |
| Бопшапапапаш | | t Pillaganahalli | - | 3.0 | - | | | 464 |
| | | Naganathapur | _ | 5.0 | _ | | | |
| | VR-U1 | Somapura | 8.0 | 8.0 | 313 | | | |
| R.R.Nagar | VR-U2 | Hemigepura(-1) | 13.0 | 13.0 | 415 | | 24 | 752 |
| | | Hemigepura-2 | - | 11.0 | - | | | |
| | VD-U1 | Chikkabanavara-2 | 4.0 | 5.0 | 217 | 11 | | |
| | | Kariobavanahalli | 10.0 | 10.0 | 358 | 18 | | |
| Dasarahalli | VD-U2 | Herohalli | 3.0 | 3.0 | 193 | 10 | | 1.409 |
| Dasaranani | VD-U2 | Hosahalli | 6.0 | 7.0 | 265 | | | 1,409 |
| | | Nagasandra* | 9.0 | - | 337 | | | |
| | | Doddabidaraukallu | ı | 8.0 | = | | | |
| | | Total | | | | 4,4 | 189 | |

^{※1 5%} of basis

^{%2} required Sqm x600 INR/Sqr

Cost function for Civil Construction of STPs (3MLD) UNIT:INR Size of Facility Backfilling PCC Rainforced Cement Concrete Form Work 1 Form Work 2 Water Proofing Wall/L Wall/W Sub Total Slab Sub Total Wall/W Basement Wall/L Wall/W V4 =V1-V3 V2 Sub Total MPS(TSPS) 5.50 5.20 5.00 2.50 2.20 5.00 2.50 2.20 0.40 2.2 2.20 1.75 0.35 2.7 1.80 1.75 0.35 3.3 1.80 1.50 0.25 9.40 3.76 7.70 9.45 20.9 2.70 Inlet Chamber 1.30 6.70 0.40 3.5 6.70 1.15 0.35 5.4 0.60 1.15 0.35 0.7 0.60 6.00 0.25 0.4 4.30 9.70 5.00 208.6 1.30 6.70 5.00 1.30 6.70 0.20 3.6 Main Screen Channel 16.00 6.40 15.41 2.07 23.9 3.60 7.71 1 04 0.4 4.30 9.70 5.00 208.6 1.30 6.70 5.00 1.30 6.70 0.40 3.5 6.70 1.15 0.35 5.4 0.60 1.15 0.35 0.7 0.60 6.00 0.25 16.00 6.40 15.41 23.9 3.60 3.6 7.71 1.04 3 Bypass Screen Channel 5.00 176.2 6.70 0.20 6.70 0.40 14.1 21.04 2.45 0.35 18.0 6.00 2.45 0.35 111.5 28.26 Dia 6.0 9.70 6.70 21.04 8.42 103.09 28.3 51.54 4 Raw Sewage Sump 369.3 3.00 STP Civil Work 3.00 1 Inlet Chamber 1.8 1.5 1.0 5.50 5.20 1.00 28.6 2.50 2.20 1.00 2.50 2.20 0.20 2.50 2.20 0.40 2.2 2.20 1.75 0.35 2.7 1.80 1.75 0.35 3.3 1.80 1.50 0.25 9.40 3.76 7.70 9.45 20.9 2.70 2.7 3.85 4.73 1.30 6.70 0.40 3.5 6.70 1.15 0.35 5.4 0.60 1.15 0.35 0.7 0.60 6.00 0.25 0.4 4.30 9.70 1.00 41.7 1.30 6.70 1.00 1.30 6.70 0.20 16.00 6.40 15.41 2.07 3.6 7.71 1.04 Main Screen Channe 0.6 6.0 10.5 23.9 3.60 3 Bypass Screen Channel 0.6 6.0 0.4 4.30 9.70 1.00 41.7 1.30 6.70 1.00 1.30 6.70 0.20 1.30 6.70 0.40 3.5 6.70 1.15 0.35 5.4 0.60 1.15 0.35 0.7 0.60 6.00 0.25 10.5 16.00 6.40 15.41 2.07 23.9 3.60 3.6 7.71 1.04 8.74 0.40 8.6 11.62 1.65 0.35 13.4 3.00 1.65 0.35 0.9 6.70 70.5 3.70 1.00 21.5 3.70 0.20 3.70 3.00 25.5 86.0 14.13 14.1 38.34 4 Grit Chamber Dia 3.0 11.62 9.29 76.68 38.34 Parshall Flume 1.5 10.0 0.8 5.20 13.70 1.00 71.2 2.20 10.70 1.00 23.5 2.20 10.70 0.20 2.20 10.70 0.40 9.4 10.70 1.55 0.35 11.6 1.50 1.55 0.35 2.4 1.50 10.00 0.25 27.2 25.80 10.32 33.17 6.98 50.5 15.00 15.0 16.59 3.49 6 Distribution Chamber 3.00 8.0 39.0 5.5 H 11.70 42.70 5.00 4,995.9 8.70 39.70 5.00 3,453.9 138.2 8.70 39.70 0.40 276.3 39.70 6.25 0.35 347.4 8.00 6.25 0.35 105.0 8.00 39.00 0.25 156.0 884.7 96.80 77.44 992.50 300.00 1,369.9 624.00 624.0 Anoxic/Aerobic Tank 3.5 16.70 2,189.3 5.00 1,473.4 0.20 0.40 117.9 43.02 4.25 0.35 128.0 13.00 4.25 0.35 13.00 43.02 34.41 731.31 265.3 8 Secandary Clarifire 13.70 312.2 765.7 265.33 9 Secondary Sludge Sump 3 00 1.5 30.0 1.5 5.20 33.70 5.00 876.2 2.20 30.70 5.00 337.7 2.20 30.70 0.20 13.5 2.20 30.70 0.40 27.0 30.70 2.25 0.35 48.4 1.50 2.25 0.35 3.5 1.50 30.00 0.25 11.3 65.80 26.32 138.15 10.13 174.6 45.00 5.3 3.0 1.5 9.00 6.70 5.00 3015 6.00 3.70 5.00 111.0 6.00 3.70 0.20 4.4 6.00 3.70 0.40 8.9 3.70 2.25 0.35 5.8 5.30 2.25 0.35 12.5 5.30 3.00 0.25 31.2 19.40 7.76 16.65 35.78 60.2 15.90 11 Dechlorine Mixing Tank 13 Thickened Sludge Sump 3.5 7.70 8.20 14 Centrifuge Feed Sump 4.0 4.5 4.70 5.20 9.8 4.70 5.20 0.40 19.6 5.20 4.25 0.35 30.9 4.00 4.25 0.35 35.7 4.00 4.50 0.25 9.0 19.80 15.84 88.40 102.00 206.2 36.00 6.80 2.72 5.95 5.25 1.70 1.70 0.40 1.2 1.70 1.75 0.35 2.1 1.00 1.75 0.35 1.8 1.00 1.00 0.25 15 Filtrate Sump 1.0 1.0 1.0 4.70 4.70 1.70 1.70 1.70 1.70 0.20 5.3 13.9 1.00 251 1,064 9,546 5.735 3.811 5,735 1.570 2,976 521 5,82 6,542 Rate (INR) Rate 126 76.219 Rate 373 Rate Rate 10% of Sub Total 480,500 146,088 4,974,41 834,974 1,460,76 10,274,217 11,970,032 1,109,893 521,11 Sub Total Cost (INR) Total Cost (INR) 35.000.000 Architecht Sam INR/Sam 20 Administration Building 15.0 15.0 10.0 H 225 8,775,000 9,000,000 21 Maintenance Building 10.0 8.0 4.5 H 80 27,000 2,160,000 3 000 000 10.0 10.0 5.0 H 22 D.G Room 100 27,000 2,700,000 3.000.000 23 Air Blower Building 8.0 12.0 6.0 H 4,416,000 5,000,000 24 Centrifuse Building 15.0 15.0 10.0 H 225 64 000 14 400 000 15,000,000 8.0 10.0 6.0 H 26 Clolorination Building 5.0 5.0 4.0 H 25 44 000 1 100 000 2,000,000 Other Work 10.0% of above 27 Sewer and Sludge Pine Line 7 700 000 28 Road Construction and othe 10.0% of above 7,700,000

3MLD

Cost function for Civil Construction of STPs (10MLD)

| | | Size o | f Faci | ity | | E | xcava | tion | | | Be | ckfilling | | Di | isposal | _ | PCC | _ | | _ | | _ | Rai | nforced C | ement C | oncre | te | | _ | _ | | Reinforce ment Steel | | ı | orm W | ork 1 | | Fort | m Work 2 | 2 | Water P | roofing | Miscellaneou |
|--------------------------------|-----|----------|--------|------|--------|---------|---------|----------|---------|----------|-----------|-----------|--------|-------|--------------|-------|------------|---------|----------|----------|-------------|-------------|----------|-----------|-------------------------------|---------|--------------|----------|----------|-----------|------------|----------------------------|---------|-----------|-----------|-----------|-----------|------------|----------|---------|------------------|------------|---------------|
| Items | Noe | W /Dia | L | SWD/ | H W/D | ia L | н | V1 | W/ | /Dia | L I | H V2 | V3=V1- | ·V2 _ | V4 =V1-V3 | W/Dia | L t | V | W/D | | ment t V | | Wall/L | 1/0 | Wall/ | | (2) | | ilab | s | Sub Total | Sub Total | - | ment | Wall/L | Wall/V | Sub Total | Slab A4 | Sub Tot | | all/L Wall/V | | |
| | NOS | MR | MR | MR | MF | R MF | R MR | Cum | N | MR | MR M | IR Cum | Cum | | Cum | MR | MR MF | Cum | MR | | t V | 1 L m MR | MR ME | | W H MR MR | | /3 W um M | | | V4 Cum | Cum | Tone | L MR | A1 Sqm | A2 Sqm | A3 Sqm | Cum | Sqm | Cum | | AI AZ iqm Sqm | | |
| MPS(TSPS) | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1 Inlet Chamber | 1 | 2.0 | 2.5 | 0.6 | 5.7 | 70 6.2 | 20 5.00 | 17 | 76.7 | 2.70 | 3.20 5.0 | 00 43 | 3.2 | | | 2.70 | 3.20 0.2 | 0 | 1.7 2.7 | 70 3.2 | 0.40 | 1.5 3.20 | 1.35 0.3 | 3.0 | 2.00 1.35 0 | 0.35 | 2.8 2. | 00 2.5 | 0 0.25 | 1.3 | 10.6 | | 11.80 | 4.72 | 8.64 | 8.10 | 21.5 | 5.00 |) | 5.0 4. | 1.32 4.05 | 8.37 | |
| 2 Main Screen Channel | 2 | 1.0 | 6.0 | 0.6 | 4.7 | 70 9.3 | 70 5.00 | 45 | 55.9 | 1.70 | 6.70 5.0 | 00 113 | 1.9 | | | 1.70 | 6.70 0.2 | 0 - | 4.6 1.7 | 70 6.7 | 0.40 | 6.70 | 1.35 0.3 | 12.7 | 1.00 1.35 | 0.35 | 2.8 1. | 00 6.0 | 0.25 | 3.0 | 27.6 | | 16.80 | 13.44 | 36.18 | 8.10 | 57.7 | 12.0 |) 1 | 2.0 18. | 3.09 4.05 | 22.14 | |
| 3 Bypass Screen Channel | 1 | 1.0 | 6.0 | 0.6 | 4.7 | 70 9.3 | 70 5.00 | 22 | 28.0 | 1.70 | 6.70 5.0 | 00 57 | 7.0 | | | 1.70 | 6.70 0.2 | | 2.3 1.7 | 6.7 | 0.40 | 6.70 | 1.35 0.3 | 6.3 | 1.00 1.35 | 0.35 | 1.4 1. | 00 6.0 | 0.25 | 1.5 | 13.8 | | 16.80 | 6.72 | 18.09 | 4.05 | 28.9 | 6.00 |) | 6.0 9. | 0.05 2.03 | 11.07 | |
| 4 Raw Sewage Sump | 1 | Dia 11.0 | | 1.7 | 14.7 | 70 | 5.00 | 84 | 48.2 11 | 1.70 | 5.0 | 537 | 7.3 | | | 11.70 | 0.2 | 2 | 1.5 11.7 | 07 | 0.40 43 | 36.74 | 2.45 0.3 | 31.5 1 | 1.00 2.45 | 0.35 | 11. | 00 | 0.25 | 23.7 | 98.2 | | 36.74 | 14.70 | 180.02 | | 194.7 | 94.9 | 9 | 5.0 90. | 0.01 | 90.01 | |
| | | | | | 3.0 | 00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| STP | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Civil Work | | | | | 3.0 | 00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1 Inlet Chamber | 1 | 2.0 | 2.0 | 2.0 | 5.7 | 70 5. | 70 1.00 | 3 | 32.5 | 2.70 | 2.70 1. | 00 7 | 1.3 | | | 2.70 | 2.70 0.2 | 0 | 1.5 2.7 | 70 2.7 | 0 0.40 | 2.70 | 2.75 0.3 | 5.2 | 2.00 2.75 | 0.35 | 5.8 2. | 00 2.0 | 0 0.25 | 1.0 | 14.9 | | 10.80 | 4.32 | 14.85 | 16.50 | 35.7 | 4.00 | ð | 4.0 7. | 7.43 8.25 | 15.68 | |
| 2 Main Screen Channel | 2 | 0.8 | 6.0 | 0.4 | 4.5 | 50 9.3 | 70 1.00 | 8 | 37.3 | 1.50 | 6.70 1.6 | 00 20 | 0.1 | | | 1.50 | 6.70 0.2 | 0 . | 4.0 1.5 | 6.7 | 0 0.40 8 | 6.70 | 1.15 0.3 | 10.8 | 0.80 1.15 0 | 0.35 | 1.9 0. | 80 6.0 | 0 0.25 | 2.4 | 23.2 | | 16.40 | 13.12 | 30.82 | 5.52 | 49.5 | 9.60 | ð | 9.6 15. | 5.41 2.76 | 18.17 | |
| 3 Bypass Screen Channel | 1 | 0.8 | 6.0 | 0.4 | 4.5 | 50 9.3 | 70 1.00 |) 4 | 43.7 | 1.50 | 6.70 1.0 | 00 10 | 0.1 | | | 1.50 | 6.70 0.2 | 0 : | 2.0 1.5 | 6.7 | 0 0.40 4 | 1.0 6.70 | 1.15 0.3 | 5.4 | 0.80 1.15 0 | 0.35 | 1.0 0. | 80 6.0 | 0 0.25 | 1.2 | 11.6 | | 16.40 | 6.56 | 15.41 | 2.76 | 24.7 | 4.80 | 0 | 4.8 7. | 7.71 1.38 | 9.09 | |
| 4 Grit Chamber | 2 | Dia 5.0 | | 0.9 | 8.7 | 70 | 1.00 | 11 | 18.8 | 5.70 | 1.0 | 00 51 | .0 | | | 5.70 | 0.2 | 0 10 | 0.2 5.7 | 70 | 0.40 20 | 17.90 | 1.65 0.3 | 20.7 | 5.00 1.65 0 | 0.35 | 5. | 00 | 0.25 | 9.8 | 50.9 | | 17.90 | 14.32 | 118.13 | | 132.4 | 39.2 | 5 5 | 9.3 59. | 0.06 | 59.06 | |
| 5 Parshall Flume | 1 | 1.5 | 10.0 | 0.8 | 5.2 | 20 13. | 70 1.00 | ; | 71.2 | 2.20 | 10.70 1. | 00 23 | 1.5 | | | 2.20 | 10.70 0.2 | 0 . | 4.7 2.2 | 20 10.7 | 0 0.40 1 | 10.70 | 1.55 0.3 | 11.6 | 1.50 1.55 0 | 0.35 | 2.4 1. | 50 10.0 | 0 0.25 | 3.8 | 27.2 | | 25.80 | 10.32 | 33.17 | 6.98 | 50.5 | 15.00 | 0 1 | 5.0 16. | 5.59 3.49 | 20.07 | |
| 6 Distribution Chamber | | | | | 3.0 | _ | | | | T | | | | | | | | | | | | | | | | | 1 | | TT | | | | | | | t | | | | | 1 | | |
| 7 Anoxic/Aerobic Tank | 2 | 8.0 | 123.0 | 5.5 | н 11.3 | 70 126. | 70 5.00 | 14,82 | 23.9 | 8.70 1 | 23.70 5.0 | 00 10,761 | .9 | | | 8.70 | 123.70 0.2 | 0 43 | 0.5 8.7 | 70 123.7 | 0 0.40 86 | .0 123.70 | 6.25 0.3 | 1,082.4 | 3.00 6.25 0 | 0.35 10 | 5.0 8. | 00 123.0 | 0 0.25 4 | 192.0 | 2,540.3 | | 264.80 | 211.84 | 3,092.50 | 300.00 | 3,604.3 | 1,968.00 | 0 1,96 | 8.0 | + | | |
| 8 Secandary Clarifire | 2 | Dia 23.0 | | 3.5 | 26.7 | 70 | 5.00 | 5,59 | 96.2 23 | 3.70 | 5.0 | 00 4,409 | 0.3 | | | 23.70 | 0.2 | 0 17 | _ | - | | .7 74.42 | | | | _ | 23. | _ | 0.25 2 | | 781.8 | | 74.42 | 59.53 | 1,265.11 | | 1,324.6 | 830.5 | 3 83 | 10.5 | | | |
| 9 Secondary Sludge Sump | | | | | 3.0 | 00 | | | | | | | | | | | | | | | | | | | | | | | 1 | | | | | | | | | | | | | | |
| 10 Chlorine Contact Tank | 1 | 2.0 | 54.0 | 2.0 | +- | _ | 70 5.00 | 1,64 | 44.5 2 | 2.70 | 54.70 5.0 | 00 738 | 1.5 | | | 2.70 | 54.70 0.2 | 0 2: | 9.5 2.7 | 70 54.7 | 0 0.40 59 | 1.1 54.70 | 2.75 0.3 | 105.3 | 2.00 2.75 0 | 0.35 | 5.8 2. | 00 54.0 | 0 0.25 | 27.0 | 197.1 | | 114.80 | 45.92 | 300.85 | 16.50 | 363.3 | 108.0 | 0 10 | 0.80 | _ | | |
| 11 Dechlorine Mixing Tank | 1 | 6.8 | - | | | _ | 70 5.00 | | _ | _ | 5.70 5.0 | _ | | | | | 5.70 0.2 | | 8.6 7.5 | _ | 0 0.40 13 | _ | | | 6.80 2.75 0 | _ | _ | _ | + | 8.5 | 56.2 | | 26.40 | 10.56 | | 56.10 | | | | 84.0 | - | | |
| 12 Sludge Thickner | | | | | ╁ | | | | | + | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | - | | |
| 13 Thickened Sludge Sump | | | | | ╁ | | | | | + | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | - | | |
| 14 Centrifuge Feed Sump | 2 | 6.0 | 7.0 | 4.0 | 9.7 | 70 10.3 | 70 | | | 6.70 | 7 70 | | | | | 6.70 | 7.70 0.2 | n 21 | 0.6 6.7 | 77 | 0 0.40 41 | .3 7.70 | 4.75 0.3 | 51.2 | 5.00 4.75 0 | 135 5 | 9.9 6. | 00 70 | 0 0.25 | 21.0 | 173.3 | | 28.80 | 23.04 | 146 30 | 171.00 | 340.3 | 84.0 | 0 8 | 24.0 | | | |
| 15 Filtrate Sump | 1 | 2.0 | - | | + | _ | _ | | _ | 2.70 | _ | | | | | _ | _ | | 1.5 2.7 | + | | 1.9 2.70 | | | 2.00 1.75 0 | _ | 3.7 2 | _ | + | 1.0 | 10.9 | | 10.80 | 4.32 | | 10.50 | | | _ | 4.0 | | | |
| Quantity | H | 2.0 | 2.0 | 1.0 | - | | ,,, | 24,1 | _ | 2.70 | 2.70 | 16,91 | 37 7,5 | 07 | 16,987 | 2.70 | 2.70 0.2 | | 19 | 2 | | | 1.70 0.0 | 0.0 | | ,.00 | 0.7 | 2.0 | 010 | 1.0 | 4,038 | 404 | 10.00 | 1.02 | 0.40 | 10.00 | 6,350 | | 3,2 | 210 | + | 254 | |
| Rate (INR) | | | | | - | | Rate | | 521 | \dashv | | Ra | _ | 26 | 146 | | Rati | | | - | | - | | | + | | | + | + | Rate | 6.542 | 76,219 | | | | Rate | - | | | 190 | Rate | | |
| rate (INIV) | | | | | - | | reate | | | \dashv | | rea | | - | | | reat | | _ | - | | - | | | + | | | + | + | | -, | | | | | rtate | | reate | | | reate | | 10% of Sub To |
| Sub Total Cost (INR) | | | | | | | ١. | 12,810, | | | | | 957,7 | | 2,473,263 | | | 4,193,6 | | | | | | | | | | | | | 26,414,462 | 30,774,312 | | | | ١. | 2,368,461 | ١. | 1,576,0 | | | 228,647 | |
| Total Cost (INR) | | | | | +- | | | 12,811,0 | 000 | | | | 958,0 | 00 2 | 2,474,000 | | | 4,194,0 | 00 | | | | | | | | | | | - 20 | 8,415,000 | 30,775,000 | | | | - | 2,369,000 | • | 1,577,0 | 000 | | 229,000 | |
| Total Gost (INR) | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 0,000,00 |
| A | | | | | +- | 1 | | 1 | | | - 1 | _ | | | 1 | | | 1 | - | 1 | | 1 | | г г | т т | | | | т т | | | | | | | ı | | | Т | | | | |
| Architecht | | | | | | | | | | _ | | - | | + | | | | | | + | | | | | \perp | | | | + | _ | | | | | | | Sq | | _ | ₹/Sqm | | INR | |
| 20 Administration Building | 1 | 15.0 | - | | _ | | | | | | | - | | - | | | | | | - | | | | | | | | | + | _ | | | | | | | 34 | | | 9,000 | _ | 13,455,000 | 14,000,0 |
| 21 Maintenance Building | 1 | 15.0 | - | | +- | | | | | | | | | + | | | | | | | | | | | | | - | | | | | | | | | | 12 | | | 7,000 | _ | 3,240,000 | 4,000,0 |
| 22 D.G Room | 1 | 15.0 | - | | _ | + | | 1 | 4 | _ | | 1 | 1 | _ | | | | | | _ | \Box | - | | | \perp | _ | - | _ | 1-1 | _ | | | | | | | 22 | | | 7,000 | 4 | 6,075,000 | 7,000,0 |
| 23 Air Blower Building | 1 | 8.0 | - | | Н | | | | | | | | | 4 | | | | | | _ | | | | | $\perp \downarrow \downarrow$ | | _ | | \perp | _ | | | | | | <u> </u> | 16 | | _ | 6,000 | | 7,360,000 | 8,000,0 |
| 24 Centrifuge Building | 1 | 15.0 | - | 10.0 | н | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 37 | | | 4,000 | | 24,000,000 | 24,000,0 |
| 25 Chemical Building | 1 | 8.0 | 10.0 | 6.0 | н | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 81 |) | 6. | 2,000 | | 4,960,000 | 5,000,0 |
| 26 Clolorination Building | 1 | 10.0 | 7.0 | 5.5 | н | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 70 |) | 4/ | 4,000 | | 3,080,000 | 4,000,0 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Other Work | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 27 Sewer and Sludge Pipe Lines | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 10.0 | % of above | 15,600,0 |
| 28 Road Construction and other | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 10.0 | % of above | 15,600,0 |
| 20 House Constitution and Care | | | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 10.0 | | |
| to the construction and outer | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 10.0 | | |

10MLD

Supporting Repo

Cost function for Civil Construction of STPs (15MLD)

| | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | Reinforce | l . | | | | | l | | Т | | | UNIT:INR |
|--------------------------------|------------|----------|---------|-------|-------------|------------|-------|--------|------|----------|------------------------|--------------|-------|--------|------|--------------------------------|----------|----------|------------|----------|---------------------|------------|----------|--------|---------|-------------|----------|---------------------------------|---------------------------------|-----------|------------|--------------|--------------|-------------------------------|------------|------------------------|-------|-----------|---------------------------|-----------------|
| | Size o | f Facili | ty | | Excavation | on | | | Back | filling | | Disposal | | PC | C | | | | | | Rainf | forced Cen | ent Con | crete | | | | | ment Steel | | F | orm W | ork 1 | | Fon | n Work 2 | | later Pro | - | Miscellaneous |
| Items | W /Dia | L | SWD/H V | N/Dia | L H | V1 | W/Dia | a L | н | V2 | V3=V1-V2 | V4 =V1-V3 | W/Dia | L | t | ٧ | | aseme | nt t V1 | | Wall/L | V2 W | Wall/W | | | Slab L t | V4 | Sub Total | Sub Total | Base L | ment A1 | Wall/L A2 | Wall/W A3 | | Slab A4 | Sub Total | Wall/ | L Wall/W | Sub Total | |
| | MR | MR | MR | MR | MR MR | Cum | MR | MR | MR | Cum | Cum | Cum | MR | MR | MR | Cum | | IR N | | | R MR MR | | MR M | | MR M | | | Cum | Tone | MR | Sqm | Sqm | Sqm | | Sqm | Cum | Sqm | AZ. | | |
| MPS(TSPS) | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1 Inlet Chamber | 1 2.9 | 2.5 | 0.6 | 6.60 | 6.20 5.00 | 204.6 | 3.60 | 3.20 | 5.00 | 57.6 | | | 3.60 | 3.20 | 0.20 | 2.3 | 3.60 | 8.20 0. | 40 4.6 | 3.2 | 20 1.35 0.35 | 3.0 2.9 | 1.35 0.3 | 5 4.1 | 2.90 2 | 2.50 0.25 | 1.8 | 13.6 | | 13.60 | 5.44 | 8.64 | 11.75 | 25.8 | 7.2 | 5 7.3 | 4.3 | 5.87 | 10.19 | |
| 2 Main Screen Channel | 2 1.2 | 8.0 | 0.6 | 4.90 | 11.70 5.00 | 573.3 | 1.90 | 8.70 | 5.00 | 165.3 | | | 1.90 | 8.70 | 0.20 | 6.6 | 1.90 | 3.70 0. | 40 13.2 | 2 8.7 | 70 1.35 0.35 | 16.4 1.2 | 1.35 0.3 | 5 3.4 | 1.20 8 | 3.00 0.25 | 4.8 | 37.9 | | 21.20 | 16.96 | 46.98 | 9.72 | 73.7 | 19.2 | 0 19.2 | 23.4 | 19 4.86 | 28.35 | |
| 3 Bypass Screen Channel | 1 1.2 | 8.0 | 0.6 | 4.90 | 11.70 5.00 | 286.7 | 1.90 | 8.70 | 5.00 | 82.7 | | | 1.90 | 8.70 | | 3.3 | 1.90 | 8.70 0. | | | 70 1.35 0.35 | | 1.35 0.3 | | | 3.00 0.25 | _ | 18.9 | | 21.20 | | 23.49 | 4.86 | 36.8 | 9.6 | 0 9.6 | 11.7 | 5 2.43 | 14.18 | |
| 4 Raw Sewage Sump | 1 Dia 11.0 |) | 2.2 | 14.70 | 5.00 | 848.2 | 11.70 |) | 5.00 | 537.3 | | | 11.70 | (| 20 | 21.5 | 11.70 | 0. | 40 43.0 | 36.7 | 74 2.95 0.35 | 37.9 11.0 | 2.95 0.3 | 15 1 | 1.00 | 0.25 | 23.7 | 104.7 | | 36.74 | 14.70 | 216.75 | | 231.4 | 94.9 | 9 95.0 | 108.3 | 8 | 108.38 | |
| | | | | 3.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| STP | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Civil Work | | | | 3.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1 Inlet Chamber | 1 2.9 | 2.5 | 2.0 | 6.60 | 6.20 1.00 | 40.9 | 3.60 | 3.20 | 1.00 | 11.5 | | | 3.60 | 3.20 | 0.20 | 2.3 | 3.60 | 8.20 0. | 40 4.6 | 3.2 | 20 2.75 0.35 | 6.2 2.9 | 2.75 0.3 | 5 8.4 | 2.90 2 | 2.50 0.25 | 1.8 | 21.0 | | 13.60 | 5.44 | 17.60 | 23.93 | 47.0 | 7.2 | 5 7.3 | 8.8 | 11.96 | 20.76 | |
| 2 Main Screen Channel | 2 1.0 | 6.0 | 0.5 | 4.70 | 9.70 1.00 | 91.2 | 1.70 | 6.70 | 1.00 | 22.8 | | | 1.70 | 6.70 | 0.20 | 4.6 | 1.70 | 5.70 0. | 40 9.1 | | 70 1.25 0.35 | | 1.25 0.3 | 5 2.6 | 1.00 6 | 6.00 0.25 | 3.0 | 26.5 | | 16.80 | 13.44 | 33.50 | 7.50 | 54.4 | 12.0 | 0 12.0 | 16.7 | 3.75 | 20.50 | |
| 3 Bypass Screen Channel | 1 1.0 | | 0.5 | 4.70 | 9.70 1.00 | 45.6 | - | _ | 1.00 | 11.4 | | | 1.70 | 6.70 | 0.20 | 2.3 | 1.70 | 6.70 0. | _ | _ | 70 1.25 0.35 | | 1.25 0.3 | | | | 1.5 | 13.2 | | 16.80 | | 16.75 | 3.75 | 27.2 | 6.0 | 0 6.0 | 8.3 | 1.88 | 10.25 | |
| 4 Grit Chamber | 2 Dia 6.0 | | 0.9 | 9.70 | 1.00 | 147.7 | 6.70 | 0 | 1.00 | 70.5 | | | 6.70 | (| 0.20 | 14.1 | 6.70 | _ | _ | 21.0 | 04 1.65 0.35 | 24.3 6.0 | 1.65 0.3 | 15 | 6.00 | 0.25 | 14.1 | 66.6 | | 21.04 | 16.83 | 138.85 | | 155.7 | 56.5 | 2 56.5 | 69.4 | 3 | 69.43 | |
| 5 Parshall Flume | 1 1.5 | 10.0 | 0.8 | 5.20 | 13.70 1.00 | 71.2 | 2.20 | 10.70 | 1.00 | 23.5 | | | 2.20 | 10.70 | 20 | 4.7 | 2.20 10 | 0.70 0. | 40 9.4 | 10.7 | 70 1.55 0.35 | 11.6 1.5 | 1.55 0.3 | 5 2.4 | 1.50 10 | 0.00 0.25 | 3.8 | 27.2 | | 25.80 | 10.32 | 33.17 | 6.98 | 50.5 | 15.0 | 0 15.0 | 16.5 | 9 3.49 | 20.07 | |
| 6 Distribution Chamber | | | | 3.00 | | | | | | | | | | | | | | | | | $\perp \! \! \perp$ | | | | | | | | | | | | | | | | | \bot | | |
| 7 Anoxic/Aerobic Tank | 2 8.0 | 180.0 | 5.5 H | 11.70 | 183.70 5.00 | 21,492.9 | 8.70 | 180.70 | 5.00 | 15,720.9 | | | 8.70 | 180.70 | 0.20 | 628.8 | 8.70 180 | _ | _ | | 70 6.25 0.35 | | | | | 0.00 0.25 7 | _ | 3,663.8 | | 378.80 | 303.04 | 4,517.50 | 300.00 | 5,120.5 | 2,880.0 | 2,880.0 |) | | | |
| 8 Secandary Clarifire | 2 Dia 28.5 | 5 | 3.5 | 32.20 | 5.00 | 8,139.2 | 29.20 | 0 | 5.00 | 6,693.2 | | | 29.20 | (| 0.20 | 267.7 | 29.20 | 0. | 40 535.5 | 91.6 | 69 4.25 0.35 | 272.8 28.5 | 4.25 0.3 | 5 2 | 8.50 | 0.25 3 | 318.8 | 1,127.0 | | 91.69 | 73.35 | 1,558.70 | | 1,632.0 | 1,275.2 | 3 1,275.2 | 2 | | | |
| 9 Secondary Sludge Sump | | | | 3.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 Chlorine Contact Tank | 1 2.0 | 81.0 | 2.0 | 5.70 | 84.70 5.00 | 2,414.0 | 2.70 | 81.70 | 5.00 | 1,103.0 | | | 2.70 | 81.70 | 0.20 | 44.1 | 2.70 81 | .70 0. | 40 88.2 | 2 81.7 | 70 2.75 0.35 | 157.3 2.0 | 2.75 0.3 | 5 5.8 | 2.00 81 | 1.00 0.25 | 40.5 | 291.8 | | 168.80 | 67.52 | 449.35 | 16.50 | 533.4 | 162.0 | 0 162.0 |) | | | |
| 11 Dechlorine Mixing Tank | 1 6.8 | 8.0 | 2.0 | 10.50 | 11.70 5.00 | 614.3 | 7.50 | 8.70 | 5.00 | 326.3 | | | 7.50 | 8.70 | 20 | 13.1 | 7.50 8 | 3.70 0. | 40 26.1 | 1 8.7 | 70 2.75 0.35 | 16.7 6.8 | 2.75 0.3 | 5 19.6 | 6.80 8 | 3.00 0.25 | 13.6 | 76.1 | | 32.40 | 12.96 | 47.85 | 56.10 | 116.9 | 54.4 | 0 54.4 | | | | |
| 12 Sludge Thickner | 2 Dia 11.0 |) | 4.0 | 14.70 | 5.00 | 1,696.3 | 11.70 | 0 | 5.00 | 1,074.6 | | | 11.70 | (| 20 | 43.0 | 11.70 | 0. | 40 86.0 | 36.7 | 74 4.75 0.35 | 122.2 11.0 | 4.75 0.3 | 15 1 | 1.00 | 0.25 | 47.5 | 255.6 | | 36.74 | 29.39 | 698.02 | | 727.4 | 189.9 | 7 190.0 |) | | | |
| 13 Thickened Sludge Sump | 2 3.5 | 4.0 | 3.0 | 7.20 | 7.70 5.00 | 554.4 | 4.20 | 0 4.70 | 5.00 | 197.4 | | | 4.20 | 4.70 | 20 | 7.9 | 4.20 | 1.70 0. | 40 15.8 | 8 4.7 | 70 3.75 0.35 | 24.7 3.5 | 3.75 0.3 | 5 27.6 | 3.50 4 | 1.00 0.25 | 7.0 | 75.0 | | 17.80 | 14.24 | 70.50 | 78.75 | 163.5 | 28.0 | 0 28.0 |) | | | |
| 14 Centrifuge Feed Sump | 2 6.0 | 6.0 | 4.0 | 9.70 | 9.70 5.00 | 940.9 | 6.70 | 6.70 | 5.00 | 448.9 | | | 6.70 | 6.70 | 0.20 | 18.0 | 6.70 | 5.70 0. | 40 35.9 | 6.7 | 70 4.75 0.35 | 44.6 6.0 | 4.75 0.3 | 5 59.9 | 6.00 6 | 6.00 0.25 | 18.0 | 158.3 | | 26.80 | 21.44 | 127.30 | 171.00 | 319.7 | 72.0 | 0 72.0 |) | | | |
| 15 Filtrate Sump | 1 2.0 | 2.0 | 1.0 | 5.70 | 5.70 5.00 | 162.5 | 2.70 | 2.70 | 5.00 | 36.5 | | | 2.70 | 2.70 | 20 | 1.5 | 2.70 2 | 2.70 0. | 40 2.9 | 2.7 | 70 1.75 0.35 | 3.3 2.0 | 1.75 0.3 | 5 3.7 | 2.00 2 | 2.00 0.25 | 1.0 | 10.9 | | 10.80 | 4.32 | 9.45 | 10.50 | 24.3 | 4.0 | 0 4.0 |) | | | |
| Quantity | | | | | | 38,324 | | | | 26,583 | 11,740 | 26,583 | | | | 1,088 | | | | | | | | | | | | 5,988 | 599 | | | | | 9,340 | | 4,893 | | | 302 | |
| Rate (INR) | | | | | Rate | 521 | | | | Rate | 126 | 146 | | F | ate | 5,829 | | | | | | | | | | | Rate | 6,542 | 76,219 | | | | Rate | 373 | Rat | 490 |) | Rate | 901 | |
| Sub Total Cost (INR) | | | | | | 19,970,391 | | | | | 1,480,148 1,481,000 | 3,870,516 | | | | 6,328,144 6, 329,000 | | | | | | | | | | | | 39,174,427 39,175,000 | 45,640,378 45,641,000 | | | | | 3,483,592 3,484,000 | ١. | 2,395,712 2,396,000 | | | 272,322 273,000 | 10% of Sub Tota |
| Total Cost (INR) | | | | | - 1 '1 | 10,011,000 | | | | | 17151,000 | 40111000 | | | | ,,,,,,,,,, | | | | | | | | | | | - 1 | | 10,011,000 | _ | | | | GI GI GI | | | 1 | | 1,0,000 | 135,000,00 |
| | | | | | | | | | | | | | | | | | | | | | - | | | | | | | | | | | | | | | | | | \rightarrow | 100,000,00 |
| Architecht | | | | | | | | | П | | | | | | Т | | | | | | \top | | | | | | | | | | | | | Sa | m | INR/S | Sam | \top | INR | |
| 20 Administration Building | 1 150 | 23.0 | 10.0 H | | | | | | | | | | | | | | | | | | ++- | | | | | \pm | | | | | | | | 34 | 5 | 39,0 | 100 | + | 13,455,000 | 14.000.00 |
| 21 Maintenance Building | 1 15.0 | | 4.5 H | | | | | | | | | | | | + | | | - | | | + | | | | | | | | | | | | | 12 | | 27,0 | | | 3,240,000 | 4,000,00 |
| 22 D.G.Room | | 15.0 | 5.0 H | | | | | | | | | | | | | | | | | | ++- | | | | | \pm | | | | | | | | 22 | | 27.0 | | _ | 6.075.000 | 7,000,00 |
| 23 Air Blower Building | | 20.0 | 6.0 H | | | | | | | | | | | | + | | | - | | | + | | | | | | | | | | | | | 16 | 0 | 46.0 | 100 | + | 7,360,000 | 8,000,000 |
| 24 Centrifuge Building | | 25.0 | 10.0 H | - | -++ | | | + | + | | | | | - | + | | | + | | 1 | ++ | | | | + | + | \dashv | | | | | | | 37 | | 64,0 | 100 | _ | 24,000,000 | 24,000,00 |
| 25 Chemical Building | 1 8.0 | - | 6.0 H | - | | | | + | | _ | | | | - | + | | | \dashv | | \vdash | + | | | | _ | + | | | | | | | | 80 | | 62,0 | | | 4,960,000 | 5,000,00 |
| 26 Clolorination Building | 1 10.0 | - | 5.5 H | + | | | 1 | + | | | | | | + | + | | | + | | - | + | | | ++ | - | + | - | | | | | | | 70 | | 44.0 | | | 3.080.000 | 4,000,00 |
| | | | | | | | 1 | 1 | Ш | | | | | | | | | | | 1 | | | | | | | | | | 1 | | | | 1 | | 1 | | | | .,, |
| Other Work | | | T | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | - |
| 27 Sewer and Sludge Pipe Lines | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 10.0% | of above | 20,100,00 |
| 28 Road Construction and other | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 10.0% | of above | 20,100,00 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Gran Total | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 241,200,000 |
| | | - | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 15MLD |

15MLD

NJS Consultants Co., Ltd.

| | < |
|------------|---|
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | Ç |
| | |
| | - |
| | 4 |
| _ | |
| Supporting | |
| ~ | |
| 2 | |
| - | |
| 0 | |
| 7 | |
| 9 | 0 |
| | |
| \sim | |
| -2 | |
| 4 | |
| C | |
| ~ | |
| ~ | - |
| <i>y</i> 0 | |
| | |
| h | |
| 27 | |
| | |
| Rep | |
| 7 | |
| | |

Cost function for Civil Construction of STPs (24MLD)

| | | Size | of Fac | cility | | | Exc | avatio | on | | | Bac | kfilling | | Disp | osal | | PCC | 0 | | | | | | | Rainfo | orced (| Cemer | nt Conc | crete | | | | | Reinforce ment | 1 | - | orm W | ork 1 | | Fo | rm Work | | Water P | _ | Miscellan |
|--------------------------------|-----|---------|--------|--------|--------|--------|--------|--------|----------|---------|---------|----------|----------|---------|--------|----------|---------|----------|------|----------|-------------|---------|----------|---------|------------|----------|---------|-----------|-----------|---------------|-----------|-------------|-------|------------|--------------------|---------|-----------|-----------|-----------|-----------|-----------|---------|----------|-----------------|---------------|-----------|
| Items | | W /Dia | L | ew | D/H W | //Dia | L | , l | V1 | W/E | Dia L | | V2 | V3=V1- | · · | 4 -V3 | I/Dia | | | v | | Basem | ent | | W | /all/L | | | Wall/W | | | Slab | | Sub Total | Steel Sub Total | Base | ement | Wall/L | Wall/W | Sub Total | Slal | Sub To | Wal | II/L Wall/ | N Sub Tota | |
| | Nos | MR | | | | | MR | MR | Cum | M | | | Cum | V3-V1- | VZ =V1 | | | IR MF | | v Sum | W/Dia MR | L MR | | | L H | | | W MR N | H t | V3 V Cum M | | 1 - 1 | V4 | Cum | Tone | L MR | A1 Sam | A2 Sam | A3 Sam | Cum | A4 Sar | | _ ^ | ı1 A2 gm Sgn | Cum | |
| MPS(TSPS) | T | imit | | | | | | | Odili | | | | Cum | Oum | | | | | | Zum | , man x | | | | | | Cum | | mix mix | Odin in | | | Zum | Ouiii | TOTO | | Oqn | Ogiii | Oqiii | Ouiii | | Can | | gii Oqii | Oum | |
| I Inlet Chamber | 1 | 4.4 | 2. | .8 | 0.6 | 8.10 | 6.50 | 5.00 | 26 | 3.3 5. | .10 3. | .50 5.00 | 89.3 | 3 | | | 5.10 | 3.50 0.2 | 10 | 3.6 | 5.10 | 3.50 | 0.40 | 7.1 | 3.50 1.35 | 0.35 | 3.3 | 4.40 1 | 1.35 0.35 | 6.2 4. | .40 2.1 | 30 0.25 | 3.1 | 19.8 | | 17.20 | 6.88 | 9.45 | 17.82 | 34. | 2 12 | 32 1 | 2.3 4. | .73 8.9 | 13.64 | |
| Main Screen Channel | 3 | 1.2 | 6. | .0 | 0.6 | 4.90 | 9.70 | 5.00 | 71: | 3.0 1. | 90 6. | .70 5.00 | 191.0 | | | | 1.90 | 6.70 0.2 | 10 | 7.6 | 1.90 | 6.70 | 0.40 | 15.3 | 6.70 1.35 | 0.35 | 19.0 | 1.20 1 | 1.35 0.35 | 5.1 1. | 20 6.0 | 0.25 | 5.4 | 44.8 | | 17.20 | 20.64 | 54.27 | 14.58 | 89. | 5 21 | 60 2 | 1.6 27. | .14 7.2 | 34.43 | : |
| 3 Bypass Screen Channel | 1 | 1.2 | 6. | .0 | 0.6 | 4.90 | 9.70 | 5.00 | 23 | 7.7 1. | 90 6. | .70 5.00 | 63.7 | 7 | | | 1.90 | 6.70 0.2 | 10 | 2.5 | 1.90 | 6.70 | 0.40 | 5.1 | 6.70 1.35 | 0.35 | 6.3 | 1.20 1 | 1.35 0.35 | 1.7 1. | 20 6.0 | 0.25 | 1.8 | 14.9 | | 17.20 | 6.88 | 18.09 | 4.86 | 293 | 8 7 | 20 | 7.2 9. | .05 2.4 | 11.48 | |
| 4 Raw Sewage Sump | 1 | Dia 14: | 0 | | 2.2 1 | 7.70 | | 5.00 | 1,22 | 9.7 14. | .70 | 5.00 | 848.2 | 2 | | 1 | 14.70 | 0.2 | :0 | 33.9 | 14.70 | | 0.40 | 67.9 4 | 16.16 2.95 | 0.35 | 47.7 | 14.00 2 | 2.95 0.35 | 14. | .00 | 0.25 | 38.5 | 154.0 | | 46.16 | 18.46 | 272.33 | | 2903 | 8 153 | 86 15 | 3.9 136. | .17 | 136.17 | |
| | | | | | | 3.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| STP | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Civil Work | | | | | | 3.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1 Inlet Chamber | 1 | 2.8 | 2. | .8 | 1.5 | 6.50 | 6.50 | 1.00 | 4: | 2.3 3. | .50 3. | .50 1.00 | 12.3 | 3 | | | 3.50 | 3.50 0.2 | 10 | 2.5 | 3.50 | 3.50 | 0.40 | 4.9 | 3.50 2.25 | 0.35 | 5.5 | 2.80 2 | 2.25 0.35 | 6.6 2. | .80 2.1 | 30 0.25 | 2.0 | 19.0 | | 14.00 | 5.60 | 15.75 | 18.90 | 40. | 3 7 | 84 | 7.8 7. | .88 9.4 | 17.33 | |
| 2 Main Screen Channel | 2 | 1.2 | 6. | .0 | 0.6 | 4.90 | 9.70 | 1.00 | 9 | 5.1 1. | .90 6. | .70 1.00 | 25.5 | 5 | | | 1.90 | 5.70 0.2 | 10 | 5.1 | 1.90 | 6.70 | 0.40 | 10.2 | 6.70 1.35 | 0.35 | 12.7 | 1.20 1 | 1.35 0.35 | 3.4 1. | 20 6.0 | 00 0.25 | 3.6 | 29.8 | | 17.20 | 13.76 | 36.18 | 9.72 | 59. | 7 14 | 40 1 | 4.4 18. | .09 4.8 | 22.95 | |
| 3 Bypass Screen Channel | 1 | 1.2 | 6. | .0 | 0.6 | 4.90 | 9.70 | 1.00 | 4 | 7.5 1. | 90 6. | .70 1.00 | 12.7 | , | | | 1.90 | 5.70 0.2 | 10 | 2.5 | 1.90 | 6.70 | 0.40 | 5.1 | 6.70 1.35 | 0.35 | 6.3 | 1.20 1 | 1.35 0.35 | 1.7 1. | 20 6.0 | 00 0.25 | 1.8 | 14.9 | | 17.20 | 6.88 | 18.09 | 4.86 | 293 | 8 7 | 20 | 7.2 9. | .05 2.4 | 11.48 | |
| 4 Grit Chamber | 2 | Dia 7. | +- | _ | _ | 1.20 | | 1.00 | 191 | _ | 20 | 1.00 | 105.6 | | | _ | 8.20 | 0.2 | 10 | 21.1 | | _ | _ | _ | 25.75 1.65 | + | _ | _ | 1.65 0.35 | | 50 | | 22.1 | 94.0 | | - | 20.60 | | | 190. | _ | | 8.3 84. | _ | 84.97 | |
| 5 Parshall Flume | 1 | 1.5 | + | | | _ | 15.70 | | 8 | _ | _ | .70 1.00 | _ | | | | _ | 2.70 0.2 | 10 | 5.6 | | 12.70 | - | | 12.70 1.55 | + | _ | - | 1.55 0.35 | | _ | | 4.5 | 31.9 | | 29.80 | - | | 6.98 | | _ | _ | _ | .69 3.4 | | _ |
| 6 Distribution Chamber | T | | | | -+ | 3.00 | | | | | | | | | | | | 1 | | | | | 1 | 1 | | T | | | | | | | | | | | | | | | | | | | | |
| 7 Anoxic/Aerobic Tank | 4 | 8.0 | 147. | .0 5 | .5 H 1 | 1.70 1 | 150.70 | 5.00 | 35,26 | 3.8 8. | 70 147. | .70 5.00 | 25,699.8 | | | | 8.70 14 | 7.70 0.2 | 10 | 1,028.0 | 8.70 | 147.70 | 0.40 2,0 | 56.0 14 | 17.70 6.25 | 0.35 2 | 2,584.8 | 8.00 6 | 5.25 0.35 | 210.0 8. | .00 147.0 | 00 0.25 1,1 | 176.0 | 6,026.7 | | 312.80 | 500.48 | 7,385.00 | 600.00 | 8,485. | 5 4,704 | 00 4,70 | 4.0 | | | |
| 8 Secandary Clarifire | 4 | Dia 26. | _ | - | | 9.70 | | 5.00 | | 3.8 26. | _ | _ | 11,192.4 | | | | 26.70 | 0.2 | | | 26.70 | _ | _ | _ | 33.84 4.25 | | | | | | | 0.25 | _ | 1,924.9 | | | - | 2,850.49 | | | 6 2,122 | | 2.6 | | | |
| 9 Secondary Sludge Sump | | | + | + | _ | 3.00 | | H | | | + | | 1 | | | | + | + | | | | _ | ۳ | + | + | H | | - - | | | + | | | | | Ė | | | | | H | | | | | |
| 10 Chlorine Contact Tank | 1 | 2.0 | 130. | .0 | _ | | 133.70 | 5.00 | 3,810 | 0.5 2. | 70 130. | .70 5.00 | 1,764.5 | 5 | | | 2.70 13 | 0.70 0.2 | 10 | 70.6 | 2.70 | 130.70 | 0.40 1 | 41.2 13 | 30.70 2.75 | 5 0.35 | 251.6 | 2.00 2 | 2.75 0.35 | 5.8 2. | .00 130.0 | 00 0.25 | 65.0 | 463.5 | | 266.80 | 106.72 | 718.85 | 16.50 | 842. | 1 260 | 00 26 | 0.0 | + | | |
| 11 Dechlorine Mixing Tank | 1 | 11.6 | - | - | | _ | 11.70 | | 89 | _ | _ | .70 5.00 | | | | | _ | 3.70 0.2 | | | 12.30 | _ | _ | _ | 8.70 2.75 | + | _ | _ | 2.75 0.35 | | _ | | 23.2 | 116.2 | | _ | 16.80 | | - | | _ | | 2.8 | | | |
| 12 Sludge Thickner | | Dia 14: | - | - | | 7 70 | 11.70 | 5.00 | 2,451 | _ | 70 | 5.00 | _ | | | | 14.70 | 0.2 | | 67.9 | | _ | _ | _ | 16.16 4.75 | + | 153.5 1 | _ | 4.75 0.35 | | _ | | 76.9 | 366.1 | | _ | 36.93 | | 00.70 | 913. | _ | | _ | | | |
| 13 Thickened Sludge Sump | 2 | 3.5 | +- | _ | | | 7.70 | _ | 55 | _ | _ | .70 5.00 | _ | | | | _ | 1.70 0.2 | | | 4.20 | 4.70 | | _ | 4.70 4.25 | + | _ | _ | | 31.2 3. | _ | | 7.0 | 82.0 | | 17.80 | - | | 89.25 | | _ | | 8.0 | | | |
| 14 Centrifuge Feed Sump | ^ | 6.0 | - | - | - | _ | 10.70 | | 1,03 | _ | _ | .70 5.00 | | | | | _ | 7.70 0.2 | | 20.6 | | 7.70 | _ | - | 7.70 4.75 | + | 51.2 | | 4.75 0.35 | | _ | | 21.0 | 173.3 | | _ | 23.04 | | - | 340. | _ | | 4.0 | | | |
| 15 Filtrate Sump | | 2.0 | +- | _ | | - | 5.70 | - | 1,03 | _ | _ | .70 5.00 | + | | | _ | | 2.70 0.2 | | | 2.70 | 2.70 | _ | _ | 2.70 1.75 | + | 3.3 | | 1.75 0.35 | | _ | 00 0.25 | 1.0 | 10.9 | | 10.80 | - | | - | 24.3 | _ | | 4.0 | | | |
| Quantity | Ľ | 2.0 | 2 | .0 | 1.0 | 3.70 | 5.70 | 5.00 | | _ | .70 2. | .70 5.00 | | | | | 2.70 . | 2.70 0.2 | :0 | 1,750 | | 2.70 | 0.40 | 2.9 | 2.70 1.75 | 0.35 | 3.3 | 2.00 1. | 1.75 0.35 | 3.1 2. | .00 2.1 | 0.23 | 1.0 | | | | 4.32 | 9.45 | 10.30 | | _ | | _ | | | |
| Rate (INR) | | | | | - | | | | 60,9 | _ | | | 43,014 | | | 3,014 | _ | - | | - | | | | - | | ++ | | - | | | | | | 9,587 | 956 | | | | | 14,75 | _ | 7,6 | _ | | 35 | _ |
| Mate (INR) | | | | - | _ | _ | | Rate | 5 | _ | | | Rate | | 26 | 146 | | Rat | ·e | 5,829 | | | | | | + | | | | | | | Rate | 6,542 | 76,219 | - | | | Rate | | _ | | 190 | Rat | | |
| Sub Total Cost (INR) | | | | | | | | | 31,755,2 | | | | | 2,259,8 | | 52,792 | | | | 200,151 | | | | | | | | | | | | | | 62,718,092 | 73,070,052 | | | | | 5,503,91 | | 3,884,2 | | | 320,53 | |
| | | | | - | _ | | | * | 31,756,0 | 00 | | | • | 2,260,0 | 6,26 | 3,000 | | • | 10,2 | 01,000 | | | | | | | | | | | | | 4 6 | 2,719,000 | 73,071,000 | 1 | | | 4 | 5,504,000 | 9 | 3,885,0 | 00 | | 321,00 | |
| Total Cost (INR) | | | | | _ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 216,0 |
| | | | | | _ | - | | | | _ | | | 1 | | | | | | 1 | | | | | | | т т | | | | | | | | - | | 1 | | | | | | 1 | | _ | INR | |
| Architecht | L | | | | _ | | | | | | | | | | | | | | | | | | | _ | | | | _ | | | | | | | | | | | | | qm | | 2/Sqm | | | |
| 20 Administration Building | 1 | 15.0 | _ | _ | | 4 | | Н | | - | - | | 1 | 1 | | _ | | | - | | | | 4 | _ | | 1 | | _ | | | | \perp | | | | | | | | | 50 | _ | 9,000 | - | 17,550,00 | _ |
| 21 Maintenance Building | 1 | 12.0 | _ | .0 4 | | _ | | | | | | | | | - | | | - | - | | \vdash | | _ | - | | + | | | _ | | | | _ | | | - | | | | | 96 | | 7,000 | _ | 2,592,00 | |
| 22 D.G Room | 1 | 15.0 | _ | | .0 H | 4 | | Н | | - | - | | 1 | 1 | | _ | | | - | | | | 4 | _ | | 1 | | _ | | | | \perp | | | | | | | | | 25 | | 7,000 | - | 6,075,00 | |
| 23 Air Blower Building | 1 | 8.0 | - | - | .0 H | | | | | | | | 1 | | | | | | _ | | | | _ | | | \sqcup | _ | | | | | | | | | | | | | | 60 | | 6,000 | | 7,360,00 | |
| 24 Centrifuge Building | 1 | 15.0 | +- | | | | | Ш | | _ | _ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | _ | 75 | | 4,000 | | 24,000,00 | - |
| 25 Chemical Building | 1 | 8.0 | - | _ | .0 Н | _ | | Ш | | _ | \perp | | 1 | | _ | | | | _ | | | | 1 | 1 | | Ш | | _ | | | | | _ | | | | | | | | 60 | | 2,000 | | 9,920,00 | |
| 26 Clolorination Building | 1 | 6.5 | 7. | .5 5 | .5 H | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 4 | 19 | 4 | 4,000 | | 2,145,00 | 0 3, |
| Other Work | - | | - | + | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1 |
| | ┞ | | - | - | 4 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 10.0 | V . C . L | 1 |
| 27 Sewer and Sludge Pipe Lines | H | | + | + | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | % of above | 28, |
| 28 Road Construction and other | H | | - | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 10.0 | % of above | 28,5 |
| | H | | - | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Gran Total | l | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | 346,80 |

Cost function for Mechanical and Electrical Construction of STPs

Unit: Million INR

| Item | | 3MLD | | | 10MLD | | | 15MLD | | | 24MLD | |
|------------|-----------|------------|---------------------|------------|-------------|---------------------|------------|-------------|----------------------|------------|-------------|----------------------|
| Item | TSPS | STP | Sub-Total | TSPS | STP | Sub-Total | TSPS | STP | Sub-Total | TSPS | STP | Sub-Total |
| Machanical | 8,945,522 | 47,118,456 | 56,063,978 | 18,475,324 | 81,852,871 | 100,328,195 | 25,526,974 | 98,790,264 | 124,317,238 | 29,556,489 | 145,868,425 | 175,424,914 |
| Mechanical | | | ≒ 56,100,000 | | | ≒100,400,000 | | | ≒124,400,000 | | | ≒175,500,000 |
| Electrical | Included | 44,782,240 | 44,782,240 | Included | 70,329,420 | 70,329,420 | Included | 85,526,640 | 85,526,640 | Included | 108,635,584 | 108,635,584 |
| Electrical | in STP | | ≒ 44,800,000 | in STP | | ≒ 70,400,000 | in STP | | ≒ 85,600,000 | in STP | | ≒108,700,000 |
| Total | 8,945,522 | 91,900,696 | 100,846,218 | 18,475,324 | 152,182,291 | 170,657,615 | 25,526,974 | 184,316,904 | 209,843,878 | 29,556,489 | 254,504,009 | 284,060,498 |
| 1 Otal | | | ≒100,900,000 | | | ≒170,700,000 | | | ≒ 209,900,000 | | | ⇒ 284,100,000 |

Supporting Report

Mechanical Cost for TSPSs (3MLD)

| | MECHANICAL ITEMS | | | SI | PECIFI | CATION | | | (k W/LIN | т | NUM | IBER | | DESCRIPTION | ELECTRIC CAPACITY | Consu | al power mptioon | NJS 複算単価 | BISIC | EXCISE DUTY | TAX/V | PACKING & FORWAR | T | BASIC COST | TOTAL COST | ERECTI ON | NJS積算 TOTAL | Toshiba 見機額 |
|---|-------------------------------|---------------|--------|-------|--------|--------|-------------------------------|-------|-------------|-----|-----|------|------|---|-------------------|----------------|---------------------|-------------|-----------|-----------------|---------------------|------------------------|--------|---------------|----------------|-----------------|----------------|----------------|
| | | | | | | | | | | W | | S | Т | | k W | hours/d 3.0 | kWh/d 0.70 | Rs./unit | 8 | 12.36% 9=8 × | 12.50% 10=(8+8)× | 2.00% 11=8 × | 2.00% | 13=SUM(8:12) | 14=13×TOTAL NO | 3.00% 15=14× | 16=14+15 | - |
| - | INLET GATE | W (m | : 0.40 | L(i | m) : | 0.60 | Design Water Depth(m) : | 8.00 | | - 2 | | | 2 | Manually Sluice Gate, Wall Thimble:Cast Iron, Gate: cast iron, Frame: cast iron. Floor+5.000, Bottom+0.000 | 0.00 | | | 190,000 | 190,000 | 23,484 | 26,686 | 3,800 | 3,800 | 247,770 | 495,539 | 14,866 | 510,405 | 1,368,00 |
| 2 | COARSE SCREEN (MECHANICAL) | W (m | : 0.60 | L(i | m) : | 6.00 | SWD(m) : | 0.50 | 1.5 |) 1 | - | 0 | . 0 | Climber screen, including control panel. Screen: SS316L Open space 20mm Floor+5.000, Bottom+0.000 | 1.50 | | | 1,500,000 | 1,500,000 | 185,400 | 210,675 | 30,000 | 30,000 | 1,956,075 | 1,956,075 | 58,682 | 2,014,757 | |
| 3 | COARSE SCREEN (MANUAL) | W (m | : 0.60 | L(i | m) : | 6.00 | SWD(m) : | 0.50 | | - 0 | | 1 | . 1 | Manually Bar Screen. Screen: SS316L Open space 50mm Floor+5.000, Bottom+0.000 | 0.00 | | | 160,000 | 160,000 | 19,776 | 22,472 | 3,200 | 3,200 | 208,648 | 208,648 | 6,259 | 214,907 | 1,044,00 |
| 4 | BELT CONVEYOR | Belt Width (m | 0.60 | L(i | m) : | 5.00 | | - | 1.50 | 0 | | 0 | 0 | Frame: MS+ Epoxy, Belt: NBR 3mm | 0.00 | | | 400,000 | 400,000 | 49,440 | 56,180 | 8,000 | 8,000 | 521,620 | 0 | 0 | 0 | |
| 5 | SEWAGE PUMP 1 | Dia (mm) | : 200 | Q(m3/ | 'h) : | 315 | H(m): | 15.00 | 30.0 |) 1 | | 1 | 2 | Submeraible sludge pump with detachable device. Overall efficiency more than 60%. Casing: CI, Impelier SS ASTM A743, Guide/Lifting chain: SS316. Pump efficiency shall be more than 60%. Floor+6,000, Bottom+0,000 | 30.00 | 9.5 | 203.75 | 800,000 | 800,000 | 98,880 | 112,360 | 16,000 | 16,000 | 1,043,240 | 2,086,480 | 62,594 | 2,149,074 | 5,940,00 |
| 9 | SEWAGE PUMP 2 | | | | | | | | | | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 7 | ELECTRIC HOIST | RL(T) | : 3.00 | LG | m) : | 6.00 | | - | 8.5 |) 1 | | 0 | 1 | Single-girder overhead type. | 8.50 | | | 800,000 | 800,000 | 98,880 | 112,360 | 16,000 | 16,000 | 1,043,240 | 1,043,240 | 31,297 | 1,074,537 | 1,224,00 |
| | | | | | | | | | | | | T | OTAL | | 40.00 | | 203.75 | | | | | | | | | | 5,963,681 | 9,576,00 |
| | | | | _ | | _ | | _ | | | | | | Tota | kW | | kWh/d | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | <u> </u> |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | 1 |

Mechanical Cost for TSPSs (10MLD)

| | | | SPECI | FICATION | | | (k W/UNIT | | NUMBER | t | DESCRIPTION | ELECTRIC CAPACITY | Consu | al power mptioon | NJS 被算単価 | BISIC | EXCISE DUTY | TAX/V | PACKING & FORWAR | T | BASIC | TOTAL COST | ERECTI ON | NJS 積算額 TOTAL | Toshiba 見積額 |
|--------------------------|--|--|---|--------------------------------|--|-------------------------|--------------|-----------|-----------|------------|--|---|---|--------------------------|--------------------------|--------------------------|---|--------------------------|--|---|-------------------|--|--|--|--|
| | | | | | | | | w | S | T | | k W | | kWh/d 0.70 | | | 12.36% | | 2.00% | 2.00% | | | 3.00% | 40.44.40 | |
| | | | | | | | - | | | | | | 10.0 | 0.70 | | | 9=8 × | 10=(8+9) × | 11=8 × | 12=8 × | 13=SUM(8:12) | 14=13×TOTAL NO. | 15=14× | 10=14+15 | - |
| ET GATE | W (m) | : 0.60 | L(m) : | 0.90 | Design Water Depth(m) : | 8.00 | - | 2 | 1 | 3 | Manuelly Sluice Gete, Wall Thimble:Cast Iron, Gete: cast iron, Frame: cast iron. Floor+5.000, Bottom+0.000 | 0.00 | | | 270,000 | 270,000 | 33,372 | 37,922 | 5,400 | 5,400 | 352,094 | 1,056,281 | 31,688 | 1,087,969 | 2,511,000 |
| ARSE SCREEN CHANICAL) | W (m) | : 1.00 | L(m) : | 6.00 | SWD(m) : | 0.60 | 1.50 | 1 | 0 | 1 | Climber screen, including control panel. Screen: SS318L Open space 20mm Floor+5.000, Bottom+0.000 | 1.50 | 6.0 | 6.30 | 2,100,000 | 2,100,000 | 259,560 | 294,945 | 42,000 | 42,000 | 2,738,505 | 2,738,505 | 82,155 | 2,820,660 | 4,950,000 |
| ARSE SCREEN (MANUAL) | W (m) | : 1.00 | L(m) : | 6.00 | SWD(m) : | 0.60 | - | . 0 | 1 | 1 | Manually Bar Screen. Screen: SS316L Open space 50mm Floor+5.000, Bottom+0.000 | 0.00 | | | 260,000 | 260,000 | 32,136 | 36,517 | 5,200 | 5,200 | 339,053 | 339,053 | 10,172 | 349,225 | 1,710,000 |
| T CONVEYOR | Belt Width (m | 0.60 | L(m) : | 5.00 | | - | 1.50 | 1 | 0 | 1 | Frame: MS+ Epoxy, Belt: NBR 3mm | 1.50 | 7.0 | 7.35 | 400,000 | 400,000 | 49,440 | 56,180 | 8,000 | 8,000 | 521,620 | 521,620 | 15,649 | 537,269 | 963,000 |
| YAGE PUMP 1 | Dia (mm) | : 200 | Q(m3/h) : | 380 | H(m): | 15.00 | 30.00 | 2 | 1 | 3 | 60%. Casing: CI, Impeller SS ASTM A743, Guide/Lifting chain: SS316. Pump efficiency shall be more than 60%. | 60.00 | 10.5 | 543.33 | 1,000,000 | 1,000,000 | 123,600 | 140,450 | 20,000 | 20,000 | 1,304,050 | 3,912,150 | 117,365 | 4,029,515 | 6,210,000 |
| VAGE PUMP 2 | Die (mm) | : 150 | Q(m3/h) : | 190 | H(m): | 15.00 | 15.00 | 1 | 1 | 2 | Submersible sludge pump with detachable device. Overall efficiency more than 80%. Caeing: CI, Impeller SS ASTM A743, Guide/Lifting chain: SS316. Pump efficiency shall be more than 60%. Floor+8,000. Bottom+0,000 | 15.00 | 10.5 | 135.83 | 900,000 | 900,000 | 111,240 | 126,405 | 18,000 | 18,000 | 1,173,645 | 2,347,290 | 70,419 | 2,417,709 | 3,510,000 |
| CTRIC HOIST | RL(T) | : 3.00 | L(m) : | 6.00 | | - | 8.50 | 1 | 0 | 1 | Single-girder overhead type. | 8.50 | | | 800,000 | 800,000 | 98,880 | 112,380 | 18,000 | 16,000 | 1,043,240 | 1,043,240 | 31,297 | 1,074,537 | 1,440,000 |
| | | | | | | | | | | TOTAL | | 86.50 | | 692.82 | | | | | | | | | | 12,316,883 | 21,294,000 |
| | | | | | | | | | | | | kW | | kWh/d | | | | | | | | | | INR | INR |
| | | | | | | | 1 | 1 | | | | | | | | | | | | | | | | | t |
| | | | | | | | + | ! | | | | | | | | | | | | | | | | | |
| A) | RSE SOREEN HANICAL) RSE SOREEN (MANUAL) CONVEYOR AGE PUMP 1 AGE PUMP 2 | RSE SOREEN W (m) RSE SOREEN (MANUAL) CONVEYOR Bet Web (m) AGE PUMP 1 Dia (mm) Dia (mm) | RSE SOREEN W (m): 1.00 RSE SOREEN (MANUAL) W (m): 1.00 CONVEYOR Belt Week (m): 0.60 AGE PUMP 1 Dia (mm): 200 AGE PUMP 2 Dia (mm): 150 | RSE SOREEN W (m): 1.00 L(m): | RSE SCREEN HANICALD W (m): 1.00 L(m): 6.00 RSE SCREEN (MANUAL) W (m): 1.00 L(m): 6.00 CONVEYOR Belt Week (m): 0.60 L(m): 5.00 AGE PUMP 1 Dia (mm): 200 Q(m3/h): 380 AGE PUMP 2 Dia (mm): 150 Q(m3/h): 190 | Depth(m) : RSE SOREEN | Depth(m) : | Depth(m): | Depth(m): | Depth(m) : | RSE SCREEN W (m): 1.00 L(m): 6.00 SWD(m): 0.60 1.50 1 0 1 | RSE SCREEN W (m): 1.00 L(m): 6.00 SWD(m): 0.60 1.50 1 0 1 | No. Converger Converger | RSE SCREEN W (m): 1.00 | RSE SCREEN W (m): 1.00 | RSE SCREEN W (m): 1.00 | CALLE W (m) 1.00 L(m) 0.00 SWD(m) 0.80 1.50 1 0 1 0 1 0 0 0 0 | RSE SCREEN W (m): 1.00 | Columber Screen W (m) 1.00 L(m) 1. | Columber Columber | Floor-SQUE Pump | CALLE W (m) 1.00 L(m) 0.00 Depth(m) 0.00 1.50 1 | ## Note: Column C | CALLE Wildly Unit Unit | CONVEYOR Discriment Discr |

Supporting Report

Mechanical Cost for TSPSs (15MLD)

| | MECHANICAL ITEMS | | | SPECII | FICATION | | | (k W/UNIT | | NUMBE | | DESCRIPTION | ELECTRIC CAPACITY | Consu | al power mptioon | NJS 複算単価 | BISIC | EXCISE DUTY | TAX/V AT | PACKING & FORWAR | т | BASIC COST | TOTAL COST | ON | NJS 積算額 TOTAL | |
|---|-------------------------------|------------------|------|-----------|----------|-------------------------------|-------|--------------|---|-------|------|--|----------------------|-------|---------------------|-------------|-----------|----------------|-------------|------------------------|--------|---------------|-------------------|---------|-------------------------|----|
| | | | | | | | | | W | S | T | | k W | | kWh/d | | | 12.36% | | 2.00% | 2.00% | | | 3.00% | | Rs |
| | | | | | | | | | | | | | | 15.0 | 0.70 | | 8 | 9=8 × | 10+(8+9) × | 11=8 × | 12=8 × | 13=SUM(8:12) | 14=13 × TOTAL NO. | 15=14× | 16=14+15 | |
| 1 | INLET GATE | W (m) : | 0.60 | L(m) : | 0.90 | Design Water Depth(m) : | 8.00 | - | 2 | 1 | 3 | Manually Sluice Gate, Wall Thimble:Cast Iron, Gate: cast iron, Frame: cast iron. Floor+5.000, Bottom+0.000 | 0.00 | | | 270,000 | 270,000 | 33,372 | 37,922 | 5,400 | 5,400 | 352,094 | 1,056,281 | 31,688 | 1,087,969 | |
| 2 | COARSE SCREEN (MECHANICAL) | W (m) : | 1.00 | L(m) : | 6.00 | SWD(m) : | 0.60 | 1.50 | 2 | 0 | 2 | Climber screen, including control panel. Screen: SS316L Open space 20mm Floor+5.000, Bottom+0.000 | 3.00 | 6.0 | 12.60 | 2,100,000 | 2,100,000 | 259,560 | 294,945 | 42,000 | 42,000 | 2,738,505 | 5,477,010 | 164,310 | 5,641,320 | |
| 3 | COARSE SCREEN (MANUAL) | W (m) : | 1.00 | L(m) : | 6.00 | SWD(m) : | 0.60 | - | 0 | 1 | 1 | Manually Ber Screen: Screen: SS316L Open space 50mm Floor+5.000, Bottom+0.000 | 0.00 | | | 280,000 | 260,000 | 32,136 | 36,517 | 5,200 | 5,200 | 339,053 | 339,053 | 10,172 | 349,225 | |
| 4 | BELT CONVEYOR | Belt Width (m) : | 0.60 | L(m) : | 5.00 | | - | 1.50 | 1 | 0 | 1 | Frame: MS+ Epoxy, Belt: NBR 3mm | 1.50 | 7.0 | 7.35 | 400,000 | 400,000 | 49,440 | 56,180 | 8,000 | 8,000 | 521,620 | 521,620 | 15,649 | 537,269 | |
| 5 | SEWAGE PUMP 1 | Dia (mm) : | 300 | Q(m3/h) : | 570 | H(m): | 15.00 | 45.00 | 2 | 1 | 3 | Submerable sludge pump with detachable device. Overall efficiency more than 60%. Casing: CI, Impelier SS ASTM A743, Guide/Lifting chain: SS316. Pump efficiency shall be more than 60%. Floor+8,000. Bottom+0,000 | 90.00 | 10.5 | 815.00 | 1,400,000 | 1,400,000 | 173,040 | 196,630 | 28,000 | 28,000 | 1,825,670 | 5,477,010 | 164,310 | 5,641,320 | |
| 6 | SEWAGE PUMP 2 | Dia (mm) : | 200 | Q(m3/h) : | 285 | H(m): | 15.00 | 30.00 | 1 | 1 | 2 | Submersible studge pump with detachable device. Overall efficiency more than 60%. Casing: CI, Impeller SS ASTM A743, Guide/Lifting chain: SS316. Pump efficiency shall be more than 60%. Floor+8.000, Bottom+0.000 | 30.00 | 10.5 | 203.75 | 1,000,000 | 1,000,000 | 123,600 | 140,450 | 20,000 | 20,000 | 1,304,050 | 2,608,100 | 78,243 | 2,686,343 | |
| 7 | ELECTRIC HOIST | RL(T): | 3.00 | L(m) : | 6.00 | | - | 8.50 | 1 | 0 | 1 | Single-girder overhead type. | 8.50 | | | 800,000 | 800,000 | 98,880 | 112,380 | 18,000 | 16,000 | 1,043,240 | 1,043,240 | 31,297 | 1,074,537 | |
| | | | | | | | | | | | TOTA | | 133.00 | | 1038.70 | | | | | | | | | | 17,017,983 | |
| | | | | | | | | | | | | | k W | 1 | kWh/d | | | | | | | | | | INR | |
| | | | | | | | | | | | | | | | | | - | | | | | | | | | |
| П | | | | | | | | 1 - | | 1 | | | | | | | | | | | | | | | | 1 |

Supporting Report

Mechanical Cost for TSPSs (24MLD)

| | MECHANICAL ITEMS | | | SPECIF | TCATION | | | (k | NU | JMBER | | DESCRIPTION | ELECTRIC CAPACITY | | al power | NJS 被算単価 | BISIC | EXCISE DUTY | TAX/V | PACKING & | т | BASIC | TOTAL COST | ERECTI ON | NJS被算額 TOTAL | Toshiba 見物額 |
|-------|-----------------------------|------------------|------|-----------|---------|-------------------------------|-------|---------|----|--------------|-------|--|----------------------|------|----------|-------------|-----------|-------------|---------------------|-----------------|-----------------|--------------|-----------------|--------------|-----------------|----------------|
| | | | | | | | | W/UNIT_ | w | | - | | k W | | kWh/d | カー・カー | 0081 | 12.36% | | FORWAR 2.00% | INSURA 2.00% | 0081 | | 3,00% | TOTAL | Rs. |
| | | | | | | | | | " | • | • | | K 17 | 24.0 | 0.70 | | 8 | 9=8 X | 12.5U% 10=(8+9)× | 11=8 × | | 13=SUM(8:12) | 14=13×TOTAL NO. | | 16=14+15 | FUS. |
| 1 INL | LET GATE | W (m) : | 0.60 | L(m) : | 0.90 | Design Water Depth(m) : | 8.00 | - | 3 | 1 | | Manually Sluice Gate, Wall Thimble:Cast Iron, Gate: cast iron, Frame: cast iron. Floor+5.000, Bottom+0.000 | 0.00 | | | 270,000 | 270,000 | 33,372 | 37,922 | 5,400 | 5,400 | 352,094 | 1,408,374 | 42,251 | 1,450,625 | 3,348,000 |
| 2 CO | OARSE SCREEN IECHANICAL) | W (m) : | 1.20 | L(m) : | 6.00 | SWD(m): | 0.60 | 1.50 | 2 | 0 | | Climber screen, including control panel. Screen: SS316L Open apace 20mm Floor+5.000, Bottom+0.000 | 3.00 | 6.0 | 12.60 | 2,200,000 | 2,200,000 | 271,920 | 308,990 | 44,000 | 44,000 | 2,868,910 | 5,737,820 | 172,135 | 5,909,955 | 7,680,000 |
| з со | DARSE SCREEN (MANUAL) | W (m) : | 1.20 | L(m) : | 6.00 | SWD(m): | 0.60 | - | 0 | 1 | | Manually Bar Screen. Screen: SS316L Open apace 50mm Floor+5.000, Bottom+0.000 | 0.00 | | | 340,000 | 340,000 | 42,024 | 47,753 | 6,800 | 6,800 | 443,377 | 443,377 | 13,301 | 456,678 | 2,160,000 |
| 4 BEI | ELT CONVEYOR | Belt Width (m) : | 0.60 | L(m) : | 7.00 | | - | 1.50 | 1 | 0 | 1 | Frame: MS+ Epoxy, Belt: NBR 3mm | 1.50 | 7.0 | 7.35 | 400,000 | 400,000 | 49,440 | 56,180 | 8,000 | 8,000 | 521,620 | 521,620 | 15,649 | 537,269 | 1,143,000 |
| 5 SET | EWAGE PUMP 1 | Die (mm) : | 350 | Q(m3/h) : | 900 | H(m): | 15.00 | 75.00 | 2 | 1 | 3 | Submerable studge pump with detachable device. Overall efficiency more than 80%. Casing: CI, Impeller SS ASTM A743, Quide/Lifting chain: SS316. Pump efficiency shall be more than 80%. | 150.00 | 10.7 | 1304.00 | 1,750,000 | 1,750,000 | 216,300 | 245,788 | 35,000 | 35,000 | 2,282,088 | 6,846,263 | 205,388 | 7,051,650 | 9,990,000 |
| 6 SE | EWAGE PUMP 2 | Dia (mm) : | 250 | Q(m3/h) : | 450 | H(m): | 15.00 | 37.00 | 1 | 1 | 2 | Submerable studge pump with detachable device. Overall efficiency more than 80%. Casing: CI, Impeller SS ASTM A743, Guide/Lifting chain: SS316. Pump efficiency shall be more than 60%. Floor+6.000, Bottom+0.000. | 37.00 | 10.7 | 326.00 | 1,200,000 | 1,200,000 | 148,320 | 168,540 | 24,000 | 24,000 | 1,564,860 | 3,129,720 | 93,892 | 3,223,612 | 4,500,000 |
| 7 ELI | ECTRIC HOIST | RL(T): | 3.00 | L(m) : | 6.00 | | - | 8.50 | 1 | 0 | 1 | Single-girder overhead type. | 8.50 | | | 800,000 | 800,000 | 98,880 | 112,360 | 16,000 | 16,000 | 1,043,240 | 1,043,240 | 31,297 | 1,074,537 | 1,440,000 |
| | | | | | | | | | | | TOTAL | | 200.00 | | 1649.95 | | | | | | | | | | 19,704,326 | 30,261,000 |
| | | | | | | | | | | | | | k W | | kWh/d | | | | | | | | | | INR | INR |

Supporting Report

Mechanical Cost for STPs (3MLD)

| MECHANICAL ITEMS | | SPECI | FICATION | | | (k W/LINIT | | JMBER | | DESCRIPTION | ELECTRIC CAPACITY | Consu | al power mptioon | NJS 被算単価 | BISIC | DO11 | TAX/V AT | FORWAR | T | BASIC | TOTAL COST | ON | NJS 被算额 TOTAL | 見積 |
|--|----------------------|-----------------------|----------|-------------------------------|-------|---------------|---|-------|---|--|-------------------|----------------|---------------------|-------------|-----------|----------------|-------------|--------|--------|------------------|------------------|-----------------|-------------------------|-------|
| | | | | | | | w | S | Т | | k W | hours/d 3.0 | kWh/d 0.70 | | | | 12.50% | | 2.00% | 13=51 4/9-19\ | 14=13×TOTAL NO | 3.00% 15=14× | 16=14+15 | Rs./u |
| INLET GATE | W (m): 0.40 | L(m) : | 0.60 | Design Water Depth(m) : | 2.00 | - | 1 | 1 | 2 | Manually Sluice Gate, Well Thimble:Cast Iron, Gate: cast iron, Frame: cast iron. floor+****** bottom+****** | 0.00 | 0.0 | 0.70 | 190,000 | 190,000 | 23,484 | 26,686 | 3,800 | 3,800 | 247,770 | 495,539 | 14,866 | 510,405 | 1,674 |
| FINE SCREEN (MECHANICAL) | W (m): 0.60 | L(m) : | 6.00 | SWD(m) : | 0.40 | 1.50 | 1 | 0 | 1 | Step Type Screen including control panel. Screen: SS316L Open space 6mm | 1.50 | 6.0 | 6.30 | 1,900,000 | 1,900,000 | 234,840 | 266,855 | 38,000 | 38,000 | 2,477,695 | 2,477,695 | 74,331 | 2,552,026 | 3,330 |
| FINE SCREEN (MANUAL) | W (m): 0.60 | L(m) : | 6.00 | SWD(m) : | 0.40 | - | 0 | 1 | 1 | Manually Bar Screen: Screen: SS316L Open space 20mm | 0.00 | 0.0 | | 160,000 | 160,000 | 19,776 | 22,472 | 3,200 | 3,200 | 208,648 | 208,648 | 6,259 | 214,907 | 901 |
| BELT CONVEYOR | Belt Width (m): 0.60 | L(m) : | 5.00 | | - | 1.50 | 1 | 0 | 1 | Frame: MS+ Epoxy, Belt: NBR 3mm | 1.50 | 7.0 | 7.35 | 400,000 | 400,000 | 49,440 | 56,180 | 8,000 | 8,000 | 521,620 | 521,620 | 15,649 | 537,269 | 54 |
| GRIT CHAMBER | W (m): 3.00 | L(m) : | 3.00 | SWD(m) : | 0.90 | 2.25 | 1 | 1 | 2 | DETRITOR MECHANIS including a grit collector, a classifier, an organic return pumpa, control panel. Wetted Parts : MS+Epoxy coated | 2.25 | 24.0 | 37.80 | 1,100,000 | 1,100,000 | 135,960 | 154,495 | 22,000 | 22,000 | 1,434,455 | 2,868,910 | 86,067 | 2,954,977 | 3,2 |
| INLET WEIR GATE | W (m): 0.30 | H(m) : | 0.30 | Stroke (m) : | 0.35 | - | 2 | 0 | 2 | Manually Sluice Weir, Wall Thimble:Cast Iron, Gate: cast iron, Frame: cast iron. floor+******* bottom+******* | 0.00 | 0.0 | | 110,000 | 110,000 | 13,596 | 15,450 | 2,200 | 2,200 | 143,446 | 286,891 | 8,607 | 295,498 | 1,1 |
| MIXERS FOR ANAEROBIC TANK | W (m): 8.00 | L(m) : | 3.00 | SWD(m) : | 5.50 | 4.00 | 2 | 0 | 2 | Submersible Mixer. Casing: SS316L, Impeller: SS316L. | 8.00 | 24.0 | 134.40 | 750,000 | 750,000 | 92,700 | 105,338 | 15,000 | 15,000 | 978,038 | 1,956,075 | 58,682 | 2,014,757 | 3,18 |
| MIXERS FOR ANOXIC TANK | W (m): 8.00 | L(m) : | 8.00 | SWD(m) : | 5.50 | 4.00 | 2 | 0 | 2 | Submersible Mixer. Casing: SS316L, Impeller: SS316L. | 8.00 | 24.0 | 134.40 | 750,000 | 750,000 | 92,700 | 105,338 | 15,000 | 15,000 | 978,038 | 1,956,075 | 58,682 | 2,014,757 | 3,1 |
| DIFFUSER | SOR(kg/h) 65 | depth of diffusers | 5.0 | Efficiency E(%) | 28.0 | - | 2 | 0 | 2 | Fine Bubble Membrane Type. | 0.00 | 0.0 | | 800,000 | 800,000 | 98,880 | 112,360 | 16,000 | 16,000 | 1,043,240 | 2,086,480 | 62,594 | 2,149,074 | 1,6 |
| Air Grid Pipe Work for Diffuser imported UPVC Pipes. | W (m): 8.00 | L(m) : | 30.00 | SWD(m) : | 5.50 | - | 2 | 0 | 2 | Air Grid Pipe Work for Diffuser imported UPVC Pipes. | 0.00 | 0.0 | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1,8 |
| AIR BLOWER | Dia (mm): 150 | Q(m3/h) : | 1000 | P(K Pa) | 65 | 30.00 | 2 | 1 | 3 | Rotary lobe blower, Tri-lube type with VFD. Casing: CI, Lobes CI. With Acoustic Enclosures Noise Level:85dB at 1m DISTANCE | 60.00 | 24.0 | 1284.05 | 500,000 | 500,000 | 61,800 | 70,225 | 10,000 | 10,000 | 652,025 | 1,956,075 | 58,682 | 2,014,757 | 3,0 |
| CIRCULATION PUMP | Dia (mm): 150 | Q(m3/h) : | 120 | H(m): | 5.00 | 3.70 | 4 | 2 | 6 | Submersible sludge pump with detachable device. Overall efficiency more than 60%. Casing: CI, Impeller SS ASTM A743, Guide/Lifting chain: SS316. Pump efficiency shall be more than 60%. | 14.80 | 24.0 | 248.64 | 350,000 | 350,000 | 43,260 | 49,158 | 7,000 | 7,000 | 456,418 | 2,738,505 | 82,155 | 2,820,660 | 3,1 |
| RAS PUMP | Dia (mm): 100 | Q(m3/h) : | 40 | H(m): | 5.00 | 1.50 | 2 | 2 | 4 | Submerable studge pump with detachable device. Overall efficiency more than 60%. Casing: CI, Impelier SS ASTM A743, Gulde/Lifting chain: SS316. Pump efficiency shall be more than 60%. Submerable studge pump with detachable device. Overall efficiency more than | 3.00 | 24.0 | 50.40 | 220,000 | 220,000 | 27,192 | 30,899 | 4,400 | 4,400 | 286,891 | 1,147,584 | 34,427 | 1,181,991 | 8 |
| SAS PUMP | Dia (mm): 80 | Q(m3/h) : | 14 | H(m): | 15.00 | 2.20 | 2 | 2 | 4 | 60%. Casing: Cf. Impeller SS ASTM A743, Guide/Lifting chain: SS316. Pump efficiency shall be more than 60%. | 4.40 | 6.0 | 18.48 | 200,000 | 200,000 | 24,720 | 28,090 | 4,000 | 4,000 | 260,810 | 1,043,240 | 31,297 | 1,074,537 | 7 |
| BLOC FOR RAS/SAS PUMP | RL(T): 1.00 | L(m) : | 6.00 | | - | - | 3 | 0 | 3 | Bridge-supported type including a centre drum, two scraper arms, a scum | 0.00 | 0.0 | | 170,000 | 170,000 | 21,012 | 23,877 | 3,400 | 3,400 | 221,689 | 665,066 | 19,952 | 685,017 | 1 |
| FINAL CLARIFIER | Dia (m): 13.00 | L(m) : | - | SWD(m) : | 3.50 | 0.40 | 2 | 0 | 2 | oollector, a fixed bridge. MS+epoxy resin painting Disphragm Type. Casing: SS, Disphragm: PTFE. | 0.80 | 24.0 | 13.44 | 2,200,000 | 2,200,000 | 271,920 | 308,990 | 44,000 | 44,000 | 2,868,910 | 5,737,820 | 172,135 | 5,909,955 | 6,8 |
| ALUM DOSING PUMP | Dia (mm) : 25 | Q(I/h) : | 60 | H(MPa): | 0.70 | 0.40 | 2 | 1 | 3 | Turbine impeller. SS316L | 0.80 | 24.0 | 13.44 | 40,000 | 40,000 | 4,944 | 5,618 | 800 | 800 | 52,162 | 156,486 | 4,695 | 161,181 | 4 |
| MIXERS FOR ALUM SOLUTION | W (m): 1.00 | L(m) : | 1.00 | SWD(m) : | 1.00 | 0.40 | 2 | 0 | 2 | Gas Chlorination System including Vacuum Chlorinators, Booster Pumps , | 0.80 | | 1.12 | 60,000 | 60,000 | 7,416 | 8,427 | 1,200 | 1,200 | 78,243 | 156,486 | 4,695 | 161,181 | _ ' |
| CHLORINATOR | Q(kg/h): 3.1 | - | - | - | - | 0.10 | 1 | 1 | 2 | Interconnecting Piping , Leak Detector, Residual Ohlorine Analyses, Leak Absorption System ,Safety equipment and other accessories | 0.10 | 24.0 | 1.68 | 1,300,000 | 1,300,000 | 160,680 | 182,585 | 26,000 | 26,000 | 1,695,265 | 3,390,530 | | 3,492,246 | |
| CHLORINE BOOSTER PUMP | Dia (mm): 25 | Q(m3/h) : | 2.1 | H(m): | | 0.75 | 1 | 1 | 2 | | 0.75 | 24.0 | 12.60 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 |
| CHLORINE TONNERS ELECTRIC HOIST FOR | - | | - | | - | - | 2 | 2 | 4 | Single-girder overhead type. | 0.00 | | | 150,000 | 150,000 | 18,540 | 21,068 | 3,000 | 3,000 | 195,608 | 782,430 | 23,473 | 805,903 | 8 |
| TONNERS | RL(T): 3.00 | L(m) : | 6.00 | | - | 8.60 | 1 | 0 | 1 | Diaphragm Type. Casing: SS, Diaphragm: PTFE. | 8.60 | | 6.02 | 800,000 | 800,000 | 98,880 | 112,380 | 16,000 | 16,000 | 1,043,240 | 1,043,240 | 31,297 | 1,074,537 | 1 |
| DECHLORINE DOSING PUMP MIXER FOR DECLORINE | Dia (mm): 15 | Q(I/h) : | 7.5 | P(M Pa) | 1.0 | 0.20 | 1 | 0 | 1 | Turbine impeller. SS318L | 0.20 | | 3.36 | 20,000 | 50,000 | 2,472 6.180 | 7,023 | 1,000 | 1,000 | 26,081 65,203 | 52,162 65,203 | 1,565 | 53,727 67,159 | 2 |
| SOLUTION AIR BLOWER FOR DECHLORINE MIXING | Dia (mm): 40 | Q(m3/h) : | 12 | P(K Pa) | 20 | 0.75 | 1 | 1 | 2 | Rotary lobe blower, Tri-lube type. Casing: Cl, Lobes Cl. With Accustic Enclosures Noise Levelt8dB at 1m DISTANCE | 0.10 | | 12.60 | 100,000 | 100,000 | 12,360 | 14,045 | 2,000 | 2,000 | 130,405 | 260,810 | 7,824 | 268,634 | 8 |
| TANK ELECTRIC HOIST FOR | RL(T): 1.00 | L(m): | | r(n ra) | - | 4.70 | 1 | 0 | 1 | Single-girder overhead type. | 4.70 | 1.0 | 3.29 | 500,000 | 500,000 | 61,800 | 70,225 | 10,000 | 10,000 | 652.025 | 652,025 | 19,561 | 671,586 | |
| AIR BLOWER FOR CENTRIFUGE FEED | Dia (mm): 65 | Q(m3/h) : | 130 | P(K Pa) | 40 | 3.70 | 1 | 1 | | Rotary lobe blower, Tri-lube type. Casing: CI, Lobes CI. With Acoustic Enclosures Noise Levek85dB at 1m DISTANCE | 3.70 | | 31.08 | 160,000 | 160,000 | | 22,472 | | 3,200 | 208.648 | 417.296 | 12,519 | 429,815 | 7 |

| pply |
|----------|
| and |
| Sewerage |
| Project |
| (Pha |

Supporting Report

| STATIFUGE FEED PUMP Dia (mm) : 100 O(m3/h) : 16 | MECHANICAL ITEMS | | SPEC | IFICATION | | | (k W/LINIT | | NUMBEI | R | DESCRIPTION | ELECTRIC CAPACITY | | ical power umptioon | NJS 積算単価 | BISIC | EXCISE DUTY | TAX/V | PACKING & FORWAR | Т | BASIC | TOTAL COST | ERECTI ON | NJS 積算額 TOTAL | Toshiba 見積額 |
|--|-------------------------------|----------------|-----------|-----------|----------|-------|---------------|---|--------|-------|--|----------------------|------|------------------------|-------------|-----------|-------------|------------|------------------------|--------|--------------|-------------------|--------------|-------------------------|----------------|
| INTRIFUCE FEED PUMP Dia (mm): 100 Q(m3/h): 16 Hm): 20 5.50 1 1 2 Progress Cevity Pump. Casing: CI, Rotor: SS316, Stator: NB. 5.50 10.3 38.66 210,000 210,000 25,856 28,465 4,200 4,200 273,851 547,701 16,431 544,132 594. INTRIFUCE Q(m3/h): 16.00 22.20 1 1 2 Solid bowl type with Motor including a control panel. Input TSS Oct. Min. W/L. Westerd Parks SS304. Input TSS Oct. Min. Will Parks SS304. Input TSS Oct. Min. W/L. Westerd Parks SS304. Input TSS Oct. Min. W/L. West | | | | | | | | W | S | Т | | k W | | | | | | | | | | | | | Rs./unit |
| INTRIFUGE FEED PUMP Dia (mm): 100 Q(m3/h): 160 Hm): 20 5.50 1 1 1 2 Solid bowl type with Motor including a control panel. Wetted Parts SS304. Early TSS 0.5% w/r. Dewatered sludge TSS required 19%w/w st polymer dose INTRIFUGE Q(m3/h): 1.00 22.20 1 1 2 Solid bowl type with Motor including a control panel. Wetted Parts SS304. Early TSS 0.5% w/r. Dewatered sludge TSS required 19%w/w st polymer dose INTRIFUGE Q(m3/h): 1.00 22.20 1 1 1 2 Solid bowl type with Motor including a control panel. INTRIFUGE Q(m3/h): 1.00 22.20 1 1 1 2 Solid bowl type with Motor including a control panel. INTRIFUGE Q(m3/h): 1.00 22.20 1 1 1 2 Solid bowl type with Motor including a control panel. INTRIFUGE PARTS SS304. Early TSS 0.5% w/r. Dewatered sludge TSS required 19%w/w st polymer dose INTRIFUGE Q(m3/h): 1.00 22.20 1 1 1 2 Solid bowl type with Motor including a control panel. INTRIFUGE Q(m3/h): 1.00 22.20 1 1 1 2 Solid bowl type with Motor including a control panel. INTRIFUGE PARTS SS304. Early TSS 0.5% w/r. Dewatered sludge TSS required 19%w/w st polymer dose INTRIFUGE Q(m3/h): 1.00 - 1.00.00 1.100 | | | | | | | | | | | | | 3.0 | 0.70 | | 8 | 9=8 × | 10+(8+8) × | 11=8× | 12=8 × | 13=SUM(8:12) | 14=13 × TOTAL NO. | 15=14× | 16=14+15 | |
| INTRIFUGE Q(m3/h): 16.00 22.20 1 1 2 Wetted Parts SS304. Input TSS O(sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge TSS required 19km/w at polymer does Input TSO (sk W/n. Dewatered sludge | CENTRIFUGE FEED PUMP | Dia (mm): 100 | Q(m3/h) : | 16 | H(m): | 20 | 5.50 | 1 | 1 | 2 | Progress Cavity Pump. Casing: Cl., Rotor: SS316, Stator: NB. | 5.50 | 10.3 | 39.66 | 210,000 | 210,000 | 25,956 | 29,495 | 4,200 | 4,200 | 273,851 | 547,701 | 16,431 | 564,132 | 594,0 |
| LECTRIC HOIST RL(T): 5.00 L(m): 8.00 - 17.10 1 0 1 T T T T T T T T T T T T T T T T | GENTRIFUGE | Q(m3/h): 16.00 | - | - | - | - | 22.20 | 1 | 1 | 2 | Wetted Parts SS304. | 22.20 | 10.3 | 160.08 | 3,600,000 | 3,600,000 | 444,980 | 505,620 | 72,000 | 72,000 | 4,694,580 | 9,389,160 | 281,675 | 9,670,835 | 7,920,0 |
| Vivile (Procedure Dosing W (m): 1.00 L(m): 1.50 SWD(m): 1.80 0.75 2 0 2 0 2 0 2 0 2 0 0 | ELECTRIC HOIST | RL(T): 5.00 | L(m) : | 6.00 | | - | 17.10 | 1 | 0 | 1 | Single-girder overhead type. | 17.10 | 0.0 | 0.00 | 1,100,000 | 1,100,000 | 135,980 | 154,495 | 22,000 | 22,000 | 1,434,455 | 1,434,455 | 43,034 | 1,477,489 | 1,440,0 |
| NYELEGYROL/TE DOSING Dia (mm): 20 Q(m3/h): 0.50 H(m): 20.00 0.40 1 1 2 288,834 450 4 | POLYELECTROLYTE DOSING SYSTEM | W (m): 1.00 | L(m) : | 1.50 | SWD(m) : | 1.80 | 0.75 | 2 | 0 | 2 | Agitator 100RPM,Slow Speed, SS304 | 1.50 | 2.0 | 2.10 | 80,000 | 80,000 | 9,888 | 11,236 | 1,600 | 1,600 | 104,324 | 208,648 | 6,259 | 214,907 | 540,0 |
| INTRATE TRANSFER PUMP Dia (mm): 100 Q(m3/h): 40 H/m): 15 5.50 1 1 2 with detachable device Efficiency >50% 5.50 1.0 15.40 300,000 30,000 37,080 42,135 6,000 6,000 391,215 782,430 23,473 806,903 306,000 30,0 | POLYELECTROLYTE DOSING PUMP | Dia (mm): 20 | Q(m3/h) : | 0.50 | H(m): | 20.00 | 0.40 | 1 | 1 | 2 | Progress Cavity Pump. Casing: CI, Rotor: SS316, Stator: NB. | 0.40 | 10.3 | 2.88 | 100,000 | 100,000 | 12,360 | 14,045 | 2,000 | 2,000 | 130,405 | 260,810 | 7,824 | 268,634 | 450, |
| | CENTRATE TRANSFER PUMP | Dia (mm): 100 | Q(m3/h) : | 40 | H(m): | 15 | 5.50 | 1 | 1 | 2 | with detachable device | 5.50 | 4.0 | 15.40 | 300,000 | 300,000 | 37,080 | 42,135 | 6,000 | 6,000 | 391,215 | 782,430 | 23,473 | 805,903 | 306,0 |
| | | | | | | | | | | TOTAL | • | 176.95 | | 2240.69 | | | | | | | | | | 47,118,456 | 60,246,0 |
| | | | | | | | | | | | | kW | ٧ | kWh/d | | | | | | | | | | INR | INR |
| | | | | | | | | | | | | | 1 | | | | | | | | | | | | 1 |

Mechanical Cost for STPs (10MLD)

| MECHANICAL ITEMS | | | SPECI | FICATION | ı | | (k W/HNIT | , | NUMBER | t | DESCRIPTION | ELECTRIC CAPACITY | Electric Consu | al power mptioon | NJS 積算単価 | BISIC | EXCISE DUTY | SALES TAX/V | PACKING & FORWAR | T | BASIC | TOTAL COST | ERECTI ON | NJS積算額 TOTAL | Toshiba 見積額 |
|--|------------------|-------|-----------------------|----------|-------------------------------|-------|--------------|---|--------|---|--|----------------------|-------------------|---------------------|-------------|-----------|-------------|----------------|------------------------|--------|--------------|-----------------|--------------|-----------------|----------------|
| | | | | | | | W/ Care | w | S | т | | k W | hours/d | kWh/d | | | 12.36% | 12.50% | | 2.00% | | | 3.00% | | Rs. |
| | | | | | | | | | | | | | 10.0 | 0.70 | | 8 | 9=8× | 10=(8+9)× | 11=8× | 12=8× | 13=SUM(8:12) | 14=13×TOTAL NO. | 15=14× | 16=14+15 | |
| INLET GATE | W (m) : | 0.40 | L(m) : | 0.60 | Design Water Depth(m) : | 2.00 | - | 2 | 1 | 3 | Manually Sluice Gate, Wall Thimble:Cast Iron, Gate: cast iron, Frame: cast iron. floor******* | 0.00 | | | 190,000 | 190,000 | 23,484 | 26,686 | 3,800 | 3,800 | 247,770 | 743,309 | 22,299 | 765,608 | 2,511,0 |
| FINE SCREEN (MECHANICAL) | W (m) : | 0.80 | L(m) : | 6.00 | SWD(m) : | 0.40 | 1.50 | 2 | 0 | 2 | Step Type Screen including control panel. Screen: SS316L. Open space 6mm | 3.00 | 6.0 | 12.60 | 2,000,000 | 2,000,000 | 247,200 | 280,900 | 40,000 | 40,000 | 2,608,100 | 5,216,200 | 156,486 | 5,372,686 | 6,660,0 |
| FINE SCREEN (MANUAL) | W (m) : | 0.80 | L(m) : | 6.00 | SWD(m) : | 0.40 | - | 0 | 1 | 1 | Manually Bar Screen. Screen: SS316L Open space 20mm | 0.00 | | | 250,000 | 250,000 | 30,900 | 35,113 | 5,000 | 5,000 | 326,013 | 326,013 | 9,780 | 335,793 | 1,350,0 |
| BELT CONVEYOR | Belt Width (m) : | 0.60 | L(m) : | 7.00 | | - | 1.50 | 1 | 0 | 1 | Frame: MS+ Epoxy, Belt: NBR 3mm | 1.50 | 7.0 | 7.35 | 400,000 | 400,000 | 49,440 | 56,180 | 8,000 | 8,000 | 521,620 | 521,620 | 15,649 | 537,269 | 810,0 |
| GRIT CHAMBER | W (m) : | 5.00 | L(m) : | 5.00 | SWD(m) : | 0.90 | 2.25 | 1 | 1 | 2 | DETRITOR MECHANIS including a grit collector, a classifier, an organic return pumps, control panel. Wetted Parts: MS+Epoxy coated | 2.25 | 24.0 | 37.80 | 1,550,000 | 1,550,000 | 191,580 | 217,698 | 31,000 | 31,000 | 2,021,278 | 4,042,555 | 121,277 | 4,163,832 | 4,140,0 |
| 3 INLET WEIR GATE | W (m) : | 0.80 | H(m) : | 0.40 | Stroke (m) : | 0.45 | - | 2 | 0 | 2 | Manually Sluice Weir, Wall Thimble:Cast Iron, Gate: cast iron, Frame: cast iron. floor+****** | 0.00 | | | 340,000 | 340,000 | 42,024 | 47,753 | 6,800 | 6,800 | 443,377 | 886,754 | 26,603 | 913,357 | 1,566,0 |
| MIXERS FOR ANAEROBIC TANK | W (m) : | 8.00 | L(m) : | 8.00 | SWD(m) : | 5.50 | 4.00 | 2 | 0 | 2 | Submersible Mixer. Casing: SS316L, Impeller: SS316L | 8.00 | 24.0 | 134.40 | 750,000 | 750,000 | 92,700 | 105,338 | 15,000 | 15,000 | 978,038 | 1,956,075 | 58,682 | 2,014,757 | 6,300,0 |
| MIXERS FOR ANOXIC TANK | W (m) : | 8.00 | L(m) : | 12.50 | SWD(m) : | 5.50 | 4.00 | 4 | 0 | 4 | Submersible Mixer. Casing: SS316L, Impeller: SS316L. | 16.00 | 24.0 | 268.80 | 750,000 | 750,000 | 92,700 | 105,338 | 15,000 | 15,000 | 978,038 | 3,912,150 | 117,365 | 4,029,515 | 6,300,0 |
| DIFFUSER | SOR(kg/h) | 218 | depth of diffusers | 5.0 | Efficiency E(%) | 28.0 | - | 2 | 0 | 2 | Fine Bubble Membrane Type. | 0.00 | | | 2,500,000 | 2,500,000 | 309,000 | 351,125 | 50,000 | 50,000 | 3,260,125 | 6,520,250 | 195,608 | 6,715,858 | 2,700,0 |
| 0 AIR BLOWER | Dia (mm) : | 200 | Q(m3/h) : | 1700 | P(K Pa) | 65 | 55.00 | 4 | 2 | 8 | Rotary lobe blower, Tri-lube type with VFD. Casing Cl, Lobes Cl. With Acoustic Enclosures Noise Level:85dB at 1m DISTANCE | 220.00 | 24.0 | 4365.79 | 550,000 | 550,000 | 67,980 | 77,248 | 11,000 | 11,000 | 717,228 | 4,303,365 | 129,101 | 4,432,466 | 6,588,0 |
| 1 CIRCULATION PUMP | Dia (mm) : | 200 | Q(m3/h) : | 385 | H(m): | 5.00 | 11.00 | 4 | 2 | 6 | Submersible sludge pump with detachable device. Overall efficiency more than 60%. Casing: Cl, Impeller SS ASTM A743, Guide/Lifting chain: SS316. | 44.00 | 24.0 | 739.20 | 880,000 | 880,000 | 108,768 | 123,596 | 17,600 | 17,600 | 1,147,564 | 6,885,384 | 206,562 | 7,091,946 | 10,098, |
| 2 RAS PUMP | Dia (mm) : | 100 | Q(m3/h) : | 125 | H(m): | 5.00 | 3.70 | 2 | 2 | 4 | Submersible sludge pump with detachable device. Overall efficiency more than 60%. Casing: Cl, Impeller SS ASTM A743, Guide/Lifting chain: SS316. | 7.40 | 24.0 | 124.32 | 250,000 | 250,000 | 30,900 | 35,113 | 5,000 | 5,000 | 326,013 | 1,304,050 | 39,122 | 1,343,172 | 2,088, |
| 3 SAS PUMP | Dia (mm) : | 100 | Q(m3/h) : | 50 | H(m): | 15.00 | 5.50 | 2 | 2 | 4 | Submersible sludge pump with detachable device. Overall efficiency more than 60%. Casing: Cl, Impeller SS ASTM A743, Guide/Lifting chain: SS316. | 11.00 | 6.0 | 46.20 | 300,000 | 300,000 | 37,080 | 42,135 | 6,000 | 6,000 | 391,215 | 1,564,860 | 46,946 | 1,611,806 | 1,800, |
| HAND OPERATION CHAIN BLOC FOR RAS/SAS PUMP | RL(T): | 1.00 | L(m) : | 6.00 | | | - | 3 | 0 | 3 | | 0.00 | | | 170,000 | 170,000 | 21,012 | 23,877 | 3,400 | 3,400 | 221,689 | 665,066 | 19,952 | 685,017 | 999, |
| FINAL CLARIFIER | Dia (m) : | 23.00 | L(m) : | - | SWD(m) : | 3.50 | 2.20 | 2 | 0 | 2 | Column-supported type including a centre drum, two scraper arms, a scum collector, a fixed bridge. MS+epoxy resin painting | 4.40 | 24.0 | 73.92 | 3,500,000 | 3,500,000 | 432,600 | 491,575 | 70,000 | 70,000 | 4,564,175 | 9,128,350 | 273,851 | 9,402,201 | 12,600, |
| 6 ALUM DOSING PUMP | Dia (mm) : | 25 | Q(I/h) : | 180 | H(MPa): | 0.70 | 0.40 | 2 | 1 | 3 | Diaphragm Type. Casing: SS, Diaphragm: PTFE. | 0.80 | 24.0 | 13.44 | 40,000 | 40,000 | 4,944 | 5,618 | 800 | 800 | 52,162 | 156,486 | 4,695 | 161,181 | 1,026,0 |
| 7 MIXERS FOR ALUM SOLUTION | W (m) : | 1.20 | L(m) : | 1.20 | SWD(m) : | 1.80 | 0.75 | 2 | 0 | 2 | Turbine impeller. SS316L | 1.50 | 2.0 | 2.10 | 60,000 | 60,000 | 7,416 | 8,427 | 1,200 | 1,200 | 78,243 | 156,486 | 4,695 | 161,181 | 666,0 |

NJS Consultants Co.,

MECHANICAL ITEMS

19 CHLORINE BOOSTER PUMP

21 ELECTRIC HOIST CRANE

22 DECHLORINE DOSING PUMP

23 MIXER FOR DECLORINE SOLUTION

25 ELECTRIC HOIST FOR CHEMICALS

AIR BLOWER 26 FOR CENTRIFUGE FEED

27 CENTRIFUGE FEED PUMP

28 CENTRIFUGE

29 ELECTRIC HOIST

30 MIXER FOR POLYELECTROLYTE SOLUTION TANK

31 DRY POLYELECTROLYTE FEEDER

AIR BLOWER 24 FOR DECHLORINE MIXING

20 CHLORINE TONNERS

18 CHLORINATOR

SPECIFICATION

Q(m3/h): 3.6

L(m): 6.00

Q(I/h): 23

Q(m3/h): 40

L(m): 6.00

Q(m3/h): 27

L(m): 6.00

L(m): 1.50

Q(m3/h): 0.80

Dia (mm): 100 Q(m3/h): 400

Q(kg/h): 9.4

Dia (mm): 25

RL(T): 3.00

Dia (mm): 15

Dia (mm): 40

RL(T): 1.00

Dia (mm): 125

Q(m3/h): 27.00

RL(T): 5.00

W (m): 1.50

needty (tuz/h): 15.00

Dia (mm): 32

33 CENTRATE TRANSFER PUMP Dia (mm): 100 Q(m3/h): 40

(k W/UNIT

0.10

1.50 1 1

8.60

0.20 1

1.50 1 1

4.70

11.00 1

7.50 2 1

44.50 2

17.10

1.50 2 0

0.40 2 0

0.75 2

5.50 2

1 0

0.10 1

H(m): 50.00

H(MPa): 1.00

P(K Pa) 40

SWD(m):

P(K Pa) 20

H(m): 20

H(m): 20.00

H(m): 15

NUMBER

1

0

0

1

w s

2 2

| Bengaluru |
|-----------|
| Water |
| Supply |
| and |
| Sewerage |
| Project |
| (Phase |

EXCISE DUTY AT FORWAR INSURA

12.36% 12.50% 2.00% 2.00%

40,000 40,000

3,000 3,000

2,200 2,200

4.400 4.400 286.891

11,000 11,000 717,228

84,000 84,000 5,477,010

4,000 4,000 260,810

6,000 6,000 391,215

22,000

247,200 280,900

18,540 21,068

98,880 112,360 16,000 16,000 1,043,240

2,472 2,809 400 400 26,081

7,416 8,427 1,200 1,200 78,243

13.596

61,800 70,225 10,000 10,000

11,124 12,641 1,800 1,800 117,365

17,304 19,663 2,800 2,800

27.192 30.899

67,980 77,248

519,120 589,890

24,720 28,090

37,080 42,135

135,980 154,495 22,000

15,450

BASIC

9=8 × 10=(0=0)× 11=8 × 12=8 × 13=SUM(8:12) 14=13×TOTAL NO. 15=14 × 16=14+15

2,608,100

195,608

143,446

652,025

1,434,455

182,567

TOTAL COST ERECTI NJS被算額 TOTAL

5,216,200

782,430

1,043,240

52,162

78,243

286.891

652,025

573,782

2,151,683

16,431,030

1.434.455

234,729

521.620

547,701

1,173,645

3.00%

156,486 5,372,686

0 0

23,473 805,903

31,297 1,074,537

1.565

2,347 80,590

8,607 295,498

19,561 671,586

17.213 590.995

64,550 2,216,233

492,931 16,923,961

43.034 1.477.489

7,042 241,771

15,649 537,269

16,431 564,132

35,209 1,208,854

53,727

Toshiba 見積額

Rs.

6,480,000

450,000

864,000

900,000

450,000

324,000

1.152.000

900,000

1,926,000

1,755,000

20,520,000

1.440,000

666,000

2.520.000

945,000

594,000

INR

81,852,871 110,088,000

INR

Electrical power Consumptioon

hours/d kWh/d

10.0 0.70

NJS 積算単価

2,000,000

150,000 150,000

800,000 800,000

20,000 20,000

60,000 60,000

110,000 110,000

500,000 500,000

550,000 550,000

4,200,000

1.100.000

90,000 90,000

200.000 200.000

140,000 140,000

300,000 300,000

6799.17

kWh/d

220.000 220.000

4,200,000

1.100,000

BISIC

8

2,000,000

ELECTRIC CAPACITY

k W

0.10 24.0 1.68

1.50 24.0 25.20

0.00

8.60 1.0 6.02

0.20 24.0 3.36

0.10 2.0 0.14

1.50

4.70 1.0 3.29

11.00 12.0 92.40

15.00 10.3 108.15

89.00 10.3 641.69

17.10 0.0 0.00

0.80 0.5 0.28

1.50 10.3 10.82

11.00 6.6 50.82

484.95

k W

24.0 25.20

2.0 4.20

DESCRIPTION

Gas Chlorination System including Vacuum Chlorinators, Booster Pumps , Interconnecting Piping , Leak Detector, Residual Chlorine Analyses, Leak Absorption System ,Safety equipment and other

Single-girder overhead type.

Turbine impeller. SS316L

Single-girder overhead type.

ingle-girder overhead type.

CI, Submersible Type with detachable device Efficiency >50%

TOTAL

Agitator 100RPM.Slow Speed, SS304

Diaphragm Type. Casing: SS, Diaphragm: PTFE.

Rotary lobe blower, Tri-lube type. Casing: Cl, Lobes Cl. With Acoustic Enclosures Noise Level:85dB at 1m DISTANCE

Rotary lobe blower, Tri-lube type. Casing: CI, Lobes CI. With Acoustic Enclosures Noise Level:85dB at 1m DISTANCE

Progress Cavity Pump. Casing: Cl, Rotor: SS316, Stator: NB.

Solid bowl type with Motor including a control panel. Wetted Parts SS304. Input TSS 0.8% w/w. Dewatered sludge TSS required 18%w/w at

Automatic feed system for batch-wise preparation and metering of

Progress Cavity Pump. Casing: CI, Rotor: SS316, Stator: NB.

Supporting Report

Mechanical Cost for STPs (15MLD)

| MECHANICAL ITEMS | | | SPECI | FICATION | | | (k W/UNIT | w | NUMBER | ₹ T | DESCRIPTION | ELECTRIC CAPACITY k W | Consu | al power nptioon | NJS 積算単価 | BISIC | EXCISE DUTY 12.36% | TAX/V AT | PACKING & FORWAR 2.00% | INSURA NGE | BASIC | TOTAL COST | ON | |
|---|------------------|-------|--------------------------------------|----------|-------------------------------|-------|--------------|---|--------|----------|--|-----------------------------|-----------------|---------------------|-------------|-----------|--------------------------|---------------------|---------------------------------|----------------|--------------|----------------|-----------------|-------|
| | | | | | | | | | • | • | | KΨ | hours/d 15.0 | kWh/d 0.70 | | 8 | 9=8 × | 12.50% 10=(8+9)× | 2.00% 11=8 × | 2.00% 12=8× | 13=SUM(8:12) | 14=13×TOTAL NO | 3.00% 15=14× | × 16= |
| INLET GATE | W (m): | 0.50 | L(m) : | 0.75 | Design Water Depth(m) : | 2.00 | - | 2 | 1 | 3 | Manually Sluice Gate, Wall Thimble:Cast Iron, Gate: cast iron, Frame: cast iron. floor+****** bottom********************************** | 0.00 | | | 240,000 | 240,000 | 29,664 | 33,708 | 4,800 | 4,800 | 312,972 | 938,916 | 28,167 | 7 96 |
| FINE SCREEN (MECHANICAL) | W (m) : | 1.00 | L(m) : | 6.00 | SWD(m) : | 0.50 | 1.50 | 2 | 0 | 2 | Step Type Screen including control panel. Screen: SS316L Open space 6mm | 3.00 | 6.0 | 12.60 | 2,100,000 | 2,100,000 | 259,560 | 294,945 | 42,000 | 42,000 | 2,738,505 | 5,477,010 | 164,310 | 0 5,6 |
| FINE SCREEN (MANUAL) | W (m): | 1.00 | L(m) : | 6.00 | SWD(m) : | 0.50 | - | 0 | 1 | 1 | Manually Bar Screen. Screen: SS316L Open space 20mm | 0.00 | | | 310,000 | 310,000 | 38,316 | 43,540 | 6,200 | 6,200 | 404,256 | 404,256 | 12,128 | 8 41 |
| BELT CONVEYOR | Beit Width (m) : | 0.60 | L(m) : | 7.00 | | - | 1.50 | 1 | 0 | 1 | Frame: MS+ Epoxy, Belt: NBR 3mm | 1.50 | 7.0 | 7.35 | 400,000 | 400,000 | 49,440 | 56,180 | 8,000 | 8,000 | 521,620 | 521,620 | 15,649 | 9 5 |
| GRIT CHAMBER | W (m): | 6.00 | L(m) : | 6.00 | SWD(m) : | 0.90 | 2.25 | 1 | 1 | 2 | DETRITOR MECHANIS including a grit collector, a classifier, an organic return pumps, control panel. Wetted Parts: MS+Epoxy coated | 2.25 | 24.0 | 37.80 | 1,600,000 | 1,600,000 | 197,760 | 224,720 | 32,000 | 32,000 | 2,086,480 | 4,172,960 | 125,189 | 19 4, |
| INLET WEIR GATE | W (m) : | 0.80 | H(m) : | 0.50 | Stroke (m) : | 0.55 | - | 2 | 0 | 2 | Manually Sluice Weir, Wall Thimble:Cast Iron, Gate: cast iron, Frame: cast iron. | 0.00 | | | 340,000 | 340,000 | 42,024 | 47,753 | 6,800 | 6,800 | 443,377 | 886,754 | 26,603 | 3 9 |
| MIXERS FOR ANAEROBIC TANK | W (m): | 8.00 | L(m) : | 12.00 | SWD(m) : | 5.50 | 4.00 | 2 | 0 | 2 | bottom****** Submersible Mixer. Casing: SS316L, Impeller: SS316L. | 8.00 | 24.0 | 134.40 | 750,000 | 750,000 | 92,700 | 105,338 | 15,000 | 15,000 | 978,038 | 1,956,075 | 58,682 | 2 2, |
| MIXERS FOR ANOXIC TANK | W (m): | 8.00 | L(m) : | 12.40 | SWD(m): | 5.50 | 4.00 | 6 | 0 | 6 | Submersible Mixer. Casing: SS316L, Impeller: SS316L. | 24.00 | 24.0 | 403.20 | 750,000 | 750,000 | 92,700 | 105,338 | 15,000 | 15,000 | 978,038 | 5,868,225 | 176,047 | 7 6,0 |
| DIFFUSER | SOR(kg/h) | 345 | The setting depth of diffusers | 5.0 | Efficiency E(%) | 28.0 | - | 2 | 0 | 2 | Fine Bubble Membrane Type. | 0.00 | | | 3,200,000 | 3,200,000 | 395,520 | 449,440 | 64,000 | 64,000 | 4,172,960 | 8,345,920 | 250,378 | 8 8, |
| AIR BLOWER | Dia (mm) : | 200 | H(m) · Q(m3/h) : | 2600 | P(K Pa) | 65 | 90.00 | 4 | 2 | 6 | Rotary lobe blower, Tri-lube type with VFD. Casing: CI, Lobes CI. With Acoustic Enclosures Noise Level:85dB at 1m DISTANCE | 360.00 | 24.0 | 6676.99 | 650,000 | 650,000 | 80,340 | 91,293 | 13,000 | 13,000 | 847,633 | 5,085,795 | 152,574 | 4 5 |
| CIRCULATION PUMP | Dia (mm) : | 300 | Q(m3/h): | 580 | H(m): | 5.00 | 18.50 | 4 | 2 | 6 | Submersible sludge pump with detachable device. Overall efficiency more than 80%. Casing: CI, Impeller SS ASTM A743, Quide/Lifting chain: SS316. | 74.00 | 24.0 | 1243.20 | 1,300,000 | 1,300,000 | 160,680 | 182,585 | 26,000 | 26,000 | 1,695,265 | 10,171,590 | 305,148 | 8 10 |
| RAS PUMP | Dia (mm) : | 150 | Q(m3/h): | 190 | H(m): | 5.00 | 5.50 | 2 | 2 | 4 | Submersible sludge pump with detachable device. Overall efficiency more than 80%. Casing: Cl, Impeller SS ASTM A743, Quide/Lifting chain: SS316. | 11.00 | 24.0 | 184.80 | 400,000 | 400,000 | 49,440 | 56,180 | 8,000 | 8,000 | 521,620 | 2,086,480 | 62,594 | 4 2 |
| SAS PUMP | Dia (mm) : | 100 | Q(m3/h): | 80 | H(m): | 15.00 | 7.50 | 2 | 2 | 4 | Submersible sludge pump with detachable device. Overall efficiency more than 80%. Casing: Cl, Impeller SS ASTM A743, Quide/Lifting chain: SS316. | 15.00 | 6.0 | 63.00 | 340,000 | 340,000 | 42,024 | 47,753 | 6,800 | 6,800 | 443,377 | 1,773,508 | 53,205 | 5 1, |
| HAND OPERATION CHAIN BLOC | RL(T): | 1.00 | L(m) : | 6.00 | | - | - | 3 | 0 | 3 | | 0.00 | | | 170,000 | 170,000 | 21,012 | 23,877 | 3,400 | 3,400 | 221,689 | 665,066 | 19,952 | 2 6 |
| FOR RAS/SAS PUMP FINAL CLARIFIER | Dia (m) : | 28.50 | L(m) : | - | SWD(m) : | 3.50 | 2.20 | 2 | 0 | 2 | Column-supported type including a centre drum, two scraper arms, a soum collector, a fixed bridge. MS+epoxy resin painting | 4.40 | 24.0 | 73.92 | 4,000,000 | 4,000,000 | 494,400 | 561,800 | 80,000 | 80,000 | 5,216,200 | 10,432,400 | 312,972 | 2 10 |
| ALUM DOSING PUMP | Dia (mm) : | 40 | Q(I/h) : | 260 | H(MPa): | 0.30 | 0.75 | 2 | 1 | 3 | Diaphragm Type. Casing: SS, Diaphragm: PTFE. | 1.50 | 24.0 | 25.20 | 100,000 | 100,000 | 12,360 | 14,045 | 2,000 | 2,000 | 130,405 | 391,215 | 11,736 | 6 4 |
| MIXERS FOR ALUM SOLUTION | W (m) : | 1.40 | L(m) : | 1.40 | SWD(m) : | 1.80 | 0.75 | 2 | 0 | 2 | Turbine impeller. \$\$316L | 1.50 | 2.0 | 2.10 | 60,000 | 60,000 | 7,416 | 8,427 | 1,200 | 1,200 | 78,243 | 156,486 | 4,695 | , 1 |
| CHLORINATOR | Q(kg/h): | 14.1 | - | - | - | - | 0.10 | 1 | 1 | 2 | Gas Chlorination System including Vacuum Chlorinators, Booster Pumps , Interconnecting Piping , Leak Detector, Residual Chlorine Analyses, Leak Absorption System ,Safety equipment and other accessories | 0.10 | 24.0 | 1.68 | 2,550,000 | 2,550,000 | 315,180 | 358,148 | 51,000 | 51,000 | 3,325,328 | 6,650,655 | 199,520 | 20 6 |
| CHLORINE BOOSTER PUMP | Dia (mm) : | 25 | Q(m3/h) : | 5.4 | H(m): | 50.00 | 2.20 | 1 | 1 | 2 | Paradiplication of the paradiplication and the paradip | 2.20 | 24.0 | 36.96 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| CHLORINE TONNERS | | - | | - | | - | - | 2 | 2 | 4 | | 0.00 | | | 150,000 | 150,000 | 18,540 | 21,068 | 3,000 | 3,000 | 195,608 | 782,430 | 23,473 | 3 |
| ELECTRIC HOIST CRANE | RL(T): | 3.00 | L(m) : | 6.00 | | - | 8.60 | 1 | 0 | 1 | Single-girder overhead type. | 8.60 | 1.0 | 6.02 | 800,000 | 800,000 | 98,880 | 112,360 | 16,000 | 16,000 | 1,043,240 | 1,043,240 | 31,297 | 7 1 |
| DECHLORINE DOSING PUMP | Dia (mm) : | 15 | Q(I/h) : | 17 | H(MPa): | 1.00 | 0.20 | 2 | 1 | 3 | Diaphragm Type. Casing: SS, Diaphragm: PTFE. | 0.40 | 24.0 | 6.72 | 20,000 | 20,000 | 2,472 | 2,809 | 400 | 400 | 26,081 | 78,243 | 2,347 | , |
| MIXER FOR DECLORINE SOLUTION | Capacity(m3) : | 0.20 | | | | | 0.10 | 2 | 0 | 2 | Turbine impeller. SS316L | 0.20 | 2.0 | 0.28 | 60,000 | 60,000 | 7,416 | 8,427 | 1,200 | 1,200 | 78,243 | 156,486 | 4,695 | 5 |
| AIR BLOWER FOR DECHLORINE MIXING TANK | Dia (mm) : | 40 | Q(m3/h) : | 55 | P(K Pa) | 20 | 1.50 | 1 | 1 | 2 | Rotary lobe blower, Tri-lube type. Casing: CI, Lobes CI, With Acoustic Enclosures Noise Level:85dB at 1m DISTANCE | 1.50 | 24.0 | 25.20 | 110,000 | 110,000 | 13,596 | 15,450 | 2,200 | 2,200 | 143,446 | 286,891 | 8,607 | , : |
| ELECTRIC HOIST FOR CHEMICALS | RL(T) : | 1.00 | L(m) : | 6.00 | | - | 4.70 | 1 | 0 | 1 | Single-girder overhead type. | 4.70 | 1.0 | 3.29 | 500,000 | 500,000 | 61,800 | 70,225 | 10,000 | 10,000 | 652,025 | 652,025 | 19,561 | 11 |
| SLUDGE THICKENER | Dia (m) : | 11.00 | L(m) : | - | SWD(m): | 4.00 | 0.40 | 2 | 0 | 2 | Bridge-supported type including a centre drum, two scraper arms, a scum collector, a fixed bridge. MS-tepoxy resin painting | 0.80 | 24.0 | 13.44 | 2,000,000 | 2,000,000 | 247,200 | 280,900 | 40,000 | 40,000 | 2,608,100 | 5,216,200 | 156,486 | 6 5, |

| | , | , | , | |
|---|---|---|---|--|
| | 4 | ı | | |
| | | | | |
| | | | | |
| | į | ۱ | | |
| , | | | | |
| • | 4 | | | |
| | 1 | | • | |
| | | | | |
| C | | ì | | |
| ٠ | , | | | |
| | | | | |

| MECHANICAL ITEMS | | | SPECIF | ICATION | | | (k W/UNIT | ı | NUMBE | R | DESCRIPTION | ELECTRIC CAPACITY | Electric Consu | al power nptioon | NJS 積算単価 | BISIC | EXCISE DUTY | TAX/V | PACKING & FORWAR | FREIGHT INSURA NCF | BASIC COST | TOTAL COST | . ERECTI | I NJS被算机 TOTAL |
|---|---------------------|------|-----------|---------|----------|------------|--------------|---|-------|-------|--|-------------------|-------------------|---------------------|-------------|-----------|-----------------|---------------------|------------------------|--------------------------|---------------|----------------|------------------|-------------------|
| | | | | | | | | W | S | Т | | k W | hours/d 15.0 | kWh/d 0.70 | | 8 | 12.36% 9=8 × | 12.50% 10=(8+9)× | 2.00% 11=8 × | 2.00% 12=8× | 13=SUM(8:12) | 14=13×TOTAL NO | 3.00% 15=14 × | Rs. × 16=14+1 |
| 7 THICKENED TRANSFERSLUDGE PUMP | Dia (mm) : 1 | 00 | Q(m3/h) : | 80 | H(m): | 15.00 | 11.00 | 2 | 2 | 4 | CI, submersible sludge pump with detachable device | 22.00 | 6.0 | 92.40 | 520,000 | 520,000 | 64,272 | 73,034 | 10,400 | 10,400 | 678,106 | 2,712,424 | 81,373 | 2,793,797 |
| AIR BLOWER FOR CENTRIFUGE FEED SUMP | Dia (mm) : 1 | 00 | Q(m3/h) : | 350 | P(K Pa) | 40 | 11.00 | 1 | 1 | 2 | Rotary lobe blower, Tri-lube type. Casing: CI, Lobes CI. With Acoustic Enclosures Noise Level:85dB at 1m DISTANCE | 11.00 | 12.0 | 92.40 | 220,000 | 220,000 | 27,192 | 30,899 | 4,400 | 4,400 | 286,891 | 573,782 | 17,213 | 590,995 |
| 9 CENTRIFUGE FEED PUMP | Dia (mm): 1 | 00 | Q(m3/h) : | 14 | H(m): | 20 | 5.50 | 2 | 1 | 3 | Progress Cavity Pump. Casing: CI, Rotor: SS316, Stator: NB. | 11.00 | 10.3 | 79.31 | 210,000 | 210,000 | 25,956 | 29,495 | 4,200 | 4,200 | 273,851 | 821,552 | 24,647 | 846,198 |
| 0 CENTRIFUGE | Q(m3/h): 1- | 1.00 | - | - | - | - . | 22.20 | 2 | 1 | 3 | Solid bowl type with Motor including a control panel. Wetted Parts SS304. Input TSS 0.8% w/w. Dewatered sludge TSS required 18%w/w at polymer dose | 44.40 | 10.3 | 320.12 | 3,600,000 | 3,600,000 | 444,960 | 505,620 | 72,000 | 72,000 | 4,694,580 | 14,083,740 | 422,512 | 14,508,25 |
| ELECTRIC HOIST | RL(T): 3 | .00 | L(m) : | 6.00 | | - | 8.60 | 1 | 0 | 1 | Single-girder overhead type. | 8.60 | 0.0 | 0.00 | 800,000 | 800,000 | 98,880 | 112,360 | 16,000 | 16,000 | 1,043,240 | 1,043,240 | 31,297 | 1,074,537 |
| MIXER FOR 2 POLYELECTROLYTE SOLUTION TANK | W (m): 1 | .50 | L(m) : | 2.00 | SWD(m) : | 2.00 | 1.50 | 2 | 0 | 2 | Agitator 100RPM,Slow Speed, SS304 | 3.00 | 2.0 | 4.20 | 90,000 | 90,000 | 11,124 | 12,641 | 1,800 | 1,800 | 117,365 | 234,729 | 7,042 | 241,771 |
| 3 DRY POLYELECTROLYTE FEEDER | Capacity (kg/h): 20 | 0.00 | | | | | 0.40 | 2 | 0 | 2 | Automatic feed system for batch—wise preparation and metering of polymer solutions from powdered. | 0.80 | 0.5 | 0.28 | 200,000 | 200,000 | 24,720 | 28,090 | 4,000 | 4,000 | 260,810 | 521,620 | 15,649 | 537,269 |
| 4 POLYELECTROLYTE DOSING PUMP | Dia (mm) : | 32 | Q(m3/h) : | 1.30 | H(m): | 20.00 | 0.75 | 2 | 1 | 3 | Progress Cavity Pump. Casing: CI, Rotor: SS316, Stator: NB. | 1.50 | 10.3 | 10.82 | 140,000 | 140,000 | 17,304 | 19,663 | 2,800 | 2,800 | 182,567 | 547,701 | 16,431 | 564,132 |
| 5 CENTRATE TRANSFER PUMP | Dia (mm): 1 | 00 | Q(m3/h): | 40 | H(m): | 15 | 5.50 | 2 | 1 | 3 | OI, Submersible Type with detachable device Efficiency >50% | 11.00 | 12.0 | 92.40 | 300,000 | 300,000 | 37,080 | 42,135 | 6,000 | 6,000 | 391,215 | 1,173,645 | 35,209 | 1,208,854 |
| | | | | | | | | | | TOTAL | • | 637.95 | | 9,650.08 | 28,980,000 | | | | | | | | | 98,790,26 |

Mechanical Cost for STPs (24MLD)

| MECHANICAL ITEMS | | SPEC | IFICATION | ı | | (k W/UNIT | NU | UMBER | | DESCRIPTION | CAPACITY | | cal power imptioon | NJS 被算単価 | BISIC | EXCISE | TAX/V | PACKING & FORWAR | T | BASIC | TOTAL COST | ERECTI NJS見積着 ON TOTAL | 頁 Tos |
|--|----------------------|--------------------------------------|-----------|-------------------------------|-------|--------------|----|-------|----|---|----------|-----------------|-----------------------|-------------|-----------|---------|---------|------------------------|---------------------------|--------------|-----------------|---------------------------|-------|
| | | | | | | W/UNIT_ | w | s | Т | | k W | hours/d 24.0 | kWh/d 0.70 | | 8 | 12.36% | 12.50% | 2.00% 11=8 × | 1NSURA 2.00% 12=8 × | 13=SUM(8:12) | 14=13×TOTAL NO. | 3.00% 15=14× 16=14+15 | 5 F |
| INLET GATE | W (m): 0.60 | L(m) : | 0.90 | Design Water Depth(m) : | 2.00 | - | 2 | 1 | 3 | Manually Sluice Gate, Wall Thimble:Cast Iron, Gate: cast iron, Frame: cast iron. floor=*********************************** | 0.00 | | | 270,000 | 270,000 | | 37,922 | 5,400 | 5,400 | 352,094 | 1,056,281 | 31,688 1,087,969 | 9 2,5 |
| FINE SCREEN (MECHANICAL) | W (m): 1.20 | L(m) : | 6.00 | SWD(m) : | 0.60 | 2.20 | 2 | 0 | 2 | Step Type Screen including control panel. Screen: SS316L Open space 6mm | 4.40 | 6.0 | 18.48 | 2,660,000 | 2,660,000 | 328,776 | 373,597 | 53,200 | 53,200 | 3,468,773 | 6,937,546 | 208,126 7,145,672 | 2 9,1 |
| FINE SCREEN (MANUAL) | W (m): 1.20 | L(m) : | 6.00 | SWD(m) : | 0.60 | - | 0 | 1 | 1 | Manually Bar Screen. Screen: SS316L Open space 20mm | 0.00 | | | 370,000 | 370,000 | 45,732 | 51,967 | 7,400 | 7,400 | 482,499 | 482,499 | 14,475 496,973 | 1,5 |
| BELT CONVEYOR | Beit Width (m): 0.60 | L(m) : | 9.00 | | - | 1.50 | 1 | 0 | 1 | Frame: MS+ Epoxy, Belt: NBR 3mm | 1.50 | 7.0 | 7.35 | 400,000 | 400,000 | 49,440 | 56,180 | 8,000 | 8,000 | 521,620 | 521,620 | 15,649 537,269 | |
| GRIT CHAMBER | W (m): 7.50 | L(m) : | 7.50 | SWD(m) : | 0.90 | 2.25 | 1 | 1 | 2 | DETRITOR MECHANIS including a grit collector, a classifier, an organic return pumpa, control panel. Wetted Parts : MS4Epoxy coated | 2.25 | 24.0 | 37.80 | 1,800,000 | 1,800,000 | 222,480 | 252,810 | 36,000 | 36,000 | 2,347,290 | 4,694,580 | 140,837 4,835,417 | 7 5, |
| NLET WEIR GATE | W (m): 0.80 | H(m) : | 0.40 | Stroke (m) : | 0.45 | - | 4 | 0 | 4 | Manually Sluice Weir, Wall Thimble:Cast Iron, Gate: cast iron, Frame: cast iron. floor+sesses bottom+sesses | 0.00 | | | 340,000 | 340,000 | 42,024 | 47,753 | 6,800 | 6,800 | 443,377 | 1,773,508 | 53,205 1,826,713 | 3 3, |
| MIXERS FOR ANAEROBIC TANK | W (m): 8.00 | L(m) : | 10.00 | SWD(m) : | 5.50 | 4.00 | 4 | 0 | 4 | Submersible Mixer. Ceaing: \$\$318L, Impeller: \$\$316L. | 16.00 | 24.0 | 268.80 | 750,000 | 750,000 | 92,700 | 105,338 | 15,000 | 15,000 | 978,038 | 3,912,150 | 117,365 4,029,515 | 5 18, |
| MIXERS FOR ANOXIC TANK | W (m): 8.00 | L(m) : | 10.00 | SWD(m) : | 5.50 | 4.00 | 12 | 0 | 12 | Submersible Mixer. Casing: \$\$316L, Impeller: \$\$316L. | 48.00 | 24.0 | 806.40 | 750,000 | 750,000 | 92,700 | 105,338 | 15,000 | 15,000 | 978,038 | 11,736,450 | 352,094 12,088,54 | 14 18 |
| DIFFUSER | SOR(kg/h) 262 | the setting depth of diffusers | 5.0 | Efficiency E(%) | 28.0 | - | 4 | 0 | 4 | Fine Bubble Membrane Type. | 0.00 | | | 3,000,000 | 3,000,000 | 370,800 | 421,350 | 60,000 | 60,000 | 3,912,150 | 15,648,600 | 469,458 16,118,05 | 8 5 |
| AIR BLOWER | Dia (mm): 250 | Q(m3/h) : | 4100 | P(K Pa) | 65 | 130.00 | 4 | 2 | 6 | Rotary lobe blower, Tri-lube type with VFD. Caeing: Cl. Lobes Cl. With Acoustic Enclosures Noise Level:85dB at 1m DISTANCE | 520.00 | 24.0 | 10529.18 | 900,000 | 900,000 | 111,240 | 126,405 | 18,000 | 18,000 | 1,173,645 | 7,041,870 | 211,256 7,253,126 | 8 10 |
| CIRCULATION PUMP | Dia (mm): 250 | Q(m3/h) : | 460 | H(m): | 5.00 | 15.00 | 8 | 4 | 12 | Submeraible studge pump with detachable device. Overall efficiency more than 60%. Casing: CI, Impeller SS ASTM A743, Guide/Lifting chain: SS316. | 120.00 | 24.0 | 2016.00 | 750,000 | 750,000 | 92,700 | 105,338 | 15,000 | 15,000 | 978,038 | 11,736,450 | 352,094 12,088,54 | 4 20 |
| RAS PUMP | Dia (mm): 150 | Q(m3/h) : | 150 | H(m): | 5.00 | 5.50 | 4 | 4 | 8 | Submeraible sludge pump with detachable device. Overall efficiency more than 60%. Casing: CI, Impelier SS ASTM A743, Quide/Lifting chain: SS316. | 22.00 | 24.0 | 369.60 | 400,000 | 400,000 | 49,440 | 56,180 | 8,000 | 8,000 | 521,620 | 4,172,980 | 125,189 4,298,149 | |
| SAS PUMP | Dia (mm): 100 | Q(m3/h) : | 65 | H(m): | 15.00 | 5.50 | 4 | 4 | 8 | Submeraible sludge pump with detachable device. Overall efficiency more than 60%. Casing: CI, Impelier SS ASTM A743, Guide/Lifting chain: SS316. | 22.00 | 6.0 | 92.40 | 300,000 | 300,000 | 37,080 | 42,135 | 6,000 | 6,000 | 391,215 | 3,129,720 | 93,892 3,223,612 | 2 3 |
| HAND OPERATION CHAIN BLOC FOR RAS/SAS PUMP | RL(T): 1.00 | L(m) : | 6.00 | | - | - | 6 | 0 | 6 | | 0.00 | | | 170,000 | 170,000 | 21,012 | 23,877 | 3,400 | 3,400 | 221,689 | 1,330,131 | 39,904 1,370,035 | 5 1 |
| FINAL CLARIFIER | Dia (m): 26.00 | L(m) : | - | SWD(m) : | 3.50 | 2.20 | 4 | 0 | 4 | Column-supported type including a centre drum, two scraper arms, a scum collector, a fixed bridge. MS+epoxy resin painting | 8.80 | 24.0 | 147.84 | 3,800,000 | 3,800,000 | 469,680 | 533,710 | 76,000 | 76,000 | 4,955,390 | 19,821,560 | 594,647 20,416,20 | 7 33 |
| ALUM DOSING PUMP | Dia (mm): 40 | Q(I/h) : | 410 | H(MPa): | 0.30 | 0.75 | 2 | 1 | 3 | Diaphragm Type. Casing: SS, Diaphragm: PTFE. | 1.50 | 24.0 | 25.20 | 100,000 | 100,000 | 12,360 | 14,045 | 2,000 | 2,000 | 130,405 | 391,215 | 11,736 402,951 | 1 |
| MIXERS FOR ALUM SOLUTION | W (m): 1.60 | L(m) : | 1.60 | SWD(m) : | 2.00 | 1.50 | 2 | 0 | 2 | Turbine impeller. SS316L | 3.00 | 2.0 | 4.20 | 80,000 | 80,000 | 9,888 | 11,236 | 1,600 | 1,600 | 104,324 | 208,648 | 6,259 214,907 | |
| CHLORINATOR | Q(kg/h): 23.0 | - | - | - | - | 0.10 | 1 | 1 | 2 | Gas Chlorinstion System including Vacuum Chlorinstors, Booster Pumps , Interconnecting Piping . Leak Detector, Residual Chlorine Analyses, Leak Absorption System ,Safety equipment and other accessories | 0.10 | 24.0 | 1.68 | 4,000,000 | 4,000,000 | 494,400 | 561,800 | 80,000 | 80,000 | 5,216,200 | 10,432,400 | 312,972 10,745,37 | 2 11, |
| CHLORINE BOOSTER PUMP | Dia (mm): 40 | Q(m3/h) : | 8.1 | H(m): | 50.00 | 3.70 | 1 | 1 | 2 | | 3.70 | 24.0 | 62.16 | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 0 | |
| CHLORINE TONNERS | - | | - | | - | - | 3 | 2 | 5 | | 0.00 | | | 150,000 | 150,000 | 18,540 | 21,068 | 3,000 | 3,000 | 195,608 | 978,038 | 29,341 1,007,379 | 9 1 |
| ELECTRIC HOIST CRANE | RL(T): 3.00 | L(m) : | 6.00 | | - | 8.60 | 1 | 0 | 1 | Single-girder overhead type. | 8.60 | 1.0 | 6.02 | 800,000 | 800,000 | 98,880 | 112,380 | 16,000 | 16,000 | 1,043,240 | 1,043,240 | 31,297 1,074,537 | 7 |
| MIXER FOR DECLORINE SOLUTION | Capacity(m3): 0.36 | | | | | 0.10 | 2 | 0 | 2 | Turbine Impeller. SS316L | 0.20 | 2.0 | 0.28 | 60,000 | 60,000 | 7,416 | 8,427 | 1,200 | 1,200 | 78,243 | 156,486 | 4,695 161,181 | |
| DECHLIRINE DOSING PUMP | Dia (mm): 15 | Q(I/h) : | 27 | H(MPa): | 0.30 | 0.20 | 2 | 1 | 3 | Diaphragm Type. Casing: SS, Diaphragm: PTFE. | 0.40 | 24.0 | 6.72 | 100,000 | 100,000 | 12,360 | 14,045 | 2,000 | 2,000 | 130,405 | 391,215 | 11,736 402,951 | 1 |
| AIR BLOWER FOR DECHLORINE MIXING TANK | Dia (mm) : 50 | Q(m3/h) : | 95 | P(K Pa) | 30 | 2.20 | 1 | 1 | 2 | Rotary lobe blower, Tri-lube type. Casing: CI, Lobes CI. With Acoustic Enclosures Noise Level:83dB at 1m DISTANCE Single-girder overhead type. | 2.20 | 24.0 | 36.96 | 140,000 | 140,000 | 17,304 | 19,663 | 2,800 | 2,800 | 182,567 | 365,134 | 10,954 376,088 | 1 |
| ELECTRIC HOIST FOR CHEMICALS | RL(T): 1.00 | L(m) : | 6.00 | | - | 4.70 | 1 | 0 | 1 | Bridge-supported type including a centre drum, two scraper arms, a soum | 4.70 | 1.0 | 3.29 | 500,000 | 500,000 | 61,800 | 70,225 | 10,000 | 10,000 | 652,025 | 652,025 | 19,561 671,586 | |
| SLUDGE THICKENER | Dia (m): 14.00 | L(m) : | - | SWD(m) : | 4.00 | 0.75 | 2 | 0 | 2 | Bridge-supporced type including a centre grum, two scraper arms, a soum collector, a fixed bridge. MS+epoxy resin painting | 1.50 | 24.0 | 25.20 | 2,200,000 | 2,200,000 | 271,920 | 308,990 | 44,000 | 44,000 | 2,868,910 | 5,737,820 | 172,135 5,909,955 | 5 6, |
| THICKENED TRANSFERSLUDGE PUMP | Dia (mm): 100 | Q(m3/h) : | 120 | H(m): | 15.00 | 15.00 | 2 | 2 | 4 | Cl, submersible sludge pump with detachable device | 30.00 | 6.0 | 126.00 | 450,000 | 450,000 | 55,620 | 63,203 | 9,000 | 9,000 | 586,823 | 2,347,290 | 70,419 2,417,709 | 9 2, |

Supporting Report

| engaluru | |
|----------|--|
| Water | |
| Supply | |
| and | |
| Sewerage | |
| Project | |

| MECHANICAL ITEMS | | | SPECI | FICATION | | | (k W/LINIT | | IUMBEF | ₹ | DESCRIPTION | ELECTRIC CAPACITY | | cal power imptioon | NJS 複算単価 | BISIC | EXCISE DUTY | TAX/V | PACKING & FORWAR | T | BASIC | TOTAL COST | ERECTI ON | NJS見積額 TOTAL | Toshiba 見積額 |
|--|-----------------|---------|-----------|----------|----------|-------|---------------|---|--------|-------|--|----------------------|-----------------|-----------------------|-------------|-----------|-------------|---------------------|------------------------|--------|----------------|----------------|--------------|-----------------|----------------|
| | | | | | | | | W | S | Т | | k W | hours/d 24.0 | kWh/d 0.70 | | | 12.36% | 12.50% 10+(8+8)× | 2.00% | 2.00% | 19-01114/0-19\ | 14=13×TOTAL NO | 3.00% | 16=14+15 | Rs. |
| AIR BLOWER FOR CENTRIFUGE FEED SUMP | Dia (mm) | 100 | Q(m3/h) : | 400 | P(K Pa) | 40 | 11.00 | 1 | 1 | 2 | Rotary lobe blower, Tri-lube type. Casing: CI, Lobes CI. With Acoustic Enclosures Noise Level:85dB at 1m DISTANCE | 11.00 | 12.0 | 92.40 | 500,000 | 500,000 | | 70,225 | 10,000 | 10,000 | 652,025 | 1,304,050 | | 1,343,172 | 1,926,000 |
| 29 CENTRIFUGE FEED PUMP | Dia (mm) : | : 125 | Q(m3/h) : | 25 | H(m): | 20 | 7.50 | 2 | 1 | 3 | Progress Cavity Pump. Casing: CI, Rotor: SS316, Stator: NB. | 15.00 | 10.3 | 108.15 | 550,000 | 550,000 | 67,980 | 77,248 | 11,000 | 11,000 | 717,228 | 2,151,683 | 64,550 | 2,216,233 | 2,079,000 |
| 30 CENTRIFUGE | Q(m3/h) : | 21.00 | - | - | - | - | 44.50 | 2 | 1 | 3 | Solid bowl type with Motor including a control panel. Wetted Parts SS304. Input TSS 0.8% w/w. Dewatered sludge TSS required 18%w/w at polymer dose | 89.00 | 10.3 | 641.69 | 4,000,000 | 4,000,000 | 494,400 | 561,800 | 80,000 | 80,000 | 5,216,200 | 15,648,600 | 469,458 | 16,118,058 | 16,200,00 |
| 31 ELECTRIC HOIST | RL(T) | 5.00 | L(m) : | 6.00 | | - | 17.10 | 1 | 0 | 1 | Single-girder overhead type. | 17.10 | 0.0 | 0.00 | 1,100,000 | 1,100,000 | 135,960 | 154,495 | 22,000 | 22,000 | 1,434,455 | 1,434,455 | 43,034 | 1,477,489 | 1,440,00 |
| MIXER FOR 32 POLYELECTROLYTE SOLUTION TANK | W (m) : | 2.00 | L(m) : | 2.00 | SWD(m) : | 2.50 | 2.20 | 2 | 0 | 2 | Agitator 100RPM,Slow Speed, SS304 | 4.40 | 2.0 | 6.16 | 120,000 | 120,000 | 14,832 | 16,854 | 2,400 | 2,400 | 156,486 | 312,972 | 9,389 | 322,361 | 900,000 |
| 33 DRY POLYELECTROLYTE FEEDER | Capacity (kg/h) | : 37.00 | | | | | 0.40 | 2 | 0 | 2 | Automatic feed system for betch—wise preparation and metering of polymer solutions from powdered. | 0.80 | 0.5 | 0.28 | 750,000 | 750,000 | 92,700 | 105,338 | 15,000 | 15,000 | 978,038 | 1,956,075 | 58,682 | 2,014,757 | 2,880,00 |
| 34 POLYELECTROLYTE DOSING PUMP | Dia (mm) : | : 40 | Q(m3/h) : | 1.90 | H(m): | 20.00 | 0.75 | 2 | 1 | 3 | Progress Cavity Pump. Casing: Cl, Rotor: SS316, Stator: NB. | 1.50 | 10.3 | 10.82 | 140,000 | 140,000 | 17,304 | 19,663 | 2,800 | 2,800 | 182,567 | 547,701 | 16,431 | 564,132 | 891,00 |
| 35 CENTRATE TRANSFER PUMP | Dia (mm) : | 100 | Q(m3/h) : | 40 | H(m): | 15 | 5.50 | 3 | 1 | 4 | CI, Submersible Type with detachable device Efficiency 50% | 16.50 | 12.0 | 138.60 | 300,000 | 300,000 | 37,080 | 42,135 | 6,000 | 6,000 | 391,215 | 1,564,860 | 46,946 | 1,611,806 | 594,00 |
| | | | | | | | | | | TOTAL | • | 976.15 | | 15589.66 | | | | | | | | | | 145,868,425 | 195,696,00 |
| | | | | | | | | | | | | kW | 1 | kWh/d | | | | | | | | | | INR | INR |
| | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | 1 | 1 | | | l | | | | | | | | | 1 |

| Capacity | Estim | ated cost INR | Unit cost Million INR/MLD | Reference |
|----------|-------------|------------------|---------------------------------|---------------------|
| 0.5MLD | 9,9 | 000,000 | 19.8 | DPR |
| 1.0MLD | 13, | 900,000 | 13.9 | DEK |
| 5MLD | 92,000,000 | Ave105.500.000 | 18.4 | StageIV |
| 5MLD | 119,000,000 | Ave103,300,000 | 23.8 | phase II (Except |
| 20MLD | 222 | ,000,000 | 11.1 | O&M) |

※1 92,000,000 ≒72,100,000 × 1.27
 ※2 119,000,000 ≒77,400,000 × 1.53

%3 222,000,000 ≒145,000,000 × 1.53

Cost Function

| MI | LD | | Million INR |
|-----|------|-----|-------------|
| x = | 0.5 | у = | 9.9 |
| x = | 1.0 | у = | 20.6 |
| x = | 1.5 | у = | 31.3 |
| x = | 2.0 | у = | 42.0 |
| x = | 2.5 | у = | 52.7 |
| x = | 3.0 | у = | 63.4 |
| x = | 3.5 | у = | 74.1 |
| x = | 4.0 | у = | 84.8 |
| x = | 4.5 | у = | 95.5 |
| x = | 5.0 | у = | 105.5 |
| x = | 6.0 | у = | 113.3 |
| x = | 7.0 | у = | 121.0 |
| x = | 8.0 | у = | 128.8 |
| x = | 9.0 | у = | 136.6 |
| x = | 10.0 | у = | 144.4 |
| x = | 11.0 | у = | 152.2 |
| x = | 12.0 | у = | 160.0 |
| x = | 13.0 | у = | 167.8 |
| x = | 14.0 | у = | 175.6 |
| x = | 15.0 | у = | 183.4 |
| x = | 16.0 | у = | 191.2 |
| x = | 17.0 | у = | 199.0 |
| x = | 18.0 | у = | 206.8 |
| x = | 19.0 | у = | 214.6 |
| x = | 20.0 | у = | 222.0 |

Construction Cost of ISPSs

| Zone | Package | Nome | of ISPS | | n Flow MLD) | Million INR |
|---------------|----------|------------------|------------------|----------------|----------------|-------------|
| Zone | 1 ackage | Name | 01 131 3 | JICA Surbey | DPR | JICA Surbey |
| Byatrayanpura | VB-U1 | Bellahalli | | 0.9 | 1.0 | 9.9 |
| Mahadevapura | VM-U2 | Hagadur | Changed from STP | 15.0 | - | 183.4 |
| Bommanahari | VBO-U3 | Naganathapura | Changed from STP | 9.0 | - | 136.6 |
| R.R Nagar | VRRN-U2 | Arehalli 1 | | 1.1 | 0.5 | 20.6 |
| K.K Nagai | VKKIN-UZ | Hemigepura | Changed from STP | 1.7 | - | 31.3 |
| Dasarahalli | VD-U2 | Herohalli | Changed from MP | 0.5 | 0.5 | 9.9 |
| Dasaranani | VD-02 | Daddabidarakallu | Changed from STP | 8.1 | - | 128.8 |
| | | Tota | | | | 520.5 |

NJS Consultants Co., Ltd.

Result of Stage IV hase II (Unit Cost for Construction of STPs and ISPSs)

| Proj | ect | | Items | Avg Initial Capacity | Treatment Process | Total HRT (at high level for SBR) | Direc | mated t Cost <1 | Estimated Cost ※2 | Awarded Cost ※2 | Estimated (SOR) Year | Awarded Year | Escalation for Estimated 5-2017 | Escalation for Awarded 6-2017 | Revised Estimated Cost 2017 | Revised Awarded Cost 2017 | Estimated Unit Direct cost MillionINR / MLD | Estimated Unit Direct cost MillionINR / MLD | Awarded Unit Direct cost MillionINR / MLD | NOTE 1 (Range of Capacity) | NOTE 2 | |
|----------|------|------|----------------------------|-------------------------|----------------------|--|-------|-----------------------|-------------------------|-----------------------|----------------------------|-----------------|--|--|--------------------------------------|------------------------------------|---|---|---|-------------------------------|-----------------------------|-----------------------------|
| | | | Raja canal | 40 MLD | EA | 23 hrs | 590 | | 3 | 7 | , | · · | , | Ů | 3-3-7 | 10-4-0 | 14.8 | 22.6 | 20.1 | | | |
| | | STP | Horamavu agara | 20 MLD | SBR | 34 hrs | 366 | 1 | 247.8 290.6 | | | | | | | | 18.3 | 28.0 | 24.9 | STP 20~40 MLD | | |
| | S1a1 | | Nagasandra | 20 MLD | SBR | 34 hrs | 342 | 1,521 | | 247.8 | 290.6 | 290.6 2010 | 2013 1.53 | 1.53 | 1.16 | 379.1 | 337.1 | 17.1 | 26.1 | 23.2 | | |
| | | | Horamavu agaraat Rajacanal | 20 MLD | - | _ | 145 | † | | | | | | | | | | 7.3 | 11.1 | 9.9 | ISPS 20 MLD | Not Include Pumping Main |
| | | ISPS | Karibuvanahalli | 5 MLD | - | _ | 77.4 | İ | | | | | | | | | 15.5 | 23.7 | 21.1 | ISPS 5 MLD | Not Include Pumping Main | |
| | S1a2 | STP | Kadugodi | 6 MLD | SBR | 37 hrs | 246 | 461 | 72.3 95.6 | OE e | 2010 2014 1.53 | 1 50 | 1.10 | 110.6 | 105.2 | 41.0 | 62.8 | 59.7 | STP 5~6 MLD | | | |
| Phase II | | SIP | Chika banavara | 5 MLD | SBR | 36 hrs | 214 | 401 | 72.3 | 95.0 | 2010 | 2014 | 1.53 | 1.10 | 110.6 | 105.2 | 42.9 | 65.6 | 62.4 | 215 2~0 MFD | | |
| Stage IV | S1a3 | STP | Kachohalli,(Agaram?) | 3 MLD | MBR | 23 hrs | | _ | _ | _ | | | | | _ | - | ı | - | | | | |
| | S1b | STP | Kengari | 60 MLD | AS w/o PG | 14 hrs | | - | | _ | | | | | _ | - | ı | - | | | | |
| | S1c | STP | K&C Valley | 60 MLD | AS with PG | 14 hrs | - | _ | _ | _ | | | | | _ | - | ı | 1 | | Expantion | | |
| | S1d | STP | Bellundor Amanikere | 90 MLD | AS w/o PG | 14 hrs | - | _ | _ | _ | | | | | _ | - | - | 1 | | | | |
| | | STP | Doddabela | 20 MLD | SBR | 34 hrs | 486 | | | | | | | | | | 24.3 | 30.8 | 27.3 | STP 15~20 MLD | | |
| | S1e | 011 | Yellemall-appa Chetty | 15 MLD | SBR | 35 hrs | 458 | 1,016 | 151.9 | 155.0 | 2012 | 2014 | 1.27 | 1.10 | 192.9 | 170.5 | 30.5 | 38.8 | 34.3 | 011 10 20 MLD | | |
| | | ISPS | Sadoramangala | 5 MLD | - | _ | 72.1 | | | | | | | | | | 14.4 | 18.3 | 16.2 | ISPS 5 MLD | Not Include Pumping Main | |

X1 Based on Excel Data obtained from BWSSB. In the Civil Cost, O & M Cost is not included and It is considered the defferance of HRT. (HRT of JICA-S = 25 hrs)

※2 Based on MONTHLY PROGRESS REPORT of Stage

▼ Phase II

Cost of ISPSs [Based on DPR]

| | | Capacit | ty(MLD) | INR (Crore) | | | |
|-----------------|---|---------|---------|-------------|-------------|-----------------------------|--|
| Area | Item | 2034 | 2049 | INK (Grore) | 2 /① | Note | |
| | | 1 | | 2 | | | |
| Byatarayanpura | Intermediate Sewage Pumping Station - Bellahalli | 1.00 | 1.55 | 13.9 | 13.9 | Not Include Pumping Main | |
| R R Nagar Total | ISPS (Arehalli −1) | 0.50 | 0.75 | 9.9 | 19.8 | Not Include Pumping Main | |
| Dasarahalli | Manhole Pump & Sump (IV. Herohallii-1477) | 0.50 | 0.75 | 6.2 | 12.4 | Manhole Pump | |

| | Price Escaration in India | | | | | | | |
|--------------|---------------------------|-------|--------|--------|---------------|--------|--------------|--|
| Base Year | escaratio n/Year | | 2010 | 2011 | 2012 | 2013 | 2014 | |
| 2009 | 10.61 | | | | | | | |
| 2010 | 9.50 | 1.000 | 1.000 | | | | | |
| 2011 | 9.54 | 1.095 | 1.095 | 1.000 | | | | |
| 2012 | 9.94 | 1.099 | 1.204 | 1.099 | 1.000 | | | |
| 2013 | 9.44 | 1.094 | 1.318 | 1.203 | 1.094 | 1.000 | | |
| 2014 | 5.93 | 1.059 | 1.396 | 1.275 | 1.159 | 1.059 | 1.00 | |
| 2015 | 4.91 | 1.049 | 1.465 | 1.337 | 1.216 | 1.111 | 1.04 | |
| 2016 | 2.00 | 1.020 | 1.494 | 1.364 | 1.241 | 1.134 | 1.07 | |
| 2017 | 2.00 | 1.020 | 1.524 | 1.391 | 1.265 | 1.156 | 1.09 | |
| | | | → 1.53 | → 1.40 | → 1.27 | → 1.16 | → 1.1 | |

ote: : http://www.globalnote.jp/p-cotime/
(Based on IMF Data)

Supporting Repo

Supporting Report 16

Financial and Economic Considerations

Chapter 16 FINANCIAL AND ECONOMIC CONSIDERATIONS 16.3 PRESENT PRACTICE FOR WATER AND SEWERAGE TARIFF

16.3.2 Study on Present Water and Sewerage Tariff

(1) Other Special Arrangement

The details of special sanitary charges are shown in Table 16.3.1 to Table 16.3.2

Table 16.3.1 Special Sanitary Charges for Domestic-Connection

Conditions of Domestic-Connection

INR.50 per month per individual house or per flat

Source: BWSSB

Table 16.3.2 Special Sanitary Charges for Non-Domestic-Connection

| Conditions of Non-Domestic Connection | Special Sanitary Charge (INR/month) | |
|---------------------------------------|--|----------|
| 1.Hotels | All Kinds of Hotels | 2,000 |
| | Darshini hotels, cafeteria and coffee bars | 1,000 |
| 2.Hotels with lodging facility | Up to 50 rooms | 2,000 |
| | 50 to 100 rooms | 4,000 |
| | more than 100 rooms | 10,000 |
| | Bar and Restaurant | 2,000 |
| 3.Star Hotels | Less than 50 rooms | 10,000 |
| | 51 to 100 rooms | 15,000 |
| | More than 100 rooms | 20,000 |
| 4.Hospitals | Without beds | 2,500 |
| | Up to 50 beds | 5,000 |
| | More than 50 and up to 100 | 7,500 |
| | More than 100 beds | 10,000 |
| | Dispensary, Clinic | 100 |
| 5.Hostels | Paying Guest accommodations | 2,000 |
| | Hostels with Non Domestic Water Supply | 2,000 |
| 6.Shopping Malls | Having theatres | 25,000 |
| | Without theatres | 5,000 |
| | Super Bazaars | 1,000 |
| 7.Multiplex, Theatres, Cinema halls | | 10,000 |
| 8.Community halls/ Kalyana Mantapas | With A.C | 7,500 |
| | Without A.C | 5,000 |
| 9.Choultries/Party halls | Less than 250 seats | 2,000 |
| <u> </u> | | <u> </u> |

The details of new connection charges are shown in Table 16.3.3 to Table 16.3.11

Table 16.3.3 Application form fee rate

| Application form fee rate |
|---------------------------|
| (INR/Application) |
| 100 |

Source: BWSSB.

Table 16.3.4 Attachment Fee for Pro Rata Charges

| 1. Pro Rata Charges | 2. Attachment Cost | | |
|---------------------------------------|------------------------|-------------------------|-------------|
| | Rate | Class of water supply | Rate |
| Class/Nature of Building | (INR/m ² of | connection | (INR/connec |
| | built up area) | connection | tion) |
| 1)Residential building | 150 | 1)15 mm & 20 mm dia | 25 |
| 2)Multi storeyed residential building | 200 | 2)25 mm up to 80 mm dia | 50 |
| 3)Fully owned buildings by Cen- | | | |
| tral/State Govt.(not applicable to | 240 | 3)100 mm & above dia | 100 |
| Govt undertakings organization) | | | |
| 4)Commercial Buildings | 300 | | |

Source: BWSSB

Table 16.3.5 Inspection Charges

| 1. Inspection Charge for Residential I | Buildings | 2. Inspection Charge for Commercial Buildings | | | |
|---|-------------------|---|-------------------|--|--|
| Decidential Duilding true | Charge | Built up area | Charge | | |
| Residential Building type | (INR/Application) | (m^2) | (INR/Application) | | |
| A)Domestic connections & temporary | | | | | |
| Non-Domestic connection for con- | 250 | 1)up to 100 | 500 | | |
| struction purpose | | | | | |
| B)Residential apartments: | | 2)101 up to 200 | 2,000 | | |
| 1)up to 50 apartments | 1,000 | 3)201 up to 400 | 4,000 | | |
| 2)50 and above up to & inclusive of | 2,000 | 4) from 101 | 5,000 | | |
| 100 apartments | 2,000 | 4)from 401 up | 5,000 | | |
| 3) for every increase of 100 apartments | Plus 1,000 | | | | |
| or part thereof of 100 apartments | Fius 1,000 | | | | |

Table 16.3.6 Three Months Minimum Deposit

| No. | Size | Rate for Non-Domestic Connection (INR) | Rate for Domestic Connection (INR) |
|-----|-----------|--|------------------------------------|
| 1 | 15 mm dia | 1,300/- for 10,000 ltrs | 315/- for 15,000 ltrs |
| 2 | 20 mm dia | 5,900/- for 40,000 ltrs | 1,800/- for 40,000 ltrs |
| 3 | 25 mm dia | 11,600/- for 70,000 ltrs | 4,300/- for 70,000 ltrs |
| 4 | 40 mm dia | 28,600/- for 1,50,000 ltrs | 14,500/- for 1,50,000 ltrs |
| 5 | 50 mm dia | 61000/- for 3,00,000 ltrs | 35,300/- for 3,00,000 ltrs |

Source: BWSSB

Table 16.3.7 Water Meter Cost (AMR)

| No | Cino | AMR Meter Cost |
|-----|--|----------------|
| No. | Size | (INR/Meter) |
| 1 | 15 mm multi jet mech meters with AMR facilities for Non Domestic | 37,200 |
| 2 | 20 mm multi jet mech meters with AMR facilities for Non Domestic | 43,800 |
| | 25 mm multi jet mech meters with AMR facilities for Domestic & Non | 50.400 |
| 3 | Domestic | 50,400 |
| | 40 mm multi jet mech meters with AMR facilities for Domestic & Non | 56 400 |
| 4 | Domestic | 56,400 |
| 5 | 50 mm electromagnetic AMR flow meters | 84,000 |
| 6 | 80 mm electromagnetic AMR flow meters | 96,000 |
| 7 | 100 mm electromagnetic AMR flow meters | 114,500 |
| 8 | 150 mm electromagnetic AMR flow meters | 133,000 |
| 9 | 200 mm electromagnetic AMR flow meters | 154,500 |
| 10 | 150 mm electromagnetic AMR flow meters | 133,000 |
| 11 | 200 mm electromagnetic AMR flow meters | 154,500 |

Source: BWSSB

Table 16.3.8 Water Meter Cost (Mechanical)

| No | Size | Mechanical Meter Cost for Domestic (INR./Meter) | Mechanical Meter Cost for Non-Domestic (INR./Meter) |
|----|--------------------|---|---|
| 1 | 1/2inch mech meter | 965 | 965 |
| 2 | 3/4inch mech meter | 2,250 | 2,250 |

Source: BWSSB

Table 16.3.9 Sanitary Point Charges

| Sanitary Point Charge Rate |
|----------------------------|
| (INR./point) |
| 120 |

Table 16.3.10 GBWASP Charges

| No. | Conditions | Total Charges | | |
|-----|--|----------------------------|--|--|
| NO. | Conditions | (INR.) | | |
| A | Residential SITES | | | |
| 1 | up to 600 sq. ft. | NIL | | |
| 2 | 600 to 1200 sq. ft. | 8,000/- per site | | |
| 3 | 1200 to 2400 sq. ft. | 16,000/- per site | | |
| 4 | up to 2400 sq. ft. & above | 24,000/- per site | | |
| В | Residential HOUSE/ FLAT | | | |
| 1 | up to 600 sq. ft. built up area (B.A) | 4,000/- per house or flat | | |
| 2 | 600 to 1200 sq. ft. B.A | 8,000/- per house or flat | | |
| 3 | 1200 to 2400 sq. ft. B.A | 16,000/- per house or flat | | |
| 4 | up to 2400 sq. ft. & above B.A | 24,000/-per house or flat | | |
| С | Educational Institutions / Hospitals / Nursing Homes, Charity etc., | 14/-per sft per B.A | | |
| D | Commercial Establishments / Shops etc., | 14/-per sft per B.A | | |
| Б | Office / Industries / Software & Hardware companies / BPOs/ Call Centers / | 11/ | | |
| Е | Convention Halls / Community Halls / Marriage Halls etc., | 11/-per sft per B.A | | |
| F | Hotels / Restaurants | 24/-per sft per B.A | | |

Table 16.3.11 Pro Rata Charges

| No. | Particulars | Conditions and Remarks | | Rates (INR.) |
|-----|--------------------------------|--------------------------------------|----|--|
| 1 | Residential build- | Up to 1,199 sq.ft. Sital area | 1. | Regular deposit and meter cost |
| | ing having base- | (Does not apply Pro Rata | 2. | Sanitary point charges at INR.120/-per point (minimum 5 |
| | ment, GF + 1st | charges up to 2 nd Floor) | | points per house) |
| | floor & 2 nd Floor | | 3. | Inspection charges at INR.250/-per building |
| 2 | Residential build- | For 1,200 sq.ft. sital area | 1. | INR.150/-per m ² on built area for both water supply con- |
| | ing having base- | (Does not attract Pro Rata | | nection & sanitary connection. |
| | ment, GF + 1st | charges up to 1st Floor) | 2. | Sanitary point charges at INR120/-per point (minimum 5 |
| | floor, 2 nd Floor & | | | points per house) |
| | additional floors | | 3. | Inspection charges at INR.250/-per building. |
| 3 | Residential build- | Above 1,200 sq.ft. sital area | 1. | Regular deposit and meter cost |
| | ing having base- | Does not apply Pro Rata | 2. | Sanitary point charges at INR.120/-per point (minimum 5 |
| | ment, GF + 1st | charges up to 1st Floor) | | points per house). |
| | Floor (a single | | 3. | Inspection charges at INR.250/-per building |
| | kitchen house | | | |
| | accommodation) | | | |
| 4 | Residential build- | Above 1,200 sq.ft. sital area | 1. | INR.150/-per m ² on built area for both water supply con- |
| | ing having base- | Attracts Pro Rata charges for | | nection & sanitary connection. |

| No. | Particulars | Conditions and Remarks | | Rates (INR.) |
|-----|---------------------|--------------------------------------|----|---|
| | ment, GF + 1st | 2 nd Floor & above floors | 2. | Sanitary point charges at INR.120/-point (minimum 5 |
| | Floor + additional | | | points per house) |
| | floors (a single / | | 3. | Inspection charges at INR.250/-per building. |
| | double kitchen | | | |
| | house accommo- | | | |
| | dation) | | | |
| 5 | Residential build- | For sital area of 2,400 sq.ft. | 1. | INR.150/-per sqmt on built area for both water supply |
| | ing having GF +1st | Attracts Pro Rata charges for | | connection & sanitary connection. |
| | floor + additional | 2 nd Floor & above floors | 2. | Sanitary point charges at INR.120/-point (minimum 5 |
| | floors(in the erst- | | | points per house) |
| | while 7 CMC & 1 | | 3. | Inspection charges at INR.250/-per building |
| | TMC areas) | | | |
| 6 | Residential mul- | Above 1,200 sq.ft. sital area | 1. | INR.200/-per sqmt on built area for both water supply |
| | tistoried building | Attracts Pro Rata charges for | | connection & sanitary connection. |
| | (having 3 & above | all floors inclusive of Base- | 2. | Sanitary point charges at INR.120/-per point (minimum 5 |
| | kitchen house | ment Floor (since it is con- | | points per house) |
| | accommodation) | sidered as an apartment) | 3. | Inspection charges at INR.1,000/-up to 50 flats |
| | Exclusively in the | | 4. | Inspection charges at INR.2,000/-from 51up to 100 flats |
| | jurisdiction of | | 5. | Inspection charges at INR.,3000/-from 101 up to 200 flats |
| | BBMP core area | | 6. | Inspection charges at INR.4,000/-from 201 up to 300 flats |
| | | | 7. | Inspection charges at INR.5,000/-from 301 up to 400 flats |
| | | | 8. | Inspection charges at INR.6,000/-from 401 up to 500 flats |
| | | | 9. | Inspection charges at INR.7,000/-from 501 up to 600 flats |
| 7 | Residential | Irrespective of sital area | 1. | INR.200/-per sqmt on built area for both water supply |
| | apartment | Attractive Pro Rata for the | | connection & sanitary connection. |
| | | entire built area inclusive of | 2. | Sanitary point charges at INR.120/-per point (minimum 5 |
| | | basement area | | points per house) |
| | | | 3. | Inspection charges at INR.1,000/-up to 50 flats |
| | | | 4. | Inspection charges at INR.,2000/-from 51upto 100 flats |
| | | | 5. | Inspection charges at INR.3,000/-from 101 up to 200 flats |
| | | | 6. | Inspection charges at INR.4,000/-from 201 up to 300 flats |
| | | | 7. | Inspection charges at INR.5,000/- from 301 up to 400 flat |
| | | | 8. | Inspection charges at INR.6,000/- from 401 up to 500 flat |
| | | | 9. | Inspection charges at INR.7,000/- from 501 up to 600flats |
| 8 | Government | Irrespective of sital area | 1. | INR.240/-per sqmt on built area for water supply connec- |
| | owned buildings | Attractive pro rate for the | | tion& sanitary connection. |
| | | entire built area inclusive of | 2. | Sanitary point charges at INR.120/-per point (minimum 5 |
| | | basement area | | point per house) |

| No. | Particulars | Conditions and Remarks | | Rates (INR.) |
|-----|-------------------|--------------------------------|----|--|
| | | | 3. | Inspection charges at INR.500/-up to 1000 sft built up |
| | | | | area |
| | | | 4. | INR.2,000/-up to 2,000 sft built up area |
| | | | 5. | INR.4,000/-up to 4,000 sft built up area |
| | | | 6. | INR.5,000/-above 4,000 sft built up area |
| 9 | Commercial | Irrespective of sital area | 1. | INR.300/-per sqmt on built area for water supply connec- |
| | buildings & Edu- | Attractive prorate for the | | tion& sanitary connection. |
| | cational Institu- | entire built area inclusive of | 2. | Sanitary point charges at INR.120/-per point (minimum |
| | tions | basement area | | 5point per house) |
| | | | 3. | Inspection charges at INR.500/-up to 1000 sft built up |
| | | | | area |
| | | | 4. | INR.2000/-up to 2000 sft built up area |
| | | | 5. | INR.4000/-up to 4000 sft built up area |
| | | | 6. | INR.5000/-above 4000 sft built up area |

Source: BWSSB

16.4 STUDY ON ALTERNATIVES FOR WATER AND SEWERAGE TARIFF 16.4.3 Study for the Number of Beneficiary

Beneficiaries to be served by the JICA Survey Project are shown in Table 16.4.1

Table 16.4.1 Population Projections for Water & Sewerage (Core + ULB + 110 Villages)

Unit: Person

| | | | Population | Projections for W | ater & Sewerage | (Core + ULB + 1 | 10 Villages) | | | Water+ Se | ewerage |
|------|-----------|-----------|-----------------------|-----------------------|-----------------------|---------------------------------------|---|--|-------------|----------------------------|-----------------------------|
| Year | Core Area | ULB | Service Population | Service Population | Service Population | Projected Connections for Water | 110 Villages - Service Population | Projected Connections for Sewerage | Avg HH Size | Total Households Served | Total Service Population |
| | | MLD | 1,827 | 367 | 1,460 | | 408 | | | | |
| 2016 | 5,636,817 | 2,440,189 | 8,077,006 | 1,622,475 | 6,454,531 | - | 1,429,293 | - | 4.00 | - | 9,506,299 |
| 2017 | 5,680,784 | 2,547,069 | 8,227,853 | 1,652,776 | 6,575,077 | - | 1,491,896 | - | 4.00 | - | 9,719,749 |
| 2018 | 5,725,094 | 2,658,631 | 8,383,725 | 1,684,087 | 6,699,638 | - | 1,557,241 | - | 4.00 | - | 9,940,966 |
| 2019 | 5,769,750 | 2,775,080 | 8,544,830 | 1,716,449 | 6,828,381 | - | 1,648,369 | - | 4.00 | - | 10,193,199 |
| 2020 | 5,814,754 | 2,879,146 | 8,693,900 | 1,746,394 | 6,947,506 | - | 1,720,568 | - | 4.00 | - | 10,414,467 |
| 2021 | 5,860,109 | 2,987,113 | 8,847,223 | 1,777,192 | 7,070,030 | - | 1,795,928 | - | 4.00 | - | 10,643,151 |
| 2022 | 5,905,818 | 3,099,130 | 9,004,948 | 1,808,876 | 7,196,072 | - | 1,874,590 | - | 4.00 | - | 10,879,538 |
| 2023 | 5,951,883 | 3,215,348 | 9,167,231 | 1,841,474 | 7,325,757 | 100% | 1,956,697 | 24% | 4.00 | 577,770 | 11,123,928 |
| 2024 | 5,998,307 | 3,376,559 | 9,374,866 | 1,883,183 | 7,491,683 | 100% | 2,003,593 | 37% | 4.00 | 656,128 | 11,378,459 |
| 2025 | 6,045,094 | 3,503,180 | 9,548,274 | 1,918,017 | 7,630,257 | 100% | 2,078,728 | 47% | 4.00 | 723,755 | 11,627,001 |
| 2026 | 6,092,246 | 3,634,549 | 9,726,795 | 1,953,877 | 7,772,918 | 100% | 2,156,680 | 57% | 4.00 | 795,796 | 11,883,475 |
| 2027 | 6,139,765 | 3,770,845 | 9,910,610 | 1,990,801 | 7,919,809 | 100% | 2,237,556 | 67% | 4.00 | 872,491 | 12,148,165 |
| 2028 | 6,187,655 | 3,912,251 | 10,099,907 | 2,028,826 | 8,071,080 | 100% | 2,321,464 | 77% | 4.00 | 954,088 | 12,421,371 |
| 2029 | 6,235,919 | 4,058,961 | 10,294,880 | 2,067,992 | 8,226,888 | 100% | 2,408,519 | 87% | 4.00 | 1,040,851 | 12,703,399 |
| 2030 | 6,284,559 | 4,211,172 | 10,495,731 | 2,108,338 | 8,387,393 | 100% | 2,498,838 | 92% | 4.00 | 1,101,817 | 12,994,569 |
| 2031 | 6,333,579 | 4,369,091 | 10,702,670 | 2,149,907 | | 100% | 2,592,545 | 95% | 4.00 | 1,153,206 | 13,295,214 |
| 2032 | 6,382,981 | 4,532,932 | 10,915,912 | 2,192,742 | 8,723,170 | 100% | 2,689,765 | 97% | 4.00 | 1,200,454 | 13,605,677 |
| 2033 | 6,432,768 | 4,702,917 | 11,135,685 | 2,236,889 | 8,898,796 | 100% | 2,790,631 | 99% | 4.00 | 1,249,903 | 13,926,316 |
| 2034 | 6,482,943 | 4,809,070 | 11,292,013 | 2,268,292 | 9,023,722 | 100% | 2,843,080 | 100% | 4.00 | 1,277,843 | 14,135,093 |
| 2035 | 6,533,510 | 4,965,365 | 11,498,875 | 2,309,845 | 9,189,030 | 100% | 2,935,480 | 100% | 4.00 | 1,311,331 | 14,434,355 |
| 2036 | 6,584,472 | 5,126,739 | 11,711,211 | 2,352,498 | 9,358,713 | 100% | 3,030,883 | 100% | 4.00 | 1,345,845 | 14,742,094 |
| 2037 | 6,635,831 | 5,293,358 | 11,929,189 | 2,396,285 | | 100% | 3,129,387 | 100% | 4.00 | 1,381,418 | 15,058,576 |
| 2038 | 6,687,590 | 5,465,392 | 12,152,982 | 2,441,239 | , , | 100% | 3,231,092 | 100% | 4.00 | 1,418,083 | 15,384,074 |
| 2039 | 6,739,753 | 5,643,018 | 12,382,771 | 2,487,398 | 9,895,372 | 100% | 3,336,102 | 100% | 4.00 | 1,455,875 | 15,718,873 |
| 2040 | 6,792,323 | 5,826,416 | 12,618,739 | 2,534,799 | 10,083,940 | 100% | 3,444,526 | 100% | 4.00 | 1,494,831 | 16,063,265 |
| 2041 | 6,845,303 | 6,015,774 | 12,861,078 | 2,583,479 | 10,277,599 | 100% | 3,556,473 | 100% | 4.00 | 1,534,988 | 16,417,551 |
| 2042 | 6,898,697 | 6,211,287 | 13,109,984 | 2,633,478 | , , | 100% | 3,672,058 | 100% | 4.00 | 1,576,384 | 16,782,042 |
| 2043 | 6,952,507 | 6,413,154 | 13,365,660 | 2,684,837 | 10,680,823 | 100% | 3,791,400 | 100% | 4.00 | 1,619,059 | 17,157,060 |
| 2044 | 7,006,736 | 6,621,581 | 13,628,317 | 2,737,599 | 10,890,719 | 100% | 3,914,621 | 100% | 4.00 | 1,663,055 | 17,542,938 |
| 2045 | 7,061,389 | 6,836,782 | 13,898,171 | 2,791,806 | , , | 100% | 4,041,846 | 100% | 4.00 | 1,708,413 | 17,940,017 |
| 2046 | 7,116,468 | 7,058,978 | 14,175,446 | 2,847,503 | , , | 100% | 4,173,206 | 100% | 4.00 | 1,755,177 | 18,348,651 |
| 2047 | 7,171,976 | 7,288,395 | 14,460,371 | 2,904,738 | 11,555,633 | 100% | 4,308,835 | 100% | 4.00 | 1,803,393 | 18,769,206 |
| 2048 | 7,227,917 | 7,525,268 | 14,753,185 | 2,963,557 | 11,789,628 | 100% | 4,448,872 | 100% | 4.00 | 1,853,107 | 19,202,057 |
| 2049 | 7,284,295 | 7,620,606 | 14,904,901 | 2,994,033 | 11,910,868 | 100% | 4,490,582 | 100% | 4.00 | 1,871,154 | 19,395,483 |

16.5 FINANCIAL ANALYSIS AND CONSIDERATIONS ON THE PROPOSED PROJECT 16.5.4 Financial Sensitivity

The detailed analysis is shown in Table 16.5.1 to Table 16.5.2.

Table 16.5.1 Sensitivity Analysis (Benefit Base)

Unit: Million INR.

| Cost in Total | Benefit in Total | | Cost in Total | Benefit in Total | | Cost in Total | Benefit in Total | |
|---------------|------------------|------------------|------------------|---------------------|------------------|---------------|------------------|------------------|
| Base | | | 5% | | _ | 10% | | |
| Total | Total | Cash Balance | Total | Total | Cash Balance | Total | Total | Cash Balance |
| 7,485 | 0 | -7,485 | 7,859 | 0 | -7,859 | 8,233 | 0 | -8,233 |
| 4,428 | 0 | -7,483 -4,428 | 4,649 | 0 | -7,839 -4,649 | 4,870 | 0 | -6,233 -4,870 |
| 2,001 | 0 | -2,001 | 2,102 | 0 | -2,102 | 2,202 | 0 | -2,202 |
| 23,524 | 0 | -23,524 | 24,700 | 0 | -24,700 | 25,876 | 0 | -25,876 |
| 15,665 | 0 | -15,665 | 16,449 | 0 | -16,449 | 17,232 | 0 | -17,232 |
| 15,912 | 0 | -15,912 | 16,708 | 0 | -16,708 | 17,503 | 0 | -17,503 |
| 7,774 | 6,183 | -1,591 | 8,162 | 6,183 | -1,980 | 8,551 | 6,183 | -2,368 |
| 4,518 | 6,183 | 1,664 | 4,744 | 6,183 | 1,439 | 4,970 | 6,183 | 1,213 |
| 2,782 | 6,183 | 3,401 | 2,921 | 6,183 | 3,261 | 3,060 | 6,183 | 3,122 |
| 2,816 | 6,183 | 3,366 | 2,957 | 6,183 | 3,225 | 3,098 | 6,183 | 3,085 |
| 2,862 | 6,183 | 3,321 | 3,005 | 6,183 | 3,178 | 3,148 | 6,183 | 3,035 |
| 2,907 | 6,183 | 3,276 | 3,052 | 6,183 | 3,131 | 3,197 | 6,183 | 2,985 |
| 2,952 | 6,183 | 3,231 | 3,099 | 6,183 | 3,083 | 3,247 | 6,183 | 2,936 |
| 2,974 | 6,183 | 3,208 | 3,123 | 6,183 | 3,059 | 3,272 | 6,183 | 2,911 |
| 2,988 | 6,183 | 3,195 | 3,137 | 6,183 | 3,045 | 3,287 | 6,183 | 2,896 |
| 2,997 | 6,183 | 3,186 | 3,147 | 6,183 | 3,036 | 3,297 | 6,183 | 2,886 |
| 3,006 | 6,183 | 3,177 | 3,156 | 6,183 | 3,026 | 3,307 | 6,183 | 2,876 |
| 3,011 | 6,183 | 3,172 | 3,161 | 6,183 | 3,022 | 3,312 | 6,183 | 2,871 |
| 3,011 | 6,183 | 3,172 | 3,161 | 6,183 | 3,022 | 3,312 | 6,183 | 2,871 |
| 3,011 | 6,183 | 3,172 | 3,161 | 6,183 | 3,022 | 3,312 | 6,183 | 2,871 |
| 3,011 | 6,183 | 3,172 | 3,161 | 6,183 | 3,022 | 3,312 | 6,183 | 2,871 |
| 4,513 | 6,183 | 1,670 | 4,738 | 6,183 | 1,444 | 4,964 | 6,183 | 1,219 |
| 4,513 | 6,183 | 1,670 | 4,738 | 6,183 | 1,444 | 4,964 | 6,183 | 1,219 |
| 3,011 | 6,183 | 3,172 | 3,161 | 6,183 | 3,022 | 3,312 | 6,183 | 2,871 |
| 3,011 | 6,183 | 3,172 | 3,161 | 6,183 | 3,022 | 3,312 | 6,183 | 2,871 |
| 3,011 | 6,183 | 3,172 | 3,161 | 6,183 | 3,022 | 3,312 | 6,183 | 2,871 |
| 3,011 | 6,183 | 3,172 | 3,161 | 6,183 | 3,022 | 3,312 | 6,183 | 2,871 |
| 3,011 | 6,183 | 3,172 | 3,161 | 6,183 | 3,022 | 3,312 | 6,183 | 2,871 |
| 3,011 | 6,183 | 3,172 | 3,161 | 6,183 | 3,022 | 3,312 | 6,183 | 2,871 |
| 3,011 | 6,183 | 3,172 | 3,161 | 6,183 | 3,022 | 3,312 | 6,183 | 2,871 |
| 149,732 | 148,383 | (1,350) | 157,219 | 148,383 | (8,836) | 164,706 | 148,383 | (16,323) |
| | | -0.13% | | | -0.85% | | | -1.54% |

Table 16.5.2 Sensitivity Analysis (Benefit-5%)

| Cost in | Benefit in | | Cost in | Benefit in | | Cost in | Benefit in | |
|---------|------------|-----------------|---------|------------|-----------------|---------|------------|-----------------|
| Total | Total | | Total | Total | | Total | Total | |
| Base | -5% | | 5% | -5% | | 10% | -5% | |
| Total | Total | Cash Balance | Total | Total | Cash Balance | Total | Total | Cash Balance |
| | | | | | | | | |
| 7,485 | 0 | -7,485 | 7,859 | 0 | -7,859 | 8,233 | 0 | -8,233 |
| 4,428 | 0 | -4,428 | 4,649 | 0 | -4,649 | 4,870 | 0 | -4,870 |
| 2,001 | 0 | -2,001 | 2,102 | 0 | -2,102 | 2,202 | 0 | -2,202 |
| 23,524 | 0 | -23,524 | 24,700 | 0 | -24,700 | 25,876 | 0 | -25,876 |
| 15,665 | 0 | -15,665 | 16,449 | 0 | -16,449 | 17,232 | 0 | -17,232 |
| 15,912 | 0 | -15,912 | 16,708 | 0 | -16,708 | 17,503 | 0 | -17,503 |
| 7,774 | 5,873 | -1,900 | 8,162 | 5,873 | -2,289 | 8,551 | 5,873 | -2,678 |
| 4,518 | 5,873 | 1,355 | 4,744 | 5,873 | 1,129 | 4,970 | 5,873 | 903 |
| 2,782 | 5,873 | 3,091 | 2,921 | 5,873 | 2,952 | 3,060 | 5,873 | 2,813 |
| 2,816 | 5,873 | 3,057 | 2,957 | 5,873 | 2,916 | 3,098 | 5,873 | 2,775 |
| 2,862 | 5,873 | 3,012 | 3,005 | 5,873 | 2,869 | 3,148 | 5,873 | 2,726 |
| 2,907 | 5,873 | 2,967 | 3,052 | 5,873 | 2,821 | 3,197 | 5,873 | 2,676 |
| 2,952 | 5,873 | 2,922 | 3,099 | 5,873 | 2,774 | 3,247 | 5,873 | 2,626 |
| 2,974 | 5,873 | 2,899 | 3,123 | 5,873 | 2,750 | 3,272 | 5,873 | 2,602 |
| 2,988 | 5,873 | 2,885 | 3,137 | 5,873 | 2,736 | 3,287 | 5,873 | 2,587 |
| 2,997 | 5,873 | 2,876 | 3,147 | 5,873 | 2,727 | 3,297 | 5,873 | 2,577 |
| 3,006 | 5,873 | 2,867 | 3,156 | 5,873 | 2,717 | 3,307 | 5,873 | 2,567 |
| 3,011 | 5,873 | 2,863 | 3,161 | 5,873 | 2,712 | 3,312 | 5,873 | 2,562 |
| 3,011 | 5,873 | 2,863 | 3,161 | 5,873 | 2,712 | 3,312 | 5,873 | 2,562 |
| 3,011 | 5,873 | 2,863 | 3,161 | 5,873 | 2,712 | 3,312 | 5,873 | 2,562 |
| 3,011 | 5,873 | 2,863 | 3,161 | 5,873 | 2,712 | 3,312 | 5,873 | 2,562 |
| 4,513 | 5,873 | 1,361 | 4,738 | 5,873 | 1,135 | 4,964 | 5,873 | 910 |
| 4,513 | 5,873 | 1,361 | 4,738 | 5,873 | 1,135 | 4,964 | 5,873 | 910 |
| 3,011 | 5,873 | 2,863 | 3,161 | 5,873 | 2,712 | 3,312 | 5,873 | 2,562 |
| 3,011 | 5,873 | 2,863 | 3,161 | 5,873 | 2,712 | 3,312 | 5,873 | 2,562 |
| 3,011 | 5,873 | 2,863 | 3,161 | 5,873 | 2,712 | 3,312 | 5,873 | 2,562 |
| 3,011 | 5,873 | 2,863 | 3,161 | 5,873 | 2,712 | 3,312 | 5,873 | 2,562 |
| 3,011 | 5,873 | 2,863 | 3,161 | 5,873 | 2,712 | 3,312 | 5,873 | 2,562 |
| 3,011 | 5,873 | 2,863 | 3,161 | 5,873 | 2,712 | 3,312 | 5,873 | 2,562 |
| 3,011 | 5,873 | 2,863 | 3,161 | 5,873 | 2,712 | 3,312 | 5,873 | 2,562 |
| 149,732 | 140,964 | (8,769) | 149,732 | 140,964 | (16,255) | 149,732 | 140,964 | (23,742) |
| | | -0.88% | | | -1.62% | | | -2.34% |

Table 16.5.3 Sensitivity Analysis (Benefit-10%)

| Cost in Total | Benefit in Total | | Cost in Total | Benefit in Total | | Cost in Total | Benefit in Total | |
|---------------|------------------|--------------|---------------|------------------|--------------|------------------|------------------|--------------|
| Base | -10% | | 5% | -10% | • | 10% | -10% | |
| Total | Total | Cash Balance | Total | Total | Cash Balance | Total | Total | Cash Balance |
| 7,485 | 0 | -7,485 | 7,859 | 0 | -7,859 | 8,233 | 0 | -8,233 |
| 4,428 | 0 | -4,428 | 4,649 | 0 | -4,649 | 4,870 | 0 | -4,870 |
| 2,001 | 0 | -2,001 | 2,102 | 0 | -2,102 | 2,202 | 0 | -2,202 |
| 23,524 | 0 | -23,524 | 24,700 | 0 | -24,700 | 25,876 | 0 | -25,876 |
| 15,665 | 0 | -15,665 | 16,449 | 0 | -16,449 | 17,232 | 0 | -17,232 |
| 15,912 | 0 | -15,912 | 16,708 | 0 | -16,708 | 17,503 | 0 | -17,503 |
| 7,774 | 5,564 | -2,209 | 8,162 | 5,564 | -2,598 | 8,551 | 5,564 | -2,987 |
| 4,518 | 5,564 | 1,046 | 4,744 | 5,564 | 820 | 4,970 | 5,564 | 594 |
| 2,782 | 5,564 | 2,782 | 2,921 | 5,564 | 2,643 | 3,060 | 5,564 | 2,504 |
| 2,816 | 5,564 | 2,748 | 2,957 | 5,564 | 2,607 | 3,098 | 5,564 | 2,466 |
| 2,862 | 5,564 | 2,703 | 3,005 | 5,564 | 2,560 | 3,148 | 5,564 | 2,417 |
| 2,907 | 5,564 | 2,658 | 3,052 | 5,564 | 2,512 | 3,197 | 5,564 | 2,367 |
| 2,952 | 5,564 | 2,612 | 3,099 | 5,564 | 2,465 | 3,247 | 5,564 | 2,317 |
| 2,974 | 5,564 | 2,590 | 3,123 | 5,564 | 2,441 | 3,272 | 5,564 | 2,292 |
| 2,988 | 5,564 | 2,576 | 3,137 | 5,564 | 2,427 | 3,287 | 5,564 | 2,278 |
| 2,997 | 5,564 | 2,567 | 3,147 | 5,564 | 2,417 | 3,297 | 5,564 | 2,268 |
| 3,006 | 5,564 | 2,558 | 3,156 | 5,564 | 2,408 | 3,307 | 5,564 | 2,258 |
| 3,011 | 5,564 | 2,554 | 3,161 | 5,564 | 2,403 | 3,312 | 5,564 | 2,253 |
| 3,011 | 5,564 | 2,554 | 3,161 | 5,564 | 2,403 | 3,312 | 5,564 | 2,253 |
| 3,011 | 5,564 | 2,554 | 3,161 | 5,564 | 2,403 | 3,312 | 5,564 | 2,253 |
| 3,011 | 5,564 | 2,554 | 3,161 | 5,564 | 2,403 | 3,312 | 5,564 | 2,253 |
| 4,513 | 5,564 | 1,052 | 4,738 | 5,564 | 826 | 4,964 | 5,564 | 601 |
| 4,513 | 5,564 | 1,052 | 4,738 | 5,564 | 826 | 4,964 | 5,564 | 601 |
| 3,011 | 5,564 | 2,554 | 3,161 | 5,564 | 2,403 | 3,312 | 5,564 | 2,253 |
| 3,011 | 5,564 | 2,554 | 3,161 | 5,564 | 2,403 | 3,312 | 5,564 | 2,253 |
| 3,011 | 5,564 | 2,554 | 3,161 | 5,564 | 2,403 | 3,312 | 5,564 | 2,253 |
| 3,011 | 5,564 | 2,554 | 3,161 | 5,564 | 2,403 | 3,312 | 5,564 | 2,253 |
| 3,011 | 5,564 | 2,554 | 3,161 | 5,564 | 2,403 | 3,312 | 5,564 | 2,253 |
| 3,011 | 5,564 | 2,554 | 3,161 | 5,564 | 2,403 | 3,312 | 5,564 | 2,253 |
| 3,011 | 5,564 | 2,554 | 3,161 | 5,564 | 2,403 | 3,312 | 5,564 | 2,253 |
| | | | | | | | | |
| 149,732 | 133,544 | (16,188) | 149,732 | 133,544 | (23,675) | 149,732 | 133,544 | (31,161) |
| | | -1.70% | | | -2.46% | | | -3.22% |

16.6 ECONOMIC ANALYSIS AND CONSIDERATIONS ON THE PROPOSED PROJECT

Table 16.6.1 shows population projections for water & sewerage services in 110 Villages.

Table 16.6.1 Population Projections for Water & Sewerage (110 Villages)

Unit: Number.

| Year | 110 villages HH |
|------|-----------------|
| 2016 | 357,323 |
| 2017 | 372,974 |
| 2018 | 389,310 |
| 2019 | 412,092 |
| 2020 | 430,142 |
| 2021 | 448,982 |
| 2022 | 468,648 |
| 2023 | 489,174 |
| 2024 | 500,898 |
| 2025 | 519,682 |
| 2026 | 539,170 |
| 2027 | 559,389 |
| 2028 | 580,366 |
| 2029 | 602,130 |
| 2030 | 624,710 |
| 2031 | 648,136 |
| 2032 | 672,441 |
| 2033 | 697,658 |
| 2034 | 710,770 |
| 2035 | 733,870 |
| 2036 | 757,721 |
| 2037 | 782,347 |
| 2038 | 807,773 |
| 2039 | 834,026 |
| 2040 | 861,131 |
| 2041 | 889,118 |
| 2042 | 918,015 |
| 2043 | 947,850 |
| 2044 | 978,655 |
| 2045 | 1,010,461 |
| 2046 | 1,043,301 |
| 2047 | 1,077,209 |
| 2048 | 1,112,218 |
| 2049 | 1,122,646 |

16.6.5 Economical Sensitivity

The detailed analysis is shown in Table 16.6.2 to Table 16.6.4

Table 16.6.2 Economic Sensitivity Analysis (Benefit: Base)

Unit: Million INR.

| | Cost in Total | Benefit in Total | | Cost in Total | Benefit in Total | | Cost in Total | Benefit in Total | milon ivk. |
|---|------------------|------------------|-------------------|-----------------|------------------|-------------------|-----------------|------------------|--------------------|
| | Base | | | 5% | | | 10% | | |
| | Total | Total | Cash Balance | Total | Total | Cash Balance | Total | Total | Cash Balance |
| | = 22 0 | | 7.22 0 | 7. 500 | | 5.500 | 7 051 | ^ | 7 074 |
| | 7,230 | 0 | -7,230 | 7,592 | 0 | -7,592 | 7,954 | 0 | -7,954 |
| | 4,277 | 0 | -4,277 | 4,491 | 0 | -4,491 | 4,705 | 0 | -4,705 |
| | 1,933 22,724 | 0 0 | -1,933 -22,724 | 2,030 23,860 | 0 | -2,030 -23,860 | 2,127 24,996 | 0 | -2,127 -24,996 |
| | 15,133 | 0 | -22,724 | 15,889 | 0 | -25,889 | 16,646 | 0 | -24,990 -16,646 |
| | 15,371 | 0 | -15,371 | 16,140 | 0 | -16,140 | 16,908 | 0 | -16,908 |
| | 7,359 | 25,142 | 17,783 | 7,727 | 25,142 | 17,415 | 8,095 | 25,142 | 17,047 |
| | 4,390 | 25,032 | 20,643 | 4,609 | 25,032 | 20,423 | 4,829 | 25,032 | 20,204 |
| | 2,529 | 25,026 | 22,497 | 2,655 | 25,026 | 22,371 | 2,782 | 25,026 | 22,245 |
| | 2,744 | 25,055 | 22,311 | 2,881 | 25,055 | 22,174 | 3,018 | 25,055 | 22,037 |
| | 2,787 | 25,086 | 22,299 | 2,926 | 25,086 | 22,160 | 3,066 | 25,086 | 22,020 |
| | 2,830 | 25,118 | 22,289 | 2,971 | 25,118 | 22,147 | 3,113 | 25,118 | 22,006 |
| | 2,872 | 25,153 | 22,280 | 3,016 | 25,153 | 22,137 | 3,160 | 25,153 | 21,993 |
| | 2,894 | 25,102 | 22,208 | 3,039 | 25,102 | 22,063 | 3,183 | 25,102 | 21,919 |
| | 2,907 | 25,088 | 22,181 | 3,052 | 25,088 | 22,036 | 3,197 | 25,088 | 21,890 |
| | 2,915 | 24,995 | 22,079 | 3,061 | 24,995 | 21,934 | 3,207 | 24,995 | 21,788 |
| | 2,924 | 25,009 | 22,085 | 3,070 | 25,009 | 21,938 | 3,216 | 25,009 | 21,792 |
| | 2,928 | 25,019 | 22,091 | 3,075 | 25,019 | 21,944 | 3,221 | 25,019 | 21,798 |
| | 2,928 | 25,025 | 22,097 | 3,075 | 25,025 | 21,951 | 3,221 | 25,025 | 21,804 |
| | 2,928 | 25,032 | 22,104 | 3,075 | 25,032 | 21,957 | 3,221 | 25,032 | 21,811 |
| | 2,928 | 25,038 | 22,110 | 3,075 | 25,038 | 21,964 | 3,221 | 25,038 | 21,818 |
| | 4,379 | 25,045 | 20,666 | 4,598 | 25,045 | 20,447 | 4,817 | 25,045 | 20,228 |
| | 4,379 | 25,053 | 20,674 | 4,598 | 25,053 | 20,455 | 4,817 | 25,053 | 20,236 |
| | 2,928 | 25,060 | 22,132 | 3,075 | 25,060 | 21,986 | 3,221 | 25,060 | 21,839 |
| | 2,928 | 25,068 | 22,140 | 3,075 | 25,068 | 21,993 | 3,221 | 25,068 | 21,847 |
| | 2,928 | 25,076 | 22,148 | 3,075 | 25,076 | 22,001 | 3,221 | 25,076 | 21,855 |
| | 2,928 | 25,084 | 22,156 | 3,075 | 25,084 | 22,009 | 3,221 | 25,084 | 21,863 |
| | 2,928 | 25,093 | 22,164 | 3,075 | 25,093 | 22,018 | 3,221 | 25,093 | 21,872 |
| | 2,928 | 25,101 | 22,173 | 3,075 | 25,101 | 22,027 | 3,221 | 25,101 | 21,880 |
| | 2,928 | 25,104 | 22,176 | 3,075 | 25,104 | 22,029 | 3,221 | 25,104 | 21,883 |
| | 127.556 | 0 | 0 | 144 424 | 0 | 457.160 | 151 212 | 0 | 450.201 |
| - | 137,556 | 601,603 | 464,047 | 144,434 | 601,603 | 457,169 | 151,312 | 601,603 | 450,291 |
| | | | 21.26% | | | 20.39% | | | 19.57% |

Table 16.6.3 Economic Sensitivity Analysis (Benefit-5%)

| | | | | | | | | VIIIIon INK. |
|---------|------------|-----------------|---------|------------|-----------------|---------|------------|-----------------|
| Cost in | Benefit in | | Cost in | Benefit in | | Cost in | Benefit in | |
| Total | Total | | Total | Total | | Total | Total | |
| Base | -5 % | | 5% | -5 % | | 10% | -5 % | |
| Total | Total | Cash Balance | Total | Total | Cash Balance | Total | Total | Cash Balance |
| 7,230 | 0 | -7,230 | 7,592 | 0 | -7,592 | 7,954 | 0 | -7,954 |
| 4,277 | 0 | -4,277 | 4,491 | 0 | -4,491 | 4,705 | 0 | -4,705 |
| 1,933 | 0 | -1,933 | 2,030 | 0 | -2,030 | 2,127 | 0 | -2,127 |
| 22,724 | 0 | -22,724 | 23,860 | 0 | -23,860 | 24,996 | 0 | -24,996 |
| 15,133 | 0 | -15,133 | 15,889 | 0 | -15,889 | 16,646 | 0 | -16,646 |
| 15,371 | 0 | -15,371 | 16,140 | 0 | -16,140 | 16,908 | 0 | -16,908 |
| 7,359 | 23,885 | 16,526 | 7,727 | 23,885 | 16,158 | 8,095 | 23,885 | 15,790 |
| 4,390 | 23,781 | 19,391 | 4,609 | 23,781 | 19,172 | 4,829 | 23,781 | 18,952 |
| 2,529 | 23,775 | 21,246 | 2,655 | 23,775 | 21,120 | 2,782 | 23,775 | 20,993 |
| 2,744 | 23,802 | 21,058 | 2,881 | 23,802 | 20,921 | 3,018 | 23,802 | 20,784 |
| 2,787 | 23,832 | 21,045 | 2,926 | 23,832 | 20,905 | 3,066 | 23,832 | 20,766 |
| 2,830 | 23,862 | 21,033 | 2,971 | 23,862 | 20,891 | 3,113 | 23,862 | 20,750 |
| 2,872 | 23,895 | 21,023 | 3,016 | 23,895 | 20,879 | 3,160 | 23,895 | 20,735 |
| 2,894 | 23,847 | 20,953 | 3,039 | 23,847 | 20,808 | 3,183 | 23,847 | 20,663 |
| 2,907 | 23,833 | 20,927 | 3,052 | 23,833 | 20,781 | 3,197 | 23,833 | 20,636 |
| 2,915 | 23,745 | 20,830 | 3,061 | 23,745 | 20,684 | 3,207 | 23,745 | 20,538 |
| 2,924 | 23,758 | 20,834 | 3,070 | 23,758 | 20,688 | 3,216 | 23,758 | 20,542 |
| 2,928 | 23,768 | 20,840 | 3,075 | 23,768 | 20,693 | 3,221 | 23,768 | 20,547 |
| 2,928 | 23,774 | 20,846 | 3,075 | 23,774 | 20,699 | 3,221 | 23,774 | 20,553 |
| 2,928 | 23,780 | 20,852 | 3,075 | 23,780 | 20,706 | 3,221 | 23,780 | 20,559 |
| 2,928 | 23,787 | 20,858 | 3,075 | 23,787 | 20,712 | 3,221 | 23,787 | 20,566 |
| 4,379 | 23,793 | 19,414 | 4,598 | 23,793 | 19,195 | 4,817 | 23,793 | 18,976 |
| 4,379 | 23,800 | 19,421 | 4,598 | 23,800 | 19,202 | 4,817 | 23,800 | 18,983 |
| 2,928 | 23,807 | 20,879 | 3,075 | 23,807 | 20,733 | 3,221 | 23,807 | 20,586 |
| 2,928 | 23,814 | 20,886 | 3,075 | 23,814 | 20,740 | 3,221 | 23,814 | 20,593 |
| 2,928 | 23,822 | 20,894 | 3,075 | 23,822 | 20,747 | 3,221 | 23,822 | 20,601 |
| 2,928 | 23,830 | 20,902 | 3,075 | 23,830 | 20,755 | 3,221 | 23,830 | 20,609 |
| 2,928 | 23,838 | 20,910 | 3,075 | 23,838 | 20,763 | 3,221 | 23,838 | 20,617 |
| 2,928 | 23,846 | 20,918 | 3,075 | 23,846 | 20,772 | 3,221 | 23,846 | 20,625 |
| 2,928 | 23,849 | 20,921 | 3,075 | 23,849 | 20,774 | 3,221 | 23,849 | 20,628 |
| 127.556 | 571.522 | 422.067 | 144 424 | 571.522 | 427.090 | 144 424 | 571.522 | 420.211 |
| 137,556 | 571,523 | 433,967 | 144,434 | 571,523 | 427,089 | 144,434 | 571,523 | 420,211 |
| | | 20.35% | | | 19.49% | | | 18.69% |

Table 16.6.4 Economic Sensitivity Analysis (Benefit-10%)

| | | | | | | | Unit: N | Million INR. |
|----------------|---------------------|------------------|------------------|------------------|------------------|------------------|---------------------|------------------|
| Cost in Total | Benefit in Total | | Cost in Total | Benefit in Total | | Cost in Total | Benefit in Total | |
| Base | -10 % | | 5% | -10 % | | 10% | -10 % | |
| | | | | | | | | |
| Total | Total | Cash Balance | Total | Total | Cash Balance | Total | Total | Cash Balance |
| | | | | | | | | |
| 7,230 | | -7,230 | 7,592 | 0 | -7,592 | 7,954 | 0 | -7,954 |
| 4,277 | | -4,277 | 4,491 | 0 | -4,491 | 4,705 | 0 | -4,705 |
| 1,933 | | -1,933 | 2,030 | 0 | -2,030 | 2,127 | 0 | -2,127 |
| 22,724 | | -22,724 | 23,860 | 0 | -23,860 | 24,996 | 0 | -24,996 |
| 15,133 | | -15,133 | 15,889 | 0 | -15,889 | 16,646 | 0 | -16,646 |
| 15,371 | | -15,371 | 16,140 | 0 | -16,140 | 16,908 | 0 | -16,908 |
| 7,359 | | 15,268 | 7,727 | 22,627 | 14,900 | 8,095 | 22,627 | 14,533 |
| 4,390 | | 18,139 | 4,609 | 22,529 | 17,920 | 4,829 | 22,529 | 17,701 |
| 2,529 | | 19,995 | 2,655 2,881 | 22,524 22,550 | 19,868 19,668 | 2,782 | 22,524 22,550 | 19,742 |
| 2,744 2,787 | | 19,806 | 2,881 | 22,530 | 19,668 | 3,018 3,066 | 22,530 | 19,531 19,512 |
| 2,787 | | 19,790 19,777 | 2,920 | 22,607 | 19,635 | 3,113 | 22,607 | 19,312 |
| 2,830 | | 19,777 | 3,016 | 22,637 | 19,633 | 3,113 | 22,637 | 19,494 |
| 2,894 | | 19,698 | 3,039 | 22,592 | 19,553 | 3,183 | 22,592 | 19,408 |
| 2,907 | | 19,672 | 3,052 | 22,579 | 19,527 | 3,197 | 22,579 | 19,382 |
| 2,915 | | 19,580 | 3,061 | 22,495 | 19,434 | 3,207 | 22,495 | 19,288 |
| 2,924 | | 19,584 | 3,070 | 22,508 | 19,438 | 3,216 | 22,508 | 19,291 |
| 2,928 | | 19,589 | 3,075 | 22,517 | 19,442 | 3,221 | 22,517 | 19,296 |
| 2,928 | | 19,594 | 3,075 | 22,523 | 19,448 | 3,221 | 22,523 | 19,302 |
| 2,928 | | 19,600 | 3,075 | 22,529 | 19,454 | 3,221 | 22,529 | 19,308 |
| 2,928 | | 19,606 | 3,075 | 22,535 | 19,460 | 3,221 | 22,535 | 19,314 |
| 4,379 | | 18,162 | 4,598 | 22,541 | 17,943 | 4,817 | 22,541 | 17,724 |
| 4,379 | | 18,168 | 4,598 | 22,547 | 17,949 | 4,817 | 22,547 | 17,730 |
| 2,928 | | 19,626 | 3,075 | 22,554 | 19,480 | 3,221 | 22,554 | 19,333 |
| 2,928 | 22,561 | 19,633 | 3,075 | 22,561 | 19,487 | 3,221 | 22,561 | 19,340 |
| 2,928 | 22,568 | 19,640 | 3,075 | 22,568 | 19,494 | 3,221 | 22,568 | 19,347 |
| 2,928 | 22,576 | 19,647 | 3,075 | 22,576 | 19,501 | 3,221 | 22,576 | 19,355 |
| 2,928 | 22,583 | 19,655 | 3,075 | 22,583 | 19,509 | 3,221 | 22,583 | 19,362 |
| 2,928 | 22,591 | 19,663 | 3,075 | 22,591 | 19,517 | 3,221 | 22,591 | 19,370 |
| 2,928 | 22,593 | 19,665 | 3,075 | 22,593 | 19,519 | 3,221 | 22,593 | 19,372 |
| (| | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 144,434 | 541,443 | 403,886 | 144,434 | 541,443 | 397,009 | 144,434 | 541,443 | 390,131 |
| | | 19.40% | | | 18.56% | | | 17.77% |

Supporting Report 17.1.1

Details of Service Stations with Number of Connections and Water Consumption

Supporting Report 17.1.1

Details of Service Stations with Number of Connections and Water Consumption

| Sl No. | SDID | Name of Service Station | No. of Connections | Consumption in ML |
|-----------|------|----------------------------|-----------------------|-------------------|
| 1 | C-1 | Banappa Park | 5,632 | 94.49 |
| 2 | C-1 | Chikkalalbagh | 8,403 | 126.12 |
| 3 | C-1 | L.L.R Station | 3,068 | 338.62 |
| 4 | C-1 | Sudhamanagar | 4,457 | 91.36 |
| 5 | C-2 | Coles Park | 6,671 | 299.50 |
| 6 | C-2 | H.G.R | 6,979 | 319.25 |
| 7 | C-3 | Frazer Town | 6,729 | 183.69 |
| 8 | C-3 | Machalibetta | 9,206 | 251.06 |
| 9 | C-3 | Pillanna Garden | 20,621 | 211.90 |
| 10 | E-1 | Banasawadi | 7,013 | 118.58 |
| 11 | E-1 | H.B.R | 10,153 | 170.30 |
| 12 | E-1 | H.R.B.R | 5,077 | 136.92 |
| 13 | E-1 | Lingarajapuram | 9,421 | 135.69 |
| 14 | E-1 | O.M.B.R | 4,516 | 100.41 |
| 15 | E-2 | AECS Layout | 5 | 1.07 |
| 16 | E-2 | AECS-1 | 6,840 | 169.72 |
| 17 | E-2 | AECS-2 | 2,545 | 101.07 |
| 18 | E-2 | Hoodi | 4,599 | 469.63 |
| 19 | E-3 | A.Narayanapura | 4 | 0.04 |
| 20 | E-3 | Devasandra Service Station | 3,578 | 53.35 |
| 21 | E-3 | K.R.Puram | 10,496 | 140.54 |
| 22 | E-3 | Ramamurthynagar | 10,058 | 249.76 |
| 23 | E-3 | Vijinapura Service Station | 4,711 | 65.49 |
| 24 | E-4 | A. Narayanapura | 5,647 | 115.57 |
| 25 | E-4 | HAL Airport | 6,039 | 125.72 |
| 26 | E-4 | Vignananagar | 7,121 | 183.32 |
| 27 | N-1 | Bahubali Nagar N-1 | 5,890 | 330.31 |
| 28 | N-1 | M.E.I Layout (DSH) | 13,857 | 242.57 |
| 29 | N-2 | Yelahanka New Town | 8,687 | 430.49 |
| 30 | N-2 | Yelahanka Old Town | 1,495 | 25.01 |
| 31 | N-3 | Jakkur | 8,231 | 191.92 |

| Sl No. | SDID | Name of Service Station | No. of Connections | Consumption in ML |
|-----------|------|------------------------------|-----------------------|-------------------|
| 32 | N-3 | Sahakara Nagar | 5,095 | 98.28 |
| 33 | N-3 | Vidyaranyapura | 14,198 | 234.06 |
| 34 | NE1 | Bhashym Park | 8,445 | 152.34 |
| 35 | NE1 | Malleswaram | 9,879 | 345.42 |
| 36 | NE1 | No Name | 1 | 0.00 |
| 37 | NE1 | SRIRAMPURAM | 5,546 | 136.08 |
| 38 | NE1 | YASHWANTHPURA | 14,881 | 306.82 |
| 39 | NE2 | JayaMahal | 6,140 | 238.40 |
| 40 | NE2 | K.G.Tower | 3,875 | 108.52 |
| 41 | NE2 | Kumara Park | 7,012 | 157.20 |
| 42 | NE3 | R.T.Nagar | 26,816 | 543.99 |
| 43 | NE3 | Sanjayanagar | 13,175 | 242.67 |
| 44 | NW1 | Kethmaranahalli | 6,265 | 164.00 |
| 45 | NW1 | Mahalakshmi Layout | 7,134 | 170.26 |
| 46 | NW1 | Nandini Layout | 13,846 | 321.74 |
| 47 | NW1 | Rajajinagar | 9,645 | 275.53 |
| 48 | NW1 | Yet to be assigned | 3 | 0.00 |
| 49 | NW2 | A.D.Halli | 5,216 | 142.73 |
| 50 | NW2 | Kamalanagar / Kamakshi Palya | 16,341 | 393.80 |
| 51 | NW2 | West Of Chord Road – I | 11,188 | 320.37 |
| 52 | NW2 | Yet to be Assigned | 1 | 0.00 |
| 53 | NW3 | Hegganahally | 17,994 | 383.06 |
| 54 | NW3 | Peenya | 17,828 | 360.13 |
| 55 | NW3 | Peenya Dasarahalli | 5,942 | 158.75 |
| 56 | S-1 | Banashankari-I | 5,277 | 135.90 |
| 57 | S-1 | Banashankari-II | 4,680 | 148.56 |
| 58 | S-1 | ISRO Layout | 5,448 | 100.36 |
| 59 | S-1 | Kumaraswamy Layout | 7,496 | 209.04 |
| 60 | S-1 | Poornapragna Layout | 7,195 | 215.18 |
| 61 | S-2 | KothnurDinne | 25,269 | 693.22 |
| 62 | S-2 | Vijayabank Layout S-2 | 9,043 | 333.28 |
| 63 | S-3 | B.T.M layout-1 | 13,970 | 427.64 |
| 64 | S-3 | B.T.Mlayout-2 | 7,129 | 249.70 |
| 65 | S-4 | HSR Layout | 13,865 | 463.67 |

| Sl No. | SDID | Name of Service Station | No. of Connections | Consumption in ML |
|-----------|------|-------------------------|-----------------------|-------------------|
| 66 | S-4 | KodiChikkanahalli | 11,897 | 418.92 |
| 67 | SE1 | CLR | 10,955 | 240.55 |
| 68 | SE1 | Domlur | 10,484 | 382.47 |
| 69 | SE1 | Jhonson Market | 11,789 | 255.17 |
| 70 | SE1 | Ulsoor | 8,406 | 307.19 |
| 71 | SE1 | Yet to be Assigned | 1 | 0.00 |
| 72 | SE2 | Bayappanahalli | 2,384 | 54.71 |
| 73 | SE2 | Bhuvaneshwari Nagar | 4,547 | 360.31 |
| 74 | SE2 | H.A.L | 4,224 | 130.55 |
| 75 | SE2 | Indiranagar | 4,264 | 85.71 |
| 76 | SE2 | Jeevan Bhimanagar | 7,789 | 158.80 |
| 77 | SE3 | Koramangala-1 | 7,281 | 319.76 |
| 78 | SE3 | Koramangala-2 | 7,374 | 202.61 |
| 79 | SE3 | Bellandur | 1,033 | 10.13 |
| 80 | SW1 | Chamarajpet | 10,652 | 227.48 |
| 81 | SW1 | JJNager | 10,668 | 188.15 |
| 82 | SW1 | K.G.Nagar | 3,666 | 81.17 |
| 83 | SW1 | V.V.Puram | 8,458 | 162.42 |
| 84 | SW2 | Devagiri-1 | 5,456 | 139.45 |
| 85 | SW2 | Devagiri-2 | 7,727 | 193.02 |
| 86 | SW2 | Giri Nagar | 5,836 | 134.00 |
| 87 | SW2 | Hosakerehalli | 6,824 | 146.48 |
| 88 | SW2 | Ittamadu | 4,010 | 97.86 |
| 89 | SW2 | Kathriguppa | 5,155 | 122.00 |
| 90 | SW3 | Girinagar SW3 | 1,899 | 35.74 |
| 91 | SW3 | M.N.K Park | 10,209 | 233.65 |
| 92 | SW3 | MountJoy | 9,375 | 223.59 |
| 93 | SW3 | Nagendra Block | 11,679 | 258.29 |
| 94 | SW3 | Yet to be assigned | 1 | 0.00 |
| 95 | SW4 | Byrasandra – I | 7,520 | 181.79 |
| 96 | SW4 | Hombegowda Nagara | 8,623 | 298.99 |
| 97 | SW4 | J.P.Nagar I Phase | 4,234 | 134.29 |
| 98 | SW4 | J.P.Nagar III Phase | 4,833 | 149.09 |
| 99 | SW4 | Jayanagar | 3,247 | 89.04 |

| Sl No. | SDID | Name of Service Station | No. of Connections | Consumption in ML |
|-----------|---|--------------------------|-----------------------|-------------------|
| 100 | SW4 | Jayanagar T – Block | 7,156 | 187.06 |
| 101 | W-1 | Hosahalli | 8,759 | 228.16 |
| 102 | W-1 | MagadiRoad | 12,061 | 206.59 |
| 103 | W-1 | Mysore Road | 68,52 | 154.55 |
| 104 | W-2 | Annapoorneshwari Nagara | 11,525 | 271.58 |
| 105 | W-2 | Nagarbhavi | 6,635 | 143.31 |
| 106 | W-2 | Sir M. Visveswaraiah – I | 1,868 | 31.73 |
| 107 | W-3 | Ideal Home (B E M L) | 5,236 | 110.75 |
| 108 | W-3 | Kengeri Satalite Town | 14,291 | 232.04 |
| 109 | W-3 | W-3-BEML Layout | 6,683 | 133.83 |
| 110 | W-4 | Chandra Layout | 20,703 | 522.18 |
| 111 | W-4 | Moodalapalya W-4 | 7,562 | 166.57 |
| 112 | W-4 | Vijayanagara OHT | 7,508 | 165.58 |
| | | Total | 872,926 | 22,281.48 |
| | There are 105 operational service stations out of a total of 112. The seven stations (Sl no. 15, 19, 36, 48, 52, 71 and 94) are yet to be made fully operational. | | | |

Supporting Report 17.1.2

Existing Staff Strength of BWSSB as on Jan 25, 2017

Supporting Report 17.1.2

Existing Staff Strength of BWSSB as on Jan 25, 2017 (Source: Personnel Officer, BWSSB)

| No. | Category of the Post | Sanctioned strength | In-position Strength | Vacant Positions |
|-----|--|---------------------|-------------------------|---------------------|
| | GROUP- 'A' | ~~~ ~ | 2 12 12 g | |
| 1 | Chairman | 1 | 1 | |
| 2 | Chief Administrative officer cum Secretary | 1 | 1 | |
| 3 | Project Director | 1 | 0 | 1 |
| 4 | Financial Advisor & Chief Accounts Officer | 1 | 1 | |
| 5 | Engineer in Chief | 1 | 0 | 1 |
| 6 | Chief Engineer | 4 | 2 | 2 |
| 7 | Additional Chief Engineer | 13 | 11 | 2 |
| 8 | Executive Engineer | 39 | 37 | 2 |
| 9 | Assistant Executive Engineer | 133 | 95 | 38 |
| 10 | Law Officer | 1 | 1 | |
| 11 | Personnel Manager | 1 | 0 | 1 |
| 12 | Administrative Officer | 1 | 0 | 1 |
| 13 | Public Relation Officer | 1 | 1 | |
| 14 | Accounts Officer | 8 | 6 | 2 |
| 15 | Asst. Labor Commissioner (Depu) | 1 | 0 | 1 |
| | Total | 207 | 155 | 52 |
| | GROUP- 'B' | | | |
| 1 | Assistant Personnel Manager | 1 | 0 | 1 |
| 2 | Asst. Welfare Officer | 1 | 0 | 1 |
| 3 | Medical Officer (Depu) | 1 | 0 | 1 |
| 4 | Asst. Law Officer | 1 | 1 | |
| 5 | Asst. Public Relation Officer | 1 | 0 | 1 |
| 6 | Sr. Labor Inspector | 1 | 0 | 1 |
| 7 | Asst. Accounts Officer | 14 | 13 | 1 |
| 8 | Asst. Engineer | 233 | 126 | 107 |
| 9 | Asst. Chemical Examiner | 1 | 0 | 1 |
| 10 | Asst. Stores Officer | 2 | 1 | 1 |
| 11 | Asst. Marketing Officer | 1 | 1 | |
| 12 | PS to Chairman | 1 | 1 | |
| 13 | Revenue Recovery Officer (Depu) | 1 | 0 | 1 |
| 14 | Accounts Superintendent | 50 | 48 | 2 |
| | Total | 309 | 191 | 118 |

| No. | Category of the Post | Sanctioned | In-position | Supporting Rep Vacant |
|------|--------------------------------|------------|-------------|--------------------------|
| 110. | | strength | Strength | Positions |
| | GROUP- 'C' | - | 50 | 22 |
| 1 | Junior Engineer | 82 | 59 | 23 |
| 2 | J. E. (Operation) | 12 | 11 | 1 |
| 3 | Draughtsman | 1 | 0 | 1 |
| 4 | Senior Manager | 14 | 10 | 4 |
| 5 | Superintendent | 45 | 28 | 17 |
| 6 | Superintendent (PRO) | 1 | 0 | 1 |
| 7 | Senior Personal Asst. | 4 | 3 | 1 |
| 8 | Junior Personal Asst. | 6 | 0 | 6 |
| 9 | Stenographer | 10 | 9 | 1 |
| 10 | Special Grade Typist cum DEO | 10 | 9 | 1 |
| 11 | Senior Typist cum DEO | 21 | 16 | 5 |
| 12 | Typist cum Data Entry Operator | 61 | 20 | 41 |
| 13 | Senior Assistant | 109 | 105 | 4 |
| 14 | Assistant | 167 | 108 | 59 |
| 15 | Junior Assistant | 275 | 164 | 111 |
| 16 | Stores Superintendent | 10 | 0 | 10 |
| 17 | First Division Storekeeper | 13 | 1 | 12 |
| 18 | Second Division Storekeeper | 19 | 6 | 13 |
| 20 | Telephone Operator (MR) | 6 | 2 | 4 |
| 21 | Special Grade Driver | 12 | 9 | 3 |
| 22 | Senior Driver | 20 | 14 | 6 |
| 23 | Driver | 74 | 43 | 31 |
| 24 | Senior Sanitary Inspector | 2 | 1 | 1 |
| 25 | Sanitary Inspector | 7 | 1 | 6 |
| 26 | Sanitary Overseer | 22 | 18 | 4 |
| 27 | Sanitary Mistry | 60 | 23 | 37 |
| 28 | Electrician Grade-I | 5 | 0 | 5 |
| 29 | Electrician Grade-II | 9 | 9 | |
| 30 | Sr. Work Inspector (MR) | 6 | 3 | 3 |
| 31 | Work Inspector (MR) | 14 | 0 | 14 |
| 32 | Water Analyst | 3 | 0 | 3 |
| 33 | Chemist-Grade-1 | 1 | 1 | |
| 34 | Chemist-Grade-2 | 3 | 3 | |
| 35 | Lab-Assistant Grade-1 | 6 | 2 | 4 |

| No. | Category of the Post | Sanctioned | In-position | Supporting Re Vacant |
|-----|------------------------|------------|-------------|-------------------------|
| | | strength | Strength | Positions |
| 36 | Lab-Assistant Grade-2 | 10 | 5 | 5 |
| 37 | Senior Operator | 17 | 17 | |
| 38 | Operator | 45 | 41 | 04 |
| 39 | Senior Water Inspector | 31 | 28 | 3 |
| 40 | Water Inspector | 150 | 141 | 9 |
| 41 | Meter Reader | 360 | 239 | 121 |
| 42 | Senior Jamedhar | 2 | 0 | 2 |
| 43 | Jamedhar | 4 | 1 | 3 |
| 44 | Senior Dafedar | 2 | 0 | 2 |
| 45 | Head Gardener | 3 | 1 | 2 |
| 46 | Senior Fitter | 60 | 1 | 59 |
| 47 | Fitter | 140 | 100 | 40 |
| 48 | Senior Cook | 1 | 1 | |
| | Total | 1,935 | 1,253 | 682 |
| | GROUP- 'D' | | | |
| 1 | Sr. Attendant | 25 | 16 | 17 |
| 2 | Jr. Attendant | 105 | 63 | 42 |
| 3 | Sr. Watchman | 31 | 4 | 27 |
| 4 | Watchman | 6 | 2 | 4 |
| 5 | Sanitary Worker | 250 | 133 | 117 |
| 6 | Dafedar | 1 | 0 | 1 |
| 7 | Sweeper | 50 | 28 | 22 |
| 8 | Gardener | 2 | 0 | 2 |
| 9 | Helper | 550 | 351 | 199 |
| 10 | Cook | 4 | 1 | 3 |
| 11 | Junior Helper | 25 | 6 | 19 |
| | Total | 1,049 | 604 | 445 |

ABSTRACT

| 1 | Group A | 207 | 155 | 52 |
|---|---------|-------|-------|------|
| 2 | Group B | 309 | 191 | 118 |
| 3 | Group C | 1,935 | 1,253 | 682 |
| 4 | Group D | 1049 | 604 | 445 |
| | Total | 3500 | 2203 | 1297 |