۰.

TECHNICAL NOTES

PREPARATORY SURVEY (FIELD SURVEY 1) ON

THE PROJECT FOR IMPROVEMENT OF PRIMARY AND SECONDARY SCHOOLS IN ULAANBAATAR CITY IN MONGOLIA

After signing of the Minuit of Discussions dated December 6, 2016, the Consultant's team (the Team) continued the field survey and had discussions on the technical matters of the Project with the Education Department of Ulaanbaatar City (UBC-ED). The followings are the points which are confirmed by both sides:

(1) Project Sites

1) Preliminary screening of the candidate sites

Based on the statistical and general information, the Team identified 7 sites to be excluded from the list (original list of 28 candidate sites which was submitted by UBC-ED during the official mission) in the light of the agreed criteria. The name of sites are as follows:

- Nalaikh No. 4 Khoroo : Permafrost soil is common in Nalaikh area
- Nalaikh Erdmin orgil C.S. : Ditto
- Nalaikh Terelj School : Ditto
- Chingeltei No. 112 School : Not a general school (religious school)
 - Songinokhairkhan
 No. 121 School
 : Not so much demand expected

 Bagakhangai
 No. 2 Khoroo
 : Canceled by UBC-ED
 - Baganur
 New residential area : Location of the site is uncertain

2) Result of site investigations

The Team visited all the existing schools and 3 new school sites in the revised list of 10 schools which was submitted at Dec. 8, 2016 by UBC-ED to JICA Mongolian Office, and made a preliminary evaluation on each site. The result of the evaluation is described in ANNEX I attached hereto.

After explanation of the result, the Team made a recommendation to UBC-ED to replace 3 sites which do not meet the minimum requirements with other candidates having positive evaluation.

 Selection of the site will be finalized after the field survey 2, among 10 candidate sites finally listed in the revised list.

(2) Basic Conditions for Facility Planning

Through the discussion, both sides confirmed the items shown on ANNEX II as basic conditions for facility planning. The Team will develop a schematic plan of the Project facilities based on the agreed conditions for further discussions during the field survey 2.

(3) Documents and Information to be submitted by Mongolian side

UBC-ED promised to submit the following documents and information requested by the Team by e-mail or other measures to the address below:

Tomohiro Osawa

50

osawa@matsucon.co.jp

 Breakdown of construction cost for recent construction project, such as School No.3, School and School No. 125.

END

Ulaanbaatar, December 13, 2016

Mr. J. Gantulge

Director, Education Department of Ulaanbaatar City Mongolia

lank

Mr. Tomohiro Osawa

Managing Director Matsuda Consultants International Co., Ltd.



ί.

ANNEX-I Preliminary Result of the site investigations

10 Sites with first priority selected by UBC Education Department

No.	District	Site	Request for:	Prelin	ninary evaluation
1	Chingeltei	No. 7 Khoroo	New school	0	The proposed land is moderately sloped and reclamation will be necessary for construction, located in the edge of ger area being not far from city center. Enough enrollment will be expected by the curren number of children who attend the kindergarten next to the site. No public utility is available beside electricity.
2	Khan-Uul	No. 75 School	Re-build after demolition of existing buildings	Δ	Demolition of existing building which were built in 1959, including its substructure, will be required to be done by the Mongolian side before the notice of tender for construction. Capital budget needs to be secured for the demolition work in the budget for FY2018.
3	Songinokhairkhan	No. 32 Khoroo	New school	0	The proposed land is located in the Khoroo at the west end of UBC. It will be good for establishmen of new school with sufficient flat land alongside the national road in spite of being far from the city center. High growth will be expected even though current population is not sufficient. No public utility is available besides electricity.
4	Khan-Uul	No. 10 Khoroo	New school	×	The proposed land occupies one of the plot in the new housing development area called "New Yarmag" where houses for 2,910 families are under development by the private investment company jointly funded by the Chinese bank. No inhabitant is in the area that means the planned school will be dedicated only for the development. It is not appropriate for Japan's Grant Aid. In addition, it is less likely to be filled with new inhabitants considering current economic situation in Mongolia.
5	Khan-Uul	No. 59 School	Transfer to the new plot by building a school with full-grades	Δ	The school's main building was built originally for a kindergarten and accommodates middle and high grades. Branch building was built for primary grades in the place approximately 3km from the main building this year as a complex with a kindergarten. The proposed land, just opposite to the curren plot, is far from the city center and no public utility is available besides electricity though it is flat with sufficient area. Careful analysis will be required for future enrollment considering the branch school.
6	Bayanzurkh	No. 53 School	Expansion	0	No major obstacle is expected.
7	Songinokhairkhan	No. 42 School	Expansion	0	Demolition of an existing building has been ordered by the specialized agency and will be required before the notice of the tender for the Project. Current enrollment is not so much in average but

.

1 . Ja

ANNEX I-1

~	~
X	16
Y	771
2	24

10

	54 				from the municipal network. Heating is supplied from the private boiler behind the school. The school has football court which is served for community use as well as for evacuation place.
17	Chingeltei	No. 112 School	Expansion	×	It is specialized religious school.
18	Songinokhairkhan	No. 29 Khoroo	New school		Not visited.
19	Songinokhairkhan	No. 121 School	Expansion	×	The school was built by Japan's Grant Aid and has enough classrooms for the target area.
21	Bagakhangai	No. 2 Khoroo	New school	×	Canceled by UBC-ED
22	Songinokhairkhan	No. 1 Khoroo	New school		Not visited.
25	Khan-Uul	No. 118 School	Expansion		The school was built by Japan's Grant Aid
26	Baganur	New residential area	New school	×	The request is based on future development of new housing zone. Under recent difficult condition of Mongolian economy, such a development will not likely be realized as planned.
27	Bayanzurkh	No. 14 Khoroo	New school		Not visited.
28	Songinokhairkhan	No. 28 Khoroo	New school		Not visited.

. . .

•

Recommendation:

In order to widen range of site selection at the time of the Field Survey 2, we recommend UBC Education Department to replace the following sites from the list of top 10 sites with the site of more positive evaluation.

1) Khan-Uul No. 10 Khoroo

2) Bayanzurkh Bayanzurkh C.S (Primary branch school).

3) Bayanzurkh No. 120 School

2					
					increasing rapidly. Private boiler system is available for heating. Special classroom for students wi disabilities had been in operation for 6 years, 3 years by World Vison's assistance and 3 years upor their parents' request, with 10 to 8 students.
8	Bayanzurkh	Bayanzurkh C.S (Primary branch school).	Re-build after demolition of existing buildings	×	The area of the school plot is approximately 2,600 sq.m, which is too small for a school building wi full grades, for example, the minimum type with full grades of standard design occupies more the 2,000 sq.m of land. Therefore, it is impossible to build a full grade school.
9	Chingeltei	No. 61 School	Expansion	Δ	The school's main building was built by Japan's Grant Aid (Phase III). Gym and kitchen/cafeteria bloo is under construction and will be opened next academic year. Only narrow space after demolition the old classrooms is available for construction.
10	Bayanzurkh	No. 120 School	Expansion	×	The school was established by Japan's Grant Aid Project (Phase IV). The plot is surrounded I residential lots some of them being inhabited, excluding the military compound in the north of the school. It is likely impossible to extend the land without resettlement.

1.1

5

Other 18 sites nominated in the original list

No.	District	Site	Request for:	Preli	minary evaluation
4	Songinokhairkhan	No. 7 Khoroo	New school		Not visited.
6	Bayangol	No. 1 Khoroo	New school		Not visited.
7	Nalaikh	No. 4 Khoroo	New school	×	In Nalaikh, construction of buildings needs special attention to permafrost soil which are common in
8	Nalaikh	Erdmin orgil C.S.		×	the area.
9	Nalaikh	Terelj School		×	
12	Bayangol	No.11/12 Khoroo	New school		Not visited.
13	Bayanzurkh	No. 21 School	Re-build after demolition of existing buildings	Δ	Demolition of existing building built in 1958 will be required to be done by the Mongolian side before the notice of tender for construction. Although the situation of overcrowding is serious with 3 sift classes in primary section, existing buried pipes makes construction difficult.
15	Sukhbaatar	No. 16 School	Expansion	Δ	One of the target for START project. Overcrowding is moderate. Main part of the existing building is single story so that it can make barrier-free condition easily. Space is available for expansion.
16	Chingeltei	No. 57 School	Expansion	\triangle	Overcrowding is moderate. Located in the middle of ger area, electricity, water, sewage is available

5

ANNEX-II Basic conditions for planning

1)	Standard size of a class	room: 35-40 students per classroom
	Size of a classroom:	56-60 sq.m

2) Number of classrooms

For new schools:	2 stream: 12 grades x 2 classes = 24 classrooms x 40=960 seats
or	2 stream for basic, 1 stream for high grades:
	9 grades x 2 + 3 grades x 1 21 classrooms x 40=840 seats
For expansion	basically new building will be designed to accommodate primary section

3) Components

Principle to design the project components:

To keep necessary function while pursuing efficiency as much as possible,

General classrooms

Special classrooms

- Following functions (activities) will be taken into account for designing special classrooms

Science laboratory for physics and chemistry

Technical subject for male and female students

Informatics and computer technology

Music room (to store music instruments)

* Preparation room will be attached to each of the room

Teachers' and staff's room

- Following rooms will be designed as a separate room:

Teachers' room

Education manager's office (for primary/secondary grades)

Social worker's office

- Doctor's office
- Principal's office

Accountant's office

Maintenance staff's room (cleaner, plumber, electrician, etc.)

Cloak

- Cloak is not necessary in case lockers for storing cloths are provided in each classroom

Gymnasium

Library

- Following functions will be taken into account for Library space

Librarian's work space

Book store

Reading space

ANNEX II·1

(100

Kitchen/Pantry and Cafeteria (Dining Hall)

- Following functions will be taken into account for kitchen and cafeteria

- To cook hot meals for primary students which will be served at each classroom
 - To cook and serve meals for teaching/supporting staff
 - To cook and serve light meals for secondary students
- Cafeteria is mainly designed for staff and students of upper grades (G9-G12)
- Kitchen and cafeteria will be designed to be outsourced to a private firm.
- UBC-ED may provide kitchen equipment as a apart of the recipient's work.

Other components to be taken into consideration:

- Children development center: the room may be designed as a place to develop each children's talents to provide individual guidance to their special needs under management by a social worker.
- The function to promote community's use of school facilities may be taken into consideration.
- 4) Principles for the outline design
 - Construction system

: External wall insulation system will be applied to external walling.

Stories

: Buildings will be designed with 4 stories and a basement for efficient use of the land.

Structural design

: Structural design will be in accordance with the revised standards and regulation in Mongolia which scheduled to be published at January, 2017.

5) Request from Mongolian side

UBC-ED requested following items to be considered in the facility design.

- To provide space for cultural and extra-curricular activities
- To improve acoustic environment of classrooms and gymnasium
- To follow UBC's policy of "ECO Buildings" to save the cost for maintenance by use of natural energy and/or reuse of resources.

ANNEX II · 2

TECHNICAL NOTES

PREPARATORY SURVEY (FIELD SURVEY 3) ON THE PROJECT FOR IMPROVEMENT OF PRIMARY AND SECONDARY SCHOOLS IN ULAANBAATAR CITY IN MONGOLIA

From April 10, 2017, the Consultant's team (the Team), to whom Japan International Cooperation Agency (JICA) entrusted implementation of a preparatory survey on the captioned project, has conducted the Field Survey 3 (the FS3) for the purpose of technical surveys on the candidate sites for the project and other incidental surveys including a series of discussions with concerned officials from the Education Department of Ulaanbaatar City (UBC). The followings are the points which are confirmed by both sides through discussions:

(1) Equipment

Items, quantities and specifications
 Mongolian side confirmed the items, their specifications and quantities to be distributed to
 each site, as listed in "ANNEX-1" attached hereto.

(2) Soft-component

 Outline of planned "soft-component" The Mongolian side basically agreed with the contents of the soft-component, explained by the Team. The outline of the component's plan is as attached in "ANNEX-2".

(3) Facility plan

The preliminary plan for outline design of the facilities was explained by the Team to UBC Education Department as well as other regulatory authorities. The followings are major instructions and/or requests which will be incorporated in the outline design:

- 1) Instructions by UBC Fire Department
 - Between the first basement floor and the first floor shall be a fireproof compartment, and fire doors must be installed for that staircase.
 - External escape stairs should be provided that can be accessed directly from the first basement floor to the first floor.
 - Smoke exhaust system should be provided.
- (4) Documents and Information to be submitted by Mongolian side

UBC Education Development promised to submit the following documents and information requested by the Team by e-mail or other measures to the address below by the end of April:

Tomohiro Osawa

osawa@matsucon.co.jp

- Land use permit and registration drawing for No. 75 school.
- Registration drawing for No. 53 school.

(E)

(5) Schedule of the Survey

After this Field Survey 3, the Team will continue to develop the outline design, to estimate the project cost, and prepare a draft Preparatory Survey Report by the end of August, 2017. The fourth survey mission to Mongolia will be dispatched around September, 2017 to explain the contents of the draft Preparatory Survey Report for finalizing the Survey with the consent of the Government of Mongolia.

END

E

Ulaanbaatar, April 25, 2017

Mr. J. Gantalga

Director, Education Department of Ulaanbaatar City Mongolia

Tatsuji Tsuchiya Mr. Tatsuji Tsuchiya

Assistant Chief Consultant The Preparatory Survey Team Matsuda Consultants International Co., Ltd.



ANNEX-1

Ð

		Sec. 12	Qty.		Type of	Facility	1	Qty.
Category	Item No.	Item Name	(per 1 room)	A-1	A-2	B-1	B-2	Total
rimary Education			100117		1111			
Mathematics	PRM- 01	Abacus for demonstrating	1	5	4	4	4	17
Tradition and the second	PRM- 02	Geometric block models set	18	90	72	72	72	306
	PRM- 03	Measurement set for students	18	90	72	72	72	306
	PRM- 04	Time teaching set	1	5	4	4	4	17
	PRM- 05	Abacus for students	18	90	72	72	72	306
	PRM- 06	Scales set for teacher	1	5	4	4	4	17
Mongolian	PRM- 07	CD Audio system	1	5	4	4	4	17
Language	100000							
Human	PRM- 08	Zoological Map and Botanical Map of Mongolia	1	5	4	4	4	17
Environment	PRM- 09	World Geographic Map	1	5	4	4	4	17
Common	PRM-10	Chess set for demonstrating	1	5	4	4	4	17
Equipment	PRM-11	Checker set for demonstrating	1	5	4	4	4	17
	PRM-12	Chess set for students	9	45	36	36	36	-
	PRM- 13	Checker set for students	9	45	36	36	36	153
Secondary Education			20	20	20	20	0	60
Equipment for	GYM-01	Hurdle	20	20	20	20	0	60 3
Gymnasium	GYM- 02	Traffic cone	1 9	1	9	9	0	3
	GYM-03	Basketball balls (Size 7)	9	9	9	9	0	27
	GYM-04 GYM-	Basketball balls (Size 6) Basket ball goal set	9	9	9	9	0	3
	GYM-05	Movable scoreboard	1	1	1	1	0	3
	GYM-06	Volleyball Balls	18	18	18	18	0	54
	GYM- 07	Volley ball pole set	1	1	1	1	0	3
	GYM-08	Volley ball net	6	1 6	1 6	1 6	0	3
	GYM-09 GYM-10	Gymnastics mat Ropes for tug-of-war	1	0	1	1	0	3
	GYM-11	CD Audio system	1	1	1	1	0	3
	GYM-	Wall Bars	1	1	1	1	0	3
	GYM-12	Futsal Balls	18	18	18	18	0	54
	GYM-13 GYM-14	Table tennis table set Table tennis racket	2 8	8	8	8	0	24
	GYM-15	Badminton Shuttle	18	18	18	18	0	54
	GYM-16	Badminton rackets	18	18	18	18	0	54
	GYM-17	Badminton pole set	1	1	1	1	0	3
	GYM-18	Badminton net	1	1	1	1	0	3
Mongolian			1	1	1	1	1	4
Language	MGL-01	CD Audio system	1	1	1	1	1	4
Foreign	FLG-01	CD Audio system	1	1	1	1	1	4
Language Physics Lab.	PHY-01	Experimental apparatus for dynamics	6	6	6	6	6	24
Equipment	PHY-02	Pulley set	6	6	6	6	6	24
Equipment	PHY-03	Mass with hanger	6	6	6	6	6	24
	PHY-04	Dynamics movement apparatus	6	6	6	6	6	24
	PHY-05	Spring set	6	6	6	6	6	24
	PHY-06	Photovoltaic experiment set	6	6	6	6	6	24
	PHY-07 PHY-08	Hand generator Air column resonance apparatus	6	6	0	0	0	4
	PHY- 09	Light for learning three primary colors of light	6	6	6	6	6	24
	PHY-10	Optical experiment set	1	1	1	1	1	4
	PHY-11	DC low voltage power supply	6	6	6	6	6	24
	PHY-12 PHY-13	Digital multi tester Slide rheostat	6	6	6	6	6	24
	PHY-13 PHY-14	Leads and crocodile clip	6	6	6	6	6	24
	PHY-14 PHY-15	Oscilloscope	1	1	1	1	1	4
	PHY-15 PHY-16	Magnet set	6	6	6	6	6	24
Chemistry Lab.	CHE-	Fune hood (Lab Ductless Fume Hood)	1	1	1	1	1	4
	CHE-01	Burette	12	12	12	12	12	48
Equipment	CHE- 01 CHE- 02	Retort stand set	12	12	12	12	12	48
	CHE-02	Watch glass	36	36	36	36	36	144
	CHE- 04	Molecular model set	6	6	6	6	6	24
	CHE-05	Bulb pipette with teat	36	36	36	36	36	144 144
	CHE- 06 CHE- 07	Measuring pipette Digital pH meter	36	36	36	36	36	48
	CHE- 07	Thermometer	12	12	12	12	12	48
	CHE- 09	Crucible Tongues	12	12	12	12	12	48
	CHE- 10	Crucible with lid	12	12	12	12	12	48
	CHE-11	Mortar set	12	12	12	12	12 12	48
	CHE- 12 CHE- 13	Evaporating basin Drying chamber	12	12	12	12	12	40
	CHE-14	Test tube set	1	1	1	1	1	4
	CHE- 15	Volumetric flask, 1000ml	6	6	6	6	6	24
	CHE- 16	Volumetric flask, 100ml	6	6	6	6	6	24
	CHE-17	Volumetric flask, 500ml	0	0	U	0	0	24

ANNEX-1

		T	Qty.		Type of	Facility		
Category	Item No.	Item Name	(per 1	A-1	A-2	B-1	B-2	
	CHE-19	Measuring cylinder, 50 ml	room) 6	6	6	6	6	-
	CHE- 20	Measuring cylinder, 100 ml	6	6	6	6	6	_
	CHE-21	Measuring cylinder, 500 ml	6	6	6	6	6	
	CHE- 22 CHE- 23	Centrifuge Beaker, 50ml	12	12	12	12	12	ŀ
	CHE-24	Beaker, 100ml	12	12	12	12	12	
	CHE-25	Beaker, 250ml	12	12	12	12	12	-
	CHE- 26 CHE- 27	Beaker, 500ml Conical beaker, 500ml	12	12	12	12	12	t
	CHE-28	Desiccator	1	1	1	1	1	
	CHE- 29	Electronic balance	1	1	1	1 12	1	-
	CHE- 30 CHE- 31	Conical flask (Erlenmeyer flask), 100ml Conical flask (Erlenmeyer flask), 300ml	12	12	12	12	12	⊢
	CHE-31 CHE-32	Funnel, caliber 75mm	12	12	12	12	12	ŀ
	CHE-33	Funnel, caliber 120mm	12	12	12	12	12	F
Biology Lab.	BIO-01	Compound microscope	18	18	18	18	18	
Equipment	BIO- 02	Hand lens	18	18	18	18	18	
	BIO-03	Water distiller	1	1	1	1	1	
	BIO-04	Water bath	1	1	1	1	1	
	BIO-05	Various thermometers	6	6	6	6	6	
	BIO-06	Dissecting kit	12	12	12	12	12	L
	BIO- 07	Petri dish	36	36	36	36	36	⊢
	BIO-08 BIO-09	Syringes set Immersion specimen	36	30	1	1	1	1
	BIO- 10	Anatomical model of human body	1	1	i	1	1	L
	BIO-11	Human skeleton	1	1	1	1	1	
	BIO- 12	Prepared slide set	1	1	1	1	1	
	BIO-13	Various specimens	1	1	1	1	1	_
	BIO- 14	Skeletal of vertebrate	1	1	1	1	1	1
	BIO-15	DNA model	1	1	1	1	1	-
	BIO-16 BIO-17	Human brain and head models Human eye model		1	1	1	1	-
	BIO-18	Human ear model	1	1	1	1	1	
	BIO- 19	Human teeth model	1	1	1	1	1	-
	BIO- 20 BIO- 21	Human heart model Lung model with larynx		$\frac{1}{1}$	1	1	1	1
Technology	BIO-21					1		
1 Sewing	WTE-01	Electric sewing machine	9	9	9	0	9	
0.000	WTE- 02	Over locker sewing machine	1	1	1	0	1	
	WTE- 03	Steam iron	2	2	2	0	2	
	WTE- 04	Ironing board	2	2	2	0	2	1
	WTE- 05	Shears for sewing	18	18	18	0	18	
	WTE- 06	Crochet hook set for knitting	18	18	18	0	18	
	WTE- 07	Embroidery frame	18	18	18	0	18	╞
② Metal work	MET- 01	Metal cutting saw	18	18	18	0	18	╞
	MET- 02	Vernier calliper	9	9	9	0	9	1
	MET- 03	Metallic file	9	9	9	0	9	-
l	MET- 04	Cold chisel for metalwork	9	9	9	0	9	-
	MET- 05	Center punch	9	9	9	0	9	-
	MET- 06	Pliers	9	9	9	0	9	+
	MET- 07	End Cutting Nippers	9	9	9	0	9	+
	MET- 08 MET- 09	Longnose pliers Vise	12	12	12	0	12	\uparrow
	MET- 10	Vise Soldering iron	9	9	9	0	9	t
	MET-10 MET-11	Digital multi tester	3	3	3	0	3	t
	MET-11 MET-12	Metal lathe	1	1	1	0	1	1
	MET-12	Grinder	1	1	1	0	1	T
	MET-14	Compressor airbrush set	1	1	1	0	1	
3 Wood work	WOD-01	Plane	9	9	9	0	9	Ι
	WOD- 02	Chisel set	9	9	9	0	9	F
	WOD- 03	Saw for woodwork	9	9	9	0	9	
	WOD-04	Wooden hammer	9	9	9	0	9	
l.	WOD-05	Clamp	6	6	6	0	6	L
	WOD- 06	Small axe	6	6	6	0	6	
	WOD- 07	Cross slot screwdriver	9	9	9	0	9	1
	WOD- 08	Tape measure	6	6	6	0	6	1
1	WOD- 09	Hammer	9	9	9	0	9	1
	WOD-10	Thicknesser (Planer)	1	1	1	0	1	+
	WOD-11	Drill press	1	1	1	0	1	+
	WOD-12	Wood lathe	1	1	1	0	1	+
	WOD-13	Scroll saw						



ANNEX-1

E

			Qty.		Type of	Facility		Qty.
Category	Item No.	Item Name	(per 1 room)	A-1	A-2	B-1	B-2	Total
	WOD-15	Electric drill	- 1	1	1	0	1	3
	WOD- 16	Power planer	1	1	1	0	1	3
	WOD-17	Orbit sander	1	1	1	0	1	3
	WOD- 18	Jig saw	1	1	1	0	1	3
	WOD- 19	Milling machine (Router)	1	1	1	0	1	3
	WOD- 20	Electric circular saw	1	1	1	0	_1	3
Fine Art	ART-01	Wood chisel	36	36	36	0	0	72
	ART-02	Clay scraper spatula	36	36	36	0	0	72
	ART- 03	Easel	36	36	36	0	0	72
	ART-04	Portable drawing board	36	36	36	0	0	72
Music	MUS-01	Smart board for music	1	1	1	0	0	2
	MUS-02	Stereo system	1	1	1	0	0	2
	MUS-03	Morin khuur	9	9	9	0	0	18
	MUS-04	Yatga 120cm	5	5	5	0	0	10
	MUS-05	Yatga 180cm	5	5	5	0	0	10
	MUS-06	Shanz 110cm	3	3	3	0	0	6
	MUS- 07	Shanz 140cm	3	3	3	0	0	6
	MUS- 08	Khuuchir	2	2	2	0	0	4
	MUS- 09	Flute (Bamboo)	1	1	1	0	0	2
	MUS-10	Flute (Iron)	1	1	1	0	0	2
	MUS-11	Yoochin	3	3	3	0	0	6
	MUS- 12	Electronic keyboard	1	1	1	0	0	2
	MUS-13	Keyboard harmonica	36	36	36	0	0	72
ICT	ICT-01	Desk top computer	37, 19	37	37	19	37	130
	ICT- 02	Complex type printer, monochrome	1	1	1	1	1	4
	ICT- 03	Switching hub 24 ports	1	1	1	1	1	4
Kitchen	KIT-	Electric Steam Oven, 8 level trays	1	1	1 2	0	0	2
Equipment	KIT- KIT-	Electric oven, 2 Comparments Electric 4-Hot plate Cooker with Oven	2	2	2	0	0	4
	KIT-	Electric Indirect Jacketed Boiling Pan	1	1	1	0	0	2
	KIT-	Electric Tilting Braising Pan	1	1	1	0	0	2
	KIT-	Electric Instant storage water heater /geyser	1	1	1	0	0	2
	KIT- KIT-	Electric Rice Cooker 4-Door Fan cooling reach-In Kitchen refrigerator	1	1	1	0	0	2
	KIT-	360L Single Door Upright Cooler	1	1	1	0	0	2
	KIT-	8kg Potato Peeler	1	1	1	0	0	2
	KIT-	Fruit and Vegetable Cutter	1	1	1	0	0	2
	KIT- KIT-	Mincer Chest Freezer	1	1	1	0	0	2
	KIT-	Dough Mixer	i	1	1	0	0	2
	KIT-	Electric sterilizer	1	1	1	1	1	4
	KIT-	700mm Triple Sinks Bench	1	1	1	1 0	1 0	4
	KIT- KIT-	700mm Single Sink Bench With Under Shelf 700mm Work Bench With Splashback	3,1	3	3	1	1	8
	KIT-	1.8m Work Bench With Slotted Undershelf	2	2	2	2	2	8
	KIT-	Water Filter Dispenser RO Purification System	1	1	1	1	1	4
	KIT-	Water Filter Dispenser RO Purification System	1	1	1	0	0	2
	KIT-	4-Layer Shelf	4,1	4	4	1	1	10
Equipment for	DOC-01	UV lam disinfection trolley	1	1	1	1	1	4
Medical office	DOC-02	Weight scale	1	1	1	1	1	4
	DOC-03	Height measuring scale	1	1	1	1	1	4
	DOC-04	Sphygmomanometer	1	1	1	1	1	4
	DOC- 05	Spirometer	1	1	1	1	1	4
Equipment for	CWD-01	Book stand (book holder)	5	5	5	5	5	20
CWDs	CWD-02	Desktop electronic magnifier for reading assistance	5	5	5	5	5	20
	CWD-	Partition wall	2	2	2	2	2	8
	CWD-	White board small	5	5	5	5	5	20
	CWD-	Cushion Chair	2	2	2	2	2	8
	CWD-03	Triangle Cushion	2	2	2	2	2	8
	CWD-04	Mat	2	2	2	2	2	8
Common	COM-01	Projector 1 (fixed)	2	2	2	2	2	8
Common	COM-02	Projector 2 (fixed)	1	1	1	0	0	2
	COM-02	Screen	1	1	1	0	0	2
	COM- 04	Sound equipment	1	1	1	0	0	2
	00111-04	Sound Alarkment	2	2	2	2	2	8

*1: These items are included in "Building work"

Preparatory Survey on the Project for Improvement of Primary and Secondary Schools in Ulaanbaatar City

Soft Component Plan

1. Background

This project aims at constructing quality schools, as models for new schools to be constructed by the Government of Mongolia (GoM) in future, with due consideration of children with disabilities (CWD) and the issue of Disaster Prevention based on principles of "universal design". To achieve such an aim, two prerequisite must be emphasized, i.e., 1) school staff should use the facilities properly and effectively according to its purpose, with full understanding on what the point of the design is and why it is adopted there, 2) the design, accompanying technical information, should be disseminated into persons who concern to improve physical school environment in Mongolia, by whom an element of the design may be introduced and materialized. This "soft component" is to assist the initial stage of dissemination to make sure that the project contribute to improvement of the quality in school construction in Mongolia.

2. Purpose of the Component

The purpose of the soft component is to improve educational environment by increase of quality schools with "consideration of disabilities" and "consideration of disaster prevention" in Mongolia.

3. Planned Activities

Activities of assistance by the soft component will be the following three (3) items:

1) To prepare and distribute the booklet and other material for publicity.

To compile the following publicity material as handouts of the seminars and guided tour of the new facilities. The material also will be used as tools for continuous activities for dissemination by the implementing agency in Mongolia:

- a. Booklet to introduce the points of universal designs incorporated in the facility design in view of "consideration of disabilities" and "consideration of disaster prevention". Items for school-level activities are to be distinguished.
 - Mongolian edition, printed and bound, approx. 40 pages
 - Japanese or English edition, simplified using photocopy, approx. 40 pages To be distributed to:
 - Concerned sections of MECSS, UBC Education Department,
 - Governmental organs responsible for construction, urban planning, disaster prevention and persons with disabilities,
 - Schools (Directors of public schools in Ulaabaatar),
 - Non-governmental organizations such as union for disables, parents, etc., and

A-94

- Private firms who are concerning to school constructions.
- b. Leaflet, a summary of the booklet, which gives more concise explanations for the public
 - Mongolian edition, in folio, 8 pages
 - Japanese or English edition, using photocopy, 8 pages
 - To be distributed to participants of the workshop, seminars and guided tours in addition to the above.
- c. Presentation slides for Powerpoint
- 2) Workshop to introduce the new facilities to the staff at the target schools

To hold a workshop for teachers at the target schools on how to use the new facility effectively upon sound comprehension of basic points of considerations.

- Participants: Directors, training managers, social workers and general teachers. Selected members (approx. 15 persons per school, i.e. 60 persons in total) will be invited
- Program: Introduction, presentation of the Project, lectures from the facility designers, session to experience completed facility and discussions (a half day for the whole program)
- Place: the art hall of the new school (A-1 type)
- 3) Seminar to introduce the new facilities to whom concerned to school construction

To hold the seminar for the persons concerned to school construction in Mongolia. Two seminars, which have the same program for a half day will be held one for persons in education sector and another for persons in construction sector as the target. The aim is to achieve wide recognition on the design and the function of the model which will be constructed by the Project focusing on "consideration of disabilities" and "consideration of disaster prevention." Tours guided by the project's consultants also will be planned.

- Participants: [For persons in education fields] Officials from MECSS/UBC Education Department, persons concerned to inclusive education and directors in the public schools, [For persons in building/construction fields] Officials in charge of construction and in charge of disaster prevention and private consulting firms having records of school construction.
- Program: Introduction, explanation of the Project, presentation by the facility designers, guided tours of the completed facility, presentation by a party related to person with disabilities and an officer in charge of disaster management (a half day for the whole program)
- Place: the art hall of the new school (A-1 type)

4. Implementation Schedule

Activity 1). 10 weeks for compiling, translating, printing and binding of material

Activity 2). and 3).2 weeks for preparation and implementation of seminars and a workshop

2

PREPARATORY SURVEY REPORT ON THE PROJECT FOR IMPROVEMENT OF PRIMARY AND SECONDARY EDUCATION FACILITIES IN ULAANBAATAR CITY

IN

MONGOLIA

SOFT COMPONET PLAN

AUGUST 2017

MATSUDA CONSULTANTS INTERNATIONAL CO., LTD.

KOEI RESEARCH & CONSULTING INC.

1. Background of Planning Soft Component

While Mongolia has already achieved high enrollment rates, the educational environments have been acutely deteriorating. This is primarily due to population growth accelerating in urban areas which continue to expand around the capital Ulaanbaatar city (UBC), and a resulting increase in the number of students there. To address this situation, the Government of Mongolia (GOM) has been working on a broader coverage of educational infrastructure that simultaneously offers quality learning environments. As the country recognizes shared needs to address inter-sectoral challenges, namely, specific accommodations for children with disabilities (CWD), disaster preparedness, and environmental friendliness, schools are now tasked with incorporating such functional considerations into their facilities.

Under these circumstances, the Project for Improvement of Primary and Secondary Education Facilities in Ulaanbaatar City (the Project) intends to build quality model schools applying universal design principles, which are accessible for CWD and prepared against natural disasters. These models call for GOM's adoption to its school construction projects in the future, which requires the following two-faceted endeavors;

- Key functional arrangements included in the architectural design and construction are understood correctly by administrators and staff in the target schools so that they use their facilities to meet the intended purposes; and,
- (2) The said arrangements accommodated in the facilities and actual benefits are acknowledged, together with technical know-how, among different groups of people involved in school construction in Mongolia. This should actuate their attempt to improve specific physical environments in their own schools, which will enhance the quality of educational settings as a whole.

Furthermore, in accordance with a request of GOM taking the Green Development initiative, the Project adopts energy-saving, resource-efficient solutions to make school facilities environmentally friendly, particularly cost-reducing in maintenance, which is crucial features to be mainstreamed in the future. Four types of models are thus proposed with the optimal building installations suitable for their sites having different sets of physical conditions and available utilities. Mongolia is developing guidelines to insulate school buildings and their mechanical systems, use energy-saving devices and renewable energy. The Project's models will put more values when they are able to show numerated differences resulting from its energy- and cost-saving strategies. To this end, the target schools should develop energy management schemes that employ measured data to help efficient heating operations.

Central to the main contributions of the Project, considerations for persons with disabilities or disaster preparedness have gained attentions recently in Mongolia as what should be addressed in the society. Relatively new for teachers and staff in general education schools, these issues are less familiarized among them, who will be managing and operating the facilities constructed by the Project. In term of making students with special needs accessible to education, all of the existing three target schools accommodate CWD in their regular classes. However, without allocating teachers specialized in inclusive education, these schools probably do not have as much knowledge and understanding as they should regarding how to instruct CWD. Their regular-class teachers thus need to obtain essential know-how and understand what each functional arrangement made in the Project's school facilities is intended and what benefits it delivers. This is critical for them to exercise and disseminate good practices in accessible education, using better-equipped learning settings. As for efforts to prepare against disaster risks, they are currently under the initiative of National Emergency Management Agency. School staff and other potential stakeholders do not always know about functions of schools expected in the event of natural disaster. Again, it is of vital importance that they should have essential disaster-related knowledge and understanding in order to respond appropriately to emergency situations, fully utilizing prepared resources. Environmental considerations involve building installations recently developed and applied in Mongolia. Obtaining enough benefits from them will require not only operational training on the systems, but also a deeper understanding of school staff on energy conservation. Technical staff should also learn about practical schemes to efficiently operate the building installations.

Although the above-mentioned thematic issues are acknowledged little by little in the Mongolian society, a core understanding is crucially lacking among engineers, municipal personnel, and school staff involved in school construction. Consequently, the building components are often missing the key elements of how they should be, for instance, ramps unclimbable with wheelchairs, and "accessible" toilets with the entrances allowing no wheelchair passage, eventually left disused. Similarly, people are generally less concerned with saving energy. Heated room temperature is adjusted by manually opening and closing windows, which is deemed wasting thermal energy. The Project will therefore exert on presenting coherent models that exemplify appropriate approaches to those problems. The soft component will be started with activities to foster thorough understanding of such approaches among school staff and other potential stakeholders, so that this leads to specific suggestion for other schools based on the benefits they feel.

It should be noted that the soft component will be implemented in partnership with JICA's ongoing technical cooperation known as the Project for Strengthening Teachers' Ability and Reasonable Treatments for Children with Disabilities (to be closed in July 2019). This is primarily for the sake of capacity development for staff of the target schools (including the Director, administrators, and teachers) who need basic know-how and understanding on inclusive education, which will require a longer period of time for training than a soft component timetable would allow.

2. Objective and Outputs of Soft Component

- Objective: Staff at the target schools (school staff) fully understand key features of their educational facilities and installations integrating disability-related accommodations, disaster preparedness, and environmental friendliness as well as regular methods of operations and maintenance of the school facilities. Such guiding models are shared among stakeholders in education so that they suggest applying the good practices to their own educational settings.
- Output 1: School staff understand purposes and benefits of universally designed facilities that incorporate disability-related accommodations and disaster preparedness.

- Output 2: Booklet is prepared and distributed as a tool that helps policy makers and school construction personnel to understand key features of functional arrangements and resultant benefits, which include universal design, disability-related accommodations, disaster preparedness, and environmental friendliness. Practical examples complied in the booklet are used in their education projects.
- Output 3: School staff learn effective energy-saving schemes that lower maintenance costs through their operations of building installations, and a set of such know-how is included in General Operation Manual.
- Output 4: Policy makers and school staff better understand energy conservation and energy efficiency schemes, learning from numerated differences obtained from energy-saving operations.

3. Means of Verification for the Achieved Outputs

- Output 1: With interviews with and a questionnaire for school staff, it is ensured or planned that new facility components will be used as intended, including Child Development Center, stockpile warehouse for emergency relief, node (conjunction space), and energy-saving heating system.
- Output 2: Booklet and other PR tools are prepared and distributed to relevant organizations to increase publicity of the quality schools equipped with functional arrangements. A questionnaire evaluates the degree of which recipients of the booklet, seminar participants, and on-site visitors deem the models are useful for their future work and services.
- Output 3: General Operation Manual is prepared to compile numerated energy-saving efficiency in the target schools and enabling schemes.
- Output 4: With interviews with and a questionnaire for participants after the verification seminar, it is ensured that they understand energy-saving operations leading to numerated benefits and that such operations will be continued on a long-term basis.

4. Activities in Soft Component (Input planning)

Soft component will include the following activities;

1) Providing school staff with a model case study that enables their hands-on understanding of the concepts underlying guiding practices (functional arrangements) in the target schools and how to use each function equipped:

2) Organizing a seminar on the purposes of functional arrangements and key technical features included in the target schools. Preparing a booklet as an illustrative aid during 1) and 2), which also serves as a regular tool to publicize the model schools in the seminar planned in 2): and,

3) Organizing a seminar on energy management schemes and practices for facility managers and operation staff in the target schools, together with quantitative evaluation on energy-saving efficiency.

The Project will support these publicity activities and verification of energy efficiency in which the implementing agency will be the lead organizer. There, the models are used to demonstrate how to apply the functional arrangements to school construction projects.

(1) Preparation and distribution of booklet

The following publicity materials will be prepared to carry out activities 1) and 2) mentioned above and to aid the implementing agency to run its continuous publicity and dissemination events on the model schools.

- a. Booklet (A collection of functional arrangements made in the Project's model schools, which features disability-related accommodations incorporating universal design, disaster preparedness, and environmental friendliness. This tool chiefly targets people who are involved in school construction) in Mongolian and Japanese or English
- Brochure (A simplified version of the booklet so as to prompt readers to understand highlights of the specific considerations given to the model schools. This tool chiefly targets teachers and people who are not much involved in building school facilities.) - in Mongolian and Japanese or English
- c. PowerPoint (PPT) slides for a presentation: in Mongolian and Japanese or English

Booklet and brochure in Mongolian will be printed and bound form, and Japanese or English counterpart, copied in color with simple binding. Including what the architect originally intended to achieve, the contents must be edited with involvement of the Mongolian side so as to foster their project ownership, for instance, putting comments from the implementing agency, and various groups and agencies working on the particular areas of issues addressed in the Project.

Description

[Target]

Distribution to MECSS ¹ , UBC ² -ED	20 copies
Distribution to organizations related to architecture and construction, persons with disabilities, and disaster prevention	30 copies
Distribution to directors of public schools in UBC	130 copies
Distribution to participants in on-site tours and PR seminars	120 copies+200 copies, 500 copies in total
	Distribution to organizations related to architecture and construction, persons with disabilities, and disaster prevention Distribution to directors of public schools in UBC Distribution to participants in on-site tours and

¹ Ministry of Education, Culture, Science and Sports

² Ulaanbaatar City

	The same number of copies are dis and reprinted, as required, with fina the Mongolian side	
c. PPT slides	Sending data to MECSS and UBC- subdivisions related to school cons projects	=
Structure of contents	5]	
a. Booklet		y components related to disability-related aredness, and environmental friendliness)
	• Universal design concept	
	Detailed functional arrangement	ts (1) (requiring relatively high costs)
	Detailed functional arrangement	tts (2) (requiring affordable costs for schools
	(Notes)	
	 Visual images are chief materia messages 	ls to help intuitive understanding of the key
	• Clear illustration of technical k are actually applied to the school	now-how and functional arrangements that ol facilities
	ownership of the soft-compone	volve the implementing agency to foster its nt implementation, for instance, by including by the State Secretary of MECSS.
b. Brochure	Briefly explain examples of con accommodations, disaster prepa	nsiderations given to disability-related aredness, and environment.
Implementation re	Contain pages each presenting	the four models
 Implementation re [Japanese consultant] Activities in Japan 	esources	the four models
[Japanese consultant]	esources	the four models 5 man-days (40p x 1h/p=40 hours)
[Japanese consultant] • Activities in Japan -Leader (Architectur	esources	
[Japanese consultant] • Activities in Japan -Leader (Architectur planning)	esources Collection of resource materials and editing of visual	5 man-days (40p x 1h/p=40 hours)
[Japanese consultant] • Activities in Japan -Leader (Architectur planning) -Building designer	esources Collection of resource materials and editing of visual images Preparation of a block copy and PPT slides	5 man-days (40p x 1h/p=40 hours) 10 man-days (40p x 2h/p=80 hours) 5 man-days (40p x 0.5h/p+0.5h/p=40 hours) rrsued by UBC-ED, the project implementer, ese resident engineer, and therefore no
[Japanese consultant] • Activities in Japan -Leader (Architectur planning) -Building designer -Editor	esources Collection of resource materials and editing of visual images Preparation of a block copy and PPT slides lia * Activities in Mongolia are pu under the supervision of Japan	5 man-days (40p x 1h/p=40 hours) 10 man-days (40p x 2h/p=80 hours) 5 man-days (40p x 0.5h/p+0.5h/p=40 hours) rrsued by UBC-ED, the project implementer, ese resident engineer, and therefore no
[Japanese consultant] • Activities in Japan -Leader (Architectur planning) -Building designer -Editor • Activities in Mongol	esources Collection of resource materials and editing of visual images Preparation of a block copy and PPT slides lia * Activities in Mongolia are pu under the supervision of Japan budget is allocated for Japanes Supervision of procurement	5 man-days (40p x 1h/p=40 hours) 10 man-days (40p x 2h/p=80 hours) 5 man-days (40p x 0.5h/p+0.5h/p=40 hours) rrsued by UBC-ED, the project implementer, ese resident engineer, and therefore no e consultant. (No project budget is allocated)
[Japanese consultant] • Activities in Japan -Leader (Architectur planning) -Building designer -Editor • Activities in Mongol	esources Collection of resource materials and editing of visual images Preparation of a block copy and PPT slides lia * Activities in Mongolia are pu under the supervision of Japan budget is allocated for Japanes Supervision of procurement and order placement Supervision of acceptance and	5 man-days (40p x 1h/p=40 hours) 10 man-days (40p x 2h/p=80 hours) 5 man-days (40p x 0.5h/p+0.5h/p=40 hours) rrsued by UBC-ED, the project implementer, ese resident engineer, and therefore no e consultant. (No project budget is allocated)
[Japanese consultant] • Activities in Japan -Leader (Architectur planning) -Building designer -Editor • Activities in Mongol -Resident engineer -	esources Collection of resource materials and editing of visual images Preparation of a block copy and PPT slides lia * Activities in Mongolia are pu under the supervision of Japan budget is allocated for Japanes Supervision of procurement and order placement Supervision of acceptance and distribution	5 man-days (40p x 1h/p=40 hours) 10 man-days (40p x 2h/p=80 hours) 5 man-days (40p x 0.5h/p+0.5h/p=40 hours) rrsued by UBC-ED, the project implementer, ese resident engineer, and therefore no e consultant. (No project budget is allocated)

	Contractor/Procurement	previously involved in projects of JICA or other international organizations)	
	Contracted services	 Booklet (in Mongolian) Adjusted A4-size, saddle-stitched, 40 p 500 copies in full color 	
		2) Booklet (in Japanese or English) Colored 30 copies with simple binding	
		3) Brochure (in Mongolian) A4-sized in folio, 8p 500 copies in full color	
		4) Brochure (in Japanese or English) Colored 30 copies in folio5) Printing envelops for distribution	
【Local resource】 Management of procurement and order placement: UBC-ED Acceptance and distribution: UBC-ED Distribution to organizations and personnel concerned: UBC-EI			

(2) Implementation of an on-site model case study (focusing on functional arrangements)

The following session will be organized so that administrators, teachers and other staff in the target schools will be able to operate their facilities effectively based on their basic and proper understandings of what all kinds of accommodations are to serve for. The session will be organized by UBC-ED implementing the Project, where participants learn at first hand various functions equipped in their school facilities.

·				
[Target]	Directors, Training Manag Workers, and teachers in th		A total of 60 people, 15 each from the target school	
[Structure of contents]	Envisioned contributions of the completed models		Japanese consultant on architectural design	
	• Universal design concep	t	Staff in the implementing agency	
	• Strategies to integrate di	•	Tool: PR brochure	
	accommodations, disaster preparedness, and environmental friendliness (energy conservation) into school facilities		Site tour participants: 20 people x 3 groups	
	• On-site briefing and disc	cussion		
[Venue and schedule]	Newly constructed school (tentatively A-1) -Lecture: Art Hall -Site tour: as designated		Half a day to cover a lecture and site tour	
Implementation resou	rce			
[Japanese consultant]				
Activities in Mongolia	ngolia Schedule applicable both to Activity (2)		ble both to Activity (2) and (3)	
-Leader (Architectural planning)	Training planner and manager, lecturer	10 man-days, trip to Mongolia (including Activity (3)) The trip also includes a completion inspection and thus is not allocated with		

Description

additional traveling expenses, except for 10-days

accommodations.

(Details)

		Coordination and schedule management (1day)
		On-site preparation and program check (1day
		Tutorial direction (MC), seminar direction (MC), site tour guide (6 days, of which 3 days are spent on the seminar and other tasks)
		Debrief and wrap-up (1 day)
		Day off (1day)
-Building design	MC and instructor	12 man-days, trip to Mongolia (including Activity(3))
		[Details]
		Travel (1 days)+coordination and schedule management (1 day)
		Direction of venue setting and coordination of presenters (1 day)
		Seminar presentation, attendance and presentation in the seminar, site tour guide (6 days, of which 3 days are spent on the seminar and other tasks)
		Debrief and wrap-up (1 day) + travel (1 day)
		Day off (1day)
[Local contractor]		- ` •/
Translator	From Japanese or	7 man-days x 1 person (including Activity (3))
	English to Mongolian	Translating the tutorial 1/2 day
[Local resource]	Main host, lead coordinator	UBC-ED
	Venue setting and preparation	School staff in the target schools

(3) Implementation of on-site model case seminar for school construction staff

The model schools are intended to be a catalyst for improving the quality of educational infrastructure through which functional arrangements are learned by potential stakeholders, and then adopted in future school construction projects in Mongolia. To this end, key features, including technical know-how, purposes and benefits, must become known to and understood by as many professionals involved in school construction as possible. It is also important for them to see actual facilities and learn directly examples of what desirable school environments should be as whole. As a part of supporting an initial stage of publicity activities regarding the model schools, the Project will distribute a booklet to various related organizations and personnel and organize a site tour of the completed facilities, open to the public, as well as a seminar inviting architects, users, and various stakeholders. The components of these events are planned as below.

The seminar will be held twice, each for a different group of participants. It should avoid a one-sided presentation style and must have remarks on how Mongolian participants (disability-related organizations and disaster-prevention administrators) evaluate the model schools. The seminar should be such an opportunity that the models will be broadly replicated across Mongolia to achieve quality educational settings. During activities mentioned in (2) and (3), the model facilities will be open to the public, allowing

wide-ranging groups of people to visit and look around. Including the Japanese architects, tour guides will be assigned to describe key design features and receive comments and ideas from visitors.

[Target] A total of 60 people per (1) Stakeholders in education: MECSS, UBC-ED administrators, officers in seminar x twice special needs education, and directors in public schools in UBC A total of 120 (2) Private-sector consultants involved in architecture and construction, school construction projects, and disasterprevention administrators [Structure of contents] • Site tour in the completed facilities (for 20 people at maximum x 3 to all participants) 4 groups Tool: PR booklet • Project brief (for all participants) · Key environmental consideration (energy conservation) (for all participants) Lecturers: · Key features of disability-related Japanese consultant on accommodations (1) architectural design • Evaluation of persons with disabilities (1) Representatives of disability-• Key features of disaster preparedness (2) related groups, disasterprevention administration, and · Evaluation of disaster-prevention manager MECSS/UBC-ED (2)• Discussion (for all participants) [Venue and schedule] Newly constructed school (tentatively A-1) 2 days (for the seminar) -Lecture: Art Hall 6 days (for the site tour) -Site tour: as designated

Implementation resources

[Japanese consultant]

Description

•		
Activities in Japan		
-Leader (Architectural planning)	Training planner and manager, lecturer	(Included in Activity (2))
-Building design	MC and lecturer	Same as above
[Local contract]		
Translator	From Japanese or English to Mongolian	Translating the seminar $1/2 \text{ day x } 2 \text{ days}$
[Local resource]	Main host, lead coordinator	UBC-Ed
	Venue setting and preparation	School staff in the target schools
	Lecturer	Representatives of local disability-related groups and (school) disaster-prevention administration

(4) Implementation of on-site energy management training in the target schools

Facility managers in the target schools are expected to learn and practice energy-efficient heating operations based on measured data. This should lead to creating good practices in energy management suitable for different heat sources, and eventually reducing maintenance costs. The first step is to foster understanding of school staff on energy conservation and management, and to provide hands-on learning on procedures and schemes required for actual heating system operations. It specifically involves: 1) a group seminar highlighting energy conservation and management, and 2) an on-site training using completed systems. The latter contains three major components: common items applicable to all heat sources and systems provided, system-specific items, and hands-on system operations. This training will focus on practical learning, targeting facility operators in the target schools. The group seminar will include participants from policy makers and school facility managers involved in school construction so that they become keen about reducing maintenance costs and saving energy.

Description

[Target]	 Directors in the target schools Facility managers and operators Administrators involved in school construction 	
[Structure of contents]	[Group seminar] (1)+(2)+(3)	
	• Envisioned contributions of the completed models	Japanese expert on energy management
	 Energy-saving strategies planned in the Project 	
	 Energy management schemes and institutionalization 	Tool: General Operation Manual
	[On-site training] $(1) + (2)$	
	• Control scheme of heating water ; e.g. adjusted to the differences between the external and internal temperatures, and those between the ground and upper levels	
[Venue and schedule]	[Group seminar]	1 day to cover the whole
	Newly constructed school (tentatively A-1) -Lecture: Art Hall	program
	[On-site training]	
	1. Instruction on basic and common items	2 days in total for general session
	2. Site-specific instruction using different heat sources	2 days for item-specific session
	3. Training on heating operations in all four target schools	6 days in total

Implementation resources

 Activities in Japan 		
-Energy management	Support for preparing seminar materials	10 man-days
		Details
		• 5 days for preparing materials for urban schools (A4 20p)
		• 5 days for preparing materials for rural schools (A4 20p)
Activities in Mongolia		
-Energy management	Lecturer, on-site training	16 man-days, trip to Mongolia 【Details】
		• Travel, preparation, and meeting: 1day each
		• Adjustment of instrumentation: 1 day per target school, totaling 4 days
		• Updating General Operation Manual: 1 day
		• Instruction on basic matters common to the target schools: 1 day
		• Heating operation training in all the target schools : 4 days in total
		• Wrap-up and debrief: 1 day
		• Day off (Sunday): 2 days
		• Travel: 1 day
[Equipment]	Supply data recording device	* New equipment needed is built in the system (included in the Project's construction contract)
	Thermometer with data recording device	in advance.
	(for measuring room temperature)	
[Local contract]		
• Translator (including conference interpreting)	Japanese or English to Mongolian	4.0 man-days
Local energy engineer	Preparing seminar materials on energy management	6 man-days: Preparing seminar materials under supervision of a Japanese engineer
	Seminar and operation instruction	8 man-days: Adjustment of instrumentation, operational training in the target schools
Translation	Prepared seminar materials (English to Mongolian) are translated by a local energy engineer.	
[Local resource]	Main host and lead coordinator	UBC-ED
	Venue setting and	School staff in the target school
	preparation, Presentation	Facility managers in the target school

(5) Establishment of maintenance schemes through energy-saving practices and quantifying increased efficiency

With respect to the energy-saving schemes learned in Activity (4), it is crucial to be trained in efficient heating operations properly adopted to seasonal temperature differences in Mongolia. Therefore, a local energy engineer will be assigned to supervise appropriate operation procedures over eight months from a start of heating in October through the end in May. With this, the operators will practice heating operations in an efficient manner and make them established on site. The established procedures will be described in the General Operation Manual as a tutorial applicable to other schools to enable their energy-saving practices to continue.

As the same time, differences resulting from energy-saving practices (less coal consumption and running costs and reduction in air pollutants and greenhouse gases which is co-benefit) will be quantified (into numbers) to promote understanding on importance of appropriate use of energy.

Description		
【Target】	 Directors in the target schools Facility managers and operators Administrators involved in school construction 	
[Structure of contents]	 [On-site demonstration] (1) + (2) 1) Instruction on recording of heating operations (external and internal temperatures and heat consumption at a scheduled period) 2) Training on data check and efficient room-temperature control schemes 3) Optimization of the schemes (higher efficiency and feasibility) and incorporation into a manual to ensure continuous practices 	Local energy engineer Tool: General Operation Manual
	 [Verification seminar] (1) + (2) + (3) 1) Implementation of the energy-efficiency verification seminar based on data analysis, numerated increase in energy efficiency, modeling of appropriate schemes for heating system operations 	Facility managers in the targets schools Japanese expert on energy management Tool: Verification report (slides), General Operation Manual
【Venue and schedule】	 1) Target schools (1 session in every two weeks, totaling 32 weeks, 0.5 day per school x 4 schools) 2) Same as above 3) 1 month prior to a defection inspection (June when heating is terminated) Newly constructed school (tentatively A-1) -Lecture: Art Hall 	Local energy engineer Local energy engineer 1 day Japanese expert on energy management and local energy engineer local energy engineer
Implementation re	source	

[Japanese consultant]

ب و ورو ور پ		
 Activities in Japan 		
-Energy management	Support for analysis of verified data	10 man-days 【Details】
		• Review and data entry of monitoring results on heating systems and temperature data: 1 day
		 Data analysis and on-site operation training: 5 days
		Review of verified results: 2 days
		• Preparation of presentation materials for the energy-efficiency verification seminar: 2 days
 Activities in Mongolia 		
-Energy management	Discussion on verified results with school staff	6 man-days, trip to Mongolia 【Details】
	MC for the verification seminar,	 Travel + preparation: 1day*
	lecturer	Verification seminar: 1 day
		 Check and supplementary operation training: 2 days (0.5 days for 4 schools)**
		 Wrap-up and debrief at UBC-ED: 1 day Travel: 1 day**
[Local contract]		-
Translator (including	Japanese or English to Mongolia	2.5 man-days
conference interpreting)		(*above requires 0.5 days, **above entails no budget)
• Local energy engineer	Training on efficient room temperature control	32 man-days in total-check analyzed data quality and efficiency, requiring a 0.5 day- visit each to the target schools in every two weeks. Monitor and instruct the four schools to obtain comparable data (0.5 day per school*4 sites*0.5 session/week*32 weeks)
	Support for analysis of verified data	5 man-days in total
	Assistant in the verification seminar	3 man-days
[Local resource]	Main host and lead coordinator	UBC-ED
	Venue setting and preparation	School staff in the target school
	Presentation	Facility managers in the target school


5. Procurement of Resources Required for Implementation of Soft Component

The soft component described here is intended to make designed physical components broadly known and disseminated. The main activities are integral to assistance provided by the Project where the implementing agency will carry out publicity activities and energy-saving practices. The Japanese consultant involved in the detailed design of the school facilities will mobilize relevant local resources to the possible extent. Responsibilities are assigned as below.

- Preparation of booklet and other tools: The Japanese consultant will complete drafting, including input from the implementing agency (Translation into Mongolian will be outsourced to a local translator). Upon delivery of a block copy, printing and bookbinding will be contracted to one of three or more agencies selected with their competitive quotations. Potential agencies are invited from those who have previously worked for JICA projects.
- On-site model case study (focusing on functional arrangements): With the implementing agency hosting the model case study, the Japanese consultant will pursue overall management jointly, direct a site tour, and make a presentation. During the site tour, a resident engineer assigned by the Japanese consultant will be assisting
- Model case seminar for school construction staff: With the implementing agency hosting the model case seminar, the Japanese consultant will pursue overall management jointly, direct a site tour, and make a presentation. During the site tour, a resident engineer assigned by the Japanese consultant will be assisting
- On-site energy management training: The Japanese consultant will be tasked with an entire process from preparation of training materials to on-site practices. Because this requires technical expertise, the Project will assign a person who has previously worked for an energy efficiency project in UBC funded by Japan.
- Energy-saving practices and verification of increased efficiency: Under the guidance of Japanese consultant, a hands-on training will be provided in the target schools, instructed by a local energy engineer. Because such engineer must be knowledgeable of theoretical understanding, and have practical skills in installing, operating and maintaining a boiler system, the Project will assign a person who has first-hand experiences in similar projects.

6. Implementation Schedule of Soft Component

Activities (1), (2), and (3) that constitute the soft component are scheduled in a period between the facility completion and handover. Prior to this, a booklet and other tools modifying it (brochure and presentation slides) will be completed. As for Activity (4), an on-site training will be held after September 15 when a district heating system starts to operate. Activity (5) is scheduled in late June prior to a defect inspection of the completed facilities, after continuous thermal monitoring is completed over a heating period from October through May.



7. Deliverables of Soft Component

Deliverables will include a completion report on the soft component submitted to the Government of Mongolia and Japan, a booklet, brochure, PPT presentation slides, lists of participants in the publicity events, their responses to questionnaires, training materials on energy management (General Operation Manual and others), verified data on energy management, finalized General Operation Manual, and so on.


8. Responsibilities of the Recipient Country


As leading organizers of publicity events on the completed schools, MECSS and UBC-ED must be prepared to decide on and invite potential participants and receive as many visitors. With outcomes obtained in energy-related training sessions, these agencies are expected to encourage other schools to practice energy-efficient management schemes for the sake of their appropriate spending of maintenance costs.

The soft component is planned as a minimum essential endeavor to make the model schools used as intended and known broadly among people involved in education, particularly regarding what functions they serve for. UBC-ED, the project implementer, should continue to gain publicity of those model schools, using a booklet and other available tools. In particular, they are expected to understand key features to be applied to their school construction, namely, disability-related accommodations, disaster preparedness, and environmental friendliness. The guiding models in the Project should be also a design foundation on which further improvements are made.


6. Other Relevant Data

- 6-1 Topographic Survey Map
 - No. 75 School (A-1) construction site, Khan-Uul District
 - Chingeltei No. 7 Khoroo (A-2) construction site
 - No. 53 School (B-1) construction site, Bayanzurkh District
 - No. 109 School (B-2) construction site, Nalaikh District












.

No. 53 School (B-1) construction site, Bayanzurkh District





6-2 Geotechnical Survey Report (abstruct)

- No. 75 School (A-1) construction site, Khan-Uul District
- Chingeltei No. 7 Khoroo (A-2) construction site
- No. 53 School (B-1) construction site, Bayanzurkh District
- No. 109 School (B-2) construction site, Nalaikh District

Engineer-geological survey report for new school construction area in 2nd khoroo, Khan-Uul district, Ulaanbaatar

Table of Contents

2.4 Geomorphology characteristics and physic geological appearance, process.....

3.1 Soil engineer geological classification and formation

3.2 Soil physic mechanic characteristic

ENGINEERING-GEOLOGICAL CONDITIONS AND PHYSICAL AND MECHANICAL

GENERAL INFORMATION.

2.2 Climatic conditions 2.3 Geological formation

2.5 Hydro-geological condition

Survey condition of engineer geology

1.1 Survey basis .. 1.2 Survey technique ...

2.1 Location

PROPERTIES ...

Conclusion Reference list

Borehole logs.

.

city

5

5 5

.6

...6

..6

7

. 7

7

.9

.10

APPENDIXES

1.	LOCATION OF BOREHOLES, SC 1:1000, APPENDIX №1			
2.	ENGINEERING-GEOLOGICAL SECTION, APPENDE	X №2		
	SC	Horizontal	1:100	
		Vertical	1:1000	
3.	STANDARD PENETRATION TEST RESULT APPEND	DIX №4		

Зураг төсөл, хайгуул судалгааны "ИНЖЕНЕР ГЕОДЕЗИ" ХХК

	"ENGINEERING GEODESY" LLC
J.	Uhumbaatar-16081 Bayango district , 6-r, khoroo 10 ⁶ ndero 65 ⁶ hudding A corpus Postz 60 ⁶ post 246 ⁵ hox Postz 26 ⁶ post 246 ⁵ hox Mobiles s994055339, 91911854 Webs rever, gene-mongol.mm

ZT19-615/14

Engineering-geological investigation report for new school building area in 2nd micro, Khan-Uul district, Ulaanbaatar city

/Detail design stage/

Approved by:

Δ

Archive 17/039

Director

Prepared by:

Engineer geologist G.Erdenetsetsea

TS.Bileg

Ulaanbaatar city

2017

Engineer-geological survey report for new school construction area in 2nd khoroo, Khan-Uul district, Ulaanbaatar

GENERAL INFORMATION I.

1.1 Survey basis

Engineer Geodesy LLC /Drawing and geological survey company/ completed engineer geological survey work of construction area of 75th school extension in Ulaanbaatar city, han-Uul district, 2nd khoroo by "MECSS" tender in April 19th-28th 2017 and survey planned and completed as their requested.

1.2 Survey technique

Team with drill master Galzagd.Y, assistant worker Byambasuren.G is executed the drill work by UGB-50M equipment, 5 boreholes 10.0 meters depth, 50.0 t/m column drilling, to locate and define underground water depth, characteristics, construction fundament pressure effective soil depth and distribution, according to the plan and SNIP 11-03-01 in survey area engineer geological survey work.



Soil physic and mechanic characteristics been defined by taking 29 pieces of samples from drilled boreholes in soil study laboratory. According to ASTM standard, Tsagaandarkhi.L /laboratory chief/, Ganchimeg.G /laboratory engineer/ are summarized the result and tabled soil analyze in soil study laboratory of Engineer Geodesy LLC /with guaranteed number of TL-78 from Standardization and Metrology department, satisfied the standard of ISO/IEC 17025:2005, MNS ISO/IEC 17025:2005/. Engineer Geologist Erdenetsetseg.G processed the engineer geological report to create procedural plan which is made by comparison of field survey material and laboratory analyze result.

Source materials related to survey work stored in archive of Engineer Geodesy LLC.

Engineer-geological survey report for new school construction area in 2nd khoroo, Khan-Uul district, Ulaanbaatar

II. ENGINEERING GEOLOGICAL INVESTIGATED CONDITION

2.1 Location

Area of re-building where 19th bus station of 2nd khoroo, Han-Uul district and 75th school's new school and planning now.



Drawing №1. Survey area of location

2.2 Climatic conditions

"Buyant-Ukhaa" climate stations indices CCM 23-01-09 standard "Climate and geotechnical indices for the construction work" have been used for the climate indices of this site, and showed in tables

Station	1000	Month									Year					
	1	II	III	IV	V	VI	VII	VIII	IX	X	XI	XII	1.1.1			
Buyant- Ukhaa	-25.7	-21.1	-10.2	-0.8	8.7	15.0	17.2	15.0	7.6	-1.5	-14.1	-23.4	-2.6			

Absolute maximum air temperature, °C

			Table II-	- 4
Station	Absolute maximum	Date	July average	٦.
Buyant-Ukhaa	39.4	2005.VII.15	-31.4	

Absolute minimum air temperature, °C

Station	Absolute minimum	Date	Jan average
uvant-Ukhaa	-49.0	1954.VII.30	-39.9

Зураг төсөл, хайгуул судалгааны "ИНЖЕНЕР ГЕОДЕЗИ" ХХК

Table II 2

.....

Engineer-geological survey report for new school construction area in 2nd khoroo, Khan-Uul district, Ulaanbaatar

III. ENGINEERING-GEOLOGICAL CONDITIONS AND PHYSICAL AND MECHANICAL PROPERTIES

3.1 Soil engineer geological classification and formation

In survey area, soil color was brown yellowish and type was well-graded gravel with sand -GW soil /EGE-1/. Physics and mechanical properties of soil determined and draw cut to spread and thick.

3.2 Soil physics mechanic characteristic

Depending on soil particle structure and physic mechanic characteristic classified to engineer geological 1 element.

EGE-1. Well-graded gravel with sand /GW/

Brown yellowish color, up and modern Quaternary alluvium-proluvium (apQ_{III-IV}), saturation by water and sandy equal gravel soil.

Granulometric composition from the laboratory analysis of these soil samples includes: (%):

Gravel	63.3
• Sand	32.9
Silt	3.8
Clay	3.8

Physical properties indices of the soil:

	 Natural moisture content 	8.0
	 Specific gravity, g/sm³ 	2.65
	 Wet density g/sm³ 	2.28
- 5	 Dry density g/sm³ 	2.11
	 Porocity, % 	20.34
	 Porocity ratio 	0.256
	 Moisture content degree 	0.83

Normative and calculation indices of the mechanical properties:

According to the norm and regulations to create the construction groundwork - CCM 50-01-16 and Table I:

Nor	mat	ive	val	ues:

Cohesion	$C_n = 2.0 \text{ kPa}$
 Angle of internal friction 	$\phi_n=40^0$
 Deformation modulus 	E= 45 MPa
Calculation value:	
 Cohesion 	Cn2= 1.33 kPa
· Apple of internal friction	26.260

Angle of internal metion	φη2 50.50
Calculated resistance	$R_0 = 500 \text{ kPa}$

According to CCM 50-01-16 and 5.3.2, well-graded gravel with clay and said soil is normalize by none swellings.

Silty sand with gravel soil seasonal freezing depth	3.8 m	
Earthwork of measuring, dig-up	Ш	

Зураг төсөл, хайгуул судалгааны "ИНЖЕНЕР ГЕОДЕЗИ" ХХК

Engineer-geological survey report for new school construction area in 2nd khoroo, Khan-Uul district, Ulaanbaatar

Structure and technical calculation temperature, 9

					Table II-4		
	Calculation temperature, °C						
E		One day during					
Station	1 day	3 day	5 day	Airring	hottest temperature		
Buyant-Ukhaa	-36.7	-35.3	-34.2	-29.9	25.8		

Temperature supply indices for the construction and technical calculation during winter time (⁰C)

Table II-5

Station	The		lays tempe oly, %	rature	The coldest 1 day temperature supply, %			
	99.2	99.5	94	92	99.9	99.5	94	92
Buyant-Ukhaa	-41.8	-41.7	-39.4	-39,0	-43.3	-43.2	-41.5	-40.7

Air humidity and precipitation

Tab	le]	I-6

T 11. IT -

1.00				Pre	cipitation			
Station	Warm season	Cold season	Annual	In warm season	Maximum of day	Year	Month	Day
Buyant-Ukhaa	50	72	248.8	236.5	74.9	1967	VI	27

Annual and monthly average wind speed

Station					Mont	h. wint	er, aver	rage spe	ed of y	ear. m	sec			- 1
	I	U	ш	IV	V	VI	VII	VIII	IX	X	XI	XII	winter	year
Buyant-Ukhaa	0.7	1.3	2.5	3.7	3.8	3.4	2.9	2.6	2.5	2.1	1.3	0.7	0.9	2.3

2.3 Geological formation

In survey area, from below filled soil upper and modern Quaternary alluvium-proluvium. Equal well graded gravel with sand soil spread equally thickness in survey area until 10 meter deep continued. In survey area, spread soil classified engineering-geological elements that EGE-1, defined characteristics of physics-mechanical and cross section of depth and distribution shown in drawing.

2.4 Geomorphological features 6a physic-geological scene and process

Survey area different from geomorphological one element and located in higher river terraces in right hand side of Tuul river. In survey area, soil was generally equal structure and elevation is between 1284.90-1285.50 meter then elevation difference is 0.60 meter.

2.5 Hydro-geological condition

In survey area, soil groundwater has been occurred in 3.60-3.80meter deep by 5 drill holes with 10 meter depth /dated April 19-20th ,2017/. Soil ground water is minimum low level in April and it can be increased by rainfall. Ground water is with free surface and hydraulic related to Tuul river. In summer and autumn, soil ground water level increase about 1.0-1.5meter from current level and it depends on source of water.

Зураг төсөл, хайгуул судалгааны "ИНЖЕНЕР ГЕОДЕЗИ" ХХК

Engineer-geological survey report for new school construction area in 2nd khoroo, Khan-Uul district, Ulaanbaatar city

IV. CONCLUSION

- In survey area, low and average blub engineer geological 1 types of element occurred, and there is no swellings, soil ground water detected in 3.60-3.80meter, filled up ground spread vary thickness related to human and engineering process and this area depend on hard condition for engineering geology. For example: underground cable, network (thermal and pure water pipelines), electrical cable (lot of shear), earthquake magnitude is 8 that value is intense range.
- Parameters of calculation and main soil spread to area physic and mechanic characteristic normative are shown in section of Engineer Geological classification and soil Physic mechanic characteristic.
- Table IV-1 is shown soil blub level and earth work degree for distributed soil in survey area. Earth work degree counted as manually executed.

Table IV-1

Soil type	Earthworks degree	Bulging degree	Specific reactance om, n
Well graded gravel	ш	None bulging	Dry condition: 2000-10000 Watery condition: 200-600

4. Survey area is in 8 magnitude earthquake region. (143-190cm/c² acceleration of top soil)

5. Soil groundwater has not been occurred in 3.60-3.80meter deep by 5 drill holes with 10 meter depth /dated April 19-20th, 2017/. Soil ground water is minimum low level in April and it can be increased by rainfall. Ground water is with free surface and hydraulic related to Tuul river. In summer and autumn, soil ground water level increase about 1.0-1.5meter from current level and it depends on source of water.

6. Soil test is necessary after opening of building fundament galvanized.

Summary is written Erdenetsetseg.G /Engineer-geologist/

Engineer-geological survey report for new school construction area in 2nd khoroo, Khan-Uul district, Ulaanbaatar

V. REFERENCE LIST

- CCM 2.02.01-94. Construction codes on designing of construction foundation Ulaanbaatar, 1994 y.
- CCM 23-01-09. Climate and geotechnical indices for the construction work. Ulaanbaatar, 2009 y.
- CCM 22.01.01/2006. Construction codes on construction planning at seismic zones of Mongolia Ulaanbaatar, 2006 y
- 4. "CG 11-107-11. Guideline of engineering geologic report and summary
- 5. "CCM 11-03-01 Contruction norm and regulation
- Инженерные изыскания встройтельсве (Спаровочнык) страниц таблиц -131, 1975года., зав.редакций Е.А.Ларина "Земляные работы" / СНИП-IV-5/
- 7. ASTM D 2487

Зураг төсөл, хайгуул судалгааны "ИНЖЕНЕР ГЕОДЕЗИ" ХХК

Зураг төсөл, хайгуул судалгааны "ИНЖЕНЕР ГЕОДЕЗИ" ХХК

		V. BOREHOLE LOGS BOREHOLE-1	
Depth .m	10.00	Elevation, m	1284.93
Diameter,mm	168	Drilling date:	2017.04.19
1. Filled up soil	color is dark	gray and contained building waste.	0,00-1.30
			1.30
2. Well-graded	gravel with sa	nd soil color is brown yellowish.	1.30-10.0
			8.70
	Se	oil groundwater detected at 3.60m.	
		/Current date April 19th,2017 /	

BOREHOLE -2

Depth .m	10.00	Elevation, m	1285.0
Diameter,mm	168	Drilling date:	2017.04.19
1. Filled up soil	color is dark	gray and contained building waste.	0.00-1.40
			1.40
2. Well-graded	gravel with sa	nd soil color is brown yellowish.	1.40-10.0
			8.60
	Se	oil groundwater detected at 3.70m.	
		/Current date April 19th,2017 /	

BOREHOLE -3

Depth .m	10.00	Elevation, m	1285.08
Diameter.mm	168	Drilling date:	2017.04.20
1. Filled up soil	color is dark	gray and contained building waste.	0.00-1.70
2. Well-graded	gravel with sa	nd soil color is brown yellowish.	1.70-10.0
	Se	il groundwater detected at 3.80m. /Current date April 19 th ,2017 / BOREHOLE -4	
Depth ,m	10.00	Elevation, m	1285.50
Diameter,mm	168	Drilling date:	2017.04.20

10

Зураг төсөл, хайгуул судалгааны "ИНЖЕНЕР ГЕОДЕЗИ" ХХК

1.	Filled up soil color is dark gray and contained building waste.	0.00-1.20
		1.20
2.	Well-graded gravel with sand soil color is brown yellowish.	1.20-10.0

Engineer-geological survey report for new school construction area in 2nd khoroo, Khan-Uul district, Ulaanbaatar

			8.80
	Se	oil groundwater detected at 3.80m.	
		/Current date April 19th,2017 /	
		BOREHOLE -5	
Depth ,m	10.00	Elevation, m	1285.30
Diameter,mm	168	Drilling date:	2017.04.20
1. Filled up soi	l color is dark	gray and contained building waste.	0.00-1.50
			1.50
2. Well-graded	gravel with sa	nd soil color is brown yellowish.	1.50-10.0
			8.50
	Se	oil groundwater detected at 3.80m.	


/Current date April 19th,2017 /


Borehole logs written by:


D.Dashzeveg

Зураг төсөл, хайгуул судалгааны "ИНЖЕНЕР ГЕОДЕЗИ" ХХК

11







	ENGIN		G GEO Object		LL.C		Eng	gineeri	ing-ge	ologia	cal in v	restiga	tion r								ST RE:		Uni dis	trict, L	llaan by	utür city		MNS ISC		7025:20 Start das Finish d	ie:			2017.0 2017.0				
Na	Borehole number	depth of sumple [m]	37.5	25.0	61	12.5	ain siz	e maly	sis, [m 92 2	0.600	0.425	0.300	0.075	6600	220.0	Hydro 1100	metr,	um)%	4.001 Ú	0.001	*	Gravel	Suid	shirchay	Soil	type / ASTM D 2487/		nic index/ M D 4318 PL		Ģ.	cc	Vatural mostiture content(W),	Spectic gravy G, r/cs4	Wet density, p. r/cv/	Dry density, ps. r/cw ¹	Porocity, n. %	Perocety ratio. e	Saturation degree, Sr
-	-	-	-	-	-	-	_	-	-	-	-	_	-		-	-	-	Б	GE-2	Well-er	nded are	wel with	and GV	1	-			- 1	_	-	-	4	-	-	-		-	-
1	1	-6.0	6.0	7.0	9.7	6.2	15.7	16.9	14	6.0	36	3.8	3.9	-0.4	6.8	0.7	11	0.8	0.1	0.1	100.0	60.0	12.6	41	GW	well-graded gravet	-	inclastic		32	24.22	10.2	2.67	2.29	2.08	22.17	0.285	0.9
2	1	9.5	6.5	7.5	9.2	7.6	161	16.4	15.9	63	12	3.9	13	0.9	U	0.5	0.4	0.5	0.2	0.3	100.0	63.3	32.8	3.9	GW	with and will-graded gravel	-	inclastic		32	25.92	8.9	2.63	2.38	2.09	20.39	0.256	0.9
	2	3.0	7.1	6.9	8.6	7.0	15.4	17.2	14.2	6.5	4.5	4.6	3.3	0.5	0.6	0.0	0.8	0.4	0.5	0.1	100.0	63.1	33.4	3.8	GW	with sand well-graded gravel	-	inclastic		45	36.4	7.8	2.65	2.28	2.12	20.19	0253	0.1
t	3	4.0	6.2	7.2	9.4	**	15.6	16.2	14.5	12	14	4.0	1.8	0.8	1.0	0.4	0.3	0.7	0.2	0.1	100.0	63.4	12.9	17	GW	with sand well-graded gravel	-	inclastic		45	40.6	6.8	2.66	2.29	7.14	19,19	0.247	n.
	1	20	5.9	8.1	8.6	43	16.0	16.0	14.1	68	3.5	3.7	4.0	<u>68</u>	0.7	0.6	0.5	0.3	0.4	0.2	100.0	64.4	32.1	3.5	GW	well-graded graved		inelastic		50	45.1	24	2.67	2.29	2.17	18.63	0.229	10
đ	3	23	6.6	7.7	8.6	8.0	152	16.7	15.9	7.0	4.1	3.8	3.0	0.4	0.9	0.6	0.7	6.4	0.5	0.1	100.0	62.8	33.6	26	GW	well-graded gravel with sand	-	inclastic	-	22.5	21.1	7.9	2.64	2.27	2.10	20.31	0.255	0,
,	1	3.4	7A	7,4	9.0	3.9	158	17.2	15.8	61	3.1	47	<u>1</u> 3	0.7	12	0,5	6.1	8.7	0.8	0.1	100.0	62.5	33,4	43	GW	well-graded gravel		inelastic		26	1.640	61	2,63	2.25	2.12	19.37	0.240	0.
	2	1.6	6.4	6.8	8.4	9.1	16.2	16.6	13.9	7.3	4.0	4.5	3.1	0.4	0.7	0.6	9.8	0.5	0,4	0.2	106.0	63.8	32.6	3.6	0W	well-graded gravel		indestic		30	28.8	7.4	2,64	2.26	2.10	20.29	0.255	0,
,	0.	5.0	5.5	7.0	8.9	8.5	15.7	17.5	16.0	6.8	3.8	12	3.9	0.2	1.1	8.4	9.6	0.4	0.1	0.3	100.0	63.1	33.7	3.2	GW	well-graded gravel with sand		inelastic		17.5	30.1	7.2	2.63	2.28	2.13	19.13	0.237	11.
0	5	55	8.7.	7.3	9.2	9.7	15.0	16.5	14.8	7.1	3.4	4,4	3.4	0.7	0.6	0.1	9.4	0.6	0.5	0.2	100.0	63,4	33.1	3.5	GW	well-graded gravel		melastic		38.3	31.05	8.0	2.65	2,27	2.10	20.68	0.261	.0.7
1	2	55	5.3	9.4	hz	3.8	13.4	17.3	13.0	81	42	4,0	12	6.9	12	0.5	0.6	0.3	92	0.4	100.0	63,4	32.5	41	GW	well-graded gravel with saud		inelastic		50	36.9	7.7	2.66	2.29	2.11	20.04	0.251	6.8
12	3	35	7.0	7.0	8.2	8.6	15.8	17.0	14.9	7.5	4.2	23	3.0	1.0	0.9	0.7	0.3	0.5	0.8	0.3	100.0	63.6	31.9	45	GW	well-graded gravel		inelastic		25	22.5	7.3	2.65	2.28	2.12	19.82	0.247	0.7
3	4	:6.0	3.0	<u>9</u> .0	6.5	9.7	143	18.7	13.5	6.9	4.7	5.1	2.8	0.8	9.6	0.5	8.6	0.7	0.4	0.2	100.0	63.2	33,0	3.8	GW	with sand well-graded gravel with sand	-	inclustic		45	32.5	8.0	2.64	2.26	2.09	20.74	0.262	0.1
	3.	65	6.4	7.0	7.4	10.8	13.9	19.1	13.7	8.2	3.0	17	3.7	0.4	1.0	0.4	0.7	0.3	0.2	0.1	100.0	54,6	32.3	31	0W	well-graded gravel with sand		inclastic		24.6	24	8.1	2.63	2.27	2,10	20.16	0.252	0.4
5		4.0	63	7.9	7.5	9.8	171	15.9	13.7	8.5	3.7	3.1	3.9	0.5	9.7	0.5	0.3	6.4	0.1	0.1	100.0	64,5	32.9	2.6	GW	well-graded gravel with sand		inelastic		-25	23	7.4	2,64	2.28	2.12	19.59	0.244	0.6
6	2	7.9	5.6	8.7	9.1	7.1	16.6	14.5	(2.)	10.8	3.2	4.1	3.5	0.7	1.2	0.7	9.5	0.8	92	0.3	100,0	61.9	33.7	4.4	GW	well-graded gravel with und	×	inelastic		40	25.6	8.1	2.65	2.27	2.10	20.76	0.282	0.3
7	4	2.5	7.5	6.8	8.4	7.8	16.0	15.8	16,3	7,4	27	3.4	32	1.0	1.4	0.3	0.9	0.8	9.1	9.7	100.0	62,3	.33.0	14.7	GW	well-graded gravel with sand		inclusio		42	26-89	7.1	2.06	2.79	2.14	19.62	11,244	0.
8	3	5.0	64	7.2	9.0	3.8	148	17.2	10,8	93	3.7	3.8	3.8	6,7	1.9	0.6	0.7	0.2	9.3	0.1	100.0	63.1	32,4	45	ũW	well-graded gravel with sand		inclustic		40	25.6	8.1	2.64	2.28	2.0	20.11	0.252	<i>w</i>
6	1	7.0	4.5	61	9.2	7.8	16.5	16.8	15.4	7.7	4.1	3.6	3.6	14	1.5	0.7	0.3	0.5	0.4	0.2	100.0	60,9	34.4	4,7	GW	well-graded gravel with sand		inclusic		40	24.3	7.7	2.63	2.27	2.11	19.86	0.248	0.1
0	5	7.0	6.0	8.1	8.2	10.2	14.8	(7.3	15.6	5.7	2.8	3.8	3.9	0.9	3.1	0.5	0.7	0.4	0.3	0.3	100.0	64.6	31.2	42	GW	well-graded gravel with sand	1	inclustic	2	45	36.5	8.1	2.64	2.27	2.10	20.46	0.257	11.
21	2	10.0	7.8	7.4	9.2	8.7	124	10.5	14.7.	6.4	3.5	3.2	32	0.5	0.0	0.1	0.8	0.7	96	0.2	100.0	65.0	31.0	4.0	ow	well-graded gravel with and		inclasii:		45.4	36.8	9.4	2.65	2.28	2.08	21.35	0.272	0.5

Borehole	Depth	0-15cm	15-30c	m	30-45ci	m	N
number	of SPT (m)	Blow counts	Real penetration thickness(cm)	Blow counts	Real penetration thickness(cm)	Blow counts	Blow counts
	2.0	25	15	42	6	50	92/21cm
	3.0	22	15	47	7	50	97/22cs
	4.0	14	15	18	15	22	40
	5.0	17	15	19	15	23	42
BH-1	6.0	15	15	17	15	27	44
	7.0	28	15	30	15	32	62
	8.0	29	15	32	15	37	69
	9.0	28	15	31	15	35	66
	10.0	33	15	42	15	48	90
	2.0	30	15	37	11	50	87/26cm
	3.0	28	15	35	13	50	85/28cm
	4.0	21	15	24	15	26	50
	5.0	24	15	26	15	30	56
BH-2	6.0	26	15	27	15	30	57
	7.0	28	15	31	15	33	64
	8.0	32	15	33	15	37	70
	9.0	34	15	38	15	40	78
	10.0	37	15	40	14	50	90/29cm
	2.0	29	15	42	10	50	92/25cm
	3.0	35	15	49	8	50	99/23cm
	4.0	24	15	26	15	25	51
	5.0	26	15	26	15	27	53
BH-3	6.0	25	15	27	15	28	55
	7.0	24	15	25	15	28	53
	8.0	25	15	28	15	30	58
	9.0	27	15	30	15	31	61
	10.0	29	15	30	15	32	62
	2.0	28	15	39	11	50	89/26cm
	3.0	33	15	46	8	50	96/23cm
	4.0	19	15	20	15	22	42
	5.0	21	15	21	15	25	46
BH-4	6.0	20	15	21	15	23	44
	7.0	19	15	22	15	22	44
	8.0	20	15	22	15	24	46
	9.0	22	15	25	15	28	53
	10.0	23	15	26	15	32	58
	2.0	24	15	42	12	50	92/27cm
	3.0	30	15	45	13	50	95/28cm
	4.0	18	15	21	15	22	43
	5.0	19	15	22	15	24	46
BH-5	6.0	20	15	22	15	25	47
	7.0	24	15	24	15	28	52
	8.0	25	15	27	15	28	55
	9.0	34	15	36	15	36	72
	10.0	35	15	38	15	40	78
	1. 1. 1. 1		red by:		E.Uchral		

STANDARD PENETRATION TEST RESULT /SPT/

8.8 12 18 13 84 2 2 8.4 5.0 0.9 18 10 10 10 10 12.6 14.2 15.0 10.4 15.1 13.6 7/2 6/8 1/9 8/0 7/2 7/2 18.7 2.0 61 34 35 35 26 21 21 2.9 3.0 3.4 3.4 3.4 3.5 3.5 3.5 2.6 2.6 3.4 12 4 83 1.00 1.00 9.7 9.7 1.00 6.6 6.6 6.0 0.2 70 70 70 70 70 70 70 70 70 70 70 0.3 0.5 0.3 0.3 0.5 0.5 6.5 6.5 6.4 6.7 6.7 ru 10 10 10 10 10 10 10 10 0.1 0.1 0.1 0.1 100.0 60.0 1.0 1 2 2 7 28 0. GW GW GW GW GW . G. Gandhimeg A. Bayannagnai 8.0 2.64 2.24 2.00 20.86 0.264 0.96 0.89 0.76 0.76 0.85 0.85 0.85 0.85

laborant

A-124

à	"ENGINEERING GEODESY" LLC		
1		TABLE OF CONTENTS I. GENERAL INFORMATION	
Λ	Ulaanbaattar-16081 Bayangol district, 6-r khoroo		
	10 ⁴ micro, 65 ⁴ building A corpus Post: 26 ⁴⁰ post: 246 ⁴ hox Phone/fax: 77278899	1.1. Survey basis	
	Mobile: 99095839, 9191484 Web: www.geo-mongol.mn	1.2. Survey technique	
Archive 17/035	3T19-615/14	II. SURVEY CONDITION OF ENGINEER GEOLOGY	
		2.1 Location	
		2.2 Climatic conditions	
		2.3 Geological formation	
		2.4 Geomorphology characteristics and physic geological	appearance, process
		2.5 Hydro-geological condition	
		III. ENGINEERING-GEOLOGICAL CONDITIONS AND P	HYSICAL-
	A second baseline in the second se	MECHANICAL PROPERTIES	
ENGINEER GEOLOGICAL S	URVEY REPORT OF NEW SCHOOL	3.1 Soil engineer geological classification and formation	
CONSTRUCTION AREA IN 7"	* KHOROO, CHINGELTEI DISTRICT,	3.2 soil physic-mechanic characteristic	
ULAAN	BAATAR CITY	IV. CONCLUSION	
/ Detai	l design stage /	V. REFERENCE LIST	
		VI. BOREHOLE LOGS	
		APPENDIXES	
		1. TOPOGRAPHY AND LOCATION OF BOREHOLES, SC 1:100)0, (APPENDIX №1)
Approved by:		2. ENGINEERING-GEOLOGICAL SECTION, (APPENDIX №2)	
	10 To 10	SC HORIZO	ONTAL 1:100
DIRECTOR	TS.BILEG	VER	TICAL 1:1000
		3. SOIL PHYSIC MECHANIC CHARACTERISTIC GENERAL T	ABLE
Prepared:		(AI	PPENDIX №3)
Engineer geologist	E.Uchral		
Ulaar	nbaatar city		
oldul	2017		

Chingeltei No. 7 Khoroo (A-2) construction site

Engineer geological survey reportof new school construction area in 7th khoroo, Chingeltei district, Ulaanbaatar city

I. GENERAL INFORMATION

1.1 Survey basis

Engineer Geodesy LLC /Drawing and geological survey company/ completed engineer geological survey work of construction area of school extension in Ulaanbaatar city, Chingeltei district, 7th khoroo by MECSS tender in April 17th-27th 2017 and survey planned and completed as their requested.

1.2 Survey technique

Team with drill master Ganbold. B, Byambaa. G, Lhagvatseren. N is executed the drill work by UGB-1BC equipment, POWER4000 drilling machine 5 boreholes 10.0 meters depth, 50.0 t/m column drilling, to locate and define underground water depth, characteristics, construction fundament pressure effective soil depth and distribution, according to the plan and SNIP 11-03-01 in survey area engineer geological survey work.



Soil physic and mechanic characteristics been defined by taking 5 pieces of samples from drilled boreholes in soil study laboratory. According to ASTM standard, Tsagaandarkhi.L /laboratory chief/, Ganchimeg.G /laboratory engineer/ and Bayarmagnai.A /laboratory of Engineer Geodesy LLC /with guaranteed number of TL-78 from Standardization and Metrology department, satisfied the standard of ISO/IEC 17025:2005/. Engineer Geologist Uchral.E processed the engineer geological report to create procedural plan which is made by comparison of field survey material and laboratory analyze result.

Source materials related to survey work stored in archive of Engineering Geodesy LLC.

II. Survey condition of engineer geology

2.1 Location

Ulaanbaatar city, Chingeltei district, 7th khoroo, existent 224th kindergarden school building to front new school construction.



Drawing №1. Survey area of location

2.2 Climatic conditions

Station

MUIS

MUIS climate stations indices and CCM 23-01-09 standard "Climate and geotechnical indices for the construction work" have been used for the climate indices of this site, and showed in tables

Annual and monthly average air temperature, °C

Station						Mo	onth						Ann ual
	I	II	III	IV	V	VI	VII	VIII	IX	X	XI	XII	1
MUIS	-21.2	-14.9	-7.9	1.7	10.0	15.2	17.5	15.4	8.6	0.3	-11.3	-18.8	-0.5

 Absolute max
 Date
 VII avarege

 33.8
 1997.VII.10
 26.5

 Absolute minimum air temperature, ⁰C

.....

Table II-2

	T		
Station	Absolute	Date	l avarege
MUIS	-36.0	1988.I.23	-31.9

Engineer geological survey reportof new school construction area in 7th khoroo, Chingeltei district, Ulaanbaatar city

Structure and technical calculation temperature, ⁰C

		Ci	alculation tem	perature, °C			
		Coldest temprature					
Station	l day	3 day	5 day	Airring	hottest temperature		
MUIS	-31.4	-30.3	-28.9	-25.0	26.4		

Temperature supply indices for the construction and technical calculation during winter time (⁰C)

Table II-5

Station	The		lays tempe oly, %	erature	The col	dest 1 day	temperatur %	e supply
	99.2	99.5	94	92	99.9	99.5	94	92
Buyant- Ukhaa	-41.8	-41.7	-39.4	-39.0	-43.3	-43.2	-41.5	-40.7

Air humidity and precipitation

	e	

	1			Precipita	ation			
Station	Warm season	Cold season	Annu al	In warm season	Maximum in a day	Year	Mont h	Day
Buyant- Ukhaa	50	72	248.8	236.5	74.9	1967	VI	27

Table II-7

Station					Mor	nth,wi	nter,a	nnual a	averag	ge spo	ed, n	ı/s		
	I	п	Ш	IV	V	VI	VII	VIII	IX	X	XI	XII	Winter	Annual
MUIS	0.6	0.9	1.5	2.2	2.1	1.8	1.5	1.2	1.4	1.2	0.9	0.5	0.7	1.3

2.3 Geological formation

In survey area distributed equally well graded gravel with clay and sand soil, weathered sandstone of poured soil from below, up and modern Quaternary eluvial-deluviam. In survey area spread silt soil is classified as a engineer geological element, physic mechanic characteristics defined and depth and distribution cross section shown.

2.4 Geomorphology characteristics and physic geological appearance, process

Survey area's relief is rugged character and general surface elevation between 1487.15-1496.75 m then slope decreased from north west to east south and generally move slowly slope formation. Survey area little bit exposed by engineering process and between current planning object and current kindergarden ravine road made by engineering process. In survey area, linear and field washed process shall be may occur.

2.5 Hydro-geological condition

Soil groundwater has not been occurred by 5 drill holes with 10.0 meter depth in survey area /dated April 17^{th} - 19^{th} 2017/. Permeability test was conducted on BH-3 in this site. Permeability K=0.116 cm/sec.

Engineer geological survey reportof new school construction area in 7th khoroo. Chingeltei district, Ulaanbaatar city

III. ENGINEERING-GEOLOGICAL CONDITIONS AND PHYSICAL ,MECHANICAL PROPERTIES

3.1 Soil engineer geological classification and formation

In survey area well-graded gravel with clay and sand /EGE-1/ distributed equally.

3.2 Soil physic mechanic characteristic

Depending on soil particle structure and physic mechanic characteristic classified to engineer geological 1 elements.

EGE-1. Well-graded gravel with clay and sand

Yellowish, up and modern Quaternary eluvial- deluviam origin /dpQIII-IY/, solid consistency well-graded with clay and sand.

Granulometric composition from the laboratory analysis of these soil samples includes: (%):

	Gravel	67.8%
	Sand	23.3%
	Silt	7.0%
	Clay	1.9%
Physical pr	operties indices of the soil:	
	 Natural moisture content 	5.5
	 Liquid limit 	25.37
	 Plastic limit 	18.94
	 Plastic indices 	6.43
	 Specific gravity, g/cm³ 	2.69
	 Wet density g/cm³ 	2.23
	 Dry density g/cm³ 	2.12
	 Porocity, % 	21.34
	 Porocity ratio 	0.272
	 Moisture content degree 	0.55
	 Consistency 	< 0

Normative and calculation indices of the mechanical properties:

According to the norm and regulations to create the construction groundwork - CCM 50-01-16 and Table I:

Normative value

•	Cohesion	C _n =14kPa
	Angle of internal friction	$\varphi_n = 45^0$
•	Deformation modulus	E=49MPa
Calculation val	lue:	
	Cohesion	Cn2=9.33Pa
	Angle of internal friction	$\phi_{n2}=39.13^{\circ}$
•	Calculated resistance	R ₀ =450
Calculation va	Deformation modulus lue: Cohesion Angle of internal friction	E=49MPa $C_{n2}=9.33Pa$ $\phi_{n2}=39.13^{0}$

According to CCM 50-01-16 and 5.3.6, well graded gravel elay and sand is D=3.50 and saturation of degree is S_r =0.55 which means it can create a weak bulging region.

Engineer geological survey reportof new school construction area in 7th khoroo. Chingeltei district, Ulaanbaatar city

Well graded gravel clay and sand seasonal freezing depth.

Earthwork of measuring, dig-up

The rock soil.-Rock/Sandstone /soil weathering zone - / K1/

In area of Sandstone weathering zone -/ $K_{\rm I}/$ distribute widely and stone distribution depth until 7.20-9.20m thickness and it shown in engineer-geological cross section. In survey area most part of color is light green grey and bigger than average unit, distributed mica sandstone

weathering zone. Sandstone physics indices: Weathered rock soil volume weight None weathered rock soil хадан ул volume weight Rock soil percentage of erosion /%/ Quality of interaction with water softened Dispersely condition Rock soil earthwork degree dig by manual: Soil of weathered rock

2.50-2.62 g/sm³ 2.65 g/sm³ 33.7-35.6 disperse by hammer Y

Ш



Engineer geological survey reportof new school construction area in 7th khoroo. Chingeltei district, Ulaanbaatar city

IV. Conclusion

- In survey area low blub engineer geological 1 types of element occurred, situated in one element by geomorphology, soil groundwater is not occurred and human engineering process is effected low grade area counted as a average engineer geological condition area.
- Parameters of calculation and main soil spread to area physic and mechanic characteristic normative are shown in section of Engineer Geological classification and soil Physic mechanic characteristic.
- Table IV-1 is shown soil blub level and earth work degree for distributed soil in survey area. Earth work degree counted as manually executed.

Table IV-1

Soil type	Earthworks degree	Bulging degree	Specific reactance om, m
Well-graded gravel with clay and sand	Ш	Weak bulging	4-40

4. Survey area is in 7 magnitude earthquake region.

 Soil groundwater has not been occurred by 5 drill holes with 10.0 meter depth in survey area /dated April 17th -19th 2017/. Soil ground water is minimum low level in April and it can be increased by rainfall.

6. Soil test is necessary after opening of building fundament galvanized.

Summary is written:

E. Uchral /Engineer/

A-128

Engineer geological survey reportof new school construction area in 7th khoroo. Chingeltei district, Ulaanbaatar city

Engineer geological survey reportof new school construction area in 7th khoroo. Chingeltei district, Ulaanbaatar city

V. Reference list

- CCM 50-01-16. Construction codes on designing of construction foundation Ulaanbaatar, 2016 y.
- CCM 23-01-09. Climate and geotechnical indices for the construction work Ulaanbaatar, 2009 y.
- 3. Seismic zone of Ulaanbaatar city. SC 1:10 000, 2015y.
- 4. "CG 11-107-11. Guideline of engineering geologic report and summary
- 5. "CCM 11-03-01 Contruction norm and regulation
- Инженерные изыскания встройтельсве (Спаровочнык) страниц таблиц -131, 1975года., зав.редакций Е.А.Ларина,
- 7. "Земляные работы" / СНИП-IV-5/
- 8. ASTM D 2487

Development of designs and	exploration surveys,	ENGINEERING GEODESY LLC

10

		VI. Borehole logs BOREHOLE-1	
Depth , m	10.0	Elevation, m	1496.75
Diameter , mm	168	Drilling date	2017.04.17
1. Top soil com	tained root of	plant.	0.00-0.20
			0.20
2. Yellowish w	ell-graded gra	ivel with clay and sand.	0.20-0.80
			0.60
3. Grey green s	andstone wea	thering area.	0.80-3.10
			2.30
4 Grey green s	andstone.		3.10-10.0
			6.90
		Soil groundwater not detected. /current date April 17 th 2017/ BOREHOLE-2	
Depth , m	10.0	Elevation, m	1496.25
Diameter , mm	168	Drilling date	2017.04.17
1. Top soil cont	tained root of	plant.	0.00-0.20
			0.20
2. Yellowish w	ell-graded gra	avel with clay and sand.	0.20-1.00
			0.80
3. Grey green s	andstone wea	thering area.	1.00-3.50
			2.50
4 Grey green s	andstone.		3.50-10.0
			6.50
		Soil groundwater not detected. /current date April 17 th 2017/ BOREHOLE-3	
Depth , m	10.0	Elevation, m	1487.15
Diameter , mm	168	Drilling date	2017.04.18
1. Filled up soil	L.		0.00-0.40
			0.40
2. Yellowish w	ell-graded gra	avel with clay and sand.	0.40-2.80
			2.40


Development of designs and exploration surveys, ENGINEERING GEODESY LLC


11


Grey green s	andstone wea	thering area.	2.80-5.00			
			2.20			
Grey green s		5.00-10.0				
			5.00			
		Soil groundwater not detected. /current date April 18 th 2017/				
		BOREHOLE-4				
epth, m	10.0	Elevation, m	1493.25			
iameter , mm	168	Drilling date	2017.04.18			
. Top soil con	tained root of	plant.	0.00-0.20			
			0.20			
Yellowish w	ell-graded gra	avel with clay and sand.	0.20-1.20			
	and have braced branch with only and when					
Grey green s	andstone wea	thering area.	1.20-3.80			
			2.26			
Grey green s	andstone.		3.80-10.0			
			6.20			
		Soil groundwater not detected, /current date April 18 th 2017/ BOREHOLE-5				
epth . m	10.0	Elevation, m	1490.25			
iameter, mm	168	Drilling date	2017.04.19			
. Filled up soi	Ú.		0.00-0.40			
			0.40			
. Yellowish w	ell-graded gra	avel with clay and sand.	0.40-2.00			
			1.60			
Grey green s	andstone wea	thering area.	2.00-4.60			
			2.60			
4 Grey green s	andstone.		4.60-10.0			
			5.40			
		Soil groundwater not detected. /current date April 19 th 2017/				
	ehole logs wr		D. Dashzeves			


Development of designs and exploration surveys, ENGINEERING GEODESY LLC


12











STANDARD PENETRATION TEST RESULT /SPT/





Engineer geological survey report of construction areaof 53th schoo	extension construction in 16th khoroo.
	Bayanzurkh district, Ulaanbaatar city

	Table of Contents
	GENERAL INFORMATION
	1.1 Survey basis
	1.2 Survey technique
2.	Survey condition of engineer geology5
3	2.1 Location
2	2.2 Climatic conditions
-	2.3 Geological formation6
3	2.4 Geomorphology characteristics and physic geological appearance, process
3	2.5 Hydro-geological condition
3.	ENGINEERING-GEOLOGICAL CONDITIONS AND PHYSICAL AND
M	ECHANICAL PROPERTIES
	3.1 Soil engineer geological classification and formation7
	3.2 Soil physic mechanic characteristic
4.	CONCLUSION10
5.	REFERENCE LIST
6.	BOREHOLE LOGS

APPENDIXES

 LOCATION OF BOREHOLES, SC 1:1000, APPENDIX №1
 ENGINEERING-GEOLOGICAL SECTION, APPENDIX №2 SC Horizontal 1:100

Vertical 1:1000

3

.

No. 53 School (B-1) construction site, Bayanzurkh District

3. STANDARD PENETRATION TEST RESULT APPENDIX №4

Engineer geological survey report of construction area of 53th school extension construction in 16th khoroo. Bayanzurkh district, Ulaanbaatar city

1. GENERAL INFORMATION

1.1 Survey basis

Engineer Geodesy LLC /Drawing and geological survey company/ completed engineer geological survey work of construction area of 53th school extension in Ulaanbaatar city, Bayanzurkh district, 16th khoroo by MECSS tender in April 13th-26th 2017 and survey planned and completed as their requested.

1.2 Survey technique

Team with drill master Enkh-Amagalan, assistant worker Lkhagvatseren.N is executed the drill work by UGB-1BC equipment, 2 boreholes 10.0 meters depth, 20.0 t/m column drilling, to locate and define underground water depth, characteristics, construction fundament pressure effective soil depth and distribution, according to the plan and SNIP 11-03-01 in survey area engineer geological survey work.



Soil physic and mechanic characteristics been defined by taking 12 pieces of samples from drilled boreholes in soil study laboratory. According to ASTM standard, Tsagaandarkhi.L /laboratory chief/, Ganchimeg.G /laboratory engineer/ and bayarmagnai.A /laboratory assistant/ are summarized the result and tabled soil analyze in soil study laboratory of Engineer Geodesy LLC /with guaranteed number of TL-78 from Standardization and Metrology department, satisfied the standard of ISO/IEC 17025:2005, MNS ISO/IEC 17025:2005/. Engineer Geologist Uchral.E processed the engineer geological report to create procedural plan which is made by comparison of field survey material and laboratory analyze result.

Source materials related to survey work stored in archive of Engineering Geodesy LLC.

Engineer geological survey report of construction areaof 53th school extension construction in 16th khoroo. Bayanzurkh district, Ulaanbaatar city

II. Survey condition of engineer geology

2.1 Location

Ulaanbaatar city, Bayanzurkh district, 16th khoroo, existing 53rd school building extension construction plan



Drawing №1. Survey area of location

2.2 Climatic conditions

Ulaankhuaran, MUIS climate stations indices and CCM 23-01-09 standard "Climate and geotechnical indices for the construction work" have been used for the climate indices of this site, and showed in tables.

Annual and monthly average air temperature, °C

Station	Month								Annual				
	I	II	III	IV	V	VI	VII	VIII	IX	X	XI	XII	
Ulaan- khuaran	-21.7	-18.7	-8.0	0.5	8.7	14.7	16.5	14.7	8.2	-0.5	-11.3	-20.1	-1.7

maximum		

	Table	II-2
11	S.200	

Absolute max	Date	July avarege
33.5	1969.VI.20	30.2

	Prosolute III	Table	
Station	Absolute min	Date	Jan avarege
Ulaankhuaran	-36.0	1988.1.23	-31.9

Development of designs and exploration surveys, ENGINEERING GEODESY LLC

Development of designs and exploration surveys, ENGINEERING GEODESY LLC

Engineer geological survey report of construction area of 53th school extension construction in 16th khoroo. Bayanzurkh district, Ulaanbaatar city

Structure and technical calculation temperature, ⁰C

					1 able 11-4
		C	alculation tem	perature, °C	
		One day during			
Station	1 day	3 day	5 day	Airring	hottest temperature
Ulaankhuaran	-33.7	-32.7	-31.6	-23.0	24.7

Temperature supply indices for the construction and technical calculation during winter time (%C)

Table II-5

Table II 4

Station	The		lays tempe bly, %	erature	The coldest 1 day temperature supply %			
	99.2	99.5	94	92	99.9	99.5	94	92
Buyant- Ukhaa	-41.8	-41.7	-39.4	-39.0	-43.3	-43,2	-41.5	-40.7

Air humidity and precipitation

	Table	11-6

Table IT 7

Station	Precipitation								
	Warm season	Cold season	Annu al	In warm season	Maximum in a day	Year	Mont h	Day	
Ulaankhua ran	67	72	245.2	232.5	68.6	1966	VII	- 11	

Annual and monthly average wind speed

dis dista	1	I II III V V VI VII VIII IX X XI XII winter Annual 0.6 0.9 1.5 2.2 2.1 1.8 1.5 1.2 1.4 1.2 0.9 0.5 0.7 1.3														
Station	1	II	ш	IV	V	VI	VII	VIII	IX	X	XI	XII	winter	Annual		
MUIS	0.6	0.9	1.5	2.2	2.1	1.8	1.5	1.2	1.4	1.2	0.9	0.5	0.7	1.3		

2.3 Geological formation

In survey area distributed equally silty sand with gravel soil, clayey with sand soil and sandy lean clay origin of filled up soil from below, up and modern Quaternary diluviam-proluvial. In survey area spread silt soil is classified as a engineer geological element, physic mechanic characteristics defined and depth and distribution cross section shown.

2.4 Geomorphology characteristics and physic geological appearance, process

Survey area is located in low height slope of mountain. Survey area is gradually slope from western north to eastern south, average height is 1318.50-1320.00 meters and height difference is 1.50 meter. In survey area much engineering work has been done. Physic Geology appearance, processes are not occurred.

2.5 Hydro-geological condition

Soil groundwater has not been occurred by 2 drill holes with 10.0 metr depth in survey area /dated April 13th 2017/. Soil groundwater is minimum low level in April and it can be increased by rainfall.

Engineer geological survey report of construction areaof 53th school extension construction in 16th khoroo. Bayanzurkh district, Ulaanbaatar city

III. ENGINEERING-GEOLOGICAL CONDITIONS AND PHYSICAL AND MECHANICAL PROPERTIES

3.1 Soil engineer geological classification and formation

In survey area silty sand with gravel soil /EGE-1/, clayey with sand soil /EGE-2/ and sandy lean clay soil /EGE -3/ distributed equally.

3.2 Soil physic mechanic characteristic

Depending on soil particle structure and physic mechanic characteristic classified to engineer geological 3 elements.

EGE-1. Silty sand with gravel (dpQm-w) /SC/

Brownish yellow, up and modern Quaternary diluviam-proluvial origin /dpQ_{III-IV}/, low moist silty sand with gravel soil.

Granulometric composition from the laboratory analysis of these soil samples includes: (%):

	 Gravel 	17.9
	Sand	66.7
	Silt	13.0
	Clay	2.5
ical pr	roperties indices of the soil:	
	 Natural moisture content 	2.86
	 Specific gravity, g/sm³ 	2.67
	 Wet density g/sm³ 	2.25
	 Dry density g/sm³ 	2.18
	 Porocity, % 	18.26
	 Porocity ratio 	0.223
	 Moisture content degree 	0.342

Normative and calculation indices of the mechanical properties:

According to the norm and regulations to create the construction groundwork - CCM 50-01-16 and Table I:

Normative value

Physic

 Cohesion 	C _n =26kPa
 Angle of internal friction 	$\phi_n = 40^0$
 Deformation modulus 	E=39MPa
Calculation value:	
 Cohesion 	Cn2=5.33Pa
 Angle of internal friction 	$\phi_{n2}=30.91^{\circ}$
 Calculated resistance 	R ₀ =250
According to CCM 50-01-16 and 5.3.6. Gravel w	ith clavey is D=14 76 and

According to CCM 50-01-16 and 5.3.6, Gravel with clayey is D=14.76 and saturation of degree is S₁=0.342 which means it can create a weak bulging region.

Silty sand with gravel soil seasonal freezing depth	3.1 m
Earthwork of measuring, dig-up	I

Se	Bayanzurkh district, Ulaanbaatar city	
EGE-2. Clayey with sand soil (dpQm-rv) /SC/		
Clayey with sand soil is red-brown, modern q	uaternary age, diluviam-proluvial origin	
(dpQm.iv) solid consistency.		
Granulometric composition from the laboratory analy	sis of these soil samples includes: (%):	
 Gravel 	65.1	
Sand	20.3	
• Silt	8.4	
Clay	6.2	
Physical properties indices of the soil:		
 Natural moisture content 	7.5	
Liquid limit	27.1	
Plastic limit	15.6	
 Plastic indices 	11.5	
 Specific gravity, g/cm³ 	2.72	
 Wet density g/cm³ 	2.07	
 Dry density g/cm³ 	1.93	
 Porocity, % 	29.08	
 Porocity ratio 	0.411	
 Moisture content degree 	0.490	
 Consistency 	< 0.0	
Wards and a state of the state	boot doe	
Normative and calculation indices of the mechanical		
According to the norm and regulations to create the	construction groundwork - CCM 50-01-16	
and Table 1:		
Normative value:		
 Cohesion 	$C_n = 47.0 kPa$	
 Angle of internal friction 	$\varphi_n = 25^0$	
 Deformation modulus 	E=47MPa	
Calculation value:		
Cohesion	Cu2=31.33kPa	
 Angle of internal friction 	$\phi_{n2}=21.74^{0}$	
 Calculated resistance 	R ₀ =300	
According to CCM 50-01-16 and 5.3.5: Clayey with	a sandy /EGE-2/ is Rr=0.49 which means it	
can't measurable a bulging freezing region.		
Clayley with sand soil seasonal freezing depth	2.6 m	
Earthwork of measuring, dig-up	1	
EGE-3. Sandy lean clay /CL/		
	quaternary age, delivuim-proluvial origin	
(dpQmiiv) solid consistency.		
Granulometric composition from the laboratory analy	sis of these soil samples includes: (%):	
Gravel	14.0	
	23.8	
 Sand 	23.8	

8

Development of designs and exploration surveys, ENGINEERING GEODESY LLC

• Clay 12.4 Physical properties indices of the soil: • Natural moisture content 21.0 • Liquid limit 37.2 Plastic limit 19.9 · Plastic indices 17.3 Specific gravity, g/см³ 2.73 • Wet density g/cm3 1.97 • Dry density g/cm3 1.63

Engineer geological survey report of construction area of 53th school extension construction in 16th khoroo. Bayanzurkh district, Ulaanbaatar city

 • Porocity, %
 40.35

 • Porocity ratio
 0.680

 • Moisture content degree
 0.831

 • Consistency
 <0.0</td>

Normative and calculation indices of the mechanical properties:

According to the norm and regulations to create the construction groundwork - CCM 50-01-16 and Table 1:

Normative value:	
 Cohesion 	$C_n = 63.0 \text{kPa}$
 Angle of internal friction 	$\phi_n = 20^0$
 Deformation modulus 	E=23MPa
Calculation value:	
Cohesion	Cn2=42.0kPa
 Angle of internal friction 	$\varphi_{n2}=17.39^{0}$
 Calculated resistance 	R0=400
According to CCM 50-01-16 and 5.3.5: Clayey v can't weak a bulging freezing region.	with sandy /EGE-3/ is $R_f=0.15$ which means it
Sandy lean clay soil seasonal freezing depth	2.6 m

I.

9

Earthwork of measuring, dig-up

Engineer geological survey report of construction areaof 53th school extension construction in 16th khoroo. Bayanzurkh district, Ulaanbaatar city

IV. CONCLUSION

- In survey area low and average blub engineer geological 3 types of element occurred, situated in one element by geomorphology, groundwater is not occurred and human engineering process is effected pretty much etc area counted as a average engineer geological condition area.
- Parameters of calculation and main soil spread to area physic and mechanic characteristic normative are shown in section of Engineer Geological classification and soil Physic mechanic characteristic.
- Table IV-1 is shown soil blub level and earth work degree for distributed soil in survey area. Earth work degree counted as manually executed.

Хүснэгт IV-1

10

Soil type	Earthwork degree	Bulging degree	Spectic reactance om, m				
Silty sand with gravel	r	Weak bulging	Dry condition: 2000-10000 Watery condition: 200-600				
Clayey with sand	1	Measurable bulging	40-80				
Sandy lean clay	1	Weak bulging	4-40				

4. Survey area is in 8 magnitude carthquake region.

- Soil groundwater has not been occurred by 2 drill holes with 10.0 meter depth in survey area /dated April 13th 2017/, Tilt soil ground water is minimum low level in April and it can be increased by rainfall.
- 6. Soil test is necessary after opening of building fundament galvanized.

Summary is written

E. Uchral /Engineer-geologist/

Engineer geological survey report of construction areaof 53th school extension construction in 16th khoroo. Bayanzurkh district, Ulaanbaatar city


4. REFERENCE LIST

- CCM 50-01-16. Construction codes on designing of construction foundation Ulaanbaatar, 2016 y.
- CCM 23-01-09. Climate and geotechnical indices for the construction work Ulaanbaatar, 2009 y.
- CCM 22.01.01/2006. Construction codes on construction planning at seismic zones of Mongolia Ulaanbaatar, 2006 y
- 4. "CG 11-107-11. Guideline of engineering geologic report and summary
- 5. "CCM 11-03-01 Contruction norm and regulation
- Инженерные изыскания встройтельсве (Спаровочнык) страниц таблиц -131, 1975года., зав.редакций Е.А.Ларина,
- 7, "Земляные работы" / СНИП-IV-5/
- 8. ASTM D 2487

Development of designs and exploration surveys, ENGINEERING GEODESY LLC

		5. BOREHOLE LC Borehole-1	OGS					
epth , m	10.00	Elevation, m	1318.60					
iametr , mm	168	Drilling date	2017.04.13					
. Filled up sc	il.		0.00-0.60					
			0.60					
Brownish c	olor, silty sand	with gravel.	0.60-2.30					
			1.70					
Red-brown	color, clayey w	rith sand soil.	2.30-3.80					
			1.50					
Red-brown	color, sandy le	an clay soil.	3.80-10.00					
			6.20					

		Borehole-2	
Depth , m	10.00	Elevation , m	1319 59
Diametr , mm	168	Drilling date	2017.04.13
1. Filled up so	il.		0.00-0.90
2. Red-brown	color, clayey w	0.90 0.90-7.00	
a . n. 11			6.10
3. Red-brown	color, sandy le	an clay soil.	7.00-10.00 3.00




Borehole logs written by:


D. Batbayar


LOCATION OF

HOLE










A-140

	6 EN	GINE	- KI	NG G	EODI	ESYI	rc							ABC														4	MNS 15	TL-78 D/IEC		:2007					
	4	Objec	t	E	igine	er geo	logic	at sur	vey re	port o	of 531	h sch	ool ex	tensio	n cou	struc	tion a	rea in	16th	khor	00, Ba	yanzur	kh dist	rict, U	laanba	atar c	ity			Start da Fintsh d					2017.04		
1	×	[10]		_	1	0	rain siz	e analy	nis, (m	m)			-			Hydro	metr; [mm]ª4	2		- 1					(Pl	astic ind	ex			÷.,	2	(ev)	CNO.			3
	Borehole number	depth of sample	75.0	37.5	10	9.5	4.75	2.36	1.18	09'0	0.300	0.150	\$20.0	0.035	0.022	0.012	600'0	0.006	0.003	0.001		Gravel	Sand	Silt	Clay	ί ι .	PL.	PI	Cu	cc	Natural moistu pontent(W), 5	Spectic gravy e	Wet density, p. r	Dry density, n. r	Porocity, n. %	Porocity ratio,	
	-	-	-	-			-				-			-	-			EGE	1. Silty	y sand	with gra	wel		_					-	-	-	-	_		_		-
	BH-1	Ĩ,0	0,0	0.0	0.0	0,0	18.3	28.8	7,5	11.1	9.9	5.8	3.7	3,4	2,8	1.3	2.1	1.8	1.4	1.1	100.0	18.3	66.8	12.4	2,5	1.0	inelastic		107.69	3.887	2.87	2.67	2,24	2,18	18.45	0.226	0
1	BH-1	2.0	0,0	0.0	0.0	0.0	17.5	27.8	7,3	12.1	9.2	6.0	4.1	4.0	3.0	2.6	3.0	1.9	15	1.0	1003)	173	66.5	13.5	2.5		inelastic	11	121.74	14.91	2.85	2.67	2.25	2.19	18.07	0.220	0
V	Avares		0.0	0.0	0,0	0.0	17.9	28.3	7.8	11.6	9.6	5.9	3.9	3.7	2,9	2,5	2.1	1.9	1.5	11	100.0	17.9	66.7	13.0	2,5	100	ipelastic		114.72	9.40	2,86	2,67	2.25	2,18	18.26	0.223	1
b	solute 1	nax	0,0	0.0	0.0	0.0	18.3	28.8	15	12.1	9.9	6.0	4.1	4.0	3.0	1,5	4.1	1.9	15	14	100.0	18,3	66.8	13.5	2,5	1116	inelastic		121,74	14.91	2,87	2.67	3.25	2.19	18.45	0.226	1
	solute	min	0.0	0.0	0,0	0.0	17.5	27.8	7.3	11.1	9.2	5.8	3.7	3.4	2.8	2.3	2.0	1.8	1.4	1.0	100.0	17.5	66.5	12.4	2.5		inelastic		107.69	3.89	2.85	2.67	2.24	2.18	18.07	0.220	t

Laboraut:

A. Bayarmagnai



Borehole	Depth	0-15cm	15-30c	m	30-45c	m	N
number	of SPT (m)	Blow counts	Real penetration thickness(cm)	Blow counts	Real penetration thickness(cm)	Blow counts	Blow
	1.0	25	15	31	15	42	73
	2.0	28	15	36	15	46	82
	3.0	15	15	18	15	22	40
	4.0	17	15	18	15	23	41
	5.0	14	15	16	15	20	36
BH-1	6.0	18	15	21	15	23	44
	7.0	12	15	14	15	15	29
	8.0	10	15	13	15	15	28
	9.0	14	15	17	15	21	38
	10.0	15	15	16	15	15	31
	2.0	14	15	17	15	18	35
	3.0	16	15	19	15	23	42
	4.0	11	15	14	15	13	27
	5.0	12	15	16	15	19	35
	6.0	15	15	18	15	20	38
BH-2	7.0	9	15	13	15	14	27
	8.0	7	15	10	15	12	22
	9.0	8	15	11	15	-11	22
	10.0	10	15	12	15	14	26

E.Uchral

STANDARD PENETRATION TEST RESULT /SPT/

Prepared by:

A-142

-	district, Ulaanbaatar ci
	Table of Contents
I.	GENERAL INFORMATION
1.1 Sur	rvey basis
1.2 Sur	vey technique
п.	Survey condition of engineer geology
2.1 Los	cation
2.2 Cli	matic conditions
2.3 Geo	ological formation
2.4 Ge	omorphology characteristics and physic geological appearance, process
2.5 Hy	dro-geological condition
2.6 Pc	rmafrost /PFT/
ш.	ENGINEERING-GEOLOGICAL CONDITIONS AND PHYSICAL AND MECHANICAL PROPERTIES
3.1 Soil	l engineer geological classification and formation
3.2 Soi	l physic mechanic characteristic
IV.	Conclusion
v.	Reference list
VI.	Borehole logs

APPENDIXES

1.	LOCATION OF BOREHOLES, SC 1:1000, (APPEN	DIX №1)	
2.	ENGINEERING-GEOLOGICAL SECTION, (APPEN	NDIX Nº2)	
	SC	Horizontal	1:100
		Vertical	1:1000
3.	SOIL PHYSIC MECHANIC CHARACTERISTIC GI	ENERAL TAB	LE
		(APPENDI	X №3)
4.	STANDARD PENETRATION TEST RESULT (APP	ENDIX Nº4)	

Development of designs and exploration surveys, ENGINEERING GEODESY LLC

"ENGINEERING GEODESY_ LLC Uhanbaara: 16831 Bayangd district, 6 s: khoroo 10a mircu 6 5a building A corpus Phone/fax: 77:278899 Mobile: 99095839, 91911484 Web: www.geo-mongol.mn B36: www.geo-mongol.mn

ENGINEER GEOLOGICAL SURVEY REPORT OF CONSTRUCTION AREA OF 109th SCHOOL EXTENSION CONSTRUCTION IN 3rd KHOROO, NALAIKH DISTRICT, ULAANBAATAR CITY / Detail design stage /

Approved by: Director Prepared by: Engineer geologist

Archive 17/034

E.Uchral

TS.Bileg

Ulaanbaatar city 2017

A-143

3

.

No. 109 School (B-2) construction site, Nalaikh District

Engineer geological survey report of construction area of 109th school extension construction in 3rd khoroo. Nalaikh district, Ulaanbaatar city

I. GENERAL INFORMATION

1.1 Survey basis

Engineer Geodesy LLC /Drawing and geological survey company/ completed engineer geological survey work of construction area of 109th school extension in Ulaanbaatar city, Bayanzurkh district, 3rd khoroo by MECSS tender in April 17th-28th 2017 and survey planned and completed as their requested.

1.2 Survey technique

Team with drill master Enkh-Amagalan, assistant worker Lkhagvatseren.N is executed the drill work by UGB-1BC equipment, 2 boreholes 10.0 meters depth, 40.0 t/m column drilling,to locate and define underground water depth, characteristics, construction fundament pressure effective soil depth and distribution, according to the plan and SNIP 11-03-01 in survey area engineer geological survey work.



Soil physic and mechanic characteristics been defined by taking 24 pieces of samples from drilled boreholes in soil study laboratory. According to ASTM standard, Tsagaandarkhi.L/laboratory chief/, Ganchimeg.G /laboratory engineer/ and bayarmagnai.A /laboratory assistant/ are summarized the result and tabled soil analyze in soil study laboratory of Engineer Geodesy LLC /with guaranteed number of TL-78 from Standardization and Metrology department, satisfied the standard of ISO/IEC 17025:2005, MNS ISO/IEC

17025:2005/. Engineer Geologist UchraLE processed the engineer geological report to create procedural plan which is made by comparison of field survey material and laboratory analyze result.

Source materials related to survey work stored in archive of Engineer Geodesy LLC.

Engineer geological survey report of construction area of 109th school extension construction in 3rd khoroo. Nalaikh district, Ulaanbaatar city

II. ENGINEERING GEOLOGICAL INVESTIGATED CONDITION

2.1 Location


The extension construction of school 109 was planned by connect to the construction of 109th school's left side which located in 3rd khoroo, Nalaikh district, Ulaanbaatar .



Drawing 1. Survey area of location 2.1 Climatic conditions

Khurel-togoot, Terelj climate stations indices and CCM 23-01-09 standard "Climate and geotechnical indices for the construction work" have been used for the climate indices of this site,

and showed in tables. Annual and monthly average air temperature, °C



Development of designs and exploration surveys, ENGINEERING GEODESY LLC

Engineer geological survey report of construction area of 109th school extension construction in 3rd khoroo.Nalaikh district, Ulaanbaatar city

 Khurel-togoot
 -36.7
 1966 L16
 -30.3

 Structure and technical calculation temperature, ⁰

Table II-4

			Calculation	temperature	_ °C
Station		One day during			
	1 day	3 day	5 day	Airring	hottest temperature
Terelj	-34.8	-33.1	-31.5	-26.7	23.9

Air humidity and precipitation

0.000	Precipitation									
Station	Warm	Cold season	Annual	In warm season	Maximum in a day	Year	Month	Day		
Terelj	56	75	372.9	354.9	55.5	1994	VIII	04		

Annual and monthly average wind speed

Table II-6

Station	1.0	1	100		Mo	nth, wi	nter, a	verage s	peed o	f year,	m/s			
	1	п	m	IV	V	VI	VII	VIII	IX	X	XI	XII	winter	annual
Terelj	0.8	1.2	1.8	2.6	2.3	1.5	1.2	1.2	1.6	1.5	1.1	0.8	0.9	1.5

In survey area distributed equally silty sand with gravel soil, clayey with sand soil and sandy lean clay origin of filled up soil from below, up and modern Quaternary diluviam-proluvial. In survey area spread silt soil is classified as a engineer geological element, physic mechanic characteristics defined and depth and distribution cross section shown.

2.4 Geomorphology characteristics and physic geological appearance, process

Survey area is located on the geomorphology's one element and surface's elevation is 1481.04-1481.85 meters, height difference is 0.81 meter. The survey area is went down from eastern north to western south and it's surface is being generally flat. In survey area permafrost soil was spreaded, because seasonal melting process is being dominated.

2.5 Hydro-geological condition

Survey area is located on the geomorphology's one element and surface's elevation is 1481.04-1481.85 meters, elevation's difference is 0.81 meters. /April, 17th, 2017/. Soil ground water is minimum low level in April and it can be increased by rainfall. And soil ground water increase depends on seasonal melting process. Permeability test was conducted on BH-4 in this site. Permeability K=7.1*10³ cm/sec.

2.6 Permafrost /PFT/

Nataikh district belong in zone which discontinuities distribution permafrost soil. In planning building area, permafrost soil depth started from 4 meter and Silty sand with gravel soil is permafrost then with solid texture, low ice form hard to dry permafrost. Permafrost soil 10 meter's depth temperature is $(-0.5^{\circ}c)$. Top boundary of permafrost soil connect to directly depth of freezing and melting. Freezing temperature of soil is $-0.1^{\circ}C$.

Development of designs and exploration surveys, ENGINEERING GEODESY LLC

Engineer geological survey report of construction area of 109th school extension construction in 3rd khoroo Nalaikh district, Ulaanbaatar city

III. ENGINEERING-GEOLOGICAL CONDITIONS AND PHYSICAL, MECHANICAL PROPERTIES

3.1 Soil engineer geological classification and formation

In survey area, from light yellowish to brown yellow color silty sand with gravel soil/EGEl/distributed. Soil physical mechanical properties determined and shown by drawing section of distribution and thickness. Then soil type is 2 class which first class is seasonal freezing and melting silty sand with gravel soil, second class is permafrost soil and determined physical mechanical properties indices one by one.

3.2 Soil physic mechanic characteristic

Depending on soil particle structure and physic mechanic characteristic classified to engineer geological 1 elements.

EGE-1. Silty sand with gravel soil /seasonal freezing and melting/

From light yellowish to brown color, top and modern quaternary age, delivuim-proluvial origin (dpQm:tv) solid consistency, with moisture and this soil that silty sand with gravel soil. Brown color clay sand with gravel soil lens layer 4.80-5.00 meter.

Granulometric composition from the laboratory analysis of these soil samples includes: (%):

 Gravel 	39.4
• Sand	44.6
Silt	13.5
Clay	2.6
Physical properties indices of the soil:	

•	Natural moisture content	7.8
	Specific gravity, g/sm3	2.67
•	Wet density g/sm3	2.26
	Dry density g/sm3	2.10
	Porocity, %	21.47
	Porocity ratio	0.275
	Moisture content degree	0.719

According to the norm and regulations to create the soil mechanical properties - BNaR 50-01-16 and Table I Normative value

1101111	arre value	
	Cohesion	$C_n = 2.0$ кПа
	 Angle of internal friction 	$\varphi_n = 40^0$
	 Deformation modulus 	E=45MIIa
Calcu	lation value:	
	Cohesion	Cn2= 1.33 kPa
	 Angle of internal friction 	$\varphi_{n2} = 36.0^{-0}$
	 Calculated resistance 	$R_0 = 500 \text{ kPa}$

Engineer geological survey report of construction area of 109th school extension construction in 3rd khoroo.Nalaikh district, Ulaanbaatar city

According to CCM 50-01-16 and 5.3.2, Silty sand with gravel soil is normalize by none swellings. Silty sand with gravel soil merge directly upper boundary of PFT soil's seasonal melting depth . Earthwork grade dig by manually III

IGE-1a. Silty sand with gravel soil /with PFT /

From light yellowish to brown color, top and modern quaternary age, delivuim-proluvial origin(dpQmIv) solid consistency, saturated with water this soil that silty sand with gravel soil.

Granulometric composition from the laboratory analysis of these soil samples includes: (%):

 Gravel 	38.6
Sand	45.1
Silt	13.5
Clay	2.8

Physical properties of PFT soil:

1.	Total moisture Wc=Wr	0.121
2.	Permafrost soil's pore filled grade by water and ice	0.93
3.	Sum of ice - same of sum moisture	$W_c = M_c$
4.	Melting factor	A=0.0099

Engineer geological survey report of construction area of 109th school extension construction in 3rd khoroo, Nalaikh district, Ulaanbaatar city

IV. CONCLUSION

- In survey area low and average blub engineer geological 1 types of element occurred, groundwater not detected, filled up ground spread vary thickness, permafrost /PFT/ soil is same and it is related to hard condition area for engineer-geology
- Base soil in area which physics and mechanical properties indices of calculation and norm is shown in "ENGINEERING GEOLOGICAL CLASSIFICATION AND PHYSICAL-MECHANICAL PROPERTIES OF SOIL" chapter.
- Table IV-1 is shown soil blub level and earth work degree for distributed soil in survey area. Earth work degree counted as manually executed.

Table IV-1

Soil type	Earthrocks degree	Bulging degree	Specific reactance om, m
Silty sand with gravel soil	ш	None swellings	Dry condition: 2000-10000 Wet condition: 200-600

4. Survey area is in 7 magnitude earthquake region.

5. In survey area, soil groundwater has been occurred in 4 drill holes with 10 meter depth /dated April 17th ,2017/. Soil ground water is minimum low level in April and it can be increased by rainfall. And soil ground water increase depends on seasonal melting process.

6. Soil test is necessary after opening of building fundament galvanized.

Summary is written:

Uchral.E / Engineer-geologist/

Engineer geological survey report of construction area of 109th school extension construction in 3rd khoroo.Nalaikh district, Ulaanbaatar city Engineer geological survey report of construction area of 109th school extension construction in 3rd khoroo Nalaikh district, Ulaanbaatar city

VI. BOREHOLE LOGS

Borehole-1

Dep	th , m	10.00	Elevation, m	1481.85
Dia	neter , mm	168	Drilling date	2017.04.17
1.	Filled up soil	color is dark g	gray and contained building waste.	0.00-0.50
				0.50
2.	0.50-10.0			
	that silty sand	with gravel se	bil	9.50
	Dia	2. From light ye	Diameter, mm 168 1. Filled up soil color is dark g 2. From light yellowish to bro	Diameter, mm 168 Drilling date 1. Filled up soil color is dark gray and contained building waste.

Soil groundwater not detected. PFT soil detected at 4.00 meter. /current date April 17th 2017/

Borehole-2

Depth , m 10.0		Elevation, m	1481.15				
Diameter, mm	168	Drilling date	2017.04.17				
1. Filled up soil	0.00-0.60						
	From light yellowish to brown color with moisture and this soil that silty sand with gravel soil.						
		Soil groundwater not detected. PFT soil detected at 4.00 meter. /current date April 17 th 2017/					
		Borehole-3					
Depth , m	10.00	Absolute elevation , m	1481.04				

Dep	oth , m	10.00	Absolute elevation , m	1481.04	
Dian	meter, mm	168	Drilling date	2017.04.17	
ì,	Filled up soil	color is dark	gray and contained building waste	0.00-0.60	
2.	From light ye that silty sand	0.60 0.60-10.0 9.40			
			Soil groundwater not detected.		
		I	PFT soil detected at 4.00 meter. /current date April 17 th 2017/		

10 Development of designs and exploration surveys, ENGINEERING GEODESY LLC

11


V. REFERENCE LIST

- CCM 50-01-16. Construction codes on designing of construction foundation Ulaanbaatar, 2016 y.
- CCM 23-01-09. Climate and geotechnical indices for the construction work Ulaanbaatar, 2009 y.
- 3. Seismic zones of Nalaikh. SC 1:34000, 2015y.
- 4. "CG 11-107-11. Guideline of engineering geologic report and summary
- 5. "CCM 11-03-01 Contruction norm and regulation
- 6. Инженерные изыскания встройтельсве (Спаровочнык) страниц таблиц -
- 131,1975года., зав.редакций Е.А.Ларина,
- 7. "Земляные работы" / СНИП-IV-5/


8. ASTM D 2487




			Borehole-4			
Depth .		10.00	Elevation , m	1481.3	20	
22.0						
Diamet	er, mm	168	Drilling date:	2017.0	04.17	
1. F	illed up soil c	color is dark	gray and contained building waste.	-	00-0.70	
					0.70	
			wn color with moisture and this soi	_	70-4.80	
th	at silty sand	with gravel s	011.		4.10	
3. B	rown color c	lay sand with	h gravel soil lens layer.	4.8	80-5.10	
					0.30	
			wn color with moisture and this soi	-	10-10.0	
th	nat silty sand	with gravel s	011.		4.90	
			Soil groundwater not detected.			
			FT soil detected at 4.00 meter. /current date April 17 th 2017/			
		Borehole log	25 written by: E.t	Jchral		to an adverse of
		Borehole log	25 written by: E.U	Jchral		Contract.
		Borehole loj	es written by: E.t	Jehral		




A-148





STANDARD PENETRATION TEST RESULT /SPT/

Borehole	Depth	0-15cm 15-30cm			30-45c	N	
number	of SPT (m)	Blow counts	Real penetration thickness(cm)	Blow counts	Real penetration thickness(cm)	Blow counts	Blow counts
	1.0	29	15	48	8	50	98/23cm
	2.0	32	15	45	10	50	95/25cm
	3.0	35	15	44	8	50	94/23em
	4.0	28	15	46	11	50	96/26cm
	5.0	33	15	49	9	50	99/24em
BH-1	6.0	28	15	42	13	50	92/28cm
	7.0	24	15	36	14	50	86/29cm
	8.0	28	15	40	12	50	90/27cm
	9.0	30	15	46	9	50	96/24em
	10.0	34	15	47	7	50	97/22cm
	1.0	33	15	46	9	50	96/24cm
	2.0	30	15	41	11	50	91/26cm
	3.0	28	15	42	13	50	92/28cm
	4.0	35	15	48	8	50	98/23em
	5.0	31	15	47	7	50	97/22cm
BH-2	6.0	28	15	44	10	50	94/25cm
	7.0	30	15	45	9	50	95/24cm
	8.0	32	15	43	11	50	93/26cm
	9.0	29	15	46	8.8	50	96/23.8cm
	10.0	36	15	50	6	50	100/21cm
	2.0	31	15	44	8	50	94/23cm
	3.0	35	15	48	6.5	50	98/21.5cm
	4.0	37	15	50	6	50	100/21em
	5.0	32	15	49	7	50	99/22cm
	6.0	29	15	45	10	50	95/25cm
BH-3	7.0	27	15	40	8	50	90/23cm
	8.0	31	15	47	9	50	97/24cm
	9.0	33	15	45	8	50	95/23cm
	10.0	30	15	42	10.5	50	92/25.5en
	1.0	33	15	47	7	50	97/22cm
	2.0	31	15	44	10	50	94/25cm
	3.0	36	15	47	9.3	50	97/24.3 cm
	4.0	35	15	49	8	50	99/23cm
BH-4	6.0	30	15	45	12	50	95/27cm
	7.0	29	15	41	11	50	91/26cm
	8.0	30	15	46	9	50	96/24cm
	9.0	34	15	48	7	50	98/22cm
	10.0	33	15	47	9	50	97/24cm



A-150



7. References

No.	Document title	Medium	Issued yr	Issuing agency
1	Mongolia Sustainable Development Vision 2030	Electric data	2016	Parliament of Mongolia
2	Action Program of the Government of Mongolia for 2016-2020	Electric data	2016	Parliament of Mongolia
3	State Education Policy 2014-2024 (in Mongolian)	Electric data	2014	Parliament of Mongolia
4	Educational Quality Reform Policy 2012-2016 (in Mongolian)	Electric data	2013	MECS
5	Statistical Yearbook- Eduction and Science 2015-16	Booklet	2016	MECS
6	Statistics of General Education Schools 2016-17 (in Mongolian)	Electric data	2017	MECSS
7	UBC Education Statistics 2016-17 (in Mongolian)	Electric data	2017	UBC Education Dept.
8	UBC Education Statistics 2015-16 (in Mongolian)	Electric data	2016	UBC Education Dept.
9	Mongolian Statistical Yearbook 2015	Electric data	2016	NSO
10	Pupulation by district/khoroo and type of dwelling 2016 (in Mongolian)	Electric data	2017	UBC Statistical Division
11	Population by single age 2016 (in Mongolian)	Electric data	2017	UBC Statistical Division
12	Future development challenges in Mongolia: Multi-state population projections by age, sex and education	Electric data	2013	IUSSP-International Population Conference
13	Mongolia State Budget 2017 (in Mongolian)	Electric data	2016	Miinstry of Finance
14	Mongolia State Budget 2016 (in Mongolian)	Electric data	2015	Miinstry of Finance
15	Ulaanbaatar City Budget 2017 (in Mongolian)	Electric data	2016	Miinstry of Finance
16	Needs for new kindergartens, schools, dormitories and gyms and options to meet those needs-Policy Project	Booklet	2012	MECS
17	School location map of General Education Schools and Kindergartens (in Mongolia)	Electric data	—	UBC Education Department
18	Model Blueprints of General Education Schools (in Mongolian)	Electric data	—	Swaziland National Trust Commission
19	Initial Environmental Examination - Mongolia: Sustaining Access to and Quality of Education during Economic Dificulties	Electric data	2017	MECSS/ADB
20	Construction Code of Mongolia (CCM) 31-03-03/11, Public and Civil Buildings (in Mongolian)	Booklet	2011	MCUD
21	Construction Regulations (CR) 31-113-11 Designing of General Education Institutions (in Mongolian)	Booklet	2011	MCUD

No.	Document title	Medium	Issued yr	Issuing agency
22	CCM 52-01-10 Concrete and Reinforced Concrete Structures, Principal Rules (in Mongolian)	Booklet	2010	MCUD
23	CR 31-101-04 Handbook for Barrier-Free Construction- Planning for Handicapped (in Mongolian)	Booklet	2004	MCUD
24	CCM 22-101-01/2013 Construction Planning at Seismic Zones of Mongolia	Booklet	2013	
25	Ulaanbaatar City General Development Plan 2030 (in Mongolian)	Electric data	2014	MCUD, UBC
26	Law of Mongolia on the Rights of Persons with Disabilities (Un-authorized translation)	Electric data	2016	Parliament of Mongolia
27	Report: Data Collection and Verification Survey on Special Needs Education in Mongolia (in Japanese)	Electric data	2014	JICA (Human Development Dept.)
28	PPTA- Ensuring inclusiveness and service delivery to persons with disabilities- Poverty and Social Analysis	Electric data	2016	ADB
29	Mongolia Country data book on Disability (in Japanese)	Electric data	2016	Project for promoting social participation of PWD in UBC
30	Law of Mongolia on Disaster Protection (Revised, in Mongolian)	Electric data	2017	Parliament of Mongolia
31	Final Report: Data Collection and Verification Survey on Disaster Prevention Sector of Mongolia (in Japanese)	Electric data	2016	ЛСА
32	Desaster Management in Schools (in Mongolian)	Booklet	2016	MECSS
33	Advancing School Safety in Asia	Electric data	-	World Vision
34	Environmental Protection Law of Mongolia	Electric data	1995	Parliament of Mongolia
35	Law of Mongolia on Environmental Impact Assessment	Electric data	2011	Parliament of Mongolia
36	Strategies for Development of Green Energy Systems in Mongolia (2013-2035)-Extended Executive Summary	Booklet	2015	Global Green Growth Institute
37	Green Public-Private-Partnerships for Public Infrastructure in Mongolia	Booklet	2016	Global Green Growth Institute
38	Financing Mechanisms for Green Public Education Buildings in Mongolia	Booklet	2016	Global Green Growth Institute
39	Green School- PPT Presentation	Electric data	-	"N.A.P Group" LLC