Appendix 1 Member List of the Survey Team

Name	Specialty	Title / Organization	
Mr. Kenichi ITO	Leader	Director, Health Division 1, Health Group 1, Human Development Department, JICA	
Dr. Hiroshi TAKENAKA	Technical Advisor	JICA Senior Advisor	
Mr. Mikuni YAMAE	Cooperation Planning	Health Division 1, Health Group 1, Human Development Department, JICA	
Mr. Keiichi IDE	Project Manager / Architectural Planning	Yokogawa Architects & Engineers, Inc.	
Mr. Koki MASUMI	Assistant Project Manager / Architectural Design	Yokogawa Architects & Engineers, Inc.	
Mr. Yasumichi DOI	Equipment Planning 1 / Maintenance	INTEM Consulting, Inc.	
Dr. Kyo HANADA	Health and Medical Planning	Estrella INC.	
Ms. Misato OHARA	Equipment Planning 2 / QS (Voluntary)	INTEM Consulting, Inc.	
Mr. Kazufumi UCHIDA	Health and Medical Planning Assistance (Voluntary)	Estrella INC.	

(1) Field Survey 1 (November 12 – December 4, 2016)

Name	Specialty	Title / Organization
Mr. Kenichi ITO	Leader	Director, Health Division 1, Health Group 1,Human Development Department, JICA
Dr. Hiroshi TAKENAKA	Technical Advisor	JICA Senior Advisor
Mr. Mikuni YAMAE	Cooperation Planning	Health Division 1, Health Group 1, Human Development Department, JICA
Mr. Keiichi IDE	Project Manager / Architectural Planning	Yokogawa Architects & Engineers, Inc.
Mr. Koki MASUMI	Assistant Project Manager / Architectural Design	Yokogawa Architects & Engineers, Inc.
Mr. Yasumichi DOI	Equipment Planning 1 / Maintenance	INTEM Consulting, Inc.
Mr. Satoru KATO	Health and Medical Planning	Yokogawa Architects & Engineers, Inc.
Mr. Shoichi TASHIRO	Construction Planning/QS	Yokogawa Architects & Engineers, Inc.
Ms. Misato OHARA	Equipment Planning 2 / QS (Voluntary)	INTEM Consulting, Inc.

(2) Field Survey 2 (February 7 – March 12, 2017)

(3) Draft Outline Design Explanatory Mission (August 19 – 27, 2017)

Name	Specialty	Title / Organization
		Deputy Director, Grant Aid Project Management
Mr. Shintaro TAKANO	Leader	Division 2, Financial Cooperation Implementation
		Department, JICA
		Health Division 1, Health Group 1, Human
Mr. Mikuni YAMAE	Cooperation Planning	Development Department, JICA
Mr. Keiichi IDE	Project Manager / Architectural Planning	Yokogawa Architects & Engineers, Inc.
Mr. Koki MASUMI	Assistant Project Manager / Architectural Design	Yokogawa Architects & Engineers, Inc.
Mr. Yasumichi DOI	Equipment Planning 1 / Maintenance	INTEM Consulting, Inc.

Appendix 2 Survey Schedule

			Off	icial Members			Consultant	Members		Consultant Mem	bers (Voluntary)
No.	Date	Day	Leader	Cooperation Planning	Technical Advisor	PM / Architectural Planning	Assistant PM / Architectural Design	Equipment Planning 1 / Maintenance	Health and Medical Planning	Equipment Planning 2 / QS	Health and Medical Planning Assistance
			Mr. Kenichi Ito	Mr. Mikuni Yamae	Dr. Hiroshi Takenaka	Mr. Keiich i Ide	Mr. Koki Masumi	Mr. Yasumichi Doi	Mr. Kyo Hanada	Ms. Misato Ohara	Mr. Kazufumi Uchida
S	urvey da	ys	8	21	21	21	21	19	23	13	23
1	11/12	Sat					Narita 22	:20>			Narita 22:20 >
2	11/13	Sun		Haneda>	• Entebbe		(Doha)> Er	ntebbe 14:15			(Doha)> Entebbe 14:15
3	11/14	Mon		Courtesy	call to JICA	office, courtesy	call to Ministry of H	Health (MOH) / d	liscussions		Accompanying PM
4	11/15	Tue			PM: Sur		4.5Hrs.)> Mbara RH, Mbarara (2Hrs.				Accompanying PM
5	11/16	Wed				Masaka NRH, Ma	asaka (4Hrs.)>	Lira			Accompanying PM
6	11/17	Thu				Surve	y of Lira RRH				Accompanying PM
7	11/18	Fri				Surve	y of Lira RRH				Accompanying PM
8	11/19	Sat		AM: Roundup of the survey and report to Lira RRH Accompanyin PM: Lira (4Hrs.)> Arua PM						Accompanying PM	
9	11/20	Sun		Team meeting / data filing Joining the Accompanying team at Arua PM						Accompanying PM	
10	11/21	Mon		Survey of Arua RRH							
11	11/22	Tue		Survey of Arua RRH							
12	11/23	Wed		AM: Roundup of the survey and report to Arua RRH Arua (4Hrs.)> Gulu							
13	11/24	Thu		Survey of Gulu RRH							
14	11/25	Fri		Survey of Gulu RRH							
15	11/26	Sat	Haneda> Entebbe			AM: R	oundup of the sur PM: Gulu (5H	vey and report t Irs.)> Kampala			
16	11/27	Sun	Team meeting / preparation of "Observations by the Survey Team"								
17	11/28	Mon	AM: Report of the survey results of the 3 RRHs to MOH PM: Drafting Minutes of Discussions (M/D)								
18	11/29	Tue	Discussions on M/D Accompanying Leader Entebbe 19:10> Supplementary Accompanying Supplementary surveys Leader surveys						Supplementary surveys		
19	11/30	Wed						Supplementary surveys			
20	12/1	Тhu		eport to JICA o anese Embassy	ffice and	Accompar	iying Leader		Supplementary surveys	Entebbe>	Supplementary surveys
21	12/2	Fri	E	ntebbe>			Hrs.)> Kabale of Kabale RRH		Supplementary surveys	(Dubai)> Japan	Supplementary surveys
22	12/3	Sat	> Haiti	> Japan	> Zambia	Defect inspect	ion at Hoima and		Entebbe 19:10>		Entebbe 19:10>
23	12/4	Sun				Kabale RRHs	till December 8		(Doha)> Narita 19:00		(Doha)> Narita 19:00

(1) Field Survey 1 (November 12 – December 4, 2016)

				Official Members				Official Mer	nbers		
ó	te	An a	Leader	Cooperation	Technical Advisor	PM / Architectural Planning	Assistant PM /	Utility Planning	Construction Planning	Equipment Planning 1 /	Equipment Planning 2 /
No.	Date	Day		Planning			Architectural Design		/ QS	Maintenance	QS
			Mr. Keiichi Ito	Mr. Mikuni Yamae	Dr. Hiroshi Takenaka	Mr. Keiich i Ide	Mr. Koki Masumi	Mr. Satoru Kato	Mr. Shoichi Tashiro	Mr. Yasumichi Doi	Ms. Misato Ohara
S	urvey da		7	12	15	33	33	22	29	33	33
-	2/7	Tue				Narita 22:00> (Doha)> Entebbe					22:00>
2	2/8	Wed				13:15	Narita 22:00>			(Doha)>	Entebbe 13:15
3	2/9	Thu				Courtesy call to JICA office, courtesy call to Ministry of Health (MOH) / discussions	(Doha)> Entebbe 13:15 Courtesy call to Ministry of Health (MOH) / discussions			Accor	npanying PM
4	2/10	Fri				Discussion wit	h MOH, USAID			Accor	npanying PM
5	2/11	Sat				Data filing	Commissioning survey of natural conditions	Narita	22:00>	Di	ata filing
6	2/12	Sun				Kampala (7 Hrs.)> Arua	Data filing		>Entebbe 3:15	Kampala (/ Hrs.)> Arua
7	2/13	Mon				Survey of Arua RRH	Commissioning survey of natural conditions	Survey of le	ocal contractors ction situation	Survey	of Arua RRH
8	2/14	Tue				Survey of Arua RRH	Kampa	la (7 Hrs.)> Ar	rua	Survey	of Arua RRH
9	2/15	Wed				Survey of Arua RRH	Sur	vey of Arua RRH		Survey	of Arua RRH
10	2/16	Thu				Arua (4.5 Hrs.) > Gulu	Sur	vey of Arua RRH		Arua (4.5	Hrs.)> Gulu
11	2/17	Fri				Survey of Gulu RRH	Sur	vey of Arua RRH		Survey	of Gulu RRH
12	2/18	Sat			Haneda>(Dubai) >Entebbe	Survey of Gulu RRH	Arua	(4.5 Hrs.)> Gu	lu	Survey	of Gulu RRH
13	2/19	Sun			Entebbe>Gulu		ł	Team meeting /	Data filing	,	
14	2/20	Mon					Surve	y of Gulu RRH			
15	2/21	Tue		Haneda> Entebbe			Surve	y of Gulu RRH			
16	2/22	Wed				of Gulu RRH Hrs.)> Lira					
17	2/23	Thu	Survey of Lira R			RH	Gulu (2 Hrs.)> Lira, Survey of Lira RRH				
18	2/24	Fri					Survey of Lira RRH				
19	2/25	Sat	Haneda>				Survey of Lira	RRH			
20	2/26	Sun	(Dubai)> Entebbe Kampala>	Lira	> Hoima			Team meeting /	Data filing		
21	2/27	Mon	Hoima	Survey of Hoima RF	RH			Survey of Li	ra RRH		
22	2/28	Tue	AM: Hoima> Kampala AM: Lira (4.5Hrs.)> Kampala								
			PM: Team meeting: Summarizing the survey results of the 3 RRHs AM: Report of the survey results of the 3 RRHs to MOH								
23	3/1	Wed					ng Minutes of Discussions			1	
24	3/2	Thu		F	Presenting and discu	ussions on MD		Survey of lo	ocal contractors	Accomp	anying Leader
25	3/3	Fri	Report to	JICA and Japanes Entebbe>	e Embassy	Accompan	ying Leader	Entebbe18:30 >	Survey of local contractors	Accompanying leader	Market research relevant to equipment supply / local agent
26	3/4	Sat	> Iran	> N	loldova	Examination of the pl oth	an of the target RRH, ers	(Doha)> Narita 17:35	Market research relevant to construction materials		earch relevant to upply / local agent
27	3/5	Sun				Data	filing			Data filing	
28	3/6	Mon					MD draft with MOH and ng MD		Construction materials market research	Accor	npanying PM
29	3/7	Tue				Visit Uganda Cancer Institute	Examination of the plan of the target RRH, others		Construction materials market research	Accompanying PM	Equipment market research / local agent
30	3/8	Wed					Women's Day filing		Survey of local contractors		nal Women's Day ata filing
31	3/9	Thu				Discussion with MOH /			Survey of local contractors	Accompanying PM	Equipment market research / local
32	3/10	Fri				Entebbe 18:30>	Receiving survey data of natural conditions			Entebbe 18:30	->
33	3/11	Sat				(Doha)>Narita 17:45	Entebbe 18:30>		(D	oha)> Narita 1	7:45
34	3/12	Sun					(Doha)>Narita 17:45				

(2) Field Survey 2 (February 7 – March 12, 2017)

			Official	Members		Consultant Members		
ė	Ð	v	Leader	Cooperation Planning	PM / Architectural Planning	Assistant PM / Architectural Design	Equipment Planning 1 / Maintenance	
No.	Date	Day	Mr. Shintaro Takano	Mr. Koki Masumi	Mr. Yasumichi Doi			
			Grn. Manag. Div.2, Fin.Coop. Impl. Dept., JICA Health Team 1, Health Group 1, HD Dept., JICA		Yokogawa Architects & Engineers, Inc.	Yokogawa Architects & Engineers, Inc.	INTEM Consulting, Inc.	
S	urvey da	ys	8	8	9	9	9	
1	8/19	Sat	Narita 21:25>					
2	8/20	Sun	Haneda 01:00>(Doha)> Entebbe 14:45 (Doha)> Entebbe 14:45					
3	8/21	Mon	9:30-12:00 Discussions with HID, MOH 16:00-17:00 Meeting with JICA Office (with CR, Takayama, Sugai)					
4	8/22	Tue	9:00–13:00 Discussions with target RRH executives in the presence of MOH (in Kampala) $15:00-17:00$ Draft Minutes of Discussions within the team					
5	8/23	Wed	9:30–11:30 Presentation to the Minister and discussions with target RRH and MOH 14:00–17:00 Draft Minutes of Discussions within the team and send the final draft to MOH					
6	8/24	Thu	9:00–12:00 Draft Minutes of Discussions with MOH 15:00 Discussion with MOFPED					
7	8/25	Fri	10:30 Sign Minutes/Explanation to MOH 14:45 Sign Minutes/Explanation to MOFPED 15:30-16:30 Meeting with EOJ (with Takayama) 17:00-18:00 Meeting with JICA Office (Confirmed)					
8	8/26	Sat	Entebbe 16:15>					
9	8/27	Sun	(Doha)>Narita 19:05 (Doha)> Narita 19:05					

(3) Draft Outline Design Explanatory Mission (August 19 – 27, 2017)

Name	Title, Position
Ministry of Health	
Dr. Aceng Jane Ruth	Minister
Dr. Diana Atwine	Permanent Secretary
Dr. Olaro Charles	Director, Clinical Services
Dr. Jackson Amone	Commissioner, Curative Services
Dr. Henry Mwebesa	Director Health Services, Planning & Development
Eng. Priscilla Nakiboneka	Assistant Commissioner
Eng. Paul Kaliba	Civil Engineer, Infrastructure Dept.
Eng. Tusbira Samuel	Civil Engineer, Infrastructure Dept.
Eng. Kataaha Edward	Electrical Engineer, Infrastructure Dept.
Eng. Sitra Mulepo	Equipment Engineer, Infrastructure Dept.
	Equipment Engineer, initiasit deture Dept.
Gulu Regional Referral Hospital Dr. James Elima	Director
	Director
Dr. Onyachi Nathan	Ex. Director
Tibemanya David	Principal Hospital Administrator
Mubiru Muhammed	Ex. Principal Hospital Administrator
Lanyero Agnes Patricia	PPT
Omara Julius	AMRO
Odyek Beatrice	SNO90
Dr. Arach Milly	МО
Chebet Juliet	SMSW
Bermas Henry	РМСО
Opio George Pius	AMRO
Ochorog Gabriel	AMRO
Opio Larubi Micheal	Electrician
Dr. Ssenfuka Samuel	MO
Saad Waigonda	Biomedical engineer
Emeru James	Inventory Officer
Lukwiya Geoffrey	Electrician
Ekou Edson E	Plumber
Tolit James	SAS Laroo Division
Lira Regional Referral Hospital	
Dr. Odu Bernard	Director
Dr. James Elima	Ex. Director
Michael Odur	Ex. Principal Hospital Administrator
Ogwal Walter	W/S Eng.
Oyang William	Cons. Paed.
Dralada Thomas Opeli	Psych. NO
Acan Ruth Lucy	SNO
Apio Stella	SNO
Evalyn Abongo	NO
Margaret Odongwen	PNO
Odepe Simon	Head Accts.
Urassa Johnathan G.	S. Radio
Sangadi Justine	PCO
Aciro Rose	SNO
Akuno Doreen Ruth	NO
Opota Walter	SEC

Appendix 3 List of Parties Concerned in the Recipient Country

Arua Regional Referral Hospital	
Dr. Adakau Alex	Ag. Director
Dr. Odu Bernard	Ex. Director
Okello Odeke Peter	Ex. Principal Hospital Administrator
Ezati Ezaruku	Chairperson Hospital Member of Board
Obeti Francis	BMET
Anite Joyce	N/O
Alezuyo Janet A	AC SPNO
Emudu Abosolom	Ag. Engineering Officer
Dr. Candia Robert	Dental Surgeon
Ogen-Mungu Ronald	Asst. Engineering Officer
USAID/SUSTAIN	
Gladyst Tugume	Deputy Chief of Party
Kiwanuka Paul	Director for Operations
Hillary Alima	Care & Treatment Advisor
Julien Natulaurla	Communication Specialist
Kayita Crolgry	QI-TA
UNHCR Arua Office	
Ezati Erzaruku	Chairperson HMB
Omed Aiyoub	Associate Field Officer
Anchinesh Mahotome	Protectional Officer
Uganda Cancer Institute	
Dr. Jackson Orem	Director
Ministry of Finance , Planning & Eco	onomic Development
Maris Wanyera	Ag. Director, Directrate Debt & Cash Policy

Appendix 4 Minutes of Discussions

(1) Field Survey 1

Minutes of Discussions on the Preparatory Survey I for the Project for Rehabilitation and Re-Equipping of Hospitals in Northern Uganda, in the Republic of Uganda

In response to the request from the Government of the Republic of Uganda (hereinafter referred to as "Uganda"), Japan International Cooperation Agency (hereinafter referred to as "JICA") dispatched the Preparatory Survey Team (hereinafter referred to as "the Team") for the Outline Design of "the Project for Rehabilitation and Re-Equipping of Hospitals in Northern Uganda" (hereinafter referred to as "the Project"), to Uganda, headed by Mr. Kenichi Ito, Director of Health Team 1, Health Group 1, Human Development Department, JICA, from 13th November to 3rd December, 2016. The Team held a series of discussions with the officials of the Government of Uganda and conducted a field survey. In the course of the discussions, both sides have confirmed the main items described in the attached sheets.

Ck

Mr. Kenichi Ito Leader, Preparatory Survey Team Japan International Cooperation Agency Japan

Kampala, 30th November, 2016

Dr. Diana Atwiine Permanent Secretary Ministry of Health Republic of Uganda

Witness

Ms. Maris Wanyera For: Permanent Secretary/Secretary to the Treasury Ministry of Finance, Planning and Economic Development Republic of Uganda

ATTACHMENT

1. Objective of the Project

The objective of the Project is to strengthen the functions of the selected Regional Referral Hospitals (hereinafter referred to as "RRH") in the northern region of Uganda, through construction of facilities and procurement of equipment, thereby contributing to improving access to and quality of health care services in Northern Uganda.

2. Title of the Preparatory Survey

Both sides agreed to amend the title of the Preparatory Survey as "the Preparatory Survey for the Project for Improvement of Regional Referral Hospitals in Northern Uganda," to reflect the content of the Project more clearly. The final title will be decided by the Government of Japan.

3. Project sites

The Project sites will be selected from Gulu RRH, Lira RRH, and Arua RRH. The location map of the candidate Project sites is shown in Annex 1. All of these sites are in legal possession of the Ministry of Health (hereinafter referred to as "MOH") as shown in Annex 2-1, 2-2 and 2-3.

4. Responsible authorities for the Project

Both sides confirmed the authorities responsible for the Project are as follows: The Health Infrastructure Division under the Department of Clinical Services of MOH and the RRHs to be covered by the Project will be the executing agencies for the Project (hereinafter referred to as "the Executing Agencies"). The Executing Agencies shall coordinate with all the relevant authorities to ensure smooth implementation of the Project and ensure that the undertakings for the Project shall be managed by relevant authorities properly and on time. The current organograms of MOH, the Health Infrastructure Division, and the RRHs are shown in Annex 3-1, 3-2, 3-3 and 3-4.

- 5. Items requested by the Government of Uganda
 - 5-1-1. As a result of discussions, both sides confirmed the facilities requested by the Government of Uganda, with findings by the Team and priorities agreed by both

D'A



sides, which are shown in Annex 4.

- 5-1-2. Each RRH submitted the priority department list for equipment (Annex 5). The revised priority department list and the requested equipment list with priority in sequential number by each department shall be finalized and submitted to JICA Uganda Office by the end of December, 2016.
- 5-2. JICA will assess the feasibility of the items in Annex 4, 5 and the requested equipment list through the Preparatory Survey, and JICA will report the findings to the Government of Japan. Both sides will elaborate and refine the scope of the Project during the Preparatory Survey II. The final scope of the Project will be decided by the Government of Japan.
- 6. Procedures and Basic Principles of Japanese Grant
 - 6-1. The Ugandan side agreed that the procedures and basic principles of Japanese Grant as described in Annex 6 shall be applied to the Project. As for the monitoring of the implementation of the Project, JICA requires Ugandan side to submit the Project Monitoring Report, the form of which is attached as Annex 7.
 - 6-2. The Ugandan side agreed to take the necessary measures, as described in Annex 8, for smooth implementation of the Project. The contents of Annex 8 will be elaborated and refined in the Preparatory Survey II and be agreed in the mission dispatched for explanation of the Draft Preparatory Survey Report. The contents of Annex 8 will be used as an attachment to the Grant Agreement.
- 7. Schedule of the Survey
 - 7-1. JICA will dispatch a mission as the Preparatory Survey II around February, 2017, in order to further discuss the details of the scope of the Project.
 - 7-2. JICA will prepare a draft Preparatory Survey Report in English and dispatch a mission to Uganda in order to explain its contents around August, 2017.
 - 7-3. When the contents of the draft Preparatory Survey Report are accepted and the undertakings for the Project are fully agreed by the Ugandan side, JICA will finalize the Preparatory Survey Report and send it to the Ugandan side around October, 2017.
 - 7-4. The above schedule is tentative and subject to change.
- 8. Environmental and Social Considerations
 - 8-1. The Ugandan side confirmed to give due environmental and social considerations before and during implementation, and after completion of the Project, in





accordance with the JICA Guidelines for Environmental and Social Considerations (April, 2010).

- 8-2. The Project is categorized as "C" from the following considerations: not located in a sensitive area, nor has it sensitive characteristics, nor falls it into sensitive sectors under the Guidelines, and its potential adverse impacts on the environment are not likely to be significant.
- 9. Other Relevant Issues
 - 9-1. The Ugandan side agreed to allocate budget (operational and maintenance costs) and human resources (health service providers and any other personnel) necessary for the proper and sustainable operation and maintenance of the facilities and the equipment under the Project.
 - 9-2. The Ugandan side expressed their needs for Soft Component under the Japan's Grant Aid. The contents will be discussed during the Preparatory Survey II. The Team will convey the request to the Government of Japan.
 - 9-3. The Ugandan side will submit the future plans of the assistance from other development partners towards the three RRHs, especially the project of procurement of medical imaging equipment for Gulu RRH by Italian Cooperation and the project of renovation of neonatal intensive care unit of Lira RRH by UNICEF, to JICA Uganda Office by the end of December, 2016.
 - 9-4. Both sides confirmed that the followings would be the undertakings of the Government of Uganda;
 - 1) demolition of existing facilities and land leveling to construct new facilities and
 - 2) providing alternative space and functions of demolished facilities during construction period.
 - 9-5. Both sides noted that treatment of taxes and duties for the Project shall be in accordance with the agreement to be concluded between the Government of Uganda and the Government of Japan. MOH shall take necessary measures according to the agreement.

Annex 1 Location map of the candidate Project sites

Annex 2-1, 2-2, 2-3 Ownership of land

Annex 3-1, 3-2, 3-3 and 3-4 Organograms of MOH, the Health Infrastructure Division and 3 RRHs

Annex 4 Requested facilities list

Annex 5 Priority department list for equipment

Annex 6 Japan Grant Aid

Annex 7 Project Monitoring Report (template)


Annex 8 Major Undertakings to be taken by the Government of Uganda



,







Annex 2-1

1



GULU DISTRICT LOCAL GOVERNMENT

DEPARTMENT OF NATURAL RESOURCES LAND MANAGEMENT SECTOR

P.O. Box 2,

Date: 5th October, 2016

The Chief Representative

Japan International Cooperation Agency (JICA)

- RE: GULU REGIONAL REFERRAL HOSPITAL LAND

This letter serves to confirm that **plot nos 4 – 10 Dr. Mathew Lukwiya Road** – on Sheet **No. 22/2/21/NE/4** is gazetted as Land belonging to Gulu Regional Referral Hospital.

The Board has received an application from the Hospital Management for acquiring a land title over the said plot and upon the acquisition of the land title, a copy shall be forwarded to your office.

Jul 2-1


District Land officer/Gulu


Cc Director Gulu Regional Referral Hospital

Cc The Hospital Administrator/ Gulu Regional Referral Hospital


Cc File.








S





Ł



ULC/154/1052

THE REPUBLIC OF UGANDA

REGISTRATION OF TITLES ACT.

Certificate of Title.

FREEHOLD REGISTER

Volume 765 Folio 5

DESCRIPTION OF LAND

ALL THAT piece of land delineated and edged red on the plan hereto annexed containing the following area or thereabouts and situate as follows:-

Area.	County.	District
16.023HECTARES	L. IRA MUNICIPALITY	

and known as PLOTS 9-19, 21 - 41 NGETTA ROAD AND 6-14 AGORA ROAD

(SUBJECT TO CONDITIONS HEREIN)

OWNERSHIP

Date, time UGANDA LAND COMMISSION OF P.O. Box 36408, KAMPALA and Inst. No. REGD 25.6.2010

ат.2.10р.м. INST. 430893

> is/are now the proprietors of an estate in fee simple in the land above described subject to the conditions and incumbrances hereinafter set out.

Dated this 2ND day of JULY

20 10

Signature of

Registrar

Registrar of Titles.

Signature of Date, lime Name and Address of Owner Registrar and Inst. No: FR.

OWNERSHIP—continued

CONDITIONS

ate, time I Inst. No.	Particulars	Signature of Registrar
A)	USER TO BE RESTRICTED TO LIRA REGIONAL REFERRAL Hospital (Hospital, Hedical trauning school and a récreation ground)	Bron S
	e e	
		¢ &

ŝ

Annex	2-3

£ 1

ALC 3
E DEDURI LO OF LOAD

ULC/154/522

THE REPUBLIC OF UGANDA

REGISTRATION OF TITLES ACT.

Certificate of Title.

FREEHOLD REGISTER

Volume 657 Folio

16

DESCRIPTION OF LAND

ALL THAT piece of land delineated and edged red on the plan hereto annexed containing the following area or thereabouts and situate as follows:-

County.	District.	
N 21	400114	
	County. ARUA MUNICIPALITY	ARUA

and known as PLOT 26-62 AVENUE ROAD - ARUA

(SUBJECT TO CONDITIONS HEREIN)

OWNERSHIP


Datestime UGANDA LAND COMMISSION OF P.O. Box 36408, KAMPALA and Inst. No. 30.12.6.09 ,3.20P.M. r.414346 is/are now the proprietors of an estate in fee simple in the land above described subject to the conditions and incumbrances hereinafter set out. Dated this

Signature of Registrar

 4^{TH} day of

2009 AUGUST

Registrar of Titles.




Cappen and Cappen and


.

CONDITIONS


ata tina -	HENT	
ate, time d Inst. No.	- Particulars	Signature of Registrar
A) "	Ministry of Health (Arua Regional Referrae Hospital)	
	2.8.1	
		4
	M	L





OWNERSHIP—continued



Organogram of the Health Infrastructure Division








Annex 3-3 Organogram of Lira RRH

R.

Annex 3-4

Appendix (ii)

Functional Organisation Structure for Arua Regional Referral Hospital



500- Jas

list
facilities
Requested
Annex 4

			Gulu	n			Lira			Arua	Ja
-	Hospital	(1) Mate	Maternity, Theatre, Casualty	Sasualty	(2) OPD	(1) OPD + Casualty	Casualty	(2) Ma	Maternity	(1) OPD + Casualty	(2) Maternity Ward
Prio	Priority by each hospital		۷		Ω	A		ш	8	۷	ß
		Maternity	Theatre	Casualty	ado	OPD	Casualty	Delivery	Ward	OPD + Casualty	Maternity Ward
		A	4	υ	U	A-	B	A+	υ	В	υ
		Minimal function. Theater cannot	No good separation of sterile and	Functioning good, including observation	Function scattered, but each	Functioning, but scattered. No good	Using old main theater. Located in	Concerns regarding nosocomial	Functionin g good with necessary	Main OPD buildings and MCH are	Functioning good including operating
Fin	Function of the facility	be used.	non-sterile areas. No good function of sterilization room or	beds.	building is functioning good.	environment regarding waiting space.	inpattent area, far from OPD.	intection	facility and equipment.	separated. Complicated patient flow.	tneatre, Neonatal ward, 10 delivery beds.
dint		A+	V	۷	۵	•	A+	•	A+	A-	υ
js by JICA Si	Aging level of the facility	Renovated in 2010, but not in good condition inside.	Renovated recently, but not in good condition inside.	Built in 1930s. Old.	Built in 1930s.	Built in 1930s. Old	.bld	Built in 1920s. Old	s. Old.	Built in 1930s. Maintained in good condition,	Built in 1930s. Renovated in recent years with good condition.
urve		A+	A	ß	۷	+4	U	+A+	ш	8	U
ey team	Insufficienc y of the space	Absolute lack of the space, e.g. beds in the corridor.	Small as a teaching hospital. Corridor, changing room also has no enough space.	Currently enough space to accommodate patients.	Not overcrowded	Absolute lack of space.	Not too congested.	Only 4 delivery beds. Extremely small space between beds.	Lack of space, but not so highly urgent.	Small space in consultation room or corridor. Relatively enough space for waiting area.	Enough space.
	Overall assessmen t by JICA team	A	A	Δ	-A	¥	-A	+¥	Ω	ß	υ
Pri	Tentative Prioritization	A	A	A	B	۲	۲	A	ပ	÷8	υ
	Remarks		*	*1						*2	

*2 MOH expressed great need of OPD + Casulaty complex of Arua RRH to be included in the Project.

F

Hospital		Department	Priority
Gulu RRH	Operation Th		1
	Emergency		2
	Imagery		3
2	OB/GYN		4
	Outpatient D	epartment	5
		g Recovery room)	6
	Surgery War		7
6	Laboratory		8
	Ambulance		9
	Sterilization a	and Laundry	10
	Dental		10
	ENT		12
7	Internal Medi	cine Ward	12
	Physiotherap		14
	Pharmacy	y	14
	Paediatric		16
	Orthopeadic	work shop	17
	Maintenance	· · · · · · · · · · · · · · · · · · ·	17
Lira RRH	Out patient	work shop	10
	OB/GYN		2
	Imaging		3
	Ambulance		4
	Emergency		5
	Sterilisation &	8 Jaundany	6
	Dental	Cauldary	7
	Peadiatric		8
	Operation Th	peatre	9
	Sugery ward		10
	ENT		11
	Laboratory		12
	Internal Med	icino	12
	ICU/Recover		13
	Internal Med		14
	Phamarcy Medical Equi	nment W/s	16
	nvieuluai Equi	Including Accident/Emergency,	17
Arua RRH		Dental, Phisiotherapy, Imaging Unit,	
	OPD		1
		Orthopedics, Laboratory Including Labour suite, Anetenatal-	
	D.d.o.ut.o.ut.ut.	÷	
	Martenirty	Post natala ward, Theatre, Neonatal	2
	CSSD	Unit	2
	Ambrance		3
	Amplance	11	4

Annex 5 Priority department list for equipment



Main operating theatre	5
Medical ward	6
Pediatric Ward	7
Surgical Ward	8
Medical Workshop	9

Fla

JAPANESE GRANT

The Japanese Grant is non-reimbursable fund provided to a recipient country (hereinafter referred to as "the Recipient") to purchase the products and/or services (engineering services and transportation of the products, etc.) for its economic and social development in accordance with the relevant laws and regulations of Japan. Followings are the basic features of the project grants operated by JICA (hereinafter referred to as "Project Grants").

1. Procedures of Project Grants

Project Grants are conducted through following procedures (See "PROCEDURES OF JAPANESE GRANT" for details):

(1) Preparation

- The Preparatory Survey (hereinafter referred to as "the Survey") conducted by JICA

(2) Appraisal

-Appraisal by the government of Japan (hereinafter referred to as "GOJ") and JICA, and Approval by the Japanese Cabinet

(3) Implementation

Exchange of Notes

-The Notes exchanged between the GOJ and the government of the Recipient

Grant Agreement (hereinafter referred to as "the G/A")

-Agreement concluded between JICA and the Recipient

Banking Arrangement (hereinafter referred to as "the B/A")

-Opening of bank account by the Recipient in a bank in Japan (hereinafter referred to as "the Bank") to receive the grant

Construction works/procurement

-Implementation of the project (hereinafter referred to as "the Project") on the basis of the G/A

(4) Ex-post Monitoring and Evaluation

-Monitoring and evaluation at post-implementation stage

2. Preparatory Survey

(1) Contents of the Survey

The aim of the Survey is to provide basic documents necessary for the appraisal of the the Project made by the GOJ and JICA. The contents of the Survey are as follows:

- Confirmation of the background, objectives, and benefits of the Project and also institutional capacity of

relevant agencies of the Recipient necessary for the implementation of the Project.

- Evaluation of the feasibility of the Project to be implemented under the Japanese Grant from a technical, financial, social and economic point of view.
- Confirmation of items agreed between both parties concerning the basic concept of the Project.
- Preparation of an outline design of the Project.
- Estimation of costs of the Project.
- Confirmation of Environmental and Social Considerations

The contents of the original request by the Recipient are not necessarily approved in their initial form. The Outline Design of the Project is confirmed based on the guidelines of the Japanese Grant.

JICA requests the Recipient to take measures necessary to achieve its self-reliance in the implementation of the Project. Such measures must be guaranteed even though they may fall outside of the jurisdiction of the executing agency of the Project. Therefore, the contents of the Project are confirmed by all relevant organizations of the Recipient based on the Minutes of Discussions.

(2) Selection of Consultants

For smooth implementation of the Survey, JICA contracts with (a) consulting firm(s). JICA selects (a) firm(s) based on proposals submitted by interested firms.

(3) Result of the Survey

JICA reviews the report on the results of the Survey and recommends the GOJ to appraise the implementation of the Project after confirming the feasibility of the Project.

3. Basic Principles of Project Grants

(1) Implementation Stage

1) The E/N and the G/A

After the Project is approved by the Cabinet of Japan, the Exchange of Notes (hereinafter referred to as "the E/N") will be singed between the GOJ and the Government of the Recipient to make a pledge for assistance, which is followed by the conclusion of the G/A between JICA and the Recipient to define the necessary articles, in accordance with the E/N, to implement the Project, such as conditions of disbursement, responsibilities of the Recipient, and procurement conditions. The terms and conditions generally applicable to the Japanese Grant are stipulated in the "General Terms and Conditions for Japanese Grant (January 2016)."

- S

- 2) Banking Arrangements (B/A) (See "Financial Flow of Japanese Grant (A/P Type)" for details)
 - a) The Recipient shall open an account or shall cause its designated authority to open an account under the name of the Recipient in the Bank, in principle. JICA will disburse the Japanese Grant in Japanese yen for the Recipient to cover the obligations incurred by the Recipient under the verified contracts.
 - b) The Japanese Grant will be disbursed when payment requests are submitted by the Bank to JICA under an Authorization to Pay (A/P) issued by the Recipient.

3) Procurement Procedure

The products and/or services necessary for the implementation of the Project shall be procured in accordance with JICA's procurement guidelines as stipulated in the G/A.

4) Selection of Consultants

In order to maintain technical consistency, the consulting firm(s) which conducted the Survey will be recommended by JICA to the Recipient to continue to work on the Project's implementation after the E/N and G/A.

5) Eligible source country

In using the Japanese Grant disbursed by JICA for the purchase of products and/or services, the eligible source countries of such products and/or services shall be Japan and/or the Recipient. The Japanese Grant may be used for the purchase of the products and/or services of a third country as eligible, if necessary, taking into account the quality, competitiveness and economic rationality of products and/or services necessary for achieving the objective of the Project. However, the prime contractors, namely, constructing and procurement firms, and the prime consulting firm, which enter into contracts with the Recipient, are limited to "Japanese nationals", in principle.

6) Contracts and Concurrence by JICA

The Recipient will conclude contracts denominated in Japanese yen with Japanese nationals. Those contracts shall be concurred by JICA in order to be verified as eligible for using the Japanese Grant.

7) Monitoring

The Recipient is required to take their initiative to carefully monitor the progress of the Project in order to ensure its smooth implementation as part of their responsibility in the G/A, and to regularly report to JICA about its status by using the Project Monitoring Report (PMR).

8) Safety Measures

The Recipient must ensure that the safety is highly observed during the implementation of the Project.

9) Construction Quality Control Meeting

Construction Quality Control Meeting (hereinafter referred to as the "Meeting") will be held for quality assurance and smooth implementation of the Works at each stage of the Works. The member of the Meeting will be composed by the

K &

Recipient (or executing agency), the Consultant, the Contractor and JICA. The functions of the Meeting are as followings:

- a) Sharing information on the objective, concept and conditions of design from the Contractor, before start of construction.
- b) Discussing the issues affecting the Works such as modification of the design, test, inspection, safety control and the Client's obligation, during construction.

(2) Ex-post Monitoring and Evaluation Stage

1) After the project completion, JICA will continue to keep in close contact with the Recipient in order to monitor that the outputs of the Project is used and maintained properly to attain its expected outcomes.

2) In principle, JICA will conduct ex-post evaluation of the Project after three years from the completion. It is required for the Recipient to furnish any necessary information as JICA may reasonably request.

(3) Others

1) Environmental and Social Considerations

The Recipient shall carefully consider environmental and social impacts by the Project and must comply with the environmental regulations of the Recipient and JICA Guidelines for Environmental and Social Considerations (April, 2010).

2) Major undertakings to be taken by the Government of the Recipient

For the smooth and proper implementation of the Project, the Recipient is required to undertake necessary measures including land acquisition, and bear an advising commission of the A/P and payment commissions paid to the Bank as agreed with the GOJ and/or JICA. The Government of the Recipient shall ensure that customs duties, internal taxes and other fiscal levies which may be imposed in the Recipient with respect to the purchase of the Products and/or the Services be exempted or be borne by its designated authority without using the Grant and its accrued interest, since the grant fund comes from the Japanese taxpayers.

3) Proper Use

The Recipient is required to maintain and use properly and effectively the products and/or services under the Project (including the facilities constructed and the equipment purchased), to assign staff necessary for this operation and maintenance and to bear all the expenses other than those covered by the Japanese Grant.

4) Export and Re-export

The products purchased under the Japanese Grant should not be exported or re-exported from the Recipient.




Stage	Procedures	Remarks	Recipient Government	Japanese Government	JICA	Consultants	Contractors	Agent Bank
Official Request	Request for grants through diplomatic channel	Request shall be submitted before appraisal stage.	x	х				
1. Preparation	(1) Preparatory Survey Preparation of outline design and cost estimate		х		x	x		
	(2)Preparatory Survey Explanation of draft outline design, including cost estimate, undertakings, etc.		х		x	x		
2- Appraisal	(3)Agreement on conditions for implementation	Conditions will be explained with the draft notes (E/N) and Grant Agreement (G/A) which will be signed before approval by Japanese government.	x	x (E/N)	x (G/A)			
	(4) Approval by the Japanese cabinet			х				
	(5) Exchange of Notes (E/N)		x	x				
	(6) Signing of Grant Agreement (G/A)		x		x			
	(7) Banking Aπangement (B/A)	Need to be informed to JICA	x					x
	(8) Contracting with consultant and issuance of Authorization to Pay (A/P)	Concurrence by JICA is required	x			х		x
	(9) Detail design (D/D)		x			x		
3. Implementation	(10) Preparation of bidding documents	Concurrence by JICA is required	x			x		
	(11) Bidding	Concurrence by JICA is required	x			x	x	
	(12) Contracting with contractor/supplier and issuance of A/P	Concurrence by JICA is required	x				x	х
	(13) Construction works/procurement	Concurrence by JICA is required for major modification of design and amendment of contracts.	x			x	x	
	(14) Completion certificate		x			x	x	
4. Ex-post monitoring &	(15) Ex-post monitoring	To be implemented generally after 1, 3, 10 years of completion, subject to change	x		x			
evaluation	(16) Ex-post evaluation	To be implemented basically after 3 years of completion	x		x			

notes:

1. Project Monitoring Report and Report for Project Completion shall be submitted to JICA as agreed in the G/A

2. Concurrence by JICA is required for allocation of grant for remaining amount and/or contingencies as agreed in the G/A





Attachment 2

Project Monitoring Report on Project Name Grant Agreement No. XXXXXXX 20XX, Month

Organizational Information

Signer of the G/A	Person in Charge	(Designation)
(Recipient)	Contacts	Address: Phone/FAX: Email:
Executing Agency	Person in Charge Contacts	(Designation) Address: Phone/FAX: Email:
Line Ministry	Person in Charge Contacts	(Designation) Address: Phone/FAX: Email:

General Information:

Project Title	
E/N	Signed date: Duration:
G/A	Signed date: Duration:
Source of Finance	Government of Japan: Not exceeding JPY <u>mil.</u> Government of ():





1: **Project Description**

1-1 Project Objective

1-2 Project Rationale

- Higher-level objectives to which the project contributes (national/regional/sectoral policies and strategies)
- Situation of the target groups to which the project addresses

1-3 Indicators for measurement of "Effectiveness"

Indicators	Original (Yr)	Target (Yr)
	re the attainment of project object	

2: Details of the Project

2-1 Location

(PMR)

Components	Original	Actual
	(proposed in the outline design)	

2-2 Scope of the work

Components	Original*	Actual*
	(proposed in the outline design)	
1.		

Reasons for modification of scope (if any).

t 2

2-3 Implementation Schedule

	Original		
Items	(proposed in the outline design)	(at the time of signing the Grant Agreement)	Actual

Reasons for any changes of the schedule, and their effects on the project (if any)

2-4 Obligations by the Recipient 2-4-1 Progress of Specific Obligations See Attachment 2.

- **2-4-2 Activities** See Attachment 3.
- **2-4-3 Report on RD** See Attachment 11.

2-5 Project Cost

2-5-1 Cost borne by the Grant(Confidential until the Bidding)

Components		Cos (Millior	
Original (proposed in the outline design)	Actual (in case of any modification)	Original ^{1),2)} (proposed in the outline design)	Actual
 1.			
Total			

Note: 1) Date of estimation: 2) Exchange rate: 1 US Dollar = Yen

2-5-2 Cost borne by the Recipient

Components		Cost	
Original (proposed in the outline design)	Actual (in case of any modification)	Original ^{1),2)} (proposed in the outline design)	Actual
1.			

Note: 1) Date of estimation: 2) Exchange rate: 1 US Dollar =

Reasons for the remarkable gaps between the original and actual cost, and the countermeasures (if any)

(PMR)

2-6 Executing Agency

- Organization's role, financial position, capacity, cost recovery etc,
- Organization Chart including the unit in charge of the implementation and number of employees.

Original (at the time of outline design) name: role: financial situation: institutional and organizational arrangement (organogram): human resources (number and ability of staff):

Actual (PMR)

2-7 Environmental and Social Impacts

- The results of environmental monitoring based on Attachment 5 (in accordance with Schedule 4 of the Grant Agreement).

- The results of social monitoring based on in Attachment 5 (in accordance with Schedule 4 of the Grant Agreement).

- Disclosed information related to results of environmental and social monitoring to local stakeholders (whenever applicable).

3: Operation and Maintenance (O&M)

3-1 Physical Arrangement

- Plan for O&M (number and skills of the staff in the responsible division or section, availability of manuals and guidelines, availability of spareparts, etc.)

Original (at the time of outline design)

Actual (PMR)

3-2 Budgetary Arrangement

- Required O&M cost and actual budget allocation for O&M

Original (*at the time of outline design*)

4

4: Potential Risks and Mitigation Measures

- Potential risks which may affect the project implementation, attainment of objectives, sustainability
- Mitigation measures corresponding to the potential risks

Potential Risks	Assessment
1. (Description of Risk)	Probability: High/Moderate/Low
	Impact: High/Moderate/Low
	Analysis of Probability and Impact:
	Mitigation Measures:
	Action required during the implementation stage:
	Contingency Plan (if applicable):
2. (Description of Risk)	Probability: High/Moderate/Low
` 1 /	Impact: High/Moderate/Low
	Analysis of Probability and Impact:
	Mitigation Measures:
	Action required during the implementation stage:
	Contingency Plan (if applicable):
. (Description of Risk)	Probability: High/Moderate/Low
(r	Impact: High/Moderate/Low
	Analysis of Probability and Impact:
	Mitigation Measures:
	Action required during the implementation stage:
F	5

Assessment of Potential Risks (at the time of outline design)

	Contingency Plan (if applicable):
Actual Situation and Countermeasure	S
(PMR)	

5: Evaluation and Monitoring Plan (after the work completion)

5-1 Overall evaluation

Please describe your overall evaluation on the project.

5-2 Lessons Learnt and Recommendations

Please raise any lessons learned from the project experience, which might be valuable for the future assistance or similar type of projects, as well as any recommendations, which might be beneficial for better realization of the project effect, impact and assurance of sustainability.

5-3 Monitoring Plan of the Indicators for Post-Evaluation

Please describe monitoring methods, section(s)/department(s) in charge of monitoring, frequency, the term to monitor the indicators stipulated in 1-3.



Attachment

- 1. Project Location Map
- 2. Specific obligations of the Recipient which will not be funded with the Grant
- 3. Monthly Report submitted by the Consultant

Appendix - Photocopy of Contractor's Progress Report (if any)

- Consultant Member List
- Contractor's Main Staff List
- 4. Check list for the Contract (including Record of Amendment of the Contract/Agreement and Schedule of Payment)
- 5. Environmental Monitoring Form / Social Monitoring Form
- 6. Monitoring sheet on price of specified materials (Quarterly)
- 7. Report on Proportion of Procurement (Recipient Country, Japan and Third Countries) (PMR (final)only)
- 8. Pictures (by JPEG style by CD-R) (PMR (final)only)
- 9. Equipment List (PMR (final)only)
- 10. Drawing (PMR (final)only)
- 11. Report on RD (After project)

1. Initial Conditions (Confirmed)

		Initial Unit	Initial total	1% of Contract	Condition of payment	of payment
Items of Specified Materials	ls Initial Volume A	Price (¥) B	Price C=A×B	Price D	Price (Decreased) E=C-D	Price (Increased) F=C+D
Item 1	0¢t	•		•	•	
2 Item 2	0¢	•		•		
Item 3						
Item 4						
5 Item 5						

B. Monitoring of the Unit Price of Specified Materials
(1) Method of Monitoring : .

W

(2) Result of the Monitoring Survey on Unit Price for each specified materials

and the second	Items of Specified Materials	• month, 2015	ena month, 2015	era Omonth, 2015	4 01	Очн	OUL
	Item 1						
2	Item 2						
က က	Item 3						
4	Item 4						
ىر مى	Item 5						

(3) Summary of Discussion with Contractor (if necessary)



Attachment 7

Report on Proportion of Procurement (Recipient Country, Japan and Third Countries) (Actual Expenditure by Construction and Equipment each)

	Domestic Procurement	Foreign Procurement	Foreign Procurement	Total
	(Recipient Country)	(Japan)	(Third Countries)	D
	A	B	С	
Construction Cost	(%D%)	(B/D%)	(C/D%)	
Direct Construction Cost	(9%D/V)	(B/D%)	(C/D%)	
others	(A/D%)	(B/D%)	(C/D%)	
Equipment Cost	(A/D%)	(B/D%)	(C/D%)	
Design and Supervision Cost	(%D%)	(B/D%)	(C/D%)	
Total	(A/D%)	(B/D%)	(C/D%)	



Annex 8

Major Undertakings to be taken by the Government of Uganda

Specific obligations of the Government of Uganda which will not be funded with the Grant

(1) Before the Tender

NO	Items	Deadline	In charge	Estimated Cost	Ref.
1	To open bank account (B/A)	within 1 month after the signing of the G/A	MOH		
	To issue A/P to a bank in Japan (the Agent Bank) for the payment to the consultant	within 1 month after the signing of the contract	MOH		
	To provide alternative space and functions of facilities to be demolished during construction period.	before start of demolition	RRHs		
	To secure and clear the following lands 1) the project site(s) to construct facility(ies) 2) the temporary construction yard and stock yard near to the Project site(s)	before notice of the bidding document	RRHs		
5	To obtain the planning, zoning, building permit	before notice of the bidding document	MOH and RRHs		
6	To clear, level and reclaim the following sites 1) existing facilities	before notice of the bidding document	RRHs		
7	To submit Project Monitoring Report (with the result of Detail Design)	before preparation of bidding documents	MOH		

(B/A: Banking Arrangement, A/P: Authorization to pay, N/A: Not Applicable)

h 7

(2) During the Project Implementation

	(2) During the Project implementation			227-128 N. M.	
NO	Items	Deadline	In charge	Estimated Cost	Ref.
	To issue A/P to a bank in Japan (the Agent Bank) for the payment to the Supplier(s)	within 1 month after the signing of the contract(s)	MOH		
	To bear the following commissions to a bank in Japan for the banking services based upon the B/A		MOH		
	1) Advising commission of A/P	within 1 month after the signing of the contract(s)	MOH		
	2) Payment commission for A/P	every payment	MOH		
	To ensure prompt customs clearance and to assist the Supplier(s) with internal transportation in recipient country	during the Project	МОН		
	To accord Japanese nationals and/or physical persons of third countries whose services may be required in connection with the supply of the products and the services such facilities as may be necessary for their entry into the country of the Recipient and stay therein for the performance of their work	during the Project	МОН		
5	To ensure that customs duties, internal taxes and other fiscal levies which may be imposed in the country of the Recipient with respect to the purchase of the products and/or the services shall be in accordance with the agreement to be concluded between the Government of Uganda and the Government of Japan. MOH shall take necessary measures according to the agreement	during the Project	МОН		
6	To bear all the expenses, other than those covered by the Grant, necessary for the implementation of the Project	during the Project	MOH and RRHs		
7	To submit Project Monitoring Report	every month	MOH		
	1) To submit Project Monitoring Report (final)	within one month after signing of Certificate of Completion for the works under the contract(s)	МОН		
8	To submit a report concerning completion of the Project	within six months after completion of the Project	МОН		
9	To construct access roads 1) Outside the site	3 months before completion of the construction	RRHs		
10	To provide facilities for distribution of electricity, water supply and drainage and other incidental facilities necessary for the implementation of the Project outside the sites		RRHs		
	1) Electricity The distributing line to the sites	before start of the construction	RRHs		
	 Water Supply The city water distribution main to the sites 	6 months before completion of the construction	RRHs		
	 Drainage The city drainage main (for storm, sewer and others) to the sites 	6 months before completion of the construction	RRHs		
	 Furniture and Equipment General furniture 	1 month before completion of the construction	RRHs		1

4

11 To take necessary measure for safety construction - traffic control	during the construction	RRHs		
---	-------------------------	------	--	--

K



(3) After the Project

NO	Items	Deadline	In charge	Estimated Cost	Ref.
	 To maintain and use properly and effectively the facilities constructed and equipment provided under the Grant Aid 1) Allocation of maintenance cost 2) Operation and maintenance structure 3) Routine check/Periodic inspection 	After completion of the construction	MOH and RRHs		

the

(2) Field Survey 2

Minutes of Discussions on the Preparatory Survey 2 for the Project for Improvement of Regional Referral Hospitals in Northern Uganda, in the Republic of Uganda

In response to the request from the Government of the Republic of Uganda (hereinafter referred to as "Uganda"), Japan International Cooperation Agency (hereinafter referred to as "JICA") dispatched the Preparatory Survey Team (hereinafter referred to as "the Team") for the Outline Design of the Project for Improvement of Regional Referral Hospitals in Northern Uganda (hereinafter referred to as "the Project"), to Uganda, headed by Mr. Kenichi Ito, Director of Health Team 1, Health Group 1, Human Development Department, JICA, from 8th February to 11th March, 2017. The Team held a series of discussions with the officials of the Government of Uganda and conducted a field survey. In the course of the discussions, both sides have confirmed the main items described in the attached sheets.

Mr. Kenichi Ito Leader, Preparatory Survey Team Japan International Cooperation Agency Japan Kampala, 2nd March, 2017

Dr. Diana Atwine Permanent Secretary Ministry of Health Republic of Uganda

Witness

Ms. Maris Wanyera For: Permanent Secretary/Secretary to the Treasury Ministry of Finance, Planning and Economic Development Republic of Uganda

ATTACHMENT

1. Objective of the Project

The objective of the Project is to strengthen the functions of the selected Regional Referral Hospitals (hereinafter referred to as "RRH") in the northern region of Uganda, through construction of facilities and procurement of equipment, thereby contributing to improving access to and quality of health care services in Northern Uganda.

2. Title of the Preparatory Survey

Both sides confirmed the title of the Preparatory Survey as "the Preparatory Survey for the Project for Improvement of Regional Referral Hospitals in Northern Uganda". The final title will be decided by the Government of Japan.

3. Project sites

Both sides confirmed that the sites of the Project are Gulu RRH, Lira RRH and Arua RRH. The location map of the Project sites is shown in Annex 1. All of these sites are in legal possession of the Ministry of Health (hereinafter referred to as "MOH") as shown in Annex 2-1, 2-2 and 2-3.

4. Responsible authorities for the Project

Both sides confirmed the authorities responsible for the Project are as follows: The Health Infrastructure Division under the Department of Clinical Services of MOH, planned to be upgraded to the Department of Health Infrastructure from July, 2017, and the RRHs to be covered by the Project will be the executing agencies for the Project (hereinafter referred to as "the Executing Agencies"). The Executing Agencies shall coordinate with all the relevant authorities to ensure smooth implementation of the Project and ensure that the undertakings for the Project shall be managed by relevant authorities properly and on time. The current organograms of MOH, the Health Infrastructure Division, and the RRHs are shown in Annex 3-1, 3-2, 3-3 and 3-4.

- 5. Items requested by the Government of Uganda
 - 5-1. As a result of discussions, both sides confirmed the items requested by the Government of Uganda, which are shown in Annex 4 (facility) and Annex 5 (equipment). Both sides also confirmed the priority of requested equipment within each department in each RRH by the Government of Uganda as shown in

Annex 5.

- 5-2. JICA will assess the feasibility of the items in Annex 4 and 5 through the Preparatory Survey and report the findings to the Government of Japan. The final scope of the Project will be decided by the Government of Japan.
- 6. Procedures and Basic Principles of Japanese Grant
 - 6-1. The Ugandan side agreed that the procedures and basic principles of Japanese Grant as described in Annex 6 shall be applied to the Project. As for the monitoring of the implementation of the Project, JICA requires the Ugandan side to submit the Project Monitoring Report, the form of which is attached as Annex 7.
 - 6-2. The Ugandan side agreed to take the necessary measures, as described in Annex 8, for smooth implementation of the Project. The contents of Annex 8 will be elaborated and refined during the Preparatory Survey and be agreed in the mission dispatched for explanation of the Draft Preparatory Survey Report. The contents of Annex 8 will be used as an attachment to the Grant Agreement.
 - 6-3. The Ugandan side agreed to allocate the necessary budget for the items in Annex8 which will be completed in the Ugandan financial year 2017/18 (from July 2017 to June 2018).
- 7. Schedule of the Survey
 - 7-1. The Team will proceed with further survey in Uganda until 11th March, 2017.
 - 7-2. JICA will prepare a draft Preparatory Survey Report in English and dispatch a mission to Uganda in order to explain its contents around August, 2017.
 - 7-3. When the contents of the draft Preparatory Survey Report are accepted and the undertakings for the Project are fully agreed by the Ugandan side, JICA will finalize the Preparatory Survey Report and send it to the Ugandan side around October, 2017.
 - 7-4. The above schedule is tentative and subject to change.
- 8. Environmental and Social Considerations
 - 8-1. The Ugandan side confirmed to give due environmental and social considerations before and during implementation, and after completion of the Project, in accordance with the JICA Guidelines for Environmental and Social Considerations (April, 2010).
 - 8-2. The Project is categorized as "C" from the following considerations: not located in a sensitive area, nor has it sensitive characteristics, nor falls into sensitive

De

sectors under the Guidelines, and its potential adverse impacts on the environment are not likely to be significant.

- 9. Other Relevant Issues
 - 9-1. The Ugandan side agreed to allocate budget (operational and maintenance costs), human resources with skills (health service providers and any other personnel), and goods (spare parts and consumables) necessary for the proper and sustainable operation and maintenance of the facilities and the equipment under the Project. Especially, the Ugandan side agreed to take necessary measures to train and allocate sufficient human resources with adequate skills to functionalize Intensive Care Unit (ICU) requested to be built in Gulu RRH before the completion of the Project. In addition, the Ugandan side confirmed that the oxygen plants will be built in all the target three RRHs by the Government of Uganda in order to make oxygen available at all times by the completion of the Project.
 - 9-2. The Ugandan side expressed their needs for Soft Component under the Japan's Grant Aid for clinical operation and maintenance targeting some of procured medical equipment in the Project. The Team will convey the request to the Government of Japan.
 - 9-3. Both sides confirmed the tentative plan of the construction site of new facilities and the facilities to be demolished as shown in Annex 9 and 10. Based on this plan, both sides confirmed the followings would be the undertakings of the Government of Uganda;
 - 1) demolition of existing facilities and land leveling to construct new facilities
 - 2) providing alternative space for the services carried out in the demolished facilities during the construction period.
 - 9-4. Both sides noted that treatment of taxes and duties for the Project shall be in accordance with the agreement to be concluded between the Government of Uganda and the Government of Japan. MOH shall take necessary measures according to the agreement.
 - 9-5. Both sides agreed that the facility plan will be designed in accordance with the following policies.
 - Health Sector Development Plan 2015/16-2019/20 and the provisional facility master plans of Gulu RRH and Lira RRH should be referred. If the master plan or its draft of Arua RRH is established and submitted to JICA Uganda office by the end of March, 2017, this should be referred. The facilities to be constructed in the Project should be planned in consideration

that they will continuously take the central role of medical service delivery in the future.

- 2) The component and grade of facilities will be designed to achieve the objective of the Project.
- 3) The scale or size of the planned facilities of the target hospitals will be determined based on the present and past performance data on diagnosis and treatment, and also considered forecast population increases in the areas to be covered by these hospitals.
- 4) The facility plan will be formulated in consideration of the technical and fiscal sustainability of the hospitals, based on their management capabilities (the number of medical and healthcare professionals, their technical levels, financial affordability, state of procurement of consumables and spare parts, etc.) and staff reinforcement plan of the medical staff.
- 5) The Ugandan standards for earthquake resistance and wind force resistance will be adopted, and the structure of the facilities will be designed to allow the facilities to provide continuous medical activities without disruption in case of natural disasters.
- 6) The plot plan and construction plan will be designed to enable the provision of sustainable medical service delivery, and to minimize the influence of construction on medical service provision.
- 9-6. Both sides agreed that the equipment will be selected in accordance with the following criteria.
 - The equipment listed in the National Medical Equipment Policy (2009, MOH) should be referred to.
 - 2) The equipment plan will be formulated to achieve the objective of the Project.
 - 3) The selection and the number of the equipment to be procured will be determined based on the present and past performance data on diagnosis and treatment, and also on forecast of population increases in the areas to be covered by these hospitals.
 - 4) The equipment plan will be formulated in consideration of the technical and fiscal sustainability of the hospitals, based on their management capabilities (the number of medical and healthcare professionals, their technical levels to properly operate and maintain the equipment, financial affordability, state of procurement of consumables and spare parts, etc.) and staff reinforcement plan of the medical staff.
 - 5) The equipment to be installed to the facilities which will be constructed in

hè

the Project will be prioritized.

- 6) The room in the existing building where the equipment will be installed should be secured, and be made ready to install the equipment.
- 7) The equipment which will be installed in existing building should not require large scope of construction works for its installation.
- 8) The equipment for which spare parts and consumables are readily available in Uganda should be selected.
- 9) The equipment which can be maintained and repaired properly by the agencies in Uganda should be prioritized.
- 10) The equipment should not be for private use.
- 11) The equipment should be for clinical use. (General furniture, office equipment, etc. will be excluded.)
- 12) The equipment that can be easily procured by the Ugandan side will be excluded.
- 13) The equipment which will overlap the existing ones or will be supplied by other donors or by the budget of the Government of Uganda will be excluded.
- 9-7. The Team explained that the Team does not think of including CT scan in the Project because it requires high technical levels of healthcare professionals, high financial affordability, and highly stabilized infrastructure to operate and maintain. The Ugandan side expressed their strong need for CT scan and their will to take necessary measures to operate and maintain it.
- 9-8. In accordance with the selection criteria of equipment above, both sides agreed that the equipment which will be procured by Italian Cooperation or UNICEF will be excluded. MOH will submit the plan and/or the result of these two partners' projects by the end of March, 2017.
- 9-9. Both sides noted that it is necessary to consider the possibility of including maintenance service contract to some major medical equipment that needs frequent maintenance in the component of the Project.

Annex 1 Location map of the Project sites

Annex 2-1, 2-2, 2-3 Ownership of land

Annex 3-1, 3-2, 3-3 3-4 Organograms of MOH, the Health Infrastructure Division and 3 RRHs

Annex 4 Requested facilities list

Annex 5-1, 5-2, 5-3 Requested equipment list with priority

5

Annex 6 Japan Grant Aid


Annex 7 Project Monitoring Report (template)

Annex 8 Major Undertakings to be taken by the Government of Uganda

Annex 9-1, 9-2, 9-3 Plot plan of facilities in each RRH

Annex 10-1, 10-2, 10-3 Memorandum of meetings between each RRH and consultant

Jei



7

Annex 1: Location map of the candidate Project sites

Annex 2-1



GULU DISTRICT LOCAL GOVERNMENT

DEPARTMENT OF NATURAL RESOURCES LAND MANAGEMENT SECTOR

P.O. Box 2,

Date: 5th October, 2016

ł

The Chief Representative

Japan International Cooperation Agency (JICA)

RE: GULU REGIONAL REFERRAL HOSPITAL LAND

8

This letter serves to confirm that plot nos 4 – 10 Dr. Mathew Lukwiya Road – on Sheet No. 22/2/1/NE/4 is gazetted as Land belonging to Gulu Regional Referral Hospital.

The Board has received an application from the Hospital Management for acquiring a land title over the said plot and upon the acquisition of the land title, a copy shall be forwarded to your office.


J√u h-) ⇒ Ojera Alex


District Land officer/Gulu

Cc Director Gulu Regional Referral Hospital

Cc The Hospital Administrator/ Gulu Regional Referral Hospital


Cc File.






10

_____ ____







ULC/154/1052

		THE REPUBLIC OF UGANDA		
	REG	GISTRATION OF TITLES A	СТ.	
	Certi	ficate of (Litle.	\$1
	FREEHOLD REG	GISTER Volum	e 765 Folio 5	
	DE	ESCRIPTION OF LAN	ID	
	edged red on the	IAT piece of lan plan hereto annexe thereabouts and situ	ed containing the	
	Area.	County.	District.	
	16-023HECTARES	L.IRA MUNICIPALITY	LIRA	
	and known as AND 5-14 Agora R	S PLOTS 9-19, 21 -	- 41 Ngetta Road	
	(SUB JE	CT TO CONDITIONS	HEREIN)	
		OWNERSHIP		conn .
Date, time and Inst. No. REGD • 25 • 6 • 201 AT • 2 • 10P • M • INST • 439893	L	SSION OF P.O. BOX	: 36408,Kampala	Signature of Registrar
 Contribution for the second sec		prietors of an estate scribed subject to th einafter set out.	-	
	Dated this 2	ND day of July	r 20 10	
		• I	Registrar of Titles.	

OWNERSHIP–continued

Date, time nd Inst. No.	Name and Address of Owner	Signature of Registrar
	÷.	
	э	3
8.		
	4	
		1
	14	

CONDITIONS

1-1700-1

Date, time nd Inst. No.	Particulars	Signature of Registrar	
A)	USER TO BE RESTRICTED TO LIRA REGIONAL REFERRAL	•	_
5	HOSPITAL (HOSPITAL, MEDICAL TRAUNING SCHOOL AND A RECREATION GROUND)	Corror . S	D
	9 		
			*
	8		
			8
	1		17
	15 4	De	Kal

Annex 2-3

BOK	A
ALL AND	NØ
	P
E DEBUDU LO OR LÍO	

ULC/154/522

THE REPUBLIC OF UGANDA

REGISTRATION OF TITLES ACT.

Certificate of Title.

FREEHOLD REGISTER

Volume 657 Folio

Folio 16

DESCRIPTION OF LAND

ALL THAT piece of land delineated and edged red on the plan hereto annexed containing the following area or thereabouts and situate as follows:-

Area.	County.	District.
	ARUA	
9+920HECTARE	MUNICIPALITY	ARUA

and known as PLOT 26-62 AVENUE ROAD - ARUA

(SUBJECT TO CONDITIONS HEREIN)

OWNERSHIP

Date, time UGANDA LAND COMMISSION OF P.O. Box 36408, KAMPALA

ав.12.6.09 ,3.20р.м. г.414346

()

is/are now the proprietors of an estate in fee simple in the land above described subject to the conditions and incumbrances hereinafter set out.


16

Dated this 4TH day of

August 2009

Signature of Registrar

Registrar of Titles.




CONDITIONS

	CONDITIONS					
Date, time and inst. No.	Particulars				Signature of Registrar	
A) .	HINISTRY OF HEALT Hospital)	'H (Årua Ri	EGIONAL REFE	RRAE		
×				e.		
	ĝ					
			e.			
S.	2 8			5		
		u Ba				
					180	
				2		
				7	6 Frid	
		18		Π	Xe \	


Date, time and Inst. No.	Name and Address of Owner	Signature of Registrar
	3	
	5	
	1	
	98020 73	
	4 * * * *	*
	5. BA	
21		
2 ¹		
~		()
	- 19	S- N


i.


OWNERSHIP-continued




Organogram of the Health Infrastructure Division










Annex 3-3 Organogram of Lira RRH

24

W

Annex 3-4

Appendix (ii)



25

500.2.014

Annex 4 Requested facilities list

Hospital	Facility	Contents
Gulu	the Maternity /	Maternity
RRH	Theatre / Casualty	1) 75 to 81 patient beds
	Block	2) six delivery rooms
		3) one kangaroo care room
		4) one Neonatal Intensive Care Unit (NICU)
		Theatre
		5) one surgical operation room
		6) one orthopaedic operation room
		7) one obstetrics/gynaecology operation room
		8) one recovery space
		Casualty
		9) one resuscitation room for 12 to 15 beds
		10) one triage room/clinic
		11) one minor operation theatre connected to the Theatre
		Others
		12) one ICU^1 for four to six beds
		13) Central Supply and Sterilization Department
		(CSSD) adjacent to the Theatre and also
		accessible from other departments
		14) one connection corridor between the new
		building and the imagery building
Lira RRH	Outpatient	OPD
	Department (OPD)	1) one pharmacy/dispensary
	Complex	2) one satellite laboratory
		3) two pediatric consultation rooms
		4) one male consultation room
		5) one female consultation room
		6) one diabetic consultation room
		7) one dental clinic
		8) one Ear, Nose and Throat (ENT) clinic
		9) one Most At Risk Populations (MARPs) room
		10) one treatment room
2		11) one orthopedic consultation room
		12) one physiotherapy/occupational consultation room
		13) two specialized clinics
		Maternal and Child Health (MCH)
		14) one office for in charge
		15) one palpation room with six couches
		1.5) one parparon room with six couches

¹ The level of this ICU will be between the level which provides general intensive monitoring of the patients and the level which provides intensive care for the patients with one organ failure. The level will be almost the same as the level of HDUs in Hoima RRH and Kabale RRH built by the Project for the Rehabilitation of Hospitals and Supply of Medical Equipment in the Western Region in Uganda

F Ju-

		16) one treatment room
		17) one Early Infant Diagnosis (EID) point
		treatment room
		18) one immunization room,
		19) family planning
		20) cervical cancer screening
		X-Ray
		21) one X-Ray room
		22) one ultra sound room
		Casualty
		23) one resuscitation room with $10 - 12$ beds
	1	24) one minor operation theatre
		Others
		25) Waiting space for MCH attached to OPD
		complex
	Delivery Complex	1) six delivery suites
		2) one new born baby room (NICU)
	×	3) one sterilisation room
		4) one nurse station
		5) changing/wash rooms for nurses
Arua	the OPD and Casualty	OPD
RRH	unit	1) four general OPD consultation rooms
		2) one medical outpatient consultation room
		3) two paediatric rooms
		4) one surgical outpatient consultation room
		room
		6) one gynaecology consultation room
		_ · · · · · · · · · · · · · · · · · · ·
		*
		9) two HIV Counseling and Testing (HCT) rooms
		9) two HIV Counseling and Testing (HCT) rooms
		 9) two HIV Counseling and Testing (HCT) rooms 10) one MARPs room
		 9) two HIV Counseling and Testing (HCT) rooms 10) one MARPs room 11) one satellite laboratory
		 9) two HIV Counseling and Testing (HCT) rooms 10) one MARPs room 11) one satellite laboratory 12) one pharmacy/dispensary
		 9) two HIV Counseling and Testing (HCT) rooms 10) one MARPs room 11) one satellite laboratory
		5) one ENT and ophthalmology consultation

FL M

Requested No.	No.in Dep	Equipment Name	Final Q'ty	Final Priority
140.	OUT PAT		Gruy	THORICY
1		BP machines	8	1
2		weighing scales adult	5	2
3		weighing scales children	1	3
4		Height meters	5	6
5		Autoclaves	1	5
6		Pulse oximeters	8	7
7	7	Thermometers	8	8
8	8	Examination lights	8	4
	EMERGEN			
9		BP machine	6	10
10		Stethoscopes	6	11
11		Weighing scales infant	1	12
12		Thermometers	6	13
13		Pulse Oximeters	6	9
14		Oxygen Cylinder Set	5	5
15		Suction machines	3	3
16		Mobile X-ray		1
17		Ultrasound machine		2
18		X-ray film viewer boxes		17
19 20		Examination light	2	18
20		Infusions Pumps Patient monitor	4	19 6
21		Patient monitor Suction machine manual	3	6
22		Operation light (mobile)		16
23		Syringe pump	2	20
24		Emergency bed	4	15
26		Operation Table	1	14
27		Ambu bag	1	21
28		Cervical spine fixed color	2	22
29		Patient trolley	2	8
30		Wheel chair	3	7
		NG THEATRE		
31		Anesthetic machines	1	1
32	2	Operating lights	3	2
33		Patient monitor	4	4
34	4	Oxygen Cylinder Set	2	7
35		Suction machines	3	5
36	6	Weighing scales set	1	15
37		Operating Beds	3	3
38		Electro surgery machines	3	8
39		Defibrillators	1	9
40		Refrigerator	1	10
41		Operating light (mobile)	2	14
42		Patient trolley	5	11
43		Syringe pump	2	6
44		Instrument trolley	3	12
45		Mayo table	3	12
46		Instrument set for OT		13
		DEPARTMENT	1	
47 48		General mounted X-ray machine		1
48 49		Mobile X-ray CR machines	1	5
49 50		Mammography X-ray machine		9
50		CT Scan		9 4
52		Ultrasound machine		6
53		ECG	1	7
54	ן ג	Eco – cardiogram ultrasound machine		3
55		X-ray viewing boxes	10	10
56		Fluoroscopy X-ray machine	1	8
	ICU			U
57		ICU bed	4-6	2
60			1	4
58 59	2 3	Vital monitors Suction machines Oxygen cylinder set 28		3 5

Annex 5-1 Gulu RRH Requested Equipment List

No.	No. in Dep	Equipment Name	Final Q'ty	Final Priority
61	5	Autoclaves	1	6
62		Infusion pumps	1	7
63		Ventilator	1	1
64	8	Ambu bag	1	8
65		Nebulizer	1	9
	NICU			
66	1	Infants incubators	5	1
67	2	Photo therapy units	1	5
68		Patient monitor	1	8
69	4	Infusion Pumps	1	7
70	5	Pulse oximeters	2	3
71	6	Infant warmer	1	4
72	7	Examination lamp	2	6
73	8	Oxygen cylinder set	1	2
74		BP machine for infant	2	9
	OB&GY			
75	1	Examination Bed for Gyn	3	12
76	2	Examination beds	4	13
77		Ultrasound machines	2	9
78		Doppler Fetoscope	3	11
79		Autoclaves	1	2
80		Cryo-therapy machine	1	3
81		Oxygen cylinder set	4	5
82		Suction machines	4	6
83		Delivery bed	6	1
84		Fetal monitor	1	14
85		Vacuum extractor (manual)	2	4
86		Patient monitor	2	8
87		Infant warmer	2	10
88	14	Patient trolley	4	7
89		Corpo scope	1	15
90		Speculum set	20	17
91		Curettage Instrument set	5	16
92	18	LEEP machine	1	18
F	PAEDIATE	RICS		
93		Oxygen cylinder set	10	1
94	2	weighing scales infants	4	8
95	3	Infusion pumps	4	4
96	4	Patient Monitor	1	2
97		Stethoscopes	5	7
98		Examination lights		
0.0	7		3	9
99		Infant BP machines	3	6
100	8	Nebulizer		
100 101	8 9	Nebulizer Gluco meter	3	6
100 101	8 9 CSSD and	Nebulizer Gluco meter LAUNDRY	3 2 1	6 3
100 101 02	8 9 CSSD and 1	Nebulizer Gluco meter LAUNDRY Big Autoclaves	3 2 1 	6 3 5 1
100 101 102 102	8 9 <u>CSSD and</u> 1 2	Nebulizer Gluco meter LAUNDRY Big Autoclaves Laundry machine	3 2 1	6 3 5 1 2
100 101 102 103 104	8 9 <u>CSSD and</u> 1 2 3	Nebulizer Gluco meter LAUNDRY Big Autoclaves Laundry machine Ironing machine	3 2 1 	6 3 5 1 2 3
100 101 102 103 104 105	8 9 <u>CSSD and</u> 1 2 3 4	Nebulizer Gluco meter LAUNDRY Big Autoclaves Laundry machine Ironing machine Dryers	3 2 1 1 1 1 1 1 1	6 3 5 1 2 3 4
100 101 102 103 104 105 106	8 9 <u>CSSD and</u> 1 2 3 4 5	Nebulizer Gluco meter LAUNDRY Big Autoclaves Laundry machine Ironing machine Dryers Working table for CSSD	3 2 1 	6 3 5 1 2 3 4 7
100 101 102 103 104 105 106 107	8 9 <u>CSSD and</u> 1 2 3 4 5 5 6	Nebulizer Gluco meter LAUNDRY Big Autoclaves Laundry machine Ironing machine Dryers Working table for CSSD Laundry trolley	3 2 1 1 1 1 1 1 1	6 3 5 1 2 3 4 7 5
100 101 102 103 104 105 106 107 108	8 9 <u>CSSD and</u> 1 2 3 4 5 6 7	Nebulizer Gluco meter LAUNDRY Big Autoclaves Laundry machine Ironing machine Dryers Working table for CSSD	3 2 1 1 1 1 1 1 1	6 3 5 1 2 3 4 7
100 101 102 103 104 105 106 107 108 E	8 9 CSSD and 1 2 3 4 5 6 7 2 NT	Nebulizer Gluco meter LAUNDRY Big Autoclaves Laundry machine Ironing machine Dryers Working table for CSSD Laundry trolley Storage cabinet	3 2 1 1 1 1 1 1 1 1 1 1 1 1	6 3 5 1 2 3 4 7 5 6
100 101 102 103 104 105 106 107 108 108 109	8 9 CSSD and 1 2 3 4 5 6 7 7 ENT 1	Nebulizer Gluco meter LAUNDRY Big Autoclaves Laundry machine Ironing machine Dryers Working table for CSSD Laundry trolley Storage cabinet Tonsillectomy set	3 2 1 1 1 1 1 1 1 1 1 1 1 2	6 3 5 1 2 3 4 7 5 6
100 101 102 103 104 105 106 107 108 E 109 110	8 9 CSSD and 1 2 3 4 5 6 7 7 ENT 1 2	Nebulizer Gluco meter LAUNDRY Big Autoclaves Laundry machine Ironing machine Dryers Working table for CSSD Laundry trolley Storage cabinet Tonsillectomy set Adenoidectomy set	3 2 1 1 1 1 1 1 1 1 1 1 2 2 2	6 3 5 1 2 3 4 7 5 6 1 2
100 101 102 103 104 105 106 107 108 E 109 110 111	8 9 CSSD and 1 2 3 4 5 6 7 7 ENT 1 2 3	Nebulizer Gluco meter LAUNDRY Big Autoclaves Laundry machine Ironing machine Dryers Working table for CSSD Laundry trolley Storage cabinet Tonsillectomy set Adenoidectomy set Laryngoscopy set	3 2 1 1 1 1 1 1 1 1 1 1 2 2 2 1	6 3 5 1 2 3 4 7 5 6 1 2 3
100 101 102 103 104 105 106 107 108 E 109 110 111 111	8 9 CSSD and 1 2 3 4 5 6 7 7 ENT 1 2 3 4	Nebulizer Gluco meter LAUNDRY Big Autoclaves Laundry machine Ironing machine Dryers Working table for CSSD Laundry trolley Storage cabinet Tonsillectomy set Adenoidectomy set Laryngoscopy set Caldwell luc set	3 2 1 1 1 1 1 1 1 1 1 1 2 2 2	6 3 5 1 2 3 4 7 5 6 1 2 3 4
100 101 102 103 104 105 106 107 108 E 109 110 111 112 113	8 9 CSSD and 1 2 3 4 5 6 7 7 ENT 1 2 3 4 5	Nebulizer Gluco meter Gluco meter LAUNDRY Big Autoclaves Laundry machine Ironing machine Dryers Working table for CSSD Laundry trolley Storage cabinet Tonsillectomy set Adenoidectomy set Laryngoscopy set Caldwell luc set Tracheostomy set	3 2 1 1 1 1 1 1 1 1 1 1 2 2 2 1 1 1 1	6 3 5 1 2 3 4 7 5 6 1 2 3 4 1 2 3 4 13
100 101 002 103 104 105 106 107 108 E 109 110 111 112 113 114	8 9 CSSD and 1 2 3 4 5 6 7 7 ENT 1 2 3 4 5 6	Nebulizer Gluco meter LAUNDRY Big Autoclaves Laundry machine Ironing machine Dryers Working table for CSSD Laundry trolley Storage cabinet Tonsillectomy set Adenoidectomy set Laryngoscopy set Caldwell luc set Tracheostomy set Suction machines	3 2 1 1 1 1 1 1 1 1 1 1 1 2 2 2 1 1 1 1	6 3 5 1 2 3 4 7 5 6 6 1 2 3 4 13 7
100 101 03 103 104 105 106 107 108 E 109 110 111 112 113 114 115	8 9 CSSD and 1 2 3 4 5 6 7 2 NT 1 2 3 4 5 6 7	Nebulizer Gluco meter LAUNDRY Big Autoclaves Laundry machine Ironing machine Dryers Working table for CSSD Laundry trolley Storage cabinet Tonsillectomy set Adenoidectomy set Laryngoscopy set Caldwell luc set Tracheostomy set Suction machines Operating Microscopes	3 2 1 1 1 1 1 1 1 1 1 1 1 2 2 2 2 1 1 1 1 2 1	6 3 5 1 2 3 4 7 5 6 8 1 2 3 4 13 7 9
100 101 102 103 104 105 106 107 108 E 109 110 111 112 113 114 115 116	8 9 CSSD and 1 2 3 4 5 6 7 ENT 1 2 3 4 5 6 7 8	Nebulizer Gluco meter LAUNDRY Big Autoclaves Laundry machine Ironing machine Dryers Working table for CSSD Laundry trolley Storage cabinet Tonsillectomy set Adenoidectomy set Laryngoscopy set Caldwell luc set Tracheostomy set Suction machines Operating Microscopes Middle ear set	3 2 1 1 1 1 1 1 1 1 1 1 1 2 2 2 1 1 1 1	6 3 5 1 2 3 4 7 5 6 8 1 2 3 4 13 7 9 10
100 101 102 103 104 105 106 107 108 E 109 110 111 112 113 114 115 116 117	8 9 CSSD and 1 2 3 4 5 6 7 ENT 1 2 3 4 5 6 7 7 8 9	Nebulizer Gluco meter LAUNDRY Big Autoclaves Laundry machine Ironing machine Dryers Working table for CSSD Laundry trolley Storage cabinet Tonsillectomy set Adenoidectomy set Laryngoscopy set Caldwell luc set Tracheostomy set Suction machines Operating Microscopes Middle ear set Mastoid drill	3 2 1 1 1 1 1 1 1 1 1 1 1 2 2 2 2 1 1 1 1 2 1	6 3 5 1 2 3 4 7 5 6 1 2 3 4 13 7 9 10 11
100 101 102 103 104 105 106 107 108 E 109 110 111 112 113 114 115 116 117 118	8 9 CSSD and 1 2 3 4 5 6 7 ENT 1 2 3 4 5 6 7 7 8 9 9 10	Nebulizer Gluco meter LAUNDRY Big Autoclaves Laundry machine Ironing machine Dryers Working table for CSSD Laundry trolley Storage cabinet Tonsillectomy set Adenoidectomy set Laryngoscopy set Caldwell luc set Tracheostomy set Suction machines Operating Microscopes Middle ear set Mastoid drill Esophagoscopy	3 2 1 1 1 1 1 1 1 1 1 1 1 2 2 2 2 1 1 1 1 2 1	6 3 5 1 2 3 4 7 5 6 1 2 3 4 1 3 4 13 7 9 10 11 6
100 101 102 103 104 105 106 107 108 E 109 110 111 112 113 114 115 116 117	8 9 CSSD and 1 2 3 4 5 6 7 ENT 1 2 3 4 5 6 7 7 8 9 9 10 11	Nebulizer Gluco meter LAUNDRY Big Autoclaves Laundry machine Ironing machine Dryers Working table for CSSD Laundry trolley Storage cabinet Tonsillectomy set Adenoidectomy set Laryngoscopy set Caldwell luc set Tracheostomy set Suction machines Operating Microscopes Middle ear set Mastoid drill	3 2 1 1 1 1 1 1 1 1 1 1 1 2 2 2 2 1 1 1 1 2 1	6 3 5 1 2 3 4 7 5 6 1 2 3 4 13 7 9 10 11

29

F b

Requested No.	No. in Dep	Equipment Name	Final Q'ty	Final Priority
122		Walsham forceps	1	14
	ABORAT			14
123		Binocular microscopes	2	5
124	2	Centrifuge	3	11
125		Fridges	2	1
126		Glucometer	3	10
127		Water bath	1	11
128		Incubators	1	12
129		Safety cabinets	1	13
130		shakers	3	14
131		Pipette	5	9
132		Heamometers Water distiller	1	15
134		Chemistry analyzer		8 16
135		Autoclaves		6
136		Hot air oven	1	7
137		Deep freezer	1	2
138	16	Blood bank refrigerator	1	4
139		ELISA system with PCR	1	3
140		Electrolyte analyzer		5
141		Eye wash station	1	17
142		GeneXpert	1	18
	DENTAL			
143		Dental unit	3	1
144	2	Dental X-ray	1	2
145		Dental instrument sets	1	3
146	4	Light Curing machines	1	4
147	5	Intra oral cameras	1	7
148		Pulp Tester	1	5
149		Dental laboratory equipment	1	8
150		Autoclaves	1	6
	HARMAC			
151		Drugs shelves	1	4
152	2	Drugs fridges	4	1
153	3	Dispensing tray	6	5
154 155		Drug trolley	5	3
		Cupboard	2	2
156		Oxygen cylinder set	3	2
157	2	Vital monitors	2	4
158		Autoclaves	1	1
159		Examination lights	2	6
160		BP machines	2	9
161		Suction machine	2	3
162		Patient trolley	2	11
163	8	Drum set	2	5
164		Diagnosis set		7
165	10	Weighing scale	1	10
166		Pulse oximeter	1	8
		MEDICINE		
167		Endoscopy unit	1	12
168		BP machine	4	7
169		Weighing scales	3	11
170		Pulse oximeter	2	9
171		Portable ultrasound machine	1	3
172		Oxygen cylinder set	6	1
173 174		Nebulizer Diagnosis set	4	2
174		Diagnosis set	2	8
175		Patient trolley	4	6
170		Nheel chair	4	14
178		Fibroscan	4	4
179		Medicine trolley	4	4
180		Suction machine	2	15
181		Ventilator	1	13
	101			0
				\bigcirc
				pra
		30		

NI,

GULU RRH

equested No.	No.in Dep	Equipment Name	Final Q'ty	Final Priority
	AMBULA	NCE		
182		Ambulance	1	
		EDIC CLINICAL		
183		Plaster shear Manual	2	2
184		Plaster shear (electrical)	1	1
185		Plaster opener	2	4
186		Plaster bender	2	6
187		Splint set	1	3
188		Operating Fracture bed	1	7
189		C-Arm		5
190		Film viewer		8
100	PHYSIOT			0
		erapy Section		
191		UV Lamp	2	13(1A, 1B)
192		Therapeutic ultrasound	2	2(1A, 1B)
193		Short wave diathermy		
194		TENS		3
195		EMS	1	11
195		Infra-Red Radiation lamps	1	15
196			2	4
197		Electrical massager	2	12
198				1
		Traction machines (Cervical and lumber)		1
199	9	Therapeutic Massage beds	3	5
000		herapy section	- 1	r
200		Tread mill	2	6
201		Pulley systems	1	16
202		Suspension bed	1	17
203		Muscle strengthening weights	2	18
204		Therapeutic mats	3	19
205		Postural mirror	1	20
206		Hand exercise equipment	1	24
207		Shoulder wheels	1	25
208		stationary bikes, – adult	2	8
209	19	Stationary bikes - children	1	9
210		Quadriceps bench with accessories like weights	1	7
211		Bo baths balls different sizes	1	10
212	22	Stares adult	1	26
213		Stares children	1	27
214		Parallel bars children	1	28
215		Abdominal strengthening equipment	1	21
		apy facilities		
216	26	Warm parks equipment	2	22
217		Cold parks equipment	2	23
218	28	Parallel bars adult	1	29
219	29	Electrical Oscillatory manipulative bed	1	14
		lic workshop		
220		Jig saw	1	5
221		Heavy duty oven		9
222		Rotor machine	1	1
223		Dust Suction machine	2	3
224		Pressure compressor	1	4
225		Vertical band saw		12
226		Pipe bender		2
227		Hand drilling machine	2	6
228		Vacuum machine		7
229		Automatic parallels bars		10
229		Mirror		
230				11
		Polishing machine	1	8
232		Carpentry tool box		5
233		Plumbing tool box	1	4
234		Oxygen gas analyzer	2	7
235		Digital Multi-meter	2	6
236		Welding generator	1	2
237	6	Heavy Duty Engraving machine	1	8
238	7	Electric safety analyzer machine	1	9

F

S

GULU RRH

Requested No.	No. in Dep	Equipment Name	Final Q'ty	Final Priority
239	8	Working mats for electronics	1	10
240		Electronics tool box	2	1
241		Mechanical tool box	2	3
	OPTHAL	MOLOGY		
242	1	Operating Microscopes	1	1
243	2	Slit lamp	1	4
244	3	Visual field analyzer (automated)	1	2
245		Hand held portable slit lamp	1	7
246	5	Direct ophthalmoscope	3	8
247	6	Parkins tomometer	1	11
248	7	Cataract set	8	6
249	8	Extra owler (lid surgery) set	5	10
250	9	Suction machines	1	3
251	10	Magnifying head loop	4	9
252		Autorefracto meter	1	5
1	MENTAL	HEALTH CARE		
253	1	BP machines	3	1
254	2	Weighing scale	4	3
255	3	Autoclaves	1	2
256	4	Drum set	2	7
257		Oxygen cylinder	2	11
258		ECT (Electroconvulsive Therapy)	1	6
259		Pulse oximeter	1	4
260	8	Patient trolley	2	5
261		Examination bed	3	10
262		Infusion pump	1	8
263	11	Wheel chair	2	9

f <u>b</u>

No.	Dep.	Equipment Name	Final Q'ty	Final Priority
	Out Pati	ent		
1	1	BP machine	each clinical room	1
2	2	Examination Couch	each clinical room	3
3	3	Wheel Chair	2	4
4	4	Weighing Scale	each clinical room	5
5	5	Glucometer	each clinical room	6
6	6	Diagnostic set	each clinical room	2
7	7	Patient trolley	1	7
	OB/GYN			
8	1	Delivery Bed	4	1
9		Operation Light mobile	2	2
10		Oxygen cylinder set	2	7
11		suction Machine	2	11
12		Examination Couch	2	5
13		weighing and height Scale	3	8
14		BP machine	4	4
15		Cesarean operating instrument set	4	3
16		Intubation set	2	13
17		Resuscitation kit	1	14
18		Autoclave		9
19		Patient monitor		12
20		Examination bed for OBGY	2	
20			2	6
		Drum set	3	10
	Imaging	СТ		
22		No. 1997	1	4
23		Fluoroscopy machine		5
24		ultra sound scanner	1	3
25		Fixed X-ray with card reader	1	1
26		Automatic film processor	1	2
27		Read character	1	7
28		Mobile X-ray machine	1	6
29		CR system	1	8
	Ambulanc			
30		Ambulance	1	1
	Emgency			
31		Ventilator	2	4
32		Anesthesia machine	1	5
33		Autoclave	1	7
34		patient Trolley	4	10
35	5	suction machine	2	8
36	6	Operation table	1	2
37	7	patient Monitor	2	6
38		Operating instrument set	2	11
39		Emergency bed	4	1
40		Diagnostic set	2	12
41		Drum Set	5	9
42		B.P. machine	2	13
43		Operation light mobile	1	3
		on in Thetre and OBGY	i i	J
44		Autoclave for sterilization	2	1
44		Boiler	1	
45		Storage cabinet		2
40			2	3
		Steel cabinet	2	4
	aundry	la va da sua a bi-		
48		laundry machine	1	1
49		Heavy duty electric iron	11	2
50		Dryer	1	3
	Dental			
51		Dental Chair	4	1
	2	Dental X-Ray	1	2
52				
	3	Autoclave Light cure machine	1	3 5

Annex 5-2 Lira RRH Requested Equipment List

Requested No.	No.in Dep:	Equipment Name	Final Q'ty	Final Priority
55	•	Electronic scaler	1	6
56		Dry-heat sterilizer	1	9
57		Dental forceps (all sets)	5	4
58		Sterilizing box set	1	10
59		Drums set	1	11
60		Pulp tester	1	7
61		Intra oral cameras	1	8
	Peadiatri			
62	1	Oxygen cylinder set	1.0	1
63		Radiant warmer (for NICU)	2	2
64	3	Incubator (for NICU)	2	3
65		weighing scale	2	4
66		patient Monitor	2	5
67	6	Pulse oximeter	8	6
68	7	Pediatric BP machine	3	7
69		Diagnostic set	3	8
		n Theatre		
70		Anesthesia machine	1	1
71		Patient Monitor	1	2
72		suction machine	3	6
73		Oxygen cylinder set	4	5
74		Operation table	2	7
75		Pulse oximeter	4	3
76		BP machine Digital	4	4
77		Glucometer	1	8
78		Sterilizing drum Large	10	13
79		Sterilizing drum Medium	5	14
80		Sterilizing drum Small	5	15
81		Operation light portable	2	9
82		Autoclave	1	10
83		patient Trolley	2	11
84		Laparotomy set	1	12
85		Instrument trolley	2	16
	Sugery W	lard		
86		Autoclave	2	2
87		suction machine	2	11
88		BP machine	2	12
89		examination couch	3	8
90		Drip stand	10	7
91		Patient trolley	2	3
92		Wheel Chair	2	4
93	8	Drum set	3	6
94		Oxygen cylinder set	2	1
95		Dressing trolley	2	9
96		Drug trolley	2	10
97		Resuscitation kit	2	5
98		Glucometer	2	13
99		Dressing instrument set	2	14
100		Pulse oximeter	2	15
101		Weighing scale	2	16
E	ENT			
102	1	ENT examination microscope	1	9
103		ENT examination set complete	1	1
104		Mastidectomy set	1	8
105		Tonsillectomy set	1	7
106		Bronchoscopy set	1	2
107		ENT examination unit	1	6
108		Tympanometer	1	3
109		BP machine	1	5
110		Audiometer	1	4
1101				

34

7

R

Requested No.	No. in Dep.	Equipment Name	Final Q'ty	Final Priority
112	2	Biochemistry machine	1	4
113		Refrigerator Blood Bank	1	1
114		Microscope	2	5
115	5	Centrifuge	2	10
116	6	Incubator	1	7
117	7	Autoclave	1	6
118	8	Voltex mixer	1	11
119	9	weighing scale	1	9
120	10	Water desterilizer	1	8
121	11	Refrigerator	1	2
	Internal M			
122	1	Oxygen cylinder set	2	2
123		Nebulizer	1	4
124		suction Machine	1	6
125		patient Trolley	2	5
126		syringe pump	2	8
127		infusion pump	2	7
128		Drip stand	10	3
129		Ultrasound machine portable	1	1
	CU			
130		syringe pump	2	1 1
	harmac		4	1. ť
131		y Refrigerator (large)	7	1
132			4	2
132		Refrigerator (small)		
133		Table drug	1	5
		Drug trolley Steel cabinet	3	6
135			2	8
136		Water destilizer	2	4
137		Autoclave		3
138		Drug cupboard	7	7
		quipment		
139		Portable oscilloscope	1	7
140		Thermometer/hygrometer	1	9
141		Analyzer Tachometer	1	8
142		Insulation resistance tester	1	1
143		Earth mega tester	1	3
144		Cramp meter	1	2
145		Welding machine mobile	1	5
146	8	Electrical tool box	1	6
147		Pipe bender	1	4
(Orthoped	lic workshop		
148	1	Broad Belt Sander	1	4
149	2	Vacuumed machine	1	3
150	3	Welding hot jet	1	5
151		Welding MIRROR	1	2
152	5	Router machine	1	1
	Orthoped			
153		Oscillation Plaster cutter	1	1 1
154		Plaster share	1	2
155		Plaster bender	1	6
156		Plaster opener	1	8
157		Operating flucture bed	1	9
158		Bone fracture instrument set	1	7
159		Thomas splint	20	3
160		Browne splint	20	4
161		Electrical bone drill	1	10
161		Wheel Chair	5	
) Dpthalom		Ü	5
163			4	1 2
		Operating microscope	1	2
164		Cataract operation instrument set	6	3
165	~~	Autoclave	1	4
166		Slit lamp with Tonometer	1	6
167	51	Area thetie machine		5

Requested No.	No.in Dep.	Equipment Name	Final Q'ty	Final Priority
168	· · ·	Instrument trolley	2	11
169		Kerato meter	1	7
170		Trial lens set	1	10
171	9	weighing scale	2	9
172		BP machine	2	8
173		Phaco emulsification machine	1	1
	Physioth			-h)
174	1	Ultrasound therapy	1	2
175	2	Short wave therapy	1	1
176	3	Infra-Red Radiation lamps	1	3
177	4	Exercise mat	2	5
178	5	Stationary bike	2	6
179		Balance ball	2	7
180		Traction bed	1	4
181		Electrical massager	1	8
182		Refrigerator	1	9
	Mental H			
183	1	Drug trolley	2	4
184		Drug cupboard	1	3
185		Examination coach	2	2
186	4	Chito forceps	2	6
187		Drums set	2	5
188		Autoclave	1	1 1
189		Drip stand	4	7
F	Pathology			
190	1	Mortuary refrigerator	1	2
191	2	Mortuary trolley with cover	2	1
192		Mortuary Instrument set	1	4
193		Holding patient trolley	2	3
1	NMCH			
194	1	Examination couch	9	1
195		Examination lump	2	7
196	3	Speculum set	1	8
197	4	Uterine sonde set	2	13
198	5	Uterine Elevator instrument set	5	14
199	6	Drum set	4	5
200	7	Cupboard	2	9
201	8	Deep freezer	1	4
202	9	Refractor for vaccines	1	3
203		Vaccine carrier	10	6
204		Weighing scale neonatal	3	10
205		BP machine	7	2
206		Weighing and height scale adult	3	10
207		Patient trolley	1	11
208		Wheel chair	1	12

S

4

equested No.	No. in Dep	Equipment Name	Final Q'ty	Final Priority
	Accident	And Emergency		
1	1	Vital sign monitor [ECG,Pulse rate Bp,SP2]	2	1
2	2	Endoscopy machine	1	19
3	3	Emergency Respirators	1	2
4	4	Defibrilators	1	16
5	5	Oxygen cylinder set	2	8
6	6	Suction machine Electrical	2	3
7	7	Nebulizer	2	4
8	8	Patient transfer trolleys	4	5
9	9	Wheel chairs	4	9
10	10	Operating table	1	6
11	11	Operating light mobile	1	7
12	12	Drug trolley	1	17
13	13	Medicine Cupboaards	2	18
14	14	Emergency Bed	5	10
15	15	Examination light	1	11
16	16	Dressing cart	1	12
17	17	Dressing instrument set	1	14
18	18	Diagnosis set	1	15
19	19	Minor surgery instrument set,	1	13
20	20	Autoclave	1	20
	Ambulanc			
21	1	Ambulance	1	1
	Dental		'	
22	1	Dental Unit	3	1
23	2	Dental imaging/x-ray machine and processors	1	2
24	3	Vacuum Autoclaves	1	4
25	4	LED cure lights	2	6
26	5	Ultrasonic Scalers	2	7
27	6	Ultrasonic cleaner	1	8
28	7	Dental implant surgical motors	1	15
29	8	Handpieces oiler	1	9
30	9	Apex Locators	1	10
31	10	Casting machine	1	11
32	11	Polishing and trimming machines	1	12
33	12	Hydroflasks, Heat cure flasks and articulators	1	13
34	13	Orthopantomogram	1	14
35	14	Electric pulp tester	2	5
36	15	Dental instrument set	1	3
		onal Therapy		0
37	1	Large portable mirrow	1 1 1	2
38	2	Sewing machines	1	3
39	3	Standing frames, adults and children	1	6
40	4	Walking frames, adults and children	2	4
41	5	Parralel bars, adults and children	1	1
42	6	Prone baords		5
	Physiothe		'	
43	1	Short wave Diathermy	2	1
44	2	Infra Red machine	2	2
45	3	Ultra sound Machine	1	3
46	4	Muscle stimulators		4
47	5	Cervical Traction machine		5
48	6	Lumbar traction machine		6
49	7	TENS Machine	2	7
50	8	Shoulder traction machine		8
50	9	Stational bicycle	2	9
52	10	Exercise mat	3	
53	11	Wheel chair	5	10
54	12	Bobbath ball	5	12
55	13	Hand therapy springs	2	12

Annex 5-3 Arua RRH Requested Equipment List

37

equested No.	No. in Dep	Equipment Name	Final Q'ty	Final Priority
	Imargery			
56	1	Computerised Tommographic Scan (CT-Scan)	1 1 1	1
57	2	Berium Enamel set	1 i 1	6
58	3	Mamography Machine	- i - i	4
59	4	Ultra sound scan [Cardiac Abdominal,obstetric] with doppler	1 1	2
60	5	Digital Radiography system DRS		3
61				
	7	Hysterosalpingogram set		7
62	8	Electro encephalogram	1 1	
	Pharmacy			
63	1	Refrigerators Large	1	1
64	2	Drug Cupboards Metallics	3	2
65	3	Autoclave	1	4
66	4	Dry oven	Ĩ	5
67	5	Water Distillers	2	3
68	6	Water bath	1	6
69	7	Weighing scale digital	2	7
	Orthopea			,
70	1	Gypsum cutter		1
70	2	Manual Plaster cutter	1	
			2	14
72	3		1	2
73	4	Oxygen cylinder and mask	11	3
74	5	Dressing set	1	4
75	6	Dressing trolly	1	5
76	7	Patient trasnfer trolly	2	6
77	8	Drug trolly	1 1	7
78	9	Drum set	1	8
79	10	Autoclye	1	9
80	11	Drip stand	10	10
81	12	Examination couch	3	11
82				
	13	Plaster table	1	12
83	14	Wheel chiar	2	13
84	15	Bed craddle	5	15
85	16	Working frame	2	16
86	17	Orthopedic braun frame for traction	5	17
87	18	C-arm	1	18
88	19	Instrument set for orhopedic surgery	1	19
	Laborator			
89	1	Heamatology analyser [5 parameetre]	1 1	7
90	2	Clinical Chemistry Analysers	1	8
91	3	Refrigerator	2	1
92			-	
	4	Electrical centrifuge [8-12 Buckets]	2	2
93	5	Orbital shaker		9
94	6	Blood mixer [Roller]	1	10
95	7	Laboratory incubator	1	11
96	8	Electrical weighing Scale [Laboratory]	1	4
97	9	Weighing Scale for blood transfusion	1	3
98	10	Autoclave Elecrtical	1	5
99	11	Microscope Olympus	2	6
100	12	Hemoglobino meter	1	12
	CSSD		<u> </u>	16.
101	1	Autoclave Set	TIT	1
102				1
	2	Whashing Machines		-
103	3	Dryer		2
104	4	Irooning roller	1	3
105	5	Flat ironning machine		5
106	6	Laundry trolley	4	4
	MARTENI			
	Labour	and Delivery room , HDU		
107	1	Vital sign monitor [ECG,Pulse rate ,SP2,Foetal doppler]	3	4
108	2	Blood preesure machine wll mounted or on stands	32	9
109	3	Delivery Beds	8	1
	Ų	In the second seco	_	
110	4	Infant Warmer	3	3

Þ

Requested No.	No. in Dep	Equipment Name	Final Q'ty	Final Priority
112	6	Oxygen cylinder set	5	11
113	7	Wheel chairs	2	12
114	8	Examminations spot lights	2	10
115	9	Instrument set for delivery	10	5
116	10	Suction machine Electrical	2	8
117	11	Fetal dopper	2	7
118	12	Ambubag set fro neonatal	2	6
119	13	Vacuum extractor	1	13
	OB/GY			
120	1	Vital sign monitor [ECG,Pulse rate Bp,SP2]	2	4
121	2	Drug Trolleys	3	7
122	3	Dressing trollely	3	8
123	4	Dressing sets [Forceps,Kidney dishes,arteries etc]	2	5
124	5	Examination table	3	3
125	6	Fetal dopper	2	6
126	7	Instrument set for examination	11	2
127	8	Blood pressure	6	1
	Theatre			
128	1	Vital sign monitors	2	1
129	2	Electrical suction machine	2	2
130	3	Anasthetic machine	1	3
131	4	Ceiling mounted mobile type	2	4
132	5	Oxygen cylinder set	2	5
133	6	Autoclave	1	7
134	7	Instrument Set for theatre	1	6
	Neonta	al unit		
135	1	Incubators	4	3
136	2	Oxygen cylinder set	4	6
137	3	Baby courches	5	2
138	4	Vital sign monitor [ECG,Pulse rate Bp,SP2]	2	1
139	5	Suction machine electrical	1	7
140	6	Infant Radiant Warmers	2	5
141	7	Continuous postive air way pressure(CPAP) sets	1	4
	Internal M			
142	1	Oxygen cylinder set	5	11
143	2	Suction machine Electrical	2	2
144	3	Autoclave small	1	3
145	4	Wheel chair	3	4
146	5	Vital sign monitor [ECG,Pulse rate Bp,SP2]	2	5
147	6	Patient trolley	2	6
148	7	HBAIc machine	1	8
149	8	Drug infusion pumps	4	9(2A, 2B)
150	9	Nebulisers	1	10
151	10	Diagnostic set general	2	7
152	11	Refrigerators medicine	2	12(1A, 1B)
153	12	Dressing instrument set	2	13
154	13	Drug trolley	2	14
155	14	Instument drums set	1	15
156	15	Patient examination coach	2	18
157	16	Glucometer	2	19
158	17	Pulsoximeter	2	20
159	18	Weighing scale	2	21
		ating Theatre		r
160	1	Operating table	3	1 (2A, 1B)
	2	Vital sign monitor [ECG,Pulse rate Bp,SP2]	3	4(2A, 1B)
161	3	Operating lamp mobile type	3	2(2A, 1B)
162	4	Anaesthetic Machine	2	6
162 163		Electrical Dermatome(Skin Graft Set)	2	5(1A, 1B)
162 163 164	5			
162 163 164 165	6	Oxygen cylinder set	2	9
162 163 164 165 166	6 7	Oxygen cylinder set Pneumatic tournique	2	8
162 163 164 165 166 167	6 7 8	Oxygen cylinder set Pneumatic tournique Patient Transfer trolley	2 2 2	87
162 163 164 165 166	6 7	Oxygen cylinder set Pneumatic tournique	2	8

Requested No.	No. in Dep	Equipment Name	Final Q'ty	Final Priority
170	11	Instrument set for OP theatre	1	11
	General			
171	1	Vital sign monitor [ECG,Pulse rate Bp,SP2]	2	5
172	2	Oxygen cylinder set	2	7
173	3	Suction machine	2	6
174	4	Medicine/treatment trolleys	4	3
175	5	Patient screens	6	8
176	6	Patient transfer trolleys	3	2
177	7	Instrument set	1	1
178	8	Dressing trolley	4	4
	Pediatric			
179	1	Oxygen cylinder set	4	1
180	2	Nebulisers	3	2
181	3	Vital sign monitor [ECG,Pulse rate Bp,SP2]	2	3
182	4	infant and child Blood pressure machine	6	4
183	5	Pulse oximetre	10	6
184	6	Patient screens	4	12
185	7	reservoir bags with face masks	4	13
186	8	Examination couch	5	7
187	9	Stethoscope paediatrics	3	8
188	10	Files trolley	3	11
189	11	Diagnosis set	3	10
190	12	Thermometre digital	12	9
191	13	Examination light	5	5
	Medical E	Equipment Workshop		
192	1	Electronic / Electrical tools	2	7
193	2	Refrigeration tools	1	1
194	3	Oxygen analyser	2	5
195	4	Mechanical tools	2	6
196	5	Welding Genarator Portable	1	4
197	6	Plumbling Tool	1	9
198	7	Drilling machine	1	3
199	8	Carpently tool set	1	10
200	9	Multimeter	2	8
201	10	Clamp meter	2	2

T de

JAPANESE GRANT

The Japanese Grant is non-reimbursable fund provided to a recipient country (hereinafter referred to as "the Recipient") to purchase the products and/or services (engineering services and transportation of the products, etc.) for its economic and social development in accordance with the relevant laws and regulations of Japan. Followings are the basic features of the project grants operated by JICA (hereinafter referred to as "Project Grants").

1. Procedures of Project Grants

Project Grants are conducted through following procedures (See "PROCEDURES OF JAPANESE GRANT" for details):

- (1) Preparation
 - The Preparatory Survey (hereinafter referred to as "the Survey") conducted by JICA
- (2) Appraisal

-Appraisal by the government of Japan (hereinafter referred to as "GOJ") and JICA, and Approval by the Japanese Cabinet

- (3) Implementation
 - Exchange of Notes
 - -The Notes exchanged between the GOJ and the government of the Recipient
 - Grant Agreement (hereinafter referred to as "the G/A")
 - -Agreement concluded between JICA and the Recipient
 - Banking Arrangement (hereinafter referred to as "the B/A")
 - -Opening of bank account by the Recipient in a bank in Japan (hereinafter referred to as "the Bank") to receive the grant
 - Construction works/procurement

-Implementation of the project (hereinafter referred to as "the Project") on the basis of the G/A

(4) Ex-post Monitoring and Evaluation

-Monitoring and evaluation at post-implementation stage

2. Preparatory Survey

(1) Contents of the Survey

The aim of the Survey is to provide basic documents necessary for the appraisal of the the Project made by the GOJ and JICA. The contents of the Survey are as follows:

- Confirmation of the background, objectives, and benefits of the Project and also institutional capacity of

41

relevant agencies of the Recipient necessary for the implementation of the Project.

- Evaluation of the feasibility of the Project to be implemented under the Japanese Grant from a technical, financial, social and economic point of view.
- Confirmation of items agreed between both parties concerning the basic concept of the Project.
- Preparation of an outline design of the Project.
- Estimation of costs of the Project.
- Confirmation of Environmental and Social Considerations

The contents of the original request by the Recipient are not necessarily approved in their initial form. The Outline Design of the Project is confirmed based on the guidelines of the Japanese Grant.

JICA requests the Recipient to take measures necessary to achieve its self-reliance in the implementation of the Project. Such measures must be guaranteed even though they may fall outside of the jurisdiction of the executing agency of the Project. Therefore, the contents of the Project are confirmed by all relevant organizations of the Recipient based on the Minutes of Discussions.

(2) Selection of Consultants

For smooth implementation of the Survey, JICA contracts with (a) consulting firm(s). JICA selects (a) firm(s) based on proposals submitted by interested firms.

(3) Result of the Survey

JICA reviews the report on the results of the Survey and recommends the GOJ to appraise the implementation of the Project after confirming the feasibility of the Project.

3. Basic Principles of Project Grants

(1) Implementation Stage

1) The E/N and the G/A

After the Project is approved by the Cabinet of Japan, the Exchange of Notes (hereinafter referred to as "the E/N") will be singed between the GOJ and the Government of the Recipient to make a pledge for assistance, which is followed by the conclusion of the G/A between JICA and the Recipient to define the necessary articles, in accordance with the E/N, to implement the Project, such as conditions of disbursement, responsibilities of the Recipient, and procurement conditions. The terms and conditions generally applicable to the Japanese Grant are stipulated in the "General Terms and Conditions for Japanese Grant (January 2016)."

2) Banking Arrangements (B/A) (See "Financial Flow of Japanese Grant (A/P Type)" for details)

- a) The Recipient shall open an account or shall cause its designated authority to open an account under the name of the Recipient in the Bank, in principle. JICA will disburse the Japanese Grant in Japanese yen for the Recipient to cover the obligations incurred by the Recipient under the verified contracts.
- b) The Japanese Grant will be disbursed when payment requests are submitted by the Bank to JICA under an Authorization to Pay (A/P) issued by the Recipient.

3) Procurement Procedure

The products and/or services necessary for the implementation of the Project shall be procured in accordance with JICA's procurement guidelines as stipulated in the G/A.

4) Selection of Consultants

In order to maintain technical consistency, the consulting firm(s) which conducted the Survey will be recommended by JICA to the Recipient to continue to work on the Project's implementation after the E/N and G/A.

5) Eligible source country

In using the Japanese Grant disbursed by JICA for the purchase of products and/or services, the eligible source countries of such products and/or services shall be Japan and/or the Recipient. The Japanese Grant may be used for the purchase of the products and/or services of a third country as eligible, if necessary, taking into account the quality, competitiveness and economic rationality of products and/or services necessary for achieving the objective of the Project. However, the prime contractors, namely, constructing and procurement firms, and the prime consulting firm, which enter into contracts with the Recipient, are limited to "Japanese nationals", in principle.

6) Contracts and Concurrence by JICA

The Recipient will conclude contracts denominated in Japanese yen with Japanese nationals. Those contracts shall be concurred by JICA in order to be verified as eligible for using the Japanese Grant.

7) Monitoring

The Recipient is required to take their initiative to carefully monitor the progress of the Project in order to ensure its smooth implementation as part of their responsibility in the G/A, and to regularly report to JICA about its status by using the Project Monitoring Report (PMR).

8) Safety Measures

The Recipient must ensure that the safety is highly observed during the implementation of the Project.

9) Construction Quality Control Meeting

Construction Quality Control Meeting (hereinafter referred to as the "Meeting") will be held for quality assurance and smooth implementation of the Works at each stage of the Works. The member of the Meeting will be composed by the Recipient (or executing agency), the Consultant, the Contractor and JICA. The functions of the Meeting are as followings:

- a) Sharing information on the objective, concept and conditions of design from the Contractor, before start of construction.
- b) Discussing the issues affecting the Works such as modification of the design, test, inspection, safety control and the Client's obligation, during construction.

(2) Ex-post Monitoring and Evaluation Stage

1) After the project completion, JICA will continue to keep in close contact with the Recipient in order to monitor that the outputs of the Project is used and maintained properly to attain its expected outcomes.

2) In principle, JICA will conduct ex-post evaluation of the Project after three years from the completion. It is required for the Recipient to furnish any necessary information as JICA may reasonably request.

(3) Others

1) Environmental and Social Considerations

The Recipient shall carefully consider environmental and social impacts by the Project and must comply with the environmental regulations of the Recipient and JICA Guidelines for Environmental and Social Considerations (April, 2010).

2) Major undertakings to be taken by the Government of the Recipient

For the smooth and proper implementation of the Project, the Recipient is required to undertake necessary measures including land acquisition, and bear an advising commission of the A/P and payment commissions paid to the Bank as agreed with the GOJ and/or JICA. The Government of the Recipient shall ensure that customs duties, internal taxes and other fiscal levies which may be imposed in the Recipient with respect to the purchase of the Products and/or the Services be exempted or be borne by its designated authority without using the Grant and its accrued interest, since the grant fund comes from the Japanese taxpayers.

3) Proper Use

The Recipient is required to maintain and use properly and effectively the products and/or services under the Project (including the facilities constructed and the equipment purchased), to assign staff necessary for this operation and maintenance and to bear all the expenses other than those covered by the Japanese Grant.

4) Export and Re-export

The products purchased under the Japanese Grant should not be exported or re-exported from the Recipient.

PROCEDURES OF JAPANESE GRANT

		r	r					
Stage	Procedures	Remarks	Recipient Government	Japanese Government	JICA	Consultants	Contractors	Agent Bank
Official Request	Request for grants through diplomatic channel	Request shall be submitted before appraisal stage.	x	x				
1 Preparation	(1) Preparatory Survey Preparation of outline design and cost estimate		x		x	x		
	(2)Preparatory Survey Explanation of draft outline design, including cost estimate, undertakings, etc.		х		x	х		
2. Appraisal (3)Agreement on conditions for implementation (G/A) which will be signed bef		Conditions will be explained with the draft notes (E/N) and Grant Agreement (G/A) which will be signed before approval by Japanese government.	x	x (E/N)	x (G/A)			
			x		2			
	(5) Exchange of Notes (E/N)		x	x				
	(6) Signing of Grant Agreement (G/A)		x		x			
	(7) Banking Arrangement (B/A)	Need to be informed to JICA	x					х
	(8) Contracting with consultant and issuance of Authorization to Pay (A/P)	Concurrence by JICA is required	x			x		x
	(9) Detail design (D/D)		x			x		
3 Implementation	(10) Preparation of bidding documents	Concurrence by JICA is required	x			x		
	(11) Bidding	Concurrence by JICA is required	x			x	x	
	(12) Contracting with contractor/supplier and issuance of A/P	Concurrence by JICA is required	x				x	x
	(13) Construction works/procurement	Concurrence by JICA is required for major modification of design and amendment of contracts.	x			х	x	
	(14) Completion certificate		x			x	x	
4. Ex-post nonitoring &	(15) Ex-post monitoring	To be implemented generally after 1, 3, 10 years of completion, subject to change	x		x			
evaluation	(16) Ex-post evaluation	To be implemented basically after 3 years of completion	x		х			

notes:


I. Project Monitoring Report and Report for Project Completion shall be submitted to JICA as agreed in the G/A.

2. Concurrence by JICA is required for allocation of grant for remaining amount and/or contingencies as agreed in the G/A.

Ł Da

Attachment 2

Financial Flow of Japanese Grant (A/P Type)



Project Monitoring Report on Project Name Grant Agreement No. XXXXXXX 20XX, Month

Organizational Information

Signer of the G/A	Person in Charge	(Designation)
(Recipient)	Contacts	Address:
		Phone/FAX: Email:
Executing Agency	Person in Charge Contacts	(Designation) Address: Phone/FAX: Email:
Line Ministry	Person in Charge Contacts	(Designation) Address: Phone/FAX: Email:

General Information:

Project Title	
E/N	Signed date: Duration:
G/A	Signed date: Duration:
Source of Finance	Government of Japan: Not exceeding JPY <u>mil.</u> Government of ():

1: Project Description

1-1 Project Objective

1-2 Project Rationale

- Higher-level objectives to which the project contributes (national/regional/sectoral policies and strategies)
- Situation of the target groups to which the project addresses

1-3 Indicators for measurement of "Effectiveness"

Indicators	Original (Yr)	Target (Yr)
Qualitative indicators to measur	e the attainment of project object	

2: Details of the Project

2-1 Location

Components	Original (proposed in the outline design)	Actual
1.		

2-2 Scope of the work

Components	Original* (proposed in the outline design)	Actual*
1		

Reasons for modification of scope (if any). (PMR)

Dra_

2-3 Implementation Schedule

	Or	iginal	
Items	(proposed in the outline design)	(at the time of signing the Grant Agreement)	Actual

Reasons for any changes of the schedule, and their effects on the project (if any)

2-4 Obligations by the Recipient

- **2-4-1 Progress of Specific Obligations** See Attachment 2.
- **2-4-2 Activities** See Attachment 3.
- 2-4-3 Report on RD See Attachment 11.

2-5 Project Cost

2-5-1 Cost borne by the Grant(Confidential until the Bidding)

Components			Cos (Millior		
	Original (proposed in the outline design)	Actual (in case of any modification)	Original ^{1),2)} (proposed in the outline design)	Actual	
1.					
	Total				

Note: 1) Date of estimation: 2) Exchange rate: 1 US Dollar = Yen

2-5-2 Cost borne by the Recipient

Components		Cost	
Original (proposed in the outline design)	Actual (in case of any modification)	Original ^{1),2)} (proposed in the outline design)	Actual
1.			

3 49

&-

Note: 1) Date of estimation:

2) Exchange rate: 1 US Dollar =

Reasons for the remarkable gaps between the original and actual cost, and the countermeasures (if any)

(PMR)

2-6 Executing Agency

- Organization's role, financial position, capacity, cost recovery etc,
- Organization Chart including the unit in charge of the implementation and number of employees.

Original (at the time of outline design)

name:

role:

financial situation:

institutional and organizational arrangement (organogram): human resources (number and ability of staff):

Actual (PMR)

2-7 Environmental and Social Impacts

- The results of environmental monitoring based on Attachment 5 (in accordance with Schedule 4 of the Grant Agreement).

- The results of social monitoring based on in Attachment 5 (in accordance with Schedule 4 of the Grant Agreement).

- Disclosed information related to results of environmental and social monitoring to local stakeholders (whenever applicable).

3: Operation and Maintenance (O&M)

3-1 Physical Arrangement

- Plan for O&M (number and skills of the staff in the responsible division or section, availability of manuals and guidelines, availability of spareparts, etc.)

Original (at the time of outline design)

Actual (PMR)

3-2 Budgetary Arrangement

- Required O&M cost and actual budget allocation for O&M

Original (at the time of outline design)

4: Potential Risks and Mitigation Measures

- Potential risks which may affect the project implementation, attainment of objectives, sustainability
- Mitigation measures corresponding to the potential risks

Assessment of Potential Risks (at the time of outline design)

Potential Risks	Assessment
1. (Description of Risk)	Probability: High/Moderate/Low
· · · /	Impact: High/Moderate/Low
	Analysis of Probability and Impact:
	Mitigation Measures:
	Action required during the implementation stage:
	Contingency Plan (if applicable):
2. (Description of Risk)	Probability: High/Moderate/Low
	Impact: High/Moderate/Low
	Analysis of Probability and Impact:
	Mitigation Measures:
	Action required during the implementation stage:
	Contingency Plan (if applicable):
3. (Description of Risk)	Probability: High/Moderate/Low
	Impact: High/Moderate/Low
	Analysis of Probability and Impact:
	Mitigation Measures:
	Action required during the implementation stage:

7

8

	Contingency Plan (if applicable):
Actual Situation and Countermeasure	S
(PMR)	

5: Evaluation and Monitoring Plan (after the work completion)

5-1 Overall evaluation

Please describe your overall evaluation on the project.

5-2 Lessons Learnt and Recommendations

Please raise any lessons learned from the project experience, which might be valuable for the future assistance or similar type of projects, as well as any recommendations, which might be beneficial for better realization of the project effect, impact and assurance of sustainability.

5-3 Monitoring Plan of the Indicators for Post-Evaluation

Please describe monitoring methods, section(s)/department(s) in charge of monitoring, frequency, the term to monitor the indicators stipulated in 1-3.

Attachment

- 1. Project Location Map
- 2. Specific obligations of the Recipient which will not be funded with the Grant
- 3. Monthly Report submitted by the Consultant

Appendix - Photocopy of Contractor's Progress Report (if any)

- Consultant Member List
- Contractor's Main Staff List
- 4. Check list for the Contract (including Record of Amendment of the Contract/Agreement and Schedule of Payment)
- 5. Environmental Monitoring Form / Social Monitoring Form
- 6. Monitoring sheet on price of specified materials (Quarterly)
- 7. Report on Proportion of Procurement (Recipient Country, Japan and Third Countries) (PMR (final)only)
- 8. Pictures (by JPEG style by CD-R) (PMR (final)only)
- 9. Equipment List (PMR (final)only)
- 10. Drawing (PMR (final)only)
- 11. Report on RD (After project)

Monitoring sheet on price of specified materials

1. Initial Conditions (Confirmed)

		Initial Walnuma	Initial Unit	Initial total	1% of Contract		Condition of payment
	Items of Specified Materials		Price (¥)	Price	Price	1711	Price (Increased)
		V	В	C=A×B	D		F=C+D
	Item 1	O t	•	•	•	•	•
5	Item 2	000	•	•	•		
က	Item 3						
4	Item 4						
ъ	Item 5						

- 2. Monitoring of the Unit Price of Specified Materials(1) Method of Monitoring : •••
- (2) Result of the Monitoring Survey on Unit Price for each specified materials

Items of Snevified Materials	Ist	2nd	3rd	4th	5th	6th
TATES AT SPACETAGE MIGRATIN	month, 2015	•month, 2015	• month, 2015	ALL STATION OF		
Item 1						
Item 2						
Item 3						
Item 4						
Item 5						

(3) Summary of Discussion with Contractor (if necessary)

9

Attachment 7

Report on Proportion of Procurement (Recipient Country, Japan and Third Countries) (Actual Expenditure by Construction and Equipment each)

	Domestic Procurement	Foreign Procurement	Foreign Procurement	Total
	(Recipient Country)	(Japan)	(Third Countries)	D
	A	B	C	
Construction Cost	(A/D%)	(B/D%)	(C/D%)	
Direct Construction Cost	(WD%)	(B/D%)	(C/D%)	
others	(%D/V)	(B/D%)	(C/D%)	
Equipment Cost	(A/D%)	(B/D%)	(C/D%)	
Design and Supervision Cost	(A/D%)	(B/D%)	(C/D%)	
Total	(A/D%)	(B/D%)	(C/D%)	

R

ŧ

Annex 8

Major Undertakings to be taken by the Government of Uganda

Specific obligations of the Government of Uganda which will not be funded with the Grant

(1) Before the Tender

	(1) Before the render				
NO	Items	Deadline	In charge	Estimated Cost	Ref.
1	To open bank account (B/A)	within 1 month after the signing of the G/A	MOH		
	To issue A/P to a bank in Japan (the Agent Bank) for the payment to the consultant	within 1 month after the signing of the contract	MOH		
	To provide alternative space for the services carried out in the facilities to be demolished during construction period.	before start of demolition	RRHs		
	 To secure and clear land for ; 1) the construction areas 2) the area for temporary office, temporary store and working shade, stock yard for materials and concrete mixing space 	before notice of the bidding document	RRHs		
5	To obtain the planning, zoning, building permit	before notice of the bidding document	MOH and RRHs		
	 To clear, level and reclaim the following sites at the construction areas including their foundations 1) the existing buildings 2) all existing trees 3) the existing sewerage pipes, manholes, water supply pipes, underground electric cables 4) any other obstacles 	before notice of the bidding document	RRHs		
7	To submit Project Monitoring Report (with the result of Detail Design)	before preparation of bidding documents	МОН		

(B/A: Banking Arrangement, A/P: Authorization to pay, N/A: Not Applicable)

1 ha


(2) During the Project Implementation


	(2) During the Project implementation			I- - - -	
NO	Items	Deadline	In charge	Estimated Cost	Ref.
	To issue A/P to a bank in Japan (the Agent Bank) for the payment to the Supplier(s)	within 1 month after the signing of the contract(s)	MOH		
	To bear the following commissions to a bank in Japan for the banking services based upon the B/A		MOH		
	1) Advising commission of A/P	within 1 month after the signing of the contract(s)	МОН		
	2) Payment commission for A/P	every payment	MOH		
	To ensure prompt customs clearance and to assist the Supplier(s) with internal transportation in recipient country	during the Project	МОН		
	To accord Japanese nationals and/or physical persons of third countries whose services may be required in connection with the supply of the products and the services such facilities as may be necessary for their entry into the country of the Recipient and stay therein for the performance of their work	during the Project	МОН		
	To ensure that customs duties, internal taxes and other fiscal levies which may be imposed in the country of the Recipient with respect to the purchase of the products and/or the services shall be in accordance with the agreement to be concluded between the Government of Uganda and the Government of Japan. MOH shall take necessary neasures according to the agreement.	during the Project	МОН		
1	To bear all the expenses, other than those covered by he Grant, necessary for the implementation of the Project	during the Project	MOH and RRHs		
7	To submit Project Monitoring Report	every month	MOH		
	1) To submit Project Monitoring Report (final)	within one month after signing of Certificate of Completion for the works under the contract(s)	МОН		
8	To submit a report concerning completion of the Project	within six months after completion of the Project	МОН		
l	To conduct necessary pre-installation works in the case of installing new equipment in the existing buildings	before installation of equipment	RRHs		
Ì	To provide facilities for distribution of electricity, water supply and drainage and other incidental acilities necessary for the implementation of the Project outside the sites		RRHs		
	 Electricity The distributing line and appropriate power supply to the buildings 	before start of the construction	RRHs		
	2) Water Supply The water supply line and the appropriate water supply to the buildings	6 months before completion of the construction	RRHs		
10.0	Drainage The public sewer line and the appropriate drainage system to the buildings	6 months before completion of the construction	RRHs		
-	 Furniture and Equipment general furniture and office equipment spare parts and consumables 	1 month before completion of the construction			
	o take necessary measure for safe construction and raffic control	during the construction	RRHs		

(3) After the Project

NO	Items	Deadline	In charge	Estimated Cost	Ref.
	 To maintain and use properly and effectively the facilities constructed and equipment provided under the Grant Aid 1) Allocation of maintenance cost 2) Operation and maintenance system 3) Routine check/Periodic inspection 	After completion of the construction	MOH and RRHs		

Ł. 8







GULU RRH


2017.02


1:1,500


YOKOGAVA ARCHITECTS & ENGINEERS, INC.

















64

FSe

Annex 10-1

THE PROJECT FOR IMPROVEMENT OF REGIONAL REFERRAL HOSPITALS IN NORTHERN UGANDA IN THE REPUBLIC OF UGANDA

PREPARATORY SURVEY 2 FOR FACILITY BETWEEN GULU REGIONAL REFERRAL HOSPITAL AND CONSULTANT

Memorandum

The memorandum records the results of the preparatory survey for facility planning held between Gulu Regional Referral Hospital ("Gulu RRH") and the Preparatory Survey Team ("the Team") for the Project for Improvement of Regional Referral Hospital in Northern Uganda, in the Republic of Uganda.

The preparatory survey for facilities was held at Gulu RRH, from 20^{th} to 22^{nd} February, 2017. As the result of the discussion, both sides have confirmed the main items described below:

1. Final Requested Facility

Both sides confirmed the final requested facility is the Maternity / Theatre / Casualty Block including:

- 1) 75 to 81 patient beds,
- 2) six delivery rooms,
- 3) a kangaroo care room,
- 4) a NICU in the Maternity Ward,
- 5) a surgical operation room,
- 6) an orthopaedic operation room,
- 7) an obstetrics/gynaecology operation room, and
- 8) a recovery space, in the Operation Theatre, ~
- 9) a resuscitation room for 12 to 15 beds,
- 10) a triage room/clinic, and
- 11) a minor operation theatre connected to the Operation Theatre, in the Casualty Unit, and
- 12) an ICU for four to six beds,
- 13) CSSD adjacent to the Operation Theatre and also accessible from other departments, and
- 14) a connection corridor between the new building and the imagery building.

The Team will explain the final facility plan in the Explanation of Draft Final Report (DOD) to Ugandan side.

- 2. Minutes of the meeting held on 21^{st} and 22^{nd} February 2017
 - 1) The Hospital approved to use part of its land in front of the Mental Unit for temporary office, temporary store and working shade, stock yard for materials and concrete mixing space.
 - 2) The Hospital approved to use the existing gate at Mental Health Unit for construction activities.
 - 3) The Contractor will deploy two guards to control construction traffic, in order to ensure safety of the patients, their attendants, and Hospital staff.
 - 4) The Contractor will construct a temporary fence at the construction site and temporary storage area to ensure safety of the patients, their attendants, and Hospital staff.
 - 5) The Hospital will demolish the existing old X-Ray building including its foundation before the

NGA

E

commencement of construction works

- 6) The Hospital will demolish the following buildings including their foundations before commencement of construction works in case they are to be obstacles for the works:
 - a. existing main operation theatre,
 - b. existing toilet facility for medical ward, and
 - c. existing store next to toilet facility for medical ward.
- 7) The Hospital will demolish the following before commencement of construction works:
 - a. all existing trees at the construction area,
 - b. existing sewerage pipes, manholes, water supply pipes, underground electric cables, and
 - c. any other obstacles.
- 8) The Hospital approved to stop using the open burning pit near the incinerator.
- 9) The Hospital requested the Project to install rain water harvesting tanks.
- 10) The Hospital agreed to connect the sewer line from the new building to the existing public sewer line.
- 11) A new electric pole, transformer and protection circuit will be installed by the Japanese side.
- 12) The Hospital requested the Project to install solar water heater for the new building.
- 13) The Ministry of Health requested the Project to install a solar electric system (power back up) for the new building.
- 14) The Hospital requested the Project to install manifold system for oxygen supply.
- 15) The Hospital approved to connect the existing water supply line to the new building.

HOSPITAL DIRECTOR * 22 FEB 2017 REF. HOSPITAL O. BOX 160 GULU(U)

Dr. Onyachi Nathan Hospital Director Gulu Regional Referral Hospital The Republic of Uganda Gulu, 22nd February, 2017

each

Mr. Keiichi IDE Project Manager, Preparatory Survey Team The Consortium of the Yokogawa Architects & Engineers, Inc. and INTEM Consulting, Inc.

Witness

Innucl.

Samuel Tusubira Engineer Ministry of Health

Ł

THE PROJECT FOR IMPROVEMENT OF REGIONAL REFERRAL HOSPITALS IN NORTHERN UGANDA IN THE REPUBLIC OF UGANDA

PREPARATORY SURVEY 2 FOR EOUIPMENT BETWEEN GULU REGIONAL REFERRAL HOSPITAL AND CONSULTANT

Memorandum

The memorandum records the results of the preparatory survey for equipment planning held between Gulu Regional Referral Hospital ("Gulu RRH") and the Preparatory Survey Team. ("the Team") for the Project for Improvement of Regional Referral Hospital in Northern Uganda, in the Republic of Uganda. The preparatory survey for equipment was held at Gulu RRH, from 17th to 22nd February, 2017. As the result of the discussion, both sides have confirmed the main items described bellow.

Final Requested Equipment List 1.

Both side confirmed the final requested equipment list with priority from Gulu RRH. The Team will analyze the final requested equipment list in Japan and plan the component of equipment for the project. The Team will explain the final equipment plan in the Explanation of Draft Final Report to Ugandan side. The final requested equipment list is referred to the Attachment 1.

2. Undertaking by Ugandan Side

Both side confirmed the following would be undertaking of the Government of Uganda;

(1) Dental: To remove existing dental unit, and provide appropriate water supply and drainage.

(2) Laboratory: To remove existing biosafety cabinet.

(3) Imagery: To prepare rooms for imagery machines including X-ray protection wall, X-ray protection window and AC, and provide appropriate power supply in case of the project includes imagery equipment.

(4) Physiotherapy: To remove existing equipment adapting and renovate existing room if necessary.

(5) Orthopedic workshop: To remove existing equipment, supply appropriate power supply and renovate existing building if necessary.

(6) Pharmacy: To remove existing wooden shelves at the candidate inpatient pharmacy.

(7) Other department which use existing rooms: To prepare appropriate space and power supply.

3. Attendance List

The preparatory survey was held with attendance of staff from Gulu RRH as in Attachment 2.

Gulu, 23 February, 2017









Dr. Onyachi Nathan Hospital Director Gulu Regional Referral Hospital The Republic of Uganda

小江 for

Mr. Keiichi IDE Project Manager, Preparatory Survey Team The Consortium of the Yokogawa Architects & Engineers, Inc. and INTEM Consulting, Inc.

Witness

Hlatacha

Eng. Kataha Edward Principal Electrical Engineer Ministry of Health

\$ b

equested No.	No. in Dep	Equipment Name	Q'ty	Priority
	OUT PAT	IENT		
1	1	BP machines	8	1
2		weighing scales adult	5	2
3		weighing scales children	1	3
4		Height meters	5	6
5		Autoclaves	1	5
6		Pulse oximeters	8	7
7	-	Thermometers	8	8
	EMERGEN	Examination lights		4
9		BP machine	6	10
10		Stethoscopes	6	11
10		Weighing scales infant	1	12
12		Thermometers	6	13
13		Pulse Oximeters	6	9
14		Oxygen Cylinder Set	5	5
15		Suction machines	3	3
16	8	Mobile X-ray	1	1
17		Ultrasound machine	1	2
18		X-ray film viewer boxes	1	17
19		Examination light	2	18
20		Infusions Pumps	4	19
21		Patient monitor	3	6
22		Suction machine manual	3	4
23		Operation light (mobile)	1	16
24		Syringe pump	2	20
25		Emergency bed	4	15
26 27		Operation Table Ambu bag	1	14
27		Cervical spine fixed color	2	21
20		Patient trolley	2	8
30		Wheel chair	3	7
00		NG THEATRE		
31		Anesthetic machines	1	1
32		Operating lights	3	2
33		Patient monitor	4	4
34	4	Oxygen Cylinder Set	2	7
35		Suction machines	3	5
36		Weighing scales set	1	15
37		Operating Beds	3	3
38		Electro surgery machines	3	8
39		Defibrillators	1	9
40		Refrigerator	1	10
41		Operating light (mobile)	2	14
42		Patient trolley	5	11
43 44		Syringe pump	2	6 12
44 45		Instrument trolley Mayo table	3	12
45		Instrument set for OT	1	12
		DEPARTMENT	'	10
47		General mounted X-ray machine	1	1
48	2	Mobile X-ray	i	5
49		CR machines	1	2
50		Mammography X-ray machine	1	9
51		CT Scan	1	4
52	6	Ultrasound machine	1	6
53		ECG	1	7
54		Eco – cardiogram ultrasound machine	1	3
55		X-ray viewing boxes	10	10
56		Fluoroscopy X-ray machine	1	8
	ICU			
57		ICU bed	4-6	2
58		Vital monitors	2	3
59		Suction machines		5
60	14	Oxygen cylinder set		4
		69	B 1 Htn 1	be

Attachment1. Final Requested Equipment List

69

N

ti j

Requested No.	No.in Dep	Equipment Name	Q'ty	Priority
61		Autoclaves	1	6
62		Infusion pumps	1	7
63		Ventilator	1	1
64		Ambu bag	1	8
65		Nebulizer	1	9
	NICU	1 C		
66		Infants incubators	5	1
67 68		Photo therapy units Patient monitor		5
69		Infusion Pumps	1	8
70		Pulse oximeters	2	3
70		Infant warmer	1	4
72		Examination lamp	2	6
73		Oxygen cylinder set	1	2
74		BP machine for infant	2	9
	OB&GY			
75		Examination Bed for Gyn	3	12
76		Examination beds	4	13
77		Ultrasound machines	2	9
78		Doppler Fetoscope	3	11
79		Autoclaves	1	2
80		Cryo-therapy machine		3
81		Oxygen cylinder set	4	5
82 83	8	Suction machines Delivery bed	6	6
83		Fetal monitor	1	14
85		Vacuum extractor (manual)	2	4
86		Patient monitor	2	8
87		Infant warmer	2	10
88		Patient trolley	4	7
89		Corpo scope	1	15
90		Speculum set	20	17
91		Curettage Instrument set	5	16
92		LEEP machine	1	18
00	PAEDIAT		10	4
93 94		Oxygen cylinder set weighing scales infants	10	1
94		Infusion pumps	4	8
96		Patient Monitor	1	2
97		Stethoscopes	5	7
98		Examination lights	3	9
99		Infant BP machines	3	6
100		Nebulizer	2	3
101		Gluco meter	1	5
		LAUNDRY		
102		Big Autoclaves	1	1
103		Laundry machine	1	2
104		Ironing machine	1	3
105 106		Dryers Working table for CSSD	$\frac{1}{1}$	4
106		Laundry trolley	1	5
107		Storage cabinet	1	6
100	ENT	Locolago cabillor		1
109		Tonsillectomy set	2	1
110		Adenoidectomy set	2	2
111		Laryngoscopy set	1	3
112		Caldwell luc set	1	4
113	5	Tracheostomy set	1	13
114		Suction machines	2	7
115		Operating Microscopes	1	9
116		Middle ear set	1	10
117		Mastoid drill	1	11
118		Esophagoscopy	1	6
119		Bronchoscopy for children	1	5
120 121		Tympanometer Acoustic Emission Testing machine	1	8
121	1 13		- · ·	
		70 ANY	3	R

70

Requested No.	No.in Dep	Equipment Name	Q'ty	Priority
122		Walsham forceps	1	14
122	LABORAT			14
123		Binocular microscopes	2	5
124		Centrifuge	3	11
125		Fridges	2	1
126		Glucometer	3	10
127		Water bath	1	11
128		Incubators		12
129		Safety cabinets		13
130		shakers	3	14
131		Pipette	5	9
132		Heamometers	1	15
133		Water distiller		8
134		Chemistry analyzer	1	16
135		Autoclaves		6
136		Hot air oven		7
130		Deep freezer		2
137		Blood bank refrigerator		
138		ELISA system with PCR	1	4
139		Electrolyte analyzer		3
140		Electrolyte analyzer Eye wash station		5
141		GeneXpert		17
142	DENTAL	Generation		18
143		Dental unit		
143		Dental Unit Dental X-ray	3	1
144				2
		Dental instrument sets	1	3
146		Light Curing machines	1	4
147		Intra oral cameras	1	7
148		Pulp Tester		5
149 150		Dental laboratory equipment		8
150		Autoclaves	1	6
151	PHARMA			
151		Drugs shelves	1	4
152		Drugs fridges	4	1
153		Dispensing tray	6	5
<u>154</u> 155		Drug trolley	5	3
100	SURGICA	Cupboard	2	2
150				-
<u>156</u> 157		Oxygen cylinder set	3	2
157		Vital monitors	2	4
158		Autoclaves		1
		Examination lights	2	6
160	5	BP machines	2	9
161		Suction machine	2	3
162		Patient trolley	2	11
163		Drum set	2	5
<u>164</u> 165		Diagnosis set	1	7
		Weighing scale	1	10
166		Pulse oximeter	1	8
107				10
167		Endoscopy unit		12
168		BP machine	4	7
169		Weighing scales	3	11
170		Pulse oximeter	2	9
171		Portable ultrasound machine		3
172		Oxygen cylinder set	6	1
173		Nebulizer	4	2
174		Diagnosis set	2	8
175		Infusion pumps	1	10
176		Patient trolley	4	6
177		Wheel chair	4	14
178		Fibroscan	1	4
179		Medicine trolley	4	5
	1 4 4	Suction machine	0	15
180 181		Ventilator	2	13

71

A MA G

S

GULU RRH

No.	No.in Dep	Equipment Name	Q'ty	Priority
110.	AMBULAN	NCE		
182		Ambulance	1	
		EDIC CLINICAL		
183		Plaster shear Manual	2	2
184		Plaster shear (electrical)	1	1
185		Plaster opener	2	4
186		Plaster bender	2	6
187		Splint set		3
<u>188</u> 189		Operating Fracture bed C~Arm		5
190		Film viewer		8
190	PHYSIOT			
		erapy Section		
191		UV Lamp	2	13(1A, 1B)
192	2	Therapeutic ultrasound	2	2(1A, 1B)
193		Short wave diathermy	1	3
194		TENS	1	11
195		EMS	1	15
196		Infra-Red Radiation lamps	2	4
197		Electrical massager	2	12
100	and the second se	ive therapy Traction machines (Cervical and lumber)	1 1	1 1
<u>198</u> 199		Traction machines (Cervical and lumber) Therapeutic Massage beds		1 5
199		therapy section	1 3	1 3
200		Tread mill	2	6
200		Pulley systems	1	16
202		Suspension bed	1	17
203		Muscle strengthening weights	2	18
204	14	Therapeutic mats	3	19
205		Postural mirror	1	20
206		Hand exercise equipment	1	24
207		Shoulder wheels	1	25
208		stationary bikes, – adult	2	8
209		Stationary bikes – children		9
210 211		Quadriceps bench with accessories like weights Bo baths balls different sizes		10
211		Stares adult	1	26
212		Stares children	1	27
214		Parallel bars children	1	28
215		Abdominal strengthening equipment	1	21
		rapy facilities		
216		Warm parks equipment	2	22
217		Cold parks equipment	2	23
218		Parallel bars adult	1	29
219		Electrical Oscillatory manipulative bed	1	14
000		dic workshop	1	
220		Jig saw		5
221 222		Heavy duty oven Rotor machine		9
223		Dust Suction machine	2	3
223		Pressure compressor	1	4
225		Vertical band saw	1	12
226		Pipe bender	1	2
227	8	Hand drilling machine	2	6
228	9	Vacuum machine	1	7
229	10	Automatic parallels bars	1	10
230		Mirror	1	11
231		Polishing machine	1	8
		LWORKSHOP		F
232		Carpentry tool box	1	5
233		Plumbing tool box	2	4
234		Oxygen gas analyzer Digital Multi-meter	2	6
		Welding generator	1	2
226		Heavy Duty Engraving machine		8
236	/ 6			

72

GULU RRH

Requested	No. in	Equipment News	01	Defense
No.	Dep	Equipment Name	Q'ty	Priority
239	8	Working mats for electronics	1	10
240	9	Electronics tool box	2	1
241	10	Mechanical tool box	2	3
	OPTHALM	NOLOGY		
242	1	Operating Microscopes	1	1
243	2	Slit lamp	1	4
244	3	Visual field analyzer (automated)	1	2
245	4	Hand held portable slit lamp	1	7
246		Direct ophthalmoscope	3	8
247		Parkins tomometer	1	11
248		Cataract set	8	6
249	8	Extra owler (lid surgery) set	5	10
250		Suction machines	1	3
251	10	Magnifying head loop	4	9
252		Autorefracto meter	1	5
	MENTAL	HEALTH CARE		
253	1	BP machines	3	1
254	2	Weighing scale	4	3
255	3	Autoclaves	1	2
256	4	Drum set	2	7
257	5	Oxygen cylinder	2	11
258	6	ECT (Electroconvulsive Therapy)	1	6
259	7	Pulse oximeter	1	4
260	8	Patient trolley	2	5
261		Examination bed	3	10
262	10	Infusion pump	1	8
263	11	Wheel chair	2	9

Anox 10-2

THE PROJECT FOR IMPROVEMENT OF REGIONAL REFERRAL HOSPITALS IN NORTHERN UGANDA IN THE REPUBLIC OF UGANDA

2.

PREPARATORY SURVEY 2 FOR FACILITY BETWEEN LIRA REGIONAL REFERRAL HOSPITAL AND CONSULTANT

Memorandum

The memorandum records the results of the preparatory survey for facility planning held between Lira Regional Referral Hospital ("Lira RRH") and the Preparatory Survey Team ("the Team") for the Project for Improvement of Regional Referral Hospital in Northern Uganda, in the Republic of Uganda.

The preparatory survey for facilities was held at Lira RRH, from $23^{rd} - 27^{th}$ February, 2017. As the result of the discussion, both sides have confirmed the main items described below:

1. Final Requested Facility

Both sides confirmed the final requested facility is the OPD, MCH, Casualty Block and Delivery unit complex including:

OPD Complex

- 1) Pharmacy/Dispensary
- 2) Satelite Laboratory
- 3) 2No. pediatric consultation rooms
- 4) Male consultation room
- 5) Female consultation room
- 6) Diabetic consultation room
- 7) Dental clinic
- 8) ENT clinic
- 9) MARPS room
- 10) Treatment room
- 11) Orthopedic consultation room
- 12) Physiotherapy/Occupational consultation room
- 13) 2No. specialized clinics.
- 14) MCH consultation rooms (office for in charge, palpation room with 6No. couches, treatment room, EID point treatment room, immunization room, family planning, cervical cancer screening)
- 15) X-Ray room, ultra sound room
- 16) Casualty (resuscitation room with 10 12 beds and minor operation theatre.)
- 17) Waiting space for MCH attached to OPD complex

Adolescent consultation room should be considered by Lira Hospital using existing nearby buildings.

Delivery Complex

- 1) 6No. delivery suites
- 2) New born baby room (NICU)
- 3) Sterilisation room
- 4) Nurse station
- 5) Changing/wash rooms for nurses

The Team will explain the final facility plan in the Explanation of Draft Final Report (DOD) to Ugandan side.

1 Mar

- 2. Minutes of the meeting held on $23^{rd} 27^{th}$ February 2017
 - 1) The Hospital approved to use part of its land in front of the staff quarters for temporary office, temporary store and working shade, stock yard for materials and concrete mixing space.
 - 2) The Hospital approved to establish a temporary gate for construction work at the west part of the Hospital land.
 - 3) The Hospital will demolish the OPD building including its foundations before commencement of construction works.
 - 4) The Hospital requested the Project to construct a new access road to the staff quarters along the temporary fence.
 - 5) The Hospital will demolish the following before commencement of construction works:
 - a. All existing trees at the construction area,
 - b. Existing sewerage pipes, manholes, water supply pipes, underground electric cables.
 - c. Any other obstacles.
 - 6) The Contractor will deploy guards to control construction traffic, ensure safety of the patients, their attendants and Hospital staff.
 - 7) The Hospital requested the Project to install rain water harvesting tanks.
 - 8) The Hospital approved to connect the sewer line from the new building to the existing sewer line.
 - 9) A new electric pole, transformer and protection circuit will be installed by the Japanese side.
 - 10) The Ministry of Health requested the Project to install a solar electric system (the power back up) for the new building.
 - 11) The Hospital approved to connect the existing public water supply line to the new building.
 - 12) The Hospital requested the Project to install Local Area Network (LAN) to the new building.

Lira 27th February, 2017

Dr. Elima James Hospital Director Lira Regional Referral Hospital The Republic of Uganda

wich

Mr. Keiichi IDE Project Manager, Preparatory Survey Team The Consortium of the Yokogawa Architects & Engineers, Inc. and INTEM Consulting, Inc.

Witness

nd

Samuel Tusubira Engineer Ministry of Health

THE PROJECT FOR IMPROVEMENT OF REGIONAL REFERRAL HOSPITALS IN NORTHERN UGANDA IN THE REPUBLIC OF UGANDA

PREPARATORY SURVEY 2 FOR EQUIPMENT BETWEEN LIRA REGIONAL REFERRAL HOSPITAL AND CONSULTANT

Memorandum

The memorandum records the results of the preparatory survey for equipment planning held between Lira Regional Referral Hospital ("Lira RRH") and the Preparatory Survey Team. ("the Team") for the Project for Improvement of Regional Referral Hospital in Northern Uganda, in the Republic of Uganda.

The preparatory survey for equipment was held at Lira RRH, from 23rd to 27nd February, 2017. As the result of the discussion, both sides have confirmed the main items described bellow.

1. Final Requested Equipment List

Both side confirmed the final requested equipment list with priority from Lira RRH. The Team will analyze the final requested equipment list in Japan and plan the component of equipment for the project. The Team will explain the final equipment plan in the Explanation of Draft Final Report to Ugandan side. The final requested equipment list is referred to the Attachment 1.

2. Undertaking by Ugandan Side

Both side confirmed the following would be undertaking of the Government of Uganda;

(1) Laundry: To renovate existing room for new machines if necessary, and supply appropriate power supply and water supply.

(2) Sterilization unit in Main Operation Theatre: To prepare appropriate power supply, water supply and drainage.

(3) Imagery: To construct wired LAN network from new building to existing buildings where Client PCs

for CR system will be installed in case of CR system is included in the project.

(4) Pathology: To renovate existing room for new machines if necessary, and supply appropriate power supply.

(5) Other department which use existing rooms: To prepare appropriate space and power supply.

3. Attendance List

The preparatory survey was held with attendance of staff from Lira RRH as in Attachment 2.

Lira 27 March, 2017

76

+执(

Dr. Elima James Hospital Director Lira Regional Referral Hospital The Republic of Uganda

stich

Mr. Keiichi IDE Project Manager, Preparatory Survey Team The Consortium of the Yokogawa Architects & Engineers, Inc. and INTEM Consulting, Inc.

Witness

thata ang

Eng. Kataha Edward Principal Electrical Engineer Ministry of Health

LIRA RRH

Requested No.	No.in Dep.	Equipment Name	Final Q'ty	Final Priority
	Out Pati	ent		14
1		BP machine	each clinical room	1
2	2	Examination Couch	each clinical room	3
2 3	3	Wheel Chair	2	4
4		Weighing Scale	each clinical room	5
5		Glucometer	each clinical room	6
6		Diagnostic set	each clinical room	2
7	7	Patient trolley	1	7
	OB/GYN			
8 9		Delivery Bed	4	1
9 10		Operation Light mobile Oxygen cylinder set	2 2	2 7
11		suction Machine	2	11
12		Examination Couch	2	5
13		weighing and height Scale	3	8
14		BP machine	4	4
15		Cesarean operating instrument set	4	3
16		Intubation set	2	13
17		Resuscitation kit	1	14
18		Autoclave	1	9
19		Patient monitor	2	12
20		Examination bed for OBGY	2	6
21		Drum set	3	10
	Imaging			
22		СТ	1	4
23		Fluoroscopy machine	1	5
24		ultra sound scanner	1	3
25		Fixed X-ray with card reader		1
26 27		Automatic film processor		2
27		Read character Mobile X-ray machine		7 6
20		CR system		8
	Ambulan		I	0
30		Ambulance	1 1	1
	Emgency		· · · · ·	
31	1	Ventilator	2	4
32		Anesthesia machine	1	5
33	3	Autoclave	1	7
34		patient Trolley	4	10
35		suction machine	2	8
36		Operation table	1	2
37		patient Monitor	2	6
38		Operating instrument set	2	
39	and the second sec	Emergency bed	4	1
40		Diagnostic set	2	12
41 42		Drum Set B.P. machine	5	9
42		Operation light mobile	2	13 3
		ion in Thetre and OBGY	I I	3
44		Autoclave for sterilization	2	1
45		Boiler	1	2
46		Storage cabinet	2	3
47		Steel cabinet	2	4
	Laundry			
48		laundry machine	1	1
49		Heavy duty electric iron	1	2
50		Dryer	1	3
	Dental			
51		Dental Chair	4	1
52		Dental X–Ray	1	2
53	the second size and second sec	Autoclave		3
54	4	Light cure machine		5 A
		78-	FATC Fime	SK

78

LIRA RRH

	Dep.	Equipment Name	Final Q'ty	Final Priority
55	5	Electronic scaler	1	6
56		Dry-heat sterilizer	1	9
57		Dental forceps (all sets)	5	4
58		Sterilizing box set	1	10
59		Drums set	1	11
60		Pulp tester	1	7
61		Intra oral cameras	1	8
	Peadiatri			· · · · · · · · · · · · · · · · · · ·
62		Oxygen cylinder set	10	1
63 64		Radiant warmer (for NICU)	2	2
65		Incubator (for NICU)	2	3
66		weighing scale patient Monitor	2	4
67		Pulse oximeter	2	5
68		Pediatric BP machine	8	6
69		Diagnostic set	3	7
		n Theatre	3	8
70		Anesthesia machine	1 1	1 1
71		Patient Monitor	1	
72	and the second se	and the second birds of the second	3	6
73		Oxygen cylinder set	4	5
74		Operation table	2	5
75		Pulse oximeter	4	3
76		BP machine Digital	4	4
77		Glucometer	1	8
78		Sterilizing drum Large	10	13
79		Sterilizing drum Medium	5	14
80		Sterilizing drum Small	5	15
81		Operation light portable	2	9
82		Autoclave	1	10
83		patient Trolley	2	11
84		Laparotomy set	1	12
85		Instrument trolley	2	16
	Sugery W		-	
86		Autoclave	2	2
87		suction machine	2	11
88		BP machine	2	12
89	4	examination couch	3	8
90	5	Drip stand	10	7
91	6	Patient trolley	2	3
92	7	Wheel Chair	2	4
93	8	Drum set	3	6
94		Oxygen cylinder set	2	1
95		Dressing trolley	2	9
96		Drug trolley	2	10
97		Resuscitation kit	2	5
98		Glucometer	2	13
99		Dressing instrument set	2	14
100		Pulse oximeter	2	15
101		Weighing scale	2	16
	NT			
102		ENT examination microscope	1	9
103		ENT examination set complete	1	1
104		Mastidectomy set	1	8
105		Tonsillectomy set	1	7
106		Bronchoscopy set	1	2
107		ENT examination unit	1	6
108		Tympanometer	1	3
109		BP machine	1	5
110		Audiometer	1	4
	aborator			
111	1	Hematology analyzer	1	3

LIRA RRH

Requested No.	No. in Dep.	Equipment Name	Final Q'ty	Final Priority
112		Biochemistry machine	1	4
113		Refrigerator Blood Bank	1	1
114		Microscope	2	5
115		Centrifuge	2	10
116		Incubator	1	7
117	7	Autoclave	1	6
118	8	Voltex mixer	1	11
119		weighing scale	1	9
120		Water desterilizer	1	8
121		Refrigerator	1	2
]	Internal M	Medicine		
122	1	Oxygen cylinder set	2	2
123		Nebulizer	1	4
124	3	suction Machine	1	6
125	4	patient Trolley	2	5
126		syringe pump	2	8
127		infusion pump	2	7
128		Drip stand	10	3
129		Ultrasound machine portable	1	1
	ICU			-l
130		syringe pump	2	1 1
	Pharmac	y		
131	1	Refrigerator (large)	1 7	1
132		Refrigerator (small)	4	2
133		Table drug	1	5
134		Drug trolley	3	6
135		Steel cabinet	2	8
136		Water destilizer	2	4
137		Autoclave	1	3
138		Drug cupboard		7
		quipment		/
139		Portable oscilloscope	1	7
140		Thermometer/hygrometer		9
141		Analyzer Tachometer		8
142		Insulation resistance tester		1
143	5	Earth mega tester		1
144	6	Cramp meter		3
145		Welding machine mobile		
146		Electrical tool box		5
147		Pipe bender		6
		ic workshop	1	4
148		Broad Belt Sander		
149		Vacuumed machine		4
149				3
150		Welding hot jet	1	5
151		Welding MIRROR		2
		Router machine	1	1
153	Orthoped			1 .
		Oscillation Plaster cutter	1	1
154		Plaster share	1	2
155		Plaster bender	1	6
156		Plaster opener		8
157		Operating flucture bed	1	9
158		Bone fracture instrument set	1	7
159		Thomas splint	20	3
160		Browne splint	20	4
161		Electrical bone drill	1	10
162		Wheel Chair	5	5
	Opthalom			
163		Operating microscope	1	2
164		Cataract operation instrument set	6	3
165		Autoclave	1	4
166	4	Slit lamp with Tonometer	1	6
	Y	AD T	De HALL R	

Requested No.	No.in Dep.	Equipment Name	Final Q'ty	Final Priority
167		Area thetie machine	1	5
168		Instrument trolley	2	11
169		Kerato meter	1	7
170		Trial lens set	1	10
171		weighing scale	2	9
172		BP machine	2	8
173	the second se	Phaco emulsification machine	1	1
	Physioth	erapy		
174		Ultrasound therapy	1	2
175		Short wave therapy	1	1
176		Infra-Red Radiation lamps	1	3
177		Exercise mat	2	5
178		Stationary bike	2	6
179		Balance ball	2	7
180		Traction bed	1	4
181		Electrical massager	1	8
182		Refrigerator	1	9
	Mental H			
183	1	Drug trolley	2	4
184		Drug cupboard	1	3
185		Examination coach	2	2
186	4	Chito forceps	2	6
187		Drums set	2	5
188	6	Autoclave	1	1
189	7	Drip stand	4	7
	Pathology	/		
190	1	Mortuary refrigerator	1	2
191		Mortuary trolley with cover	2	1
192	3	Mortuary Instrument set	1	4
193	4	Holding patient trolley	2	3
	NMCH			
194	1	Examination couch	9	1
195	2	Examination lump	2	7
196	3	Speculum set	1	8
197	4	Uterine sonde set	2	13
198	5	Uterine Elevator instrument set	5	14
199	6	Drum set	4	5
200	7	Cupboard	2	9
201		Deep freezer	1	4
202		Refractor for vaccines	1	3
203		Vaccine carrier	10	6
204		Weighing scale neonatal	3	10
205		BP machine	7	2
206	13	Weighing and height scale adult	3	10
207		Patient trolley	1	11
208		Wheel chair		12

Kti

AHC

Filme

F/

Annex 10-3

THE PROJECT FOR IMPROVEMENT OF REGIONAL REFERRAL HOSPITALS IN NORTHERN UGANDA IN THE REPUBLIC OF UGANDA

PREPARATORY SURVEY 2 FOR FACILITY BETWEEN ARUA REGIONAL REFERRAL HOSPITAL AND CONSULTANT

Memorandum

The memorandum records the results of the preparatory survey for facility planning held between Arua Regional Referral Hospital ("Arua RRH") and the Preparatory Survey Team ("the Team") for the Project for Improvement of Regional Referral Hospital in Northern Uganda, in the Republic of Uganda.

The preparatory survey for facilities was held at Arua RRH, from 13th to 17th February, 2017. As the result of the discussion, both sides have confirmed the main items described below:

1. Final Requested Facility

Both sides confirmed the final requested facility is the OPD and Casualty unit including:

- 1) four General OPD consultation rooms,
- 2) one Medical Outpatient consultation room,
- 3) two Paediatric rooms,
- 4) one Surgical Outpatient consultation room,
- 5) one ENT and Ophthalmology consultation room,
- 6) one Gynaecology consultation room,
- 7) one Dental room, one Adolescence room,
- 8) two HCT rooms,
- 9) one MARPs room in the OPD, and
- 10) a resuscitation room with four beds
- 11) a minor operation theatre in the Casualty Unit.

The Team will explain the final facility plan in the Explanation of Draft Final Report (DOD) to Uganda side.

- 2. Minutes of the meeting held on 17th February 2017
 - 1) The Hospital approved to use part of its land for the Construction of the new OPD.
 - 2) The Hospital approved to demolish part of the perimeter wall to create access for construction materials. The Contractor will repair the demolished part of the wall after completion of the construction.
 - 3) The Hospital approved to use part of its land for site accommodation.
 - 4) The Hospital approved to use part of its land for dumping soil excavated from the construction site.
 - 5) The Hospital requested the Project to install rain water harvesting tanks.
 - 6) The Hospital approved to connect the sewer linc from the new building to the existing sewer line,
 - 7) The Hospital agreed that there is no need to create a new ambulance entrance. They will use the existing of the entrance at the main gate.
 - 8) A new electric pole, transformer and protection circuit will be installed by the Japanese side.
 - 9) The Hospital requested the Project to install solar water heater for the new building.

(durrel.

- 10) The Hospital requested the Project to install a solar electric system (the power back up) for the new building.
- 11) The Hospital requested the Project to install manifold system for oxygen supply.
- 12) The Hospital approved to connect the existing water supply line to the new building.
- 13) The Hospital requested the project to install Local Area Network(LAN) to the new building.

omello preita Dr. Odu Bernard Hospital Director Arua Regional Referral Hospital The Republic of Uganda HOSPITAL FOI Witness ARUAREGIO 0.9

Arua, 17 February, 2017

直角広村町

Project Manager, Preparatory Survey Team The Consortium of the Yokogawa Architects & Engineers, Inc. and INTEM Consulting, Inc.

annul!

Samuel Tusubira Engineer Ministry of Health

P de

THE PROJECT FOR IMPROVEMENT OF REGIONAL REFERRAL HOSPITALS IN NORTHERN UGANDA IN THE REPUBLIC OF UGANDA

PREPARATORY SURVEY 2 FOR EQUIPMENT BETWEEN ARUA REGIONAL REFERRAL HOSPITAL AND CONSULTANT

Memorandum

The memorandum records the results of the preparatory survey for equipment planning held between Arua Regional Referral Hospital ("Arua RRH") and the Preparatory Survey Team. ("the Team") for the Project for Improvement of Regional Referral Hospital in Northern Uganda, in the Republic of Uganda. The preparatory survey for equipment was held at Arua RRH, from 13th to 15th February, 2017. As the result of the discussion, both sides have confirmed the main items described bellow.

1. Final Requested Equipment List

Both side confirmed the final requested equipment list with priority from Arua RRH. The Team will analyze the final requested equipment list in Japan and plan the component of equipment for the project. The Team will explain the final equipment plan in the Explanation of Draft Final Report to Ugandan side. The final requested equipment list is referred to the Attachment 1.

2. Undertaking by Ugandan Side

Both side confirmed the following would be undertaking of the Government of Uganda;

(1) Dental: To remove existing dental unit in case the dental department is remained in existing building, and provide appropriate water supply and drainage.

(2) CSSD: To renovate the existing sterilization room in the main operation theatre, and provide appropriate power and water supply for autoclaves.

(3) Laundry: To renovate the existing laundry and provide appropriate power and water supply.

(4) Imagery: To construct wired LAN network from new OPD building to existing buildings where Client PCs for CR system will be installed.

3. Attendance List

The preparatory survey was held with attendance of staff from Arua RRH as in Attachment 2.

Arua, 16 February, 2017

М

Dr. Bernard Odu Hospital Director Arua Regional Referral Hospital The Republic of Uganda

Lu each .

Mr. Keiichi IDE Project Manager, Preparatory Survey Team The Consortium of the Yokogawa Architects & Engineers, Inc. and INTEM Consulting, Inc.

Witness

, 17. Eng. Sitra Muleo l Senior Engineer Ministry of Health

1	And Emergency		Priority
	- Berry		
	Vital sign monitor [ECG,Pulse rate Bp,SP2]	2	1
2	Endoscopy machine	1	19
3	Emergency Respirators	1	2
4	Defibrilators	1	16
5	Oxygen cylinder set	2	8
		2	3
		2	4
		4	5
		4	9
		1	6
		1	7
		1	17
		2	18
		5	10
		1	11
		1	12
17	Dressing instrument set	1	14
18		1	15
		1	13
		1	20
Ambulanc	e		11
1	Ambulance	1	1
Dental			
1		3	1
	Dental imaging/x-ray machine and processors	1	2
		1	4
		2	6
		2	7
		1	8
		1	15
		1	9
		n: 1	10
		1	11
	Polishing and trimming machines	1	12
		1	13
		1	14
		2	5
		1	3
-	Large portable mirrow	1	2
	Sewing machines	1	3
	Standing frames,adults and children	1 2	6
		2	4
		1	1
		1	5
			0
		2	1
			2
		1	3
-		1	4
		1	5
		1	6
7	TENS Machine	2	7
		1	8
	Stational bicycle	2	9
	Exercise mat	3	10
11	Wheel chair	5	11
12	Bobbath ball	5	12
	6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 Ambulance 1 2 3 4 5 6 7 8 9 10 11 12 3 4 5 6 7 8 9 10 11 2 3 4 5 6 7 8 9 10 11 2 3 4 5 6 7 8 9 10	6 Suction machine Electrical 7 Nebulizer 8 Patient transfer trolleys 9 Wheel chairs 10 Operating table 11 Operating light mobile 12 Drug trolley 13 Medicine Cupboaards 14 Emergency Bed 15 Examination light 16 Dressing part 17 Dressing instrument set 18 Diagnosis set 19 Minor surgery instrument set, 20 Autoclave Ambulance Dental 1 Zontal week 2 Dental Unit 2 Dental linging/x=ray machine and processors 3 Vacuum Autoclaves 4 LED cure lights 5 Ultrasonic Scalers 6 Ultrasonic Scalers 7 Dental implant surgical motors 8 Handpieces oiler 9 Apex Locators 10 Casting machines 11 Polishing and trimming machines 12 Hydroflasks, Heat	6 Suction machine Electrical 2 7 Nebulizer 2 8 Patient transfer trolleys 4 9 Wheel chairs 4 10 Operating light mobile 1 11 Operating light mobile 1 12 Drug trolley 1 13 Medicine Cupboaards 2 14 Emergency Bed 5 15 Examination light 1 16 Dressing cart 1 17 Dressing instrument set 1 20 Autoclave 1 1 Ambulance 1 1 Dental imaging/x-ray machine and processors 1 1 Dental imaging/x-ray machine and processors 1 1 Ambulance 1 1 1 Dental imaging/x-ray machine and processors 1 1 Ambulance 1 1 1 Mapieces oiler 1 1 1 Darasonic Scalers 2

Attachment1. Final Requested Equipment List

Not

1 the

Requested No.	No.in Dep	Equipment Name	Final Q'ty	final Priority	
	Imargery				
56	1	Computerised Tommographic Scan (CT-Scan)	1	1	
57	2	Berium Enamel set	1	6	
58	3	Mamography Machine	1	4	
59	4	Ultra sound scan [Cardiac Abdominal,obstetric] with doppler	1	2	
60	5	Digital Radiography system DRS	1	3	
61	7	Hysterosalpingogram set	1 1	7	
62	8	Electro encephalogram	1 i	8	
	Pharmacy		-		
63	1	Refrigerators Large	1	1	
64	2	Drug Cupboards Metallics	3	2	
65	3	Autoclave	1	4	
66	4	Dry oven		5	
67	5	Water Distillers	2	3	
68	6	Water bath	1	6	
	7		2	7	
69		Weighing scale digital	Z		
70	Orthopead				
70		Gypsum cutter		1	
71	2	Manual Plaster cutter	2	14	
72	3	Pulse oximetre	1	2	
73	4	Oxygen cylinder and mask	1	3	
74	5	Dressing set	1	4	
75	6	Dressing trolly	1	5	
76	7	Patient trasnfer trolly	2	6	
77	8	Drug trolly	1	7	
78	9	Drum set	1	8	
79	10	Autoclve	1	9	
80	11	Drip stand	10	10	
81	12	Examination couch	3	11	
82	13	Plaster table	1	12	
83	14	Wheel chiar	2	13	
84	15	Bed craddle	5	15	
85	16	Working frame	2	16	
86	17	Orthopedic braun frame for traction	5	17	
87	18	C-arm	1	18	
88	19	Instrument set for orhopedic surgery	1	19	
	Laborator	y .		29	
89	1	Heamatology analyser [5 parameetre]	1	7	
90	2	Clinical Chemistry Analysers	1	8	
91	3	Refrigerator	. 2	1	
92	- 4	Electrical centrifuge [8-12 Buckets]	2	2	
93	5	Orbital shaker	1	9	
94	6	Blood mixer [Roller]	1	10	
95	7	Laboratory incubator	1	11	
96	8	Electrical weighing Scale [Laboratory]	1	4	
97	9	Weighing Scale for blood transfusion	1	3 -	
98	10	Autoclave Elecrtical	1	5	
99	11	Microscope Olympus	2	6	
100	12	Hemoglobino meter	1	12	
101	1	Autoclave Set	1 1	1	
102	2	Whashing Machines	1 - 1	1	
102	3	Dryer	1	2	
103	4	Irooning roller	1	3	
	4		1	5	
105		Flat ironning machine			
106	6	Laundry trolley	4	4	
	MARTENITY				
4		and Delivery room , HDU	-		
107		Vital sign monitor [ECG,Pulse rate ,SP2,Foetal doppler]	3	4	
108	2	Blood preesure machine wll mounted or on stands	2	9	
109	3	Delivery Beds	8	1	
110	4	Infant Warmer	3	3	
111	5	Patient Transfer trolleys	2	2	

FI

No.		Dep Equipment Name		inal final A'ty Priorit
112		6 Oxygen cylinder set		
113		7 Wheel chairs 8 Exampleations agent light		5 11
114		Examminations spot lights		2 12 2 10
116		Instrument set for delivery		10
117		Suction machine Electrical		10 5
118		1 Fetal dopper		2 8
119		2 Ambubag set fro neonatal 3 Vacuum extractor		2 7
		3 Vacuum extractor		2 <u>6</u> 1 13
120	_	Vital sign monitor [ECG,Pulse rate Bp,SP2]		
121		Drug Trolleys		2 4
122				3 7
123	4	Drossing Sets [Forceps Kidney diches artarias at 1		
124	5		2	
125	6		3	
126	7	inst unerit set for examination	2	
127	8	Blood pressure	1	-
100		atre	6	1
128	1	Vital sign monitors		
129	2	Electrical suction machine	2	
130	3	Anasthetic machine	2	
131	4	Ceiling mounted mobile type	1	3
132	5	Oxygen cylinder set	2	
133	6	Autoclave	2	5
134	7 Nec	Instrument Set for theatre	1	- 7 6
135	1	Incubators		
136	2	Oxygen cylinder set	4	3
137	3	Baby courches	4	6
138	4	Vital sign monitor [ECG,Pulse rate Bp,SP2]	5	2
139	5	Suction machine electrical	2	1
140	6	Infant Radiant Warmers	1	7
141	7	Continuous postive air way pressure (ODAD)	2	5
	Interna	inculaine and a second s	1	4
142	1	Oxygen cylinder set		
143	2	Suction machine Electrical	5	1
144	3	Autoclave small	2	2
145	4	Wheel chair	1	3
146	5	Vital sign monitor [ECG,Pulse rate Bp,SP2]	3	4
147	6	Patient trolley	2	5
148	7	HBAIc machine	2	6
149	8	Drug infusion pumps		8
150	9	Nebulisers	4	9(2A, 2B)
151	10	Diagnostic set general	1	10
152	11	Refrigerators medicine	2	7
153	12	Dressing instrument set	2	12(1A, 1B)
154	13	Drug trolley	2	13
155 156	14	Instument drums set	2	14
	15	Patient examination coach	2	15
57 58	16	Glucometer	2	18
59	17	Pulsoximeter	2	19
	18 ain On	Weighing scale erating Theatre	2	20
60	1	Operating table		1 41
61	2	Vital sime meniter [500 p. (3	1 (2A, 1B)
62	3	Vital sign monitor [ECG,Pulse rate Bp,SP2]	3	4(2A, 1B)
63	4	Operating lamp mobile type	3	2(2A, 1B)
64	5	Anaesthetic Machine	2	6
65	6	Electrical Dermatome(Skin Graft Set)	2	5(1A, 1B)
66	7	Oxygen cylinder set	2	9
67	8	Pneumatic tournique	2	8
38	9	Patient Transfer trolley	2	7
59	10	Suction machine electrical Electrical surgical unit	3	3
	0	Lieurical surgical unit		

88

列

ARUA RRH

Requested No.	No.in Dep	Equipment Name	Final Q'ty	final Priority	
170	11	Instrument set for OP theatre	1	11	
170	General				
171	1	Vital sign monitor [ECG,Pulse rate Bp,SP2]	2	5	
172	2	Oxygen cylinder set	2	7	
172	3	Suction machine	2	6	
173	4	Medicine/treatment trolleys	4	3	
175	5	Patient screens	6	8	
176	6	Patient transfer trolleys	3	2	
177	7	Instrument set	1	1	
178	8	Dressing trolley	4	4	
170	Pediatric				
179	1	Oxygen cylinder set	4	1	
180	2	Nebulisers	3	2	
181	3	Vital sign monitor [ECG,Pulse rate Bp,SP2]	2	3	
182	4	infant and child Blood pressure machine	6	4	
183	5	Pulse oximetre	10	6	
184	6	Patient screens	4	12	
185	7	reservoir bags with face masks	4	13	
186	8	Examination couch	5	7	
187	9	Stethoscope paediatrics	3	8	
188	10	Files trolley	3	11	
189	11	Diagnosis set	3	10	
190	12	Thermometre digital	12	9	
190	13	Examination light	5	5	
191		Equipment Workshop			
192	1	Electronic / Electrical tools	2	7	
193	2	Refrigeration tools	1	1	
193	3	Oxygen analyser	2	5	
195	4	Mechanical tools	2	6	
196	5	Welding Genarator Portable	1	4	
197	6	Plumbling Tool	1	9	
198	7	Drilling machine	1	3	
199	8	Carpently tool set	1	10	
200	9	Multimeter	2	8	
201	10	Clamp meter	2	2	

A.F

Minutes of Discussions on the Preparatory Survey for the Project for Improvement of Regional Referral Hospitals in Northern Uganda, in the Republic of Uganda (Explanation on Draft Preparatory Survey Report)

With reference to the minutes of discussions signed between the Ministry of Health (hereinafter referred to as "MOH") and the Japan International Cooperation Agency (hereinafter referred to as "JICA") on 30th November, 2016 and 2nd March, 2017 and in response to the request from the Government of the Republic of Uganda (hereinafter referred to as "Uganda") dated 8th August, 2011, JICA dispatched the Preparatory Survey Team (hereinafter referred to as "the Team") for the explanation of Draft Preparatory Survey Report (hereinafter referred to as "the Draft Report") for the Project for Improvement of Regional Referral Hospitals in Northern Uganda (hereinafter referred to as "the Project"), headed by Mr. Shintaro Takano, Deputy Director, Grant Aid Project Management Division 2, Financial Cooperation Implementation Department, JICA from 20th to 26th August, 2017.

As a result of the discussions, both sides agreed on the main items described in the attached sheets.

Mr. Shintaro Takano Leader, Preparatory Survey Team Japan International Cooperation Agency Japan

Kampala, 25th August, 2017 my

Dr. Diana Atwine Permanent Secretary Ministry of Health Republic of Uganda

Witness

I

Ms. Maris Wanyera For: Permanent Secretary/Secretary to the Treasury Ministry of Finance, Planning and Economic Development Republic of Uganda

ATTACHEMENT

1. Responsible authority for the Project

Both sides confirmed the authority responsible for the Project is MOH which will be the executing agency for the Project (hereinafter referred to as "the Executing Agency"). The Executing Agency shall coordinate with all the relevant authorities to ensure smooth implementation of the Project and ensure that the undertakings for the Project shall be taken care by relevant authorities properly and on time.

2. Contents of the Draft Report

After the explanation of the contents of the Draft Report by the Team, the Ugandan side agreed to its contents. The facility components which are included in the Project are shown in Annex 1 and the equipment list in each RRH is shown in Annex 2.

3. Cost estimate

Both sides confirmed that the cost estimate be borne by the Japanese side including the contingency described in Annex 3 is provisional and will be examined further by the Government of Japan for its approval. The contingency would cover the additional cost against natural disaster, unexpected natural conditions, etc.

- 4. Confidentiality of the cost estimate and technical specifications Both sides confirmed that the cost estimate and technical specifications in the Draft Report and Annex 3 should never be duplicated or disclosed to any third parties except for Ministry of Finance, Planning and Economic Development until all the contracts under the Project are concluded.
- 5. Timeline for the project implementation The Team explained to the Ugandan side that the expected timeline for the Project implementation is as attached in Annex 4.

6. Expected outcomes and indicators

Both sides agreed that key indicators for expected outcomes are as follows. The Ugandan side will be responsible for the achievement of agreed key indicators targeted in the Ugandan financial year 2022/23 and shall monitor the progress based on those indicators.

2 Jun

[Quantitative indicators]

Gulu RRH

Indicator	Baseline (Avarage number of 2011/12-2015/16)	Target (2022/23)
Number of Deliveries (case/year)	4,768	5,500
Number of Operations (case/year)	1,543	1,800
Number of Emergency Patients (person/year)	5,445	6,300
Number of Patients of Intensive Care Unit (ICU) (person/year)	0	200

Lira RRH

Indicator	Baseline (Avarage number of 2011/12-2015/16)	Target (2022/23)
Number of Outpatients *1 (person/year)	121,345	144,000
Number of Patients of Maternal and Child Health Unit (person/year)	36,164	42,900
Number of Emergency Patients (person/year)	4,800	5,400
Number of Deliveries (case/year)	5,804	6,800

*1: This number consists of the patients of Genaral Outpatients clinic, Orthopedics clinic, Ophthalmology clinic, Ear, Nose and Throat (ENT) clinic, and Dental clinic

Arua RRH

Indicator	Baseline (Avarage number of 2011/12-2015/16)	Target (2022/23)
Number of Outpatients *2 (person/year)	96,208	116,000
Number of Emergency Patients (person/year)	5,315	6,400

*2: This number consists of the patients of Genaral Outpatients clinic, Medical Outpatients clinic, Diabetes clinic, Nutrition clinic, Palliative care clinic, Paediatrics clinic, Surgery clinic, Orthopedics clinic, ENT clinic, Ophthalmology clinic, Dental clinic, and Obstetrics and Gynaecology clinic.

3 /

[Qualitative indicators]

- Through strengthening the functions which are necessary for RRH as the top referral hospital in each sub-region, the access to and quality of health care services in Northern Uganda will be improved.
- Through construction of facilities and procurement of equipment, the inconvinience such as the congestion and the dirty environment will be improved, thereby crediblity and satisfaction of the hospitals for the people in Nothern Uganda including refugees will be boosted.
- 7. Technical assistance ("Soft Component" of the Project)
 - Considering the sustainable operation and maintenance of the products and services granted through the Project, following technical assistance is planned under the Project. The Ugandan side confirmed to deploy necessary number of counterparts who are appropriate and competent in terms of its purpose of the technical assistance as described in the Draft Report.
- 8. Undertakings of the Project
- 8-1. Both sides confirmed the undertakings of the Project as described in Annex 5 which will be used as an attachment of G/A.
- 8-2. Both sides confirmed that customs duties, internal taxes and other fiscal levies which may be imposed in Uganda will be budgeted for by MOH without using the Grant, according to the agreement between the Government of Uganda and the Government of Japan.
- 8-3. The Ugandan side assured to take the necessary measures and coordination including allocation of the necessary budget which are preconditions of implementation of the Project as descriced in Annex 3 and 5. It is further agreed that the costs are indicative, i.e. at Outline Design level. More accurate costs will be calculated at the Detailed Design stage.
- 8-4. Both sides confirmed the following would be the undertakings of the Government of Uganda to be completed according to the schedule in Annex 4;
 - 1) demolition of existing facilities and land leveling to construct new facilities
 - 2) providing alternative space for the services carried out in the demolished facilities during the construction period.
- 8-5.The Ugandan side agreed to allocate budget (operational and maintenance costs), human resources with skills (health service providers and any other personnel), and goods (spare parts and consumables) necessary for the proper and sustainable operation and maintenance of the facilities and the equipment under the Project based on the Draft Report. Specifically, the Ugandan side agreed to take necessary

4 May

Annex 1 Outline of the Facilities

Annex 2 Equipment List

Annex 3 Project Cost Estimation (confidential)

Annex 4 Project Implementation Schedule (tentative)

Annex 5 Major Undertakings to be taken by the Government of Uganda

Annex 6 Project Monitoring Report (template)

6 Kun

Annex 1: Outline of the facilities

Gulu RRH

Project Component		Description
Theatre /Casualty / Maternity Ward	GF 1,208.89 m ²	ICU: ICU, Anteroom, Staff room, Office, etc. Common: Power house, Generator house, Fire pump room, etc.
	1F 1,260.11 m ²	Maternity bed rooms (81 beds), NICU (2), Delivery room (5) Labour room, Nurse station, Sluice/sterilisation room, Patient toilet, etc.
Total	2,469.00m ²	

Lira RRH

Project Component			Description
OPD/Casualty	GF	980.30 m ²	OPD: Reception, Laboratory, Pharmacy, Imagery, etc. Casualty: Ambulance, Triage/clinic, Resuscitation room, Minor operation room, Sluice/sterilisation room, Office, Staff room, etc. MCH: Clinic, Office, etc. Common: Patient toilet, etc.
Block	lF	1,022.56 m ²	OPD: Clinics (paediatric, obstetrics, general OPD, specialised OPD), Dental clinic, etc. MCH: Clinic, Vaccine store, etc. Common: Patient toilet, etc.
Subtotal	-	2,002.86 m ²	
Power House	GF	17.31 m ²	Power house, Generator house
Delivery Suite	GF	278.98m ²	Delivery room (6), NICU, Sluice/sterilisation room, Staff room, etc.
Generator House	GF	13.78 m ²	Generator house
Total		2,312.93 m ²	

Arua RRH

Project Component			Description
OPD/Casualty Block	GF	865.97 m ²	Common: Patient toilet, etc.
	1F	897.20 m ²	OPD: Clinic (paediatric, gynaecology, general OPD, specialised OPD), Dental clinic, Patient toilet, etc.
Subtotal		1,763.17 m ²	
Power House	GF	17.31 m ²	Power house, Generator house
Total	Ì	1,780.48m ²	<u> </u>

7

Min

Annex	2: Equipmo	ent List					
					Gulu RRH	Lira <u>RRH</u>	Arua RRH
No.	Requested No.	Equipment Name	Q'ty	Unit	Total Q'ty	Total Q'ty	Total Q'ty
1	Req-3	Adenoidectomy and Tonsillectomy instrument set	2	Sets	1	1	
2	Req-4	Ambu bag set for adult	2	Sets	2		
3	Req-5	Ambu bag set for neonatal	3	Sets			3
4	Req-6	Ambubag set	1	Set			1
5	Req-7	Ambulance	3	Sets	1	1	1
6	Req-8	Anaesthesia Machine	7	Sets	2	2	3
7	Req-10	Audiometer (Screening)	1	Set		1	
8	Req-11	Autoclave (desktop)	20	Sets	7	7	6
9	Req-12	Autoclave (Laboratory type)	1	Set			1
10	Req-13	Autoclave (stand alone)	3	Sets	1	1	1
11	Req-16	Baby bed	2	Sets			2
12	Req-20	Binocular microscope	2	Sets	1		1
13	Req-21	Biochemistry analyzer	3	Sets	1	1	1
14	Req-26	BP machine	13	Sets	8	5	
15	Req-29	BP machine for adult	10	Sets	1	4	5
16	Req-30	BP machine for neonatal	6	Sets	3	1	2
17	Req~31	Broad belt sander	1	Set		1	
18	Req-32	Esophagoscope	3	Sets	1	1	1
19	Req-35	Caesarean instrument set	3	Sets		2	1
20	Req-36	Caldwel luc instrument set	1	Set	1		
21	Req-40	Centrifuge	3	Sets	1	1	1
22	Req-43	Clamp meter	2	Sets		I	1
23	Req-47	Colpo scope	1	Set	1		
24	Req-48	СРАР	1	Set			1
25	Req-49	CR system	2	Sets		1	1
26	Req-51	Cryosurgery machine	1	Set	1		
27	Reg-54	Curettage instrument set	3	Sets	3		
28	Req~55	Deep freezer	2	Sets	1	1	
29	Req-57	Delivery bed	16	Sets	6	4	6
30	Req-59	Delivery instrument set	5	Sets			5
31	Req~61	Dental chair	3	Sets	1	1	1
32	Req-63	Dental instrument set	5	Sets	1	3	1
33	Req-66	Dental X-ray machine	3	Sets	1	1	1
34	Req-66-2	Dental X-ray CR	3	Sets	1	1	1
35	Req-67	Diagnosis set	12	Sets	2	7	3

Annex 2: Equipment List

8 Jun

36	Req-69	Dressing cart	6	Sets		2	4
7	Req-70	Dressing instrument set	7	Sets		2	5
38	Req-71	Drilling machine	1	Set			1
39	Req-72	Drip stand	10	Sets		8	2
40	Req-73	Drug trolley	12	Sets	4	2	6
41	Req−74	Drum set	8	Sets	1	6	1
42	Req-79	Dryer	3	Sets	1	1	1
43	Req-80	Dust vacuume machine	1	Set	1		
44	Req-81	Earth mege tester	1	Set		1	
45	Req-82	ECG	1	Set	1		
46	Req-85	Electrical balance	2	Sets			2
47	Req-86	Electrical dermatome	1	Set			1
48	Req-89	Electrical tool set	2	Sets	1	1	
49	Req-90	Electro surgical unit	3	Sets	2		1
50	Req-93	Eletrolyte analyzer	1	Set	1		
51	Req-95	Emergency bed	36	Sets	12	12	12
52	Req-97	EMS	2	Sets	1		1
53	Req-98	Engraving machine	1	Set	1		
54	Req-99	ENT chair	1 -	Set		1	
55	Req-100	ENT examination instrument set	I	Set		1	
56	Req-101	ENT oprating microscope	2	Sets	1	1	
57	Req-103	Examination bed	29	Sets	2	23	4
58	Reg-104	Examination light	17	Sets	9	1	7
59	Reg-106	Examination table for OB&GY	6	Sets	2	2	2
60	Req-107	Exercise mat	3	Sets	1	1	1
61	Req-110	Fetal doppler	6	Sets	2	1	3
62	Req-116	Fluoroscopy X-ray machine	2	Sets		1	1
63	Req-118	General X-ray machine	2	Sets		1	1
64	Req~120	Glucometer	17	Sets	3	13	1
65	Req-122	Hand drilling machine	1	Set	1		
66	Req-126	HBA1c analyzer	1	Set			1
67	Req-127	Height meter	r'ı	Set	1	-	
68	Req-128	Hematology analyzer	3	Sets	1	1	1
69	Req-130	Hot air oven	1	Set	1		
70	Req-133	Hysterosalpingogram set	1	Set			1
71	Reg-134	ICU bed	5	Sets	5		
72	Req-135	Incubator	2	Sets	1	1	
73	Req-136	Infant incubator	10	Sets	4	2	4
74	Req-137	Infant warmer	4	Sets	1	1	2
75	Req-138	Infra red machine	3	Sets	1	1	1

TA

9 mm

76	Req-139	Infusion pump	5	Sets	3		2
77	Req-141	Instrument trolley	3	Sets	3		
78	Reg-142	Insulation resistance tester	1	Set		1	
79	Req-145	Jig saw	1	Set	1		
80	Reg-149	Laryngoscope	1	Set	1		
81	Reg-154	Light cure machine	3	Sets	1	1	1
82	Req-158	Mayo table	3	Sets	3		
83	 Req-160	Medicine cupboard	5	Sets		1	4
84	Req-161	Micropipette set	2	Sets	2		
85	Req-162	Middle ear instrument set	1	Set	1		
86	Req-163	Minor surgery instrument set	3	Sets		2	1
87	Reg-164	Mobile X-ray machine	2	Sets	1	1	
	Reg-166	Multimeter	2	Sets	1		1
	Reg-168	Nebulizer	10	Sets	5	1	4
	Reg-171	Operating light (ceiling mont)	4	Sets	4		
	Req-172	Operating light (mobile)	9	Sets		5	4
	Req-173	Operating table	7	Sets	. 3	2	2
-	Req-174	Operating table with traction	3	Sets	1	1	1
94	Req-178	Orthopedic instrument set	1	Set			1
95	Req-179	Oscilloscope (portable)	1	Set		1	
96	Reg-182	Oxygen cylinder set	47	Sets	16	14	17
97	Req-185	Parallel bar for adult	1	Set	1		1
98	Req-186	Patient Bed	86	Sets	86		
99	Req-189	Patient monitor	27	Sets	10	5	12
100	Reg-194	Patient trolley	32.	Sets	12	8	12
101	Req-197	Photo therapy unit	1	Set	1		
102	Reg-198	Pipe bender	1	Set	1		1
103	Reg-199	Plaster bender	2	Sets	1	1	1
104	Req-200	Plaster cutter (electrical)	3	Sets	1	1	1
105	Req-201	Plaster cutter (manual)	2	Sets	1	1	1
106	Reg-202	Plaster opener	2	Sets	1	1	1
107	Req-206	Pneumatic tournique	1	Set			1
108	Reg-208	Polishing machine	1	Set	1		-
109	Req-209	Posture mirror	1	Set	1		-
110	Req-211	Pulp tester	3	Sets	1	1	1
111	Req-212	Pulse oximeter	29	Sets	15	7	7
112	Reg-217	Refrigerator (battery type)	2	Sets		1	1
113	Req-218	Refrigerator for bloodbank	3	Sets	1	1	1
114	Req-220	Refrigerator for drug (large)	4	Sets		2	2
115	Req-221	Refrigerator for drug (medium)	7	Sets	4	1	2
1		10	L.	m	6.1		
			7 My		py		

Int Part of a statution Part of a statution Part of a statution Part of a statution 117 Req-228 Resurchation est 11 Satt 11 Image: Part of a statution 11 Satt 11 Image: Part of a statution 11 Satt 11 11 11 118 Req-228 Shoter wave dictormy 33 Satt 11 12 11 12 Req-230 Shulder wheel 11 13 33 11 11 11 12 11	116	Req-222	Refrigerator for drug (small)	3	0-1-	<u> </u>		1.
Int No. No. No. No. No. 118 Req-228 Rotor machine 2 Sets 1 No. 119 Req-231 Shaker 1 Sets 1 No. 120 Req-232 Shot wave disthermy 3 Sets 1 1 121 Req-236 Speculum act 1 Set 1 1 122 Req-248 Stationary bike for adult 4 Sets 2 1 1 123 Req-244 Stationary bike for adult 4 Sets 2 1 1 122 Req-244 Stationary bike for adult 4 Sets 2 1 1 123 Req-244 Stationary bike for adult 4 Sets 1 1 1 124 Req-244 Stationary bike for adult 2 Sets 1 1 1 123 Req-250-2 Station machine (Gult CSBD 1 Stat 1					Sets	I	1	1
In Req-231 Staker In Sets In In 120 Req-232 Short wave diatharmy 3 Sets 1 1 1 121 Req-233 Shulder wheel 1 Set 1 1 1 122 Req-234 Sprulder wheel 1 Set 10 1 3 123 Req-244 Stationary bik for adult 4 Sets 2 1 1 124 Req-244 Stationary bik for adult 4 Sets 2 1 1 125 Req-245 Stationary bik for adult 4 Sets 2 1 1 126 Req-247 Statinary bik for adult CSSD 1 Set 1 1 128 Req-250 Storage cabinet for drug atorage 1 Set 1 1 129 Req-251 Storage cabinet for drug atorage 1 Set 1 1 129 Req-252 Storage cabinet for drug ato						<u> </u>		
10 10 10 10 1 1 121 Req-233 Short wave diathermy 3 Sets 1 1 1 121 Req-233 Shulder wheel 11 Sets 10 1 3 122 Req-246 Speculum sat 14 Sets 2 1 1 124 Req-246 Stationary bike for adult 4 Sets 2 1 1 125 Req-246 Stationary bike for adult 4 Sets 2 1 1 126 Req-247 Stationary bike for adult 4 Sets 2 1 1 125 Req-247 Stationacope for pediatric 2 Sets 1 1 126 Req-252 Storage cabinet for Clu's OSD 1 Set 1 1 130 Req-253 Suctor machine (merual) 4 Sets 3 1 1 133 Req-254 Suctor machine (merual) 31							I	
121 Req-233 Shulder wheel 1 Set 1 1 122 Req-240 Speaulum set 144 Sets 10 1 3 123 Req-240 Spring balance 1 Set 2 1 1 124 Req-244 Stationary biks for adult 4 Sets 2 1 1 125 Req-247 Stationary biks for adult 4 Sets 2 4 1 126 Req-247 Statinaccoe for padiatric 2 Sets 1 1 1 127 Req-250-1 Storage cabinet for Gulu CSD 1 Set 1 1 1 130 Req-262 Storage cabinet for gharange 1 Set 1 1 1 131 Req-263 Storage cabinet for gharange 1 Set 1 1 1 133 Req-264 Storage cabinet for gharange 1 Set 1 1 1 133 <td></td> <td></td> <td></td> <td></td> <td></td> <td>+</td> <td></td> <td></td>						+		
12 Req-268 Speculum act 14 Sets 10 1 121 Req-240 Sporing balance 11 Set 10 1 3 122 Req-244 Stationary bike for adult 44 Sets 2 1 1 124 Req-246 Stationary bike for adult 4 Sets 2 1 1 125 Req-247 Starlizing box set 2 Sets 2 4 1 126 Req-260-1 Storage cabinet for Gull CSSD 1 Set 1 1 128 Req-252 Storage cabinet for drug storage 1 Set 1 1 130 Req-252 Storage cabinet for plaronacy 1 Set 1 1 131 Req-253 Sucton machine (electrical) 31 Sets 3 1 1 132 Req-254 Sucton machine (manual) 44 Sets 3 1 1 133 Req-256 Syri								I
123 Reg-240 Spring balance 1 Sets 10 1 124 Reg-244 Stationary bike for adult 1 Sets 2 1 1 125 Reg-244 Stationary bike for adult 6 Sets 2 1 1 125 Reg-244 Stationary bike for adult 6 Sets 2 1 1 125 Reg-244 Stationscope for pediatric 2 Sets 2 1 1 126 Reg-251 Storage cabinet for Ulu CSSD 1 Set 1 1 1 130 Reg-252 Storage cabinet for Jarg storage 1 Set 1 1 1 131 Reg-253 Surdion machine (instruat) 31 Sets 13 8 10 133 Reg-264 Surdion machine (instruat) 31 Sets 3 11 133 Reg-265 Surdion machine (instruat) 3 Sets 1 2 1				<u></u>			<u> </u>	
124 Req-244 Stationary biks for adult 1 1 125 Req-246 Sted cabinet 6 Sets 2 1 1 125 Req-247 Sterilizing box set 2 Sets 2 1 1 126 Req-247 Sterilizing box set 2 Sets 2 1 1 127 Req-249 Stethoscope for pediatric 2 Sets 1 1 1 128 Req-250-1 Storage cabinet for Lira OSSD 1 Set 1 1 1 130 Req-253 Storage cabinet for hurmacy 1 Set 1 1 1 131 Req-254 Suction machine (electrical) 31 Sets 3 1 1 133 Req-256 Surgery instrument set 1 Set 3 1 2 1 133 Req-264 Theraputic message bad 1 Set 1 1 1 135 Req-26		+ ·····				10	1	3
125 Req-246 Steel abinet 1 1 1 126 Req-247 Starlizing box set 2 Sets 2 1 1 127 Req-247 Starlizing box set 2 Sets 2 1 1 128 Req-247 Starlizing box set 2 Sets 1 1 1 129 Req-250-1 Storage abinet for Gulu CSSD 1 Set 1 1 1 130 Req-251 Storage abinet for Jura CSSD 1 Set 1 1 1 131 Req-253 Suction machine (for Jura CSSD 1 Set 1 1 1 132 Req-253 Suction machine (for Jura CSSD 3 Set 1 1 1 133 Req-254 Suction machine (for Jura CSSD 3 Set 1 1 1 133 Req-264 Thorapeutio massage bad 3 Sets 1 1 1 133 R	<u> </u>	·					<u> </u>	1
International and the set Image: Constraint of the set Image: Constraint of the set Image: Constraint of the set 127 Req-247 Startizing box set Image: Constraint of the set								1
Image of the second of the parameter Image of the second of the parameter Image of the second of th		· · · · · · · · · · · · · · · · · · ·			Sets	2	4	
Interface Interface Image of the set of th		· · · · · · · · · · · · · · · · · · ·			Sets		1	1
129 Req-250-2 Storage cabinet for Lira CSSD 1 Set 1 1 130 Req-251 Storage cabinet for drug storage 1 Set 1 1 131 Req-252 Storage cabinet for pharmacy 1 Set 1 1 132 Req-253 Suction machine (electrical) 31 Sets 13 Rs 10 133 Req-254 Suction machine (manual) 44 Sets 33 1 1 134 Req-255 Surgery instrument set 1 Set 1 2 1 135 Req-264 Therapeutic massage bed 2 Sets 1 2 1 136 Req-266 Traction bed 1 Set 1 1 1 140 Req-270 Tread mill 1 Set 1 1 1 141 Req-272 Tympanometer 2 Sets 1 1 1 142 Req-270 It		· · · · · · · · · · · · · · · · · · ·		2	Sets	2		
Image Califies of any storage Image Califies of any storage of any				1	Set	1		
Integer and services Integer a				1	Set		1	
12 Req-253 Suction machine (electrical) 31 Sets 13 8 10 133 Req-254 Suction machine (manual) 4 Sets 3 1 1 134 Req-255 Surgery instrument set 1 Sets 3 1 1 135 Req-258 Syringe pump 3 Sets 1 2 1 136 Req-261 Therapeutic massage bed 2 Sets 2 5 137 Req-263 Thermometer 7 Sets 1 1 1 139 Req-266 Traction bed 1 Set 1 1 1 140 Req-270 Tread mill 1 Set 1 1 1 141 Req-271 Tympanometer 2 Sets 1 1 1 142 Req-272 Ultrasound machine (cardiac) 3 Sets 1 1 1 142 Req-282 Vacu			Storage cabinet for drug storage	1	Set	1		_
Interfer			Storage cabinet for pharmacy	1	Set		1	
134 Req-255 Surgery instrument set 1 Set 1 1 135 Req-258 Syringe pump 3 Sets 1 2 1 136 Req-261 Therapeutic massage bed 2 Sets 2 1 1 137 Req-263 Thermometer 7 Sets 2 1 1 138 Req-266 Traction bed 1 Set 1 1 1 139 Req-267 Traction machine for cervical 1 Set 1 1 1 140 Rea-270 Tread mill 1 Set 1 1 1 141 Req-272 Tympanometer 2 Sets 1 1 1 142 Req-277 Ultrasound machine (cardiac) 3 Sets 1 1 1 143 Req-278 Ultrasound machine (mobile) 4 Sets 3 1 1 144 Req-284 Vacu	<u> </u>			31	Sets	13	8	10
135 Req-258 Syringe pump 3 Sets 1 2 136 Req-261 Therapeutic massage bed 2 Sets 2 2 5 137 Req-263 Thermometer 7 Sets 2 2 5 138 Req-266 Traction bed 1 Sett 1 1 1 140 Req-270 Treation machine for cervical 1 Sett 1 1 1 140 Req-270 Tread mill 1 Sett 1 1 1 144 Req-277 Utrasonic therapy machine 3 Sets 1 1 1 143 Req-278 Uttrasound machine (cardiac) 3 Sets 1 1 1 144 Req-278 Uttrasound machine (mobile) 4 Sets 3 1 1 145 Req-284 Vacuum extractor 1 Sett 1 1 1 144 Req-293	133	Req-254	Suction machine (manual)	4	Sets	3	1	
136 Req-261 Therapeutic massage bed 2 Sets 2 2 137 Req-263 Thermometer 7 Sets 2 5 138 Req-266 Traction bed 1 Set 1 2 5 139 Req-267 Traction machine for cervical 1 Set 1 1 140 Req-270 Tread milt 1 Set 1 1 1 141 Req-270 Tread milt 1 Set 1 1 1 142 Req-275 Ultrasonic therapy machine 3 Sets 1 1 1 143 Req-275 Ultrasound machine (cardiac) 3 Sets 1 1 1 143 Req-278 Ultrasound machine (mobile) 4 Sets 3 1 1 144 Req-284 Vacuum extractor 1 Set 1 1 1 144 Req-294 Water bath 1	134	Req-255	Surgery instrument set	1	Set			1
InterpreterminationImage: SetsImage: SetsI	135	Req-258	Syringe pump	3	Sets	1	2	
138 Req-266 Traction bed 1 Set 1 Set <td>136</td> <td>Req-261</td> <td>Therapeutic massage bed</td> <td>2</td> <td>Sets</td> <td>2</td> <td></td> <td></td>	136	Req-261	Therapeutic massage bed	2	Sets	2		
139Req-267Traction machine for cervical1Set11140Req-270Tread mill1Set11140Req-270Tread mill1Set11141Req-272Tympanometer2Sets111142Req-275Ultrasonic therapy machine3Sets111143Req-277Ultrasound machine (cardiac)3Sets111144Req-278Ultrasound machine (mobile)4Sets311144Req-284Vacuum extractor1Set111145Req-285Ventilator1Set111146Req-285Ventilator1Set111147Req-284Water bath1Set111148Req-294Water bath1Set111148Req-295Water distillizer4Sets121150Req-296Weighing and height scale for adult3Sets531151Req-298Weighing scale for infant5Sets411153Req-306Working table for CSSD2Sets2Sets2Sets	137	Req-263	Thermometer	7	Sets	2		5
140Req-270Tread mill1Set11141Req-270Tread mill1Set11141Req-272Tympanometer2Sets11142Req-275Ultrasonic therapy machine3Sets111143Req-277Ultrasound machine (cardiac)3Sets111144Req-278Ultrasound machine (mobile)4Sets311144Req-284Vacuum extractor1Set111145Req-285Ventilator1Set111146Req-285Ventilator1Set111147Req-294Water bath1Set111148Req-294Water bath1Set121150Req-296Weighing and height scale for adult3Sets531151Req-300Weighing scale for infant5Sets411153Req-304Wheel chair17Sets458154Req-306Working table for CSSD2Sets2 \cdots 1	138	Req-266	Traction bed	1	Set	1		
Interpretation Interpr	139	Req-267	Traction machine for cervical	1	Set			1
142Req-275Ultrasonic therapy machine3Sets11143Req-277Ultrasound machine (cardiac)3Sets111144Req-278Ultrasound machine (mobile)4Sets311144Req-282Vacuum extractor1Set111145Req-282Vacuum extractor1Set111146Req-285Ventilator1Set111147Req-293Washing machine3Sets111148Req-294Water bath1Set111149Req-295Water distillizer4Sets121150Req-296Weighing and height scale for adult3Sets531151Req-298Weighing scale for infant5Sets411153Req-300Weighing table for CSSD2Sets258154Req-306Working table for CSSD2Sets2553	140	Req-270	Tread mill	1	Set	1		
143Req-277Ultrasound machine (cardiac)3Sets111144Req-278Ultrasound machine (mobile)4Sets311144Req-282Vacuum extractor1Set111145Req-282Vacuum extractor1Set111146Req-285Ventilator1Set111147Req-293Washing machine3Sets111148Req-294Water bath1Set111149Req-295Water distillizer4Sets121150Req-296Weighing and height scale for adult3Sets531151Req-300Weighing scale for infant5Sets411153Req-304Wheel chair17Sets258154Req-306Working table for CSSD2Sets211	141	Req-272	Tympanometer	2	Sets	1	1	
144Req-278Ultrasound machine (mobile)4Sets31145Req-282Vacuum extractor1Sets11146Req-285Ventilator1Set11146Req-293Washing machine3Sets11147Req-293Washing machine3Sets11148Req-294Water bath1Set11149Req-295Water distillizer4Sets121150Req-296Weighing and height scale for adult3Sets31151Req-298Weighing scale for adult9Sets531152Req-300Weighing scale for infant5Sets411153Req-304Wheel chair17Sets258154Req-306Working table for CSSD2Sets21	142	Req-275	Ultrasonic therapy machine	3	Sets	1	1	1
145Req-282Vacuum extractor1Set11146Req-285Ventilator1Set11147Req-293Washing machine3Sets111148Req-294Water bath1Set111149Req-295Water distillizer4Sets121150Req-296Weighing and height scale for adult3Sets531151Req-298Weighing scale for adult9Sets531152Req-300Weighing scale for infant5Sets411153Req-306Working table for CSSD2Sets2I1	143	Req-277	Ultrasound machine (cardiac)	3	Sets	1	1	1
146Req-285Ventilator1Set11147Req-293Washing machine3Sets111148Req-294Water bath1Sets111149Req-295Water distillizer4Sets121150Req-296Weighing and height scale for adult3Sets531151Req-298Weighing scale for adult9Sets531152Req-300Weighing scale for infant5Sets411153Req-304Wheel chair17Sets21154Req-306Working table for CSSD2Sets21	144	Req-278	Ultrasound machine (mobile)	4	Sets	3	1	
147Req-293Washing machine3Sets111148Req-294Water bath1Sets111149Req-295Water distillizer4Sets121150Req-296Weighing and height scale for adult3Sets121151Req-298Weighing scale for adult9Sets531152Req-300Weighing scale for infant5Sets411153Req-304Wheel chair17Sets281154Req-306Working table for CSSD2Sets211	145	Req−282	Vacuum extractor	1	Set	1		
148Req-294Water bath1Set11149Req-295Water distillizer4Sets121150Req-296Weighing and height scale for adult3Sets33151Req-298Weighing scale for adult9Sets531152Req-300Weighing scale for infant5Sets411153Req-304Wheel chair17Sets458154Req-306Working table for CSSD2Sets21	146	Req-285	Ventilator	1	Set	1		
148Req-294Water bath1Set11149Req-295Water distillizer4Sets121150Req-296Weighing and height scale for adult3Sets331151Req-298Weighing scale for adult9Sets531152Req-300Weighing scale for infant5Sets411153Req-304Wheel chair17Sets458154Req-306Working table for CSSD2Sets21	147	Req-293	Washing machine	3	Sets	1	1	1
150Req-296Weighing and height scale for adult3Sets121151Req-298Weighing scale for adult9Sets531152Req-300Weighing scale for infant5Sets41153Req-304Wheel chair17Sets458154Req-306Working table for CSSD2Sets21	148	Req-294	Water bath	1	Set	1		
150Req-296Weighing and height scale for adult3Sets3151Req-298Weighing scale for adult9Sets531152Req-300Weighing scale for infant5Sets411153Req-304Wheel chair17Sets458154Req-306Working table for CSSD2Sets21	149	Req-295	Water distillizer	4	Sets	1	2	1
151 Req-298 Weighing scale for adult 9 Sets 5 3 1 152 Req-300 Weighing scale for infant 5 Sets 4 1 1 153 Req-304 Wheel chair 17 Sets 4 5 8 154 Req-306 Working table for CSSD 2 Sets 2	150	Req-296	Weighing and height scale for adult	3	Sets			
152 Req-300 Weighing scale for infant 5 Sets 4 1 153 Req-304 Wheel chair 17 Sets 4 5 8 154 Req-306 Working table for CSSD 2 Sets 2	151	Req-298	Weighing scale for adult	9		5		1
153 Req-304 Wheel chair 17 Sets 4 5 8 154 Req-306 Working table for CSSD 2 Sets 2	152	Req 3 00	Weighing scale for infant	5				
154 Req-306 Working table for CSSD 2 Sets 2 155 D 2027 Weak in the set of the se	153	Req-304	Wheel chair					
	154	Req-306	Working table for CSSD					
	155		Working table for pharmacy		Set		1	

M

hung

11

A

This page is closed due to the confidentiality.

This page is closed due to the confidentiality.

This page is closed due to the confidentiality.

			Total Months	ths											
/		12 13	14 15	5 16	17	18	19	20	21	22 23	24	25	26	27 28	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~
/	Dig Feb Mar Anr May Jun Jul Aug Sep Oct Nov	Dec Jan.2019	Feb Mar	ar Apr	May	Jun	lut	Aug	Sep	Oct Nov	Dec	Jan.2020	Feb A	Mar Apr	Ы
	A Transfer of the Detailed design														*******
Entire Schedule			Sune	tvision.of.cs	į onstructio] 1 work and e	auinment s	timiy / insta	Sunervision of construction work and continuent sumby / installation / 16 months)	i aonths)					
ę	Onsultant surcement Consultant arreement Perification of consultant arreement Verification of consultant arreement Field survey for detailed design Detailed design D/D Detailed design E Detailed design														
Tender	Preparation of trader documents Preparation of trader documents Prequalification (P/O) notice & ev Reporting P/O. Approval Eva	ntract		,	****				//////////////////////////////////////						
		GCS													
IL				Construc Construc Construc	Construction work /16 Construction work /14 Construction work /14 Construction work /12		months) at Gutta RPH months) at Liza RPH months) at Ama RRH	H. H. H.							
supervis of Construct / Equipm Works	upervasou of Bquipment Works		*****		Cut Cut	Gultı RRH	Shipping	stallation adju Drefation	Alternation adjustment	ereconstruction adjustment in a second and a second adjustment in a second adjustment in a second and a second adjust over the second adj				,	1993 W 1 W 1 W W 1 W 1 W 1 W 1 W 1 W 1 W 1
			10-00-00-00-00-00-00-00-00-00-00-00-00-0		Anu	Arua RRH	Shinoing I	stallation, a Opera <u>operation</u> stallation, a Opera	Installation, adjustment Installation, adjustment Installation, handi Operation training, handi Operation adjustment Installation, adjustment Installation, band	ation, adiustment Operation training, handing over 					************************************
	Demolition and/or removal of existing buildings and sinctures, site leveling, etc. Gulu														
Measures to be taken by the GOU	Percent and arructures, site level	int etc. Lifa structures, site levelint etc. /	Arua				•					•		<u></u>	*****
	Note 1) Supervision period of construction / equipment works will be reconsidered according to the result of field surveys 2) : Works in Uganda	result of field surve	ski												
]														

Annex 4: Project Implementation Schedule (tentative) (Detailed Design / Construction - Equipment Works)

4: Project Implementation Schedule (tentative) ۸n

Annex 5: Major Undertakings to be taken by the Government of Uganda

Specific obligations of the Government of Uganda which will not be funded with the Grant

(1) Before the Tender

NO	Items	Deadline	In charge	Estimated Cost (1,000UShs)	Ref.
1	To open bank account (B/A)	within 1 month after the signing of the G/A	MOH	-	
-	To issue A/P to a bank in Japan (the Agent Bank) for the payment to the consultant	within 1 month after the signing of the contract	MOH	9,100	the Draft Report
	To provide alternative space for the services carried out in the facilities to be demolished during construction period.	before start of demolition	RRHs	Gulu 6,000 Lira 21,500 Arua 6,000	the Draft Report
4	 To secure and clear land for ; 1) the construction areas 2) the area for temporary office, temporary store and working shade, stock yard for materials and concrete mixing space 	before notice of the bidding document	RRHs	-	
5	To obtain the planning, zoning, building permit	before notice of the bidding document	MOH and RRHs	-	
6	To clear, level and reclaim the following sites at the construction areas including their foundations	before notice of the bidding document	Gulu RRH	58,600	
	 the existing buildings all existing trees the existing sewerage pipes, 		Lira RRH	49,300	the Draft Report
	 any other obstacles 		Arua RRH	43,100	
7	To submit Project Monitoring Report (with the result of Detailed Design)	before preparation of bidding documents	МОН		

(B/A: Banking Arrangement, A/P: Authorization to pay, N/A: Not Applicable)

16

(2) During the Project Implementation

NO	Items	Deadline	In charge	Estimated Cost (1,000UShs)	Ref.
	To issue A/P to a bank in Japan (the Agent Bank) for the payment to the Contractor(s)	within 1 month after the signing of the contract(s)	MOH	(1,00000000)	
2	To bear the following commissions to a bank in Japan for the banking services based upon the B/A		МОН	77,560	the Draft Report
	1) Advising commission of A/P	within 1 month after the signing of the contract(s)	MOH		
	2) Payment commission for A/P	every payment	MOH	<u> </u>	
3	To ensure prompt customs clearance and to assist the Supplier(s) with internal transportation in recipient country	during the Project	МОН	-	
4	To accord Japanese nationals and/or physical persons of third countries whose services may be required in connection with the supply of the products and the services such facilities as may be necessary for their entry into the country of the Recipient and stay therein for the performance of their work	during the Project	МОН	-	
5	To ensure that customs duties, internal taxes and other fiscal levies which may be imposed in the country of the Recipient with respect to the purchase of the products and/or the services be borne by its designated authority without using the Grant.	during the Project	МОН	*	
6	To bear all the expenses, other than those covered by the Grant, necessary for the implementation of the Project	during the Project	MOH and RRHs		
7	To submit Project Monitoring Report	every month	MOH	-	
	 To submit Project Monitoring Report (final) 	within one month after signing of Certificate of Completion for the works under the contract(s)		-	
8	To submit a report concerning completion of the Project	completion of the Project		-	
9	To conduct necessary pre-installation	before installation of	Gulu RR	н 11,000	
	works in the case of installing new	equipment	Lira RRI	H 6,500	the Dra
	equipment in the existing buildings		Arua RR	H 12,000	
10	To provide facilities for distribution of electricity, water supply and drainage and other incidental facilities necessary for the implementation of the Project outside the sites		RRHs		
	 1) Electricity The distributing line and appropriate power supply to the buildings 	before start of the construction	Gulu RR Lira RR Arua RR	H 1,550	the Dra Repor
	TA	17 Muy		M	\

......

*

 Water Supply The water supply line and the appropriate water supply to the buildings 	6 months before completion of the construction	RRHs	-	
 Drainage The public sewer line and the appropriate drainage system to the buildings 	6 months before completion of the construction	RRHs	-	
4) LAN systemLAN system wiring in the existing	6 months before completion of the construction	Lira RRH	10,000	
building and between the existing building and the new building (for CR system)		Arua RRH	10,000	the Draft Report
5) Furniture and Equipment	1 month before completion	Gulu RRH	31,000	
- general furniture and office	of the construction	Lira RRH	31,000	the Draft
equipment		Arua RRH	31,000	Report
To take necessary measure for safe construction and traffic control	during the construction	RRHs	-	

* The estimated costs to be borne by by the Executing Agency will be calculated in the later stage.

my 18

(3) After the Project

NO	Items	Deadline	In charge	Estimated Cost (1,000UShs)	Ref.
1	To maintain and use properly and effectively the facilities constructed and equipment provided under the Grant Aid 1) Allocation of maintenance cost 2) Operation and maintenance system 3) Routine check/Periodic inspection 4) Spare parts and Consumables	After completion of the construction	MOH and RRHs	-	

M 19

Project Monitoring Report on Project Name Grant Agreement No. XXXXXXX 20XX, Month

Organizational Information

Signer of the G/A (Recipient)	Person in Charge Contacts	Address:
		Phone/FAX: Email:
Executing Agency	Person in Charge Contacts	(Designation) Address: Phone/FAX: Email:
Line Ministry	Person in Charge Contacts	(Designation) Address: Phone/FAX: Email:

General Information:

Project Title	
E/N	Signed date: Duration:
G/A	Signed date: Duration:
Source of Finance	Government of Japan: Not exceeding JPY <u>mil.</u> Government of ():

20 Sum

1: Project Description

1-1 Project Objective

1-2 Project Rationale

- Higher-level objectives to which the project contributes (national/regional/sectoral policies and strategies)
- Situation of the target groups to which the project addresses

1-3 Indicators for measurement of "Effectiveness"

Quantitative indicators to measure the attainment of project objectives					
Indicators	Original (Yr)	Target (Yr)	
					
Qualitative indicators to measure the	attainment of projec	t objectives	3		

2: Details of the Project

2-1 Location

	Components	Original (proposed in the outline design)	Actual	
1.				
	~		·	

2-2 Scope of the work

Components	Original*	Actual*
-	(proposed in the outline design)	
1.		

2

Reasons for modification of scope (if any).

(PMR)

Implementation Schedule 2-3

	Or	iginal	
Items	(proposed in the outline design)	(at the time of signing the Grant Agreement)	Actual

Reasons for any changes of the schedule, and their effects on the project (if any)

2-4 **Obligations by the Recipient**

- 2-4-1 Progress of Specific Obligations See Attachment 2.
- 2-4-2 Activities See Attachment 3.
- 2-4-3 Report on RD See Attachment 11.
- 2-5 **Project Cost**

2-5-1 Cost borne by the Grant(Confidential until the Bidding)

 Components		Co (Million	
 Original (proposed in the outline design)	Actual (in case of any modification)	Original ^{1),2)} (proposed in the outline design)	Actual
 1.			
 Total			

•..

1) Date of estimation: Note:

2) Exchange rate: 1 US Dollar = Yen

Cost borne by the Recipient 2-5-2

 Components		Cost	
Original (proposed in the outline design)	Actual (in case of any modification)	Original ^{1),2)} (proposed in the outline design)	Actual
1.			
)
M	22 Mary	Ń	l

Note: 1) Date of estimation:

2) Exchange rate: 1 US Dollar =

.

..

Reasons for the remarkable gaps between the original and actual cost, and the countermeasures (if any)

.

(PMR)

2-6 Executing Agency

- Organization's role, financial position, capacity, cost recovery etc,
- Organization Chart including the unit in charge of the implementation and number of employees.

Original (at the time of outline design)

name: role:

financial situation:

institutional and organizational arrangement (organogram): human resources (number and ability of staff):

Actual (PMR)

2-7 Environmental and Social Impacts

- The results of environmental monitoring based on Attachment 5 (in accordance with Schedule 4 of the Grant Agreement).

- The results of social monitoring based on in Attachment 5 (in accordance with Schedule 4 of the Grant Agreement).

- Disclosed information related to results of environmental and social monitoring to local stakeholders (whenever applicable).

3: Operation and Maintenance (O&M)

3-1 Physical Arrangement

- Plan for O&M (number and skills of the staff in the responsible division or section, availability of manuals and guidelines, availability of spareparts, etc.)

Original (at the time of outline design)

Actual (PMR)

3-2 Budgetary Arrangement

- Required O&M cost and actual budget allocation for O&M

Original (at the time of outline design)

outline design)	2.	١
to -	23 / mm	M

4: Potential Risks and Mitigation Measures

- Potential risks which may affect the project implementation, attainment of objectives, sustainability
- Mitigation measures corresponding to the potential risks

Assessment of Potential Risks (at the time of outline design)

Potential Risks	Assessment
1. (Description of Risk)	Probability: High/Moderate/Low
	Impact: High/Moderate/Low
	Analysis of Probability and Impact:
	Mitigation Measures:
	Action required during the implementation stage:
	Contingency Plan (if applicable):
2. (Description of Risk)	Probability: High/Moderate/Low
2. (Description of Risk)	Impact: High/Moderate/Low
	Analysis of Probability and Impact:
	Mitigation Measures:
	Action required during the implementation stage:
	Contingency Plan (if applicable):
3. (Description of Risk)	Probability: High/Moderate/Low
	Impact: High/Moderate/Low
	Analysis of Probability and Impact:
	Mitigation Measures:
	Action required during the implementation stage:
7	3 24 hring M

	Contingency Plan (if applicable):
Actual Situation and Countermeasure	S
(PMR)	······································

5: Evaluation and Monitoring Plan (after the work completion)

5-1 Overall evaluation

Please describe your overall evaluation on the project.

5-2 Lessons Learnt and Recommendations

Please raise any lessons learned from the project experience, which might be valuable for the future assistance or similar type of projects, as well as any recommendations, which might be beneficial for better realization of the project effect, impact and assurance of sustainability.

5-3 Monitoring Plan of the Indicators for Post-Evaluation

Please describe monitoring methods, section(s)/department(s) in charge of monitoring, frequency, the term to monitor the indicators stipulated in 1-3.

25 Muy

1. Initial Conditions (Confirmed)

г							
	ffpayment Price (Increased) ************************************	•					
	-Condition of Price (Decreased) E=C-D:	•					
	1% of Contract, Prices D	•	•				
	Initial total Price C=A×B	•	•				
	Unit (¥)	•	•				
	ime Prices Brice	●●t	••t				
/	Initial Volume						
momentary empiritual remains	Items of Specified Materials						
TTOO TRIVITE T	Items of S	Item 1	Item 2	Item 3	Item 4	Item 5	
-		-	2	က	4	ъ	

- Monitoring of the Unit Price of Specified Materials
 Method of Monitoring : ●●
- (2) Result of the Monitoring Survey on Unit Price for each specified materials

Items of Specified Materials Items of Specified Materials Items of Specified Materials 6th Item 1 Item 2 Item 2 Item 4 6th 5 Item 5 Item 5 Item 4 6th	ſ					-				
ems of Specified Materials Control of the Monthly 2015 Conducting Survey of Other Active Acti		न								
ems of Specified Materials Control of the Monthly 2015 Conducting Survey of Other Active Acti		6								
ems of Specified Materials Control of the Monthly 2015 Conducting Survey of Other Active Acti										
ems of Specified Materials Control of the Monthly 2015 Conducting Survey of Other Active Acti		17-13) 17-13) 18-13								
ems of Specified Materials Control of the Monthly 2015 Conducting Survey of Other Active Acti	-	th								
sult of the Monthly Durvey of Onth 2015 Circle Materials and 1 Circle Materials Conth, 2015 Circle Month, 2015 Circle Materials Circle Material	:	9								
sult of the Monthly Durvey of Onth 2015 Circle Materials and 1 Circle Materials Conth, 2015 Circle Month, 2015 Circle Materials Circle Material										
sult of the Monthly Durvey of Onth 2015 Circle Materials and 1 Circle Materials Conth, 2015 Circle Month, 2015 Circle Materials Circle Material										
sult of the Monthly Durvey of Onth 2015 Circle Materials and 1 Circle Materials Conth, 2015 Circle Month, 2015 Circle Materials Circle Material		4th								
ems of Specified Materials • • month, 2015 • • 2nd em 1 em 2 em 5 em 5										
ems of Specified Materials • • month, 2015 • • 2nd em 1 em 2 em 5 em 5		<u>.</u>				-				
ems of Specified Materials • • month, 2015 • • 2nd em 1 em 2 em 5 em 5		d h; 201								
ems of Specified Materials • • month, 2015 • • 2nd em 1 em 2 em 5 em 5		3r mont							1	
ems of Specified Materials month, 2015 mon		altania.				-				
ems of Specified Materials month, 2015 mon		2015								
ems of Specified Materials month, 2015 mon		2nd nth, 5				-			ļ	
1 Items of Specified Materials 1 Items of Specified Materials 2 Item 1 1 Item 2 1 Item 2 1 Item 3 1 Item 4 5 Item 5		Omo								
2) Result of Life Molluoling Durvey of Life 1 Items of Specified Materials month, 201 2 Item 2 1 Item 3 5 Item 3 5 Item 5 1 Item 5	TOL CO	2							-	
1 Items of Specified Materials 1 Items of Specified Materials 1 Item 1 1 Item 2 1 Item 3 1 Item 4 1 Item 5	- LICE -	t. 1,201								5
2) And the molitoning our ey of the molitoning our ey of the sector of the molitoning our ey of the sector of the molitoning our ey of the sector of the molitoning our eyes of the molitoning our	r mr o	nontl								
2 Items of Specified Materials 1 Item 1 2 Item 2 3 Item 3 5 Item 5 1 It	л оп									
2) Result of Litems of Specified Materials 1 Item 1 2 Item 2 1 Item 3 1 Item 3 5 Item 4 5 Item 5 1	avino	ials								,
2) result of Lifems of Specified 1 Item 1 1 Item 2 2 Item 2 1 Item 3 5 Item 5 1 Item 5 1 Item 5	gma	Mate	i							
2) Ansult of Litems of Spec 1 Item 1 1 Item 2 2 Item 2 1 Item 3 1 Item 3 1 Item 3 1 Item 3 1 Item 5 1 Item	TOTTO	ifiéd								
$\begin{array}{c c} & & & & \\ \hline \\ & & & \\ \hline & & & \\ \hline & & & \\ \hline \\ \hline$	и апл	Spec								ĥ
The second secon	TO 311	ims of	n 1	n 2	n 3	n 4	n 5			
AD 27 Muy	ves	Ite	Iter		-					2
75 27 Jun	۲ ب		Η		I	I	ы С		1	2 3
	\checkmark	Σ_{-}			27	!	/	7	M	η

(3) Summary of Discussion with Contractor (if necessary)

Attachment 7

Report on Proportion of Procurement (Recipient Country, Japan and Third Countries) (Actual Expenditure by Construction and Equipment each)

	Domestic Procurement	Foreign Procurement	Foreign Procurement	Total
	(Recipient Country)	(Japan)	(Third Countries)	Q
	Α	B	C	
Construction Cost	(%D/D)	(B/D%)	(C/D%)	
Direct Construction Cost	(%D/V)	(B/D%)	(C/D%)	
others	(%D%)	(B/D%)	(C/D%)	i
Equipment Cost	(%D/V)	(B/D%)	(C/D%)	
Design and Supervision Cost	(%D/V)	(B/D%)	(C/D%)	
Total	(%U/D)	(B/D%)	(C/D%)	

ÂĄ,

28

A

Appendix 5 Technical Note

TECHNICAL NOTE ON PREPARATORY SURVEY (FIELD SURVEY 2) ON THE PROJECT FOR IMPROVEMENT OF REGIONAL REFERRAL HOSPITALS IN NORTHERN UGANDA

After Signing of Minutes of Discussions on 2nd March 2017, the consultant team held discussions with the officials concerned from the Government of Uganda. In the course of discussions and field surveys, both parties confirmed the items described below.

- 1. Facilities
- (1) The Japanese Survey Team explained roughly the required building Conceptual Schematic Design (Maternity/Casualty/Theatre Block in Gulu RRH, OPD/Casualty Block and Delivery Suite in Lira RRH, and OPD/Casualty Block in Arua RRH) as shown in ANNEX to the Ugandan Counterparts. The Ugandan Counterparts agreed to the preliminary Building Conceptual Schematic Design.
- (2) The Japanese Survey Team and the Ugandan Counterparts agreed that the solar water heater system shall be installed in the Maternity/Casualty/Theatre Block in Gulu RRH and the Delivery Suite in Lira RRH, and shall not be installed in the OPD/Casualty Blocks in Lira and Arua RRHs.
- (3) The Japanese Survey Team and the Ugandan Counterparts agreed that the manifold and the oxygen piping shall only be installed in the Operation Theatre and the ICU in Gulu RRH, and shall not be installed in any other buildings including the Casualty Units in all RRHs.
- 2. Equipment

The Ugandan side additionally requested equipment as below;

- Laparoscope x 1unit, Colonoscope x 1unit and Gastroscope x 1unit for Gulu RRH
- Mammograph x 1unit and Fetal Doppler x 1unit for Lira RRH

The Japanese Survey Team will analyze the requested equipment for all the three hospitals (including the additional requested equipment) in Japan, and plan the component of equipment for the project.

parchánio.



Kampala, 9th March, 2017

γ.


facciano. Dr. Jackson Amone

Acting Commissioner for Health Services (Clinical Services), MOH

Con et keiichi Ide


Mr. Keiichi Ide Project Manager Survey Team

ANNEX











CENSULTANT

THE CONSURTIUM OF YOROGAVA ARCHITECTS & ENGINEERS, DAC AND INTEM CONSULTING, INC


INTERNE HERe Country In WYORDGAWA ARCHITECTS & ENGINEERS, INC.



THE PREPARATORY SURVEY FOR THE PROJECT FOR IMPROVEMENT OF REGIONAL REFERRAL HOSPITALS IN NORTHERN UGANDA



Aachiamo.



THE CONSORTIUM OF YOROGAWA ARCHITECTS & ENGINEERS, INC AND INTEM CONSULTING, INC. PROJECT THE PREPARATORY SURVEY FOR THE PROJECT FOR IMPROVEMENT OF REGIONAL REFERRAL HOSPITALS IN NORTHERN UGANDA



Gachamo.



YORGAWA ARCHITECTS & ENGINEERS, INC.

THE PREPARATORY SURVEY FOR THE PROJECT FOR IMPROVEMENT OF REGIONAL REFERRAL HOSPITALS IN NORTHERN UGANDA


DATE E SITE LIRA RRH ù,

fachamo.

CONSULTANT THE CONSURTIUM OF YDROGAWA ARCHITECTS & ENGINEERS, INC AND INTEM CONSULTING, INC.


WTEH:







Y














CONSULTANT

THE CONSORTIUM OF YORDGAVA ARCHITECTS & ENGINEERS, INC. AND INTEM CONSULTING, INC

YORDGAWA ARCHITECTS & ENGINEERS, INC.



PREJECT THE PREPARATORY SURVEY FOR THE PROJECT FOR IMPROVEMENT OF REGIONAL REFERRAL HOSPITALS IN NORTHERN UGANDA





PREPARATORY SURVEY ON THE PROJECT FOR IMPROVEMNET OF REGIONAL REFERRAL HOSPITALS IN NORTHERN UGANDA

SOFT COMPONENT (TECHNICAL ASSISTANCE) PLAN

August 2017

Consortium of Yokogawa Architects & Engineers, Inc. and INTEM Consulting, Inc.

Contents

1.	Background of Soft Component	1
	Objectives of Soft Component	
	Output of Soft Component	
	Method for Confirming the Degrees of Achievement of Outouts	
	Activities of Soft Component (Input Plan)	
	Method for Procuring Resources for the Implementation of Soft Component	
7.	Implementing Schedule of Soft Component	9
8.	Deliverable of Soft Component	10
	Responsibility of Implementing Agencies of Recipient Country	

1. Background of Soft Component

The Project for Improvement of Regional Referral Hospitals in Northern Uganda (hereinafter called the Project) in to improve facilities and medical equipment in three regional referral hospitals in Northern Uganda. Among the targeted hospitals, Gulu Regional Referral Hospital (hereinafter called "RRH"), Lira RRH and Arua RRH will be assisted though the construction of facilities and procurement of medical equipment.

The Ugandan government is progressing activities focusing on the improvement of healthcare service as an important area, following Health Sector Development Plan: (HSDP, 2015-2019). Japanese government has implemented support to RRH in Soroti region, East area, Central area and Western area as Grant Aid in the past. This Project is positioned as following these projects, and the content of support is similar.

The equipment planned for this Project has been selected through adequate discussions with the Ugandan side in the field survey as well as complying with the standard equipment list specified by the Ministry of Health (hereinafter called "MOH"). In addition, its validity has been sufficiently verified, consistent with the Ugandan implementation system (personnel, budget, etc.), and there is no particular problem in its use. However, some equipment items at the target hospitals are not currently used due to lack of actual equipment at hospitals, aging of equipment or breakdowns. Therefore, although doctors or nurses have experiences of using equipment in the past, there are some concerning about handling techniques of the equipment. For these reasons, it is desirable to brush up clinical techniques to use supplied equipment based on sustained and up-to-date knowledge after the procurement.

Under these circumstances, soft components aimed at brushing up clinical techniques have been implemented in the past projects targeting central and western Regional Referral Hospitals, and have lead to effective utilization of equipment after project implementation. From past actual achievement, it is highly significant to implement soft component intended to brush up clinical techniques.

Additionally, CR (Computed Radiography) system is planned in place of the existing system for using film in radiation diagnosis. This system is an alternative system of classic method, and since the conventional technology is applied, no major technical obstacle is not likely to be occurred. However, the data management method such as storing digital data in server, the image sharing method which share in digital data via LAN instead of film are totally different. It is also an advantage for CR system to be able to use image editing technology by using software, for example emphasizing necessary diagnostic part or correcting insufficient exposure.

In order to understand these differences from the operation method with film and to make effective operation of obtained data, it is necessary to implement comprehensive training including LAN environment as well as training by equipment manufacture. Unlike initial instruction and operation training by agent technician, this soft component is effective that including how to process clinically useful digital data and how to decide rules for data sharing across hospitals.

In the past projects, supplier and technician from agent conducted instruction for operation and maintenance. However the knowledge and technique are likely to become ambiguous as time passed, as a result, there are risk in which the equipment is operated with inappropriate usage method or a slight breakdown is ignored. Besides, the staffs who have received training when installation are sometimes in place changed after a year since installation. Therefore this soft component which implement training after half of year from installation can contribute to resolve and improve these issues significantly by re-training the operation method including clinical technology and the maintenance method.

From above viewpoints, the MOH has requested the Japanese side to provide soft component service for these technical assistance. In response to that request, the Project plan the following soft components.

- I Training in Clinical Techniques
- II Training in CR system
- III Training in maintenance management

Remark, currently technical cooperation project "Project on Improvement of Health Service through Health Infrastructure Management (Phase2)" has been implemented. User trainer who has capability to train effective operation and maintenance method of medical equipment have been trained up in captioned project targeting Regional Referral Hospital including targeted 3 RRH of this project. Additionally this captioned project has made maintenance system be strengthening for regional workshops¹. This soft component narrow down the targeted equipment based on the result of this technical cooperation project.

2. Objectives of Soft Component

At the target hospitals, clinical training, maintenance training and CR system training will be carried out to medical staffs (doctors, nurses, etc.). Also training on equipment maintenance management technology will be implemented to regional workshop engineers. The achievement of the following three objectives can be expected after implementation soft component in case of the effectiveness is continued after the implementation.

- I Supplied equipment is effectively used
- II The CR system is effectively operated
- III Technique for maintenance management of supplied equipment is improved, and equipment is appropriately managed and operated for a long time

3. Output of Soft Component

The outputs to be achieved at the completion of soft components are as follows.

I Training in Clinical Techniques

This training will be implemented after half of year since the hand over. Outputs are as bellow.

- I-① Marshal clinical knowledge about function and role of supplied equipment
- I-2 Mater appropriate handling technique depending on situation of patient using targeted equipment

II Training in CR system

This training will be implemented just after the handover. This targets medical staffs for X-ray such as X-ray technicians, X-ray doctors and doctors in each department. Outputs are as bellow.

II-(1) Share X-ray image effectively within the hospital

II - 2 Improve the quality of X-ray image and increase accuracy of diagnosis

III Training in maintenance management

This training will be implemented after half of year since the handover of equipment.

This training targets medical staffs such as doctors and nurses who operate supplied equipment in the target hospital and regional workshop technicians.

III-① Re-confirm principle purpose of supplied equipment and improve operation technique

III-2 Learn inspection and maintenance method focused on supplied equipment and construct constant maintenance and operation system

III-③ Improve technique for trouble shooting to identify problem on equipment and be able to share correct information about trouble to the central workshop or technicians in manufactures.

4. Method for Confirming the Degrees of Achievement of Outputs

Achievement of the soft components will be confirmed in the following manner.

¹ Workshop: workshops are in charge of maintenance and management of all infrastructures including facilities and medical equipment at governmental healthcare facility. There are 12 workshops in Uganda. The capital, Kampala, is covered by the central workshop under the control of the Infrastructure department of MOH, and the other 11 areas are covered by regional workshops. A regional workshop is located at each of the targeted are of RRH, controlling maintenance and management of all the health facilities allocated in these areas.

	Output	Method of Confirming Achievements
I Training in	① Marshal clinical knowledge about function and role of supplied equipment	Level of understanding will be confirmed by carrying out technical assessment before and after the provision of technical training.
Clinical Techniques	② Mater appropriate handling technique depending on situation of patient using targeted equipment	Level of understanding will be confirmed by carrying out technical assessment before and after the provision of technical training.
II Training in CR system	① Share X-ray image effectively within the hospital	Level of understanding will be confirmed by carrying out post-test after the provision of technical training.
	② Improve the quality of X-ray image and increase accuracy of diagnosis	Check edited images after training and confirm level of understanding
III Training in maintenance management	① Improve operation technique	Check the number of unused equipment and the frequency of use before training, and confirm the improvement of availability ratio after training.
	2 Learn inspection and maintenance method focused on supplied equipment and construct constant maintenance and operation system	Level of learning will be confirmed by carrying out technical assessment before and after the provision of technical training.
	3 Improve technique for trouble shooting to identify problem	Improvement of technique will be confirmed by carrying out technical assessment before and after the provision of technical training.

5. Activities of Soft Component (Input Plan)

Activities to achieve each output (Input Plan) are as follows.

- (1) Trainers
- Consultant for clinical technique: Ugandan doctor, 1 person
- Consultant for CR system: Japanese expert, 1 person
- Consultant for operation and maintenance technique: Japanese expert, 1 person
- Consultant for training planning: Japanese expert, 1 person
- (2) Plan of Operation

Activities ①Preparation work in Japan ②Field work ③Post work in Japan Details are as follows.

① Preparation work in Japan

Each consultant prepares lecture materials necessary for each training. Consultant for training planning will organize the training program of each specialized training, meeting with MOH, targeted hospitals, other related organizations, and arrange venues and transportation in advance. Number of days required for domestic preparation work: Consultant for CR system 3 days. Consultant for operation and maintenance technique 3 days. Consultant for training planning 5 days.

Cosultant for clinical technique and consultant for operation and maintenance technique need to check the situation of equipment before visiting the hospitals via email and prepare necessary documents before the training which is implemented after half of year since the handover.

⁽²⁾Training in Uganda

			Plan of Operation			
	Output	Lecture	Outline of Training			
I Training in Clinical	①Marchal clnical knowledge about function and role of supplied equipment	Consultant for clinical	-Confirmation of principle and purpose of use, re-learning basic knowledge (just after hand over) -Resolusion of unclear point and re-confirmation of principle and purpose of use on equipment (after half of year sicce hand over)			
Techniques	⁽²⁾ Mater appropriate handling technique depengin on situation of patient using targeted equipment	technique	 Training method of applying real case in practice (just after hand over) Re-training method of applying real case in practice and resolusion of unclear points (after half of year sicce hand over) 			
II Training in CR system	 ①Share X-ray image effectively within the hospital ②Improve the quality of X-ray image and incressase accuracy of diagnosis 	Consultant for CR system	 Training operation method of digital data including receive, store and search method Construct rule to store digital data Training editing techniques for actual obtained images 			
III Training in maintenance management	 ①Improve operation technique ②Learn inspection and maintenance method focused on supplied equipment and construct constant maintenance and opearation system ③Improve technique for 	Consultant for operation and maintenance technique	 Re-training method of preparation and operation on ineffectively used equipment Re-training maintenance method on insufficient maintained equipment Training inspection and maintenance 			
	trouble shooting to identify problem		techniques with real broken equipment			

Targeted equipment

	Gulu RRH	Lira RRH	Arua RRH
CR system		0	0
Ventilator	0		
Anesthesia machine	0	0	0
Infusion pump	0		0
Syringe pump	0	0	
ECG	0		
Esophagoscope	0	0	0
Electric surgical unit	0		0
Patient Monitor	0	0	0

Curriculum(draft)

I. Training of Clinical Techniques

	Gulu l	RRH		
No.		Training Item	Form	Trainee
Day 1	AM	Confirmation of functions and roles of procured equipment	Lecture	Medical doctors and nurses (approx. 10
Day 1	PM	Confirmation of clerical knowledge concerning anaesthesia	Lecture	people)
	AM	Breath control method	Lecture	Ditto
Day 2	PM	Handling of ventilators and Confirm alarm activation condition and countermeasure method	Practical Training	Ditto
	AM	Infusion management method	Lecture	
Day 3	PM	Handling of syringe pump and infusion pump and Confirm alarm activation condition and countermeasure method	Practical Training	Ditto
Day 4	AM	Methods of general management and postoperative management of patients in severe condition	Lecture	Ditto
Day 4	PM	Handling of patient monitor/ECG and confirm alarm activation condition and countermeasure method	Practical Training	Ditto
	AM	Method of patient management during operation	Lecture	
Day 5	PM	Handling of anaesthesia machine, Electrical surgical unit, patient monitor, infusion pump and Esophagoscope during operation	Practical Training	Ditto
Day 6	AM	Question resolved,Summary	Lecture	Ditto
Day 6	PM	Confirmation of assignment documents and levelof settlement	Lecture	Ditto

(1) The first time (Just after hand over of equipment)

Lira RRH

No.		Training Item	Form	Trainee
	AM	Confirmation of functions and roles of procured equipment	Lecture	Medical doctors and nurses (approx. 10
Day 1	PM	Confirmation of clerical knowledge concerning anaesthesia	Lecture	people)
	AM	Infusion management method	Lecture	
Day 2	PM	Handling of syringe pump and infusion pump and Confirm alarm activation condition and countermeasure method	Practical Training	Ditto
Day 3	AM	Methods of general management and postoperative management of patients in severe condition	Lecture	Ditto
Day 5	PM	Handling of portable monitor and confirm alarm activation condition and countermeasure method	Practical Training	
	AM	Method of patient management during operation	Lecture	
Day 4	PM	Handling of anaesthesia machine, patient monitor and Syringe pump during operation	Practical Training	Ditto
Day 5	AM	Handling of Esophagoscope	Lecture	Ditta
Day 5	PM	Question resolved	Practical Training	Ditto
Day 6	AM	Summary	Lecture	Ditto
Day 0	PM	Confirmation of assignment documents and levelof settlement	Lecture	Ditto

Ar	ua RR	Н		
No.		Training Item	Form	Trainee
Day 1	AM	Confirmation of functions and roles of procured equipment	Lecture	Medical doctors and nurses (approx. 10
Day 1	PM	Confirmation of clerical knowledge concerning anaesthesia	Lecture	people)
	AM	Infusion management method	Lecture	
Day 2	PM	Handling of syringe pump and infusion pump and Confirm alarm activation condition and countermeasure method	Practical Training	Ditto
Day 3	AM	Methods of general management and postoperative management of patients in severe condition	Lecture	Ditto
Day 5	PM	Handling of portable monitor and enfirm alarm activation condition and countermeasure method	Practical Training	
	AM	Method of patient management during operation	Lecture	
Day 4	PM	Handling of anaesthesia machine, Electric knife, patient monitor, infusion pump and Esophagoscope during operation	Practical Training	Ditto
Day 5	AM	Handling of Esophagoscope	Lecture	Ditto
Day 5	PM	Question resolved	Practical Training	
Day 6	AM	Summary	Lecture	Ditto
Day 6	PM	Confirmation of assignment documents and levelof settlement	Lecture	

The target equipment differs in each RRH, but training for each RRH uniform 6 days is assumed. The reason is as follows. The level of the staff of each hospital and the experience of using the equipment are finely different. Also, the training executor can turn multiple hospitals efficiently and with the maximum number of days. (Monday to Saturday training, Sunday movement)

(2) The second time (six months after the hand over)

No.		Training Item	Form	Trainee
Day1	AM	Selection of target equipment and retraining of operation techniques	Practical Training	Medical doctors and nurses (approx. 10
Dayı	PM	Ditto	Practical Training	people)
Day2 AM		AM Ditto		Ditto
Day2	PM	Ditto	Practical Training	Ditto
Day 3	AM	Ditto	Practical Training	Ditto
Day 5	PM	Ditto	Practical Training	
Day 4	AM Summary		Practical Training	Ditto
Day 4	PM	Confirmation of assignment documents and levelof settlement	Practical Training	

No.		Training Item	Form	Trainee	
D 1	AM	Confirmation of outline of CR system and mechanism	Lecture	Doctors who read diagnostic images,	
Day 1	РМ	Method of digital data acquisition from CR plate CR	Practical Training	Diagnostic person in image department (about 20 people)	
Day 2	AM	Storing and managing digital image data	Lecture	Ditto	
Day 2	PM	Method of digital image data transfer	Practical Training	Ditto	
Day 2	AM	Method of data acquisition from server on client PC	Practical Training	Ditto	
Day 3	PM	Ditto	Practical Training		
Davi 4	AM	Image processing technology of image data	Practical Training	Ditto	
Day 4	PM	Ditto	Practical Training		
	AM	Periodic inspection, maintenance method	Practical Training	Doctors who interpret diagnostic images,	
Day 5	PM	Troubleshooting in case of breakdown	Practical Training	Diagnostic person in image department and Equipment maintenance engineer (about 25 people)	
Day 6	AM	Summary	Lecture	Ditto	
Day 6	РМ	Confirmation of assignment documents and levelof settlement	Practical Training		

II .Training of CR system (Just after hand over)

III. Training of Maintenance and Management Techiques (six months after the hand over)

No.		Training Item	Form	Trainee
Day1	AM	Selection of target equipment	Practical Training	Regional workshop technicians, user trainers
Dayı	PM	Training of operation methods	Practical Training	and nurses (approx. 10 people)
Dav2	AM	Ditto	Lecture Practical Training	Ditto
Day2	РМ	Ditto	Lecture Practical Training	Ditto
Day 3	AM	Ditto	Lecture Practical Training	Ditto
Day 5	РМ	Ditto	Lecture Practical Training	Ditto
Day 4	AM	Training of Equipment maintenance management	Lecture Practical Training	Ditto
Day	РМ	Ditto	Lecture Practical Training	Ditto
Day 5	AM	Training for equipment troubleshooting methods etc.	Lecture Practical Training	Ditto
Day 5	РМ	Ditto	Lecture Practical Training	
D	AM	Summary	Lecture	D'#
Day 6	PM	Confirmation of assignment documents and levelof settlement	Lecture	Ditto

Although targeted equipment items in training of maintenance and management techiques will be changed based on real situation of operation, maintenance and some other conditions on each hospital, the possible number of targeted equipment is around 40-50 in each RRH. The targeted equipment will be decided with acutual situation which heared via email before the training, especially the priority for training will give on equipment with following categories; 1. Critical problem occurred because of trouble on equipment, 2. Expensive equipment and 3. High frequency of use (approx. 10-20 items are targeted, although conditions and situations are different in each hospital). Especially equipment with category 1 give direct impact to patients 'life, therefore training will be repeated as much as possible within the term.

The period of dispatch for each training session is as bellow.

I. Training of Clinical Techniques

- Consultant for clinical technique : Ugandan doctor, 1 person

A total of 23days (6 for training x 3hospitals, 4 for domestic travel and 1 for report to MOH, JICA and Japanese embassy) x 1 time

A total of 19days (4 for training x 3hospitals, 4 for domestic travel and 1 for report) x 1 time

- Consultant for CR system : Japanese expert. 1 person

A total of 20 days (4 for international travel, 6 for training x 2hospitals (Lira and Arua), 3 for domestic travel and 1 for report) x1 time

- Consultant for operation and maintenance technique : Japanese expert, 1 person

A total 27 days (4 for international travel, 6 for training x 3hospitals, 4 for domestic travel and 1 for report) x 1 time

- Consultant for training planning : Japanese expert, 1 person

A total 27days (4 for international travel, 6 for training x 3hospitals, 4 for domestic travel and 1 for report) x 2 times

④ Post work in Japan

Summarize the result of technical training etc., and the Interim Report, Implementation Report and Completion Report created. The number of days required for the work in Japan shall be 2 days for the consultant for CR system and the consultant for operation and maintenance technique and 3days for consultant for training planning.

6. Method for Procuring Resources for the Implementation of Soft Component

For the implementation of soft component, "Training of clinical technique" will be done by a Ugandan doctor from the viewpoint of cost, language, local custom and sustainability of training after the completion. Doctors who have sufficient knowledge and skills related to clinical practice using targeted equipment, and work in higher referral hospital such as National Hospital, and also have experience of training lecturers on clinical techniques, are dispatched. The first training will be carried out just after the handover of equipment. The second training will be carried out after half of year since the hand over for equipment that target hospital requests to re-train, and the consultants check the degree of establishment and give training again on the equipment with luck of establishment.

"Training of CR system" basically dispatches a consultant who is qualified as a medical radiology technician in Japan and has sufficient experience in CR operation and implements technical training using the supplied CR system in the Project.

"Training of operation and maintenance technique" dispatches a Japanese consultant with general expertise to supplied equipment in the Project, confirms the degree of utilization of supplied equipment, and re-train the equipment that is deemed necessary for technical training again.

The "technical guidance plan" dispatches a Japanese consultant who grasps the soft components, the structure of Japanese grant aid, and the details of the equipment to be suppled, and has experience of coordination work. The consultant organize the technical training process, overall schedule, etc., as well as formulate a detailed implementation plan, in consultation with the executing agency such as Ministry

of Health, central workshop, target hospital, regional workshop etc.. After that, during each training implementation period, in cooperation with the hospital staff in charge, support the implementation of appropriate and efficient training such as participant count management, venue coordination, schedule management and so on. In order each expert to be able to concentrate on the training, the consultant do consideration / adjustment so that the participants can get the maximum technical skill.

7. Implementing Schedule of Soft Component

The implementation of the soft component will basically be started after the installation of supplied equipment. As mentioned above, training of clinical training will be conducted twice, including the first training (immediately after handover of equipment) and follow-up training (half year after the hand over). Training of CR system will be conducted once after handover of equipment. Training of operation maintenance and management techniques will be conducted about half a year after handover of equipment.

Estimated implementation schedule at this stage is as follows. The final implementation schedule will be determined after discussion with Ugandan related organization and Japanese experts.

	Schedule from E/N	1	2	3	 21	22	23	24	25	26	27	28	29	30	31	32	33
	Construction																
Imple menti ng	Equipment Procurement Gulu RRH LiraRRH Arua RRH																
Sched ule	Implementation of Soft Component Gulu RRH LiraRRH Arua RRH																
Dispa tch of exper ts	Consultant for clinical technique Consultant for CR system Consultant for operation and maintenance technique Consultant for training planning								••• •••					N			
Delivo	erable								P	∆ rogress	Report			C	ompletie	on Repo	rt

Overall Schedule

The place of implementation is Gulu RRH, Lira RRH, Arua RRH of this project.

8. Deliverable of Soft Component

Other than the completion report to the client and Japanese side, the following documents will be the deliverables of the soft components.

- ① Training materials: Lecture materials, maintenance management manual, maintenance checklist, etc.
- ② Repots: Training report by each consultant, summary of test results before and after training etc.


9. Responsibility of Implementing Agencies of Recipient Country

Persons concerned in the plan in the Infrastructure Division of MOH, the central workshop, targeted hospitals, regional workshops etc. are required to select trainees and ensure they will participate in the technical training, as well as coordinating the schedule of the technical training and providing the venues.

In addition, the responsible persons from the target hospital and the Infrastructure department of MOH participate in this training as necessary. In order to ensure proper operation and maintenance of supplied equipment for a long time, it is necessary to improve existing management system and continue similar trainings by Ugandan side. MOH and target hospitals are required to secure budget for maintaining operational structure with appropriate personnel, consumables and spare parts as responsibility.


Appendix 7 Excerpt of the investigation report of natural conditions


7-1 Gulu RRH (1) Topographic Map





CROSS SECTION OF GULU HOSPITAL





1	421894.9	307395.4	1111.073	BH-1
2	421920.6	307380.9	1110.654	BH-2
3	421903.4	307364.3	1110.151	BH-3

1	421896.9	307369.4	1109.961	EXC-1
2	421932.3	307384.2	1110.918	EXC2
3	421913.6	307361	1109.821	EXC-3

AES-YAEIC-GI-G-2017-01/ Rev-0

PREPARATORY SURVEY FOR THE PROJECT FOR IMPROVEMENT OF REGIONAL REFERRAL HOSPITALS IN NORTHERN UGANDA

GEOTECHNICAL INVESTIGATIONS AT GULU REGIONAL REFERRAL HOSPITAL

Client:

Yokogawa Architects & Engineers, Inc.& INTEM Consulting, Inc

Investigations Report



Contractor:

Associated Engineering Surveyors (AES)

March 2017


0	Technical Office	Orena	Akena	19/03/17	First Issue	Report
Rev	Established	Checked	Approved by	Date	Comments/ Amendments	STAT

2 FIELD INVESTIGATIONS AND LABORATORY TESTING

2.1 Field Activities

Field works were commenced on 20th of February 2017 and completed on 22nd of February 2017. Geotechnical investigation works were carried out in accordance with the specifications provided by the client; Yokogawa Architects & Engineers, Inc.& INTEM Consulting, Inc.

An investigations location layout is presented below: -



Yokogawa Architects & Engineers, Inc.& INTEM Consulting, Inc Associated Engineering Surveyors (AES)

- 6 -

3 BOREHOLE 1 LOG AND CORE PHOTOS

Borehole 1 was drilled from 0.0m at the surface down to 15m as instructed by the client.

3.1 BH -01 borehole log

Client: Yokogawa Architects & Engined & INTEM Consulting, Inc	Bo	orehole No.	BH - 01		
Project: Geotechnical Investigations a	Date	Start:	20 – Feb - 2017		
Regional Referral Hospital					
Location: Gulu Regional Referral Hosp	Location: Gulu Regional Referral Hospital			21 – Feb - 2017	
Equipment: GY-100		Co-ordir	nates: E 4218	94.896 N 3	07395.431
Ground elevation: 1111.073	• •		of Borehole	15.0m	
Description	Legend	Depth (m)	SPT (N)	SPT Depth Range (m)	Undisturbed Sample
Brown red silty clay soils. Stiff.		0			
Locally contains quartz fragments.		1			
Moderately stiff		2	47	1.0 - 1.45	(1.45m – 1.75m)
		3	19	2.75 – 3.2	
		4	-		(3.2m – 3.5m)
			10		
		5	16	4.5 – 4.95	(4.95m – 5.25m)
		6	12	6.25 – 6.7	
		7			(6.7m – 7.0m)
		8	13	8.0 - 8.45	
		9	15	8.0 - 8.45	(8.45m – 8.75m)
		10	10	9.75 – 10.2	
		11			
		12	18	11.2 – 11.65	
		13	15	12.65 – 13.1	
		14	-	-	(13.1m – 13.4m) -
Brown gray gravel soils		15		_	_

4 BOREHOLE 2 LOG AND CORE PHOTOS

Borehole 2 was drilled from 0.0m at the surface down to 15m as instructed by the client.

4.1 BH -02 borehole log

Client: Yokogawa Architects & Engineers, Inc. & INTEM Consulting, Inc			Borehole No.	BH - 02	
Project: Geotechnical Investigations at Gulu			Start:	21 – Feb - 2017	
Regional Referral Hospital					
Location: Gulu Regional Referral Hospital			Finish:	22 – Feb - 2017	
Equipment: GY-50			inates: E 4219	920.551 N 3	07380.866
Ground elevation: 1110.654		· · ·	h of Borehole	15.0m	÷
Description	Legend	Depth (m)	SPT	SPT Depth	Undisturbed
		(m)	(N)	Range (m)	Sample
Brown red silty clay soils. Stiff.		0			
Locally contains quartz fragments.		1			
Moderately stiff. Becomes sandy at 12.5m to 15m			53	1.0 - 1.45	
at 12.5m to 15m		2			(1.45m – 1.75m)
		3	56	2.75 – 3.2	
					(3.2m – 3.5m)
		4			
		5	40	4.5 – 4.95	
		6			
			20	5.95 – 6.4	
		7			(6.4m – 6.7m)
		8	40	7.7 – 8.15	
		9			
			34	9.15 – 9.6	
		10			
		11	23	10.6 - 11.05	
		12			
			17	12.05 – 12.5	
		13			
		14	>50 (Refusal)	13.5 – 13.95	
					(13.95m – 14.25m)
		15			

5 BOREHOLE 3 LOG AND CORE PHOTOS

Borehole 3 was drilled from 0.0m at the surface down to 15m as instructed by the client.

5.1 BH -03 borehole log

Client: Yokogawa Architects & Engineers, Inc. & INTEM Consulting, Inc		E	Borehole No.	BH - 03	
Project: Geotechnical Investigations at Gulu		Date	Start:	20 – Feb - 2017	
Regional Referral Hospital					
Location: Gulu Regional Referral Hospital			Finish:	21 – Feb - 2017	
Equipment: GY-50			inates: E 421		7364.31
Ground elevation: 1110.151			h of Borehole	15.0m	1
Description	Legend	Depth (m)	SPT (N)	SPT Depth Range (m)	Undisturbed Sample
Brown red silty clay soils. Stiff		0			
with some gravel		1			
			>50 (Refusal)	1.0 - 1.45	
		2			(1.45m – 1.75m)
		3	>50 (Refusal)	2.75 – 3.2	
		4			(3.2m – 3.5m)
		5	41	4.5 – 4.95	
	1	6			(4.95m – 5.25m)
		7	17	6.25 – 6.7	
	1	8	25	7.7 – 8.15	
		9			
		10	22	9.15 – 9.6	
	1	11			
		12		-	
		13	17	12.05 – 12.5	
Clayey sand, brown gray in color		14			
		15	48	14.0 – 14.45	

AES-YAEIC-UOI-G-2017-01/ Rev-0

PREPARATORY SURVEY FOR THE PROJECT FOR IMPROVEMENT OF REGIONAL REFERRAL HOSPITALS IN NORTHERN UGANDA

UNDERGROUND OBSTACLES INVESTIGATIONS AT GULU REGIONAL REFERRAL HOSPITAL

Client:

Yokogawa Architects & Engineers, Inc.& INTEM Consulting, Inc

Investigations Report



Contractor:

Associated Engineering Surveyors (AES)

March 2017


0	Technical Office	Orena	Akena	08/03/17	First Issue	Report
Rev	Established	Checked	Approved by	Date	Comments/ Amendments	STAT

2 FIELD INVESTIGATIONS AND LABORATORY TESTING

2.1 Field Activities

Field works were commenced on 22nd of February 2017 and completed on 23rd February 2017. Underground obstacles investigation works were carried out in accordance with the specifications provided by the client; Yokogawa Architects & Engineers, Inc.& INTEM Consulting, Inc.


An investigations location layout is presented below: -



Yokogawa Architects & Engineers, Inc.& INTEM Consulting, Inc Associated Engineering Surveyors (AES)

3 PIT/ TRENCH 1 UNDERGROUND OBSTACLES

Excavations at pit/ trench 1 revealed no underground obstacles down to a depth of 2.0m as shown in the profile below: -





4 PIT/ TRENCH 2 UNDERGROUND OBSTACLES

Excavations at pit/ trench 1 revealed no underground obstacles down to a depth of 2.0m as shown in the profile below: -

Co-ordinates: E 421932.3 N 307384.2 Z 1110.9		
Picture EXC-02	depth (m)	description
	0.0 - 0.3	Brown lateritic clay soil. Moderately compacted
	0.3 - 0.6	Brown red clay soils. Slightly compacted
	0.6 – 2.0	Brown lateritic (murram) soils. Very hard to excavate by hand



5 PIT/ TRENCH 3 UNDERGROUND OBSTACLES

Excavations at pit/ trench 3 revealed no underground obstacles down to a depth of 2.0m as shown in the profile below: -

Co-ordinates: E 421913.6 N 307361.0 Z 1109.8		
Picture EXC-03	depth (m)	description
	0.0 - 1.0	Gray brown silty clay soil. Moderately compacted
	1.0 - 2.0	Brown lateritic (murram) soils. Hard to excavate by hand



(4) Water Quality Certificate Analysis

CLIENT: Yokogawa Architect & Engineers

Address: Kampala

Tel:



NATIONAL WATER AND SEWERAGE CORPORATION CENTRAL LABORATORY - BUGOLOBI. P.O.BOX 7053 KAMPALA. E-mail: waterquality@nwsc.co.ug CERTIFICATE OF ANALYSIS

Email: Date Sample Received: 06-March-2017		Sample Source: Gulu Date of Report: 21-March-2017				
Fable of Analytical Results Parameters	Units	Gulu	National standards for Potable water			
WS Sample Nr		K1087/17/C/B				
pH		6.3	6.5-8.5			
Electrical Conductivity (EC)	μS/cm	227	2500			
Total Dissolved Solids (TDS)	mg/L	145.3	1200			
Total Suspended Solids (TSS)	mg/L	0	. 0			
Ammonia-N	mg/L	0.01	. 1.0			
Turbidity	NTU	0.45	10.0			
Alkalinity: Total as CaCO3	mg/L	32	500			
Bicarbonate	mg/L	39	500			
Hardness: Total	mg/L	66	500			
Arsenic	μg/L	<0.004	0.010			
Manganese	mg/L	0.0	0.1			
Chloride- Cl	mg/L	0	500			
Aluminium Residual	mg/L	0	0.2			
Nitrate-N	mg/L	0.0	5.0			
Iron:Total	mg/L	0.050	1.0			
Fluoride	mg/L	0.0	1.5			
Calcium: as Ca ²⁺	mg/L	12.8	75			
Magnessium: as Mg ²⁺	mg/L	17.6	50			
Colour (apparent)	PtCo	0	15			
Sulphate: SO42-	mg/L	0	200			
Odur		-	Not Specified			
Taste			Not Specified			
Potassium: K	mg/L	1.96	100			
Sodium: Na	mg/L	3.17	400			
Bact: Ecoli	CFU/100mL	0	0			
Bact: Faecal Coliforms	CFU/100mL	0	0			
Bact:Total Coliforms	CFU/100mL	0	10			

Remarks:

The sample showed complying physiochemical and bacteriological characteristics with the exception of pH as compared to the National 6 standards for Potable water.

ANALYSED BY Robinah Muheirwe and Keneddy Araa

......MANAGER, Central Laboratory Services AUTHORISED BY:


APPROVED BY:

Ref No:LS098/INV/2017/265 Sampled by: Client Type of container: Plastic Sample Source: Gulu


P.o. Box 7053 Kampala, Uganda. SENIORMANAGER, Water Quality Management Department +2566313315111/715 Email:external.se REF. NO. D SIGN: VALSE

7-2 Lira RRH

(1) Topographic Map



1	1 489146.1 249253.9	249253.9	1088.241 EXC-1	(C-1
2	489114.3	249267.7	1084 EXC-2	(C-2
C	489105	249282.6	1084.21 EXC-3	(C-3
4	488958.8	249238.9	1088.31 EXC-4	(C-4
1	1 488963.8 249237.4	249237.4	1088.29 BH-1	H-1
2	489105	249282.6	1084.2 BH-2	H-2
£	489096.9	249300.2	1084.196 BH-3	H-3
4	4 488963.8 249237.4	249237.4	1088.29 BH-4	H-4



+

CRDSS SECTIONS OF LIRA HOSPITAL

Sec 2-2

AES-YAEIC-GI-L-2017-01/ Rev-0

PREPARATORY SURVEY FOR THE PROJECT FOR IMPROVEMENT OF REGIONAL REFERRAL HOSPITALS IN NORTHERN UGANDA

GEOTECHNICAL INVESTIGATIONS AT LIRA REGIONAL REFERRAL HOSPITAL

Client:

Yokogawa Architects & Engineers, Inc.& INTEM Consulting, Inc



Contractor:

Associated Engineering Surveyors (AES)

March 2017


0	Technical Office	Orena	Akena	19/03/17	First Issue	Report
Rev	Established	Checked	Approved by	Date	Comments/ Amendments	STAT

2 FIELD INVESTIGATIONS AND LABORATORY TESTING

2.1 Field Activities

Field works were commenced on 24th of February 2017 and completed on 26th February 2017. Geotechnical investigation works were carried out in accordance with the specifications provided by the client; Yokogawa Architects & Engineers, Inc.& INTEM Consulting, Inc.

An investigations location layout is presented below: -



Yokogawa Architects & Engineers, Inc.& INTEM Consulting, Inc Associated Engineering Surveyors (AES)

3 BOREHOLE 1 LOG AND CORE PHOTOS

Borehole 1 was drilled from 0.0m at the surface down to 15m as instructed by the client.

3.1 BH -01 borehole log

Client: Yokogawa Architects & Engine	ers, Inc.	E	Borehole No.	BH - 01	
& INTEM Consulting, Inc Project: Geotechnical Investigations at Lira			Start:	24 – Feb - 201	
Regional Referral Hospital			Start		
Location: Lira Regional Referral Hospi	ital	-	Finish:	25 – Feb - 201	7
Equipment: GY-50		Co-ord	inates: E 488	963.8 N	249237.4
Ground elevation: 1088.3		Dept	h of Borehole	15.0m	
Description	Legend	Depth (m)	SPT (N)	SPT Depth Range (m)	Undisturbed Sample
Brown loamy clay soil		0			
		1			
Red brown lateritic clay soils, stiff		2	34	1.0 - 1.45	(1.45m – 1.75m)
		3	17	2.75 – 3.2	
		4			(3.2m – 3.5m)
		5	20	4.5 – 4.95	
		6			(4.95m – 5.25m)
Red brown to orange clay soil, moderate stiff		7	26	5.95 – 6.4	
		8	15	7.4 – 7.85	-
		9	-	-	-
Gray silty clays with mica, very stiff		10	40	5.95 – 6.4	(9.3m – 9.6m)
		11	>50 (Refusal)	10.4 – 10.85	
		12	_	-	-
		13	>50 (Refusal) -	11.85 – 12.3 -	-
		14	>50 (Refusal) -	13.3 – 13.75 -	-
		15	_	-	-

4 BOREHOLE 2 LOG AND CORE PHOTOS

Borehole 2 was drilled from 0.0m at the surface down to 15m as instructed by the client.

4.1 BH -02 borehole log

Client: Yokogawa Architects & Engineers, Inc. & INTEM Consulting, Inc			Borehole No.	BH - 02	2
Project: Geotechnical Investigations at Lira Regional Referral Hospital			Start:	25 – Feb - 20	17
Location: Lira Regional Referral Hospi	tal		Finish:	26 – Feb - 20	17
Equipment: GY-100			inates: E 489	105.0	N 249282.6
Ground elevation: 1084.2	-		h of Borehole	15.0m	
Description	Legend	Depth (m)	SPT (N)	SPT Depth Range (m)	Undisturbed Sample
Brown clay soil		0			
	-	1			
		2	10	1.0 – 1.45	(1.45m – 1.75m)
		3	>50 (Refusal)	2.75 – 3.2	
Red brown lateritic clay. Very stiff		4			(impenetrable)
		5			
Weathered rock corestone		6			
		7			
Clayey sand. dense		8	-	-	-
		9	-	-	-
		10	-	-	-
		11	-	-	-
		12	-	-	-
		13	-	-	-
		14	-	-	-
		15	-	-	-

5 BOREHOLE 3 LOG AND CORE PHOTOS

Borehole 3 was drilled from 0.0m at the surface down to 15m as instructed by the client.

5.1 BH -03 borehole log

Client: Yokogawa Architects & Engine & INTEM Consulting, Inc	E	Borehole No.	BH - 03	}	
Project: Geotechnical Investigations at Lira Regional Referral Hospital			Start:	24 – Feb - 201	7
Location: Lira Regional Referral Hospi	tal		Finish:	25 – Feb - 201	7
Equipment: GY-100		Co-ord	inates: E 489	096.9 N	249300.2
Ground elevation: 1084.2		Dept	h of Borehole	15.0m	
Description	Legend	Depth (m)	SPT (N)	SPT Depth Range (m)	Undisturbed Sample
Brown clay, very firm		0			
		1			-
		2	>50 (Refusal)	1.0 - 1.45	(1.45m – 1.75m)
Brown sandy clay. Very stiff between 3m and 5m. becomes		3	>50 (Refusal)	2.75 – 3.2	
red brown and softer between 5m and 10m		4			
		5			
		6	18	5.6 – 6.05	-
		7			(6.05m – 6.35m)
		8	14	7.35 – 7.8	-
		9			-
		10	14	8.8 – 9.25	
Gray clayey sands with mica. stiff		11	24	10.25 – 10.7	(10.7m – 11.0m)
		12			
		13	>50 (Refusal) -	12.0 – 12.45 -	-
		14	-	-	-
		15	-	-	-

6 BOREHOLE 4 LOG AND CORE PHOTOS

Borehole 4 was drilled from 0.0m at the surface down to 15m as instructed by the client.

6.1 BH -04 borehole log

Client: Yokogawa Architects & Engine & INTEM Consulting, Inc	ers, Inc.	E	Borehole No.	BH - 04		
Project: Geotechnical Investigations a Regional Referral Hospital	Date	Start:	25 – Feb - 201	7		
Location: Lira Regional Referral Hospi	ital	-	Finish:	26 – Feb - 201	.7	
Equipment: GY-50		Co-ord	inates: E 488	963.8 N	249237.4	
Ground elevation: 1088.3	_	Dept	h of Borehole	15.0m		
Description	Legend	Depth (m)	SPT (N)	SPT Depth Range (m)	Undisturbed Sample	
Red brown lateritic clay		0 1			-	
		2	>50 (Refusal)	1.0 - 1.45	(impenetrable)	
		3				
		4	17	3.0 – 3.45	(3.45m – 3.75m)	
		5	26	4.5 – 4.95	-	
		6			-	
Gray brown silty sands, dense, with mica		7	35	6.2 – 6.65	(6.65m – 6.95m)	
		8				
		9	35	7.95 – 8.4		
		10	41	9.4 – 9.85		
		11				
		12	32	7.95 – 8.4	(impenetrable)	
		13	41	12.6 - 13.05		
		14				
		15	48	14.05 – 14.5		

AES-YAEIC-UOI-L-2017-01/ Rev-0

PREPARATORY SURVEY FOR THE PROJECT FOR IMPROVEMENT OF REGIONAL REFERRAL HOSPITALS IN NORTHERN UGANDA

UNDERGROUND OBSTACLES INVESTIGATIONS AT LIRA REGIONAL REFERRAL HOSPITAL

Client:

Yokogawa Architects & Engineers, Inc.& INTEM Consulting, Inc



Contractor:

Associated Engineering Surveyors (AES)

March 2017


0	Technical Office	Orena	Akena	08/03/17	First Issue	Report
Rev	Established	Checked	Approved by	Date	Comments/ Amendments	STAT

2 FIELD INVESTIGATIONS AND LABORATORY TESTING

2.1 Field Activities

Field works were commenced on 24th of February 2017 and completed on 26th February 2017. Underground obstacles investigation works were carried out in accordance with the specifications provided by the client; Yokogawa Architects & Engineers, Inc.& INTEM Consulting, Inc.

An investigations location layout is presented below: -



Yokogawa Architects & Engineers, Inc.& INTEM Consulting, Inc Associated Engineering Surveyors (AES)

3 PIT/ TRENCH 1 UNDERGROUND OBSTACLES

Excavations at pit/ trench 1 revealed no underground obstacles down to a depth of 2.0m as shown in the profile below: -

Co-ordinates: E 489146.1 N 249253.9 Z 1088.2		
Picture EXC-01	depth (m)	description
	0.0 – 0.8	Brown loamy soils, very firm
	0.8 - 1.4	Red brown silty sand. firm
28/02/2017 09:09	1.4 – 2.0	Red brown sandy silt. Moderately compacted



4 PIT/ TRENCH 2 UNDERGROUND OBSTACLES

Excavations at pit/ trench 1 revealed no underground obstacles down to a depth of 2.0m as shown in the profile below: -

Co-ordinates: 489114.3 N 249267.7 Z 1084.0		
Picture EXC-02	depth (m)	description
	0.0-0.1	Gray brown loamy soils
	0.1 – 1.2	Red brown lateritic soils, hard to excavate
	1.2 – 2.0	Red Brown sandy silts. Moderately compacted
26/02/2017 17-07		



5 PIT/ TRENCH 3 UNDERGROUND OBSTACLES

Excavations at pit/ trench 3 revealed no underground obstacles down to a depth of 2.0m as shown in the profile below: -

Co-ordinates: E 489105.0 N 249282.6 Z 1084.2		
Picture EXC-03	depth (m)	description
	0.0 - 0.7	brown loamy soil
	0.7 – 1.65	Dark brown silty clay soils. Very firm
26/02/2017 11:52	1.65 – 2.0	Red brown sandy silts, firm



6 PIT/ TRENCH 4 UNDERGROUND OBSTACLES

Excavations at pit/ trench 4 revealed no underground obstacles down to a depth of 1.0m as shown in the profile below: -

Co-ordinates: E 488958.8 N 249238.9 Z 1088.3 Picture EXC-04	depth (m)	description
Text Tkiaki Prok sikarruna Looktiosi site Prove Dife Isiozioni	0.0-0.2	Gray brown silty clay soil with root growth
	0.2 - 1.0	Red brown lateritic soils with duricrust. Hard to excavate by hand
25/02/2017	16:24	







(4) Water Quality Certificate of Analysis

NATIONAL WATER AND SEWERAGE CORPORATION CENTRAL LABORATORY - BUGOLOBI

P.O.BOX 7053 KAMPALA.

E-mail: waterquality@nwsc.co.ug CERTIFICATE OF ANALYSIS

mail: Pate Sample Received: 06-March-2017		Sample Source: Lira Date of Report: 21-March-2017				
able of Analytical Results Parameters	Units	Lira	National standards for Potable water			
WS Sample Nr		K1088/17/C/B				
pH	-	7.2	6.5-8.5			
Electrical Conductivity (EC)	μS/cm	220	2500			
Total Dissolved Solids (TDS)	ng/L	140.8	1200			
Total Suspended Solids (TSS)	mg/L	0	0			
Ammonia-N	mg/L	0.03	1.0			
Turbidity	NTU	0.9	10.0			
Alkalinity: Total as CaCO3	mg/L	128	500			
Bicarbonate	mg/L	156.2	500			
Hardness: Total	mg/L	104	500			
Arsenic	µg/L	<0.004	0.010			
Manganese	mg/L	0.01	0.1			
Chloride- Cl ⁻	mg/L	0	500			
Aluminium Residual	mg/L	0.0	0.2			
Nitrate-N	mg/L	0.01	5.0			
Iron:Total	ng/L	0.007	1.0			
Fluoride	ng/L	0.0	1.5			
Calcium: as Ca ²⁺	ng/L	19.2	75			
Magnessium: as Mg ²⁺	ng/L	23.0	50			
Colour (apparent)	PtCo	21	15			
Sulphate: SO42-	ng/L	4	200			
Odur			Not Specified			
Taste			Not Specified			
Potassium: K	ng/L	6.9	100			
Sodium: Na	ng/L	17.1	400			
Bact: Ecoli	CFU/100mL	0	0			
Bact: Faecal Coliforms	CFU/100mL	0	0			
Bact:Total Coliforms	CFU/100mL	3	10			

CLIENT: Yokogawa Architect & Engineers Address: Kampala Tel:

Ref No:LS098/INV/2017/265 Sampled by: Client Type of container: Plastic

Remarks:

The sample showed complying physiochemical and bacteriological characteristics with the exception of colour as compared to the National ERAG standards for Potable water. 81 0

ANALYSED BY Robinah Muheirwe and Keneddy Araa

......MANAGER, Central Laboratory Services AUTHORISED BY:

ES APPROVED BY: ________SENIORMANAGER, Water Quality Management Department x 7053 Kampala, Uganda Tel:+2566313:315111 / 715 Email:external.services@ WSC.CO.UC REF. NO.: 2017 8 SIGN: DATE ERNAL SE



NATIONAL WATER AND SEWERAGE CORPORATION QUALITY CONTROL DEPARTMENT BACTERIOLOGICAL SAMPLE RECEPTION AND ANALYSIS RESULTS FORM

Date and time sampled	Date and time received	Lab No	Sample description	pH	Colour (P1Co)	 Contraction of the second secon	Free Ci2 mg/f	Total chlorine(mg/l)	CFU counts/100 mis	Romarks
	12/672017, 4 25 24		Raw water		86	9	N/A	N/A	20	R
		167	Final water		14	<5	0.75	0.95	0	FT
	-	168	Agwata Booster		14	<5	0.7	0.98	0	B
		189	Adwila Gravity Tank		14	<5	0.35	0.65	0	D
		170	Ireda Res		16	<5	0.4	0.85	0	D
		171	UTC Lira	1000	15	<5	0.35	0.5	0	D
-	10.00	172	Akia	1000	15	<5	0.25	0.45	0	D
		173	Obulo welo		15	<5	0.19	0.45	0	0
		174	Aduku Road		14	<5	0.25	0.45	0	D
		175	Ireda Chamber		13	<5	02	0.45	0	D
		176	Juba Road	1000	34	<5	02	0.42	0	D
		nives		1		1.000	1.1			
				1				1	A	1



NATIONAL WATER AND SEWERAGE CORPORATION QUALITY CONTROL DEPARTMENT BACTERIOLOGICAL SAMPLE RECEPTION AND ANALYSIS RESULTS FORM

	Date and time received	Lab No	Sample description	рH	Colour (PtCo)		Free Ci2 mg/l	Total chlorine(mg/l)	CFU counts/100 mils	Remarks
	19/0/2017, 3:05 PM		Raw water	8	80	12	N/A	N/A	18	R
indizo III	- and the second second	178	Final water	7.5	14	<5	0.7	0.9	D	FT
		179	Agwata Booster	7.5	14	<5	0.6	0.88	0	8
		180	Adwila Gravity Tank	75		<5	0.35	0.58	0	0
		181	liceda Rea	7.5	16	<5	0.5	0.85	0	9
		182	Milcan Quarters	75		<5	0.35	0.55	0	
		183	Kakogo PSP	75	15	<5	0.15	0.3	0	1 3
	10 C 10 C 11 C	184	UTC Lira	75	16	<5	0.19	03	0	D
		185	Ngeta Ginnery	7.5	34	<5	0,18	0.35	0	D
		186	Anai Okii	7.5		<5	0.2	0.45	0	D
		187	Akwoyo	7.5	14	<5	D.22	0.45	0	D
			the second second							



NATIONAL WATER AND SEWERAGE CORPORATION · QUALITY CONTROL DEPARTMENT BACTERIOLOGICAL SAMPLE RECEPTION AND ANALYSIS RESULTS FORM

	Date and time received	Lab No	Sample description	pH	Colour (PiCo)	Turbidit y (FTU)	Free Cl2 mg/i	Total chlorine(mg/l)	CFU counts/100 mis	Remarks
		188	Raw.water	8	85	12	N/A	N/A	22	R
		189	Final water	7.8	16	<5	0.8	0.9	0	FT
		190	Agwata Booster	7.6	14	<5	0.6	0.85	0	B
1		192	Adwila Gravity Tank	7.6	15	<5	0.3	0.55	0	D
the second second		193	Ireda Res.	7.5	15	<5	0.6	0.8	0	0
		194	Kakoge CDC	7.6	1 15	<5	0.3	0.55	0	1 1)
		195	Socoli Road	78		<5	0,35	0.45	0	0
		196	Royal Academy SS	7.5	14	<5	D.25	0.45	0	D
nin reis		197	VH Primary School	7.5		<5	0.25	0.45	0	D.
1000 - 1000 - 1000 - 1000 - 1000 - 1000 - 1000 - 1000 - 1000 - 1000 - 1000 - 1000 - 1000 - 1000 - 1000 - 1000 -	State of the local division of the local div	198	Anal Ober.	7.5	16	45	0.19	0.4	0	0
		199	Akwoyo	7.5	15	<5	0.18	0.4		10000



NATIONAL WATER AND SEWERAGE CORPORATION QUALITY CONTROL DEPARTMENT BACTERIOLOGICAL SAMPLE RECEPTION AND ANALYSIS RESULTS FORM

Date and D time sampled ti	Date and Ime received	Lab No	Sample description	pH	(PiCo)	Turbidlt y (FTU)	Free Cl2 mg/l	Total chlorine(mg/l)	counts/100 mis	Remarks
31/1/2017. 11	5/5/17; 4:05 PM	133	Raw water		70	10	N/A	N/A	22	Ř
and an		134	Final water		14	<5	0.7	0.95	Q	FT
	1000	135	Agwata Booster		15	<5	0.55	0.8	0	В
	1000	136	Adwila Gravity Tank		15	<5	0.35	0.65	0	D
	100	137	Ireda Res.	1	13	<5	0.45	0.6	0	D
		138	Kirombe North		14	<5	0.25	0.45	0	D
		139	Kakoge CDC	-	13	<5	0.25	0.46	0	D
		140	African Quarters		13	<5	0.3	0.6	0	D
		141	Anai	1.1	15	<5	0,25	0.65	0	D
		142	UTC Lira		15	<1	0.2	0.4	0	D
		143	Ngella Ginnery		14	<5	0.25	0.45	Û	D



NATIONAL WATER AND SEWERAGE CORPORATION QUALITY CONTROL DEPARTMENT BACTERIOLOGICAL SAMPLE RECEPTION AND ANALYSIS RESULTS FORM

Date and time sampled	Date and time received	Lab No	Sample description	рН	Colour (PtCo)	Turbidit y (FTU)	Free Cl2 mg/l	Total chlorine(mg/l)	CFU counts/100 mls	Remarks
1/2/0017	25/5/17, 6.09 PM	144	Row water	8	85	12	N/A	N/A	22	R
		145	Final water	7.5	16	<5	0.8	0.9	0	EL
		1/6	Agwata Booster	7.5	- 14	<5	0.6	0.85	0	B
(A.M. 1997) 2010	ALC: NO. OF THE	147	Auwila Gravity Tank	7.6	15	<5	0.3	0.55	0	D
이 사실 등 등 등 등	2	148	lireoa Res	7.8	15	<5	D.G	0.8	0	D
		149	Kakoge CDC	7.6	12	1	0.3	0.55	0	U
		150	Sproti Road	73	15	<5	0.35	0 45	0	1
total and allow		151	Royal Academy SS	7.5	16	<5	0.25	0.45	0	D-
		152	Whi Primary School	75	14	1	0.25	0.45	0	0
_		153	Anai Ober	78	16	<1	0.19	0.4	0	D
The second second		154	Akwoyo	7.5	- 15	e	0.18	0.4		- Colore



NATIONAL WATER AND SEWERAGE CORPORATION QUALITY CONTROL DEPARTMENT


	BACTERIOLOGICAL	SAMPLE RECE	110N AND ANALYS	SIS RESULIS FORM
--	-----------------	-------------	-----------------	------------------

	Date and time received	Lab No	Sample description	рН	Colour (PtCo)	110000000000	Free Cl2 mg/l	Total chlorine(mg/l)	CFU counts/100 mls	Remarks
	5/6/2017 5.05 PM		Raw water		57	7	N/A	N/A	20	R
	1919 - 1919 V	156	Final water	1.	14	<5	0.7	0.92	0	ET.
		157	Agwata Booster		13	<5	0.5	0.8	0	8
		158	Adwila Gravity Tank		12	<5	0.35	0.65	0	D
	1000	159	Ireda Res	-	12	<5	0.6	0.8	0	D
		160	Kachung Junior Sch	1.2	13	<5	0.5	075	C	D
		161	Presidential Lodge		15	<5	0.2	0.45	0	0
		162	Ambalal P. Sch.		10	<5	0.3	0.45	0	D_
		163	Ayago P. Scn.		14	<6	0.25	04	0	D
		164	Odokomit Ginnery		:3	<5	0.25	0.45	0	D
		165	Ipwo Akere						1	
		-		1				15 July 10 20		
			1 march and the state	-	U			1		1

3 8 2


7-3 Arua RRH

(1) Topographic Map



999.261 BH1	1000.288 BH2	1000.707 BH3	999.5 EXC-1	1000.124 EXC-2	1000.815 EXC-3
666	1000	1000	6	1000	1000
334396.8	334365.4	334342	334395	334368.6	334340.3
267852.2	267807.8	267836.3	267854.4	267806.5	267838.4

HOSPITAL ARUA ЧО SECTION CROSS



AES-YAEIC-GI-A-2017-01/ Rev-0

PREPARATORY SURVEY FOR THE PROJECT FOR IMPROVEMENT OF REGIONAL REFERRAL HOSPITALS IN NORTHERN UGANDA

GEOTECHNICAL INVESTIGATIONS AT ARUA REGIONAL REFERRAL HOSPITAL

Client:

Yokogawa Architects & Engineers, Inc.& INTEM Consulting, Inc

Investigations Report



Contractor:

Associated Engineering Surveyors (AES)

March 2017


0	Technical Office	Orena	Akena	19/03/17	First Issue	Report
Rev	Established	Checked	Approved by	Date	Comments/ Amendments	STAT

2 FIELD INVESTIGATIONS AND LABORATORY TESTING

2.1 Field Activities

Field works were commenced on 17th of February 2017 and completed on 19th February 2017. Geotechnical investigation works were carried out in accordance with the specifications provided by the client; Yokogawa Architects & Engineers, Inc.& INTEM Consulting, Inc.

An investigations location layout is presented below: -



The field works comprised of mainly the following activities: -

- Boring to 15m depth
- Standard Penetration Test (SPT)
- Undisturbed sampling

3 BOREHOLE 1 LOG AND CORE PHOTOS

Borehole 1 was drilled from 0.0m at the surface down to 15m as instructed by the client.

3.1 BH -01 borehole log

Client: Yokogawa Architects & Engine & INTEM Consulting, Inc	ers, Inc.	В	orehole No.	BH - 01				
Project: Geotechnical Investigations a	t Arua	Date	Start:	18 – Feb - 20	17			
Regional Referral Hospital								
Location: Arua Regional Referral Hosp	oital		Finish: 18 – Feb - 2017					
Equipment: GY-100	Co-ordi	nates: E 2678	852.2 , N 3343	96.8				
Ground elevation: 999.261		Depth	of Borehole	15.0m				
Description	Legend	Depth	SPT	SPT Depth Undisturbed				
		(m)	(N)	Range (m)	Sample			
Gray silty clay becoming sandy		0						
clay with depth		1						
			17	1.0 – 1.45				
Red brown clay, somewhat		2			(1.45m – 1.75m)			
lateritic. Becomes sandy at 4.5m		3	13	2.75 – 3.2				
to 5.0m		3	15	2.75 - 5.2	(3.2m – 3.5m)			
		4			(3.2111 – 3.3111)			
		5	25	4.5 – 4.95				
Gray silty sands, with some quartz					(4.95m – 5.25m)			
particles		6						
		_						
		7	-	-	-			
		8	-	-	-			
Highly weathered to moderate		9	-	_	_			
weathered gneissic rock. Highly								
foliated and fractured. Becomes		10	-	-	-			
strong to very strong with depth	a state	11	-	-	-			
	-	12	-	-	-			
		13	-	-	-			
		14	-	-	-			
	and the second	15	-	-	-			

4 BOREHOLE 2 LOG AND CORE PHOTOS

Borehole 2 was drilled from 0.0m at the surface down to 15m as instructed by the client.

4.1 BH -02 borehole log

Client: Yokogawa Architects & Engine & INTEM Consulting, Inc	ers, Inc.	E	Borehole No.	BH - 02	2		
Project: Geotechnical Investigations a Regional Referral Hospital	nt Arua	Date	Start:	17 – Feb - 20	17		
Location: Arua Regional Referral Hos	oital		Finish: 17 – Feb - 2017				
Equipment: GY-100	Equipment: GY-100			807.8 N	334365.4		
Ground elevation: 1000.288		h of Borehole	15.0m				
Description	Legend	Depth (m)	SPT (N)	SPT Depth Range (m)	Undisturbed Sample		
Gray silty clay		0					
Red brown sandy clay with some		1					
loose gravel		2	18	1.0 – 1.45	(1.45m – 1.75m)		
		3	29	2.75 – 3.2			
Coarse gray brown sand		4			(3.2m – 3.5m)		
		5	>50 (Refusal)	4.5 – 4.95			
Gray silty sand. Dense sands		6			(4.95m – 5.25m)		
		7	>50 (Refusal)	7.0 – 7.45			
		8	-	-	-		
		9	-	-	-		
		10	-	-	-		
		11	-	-	-		
		12	-	-	-		
		13	-	-	-		
		14	-	-	-		
		15	-	-	-		

5 BOREHOLE 3 LOG AND CORE PHOTOS

Borehole 3 was drilled from 0.0m at the surface down to 15m as instructed by the client.

5.1 BH -03 borehole log

Client: Yokogawa Architects & Engine & INTEM Consulting, Inc	ers, Inc.	E	Borehole No.	BH - 03	3			
Project: Geotechnical Investigations a	it Arua	Date	Start:	17 – Feb - 20	17			
Regional Referral Hospital								
	Location: Arua Regional Referral Hospital			Finish: 17 – Feb - 2017				
Equipment: GY-50		inates: E 2678		334342				
Ground elevation: 1000.707	1	h of Borehole	15.0m					
Description	Legend	Depth (m)	SPT (N)	SPT Depth Range (m)	Undisturbed Sample			
Gray brown clay, somewhat		0			•			
lateritic		1			-			
		2	14	1.0 – 1.45	(1.45m – 1.75m)			
		3	28	2.75 – 3.2	(2.2m, 2.5m)			
		4			(3.2m – 3.5m)			
Gray brown sands, very dense		5	37	4.5 – 4.95	-			
		6	40	5.95 – 6.4	-			
		7			-			
		8	44	7.4 – 7.85	-			
		9			-			
		10	>50 (Refusal)	9.0 – 9.45	-			
		11	-	-	-			
		12	-	-	-			
		13	-	-	-			
		14	-	-	-			
		15	-	-	-			



UNDERGROUND OBSTACLES INVESTIGATIONS AT ARUA REGIONAL REFERRAL HOSPITAL

Client:

Yokogawa Architects & Engineers, Inc.& INTEM Consulting, Ltd.

Investigations Report (ARUA)



Contractor:

Associated Engineering Surveyors (AES)

March 2017


0	Technical Office	Orena	Akena	08/03/17	First Issue	Report
Rev	Established	Checked	Approved by	Date	Comments/ Amendments	STAT

2 FIELD INVESTIGATIONS AND LABORATORY TESTING

2.1 Field Activities

Field works were commenced on 18th of February 2017 and completed on 19th February 2017. Underground obstacles investigation works were carried out in accordance with the specifications provided by the client; Yokogawa Architects & Engineers, Inc.& INTEM Consulting, Inc.

An investigations location layout is presented below: -



The field works comprised of mainly the following activities: -

- Excavation by hand of 3 pits/ trenches of 1.5 meters x 1.5 meters and 2 meters deep
- Collecting both disturbed and undisturbed samples for laboratory analysis

The table below lists the co-ordinate locations of the excavated pits/ trenches. Co-ordinates are in Arc 1960 UTM system: -

3 PIT/ TRENCH 1 UNDERGROUND OBSTACLES

Excavations at pit/ trench 1 revealed no underground obstacles down to a depth of 2.0m as shown in the profile below: -

Co-ordinates: E 267854.4, N 334395, Z 999.5		
Picture EXC-01	depth (m)	description
A State of the second	0.0 - 0.3	Gray loamy soils with fragments of quartz rock
	0.3 – 2.0	Gray brown silty clay soils

Site Pictures



4 PIT/ TRENCH 2 UNDERGROUND OBSTACLES

Excavations at pit/ trench 2 revealed no underground obstacles down to a depth of 1.5m as shown in the profile below: -

Co-ordinates: EXC-02 E 267806.5, N 334368.6, Z 1000.124]	
Picture EXC-02	depth (m)	description
Control of	0.0 - 1.0	Gray brown silty clay soils, moderately compacted
	0.3 - 1.5	Brown lateritic soils that are very hard to excavate with pick axe

Site Pictures



5 PIT/ TRENCH 3 UNDERGROUND OBSTACLES

Excavations at pit/ trench 3 revealed no underground obstacles down to a depth of 2.0m as shown in the profile below: -

Co-ordinates: EXC-03 E 267838.4 N 334340.3 Z 1000.815		
Picture EXC-03	depth (m)	description
	0.0 – 0.5	Gray brown silty clay soils, lateritic, very hard to excavate manually. Quartzite rock fragments at 2.0m, mixed with laterite

Site Pictures



(4) Water Quality Certificate of Analysis



NATIONAL WATER AND SEWERAGE CORPORATION

CENTRAL LABORATORY - BUGOLOBI. P.O.BOX 7053 KAMPALA.

E-mail: waterquality@nwsc.co.ug

CLIENT: Yokogawa Architect & Engineers Address: Kampala Tel: Email: Date Sample Received: 06-March-2017 Table of Analytical Results

Ref No:LS098/INV/2017/265 Sampled by: Client Type of container: Plastic Sample Source: Arua Date of Report: 21-March-2017

P.o. Box 7053 Kampala, Uganda

Tel:+2566313315111 / 715

REF. NO.

SIGN De

Z

Parameters	Units	Arua	National standards for Potable water
WS Sample Nr	Carlo Carlo Carlos	K1089/17/C/B	
pH	-	7.3	6.5-8.5
Electrical Conductivity (EC)	μS/cm	167.8	2500
Total Dissolved Solids (TDS)	mg/L	107.4	1200
Total Suspended Solids (TSS)	mg/L	4	0
Ammonia-N	mg/L	0.02	1.0
Turbidity	NTU	9.8	10.0
Alkalinity: Total as CaCO ₃	mg/L	84	500
Bicarbonate	mg/L'	102.5	500
Hardness: Total	mg/L	76	500
Arsenic	µg/L	<0.004	0.010
Manganese	mg/L	0.06	0.1
Chloride- Cl	mg/L	33	500
Aluminium Residual	mg/L	0.0	0.2
Nitrate-N	mg/L	0.02	5.0
Iron:Total	mg/L	0.32	1.0
Fluoride	mg/L	0.0	1.5
Calcium: as Ca ²⁺	mg/L	16	75
Magnessium: as Mg ²⁺	mg/L	21.8	50
Colour (apparent)	PtCo	88	15
Sulphate: SO42	mg/L	13	200
Odur			Not Specified
Taste			Not Specified
Potassium: K	mg/L	3.4	100
Sodium: Na	mg/L	8.9	400
Bact: Ecoli	CFU/100mL	0	0
Bact: Faecal Coliforms	CFU/100mL	0	0
Bact: Total Coliforms	CFU/100mL	2	10

Remarks:

The sample showed complying physiochemical and bacteriological characteristics with the exception of Colour and TSS as compared to the National standards for Potable water. ANALYSED BY Robinah Muleirwe and Keneddy Araa

AUTHORISED BY:MANAGER, Central Laboratory Services

SENIORMANAGER, Water Quality Management Departmen Email:external.sen **APPROVED BY:**

January, 2017 NWSC-ARUA

Parameter builtUnitMaterworksMater in supplyMater in supplyNational Standards for Standards for 						Monite	Monitoring points			×
Tatalities Final water Final water Reservoir water Wworks Ediofe Filling Rock filling Muni rading Oli T.C les $N953$ N954 N955 N956 N957 N958 N959 les \dots 6.78 6.52 6.95 6.74 6.13 5.96 μ \dots 5.78 6.52 6.95 6.74 6.13 5.96 μ μ 266 268 264 144 188 151 150 bidity NTU 3.77 2.58 6.62 1.82 2.52 1.9 1.77 our PCo_0 10 6 7 9 11 10 8 n mg/L 0.152 0.168 0.157 0.265 0.154 n mg/L 0.162 0.157 0.265 0.154 n mg/L 0.168 0.162 0.157 <		1114		Waterworks			Water in	ypply i		National
les N953 N954 N955 N956 N957 N958 N959 i 6.78 6.52 6.95 6.74 6.13 5.96 bidity 1 6.78 6.52 6.95 6.14 6.13 5.96 bidity 1 266 268 264 144 188 151 150 bidity NTU 3.77 2.58 6.62 1.82 2.52 1.9 1.77 our $PtCo$ 10 6 7 9 11 10 8 our mg/L 0.154 0.162 0.154 0.157 0.265 0.154 or mg/L 0.168 0.154 0.162 0.157 0.265 0.154 or mg/L 0.168 0.162 0.162 0.157 0.265 0.154 or mg/L 0.160 0.162 0.152 <t< th=""><th>r an amerer</th><th></th><th>Final water</th><th>Reservoir</th><th>W.works PSP</th><th>Ediofe T.C</th><th>Rock filling Station</th><th>Muni Trading Centre</th><th>Oli T.C</th><th>Standards for potable water quality (water</th></t<>	r an amerer		Final water	Reservoir	W.works PSP	Ediofe T.C	Rock filling Station	Muni Trading Centre	Oli T.C	Standards for potable water quality (water
6.78 6.52 6.95 6.74 6.13 5.96 bidity $\mu s' cm$ 266 268 264 144 188 151 150 bidity NTU 3.77 2.58 6.62 1.82 2.52 1.9 1.77 our PtCo) 10 6 7 9 11 10 8 nmg/L 0.152 0.168 0.154 0.157 0.265 0.154 1.77 simity mg/L 0.152 0.168 0.162 0.157 0.265 0.154 of mg/L 0.162 0.162 0.157 0.265 0.154 of mg/L 0.70 0.70 0.70 0.76 0.76 of mg/L 70 70 70 70 70 70 of mg/L 1.5 1.6 70 70 70 70 <	Codes		N953	N954	N955	N956	N957	N958	059N	In supply)
$ \begin{array}{llllllllllllllllllllllllllllllllllll$	pH	:	6.78	6.52	6.95	6.74	6.78	6.13	5.96	6.5-8.5
idityNTU 3.77 2.58 6.62 1.82 2.52 1.9 1.77 urPtCo)1067911108mg/L 0.152 0.168 0.154 0.157 0.265 0.154 mg/L 0.0 000000mg/L 64 60 66 70 58 62 68 nessmg/L 70 72 72 68 70 70 70 ninum Residuemg/L 1.5 1 0.3 0.4 0.4 0.4 0.4 ninum Residuemg/L 1.5 1 0.3 0.4 0.4 0.4 0.4 ninum Residuemg/L 1.5 1 0.3 0.4 0.4 0.4 0.4 ninum Residuemg/L 1.5 1 0.3 0.4 0.4 0.4 0.4	EC	µs/cm	266	268	264	144	188	151	150	1500
urPtCo)1067911108mg/L 0.152 0.168 0.154 0.162 0.157 0.265 0.154 mg/L 0 0 0 0 0 0 0 0 linitymg/L 64 60 66 70 58 62 68 nessmg/L 70 72 72 68 70 70 70 nessmg/L 1.5 1.5 $1.$ 0.3 0.4 0.4 0.4 obsidemg/L 1.5 $1.$ 0.3 0.4 0.4 0.4 obsidemg/L 1.5 $1.$ 0.3 0.4 0.4 0.4 of m/L 0.3 0.4 0.3 0.4 0.4 0.4 of m/L $0.$ 0 0 0 0 0 0	Turbidity	NTU	3.77	2.58	6.62	1.82	2.52	6.1	1.77	5
$ \begin{array}{l l l l l l l l l l l l l l l l l l l $	Colour	PtCo)	10	9	7	6	Ш	10	8	15
$ \begin{array}{ c c c c c c c c c c c c c c c c c c c$	Iron	mg/L	0.152	0.168	0.154	0.162	0.157	0.265	0.154	0.300
$ \begin{array}{ c c c c c c c c c c c c c c c c c c c$	TSS	mg/L	0	0	0	0	0	0	0	0
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	Alkalinity	mg/L	64	60	66	70	58	62	68	500
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	Hardness	mg/L	70	72	72	68	70	70	70	300
mg/L 1.5 1 0.3 0.4 0.3 0.4 0.4 CFU/100 0 0 0 0 0 0 0 0 0	Aluminium Residue	mg/L	0.2	NR	NR	NR	NR	NR	NR	0.2
CFU/100 0 0 0 0 0 0 mL 0<	Free chlorine	mg/L	1.5	1	0.3	0.4	0.3	0.4	0.4	0.20-0.50
	E-Coli	CFU/ 100 mL	0	0	0	0	0	0	0	0

Kemarks

All the water samples from different points showed complying physiochemical and bacteriological characteristics compared to the National standards for potable water.

Manager, Central Laboratory Services 8: Dr. Mohammed Babu ... Approved by:

February, 2017 NWSC-ARUA

					Monite	Monitoring points			
		Water	Waterworks		W:	Water in Supply	ly		
Parameter	Unit	Final water	Reservoir	Arua P.S	Ediofe T.C	Godown Road	Oli Health Centre	Androa Road PSP	National Standards for potable water
Lab No.		N171	N172	N173	N174	N175	N176	N177	quanty (water in supply)
Codes		WWFT4	DR5	DSP3	DCP6	DSP5	DCP7	DSP2	
pH	:	7.04	7.13	7.17	7.25	7.22	7.27	7.28	6.5-8.5
EC	μs/cm	628	613	567	530	530	426	450	1500
Colour	PtCo.	9	5	4	7	8	6	8	15
Turbidity	NTU	2.79	1.71	1.61	1.06	1.36	1.94	1.42	S
Iron: Total	mg/L	0.187	0.345	0.288	0.142	0.134	0.222	0.211	0.300
TSS	mg/L	0	0	0	0	0	0	0	0
Alkalinity	mg/L	128	188	170	172	174	180	178	500
Hardness	mg/L	156	172	140	164	116	150	160	300
Aluminium Residue	mg/L	0.025	N/R	N/R	N/R	N/R	N/R	N/R	0.2
Free chlorine	mg/L	1.2	-	0.4	0.5	0.3	0.4	0.5	0.20-0.50
E-Coli	CFU/100 mL	0	0	0	0	0	0	0	0

Remarks

All the water samples from different points showed complying physiochemical and bacteriological characteristics compared to the National standards for potable water.

1 Approved by:

Dr. Mohammed Babu.

Manager, Central Laboratory Services

VIOLENDER I SHOPPITUN

6. ...

					Monito	Monitoring points	~		
	:	Water	Waterworks		Wa	Water in Supply	ply		
Parameter	Cuit	Final water	Reservoir	Oli H/C	Ediofe T.C	Arua P.S	Muni T.C	Androa Road PSP	National Standards for potable water quality (water
Lab No.		N397	N398	N399	N400	N401	N402	N403	in supply)
Codes		WWFT4	DR5	DSP7	DCP6	DSP3	DVP1	DSP2	
pH	:	7.08	7.05	7.21	7.08	7.12	7.17	7.1	6.5 - 8.5
EC	μs/cm	533	520	484	546	532	559	536	1500
Colour	PtCo.	3	5	0	8	-	13	15	15
Turbidity	NTU	2.43	2.24	1.68	1.64	1.96	4.32	4.07	5
Iron: Total	mg/L	0.272	0.283	ND	ND	ND	ND	ND	0.300
TSS	mg/L	0	0	0	0	0	0	1	0
Alkalinity	mg/L	72	100	110	06	72	72	80	500
Hardness	mg/L	88	100	84	92	88	110	88	300
Aluminium Residue	mg/L	0.058	N/R	N/R	N/R	N/R	N/R	N/R	0.2
Free chlorine	mg/L	0.4	0.4	0.3	0.3	0.2	0.2	0.2	0.20-0.50
E-Coli	CFU/100 mL	0	0	0	0	0	0	0	0

ALLA DAVA TINC N.

Remarks

All the water samples from different points showed complying physiochemical and bacteriological characteristics with exception of sample N403 which showed slightly higher TSS as compared to the National standards for potable water.

Approved by:

Dr. Mohammed Babu..

Manager, Central Laboratory Services