





















DRAINAGE SYSTEM PLAN AND OUTLETS (LEFT RIVER BANK)

S= 1:2000





LEGEND

-  FLOW OF SCHEDULED CULVERT
-  FLOW OF SCHEDULED SIDE DITCH
-  FLOW OF EXISTING DRAINAGE
-  CATCHMENT AREA



<small>PROJECT NAME</small> DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	<small>FINANCED BY</small>  JAPAN INTERNATIONAL COOPERATION AGENCY	<small>COUNTERPART</small>  REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	<small>JICA STUDY TEAM</small>  NIPPON KOEI CO., LTD.  ORIENTAL CONSULTANTS GLOBAL CO., LTD.  METROPOLITAN EXPRESSWAY COMPANY LIMITED  CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 10%;"></th> <th style="width: 20%;">NAME</th> <th style="width: 20%;">SIGNATURE</th> <th style="width: 10%;">DATE</th> </tr> </thead> <tbody> <tr> <td>PREPARED BY</td> <td>EMYORITA</td> <td></td> <td>15 Jun. 2017</td> </tr> <tr> <td>CHECKED BY</td> <td>T. HAYAKAWA</td> <td></td> <td>20 Jun. 2017</td> </tr> <tr> <td>APPROVED BY</td> <td>Y. SANO</td> <td></td> <td>21 Jun. 2017</td> </tr> </tbody> </table>		NAME	SIGNATURE	DATE	PREPARED BY	EMYORITA		15 Jun. 2017	CHECKED BY	T. HAYAKAWA		20 Jun. 2017	APPROVED BY	Y. SANO		21 Jun. 2017	<small>DRAWING TITLE</small> DRAINAGE SYSTEM PLANS (LEFT RIVER BANK) S= 1:2000	<small>PACKAGE</small> 1 DWG No. P1-RD-3000
	NAME	SIGNATURE	DATE																			
PREPARED BY	EMYORITA		15 Jun. 2017																			
CHECKED BY	T. HAYAKAWA		20 Jun. 2017																			
APPROVED BY	Y. SANO		21 Jun. 2017																			

DRAINAGE SYSTEM PLAN (1) S= 1:1000





<small>PROJECT NAME</small> DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	<small>FINANCED BY</small> JAPAN INTERNATIONAL COOPERATION AGENCY	<small>COUNTERPART</small> REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	<small>JICA STUDY TEAM</small> NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO. LTD. NIPPON ENGINEERING CONSULTANTS CO.,LTD.	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: left;">NAME</th> <th style="text-align: left;">SIGNATURE</th> <th style="text-align: left;">DATE</th> </tr> <tr> <td>PREPARED BY</td> <td>M. TORIU</td> <td>15 Jun. 2017</td> </tr> <tr> <td>CHECKED BY</td> <td>T. HAYAKAWA</td> <td>20 Jun. 2017</td> </tr> <tr> <td>APPROVED BY</td> <td>Y. SANO</td> <td>21 Jun. 2017</td> </tr> </table>	NAME	SIGNATURE	DATE	PREPARED BY	M. TORIU	15 Jun. 2017	CHECKED BY	T. HAYAKAWA	20 Jun. 2017	APPROVED BY	Y. SANO	21 Jun. 2017	<small>DRAWING TITLE</small> DRAINAGE SYSTEM PLAN(1) S=1:1000	<small>PACKAGE</small> 1 DWG No. P1-RD-3010
NAME	SIGNATURE	DATE																
PREPARED BY	M. TORIU	15 Jun. 2017																
CHECKED BY	T. HAYAKAWA	20 Jun. 2017																
APPROVED BY	Y. SANO	21 Jun. 2017																

DRAINAGE SYSTEM PLAN (2) S= 1:1000




PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE DRAINAGE SYSTEM PLAN(2) S=1:1000	PACKAGE	
				PREPARED BY	M. TORIU			15 Jun. 2017	1
				CHECKED BY	T. HAYAKAWA			20 Jun. 2017	DWG No.
				APPROVED BY	Y. SANO			21 Jun. 2017	P1-RD-3011

DRAINAGE SYSTEM PLAN (3) S= 1:1000




DETAIL OF BOX CULVERT (1) BAR ARRANGEMENT OF BOX CULVERT S=1:50


GENERAL DRAWING S=1:50




ERECTION DIAGRAM OF MAIN REINFORCEMENT




TOP SLAB



SECTION S=1:50



BOTTOM SLAB




DESIGN CRITERIA

INSIDE DIMENSION		WIDTH	1.00 m
		HEIGHT	1.00 m
LIVE LOAD		T-TYPE LIVE LOAD	
UNIT WEIGHT	REINFORCED CONCRETE	24.5 kN/m ³	
	SOIL	18 kN/m ³	
CONCRETE DESIGN STRENGTH		24 N/mm ²	
ALLOWABLE STRESS			
COMPRESSIVE STRESS DUE TO BENDING		8 N/mm ²	
SHEARING STRESS		0.39 N/mm ²	
TENSILE STRESS (SD345)		160 N/mm ²	
COEFFICIENT OF EARTH PRESSURE		0.5	
IMPACT COEFFICIENT		-	
SEISMIC COEFFICIENT		-	
ANGLE OF SKEW		90°00'00"	
RADIUS OF CURVATURE		R=∞	
GRADIENT OF BOX CULVERT		i=0.500%	

(PER 1m)

MARK	No.	SEC.	EACH	LENGTH (mm)	L 1 (mm)	L 2 (mm)	L 3 (mm)	L 4 (mm)	H (mm)	R (mm)
S 1	4	D13	4	3080	600	220	1120	920		140
S 2	1	D13	4	1400	1400					
S 3	1	D13	16	1000	1000					
S 4	5	D13	8	1040	195	649			459	
S 5	3	D13	3	980		126				
W 1	1	D13	8	1390	1390					
W 2	1	D13	20	1000	1000					
W 3	2	D13	12	360		152				
F 1	4	D13	4	3080	600	220	1120	920		140
F 2	1	D13	4	1400	1400					
F 3	1	D13	16	1000	1000					
F 4	5	D13	8	650	195	255			180	
F 5	3	D13	3	940		106				

SIDE SLAB



LIST OF REINFORCEMENT

(PER 1m)

MARK	SEC.	LENGTH (mm)	EACH	WEIGHT (kg/m)	WEIGHT/one (kg)	WEIGHT (kg)	REMARKS
S 1	D13	3080	4	0.995	3.065	12.260	
S 2	D13	1400	4	0.995	1.393	5.572	
S 3	D13	1000	16	0.995	0.995	15.920	
S 4	D13	1040	8	0.995	1.035	8.280	
S 5	D13	980	3	0.995	0.975	2.925	
W 1	D13	1390	8	0.995	1.383	11.064	
W 2	D13	1000	20	0.995	0.995	19.900	
W 3	D13	360	12	0.995	0.358	4.296	
F 1	D13	3080	4	0.995	3.065	12.260	
F 2	D13	1400	4	0.995	1.393	5.572	
F 3	D13	1000	16	0.995	0.995	15.920	
F 4	D13	650	8	0.995	0.647	5.176	
F 5	D13	940	3	0.995	0.935	2.805	

MATERIALS



(PER 1m)

ITEM	UNIT	QUANTITY
CONCRETE (DII)	TOP	m ³ 0.480
	SIDE	m ³ 0.640
	BOTTOM	m ³ 0.480
	TOTAL	m ³ 1.600
FORM	m ²	5.966
REINFORCING BAR	D19	kg 0
	D16	kg 0
	D13	kg 121.950
	TOTAL	kg 121.950
LEVELING CONCRETE (EI) t=100	m ²	0.180
FOUNDATION t=200	m ²	0.360


D	a (mm)	b (mm)	c (mm)	R (mm)	L (mm)
D13	66	164	230	42	410
D16	75	195	270	48	500
D19	94	236	330	60	600
D22	104	266	370	66	690
D25	122	308	430	78	790
D29	141	349	490	90	910
D32	151	389	540	96	1000

Note1: Size of Box Culvert and Bar Arrangement are based on Standard Drawing of Ministry of Land, Infrastructure, Transport and Tourism of Japan
 Note2: Specification of Steel Reinforcement Bar shall comply with SD345 (JIS G3112) or equivalent



DETAIL OF BOX CULVERT (2) FOR ROAD ACCESS




DETAIL OF REINFORCEMENT REINFORCING ROD



CATCH PIT (700X700X1850)





SECTION




COVER

CATCH PIT (700X700X2250)





SECTION




COVER

CATCH PIT (1200X1200X1600)



SECTION





COVER

Note: 1. Concrete Class DII
2. Leveling Concrete Class EI
3. Steel Reinforcement SD345

PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME M. TORIU	SIGNATURE 	DATE 15 Jun. 2017	DRAWING TITLE DETAIL OF BOX CULVERT (2) FOR ROAD ACCESS	PACKAGE 1 DWG No. P1-RD-3021
				PREPARED BY M. TORIU	CHECKED BY T. HAYAKAWA	APPROVED BY Y. SANO		
				DATE 20 Jun. 2017	DATE 21 Jun. 2017			


GENERAL VIEW OF BOX CULVERT

SIDE ELEVATION S = 1:150




KEY PLAN S=1:2000

PLAN S = 1:150




GENERAL DRAWING S=1:50



PROJECT NAME	FINANCED BY	COUNTERPART	JICA STUDY TEAM	NAME	SIGNATURE	DATE	DRAWING TITLE	PACKAGE
DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	JICA JAPAN INTERNATIONAL COOPERATION AGENCY	REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	M. TORIU	<i>[Signature]</i>	15 Jun. 2017	GENERAL VIEW OF BOX CULVERT	1
				T. HAYAKAWA	<i>[Signature]</i>	20 Jun. 2017		DWG No.
				Y. SANO	<i>[Signature]</i>	21 Jun. 2017		P1-RD-3030

DETAIL OF CONCRETE PIPE CULVERT 300 (CON 360°) TYPE B S= 1:15




WORK QUANTITIES PER UNIT (PER 10m)

ITEM	UNIT	QUANTITY	REMARKS
R.C.PIPE 300	m	10.000	JIS A 5303 CLASS 1
CONCRETE (DII)	m ³	2.118	28 days = 240 kg/cm ²
MORTAR	m ²	0.264	
FORM	m ²	11.200	

WORK QUANTITIES PER UNIT FOR REINFORCEMENT BAR (PER 1.0m)

Dia	Nos	Length (mm/nos)	Unit Weight (kg/m)	Weight (kg)	Remarks
D13	6	1,000	0.995	5.970	Ⓡ1 / SD345
D13	5	420	0.995	2.090	Ⓡ2 / SD345
D13	5	1,310	0.995	6.517	Ⓡ3 / SD345
TOTAL				14.557	

DETAIL OF STEEL REINFORCEMENT




Note: Precast R.C. Pipe 300 Reinforced Spun and Centrifugal Reinforced Concrete Pipes shall be Selected.

DETAIL OF CONCRETE PIPE CULVERT 900 (CON.360°) S= 1:30

CONCRETE PIPE CULVERT
900 (CON.360°)

A - A



PLAN

SECTION A - A

SECTION B - B

WORK QUANTITIES PER UNIT (PER 10m)

ITEM	UNIT	QUANTITY	REMARKS
R.C.PIPE 900	m	10.000	JIS A 5303 CLASS 1
CONCRETE (DII)	m ³	12.657	28 days = 240 kg/cm ²
FOUNDATION	m ²	16.600	GRAVEL / t=200mm
FORM	m ²	29.200	
LEVELLING CONCRETE (EI)	m ³	1.660	t=100

WORK QUANTITIES PER UNIT FOR REINFORCEMENT BAR (PER 1.0m)


Dia	Nos	Length (mm/nos)	Unit Weight (kg/m)	Weight (kg)	Remarks
D13	10	3,110	0.995	30.945	Ⓜ2 / SD345
D16	28	1,000	1.560	43.680	Ⓜ1 / SD345
TOTAL				74.625	

Note: Precast R.C. Pipe 900 Reinforced Span and Centrifugal Reinforced Concrete Pipes shall be Selected.


PROJECT NAME	FINANCED BY	COUNTERPART	JICA STUDY TEAM	NAME	SIGNATURE	DATE	DRAWING TITLE	PACKAGE
DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	JICA JAPAN INTERNATIONAL COOPERATION AGENCY	REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	PREPARED BY M. TORIU	<i>M. Toriu</i>	15 Jun. 2017	DETAIL OF CONCRETE PIPE CULVERT 900 (CON.360°) S=1:30	1
				CHECKED BY T. HAYAKAWA	<i>T. Hayakawa</i>	20 Jun. 2017		DWG No.
				APPROVED BY Y. SANO	<i>Y. Sano</i>	21 Jun. 2017		P1-RD-3041

GENERAL VIEW OF R.C. PIPE CULVERT (1)


PC-A1-N-01 - STA.0+025.900 (CON.360°)




PLAN
PC-A1-N-01



SECTION A-A




PC-A1-N-01
KEY PLAN




SECTION C-C (OUTLET) S = 1:50

SECTION B-B (INLET) S = 1:50



RCP CROSS SECTION S = 1:50









DETAIL OF R.C. PIPE S=1:50

PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th style="width: 15%;">NAME</th> <th style="width: 15%;">SIGNATURE</th> <th style="width: 15%;">DATE</th> </tr> <tr> <td>PREPARED BY M. TORIU</td> <td></td> <td>15 Jun. 2017</td> </tr> <tr> <td>CHECKED BY T. HAYAKAWA</td> <td></td> <td>20 Jun. 2017</td> </tr> <tr> <td>APPROVED BY Y. SANO</td> <td></td> <td>21 Jun. 2017</td> </tr> </table>	NAME	SIGNATURE	DATE	PREPARED BY M. TORIU		15 Jun. 2017	CHECKED BY T. HAYAKAWA		20 Jun. 2017	APPROVED BY Y. SANO		21 Jun. 2017	DRAWING TITLE GENERAL VIEW OF R.C. PIPE CULVERT (1)	PACKAGE 1 DWG No. P1-RD-3050
NAME	SIGNATURE	DATE																
PREPARED BY M. TORIU		15 Jun. 2017																
CHECKED BY T. HAYAKAWA		20 Jun. 2017																
APPROVED BY Y. SANO		21 Jun. 2017																

GENERAL VIEW OF R.C. PIPE CULVERT (2)

PC-A1-N-02 - STA.0+062.100 (CON.360°)



PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th style="width: 10%;">NAME</th> <th style="width: 10%;">SIGNATURE</th> <th style="width: 10%;">DATE</th> </tr> <tr> <td>PREPARED BY</td> <td>M. TORII</td> <td>15 Jun. 2017</td> </tr> <tr> <td>CHECKED BY</td> <td>T. HAYAKAWA</td> <td>20 Jun. 2017</td> </tr> <tr> <td>APPROVED BY</td> <td>Y. SANO</td> <td>21 Jun. 2017</td> </tr> </table>	NAME	SIGNATURE	DATE	PREPARED BY	M. TORII	15 Jun. 2017	CHECKED BY	T. HAYAKAWA	20 Jun. 2017	APPROVED BY	Y. SANO	21 Jun. 2017	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th style="width: 100%;">DRAWING TITLE</th> <th style="width: 100%;">PACKAGE</th> </tr> <tr> <td style="text-align: center;">GENERAL VIEW OF R.C. PIPE CULVERT (2)</td> <td style="text-align: center;">1</td> </tr> <tr> <td></td> <td style="text-align: center;">DWG No.</td> </tr> <tr> <td></td> <td style="text-align: center;">P1-RD-3051</td> </tr> </table>	DRAWING TITLE	PACKAGE	GENERAL VIEW OF R.C. PIPE CULVERT (2)	1		DWG No.		P1-RD-3051
NAME	SIGNATURE	DATE																							
PREPARED BY	M. TORII	15 Jun. 2017																							
CHECKED BY	T. HAYAKAWA	20 Jun. 2017																							
APPROVED BY	Y. SANO	21 Jun. 2017																							
DRAWING TITLE	PACKAGE																								
GENERAL VIEW OF R.C. PIPE CULVERT (2)	1																								
	DWG No.																								
	P1-RD-3051																								


DETAIL OF SIDE DITCH (1)

S=1:50


NOTES:

1. Concrete Class DII
(240kg/cm³)
2. Steel Reinforcement
SD345
3. Pit of Steel Reinforcement
is 200mm


SIDE DITCH TYPE U-300×300




SIDE DITCH TYPE U-500×500




SIDE DITCH TYPE U-800×800



SIDE DITCH TYPE U-1000×1000



SIDE DITCH TYPE U-1500×1500




PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE DETAIL OF SIDE DITCH (1) S=1:50	PACKAGE	
				PREPARED BY	M. TORIU			15 Jun. 2017	1
				CHECKED BY	T. HAYAKAWA			20 Jun. 2017	DWG No.
				APPROVED BY	Y. SANO			21 Jun. 2017	P1-RD-3060

DETAIL OF SIDE DITCH (2)


S=1:50

- NOTES:
1. Concrete Class DII (240 kg/cm²)
 2. Steel Reinforcement SD345
 3. Pit of Steel Reinforcement is 200mm


SIDE DITCH TYPE U-500×500 WITH COVER




SIDE DITCH TYPE U-500×850 WITH COVER




SIDE DITCH TYPE U-800×800 WITH COVER




SIDE DITCH TYPE U-800×1000 WITH COVER




SIDE DITCH TYPE U-1500×2500 WITH COVER




SIDE DITCH TYPE U-1000×1000 WITH COVER




SIDE DITCH TYPE U-1000×1500 WITH COVER



SIDE DITCH TYPE U-1500×1500 WITH COVER



INVERT CONCRETE (U-800×1000) S=1:50




PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE DETAIL OF SIDE DITCH (2) S=1:50, 1:500	PACKAGE 1 DWG No. P1-RD-3061	
				PREPARED BY	M. TORIU				15 Jun. 2017
				CHECKED BY	T. HAYAKAWA				20 Jun. 2017
				APPROVED BY	Y. SANO				21 Jun. 2017


DETAIL OF SIDE DITCH (3)

S=1:20

CONCRETE COVER
SIDE DITCH TYPE U-500×500 WITH COVER




CONCRETE COVER
SIDE DITCH TYPE U-800×800 WITH COVER
SIDE DITCH TYPE U-800×1000 WITH COVER




NOTES:

1. Concrete Class DII (240kg/cm³)
2. Steel Reinforcement SD345
3. Pit of Steel Reinforcement is 200mm


CONCRETE COVER
SIDE DITCH TYPE U-1000×1000 WITH COVER
SIDE DITCH TYPE U-1000×1500 WITH COVER



CONCRETE COVER
SIDE DITCH TYPE U-1500×1700 WITH COVER




CONCRETE COVER
SIDE DITCH TYPE U-1500×2500 WITH COVER




PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE DETAIL OF SIDE DITCH (3) S=1:20	PACKAGE 1 DWG No. P1-RD-3062	
				PREPARED BY	M. TORIU				15 Jun. 2017
				CHECKED BY	T. HAYAKAWA				20 Jun. 2017
				APPROVED BY	Y. SANO				21 Jun. 2017

DETAIL OF CATCH PIT (1)


DETAIL OF CATCH PIT (C-DITCH) TYPE A S=1:40



DETAIL OF CATCH PIT (C-DITCH) TYPE C S=1:40



DETAIL OF CATCH PIT (C-DITCH) TYPE D S=1:40




SCHEDULE OF CATCH PIT & VERTICAL DRAIN


PACKAGE	ROAD	SIDE	STATION	CATCH PIT (C-DITCH)				VERTICAL DRAIN TYPE A	VERTICAL DRAIN TYPE B		
				TYPE A	TYPE B	TYPE C	TYPE D				
				Nos.	Nos.	Nos.	Nos.				
1	MAIN	LEFT	325.000	1	-	1	-	1	-		
			305.000	1	-	-	-	-	-		
			285.000	1	-	1	-	1	-		
			270.000	1	-	-	-	-	-		
			260.000	1	-	1	-	1	-		
		TOTAL		5	-	3	-	3	-		
2	MAIN	LEFT	2413.416	1	-	-	-	-	-		
			2428.416	1	-	1	-	1	-		
			2438.416	1	-	-	-	-	-		
			2448.416	1	-	1	-	1	-		
			2453.416	1	-	-	-	-	-		
			2458.416	1	-	1	-	1	-		
			2463.416	1	-	-	-	-	-		
			2468.416	1	-	1	-	1	-		
			2473.416	1	-	-	-	-	-		
			2478.416	1	-	1	-	1	-		
			2483.416	1	-	-	-	-	-		
			2488.416	1	-	1	-	1	-		
			2505.500	-	-	1	1	1	-		
			2518.741	1	-	1	-	1	-		
		2523.741	1	-	-	-	-	-			
		2528.741	1	-	1	-	1	-			
		2533.741	1	-	-	-	-	-			
		2538.741	1	-	1	-	1	-			
		2543.741	1	-	-	-	-	-			
		2548.741	1	-	1	-	1	-			
		2553.741	1	-	-	-	-	-			
		2558.741	1	-	1	-	1	-			
		2568.741	1	-	-	-	-	-			
		2578.741	1	-	1	-	1	-			
		2588.741	1	-	-	-	-	-			
				RIGHT	2505.500	-	-	-	1	-	1
		FLYOVER	LEFT		2601.400	-	2	1	-	1	-
					2628.741	1	-	-	-	-	-
RIGHT			2601.400	-	2	-	-	-	1		
			2628.741	1	-	-	-	-	-		
ON-RAMP	LEFT		2645.000	1	-	-	-	-	-		
			2675.000	1	-	-	-	-	-		
			2705.000	1	-	1	-	1	-		
			2730.000	1	-	1	-	1	-		
			2745.000	1	-	-	-	-	-		
	2755.000	1	-	1	-	1	-				
		TOTAL		32	4	17	2	17	2		

DETAIL OF CATCH PIT (2)


CATCH PIT (700X700X1050) S = 1:40



PLAN




SECTION




COVER


CATCH PIT (1000X1000X1350) S = 1:40



PLAN




SECTION




COVER


CATCH PIT (1200X1200X1600) S = 1:40



PLAN



SECTION



COVER

NOTES:



1. Concrete Class DII (240 kg/cm²)
2. Steel Reinforcement SD345
3. Pit of Steel Reinforcement is 200mm

PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JICA JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE DETAIL OF CATCH PIT (2)	PACKAGE 1 DWG No. P1-RD-3071
				PREPARED BY	M. TORIU	15 Jun. 2017		
				CHECKED BY	T. HAYAKAWA	20 Jun. 2017		
				APPROVED BY	Y. SANO	21 Jun. 2017		



DETAIL OF CATCH PIT (3) S=1:20

CATCH PIT (C-DITCH) TYPE B

Note
1. Specification of Plain Concrete should be CLASS EI



DETAIL OF GRATING COVER FOR CATCH PIT




Title	Specification	Quantity
Body		
Concrete	18N/mm ²	8.570 m ³
Reinforcing bar		kg
Form		78.40 m ²
Foundation	t=100	13.20 m ²
Cover		
Grating Cover		10 each


PROJECT NAME	FINANCED BY	COUNTERPART	JICA STUDY TEAM	NAME	SIGNATURE	DATE	DRAWING TITLE	PACKAGE
DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	JICA JAPAN INTERNATIONAL COOPERATION AGENCY	REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	M. TORIU	<i>[Signature]</i>	15 Jun. 2017	DETAIL OF CATCH PIT (3)	1
				T. HAYAKAWA	<i>[Signature]</i>	20 Jun. 2017		DWG No.
				Y. SANO	<i>[Signature]</i>	21 Jun. 2017		P1-RD-3072

VERTICAL DRAIN TYPE A (1)


DETAIL OF CATCH PIT (C-DITCH) TYPE A S=1:20




SECTION A-A




DETAIL OF VERTICAL DRAIN S=1:30



DETAIL OF CATCH PIT (C-DITCH) TYPE C S=1:20




SECTION A-A



PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE VERTICAL DRAIN TYPE A (1)	PACKAGE	
				PREPARED BY	M. TORIU			15 Jun. 2017	1
				CHECKED BY	T. HAYAKAWA			20 Jun. 2017	DWG No.
				APPROVED BY	Y. SANO			21 Jun. 2017	P1-RD-3080


VERTICAL DRAIN TYPE A (2)

UPVC200mm(8inch) S=1:10
(O.D.216mm)




Note: UPVC pipes one end with Socket shape

JOINT (90°) 200mm(8inch) S=1:10




PIPE BRACE S=1:10
(200mm)




Vertical Drain Location	Ground	H	Pipe Length (m)			JOINT (nos.)	Remark	
			Straight	Cross	Total			
PK1(Thanlyin side)	0+260.000	4.30	1.684	1.524	0.710	2.8570	1	
	0+285.000	4.30	2.261	2.101	0.710	3.434	1	
	0+325.000	4.30	3.074	2.914	0.710	4.247	1	
				Total		10.538	3	
PK2(Thaketa side)	2+428.400	4.30	3.429	3.268	0.710	4.601	1	
	2+448.400	4.30	3.125	2.965	0.710	4.298	1	
	2+458.400	4.30	2.996	2.836	0.710	4.169	1	
	2+468.400	4.30	2.920	2.760	0.973	4.356	1	
	2+478.400	4.30	2.859	2.699	0.973	4.295	1	
	2+488.400	4.30	2.849	2.689	0.973	4.285	1	
	2+505.500	4.30	2.719	2.559	0.973	4.155	1	CATCH PIT TYPE C
	2+518.700	4.30	2.814	2.654	0.973	4.250	1	
	2+528.700	4.30	2.853	2.693	0.973	4.289	1	
	2+538.700	4.30	2.901	2.741	0.973	4.337	1	
	2+548.700	4.30	2.987	2.827	0.710	4.160	1	
	2+558.700	4.30	3.086	2.926	0.710	4.259	1	
	2+578.700	4.30	3.363	3.203	0.710	4.536	1	
	2+600.000	4.30	3.728	3.568	0.710	4.901	1	
	2+705.000	4.30	1.246	1.086	0.710	2.419	1	
2+730.000	4.30	0.277	0.117	0.710	1.450	1		
2+755.000	4.30	0.218	0.058	0.710	1.391	1		
				Total		66.151	17	

VERTICAL DRAIN TYPE A (3)


DETAIL OF CATCH PIT (C-DITCH) TYPE D S=1:20
(STA.2+505.500)



SECTION A-A



DETAIL OF VERTICAL DRAIN S=1:30
(STA.2+505.500)




<small>PROJECT NAME</small> DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	<small>FINANCED BY</small> JAPAN INTERNATIONAL COOPERATION AGENCY	<small>COUNTERPART</small> REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	<small>JICA STUDY TEAM</small> NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 10%;"></th> <th style="width: 20%;">NAME</th> <th style="width: 20%;">SIGNATURE</th> <th style="width: 20%;">DATE</th> </tr> </thead> <tbody> <tr> <td>PREPARED BY</td> <td>M. TORIU</td> <td></td> <td>15 Jun. 2017</td> </tr> <tr> <td>CHECKED BY</td> <td>T. HAYAKAWA</td> <td></td> <td>20 Jun. 2017</td> </tr> <tr> <td>APPROVED BY</td> <td>Y. SANO</td> <td></td> <td>21 Jun. 2017</td> </tr> </tbody> </table>		NAME	SIGNATURE	DATE	PREPARED BY	M. TORIU		15 Jun. 2017	CHECKED BY	T. HAYAKAWA		20 Jun. 2017	APPROVED BY	Y. SANO		21 Jun. 2017	DRAWING TITLE VERTICAL DRAIN TYPE A (3)	PACKAGE 1 DWG No. P1-RD-3082
	NAME	SIGNATURE	DATE																			
PREPARED BY	M. TORIU		15 Jun. 2017																			
CHECKED BY	T. HAYAKAWA		20 Jun. 2017																			
APPROVED BY	Y. SANO		21 Jun. 2017																			

DRAINAGE OUTLET TYPE-A (1)


LEFT SIDE OF MAIN ROAD (1) S=1:100

PLAN VIEW



- NOTES:
1. Concrete Class DII (240 kg/cm³)
 2. Steel Reinforcement SD345

SECTION




LOCATION		LEFT RIVER BANK
INSIDE DIMENSION	WIDTH	1.000 m
	HEIGHT	1.000 m
TOTAL BOX CULVERT LENGTH		5.235 m
UNIT WEIGHT	REINFORCED CONCRETE	24.5 kN/m ³
	SOIL	18.0 kN/m ³
CONCRETE DESIGN STRENGTH		24.0 N/mm ²
ALLOWABLE STRESS	COMPRESSIVE STRESS DUE TO BENDING	8 N/mm ²
	SHEARING STRESS	0.39 N/mm ²
	TENSILE STRESS (SD345)	160 N/mm ²
COEFFICIENT OF EARTH PRESSURE		0.5000
IMPACT COEFFICIENT		-
SEISMIC COEFFICIENT		-
ANGLE OF SKEW		90°00'
RADIUS OF CURVATURE		R=
GRADIENT OF BOX CULVERT		i = 0.100 %

DRAINAGE OUTLET TYPE-A (2)


RIGHT SIDE OF MAIN ROAD (1) S=1:100

PLAN VIEW



- NOTES:
1. Concrete Class DII (240 kg/cm³)
 2. Steel Reinforcement SD345


SECTION



LOCATION		LEFT RIVER BANK
INSIDE DIMENSION	WIDTH	1.000 m
	HEIGHT	1.000 m
TOTAL BOX CULVERT LENGTH		5.084 m
UNIT WEIGHT	REINFORCED CONCRETE	24.5 kN/m ³
	SOIL	18.0 kN/m ³
CONCRETE DESIGN STRENGTH		24.0 N/mm ³
ALLOWABLE STRESS	COMPRESSIVE STRESS DUE TO BENDING	8 N/mm ³
	SHEARING STRESS	0.39 N/mm ³
	TENSILE STRESS (SD345)	160 N/mm ³
COEFFICIENT OF EARTH PRESSURE		0.5000
IMPACT COEFFICIENT		-
SEISMIC COEFFICIENT		-
ANGLE OF SKEW		90°00
RADIUS OF CURVATURE		R=
GRADIENT OF BOX CULVERT		i= 0.100 %

DRAINAGE OUTLET TYPE-A (3)

INLET AND OUTLET FOR TYPE A S=1:75




QUANTITIES OF DRAINAGE OUTLET


No.	Description	Width	Length	Thickness	Height	Number	Unit	Quantity
		W	L	T	H			
1	Box 1000x1000		5.235				m	5.235
2	Leveling concrete						m ³	2.794
	Outlet Slab1	2.200	4.000	0.100		1	m ³	0.880
	Outlet Slab2	2.309	3.950	0.100		1	m ³	0.912
	Inlet Slab	5.812	1.000	0.100		1	m ³	0.581
	Inlet Wall	2.106	1.000	0.100		2	m ³	0.421
3	Foundation						m ³	5.588
	Outlet Slab1	2.200	4.000	0.200		1	m ³	1.760
	Outlet Slab2	2.309	3.950	0.200		1	m ³	1.824
	Inlet Slab	5.812	1.000	0.200		1	m ³	1.162
	Inlet Wall	2.106	1.000	0.200		2	m ³	0.842
4	Reinforced Concrete (DII)						m ³	15.845
	Inlet Front Slab	5.812	0.700	0.300		1	m ³	1.221
	Inlet Back Slab	2.106	1.000	0.300		2	m ³	1.264
	Inlet Wall1	5.812		0.300	2.500	1	m ³	4.359
	Inlet Wall2	1.600		0.300	1.300	-1	m ³	-0.624
	Outlet Slab1	1.600	4.000	0.300		1	m ³	1.920
	Outlet Slab2	2.309	4.000	0.300		1	m ³	2.771
	Outlet Slab3	6.518		0.300	0.600	1	m ³	1.173
	Outlet Wing Wall1	4.619		0.300	1.600	1	m ³	2.217
	Outlet Wing Wall2	4.619		0.260	0.300	2	m ³	0.721
	Outlet Wing Wall3	0.300		0.300	1.900	2	m ³	0.342
	Outlet Head Wall1	1.600		0.300	0.703	1	m ³	0.337
	Outlet Head Wall2	1.600		0.300	0.300	1	m ³	0.144
5	Formwork of out-let						m ²	63.942
	Inlet Wall1	5.812			2.500	2	m ²	29.060
	Inlet Wall2	1.600			1.000	-2	m ²	-3.200
	Outlet Slab	6.518			0.900	2	m ²	11.732
	Outlet Wing Wall	4.619			1.600	2	m ²	14.781
	Outlet Head Wall1	2.200			2.603	2	m ²	11.453
	Outlet Head Wall2	1.600			1.000	-2	m ²	-3.200
	Leveling Concrete1	5.812			0.100	2	m ²	1.162
	Leveling Concrete2	10.768			0.100	2	m ²	2.154
6	Riprap for Bedding Stone	6.500	2.000	0.300		1	m ³	3.900

DRAINAGE OUTLET TYPE-A (4) BAR ARRANGEMENT OF BOX CULVERT S=1:50


GENERAL DRAWING S=1:50




ERECTION DIAGRAM OF MAIN REINFORCEMENT




TOP SLAB



SECTION S=1:50




BOTTOM SLAB



DESIGN CRITERIA


INSIDE DIMENSION		WIDTH	1.00 m
		HEIGHT	1.00 m
LIVE LOAD		T-TYPE LIVE LOAD	
UNIT WEIGHT	REINFORCED CONCRETE (DII)	24.5	kN/m ³
	SOIL	18	kN/m ³
CONCRETE DESIGN STRENGTH		24	N/mm ²
ALLOWABLE STRESS			
COMPRESSIVE STRESS DUE TO BENDING		8	N/mm ²
SHEARING STRESS		0.39	N/mm ²
TENSILE STRESS (SD345)		160	N/mm ²
COEFFICIENT OF EARTH PRESSURE		0.5	
IMPACT COEFFICIENT		-	
SEISMIC COEFFICIENT		-	
ANGLE OF SKEW		90°00'00"	
RADIUS OF CURVATURE		R=∞	
GRADIENT OF BOX CULVERT		i=0.100%	

(PER 1m)



MARK	No.	SEC.	EACH	LENGTH (mm)	L1 (mm)	L2 (mm)	L3 (mm)	L4 (mm)	H (mm)	R (mm)
S 1	4	D13	4	3080	600	220	1120	920		140
S 2	1	D13	4	1400	1400					
S 3	1	D13	16	1000	1000					
S 4	5	D13	8	1040	195	649				459
S 5	3	D13	3	980		126				
W 1	1	D13	8	1390	1390					
W 2	1	D13	20	1000	1000					
W 3	2	D13	12	360		152				
F 1	4	D13	4	3080	600	220	1120	920		140
F 2	1	D13	4	1400	1400					
F 3	1	D13	16	1000	1000					
F 4	5	D13	8	650	195	255				180
F 5	3	D13	3	940		106				

SIDE SLAB



LIST OF REINFORCEMENT

(PER 1m)

MARK	SEC.	LENGTH (mm)	EACH	WEIGHT (kg/m)	WEIGHT/one (kg)	WEIGHT (kg)	REMARKS
S 1	D13	3080	4	0.995	3.065	12.260	
S 2	D13	1400	4	0.995	1.393	5.572	
S 3	D13	1000	16	0.995	0.995	15.920	
S 4	D13	1040	8	0.995	1.035	8.280	
S 5	D13	980	3	0.995	0.975	2.925	
W 1	D13	1390	8	0.995	1.383	11.064	
W 2	D13	1000	20	0.995	0.995	19.900	
W 3	D13	360	12	0.995	0.358	4.296	
F 1	D13	3080	4	0.995	3.065	12.260	
F 2	D13	1400	4	0.995	1.393	5.572	
F 3	D13	1000	16	0.995	0.995	15.920	
F 4	D13	650	8	0.995	0.647	5.176	
F 5	D13	940	3	0.995	0.935	2.805	

MATERIALS






(PER 1m)

KIND	UNIT	QUANTITY
CONCRETE (DII)	TOP	m ³ 0.480
	SIDE	m ³ 0.640
	BOTTOM	m ³ 0.480
	TOTAL	m ³ 1.600
FORM	m ² 5.966	
REINFORCING BAR	D19	kg 0
	D16	kg 0
	D13	kg 121.950
	TOTAL	kg 121.950
	LEVELING CONCRETE (EI) t=100	m ² 0.180
FOUNDATION t=200	m ² 0.360	

	D	a (mm)	b (mm)	c (mm)	R (mm)	L (mm)
D13	66	164	230	42	410	
D16	75	195	270	48	500	
D19	94	236	330	60	600	
D22	104	266	370	66	690	
D25	122	308	430	78	790	
D29	141	349	490	90	910	
D32	151	389	540	96	1000	

Note1: Size of Box Culvert and Bar Arrangement are based on Standard Drawing of Ministry of Land, Infrastructure, Transport and Tourism of Japan
 Note2: Specification of Steel Reinforcement Bar shall comply with SD345 (JIS G3112) or equivalent

DRAINAGE OUTLET TYPE-A (5) BAR ARRANGEMENT OF INLET S=1:200




PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 15%;">NAME</th> <th style="width: 15%;">SIGNATURE</th> <th style="width: 15%;">DATE</th> </tr> </thead> <tbody> <tr> <td>PREPARED BY</td> <td>M. TORIU</td> <td>15 Jun. 2017</td> </tr> <tr> <td>CHECKED BY</td> <td>T. HAYAKAWA</td> <td>20 Jun. 2017</td> </tr> <tr> <td>APPROVED BY</td> <td>Y. SANO</td> <td>21 Jun. 2017</td> </tr> </tbody> </table>	NAME	SIGNATURE	DATE	PREPARED BY	M. TORIU	15 Jun. 2017	CHECKED BY	T. HAYAKAWA	20 Jun. 2017	APPROVED BY	Y. SANO	21 Jun. 2017	DRAWING TITLE DRAINAGE OUTLET TYPE-A (5)	PACKAGE 1 DWG No. P1-RD-3094
NAME	SIGNATURE	DATE																
PREPARED BY	M. TORIU	15 Jun. 2017																
CHECKED BY	T. HAYAKAWA	20 Jun. 2017																
APPROVED BY	Y. SANO	21 Jun. 2017																

DRAINAGE OUTLET TYPE-A (6)

BAR ARRANGEMENT OF INLET S=1:40

INLET




LIST OF REINFORCEMENT(INLET)

MARK	SEC.	LENGTH (mm)	EACH	WEIGHT (kg/m)	WEIGHT/one (kg)	WEIGHT (kg)	REMARKS
A 1	D13	2 380	32	0.995	2.368	76	L
A 2	"	800	16	"	0.796	13	
A 3	"	1 500	18	"	1.493	27	
A 4	"	1 500	34	"	1.493	51	
A 5	D10	2 256	52	0.560	1.263	66	—
A 6	D13	2 440	68	0.995	2.428	165	—
A 7	"	1 670	22	"	1.662	37	—
A 8	D10	5 712	16	0.560	3.199	51	—
C 1	"	2 300	49	"	1.288	63	⊥
D 1	D13	1 610	11	0.995	1.602	18	⊥
D 2	"	2 960	4	"	2.945	12	—
SUB TOTAL						579	kg
D10						180	kg
D13						399	kg
Total						579	kg

D	a (mm)	b (mm)	c (mm)	R (mm)	L (mm)
D10	47	120	167	30	320
D13	57	144	201	36	380
D16	75	195	270	48	500
D19	94	240	334	60	630

DRAINAGE OUTLET TYPE-A (8) BAR ARRANGEMENT OF OUTLET S=1:50




LIST OF REINFORCEMENT(INLET)

MARK	SEC.	LENGTH (mm)	EACH	WEIGHT (kg/m)	WEIGHT/one (kg)	WEIGHT (kg)	REMARKS
E 1	D16	2 300	44	1.560	3.588	158	L
E 2	"	1 859	12	"	2.900	35	L (AVE)
E 3	"	1 090	10	"	1.700	17	I
E 4	"	1 295	42	"	2.020	85	I (AVE)
E 5	D13	1 233	54	0.995	1.227	66	I (AVE)
E 6	D10	3 449	36	0.560	1.931	70	— (AVE)
E 7	"	5 715	4	"	3.200	13	—
E 8	D13	4 880	9	0.995	4.856	44	—
E 9	"	2 630	22	"	2.617	58	— (AVE)
E 10	D10	5 064	53	0.560	2.836	150	— (AVE)
E 11	"	6 430	4	"	3.601	14	—
E 12	"	7 117	4	"	3.986	20	—
E 13	D13	4 880	9	0.995	4.856	16	—
G 1	"	2 300	35	"	2.289	80	—
H 1	D13	2 318	15	0.995	2.306	35	—
H 2	"	2 100	10	"	2.090	21	—
SUB TOTAL						906	kg
					D10	263	kg
					D13	348	kg
					D16	295	kg
					Total	906	kg



D	a (mm)	b (mm)	c (mm)	R (mm)	L (mm)
D10	47	120	167	30	320
D13	66	164	230	42	410
D16	75	195	270	48	500
D19	94	236	330	60	600

DRAINAGE OUTLET TYPE-A (9)

DETAIL OF FLAP GATE S=1:30




SIDE VIEW




PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE DRAINAGE OUTLET TYPE-A (9)	PACKAGE	
				PREPARED BY	M. TORIU			15 Jun. 2017	1
				CHECKED BY	T. HAYAKAWA			20 Jun. 2017	DWG No.
				APPROVED BY	Y. SANO			21 Jun. 2017	P1-RD-3098

MECHANICALLY STABILISED EARTH WALL MAIN ROAD (1)


LEFT SIDE (DEVELOP FROM BACK SIDE) S=1:200
Main Road (STA. 0+250~0+350)



PLAN S=1:300




CROSS SECTION S=1:100



PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE MECHANICALLY STABILISED EARTH WALL MAIN ROAD (1)	PACKAGE	
				PREPARED BY	J.TSUCHIYA			15 Jun. 2017	1
				CHECKED BY	T. HAYAKAWA			20 Jun. 2017	DWG No.
				APPROVED BY	Y. SANO			21 Jun. 2017	P1-RD-4000


MECHANICALLY STABILISED EARTH WALL MAIN ROAD(2)

LEFT SIDE (DEVELOP FROM BACK SIDE) S=1:100
Main Road (STA. 0+250~0+350)




NOTE)
1) The mark "L" indicates the length of steel strip determined by the stability calculation.
2) Wall length indicates the length of wall surface.

JOINT DETAIL DRAWING S=1:20




GALVANIZED STEEL PLATE S=1:20



PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JICA JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE MECHANICALLY STABILISED EARTH WALL MAIN ROAD(2)	PACKAGE	
				PREPARED BY	J.TSUCHIYA	土屋 潤		15 Jun. 2017	1
				CHECKED BY	T. HAYAKAWA	平川 知那		20 Jun. 2017	DWG No.
				APPROVED BY	Y. SANO	佐野 祐一		21 Jun. 2017	P1-RD-4010

MECHANICALLY STABILISED EARTH WALL MAIN ROAD(3)


LEFT SIDE (DEVELOP FROM BACK SIDE) S=1:100
Main Load (STA. 0+250~0+350)




JOINT FILLER: t=20
EDGE ANGLE (θ=90°)
2R-125 × 210 × 3.2 × 1500
ANCHOR BOLT
M12 × 90 n=6

NOTE)
1) The mark "L" indicates the length of steel strip determined by the stability calculation.
2) Wall length indicates the length of wall surface.

CONCRETE FOUNDATION DRAWING S=1:20






EDGE DETAIL DRAWING S=1:20



PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JICA JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE MECHANICALLY STABILISED EARTH WALL MAIN ROAD(3)	PACKAGE	
				PREPARED BY	J.TSUCHIYA	土屋 潤		15 Jun. 2017	1
				CHECKED BY	T. HAYAKAWA	平川 知那		20 Jun. 2017	DWG No.
				APPROVED BY	Y. SANO	佐野 祐一		21 Jun. 2017	P1-RD-4020

MECHANICALLY STABILISED EARTH WALL RAMP(1)



Note : HDPE pipe set in Concrete Barrier exsept Right side

PROJECT NAME
DETAILED DESIGN ON
BAGO RIVER BRIDGE
CONSTRUCTION PROJECT

FINANCED BY
JICA
JAPAN INTERNATIONAL
COOPERATION AGENCY

COUNTERPART
REPUBLIC OF THE UNION OF MYANMAR
MINISTRY OF CONSTRUCTION
DEPARTMENT OF BRIDGE

JICA STUDY TEAM
NIPPON KOEI CO., LTD.
ORIENTAL CONSULTANTS GLOBAL CO., LTD.
METROPOLITAN EXPRESSWAY COMPANY LIMITED
CHODAI CO., LTD.
NIPPON ENGINEERING CONSULTANTS CO., LTD.

	NAME	SIGNATURE	DATE
PREPARED BY	J.TSUCHIYA	土屋 潤	15 Jun. 2017
CHECKED BY	T. HAYAKAWA	平川 知那	20 Jun. 2017
APPROVED BY	Y. SANO	佐野 祐一	21 Jun. 2017


DRAWING TITLE
MECHANICALLY STABILISED EARTH WALL RAMP(1)

PACKAGE
1
DWG No.
P1-RD-4030

MECHANICALLY STABILISED EARTH WALL RAMP(2)

LEFT SIDE (DEVELOP FROM BACK SIDE) S=1:100


NEW Star City Approach Road (STA. 0+360~0+405)




NOTE)

- 1) The mark "L" indicates the length of steel strip determined by the stability calculation.
- 2) Wall length indicates the length of wall surface.

CONCRETE FOUNDATION DRAWING S=1:20




EDGE DETAIL DRAWING S=1:20




PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JICA JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE MECHANICALLY STABILISED EARTH WALL RAMP(2)	PACKAGE	
				PREPARED BY	J.TSUCHIYA	土屋 潤		15 Jun. 2017	1
				CHECKED BY	T. HAYAKAWA	平川 知那		20 Jun. 2017	DWG No.
				APPROVED BY	Y. SANO	佐野 裕一		21 Jun. 2017	P1-RD-4040

DETAIL OF MECHANICALLY STABILISED EARTH WALL(1)


SKIN ARRANGEMENT S=1:30




A-A CROSS SECTION S=1:30




B-B CROSS SECTION S=1:20




C-C CROSS SECTION S=1:20



FILTER CLOTH S=1:20






BEARING PAD S=1:10



DETAIL OF MECHANICALLY STABILISED EARTH WALL(2)




TYPE OF CONCRETE SKIN S=1:20

COPING REINFORCEMENT S=1:30




D-D CROSSSECTION


BAR SCHEDULING



BOLT NUT (M12x40) S=1:2



RIBBED STRIP S=1:10




NOTE) "H4" IS THE HIGH OF COPING REINFORCEMENT

PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE	PACKAGE	
				PREPARED BY	J.TSUCHIYA				15 Jun. 2017
				CHECKED BY	T. HAYAKAWA				20 Jun. 2017
				APPROVED BY	Y. SANO				21 Jun. 2017
DETAIL OF MECHANICALLY STABILISED EARTH WALL(2)							1	DWG No.	P1-RD-4060

DETAIL OF MECHANICALLY STABILISED EARTH WALL(3)


CONCRETE FOUNDATION DRAWING S=1:20

FRONT VIEW DRAWING




NOTE) 1. FOUNDATION WORK OF TOP FINISH:TROWEL FINISH

CROSS SECTION




JOINT DETAIL DRAWING S=1:20

CROSS SECTION




GALVANIZED STEEL PLATE S=1:20

FRONT VIEW DRAWING CROSS SECTION




EDGE DETAIL DRAWING

CROSS SECTION S=1:3



NOTE) 1. BOLT IT IS USED TWO PER ONE EDGE ANGLE


EDGE ANGLE BRACKET S=1:10




PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JICA JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE DETAIL OF MECHANICALLY STABILISED EARTH WALL(3)	PACKAGE 1 DWG No. P1-RD-4070	
				PREPARED BY	J.TSUCHIYA	土屋 潤			15 Jun. 2017
				CHECKED BY	T. HAYAKAWA	平川 知那			20 Jun. 2017
				APPROVED BY	Y. SANO	佐野 祐一			21 Jun. 2017

DETAIL OF MECHANICALLY STABILISED EARTH WALL(4)


CONCRETE COPING



BIRD'S EYE VIEW




CONCRETE SKIN PLATE




<small>PROJECT NAME</small> DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	<small>FINANCED BY</small> JAPAN INTERNATIONAL COOPERATION AGENCY	<small>COUNTERPART</small> REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	<small>JICA STUDY TEAM</small> NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: left;">NAME</th> <th style="text-align: left;">SIGNATURE</th> <th style="text-align: left;">DATE</th> </tr> <tr> <td>PREPARED BY J.TSUCHIYA</td> <td></td> <td>15 Jun. 2017</td> </tr> <tr> <td>CHECKED BY T. HAYAKAWA</td> <td></td> <td>20 Jun. 2017</td> </tr> <tr> <td>APPROVED BY Y. SANO</td> <td></td> <td>21 Jun. 2017</td> </tr> </table>	NAME	SIGNATURE	DATE	PREPARED BY J.TSUCHIYA		15 Jun. 2017	CHECKED BY T. HAYAKAWA		20 Jun. 2017	APPROVED BY Y. SANO		21 Jun. 2017	<small>DRAWING TITLE</small> DETAIL OF MECHANICALLY STABILISED EARTH WALL(4)	<small>PACKAGE</small> 1 DWG No. P1-RD-4080
NAME	SIGNATURE	DATE																
PREPARED BY J.TSUCHIYA		15 Jun. 2017																
CHECKED BY T. HAYAKAWA		20 Jun. 2017																
APPROVED BY Y. SANO		21 Jun. 2017																

GUARDRAIL ON MECHANICALLY STABILISED EARTH WALL MAIN ROAD(1) S=1:20


SECTION




BREAST WALL




BOTTOM SLAB



SETTING



BAR ASSEMBLING



PROJECT NAME
DETAILED DESIGN ON
BAGO RIVER BRIDGE
CONSTRUCTION PROJECT

FINANCED BY
 JAPAN INTERNATIONAL
COOPERATION AGENCY

COUNTERPART
 REPUBLIC OF THE UNION OF MYANMAR
MINISTRY OF CONSTRUCTION
DEPARTMENT OF BRIDGE

JICA STUDY TEAM
 NIPPON KOEI CO., LTD.
 ORIENTAL CONSULTANTS GLOBAL CO., LTD.
 METROPOLITAN EXPRESSWAY COMPANY LIMITED
 CHODAI CO., LTD.
 NIPPON ENGINEERING CONSULTANTS CO., LTD.


	NAME	SIGNATURE	DATE
PREPARED BY	J.TSUCHIYA		15 Jun. 2017
CHECKED BY	T. HAYAKAWA		20 Jun. 2017
APPROVED BY	Y. SANO		21 Jun. 2017

DRAWING TITLE
**GUARDRAIL ON
MECHANICALLY STABILISED EARTH WALL MAIN ROAD(1)**

PACKAGE
1
DWG No.
P1-RD-4090

GUARDRAIL ON MECHANICALLY STABILISED EARTH WALL MAIN ROAD(2)


BAR SCHEDULING



LIST OF REINFORCEMENT (per 10.0m)

NAME	PIANETER	LENGTH (mm)	NUMBER (nos.)	UNIT WEIGHT (kg/m)	WEIGHT/BAR (kg)	WEIGHT (kg)	REMARKS
BOTTOM SLAB							
1	D13	1430	82	0.995	1.42	116	┘
2	D13	1730	41	0.995	1.72	71	┘
3	D13	1730	41	0.995	1.72	71	┘
4	D13	850	41	0.995	0.85	35	┘
5	D13	690	41	0.995	0.69	28	┘
6	D13	930	18	0.995	0.93	17	┘
7	D13	9800	23	0.995	9.75	224	—
						D13	562 kg
total							562 kg


φ200 BOX WITHOUT REINFORCEMENT VIEW




LIST OF REINFORCEMENT (per 1 place)

NAME	PIANETER	LENGTH (mm)	NUMBER (nos.)	UNIT WEIGHT (kg/m)	WEIGHT/BAR (kg)	WEIGHT (kg)	REMARKS
HANDRAIL							
20	D13	1200	8	0.995	1.19	10	┘
21	D13	1100	8	0.995	1.09	9	—
						D13	19 kg
total							19 kg


CROSS SECTION OF WHEEL GUARD S=1:20



A - A



REINFORCING REBAR S=1:10




LIST OF REINFORCEMENT (per 10.0m)


NAME	PIANETER	LENGTH (mm)	NUMBER (nos.)	UNIT WEIGHT (kg/m)	WEIGHT/BAR (kg)	WEIGHT (kg)
Reinforcing rebar	D25	1550	10	3.98	6.17	62
					D25	62 kg
total						62 kg

GUARDRAIL ON MECHANICALLY STABILISED EARTH WALL RAMP(1) S=1:20


SECTION




BREST WALL




BOTTOM SLAB



SETTING




BAR ASSEMBLING



PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>NAME</th> <th>SIGNATURE</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td>PREPARED BY J.TSUCHIYA</td> <td></td> <td>15 Jun. 2017</td> </tr> <tr> <td>CHECKED BY T. HAYAKAWA</td> <td></td> <td>20 Jun. 2017</td> </tr> <tr> <td>APPROVED BY Y. SANO</td> <td></td> <td>21 Jun. 2017</td> </tr> </tbody> </table>	NAME	SIGNATURE	DATE	PREPARED BY J.TSUCHIYA		15 Jun. 2017	CHECKED BY T. HAYAKAWA		20 Jun. 2017	APPROVED BY Y. SANO		21 Jun. 2017	DRAWING TITLE GUARDRAIL ON MECHANICALLY STABILISED EARTH WALL RAMP(1)	PACKAGE 1 DWG No. P1-RD-4110
NAME	SIGNATURE	DATE																
PREPARED BY J.TSUCHIYA		15 Jun. 2017																
CHECKED BY T. HAYAKAWA		20 Jun. 2017																
APPROVED BY Y. SANO		21 Jun. 2017																

GUARDRAIL MECHANICALLY STABILISED EARTH WALL RAMP(2)


BAR SCHEDULING




LIST OF REINFORCEMENT (per 10.0m)

NAME	PIANETER	LENGTH (mm)	NUMBER (本)	UNIT WEIGHT (kg/m)	WEIGHT/BAR (kg)	WEIGHT (kg)	REMARKS
BOTTOM SLAB							
1	D13	1180	41	0.995	1.17	48	┘
2	D16	1220	41	1.560	1.90	78	┘
3	D13	1930	41	0.995	1.92	79	┘
4	D13	1930	41	0.995	1.92	79	┘
5	D13	850	41	0.995	0.85	35	┘
6	D13	690	20	0.995	0.69	14	┘
7	D13	930	35	0.995	0.93	33	┘
8	D13	9800	23	0.995	9.75	224	—
						D16	78 kg
						D13	512 kg
total							590 kg


CROSS SECTION OF WHEEL GUARD S=1:20



A - A



REINFORCING REBAR S=1:10




LIST OF REINFORCEMENT (per 10.0m)


NAME	PIANETER	LENGTH (mm)	NUMBER (nos.)	UNIT WEIGHT (kg/m)	WEIGHT/BAR (kg)	WEIGHT (kg)
Reinforcing rebar	D25	1550	10	3.98	6.17	62
					D25	62 kg
total						62 kg

GUARDRAIL ON MECHANICALLY STABILISED EARTH WALL RAMP(3) S=1:20


SECTION




BREAST WALL




BOTTOM SLAB



SETTING




BAR ASSEMBLING



PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 15%;">NAME</th> <th style="width: 15%;">SIGNATURE</th> <th style="width: 15%;">DATE</th> </tr> </thead> <tbody> <tr> <td>PREPARED BY J.TSUCHIYA</td> <td></td> <td>15 Jun. 2017</td> </tr> <tr> <td>CHECKED BY T. HAYAKAWA</td> <td></td> <td>20 Jun. 2017</td> </tr> <tr> <td>APPROVED BY Y. SANO</td> <td></td> <td>21 Jun. 2017</td> </tr> </tbody> </table>	NAME	SIGNATURE	DATE	PREPARED BY J.TSUCHIYA		15 Jun. 2017	CHECKED BY T. HAYAKAWA		20 Jun. 2017	APPROVED BY Y. SANO		21 Jun. 2017	DRAWING TITLE GUARDRAIL ON MECHANICALLY STABILISED EARTH WALL RAMP(3)	PACKAGE 1 DWG No. P1-RD-4130
NAME	SIGNATURE	DATE																
PREPARED BY J.TSUCHIYA		15 Jun. 2017																
CHECKED BY T. HAYAKAWA		20 Jun. 2017																
APPROVED BY Y. SANO		21 Jun. 2017																

GUARDRAIL MECHANICALLY STABILISED EARTH WALL RAMP(4)

BAR SCHEDULING




LIST OF REINFORCEMENT (per10.0m)


NAME	PIANETER	LENGTH (mm)	NUMBER (本)	UNIT WEIGHT (kg/m)	WEIGHT/BAR (kg)	WEIGHT (kg)	REMARKS
BOTTOM SLAB							
1	D13	1080	41	0.995	1.07	44	┘
2	D16	1120	41	1.560	1.75	72	┘
3	D13	1930	41	0.995	1.92	79	┘
4	D13	1930	41	0.995	1.92	79	┘
5	D13	850	41	0.995	0.85	35	┘
6	D13	690	20	0.995	0.69	14	┘
7	D13	930	35	0.995	0.93	33	┘
8	D13	9800	21	0.995	9.75	205	—
						D16	72 kg
						D13	489 kg
total							561 kg

CROSS SECTION OF WHEEL GUARD


S=1:20



A - A



REINFORCING REBAR S=1:10




LIST OF REINFORCEMENT (per 10.0m)


NAME	PIANETER	LENGTH (mm)	NUMBER (nos.)	UNIT WEIGHT (kg/m)	WEIGHT/BAR (kg)	WEIGHT (kg)
Reinforcing rebar	D25	1550	10	3.98	6.17	62
					D25	62 kg
total						62 kg

DETAIL OF LIGHTING FOUNDATION




CROSS SECTION S=1:40




PLAN S=1:40




PULLBOX DETAIL S=1:50




S1-1 3-D13x2560




S1-2 1-D13x2430




S1-3 1-D13x2950




S2-1 4-D13x1440




S2-2 2-D13x1390




S2-3 2-D13x1330




S3-1 4-D13x970




S3-2 2-D13x840




S3-3 2-D13x690




S4-1 1-D13x2610



S4-2 1-D13x3350



S5-1 1-D13x910



S5-2 1-D13x1280

BAR LIST

REBAR NO.	DIA (mm)	LENGTH (mm)	NUMBER	UNIT WEIGHT (kg/m)	WEIGHT/ONE (kg)	WEIGHT (kg)	REMARKS
S 1 -1	D13	2560	3	0.995	2.55	8	
S 1 -2	D13	2430	1	0.995	2.42	2	
S 1 -3	D13	2950	1	0.995	2.94	3	
S 2 -1	D13	1440	4	0.995	1.43	6	
S 2 -2	D13	1390	2	0.995	1.38	3	
S 2 -3	D13	1330	2	0.995	1.32	3	
S 3 -1	D13	970	4	0.995	0.97	4	
S 3 -2	D13	840	2	0.995	0.84	2	
S 3 -3	D13	690	2	0.995	0.69	1	
S 4 -1	D13	2610	1	0.995	2.60	3	
S 4 -2	D13	3350	1	0.995	3.33	3	
S 5 -1	D13	910	1	0.995	0.91	1	
S 5 -2	D13	1280	1	0.995	1.27	1	
						40	kg
TOTAL						40	kg

PROJECT NAME
DETAILED DESIGN ON
BAGO RIVER BRIDGE
CONSTRUCTION PROJECT

FINANCED BY
JICA
JAPAN INTERNATIONAL
COOPERATION AGENCY

COUNTERPART
REPUBLIC OF THE UNION OF MYANMAR
MINISTRY OF CONSTRUCTION
DEPARTMENT OF BRIDGE


JICA STUDY TEAM
NIPPON KOEI CO., LTD.
ORIENTAL CONSULTANTS GLOBAL CO., LTD.
METROPOLITAN EXPRESSWAY COMPANY LIMITED
CHODAI CO., LTD.
NIPPON ENGINEERING CONSULTANTS CO., LTD.

	NAME	SIGNATURE	DATE
PREPARED BY	J.TSUCHIYA	土屋 潤	15 Jun. 2017
CHECKED BY	T. HAYAKAWA	平川 知那	20 Jun. 2017
APPROVED BY	Y. SANO	佐野 祐一	21 Jun. 2017


DRAWING TITLE
DETAIL OF LIGHTING FOUNDATION

PACKAGE
1
DWG No.
P1-RD-4150

SOFT SOIL IMPROVEMENT MEASURES:MAIN ROAD(1)



PROFILE V=1:500
H=1:1000
LEFT SIDE(DEVOLP FROM BACK SIDE)
MAIN ROAD(STA.0+120.000~0+351.200)




LEGEND	
	SHALLOW IMPROVEMENT
	DRY EXCAVATION LENGTH
	DEEP SOIL MIXING
	SURCHARGE


Elevation represents above MSL unless otherwise indicated.

PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE	PACKAGE			
				PREPARED BY	R.HOSOKAWA				29 Sept. 2017	SOFT SOIL IMPROVEMENT MEASURES:MAIN ROAD(1)	1
				CHECKED BY	T. HAYAKAWA				3 Oct. 2017		DWG No.
				APPROVED BY	Y. SANO				6 Oct. 2017		P1-RD-5000

SOFT SOIL IMPROVEMENT MEASURES:MAIN ROAD(2)




PROFILE V=1:500
H=1:1000
RIGHT SIDE
MAIN ROAD(STA.0+120.000~0+351.200)





Elevation represents above MSL unless otherwise indicated.

PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE	PACKAGE				
				PREPARED BY	R.HOSOKAWA				29 Sept. 2017	SOFT SOIL IMPROVEMENT MEASURES:MAIN ROAD(2)	1	
				CHECKED BY	T. HAYAKAWA				3 Oct. 2017			DWG No.
				APPROVED BY	Y. SANO				6 Oct. 2017			P1-RD-5010

SOFT SOIL IMPROVEMENT MEASURES:RAMP



LEFT SIDE(DEVELOP FROM BACK SIDE)



Elevation represents above MSL unless otherwise indicated.



PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE	PACKAGE	
				PREPARED BY	R.HOSOKAWA				29 Sept. 2017
				CHECKED BY	T. HAYAKAWA				3 Oct. 2017
				APPROVED BY	Y. SANO				6 Oct. 2017
SOFT SOIL IMPROVEMENT MEASURES:RAMP							1	DWG No.	
								P1-RD-5020	

CROSS SECTION OF SURCHARGE:MAIN ROAD(1)

S=1:400



STA.0+161.513
GH=4.08
PH=5.689

STA.0+212.713
GH=4.19
PH=6.076





STA.0+160
GH=3.99
PH=5.681

STA.0+200
GH=3.51
PH=5.953



STA.0+140
GH=5.44
PH=5.610

STA.0+180
GH=3.80
PH=5.796



Elevation represents above MSL unless otherwise indicated.


LEGEND
SAND MAT

PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO.,LTD. NIPPON ENGINEERING CONSULTANTS CO.,LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE	PACKAGE	
				PREPARED BY	R.HOSOKAWA				29 Sept. 2017
				CHECKED BY	T. HAYAKAWA				3 Oct. 2017
				APPROVED BY	Y. SANO				6 Oct. 2017
CROSS SECTION OF SURCHARGE:MAIN ROAD(1)							1	DWG No.	
								P1-RD-5030	


CROSS SECTION OF SURCHARGE:MAIN ROAD(2)

S=1:400


STA.0+260
GH=4.28
PH=6.686




STA.0+320
GH=3.33
PH=7.809




STA.0+240
GH=4.26
PH=6.399




STA.0+300
GH=3.56
PH=7.392



STA.0+220
GH=4.48
PH=6.154



STA.0+280
GH=3.62
PH=7.017









Elevation represents above MSL unless otherwise indicated.

LEGEND
SAND MAT

PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE	PACKAGE	
				PREPARED BY	R.HOSOKAWA				29 Sept. 2017
				CHECKED BY	T. HAYAKAWA				3 Oct. 2017
				APPROVED BY	Y. SANO				6 Oct. 2017
CROSS SECTION OF SURCHARGE:MAIN ROAD(2)							1		
							DWG No.		
							P1-RD-5040		

CROSS SECTION OF DEEP MIXING METHOD:MAIN ROAD(1)

S=1:400




LEGEND	
	SHALLOW IMPROVEMENT
	DRY EXCAVATION LENGTH
	DEEP SOIL MIXING

Elevation represents above MSL unless otherwise indicated.

PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE CROSS SECTION OF DEEP MIXING METHOD: MAIN ROAD(1)	PACKAGE	
				PREPARED BY	R.HOSOKAWA			29 Sept. 2017	1
				CHECKED BY	T. HAYAKAWA			3 Oct. 2017	DWG No.
				APPROVED BY	Y. SANO			6 Oct. 2017	P1-RD-5050

CROSS SECTION OF DEEP MIXING METHOD:MAIN ROAD(2)

S=1:400




Elevation represents above MSL unless otherwise indicated.

PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE CROSS SECTION OF DEEP MIXING METHOD: MAIN ROAD(2)	PACKAGE	
				PREPARED BY	R.HOSOKAWA			29 Sept. 2017	1
				CHECKED BY	T. HAYAKAWA			3 Oct. 2017	DWG No.
				APPROVED BY	Y. SANO			6 Oct. 2017	P1-RD-5060

CROSS SECTION OF DEEP MIXING METHOD:MAIN ROAD(3)

S=1:400





Elevation represents above MSL unless otherwise indicated.

LEGEND	
	SHALLOW IMPROVEMENT
	DRY EXCAVATION LENGTH
	DEEP SOIL MIXING

PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE CROSS SECTION OF DEEP MIXING METHOD: MAIN ROAD(3)	PACKAGE	
				PREPARED BY	R.HOSOKAWA			29 Sept. 2017	1
				CHECKED BY	T. HAYAKAWA			3 Oct. 2017	DWG No.
				APPROVED BY	Y. SANO			6 Oct. 2017	P1-RD-5070

CROSS SECTION OF DEEP MIXING METHOD:RAMP(1)

S=1:400




Elevation represents above MSL unless otherwise indicated.

LEGEND	
	SHALLOW IMPROVEMENT
	DRY EXCAVATION LENGTH
	DEEP SOIL MIXING

PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE	PACKAGE			
				PREPARED BY	R.HOSOKAWA				29 Sept. 2017	CROSS SECTION OF DEEP MIXING METHOD:RAMP(1)	1
				CHECKED BY	T. HAYAKAWA				3 Oct. 2017		DWG No.
				APPROVED BY	Y. SANO				6 Oct. 2017		P1-RD-5080

CROSS SECTION OF DEEP MIXING METHOD:RAMP(2)

S=1:400



Elevation represents above MSL unless otherwise indicated.


LEGEND	
	SHALLOW IMPROVEMENT
	DRY EXCAVATION LENGTH
	DEEP SOIL MIXING

PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE	PACKAGE			
				PREPARED BY	R.HOSOKAWA				29 Sept. 2017	CROSS SECTION OF DEEP MIXING METHOD:RAMP(2)	1
				CHECKED BY	T. HAYAKAWA				3 Oct. 2017		DWG No.
				APPROVED BY	Y. SANO				6 Oct. 2017		P1-RD-5090


(REFERENCE) CONSTRUCTION PROCEDURE(1)

S=1:400


1. CONSTRUCTION OF SHALLOW IMPROVEMENT




3. CONSTRUCTION OF SAND MAT



2. CONSTRUCTION OF DEEP SOIL MIXING



CONSTRUCTION CYCLE



Elevation represents above MSL unless otherwise indicated.


PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JICA JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME PREPARED BY R. HOSOKAWA CHECKED BY T. HAYAKAWA APPROVED BY Y. SANO	SIGNATURE 細川 亮介 平川 和男 佐野 祐一	DATE 29 Sept. 2017 3 Oct. 2017 6 Oct. 2017	DRAWING TITLE (REFERENCE) CONSTRUCTION PROCEDURE(1)	PACKAGE 1 DWG No. P1-RD-5100
---	--	---	--	--	--------------------------------------	---	--	---------------------------------------

(REFERENCE) CONSTRUCTION PROCEDURE(2)

S=1:400


4. EMBANKMENT CONSTRUCTION

STA.0+320
GH=3.33
PH=7.809




6. CONSTRUCTION OF MECHANICALLY-STABILISED EARTH WALL

STA.0+320
GH=3.33
PH=7.809



5. CUT OF EMBANKMENT


STA.0+320
GH=3.33
PH=7.809



Elevation represents above MSL unless otherwise indicated.

7. PAVING WORK ETC.


STA.0+320
GH=3.33
PH=7.809




LEGEND	
	SAND MAT
	SHALLOW IMPROVEMENT
	DRY EXCAVATION LENGTH
	DEEP SOIL MIXING

PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE (REFERENCE) CONSTRUCTION PROCEDURE(2)	PACKAGE	
				PREPARED BY	R.HOSOKAWA			29 Sept. 2017	1
				CHECKED BY	T. HAYAKAWA			3 Oct. 2017	DWG No.
				APPROVED BY	Y. SANO			6 Oct. 2017	P1-RD-5110


DETAILS OF KERB SCALE = 1:20




CONCRETE KERB TYPE A-1




CONCRETE KERB TYPE A-2
TRANSITION BLOCK BETWEEN
TYPE A-1 AND TYPE A-3




CONCRETE KERB TYPE A-3




CONCRETE KERB TYPE C




CONCRETE KERB TYPE A-4
TRANSITION BLOCK BETWEEN
TYPE A-1 AND TYPE A-5




CONCRETE KERB TYPE A-5




CONCRETE KERB TYPE D




CONCRETE KERB TYPE B-1



CONCRETE KERB TYPE B-2
TRANSITION BLOCK BETWEEN
TYPE B-1 AND TYPE B-3



CONCRETE KERB TYPE B-3



CONCRETE KERB TYPE E

MATERIAL LIST (QUANTITIES PER 10 M)


TYPE	A-1	A-2	A-3	A-4	A-5	B-1	B-2	B-3
DIMENSION	180/205×H250×L600	180/205×H250 198/205×H70 ×L600	198/205×H70×L600	180/205×H250 195/205×H100 ×L600	195/205×H100×L600	180/210×H420×L600	180/210×H420 204/210×H220 ×L600	204/210×H220×L600
CONCRETE	CLASS E I	CLASS E I	CLASS E I	CLASS E I	CLASS E I	CLASS E I	CLASS E I	CLASS E I
MORTAR (1:3)	0.0915 m ³	0.0915 m ³	0.0915 m ³	0.0915 m ³	0.0915 m ³	0.142 m ³	0.142 m ³	0.142 m ³
CRUSHER-RUN	0.305 m ³	0.305 m ³	0.305 m ³	0.305 m ³	0.305 m ³	0.760 m ³	0.760 m ³	0.760 m ³
GUTTER CONCRETE	-	-	-	-	-	0.925 m ³	0.925 m ³	0.925 m ³

MATERIAL LIST (QUANTITIES PER 10 M)

TYPE	C	D	E
DIMENSION	120×H150×L600	75/150×H346×L600	180/210×H300×L600
CONCRETE	CLASS E I	CLASS E I	CLASS E I
MORTAR (1:3)	-	-	-
CRUSHER-RUN	-	-	0.093 m ³
BASE CONCRETE	0.110 m ³	-	0.310 m ³
LEAN CONCRETE	-	0.500 m ³	-
BRICK	-	1.380 m ³	-


DETAILS OF CONCRETE SEAL S=1:10

NOTE
1. SPECIFICATION OF PLAIN CONCRETE SHOULD BE CLASS EI




QUANTITY		PER 100 M
TITLE	SPECIFICATION	QUANTITY
CONCRETE	% B#a zhi %S	100.00 A
WIRE NET		100.00 A
FOUNDATION	t = 120	100.00 A

**CONCRETE SEAL (t = 100 mm)
UNDER FLYOVER SECTION**



**MEDIAN TYPE C (t = 70 mm)
EARTHWORK SECTION**


QUANTITY		PER 100 M
TITLE	SPECIFICATION	QUANTITY
CONCRETE	% B#a zhi +S	7.70 M
FOUNDATION	t = 50	110.00 M
WELL GRADED SOIL		27.30 M




**MEDIAN TYPE B (t = 70 mm)
MECHANICALLY STABILISED EARTH WALL/GRAVITY WALL SECTION**

QUANTITY		PER 100 M
TITLE	SPECIFICATION	QUANTITY
CONCRETE	% B#a zhi +S	2.10 M
FOUNDATION	t = 50	30.00 M
WELL GRADED SOIL		5.20 M


DETAIL OF SIGNBOARD FOUNDATION AND POST




SIGN POST
S=1:50





FOUNDATION PLAN
S=1:50




FOUNDATION ELEVATION
S=1:50





**TOP VIEW
PLAN OF SIGN BOARD**
S=1:20



CLAMP DETAILS-2
S=1:10



DETAIL OF "A"
S=1:10




CLAMP DETAILS-1
S=1:10

QUANTITY		PER 10 EACH	
TITLE	SPECIFICATION	QUANTITY	DESCRIPTION
SIGNBOARD	ALMINIUM: t = 2.0 MM	10 EACH	WIDE-ANGLE PRISM TYPE
POST	60.3x3380x3.6	10 EACH	COATING SPECIFICATION
CONCRETE	E I	«% A	
FOUNDATION	t = 100	*(S'A	
FORM		%(S'A	

NOTE
1. SPECIFICATION OF PLAIN CONCRETE SHOULD BE CLASS EI

PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE DETAIL OF SIGNBOARD FOUNDATION AND POST	PACKAGE	
				PREPARED BY	K. TACHIBANA			15 JUNE 2017	1
				CHECKED BY	T. HAYAKAWA			20 JUNE 2017	DWG No.
				APPROVED BY	Y. SANO			21 JUNE 2017	P1-RD-6010


DETAIL OF SIGNBOARD



TS-1
STOP
SIZE: 600 MM×600 MM



TS-2
SPEED LIMIT 60 KM/H
SIZE: 600 MM DIAMETER




TS-3
SPEED LIMIT 40 KM/H
SIZE: 600 MM DIAMETER




TS-4
SPEED LIMIT 30 KM/H
SIZE: 600 MM DIAMETER



TS-5
NO U-TURN
SIZE: 600 MM DIAMETER




TS-6
CROSS ROAD
SIZE: 600 MM×600 MM



TS-7
TRAFFIC SIGNAL
SIZE: 600 MM×600 MM



TS-8
PEDESTRIAN CROSSING
SIZE: 600 MM×600 MM



TS-9
KEEP RIGHT (THIS WAY)
SIZE: 600 MM×600 MM



TS-10
SLOW DOWN
SIZE: 600 MM×600 MM



TS-11
SCHOOL ZONE
SIZE: 600 MM×600 MM




TS-12
REVERSE TURN (RIGHT)
SIZE: 600 MM×600 MM











TS-13
REVERSE TURN (LEFT)
SIZE: 600 MM×600 MM

COLORS: BLACK RED YELLOW GREEN WHITE LIGHT BLUE


PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE DETAIL OF SIGNBOARD	PACKAGE	
				PREPARED BY	K. TACHIBANA			15 JUNE 2017	1
				CHECKED BY	T. HAYAKAWA			20 JUNE 2017	DWG No.
				APPROVED BY	Y. SANO			21 JUNE 2017	P1-RD-6020




SIGNBOARD LAYOUT PLAN AT STAR CITY INTERSECTION AREA NO SCALE

SIGNBOARD	QUANTITY	SIGNBOARD	QUANTITY	SIGNBOARD	QUANTITY	SIGNBOARD	QUANTITY
 TYPE TS-1	2	 TYPE TS-3	2	 TYPE TS-6	4	 TYPE TS-9	3
 TYPE TS-2	4	 TYPE TS-4	1	 TYPE TS-7	5	 TYPE TS-13	1


DETAIL OF INFORMATORY SIGNBOARD



TYPE GS-5



TYPE GS-6




TYPE GS-7




TYPE GS-8



TYPE GS-1



TYPE GS-2



TYPE GS-3




TYPE GS-4

COLORS: WHITE BLUE GREEN


PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE DETAIL OF INFORMATORY SIGNBOARD	PACKAGE	
				PREPARED BY	K. TACHIBANA			15 JUNE 2017	1
				CHECKED BY	T. HAYAKAWA			20 JUNE 2017	DWG No.
				APPROVED BY	Y. SANO			21 JUNE 2017	P1-RD-6040

DETAIL OF INFORMATORY SIGNBOARD-TYPE C FOUNDATION AND POST (1)


GENERAL VIEW S = 1:40




SECTION OF PANEL S = 1:40




DETAIL OF MOUNTING BRACKET S = 1:20






DETAILS OF INTERACTION BETWEEN BEAM AND PILLAR S = 1:20



DETAILS OF COLUMN BASE S = 1:20




DETAIL OF ANCHOR BOLT S = 1:20




QUANTITY		PER ONE EACH	
TITLE	SPECIFICATION	QUANTITY	DESCRIPTION
SIGNBOARD	ALUMINIUM: T = 2.0 MM	1 EACH	ENCAPSULATED LENS TYPE
POST	(S ⁺)x7300x6.4	309.52 KG	HDZ 55
BEAM	% S ⁺ x4700x5.3	96.00 KG	HDZ 55
POST JOINTING	% -" x1000x4.5	20.20 KG	HDZ 55
STIFFENER		209.92 KG	
ANCHOR BOLT	M42x1000	48.40 KG	HDZ 55
ANCHOR BOLT FIXED FRAME	PL-100x700x6	20.72 KG	HDZ 55

DETAIL OF INFORMATORY SIGNBOARD-TYPE C FOUNDATION AND POST (2) S=1:30

FRONT VIEW OF BASEMENT




SIDE VIEW OF BASEMENT




Note
 1. Specification of Reinforced Concrete should be CLASS DII
 2. Specification of Steel reinforcement bar should be SD345

PLAN VIEW OF BASEMENT




REBAR PROCESSING DRAWING




QUANTITY			PER ONE EACH
TITLE	SPECIFICATION	QUANTITY	DESCRIPTION
CONCRETE	D II	4.20 A	
REINFORCING BAR	D13	105.31 KG	
FOUNDATION	t = 150 MM	4.44 A	
FORM		10.80 A	

PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE DETAIL OF INFORMATORY SIGNBOARD-TYPE C FOUNDATION AND POST (2) S=1:30	PACKAGE	
				PREPARED BY	E. YOKOTA			15 JUNE 2017	1
				CHECKED BY	T. HAYAKAWA			20 JUNE 2017	DWG No.
				APPROVED BY	Y. SANO			21 JUNE 2017	P1-RD-6060




PROPOSED INFORMATORY SIGNBOARD AT STAR CITY INTERSECTION AREA


INFORMATORY SIGNBOARD	FOUNDATION AND POST	PROPOSED LOCATION TO INSTALL	QUANTITY
 TYPE GS-7	TYPE C	RIGHT SIDE OF THILWAACCESS ROAD BEFORE INTERSECTION	1
 TYPE GS-8	TYPE C	RIGHT SIDE OF STAR CITY LINE BEFORE INTERSECTION	1




LINE MARKINGS SCALE = 1:100



ZEBRA ZONE SCALE = 1:100




DETAILED ARRANGEMENT OF PEDESTRIAN CROSSING AND STOP LINE SCALE = 1:200




PAVEMENT MARKINGS AT CROSS ROAD NO SCALE

PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM 	NAME	SIGNATURE	DATE	DRAWING TITLE	PACKAGE		
				PREPARED BY	K. TACHIBANA	15 JUNE 2017			ROAD MARKING DETAILS (1)	1
				CHECKED BY	T. HAYAKAWA	20 JUNE 2017				DWG No.
				APPROVED BY	Y. SANO	21 JUNE 2017				P1-RD-6080




PM-1 SPEED LIMIT 30 KM/H PM-2 SPEED LIMIT 40 KM/H PM-3 SPEED LIMIT 60 KM/H



PM-4 TOLL AHEAD
 REFERENCE SHALL BE MADE TO
 DRAWING NO. PWD(RD)/SD91/20-1,
 ROAD AND TRANSPORTATION DIVISION,
 PUBLIC WORKS DEPARTMENT








COLORS: WHITE ORANGE



ARROW MARKS
 REFERENCE SHALL BE MADE TO
 DRAWING NO. PWD(RD)/SD91/8-2
 ROAD AND TRANSPORTATION DIVISION,
 PUBLIC WORKS DEPARTMENT


PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM 	NAME	SIGNATURE	DATE	DRAWING TITLE	PACKAGE	
				PREPARED BY	K. TACHIBANA				15 JUNE 2017
				CHECKED BY	T. HAYAKAWA				20 JUNE 2017
				APPROVED BY	Y. SANO				21 JUNE 2017
ROAD MARKING DETAILS (2)							1	DWG No.	
							P1-RD-6090		

GUARDRAIL TYPE-A (GR-A)




PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE DETAILS OF GUARDRAIL (1) TYPE-A	PACKAGE	
				PREPARED BY	E. YOKOTA			15 JUNE 2017	1
				CHECKED BY	T. HAYAKAWA			20 JUNE 2017	DWG No.
				APPROVED BY	Y. SANO			21 JUNE 2017	P1-RD-6100


GUARDRAIL TYPE-Am (GR-Am)





PLAN S = 1:30




ELEVATION S = 1:30




GR-Am SECTION S = 1:30



ENDPIECE DETAIL S = 1:20










BEEM S = 1:10



BRACKET (SS400) S = 1:10


PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM 	NAME	SIGNATURE	DATE	DRAWING TITLE DETAILS OF GUARDRAIL (2) TYPE-Am	PACKAGE	
				PREPARED BY	E. YOKOTA			15 JUNE 2017	1
				CHECKED BY	T. HAYAKAWA			20 JUNE 2017	DWG No.
				APPROVED BY	Y. SANO			21 JUNE 2017	P1-RD-6105

GUARDRAIL TYPE-B (GR-B)




PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE DETAILS OF GUARDRAIL (3) TYPE-B	PACKAGE	
				PREPARED BY	E. YOKOTA			15 JUNE 2017	1
				CHECKED BY	T. HAYAKAWA			20 JUNE 2017	DWG No.
				APPROVED BY	Y. SANO			21 JUNE 2017	P1-RD-6110


GUARD PIPE TYPE-A (GP-A)




PLAN S = 1:20




ELEVATION S = 1:20




SECTION S = 1:20




JOINT BLACKET S = 1:5



INTERMEDIATE BLACKET S = 1:5



GP-A BEAM S = 1:10



INNER SLEAVE S = 1:10

PROJECT NAME DETAILED DESIGN ON BAGO RIVER BRIDGE CONSTRUCTION PROJECT	FINANCED BY JAPAN INTERNATIONAL COOPERATION AGENCY	COUNTERPART REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF CONSTRUCTION DEPARTMENT OF BRIDGE	JICA STUDY TEAM NIPPON KOEI CO., LTD. ORIENTAL CONSULTANTS GLOBAL CO., LTD. METROPOLITAN EXPRESSWAY COMPANY LIMITED CHODAI CO., LTD. NIPPON ENGINEERING CONSULTANTS CO., LTD.	NAME	SIGNATURE	DATE	DRAWING TITLE DETAILS OF GUARD PIPE TYPE-A	PACKAGE	
				PREPARED BY	E. YOKOTA			15 JUNE 2017	1
				CHECKED BY	T. HAYAKAWA			20 JUNE 2017	DWG No.
				APPROVED BY	Y. SANO			21 JUNE 2017	P1-RD-6120

(REFERENCE) QUANTITY TABLE OF ROAD (1)

Item	Description	Unit	Qty								
			Package1								
			Main Road Before STA 0+177	Main Road After STA 0+177	On-ramp	Star City Access Line	Yangon Access Line	Thilawa Access Line	Total		
Road Structures											
1. Earthworks	Excavation & Backfilling	Filling for Surcharge W>=4m	m3		13,627.200	-				13,627	
		Sand Mat for Surcharge W>=4m	m3		2,324.000	-				2,324	
		Filling W>=4m	m3	Bulldozer		561.400	1,322.500	-	143.700	3.200	2,031
		Filling W<4m	m3			416.200	136.400	39.300	68.600	52.800	713
		Cutting W>=4m	m3	Bulldozer		11,042.400	888.400	288.200	463.800	472.900	13,156
		Back Fill of Wall W>=4m	m3			1,367.600	940.700				2,308
	Trimming of Slope	Slope of Embankment	m2		700.100	1,341.314	748.240	28.800	272.100	124.300	3,215
		Cut Slope	m2						5.400	11.500	17
	Slope Protection	Sodding	m2		700.100	1,341.314	748.240	28.800	272.100	124.300	3,215
2. Pavement	Main Road, On-ramp & Relocation Road to Existing Thanlyin Bridge	Subgrade course	m2								-
		Aggregate, t=500mm	m2		4,297.900						4,298
		t=350mm	m2		4,805.530						4,806
		t=300mm	m2								-
		t=250mm	m2								-
		t=150mm	m2				2,647.630		983.800	1,125.000	4,756
		Base course	m2		8,670.450						8,670
		Aggregate, t=250mm	m2				2,588.790		938.500	1,077.400	4,605
		t=150mm	m2				8,458.910		383.300	418.200	11,643
		Prime Coat	m2				8,456.910		908.300	1,045.600	12,816
		Surface Base	m2								-
		Binder course	m2								-
	Tack Coat	m2				8,250.000		363.300	418.200	11,465	
	Surface course	m2				8,250.000	2,433.000	908.300	1,045.600	12,637	
	Toll Plaza	Subgrade course	m2								-
		Aggregate, t=350mm	m2								-
		Subbase course	m2								-
		Aggregate, t=250mm	m2								-
		Base course	m2								-
		Aggregate, t=100mm	m2								-
		t=250mm σ _{ck} =24N/mm	m2								-
		t=250mm σ _{ck} =18N/mm	m2								-
		Attainment section σ _{ck} =24N/mm	m3								-
		Metal Lath	kg								-
Star City Access Main Road	Sand Compacted	m2					613.100			613	
	t=200mm	m2					613.100			613	
	Hard Core with Sand	m2					613.100			613	
	Plastic Sheet	m2					613.100			613	
	Lean concrete v1.3:6	m2					613.100			613	
	t=80mm	m2					613.100			613	
	Concrete	m2					613.100			613	
	t=200mm	m2					613.100			613	
	STEEL MESH	kg					5,051.000			5,051	
	TRANSVERSE JOINT	kg					1,079.000			1,079	
	LONGITUDINAL JOINT	kg					1,084.000			1,084	
	DEFORMED TIE BAR, D22	kg					1,084.000			1,084	
Star City Access Side Walk	Sand Compacted	m2					102.400			102	
	t=300mm	m2					46.400			46	
	Hard Core with compacted sand	m2					46.400			46	
	Expose Aggregate Finished Footpath	m2								-	
	t=75mm	m2								-	
	Soil Aggregate C-30	m2		581.200				210.900	52.000	844	
t=100mm	m2								-		
Sand	m2		567.680				210.900	52.000	831		
t=30mm	m2								-		
Precast Concrete Paving Block	m2		580.760				210.900	52.000	844		
t=60mm	m2								-		
3. Soft Soil Treatment	Deep Mixing Method	Soil Cement Columns (Working Pile) including Field Test	lm		14,615.500		8,211.300			22,827	
		Soil Cement Columns (Preliminary Test Columns; Non-working Pile) including Field Test	lm		75.000		81.250			156	
		Solidifying material addition	t		11,523.390		6,468.120			17,992	
	Shallow Improvement	depth=2.0m (L=42.522m, W=3.708m)	m3								-
		depth=1.3m	m3		3,582.710		1,286.310			4,869	
		Solidifying material addition	t		824.020		295.650			1,120	
Solidifying material addition	t								-		

(REFERENCE) QUANTITY TABLE OF ROAD (2)

Item	Description	Unit	Qty								
			Package1								
			Main Road Before STA 0+177	Main Road After STA 0+177	On-ramp	Star City Access Line	Yangon Access Line	Thilawa Access Line	Total		
4. Wall Structures	Mechanically Stabilised Earth Wall	Wall Area	Profabricated Concrete Block	m ²		283.380	176.080				459
		Strip	W 80mm, t 3mm	m		2,562.000	1,664.000				4,226
		Crushed Stone of Back Wall	C-40	m ³		619.210	310.690				930
		Rising Concrete (Include Curb)	Concrete $\sigma_{ck}=24N/mm^2$	m ³		142.070	51.450				194
			Form	m ²		430.130	153.510				584
			Steel Bar(SD345 D16)	kg		630.500	527.900				1,158
			Steel Bar(SD345 D13)	kg		7,127.000	2,486.100				9,613
			Steel Bar(SD345 D10)	kg							-
			Joint Filler(bituminous material) t=20mm	m ²		1.440	1.440				3
			Joint Filler(bituminous material) t=10mm	m ²		17.550	9.040				27
		Leveling Concrete	m ³							-	
		Crushed Stone (C-40)	m ³							-	
		Rubber Plate	t=10mm (10x300x600)	m ²		30.480	6.660				39
		Base Concrete of Wall	Concrete $\sigma_{ck} 18N/mm^2$	m ³		23.370	9.330				33
		Form	m ²		40.730	15.640				56	
		Geotextile	m ²		406.480	155.600				562	
		Gravity Wall	Concrete	m ³							-
			Form	m ²							-
			Steel Bar	SD345 D16	kg						-
			SD345 D13	kg							-
	Joint	t=10mm	m ²							-	
		Lighting Foundation	Concrete $\sigma_{ck}=24N/mm^2$	m ³		1.380	0.460				2
	Form	m ²		5.042	2.014					8	
	Form	m ²			0.120	0.040				-	
	Steel Bar(SD345 D13)	kg								-	
5. Miscellaneous	Concrete Kerb and Concrete Block	Concrete Kerb(typeA-1)	m	348.100	358.480			190.800	40.000	937	
		Concrete Kerb(typeA-2)	m	1.000						1	
		Concrete Kerb(typeA-3)	m	3.800						4	
		Concrete Kerb(typeA-4)	m							-	
		Concrete Kerb(typeA-5)	m							-	
		Concrete Kerb(typeB-1)	m	91.100						91	
		Concrete Kerb(typeB-2)	m	5.000						5	
		Concrete Kerb(typeB-3)	m	11.800						12	
		Concrete Kerb(typeC)	m							-	
		Concrete Kerb(typeD)	m				29.500			30	
	Concrete Kerb(typeE)	m							-		
	Guard-rail	Bridge type	Metal type(GR-A)	m		101.695	38.975				141
			Metal type(GR-B)	m	243.300	246.785		43.300			533
			Metal type(GR-C)	m			720.610			131.200	852
	Guard pipe	Metal type(GP-A)		m	45.700						46
				m	639.300			202.400	377.100	393.400	1,612
	Road Marking	unbroken ,white	W=15cm	m	143.200			29.000			172
			W=8cm	m		4,540.120	1,420.503				5,960
			W=10cm	m							-
			W=30cm	m	19.500			13.700		4.200	37
			W=45cm	m	165.100			56.800			222
			broken ,white	m	39.000			8.000			45
			broken ,white	m		2,270.060					2,270
			Speed Limit Marks	Nos		0	1				1
			Toll Ahead Marks	Nos		0	0				0
			Arrow Mark ,white	Nos	9.000	0	3	3.000		1.000	16
	Concrete Seal	Median Strip	W=1.5m	m		179.230					179
			W 0.75m	m							-
			Side Strip (Toll Plaza Section)	m ²							-
			Side Strip next to "Wall"	m							-
Under Flyover Section (Thaketa Side)	W Varied		m ²							-	
			m ²							-	
Signboard	Informatory Signboard Type A	Informatory Signboard Type B	Nos							-	
		Informatory Signboard Type C	Nos	2						2	
		Regulatory Signs	Nos	12						12	
		Warning Signs	Nos	10						10	
			Nos	10						10	
Approach Slab for Flyover Section (A1-1)	Concrete	Concrete	m ³							-	
		Form	m ²							-	
		Reinforcement Bar	t							-	
		Rubber Bearing	t 20mm	m ²						-	
		Joint Material	t=20mm	m ²						-	
		Gas Pipe	Spp400	kg						-	
		Cap	$\phi 60 \times 3.2$	kg						-	

(REFERENCE) QUANTITY TABLE OF ROAD (3)

Item	Description	Unit	Qty						Total	
			Package1							
			Main Road Before STA 0+177	Main Road After STA 0+177	On-ramp	Star City Access Line	Yangon Access Line	Thilawa Access Line		
6. Drainage Structures	Open Ditches	Side Ditch Type U-300x300	-	78.780	-	-	-	-	79	
		Side Ditch Type U-500x500	-	-	-	-	181.000	-	181	
		Side Ditch Type U-800x800	-	846.550	344.504	36.000	-	-	1,227	
		Side Ditch Type U-1000x1000	-	187.425	-	-	-	-	187	
		Side Ditch Type U-1500x1500	-	-	-	-	-	-	-	
		Side Ditch Type U-500x500 with Concrete Cover	-	-	-	-	-	-	-	
		Side Ditch Type U-500x850 with Concrete Cover	37.000	-	-	-	52.000	241.900	331	
		Side Ditch Type U-800x800 with Concrete Cover	-	84.900	-	-	-	-	85	
		Side Ditch Type U-800x1000 with Concrete Cover	16.000	-	-	-	-	-	16	
		Side Ditch Type U-1000x1000 with Concrete Cover	-	-	-	-	-	-	-	
		Side Ditch Type U-1000x1500 with Concrete Cover	-	-	-	-	-	-	-	
		Side Ditch Type U-1500x1500 with Concrete Cover	-	-	-	-	-	-	-	
		Side Ditch Type U-1500x2500 with Concrete Cover	-	-	-	-	-	-	-	
		Catch Basins/Pits, Inlets, Outlets, Manholes	Catch Pit (C=DITCH) Type A	Nos	-	5.000	-	-	-	5
			Catch Pit (C=DITCH) Type C	Nos	-	3.000	-	-	-	3
	Catch Pit (C=DITCH) Type D		Nos	-	-	-	-	-	-	
	Catch Pit (C=DITCH) Type B		Nos	-	-	-	-	-	-	
	Catch Pit 700 x 700 x 1050		Nos	-	3.000	-	-	-	3	
	Catch Pit 700 x 700 x 1850		Nos	-	-	-	2.000	1.000	3	
	Catch Pit 700 x 700 x 2250		Nos	-	-	-	1.000	-	1	
	Catch Pit 1000 x 1000 x 1350		Nos	-	14.000	-	-	-	14	
	Catch Pit 1200 x 1200 x 1600		Nos	-	11.000	-	-	1.000	12	
	Catch Pit 600 x 600 x 1100		Nos	-	-	-	-	-	-	
	Concrete Pipe Culverts	Concrete Pipe Culvert φ300 (CON. 360°) TYPE B	m	-	70.000	-	-	-	70	
		Concrete Pipe Culvert φ300 (CON. 360°) TYPE A	m	-	-	-	-	-	-	
		Concrete Pipe Culvert φ900 (CON. 360°)	m	-	44.630	-	-	-	45	
	Concrete Box Culverts	Box Culver: Type 1000 x 1000	m	-	-	-	20.700	-	21	
	Vertical Drain	Vertical Drain Type A UPVC Pipe φ200mm	m	-	10.538	-	-	-	11	
		Vertical Drain Type A Joint (90°) φ200mm	Nos	-	3.000	-	-	-	3	
		Vertical Drain Type B U-Ditch Section A-A	m	-	-	-	-	-	-	
Vertical Drain Type B U-Ditch Section B-B		m	-	-	-	-	-	-		
Vertical Drain Type B U-Ditch Section C-C		m	-	-	-	-	-	-		
Vertical Drain Type C UPVC Pipe φ150mm		m	-	-	-	-	-	-		
Drainage Outlet	Drainage Outlet Type A Left Side	L.S	-	1.000	-	-	-	1		
	Drainage Outlet Type A Right Side	L.S	-	1.000	-	-	-	1		
	Drainage Outlet Type A Flap Gate 1000 x 1000	Nos	-	2.000	-	-	-	2		
	Drainage Outlet Type B Left Side	L.S	-	-	-	-	-	-		
	Drainage Outlet Type B Right Side	L.S	-	-	-	-	-	-		
	Drainage Outlet Type B Flap Gate 2000 x 1500	Nos	-	-	-	-	-	-		