

5. Field Report

PREPARATORY SURVEY
ON
IMPROVEMENT OF SUBSTATIONS AND
DISTRIBUTION NETWORK PHASE 3
IN
THE REPUBLIC OF RWANDA

FIELD REPORT

22nd JUNE 2017

Prepared and Submitted by:

Confirmed and Agreed by:



Mr. Makoto Abe
Chief Consultant
JICA Preparatory Survey Team

Eng. NSHUTI Yves
Director of Energy Planning
Energy Development Corporation Limited
Rwanda Energy Group
Implementing Agency for the Project

Confirmed and Agreed by:



Eng. GAKWAVU Claver
Director, Planning
Energy Utility Corporation Limited
Rwanda Energy Group
Relevant organization for the Project

JICA PREPARATORY SURVEY TEAM

Yachiyo Engineering Co.,Ltd.
West Japan Engineering Consultants, Inc.

Contents

1. Outline of the Project	1
1.1 Background of the Project	1
1.2 Framework for the Project	1
1.3 Scope of the Japanese side	1
1.4 Obligation/Undertakings of the Rwandan side for the Project	2
1.4.1 General requirement	2
1.4.2 General requirement	2
2. Technical requirements confirmed in the first field survey	4
2.1 Technical requirements for the Substation of the Project	4
2.1.1 General requirement	4
2.1.2 Technical requirements for the equipment of New Gasogi Substation	5
2.1.3 Technical requirements for the equipment of existing Jabana Substation	9
2.2 Technical requirements for Transmission and Distribution Lines	11
2.2.1 Technical requirements for Transmission and Distribution Lines	11
2.2.2 Technical requirements for the Foundation of Transmission and Distribution Lines	13
2.3 Environmental and Social Consideration	14
2.3.1 Environmental Impact Assessment	15
2.3.2 Abbreviated Resettlement Action Plan	15
2.4 Procurement Plan of Spare Parts and Maintenance Tools	17
2.5 On-the-Job Training (OJT)	19
2.6 Power flow analysis	19
3. Tentative Implementation Schedule of the Project	20
4. Drawings	20

[Attachment]

Attachment – 1 Member List of the Study Team

Attachment – 2 Work Demarcation for Transmission Line, Distribution Line and Ring Main Unit

Attachment – 3 Tentative Implementation Schedule

1. Outline of the Project

1.1 Background of the Project

In response to the request from the Government of the Republic of Rwanda (Rwanda), Japan International Cooperation Agency (JICA), in consultation with the Government of Japan, decided to conduct a Preparatory Survey (the Survey) on the Project for Improvement of Substations and Distribution Network Phase 3 (the Project).

JICA sent to Rwanda the Preparatory Survey Team (the Team) headed by Mr. Tsunenari Soyama, Deputy Director, JICA, to conduct the first field survey and the Team is scheduled to stay in the country from 27th May to 30th June, 2017.

The Team continued discussions with the concerned officials of Rwanda and the field survey in Rwanda.

EDCL, EUCL and the Team had series of technical discussions to form mutual understandings about the contents, scope, preconditions for the Outline Design, basic specifications, general layouts, and so on of the Project throughout the first field survey. EDCL, EUCL and the Team agreed to record the following issues described on this Field Report as a conclusion of the discussions.

Components of the Project will be further examined and may be modified through the consultation with the Japanese Ministry of Foreign Affairs and JICA headquarters. It is important for the Rwandan side to understand that the Preparatory Survey is not a commitment for the future implementation of the Project.

Particularly, in consideration of the schedule and procedures of Japan's Grant Aid projects, the Team explained, and EDCL and EUCL agreed with the Team to proceed to the further study, the outline design, planning of the implementation schedule, the cost estimation and so on of the Project in accordance with the mutual understandings made on this field report immediately after the first field survey.

1.2 Framework for the Project

The framework for the Project is shown as follows;

- The responsible ministry is Ministry of Infrastructure (MININFRA).
- The implementing agency is Energy Development Corporation Limited (EDCL).
- The relevant organization is Energy Utility Corporation Limited (EUCL).

1.3 The Scope of the Japanese side

The Scope of the Japanese side is shown in Table 1.3-1 and GA-01 Site Location Map in the Drawings.

mm

A

he

\$

Table 1.3-1 Outline of the Proposed Components

Components	Capacity
<u>Procurement and Installation Work</u>	
1. New Gasogi Substation (a) 20-MVA 110 /15 kV transformer <i>2x15MVA</i> (b) 110 kV switchgear (c) 15 kV switchgear (d) Control and supervisory facilities	1 unit 1 set 1 set 1 set
2. Transmission Line for New Gasogi Substation (a) 110 kV transmission line (Single circuit) from the existing line between Birembo (Ndera) and Musha substations to New Gagosi Substation	Approx. 0.2 km
3. Distribution Line (a) 15 kV distribution line (Single circuit) from New Gagosi Substation to Masaka connection point (b) 15 kV distribution line (Single circuit) from New Gagosi Substation to Nyagasambu connection point	Approx. 8.5 km Approx. 11.5 km
4. Reinforcement of Transmission Line between Birembo and Jabana Substations (a) 110 kV transmission line (Single circuit) from Birembo to Jabana Substations	Approx. 7.0 km
<u>Procurement Work</u>	
5. Maintenance Tools for the Equipment to be procured under the Project	1 lot
6. Spare parts for the Equipment to be procured under the Project	1 lot
<u>Construction Work</u>	
7. Installation of Gantries, Towers, etc.	1 lot
8. Construction of Control Building of New Gasogi Substation	1 lot
9. Civil Works	1 building

[Remark] Quantities shall be examined in the outline design.

1.4 Obligations/Undertakings of the Rwandan side for the Project

1.4.1 Preconditions

The Rwandan side has agreed to conduct the environmental and social considerations required by JICA Guidelines for Environmental and Social Considerations (2010) as well as laws and regulations in Rwanda. An Abbreviated Resettlement Action Plan (ARAP) must be implemented and the land acquisition should be completed three (3) months after the Approval of the Project by the Japanese Government. An approval on environmental clearance, such as EIA Certificate of Authorization as well as other relevant permits/licenses required for the implementation of the Project must be obtained in a timely manner to meet the Project schedule. An Environmental Management Plan (EMP), monitoring plan and impact mitigation measures must be prepared during an environmental assessment.

1.4.2 Necessary Inputs by the Rwandan side

A Before the Tender announcement

A-1 Completion of Environmental Assessment and Issue of EIA Certificate of Authorization

A-2 Preparation and Implementation of ARAP, Issue of the Land Title, Bush clearing and removal

of obstacles of the land

- A-3 Approval of the Layout plan and Line routes from the City of Kigali in the detailed design stage

B Prior to the Commencement of the Construction Work

- B-1 Site preparation work such as construction of access road, removing obstacles, tree cutting, etc. necessary for commencement of the construction work for the project components mentioned in Table 1.3-1 above.

- B-2 Temporary storage yard for equipment and materials

C During the Construction Work

[New Gasogi Substation]

- C-1 Construction of Gate and fence
- C-2 Protection Relay setting confirmation and change of the substations where the transmission lines from New Gasogi substation to be interconnected.
- C-3 Modification of SCADA System of NECC and Network Management system for accommodation of New Gasogi S/S. This modification includes the additional network connection measures of the Multiplexer/SDH panel in New Gasogi substation for the connection of new optic fiber cable.

[110 kV Transmission line (Switch over to New Gasogi)]

- C-4 Gate and Fence
- C-5 Power outage
- C-6 Removal work of the existing conductor, grounding wire, accessories, steel tower and foundation etc.

[15 kV Distribution Line (D/L)]

- C-7 Power outage
- C-8 Replacement or reconnection of the existing lines

[110 kV Transmission line (from Jabana substation to Birembo substation)]

- C-9 Power outage
- C-10 Removal work of the existing conductor, grounding wire, accessories, steel tower and foundation etc.
- C-11 Testing of communication network after installation of OPGW on 110kV transmission line between Jabana and Birembo substation

D After Handing Over

D-1 To monitor environmental and social impacts during the operation with an adaptive management approach.

2. Technical requirements confirmed in the first field survey

2.1 Technical requirements for the Substation of the Project

2.1.1 General requirement

(a) General Design Condition

Table 2.1.1-1 Basic Conditions for the Facility Design of the Project

Items		Values
Altitude		2,000 m
Ambient Temperature	Maximum	40 Degrees Centigrade
	Minimum	5 Degrees Centigrade
	Mean	20 Degrees Centigrade
Maximum Wind Velocity		30 m/s
Annual Rain Fall		1,450 mm/year
Seismic Force		Horizontal 0.10 G
Soil Bearing Capacity		Depends on the soil survey result

(b) System voltage

- 110 kV : 110 kV ± 10% (99.0 - 110 - 121.0 kV)
- 15 kV : 15 kV ± 10% (13.5 - 15 - 16.5 kV)

(c) Frequency

50 Hz ± 0.5 Hz (49.5 - 50 - 50.5 Hz)

(d) Short circuit current

According to our approximate system analysis, the following short circuit current is considered.

- 110 kV : 31.5 kA or more
- 15 kV : 25 kA or more

(e) Grounding system

- 110 kV : Solid grounding
- 15 kV : Solid grounding

(f) Pollution level for Insulator

Light (IEC-60815)

(g) Applicable Codes and Standards

As a rule, the transmission and substation system equipment shall be designed in accordance with IEC and IEC compatible standards. (JEC and so on)

ma
le
A

2.1.2 Technical requirements for the equipment of New Gasogi Substation

The following equipment shall be installed for New Gasogi Substation.

- One (1) set of 110/15 kV, 20 MVA transformer (2x15MVA)

Important note:-

110/15 kV transformer with vector group Yd11 is required by EDCL at this time, since the harmonic frequency could be suppressed by the delta winding. New Gasogi substation will be constructed between existing Ndera and Musha substations. The transformer in Ndera substation is of vector group Yy0, while the vector group Yd11 in Musha substation (30o phase angle difference). Hence, JICA study team agrees with the requirement provided that:-

“When the source of 15 kV supply is switched over from Ndera to Musha or vice versa, the switchover operation must be done after shutdown of the associated lines.”

EDCL agreed.

- 110 kV outdoor conventional type switchgear shall be installed as follows:-
 - Two (2) bays of transmission lines for Ndera and Musha substations
 - Three (3) bays of transmission lines for future installation
 - One (1) bay of 110/15 kV transformer (T1)
 - One (1) bay of 110/15 kV transformer (T2) for future installation
- Indoor type, 15 kV gas insulated switchgear with single busbar system shall be installed in the new control building.
- Control and protection equipment including Micro SCADA system
- Communication equipment for National Electricity Control Center (NECC) through existing optical fiber cables
- Entire earthing system in the substation shall be considered.
- At the time of cut-in of the 110 kV existing transmission line to New Gasogi substation, approximate 9 days shutdown shall be necessary. See SS-03 “Switchover Procedure for New Gasogi SS”, as attached.

Reference drawings:-

SS-01: Single Line Diagram for Gasogi Substation (Preliminary)

SS-02: Control and Protection System for Gasogi Substation

SS-03: Switchover Procedures for New Gasogi Substation (Draft)

mm

Q

me

Q

Table 2.1.2-1 Equipment to be provided for New Gasogi Substation

No.	Equipment	Q'ty	Unit	Major Specifications
(1)	Transformers			
a.	20 MVA, 110/15 kV Transformer	1	set	<ul style="list-style-type: none"> - 20 MVA Transformer with On-load tap changer - Primary: 110 kV +/- 13*1.23% (27 taps) - Secondary: 15 kV - Vector group: YNd11 with Earthing transformer - The mounting provisions for fans shall be made on the radiators for future 25 MVA ONAF (oil-immersed, air-forced cooled) cooling in order to increase the transformer capacity. - Fan control circuits and associated power supply circuits for ONAF cooling are provided in a local control box from the beginning. - Future parallel operation of the two transformers is considered.
b.	Earthing transformer	1	set	<ul style="list-style-type: none"> - 160 kVA Earthing transformer - Primary: 15 kV - Short-time duty (5 sec.): 1,050 A - ONAN - Vector group: ZN - CT; 15 kV, 1200/1 A, 5P20, 30 VA
c.	250 kVA, 15/0.4 kV Auxiliary transformer	1	set	<ul style="list-style-type: none"> - 250 kVA Transformer with No-load tap changer - Primary: 15 kV +/- 2*2.5% (5 taps) - Secondary: 400-230 V, Three phase, four wires - The capacity should be confirmed at the time of implementation stage, considering the auxiliary loads in the substation.
(2)	110 kV Switchgear	1	lot	<ul style="list-style-type: none"> - 2 sets of 110 kV Feeder bay 145 kV*, 31.5 kA or more - 1 set (for three phases) comprising of;- <ul style="list-style-type: none"> • Disconnecting Switch (DS) • Circuit Breaker (CB) • Current Transformer (CT) • DS with Earthing Switch (ES) • Voltage Transformer (VT) • Lightning Arrester (LA) - 1 set of 110/15 kV Transformer bay 145 kV*, 31.5 kA or more - 1 set (for three phases) comprising of;- <ul style="list-style-type: none"> • Disconnecting Switch (DS) • Circuit Breaker (CB) • Current Transformer (CT) • Lightning Arrester (LA) - 3 phases of 110 kV VT for 110 kV Busbars <p>Note*; Taking into consideration of altitude of the site (approximately 1,500 m), the rated voltage of 110 kV system shall be 145 kV.</p>

Mu *lu*

D

No.	Equipment	Q'ty	Unit	Major Specifications
				<p>Common specifications</p> <p>Rated voltage: 145 kV</p> <p>Rated current</p> <ul style="list-style-type: none"> - Busbar : 1,250 A - Transmission line bay : 1,250 A - Transformer bay : 1,250 A <p>Rated short-time withstand current: 31.5 kA (3 sec.)</p> <p>Rated lightning impulse withstand voltage: 650 kV</p> <p>Rate power frequency withstand voltage (1 min.): 275 kV</p> <p>Creepage distance: 16 mm/kV</p>
(3)	Necessary materials for 110 kV outdoor substation			
a.	110 kV busbar	1	lot	<p>Aluminum tubes for three phase busbars</p> <p>110 kV busbars are installed for all future bays, i.e., 2 x transformer bays and 5 x transmission line bays</p> <p>Note; The conductor fittings on the busbars for future bays should be provided.</p>
b.	Gantry towers	1	lot	Dead-end gantry towers for 3 circuits of 110 kV transmission line bays
c.	Insulators	1	lot	Support insulators for 110 kV busbar and transmission line wires at gantry towers
d.	110 kV conductors and fittings	1	lot	<ul style="list-style-type: none"> - 2 sets for 110 kV transmission line bays - 1 set for 110/15 kV transformer bays - 1 set for 110 kV busbars
e.	Other necessary materials	1	lot	Foundations for equipment, Supporting structures and other necessary materials
(4)	15 kV Gas insulated switchgear with single busbar	1	lot	<ul style="list-style-type: none"> - 1 set of 110/15 kV transformer bay 36 kV*, 1,250 A, 25 kA or more - 7 sets of feeder bays 36 kV*, 1,250 A, 25 kA or more - 1 set of Auxiliary transformer bay 36 kV*, 630 A, 25 kA or more - 2 sets of Busbar connection bays 36 kV*, 1,250 A, 25 kA or more - 1 set of Voltage transformer bay 36 kV*, 25 kA or more <p>Note*; The rated voltage of 15 kV system shall be 36 kV, since the distribution voltage of the whole country is 30 kV, while that in Kigali city is 15 kV.</p> <p>Common specifications</p> <p>Type: Indoor type, SF6 gas insulated metal-clad switchgear (GIS)</p> <p>Rated voltage: 36 kV</p> <p>Rated current</p> <ul style="list-style-type: none"> Busbar : 2,500 A 20 MVA transformer : 1,250 A 15 kV feeder : 1,250 A Aux. transformer : 630 A <p>Circuit breaker (CB)</p> <p>Type: VCB</p>

No.	Equipment	Q'ty	Unit	Major Specifications
				Rated interrupting current: 25 kA Auto-reclosing: 3 phase reclosing Operating duty: O-3 sec.-CO-3 min.-CO Rated short-time withstand current: 25 kA (3 sec.) Rated lightning impulse withstand voltage: 170 kV Rated power frequency withstand voltage (1 min.): 70 kV
(5)	110 kV Control and protection Transmission lines	1	lot	For two (2) circuits - Bay control units (ABB REF 670 or equivalent) - Protection relays (Areva P545 or equivalent)
	20 MVA transformer	1	lot	For one (1) transformer - On-load tap change control - Bay control unit (ABB RET 670 or equivalent) - Transformer differential protection relays
	15 kV Control and protection	1	lot	For all 15 kV feeders including 20 MVA and Auxiliary transformers - Bay control unit (ABB REF 670 or equivalent)
(6)	Micro SCADA system	1	lot	- Server and Client (Workstation HMI) with bay control unit (BCU) system for control and supervising of the whole substation - Remote Terminal Unit (RTU) and/or gateway system for communication with the existing National Electricity Control Center (NECC) SCADA system (ABB RTU 560 or equivalent)
(7)	Communication System	1	lot	The communication system includes;- - SDH multiplexer panel (including ECI NPT-1200 or equivalent) - IP PBX equipment with telephone sets - Cables including optical fiber cables for the substation inside
(8)	Substation AC power supply system	1	lot	400/230 V AC distribution panel(s) Molded-case circuit breakers (MCCB) for 400/230 V AC, three phase, four wires, with 10% spare MCCBs
(9)	Substation DC power supply system			
	a. 110 V DC system - Charger	1	lot	Thyristor rectifier system, Dual charger system Input; 400/230 V AC, Output; 110 V DC
	- Battery	1	Lot	Valve regulated lead acid (VRLA) type or equivalent 300 Ah/10 Hr (The capacity shall be confirmed at the time of implementation, using actual auxiliary loads in the substation.)
	- Distribution panel(s)	1	lot	MCCBs for 110 V DC with 10% spare MCCBs
	b. 48 V DC system - Charger	1	lot	Thyristor rectifier system, Single charger system Input; 400/230 V AC, Output; 48 V DC Valve regulated lead acid (VRLA) type or equivalent 100 Ah/10 Hr (The capacity shall be confirmed at the time of

No.	Equipment	Q'ty	Unit	Major Specifications
	- Battery	1	lot	implementation, using actual auxiliary loads in the substation.) Valve regulated lead acid (VRLA) type or equivalent 100 Ah/10 Hr (The capacity shall be confirmed at the time of implementation, using actual auxiliary loads in the substation.)
	- Distribution panel(s)	1	lot	MCCBs for 48 V DC with 10% spare MCCBs
(10)	Uninterruptible Power Supply (UPS)	1	set	- For Micro SCADA equipment - Input voltage: 400/230 V AC, three or single phase - Output voltage: 230 V AC, single phase - The back-up time is at least 1 hour.
(11)	15 kV power cables	1	lot	15 kV power cables and necessary accessories for connection - 15 kV cables between 110/15 kV transformer and 15 kV switchgear (incoming circuit) - 15 kV cables between 110/15 kV transformer and Earthing transformer - 15 kV cables between 15 kV switchgear panels and first 15 kV distribution tower(s) and/or pole(s)
(12)	Low voltage power and control cables	1	lot	- Necessary low voltage power and control cables and necessary accessories for connection
(13)	Earthing system in the substation	1	lot	- Earthing conductors and accessories - Overhead grounding wires for new 110 kV switchgear and transformer area

2.1.3 Technical requirements for the equipment of existing Jabana Substation

Taking the opportunity of the replacement of 110 kV transmission lines between Jabana and Birembo substations, the basis of the work is described as below.

- Since the associated Circuit breaker (CB)* and busbar side Disconnecting switch (DS)* are made in 1986, the equipment should be replaced with new ones.
- Some part of conductors in this bay (Birembo line) should be replaced with bigger conductors.
- Dead-end tower for Birembo line should also be replaced due to the existing tower distorted.
- The foundations of the equipment and the gantry tower are newly provided.
- The other existing equipment such as CT, VT and line side DS are utilized as they were installed in 2008.
- Since the existing control and protection cables between the equipment and the existing control room should be used, an interconnection marshalling box is installed close to the existing CB and DS, and new control cables are connected to the marshalling box from newly installed CB and DS. The restoring tests of the circuits of CB and DS as listed below should be done at the existing control room after the installation of the equipment.
 - ✓ Control and protection circuits
 - ✓ Interlock circuits
 - ✓ Alarm circuits, and other circuits if any

- AC/DC power for new equipment should be supplied by the existing power supply system.

Reference drawings;

SS-04: Single Line Diagram for Jabana Substation

SS-05: Consideration for modification works of Jabana/Birembo substation

Table 2.1.3-1 Replacement Equipment List at Jabana Substation

No.	Equipment	Q'ty	Unit	Major Specification
(1)	110 kV gas circuit breaker	1	set	Rated voltage : 145 kV Rated current : 2,500 A Rated interrupting current : 40 kA Rated short-time withstand current : 40 kA (3 sec.) Rated impulse withstand voltage : 650 kV Rated power frequency withstand voltage: 275 kV Single auto-reclosing : Yes Operating duty: O-3 sec.-CO-3 min.-CO
(2)	110 kV Disconnecting switch	1	set	Rated voltage : 145 kV Rated current : 1,250 A Rated short-time withstand current : 31.5 kA (3 sec.) Rated impulse withstand voltage : 650 kV Rated power frequency withstand voltage : 275 kV
(3)	Necessary materials for 110 kV substation			
a.	110 kV conductors and fittings	1	lot	Type AAC, 300 mm ² for 3 phase
b.	Gantry towers	1	set	Dead-end gantry towers for 110 kV Birembo transmission line
c.	Insulators	1	lot	Insulators for 110 kV conductors and transmission line wires at the gantry towers
d.	Supporting structures	1	lot	Supporting structures for CB and DS
e.	Foundations	1	lot	Foundations for CB, DS and Dead-end gantry tower
f.	Other necessary materials	1	lot	Compression terminals, terminals for earthing system and other necessary materials
(4)	All other materials			
a.	Cabling materials	1	lot	Conduits, Cabling materials and other necessary materials
b.	Low voltage cables	1	lot	600 V XLPE cables Control cables with shield Crimp terminals and other necessary materials for cabling

2.2 Technical requirement for Transmission and Distribution Lines

2.2.1 Technical requirement for Transmission and Distribution Lines

(1) Scope of Work

Scope of the work for transmission and distribution lines is shown in GA-01 Site Location Map in the Drawings.

a) 110 kV Transmission Line at Gasogi substation

New Gasogi substation will be energized from existing 110 kV transmission line between Birembo (Ndera) substation and Musha substation. The existing suspension tower No. 217 on the transmission line shall be dismantled and new dead end type towers No.217A and No.217B shall be erected between No.216 and No.218, one is for Birembo (Ndera) line and the other one is for Musha line, refer to attached drawing TL-01.

b) 110 kV Transmission Line between Birembo substation and Jabana substation

Current capacity of existing 110 kV line between Birembo substation and Jabana substation will be upgraded by constructing new 110 kV transmission line within the existing right of way including towers and foundations using new conductor ACSR-240mm², refer to attached drawing TL-02. Existing towers and foundations shall be removed by the responsibilities of EUCL.

c) 15 kV Distribution Line: North Route from New Gasogi substation

15 kV distribution line: North route with single circuit from New Gasogi substation to Nyagasambu existing dead end tower as shown in the drawing DL-01 will be constructed, the line length is approx. 11.5 km. Support structure of the 15kV distribution line shall be steel tower and/or steel pole types, refer to the drawing DL-03 with triangle conductor configuration.

d) 15 kV Distribution Line: South Route from New Gasogi substation.

15 kV distribution line: South Route with single circuit from New Gasogi substation to existing 15 kV distribution line at Masaka hospital connection point as shown in the drawing DL-02 shall be constructed. The line length is approx. 8.5 km. Support structure of this line is same as c). This 15 kV Distribution line shall also be used for 30 kV distribution line.

(2) Design Conditions for 110 kV Transmission (T/L) and 15 kV Distribution Lines (D/L)

Natural Conditions and Electrical Conditions are shown in Table 2.2.1-1 and Table 2.2.1-2, respectively.

mu

\$

he

\$

Table 2.2.1-1 Natural Conditions

Items	Design Values
Altitude	Over 1000m up to 2000m
Conductor temperature	-
Minimum temperature	5 degree Centigrade
Everyday temperature	25 degree Centigrade
Maximum temperature	80 degree Centigrade
Sag calculation to determine steel tower height	50 degree Centigrade
Wind speed	30 m/s
Wind load on conductors	552 Pa
Wind load on steel tower	1,599 Pa
Soil bearing capacity	Depends on the soil survey result

Table 2.2.1-2 Electrical Conditions

Items	Design Value
Standard Span Length	350m to 500m for 110kV T/L, 250m for 15kV D/L
Wind Span	350m to 500m for 110kV T/L, 250m for 15kV D/L
Vertical component of the conductor & G.wire	15% of Max Working Tension
Right of Way (ROW)	- 110kV T/L: 15m width (7.5m +7.5m) - 15kV D/L for double circuits: 10m width (5m +5m) - 15kV D/L for Single circuit: 6m width (3m +3m)
Height of conductor - See Note b) -	
General area (m)	7 m
Waterway (m)	10 m
to Road crossing (m)	8 m
Shield angle for Lightning	30 degree
Minimum nominal specific creepage distance	16 mm/kV
Equivalent salt deposit density	0.063 mg/cm ²

Note:

- As EUCL's concept, facility for 15kV distribution line shall be designed usable for 30kV distribution line.
- To decide standard tower height, conductor height of 8 meters shall be employed.

(3) Requirements for 110 kV Transmission and Distribution Lines

Specifications for 110 kV Transmission and Distribution Lines are shown as follows.

Table 2.2.1-3 Specifications for 110kV Transmission Line

No.	Items	Specifications
1)	Line Structure	<p>For New Gasogi sub station</p> <p>Type: Steel lattice type tower</p> <p>Configuration of tower: Single circuits, Horizontal layout (See DWG. TL-03)</p> <p>Type of tower: Dead end type (110D1H: Angle: 90 degree),</p> <p>Safety factor: 1.0 for main body 1.2 for arms</p> <p>For Jabana substation to Birembo substation</p> <p>Type: Steel lattice type tower</p> <p>Configuration of tower: Single circuits, Triangle layout (See DWG. TL-04)</p> <p>Type of tower: Suspension tower 110-A1 Light angle tower (long span) 110-B1</p>

No.	Items	Specifications
		Middle angle tower 110-C1 Dead end tower (Straight) 110-D1-1 Dead end tower (Right angle) 110-D1-2 Safety factor: 1.0 for main body 1.2 for arms
2)	Overhead Line (Conductor)	Type: ACSR-240/26/7 Size: $\phi 21.8 \text{ mm}$ $w = 0.976 \text{ kg/m}$ Right hand ray
3)	Insulator	Standards: IEC60383-1 or equivalent Size: 254 mm suspension insulators Creepage distance: 292 mm Material: Porcelain Color: Brown Ball and socket coupling: 16mm Number of insulators: 9 pcs/phase (Double or Single)
4)	Shield Wire and Optical Fiber Cable	Type: OPGW-100mm ² SM24 x 1 Number of Optic Fiber Core: 24 cores Shielding angle: less than 30 degree.

Table 2.2.1-4 Specifications for 15kV Distribution Line

No.	Items	Specifications
1)	Line Structure	Type: Steel lattice type tower and/or Steel Pole Configuration of tower: Single circuit, triangle layout for tower and for steel pole
2)	Overhead Line (Conductor)	Type: ACSR Size: 120/20, DIN
3)	Insulator for Tower	Specification : Same as 110kV Transmission Line but electromechanical Failing Load is 70kN Number of insulators: Four (4) units/string :
4)	Insulator for Pole	Type: Pin type on cross arm
5)	Shield Wire	Type: OPGW-50mm ² Number of Optic Fiber Core: 24 cores Shielding angle: less than 30 degree.

2.2.2 Technical requirements for the Foundation of Transmission and Distribution Lines

(1) Requirements for the Facilities

Necessary land development including Access Road, Earth wall, Land Leveling, Boundary Fence would be constructed by the Rwanda side.

1) Foundations for Towers of 110 kV Transmission lines

The Outline of the foundations for Towers 110 kV Transmission Lines is shown in Table 2.2.2-1.

Table 2.2.2.1 Outline of the Foundations of 110 kV Transmission Line Tower

Items	Contents	Details
Structure	Reinforced Concrete Foundation (Pad & Chimney Type)	Stability by the result of soil investigation report. Safety factor : 2.0 for stability calculation Reinforcing Bar : Deformed Bar : Mild steel Required strength of concrete : 20N/mm ²

2) Foundations for Towers of 15 kV Distribution lines

The Outline of the foundations for Towers 15 kV Distribution Lines is shown in Table 2.2.2-2.

Table 2.2.2-2 Outline of the Foundations of 15 kV Distribution Line Tower

Items	Contents	Details
Structure	Reinforced Concrete Foundation	Stability by the result of soil investigation report. Safety factor : 2.0 for stability calculation Reinforcing Bar : Deformed Bar ; Mild steel Required strength of concrete : 20N/mm ²

(2) Detail procedure of the work

Work shall be performed with maximum care to avoid collapse of existing towers during construction. To apply adequate work procedure is essential.

Some of the preparatory work has to be done with energized condition. Maximum care is deemed to be necessary in order not to make electrical accident.

To minimize the shutdown duration, it is essential to plan and apply parallel works as much as possible.

Followings are the tentative work procedure.

For new Gasogi substation: See drawing SS-03

For Jabana substation to Birembo substation 110 kV line: See drawing TL-05

2.3 Environmental and Social Consideration

The following table shows a schedule for EIA and ARAP, which was agreed upon between EDCL and JICA Preparatory Survey Team. The detail explanation is described in Table 2.3-1 and 2.3-2 below. During all the work of EIA and ARAP, EDCL should work in collaboration with a local consultant hired by JICA Preparatory Survey Team and facilitate them in accessing necessary data and information to carry out their tasks.

Table 2.3-1 Schedule of Environmental Assessment and Preparation of ARAP

Items	Activities	Organizations in charge	2017				2018
			Jun.	Jul.	Aug.	Sep.	May
Environmental Assessment	Submission of project brief to RDB for screening	EDCL/JICA/ Local consultant	█				
	Issue of screening results	RDB		█			
	Further environmental study (if required)	EDCL/ Local consultant		█	█		
	Submission of EIA report to RDB	EDCL/ Local consultant			█		
	Issue of EIA Certificate of Authorization	RDB				█	
Preparation of ARAP	ARAP study	EDCL/ Local consultant			█	█	
	Submission of ARAP to JICA Study Team	EDCL/ Local consultant				█	
	Approval of ARAP by EDCL	EDCL				█	
Implementation of ARAP	Completion of land acquisition/ compensation	EDCL					█
Others	Mobilization of a local consultant	JICA/ Local consultant	█	█	█	█	

Note: Implementation of ARAP should be fully completed within three months after the approval of the Project by the Japanese Government.

2.3.1 Environmental Impact Assessment

In line with the Environmental Impact Assessment (EIA) Guideline (*General Guidelines and Procedure for Environmental Impact Assessment, 2006*), EDCL submitted the Project Brief to Rwanda Development Board (RDB) on 12 June 2017. RDB will determine whether the Project requires a full EIA and issue screening results to EDCL within 2 weeks after the submission. EDCL should keep close communication with RDB, including conducting site inspection, so that RDB can have sufficient information for screening.

In accordance with screening results from RDB, a further environmental study or a full EIA study will be carried out; if required, EDCL should submit an EIA report by 4 August 2017 with the support of a local subcontractor. It is expected that RDB will issue the EIA Certificate of Authorization by the end of August 2017 (Review process of an EIA report by RDB will take 20 days).

2.3.2 Abbreviated Resettlement Action Plan

JICA Preparatory Survey Team conducted the site visit with EDCL, and confirmed that the Project would require land acquisition and resettlement to some extent. Based on the JICA Guideline (2010), EDCL is required to prepare an abbreviated resettlement action plan (ARAP). ARAP should be finalized and authorized by EDCL by 15 September 2017.

According to the Guideline of Right-of-Way (*Guideline No.01/GL/EL-EWS/RURA/2015 on Right-of-way for Power Lines, 2015*), the following principles are applied for newly-constructed 15 kV distribution lines (Gasogi-Nyagasambu/ Gasogi-Masaka):

- Right-of-Way of 15kV electrical lines is **12m width (6m + 6m)**.
- Any permanent building such as houses and shops is not permitted on the Right-of-Way.

Based on the discussion with Rwanda Utilities Regulatory Authority (RURA) on 21 June 2017, EDCL agreed and stated that the following criteria of resettlement and land acquisition are applied for reinforcement of existing 110kV transmission line between Birembo and Jabana Substation:

Table 2.3-2 Rights-of-Ways, Criteria for Land Acquisition and Resettlement

No.	Items	Right-of-Ways, Criteria for land acquisition and resettlement
1.	Right-of Ways	110 kV transmission line: 25m width (12.5m +12.5m)
2.	Land acquisition	Lands are required only where towers will be erected.
3.	Resettlement of structures lived or used by people such as houses , shops etc.	A minimum vertical clearance from the lowest conductor to the top of structures is 5m . Structures within Right-of-Way that do not meet the above minimum clearance, meaning the distance between the lowest conductor and the top of structures is less than 5m, are subject of resettlement.
4.	Resettlement of trees	All trees within the above Right-of-Way must be removed.
5.	Resettlement of other objects	Other objects within the above Right-of Way not meeting the minimum clearance (5m) will be evaluated based on social impacts and safety.

Once the exact coordinates of towers are finalized, EDCL should conduct site visit with the local sub-contractor. In case involuntary resettlement is predicted due to the Project, EDCL should avoid

or minimize the impacts, exploring all viable alternative routes.

The schedule of land acquisition agreed upon between EDCL and JICA Preparatory Survey Team is shown in the table below. For the smooth implementation of the project, EDCL agreed to complete all the land acquisition as well as compensation process within three months after the approval of the Project by the Japanese Government.

Table 2.3-3 Schedule of Land Acquisition after ARAP Preparation

Stage	Responsible bodies	Actions	Timeframe
6. Submission of the Payment order to MINECOFIN	From EDCL Finance Department to MINECOFIN	From EDCL finance department, the Payment order and the original compensation forms are forwarded to the Ministry of Finance for Payment.	By October 31, 2017
7. Payment process by MINECOFIN	From the MINECOFIN to the National Bank of Rwanda	MINECOFIN submits the Payment Order to the National Bank of Rwanda. The Payment by the National Bank of Rwanda through PAPs' respective Bank accounts.	November to December, 2017
8. Relocation of PAPs	PAPs/ EDCL	The PAPs will be relocated.	January to March, 2018
9. Land title request	EDCL/ Kigali City	EDCL will submit request for transfer of land title to Kigali City	April, 2018 (Within 3 months after the approval of the Project by Japanese Government)



Project site (area to require land acquisition due to the construction of a new Gasogi Substation)



Houses to be affected by the transmission line (Jabana- Birembo)

[Handwritten signature]

[Handwritten signature]

[Handwritten mark]

2.4 Procurement Plan of Spare Parts and Maintenance Tools

Capability of sustainable operation and maintenance for the equipment of the Project by the Recipient is one of conditions for the Japan's Grant Aid. The Rwandan side shall keep operation and maintenance for the equipment of the Project properly by himself, including procurement of spare parts. On the other hand, the warranty period for the Project is 1 year after insurance of the completion certificate in case of the Japan's Grant Aid. To secure operation and maintenance for the equipment of the Project for the warranty period, the Spare parts required for the period shall be provided as the scope of the Japanese.

Possession of maintenance tools for proper operation and maintenance for the equipment of the Project by the Recipient is one of conditions for the Japan's Grant Aid. However, the special tools required for operation and maintenance of the equipment of the Project shall be provided as the scope of the Japanese.

Spare parts and maintenance tools listed in Table 2.4-1 and Table 2.4-2 are recommended to be procured. More detailed parts, tools, test equipment and the quantity will be explained in the Draft Final Report.

Table 2.4-1 Recommended Spare Part List

Legend; pc: piece, ea.: each, N.A.: Not applicable

Name of Spare Parts	Quantity	
	Gasogi	Jabana
1. 110 kV Switchgear equipment		
1.1 Circuit Breaker		
(1) Closing coil	1 pc	1 pc
(2) Tripping coil	1 pc	1 pc
1.2 Disconnecting Switch (DS)		
(1) Fixed and moving contact (3 phase set for DS)	1 set	1 set
(2) Fixed and moving contact (3 phase set for Earthing switch)	1 set	N.A.
1.3 Transformer		
1.3.1 110/15 kV Transformer		
(1) Gasket (complete set)	1 set	N.A.
(2) Buchholz relay set	1 set	N.A.
(3) Oil temperature indicator (main tank and conservator)	1 pc ea.	N.A.
(4) Oil level indicators (main tank and conservator)	1 pc ea.	N.A.
(5) Silica gel for Breathers	200%	N.A.
1.3.2 15/0.4 kV Transformer		
(1) Oil temperature indicator	1 pc	N.A.
2. 15 kV Switchgear equipment		
(1) Closing coil	1 pc	N.A.
(2) Tripping coil	1 pc	N.A.
(3) Vacuum bulbs complete with necessary accessories for replacement (for three phase)	1 set ea.	N.A.

Name of Spare Parts	Quantity	
	Gasogi	Jabana
(4) Isolating main terminals (completed one pole)	1 set ea.	N.A.
(7) Fuse (each type)	100%	N.A.
(8) Meter (each type)	1 pc ea.	N.A.
(9) Auxiliary relay (each type)	1 pc ea.	N.A.
(10) Necessary accessories for 15 kV cable	1 set	N.A.
3. Control and Protection		
(1) Protection relay (each type)	1 pc ea.	N.A.
(2) Bay control unit	1 pc ea.	N.A.
(3) Fuse (each type)	100%	N.A.
(4) Meter (each type)	1 pc ea.	N.A.
(5) Auxiliary relay (each type)	1 pc ea.	N.A.
(6) Control and selector switch, if any (each type)	1 pc ea.	N.A.
4. Station LV Power Supply Equipment		
4.1 AC Distribution Board		
(1) MCCB (each type)	1 pc ea.	N.A.
(2) Indicating lamp, if any (each type)	100%	N.A.
(3) Fuse (each type)	100%	N.A.
(4) Meter (each type)	1 pc ea.	N.A.
4.2 DC Distribution Board		
(1) MCCB (each type)	1 pc ea.	N.A.
(2) Indicating lamp, if any (each type)	100%	N.A.
(3) Fuse (each type)	100%	N.A.
(4) Meter (each type)	1 pc ea.	N.A.
4.3 Battery and Charger		
(1) Battery	2 cells ea.	N.A.
(2) Electrolyte (20 liter/tank)	1 tank	N.A.
(3) Control Card and diode module	1 pc ea.	N.A.
(4) Indicating lamp, if any (each type)	100%	N.A.
(5) Fuse (each type)	100%	N.A.
(6) Meter (each type)	1 pc ea.	N.A.
4.4 Uninterruptible power supply system		
(1) Battery	2 pc ea.	N.A.
(2) Pulse generator	1 pc ea.	N.A.
(3) Thyristor stack	1 pc ea.	N.A.
(4) MCCB	1 pc ea.	N.A.
(5) Indication lamp (each type)	100%	N.A.
(6) Fuse (each type)	100%	N.A.
(7) Meter (each type)	1 pc.ea.	N.A.

Name of Spare Parts	Quantity	
	Gasogi	Jabana
5. Communication		
(1) RTU card and/or NPT-1200 Communication card	1 pc ea.	N.A.
(2) Cards for IP Media Gateway	1 pc ea.	N.A.

2.5 On-the-Job Training (OJT)

On-the-job training (OJT) shall be carried out during the construction period. Through the OJT, maintenance and operation staff of the Rwandan side will be able to experience practical and advanced skill from Manufacturer's engineers. Contents of OJT are suggested as follows;

- Operation and maintenance on 110 kV and 15 kV substation equipment
- Protection relay setting
- Fault analysis and operation record management

2.6 Power flow analysis

(1) Power demand forecast

Power demand forecast which was conducted in a master plan study titled "Electricity development plan for sustainable geothermal energy development in Rwanda" (November 2014 by JICA) is the basis of the preparatory survey for the project. Table 2.6-1 shows the energy peak demand of each 3 scenario, High middle low case, in the master plan to be applied to the survey. Load allocation to each substation is estimated by the team based on the demand forecast described in the master plan.

Table 2.6-1 Power demand forecast (Rwanda central Area)

Year	Peak demand(MW)			Year	Peak demand(MW)		
	High	Middle	Low		High	Middle	Low
2018	122	105	81	2028	293	257	218
2019	133	114	90	2029	319	280	238
2020	145	125	100	2030	348	305	261
2021	158	137	111	2031	380	333	285
2022	173	150	122	2032	415	362	311
2023	189	165	135	2033	452	394	338
2024	206	180	149				
2025	225	197	164				
2026	246	215	181				
2027	268	235	190				

(1) Power system analysis

The necessity of new Gasogi substation and the necessity of reinforcement for transmission line between Jabana - Birembo substation are evaluated by power system analysis.

This project is aimed to assist enhancement of transmission and distribution facilities in the Kigali area to improve the serious damage to economic activity in the area by insufficient power supply capacity from power transmission/distribution facilities and aging facilities. Therefore power system analysis shall be performed with the range shown figure 2.6-1 as the target.




Figure 2.6-1 Range for power flow analysis

3. Tentative Implementation Schedule of the Project

The tentative implementation schedule is shown in Attachment-3. In case that the Project is approved by the Japanese Government, the Project will proceed as below in the earliest scenario. The installation work of the Project will start in October, 2018. It is important for both sides to understand that the Preparatory Survey is not a commitment for the future implementation of the Project.

- The Exchange of Notes between the Rwanda and Japanese Government shall be signed in March, 2018.
- The Tender Opening will be held in August 2018.
- Installation work of the Project will start in October, 2018.
- Commissioning of the Project will be in March, 2020.

4. Drawings

Part 1 General

Part 2 Substation

Part 3 Transmission and Distribution Lines


Part 4 Architectural

mb

[Handwritten signature]

he

Part1 General



GA-01 Site Location Map


Handwritten signature

Handwritten symbol

Handwritten signature

Handwritten symbol

Control System Diagram of Gasogi Substation



Drawing No. SS-03

Switchover Procedures for New Gasogi Substation (Draft)

In order to cut-in 110 kV transmission line to New Gasogi SS, 110 kV transmission line between Ndera and Musha substations needs to be shut down. This is to study the duration of shutdown including work items and the schedule for Switchover from existing substation to new substation.

[Duration of Shutdown]

About 9 days

[Procedures]

- Two additional towers should be constructed within the property of existing Gasogi substation for stringing new 110 kV conductors to new Gasogi substation. In order to minimize the the duration of shutdown of 110 kV transmission line, the foundation work and the assembling works of the lower part of new towers should be conducted even under live condition of the 110 kV transmission line.
- In order not to postpone the duration of shutdown for transmission line work, all possible works and tests of substation equipment should be done before the shutdown, except the works and tests for communication aspect through OPGW.

	Pre-works	No. of Shutdown Days on Ndera - Musha line										Remarks			
		1	2	3	4	5	6	7	8	9	10				
110 kV Transmission Line	Energized condition	Shutdown											Restored	Energized	
Transmission Line Work	- Foundation works of new Towers - Assembling Works of new Towers (Lower part) (30 days)														
Substation Work	All possible works and tests of substation equipment to be done.														

[Attachment]

- Switchover Procedure for 110 kV Transmission Line
- Switchover Procedure for Gasogi Substation


2017/6/13/8:30

EXTENSION and Update of GASOGI SUB STATION

1/8

EXTENSION and UPDATE PLAN of GASOGI SUB STATION

This plan has been made for the purpose of checking feasibility and budgeting. Therefore, this paper does not bind the contractor's free hand to apply any method as far as it is reasonable.



mu


Q







me

DETAILED WORK STEP

- 1 Work shall be performed with maximum care to avoid collapse of existing towers during construction. To achieve this, it is essential to apply each and all adequate countermeasures.
- 2 Some of the preparatory work has to be done with energized condition. Maximum care is deemed to be necessary in order not to make electrical accident.
- 3 To minimize the shut down duration, it is essential to plan and apply parallel works as much as possible.

Step	WORK CONDITION	WORK to be DONE	Remarks		(days) Expected Duration
1	Live Condition	New Foundation for Tower 227A & 227B to be constructed	Work to be done simultaneously.	Foundation shall be newly designed	30.0
2		New Tower 227A & 227B shall be erected up to the bent position		Tower shall be newly designed	
3		Stay wire foundations to be constructed at tower No.226 & No.228		Keep safety distance from energized conductor	
4		Circuit to be shut down		Need to check the capacity of stay wire foundation	
5	Shut down Condition	Existing Tower No.226 & No.228 shall be tied to the ground by stay wire	Work to be done simultaneously.	By EDUL	0.5
6		Ground wire and conductor shall be tied to the arm at tower No.226 & 228		Check necessary tension	
7		Release ground wire & conductor from suspension clamp at tower No.226, No.227 & 228		Check necessary tension	
8		Cut and unloading ground wire & conductor between tower No.226 & No.228 to the ground		Avoid unbalance tension to towers	
9				Cutting point shall be at the suspension clamp but maintain extra length in order to utilize for re connection	
10	Shut down Condition	Erect new tower No.227A & 227B up to the top.	Work to be done simultaneously.	Edge of the ground wire shall be well protected to avoid damage and water immersion	1.0
11		Dismantle upper part of existing Tower No.227.		Ground wire & conductors shall be scrapped	
12	Shut down Condition	String ground wire & conductor between Tower No.226 and tower No.227A	Work to be done at both tower simultaneously.	Use Truck Crane if available	3.0
13		String ground wire & conductor between Tower No.228 and tower No.227B		Ground wire and conductor shall be new and to be connected to the existing by sleeve at tower No.226 and No.228	
14		String ground wire & conductor between Tower No.227A and Gantry			
15		String ground wire & conductor between Tower No.227B and Gantry			
16	Re connect ground wire with connection box at tower No.226 and Gantry & at tower No.228 and Gantry	Work shall be done with care to avoid over tension to ground wire and conductors			
17	Re connect conductor at tower No.226 - Gantry - No.228 with suitable fittings				
18	Release stay wire at Tower No.226 & No.228				
19	Clear unloaded ground wire and conductor from the site				
20	Shut down to live	Energize the circuit		By EDUL	0.5
21		Dismantle existing Tower No.227 below bent point			
22	Live Condition	Stay wire foundations shall be removed at tower No.226 & No.228		By EDUL	2.0
23					
Total Expected Working days					39.0
Required Shutdown days					6.0






mm


⊗

he


11	String ground wire & conductor between Tower No.228 and tower No.227A	SHUT DOWN CONDITION
12	String ground wire & conductor between Tower No.228 and tower No.227B	



13	String ground wire & conductor between Tower No.227A and Gantry	SHUT DOWN CONDITION
14	String ground wire & conductor between Tower No.227B and Gantry	



15	Re connect ground wire with connection box at tower No.228 and Gantry & at tower No.228 and Gantry	SHUT DOWN CONDITION
16	Re connect conductor at tower No.228 - Gantry - No.228 with suitable fittings	
17	Release stay wire at Tower No.228 & No.228	
18	Clear unloaded ground wire and conductor from the site	




ma

⊗

he

⊗



Switchover Procedure for Gasogi Substation (Draft)

Step	Item	Single Line Diagram	Procedure	Necessary Time
1	Preparation Work of Existing Facilities		<p>[Shutdown of Existing Substation (SS)]</p> <ul style="list-style-type: none"> - To open CB (1) of 15 kV Feeders - To de-energize 110 kV Ndera - Musha Line (2) for Shutdown of Gasogi SS <p>[Connection change to New SS]</p> <ul style="list-style-type: none"> - To connect OPGW cable to New SS - To install and connect 15 kV Cables for all 15 kV feeders <p>[Test of Feeder Protection Relays (87L)]</p> <ul style="list-style-type: none"> - To test 87L for Ndera SS and for Musha SS, utilizing OPGW. <p>* All equipment in New Gasogi SS shall be installed and tested as much as possible before Switchover. * AC/DC supplis at this stage are fed from the temporary power supply for construction work.</p>	
2	Energization by Ndera Feeder		<p>[Preparation work before Energization of New Gasogi SS]</p> <ul style="list-style-type: none"> - To confirm all CBs, DSs to be open. - To re-confirm 2 x DS (1 & 4), ES (2) and CB (3) on Ndera feeder to be open. <p>[Energization from Ndera SS]</p> <ul style="list-style-type: none"> - Close 110 kV CB at Ndera SS for Gasogi SS. (Energization of Ndera - Gasogi feeder) <p>[Check]</p> <ul style="list-style-type: none"> - To check the voltages of Ndera feeder and the phase angles 	2 hours

Switchover Procedure for Gasogi Substation (Draft)



Step	Item	Single Line Diagram	Procedure	Necessary Time
3	Energization of 110 kV Bus		<p>[Operation of Power Receiving]</p> <ul style="list-style-type: none"> - To close DS (①) on Ndera feeder - To close DS (②) on Ndera feeder - To close CB (③) on Ndera feeder <p>(Energization of 110 kV Bus)</p> <p>[Check]</p> <ul style="list-style-type: none"> - To check the voltages of 110 kV Bus and the phase angles 	1 hour
4	Power Transmission to Musha SS		<p>[Operation of Power Transmitting]</p> <ul style="list-style-type: none"> - To close DS (①) on Musha feeder - To close DS (②) on Musha feeder - To close CB (③) on Musha feeder <p>(Power transmitting to Musha SS)</p> <p>[Check]</p> <ul style="list-style-type: none"> - To check the voltages of 110 kV Musha feeder and the phase angles 	2 hours

Switchover Procedure for Gasogi Substation (Draft)

Step	Item	Single Line Diagram	Procedure	Necessary Time
5	Energization of 110/15 kV Transformer		<p>[Operation of Transformer Energization]</p> <ul style="list-style-type: none"> - To close DS (①) on Transformer feeder - To close CB (②) on Transformer feeder <p>(Energization of 110/15 kV Transformer)</p> <p>[Check]</p> <ul style="list-style-type: none"> - To check the voltages of 15 kV side and the phase angles 	1 hour
6	Energization of 15 kV Bus		<p>[Operation of 15 kV Bus Energization]</p> <ul style="list-style-type: none"> - To close 15 kV side CB (①) on Transformer feeder <p>(Energization of 15 kV Bus)</p> <p>[Check]</p> <ul style="list-style-type: none"> - To check the voltages of 15 kV Bus and the phase angles 	1 hour

mu
⊕
lu
⊕


Switchover Procedure for Gasogi Substation (Draft)

Step	Item	Single Line Diagram	Procedure	Necessary Time
7	Power Transmission for 15 kV feeders	 <p>The diagram shows a 15 kV busbar system with two incoming feeders from Maska and Ndora. The busbar is connected to a 15/0.4 kV transformer (Tr). Below the busbar, there are four feeders and one auxiliary transformer (Aux Tr). The diagram includes circuit breakers (CB), disconnector switches (DS), and current transformers (CT).</p>	<p>[Operation of 15 kV feeder Energization]</p> <ul style="list-style-type: none"> - To close DS (①) on 15 kV Kanombe feeder - To close CB (②) on 15 kV Kanombe feeder (Power transmitting to 15 kV Kanombe feeder) <p>Same operation of the above for other 15 kV feeders.</p> <p>[Check]</p> <ul style="list-style-type: none"> - To check the voltages of 15 kV feeders and the phase angles 	2 hours
8	Energization of 15/0.4 kV Auxiliary Transformer	 <p>The diagram is similar to the one for step 7, but it highlights the auxiliary transformer (Aux Tr) and its connection to the 15 kV busbar. The auxiliary transformer is connected to the busbar through a circuit breaker (CB) and a disconnector switch (DS).</p>	<p>[Operation of Aux. Transformer Energization]</p> <ul style="list-style-type: none"> - To close DS (①) on Aux. Transformer feeder - To close CB (②) on Aux. Transformer feeder (Energization of 15/0.4 kV Auxiliary Transformer) <p>[Check]</p> <ul style="list-style-type: none"> - To check the voltages of 0.4 kV side and the phase angles 	1 hour

ma

[Signature]

[Signature]



Drawing No. SS-04 rev.0
Single Line Diagram of
Jabana Substation

- Legend**
- CB : Circuit Breaker
 - CT : Current Transformer
 - CVT: Capacitor Voltage Transformer
 - DS : Disconnecting Switch
 - ES : Earthing Switch
 - LA : Lightning Arrester
 - 21 : Distance relay
 - 25 : Synchronism Check
 - 50 : Overcurrent relay (Instantaneous)
 - 51 : Overcurrent relay (Inverse time)
 - 79 : Auto Recloser
 - 87L: Current differential relay
 - N : Neutral circuit
 - MM: Digital Multimeter

Scope of Work
(Replace)

mm

me

⊗

Drawing No.SS-05 rev.0

Consideration for modification works of Jabana/Birembo substation

Based on proposal requested by EDCL (reinforcement of existing T/L among Jabana to Birembo), Team considered of countermeasures for modification works of Jabana, Gasogi Substation.

The detail works shown as following tables.


S/S	Component	current situation	Counter measure	Others
Jabana	Gantry	At connection point between Gantry and T/L conductor, Strain of steel materials was founded (especially Conspicuous phase B) Team decided that reuse of existing gantry is difficult	<ul style="list-style-type: none"> To install new gantry near existing ones In order to avoid the influence on existing access road, New gantry is installed on the same line as existing LA 	
	Electrical Equipment	Circuit breaker and Disconnection switch (bus side) was installed at 1986. those reliability seem to low.	Improve reliability by replacement of equipment	Installation works for new foundation is as necessary
	Conductor	Size of horizontal auxiliary bus conductor between gantry and 110 kV Bus is very thin.	To updated conductor size up to 300mm ²	
Birembo	Gantry	Problematic place in not founded	N/A	
	Electrical Equipment	Circuit breaker and Disconnection switch (bus side) was updated at 2008. those reliability seem to high.	N/A	
	Conductor	Size of horizontal auxiliary bus conductor between gantry and 110 kV Bus is 300mm ² . Those size is as right	N/A	After completion of conductor reinforcement, Connection point of transmission line will be First Transmission tower,

Result of survey for specification of Jabana / Birembo Substation


S/S	Contents	Tension of gantry	Line Conductor	Line Arrestor	VT	DS (Line side)	CT	CB	DS (Bus side)	Bus pipe	備考
Jabana	Specification	None	300mm ² (※1)	None	110/√3 /0.1/√3 /0.1/3 kV	145kV 1250A 31.5kA(3s)	123kV 100/1A	145kV 2500A 40kA(3s)	None		※1: Size of horizontal auxiliary bus conductor between gantry and 110 kV Bus is very thin.
	Manufacture date	-	-	2008 (9 years)	2008 (9 years)	2007 (10 years)	2007 (10 years)	1986 (31 year)	None(※2)		※2: The team made the following consideration based on survey result. • operation voltage of Birembo line was updated 70kV to 110 kV in 2013 • By updated works, CT and LA was replaced for operation voltage increase. But CB,DS has not necessity of replacement,so that reason originally equipment still operated.
Birembo	Specification	Max 10kN	300mm ² (※3)	None	110/√3 /0.1/√3 /0.1/3 kV	145kV 1250A 31.5kA(3s)	140kV 200/1A	145kV 3150A 40kA(3s)	145kV 1250A 31.5kA(3s)	D100 t=5	※3: After completion of conductor reinforcement, Connection point of trasmission line will be First Transmission tower.
	Manufacture date	2008 (9 years)	-	2008 (9 years)	2008 (9 years)	2008 (9 years)	2008 (9 years)	2008 (9 years)	2008 (9 years)		

LEGEND


TR	Transformer
CBt	Circuit Breaker for T/A Feeder
CBS	Circuit Breaker for Intra-Feeder
DS	Disconnector
DS/E	Disconnector with Earthing Switch
CTt	Current Transformer for T/A Feeder
CTS	Current Transformer for Intra-Feeder
CVT	Capacitor Voltage Transformer
LA	Lightning Arrestor
FAU	Feeder Adaptation Unit




View A - A




View B - B



View C - C
Circuit Breaker
(Biremo line)





REGEN

- 110kV HV Lines
- 15kV MV Lines
- KC Transformers
- ⊙ Thermal power plant
- ⊙ KC Substations
- ⊙ Existing towers (No.)


Existing 110kV HV Line
(approx. 7km)

TID	Remark	X	Y	Z	TID	Remark	X	Y	Z
Gantry	Jabana1	507350.8	4790995.0	1385.3	187		510777.6	4789999.1	1422.7
176		507445.5	4790961.4	1371.3	188		511033.1	4789924.0	1409.6
177		507763.2	4790874.7	1369.0	189		511356.4	4789830.4	1384.1
178		507880.8	4790837.7	1369.4	190		511727.6	4789728.4	1397.4
179		508327.1	4790711.1	1400.1	191		511938.3	4789662.0	1411.1
180		508438.3	4790675.7	1413.2	192		512199.2	4789583.7	1434.7
181		508942.7	4790527.1	1416.3	193		512429.0	4789516.3	1424.6
182		509257.2	4790440.4	1447.6	194		513034.7	4789338.3	1425.4
183		509423.0	4790390.1	1468.5	195		513262.1	4789274.9	1457.8
184		509690.2	4790313.1	1468.9	196		513429.5	4789224.3	1462.1
185		509888.7	4790253.6	1456.2	197		513626.1	4789167.2	1463.9
186		510551.6	4790062.3	1412.5	198	Birembo SS	514034.2	4789052.2	1479.4

Existing 110kV Transmission Line from Jabana to Birembo Substation

TL-02

110 kV A1 Suspension R/03



Description	Unit	Design Value
Voltage	kV	110
Circuit	cct	1
Tower Type	-	110-A1
Wind Span	m	350
Line Angle	deg	0 - 3
Vertical Angle	$\Sigma \tan \delta$	± 0.15
CONDUCTOR		
Code	-	ACSR 240/40
Numbers	-	1
Diameter	mm	21.8
Unit Mass	kg/m	0.976
Unit Tension	N/wire	26,478
GROUND WIRE		
Code	-	OPGW-100
Numbers	-	1
Diameter	mm	14.0
Unit Mass	kg/m	0.467
Unit Tension	N/wire	20,594
Insulator		
Kind	-	250mm Suspension
Numbers	-	9 x 2 Double SUS
Weight	kg/set	180
Length	mm	2,000
Wind	N/set	488
Tower	Pa	1,599
Conductor	Pa	552
Ground Wire	Pa	552


※ Body Extension +3, +6, +9
 ※ Safety factor = 1.0 for Body, 1.2 for Arm

TL-04

A5-41

Long span Tension

110 kV B1 R/03




Description	Unit	Design Value
Voltage	kV	110
Circuit	cct	1
Tower Type	-	110-B1
Wind Span	m	500
Line Angle	deg	0 - 15
Vertical Angle	$\Sigma \tan \delta$	± 0.15
CONDUCTOR		
Code	-	ACSR 240/40
Numbers	-	1
Diameter	mm	21.8
Unit Mass	kg/m	0.976
Unit Tension	N/wire	26,478
Unbalance Tension	N/wire	7,360
GROUND WIRE		
Code	-	OPGW-100
Numbers	-	1
Diameter	mm	14.0
Unit Mass	kg/m	0.467
Unit Tension	N/wire	20,594
Unbalance Tension	N/wire	5,730
Insulator		
Kind	-	250mm Suspension
Numbers	-	9 x 2 Double TEN
Weight	kg/set	360
Length	m	3,200
Jumper Depth	m	1,600
Wind	N/set	771
Tower	Pa	1,599
Conductor	Pa	552
Ground Wire	Pa	552

※ Body Extension +3, +6, +9
 ※ Safety factor = 1.0 for Body, 1.2 for Arm

Description	Unit	Design Value
Voltage	kV	110
Circuit	ect	1
Tower Type	-	110-D1
		Line side
Wind Span	m	200
Line Angle	deg	0 - 30
Vertical Angle	$\Sigma \tan \phi$	± 0.15
		Gantry side
Code	-	ACSR 240/40
Numbers	-	1
Diameter	mm	21.8
Unit Mass	kg/m	0.976
Unit Tension	N/wire	26.478
		9.807
Code	-	OPGW-100
Numbers	-	1
Diameter	mm	14.0
Unit Mass	kg/m	0.467
Unit Tension	N/wire	20.594
		6.865
Kind	-	250mm Suspension
Numbers	-	9 x 2 TEN
Weight	kg/set	180
Length	mm	3.200
Jumper Depth	mm	1.600
Wind	N/set	386
		386
Support Insulator	mm	1,660
Weight	kg	55
Wind	N/set	170
Tower	Pa	1,599
Conductor	Pa	552
Ground Wire	Pa	552


※ Body Extension +3, +6, +9
 ※ Safety factor = 1.0 for Body, 1.2 for Arm



Description	Unit	Design Value
Voltage	kV	110
Circuit	cct	1
Tower Type	-	110-D1
		Line side Gantry side
Wind Span	m	250
Line Angle	deg	0 - 45
Vertical Angle	$\Sigma \tan \delta$	± 0.15
		Line side Gantry side
Code	-	ACSR 240/40
Numbers	-	1
Diameter	mm	21.8
Unit Mass	kg/m	0.976
Unit Tension	N/wire	26,478
		9,807
Code	-	OPGM-100
Numbers	-	1
Diameter	mm	14.0
Unit Mass	kg/m	0.467
Unit Tension	N/wire	20,594
		6,865
		Line side Gantry side
Kind	-	250mm Suspension
Numbers	-	9 x 2 TEN 9 x 2 TEN
Weight	kg/set	180
Length	mm	3,200
Jumper Depth	mm	1,600
Wind	N/set	386
Support Insulator	mm	1,660
Weight	kg	55
Wind	N/set	170
Tower	Pa	1,599
Conductor	Pa	552
Ground Wire	Pa	552

※ Body Extension +3, +6, +9
 ※ Safety factor = 1.0 for Body, 1.2 for Arm

110 kV JABANA S/S GANTRY



mm *A* *he*

Description	Unit	Design Value
Voltage	kV	110
Circuit	cct	1
Tower Type	-	GANTRY at JABANA S/S
		Line side End side
Wind Span	m	50 0
Line Angle	deg	0 - 5 0
Vertical Angle	$\Sigma \tan \delta$	0.15 0
		Line side End side
Code	-	ACSR 240/40
Numbers	-	1
Diameter	mm	21.8
Unit Mass	kg/m	0.976
Unit Tension	N/wire	9,807 150
Code	-	OPGW-100
Numbers	-	1
Diameter	mm	14.0
Unit Mass	kg/m	0.467
Unit Tension	N/wire	6,865 100
		Line side
Kind	-	250mm Suspension
Numbers	-	9 x 1 TEN
Weight	kg/set	180
Length	mm	3,200
Jumper Depth	mm	1,600
Wind	N/set	488
Tower	Pa	1,599
Conductor	Pa	552
Ground Wire	Pa	552

CONDUCTOR

GROUND WIRE

Insulator

Wind Pressure

※ Body Extension Nil

※ Safety factor = 1.0 for Body, 1.2 for Arm

me

⊕


me

⊕

Dismantle and New Construction of 110 kV Transmission Line between JABANA Sub Station and BIREMBO Sub Station

This plan has been made for the purpose of checking feasibility and budgeting. Therefore, this paper does not bind the contractor's free hand to apply any method as far as it is reasonable.


Present Situation




DETAILED WORK STEP

- 1 Work shall be performed with maximum care to avoid collapse of existing towers during construction. To achieve this, it is essential to apply each and all adequate countermeasure.
- 2 Some of the preparatory work has to be done with energized condition. Maximum care is deemed to be necessary in order not to make electrical accident.
- 3 To minimize the shut down duration, it is essential to plan and apply parallel works as much as possible.


Step	Activity	Site Condition	Work By	Cycle	Remarks	Work day (day)				
Step 1	Construct New Foundation	Energized	Japan		Construction to be in accordance with the design	150				
Step 2	Shut down the circuit	Energized to Shut down	EUCL		Under responsibility of EUCL	1				
Step 3	Set stay wire to the tower to avoid collapse of tower by unbalanced tension.	Shut down	EUCL	Repeat Step-3 to Step-12 for all string section	Check adequate stay wire tension Type to be adequate to the conductor Avoid conductor fall down to the ground Only expert shall work Set straight to the line Use adequate jig which have enough strength Use adequate jig which have enough strength Care not to give vibration to tower Watch sag not to drop the conductor	45				
Step 4	Hang snatch block									
Step 5	Release ground wire or conductor from suspension clamp and set on to the snatch block Jumper loop at the tension towers shall be open									
Step 6	Set Winch and Tensioner at the both side of tension tower.									
Step 7	Connect messenger wire of the winch to the end of the clamp									
Step 8	Connect messenger wire of the tensioner to the end of the clamp									
Step 9	Dismantle both side of tension clamp									
Step 10	Wind the conductor. Tensioner must give adequate tension to the conductor.									
Step 11	After whole conductor is rewinded, repeat the same to the next conductor (Repeat from step-4)									
Step 12	Same procedure shall be applied to the next section until to complete.									
Step 13	Disassemble stay wire, anchor and snatch block. Remove winch and tensioner from the site.									
Step 14	Dismantle existing towers Erect new towers on the new foundation Set snatch block at each tower to the string section towers						EUCL Japan	Parallel	Work to be done by EDUL Parallel work with dismantling work by EDUL	120
Step 15	Hang adequate insulator string Set winch, tensioner and conductor dram at the position						Japan	Repeat step 15 to 22	Repeat step 15 to 21 for adjacent span	Special care not to damage insulators Watch sag and tension not to drop the conductor Care not to give vibration to tower Care not to give vibration to tower Confirm necessary stay wire tension
Step 16	Pull messenger with winch until the conductor reaches the string section end tower									
Step 17	Pull the conductor by adequate tool to set the conductor tension to design value.									
Step 18	Separate the conductor from the tower									
Step 19	Remove snatch blocks, conductor dram from the tower									
Step 20	Set stay wire to the position of strung conductor and proceed the same for next conductor									
Step 21	Set stay wire at the strung conductor and proceed the same for the adjacent string span									
Step 22	Connect ground wire and conductor with jumper loop at the tension tower									
Step 23	Repeat the same procedure for all the string spans are completed									
Step 24	Disassemble stay wires Re energize the line	Shut down to Energized	EUCL	Under responsibility of EUCL	1					
Step 25	Dismantle existing foundation	Energized	EUCL	Under responsibility of EUCL	120					




- ※ Construction to be in accordance with the design, plan and profile drawings
- ※ Work shall be done with highest care with the energized conductor.



- ※ Shut down shall be done by EDCL in accordance with their procedure



- ※ Strength of stay wire and anchor shall be confirmed
- ※ Theoretically, step-3 to step-11 shall be performed between Tension tower and tension tower, however, if the distance between tension tower to tension tower is longer than the capacity of pulling machine, it is acceptable to do so between suspension towers. In this case, however, special care shall be taken to avoid unbalance tension to the towers.




⊙ = Snatch block

Handwritten signature


Handwritten mark

Handwritten mark


Step 5	Release ground wire or conductor from suspension clamp and set on to the snatch block Jumper loop at the tension towers shall be open	Shut down
--------	--	-----------




Step 6	Set Winch and Tensioner at the both side of tension tower.	Shut down
--------	--	-----------







Step-7	Connect messenger wire of the winch to the end of the clamp	Shut down
Step-8	Connect messenger wire of the tensioner to the end of the clamp	



Step-9	Dismantle both side of tension clamp	Shut down
--------	--------------------------------------	-----------



Handwritten signatures and marks:
 min A he







mm

⊙


he

⊙




mm
⊙
be

Step-18 Separate the conductor from the tower Shut down




⊙ = Snatch Block


Step-19 Remove snatch blocks, conductor dram from the tower Shut down



Step-20 Set stay wire to the position of strung conductor and proceed the same for next conductor Shut down



Step-21 Set stay wire at the strung conductor and proceed the same for the adjacent string span Shut down




mu

lee


Q

Q


Step-22	Connect ground wire and conductor with jumper loop at the tension tower	Shut down
---------	---	-----------




Step-23	Repeat the same procedure for all the string spans are completed Disassemble stay wires	Shut down
---------	--	-----------



Step-24	Re energize the line	Shut down
---------	----------------------	-----------




Step-25	Dismantle existing foundation	Energized
---------	-------------------------------	-----------



終わり

Handwritten blue scribbles and a signature.

Handwritten blue signature.



- REGEND**
- Existing 110kV HV Lines
 - Existing 15kV MV Lines
 - Existing Transformers
 - 15kV MV Line Under Construction
 - Proposed 15kV MV Line
 - New Gasogi Substation
 - New towers angle points (No.)


Proposed 15kV MV Line
(approx. 11.5km)

North Route

From Gasogi to Nyagasambu

	X	Y	X	Y
AP1	522538.1	4787464.0	AP11	527242.4
AP2	522295.0	4788668.4	AP12	527896.5
AP3	522312.3	4789119.7	AP13	528390.8
AP4	522502.5	4789633.9	AP14	528591.5
AP5	523284.6	4790097.6	AP15	529979.4
AP6	523812.6	4790072.5	AP16	530651.2
AP7	524559.8	4790249.7	AP17	530958.9
AP8	524960.7	4790197.4	AP18	530988.2
AP9	525355.4	4790160.5		
AP10	526182.7	4789942.8		

Proposed 15kV Distribution Line from New Gasogi Substation to Nyagasambu Connection Point



mu

A5-54

he

South Route		
From Gasogi to Masaka Hospital		
	X	Y
AP1	522486.0	4787420.0
AP2	522491.0	4787266.0
AP3	522524.0	4786275.0
AP4	522617.0	4785758.0
AP5	522915.0	4785130.0
AP6	522956.0	4784897.0
AP7	523271.0	4784242.0
AP8	523386.0	4783710.0
AP9	523764.0	4782816.0
AP10	523327.0	4782135.0
AP11	523334.0	4782078.0
AP12	523365.0	4781998.0
AP13	523345.0	4781635.0
AP14	523506.0	4781602.0
AP15	523706.0	4781302.0
AP16	523505.0	4780879.0
AP17	523247.0	4780775.0
AP18	523230.0	4780135.0
AP19	523421.0	4779824.0


Proposed 15kV Distribution Line from New Gasogi Substation to Masaka Hospital Connection Point

Tension Tower Type

1. Classification for Member and Bolt

Standard	Class	Members	Bolts
JIS G 3101	SS400	L45x4 - L100x10	
JIS B 1051	SS540	More than HL120x8	
	5.8		16
	6.8		20


2. All dimensions are in millimeter.



DESIGN CONDITION TABLE	
DESCRIPTION	UNIT
VOLTAJE	15 (20)
CTRCUIT	cd
WIND TOWER	15-TB1
LOAD SPAN	250
WEIGHT	350
LINE ANGLE	0 ~ 30
VERTICAL ANGLE	0.5 ~ 0.15
C.O.D.E	ACSR 120/20 (DIN)
NUMBERS	(ONE) 1
DIAMETER	mm
UNIT MASS	kg/m
UNIT TENSION	15,690 (11,000 N/m ²)
CONDUCTOR	OPGW-ACS-45-3.9
NUMBERS	(ONE) 1
DIAMETER	mm
UNIT MASS	kg/m
UNIT TENSION	11,770 (1,200 N/m ²)
INSULATORS	250mm Suspension Type
NUMBERS	4 x 2 (Double Tension)
WEIGHT	210
WEIGHT	458
CONDUCTOR	1500 (151.9kg/m)
WEIGHT	552 (56.3kg/m)
CONDUCTOR	552 (56.3kg/m)
WEIGHT	552 (56.3kg/m)

1. Standard JIS-C-127
2. Minimum Safety Factor: Body=1.0, Arm=1.2

Wire Condition Diagram




APPROVED BY	15KV	DISTRIBUTION LINE
CHECKED BY		SINGLE CIRCUIT
DESIGNED BY		TYPE 15-TB1
DRAWN BY		TOWER SKELETON DRAWING
DATE		
DRAWING No.	NE201505-2000	SCALE
		1/100
		UNIT
		mm

Suspension Tower Type

1. Classification for Member and Bolt

Standard	Class	Members	Bolts
JIS G 3101	SS400	L45x4 - L100x10	
JIS B 1051	SS540	More than HL120x8	
	5.8		16
	6.8		20


2. All dimensions are in millimeter.



DESCRIPTION	UNIT	DESIGN VALUE
VOLTAJE	kV	15 (20)
CIRCUIT	cd	1
TYPE TOWER		15-TA1
WIND LOAD SPAN	m	250
WIND LOAD SPAN	m	350
LINE ANGLE	Down	0-3
VERTICAL ANGLE	2 tan α	0.15
C.O.D.E		ACSR-120/20 (DIN)
NUMBER OF WIRE	mm	(ONE) 1
UNIT MASS	kg/m	0.362
UNIT TENSION	N/wire	15,680 (1,600 kg/wire)
C.O.D.E		OPGW-ACS-46-3.9 (ONE) 1
NUMBER OF WIRE	mm	9.6
DIAMETER	mm	0.352
UNIT MASS	kg/m	11,770 (1,200 kg/wire)
UNIT TENSION	N/wire	250mm Suspension Type
KIND		4 * 2 (Double Suspension)
INSULATOR	Numbers	120
WEIGHT	kg/seat	346 (35.3 kg/seat)
WIND	N/m	1,909 (193.1 kg/m)
CONDUCTOR	Pa	352 (35.3 kg/m)
GROUND WIRE	Pa	352 (35.3 kg/m)

1. Standard (JEC-127)
2. Minimum Safety Factor: Bolt=1.3, Arm=1.2

Wire Condition Diagram



APPROVED BY	15kV	DISTRIBUTION LINE
CHECKED BY		SINGLE CIRCUIT
DESIGNED BY		TYPE 15 - TA1
DRAWN BY		TOWER SKELETON DRAWING
DATE		
DRAWING No.	NE201505-1000	SCALE
		1/100
		UNIT
		mm

me a




he

Tension Tower Type

1. Classification for Member and Bolt

Standard	Class	Members	Bolts
JIS G 3101	SS400	L45x4 - L100x10	
JIS B 1051	SS540	More than HL120x8	
	5.8		16
	6.8		20


2. All dimensions are in millimeter.



DESIGN CONDITION TABLE	
DESCRIPTION	UNIT DESIGN VALUE
VOLTAJE	15 (30)
CIRCUIT	1
TYPE TOWER	15-TB1
WIND LOAD SPAN	250
LINE ANGLE	0-90
VERTICAL ANGLE	0-90
CONDUCTOR	ACSR 120/20 (DIN)
NUMBER	(ONE) 1
DIAMETER	15.5
UNIT MASS	kg/m
UNIT TENSION	15,600 (1,600 kgf/wire)
CODE	OPGW-ACS-46-3.3
NUMBER	(ONE) 1
DIAMETER	9.6
UNIT MASS	kg/m
UNIT TENSION	0.352
WIRE	11,770 (1,200 kgf/wire)
INSULATOR	250mm Suspension Type
NUMBER	4 x 2 (tower remain)
WEIGHT	200
WEIGHT	458 (46.7 kgf/str)
UNIT MASS	kg/m
UNIT TENSION	1,599 (163.1 kgf/m)
CONDUCTOR	552 (56.3 kgf/m)
GROUND WIRE	552 (56.3 kgf/m)


1. Standard (JIS-C-137)
2. Minimum Safety Factor: Body=1.0, Armet=1.2

Wire Condition Diagram



APPROVED BY	15KV	DISTRIBUTION LINE
CHECKED BY		SINGLE CIRCUIT
DRAWN BY		TYPE 15 - TB1
DATE		TOWER SKELETON DRAWING
DRAWING No.	NE201505-2000	SCALE
		1/100
		UNIT
		mm

Part4 Architectural




mu

⊕

de

⊕



New Gasogi Sub Station Layout plan

ma

A5-62

he

17000

77500

Boundary wall by Rwanda side

Retaining wall

Existing ground line

Soil Excavation

1642.0

Soil Back filling

Retaining wall

45°

Longitudinal Section

42700

28500

17000

Control room

Soil Back filling

Retaining wall

Existing ground line

Longitudinal Layout of the Control room and Transformer Yard

Control room and Transformer Yard


1642.0

Handwritten signature




Handwritten initials





GFL Plan



South Elevation

mm

[Signature]

he

15 kV Switchgear Room


No.	Panel Name	Note
S-1	T1 Transformer	
S-2	Bus Connection (Send)	
S-3	Busbar VT	
S-4	Kanombe (existing)	
S-5	Inyanga (existing)	
S-6	Rutunaa (existing)	
S-7	New feeder (JICA Phase-3)	
S-8	Spare feeder	
S-9	Aux. Tr	
S-10	T2 Transformer	for future
S-11	Bus Connection (Receive)	
S-12	Kabuga (JICA Phase-2)	
S-13	New feeder (JICA Phase-3)	

Control Room

No.	Panel Name	Note
C-1	Sub station control Panel-1	
C-2	Sub station control Panel-2	
C-3	15 kV Control Panel-1	
C-4	15 kV Control Panel-2	for future
C-5	110 kV Transmission line Panel-1 to Ndera	
C-6	110 kV Transmission line Panel-2 to Mushi	
C-7	110 kV Transmission line Panel-3 for future	
C-8	110 kV Transmission line Panel-4 for future	
C-9	110 kV Transmission line Panel-5 for future	
C-10	T1 Transformer Control Panel-1	
C-11	T2 Transformer Control Panel-2	for future
C-12	Telcom Panel	
C-13	Desk for SCADA	

Charger Room

No.	Panel Name
P-1	DC Distribution panel
P-2	AC Distribution panel
P-3	UPS (Inverter)
P-4	UPS (Battery charger)
P-5	UPS (Battery)
P-6	48 V DC Battery charger
P-7	48 V DC Battery panel
P-8	110 V DC No.2 Battery charger panel
P-9	110 V DC No.1 Battery charger panel
P-10	110 V Battery panel



Section A-A

PROJECT	The Project for Improvement of Substation and Distribution Network Phase 3 in the Republic of Rwanda		CONSULTANTS	YACO ENGINEERING CO., LTD. TOKYO, JAPAN		TITLE	Equipment Layout in Control Building for Gasogi Substation		DRG NO.:	
LOCATION			DESIGNED BY:	CHECKED BY:	APPROVED BY:	DATE:			SCALE:	for A4 paper

[Handwritten symbol]

he

Attachment

mm

[Signature]

1. Member List of the Study Team

First Field Survey

Name	Assignment	Organization
Tsunenari SOYAMA	Vice Team Leader	Japan International Corporation Agency
Makoto ABE	Chief Consultant/ Transmission and Distribution Planning	Yachiyo Engineering Co., Ltd.
Kenji SAKEMURA	Substation Facilities	West Japan Engineering Consultants, Inc.
Seiji SATO	Substation Facilities-2	West Japan Engineering Consultants, Inc.
Taro NAKAMURA	Power Flow Analysis/ Protection Control	West Japan Engineering Consultants, Inc.
Michio ISHIGAMORI	Transmission and Distribution Facilities	Yachiyo Engineering Co., Ltd.
Kyohei KUROHANE	Equipment Planning/ Cost Estimation	Yachiyo Engineering Co., Ltd.
Hisayuki YAMAMOTO	Facility Planning/ Cost Estimation	Yachiyo Engineering Co., Ltd.
Akihiro OSADA	Social and Environmental Considerations	Yachiyo Engineering Co., Ltd.





Work Demarcation for the Project

No.	Work Items	Japan Side		Rwanda Side	
		Provision	Installation	Provision	Installation
General					
(1)	Access road to the project sites			●	●
(2)	Temporary storage yard for equipment and materials			●	●
1. New Gasogi Substation					
(1)	Land acquisition, Bush clearing and removal of obstacles			●	●
(2)	Site leveling (Land development)	●	●		
(3)	Gate and fence			●	●
(4)	Road and parking lot in the site	●	●		
(5)	Building work of the substation (including control room, support structure, steel gantry and foundations)	●	●		
(6)	110 kV switchgear	●	●		
(7)	20 MVA 110/15 kV transformers	●	●		
(8)	160 kVA grounding (earthing) transformer	●	●		
(9)	250 kVA auxiliary transformer	●	●		
(10)	15 kV switchgear	●	●		
(11)	Substation control and protection equipment	●	●		
(12)	110 V DC battery and charger	●	●		
(13)	48 V DC battery and charger	●	●		
(14)	AC 230 V Uninterruptible Power Supply (UPS)	●	●		
(15)	Communication equipment including RTU and SDH equipment	●	●		
(16)	15kV cables between transformers and switchgear	●	●		
(17)	Outgoing 15 kV Cables	●	●		
(18)	Protection Relay setting confirmation and change of the substations where the transmission lines from New Gasogi substation to be interconnected				●
(19)	Spare parts for substation	●			
(20)	Maintenance tools for substation	●			
(21)	Technical training for equipment		●		

A2-1

A5-69

No.	Work Items	Japan Side		Rwanda Side	
		Provision	Installation	Provision	Installation
2	110 kV Transmission line (Switch over to New Gasogi)				
(1)	Land acquisition, Bush clearing and removal of obstacles, tree cutting work within the 110 kV transmission line Right Of Way			●	●
(2)	Gate and Fence			●	●
(3)	Dead end heavy angle steel towers and foundations	●	●		
(4)	Overhead conductor	●	●		
(5)	Overhead grounding wire (including OPGW)	●	●		
(6)	Connection bow for OPGW	●	●		
(7)	Power outage				●
(8)	Removal work of the existing conductor, grounding wire, accessories, steel tower and foundation etc.				●
3.	15 kV Distribution Line (D/L)				
(1)	Land acquisition, Bush clearing, tree cutting and removal of obstacles			●	●
(2)	Power outage				●
(3)	Replacement or reconnection of the existing lines			●	●
(4)	Steel towers and foundations	●	●		
(5)	Overhead conductor	●	●		
(6)	Overhead grounding wire (including OPGW)	●	●		
(7)	Switching device	●	●		
4.	110 kV Transmission line (from Jabana substation to Birembo substation)				
(1)	Land acquisition, Bush clearing and removal of obstacles and tree cutting work within the 110 kV transmission line Right Of Way			●	●
(2)	Steel towers and foundations	●	●		
(3)	Overhead conductor	●	●		
(4)	Overhead grounding wire (including OPGW)	●	●		
(5)	Connection bow for OPGW	●	●		
(6)	Power outage				●
(7)	Removal work of the existing conductor,			●	●

No.	Work Items	Japan Side		Rwanda Side	
		Provision	Installation	Provision	Installation
	grounding wire, accessories, steel tower and foundation etc.				
(8)	Reinforcement of 110kV outgoing bay at Jabana substation (Replacement of steel gantry and foundation, replacement of partial busbar conductor, and 110 kV disconnecting switch (busbar side), circuit breaker)	●	●		
(9)	Open/close operation of existing auxiliary power supply circuits for 110 kV disconnecting switch and circuit breaker				●
5.	NECC SCADA System				
(1)	Modification of SCADA System of NECC and Network Management system for accommodation of new Gasogi S/S			●	●
(2)	Testing of communication network after installation of OPGW on 110kV transmission line between Jabana and Birembo substation			●	●





Tentative Implementation Schedule of the Project

		FISCAL YEAR		2018												2019												2020						
		2017	2018	2018												2019												2020						
CALENDAR YEAR																																		
CALENDAR MONTH																																		
ACCUMULATE MONTH																																		
Item		0	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5			
Contract	Exchange of Notes for the Project		▼																															
	Grant Agreement for the Project		▼																															
	Consulting Services Agreement		▼																															
Detailed Design	Reconfirmation of the Site Situations			■																														
	Preparation of the Tender Documents (T/D)			■	■																													
	Approval of the T/D by the Rwandan side				■																													
	Announcement of the Tender					■																												
	Distribution of the Tender Documents					■	■																											
	Tender Opening							■																										
	Tender Evaluation								■																									
	Construction Contract with the Successful Tenderer									■																								
	Procurement of Equipment	Kick-off meeting with the Contractor																																
		Preparation and approval of shop drawings																																
Fabrication/procurement of the equipment																																		
Pre-shipment inspection for the equipment																																		
Transportation of equipment																																		
Installation of Equipment		I. New Gasogl S/S - Nyagasambu (Approx. 11.5km)																																
		1) Foundation work for 15 kV towers																																
		2) Installation of 15 kV towers																																
		3) Installation of 15 kV distribution line																																
		II. New Gasogl S/S - Mesaka (8.5km)																																
	1) Foundation work for 15 kV towers																																	
	2) Installation of 15 kV towers																																	
	3) Installation of 15 kV distribution line																																	
	I. New Gasogl S/S - Branch point (0.2km)																																	
	1) Foundation work for 110 kV towers																																	
2) Installation of 110 kV towers																																		
3) Installation of 110 kV transmission line																																		
II. Jabana S/S - Birembo S/S (7.0km)																																		
1) Foundation work for 110 kV towers																																		
2) Installation of 110 kV towers																																		
3) Installation of 110 kV transmission line																																		
4) Test and adjustment																																		
New Gasogl Substation	1) Building work																																	
	A Leveling work																																	
	B Control building construction																																	
	C Equipment foundation construction																																	
	D Landscaping work																																	
	2) Installation of Substation facilities																																	
	3) Test and adjustment																																	
	4) Initial operation training and Maintenance training																																	
	Before the Tender announcement	A-1 Completion of Environmental Assessment and Issue of EIA Certificate of Authorization																																
		A-2 Preparation and Implementation of ARAP, Issue of Land Title																																
A-3 Approval of the Layout plan and Line routes from the City of Kigali in the detailed design stage																																		
Before Construction		B-1 Site preparation work such as construction of access road, site leveling, removing obstacles, tree cutting, etc. necessary for commencement of the construction work																																
		B-2 Temporary storage yard for equipment and materials																																
Rwanda side		[New Gasogl Substation]																																
		C-1 Construction of Gate and fence																																
		C-2 Protection Relay setting confirmation and change of the substations where the transmission lines from New Gasogl substation to be interconnected.																																
		C-3 Modification of SCADA System of NECC and Network Management system for accommodation of new Gasogl S/S																																
		[110 kV Transmission line (Switch over to New Gasogl)]																																
	C-4 Gate and Fence																																	
	C-5 Power outage																																	
	C-6 Removal work of the existing conductor, grounding wire, accessories, steel tower and foundation etc.																																	
	[15 kV Distribution Line (D/L)]																																	
	C-7 Power outage																																	
C-8 Replacement or reconnection of the existing lines																																		
[110 kV Transmission line (from Jabana substation to Birembo substation)]																																		
C-9 Power outage																																		
C-10 Demolish work of existing transmission line (Jabana S/S - Birembo S/S)																																		
C-11 Testing of communication network after installation of OPGW on 110kV transmission line between Jabana and Birembo substation																																		
Handover																																		

Remarks Legend: ■ : Work in Japan ■ : Work in Rwanda ■ : Equipment work ■ : Work to be done by the Rwandan side