

添付資料 4.15

2017 年秋期研修「O&M of Sewer and Storm Water Drainage」の教材
















































Introduction

17/20




ADVANTAGES OF AN EFFICIENT (O&M) SYSTEM




- Full use of the system over its intended design life will be achieved.
- It will result in high reliability of equipment and facilities as designed.
- It will ensure that facilities and equipment are available as intended.
- It will maintain the value of the infrastructure investment.
- There will be a collection of accurate <u>information and data</u> on which the operation and maintenance can be planned and budgeted for.
- It will <u>reduce costs</u> since planned maintenance and repairs are much more cost-effective than late-night emergency repairs.




Introduction





jica					ALJAZARI — ACADEMY —
Module 01 (An Overview) Safety Control and Measures for Sewerage and Drainage Works No. of Topics 06 No. Lectures 09 Theory 04					
	The rest topics of the rest to		OST 03		
		Risks and hazards	Risks and hazards	Theory	
	DAY 01	associated with sewers & drains	☐ Control measures	Theory	
		☐ Safety practices for sewers & drain O&M	☐ Current safety practices in WASA & Visit to WASA Training Center	OST	
		Use of safety gears	☐ Concept of PPEs	Theory	
		Dest safety practices	☐ Working in confined spaces	OST	
		☐ Best safety practices	Tests for hazardous gases	031	
		☐ First aid	Arrangements for medical treatment	Theory	
	☐ Traffic control	☐ Identification of a specific manhole	OST		
	practice	☐ Traffic control plan	031		
					3/15



Objectives:

- To Give an overview of job related hazards & risks
- Assessment of risks at WASA work sites during O&M



Important Definitions

Hazard



A Hazard is a potential source of harm.

Risk



Risk is the likelihood that a person may be harmed.

Assessment



Identify hazards + Analyze or evaluate risk + Determine methods to control

Prioritization



Evaluating risks and ranking them in their order of severity.

Module-1 Lecture-1 Risks and Hazards

5/15





Find out the Hazards in office...








Module-1 Lecture-1 Risks and Hazards




















In the name of Allah, the most Gracious and ever Merciful






Objectives:

To aware participants about various control measures to be adopted to avoid risks during O&M



Important Definitions



Elimination Remove hazard from the workplace


> Substitution Replace hazardous materials or machines with less hazardous ones

Engineering
Design modifications to reduce the hazard

Administration
Procedure changes, employee training, signs, labels & exercise breaks

▶ PPE Protective clothing, helmets, goggles & equipment etc.

Module-1 Lecture-2 Control Measures





Control Measures during O&M:







Atmospheric Hazards:

Explosive	Toxic	Deficiency
Methane - CH ₃	Hydrogen Sulfide - H ₂ S Carbon Monoxide - CO	Oxygen - O ₂

Any space where:

- ☐ Existing ventilation is insufficient
- ☐ Oxygen is deficient
- Access is difficult
- ☐ Getting out is difficult

Module-1 Lecture-2 Control Measures

☐ Not designed for permanent dwelling

Control Measures:

- ☐ Use gas detector/monitor
- Continuous Ventilation ☐ Continuous Testing
- ☐ Self Contained Breathing Apparatus (SCBA)









ALJAZARI















Risks:

☐ Strained Muscles

Control Measures:

☐ Light Weight Ladder

□ Correct Position/Orientation

- ☐ Torn Skin
- Abrasion
- Swelling
- Puncture
- □ Fracture

□ Correct SOP



Hazards:

- ☐ Uneven Footing
- Poor Balance
- Awkward Position
- Weak Manhole Rungs
- Dropping Tool
- Sharp Objects


■ Avoid Tool Drop & Throw/Toss ☐ Ladder Drop


☐ PPE (Helmet + Goggles + Gloves + Safety Shoes)








Module-1 Lecture-2 Control Measures
















In the name of Allah, the most Gracious and ever Merciful

Module 01

Safety Control and Measures for Sewerage and Drainage Works

Topic No. 02

Risks and Hazards Associated with Sewers & Drains

Lecture No. 03

Current Safety
Practices in WASA

Theory

Lecture Breakdown

OJT

OJT Cycle for WASA Site

OJT Success at WASA Site

Current Safety Practices in WASA Pictorial...

Q&A

Duration

15 Min.





OJT...Dates Back

Module-1 Lecture-3 Current Safety Practices in WASA




On-the-Job (OJT) Training:





- 1 Training where the <u>"Trainer" instructs the new "Trainees"</u> on the skills needed to perform his/her new job effectively
- 2 Either the <u>Trainee performs the job</u> while the Trainer instructs <u>Or</u>
- The <u>Trainer performs the job</u> while the Trainee observes.
- 4 On-the-Job training should take place mostly in the <u>field</u>; however, some <u>classroom</u> training is also permissible.


Module-1 Lecture-3 Current Safety Practices in WASA





























Manhole Structural Details





















Module 01

Safety Control and Measures for Sewerage and Drainage Works

Topic No. 03

Use of safety gears during operation & maintenance of sewerage & drainage system

Lecture No. 04


Concept of Personal Protective Equipment (PPE)

Theory


Lecture Breakdown	Duration
Purpose of PPE	20 Min.
Selection of PPE	11 12 1
PPE in Details	10 2 3
Care & Maintenance	87 6 5 ⁴
Q&A	





Module-1 Lecture-4 Concept of Personal Protective Equipment (PPE)























jica					ALJAZARI — ACATEMY
	Work Sub-D Forem	SELECTION ON Site:ivision: nan:		SSMENT	
	SR. NO.	JOB	HAZARDS	PPE REQUIRED	
Modu	le-1	Lecture-4 Conc	ept of Personal Protective Equipi	ment (PPE)	11/17














Module-1 Lecture-4 Concept of Personal Protective Equipment (PPE)



Module-1 OST-1 Day/Date: Name: Visit Location: Designation: Observations 1. 2. 3. 4. 5. 6. Suggestions for Improving the Training Directorate Facilities





Safety Control and Measures for Sewerage and Drainage Works

Topic No. 04

Standard Safety Practices during Sewer and Manhole Operations

Lecture No. 05

Working in Confined Space

OJT

Lecture Breakdown

Safety Equipment & Procedures

Precautions before Manhole Entry

Procedure during Manhole Entry

While Operator is in Manhole

Special Problems relates with Manhole O&M

After Leaving the Manhole

Q&A


Module-1 Lecture-5 Working in Confined Space




Manhole - A Confined Space


2/17

1











Accident during Manhole Operation (00:04:52)





Module-1 Lecture-5 Working in Confined Space



3/14

ALJAZARI





Health Conditions of Operator:

- ✓ Be in good health
- ✓ Be in sound physical condition
- ✓ Be free from alcohol or drugs

<u>Required Tools + Materials + Equipment:</u>

- ✓ Examine the condition of all required tools
- ✓ Arrange tools & equip. so that work must be accomplished with single entry & exit

Foreman or Crew Leader should Hold Briefing

- √ To explain about HSE rules
- √ To explain the work sequence
- √ To explain SOP
















Module-1 Lecture-5 Working in Confined Space

Manhole Ei	ntry Form	
ate: Structure Entering:	Location:	
Person Entering:		
upervisor:		
-	Not Applicable	Complete
. Unit Pumped Out		
. Unit Ventilated		
. Explosive Vapors Less Than 20% Of LEL		
. Oxygen Content 19.5% Minimum		
H ₂ S Less Than 10 Ppm		
PPE and Rescue Devices		
a. Harness on Person Entering		
b. Lifeline Attached to Harness		
c. SCBA on Employee Entering		
7. Emergency Procedure Explained and Understood		
Send Original To Supervisor	Send Copy To	Safety Office







Operation of Manhole Entry

Following procedure shall be adhered to:

- ☐ Place the manhole <u>safety enclosure</u> around the manhole
- ☐ <u>Calibrate</u> the portable atmospheric monitor BEFORE removing the manhole cover
- ☐ <u>Test</u> the manhole from top to bottom for oxygen deficiency, explosive and toxic (hydrogen sulfide) gases
- Never use hands to remove the <u>manhole cover</u>
- Open manholes upstream and downstream from the work area
- Sweep the area before removing the manhole cover
- Before entering the manhole start the <u>ventilation blower</u>
- Once the operator going into the hole confirm safety harness and lifeline is attached
- ☐ Continue to use the atmospheric monitoring system

Module-1 Lecture-5 Working in Confined Space

11/17





While Operator is in Manhole

Following procedure shall be adhered to:

- ☐ The end of the lifeline must be secured outside of the confined space
- ☐ Whenever an operator is in a manhole continuously test the atmosphere
- ☐ The operator in the manhole must be observed continuously
- ☐ If there are any indications of trouble immediately remove the operator





Module-1 Lecture-5 Working in Confined Space





Special Problems of Manhole Work

Following problems may occur during working in manhole:

- ☐ Sharp odor or prolonged breathing of an odorous atmosphere will cause the sense of smell to be temporarily lost
- NEVER allow anyone to enter a manhole until the oxygen content tests greater than 19.5 percent oxygen
- ☐ Victims suffering from a lack of oxygen may require artificial respiration if the case is severe

OXYGEN DEFICIENT CONFINED SPACE



Module-1 Lecture-5 Working in Confined Space

13/17





After Leaving the Manhole


<u>Following steps should be taken after operation</u> inside manhole:

- 1. Take hot shower.
- 2. Put on clean clothes.
- 3. Don't wear the clothing worn in manhole, at home.
- 4. Never expose your family to any object which was in contact with your clothing.
- 5. No clothing should be washed with the family laundry.





Module-1 Lecture-5 Working in Confined Space





Module 01


Safety Control and Measures for Sewerage and Drainage Works

Topic No. 05
First Aid in Emergency
Situations

Lecture No. 06

Arrangements for Medical Treatment

Theory (Visual Aids)









Module-1 Lecture-6 Arrangements for Medical Treatment





Objectives

The objective of this lecture is to improve capacity of participants to render first aid in emergency situations

FIRST AID:

First aid is the assistance given to any person suffering a sudden illness or injury, with care provided to preserve life, prevent the condition from worsening, and/or promote recovery.

Module-1 Lecture-6 Arrangements for Medical Treatment

3/11





Purposes of First Aid

- 1. Prevent further injury
- 2. Preserve life
- 3. Promote recovery

Phases of First Aid

- 1. Self-aid
- 2. Assistance from a companion
- 3. Emergency treatment
- 4. Initial surgery

Module-1 Lecture-6 Arrangements for Medical Treatment






First Aid Rules







- 1. Do not get excited
- 2. Do not move injured victim unless it is necessary
- 3. Keep the victim lying down
- 4. Keep the victim warm and comfortable
- 5. Examined the victim gently
- 6. Avoid allowing the victim to see his own injury
- 7. Do not try to give any solid or liquid substance by mouth
- 8. Do not touch open wounds or burns with fingers or other objects
- 9. Seek medical attention immediately

Module-1 Lecture-6 Arrangements for Medical Treatment









Module 01

Safety Control and Measures for Sewerage and Drainage Works

Topic No. 06


Traffic Control Practice during Sewer and Manhole Cleaning Operations Lecture No. 07
Traffic Control Plan


Theory & OJT

Lecture Breakdown	Duration
Objectives	30 Min.
General Conditions	11 17 1
Traffic Control Criteria	$ \begin{array}{ccc} 10 & & 2 \\ 9 & & & 3 \\ 8 & & & 4 \end{array} $
Areas of Traffic Control	765
Traffic Control Devices	
Q&A	



Module-1 Lecture-7 Traffic Control Plan










Routing Traffic Criteria

Answers to several questions will determine traffic control criteria around the WASA work site:

- ➤ Is traffic moving at a low speed (0-60 Km/Hr.) or a high speed (60-90 Km/Hr.)?
- Is the road two-lane, one-way or two-way?
- > Is it undivided four-lane?
- > Is it multi-lane one-way?
- Are pedestrian walkways affected?
- > Is it in a residential area?
- ➤ Will a lane closure be required?
- Will more than one lane be closed?
- Will traffic control be required during peak traffic periods or at night?

Module-1 Lecture-7 Traffic Control Plan







1 - Advance Warning Area

- ☐ The purpose of this area is to <u>alert drivers</u> to activity ahead.
- ☐ Allow them enough time to alter their driving patterns prior to reaching the work area.

2 - Transition Area

☐ <u>Traffic is channeled</u> from the normal traffic lane to the path required to move it around the work area

Module-1 Lecture-7 Traffic Control Plan

7/16





3 - Buffer Space

☐ This zone provides an <u>additional margin</u> of safety for both traffic and working operators


4 - Work Area


☐ Work area is that portion of the road which contains the <u>work activity</u> and equipment, is closed to the traffic


5 - Termination Area


☐ This area provides a short distance for traffic to get clear of the work area and to return to the normal traffic lanes


Module-1 Lecture-7 Traffic Control Plan
















HSE Action Plan Module 01

ACTION PLAN DESCRIPTION OF PROBLEM Description of Problem 1 Date Major **Probable** 2 Type / Rating of Hazard Moderate Outcomes Minor **Hazard Discovered** Any 3 Through Accident Inspection **Near Miss** Other

В	IMMEDIATE ACTION						
		l	Remove Hazard	How?			
	lake immed	diate Action	Isolate Hazard	How?			
1			Restrict the Access	How?			
	Date of Response		Erect Signage	How?			
			Any Other	How?			
2	Finding Root Cause		Apply "5Whys" Methodology				
	Contributing Reasons / Causes		Lack of Training	Un-Safe (O&M Method	Ignorance	
3			No Use of PPE	Lack of Proper Tools		Willful Misconduct	
			Improper House Keeping	Improper Maintenance		Any Other	

C - Action Plan Template													
	1	2	3	4		5		6	7				
Sr. No.	WHAT TO DO?	HOW TO DO?	WHEN TO DO?	wно то	DO?	DO WITH V	WHAT?	CHECK DONE?	WHO TO CHECK?				
	Preventive	(Follow	(Frequency)	(Carried	out By)	Materials	Tools/					How to Check?	Effectiveness to be Checked
	Action	SOP)		Class of Work	Worker		Equip.	p.	By?				

	- Action i la	n Template	C- Action Plan Template							
Sr. Due Date No.	Date Complete	Date Verified	Any New Risi Developed	k / Hazard						
D- SIGNATURES										
Implementer Name		:	Signature							
Authority Title		:	Signature							

O&M of Drainage System



O&M of Drainage System

- Components
- ➤ O&M Objectives

Strategy for Improvement

- Sensitizing Senior Decision Makers
- Assessing the Existing Facilities
- ➤ Identification of Factors affecting Quality of Maintenance
- > Snags in Management
- Immediate Action Plan
- ➤ Long term Action Plan







Course

Operation and Maintenance (O&M) of Sewer & Storm Water Drainage System including Safety Precautions

Module 2

O&M of Storm Water Drainage System

Lecture 1

Need for O&M of Storm Water Drainage System

Module-2 Lecture-1




Lecture Contents



- 1. Storm Water Drainage System and its Components
- 2. Current Issues
- 3. Sediment Deposition
- 4. Need for O&M
- 5. Maintenance of Drains



Module-2 Lecture-1





Culvert



- □ A drainage pipe used to convey a stream through a road or embankment
- ☐ It may carry a stream for a long distance underground to a surface discharge location
- ☐ Short in length and open at both ends and often must withstand substantial traffic loads





Module-2 Lecture-1

5/15

Ditch

- ☐ Ditches are constructed to convey water from storm runoff to an adequate outlet.
- ☐ A good ditch is shaped and lined and does not cause flooding, erosion, or sedimentation.



Gutter



■ That portion of the roadway section adjacent to the curb which is utilized to convey storm water runoff.

Module-2 Lecture-1



Drop Inlet





A location where storm water runoff from an open area enters the storm drain system.



Drop inlets are usually part of the public drainage system, but can sometimes be considered private.

Module-2 Lecture-1

7/15




Catch Basin




A structure in the form of a chamber which is provided along with the sewer line to admit clear rain Water free from silt, grit, debris, etc, into the combined sewer

Allows rainwater runoff to be safely collected to prevent road and property flooding



Module-2 Lecture-1








Sediment Deposition & Related Issues



Due to the sediment deposition the problems occurred in the **open channel** includes:

- Encourages prolific weed growth
- ☐ Cause flooding of various degrees of magnitude
- Ponding of water creates breeding grounds for some disease causing agents
- Silted roadside drains produce ponding on roads



Module-2 Lecture-1

11/15



Sediment Deposition & Related Issues



In the case of **buried or completely covered** storm channels, problems occurred are:

- ☐ Silting + Weed Growth + Bushes
- Release & accumulation of gases (that can be highly corrosive to the channel material)



Module-2 Lecture-1



Need for Maintenance



Lack of regular maintenance cause the accumulation of the sediment and garbage in the drain

Extensive, regular sediment removal is a difficult and expensive process

Routine inspection and preventive maintenance are the best ways to prevent blockages and deterioration of drains

Module-2 Lecture-1

13/15



O&M of Drainage System



Departments should devise maintenance procedures including:

- Frequency of inspection
- Programme for dredging
- Necessary repair works
- Documentation for maintenance records



Module-2 Lecture-1









Course

Operation and Maintenance of Sewer & Storm Water Drainage System Including Safety Practices

Module 2

Operation and Maintenance of Storm Water Drainage System







Hydraulic Excavator



- Excavators (Hydraulic Excavators) are heavy construction equipment consisting of a boom, dipper (or stick), bucket and cab on a rotating platform known as the "house"
- All movement and functions of a hydraulic excavator are accomplished through the use of hydraulic fluid, with hydraulic cylinders and hydraulic motors



Module-2 Lecture-2

5/15



Excavation Buckets





Digging Bucket

- Excavates materials using a pulling movement
- It is often implemented to remove thin layers of silt



Dredging Bucket

- Slightly different from standard buckets
- Characterized by holes that retain silt while allowing water to escape



Visor Bucket

- Traditional excavation bucket
- Excavate thin and very dense layers with low water content

Module-2 Lecture-2



Excavation Buckets



Clamshell

- Operates using a gripping movement
- Excavate thick layers of silt and for transferring materials
- □ Layer thickness must be at least 0.5 m in order to achieve reasonable productivity



Environmental Grab Bucket

- ☐ An alternative type of grab bucket
- Enables an almost horizontal closing movement
- ☐ The maximum opening is circa 80% larger than a traditional grab bucket
- Relatively thin layers can also be excavated efficiently

Module-2 Lecture-2

7/15



Excavation Buckets



Backhoe

- ☐ It has emerged as a suitable workhorse for soils:
 - glacial tills
 - fragmented or softish, crumbly rock
 - variety of non-rock types of soils that have stones
- May be used for dredging relatively small quantities of material that are at varying depths
- Often used for bulk dredging of a variety of sediments



Module-2 Lecture-2



Variations for Excavators



A wide range of variations have been developed for hydraulic excavators over the years due to:

- Height restrictions
- Propulsion issues
- Insufficient access to the water bottom

The following variations can be encountered:

- Excavator boat
- Amphibious Excavators
- Tractor with Side-Arm





oat Amphibious Excavator



iractor with Side-Arm

Module-2 Lecture-2

9/15



Silt Push Boat



- ☐ A silt push boat is like a floating bulldozer, which has been developed especially for cleaning ponds, lakes and small waterways
- ☐ The machine is primarily used in situations where it is difficult to work from the water's bank

Range of Applications

- Primarily suitable for soft water bottoms (silt, clay, turf, mud, etc.)
- Effective on relatively long, straight waterways
- It can also be used for thicker layers.
- Only effective in relatively shallow waters.
- Depending on the dimensions of the machine, it is possible to work in Depths of up to 2 m
- Machine becomes unsuitable when depths exceed 3 m

Module-2 Lecture-2



Cutter Suction Dredger



□ A cutter suction dredger is a dredging machine that is used in continuous excavation processes and is positioned using spud poles or winch cables



Range of Applications

- Generally only suitable for silt, clay and sand.
- Depending on the dredger design, be used up to 6 m deep
- The soil type and project conditions must be known for each project
- For harder bottoms (i.e. sand), a cutter with larger cutting sections must be selected in order to penetrate the layer of sand

Module-2 Lecture-2

11/15



Dredge Pump



- Used to suck dredging materials from the water bottom
- ☐ The pump's suction opening is guided through the center of ditches to maximize contact with dredged materials
- ☐ Dredge pumps can be mounted to a tractor or crane, or can also be placed on a boat



Range of Applications

- Only suitable for soft water bottoms (silt, turf, etc.)
- Suited to waterways with non-polluted silt
- Cutter can also be attached for dredging more solid water bottoms
- Dredge pumps are susceptible to stones and branches, which could block the opening
- Less suited to dredging activities in urban settings

Module-2 Lecture-2



Dredge Pump



Observations

Module-2 Lecture-2

13/15



Module-2 Field Visit-01 (Observation of De-Silting Machinery)




Date: Name:
Day: Designation:
Field Visit Site: WASA/TMA:
Temp.

Sr.			Machinery			Attachr	nent(s)	
No.	Name/Type	Nos.	Manufacturer /Year	Capacity (Tons)	Fuel Consumption (Liters/day)	Name/Type	Capacity (Tons)	Remarks
1.								
2.								
3.								
4.								
5.								
6.								
7.								

Module-2 Lecture-2

Observations





In the name of Allah, the most Gracious and ever Merciful





Course

Operation and Maintenance of Sewer & Storm Water Drainage System including Safety Practices

Module 2

Operation and Maintenance of Storm Water Drainage System

Lecture 3

Measurement of Sludge Quantity in Drains

Module-2 Lecture-3 (Measurement of Sludge Quantity in Drains)



Lecture Details



Class Work Field Work

Documents
Equipment &
Tools
PPE

- Presentation + Discussion on Current Practices
- Estimation of Deposited Sludge (at Maulana Shaukat Ali Drain, Akbar Chowk, Township)
- > Drain map of area + Templates
- Ranging Rod + Aluminum Staff + Distance Meter+ Road Signs + Traffic Cones etc.
- ➤ Helmet + Goggles + Hand Gloves + Safety Shoes + Gum Boots















Module-2 Lecture-3 (Measurement of Sludge Quantity in Drains)

3/19



Lecture Contents



- Need of Measurement of Sludge Quantity in Drains
- Equipment
- Procedure
- Sludge Volume Calculations
- Observations

Module-2 Lecture-3 (Measurement of Sludge Quantity in Drains)




Need for Measurement of Sludge Quantity in Drains



- ☐ To prevent excessive sediment built-up
- ☐ No standard method of measuring the sediment build-up
- A regular monitoring programme and measurement tools will ensure that the depth of accumulated sludge is accurately measured
- ☐ Inconsistent and inaccurate readings of sediment accumulation could result in too frequent maintenance

Module-2 Lecture-3 (Measurement of Sludge Quantity in Drains)





2- Ranging Rod





- Ranging Rod (6 feet Height)
- Colour Coded
- Each Segment is 01 Foot Long
- Metal Conical Tip for Penetration in Sludge






Module-2 Lecture-3 (Measurement of Sludge Quantity in Drains)









Sludge Measuring Procedure



- 1. First **select the venue** where you have to do dredging or sediment thickness measurement
- 2. Select some culvert or bridge
- 3. Properly apply traffic control plan
- 4. Ensure that each worker has worn the proper safety gadgets
- 5. Find out the **dimensions** of the drain i.e. Length Width and Depth
- 6. Mark the stations on the drain

Module-2 Lecture-3 (Measurement of Sludge Quantity in Drains)

11/19





Sludge Measuring Procedure




- 7. Two persons at both banks of the drain are required
- 8. Find the depth by using staff having graduations on it
- 9. Find out the capacity of dump truck for transporting sludge
- **10.** Calculate the number of trips by dumper from dredging to disposal site
- 11. Also calculate the time required by the dumper per trip and total time for overall operation
- 12. If the cleaning along the road is required because of spillage of waste then clean that

Module-2 Lecture-3 (Measurement of Sludge Quantity in Drains)











Sludge Volume Calculation



Depth at Foot	Avg. Depth at	Depth at Foot 2	Depth at	Overall Avg.	Width at Foot	Width at Foot 2	Avg. Width	Length Inner	Length Outer	L _c	Sludge Volume
1 S _n = (D- W _n)	Foot 1 S _{avg}	S _n = (D- W _n)	Foot 2 S' _{avg}	Depth D _{avg}	B ₁	B ₂	B _{avg}	L _i	L _o		v
S ₁		S' ₁									
S ₂		S' ₂ S' ₃									

D₁= D₂= Estimated Sludge Quantity (Vol.) = (L_{C} X $B_{\text{avg.}}$ X $D_{\text{avg.}}$)

CUM or CFT

Estimated Sludge Quantity (Vol) **X** X)

CUM or CFT

 $L_C = (L_O + L_I) / 2$ (if drain stretch is curved)

 $S' = (S_1 + S_2 + S_3 + ...) / n$

 $S'' = (S'_1 + S'_2 + S'_3 + ...) / n$ $D_{avg.} = (S' + S'' + S''' + ...) / n$ $B_{avg.} = (B_1 + B_2 + B_3 + ...) / n$

Module-2 Lecture-3 (Estimation of Sludge Quantity)

17/19



Observations



Sr. No.	Observations	Remarks
1.	Type of de-silted material	
2.	Flow conditions before the dredging	
3.	Flow conditions after the dredging	



Module-2 Lecture-3 (Measurement of Sludge Quantity in Drains)







Course

Operation and Maintenance of Sewer & Storm Water Drainage System Including Safety Practices

Module 2


Operation and Maintenance of Storm Water Drainage System

Lecture 4

Dredging and Desilting Operations

Module-2 Lecture-4







Critical Processes in Small-Scale Dredging



- Accessibility along and in channels and lakes
- Logistics and transport of material in populated areas (traffic)
- ☐ Limited space for disposal of sediment and waste
- Sensitive project environment:
 - hinder to surroundings
 - highly visible
 - public opinion and interest
- (Old) embankments, low bridges, etc.
- ☐ Household waste & objects



Module-2 Lecture-4

5/12

jica

Dredging Process



Excavation

Process involves the: Dislodgement; Removal of sediments (soils) and/or rocks

Dredger – is used to excavate the material either:

- Mechanically
- Hydraulically
- By combined action

Transportation


Transportation of dredged material is achieved by:

- In self-contained hoppers of the dredgers;
- In barges;Rarely used transport methods are:
 - Truck
 - Conveyor belt

Utilization or Disposal

- In construction projects, dredging is driven by the demand for dredged material.
- In navigation and remediation dredging, the project is driven by the objective of removing the material from its original place

Module-2 Lecture-4





Dredging Techniques



Hydraulic Dredging

- Used for maintenance dredging projects
- Removal of loosely compacted materials by cutter heads, dustpans, hoppers, hydraulic pipeline, plain suction, and side casters

Cutter Head

Mechanical Dredging

- Used either for maintenance or new-work projects
- Removal of loose or hard compacted materials by clamshell, dipper, or ladder dredges



Module-2 Lecture-4



Selection Criteria for Dredging Techniques



While selection of dredging technique, the following factors must be taken into consideration:

- Composition of dredged materials
- Type and level of pollution
- Size of project
- Acceptable opacification and spillage
- Required accuracy
- Side-effects
- Ecological considerations



9/12

Module-2 Lecture-4

jica	Workplace Worksheet	ALJAZARI — ACADEMY —
	Work Report No:	
	MANPOWER USED: Name	
Module-2 Lecture-4		10/12







Course


Operation and Maintenance of Sewer & Storm Water Drainage
System Including Safety Practices


Module 2

Operation and Maintenance of Storm Water Drainage System

Lecture 5

Maintenance of Storm Water Drainage System






jica

Requirement of O & M Plan



- Define the Area to be Covered
- Identify Problem Areas
- Set an Inspection Schedule
- Assign Responsibility for Inspection
- Define What Categories of Work will be Performed Under this Program
- Identify Parties Responsible for Debris Removal
- Keep Records
- Budget

Module-2 Lecture-5





Storm water system feature	Are any of these conditions present?	Problem	Recommendation		
General	Grass is taller than Overgrown 10"m Vegetation 4-9" for best storm water control. Avoid over fertilizers. Excessive fertilizer application may compoun quality problems.				
	Offensive color, odor, or sludge is present	Unknown or uncharacteristic substances	Remove substance and eliminate its source. If you don't know if the substance is hazardous, either take a sample or contact a qualified hazardous waste consultant for more information.		
	Excessive mosquito population is present	Mosquitos	Install predacious bird and bat nesting boxes to control insects		


jica	O & M Plan for Open Drains								
Storm water system feature	Are any of these conditions present?	Problem	Recommendation						
General	Water flows through holes in dam or berm; holes are present around pond	Rodents	Destroy rodents and repair dam or berm.						
	Large trees interfere with maintenance activities	Overgrown trees	Remove trees that interfere with access or maintenance activities. Preserve trees that are not a problem						
	Accumulated sediment exceeds 10% of the designed pond depth	Excessive sediment	Clean out sediment to original shape and depth of the pond. Re-seed pond, if necessary, to control erosion.						
Module-2	Lecture-5		8/22						


Storm water system feature	Are any of these conditions present?	Problem	Recommendation
General	Accumulated sediment or trash exceeds 20% of the diameter of the pipe	Excess accumulation of sediment or trash	Clean out sediment and trash from pipe. You can use a high pressure hose, vacuum suction
	Vegetation is impeding water flow	Overgrown vegetation	or other appropriate cleaning method.
	Pipe is rusted; protected coating is damaged	Corroded pipe	
	Dent in pipe has reduced the pipe diameter by 20%; water flow is impeded; pipe is broken	Defective pipe	Replace or repair pipe to original design specifications.
	Water is leaking from pipe	Cracked pipe	


















Catch Basins/Inlet Structures



Municipal staff should regularly inspect facilities to ensure the following:

- ☐ Immediate repair of any deterioration
- ☐ Cleaning before the sump is 40% full
- ☐ Clean structures in high pollutant load areas just before the wet season
- Keep accurate logs of the number of catch basins cleaned
- Record the amount of waste collected
- Store wastes in appropriate containers or temporary storage sites



Module-2 Lecture-5



Open Channel



- Consider modification of storm channel characteristics to:
 - Improve channel hydraulics,
 - Increase pollutant removals, and
 - Enhance channel/creek aesthetic and habitat value.
- Conduct channel modification/improvement in accordance with existing laws.



Module-2 Lecture-5



Illegal Dumping



- ☐ Regularly inspect and clean up hot spots
- Establish a system for tracking incidents. The system should be designed to identify the following:
 - Illegal dumping hot spots
 - Types and quantities (in some cases) of wastes
 - Patterns in time of occurrence
 - Mode of dumping
 - Responsible parties
- Post "No Dumping" signs in problem areas with a phone number for reporting



Module-2 Lecture-5

19/22





BMPs for Dredging

Module-2 Lecture-5



BMPs for Dredging



- Installation of temporary silt fence
- Fence shall remain in place for the duration of the maintenance dredging activity
- Stop the activity if watercourse flows are encountered
- Accumulated silt shall be removed to the greatest extent possible
- Dredging shall be conducted with hand tools and/ or a tracked equipment



Module-2 Lecture-5 21/22

JICA

BMPs for Dredging



- Dredging shall be held to the absolute minimum necessary to achieve the target channel width, depth and gradient
- ☐ The channel banks shall be sloped such that the resulting channel banks are stable
- Maintenance dredging shall not straighten or shorten the existing channel alignment
- Woody material embedded in the channel bank shall be left undisturbed and intact



Module-2 Lecture-5








Course


Operation and Maintenance of Sewer & Storm Water Drainage
System Including Safety Practices

Module 2

Operation and Maintenance of Storm Water Drainage System

Module-2 Lecture- 6 & 7







Importance of Site Selection



- Minimizes the future impact on public health
- Reduces the cost of:
 - Design and Construction
 - Operation
 - Maintenance





Module-2 Lecture- 6

5/24



Early Considerations



Size

 depends on the waste stream over the predicted site life and provision for sufficient buffer zones

Strategic Location

 determined by the waste generation areas to be served and transport routes

Module-2 Lecture- 6




Requirements for Site Selection





- · Spatial and urban planning requirements
- Spatial and regional requirements
- Required land area
- Transportation distances
- Local site conditions
- Topography
- Climate conditions
- Hydrogeological conditions
- Geological conditions
- Geo-mechanical conditions
- Environmental protection



Module-2 Lecture- 6









Lecture-7: Sludge Disposal Techniques




Contents

- Introduction
- Controlled Dumping
 - Important Considerations for Controlled Dumping
- Landfilling
 - How it Works
 - Sludge Disposal at a MSW Landfill
 - Sludge/Solid Waste Mixture
 - Sludge/Soil Mixture

Module-2 Lecture- 7







Controlled Dumping



- Essential burial of waste in earth on a daily basis, in an isolated and demarcated site
- An established system for rotational and organized deposit of waste
- ☐ To prepare the site to retain its waste more effectively



Module-2 Lecture- 7


13/24



Important Considerations



- Minimize its chances of contact with humans and animals
- Waste should be covered with a soil layer 10-15cm deep
- ☐ If coverage with soil is not possible, lime may be deposited over the waste
- Access to these dedicated disposal areas should be restricted
- ☐ It would require supervision by staff
- Prevent scavenging





Sanitary Landfilling



■ Landfill is the site where waste is isolated from environment until it is safe

(Until completely degraded biologically, chemically and physically)







Module-2 Lecture- 7

15/24



How it Works



- ☐ In landfill operation, Sludge is spread and compacted in thin layers within a small area
- To allow for proper compaction, the cell depth should not exceed about 2 meters
- ☐ The cell is then covered with a **layer of soil** which is spread uniformly and then compacted
- ☐ To provide an adequate **seal the cover** should normally be at least 20 cm thick

Module-2 Lecture- 7





How it Works




- When a number of cells reach the final desired elevation, a final cover of about one meter of earth is placed and it is again compacted
- Landfill must be provided with Liners to prevent the migration of waste out of landfill to adjacent surface soil or ground water or surface water during anytime

Module-2 Lecture- 7









Sludge/Solid Waste Mixture



- ☐ To provide adequate workability of the sludge/solid waste mixture, the bulking ratio for a 20 percent solids sludge should be 4 mg of solid waste to 1 wet mg of sludge
- Sludge application rates for sludge/solid waste mixtures compare favorably with rates for other types of sludge disposal methods
- □ Disposal rates generally range from 500 to 4,200 yd³ of sludge per acre (900 to 7,900 m3 of sludge per ha)

Module-2 Lecture-7

21/24



Sludge/Soil Mixture



- □ Sludge is mixed with soil and applied as intermediate or final cover over completed areas of the MSW landfill
- ☐ This is not strictly a sludge landfilling method from an engineering standpoint, because the sludge is not buried



But it is a viable and proven option for disposal of sludge at MSW landfills

Module-2 Lecture-7

Storm Water Drains


Action Plan for Desilting Operation (Example)

1. Purpose of the plan

One of the problems that WASA faces at present is the deposition of sludge in the drainages and ultimately the flow rate of the drainage system is decreased, which is causing overflowing and flooded conditions. For avoiding the flood, proper drainage cleaning plan should be made.

2. Human resources

Organization of staff is followings. The plan should be performed within staff member.



3. Equipment

We have and can use following equipment in WASA

Equipment	Quantity
Truck (8t)	1
Truck (4t)	2
Truck (2t)	3
Back Hoe (0.25m3)	3
Back Hoe (0.40m3)	4
Clam shell (0.4m3)	2
Clam shell (0.7m3)	2

4- Implementation

The plan includes following implementations

- Survey of sludge deposit quantities
- ➤ Flow rate calculation
- > To make plan of the cleanings
- Implementation of the cleanings

(1) Survey of sludge deposit quantities

At first sludge deposit in drainages should be measured for making the cleaning plan.

Methodology

Same as study in the training method

Equipment

Map, Digital camera, Measuring stuff, Survey pole

Team

Two supervisors

Productivity

Visiting and surveying one place per hour per team

(2) Flow rate calculation

<u>Methodology</u>

From result of the survey of sludge deposit quantities, we calculate water flow rate in the all drainages, and they compare original flow rate of the drainages.

Equipment

Computers

<u>Team</u>

Engineers

Productivity

All calculation within a week

(3) To make plan of the cleanings

Methodology

At first, priority of cleaning place should be decided by the results of the calculation and comparison of original flow. And we make the cleaning plan considering staff and equipment.

Equipment

Computers

Team

Engineers

Productivity

All calculation within a week

(4) Implementation of the cleanings

Methodology

We implement the cleaning within the scope of the plan.

Equipment

Same as above table

<u>Team</u>

One supervisor, Two heavy machine operators, Two truck drivers per team (to make two teams)

Productivity

Around 50m3 per day

4. Schedule for Implementations

	20	16					20	17					
Working items		Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Remarks
Survey of sludge deposit quantities													240places survey
Flow rate calculation													
To make plan of the cleanings			-										
Implementation of the cleanings													

ACTION PLAN FOR DRAIN DE-SILTING

- A Purpose of the plan
- **✓** To avoid Over Flowing & Flooded Conditions in Storm Water Drains

B - Human resources

Dir	ector
Dy D	irector
Assi [Director
Su	b Eng
Super	rvisor(2)
Heavy maci	ne operator(4)
Truck	driver (5)
Sewer	man (10)

ACTION PLAN FOR DRAIN DE-SILTING

C - Equipment

Equipment	Nos.
Truck (8t)	1
Truck (4t)	2
Truck (2t)	3
Back Hoe (0.25m3)	3
Back Hoe (0.40m3)	4
Clam shell (0.4m3)	2
Clam shell (0.7m3)	2

ACTION PLAN FOR DRAIN DE-SILTING

D - Implementation

The plan includes following implementations:

- > Survey of sludge deposit quantities
- > Flow rate calculation
- > To make plan of the cleanings
- > Implementation of the cleanings

SCHEDULES

Working items		2016		2017									
		Dec	Jan	Feb	Mar	Apr	May	J un	J ul	Aug	Sep	Oct	Remarks
Survey of sludge deposit quantities													240places survey
Flow rate calculation													
To make plan of the cleanings			-										
Implementation of the cleanings				_		_	_					_	

SCHEDULES

Sr.No	Date	Name of Durin	Rei	ch		ength to be ted per day	Machinery
		. Same	Admir to Danie	From	To	Rfr	Size (ftxff)
			Schedule of Heavy Machin	віу			
1	15-11-2016 to 30-11-2016	Canti Drian	Shadman Bridge	Shama Bridge	100	50 x12	01 Long boom + 05 Dump Trucks
2	15-11-2016 to 30-11-2016	Kharak Drain	Liagat Tokay Walli Pully	WAPDA God Station	90	14 67	01 Ex. + 05 Dump Trucks
3	15-11-2016 to 20-11-2015	Birdwood Dinan	Jail Road	LOS Ferozepur Road	120	1518	01 Clamshall + 05 Cump Trucks
6	01-12-2016 to 15-12-2016	Cantt Orian	Shera Kot	Old Babu Sabu	100	90x11	O1 Long boom + 05 Dum Trucks
8	01-12-2016 to 10-12-2016	Guiberg Drain-i	Raitway Line	Main Bouleward Gulberg	105	30x07	01 Clemshall + 05 Dump Trucks
14	16-12-2016 to 31-12-2016	Canti Drian	Shera Kot	Gulshan-e-Raw	100	90x11	01 Ex. + 05 Dump Trucks
Note:	Heavy Machinery schedule for Back Hoe, Trolley and Wheel I Schedule Subject to availability During the Desilting for the pur	oader as per requirme of POL		ngineer.	615	187	

SCHEDULES

Date	Name of Drain	Locations	Total Length (Rft)	to l Desi	4	Labour Deployed	Name of Sub Engineer	Name of Supervisor	Remarks
01-04-2016 to 30-04-2016	Nagra Drain	Ghugian Nagra	3000	11	I	8	Mirza Kashif	Hamida	3rd Shift
01-04-2016 to 30-04-2016	Abu Bakar Saddique Colony	In Colony	2500	10		8	Ayaz Hanif	Ashiq	1st Shift
01-04-2016 to 30-04-2016	Open Nagra Drain, G- Block Sabzazar & Line- B Sabzazar	Telephone	2500	12	Ī	8	Mirza Kashif	Ishaque	1st Shift
01-04-2016 to 30-04-2016	Cantt Drian	Shama Bridge	250	25		12	Umair Raza	Khushi	Ist Shift
	Sub Engineer-I	Sub Engineer-II Sub Engineer-III		SDO Drainage Central					



O&M of Drainage System Module 02

Action Plan Template WHAT TO HOW TO WHEN TO WHO TO DO? DO WITH WHAT? **CHECK DONE?** wно то DO? DO? DO? CHECK? No (Define (Follow Materials Tools/ **How to Check?** To be Checked (Frequency) (Carried out By) **0&M** SOP Ref.#) Equip. By? Class of Worker Task) Work

Thanks indeed for your valuable time • GOOD BYE

Have a Safe Journey







In the name of Allah, the most Gracious and ever Merciful



WELCOME BACK TO AL-JAZARI ACADEMY





Introduction







3rd Module Training
Operation and Maintenance of Sewerage System

Introduction

3/25





3rd ModuleOperation and Maintenance of Sewerage System

Start Date	Closing Date	Duration (Days)	Participants
04 October, 2017 (Wednesday)	05 October, 2017 (Thursday)	02	EngineersSub-Engineers


Topics 05

Lectures 08


Field Visits 02


Introduction


jica		Operation and M	le 03 (An Overview) Maintenance of Sewerage System	ALJAZARI ACADIM
		Topics 05	Lectures 08 Field Visits 04	
	DAY 01	☐ Inspection & Testing of Sewers & Manholes	☐ Inspection of Manholes & Sewer Lines ☐ Testing Techniques ☐ 102 Lectures + 01 Field Vi	isit
	DAY 02	☐ Machinery, Tools & Equipment for Cleaning Sewer Lines & Manholes	☐ Machinery, Tools & Equipment ☐ Cleaning Techniques 02 Lectures + 01 Field Vi	isit
	DAY 03	☐ O&M of Disposal Station	Disposal Station Introduction & O&M 01 Lecture + 02 Field Vis	sits
	DAY 04	□ Maintenance &Rehabilitation□ Emergency Response Planning	Repair & Rehabilitation Emergency Planning for Rainy Season 02 Lecture + 01 Action P	lan
Introduction	n			5/25













Sewerage System



Definitions

Sewerage System

- ✓ An underground <u>infrastructure</u> that conveys liquid waste.
- ✓ It is the system of pipes, manholes and disposal stations etc.



✓ Its <u>liquid waste</u> originating from homes, commercial buildings and industrial establishments.



Sewer

✓ An <u>underground conduit</u> through which sewage is carried to a point of discharge or disposal.



Introduction

11/25





Sewerage System



1 - Combined Sewerage System

2 - Separate Sewerage System






Introduction



Sewerage System



3 - Effluent Sewerage System



Introduction

13/25



O&M of Sewerage System





- 1) Components
- 2) O&M Objectives


Strategy for Improvement


- 1) Sensitizing Senior Decision Makers
- 2) Assessing the Existing Facilities
- 3) Identification of Factors affecting Quality of Maintenance
- 7) Snags in Management
- 8) Immediate Action Plan
- 9) Long term Action Plan


Introduction

















- 1. Lateral Sewer
- 2. Sub-Main Sewer
- 3. Main Sewer
- 4. Trunk Sewer
- 5. Sullage Carrier or Outfall Sewer
- 6. Pumping Station(Disposal/Lift Station)



Introduction









Now What are your...



About Module & Training



Introduction





In the name of Allah, the most Gracious and ever Merciful

Module 03

Safety Control and Measures for Sewerage and Drainage Works

Traffic Control Practice during Sewer and Manhole Cleaning Operations Lecture No. 01

Identification of a Specific Manhole OJI

Lecture Breakdown	Duration
Objectives	1 Hour
Reasons for Identifying a Specific Manhole	11 12 1
Early Metal Locator	9 3
Manhole Cover Locator	7 6 5
Parts with Labels	
Working Principle	





Module-3 Lecture-1 Identification of a Specific Manhole





Objectives

The objectives of this lecture are:

- To understand the need of locating a buried manhole
- To comprehend the working principle of metal locator device
- To identify the <u>buried manhole</u> with the help of metal locator

Module-3 Lecture-1 Identification of a Specific Manhole

3/12






Reasons for Identifying a Specific Manhole

The reasons are:

- To conduct an inspection survey against the sewer system related complaint
- To initiate operation and maintenance work at the rightly identified manhole for redressing the complaint received

Module-3 Lecture-1 Identification of a Specific Manhole








jica



Manhole Cover Locator (Parts with Labels)






Module-3 Lecture-1 Identification of a Specific Manhole

7/12





Module-3 Lecture-1 Identification of a Specific Manhole





Working Principle of Manhole Cover Detector


- A battery in the top of the metal detector activates the transmitter circuit (red) that passes electricity to the transmitter coil
- 2. When electricity flows through the transmitter coil, it creates a **magnetic field** all around it.
- 3. If you sweep the detector above a **metal object** electric current flow inside the metal object.
- 4. This flowing electric current creates a loudspeaker buzz and alerting you you've found something.

Module-3 Lecture-1 Identification of a Specific Manhole





In the name of Allah, the most Gracious and ever Merciful




Safety Control and Measures for Sewerage and Drainage Works

Standard Safety Practices during Sewer and Manhole **Operations**

Lecture No. 02

Test for Hazardous Gases


Lecture Breakdown	Duration
Various Gas Monitors	1 Hour
Purpose of Use	11 12 1
Portable Gas Monitor GX-8000	9 3
Names & Functions for Each Part	765
Start the Gas Monitor	
LCD Display, Features & Cautions	
Q&A	




Gas Monitoring at Manhole


Module-3 Lecture-2 Test for Hazardous Gases






































Course ... O & M of Sewerage & Drainage System


Field Work on Test for Hazardous Gases in Manholes (Module 03...Lecture No. 02)

Name	
Designation	
Company	
Date / Day	
Time	
Site Location	Around Al-Jazari WATSAN Academy

Observation Table for Hazardous Gas Concentration in Manholes

				Hazar	dous Gases		
			Flammabl	le Gases	Toxic Gases		
		UoM Max.	Oxygen (O2) % 19.5%	Methane (CH4) %LEL 10% LEL	Hydrogen Sulphide (H ₂ S) PPM 10 PPM	Carbon Mono Oxide (CO) PPM 50 PPM	
		Values					
Sr. No.	Case / Situation	Location					Remarks
1.	Gases Concentration	Manhole No. 01					
2.	immediate after Removal	Manhole No. 02					
3.	of Lid	Manhole No. 03					
		ı					
4.	Gases Concentration	Manhole No. 01					
5.	after Air Blowing	Manhole No. 02					
6.	Operation	Manhole No. 03					







Lecture Contents



Inspection of Sewers & Manholes

- Objectives of Inspection
- Types of Manholes
- X-Sections & Profiles
- Inspection Methods
- Inspection & Report Forms



Module-3 Lecture-3 Inspection Techniques

3 / 28


Objectives of Manhole Inspection



- To identify existing or potential problems in Manhole
- To examine <u>structural integrity</u> of the manhole
- To observe <u>functional capacity</u> of manhole
- To generate concise and meaningful reports









Module-3 Lecture-3 Inspection Techniques

Types Manholes (Shallow + Medium + Deep)








Concentric Manhole

Eccentric Manhole


Module-3 Lecture-3 Inspection Techniques


5 / 28



X-Section of Manhole

Module-3 Lecture-3 Inspection Techniques







X-Section of Manhole R.C.C Surround

Module-3 Lecture-3 Inspection Techniques


7 / 28






X-Section of Manhole Cover / Lid

Module-3 Lecture-3 Inspection Techniques






X-Section of Sewer in Trench


Module-3 Lecture-3 Inspection Techniques


9 / 28




Profile of Sewer Line

Module-3 Lecture-3 Inspection Techniques







Arrangements before Ir	nspection:	
Map of the Collection	Scrapers and Wire Brushes for	
System	Cleaning the Manhole Ring	
Metal Detector	Powerful Flashlight	
Warning Devices, Safety	Gas Detection Devices	
Cones and Traffic Safety		
Devices		
Manhole Lid Removal	Blower and Hose for	
Device	Ventilating Manhole	
Leather Gloves		

















V. SEC. P. SANTARY SEWER MANHOLE INSPECTION FORM M.H. C: DATE: L. INTIAL INSPECTION II. HYDRAULIC INSPECTION II. HYDR					
I. INTIMAL INSPECTION III. HYDRAULG INSPECTION A. COCATON: 1. Roadway 2. Gustler 3. Serviceable 2. Unsale 3. Missing (No.) 4. Corroded 8. SURCHARGE RIDICATIONS: 1. Debts on Sides Shelf SURCHARGE RIDICATIONS: 1. Debts on Sides Shelf SURCHARGE RIDICATIONS: 1. Serviceable 2. Descent 5. See 8. Shelf C. CLARITY OF FLON: 1. Serviceable 2. Descent 3. Sulfided 4. Missing Grout 5. Needs Raiking 6. Needs Lovering C. RINGS FRAME: 1. Serviceable 2. Bolsen 3. Sulfided 4. Surcharging 5. Subgliced 4. Surcharging 5. Subgliced 5. Subgliced 6. Needs Lovering 6. Needs Loveri	V. SEC. #:	SAN	ITARY SEWER MANHOLE INSPECTIO	N FORM	•
1. Notation	JICA M.H. DEPTH:	FORM:	M.H. #:	DATE:	ALJAZARI
1. Roadway 2. Cutaria 3. Missing (No.) 4. Unpawed Alley 3. Missing (No.) 4. Cornoded 3. Missing (No.) 4. Cornoded 5. Cassement 6. Other 6. Other 7. Serviceable 2. Broken 7. Serviceable 2. Broken 7. Serviceable	I. INITIAL INSPEC	TION	II. STRUCTURAL INSPECTION	III. HYDRAULIC INSPECTION	ACSULAT
Module-3 Lecture-3 Inspection Techniques 21 / 28	1. Roadway 2. Gutter 3. Pared Alley 4. Urpaved Alley 4. Urpaved Alley 4. Urpaved Alley 4. Urpaved Alley 5. Eastment 6. Other 8. MANHOLE COV 1. Serviceable 2. Damaged 3. Displaced 4. Missing Grou 5. Needs Raisii 6. Needs Lower C. RING a FRAME 1. Serviceable 2. Loose 3. Displaced 4. Missing Grou 5. Needs Raisii 6. Needs Lower D. MANHOLE MAT 1. Brick 2. Concrete E. SIZE M.H. COV 1. 24 Inch 2. 30 Inch F. MANHOLE SIZE 1. 4 Inch 2. 50 Inch F. MANHOLE SIZE 1. 4 Inch 2. 5 Isot OBSERNATION SU	ER:	1. Serviceable 2. Unsala 3. Missing (Na.) 4. Corroded B. CONE: 1. Serviceable 2. Broken 3. Sulfdad 4. Missigned 5. Leaking/Bad Joints C. RISER: 1. Serviceable 2. Broken 3. Sulfdad 4. Missigned 5. Leaking/Bad Joints D. SHELF: 1. Serviceable 2. Broken 3. Sulfdad 5. Leaking/Bad Joints C. Broken 3. Sulfdad 4. Missigned 5. Leaking/Bad Joints D. SHELF: 1. Serviceable 2. Broken 3. Diffy 4. Sulfided 5. Bad Base Joint 5. CHANNE: 1. Serviceable 2. Obstructed 3. Sulfded 4. Bad Pipe Joint 5. St. 6. Poor Struct, Cond.	1. Debris on Sides/ Shelf B. SURCHARGE INDICATIONS: 1. Gresse/Debris on Sides & Shelf C. CLARITY OF FLOW: 1. Turbid Appearance 2. Clear Appearance 2. Clear Appearance 3. Turbident 4. Surcharging 5. Sluggish E. PLOW DEPTH COMPARED TO ADJACENT MANNOLES: 1. Same 2. Lower 3. Higher F. FLOW DEPTH: Inches Time AMMPM IV. VERMIN 1. Roaches 2. Rats	Form







Closed Circuit Television Inspections (CCTV)



Module-3 Lecture-3 Inspection Techniques

23 / 28

Objectives of CCTV Inspection



- To look for damages / breaks in sewer line
- To locate root intrusion
- To find unrecorded connection
- To locate protruding laterals
- To locate cracks / inflow sources
- To search lost / buried manholes
- To verify alignment


Module-3 Lecture-3 Inspection Techniques



Module-3 Lecture-3 Inspection Techniques









Lecture Contents



Testing of Sewers

- Objectives of Testing
- Types of Testing
- Equipment Required for Testing
- Methods





Module-3 Lecture-4 Testing of Sewers


Module-3 Lecture-4 Testing of Sewers


3 / 14

Objectives of Testing ALJAZARI • Find out leaks in sewers joints and manholes Locate and determine the inflow, infiltration and exfiltration **Objectives** problems • Effectively use tools & equipment











Dye Testing




Objectives

The typical application of dye testing includes the following:


- To identify illegal connections
- To reveal interconnection between sanitary & storm sewer
- Testing for infiltration and exfiltration
- Flow <u>velocity</u> measurement




Module-3 Lecture-4 Testing of Sewers

















Lecture 05


Machinery, Tools & Equipment for Sewer & Manhole Cleaning






Module-3 Lecture-5 Machinery, Tools & Equipment





Module-3 Lecture-5 Machinery, Tools and Equipment





Sewer Cleaning Equipment



1 - Split Bamboo Cane

Hand Rodding





- Oldest Method
- Torque by Hand

Module-3 Lecture-5 Machinery, Tools & Equipment

7 / 33

ALJAZARI



2 - Steel Rod


Hand Rodding





Torque by Hand



Module-3 Lecture-5 Machinery, Tools & Equipment

















5- High Pressure Water Jetting Machine







Courtesy – WASA Mustafa Town Sub-Division


Module-3 Lecture-5 Machinery, Tools & Equipment








Module-3 Lecture-5 Machinery, Tools & Equipment















Bucket Machine


<mark>Advantages</mark>

Efficient in removing sand, gravel, and debris

Limitations

- Can damage pipe line internally
- Setting up equipment is time taking activity

Module-3 Lecture-5 Machinery, Tools & Equipment







Flushing

Advantages


 Supplies a surge of water to move light matter downstream in slowly flowing sewers


Limitations


Flushing does not remedy the cause of the problem


 This method does not move heavy debris and grit


Module-3 Lecture-5 Machinery, Tools & Equipment

























Cleaning Techniques





Contents


- 1. Objectives
- 2. Sewer Blockages & its Types
- 3. Reasons of Cleaning
- 4. Methods of Cleaning
- 5. Record of Cleaning Operation



Module-3 Lecture-6 Cleaning Techniques











Reasons for Cleaning Sewer & Manhole

- 1. To remove the obstruction
- 2. To reduce the complaints regarding the bad odor
- 3. To minimize the overflow and ponding of sewage

Methods for Sewer & Manhole Cleaning

- 1) Manual
- 2) Mechanical
- 3) Hydraulic
- 4) Chemical

Module-3 Lecture-6 Cleaning Techniques

7/19



Manual Method



Hand Rodding

Long strips from bamboo stem are taken and tailored to use as sewer cleaning rod between two consecutive manholes

Crew

If a crew is essentially doing only hand rodding, at least two operators recommended:

- 1. Maintenance man I
- Maintenance man II.



Module-3 Lecture-6 Cleaning Techniques



Hand Rodding (Set Up and Procedure)




- 1. <u>Ventilate</u> the manhole and test for toxic gases, explosive gases, and oxygen level
- 2. Determine the depth of the manhole
- 3. <u>Assemble sufficient rod portion</u> to firmly rest in the sewer and leave enough protruding above the street level to allow for working conditions, usually about 18 to 24 inches

Module-3 Lecture-6 Cleaning Techniques

Module-3 Lecture-6 Cleaning Techniques

9/19





Bucket Machine (Winch Machine)





Equipment Set up

- 1) Position the two machines over the respective manholes
- 2) Place the pads under the stabilizer feet of the machine and jack them down. The lower manhole roller is lowered into the manhole.

Module-3 Lecture-6 Cleaning Techniques

11 / 19




Bucket Machine (Winch Machine)



Equipment Set up

- 4) To thread the sewer, a synthetic rope can be used
- 5) To this rope attach a nylon parachute designed for such use and allow this parachute to float downstream to the working manhole



Module-3 Lecture-6 Cleaning Techniques



Bucket Machine (Winch Machine)



Equipment Set up

- 6) The clearing bucket is now ready to be attached to the cable
- 7) As the bucket is pulled upstream into the material deposited in the sewer, a definite resistance can be noticed when the bucket is full
- 8) When the bucket is full, pull the loaded bucket back out of the sewer
- 9) Final cleanup is performed with special care given to washing down and completely cleaning the entire area

Module-3 Lecture-6 Cleaning Techniques

13 / 19

jica

Hydraulic Methods



1 - Flushing

- 1. Start operation at the upstream end
- Place the water line over the manhole
- 3. Clean the manhole first.
- 4. Dumped some of the water
- 5. Observe any evidence of water backing up
- 6. Look for signs of grease & roots etc.
- 7. Close the manhole and go to downstream manhole
- 8. Repeat from manhole to manhole

Module-3 Lecture-6 Cleaning Techniques



2- Jetting and Sucking



The use of hydraulic pressure to de-silt sewers dates back to the early 1900s; however, this method has been developed with the passage of time by using high velocity cleaning machines

- ☐ High velocity cleaning machines are confidently used to:
 - **Open Stoppages**
 - Remove Grease
 - Clean lines of Debris
 - Wash Manholes and Wet Wells

Module-3 Lecture-6 Cleaning Techniques


15 / 19

Equipment Set up and Operation



Sr. No.	Set up and working
1	Fill the water tank from a fire hydrant close to the area where you will do the
	cleaning
2	Start at the top or highest point in the collection system
3	Select the appropriate nozzle for the size of pipe to be cleaned
4	Install the proper size sand or debris trap in the downstream manhole
5	Turn the reel directional control to "Out" and lower the hose and cleaning nozzle into
	the manhole
6	Turn the water valve on and start the high pressure pump

Module-3 Lecture-6 Cleaning Techniques





Module-3 Lecture-6 Cleaning Techniques


Section 01		
Division	Subdivision	
Foreman	Time of cleaning	
	started	
Date	Time of cleaning	
	finished	
Temperature	Duration	
Street no.	Line size (dia.)	
Block / Mohallah	Manhole number	
a) Condition of flow	b) Machines used	
	tails of cleaning operation	
before cleaning	o) maemies asea	
c) Condition of flow	d) Tools and	
after cleaning	equipment	
e) Kind of materials		
removed		
after cleaning e) Kind of materials		




jica ALJAZARI **Operation & Maintenance of Sewer &** Drainage system (S 3221) Module 3 Topic 5: **Lecture 7: Duration: Emergency Emergency** 45 Min. Response Plans for **Planning** Rainy Season Module-3 Lecture-7 2/25













Emergency Management Process

Preparedness Phase

Consists of activities carry out in advance before an emergency strike to improve response to emergency

E.g. hazard or risk analyses, training, drills and exercises, emergency plans and procedures, emergency communications, joint cooperation consensus, warning systems procedures and response planning.

Module-3 Lecture-7 (Emergency Planning)

7/25



Emergency Management Process




Response Phase


Consists of the immediate response to emergency by the ERT


Olt is aim at containing the disaster so as to minimize loss of life and destruction to property.


Includes measures such as: notification, implementation of emergency plans, activation of emergency operation centers, mobilization of resources, issuance of warnings and directions, provisions of medical and social services assistance, announcement of emergencies or disasters by the management.

Module-3 Lecture-7 (Emergency Planning)

















Special Arrangements for Rainy Season

Cleaning & Desilting of

- ✓ Sewer lines
- ✓ Disposal stations
- √ Storm water channels









Module-3 Lecture-7 (Emergency Planning)

15/25





Special Arrangements for Rainy Season

- □Strengthening of katcha drains/channels
- ☐ Repair of pacca channels
- □ Closure schedule of factories



□ Proper & effective CMS should be established



Module-3 Lecture-7 (Emergency Planning)





Special Arrangements for Rainy Season

- Maintenance and utilization of dewatering sets
- ☐ Installation of Mobile Dewatering Sets





- ☐ Stockage of material for repair of channels
- Repair of pumping machinery
- Repair of heavy mobile machinery



Module-3 Lecture-7 (Emergency Planning)

17/25



Special Arrangements for Rainy Season

- ☐ Arrangements for low lying areas
- ☐ Duties of emergency duty staff
- Response of O & M official during emergency
- ☐ Duties of O & M staff during rain
- Identification of Major Low lying areas of the city








- Availability of Double Feeder System
- Report of rain water after rain
- ☐ Enhancement of generation capacity of Disposal Station



Module-3 Lecture 7 (Emergency Planning)











Monitoring System

All work operation should be properly monitored by high authority. There should be a proper monitoring system established.

Monitoring Teams supervised by listed officers, along with subordinate officers shall be in place to feed back the actual position of the city during rain fall.

Directors shall once daily check the functionality and operation of disposal/lift stations through their teams

Module-3 Lecture-7 (Emergency Planning)



Reporting Mechanism



Focal Person should be selected

Central Control Office should be established at Head Office for coordination with all Field Complaints Centers and Emergency Control Room

Immediate and remedial actions on reporting of emergency including power failure, machinery break down etc.

Action plan and status of Disposal Stations should be submitted to focal person immediately after rainfall

Module-3 Lecture-7 (Emergency Planning)

23/25


Alarm Systems



Alarm systems with a backup power source shall be provided for pumping stations. The alarm shall be activated in cases of power failure, dry well sump and wet well high water levels, pump failure, unauthorized entry, or any other cause of pump station malfunction. Pumping station alarms including identification of the alarm condition shall be transmitted to a municipal facility that is staffed 24 hours a day. If such a facility is not available and a 24-hour holding capacity is not provided, the alarm shall be transmitted to municipal offices during normal working hours and to the home of the responsible person(s) in charge of the lift station during off-duty hours. Audio-visual alarm systems may be acceptable in some cases in lieu of a transmitting system depending upon location, station holding capacity and inspection frequency.

Module-3 Lecture-7 (Emergency Planning)







Sewage Pumping Station



PURPOSE

Pumping stations are used to move sewage to higher elevations.

- **□** Disposal Station
- ☐ Lift Station

COMPONENTS

- 1. Collection Chamber (Screening Area)
- 2. Wet Well(s)
- 3. Dry Pit (Pump Room)
- 4. Force Main



Pumping station - Netherlands

WELL.

Module 3 Lecture 8 Sewage Pumping Station

03/31




Sewage Pumping Station





Working Principle


- 1- Raw sewage is received from underground sewers.
- 2- Screening is performed.
- 3- Sewage is stored in an underground pit (a wet well) (Wet well is equipped with electrical instrumentations)
- **4-** Electrical instrumentations detect the level of sewage.
- **5-** As sewage level rises to a point, pump starts.
- 6- Pump lifts the sewage upward.
- 7- Sewage is discharged into some other channel/sewer. (Cycle repeats until the sewage reaches its fixed/lowest point in wet well)


Module 3 Lecture 8 Sewage Pumping Station
































Modern Pumping Station



- Do not require a dry well or pump house.
- Only consisting of a wet well.
- Submersible pumps with motors are mounted in the wet well.
- For maintenance or replacement, submersible pumps are raised by a chain pulley system.
- · Reinstalling the pumps simply reverses this process.
- No above ground structures are required.
- Except electrical switchgear and control systems.

Module 3 Lecture 8 Sewage Pumping Station

17/31

jica


Sewage Pumping Station (Basic HSE Considerations)




- The interior of a sewage pump station is a very dangerous place.
- Gases, such as methane and hydrogen sulfide, can accumulate in the wet well.
- Entry into the wet well requires <u>confined space</u> entry method.



Module 3 Lecture 8 Sewage Pumping Station





jica

Maintenance of Pumping Station



- <u>Quarterly inspection</u> of submersible pumps, impellers, and floats allows for clearance of debris and grease.
- <u>Half yearly inspection</u> of check valves ensures proper valve function that restricts backflow from the force main to the wet well.
- Wet well cleaning is done at least twice a year.
- The electrical motor equipment has to be inspected <u>twice a year</u> to identify poor connections and replace worn out parts.
- Light and alarm system need to be inspected every week.

Module 3 Lecture 8 Sewage Pumping Station

21/31

jica

Maintenance of Pumping Station



The routine inspection and maintenance activities include the following:

- <u>Visually inspect</u> the station for vandalism or damage.
- Clean up any trash or debris found on the site.
- Record pump run time hours for each pump.
- Record kilowatt-hour meter reading for the pump station.
- Run each pump by hand (manual control) to ensure pumps/motors are operating properly.

Module 3 Lecture 8 Sewage Pumping Station

jica

Maintenance of Pumping Station



The routine inspection and maintenance activities include the following:

- Inspect wet well to determine need for cleaning.
- Test panel lights and change as needed to ensure proper operation.
- Complete any scheduled PM Work Orders.
- Place pump controls back in auto position prior to leaving station.
- Lock up station, including exterior power panels if required, prior to leaving.

Module 3 Lecture 8 Sewage Pumping Station

23/31

jica

Emergency



- Any lift station failure must be responded to immediately with an appropriate back-up plan.
- •The <u>alarm system</u> should be in working order to immediately alert the authorities to problems.
- •The <u>log book</u> is referenced for the maintenance dates and appropriate action is taken.
- <u>Generator back-up</u> for power outage during storms or usage of engine-driven pumps ensure unhindered sewage water treatment and processing.

Module 3 Lecture 8 Sewage Pumping Station

O&M OF DISPOSAL STATION

Field Work Exercise

Module 3 Lecture 8 Sewage Pumping Station

25/31

Disposal Station (General Data Sheet)




Module 3 Lecture 8 Sewage Pumping Station


Disposal Station (General Data Sheet)						
Disposal Station						
Catchment Area (Sq. Km)						
Screening Chamber(s)						
Size						
Incoming Sewer Dia. (Inch)						
Depth of Sewer Invert (Feet)						
Depth to Bottom (Feet)						
Collecting Tank(s)						
Numbers						
Size (Length x Breadth x Height)						
Depth of Pipe (Feet)						
Depth to Bottom (Feet)						
Discharge Point (Location)						
Miscellaneous Information	_					
Module 3 Lecture 8 Sewage Pumping Station	27/31					


	Existence	If Yes Then	If Yes Then		
Structure	Yes/No	Satisfactory	Damaged/ Unsatisfactory		
Pump House					
Electric Wiring					
Incoming Sewer Dia. (Inch)					
Doors & Windows					
Screening Chamber(s)					
Wet Well(s)					
Wet Well Number(s)					
Generator Room					
Boundary Wall					
Gate					

Pump	Suction /	Make /	Year of	Capacity	Head	Drive	en By	Working	Condition
No.	Delivery	Type	Install	(cfs)	(feet)	Elec. (BHP)	Diesel (BHP)	Hours in a Day	


Typo	Make	Year	Canacity	Condition
Type	Make	Teal	Capacity	Condition
Generator(s)				
1)				
2)				
3)				
Force Main				





























































Spot Repair

The following techniques are available for spot repairs of short deficient sections of a pipeline which is otherwise in a generally good condition:



- **CIPP**
- ❖Internal Grouting
- External Grouting
- Rubber Seals with Stainless Mechanical Bands





Module-3, Lecture-8 (Repair & Rehabilitation)

21/34





Renovation


- Renew the Structural Integrity of the Sewer
- Use the Existing Pipe Structure to "build" a New Pipe or Support a New Lining
- Coating and Lining

Replacement

- The classic Method
- Cheaper than Lining Technologies
- Requires more Construction Time

Module-3, Lecture-8 (Repair & Rehabilitation)









Sewer Line Rehabilitation

Cured-In-Place-Pipe (CIPP)

- Used for both structural and semi-structural rehabilitation of sewer lines.
- The CIPP liner consists of a tubular felt like material saturated with an epoxy resin that after curing turns into a rigid liner for the pipe.
- Before the process is initiated, pipes must be thoroughly cleaned and dried.

Module-3, Lecture-8 (Repair & Rehabilitation)

25/34






Sewer Line Rehabilitation

Fold and Form

Fold & form is a technology for rehabilitation of sewer lines by inserting a folded liner into the existing pipe and expanding it through pressure, heat or mechanical means to restore its original circular shape





Module-3, Lecture-8 (Repair & Rehabilitation)






Sewer Line Rehabilitation

Spirally Wound Pipe

- This technique is based on forming a pipe in-situ by using PVC-ribbed profiles with interlocking edges. The ribs enhance the hoop strength of the liner.
- This method is applicable to sewer lines smaller than 30 inches in diameter.
- The process involves the fabrication of the liner in the manhole by helically winding a continuous PVC fabric.

Module-3, Lecture-6 (Repair & Rehabilitation)







Manhole Rehabilitation

The following methods are available for manhole rehabilitation:

- Chemical Grouting
- Coating Systems
- Structural Linings
- Frame, Cover & Chimney Rehabilitation
 - Full depth Lining
 - Frame and cover casting adjustment, including replacement or resetting
 - Manhole Replacement
 - Grouting

Module-3, Lecture-8 (Repair & Rehabilitation)

29/34





Manhole Rehabilitation

Open Cut Replacement

- ✓ If a manhole is severely deteriorated, open cut replacement may become a preferred option
- ✓ Open cut may also be utilized if manhole relocation is dictated by hydraulic or access requirements.

Module-3, Lecture-8 (Repair & Rehabilitation)





Manhole Rehabilitation

Chemical Grouting

- Chemical grouting is used to reduce I/I in manhole structures.
- Grouts give best results in cohesive soils.
- They may be used to fill voids and stabilize soils behind manhole walls.
- Grouts are normally applied under pressure through grout holes drilled into the manhole walls



Module-3, Lecture-8 (Repair & Rehabilitation)

31/34






Manhole Rehabilitation

Coating Systems

- Coating systems may be used as a corrosion protection barrier and/or to enhance structural integrity of manhole structures.
- Coatings can be applied by spraying, or hand applied. When using coating system, it is essential that the surfaces be properly cleaned and prepared.



Module-3, Lecture-8 (Repair & Rehabilitation)



	Action Plan Template (Module 03)						<u>03)</u>	Department: _	
	1	2	3	4		5		6	7
Sr. No.	WHAT TO DO?	HOW TO DO?	WHEN TO DO?	wно то	DO?	DO WITH WHAT?		CHECK DONE?	WHO TO CHECK?
	(Define	(Follow	(Frequency)	(Carried out By)		Materials	Tools/	How to Check?	To be Checked
	O&M Task)	SOP Ref.#)		Class of Work	Worker		Equip.		By?

Thanks indeed for your valuable time • GOOD BYE

Have a Safe Journey