

National Irrigation Administration (NIA)
The Republic of the Philippines

**PREPARATORY SURVEY
ON
MALITUBOG-MARIDAGAO
IRRIGATION PROJECT
(PHASE II)
IN
THE REPUBLIC OF THE PHILIPPINES**




FINAL REPORT

September 2018

Japan International Cooperation Agency (JICA)
Sanyu Consultants Inc. (SCI)

1R
CR(3)
18-064

LOCATION MAP : MALITUBOG MARIDAGAO IRRIGATION PROJECT



Service Area	Phase	Starting Year	Irrigation Area, ha	Beneficiary FHH	Population	Area/ FHH, ha
Maridagao	Phase 1	Completed in 2011	5,562	4,278	21,521	1.30
Upper Malitubog	Phase 1		1,611	1,239	6,233	1.30
Upper Malitubog	Phase 2	Started in 2011	2,958	1,782	8,963	1.66
Pagalungan Ext.	Phase 2	2015	988	788	3,963	1.25
Lower Malitubog	Phase 2	Whole	6,590	5,255	26,434	1.25
		2015	1,303	1,039	5,227	1.25
		2016	1,736	1,384	6,963	1.25
		2017-18	1,418	1,131	5,688	1.25
		2019 (ODA)	2,133	1,701	8,556	1.25
Total	Phase 1		7,173	5,518	27,754	1.30
	Phase 2		10,536	7,825	39,360	1.35
Ground Total			17,709	13,343	67,114	1.33

Note: No. of typical family members was assumed to be 5.03 persons per family as per Census 2015.



EXECUTIVE SUMMARY

PREFACE

0.1 Submitted herewith is the Final Report prepared at the end of the field surveys on ‘the Preparatory Survey on Malitubog-Maridagao Irrigation Project Phase II (MMIP II)’. A survey team organized by JICA headquarters commenced a series of field surveys for the Preparatory Survey from the beginning of May 2017, and this report presents major findings, flood simulation, project components, project cost, implementation arrangement, project evaluation, environmental and social consideration including indigenous peoples’ issues, and conclusion and recommendations.

1. RATIONALE OF THE SURVEY

1.1 National Economic and Development Authority (NEDA) Board officially approved the Philippine Development Plan 2017-2022 on February 20, 2017. In this Plan, growth is expected to be more inclusive, where overall poverty ratio for the nation is targeted to decline from 21.6 % to 14 percent, and poverty incidence in rural areas to decrease from 30 % in 2015 to 20 % in 2022. Thus, the Plan puts priority on the poverty reduction in rural areas, e.g. central Mindanao area where the MMIP II site is located.

1.2 The Plan 2017-2022 is founded on three main pillars of: 1) regaining of people’s trust, 2) inequality-reducing through increasing opportunities for growth, and 3) increasing of potential growth through sustaining and accelerating economic growth. Under the second pillar, opportunities in agriculture sector are expected to expand. Further, under the three pillars lie cross-cutting strategies, i.e.: 1) attaining just and lasting peace, 2) ensuring security, public order and safety, 3) accelerating infrastructure development, and so on. In this regard, MMIP I, the foregoing project to MMIP II, is well known to have contributed to the peace and order in that area.

1.3 The National Irrigation Administration (NIA) has its six-year plan for the period from 2012 to 2017. According to this plan, the rate of irrigation development in central Mindanao area was as low as 41.7% compared to the national average of 55.6% in the year 2015. In order to address such under-development in irrigation and the challenge to poor maintenance for the existing irrigation facilities, among other challenges, the plan aims at accelerating the development and rehabilitation of irrigation facilities as well as a partial transfer of the O&M responsibilities of National Irrigation Systems (NISs) from NIA to Irrigators Associations (IAs).

1.4 The project site for the MMIP II has not been yet socio-economically developed. The agricultural production is low in spite of its potential being high, and thus improvement on irrigation facilities and agricultural productivity is an important development issue in the area. Based on these circumstances, MMIP II is expected to contribute to poverty reduction and long-lasting peace of this area. MMIP II could benefit the population of this area by bringing about an economic development through the irrigation development, hence, the MMIP II should be implemented/ completed as early as possible, and accordingly this Preparatory Survey is commenced.

1.5 In fact, this Survey was initiated by a request for Japanese ODA loan funding to the Lower Malitubog Service Area (LMSA), or to a part of the LMSA as MMIP II has been undergoing since year 2011. However, it is noted that flood simulation undertaken in this Survey revealed that dyke construction surrounding the LMSA for the purpose of protecting the area from flood coming from Pulangi river is not feasible technically and financially. With this outcome in which dyke should not be constructed, NIA has recognized that the current NEDA approved budget could be enough to complete the remaining parts of the MMIP II.

1.6 NIA issued a letter to Department of Finance on May 22, 2018 stating that NIA would intend to

withdraw its proposal for the funding of MMIP II through the Japan ODA financing as NIA believes that the remaining balance is too inconsequential for it to be funded by ODA loan. Following this NIA's action, government officials of the Philippines raised during a Japan-Philippines Economic Cooperation Infrastructure Joint Meeting held on June 21, 2018 that the GOP withdraws the ODA loan request for the MMIP II.

1.7 With above withdrawal, this Survey now places priority more on its feasibility and sound development plan formulation of the LMSA. The outputs of the Survey are thus the recommendations of the project components, and investment scale of the MMIP II with feasibility evaluation, including measures against flooding. The Survey is therefore to investigate and analyze the different aspects of the project and consolidate the results in form of a project implementation plan taking into account the impact of Pulangi river flooding.

2. THE PROJECT AREA

2.1 The Project, Malitubog Maridagao Irrigation Project (MMIP) is composed of MMIP I and MMIP II, and the entire Project area covers 17,709 ha consisting of 7,173 ha from MMIP I and 10,536 ha from MMIP II. The Project site is spread over 5 municipalities of Carmen, Kabacan, Pikit, Datu Montawal and Pagalungan. The first 3 municipalities fall in Cotabato province while the latter 2 municipalities in Maguindanao province (ARMM). A total of 13,343 farmer households or 67,114 persons was estimated to be benefitted from the entire MMIP (5,518 households from MMIP I and 7,825 households from MMIP II).

2.2 The Project area of MMIP I starts at the diversion point established on the Maridagao river, through which water is withdrawn into the Maridagao Service Area (MSA), and then after crossing the river with a siphon, it irrigates the Upper Malitubog Service Area (UMSA) upstream site. The irrigation water further reaches to the MMIP II area, namely, UMSA downstream site, the Pagalungan Extension Service Area (PESA) and the Lower Malitubog Service Area (LMSA). Thus, the MMIP area extends over from north to south, approximately 27 km, and from west to east about 30 km. The diversion point has the highest elevation of 35 m, while the most downstream point has the lowest elevation, almost 0 m.

2.3 The implementation of MMIP I was commenced in April 1993 and completed in 2011, thus it took more than 17 years to be completed due to unstable peace and order in and around the Project site. The total project cost for MMIP I amounted to 3,184.34 million Php equivalent to JPY 8.43 billion, and out of which, JPY 4.541 billion was from the Japanese ODA Loan. In the same year 2011, MMIP II was started, and as of July 2018, leaving the area for which ODA Loan was originally requested, the MMIP II area has been either completed, under construction, or to be worked by already awarded contractors. For the MMIP II, the NEDA-ICC approved project cost is 5,444.84 million Php.

2.4 The Project area has a tropical wet climate being constantly moist, represented with year-round rainfall. There is not much temperature fluctuation throughout year ranging from 20 to 35 Celsius degree, with a bit of increase in March – May. The monthly basis rainfall indicates no clear demarcation between seasons; however, it is generally said that the rainy season is from May to October while the dry season is from November to April of the following year. The annual rainfall in the Project site marks only 902 mm, of which about 40% falls during the dry season, while the annual rainfall at the most upstream edge of the catchment area marks as much as 6,477 mm.

2.5 The population growth ratio in the Project area is higher than that of the national average. In 2015, the population of Cotabato province marked 1,373,962 and its land area covered 9,317 km², giving 148 persons per km² population density. The average household size was 4.29. On the other

hand, the population of Maguindanao province was 1,172,381 with the land area of 9,968 km², showing the population density of 118 persons per km². The average household size was 6.03. The Census of Population and Housing 2010 estimated about 1.7% and 1.8 % population growths for Cotabato province, Region XII, while approximately 2.2% and 2.4% for Maguindanao province and ARMM.

2.6 ARMM is agriculture dominated region, while Region XII is not such, although the agriculture production dependency is decreasing in both regions. In Region XII, the primary sector of agriculture, hunting, forestry and fishing shared 26.2% of the gross regional domestic product (GRDP) in 2015, while that of ARMM did as high as 59.3% of the GRDP. It is clearly found that agriculture industry has been prevailing as the main industry as compared to the national average; accounted for around 30% and 60% as of 2015 in Region XII and ARMM respectively. Further, changes in times look differently by region.

2.7 In order to identify the impact of the MMIP I and to set baseline values for the project area, a baseline survey was conducted by JICA team in the MMIP I and MMIP II areas from June to July 2017. In all the eight barangays, farming is the primary livelihood; however, those villages belonging to LMSA tend to have larger share of non-farmer households. The average cultivated land per household is about 1.52 ha, out of which 1.48 ha is self-owned. Most of the farmers can be categorized as “small scale farmers” with 0.5 - 1.0 ha farmland. For both irrigated/ rain-fed lowlands, the major crops are rice, coconuts, corn, and sugarcane.

2.8 The average farmer household income examined through the baseline survey is Php 120,914, which is lower than the average of Region XII, Php 198,438, while it is higher than the average of ARMM, Php 85,514. However, the average income per capita, Php 22,987, is only slightly higher than the 2015 poverty line of Region XII, Php 21,025 and that of ARMM, Php 21,563. There is a clear tendency that farmers in the area with access to water for agricultural use depend much on cropping income, while farmers in the area that is prone to flood damages have diversified their income sources. When compared, female headed households earn less income from cropping, yet more variety in income sources than male headed households.

2.9 “Damage by pest and disease” and “Bad / poor transportation road to market / millers” are the most needed issues to be addressed in farming. When disaggregated, “Unstable Rainfall” and “Occurrence of Floods” should be addressed in the rain-fed agriculture areas, while “Water shortage of irrigation” is the one in the irrigated agriculture area. In this regard, it can be said that the proposed plan has relevance to implement.

2.10 Liguasan marsh is the largest marsh in the Philippines. Its size has been reported to be 220,000 to 288,000 ha with 40 km length and 20 km width along the Pulangi river. The Project area, especially LMSA, is located at a middle part facing north-eastern side of the marsh. Liguasan marsh is a wetland ecosystem, which performs significant ecological functions. For instance, it reduces the impact of flood in the Cotabato river basin and sediment loads carried by the floods are deposited and filtered in it. Plants in the marsh absorb excess nitrogen and phosphorous from sewerage and other pollution causing effluents. The marsh also has a rich biodiversity, and it is known as a home of endemic species of flora and fauna and it provides feeding ground for various migratory birds.

2.11 Liguasan marsh is, for some Lumad people, the place of origin of lives. Not only fauna and flora, but also people are living within the area, and its population as of 2015 could be estimated as almost 582,000 with the population density of as high as 171 persons/km². Many people living in the marsh may know how to cope with or utilize the impact of frequent flooding. Inland fisheries activities by utilizing gill-nets are popular livelihoods for the population to catch tilapia, carp, mudfish, freshwater goby, and freshwater shrimp, and so forth. Other than the marsh areas, flat lowland is

already used for paddy (palay) cultivation, especially during the dry seasons.

2.12 The production of major crops in Pikit Municipality, covering most areas of MMIP, shows that paddy and maize are the 2 leading crops in the MMIP area, since planted area of the both crops accounts for about two-thirds, 65%, of the total harvested area of the major crops. Fruits and tree crops, mainly coconut, could also be important crops after the 2 leading crops in the area. The 3 major crops, i.e. paddy, maize and coconuts, occupy as much as 87% of the total harvested area in the Municipality.

2.13 The JICA team analyzed satellite images in order to clarify cropping area in the MMIP area. According to the analysis, while cropped area of paddy in LMSA was 511 ha in rainy season and 655 ha in dry season of 2015/2016, that of maize was 1,510 ha and 1,071 ha, respectively. Though lots of farms could be seen in this area on Google Earth, the total cropped area shares only 22% in rainy season and 19% in dry season of the gross area and they are scattered over this area. It is predicted that especially in rainy season, farmers would hesitate to plant crops due to the high frequency of flooding.

2.14 Paddy rice is almost exclusively grown in irrigated areas. Two crops of paddy rice in a year is common cropping pattern in the irrigated areas as is practiced in already completed MMIP areas such as Maridagao Service Area, Upper Malitubog Service Areas (MMIP I) and parts of the Upper Malitubog Service Area developed under MMIP II. Coconuts, banana and vegetables are grown in surrounding areas of the paddy fields even on a border ridge/pass of paddy fields. Since LMSA is still under construction, rain-fed paddy rice and corn are dominant crops in wet season and also grown with residual moisture during dry period when inundation water level downs.

2.15 According to relevant statistical data of various sources, yield of rain-fed rice ranges from 2.0 ton/ha to 3.5 ton/ha and that of irrigated one does from 3.0 ton/ha to 5.63 ton/ha. Besides, the baseline survey conducted by JICA team clarified that they are 1.69 ton/ha and 3.38 ton/ha for the rain-fed paddy (palay) and irrigated paddy respectively, and yield of corn is 2.12 ton/ha. Further, the satellite image analysis conducted by the JICA team revealed that the current crop intensity in LMSA is 72% in rainy season and 47% in dry season. Upon completion of irrigation facilities, farmers can expect higher crop intensity even during dry season.

2.16 Various DA agencies including ATI, universities and colleges have been involved in providing the extension services directly to farmers. In addition, a Yen Loan Technical Assistance (YLTA) was implemented in order to increase productivity of rice in the MMIP project area through enhancement of farming skills and financial management of target Irrigator Associations (IAs). YLTA had 3 major components; namely, 1) Participatory Demonstration Farms, 2) Farm Production Input Assistance, and 3) Development of Extension Modality. On the achievement of YLTA, the productivity of rice in all the selected 7 IAs remarkably increased after the intervention and the average increase was 2.70 ton/ha from 2.93 ton/ha to 5.63 ton/ha.

2.17 The Malitubog-Maridagao Irrigation Project (MMIP) was set out with the technical assistance in the feasibility study conducted from 1985 to 1988, which was financed by ADB. MMIP was divided into two phases: the Phase-I (MMIP I) to irrigate 10,840 ha; and the Phase-II (MMIP II) to irrigate 8,760 ha. MMIP I was commenced in October 1989 with an assistance of Japanese ODA Loan, and the actual construction works was started in April 1993. However, the project was often interrupted due to recurring armed conflicts. Finally, the MMIP I had completed the MSA and a part of UMSA (upstream site) on October 31, 2011. As of April 2017, the net irrigable area for MMIP I is 7,173 ha, with a break-down of 5,562 ha in MSA and 1,611 ha in UMSA (upstream site).

2.18 MMIP II started in January 2011 aiming at generating 9,784 ha of irrigable area in UMSA (downstream site), LMSA and PESA and its target of the total irrigable area was later expanded to the 10,541 ha. As of May 2018, the irrigable area which has been generated since the commencement of

the MMIP II arrives at 5,513 ha, namely, about 53% of the MMIP II target. This consists of: 2,958 ha in UMSA (downstream site), 1,567ha in LMSA and 988 ha in PESA. As of May 2018, the total area under operation of MMIP II is 1,478 ha, which is a part of UMSA (downstream side).

2.19 The total lengths of main canal and lateral canals of MMIP II are planned to be 66.8 km and 100.2 km totaling 167.0 km. The total numbers of the canal structures and the turnouts are planned at 207 and 412. For the on-farm development, construction of total 168.85 km of on-farm canals with 1,605 farm structure is planned. Total 323 steel gates are planned for water management purpose. In addition, a total length of 127 km of main and lateral drainage canals together with the total length of 94.18 km of farm drainage canals are also to be constructed. The completion date of the project was originally planned in December 2015, however it was extended to December 2019 as of May 2018. The progress rate of the Project is evaluated at 45.9% on the basis of value of accomplishment and at 40.7% on the basis of actual expenditure.

2.20 Maridagao River Irrigation System (MRIS) Management Office, which is in the Operation & Maintenance Section of Cotabato Irrigation Management Office (CIMO) under the NIA Region XII, has the responsibility of O&M for the irrigation systems such as diversion dam, siphon, main canal and lateral canals in service area of MRIS. The O&M costs for the facilities and day-to-day operation activities are covered under the CIMO's and MRIS management office's budgets while the NIA Central Office has a budget framework to finance major maintenance and rehabilitation works as needed. Approved corporate operating budget for MRIS is 6,472,519 Php for personal service (PS) and 3,663,373 Php for maintenance and other operation expenses (MODE) for an average of past 5 years.

2.21 Under MMIP I, there are 12 IAs within the Maridagao Service Area (MSA) and 2 IAs in the Upper Malitbog Service Area (UMSA) upstream site, totaling to 14 IAs. Under UMSA (downstream site) of MMIP II, initially 2 IAs were established and have been operating since 2013. In 2017, another 5 IAs were established and started operation. Further, additional 4 IAs, which has been already registered, will start operation within 2018, and therefore there will be total 11 IAs to be established in the UMSA (downstream site) of MMIP II. For the Pagalungan Service Area, till May 2018, 3 IAs were established and registered, and for LMSA 13 IAs were established and registered to date and another 8 IAs are to be established in the coming years of 2019 – 2020.

2.22 3. FLOOD SIMULATION

3.1 LMSA is a flood prone area and the flood is caused by water spilling over natural leaves and flowing into the hinterland on the right side of the Pulangi river in the rainy season. While in the dry season, permanent water remains only along the Pulangi river and also along the main channels in the left side of the river. In the peak period of rainy season, most of the areas are once covered by water at least one month. However, in the dry season, only several separate pond-like waters remain in such areas deeply depressed. Water extent in 50% recurrence, i.e. return period 2 year, which can be regarded as normal hydrological year, covers 34% of LMSA while leaving 66% as surface land area according to a satellite image analysis (44% water extent in case of maximum inundation).

3.2 Flood protection dike may be considered as a measure to protect LMSA from floods. Two dike alignments are considered; one along the peripheral of LMSA and the other along the right bank of Pulangi river. The latter case option, if dyke should be constructed, is selected due to economical and technical feasibility. While a foundation work is required to stabilize the dike because the basement of the dike is very soft. Finally, sand compaction pile method is selected as a suitable foundation work due to its construction cost advantage. Although the dike works in protecting LMSA from flood, it makes the flood condition of the Liguasan Marsh serious and causes inland inundation within the

LMSA by rainfall originating from inside of the dike. Additionally, the dike would act as a physical border dividing the vicinity areas socially and environmentally.

3.3 Dredging of the Pulangi river may be considered as another flood protection measure as it works to increase flow capacity of the Pulangi river while reducing the flood volume spilling over natural leaves. Though dredging works would mitigate flood damages in LMSA and it would not work as a physical border like flood protection dike, it may cause; 1) drying up of parts of the Liguasan marsh, and also 2) change of ecosystem of the Pulangi river, etc.

3.4 As rough assessment of the positive/negative impacts by construction of the flood protection dike and dredging, preliminary examinations are carried out under the three cases in the table below:

Table 3.1 Summary of Simulation Cases (Preliminary Examinations)

Case		Purpose	
1	Flood Simulation by Simplified Storage Model	✓	To assess maximum flood discharge, maximum flood water level and maximum inundation area
2	Inland Inundation Simulation by Simple Rainfall-Evaporation Model	✓	To assess the inundation area in the LMSA
		✓	To assess the necessity of any drainage facilities
3	Dredging Simulation by the Uniform Flow Calculation	✓	To assess required dredging volume

Source: JICA Survey Team

3.5 On the Flood Simulation by Simplified Storage Model, catchment area at the bottle neck point, at which there is a narrow flow point between two hills near Datu Piang, is taken as a simplified storage reservoir and flood simulation are carried out by employing rational formula in order to assess; 1) maximum flood discharge, 2) maximum flood water level, and 3) maximum inundation area under present condition (i.e. without dike) and after construction of the dike (i.e. with dike). The results of the simulation show that water level after construction of the dike becomes 25cm and 31cm higher than those of the present condition under 30-year and 100-year return period respectively. Additionally, inundation area in the Liguasan marsh is enlarged by around 10% by the construction of the dike.

3.6 Inland Inundation Simulation by Simple Rainfall-Evaporation Model is meant to assess; 1) maximum inundation area of LMSA, 2) maximum inland flood water level of LMSA, and 3) damages on the designed irrigable area by inundation. This is because as LMSA is enclosed by a dike, inland inundation will be occurring originating in rainfall. The results of the simulation show that even in case of 2-year return period, 28.9% of the irrigable area is inundated and about half of the irrigable area is inundated in case of 10- year return period. According to these results, drainage structures should be required to reduce the inundation whereby keeping the beneficiary area. Though pumping stations are considered as a drainage measure, those are not economically feasible due to high initial cost and not technically feasible due to difficulty of the O&M including electricity unavailability.

3.7 Dredging Simulation by the Uniform Flow Calculation is conducted in order to assess the impact of the dredging which may work in mitigating flood damages in and to the LMSA due to its increased capacity of flow of the Pulangi river. As low flow capacity at the bottle neck point is considered as one of the main causes of the floods in and to the LMSA, a cross section formation at this point with enough flow capacity able to mitigate flood damages in and to the LMSA is examined. The results show that; 1) it is possible to mitigate flood damage in LMSA by dredging, however 2) dredging from bottle neck point to river mouths are required and 3) dredging volume becomes 306 MCM, indicating economically not feasible.

3.8 In addition to the simple preliminary examinations above-mentioned and further to assess in detail positive/negative impacts by the construction of the flood protection dike and also by the dredging, unsteady non-uniform flow simulations are carried out under three cases as shown in the table below:

Table 3.2 Simulation Cases for Detail Hydraulic Simulations by Unsteady Non-uniform Analysis

Simulation Cases		Purpose	
1	Flood Simulation with/without Dike	✓	Determination of the inundation area and flood water level
		✓	Assessment of the impact by the construction of the dike, especially impacts on the Liguasan marsh
2	Inland Inundation Simulation with/without Drainage Structures	✓	Assessment of inland inundation within the LMSA after the dike construction
		✓	Examination of the necessary structures to mitigate the inland inundation
3	Flood Simulation with/without Dredging	✓	Assessment of the necessary dredging volume of the Pulangi river to protect the LMSA from the flood. Note that the dredging considers 2 cases; 1) dredging along almost whole stretches of the Pulangi river and 2) dredging or widening of the bottle neck point.

Source: JICA Survey Team

3.9 Flood Simulation with/without Dike is conducted to calculate the change in water level on the Liguasan marsh and the Pulangi river, and also change in terms of inundation area on the Liguasan marsh between with and without dike. After construction of the dike, inundation area on the Liguasan marsh would be expanded by 19% in case of 2-year Return Period (RP) and 34% in case of DPWH design RP, 100-year. In addition, maximum water level on the Marsh would become 79cm and 80cm higher than the case of without dike under 2-year and 100-year RP respectively.

3.10 Further in addition to above, current design height of the dike is based on the past maximum flood water record (flood in 2009), which is EL. 8.01m at the most downstream area of LMSA. According to the simulation result, this height corresponds to the flood of 40-year return period, and the river water level further rises by 50cm in this case as the dike works in reducing the overflow area of the flood. Since the current NIA design does not consider this additional water level rise, it is necessary to have the design height of the dike 50cm higher than the current NIA design, should the dike be constructed. The cost for the modified design is estimated to be approximately 2,295 million Php (5,186 million JPY).

3.11 According to the afore-mentioned preliminary examination, a measure to drain inland water is required but pumping stations are not feasible. In this Inland Inundation Simulation with/without Drainage Structures, sluices are installed as an alternative drainage measure and required numbers of those are assessed. The sluices are of flap-valve type, which stops flood coming into LMSA from the Pulangi river while releases the inland inundation when the water level of Pulangi river is lower than that of LMSA. In the simulation, 2 to 100 sluices, which are 2m height × 2m width each on the ground at EL.4.5m (the lowest elevation of the LMSA), are applied, and the sluices are set at Paidu Pulangi, the most western part of LMSA.

3.12 Inland Inundation Simulation with/without Drainage Structures shows that in case of 2-year return period, 48% of LMSA becomes inundated even if 100 sluices are installed, while 52% would be inundated without sluice. Likewise, in case of the 30-year return period, 71% becomes inundated with 100 sluices while 82% without sluice, indicating that the impact of the sluices is very limited. This is because the water level on the Pulangi river remains higher than the water level in the LMSA during most of the rainy season, unable to drain the inland inundation out to the Pulangi river. In case of 2-year return period, the result shows 30 sluices (50 sluices with 30-year RP) enable the water depth in the LMSA to be nearly zero from December and thus the farmers able to start rice cropping on the whole LMSA. However, in rainy season, almost half of the LMSA is still not possible to cultivate due to the inundation, and also the construction cost is estimated at 2,412.3 million Php (5,451.6 million JPY).

3.13 In the preliminary examination, dredging formation and its required volume were assessed at the bottle neck point only. To assess dredging formation and its required volume in detail, this Flood Simulation with/without Dredging is carried out. The simulation indicates that even to mitigate the

damage on the LMSA by flood in case of 2-year return period, the required expansion width is as much as 500m all along the target river sections, i.e. from the upstream of LMSA to the bifurcation point of the Pulangi river into Rio Grand Mindanao river and Tamontaka river (total 95 km). . In this case, construction cost (direct cost only) is estimated at 22,080 million PHP (49,901 million JPY). Since it is only for dredging cost, the cost for the other work items such as dehydration, transportation of the dredged soil, land acquisition for disposal pit and so on are additionally required, indicating not feasible for this dredging.

3.14 According to the above-mentioned results of Flood Simulation with/without Dredging, dredging over as long as approximately 95km is required and its volume and cost are too huge. Meanwhile, low flow capacity of the bottle neck point is one of the reasons to cause flood in/towards LMSA, and therefore it is considered that dredging of only around the bottle neck point, so-called partial dredging, may contribute to mitigating the flood damages to LMSA. Based on the simulation, even in case with 500m expansion of the cross sections around the bottle neck point, flood damage in LMSA cannot be eliminated completely. Of course, a part of beneficiary area which is inundated without dredging becomes dry and possible to cultivate. However, its cost of generating one unit hector of dry land is estimated at 4.88 million PhP/ha in the minimum case, which is much higher than 0.52 million PhP/ha of the original unit-hector development cost of MMIP II.

3.15 According to a series of flood simulation and dredging simulation, as afore-mentioned, it could be hardly possible to construct the dike because; 1) flood protection dike makes flood condition in the Liguasan marsh serious, 2) flood protection dike leads inland flood originating in rainfall in LMSA, 3) as a drainage measure for the inland flood, pumping stations are not feasible, 4) while sluices could be selected as another drainage measure, 30 sluices are required even to eliminate inland flood in case 2-year return period and its cost come to 2,412.3 million PhP (5,451.6 million JPY), and further even if 30 sluices are installed, almost the half of the LMSA is inundated during rainy season, 5) for the dredging, even in case of 2-year period, 345MCM dredging with construction cost 22,080 million PhP (49,901 million JPY) is required, and 6) effect of partial dredging is also very limited and still costly.

4. DEVELOPMENT DIRECTION AND PROJECT COMPONENTS

4.1 Development Direction

4.1 MMIP II should be designed by learning from the experience of MMIP I. There are five lessons learnt from MMIP I. First, it is important to take necessary measures to avoid the inundation in lower places of the area. Secondly, the land acquisition should be well prepared to settle multiple claimers. Thirdly, the transparency and equitability in the distribution of benefits among beneficiaries should be maintained. Fourthly, responsibilities between NIA and the beneficiary farmers should be set realistic to make sure that on-farm ditches are developed. Lastly, the scale of construction packages should be large enough to attract contractors with enough capacity in order to avoid delays in the works.

4.2 On the other hand, four major impacts generated by MMIP I are recognized by local people. First, increases in the crop production and income of the beneficiary farmers are recognized. Secondly, the access to markets and any other socio-economic services for the farmers and their family members has been improved due to the roads constructed. Thirdly, food security and the sustainability in the farming of farmer beneficiaries have also been improved. Lastly, those people involved in conflicts returned and are now engaged in farming activities as livelihoods, and thus many local people affirmed that the Project (MMIP I) has contributed to maintain peace and order in the area.

4.3 As the afore-mentioned flood simulation revealed, there should be NO dike construction for the purpose of protecting the LMSA from flood. Instead, 2 cases of development of irrigation networks for

the LMSA should be explored; i.e. 1) construct the irrigation network up to the peripheral delineated, within which the paddy cultivation can still be managed with allowable inundation depth (Case-1), and 2) construct the irrigation network as originally planned (Case-2). For the latter case, mid-lower parts of the irrigation network will be inundated every year during rainy season, however during dry season full beneficial area could be cultivated, on condition that damaged parts during the flood season are to be well maintained/ repaired.

4.4 In the construction remaining parts of LMSA, main canal (MC 2) and associated lateral canals of the MC 2 and MC 3 (already completed) should be constructed according to the coverage by case afore-mentioned, and main drainage canal and lateral drainage canals should be constructed as per the original plan. The construction of intra-roads, which work as farm-to-market road in order to ship agricultural produces out of the farmlands as well as to facilitate rural population's mobility especially during rainy season will have to be done. Agriculture development and the extension service delivery should also be addressed so that the beneficiary farmers can well utilize irrigation water, whereby 2 times irrigated paddy cultivation will be established.

4.2 Agriculture and Extension Development

4.5 The Philippine Development Plan 2017-2022 was officially approved by National Economic and Development Authority (NEDA) Board on February 20, 2017. The new strategy applied to the said plan would put more focus on the strengthening of overall farm productivity and profitability on a sustainable basis. With this, corn, rice and coconut are the dominant crops planted in the Project area under the rain-fed agriculture system. As explained in the strategy, two-time cropping of rice in a year is expected in all the irrigated areas developed by the Project. The Project, however, should maintain the existing coconut trees and some other perennial crops.

4.6 On the whole, the growing area and productivity will be remarkably increased by the Project upon completion. The current annual production of rice and corn in LMSA is estimated at 5,354 tons (1,401 for rice and 3,953 for corn) and that in the MMIP II area is 8,559 ton (2,240 for rice and 6,319 for corn). After the completion of the Project, the annual rice production will be increased to 30,541 tons in the Case-1, and to 48,880 tons in the Case-2 in LMSA. The same in the entire MMIP II area will be increased to 67,633 tons in the Case-1 and to 85,972 tons in the Case-2.

4.7 Although 3,688 ha of land in LMSA is expected to be irrigated and planted in the Case-1, the area during the rainy season is to be reduced to 2,810 ha due to inundation, and 1,940 ha of land will be inundated up to 0.5m in the depth. The irrigated rice production would have some damages on its productivity due to flooding. In Case-2 where the canal network is constructed as per the NIA-PMO original plan, due to the significant production in the dry season the production through the year is much larger than that of the Case-1. In order to mitigate reduction of the productivity in the inundated area, submerge-tolerant varieties, such as NSIC RC 222, should firstly be tested on farmer fields.

4.8 To ensure positive outcome and impact of the infrastructure development in terms of farmers production and income, it is recommended that the Project should implement an agriculture and extension development program by ATI and other major stakeholders, consisting of:

- ✓ Technical assistance for irrigated rice production; MMIP II should support ATI in the continuation of the provision of technical assistance by applying the same approach of the Yen Loan Technical Assistance (YLTA) until the remaining part of the MMIP area is covered. This should concentrate on 28 IAs which have neither received supporting services from YLTA nor additional program of GOP.
- ✓ Enhancement of agriculture extension services at the municipal level; the capacity of the LGU

extension workers should be strengthened so that they can fulfil their mandate of the provision of agriculture extension services. The activity should provide a step-wise training including technical and on-the-job trainings to Municipal Agriculturist and Agricultural Technologists in Cotabato Province and, Municipality Agriculture Officer and Agricultural Technologists in Maguindanao Province, those who are working at municipality level.

- ✓ Development of seed production; the production of rice seeds within the MMIP area should be further enhanced to meet increasing demand by farmers as the Project goes by. This pursues establishment of community based, meaning IA based, registered or certificated seed production system rather than building large-scale seed center producing foundation seeds.

4.9 In addition to the above-mentioned agriculture and extension development program, MMIP II is also recommended to address crop diversification and agriculture mechanization in order to ensure its positive outcome and impact on farmers. To promote crop diversification, high value and market oriented commodities such as vegetables could be promoted in upland areas, while rice cultivation should prevail in lowlands. In order to initiate crop diversification, the promotion of home gardening with vegetables should be considered, since they can contribute to balanced diet for farm households, and to additional income.

4.10 The agricultural development strategy of the Philippine Development Plan 2017-2022 stresses agricultural mechanization as an important tool to attain improvement of the agricultural productivity. As pre- and post-harvest machineries are required to improve the productivity in the irrigated agriculture, in addition to what were mentioned in above agriculture and extension development program, the Project further recommends to support the machine assembling at the local level and to enhance the knowledge and skills of farmers in the operation and maintenance of agriculture machineries.

4.3 Irrigation and Drainage Development

4.11 The lowland parts of the Lower Malitubog Service Area (LMSA) are inundated during the rainy season. Without dike for flood protection, inundation condition will be the same as the present one. Therefore, the setting of target irrigable area for the LMSA shall be made based on the inundation condition. After that, the project components should be planned based on the irrigable area planned. According to the satellite image analysis, if the dike is not constructed, 44% of LMSA would be inundated. In this case, it is impossible to develop 6,590 ha of all the irrigable area of LMSA, and only 3,688ha (about 56 % of planned irrigable area) could be available for the development. In the target area for the remaining portion from the works of year 2019, only 1,001 ha will be available for the development, while 2,133 ha could have been developed if whole LMSA were to be developed.

4.12 The area to be inundated in the rainy seasons can be irrigated during the dry seasons with the construction of all the planned irrigation canals. In this case, countermeasures of avoiding damages on the irrigation canals from flood are necessary, which could be such works as raising height of canal embankment, slope protection on the slope of embankment and introduction of concrete flume canal at the end portion of lateral canals and on-farm canals instead of the originally planned earthen canal. Accordingly the project cost will be increased and maintenance costs will also be raised. Therefore, the project should select either one from the two cases; namely, Case-1: target area is parts of LMSA with the construction of parts of the irrigation canals, and Case-2: target area is the same as all the LMSA with all the irrigation canals constructed as per the NIA-PMO original design.

4.13 NIA has conducted a survey for the assessment on the impact of the past floods within MMIP whole area in year 2010. In this survey, an interview survey was carried out to the residents of 49

Barangays within the MMIP area to confirm any information of the floods, e.g., frequency of flood occurrence, depth of flood, flooding period, etc., together with the location information by GPS. Based on these survey results, the flooded areas had been categorized in that Lower Malitubog Service Area (LMSA) has the highest record of flooded area with about 5,720 ha equivalent to about 87% inundated. It means that only 870 ha of areas can be said free from flood throughout year.

4.14 However, out of the 5,720 ha area inundated, there are total 2,940 ha of areas with flooded water depth of not more than 50 cm is possibility. This 2,940 ha of area has a potential being the part of target irrigable area since rice is resistant to certain level of flooding. Magnitude of damage of paddy by inundation varies with the timing of inundation, duration and the depth of water. Based on an estimated paddy production loss by inundation (statistic information from Divisional Agriculture and Forestry Economic Bureau) and by taking into account the fact that the planned rice would grow to 100 cm or more at the booting period, the allowable inundation depth could be set at 50 cm in order to prevent the damage mainly in the booting period. Target service area to be developed and irrigable area are set as shown in the table below:

Table 4.1 Target Irrigable Area by Case (Case-1; Partial Development, Case-2: Full Development)

Category	Case-1	Case-2	Remarks
Target Developed Service Area	3,688 ha	6,590 ha	Counted as the dry season irrigable area
Non-submerged area by flood	870 ha	870 ha	Included in the target irrigable area in rainy season
Flooded area of up to 0.5 m	1,940 ha	2,940 ha	Can/should be included in the target irrigable area in rainy season, though this area will be affected by flood.
Area of Non-submerged + Flooded area up to 0.5m	(2,810 ha)	(3,810 ha)	Total target irrigable area in rainy season.
Flooded area of more than 0.5 to 1.0 m	878 ha	2,780 ha	Excluded from the target irrigable area of rainy season.

Source: JICA Survey Team

4.15 The irrigation canal system for LMSA consists of 2 main canals, namely Main Canal No.2 (MC-2) and Main Canal No.3 (MC-3), which are branched at the end of RMC ECT-1, and total 31 lateral canals for the originally designed irrigation area of 6,590 ha. The total length of canals arrives at 107.3 km, divided into about 34.2 km for the main canals and about 84.5 km for lateral canals. The canal lining is planned only for the main canals with concrete lining; while lateral canals are planned to be of earthen canals without lining.

4.16 In case of NO dike construction, all or parts of irrigable areas to be covered by Lateral canal D, D-3, E, F, G, J, K, L, L-1, N, N-2, O, O-1, O-1-1, O-2, and O3 will be inundated during rainy season. Accordingly, those canals mentioned here should be removed totally or partially from the project components under Case-1 where the canal network will be limited only to the areas inundated not more than 0.5m. In this case, the length of main canals will be reduced to 23.0 km from 34.2 km, and the length of lateral canals is to be reduced to 57.8 km from 84.5 km, and thus the total length of canals are to be 69.4 km from the originally designed 107.3 km.

4.17 On the other hand, however, despite whichever case for the canal network establishment is decided by NIA, all the drainage canals should be constructed as per the original design for the sake of improvement of the drainage system in the LMSA. Such improvement on the drainage system will facilitate farmers not only in the irrigated areas free from flooding but also in the inundated areas to start the dry season farming immediately after the rainy season. It is noted that since the elevation of the major part of LMSA is lower than that of flood water level of the Pulangi river, drainage facilities with flap gates should be installed at connection points to the Pulangi river to prevent back-flow of water.

4.18 On Case-2 in which target area covers all the LMSA with the construction of all irrigation

canals and all drainage canals, parts of the irrigation canals will be affected by flood every year. Therefore, countermeasures to mitigate damages on the irrigation facilities are necessary. The countermeasures could be such those as; 1) raising height of canal embankment, 2) slope protection on the slope of embankment, 3) concrete lining inside canal and 4) replacement to the concrete flume canal at end portion of lateral canals and field canals from earthen canal.

4.19 In order to compare the irrigation development cost per hector of both cases in LMSA, the direct cost of civil works was estimated. Unit costs of the works required are the same as the unit costs NIA-PMO has applied for the cost estimation in 2018. The total direct construction cost of irrigation development in LMSA comes to 2,356 million PHP (4,878 million Japanese yen) in Case-1 whose target area covers only parts of LMSA with the construction of partial irrigation canals and all drainage system, and 3,228 million PHP (6,682 million Japanese yen) in Case-2 which target area covers all the LMSA with all irrigation canals and all drainage canals as per the original design.

4.20 In Case-1, an irrigable area of 3,688 ha is to be developed, and therefore the irrigation development cost (direct construction cost only) per hector comes to 639 thousand PHP (1,323 thousand Japanese yen). On the other hand, under Case-2, the irrigable area of originally designed 6,950 ha is to be developed, and therefore, the irrigation development cost (direct cost only) per hector arrives at 490 thousand PHP (1,014 thousand Japanese yen). Unit development cost of Case 1 is higher than that of Case 2 since main canals and lateral canals already constructed or being constructed are already of the size corresponding to those of Case-2 (originally designed ones).

4.21 The Maridagao River Irrigation System (MRIS) Management Office, which is in the Operation & Maintenance Section of Cotabato Irrigation Management Office under the NIA Region XII, has the responsibility in the operation of the irrigation systems and the maintenance of main structures such as diversion dam, siphon, diversion canals, main canals and lateral canals in the Service Areas of MMIP I. Concerning MMIP II area, the service areas under seven IAs in UMSA were already handed over to the MRIS Management Office from the PMO. Thus, after the completion of the project, all irrigation systems and drainage systems will be handed over to MRIS Management Office from the PMO for its operation and maintenance.

4.22 According to the current staffing structure and appointment status of the MRIS Management Office, all the 21 positions were filled as planned. The executing agency has not reported any significant O&M constraints due to shortages in staffing. Routine (day-to-day) and monthly inspections based on pre-set maintenance items are conducted in order to identify probable incidences as early as possible. However, after completion of the project, the Service Area will be expanded up to almost two times of the current service area, and therefore, NIA should increase the staff engaged in the O&M based on the size of service area and work volume.

4.23 The MRIS Management Office has their own machinery for maintenance of irrigation canals and drainage canals including service road. According to the MRIS Management Office, with the existing equipment, they narrowly manage all the necessary repair works and rehabilitation works required in the operation & maintenance of the irrigation system; however, they have difficulties in rehabilitating all the present service roads including the ones within the new irrigation Service Area of 2,206 ha of UMSA. Therefore additional maintenance machinery is necessary such as back-hoe, dozer, track, etc.

4.24 The MRIS Management Office has its own O&M Manual that consists of the following three volumes: Volume I Main System; Volume II Diversion Dam O&M; and Volume III Annexes. Some revisions should be made based on the actual irrigated area, as-built (actual) canal design and irrigation facilities in order to avoid the shortage of irrigation water especially at lower areas by proper operation. In addition, it is important to reduce the excess irrigation water which flows to low ground

level areas as drainage water in order to prevent damage by inundation. Therefore, the operation for reducing excess water should also be added to the manual.

4.25 With the development of the irrigation system, the operation and maintenance (O&M) of the facilities are to be another crucial issue to enhance irrigation performance, as well as, to sustain the facilities and ensure the water supply up to the end beneficiaries. The advantages of the IMT are considered as the beneficially-oriented irrigation management and the better cost and human allocation based on the reformation of the government irrigation sector. Farmers are the ones who use the water, conduct irrigated farming, and are directly benefited from the irrigation systems, and also, know the condition and the needs of the terminal irrigation facilities. Frequent minor maintenance by the end water users can reduce necessity of large-scale rehabilitation to be managed by the government.

4.26 Having seen above points, joint irrigation management is recommended as the potential breakthrough in enhancing the irrigation performance upon completion of the MMIP II. According to the IAs already established under MMIP I, average IA coverage area comes to 350 ha with 266 farmer memberships. This size of IAs could be manageable if the structure is stratified starting with TSAGs and then IA. With reference to the total number of TSAGs in Maridagao Service area, 174 in total, and also the 11 IAs in the Maridagao SA, one IA is to have 16 TSAGs.

4.27 In Lower Malitubog Service Area (LMSA), there are 16 laterals in total providing irrigation water to 6,590 ha of area. If there will be 16 IAs assigned to each of the laterals, the average coverage area arrives at 412 ha with 313 memberships, which are in fact bigger than what the farmers seem able to manage. Therefore, big laterals, e.g. Lateral-D, H, O have to be divided into smaller units, e.g. to 2 areas or even 3 areas. NIA-PMO is planning to add additional 5 IAs, and therefore there will be total 21 IAs, whereby a typical average IA is to cover 314 ha with 239 memberships.

4.28 The construction of irrigation canals and facilities under MMIP I was started in 1990 and finished in 2011. Some of the facilities which were constructed at the beginning of the project implementation period have already passed more than 20 years, and there are some damaged facilities which need rehabilitation, e.g. gate operation system for the headworks. The Maridagao River Irrigation System (MRIS) Management Office has a list for the items for rehabilitation/ improvement of the irrigation and drainage systems constructed under the MMIP I, which may be implemented as another project in future.

4.29 NIA PMO hopes to improve the earthen lateral canals to concrete lining canals for the purpose of reducing the work load of maintenance. In addition, if NIA should select the Case-2 in which all the irrigation network is to be constructed as per original plan, targeting whole 6,590 ha of LMSA, the remaining budget would not be sufficient to construct all the remaining components. The countermeasures to reduce the damages on the irrigation canals by flood may have to be canceled. Some drainage canal may have to be canceled too. Downstream portion of some irrigation canals may further be canceled to adjust construction cost within the remaining NEDA approved budget. The cancelled component including improvement may be required as another project in future.

4.4 Distribution Infrastructure Development

4.30 Roads in and around the Project area consist of national road, provincial road, municipal road and Barangay road. In addition to these roads controlled by DPWH and LGUs, there are canal maintenance roads running in parallel with the irrigation canals under NIA. In fact, the canal maintenance roads contribute to facilitating rural mobility as has been observed in the MMIP I area. The MMIP II is to construct access road, or so-called intra-site road, which can work as farm-to-market road to ship out agricultural produces from the farmlands out to major towns, e.g. Pikit,

Kabacan, Midsayap, etc. and to the national and provincial roads.

4.31 NIA engineering section provides 4 typical cross sections of canal maintenance road as its NIA's design standard. The roadway width and the shoulder width of each of the cross sections are regulated by the scale of canal, which should vary according to canal design discharge. The large scaled canals need heavy equipment (e.g. back-hoe, long-armed back hoe and dump truck, etc.) for maintenance works, hence the roadway width should be sufficient for the passage of the heavy equipment. Meanwhile, the maintenance works for small scaled canals require small equipment (e.g. mini-back hoe and light truck, etc.) or human power only, so that the roadway width can be narrower than the large scaled one.

- ✓ Canal Design Discharge ($Q > 30$ (m³/s): Road width = 7.00m (including shoulder)
- ✓ Canal Design Discharge ($Q = 30$ to 10 (m³/s): Road width = 6.00m (including shoulder)
- ✓ Canal Design Discharge ($Q = 10$ to 0.3 (m³/s): Road width = 4.00m (including shoulder)
- ✓ Canal Design Discharge ($Q < 0.3$ (m³/s): Road width = 3.00m (including shoulder)

4.32 The maintenance works of access roads will be transferred to LGUs upon completion of the Project. Since the road design standards of LGUs have followed the design criteria of DPWH, the design of access roads should be conducted according to the equivalent design criteria. Since the functions of access roads are equivalent to those of farm-to-market roads, they are classified as the farm-to-market roads. The minimum design standards for the farm-to-market road are prescribed in DPWH's Department Order issued in 2014 (Order No.11) as follows:

- ✓ Road Width: Roadway Width (4.00m) + Shoulder Width (1.50m*2) = 7.00m
- ✓ Crossing Gradient: 1.50% (from road center to both side)
- ✓ Thickness of Concrete Pavement: 150mm
- ✓ Thickness of Aggregate Subbase Course: 200mm

4.33 "East to West Access Road" will intersect at 12 irrigation canals and 10 drainage canals. "North to South Access Road-1 & Road-2" will also intersect at 7 drainage canals and irrigation canals. Moreover, these 3 access roads are supposed to intersect at a large number of small scaled farm drains which are extended all over the Project area. The types and materials of the crossing structure will be e.g. concrete slab bridge, steel girder bridge, concrete box culvert, conduit (concrete pipe), etc., which will be determined based on the detailed survey.

5. PROJECT COST AND IMPLEMENTATION ARRANGEMENT

5.1 The MMIP II Project consists of 3 major components; namely, 1) irrigation and drainage development, 2) distribution infrastructure improvement, and 3) agriculture & extension development. The former 2 components should be undertaken by NIA while the last one, agriculture & extension development, is to be conducted by ATI of DA. In addition to those components, there are other related/ associated activities, e.g. Parcellary Mapping/ Survey, Institutional Development Program (IA establishment), Field Support for Supervision and Monitoring, etc.

5.2 Further in addition to above, this Survey recommends such works as; 1) Rehabilitation of MMIP I area (MSA & UMSA), 2) Improvement of MMIP II area (UMSA, LMSA and PESA), and 3) Procurement of machineries (for maintenance) for future works. Right now, there will be no ODA loan assistance, and therefore the remaining works should all be managed/ completed within the NEDA approved budget, so that these additional works are not included in the MMIP II works, and thus recommended as another project, say MMIP III, in future.

5.3 To implement the Project components and sub-components, the best implementation modality should be applied, e.g. direct force account, contractor/ supplier through local competitive bidding, contractor/ supplier through international competitive bidding, direct shopping, etc. One thing noted is that contractors interested in undertaking civil works in very much security concerned areas may be few in the Philippines as have been already experienced under the on-going construction works. With this in mind, the implementation modality for each of the sub-components could be classified as direct force account (DFA), and local competitive bidding (LCB) etc. as in the following table:

Table 5.1 Project Components and Implementation Agency/Modality

No.	Component	Sub-component	Agency	Procurement
1	Irrigation and Drainage Development	1-1. Construction of MC 2	NIA	LCB
		1-2. Construction of Lateral Canals under MC 2		LCB
		1-3. Construction of MDCs		LCB
		1-4. Construction of LDCs		LCB
		1-5. Construction of FAÇADE drain		LCB
		1-6. Flood Protection Works (canal slope protection, etc.)		LCB
		1-7. Urgent Works for MMIP I Area (gates and drainages etc.)		DFA/LCB
2	Distribution Infrastructure Improvement	2-1. Access Road (intra-site road) Construction	NIA	LCB
		2-2. Bridge Construction (along access road)		LCB
3	Agriculture & Extension Development	3-1. Technical Assistance for Irrigated Rice Production	ATI	DFA
		3-2. Enhancement of Agriculture Extension Services at Municipality Level		DFA
		3-3. Development of Seed Production		DFA
4	Other Related Activities	4-1. Parcellary Mapping/ Survey	NIA	DFA
		4-2. Institutional Development Program (IA establishment)		DFA
		4-3. Field Support for Supervision and Monitoring		DFA
		4-4. Project Service Facilities		DFA
		4-5. Detailed Engineering		DFA
		4-6. Other Administrative Works		DFA
MMIP III	In future, to be required	III-1. Rehabilitation of MMIP I Area (MSA & UMSA)	NIA	LCB
		III-2. Improvement of MMIP II Area (UMSA, LMSA and PESA)		LCB
		III-3. Procurement of Maintenance Machineries		ICB/LCB

Source: JICA Survey Team

5.4 Total period of the implementation is defined by, in general, the biggest component undertaken in the Project in terms of work volume as well as by such activities requiring longer implementation period, e.g. institutional development (IA establishment) and agriculture and extension development. Total implementation period for the remaining works of MMIP II is therefor set at 4 years starting from 2019 onwards with reference to the implementation speed/ progress which have been experienced in the on-going MMIP II construction works.

5.5 On the seasonal implementation plan, construction works should be conducted from September to the following year's May. Further, most south-eastern part of MC 2 and also canals/ drainages located in southern parts of LMSA will be implemented probably from December to only the following year's March since the construction sites are located along the Pulangi river, and therefore the magnitude of inundation and flooding in these areas could be bigger, resulting in shorter period of construction time. Other supportive works such as IA establishment and parcellary map updating can be done throughout year including agriculture and extension development activities.

5.6 The construction plan of "1) irrigation and drainage development", which is to construct the irrigation and drainage facilities in LMSA, has two options, so-called Case-1 and Case-2. The total project cost of Case-1 arrives at 1,350 million PHP (2,795 million JPY), out of which direct cost amounts to 1,081 million PHP (2,238 million JPY), and indirect cost amounts to 269 million PHP (557

million JPY) composed of land acquisition, VAT, price escalation and physical contingency. On the other hand, the total project cost of Case-2 arrives at 2,433 million PHP (5,037 million JPY), out of which direct cost amounts to 1,949 million PHP (4,035 million JPY), and indirect cost shares 484 million PHP (1,003 million JPY).

Table 5.2 Summary of the Project Cost (Case-1 & Case-2)

Particulars	Project Cost			
	Case-1		Case-2	
	Million PHP	Million JPY	Million PHP	Million JPY
A. Direct Cost				
1. Irrigation and Drainage Development				
1-1. Construction of the MC-2	254.99	527.83	680.96	1,409.59
1-2. Construction of the Lateral under MC-2	206.94	428.37	274.51	568.23
1-3. Construction of the Main Drainage (MDC)	35.27	73.01	35.27	73.01
1-4. Construction of the Main Drainage (LDC)	14.71	30.46	14.71	30.46
1-5. Construction of FAÇADE DRAIN	169.63	351.13	169.63	351.13
1-6. Flood Protection Works (canal slope protection, etc.)	0.00 *	0.00 *	269.65	558.17
1-7. Urgent Works for MMIP I Area				
(1) Supply and delivery of steel gates	5.72	11.84	5.72	11.84
(2) Drainage Structures	3.36	6.96	3.36	6.96
2. Distribution Infrastructure Improvement				
2-1. Access Road (Intra-site Road) Construction	114.66	237.35	141.50	292.91
2-2. Bridge Construction (along Access Road)	124.78	258.30	146.34	302.93
3. Agriculture & Extension Development				
3-1. Technical Assistance for Irrigated Rice Production	69.13	143.11	69.13	143.11
3-2. Enhancement of Agriculture Extension Services at Municipality Level	5.24	10.84	5.24	10.84
3-3. Development of Seed Production	4.33	8.95	4.33	8.95
4. Other Related Activities				
4-1. Parcellary Mapping/ Survey				
(1) Parcellary Survey	1.36	2.81	2.64	5.46
(2) Construction Survey	1.76	3.64	3.42	7.09
4-2. Institutional Development Program (IA establishment)				
(1) On-Farm Development	3.26	6.74	6.73	13.94
(2) IA Strengthening/Organizing	2.53	5.23	5.22	10.80
4-3. Field Support for Supervision and Monitoring	12.18	25.21	23.71	49.07
4-4. Project Service Facilities	1.00	2.08	1.94	4.03
4-5. Detailed Engineering	20.12	41.64	34.04	70.46
4-6. Other Administrative Works	30.17	62.46	51.05	105.68
Total of Direct Cost (A)	1,081.14	2,237.95	1,949.11	4,034.66
B. Indirect Cost				
Land Acquisition	11.12	23.02	19.00	39.34
VAT	143.08	296.19	258.44	534.97
Price Escalation	50.45	104.42	90.92	188.20
Physical Contingency	64.29	133.08	115.87	239.86
Total Indirect Cost (B)	268.94	556.71	484.23	1,002.36
Total Project Cost (A) +(B)	1,350.08	2,794.66	2,433.35	5,037.03

Exchange Rate: 2.07 JPY/ PHP, Source: JICA Survey Team

*/ Flood protection works are not considered in the Case-1 since most of the canals are to be constructed within the area less/ least affected by flood while it was well considered in the Case-2 as Case-2 is to construct all the canals as per NIA-PMO original design.

5.7 NIA had started the MMIP II project from the current year of 2011 (CY2011) with estimated total project cost of 5,444.85 million PHP (NEDA approved project cost). Table 5.3 shows the yearly allotment of project cost from CY2011 to as at CY2018, and total allotment of the project cost amounts to 3,991.35 million Php till the end of fiscal year 2018 (December 2018). Therefore, NIA is supposed to complete the remaining works of MMIP II project by using the balance of 1,453.50 million Php.

Table 5.3 MMIP II Project Cost (NIA Estimation)

Construction Year (CY)	Targeted Area	Project Cost (Yearly Allotment)
CY 2011	UMSA	200,000,000 PHP
CY 2012	UMSA	391,350,000 PHP
CY 2013	UMSA	200,000,000 PHP
CY 2014	UMSA	600,000,000 PHP
CY 2015	LMSA	850,000,000 PHP
	PESA	
CY 2016	LMSA	850,000,000 PHP
CY 2017	LMSA	600,000,000 PHP
CY 2018	LMSA	300,000,000 PHP
Total (CY2011~2018)		3,991,350,000 PHP
Overall Cost (NIA Estimation/ NEDA approved cost)		5,444,850,000 PHP
Balance		1,453,500,000 PHP

Source: NIA PMO

5.8 Table 5.4 shows the project cost for the remaining civil works of the MMIP II project area, and the difference between the available remaining budget and the JICA Team's estimation for the both Case-1 and Case-2. The project cost of Case-1 estimated by JICA Team is smaller than that of the NIA's estimation while the cost of Case-2 is more than the available remaining budget. It means that NIA can complete the Case-1 components while NIA cannot undertake Case-2 works unless otherwise there should another additional budget arrangement.

Table 5.4 Estimated Project Cost for Remaining Civil Works in MMIP II Project Area

Basis of Estimation	Project Cost *1 (million PHP)	Ratio	Difference	Remarks	
Remaining Budget	1,453.50	100.00%	-	Balance of Allotment Budget (see Table 5.4.3)	
JICA Team's Estimation	Case-1	896.07 (-557.43) *2	61.65%	-	NIA Portion (Irrigation & Drainage Facilities) only *3
		1,237.78 (-215.72)	85.16%	+341.70 (23.51%)	+ Road and Bridge
		1,350.08 (-103.42)	92.88%	+112.30 (7.73%)	+ Agriculture Component
	Case-2	1,527.61 (74.11)	105.10%	-	NIA Portion (Irrigation & Drainage Facilities) only (without Flood Protection Works *3)
		1,882.94 (429.44)	129.55%	+355.33 (24.45%)	NIA Portion (Irrigation & Drainage Facilities) only (including Flood Protection Works *4)
		2,321.04 (867.54)	159.69%	+438.10 (30.14%)	+ Road and Bridge
		2,433.35 (979.85)	167.41%	+112.30 (7.73%)	+ Agriculture Component

*1: Including "Other Related Works" and "Indirect Works (Land Acquisition, VAT, Physical Contingency and Price Escalation)"

*2: shows difference between the cost and the remaining budget.

*3: "Flood Protection Works" are not considered in Case-1

*4: Flood Protection Works: Canal Slope Protection, Concrete Flume Introduction, Sluice Gates Introduction along the Pulangi River etc.

5.9 As afore-mentioned, remaining budget is estimated at 1,453.50 million PHP, and as a matter of fact this budget can cover the required cost of Case-1 only. Also, from the view point of maintenance of the irrigation facilities in the LMSA, Case-1 is much easier than that of Case-2 since the canal network of Case-1 is to be installed within the area less or minimally affected by flooding. Therefore, JICA team recommends NIA central office to go with Case-1 and complete the MMIP II as soon as possible with the remaining available budget. Therefore, should NIA want to complete all the LMSA as originally designed, JICA team recommend to go with step-wise development; first Case-1 investment and then Case-2 investment.

5.10 NIA MMIP II PMO is in charge of the on-going construction works of MMIP II. PMO is

directly under Engineering and Operation Sector of the central office. Though the PMO structure is basically similar to that of central office, it is simplified as there are only 2 divisions under the Project Manager; Administrative and Finance Division and Engineering Division. The MMIP II PMO is located in Midsayap, opposite side of the Region XII Office, and there are as of May 30, 2017, 192 staff in total composed of 22 monthly co-terminous, 74 casual employment and 96 service/ job contracts.

5.11 In implementing the remaining works of MMIP II, there should be an institutional arrangement, which should of course be established based on the existing on-going organizational set up. To complete the remaining works of MMIP II, setting up of Steering Committee (SC) at the NIA central level, comprising of concerned divisions of NIA and ATI central office, and coordination mechanism with the PMO should be established. This SC/PMO arrangement is proposed basically with reference to that of the on-going MMIP II. The major difference from the on-going arrangement is the inclusion of ATI at the central level since ATI is to be engaged in agriculture and extension development activities to be conducted within the MMIP area.

6. PROJECT EVALUATION

6.1 The MMIP II Service Areas, total 10,536 ha, is composed of Upper Malitubog Service Area (UMSA) and Lower Malitubog Service Area (LMSA). The originally requested ODA target area was the most eastern part of LMSA (2,133ha). Then, the initial target area of this economic analysis was to cover only the eastern part of LMSA since the economic analysis aimed to evaluate the economic validity of the ODA project area requested. However, NIA decided to withdraw the MMIP II project from its proposal to be funded by Japan ODA financing. Therefore, the economic analysis as an ODA project is no longer necessary. Alternatively, the economic analysis should be done on costs and benefits generated from NIA's on-going and planned project. In this respect, the Target Area should be LMSA or the MMIP II Service Area overall.

6.2 In rainy season, parts of the Target Service Area are free from flooding. While other parts of the areas are probably affected by flood. Of them, the expected flooded areas of 0.5 to 1.0 m inundation are out of the target irrigable area in the rainy season. On the other hand, flooded areas of up to 0.5 m could still be considered as a part of target irrigable area, yet the production would be affected by floods. The losses due to this flooding are assumed based on four scenarios; 1) no damage scenario (0% loss in yield; notified as "D00"), 2) partially damaged scenario (30% loss; notified as "D30"), 3) half damaged scenario (50% loss; notified as "D50"), and 4) almost-totally damaged scenario (80% loss; notified as "D80").

6.3 As MMIP II project as a whole, the EIRR performs relatively good; 10.07% as of 30% reduction scenario in Case-1, and 10.73% as of 30% reduction scenario in Case-2. While, considering only the part of LMSA, this case is not economically viable; 6.57% even as of no reduction scenario in Case 1, and 8.19% as of no reduction scenario in Case-2, due to the large unit cost against beneficial area as compared to other areas than that of LMSA. If flooding damages of more than 50% take place in the production in flooded areas of up 0.5 m, the project is not economically viable. For example, 9.68% as of 50% reduction scenario in Case-1 and 9.07% as of 80% reduction case in Case-1 of MMIP II Areas. The result implies that economic efficiency is sensitive to hydrological situation of the sites.

6.4 If one compares "Case-1" and "Case-2", when other conditions are same, EIRRs in Case-2 are always a bit higher than those of Case1's. For example, the EIRRs are 10.07% as of 30% reduction scenario in Case-1 and 10.73% as of 30% scenario in Case-2 of MMIP II areas. These results may suggest that Case-2, in that irrigation canals are to be constructed as per the original design, could be

recommendable in term of economic efficiency; however, in this Case-2 much maintenance works should be expected and therefore, NIA should well be prepared for the routine experience maintenance (maintenance cost of Case-2 is estimated at 2 times that of Case-1).

6.5 On the viewpoint of feasibility analysis of NIA, it is better to evaluate MMIP II project overall (namely, "M2" cases). According to the results, the EIRR exceeds 10% of social discount ratio in this Country in both C1-M2-D30 and C2-M2-D30 cases that the Team considers as benchmark cases. Then, the conclusion of economic analysis is that the project is economically viable as MMIP II whole.

6.6 To analyze project impacts on individual farmer's viewpoints, farm budgetary analysis has been conducted. Upon the project implementation completed, two types of major benefits are to be accrued; 1) the yield increase owing to additional water supply and agriculture extension activities; and 2) the cultivation area increase after adequate irrigation water to be availed. Thanks to these benefits, the potential income increment upon the project implementation completed could be 70% to 89% from the present condition. Since poverty reduction is one of the central agenda of the area, the income improvement should contribute to the regional development as well as to the social unification in the area.

7. ENVIRONMENT AND INDIGENOUS PEOPLE

7.1 Components which need land acquisition are construction of main canal, lateral canals, drainages and access roads (intra-site road). NIA-PMO prioritizes irrigation canal construction, therefore, identification of Project Affected Persons (PAPs) and compensation for damage to crops and structures by canal construction is on-going. However, none of compensation for land loss due to the canal construction has been finished as of July 2018. The reason for this situation is as follows:

- ✓ An evaluation survey of land value was implemented in 2003 to estimate the compensation rates for irrigation facility construction, and it was revealed that actual land price varies from P11.3 - P12.5 per square meter, which is described in "ROW Committee Resolution No. 2003-01". However, determined compensation rates for land loss for paddy field and other crop field were P10.5 and P7.5 per square meter, respectively, which were much less than actual ones. Yet, the amounts are applied as the compensation rates even in 2018, which is not acceptable for the PAPs.
- ✓ Only one person in Upper Malitubog Area has agreed the rates and has been paid, which means that the construction works of canals in MMIP II have been started prior to the compensation payment for land loss. It is noted that any laws in Philippines do not stipulate payment timing of compensation, and such a condition may not be a big issue on the ground level, thus the PAPs are waiting for the compensation for land loss.

7.2 For the purpose of assessment of impacts on ecology in the Liguasan Marsh by the Project, fish survey and bird survey were implemented in and around the Marsh. Identified results are as follows:

- ✓ Ten fish species were identified by the spot-survey while two species were done by the interviews, in other words, 12 species in total were identified. It is unveiled that *Oreochromis niloticus* (Nile tilapia), *Channa striata* (Mudfish) and *Cyprinus carpio* (Common carp) are dominant, especially, the number of *Oreochromis niloticus* (Nile tilapia) is very big. Regarding *Anguilla* sp. (Eel), *Mesopristes* sp (Cross-Barred Grunter) and *Mesopristes* sp (Cross-Barred Grunter), only one was caught, respectively.
- ✓ With the Project which will not construct the dike, the conditions of Liguasan marsh will not be changed, given that inundated area of the Marsh is seasonally and annually changed drastically

even now. Under such severe condition, the fish have survived so far. The proposed construction works will not cause significant hydrological change, which leads to minor impact on the fish eco-system. However, there is a possibility that excessive fish catch and exotic fish introduction can lead to change of fish eco-system in the marsh, and balanced management is recommended.

- ✓ In total, 63 bird species were identified by the spot-survey, transect survey and interview to the people in July 2017. Out of identified species by the survey, *Haliastur indus* (Philippine duck) and *Anhinga melanogaster* (Oriental darter) are classified endangered species in the IUCN Red List. According to the people interviewed, Philippine duck is rarely observed recently, and they attribute the decline of the bird to hunting. The Project, construction of irrigation canal, drainage and access roads in LMSA is not expected to give a severe damage to habitat of those birds. Rather than the impacts by the Project, hunting of those bird species is probably a bigger issue to be managed, and it is requested to control such illegal activity regardless of the Project.

7.3 Some environmental impacts will be caused by the Project, for instance, air pollution, noise/vibration, traffic jam in construction stage. However, the extent of impacts is not very significant, since the proposed components will not cause dynamic change of hydrological conditions. In operation stage, as there is a possibility of conflict on water distribution, it is needed to promote even water distribution through IA initiative and cooperation with NIA.

7.4 According to results of a survey conducted by National Commission on Indigenous Peoples (NCIP), the population of Indigenous People (IPs) at the national level could be estimated at between 12 and 15 million, constituting almost 10 to 15% of the total population of the Country. The IPs are concentrated in Mindanao sharing as much as 61%. In Mindanao, it has been confirmed the presence of Muslim IPs and other IPs who are neither Muslim nor Christian (called Lumad), in addition to settlers who are mainly Christians and originally from outside Mindanao Island.

7.5 Upon contacted by the Survey Team at the end of May 2017, NCIP decided to take the Field-Based Investigation (FBI) process through its Regional Office in Region XII. The JICA Survey Team has provided technical and financial support through the FBI process. By overlaying the map of the target project site with the maps of two different Ancestral Domains (ADs) which are located nearby, it was revealed that the target project site remains away from the two ADs. Concurrently, the FBI team conducted the actual FBI process on the ground, and prepared the FBI report based on the findings.

7.6 The FBI report concluded that there are no Indigenous Cultural Communities/ Indigenous Peoples present in the area for which originally the ODA Loan was requested, and therefore, it is highly recommended that an irrigation system will be implemented in the area. The report was submitted to the NCIP Regional Director of the Region XII by the leader of the FBI team on July 5 of 2017. Thus, there is no need to prepare an Indigenous Peoples Plan (IPP) to do the construction works for the concerned area within LMSA.

8. GLOBAL ISSUES

8.1 The poverty ratios of Region XII and that of ARMM are very high, especially the ratio of ARMM/ Maguindanao is the highest in the Philippines; almost 3 times higher than that of whole nation, about 48% vs. 16.5% in 2015. There are components which can raise the income of the beneficiaries through the increase of production of agricultural produces; namely, 1) irrigation and drainage development, and 2) agriculture and extension development. For these components, increase of the farm budgets is estimated by comparing the before-after projects, showing approximately an increase of 70 - 89% in the farm budget; thus the Project will contribute to mitigating the poverty of

the beneficiaries.

8.2 On the climate change issues, the major component of MMIP II, the irrigation and drainage development, can cope with or at least mitigate such impact of climate change concerning anomalies of the rainfall pattern. The change of the monsoon season could be very much associated with intensive rainfall pattern, meaning the rain tends to fall at once with severer intensity, often resulting in torrential rain and flood, as has been already observed. The component of irrigation and drainage construction would work in mitigating this climate change, rainfall and monsoon season pattern change.

8.3 Men and women share works in farming, and there is a clear division of labors by gender. The criterion applied for the division of labor is the extent, to which physical power is required. On the other hand, food processing to add value to their agricultural produce is done only by women. This criterion is common among farmer households in the Project area, irrespective of their religion. All the major decisions on farming activities are made only by men. Such division of labor by gender and concentration of decision-making power only in men should be considered in the operation and maintenance of the irrigation facilities through the formation and operation of IAs. For example, more female members in the IA board should be included as from the current only 6% to say 30%.

9. CONCLUSION AND RECOMMENDATIONS

This Survey was initiated by a request for ODA loan financing as of January 2017 on the remaining (untouched) areas of MMIP II. However, with recognition not feasible technically and financially to construct protection and ring dykes protecting the Lower Malitubog Service Area (LMSA) from the floods of Pulangi river, NIA as well as the Government of Philippines have decided to withdraw the request and instead push through the MMIP II project on its own government budget. With this decision, the JICA Team summarizes the survey results, as conclusion, given of the following:

- 1) The flood protection and ring dykes originally designed by NIA-PMO should NOT be constructed from the view point that;
 - 1.1) As the foundation, on which protection and ring dykes are planned to be constructed, is expected to be very soft, the NIA designed ring dyke having around 7 m height would require consolidation settlement, probably reaching as much as 1.5 m and, in the worst case, would cause potential circular sliding through the foundation if no foundation treatment were to be done. Even if foundation treatment were to be done, such treatment would entail huge construction cost, say approximately 4 billion PHP, which apparently indicates economic non-viability.
 - 1.2) In addition to above, dikes, if constructed, would give on the Liguasan March such impacts of; 1) enlarging the inundation area by 19% - 34%, and 2) raising water level by 65 – 81 cm depending on the return-period (2, 10, 20, 30, 50 and 100 years) according to the flood simulation. This would cause resettlements of the houses on the left bank of the Pulangi river, or at least should provide a means of raising the floor of the houses. The dikes, if constructed, would thus cause social and environmental issues to the existing natural conditions and also on the people's life and livelihood.
 - 1.3) Further in addition, rain falling on the LMSA would cause inland ponding, inundating as much as 50% (80%) of the LMSA during rainy season under 2 (30) - year return period. With 30 nos of drainage sluice gates, each H2m x B2m, at a cost of 2.4 billion Php, the inundation would be released in November, enabling the dry season paddy cultivation under 2-year return period (50 gates under 30 years return period), yet large portions of the

LMSA, say 50 – 80%, would anyway have to give up the rainy season's cultivation. If drainage pumps were to be installed, even the rainy season paddy could be cultivated; however it would need an additional cost of 4.2 billion Php under 10 years return period, not economically feasible.

- 1.4) If dredging were to be tried on the Pulangi river in order to enlarge the flow capacity of the river, namely, mitigating the flood to the LMSA, a scale of 500m expansion of the river almost all along the target sections (94 km) would enable the LMSA almost free from the flooding. However, this measure would require 345 million CUM removal at a huge cost of 22 billion Php for the direct cost only. Besides, partial dredging for only the bottleneck area (13km reach), at which the width of Pulangi river becomes very narrow located at about 6-7 km downstream from the most western part of LMSA, was examined; however, it was revealed that even 500m expansion could have limited effects such as 198 ha, 206 ha, and 339 ha increases of beneficial area under 100-year, 30-year and 2-year return periods, respectively, with huge investments of 3.8 billion Php, 1.5 billion Php and 0.76 billion Php.
- 2) Without flood protection and ring dykes, there should be two options in terms of developing the canal network of the LMSA as to; 1) Case-1 limiting the canal network within the beneficial area less/least affected by inundation (2,810 ha for rainy season and 3,688 ha during dry season), or 2) Case-2 constructing the canal network as per the NIA-PMO original design (original 6,590 ha cultivable during dry season while only 3,810 ha cultivable for rainy season). This Survey recommends the first option (Case-1) with the following reasons:
 - 2.1) In the case of constructing all the canal network in LMSA as per the NIA-PMO original design (Case-2), there should be at least some flood protection works, e.g. canal slope protection, concrete flume introduction, etc., applied to strengthen the mid-terminal points of the canal network flooded every year. This flood protection works would require an additional direct cost of 269.65 million Php at least, which unfortunately would go beyond the originally NEDA approved budget. Further, maintenance cost for the Case-2 will be much higher than that of Case-1, approximately twice higher maintenance cost per unit area than that of Case-1.
 - 2.2) In fact, EIRR showed higher return in the Case-2 than Case-1 as 11.87% vs. 10.90%, 10.73% vs. 10.07%, 10.18% vs. 9.68%, 9.32% vs. 9.07% respectively in the cases of NIL damage for wet season paddy, 30% damage, 50% damage and 80% damage for the whole MMIP II area. These EIRRs are however not much different each other, and thus the JICA Team would recommend the canal network development of Case-1 for which the canals are to be constructed mostly within the less/least flooded area and thus maintenance works would be much easier than that of Case-2. It is also indicated by comparing the maintenance costs of Case-2 and Case-1; the former unit cost per ha being almost double than that of the latter, again indicating easier maintenance works in terms of financial arrangement for the Case-1.
- 3) Though the JICA team recommends the Case-1 as afore-mentioned, should NIA want to develop all the LMSA with the Case-2 investment, JICA team would recommend a step-wise development, in that anyway NIA should complete MMIP II as early as possible with the Case-1 investment which is manageable within the available remaining budget, and then in future proceed to the Case-2 investment given additional budget.
- 4) Some of the facilities of MMIP I had been constructed already more than 20 years, requiring certain level of rehabilitation/ repair though lack of budgets has been hindering such rehabilitation works. Especially, gates installed on the headworks are out of order as of 2017,

risking the structural stability during high flood season. NIA should prepare for enough budget to carry out necessary rehabilitation and/or improvement works, which may be named as MMIP III. This MMIP III investment may be combined with Case-2 investment.

- 5) Concerning environmental consideration, land acquisition is necessary for the Project implementation, however, as discussed in Chapter 7, almost all of the Project Affected Persons (PAPs) have not accepted the proposed compensation rates for the land loss due to their low amounts, which were fixed in 2003 and being applied even at this moment. As a result, the construction works were started and are on-going without payment of compensation for the land loss. It is recommended to negotiate with the PAPs to fix acceptable compensation rates and to finalize the payment.

MAIN REPORT

CONTENTS

LOCATION MAP OF THE SURVEY AREA

CONTENTS

LIST OF TABLES

LIST OF FIGURES

CHAPTER 1	RATIONALE AND GOAL OF THE PROJECT.....	1-1
1.1	Rationale of the Survey.....	1-1
1.2	Purpose of and Outputs from the Survey.....	1-2
1.3	Contents of the Official Request and Scope of the Works.....	1-2
1.4	Schedule of the Survey.....	1-4
1.5	The Survey Area.....	1-5
1.6	Implementation Arrangement of the Survey.....	1-6
CHAPTER 2	THE PROJECT AREA.....	2-1
2.1	Salient Features of the Project Area.....	2-1
2.1.1	Spatial Settings and Contextual Positioning.....	2-1
2.1.2	History of MMIP Development.....	2-2
2.1.3	Area, Population and Beneficiaries of MMIPII.....	2-4
2.1.4	Meteorology: Temperature and Rainfall.....	2-5
2.1.5	Hydrology and Future Irrigation Water Availability.....	2-7
2.1.6	Regional and Barangay (Household) Economies.....	2-8
2.1.7	Social and Cultural Features.....	2-19
2.1.8	Access to Public Services and Local Governance.....	2-21
2.2	Liguasan Marsh and Indigenous People.....	2-25
2.2.1	Location and Size of the Marsh.....	2-25
2.2.2	Ecology of the Marsh.....	2-27
2.2.3	People Living on the Marsh.....	2-28
2.3	Agriculture and Extension in the Project Area.....	2-30
2.3.1	Agricultural Land Use and Soils.....	2-30
2.3.2	Agricultural Land Use by Satellite Image Analysis.....	2-32
2.3.3	Cropping Pattern and Production.....	2-37
2.3.4	Agricultural Mechanization.....	2-47
2.3.5	Agricultural Extension Service to Farmers.....	2-48
2.4	Irrigation System in MMIP.....	2-57
2.4.1	Irrigable Area of MMIP.....	2-57
2.4.2	Irrigable System of MMIP.....	2-58
2.4.3	Area Irrigated by Year and by Crop (MMIP I: MRIS).....	2-65
2.4.4	Operation and Maintenance.....	2-66
2.4.5	Irrigators Association and IMT.....	2-67
2.5	Distribution Infrastructure; Road and Bridges.....	2-70
2.5.1	Roads in and around the Project Area (Pikit Municipality).....	2-70
2.5.2	Bridges in and around the Project Area (Pikit Municipality).....	2-71
2.6	Related Projects and Programs.....	2-72
2.6.1	National Irrigation Sector Rehabilitation and Improvement Plan (NISRIP).....	2-72

2.6.2	Participatory Irrigation Development Project (PIDP).....	2-73
2.6.3	Southern Philippines Irrigation Sector Project.....	2-73
2.6.4	JICA Technical Cooperation Project.....	2-74
2.6.5	Other On-going Project in Neighboring Area of MMIP II.....	2-74

CHAPTER 3 DELINEATION OF LMSA WITH FLOOD PROTECTION MEASURES 3-1

3.1	Past Flood Occurrence and Its Magnitude on LMSA.....	3-1
3.1.1	Basin Area Covering the Project Area	3-1
3.1.2	Channel Change in the Pulangi River	3-1
3.1.3	Long Term Water Occurrence Change	3-2
3.1.4	Seasonal Change	3-3
3.1.5	Maximum Flood Water Extent and Inundation Ratio of LMSA.....	3-3
3.1.6	Elevation Corresponding to the Maximum Flood Area	3-4
3.1.7	Past Design Flood Water Level.....	3-6
3.2	Flood Protection Measures	3-8
3.2.1	Flood Protection Dike	3-8
3.2.2	Dredging of the Pulangi River	3-16
3.3	Preliminary Examination on Flood and its Mitigation Measures	3-17
3.3.1	Examination Cases.....	3-17
3.3.2	Flood Simulation by Simplified Storage Model	3-18
3.3.3	Inland Inundation Simulation by Simple Rainfall-Evaporation Model	3-25
3.3.4	Dredging Simulation by the Uniform Flow Calculation.....	3-30
3.4	Numerical Model for the Computer Simulations.....	3-31
3.4.1	Simulation Cases.....	3-31
3.4.2	General Conditions of the Simulation.....	3-32
3.4.3	Model Design.....	3-41
3.4.4	Simulation Theory.....	3-46
3.5	Flood Simulation with/without Dike	3-47
3.5.1	Specific Conditions for Flood Simulation with/without Dike	3-47
3.5.2	Simulation Result-1 (Inundation Area)	3-48
3.5.3	Simulation Result-2 (Flood Water Level)	3-50
3.6	Inland Inundation Simulation with/without Drainage Structures	3-64
3.6.1	Specific Conditions for Inland Inundation Simulation with/without Drainage Structures.....	3-65
3.6.2	Simulation Result.....	3-68
3.6.3	Required Number of the Sluice.....	3-76
3.7	Flood Simulation with/without Dredging	3-76
3.7.1	Specific Conditions for Flood Simulation with/without Dredging	3-76
3.7.2	Simulation Result.....	3-78
3.8	Flood Simulation with/without Partial Dredging.....	3-80
3.8.1	Specific Conditions for Flood Simulation with/without Partial Dredging.....	3-80
3.8.2	Simulation Result.....	3-80
3.8.3	Preliminary Economic Evaluation	3-85
3.9	Flood Simulation with the Ambal-Simuay River and Rio Grande de Mindanao Flood Control Projects	3-86
3.9.1	Specific Conditions for Flood Simulation with the Ambal-Simuay River and Rio	

Grande de Mindanao Flood Control Projects.....	3-88
3.9.2 Simulation Result.....	3-88
3.10 Conclusion of the Simulations.....	3-89
CHAPTER 4 PROJECT PLANNING AND DESIGNING	4-1
4.1 Direction Settings and Major Project Components.....	4-1
4.1.1 Lessons learnt and Impacts from MMIP I.....	4-1
4.1.2 Project Implementation Schedule	4-6
4.1.3 MMIP II Delineation and Components.....	4-7
4.2 Agriculture and Extension Development.....	4-10
4.2.1 Agriculture Development Strategy of the Philippine Development Plan 2017-2022	4-10
4.2.2 Agriculture Planning in the Project.....	4-10
4.2.3 Agriculture Support Plan	4-15
4.2.4 Future Recommendation for Agriculture Development in the MMIP Area.....	4-25
4.3 Irrigation and Drainage Improvement.....	4-27
4.3.1 Irrigation Water Reliability	4-27
4.3.2 Development Direction for Lower Malitubog Service Area in MMIP II.....	4-30
4.3.3 Irrigation Development Component	4-34
4.3.4 Drainage Component	4-36
4.3.5 Countermeasure for the Damage of Irrigation Canal Caused by Flood.....	4-38
4.3.6 Construction Cost of Irrigation System and Drainage System in LMSA	4-38
4.3.7 Operation and Maintenance of Irrigation Systems.....	4-40
4.3.8 IMT and Irrigators Association Establishment.....	4-42
4.3.9 Future's Plan/Project after MMIP II.....	4-47
4.4 Distribution Infrastructure Improvement and Upgrading	4-50
4.4.1 Construction Area and Expected Influence of Canal Maintenance Road	4-50
4.4.2 NIA's Design Policy of Canal Maintenance Road	4-51
4.4.3 Network of Access Road (Intra-site Road) and Land Acquisition	4-54
4.4.4 Principle of Design for Access Road (Intra-site Road).....	4-55
4.4.5 Arrangement Plan of Bridge along Access Road.....	4-57
CHAPTER 5 PROJECT COST AND IMPLEMENTATION ARRANGEMENT	5-1
5.1 Project Components Selected and Implementing Departments	5-1
5.2 Implementation Modality by Component.....	5-2
5.3 Implementation Schedule.....	5-3
5.3.1 Seasonal Implementation Schedule.....	5-3
5.3.2 Overall Implementation Schedule by Component	5-4
5.4 Cost Estimation and Disbursement.....	5-6
5.4.1 Basis of Cost Estimation	5-6
5.4.2 Cost Estimation.....	5-7
5.4.3 Step-wise Implementation.....	5-10
5.5 Institutional Setup for Project Implementation.....	5-11
5.5.1 Agencies Concerned and Implementation Capacities at the Central Level	5-11
5.5.2 Agencies at the Regional and Field Level.....	5-13
5.5.3 NIA MMIP II Project Management Office (PMO).....	5-14

5.5.4	Implementation Arrangement for the Remaining MMIP II	5-15
CHAPTER 6	PROJECT EVALUATION	6-1
6.1	Conditions, Methodology and Evaluation Cases	6-1
6.1.1	Basic Condition and Assumptions	6-1
6.1.2	Cases for Project Evaluation	6-1
6.2	Economic Term of Project Cost and Benefit.....	6-3
6.2.1	Economic Term of Project Cost	6-3
6.2.2	Economic Term of Project Benefit.....	6-4
6.3	Result of Economic Analysis	6-6
6.3.1	Calculation of EIRR, NPV and B/C	6-6
6.4	Farm Budget Analysis.....	6-7
6.5	Proposed Indicators for Project Operation and Effects.....	6-9
CHAPTER 7	ENVIRONMENTAL AND INDIGENOUS PEOPLE CONSIDERATION.....	7-1
7.1	Project Components	7-1
7.2	Legislative and Institutional Framework of Environmental Consideration	7-1
7.2.1	Legislative and Institutional System for Environmental Impact Assessment	7-1
7.2.2	Environmental Standards	7-5
7.2.3	Legal Framework of Land Acquisition	7-7
7.2.4	JICA Policy for Involuntary Resettlement and Land Acquisition.....	7-8
7.2.5	Gap Analysis	7-9
7.3	General Conditions in and around the Target Area.....	7-12
7.3.1	Metrological Conditions	7-12
7.3.2	Positional Relation between the Target Area, Surrounding Rivers and Liguasan Marsh.....	7-12
7.3.3	Mindanao River Basin and Pulangi River Basin.....	7-14
7.3.4	Protected Areas around the Target Area	7-15
7.3.5	Main Income of MMIP Area.....	7-16
7.3.6	Farming in the MMIP II Area	7-17
7.4	Scoping	7-20
7.5	Result of Environmental Examination.....	7-24
7.5.1	Ecological Survey	7-24
7.5.2	Water Quality Test.....	7-30
7.6	Environmental Evaluation	7-31
7.7	Mitigation Measures and Cost	7-38
7.8	Monitoring Plan	7-40
7.9	Stakeholder Meeting	7-43
7.10	Resettlement and Land Acquisition	7-43
7.10.1	Construction Progress	7-43
7.10.2	Land Acquisition.....	7-44
	Column: Progress of Compensation in LMSA	7-46
7.11	Indigenous People Consideration	7-48
7.11.1	JICA's Safeguard Policy on Indigenous Peoples.....	7-48
7.11.2	Scope of the Survey on Indigenous Peoples	7-49
7.11.3	Related Legal Instruments and Government Structure of the Philippines	7-50

7.11.4	Screening of the Presence of IPs and ADs to be affected	7-51
7.11.5	Results of the Field Based Investigation.....	7-53
7.12	Recommendation	7-54
CHAPTER 8	GLOBAL ISSUES.....	8-1
8.1	Poverty Reduction.....	8-1
8.2	Climate Change.....	8-2
8.2.1	Climate Change Review and Future Simulation	8-2
8.2.2	Project Intervention in the Climate Change	8-6
8.3	Gender.....	8-7
8.3.1	Current Gender Conditions in the Philippines	8-7
8.3.2	Gender Mainstreaming in the Proposed Components.....	8-10
CHAPTER 9	CONCLUSION AND RECOMMENDATIONS	9-1
 APPENDIXES		
I.	IMPLEMENTATION ARRANGEMENT	I-1
II.	METEOROLOGY AND HYDROLOGY	II-1
III.	AGRICULTURE	III-1
IV.	IRRIGATION AND DRAINAGE	IV-1
V.	ROAD AND BRIDGE.....	V-1
VI.	FLOOD SIMULATION.....	VI-1
VII.	ENVIRONMENT	VII-1
XIII.	INDIGENOUS PEOPLE AND OTHER SOCIAL ISSUES.....	VIII-1
IX.	COST ESTIMATION	IX-1
X.	PROJECT EVALUATION	X-1
XI.	SATELLITE IMAGE ANALYSIS	XII-1
XII.	CATCHUP PLAN FOR HELP FOR CATUBIG AGRICULTURAL ADVANCEMENT PROJECT(HCCAP)	XIII-1
XIII.	TOR AND PERSON-MONTH FOR LOAN CONSULTANT	XIII-1

ACRONYMS AND ABBREVIATIONS

AERR	ASEAN Emergency Rice Reserve
AFP	Armed Forces of the Philippines
AFTA	ASEAN Free Trade Area
ARMM	Autonomous Region in Muslim Mindanao
ARMMIARC	ARMM Integrated Agriculture Research Center
ATI	Agriculture Training Institute
BDA	Bangsagmoro Development Authority
CFSR	Climate Forecast System Reanalysis
DA	Department of Agriculture
DAR	Department of Agrarian Reform
DBM	Department of Budget and Management
DENR	Department of Environment and Natural Resources
DepED	Department of Education
DOF	Department of Finance
DOH	Department of Health
DPWH	Department of Public Works and Highways
DSWD	Department of Social Welfare and Development
EO	Executive Order
FAO	Food and Agriculture Organization of the United Nations
FAOSTAT	Food and Agriculture Organization of the United Nations Statistics
FDI	Foreign Direct Investment
GDP	Gross Domestic Product
GEM Program	Growth with Equity in Mindanao Program
GOP	Government of the Republic of the Philippines
IA	Irrigators' Association
ICC	Investment Coordination Committee
IMT	Irrigation Management Transfer
IRA	Internal Revenue Allotment
ISF	Irrigation Service Fee
J-BIRD	Japan-Bangsamoro Initiatives for Reconstruction and Development
LGPMs	Local Governance Performance Management System
LGSP	Local Government Support Program
LGU	Local Government Unit
LMC	Left Main Canal
LMSA	Lower Malitubog Service Area
MAG	Monitoring Advisory Group
MAG-	MMIP Monitoring and Advisory Group for the MMIP
MAO	Municipal Agricultural Officer
MDC	Main Drainage Canal
MDF	Municipal Development Fund
MDFO	Municipal Development Fund Office
MEDCo	Mindanao Economic Development Council
MILF	Moro Islamic Liberation Front
MMIP	Malitubog-Maridagao Irrigation Project

MOA	Memorandum of Agreement
MOU	Memorandum of Understanding
MPDC	Municipal Planning and Development Coordinator
MRDP	Mindanao Rural Development Project
MRIS	Maridagao River Irrigation System
MTPDP	Medium Term Philippine Development Plan
MWG	Mindanao Working Group
NCEP	National Centers for Environmental Prediction, National Weather Service, US
NCIP	National Commission on Indigenous Peoples
NEDA	National Economic Development Authority
NIA	National Irrigation Administration
NIS	National Irrigation System
NPA	New People's Army
NSCB	National Statistical Coordination Board
NWRB	National Water Resources Board
OPAPP	Office of the Presidential Adviser on the Peace Process
PAGASA	Philippine Atmospheric, Geophysical and Astronomical Services Administration
PAO	Provincial Agricultural Officer
PDAP	Philippine Development Assistance Program
PEIS	Philippine Environment Impact Statement
PESA	Pagalungan Extension Service Area
PhilRice	Philippine Rice Research Center
PMC	Project Monitoring Committee
PMO	Project Management Office
PSC	Project Steering Committee
PPDC	Provincial Planning and Development Coordinator
PSA	Philippine Statistics Authority
RMC	Right Main Canal
ROW	Right-of-Way
SEC	Security and Exchange Commission
SEED MalMar	Special Economic Enhancement and Development for MMIP
SEED PIKIT	Special Economic Enhancement and Development for Pikit
STARCM	Support to Agrarian Reform Communities in Central Mindanao
SZOPAD	Special Zone of Peace and Development
TSAG	Turnout Service Area Group
TWG	Technical Working Group
UMSA	Upper Malitubog Service Area
WRFT	Water Resources Facilities Technologist
YLTA	Yen Loan Technical Assistance

UNIT CONVERSION

1 lb (pound)	0.453 592 kg
1 kilogram	2.205 pounds
1 ton (long ton)	2240 pounds
1 metric ton	1000 kilograms
	2204.623 pounds
1 pond	0.4536 kg
1 kg	2.2046 ponds
1 Gallon	4.5461 litre
1 Litre	0.2200 Gallon
1 inch (in.)	2.54 cm
1 feet (ft.)	30.5 cm
1 meter	3.279 feet
1 kilometer	0.621 mile
1 mile	1.601 kilometers
1 acre (ac)	0.40468 ha
1 hectare (ha)	2.471 ac
1 ac-ft	1233.4 cum
1 square kilometer	0.386 sq.mile

CURRENCY EQUIVALENTS (AS AT JUNE 2018)

1 US\$	=	108.81 Japanese Yen (TTB)
1 PHP	=	2.07 Yen (TTS)
1 US\$	=	52.57 PHP

PHILIPPINES' FINANCIAL YEAR

January 1 to December 31

LIST OF TABLES

Table 1.3.1	Project Area for MMIP II (as of January 26, 2017).....	1-2
Table 1.3.2	Proposed Project Cost Breakdown (as of January 26, 2017).....	1-3
Table 1.3.3	Potential Scopes of MMIP II for ODA Loan Financing.....	1-4
Table 1.4.1	Overall Survey Schedule.....	1-5
Table 2.1.1	Actual Expenditure for the MMIP I.....	2-3
Table 2.1.2	Summary of the Irrigation Service Area.....	2-4
Table 2.1.3	Summary of the Irrigation Beneficiaries Farmer Households (FHHs).....	2-5
Table 2.1.4	Climate Stations (by Satellite Image Analysis).....	2-5
Table 2.1.5	Climate Stations and Command Area.....	2-7
Table 2.1.6	Demographic Statistics of the Relevant Provinces and Municipalities.....	2-9
Table 2.1.7	Gross Domestic Product by Industrial Origin, 2016 at Current Price.....	2-10
Table 2.1.8	Distribution of Household by Income Class and by Region, 2015.....	2-11
Table 2.1.9	Poverty Incidence (Province/ Municipality).....	2-11
Table 2.1.10	Employed Persons by Region and Major Industry Group, 2014.....	2-12
Table 2.1.11	Employed Persons by Region and Class of Worker, 2014.....	2-13
Table 2.1.12	Name of Barangays and the Number of Sample Famer Households (FHHs).....	2-14
Table 2.1.13	Cultivated Area of Lowland per FHHs by Crop and by Irrigation Access.....	2-16
Table 2.1.14	Sample Size Segmented by TA Recipient and Non-Recipient.....	2-19
Table 2.1.15	IP in Cotabato & Maguindanao P.....	2-20
Table 2.1.14	Comparison of the Access to Safe Water and Sanitary Toilet in Region XII and ARMM.....	2-23
Table 2.2.1	Endangered Species in Liguasan Marsh.....	2-27
Table 2.2.2	Overview of the Municipalities and City in the Liguasan Marsh.....	2-28
Table 2.3.1	Crop Production in Pikit Municipality (Average between 2014 and 2016).....	2-30
Table 2.3.2	Soil Types in 5 Municipalities in the Project Area.....	2-31
Table 2.3.3	Wavelength and Spatial Resolution of LANDSAT8/OLI and SENTINEL-2A/MSI.....	2-32
Table 2.3.4	Agricultural Land Use Area in Each Irrigation Service Area by Satellite Image Analysis (ha).....	2-34
Table 2.3.5	Crops and Cropping Pattern in 5 Municipalities in the Project Area.....	2-37
Table 2.3.6	Productivity (ton/ha) of Rice and Corn from Relevant Statistical Data.....	2-39
Table 2.3.7	Crop Intensity and Estimated Crop Production in LMSA.....	2-40
Table 2.3.8	Average Farm Size of Paddy Farm Parcels in 2013 (Unit: ha).....	2-40
Table 2.3.9	Percentage Distribution of Paddy Farm Parcels by Tenure Status in 2013 (Unit: %).....	2-41
Table 2.3.10	Percentage of Paddy Farm Parcels Irrigated in 2013 (Unit: %).....	2-41
Table 2.3.11	Percentage of Farmers Owned & Used Drawing Animals & Farm Machinery (Unit: %).....	2-41
Table 2.3.12	Percentage of Paddy Farmers by Type of Work Power Used in Land Preparation in 2013 (Unit: %).....	2-41
Table 2.3.13	Planting Methods, %.....	2-41
Table 2.3.14	Percentage Distribution of Paddy Farmers by Ecosystem, by Type of Seed Planted in 2013, Unit %.....	2-42
Table 2.3.15	Quantity of Paddy Seeds(Unit: kg/ha).....	2-42
Table 2.3.16	Average Quantity of Chemical Fertilizers Applied for Paddy in 2013.....	2-43

Table 2.3.17	Percentage of Paddy Farmers by Method of Fertilizer Application in 2013 (Unit: %)	2-43
Table 2.3.18	Average Farm Size of Corn Farm Parcels in 2013, ha.....	2-44
Table 2.3.19	Average Area Planted and Harvested of Corn Farm Parcels in 2013, ha.....	2-44
Table 2.3.20	Percentage Distribution of Corn Farm Parcels by Tenure Status in 2013, %	2-45
Table 2.3.21	Percentage of Farmers Owned & Used Drawing Animals & Farm Machinery in Corn Farm, %	2-45
Table 2.3.22	Percentage of Corn Farmers by Type of Work Power Used in Land Preparation in 2013, %	2-45
Table 2.3.23	Percentage Distribution of Corn Farmers by Corn Type by Type of Seed in 2013, %	2-45
Table 2.3.24	Percentage of Corn Farmers by Source/s of Modern and Native OPV Seeds in 2013, %	2-46
Table 2.3.25	Seed Ratio of Corn, kg/ha.....	2-46
Table 2.3.26	Average Quantity of Chemical Fertilizers Applied for Corn in 2013, Kg/ha	2-46
Table 2.3.27	Percentage of Corn Farmers by Method of Fertilizer Application in 2013, %	2-46
Table 2.3.28	Agricultural Mechanization by Crops in the Philippines.....	2-47
Table 2.3.29	Percentage of Rice & Corn Farmers Owned & Used Farm Machinery in 2013 (unit: %).....	2-47
Table 2.3.30	Percentage of Rice & Corn Farmers Used Farm Machinery in 2013 (unit: %).....	2-47
Table 2.3.31	Percentage of Farmers Own Farm Machinery Identified at the Baseline Survey (unit: %).....	2-48
Table 2.3.32	Annual Budget of ATI from 2014-2017 (unit: 1000 Pesos).....	2-49
Table 2.3.33	Number of Staff of ATI Regional Training Centre (XII)	2-50
Table 2.3.34	Annual Budget of ATI Regional Training Centre (XII).....	2-50
Table 2.3.35	Staff in Office of Municipal Agriculturist (in Cotabato Province) and Allocated DAF Staffs to Municipality (in ARMM) as of 2017.....	2-51
Table 2.3.36	Target IAs of YLTA	2-53
Table 2.3.37	Number of Participants/Beneficiaries of YLTA.....	2-54
Table 2.3.38	Paddy Yield Comparison with-YLTA and without-YLTA	2-54
Table 2.3.39	Annual Budget of Additional Program Funded by GOP	2-55
Table 2.3.40	Number of Beneficial IAs and Farmers of YLTA and Additional Program Funded by GOP as of June 2018.....	2-55
Table 2.4.1	Irrigable Areas of MMIP I and MMIP II	2-58
Table 2.4.2	Specifications of the Diversion Dam.....	2-59
Table 2.4.3	Length of Main canal & Lateral Canal and Number of Turnout in MMIP.....	2-60
Table 2.4.4	Drainage Canal in MSA.....	2-61
Table 2.4.5	Drainage Canal in UMSA.....	2-62
Table 2.4.6	Drainage Canals in LMSA.....	2-62
Table 2.4.7	Drainage Canal in PESA	2-62
Table 2.4.8	Service Areas of MMIP II (by Service Area & Municipalities)	2-63
Table 2.4.9	Progress in Generation of Irrigable Area in MMIP II (as of April 2017)	2-63
Table 2.4.10	Project Components of MMIP II	2-63
Table 2.4.11	Progress in the Implementation of MMIP II.....	2-64
Table 2.4.12	Progress in Civil Works (Contract works and Direct Force Account) of MMIP II..	2-64
Table 2.4.13	Current Condition of the Service Area in MRIS.....	2-65

Table 2.4.14	Actual Irrigated Area in Maridagao Service Area (MRIS)	2-66
Table 2.4.15	Staffing Structure of the MRIS Management Office	2-66
Table 2.4.16	Approved Budget, Income and Expenditure of MRIS Management Office.....	2-67
Table 2.4.17	Transition of IAs in MRIS	2-68
Table 2.4.18	Irrigators Association in MRIS	2-68
Table 2.4.19	Irrigators Association established under MMIP II	2-69
Table 2.5.1	Criteria of Road Classification in the Philippines	2-70
Table 2.5.2	Status of Road Infrastructure in Pikit Municipality	2-71
Table 2.5.3	Status of Bridges in Pikit Municipality, as of 2018	2-71
Table 2.6.1	Major Donor-Assisted Projects by NIA.....	2-72
Table 3.1.1	Water Area on LMSA in Normal Year (probability: 50%) and Maximum Water Extent	3-4
Table 3.1.2	Estimation of Past Maximum Inundation Elevation with DEM Data	3-5
Table 3.1.3	Flood Water Records and Design Flood Water by 1992 Detail Design.....	3-6
Table 3.1.4	Design Flood Water Level by NIA-PMO	3-7
Table 3.1.5	Design Flood Water Levels by Studies	3-8
Table 3.2.1	Flood Protection Dike Construction Options.....	3-9
Table 3.2.2	Consolidation Parameters	3-10
Table 3.2.3	Estimated Years to Settle for the Dike Foundation.....	3-12
Table 3.2.4	Summary of Foundation works (Foundation Treatment Methods).....	3-12
Table 3.2.5	Comparison of Foundation Works (Foundation Treatment Methods)	3-13
Table 3.2.6	Land Acquisition for Dike Construction.....	3-16
Table 3.3.1	Examination Case of the Preliminary Examination.....	3-18
Table 3.3.2	Conditions of the Simulation	3-18
Table 3.3.3	Probable 4-Day Rainfall (Mean Rainfall within the Catchment Area) by Return Period.....	3-19
Table 3.3.4	Conditions for Rational Formula	3-19
Table 3.3.5	Peak Flood Discharge by Return Period.....	3-20
Table 3.3.6	Water Surface and Volume with/without Dike	3-21
Table 3.3.7	Maximum Flood Water Level with and without Dike	3-22
Table 3.3.8	Maximum Inundation Area with and without Dike (only Left Side of the Pulangi River).....	3-22
Table 3.3.9	Probable Annual Rainfall at Datu Piang Observation Station and Selected Years ...	3-26
Table 3.3.10	Inundation Magnitude Caused by Rainfall less Evaporation.....	3-27
Table 3.3.11	Scope of Drainage Pumping Stations including Preliminary Cost	3-29
Table 3.3.12	Conditions of the Calculation	3-30
Table 3.4.1	Simulation Cases for Detail Hydraulic Simulations	3-32
Table 3.4.2	Roughness Coefficients by Land Uses	3-34
Table 3.4.3	Information of the Rainfall Gauge Stations.....	3-35
Table 3.4.4	Data Availability of each Rainfall Gauge Station (○: 365-day data available)	3-36
Table 3.4.5	Maximum 4-day Basin Mean Rainfall Amount in MRB.....	3-37
Table 3.4.6	Maximum 4-day Basin Mean Rainfall Amount in MRB.....	3-37
Table 3.4.7	Pan-Evaporation Stations in the Mindanao Island.....	3-40
Table 3.4.8	Runoff Coefficient by Land Use Category	3-41
Table 3.4.9	Model Extent	3-41
Table 3.4.10	Flood velocity by Kraven Formula.....	3-44

Table 3.4.11	Sub-basin Parameters.....	3-45
Table 3.5.1	Simulation Cases for With/Without Dike	3-47
Table 3.5.2	Maximum Inundation area in the Liguasan Marsh.....	3-48
Table 3.5.3	Maximum Flood Water Level at "Marsh 2" Point	3-50
Table 3.5.4	Maximum Water Level at "Paidu Pulangi" Point	3-50
Table 3.5.5	Maximum Flood Water Level at "Bottleneck Point-2"	3-64
Table 3.5.6	Construction Cost (Direct Cost) of the Dike (Height is 50cm Higher than the Current Design)	3-64
Table 3.6.1	Annual Basin Mean Rainfall Amount in the MRB.....	3-65
Table 3.6.2	Annual Rainfall Amount at Datu Piang Rainfall Gauge Station.....	3-66
Table 3.6.3	Simulation Cases for Inland Inundation Simulation.....	3-68
Table 3.6.4	Summary of the Results (Return Period: 2 year)	3-69
Table 3.6.5	Summary of the Results (Return Period: 10 year).....	3-69
Table 3.6.6	Summary of the Results (Return Period: 20 year)	3-69
Table 3.6.7	Summary of the Results (Return Period: 30 year).....	3-69
Table 3.6.8	Summary of the Results (Return Period: 50 year).....	3-69
Table 3.6.9	Summary of the Results (Return Period: 100 year).....	3-69
Table 3.6.10	Construction Cost (Direct Cost) of the 30 Sluices.....	3-76
Table 3.7.1	Simulation Cases of Flood Simulation with/without Dredging.....	3-78
Table 3.7.2	Dredging Amount and Maximum Water Level on the Pulangi River after Dredging	3-78
Table 3.7.3	Construction Cost (Direct Cost) of the Dredging	3-79
Table 3.8.1	Simulation Cases of Flood Simulation with/without Partial Dredging	3-80
Table 3.8.2	Simulation Results (Maximum Water Level at Paidu Pulangi), Unit: EL. m.....	3-81
Table 3.8.3	Simulation Results (Average Water Depth in LMSA).....	3-83
Table 3.8.4	Planted Area to be Increased by Partial Dredging	3-85
Table 3.8.5	Expected Planted Area Increased by Partial Dredging	3-85
Table 3.8.6	Construction Cost (Direct Cost) of the Dredging	3-86
Table 3.9.1	Simulation Results (Average Water Depth in LMSA).....	3-89
Table 4.1.1	Cropped Area in the Dry and Rainy Seasons (2016).....	4-2
Table 4.1.2	Progress of Procured Packages in 2015 and 2016	4-4
Table 4.1.3	Yield of Paddy before MMIP I and After MMIP I.....	4-5
Table 4.1.4	Differences in Net Profit of Rain-fed Paddy, Corn and Irrigated Paddy	4-7
Table 4.1.5	Implementation Schedule	4-7
Table 4.2.1	Strategic Framework of Agricultural Development of the Philippine Development Plan 2017-2022.....	4-10
Table 4.2.2	Productivity (ton/ha) of Rice and Corn from Relevant Statistical Data	4-12
Table 4.2.3	Annual Planted Area and Production of Rice and Corn in the LMSA	4-13
Table 4.2.4	Annual Planted Area and Production of Rice and Corn in the whole MMIP 2 Area	4-13
Table 4.2.5	Characteristics of Planted and Recommended Rice Varieties by PhilRice in the MMIP Area	4-14
Table 4.2.6	Main Components of YLTA and Their Activities	4-16
Table 4.2.7	YLTA Implementation Process	4-16
Table 4.2.8	Number of IAs in the MMIP Area as of June 2018	4-17
Table 4.2.9	Implementation Schedule of YLTA Phase II.....	4-18
Table 4.2.10	Necessary Inputs of Technical Assistance for Irrigated Rice Production	4-18

Table 4.2.11	Implementation Schedule of Enhancement of Agriculture Ex. Services at Municipality Level.....	4-20
Table 4.2.12	Equipment to be Installed to the Five Municipal Offices	4-20
Table 4.2.13	No. of Motorcycles to be provided to the Five Municipal Offices	4-20
Table 4.2.14	Training Topics for the Agriculture Staff at Municipality Level	4-21
Table 4.2.15	Amount of Rice Seed Produced by Seed Growers in 2017 in Selected Municipalities of Cotabato Province	4-22
Table 4.2.16	Number and Area of Accredited Seed Growers in the MMIP Area and Nearby Municipalities	4-22
Table 4.2.17	Implementation Schedule of Development of Seed Production in MMIP	4-23
Table 4.2.18	Necessary Inputs for Development of Seed Production	4-24
Table 4.2.19	Necessary Items for Seed Inspections by BPI-NSQCS	4-24
Table 4.2.20	Inventory of Agriculture Machines in the MMIP area.....	4-26
Table 4.2.21	Capacity of Agriculture Machines and Estimated Progress (%) of Agricultural Mechanization	4-26
Table 4.3.1	Return Periods of Maridagao River Runoff at the Diversion Point.....	4-27
Table 4.3.2	Cropping Pattern and Irrigation Water Requirement Computation	4-29
Table 4.3.3	Proposed Repair or Rehabilitation of Irrigation/ Drainage Systems	4-30
Table 4.3.4	Flooded Status of Irrigable Areas	4-33
Table 4.3.5	Target Service Area to be Developed and Irrigable Area in Dry & Rainy Season ...	4-33
Table 4.3.7	List of Drainage Canals and Excavation Volume in LMSA	4-37
Table 4.3.8	Comparison of Direct Cost on Civil Works for Irrigation Development in LMSA..	4-39
Table 4.3.9	Proposed Staffing Plan of the Maridagao River Irrigation System (MRIS) Management Office	4-40
Table 4.3.10	Existing Maintenance Machinery which MRIS Office Owns	4-41
Table 4.3.11	MRIS Office's Request of Additional Maintenance Machinery.....	4-41
Table 4.3.12	Irrigators Association and Turnout Service Area Group.....	4-44
Table 4.3.13	Proposed Repair or Rehabilitation of Irrigation/ Drainage Systems	4-48
Table 4.3.14	Proposed Improvement of Irrigation/ Drainage System Constructed under MMIP II	4-49
Table 4.3.15	Procurement Plan of Maintenance Machinery.....	4-49
Table 4.4.1	Canal Maintenance Road and Density.....	4-50
Table 4.4.2	Public Roads Available within Pikit Municipality Area	4-50
Table 4.4.3	Recommended Thickness of Gravel Pavement	4-51
Table 4.4.4	Soil Classification in relation to Road Design.....	4-51
Table 4.4.5	Width of Canal Maintenance Roads	4-52
Table 4.4.6	Access Road to be Constructed within Upper Malitubog Service Area	4-54
Table 4.4.7	Minimum Design Standards for Farm-to-Market Road (Access Road)	4-56
Table 4.4.8	List of Bridge along Access Road (Construction Plan of Case-1).....	4-58
Table 4.4.9	List of Bridge along Access Road (Construction Plan of Case-2).....	4-59
Table 5.1.1	Project Components by Implementing Agencies.....	5-1
Table 5.2.1	Project Components and Implementation Modality	5-3
Table 5.3.1	Seasonal Implementation Schedule	5-4
Table 5.3.2	Implementation Schedule by Component/ Sub-component (MMIP II).....	5-5
Table 5.4.1	Disbursement of the Project Cost, Unit Million JPY.....	5-7
Table 5.4.2	Disbursement of the Project (Case-1 & Case-2).....	5-8

Table 5.4.3	MMIP II Project Cost (NIA Estimation).....	5-8
Table 5.4.4	Estimated Project Cost for Remaining Civil Works in MMIP II Project Area	5-9
Table 5.4.5	Summary of the Project Cost of MMIP III Project.....	5-10
Table 5.4.6	Preliminary Plan of Step-wise Implementation towards Case-2 and MMIP III	5-11
Table 5.5.1	NIA Headquarters Staffing as at May 31, 2017	5-12
Table 5.5.2	NIA's Financial Statement by Project and Program	5-13
Table 5.5.3	NIA's Financial Statement by Project and Program	5-14
Table 6.1.1	Applied Conversion Factors	6-1
Table 6.1.2	Cases for Project Evaluation.....	6-1
Table 6.1.3	Evaluation Cases Only for LMSA Area.....	6-2
Table 6.1.4	Evaluation Cases for all MMIP II Area	6-3
Table 6.2.1	Financial and Economic Cost (Case 1; LMSA), Million Peso	6-3
Table 6.2.2	Financial and Economic Cost (Case 2; LMSA), Million Peso	6-4
Table 6.2.3	Financial and Economic Cost (Case 1; MMIP II), Million Peso	6-4
Table 6.2.4	Financial and Economic Cost (Case 2; MMIP II), Million Peso	6-4
Table 6.2.5	Applied Target Yields of Extension by Year.....	6-5
Table 6.2.6	Cost and Return Calculation for Rain-fed Crops.....	6-5
Table 6.2.7	Cost and Return Calculation for Irrigated Paddy.....	6-6
Table 6.2.8	Percentages Indicating Benefit Generation Process by Year (LMSA)	6-6
Table 6.2.9	Percentages Indicating Benefit Generation Process by Year (MMIP2).....	6-6
Table 6.3.1	Summary of Annual Net Benefit, EIRR, NPV, and B/C.....	6-7
Table 6.4.1	Farm Budget Analysis by the Evaluation Case.....	6-8
Table 6.5.1	Proposed Operation and Effect Indicator (Case-1, LMSA).....	6-9
Table 6.5.2	Proposed Operation and Effect Indicator (Case-2, LMSA).....	6-9
Table 6.5.3	Proposed Operation and Effect Indicator (Case-1, MMIP)	6-10
Table 6.5.4	Proposed Operation and Effect Indicator (Case-2, MMIP2)	6-10
Table 7.2.1	Categories of Project Requiring Environmental Examination.....	7-3
Table 7.2.2	Required Documents, Procedures and Decision Making Organization by Category .	7-3
Table 7.2.3	National Ambient Air Quality Guideline for Criteria Pollutants	7-5
Table 7.2.4	Water Quality Criteria for Conventional and Other Pollutants Contributing to Aesthetics and Oxygen Demand for Fresh Waters	7-6
Table 7.2.5	Permissible Noise Standard	7-7
Table 7.2.6	Gap Analysis between Laws in Philippines and the JICA Guidelines.....	7-10
Table 7.3.1	Target Villages of Socio-Economic Survey and No. of Interviewed Households	7-17
Table 7.3.2	Crop Production in Pikit Municipality (Ave. 2014-16)	7-18
Table 7.4.1	Scoping Result	7-20
Table 7.4.2	Terms of Reference for Environmental Examination	7-23
Table 7.5.1	Identified Fish Species.....	7-27
Table 7.5.2	Identified Fish Species in 1998 & 2017 and Impacts of Introduced Species	7-27
Table 7.5.3	Endangered Bird Species Identified by the Survey	7-30
Table 7.5.4	Water Quality Check Result	7-30
Table 7.6.1	Environmental Evaluation	7-35
Table 7.7.1(1)	Mitigation Measures to/against the Negative Impacts: Before Construction/Construction Stage	7-38
Table 7.7.1(2)	Mitigation Measures to/against the Negative Impacts: Operation Stage.....	7-39
Table 7.8.1	Recommended Monitoring Plan.....	7-40

Table 7.9.1	Date and Target Barangay of Stakeholder Meeting	7-43
Table 7.10.1	Land Acquisition Area in LMSA	7-44
Table 7.10.2	Land Acquisition Area for Main and Lateral Canals in LMSA	7-44
Table 7.10.3	Land Acquisition Area for Main and Lateral Drains in LMSA	7-45
Table 7.10.4	Possible Land Acquisition Area for Access Roads in LMSA	7-46
Table 7.11.1	Outlines of Indigenous Peoples Plan (IPP).....	7-48
Table 7.11.2	Legal Instruments on Indigenous People’s Rights of the Philippines.....	7-50
Table 8.1.1	Poverty Ration by Region in Philippines (1991 – 2015)	8-1
Table 8.1.2	Estimated Farm Budget comparing the Before-After Projects	8-2
Table 8.2.1	Seasonal Temperature Increases in 2020 and 2050 under Medium-range Emission Scenario	8-5
Table 8.2.2	Seasonal Rainfall Change in 2020 and 2050 under Medium-range Emission Scenario	8-5
Table 8.2.3	Frequency of Extreme Events in 2020 and 2050 under Medium-range Emission Scenario	8-6
Table 8.3.1	Distribution of Government Doctors, Dentists, Nurses and Midwives per Region, 2008-8	8-8
Table 8.3.2	Normal Type of Deliveries by Place.....	8-8
Table 8.3.3	Livebirths attended by Medical Doctors, Public Health Nurses and Midwives	8-9
Table 8.3.4	Livebirths attended by Traditional Birth Attendants and Others	8-9
Table 8.3.5	Gender Development Index 2009 for Cotabato and Maguindanao Provinces.....	8-9
Table 8.3.6	Distribution of Roles by Gender in Farming Activities	8-10
Table 8.3.7	Female Ratio in IAs of MMIP	8-11

LIST OF FIGURES

Figure 1.5.1	MMIP Service Area and the Major Survey Area	1-5
Figure 1.6.1	Working Structure for the Preparatory Survey	1-6
Figure 2.1.1	Project Map of MMIP I and MMIP II.....	2-1
Figure 2.1.2	Project Site and Marsh Affected Area.....	2-2
Figure 2.1.3	Project Area by Commencement Year	2-4
Figure 2.1.4	Climate Station Location	2-5
Figure 2.1.5	Monthly Temperature Trend (Pikit Area)	2-6
Figure 2.1.6	Monthly Rainfall Trend (Pikit Area).....	2-6
Figure 2.1.7	Long Term Trend for Annual Rainfall (Pikit).....	2-6
Figure 2.1.8	Long Term Trend for Dry Season Rainfall (Pikit)	2-6
Figure 2.1.9	Monthly Rainfall Trend (Catchment Area).....	2-7
Figure 2.1.10	Long Term Trend of Annual Rainfall (CA)	2-7
Figure 2.1.11	Long Term Trend of Dry Season Rainfall (CA)	2-7
Figure 2.1.12	Annual Runoff at the Diversion Dam Point (1,380 sq.km catchment area)	2-8
Figure 2.1.13	Dry Season Runoff at the Diversion Dam Point (1,380 sq.km catchment area).....	2-8
Figure 2.1.14	Projected Population by Five-Calendar Year	2-9
Figure 2.1.15	Annual Growth Rates by Five Calendar-Year	2-9
Figure 2.1.16	Percentage of Agricultural Production in GRDP, 2001-2015 at current price.....	2-10
Figure 2.1.17	Poverty Estimates 2006 – 2015	2-11
Figure 2.1.18	Location Map of Selected Barangays for Baseline Survey	2-14
Figure 2.1.19	Population of Target Barangays by Sex.....	2-15

Figure 2.1.20	Population Share of Target Barangays by Selected Religion	2-15
Figure 2.1.21	Composition of Primary Ethnic Group.....	2-15
Figure 2.1.22	Composition of Employment in the Target Barangays.....	2-15
Figure 2.1.23	Histogram of Farmer HH Segmented by Farmland Size	2-16
Figure 2.1.24	Shares of Farmer Household Income by Income.....	2-16
Figure 2.1.25	Recognized Issues on Farming & % of Farmers (Unit: %)	2-17
Figure 2.1.26	Evaluation of MMIP I Project & % of Farmers (Unit: %).....	2-17
Figure 2.1.27	Expectation of MMIP II Project and Percentage of Farmers (Unit: %).....	2-17
Figure 2.1.28	Income Comparison between Male and Female Headed HHs	2-18
Figure 2.1.29	Income Comparison between TA Recipient and Non-Recipient	2-18
Figure 2.1.30	Ethnic proportion of the population of Mindanao	2-19
Figure 2.1.31	Positive Impact of MMIP I Confirmed at the Ex-post Evaluation	2-22
Figure 2.1.32	Degree of Beneficiaries' Satisfaction at the Ex-post Evaluation	2-22
Figure 2.1.33	Improved HD Indices of Cotabato and Maguindanao Provinces	2-22
Figure 2.1.34	Government Structure: Differences between ARMM and Other Regional Offices..	2-23
Figure 2.1.35	Budget of ARMM b/t 2010 and 2014 (Unit: PHP).....	2-23
Figure 2.1.36	2014 Budget allocated to ARMM (Unit: PHP).....	2-24
Figure 2.1.37	Inequality among Different Groups in Literacy Rate	2-24
Figure 2.1.38	Inequality among Different Groups in Access to Safe Water & Sanitary Toilet.....	2-24
Figure 2.2.1	Marsh area in Mindanao Basin	2-25
Figure 2.2.2	Diversion Channel and the Project Area.....	2-26
Figure 2.2.3	Location and Size of Liguasan Marsh (as max. extent of water cover).....	2-26
Figure 2.2.4	Income Source for Buliok and Talitay Barangays	2-29
Figure 2.3.1	Pikit Municipality and MMIP Area	2-30
Figure 2.3.2	Share of Harvested Area	2-31
Figure 2.3.3	Assumed Cropping Pattern and Example of NDVI and NDWI Changes	2-33
Figure 2.3.4	Basic Flowchart for Identifying Each Cropped Area.....	2-34
Figure 2.3.5	Agricultural Land Use of MSA in 2016.....	2-35
Figure 2.3.6	Agricultural Land Use of UMSA under MMIP I in 2016.....	2-36
Figure 2.3.7	Agricultural Land Use of UMSA under MMIP II in 2016	2-36
Figure 2.3.8	Agricultural Land Use of LMSA under MMIP II in 2015/2016.....	2-37
Figure 2.3.9	Agricultural Land Use of Pagalungan Ext. Service Area in 2015/2016	2-37
Figure 2.3.10	Cropping Calendar in the Project Area.....	2-39
Figure 2.3.11	ATI Organizational Structure.....	2-49
Figure 2.3.12	Organization of ATI Regional Training Centre (XII)	2-49
Figure 2.3.13	Agricultural Extension Setup in Cotabato Province	2-50
Figure 2.3.14	Agricultural Extension Setup in Maguindanao Province	2-51
Figure 2.3.15	Farmers' Observations on Agriculture Extension Services in the MMIP Area.....	2-52
Figure 2.3.16	Implementation Setup of YLTA.....	2-53
Figure 2.4.1	Project Map of MMIP I and MMIP II.....	2-57
Figure 2.4.2	Land Use of Maridagao Service Area in Dec. 2006	2-58
Figure 2.4.3	Irrigation Canal Network in MMIP	2-60
Figure 2.4.4	Location of the IAs in UMSA (Ph.2).....	2-69
Figure 2.5.1	MMIP Area and National Road Network	2-70
Figure 3.1.1	Watershed Area for the Project Area.....	3-1
Figure 3.1.2	River Channel Change in the Pulangi River (1/2)	3-1

Figure 3.1.2	River Channel Change in the Pulangi River (2/2)	3-2
Figure 3.1.3	Long Term Water Occurrence Change (1984-2014).....	3-2
Figure 3.1.4	Seasonality of Water Surface (1984-2014)	3-3
Figure 3.1.5	Flood Area and Recurrence of Annual Behavior of Water Surface (1984-2014)	3-3
Figure 3.1.6	Overlaid Maximum Inundation line with the Topo Map	3-4
Figure 3.1.7	DEM and Max. Water Extent.....	3-5
Figure 3.1.8	Flood Observation Stations (1987)	3-6
Figure 3.1.9	Flood Records at 4 Stations (1987).....	3-6
Figure 3.2.1	Dike Construction Options	3-8
Figure 3.2.2	Dike Heights by Option	3-9
Figure 3.2.3	Typical Cross Section of Ring Dike	3-10
Figure 3.2.4	An Example of the Sand Compaction Pile Method	3-13
Figure 3.2.5	An Example of the Sand Drain Method.....	3-13
Figure 3.2.6	Image of Flood Situation under Present Condition and After Construction of the Dike.....	3-14
Figure 3.2.7	Image of Inundation Situation within LMSA	3-14
Figure 3.2.8	Examples of the Constructed Dike	3-15
Figure 3.2.9	Topographic Map (1/4,000) showing Houses Near the Pulangi river.....	3-15
Figure 3.2.10	Target Area for Dredging.....	3-16
Figure 3.2.11	Image of the Dredging Formation	3-17
Figure 3.3.1	Location of the Bottle Neck Point	3-18
Figure 3.3.2	Rainfall Distribution	3-19
Figure 3.3.3	Triangle-shape Hydrograph	3-20
Figure 3.3.4	Cross Section and H (Elevation) - Qout Relation at the Bottle Neck Point.....	3-20
Figure 3.3.5	H-A and H-V Relation of the Catchment Area at the Bottle Neck Point.....	3-21
Figure 3.3.6	Results of the Flood Simulation by Simplified Storage Model (1/3)	3-22
Figure 3.3.6	Results of the Flood Simulation by Simplified Storage Model (2/3)	3-23
Figure 3.3.6	Results of the Flood Simulation by Simplified Storage Model (3/3)	3-24
Figure 3.3.7	Location of the Rainfall Gauge Station and Evaporation Stations	3-25
Figure 3.3.8	Evaporation at the MIT Station	3-26
Figure 3.3.9	Topographic Condition of the LMSA.....	3-26
Figure 3.3.10	Topographic Condition, H-V Relation Curve and H-A Relation Curve of the LMSA	3-26
Figure 3.3.11	Results of Inland Inundation Simulation by Simple Rainfall-Evaporation Model (1/2).....	3-27
Figure 3.3.11	Results of Inland Inundation Simulation by Simple Rainfall-Evaporation Model (2/2).....	3-28
Figure 3.3.12	A Preliminary Example of Drainage Pump Stations and Typical Cross Section.....	3-29
Figure 3.3.13	Design Cross Section Formation	3-30
Figure 3.3.14	Dredging Plan: Total 163.57 km Length.....	3-31
Figure 3.4.1	Elevation Distribution within the MRB.....	3-32
Figure 3.4.2	River Alignments and Basin Boundaries	3-32
Figure 3.4.3	River Alignments and Basin Boundaries (focusing on the area from LMSA to the River Mouths).....	3-33
Figure 3.4.4	River Network Diagram in the Mindanao River Basin (MRB).....	3-33
Figure 3.4.5	Land Use Map	3-34

Figure 3.4.6	Rainfall Gauge Stations	3-35
Figure 3.4.7	Area Division Patterns for Thiessen Method (1/2)	3-38
Figure 3.4.7	Area Division Patterns for Thiessen Method (2/2)	3-39
Figure 3.4.8	Location of the Pan-Evaporation Stations	3-40
Figure 3.4.9	Monthly and Daily Evaporation at MIT Station	3-40
Figure 3.4.10	Model Area Selected in the Simulation	3-41
Figure 3.4.11	Bathymetric Survey Area.....	3-41
Figure 3.4.12	Discharge Input Points in the Simulation Model.....	3-42
Figure 3.4.13	Calculation Procedure of 4-Day Hourly Rainfall Distribution.....	3-43
Figure 3.4.14	Unit Hydro Graph for the Mindanao River Basin (MRB).....	3-43
Figure 3.4.15	Image of the Superposition Method by each Unit Hydrograph.....	3-44
Figure 3.4.16	Image of Time Series Discharge at an Input Point	3-44
Figure 3.5.1	Image of Flood Condition With/Without Dike	3-47
Figure 3.5.2	Area of the Liguasan Marsh	3-48
Figure 3.5.3	Simulation Results (Maximum Inundation Area) (1/2)	3-48
Figure 3.5.3	Simulation Results (Maximum Inundation Area) (2/2)	3-49
Figure 3.5.4	Location of "Marsh 2" Point.....	3-50
Figure 3.5.5	Location of "Paidu Pulangi" Point.....	3-50
Figure 3.5.6	Comparison of the Flood Path between with/without the Dike.....	3-51
Figure 3.5.7	Flood Water Level and River Discharge (Present Condition) (Return Period: 2 year)	3-52
Figure 3.5.8	Flood Water Level and River Discharge (Present Condition) (Return Period: 10 year)	3-53
Figure 3.5.9	Flood Water Level and River Discharge (Present Condition) (Return Period: 20 year)	3-54
Figure 3.5.10	Flood Water Level and River Discharge (Present Condition) (Return Period: 30 year)	3-55
Figure 3.5.11	Flood Water Level and River Discharge (Present Condition) (Return Period: 50 year)	3-56
Figure 3.5.12	Flood Water Level and River Discharge (Present Condition) (Return Period: 100 year)	3-57
Figure 3.5.13	Flood Water Level and River Discharge (After Construction of the Dike) (Return Period: 2 year)	3-58
Figure 3.5.14	Flood Water Level and River Discharge (After Construction of the Dike) (Return Period: 10 year)	3-59
Figure 3.5.15	Flood Water Level and River Discharge (After Construction of the Dike) (Return Period: 20 year)	3-60
Figure 3.5.16	Flood Water Level and River Discharge (After Construction of the Dike) (Return Period: 30 year)	3-61
Figure 3.5.17	Flood Water Level and River Discharge (After Construction of the Dike) (Return Period: 50 year)	3-62
Figure 3.5.18	Flood Water Level and River Discharge (After Construction of the Dike) (Return Period: 100 year)	3-63
Figure 3.6.1	Image of Inland Flood Caused by Rainfall.....	3-64
Figure 3.6.2	Example of the Method to Create Time Series Mean Rainfall in the MRB (30-year return period).....	3-66

Figure 3.6.3	Example of the Method to Create Time Series Rainfall at Datu Piang (30-year return period).....	3-66
Figure 3.6.4	Schematic Image of the Time Series Discharge Data.....	3-67
Figure 3.6.5	Location of Drainage Point and Drainage Canal.....	3-68
Figure 3.6.6	Water Level and Inundation Situation (Return Period: 2 year).....	3-70
Figure 3.6.7	Water Level and Inundation Situation (Return Period: 10 year).....	3-71
Figure 3.6.8	Water Level and Inundation Situation (Return Period: 20 year).....	3-72
Figure 3.6.9	Water Level and Inundation Situation (Return Period: 30 year).....	3-73
Figure 3.6.10	Water Level and Inundation Situation (Return Period: 50 year).....	3-74
Figure 3.6.11	Water Level and Inundation Situation (Return Period: 100 year).....	3-75
Figure 3.6.12	Planned Cropping Pattern in LMSA (paddy).....	3-76
Figure 3.7.1	Dredging Sections and the Target Cross Sections.....	3-77
Figure 3.7.2	Example of the Cross Section before and after Dredging.....	3-77
Figure 3.7.3	Longitudinal Profile of the Maximum Flood Water Level.....	3-78
Figure 3.7.4	Change of the Discharge Volume by Dredging.....	3-79
Figure 3.8.1	Target Sections for Dredging.....	3-80
Figure 3.8.2	Longitudinal Profile of the Maximum Flood Water Level of the Pulangi River.....	3-82
Figure 3.8.3	Simulation Results (Maximum Inundation Area).....	3-84
Figure 3.8.4	H-A Relation Curve in LMSA.....	3-85
Figure 3.9.1	General Plan of the Ambal-Simuay River and Rio Grande de Mindanao Flood Control Projects.....	3-87
Figure 3.9.2	Results of Flood Simulation under Present Condition and after Implementation of the DPWH's Project.....	3-87
Figure 3.9.3	Longitudinal Profile of the Maximum Flood Water Level of the Pulangi River.....	3-88
Figure 4.1.1	Land Use Map of the dry season in 2016, made with satellite images.....	4-1
Figure 4.1.2	Typical On-farm Ditch Arrangement.....	4-3
Figure 4.1.3	Typical Cross Section of Main Farm Ditch (Left) and Typical Supplementary Farm Ditch (Right).....	4-3
Figure 4.1.4	Conceptual Irrigation Development of Case 1 and Case 2.....	4-8
Figure 4.2.1	Conceptual Cropping Pattern in the Project Area before and after the Project.....	4-11
Figure 4.3.1	Runoff at Diversion Point for Average and 80% Reliability.....	4-28
Figure 4.3.2	Average, 80% Probability and Effective Rainfalls (Pikit).....	4-28
Figure 4.3.3	Diversion Requirement and 80% Reliable Runoff.....	4-29
Figure 4.3.4	Inundated Area in LMSA during the Rainy Seasons.....	4-30
Figure 4.3.5	Locations of the Remaining Project Components to be Constructed after 2019.....	4-31
Figure 4.3.6	Flooded Area Affected based on the Vulnerability Assessment conducted in 2010.....	4-32
Figure 4.3.7	Estimated losses on Paddy Production by Inundation.....	4-33
Figure 4.3.8	Growing Stage of Rice.....	4-33
Figure 4.3.9	Plan of Irrigation Canal System for LMSA.....	4-34
Figure 4.3.10	Typical Cross section of Canal and Elements of Main Canal MC-2.....	4-36
Figure 4.3.11	Plan of Drainage Canal System for LMSA.....	4-37
Figure 4.3.12	Countermeasure Method for the Damage of Irrigation Canal by Flood.....	4-38
Figure 4.3.13	Image of Irrigation Management Transfer.....	4-44
Figure 4.3.14	Organizational Structure of WUA for Distributary Canal.....	4-45
Figure 4.4.1	Typical cross Section of Canal Maintenance Roads.....	4-53
Figure 4.4.2	Planned Access Road within LMSA.....	4-54

Figure 4.4.3	Typical Cross Section of Farm to Market Road (Access Road)	4-56
Figure 4.4.4	Annex “1” of DPWH Department Order (No.40 in 2014)	4-57
Figure 4.4.5	Annex “2” of DPWH Department Order (No.40 in 2014)	4-57
Figure 4.4.6	Location Map of Access roads and Bridges (Construction Plan of Case-1).....	4-59
Figure 4.4.7	Location Map of Access roads and Bridges (Construction Plan of Case-2).....	4-60
Figure 5.5.1	NIA Organizational Structure	5-11
Figure 5.5.2	NIA’s Project and Program Budgets	5-13
Figure 5.5.3	Organizational Structure of MMIP II PMO	5-15
Figure 5.5.4	Project Implementation Arrangement.....	5-16
Figure 6.3.1	Comparison of EIRR by Evaluation Case	6-7
Figure 7.1.1	Location of MMIP II Area	7-1
Figure 7.2.1	Organization Chart of DENR	7-2
Figure 7.2.2	Process of EIA Document Approval.....	7-4
Figure 7.3.1	Monthly Temperature Trend (Pikit Area)	7-12
Figure 7.3.2	Monthly Rainfall Trend (Pikit Area).....	7-12
Figure 7.3.3	Three-Dimension Map of Liguasan Marsh and ODA Area (Vegetation Distribution)	7-13
Figure 7.3.4	Location Map of Liguasan Marsh and MMIP Area.....	7-13
Figure 7.3.5	Land Use of Lower Malitubog Area in Rainy and Dry Seasons.....	7-14
Figure 7.3.6	Main Rivers in Pulangi River Basin	7-14
Figure 7.3.7	Sub-basins in Mindanao River.....	7-15
Figure 7.3.8	Location of Protected Areas around the Target Area	7-16
Figure 7.3.9	Location of Target Communities of Socio-economic Survey.....	7-16
Figure 7.3.10	Income Sources in LMSA and MMIP I Area.....	7-17
Figure 7.3.11	Annual Income in LMSA and MMIP I Area	7-17
Figure 7.3.12	Land Use in Lower Malitubog Area	7-18
Figure 7.3.13	Amount of Applied Fertilizers for Paddy	7-19
Figure 7.3.14	Amount of Applied Liquid Pesticide for Corn.....	7-19
Figure 7.5.1	Fish Survey Points	7-25
Figure 7.5.2	Bird Survey Points and Transect Routes.....	7-26
Figure 7.5.3	Fish Population and Species by Spot.....	7-27
Figure 7.5.4	Water Sampling Points.....	7-30
Figure 7.10.1	Construction Progress of MMIP II	7-44
Figure 7.11.1	FBI Process & Preparation of IPP	7-52
Figure 7.11.2	Non-overlap among the Ancestral Domain, LAMP, CADT No. R12-CAR-0703-0009 and the Entire MMIP Site.....	7-54
Figure 8.1.1	Poverty Ratio by Region (2015)	8-1
Figure 8.1.2	Trend of Poverty Ratio by Region (1991-2015)	8-2
Figure 8.2.1	Trend of Annual Mean Temperature with Anomalies in the Philippines Based on 1971-2000 Normal Values	8-3
Figure 8.2.2	Decadal Changes in Intense Tropical Cyclone Occurrence in the Three Main Islands in the Philippines (1951-2000)	8-3
Figure 8.2.3	Projected Seasonal Temperature Increase.....	8-5
Figure 8.2.4	Projected Seasonal Rainfall Increase, %	8-5

CHAPTER 1 RATIONALE AND GOAL OF THE PROJECT

Submitted herewith is the Final Report prepared for the ‘Preparatory Survey on Malitubog Maridagao Irrigation Project Phase II (MMIP II)’. A survey team organized by JICA headquarters commenced a series of field surveys for the Preparatory Survey from the beginning of May 2017, and this report presents major findings of the project area, flood simulation results, identification of potential project components, feasibility study results for the Lower Malitubog Service Area (LMSA) including requested ODA loan target area, environmental and social issues including indigenous people’s issues, and conclusion and recommendations.

1.1 Rationale of the Survey

The government of the Republic of Philippines has been making efforts for poverty reduction through the implementation of the “Philippine Development Plan 2011-2016”. One of the plan’s objectives is to achieve economic “Inclusive Growth” by creating jobs including the poor. To this end, the plan aims at addressing governance, social security reform, peace building and security, and so on, and as strategy for the infrastructure development, the plan upholds irrigation development in rural areas. The plan prioritizes improvement of agricultural productivity as well as agricultural income, and as one of the measures to be taken to achieve these priorities, irrigation development is highly counted.

Following the Plan 2011-2016, National Economic and Development Authority (NEDA) Board officially approved the Philippine Development Plan 2017-2022 on February 20, 2017. In this Plan, growth is expected to be more inclusive, where overall poverty rate is targeted to decline from 21.6 percent to 14 percent, and poverty incidence in rural areas to decrease from 30 percent in 2015 to 20 percent in 2022. Thus, the Plan puts priority on the poverty reduction in rural areas, e.g. central Mindanao area where the MMIP II site is located.

The Plan 2017-2022 is founded on three main pillars of: 1) regaining of people’s trust, 2) inequality-reducing transformation through increasing opportunities for growth, and 3) increasing of potential growth through sustaining and accelerating economic growth. Under the second pillar, opportunities in agriculture sector are expected to expand. Further, under the three pillars lie four cross-cutting strategies, i.e.: 1) attaining just and lasting peace, 2) ensuring security, public order and safety, 3) accelerating strategic infrastructure development and; 4) ensuring ecological integrity and a clean and healthy environment. In this regard, MMIP I, the foregoing project to MMIP II, is well known to have contributed to the peace and order in that area.

The National Irrigation Administration (NIA), which is the implementing agency of the proposed project, has its six-year plan for the period from 2012 to 2017. According to this plan, the rate of irrigation development in central Mindanao area was as low as 41.7% compared to the national average of 55.6% in the year 2015. In order to address such under-development in irrigation and the challenge of poor maintenance for the existing irrigation facilities, among other challenges, the plan aims at accelerating the development and rehabilitation of irrigation facilities as well as a partial transfer of the O&M responsibilities of National Irrigation Systems (NISs) from NIA to Irrigators Associations (IAs).

The project site for the MMIP II has not been yet socio-economically developed enough and the poverty rate in the area is still high. The agricultural production is low in spite of its potential being high, and thus improvement on irrigation facilities and agricultural productivity is an important development issue in the area. Based on these circumstances, it is expected that MMIP II will contribute to poverty reduction and long-lasting peace of this area. MMIP II could benefit the population of this area, who has been exhausted by a long-term conflict, by bringing about a comprehensive economic development and an improvement on basic living standards through the irrigation development, hence, the MMIP II should be implemented as early as possible, and

accordingly this Preparatory Survey is commenced.

1.2 Purpose of and Outputs from the Survey

The purpose of this Preparatory Survey is to formulate a sound project for its implementation of the MMIP II, towards which the Team is to review all the existing data or information and to carry out necessary studies and field surveys. The results of the studies and field surveys are to be utilized to plan and propose the implementation of MMIP II including possible funding from the Japanese ODA Loan, as requested by the government of the Republic of the Philippines (GOP).

As mentioned above, this Survey was initiated by a request for Japanese ODA loan funding to the LMSA, or to a part of the LMSA as MMIP II has been undergoing since year 2011. However, it is noted that flood simulation undertaken in this Survey revealed that dyke construction surrounding the LMSA for the purpose of protecting the area from flood coming from Pulangi river is not feasible (refer to Chapter 3 for detail). With this outcome in which dyke should not be constructed, NIA has recognized that the current NEDA approved budget could be enough to complete the remaining part of the MMIP II.

NIA issued letter to Department of Finance on May 22, 2018 stating that NIA would intend to withdraw its proposal for the funding of MMIP II through the Japan ODA financing as NIA believes that the remaining balance is too inconsequential for it to be funded by ODA loan. Following this NIA's action, government officials of the Philippines raised during a Japan-Philippines Economic Cooperation Infrastructure Joint Meeting held on June 21, 2018 that the GOP withdraws the ODA loan request for the MMIP II. With this withdrawal, this Survey places priority more on its feasibility and sound development plan formulation of the LMSA.

The outputs of the Survey are thus the recommendations of the project components, and investment scale of the MMIP II with feasibility evaluation, including measures against flooding. The Survey is therefore to investigate and analyze the different aspects of the project and consolidate the results in form of a project implementation plan taking into account the impact of Pulangi river flooding. Those aspects to be addressed by the Survey are: 1) methodologies and contents of the procurement and construction; 2) project costs; 3) organizational arrangement in executing the project; 4) institutional arrangements for operation, maintenance and management; 5) indicators to measure effect of the project operation; and 6) major issues to be examined for environmental and social considerations.

1.3 Contents of the Official Request and Scope of the Works

MMIP II is to undertake irrigation development as its major component. By tapping water through the headworks constructed at the Maridagao river during the MMIP I, it was planned to irrigate 10,541 ha of beneficiary farms, composed of 2,550 ha in Upper Malitubog Service Area (UMSA), 6,849 ha in LMSA, and 1,142 ha in Pagalungan Extension Service Area (PESA) once MMIP II is completed. Of them, the originally requested area for the possible ODA loan financing is located within the service area of Lower Malitubog; namely, only 3,581 ha was requested for the ODA loan financing out of the total LMSA of 6,849 ha (see Table 1.3.1):

Table 1.3.1 Project Area for MMIP II (as of January 26, 2017)

Site	Total Service Area (ha)	Area covered by Local Funds (ha)	Proposed Area for ODA Financing (ha)
Upper Malitubog Service Area	2,550	2,550	-
Lower Malitubog Service Area	6,849	3,268	3,581
Pagalungan Extension Service Area	1,142	1,142	-
Total MMIP II Area	10,541	6,960	3,581

Source: Explanatory Letter issued to Chief Representative of JICA Philippines by NIA Administrator (dated January 26, 2017)

Note: The Irrigated area indicated by the official request letter dated October 19, 2016 was 9,784 ha and it was increased in the NIA Letter issued on January 26, 2017.

According to an official letter issued to JICA Philippines Office from the NIA administrator on January 26, 2017, the total project cost for the MMIP II is estimated at PhP 5,445 million (equivalent to almost 12,197 million Yen). Out of the total cost, PhP 2,353 million (about 5,272 million Yen, with which 3,581 ha will be benefitted) is requested to invest by the possible ODA loan financing, while the balance PhP 3,092 million (about 6,925 million Yen, with which 6,960 ha will be benefitted) is to be invested by the government of the Republic of Philippines (see Table 1.3.1 and Table 1.3.2):

Table 1.3.2 Proposed Project Cost Breakdown (as of January 26, 2017)

Particulars	Total Project Cost (M PhP)	Cost proposed for ODA Financing (M PhP)	Cost proposed for ODA Financing (M Yen)
I. Direct Cost			
a. Civil Works			
1. Upper Malitubog Area	1,678.50		
2. Lower Malitubog Area	3,122.93	2,234.17	5,004.6
3. Pagalungan Ext. Area	294.63		
Sub Total (Direct, Civil)	5,096.06	2,234.17	5,004.6
b. Social Preparation	1.80		
c. Institutional Dev. Program	38.50	7.60	17.0
d. Procurement of Service Vehicle	7.00		
e. Right of Way Acquisition	135.74	57.87	129.6
f. Project Service Facilities	45.06	2.80	6.3
g. Detailed Engineering	20.03		
h. Parcellary Mapping Survey	15.83	5.80	13.0
i. Filed Support for Supervision & Monitoring	56.14	35.25	79.0
Sub Total (Direct, Others)	320.10	109.32	244.9
Sub Total (Direct)	5,416.16	2,343.49	5,249.5
II. Indirect Cost			
j. Management Fee (5%)	10.00		
k. GESA, 1/	8.84		
l. Price Contingency	10.00	10.00	22.4
Sub Total (Indirect)	28.84	10.00	22.4
Total Project Cost	5,445.00	2,353.49	5,271.9

Source: Explanatory in the Yen amount (as the JICA official rate of May, 2017)

Note: 1/ GESA, means for 'General Engineering Supervision and Administration'.

The total beneficiary area for MMIP II includes those where the planned civil works have been already completed or under implementation with funding from the GOP. The Survey is therefore, firstly, to define the actual area where civil works are still for implementation after 2018, by obtaining the information on the civil works that were already completed, and those that are being constructed which will be also carried out for funding in the future by the Philippine government.

Concerning the area to be developed with possible ODA loan financing, in fact, it was noted that though 3,581 ha was requested to JICA, NIA had already started tendering on the western part of LMSA by its own fund in late May 2017. Therefore, the actual service area which was originally required for Japanese ODA loan, was reduced covering probably only the eastern part of LMSA.

Though the request for the ODA loan financing was only for civil works with some appurtenant activities, there may be needs of implementing such additional works such as rehabilitation of already constructed facilities, support for farming, procurement of machineries for maintenance works, and also consulting services. With these in mind, the scope of MMIP II may have to cover the following areas:

Table 1.3.3 Potential Scopes of MMIP II for Possible ODA Loan Financing

Potential Scope	Contents
Development of the irrigation and drainage facilities in Lower Malitubog Service Area (3,581 ha requested)	To plan the development and rehabilitation of irrigation facilities in the target area. Note that though 3,581 ha was requested to JICA, in fact at the beginning of May 2017, NIA has already started tendering on the western part of Lower Malitubog service area by its own fund. Therefore, the actual service area to be funded by Japanese loan will be reduced, covering only eastern part of LMSA.
Rehabilitation of the existing irrigation facilities, which were developed by the project either in the MMIP I or in the early stage of MMIP II	To develop the rehabilitation or improvement plan based on the current situation of the already constructed facilities by the project in the total beneficiary area, irrespective of the project phase. Note that there are already damaged and/or dilapidated facilities which need rehabilitation or improvement.
Support for farming	To develop agriculture development support program/ activities for the total beneficiary area of the project. It is noted that though NIA does not directly undertake agriculture extension services, this activity of supporting farming is very essential since the beneficiary farmers are not used to irrigated farming. Therefore, supporting for farming should be one of scope, undertaken by ATI, PhilRice, or any other organizations.
Procurement of maintenance machineries	To plan procurement of machineries to be required for maintaining the irrigation facilities which, in fact, cover a total area of approximately 18,000 ha composed of both MMIP I and MMIP II. NIA regional office and NIA Cotabato Irrigation Management office do not have any equipment for maintaining the irrigation system, whereby a set of machineries should be procured for the purpose of sound maintenance.
Consulting service	To develop the plan of consulting services to be required for civil works and other "soft" components such as institutional development, e.g. IA establishment, procurement, support for farming, etc.

Source: JICA Survey Team

1.4 Schedule of the Survey

To attain the objective, the Survey was carried out in a step-wise manner divided into two: the first part deals mainly with situation analysis, identification of project scope, and formulation of preliminary project proposal, and the second part undertakes through the discussions with the relevant organizations and additional field surveys, the finalization of the project plan including project design, project evaluation, implementation arrangement, etc. Note that environmental and social consideration are, of course, undertaken in the former part, and additional surveys are to be conducted during the latter part of the Survey including, as per the need, preparation of Resettlement Action Plan (RAP) and Indigenous Peoples Plan (IPP).

The original survey period was set to complete within 6 months from May 2017 to October 2017 provided that significant environmental and social issues are not foreseen. The environmental category for the MMIP II is type 'B' as of the survey commencement; however, if the category is to be changed to 'A' which is expected to give noticeable impact on the environment and/or social conditions, additional surveys should be required and hence the survey period shall be extended accordingly. Additional surveys, here expected, are for example preparation of resettlement action plan, preparation of indigenous peoples plan, among others.

Though the original survey period was 6 months as above-mentioned, a martial law was enforced in the whole of Mindanao on May 23, 2017 by a proclamation No. 216 issued by Philippine President Rodrigo Duterte. The martial law was extended on July 23, 2017 valid until December 31, 2017. Then, the martial law was further extended until the end of year 2018. Due to this martial law, field surveys for the Preparatory Survey were suspended in late May 2017, and the JICA team has been unable to go back to the project area to date.

During the suspension, a new task which is flood simulation for Pulangi river was added in order to

explore the impact of flooding of Pulangi river to the LMSA. The JICA Team had conducted river survey, longitudinal and cross-sectional surveys, and accordingly the flood simulation from September 2017 to March 2018. With this additional task, the survey period was extended to October 2018. On the way of the extended survey period, 1st interim report was produced at mid July 2017 summarizing the draft project proposal, and the 2nd interim report is presented in Mid July 2018, and then draft final report will be submitted at around August 2018, and its final version is to be produced at around October 2018 (see the table below).

Table 1.4.1 Overall Survey Schedule

Year/ Month	2017										2018									
	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	
Stage 1																				
Draft f Project Proposal																				
Flood Simulation																				
Stage 2																				
Finalization of Project																				
Report		ICR		ITR1							SR				ITR2	DFR		FR		

Where; IC/R: Inception Report, ITR: Interim Report, SR: Flood Siulation Report, DFR: Draft Final Report, FR: Final Report

1.5 The Survey Area

MMIP is located in the municipalities of Aleosan, Pikit and Carmen in Cotabato province, and municipality of Pagalungan and Datu Montawal in Maguindanao province. MMIP is implemented in two phases, the Phase I (MMIP I) was envisioned to generate irrigation facilities on 10,840 hectares while the remaining area of 8,760 hectares for Phase II (MMIP II) was planned to commence upon the completion of MMIP I.

Despite of difficulties of project implementation in conflict area, MMIP I concluded and turned-over completed facilities of 5,562 ha in MSA and 1,611 ha of UMSA. These two areas declared the formal turn-over to Regional Office XII effective on October 31, 2011 after the completion of additional improvement works. On the other hand, the MMIP II area is composed of 3 service areas; 1) UMSA, 2) PESA, and LMSA, and the construction work of MMIP II was started in 2011.

The construction of MMIP II was commenced from the service area of Upper Malitubog in 2011, and till today construction of PESA and LMSA are on-going including the mid-eastern part which was started in 2015, central part in 2016, and whole western part with a bit of most north-eastern part which started in 2017.

Southeastern part is left untouched and is where the main survey area for the originally requested ODA loan funding. Note that the request of NIA included the most western part and the most south-eastern part of




Figure 1.5.1 MMIP Service Area and the Major Survey Area

Source: MMIP II PMO, JICA Survey Team

Lower Malitubog Service Area; however, the works in the former part was starting as of July 2017. The untouched area covers approximately 2,100 ha, and the works possibly funded by loan may, aside from the establishment of irrigation network in that untouched area, include access road construction, ring dyke construction along the southern most boundary of the LMSA.

1.6 Implementation Arrangement of the Survey

The chart below shows the working structure for the Preparatory Survey. NIA MMIP Project Management Office (PMO) is the executing agency, and therefore was the main counterpart organization to the Survey. In addition, NIA Region XII office and NIA Cotabato Irrigation Management Office are support offices from which relevant data & information were furnished concerning irrigation operation & maintenance. The Team members worked with these counterpart personnel from the executing agencies in coordination with JICA headquarters and JICA Philippines office. Relevant organizations are also shown, to which the Survey Team gathered information and collected data.




Figure 1.6.1 Working Structure for the Preparatory Survey

Source: JICA Survey Team

CHAPTER 2 THE PROJECT AREA

The Project, Malitubog Maridagao Irrigation Project (MMIP) is composed of MMIP I and MMIP II, which are located in parts of 5 municipalities of Carmen, Kabacan, Pikit, Datu Montawal and Pagalungan. The first 3 municipalities fall in Cotabato province while the latter 2 municipalities in Maguindanao province (ARMM). The JICA survey team interviewed relevant government offices, such as NIA PMO and local government units (municipalities). Further, the team conducted surveys to barangays, villagers, etc. to grasp current situation. In this chapter, the current condition of the Project area is discussed based on those interviews and surveys:

2.1 Salient Features of the Project Area

2.1.1 Spatial Settings and Contextual Positioning

The Project area of MMIP starts at the diversion point established on the Maridagao River with coordinates of 7°11'49" N and 124°43'08" E, located in Municipality of Carmen, Province of Cotabato. The diversion dam, a headworks, provides water to the Maridagao Service Area (MMIP I) extending on the left bank side of the Maridagao river, and then after crossing the river with a siphon, it further irrigates the Upper Malitubog Service Area (upstream) now extending on the right side of Maridagao river. Both Maridagao Service Area and the Upper Malitubog Service Area (upstream) were established under MMIP I.




Figure 2.1.1 Project Map of MMIP I and MMIP II

Source: NIA- PMO

After the Upper Malitubog Service Area (UMSA) under MMIP I, the irrigation water is further delivered to 3 blocks which are all placed under MMIP II construction works; namely, 1) Upper Malitubog Service Area (downstream UMSA), 2) Pagalungan Extension Service Area (PESA) and 3) Lower Malitubog Service Area (LMSA). The most downstream area of MMIP is therefore located in the most southern part of the irrigable area with coordinates of 6°57'8" N and 124°40'01" E. Thus, from north to south direction, the MMIP area extends over a distance of approximately 27 km while it extends over about 30 km length from west to east direction. Concerning the elevation, the diversion point indicates 35 m as top bank elevation¹ while the most downstream point shows almost 0 meter altitude.

The Project site falls in the 2nd biggest basin in the Philippines, Mindanao river basin, which has as large area as 21,530 sq.km, and in fact it is located at the vicinity of, and partly within, a large marsh, so-called Liguasan marsh (see Figure 2.1.2). Liguasan marsh occupies an area of approximately 80,000 ha² and the area including the surrounding ones may reach as huge area as 280,000 ha³. Therefore, the project area, especially the southern parts of it, is very prone to flood taking place

¹ The design flow level at the diversion point is 32.50 AMSL, and normal operation water level is 31.00 AMSL. Intake upper water level is 31.00 AMSL and intake mean water level is 30.08 AMSL. Intake maximum discharge is set at 35.6 cum/s.

² 'Liguasan marsh development master plan, November 1998.

³ BirdLife International (2017) Important Bird Areas factsheet: Liguasan marsh.

almost every year along the Pulangi River, a big tributary of Mindanao River.

2.1.2 History of MMIP Development

The implementation of MMIP I was commenced in April 1993. However, the construction of MMIP I had undergone very difficult situations which caused the death of more than 200 combatants, thousands of displaced families, and millions of lost personal belongings and properties, and resulted in periodical stoppages of the works. Despite those difficulties, the MMIP I had finally been completed and the project handed over the completed areas of MSA (5,562 ha) and UMSA (upstream, 1,611 ha) to the Regional Office XII on October 31, 2011. It took more than 17 years since the commencement till the completion for the MMIP I.

The contract for the construction of diversion dam, wing dikes, diversion canal, left main canal, bridge and siphon was procured through International Competitive Bidding (ICB), and it was awarded to Shinsung Corporation, a Korean firm. The contract package had the duration of 1,320 calendar days with the contract expiry date on November 14, 1996.

In the course of the implementation, the Korean firm had encountered several challenges. Among them, peace and order problem in particular was really beyond the control of NIA-PMO and the Korean firm. Due to unstable peace and order within the project area in the years 1994 to 1995, and in spite of several attempts of both NIA and the Korean firm to resume the work, the contract was terminated on April 27, 1995 by mutual agreement. All the construction works for the contract package MMIP I-C-1 were therefore suspended with only 17.4% cumulative accomplishment upon the termination.

The Department of Agriculture through the initiatives of NIA on March 24, 1997 sent a letter to the Ambassador of Japan to the Philippines to request for assistance in the project resumption with the information on the peace agreement (General Cessation of Hostilities) between GOP and MILF. Finally, on May 18, 1998, the Government of Japan (GOJ) through its embassy gave GOP the go-signal to resume works of the project. On December 7, 1999, the bidding for the remaining works was successfully conducted and China Electric Power Technology Import & Export Corporation (CETIC) was awarded. The work by the Chinese company was completed in September 2001.

After the completion of the works by the Chinese company, force account and local contractor works had been progressed and consultant also had been engaged till April 2003 in order to supervise the force account works. Even after the closure of the Yen loan for MMIP I in May 2003, after an extension, force account works with local contractor works had continued being implemented till 2011, during which the Upper Malitubog Service Area, 1,611 ha⁴, was completed with the GOP fund.




Figure 2.1.2 Project Site and Marsh Affected Area

Source: Mindanao River Basin MP, JICA Team

⁴ The original plan of MMIP I was to construct 2 blocks of Upper Malitubog Services Areas, however due to fund shortage by the Philippine government, only the upstream UMSA, 1,611 ha, was undertaken by MMIP I and the remaining part was pushed to the MMIP II, which had started in 2011.

In the same year 2011, when MMIP I had been completed, MMIP II was started with the construction of UMSA with the GOP's own budget. The construction of the UMSA had continued till 2014, and new construction was started in 2015 undertaking Pagalungan Extension Service Area as well as a mid-eastern part of the LMSA. Further in 2016, construction in the central part of the LMSA was commenced, and in 2017 the most western part of the LMSA was placed in bidding, and expected to start the construction within the year.

With respect to the cost of MMIP I, the original cost was PhP1.05-billion with scheduled project completion on December 1996. First project cost increase was approved amounting to PhP2.5-billion and extended the project to December 2002. With further additional cost of approximately PhP600-million, the project actual expenditures as of June 30, 2006 arrived at PhP3,103.35-million. However, as there were additional and improvement works needed to be done, an amount of PhP79.99-million was incurred until December 2010, hence total project cost for MMIP I amounted to PhP3,183.34-million. In terms of Yen, total expenditure amounted at 8.43 billion Yen, of which 4.541 billion Yen was disbursed by the ODA loan.

Table 2.1.1 Actual Expenditure for the MMIP I

Breakdown of Cost (Fiscal Year)	Foreign		Local		Total	
	Total Cost	OECF	Total Cost	OECF	Total Cost	OECF
	(in million yen)		(in million pesos)		(in million yen)	
1990	0	0	10		59	0
1991	121	121	7		156	121
1992	508	508	14		577	508
1993	512	512	29		632	512
1994	312	312	51		510	312
1995	112	112	42		271	112
1996	55	55	28		161	55
1997	115	115	43		290	115
1998	327	327	63		544	327
1999	12	12	114		344	12
2000	413	413	114		691	413
2001	769	769	216		1,303	769
2002	716	716	375		1,624	716
2003	569	569	124		834	569
2004			230.11		230	
2005			121.30		121.30	
2006						
2007						
2008			36.43		36.43	
2009			33.56		33.56	
2010			10		10	
2011			100			
Total	4,541	4,541	1,761.30		8,427.4	4,541

Source: Project Completion Report, MMIP, Stage I, November 2014

For the MMIP II, the NEDA-ICC approved project cost is PhP5,444.84-million, which started to flow in year 2011 with PhP200-million allotment. Till the end 2016, total PhP3,091-million had been allotted, of which PhP2,987-million had been released to the PMO, and further out of the released budget, PhP1,893-million has been actually expensed. According to NIA original plan, construction by the government own budget will continue till 2018 with PhP600-million allotment per year, and thereafter loan was expected to use for the remaining works (note that as of June 2018, loan request was withdrawn).

2.1.3 Area, Population and Beneficiaries of MMIP II

As mentioned above, the MMIP is composed of MMIP I and MMIP II, and further the MMIP I area is composed of 2 irrigation blocks while the MMIP II consists of total 3 irrigation blocks. The irrigable area of MMIP I comes to 7,173 ha while that of MMIP II arrives at 10,536 ha, totaling to 17,709 ha. It is noted that the area is basically defined as net irrigable area; however, there are coconut tree farms within the irrigable area. Coconut farmers seldom, or at least within a short period of time, do not change the coconut farm to crop farmland. Therefore, actual net irrigable area for crops should be the following area less coconut farmland area.

Table 2.1.2 Summary of the Irrigation Service Area

Project	Irrigation Block	Service Area, ha	Construction
MMIP I	Maridagao Service Area	5,562	2011 completed
	Upper Malitubog Area (upstream)	1,611	2011 completed
Sub-total		7,173	
MMIP II	Upper Malitubog Area (downstream)	2,206	Commenced in 2011
	Pagalungan Extension Service Area	988	Commenced in 2015
	Lower Malitubog Service Area	6,590	Commenced in 2015
Sub-total		10,536	
Total		17,709	

Source: NIA-PMO, MMIP II

MMIP II area is further categorized by the commencement year of the construction. The construction of UMSA was firstly commenced in 2011 (see brown colored part), followed by the construction of extension service area in 2013 (yellow part), and lastly the construction was started in 2013 in the eastern part (light blue color). Then, in 2015 the construction progressed to the PESA as well as to the eastern part of LMSA (light green colored parts). The construction further progressed to, e.g., the central part of LMSA in 2016, the most western part of LMSA in 2017. As of May 2017, the bidding was already held for the most western part of LMSA, whereby the untouched part is only the south-eastern part of the LMSA as of May 2017 (see light blue colored part; a part of areas originally requested for ODA loan funding).




Figure 2.1.3 Project Area by Commencement Year

Source: NIA-PMO

In the project area, there are farmer households (HHs) who will directly benefit from the irrigation systems. Though the identification of beneficiaries is still on-going as the project progresses, there are already some areas where the number of beneficiaries was confirmed. Those areas where the number of beneficiaries are already confirmed, are the MMIP I areas, the UMSA of MMIP II, and the part of LMSA, where the construction was started in 2015. Based on the identified number of beneficiaries, the average farmland area can be estimated as from 1.2 to 1.7 ha per farm household approximately. Further, by applying these figures of estimated average farmland area per household, the number of beneficiaries for those un-surveyed areas can be also estimated. As a result, the number of beneficiaries of each area can be estimated as shown in Table below:

Table 2.1.3 Summary of the Irrigation Beneficiaries Farmer Households (FHHs)

Service Area	Stage	by Starting Year	Irrigable Area, ha	Beneficiary FHHs	Population	Area/ FHHs, (ha)	Status
Maridagao	Phase 1	Completed in	5,562	4,278	21,521	1.30	Confirmed
Upper Malitubog	Phase 1	2011	1,611	1,239	6,233	1.30	Confirmed
	(Phase 1)	Started in 2011	2,958	1,782	8,963	1.66	Confirmed
	↓						
Phase 2							
Pagalungan Ext.	Phase 2	Started in 2015	988	788	3,963	1.25	Confirmed
Lower Malitubog	Phase 2	Whole	6,590	5,255	26,434	1.25	Estimated
		2015	1,303	1,039	5,227	1.25	Confirmed
		2016	1,736	1,384	6,963	1.25	Estimated
		2017-18	1,418	1,131	5,688	1.25	Estimated
		2019 (ODA)	2,133	1,701	8,556	1.25	Estimated
Total	Phase 1		7,173	5,518	27,754	1.30	
	Phase 2		10,536	7,825	39,360	1.35	
G. Total			17,709	13,343	67,114	1.33	

Source: NIA-PMO, MMIP II, JICA Survey Team

In the MMIP I area, it is estimated that there is a total of 5,518 farm household beneficiaries while that of MMIP II area would be 7,825 farm household beneficiaries; therefore, the total number of beneficiary HHs can be 13,343. Taking into account that the average rate of household members in Pikit municipality for 2015, namely, 5.03 persons/ household, the total number of beneficiaries can be estimated around 67,114 persons.

2.1.4 Meteorology: Temperature and Rainfall

Since the Project area is located in the N-coordinate of around 7 degrees, it has a tropical wet climate with no dry or cold season as it is constantly moist, represented with year-round rainfall. The climate data are available in Midsayap and Kabacan towns, which in fact have not been continuously recorded. There is, however, a series of simulated climate data based on satellite image analysis at a point of each 35 km x 35 km, which are provided by Climate Forecast System Reanalysis (CFSR) operated by the National Centers for Environmental Prediction (NCEP, US)⁵. The data are available since year 1979 to July 2015.


Table 2.1.4 and Figure 2.1.4 show the points where climate data are available provided by CFSR; namely Station No.13 located near Pikit town may represent the climate of the irrigable area while Station No. 18, No.23, No.24 and No.28 may represent climate condition within the catchment area.

Monthly temperature and monthly rainfall at Station No.13 are indicated in Figures 2.1.5 and 2.1.6. One of the characteristics is that in fact there is not much temperature fluctuation throughout year, with a bit of

Table 2.1.4 Climate Stations (by Satellite Image Analysis)

Station No.	Elevation, m	Longitude	Latitude
S13	10	124.688	7.025
S18	399	124.688	7.337
S23	794	124.688	7.649
S24	321	125.000	7.649
S28	1,277	124.688	7.962

Source: NCEP

**Figure 2.1.4 Climate Station Location**

Source: NCEP, US

⁵ All data are available and downloadable from: <https://globalweather.tamu.edu/>

increase in March – May which is the right before the onset of rainy season. The minimum monthly temperature hovers at around 20 Celsius degrees while the maximum one ranges from 33 to 35 Celsius degrees.

The monthly basis rainfall indicates no clear demarcation between dry season and rainy season; however, it is generally said that the rainy season is from May to October while the dry season is from November to April in the following year. The annual rainfall at Station No.13, estimated for the period from 1979 to 2015, marks only 902 mm, of which about 40% falls during the dry season.




Figure 2.1.5 Monthly Temperature Trend (Pikit Area)
Source: NCEP, US




Figure 2.1.6 Monthly Rainfall Trend (Pikit Area)
Source: NCEP, US

Figure 2.1.7 shows annual rainfall trend while Figure 2.1.8 indicates only the dry season’s rainfall from November to April at Station No.13 (Pikit town). The average annual rainfall, as afore-mentioned, arrives at 902 mm while the dry season’s rainfall comes to 352 mm, equivalent to approximately 40% of the annual rainfall. There is a unique character in that rainfall for the last 3 years (4 dry seasons) has in fact increased to as much as double amount as compared to the past rainfalls. The long-term trend may be said that the rainfall, both annual and dry season ones, have fluctuated with an overall increase trend.




Figure 2.1.7 Long Term Trend for Annual Rainfall (Pikit)
Source: NCEP, US




Figure 2.1.8 Long Term Trend for Dry Season Rainfall (Pikit)
Source: NCEP, US

Concerning rainfall in the catchment area of the irrigation system, Figure 2.1.9 summarizes the monthly basis rainfall for the 5 stations; one is Station No.13 (Pikit) and the rests are associated with the catchment area. As is well shown in the monthly rainfall, the amount differs by station very much; namely, the station located at lower elevation shows less amount of rainfall while such stations located in higher elevation indicate much bigger amount of rainfall. In fact, Station 13 (around Pikit town area) shows only 902 mm while the Station 28 located at the most upstream edge of the catchment area gives as much as 6,477 mm, approximately as much as 6 times rainfall.




Figure 2.1.9 Monthly Rainfall Trend (Catchment Area)

Source: NCEP, US

proportionally calculated based on the catchment area covered by each of the Stations⁶ of No. 18, 23, 24, and 28 as indicated in Table 2.1.5.

Figure 2.1.10 depicts the annual rainfall weighted over the catchment area ranges in most years from 3,000 mm to 6,000 mm with an average of 4,778 mm while Figure 2.1.11 indicates the dry season rainfall does from 1,000 mm to 2,000 mm with an average of 1,755 mm. Though the rainfall fluctuates year by year, the overall trend may be said on an increase, especially with the last 3-4 years much rainfall.

Table 2.1.5 Climate Stations and Command Area

Station No.	Elevation, m	Area, sqkm	Ratio
S13	10	0	0.00
S18	399	375	0.27
S23	794	659	0.48
S24	321	75	0.05
S28	1,277	271	0.20
Total		1,380	1.00

Source: NCEP, and JICA Survey Team

Figure 2.1.10 and Figure 2.1.11 show the weighted annual rainfall and weighted dry season rainfall (from November to April) for the catchment area of the diversion dam. The weighted rainfalls were




Figure 2.1.10 Long Term Trend of Annual Rainfall (CA)

Source: NCEP, US




Figure 2.1.11 Long Term Trend of Dry Season Rainfall (CA)

Source: NCEP, US

2.1.5 Hydrology and Future Irrigation Water Availability

The MMIP has the diversion point on the Maridagao River at a location of 7°11'49" N and 124°43'08" E. The catchment area at this diversion point comes to 1,389 sqkm. The diversion point does not have any gauging station, and therefore during the feasibility study (June 1986), runoff records at Tinutulan gauging station were employed to estimate the river discharge at the diversion point. The Tinutulan gauging station is located about 10 km downstream from the diversion point, and the station was functioning only from 1960 to 1972 (13 years only).

The runoff from 1960 to 1972, only 13 years, were interpolated over a period from 1956 to 1987 with reference to the rainfall recorded at Midsayap ground station during the feasibility study. Thus, the runoff data became available over a period of 32 years. The catchment area at the Tinutulan gauging

⁶ The stations referred to by the NCEP are considered to represent each 35km x 35km rectangular area. Therefore, one NCEP station provides rainfall for an area of 35km x 35km rectangular with the station being the center.

station arrives at 2,077 sqkm, and therefore the catchment area, 1,380 sqkm, of the diversion point shares 66.4 % of that of the Tinutulan gauging station. Thus, during the feasibility study, 66.4 % of the runoff at the Tinutulan gauging station was utilized to design the system reliability on irrigation water availability for the whole command area of MMIP I and MMIP II area.

As the satellite-based rainfall data is available only from year 1979 to 2014, this data cannot be utilized to directly interpolate the actual runoff data recorded at the Tinutulan gauging station, which was closed in year 1972. Therefore, by utilizing the correlation between 1979 and 1987, during which both satellite data and interpolated runoff by using Midsayap rainfall are available, the runoff discharge at the diversion point is now estimated up to 2014. Figure 2.1.12 shows the annual runoff from year 1956 to 2013 while Figure 2.1.13 indicates the dry season runoff (November to April) by year.

Annual runoff shown in Figure 2.1.12 does not much fluctuate by year and ranges from 1,500 to 2,000 million cubic meter (MCM) in most years with an average of 2,097 MCM. As correlated with the rainfall, the runoffs for the last 3 years are much more than those as compared with the past. On the other hand, dry season's runoff fluctuates more than the annual runoff, ranging from as low as less than 200 MCM to more than 1,200 MCM. The average dry season runoff over the period of 1956/57 – 2013/14 is estimated at 777 MCM. The runoff ratio, defined as the ratio between the rainfall and the discharge, is computed at 0.321.




Figure 2.1.12 Annual Runoff at the Diversion Dam Point (1,380 sq. km catchment area)

Source: National Centers for Environmental Prediction (NCEP)




Figure 2.1.13 Dry Season Runoff at the Diversion Dam Point (1,380 sq. km catchment area)

Source: National Centers for Environmental Prediction (NCEP)

2.1.6 Regional and Barangay (Household) Economies

1) Demographic Statistics

Table 2.1.6 summarizes demographic statistics for the MMIP relevant provinces / municipalities. In 2015, there were 543 barangays in the Cotabato province. The population of the province marked

1,373,962 and its land area covered 9,317.30 sq.km, giving 148 persons per sq.km population density. The average HH size of Cotabato province was 4.29, which was in fact close to the country's average of Philippines, 4.4 persons per household.

Concerning Maguindanao province which is under ARMM, there were 508 barangays in 2015 and the population came to 1,172,381 with the land area of 9,968.31 sq.km, showing the population density of 118 persons per sq.km. The average HH size was 6.03, which was significantly larger than that of Cotabato province. The average HH size in Maguindanao Province is in fact bigger than the country's average by 1.63 persons.

Table 2.1.6 Demographic Statistics of the Relevant Provinces and Municipalities

Municipality	Number of Barangay	Population	Land Area (sq.km)	Population Density (persons per sq.km)	Number of Household	Average HH Size
Cotabato (Province)	543	1,379,747	9,317.30	148	320,567	4.29
Carmen	28	95,921	1,110.43	86	21,905	4.38
Pikit	42	154,441	604.41	255	36,099	4.27
Aleosan	19	39,405	225.44	175	8,845	4.45
Maguindanao (Province)	508	1,173,933	9,968.31	118	194,507	6.03
Datu-Montawal (Pagagawan)	11	34,820	461.10	76	5,693	6.12
Pagalungan	12	39,653	898.76	44	6,810	5.82
National	42,036	100,573,715	300,000	337	22,975,630	4.40

Source: Philippine Statistics Authority, Census of Population and Housing 2015

Census of Population and Housing 2010 estimated future population of year 2010 – 2045 as shown in Figure 2.1.14. Based on the projection, the population of Cotabato province would increase to 2,167,200 at the year of 2014, 63% increase during 2010 - 2045. On the other hand, the population of Maguindanao province was expected to be almost doubled from 1,173,933 to 1,845,500 by 95% increase, during the period of 2010 – 2045.




Figure 2.1.14 Projected Population by Five-Calendar Year
Census of Population and Housing 2015




Figure 2.1.15 Annual Growth Rates by Five Calendar-Year
Census of Population and Housing 2015

Average regional and provincial annual population growth ratio by five calendar-year interval is shown in Figure 2.1.15. The expected population growth in Region XII and ARMM could be much higher than that of the national average, and especially that of the ARMM. In medium assumption as indicated in the figure, approximately 2.2% and 2.4% of the population growths are projected for Maguindanao province and ARMM respectively while about 1.7% and 1.8% population growths are expected in Region XII and Cotabato province during the years from 2020 to 2025. Note that 2% population growth ratio per annum would double the population in 36 years.

2) Gross Regional Domestic Product (GRDP)

Table 2.1.7 shows gross regional domestic product (GRDP) as of 2016 for the 2 regions of Region XII

and ARMM. In Region XII, the primary sector of agriculture, hunting, forestry and fishing shared 26.2% of the GRDP while that of ARMM did as high as 59.3% of the GRDP⁷. The industrial sectors for the 2 regions consisted of 33.3 % and 5.1% respectively for Region XII and ARMM, implying very low industrial development in the ARMM area. The service sector of the regions shared 40.6 % and 35.6 % respectively. These sector basis shares show that ARMM is very much agriculture dominated region, also as indicated by only 5.1% of share by industrial sector, while Region XII is not such.

Table 2.1.7 Gross Domestic Product by Industrial Origin, 2016 at Current Price

INDUSTRY	Region XII		ARMM	
	000' peso	%	000' peso	%
I. AGRICULTURE, HUNTING, FORESTRY & FISHING	101,214,738	26.2	61,655,650	59.3
a. Agriculture and Forestry	83,579,856	21.6	50,539,859	48.6
b. Fishing	17,634,882	4.6	11,115,791	10.7
II INDUSTRY SECTOR	128,667,035	33.3	5,302,132	5.1
a. Mining and Quarrying	690,533	0.2	363,921	0.4
b. Manufacturing	77,903,428	20.1	1,160,749	1.1
c. Construction	34,227,176	8.8	2,025,988	1.9
d. Electricity, Gas and Water Supply	15,845,899	4.1	1,751,475	1.7
III SERVICE SECTOR	156,911,343	40.6	36,973,726	35.6
a. Transportation, Storage & Communication	21,932,513	5.7	4,443,523	4.3
b. Trade & Repair of Vehicles, Motorcycles, Personal and HH Goods	41,054,351	10.6	1,359,791	1.3
c. Financial Intermediation	22,017,150	5.7	4,330,044	4.2
d. Real Estate, Renting & Business Activities	24,465,406	6.3	8,254,200	7.9
e. Public Administration & Defense; Compulsory Social Security	13,697,290	3.5	12,382,828	11.9
f. Other Services	33,744,632	8.7	6,203,340	6.0
GROSS DOMESTIC PRODUCT	386,793,116	100.0	103,931,508	100.0

Source: Philippine Statistics Authority

Figure 2.1.16 shows dependency ratio on agricultural production in the GRDP from 2001 to 2015 at current price. At a glance, it is clearly found that Agriculture Industry has been prevailing as the main industry as compared to the national average especially in the case of ARMM; accounted for around 30% and 60% as of 2015 in Region XII and ARMM respectively. Further, changes in times look differently by region. Till year 2008, the dependency on agriculture production in both regions seems to have been increasing or at least stayed at a constant level. After the year 2008, that of Region XII started decreasing while that of ARMM once jumped up to nearly about 70% in 2010, and then started decreasing.




Figure 2.1.16 Percentage of Agricultural Production in GRDP, 2001-2015 at current price (Source: Philippines Statics Authority)

3) Household Income

Table 2.1.8 summarizes household income status of the 2 regions as compared with that of Philippines (Source: 2015 Family Income and Expenditure Survey Final Report). The mean household income of Region XII is 188,000 Peso, approximately 70% of the national average (267,000 Peso). On the other

⁷ With reference to the Country STAT 2013, of the total agricultural output of Region XII, the crop sub-sector comprised as high as 68.0%, followed by fisheries sector (15.6%), livestock sector (10.8%), and poultry sector (5.6%). In ARMM, of the total agricultural output, the crop sub-sector shared the biggest range of 71.6%, followed by fisheries (22.4%), livestock (4.2%), and poultry (1.9%).

hand, the mean household income of ARMM is only 139,000 Peso, which consists only of 52% of the national average, implying high poverty incidence in the ARMM area.

By composition, as is expected by the mean income, the top income class out of 5 categories shares only 7.6% in ARMM while that of the Philippines does as much as 35%, and that of even Region XII shares 19%. With respect to the sum of lowest 3 classes less than 100,000-peso income, the nation's average shows a share of 20% while Region XII marks 39% and ARMM does 35%. In any case, both regions incomes are lower than that of the Philippines, and especially the income level of ARMM can be said quite low.

Table 2.1.8 Distribution of Household by Income Class and by Region, 2015

Regions		All Income Classes	Mean Income (in thousand Peso)	Income Class					Class Distribution
				Under 40,000	40,000 - 59,999	60,000 - 99,999	100,000 - 249,999	250,000 - and over	
Philippines	000' Families	22,730	267	355	901	3,268	10,318	7,888	
	%	100.0%		1.6%	4.0%	14.4%	45.4%	34.7%	
Region XII	000' Families	1,055	188	47	104	255	447	202	
	%	100.0%		4.5%	9.9%	24.2%	42.4%	19.1%	
ARMM	000' Families	616	139	1	24	187	357	47	
	%	100.0%		0.2%	3.9%	30.4%	58.0%	7.6%	

Source: Philippines Statistics Authority, 2015 Family Income and Expenditure Survey Final Report

4) Poverty Incidence at Municipality Level

Figure 2.1.17 shows the poverty incidence of the Country, Region XII and ARMM from 2006 to 2015 with 3-year interval (Source: Philippine Statistics Authority). In addition, Table 2.1.9 elaborates the poverty prevalence at the province and municipality level, which was collected through a national government funded project on small area estimates on poverty.




Figure 2.1.17 Poverty Estimates 2006 - 2015

Source: Philippine Statistics Authority

Table 2.1.9 Poverty Incidence (Province/ Municipality)

Area	Poverty Incidence (%)			
	2006	2009	2012	2015
Cotabato	25.6	23.4	44.8	34.5
Carmen	39.4	50.4	56.4	NA
Kabacan	30.6	35.0	38.0	NA
Pikit	51.9	48.5	57.8	NA
Maguindanao	46.4	43.3	54.5	48.8
Pagalungan	NA	NA	37.5	NA
Datu Montawal	NA	NA	76.2	NA

Source: Philippine Statistics Authority,

The national and regional level data clearly show higher poverty incidence in the 2 regions as compared to the national level. The poverty incidence of the Country is around 20% or less than that while that of Region XII marks around 30% or more and ARMM shows much worse situation, more than 40% to as high as nearly about 50-55%. It means that the share of the people falling below the poverty line in Region XII is about 1.5 times more, and that of ARMM is even more than double as compared to that of the Country.

Worse, though the national level poverty ratio shows continuous declining trend during the period from 2006 to 2015 as being from 21% to 17%, the poverty incidences for the Region XII and ARMM have not so done. The poverty incidence in Region XII once jumped up in year 2012 and same trend took place in ARMM too. The hiked poverty incidence in Region XII has dropped in 2015 to that level of 2009 or 2006; however, the increased incidence of ARMM has been kept high even in 2015.

At provincial and municipality level shown in Table 2.1.9, the poverty incidences for the both

provinces can be said worse for the recent years of 2012 and 2015. For example, the poverty incidences of Cotabato province marked 44.8% and 34.5% respectively in year 2012 and 2015, both of which are higher than those of Region XII. Same tendency can be found in Maguindanao province as exemplified by the incidences being 54.5% and 48.8% in 2012 and 2015 respectively. Looking into the poverty at municipality level, the ratio more than 50% was marked in such municipalities as Carmen (56.4%), Pikit (57.8%), and Datu Montawal (formerly Pagagawan; 76.2%).

5) Employment Structure

Table 2.1.10 shows the number and the percentage of employed persons by region and by major industry group in year 2014. Total 1,735,000 persons were employed in 2014 in Region XII, and approximately half (45%) of it was absorbed by agriculture, hunting and forestry industry group. Fishing and aquaculture has generated only 3% of the employment. Aside from the agriculture and fishing & aquaculture, 18% of total employment had been engaged in wholesale and retail trade, repair of motor vehicle and motorcycle industry, followed by transportation and storage industry (6%).

The employment in year 2014 in the ARMM region totaled to 1,295,000 persons, of which 52% were employed in the agriculture, hunting and forestry sector. Fish and Aquaculture accounted for another 16% of total employment, the second largest industry group in the ARMM region. Most of job opportunities were in fact generated from major four industries such as: 1) agriculture, hunting and forestry, 2) fishing and aquaculture, 3) wholesale & retail trade, repair of motor vehicles & motor cycles, and 4) transportation and storage, which together accounted for approximately 90% of total employment in 2014.

Table 2.1.10 Employed Persons by Region and Major Industry Group, 2014

Major Industry Group	Region XII		ARMM	
	000' worker	%	000' worker	%
Total	1,735	100%	1,295	100%
Agriculture, Hunting and Forestry	774	45%	676	52%
Fishing and Aquaculture	55	3%	212	16%
Mining and Quarrying	4	0%	3	0%
Manufacturing	93	5%	13	1%
Electricity, Gas, Steam and Air Conditioning Supply	3	0%	1	0%
Water Supply; Sewerage, Waste Management and Remediation Activities	1	0%	*	0%
Construction	56	3%	13	1%
Wholesale and Retail Trade; Repair of Motor Vehicles and Motorcycles	308	18%	190	15%
Transportation and Storage	110	6%	77	6%
Accommodation and Food Service Activities	42	2%	5	0%
Information and Communication	7	0%	1	0%
Financial and Insurance Activities	15	1%	1	0%
Real Estate Activities	3	0%	-	0%
Professional, Scientific and Technical Activities	3	0%	*	0%
Administrative and Support Service Activities	20	1%	6	0%
Public Administration and Defense; Compulsory Social Security	83	5%	44	3%
Education	55	3%	40	3%
Human Health and Social Work Activities	14	1%	3	0%
Arts, Entertainment and Recreation	7	0%	*	0%
HH Activities as Employers; Undifferentiated Goods and Service-producing Activities for Own Use	61	4%	8	1%
Activities of HHs for Own Use	18	1%	1	0%
Activities of Extraterritorial Organizations and Bodies	1	0%	*	0%

Source: Averages of Three (3) survey rounds of the Labor Force Survey

Table 2.1.11 shows the numbers and percentages of employed persons by region and by class of workers in 2014. In Region XII, about half of total employed persons were wage and salary workers (49%), while self-employment and family own business accounted for another half in 2014. In ARMM, on the contrary, wage and salary workers accounted for only 18% of the employed persons. It means

that more than 80% of workers in the ARMM were engaged in own-family operated farming or own-family operated businesses.

Table 2.1.11 Employed Persons by Region and Class of Worker, 2014

REGION AND CLASS OF WORKER	Region XII		ARMM	
	000' worker	%	000' worker	%
Total	1,735	100%	1,295	100%
Wage and Salary Workers	850	49%	228	18%
Worked for private household	55	3%	5	0%
Worked for private establishment	659	38%	144	11%
Worked with pay in own family-operated farm or business	5	0%	3	0%
Worked for government/government corporation	132	8%	75	6%
Self-employed without any paid employee	597	34%	695	54%
Employer in own family-operated farm or business	48	3%	12	1%
Without pay in own family-operated farm or business	240	14%	361	28%

Source: Averages of Three (3) survey rounds of the Labor Force Survey

6) Barangay Economies (Baseline Survey)

In order to investigate the positive/negative impact of the project and to set baseline values for the project area, a baseline survey has been conducted in the MMIP I and MMIP II areas. The survey was launched on June 12, 2017 and completed in late July 2017. In the following, the types of survey, survey design, sampling, results and discussions are shown:

6.1) Types of Survey

The survey includes different activities; namely, 1) barangay profile establishment, 2) focus group discussion, and 3) farmer household economic survey. Each activity has different purposes aiming at revealing a part of aspects in the target area:

1. Barangay Profile (9 Barangays): It aims at collecting general characteristics of the target barangays through interviewing barangay captains and other local key villagers,
2. Focus Group Discussion (9 Barangays): It aims at collecting in-depth/nuanced information on socioeconomic-needs, and evaluation and expectation of MMIP project. The participants include various stakeholders, at least, Barangay Captain; Barangay Councilors; Chairperson of Youth Council; Group / Organization / Association / Cooperative representatives in the Barangays to representative different ethnic and religious group, farmers, organizations, women's organizations etc.; and barangay residents who are basically selected to respond Farmer Household Economic Survey questionnaire, and
3. Farmer Household Economic Survey (200 HHs): It aims to collect agriculture and socio-economic characteristics of HHs in target barangays, by interviewing total 200 householders. The sampling method is intentional extraction method, which is based on the population by using pre-information.

6.2) Survey Design

Above surveys cover both MMIP I and MMIP II areas. In MMIP I area, the most important objective is to identify the output of the irrigation system upon completion. Hence, not only current characteristics but also changes after the commencement of the irrigation system were questioned. In addition, in order to examine the impact of YLTA, sample farmers in this MMIP I area were separately covered by enrollment for the technical assistances provided under YLTA.

On the other hand, in MMIP II area, irrigation water has not yet started coming. Therefore, the major objective of this area is to collect the baseline (initial) values in the target areas. These initial values are to be referred to setting the Operation Indicators and Effect Indicators which are the target

indicators with Project. In addition, expectations to the project are asked to clarify the need of the beneficiary farmer HHs.

Three Barangays were selected from Maridagao Service Area, considering respective IA's enrollment to YLTA, and then both YLTA farmers and non-YLTA farmers were equally selected to compare (10 samples each). On the other hand, 6 Barangays were selected from Lower Malitubog Service Area. In the LMSA, there is stage-wise difference, for example, in terms of progress of construction. Therefore, the Team finally selected 1 Barangay from western part of LMSA (red colored), 1 Barangay from central part of LMSA (pink colored), 1 Barangay from eastern part of LMSA (light green colored), and 3 Barangay from south-eastern part of LMSA (purple and light blue colored).

According to the ordinary Muslim custom of Mindanao, head of household is primary inherited by son, and thus the wife generally never becomes as householder. However, as per interviewers who visited the Barangays, in some ethnic-mixed Barangays, it is possible that a woman can be the household head. Through Barangay profiling, it was revealed that there were women-headed HHs in Ugalingan (about 30), Gli-Gli (about 27), and Punol (about 7). Aside from Punol, the Team selected 10 women-headed HHs each from the two Barangays (total 20 HHs). The location (yellow circle), name of Barangay, and the number of sampled farmer HHs by Barangay are summarized in Figure 2.1.18 and Table 2.1.12.




Figure 2.1.18 Location Map of Selected Barangays for Baseline Survey

Source: JICA Survey Team

The location (yellow circle), name of Barangay, and the number of sampled farmer HHs by Barangay are summarized in Figure 2.1.18 and Table 2.1.12.

Table 2.1.12 Name of Barangays and the Number of Sample Farmer Households (FHHs)

Irrigation Area	Name of Barangay	Municipality	Membership of IA	Number of Sample FHHs
Maridagao Service Area	1 Ugalingan/ General Luna	Carmen	Farmers who belongs IA of MRISIA Div.6 and received YLTA	10
			Farmers who have never received any TA	10
			HHs which headed by female	10
	2 Kibayao/ Kib-Ayao	Carmen	Farmers who belongs IA of KIPAN or NASGIA and received YLTA	10
			Farmers who have never received any TA	10
	3 Kilangan	Pagalungan	Farmers who belongs IA of Morning Light or KATINGKONGAN and received YLTA	10
Farmers who have never received any TA			10	
Lower Malitubog Service Area	4 Buliok	Pikit	Any Farmers	20
	5 Talitay	Pikit	Any Farmers	20
	6 Baguinged	Pikit	Any Farmers	20
	7 Gli-gli/Gligli	Pikit	Any Farmers	20
			HHs which headed by female	10
	8 Macabual	Pikit	Any Farmers	20
9 Punol	Pikit	Any Farmers	20	
Total				200

Source: JICA Survey Team

6.3) Basic Characteristics of Target Barangay

Basic Information and macro-level questions that are not suitable for household-level questionnaire were questioned in Barangay Profile to the Barangay Captains and other local key villagers. Figure 2.1.19 finds that the population in Kilangan is remarkably large, though the typical population in other Barangays is roughly 2,000 – 5,000 or approximately 700 – 1,000 HHs. Most of families belong to Muslim community, in fact, 5 out of 8 were pure-Muslim Barangays (100% of population were Muslim). The religious composition looks strongly correlated with ethnic groups; Figure 2.1.20 and Figure 2.1.21 easily find that the share of population who believes except for Islam such as Christianity is quite similar to that of ethnicity other than Maguindanaon (e.g. Cebuano, Ilocano).




Figure 2.1.19 Population of Target Barangays by Sex
Source: JICA Survey Team, Baseline Survey




Figure 2.1.20 Population Share of Target Barangays by Selected Religion
Source: JICA Survey Team, Baseline Survey

In every barangay, the population of farmer HHs is larger than non-farmer HHs. It is certain that farming is the primary livelihood in the Barangays. However, such villages belonging to Lower Malitubog Service Area (Ugalingan, Kibayao, Kilangan) which have always suffered from floods tend to have larger share of non-farmer HHs than three villages of Maridagao Service Area. Also, shares of peasant farmer / agriculture labor in Maridagao Service Area look higher than those of Lower Malitubog Service Area. Perhaps, arable land is more scarcity in the area because the number of HHs against population is relatively large.




Figure 2.1.21 Composition of Primary Ethnic Group
Source: JICA Survey Team




Figure 2.1.22 Composition of Employment in the Target Barangays
Source: JICA Survey Team

6.4) Arable Land per Farmer

The average cultivated land per sample 200 HHs is about 1.52 ha. Out of it, self-owned land accounts for 1.48 ha. It implies that farmland rental is not common in the area. Most of the farmers can be categorized as “small size farmer” cultivating 0.5 – 1 ha farmland. Further, 31 HHs (16%) are in fact “marginal farmers” who cultivate only less than 0.5 ha. On the other hand, 10 HHs (5%) can be

categorized “medium and large size farmer” who cultivate more than 4.5 ha. Figure 2.1.23 shows histogram segmented by land scale.




Figure 2.1.23 Histogram of Farmer HH Segmented by Farmland Size

Source: JICA Survey Team, Base Lien Survey

Table 2.1.13 shows cultivated area per farmer by crop and by irrigation access. For both irrigated / rain-fed lowlands, the major crops in the area are rice, coconuts, corn, and sugarcane. Crop intensity in irrigated lowland has already reached 200% and most of the farmers have introduced two-time cropping. On the other hand, crop intensity in rain-fed lowland is relatively low, only 102%.

Table 2.1.13 Cultivated Area of Lowland per FHHs by Crop and by Irrigation Access

Crops	Irrigated Land (Lowland)				Non-Irrigated Land (Lowland)			
	Rainy	Dry	Third	Total	Rainy	Dry	Third	Total
Rice	0.55	0.54	0.00	1.09	0.39	0.04	0.02	0.45
Coconut	0.00	0.00	0.00	0.00	0.02	0.01	0.01	0.04
Corn	0.02	0.02	0.01	0.05	0.04	0.01	0.01	0.06
Sugarcane	0.11	0.11	0.00	0.22	0.00	0.00	0.00	0.00
Others (e.g. rubber, mango)	0.00	0.01	0.00	0.01	0.00	0.00	0.00	0.00
[A] Total Cultivated Area (ha)	0.68	0.68	0.01	1.37	0.45	0.06	0.04	0.55
[B] Land Size (ha)	0.72	0.72	0.72	0.72	0.54	0.54	0.54	0.54
[A/B] Crop Intensity (%)	94.4%	94.4%	1.4%	190.3%	83.3%	11.1%	7.4%	101.9%

Source: JICA Survey Team, Base Lien Survey

6.5) Farmer’s Income

The average farmer household income is PhP120,914. Compared to official statistics collected by Philippines Statistic Authority (PSA) in 2015, the farmer household income is lower than the average of Region XII (198,438 Php), while it is larger than the average of ARMM (85,514 Php). That is to say, the average sample household income is not extremely higher nor lower compared to neighboring areas.

Divided by average household’s size 5.26, the average per capita income comes to PhP22,987. Looking at official regional poverty line estimated by PSA, the poverty line of Region XII in 2015 (latest updated) was PhP21,025, and that of ARMM in 2015 was PhP21,563. The average sample household income slightly exceeded to these thresholds. It should be noted that the comparison is not strictly applicable since it does not consider inflation and perhaps any other important factors else. Yet, it is no doubt that poverty reduction is one of the central agenda for the areas.




Figure 2.1.24 Shares of Farmer Household Income by Income

Source: JICA Survey Team, Base Lien Survey

Figure 2.1.24 shows share of farmer household income by income source. Cropping income accounts

for 57% of total household income, followed by migrant work (abroad) and remittance (14%), self-employed / cottage industry (10%), livestock selling and sub-products (7%), and fisheries and aquaculture (7%). There is a tendency that farmers in water sufficient area significantly depend on cropping income, while farmers who usually suffer from flood in rainy season relatively diversify their income into non-crop incomes such as fishery and aquaculture.

6.6) Issues on Farm Management

The Team asked about issues to be tackled to improve agriculture productivity/ farmer’s income that are summarized in Figure 2.1.25. The issues frequently answered were “Damage by pest and disease” and “Bad / poor transportation road to market / millers”, so those issues must have needs to be solved. In rain-fed areas, people tend to answer “Unstable Rainfall” and “Occurrence of Floods” as their major issues. On the other hand, in irrigated area farmers tend to answer, “water shortage of irrigation”. From these results, it seems that the proposed plan has certain validity to implement.




Figure 2.1.25 Recognized Issues on Farming & % of Farmers (Unit: %)
Source: JICA Survey Team, Base Line Survey

6.7) Evaluation of MMIP I and Expectation of MMIP II

Figure 2.1.26 shows evaluation of MMIP I project by local people. For a wide range of items from farming to security, most of the household heads (more than 70% to almost 100%) recognized “positive” or “very positive” impacts of MMIP I project, and therefore it can be concluded that the outcome of existing irrigation schemes are very much welcomed by the local people.




Figure 2.1.26 Evaluation of MMIP I Project & % of Farmers (Unit: %)
Source: JICA Survey Team, Base Line Survey




Figure 2.1.27 Expectation of MMIP II Project and Percentage of Farmers (Unit: %)
Source: JICA Survey Team, Base Line Survey

On the other hand, the expectations to MMIP II project is summarized in Figure 2.1.27, and surprisingly only 17 HHs out of the 134 sample HHs in the MMIP II area were aware of the project. The information dissemination should be strengthened to deepen the understanding of the beneficiary farmer HHs. Among others, the expectation in the yield increase is the highest, while the expectation in crop diversification towards, e.g., rice is the lowest.

6.8) Women Headed-Households

Referring to Barangay Profile, it is confirmed that there are HHs headed by female at least 30 HHs in Ugalingan, 27 in Gli-Gli, and 7 in Punol. In order to clarify socio-economic characteristics of women headed HHs, 20 women headed HHs are additionally surveyed.

The results of income comparison between male and female headed HHs are summarized in Figure 2.1.28. Although there is no significant difference between two groups in the total income amounts, the income structures seem to be different. The Female headed household’s incomes are mainly composed of crop income (40.4% of total income), livestock selling and sub products (21.5%), migrant work abroad- /remittance (17.2%), migrant work within the country (7.8%), and government cash transfer (6.6%).




Figure 2.1.28. Income Comparison between Male and Female Headed HHs

Source: JICA Survey Team, Base Lien Survey

6.9) Observed Effect from Technical Assistance Projects

The sample farmer HHs in the Maridagao Service Area can be divided into two groups: 1) farmer HHs that belong to an IA and benefited from technical assistance (TA) projects; and 2) farmer HHs that have never benefited from any TA projects (see Table 2.1.14).

Since there is no baseline data on the initial conditions for each group farmers, the results of the comparison of the current status between the two groups should be taken as reference.

In the comparison of the yields per hectare, there is a slight difference. Those householders that have ever received TA yield 3.48 tons /ha in irrigated rice fields while those HHs that have never received TA non-recipient yield 3.30 tons/ha.

Figure 2.1.29 compares income and income structure of the two groups. TA-recipient farmers can earn cropping income 150,907 peso per FHH that is larger than the




Figure 2.1.29. Income Comparison between TA Recipient and Non-Recipient

Source: JICA Survey Team, Base Lien Survey

non-recipient farmers 134,741 peso per FHH.

Table 2.1.14 Sample Size Segmented by TA Recipient and Non-Recipient

Category	Name of Service Area	Barangay	Enrollment of IA	Sample Size
TA Recipient Group	MSA	Three Barangays belong to MSA	farmers who belongs to any IA and benefited by any technical assistance project	39
Non-Recipient Group	Ditto	Ditto	Farmers never benefited from any TA	31
(Reference-Group)	(LMSA)	(Five Barangays belong to LMSA)	Ditto	(130)
Total				(200)

Source: JICA Survey Team

2.1.7 Social and Cultural Features

1) Ethnicity and Religion

The population of Mindanao can be classified into Christian, Muslims and Lumads, depending on their religion, and in general there still remain divisions among them created and reinforced by their history. According to the National Commission for Culture and the Arts (NCCA), Lumad are the general term for 15 Indigenous Peoples (IPs) in Mindanao, who are neither Muslims nor Christians and they are: *Subanen, B'laan, Mandaya, Higaonon, Banwaon, Talaandig, Ubo, Manobo, T'boli, Tiruray, Bagobo, Tagakaolo, Dibabawon, Manguangan and Mansaka*.

Although the Muslim population or Moro peoples are usually not recognized as IPs in Mindanao, some of the Moro ethnic groups are listed by National Commission on Indigenous People (NCIP) in the IP list. There are seven major Moro groups whose presence in the Mindanao-Sulu area is confirmed and they are: *Maranaw, Maguindanao, Tausug, Yakan, Samal, Iranun and Kalagan*.

The proportion of Christian, Muslims and Lumads to the total population seems to have been basically maintained after the implementation of massive settlement of Christians from Luzon and Visayas to Mindanao. According to Reyes et.al (2016), the proportion of Non-muslim IPs to the total population of Mindanao has increased by nearly 5% between 2000 and 2010, while that of Christians/others has decreased by nearly 6% during the same period. The total population of Mindanao has increased during the same period by nearly 24%.




Figure 2.1.30 Ethnic proportion of the population of Mindanao

Source: Reyes et.al. 2016. "Inequality Patterns among ethnic groups in the Philippines"⁸

⁸ Reyes and her two co-authors analyzed and compared by themselves the data of the Population and Housing Census of the Philippines Statistics Authority for 2000 and 2010.

According to Cariño (2012), in Cotabato and Maguindanao Provinces where the entire MMIP site is located, the presence of eight IP groups is confirmed as shown in Table 2.1.15 right. Tiruray and B'laan are the common groups in both the provinces, and although they are not Muslims, they live in Maguindanao Province which is under the Autonomous Region in Muslim Mindanao (ARMM). However, at the same time, the presence of Moro groups has not been confirmed in Cotabato province, and it can be said that the people are in general living separately depending on their religion.

Table 2.1.15 IP in Cotabato & Maguindanao P.

Cotabato Province	Maguindanao Province
Tiruray	
B'laan	
Aromanon	Maguindanao
Bagobo	Iranon
Ubo Manobo	
Karintik	

Source: Cariño. 2012. "Country Technical Notes on Indigenous Peoples' Issues: REPUBLIC OF THE PHILIPPINES"

2) History of Mindanao

Islam arrived at Sulu area in the last quarter of the 13th Century through Muslim traders, and it gradually took root in the area. The Sulu Sultanate was established in 1451, followed by the Mindanao Sultanate in the 1610s. However, there remained some tribes who did not convert into Muslims.

In 1565, the Spanish colonization of the Philippines started and the Jesuit missions also reached to Mindanao. However, Spaniards faced the resistance from some Muslim and non-Muslim tribes against Spanish ruling and Christianity. Spanish people named those Muslim tribes as Moros after Moors from whom they had recovered their land by force by the end of the 15th Century. Between the 16th and the 19th Centuries there were six wars repeated between Moros and Spaniards. It is said that a sense of hostility or discrimination against Moro people had been nurtured among those Christian Filipinos through this period.

With the Treaty of Paris of 1898, Spain ceded the Philippines to the United States, and Americans also faced resistance of Moros against American rule, yet by 1913 the United States of America unified the Philippines as one country by force. As consequence, Lumads and Moros were grouped under a tribal system, and they also started to lose their lands due to the introduction of the land registration system.

After the independence of the Philippines from the American rule in 1946, massive investment in Mindanao such as plantations of Dole and Del Monte, etc. took place, and a great deal of Lumad lands in Bukidnon-Davao area were given to foreign agribusiness firms. By experiencing development projects that made Lumads displaced from their homeland, such as the hydroelectric project in Mt. Apo, concerns of the Lumads people on their land were raised, and this led to the legislation for the protection of ancestral lands, and in the form of the 1997 Indigenous People's Rights Act (IPRA)⁹.

The American rule and the post-independence Philippines government pushed mass migration of Filipino Christian settlers from the Luzon and Visayas island groups to Mindanao. This resulted in the marginalization of Moros and Lumads in the demography in Mindanao, as the proportion of Moros to the total population of Mindanao fell from 76% in 1903 to 22% in 2010. The first settler to Cotabato province came mainly from Cebu to Pikit in as early as 1913, and from Pikit their children moved west-bound to Midsayap and east-bound to Kidawapan.

There is a study which revealed that more than a half of Mindanaon believes that Muslims are probably terrorists and/or extremists (56%) and are prone to run amok (54%)¹⁰, and this may be attributed to repeated wars and violent incidences, in which armed groups composed of members of

⁹ ULINDANG, Faina. 2015. LUMAD in Mindanao. Available at: <http://ncca.gov.ph/subcommissions/subcommission-on-cultural-heritagesch/historical-research/lumad-in-mindanao/> [Accessed on June 29, 2017]

¹⁰ MONSOD, Toby. 2005. "The bias against Muslims: A creeping perception"

Moro groups have been involved. The sense of historical injustice and disadvantages as consequences motivated some Moro people to fight through the 1950s and the 1960s, and it led to the official formation of the Moro National Liberation Front (MNLF) in 1973.

Following increased violent incidences caused by MNLF, the martial law was declared by the then President on September 21, 1972, and the Mindanao Civil War got fierce. It is told that more than 160,000 were killed over the following decades. The more radical Moro Islamic Liberation Front (MILF) formally split from the MNLF in 1977, and much later, Abu Sayyaf, which seeks a complete independence for Moros, also split from MNLF in 1991.

After more than two decades of conflict period, in 1996, the Government and MNLF signed an agreement and reached a ceasefire in 1997. However, the agreement was not fully implemented, as agreed assistance from the government was not fully provided and the persistence of corruption and violence was seen on both sides. In 2000, President Estrada launched an all-out war against MILF, and it went back to the war again.

The creation of an autonomous region in Muslim Mindanao was enshrined in the 1987 Constitution, and with the enactment of the Republic Act No. 6734 in 1989, also known as Organic Act for the Autonomous Region in Muslim Mindanao, the Autonomous Region in Muslim Mindanao (ARMM) was created with the 4 provinces of Lanao del Sur, Maguindanao, Sulu and Tawi-Tawi. Cotabato Province was to be also included into ARMM, but the Province rejected to be included into ARMM by plebiscite. Later, with the enactment of Republic Act 9054 in 2001, the coverage of ARMM was expanded and it is now composed of the provinces of Basilan, Lanao del Sur, Maguindanao, Sulu and Tawi-Tawi, and the cities of Marawi and Lamitan.

On the 27th of March 2014, through the brokering efforts by foreign countries, such as Malaysia and Japan, MILF and the Government of the Philippines signed the Comprehensive Agreement on the Bangsamoro (CAB), and both MILF and the Government came to a ceasefire. Under CAB, ARMM has been experiencing the transition process toward reinforced autonomy for Moro peoples in the Bangsamoro Core Territory.

The first Bangsamoro Transition Commission (BTC) came up with a Bangsamoro Basic Law (BBL) which stipulates the new political and administrative structure, but it was not passed by Congress, affected by the clash between elite police forces and Moro rebels in Mamasapano, Maguindanao province in 2015. The incumbent President, Rodrigo Duterte, established the new BTC in February 2017 and the new BTC members came up with the new BBL. New BBL was passed by Congress at the end of May 2018 and it is expected that new BBL will be effective with the signing of the President by July 2018. Subsequently, the referendum will be held during 2018 and Bangsamoro transitional government will be established in 2019, if all goes smoothly.

2.1.8 Access to Public Services and Local Governance

1) Impact of the Project in Public Services and Local Governance

The Ex-Post Evaluation of MMIP I conducted from 2014 to 2015 indicated that there were some positive impacts of the project in public service delivery and local governance. For instance, more children going to school, easier access to health services, potable water and social welfare services were recognized by beneficiaries of the project as impact of the access roads constructed under MMIP I. In addition, beneficiaries saw MMIP I had contributed to an increase in household income and creation of employment opportunities as shown in Figure 2.1.31.




Figure 2.1.31 Positive Impact of MMIP I Confirmed at the Ex-post Evaluation

Source: JICA. 2015. Ex-post Evaluation Report




Figure 2.1.32 Degree of Beneficiaries' Satisfaction at the Ex-post Evaluation

Source: JICA. 2015. Ex-post Evaluation Report

Beneficiaries, moreover, expressed their satisfaction with irrigation services provided upon the completion of the construction works of MMIP I as shown in Figure 2.1.32. Such satisfaction among beneficiaries may have attributed to an increase in trust of the local people in the government institutions and enhanced peace and order. It was reported that there were some beneficiaries who had been combatants but stopped being engaged in activities of armed group for farming, since they saw the irrigated agriculture was promising and would satisfy their needs of livelihood.

2) Literature Review

Literatures can illustrate that public services have not yet effectively reached out to the population in the beneficiary areas of the entire MMIP I and II area. For example, according to the Philippines Statistics Authority (PSA)¹¹, Maguindanao Province took the 5th place (59.4%) and Cotabato Province took the 15th place (48.9%) among the eighty-one provinces in the Country in terms of the poverty incidence as of the first semester of 2015.

The Human Development Index (HDI) of both Cotabato and Maguindanao Provinces and the entire Country experienced a period of stagnation between 2003 and 2006. Yet, if we compare the HDI value between 2000 and 2009, both the Province as well as the entire country marked a slight improvement (Figure 2.1.33.). However, both provinces still lagged behind from the national average, and the value of HDI of Maguindanao Province has been always worse than that of Cotabato province.




Figure 2.1.33 Improved HD Indices of Cotabato and Maguindanao Provinces

According to the Bangsamoro Development Plan which is recently developed by the Bangsamoro Development Agency upon the signing of the Comprehensive Peace Agreement between MILF and

¹¹ PSA 2016; 2015 First Semester Official Poverty Statistics

the Government of the Philippines, the ARMM provinces, including Maguindanao, have been ranked among those worst provinces in major social indicators, especially in education, health and WASH (Water, Sanitation and Hygiene).

The Development Plan admits that “the highly inadequate provision of social services is also a major factor in the decline in the overall welfare of the population, which disproportionately affects poor HHs”. Table 2.1.16 below shows the comparison of Region XII and ARMM in the situation of the provision of safe water & sanitary toilet. The situation of the access to safe water and sanitary toilet by HHs in Cotabato province is slightly better than the average of the entire Region XII.

Table 2.1.16 Comparison of the Access to Safe Water and Sanitary Toilet in Region XII and ARMM

Area	No. of HH	HH with safe water supply		HH with Sanitary Toilet		Source
		No.	%	No.	%	
ARMM	N/A	N/A	36.60%	N/A	22.50%	Bangsamoro Development Agency. 2015. Bangsamoro Development Plan (as of 2012)
Region XII	945,190	862,040	91.20%	769,435	81.41%	DOH. 2016. FHSIS Annual Report
Cotabato Province	273,166	260,886	95.50%	224,571	82.21%	DOH. 2015. FHSIS Annual Report

Source: Bangsamoro Development Agency, DOH 2015 FHSIS Annual Report

It should be noted that in ARMM, the ARMM Office is the sole public service provider, while in other Regions, the services are provided by the Local Government Units in conjunction with the central government. The responsibility of service provision was together with necessary financial resources devolved by the central government to ARMM.




Figure 2.1.34 Government Structure: Differences between ARMM and Other Regional Offices

Source: Drawn by Survey Team based on: Sakuma. 2011. “Status quo and challenges of decentralization in the Philippines”

According to the office of ARMM, the total budget of ARMM has been almost doubled from 2010 to 2014 as seen in Figure 2.1.35 and it can be expected that more population of ARMM has access to basic public services.

Because of the devolution of some functions of the central government, including public service delivery of different sectors, to ARMM, the central government makes budget transfer to the ARMM, which is the portion originally allocated to the government agencies of different sectors as shown in Figure 2.1.36




Figure 2.1.35 Budget of ARMM b/t 2010 and 2014 (Unit: PHP)

Source: ARMM. Available at :

<https://armm.gov.ph/discover-armm/infographics/>

[Accessed on June 28, 2017]

below. The total transfers from different government agencies amounted to almost PHP 10.3 billion and it is equivalent to almost a half of the total budget of ARMM for the same year.




Figure 2.1.36 2014 Budget allocated to ARMM (Unit: PHP)

Source: ARMM. Available at : <https://armm.gov.ph/discover-armm/infographics/>

Table 2.1.17 Average Years of Schooling in the Philippines & Mindanao

Group	2000	2010
Philippines		
Non-Muslim	5.3	7.8
Muslim	5.0	6.4
Christian/Others	7.2	7.4
Mindanao		
Non-Muslim	3.9	5.1
Muslim	4.9	5.3
Christian/Others	6.7	7.5

Source: Reyes et.al. 2016. "Inequality Patterns among ethnic groups in the Philippines"

On the other hand, Reyes et.al.¹² revealed that they can see inequalities in the public service delivery among the ethnic/ religious groups and within such groups in Mindanao. They compared the situation of schooling, literacy and access to water and sanitation among the Non-Muslim Indigenous Peoples, Muslims and Christians plus others. As seen in Table 2.1.17, Figure 2.1.37 and Figure 2.1.38, inequality among the three groups mentioned above in Mindanao is more significant in schooling, followed by access to water, access to sanitation and literacy.




Figure 2.1.37 Inequality among Different Groups in Literacy Rate

Source: Reyes et.al. 2016. "Inequality Patterns among ethnic groups in the Philippines"




Figure 2.1.38 Inequality among Different Groups in Access to Safe Water & Sanitary Toilet

Source: Reyes et.al. 2016. "Inequality Patterns among ethnic groups in the Philippines"

¹² Reyes et.al. 2016. "Inequality Patterns among ethnic groups in the Philippines"

2.2 Liguasan Marsh

2.2.1 Location and Size of the Marsh

Liguasan marsh is the largest marsh in the Philippines. Its size has been reported to be 220,000 to 288,000 ha with 40 km length and 20 km width along Pulangi River (or Mindanao River / Rio Grande). It spans the provinces of Sultan Kudarat and Cotabato in the Central Mindanao and Maguindanao in the Autonomous Region in Muslim Mindanao (ARMM). It is reported that it can serve as natural filters and the flood control for the plains of Cotabato¹ including Cotabato city.



Figure 2.2.1 Marsh Area in Mindanao Basin

Source: JICA Survey Team

In view of hydro-geomorphology, this large area is divided into three adjoining marshes²; namely, 1) Liguasan marsh, 2) Libungan marsh and 3) Ebpanan marsh taking into account their water sources and dominant tributaries as flows:

- 1) Liguasan Marsh constitutes the upper arc of Mindanao river system basin (so-called Cotabato basin) and its surface water is supplied from main course of Pulangi river and its tributaries of Maridagao, Kabacan, Allah rivers and so on. The area covers the municipalities of Pikit, Pagalungan, Datu Montawal, Kabacan, Matalam, M'lang, upper Cotabato that Tulunan, Datu Paglas, Datu Paglat, Sultan sa Barongis, Rajah Buayan, Mamasapano, Datu Salibo and Datu Piang.
- 2) Libungan Marsh occupies the middle section of Cotabato basin and has own water body supplied by Libungan river as well as Pulangi river, which includes the municipalities of Pigcawayan, Libungan, Midsayap, Upper Kabuntalan and Talayan.

¹ 4th National Report to the Convention on Biological Diversity 2009

² The extent area of '220,000 to 288,000 ha with 40 km length and 20 km width' means the 3 areas combined.

- 3) Ebpanan Marsh is the lower part of Cotabato basin stretching from the lower reach of Allah river and adjoining small streams and covers the areas of Lower Kabuntalan, Dinaig, Sultan Kudarat and Cotabato city.

The three said marshes naturally catch flood waters when the major Pulangi river is swollen due to heavy rains as much as 3,200 mm/year as an average area rainfall in the catchment. From Datu Piang located at Ebpanan marsh, all tributaries turn into single channel i.e. Pulangi river or Mindanao river which then diverts river flow again at the upper Cotabato City into two rivers; namely, Mindanao River and Tamontaka River, and finally the two rivers pour into Illana Bay.

The Project area is located at a middle part facing north-eastern side of Liguasan marsh, which is connected with a narrow channel to Libungan marsh especially in dry season. However, in the event of flooding, marsh water is dammed-up due to the narrow channel being unable to flow out the flood water towards downstream, and thus raised water spreads over or back into the marsh area. The inundated water is then gradually discharged to the downstream Libungan marsh and further to Ebpanan marsh for long time period.

On the other hand, among the surrounding area of the marsh, forests had been cleared without much provisions of reforestation. Logging has welcomed the settlers and remaining forests have been further cut for the reclamation for agricultural use. In addition, a man-made channel from Pulangi and Kabacan river to Liguasan Marsh was constructed in Tungol in early 1980s and it redirected the river water into new agriculture land which was developed at the foreland of the original marshy area (see Figure 2.2.2).




Figure 2.2.2 Diversion Channel and the Project Area

Source: JICA Survey Team




Figure 2.2.3 Location and Size of Liguasan Marsh (as max. extent of water cover)

Source: JICA Survey Team

As for the historical change around the marsh, the unpredictable water extent of Liguasan marsh is traceable with temporal 16-day interval satellite data by defining on-time extents. In Figure 2.2.3, the maximum water extent in 32 years from 1984 to 2015 is illustrated as composite image of historical extents. With the image analysis, the maximum surface water area of Liguasan marsh is estimated at 15,609 ha, which is less than 7 % of the reported whole marsh area of 220,000 to 280,000 ha. The extent of surface water will be regarded as an influencing area to the MMIP II area, especially Lower Malitubog Service Area (LMSA), and its related facilities to be constructed.

2.2.2 Ecology of the Marsh

Liguasan Marsh is a wetland ecosystem, which performs significant ecological functions. The presence of Liguasan Marsh in fact reduces the impact of flood in the Cotabato River Basin. During high flood, the marsh absorbs floodwater as a natural flood detention reservoir. The marsh also functions as natural filter. Sediment load carried by the floods are deposited and filtered in the Marsh, thus maintaining the stability of the river system. Plants in the marsh absorb excess nitrogen and phosphorous from sewerage and other pollution causing effluents.

The plant species that are native to the marsh, and of important economic value, are the sago palm (*Metroxylon*), tikog (*Fimbristylis littoratis*) and baino (*Nelumbo nucifera*). Sago palm is the source of sago flour tapioca gel and the tikog is a material for mats. The baino fruit is sold in Maguindanao town markets. The marsh has plenty of floating, emergent, submerged and microscopic floral wonders. Common floating vegetation is *kangkong*, *water hyacinths*, *kiapo* and *water lily*. Submerged vegetation is represented by *digman* or *hydrilla* and *chara*, among any others.

The marsh is identified as Important Bird Area (IBA) by the Bird Life International³. The criteria for the selection as IBA are "A1: *The site is known or thought regularly to hold significant numbers of a globally threatened species*" and "A4iii: *The site is known or thought to hold, on a regular basis, at least 20,000 water birds, or at least 10,000 pairs of seabird, of one or more species.*" In addition, 128 sites of Key Biodiversity Area (KBA) have been identified in the Philippines, and the Liguasan Marsh is registered as a KBA also⁴. However, restriction of development or protection of the Liguasan Marsh is not legally stipulated in the Philippines. It is noted that the marsh is not registered as a Ramsar Convention on Wetlands site.

Liguasan Marsh has a rich biodiversity, and it is known as a home of endemic species of flora and fauna and it provides feeding ground for various migratory birds. The numbers of species of fish, amphibian, reptile, bird and mammal, which range in the marsh, are 33, 7, 12, 53 and 11 (see Appendix VIII). A large reptile, crocodile (*Crocodylus porosus*) or Philippine Duck (*Anas luzonica*) have been identified in the marsh. Of them, some species are endangered according to the IUCN red list, 4 species of "Near Threatened" and 6 species of "Vulnerable", as they are shown in the following table.

Table 2.2.1 Endangered Species in Liguasan Marsh

Class	English Name	Scientific Name	IUCN Category
Fish	Tilapia Mozambique	<i>Oreochromis mossambicus</i>	Near Threatened
	Celebes eel	<i>Anguilla celebesensis</i>	Near Threatened
	Eel	<i>Anguilla spengeli</i>	Near Threatened
	Common Carp	<i>Cyprinus carpio</i>	Vulnerable
Amphibian	None	None	None
Reptile	Malay Pond Turtle	<i>Cuora amboinensis</i>	Vulnerable

³ Bird Life International: An environmental NGO for bird conservation, which was established in 1922 in the UK, and the NGO has 122 partners worldwide, one per country/region.

⁴ Source: "Priority Sites for Conservation in the Philippines, Key Biodiversity Areas", Conservation International Philippines

Class	English Name	Scientific Name	IUCN Category
	Sailfin Lizards	<i>Hydrosaurus postulosus</i>	Vulnerable
Bird	Philippine Duck	<i>Anas luzonica</i>	Vulnerable
Mammal	Philippine Tarsier	<i>Tarsius syrichta</i>	Near threatened
	Philippine Wild Pig	<i>Sus philippensis</i>	Vulnerable
	Philippine Deer	<i>Cervus marianus</i>	Vulnerable

Note: **Vulnerable:** it is considered to be facing a high risk of extinction in the wild (Risk is more than that of **Near Threatened**)

Near Threatened: it does not qualify for **Critically Endangered**, **Endangered** or **Vulnerable** now, but is close to qualifying for or is likely to qualify for a threatened category in the near future.

Source: National Economic and Development Authority Region XII. 1998. Liguasan Marsh Development Master Plan 1999 - 2025 Volume III, Database, Project Profiles, and Annexes.

2.2.3 People Living on the Marsh

1) Overview

Liguasan Marsh is actually a conglomeration of three marshes: Liguasan, Libungan and Ebpanan. It lies in the basin of the Mindanao river in south-central Mindanao spanning the provinces of Sultan Kudarat and Cotabato in Region XII, and the Maguindanao province in ARMM. It is a natural and ecological resource rich area, and for some Lumad people is the place of origin of lives. Not only fauna and flora, but also people are living within the Liguasan marsh area, despite frequent flooding attributing to its geographical feature.

The “Liguasan Marsh Development Master Plan 1999-2025” prepared by the National Economic and Development Authority Regional Office XII estimated the total population in the Liguasan Marsh at 258,486 with 48,577 families (5.32 persons/family), based on the results of the 1995 Census of Population. The said Master Plan was developed to cover the Marsh spreading over 191 Barangays of 19 Municipalities and 1 City over 3 Provinces, namely, Cotabato and Sultan Kudarat Provinces from Region XII and Maguindanao Province from ARMM.

Based on the results of the 2015 Census of Population of the Philippines Statistics Authority (PSA), the population of the Liguasan Marsh today can be estimated at almost 582,000⁵. It is noted that in the estimation, proportional area ratio between the Liguasan marsh (280,000 ha) and that of 22 municipalities and one city as shown in Table 2.2.2 below were applied.

Table 2.2.2 Overview of the Municipalities and City in the Liguasan Marsh

No.	Province/Region	Municipality & City	Population	Land Area (ha)	Population Density (persons/km ²)
1	COTABATO/ REGION XII	KABACAN	89,161	44,809	198.98
2		LIBUNGAN	48,768	17,250	282.71
3		MATALAM	79,361	47,600	166.72
4		MIDSAYAP	151,684	29,042	522.29
5		M'LANG	95,070	31,213	304.58
6		PIGKAWAYAN	66,796	34,011	196.40
7		PIKIT	154,441	60,461	255.44
8		TULUNAN	56,513	34,308	164.72
9		COTABATO CITY	299,438	17,600	1,701.35
10	MAGUINDANAO/ ARMM	DATU PAGLAS	28,387	13,210	214.89
11		DATU PIANG	25,600	30,297	84.50
12		DATU ODIN SINSUAT (DINAIG)	99,210	46,180	214.83
13		PAGALUNGAN	39,653	89,876	44.12
14		SULTAN KUDARAT (NULING)	95,201	71,291	133.54

⁵ As the Team was unable to obtain reliable secondary data on recent population in the Liguasan Marsh, estimation was done. Accordingly, the total population and the total land area of the 22 Municipalities and 1 City where the Liguasan Marsh is situated are 1,538,387 and 740,316ha, respectively, according to the 2015 Population Census conducted by the Philippines Statistics Authority. Assuming the total area of the Marsh as 280,000ha, the Marsh occupies almost 37.82% of the total land area of the said 22 Municipalities and 1 City. Applying this proportion of 37.82% to the total population of 1,538,387, we came to estimate the today's population of the Marsh at 581,844.

No.	Province/Region	Municipality & City	Population	Land Area (ha)	Population Density (persons/km ²)
15		SULTAN SA BARONGIS (LAMBAYONG)	22,425	29,130	76.98
16		KABUNTALAN (TUMBAO)	17,276	37,108	46.56
17		TALAYAN	30,032	14,384	208.79
18		MAMASAPANO	24,800	8,531	290.70
19		PAGAGAWAN	34,820	46,110	75.52
20		PAGLAT	15,920	17,774	89.57
21		RAJAH BUAYAN	23,652	7,198	328.59
22		NORTHERN KABUNTALAN	25,232	10,677	236.32
23		DATU SALIBO	14,947	2,256	663.54
TOTAL			1,538,387	740,316	207.80
TOTAL excluding Cotabato city			1,238,949	722,716	171.43

Source: PSA. 2015 Census of Population

The average population density among the 22 Municipalities (except for Cotabato City) is as high as 171 persons/km², although the population density varies from 44 persons/km² in Pagalungan Municipality, Maguindanao Province to 522 persons/km² in Midsayap Municipality, Cotabato Province. Such a relatively high population density may imply that many people living in the Liguasan Marsh may know how to cope with or utilize impact of frequent flooding.

2) Livelihoods

Inland fisheries activities are popular in Liguasan Marsh and gill-nets are the common tool to be utilized by local population to catch fish, such as tilapia, carp, mudfish, freshwater goby, and freshwater shrimp⁶. Other than the marsh areas, flat lowland is already used for paddy (palay) cultivation, especially during the dry seasons. The impact of inland fisheries and agriculture on household income in this area has been confirmed by a household economic survey under this JICA survey (see 2.1.6 Regional and Barangay (Household) Economies).

The economic survey had covered total 9 Barangays, of which 2 Barangays e.g. Buliok and Talitay are located in most east-southern parts of LMSA where the livelihood may be similar to that of the people living in and around Liguasan Marsh. Figure 2.2.4 summarizes the percentage of income share by means of source. As is shown, what comes first is cropping with 33%, followed by self-employed/ cottage industry (27%), migrant work (19%) and then fisheries and aquaculture with 12%.




Figure 2.2.4 Income Source for Buliok and Talitay Barangays

Source: Household Economic Survey (JICA Team)

On the other hand, a high potential of the existence of some mining resource in the Liguasan Marsh has drawn attention of some people. It has been reported that there is a natural gas reserve in Maguindanao province⁷, although it has not been fully explored yet, since the last known exploration work was done in 1997, by the Malaysian petroleum giant Petronas Carigali and the Philippine National Oil Company. It is also said that 108,000,000 MT coal deposits could exist in the same province⁸. If feasibility studies are conducted and economic feasibility in the exploitation of such natural resources is confirmed, it will surely affect the regional economy.

⁶ RECS International Inc. et. al. 2016. Final Report, Development Plan for the Bangsamoro, Comprehensive Capacity Development Project for the Bangsamoro.

⁷ Idem.

⁸ Bangsamoro Development Agency. 2015. Bangsamoro Development Plan.

2.3 Agriculture and Extension Services in the Project Area

2.3.1 Agricultural Land Use and Soils

Comprehensive information about crop production, such as planted/harvested area and production of major crops, is not available in the project area. It is, therefore, considered that a statistical data of crop production in Pikit Municipality could be utilized as proxy data on the crop production in the project area with the following reasons:

- ✓ While the project area spreads over 56 Barangays, 39 Barangays among them are located within the Pikit Municipality;
- ✓ While there are a total of 42 Barangays in the Pikit Municipality, 39 Barangays among them are located in the project area,
- ✓ As indicated in Figure 2.3.1, most of the MMIP area falls within the jurisdiction of the Municipality, except the Pagalungan Service Area located in Pagalungan Municipality and the Maridagao Service Area in Carmen, Kabacan/ Datu Montawal and Pagalungan Municipalities.




Figure 2.3.1 Pikit Municipality and MMIP Area

Source: UNOCHA, JICA Survey Team

Table 2.3.1 Crop Production in Pikit Municipality (Average between 2014 and 2016)

No	Crop	Harvested Area		Yield (ton/ha)	Production (ton)
		(ha)	(%)		
1	Paddy, irrigated	1,936.4	9.4	4.5	8,772.6
2	Paddy, rain-fed	3,986.3	19.4	3.5	14,113.4
	Paddy, total	5,922.7	28.8	3.9	22,886.0
3	Corn, yellow	1,209.0	5.9	4.2	5,127.1
4	Corn, white	6,184.6	30.0	3.9	23,925.7
	Corn, total	7,393.6	35.9	3.9¹	29,052.8
5	Root crops	76.4	0.4	-	-
6	Mung Bean	556.8	2.7	0.8	445.4
7	Squash	180.2	0.9	2.0	360.4
8	Bitter Gourd	65.3	0.3	3.3	167.0
9	Egg Plant	68.6	0.3	3.0	205.8
10	Miscellaneous vegetables	82.4	0.4	-	-
11	Sugarcane	196.8	1.0	48.0	9,446.4
	Root, vegetables, etc.	1,226.5	6.0	-	-
12	Coconut	4,684.3	22.7	3.6	16,863.5
13	Mango	820.6	4.0	2.5	2,051.5
14	Oil Palm	206.9	1.0	24.0	4,965.6
15	Rubber	109.8	0.5	2.4	263.5
16	Banana	96.0	0.5	14.5	1,392.0
17	Miscellaneous fruits	136.3	0.7	-	-
	Fruits & tree crops, total	6,053.9	29.4	-	-
	Total	20,596.7	100.0	-	-

Source: Office of the Provincial Agronomist, Cotabato Province

Table 2.3.1 shows the production of major crops in Pikit Municipality. Maize and paddy are the two leading crops planted terms of the harvested area which accounts to 65% of the total harvested area among the major crops. Coconut comes third as the most important crop cultivated in the area. The three occupy as much as 87% of the total harvested area. The other crops such as root crops, pulses, vegetables, etc. accounts for only 6% of the total area, and mung-bean, squash, eggplant, bitter-gourd

¹ This shows very high productivity of corn, for the both of white corn and yellow corn, in the area comparing to the statistical data of the Philippine Statistics Authority. An additional verification may be necessary.

and sugarcane are grown to only some extent in the area.

Corn exceeds paddy in terms of planted area by 1,472 ha. It is also interesting that the area of white corn is more than 5 times of the area of yellow corn, though the condition is in the opposite trend in Cotabato Province to which Pikit Municipality belongs. Cropping in Pikit Municipality could be influenced by adjacent areas in ARMM where white corn is widely grown. White corn is mainly consumed as food, while yellow corn is for animal feed in the Philippines.

In addition, the Christian population of Pikit, who are mainly immigrants from the Visayas region, particularly from the corn-eating province of Cebu. White corn is also likely sold at higher price as its main markets are found in the Visayas.




Figure 2.3.2 Share of Harvested Area

Source: Provincial Agronomist

Coconut is fairly dominant among perennial crops in terms of harvested area, which is 4,684 ha in total, sharing 23% of the overall area. On the other hand, oil palm, rubber and banana, which are suitable for plantation farming and famous production in Mindanao, remain very weak in this area in terms of the harvested area. In fact, the harvested areas of the oil palm, rubber and banana share only 1.0%, 0.5%, and 0.5% respectively.

It is assumed that the majority of farmers depend on subsistence farming by producing mainly staple food such as rice and corn, and may earn limited cash income from surplus cereals. In addition to the surplus cereals, coconut production, which shares 23% of the crop area, may supplement the cash income to a certain extent, and further to some extent, other fruits and seasonal farm-labor works may contribute to cash income. Off-farm works may be an important cash income source for many farmers.

The crops presented in the previous table are grown on soils summarized in Table 2.3.2 showing soil types in the relevant 5 municipalities such as Carmen, Pikit, Aleosan, Datu Montawal and Pagalungan. Kabacan, Aroman and Hydrosol are major soil types in the 5 municipalities. Kabacan and Hydrosol including Kidapawan could be dominant soil types in alluvial plain where farming lands are widely developed in the area, as Aroman soils are formed in hilly to mountainous landscape such as in Carmen.

Table 2.3.2 Soil Types in 5 Municipalities in the Project Area

Soil Type	Municipality										Total	
	Carmen		Pikit		Aleosan		D. Montawal		Pagalungan			
	(ha)	(%)	(ha)	(%)	(ha)	(%)	(ha)	(%)	(ha)	(%)	(ha)	(%)
Kabacan	25,865	23.3	36,829	60.9	1,520	6.2	39,848	86.4	12,641	14.1	116,703	35.2
Aroman	51,335	46.2	2,431	4.0	1,440	5.9	0	0.0	0	0.0	55,206	16.6
Tacloban	7,683	6.9	0	0.0	0	0.0	0	0.0	0	0.0	7,683	2.3
Faraon	21,940	19.8	0	0.0	2,240	9.2	0	0.0	0	0.0	24,180	7.3
Kidapawan	4,229	3.8	0	0.0	0	0.0	0	0.0	0	0.0	4,229	1.3
Hydrosol	0	0.0	10,714	17.7	0	0.0	6,262	13.6	64,240	71.5	81,216	24.5
Kudarangan	0	0.0	10,487	17.3	19,250	78.7	0	0.0	0	0.0	29,737	9.0
Clay Loam	0	0.0	0	0.0	0	0.0	0	0.0	12,995	14.5	12,995	3.9
Total	111,052	100.0	60,461	100.0	24,450	100.0	46,110	100.0	89,876	100.0	331,949	100.0

Source: 5 LGUs

Remark: In fact, "Clay Loam" is defined as one of soil texture not soil type. Since data obtained from Municipality of Pagalungan also categorized it as soil type, the table also includes it into the soil type.

The nature of the major soil types are summarized as follows:

- ✓ Kabacan soil: The soil is categorized in *Entisol*, and the texture is clay loam. It is formulated by recently deposited materials in hilly to mountainous landscape, and only weak profile has developed. Diversified crops, fruit trees, paddy rice, coconuts are grown in the alluvial plain on the hilly to the mountainous landscape areas.
- ✓ Hydrosol/Kidapawan soil: The both soils are categorized in *Hydrosol*, and the texture is clay to clay loam. They are mainly formulated in the alluvial plain along the rivers. The soils are poorly drained and a range of seasonally or permanently wet soils can be the character, subject to regular flooding. They occur on level to gently alluvial plain and derived from alluvial deposits. Nipa palm and mangroves are indigenous vegetation in marshes. Oil palm farms have been successfully developed in some areas of Mindanao including the Project area.
- ✓ Aroman soil: The soil is categorized in *Entisol*, and the texture is sandy loam to sandy. The soil properties are well drained, structure-less and slightly compacted. Diversified crops, e.g. paddy rice, corn, vegetables, beans, mung bean, cassava, sweet potato, palms, fruit are grown in the area.

2.3.2 Agricultural Land Use by Satellite Image Analysis

The JICA team analyzed satellite images in order to clarify cropping area in the MMIP area. As is mentioned in the previous section, the main crops in the MMIP area are paddy and maize, tree crops e.g. coconut tree, while production of vegetables is relatively limited. The analysis focused on detecting cropping area of paddy and maize in the rainy season and the dry season. Described in this section is the planted area of rice and maize, together with tree crop and forestry area, swampy land area and open water surface area, in the MMIP area in 2015-2016 cropping season.

1) Satellite Images Applied for the Analysis

In this satellite analysis, the Team exploited free satellite images which are available on the internet. The images were obtained from 2 types of satellites; namely, one is Landsat 8 satellites operated by National Aeronautics and Space Administration (NASA) and United States Geological Survey (USGS) and the other is Sentinel-2A satellite launched by European Space Agency (ESA).

Table 2.3.3 Wavelength and Spatial Resolution of LANDSAT8/OLI and SENTINEL-2A/MSI

Landsat 8			Sentinel-2A		
Band No	Wavelength Range, μm	Resolution	Band No	Central Wavelength, μm	Resolution
OLI 1	0.433–0.453(coastal/aerosol)	30 m	MSI 1	0.443 (aerosol)	60m
OLI 2	0.450–0.515(blue)	30 m	MSI 2	0.490 (blue)	10m
OLI 3	0.525–0.600(green)	30 m	MSI 3	0.560 (green)	10m
OLI 4	0.630–0.680(red)	30 m	MSI 4	0.665 (red)	10m
-	-	-	MSI 5	0.705 (vegetation classification)	20m
-	-	-	MSI 6	0.740 (vegetation classification)	20m
-	-	-	MSI 7	0.783 (vegetation classification)	20m
OLI 5	0.845–0.885(NIR)	30 m	MSI 8	0.842 (NIR)	10m
-	-	-	MSI 8A	0.865 (vegetation classification)	20m
-	-	-	MSI 9	0.945 (water vapor)	60m
-	-	-	MSI 10	1.375 (cirrus)	60m
OLI 6	1.560–1.660(SWIR-1)	30 m	MSI 11	1.610 (SWIR)	20m
OLI 7	2.100–2.300(SWIR-2)	30 m	-	-	-
OLI 8	0.500–0.680(Pan)	15 m	-	-	-
OLI 9	1.360–1.390(Cirrus)	30 m	-	-	-
-	-	-	MSI 12	2.190 (snow/ice/cloud)	20m

Source: <https://landsat.usgs.gov/what-are-band-designations-landsat-satellites>
<https://earth.esa.int/web/sentinel/user-guides/sentinel-2-msi/resolutions/spatial>

The imaging sensor called Operation Land Imager (OLI) is on board of Landsat 8 and Multispectral Instrument (MSI) is mounted on Sentinel-2A. Both of them are kinds of the multispectral imaging sensor. Table 2.3.3 presents wavelength and spatial resolution of each band in the OLI Level-1 product and the MSI Level-1C product. The highlighted four-band combinations shown in Table 2.3.3 were utilized for this analysis.

2) Methodology and Algorithm

The Normalized Difference Vegetation Index (NDVI) and the Normalized Difference Water Index (NDWI) were calculated by surface reflectance of Blue, Red, Near Infrared (NIR), and Short Wave Infrared (SWIR) band. NDVI is sensitive to the active photosynthetic compounds and is therefore utilized to measure the productivity of vegetation or greenness. NDVI is calculated by using the two bands of the electromagnetic spectrum, i.e. the visible red (OLI 4 and MSI 4) and the near-infrared (OLI 5 and MSI 8). NDWI enhances the spectral reflectance of surface water bodies, which uses differences of two bands, i.e. the visible green (OLI 3 and MSI 3) and the SWIR (OLI 6 and MSI 11) in the analysis.

In the analysis, continuous change of NDVI and NDWI in the cropping season was employed. The figure below shows the assumed cropping pattern in the Project area and its NDVI change and NDWI change; namely, tree crop is existence throughout year; irrigated paddy can be seen twice a year, e.g. rainy season and dry season, and maize can be planted anytime due to availability of rain almost continuously throughout year, thus it can mostly be dense three times in the analyzed season.




Figure 2.3.3 Assumed Cropping Pattern and Example of NDVI and NDWI Changes

Source: JICA Survey Team

During the cropping season, paddy, maize and tree crops, e.g. coconut, mango, rubber, and oil palm are planted in the MMIP area. To classify the crop, the range of NDVI change and the high NDWI, i.e. existing of water surface must be observed. Regarding tree crop and forest, its NDVI keeps high value, so its range of NDVI change becomes low. For paddy and maize area, NDVI changes from low value before planting season to high value in maturing season and low value through harvesting season.

To distinguish paddy from crop planted area including maize, the submersion of paddy field is the key factor for the distinction between the paddy and maize. If high NDWI value can be observed during

the beginning of cropping period, it is most probable that paddy must be planted in the area. On the other hand, if no water body can be detected by NDWI in the area, farmers must be producing maize in that area. With regard to the non-cropped area, the change of NDVI should be middle.

To classify each area, the threshold values of NDVI and NDWI have to be set. The threshold differs in each irrigation service area and by each season. It was mainly decided by Jenks Natural Breaks algorithm, in which the threshold is set at the value of high variation on the distribution curve of NDVI or NDWI covering the target area. The threshold decided by Jenks Natural Breaks algorithm was increased or decreased slightly as




Figure 2.3.4 Basic Flowchart for Identifying Each Cropped Area

Source: JICA Survey Team

required on the basis of the ground truth or the satellite images available on Google Earth. Figure 2.3.4 shows the basic flowchart in exposing each cropping area:

3) Quantitative Evaluation of Agricultural Land Use in the Irrigation Service Area

Table 2.3.4 below shows the result of the analysis, following which summary and the map of the agricultural land use in each irrigation service area are elaborated. Note that the map shows each of the irrigation areas plus 1,000-meter distance area (buffer area) in order for the readers to understand the spatial positioning visually.

Table 2.3.4 Agricultural Land Use Area in Each Irrigation Service Area by Satellite Image Analysis (ha)

Service Area	Stage	Starting Year	Season	Gross Area ¹	Cropped		Non-Cropped	Tree Crop, Forest	Swampy Land ²	Open Water	
					Paddy	Maize					
Maridagao	I	-	Rainy	6,433	1,863	1,394	1,615	843	706	12	
			Dry	6,433	1,991	1,298	1,583	843	706	12	
Upper Malitubog	I	-	Rainy	1,675	729	357	395	188	0	6	
			Dry	1,674	845	235	400	188	0	6	
	II	-	Rainy	3,600	789	716	1,781	291	23	0	
			Dry	3,599	698	888	1,699	291	23	0	
Lower Malitubog	II	Whole	Rainy	9,204	511	1,510	4,140	1,461	194	1,388	
			Dry	9,203	655	1,071	5,595	1,530	337	15	
		2015	Rainy	1,748	65	300	973	387	6	17	
			Dry	1,748	14	246	1,097	388	3	0	
		2016	Rainy	2,348	150	286	1,206	442	12	252	
			Dry	2,349	209	295	1,365	454	26	0	
	2017	Rainy	2,503	136	417	785	370	92	703		
		Dry	2,503	245	160	1,434	394	255	15		
	ODA	Rainy	2,605	160	507	1,176	262	84	416		
		Dry	2,603	187	370	1,699	294	53	0		
	Pagalungan Ext.	II	-	Rainy	1,248	164	184	705	195	0	0
				Dry	1,248	87	273	693	195	0	0

Source: JICA Survey Team

Remark: 1) The Difference of Gross Area between rainy season and dry season was caused by the calculation process on GIS software. 2) Swampy Land of Maridagao, Upper Malitubog, and Pagalungan Service Area was visually identified on GIS with Google Earth. While, in case of Lower Malitubog SA, it was classified by NDVI change.

The availability of irrigation water in MSA and UMSA render their paddy areas to be larger than that of maize since the construction of irrigation facilities in these service areas had been completed through MMIP I. In UMSA under MMIP II, paddy area is almost equivalent to the maize area though

construction of the Project had been carried out. This indicates that the irrigation water had not sufficiently reached UMSA in 2016.

On the other hand, the maize cropped area exceeds that of paddy in non-irrigated area, i.e. LMSA and PSA as the irrigation facilities are still under construction or to be constructed in 2017 and onwards. Especially in originally requested ODA target area of LMSA, the paddy cropped area is only 160 ha and 187 ha as compared to 507 ha and 370 ha of maize cropped area in rainy season and dry season, respectively.

3.1) Phase 1 Maridagao Service Area

MSA, being an irrigated area, relatively exhibits vast rice production (Figure 2.3.5) where 1,863 ha and 1,991 ha in rainy season and dry season respectively, which are covering 57% and 60% of the cropped area including paddy and maize. The major difference of cropped area between rainy season and dry season can not be seen in this area. It might be concluded that the irrigation water stabilizes the rice production of this area.




Figure 2.3.5 Agricultural Land Use of MSA in 2016

Source: JICA Survey Team

3.2) Phase 1 Upper Malitubog Service Area

The trend of UMSA under the MMIP I is almost same as that of MSA, i.e. paddy cropped area is more than that of maize and no major distinction could be observed between rainy season and dry season as shown in Figure 2.3.6. Paddy covers 67% and 87% of cropped area in rainy season and dry season, respectively. As can be also seen in the maps below, the paddy cropped area in rainy season was less than that in dry season. This may be because the scattered cloud covered the satellite images between July to August 2016 and the full extent of water submersion of paddy may not have been detected.




Figure 2.3.6. Agricultural Land Use of UMSA under MMIP I in 2016

Source: JICA Survey Team

3.3) Phase 2 Upper Malitubog Service Area

Though the construction of MMIP II within UMSA had been completed, the submersion of paddy field could not be clearly observed (Figure 2.3.7) from July to August and February to May as compared with MSA and UMSA under MMIP I. While the water on farms could be seen in eastern part of this area, the western part along with RMC-1 Ext.2 canal and Lat K canal must not have been irrigated in the 2016 season. Thus, because of the lack of the irrigation water, the paddy cropped area in dry season is only 698 ha which is smaller than that of rainy season i.e. 789 ha.




Figure 2.3.7 Agricultural Land Use of UMSA under MMIP II in 2016

Source: JICA Survey Team

3.4) Phase 2 Lower Malitubog Service Area

MMIP II within LMSA is under construction as of 2015-2016. It was assumed in this area that the rain-fed paddy was produced by utilizing the residual moisture from the previous rainy season from November and by utilizing the rain at the beginning of rainy season from June. Only 26% and 38% of total cropped area in rainy season and dry season were covered by paddy within the whole area of LMSA. Though lots of farms could be seen in this area on Google Earth, the total cropped area covers 22% in rainy season and 19% in dry season of gross area and they are scattered over this area. It is predicted that especially in rainy season, farmers would hesitate to plant crops due to the high frequency of flooding.




Figure 2.3.8 Agricultural Land Use of LMSA under MMIP II in 2015/2016

Source: JICA Survey Team

3.5) Phase 2 Pagalungan Extension Service Area

PESA is the smallest irrigable area among the irrigation blocks in the MMIP area. Only 28% to 29% of gross areas were cropped as of 2015-2016. In rainy season, the paddy cropped area was almost equal to the maize cropped area. On the other hand, in dry season, it was observed that the paddy cropped area is less than one third of that of maize. Due to lack of water, farmers have to plant maize instead of paddy during the dry season.




Figure 2.3.9 Agricultural Land Use of Pagalungan Ext. Service Area in 2015/2016

Source: JICA Survey Team

2.3.3 Cropping Pattern and Production

Popular crops and cropping pattern in and around the MMIP area can be demarcated by its representative agricultural ecosystem. Table 2.3.5 and Figure 2.3.10 summarize the crops and cropping pattern by municipality and by land use such as upland, lowland (rain-fed), irrigated and swampy/marsh:

Table 2.3.5 Crops and Cropping Pattern in 5 Municipalities in the Project Area

MUNICIPALITY	CROPS/ PATTERN	AGRICULTURAL ECOSYSTEM			
		Upland	Lowland (rain-fed)	Irrigated	Swampy/Marsh
CARMEN	Crops	corn, upland rice, rubber, oil palm, fruit trees, sugarcane, coconut, banana	corn, rice, sugarcane, rubber, oil palm, vegetables, fruits, coconut, banana	rice, vegetables, coconut, banana	n/a

MUNICIPALITY	CROPS/ PATTERN	AGRICULTURAL ECOSYSTEM			
		Upland	Lowland (rain-fed)	Irrigated	Swampy/Marsh
	Cropping Pattern	corn - corn upland rice - corn	rice (one crop) rice - corn corn - corn	rice - rice rice - rice - mungbeans rice - rice&vegetables	n/a
PIKIT	Crops	corn, rubber, coconut, oil palm, fruits, banana	corn, coconut, fruits, oil palm, rubber, banana	rice, vegetables, banana, coconut	rice, corn (during long dry period)
	Cropping Pattern	corn - corn	corn - corn	rice - rice rice&vegetables - rice	n/a
ALEOSAN	Crops	corn, upland rice, rubber, sugarcane, banana, coffee, cacao, coconut, oil palm, fruits	corn, rubber, banana, coconut, rice, sugarcane, fruits	rice, coconut, banana, fruits	n/a
	Cropping Pattern	corn - corn upland rice - corn	corn - corn rice (one crop)	rice - rice rice&vegetables - rice	n/a
PAGALUNGAN	Crops	n/a	corn, coconut, fruits, banana, sugarcane, oil palm	rice, corn, coconut, banana, vegetables	rice, corn (during long dry period)
	Cropping Pattern	n/a	corn - corn	rice - rice rice - rice&vegetables	n/a
DATU MONTAWAL	Crops	n/a	corn, oil palm, coconut, banana, fruits, vegetables	rice, oil palm, vegetables, sugarcane	oil palm, rice, corn (during long dry period)
	Cropping Pattern	n/a	corn - corn	rice - rice rice&vegetables - rice	n/a

Source: 5 Municipality Offices

Diversified crops, including tree crops and fruit trees such as coconut, rubber, banana, mango, etc. are grown in upland and rain-fed ecosystems. Corn must be the major cereal crop in the ecosystems, even though rice is grown in places where a water source for supplementary irrigation is expected. Two crops per year, corn + corn or corn + paddy rice, are a common cropping pattern for annual crops in the ecosystems. As moving to lowland ecosystem from upland ecosystem, paddy rice area increases, and then the diversification of growing crops decreases simultaneously. Oil palm area is becoming to expand in some areas lowland.

Rice is almost exclusively grown in irrigated areas. Two-cropping of rice in a year is a common pattern in the irrigated areas as is practiced in already completed MMIP areas such as MSA, UMSA (MMIP I) and parts of the UMSA under MMIP II. Coconuts, banana and vegetables are grown in surrounding areas of paddy fields even on a border ridge/pass of paddy fields.

Rice and corn are also grown in swampy/marsh ecosystem with residual moisture during dry period when inundation water level downs. It means that those paddy and corn are started to plant after rainy season has gone as following up the inundated water being reduced. The planted area, therefore, widely fluctuates every year in accordance with the scale of the inundation affected by the year's flood. The two crops have to be harvested before the onset of the monsoon season, before being affected by the inundation to come.

Following figure illustrates typical cropping calendar by ecosystem aforementioned. Reflecting small diversification of annual crops in the area, the figure shows a simple cropping calendar. However, the actual cropping calendar is a little bit complicated. With blessed weather condition for growing crops, i.e. stable warm-temperature and even distribution of annual rainfall, farmers in the area can grow some kind of crops whenever they want. Farmers in the area actually cultivate paddy or corn almost every month throughout a year. There is no definite cropping season for all crops in the area, though the overall cropping patterns have a tendency that farmers start cropping in February/March and continue growing the 2nd crop until the end of the year.




Figure 2.3.10 Cropping Calendar in the Project Area

Source: Agriculture Offices in 5 Municipalities in MMIP

Table 2.3.6 shows average productivity of rice and corn in the area from relevant statistical data of various sources, e.g. Country STAT Philippines, the Terminal Report of YLTA-MMIP, information from the OPA of Cotabato Province and DAF-ARMM. Besides, No.6 indicates a result of the Baseline Survey conducted in June and July 2017.

Table 2.3.6 Productivity (ton/ha) of Rice and Corn from Relevant Statistical Data

No	Source	Crop	Rain-fed			Irrigated			Remarks
			Dry	Wet	Year-round	Dry	Wet	Year-round	
1	YLTA Terminal Report (ATI)	Rice	NA	NA	2.93	5.52	5.63	5.63	368 farmers from 7 IAs in Phase I
2	Country STAT Philippines (Production)	Rice	NA	NA	2.95	NA	NA	4.18	Cotabato Province, 2014-16 Ave.
			NA	NA	2.36	NA	NA	3.56	Maguindanao Province, 2014-16 Ave
		Corn	White		2.30	Yellow		3.34	Cotabato Province, 2013-15 Ave.
			White		2.38	Yellow		3.36	Maguindanao Province, 2013-15 Ave.
3	Country STAT Philippines (Production Costs & Returns)	Rice	2.76	2.98	2.92	3.88	4.18	4.05	Region XII, 2013
			1.88	2.65	2.28	3.26	3.24	3.25	ARMM, 2013
4	OPA, Cotabato Province	Rice	NA	NA	3.50	NA	NA	4.50	Pikit Municipality (2014-16 Ave.)
		Corn	White		3.90	Yellow		4.20	
5	SAPROF Report (May, 2007)	Rice	NA	2.00	2.00	3.00	3.00	3.00	Before irrigation facilities completed
			NA	NA	NA	4.95	4.77	NA	After irrigation facilities completed

No	Source	Crop	Rain-fed			Irrigated			Remarks
			Dry	Wet	Year-round	Dry	Wet	Year-round	
6	Baseline Survey (JICA Survey Team)	Rice	NA	NA	1.69	NA	NA	3.38	
		Corn	NA	NA	2.12	NA	NA	NA	

Source: Various statistics, JICA Survey Team

In addition, Table 2.3.7 calculates a crop intensity to the target irrigable area of **Case-1** and **Case-2** and estimated current rice and corn production in LMSA. Compared to the planted area of rice and corn based on Satellite Image analyzed by JICA survey Team, that on NIA PMO of MMIP is larger, and therefore that of the crop intensity is also high. However, both data shows a similar seasonal difference of which the crop intensity in wet season is higher than that in dry season. Upon completion of irrigation facilities, people can expect higher crop intensity even during dry season.

Table 2.3.7 Crop Intensity and Estimated Crop Production in LMSA

Source	Case	Wet Season						
		Target Irrigable Area (ha)	Planted Area of Rice (ha)	Planted Area of Corn (ha)	Planted Area of Rice and Corn (ha)	CI (%)	Production of Rice (ton)	Production of Corn (ton)
Satellite Image Analysis	Case-1	2,810	511	1,510	2,021	72%	869	3,171
	Case-2	3,810	511	1,510	2,021	53%	869	3,171
NIA PMO of MMIP II	Case-1	2,810	367	1,087	1,454	52%	624	2,283
	Case-2	3,810	367	1,087	1,454	38%	624	2,283
Source	Case	Dry Season						
		Target Irrigable Area (ha)	Planted Area of Rice (ha)	Planted Area of Corn (ha)	Planted Area of Rice and Corn (ha)	CI (%)	Production of Rice (ton)	Production of Corn (ton)
Satellite Image Analysis	Case-1	3,688	655	1,071	1,726	47%	1,114	2,249
	Case-2	6,590	655	1,071	1,726	26%	1,114	2,249
NIA PMO of MMIP II	Case-1	3,688	457	795	1,252	34%	777	1,670
	Case-2	6,590	457	795	1,252	19%	777	1,670

Source: JICA Survey Team & NIA PMO

Note: Yield of rain-fed rice is 1.7 ton and that of corn is 2.1 ton based on the results of baseline survey (JICA survey team).
CI; Crop Intensity

1) Rice Farming²

1.1) Farm Size, Land Holding Status and Irrigated Farming

Average farm size of rice farmers is about 1.6 ha in Region XII and ARMM, and the rice farming size in Region XII and ARMM are 1.0 ha and 1.2 ha, respectively. Landowner farmer is the majority of rice farmers in the both regions (Region XII: 58% and ARMM: 64%), while the percentage of landowner farmer in the Philippines remains only at 37%. The percentage of share croppers is bigger than the percentage of land-leased croppers in the both region. Further, the percentage of farmers growing rice in irrigated area in Region XII and ARMM are 66% and 29%, respectively, while the percentage of the Philippines is 61%. It is noted that NIA irrigation system is not well developed in ARMM.

Table 2.3.8 Average Farm Size of Paddy Farm Parcels in 2013 (Unit: ha)

Region	Ave. Farm Size (a)	Ave. Area Planted (b)	Ave. Area Harvested	Paddy Farm % (b/a)	Remarks
Philippines	1.63	0.85	0.84	52.15	
Region XII	1.59	0.96	0.96	60.38	
ARMM	1.57	1.17	1.17	74.52	

Source: 2013 Costs & Returns of Palay Production, Philippine Statistics Authority

² Referred to An analysis of Costs & Returns Palay Production 2013, Philippine Statistics Authority

Table 2.3.9 Percentage Distribution of Paddy Farm Parcels by Tenure Status in 2013 (Unit: %)

Region	Fully Owned	Leased/ Rented	Tenanted	Others	Total
Philippines	37.13	7.54	34.60	20.73	100.00
Region XII	58.21	5.22	23.13	13.44	100.00
ARMM	64.10	2.56	14.10	19.24	100.00

Source: 2013 Costs & Returns of Palay Production, Philippine Statistics Authority

Table 2.3.10 Percentage of Paddy Farm Parcels Irrigated in 2013 (Unit: %)

Region	Irrigated	Non-irrigated	Total	Remarks
Philippines	61.23	38.77	100.00	
Region XII	66.42	33.58	100.00	
ARMM	29.49	70.51	100.00	

Source: 2013 Costs & Returns of Palay Production, Philippine Statistics Authority

1.2) Possession of Drawing Animals and Machinery

The percentage of rice farmers who own drawing animals (buffalo/cattle) in Region XII and ARMM are 50% and 59%, respectively, while the percentage of the Philippines is 42%. The percentage of 2-wheel tractor owners in Region XII is only 13%, which is almost half of the national average, while the percentage is only less than 4% in ARMM. Almost no rice farmers have 4-wheel tractors not only in Region XII and ARMM, but also at the national level.

Table 2.3.11 Percentage of Farmers Owned & Used Drawing Animals & Farm Machinery (Unit: %)

Region	Buffalo/ Cattle	Farm Machinery					
		2-wheel Tractor	4-wheel Tractor	Irrigation Pump	Thresher	Combine Harvester	Grain Dryer
Philippines	41.96	24.15	0.93	9.34	9.06	0.40	3.76
Region XII	49.83	12.69	NA	3.73	8.96	0.37	3.36
ARMM	58.97	3.85	NA	NA	1.28	NA	NA

Source: 2013 Costs & Returns of Palay Production, Philippine Statistics Authority

1.3) Land Preparation

Substantial number of rice farmers depends on machine power (mostly two-wheeled tractors) for the land preparation works except for leveling. Such condition implies that a two-wheeled tractor hiring service for land preparation becomes popular in many places in the Philippines. Animal power and machine power are almost equally utilized for plowing in the Philippines. Percentage of rice farmers who depend on machine power in Region XII is higher than the percentage in the Philippines, whereas the percentage is lower in ARMM.

Table 2.3.12 Percentage of Paddy Farmers by Type of Work Power Used in Land Preparation in 2013 (Unit: %)

Region	Plowing			Rotavating		Harrowing		Levelling	
	Man- Animal	2-W Tractor	4-W Tractor	2-W Tractor	4-W Tractor	Man- Animal	Man- Machine	Man- Animal	Man- Machine
Philippines	59.47	55.45	5.46	27.95	3.83	45.08	57.56	79.04	25.69
Region XII	42.91	69.78	2.24	47.39	0.75	45.52	39.18	97.39	2.61
ARMM	62.82	43.59	1.28	19.23	1.28	71.79	24.36	80.77	5.13

Source: 2013 Costs & Returns of Palay Production, Philippine Statistics Authority

1.4) Planting Method

While about 70% of rice farmers do transplanting at the national level, the farmers in Region XII and ARMM are in exact opposite trend. The percentages who go transplanting are about 30% and about 20% in Region XII and ARMM, respectively. The percentage is fortuitously similar to the percentage of rice farmers who enjoy NIA irrigation system in the both regions. According to

Table 2.3.13 Planting Methods, %

Region	Direct Seeding	Transplanting
Philippines	29.98	70.09
Region XII	70.15	29.85
ARMM	82.05	19.23

Source: 2013 Costs & Returns of Palay Production

information collected from rural areas, direct sowing is still popular in rain-fed area in and around the Project area, while farmers in irrigated area, e.g. farmers in Maridagao Service Area of MMIP I, started transplanting rice in general.

1.5) Seeds and Seed Rate

The percentage of rice farmers who use quality seeds (Certified seeds/Good seeds) under irrigation in Region XII and ARMM is about 35% which is lower than the national average of about 54%. However, the percentages in Region XII and ARMM are still in acceptable range for maintaining seed quality for general cultivation at farmer level. On the contrary, the percentage under rain-fed condition is still very low in Region XII and ARMM.

Table 2.3.14 Percentage Distribution of Paddy Farmers by Ecosystem, by Type of Seed Planted in 2013, Unit %

Region	Hybrid	Open Pollinated			
		Certified Seeds	Good Seeds	Farmers' Seeds	Tradition /Native
Irrigated					
Philippines	4.94	35.02	19.08	38.59	2.37
Region XII	0.56	20.79	15.17	63.48	0
ARMM	0.00	8.70	30.43	60.87	0
Non-irrigated					
Philippines	1.13	17.64	23.32	53.53	4.38
Region XII	0	1.11	3.33	95.56	0
ARMM	0	3.64	7.27	52.73	36.36
Total					
Philippines	3.46	28.28	20.93	44.38	3.15
Region XII	0.37	14.18	11.19	74.25	0
ARMM	0	5.13	14.10	55.13	25.64

Source: 2013 Costs & Returns of Palay Production, Philippine Statistics Authority

Quantity of paddy seeds used in Region XII and ARMM are about 121 kg/ha and 77 kg/ha, respectively. It is assumed that huge amounts of seeds are unnecessarily used by rice farmers in the both region, especially in Region XII, even considering the condition that direct sowing is prevailing over transplanting in the area.

Table 2.3.15 Quantity of Paddy Seeds(Unit: kg/ha)

Region	Irrigated	Non-irrigated	Total
Philippines	89.8	95.9	91.9
Region XII	117.4	133.2	121.3
ARMM	56.8	88.8	76.9

Source: 2013 Costs & Returns of Palay Production

1.6) Fertilizer Use

Urea, ammonium sulphate and NPK (14-14-14) are popular chemical fertilizers among rice farmers in Region XII and ARMM. Quite limited amounts of organic fertilizers are used by them. Many rice farmers avoid balanced nutrition application, as the farmers much depend on nitrogen fertilizers, and don't pay serious attention to apply the phosphate and the potash. It is, however, considered that the present level of nitrogen provided by the fertilizers might not be sufficient, if farmers aim to get higher productivity, e.g. 5 – 6 ton/ha. The amount of chemical fertilizers used in ARMM is much lower than the national average.

Many rice farmers apply chemical fertilizers in several times, for example before planting, in vegetation phase and in reproductive phase. However, the percentage of farmers who practice basal application of fertilizer in Region XII and ARMM are only 6% and 55%. The fertilization technique heavily depending on top-dressing is popular among farmers in Region XII and ARMM, as well as in the Philippines.

Table 2.3.16 Average Quantity of Chemical Fertilizers Applied for Paddy in 2013 (Unit: kg/ha)

Region	Urea	Ammonium Sulphate	Ammonium Phosphate	NPK	NPK	NPK	Muriate Potash
	(45/46-0-0)	(21-0-0)	(16-20-0)	(12-12-12)	(14-14-14)	(16-16-16)	(0-0-60)
	All Paddy						
Philippines	97.67	18.13	21.57	1.07	70.15	1.54	1.21
Region XII	106.48	31.02	6.57	0.78	35.44	0.19	0.78
ARMM	46.80	1.09	3.83	0.55	12.32	NA	NA
	Irrigated Paddy						
Philippines	118.04	19.08	24.22	1.23	83.23	1.58	1.40
Region XII	113.54	25.10	5.56	1.03	41.25	NA	0.78
ARMM	50.00	2.94	NA	NA	20.59	NA	NA
	Non-irrigated Paddy						
Philippines	60.31	16.39	16.71	0.79	46.15	1.47	0.86
Region XII	84.95	49.08	9.66	NA	17.74	0.79	0.79
ARMM	44.90	NA	6.10	0.87	7.41	NA	NA

Source: 2013 Costs & Returns of Palay Production, Philippine Statistics Authority

Table 2.3.17 Percentage of Paddy Farmers by Method of Fertilizer Application in 2013 (Unit: %)

Region	Basal	Side Dressing (vegetative phase)	Top Dressing (reproductive phase)
Philippines	29.59	58.90	68.12
Region XII	5.97	91.04	87.31
ARMM	55.13	30.77	34.62

Source: 2013 Costs & Returns of Palay Production, Philippine Statistics Authority

1.7) Marketing of Rice Paddy

Conventionally, most rice farmers in the MMIP area are financed by trader-lenders those who are working as input suppliers, traders and processors in rice production. Prior to the planting season, the farmers get their input supplies including seeds, fertilizers, chemicals, and even cash from the lenders. A monthly interest for the total amount of supplies and cash provided is being charged by those trader-lenders. A classic example is that; farmers shall repay a principal amount, either in cash or kind, and an interest of 1 bag of paddy rice for every PHP 1,000 per season.

For example, in Carmen, a farmer-borrower is obligated to pay back the amount of paddy equivalent to debt cash and/or inputs to a trader-lender. An interest of PHP 500 is charged for every PHP 1,000 worth of cash and/or inputs by the trader-lender. Meanwhile, the farmer-borrower has to pay an interest of 1 bag of paddy rice for every PHP 1,000 cash borrowed to an individual lender who dealing only cash transaction in the municipality. On the other hand, 5% to 10% of the interest per month is charged by the trader-lender for cash advances and/or cost of inputs used by the farmer-borrower in Pikit.

Prior to the harvest of the rice crop, the farmer informs their respective trader of the harvest and ask her/him to bring her/his hauling vehicle, and collect the paddy rice based on the computed amount financed plus the interest. If farmers still have surplus after subtracting the amount of such a debt and home consumption, they can sell the paddy rice to the trader. Such a relationship discourages the rice farmer-borrower to practice “pole-vaulting”, meaning selling his produce to other traders.

A “suki” system prevails between such a farmer-borrower and a trader-lender. “Suki” is a Filipino term which means a regular and casual farmer-trader transaction relationship wherein trust is the common denominator. This is common and informal form of transaction wherein cash and non-cash withdrawals by farmers are just written in a notebook. Farmers with cash advances from the traders, including the inputs used in the farm, usually get a lower buying price as compared to farmers without debt.

There are two types of deliveries of farmers’ product to the market; either delivered to the market by farmers or picked-up by traders. Considering very poor condition of roads between markets and farms,

farmers either use a single motorcycle and a hand tractor with trailer or hire a vehicle able to penetrate the almost inaccessible road. This results in a very high transport cost of the product. Meanwhile, the traders usually pick-up the farmers' produce using 4WD vehicles. The transportation cost to the traders' place is deducted from the proceeds.

Those big traders³ are mostly found in the Poblacion of Kabacan, Pikit and Carmen because of its proximity from the MMIP areas. Poblacion is a Barangay functioning as a center of municipality and usually located along a national highway. Then, the traders usually process the rice paddy at commercial rice millers, mostly located in Kabacan. There is another commercial rice miller in Carmen. Those rice millers also act as traders, and regularly cater to their "suki" farmers. The farmers of Datu Montawal and Pagalungan deliver their produce either to Kabacan or to Pikit traders. After milling the rice, the traders sell it at big cities such as Kidapawan, Davao and Cotabato.

Note that although there are 25 small-scale rice mills in 13 Barangays of Pikit Municipality, no commercial rice millers are found there. Therefore, these existing rice mills are presumed to be either stationary or mobile rice mills serving for home consumption rice.

2) Corn Farming⁴

2.1) Farm Size and Land Holding Status

Average farm size of corn farmers and corn farming size in Region XII are 2.2 ha and 1.5 ha, respectively, while the sizes in ARMM are 1.8 ha and 1.3 ha. All the farm sizes are bigger than the sizes of rice in the both region. As with the case of the national average, planted area of yellow corn is bigger than the area of white corn in Region XII. The areas of white and yellow corn are, however, almost equal in ARMM.

Table 2.3.18 Average Farm Size of Corn Farm Parcels in 2013, ha

Region	Ave. Farm Size (a)	Devoted to Corn (b)	Corn Farm % (b/a)
Philippines	2.14	1.14	53.27
Region XII	2.24	1.50	66.96
ARMM	1.80	1.30	72.22

Source: 2013 Costs & Returns of Corn Production, Philippine Statistics Authority

Table 2.3.19 Average Area Planted and Harvested of Corn Farm Parcels in 2013, ha

Region	White		Yellow	
	Planted	Harvested	Planted	Harvested
Philippines	0.67	0.67	1.05	1.05
Region XII	0.83	0.83	1.03	1.03
ARMM	1.12	1.10	1.15	1.15

Source: 2013 Costs & Returns of Corn Production, Philippine Statistics Authority

Landowner farmer is the majority of corn farmers in ARMM (70%), while the percentage of the farmer in Region XII is only 35%. The percentage of share croppers is lower than the percentage of rice farmers in the both region, though the percentage is still bigger than the percentage of land-leased croppers. Relatively high percentage of other growers, who might be large-scale commercial farms, is seen for corn farmers. The percentages are 37% in Region XII and 28% in ARMM.

³ Aside from the big traders, there are middle-men of rice paddy. They purchase the paddy from the farmers and sell to the big traders.

⁴ Referred to An analysis of Costs & Returns Corn Production 2013, Philippine Statistics Authority

Table 2.3.20 Percentage Distribution of Corn Farm Parcels by Tenure Status in 2013, %

Region	Fully Owned	Leased/ Rented	Tenanted	Others	Total
Philippines	36.11	3.65	25.00	35.24	100.00
Region XII	35.09	4.39	23.68	36.84	100.00
ARMM	70.41	0.00	2.04	27.55	100.00

Source: 2013 Costs & Returns of Corn Production, Philippine Statistics Authority

2.2) Possession of Drawing Animals and Machinery

The percentage of corn farmers who own drawing animals (buffalo/cattle) in Region XII and ARMM are 41% and 90%, respectively, while the percentage of the Philippines is 56%. Limited corn farmers have farm machinery not only in Region XII and ARMM, but also in the Philippines.

Table 2.3.21 Percentage of Farmers Owned & Used Drawing Animals & Farm Machinery in Corn Farm, %

Region	Buffalo/ Cattle	Farm Machinery				
		2-wheel Tractor	4-wheel Tractor	Irrigation Pump	Sheller	Grain Dryer
Philippines	56.11	3.65	0.48	4.60	1.59	0.08
Region XII	41.23	2.63	0.88	0.88	2.63	NA
ARMM	89.69	NA	NA	NA	NA	NA

Source: 2013 Costs & Returns of Corn Production, Philippine Statistics Authority

2.3) Land Preparation

Majority of corn farmers depend land preparation works on animal power. It is interesting that a relatively high percentage of corn farmers use 4-wheel tractors for the works comparing to rice farmers. This may be caused by the activity of large-scaled commercial farms.

Table 2.3.22 Percentage of Corn Farmers by Type of Work Power Used in Land Preparation in 2013, %

Region	Plowing			Rotavating		Harrowing			Furrowing	
	Man- Animal	2-W Tractor	4-W Tractor	2-W Tractor	4-W Tractor	Man- Animal	2-W Tractor	4-W Tractor	Man- Animal	Man- Machine
Philippines	58.25	1.19	14.24	0.48	2.70	40.32	3.49	2.30	63.73	2.94
Region XII	64.91	1.75	14.04	NA	NA	46.49	0.88	4.39	70.18	2.63
ARMM	57.14	NA	22.45	NA	6.12	72.45	1.02	NA	74.49	NA

Source: 2013 Costs & Returns of Corn Production, Philippine Statistics Authority

2.4) Varieties of Corn

In case of white corn, most farmers grow OPV (Open Pollinated Varieties). While the majority of farmers in Region XII grow improved varieties of white corn, the farmers in ARMM prefer much native varieties. On the contrary, hybrid varieties are popular in yellow corn cultivation among farmers. In Region XII, the percentage of farmers growing hybrid yellow corn is just 50%, whereas no farmers grow hybrid varieties even in yellow corn cultivation in ARMM. 40% of the yellow corn farmers still grow OPV native varieties in ARMM.

Table 2.3.23 Percentage Distribution of Corn Farmers by Corn Type by Type of Seed in 2013, %

Region	White			Yellow		
	Hybrid	Modern OPV	Native OPV	Hybrid	Modern OPV	Native OPV
Philippines	0.55	40.37	59.08	74.86	21.97	3.18
Region XII	0.00	88.57	11.43	50.00	47.73	2.27
ARMM	0.00	26.14	73.86	0.00	60.00	40.00

Source: 2013 Costs & Returns of Corn Production, Philippine Statistics Authority

2.5) Seed Sources of OPV and Seed Rate

Majority of corn farmers still use own produced-seeds or procure seeds from neighbor farmers for growing improved OPV and native OPV. However, a certain percentage of the farmers buy seeds of

the both OPVs from traders or seed-growers. Percentage of the farmers who buy OPV seeds from traders or seed-growers in Region XII and ARMM are higher than the percentage of national average.

Table 2.3.24 Percentage of Corn Farmers by Source/s of Modern and Native OPV Seeds in 2013, %

Region	Modern OPV			Native OPV		
	Govt.	Trader/ Seed Grower	Co-farmer/ Own produce	Govt.	Trader/ Seed Grower	Co-farmer/ Own produce
Philippines	3.59	13.03	84.49	1.09	5.99	93.11
Region XII	0.00	15.66	85.54	0.00	22.22	77.78
ARMM	0.00	37.93	62.09	0.00	17.39	84.06

Source: 2013 Costs & Returns of Corn Production, Philippine Statistics Authority

Quantity of corn seeds used in Region XII and ARMM are 18.7 kg/ha and 19.4 kg/ha, respectively. Though the both seed rates per hectare are higher than the average of the Philippines, they still remain within the reasonable level.

Table 2.3.25 Seed Ratio of Corn, kg/ha

Region	White	Yellow	Total
Philippines	15.73	18.11	16.61
Region XII	19.31	17.87	18.67
ARMM	19.22	20.57	19.37

Source: 2013 Costs & Returns of Corn Production,

2.6) Fertilizer Use

As same as the case of rice farmers, urea, ammonium sulphate and NPK (14-14-14) are popular chemical fertilizers among corn farmers in Region XII and ARMM. Trends of chemical fertilizer use, such as very limited use of organic fertilizers, heavily nitrogen-conscious application, low dependency on the basic dressing and very low volume use in ARMM are also similar to rice farmers.

Yellow corn growers tend to use much more volume of fertilizers than white corn growers. In terms of nutrients amount, fertilizer volume applied for yellow corn is higher than the volume for rice. Most farmers intend to get a higher level of productivity from yellow corn production by combining hybrid varieties and chemical fertilizers.

Table 2.3.26 Average Quantity of Chemical Fertilizers Applied for Corn in 2013, Kg/ha

Region	Urea	Ammonium Sulphate	Ammonium Phosphate	NPK	NPK	NPK	Muriate Potash
	(45/46-0-0)	(21-0-0)	(16-20-0)	(12-12-12)	(14-14-14)	(16-16-16)	(0-0-60)
All Corn							
Philippines	84.02	14.20	28.35	0.15	44.11	1.48	0.10
Region XII	97.87	20.27	5.07	NA	65.20	NA	NA
ARMM	28.54	NA	0.46	NA	35.56	NA	NA
White Corn							
Philippines	37.59	14.95	15.71	0.16	23.93	0.40	NA
Region XII	60.19	14.55	5.57	NA	45.03	NA	NA
ARMM	23.17	NA	0.51	NA	32.57	NA	NA
Yellow Corn							
Philippines	162.18	12.93	49.63	0.14	78.08	3.30	0.28
Region XII	146.57	27.65	4.42	NA	91.26	NA	NA
ARMM	73.91	NA	NA	NA	60.87	NA	NA

Source: 2013 Costs & Returns of Corn Production, Philippine Statistics Authority

Table 2.3.27 Percentage of Corn Farmers by Method of Fertilizer Application in 2013, %

Region	Basal	Side Dressing (vegetative phase)	Top Dressing (reproductive phase)
Philippines	30.79	53.41	27.14
Region XII	11.40	48.25	50.88
ARMM	12.24	25.51	14.29

Source: 2013 Costs & Returns of Corn Production, Philippine Statistics Authority

2.3.4 Agricultural Mechanization

A presentation paper⁵ prepared in 2013 depicts an outline of the agricultural mechanization in the Philippines. According to the paper, the mechanization for popular crops is still less developed in the Philippines except for land preparation, threshing/shelling and milling of rice and corn (Table 2.3.28).

Table 2.3.28 Agricultural Mechanization by Crops in the Philippines

Works/Operation	Mechanization Status		
	Rice/Corn	Vegetables, legumes & root crops	Coconut/Fruits/ Fiber crops
Land preparation	Intermediate to high	Low	-
Planting/transplanting	Low	Low	Low
Crop care/cultivation	Low	Low	Low
Harvesting	Low	Low	Low
Threshing/shelling	Intermediate to high	Low	-
Drying	Low	Low	Low
Milling/village level processing	High	Low	Low

Source: "Status of Agricultural Mechanization in the Philippines", Delfin C. Suministrado of Agricultural Machinery Testing and Evaluation Centre, University of the Philippines Los Baños, 2013

It may be assumed that the present condition in the Project area is similar to those of above table according to available secondary data and collected information. Table 2.3.29 and Table 2.3.30 show percentages of rice and corn farmers who owned or used farm machineries in 2013 in Region XII, ARMM and the Philippines. The tables imply that mechanization of plowing and threshing/shelling of rice and corn has progressed to a certain level even in the Project area, while manual labors still play an overwhelming role in the other agricultural works.

Table 2.3.29 Percentage of Rice & Corn Farmers Owned & Used Farm Machinery in 2013 (unit: %)

Region	2-W Tractor		4-W Tractor		Thresher/ Sheller		Grain Dryer	
	Rice	Corn	Rice	Corn	Rice	Corn	Rice	Corn
Philippines	24.15	3.65	0.93	0.48	9.06	1.59	3.76	0.08
Region XII	12.69	2.63	NA	0.88	8.96	2.63	3.36	NA
ARMM	3.85	NA	NA	NA	1.28	NA	NA	NA

Source: Philippine Statistics Authority

Table 2.3.30 Percentage of Rice & Corn Farmers Used Farm Machinery in 2013 (unit: %)

Region	Plowing 2-W Tractor		Plowing 4-W Tractor		Threshing/ Shelling		Drying	
	Rice	Corn	Rice	Corn	Rice	Corn	Rice	Corn
Philippines	55.45	1.19	5.46	14.24	81.65	33.57	0.48	0.08
Region XII	69.78	1.75	2.24	14.04	92.54	52.63	NA	NA
ARMM	43.59	NA	1.28	22.45	65.38	41.87	NA	NA

Source: Philippine Statistics Authority

Above tables also show that percentages of rice and corn farmers who used farm machinery for plowing and for threshing/shelling. They are much higher than the percentages of the farmers who owned relevant farm machinery not only in the Philippines, but also in Region XII and ARMM. Such condition implies that a business of farm mechanization service for plowing and threshing/shelling of rice and corn is well developed or developing in the whole country including the Project area. Comparing rice and corn, mechanization of rice farming is more progressed than that of corn farming. ARMM is less developed in terms of farm mechanization, however, if compared by region.

During the Baseline Survey carried out in June and July 2017, the farmers queried about possession of

⁵ "Status of Agricultural Mechanization in the Philippines", Delfin C. Suministrado of Agricultural Machinery Testing and Evaluation Centre, University of the Philippines Los Baños, prepared for the Regional Forum on Sustainable Agricultural Mechanization in Asia and in the Pacific at Qingdao in China in 2013.

draft animals and agriculture machineries in the project area. While some of the farmers owns the machineries in the MSA, where irrigation paddy production has been widely spread, few farmers own them in the LMSA.

Table 2.3.31 Percentage of Farmers Own Farm Machinery Identified at the Baseline Survey (unit: %)

Barangay	Area	Draft Animal	Warehouse	4-Wheel Tractor	Hand Tractor	Floating Tiller	Thresher	Water Pump	Rice Mill	Dryers
UGALINGAN/ GENERAL LUNA	MSA	23	3	0	10	10	10	3	0	0
KILANGAN	MSA	45	10	5	10	30	15	15	0	0
KIBAYAO	MSA	15	5	10	15	20	15	5	0	10
BOLIOK	LMSA	25	0	0	0	0	0	0	0	0
TALITAY	LMSA	55	0	0	5	5	0	0	0	0
BAGO-INGED	LMSA	20	0	0	0	0	0	0	0	0
GLI-GLI	LMSA	33	0	0	0	0	0	0	0	0
MACABUAL	LMSA	25	0	0	0	0	0	0	0	0
PUNOL	LMSA	15	0	0	0	0	0	0	0	0

Source: JICA Survey Team

In addition, an inventory of pre- and post-harvest facilities are summarized in APPENDIX IV, those for beneficiary Barangays of MMIP I and MMIP II in Pikit, Aleosan, Carmen, Pagalungan and Datu Montawal Municipalities.

2.3.5 Agricultural Extension Service to Farmers

1) Outline of the National Extension System

The Agriculture and Fisheries Modernization Act (AFMA) of 1997, or Republic Act No. 8435, stipulates the formulation of a National Extension System for Agriculture and Fisheries (NESAF) with three sub-systems; namely, national government sub-system, local government sub-system, and private sector sub-system. The local government units (LGUs) are mandated to deliver extension services to farmers, fisher folks, and agribusiness entrepreneurs. Provincial governments are mandated to integrate the operations for the agriculture extension services within the province and undertake continuous and periodic annual evaluation of all municipal extension programs.

2) Agricultural Training Institute (ATI)

The Agricultural Training Institute (ATI), a bureau of the Department of Agriculture (DA), is the extension and training arm of the national government sub-system. By an administrative order of DA in 2015, ATI has streamlined operations based on its role as indirect provider of extension and training services to LGU extension workers. This is to complement the LGUs responsibility to deliver direct agriculture and fisheries extension services to the beneficiary farmers and fisher folks. ATI is given the following mandate according to ATI's web-homepage:

- ✓ To lead in the formulation of the national Agriculture and Fisheries Extension (AFE) agenda and budget,
- ✓ To prepare an integrated plan for publicly-funded training programs in agriculture and fisheries,
- ✓ To formulate and issue guidelines in planning, implementing, monitoring and evaluating AFE programs,
- ✓ To assist, in coordination with state universities and colleges, the local government units extension system by improving their effectiveness and efficiency through capability building and complementary extension activities such as technical assistance, training of LGU personnel, improvement of physical facilities, extension cum research and information support services, and

- ✓ To lead in the provision of e-extension services in collaboration with the various agencies, bureaus and organizational units of the DA. This is to integrate and harmonize ICT-based extension delivery system for agriculture and fisheries.

ATI is one of 8 bureaus under the control of DA and have 4 divisions and 16 training centers in the country. Out of 16 training centers, one is the International Training Center on Pig Husbandry, while remaining 15 centers are regional training centers scattered all over the country. Figure 2.3.11 shows ATI's organizational diagram, and Table 2.3.32 shows annual budgets of ATI from 2014-2017. Note that increase in the 2017 budget is due to a special fund to alleviate poverty in the poorest 22 provinces.




Figure 2.3.11 ATI Organizational Structure

Source: Agriculture Training Institute

Table 2.3.32 Annual Budget of ATI from 2014-2017 (unit: 1000 Pesos)

Budget Item	2014	2015	2016	2017
General Administration and Support Services	229,772	25,375	229,375	182,729
Operations	686,369	795,912	767,763	2,259,831
Projects	127,579	22,637	28,075	30,896
Total	1,043,720	843,906	1,025,213	2,473,456

Source: Agriculture Training Institute Headquarters

ATI has 15 regional centers, same as the regional ATI office, and one of them is located in Tantangan, called ATI Regional Training Centre XII. The organizational structure set up of the ATI Regional Training Centre XII is shown in the following figure and tables. There are total 55 staff under the Regional Center Director, and the annual budget ranges from 64 million to 208 million pesos for the last 3 years. The regional center has outreach offices, one of which is Kabacan Outreach Office, which have been engaged in the agriculture extension services within the MMIP area.




Figure 2.3.12 Organization of ATI Regional Training Centre (XII)

Source: ATI Regional Training Centre (XII)

Table 2.3.33 Number of Staff of ATI Regional Training Centre (XII)

No	Office/Unit/Section	Number	Remarks
1	Office of the Training Centre Superintendent	2	Director & 1 Superintendent
2	Administrative and Finance Service Unit	9	
3	Planning, Monitoring and Evaluation Service Unit	3	
4	Career Development and Management Service Section	5	
5	Partnership and Accreditation Service Section	3	
6	Information Service Section	4	
7	Technical Staff for the Centre	6	
8	Administrative Support Staff for the Centre	9	
9	Kabacan Outreach Office (MMIP Project team)	14	1 Project Officer, 10 Tech. Staff (3 vacancy) & 3 Admi. Staff
	Total	55	

Source: ATI Regional Training Centre (XII)

Table 2.3.34 Annual Budget of ATI Regional Training Centre (XII)

Year	2015	2016	2017
Budget (thousands Peso)	64,417	78,692	208,315*

Note: * Increase in the 2017 budget is due to a special fund to alleviate poverty in the poorest 22 provinces including Cotabato province and Maguindanao province.

Source: Agriculture Training Institute (Region XII)

3) Agricultural Extension System in the Project Area

Agricultural extension system in the Philippines is decentralized and LGUs, i.e. municipality governments, are the responsible agency to deliver agriculture and fisheries extension services directly to farmers under the present administrative system. The extension system in the Project area is, however, slightly different between the municipalities in Cotabato Province of Region XII, i.e. Carmen, Pikit and Aleosan and municipalities in Maguindanao Province of ARMM, i.e. Datu Montawal and Pagalungan, as general administration systems between Region XII and ARMM are not the same. While the administration system in Region XII is decentralized, same as other regions in the Philippines, ARMM has a centralized governance structure.

Figure 2.3.13 illustrates the extension setup in Cotabato Province. Municipality is a local autonomous unit down the Province in the Philippines. Each municipality government in Cotabato Province has an Office of Municipal Agriculturist (OMA) represented by Municipal Agriculturist (MA) who reports directly to the Mayor. OMA handles all matters of agricultural development within the municipality jurisdiction, and thus provides agricultural extension services directly to farmers. Agricultural Technologists are positioned to OMA as extension service providers at field level. Office of Provincial Agriculturist (OPA) represented by Provincial Agriculturist (PA) supervises and coordinates municipal extension programs within the province. Subject Matter Specialists in OPA undertake a technical consultation and guidance with Agricultural Technologists of OMAs.




Figure 2.3.13 Agricultural Extension Setup in Cotabato Province

Source: Cotabato Province Agriculture Office

The extension setup in Maguindanao Province shown in Figure 2.3.14 is slightly different from that of

Cotabato province. DAF (Department of Agriculture and Fisheries) of ARMM Government has strong authority and responsibilities for agriculture administration within the ARMM. While agricultural officers are assigned at provincial level called as PAO (Provincial Agriculture Officer) and at municipality level called as MAO (Municipality Agriculture Officer), they are directly controlled and supervised by DAF-ARMM. Although the administrative management system is different from other regions, Agricultural Technologists are positioned as extension service providers at field level, and Subject Matter Specialists are positioned at provincial level as senior technical staff supporting the Agricultural Technologists.




Figure 2.3.14 Agricultural Extension Setup in Maguindanao Province

Source: Maguindanao Province Agriculture Office

Note that the PAO and the PA on Figure 2.3.14 are not the same, but coordinate with each other to implement agricultural programs and projects within the province. The national government programs/projects are coursed through the PAO while the provincial government funded ones are done by the PAO. Also, the PAO has her/his subordinate at municipal level, which is a MAO, whereas the PA has no personnel at that level.

Table 2.3.35 Staff in Office of Municipal Agriculturist (in Cotabato Province) and Allocated DAF Staffs to Municipality (in ARMM) as of 2017

No.	Title/Position	Cotabato Province								
		Carmen			Pikit			Aleosan		
		Filled	Vacant	Total	Filled	Vacant	Total	Filled	Vacant	Total
1	Municipal Agriculturist	1	0	1	1	0	1	0	1	1
2	Senior Agriculturist	1	0	1	0	0	0	0	1	1
3	Agriculturist/Agri. Technologist	7	1	8	10	0	10	6	4	10
4	Veterinarian	0	0	0	1	0	1	1	0	1
5	Coop. Dev. Specialist	0	0	0	0	0	0	1	0	1
6	Assistant Workers	3	0	3	2	0	2	2	0	2
Total		12	1	13	14	0	14	10	6	16
No.	Title/Position	ARMM								
		Datu Montawal			Pagalungan					
		Filled	Vacant	Total	Filled	Vacant	Total			
1	Municipal Agriculturist	0	0	0	1	0	1			
2	Senior Agriculturist	1	0	1	2	0	2			
3	Agriculturist/Agri. Technologist	2	0	2	0	0	0			
4	Veterinarian	0	0	0	0	0	0			
5	Coop. Dev. Specialist	0	0	0	0	0	0			
6	Assistant Workers	0	0	0	0	0	0			
Total		3	0	3	3	0	3			

Source: 5 Municipal Agriculture Offices Concerned

Table 2.3.35 shows the number of staffs concerned with agriculture administration allocated to 5 municipalities in the project area. The numbers of staffs in an OMA in Cotabato municipalities are 10 – 14, while only 3 DAF staffs are assigned to each of the municipalities in ARMM. As all the staffs participating in the agricultural administration are counted in the numbers, the actual number working for extension services must be smaller. Even if all the staffs in the table exclusively work for extension


services, the services are not able to cover all the farm households. The number of the households in the municipalities is estimated to be at least several thousand or more than ten thousands depending on the population size.

Figure 2.3.15 shows results of the Baseline Survey inquiring agricultural extension services in the MMIP area. While information source on farming is rather casual and considered limited to family members and neighborhood in the MMIP II area, it is diversified and includes official sources such as government officers and IA leaders. The Question 3 also indicates that much more attentions are given to the MMIP I area by the extension officers.

This may be attributed to the progress of the project intervention by YLTA and the government so far and none of farmers in LMSA have joined the projects yet. In addition, as already discussed, farmers in LMSA are considered engaged in more extensive farming and farming puts only 43% contribution on the farmers' total gross income according to a result of the Baseline survey. On the other hand, 82% of the gross income come from agriculture in MMIP I and the farmers conduct more intensive farming requiring more frequent technical consultation from the experts.

Q1. When you have problems in your farming, with whom do you consult?

Q2. In case of Irrigation Area, when you have problem in the irrigation service, with whom do you consult?



Q3. How many times did you meet with the extension workers in/around your Barangay for technical consultation in 2016??

Q4. What kind of extension services did you get in 2016?




Figure 2.3.15 Farmers' Observations on Agriculture Extension Services in the MMIP Area

Source: Baseline Survey

4) YLTA (Yen Loan Technical Assistance) of MMIP I

A Yen Loan Technical Assistance (YLTA) was implemented in order to increase productivity of rice in the MMIP project area through enhancement of farming skills and financial management of target IAs. YLTA selected 7 Irrigators Associations (IAs) from Cotabato Province of Region XII and

Maguindanao Province of ARMM from 2014 to 2016 as shown in Table 2.3.36. Note that actual field intervention was carried out only for 2 years, in 2014 and 2015.

Table 2.3.36 Target IAs of YLTA

IA	Year of YLTA implementation	Irrigation Area (ha)	Members Before YLTA	Province	Municipality	Barangay
KIPAN	2014	376.89	318	Cotabato	Carmen	Kibayao
NASGIA	2014	211.14	155	Cotabato	Carmen	Kibayao
MORNING LIGHT	2014	377.67	201	Maguindanao	Pagalungan	Kilangan
MRISIA Div.6	2014	515.58	331	Cotabato	Carmen	Ugalingan/ General Luna
BASBIA	2015	437.12	260	Cotabato	Carmen	Nasapian
KATINGKONGAN	2015	394.86	318	Maguindanao	Pagalungan	Kilangan
MANSAPA	2015	202.27	153	Cotabato	Carmen	Nasapian
Total	-	2,515.53	1,746	-	-	-

Source: NIS Profile (as of Dec. 31, 2014), NIA and YLTA-MMIP Terminal Report 2017, ATI

A steering committee was set up at national level for coordination and supervision of the implementation. Members of the committee are ATI (Chairman of the committee), NIA, DA and JICA. A Project Management Team (PMT) was also set up with the following members in order to coordinate an interest of stakeholders on the project site. Other relevant agencies had also participated in PMT meetings when necessary, such as PhilRice (Philippine Rice Research Institute), PhilMech (Philippine Center for Postharvest Development and Mechanization), PCIC (Philippine Crop Insurance Cooperation), universities and colleges, etc. ATI Regional Training Centre (XII).

1. NIA Regional Management Office (XII) (Vice-chairman of PMT)
2. NIA MMIP PMO (Project Management Office)
3. NIA CIMO (Cotabato Irrigation Management Office)
4. NIA MRIS (Maridagao River Irrigation System)
5. DA Regional Office (XII)
6. DAF (Department of Agriculture & Fisheries) ARMM
7. DA Maguindanao Province
8. Municipality offices in Cotabato Province (Pikit, Carmen & Aleosan)

ATI was a leading implementer of YLTA. ATI provided whole necessary assistance through ATI Regional Training Centre (XII). ATI Regional Training Centre (XII) assigned a technical team exclusively for YLTA in its Kabacan outreach office located in the campus of the University of Southern Mindanao. The technical team has 11 technical staffs and still they are working for an additional technical assistance program in the MMIP




Figure 2.3.16 Implementation Setup of YLTA

Source: YLTA-MMIP Terminal Report 2017, ATI

project area funded by the Philippine Government. Figure 2.3.16 shows the implementation setup of

YLTA.

YLTA has the following 3 major components; namely, 1) Participatory Demonstration Farms (PDF), 2) Farm Production Input Assistance (FPIA), 3) Development of Extension Modality. Besides, YLTA had agricultural machinery intervention, yet it was limited to just lending a set of floating tiller, rotavator, hand tractor with trailer, thresher and welding machine to the respective target IAs on the condition that it is returned after a certain period of utilization. Under these 3 major components, there have been a series of trainings to which following participants had participated:

Table 2.3.37 Number of Participants/Beneficiaries of YLTA

No	Components	Participants/Beneficiaries
1	Participatory Technology Demonstration (PTD)	14 sites in 7 IAs
2	Farm Production Input Assistance (FPIA)	368 beneficiaries
3	Trainings, Seminars and other Training Related Activities	
3-1	Technical Briefing on Rice Production	467 participants
3-2	Benchmark Survey and Focus Group Discussion	467 participants
3-3	Soil Sampling and Analysis	467 participants
3-4	Climate Smart Field School	467 participants
3-5	Values Re-orientation and Islamic Culture Appreciation	120 participants
3-6	Rice Production and Seed Certification Training	120 participants
3-7	Financial Management Training	120 participants
3-8	Enterprise Development Training	120 participants
3-9	Farmer-led Extension	60 participants
3-10	Farmer's Field Day (FFD)	14 sites in 7 IAs
3-11	Expository Tour	140 participants
3-12	TOT on Rice Production	30 participants
3-13	Capacity Enhancement Training	30 participants
4	Extension Materials	
4-1	Extension Manuals	-
4-2	Audio Visual Materials	-
4-3	Information Education Campaign (IEC) Materials	-
5	Farm Machineries*	4 units each

Note: * Machineries are power tillers with trailer, floating turtle, thresher, welding machine, etc.

Source: YLTA-MMIP Terminal Report 2017, ATI

On the achievement of YLTA, the productivity of rice in all the 7 IAs remarkably increased after the intervention as shown below. The average increase was 2.70 ton/ha from 2.93 ton/ha to 5.63 ton/ha. In the YLTA-MMIP Terminal Report 2017, ATI noted that there were damages of stem-borers in dry season of 2015. It implies that the productivity in the season dropped due to the damages.

Table 2.3.38 Paddy Yield Comparison with-YLTA and without-YLTA

No.	IA	YLTA Year	No. of Farmers	Yield (ton/ha)			
				Without YLTA	With YLTA		
					Dry Season	Wet Season	Ave.
1	KIPAN	2014	54	2.45	5.92	6.80	6.36
2	NASGIA	2014	55	3.10	6.06	6.85	6.46
3	MORNING LIGHT	2014	57	3.20	6.45	6.00	6.23
4	MRISIA Div.6	2014	52	3.20	5.40	6.65	6.03
5	BASBIA	2015	50	3.30	4.05	4.62	4.34
6	KATINGKONGAN	2015	50	2.80	4.85	4.89	4.88
7	MANSAPA	2015	50	2.50	4.66	5.56	5.11
Total			368	2.93	5.52	5.55	5.63

Note: 368 farmers are beneficiaries of Farm Production Input Assistance (FPIA)

Source: YLTA-MMIP Terminal Report 2017, ATI

An additional technical assistance program similar to YLTA started in 2014 wet season after a request from IA members in the MMIP project area. The Department of Budget and Management (DBM) of the President Office has approved a special fund to implement the additional program covering the areas which were not involved in YLTA. The special fund is valid for 5 years. Table 2.3.39 shows an allocated annual budget from the special fund for the additional program from 2014 – 2018.

Table 2.3.39 Annual Budget of Additional Program Funded by GOP

Year	2014	2015	2016	2017	2018 (Proposal)
Budget (thousands Peso)	28,048	22,637	28,075	30,896	30,800

Source: ATI Headquarters

With the special fund allocated by the Government, ATI Regional Training Centre (XII) also carried out additional program in parallel with the YLTA through the MMIP technical team in Kabacan outreach office. In total, 18 IAs benefited from the additional program until the end of 2017 as shown in the table below. Total numbers of IAs involved by the end of 2017 as well as the number of beneficiaries were higher than the number benefitted by YLTA.

Table 2.3.40 Number of Beneficial IAs and Farmers of YLTA and Additional Program Funded by GOP as of June 2018

No.	SA	Project (I or II)	NAME OF IA	Total No. of Beneficiaries per Year & by Source of Fund								
				YLTA		Subtotal	Government Fund				Subtotal	Total
				2014	2015		2014	2015	2016	2017		
1	MSA	MMIP I	BASBIA*1	0	60	60	0	0	30	0	30	90
2	MSA	MMIP I	MANSAPA	0	60	60	0	0	0	0	0	60
3	MSA	MMIP I	MRISIA DIV 5	0	0	0	60	0	0	0	60	60
4	MSA	MMIP I	NASFIA	0	0	0	60	0	30	0	90	90
5	MSA	MMIP I	KIPAN	65	0	65	0	0	0	0	0	65
6	MSA	MMIP I	NASGIA	66	0	66	0	30	0	0	30	96
7	MSA	MMIP I	MRISIA DIV 6	63	0	63	0	30	0	0	30	93
8	MSA	MMIP I	EDUFIA	0	0	0	0	60	30	0	90	90
9	MSA	MMIP I	GAGDANEN BAYA	0	0	0	60	30	30	0	120	120
10	MSA	MMIP I	KATINGKONGAN*1	0	60	60	0	0	0	0	0	60
11	MSA	MMIP I	MORNING LIGHT	68	0	68	0	0	60	0	60	128
12	MSA	MMIP I	TAFIA	0	0	0	60	0	60	0	120	120
19	UMSA	MMIP I	BAGONABATI*1	0	0	0	60	0	30	0	90	90
20	UMSA	MMIP I	BALATIKAN*1	0	0	0	0	60	30	0	90	90
13	UMSA	MMIP II	DALFIA*1	0	0	0	0	0	0	60	60	60
14	UMSA	MMIP II	TAMCIA*1	0	0	0	0	0	0	60	60	60
15	UMSA	MMIP II	LAGUNDE PAMBUA*1	0	0	0	0	0	0	60	60	60
16	UMSA	MMIP II	MALIGA LUPA*1	0	0	0	0	0	0	30	30	30
17	UMSA	MMIP II	SARAPANI PANICUPAN*1	0	0	0	0	0	0	60	60	60
18	UMSA	MMIP II	NALAPANI	0	0	0	0	60	0	30	90	90
21	UMSA	MMIP II	CHRISLAM*1	0	0	0	0	60	0	0	60	60
Total No. of Beneficiaries				262	180	442	300	330	300	300	1,230	1,672
Total No. of IAs				4	3	7	5	7	8	6	18	21

Source: ATI Regional Training Centre (XII)

Note: *1 Out of 21 IAs, 10 IAs will receive the government fund in the wet season of 2018.

5) Challenges of Agricultural Extension Service

It is generally recognized that agricultural extension services in the Philippine remains ineffective and receives modest support from the government despite the crucial role of the services in achieving sustainable development of agriculture. Relevant papers have pointed out the following issues and problems on an agricultural extension system in the Philippines.

- ✓ Lack of financial support: LGUs allocate budget preferentially to infrastructure projects in most cases. Funds allocated for agricultural development including extension services are minimal in general. Several papers noted that decentralization policy without financial decentralization is meaningless. Due to limited operational funds for travel, extension workers encounter difficulty in providing extension services to farmers. Shortage of funds also limits the production of information, education and communication materials necessary for the services.
- ✓ Less development of human resources: Extension workers are not well motivated for providing quality and efficient services due to lack of career development plan and opportunities. Low salaries and poor incentive systems also discourage them from concentrating on their duties. Many experiences noted that extension workers should be empowered through continuous capability building in order to facilitate community-based and participatory approaches and

enhance their technical knowledge and skills.

- ✓ Strong political influences: Political interventions largely determine type and quality of the extension services to be provided. In some extent, political influences affect hiring of the extension staff.
- ✓ Weak function of DA for supporting LGUs: ATI is mandated to function as an apex agency for agricultural extension at national level under DA. However, DA has not established yet a firm institutional channel to work with LGUs while LGUs need to have a national institution to work with on matters concerning agricultural extension policy, coordination, supporting, etc.,
- ✓ Complexities of extension services: In cope with weak capability of LGUs in providing agricultural extension services, various agencies are directly involved in providing the services to farmers. There is, however, an apparent disharmony of programs. Overlapping and redundancy of functions and activities of the agencies are often observed. Empowerment of LGUs is necessary for enabling them to play an expected role in agricultural extension under strategic and gradual implementation of the decentralization policy by the national government.

2.4 Irrigation System in MMIP

2.4.1 Irrigable area of MMIP

The Malitubog-Maridagao Irrigation Project (MMIP) was set out with the technical assistance in the feasibility study conducted from 1985 to 1988, which was financed by ADB. Initially, it was proposed to establish two independent projects with two (2) diversion dams at the Malitubog River and the Maridagao River to irrigate a total of 19,601 ha. Therefore, the project was named as the Malitubog-Maridagao Irrigation Project (MMIP), and even after the original two projects were merged into one having the Maridagao River as the only water resource, the project name was maintained. On the other hand, the management of a part of the original project was handed over to the Cotabato Irrigation Management Office (CIMO) under the NIA Region office XII, and this transferred part was named as the Maridagao River Irrigation System (MRIS).

MMIP was, due to the intermittent armed conflicts since 1970's which have affected the project sites, divided into two phases: the Phase-I (MMIP I) to irrigate 10,840 ha; and the Phase-II (MMIP II) to irrigate 8,760 ha. MMIP I was commenced in October 1989 with the signing of the Loan Agreement between the Government of the Philippines (GOP) and the Japan Bank for International Cooperation (JBIC). The general objectives of this irrigation development project were: 1) to increase rice production, 2) to reduce poverty through job generation, and 3) to contribute to the food sufficiency and sustainability in the region.



Irrigated paddy fields near the Maridagao River in the Upper Malitubog Service Area during rainy season 2016

The scope of MMIP I to generate 10,840 ha of irrigated area at Maridagao Service Area (MSA) and the Upper Malitubog Service Area (UMSA) included the construction of diversion facilities, right wing dike, left wing dike, diversion canal, bridge and siphon across the Maridagao River, irrigation and drainage facilities, canal service roads, access roads, temporary facilities, pilot demonstration farms, water master quarters, office buildings, a farmers training center, farmers quarters, and on-farm facilities, in addition to the provision of agricultural inputs and extension services as well as institutional development activities.

The implementation of the construction works under MMIP I started in April 1993. However, the Project was often interrupted due to recurring armed conflicts. Therefore, the MMIP I could finally complete the MSA and a part of UMSA (upstream) and handed them over to the MRIS Management Office of the Cotabato Irrigation Management Office (CIMO) only on October 31, 2011. It took more than 17 years from the commencement till the completion of the MMIP I.

Originally the planned gross area of MSA was about 6,562 ha. However,




Figure 2.4.1 Project Map of MMIP I and MMIP II

Source: NIA- PMO

according to the NIA Region XII and MMIP-PMO Joint Inventory Report submitted on October 7, 2003, in the course of project implementation, about 530 ha of water-logged area was identified. Of which, 306 ha was swampy through the year, and the remaining 224 ha was wet lands only in the rainy seasons and grassland during the dry seasons. Thus, the total area to be irrigated had to be reduced by 306 ha to 6,256 ha. In addition, another 695 ha was found not irrigable due to their higher elevations than the canal surface elevation. Thus, in the end the total area to be irrigated in MSA remained 5,561 ha.

According to the SAPROF report (May 2007)¹, a field inspection was carried out by walking through MSA to identify the actual conditions of the area in December 2006. As shown in the Figure 2.4.2, 4,715 ha of the cultivated area (green color) and 1,136 ha of submerged area, which could be divided into about 606 ha of water-logged area (light blue color) and 530 ha of swamp area (crisscrossed), were confirmed. In addition, the team identified 836 ha of flood prone area (light yellow color) adjacent to the Pulangi river, and other areas whose landowners opposed to irrigate their lands having coconut trees planted and houses established on them.



Figure 2.4.2 Land Use of Maridagao Service Area in Dec. 2006

Source: Final Report of SAPROF

According to the MRIS Management Office, as of April 2017, the net irrigable area for MMIP I is 7,173 ha, with the break-down of: 5,562 ha in MSA, and 1,611 ha in the MMIP I site of UMSA. On the other hand, the net irrigable area for MMIP II is 10,541 ha with the break-down of: 2,550 ha in the MMIP II site of UMSA, 6,849 ha in Lower Malitubog Service Area (LMSA), and 1,142 ha in Pagalungan Extension Service Area (PESA). Thus, the net irrigable area of the entire MMIP I and MMIP area comes to 17, 714 ha.

Table 2.4.1 Irrigable Areas of MMIP I and MMIP II

Service Area	Stage	Irrigable Area (ha)		Remark
		Original Plan	Current Plan	
Maridagao	Phase 1	6,562	5,562	5,562 ha is the net irrigable area
Upper Malitubog	Phase 1	4,278	1,611	1,611 ha is the net irrigable area
	(Phase 1) ↓ Phase 2	-	2,550	Originally the development of this area was to be undertaken under the Phase 1; however, was shifted to the Phase 2.
Lower Malitubog	Phase 2	7,618	6,849	
Pagalungan Extension	Phase 2	1,142	1,142	
Total	Phase 1	1,0840	7,173	
	Phase 2	8,760	10,541	
Grand Total		19,600	17,714	

Data Source: Project Completion Report, Malitubog Maridagao Irrigation Project, Stage 1 (Loan No. PH-P112) Year 2007
Malitubog Maridagao Irrigation Project II, Status of Construction as of May 15, 2017

2.4.2 Irrigation System of MMIP

1) Diversion Dam

All water volume required for the entire irrigation systems of MMIP I and MMIP II is taken from the

¹ Japan Bank for International Cooperation, 2007; Special Assistance for Project Formation (SAPROF) for Malitubog-Maridagao Irrigation Project (Phase-II)

Maridagao River through the diversion dam, which consists of 8 gates with concrete weir spillway structure. It is also equipped with 2 lanes of concrete bridge decks, 2 sluice ways with bascule type steel gates, 3 gate intakes with mechanically operated steel gates and trash rack, 650m-long right wing dike as well as 360m-long left wing. The elevation of the dike is set at EL35m (AMSL) to serve as reservoir at the same time, and the 65m-long fuse dike with the highest elevation of EL32.3m was designed to be collapsed by flood at EL34m level. In addition, the electro-mechanical apparatus are wired so that they can be operated from the operation house (for details, see Table 2.4.2).

Table 2.4.2 Specifications of the Diversion Dam



Description		Description	
I. Diversion Works		e) Sluice way	2 opening
a) Right Wing Dike (RWD)	Earth type	• Gate Type	Double leaf wheel type
• Length	650m	• Upper Lift	4.1m x 4.2m
• Height (maximum)	26.0m	• Lower Lift	5.0m x 4.2m
• Top Bank Elevation	EI 35.0m AMSL	• Top of Gate Elevation	EI 31.0 AMSL
• Width of Top bank	6.0m	f) Intake	3 openings
b) Left Wing Dike (LWD)	Earth type	• Gate Type	Vertical Slide
• Length	360m	• Height	1.75m
• Height (maximum)	11m	• Width	4.2m
• Top Bank Elevation	EI 35.0m AMSL	• Top of Gate Elevation	EI 29.75m AMSL
• Width of Top bank	6.0m	II. Reservoir	
c) Fuse Dike	Earth type	• Catchments Area	1,460 sq.km
• Length	65m	• Reservoir area	1.99 sq.km (WL31.0)
• Height (maximum)	1.8m	• Reservoir area/ volume	500ha/12.2 million cu m
• Top Bank Elevation	32.3m AMSL	• Design Flow Level	EI 32.50m AMSL
• Width of Top bank	4.0m	• Design Flood Discharge	1,600 cu m/s
d) Gated Spillway/Weir	8 openings	• Normal Operation Water Level	EI 31.00m AMSL
• Gate Type	Radial Type	• Upper Operation Level	EI 30.90m AMSL
• Height	3.9m	• Lower Operation Level	EI 30.70m AMSL
• Width	8.7m	• Intake Upper Water Level	EI 31.00m AMSL
• Top of Gate Elevation	EI 31.3m AMSL	• Intake Mean Water Level	EI 30.80m AMSL
		• Intake Maximum Discharge	35.9 cu m/s

Note: AMSL: above mean sea level

Data Source: Final Report (Volume II) of SAPROF for Malitubog-Maridagao Irrigation Project

2) Irrigation Canal Network

The entire MMIP beneficiary area is divided into 4 main Service Areas, namely MSA, UMSA, LMSA and PESA. UMSA can be further divided into 3 areas; Phase 1 area, Phase 2 area and an extension area. The irrigation canal network of these Service Areas consists of: 8 main canals with the total length of 117.7 km; 66 lateral canals with the total length of 165.8 km; and on-farm canal ditches with the total length of 748.9 km. The irrigation canal network is shown in Figure 2.4.3 and details of canals are also shown in Table 2.4.3 below.




Figure 2.4.3 Irrigation Canal Network in MMIP

Source of Base Drawing: NIA- PMO

Table 2.4.3 Length of Main Canal & Lateral Canal and Number of Turnouts in MMIP

Particular	Unit	MSA	UMSA (1)	UMSA (2)	LMSA.	PESA	Total
Diversion canal	km.	3.4					3.4
Main canal 2	km.	29.2					29.2
Left Main Canal	km.	13.5					13.5
Right Main Canal 1 (RMC 1)	km.		11.5	17.4	0		28.9
RMC1 - Extension No.1	km.			4.4			4.4
RMC1 - Extension No.2	km.			4.7			4.7
MC2	km.				22.5		22.5
MC3	km.				11.1		11.1
PMC	km.					7.3	7.3
Lateral & sub-lateral canal	Nos	19	5	9	30	3	66
Lateral & sub-lateral canal	km.	38.5	13.6	22.0	82.9	8.8	165.8
Turnout	Unit	186	52	82	69	28	417
Farm Canal (MFD & SFD)	km.	341.9	238.1	82.00	69.0	17.9	748.9

Data Source: NIA- PMO

The irrigation water taken from the diversion dam is carried through the diversion canal. At the bifurcation located at 3.4 km downstream from the intake, the water is distributed to the Left Main Canal and the Main Canal 2. The irrigation canal system in MSA covering 5,562 ha consists of: 2 main canals, namely, the Main Canal 2 with the length of 29.2 km and the Left Main Canal with the length of 13.5 km; and 19 lateral canals with the total length of 38.5 km. The Left Main Canal goes across the Maridagao river at the location of Sta. 4+635, and the name of the same canal is altered to the Right Main Canal 1 (RMC) when it enters into UMSA, after passing through the siphon.

The irrigation canal system in the MMIP I site in UMSA covering 1,611 ha consists of: the main canal, RMC 1 with the total length of 11.5 km from Sta. 0 to Sta.11+500, and 5 lateral canals with the total length of 13.6 km. The irrigation canal system in the MMIP II site in UMSA with 2,550 ha including the Extension area of UMSA consists of: the main canals, RMC 1 with the length of 17.4 km from Sta. 11+500 to Sta.28+900, RMC1 - Extension No.1 canal (RMC 1 - EXT-1) with the length of 4.4 km, RMC 1 - Extension No.2 canal (RMC 1 - EXT-2) with the length of 4.4 km; and 9 lateral canals with the total length 22.0 km. RMC 1 - EXT-1 is the only canal to supply the irrigation water to the Main canal No.2 & No.3 in LMSA. RMC 1 - EXT-2 is the canal to irrigate the Extension area of UMSA.

The irrigation canal system in LMSA to cover 6,849 ha consists of: Main canal No.2 (MC-2) with the length of 22.5 km; Main canal No.3 (MC-3) with the length of 11.1 km, which is derived from RMC 1 - EXT-1; and 31 lateral canals with the total length of 82.9 km. MC-2 will serve 3,224 ha of the eastern part of the service area while MC-3 is planned to serve 4,336 ha of the remaining middle and western parts of LMSA.

PESA originally formed a part of the Kabacan River Irrigation System. However, when the diversion canal running from the Pulangi river to the Liguasan Marsh was constructed, the area was left isolated from the Kabacan River Irrigation System. Therefore, the restoration of the irrigation canal system in PESA to cover 1,142 ha was planned to be carried out under MMIP II. The system consists of: the Pagalungan Main Canal (PMC) with the total length of 7.3 km, which is derived from the Lateral A of RMC 1; and 3 lateral canals with the total length of 8.8 km.



The location where PMC goes crossing the Pulangi River through a siphon structure (box size: 1.3m x 1.3m, length: 141 m).

3) Drainage System

The drainage system in MSA consists of: 3 main drainage canals with the total length of 24.3 km and 40 lateral drainage canals with the total length of 59.5 km. The total length of drainage canals in MSA reaches 50.0 km and their details are shown in Table 2.4.4. The drainage system in UMSA consists of: 3 main drainage canals with the total length of 34.4 km and 30 lateral drainage canals with the total length of 39.3 km. The total length of drainage canals in UMSA reaches 73.7 km and their details are shown in Table 2.4.5.

Table 2.4.4 Drainage Canal in MSA

Drainage canal	Length (m)	Drainage canal	Length (m)	Drainage canal	Length (m)
MDC I	10,330	LDC IC-1	1,856	MDC IA	4,662
LDC IA	3,197	LDC IC-2	2,080	MDC II	9,320
LDC IA-2	2,921	LDC IC-2A	1,243	LDC IIA	1,035
LDC IA-3	2,220	LDC ID	2,802	LDC IIB	1,720
LDC IA-3a	380	LDC ID-1	2,691	LDC IIC	5,260
LDC IA-4	2,467	LDC ID-1a	292	LDC IIC-1	2,720
LDC IA-4a	1,200	LDC ID-1b	449	LDC A	1,400
LDC IA-4b	1,280	LDC ID-2	980	LDC B	4,779
LDC IA-4c	957	LDC ID-3	940	LDC B1	1,706
LDC IA-8a	304	LDC IE	1,733	LDC B2	1,492
LDC IB	2,775	LDC IE-1	2,525	LDC EXTRA	1,996
LDC IB-1	814	LDC IE-2	713	LDC EXTRA-1	580
LDC IB-2	628	LDC IE-3	1,299	LDC EXTRA-2	1,100
LDC IB-3	465	LDC IE-4	932	Total of MDC	24,312
LDC IC	2,724	LDC IE-5	300	Total of LDC	59,453
				Total	45,995

Data Source: NIA PMO of MMIP II

Table 2.4.5 Drainage Canal in UMSA

Drainage canal	Length (m)	Drainage canal	Length (m)	Drainage canal	Length (m)
MDC KC	21,872	LDC KC-V	2,290	LDC PR-IVB-2	1,000
MDC LM	12,508	LDC KC-VI	1,616	LDC PR-IVC	1,200
LDC LM-I	3,728	LDC KC-EXTRA	2,200	LDC PR-IVD	697
LDC LM-II	7,168	LDC PR-I	1,948	LDC PR-IV-E	840
LDC LM-IIA	1,072	LDC PR-II	2,600	LDC PR-V	1,226
LDC KC-I	2,756	LDC PR-III	7,442	LDC PR-Va	470
LDC KC-II	3,180	LDC PR-IIIA	2,024	LDC PR-Vb	400
LDC KC-IIA	1,440	LDC PR-IIIB	1,565	LDC PR-Vc	763
LDC KC-III	3,040	LDC PR-IV	2,520		
LDC KC-IV	2,582	LDC PR-IVA	1,740	Total of MDC	34,380
LDC KC-IVA	2,752	LDC PR-IVB	1,040	Total of LDC	39,340
LDC KC-IVB	968	LDC PR-IVB-1	932	Total	73,720

Data Source: NIA PMO of MMIP II

The drainage system in LMSA consists of: 10 main drainage canals with the total length of 27.9 km and 20 lateral drainage canals with the total length of 24.7km. In addition, the construction of 14.7 km long Façade Drain, into which 8 of the main drainage canals flow, is planned as the last drainage canal pouring out to the Pulangi river under the framework of MMIP I & II. Construction of the 8.5 km long Kalawag Creek is also planned for the improvement on the drainage system in LMSA. The total length of drainage canals in LMSA reaches 75.8 km and their details are shown in Table 2.4.6. The drainage system in PESA consists of: only 4 main drainage canals with the total length of 14.5km, and their details are shown in Table 2.4.7:

Table 2.4.6 Drainage Canals in LMSA

Drainage canal	Length (m)	Drainage canal	Length (m)	Drainage canal	Length (m)
LDC A1	547	LDC D1	1,760	MDC E	2,562
LDC A2	1,079	LDC D2	1,220	MDC F	3,116
LDC A3	1,275	LDC D3	940	MDC G	2,871
LDC A4	882	LDC F	3,116	MDC H	2,296
LDC B1	2,746	LDC H1	1,824	MDC I	1,908
LDC B1	1,941	LDC H2	1,091	MDC J	1,066
LDC B3	651	LDC H3	883	Total of MDC	27,936
LDC B4	1,082	LDC H4	896	Total of LDC	24,657
LDC C1	874	MDC A	4,540	Total of MDC & LDC	52,593
LDC C2	1,161	MDC B	4,294	FAÇADE DRAIN	14,748
LDC C3	2,746	MDC C	2,871	KALAWAG CREEK	8,460
LDC C4	689	MDC D	2,412	Total	75,801

Data Source: NIA PMO of MMIP II

Table 2.4.7 Drainage Canal in PESA

Drainage canal	Length (m)	Drainage canal	Length (m)	Drainage canal	Length (m)
MDC LM I	3,714	MDC LM III	3,839		
MDC LM II	3,630	MDC LM IV	3,336	Total of MDC	14,549

Data Source: NIA PMO of MMIP II

4) Project Components of MMIP II

MMIP II started in January 2011 aiming at the generation of 9,784 ha of irrigable area in UMSA, LMSA and PESA and its target of the total irrigable area was later expanded to the 10,541 ha. As shown in Table 2.4.8, most of the target areas belong to Pikit Municipality and the total service area in Pikit reaches 9,208 ha, which corresponds to 87 % of the total target area under MMIP II. As of May 2018, the irrigable area which has been generated since the commencement of the project arrives at 5,513 ha, namely, about 53% of the project target. This consists of: 2,958 ha in UMSA, 1,567ha in LMSA and 988 ha in PESA and further details are shown in Table 2.4.9.

As of May 2018, the total area under operation is 1,478 ha, which is a part of UMSA. It includes the improvement area of 430 ha, where the water source was Chrislam dam in Panicupan before and was

changed to Lateral canal H of RMC 1. While for the irrigation area of 1,048 ha, water source came from Laterals canal E, F, G, I & J of RMC 1. The remaining area of UMSA which is irrigated by Lateral canals K, K Extension, L & M along RMC1 EXT.1 and RMC1 EXT. 2 will be turned-over soon. The Nalapaan Stream Check area, which was developed under MMIP II, covers 100 ha under operation by CIMO of Cotabato Province since 2012.

Table 2.4.8 Service Areas of MMIP II (by Service Area & Municipalities)

Service Area	Province	Municipality	Service Area (ha)		Farmer Beneficiaries					
			Original	Revised	Original	Revised				
UMSA	Cotabato	Pikit	2,015	2,206	2,359	2,550	343	649	694	750
		Aleosan	191		191		306		56	
LMSA	Cotabato	Pikit		6,590		6,849		1,937		2,014
PESA	Maguindanao	Pagalungan	634	988	788	1,042	186	291	232	336
		Datu Montawal	354		354		104		104	
		Total		9,784		10,541		2,877		3,100

UMSA: Upper Malitubog Service Area, LMSA: Lower Malitubog Service Area, PESA: Pagalungan Extension Service Area

Table 2.4.9 Progress in Generation of Irrigable Area in MMIP II (as of April 2017)

Service Area	Target	2011	2012	2013	2014	2015	2016	2017	2018	Total
UMSA	2,550	530	565	107	644	1,085	27	0		2,958
LMSA	6,849	-	-	-	-	10	599	341	617	1,567
PESA	1,142	-	-	-	-	988	0	0	0	988
Total	10,541	530	565	107	644	2,083	626	197		5,513
Cumulative		530	1,095	1,202	1,846	3,929	4,555	4,896	5,513	-

Data Source: Malitubog Maridagao Irrigation Project II, Status of Construction as of May 15, 2018

Note: UMSA: Upper Malitubog Service Area, LMSA: Lower Malitubog Service Area,
PESA: Pagalungan Extension Service Area

The project component of MMIP II is shown in Table 2.4.10; the total lengths of main canal and lateral canals are planned to be 66.8 km and 100.2 km totaling 167.0 km. The total numbers of the canal structures and the turnouts are planned at 207 and 412. For the on-farm development, construction of total 168.85 km of on-farm canals with 1,605 farm structure is planned. 323 steel gates for water management as well as the total length of 127 km of main and lateral drainage canals together with the total length of 94.18 km of farm drainage canals are also to be constructed in the project area.

Table 2.4.10 Project Components of MMIP II

Particular	Unit	UMSA	LMSA.	PESA	Total	Remarks
RMC1	km.	17.35	0		17.35	Main canal: 69.320 km. Revised to 66.772 km. Lateral canal: 113.660 km Revised to 100.263 km Total Canal 178.02 km Revised to 167.035 km.
RMC1 – Extra	km.		4.41		4.41	
MC2	km.		22.54		22.54	
MC3	km.		11.06		11.06	
Feeder Canal	km.			1.70	1.70	
PMC	km.			7.30	7.30	
Lateral & Sub Laterals	km.	22.00	82.86	8.8	113.66	
Canal Structure	Unit	85	100	22	207	
Turnout	Unit	82	69	28	179	Revised to 412 units
Farm Canal (MFD)	km.	82.00	69.00	17.85	168.85	
Farm Structure	unit	1,230		375	1,605	
Steel Gates	unit	98	194	31	323	
Access /Intra-site Road	km.	20.00		5.4	25.40	
Canal Service Road	km.	39.00			39.00	
Farm Bridge	unit		1		1	
Bridge & Siphon	unit			2	2	
Main Drain & Lateral Drain	km.	62	53	12	127	Revised to 119.96 km
Farm Drain	km.	82.00		12.18	94.18	Dev. Cost.
Estimated cost (M PhP)	Original	4,895.11		620.92	6,148.91	628 K/Ha.
	Revised	5,527.99		549.73	5,444.84	517 K/Ha.

Data Source: Monthly Progress Report of MMIP II, (May, 2018)

Note: UMSA: Upper Malitubog Service Area, LMSA: Lower Malitubog Service Area,
PESA: Pagalungan Extension Service Area

The completion date of the project was originally planned in December 2015, but it had been changed to December 2019 as of May 2018. The current progress of the project implementation is shown in Table 2.4.11 and Table 2.4.12. As of May 2018, the progress rate of the Project is evaluated at 45.9% on the basis of value of accomplishment and at 40.7% on the basis of actual expenditure.

The Project (MMIP II) to date constructed; 31 km in the main canal (RMC1&Ext.1&2, MC2&MC3; 52.6% of the total length planned), 46 km of lateral canals (46.3% of the total length planned), 221 canal structures (28.7% of the total units planned), 2.1 km of the drainage canal and main drainage canals (4.1% of the total length planned), 12.5 km of the lateral drainage canals (18.1% of the total length planned) and 24.3 km of farm canals (MFD & SFD; 14.4% of the total length planned).

Table 2.4.11 Progress in the Implementation of MMIP II

No	Particular (major facilities)	Unit	Plan		Progress (as of May 2018)	
			Original	Revised		
1	GENERATED AREA					
	Upper Malitubog Service Area (UMSA)	ha.	2,206	2,550	2,958	(116.0%)
	Lower Malitubog Service Area (LMSA)	ha.	6,590	6,849	806	(11.8%)
	Pagalungan Extension Service Area (PESA)	ha.	988	1,142	988	(86.5%)
	Total	ha.	9,784	10,541	5,513	52.7%
2	IRRIGATION FACILITIES					
	Main Canal (RMC1&Ext.1&2, MC2&MC3) -Lined canal	km.	60.320	59.336	31.212	(52.6%)
	Feeder Canal & Pagalungan Main Canal -Lined canal	km.	9.000	7.436	6.952	(94.5%)
	Lateral Canal - Earth canal	km.	113.660	100.263	46.435	(46.3%)
	Canal Structure	Unit	386	768	221	(28.7%)
	Additional Structure for Nalapaan & Panicupan	Unit	14	32	32	(100.0%)
	Canal Lining for Nalapaan & Panicupan	km.	4.258		4.274	(100.4%)
3	DRAINAGE FACILITIES					
	Protection Dike (PESA)	km.		8.778	5.157	(58.7%)
	Main Drainage Canal	km.	57.670	50.630	2.100	(4.1%)
	Lateral Drainage Canal	km.	69.330		12.528	(18.1%)
	Drainage Structure	Unit	3		3	(100.0%)
4	ON-FARM LEVEL FACILITIES					
	Farm Canal (MFD & SFD)	km.	168.850		24.337	(14.4%)
	Farm Structure	Unit	1,605			
5	ROAD NETWORK					
	Access Road/Intrasite Road	km.	25.400		0.360	(25.2%)
	Canal Service Road	km.	39.000			
6	OTHER MAJOR STRUCTURE					
	Farm Bridge	Unit	1			
	Bridge & Siphon	Unit	2			
	Improvement of Office Building	Unit	13		10.0	(76.9%)
	Watermasters Quarter	Unit	2		1.0	(50.0%)
7	FINANCE					
	Budget allocation	M PhP	6,148.91	5,444.84	3,991.35	(73.3%)
	Value of Accomplishment	M PhP			2,496.49	(45.9%)
	Actual Expenditure	M PhP			2,214.75	(40.7%)

Data Source: Monthly Progress Report of Malitubog Maridagao Irrigation Project II, (May, 2018)

Table 2.4.12 Progress in Civil Works (Contract Works and Direct Force Account) of MMIP II

Class/Item	Estimated Cost	Weight	Physical Accomplishment per Item	Expenditure/ Value of work	Remarks/ Actual Area Generated
	(MP)	(%)	(%)	(M PhP)	
CY2011					1,095 Ha.
a. Contract	95.922	57.21	100	93.158	Completed 2012
b. Force Account	66.073	42.79	100	66.073	Completed 2012
Total	161.995	100	100	159.231	
CY 2012 (Implemented 2013)					500 Ha.
a. Contract	347.193	94.26	100	347.193	Completed 2014
b. Force Account	21.157	5.74	100	21.157	Completed 2014
Total	368.350	100	100	368.350	
CY 2013					868 Ha.
a. Contract	135.125	77.33	100	128.052	Comp. Physically June 2015
b. Force Account	39.613	22.67	100	40.403	Completed 2015

Class/Item	Estimated Cost	Weight	Physical Accomplishment per Item	Expenditure/ Value of work	Remarks/ Actual Area Generated
	(MP)	(%)	(%)	(M PhP)	
Total	174.738	100	100	168.455	
CY 2014					495 Ha.
a. Contract	509.876	88.60	98.43	501.883	Ongoing
b. Force Account	65.624	11.40	100.00	58.003	Completed
Total	575.502	100	98.60	559.886	
CY 2015					1,825 Ha.
a. Contract	708.815	95.49	68.35	484.468	Ongoing
b. Force Account	33.470	4.51	92.45	30.944	Ongoing
Total	742.284	100	65.27	515.412	
CY 2016					570 Ha.
a. Contract	696.272	96.11	10.63	74.011	Ongoing
b. Force Account	28.145	3.89	5.93	1.670	Ongoing
Total	724.417	100	10.44	75.680	
CY 2017					152 Ha.
a. Contract	510.982	95.44	45.70	10.57	Ongoing
b. Force Account	24.414	4.56	100	71.23	Ongoing
Total	535.395	100	48.28	13.34	
CY 2018					8 Ha.
a. Contract	247.894	94.28	10	-	Ongoing
b. Force Account	15.044	5.72	20	21.20	Ongoing
Total	262.938	100	10.6	1.21	

Data Source: Monthly Progress Report of Malitubog Maridagao Irrigation Project II, (May, 2018)

2.4.3 Area Irrigated by Year and by Crop (MMIP I: MRIS)

Irrigation supply for Maridagao Service Area started in 2002, but was stalled in year 2003 due to deteriorated peace and order situation in the area. Actual operation and maintenance activities started in September 2004 with irrigated area of 3,832 ha (1,970 ha in the dry season and 1,861 ha in the wet season). Note that actual benefited area was 1,341 ha composed of 420 ha in the dry season and 921 ha in the wet season. Irrigated area and benefited area have been gradually increasing with completion of the remaining works for 1,611 ha in Upper Malitubog Service Area. From the dry season of 2013, the new additional service area of Crislam IA and Nalapani IA, which were generated under MMIP II, started supplying irrigation water.

On the current condition of the service area in the year 2016, as shown in Table 2.4.13, total service area of MRIS comes to 5,608 ha which is revised from the original service area of 7,173 ha, out of which 4,176 ha is in MSA which is also revised from original service area of 5,562 ha, and 1,431 ha is in UMSA revised from the original service area of 1,611 ha. The firm-up service areas (FUSA) of MSA and UMSA are 4,126 ha and 1,400ha respectively. Total firm-up service area (FUSA) reaches 5,527 ha.

Table 2.4.13 Current Condition of the Service Area in MRIS

Particular	Service area (ha)	Updated service area (ha)	FUSA (ha)	Operational area (ha)	Converted area (ha)	Remarks
MSA	5,562	4,176.49	4,126.14	3,165.08	50.35	Planted w/ permanent crops
UMSA	1,611	1,431.28	1,400.53	1,331.70	30.75	Planted w/ permanent crops
TOTAL	7,173	5,607.77	5,526.67	4,496.78	81.10	

Source: MRIS office (NIA Regional 12, Cotabato Irrigation Management Office)

Note: Updated service area is based on parcellary survey

FUSA is an abbreviation of "Firm-Up Service Area". It is the net service area of an irrigation system where converted areas and permanently non-restorable areas were deducted from the service area.

Operational area is the area within the FUSA where irrigation water can be served during the respective cropping seasons

As shown in Table 2.4.14, irrigated area/ planted area is 7,175 ha (4,115 ha in the dry season and 3,060 ha in the wet season), and therefore the annual crop intensity arrives at 130 % (74% in the dry season and 55% in the wet season). The benefited area comes to 5,941 ha (3,360 ha in the dry season and 2,580 ha in the wet season). Percentage of the benefited area to the irrigated area is estimated at 82 %

by the dry season, 84 % by wet season and 83% by annual. It means that over 80 % of irrigated farmland obtains the benefit, if the farmland can be irrigated.

Table 2.4.14 Actual Irrigated Area in Maridagao Service Area (MRIS)

Year	Service area (ha)	FUSA (ha) (Irrigable area)	Irrigated area/ Planted area (ha)			Crop intensity (%)			Benefited Area (ha)			Percentage of Benefited Area to irrigated area			Percentage of Benefited Area to FUSA		
			Dry	Wet	Annual	Dry	Wet	Annual	Dry	Wet	Annual	Dry	Wet	Annual	Dry	Wet	Annual
2004	5,562		1,970	1,861	3,832	35	33	69	420	921	1,341	21	49	35	8	17	24
2005	5,562		1,520	1,818	3,337	27	33	60	893	1,299	2,192	59	71	66	16	23	39
2006	5,562		2,110	2,247	4,357	38	40	78	1,324	1,980	3,304	63	88	76	24	36	59
2007	5,562		2,050	2,249	4,299	37	40	77	1,744	1,941	3,685	85	86	86	31	35	66
2008	5,562		2,745	2,508	5,252	49	45	94	1,815	2,115	3,930	66	84	75	33	38	71
2009	5,562		2,835	2,835	5,670	51	51	102	2,997	2,285	5,283	106	81	93	54	41	95
2010	5,562		3,069	3,415	6,484	55	61	117	2,646	3,088	5,734	86	90	88	48	56	103
2011	5,562	4,027	3,383	2,751	6,133	84	68	152	2,608	2,304	4,912	77	84	80	65	57	122
2012	5,562	4,027	2,896	1,087	3,983	72	27	99	2,454	908	3,362	85	84	84	61	23	83
2013	5,608	5,216	3,274	3,831	7,104	63	73	136	2,035	2,393	4,427	62	62	62	39	46	85
2014	5,608	5,608	3,868	4,369	8,237	69	78	147	2,935	3,684	6,618	76	84	80	52	66	118
2015	5,608	5,608	3,785	4,202	7,986	67	75	142	3,305	3,629	6,934	87	86	87	59	65	124
2016	5,608	5,527	4,115	3,060	7,175	74	55	130	3,360	2,580	5,941	82	84	83	61	47	107

Source: MRIS office (NIA Regional 12, Cotabato Irrigation Management Office)

Note: "Irrigated Area" is the area served irrigation water within the operational area of the FUSA during the respective cropping seasons (e.g. wet and dry seasons).

"Benefited/Planted Area" is the actual portion of the irrigated area that is planted with crops during the respective cropping seasons (e.g. wet and dry seasons).

"Cropping Intensity" is the ratio of the Irrigated area/ Planted area to the FUSA of an irrigation system.

2.4.4 Operation and Maintenance

In general, the operation and maintenance (O&M) of National Irrigation System is managed by the Irrigation Superintendent appointed under the Regional office of NIA. Maridagao River Irrigation System (MRIS) Management Office, which is in the Operation & Maintenance Section of Cotabato Irrigation Management Office (CIMO) under the NIA Region XII, has the responsibility of the operation of the irrigation system and maintenance of main structures such as diversion dam, siphon, main canal and lateral canal in service area of MRIS.

The MRIS Management Office is located near Pikit town. Table 2.4.15 shows the current staffing structure and appointment status of the MRIS management office. All the positions are filled with additional staff, e.g., three driver Mechanics, one utility worker. There are therefore not significant O&M constraints due to shortages in staff. MRIS management office has its own O&M manual which consists of Main System, Diversion Dam Operation and Maintenance, and Annexes. Based on the manuals, routine and monthly inspections are conducted.

Table 2.4.15 Staffing Structure of the MRIS Management Office

	Title	Major Responsibilities	Plan	Actual
1	Principal Engineer A	Direct supervision of the implementation and O&M	1	1
2	Senior Engineer A	Assistance in supervisory activities	1	1
3	Senior Irrigators Development Officer	Training/capacity building, strengthening of Irrigators' Associations	1	1
4	Senior Water Resources Facilities Technician	Maintenance of machinery and other mechanical equipment	4	4
5	Collection Representative A	Collection of irrigation service fees, developing plans and strategies to improve collection rates	1	1
6	Plant Electrician B	O&M of plant electrical system	1	1
7	Heavy Equipment Operator	Operation of heavy equipment	1	1
8	Accounting Processor A (Billing Check)	Accounting	1	1
9	Industrial Security Guard A	Safeguarding of properties, facilities and compounds	4	4
10	Data Encoder	Data input related to various acquired data and information	1	1
11	Driver Mechanic B	Mechanic maintenance and driving service	1	4
12	Water Resources Facilities Operator B	Operation of gates to regulate amount of water to store/needed	3	3
13	Utility Worker	Office maintenance	1	2
Total			21	25

Data Source: NIA-Region XII organizational structure and its authorized position (as of May 2017)

The O&M costs for the facilities and day-to-day operation activities are covered under the CIMO's and MRIS management office's budgets while the NIA Central Office has a budget framework to finance major maintenance and rehabilitation as needed. The financial status of MRIS is shown in Table 2.5.16. Approved corporate operating budget for MRIS is PhP 6,472,519 for personal service (PS) and 3,663,373 for maintenance and other operation expenses (MODE) for an average of past 5 years. However, as the operational area increases, the budget also increases; e.g., the budget allocated for 2016 reaches PhP7,612,183 for PS and PhP5,620,026 for MODE.

On the other hand, average expenditure for the past 5 years is PhP 6,751,339 for PS and PhP 1,978,511 for MODE, and thus the average total expenditure is PhP 8,729,850 per annum. Although the expenditure for MODE was over the budget in 2014 and 2015, it was within the total budget including the budget for personal service. The revenue-expenditure balance of the MRIS management office has been in deficit, which is average PhP 4,255,644 per year for the past 5 years. CIMO has supplemented MRIS' budgets for daily operation and maintenance activities while major rehabilitation was financed from NIA's maintenance and rehabilitation funds.

The irrigation area increases as the project progresses, and therefore the expenditure of MRIS for O&M of irrigation system will also increase in the future. As the Republic Act No.10969, Free Irrigation Service Act came to effect on February 2, 2018, it is necessary to secure new income sources such as government subsidies for sustainable and proper O&M of the irrigation systems in future.

Table 2.4.16 Approved Budget, Income and Expenditure of MRIS Management Office

Year	Approved corporate operating Budget		Income (PhP)				Expenditure (PhP)			Surplus (Deficit)
	Personal service	MODE	ISF	BA	Other Income	Total	Personal service	MODE	Total	
2012	5,779,032	2,609,375	1,848,872	255,055	48,640	2,152,567	5,395,783	1,822,022	7,217,805	-5,065,238
2013	5,880,914	2,609,375	1,622,258	192,506		1,814,764	5,986,886	1,166,075	7,152,961	-5,338,197
2014	6,074,527	3,589,243	5,227,666	371,060		5,598,726	6,701,645	2,978,442	9,680,087	-4,081,361
2015	7,015,940	3,888,844	7,246,351	608,366		7,854,717	8,168,644	2,374,430	10,543,074	-2,688,357
2016	7,612,183	5,620,026	4,701,830	216,923	31,500	4,950,253	7,503,736	1,551,586	9,055,322	-4,105,069
Total	32,362,596	18,316,863	20,646,977	1,643,910	80,140	22,371,027	33,756,694	9,892,555	43,649,249	-21,278,222
Ave.	6,472,519	3,663,373	4,129,395	328,782	40,070	4,474,205	6,751,339	1,978,511	8,729,850	-4,255,644

Source: MRIS office (NIA Regional 12, Cotabato Irrigation Management Office)

ISF: Irrigation service Fee, BA: Back account of Irrigation service Fee. MODE: Maintenance and other operation expenses

2.4.5 Irrigators Association and IMT

With the development of irrigation system, the operation and maintenance (O&M) of the facilities could be another crucial sphere to enhance irrigation performance, as well as, to sustain the facilities and ensure the water supply up to the end beneficiaries. In order to make irrigation facilities function equally to the upstream, midstream, and downstream water users, a joint management by the NIA and the farmers organized, through irrigation management transfer (IMT), is to be one of the solutions. Accordingly, NIA has been conducting IMT activities step by step according to the condition of each of the NIA irrigation systems. Establishment of IAs is, in fact, the first step for the IMT.

At the last stage of the construction for MMIP I, the initial 6 IAs were officially and legally established in Maridagao Service Area (legal registration with SEC was made in the period of 1999-2002). Since the original service area managed by each IA was large and number of the members was also many, as shown in Table 2.5.17, all initial IAs were latter divided into 2 IAs from 2006 to 2015. Service area of MRIS IA Div 5 Inc. is 903.3ha, however, operational area without swamp area is 309.6ha, so that the size of IA is of appropriate size. As of April 2017, 12 IAs are established in MSA.

Table 2.4.17 Transition of IAs in MRIS

SA	Original (at beginning)			Present (as of April 2017)			
	Name of IA	Service area (ha)	Date of restoration	No	Name of IA	Service area (ha)	Date of restoration
M S A	MRIS IA DIV. 1 INC	1,045.5	Aug. 1, 2008	1	GAGDANEN BAYA	349.17	Sep. 22, 2010
				2	TAFIA	211.34	Sep. 25, 2010
	KIFABRE IA INC.	1,070.3	Apr.1,-2001	3	KATINGKONGAN	394.86	Sep. 22, 2010
				4	MORNING LIGHT	377.67	Sep. 7, 2008
	MRIS IA DIV. 3 INC	1,053.0	Jan. 8, 2002	5	BASBIA	437.12	Sep. 21, 2011
				6	MANSAPA	202.27	Sep. 21, 2011
	KIPAN IA INC	745.7	Apr. 21, 1999	7	KIPAN	376.89	Apr. 15, 1999
				8	NASGIA	214.69	Sep 7, 2008
	MRIS IA DIV. 5 INC.	1,594.8	Jan. 8, 2002	9	MRIS IA DIV 5 INC	903.88	August 1, 2002
				10	NASFIA	168.46	Sep. 21, 2006
	MRIS IA DIV. 6 INC	1,052.8	Jan. 8, 2002	11	MRISIA DIV 6	353.73	Jan. 8, 2002
				12	EDUFIA	186.41	Apr. 5, 2015
U M S A	DIV 7		N/A	13	BAGONABATI	543.2	May 5, 2009
				14	BALATIKAN	496.8	Mar. 26, 2013
	DAM NALAPAAN STREAM CHECK		N/A	15	CRISLAM	339.3	Nov. 21,2011
				16	NALAPANI	52.0	Dec. 19, 2011
Total		6,562.0			Total	5,275.4	

Source: MRIS office (NIA Regional 12, Cotabato Irrigation Management Office)

Table 2.4.18 Irrigators Association in MRIS

No	Name of IA	Name of Service Area	Service Area (ha)	FUSA (ha)	Operational area (ha)	Number of FB's	Number of TSAG	Remarks
1	Gagdanan Baya	MSA	349.2	345.4	322.1	379	12	
2	Tafia		211.3	211.3	211.3	180	8	
3	Katingkongan		394.9	394.9	394.9	400	14	
4	Morning Light		377.7	377.7	249.0	240	13	
5	Basbia		437.1	432.9	288.0	330	11	
6	Mansapa		202.3	201.3	166.0	200	9	
7	Kipan		376.9	369.9	321.4	330	14	
8	Nasgia		211.1	211.1	211.1	185	10	
9	MRIS IA DIV. 5 Inc.		965.5	903.0	309.6	134	9	
10	Nasfia		135.0	165.6	165.6	165	9	
11	MRIS Div. 6		515.6	326.8	326.8	202	19	
12	Edufia		196.6	186.4	186.4	124	8	
13	Bagonabati	UMSA (P1)	543.2	641.0	641.0	680	33	
14	Balatikan		496.8	368.2	368.2	333	35	
15	Crislam, 1/	UMSA (P2)	339.3	339.3	283.7	316	11	Established under MMIP II
16	Nalapani, 1/		52.0	52.0	36.8	62	6	
No	Office Location	Barangay/S Covered	Date of registration	Number of farmer-member				
				Total	Christian		Muslim	
					Male	Female	Male	Female
1	Kilangan, Pagalungan	Kilangan	Sep. 22, 2010	274			272	2
2	Maridagao, Datu Montawal	Maridagao	Sep. 25, 2010	174			170	4
3	Kilangan Pagaungan	Kilangan	Sep. 22, 2010	254			250	4
4	Kilangan Pagaungan	Kilangan	Sep. 7, 2008	227			224	3
5	Nasapian. Carmen	Nabundas; Kibayao	Sep. 21, 2011	310			310	0
6	Nasapian. Carmen	Kibayao	Sep. 21, 2011	204			201	3
7	Kibayao, Carmen	Kibayao	Apr. 15, 1999	237			233	4
8	Kibayao, Carmen	Kibayao	Sep 7, 2008	192			190	2
9	Nasapian. Carmen	General Luna; Nasapian; Limbalod	August 1, 2002	124	68	22	30	4
10	Nasapian. Carmen	Nasapian	Sep. 21, 2006	127			124	3
11	Ugalingan, Carmen	General Luna; Nasapian	Jan. 8, 2002	217	107	15	91	4
12	Ugalingan, Carmen	Ugalingan	Apr. 5, 2015	63			56	7
13	Balabak, Pikit,	Bagonabati	May 5, 2009	581			576	5
14	Balatikan, Pikit	Balatikan	Mar. 26, 2013	336			333	3
15	Panicupan, Pikit	Crislam	Nov. 21,2011	261			255	6
16	Nalapaan, Pikit	Nalapani	Dec. 19, 2011	62			62	0

Source: MRIS office (NIA Regional 12, Cotabato Irrigation Management Office)

On Upper Malitubog Service Area, compared to MSA, the establishment of IA was delayed because the construction of the irrigation facilities was delayed. One IA was established under MMIP I and it was divided into 2 IAs in 2013. On the other hand, Crislam IA and Nalapani IA were established in

2011, which were the first service area generated under MMIP II. Total 4 IAs have been working within UMSA since 2013. As of May 2018, construction of the irrigation system in the MMIP II area of UMSA was almost completed and 5 IAs have been established and handed over to MRIS management office. The remaining 4 IAs will be handed over to MRIS management office in 2018. Accordingly, there are 13 IAs to be established in UMSA under MMIP I & II.

On PESA, as of May 2018, 3 IAs have been established and already registered. On Lowe Malitubog Service Area (LMSA), as of May 2018, 13 IAs were established and have been registered and remaining 8 IAs will be established in the coming years of 2019 and onwards.




Figure 2.4.4 Location of the IAs in UMSA (Ph.2)

Source: NIA-PMO

Table 2.4.19 Irrigators Association established under MMIP II

No	Name of IA	Name of Service Area	Location	Service Area (ha)	Number of FB's	Remarks
1	Dalfia	UMSA	Dalingaoen, Pikit, Cotabato	255.7	195	Turned-over
2	Tamcia		Takepan, Pikit, Cotabato	251.9	82	Turned-over
3	Lagundi Pambua		Lagunde, Pikit, Cotabato	283.0	162	Turned-over
4	Maliga Lupa		Bualan, Pikit, Cotabato	118.0	64	Turned-over
5	Paikol		Paidu Pulangi/Kolambog, Pikit, Cotabato	410.1	120	To be turned-over
6	Pamalian Taliawid		Pamalian, Pikit, Cotabato	116.9	78	To be turned over
7	Sarapani		Panicupan, Pikit, Cotabato	365.9	75	Turned-over
8	Chrislam		Panicupan, Pikit, Cotabato	339.3	316	Turned-over
9	Nalapani		Nalapaan, Pikit, Cotabato	52.0	72	Turned-over
10	Tapodoc Bangsamoro		Tapodoc, Aleosan, Cotabato	268.1	33	To be turned over
11	Dungguan-Langayen		Dungguan, Aleosan, Cotabato	191.0	28	To be turned over
12	Ubadala Farmers	PESA	Galakit, Pagalungan, Maguidanao	145.0	42	Registered
13	Layog Inug-Ug IA Inc		Layog, Pagalungan, Maguindanao	261.8	86	Registered
14	Pagalungan Taliawid		Pagalungan,, Maguindanao	N/A	40	Registered
15	Gli-Gli Lateral H & H2 Farmers	LMSA	Gli-gli, Pikit, Cotabato	292.0	163	Registered
16	Bulod Bulol		Bulod, Pikit, Cotabato	238.7	90	Registered
17	Talitay Inug-Ug Gli-Gli Poblacion		Talitay, Pikit, Cotabato	225.7	130	Registered
18	Batolawan Ginatilan Ladtingan		Batolawan, Pikit, Cotabato	362.4	82	Registered
19	Makauyag Gli-Gli Lateral H3		Gli-gli, Pikit, Cotabato	217.0	150	Registered
20	Maglib		Gli-gli, Pikit, Cotabato	481.0	171	Registered
21	Macabual Kaltan Farmers		Macabual, Pikit, Cotabato	190.1	95	Registered
22	Kaltan Balong Farmers		Balong, Pikit, Cotabato	268.5	95	Registered
23	Tambak Balong		Balong, Pikit, Cotabato	183.8	88	Registered
24	Manaulanan		Manaulanan, Pikit, Cotabato	172.7	70	Registered
25	Proper Macabual		Macabual, Pikit, Cotabato	122.7	78	Processing for registration
26	Sitio Galigayenen		Macabual, Pikit, Cotabato	245.0	89	Processing for registration
27	Nalkatan Manaulanan		Manaulanan, Pikit, Cotabato	371.3	N/A	Processing for registration

Source: MRIS office (NIA Regional 12, Cotabato Irrigation Management Office), NIA-PMO

As part of the IA-NIA relationship in the National Irrigation System (NIS), an IA is required to prepare a cropping calendar, a water distribution and delivery plan, and a maintenance and repair plan pursuant to the NIA irrigation system design guidelines. Among these requirements, a maintenance and repair plan is expected to show how the IA conducts maintenance works to the irrigation systems, such as canal clearing, desilting, road repairing and grading, debris removal and oiling of steel gates.

2.5 Distribution Infrastructure; Road and Bridges

On April 14, 2014, a memorandum was issued by the then Secretary of DPWH regarding the new road classification system as well as the route numbering to all primary roads, that has been extended to secondary roads at present. This new road classification and route numbering system was then implemented and incorporated in the Road and Bridge Information Application (RBIA) in compliance with the said memorandum. The classes of roads have included national roads, provincial roads, municipal and city roads, Barangay roads, and expressways. The table below provides the criteria for each of these classes of road:

Table 2.5.1 Criteria of Road Classification in the Philippines

Category	Contents
National Primary	✓ Directly connects major cities (at least around 100,000 people) (Cities within metropolitan areas are not covered by the criteria)
National Secondary	<ul style="list-style-type: none"> ✓ Directly connects cities to National Primary Roads, except in metropolitan areas ✓ Directly connects major ports and ferry terminals to National Primary Roads ✓ Directly connects major airports to National Primary Roads ✓ Directly connects tourist service centers to National Primary Roads or other National Secondary Roads ✓ Directly connects cities (not included in the category of major cities) ✓ Directly connects provincial capitals within the same region ✓ Directly connects major National Government Infrastructure to National Primary Roads or other National Secondary Roads
National Tertiary	✓ Other existing roads under DPWH which perform a local function
Provincial Roads	<ul style="list-style-type: none"> ✓ Connect cities and municipalities without traversing National Roads ✓ Connect to National Roads to barangays through rural areas ✓ Connect to major provincial government infrastructure
Municipal and City Roads	<ul style="list-style-type: none"> ✓ Roads within Poblacion ✓ Roads that connect to Provincial and National Roads ✓ Roads that provide inter-barangay connections to major Municipal and City Infrastructure without traversing Provincial Roads
Barangay Roads	✓ Other Public Roads (officially turned over) within the barangay and not covered in the above definitions
Expressways	✓ Highways with limited access, normally with interchanges; may include facilities for levying tolls for passage in an open or closed system.

Source: Department of Public Works and Highway

2.5.1 Roads in and around the Project Area (Pikit Municipality)

As most of the MMIP II area falls in Pikit municipality jurisdiction, following discuss the road network in the municipality. In the Pikit municipality, there is one primary national road running between Cotabato city and Davao city via Pikit town. The MMIP II area extends in southern parts from the national road while MMIP I area is located in northern parts from the national road (see Figure 2.5.1).

Table 2.5.2 summarizes the roads within the Pikit municipality as of year 2018 or 2016 by type according to the afore-mentioned category, and also by pavement type.




Figure 2.5.1 MMIP Area and National Road Network

Source: DPWH

Table 2.5.2 Status of Road Infrastructure in Pikit Municipality

Road Name	No.	Pavement Type and Road Length				Total (km)
		Concrete (km)	Asphalt (km)	Gravel (km)	Earth (km)	
National Road (as of 2018)	2	12.5	0.0	0.0	0.0	12.5
Provincial Road (as of 2016)	14	3.9	2.0	43.3	18.8	67.9
Municipal Street (as of 2018)	35	8.8	1.2	10.3	3.1	23.4
Barangay Road (as of 2018)	71	26.2	1.0	167.4	45.0	239.6
Total	122	51.4 (15%)	4.2 (1%)	221.0 (64%)	66.9 (20%)	343.4 (100)
(Total of 2015)	122	33.6 (10%)	4.2 (1%)	229.4 (67%)	74.4 (22%)	341.6 (100)

Source: Pikit Municipality

As in the above table, there are 2 national roads within the municipality; namely, Cotabato-Davao National Highway as afore-mentioned and Dualing-Silik Tertiary National Highway, total length of which comes to only 12.5 km. Provincial roads count at total 14 in number, and the total length arrives at 67.9 km composed of 3.9 km concrete road, 2.0 km asphalt road, 43.3 km gravel road and 18.8 km earth road. More than half length of the provincial roads is, in fact, of gravel (43.3 km) and earthen (18.8 km).

There are 35 municipal roads, total length of which is 23.4 km composed of 8.8 km concrete, 1.2 km asphalt, 10.3 km gravel and 3.1 km earthen. Barangay roads are extended over 71 routs with a total length of as much as 239.6 km. Though the barangay road is the longest one among the 4 categories roads, more than 200 km length (about 89%) is constructed with gravel and earthen.

By type of the roads, gravel road shares as much as 64% of the whole roads within the municipality, followed by earthen road with 20% share, and concrete with only 15%. Note that asphalt pavement roads consist of only 1% of whole roads within the municipality. With this status of the roads, especially, the earthen and gravel roads become hardly passable during rainy season (see photo as an example). With respect to the change from year 2015 to 2018, concrete pavement road was increased by 17.8 km (increased by 5%) from the gravel road and earthen road.



A typical Barangay Road in LMSA, becoming hardly passable during rainy season

2.5.2 Bridges in and around the Project Area (Pikit Municipality)

Following table indicates bridges within Pikit municipality as at year 2018. There are total of 10 bridges in the municipality, composed of 4 concrete bridges and 6 RC box culverts. In fact, concrete bridges are constructed on the national roads and provincial roads while barangay roads are equipped with only RC box culvert. The roads, extended in Pikit municipality, have a lot of small scaled crossing structures which cross the creeks and drainages etc. However, Table 2.5.3 doesn't include such a small structures due to the structural perspective, namely the small conduits (concrete pipe or corrugated steel pipe etc.) could not be categorized as the bridge.

Table 2.5.3 Status of Bridges in Pikit Municipality, as of 2018

Bridge Name or Name of Road Section (where bridge is located)	Bridge Type and Bridge Number & Average Length (as of 2018)				Total
	Concrete Bridge	Steel Bridge	Timber Bridge	RC Box Culvert	
Along the National Road	2 (L=8.0m)	0	0	0	2
Along the Provincial Road	2 (L=6.5m)	0	0	0	2
Along the Municipal Street	0	0	0	0	0
Along the Barangay Road	0	0	0	6 (L=4.0m)	6
Total	4	0	0	6	10

Source: Pikit Municipality

2.6 Related Projects and Programs

NIA has implemented in addition to own government funded projects, number of loan projects for irrigation development assisted by such donors as JICA, World Bank (WB), Asian Development Bank (ADB), among others. NIA has also received JICA Technical Assistance Programs (TA) for the irrigation improvement. The following table summarizes a list of major donor-assisted projects implemented by NIA:

Table 2.6.1 Major Donor-Assisted Projects by NIA

Donor	Period	Project Name	Type	Project Area
JICA	2012-2017	National Irrigation Sector Rehabilitation and Improvement Project (NIS RIP)	Loan	Nationwide including Region XII
World bank	2009-2024	Participatory Irrigation Development Project (PIDP)	Loan	Nationwide including Region XII
ADB	2000-2011	Southern Philippines Irrigation Sector Project	Loan	ARMM, Caraga, Region-VI, VII
JICA	2005-2007	Irrigation Association Strengthen Project	TA	Nationwide
JICA	2007-2011	Irrigators Association Strengthening Support Technical Cooperation Project	TA	Nationwide
JICA	2013-2017	The Project for Improving Operations and Maintenance of NIS	TA	Nationwide

Source: NIA Headquarters

2.6.1 National Irrigation Sector Rehabilitation and Improvement Project (NIS RIP)

NIA is currently implementing the NIS RIP financed by JICA ODA loan for the rehabilitation of 11 National Irrigation Systems (NISs). In addition to the rehabilitation and improvement of existing facilities, the NIS RIP covers IAs institutional development including promotion of Irrigation Management Transfer (IMT), agricultural support by PhilRice and O&M equipment procurement as the project components. Irrigable scale of each irrigation system and components of the NIS RIP are similar to those of MMIP II.

While NIS RIP is still under implementation as mentioned above, some delays in the civil works have been found from the original plan. Some issues have been identified for the reasons and these would be the lessons learned for the MMIP II project implementation. Issues and lessons learned from the NIS RIP are abstracted as below, and these issues would be kept in mind for the implementation of the MMIP-II civil works:

- 1) Long period for the tendering and contracting process: There were cases it took several to 6 months from the bid opening to the contract conclusion due to the staff limitation of both NIA and local contactors. At least, NIA should allocate enough staff to evaluate the bidding or otherwise need to employ consultants in the areas of procurement.
- 2) Construction materials/machineries/manpower: Deployment of heavy machineries at necessary timing for effective construction works was very often difficult for small scale contractors. It was also found that there were difficulties for small scale contractors in securing necessary manpower due to low financial condition. To improve this issue, capably contractors should be selected, e.g. employing bigger scale of contractors rather than employing many small-scale contractors (also refer to the statement blow in terms of packaging).
- 3) Low capacity of local contactors: Since the package volume of civil works was divided into small scale, small or medium scale local contractors were mostly selected. These small or medium scale contractors are characterized with relatively lower capacity both in terms of technical and financial aspects. Financial limitation affected their construction performance in terms of both construction quality and also schedule. From this experience, it will be an option to increase the scale of one contract package, so that large scale contractors from Manila or other major cities could be

interested in the project implementation.

- 4) Pre-Qualification (PQ) setting for the selection of contractor: NISRIIP set such term of contractors who can participate the bidding that the contractor shall have experiences of similar projects and shall be 3A rank in PQ. In order to prevent the selection of low capacity contractors, careful consideration should be necessary for the PQ setting in MMI II implementation, e.g. employing 3A rank contractors also with due reference to the similar experiences. It is noted that though large scale contractors are generally very much experienced in large scale civil works, those civil works may be associated with road/ bridge sector while less irrigation works implemented in very remote areas. Such similar experiences relative to irrigation sector and works in rural areas should be well taken into account.

2.6.2 Participatory Irrigation Development Project (PIDP)

NIA and World Bank (WB) are implementing PIDP since year 2009. APL (Adaptable Program Loan) was applied to the PIDP to support NIA's transformation with a long-term sector reform by three-phase implementation. PIDP APL Program components consist of; 1) irrigation sector restructuring and reform, 2) irrigation infrastructure development for 58 NISs, and 3) project management and coordination. Under component 1), NIA and the World Bank are implementing NIA Rationalization Plan (RAT Plan), NIA institutional strengthening and also irrigation management transfer (IMT) program.

NIA and WB have extended phase-1 period by two years because of the expansion of rehabilitation works for NISs which were damaged by typhoon Yolanda (November 2013). Although civil works have not been completed yet, RAT plan implementation and IMT program implementation have already accomplished their targets. IAs have been organized in all the 58 project-assisted NISs and 98%¹ IAs have successfully closed IMT program contacts for transferring of increased operation and maintenance (O&M) responsibilities under models 2-4² with institutional development training provision to IAs. For the designing and enhancement of IAs in MMIP II, example of the IMT application to IAs could be a reference, and their activities on RAP and IPP (Indigenous People Plan) would also be a reference to the MMIP II preparation.

2.6.3 Southern Philippines Irrigation Sector Project

NIA and Asian Development Bank (ADB) have implemented the project from 2000 to 2011. Project components consisted of infrastructure and institutional development. Infrastructure component covered development of NISs, CISs, SRISs (small reservoir irrigation systems) and construction of access and service roads. Institutional component was divided into two categories; one is participation for and irrigation transfer to IAs in the O&M and another one is the training for NIA and LGU staff. The project also undertook social activities including; 1) schistosomiasis control as a primary health measure, and 2) development of indigenous peoples development plan for Maranaos irrigation system in ARMM.

¹ Implementation Status & Results Report on 7th March 2017, WB

² NIA classified IMT models into 4 levels depending on the size of NIS and capacity of IAs;

Model 1: Maintenance of canals delegated to IAs; IA is compensated based on canal area maintained and existing labor rate,

Model 2: Turnover of management of lateral canals to IAs; IAs get a share of Irrigation Service Fee (ISF) collected (Typical ISF sharing: NIA 70%, IA 30%),

Model 3: Turnover of management of main and lateral canal to IA Federation; IAs get a share of Irrigation Service Fee (ISF) collected (Typical ISF sharing: NIA 70%, IA 30%), and

Model 4: Complete turnover of Irrigation system to IAs; IAs pay NIA a rental fee at a rate of 75-100 kilograms of dry palay per hectare per year.

As the lessons learned from the said project, it was raised that the project erroneously estimated that the farmers in the project area could contribute 25% of the capital cost of the irrigation systems without conducting a thorough assessment of their paying capacity. The resulting resource limitations meant that fund would not be sufficient for routine and periodic maintenance of the project-funded infrastructure.

This lesson should be reflected in the O&M plan to be designed for MMIP II. In fact, it is estimated that MMIP beneficiaries are relatively poorer as compared to other areas of Philippines, and therefore financial burden, if required, for the beneficiaries should be set at minimal level at least during the construction phase as well as for several years after the project operation, i.e. until the time the project generates planned benefit.

Regarding other lessons, for example, importance of the participation of beneficiaries at an early stage was pointed out in preparing sub-projects under the Southern Philippines Irrigation Sector Project. In addition, coordinated provisions of technical supports to beneficiaries were also raised as one of important issues along with supplies such as firm credit. MMIP II should likewise inform the beneficiaries of the project implementation well in advance, and also coordination with agriculture extension organizations should be well established.

2.6.4 JICA Technical Cooperation Project

JICA has conducted series of TAs in the field of irrigation operation and management. Irrigation Association Strengthen Project (2005-2007) and Irrigators Association Strengthening Support Technical Cooperation Project (2007-2011) had been conducted focusing on capacity enhancement of IAs. As the lesson learned from Irrigators Association Strengthening Support Technical Cooperation Project, organized coordination was found very important among the stakeholders. Especially, functional SMC (System Management Committee) consisting of NIA officer, LGU, IDO (Institutional Development Officer), etc. is very important for decision making in terms of water distribution, cropping pattern setting, and effective O&M.

On the other hand, the Project for Improving Operations and Maintenance of NIS (2013-2017) focused on the promotion of efficiency and modernization of NIA's O&M activities for irrigation systems in order to cope with the situation of curtailed O&M staff by Rationalization Plan (RAT Plan) enforced since year 2008. Project component was planned to utilize GIS for O&M activities, to introduce Asset Management (AM) concept and improve fair Water Distribution and Delivery (WDD) in the selected pilot sites. Project output could be a reference for future O&M of MMIP II.

2.6.5 Other Related Project in Neighboring Area of MMIP II

JICA is conducting various projects for peace building and rural development for ARMM area under umbrella of J-BIRD program. JICA has conducted the Technical Cooperation Project for Rice-Based Farming Systems Trainings and Support Program for ARRM with PhilRice during 2005-2010 and continues extension activities as of 2017-2018. Project succeeded in training farmers for farming techniques both rice and vegetable and achieved their income improvement by 96% from rice production and by 103 % from vegetable production according to the terminal evaluation report in 2009. As the reason for good result, it was referred to the provision of suitable techniques and efficient project management by the PhilRice. Possible linkage with PhilRice could be a good option for the improvement of rice production under MMIP II.

The Project for Community Development in Conflicted Areas (2015-2017), which is a grant project for improvement of farm to market roads, is under implementation with Department of Agriculture (DA). Barangay/municipal roads and related river crossing (bridges, box culvert) are being rehabilitated or constructed by local contractors as of 2017. Project information such as design

condition, construction schedule, performance of local contractors, etc. could be a reference for the planning and construction of the farm-to-market roads under MMIP II. In addition, the project involves Bangsamoro Development Agency (BDA) as the cooperating agency for the linkage of municipality which is the implementer of future O&M of the constructed roads. Such implementation arrangement can be a reference for the MMIP II.

JICA is also currently conducting a Cooperation Project on Comprehensive Capacity Development Project for the Bangsamoro (2013-2019). The Project conducted Quick Impact projects (QIPs) cooperating with Bangsamoro Transition Commission (BTC) and BDA. QIPs have engaged great number of community people actively with the cooperation of BDA regional office.

CHAPTER 3 DELINEATION OF LMSA WITH FLOOD PROTECTION MEASURES

3.1 Past Flood Occurrence and Its Magnitude on LMSA

3.1.1 Basin Area Covering the Project Area

Basin area covering the Project area (or Liguasan marsh) is as large as about 13,700 km². According to the historical record in and around the basin area, the mean rainfall on the catchment area of the basin is 2,016 mm/year during the past 66 years from 1951 to 2016. The total rainwater in the basin is thus estimated at 28 billion CUM per annum (13,700,000,000 x 2.016). Applying the runoff coefficient of 0.3 according to the analysis of Tinutulan gauging station (refer to sub-section 2.1.4), discharge volume becomes 8.3×10⁹ m³/year. Such copious amount of water concentrates on the Liguasan marsh which behaves as receptacle although it covers only 1 % of the basin area (156 km² / 13,700 km²).

The recent deforestation and the development of agricultural land have changed the flood condition of the basin, namely, flood event tends to occur more frequently and its damage becomes more serious. Moreover, because of the recent tendency of heavy rainfall, soil erosion occurs and heavy siltation has been taking place along the rivers within the basin. This siltation can also be seen in the main channel of the Pulangi river, where natural levees have been developed along the southern boundary of the Project area, the LMSA. Besides, grasses and debris conveyed by flood would be clogging the water course in particular at the outlet of the Liguasan marsh.



Figure 3.1.1 Watershed Area for the Project Area
Source: JICA Survey Team

3.1.2 Channel Change in the Pulangi River

The long-term channel change in the Pulangi river can be observed on Google’s “Earth Engine Timelapse”¹ which provides true color scenes over the whole earth covering 33 years between 1984 and 2016. The images of 1984, 2000, and 2016 in Figure 3.1.2 were captured on the browser and the URL is



URL: <https://earthengine.google.com/timelapse/#v=7.00335,124.64905,11.176,1atLng&t=0.03>
Source: Google Earth Engine Team, 2015. Google Earth Engine: A planetary-scale geospatial analysis platform. <https://earthengine.google.com>

Figure 3.1.2 River Channel Change in the Pulangi River (1/2)


¹ <https://earthengine.google.com/timelapse/>

linked to Timelapse page zooming in LMSA. According to the images available on Timelapse, the Pulangi river channel bordering the LMSA has not radically changed between 1984 and 2016. It is assumed that, owing to the construction of the Diversion Channel in Tunggol in early 1980s, the flow volume into the lower stream of the Pulangi river in the south of Pikit municipality had decreased, which may have resulted in much less change in the course of the Pulangi river.

3.1.3 Long Term Water Occurrence Change


Data of the surface water on the Liguasan marsh was obtained from the analytical result of ‘Mapping long-term global surface water occurrence²’ which utilized millions of LANDSAT images for a period of 32 years from 1984 to 2015. The spatial resolution is 30 m and it was recorded when water was presented, where the occurrence has changed, and how its location changed in terms of seasonality and continuity.

As for the adjacent area to the Project area, specifically in the LMSA, the water occurrence could be traced in both sides of the Pulangi river. The coverage of the water surface has been changing by season. In rainy season, the flood water spilling over natural levees and flowing into the hinterland on the right side of the Pulangi river as temporal waters. In dry season, on the other hand, permanent water remains only along the main channels in the left side of the Pulangi river as shown in Figure 3.1.3.



URL: <https://earthengine.google.com/timelapse/#v=7.00335,124.64905,11.176,latLng&t=0.03>
 Source: Google Earth Engine Team, 2015. Google Earth Engine: A planetary-scale geospatial analysis platform. <https://earthengine.google.com>

Figure 3.1.2 River Channel Change in the Pulangi River (2/2)



Source: High-resolution mapping of global surface water and its long-term changes (Jean-François Pekel et al., Nature 540, 418-422, 15 December 2016)

Figure 3.1.3 Long Term Water Occurrence Change (1984-2014)

Source: JICA Survey Team

² High-resolution mapping of global surface water and its long-term changes (Jean-François Pekel, Andrew Cottam, Noel Gorelick & Alan S. Belward, Nature 540, 418-422, 15 December 2016)

3.1.4 Seasonal Change

Regarding the seasonal change, the prominent change was found as shown in Figure 3.1.4. In the climax of the rainy season, the most of areas are once covered by water at least for one month. However, in the dry season, only several separate ponds and channels remain on the area deeply depressed along the main tributaries. The area of permanent water is estimated at only 1,570 ha, which covers only 10% of the maximum water extent in the rainy season.




Figure 3.1.4 Seasonality of Water Surface (1984-2014)

Source: JICA Survey Team

In the history of water extent revealed by the satellite imageries of 32 years, the seasonal change on the right bank can be regarded as ‘New seasonal area’, which has turned to a wet-land from the dry land during the last 3 decades. On the other hand, the left bank area is characterized as ‘Lost permanent area’ which has interrupted or dried-up water in dry season.

3.1.5 Maximum Flood Water Extent and Inundation Ratio of LMSA

The maximum water extent image was made by a composite image which provides information of detected water on all locations ever over the 32 years from 1984 by 2015. The “light blue” parts in Figure 3.1.5 shows an area of the maximum surface water extent.

The maximum water extent was not analyzed by a certain flood event but estimated based on multiple images in long period. The images applied were acquired from LANDSAT’s archive data which provide as 16 days interval in line with sun-recurrent orbit. However, the acquisition follows periodic orbit and the number of images for the analysis reached to several hundreds at different timings. These acquired images could give sufficient information in pixels bases (10m x10m) during 32 years even to understand a time series changes of water condition whether it was being in dry or wet condition all over the Project area.




Figure 3.1.5 Flood Area and Recurrence of Annual Behavior of Water Surface (1984-2014)

Source: JICA Survey Team

Although the flood area shown in Figure 3.1.5 was delineated as combined water pixels which had been experienced in wet condition at least one time during 32 years since 1984, its extent was concordant with the past inundation records of factual inundated area and depth in 2008’s flooding (NIA, 2010). The flood area shown in Figure 3.1.5 broadly covers almost the half of the LMSA by the

damming-up, which spreads from the narrow outlet channel at Paidu Pulangi. Note that a part of water inundating the southern parts of the LMSA comes back from Paidu Pulangi area, not only the direct flood water from the Pulangi river running along the southern side of the area due to elevation difference.

Dark blue color in Figure 3.1.5 shows the water extent in 50% of recurrence, i.e. return period 2-year, which can be regarded as normal hydrological year, while light blue color parts show the maximum water extent for the last 32 years based on the 16-day satellite image interval. As summarized in the following Table 3.1.1, 50% occurrence inundation area shares about 60 % to 90 % of the maximum water extent with the overall coverage of 78% (see the column of Rate (c)/(d)) for the whole LMSA.

On the other hand, the ratio between the 50% occurrence water extent and the total area comes to 0 – 55 % with the overall average of 34% (see the column of Rate (c)/(e)). It means that during the normal hydrological year, 34% of the LMSA had been inundated, leaving only 66% as surface land. Likewise, the ratio between the maximum occurrence of water extent and the total area comes to 0 – 63 % with the overall average of 44% (see the column of Rate (d)/(e)). It means that during the maximum water extent year, 44% of the LMSA had been inundated, leaving only 56% as surface land. Concerning the originally requested ODA target area located at most eastern part of the LMSA, the inundated areas reached 32% and 53% respectively for the 50% occurrence and maximum water extent occurrence.

Table 3.1.1 Water Area on LMSA in Normal Year (probability: 50%) and Maximum Water Extent

Flooding Area (ha)	Map Symbol	Remained Land area (a)	Water area on RP* (probability)			Rate (c)/(d)	Rate (c)/(e)	Rate (d)/(e)	Total Area (e)
			> 2 year (< 50%) (b)	< 2year (>50%) (c)	Max. water extent (d)				
LMSA construction area									
Construction from 2017	2017_1	800	186	1,191	1,378	86%	55%	63%	2,177
Construction from 2017	2017_2	321	1	5	6	83%	2%	2%	327
Construction from 2015	2015	1,573	43	131	174	75%	7%	10%	1,748
ODA requested area	ODA	1,222	540	841	1,381	61%	32%	53%	2,603
Construction from 2016	2016_1	1,069	122	991	1,114	89%	45%	51%	2,183
Construction from 2016	2016_2	164	0	0	0	-	0%	0%	164
Total		5,149	892	3,160	4,052	78%	34%	44%	9,201

Note: *RP: Return Period
Source: JICA Survey Team

3.1.6 Elevation Corresponding to the Maximum Flood Area

1) Elevation Corresponding to the Maximum Flood Area by Topographic Map

NIA-PMO has a topographic map of 1/4,000 scale covering whole LMSA which was made during the detail design. It is the significant material because it covers the most western part of the LMSA, which is very close to Paidu Pulangi mentioned above. The maximum flood area detected by satellite image analysis for the 32 years from 1984 to 2015 is now overlaid on this topographic map (show Figure 3.1.6). By reading the contour lines where the




Figure 3.1.6 Overlaid Maximum Inundation Line with the Topo Map

Source: JICA Survey Team

peripheral of inundation has reached, it is known that the past highest water levels had come to around 6.4 m AMSL.

2) Elevation Corresponding to the Maximum Flood Area by DEM

There are digital elevation maps available with 1.0 m contours³. Of them, Shuttle Radar Topography C-band data are available to the public. The radar contains two types of antenna panels, C-band and X-band. The near-global topographic maps of Earth called Digital Elevation Models (DEMs) are made from the C-band radar data. These data were processed at the Jet Propulsion Laboratory and are being distributed through the United States Geological Survey's Earth Resources Observation and Science (EROS) Data Center.

Figure 3.1.7 was produced with the free DEM data, on which the maximum inundation area detected by the satellite in the past 32 years was overlaid (pink colored portions show the maximum inundation areas while the white ones indicate permanent water body). Also, H-V (height-volume) and H-A (height-area) relations were generated based on the DEM data. With reference to the DEM data and H-A relationship, the elevation to which the past maximum inundation reached was estimated. According to the interpolated estimation, the highest inundation level is around 6.60 m AMSL.




Figure 3.1.7 DEM and Max. Water Extent

Source: JICA Survey Team, Jet Propulsion Laboratory

Table 3.1.2 Estimation of Past Maximum Inundation Elevation with DEM Data

El.	Area (m2)	A (ha)	Cumulative Area (ha)	Volume (MCM)	Height (ELm)	Remarks
1	256,375	26	26	0	1	
2	22,790,746	2,279	2,305	23	2	
3	691,538	69	2,374	24	3	
4	3,645,171	365	2,738	27	4	
5	15,519,410	1,552	4,290	43	5	
6	70,948,932	7,095	11,385	114	6	
	Max Water Extent		15,609	156	6.595	
7	71,046,715	7,105	18,490	185	7	
8	64,836,613	6,484	24,974	250	8	
9	114,142,418	11,414	36,388	364	9	
10	150,383,190	15,038	51,426	514	10	
11	147,992,116	14,799	66,225	662	11	
12	127,524,574	12,752	78,978	790	12	

Source: JICA Survey Team, Jet Propulsion Laboratory, US

³ <https://www2.jpl.nasa.gov/srtm/dataproduct.htm>.

3.1.7 Past Design Flood Water Level

NIA-PMO has been carrying out the detail design for the LMSA. This detail design includes not only irrigation facilities but also Protection and Ring Dikes which are to protect the irrigable area of LMSA from flooding of the Pulangi river. The design water level for the dikes was once examined and decided during the detail design stage for MMIP II concluded in December 1992 by the loan consultants⁴. After that, the design water level was changed in a later year by NIA-PMO based on the interviews to the local residents.

1) Past Design Flood Water Level for Dikes (1992 Detail Design)

In the detail design which was concluded in December 1992, the frequency analysis was conducted based on the flood data recorded at the Pagalungan bridge (Inug-ug) from 1981 to 1988. Also, one rainy season flood observation data in 1987 at 3 locations of Paidu Pulangi, Kabasalan, and Barongis, which are all located at downstream, midstream and up-mid stream of the LMSA along the Pulangi river were utilized (see Figure 3.1.8 and Figure 3.1.9).

The 1992 detail design summarized the maximum flood records as indicated below, and the maximum flood level at the 3 locations in years other than 1987 were interpolated with reference to the flood water level observed at the Pagalungan bridge (see water levels in brackets in Table 3.1.3). Taking into account the effect of diversion channel⁵ constructed in the early 1980s, the 1992 detail design concluded the 1987 flood water level (6.5 m AMSL at Paidu-Pulangi) should be applied for the design even though the flood water levels in years, for example, 1982, 1983, were higher than 1987.




Figure 3.1.8 Flood Observation Stations (1987)

Source: 1992 Detail Design of MMIP




Figure 3.1.9 Flood Records at 4 Stations (1987)

Source: 1992 Detail Design of MMIP

Table 3.1.3 Flood Water Records and Design Flood Water by 1992 Detail Design

Location	Pagalungan Bdg	Barongis	Kabasalan	Paidu Pulangi
Distance from estuary, km	102.7	84.0	75.0	62.5
Flood water slope		1/6,850	1/14,490	1/18,180
Water level deference		-2.73	-0.62	-0.69
1981	July 3	10.38	(7.65)	(6.34)
1982	Feb 1	11.04	(8.31)	(7.00)
1983	July 27	10.67	(7.94)	(6.63)

⁴ Refer to Malitubog-Maridagao Irrigation Project, Detailed Engineering Design from Stage II Areas, Final Design Report, December 1992, Associated Consultants Joint Venture, Sanyu, ECL-Electroconsult, Meralco, Engineering and Development Cooperation.

⁵ Diversion channel, called Liguasan Diversion Channel, was constructed in early 1980s, and is said to have started functioning from mid 1980s, so that the 1987 flood water level was taken up as the design water level.

Location		Pagalungan Bdg	Barongis	Kabasalan	Paidu Pulangi
1984	June 15	10.59	(7.86)	(7.24)	(6.55)
1985	Oct 13	10.46	(7.73)	(7.11)	(6.42)
1986	June 21	10.00	(7.27)	(6.65)	(5.96)
1987	Aug 26	10.46	7.80	7.30	6.50
1988	Sep 27	10.06	(7.33)	(6.71)	(6.02)
Maximum flood level		11.0	8.3	7.7	7.0
Design flood level		10.5	7.80	7.30	6.50
Proposed dike top bank		11.0	8.30	7.80	7.00

Source: MMIP Detail Design, December 1992

2) Current Design Flood Water Level for Dikes (NIA-PMO DD)

The current design water level applied in the detail design by NIA-PMO is as follows:

Table 3.1.4 Design Flood Water Level by NIA-PMO

Item	Condition
Maximum flood level	8.013 m (AMSL) at the design station 0.0 (outlet of the façade drain from the meeting point of Protection Dike and Ring dike)
Minimum flood level	7.812 m (AMSL)
Normal water level:	4.520 (AMSL)
River bed:	-3.48 m (AMSL)
Free board:	Min. 0.5m (therefore, the bank top elevation is set at MFL + 0.5m)
Elevation of starting point	8.77 m (AMSL) ⁶
Elevation of ending point	9.90 m (AMSL), equivalent to the end of Lateral G of MC-2 Note that the ring dike has a longitudinal gradient of $S = 0.00008$, and therefore the ring dike, which starts with the elevation of 8.77 m AMSL, arrives at 9.90 m AMSL at the end point of Sta:14+748.432.

Source: NIA-PMO

During the survey of ‘Vulnerability Assessment for Flooding in Malitubog-Maridagao Irrigation Project, June 2010’, a series of interviews from local residents were organized. NIA-PMO had also confirmed high flood levels experienced with reference to the markings observed on trees, walls on residences/ buildings, etc. Based on the past high flood levels observed in the localities, the NIA-PMO has decided the above flood water levels as the design water level.

3) Difference of Flood Water Level by Studies

In the 1992 detail design, the design flood water level was decided at 6.50 m at the point of Paidu Pulangi. Recently NIA-PMO revised the design flood water level and they decided that water level at the outlet of façade drain which is located almost mid point of Paidu Pulangi station and Kabasalan station. Therefore, when adjusting the flood design water level of 6.5 m at the point of Paidu Pulangi with reference to the flood level of 7.3 m at Kabasalan in the 1992 detail design, the design flood level at the mid point between the two (2) points could be the average of the two levels, i.e., 6.90 m AMSL. Likewise, the NIA-PMO flood design level of 8.013 m AMSL at the outlet of façade drain can be interpolated at less 0.4 m level at the Paidu Pulangi point, namely, 7.61 m AMSL.

Table 3.1.5 summarizes the design flood water level by studies. From the comparison in the table, it is noted that the current NIA-PMO design flood water level is almost 1.0 m higher than those in the other studies. The following are considered as the causes of this difference; 1) the analysis in the 1992 detail design did not include recent heavy rain records, and 2) Satellite images may not show the actual maximum flood area because those images were captured every 16 days and therefore timing of image capturing and maximum flooding was not same.

⁶ Though MFL 8.013 + 0.50 is 8.513m, the top elevation at the starting point of the Ring Dike (the end point of the Protection bank) is set at 8.77m. This was decided as the end elevation of the protection dike, which in turn the beginning point elevation of the ring dike.

Table 3.1.5 Design Flood Water Levels by Studies

Station	Paidu Pulangi	Outlet of façade drain	Kabasalan	Barongis
Satellite Image, 1/	6.40	(6.80)	(7.20)	(7.70)
DEM & Satellite, 1/	6.60 (inside the Lower Malitubog Service Area)			
1992 DD	6.50	(6.90)	7.30	7.80
NIA-PMO DD	(7.61)	8.013	(8.41)	(8.91)

Note: 1/ Max. water extent by Satellite image was generated by overlaying different times water extent, so that no specific year is given.

Source: JICA Survey Team

3.2 Flood Protection Measures

As described in "3.1 Past Flood Occurrence and Its Magnitude on LMSA", 32% of the originally requested ODA target area and 34% of the whole LMSA is submerged in normal hydrological year, which is equivalent to 2-year return period flood. Without any flood protection measures, this area remains as submerged area and cannot be converted to farmland during the rainy season even if irrigation facilities are constructed. Additionally, constructed structures would be damaged by flood. Therefore, any flood protection works are required to protect farmlands from the flood.

Two approaches are deemed as effective flood protection approaches; 1) Flood Protection Dike along the Pulangi river to prevent flood from flowing into the farmland, and 2) Dredging of the Pulangi river to increase flow capacity and to lower the flood water level.

3.2.1 Flood Protection Dike

1) Structure of the Dike

Generally, the structure of the flood protection dike is concrete or backfilled soil; however only backfilled soil type can be adopted because it is believed that the base is too soft for the foundation of concrete made dike.

2) Alignment of the Dike

Since the Project area is located on the right bank of the Pulangi river, it is enough to construct the dike only along the right side of the river. The following two options can be considered as the alignment of the dike (see Figure 3.2.1).

Option-1: Peripheral of the LMSA (a part of the Ring Dike)

Option-2: Along the Pulangi river (extension of the protection dike)

NIA-PMO originally proposed the Option-1 while Option-2 came later taking into account the long alignment, which will require a huge investment for the implementation of the Option-1 dike.

Table 3.2.1 summarizes the scale of the dike, construction cost with/without foundation treatment (required measure for foundation treatment is discussed later), and EIRR of the 2 options. Additionally Figure 3.2.2 comparatively shows the dike heights of the 2 options. From the table, followings are deduced:

- ✓ **Option-1 cannot be technically and financially feasible** because:




Figure 3.2.1 Dike Construction Options

Source: NIA & JICA Team

1) high dike reaching over 6 m height would require foundation treatment which causes a surge of the construction cost. Even with the most economical measure of foundation treatment, e.g. sand compaction pile method, additional PhP 4,340 million is required for the treatment. Thus, the EIRR would fall in negative range (-0.2%).

- ✓ **Option-2, on the other hand, could be financially and technically feasible** from the view point of the scale, 11.7 km length with maximum 4-5 m height dike, and the EIRR of 12.3% (foundation treatment NOT considered). In case that foundation treatment should be required, the EIRR would go down to 8%; however, this scenario's risk may not be so high considering the necessary height of dike (not more than 4.5 m for most of the alignment).

Table 3.2.1 Flood Protection Dike Construction Options

Particulars	Option-1 (NIA-PMO Original: A Part of the Ring Dike)	Option-2 (Extension of the Protection Dike)
Dike Length	19.95 km	11.7 km
Max. Dike Height	6 – 7 m	4 – 5 m
Dike Volume	1,400,775 CUM	617,105 CUM
Construction Cost	PHP1,173 million	PHP 321 million
(Foundation Treatment), 1/	PHP 4,340 million	Possibly NOT required
EIRR (NO foundation treatment)	9.9% (for whole LMSA)	12.3% (for whole LMSA)
EIRR (with foundation treatment)	-0.2% (for whole LMSA)	8.0% (for whole LMSA)

Note: 1/ since geological condition of the foundation is not known, this treatment is an assumption based on Sand Compaction Pile Method discussed later. It is noted that taking into account the geological condition conducted at a bridge construction site upstream of the LMSA, the foundation condition is very soft so that with the scale of 6-7m height dike, there should be at least some foundation treatment required.

Source: JICA Survey Team




Figure 3.2.2 Dike Heights by Option

Note: According to the NIA-PMO original design, the Option-1 dike is composed of; 1) Protection Dike which runs along the Pulangi river natural bank and 2) Ring Dike running along the peripheral line of the LMSA.

Source: JICA Survey Team

3) Required Measure for Foundation Treatment

The flood protection dike is planned to be constructed along the Pulangi river starting at Paidu Pulangi, the most western location of the LMSA, and extended to the edge of the Ring Dike (see Figure 3.2.1). The protection dike is a kind of polder dike which prevents flood water from coming into the farm lands. However, the foundation of the dike is soft and therefore would require consolidation treatments.

The following examination was conducted under the conditions of the Option-1 but the same treatment may be required for the selected Option-2.

The maximum height of the Ring Dike is, according to the NIA-PMO detail design, expected to reach as high as 7 m above the foundation, while it reaches about 5 m height in Option-2. In both cases, the foundation of the dike may be soft and may consist of clay soils though geotechnical investigation has not been done along and around the alignment of the dike. When the foundation consists of clay soils, a long-term settlement, called consolidation settlement, and/or foundation circular sliding should be considered.




Figure 3.2.3 Typical Cross Section of Ring Dike

Source: NIA-PMO

Here, there is a geotechnical investigation result conducted at the construction sites of siphon and bridge connecting the PESA (MMIP II Geotechnical Investigation & Specification for Bridge & Siphon at Pagalungan Extension, December 2014). Though its location is far by about 30 km towards upstream from the midpoint of the LMSA along the Pulangi river, this test result is the only available geotechnical data in and around the Project area. Therefore, with this test result referred, a preliminary examination of the foundation for the dike construction is conducted below:

a) Extra-banking and foundation work method of dike

The sites for the protection and ring dikes are of soft-ground and the dikes need extra-banking and foundation treatment due to the settlement and insufficient of bearing capacity of the foundation. Extra-banking height should be given by the calculation of settlement volume (depth). The consolidation settlement will proceed by the load of dike embankment. In this case, “Cc method” is commonly applied to evaluate the settlement volume (depth):

$$[\text{Cc method}] \quad S = \frac{C_c}{1 + e_0} H \log_{10} \frac{\sigma'_0 + \Delta\sigma'}{\sigma'_0}$$

S: Settlement Volume (Depth)

Cc: Compression Index (suggested by Terzaghi's theory) = 0.45

e₀: Void Ratio of Foundation Ground (before loading of dike embankment) = 1.36

H: Average Height of Dike Embankment

1) Ring Dike; 5.5m, 2) Protection Dike (along Pulangi River); 4.0m

σ'₀: Effective Stress of Foundation Ground (before loading of dike embankment) = 82 kN/m²

Δσ': Effective Stress of Dike Embankment

1) Ring Dike; 99 kN/m², 2) Protection Dike (along Pulangi River); 72 kN/m²

Value of the above-mentioned coefficient “Cc” and “e₀” are given by the laboratory test results which were conducted in the “MMIP II Geotechnical Investigation & Specification for Bridge & Siphon at Pagalungan Extension (NIA, December 2014)” survey as shown in the following table:

Table 3.2.2 Consolidation Parameters

Boring No.	Depth (m)	Symbols (USCS) 1)	Void Ratio (e ₀)	Compression Index (Cc)
BH-1	14.55~15.00	MH	1.592	0.660
BH-2	14.55~15.00	ML	0.961	0.245
BH-3	13.05~13.50	MH	1.501	0.505
BH-4	13.05~13.50	MH	1.457	0.490
BH-5	13.05~13.50	MH	1.370	0.460
BH-6	13.05~13.50	MH	1.811	0.600

Boring No.	Depth (m)	Symbols (USCS) 1)	Void Ratio (e_0)	Compression Index (Cc)
BH-7	-	-	-	-
BH-8	14.55~15.00	MH	0.999	0.264
BH-9	-	-	-	-
BH-10	-	-	-	-
BH-11	14.55~15.00	MH	1.481	0.425
BH-12	-	-	-	-
BH-13	13.05~13.50	MH	1.203	0.360
BH-14	13.05~13.50	MH	1.207	-
Average			1.36	0.45

USCS: Unified Soil Classification System

Source: "MMIP II Geotechnical Investigation & Specification for Bridge & Siphon at Pagalungan Extension (NIA, December 2014)"

According to the above-mentioned survey report, stratum structure of the soft ground area along the siphon and bridge construction sites consists of SP (poorly graded sand), SM (silty fine sand), ML (silt with few sand, low liquid limit ($50\%<$)) and MH (elastic silt, high liquid limit ($50\%>$)) etc. Further, the depth of these soft layers reaches maximum 25 m and 20 m in average depth.

The "Effective Stress of Foundation Ground (σ'_0)" and the "Effective Stress of Dike Embankment ($\Delta\sigma'$)" are calculated by the following formulas;

[Effective Stress of Foundation Ground (σ'_0)]

$$\sigma'_0 = (\gamma_s - \gamma_w) * h / 2 = (18.0 - 9.8) * 20.0 / 2 = 82 \text{ kN/m}^2 \text{ (average stress)}$$

$$\gamma_s: \text{ Unit Weight of Soil (soft ground) } = 18.0 \text{ kN/m}^3$$

$$\gamma_w: \text{ Unit weight of Water } = 9.8 \text{ kN/m}^3$$

$$h: \text{ Thickness of Soft Ground Layer } = 20\text{m (average)}$$

[Effective Stress of Dike Embankment ($\Delta\sigma'$)]

Ring Dike

$$\sigma'_0 = \gamma_s * H = 18.0 * 5.5 = 99 \text{ kN/m}^2$$

$$\gamma_s: \text{ Unit Weight of Soil (soft ground) } = 18.0 \text{ kN/m}^3$$

$$H: \text{ Average Height of Dike Embankment}$$

Protection Dike (along the Pulangi river)

$$\sigma'_0 = \gamma_s * H = 18.0 * 4.0 = 72 \text{ kN/m}^2$$

$$\gamma_s: \text{ Unit Weight of Soil (soft ground) } = 18.0 \text{ kN/m}^3$$

$$H: \text{ Average Height of Dike Embankment}$$

Therefore, the settlement volume (depth) of the ring dike and protection dike along the Pulangi river is calculated as follows, namely, around 1.5 m consolidation settlement and 1.0 m settlement would be expected for the ring dike and the protection dike respectively.

➤ **Settlement Volume (Depth) of the Ring Dike: S = 1.31 m, say 1.5 m**

➤ **Settlement Volume (Depth) of the Protection Dike (along the Pulangi river): S = 1.04 m, say 1.0 m**

In addition, time to settle is estimated with assumed consolidation indexes by applying the following formula. Unfortunately, consolidation indexes are not available in the afore-mentioned test, therefore the following range of the index is assumed, e.g., from $2 \times 10^{-3} \text{ m}^2/\text{day}$ (clay dominant soil) to $15 \times 10^{-3} \text{ m}^2/\text{day}$ (clay including sand and gravel):

[Time to settle the foundation (t)]

$$T = (HD^2/C_v) \times T$$

Where ;

t : Time (day, in the following table, the time was converted in year)

Hd: Maximum drain length (assumed to be 10 m, half of the assumed layer thickness)

Cv: Consolidation index (m²/day)

T: Time factor

Table 3.2.3 Estimated Years to Settle for the Dike Foundation

Consolidation Ratio U	Time Factor T	Consolidation Index (C _v), m ² /day					
		Clay Soil (MH)			Gravel/ sand included (SP)		
		2x10 ⁻³	3x10 ⁻³	4x10 ⁻³	5x10 ⁻³	10x10 ⁻³	15x10 ⁻³
Years to Settle (Years)							
90	0.848	116	77	58	46	23	15
80	0.567	78	52	39	31	16	10
70	0.403	55	37	28	22	11	7
60	0.287	39	26	20	16	8	5
50	0.197	27	18	13	11	5	4

Source: JICA Survey Team

According to the estimation above, taking into account such conditions as foundation soils being clay with the thickness of 20 m, the time for the foundation to settle 60% would be 20–26 years and the time to settle as much as 80% could be 39–52 years. Of course, should there be sand and gravel layers in the foundation, which can facilitate consolidation, the time to settle could be considerably reduced. For example, the calculation results show that it takes only 5 years and 10 years for 60% and 80% consolidation respectively with the consolidation index of $15 \times 10^{-3} \text{ m}^2/\text{day}$.

b) Comparison of foundation works

Foundation of dikes should have resistances against the circular slip (sliding), shear failure, differential settlement and liquefaction, etc. The foundation works (foundation treatment methods) should strengthen the bearing capacity and stability of foundation. General foundation works which can be adopted for the ring dike and the protection dike along the Pulangi river are shown in the following table;

Table 3.2.4 Summary of Foundation Works (Foundation Treatment Methods)

Foundation Treatment Methods	Construction Method and Characteristics
Replacement Method	Excavation of soft ground layer and backfilling (replace) by the fine soil. This method is generally known as most certain method. However huge amount of disposal soil will occur and disposal area and borrow-pit will be required.
Sand Compaction Pile Method	Placing the sand pile in the soft ground and quicken the consolidation and thus strengthen the ground. This method prevents especially the liquefaction failure.
Sand Drain Method	Sand is used as drain material and soft ground will be consolidated by the load of dike embankment. This method needs relatively long time to achieve the strength of foundation.
Deep Layer Mixing-type Stabilization Method	Soft ground is solidified by cement-base or lime-base coagulant (Mechanical Stirring Method). This method can achieve the strength of foundation in a quicker time.

Source: Latest Works and Points of selecting Foundation Treatment, Japanese Civil Society, Feb, 2011

Table 3.2.5 shows the purposes of different foundation works, the effects of each method and comparison of construction costs. With the comparison of these factors, it is considered that the “Sand Compaction Pile Method” should be the most economical method for the foundation treatment work for the ring dike and the protection dike as well:

Table 3.2.5 Comparison of Foundation Works (Foundation Treatment Methods)

Objectives		Name of Method	Replacement Method	Sand Compaction Pile Method	Sand Drain Method	Deep Layer Mixing-type Stabilization Method
Stability of Ground		Circular Slip (Sliding)	A	B	C	A
		Shear Failure	A	B	B	A
		Stability of Surface Ground	A	B	C	A
Control of Settlement		Consolidation Settlement	A	B	C	A
		Differential Settlement	A	B	C	A
		Quickening the Consolidation	Non applicable	A	A	Non applicable
		Prevention of Liquefaction	A	A	C	A
Cost of Foundation Work	Ring Dike 1)	(million PHP)	7,240	3,680	3,440	8,370
		(million JPY)	16,370	8,310	7,770	18,920
		Cost Ratio	(197%)	(100%)	(93%)	(243%)
	Protection Dike 2)	(million PHP)	1,930	660	930	1,120
		(million JPY)	4,370	1,480	2,110	2,520
		Cost Ratio	(292%)	(100%)	(141%)	(170%)
Evaluation			Not adopted	Adopted	Not adopted	Not adopted

- 1) Length of Ring Dike = 14.75 km, average embankment height = 5.5 m
- 2) Length of Protection Dike = 5.20 km, average embankment height = 4.0 m
- 3) A: Effective, B: Slightly effective, C: Not effective

Source: JICA Survey Team




Figure 3.2.4 An Example of the Sand Compaction Pile Method

Source: ISSMGE - TC 211 International Symposium on Ground Improvement IS-GI Brussels 31 May & 1 June 2012




Figure 3.2.5 An Example of the Sand Drain Method

Source: WAKACHIKU CONSTRUCTION Co., Ltd.

4) Negative Impact by the Construction of the Flood Protection Dike

The flood protection dike can function well to protect the beneficial irrigable area from the floods.

However, it would cause the following adverse effects:

- a) Dike construction amplifies the flood impact to the left side of the Pulangi river.

The flood protection dike limits the course of the flood because the right side of the Pulangi river is closed by this dike and the ring dike. Under this condition, flood discharge volume flowing out to the left side of the Pulangi river, namely the Liguasan marsh, will increase, which causes submerged depth to be deeper and inundation area to be wider than the present condition.




Figure 3.2.6 Image of Flood Situation under Present Condition and After Construction of the Dike

Source JICA Survey Team

- b) Dike construction may incur inundation by rainfall originating from inside of the Dike.

Under the present condition, surface water in the LMSA flows out to the Pulangi river when its water level becomes lower than that within the LMSA. However, by the construction of the dike, the LMSA will be closed by dike, thus rainfall would accumulate therein and stagnate in the LMSA at certain extent. Therefore, drainage structures would be required to drain the stagnated water out to the Pulangi river.




Figure 3.2.7 Image of Inundation Situation within LMSA

Source: NIA & JICA Survey Team

- c) Dike would act as the physical border dividing the vicinity area socially and environmentally.

There are communities belonging to the same Magindanaon ethnic group (Moro ethnic people) around the planned dike alignment. Those communities would be separated physically, and whereby socially, by the construction of the dike.

The height of the dike ranges mostly 4 – 5 m. Left photo in Figure 3.2.8 shows a dike which height is around 3 – 3.5 m only, while the right photo in the same figure is an example of very high dike reaching over 5 m to 6 m (compare with the tree in the photo). The size of the dike proposed for the LMSA may provide the people with somewhat psychological impact, namely, the local area would be divided by the wall-like dike.



An example of dike constructed in a polder area, height ranges from 3 to 3.5 m.



An example of dike constructed in MMIP II (MC-2 Main Canal), height goes up more than 5.0 m.

Figure 3.2.8 Examples of the Constructed Dike

Source: JICA Survey Team

d) Land acquisition and resettlement are required for dike construction.

There are residents living along the right side of the Pulangi river and their resettlement will be required to construct the dike. Since any field survey for the resettlement has not been conducted, the number of households to be relocated due to the dike construction is unknown at this moment.

There are, however, 1/4,000 topographic maps produced in early 1990s, and these maps show not only contour lines but also ground objectives, e.g. trees and houses. For example, a certain number of houses exist on the natural bank where direct effects by the construction of the dike will be concerned (see Figure 3.2.9). This indicates that the dike alignment, if constructed, should be put back toward inside of the LMSA in order to reduce the resettlement as much as possible.




Figure 3.2.9 Topographic Map (1/4,000) showing Houses Near the Pulangi river

Note: Since most of the houses are erected just near the Pulangi river, dike should be aligned somewhat inside in order to avoid or reduce the number of resettlements.

Source: JICA Survey Team

Land acquisition can be estimated with reference to the topographic maps. The following table summarizes the area of the land acquisition comparing with/without the dike construction. As indicated below, the case with the dike construction along the Pulangi river requires about 30ha land to construct the flood protection dike, and the total land acquisition area is estimated at around 160ha.

Table 3.2.6 Land Acquisition for Dike Construction

Works	Area to be Required, ha		Remarks
	With Dike* Construction	Without Dike Construction	
1. RMC 2 (ODA Area)	34.4	11.3	
2. Laterals (ODA Area)	26.1	19.8	
3. Drains (ODA Area)	24.3	24.3	
4. Access Road (LMSA)	14.8	14.8	
5. Borrow Area 1	20.9	7.6	
6. Borrow Area 2	8.8	No Dike Considered	
7. Façade Drain	-		
8. Protection Dike	29.79		
9. Ring Dike	-		
Total, ha	159.1	77.9	

Note:* The Dike is planned along the Pulangi river, not the ring dike running within the LMSA originally planned by NIA-PMO

Source: JICA Survey Team based on Topographic map (1/4,000)

3.2.2 Dredging of the Pulangi River

1) Target Area for Dredging

DPWH has a plan for dredging of some rivers. According to DPWH, the Rio Grande de Mindanao river, Tamontaka river and Tunggol flood way are included in the target of the dredging, however the Pulangi river is not included. The dredging of the Rio Grande de Mindanao river and Tamontaka river aims to mitigate flood damage on Cotabato city. Dredging length from the river mouth is 6.15km for Rio Grande de Mindanao river and 7.15km for the Tamontaka river. Since the Project area is located about 80 km away from the river mouth, the impact by dredging may be very limited or almost nothing from the aspect of increase in flow capacity of the Pulangi river.

As for the dredging of Tunggol flood way constructed in 1980s in an upstream of LMSA in order to relieve flooding to Pikit City, it contributes to disperse the flood water and decrease the peak volume of the Pulangi river, however does not contribute to increasing the flow capacity of the Pulangi river.

Thus, it is not expected to increase the flow capacity of the Pulangi river for the Project by the DPWH plan. Additionally, according to the interview with DPWH officers, the budget for the dredging plan has not been arranged and they are still seeking donors to implement it as of mid 2017.




Figure 3.2.10 Target Area for Dredging

Source: JICA Survey Team

Therefore, on this study, dredging plan is examined from zero base (= without any other dredging projects), and as the first-step preliminary examination, whole length of the Pulangi river, Rio Grande de Mindanao river and Tamontaka river is selected as the target for dredging.

2) Dredging Formation

The dredging should be made both by expanding the river section and making the river bottom deeper (only making the river deeper seems to be insufficient since the river bed elevation beside the LMSA is already almost zero implying much deeper dredging would incur sea water intrusion). Additionally, since right side of the Pulangi river is the beneficiary area of the LMSA, horizontal expansion should be toward the left bank side only for the reach of LMSA.




Figure 3.2.11 Image of the Dredging Formation
Source: JICA Survey Team

3) Negative Impact by the Dredging

The dredging work increases the flow capacity of the Pulangi river and lower the flood water level. However, it would cause the following concerns:

- a) The edge of the Liguasan marsh might be dried up.

Flood from the Pulangi river to the Liguasan marsh works as natural supply of water to keep the marsh area wet. By the dredging work, this natural supply of water to the Liguasan marsh decreases, which instead may cause the dry out of the marsh to some extent.

- b) Ecosystem of the Pulangi river may change.

By the dredging work, flow condition such as river depth and flow velocity will change. This may affect to the ecosystem around the Project area by changing the variety of the aquatic organisms and those residential areas.

- c) Fishing industry may be affected by the change of the ecosystem.

Due to the change of the variety of the aquatic organism and those residential areas, fishing industry may be affected adversely.

- d) Land acquisition and resettlement is required for dredging and for treating dredged mud.

There are residents living on the left bank of the Pulangi river, so dredging toward horizontal expansion will require the resettlement for those residents. Additionally, huge areas are required to dry up the dredged mud and to dispose the dried mud.

3.3 Preliminary Examination on Flood and its Mitigation Measures

3.3.1 Examination Cases

The following three simplified examinations are conducted aiming to 1) assess the feasibility of the dike construction and the river dredging, 2) evaluate positive/negative impact by the construction of the dike, and 3) examine the necessity of any additional measures to mitigate damage by flood as a rough estimate.

Table 3.3.1 Examination Case of the Preliminary Examination

Case	Purpose
1. Flood Simulation by Simplified Storage Model	- To assess maximum flood discharge, maximum flood water level and maximum inundation area
2. Inland Inundation Simulation by Simple Rainfall-Evaporation Model	- To assess the inundation area in the LMSA - To assess the necessity of any drainage facilities
3. Dredging Simulation by the Uniform Flow Calculation	-To assess required dredging volume

Source: JICA Survey Team

3.3.2 Flood Simulation by Simplified Storage Model

1) Purpose

According to the topographic map, the Pulangi river passes a narrow point located between the 2 residual hills at both sides of the river (hereinafter referred to as "bottle neck point", see Figure 3.3.1). Since the flow capacity of the Pulangi river at the bottle neck point must be low, huge flood volume may not be able to pass this point and this may cause the flood.

The purposes of this simulation are therefore to assess: 1) maximum flood discharge, 2) maximum flood water level and 3) maximum inundation area under present condition and after construction of the dike. This simulation also aims to assess the impact by the construction of the dike.




Figure 3.3.1 Location of the Bottle Neck Point

Source: JICA Survey Team

2) Methodology

Flood simulation at the bottle neck point by the rational formula, which is well known as a simplified storage model simulation, is selected.

3) Conditions for the Simulation

Catchment area at the bottle neck point is taken as a simplified storage reservoir and simulation is conducted under the conditions shown in Table 3.3.2:

Table 3.3.2 Conditions of the Simulation

Items		Condition
Rainfall	Probable Rainfall	Average rainfall within the catchment area of the bottle neck point calculated by Thiessen method
	Distribution	The method complied with the Flood Plan*
Base Flow Q_0		Specific runoff x Catchment Area at the bottle neck point
Inflow (flood discharge) Q_{in}		Calculated by Rational Formula
Outflow Q_{out}		Calculated utilizing H-Q relation at the bottle neck point
Cross section of the bottleneck point		Created by DEM data
H-Q relation curve at the bottle neck point		Created by Manning formula utilizing cross section of the bottle neck point
H-A and H-V relation curve of the catchment area		Created by DEM data

*Flood Plan: Nationwide Flood Control Plan and River Dredging Program, 1982

Source: JICA Survey Team

Detail explanation for each condition is described as below:

a) Probable rainfall

The historical rainfall records at the meteorological observation stations located within/near the catchment area are collected. The daily rainfall amount within the catchment area is determined according to the area of Thiessen division, and then 4-day consecutive rainfall data in the catchment area is calculated. Finally, annual maximum 4-day rainfalls are selected and probable 4-day rainfall is calculated as shown in the following Table 3.3.3:

Table 3.3.3 Probable 4-Day Rainfall (Mean Rainfall within the Catchment Area) by Return Period

Return Period	2years	5years	10years	20years	30years	50years	100years
4-day probable rainfall (mm/4days)	104	133	152	171	183	197	217

Source: JICA Survey Team

b) Rainfall distribution

Rainfall distribution of the Mindanao River Basin is generated according to the Mindanao River Basin Integrated Management and Development Master Plan (2014) as in the Figure 3.3.2. Since the distribution comprises of the ratio of each hourly rainfall as the design rainfall distribution, 4-day rainfall distribution by each return period is created by multiplying probable 4-day rainfall in Table 3.3.3 and this distribution.




Figure 3.3.2 Rainfall Distribution

Source: JICA Survey Team

c) Base flow: Q_0

$0.027 \text{ m}^3/\text{s}/\text{km}^2$ is applied as the base flow, which was determined as a specific base flow of the Mindanao River Basin in the above Master Plan. Since the catchment area at the bottle neck point is $13,700 \text{ km}^2$, the base flow volume is therefore calculated at $370 \text{ m}^3/\text{s}$.

$$\text{Base flow volume} = (\text{specific base flow}) \times (\text{catchment area}) = 0.027 \text{ m}^3/\text{s}/\text{km}^2 \times 13,700 \text{ km}^2 = 370 \text{ m}^3/\text{s}$$

d) Inflow (flood discharge): Q_{in}

Inflow volume at the bottleneck point is calculated by the rational formula below, and the conditions for the rational formula are shown in Table 3.3.4.

$$Q = 1/3.6 \times f \times r \times A$$

Where:

Q: Peak flood discharge (m^3/s)

f: Runoff coefficient

r: Average hourly rainfall during flood approach time (mm/hr)

A: Catchment area (km^2)

Table 3.3.4 Conditions for Rational Formula

Item	F^1	Flood Approach Time ² T (days)	r (=probable 4-day rainfall / 5.4days) (mm/hr)							A (km^2)
			2 years	5 years	10 years	20 years	30 years	50 years	100 years	
Contents	0.383	5.4	0.80	1.01	1.16	1.31	1.40	1.51	1.66	13,700

Source: JICA Survey Team

*1: Average value within the Mindanao River Basin calculated in the Master Plan.

*2: $T = T_{in} + T_{dn}$

Where:

T_{in} : Time gap from rainfall starting time within the catchment area to flood starting time at the outlet of the catchment area (=30min)

T_{dn} : Flood flow time from the upstream end of the river to the bottle neck point

$T_{dn} = \sum(L/W)$

Where:

L: Length of the main river

L1=100 km (flat slope area)

L2=229 km (moderate slope area)

W: Flood flow velocity (=20 x (h/L)^{0.6})

h: Elevation gap from the upstream end of river to the bottle neck point

h1=100m (flat slope area)

h2=871m (moderate slope area)

As a result, peak flood discharge of each return period is calculated as shown in Table 3.3.5.

Table 3.3.5 Peak Flood Discharge by Return Period

Return Period	2 years	5 years	10 years	20 years	30 years	50 years	100 years
Peak Flood Discharge Q (m ³ /s)	1,160	1,476	1,694	1,907	2,033	2,192	2,412

Source: JICA Survey Team

Regarding the time series inflow, the triangle-shape hydrograph shown in Figure 3.3.3 is adopted.

e) Outflow: Q_{out}

Q_{out} is calculated by the Manning formula with cross section at the bottle neck point and stored water depth within the catchment area (Ht). Calculated H- Q_{out} relation is shown in Figure 3.3.4.

f) H-A and H-V relation curve of the catchment area

With the DEM data, H-A and H-V relationships are estimated under the condition with/without dike. The results are shown in Table 3.3.6 and Figure 3.3.5.






Figure 3.3.3 Triangle-shape Hydrograph

Source: JICA Survey Team



Cross Section



H-Q relation Curve

Figure 3.3.4 Cross Section and H (Elevation) - Q_{out} Relation at the Bottle Neck Point

Source: JICA Survey Team

Table 3.3.6 Water Surface and Volume with/without Dike

Present Condition (Without Dike)				After Construction of Dike			Area Reduced	V reduced
A (ha)	cumulative A (ha)	V (MCM)	H (ELm)	A (ha)	cumulative A (ha)	V (MCM)	%	%
26	26	0	1	13	13	0	50.00	
2,279	2,305	23	2	689	702	7	30.46	30.46
69	2,374	24	3	33	735	7	30.98	30.98
365	2,738	27	4	96	831	8	30.36	30.36
1,552	4,290	43	5	1,310	2,141	21	49.90	49.90
7,095	11,385	114	6	6,516	8,657	87	76.04	76.04
7,105	18,490	185	7	6,126	14,783	148	79.95	79.95
6,484	24,974	250	8	4,816	19,599	196	78.48	78.48
11,414	36,388	364	9	10,045	29,644	296	81.47	81.47
15,038	51,426	514	10	14,269	43,913	439	85.39	85.39
14,799	66,225	662	11	14,323	58,237	582	87.94	87.94
12,752	78,978	790	12	12,410	70,647	706	89.45	89.45
9,889	88,867	889	13	9,654	80,300	803	90.36	90.36
8,318	97,185	972	14	8,122	88,422	884	90.98	90.98
7,589	104,774	1,048	15	7,469	95,892	959	91.52	91.52

Source: JICA Survey Team




Figure 3.3.5 H-A and H-V Relation of the Catchment Area at the Bottle Neck Point

Source: JICA Survey Team

g) Formula

Flood volume, inundation area and flood water depth are calculated by the formula below. This formula shows that the difference between inflow and outflow is stored within the catchment area and inundation area is converted by stored water depth and H-A relation curve.

$$\Delta Q_t = Q_{outt} - Q_{int} \quad \leftarrow$$

$$\Delta V_t = \Delta Q_t \times \Delta t$$

$$V_t = V_{t-1} + \Delta V_t \rightarrow \text{Converted to } H_t \quad \leftarrow$$

Where;

- Q_{outt}: Outflow
*Calculated utilizing H-Q_{outt} relation curve at the bottle neck point and H_{t-1}
- Q_{int}: Inflow
*Calculated by the rational formula
- V_t: Stored water volume
- Δt : Time step in Analysis
- H_t: Stored water depth (elevation)
*Calculated utilizing H-V relation curve of the catchment area and V_t

4) Results of the Simulation

Table 3.3.7, Table 3.3.8 and Figure 3.3.6 show the results of the simulation including the flood water level and inundation area under different probability with present condition (without dike) and after construction of the dike. In general, as the return period becomes bigger, the water level rises. The water level would, for example, rise up by 25cm and 31cm under 30-year and 100-year return periods, respectively.

Table 3.3.8 shows the inundation area on the left side of the Pulangi river by each return period. The result indicates that the inundation area would be enlarged by around 10% between with and without dike, e.g. 12.8% in case of 10-year return period and 7.9% under 30-year return period. These results may imply that the dike construction would magnify the flood impact to the left side of the Pulangi river, namely, Liguasan marsh.

Table 3.3.7 Maximum Flood Water Level with and without Dike

Return Period	(1) Present Condition (Without Dike)	(2) After Construction of Flood Protection Dike	(3) Ratio (= (2) / (1))
2 year	6.08 m	6.25 m (+17cm)	102.8 %
5 year	6.45 m	6.67 m (+12cm)	103.4 %
10 year	6.70 m	6.96 m (+26cm)	103.9 %
20 year	6.95 m	7.19 m (+24cm)	103.5 %
30 year	7.08 m	7.33 m (+25cm)	103.5 %
50 year	7.22 m	7.50 m (+28cm)	103.9 %
100 year	7.43 m	7.74 m (+31cm)	104.2 %

Source: JICA Survey Team

Table 3.3.8 Maximum Inundation Area with and without Dike (only Left Side of the Pulangi River)

Return Period	(1) Present Condition (Without Dike)	(2) After Construction of Flood Protection Dike	(3) Ratio (= (2) / (1))
2 year	83.4 km ²	93.6 km ²	112.2 %
5 year	105.6 km ²	118.6 km ²	112.3 %
10 year	120.6 km ²	136.0 km ²	112.8 %
20 year	135.6 km ²	147.3 km ²	108.6 %
30 year	142.2 km ²	153.5 km ²	107.9 %
50 year	148.6 km ²	161.4 km ²	108.6 %
100 year	158.2 km ²	172.4 km ²	109.0 %

Source: JICA Survey Team




Figure 3.3.6 Results of the Flood Simulation by Simplified Storage Model (1/3)

Source: JICA Survey Team




Figure 3.3.6 Results of the Flood Simulation by Simplified Storage Model (2/3)

Source: JICA Survey Team




Figure 3.3.6 Results of the Flood Simulation by Simplified Storage Model (3/3)

Source: JICA Survey Team

3.3.3 Inland Inundation Simulation by Simple Rainfall-Evaporation Model

1) Purpose

When the LMSA is enclosed by a dike, inland flood which is caused by the rainfall originating inside of the LMSA will occur within the LMSA. The purposes of this simulation are therefore to assess the following at a rough scale; 1) maximum inundation area, 2) maximum inland flood water level within the LMSA, and 3) damage on the designed irrigable area by inundation under the condition that the LMSA is enclosed by the dike.

2) Methodology

The balance of rainfall and evaporation within the LMSA is calculated and stored within the LMSA. The stored water volume is calculated by the formula below, and inundation area and inland flood water level are calculated with the stored water volume and H-V/H-A relation curves.

$$\Delta V_t = R_t - E_t \longrightarrow V_t = V_{t-1} + \Delta V_t$$



Where;

R_t: Rainfall

E_t: Evaporation

V_t: Stored water volume within the LMSA

Water depth H_t: Calculated with H-V relation curve of the catchment area and V_t

Inundation area A_t: Calculated with H-A relation curve of the catchment area and H_t

3) Conditions for the Simulation

a) Simulation period

The period of this simulation is 1 year, since the impact by the evaporation, to reduce stored water volume, would not clearly appear within a short period of simulation time.

b) Rainfall applied

The historical data of the Datu Piang rainfall gauge station which is the nearest station to the LMSA (see Figure 3.3.7) is selected. Also probable annual rainfall patterns by each return period are generated based on the procedures below.




Figure 3.3.7 Location of the Rainfall Gauge Station and Evaporation Stations

Source: JICA Survey Team

- i) Annual rainfall of each year at Datu Piang observation station is calculated,
- ii) Probable annual rainfalls are calculated,
- iii) Years which have the nearest rainfall amount to each target probable rainfall are selected, and
- iv) The rainfall pattern which is selected in procedure iii) is extended according to the extension ratio which is determined by the annual rainfall of the selected year and the probable annual rainfall.

Table 3.3.9 Probable Annual Rainfall at Datu Piang Observation Station and Selected Years

Return Period (years)	Probable Annual Rainfall (mm)	Selected Year (Annual Rainfall)	Extension Ratio
2	1,415	1978 (1,385mm)	1.021
5	1,734	1994 (1,628mm)	1.065
10	1,931	1974 (1,965mm)	0.983
30	2,208	1975 (2,060mm)	1.072
50	2,328	1975 (2,060mm)	1.130
100	2,482	1975 (2,060mm)	1.205

Source: JICA Survey Team

c) Evaporation

The historical data of the MIT Evaporation station which is the nearest station to the LMSA (see Figure 3.3.8) is selected. Since the only monthly evaporation data are available, daily evaporation is calculated by dividing average monthly evaporation by the days of each month.



Figure 3.3.8 Evaporation at the MIT Station

Source: JICA Survey Team

d) H-V and H-A relation curve of the LMSA

1/4,000 scale plan map of the LMSA provided by NIA-PMO is selected as topographic condition within the LMSA. Also, H-V and H-A relation curves of the LMSA are generated based on this map.




Figure 3.3.9 Topographic Condition of the LMSA

Source: JICA Survey Team




Figure 3.3.10 Topographic Condition, H-V Relation Curve and H-A Relation Curve of the LMSA

Source: JICA Survey Team

4) Results of the Simulation


Table 3.3.10 and Figure 3.3.11 indicate the computation results. Even in case of 2-year return period, there would be a certain inundation (inland flood water level within the LMSA is more than 4.5m, lowest elevation of the LMSA) which could occupy 28.9 % of the designed irrigable area of the LMSA, and as much as about half the area in case of 10-year return period. To drain out inland flood water in the LMSA, drainage pumping station(s) should be considered; otherwise the dike embankment cannot maintain the designed irrigable area of the LMSA.

It is noted that, even during the rainy season, water level of the Pulangi river may become lower than the water levels within the LMSA, which means there might be a possibility of releasing the inland flood water to the Pulangi river by gravity. Such release is, however, NOT considered in this preliminary examination to consider the safer case.

Table 3.3.10 Inundation Magnitude Caused by Rainfall less Evaporation

Return Period, Year	Max Inland Flood Water Level (EL.m)	Inundation Area within the LMSA *Elevation >4.5m	Inundated Ratio for LMSA, %
2	5.39	33.6	28.9
5	5.66	45.1	38.7
10	5.98	58.0	49.8
30	6.30	67.2	57.8
50	6.47	72.6	62.3
100	6.66	78.4	67.3
Lowest Elevation of the LMSA	4.50		


Source: JICA Survey Team



*Dark green area and blue colored area are inundation area

Figure 3.3.11 Results of Inland Inundation Simulation by Simple Rainfall-Evaporation Model (1/2)

Source: JICA Survey Team



*Dark green area and blue colored area are inundation area

Figure 3.3.11 Results of Inland Inundation Simulation by Simple Rainfall-Evaporation Model (2/2)

Source: JICA Survey Team

5) Necessary Measure to Drain Inland Flood Water from the LMSA

Based on the results of the simulation, the necessity and the scale of drainage pumping station(s) should be examined to drain the inland flood water. Conditions for the examination are as follows:

- a) Rainfalls applied are such three (3) cases as 10-year, 20-year and 30-year return periods based on the record of Datu Piang rainfall gauge station.

b) Only the water over 4.5m elevation is to be drained in 2 days (48 hours)⁷. The elevation of 4.5m is almost equivalent to the lowest point of the beneficiary area of the LMSA.

Table 3.3.11 indicates necessary specifications of the required drainage pumps with preliminary cost estimation including pump houses. As a result, it would not be financially feasible taking the followings into account:

- a) If 1,200mm diameter pumps are to be procured, there should be 21, 23, and 24 numbers of pumps in order to drain the inland flood water in 10-year, 20-year and 30-year return period respectively. Even in the case of 1,800mm diameter pumps, 9, 10, and 10 numbers of pumps should be procured for the same cases respectively.
- b) Above scope of the pumps would require huge investment, e.g. nearly around 4.5 billion PHP. In addition, power arrangement including stand-by generator should be included, which further increases the investment cost in addition to the difficulty of O&M for the huge pump stations.

Table 3.3.11 Scope of Drainage Pumping Stations including Preliminary Cost

Rainfall Probability	Drainage Amount (m ³ /48hr)	Drainage Discharge (m ³ /s)	Pump Diameter (mm)	Pump Capacity (m ³ /s)	Number of pump	Motor Capacity (KW)	Construction cost (Million PHP)		
							Pump facility	Civil & building	Total
10-year probability	11,442,177	66.2	1200	3.2	21	400	2,385	1,962	4,347
		66.2	1350	4.2	16	600	2,228	2,439	4,667
		66.2	1500	5.4	13	630	2,385	2,822	5,208
		66.2	1800	8.0	9	1000	2,239	1,926	4,164
20-year probability	12,478,143	72.2	1200	3.2	23	400	2,613	2,149	4,761
		72.2	1350	4.2	18	600	2,507	2,744	5,251
		72.2	1500	5.4	14	630	2,569	3,040	5,608
		72.2	1800	8.0	10	1000	2,488	2,139	4,627
30-year probability	13,060,145	75.6	1200	3.2	24	400	2,726	2,242	4,969
		75.6	1350	4.2	19	600	2,646	2,896	5,542
		75.6	1500	5.4	14	630	2,569	3,040	5,608
		75.6	1800	8.0	10	1000	2,488	2,139	4,627

Source: JICA Survey Team




Figure 3.3.12 A Preliminary Example of Drainage Pump Stations and Typical Cross Section

Note: As an example, there should be total 10 drainage pumps with 1,800mm diameter at 2 stations. The stations would be placed at points where inland flood water could be discharged according to the topographic condition. Moreover, open trench should be excavated to the pumping stations.

Source: JICA Survey Team

⁷ In a Japanese standard, 24 hours are indicated as allowable (without any damages) inundation period in paddy field. In this survey, 48 hours is set as allowable period under a condition that some damages are acceptable.

3.3.4 Dredging Simulation by the Uniform Flow Calculation

1) Purpose

Dike construction would act as a physical border dividing the vicinity area socially and environmentally. From this aspect, however, social/environmental impact by dredging would be less than that of dike construction. The purpose of this calculation is to assess the possibility of mitigating damage on the LMSA by the dredging of the Pulangi river.

2) Methodology

As already discussed, flood would occur due to low flow capacity of the Pulangi river at the bottle neck point. Therefore, design cross section which has enough flow capacity at the bottle neck point is examined. The design cross section shall have enough flow capacity which can discharge the target flood volume with water level less than EL.4.5m (lowest elevation of the LMSA).

This formation is examined by the uniform flow calculation with the Manning formula below.

$$Q = A \times V = A \times \frac{1}{n} \times R^{(2/3)} \times \sqrt{I}$$

Where;

- Q: Discharge (m³/s)
- A: Cross-section area of flow (m²)
- V: Flow velocity (m/s)
- n: Manning roughness coefficient (s/m^{1/3})
- R: Wetted perimeter (m)
- I: Slope

3) Conditions for the Calculation

Table 3.3.12 Conditions of the Calculation

Present Cross Section	Target Flood Discharge Q	n	I
Created by DEM data	2,782m ³ /s Base flow: 370 m ³ /s 100-year RP Flood: 2,412 m ³ /s	0.030	1/10,000 * Calculated by DEM data

Source: JICA Survey Team

4) Results of the Calculation

The design cross section is shown in Figure 3.3.13. At the bottle neck point, 1,868 m³/m of the average unit dredging volume is required and this volume is required for all along the river, 163.6km in total to lower the flood water level. In this case, total dredging volume becomes 1,868 (m³/m) x 163.6 x 103 (m) = 306 MCM.





Figure 3.3.13 Design Cross Section Formation

Source: JICA Survey Team



River	Average Unit Dredging Volume (m ²)	Rio Grande de Mindanao	Tamonotaka	Pulangi	Total
Length (km)	-	53.49	34.84	75.24	163.57
Dredging volume (MCM)	1,868	99.91	65.08	140.54	305.53

Figure 3.3.14 Dredging Plan: Total 163.57 km Length

Source: JICA Survey Team

Examination results indicate that the river dredging cannot be feasible because:

- a) It is estimated that the necessary dredging volume is very huge, saying approximately 300 MCM, equivalent to 10m height x a square of 6 km x 5 km. The expected dredging cost would amount to 20 billion PH P⁸ even not considering transportation cost to disposal area.
- b) The dredging should be made both by expanding the river section and making the river bottom deeper (only making the river deeper seems to be insufficient since the river bed elevation beside the LMSA is already almost zero implying much deeper dredging would incur sea water intrusion). Due to this reason, the result requires at least 80m horizontal expansion is required, and therefore a number of houses have to be relocated.

3.4 Numerical Model for Computer Simulations

To assess the detail impact of the dike and its countermeasures, unsteady non-uniform flow simulations are executed with the software MIKE series. The feature of this detail simulation is to simulate both behaviors of the water flow on rivers and flood plains, integrating the one and two-dimensional models. In this section, the conditions of the simulations for each analysis case are described.

3.4.1 Simulation Cases

Table 3.4.1 shows the simulation cases, which are 1) Flood Simulation with/without the dike, 2) Inland

⁸ Unit price for dredging is set at 64 PHP per CUM volume based on a cost estimation by DPWH applied for dredging works in the Rio Grand Mindanao river.

Inundation Simulation with/without the drainage structures, and 3) Flood Simulation with/without dredging, which are basically same cases as the afore-mentioned preliminary examinations.

Table 3.4.1 Simulation Cases for Detail Hydraulic Simulations

Simulation Cases		Purpose
1	Flood Simulation with/without Dike	- Determination of the inundation area and flood water level - Assessment of the impact by the construction of the dike, especially impacts on the Liguasan marsh
2	Inland Inundation Simulation with/without Drainage Structures	- Assessment of inland inundation within the LMSA after the dike construction - Examination of the necessary structures to mitigate the inland inundation
3	Flood Simulation with/without Dredging	- Assessment of the necessary dredging volume of the Pulangi river to protect the LMSA from the flood. Note that the dredging considers 2 cases; 1) dredging along almost whole stretches of the Pulangi river and 2) dredging or widening of the bottle neck point.
4	Flood Simulation with the Ambal-Simuay River and Rio Grande de Mindanao Flood Control Projects	- Assessment of the flood water level after construction of the Ambal-Simuay River and Rio Grande de Mindanao flood control projects planned by DPWH

Source: JICA Survey Team

3.4.2 General Conditions of the Simulation

1) Topography

The Digital Elevation Model (DEM) from Shuttle Radar Topography Mission (SRTM) provided by National Aeronautics and Space Administration (NASA) are utilized. The spatial resolution of the original DEM is one (1) arc (approximately 30m), and the vertical resolution is one (1) meter.

2) River Alignments and Basin Boundaries

River alignments within the Mindanao River Basin are created through the spatial analysis of the SRTM DEM. Although the river alignments and the basin boundaries can be created automatically by tracing the depression and ridge line, determination of the basin boundaries should be created carefully especially on the marshy areas where the change in elevation is very small. Therefore, the determination of the basin boundaries are finalized by collating the past study, namely, "Mindanao River Basin Integrated Management and Development Master Plan", and also by the visual confirmation with the satellite images such as Google Earth.




Figure 3.4.1 Elevation Distribution within the MRB
Source: JICA Survey Team



Figure 3.4.2 River Alignments and Basin Boundaries
Source: JICA Survey Team




Figure 3.4.3 River Alignments and Basin Boundaries (focusing on the area from LMSA to the River Mouths)

Source: JICA Survey Team




Figure 3.4.4 River Network Diagram in the Mindanao River Basin (MRB)

Source: JICA Survey Team

3) River Alignments and Basin Boundaries

Roughness coefficient on each mesh is determined based on the land use. As the Filipino standard, DPWH has their own standard about the relation between land use and roughness coefficient for the purpose of studies for flood control, and describes those roughness coefficients in "Design Guidelines, Criteria & Standards, Volume 3 Water Engineering Project 2015, DPWH" (hereinafter referred to as "DPWH standard").

In the simulation model, the average values of the DPWH standard are basically applied (see Table 3.4.2). In addition to the DPWH standard, Japanese standard is also supplementary applied in case of the land use types which are not described in the DPWH standard. Regarding the land use map, the data in 2007 provided by the Department of Agrarian Reform (DAR) is applied, which is presented in Figure 3.4.5. Figure 3.4.5 shows the catchment area is composed of cultivated annual and perennial crops, open forest, shrubs and woodlands, and inland water body, etc.




Figure 3.4.5 Land Use Map

Source: JICA Survey Team

Table 3.4.2 Roughness Coefficients by Land Uses

Land Use	Roughness Coefficient	Standard		Applied Land Use in the Standards
		Filipino	Japanese	
Closed, forest, broadleaved	0.140	✓		Wooded
Forest plantation, broadleaved	0.140	✓		Wooded
Forest plantation, coniferous	0.140	✓		Wooded
Forest plantation, mangrove	0.060	✓		Scrub& Scattered Brush
Inland water	0.025		✓	Water body
Mangrove forest	0.060	✓		Scrub& Scattered Brush, Flood Plain
Open forest, broadleaved	0.060	✓		Scrub& Scattered Brush, Flood Plain
Other land, built-up area	0.031		✓	Road
Other land, cultivated, Annual crop	0.050	✓		Cultivated Land, Nature field crops
Other land, cultivated, Perennial	0.060	✓		Scrub& Scattered Brush
Other land, cultivated, perennial crop	0.060	✓		Scrub& Scattered Brush
Other land, fishpond	0.025		✓	Water body
Other land, natural, barren land	0.035	✓		Cultivated Land (No Crop)
Other land, natural, grassland	0.038	✓		Average value of [Pasture, Short Grass, No Brush: 0.033] and [Pasture, Tall Grass, No Brush: 0.043]
Other land, natural, marshland	0.030	✓	✓	Average value of [Cultivated Land (No Crop): 0.035] in the Philippine's standard and [Water Body: 0.025] in Japanese Standard
Other land, wooded land, fallow	0.060	✓		Scrub& Scattered Brush
Other land, wooded land, shrubs	0.060	✓		Scrub& Scattered Brush
Other land, wooded land, wooded grassland	0.060	✓		Scrub& Scattered Brush
Other land, wooded lands, shrubs	0.060	✓		Scrub& Scattered Brush

Source: JICA Survey Team

4) Rainfall

All the past rainfall records (1951-2016, Maximum 66 years) at the rainfall gauge stations in the Mindanao Island were collected from Philippines Atmospheric, Geophysical and Astronomical Services Administration (PAGASA) and National Irrigation Administration (NIA). As the result, 23 rainfall gauge stations are available for the analysis purpose.

The scarcity of the rainfall data within the immediate Project area is fatal for the analysis, so all the data of the rainfall stations which are located in and around the Mindanao River Basin (MRB) should be utilized for the analysis. In this context, the stations which have more than 15-year availability of full (365-day) data are also selected, and 12 of all the 23 stations are finally selected as target stations considering their location (neighbor of the MRB) and total record period (more than 15 years full data

availability).




Figure 3.4.6 Rainfall Gauge Stations

Source: JICA Survey Team

Table 3.4.3 Information of the Rainfall Gauge Stations

Station ID	Name of Locatoin	Gauge Type*	Long. (°)	Lati. (°)	Elevation (EL.m)	Record Period	Source
81	USM Kabacan	GR	124.839	7.114	20	1969-1985	PAGASA
653	Surigao Surigao del norte	SYN	125.489	9.783	39	1951-1979 1984-2016	PAGASA
741	Diplog Zamboanga del norte	SYN	123.345	8.603	4	1981-2016	PAGASA
746	Cotabato city Maguindanao	SYN	124.215	7.162	50	1951-1960 1986-2016	PAGASA
747	Lumbia airport Misamis oriental	SYN	124.612	8.409	182	1977-2013	PAGASA
748	El Salvador city Misamis Oriental	SYN	124.617	8.433	9	2013-2016	PAGASA
751	Malaybalay Bukidnon	SYN	125.134	8.151	627	1961-2016	PAGASA
752	Butuan city Agusan del norte	SYN	125.482	8.947	18	1981-2016	PAGASA
753	Davao city Davao del sur	SYN	125.655	7.128	17	1951-2016	PAGASA
755	Hinatuan Surigao del sur	SYN	126.338	8.367	3	1951-2016	PAGASA
836	Zamboanga city Zamboanga del norte	SYN	122.063	6.920	7	1951-2016	PAGASA
851	General Santos South cotabato	SYN	125.103	6.057	132	1951-2016	PAGASA
1008	Kisolon, Sumilao Bukidnon	CR	124.938	8.298	680	1980-2000	PAGASA
1202	Kapatagan Lanao del Norte	-	123.767	7.850	90	1971-2000	PAGASA
1203	Datu Piang Maguindanao	OR	124.500	7.033	9	1972-1987 1994-1998	PAGASA
1204	Parang Maguindanao	OR	124.267	7.383	85	1972-2000	PAGASA
1205	Carmen, Tauron Sultan Kudarat	OR	124.617	6.783	29	1960-2000	PAGASA
P01	PCA, Bago Oshiro Davao del sur	-	125.522	7.037	-	1981-2016	PAGASA
N01	Claver Surigao Del Norte	-	125.824	9.543	-	1980-1982	NIA
N02	Bubunawan Bukidnon	-	124.634	8.393	-	1988-1990	NIA
N03	Camp Phillips Bukidnon	-	124.813	8.323	-	1962-1987	NIA
N04	Malaybalay Bukidnon	-	125.134	8.136	-	1957-1965 1968-1975	NIA
N05	Midsayap North Cotabato	-	124.531	7.191	-	1956-1975	NIA

Target Stations

* SYN Synoptic Station
GR Agrometeorological Station
OR Official Rain Station
CR Cooperative Rain Station

Source: JICA Survey Team

Table 3.4.4 Data Availability of each Rainfall Gauge Station (○: 365-day data available)

ID	Name	1951	1952	1953	1954	1955	1956	1957	1958	1959	1960	1961	1962	1963	1964	1965	1966	1967	1968	1969	1970	1971	1972
81	USM																						
653	Surigao	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
741	Diplog																						
746	Cotabato city	○		○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
747	Lumbia airport																						
748	El Salvador city																						
751	Malaybalay											○	○	○	○	○	○	○	○	○	○	○	○
752	Butuan city																						
753	Davao city	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
755	Hinatuan				○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
836	Zamboanga city																						
851	General Santos	○	○	○		○	○			○			○	○	○	○	○	○	○	○	○	○	○
1008	Kisolon																						
1202	Kapatagan																						
1203	Datu Piang																						○
1204	Parang																						
1205	Carmen											○	○	○	○	○				○		○	○
P01	PCA																						
N01	Claver																						
N02	Bunawan																						
N03	Camp Philips													○	○	○	○	○	○	○	○	○	○
N04	Malaybalay								○	○	○	○	○	○	○	○				○	○	○	○
N05	Midsayap								○	○	○	○	○	○	○	○	○	○	○	○	○	○	○

ID	Name	1973	1974	1975	1976	1977	1978	1979	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992	1993	1994
81	USM			○	○			○	○														
653	Surigao	○	○	○	○			○							○	○	○	○	○	○	○	○	○
741	Diplog									○	○	○	○	○	○	○	○	○	○	○	○	○	○
746	Cotabato city																○	○	○	○	○	○	○
747	Lumbia airport							○	○	○	○	○	○		○	○	○	○	○	○	○	○	○
748	El Salvador city																						
751	Malaybalay	○	○	○					○			○			○	○	○	○	○	○	○	○	○
752	Butuan city									○	○	○	○	○	○	○	○	○	○	○	○	○	○
753	Davao city			○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
755	Hinatuan	○	○	○	○	○	○	○	○	○	○	○	○		○	○	○	○	○	○	○	○	○
836	Zamboanga city			○	○																		
851	General Santos	○	○	○	○	○		○	○	○	○		○	○	○	○	○	○	○	○	○	○	○
1008	Kisolon																						
1202	Kapatagan	○	○	○				○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
1203	Datu Piang	○	○	○	○	○	○	○	○	○	○	○	○	○	○								○
1204	Parang	○	○	○	○	○	○	○	○	○	○	○	○	○	○								○
1205	Carmen	○	○	○	○	○	○	○	○	○	○	○	○	○							○	○	○
P01	PCA																		○				○
N01	Claver									○													
N02	Bunawan																	○					
N03	Camp Philips	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○							
N04	Malaybalay	○	○																				
N05	Midsayap	○	○	○																			

ID	Name	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016
81	USM																						
653	Surigao	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
741	Diplog	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
746	Cotabato city	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
747	Lumbia airport	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
748	El Salvador city																					○	○
751	Malaybalay	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
752	Butuan city	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
753	Davao city	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
755	Hinatuan	○	○	○	○	○	○	○	○	○	○	○	○	○			○	○	○	○	○		○
836	Zamboanga city																						
851	General Santos	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
1008	Kisolon	○	○	○	○		○																
1202	Kapatagan	○	○	○	○																		
1203	Datu Piang	○																					
1204	Parang	○	○	○	○		○																
1205	Carmen	○																					
P01	PCA		○	○				○		○	○			○	○	○		○	○	○	○	○	○
N01	Claver																						
N02	Bunawan																						
N03	Camp Philips																						
N04	Malaybalay																						
N05	Midsayap																						

Source: JICA Survey Team

After the selection of the rainfall gauge stations, the basin mean rainfall data of the MRB is calculated with the Thiessen method. Based on the organized data shown in Table 3.4.3, 18 Thiessen division patterns for 52 years are finally created⁹. Figure 3.4.7 shows all the Thiessen division patterns applied in the analysis.

According to the Master Plan, the recommended rainfall duration for the flood analysis in the MRB is 4 days in due consideration of the lag time of runoff. Therefore, the four-day basin mean rainfall amount is calculated for all the 52 years (see Table 3.4.5), and the maximum probable rainfall amount is then calculated based on the four-day basin mean rainfall. The result of the probability calculation is shown in Table 3.4.6.

Table 3.4.5 Maximum 4-day Basin Mean Rainfall Amount in MRB

Thiessen Pattern	First Day	Final Day	RF. Amount (mm)	Thiessen Pattern	First Day	Final Day	RF. Amount (mm)
Pattern 01	1957/7/30	1957/8/2	87.0	Pattern 13	1987/7/2	1987/7/5	95.6
Pattern 01	1959/5/29	1959/6/1	90.1	Pattern 14	1988/3/30	1988/4/2	91.0
Pattern 02	1961/2/28	1961/3/3	55.4	Pattern 14	1989/4/13	1989/4/16	92.8
Pattern 03	1963/3/16	1963/3/19	96.3	Pattern 15	1990/8/2	1990/8/5	75.2
Pattern 04	1964/4/11	1964/4/14	131.2	Pattern 14	1991/5/13	1991/5/16	75.8
Pattern 03	1965/5/31	1965/6/3	83.7	Pattern 14	1992/10/23	1992/10/26	82.2
Pattern 05	1966/12/17	1966/12/20	179.5	Pattern 13	1993/7/2	1993/7/5	71.7
Pattern 05	1967/10/13	1967/10/16	97.8	Pattern 16	1994/6/5	1994/6/8	65.2
Pattern 03	1968/6/19	1968/6/22	73.4	Pattern 17	1995/8/30	1995/9/2	81.9
Pattern 05	1969/8/16	1969/8/19	90.2	Pattern 13	1997/7/9	1997/7/12	87.3
Pattern 05	1970/10/16	1970/10/19	106.5	Pattern 13	1998/11/7	1998/11/10	71.4
Pattern 03	1971/10/1	1971/10/4	104.2	Pattern 18	1999/8/31	1999/9/3	126.0
Pattern 03	1972/4/6	1972/4/9	78.4	Pattern 13	2000/8/15	2000/8/18	112.5
Pattern 06	1973/11/18	1973/11/21	85.5	Pattern 18	2001/11/2	2001/11/5	96.3
Pattern 06	1974/10/27	1974/10/30	77.1	Pattern 18	2004/5/29	2004/6/1	127.8
Pattern 07	1975/6/19	1975/6/22	101.6	Pattern 18	2005/9/7	2005/9/10	95.6
Pattern 08	1976/7/14	1976/7/17	78.7	Pattern 18	2006/3/6	2006/3/9	101.0
Pattern 08	1977/11/26	1977/11/29	112.9	Pattern 18	2007/7/10	2007/7/13	112.2
Pattern 09	1978/6/6	1978/6/9	160.1	Pattern 18	2008/5/8	2008/5/11	150.9
Pattern 08	1979/6/21	1979/6/24	79.7	Pattern 18	2009/7/24	2009/7/27	264.8
Pattern 08	1981/5/14	1981/5/17	69.1	Pattern 18	2010/9/29	2010/10/2	93.0
Pattern 08	1982/1/27	1982/1/30	78.8	Pattern 18	2011/10/7	2011/10/10	118.4
Pattern 10	1983/7/20	1983/7/23	95.2	Pattern 18	2012/9/21	2012/9/24	108.7
Pattern 11	1984/6/12	1984/6/15	70.1	Pattern 18	2013/10/4	2013/10/7	97.0
Pattern 11	1985/10/8	1985/10/11	76.2	Pattern 18	2014/1/11	2014/1/14	99.1
Pattern 12	1986/6/16	1986/6/19	92.7	Pattern 18	2016/7/27	2016/7/30	97.9

Source: JICA Survey Team

Table 3.4.6 Maximum 4-day Basin Mean Rainfall Amount in MRB¹⁰

Return Period	Gumbel	Iwai	Gev	SqrtEt
2	94.2	92.3	90.3	93.5
10	135.8	134.9	133.8	137.6
20	151.7	152.8	156.7	156.5
30	160.8	163.4	171.9	167.9
50	172.3	177.1	193.4	182.6
100	187.7	196.3	227.1	203.4
SLSC	0.186	0.094	0.048 (Applied)	0.115

Source: JICA Survey Team

⁹ In order to secure the accuracy of the basin mean rainfall amount of each Thiessen division pattern, at least 4 stations need to surround the MRB. Therefore, 14-year record of the 66-year was not applied.

¹⁰ The 52-year record was applied to each probability distribution model, namely, Gumbel distribution, Iwai method, Generalized extreme value distribution (Gev), and Square-root exponential type maximum distribution (SqrtEt), and Generalized extreme value distribution was selected as the most appropriate model based on the Standard Least Squares Criterion (SLSC).




Figure 3.4.7 Area Division Patterns for Thiessen Method (1/2)

Source: JICA Survey Team




Figure 3.4.7 Area Division Patterns for Thiessen Method (2/2)

Source: JICA Survey Team

5) Evaporation

Weather stations which measure the evaporation rate are fewer than the rainfall gauge station, and only six (6) pan-evaporation stations within the Mindanao Island are available. As for the model application, MIT station (Station ID: N03, Recording Period: 1957-1973) which is the only station in the MRB was selected. Since the data is monthly basis record, the daily evaporation amount is assumed by dividing the days of each month.

Table 3.4.7 Pan-Evaporation Stations in the Mindanao Island

Station ID	Name of Location		Long. (°)	Lati (°)	Elevation (EL.m)	Record Period	Source
N01	Bula	General Santos	125.1904	6.1094	6	1957-1973	NIA
N02	Dadiangas	General Santos	125.1726	6.1182	19	1959-1965	NIA
N03	Mindanao Institute of Technology (MIT)	Kabacan	124.8391	7.1136	30	1957-1973	NIA
N04	Mindanao State University	Malawi	124.2605	7.9984	780	1969-1984	NIA
N05	Tagum	Davao del Norte	125.6298	7.5302	35	1977-1988	NIA
P01	PCA	Davao del Sur	125.5217	7.0367	8	2007-2016	PAGASA

Source: JICA Survey Team




Figure 3.4.8 Location of the Pan-Evaporation Stations

Source: JICA Survey Team




Figure 3.4.9 Monthly and Daily Evaporation at MIT Station

Source: JICA Survey Team

6) Runoff Coefficient

Likewise, the roughness coefficient, the runoff coefficient is determined based on the land use type. Since the values utilized in this simulation have been chosen according to the Master Plan, the same values are applied as indicated in the Table 3.4.8.

Table 3.4.8 Runoff Coefficient by Land Use Category

ID	Category	SYMBOL	Runoff Coefficient
1	Closed forest, broadleaved	NF4F	0.55
4	Open forest, broadleaved	NF2B	0.55
7	Mangrove forest	NFM	0.80
8	Forest plantation, broadleaved	FPB	0.55
9	Forest plantation, coniferous	FPC	0.55
10	Other wooded land, shrubs	Sh	0.55
12	Other wooded land, wooded grassland	WGL	0.25
13	Other land, natural, barren land	BL	0.30
14	Other land, natural, grassland	GL	0.25
15	Other land, natural, marshland	ML	0.80
16	Other land, cultivated, annual crop	AC	0.25
17	Other land, cultivated, perennial crop	PC	0.25
19	Other land, fishpond	Fs	0.30
20	Other land, built-up area	BUA	0.50
21	Inland water	IW	0.80

Source: JICA Survey Team

3.4.3 Model Design

1) Model Area

Considering the very limited available data, area covering the maximum inundation area, which was analyzed in the Master Plan, and the river mouth are selected as the model area. The model area is therefore designed as the 82,000m x 62,000m of the rectangle area divided by 500 m mesh (Total: 165x125 = 20,625 meshes). Figure 3.4.10 and Table 3.4.9 show the model extent for the



Table 3.4.9 Model Extent

Direction	Coordination (WGS84 UTM51N)			
	Minimum (m)	Maximum (m)	Mesh Size (m)	Total Mesh (nos)
X (E-W)	626,000	708,000	500	165
Y (N-S)	745,000	807,000	500	125


Source: JICA Survey Team

Figure 3.4.10 Model Area Selected in the Simulation

Source: JICA Survey Team

2) River Alignment and Cross Section

Though the model deals with the whole MRB, only the Pulangi, Rio Grande de Mindanao and Tamontaka rivers including the Tunggol floodway are considered in the model (see the blue lines in Figure 3.4.11). The alignment and cross sections of the rivers were surveyed from Nov. 2017 to Jan. 2018. The survey area and the cross sections with the interval 1.0 - 2.0 km are summarized below:



River	Number of the Cross Section
Pulangi	75
Tamontaka	18
Rio Grande de Mindanao	28
Tunggol Floodway	3
Total	124

Figure 3.4.11 Bathymetric Survey Area

Source: JICA Survey Team

3) River Alignment and Cross Section

Discharge volume at the upstream end of the model and at the confluences to the modeled rivers are calculated. According to the result of determination of the river alignment and basin boundaries (see “3.4.2 General Conditions of the Simulation, 2) River Alignments and Basin Boundaries”), 14 confluences to the modeled rivers are defined including the upstream end of the model and confluences to the Liguasan marsh (see Figure 3.4.12). Those 14 confluences are referred to as “input point”. The discharge volume of the input points is calculated by summing up the i) base flow and ii) flood discharge of the related sub-basins of all the 86 sub-basins. The procedures to determine the base flow and flood discharge in response to the rainfall amount at each input point is described below¹¹.




Figure 3.4.12 Discharge Input Points in the Simulation Model

Source: JICA Survey Team

i) Base Flow

- ✓ The water level at the time of base flow is assumed as EL.3.2m, which is based on the actual water level record at the end of the dry season in 1987 at Paidu Pulangi.
- ✓ Preliminary simulation without rainfall was conducted and $0.01485\text{m}^3/\text{s}/\text{km}^2$ is estimated as the average specific discharge in the MRB, which results in the water level at Paidu Pulangi being EL. 3.2m.
- ✓ Based on the average specific discharge, base flow discharge at each input point is determined considering each catchment area of the input points.

ii) Flood Discharge

- ✓ Probable 4-day basin mean rainfall amount in the MRB is calculated (see “3.4.2 General Conditions of the Simulation, 4) Rainfall”).

¹¹ Note that the discharge volume of the input point is calculated in response to the rainfall amount while the discharge sub-basins of the modeled rivers is directly calculated by the model, which means the rainfall parameter is given only on those sub-basins.

- ✓ Rainfall intensity (hourly rainfall distribution) is determined based on the center concentrated pattern which is the standard rainfall distribution for the MRB stated in the Master Plan (see Figure 3.4.13).





Figure 3.4.13 Calculation Procedure of 4-Day Hourly Rainfall Distribution

Source: JICA Survey Team

- ✓ The effective rainfall to discharge is calculated by multiplying the runoff coefficient which is determined on “3.4.2 General Conditions of the Simulation, 6) Runoff Coefficient”, which excludes the rainfall that becomes vapor or groundwater.
- ✓ Complying with the Master Plan, modified Snyder’s Unit hydrograph method is applied to represent the time series discharge volume generated by unit effective rainfall. Basin lag time, the time from the beginning of the rainfall event to peak discharge at the outlet of the basin, was calculated for each sub-basin (see Figure 3.4.14).



$$X = \% \text{ of } (Lg+D/2)$$

$$Lg=0.165(L \times Lca / S^{0.5})^{0.382}$$

Lg: Basin lag time (hr)

L: Length of the longest river from the point of the interest to basin divide (km)

Lca: Length of the river from the point of interest to the intersection of perpendicular from the centroid of the sub-basin to stream alignment (km)

S: Overall slope of the longest river from the point of interest to basin divide

D: Duration of unit excess rainfall (= 1hr)

$$Y = Q (Lg + D/2) / V$$

Q: Discharge (m³/s)

V: One day average excess rainfall volume (=Total excess rainfall volume within D / 24/ 60 /60)

Figure 3.4.14 Unit Hydro Graph for the Mindanao River Basin (MRB)

Source: JICA Survey Team

- ✓ Then, the times series data of the discharge volume in response to each hourly rainfall amount for each basin is calculated considering the river network and flow velocity on each sub-basin (see Figure 3.4.15). The flow velocity is calculated based on the Kraven Formula (see Table 3.4.10).




Figure 3.4.15 Image of the Superposition Method by each Unit Hydrograph
Source: JICA Survey Team

Table 3.4.10 Flood velocity by Kraven Formula

River bed slope	more than 1/100	1/100 - 1/200	less than 1/200
Flow Velocity (m/s)	3.5	3.0	2.1

Source: JICA Survey Team


iii) Time Series Discharge at an Input Point

A time series discharge at the input points is finally generated by accumulating the base flow and flood discharge from each sub-basin shown in Figure 3.4.16. Table 3.4.11 summarizes the sub-basin parameters for the 86 MRB sub-basins which characterize the flow time on the river and the lag time in response to the length of river, the shape of basin, and the river bed slope.


i) Base Flow



ii) Flood Discharge



Tn: Flood Flow Time



iii) Time Series Discharge at an Input Point

Figure 3.4.16 Image of Time Series Discharge at an Input Point

Source: JICA Survey Team

Table 3.4.11 Sub-basin Parameters

Basin_ID	BASIN	Subbasins	Area (km ²)	River Length (km)	Elevation			Slope		Lca (km)	Lg (hr)	Runoff Coefficient	Target Input Point	Flood Flow time ² (hr)
					Start (EL.m)	End (EL.m)	Difference (m)	Original (%)	Modified ¹ (%)					
R01	Pulangi	Ala_B01	570.3	64.4	1536.0	119.3	1,416.7	2.20	2.20	44.13	7.1	0.43	4	9.15
R02	Pulangi	Ala_B02	291.9	36.4	119.3	41.7	77.6	0.21	0.21	24.12	7.1	0.33	4	4.33
R03	Pulangi	Ala_B03	114.2	26.6	41.7	8.0	33.7	0.13	0.13	14.15	5.7	0.26	4	0.81
R04	Rio Grande	Ambal-Simuyay_B01	585.4	54.9	1967.9	52.0	1,915.9	3.49	3.49	25.32	5.0	0.43	12	3.56
R05	Rio Grande	Ambal-Simuyay_B02	107.0	26.9	52.0	1.0	51.0	0.19	0.19	14.66	5.4	0.29	12	0.00
R06	Pulangi	Banca_B01	679.5	93.3	1047.7	42.0	1,005.7	1.08	1.08	51.56	10.0	0.30	4	5.09
R07	Pulangi	Bulanan_B01	105.1	23.9	75.2	8.3	66.9	0.28	0.28	13.23	4.6	0.26	9	3.61
R08	Pulangi	Buluan_B01	1897.8	96.7	622.1	8.2	613.9	0.63	0.63	50.49	11.1	0.38	3	2.46
R09	Pulangi	Buluan_B02	230.3	41.2	91.7	6.4	85.3	0.21	0.21	17.18	6.6	0.27	3	1.95
R10	Tamontaka	Cabilanan_B01	704.7	98.3	1306.2	300.4	1,005.8	1.02	1.02	50.21	10.2	0.44	13	13.62
R11	Tamontaka	Cabilanan_B02	420.7	67.7	1201.7	300.4	901.3	1.33	1.33	42.41	7.9	0.45	13	13.62
R12	Tamontaka	Cabilanan_B03	330.9	52.3	300.4	13.0	287.4	0.55	0.55	21.66	6.5	0.32	13	6.71
R13	Tamontaka	Cabilanan_B04	517.1	79.9	675.8	7.7	668.1	0.84	0.84	45.49	9.4	0.31	13	4.99
R14	Pulangi	Calabugao_B01	1050.0	138.7	1455.5	302.0	1,153.5	0.83	0.83	83.43	14.7	0.41	1	23.58
R15	Pulangi	Calabugao_B02	321.9	39.9	1080.4	352.2	728.2	1.83	1.83	13.82	4.0	0.47	1	27.63
R16	Tamontaka	Dalika_B01	433.6	54.8	499.8	8.3	491.5	0.90	0.90	27.05	6.6	0.35	13	4.22
R17	Pulangi	Kabacan_B01	925.9	84.7	1912.6	17.5	1,895.1	2.24	2.24	47.98	8.2	0.32	1	2.07
R18	Pulangi	Kapingkong_B01	195.1	47.3	1411.0	119.3	1,291.7	2.73	2.73	26.55	5.0	0.42	4	9.15
R19	Pulangi	Kapingkong_B02	198.8	32.0	932.9	159.5	773.4	2.42	2.42	15.59	3.6	0.48	4	10.35
R20	Rio Grande	Libungan_B01	574.5	84.0	1991.8	7.8	1,984.0	2.36	2.36	46.21	7.9	0.35	10	2.00
R21	Pulangi	Liguasan_B01	22.5	11.4	18.3	8.0	10.3	0.09	0.09	10.15	3.9	0.25	3	0.66
R22	Pulangi	Liguasan_B02	16.2	7.3	14.4	6.8	7.6	0.10	0.10	4.00	2.2	0.26	3	1.08
R23	Pulangi	Mlang_B01	457.3	51.7	389.7	7.9	381.8	0.74	0.74	23.47	6.4	0.36	2	1.40
R24	Pulangi	Mlang_B02	709.9	73.4	1074.2	7.9	1,066.3	1.45	1.45	46.02	8.2	0.34	3	2.42
R25	Pulangi	Maitubog_B01	597.3	100.5	1484.8	19.5	1,465.3	1.46	1.46	57.26	10.1	0.37	1	3.13
R26	Rio Grande	Manuangan_B01	199.0	18.8	306.4	7.4	299.0	1.59	1.59	7.35	2.4	0.37	10	2.37
R27	Pulangi	Manupali_B01	487.4	67.6	2123.3	302.0	1,821.3	2.69	2.69	31.03	6.1	0.37	1	23.58
R28	Pulangi	Manupali_B02	519.9	54.3	1878.1	310.8	1,567.3	2.88	2.88	29.33	5.4	0.39	1	24.17
R29	Pulangi	Maridagao_B01	1438.2	151.1	1244.2	19.5	1,224.7	0.81	0.81	98.63	16.3	0.32	1	3.13
R30	Pulangi	Maridagao_B02	54.9	23.7	19.5	13.5	6.0	0.03	0.03	17.58	8.0	0.37	1	0.00
R31	Pulangi	Muleta_B01	1050.4	128.3	2175.8	27.5	2,148.3	1.67	1.67	53.46	10.5	0.30	1	5.72
R32	Pulangi	Panulapan_B01	140.1	34.4	78.0	6.0	72.0	0.21	0.21	16.62	6.1	0.30	6	0.00
R33	Pulangi	Pulangi_B01	1680.2	135.1	302.0	27.5	274.5	0.20	0.20	87.12	19.3	0.38	1	5.72
R34	Pulangi	Pulangi_B02	329.9	43.2	27.5	13.5	14.0	0.03	0.03	25.92	11.2	0.26	1	0.00
R35	Pulangi	Pulangi_B03	46.7	14.3	13.5	9.5	4.0	0.03	0.03	5.71	4.2	0.35	99	-
R36	Pulangi	Pulangi_B04	376.0	69.4	1178.6	50.9	1,127.7	1.62	1.62	57.29	8.6	0.53	1	10.55
R37	Pulangi	Pulangi_B05	177.8	39.2	1253.2	94.0	1,159.2	2.95	2.95	21.09	4.2	0.46	1	12.67
R38	Pulangi	Pulangi_B06	329.0	62.9	874.6	33.0	841.6	1.34	1.34	27.47	6.5	0.29	1	7.59
R39	Tamontaka	Residual_B01	165.3	22.8	530.4	1.0	529.4	2.32	2.32	10.98	2.8	0.34		0.00
R40	Tamontaka	Residual_B02	118.6	27.0	564.7	7.8	556.9	2.06	2.06	13.87	3.3	0.33	13	1.33
R41	Tamontaka	Residual_B03	76.6	19.7	675.4	6.7	668.7	3.40	3.40	11.30	2.5	0.35	13	1.88
R42	Tamontaka	Residual_B04	81.1	22.7	257.5	2.8	254.7	1.12	1.12	13.24	3.4	0.33	13	2.19
R43	Pulangi	Residual_B05	27.8	14.0	37.8	5.2	32.6	0.23	0.23	8.55	3.3	0.25	9	3.20
R44	Pulangi	Residual_B06	30.1	8.2	11.8	7.4	4.4	0.05	0.05	5.25	2.9	0.29	8	1.60
R45	Pulangi	Residual_B07	37.5	15.7	21.5	7.2	14.3	0.09	0.09	7.62	3.9	0.26	5	0.74
R46	Rio Grande	Residual_B08	30.9	9.8	28.4	4.5	23.9	0.24	0.24	5.76	2.4	0.25	11	2.61
R47	Rio Grande	Residual_B09	35.9	15.9	54.4	3.2	51.2	0.32	0.32	8.30	3.2	0.31	11	0.76
R48	Rio Grande	Rio Grande_B01	7.6	5.4	1.0	0.0	1.0	0.02	0.02	2.55	2.3	0.33	99	-
R49	Tamontaka	Tamontaka_B01	14.1	8.2	1.0	0.0	1.0	0.01	0.01	4.71	3.7	0.41	99	-
R50	Pulangi	Bulanan_M01	43.8	9.3	8.3	5.1	3.2	0.03	0.03	7.23	3.8	0.45	9	2.37
R51	Pulangi	Bulanan_M02	17.7	12.0	8.2	4.1	4.1	0.03	0.03	6.97	4.1	0.42	9	1.92
R52	Pulangi	Bulanan_M03	18.9	9.6	5.1	4.5	0.6	0.01	0.01	6.33	4.6	0.44	9	1.11
R53	Pulangi	Bulanan_M04	43.2	8.4	4.5	4.0	0.5	0.01	0.01	4.29	3.8	0.29	9	0.00
R54	Rio Grande	Libungan_M01	41.8	15.1	7.8	3.0	4.8	0.03	0.03	7.85	4.8	0.69	10	0.00
R55	Rio Grande	Libungan_M02	91.6	18.0	13.1	3.5	9.6	0.05	0.05	11.79	5.4	0.59	10	0.28
R56	Rio Grande_Marsh	Liguasan_M01	11.5	7.8	7.8	6.4	1.4	0.02	0.02	4.73	3.4	0.79	5	0.00
R57	Pulangi	Liguasan_M02	22.0	13.6	8.0	6.4	1.6	0.01	0.01	8.35	5.7	0.54	99	-
R58	Pulangi	Liguasan_M03	1.5	4.4	6.8	6.8	0.0	0.00	0.01	2.09	2.2	0.79	99	-
R59	Rio Grande_Marsh	Liguasan_M04	25.5	6.0	7.4	6.8	0.6	0.01	0.01	4.96	3.5	0.75	99	-
R60	Pulangi	Liguasan_M05	8.5	8.2	6.8	6.8	0.0	0.00	0.01	3.89	3.6	0.67	3	0.00
R61	Pulangi	Liguasan_M06	8.7	5.0	8.0	6.8	1.2	0.02	0.02	3.20	2.3	0.28	3	0.00
R62	Pulangi	Liguasan_M07	125.4	27.8	13.5	7.4	6.1	0.02	0.02	15.63	8.4	0.72	99	-
R63	Pulangi	Liguasan_M08	35.9	10.6	7.9	7.4	0.5	0.00	0.01	7.75	5.2	0.80	2	0.00
R64	Pulangi	Liguasan_M09	62.3	10.1	7.9	6.8	1.1	0.01	0.01	5.25	4.3	0.80	3	1.08
R65	Pulangi	Liguasan_M10	18.1	4.6	6.8	6.8	0.0	0.00	0.01	1.80	2.1	0.48	3	1.08
R66	Pulangi	Liguasan_M11	2.4	1.9	6.4	6.8	-0.4	(0.02)	0.01	0.88	1.2	0.80	3	1.69
R67	Pulangi	Liguasan_M12	8.2	5.8	8.2	6.8	1.4	0.02	0.02	3.59	2.6	0.73	3	1.69
R68	Rio Grande	Manuangan_M01	14.8	8.8	7.4	3.5	3.9	0.04	0.04	3.79	2.8	0.65	10	1.20
R69	Pulangi	Panulapan_M01	118.9	8.0	6.0	6.0	0.0	0.00	0.01	7.95	4.7	0.56	99	-
R70	Pulangi	Pulangi_M01	16.6	39.8	9.5	6.4	3.1	0.01	0.01	18.43	11.9	0.55	99	-
R71	Pulangi	Pulangi_M02	30.4	36.2	6.4	3.4	3.0	0.01	0.01	21.84	12.3	0.54	99	-
R72	Tamontaka	Residual_M01	2.1	3.9	2.6	2.6	0.0	0.00	0.01	2.16	2.2	0.80	13	0.00
R73	Tamontaka	Residual_M02	5.3	6.1	7.8	2.6	5.2	0.09	0.09	2.08	1.7	0.74	13	0.52
R74	Tamontaka	Residual_M03	24.3	8.2	2.7	2.6	0.1	0.00	0.01	5.27	4.0	0.71	13	0.52
R75	Tamontaka	Residual_M04	11.8	8.1	6.7	2.7	4.0	0.05	0.05	3.41	2.5	0.57	13	0.81
R76	Tamontaka	Residual_M05	31.2	9.3	2.8	2.7	0.1	0.00	0.01	7.68	4.9	0.69	13	0.96
R77	Tamontaka	Residual_M06	24.5	19.7	8.3	2.7	5.6	0.03	0.03	9.29	5.7	0.64	13	1.61
R78	Tamontaka	Residual_M07	108.5	19.8	7.7	3.1	4.6	0.02	0.02	6.88	5.3	0.46	13	2.37
R79	Rio Grande	Residual_M08	2.0	3.7	4.5	1.1	3.4	0.09	0.09	1.74	1.3	0.25	11	0.00
R80	Rio Grande	Residual_M09	16.0	5.1	3.2	2.2	1.0	0.02	0.02	3.80	2.6	0.25	11	0.09
R81	Pulangi	Residual_M10	10.2	6.2	5.2	5.1	0.1	0.00	0.01	5.57	3.7	0.54	9	2.37
R82	Pulangi	Residual_M11	46.5	6.0	5.5	5.4	0.1	0.00	0.01	4.16	3.3	0.31	7	0.00
R83	Pulangi	Residual_M12	32.9	12.1	7.4	4.8	2.6	0.02	0.02	7.17	4.6	0.32	8	0.00
R84	Pulangi	Residual_M13	9.6	5.6	7.2	6.4	0.8	0.01	0.01	1.92	2.2	0.47	5	0.00
R85	Rio Grande	Rio Grande_M01	73.8	28.1	3.4	1.0	2.4	0.01	0.01	11.21	8.6	0.38	99	-
R86	Tamontaka	Tamontaka_M01	53.0	27.8	3.4	1.0	2.4	0.01	0.01	12.55	9.0	0.48	99	-

*1: In case difference of the elevation is 0 or negative, 1/10,000 is adopted to river slope.

*2: "-" means the watersheds which outflow flows into the modeled rivers directly.

Source: JICA Survey Team

3.4.4 Simulation Theory

To represent both the flow on the river and on the flood plain, the integrated model of one and two-dimensional model is selected. The governing equations are shown as below and the simulation is executed with software namely "MIKE Series", which is produced by DHI, a Danish company, which is widely used all over the world.

1) Fundamental Equation for One (1) Dimension Model (for River Flow)

a) Continuity equation

$$\frac{\partial Q}{\partial x} + \frac{\partial A}{\partial t} = q$$

b) Motion equation

$$\frac{\partial Q}{\partial t} + \frac{\partial \left(\alpha \frac{Q^2}{A} \right)}{\partial t} + gA \frac{\partial h}{\partial t} + \frac{gQ|Q|}{C^2 AR} = 0$$

Where;

Q:	Discharge (m ³ /s)
A:	Cross-section area of flow (m ²)
q:	Lateral inflow (m ³ /s)
*This values show outflow volume from river to flood plain or inflow volume from flood plain to river	
t:	time (s)
α:	Coefficient for momentum distribution
g:	Acceleration of gravity (m/s ²)
h:	Water depth (m)
C:	Chezy resistance (m ^{0.5} /s)
R:	Wetted perimeter (m)

2) Fundamental Equation for Two (2) Dimension Model (for Flood Plain)

a) Continuity equation

$$\frac{\partial \zeta}{\partial t} + \frac{\partial p}{\partial x} + \frac{\partial q}{\partial y} = \frac{\partial d}{\partial t}$$

b) Motion equation

X direction

$$\begin{aligned} & \frac{\partial p}{\partial t} + \frac{\partial}{\partial x} \left(\frac{p^2}{h} \right) + \frac{\partial}{\partial y} \left(\frac{pq}{h} \right) + gh \frac{\partial \zeta}{\partial x} + \\ & + \frac{gp\sqrt{p^2 + q^2}}{C^2 h^2} - \frac{1}{p_w} \left[\frac{\partial}{\partial x} (h\tau_{xx}) + \frac{\partial}{\partial y} (h\tau_{xy}) \right] - \Omega q + \Omega p + \\ & - fVV_x - \frac{h}{p_w} \frac{\partial}{\partial x} (p_a) = 0 \end{aligned}$$

Y direction

$$\begin{aligned} & \frac{\partial q}{\partial t} + \frac{\partial}{\partial y} \left(\frac{q^2}{h} \right) + \frac{\partial}{\partial x} \left(\frac{pq}{h} \right) + gh \frac{\partial \zeta}{\partial y} + \\ & + \frac{gp\sqrt{p^2 + q^2}}{C^2 h^2} - \frac{1}{p_w} \left[\frac{\partial}{\partial y} (h\tau_{yy}) + \frac{\partial}{\partial x} (h\tau_{xy}) \right] + \Omega p \\ & - fVV_y - \frac{h}{p_w} \frac{\partial}{\partial y} (p_a) = 0 \end{aligned}$$

Where;

h(x,y,t)	Water depth (=ζ-d, m)
d(x,y,t)	Time varying water depth (m)
ζ	Surface Elevation (m)
p,q(x,y,t)	flux densities in x- and y-directions (m ³ /s/m) = (uh, vh); (u,v)= depth averaged velocities in x- and y-directions
C(x,y)	Chezy resistance (m ^{1/2} /s)
g	Acceleration due to gravity (m/s ²)
f(V)	wind friction factor
V,V _x ,V _y (x,y,t)	Wind speed and components in x- and y-direction (m/s)
Ω(x,y)	Coriolis parameter, latitude dependent (s ⁻¹)
p _a (x,y,t)	Atmospheric pressure (kg/m ²)
p _w	Density of water (kg/m ³)
x,y	space coordinates (m)
t	time(s)
τ _{xx} , τ _{xy} , τ _{yy}	Components of effective shear stress

3.5 Flood Simulation with/without Dike

The dike would have a significant impact on the beneficially area in LMSA, while it cause some adverse effects. Since total flood volume is not changed by the dike construction, the overflowed discharge to the Liguasan marsh will be increased due to smaller flow area upon construction of the dyke (see Figure 3.5.1). The flood simulation with/without dike is conducted to assess such impact focusing on the change of water level of the Liguasan marsh and the Pulangi river, and change in inundation area of the Liguasan marsh between with and without the dike.




Figure 3.5.1 Image of Flood Condition With/Without Dike

Source: JICA Survey Team

3.5.1 Specific Conditions for Flood Simulation with/without Dike

1) Simulation Cases

Return periods of the 4-day mean rainfall of the catchments area are 2, 10, 20, 30, 50 and 100 years, and those are applied into the both two cases (with and without dike). In total, the simulation is executed in 12 cases (see Table 3.5.1).

Table 3.5.1 Simulation Cases for With/Without Dike

Simulation Case	Probability	Return Period					
		2	10	20	30	50	100
1. Present Condition (without dike)		○	○	○	○	○	○
2. After Construction of the Dike (With Dike)		○	○	○	○	○	○

Source: JICA Survey Team

2) Simulation Period

The simulation period for one flood event is set at 480 hours considering the flood retardant time. In addition to the simulation period, 240 hours for warm-up time is prepared to make the model steady¹ to run.

3) Dike

The dike is placed along the right bank of the Pulangi river encompassing the LMSA. The height of the dike is set to be enough tall to avoid any flood water from the Pulangi river to come into the LMSA.

¹ Initial condition of the water level and discharge is determined by the preliminary simulation, and the initial surface water area is determined by the simulation of 2-year return period.

3.5.2 Simulation Result-1 (Inundation Area)

Assuming the red solid line area in Figure 3.5.2 as the Liguasan marsh, maximum inundation area by each return period is calculated. Table 3.5.2 shows the comparison of maximum inundation area between (1) Present condition (without dike) and (2) After construction of the dike (with dike). The results indicate the inundation area is increased by at least 19% in case of 2-year return period rainfall after construction of the dike, and is increased by as much as 34% in case of 100-year return period, which is the design return period for the flood control structure according to the DPWH standard.




Figure 3.5.2 Area of the Liguasan Marsh
Source: JICA Survey Team

Table 3.5.2 Maximum Inundation area in the Liguasan Marsh

Return Period (year)	Inundation Area (km ²)		(3) Increase ratio (=2)/(1)
	(1) Present Condition (without Dike)	(2) After Construction of the Dike	
2	181	215	1.19
10	204	244	1.20
20	214	265	1.24
30	220	275	1.25
50	229	299	1.31
100	241	323	1.34

Source: JICA Survey Team




Figure 3.5.3 Simulation Results (Maximum Inundation Area) (1/2)

Source: JICA Survey Team




Figure 3.5.3 Simulation Results (Maximum Inundation Area) (2/2)

Source: JICA Survey Team

3.5.3 Simulation Result-2 (Flood Water Level)

As an indicator of the water level in the Liguasan marsh, the point "Marsh 2" is selected for the evaluation purpose (see Figure 3.5.4). Table 3.5.3 shows the maximum flood water level at Marsh 2 during the flood event at each of the return periods. The results indicate the maximum flood water level at the Marsh 2 rises by 65 to 81cm because of the dike, which means more river water overflows to the left bank of the Pulangi river and is stored in the Liguasan marsh.



Figure 3.5.4 Location of "Marsh 2" Point
Source: JICA Survey Team

Table 3.5.3 Maximum Flood Water Level at "Marsh 2" Point

Return Period (year)	Maximum Flood Water Level (EL.m)		(3) Difference (= (2)-(1)) (m)
	(1) Present Condition (without Dike)	(2) After Construction of the Dike	
2	7.23	8.02	0.79
10	7.62	8.42	0.80
20	7.85	8.50	0.65
30	8.02	8.70	0.68
50	8.21	9.02	0.81
100	8.49	9.29	0.80

Source: JICA Survey Team

Meanwhile, maximum water level of the Pulangi river at "Paidu Pulangi" (see Figure 3.5.5) shows an opposite trend due to the impact of the dike. Table 3.5.4 compares the maximum water level at this point with and without the dike, which indicates the maximum water level after the construction of the dike becomes lower (-13 to -70cm) than the one under the present condition. This phenomenon is caused by the change of the flood path due to the dike construction as below and shown in Figure 3.5.6.

- ✓ Under the present condition, flood water from the upstream flows to the LMSA and the Liguasan marsh, and concentrates at the bottleneck point formed by the residual hills (bottleneck point-1). Considering the topographic condition, the bottleneck point-1 has relatively smaller discharge capacity, so that the inundation area spreads from the bottleneck point-1 to the upstream area.
- ✓ After the construction of the dike, the flood water diverges at the north-east edge of the dike, mostly toward the south (to the Liguasan marsh) and partly toward the west (to the north of the LMSA). It is because that the flood water flows along the limited paths, the discharge volume to the south becomes larger compared to that under the condition without dike. Then, another bottleneck point is formed between the residual hill and the dike (bottleneck point-2), so that larger volume of flood water concentrates at the bottleneck point-2, and inundation area spreads from this point. Since the point-1, Paidu Pulangi, is located at the downstream side of the bottleneck point-2, the discharge volume at this point becomes smaller due to the storage effect at bottleneck point-2.




Figure 3.5.5 Location of "Paidu Pulangi" Point
Source: JICA Survey Team

Table 3.5.4 Maximum Water Level at "Paidu Pulangi" Point

Return Period (year)	Maximum Flood Water Level (EL.m)		(3) Difference (= (2)-(1)) (m)
	(1) Present Condition (without Dike)	(2) After Construction of the Dike	
2	6.93	6.80	-0.13
10	7.42	7.00	-0.42
20	7.65	7.13	-0.52
30	7.80	7.25	-0.55
50	8.00	7.43	-0.57
100	8.28	7.58	-0.70

Source: JICA Survey Team






Figure 3.5.6 Comparison of the Flood Path between with/without the Dike
 Source: JICA Survey Team

Change of water level and discharge at each point for 2-year to 100-year return period is summarized in Figures 3.5.7 to 3.5.18, showing that water level at Paidu Pulangi keeps longer peak water level after the dike construction compared to that of the present condition.




Flood Water Level




River Discharge

Figure 3.5.7 Flood Water Level and River Discharge (Present Condition) (Return Period: 2 year)

Source: JICA Survey Team




Flood Water Level




River Discharge

Figure 3.5.8 Flood Water Level and River Discharge (Present Condition) (Return Period: 10 year)

Source: JICA Survey Team




Flood Water Level




River Discharge

Figure 3.5.9 Flood Water Level and River Discharge (Present Condition) (Return Period: 20 year)

Source: JICA Survey Team




Flood Water Level




River Discharge

Figure 3.5.10 Flood Water Level and River Discharge (Present Condition) (Return Period: 30 year)

Source: JICA Survey Team




Flood Water Level




River Discharge

Figure 3.5.11 Flood Water Level and River Discharge (Present Condition) (Return Period: 50 year)

Source: JICA Survey Team




Flood Water Level




river Discharge

Figure 3.5.12 Flood Water Level and River Discharge (Present Condition) (Return Period: 100 year)

Source: JICA Survey Team




Flood Water Level




River Discharge

Figure 3.5.13 Flood Water Level and River Discharge (After Construction of the Dike) (Return Period: 2 year)

Source: JICA Survey Team




Flood Water Level




River Discharge

Figure 3.5.14 Flood Water Level and River Discharge (After Construction of the Dike) (Return Period: 10 year)

Source: JICA Survey Team




Flood Water Level




River Discharge

Figure 3.5.15 Flood Water Level and River Discharge (After Construction of the Dike) (Return Period: 20 year)

Source: JICA Survey Team




Flood Water Level




River Discharge

Figure 3.5.16 Flood Water Level and River Discharge (After Construction of the Dike) (Return Period: 30 year)

Source: JICA Survey Team




Flood Water Level




River Discharge

Figure 3.5.17 Flood Water Level and River Discharge (After Construction of the Dike) (Return Period: 50 year)

Source: JICA Survey Team



Flood Water Level



River Discharge

Figure 3.5.18 Flood Water Level and River Discharge (After Construction of the Dike) (Return Period: 100 year)

Source: JICA Survey Team

According to the aforementioned simulation results, flood water level of the Liguasan marsh would become higher after the dike construction. Current design height of the dike was determined by NIA based on the past maximum flood water level (under present condition), and the rise in water level by the dike has not been taken into account. In this context, the present dike design by NIA is evaluated as follows:

Current design is based on the flood water level observed in 2009, which is EL. 8.01 at the bottleneck point-2 (see Figure 3.5.6). Table 3.5.5 shows the simulation results of the maximum water level at the bottleneck point-2. EL.8.01m can be regarded as approximately 40-year return period flood event, and the water level would become 50cm higher at that time by the dike. Thus, the result implies that the dike height should be 50cm higher than that of the current design.

Table 3.5.5 Maximum Flood Water Level at "Bottleneck Point-2"

Return Period (year)	(1) Present Condition (without Dike) (EL.m)	(2) After Construction of the Dike (with Dike) (EL.m)	(3) Difference (= (2)-(1)) (m)
2	7.14	7.71	0.57
10	7.59	8.10	0.51
20	7.81	8.19	0.38
30	7.96	8.39	0.43
50	8.16	8.70	0.54
100	8.44	9.02	0.58

EL.8.01m can be regarded as approximately 40-year return period flood water

Flood water level would become 50 cm higher by the construction of the dike.

Source: JICA Survey Team

In case that the dike height is 50cm higher than the current design height, the construction cost (direct cost) of the dike becomes 2,294.5 million PHP (5,185.5 million JPY).

Table 3.5.6 Construction Cost (Direct Cost) of the Dike (Height is 50cm Higher than the Current Design)

Work Items	(1) Quantity	(2) Unit Cost (PHP)	(3) Total (= (1) x (2))	
			(million PHP)	(million JPY)
Back Filling of the Dike	988,000 m ³	804	794.4	1,795.3
Founding Treatment (Sand Compaction Pile Works)	84,797 piles	17,700	1500.1	3,390.2
Grand Total			2294.5	5,185.5

Source: JICA Survey Team

3.6 Inland Inundation Simulation with/without Drainage Structures

After the construction of the dike, the LMSA will be closed by the surrounding dikes (see Figure 3.6.1). Under such condition, rainfall will be stored in the LMSA, if there is no drainage systems, which makes some areas in the LMSA inundated according to the results of the simple rainfall- evaporation model (see "3.3.3 Inland Inundation Simulation by Simple Rainfall Evaporation Model"). In this case, the beneficiary area would be smaller than the expected one, since any agricultural activities cannot be done in the inundation area. Therefore, the




Figure 3.6.1 Image of Inland Flood Caused by Rainfall

Source: JICA Survey Team

drainage structures are necessary to reduce such inundation area, and to realize the purpose of the dike construction.

According to the preliminary examination by the simple rainfall-evaporation model, installation of pumps for drainage was considered to be unfeasible. Then, sluices which are generally used as drainage structures are selected as the target drainage structures in the simulation. Sluices can drain the inland flood when the river water level at the outlet of the sluice becomes lower than that in LMSA. Therefore, simulation able to know both water levels on the river and LMSA should be conducted as follows:

3.6.1 Specific Conditions for Inland Inundation Simulation with/without Drainage Structures

1) Simulation Period

In the simulation, the inundation area in the LMSA spreads by rainfall, and is reduced by evaporation and drainage by the structures. In order to identify the trend of those phenomena and to assess the maximum inundation area, a long term simulation is required. Additionally, in order to make the impact of the sluice clear, 1-year calculation is repeated twice continuously.

2) Rainfall

Since the simulation period is one year as mentioned above, 1-year time series rainfall data should be required. In this simulation, the following two types of the rainfall data are prepared.

- a) Rainfall for the calculation of discharge at the input points
 - ✓ Daily basin mean rainfall is selected.
 - ✓ To consider the high accuracy as much as possible, rainfall data in 1973 are selected as a base rainfall pattern. This is because that the year has the largest number of rainfall gauge stations' data, and the data in this year has clear difference in rainfall pattern between dry and rainy season.
 - ✓ Probability analysis for the annual basin mean rainfall of the MRB (from 52 years available data) is carried out for n-year return period (R_n). 2, 10, 20, 30, 50, 100-year return periods are examined in the simulation (see Table 3.6.1).
 - ✓ One-year time series rainfall for n-year return period is created based on the base rainfall pattern in 1973 by multiplying the ratio between R_n and R₁₉₇₃ (see Figure 3.6.2).

Table 3.6.1 Annual Basin Mean Rainfall Amount in the MRB²

Return Period	Exp	Gumbel	Gev
2	1737.2	1819.8	1905.4
10	2595.2	2544.2	2513.9
20	2964.7	2821	2667.9
30	3180.9	2980.3	2742.2
50	3453.2	3179.3	2822.7
100	3822.7	3447.8	2912.8
SLSC	0.111	0.083	0.059 (Applied)

Source: JICA Survey Team

² The 52-year record was applied to each probability distribution model, namely, Exponential distribution (Exp), Gumbel distribution, Generalized extreme value distribution (Gev), and Generalized extreme value distribution was selected as the most appropriate model based on the Standard Least Squares Criterion (SLSC).




Figure 3.6.2 Example of the Method to Create Time Series Mean Rainfall in the MRB (30-year return period)

Source: JICA Survey Team

b) Rainfall in the LMSA

- ✓ Rainfall data at Datu Piang rainfall gauge station which is located at the nearest to the LMSA among the target stations is selected.
- ✓ Rainfall data in 1973 are selected as a base rainfall pattern due to the same reason as a).
- ✓ Probability analysis for annual rainfall amount at Datu Piang rainfall gauge station is carried out for n-year return period (RDn) in the same manner of a) (see Table 3.6.2)..
- ✓ Time series rainfall for n-year return period is created based on the base rainfall pattern in 1973 by multiplying the ratio between RDn and RD1973 (see Figure 3.6.3).

Table 3.6.2 Annual Rainfall Amount at Datu Piang Rainfall Gauge Station

Return Period	Gumbel	Iwai	Ishitaka	Gev	SqrtEt
2	1399.3	1423.7	1427.9	1414.7	1389.7
10	1933	1909.5	1902.5	1931.3	1952.2
20	2136.9	2074.9	2059.2	2110.3	2190.3
30	2254.2	2166.6	2145.1	2208.9	2333.1
50	2400.9	2278.3	2248.9	2328	2517.4
100	2598.7	2424.7	2383.7	2481.5	2776.4
SLSC	0.037	0.031 (applied)	0.033	0.035	0.04

Source: JICA Survey Team




Figure 3.6.3 Example of the Method to Create Time Series Rainfall at Datu Piang (30-year return period)

Source: JICA Survey Team

c) Discharge

Since sluices can drain inland flood water when river water level at the outlet of the sluice becomes lower than inland flood water level in the LMSA, both the river and the inland flood water level shall be prepared as input data for the simulation.

The aforementioned unit hydrograph method (see Figure 3.4.14) illustrates the concept of the conversion from rainfall during a unit time (one hour in that case) to the time series discharge. This concept is also applied in this simulation, and one-year time series discharge data is created as the following procedures.

- ✓ The base flow is regarded as the constant value (see "3.4.3 Model Design" for the concept of the base flow").
- ✓ As for the hourly rainfall pattern in a day, it is assumed that the rainfall continues in the same intensity through a whole day because the only daily rainfall data is available.
- ✓ Time series discharge at the input points is calculated on the hourly basis, and the organized on the daily basis to apply the simulation model.
- ✓ This estimation is made for every rainy day, and daily discharge is calculated by superposition of the calculated discharges from each rainfall.

Figure 3.6.4 illustrates the schematic image of the determination method to create the discharge volume from the hourly rainfall data.




Figure 3.6.4 Schematic Image of the Time Series Discharge Data

Source: JICA Survey Team

d) Sluice

As for the scale, a sluice of 2m height and 2m width is applied assuming that the height of the dike is 4m, and sluice is set at the bottom of the dike. Moreover, the bottom elevation of the sluice is set as the same elevation of the lowest elevation in the LMSA, namely, EL. 4.5m, so that the sluice can discharge whole inland flood in the beneficially area of the LMSA.

According to the results of the Flood Simulation with/without dike, the water level in the Liguasan marsh becomes higher, and river water level at Paidu Pulangi becomes lower after the construction of the dike. Therefore, the location of the sluice is selected at Paidu Pulangi to make the discharge

opportunity most effective due to the difference in the water level between the Pulangi river and the inland water in the LMSA. In this case, drainage canals are additionally required from the pond of the inland water to the sluices because the area where the elevation is lower than EL. 4.5m is mainly situated on the southern part of the LMSA (see Figure 3.6.5).




Figure 3.6.5 Location of Drainage Point and Drainage Canal
Source: JICA Survey Team

e) Simulation Cases

Simulation is executed only in the case of after the construction of the dike, and for 2, 10, 20, 30, 50, 100-year return periods rainfall with 0, 2, 10, 30, 50, 100 sluices are considered. In total, 36 cases are examined (see Table 3.6.3).

Table 3.6.3 Simulation Cases for Inland Inundation Simulation

Simulation Case	Probability	Return Period						Number of Sluices						Total Case	
		2	10	20	30	50	100	0	2	10	30	50	100		
1. Present Condition (without dike)		-	-	-	-	-	-	-	-	-	-	-	-	-	0
2. After Construction of the Dike (With Dike)		○	○	○	○	○	○	○	○	○	○	○	○	○	36

3.6.2 Simulation Result

Table 3.6.4 to 3.6.9 and Figure 3.6.6 to 3.6.11 show the results of the simulation. Although 1-year calculation is repeated twice continuously, 1.5-year result is shown in the Figures. From these results, followings can be concluded.

- ✓ The number of the sluice is important to shorten the duration of the inundation time when the situation fulfills the drainage requirement. The more the sluices are installed, the shorter duration of the inundation time becomes.
- ✓ The difference of the maximum inland flood water level in the LMSA between 2 and 100 sluices under 2-year return period rainfall is only 12cm (= 5.81m - 5.69m), which indicates the impact of the number of sluices is not significant on the water level. Moreover, the result is almost the same in the other return period cases.
- ✓ Difference in the maximum inundation area between 2 and 100 sluices under 2-year return period rainfall is also small (42.3 km² for 100 sluices and 45.3 km² for 2 sluices so that the difference in ratio is 42.3/45.3 = 93%) and almost the same ratios are found in the other cases as well.
- ✓ The results indicate that the number of the sluices is not important to mitigate both the maximum inland flood water level and the maximum inundation area. It is because the sluices cannot function from May to October, since the river water level is higher than the inland water level. During this season, all the rainfall in the LMSA is stagnated and the maximum inland water level and the maximum inundation area are identified.

Table 3.6.4 Summary of the Results (Return Period: 2 year)

Number of the Sluice	Maximum Inland Flood Water Level in the LMSA (EL.m)	Maximum Inundation Area in the LMS (km ²)	Inundated Ratio (%)	
			Whole the LMSA	ODA Target Area
0	5.86	46.3	52.9	50.3
2	5.81	45.3	51.9	49.2
10	5.78	45.3	51.9	49.2
30	5.73	45.3	51.9	49.2
50	5.71	42.3	48.1	45.9
100	5.69	42.3	48.1	45.9

Table 3.6.5 Summary of the Results (Return Period: 10 year)

Number of the Sluice	Maximum Inland Flood Water Level in the LMSA (EL.m)	Maximum Inundation Area in the LMS (km ²)	Inundated Ratio (%)	
			Whole the LMSA	ODA Target Area
0	6.77	68.3	72.1	74.2
2	6.35	6.00	69.2	64.9
10	6.30	5.78	67.3	62.8
30	6.22	5.78	67.3	62.8
50	6.19	5.48	63.5	59.5
100	6.17	5.48	63.5	59.5

Table 3.6.6 Summary of the Results (Return Period: 20 year)

Number of the Sluice	Maximum Inland Flood Water Level in the LMSA (EL.m)	Maximum Inundation Area in the LMS (km ²)	Inundated Ratio (%)	
			Whole the LMSA	ODA Target Area
0	6.91	7.05	75.0	76.6
2	6.81	6.83	72.1	74.2
10	6.64	6.43	69.2	69.8
30	6.38	6.03	70.2	65.5
50	6.35	6.00	69.2	65.2
100	6.33	6.00	69.2	65.2

Table 3.6.7 Summary of the Results (Return Period: 30 year)

Number of the Sluice	Maximum Inland Flood Water Level in the LMSA (EL.m)	Maximum Inundation Area in the LMS (km ²)	Inundated Ratio (%)	
			Whole the LMSA	ODA Target Area
0	6.94	74.0	81.7	80.4
2	6.87	70.5	75.0	76.6
10	6.72	66.8	74.0	72.6
30	6.64	66.0	71.2	71.7
50	6.55	64.3	69.2	69.8
100	6.43	62.8	71.2	68.2

Table 3.6.8 Summary of the Results (Return Period: 50 year)

Number of the Sluice	Maximum Inland Flood Water Level in the LMSA (EL.m)	Maximum Inundation Area in the LMS (km ²)	Inundated Ratio (%)	
			Whole the LMSA	ODA Target Area
0	6.97	7.40	81.7	80.4
2	6.93	7.25	78.8	78.8
10	6.81	6.90	75.0	75.0
30	6.74	6.90	75.0	75.0
50	6.72	6.90	75.0	75.0
100	6.72	6.68	74.0	72.6

Table 3.6.9 Summary of the Results (Return Period: 100 year)

Number of the Sluice	Maximum Inland Flood Water Level in the LMSA (EL.m)	Maximum Inundation Area in the LMS (km ²)	Inundated Ratio (%)	
			Whole the LMSA	ODA Target Area
0	7.06	7.53	84.6	81.8
2	6.97	7.33	81.7	79.9
10	6.85	7.28	79.8	79.1
30	6.84	7.13	77.0	77.4
50	6.83	7.13	77.9	77.4
100	6.83	7.13	77.9	77.4

Source: JICA Survey Team (for Table 3.6.4 to Table 3.6.9)




Figure 3.6.6 Water Level and Inundation Situation (Return Period: 2 year)

Source: JICA Survey Team




Figure 3.6.7 Water Level and Inundation Situation (Return Period: 10 year)

Source: JICA Survey Team




Figure 3.6.8 Water Level and Inundation Situation (Return Period: 20 year)

Source: JICA Survey Team




Figure 3.6.9 Water Level and Inundation Situation (Return Period: 30 year)

Source: JICA Survey Team




Figure 3.6.10 Water Level and Inundation Situation (Return Period: 50 year)

Source: JICA Survey Team




Figure 3.6.11 Water Level and Inundation Situation (Return Period: 100 year)

Source: JICA Survey Team

3.6.3 Required Number of the Sluices

Even in a case for 2-year return period (average-year) rainfall, 30 sluices are required to start the agricultural activities according to the planned cropping pattern (see Figure 3.6.12). The inland flood water level shall be lower than EL. 4.5m before the beginning of November which is the timing of land preparation for dry-season rice cropping. If more than 30 sluices are constructed, this condition is achieved. The construction cost for 30 sluices is almost 2412.3 million PHP (5,451.6 million JPY) as shown in the Table 3.6.10.

However, the inland flood water level would become 50cm higher than EL. 4.5m at the middle of November (see Table 3.6.4 and Figure 3.6.6). Therefore, it is required to postpone the timing of the land preparation for one month, namely, to the beginning of December.

For the rainy-season cropping from May to October, almost half of the LMSA is under inappropriate condition for cropping due to the inundation (see Table 3.6.4). This situation cannot be solved even though more sluices are installed. To cope with the situation, pumping stations should be constructed, however it is not financially feasible, or otherwise there should be another measure, e.g. dredging.

Crop (Agri-ecosystem)	Month												Remarks	
	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr		
<Irrigated Land>														
Paddy														2-paddy cropping will be introduced with the irrigation system completed.
Vegetables and pulses (eggplant, stringbeans, bitter gourd, bottle gourd)														No definite season. Vegetables are planted along the paddy bunds.

Figure 3.6.12 Planned Cropping Pattern in LMSA (paddy)

Source: JICA Survey Team

Table 3.6.10 Construction Cost (Direct Cost) of the 30 Sluices

Work Items		(1) Quantity	(2) Unit Cost (PHP)*	(3) Total (= (1) x (2))		Remarks
				(million PHP)	(million JPY)	
Dike	Back Filling of the Dike	988,000 m ³	804	794.4	1,795.3	Same amount as Table 3.5.6
	Founding Treatment (Sand Compaction Pile Works)	84.797 piles	17,700	1,500.1	3,390.2	Same amount as Table 3.5.6
Sluice	Concrete	4,641 m ³	6,901	32.0	72.3	154.7m ³ x 30 Sluices
	Steel Bar	464,100 kg	57	26.5	59.9	100kg/concrete 1m ³
	Gate (H2.0m x B2.0m)	30 num	127,586	3.8	8.6	
Drainage Canal	Excavation	781,200 m ³	71	55.5	125.3	
Sum				2,412.3	5,451.6	

Source: JICA Survey Team

*provided by NIA

3.7 Flood Simulation with/without Dredging

As already mentioned, the dyke would act as a physical border dividing the vicinity area socially and environmentally. Magindanaon ethnic group, a part of Moro group, resides in this region. The dike therefore would make physical and social separation for the dwellers as a boarder. On one hand, dredging work on the Pulangi river can be an effective measure to mitigate or eliminate flood damage without dyke. Therefore, the necessary dredging volume is examined through the flood simulation.

3.7.1 Specific Conditions for Flood Simulation with/without Dredging

1) Basic Concept of the Simulation

The maximum flood water level of the Pulangi river shall be kept lower than EL. 4.5m which is the

lowest elevation in the LMSA, to mitigate or eliminate flood damage to the LMSA. Therefore, the target river water level is determined as EL. 4.5m at the Paidu Pulangi in the simulation.

2) Target Sections of Dredging

Target sections of the dredging are from the junction of the Pulangi river and the Tunggol floodway to the junction among the Tamontaka, the Rio Grande de Mindanao, and Pulangi river (see Figure 3.7.1).

3) Target Cross Sections

Dredging shape is examined at the 10 points (see Figure 3.7.1). Among these 10 points, current cross sections at 2 points of the river mouths are kept, while remaining 8 points are reshaped by the dredging. The cross sections between the target points are given by interpolation.




Figure 3.7.1 Dredging Sections and the Target Cross Sections

Source: JICA Survey Team

4) Basic concept of the Dredging

The original cross sections are confirmed based on the result of the bathymetric survey conducted from November 2017 to January 2018. Then, for the effective discharge, the original cross sections are reshaped, changing the shape of cross section by dredging. The methodology of the simulation is the same as the Flood Simulation under the present condition (without dike) except for the shape of the cross sections. Basically, design shape of cross sections after dredging is complied with the following two principles (see Figure 3.7.2).

- a) The shape of the cross sections is expanded horizontally

After the bathymetric survey along the Pulangi river, it was found that some of the river bottom along the LMSA is already under sea level. Therefore vertical dredging is considered to have a limited contribution to the drawdown of the river water level due to the back water from the sea.

- b) The river is expanded to the left side

River expansion toward the right bank will affect the beneficially area of LMSA. To avoid any interference on LMSA, the LMSA shall not be shaved off by the dredging.




Figure 3.7.2 Example of the Cross Section before and after Dredging

Source: JICA Survey Team

5) Simulation Cases

2-year return period rainfall is the target rainfall and 5 cases, 0(original), 50, 100, 300, 500m dredge expansion are carried out under this rainfall.

Table 3.7.1 Simulation Cases of Flood Simulation with/without Dredging

Simulation Case	Probability	Return Period					Scale of Dredging					Total Case	
		2	10	20	30	50	100	0	50	100	300		500
1. Present Condition (without dike)		○	-	-	-	-	-	○	○	○	○	○	5
2. After Construction of the Dike (With Dike)		-	-	-	-	-	-	-	-	-	-	-	0

Source: JICA Survey Team

3.7.2 Simulation Result

Figure 3.7.3 illustrates the longitudinal profile of the maximum flood water level by each simulation case. The water level tends to be lower as expansion width becomes wider. The result indicates that more than 500m expansion by dredging is required to mitigate the flood damage, which is more than twice width (3 to 5 times for some river sections) of the current river width.




Figure 3.7.3 Longitudinal Profile of the Maximum Flood Water Level

Source: JICA Survey Team

Table 3.7.2 Dredging Amount and Maximum Water Level on the Pulangi River after Dredging

Expansion Width	Dredging Amount	Maximum Water Level on the Plangi river (EL.m)			
		Pagalungan	Barongis	Kabasalan	Paidu Pulangi
Original	-	11.12	7.38	7.29	6.93
50m	44 m ³ ×10 ⁶	11.10	7.24	6.95	6.17
100m	77 m ³ ×10 ⁶	11.07	7.14	6.75	5.81
300m	209 m ³ ×10 ⁶	10.68	6.76	6.24	5.10
500m	345 m ³ ×10 ⁶	9.70	5.83	5.42	4.71

Source: JICA Survey Team




The difference of water level between the original case and other cases up to 300m expansion seems not to be significant on the section of the upstream (see Figure 3.7.3). This is caused by the following reasons;

- ✓ Under the present condition, the Tunggol Floodway is functioning when a flood event occurs,

which limits the discharge volume to the Pulangi river to some extent.

- ✓ By the dredging, the flow capacity of the Pulangi river is improved. However, because the total flood volume does not change, Pulangi river attracts more water which was discharged to the Tunggol Floodway (therefore, the discharge volume on the Tunggol Floodway becomes drastically small as the expansion width get wider as shown in Figure 3.7.4).
- ✓ The flood water remains flowing into the Pulangi river, exceeding its capacity until the cases up to 300m dredging expansion. As a result, water level on the Pulangi river does not change much even though the flow capacity of the Pulangi river is improved.



* The scale of the arrows is an image of the discharge volume.

Figure 3.7.4 Change of the Discharge Volume by Dredging

Source: JICA Survey Team

As discussed before, more than 500m river expansion is required to mitigate the flood damage to the LMSA. To achieve this case practically, 345 MCM of the dredging is required and its construction cost is estimated as 22,080 million PHP (49,901 million JPY). It is the cost for the dredging to mitigate the flood damage caused by only 2-year return period rainfall.

Table 3.7.3 Construction Cost (Direct Cost) of the Dredging

Work Item	(1) Quantity	(2) Unit Cost (PhP)	(3) Total (=(1) x (2))		Remark
			(million PhP)	(million JPY)	
Dredging	345 million m ³	64	22,080	49,901	DPWH's unit cost

Source: JICA Survey Team

The cost mentioned above is dredging cost only. In addition to that, the costs for dehydration, transportation of the dredged soil, land acquisition of disposal pit must be considered. Moreover, it is worthy to say that the cost is estimated based on the case of 2-year return period rainfall, which also means the dredging becomes far more costly.

Furthermore, the purpose of the simulation is designed to consider the LMSA only; therefore the target section for the dredging is until the diversion point of the Tamontaka and the Rio Grande de Mindanao rivers. This means more flood water flows to the downstream of the end of the dredging section after the dredging. If the residential areas and properties along those rivers, such as Cotabato city, should be protected as well, the target dredging section must extend until the river mouths. In that case, additional 70-80km dredging is required, which makes the dredging volume and cost more enormous.

Finally, adverse effect on the Liguasan marsh should also be considered. Because the flood discharge to the Liguasan marsh becomes much smaller (1,354m³/s under the present condition without dredging and 148m³/s in case of 500m expansion), the wet area of the Liguasan marsh definitely shrinks.

3.8 Flood Simulation with/without Partial Dredging

According to the results of “3.5 Flood Simulation with/without Dike”, low flow capacity at the bottle neck point is considered as one of the main factors, which causes the flood damage to LMSA (see Figure 3.5.6). Therefore, the dredging around the bottle neck point only may be considered as another measure to mitigate flood damage to the LMSA, and flood simulation to examine the effect of this partial dredging is conducted as follows:

3.8.1 Specific Conditions for Flood Simulation with/without Partial Dredging

1) Target Sections of Dredging

Target sections of the dredging are from the PLG-12 which is about 3 km upstream from Paidu Pulangi to RIO-52 that is about 10 km downstream from the Paidu Pulangi and target river length of the dredging comes to about 13 km (see Figure 3.8.1).

2) Simulation Cases

The target return period for flood volume should be estimated based on the river catchment area with three patterns of return period rainfall; namely, 2-year (average year), 30-year (target period for economic evaluation) and 100-year (target return period prescribed in DPWH’s standard) are selected. Further, the flood simulation of such three cases of dredging width as 100m, 200m, 500m are carried out under each of the target return period flood:




Figure 3.8.1 Target Sections for Dredging
Source: JICA Survey Team

Table 3.8.1 Simulation Cases of Flood Simulation with/without Partial Dredging

Simulation Case	Probability	Return Period of Flood			Total Case
		2-year	30-year	100-year	
100m Dredging Expansion		○	○	○	9 Cases
200m Dredging Expansion		○	○	○	
500m Dredging Expansion		○	○	○	

Source: JICA Survey Team

3) Formation of Cross Sections

The cross section formations with each dredging expansion are diverted from those utilized in “3.7 Flood Simulation with/without Dredging”.

3.8.2 Simulation Result


Figure 3.8.2 illustrates the longitudinal profile of the maximum flood water level of the Pulangi river and Table 3.8.2 shows the maximum flood water level at Paidu Pulangi. The maximum flood water level at Paidu Pulangi in case of the partial dredging is lower than the original one (equal to the without dredging) in all return period floods. However, since the maximum flood level is higher than EL.4.5m, which is the lowest elevation of the LMSA’s beneficial area, flood damage in LMSA cannot be mitigated completely. On the other hand, maximum flood water level at the downstream areas of

dredging section is higher than the original one.


Table 3.8.2 Simulation Results (Maximum Water Level at Paidu Pulangi), Unit: EL. m

Return Period (year)	(1) Original (=without dredging)	(2) After Dredging					
		100m Expansion		200m Expansion		500m Expansion	
		Water Level	Difference from (1)	Water Level	Difference from (1)	Water Level	Difference from (1)
2	6.90	6.64	-0.26	6.49	-0.41	6.23	-0.67
30	7.78	7.44	-0.34	7.21	-0.57	6.83	-0.95
100	8.26	7.93	-0.34	7.69	-0.57	7.27	-1.00


Source: JICA Survey Team



Return Period: 2-year



Return Period: 30-year



Return Period: 100-year

Figure 3.8.2 Longitudinal Profile of the Maximum Flood Water Level of the Pulangi River

Source: JICA Survey Team

Figure 3.8.3 illustrates the maximum inundation area and Table 3.8.3 shows the average water depth in the LMSA. According to the figure and table, maximum average water depth in LMSA becomes to 12 - 50cm lower than the original one (equivalent to without dredging). On the other hand, inundation area and flood water depth at the downstream area of dredging section are bigger than the original ones.

Table 3.8.3 Simulation Results (Average Water Depth in LMSA), Unit: m

Return Period (year)	(1) Original (=without dredging)	(2) After Dredging					
		100m Expansion		200m Expansion		500m Expansion	
		Water Depth	Difference from (1)	Water Depth	Difference from (1)	Water Depth	Difference from (1)
2	1.59	1.47	-0.12	1.42	-0.17	1.40	-0.19
30	2.30	2.08	-0.22	2.00	-0.30	1.91	-0.39
100	2.72	2.47	-0.25	2.36	-0.36	2.22	-0.50

Source: JICA Survey Team




Figure 3.8.3 Simulation Results (Maximum Inundation Area)

Source: JICA Survey Team

3.8.3 Preliminary Economic Evaluation

1) Planted Area increased by Partial Dredging

Based on the i) maximum flood water level at Paidu Pulangi (see Table 3.8.2), ii) decreased average water depth in LMSA by the partial dredging (see Table 3.8.3), and 3) H (elevation) and A (area) relation curve in LMSA utilized in “3.3.3 Inland Inundation Simulation by Simple Rainfall-Evaporation Model” (see Figure 3.8.4), planted area increased by partial dredging is estimated as shown in Table 3.8.4:




Figure 3.8.4 H-A Relation Curve in LMSA

Source: JICA Survey Team

Table 3.8.4 Planted Area to be Increased by Partial Dredging

Return Period (year)	Expansion Range (m)	(1) Maximum Flood Water Level at Paidu Pulangi (EL.m) (from Table 3.8.2)	(2) Decreased Maximum Average Water Depth in LMSA by dredging (m) (from Table 3.8.3)	(3) Maximum Average Water Depth in LMSA after Dredging (= (1) + (2)) (EL.m)	(4) Planted Area in LMSA with elevation (1) (km ²) (from Figure 3.8.4)	(5) Planted Area in LMSA with elevation (2) (km ²) (from Figure 3.8.4)	(6) Difference of Area from the original one (= increased area) (= (4) – (5)) (km ²)	(7) Area Increasing Ratio (= (6) / (5) x 100) (%)
2	Original	6.90	-	-	84.6	-	-	-
	100	-	-0.12	6.78	-	81.3	3.3	4.1
	200	-	-0.22	6.68	-	78.6	6.0	7.6
	500	-	-0.25	6.65	-	77.7	6.9	8.9
30	Original	7.78	-	-	100.9	-	-	-
	100	-	-0.17	7.61	-	98.7	2.2	2.2
	200	-	-0.30	7.48	-	96.9	4.0	4.1
	500	-	-0.36	7.42	-	95.7	5.2	5.4
100	Original	8.26	-	-	105.9	-	-	-
	100	-	-0.19	8.07	-	104.4	1.5	1.4
	200	-	-0.39	7.78	-	100.9	5.0	5.0
	500	-	-0.50	7.76	-	100.7	5.2	5.2

Source: JICA Survey Team

Expected planted area to be increased by partial dredging can be illustrated in Table 3.8.5 with designed planted area by case which is proposed in consideration with inundated area (see 4.3.2 Development Direction for Lower Malitubog Service Area in MMIP II). Note that in this survey the JICA Team proposes 2 cases for canal network development; namely, 1) Case-1 where the canals within LMSA are to be constructed only within limited area, almost free from flood as well as the inundation not more than 50cm depth, and 2) Case-2 where the irrigation canals are to be constructed as per the original design.

Table 3.8.5 Expected Planted Area Increased by Partial Dredging

Case	Return Period (year)	Expansion Range (m)	(1) Planned Planted Area in LMSA (Wet Season) (ha)	(2) Area Increasing Ratio (%) (from Table 3.8.5)	(3) Planted Area Increased by Partial Dredging (= (1) x (2)), (ha)
With Project Case-1	2	100	2,810	4.1	115
		200		7.6	214
		500		8.9	250
	30	100		2.2	62
		200		4.1	115
		500		5.4	152
	100	100		1.4	39
		200		5.0	141
		500		5.2	146
With Project Case-2	2	100	3,810	4.1	156
		200		7.6	290
		500		8.9	339
	30	100		2.2	84
		200		4.1	156
		500		5.4	206

Case	Return Period (year)	Expansion Range (m)	(1) Planned Planted Area in LMSA (Wet Season) (ha)	(2) Area Increasing Ratio (%) (from Table 3.8.5)	(3) Planted Area Increased by Partial Dredging (= (1) x (2)), (ha)
	100	100		1.4	53
		200		5.0	191
		500		5.2	198

Note: the planned planted area would vary, in essence, according to the return period of flood. However, in this simple estimation of the increased planted area by partial dredging, same planted area is applied in view of simplicity of the estimation.

Source: JICA Survey Team

2) Construction Cost of Partial Dredging

Required dredging volume, its construction cost (direct cost) and unit construction cost per ha to be increased by partial dredging are summarized in Table 3.8.6. At least 4.88 million PhP/ha should be necessary and this value is much higher than 0.52 million PhP/ha which was original development cost of MMIP II estimated based on the approved project cost. Additionally, cost in Table 3.8.6 is dredging cost only, and the cost for other work items such as dehydration, transportation of the dredged soils, land acquisition of disposal areas are not considered. In this case, construction cost becomes much higher than the value in the Table 3.8.6. Therefore the partial dredging works to mitigate flood damage to LMSA is judged not to be economically feasible.

Table 3.8.6 Construction Cost (Direct Cost) of the Dredging

With/Without Project	Return Period (year)	Expansion Range (m)	(1) Required Dredging Volume (million m ³)	(2) Unit Cost (PhP)	(3) Construction Cost of Dredging (million PhP)	(4) Planted Area Increased by Partial Dredging (ha) (from Table 3.8.5)	(5) Construction Cost per ha (= (3) / (4)) (million PhP / ha)
With Project Case-1	2	100	11.9	64	762	115	6.63
		200	23.9		1,530	214	7.15
		500	59.7		3,821	250	15.28
	30	100	11.9		762	62	12.29
		200	23.9		1,530	115	13.30
		500	59.7		3,821	152	25.14
	100	100	11.9		762	39	19.54
		200	23.9		1,530	141	10.85
		500	59.7		3,821	146	26.17
With Project Case-2	2	100	11.9		762	156	4.88
		200	23.9		1,530	290	5.28
		500	59.7		3,821	339	11.27
	30	100	11.9		762	84	9.07
		200	23.9		1,530	156	9.81
		500	59.7		3,821	206	18.55
	100	100	11.9		762	53	14.38
		200	23.9		1,530	191	8.01
		500	59.7		3,821	198	19.30
Unit construction cost per 1 ha according to the NEDA Approved Budget							0.52

Note: the planned planted area would vary, in essence, according to the return period of flood. However, in this simple estimation of the increased planted area by partial dredging, same planted area is applied in view of simplicity of the estimation.

Source: JICA Survey Team

3.9 Flood Simulation with the Ambal-Simuay River and Rio Grande de Mindanao Flood Control Projects

DPWH has a project plan namely the “Ambal-Simuay River and Rio Grande de Mindanao Flood Control Projects”. This project aims to protect Cotabato city from flood with the following two measures:

- 1) Cutoff channel: This channel works to divert a part of flood water of the Ambal-Simuay River to the sea, whereby reducing flood water flowing over to the Cotabato city.

- 2) Diversion access road: This diversion access road works to store flood water from the Rio Grande de Mindanao River to in order to reduce flood water flowing into the Cotabato city.




Figure 3.9.1 General Plan of the Ambal-Simuguay River and Rio Grande de Mindanao Flood Control Projects
 Source: DPWH presentation material

According to the results of flood simulation by DPWH, almost all the flood damage on the Cotabato city could be eliminated after implementation of this DPWH’s project, composed of 1) cutoff channel which functions as flood diversion water-course, and 2) the embankment of diversion access road.

While it can be said that DPWH’s project would act in the direction of reducing the flood water level in the Ria Grande de Mindanao near Cotabato city, it could raise the water level of Pulangi river due to the embankment of diversion access road to be constructed at the upstream of Cotabato city. Flood water level of the Rio Grande de Mindanao River at the downstream side of the diversion road will be lowered than the present ones. On the other hand, flood water level at the upstream side of the diversion road would be higher by 1.0m than that of the present condition according to the simulation by DPWH. Due to this situation, flood water level of the Pulangi River would be higher than that of current ones.




Figure 3.9.2 Results of Flood Simulation under Present Condition and after Implementation of the DPWH’s Project
 Source: DPWH presentation material

Therefore, in order to assess the impact by the DPWH project on the water level of the Pulangi river, flood simulation after the implementation of this project is carried out in the following sections:

3.9.1 Specific Conditions for Flood Simulation with the Ambal-Simuay River and Rio Grande de Mindanao Flood Control Projects

1) Boundary Condition

As already discussed, flood water level at the upstream side of the diversion road would become 1.0m higher than the present condition’s one. As it is difficult to reproduce the DPHW’s simulation results, simulation model having adjusted boundary condition, which makes flood level at the diversion road point 1.0m higher than the present one, is to be employed.

2) Flood Protection Dike for LMSA

To compare the flood condition under present condition and after implementation of DPHW’s project, a model without flood protection dike for LMSA is utilized.

3) Target Flood

100-year return period flood is selected as it is prescribed in the DPWH’s standard as the target flood for design.

3.9.2 Simulation Result

Figure 3.9.3 illustrates the longitudinal profile of the maximum flood water level of the Pulangi river. Even water level at the diversion road point is 1.0m higher than that of the current condition, the maximum flood water level at Paidu Pulangi would be only 4.6cm (=8.310m – 8.264m) higher. Also Table 3.8.2 shows the average flood water depth in LMSA and in this case it is only 4.0cm higher than the current flood water level. Based on these results, the” Ambal-Simuay River and Rio Grande de Mindanao Flood Control Project” would work in the direction of raising up flood water level in and around LMSA, however its impact is very limited, only 4cm higher, whereby actual impact would not be recognized.




Figure 3.9.3 Longitudinal Profile of the Maximum Flood Water Level of the Pulangi River

Source: JICA Survey Team

Table 3.9.1 Simulation Results (Average Water Depth in LMSA)

Location	Average Water Depth (m)		Difference (= (2) - (1)) (m)
	(1) Under Present Condition	(2) After the DPWH's Projects	
LMSA	2.65	2.69	0.04
Liguasan Marsh	1.05	1.11	0.06

Source: JICA Survey Team

3.10 Conclusion of the Simulations

As conclusion, the results of the four simulations are summarized as below:

1) Impact on the Liguasan Marsh by the Dike Construction

- ✓ The dike would expand the inundation area by 19% to 34% and make the flood water level higher by 65cm to 81cm in the Liguasan Marsh.
- ✓ The required height of the dike shall be 50cm higher than the original NIA design. In this case, construction cost (direct cost) comes to 2,294.5 million PHP (5,185.5 million JPY).
- ✓ Dike might act as the physical border dividing the vicinity area socially and environmentally.
- ✓ There are residents living along the right side of the Pulangi river and therefore resettlement of these residents will be required to construct the dike.

2) Impact on the LMSA by the Dike Construction

- ✓ The dike would have a significant impact on the beneficially area in LMSA, but dike will cause inland flood originating from rainfall within the LMSA.
- ✓ Even to eliminate the inland flood in the rainy season in case of 2-year return period, 30 sluices should be installed as drainage structures. In this case, construction cost (direct cost) including dike construction is estimated at 2,412.3 million PHP (5,451.6 million JPY).
- ✓ Even if 30 sluices were installed, almost a half of the LMSA could be still inundated during the rainy-season cropping season due to inland flood. This is because that the water level on the Pulangi river remains higher than the inland water level in the LMSA throughout the rainy season. It is, therefore, difficult to drain the inland flood water to the Pulangi river. Further to mitigate the inland flood, a pumping station should be considered, which is not feasible economically as the drainage facilities.
- ✓ Such inundation originating in the rainfall would affect the commencement of the dry season cultivation as well. Even if 30 sluices were installed to mitigate the rainy season inland flooding, commencement of the land preparation for the dry-season cropping should be postponed by one month than the standard cropping timing, waiting for some time till when the land can be ready for the dry season cropping.

3) Impact on the LMSA and Liguasan Marsh by the Dredging

- ✓ Even to mitigate the damage to the LMSA by flood in case of the 2-year return period rainfall, 345 million cum dredging (expansion width becomes 500m) is required for whole stretch of the Pulangi river. In this case, construction cost (direct cost) is estimated as 22,080 million PHP (49,901 million JPY). Since it is only for the dredging, the total cost including other work items such as dehydration, transportation of the dredged soil, land acquisition for disposal areas will be further increased.
- ✓ If the target return period is more than 2-year and/or when it is needed to think compensation for loss of the properties along the Tamontaka and the Rio Grande de Mindanao rivers to be included

as the protection target, dredging volume and construction cost become enormous. In addition, land acquisition and resettlement are required for dredging and for treating dredged mud, causing further increase in the cost.

- ✓ Adverse effects on the Liguasan marsh cannot be negligible because the flow depth becomes much smaller. This may cause dry out of the marsh to some extent, change of the ecosystem of the Pulangi river as well as Liguasan march, possibly affecting the fishing industry.
- 4) Impact on the LMSA by the Partial Dredging around the Bottle Neck Point**
- ✓ The effect of the partial dredging to mitigate flood damage to LMSA is very limited.
 - ✓ Partial dredging causes more serious flood damage at the downstream area of the dredging section/reach than the original one.
 - ✓ As unit construction cost for the dredging (4.88 million PhP/ha) is much higher than 0.52 million PhP/ha, which is the unit investment cost per beneficial area estimated based on the MMIP II NEDA approved project cost. Dredging works applied partially for the bottleneck point to mitigate the flood damage to LMSA cannot still be economically feasible.
- 5) Impact on the LMSA by the DPWH's Project namely Ambal-Simuay River and Rio Grande de Mindanao Flood Control Projects**
- ✓ Cutoff channel would act to lower the flood water level of the Rio Grande de Mindanao River; however at the same time the embankment of diversion access road would act to raise up the water level of Pulangi river.
 - ✓ Totally, average flood water level in LMSA would go up by this DPWH's project; however its impact is very limited as average flood water level within the LMSA would go only 4cm.

CHAPTER 4 PROJECT PLANNING AND DESIGNING

This chapter addresses the detailed plan of the project components namely: 1) the agricultural development and extension service delivery, 2) the irrigation and drainage system development together with countermeasures against flood damages, and 3) the infrastructure improvement on water distribution, as well as the outline designs of major facilities for the implementation of these components. As the flood simulation have reached a conclusion that the dike construction is not technically and financially feasible, only the countermeasures against damages to be caused in LMSA by flood are to be discussed in this chapter:

4.1 Direction Setting and Major Project Components

4.1.1 Lessons Learnt and Impacts from MMIP I

Lessons learnt from MMIP I and impacts produced by the same Project can be summarized as follows. They are drawn from results of: Special Assistance for Project Formation (SAPROF) Study (May 2010), interviews to relevant organizations including NIA-PMO and ATI Kabacan, and will be fed-forwarded in the planning and designing of the remaining part of MMIP II. In addition, issues arisen from the on-going MMIP II should be also addressed in this section.

Lessons learnt:

- a) Inundation in the lower part of Maridagao Service Area;
- b) Land acquisition for canals and drainages (Right-of-Way);
- c) Uneven benefit distribution (e.g. SEED MALMAR);
- d) Difficulty of constructing on-farm ditches by farmers; and
- e) Delay in contractors' construction progress.

Impacts from MMIP I:

- a) Increase of agriculture production, whereby income increase;
- b) Improved access to markets facilitated by canal maintenance roads and intra-site roads;
- c) Food sufficiency and livelihood sustainability; and
- d) Contribution to peace and order condition.

The following are details of the lessons learnt and impacts from MMIP I are illustrated.

1) Lessons learnt

1.1) Inundation in the lower part of Maridagao Service Area,

Figure 4.1.1 shows the land use map made through the analysis of satellite images for the period from February to July 2016, namely for the dry season of 2016. The areas highlighted with purple color are swampy areas, or water body areas, spreading in the mid-downstream of the MSA. In fact, these areas are lower in elevation compared to the




Figure 4.1.1 Land Use Map of the dry season in 2016, made with satellite images

Source: JICA Survey Team

neighboring areas, and therefore, they tend to be inundated especially during the rainy season.

However, even in the dry season, these areas remained as inundated. One of the reasons for the inundation is the extra water irrigation practice. The paddy cultivation requires ponding water, and therefore, for the paddy cultivation, extra water irrigation practice tends to be seen in many places.

Likewise, as the MMIP II area does not require so much water being still under the construction, the water volume taken at the diversion dam is much more than what is needed in the completed MMIP I area. Therefore, at this moment there is no incentive to save irrigation water for user farmers, and this is leading to extra water application to their farms. Worse, in many cases, there are turnouts which have not been equipped with gates, although these gates were once installed; they have been stolen. With these open or uncontrolled turnouts, water is continuously running and finally stagnated in lower places.

The situation mentioned above may have contributed to a low rate of the irrigated area against the irrigable area. In 2016, the rate of the irrigated area against the irrigable area reached to 58.5% and 59.1% for the rainy and the dry season, respectively. There may be other reasons for such low rates in the application of irrigation, such as inadequate experience, farm tools, financial capacity in the user farmers to manage irrigated paddy fields. To reduce the extra water irrigation cases and also to enhance the drainage functions could contribute to an expansion of the cropped area.

Table 4.1.1 Cropped Area in the Dry and Rainy Seasons (2016)

Particular	Irrigable Area	Rainy Season (2016)	Dry Season (2016)
Area (ha)	5,562	3,256	3,233
Percent	100.0	<u>58.5</u>	<u>59.1</u>

Source: JICA Survey Team

There are lower areas/ spots where they are easily inundated within the MMIP II area, especially, the southern parts of the LMSA which have been inundated many times in the past by flooding from the Pulangi river. Should this situation continue in LMSA, southern parts of the area would turn into swampy area, and thus irrigated cultivation can be hardly practiced. In the MMIP II area as well as completed MMIP I area, water distribution should be well controlled with the installation and sound operation of gates together with the drainage system establishment.

1.2) Land Acquisition for Canals and Drainages (Right-of-Way: ROW)

Major problems regarding ROW of MMIP I were experienced during its implementation period¹: 1) multi-claimants from the same family members for the land ownership; 2) multi-claimants from two or more parties for the ownership of untitled pieces of land; and 3) multiple land title certificates on the same piece of land or certificates of paid local taxes on untitled pieces of land.

Majority of the beneficiaries of MMIP I does not have much knowledge of required procedures for issuance and transfer of land titles, since, traditionally, the only evidence for the transfer of land ownership was through word-of-mouth by the few living witnesses.

In order to avoid any ROW problems, parcellary maps for the project sites should be prepared prior to the construction works, and the negotiation for ROW arrangements should be started base on the maps. Those maps can also contribute to define the actual irrigable area as well as the potential members of future Irrigators Associations (IAs).

¹ Referred to SAPROF study, May 2007, also confirmed through interviews to NIA-PMO

1.3) Uneven Benefit Distribution (e.g. SEED MALMAR)

Uneven distribution of benefits to farmers has brought negative impact². In 2004, the Special Economic Enhancement and Development for Malitubog and Maridagao (SEED-MALMAR) Program provided farmers with farming equipment, inputs, machineries and trainings. The equipment procured by the Provincial Government under the same program was transferred to the IA Federation established in the MMIP I area for further distribution to each of the IAs. However, the equipment and inputs were distributed in an arbitrary way to IA members, in accordance with preference of IA leaders in most of the IAs, while there were no transparent distribution rules and mechanisms put into place. This incidence resulted in conflicts between benefitted and non-benefitted farmers³.

MMIP II will have the agriculture component, and therefore, for example, farming inputs, when arranged, shall be distributed in an equitable manner to all the IA members, or only to poorer farmers, when the budget is limited. Likewise, there should be put into place a revolving mechanism in which beneficiaries shall pay back the due out of his/her produce so that other farmers can be next beneficiaries with the revolved resources.

1.4) Difficulty of Constructing On-farm Ditches by Farmers,

In NIA’s national irrigation system, the on-farm ditches composed of main and supplemental farm ditches are supposed to be constructed by the beneficiary farmers, while the irrigation facilities from the diversion up to the turnouts should be constructed by NIA. In fact, supplementary farm-ditches could be constructed by farmers with simple tools like hoe. However, farmers tend to face difficulties in the construction of main-farm ditches due to their size (see typical section and photos of farm ditches).




Figure 4.1.2 Typical On-farm Ditch Arrangement
Source: JICA Survey Team




Figure 4.1.3 Typical Cross Section of Main Farm Ditch (Left) and Typical Supplementary Farm Ditch (Right)
Source: JICA Survey Team

Since the beneficiary farmers cannot afford to construct main farm ditches, NIA-PMO would construct the main farm ditches, too, while farmers would remain with the responsibility for the construction of

² Referred to the SAPROF study, May 2007

³ Originally, the monitoring and advisory group of SEED-MALMAR requested for PhP 369 Million fund to different concerned agencies but was only allocated PhP 20 million. This limited fund available at that time was also one of the reasons behind the uneven distribution of the procured equipment and materials.

supplementary ditches. Or, alternatively, farmers bear fuel cost while NIA-PMO deploys small backhoes to construct the main farm ditches. In this regard, the MMIP II project should procure and rent small size backhoes to be used in the construction of main farm ditches.

1.5) Delay in Contractors' Construction Progress

There are considerable delays in the current construction works under MMIP II. For example, 16 packages were contracted out to local private construction companies during the fiscal year of 2015 with the contract effective dates of June 15, 2015 for all the packages. The contracts expiry dates were set between October 2015 and April 2016, depending upon the contract size. Surprisingly, all the 16 packages had not been accomplished within the original contract periods, and therefore, the contracts for 15 packages were extended until June 30, 2017 (more than one-year extension), while another remaining package was extended only until March 15, 2016. As of mid May 2017, in fact, there are packages whose accomplish rate has not reached even to 50%, though the contract expiry dates have already passed.

Table 4.1.2 Progress of Procured Packages in 2015 and 2016

Package	Amount (PhP)	Effective Date	Original Duration	Revised Duration	Contract Expiry Date	Achievement rate (%) as of May 15, 2017
Procured in 2015						
Package 1	90,508,389	15-Jun-15	300	655	31-Mar-17	80.59
Package 2	92,013,977	15-Jun-15	300	655	31-Mar-17	69.07
Package 3	134,836,986	15-Jun-15	300	655	31-Mar-17	76.07
Package 4	69,791,476	15-Jun-15	300	655	31-Mar-17	72.23
Package 5	44,483,521	15-Jun-15	240	655	31-Mar-17	50.00
Package 6	24,019,060	15-Jun-15	180	655	31-Mar-17	45.25
Package 7	41,451,208	15-Jun-15	240	746	30-Jun-17	45.00
Package 8	19,829,755	15-Jun-15	180	655	31-Mar-17	56.23
Package 9	18,286,518	15-Jun-15	180	565	31-Dec-17	60.00
Package 10	16,733,264	15-Jun-15	210	655	31-Mar-17	87.34
Package 11	17,410,284	15-Jun-15	180	655	31-Mar-17	100.00
Package 12	10,497,150	15-Jun-15	150	655	31-Mar-17	98.00
Package 13	7,996,229	15-Jun-15	120	655	15-Mar-16	100.00
Package 14	7,766,752	15-Jun-15	120	655	31-Mar-17	84.00
Package 15	41,723,670	15-Jun-15	240	655	31-Mar-17	53.00
Package 16	44,699,742	15-Jun-15	240	655	31-Mar-17	45.69
Procured in 2016						
Package 1	36,671,951	15-Aug-16	180	319	30-Jun-17	12.33
Package 2	34,760,735	15-Aug-16	180	319	30-Jun-17	2.77
Package 3	35,615,631	15-Aug-16	180	319	30-Jun-17	20.31
Package 4	35,756,755	15-Aug-16	180	319	30-Jun-17	6.69
Package 5	35,960,017	15-Aug-16	180	319	30-Jun-17	9.91
Package 6	35,287,024	15-Aug-16	180	319	30-Jun-17	3.12
Package 7	35,484,990	15-Aug-16	180	319	30-Jun-17	20.72
Package 8	36,544,186	15-Aug-16	180	319	30-Jun-17	8.90
Package 9	36,321,456	15-Aug-16	180	319	30-Jun-17	1.70
Package 10	36,321,344	15-Aug-16	180	319	30-Jun-17	0.97
Package 11	39,188,238	15-Aug-16	180	319	30-Jun-17	10.24
Package 12	14,711,150	15-Aug-16	120	319	30-Jun-17	13.88
Package 13	8,491,099	15-Aug-16	100	319	30-Jun-17	6.23
Package 14	13,344,560	15-Aug-16	120	319	30-Jun-17	2.72
Package 15	15,912,027	15-Aug-16	120	319	30-Jun-17	2.68
Package 16	21,503,785	15-Aug-16	150	319	30-Jun-17	10.23
Package 17	12,050,833	11-Nov-16	120	319	30-Jun-17	2.01
Package 18	9,687,539	15-Aug-16	100	319	30-Jun-17	7.32

Source: NIA-PMO

Delays in the construction works again took place with the construction packages procured in 2016 as well. In the fiscal year of 2016, a total of 18 packages was contracted out to local civil contractors on the same date of August 15, 2016. Though the contract expiry dates were set between November 2016

and March 2017, none of the packages were completed within the agreed dates. Worse, Notice of Termination could have been issued in accordance with the guideline of NIA to the 15 packages out of the 18 could have been issued due to serious delay in the schedule.

Most of the contractors are local firms from Midsayap, Pikit, Kabacan, Davao, and other cities, and it seems that their financial capacity may be a hampering factor for them to meet the contract expiry dates. Therefore, it is recommended that the package size should be designed large enough to attract bigger civil contractors, who could associate with local companies to join the bidding. The contract amount per packages for the 2016 procurement ranges from PhP 8.5 million to PhP 39 million, and the majority of packages amounted to almost PhP 35 million. The amounts were not attractive enough for the target contractors, and the size of packages should be made bigger.

2) Impacts from MMIP I

2.1) Increase in Agriculture Production and Income

Prior to the implementation of MMIP I, the local people used to cultivate rain-fed corn and paddy in those areas where water was available. The data allow us to compare the situations before and after MMIP I are not available, however, the difference in yields before and after the project can be summarized as follows, based on the results of surveys conducted by YLTA and the SAPROF team.

Table 4.1.3 Differences in paddy yields before and after MMIP I

Particulars	Rain-fed (Without Project) (t/ha)			Irrigated (with Project) (t/ha)		
	Dry	Rainy	Year-round	Dry	Rainy	Year-round
YLTA Terminal Report (ATI)	NA	NA	2.93	5.52	5.63	5.63
SAPROF Report (May, 2007)	NA	2.00	2.00	4.95	4.77	NA

Source: YLTA Terminal Report, JBIC SAPROF Report (May 2007)

As shown in table above, year-round yield of 2.93 ton/ha was increased to as high as 5.63 ton/ha, increased by 1.9 times under the YLTA program. Also, the SAPROF team confirmed that the rainy season paddy yield was increased more than double from 2.0 ton/ha to 4.77 ton/ha after MMIP I. Through this simple comparison, it can be said that gross profit of the farmers cultivating paddy was almost doubled after the completion of MMIP I.

Table 4.1.4 shows differences in the unit profitability of rain-fed paddy and corn per hectare. Rice is cultivated with irrigation in those farms, where rain-fed corns were cultivated previously, as rice is more profitable. The average net profit of rain-fed paddy can be estimated as PhP 24,896/ha, with the disaggregation of PhP 29,796/ha for the rainy season and PhP 19,996/ha in the dry season. For corn, the average net profit is PhP 16,115/ha disaggregating of PhP 17,454/ha and PhP 14,774/ha in the rainy and dry seasons, respectively.

Table 4.1.4 Differences in Net Profit of Rain-fed Paddy, Corn and Irrigated Paddy

Crops	Financial Gross Profit per ha (PhP)	Financial Cost per ha (PhP)	Financial Net Profit per ha (PhP)	Average PhP/ha
Rain-fed Paddy, Rainy	54,880	25,084.5	29,795.5	24,896
Rain-fed Paddy, Dry	45,080	25,084.5	19,995.5	
Rain-fed Corn, Rainy	33,500	16,046.0	17,454.0	16,115
Rain-fed Corn, Dry	30,820	16,046.0	14,774.0	
Irrigated Paddy wo/YLTA, Rainy	75,200	31,557.9	43,642.1	43,642 (1.75, 2.71)
Irrigated Paddy wo/YLTA, Dry	75,200	31,557.9	43,642.1	
Irrigated Paddy, w/YLTA Rainy	88,360	36,291.6	52,068.4	
Irrigated Paddy, w/YLTA Dry	84,600	36,291.6	48,308.4	

Source: YLTA Terminal Report, JBIC SAPROF Report (May 2007)

With the MMIP I completed, farmers are expected to grow irrigated paddy 2 times in a year, and therefore the net profit of irrigated paddy is estimated at PhP 43,642/ha (average of rainy and dry). It means that the change from rain-fed paddy to irrigated paddy increases the farmer's net profit to 175%

and further the change from rain-fed corn to irrigated paddy increases the net profit to 271%.

2.2) Improved Access to Markets facilitated by Canal Maintenance and Intra-site Roads

The provision of roads along the canal and access roads linking canal roads with Barangay roads has made the inhabitants transport farm products easily to markets. The length of canal roads in MMIP I area stretches over 70 km and access roads over 22 km with a total of 92 km road in Maridagao Service Area. With the improved road condition, transport of agriculture produces can be done at lower price⁴.

Further, children now have wider access to formal educational privileges in primary and elementary level provided by the Government. The provision of roads and bridges made the children commute with the nearest Barangay or Municipality to reach their educational facilities. Parents are proud of and confident of sending children to primary and elementary schools because there is a feeling of peace in the area.

The opening of access roads to service road areas promotes the physical inter-intra integration among the conflict affected communities. This has resulted in the attraction of some temporary populations both during construction and during peak periods of agricultural labor demands. Mobility and transfer of goods and commodities were also improved. With the increasing population, more social service facilities will be needed. Through the implementation of the MMIP I, the social structure and activities could gain grounds based on activated local economy.

2.3) Contribution to Peace and Order Condition

There may be a difficulty of finding out direct relationship between the MMIP I and peace and order establishment in the area. However, there may be a possibility that the MMIP I has contributed to sustain peace and order once, for example, cessation of hostilities were agreed upon. As a matter of fact, for decades, the Project area was a ground for armed encounters between the Armed Forces of the Philippines (AFP) and the Moro National Liberation Front (MNLF), and then Moro Islamic Liberation Front (MILF). This condition was further aggravated by the constant occurrence of conflicting clans and tribes.

However, according to SAPROF report (May 2007), it is said that with the implementation of the MMIP I and the continued commitment of the Government to effect peace and development in the region, the peace and order condition were drastically improved. The project area was declared a zone of peace and therefore, the implementation of MMIP I was regarded by many local people as a development project that promoted the building of a community of peace.

The members of MNLF and MILF are basically such people who engaged themselves in fighting once ordered or once incident takes place, however otherwise they engage themselves in raising their own livelihood. It means that when the cessation of hostilities is agreed upon, they may tend to return to their livelihood, which is basically farming. The last major conflict recorded between MILF and AFP in and around the Project site was in 2003. The delivery of irrigation water by MMIP I, according to NIA-PMO, served as turning point for several MILF members who had returned and resumed the livelihood, farming and also fisheries to some extent.

4.1.2 Project Implementation Schedule

MMIP I was completed in year 2011, and at the same time construction in MMIP II was launched

⁴ During SAPROF survey, it was confirmed that prior to canal road construction, according to interviews with local residents, they used to pay 35 Pesos to 45 Pesos per bag of rice for carabaos with sled from farm to market depending on distance. Upon completion of the roads within MMIP I area, the inhabitants can sell rice with only the cost of P25 Pesos per bag.


starting with UMSA. The construction of the Upper Malitubog irrigation facilities was completed in 2016, and also the construction moved into PESA and a mid-eastern part of Lower Malitubog Service Area in year 2015.

Further, the central part of the LMSA launched the construction in 2016, and then, as of May 2017, tendering for the most western part of LMSA had been completed, and the construction was commenced within the year 2017. In year 2018, NIA is planning to start such works as dredging of Calawag creek running almost along northern boundary of LMSA. Those works are to require minimum 2 years, or even more than 3 years, till the completion from the commencement taking into account the capacity of the contractors available.

Following chart illustrates the past construction progress by service area and current on-going and estimated future construction plan. In this schedule, since ODA request was officially withdrawn on June 21, 2018, all the remaining works are to be managed by NIA's budget within the NEDA approved budget of Php 5,444,850,000.00. With this, the remaining part is to start in 2019 and continue up to year 2023, requiring almost 4-year implementation based on the on-going experiences.

Table 4.1.5 Implementation Schedule

Construction of MMIP I & MMIP II	Area, ha	Progress	1990	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024
Maridagao Service Area	5,562	Completed in 2011															
Upper Malitubog Service Area (MMIP I)	1,611	Completed in 2011															
Upper Malitubog Service Area (MMIP II)	2,958	Target															
		Actual															
Pagalungan Extension Service Area	988	Target															
		Actual															
Lower Malitubog Service Area (LMSA)	6,590																
Mid-eastern part	1,303	Target															
		Actual															
Central Part	1,736	Target															
		Actual															
Western Part	1,418	Target															
		Actual															
Eastern Part (remaining area)	2,133	Target															

Source: NIA-PMO, JICA Team  Estimated

4.1.3 MMIP II Delineation and Components

As the flood simulation revealed (see Chapter 3), there should be NO dike construction for the purpose of protecting the LMSA from flood coming from the Pulangi river. This is because, as afore-explained in Chapter 3, 1) the dike construction may need foundation treatment which raises construction cost beyond the economic viability, 2) rainfall on the LMSA will accumulate therein whereby inland inundation would take place which accordingly reduces the beneficiary area of LMSA, and 3) other means e.g. dredging of the Pulangi river and/or pumping of the accumulated inland inundation would also go beyond economic viability.

Therefore, this Survey recommends that in any case NO dike should be constructed, and instead 2 cases of development of irrigation networks for the LMSA should be explored; i.e. 1) construct the irrigation network up to the peripheral delineated, within which the paddy cultivation can still be managed with allowable inundation depth (usually maximum 50cm), and 2) construct the irrigation network as originally planned. For the latter case (Case-2), lower parts of the irrigation network will be inundated every year during rainy season, however during dry season full beneficial area could be cultivated on condition that damaged parts during the rainy season are to be well maintained/ repaired.

As for drainages, all the planned drainage canals should be recommended to construct for the both Case 1 and Case 2 in order to facilitate the dry season paddy cultivation. With the well-established drainage networks draining out to the Pulangi river, dry up of the wet lands inundated during rainy season could be facilitated, so that the dry season paddy cultivation could be started as planned. However, it is noted that maintenance of drainage canals should be well financed as every year inundation would definitely increase the cost as compared to commonly developed irrigation systems seldom affected by flooding.




Figure 4.1.4 Conceptual Irrigation Development of Case 1 and Case 2

Source: JICA Survey Team

Given the 2 cases for the LMSA irrigation development, the major component is, no doubt, the irrigation and drainage installment for the remaining areas of LMSA. The LMSA is sub-divided into 4 parts in terms of contractor procurement year, meaning commencement year of the civil works. The construction works have continued since 2015, and as of July 2018, the untouched area is the only eastern part of the LMSA. Note that construction in the most western part has not yet started within 2017, however tendering for the civil contractor had already been held in May 2017. Therefore, the contractor procurement for the western part had been completed within 2017, and actual construction works started in 2018.

Taking into account what was mentioned above and also the current condition of MMIP I and MMIP II which had been already completed somewhat ago, the remaining construction area and the components are to be as follows:

- 1) Irrigation and drainage development of the remaining area of LMSA in which there should be 2 cases; namely, 1) development of irrigation canals within a limited LMSA where paddy can be cultivated even during rainy season, and 2) development of irrigation canals as per the original plan under which dry season cultivation could be made as per the original plan while rainy season cultivation would be restricted due to the flooding. In the most eastern part of LMSA, still untouched area as of 2018 and originally requested area for ODA loan, main canal (MC 2) and associated lateral canals should be constructed according to the coverage by case, and main drainage canal and lateral drainage canals are to be constructed as per the original plan.
- 2) Distribution infrastructure improvement (construction of intra-roads), which works as

farm-to-market road in order to ship produced agricultural commodities out of the farmlands as well as facilitate rural population's mobility especially during rainy season, in which roads become muddy and impassable,

- 3) Agriculture and extension development to facilitate the beneficiary farmers able to well utilize irrigation water, whereby 2 times irrigated paddy cultivation is to be established in the MMIP II area. Note that this agriculture and extension development activity should cover not only the remaining eastern part of LMSA but also whole MMIP areas which have not yet received any agriculture extension services by, e.g. YLTA.
- 4) Other related works in line with the irrigation development, i.e. parcellary mapping, IA establishment, which are conducted by NIA-PMO and maintenance office. Note that these activities are to be implemented as a part of project management/ administration.
- 5) *Rehabilitation and, to some extent, improvement of irrigation and drainage facilities in the MMIP I area since the construction of MMIP I started in 1990 whereby there are facilities already aged and in need of rehabilitation,*
- 6) *Improvement of irrigation and drainage facilities in the MMIP II already completed area, namely, Upper Malitubog Service Area, which could be, for example, partial concrete lining for large lateral canals, bifurcation points, branching points and points where there are hydraulic structure, and*
- 7) *Procurement of machineries to be used for the maintenance of irrigation facilities of MMIP I and also MMIP II, e.g., excavator, dump truck, etc.*

Of them above, No.1 is the major project component, which is the construction and development of the irrigation and drainage facilities in the untouched area of LMSA. The sub-component of No.2 is a sort of rural infrastructure, which can facilitate transportation of agriculture produces and mobility of local population. Sub-component No.3 is conducted by ATI in collaboration with NIA-PMO and Cotabato Irrigation Management Office, which could complement irrigated agriculture promotion. Further, No.4 activity should be implemented in line with the irrigation development. These 4 sub-components are the highest priorities among above 7 sub-components, which should be put into implementation.

In addition to above 4 sub-components, the JICA team also recommends to implement sub-components No.5, No.6 and No.7 as well, on condition that these 3 components could be conducted by another GOP budget allocation or otherwise there could be donor assistances as MMIP III. No.5 is recommended to undertake rehabilitation works for the MMIP I area; No.6 to conduct an improvement of MMIP II completed area, and No.7 to be a procurement of machineries which facilitate maintenance works.

4.2 Agriculture and Extension Development

4.2.1 Agricultural Development Strategy of the Philippine Development Plan 2017-2022

The Philippine Development Plan 2017-2022 was officially approved by the National Economic and Development Authority (NEDA) Board on February 20, 2017. A framework of mid-term agricultural development strategy in the development plan is summarized in Table 4.2.1:

**Table 4.2.1 Strategic Framework of Agricultural Development
of the Philippine Development Plan 2017-2022**

Goal	The goal is to increase productivity and access
Outcome A	Expanded economic opportunities for farmers
A-1	Productivity within ecological limit improved <ul style="list-style-type: none"> To identify the comparative advantage of specific areas for promoting suitable crops and agricultural activities To construct irrigation system in high potential area (Central Luzon, Cagayan Valley (Region II), SOCCSKSARGEN (Region XII), ARMM and Bicol Region) To promote effective and efficient water saving and management technologies To facilitate the use of appropriate farm machinery and equipment To strengthen the extension system
A-2	Agro-based enterprises increased <ul style="list-style-type: none"> To develop commodities based on vulnerability, sustainability, and value-chain analysis in order to promote commodities with high value-adding and market potential To develop new form of linkages such as contract farming and corporate farming that will connect with agro-based enterprises To strengthen community-based enterprises in upland areas
Outcome B	Increased access to economic opportunities by small farmers
B-1	Access to value-chains increased <ul style="list-style-type: none"> To improve linkage between production area to market through transport networks and logistic system To organize small farmers into formal groups and farms into clusters to create economies of sale To provide capacity building for small farmers on value adding activities To provide non-farm livelihood options to seasonal farm workers through community-based employment programs
B-2	Access to innovate financing increased <ul style="list-style-type: none"> To increase the number of small farmers who are provided with agricultural insurance To provide small farmers easy access to affordable formal credit
B-3	Access to technology increased <ul style="list-style-type: none"> To raise investments in R&D for production and post-harvest technologies To enhance capacity building of small farmers to adopt better and new technologies (certified seeds and technologies for post-harvest, processing and packaging)
B-4	Access of small farmers to land and water resources increased and protected <ul style="list-style-type: none"> To ensure and protect the land tenure security of ARBs (Agrarian Reform Beneficiaries) To provide timely and free legal assistance to ARBs To authorize LGUs to reclassify agricultural land for other users

Note: Descriptions related to fisheries development are excluded

Source: Philippine Development Plan 2017-2022

The strategy is focusing on expansion of economic opportunities for farmers through increasing agricultural productivity, as well as on increased access to the opportunities through improving farm management and supporting systems. While the government has maintained key priorities in the agricultural policy, which have been to alleviate poverty by ensuring a stable and affordable supply of food and to promote self-sufficiency, particularly in rice production, the new strategy would pay more attention to the strengthening of overall farm productivity and profitability on a sustainable basis.

4.2.2 Agriculture Planning on the Project

The agriculture promotion by the Project well corresponds with the above agricultural development strategy of the Philippine Development Plan 2017-2022, especially with Outcome A-1. As shown in Table 4.2.1, Outcome A-1 pursues improvement of agricultural productivity through; 1) promotion of “right crop for right land”, 2) development of irrigation systems (Region XII and ARMM are included in the high potential area), 3) promotion of water saving and management technologies, 4) facilitation of the use of farm machinery and equipment and, 5) enhancement of extension services.

1) Cropping Pattern in the MMIP II area

As the MMIP I area has achieved to a large extent, rice shall be exclusively promoted also in the irrigated area of MMIP II with the following reasons:

- a) Rice is the most important crop of overwhelming majority of farmers in terms of main food and their livelihood;
- b) Sufficient irrigation water will be available for growing rice throughout the year with the project completed;
- c) Rice is the right crop for the irrigated land (consistent with “right crop for right land” strategy);
- d) Rice promotion has been a principal pillar of the national agricultural policy considering food security and poverty reduction;
- e) Farmers can expect a certain level of stable returns from rice, especially with a help of irrigation; and
- f) Productivity of rice in the area is still low, leaving currently a big room for production increase of rice.

Corn, rice and coconut are the dominant crops planted in the Project area at present. Corn and rice are mostly grown under rain-fed condition in annual crop fields mainly developed in flat river basins. Local farmers generally grow corn or/and rice two times or even more in a year, depending on water availability, starting from around February or March until the end of the year. Both crops actually do not have a definite cropping season due to relatively steady condition of rainfall and temperature throughout the year.

As explained in the above cropping strategy, two-time cropping of rice in a year is expected in all the irrigated areas developed by the Project (see Figure 4.2.1). The Project, however, should maintain existing coconut trees and some other perennial crops grown around annual crop fields as they are. Besides, JICA team recommends introduction of vegetable crops on home gardens in terms of crop diversification in the MMIP area”.




Figure 4.2.1 Conceptual Cropping Pattern in the Project Area before and after the Project

Source: JICA Survey Team

2) Increase of Crop Production by Improvement of Yield and Expansion of Planted Area

The JICA team estimated average productivity of rice and corn before and after the Project in the area from relevant statistical data of various sources, e.g. Country STAT Philippines, the Terminal Report of YLTA-MMIP, information from the OPA of Cotabato Province, DAF-ARMM, and the Baseline Survey. Table 4.2.2 summarizes data from the relevant statistics, and also shows, in the lowest part, estimated current yields and expected target yields with irrigation water to be supplied upon completion of the Project. For the current yield, those from baseline survey were referred, and the target was decided as year-round yield mainly based on the wet season yield of SAPROF report:

Table 4.2.2 Productivity (ton/ha) of Rice and Corn from Relevant Statistical Data

No	Source	Crop	Rain-fed			Irrigated			Remarks
			Dry	Wet	Year-round	Dry	Wet	Year-round	
1	YLTA Terminal Report (ATI)	Rice	NA	NA	2.93	5.52	5.63	5.63	368 farmers from 7 IAs in Phase I
2	Country STAT Philippines (Production)	Rice	NA	NA	2.95	NA	NA	4.18	Cotabato Province, 2014-16 Ave.
			NA	NA	2.36	NA	NA	3.56	Maguindanao Province, 2014-16 Ave.
		Corn	White		2.30	Yellow		3.34	Cotabato Province, 2013-15 Ave.
			White		2.38	Yellow		3.36	Maguindanao Province, 2013-15 Ave.
3	Country STAT Philippines (Production Costs & Returns)	Rice	2.76	2.98	2.92	3.88	4.18	4.05	Region XII, 2013
			1.88	2.65	2.28	3.26	3.24	3.25	ARMM, 2013
4	OPA, Cotabato Province	Rice	NA	NA	3.50	NA	NA	4.50	Pikit Municipality (2014-16 Ave.)
		Corn	White		3.90	Yellow		4.20	
5	SAPROF Report (May, 2007)	Rice	NA	2.00	2.00	3.00	3.00	3.00	Before irrigation facilities completed
			NA	NA	NA	4.95	4.77	NA	After irrigation facilities completed
6	Baseline Survey (JICA Survey Team)	Rice	NA	NA	1.69	NA	NA	3.38	
		Corn	NA	NA	2.12	NA	NA	NA	
		Rice (Current/ target)	-	-	1.7	-	-	4.7	
		Corn (current)	-	-	2.1	-	-	-	

Note: current yields were decided based on the results of baseline survey (JICA survey team), and the target yield of rice was mainly based on the wet season rice yield of SAPROF report as year-round yield. Note that the yields between dry season and wet season are not much different in the Project area and also in the Philippines or even the wet season yield is sometimes higher than that of dry season, and therefore in this survey, year-round yield was applied irrespective of the season.

Source: Various statistics, JICA Survey Team

Table 4.2.3 shows estimated planted area and production of crops in LMSA before the project and after the project while Table 4.2.4 shows that of whole MMIP II area. Rice and corn are grown in the both seasons of dry season and wet season under rain-fed condition at present. The annual production of the both crops from the both seasons is estimated at 5,354 tons (1,401 for rice and 3,953 for corn) and 8,559 ton (2,240 for rice and 6,319 for corn) for LMSA and MMIP II area respectively.

As per the LMSA (see Table 4.2.3), while 3,688 ha of land is expected to be irrigated and planted with the Project, the area in wet season is to be 2,810 ha of which decrease is attributed to inundation in Case-1 where the irrigation canals are to be constructed only within the area having not more than 50 cm inundation. Out of 2,810 ha, 870 ha is estimated not to be inundated by flooding and can be fully planted during wet season. On the other hand, 1,940 ha of land have inundation with its height of up to 0.5m. In this regard, irrigated rice production on this 1,940 ha of land would have some damages on its productivity due to flooding, and therefore Table 4.2.3 takes into account possible production reduction of 30%, 50% and 80%. Case-2 where the canal network is constructed as per the NIA-PMO original plan is also calculated given above conditions as Table 4.2.3 indicates.

On the whole area of MMIP II, Table 4.2.4 shows total 7,634 ha of planted area in dry season while it

is 6,756 ha in the wet season under Case-1 where the irrigation canals in the LMSA are to be constructed only within the area of LMSA having not more than 50 cm inundation. If the canal network is constructed as per the original NIA-PMO design for the LMSA, the irrigable area will 10,536 ha same as the MMIP II original design area during the dry season and that of wet season will be 7,756 ha due to inundation within the LMSA.

For the MMIP II whole area, out of 6,756 ha, 4,816 ha is estimated not to be inundated by flooding and can be fully planted during wet season. On the other hand, 1,940 ha of land have inundation with its height of up to 0.5 m. In this regard, irrigated rice production on this 1,940 ha of land would have some damages on its productivity due to flooding, and therefore Table 4.2.4 takes into account possible production reduction of 30%, 50% and 80%. Case-2 where the canal network is constructed as per the NIA-PMO original plan is also calculated given above conditions as Table 4.2.4 indicates.

On the whole, the growing area and productivity will be remarkably increased by the Project upon completion. Consequently, a total of the annual rice production will be 30,541 ton with Case-1 and 48,880 ton with Case-2 for the irrigable area of LMSA unless flooding occurs. As for MMIP II whole area, the total of the annual rice production will be 67,633 ton with Case-1 and 85,972 ton with Case-2 unless flooding occurs in the LMSA.

Table 4.2.3 Annual Planted Area and Production of Rice and Corn in the LMSA

Case	Crop	Dry Season			Wet Season			Total Production (ton)
		Planted Area (ha)	Yield (ton/ha)	Production (ton)	Planted Area (ha)	Yield (ton/ha)	Production (ton)	
-	Without Project							
-	Rice (rain-fed)	457	1.7	777	367	1.7	624	1,401
-	Corn	795	2.1	1,670	1,087	2.1	2,283	3,953
C1	With Project (Case-1)							
C1-LM-D00	Rice (Irrigated)	3,688	4.7	17,334	2,810	4.7	13,207	30,541
C1-LM-D30	30% reduction	3,688	4.7	17,334	870	4.7	4,089	27,631
					1,940	3.2	6,208	
C1-LM-D50	50% reduction	3,688	4.7	17,334	870	4.7	4,089	25,885
					1,940	2.3	4,462	
C1-LM-D80	80% reduction	3,688	4.7	17,334	870	4.7	4,089	23,169
					1,940	0.9	1,746	
C2	With Project (Case-2)							
C2-LM-D00	Rice (irrigated)	6,590	4.7	30,973	3,810	4.7	17,907	48,880
C2-LM-D30	30% reduction	6,590	4.7	30,973	870	4.7	4,089	44,470
					2,940	3.2	9,408	
C2-LM-D50	50% reduction	6,590	4.7	30,973	870	4.7	4,089	41,824
					2,940	2.3	6,762	
C2-LM-D80	80% reduction	6,590	4.7	30,973	870	4.7	4,089	37,708
					2,940	0.9	2,646	

Note: planted areas for rice and corn for the without project (current condition) were estimated based on the satellite data analysis for the LMSA.

Source: JICA Survey Team

Table 4.2.4 Annual Planted Area and Production of Rice and Corn in the whole MMIP 2 Area

Case	Crop	Dry Season			Wet Season			Total Production (ton)
		Planted Area (ha)	Yield (ton/ha)	Production (ton)	Planted Area (ha)	Yield (ton/ha)	Production (ton)	
-	Without Project							
-	Rice (rain-fed)	731	1.7	1,242	587	1.7	997	2,240
-	Corn	1,271	2.1	2,669	1,738	2.1	3,650	6,319
C1	With Project (Case-1)							
C1-LM-D00	Rice (Irrigated)	7,634	4.7	35,880	6,756	4.7	31,753	67,633
C1-LM-D30	30% reduction	7,634	4.7	35,880	4,816	4.7	22,635	64,723
					1,940	3.2	6,208	
C1-LM-D50	50% reduction	7,634	4.7	35,880	4,816	4.7	22,635	62,977
					1,940	2.3	4,462	
C1-LM-D80	80% reduction	7,634	4.7	35,880	4,816	4.7	22,635	60,261
					1,940	0.9	1,746	

Case	Crop	Dry Season			Wet Season			Total Production (ton)
		Planted Area (ha)	Yield (ton/ha)	Production (ton)	Planted Area (ha)	Yield (ton/ha)	Production (ton)	
C2	With Project (Case-2)							
C2-LM-D00	Rice (irrigated)	10,536	4.7	49,519	7,756	4.7	36,453	85,972
C2-LM-D30	30% reduction	10,536	4.7	49,519	4,816	4.7	22,635	81,562
					2,940	3.2	9,408	
C2-LM-D50	50% reduction	10,536	4.7	49,519	4,816	4.7	22,635	78,916
					2,940	2.3	6,762	
C2-LM-D80	80% reduction	10,536	4.7	49,519	4,816	4.7	22,635	74,800
					2,940	0.9	2,646	

Note: planted areas for rice and corn for the without project (current condition) of the MMIP II area were estimated by applying the same cropping ratios of LMSA to whole the MMIP II area.

Source: JICA Survey Team

Table 4.2.5 shows characteristics of irrigated rice varieties planted in 2017 and irrigated rice varieties recommended by PhilRice. Out of them, NSIC RC 222 is one of the four recommended varieties for the rainy season in Philippines, which stands at most 100 cm and with strong stems that can withstand against 40-60 kph wind speed and also against inundation. Since the MMIP area, particularly the MMIP II area, is prone to be inundated, such submerge-tolerant varieties should be tried.

According to an officer in-charge of the PhilRice Midsayap, the institute once conducted trials for the submerged-tolerant varieties, but found out that the yield performance is very low and therefore discontinued. He mentioned that said tested varieties can tolerate flooding, up to a maximum of 21 days during the vegetative stage of the plant. However, the varieties rarely grow if waterlogging occurs over the farmland during the maturing stage. It is obvious that even submerge-tolerant varieties cannot be grown in the totally inundated area of MMIP II during a long wet season, therefore reduction of the planted area is inevitable as Table 4.2.3 and Table 4.2.4 show. In order to mitigate reduction of the productivity in the partial inundated area, such submerge-tolerant variety should still be tested in the farmers' field.

Table 4.2.5 Characteristics of Planted and Recommended Rice Varieties by PhilRice in the MMIP Area

Name of Variety	Average Yield (ton/ha)	Max Yield (ton/ha)	Maturity (days)	Height (cm)	Reaction to Pest and Diseases	Grain Size	Milling Recovery (%)
Existing irrigated rice varieties planted in 2017							
NSIC RC 238 (Tubigan 21)	6.4	10.6	110	104	Moderately resistant to blast, BPH, stem borer and GLH, intermediate reactions to BLB and sheat blight, susceptible to tungro	long	70.4
NSIC RC 158 (Tubigan 13)	6	8.1	113 after seeding	94	Intermediate reaction to blast, bacterial leaf blight, green leaf hopper and tungro. Moderately susceptible to brown plant hopper. Resistant to white stem borer	long	71.1
NSIC RC 222 (tubigan 18) If transplanted	6.1	10	114	101	Intermediate to blast, bacterial leaf blight and tungro, Moderately resistant to brown planthopper and green leaf hopper.	long	68.5
NSIC RC 222 (tubigan 18) If direct seeded	5.7	7.9	106	98	Suitable for prolonged rainfed area.		
NSIC RC 128 (Mabango 1) (A)	5.5	6.2	118 days after seeding	99	Intermediate reaction to blast and tungro, moderately susceptible to brown planthopper and green leafhopper. Intermediate reaction to stem borer and bacterial leaf blight	long	65.4
NSIC RC 226 (Tubigan 20) If transplanted	6.2	9.8	112	102	Moderately resistant to brown planthopper and green planthopper. Susceptible to blast, tungro and bacterial leaf blight	NA	NA
NSIC RC 226 (Tubigan 20) If direct seeded	5.4	8.5	104	102		NA	NA
Recommended Irrigated Rice Varieties							
NSIC RC 158	ditto						
NSIC RC 222	ditto						
NSIC RC 226	ditto						

Name of Variety	Average Yield (ton/ha)	Max Yield (ton/ha)	Maturity (days)	Height (cm)	Reaction to Pest and Diseases	Grain Size	Milling Recovery (%)
PSB RC 10 (PAGSANJAN)	4.8	7.5	106 after seeding	77	Resistance to blast and brown planthopper. Intermediate reaction to bacterial leaf blight, tungro and stem borer. Moderately resistant to green leaf hopper.	medium	66.62
PSB RC 18	5.1	8.1	123 after seeding	102	Moderately susceptible to stem borer Intermediate reaction to blast, bacterial leaf blight, tungro, brown planthopper and green planthopper	long	65.34

Source: Interview to rice seed growers and PhilRice

4.2.3 Agriculture Supporting Plan

To ensure the aforementioned productivity and accelerate impact of the infrastructure development, the Project should incorporate an agriculture supporting plan into its development. This agricultural support plan shall basically be funded solely by ATI¹ with possible provisions from donors and other institutions will technically support the implementation, who are NIA, PhilRice, University of Southern Mindanao (USM), the Bureau of Plant Industry - National Seed Quality Control Services (BPI-NSQCS).

The plan possesses; 1) Technical Assistance for Irrigated Rice Production, 2) Enhancement of Agriculture Extension Services at Municipality Level, and 3) Development of Seed Production (see Appendix IV for the details of planned inputs and cost on each sub-component).

1) Technical Assistance for Irrigated Rice Production

As already discussed in “2.3.5 Agricultural Extension Service to Farmers”, Yen Loan Technical Assistance (YLTA) had achieved significant and tangible results on the rice productivity improvement. Given a strong request from IAs’ members in the MMIP area, the Government has also funded a similar program to YLTA. Although the government program continues until dry season in 2019, all the IAs in the MMIP area will not be benefited, particularly those in the MMIP II area. Therefore, the Project should continue the same approach to cover the entire area of the MMIP.

1.1) Objective

This sub-component expands technical assistance for irrigated rice production to Irrigators Associations (IAs) who were not targeted by the original YLTA and the government fund, so that it aims at increasing the productivity of rice in the whole MMIP area through improvement of farming technologies and management of the IAs.

1.2) Approach

The supporting approach of the original YLTA is systematized by the MMIP technical team of the ATI Regional Training Centre (XII) as summarized in Table 4.2.6 and Table 4.2.7. The supporting approach in this sub-component should basically adhere to the approach of YLTA including the implementation setup. As already discussed, the main components of YLTA are; 1) Participatory Demonstration Farms (PDF), 2) Farm Production Input Assistance (FPIA), and 3) Development of Extension Modality (see Table 4.2.6).

In order to cope with the uneven benefit distribution observed in SEED MALMAR, Farm Production Input Assistance on this activity has to have an arrangement of roll-over scheme as the original YLTA

¹ Even if Bangsamoro Basic Law (BBL) is enacted and the Bangsamoro Autonomous Region is established, ATI should still implement the agriculture supporting plan in the project area of the Region. In that case, ATI should gain permission from the Region to conduct the activities. Therefore, memorandum of understanding on the activities should be agreed by both department of agriculture in the Bangsamoro Autonomous Region and ATI.

achieved 100% of repayment for agricultural inputs from the beneficial farmers.

Regarding PDF, the participant farmers tried three technologies on their farm plot; i.e., Palaycheck, System of Rice Intensification (SRI), Direct Wet Seed Rice in addition to ordinary practices. The JICA team suggests that this sub-component also undertakes trials on varietal performance, fertilizer application and planting method; direct sowing versus transplanting, to test not only the yield but also the optimum economic benefit.

Especially, fertilizer application should not be maximized in the areas likely inundated by flooding since it may cause lodging of paddy when used in high amounts. This would increase the damages of rice production caused by inundation during wet season. According to PhilRice, although it depends on soil analysis results and recommended nutrient requirement rates, it is better to reduce fertilizer application rates by 20-30% in the season.

Table 4.2.6 Main Components of YLTA and Their Activities

1	<p>Establishment of Participatory Demonstration Farm (PDF) on a 5-hectare area, per IA</p> <ul style="list-style-type: none"> - conduct of major ground working activities; selection of IA beneficiaries, farmer-cooperators and benchmark survey - soil sampling and analysis - conduct of technical briefing on rice production - provision/distribution of agricultural support facilities - conduct of Farmer's Field Day (FFD) - conduct of Climate Smart Field School (CSFS)
2	<p>Farm Production Input Assistance (FPIA) to 25-hectare rice farm areas</p> <ul style="list-style-type: none"> - conduct of major ground working activities: selection of IAs, farmer-beneficiaries, and benchmark survey - soil sampling and analysis - conduct of technical briefing on rice production - provision/distribution of agricultural farm inputs - expository tour - conduct of values re-orientation and Islamic culture appreciation - farmer-led extension - organizational strengthening of IAs: training on enterprise development
3	<p>Extension Modality</p> <ul style="list-style-type: none"> - conduct of weekly project implementation monitoring activities - mid-year progress report review and planning-workshop - year-end progress report review and planning/ workshop cum presentation to stakeholders - preparation of extension manuals - exit conference

Source: Adapted from the MMIP Experience

Then, above components are organized in a step-wise manner as Table 4.2.7 shows:

Table 4.2.7 YLTA Implementation Process

Step	Activity	Description
Step 1	To prepare project document	Finalizing a detailed project proposal and manual for project operation.
Step 2	To brief project implements	Field facilitators together with PMT (Project Management Team) meet to discuss specific duties as enumerated in the project manual.
Step 3	To prepare local community	PMT prepares to make courtesy calls or meetings with local formal/informal leaders.
Step 4	To identify beneficiaries and participatory demonstration sites	Using criteria, recipient IAs are named. Farmers from the participating IA's who qualify as PDF (Participatory Demonstration Farm) and FPIA (Farm Production Input Assistance) cooperators are also identified.
Step 5	To set project launching	A separate MOA (Memorandum of Agreement) between the project and the recipient IAs is signed to document the commitment of participating farmers to the project implementation. On this occasion, local community leaders witness the signing of MOA.
Step 6	To train the project implementers (TOT: training of trainers)	Various trainings or capacity building activities are conducted at all phases of the project to equip and enhance the knowledge and skills of the project implementers.
Step 7	To collect baseline data	Baseline data are gathered from PDF and FPIA farmer-cooperators before the start of a cropping season. A focus group discussion with the farmer-cooperators is also conducted to validate the results.

Step	Activity	Description
Step 8	To conduct rice production briefing to farmers; To collect soil samples for analysis; To train farmers to use and maintain farm machines	PDF and FPIA farmer-cooperators are required to attend a technical briefing on rice production technologies (Palay Check System). The farmer-cooperators collect soil samples with a field facilitator's assistance in order determine the type and amount of fertilizers. At this briefing, the farmers get hands-on training on farm machine operation and maintenance.
Step 9	To procure and deliver farm inputs, tools and machines	Necessary farm inputs and farm machinery for PDF and FPIA are identified by the lead project implementer together with the farmer-cooperators, recipient IAs and irrigation water administrators. The procurement process follows the required bidding rules and procedures set by the COA (Commission on Audit).
Step 10	To conduct various farmers trainings	Social and technical trainings to the farmer-cooperators are carried out with parallel implementation of CSFS (Climate Smart Field School). Trained farmers act as lead farmers to their respective IA and share knowledge to other IA members.
Step 11	To set-up PDF and organize CSFS	PDF utilizes a 5.0 ha compact area composed of several different plots designed to showcase rice farming technology that is cost-reducing and yield enhancing from land preparation to post harvest management. Within the 5.0 ha PDF, a small area of 1000 m2 is allocated as learning site for CSFS.
Step 12	To monitor fields and coach/mentor farmers	Regular field monitoring after establishment of PDF and CSFS is carried out primary by PMT. Also close monitoring of PDF and FPIA beneficiaries is made on proper utilization of farm inputs.
Step 13	To conduct periodic assessment of the project	PMT meets once a month to assess the status of project implementation and to discuss issues and concerns that need immediate/appropriate action.
Step 14	To organize farmers field day (FFD)	A field day is scheduled when the rice crop is at the ripening phase in order to showcase the results of PDF and the collaborative studies of CSFS.
Step 15	To organize educational trips	After harvest, an organized educational/exposure trip for CSFS graduates is conducted to reinforce their learnings and insights gained from PDF and CSFS. The education trip exposes the farmers in rice trading and other business or entrepreneurial activities.
Step 16	To conduct project evaluation/review	In determining the strengths and weaknesses of the project, a review is conducted to determine whether target accomplishments both physical and financial are met. The review also looks at whether project aims and objectives are achieved.
Step 17	To write the project terminal report	The report tells the story of the project. It documents the project accomplishment and outcome and constitutes a full record of project activities especially the results of an evaluation. PTM takes care of the documentation.

Source: Adapted from the MMIP Experience

1.3) Activities

The supporting services will be provided through IAs in the Project area and there will be soon a total of 49 IAs in the entire MMIP area as of June 2018. Those IAs shall be the potential target for the agricultural supporting plan of the Project. However, as shown in Table 4.2.8, 21 IAs in MSA and UMSA have already received the supporting services from YLTA or additional extension program funded by GOP, so that the recommended successive YLTA program will not target those IAs.

Table 4.2.8 Number of IAs in the MMIP Area as of June 2018

Irrigation Service Areas	Number of IAs	Remarks
Maridagao Service Area (MSA)	12	All the IAs participated in YLTA and/or the GOP funded program
Upper Malitubog Service Area (UMSA)	13	While all of them did not participated in YLTA, 9 IAs out of 13 did in the GOP funded program.
Lower Malitubog Service Area (LMSA) and Pagalungan Ext. Service Area	24	Thirteen IAs registered to the Security and Exchange Commission (SEC)* and 3 IAs are now on process. Additional 8 IAs are soon to be established as of June 2018.
Total	49	

Note: *Organizations, particularly associations with a set of incorporators that need to have a legal personality, are required to be registered with the SEC. It usually provides a pro-forma Articles of Incorporation to associations to be organized.

Source: NIA PMO and ATI

As the program of GOP is expected to continue up to the dry season in 2019, all of the 18 IAs would be able to receive the 2nd round services. The agriculture support plan is therefore scheduled as shown in Table 4.2.9 with the following assumptions considering the present progress of the additional program of GOP and the total project implementation schedule:

- Implementation period from dry season in 2020 to dry season in 2022 (the additional program of GOP will cover the period from the wet season in 2018 to the dry season in 2019);
- The supporting plan concentrates on 28 IAs which have neither received supporting services from YLTA nor additional program of GOP; and
- The supporting services are provided for a set of seasons, dry and wet season, per one IA.

Table 4.2.9 Implementation Schedule of YLTA Phase II

IAs	2018		2019		2020		2021		2022		2023		2024	
	Dry	Wet	Dry	Wet	Dry	Wet	Dry	Wet	Dry	Wet	Dry	Wet	Dry	Wet
GOP funded support program														
1st batch (10 IAs)														
2nd batch (10 IAs)														
3rd batch (8 IAs)														
M&E and report making														

Source: JICA Survey Team

Table 4.2.10 summarizes necessary inputs of this sub-component;

Table 4.2.10 Necessary Inputs of Technical Assistance for Irrigated Rice Production

Inputs	Description
Staff	Technical Staff; 11 person x 3 years Documenter/ Information Officer; 1 person x 3 years Support Staff/ Administration; 1 person x 3 years Accounting Clerk; 1 person x 3 years
Equipment and Office Materials	Motorcycle (125 cc, 4-stroke) x 11 Photocopying machine x 1 Mobile phone x 12 Laptop computer x 2 Desktop Computer x 1 Computer Table with Chair x 1 Laptop Computer x 1 Printer x 1
Trainings	For Farmer Cooperator 1. Orientation & Briefing of PDF & CSFS Cooperators 2. Benchmarking and FGD Among Prospective PDF & FPIA Beneficiaries 3. Season Long Training on Climate Smart Field School For IA officers 4. Orientation of IA Officers 5. Planning Workshop of Implementers 6. Farmer-Led Extension Approach on Rice Production 7. Enterprise Development Training 8. Skills Training on Financial Resource Management for the Beneficiaries 9. Soil Sampling Technique and Methodology 10. Benchmarking/Field Tour 11. Value Reorientation & Islamic Culture & Islamic Culture Appreciation Training 12. Training Course on Social Mobilization for IA Officers For Project Management Team 13. Project Management Team Monthly Meeting 14. Mid- and Year-End Review & Planning WS
Participatory Demonstration Farm & Farm Production Input Assistance	28 IA x 30 farmer cooperators x 2 seasons

Source: JICA Survey Team

2) Enhancement of Agriculture Extension Services at Municipality Level

LGUs are responsible to deliver agriculture and fisheries extension services directly to their clientele farmers under the present administrative system in the Philippines. It is, however, widely recognized that the agricultural extension services remain ineffective due to low capability of LGUs in terms both of finance and manpower. In coping with the reality, various DA agencies including ATI, universities and colleges have been involved in providing the extension services directly to farmers on a project basis, like YLTA.

Such shortcut method is not always a good countermeasure considering future sustainable development of the agricultural extension system in the Country. ATI, as a leading national agency of agricultural extension, should incorporate a transition system into the implementation approach, so that LGU extension workers will be able to take over the responsibility for the extension works in the Project area gradually. A strategic and long-term TOT, which will enable LGU extension workers to carry out their duties, is therefore programmed in this agricultural support plan.

2.1) Objective

The objective is to enhance agriculture extension services provided to clientele farmers by LGUs in a timely and efficient manner, based on critical examination of existing farming practices and desires, problems encountered at the farm level and solutions for them.

2.2) Approach

The activity provides a step-wise training including technical and on-the-job trainings to Municipal Agriculturist (MA) and Agricultural Technologists in Cotabato Province and Municipality Agriculture Officer² and Agricultural Technologists in Maguindanao Province, those who are working at municipality level. It targets five municipalities, Carmen, Pikit, Aleosan, Datu Montawal and Pagalungan, under which currently post-filled 42 staff are to be trained in total. In addition to technical matter on rice production, they should also be trained with basic computer skills for data processing and IT based extension.

In line with the training process, on-farm technical handbooks/manuals shall be distributed in order to mitigate the limitations of individual farmers, as well as the agricultural staff working at municipality level. This enables them to refer to the handbooks/manuals for information about farming technology and farm management improvement as the closest starting point in their questioning.

In Philippines, many technical manuals on rice production have been published by several organizations such as ATI, PhilRice, IRRI, universities and colleges, etc. Therefore, contents of the manuals should be evaluated and selected by ATI and the municipal level officers. All the information on technical issues should be supported by photos or graphic drawings both in printed format and electronic ones. After selecting the manuals, ATI must have permission to copy from the copyright owner.

Technically, damage caused by pests and diseases is a serious problem on the rice production in the MMIP area. The baseline survey revealed that the largest number of interviewees, 75% of them, recognize them as a challenging problem; followed by bad/poor transportation road to market/millers (61%) and occurrence of floods or prolonged inundation (30%). Prolonged rainfall in the project area also increases an incidence of fungal diseases like rice blast. Thus, LGU extension workers should be equipped with knowledge, know-how and skills to control pests and diseases particularly on rice farming, so that they can support the farmers in the Project area.

2.3) Activities

Table 4.2.11 shows implementation schedule of this sub component;

² MAOs in Maguindanao Province are staffs of DAF-ARMM and there is always a possibility of the officers' transfer to another Municipality and/or promotion to PAO. However, they are not likely to happen over a long period since they are residing in their assigned municipality according to informal interview with the MAO.

Table 4.2.11 Implementation Schedule of Enhancement of Agriculture Ex. Services at Municipality Level

Activity	2020		2021		2022		2023		2024	
	Dry	Wet	Dry	Wet	Dry	Wet	Dry	Wet	Dry	Wet
Training Needs Assessment										
Provision of Equipment and Materials										
Distribution Manuals										
Technical Trainings										
On-the-job Trainings										
M&E and report making										

Source: JICA Survey Team

2.3.1) Provision of Equipment and Materials

In order to enhance the LGUs extension set-up, the offices should be equipped with necessary equipment including computers, accessories, audio-visual equipment, etc. at municipality level. This supports the officers to collect necessary information in accordance with the farmers' actual needs and keep their activity record and farmers' data, and preparation of extension materials. The following equipment should be installed to the respective municipal offices;

Table 4.2.12 Equipment to be Installed to the Five Municipal Offices

Item	Pikit	Carmen	Aleosan	Datu Montawal	Pagalungan	Total
Desk-top computer	1	1	1	1	1	5
Computer table with chair	1	1	1	1	1	5
Laptop computer	1	1	1	1	1	5
Printer	1	1	1	1	1	5
Internet accessories (modem & router)	1	1	1	1	1	5
Photocopier	1	1	1	1	1	5
Tablet	5	2	1	1	1	10
Overhead projector	1	1	1	1	1	5
UPS	1	1	1	1	1	5

Source: JICA Survey Team

In addition, motorcycles can promote the mobility of officers to the project site and deliver immediate extension services when the farmers encounter a challenge on irrigated rice production. Therefore, the following number of motorcycles are planned to be provided to the offices;

Table 4.2.13 No. of Motorcycles to be provided to the Five Municipal Offices

Province	Municipality	No. of Motorcycles
Cotabato	Pikit	5
	Carmen	2
	Aleosan	1
Maguindanao	Datu Montawal	1
	Pagalungan	1
Total	Total	10

Source: JICA Survey Team

2.3.2) Distribution of Manuals

After being selected by ATI, the manuals are translated into either Tagalog or other local dialect like Maguindanao. Then, ATI prints them and distributes to the municipal level officers in addition to the IA members in the entire MMIP area. The total IA members registered are 6,365 and additional 11 IAs are to be registered or established soon. Since the members are estimated to be more than 8,000 after the registration and establishment, ATI needs 9,000 sets of manuals in total. Besides, 1,000 sets of technology posters relative to rice production should be printed and mounted on walls of the offices or relevant place.

2.3.3) Technical Trainings and On-the-job Trainings

Although training needs assessment is carried out by the officers in order to determine the priority

issues, possible training topics on the agriculture extension are shown in Table 4.2.14. They include year-round and hands-on training on rice production practices, literacy and skills enhancement on computer operation and IT-based technology.

Table 4.2.14 Training Topics for the Agriculture Staff at Municipality Level

No.	Topic	Description	Total Day	No. of Participants
1	Training Needs Assessment	- To determine the priority trainings to be done in accordance with farmers' needs and the staffs weakness	1	42
2	Introduction of Agriculture Extension	- Progress of MMIP and YLTA - Theory of key topics on YLTA such as Palay Check System, Climate Smart Field School (CSFC), SRI (System of Rice Intensification), Integrated Pest Management (IPM), etc.	2	42
3	Technology of Rice Production	- Crop management such as seed quality, land preparation, crop establishment, nutrient and water management, pest and diseases, and post-harvesting - Business management such as accounting, marketing, etc.	5	42
4	Computer Operation and IT-based Technology	- Computer-based extension material preparation - Real time updates on commodity market information - Use of IT-based Information on rice production like videos and manuals, diagnostics tool ¹ for Android mobile developed by IRRI - Use of web-based SNS (e.g. Facebook) as instrument in technology transfer/promotion by creating a scheme for effective delivery	2	42
5	Refresher Training (OJT) 1	- Study Tour to Participatory Demonstration Farm (PDF) to be established by the subcomponent of Technical Assistance for Irrigated Rice Production and seed production area - Analyze on-going problems on the farm - On-site Training on the analyzed problems - If necessary, samples are taken, further analyzed and discussed such as produced rice, rice seed, soil, etc.	4	42
6	Refresher Training (OJT) 2	ditto	4	42

Source: JICA Survey Team

Note: Mobile application/software called Rice Doctor is available on <http://www.knowledgebank.irri.org/decision-tools/rice-doctor> in both English and Tagalog.

3) Development of Seed Production

While the irrigable area in the MMIP I area is 7,173 ha, that in the MMIP II area is maximum 10,536 ha. Theoretically, about 708 ton of seed is required per cropping season because recommended seed requirement is 40 kg per ha for transplanted rice and the entire area of MMIP is 17,709 ha. Direct seeding method, commonly practiced in the area, requires more seed rate which is 80 to 100 kg per ha and needs more than 1,417 tons to 1,771 tons of seed. As Table 4.2.15 shows only 842 bags, equivalent to 34 tons of seeds are currently produced in the relevant municipalities covering the MMIP area.

To meet 708 tons of seeds at least, 151 ha of land needs to be planted for rice seed production. In this regard, rice is a self-pollinating plant and farmers can save rice seed from their produced rice and replant it again at maximum 3 times. After the 3rd time, rice seed should be renewed to avoid cross pollination with other varieties. Therefore, one-third of 151 ha of land or 50 ha, should supply rice seed to the whole MMIP area.

Although there are 22 seed growers and 139 ha of seed production area in Pikit and Carmen Municipality, they produce only 34 tons of seeds in 2017, worth of only 7 ha of the production area. If the area is planted to the maximum, the production should be 639 tons meeting most of the necessary amount of rice seeds. There is big difference of actual production and expected production of rice seed, which has been planted by the current seed growers. Thus, seed production should be further promoted and the planted area within the MMIP area should be expanded accordingly.

**Table 4.2.15 Amount of Rice Seed Produced by Seed Growers
in 2017 in Selected Municipalities of Cotabato Province**

Rice Variety	Midsayap	Pikit	Carmen	Kabacan			TOTAL		
				Local	USM		bag (=40kg)	kg	ton
	CS	CS	CS	CS	CS	RS			
PSB Rc 10	405	0	0	0	0	0	405	16,200	16
PSB Rc 18	200	0	0	0	0	0	200	8,000	8
NSIC Rc 15	0	0	0	0	81	0	81	3,240	3
PSB Rc 82	227	0	0	0	0	0	227	9,080	9
NSIC Rc 122	74	0	0	0	0	0	74	2,960	3
NSIC Rc 128	72	0	0	362	0	0	434	17,360	17
NSIC Rc 158	756	0	100	642	0	0	1,498	59,920	60
NSIC Rc 160	1,589	0	0	100	0	0	1,689	67,560	68
NSIC Rc 222	1,797	0	400	5,898	75	304	8,474	338,960	339
NSIC Rc 224	627	0	0	0	0	0	627	25,080	25
NSIC Rc 226	170	42	300	638	0	0	1,150	46,000	46
NSIC Rc 238	190	0	0	94	45	50	379	15,160	15
NSIC Rc 342	269	0	0	53	0	0	322	12,880	13
NSIC Rc 344	0	0	0	80	0	0	80	3,200	3
NSIC Rc 352	570	0	0	40	0	0	610	24,400	24
NSIC Rc 358	540	0	0	818	93	0	1,451	58,040	58
NSIC Rc 360	241	0	0	0	0	0	241	9,640	10
NSIC Rc 390	150	0	0	0	0	0	150	6,000	6
TOTAL	7,877	42	800	8,725	294	354	18,092	723,680	724

Source: BPI-NSQCS, Midsayap, Cotabato

CS: Certified Seeds RS: Registered Seeds

USM: University of Southern Mindanao at Kabacan in the province of Cotabato. It has about a 60 ha of rice seed production area.

Table 4.2.16 Number and Area of Accredited Seed Growers in the MMIP Area and Nearby Municipalities

Municipality	No. of Seed Growers (Individual and Institution)	Total Area (ha)	Average Size of Area (ha)
Carmen	21	129	6.1
Pikit	1	10	10.0
Sub-total	22	139	6.3
Kabacan	44	577	13.1
Libungan	5	62	12.4
Midsayap	22	250	11.4
Sub-total	71	889	12.5
Total	93	1,028	11.1

Source: BPI-NSQCS - Midsayap, Cotabato

3.1) Objective

This sub-component aims at ensuring availability and reliable supply of healthy rice seed for farmers within the MMIP area. Here, seed should be a recommended variety one and free from seed-borne diseases and meet seed certification standard in the Philippines.

3.2) Approach

This sub-component pursues establishment of community based, meaning IA based, registered or certificated seed production system³ rather than building large-scale seed center producing foundation seeds, since the irrigation systems are still under developed to attain higher crop intensity and have an access road problem to markets. Rice seed production area is established within IAs to be selected by meeting conditions such as accessibility to other farmers and seed inspectors for regular monitoring, well-experienced in irrigated rice production, relatively less damage from waterlogging. In this regard, IAs in the MMIP I should be a candidate for the rice seed production. ATI should be the main implementing body of this sub-component in coordination with BPI-NSQCS and PhilRice, LGUs.

³ Seed certification standard in the Philippines is multi-layered and categorized into four factors; breeder, foundation, registered and certified seed.

The Project should first encourage the aforementioned 22 seed growers to produce more rice seed in their farms. ATI should make a survey of the growers' desire to produce rice seed and potential production volume, and then decide target beneficiaries from the current growers. In addition to them, ATI possibly selects beneficiaries from the farmers in the MMIP I area, those who are interested in, if the current growers cannot meet the target volume of the seed.

This sub-component should take into account a BPI-NSQCS procedure that a farmer becomes an accredited seed grower as following:

- 1) A farmer who wants to become an accredited seed grower undergoes a 5-day training on Basic Rice Seed Production and Certification required by BPI-NSQCS. Protocols on area (minimum of 1 ha), water, seeds and other requirements are discussed during the 5-day training.
- 2) After the training, a farmer expecting to be a seed grower now applies for certification.
- 3) Area validation and other documentary requirements are checked before granting the certification to become a seed grower. If qualified;
- 4) A seed inspector, an agricultural extension workers designated to the position either from office of the municipal agriculturist or office of provincial agriculturist, conducts a series of inspection in the area of an accredited seed grower. It is done two or more times per cropping season, from seeds to be planted until harvesting in coordination with BPI-NSQCS.
- 5) After harvesting rice seed, a sample is collected subject to laboratory analyses. Seed certification standard in the Philippines such as 14% of moisture content, 98% purity, contamination of other varieties, etc. should be met before BPI-NSQCS issues a tag, an indicator that rice seeds are ready for market as inputs to rice farming activity.

3.3) Activities

Table 4.2.17 shows implementation schedule of this sub-component. Although technical supports and monitoring are conducted until the wet season of 2024, inputs supports for the target IAs are carried out on one season, either dry or wet season of 2020. In this regard, this sub-component pursues that the farmer cooperators will be an independent accredited seed grower after one season support from the project.

Table 4.2.17 Implementation Schedule of Development of Seed Production in MMIP

Activity	2020		2021		2021		2023		2024	
	Dry	Wet	Dry	Wet	Dry	Wet	Dry	Wet	Dry	Wet
Selection of IAs and potential farmer cooperators										
5-day seed production training required by BPI-NSQCS										
Provision of machineries, equipment, foundation seeds to be planted										
Support seed registration and certification process										
Support marketing of produced seed to the other farmers										
Regular inspection and monitoring of established seed production areas										
M&E and report making										

Source: JICA Survey Team

3.3.1) Selection of IAs and Potential Farmer Cooperators

ATI selects the number of target seed growers to meet aforementioned 50 ha of the seed production area and the current seed growers are given priority for being selected as the beneficiaries. Here, we assume to select 5 IAs and then 10 growers from each IA; a total of 50 growers (e.g. 22 current seed grower and 28 new seed growers).

3.3.2) Seed Production Training

ATI provides the aforementioned 5-day training to the beneficial seed growers in coordination with BPI-NSQCS. The training contents are expected to cover: 1) outline such as classification of rice seed, recommended and local seed varieties, rice seed production and inspection, 2) seed treatment and nursery management, 3) farming practices in main paddy field, 4) field inspection and removal of off-type, and 5) post-harvest technology. If the current seed growers participated to the same training course before, provided by BPI-NSQCS, advance training should be prepared and provided to them.

3.3.3) Provision of Machineries, Equipment and Foundation Seeds

Table 4.2.18 shows necessary inputs for this sub-component;

Table 4.2.18 Necessary Inputs for Development of Seed Production

Item	Quantity	No. of IA	No. of Farmer	Total
Machinery & Equipment				
Thermometer	1	5	-	10
Hand Tractor with Trailer	1	5	-	5
Floating Turtle/Rotavator	1	5	-	5
Rice Reaper	1	5	-	5
Rice Thresher	1	5	-	5
Dryer	1	5	-	5
Rice moisture meter, portable	1	5	-	5
Material				
Urea for seed treatment	1 bags	5	10	50 bags
Net bag	50 bags	5	10	2,500 bag
Foundation seed	50 kg	5	10	2,500 kg
Laminated sacks	100 bags	5	10	5,000 bag
Fertilizer	3 or 4 bags	5	10	200 bag

Source: JICA Survey Team

3.3.4) Monitoring of Established Seed Production Areas

Based on the procedure specified by BPI-NSQCS, the agriculture officers who work at five municipalities conduct a series of inspection on the paddy field with the support of ATI and BPI-NSQCS. This activity can be integrated into the training content of “Enhancement of Agriculture Extension Services at Municipality Level”.

3.3.5) Support Monitoring, Registration and Certification Process by BPI-NSQCS

BPI-NSQCS has existing laboratory facilities located within the PhilRice compound at Midsayap in the province of Cotabato which is responsible for conducting analyses of submitted samples by accredited growers. Likewise, it conducts seed production training, seed production area monitoring, in coordination with ATI and the seed inspectors from each municipality, registration and certification issuance. Inventory of seed laboratory equipment in the Bureau shows the following necessary items to enhance the measuring of seed quality;

Table 4.2.19 Necessary Items for Seed Inspections by BPI-NSQCS

Item	Quantity
Automatic Seed Counter	3
Laminar Flow (Airflow fume hood for laboratory)	1
OMAX 3MP Camera 40X2000x (Digital Biological Compound Binocular)	1
Digital Handheld GPS (Garmin Oregon)	3
Total	8

Source: JICA Survey Team

3.3.6) Support for Marketing of Produced Seed to Other Farmers

After the produced rice seed tagged by BPI-NSQCS, it expects to be marketed to other farmers within the MMIP area. Any excess would be marketed outside the project area. Following the government set

price for the registered and certified seeds, ATI technically supports marketing of the seed produced by the growers.

4.2.4 Further Recommendation for Agriculture Development in the MMIP Area

1) Crop Diversification

Crop diversification is another strategy to increase total productivity of agriculture. Progress of the crop diversification is still very minimal in and around the Project area. In fact, high value and market potential commodities could, at first, be promoted in upland areas while in lowland areas rice cultivation would still prevail due to the natural condition preferable for paddy cultivation but not for high value crops e.g. vegetables.

As the government envisages in the Philippine Development Plan 2017-2022, crop diversification needs a comprehensive approach including development of promising crops, enhancement of new form of linkages between farmers and agro-based enterprises, promotion of community-based enterprises, etc. Only one project will not be able to handle all expected outputs as they are very cross-sectional and complicated. A LGU-centered decentralized approach would be ideal for addressing the issues properly, provided that LGUs are equipped with sufficient funds and manpower.

A realistic approach of the crop diversification in the area could only be the following initiatives;

- ✓ Introduction of early ripening crops suitable after the 2-time rice cropping such as pulses upon the establishment of high-yielding and reliable rice farming on sustainable basis in future, and upon development of a system of technology to shorten the rice crop seasons by introduction of early maturing varieties, farm mechanization, advanced direct-sowing⁴, etc.
- ✓ Introduction of vegetable crops to home gardens for promoting a balanced diet of farm households, as well as for generating additional income, especially for housewives, when they are blessed with surplus of the production.

In order to initiate crop diversification, a supporting component of home gardening should be considered. As mentioned above, harvested crops contribute to improving balanced diet of farm households in the Project area. Farmers in the area, especially women farmers, will be able to expect additional income from the crops when they are blessed with surplus of the production, even though the amount is small. Farmers will be ready to start growing various kinds of crops gradually after having familiarized such home gardening.

2) Agriculture Mechanization

The agricultural development strategy of the Philippine Development Plan 2017-2022 stresses agricultural mechanization as an important tool to attain improvement of the agricultural productivity. The plan expresses that the government will encourage adoption of farm machinery and equipment to reduce production costs of rice, as well as encouraging custom hiring and machine pooling to provide alternative livelihood to low-skilled workers in rural areas. The farm mechanization will be accelerated by private service providers as envisaged in the plan. The plan states that the following government supporting measures to facilitate the use of appropriate farm machinery and equipment:

- ✓ Provision of fund to local manufacturers and assemblers,
- ✓ Intensified information, education & communication activities on available local machinery, and
- ✓ Provision of proper training and certification for machine operation

⁴ Direct-sowing of rice is becoming a spotlight as a low-cost and labor-saving technology in many countries. Various research works focus on developing an advanced direct-sowing technology with high and stable yielding, as well as with low-costs.

In the Project site, it is noteworthy that out-migration of people from rural to urban centers results in scarcity of manpower working in the farms. Especially, once the prospective irrigable area of MMIP II is fully developed and operational, a problem on availability of farm workers is expected to rise. Irrigated rice production is more labor intensive than the current livelihood activities of farmers in MMIP II areas, e.g. rain-fed rice, corn farming and fisheries.

As in the results of Household Economic Survey conducted by the JICA team, very limited numbers of farmers own agriculture machineries in the MSA and almost none of them own the machineries in the LMSA. Besides, based on an inventory survey of agriculture machines in the MMIP area (Table 4.2.20) and capacity of each machine, progress of agricultural mechanization in the area is estimated. As Table 4.2.21 shows, the irrigated area still requires a significant number of pre- and post-harvest machineries to be fully mechanized. Compared to the machines for land preparation, the number of harvesting and post-harvesting machines are very small in the MMIP area. An insufficient number of them would result in reduction of production, post-harvest losses, and poor quality of rice paddy.

Table 4.2.20 Inventory of Agriculture Machines in the MMIP area

Particular	No. of Barangay	Irrigable Area (ha)	Expected Production (ton) in dry season	Power Tiller/ Hand Tractor	Floating Tiller	Rice Reaper	Rice Thresher	Solar Dryer	Rice Mill
MMIP I									
MSA	7	5,562	25,585	14	72	2	31	36	4
UMSA	6	1,611	7,411	20	10	2	14	8	3
Sub-total	13	7,173	32,996	34	82	4	45	44	7
MMIP II									
UMSA	11	2,958	13,607	59	73	0	51	48	9
PESA	2	998	4,591	5	6	0	5	1	1
LMSA (Case-1)	27	3,688	16,965	31	35	0	26	52	13
Sub-total	40	7,644	35,162	95	114	0	82	101	23

Source: 5 Municipalities

Table 4.2.21 Capacity of Agriculture Machines and Estimated Progress (%) of Agricultural Mechanization

Particular	Power Tiller/ Hand Tractor	Floating Tiller	Rice Reaper	Rice Thresher	Solar Dryer	Rice Mill
Capacity of Agricultural Machines	2 ha/ day	1.8 ha/ day	0.33 ha/ day	4 ton/ day	5 ton/ batch	6 ton/ day
Capacity per month*	60 ha	54 ha	10 ha	120 ton	75 ton	180 ton
Area & Volume to be Covered by Current Agriculture Machines						
MMIP I	2,040 ha	4,428 ha	40 ha	5,400 ton	3,300 ton	1,260 ton
MMIP II	5,700 ha	6,156 ha	0 ha	9,840 ton	7,575 ton	4,140 ton
Estimated Progress (%) of Agricultural Mechanization						
MMIP I (%)	28%	62%	1%	16%	10%	4%
MMIP II (%)	75%	81%	0%	28%	22%	12%

Source: 5 Municipalities & JICA survey Team

Note: One month is assumed to be necessary for each farming practice (e.g. preparation of land, harvesting, etc.).

YLTA had agricultural machinery intervention, yet it was limited to just leasing a set of floating tiller, rotavator, hand tractor with trailer, thresher and welding machine to the respective target IAs on the condition that it is returned after a year of utilization. A government project should pay much attention to the promotion of farm mechanization services rather than leasing farm machinery directly to farmers or farmers' group e.g. IA, not as conducted in YLTA. In case of anxious demand for farm machinery from IA members, one of alternative solution is to allow IAs to procure farm machinery and be a reliable provider of farm mechanization services. Appendix IV describes a detailed plan of "Enhancement of Agriculture Mechanization" particularly in LMSA, which is proposed by JICA survey Team.

4.3 Irrigation and Drainage Improvement

4.3.1 Irrigation Water Reliability

Maridagao river is the water source for the irrigation systems of MMIP wherein a diversion dam was constructed at Barangay Kibnes, Carmen, Cotabato. This section explores the sufficiency of the water volume from the river to irrigate the entire planned beneficiary area of MMIP I and MMIP II. The amount of water to be diverted from the river was determined through the feasibility study (FS) concluded long time back in June 1986. The FS proposed that the river discharge would be gauged at the Tinutulan station around 10 km downstream from the current diversion point, however the said station was operational only between 1960 and 1972.

Since the data of water discharge from the Maridagao river are not available, except for the above mentioned period of 1960-1972, the river runoff over a long period was estimated by interpolating the relationship between rainfalls and river runoff. Rainfall data from the Municipality of Midsayap recorded during 1979-2014 and the rainfall data estimated based on the satellite images of catchment area during the same period were employed (see section 2.1.5 Hydrology and Future Irrigation Water Availability). River runoff was also estimated using the 1956-2014 period of two rainfall data.

A drought frequency analysis is now carried out based on the estimated river runoff for a long time. A non-exceedance probability analysis in Iwai method was also conducted and results showed the annual runoff probabilities of 50%, 20%, 10% and 5% were estimated at 2,061 MCM, 1,576 MCM, 1,341 MCM and 1,156 MCM, respectively. The design reliability of the MMIP was decided at 20% during the FS, which means the reliability of the irrigation system counts at 80%. This implies that the designed irrigable area can benefit from irrigation water without any shortage of water for 8 years over a 10-year period.

Table 4.3.1 Return Periods of Maridagao River Runoff at the Diversion Point

Return Period	Probability	Annual Runoff (MCM)	Ratio	Remarks
2	0.50	2,061	0.983	
3	0.33	1,807	0.862	
4	0.25	1,669	0.796	
5	0.20	1,576	0.752	Design reliability
8	0.13	1,410	0.672	
10	0.10	1,341	0.640	
15	0.07	1,229	0.586	
20	0.05	1,156	0.551	
25	0.04	1,104	0.526	
30	0.03	1,063	0.507	
40	0.03	1,002	0.478	
50	0.02	957	0.457	
60	0.02	922	0.440	
80	0.01	869	0.414	
100	0.01	830	0.396	
Average		2,097		

Source: JICA Survey Team, MMIP FS report (June 1986), NCEP of US for long-term rainfall

As shown in table above, the ratio between the annual runoff with 80% reliability and the average annual runoff is computed at 0.752. By applying this ratio, the average runoffs estimated on a 10-day basis at the diversion point are proportionally reduced to those with 80% of reliability as illustrated in Figure 4.3.1. The figure shows the transition of both the average run-off on a 10-day basis and that with 80% of reliability. On the other hand, a horizontal red line at the value of 31.88 cum/s shows the overall design discharge required at the diversion point for all the MMIP I and MMIP II irrigable area, namely, 17,709 ha. The pre-conditions for this analysis are:

- ✓ MMIP I & MMIP II design gross irrigation duty: 1.8 l/s/ha¹
- ✓ MMIP I & MMIP II Irrigation Area: 17,709 ha (7,173 + 10.536)
- ✓ Total design discharge: 31.88 cum/s (1.8 / 1000 x 17,709 ha)

According to Figure 4.3.1, there are periods when runoffs with 80% of reliability remain below the design discharge of 31.88 cum/s: they are the 2nd 10-day period of February to 3rd 10-day period of March (the lowest runoffs of 29.4 cum/s was marked at the 1st 10-day period of March). However, the chart shows only the runoff and the design discharge, and it does not consider effect of rainfalls.




Figure 4.3.1 Runoff at Diversion Point for Average and 80% Reliability

Source: JICA Survey Team

This is because the total volume of actual rainfall cannot be simply added to the runoffs, since part of rainfall would be required by crops. Furthermore, the 31.88 cum/s is the water requirement at maximum, which could be marked during dry seasons when land soaking is high and rice is flowering (in a latter growing stage). Therefore, if the period of lowest runoffs does not correspond to the period when the water requirement reaches at its maximum, the system reliability is still secured.

Figure 4.3.2 shows the rainfall on Pikit area estimated based on satellite images on a 10-day basis for the period of 1973-2013. The chart shows average 10-day period rainfall data, 10-day period rainfall data of 80% of probability, and effective rainfall data. The rainfall data of 80% of probability were estimated by applying the following formula.

- ✓ Effective rainfall: $he=0.75 \times (h-5)$ mm, where h: 10-day rainfall (referred to the FS report)

The effective rainfall data marked its lowest record at the 3rd 10-day period of February, at 2.5 mm/10-day only. By applying the following formula, how many days it would be required to reach 0.51 cum/s over the whole irrigable area of 17,709ha, when the rainfall remains at 2.5 mm/10-day period effective rainfall: $2.5 / 1,000 \times 17,709 \times 10,000 / 86,400 / 10$.




Figure 4.3.2 Average, 80% Probability and Effective Rainfalls (Pikit)

Source: JICA Survey Team

At the highest of dry season, from late January to mid-May except the 3rd 10-day period of February, still effective rain can reach around

¹ Design gross irrigation duty of 1.8 l/s/ha was adopted from the one prepared by the Feasibility Study.

5mm/10-day-period. Therefore, during this period, except for the 3rd 10-day period of February, approximately additional 1 cum/s, generated from 5 mm/10-day-period of effective rainfall, can be expected in effective runoff.

Further, Table 4.3.2 shows the proposed cropping pattern and required irrigation water, required diversion runoff, and also surplus or deficit estimated with the following conditions²:

- ✓ Cropping patterns: rice (May-October) – rice (October-March)
- ✓ Potential evapotranspiration: estimated by application of modified Penman method with use of PAGASA agro-meteorological station data available for the period of 1969-1988 (as the FS, 1986 estimated.)
- ✓ Deep percolation: 2.8 mm/day (as the FS, 1986 estimated.)
- ✓ Land soaking + ponding: 84 mm + 20 mm (as the FS, 1986 estimated.)
- ✓ Irrigation efficiency: 51% (80% for delivery, 80% for distribution, 80% for on-farm, as the FS, 1986 estimated.)

Table 4.3.2 Cropping Pattern and Irrigation Water Requirement Computation

MONTH	MAY			JUN			JUL			AUG			SEP			OCT			NOV			DEC			JAN			FEB			MAR			APR		
DECADE	1	2	3	1	2	3	1	2	3	1	2	3	1	2	3	1	2	3	1	2	3	1	2	3	1	2	3	1	2	3	1	2	3	1	2	3
RICE-RICE CROPPING																																				
WATER BALANCE																																				
Evaporation,mm	47	47	51	43	43	43	44	44	48	43	43	47	45	45	45	45	50	40	40	40	35	35	39	41	41	45	46	46	37	54	54	59	53	53	53	
Land Soaking/Ponding,mm	14	22	28	27	10	3	0	0	0	0	0	0	0	0	6	21	24	28	19	5	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Evapotranspiration,mm	6	18	34	40	45	46	48	48	53	47	47	50	35	23	13	14	24	40	41	43	44	39	39	43	45	45	41	29	16	4	0	0	0	0	0	
Deep Percolation,mm	4	11	20	25	28	28	28	28	31	28	28	29	20	13	7	8	15	25	28	28	28	28	28	31	28	28	25	16	9	2	0	0	0	0	0	
Crop Water Req't,mm	24	51	82	92	83	77	76	76	84	75	75	79	55	36	26	43	63	93	88	76	73	67	67	74	73	73	66	45	25	6	0	0	0	0	0	
Effective Rainfall,mm	5.3	6.2	8.5	7.2	12.4	13.5	15.7	16.5	16.1	11.5	9.8	13.3	9.4	13.9	10.5	9.5	9.3	13.0	9.9	8.1	17.7	10.5	11.5	17.0	12.1	9.2	6.1	6.9	5.9	2.5	5.5	6.4	4.5	6.3	4.9	4.7
Crop Irrig Req't,mm	18.7	44.8	73.5	84.8	70.6	63.5	60.3	59.5	67.9	63.5	65.2	65.7	45.6	22.1	15.5	33.5	53.7	80	78.1	67.9	55.3	56.5	55.5	57	60.9	63.8	59.9	38.1	19.1	3.52	0	0	0	0	0	
Overall Efficiency,%	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51	51
Diversion Req't,mm	36.7	87.9	144	166	138	124	118	117	133	124	128	129	89.5	43.3	30.4	65.7	105	157	153	133	108	111	109	112	119	125	117	74.8	37.4	6.9	0	0	0	0	0	
Water Duty, l/s/ha	0.43	1.02	1.52	1.93	1.60	1.44	1.37	1.35	1.40	1.44	1.48	1.36	1.04	0.50	0.35	0.76	1.22	1.65	1.77	1.54	1.26	1.26	1.18	1.38	1.45	1.23	0.87	0.43	0.10	0.00	0.00	0.00	0.00	0.00	0.00	
Diversion Req't (MCM)	6.51	15.6	23.2	29.5	24.5	22	20.8	20.6	21.4	22	22.6	20.7	35.8	7.67	5.38	11.6	18.7	25.3	27.1	23.6	19.2	19.6	19.3	18	21.1	22.2	18.9	13.2	6.63	1.53	0	0	0	0	0	
Streamflow (MCM)	48.29	53.69	57.84	60.19	62.62	58.37	56.08	52.60	52.02	48.87	47.69	48.75	51.15	51.55	52.74	53.13	56.69	57.02	53.83	46.72	40.88	37.73	33.87	29.36	27.58	26.98	28.30	28.04	26.98	26.39	25.36	26.21	26.03	28.30	32.95	40.88
Surplus/Deficit (MCM)	41.79	38.12	34.63	30.74	38.10	36.32	35.15	31.95	30.57	26.83	25.06	28.01	35.30	43.88	47.37	41.51	38.03	31.75	26.70	23.13	21.67	18.13	14.59	11.36	6.43	4.83	9.41	14.80	20.35	24.86	25.36	26.21	26.03	28.30	32.95	40.88

NOTE: 1 First Cropping Area = 17,709 hectares, Second Cropping Area = 17,709 hectares
 2 Number of days staggered for Land soaking and land preparation = 40 days (104mm)
 3 Percolation Rate used = 2.8 mm/day(F/S,1986)
 4 Effective Rainfall at 80 percent dependable rainfall by frequency analysis

Source: JICA Survey Team

According to the computation in table above, the peak of the irrigation duty comes in the 1st 10-day period of June at 1.93 l/s/ha, which is, in fact, bigger than the estimate of the feasibility study at 1.8 l/s/ha. The critical period, from the view point of the availability of diversion discharge, is the 2nd 10-day period of January, leaving only 4.83 MCM/10-day-period as water discharge in the river. This




Figure 4.3.3 Diversion Requirement and 80% Reliable Runoff

Source: JICA Survey Team

² “Potential evapotranspiration”, “Deep percolation”, “Land soaking + ponding” and “Irrigation efficiency” were adopted from the one prepared by the Feasibility Study. Field tests for evaluating these numbers are not planned in this survey.

4.83 MCM/10-day-period discharge is equivalent to 5.59 cum/s ($4.83 \times 1,000,000 / 10 / 86,400$), which seems still enough for the requirement of downstream. The diversion requirement on a 10-day basis and runoffs with 80% of reliability are summarized in Figure 4.3.3. The chart further implies that the river runoff could still meet the diversion requirement even if the second cropping which is to be started from October, is delayed by about one month.

4.3.2 Development Direction for Lower Malitubog Service Area in MMIP II

A large part of the Lower Malitubog Service Area (LMSA) is inundated during the rainy season. The inundation in this area needs mitigation such as construction of ring dike and protection dike, lest its condition will be same as the present. Therefore, target irrigable area in LMSA shall be considered based on the inundation condition. And then the project component shall be planned based on the target irrigable area.

1) Irrigable Area in LMSA based on the satellite image analysis

The satellite image analysis in Figure 4.3.4, shows the inundated area in LMSA during the rainy season. Table 4.3.3 shows the comparison of the irrigable areas in LMSA with and without the construction of dikes. Based on the data presented, if the dikes are not constructed, 44% of gross Service Area would be inundated. In this case, it is impossible to develop 6,590 ha of




Figure 4.3.4 Inundated Area in LMSA during the Rainy Seasons

Data Resource: High-resolution mapping of global surface water and its long-term changes (Jean-François Pekel et al., Nature 540, 418-422, 15 December 2016)

Source: JICA Study Team

all the irrigable area in LMSA, and only 3,688 ha (about 56 % of planned irrigable area) will be available for development. Hence, the remaining portion for development from 2019, would only be 1,001 ha, which is short of 1,132 ha unless the planned dikes will be constructed.

Table 4.3.3 Comparison of the Irrigated Areas in LMSA with and without the Construction of the Dikes

Fiscal Year for work	Irrigable Area (ha)	Present Condition						Rate of Inundation (%)	Irrigable area (ha)	
		Rainy Season (ha)			Dry Season (ha)				With dikes	Without dikes
		Total	Paddy	Maize	Total	Paddy	Maize			
Whole	6,590	1,454	367	1,087	1,252	457	795	44.0	6,590	3,688
2015	1,303	272	48	224	194	11	183	10.0	1,303	1,173
2016	1,736	323	111	212	372	154	218	46.5	1,736	929
2017-18	1,418	313	77	236	229	139	91	55.3	1,418	634
ODA	2,133	546	131	415	457	154	303	53.1	2,133	1,001

Base drawing: NIA PMO of MMIP-2

Source: JICA study team

Figure 4.3.5 shows the locations of the major Project Components in LMSA. Since the dikes will not be constructed, some portions of the irrigation canals will not have to be constructed. Nevertheless, inundated areas can be irrigated during the dry seasons with the construction of all the planned irrigation canals. In this case however, the countermeasures for possible damage of irrigation canals that are easily coursed by flood is necessary such as; raising height of canal embankment, slope protection of embankment, and construction of the concrete flume canal at end portion of lateral canals instead of the earth canal.



A panoramic view of LMSA lowland part from Punoi Barangay toward the Pulangi river. Without an embankment, irrigated agriculture in the rainy season in this area is impossible, and 2,902 ha of irrigable area will be lost in LMSA.

Accordingly, the project cost shall also be increased to keep the original planned irrigable area of 6,590 ha during dry season. In addition, the possibility of damaged farm ditches and farm drainages in the inundated area could result to high maintenance costs every year after the rainy season.

Therefore, the project shall select one from two cases, namely **Case-1**: target area is within the upper limits of the LMSA, constructing parts of the irrigation canals and other appurtenant facilities which are above the broken line (Figure 4.3.5), and **Case-2**: target area is all of LMSA constructing all irrigation canals and other component facilities .




Figure 4.3.5 Locations of the Remaining Project Components to be Constructed after 2019

Source: JICA study team

Base drawing: NIA PMO of MMIP II

Note: Blue color is ongoing construction; red color is still for construction as of June 2017.

2) Irrigable Area in LMSA based on the result of Vulnerability Assessment for Flooding in MMIP II conducted by NIA PMO

After a severe flood in 2009, NIA conducted a survey in 2010 on the assessment of impact of the past floods within the MMIP I and MMIP II areas. The survey was carried out to the residents of the 49 Barangays within MMIP area to confirm flood information such as frequency of flood occurrence, depth of flood, flooding period, among others. GPS coordinates of the survey locations were also collected. The flooded areas were categorized based on the survey results, as shown in Figure 4.3.6.

Table 4.3.4 shows the distribution of flooded area according to depth of submergence on the total net irrigable area. It should be noted that high flooded area such as wetland, marsh, or waterlogged located in each Service Area was already excluded in the net irrigable area. In this data, it shows that Lower Malitubog Service Area has the highest record of flooded area with about 5,720 ha or 87% inundated ranging from very low to low flood. Only 870 ha are safe from flood.




Figure 4.3.6 Flooded Area Affected based on the Vulnerability Assessment conducted in 2010

Source: Vulnerability Assessment for Flooding in MMIP II

Table 4.3.4 Flooded Status of Irrigable Areas

Flood Status	Color code	Service net area (ha)					Total
		MSA	UMSA(1)	UMSA(2)	LMSA	PESA	
No flood	Green	4,362	853	1,736	870	200	8,021
Sub-total		4,362	853	1,736	870	200	8,021
% of area		78%	53%	79%	13%	20%	47%
Very low flood	Light pink	360	758	470	2,940	250	4,778
Low flood	Pink	230	0	0	2,780	538	3,548
Very low flood to high flood	Yellow	610	0	0	0	0	610
Sub-total		1,200	758	470	5,720	788	8,936
% of area		22%	47%	21%	87%	80%	53%
Total		5,562	1,611	2,206	6,590	988	16,957

Source: Vulnerability Assessment for Flooding in MMIP II

3) Target service area to be developed and irrigable area in rainy season

The 870 ha, which is non-flooded area of LMSA, is targeted as irrigable area. On one hand, the 2,940 ha flooded area (with 10 - 50 cm flood depth) is also targeted as possible irrigable area. Magnitude of damage of paddy by inundation varies with the timing, duration and depth. Figure 4.3.7 shows the estimated paddy production loss by inundation. From this, it can be said that the booting period receives damages the most. If rice is submerged 2 days, production loss would reach as much as 80%.

The flooding period continues more than 3 days in half of Barangays in the project area according to the interviews conducted under Vulnerability Assessment for Flooding. Taking into account the fact that the planted rice would grow to 100 cm or more at the booting period and the flooding period in the project site, the allowable inundation depth can be set at 50 cm in order to prevent the damage mainly in the booting period. Accordingly, the 2,940 ha with flood water depth of 10 - 50 cm can/should be included in the target area for irrigation. However, flood water beyond the 50 cm would cause certain damage to the crop, whereby reducing the production. Thus, the target service areas to be developed and irrigable areas in dry & rainy season are set as shown in Table 4.3.5.




Figure 4.3.7 Estimated losses on Paddy Production by Inundation

Source: Engineering Manual for Irrigation & Drainage (Drainage)




Figure 4.3.8 Growing Stage of Rice

Table 4.3.5 Target Service Area to be Developed and Irrigable Area in Dry & Rainy Season

Category	Case-1	Case-2	Remarks
Target Developed service area	3,688 ha	6,590 ha	
Non-submerged area by flood	870 ha	870 ha	Target irrigable area in rainy season
Flooded area of 0.1 to 0.5 m	1,940 ha	2,940 ha	Including in target irrigable area in rainy season. But this area will be affected by flood.
Flooded area of 0.5 to 1.0 m	878 ha	2,780 ha	Excluded from target irrigable area of rainy season.

Case-1: target area is part of LMSA with constructing the part of the irrigation canals and all drainage system

Case-2: target area is all LMSA with constructing all irrigation canals and drainage canals.

Source: JICA Survey Team

4.3.3 Irrigation Development Component

The Main Supply Canal for the Upper and Lower Malitubog Service Areas is designated as Right Main Canal No. 1 (RMC-1) which starts from the outlet of the siphon crossing the Malitubog River. The facilities were constructed during the implementation of MMIP I. RMC-1 extends southwestward to UMSA. RMC-1, branches out at Sta. 12+554 into RMC-1 Extension No.1 (RMC-1 EXT-1), which traverses south to the LMSA.




Figure 4.3.9 Plan of Irrigation Canal System for LMSA

Source: NIA-PMO

The irrigation canal system for LMSA consists of 2 main canals, which both branch out from RMC-1 EXT-1, namely Main Canal No.2 (MC-2) and Main Canal No.3 (MC-3). The two main canals further branch out to 31 lateral canals for the irrigation of 6,590 ha. The total length of canals arrives at 107.3 km, where 34.2 km is covered by the main canals and about 84.5 km is covered by the lateral canals. The main canals will be concrete while laterals will be earth canals.

MC-2 will convey irrigation water for the eastern portion of the Service Area of about 3,224 ha as planned in the original proposal. Several Lateral Canals are off-taking from Main Canal No. 2 designated as follows: Lateral A; B, C, D with its sub-Laterals D-1, D-2 and D-3, Lateral E, F and G. MC-2 will end at the head gates of Laterals F and G for the total length of 22.3 km.

On the other hand, MC-3 will transport irrigation water for the middle and western portions of LMSA which is about 4,336 ha. Several Lateral Canals are off-taking from the MC-3 designated as follows: Lateral H with its sub-Laterals H-1, H-2, H-3 and H-4; Lateral I, J, K, Lateral L with sub-Laterals L-1 and L-2; Lateral M; Lateral N with sub-Lateral N-1 and N-2; Lateral O with its sub-Laterals O-1, O1-1,

O-2 and O-3 and Lateral P. Main Canal No. 3 will end at the head-gates of Lateral O and Lateral P with the total length of 11.4 km.

In case of no dike construction, all or parts of irrigated areas covered by the Lateral canals D, D-3, E, F, G, J, K, L, L-1, N, N-2, O, O-1, O-1-1, O-2, and O3 will be inundated during rainy season. Accordingly, these canals will totally or partially not form part of the project component as in **Case-1**. In this scenario, the length of main canal reduces to 23.0 km from 34.2 km, and the length of lateral canals reduces to 57.8 km from 84.5 km, and then total length of canals reduces to 69.4 km from 107.3 km.


Regarding the remaining area to be constructed after 2019, target canal is MC-2 of 14,109 m from Sta. 8+680 to Sta. 22+279, and Lateral canals C, D, D-1, D-2, D-3, E, F and G. The total length of lateral canals reaches to 22,589 m. In case of no dike construction, irrigated area covered by Lateral D-3, E, F, G and downstream portion of irrigated area covered by Lateral D will be inundated during rainy season. Accordingly target canal for the construction are the MC-2 of 2,920 m from Sta. St.8+680 to Sta. 11+600, and Lateral canals C of 1,677 m, D of 3,820 m, D-1 of 1,299 m, D-2 of 2,250m, and thus total length of lateral canals reduced to 11,966 m.

Table 4.3.6 List of Irrigation Canals and Irrigable Area in LMSA

No	Canal	Case-1		Case-2		Difference		Remarks
		Canal length (m)	Irrigable area (ha)	Canal length (m)	Irrigable area (ha)	Canal length (m)	Irrigable area (ha)	
1-1	RMC-2(~Sta. 8+680)	8,680	768	8,680	768	0	0	On going
1-2	RMC-2(Sta.8+660~)	2,920	162	14,109	796	11,189	634	Remaining
2	RMC-3(~Sta.11+386)	11,386	464	11,386	464	0	0	On going
3	LATERAL A	4,442	251	4,442	251	0	0	On going
4	LATERAL B	1,369	96	1,369	96	0	0	On going
5	LATERAL C	1,677	101	1,677	101	0	0	Remaining
6	LATERAL D	3,820	259	6,341	419	2,521	160	Remaining
7	LATERAL D-1	1,299	67	1,299	67	0	0	Remaining
8	LATERAL D-2	2,250	226	2,250	226	0	0	Remaining
9	LATERAL D-3	0	0	2,288	194	2,288	194	Remaining
10	LATERAL E	0	0	1,948	121	1,948	121	Remaining
11	LATERAL F	0	0	1,990	214	1,990	214	Remaining
12	LATERAL G	0	0	2,653	134	2,653	134	Remaining
13	LATERAL H	5,987	382	5,987	382	0	0	On going
14	LATERAL H-1	3,037	168	3,037	168	0	0	On going
15	LATERAL H-2	1,248	126	1,248	126	0	0	On going
16	LATERAL H-3	3,007	184	3,007	184	0	0	On going
17	LATERAL H-4	1,606	72	1,606	72	0	0	On going
18	LATERAL I	1,648	76	1,648	76	0	0	On going
19	LATERAL J	1,200	30	2,849	193	1,649	163	On going
20	LATERAL K	1,300	34	2,302	197	1,002	163	On going
21	LATERAL L	2,360	43	2,360	370	0	327	On going
22	LATERAL L-1	1,000	31	2,114	155	1,114	124	On going
23	LATERAL M	1,702	83	1,702	83	0	0	On going
24	LATERAL N	2,500	38	3,510	240	1,010	202	On going
26	LATERAL N-1	1,120	63	1,120	63	0	0	On going
27	LATERAL N-2	1,000	28	1,921	114	921	86	On going
28	LATERAL O	1,400	27	4,542	214	3,142	187	On going
29	LATERAL O-1	0	0	2,320	247	2,320	247	On going
30	LATERAL O1-1	0	0	1,077	88	1,077	88	On going
31	LATERAL O-2	0	0	1,210	105	1,210	105	On going
32	LATERAL O-3	0	0	1,794	80	1,794	80	On going
33	LATERAL P	1,488	146	1,488	146	0	0	On going
	Total	69,446	3,925	107,274	7,154	37,828	3,229	
	Total (on going portion)	57,480	3,110	72,719	4,882	15,239	1,772	
	Total (Reaming portion)	11,966	815	34,555	2,272	22,589	1,457	

Source: NIA PMO of MMIP II

Note: **Case-1** Some portions of canals and appurtenant facilities will not be constructed **Case-2** All facilities will be constructed as planned.



Station		Q	V	A	b	d	D	Dc	R	TR	TL	Ss	S	n
from	to	m ³ /s	m/s	m	m	m	m	m	m	m	m			
0+000	1+867	5.80	0.92	6.29	2.80	1.47	2.10	1.80	0.90	4.00	2.00	1.0	0.00025	0.0016
1+867	4+911	5.26	0.90	5.83	2.60	1.44	2.00	1.70	0.87	4.00	2.00	1.0	0.00025	0.0016
4+911	9+018	5.06	0.89	5.65	2.50	1.40	2.00	1.70	0.86	4.00	2.00	1.0	0.00025	0.0016
9+018	11+586	4.84	0.88	5.47	2.50	1.40	2.00	1.70	0.86	4.00	2.00	1.0	0.00025	0.0016
11+586	17+198	3.31	0.86	3.85	2.10	1.17	1.70	1.50	0.71	4.00	2.00	1.0	0.00030	0.0016
17+198	22+789	3.05	0.84	3.61	2.00	1.15	1.60	1.40	0.69	4.00	2.00	1.0	0.00030	0.0016

Source: NIA PMO of MMIP II

Note: Q: Discharge, V: Velocity, A: Flow area, b: Canal bed width, d: water depth, D: canal depth, TR: Width of right canal bank, TL: Width of left canal bank, Ss: Slope of canal side slope, S: Slope of canal, n: Coefficient of friction

Figure 4.3.10 Typical Cross section of Canal and Elements of Main Canal MC-2



This picture shows portion of MC-3 at the diversion point from RMC-1 EXT-1. The height of canal embankment at this point is about 8.5m to convey the irrigation water to its final section that is 22.8 km away.



Concrete lining is planned for main canals. Picture shows concrete lining of RMC-1 EXT-1

4.3.4 Drainage Component

All the drainage canals should be constructed to improve the drainage system in the LMSA which will be beneficial not only to the residents and farmers within the irrigated area but also to those within the inundated area enabling the farmers to immediately start the cropping once rainy season ends. However, since the elevation of most parts of LMSA is lower than that of Pulangi river, the drainage facilities with flap gates should be considered to prevent back flow of water at connection point to the Pulangi river.

There are many streams from which flood water comes into LMSA during rainy season while out of which inland flooding goes during low water period for the Pulangi river. To prevent such back-water flooding coming from the Pulangi river into LMSA, drainage sluice should be considered to install all along the natural streams as well as on the man-made drainages existent on the right bank of Pulangi river. Such drainage sluice should be with flap gate, which stops flood water coming into LMSA while releases inland flood water according to the water levels in and out of the LMSA.

As shown in Figure 4.3.11 and Table 4.3.7, the drainage canal system for LMSA consists of 11 main drainage canals and 31 lateral drainage canals to handle excess rainfall in the Service Area. Total length of drainage canals is 75.8 km; 27.9 km belongs to main drainage canals, 24.7 km for lateral drainages, 14.7 km Façade drain, and 8.5 km Kalawag creek.

The eastern section of LMSA has 3 Main Drainage Canals, designated as MDC-A, MDC-B and MDC-C. Four (4) lateral drainage canals discharge into MDC-A. The final outfall of MDC-A is the Pulangi river at the side of Barangay, Raja Muda. There are four (4) lateral drainage canals discharging

into MDC-B which outfalls to the Façade drain. MDC-C, which connects with three (3) drain canals, also discharges drain water to the Façade drain. The Façade drain is originally planned to be constructed with the proposed Ring Dike along the natural depression.




Figure 4.3.11 Plan of Drainage Canal System for LMSA

Source: NIA-PMO, JICA Survey Team

The middle and western portions of LMSA have seven (7) main drainage canals designated as MDC-D, MDC-E, MDC-F, MDC-G, MDC-H, MDC-I, MDC-J and MDC-K. Two (2) of the seven (7) main drainage canals have lateral drainage canals namely MDC-D and MDC-H. There are three (3) lateral drainage canals discharging into MDC-D, while four (4) lateral drainage canals discharge into MDC-H. The outfall of the main drainages except MDC-K is also at the Façade drain.

NIA-PMO has completed the design of all the drainage canals, where the design of the cross sections and longitudinal sections were based on the hydraulic calculation. The design runoff was decided based on intensities corresponding to five-year return period. A drainage model for paddy field considering two-day rainfall and two-day drainage gives a peak unit drainage discharge of 6.4 l/s/ha.

Table 4.3.7 List of Drainage Canals and Excavation Volume in LMSA

No.	Drainage Canal	Length (m)	Excavation (m3)	Remarks
1	Lateral Drainage Canal A (LDC-A1)	547	1,283	Remaining
2	LDC-A2	1,079	3,833	Remaining
3	LDC-A3	1,275	3,165	Remaining
4	LDC-A4	882	5,478	Remaining
5	LDC-B1	2,746	11,727	Remaining
6	LDC-B2	1,941	8,437	Remaining
7	LDC-B3	651	2,092	Remaining
8	LDC-C1	1,082	4,425	Remaining
9	LDC-C2	874	3,378	Remaining
10	LDC-C3	1,161	7,711	Remaining
11	LDC-C4	689	1,554	Remaining
12	LDC-D1	1,760	4,840	On going
13	LDC-D2	1,220	3,303	On going

No.	Drainage Canal	Length (m)	Excavation (m3)	Remarks
14	LDC-D3	940	1,674	On going
15	LDC-F	3,116	15,831	On going
16	LDC-H1	1,824	7,680	Remaining
17	LDC-H2	1,091	4,722	Remaining
18	LDC-H3	883	1,166	Remaining
19	LDC-H4	896	1,449	Remaining
20	Main Drainage Canal A (MDC-A)	4,540	61,070	
21	MDC-B	4,294	102,797	Remaining
22	MDC-C	2,871	56,366	Remaining
23	MDC-D	2,412	19,270	On going
24	MDC-E	2,562	8,109	On going
25	MDC-F	3,116	15,866	On going
26	MDC-G	2,871	7,137	On going
27	MDC-H	2,296	21,289	Remaining
28	MDC-I	1,908	6,341	Remaining
29	MDC-J	1,066	2,083	Remaining
	Sub-total of MDC	27,936	300,328	
	Sub-total of LDC	24,657	93,748	
30	FAÇADE DRAIN	14,748	1,288,535	Remaining
31	KALAWAG CREEK	8,460	675,077	On going
	Total	75,801	2,357,688	
	on going	30,997	812,177	
	Remaining Portion	44,804	1,545,511	

Data Source: NIA PMO of MMIP II



Photo shows the lateral drainage canal (LDC-PR-III) excavated in 2011 to improve the drainage capacity.
Source: NIA-PMO



Photo shows the drainage pipe crossing at Sta. 0+120 of MC-3, which is the facility for drainage canal to cross the irrigation canal.
Source: NIA-PMO

4.3.5 Countermeasure for the Damage of Irrigation Canal Caused by Flood

Following the scenario for **Case-2**, having countermeasures for the possible damage of irrigation canals and facilities easily caused by flood is a must hence, it is necessary to: 1) raise the height of canal embankment, 2) employ slope protection on the slope of embankment, 3) concrete lining inside the canal and; 4) replacement of earth canals with concrete flume canal at the end portion of lateral canals.




Figure 4.3.12 Countermeasure Method for the Damage of Irrigation Canal by Flood

Source: JICA Survey Team

4.3.6 Construction Cost of Irrigation System and Drainage System in LMSA

In order to compare the irrigation development cost per hectare of both cases in LMSA, the direct cost

of civil works is estimated in **Case-1** and **Case-2**. Unit cost of the works is the same as the unit cost NIA PMO uses for cost estimation in 2018. The quantity of each work, except for the countermeasure for the damage of canal caused by flood, is according to the estimation of NIA-PMO. Regarding cost estimation of the countermeasure for the damage of canal caused by flood, unit cost is used the reference unit price which is used for the construction of the canal and canal structure.

As shown in Table 4.3.8, the total cost of irrigation development in LMSA becomes PhP 2,356-million (4,878 million Japanese Yen) for **Case-1**. On the other hand, **Case-2** will be PhP 3,228-million (6,682 million Japanese Yen). In **Case-1**, the irrigable area of 3,688 ha is to be developed; therefore, the irrigation development cost per hectare would be PhP 639,000.00 (1,323 thousand Japanese yen). While **Case-2**, the irrigable area of 6,590 ha is to be developed; therefore, the irrigation development cost per hectare arrives at 490 thousand PHP (1,014 thousand Japanese yen).

Table 4.3.8 Comparison of Direct Cost on Civil Works for Irrigation Development in LMSA

No	Item	Portion	Original Plan		Case-1		Case-2		Difference between Case-1 & 2	
			(M. Peso)	(M. JPY)	(M. Peso)	(M. JPY)	(M. Peso)	(M. JPY)	(M. Peso)	(M. JPY)
1	Construction of the MC-2	On going	648.19	1,341.75	648.19	1,341.75	648.19	1,341.75	0.00	0.00
		Remain	773.82	1,601.82	289.76	599.81	773.82	1,601.82	484.06	1,002.01
2	Construction of the MC-3	On going	465.92	964.46	465.92	964.46	465.92	964.46	0.00	0.00
3	Construction of the Lateral, MC-2	On going	56.52	117.00	56.52	117.00	56.52	117.00	0.00	0.00
		Remain	311.94	645.73	235.16	486.78	311.94	645.73	76.79	158.95
4	Construction of the Lateral, MC-3	On going	388.58	804.35	249.50	516.46	388.58	804.35	139.08	287.89
5	Construction of the Main Drainage (MDC)	On going	21.96	45.46	21.96	45.46	21.96	45.46	0.00	0.00
		Remain	40.08	82.96	40.08	82.96	40.08	82.96	0.00	0.00
6	Construction of the Main Drainage (LDC)	On going	1.36	2.81	1.36	2.81	1.36	2.81	0.00	0.00
		Remain	16.72	34.62	16.72	34.62	16.72	34.62	0.00	0.00
7	FAÇADE DRAIN	On going	192.76	399.02	192.76	399.02	192.76	399.02	0.00	0.00
8	KALAWAG CREEK	On going	138.70	287.11	138.70	287.11	138.70	287.11	0.00	0.00
9	Protection Dike	Remain	137.60	284.83	0.00	0.00	0.00	0.00	0.00	0.00
10	Ring Dike	Remain	1,035.92	2,144.36	0.00	0.00	0.00	0.00	0.00	0.00
11	Countermeasure for the damage of canal by flood	Additional					171.72	355.47	171.72	355.47
Total	Whole	Whole	4,230.09	8,756.28	2,356.64	4,878.24	3,228.29	6,682.56	871.65	1,804.32
		On going	1,914.00	3,961.96	1,774.92	3,674.07	1,914.00	3,961.96	139.08	287.89
		Remain	2,508.86	5,193.34	774.49	1,603.19	1,507.06	3,119.62	732.57	1,516.43
Irrigable area (ha)	Whole	Whole	6,590		3,688		6,590		2,902	
		On going	4,457		4,457		2,687		1,770	
		Remain	2,133		2,133		1,001		1,132	
Irrigable area in dry and rainy season (ha)	Whole	Whole	13,180		6,498		10,400		3,902	
		On going	8,914		4,496		7,266		2,770	
		Remain	4,266		2,002		3,134		1,132	
Unit cost per irrigable area (000 Peso/ha) (000 JPY/ha)			642	1,329	639	1,323	490	1,014	149	309
Unit cost per irrigable area of dry and rainy season (000 Peso/ha) (000 JPY/ha)			321	664	363	751	310	643	52	108

Data Source: NIA PMO of MMIP II

- Note: 1) Original plan is that the Dikes will be constructed according to the original design without foundation treatment
2) Case-1: target area is part of LMSA with constructing the part of the irrigation canals and all drainage system
3) Case-2: target area is all LMSA with constructing all irrigation canals and all drainage canals.
4) Costs of the canal structure and the drainage structure are included in the costs of the canals

4.3.7 Operation and Maintenance of Irrigation Systems

The Operation and Maintenance (O&M) of the National Irrigation Systems is managed by the Irrigation Superintendent (Principal Engineer) appointed under the Regional Irrigation Manager of NIA. The Superintendent is responsible for the management of such activities as planning, programming, monitoring and evaluation, and care and maintenance of NIA properties in the region. The Engineering Division is responsible for planning, programming, scheduling and implementation of the maintenance activities, in coordination with the Administrative and Equipment Management Divisions, under the supervision of the Superintendent.

The Maridagao River Irrigation System (MRIS) Management Office, which is in the Operation & Maintenance Section of Cotabato Irrigation Management Office under the NIA Region XII, has the responsibility in the operation of the irrigation systems and the maintenance of main structures such as diversion dam, siphon, diversion canals, main canals and lateral canals in the Service Areas of MMIP I. Concerning MMIP II area, the service areas under two IAs namely Nalapaan and Chrislam IAs were completed and already handed over to the MRIS Management Office from the PMO. Thus, after the completion of the project, all irrigation systems and drainage systems will be handed over to MRIS Management Office from PMO.

Table 4.3.9 shows the current staffing structure and appointment status of the MRIS Management Office. In terms of the appointment status at the time of survey, all the 21 positions were filled as planned. The executing agency did not report any significant O&M constraints due to shortages in staff. Routine (day-to-day) and monthly inspections based on a pre-set maintenance items are conducted in order to identify probable problems as early as possible. Once problems are identified, they are immediately reported and addressed in order to prevent further deterioration and to ensure optimum sustainable performance of the irrigation systems.

However, after completion of the project, the Service Area will be expanded up to almost two times of current service area, therefore, NIA shall increase staff based on the size of service area and work volume. The future plan shown in Table 4.3.9 is proposed by the JICA survey team. The number of the water resources facilities operator B will be revised according to the necessity from view point of the actual water management. The number of the driver mechanic B will be revised based on the maintenance machinery including procured one and annual work volume as well. Temporary driver will be acceptable.

Table 4.3.9 Proposed Staffing Plan of the Maridagao River Irrigation System (MRIS) Management Office

	Title	Major Responsibilities	Planned	Appointed	Future Plan
1	Principal Engineer A	Direct supervision of the implementation and O&M	1	1	1
2	Senior Engineer A	Assistance in supervisory activities	1	1	1
3	Senior Irrigators Development Officer	Training/capacity building, strengthening of Irrigators' Associations	1	1	2
4	Senior Water Resources Facilities Technician	Maintenance of machinery and other mechanical equipment	4	4	4
5	Collection Representative A	Collection of irrigation service fees (1/), developing plans and strategies to improve collection rates	1	1	0
6	Plant Electrician B	O&M of plant electrical system	1	1	1
7	Heavy Equipment Operator	Operation of heavy equipment	1	1	2
8	Accounting Processor A (Billing Check)	Accounting	1	1	1
9	Industrial Security Guard A	Safeguarding of properties, facilities and compounds	4	4	4
10	Data Encoder	Data input related to various acquired data and information	1	1	1
11	Driver Mechanic B	Mechanic maintenance and driving service	1	1	2

	Title	Major Responsibilities	Planned	Appointed	Future Plan
12	Water Resources Facilities Operator B	Operation of gates to regulate amount of water to store/needed	3	3	10
13	Utility Worker	Office maintenance	1	1	1
Total			21	21	30

Data Source: NIA-Region XII organizational structure and its authorized positions (as of May 2017), and the future plan is a proposal by the JICA survey team

Note: 1/ According to the current president's pledge, the irrigation service fee was granted free of charge from the monsoon season of 2017. Therefore, from this season of 2017 monsoon, the fee is not collected.

The MRIS Management Office has their own machinery as shown in Table 4.3.10 for maintenance of irrigation canals and drainage canals including service road. According to the MRIS Management Office, with the existing equipment, they could not accommodate all repair works and rehabilitation in the operation & maintenance of all present service road, which is 141.191 km including the service roads at the new irrigation Service Area of 2,206 ha in UMSA. Therefore, additional maintenance machinery was requested by MRIS Management Office as shown in Table 4.3.11.

Table 4.3.10 Existing Maintenance Machinery which MRIS Office Owns

No	item	Specification	Year of procurement	unit	Quantity
1	Dump Truck	Nissan Dump Truck, UD model CPC14HHLT	2004	unit	2
2	Backhoe	Hydraulic Walking Excavator, Euromack Mdl, 650M, wheeled type, hydraulic operated Kubota Engine, Model V3300 turbocharged, 80HO at 2200 rpm, fully air-conditioned	2001	unit	1
3	Grade	Komatsu Model GD510R Hydraulic operated Kumatsu diesel engine Model S6D95L 125 HP	2002	unit	1
4	Loader	Front end loader, Furukawa FL 150-1, 6BD1 engine	2002	unit	1
5	Crane			unit	1

Data Source: MRIS Management Office

Table 4.3.11 MRIS Office's Request of Additional Maintenance Machinery

No	Item	Specification	unit	Quantity	Remark
1	Dump Truck	332HP(246kW), Loading Capa. 10 ton	unit	6	
2	Hydraulic Excavator	Bucket 0.8m ³ (0.6m ³), 20 ton	unit	1	
3	Long Armed Hydraulic Excavator	Bucket 0.4m ³ (0.3m ³), 22 ton	unit	1	
4	Motor Grader	120 HP (89kW), 10 ton	unit	1	
5	Wheel Loader (Front-End Loader)	Bucket 1.3~1.4m ³ , 6.9 ton	unit	1	
6	Compactor (Tamping Roller)	10 ton, Vibratory	unit	1	

Source: JICA survey team

Note: Item of maintenance machinery and number is added by JICA survey team based on the original request

The MRIS Management Office has its own O&M Manual that consists of the following three volumes: Volume I- Main System; Volume II- Diversion Dam O&M; and Volume III- Annexes. The Manual provides sound and appropriate guidance for operating and maintaining the irrigation system. There have been no reported issues related to usefulness and actual usage of the manual. While most parts of the manual are still useful however, there are parts that need revision.

The revision should be made based on the actual irrigated area, as-built (actual) canal design and irrigation facilities in order to avoid the shortage of irrigation water especially at lower areas by proper operation. In addition, it is important to reduce the excess irrigation water which flows to low ground level areas as drainage water in order to prevent damage by inundation. Therefore, the operation for reducing excess water shall be added to the operation manual.

NIA has provided a wide range of training courses in order to ensure technical standards for O&M activities, including not only O&M related subjects but also financial planning/management, organization of IAs, collection of irrigation service fees³ and agricultural techniques. Some training

³ Irrigation fee was decided free from 2017 monsoon season by a current president's pledge, and therefore, from this season the irrigation service fee is not collected.

courses, such as 'Preparation of O&M plans' and 'Financial planning and control', were repeated year after year. It is required that such trainings shall be continued in order to keep irrigation system suitable.

4.3.8 IMT and Irrigators Association Establishment

With the development of the irrigation system, the operation and maintenance (O&M) of the facilities are to be another crucial sphere to enhance irrigation performance, as well as to sustain the facilities and ensure the water supply up to the end beneficiaries. In order to make irrigation facilities function equally to the water users at the upstream, midstream, and downstream, it is important to consider that NIA and the farmers would organize joint management through irrigation management transfer (IMT).

This section provides the plan for the government – farmer joint irrigation management and also farmers organization, Irrigators Association (IA), establishment.

1) Direction of Irrigation Management

To improve irrigation performance, there are mainly 3 options of irrigation management: government management, farmers' management, and joint management. Several countries where there are national irrigation systems have chosen joint management between the government and the beneficiary farmers, and transferred the responsibility, or a part of the responsibility, of irrigation management from the government to farmers' organizations.

This handing over of irrigation management is known as irrigation management transfer, so-called IMT. The movement had gradually begun around the 1950s to 1970s in distinct parts of the world, such as France, Taiwan, the United States of America, and Colombia; then it was spread in the 1980s to 1990s to the other various countries such as the Philippines, Mali, Tunisia, Bangladesh, New Zealand, Mexico, and Dominican Republic, totaling more than 60 countries.

The advantages of the IMT are considered as the beneficiary-oriented irrigation management and the better cost and human allocation based on the reformation of the government irrigation sector. Farmers are the ones who use the water, conduct irrigation farming, and are directly benefited from the irrigation systems, and also, know the condition and the needs of the terminal irrigation facilities.

Frequent minor maintenance by the end water users can reduce necessity of large-scale rehabilitation to be organized by the government. In addition, reduction of the government maintenance expenses allows them to invest more in the primary construction needs in the other parts of the country or large scale rehabilitation of existing aged systems. Finally, it leads to the increment not only of agricultural productivity but also overall revenue related to the irrigated agriculture, e.g. through irrigation service fee paid by the farmers or otherwise government subsidy in lieu of the service fee, within the country.

From the farmers' perspective, there are both burdens and benefits associated with IMT. The possible burdens and benefits for the farmers are as follows, indicating that there are considerable benefits to the farmers with IMT though there are some burdens for the farmers:

(Burdens)

- 1) Need to spare long time for the meetings, group activities, and consensus making.
- 2) Need to bear the expenses such as membership fee or maintenance fee.
- 3) Need to learn some technical matters such as water management, irrigated farming and financial management.

(Benefits)

- 1) Can promptly maintain damages or malfunctions of the canals and farm ditches where the farmers maintain.

- 2) Can consider cropping patterns and the water distribution for the area collectively among the water users using the same turnout.
- 3) Can examine the on-farm ditch construction or maintenance as a group, even in the area where plot-to-plot irrigation is the major one.
- 4) Can get water in proper timing with proper amount due to above 3 benefits.
- 5) Can increase yield and quality of the products due to proper crop selection, uniform planting period or cropping pattern in the area, resulting in reduction of disease, insect and pests.
- 6) Can rapidly claim to the relevant government agency such as NIA as an association in case the water users need large-scale repair.
- 7) Can open a bank account as an association to manage collective capital, and can collect funds as required by the association, and
- 8) Joint purchase of agricultural inputs and joint sale of the products may be possible in future.

Having seen above points, joint irrigation management is recommended as the potential breakthrough in enhancing the irrigation performance upon completion of the MMIP II. In fact, this concept has been introduced to almost all the NISs, not exceptional to MMIP I area. In order to introduce above irrigation management mechanism, establishment of farmers' organization, so-called Irrigators Association, is to be required as the responsible entities, to which handing over of operation and maintenance of some irrigation facilities from the NIA will be made.

2) Farmer Organization: Irrigators Association (IA)

Based on the plan of joint irrigation management above-mentioned, the main canals, big lateral canals or parts of the big laterals, and the related irrigation facilities are, in principle, managed by the NIA, and the relatively small lateral canals and sub-laterals, turn outs attached thereto, on-farm ditches including main farm ditch and supplementary farm ditch are to be managed by the farmers' organization namely Irrigators Association (IA), though it can be adjusted depending on the length or irrigable area of the canals.

On-farm ditches should be basically created and managed under the farmers' responsibility regardless of current on-farm conditions. In case that the area does not have clear on-farm ditches at present, which is the most common case where the irrigation facilities are being constructed and to be constructed, the water users will discuss, plan and construct those after the establishment of Turnout Service Area Group (TSAG) or the IA.

Of course, the construction of new on-farm ditches is to be conducted only when the water users understand advantages and challenges as well as required costs and labors of on-farm ditch installation, and recognize the necessity together with future crop diversification which is possible only with such on-farm ditch. To assist farmers to construct the ditches, NIA may assist by providing machineries, e.g. excavator or small roller/ compactor.

The management, such as operation and maintenance of the irrigation system including weeding, desilting and collecting of irrigation service fees when applied⁴, should be handed over to the IAs for the blue colored lateral canals basically managed by the IAs. The gates installed at the boundary of the NIA management and IA management area should be operated by the NIA gate keeper, and the facilities thereafter should be operated and maintained under the responsibility of the concerned IAs.

⁴ The irrigation service fee is now granted free of charge from 2017 monsoon season by the current president pledge made during his election campaign. However, since such irrigation service fee paid by the users should be the basis for well operating and maintaining the irrigation facilities at a sound functional level, such fee should be considered in future or otherwise the Government should provide NIA with enough subsidy, which is meant to spend on the operation and maintenance of existing irrigation systems.




Figure 4.3.13 Image of Irrigation Management Transfer

Source: JICA Survey Team

Based on the above discussions, following table presents IA establishment in the MMIP II area in the lower part together with the IAs already established in MMIP I area and two (2) IAs in MMIP II area in the upper part. According to the IAs already established, average IA coverage comes to 350 ha with 266 farmer memberships. This size of IAs could be manageable if the structure is stratified starting with TSAGs and then IA. With reference to the total number of TSAGs in MSA, 174 in total, and also the 11 IAs in the MSA, one IA is to have 16 TSAGs.

Table 4.3.12 Irrigators Association and Turnout Service Area Group

No	Name of IA	Service Area	Service Area, ha	Membership	Area/ FHH	Remarks	No. of TSAG	
1	Gagdanen Baya	MSA	349	379	0.92	MMIP I	174	
2	Tafia	MSA	211	180	1.17	MMIP I		
3	Katingkongan	MSA	395	400	0.99	MMIP I		
4	Morning Light	MSA	378	240	1.57	MMIP I		
5	Basbia	MSA	437	330	1.32	MMIP I		
6	Mansapa	MSA	202	200	1.01	MMIP I		
7	Kipan	MSA	377	330	1.14	MMIP I		
8	Nasgia	MSA	215	185	1.16	MMIP I		
9	MRIS IA DIV. 5 Inc.	MSA	904	134	6.75	MMIP I		
10	Nasfia	MSA	168	165	1.02	MMIP I		No./IA
11	MRIS Div. 6	MSA	354	202	1.75	MMIP I		16
12	Edufia	UMSA (P1)	186	124	1.50	MMIP I		
13	Bagonabati	UMSA (P1)	642	680	0.94	MMIP I		
14	Balantikan	UMSA (P1)	398	333	1.20	MMIP I		
15	Crislam, 1/	UMSA (P2)	339	316	1.07	MMIP II		
16	Nalapani, 1/	UMSA (P2)	52	62	0.84	MMIP II		
	Total		5,608	4,260	1.32			
	Average		350	266	1.32			
No.	Service Area	Stage	Area, ha	No. of Laterals	Ave Area/ IA	Membershi p/ IA	No. of TSAG	
1	Upper Malitbog	MMIP II	2,958	11	269	204	-	
2	Pagalungan Ext.	MMIP II	988	3	329	250	28	

No	Name of IA	Service Area	Service Area, ha	Membership	Area/ FHH	Remarks	No. of TSAG
3	Lower Malitubog	MMIP II	6,590	16	412	313	262
			to add +	3	347	263	No./IA
Total/ Average of MMIP II			10,536	33	319	243	14

Note: 1/ Crislam and Nalapani IAs are within the Upper Malitubog SA of MMIP II, and therefore they are included in the IAs of Upper Malitubog shown in the lower part of the table (see No.1 of lower part of the table).

Source: JICA Survey Team

Concerning the MMIP II area, in fact IAs in the UMSA have been already established, or nearly completed, providing total 11 IAs at an average area of 269 ha and average membership of 204. IAs in PSA and LMSA have not yet been established, and they are to be organized from year 2018. There are in fact 3 laterals in Pagalungan area, and therefore total 3 IAs should be established, giving an average area of 329 ha and average 250 memberships.

In LMSA, there are 16 laterals in total providing irrigation water to 6,590 ha of area. If there will be 16 IAs assigned to each of the laterals, the average coverage area arrives at 412 ha with 313 memberships, which are in fact bigger than what the farmers seem to manage. Therefore, big laterals, e.g. Lateral-D, H, and O should be divided into two (2) areas hence there will be two (2) IAs each in such big laterals. Adding the three (3) IAs, there will be total 19 IAs for the 16 laterals, whereby a typical average IA is to cover 347 ha with 263 memberships.

In sum, within the MMIP II area, there will be 33 IAs with an average coverage of 319 ha, 243 memberships, and 14 TSAGs per typical IA. Since there are 14 IAs in the MMIP I area, there will be total 47 IAs upon completion of the MMIP II. In order to organize farmers into such IAs, NIA-PMO should undertake step-by-step procedure in consolidating the farmers into TSAG, and then IA with the past experiences.




Figure 4.3.14 Organizational Structure of WUA for Distributary Canal

Source: JICA Survey Team

The IA is planned as multilayer structure to prevent centralization of the power to one specific person (see figure below). The functions of planning, decision making, and implementation should be de-centralized into the other groups of the members within the structure. As shown in the figure below,

the base structure should be the TSAGs, which are organized by each turnout water users. Each TSAG has a leader and co-leader, in addition, supporters depending on their necessity.

On the other hand, the apex structure in the IA structure is the General Assembly (GA) composed of all the water users to decide the most crucial issues for the association such as budget, registration of the association, rules and regulations. The Board of Directors (BOD) should be formed by all the TSAG leaders, which can also function as decision making body for the issues related more to the implementation such as annual target of the maintenance. When the BOD members have a meeting, NIA officers will also participate in this meeting as an observer.

Under BOD, 5 to 8 executive officials should be nominated from the BOD members and organize the Management Board (MB), which is responsible for the day-to-day implementation. Each of the MB officials has their own duty as chairperson, vice-chairperson, secretary, treasurer, auditor, and the MB members. The nominated MB members and their duties including the ones of BOD should be finally approved and decided by GA.

The workloads of these executive officials may discourage themselves to continue their duties on a voluntary basis. Therefore, incentives to the officials such as honorarium from the collected fees from members or prior water distribution may be considered and discussed among the water users based upon their needs. In addition, some positions require technical knowledge such as treasurer and auditor. Therefore, the Water Users Association (WUA) can employ those officials as a part time worker from outside of the association, if necessary.

All planning of each specific concern is made in the Planning Committees (PC) placed under the MB. The committee may include water delivery committee, financial committee, and agricultural development committee, etc. depending on their necessity. The MB officials can lead each committee as a leader: for instance, financial committee by the treasurer, water distributary committee by the vice-chairperson, and agricultural development committee by the secretary. Then, the committee members are selected from water users who are willing to participate in each committee activities.

The necessary steps to organize IA can be as follows, and the steps, especially the confirmation of turnout locations and the steps which involve farmers, such as list-up of water users and the update of the parcellary map, introduction of IA, and establishment of TSAGs, are desirable to start in parallel with the construction of the irrigation facilities. To take an attention and initial motivation of the beneficiary water users, ensured water supply from the irrigation facilities is to be crucial and fundamental to mobilize farmers into the initial multiple works required during the formation of IA:

- 1) Confirmation of turnout location,
- 2) List-up water users by each turnout,
- 3) Introduction of IA to the water users,
- 4) Decide leader and co-leader for Turnout Service Area Group (establishment of TSAGs),
- 5) Hold 1st meeting among leaders from all TSAGs (establishment of BOD),
- 6) Hold 1st General Assembly by all the IA members (establishment of GA)*,
- 7) Hold 1st meeting among selected 5 – 8 executive officials (start-up of MB),
- 8) Hold 1st meeting for Planning Committee (start-up of the PC),
- 9) Hold 2nd GA meeting (approval and start-up of activities as IA),
- 10) Preparation for legal registration of IA with SEC and;
- 11) Trainings on O&M and others.

In above process, NIA-PMO and the farmers will act as the main actors of implementation, while consultants may participate to be the supporters to present IA concepts, structure and necessary

preparations. This whole process requires 1-2 years. During the project implementation, the responsible PMO officers of IMT and IA establishment, for example institutional development officer, may organize a committee such as 'IA promotion committee' in order to proceed the IA establishment and lead or share the knowledge in the future.

4.3.9 Future's Plan/Project after MMIP II

1) Rehabilitation and Improvement of Irrigation Facilities in MMIP I

The construction of irrigation canals and facilities under MMIP I was started in 1990 and finished in 2011. Some of the facilities which were constructed at the beginning of the project implementation period have already more than 20 years, and there are some damaged facilities which need rehabilitation. The Maridagao River Irrigation System (MRIS) Management Office is responsible for the operation & maintenance of irrigation systems constructed under MMIP I, and their plan for rehabilitation/ improvement of the irrigation/ drainage systems constructed under MMIP I is shown in Table 4.3.13 below.

At the diversion dam site, 4 items which require rehabilitation/ improvement works are confirmed. The first item is the construction of the shade to protect the gate lifting devices at the 8 spillways from rain and sunlight, in order to avoid immediate drying up of greasing & oiling. The second item is the installation of the trash rack at the entrance of 3 intakes to avoid accumulation of debris that slows down the distribution of water. The third item is the repair and rehabilitation of riprap at the tail end of wing dike facing downstream to avoid scouring. The fourth item is the painting of the accessories to prevent from rusting.

In the Service Area for Bagonabati IA and Tafia IA, a drainage problem has been confirmed. To address it properly, it is necessary to repair and rehabilitate the drainage canal (LDC- PR II), to construct an additional drainage canal from lateral a-1 to Pulangi River, to install three (3) unit control gates at MDC-2 and to extend the canal at Lateral I-2 to prevent frequent flooding of the area from MDC-2.

In another Service Area where Nasf IAa, Mrisia div. 5 IA, Kipan IA, Mansapa IA, Basbia IA and Morning light IA are working, MDC-1 was completed but water has never been delivered to the IA member's farms, due to lack of irrigation facilities from the said canal. Therefore, the farm canals (MFD, SFD) and structures shall be constructed in that Service Area along Lateral D (1-unit Turn out; 4.80 km MFD), Lateral D-1 (2.5 km. MFD), Lateral D-4 (2- units T.O; 3 km. MFD), Lateral C (3.4 kms. MFD), Lateral A-2 (1.20 kms. MFD), Lateral A (2.50 kms. MFD) and Lateral A1-1 (1- unit T.O; 2.00 kms. MFD).

The total length of service roads along canals constructed under MMIP I is 169.6km. Most of them are earth roads with pavement on only a small part, if any, and they are already damaged by rain. The absence of drainage ditch along the cutting section of



Above pictures show a gate lifting device at spillway. There is no shade to protect them from rain and sunshine, and metal parts of the device rust easily. Actually, in seven devices, the cable is already rusty and broken and the lifting devices are not working properly. The operation of these devices is at risk, hence the operation of the entire dam.

the canals has spurred the speed and the extent of dilapidation. Consequently, the bad condition of these roads has hampered the provision of proper O&M to irrigation facilities.

There are damaged canal structures which require rehabilitation, such as steel gates of head regulator for lateral canals and turn-outs. Some of gates are not equipped with lifting devices, steel plate frames and other gates accessories, which are vital for O&M, especially in water distribution activities.

There are some main canals which do not have lining partially, such as 2.0 km in MC-2 and 0.98km in RMC-1. The MRIS Management Office proposed concrete lining for the said portions in main canals and 10 km of lateral canals to enhance smooth delivery and distribution of water to irrigated areas and to reduce water convey loss.



The picture shows service road along the main canal in the Maridagao Service Area. Some parts of earthen road become muddy due to rain.

Table 4.3.13 Proposed Repair or Rehabilitation of Irrigation/ Drainage Systems

No	Proposed Item	Description
1	Construction of shade to the gate lifting mechanisms (at diversion dam)	To protect the gate lifting mechanism at 8 spillways from rain & sunlight to avoid immediate drying up of greasing & oiling
2	Installation of trash rack at the entrance of 3 intakes (at diversion dam)	To avoid accumulation of debris that slows down the distribution of water.
3	Repair and rehabilitation of riprap of the tail end of wing dike (at diversion dam)	To avoid scouring of riprap.
4	Painting of the dam & accessories (at diversion dam)	To prevent some accessories from rusting.
5	Repair & Rehabilitation of Drainage Canal (LDC- PR II) Construction of the additional new drainage canal from lateral a-1 to Pulangi River	Frequent flooding This will enhance the water to flow smoothly & prevent submergence of the Irrigation area. Service area of Bagonabati IA
6	Improvement of existing drainage to be provided 3 unit control gates at MDC-2. Extension of canal at Lateral I-2.	To prevent frequent flooding of the area from MDC-2 (target area 46ha) Service area of Tafia IA
7	Construction of the farm canal (MFD, SFD) and turn out and farm structure Lateral D (1- unit Turn out; 4.80 km MFD) Lateral D-1 (2.5 km. MFD) Lateral D-4 (2- units T.O; 3 km. MFD) Lateral C (3.4 kms. MFD) Lateral A-2 (1.20 kms. MFD) Lateral A (2.50 kms. MFD) Lateral A1-1 (1- unit T.O; 2.00 kms. MFD)	Some of the area after the construction of MDC-1 was not irrigated due to lack of irrigation facilities. Service area of Nasf IA Nasf IA Mrisia div. 5 IA Kipan IA Mansapa IA Basbia IA Morning light IA
8	Rehabilitation/improvement of the service roads along canals (141.191 km)	Most of the service roads for OM of the irrigation facilities were damaged due to earth road.
9	Rehabilitation of canal structures (Steel gates for Head gates and Turn-outs)	Some of gates and turn-outs lack lifting mechanism, steel plate frames and other gates accessories which are vital for O&M especially in water distribution activities.
10	Improvement of the canal by lining MC-2 (no lining portion): 2.0 km RMC-1 (no lining portion): 0.980 km. Laterals (unlined canal): 10 km	To enhance smooth delivery and distribution of water to irrigated areas and reducing water convey loss, unlined canals will be lined.

Source: JICA Survey Team

2) Improvement of Irrigation Facilities Constructed under MMIP II

PMO want to improve the Lateral canals to concrete lining canal for reducing the load of maintenance. In addition, when NIA will select the **Case-2** plan which target area is all irrigable area of 6,590 ha in LMSA with constructing all irrigation canals and all drainage canals, the remaining budget will be insufficient to construct all irrigation canals and drainage canals including indirect cost such as Institution Development, Social Preparation, Right of Way, Procurement by Government, and Field Support, Supervision & Monitoring (FSSM). At first the countermeasure for the damage of irrigation

canals by flood will be canceled. Moreover, some drainage canal will be canceled. Downstream portion of some irrigation canals may be canceled to adjust construction cost in the remaining budget, if the construction cost will be increase due to price escalation. Cancelled component will be picked up to construct in other project.

Table 4.3.14 Proposed Improvement of Irrigation/ Drainage System Constructed under MMIP II

No	Proposed Item	Description
1	Upgrading of Lateral Canal in UMSA, LMSA and PESA	Canal Lining will be introduced to Lateral canals to reduce the maintenance load. Lateral Canals at LMSA (Total Length = 22 km) Lateral Canals at LMSA (Total Length = 82 km) Lateral Canals at PESA (Total Length = 8.8 km)
2	Countermeasure for the damage of irrigation canals by flood	1) Raising height of canal embankment, 2) slope protection on the slope of embankment, 3) concrete lining inside canal and 4) replacement to the concrete flume canal at end portion of Lateral canals and field canals from the earth canal.
3	Construction of the cancelled works which are planned to construct under MMIP II	D/S portion of irrigation canals and canal structures Some drainage canals and drainage structures Improvement of maintenance road
4	Rehabilitation of damaged irrigation and drainage facilities constructed under MMIP II	Some of the facilities will be damaged after starting operation for some years and will be repaired. In case of minor damage, it will be repaired by MRIS maintenance office by using annual budget In case of large damage, It will be rehabilitated or replaced

Source: JICA Survey Team

3) Procurement of Maintenance Machineries for MMIP

The MRIS Management Office has their own machinery for maintenance of irrigation canals and drainage canals including service road. According to the MRIS Management Office, with the existing equipment, they could not accommodate all repair works and rehabilitation in the operation & maintenance of all present service roads. Therefore, additional maintenance machinery was requested to the JICA survey team during first field survey period in 2017. Evaluated and considered the condition after the completion of the project, the JICA study team recommends the additional number and maintenance machinery, which shall be procured by future project, as future plan as shown in Table 4.3.15.

Table 4.3.15 Procurement Plan of Maintenance Machinery

No	Item	Specification	unit	Quantity	Remark
1	Dump Truck	332HP(246kW), Loading Capa. 10 ton	unit	6	NIA's Request
2	Hydraulic Excavator	Bucket 0.8m ³ (0.6m ³), 20 ton	unit	1	NIA's Request
3	Long Armed Hydraulic Excavator	Bucket 0.4m ³ (0.3m ³), 22 ton	unit	1	NIA's Request
4	Motor Grader	120 HP (89kW), 10 ton	unit	1	NIA's Request
5	Wheel Loader (Front-End Loader)	Bucket 1.3~1.4m ³ , 6.9 ton	unit	1	NIA's Request
6	Compactor (Tamping Roller)	10 ton, Vibratory	unit	1	NIA's Request
7	Track Dozer	90HP (67kW), 10 ton	unit	1	Recommend
8	Hydraulic Excavator	Bucket 0.28m ³ (0.20m ³), 7 ton	unit	4	Recommend
9	Steel Wheel Static Roller	76HP (56kW), 3 Wheels, 10~12t	unit	1	Recommend
10	Vibratory Roller	Hand Guide, 12HP (9kW), 0.6t	unit	2	Recommend
11	Vibratory Plate Compactor	4HP (3kW), 0.06t	unit	2	Recommend
12	Forklift	41HP(30kW), Loading Capa. 2.0 ton	unit	1	Recommend
13	Generator Set	20 kVA	unit	2	Recommend
14	Concrete Mixer	HP10 (7.5kW), 0.35m ³	unit	1	Recommend
15	Concrete Mixer	HP15 (11kW), 0.20m ³	unit	1	Recommend
16	Jeep	4 Wheel Drive	unit	2	Recommend
17	Pick-up	2t	unit	2	Recommend
18	Farm Tractor	HP24 (718kW), Crawler (Rear Wheel)	unit	1	Recommend
19	Track Dozer	90HP (67kW), 10 ton	unit	1	Recommend

Source: JICA survey team

Note: Item of maintenance machinery and number is added by JICA survey team based on the original request

4.4 Distribution Infrastructure Improvement and Upgrading

Roads in and around the Project area consist of national road, provincial road, municipal road and barangay road. In addition to these roads controlled by DPWH and LGUs, there are canal maintenance roads running in parallel with the irrigation canals under NIA. In fact, the canal maintenance roads could contribute to facilitating rural mobility as has been observed in the MMIP I area. Canals are by nature constructed by an embankment, whereby the maintenance roads are automatically raised up from the ground, able to be free from inundation.

In addition to above roads, the MMIP II is to construct access road, or so-called intra-site road, which can work as farm-to-market road to easily haul agricultural produce from the farmlands out to major towns, e.g. Pikit, Kabacan, Midsayap, etc., via the provincial and national roads. Such access road could of course function as barangay road in facilitating transport of goods and movement of people for the development of rural economy as a whole.

4.4.1 Construction Area and Expected Influence of Canal Maintenance Road

Table 4.4.1 summarizes the length of canals constructed and to be constructed within MMIP II area. The same lengths are allocated to the maintenance roads, and therefore, there will be total length of canal maintenance roads of 60 km for the main canal and 82 km for the lateral canals under the construction plan of **Case-1**, meanwhile, the length of the former and the latter are to be 72 km and 109 km in **Case-2** plan. Road lengths within LMSA are 23 km and 46 km, respectively for the main canal (MC 2 & MC 3) and laterals, totaling to 69 km under the Case-1, and the Case-2 gives 34 km, 73 km and 107 km in order of above (see Table 4.4.1).

Table 4.4.1 Canal Maintenance Road and Density

No.	Service Area	Canal Type	Length, km			Irrigable area (ha)	Road Density, km/sq.km	
			Case-1 *1)	Case-2 *2)	Difference		Case-1 *1)	Case-2 *2)
1	Upper Malitubog	Main Canal	24.65			2,958	1.94	
		Laterals	23.91					
2	UM Ext.	Main Canal	5.36			988	1.63	
		Laterals	3.36					
3	Pagalungan Ext.	Main Canal	7.44			6,590	1.05	
		Laterals	8.67					
4	Lower Malitubog (LMSA)	Main Canal (No.2)	11.60	22.79	11.19	10,536	1.36	1.71
		Main Canal (No.3)	11.39	11.39	0.00			
		Laterals	46.46	73.10	26.64			
MMIP II		Main Canal	60.44	71.62	11.19	10,536	1.36	1.71
		Laterals	82.40	109.04	26.64			
Grand total			142.84	180.66	37.83			

*1) Case-1: Some parts of Main Canals and Laterals, which would be submerged in rainy season, should not be constructed.

*2) Case-2: All of Main Canals and Laterals should be constructed as planned.

Source: NIA-PMO, JICA Survey Team

Table 4.4.2 Public Roads Available within Pikit Municipality Area

Road Name	No.	Pavement Type and Road Length (as of 2018)					Total (km)	Density km/sq.km
		Concrete (km)	Asphalt (km)	Gravel (km)	Earth (km)			
National Road	2	12.5	0.0	0.0	0.0	12.5	0.04	
Provincial Road	14	3.9	2.0	43.3	18.8	67.9	0.23	
Municipal Street	35	8.8	1.2	10.3	3.1	23.4	0.08	
Barangay Road	71	26.2	1.0	167.4	45.0	239.6	0.81	
Total	122	51.4	4.2	221.0	66.9	343.4	1.16	

Note: Area of Pikit municipality is 295.13 sq.km (source: UNOCHA)

Table 4.4.2 shows the available public road already constructed in Pikit municipality. The road density comes to 1.16 km per sq.km while those new roads of canal maintenance will add to a total of 181 km

with the road density of 1.71 km per sq.km. It means that the construction of canal maintenance roads would almost double the road density within the irrigable areas of MMIP II. This new road arrangement with the construction of main and lateral canals would greatly facilitate the rural economy.

4.4.2 NIA's Design Policy of Canal Maintenance Road

The designs of all types of highways in Philippines should be based on the DPWH Design Guidelines and DPWH Department Orders, which have referred to the current AASHTO (American Association of State Highway and Transportation Officials) design publications. The part of the design policy of canal maintenance road has also been complied with the DPWH Design Guidelines, namely AASHTO methods. Meanwhile, another part of the design policy, which arises from special conditions of canal maintenance road, has been led by NIA's own design views.

1) Design of Gravel Pavement

NIA has adopted the gravel pavement mainly for canal maintenance roads, and the thickness of gravel layer should be determined based on the DPWH Design Guidelines. In comparison with asphalt pavement, the thickness of gravel pavement layer is not so critical, since the small amount of surface deformation can be tolerated in such gravel roads. The important characteristics of gravel pavement surface are as follows:

- ✓ Resist rutting, wearing, raveling and corrugation,
- ✓ Present a smooth riding surface for vehicles, and
- ✓ Possess adequate tire/ soil friction, so that vehicles will not skid and driving wheels will not spin.

Table 4.4.3 shows the minimum thickness of gravel pavement in accordance with traffic volume and the material underneath (subgrade soil). The quality of canal embankment material (soil) should be equivalent to the A4 - A7 class shown in Table 4.4.4, and the traffic volume of canal maintenance road is supposed to be less than 200 vehicles per day in both directions. Accordingly, the thickness of gravel pavement of canal maintenance road is recommended to be 200mm as given of the following:

Table 4.4.3 Recommended Thickness of Gravel Pavement

Traffic Volume in Both Directions (per day)	Classification of Subgrade Soil *	Recommended Minimum Thickness of Gravel Pavement
< 200	A1, A2, A3 soils or CBR > 7	150 mm
	A4,A5,A6,A7,soils or CBR is between 3 and 7	200 mm
> 200	A1, A2, A3 soils or CBR > 7	200 mm
	A4,A5,A6,A7,soils or CBR is between 3 and 7	250 mm

*CBR tests would not be conducted under the construction supervision by NIA

Source: DPWH Design Guidelines, Criteria and Standards (Volume 4, Highway Design, 2015)

Table 4.4.4 Soil Classification in relation to Road Design

Soil Classification	Soil Type	Result of Sieve Analysis *1 (Grain Size Analysis of Soil)	Soil Characteristics in Fraction Passage of No.40 Sieve *2	General Subgrade Rating
A1 class	Stone fragment, gravel and sand	(1) A1-a class No. 10: Max. 50%, No.40: Max. 30%, No.200: Max. 15% (2) A1-b class No.40: Max. 50%, No.200: Max. 25%	Plastic limit: Max.6%	Excellent to good
A2 class	Silty or clayey gravel and sand	(1) A2-4 class No.200: Max. 35% (2) A2-5 class No.200: Max. 35% (3) A2-6 class No.200: Max. 35% (4) A2-7 class No.200: Max. 23%	(1) A2-4 class: Liquid limit; Max.40% Plastic limit; Max.10% (2) A2-5 class: Liquid limit; Min.41% Plastic limit: Max.10% (3) A2-6 class: Liquid limit; Max.40% Plastic limit; Min.11% (4) A2-7 class: Liquid limit; Min.41% Plastic limit; Min.11%	Excellent to good

Soil Classification	Soil Type	Result of Sieve Analysis *1 (Grain Size Analysis of Soil)	Soil Characteristics in Fraction Passage of No.40 Sieve *2	General Subgrade Rating
A3 class	Fine sand	No.40: Min. 51%, No.200: Max. 10%	NP (Non-plastic)	Excellent to good
A4 class	Silty soil	No.200: Max. 36%	Liquid limit: Max. 40% Plastic limit: Max. 10%	Fair to poor
A5 class	Silty soil	No.200: Max. 36%	Liquid limit: Min. 41% Plastic limit: Max. 10%	Fair to poor
A6 class	Clayey soil	No.200: Max. 36%	Liquid limit: Max.40% Plastic limit: Min. 11%	Fair to poor
A7 class	Clayey soil	No.200: Max. 36%	Liquid limit: Min. 41% Plastic limit: Min. 11%	Fair to poor

*1: Sieve Analysis is conducted by using various mesh sized sieves, e.g. No.10 sieve (2.00mm), No.40 sieve (0.42mm), and No.200 sieve (0.074mm) etc. And the ratio (percentage) of various grain sizes, which means the content of soil, will be given by this analysis.

*2: Result of liquid limit test and plastic limit test (% water content)

Source: AASHTO

There are some borrow areas (borrow pits) of embankment material (soil) in and around the MMIP II project site, and the quality of the embankment material should be examined in each borrow area. In addition, the quality control of soil (e.g. reduce water content by temporary stockpiling, etc.) should be considered according to the soil conditions in those borrow areas.


2) Typical Cross Section of Canal Maintenance Road

NIA engineering section provides 4 typical cross sections of canal maintenance road as its NIA's design standard. The roadway width and the shoulder width of each of the cross sections are regulated by the scale of canal, which should vary according to canal design discharge (see Table 4.4.5). The large scaled canals need heavy equipment (e.g. back-hoe, long-armed back hoe and dump truck, etc.) for maintenance works, hence the roadway width should be sufficient for the passage of the heavy equipment. Meanwhile, the maintenance works for small scaled canals require small equipment (e.g. mini-back hoe and light truck, etc.) or human power only, so that the roadway width can be narrower than the large scaled one.


Table 4.4.5 Width of Canal Maintenance Roads

Canal Design Discharge (Q)	Width of Canal Maintenance Roads		
	Roadway Width	Shoulder Width	Total Width
Q > 30 (m ³ /s)	5.00m	1.00m (both side)	7.00m
Q = 30 to 10 (m ³ /s)	4.50m	0.75m (both side)	6.00m
Q = 10 to 0.3 (m ³ /s)	3.00m	0.50m (both side)	4.00m
Q < 0.3 (m ³ /s)	2.00m	0.50m (both side)	3.00m


Source: NIA-PMO, JICA Survey Team




(a) Canal Design Discharge: Q>30 (m³/s)



(b) Canal Design Discharge: $Q=30$ to 10 (m^3/s)



(c) Canal Design Discharge: $Q=0.3$ to 10 (m^3/s)



(d) Canal Design Discharge: $Q < 0.3$ (m^3/s)

Figure 4.4.1 Typical cross Section of Canal Maintenance Roads

Source: NIA-PMO, JICA Survey Team

Generally, roadway cross slope is slightly to be slanted from the road center to the both sides (convexity shape) in order to drain the road-surface water (rainwater etc.). However, the crossing gradient of canal maintenance road keeps 2.0%, down from the canal side (water side) to farm land side in order to prevent the road-surface water from flowing into the waterway/ canal section. Figure 4.4.1 shows the typical cross sections of canal maintenance roads by NIA's own design standard.

The cross slope "H", indicated in Figure 4.4.1, varies according to the geology of foundation, construction method and embankment (or cutting) height. NIA's design standard indicates 1.5 of "H" in case that the canal dykes are to be constructed by embankment. Meanwhile, 1.0 of "H" is applied in case that the canal dykes are constructed by cutting. The geology of the construction site consists mainly of sandy soil and clayey soil. Therefore, the "H", given by NIA's design standard, should be

appropriate even comparing with a Japanese design standard¹.

4.4.3 Network of Access Road (Intra-site Road) and Land Acquisition

In general, canals are aligned from upstream to downstream, namely, from higher elevation to lower elevation. This implies that canal maintenance road runs also together from upstream to downstream areas. Therefore, there would be more roads, canal maintenance roads, perpendicular to the topographic contours while less roads connecting/ bisecting those canal maintenance roads. In this regard, the MMIP II project is to construct some access roads/ intra-site roads basically perpendicular to the canals.

In fact, NIA-PMO has already constructed one access road in UMSA and is constructing another access road within the PESA as of 2017-2018, both of which are aligned bisecting the canals. Same concept has been applied in LMSA too. In the LMSA, following 3 access roads are recommended to construct under the Case-2 plan, and the total length comes to 18.45 km composed of 1.65 km improvement of existing one (E-1 Section), and 18.80 km of new construction. Meanwhile, North to South Access Road-1 (N-2 Section) is not to be constructed under the Case-1 plan, since this section would be in the inundated area during the rainy season (see Table 4.4.6).




Figure 4.4.2 Planned Access Road within LMSA

Source: NIA-PMO, JICA Survey Team

Table 4.4.6 Access Road to be Constructed within Upper Malitubog Service Area

(1) Construction Plan of Case-1

No.	Road Name	Section of Access Road	Station	Road Length	Width of Acquisition *	Land Acquisition
1-1.	East to West Access Road	E-1 Section (Widening of Existing Road)	No.0+000 ~No.1+650	1,650m (1.65km)	W=2.5 (m) × 2 = 5.0(m) (widening of both sides)	8,250 sq. m
1-2.		N-1 Section (New Construction)	No.1+650 ~No.13+450	11,800m (11.80km)	7.0 (m) +1.0 (m)×2 (both sides)=9.0 (m)	106,200 sq. m
2.	North to South Access Road-1	N-2 Section (New Construction)	No.0+000 ~No.3+500	Non-construction (Located in inundated area)		
3.	North to South Access Road-2	N-3 Section (New Construction)	No.0+000 ~No.1+500	1,500m (1.50km)	7.0 (m) +1.0 (m)×2 (both sides)=9.0 (m)	13,500 sq. m
Total				-	-	127,950 sq. m (12.80ha)

¹ In a Japanese design standard for embankment and slope cutting, 1.5 – 1.8 of H is given in case of embankment less than height 5m with bank materials of sandy soil, clayey soil, gravel-sandy soil, while in case of slope cutting, 0.8 – 1.2 is given in case of less than 5m cutting height.

(2) Construction Plan of Case-2

No.	Road Name	Section of Access Road	Station	Road Length	Width of Acquisition *	Land Acquisition
1-1.	East to West Access Road	E-1 Section (Widening of Existing Road)	No.0+000 ~No.1+650	1,650m (1.65km)	W=2.5 (m) × 2 = 5.0(m) (widening of both sides)	8,250 sq. m
1-2.		N-1 Section (New Construction)	No.1+650 ~No.13+450	11,800m (11.80km)	7.0 (m) +1.0 (m)×2 (both sides)=9.0 (m)	106,200 sq. m
2.	North to South Access Road-1	N-2 Section (New Construction)	No.0+000 ~No.3+500	3,500m (3.50km)	7.0 (m) +1.0 (m)×2 (both sides)=9.0 (m)	31,500 sq. m
3.	North to South Access Road-2	N-3 Section (New Construction)	No.0+000 ~No.1+500	1,500m (1.50km)	7.0 (m) +1.0 (m)×2 (both sides)=9.0 (m)	13,500 sq. m
Total			-	18,450m (18.45km)	-	159,450 sq. m (15.95ha)

*The width of "2.5m" in E-1 section includes widened road way, shoulder, side ditch and the space for embankment & cutting. The width of "7.0m" in N-1-N3 consists of roadway width and shoulder (both sides). The width of "1.0 (m)×2" in N-1-N3 means the space for the side ditch, embankment and cutting (both sides).

Source: NIA-PMO, JICA Survey Team

4.4.4 Principle of Design for Access Road (Intra-site Road)**1) Pavement Type of Access Road**

Table 2.5.2 in "Chapter 2, 2.5.1 Roads in and around the Project area (Pikit Municipality)" shows the road length and the share (percentage) of 4 pavement types which are put on four categorized road (National Road, Provincial Road, Municipality Road and Barangay Road) in Pikit Municipality. Table 2.5.2 indicates that share of the concrete road was increased by 5% (from 10% to 15% of the whole roads) from year 2015 to 2016. That is to say, gravel and earthen road have been upgraded to concrete road, meanwhile, the share of asphalt road kept only 1% of the whole roads from year 2015 to 2016.

Following situations, related to the construction industry in Pikit Municipality, could be the main obstacles in promoting the asphalt road. As a result, gravel and earthen roads have been widely upgraded to concrete road.

- ✓ Local contractors operating in around Pikit and Midsayap areas have enough experience for PCCP (Portland Cement Concrete Pavement) construction,
- ✓ The construction method of asphalt pavement is more complicated than the PCCP,
- ✓ There are few local contractors which have specialized equipment for asphalt pavement (asphalt finisher and asphalt distributor etc.), and
- ✓ Contractor could hardly get the material of asphalt pavement (bitumen is imported from foreign countries).

Moreover, totaled lifetime cost (construction/ maintenance/ rehabilitation cost, etc.) of asphalt road tends to be larger than the concrete road thereof. Therefore, the location to be planned for asphalt road should be determined by considering wider public benefits and the projection of future traffic demands. In general, DPWH and LGUs are to lay the asphalt road at heavy traffic portions and main roads which lead to the important institutions, e.g. hospitals and schools. In view of this situations, the pavement type of access roads in MMIP II area should be concrete pavement (PCCP).

2) Typical Cross Section of Access Road

The maintenance works of access roads will be transferred to LGUs upon completion of the Project. Since the road design standards of LGUs have followed the design criteria of DPWH, the design of access roads should be conducted according to the equivalent design criteria. DPWH Design Guideline indicates that there are three major types of pavement in the Philippines, typed as "Flexible (or Asphalt

Pavement)”, “Rigid (or Concrete Pavement)”, and “Unbound, gravel surfaced, unsealed or unpaved road (usually restricted to local rural access or temporary road)”. Incidentally, the third pavement type is considered to be the subset of the “Flexible” road. The access roads are classified as “Rigid (Concrete Road)”, and the pavement design should therefore follow the DPWH’s design criteria for concrete pavement.

Since the functions of access roads are equivalent to those of farm-to-market roads, they are classified as the farm-to-market roads. The minimum design standards for the farm-to-market road were prescribed by DPWH’s Department Order in 2014 (Order No.11). Table 4.4.7 and Figure 4.4.3 show the design elements and typical cross section of farm-to-market road (as part of the above-mentioned Order).

Table 4.4.7 Minimum Design Standards for Farm-to-Market Road (Access Road)

Design Element	Requirements
Pavement Type	Portland Cement Concrete Pavement (PCCP)
Pavement Width	Minimum of 4.0m for two lane (Average daily traffic of less than 200)
Pavement Thickness	Minimum of 150mm (6 inches)
Shoulder Width	Minimum of 1.5m
Material of Shoulder	Gravel Surfacing
Roadway Cross Slope	1.50%
Radius of Horizontal Curve	Minimum of 30m
Length of Vertical Curve	Minimum of Length of 60m
Design Speed	30 (km/ hr) for All Terrain Type

Source: DPWH (Department Order No.11, Series of 2014), JICA Survey Team




Figure 4.4.3 Typical Cross Section of Farm to Market Road (Access Road)

Source: DPWH (Department Order No.11, Series of 2014), JICA Survey Team

3) Design of Concrete Pavement Joint

Joints are placed in concrete pavement to control cracking and to facilitate construction. They divide the concrete pavement (concrete slabs) for the efficient construction, delineating the traffic lane and accommodating the slab movements. There are three types of joint which are commonly used in concrete pavement. Functions of the three typed joints are as follows:

- ✓ “Contraction Joint” is intended to control cracking of concrete slab,
- ✓ “Construction Joint” allows for the interruption of concrete placement, and also functions as the planed longitudinal separations between adjacent lanes and so on,
- ✓ “Isolation (Expansion) Joint” is used to allow relative movement between adjacent structures or pavements.

Further, following design standards and figures were prescribed by DPWH’s Department Order in 2014 (Order No.40).

- 1) All weakened plane joints (contraction joints at every 4.5m and expansion joints at every 90m) shall be provided with dowels on chair (see Annex “1” of Figure 4.4.4).
- 2) For pavement re-blocking, dowels and tie bars shall be provided at transverse construction joint and longitudinal joint, respectively. Holes of at least 10mm diameter greater than the design dowel bar diameter shall be drilled on existing concrete pavement (see Annex “2” of Figure 4.4.5).
- 3) For pavement re-blocking of more than one adjacent blocks (along longitudinal direction), dowels on chairs as requested in item “1)” shall be provided at transverse joint between two adjacent new pavement slabs.




Figure 4.4.4 Annex “1” of DPWH Department Order (No.40 in 2014)

Source: DPWH (Department Order No.40, Series of 2014)




Figure 4.4.5 Annex “2” of DPWH Department Order (No.40 in 2014)

Source: DPWH (Department Order No.40, Series of 2014)

4.4.5 Arrangement Plan of Bridges along Access Roads

“East to West Access Road” will intersect at 12 irrigation canals and 10 drainage canals. “North to South Access Road-1 & Road-2” will also intersect at several drainage canals and irrigation canals.

Moreover, these 3 access roads are supposed to intersect at a large number of small scaled farm drains which are extended all over the Project area. The types and materials of the crossing structure of access roads will be e.g. concrete slab bridge, steel girder bridge, concrete box culvert, conduit (concrete pipe), etc. should be determined based on the detailed survey and past construction records.

Generally, large scale irrigation canals and drainages require the concrete or steel girder bridges due to the safe flow of irrigation water, drainage water and flood water. Concrete box culvert and conduit (concrete pipe) will be constructed at comparatively small and middle scaled canals & drainages in the Project area. Most of the small scaled farm drains will be provided with small conduit (concrete pipe) where they intersect the access roads. Table 4.4.8 and Figure 4.4.6 show the location and planned structure type of the bridges in the access roads under the Case-1 plan, and Table 4.4.9 and Figure 4.4.7 show the Case-2:

Table 4.4.8 List of Bridge along Access Road (Construction Plan of Case-1)

No.	Location of Bridge		Crossing Canal / Drainage				Supposed Structure Type of Bridge *2
	Road Name	Station No.	Canal / Drainage	Design Discharge	Canal Bottom	Canal Depth	
EW-1	East to West Access Road	No.0+440	Lateral-B	0.125(m ³ /s)	0.60(m)	0.65(m)	Concrete slab bridge or concrete box culvert
EW-2		No.0+800	MDC-A	2.461(m ³ /s)	3.10(m)	1.24(m)*1	Concrete or steel bridge
EW-3		No.1+240	Lateral-A	0.278(m ³ /s)	0.70(m)	0.75(m)	Concrete slab bridge or concrete box culvert
EW-4		No.1+680	LDC-A2-a	0.103(m ³ /s)	0.60(m)	0.60(m)	Concrete slab bridge or concrete box culvert
EW-5		No.2+280	Lateral-H3	0.175(m ³ /s)	No drawings		Concrete slab bridge or concrete box culvert
EW-6		No.2+810	Lateral-H	0.385(m ³ /s)	No drawings		Concrete slab bridge or concrete box culvert
EW-7		No.3+300	Lateral-H2	0.035(m ³ /s)	No drawings		Concrete box culvert or conduit (concrete pile)
EW-8		No.3+970	LDC-D1	1.212(m ³ /s)	2.20(m)	0.88(m)*1	Concrete or steel bridge
EW-9		No.4+380	Lateral-H1	0.125(m ³ /s)	No drawings		Concrete slab bridge or concrete box culvert
EW-10		No.4+880	LDC-D3-1	0.705(m ³ /s)	2.00(m)	1.10(m)*1	Concrete or steel bridge
EW-11		No.5+740	LDC-D3	0.551(m ³ /s)	1.80(m)	0.72(m)*1	Concrete or steel bridge
EW-12		No.6+220	Lateral-J	0.180(m ³ /s)	No drawings		Concrete slab bridge or concrete box culvert
EW-13		No.6+530	MDC-E	0.773(m ³ /s)	2.10(m)	0.84(m)*1	Concrete or steel bridge
EW-14		No.6+810	Lateral-K	0.145(m ³ /s)	No drawings		Concrete slab bridge or concrete box culvert
EW-15		No.7+480	MDC-F	0.889(m ³ /s)	2.00(m)	0.80(m)*1	Concrete or steel bridge
EW-16		No.7+700	Lateral-L1	0.085(m ³ /s)	No drawings		Concrete box culvert or conduit (concrete pile)
EW-17		No.8+020	MDC-G	0.459(m ³ /s)	1.70(m)	0.66(m)*1	Concrete or steel bridge
EW-18		No.10+010	Lateral-L	0.095(m ³ /s)	No drawings		Concrete box culvert or conduit (concrete pile)
EW-19		No.10+470	MDC-H	3.909(m ³ /s)	3.60(m)	1.44(m)*1	Concrete or steel bridge
EW-20		No.10+980	LDC-H3	0.200(m ³ /s)	1.10(m)	0.44(m)*1	Concrete slab bridge or concrete box culvert
EW-21		No.11+150	Lateral-N2	0.035(m ³ /s)	No drawings		Concrete box culvert or conduit (concrete pile)
EW-22		No.11+780	Lateral-N	0.529(m ³ /s)	0.90(m)	0.90(m)	Concrete slab bridge or concrete box culvert
NS-1	North to South Access Road-1	No.0+900	MDC-C	Non-construction (Located in inundated area)			
NS-2		No.2+210	Lateral-D3				
NS-3		No.2+550	Lateral-D				
NS-4	North to South Access Road-2	No.0+540	LDC-C1	1.523(m ³ /s)	2.00(m)	1.01(m)*1	Concrete or steel bridge
NS-5		No.0+920	LDC-C3	1.940(m ³ /s)	1.50(m)	1.62(m)*1	Concrete or steel bridge

*1: Water depth calculated by hydraulic analysis (not including freeboard).

*2: Types and construction materials of crossing structures should be determined based on the detailed survey and past construction records etc.

Source: NIA-PMO, JICA Survey Team




Figure 4.4.6 Location Map of Access roads and Bridges (Construction Plan of Case-1)
 Source: JICA Survey Team

Table 4.4.9 List of Bridge along Access Road (Construction Plan of Case-2)

No.	Location of Bridge		Crossing Canal / Drainage				Supposed Structure Type of Bridge *2
	Road Name	Station No.	Canal / Drainage	Design Discharge	Canal Bottom	Canal Depth	
EW-1	East to West Access Road	No.0+440	Lateral-B	0.125(m3/s)	0.60(m)	0.65(m)	Concrete slab bridge or concrete box culvert
EW-2		No.0+800	MDC-A	2.461(m3/s)	3.10(m)	1.24(m)*1	Concrete or steel bridge
EW-3		No.1+240	Lateral-A	0.278(m3/s)	0.70(m)	0.75(m)	Concrete slab bridge or concrete box culvert
EW-4		No.1+680	LDC-A2-a	0.103(m3/s)	0.60(m)	0.60(m)	Concrete slab bridge or concrete box culvert
EW-5		No.2+280	Lateral-H3	0.175(m3/s)	No drawings		Concrete slab bridge or concrete box culvert
EW-6		No.2+810	Lateral-H	0.385(m3/s)	No drawings		Concrete slab bridge or concrete box culvert
EW-7		No.3+300	Lateral-H2	0.035(m3/s)	No drawings		Concrete box culvert or conduit (concrete pile)
EW-8		No.3+970	LDC-D1	1.212(m3/s)	2.20(m)	0.88(m)*1	Concrete or steel bridge
EW-9		No.4+380	Lateral-H1	0.125(m3/s)	No drawings		Concrete slab bridge or concrete box culvert
EW-10		No.4+880	LDC-D3-1	0.705(m3/s)	2.00(m)	1.10(m)*1	Concrete or steel bridge
EW-11		No.5+740	LDC-D3	0.551(m3/s)	1.80(m)	0.72(m)*1	Concrete or steel bridge
EW-12		No.6+220	Lateral-J	0.180(m3/s)	No drawings		Concrete slab bridge or concrete box culvert
EW-13		No.6+530	MDC-E	0.773(m3/s)	2.10(m)	0.84(m)*1	Concrete or steel bridge
EW-14		No.6+810	Lateral-K	0.145(m3/s)	No drawings		Concrete slab bridge or concrete box culvert
EW-15		No.7+480	MDC-F	0.889(m3/s)	2.00(m)	0.80(m)*1	Concrete or steel bridge
EW-16		No.7+700	Lateral-L1	0.085(m3/s)	No drawings		Concrete box culvert or conduit (concrete pile)
EW-17		No.8+020	MDC-G	0.459(m3/s)	1.70(m)	0.66(m)*1	Concrete or steel bridge
EW-18		No.10+010	Lateral-L	0.095(m3/s)	No drawings		Concrete box culvert or conduit (concrete pile)
EW-19		No.10+470	MDC-H	3.909(m3/s)	3.60(m)	1.44(m)*1	Concrete or steel bridge

No.	Location of Bridge		Crossing Canal / Drainage				Supposed Structure Type of Bridge *2
	Road Name	Station No.	Canal / Drainage	Design Discharge	Canal Bottom	Canal Depth	
EW-20		No.10+980	LDC-H3	0.200(m3/s)	1.10(m)	0.44(m)*1	Concrete slab bridge or concrete box culvert
EW-21		No.11+150	Lateral-N2	0.035(m3/s)	No drawings		Concrete box culvert or conduit (concrete pile)
EW-22		No.11+780	Lateral-N	0.529(m3/s)	0.90(m)	0.90(m)	Concrete slab bridge or concrete box culvert
NS-1	North to South Access Road-1	No.0+900	MDC-C	6.657(m3/s)	3.50(m)	2.24(m)*1	Concrete or steel bridge
NS-2		No.2+210	Lateral-D3	0.438(m3/s)	1.00(m)	0.80(m)	Concrete slab bridge or concrete box culvert
NS-3		No.2+550	Lateral-D	0.317(m3/s)	0.90(m)	0.80(m)	Concrete slab bridge or concrete box culvert
NS-4	North to South Access Road-2	No.0+540	LDC-C1	1.523(m3/s)	2.00(m)	1.01(m)*1	Concrete or steel bridge
NS-5		No.0+920	LDC-C3	1.940(m3/s)	1.50(m)	1.62(m)*1	Concrete or steel bridge

*1: Water depth calculated by hydraulic analysis (not including freeboard).

*2: Types and construction materials of crossing structures should be determined based on the detailed survey and past construction records etc.

Source: NIA-PMO, JICA Survey Team




Figure 4.4.7 Location Map of Access roads and Bridges (Construction Plan of Case-2)

Source: JICA Survey Team

CHAPTER 5 PROJECT COST AND IMPLEMENTATION ARRANGEMENT

This chapter discusses the project cost by component and necessary implementation arrangement. The cost consists of direct works, in-direct cost including administration cost, physical contingency and price contingency for inflation, etc. In fact, there are several project components and the implementation modality should vary from one to another such as direct force account, local competitive bidding, etc. It is, however, noted that since ODA loan request was withdrawn, all the project components and related activities are to be planned within GOP budget arrangement as below:

5.1 Project Components Selected and Implementing Departments

Through the afore-mentioned discussions in Chapter 4, the project components have been identified with sub-components. The agencies to be involved in implementing the project components are basically NIA being the principal player, a Government owned and controlled cooperation placed under the Office of the President, and ATI which is controlled by Department of Agriculture (DA). Following table summarizes the project components/ sub-components which are to be financed by GOP budget together with the relevant responsible agencies to implement:

Table 5.1.1 Project Components by Implementing Agencies

No.	Component	Sub-component	Agency
1	Irrigation and Drainage Development	1-1. Construction of MC 2 1-2. Construction of Lateral Canals under MC 2 1-3. Construction of MDCs 1-4. Construction of LDC 1-5. Construction of FAÇADE drain 1-6. Flood Protection Works (canal slope protection, etc.) 1-7. Urgent Works for MMIP I Area (gates and drainages, etc.)	NIA
2	Distribution Infrastructure Improvement	2-1. Access Road (intra-site road) Construction 2-2. Bridge Construction (along access road)	NIA
3	Agriculture & Extension Development	3-1. Technical Assistance for Irrigated Rice Production 3-2. Enhancement of Agriculture Extension Services at Municipality Level 3-3. Development of Seed Production	ATI
4.	Other Related Activities	4-1. Parcellary Mapping/ Survey 4-2. Institutional Development Program (IA establishment) 4-3. Field Support for Supervision and Monitoring 4-4. Project Service Facilities 4-5. Detailed Engineering 4-6. Other Administrative Works	NIA
MMIP III	In future, to be required	III-1. Rehabilitation of MMIP I Area (MSA & UMSA) III-2. Improvement of MMIP II Area (UMSA, LMSA and PESA) III-3. Procurement of Machineries (for maintenance)	NIA

Note: As a project item/cost, not only the above components but also other relevant expenses should be considered such as price escalation, physical contingency, land acquisition, VAT, etc.; however since the above table shows only the direct major components to be undertaken by the implementing agencies, those are not indicated.

Source: JICA Survey Team

As shown above, there are mainly 3 components under MMIP II; namely, 1) irrigation and drainage development, 2) distribution infrastructure improvement, and 3) agriculture & extension development. The former 2 components should be undertaken by NIA while the last one, agriculture & extension development, is to be conducted by ATI of DA. In addition to those components, there are other related activities as follows (see item 4 in the above table):

- 4-1. Parcellary Mapping/ Survey: In this item, all the irrigable service areas with land owners are to be identified plot by plot, which will be the basis of the firmed-up area upon completion of the construction and also the basis of the formation of IAs,
- 4-2. Institutional Development Program: In this activity, Irrigators Association (IA) will be

- established and necessary trainings will be provided to the IA members such as organizational operation, leadership installment, financial and administrative capacity building, water utilization for irrigation, etc.,
- 4-3. Field Support for Supervision and Monitoring: In this item, construction supervision, including procurement of motorbikes and fuel/ lubricant, will be conducted by NIA-PMO in order to monitor and control the project implementation,
 - 4-4. Project Service Facilities: Under this activity, field offices with necessary equipment/ furniture will be constructed, which will be utilized as gate keeper stand-by field office, and also gathering venue for the IAs to be established,
 - 4-5. Detailed Engineering: In this activity, NIA-PMO's detailed engineering works including necessary surveys will be conducted, which may cover the remaining detail design works for the irrigation & drainage system of Lower Malitubog Service Area (LMSA), and minor structures to be required, and
 - 4-6. Other Administrative Works: In this activity, NIA-PMO's general administrative works including procurement of contractors will be conducted.

Completed facilities of irrigation and drainage will be operated and maintained by NIA, in collaboration with IAs, as have been so practiced. On the other hand, the maintenance of distribution infrastructure upon completion is not clear as at now. Basically, such rural roads, or farm-to-market roads, can and should be handed over to Local Government Units (LGUs), specifically saying the municipality government, upon the completion. However, municipalities who do not have enough budget to maintain such rural infrastructure may refuse to take them over as have been experienced in NIA constructed access roads (intra-roads). In this case, NIA will have to operate and maintain such access/ rural roads even after the completion of such roads.

Agriculture and extension development activities will be undertaken by ATI since ATI had been engaged in the agriculture extension services within the MMIP I area. The extension services rendered under MMIP I was funded by JICA's Yen Loan Technical Assistance program, and even as of now ATI still continues such extension activities with the government fund. The office in charge of extension services is an outreach ATI office located in Kabacan controlled by Region XII ATI office. This outreach office is planned to provide agriculture extension services to not only the MMIP I area but also MMIP II area.

Further in addition to above, this Survey recommends such works as; 1) Rehabilitation of MMIP I Area (MSA & UMSA), 2) Improvement of MMIP II Area (UMSA, LMSA and PESA), and 3) Procurement of Machineries (for maintenance) for future works. Right now, there will be no ODA loan assistance, and therefore the remaining works should all be managed/ completed within the NEDA approved budget, so that these additional works are not included in the MMIP II works, and thus recommended as MMIP III in future.

5.2 Implementation Modality by Component

To implement the project components and sub-components, the best implementation modality should be applied, e.g. direct force account, contractor/ supplier through local competitive bidding, contractor/ supplier through international competitive bidding, direct shopping, etc. One thing noted is that contractors interested in undertaking civil works in very much security concerned areas may be few in the Philippines as have been already experienced under the on-going construction works. With this in mind, Table 5.2.1 proposes the implementation modality for each of the sub-components, e.g., by direct force account (DFA), and local competitive bidding (LCB):

Table 5.2.1 Project Components and Implementation Modality

No.	Component	Sub-component	Procurement
1	Irrigation and Drainage Development (NIA)	1-1. Construction of MC 2	LCB
		1-2. Construction of Lateral Canals under MC 2	LCB
		1-3. Construction of MDCs	LCB
		1-4. Construction of LDCs	LCB
		1-5. Construction of FAÇADE drain	LCB
		1-6. Flood Protection Works (canal slope protection, etc.)	LCB
		1-7. Urgent Works for MMIP I Area (gates and drainages etc.)	DFA/LCB
2	Distribution Infrastructure Improvement	2-1. Access Road (intra-site road) Construction	LCB
		2-2. Bridge Construction (along access road)	LCB
3	Agriculture & Extension Development	3-1. Technical Assistance for Irrigated Rice Production	DFA
		3-2. Enhancement of Agriculture Extension Services at Municipality Level	DFA
		3-3. Development of Seed Production	DFA
4	Other Related Activities	4-1. Parcellary Mapping/ Survey	DFA
		4-2. Institutional Development Program (IA establishment)	DFA
		4-3. Field Support for Supervision and Monitoring	DFA
		4-4. Project Service Facilities	DFA
		4-5. Detailed Engineering	DFA
		4-6. Other Administrative Works	DFA
MMIP III	In future, to be required	III-1. Rehabilitation of MMIP I Area (MSA & UMSA)	LCB
		III-2. Improvement of MMIP II Area (UMSA, LMSA and PESA)	LCB
		III-3. Procurement of Maintenance Machineries	ICB/LCB

Source: JICA Survey Team

In proposing the implementation modality above, following were taken into consideration:

- 1) Canal construction, both main and laterals, drainage construction and access road construction can be handled by local contractors, and therefore LCB can be applied in those civil works. Note that the contractors currently engaged are of small scale coming from local areas such as Midsayap, Kabacan, etc. Taking into account the delayed progress in the current works, the local contractors should be widely invited including Davao based ones. With regards to qualification of the contractors, post-qualification method can be applied in these LCB, in which one-stage two-envelope bidding should be conducted.
- 2) Direct force account works can be applied to such support activities as; parcellary map updating, institutional development, field support for supervision and monitoring, establishment of project service facilities, detail engineering by NIA-PMO, and also the agriculture and extension development activities to be undertaken by ATI (refer to the 4-1 to 4-6 of Other Related Works and also 3-1 to 3-3 of Agriculture and Extension Development in above Table 5.2.1).

5.3 Implementation Schedule

5.3.1 Seasonal Implementation Schedule

Though the annual rainfall recorded at Pikit does not amount much, only approximately 900 mm per annum (National Centers for Environmental Prediction: NCEP, US), the rain falls almost throughout year. During monsoon season from May to October, about 80 to 100 mm monthly rainfall appears while during dry season approximately 40 to 60 mm monthly rainfall can be expected. This condition in that rain falls almost throughout year makes workability very low, and during peak rainy season civil works can hardly be undertaken.

In addition, inundation starts taking place at around May/June from the south-boundary of LMSA, flooded from the Pulangi river, and progresses towards mid and northern parts of the LMSA.

Therefore, during the rainy season, southern part of Main Canal No.2 (MC 2) to be constructed in the most east-south part of LMSA will be impossible. The civil works carried out along the southern boundary as well as lower parts of LMSA are therefore given very short period of time for the construction.

Taking into account the above condition, following seasonal implementation schedule is presented as;

- 1) Construction works should be conducted from September to the following year's May though there will be difficulties in September to November to engage the contractors in full construction works. During this period of September to November, mobilization and preparation works should mostly be arranged.
- 2) Most south-eastern part of MC 2 and also canals/ drainages located in southern parts of LMSA will be implemented probably from December to only the following year's March, total 4 months construction period per annum. This is because the construction sites are located along the Pulangi river, and therefore the magnitude of inundation and flooding in these areas could be bigger, resulting in shorter period of construction time.
- 3) Other supportive works such as IA establishment and parcellary map updating can be done almost throughout year including agriculture and extension development activities though there will be difficulties to access the mid and lower parts of LMSA during the rainy season.

Table 5.3.1 Seasonal Implementation Schedule

Component	Agency	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Rainfall	100mm												
	50mm												
	0mm												
1. Irrigation and Drainage Development													
(1) Construction of MC 2/ Laterals under MC 2	NIA												
(2) Construction of MDCs/ LDCs/ FAÇADE drain	NIA												
(3) Flood Protection Works (canal slope protection, etc.)	NIA												
(4) Urgent Works for MMIP I Area (Gates and drainages etc.)	NIA												
2. Distribution Infrastructure Improvement													
3. Agriculture & Extension Development Activities													
4. Other Supportive Activities (IA establishment, etc.)													

Source: JICA Survey Team

Construction/ implementation can be done.

5.3.2 Overall Implementation Schedule by Component

Total period of the implementation is defined by, in general, the biggest component undertaken in the Project in terms of work volume as well as by such activities requiring longer implementation period, e.g. institutional development (IA establishment) and agriculture and extension development. Total implementation period is therefore set at 4 years starting from 2019 onwards with reference to the implementation speed/ progress which have been experienced in the on-going MMIP II construction works (see Table 5.3.1).

5.4 Cost Estimation and Disbursement, and Step-wise Implementation

5.4.1 Basis of Cost Estimation

In the previous chapters, series of project components and sub-components have been identified and the implementation plans and schedule have been formulated. This sub-chapter stipulates cost estimation by component, and the manner of the estimation is summarized below:

- ✓ Irrigation and Drainage Development: Major costs are the construction of Main Canal No.2, its lateral canals, other remaining irrigation canals and drainage canals, etc. The costs were referred to those ones set by NIA-Regional Office and NIA-PMO and already applied in the on-going construction contracts.
- ✓ Distribution Infrastructure Improvement (Access Road and Bridge Construction): NIA-PMO is to construct the access road and bridge along the access road, and therefore the relevant costs were estimated based on those ones set by NIA-Regional Office and NIA-PMO and already applied in the past road (intra-road) construction/ improvement works within the MMIP. The cost estimation is made on basis of quantities estimated and relevant unit prices applied by NIA-Regional Office/PMO. The major cost for the access road construction is for the concrete-pavement.
- ✓ Agriculture and Extension Development: Major costs are establishment of demonstration farms and related logistics support for the extension field workers. Trainings to municipality agricultural staff and production of dissemination materials are also included in this cost estimation of the agriculture extension. A set of extension team is arranged, who is composed of ATI staff and contractual-basis extension staff. The extension staff are in charge of frontline extension to the famers upon trainings completed by the subject matter specialist stationed in regional office.

Direct costs under this Project are composed of; direct civil and structure construction cost, demonstration farm establishment cost with necessary logistics cost, construction of offices/ housing unit, and other supportive activities including IA establishment, while in-direct cost shall cover price escalation, physical contingency, land acquisition and compensation when required, and VAT. The in-direct costs under this Project are estimated as follows including exchange ratio;

- ✓ Exchange Rate: 1) US\$ 1 = ¥ 108.81, 2) US\$ 1 = PHP 52.57, 3) PHP 1 = ¥ 2.07
 - ✓ Price Escalation Rate: 1) Foreign Currency Portion: 1.7%, 2) Local Currency Portion: 1.9%
 - ✓ Physical Contingency: Construction: 5.0%
 - ✓ Rate of Tax: 1)VAT: 12.0%, 2) Import Tax: 0.0%
 - ✓ Rate of Administration Cost: 5.0% (including detail design)
- 1) Foreign exchange ratios are set at 108.81 Yen against one US dollar and PHP 52.57 against one US dollar, accordingly 2.07 Yen per one PHP, applied as of the values of June 2018.
 - 2) Price escalation for foreign currency portions of direct cost is set at 1.7% of inflation index while the price escalation of local currency portions to be 1.9% of inflation index estimated as the average of construction materials whole sale price index in the years of 2014¹, 2016, 2017. Note that the price escalation is applied for the direct construction cost, and when needed machineries procurement cost, latter of which is also a part of the direct cost.
 - 3) Physical contingency is set at 5.0% to be applied both for foreign and local portions and also for all the direct cost such as construction costs and when needed procurement costs. This physical contingency ratio is applied over the direct cost plus the above price escalation cost.
 - 4) VAT is set at 12% as practiced in the Philippines while import tax is set at 0.0% according to

¹ the inflation index in year 2015 was minus 0.708%, and therefore it was omitted to estimate the past average.

information given by JICA Headquarters.

- 5) Administration cost covers salaries of government staff engaged in the Project including various allowance, depreciation cost for existing machineries that the NIA-PMO owns, maintenance cost of machineries, equipment, offices, material management cost, etc. The ratio of the administration cost is set at 5.0% over the direct costs and also those price escalation and physical contingencies.

5.4.2 Cost Estimation

1) Costs of Case-1 and Case-2

The Project cost is estimated by component, which consists of; 1) irrigation and drainage development, 2) distribution infrastructure improvement, 3) agriculture & extension development, 4) other related activities (including detail design and administration cost, etc.), 5) land acquisition, 6) VAT, 7) price escalation, and 8) physical contingency. The construction plan of “1) irrigation and drainage development”, which is to install the irrigation and drainage facilities in LMSA, has two options, so-called Case-1 and Case-2. The main canals and lateral canals, which will be very much affected by flood in rainy season, will not be constructed in Case-1, while the construction plan of Case-2 covers all the main canals and lateral canals as per NIA-PMO original plan. The all the planned drainage canals (main/ lateral/ Façade drain) should be constructed in both Case-1 and Case-2.

The difference of direct cost between Case-1 and Case-2 should affect the other related works and indirect costs. The total project cost of Case-1 arrives at 1,350 million PHP (2,795 million JPY), out of which direct cost amounts to 1,081 million PHP (2,238 million JPY), and indirect cost amounts to 269 million PHP (557 million JPY) composed of land acquisition, VAT, price escalation and physical contingency (see Table 5.4.1). On the other hand, the total project cost of Case-2 arrives at 2,433 million PHP (5,037 million JPY), out of which direct cost amounts to 1,949 million PHP (4,035 million JPY), and indirect cost shares 484 million PHP (1,002 million JPY) composed of land acquisition, VAT, price escalation and physical contingency (see Table 5.4.1). The physical implementations of both cases will be carried out over 4 years (from 2019 to 2022) as shown in Table 5.4.2.

Table 5.4.1 Summary of the Project Cost (Case-1 & Case-2)

Particulars	Project Cost			
	Case-1		Case-2	
	Million PHP	Million JPY	Million PHP	Million JPY
A. Direct Cost				
1. Irrigation and Drainage Development				
1-1. Construction of the MC-2	254.99	527.83	680.96	1,409.59
1-2. Construction of the Lateral under MC-2	206.94	428.37	274.51	568.23
1-3. Construction of the Main Drainage (MDC)	35.27	73.01	35.27	73.01
1-4. Construction of the Main Drainage (LDC)	14.71	30.46	14.71	30.46
1-5. Construction of FAÇADE DRAIN	169.63	351.13	169.63	351.13
1-6. Flood Protection Works (canal slope protection, etc.)	0.00 *	0.00 *	269.65	558.17
1-7. Urgent Works for MMIP I Area				
(1) Supply and delivery of steel gates	5.72	11.84	5.72	11.84
(2) Drainage Structures	3.36	6.96	3.36	6.96
2. Distribution Infrastructure Improvement				
2-1. Access Road (Intra-site Road) Construction	114.66	237.35	141.50	292.91
2-2. Bridge Construction (along Access Road)	124.78	258.30	146.34	302.93
3. Agriculture & Extension Development				
3-1. Technical Assistance for Irrigated Rice Production	69.13	143.11	69.13	143.11
3-2. Enhancement of Agriculture Extension Services at Municipality Level	5.24	10.84	5.24	10.84
3-3. Development of Seed Production	4.33	8.95	4.33	8.95
4. Other Related Activities				
4-1. Parcellary Mapping/ Survey				
(1) Parcellary Survey	1.36	2.81	2.64	5.46

Particulars	Project Cost			
	Case-1		Case-2	
	Million PHP	Million JPY	Million PHP	Million JPY
(2) Construction Survey	1.76	3.64	3.42	7.09
4-2. Institutional Development Program (IA establishment)				
(1) On-Farm Development	3.26	6.74	6.73	13.94
(2) IA Strengthening/Organizing	2.53	5.23	5.22	10.80
4.3. Field Support for Supervision and Monitoring	12.18	25.21	23.71	49.07
4-4. Project Service Facilities	1.00	2.08	1.94	4.03
4-5. Detailed Engineering	20.12	41.64	34.04	70.46
4-6. Other Administrative Works	30.17	62.46	51.05	105.68
Total of Direct Cost (A)	1,081.14	2,237.95	1,949.11	4,034.66
B. Indirect Cost				
Land Acquisition	11.12	23.02	19.00	39.34
VAT	143.08	296.19	258.44	534.97
Price Escalation	50.45	104.42	90.92	188.20
Physical Contingency	64.29	133.08	115.87	239.86
Total Indirect Cost (B)	268.94	556.71	484.23	1,002.36
Total Project Cost (A) +(B)	1,350.08	2,794.66	2,433.35	5,037.03

Exchange Rate: 2.07 JPY/ PHP, Source: JICA Survey Team

* / Flood protection works are not considered in the Case-1 since most of the canals are to be constructed within the area less/ least affected by flood while it was well considered in the Case-2 as Case-2 is to construct all the canals as per NIA-PMO original design.

Table 5.4.2 Disbursement of the Project (Case-1 & Case-2)

Year	Annual Budget					
	Case-1			Case-2		
	(million PHP)	(million JPY)	Ratio	(million PHP)	(million JPY)	Ratio
2019	192.38	398.23	14.2%	346.37	716.99	14.2%
2020	512.07	1,059.98	37.9%	922.83	1,910.25	37.9%
2021	450.46	932.46	33.4%	812.28	1,681.42	33.4%
2022	195.17	403.99	14.5%	351.87	728.37	14.5%
Total	1,350.08	2,794.66	100.0%	2,433.35	5,037.03	100.0%

Exchange Rate: 2.07 JPY/ PHP

Source: JICA Survey Team

2) Comparison between NIA Estimation and JICA Estimation for Case-1 and Case-2

NIA started the MMIP II project from the current year of 2011 (CY2011) with estimated total project cost of 5,444.85 million PHP (NEDA approved project cost). Table 5.4.3 shows the yearly allotment of project cost from CY2011 to as at CY2018, and total allotment of the project cost amounts to 3,991.35 million PHP till the end of fiscal year 2018 (December 2018). Therefore, NIA is supposed to complete the remaining works of MMIP II project by using the balance of 1,453.50 million PHP.

Table 5.4.3 MMIP II Project Cost (NIA Estimation)

Construction Year (CY)	Targeted Area	Project Cost (Yearly Allotment)
CY 2011	UMSA	200,000,000 PHP
CY 2012	UMSA	391,350,000 PHP
CY 2013	UMSA	200,000,000 PHP
CY 2014	UMSA	600,000,000 PHP
CY 2015	LMSA	850,000,000 PHP
	PESA	
CY 2016	LMSA	850,000,000 PHP
CY 2017	LMSA	600,000,000 PHP
CY 2018	LMSA	300,000,000 PHP
Total (CY2011~2018)		3,991,350,000 PHP
Overall Cost (NIA Estimation/ NEDA approved cost)		5,444,850,000 PHP
Balance		1,453,500,000 PHP

Source: NIA PMO

Though the project costs of Case-1 and Case-2 estimated by JICA Team include sufficient budget for “Distribution Infrastructure Improvement (access road & bridge)” and also “Agriculture & Extension Development”, the NIA’s estimation is mostly composed of civil works and other related works only relevant to the irrigation and drainage works. Further, the project cost of Case-2 estimated by JICA Team includes the necessary cost of “Flood Protection Works, e.g. canal slope protection works”, which prevents the canal slopes from being damaged by floods. This cost is not included in NIA’s estimation.

Table 5.4.4 shows the available budget for remaining civil works for the MMIP II project area (1,453.5 million PHP), and the comparison between the remaining budget and the JICA Team’s estimation for the both Case-1 and Case-2 by scope of the components covered. Note that indirect costs have been proportionally included into the relevant direct costs for the Case-1 and Case-2. The table indicates the following:

- ✓ The project cost of Case-1 estimated by JICA team is smaller than that of the remaining budget due to reduction of the scope of construction for irrigation canals, for which canal network is to be constructed only within the area not much affected by flooding. Excluding the agriculture component, required cost to complete the Case-1 amounts to 1,237.79 million PHP, which is only 85% of the remaining budget. Even with the agriculture component included, the required budget comes to 1,350 million PHP, which is manageable within the remaining budget (93% of the remaining budget).
- ✓ On the other hand, the cost of Case-2 comes to 1,528 million PHP even only for the construction of irrigation and drainage canals, which is already beyond the remaining budget by 5% (74 million PHP over). The JICA team is of the opinion that Case-2 should be implemented with at least some flood protection works such as canal slope protection, concrete flume introduction to on-farm ditches, sluice gates introduction along the Pulangi river, etc. With this flood protection works, the required amount arrives at 1,883 million PHP, already exceeded by about 30% (429 million PHP over). Then, with the road and bridge construction, the required cost will exceed by 60% (868 million PHP over). Further, with the agriculture component, the total required cost comes to 2,433 million PHP, exceeded by 67% (980 million PHP over).

Table 5.4.4 Estimated Project Cost for Remaining Civil Works in MMIP II Project Area

Basis of Estimation	Project Cost *1 (million PHP)	Ratio	Difference	Remarks	
Remaining Budget	1,453.50	100.00%	-	Balance of Allotment Budget (see Table 5.4.3)	
JICA Team's Estimation	Case-1	896.07 (-557.43) *2	61.65%	-	NIA Portion (Irrigation & Drainage Facilities) only *3
		1,237.78 (-215.72)	85.16%	+341.70 (23.51%)	+ Road and Bridge
		1,350.08 (-103.42)	92.88%	+112.30 (7.73%)	+ Agriculture Component
	Case-2	1,527.61 (74.11)	105.10%	-	NIA Portion (Irrigation & Drainage Facilities) only (without Flood Protection Works *3)
		1,882.94 (429.44)	129.55%	+355.33 (24.45%)	NIA Portion (Irrigation & Drainage Facilities) only (including Flood Protection Works *4)
		2,321.04 (867.54)	159.69%	+438.10 (30.14%)	+ Road and Bridge
		2,433.35 (979.85)	167.41%	+112.30 (7.73%)	+ Agriculture Component

*1: Including "Other Related Works" and "Indirect Works (Land Acquisition, VAT, Physical Contingency and Price Escalation)"

*2: shows difference between the cost and the remaining budget.

*3: "Flood Protection Works" are not considered in Case-1

*4: Flood Protection Works: Canal Slope Protection, Concrete Flume Introduction, Sluice Gates Introduction along the Pulangi River etc.

Source: NIA PMO, JICA Survey Team

3) Cost of MMIP III

Some of the irrigation facilities constructed in MMIP I area and constructed in early stage of MMIP II area have been deteriorated, and thus require some rehabilitation/ improvement works. With this situation, the rehabilitation/ improvement project, so-called “MMIP III Project”, should be planned to implement in the near future. MMIP III Project should be composed of 3 major works, such as “Rehabilitation of MMIP I Area (MSA & UMSA)”, “Improvement of MMIP II Area (UMSA, LMSA and PESA)”, and “Procurement of Machineries (for maintenance)”. The current status of lacking the maintenance machineries would prevent sound maintenance works burdened by flooding. Therefore, sufficient number of machineries should be procured in the MMIP III Project.

The total project cost for the MMIP III arrives at 450 million PHP (932 million JPY), out of which direct cost amounts to 338 million PHP (781 million JPY), and indirect cost shares 73 million PHP (151 million JPY) composed of VAT, physical contingency and administration cost (see Table 5.4.5). Since the project implementation schedule has not yet been fixed, this project cost does not include the price escalation cost.

Table 5.4.5 Summary of the Project Cost of MMIP III Project

Particulars	Procurement Method	Project Cost	
		Million PHP	Million JPY
A. Direct Cost			
III-1. Rehabilitation of MMIP I Area (MSA & UMSA)	LCB	149.60	309.67
III-2. Improvement of MMIP II Area (UMSA, LMSA and PESA)	LCB	101.49	210.09
III-3. Procurement of Machineries (for maintenance)	ICB/LCB	126.43	261.70
Total of Direct Cost (A)	-	377.52	781.46
B. Indirect Cost			
VAT	-	34.24	70.88
Physical Contingency	-	18.88	39.07
Administration Cost	-	19.82	41.03
Total Indirect Cost (B)	-	72.93	150.98
Total Project Cost (A)+(B)	-	450.45	932.43

Exchange Rate: 2.07 JPY/ PHP

Source: JICA Survey Team

5.4.3 Step-wise Implementation

As afore-mentioned, remaining budget at the end of 2018 is estimated at 1,453.50 million PHP, and as a matter of fact this budget can cover the required cost of Case-1 only. Also, from the view point of maintenance of the irrigation facilities in the LMSA, Case-1 is much easier than that of Case-2 since the canal network of Case-1 is to be installed within the area less or minimally affected by flooding. Therefore, JICA team recommends NIA central office to go with Case-1 and complete the MMIP II as soon as possible with the remaining available budget.

Though the Case-1 is the highly recommend plan by the JICA team, should NIA want to proceed to Case-2 in that the canal network is to be constructed as per the original NIA-PMO design keeping the designed irrigable area of 6,590 ha, there should of course be another budget arrangement. Taking into account this additional budgetary requirement, the JICA team recommends NIA Central Office to implement Case-1 first, and then proceed by step-wise implementation as indicated in the following:

- ✓ First priority should be to complete the Case-1 construction including roads and bridges and also together with agriculture components. All the components under Case-1 require 1,350.08 million PHP, which can be managed within the available remaining budget of 1,453.5 million PHP.
- ✓ With another budget arrangement of 868 million PHP, NIA may proceed to Case-2 should NIA intend so. In this case, agriculture component should also be included, requiring total 980 million additional budget. If there is an opportunity of arranging further additional 450 million PHP, NIA

may implement Case-2 works together with MMIP III, requiring total 1,430.3 million PHP.

Table 5.4.6 Preliminary Plan of Step-wise Implementation towards Case-2 and MMIP III

Remaining Budget	Project Cost *1 (million PHP)			Remarks
	Case-1 (First Priority)	Case-2 (2 nd stage)	MMIP III	
1,453.50 Million PHP	1,237.78 (-215.72) *2	-	-	Irrigation & Drainage + Road and Bridge, *3
	1,350.08 (-103.42)	-	-	+ Agriculture Component
	-	1,882.94 (429.44)	-	NIA Portion (Irrigation & Drainage Facilities) only (including Flood Protection Works *4)
	-	2,321.04 (867.54)	-	+ Road and Bridge
	-	2,433.35 (979.85)	-	+ Agriculture Component
	-	-	450.45	Rehab of MMIP I, Improvement of MMIP II, and procurement of maintenance machineries.
	-	-	1,430.3 (979.85+450.45)	Combine Case-2 and MMIP III

*1: Including "Other Related Works" and "Indirect Works (Land Acquisition, VAT, Physical Contingency and Price Escalation)"

*2: shows difference between the cost and the remaining budget.

*3: "Flood Protection Works" are not considered in Case-1

*4: Flood Protection Works: Canal Slope Protection, Concrete Flume Introduction, Sluice Gates Introduction along the Pulangi River etc.

5.5 Institutional Setup for Project Implementation

5.5.1 Agencies Concerned and Implementation Capacities at the Central Level

National Irrigation Administration (NIA) is the implementing agency of the MMIP II (the Project). NIA was created under Republic Act (RA) 3601 on 22 June 1963. NIA is one of the government owned corporations with approximately 9,000 permanent staff as of May 23, 2017. Aside from the permanent position staff, there are about 400 staff engaged in maintenance and other operation, and contractual of about 4,000 staff, totaling to 14,000 staff as of now.

Figure 5.5.1 shows the NIA's organization structure, in which the headquarters consists mainly of Engineering and Operations Sector and Administration and




Figure 5.5.1 NIA Organizational Structure

Source: NIA Headquarters

Finance Sector. Under the former Engineering and Operations Sector, there are 2 departments; namely, Engineering Department and Operations Departments. Further down the Engineering Department, there are 3 divisions such as Project Planning Division, Design and Specifications Division, and Construction Management Division (CMD). Since MMIP II is an on-going project, the NIA-PMO is supposed to report to the CMD of the Engineering Department.

There are 14 regional offices, each of which is composed, similarly to that of the Headquarters, of Engineering and Operations Division and Administrative and Finance Division. The MMIP is located within the jurisdiction of NIA Regional Office No. XII. Under the regional office, there are irrigation management offices, which are directly engaged in the operation and maintenance of completed irrigation systems. It means that, for example, MMIP I is now under one of the irrigation management offices of NIA Region XII, called Cotabato Irrigation Management Office located in Kidapawan town, about 52 km east from the Pikit town.

Further, there is a field office called Maridagao River Irrigation System office, which is controlled by the Cotabato Irrigation Management Office. This field office is the front-line in-charge of operation and maintenance of the completed irrigation systems such as Maridagao Service Area of MMIP I, Upper Malitbog SA completed under MMIP I and a part of the UMSA completed under MMIP II as of July 2017. As such, upon completion of parts of MMIP, such completed parts have been transferred from NIA-PMO in charge of the construction to the respective management office.

Table 5.5.1 shows the staff assignment at the NIA headquarters. In the HQs, there are total 717 staff composed of 421 monthly/ permanent positions, daily/ casual positions, and contract of service positions. With regards to the Construction Management Division, there are in fact only 36 staff composed of 14 monthly/ permanent positions and 22 daily/ casual positions.

Table 5.5.1 NIA Headquarters Staffing as at May 31, 2017

Division/ Position	Vacant Positions	Monthly/ Permanent Positions	Daily/ Casual Position	Contract of Service Positions	Total	Filled Positions
Office of the Corporate Board Secretary	1	2	-	-	3	2
Internal Audit Services	7	18	8	0	33	26
Office of the Administrator	6	9	3	3	21	15
Office of the Senior Deputy Administrator	1	6	-	-	7	6
Corporate Planning Services	5	23	11	1	40	35
Public Affairs and Information Staff	5	5	8	-	18	13
Legal Services	2	9	1	-	12	10
Office of the Deputy Administrator for E&O	2	6	-	-	8	6
Engineering Department						
Office of the Depart Manager – Eng. Dept	1	2	1	-	4	3
Construction Management Division	3	14	22	-	39	36
Design and Specifications Division	7	13	15	-	35	28
Project Planning Division	3	24	22	3	52	49
Operations Department						
Office of the Depart Manager – Ope. Dept	1	2	2	-	5	4
Institutional Development Division	1	15	4	2	22	21
Irrigation Engineering Center	3	17	3	-	23	20
Equipment Management Division	2	12	7	-	21	19
Systems Management Division	2	18	7	1	28	26
Office of the Deputy Administrator for A&F	2	6	3	-	11	9
Financial Management Department	18	44	16	0	78	60
Administrative Department	21	59	54	6	140	119
Commission on Audit (COA)	-	-	3	-	3	3
Office of the Ombudsman	-	-	1	-	1	1
TOTAL	116	421	274	22	833	717

Source: NIA Headquarters, as of May 31, 2017

Table 5.5.2 summarizes the budget allocated to NIA for the last 8 years. NIA's projects are composed of local funded projects, foreign assisted project, international agency projects, and other sources while NIA's programs are those of feasibility study, detailed engineering, pre-engineering activities, restoration/ rehabilitation/ repair of irrigation system, improvement of service roads, heavy equipment procurement, irrigation management transfer support services, environmental impact statement, climate change adaptation works etc. Note that the program budget before the year 2014 was not available, and therefore the budgets before that year show only the project budget.

Table 5.5.2 NIA's Financial Statement by Project and Program

Fiscal Year	NIA's Projects 1)					NIA's Programs 2)				Total (1)+(2)
	Local Fund Projects	Foreign Assisted Projects	International Agency Projects	Other Source	Sub-total (1)	General Administration and Support	Support to Operations	Operations	Sub-total (2)	
2010	10,815,986	4,144,324	661,613	-	15,621,923	NA			NA	15,621,923
2011	7,837,623	5,448,431	448,985	2,433,671	16,168,710	NA			NA	16,168,710
2012	20,328,649	4,125,403	609,756	-	25,063,808	NA			NA	25,063,808
2013	23,314,142	4,015,153	-	-	27,329,295	NA			NA	27,329,295
2014	14,253,209	2,479,215	-	-	16,732,424	-	-	4,379,425	4,379,425	21,111,849
2015	15,424,674	2,278,699	-	-	17,703,373	1,642,973	575,481	8,828,614	11,047,068	28,750,441
2016	10,860,750	3,757,074	-	-	14,617,824	7,288,561	563,285	10,273,514	18,125,360	32,743,184
2017	9,554,575	3,170,129	-	-	12,724,704	10,711,537	140,500	14,799,700	25,651,737	38,376,441

Source: NIA Headquarters, May 2017

Figure 5.5.2 illustrates the NIA's budgets for projects and programs (program budgets before 2014 were not available). As is shown, the project budget once peaked in 2013 with an amount of 27 billion PHP, after which the budget started decreasing. Instead, program budget has been increasing year by year. As of year 2017, the program budget amounts to 25.7 billion PHP while that of projects marks 12.7 billion PHP, totaling to 38.4 billion PHP.




Figure 5.5.2 NIA's Project and Program Budgets

Source: NIA Headquarters (May 2017)

In fact, taking into account the annual budget scale for projects marking around 12 to 14 billion PHP for the last 2 years, the remaining works of MMIP II project, requiring maximum annual disbursement of 720 – 820 million PHP (see Table 5.4.2), could be managed by NIA from the view point of budget disbursement since it shares only around 6%. On the proposed MMIP III Project, the project cost is estimated at 450 million PHP (see Table 5.4.5). If the construction is planned to complete within 2 years, one-year disbursement should be around 230 million PHP, which is less than 2% of the NIA's annual project budget. Thus, from the financial disbursement view, NIA will be able to manage the remaining works of MMIP II as well as the works of MMIP III.

5.5.2 Agencies at the Regional and Field Level

NIA has its regional office, and the structure of the regional office is basically same as that of the NIA HQs with some simplified cadres. For example, the regional office is structured with 2 divisions of Engineering & Operation Division and Administrative and Finance Division (at the HQs level, these 2 divisions are called Sector). Under the Engineering & Operation Division, there are 5 sections such as Planning & Design Section, Construction Management Section, Operation Section, Institutional Development Section, and Equipment Management Section.

Under the regional office, there are irrigation management offices directly in charge of operation and management of completed irrigation systems². The structure here is basically same as that of the regional office with some simplified layers. Namely, under the head of irrigation management office, called Division Manager, there are 4 sections such as Institutional Development Section, Engineering Section, Operation and Maintenance Section, and Administration and Finance Section.

The Operation and Maintenance Section of the irrigation management office undertakes the frontline responsibility for O&M of completed irrigation systems. In case of Cotabato Irrigation Management Office, the Operation and Maintenance Section should oversee total 4 irrigation systems, and therefore 4 principal engineers are assigned to lead each team in operating and maintaining the irrigation systems. One of the 4 irrigation systems is, in fact, the Maridagao River Irrigation system, which include Maridagao Service Area (MMIP I), Upper Malitubog Service Area (MMIP I), and Upper Malitubog Service Area completed under MMIP II.

Table 5.5.3 summarizes the staff allocation of the Region XII office and Cotabato Irrigation Management Office. There are 54 staff in the NIA Region XII office, out of which 5 are in the manager's office, 29 in the Engineering and Operation Division and 20 in the Administrative & Finance Division. Note that the number of whole staff in the Region XII including the subordinate irrigation management offices comes to 309. With regard to the Cotabato Irrigation Management Office, there are total 93 staff under the Division Manager. The Maridagao River Irrigation System is manned with a total of 21 staff.

Table 5.5.3 NIA's Staff Allocation in Regional XII and Cotabato Irrigation Management Office

Division/ Section	Authorized	Filled Positions
NIA Region XII		
Office of the Regional Manager (Region XII)	5	
Engineering and Operation Division	2	
Planning and Design Section	7	
Construction Management Section	4	
Operation Section	4	
Institutional Development Section	4	
Equipment Management Section	8	
Sub total of Engineering and Operation Division	29	
Administrative & Finance Division	2	
Finance Section	7	
Administrative Section	11	
Sub total of Administrative & Finance Division	20	
Total of NIA Region XII	54	Grand total is 309 for the region
Cotabato Irrigation Management Office		
Office of the Division Manager	3	
Engineering Section	5	
Administrative and Finance Section	10	
Operation Maintenance Section		
Kabacan River Irrigation System (RIS)	12	
Libungan RIS	21	
M'lang-Masila RIS	21	
Maridagao RIS	21	In charge of MMIP completed area
Total of Cotabato Irrigation Management Office (Region XII)	93	

Source: NIA Region XII and Cotabato Irrigation Management Office, May, 2017

5.5.3 NIA MMIP II Project Management Office (PMO)

NIA MMIP II PMO is in charge of the on-going construction works of MMIP II. PMO is directly

² There are total 4 irrigation management offices under Region XII office; namely, Cotabato Irrigation Management Office (IMO), South Cotabato-Sarangani IMO, Sultan Kudarat IMO, Maguindanao-Lanao Del Sur-Basilan-Sulu-Tawi-Tawi IMO.

under Engineering and Operation Sector of the central office. Though the PMO structure is basically similar to that of central office, it is simplified as there are only 2 divisions under the Project Manager; Administrative and Finance Division and Engineering Division as shown in the Figure 5.5.3. The MMIP II PMO is located in Midsayap, opposite side of the Region XII Office, and there are as of May 30, 2017, 192 staff in total composed of 22 monthly co-terminous, 74 casual employment and 96 service/ job contracts.




Figure 5.5.3 Organizational Structure of MMIP II PMO

Source: NIA MMIP II PMO

5.5.4 Implementation Arrangement for the Remaining MMIP II

In implementing the remaining works of MMIP II, there should be an institutional arrangement, which should of course be established based on the existing on-going organizational set up. To complete the implementation of the remaining works of MMIP II, setting up of Steering Committee (SC) at the NIA central level, comprising of 5 divisions of NIA and ATI central office, and coordination mechanism with the PMO being the center at the site level, comprising of the relevant organizations, should be as in the Figure 5.5.4:

This SC/PMO arrangement is proposed, as afore-mentioned, basically with reference to that of the on-going MMIP II. The major difference from the on-going arrangement is the inclusion of Agriculture Training Institute (ATI) at the central level since ATI is to be engaged in agriculture and extension development activities to be conducted within the MMIP area. The SC should be chaired by the Administrator and the secretariat should be the manager of Engineering Department. Also, JICA Philippines office may participate to follow up the implementation of MMIP II.

With the foregoing, the SC is to facilitate smooth project implementation through proper budget allocation, provision of necessary technical guidance, and control of budget expenditures. The SC has responsibility and authority on all activities such as planning, coordination between divisions, management at the central level, etc. Also, SC has the authority to supervise financial and accounting section as well in order to secure sufficient financial resources and appropriate payment for smooth project implementation. In addition, two working groups will be established at the SC, namely;

- 1) Accounting & Disbursement Management Group: Accounting & Disbursement Management

Group takes responsibility of managing the accounting and disbursement status and internal procedure based on the report from the PMO. Accounting & Disbursement Management Group will be comprised of members of Accounting Division and Budget and Revenue Division of the NIA central office.

- 2) Project Monitoring & Evaluation Group: A project monitoring report should be compiled as per NIA’s internal procedure. In order to monitor the project progress and to ensure preparation of the monitoring report without delay, the Project Monitoring & Evaluation Group manages the necessary internal procedures for the preparation of the report. The Project Monitoring and Evaluation Group should be comprised of members of Construction Management Division.

At the field level, though the current PMO structure can be retained as it is, there should be an explicit coordination mechanism which should include MILF task force, municipalities, e.g. Pikit Municipality, NIA Region XII office with Cotabato Irrigation Management Office and ATI Region XII office with the outreach office of ATI located in Kabacan. MILF task force, with municipalities, will coordinate NIA-PMO in the issues of security as well as contacting the beneficiary and project to-be-affected peoples. Cotabato IMP under the Region XII office will take-over the irrigation system upon completion, and the ATI outreach office (Kabacan), controlled by its Region XII office (Tantangan), will provide agriculture extension services to the beneficiary farmers.




Figure 5.5.4 Project Implementation Arrangement

Source: JICA Survey Team

CHAPTER 6 PROJECT EVALUATION

6.1 Condition, Methodology and Evaluation Cases

In this chapter, an economic evaluation is performed to determine the economic viability of the Project. In order to examine the proposed project plan, internal rate of return is calculated as the economic indicator. Net present value and B/C are also calculated as supplemental indices. The methodologies and results are shown as follows:

6.1.1 Basic Condition and Assumptions

- 1) Referring to other similar projects in the irrigation/agriculture sector, the economic life of the project related to agriculture production is designed as 30 years. It means that economic evaluations are encoded over this period of 30 years considering the initial investments including operation and maintenance costs to accrue.
- 2) Project cost and benefit are calculated in Philippines Peso (Php). All cost and benefit are calculated adopting the level of June 2018 price, standardized by using consumer price index (CPI) and construction materials wholesale price index (CMWPI).
- 3) For the operation and maintenance cost calculation, one (1) percentages for Case-1 and two (2) percentage for Case-2 of the total costs are applied. The Cases are detailed in Chapter 6.1.2.
- 4) In the evaluation, the foreign exchange rate of 1 Php = 2.07 JPY is applied as of June 2018.
- 5) As per the Social Discount Rate in the Philippine, according to NEDA, generally 10% is applied with practices of similar investment projects in the irrigation/agriculture sector in the Country. In this economic evaluation, the EIRR should therefore be more than 10% or more, otherwise the investment cannot be justified.
- 6) Transfer costs such as import tax, VAT, and interests are eliminated from the economic cost. Also, price contingency (inflation) cost is not counted in the economic evaluation, while physical contingency is counted in the evaluation.
- 7) Table 6.1.1 shows conversion factors which are applied to estimate economic costs/prices. Note that conversion factors are not standardized in Philippines, so that the Standard Conversion Factor (SCF) which was employed in “Philippine Rural Development Project”; World Bank, 2014, is applied in this economic evaluation (see Table 6.1.1).

Table 6.1.1 Applied Conversion Factors

Particulars	Factor	Reference
Standard Conversion Factor (SCF)	0.90	Philippine Rural Development Project, World Bank, 2014
Skilled Labor	1.00	Assumed placed under competitive market
Unskilled Labor/ Family Labor	0.60	Philippine Rural Development Project, World Bank, 2014

Source: JICA Survey Team

6.1.2 Cases for Project Evaluation

Basic Cases: There are two cases to be analyzed in the evaluation. In Case-1, by constructing only part of the irrigation canals with all drainage, the irrigation water would be supplied for a part of LMSA. On the other hand, in Case-2, by constructing all irrigation canals and drainage canals as per the original design for Lower Malitbog Service Area (LMSA), the LMSA can be benefitted during dry season (note that during rainy season, parts of LMSA would be affected by flooding):

Table 6.1.2 Cases for Project Evaluation

Case	Notation	Beneficial Areas	Detail
Case-1	C1	Part of LMSA	Construct only part of the irrigation canals with all drainages
Case-2	C2	Whole Area of LMSA	Construct all irrigation canals and drainage canals

Source: JICA Survey Team

The Target Area: The MMIP II Service Areas, total 10,536 ha, is composed of Upper Malitubog Service Area (UMSA) and LMSA. The originally requested ODA target area was the most eastern part of LMSA (2,133ha). Then, the initial target area of this economic analysis covered only the eastern part of LMSA, since the economic analysis aimed to evaluate the economic validity of the ODA project area requested. However, NIA decided to withdraw the MMIP II project from its proposal to be funded by Japan ODA financing, as NIA believes that the remaining balance is too inconsequential to be funded by the ODA loan. Therefore, the economic analysis of the ODA project is no longer necessary. Instead, the economic analysis is done on costs and benefits occurred from NIA's on-going and planned project. In this respect, the Target Area should be LMSA or entire MMIP II Service Area.

Flood Affection Scenario: In rainy season, parts of the Target Service Area are free from flooding, while other parts of the areas are probably affected by flood. The expected flooded areas with 0.5 to 1.0 m inundation are out of target irrigable area in the rainy season. On the other hand, flooded areas of up to 0.5 m could still be considered as a part of target irrigable area, yet the production would be affected by floods. The losses due to the flooding are assumed based on four scenarios; 1) no damage scenario (0% loss in yield; notified as "D00"), 2) partially damaged scenario (30% loss; notified as "D30"), 3) half damaged scenario (50% loss; notified as "D50"), and 4) almost-totally damaged scenario (80% loss; notified as "D80"). The economic analysis is to be conducted by each of the scenarios as sensitivity analysis. To judge economic feasibility of the Project, 30% reduction cases are applied as the "benchmark" case.

In summary, there are four flood damaged scenarios under each of the two cases. It means that there are eight cases in total to be analyzed in the evaluation. In each of eight cases, two target areas are considered i.e. LMSA and entire MMIP II. Table 6.1.3 shows evaluation cases of the Projects in LMSA areas (notified as "LM"). On the other hand, Table 6.1.4 shows evaluation cases in MMIP II whole area (notified as "M2"). In total, therefore, there are 16 cases to be evaluated:

Table 6.1.3 Evaluation Cases Only for LMSA Area

Case	Crop	Dry Season			Wet Season			Total Production (ton)
		Planted Area (ha)	Yield (ton/ha)	Production (ton)	Planted Area (ha)	Yield (ton/ha)	Production (ton)	
-	Without Project							
-	Rice (rain-fed)	457	1.7	777	367	1.7	624	1,401
-	Corn	795	2.1	1,670	1,087	2.1	2,283	3,953
C1	With Project (Case-1)							
C1-LM-D00	Rice (Irrigated)	3,688	4.7	17,334	2,810	4.7	13,207	30,541
C1-LM-D30	30% reduction	3,688	4.7	17,334	870	4.7	4,089	27,631
					1,940	3.2	6,208	
C1-LM-D50	50% reduction	3,688	4.7	17,334	870	4.7	4,089	25,885
					1,940	2.3	4,462	
C1-LM-D80	80% reduction	3,688	4.7	17,334	870	4.7	4,089	23,169
					1,940	0.9	1,746	
C2	With Project (Case-2)							
C2-LM-D00	Rice (irrigated)	6,590	4.7	30,973	3,810	4.7	17,907	48,880
C2-LM-D30	30% reduction	6,590	4.7	30,973	870	4.7	4,089	44,470
					2,940	3.2	9,408	
C2-LM-D50	50% reduction	6,590	4.7	30,973	870	4.7	4,089	41,824
					2,940	2.3	6,762	
C2-LM-D80	80% reduction	6,590	4.7	30,973	870	4.7	4,089	37,708
					2,940	0.9	2,646	

Source: JICA Survey Team

Table 6.1.4 Evaluation Cases for all MMIP II Area

Case	Crop	Dry Season			Wet Season			Total Production (ton)
		Planted Area (ha)	Yield (ton/ha)	Production (ton)	Planted Area (ha)	Yield (ton/ha)	Production (ton)	
-	Without Project							
-	Rice (rain-fed)	731	1.7	1,242	587	1.7	997	2,240
-	Corn	1,271	2.1	2,669	1,738	2.1	3,650	6,319
C1	With Project (Case-1)							
C1-M2-D00	Rice (Irrigated)	7,634	4.7	35,880	6,756	4.7	31,753	67,633
C1-M2-D30	30% reduction	7,634	4.7	35,880	4,816	4.7	22,635	64,723
					1,940	3.2	6,208	
C1-M2-D50	50% reduction	7,634	4.7	35,880	4,816	4.7	22,635	62,977
					1,940	2.3	4,462	
C1-M2-D80	80% reduction	7,634	4.7	35,880	4,816	4.7	22,635	60,261
					1,940	0.9	1,746	
C2	With Project (Case-2)							
C2-M2-D00	Rice (irrigated)	10,536	4.7	49,519	7,756	4.7	36,453	85,972
C2-M2-D30	30% reduction	10,536	4.7	49,519	4,816	4.7	22,635	81,562
					2,940	3.2	9,408	
C2-M2-D50	50% reduction	10,536	4.7	49,519	4,816	4.7	22,635	78,916
					2,940	2.3	6,762	
C2-M2-D80	80% reduction	10,536	4.7	49,519	4,816	4.7	22,635	74,800
					2,940	0.9	2,646	

Source: JICA Survey Team

6.2 Economic Term of Project Cost and Benefit

6.2.1 Economic Term of Project Cost

The project costs are composed of foreign currency and local currency portions. Both foreign and local currency portions are further categorized into direct and indirect cost. As for direct cost, it is divided into skilled labor, unskilled labor, and other material portions to apply appropriate conversion factors. As indirect costs, physical contingency, land acquisition cost, and administration costs are taken into account as economic cost. Note that other indirect costs such as price escalation, interests, import tax and VAT are not included in the economic cost, because they can be assumed to be neutral on economic analysis, and negligible.

Regarding the costs that have been already expended by the year 2018, they should be converted into current price level, by using construction materials wholesale price index. On the other hand, the costs from 2019 are evaluated at the current price level. Table 6.2.1 – Table 6.2.5 show financial and economic costs after the conversion:

Table 6.2.1 Financial and Economic Cost (Case 1; LMSA), Million Peso

Component	Financial Cost			Economic Cost		
	FC	LC	Total	FC	LC	Total
Construction Cost	963.2	1,444.9	2,408.1	963.2	1,300.4	2,263.6
Other Material	898.5	999.4	1,898.0	898.5	899.5	1,798.0
Skilled Labor	41.0	235.8	276.8	41.0	235.8	276.8
Unskilled Labor	23.7	209.7	233.4	23.7	140.0	163.7
Land Acquisition	32.1	48.1	80.2	32.1	43.3	75.4
Consultant Fee	0.0	0.0	0.0	0.0	0.0	0.0
Administration Fee	52.2	78.3	130.5	52.2	70.5	122.7
Base Cost	1,048	1,571.3	2,618.8	1,047.5	1,414.1	2,461.6
Physical Contingency	51.9	77.8	129.7	51.9	70.7	122.6
BC+PhC	1,099	1,649.1	2,748.4	1,099.4	1,484.8	2,584.2

Source: JICA Survey Team; the Cost Includes irrigation canals, drainage, and agriculture extension works.

Note: The costs that has already expended by 2018 are converted into current price level by using CMWPI

Table 6.2.2 Financial and Economic Cost (Case 2; LMSA), Million Peso

Component	Financial Cost			Economic Cost		
	FC	LC	Total	FC	LC	Total
Construction Cost	1,286.0	1,929.0	3,215.0	1,286.0	1,736.1	3,022.1
Other Material	1,205.2	1,338.3	2,543.5	1,205.2	1,204.5	2,409.7
Skilled Labor	49.1	308.4	357.5	49.1	308.4	357.5
Unskilled Labor	31.7	282.3	314.0	31.7	188.4	220.2
Land Acquisition	38.1	57.1	95.2	38.1	51.4	89.5
Consultant Fee	0.0	0.0	0.0	0.0	0.0	0.0
Administration Fee	69.4	104.1	173.5	69.4	93.7	163.1
Base Cost	1,393	2,090.2	3,483.7	1,393.5	1,881.2	3,274.7
Physical Contingency	67.2	100.8	168.0	67.2	94.0	161.3
BC+PhC	1,460.7	2,191.0	3,651.7	1,460.7	1,975.2	3,435.9

Source: JICA Survey Team; the Cost Includes irrigation canals, drainage, and agriculture extension works.

Note: The costs that has already expensed by 2018 are converted into current price level by using CMWPI

Table 6.2.3 Financial and Economic Cost (Case 1; MMIP II), Million Peso

Component	Financial Cost			Economic Cost		
	FC	LC	Total	FC	LC	Total
Construction Cost	1,654.4	2,481.6	4,135.9	1,654.4	2,233.4	3,887.8
Other Material	1,555.1	1,725.1	3,280.2	1,555.1	1,552.6	3,107.7
Skilled Labor	58.3	391.3	449.6	58.3	391.3	449.6
Unskilled Labor	40.9	365.2	406.1	40.9	243.7	284.6
Land Acquisition	57.2	85.8	143.1	57.2	77.3	134.5
Consultant Fee	0.0	0.0	0.0	0.0	0.0	0.0
Administration Fee	88.6	132.9	221.6	88.6	119.7	208.3
Base Cost	1,800	2,700.3	4,500.6	1,800.2	2,430.3	4,230.5
Physical Contingency	64.1	96.2	160.3	64.1	121.5	185.6
BC+PhC	1,864.3	2,796.5	4,660.9	1,864.3	2,551.8	4,416.2

Source: JICA Survey Team; the Cost Includes irrigation canals, drainage, and agriculture extension works.

Note: The costs that has already expensed by 2018 are converted into current price level by using CMWPI

Table 6.2.4 Financial and Economic Cost (Case 2; MMIP II), Million Peso

Component	Financial Cost			Economic Cost		
	FC	LC	Total	FC	LC	Total
Construction Cost	1,977.1	2,965.7	4,942.9	1,977.1	2,669.1	4,646.3
Other Material	1,861.8	2,064.0	3,925.8	1,861.8	1,857.6	3,719.4
Skilled Labor	66.4	463.9	530.3	66.4	463.9	530.3
Unskilled Labor	49.0	437.8	486.8	49.0	292.1	341.1
Land Acquisition	63.2	94.8	158.1	63.2	85.4	148.6
Consultant Fee	0.0	0.0	0.0	0.0	0.0	0.0
Administration Fee	105.8	158.8	264.6	105.8	142.9	248.7
Base Cost	2,146	3,219.3	5,365.5	2,146.2	2,897.4	5,043.6
Physical Contingency	79.5	119.2	198.6	79.5	144.9	224.3
BC+PhC	2,225.7	3,338.5	5,564.1	2,225.7	3,042.2	5,267.9

Source: JICA Survey Team; the Cost Includes irrigation canals, drainage, and agriculture extension works.

Note: The costs that has already expensed by 2018 are converted into current price level by using CMWPI

6.2.2 Economic Term of Project Benefit

The project benefits are composed of two major sources; the first one is 1) the yield increase owing to additional water supply and agriculture extension activities, and the second one is 2) the cultivation area increase after adequate irrigation water to be availed. The project benefit is calculated as the difference of aggregated net benefits between with and without project.

As per former benefit, it can be a natural assumption that the current yield level under rain-fed cultivation will be increased immediately upon the construction up to the average irrigated rice level, i.e., 3.4 ton per ha. Further yield increase up to the target yield level, i.e., 4.7 ton per ha, is supposed to be achieved through agriculture extension. Such extension activities may need several years; 0% in the

first year of the construction completion (assumed that extension is still in the preparation stage), 30% in the 2nd year (assumed that even extension have been commenced, farmers have not applied the technology yet), 60% in the 3rd year, and 100% in the 4th years and onwards after the completion of the Project. Table 6.2.5 illustrates applied target yields by means of extension.

Table 6.2.5 Applied Target Yields of Extension by Year

Year of Extension	Before Construction		1st Year After construction		2nd Year After construction		3rd Year After construction		After Extension	
	Dry	Rainy	Dry	Rainy	Dry	Rainy	Dry	Rainy	Dry	Rainy
Season	Dry	Rainy	Dry	Rainy	Dry	Rainy	Dry	Rainy	Dry	Rainy
Percentage, %	0%	0%	0%	0%	30%	30%	60%	60%	100%	100%
Yield Level, ton/ha	2.5	2.5	3.4	3.4	3.8	3.8	4.2	4.2	4.7	4.7

Source: JICA Survey Team.

Note: The Yield Level Difference from "Before Construction" up to "1st Year" is equivalent to the gap between averages of rain-fed paddy and irrigation paddy.

Currently, the dominant crops in the unirrigated areas of the LMSA are rain-fed paddy and corn. With the project, these crops are supposed to be substituted by irrigated rice as MMIP I area has experienced. In fact, according to cost and return calculations based on the results of household survey conducted by the JICA Team, 2017, generally, irrigated rice seems to be more profitable than rain-fed paddy and corn. To illustrate this, one may compare net profits of Table 6.2.2 and Table 6.2.3. Differences of profits between irrigated and rain-fed paddy are 13,619 (=32,668-19,049) pesos, and 22,234 (=32,668-10,434) pesos for paddy and corn, respectively, in financial terms.

Further yield increase can be expected with extension activities implemented. The SAPROF report (May 2007) proposed that the target yields which can be accomplished after the irrigation facilities completion were 4.95 ton per ha and 4.77 ton per ha, in dry season and rainy season, respectively. According to the previous report, a realistic assumption is that the yields in target areas can potentially increase up to 4.7 ha¹.

Assumption mentioned above implies that the farmers can get more income even at the same size of cultivation. Moreover, it is expected that the cultivation area would be increased after supply of adequate irrigation water, as shown in Table 6.1.3 and Table 6.1.4. The additional income due to the cultivation area increase is the second major project benefits.

Table 6.2.6 Cost and Return Calculation for Rain-fed Crops

Items	Financial Price		Economic Price	
	Rain-fed Paddy	Corn	Rain-fed Paddy	Corn
Yield	1.7	2.1	1.7	2.1
Farm-gate Price, 2018 Price Level	17.2	11.1	15.6	10.0
Gross Profit	29,274	23,614	26,347	21,252
Total Cost, 2018 Price Level	10,225	13,180	8,787	10,361
Net Profit	19,049	10,434	17,560	10,892
Return Ratio	65.1%	44.2%	66.6%	51.2%

Source: JICA Survey Team based on household survey conducted in June 2018.

Note 1) Farm-gate Prices are converted to June 2018 price level by applying Consumer Price Index (CPI)

2) Farm-gate Price of irrigated paddy is referred data collected from Philippines Statistic Authority June 2018.

3) Manipulated Cost is not taken into account for financial cost.

4) Tax and Interest payment are not considered in economic cost because it is zero-sum on viewpoint of national economy.

¹ In fact, YLTA Terminal Report prepared by ATI suggests that the yields of irrigated paddy were 5.52 ton/ha (dry) and 5.63 ton/ha (wet), averaged 368 farmers from 7 IAs in Phase 1.

Table 6.2.7 Cost and Return Calculation for Irrigated Paddy

Items	Financial Price		Economic Price	
	Irrigated Paddy woTA	Irrigated Paddy wTA	Irrigated Paddy woTA	Irrigated Paddy wTA
Yield	3.4	4.7	3.4	4.7
Farm-gate Price, 2018 Price Level	20.4	20.4	18.4	18.4
Gross Profit	68,988	95,880	62,089	86,480
Total Cost, 2018 Price Level	36,320	50,443	27,728	38,657
Net Profit	32,668	45,447	34,361	47,823
Return Ratio	47.4%	47.4%	55.3%	55.3%

Source: JICA Survey Team Based on Philippine National Statistic Authority 2013, taking simple average of Region XII and ARMM.

Note 1) Farm-gate Prices are converted to May 2018 price level by applying Consumer Price Index (CPI)

2) Manipulated Cost is not taken into account for financial cost.

3) Tax and Interest payment are not considered in economic cost because it is zero-sum on a viewpoint of national economy

4) Assume that net return ratio is constant between wo/TA and w/TA. Based on the assumption, total cost for irrigated paddy with TA is calculated as the product of gross profit and return ratio.

For simplicity, the project benefit owing to irrigation and drainage rehabilitation would accrue at the same proportion of the total budget disbursed till the previous year. Table 6.2.8 and Table 6.2.9 show the benefit generation process by year:

Table 6.2.8 Percentages Indicating Benefit Generation Process by Year (LMSA)

Year	2011	2012	2013	2014	2015	2016	2017	2018
Area Increase	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	4.2%	22.9%
Yield Increase	0%	0%	0%	0%	0%	0%	1%	8%
Year	2019	2020	2021	2022	2023	2024	2025	After 2026
Area Increase	44.9%	62.3%	69.2%	72.1%	80.7%	92.3%	100.0%	100.0%
Yield Increase	22%	41%	58%	71%	81%	90%	97%	100%

Source: JICA Survey Team

Table 6.2.9 Percentages Indicating Benefit Generation Process by Year (MMIP2)

Year	2011	2012	2013	2014	2015	2016	2017	2018
Area Increase	0.0%	5.6%	11.2%	16.8%	22.5%	31.2%	37.1%	49.4%
Yield Increase	0%	6%	11%	17%	22%	31%	33%	38%
Year	2019	2020	2021	2022	2023	2024	2025	After 2026
Area Increase	63.8%	75.3%	79.8%	81.7%	87.3%	94.9%	100.0%	100.0%
Yield Increase	49%	61%	73%	81%	87%	93%	98%	100%

Source: JICA Survey Team

6.3. Results of Economic Analysis

6.3.1 Calculation of EIRR, NPV and B/C

The result of economic analysis is summarized in Table 6.3.1. As a whole, EIRR of MMIP II performs relatively well; 10.07% as of 30% reduction scenario in Case-1, and 10.73% as of 30% reduction scenario in Case-2, respectively. On the other hand, considering only the part of LMSA, this case is not economically viable; EIRR is 6.57% even as of no reduction scenario in Case 1, and EIRR is 8.19% as of no reduction scenario in Case-2, due to the large unit cost against the beneficial areas compared to other areas.

If flooding would affect more than 50% in production in flooded areas of up to 0.5 m, the project is not economically viable. For example, EIRR is 9.68% as of 50% reduction scenario in Case-1, and 9.07% as of 80% reduction case in Case-1 of MMIP II areas. The result implies that the economic efficiency is sensitive to hydrological situation of the sites.

If one compares “Case-1” and “Case-2” when other conditions are same, EIRRs in Case-2 are always a bit higher than those of Case-1. For example, the EIRRs are 10.07% as of 30% reduction scenario in

Case-1 and 10.73% as of 30% reduction scenario in Case-2 of MMIP II areas. These results may suggest that Case-2, in that irrigation canals are to be constructed as per the original design, could be recommendable in terms of economic efficiency; however, in Case-2, much maintenance works should be expected and therefore NIA should well be prepared for the payment of routine expensive maintenance (maintenance cost of Case-2 is estimated at 2 times that of Case-1).

On the viewpoint of feasibility analysis of NIA, it is better to evaluate entire MMIP II (namely, “M2” cases). According to the results, the EIRR exceeds 10% of social discount ratio in this Country in 30% reduction case that the JICA Team considers as the “benchmark”. Then, the conclusion gained through the economic analysis is that the project is economically viable.

Table 6.3.1 Summary of Annual Net Benefit, EIRR, NPV, and B/C

SN	Case	Annual Benefit (Million Php)	IRR (%)	NPV (Million Php)	B/C
1	C1-LM-D00	244.2	6.57%	-787.6	0.74
2	C1-LM-D30	217.7	5.40%	-1,030.6	0.65
3	C1-LM-D50	201.7	4.66%	-1,175.8	0.61
4	C1-LM-D80	176.9	3.43%	-1,402.6	0.53
5	C2-LM-D00	402.2	8.19%	-533.6	0.87
6	C2-LM-D30	364.6	6.96%	-876.9	0.79
7	C2-LM-D50	340.5	6.14%	-1,097.9	0.74
8	C2-LM-D80	302.9	4.79%	-1,441.4	0.65
9	C1-M2-D00	562.2	10.90%	423.6	1.07
10	C1-M2-D30	535.7	10.07%	35.1	1.01
11	C1-M2-D50	519.7	9.68%	-150.8	0.98
12	C1-M2-D80	494.9	9.07%	-440.3	0.93
13	C2-M2-D00	729.7	11.87%	940.8	1.13
14	C2-M2-D30	689.5	10.73%	374.0	1.05
15	C2-M2-D50	665.3	10.18%	91.5	1.01
16	C2-M2-D80	627.7	9.32%	-347.4	0.95

Source: JICA Survey Team Net Present Value is calculated with 10% of Social Discount Ratio




Figure 6.3.1 Comparison of EIRR by Evaluation Case
Source: JICA Survey Team

6.4 Farm Budget Analysis

To analyze project impacts on individual farmer’s viewpoints, a farm budgetary analysis has been conducted. The calculation methodologies are shown below:

Firstly, it is assumed that beneficial areas in LMSA under the present condition of total 2,002 ha (in rainy season) would go up to 7,634 ha if part of development plan will be implemented (Case-1), and would further increase to 10,536 ha if all of the development plan will be implemented as per the original plan (Case-2). Dividing the beneficial areas by average farmland areas, the number of beneficiaries is estimated, which are 1,601 Farmer House Holds (FHHs) at present. After the construction completed, the number of beneficiaries of LMSA would be increased to 6,107 FHH (Case-1) and 8,429 FHH (Case-2), respectively.

Total financial net profit is defined as annual total profit for the whole beneficiaries in a year. At the present condition, total financial net profit of 56.1 million Php is generated by 1,601 FHHs. Upon the project implementation completed, two types of major benefits are to be accrued; 1) the yield increase owing to additional water supply and agriculture extension services; and 2) the cultivation area increase after adequate irrigation water to be availed. Thanks to these benefits, such incremental farm incomes would accrue as shown in Row (7) and Row (8) of Table 6.4.1.

Table 6.4.1 Farm Budget Analysis by the Evaluation Case

SN	Case	Beneficial Area without Project (ha)	Beneficial Area after Project (ha)	Average Farmland Area (ha/FHH)	Estimated No. of Farm Household without Project (FHHs)	Estimated No. of Farm Household with Project (FHHs)	Total Financial Net Profit without Project (Million Php)
		(1)	(2)	(3)	(4)=(1)/(3)	(5)=(2)/(3)	(6)
1	C1-M2-D00	2,002	7,634	1.25	1,601	6,107	56.1
2	C1-M2-D30	2,002	7,634	1.25	1,601	6,107	56.1
3	C1-M2-D50	2,002	7,634	1.25	1,601	6,107	56.1
4	C1-M2-D80	2,002	7,634	1.25	1,601	6,107	56.1
5	C2-M2-D00	2,002	10,536	1.25	1,601	8,429	56.1
6	C2-M2-D30	2,002	10,536	1.25	1,601	8,429	56.1
7	C2-M2-D50	2,002	10,536	1.25	1,601	8,429	56.1
8	C2-M2-D80	2,002	10,536	1.25	1,601	8,429	56.1

Source: JICA Survey Team

Table 6.4.1 Farm Budget Analysis by the Evaluation Case (Continued)

SN	Case	Financial Annual Benefit sourced from Area Increase (Million Php)	Financial Annual Benefit sourced from Yield Increase (Million Php)	Financial household farming Income without Project (Php/FHH)	Per household Income Increase owing Area Increase (Php/FHH)	Per household Income Increase owing Yield Increase (Php/FHH)	Financial household farming Income with Project (Php/FHH)
		(7)	(8)	(9)	(10-a)	(10-b)	(11)
1	C1-M2-D00	414.4	147.8	35,013.2	67,857.6	24,205.7	127,076.4
2	C1-M2-D30	387.8	147.8	35,013.2	63,505.5	24,205.7	122,724.3
3	C1-M2-D50	371.9	147.8	35,013.2	60,894.3	24,205.7	120,113.1
4	C1-M2-D80	347.1	147.8	35,013.2	56,832.3	24,205.7	116,051.2
5	C2-M2-D00	547.5	182.3	35,013.2	64,948.5	21,625.4	121,587.0
6	C2-M2-D30	507.2	182.3	35,013.2	60,169.9	21,625.4	116,808.5
7	C2-M2-D50	483.0	182.3	35,013.2	57,302.8	21,625.4	113,941.4
8	C2-M2-D80	445.4	182.3	35,013.2	52,842.9	21,625.4	109,481.4

Source: JICA Survey Team

Table 6.4.1 Farm Budget Analysis by the Evaluation Case (Continued)

SN	Case	Financial non-Farming Income (Php/FHH)	Financial non-Farming Income (Php/FHH)	Financial household Income without	Financial household Income with	Ratio b/t with & without Project
		(12-a)	(12-b)	(13)	(14)	(16)
1	C1-M2-D00	55,954	45,271	90,967	172,347	1.89
2	C1-M2-D30	55,954	45,271	90,967	167,995	1.85
3	C1-M2-D50	55,954	45,271	90,967	165,384	1.82
4	C1-M2-D80	55,954	45,271	90,967	161,322	1.77
5	C2-M2-D00	55,954	45,271	90,967	166,858	1.83
6	C2-M2-D30	55,954	45,271	90,967	162,080	1.78
7	C2-M2-D50	55,954	45,271	90,967	159,212	1.75
8	C2-M2-D80	55,954	45,271	90,967	154,752	1.70

Source: JICA Survey Team

Dividing the total financial net profit by the numbers of beneficiaries, per farmer household's cropping income is estimated under the present/future conditions, which are shown in Row (9) and (11). However, a typical farmer normally has other income sources. According to the results of household survey conducted by the JICA Team in June 2017, a typical farmer in rain-fed areas earned 55,954 Php from non-cropping e.g. migrant works, livestock breeding and selling being composed of more than half of total income. On the other hand, a typical farmer in irrigable areas earned slightly less amount of non-cropping income i.e. 45,271 Php on average. Considering these, financial household incomes at without/with conditions are estimated and summarized in Row (13) and (14), as a sum of cropping and

non-cropping income.

The result of analysis in Row (16) shows that the potential income increment rate could be 70% to 89% from the present condition upon the project implementation. Since poverty reduction is one of the main agenda of the area, the income improvement should contribute to the regional development as well as to the social unification in the area.

6.5 Proposed Indicators for Project Operation and Effects

Several indicators are proposed in order to measure the project impacts by comparing before- and after-project. There are two types of indicators; namely, operation and effect indicators. Operation indicator aims to measure operational status of the project, while effect indicator aims at measuring generated effects. In other words, after the facility construction by the project, how the improved facilities are utilized properly is evaluated by the operation indicator, and how effects are caused to the beneficiaries by the improved facilities is evaluated by effect indicator.

The proposed operation indicator of Irrigation and Drainage Improvement is “*Total Cultivated Area by the Beneficiaries*” which aims to measure the performance of irrigation and drainage facilities. Further, the effect indicator for irrigation and drainage system aims to monitor how the facilities make effect on beneficiaries and the target area, so the proposed indicator should be the increase in “*Gross Annual Average Farming Income*” per farmer household.

One might think that “*Net Annual Average Farming Income*” reflects the effect more exactly. It is true; however, one of the desirable features as a good effect indicator is “the easiness to collect data”, but it is not a trivial work to capture all of farming costs. Therefore, the Team proposes “*Gross Annual Average Farming Income*” as the basic effect indicator, and “*Net Annual Average Farming Income*” is proposed only for a secondary effect indicator.

For agriculture extension component, the effect indicator should be “*Average Yields of Major Crops per Ha*” because yield increase is one of the major expected outcomes of the project and the component should be responsible for it.

Table 6.5.1 Proposed Operation and Effect Indicator (Case-1, LMSA)

Operation Indicator		Effect Indicator	
Definition: Total Cultivated Area by The Beneficiaries (Ha)		Definition: 1. Gross Annual Average Farming Income (Php/Year/Household) 2. Net Annual Average Farming Income (Php/Year/Household)	
Method of Data Collection: Interview to NIA		Method of Data Collection: Reference to Farmer Household Survey Result	
Baseline (2018)	Target (3 years after Completion)	Baseline (2018)	Target (3 years after Completion)
Rainy: Paddy 367.0 ha Corn 1,087.0 ha Dry: Paddy 457.0 ha Corn 795.0 ha	Rainy Paddy 2,810.0 ha Dry: Paddy 3,688.0 ha	1. Gross Profit: 58,438 Php/FHH 2. Net Profit: 30,148 Php/FHH 3. Yield Paddy: 2.1 ton/ha Corn: 1.7 ton/ha	1. Gross Profit: 190,792 Php /FHH 2. Net Profit: 103,929 Php /FHH 3. Yield Paddy: 3.4 ton/ha (wo TA) Paddy: 4.7 ton/ha (w TA)
Remarks: Gross Profit and Net Profit are calculated based on D30 cases; the Target cultivated area of irrigation paddies is the sum of flood unaffected areas and flooded areas of up to 0.5 m			

Source: JICA Survey Team

Table 6.5.2 Proposed Operation and Effect Indicator (Case-2, LMSA)

Operation Indicator		Effect Indicator	
Definition: Total Cultivated Area by The Beneficiaries (Ha)		Definition: 1. Gross Annual Average Farming Income (Php/Year/Household) 2. Net Annual Average Farming Income (Php/Year/Household)	
Method of Data Collection: Interview to NIA		Method of Data Collection: Reference to Farmer Household Survey Result	
Baseline (2018)	Target	Baseline (2018)	Target (3 years after

Operation Indicator		Effect Indicator	
	(3 years after Completion)		Completion)
Rainy: Paddy 367.0 ha Corn 1087.0 ha Dry: Paddy 457.0 ha Corn 795.0 ha	Rainy Paddy 3,810.0 ha Dry: Paddy 6,590.0 ha	1. Gross Profit: 58,438 Php/FHH 2. Net Profit: 30,148 Php/FHH 3. Yield Paddy: 2.1 ton/ha Corn: 1.7 ton/ha	1. Gross Profit: 168,941 Php /FHH 2. Net Profit: 99,313 Php /FHH 3. Yield Paddy: 3.4 ton/ha (wo TA) Paddy: 4.7 ton/ha (w TA)
Remarks: Gross Profit and Net Profit are calculated based on D30 cases; the Target cultivated area of irrigation paddies is the sum of flood unaffected areas and flooded areas of up to 0.5 m			

Source: JICA Survey Team

Table 6.5.3 Proposed Operation and Effect Indicator (Case-1, MMIP)

Operation Indicator		Effect Indicator	
Definition: Total Cultivated Area by The Beneficiaries (Ha)		Definition: 1. Gross Annual Average Farming Income (Php/Year/Household) 2. Net Annual Average Farming Income (Php/Year/Household)	
Method of Data Collection: Interview to NIA		Method of Data Collection: Reference to Farmer Household Survey Result	
Baseline (2018)	Target (3 years after Completion)	Baseline (2018)	Target (3 years after Completion)
Rainy: Paddy 586.8 ha Corn 1,737.9 ha Dry: Paddy 730.6 ha Corn 1,271.0 ha	Rainy Paddy 6,756.0 ha Dry: Paddy 7,634.0 ha	1. Gross Profit: 67,869 Php/FHH 2. Net Profit: 35,013 Php/FHH 3. Yield Paddy: 2.1 ton/ha Corn: 1.7 ton/ha	1. Gross Profit: 215,885 Php /FHH 2. Net Profit: 122,724 Php /FHH 3. Yield Paddy: 3.4 ton/ha (wo TA) Paddy: 4.7 ton/ha (w TA)
Remarks: Gross Profit and Net Profit are calculated based on D30 cases; the Target cultivated area of irrigation paddies is the sum of flood unaffected areas and flooded areas of up to 0.5 m			

Source: JICA Survey Team.

Table 6.5.4 Proposed Operation and Effect Indicator (Case-2, MMIP2)

Operation Indicator		Effect Indicator	
Definition: Total Cultivated Area by The Beneficiaries (Ha)		Definition: 1. Gross Annual Average Farming Income (Php/Year/Household) 2. Net Annual Average Farming Income (Php/Year/Household)	
Method of Data Collection: Interview to NIA		Method of Data Collection: Reference to Farmer Household Survey Result	
Baseline (2018)	Target (3 years after Completion)	Baseline (2018)	Target (3 years after Completion)
Rainy: Paddy 586.8 ha Corn 1,737.9 ha Dry: Paddy 730.6 ha Corn 1,271.0 ha	Rainy Paddy 7,756.0 ha Dry: Paddy 10,536.0 ha	1. Gross Profit: 67,869 Php/FHH 2. Net Profit: 35,013 Php/FHH 3. Yield Paddy: 2.1 ton/ha Corn: 1.7 ton/ha	1. Gross Profit: 197,108 Php /FHH 2. Net Profit: 116,809 Php /FHH 3. Yield Paddy: 3.4 ton/ha (wo TA) Paddy: 4.7 ton/ha (w TA)
Remarks: Gross Profit and Net Profit are calculated based on D30 cases; the Target cultivated area of irrigation paddies is the sum of flood unaffected areas and flooded areas of up to 0.5 m			

Source: JICA Survey Team

CHAPTER 7 ENVIRONMENTAL AND INDIGENOUS PEOPLE CONSIDERATION

7.1 Project Components

The Project area of MMIP, which starts at the diversion dam established at the Maridagao River, is divided into MMIP I area and MMIP II area. The construction works in MMIP I area was completed in 2011, while those of MMIP II have been started in 2011. MMIP II is further sub-divided into three areas, namely, Upper Malitubog and Lower Malitubog and Pagalungan. Construction works in Upper Malitubog has been already done, while those in Lower Malitubog have been started partly. In southeastern part of Lower Malitubog area, no construction works have begun. In the shaded (diagonal green lines) portion in the figure below, no works have been started, since it was planned to be covered by Japanese ODA loan according to the initial request, however, it is worthy to note that the request was withdrawn by NIA in June 2018.




Figure 7.1.1 Location of MMIP II Area

Source: JICA Survey Team (modified from the map "Malitubog Maridagao Irrigation Project" prepared by NIA)

Two cases, namely, Case-1 and Case-2 were examined. Case-1 is to construct some of the parts of the proposed irrigation system and drainage system within the LMSA without dikes, while Case-2 is to construct the whole components of the planned irrigation system and drainage system within the LMSA without the dikes. The proposed project components are to be implemented under the GOP funding. The total lengths of irrigation canals, drainages and access roads are 72,554 m, 75,801 m and 14,950 m, respectively for Case 1 while 107,274 m, 75,801 m and 18,450 m, respectively for Case 2.

7.2 Legislative and Institutional Framework of Environmental Consideration

7.2.1 Legislative and Institutional System for Environmental Impact Assessment

1) Institutional Framework

The Department of Environment and Natural Resources (DENR) is the lead agency mandated under the Executive Order 192 (1987), responsible for the conservation, management, development, and proper use of the country's environment and natural resources. In order to implement the tasks mentioned, six (6) line bureaus were formed as shown in the following figure: 1) Environmental Management Bureau (EMB); 2) Biodiversity Management Bureau; 3) Land Management Bureau; 4)

Forest Management Bureau; 5) Ecosystems Research and Development Bureau and; 6) Mines and Geosciences Bureau to enforce various national environmental laws and policies. Out of those management bureaus, EMB is responsible for environmental impacts assessment.

EMB is responsible for providing advice to the Department Secretary on matters relating to environmental management. Further, it is also mandated to do, formulation of plans and policies and development of appropriate environmental quality standards (water, air and noise), control of pollution and protection of the environment, review and assess Environmental Impact Assessment (EIA) reports, provision of comments or decisions to project proponents and so on.




Figure 7.2.1 Organization Chart of DENR

Source: Homepage of DENR as of 2017 June

2) Legal Framework

Legal system for environmental consideration in Philippines was begun with “Presidential Decree (PD) 1151: Philippine Environmental Policy” and “PD 1152: Philippine Environmental Code” in 1977. In general, a series of EIA procedures is called as Environmental Impact Statement (EIS) system in Philippines (PD 1586), and PD 2146 in 1981 specifies Environmental Critical Areas (ECAs) and Environmental Critical Projects (ECPs) as targets of EIS system.

In 1992, “DENR Administrative Order (DAO) No.12” stipulates environmental policy, objectives, and procedure including stakeholder meeting, Environmental Compliance Certificate (ECC) and monitoring. Further, in 2003, “DAO-2003-30: Implementing Rules and Regulations for the Philippine Environmental Impact Statement System” classifies any projects into four categories, namely, Category A, B, C and D. The categorization is determined considering combination of two elements, namely, ECPs and ECAs.

The “Revised Procedural Manual for DAO 2003-30”, which was issued in 2007, further sub-divides the category mentioned above into 11 groups based on not only ECPs and ECAs but also progress of the project implementation, namely, “I: New”, “II: Existing with ECC but with Proposal for Modification or Resumption of Operation” and “III: Operating Without ECC”. Moreover, “Memorandum Circular: Standardization of Requirements and Enhancement of Public Participation in the Streamlined Implementation of the Philippine EIS System”, which promotes public participation was issued in 2010. In this manner, the EIS System has been developed gradually for fair

environmental consideration.

In 2014, EMB issued Memorandum Circular No. 005 “Revised Guidelines for Coverage Screening and Standardized Requirements” which modifies category classification was issued. The new groups are broadly classified into Category A, B, C and D. The contents of categories are as follows:

Table 7.2.1 Categories of Project Requiring Environmental Examination

Category	Contents
Category A	Any projects which are categorized into ECPs based on PD 2146 and any others declared by laws in Philippines. Project proponent are required to secure ECC.
Category B	Any project not categorized into Category A, however, are deemed to cause significant environmental impacts by being located in ECAs based on PD 2146. Project proponent are required to secure ECC.
Category C	Any projects are intend to enhance the quality of environment or address existing environmental problems. Project proponent are required to secure Certificate of Non-Coverage (CNC).
Category D	Any project which are unlikely to cause significant adverse environmental impacts. Those projects are not covered by EIS system.

Source: EMB, 2014, Revised Guidelines for Coverage Screening and Standardized Requirements

Any projects which fall under the Category A and B are further divided into 1) New, 2) Existing and to be expanded, modified and/or rehabilitated, and 3) Operating without ECC, and necessary EIA documents are determined based on the sub-classification. Proponents of Category A projects have to submit EIS to EMB Central Office, while those of other categories projects have to submit necessary EIA documents to the EMB Regional Office (see Table 7.2.1).

It is noted that required documents depend on the project scale according to the Annex A of the Guidelines in 2014 mentioned above. In case of an irrigation project, if benefit area is more than 1,000 ha, an EIS is necessary, while an IEE check list is to be prepared if its beneficial area is 300 ha to 1,000 ha. Moreover, if the area is less than 300 ha, only a part of Project Description is needed to be prepared, and the project is classified as Category D, which the project is not covered by the EIS system.

Table 7.2.2 Required Documents, Procedures and Decision Making Organization by Category

Category	Applied to	Documents required for ECC/CNC application	Office to process and decide	
A: Environmentally Critical Projects	A-1: New	Co-located projects	Programmatic EIS	EMB Central Officer
		Single project	EIS	EMB Central Officer
	A-2: Existing and to be expanded, modified and/or rehabilitated	Co-located projects	Programmatic EPRMP (in case programmatic monitoring data are available)	EMB Central Officer
	A-3: Operating without ECC	Single project	EPRM in case monitoring data available EIS if no monitoring data are available	EMB Central Officer
B: Non-environmentally Critical Projects	B-1: New	Co-located projects	Programmatic EIS	EMB Regional Office in region where the proposed project is located
		Single project	EIS IEE checklist	EMB Regional Office in region where the proposed project is located
	B-2: Existing and to be expanded, modified and/or rehabilitated	Co-located projects	EPRMP EPRMP checklist	EMB Regional Office in region where the proposed project is located
	B-3: Operating without ECC	Single project	PEPRMP	EMB Regional Office in region where the proposed project is located

Category	Applied to	Documents required for ECC/CNC application	Office to process and decide
C: Environmental Enhancement or Direct Mitigation	Co-located projects or Single project	Project Description (Part I and Part II) (to confirm non-coverage or future classify as either Category A or B)	EMB Regional Office in region where the proposed project is located
D: Not Covered		Project Description (Part I only) Project prior to 1982-Proof of Project Implementation prior 1982 without expansion /alternation/ modification shall also be submitted (if applying for CNC)	EMB Regional Office in region where the proposed project is located

EIS (Environmental Impact Statement): a document of studies on the environmental impacts of a project
 PEIS (Programmatic Environmental Impact Statement): a document of comprehensive studies on environmental baseline conditions of contiguous area relating to co-located projects (i.e. industrial estates or economic zones)
 IEE (Initial Environmental Examination): a document in checklist or narrative report form
 PEPRMP (Programmatic Environmental Performance Report and Management Plan): a document of actual cumulative environmental impacts of co-located projects with proposals for expansions
 EPRMP (Environmental Performance Report and Management Plan): a document of the actual cumulative environmental impacts and effectiveness of current measures for single projects that are already operating
 PD (Project Description): a standard document of the description of the proposed project
 Source: JICA Survey Team

The EIA process begins with the screening of the proposed undertakings, which allows the proponent to determine whether it is covered by the EIS system, and which type of document shall be prepared. If a project is considered as one which can cause significant impacts on the surrounding environment at the screening, the proponent proceeds to the scoping process. Scoping is to be done formally with various stakeholders to determine the Terms of References (TORs) of the EIA study.

After the formal scoping, the EIA study shall be conducted by the consultants/team registered under the EMB. The study results are compiled as an EIA Report¹ and submitted to EMB. Further, review of the EIA report, which normally includes checking of the proponent's compliance to scoping commitments and then substantive review of the documents, is done within 60 business days after the submission; 120




Figure 7.2.2 Process of EIA Document Approval
 (Source: Homepage of EMB, partly modified)

¹¹ EIA report is the generic term, which includes EIS, Project Description and IEE checklist to apply for ECC/CNC in Philippines.

business days after if submitted to the Central Office. Once approved, an ECC is issued within 10 days if it is at the regional office level (see Figure 7.2.2).

If any projects have been stopped more than 5 years, the project proponents have to submit new applications for approval prior to the project resumption. However, if a project satisfies all following conditions, such procedures can be skipped:

- ✓ Compliance Monitoring Report (CMR) had been continuously submitted or an official request for suspension of CMR has been approved by EMB.
- ✓ No request for relief and/or cancellation of ECC has been approved.
- ✓ The resumption of operation will not involve expansion in terms of production capacity or area.
- ✓ The resumption of operation will not involve change or modification in technology/ production method or manufacturing process/operation used.
- ✓ There is no change in ownership or corporate dissolution.

3) Background of ECC Securement of MMIP

The original EIA document for the MMIP II, which was prepared at IEE level² during the Detailed Design stage of MMIP II, was submitted to the EMB Regional Office XII in December, 1992. The EIA document does not clearly mention the reason for being IEE level. In 2003 July, the ECC of MMIP II was obtained from EMB Region XII Office³.

However, the Project could not be implemented due to the security deterioration in the MMIP II target area, and NIA submitted the new IEE Report again and secured the ECC in August 2007, which is the latest ECC for the MMIP II. In 2011, a part of construction works in the Upper Malitbog area, which is a part of the MMIP II area, was started by the Government of Philippines. Given that the project has been suspended less than 5 years, it can be thought that the ECC is still effective for whole MMIP II area including the initially requested ODA target area.

MMIP I, which had been started ahead of MMIP II, did not have submitted EIS prior to the construction works, the project proponent, therefore, submitted the EIS with incurred penalties, to the EMB, and secured the ECC for the MMIP I in November 2003. In 2011, all of the construction works of MMIP I have been completed. The ODA loan, if applied in the MMIP I area, covers only repair of existing facilities such as gravel pavement, lining of canals and so on, which does not accompany expansion of road or route change of existing facilities. Therefore, it can be judged that re-securement of ECC for the rehabilitation works in the MMIP I area is not necessary.

7.2.2 Environmental Standards

Environmental Standards in Philippines are sufficiently developed, and each standard for air pollution, water quality, effluent water quality, noise has been established. RA 8749 (1999) set permissible values for both long term and short term, respectively. National Ambient Air Quality Guideline for Criteria Pollutants is shown as below:

Table 7.2.3 National Ambient Air Quality Guideline for Criteria Pollutants

Pollutant	Short Term			Long Term		
	µg/NCM	Ppm	Time	µg/NCM	Ppm	Time
TSP	230	-	24 hours	90	-	1 year
PM10	150	-	24 hours	60	-	1 year
Sulfur Dioxide	180	0.07	24 hours	80	-	1 year

² The title of the EIA document is described as “Environmental Impacts Assessment” in the cover of report, however, there is mention that “the EIA document is prepared at IEE level”.

³ It was more than 10 years after the IEE submission, however, the reason for such delay is unknown.

Pollutant	Short Term			Long Term		
	µg/NCM	Ppm	Time	µg/NCM	Ppm	Time
Nitrogen Dioxide	150	0.08	24 hours	-	-	-
Photochemical Oxidants	140	0.07	1 hour	-	-	-
As Ozone	60	0.03	8 hours	-	-	-
Carbon Monoxide	35	30	1 hour	-	-	-
	10	9	8 hours			

Source: An Act Providing For A Comprehensive Air Pollution Control Policy and For Other Purposes (Republic Act No.8749) (1999)

Concerning water quality standard, there are 5 classes for fresh surface waters (lake, river, reservoirs etc.) and 4 classes of sea water depending on the purposes of utilization (DAO No.34, 1991) in the Philippines. Permissible water quality values are various depending on the classes. Water quality criteria for fresh waters are described as follows:

Table 7.2.4 Water Quality Criteria for Conventional and Other Pollutants Contributing to Aesthetics and Oxygen Demand for Fresh Waters

Parameter	Class AA: Public water supply class I	Class A: Public water supply class II	Class B: Recreational water class	Class C: Fishery water, recreational water class II, Industrial water supply class I	Class D (b): Agriculture, industrial water supply class II
Color (PCU)	15	50	(c)	(c)	(c)
Temperature (°C)(d)		3	3	3	3
pH	6.5-8.5	6.5-8.5	6.5-8.5	6.5-8.5	6.0-9.0
DO(e) (%salt)	70	70	70	60	40
(mg/l)	5.0	5.0	5.0	5.0	3.0
BOD (5-Day 20°C)(mg/l)	1	5	5	7 (10)	10 (15)
Total Suspended Solid (mg/l)	25	50	(f)	(g)	(h)
Total Dissolved Solid (mg/l)	500 (i)	1,000(i)	-	-	1,000(i)
Surfactants (MBAS) (mg/l)	Nil	0.2 (0.5)	0.3 (0.5)	0.5	-
Oil/Grease (mg/l)	Nil	1	1	2	5
NO ₃ -N (mg/l)	1.0	10	Nr	10(j)	-
PO ₄ -P (mg/l)	Nil	0.1(k)	0.2(k)	0.4(k)	-
Phenolic Substances as Phenols (mg/l)	Nil	0.002	0.005(l)	0.02(i)	-
Total Coliforms (MPN/100ml)	50 (m)	1,000(m)	1,000(m)	5,000(m)	-
Or Fecal Coliforms (MPN/100ml)	20 (m)	100(m)	200(m)	-	-
Chloride as Cl (mg/l)	250	250	-	350	-
Copper (MPN/100ml)	1.0	1.0	-	0.05 (o)	

- (a) Except as otherwise indicated, the numerical limits in Tables 1 and 3 are yearly average values. Values enclosed in parentheses are maximum values.
- (b) For irrigation purposes, SAR should have a minimum value of 8 and a maximum value not to exceed 18. Boron should not exceed 0.75 mg/L.
- (c) No abnormal discoloration from unnatural causes
- (d) The allowable temperature increase over the average ambient temperature for each month. This rise shall be based on the average of the maximum daily temperature readings recorded at the site but upstream of the mixing zone over a period of one (1) month.
- (e) Sampling taken between 9:00 AM and 4:00 PM
- (f) Not more than 30% increase
- (g) Not more than 30 mg/L increase
- (h) Not more than 60 mg/L increase
- (i) Do not apply if natural background is higher in concentration. The latter will prevail and will be used as baseline
- (j) Applicable only to lakes or reservoirs, and similarly impounded water
- (k) When applied to lakes or reservoirs, the Phosphate as P concentration should not exceed an average of 0.05 mg/L nor a

- maximum of 0.1 mg/L (l). Not present in concentrations to affect fish flavor/taste
- (m) These values refer to the geometric mean of the most probable number of coliform organism during a 3-month period and that the limit indicated shall not be exceeded in 20 percent of the samples taken during the same period
- (n) For spawning areas for *Chanos chanos* and other similar species
- (o) Limit is in terms of dissolved copper nil - Extremely low concentration and not detectable by existing equipment --- Means the standard of these substances are not considered necessary for the present time, considering the stage of the country's development and DENR capabilities, equipment and resources

nr: Means No Recommendation made

Source: DENR Administrative Order No.34, 1990

Allowable noise level in Philippines is stipulated in “National Pollution Control Commission’s Memorandum Circular No. 002” (1980). The standard levels are prescribed by period of time and class of areas. The permissible noise standards are described as shown below:

Table 7.2.5 Permissible Noise Standard

Time	Class				
	AA	A	B	C	D
Daytime (9AM-6PM)	50dB	55dB	65dB	70dB	75dB
Evening (6PM-10PM)	45dB	50dB	60dB	65dB	70dB
Night Time (10PM-5AM)	40dB	45dB	55dB	60dB	65dB
Morning (5AM-9AM)	40dB	50dB	60dB	65dB	70dB

Class AA: a section of contiguous area which requires quietness, such as areas within 100 m from school sites, nursery schools, hospitals and special homes for the aged.

Class A: a section or contiguous area which is primarily used for residential purposes.

Class B: a section or contiguous area which is primarily a commercial area.

Class C: a section primarily zoned or used as light industrial area.

Class D: a section which is primarily reserved, zoned or used as a heavy industrial area

Source: National Pollution Control Commission’s Memorandum Circular No. 002, 1980

7.2.3 Legal Framework of Land Acquisition

Various laws and guidelines regarding land acquisition and involuntary resettlement have been already established in Philippines. The following describe salient points of the various acts and regulations, which stipulate compensation for land loss or resettlement and necessary procedures in Philippines.

1) Republic Act 7279 (Urban Development and Housing Act of 1992) and its Implementing Rules and Regulations

The mandate of this Act is to uplift the conditions of the underprivileged and homeless citizens in urban areas and in resettlement areas by making available to them decent housing at affordable cost, basic services, and employment opportunities. The government shall establish and develop resettlement sites for informal settlers, including the provision of adequate basic services and community facilities, in anticipation of informal settlers that have to be removed from the right-of-way (ROW) site or location of future infrastructure projects.

2) Republic Act 8974 and its Implementing and Rules and Regulations (2000)

Republic Act 8974, otherwise known as “An Act to Facilitate the Acquisition of Right-of-Way, Site or Location for National Government Infrastructure Projects and for Other Purposes” prescribes new standards for assessment of the value of the land or expropriation proceedings. In order to facilitate the determination of just compensation, the court may consider following matters:

- ✓ The developmental costs for improving the land;
- ✓ The value declared by the owners;
- ✓ The current selling price of similar lands in the vicinity;
- ✓ The reasonable disturbance compensation for the removal and/or demolition of certain improvement on the land and for the value of improvements thereon;
- ✓ This size, shape or location, tax declaration and zonal valuation of the land;

- ✓ The price of the land as manifested in the ocular findings, oral as well as documentary evidence presented; and
- ✓ Such facts and events as to enable the affected property owners to have sufficient funds to acquire similarly-situated lands of approximate areas as those required from them by the government, and thereby rehabilitate themselves as early as possible.

The Act also stipulates that the implementing agency and the owner of the property shall agree on a negotiated sale for the acquisition of right-of-way, site or location for any national government infrastructure project. Also, they shall determine fair market value of the property, subject to review and approval by the head of the agency or department concerned.

Another feature of the Act and Implementation Rules and Regulations, is to make ROW acquisition more acceptable to property owners, which is described in Section 10 that valuation of affected improvements and/or structures to be computed based on replacement cost method. The replacement cost of improvements/structures is defined as “the amount necessary to replace the improvements/structures, based on the current market prices for materials, equipment, labor, contractor’s profit and overhead, and all other attendant cost associated with the acquisition and installation in place of the affected improvement/structures”.

3) Republic Act No. 7160: “The Act Providing For a Local Government Code” (1991)

No project or program shall be implemented by the government authorities unless the consultations, and prior approval of the *Sanggunian* concerned shall be obtained. Occupants in areas where such projects are to be implemented shall not be evicted unless appropriate relocation sites have been provided, in accordance with the provisions of the Constitution.

4) Republic Act No. 10752 (The Act Facilitating the Acquisition of Right-of-Way Site or Location for National Government Infrastructure Projects, 2016)

The implementing agency may acquire lands for any public infrastructure projects, through negotiation of sale, the right-of-way site or location under the following rules. The implementing agency shall offer to the property owner concerned, as compensation price, the sum of:

- ✓ The current market value of the land;
- ✓ The replacement cost of structures and improvements therein; and
- ✓ The current market value of crops and trees therein.

To determine the appropriate price to be offered, the implementing agency may engage the services of a government financial institution with adequate experience in property appraisal, or an independent property appraiser.

5) Implementing Rules and Regulation (IRR) of RA 10752

Section 18 of IRR of RA10752 (2016) stipulates that each implementation agency shall prepare and implement its own manual of procedures for ROW Acquisition. The manual shall include preparation of Land Acquisition Plan and Resettlement Action Plan. However, when it was enacted in 2016, MMIP II had been already started, and it has not been applied so far. Moreover, NIA is drafting own manual procedure for ROW Acquisition and it is still under development as of July 2018.

7.2.4 JICA Policy for Involuntary Resettlement and Land Acquisition

The key principle of JICA policies on involuntary resettlement is summarized below:

- a) Involuntary resettlement and loss of means of livelihood are to be avoided when feasible by exploring all viable alternatives.

- b) When, population displacement is unavoidable, effective measures to minimize the impact and to compensate for losses should be taken.
- c) People who must be resettled involuntarily and people whose means of livelihood will be hindered or lost must be sufficiently compensated and supported, so that they can improve or at least restore their standard of living, income opportunities and production levels to pre-project levels.
- d) Compensation must be based on the full replacement cost⁴ as much as possible.
- e) Compensation and other kinds of assistance must be provided prior to displacement.
- f) For projects that entail large-scale involuntary resettlement, resettlement action plans must be prepared and made available to the public. It is desirable that the resettlement action plan include elements laid out in the World Bank Safeguard Policy, OP 4.12, Annex A.
- g) In preparing a resettlement action plan, consultations must be held with the affected people and their communities based on sufficient information made available to them in advance. When consultations are held, explanations must be given in a form, manner, and language that are understandable to the affected people.
- h) Appropriate participation of affected people must be promoted in planning, implementation, and monitoring of resettlement action plans.
- i) Appropriate and accessible grievance mechanisms must be established for the affected people and their communities.
- j) Above principles are complemented by World Bank OP 4.12, since it is stated in JICA Guideline that "JICA confirms that projects do not deviate significantly from the World Bank's Safeguard Policies". Additional key principle based on World Bank OP 4.12 is as follows.
- k) Affected people are to be identified and recorded as early as possible in order to establish their eligibility through an initial baseline survey (including population census that serves as an eligibility cut-off date, asset inventory, and socioeconomic survey), preferably at the project identification stage, to prevent a subsequent influx of encroachers or others who wish to take advance of such benefits.
- l) Eligibility of Benefits include, the PAPs who have formal legal rights to land (including customary and traditional land rights recognized under law), the PAPs who don't have formal legal rights to land at the time of census but have a claim to such land or assets and the PAPs who have no recognizable legal right to the land they are occupying.
- m) Preference should be given to land-based resettlement strategies for displaced persons whose livelihoods are land-based.
- n) Provide support for the transition period between displacement and livelihood restoration.
- o) Particular attention must be paid to the needs of the vulnerable groups among those displaced, especially those below the poverty line, landless, elderly, women and children, ethnic minorities etc.
- p) For projects that entail land acquisition or involuntary resettlement of fewer than 200 people, abbreviated resettlement plan is to be prepared.

In addition to the above core principles on the JICA policy, it also laid emphasis on a detailed resettlement policy, inclusive of all the above points, project specific resettlement plan, institutional framework for implementation, monitoring and evaluation mechanism, time schedule for implementation and detailed financial plan as well.

7.2.5 Gap Analysis

As mentioned before, laws/regulations regarding land acquisition and involuntary resettlement in Philippines have been already developed, which do not result in significant gaps with the JICA Guidelines for Environmental and Social Consideration, 2010 (hereinafter referred to as "JICA Guidelines"). Table 7.2.6 analyzes gaps between laws/regulations in Philippines and the JICA Guidelines.

⁴ Description of "replacement cost" is as follows.

Land	Agricultural Land	The pre-project or pre-displacement, whichever is higher, market value of land of equal productive potential or use located in the vicinity of the affected land, plus the cost of preparing the land to levels similar to those of the affected land, plus the cost of any registration and transfer taxes.
	Land in Urban Areas	The pre-displacement market value of land of equal size and use, with similar or improved public infrastructure facilities and services and located in the vicinity of the affected land, plus the cost of any registration and transfer taxes.
Structure	Houses and Other Structures	The market cost of the materials to build a replacement structure with an area and quality similar or better than those of the affected structure, or to repair a partially affected structure, plus the cost of transporting building materials to the construction site, plus the cost of any labor and contractors' fees, plus the cost of any registration and transfer taxes.

Table 7.2.6 Gap Analysis between Laws in Philippines and the JICA Guidelines

JICA Guidelines	Laws in Philippines	Gap	Measures against gap
1. Involuntary resettlement and loss of means of livelihood are to be avoided when feasible by exploring all viable alternatives.	"No person shall be deprived of life, liberty, or property without due process of law, nor shall any person be denied the equal protection of the laws." (Article III Section 1 of the Constitution, 1987).	None	-
2. When population displacement is unavoidable, effective measures to minimize impact and to compensate for losses should be taken.	An implementing agency shall pay the owner of the property the amount equivalent to the sum of (1) one hundred percent (100%) of the value of the property based on the current relevant zonal valuation of the Bureau of Internal Revenue (BIR); and (2) the value of the improvements and/or structures as determined (Section 4, RA 8974, 2000). The government shall establish and develop squatter relocation sites, including the provision of adequate utilities and services, in anticipation of squatters that have to be removed from the right-of-way or site of future infrastructure projects (Section 9, RA 8974).	None	-
3. People who must be resettled involuntarily and people whose means of livelihood will be hindered or lost must be sufficiently compensated and supported, so that they can improve or at least restore their standard of living, income opportunities and production levels to pre-project levels.	Government shall ensure that owners of real property acquired for national government infrastructure projects are promptly paid just compensation (Section 1, RA 8974, 2000). It is necessary to uplift the conditions of the underprivileged and homeless citizens in urban areas and in resettlement areas by making available to them decent housing at affordable cost, basic services, and employment opportunities (Section 2 (a), RA 7279, 1992)	None	-
4. Compensation must be based on the full replacement cost as much as possible.	The implementing agency shall offer to the property owner concerned, as compensation price, the sum of: (1) The current market value of the land, (2) The replacement cost of structures and improvements therein; and (3) The current market value of crops and trees therein (Section 5, RA 10752, 2016). With regard to the taxes and fees relative to the transfer of title of the property to the Republic of the Philippines through negotiated sale, the implementing agency shall pay. Moreover, the capital gains tax, documentary stamp tax, transfer tax and registration fees shall be paid by the proponent (Section 5 (c), RA 10752, 2016).	None	-
5. Compensation and other kinds of assistance must be provided prior to displacement.	No project or program shall be implemented by government authorities unless the consultations (Section 27, RA 7160, 1991). Compensation timing is not clearly mentioned in any laws/regulations, however, Section 6.10 of IRR of RA10752 states that implementation agencies should pay compensation of: 1. affected land (at 50% of the negotiated price). 2. Affected structure (at 70% of the negotiated price) upon the implementation of Sale of Deed. Remaining balance of the price shall be paid upon the transfer of title to the Republic of the Philippines.	The IRR of RA 10752 allows payment by installments instead of paying in full.	All compensations have to be paid to the PAPs before displacement.
6. For projects that entail large-scale involuntary resettlement, resettlement action plans must be prepared and made available to the public.	Preparation of a resettlement action plan is listed up as one of ICC REQUISITE DOCUMENTS, where applicable. (NEDA, Investment Coordination Committee Guidelines and Procedures, Annex B, Section 7). Section 18 of IRR of RA 10752 mentions that each implementation agency should prepare manual for ROW acquisition, which stipulates preparation of a RAP.	None	-
7. In preparing a resettlement action plan, consultations must be held with the affected people and their communities based on sufficient information made available to them in	A project proponent shall explain the goals and objectives of the project, and its environmental impact and the measures. Moreover, no project or program shall be implemented by government authorities unless the consultations (Section 26 and Section 27, RA7160, 1991). In the execution of eviction or demolition orders involving	None	-

JICA Guidelines	Laws in Philippines	Gap	Measures against gap
advance.	underprivileged and homeless citizens, it is needed to notice at least 30days prior to eviction or demolition and to implement adequate consultations on the matter of settlement (Section 28 (1) (2), RA 7279, 1992)		
8. When consultations are held, explanations must be given in a form, manner, and language that are understandable to the affected people.	Official documents in Philippines are prepared in English, which means that a series of EIA reports are also to be prepared in English. Still, it is possible to explain the project outline to the Project Affected Persons (PAPs) in Tagalog language or any other local language, which is understandable for the people. All information about the proposed project or undertaking shall be presented by the proponent to the public in a language and manner that are easily understood (Sec 2.0 of Article IV, DENR Ministry Order No. 96-37, 1996).	None	-
9. Appropriate participation of affected people must be promoted in planning, implementation, and monitoring of resettlement action plans.	EIA finding for Environmental Critical Projects shall be presented in a public consultation meeting during the Scoping sessions (DENR, Section 3.2, Memorandum Circular, 2010). Public participation of the stakeholders is to be sustained during EIA Study and project implementation (DENR, Annex 4, Memorandum Circular, 2010). There is no mention to participation in monitoring system by PAPs.	None	A monitoring system the PAPs can join in shall be set up.
10. Appropriate and accessible grievance mechanisms must be established for the affected people and their communities.	In the event that the owner of the property contests the implementing agency's pre-offered value, the court shall determine the just compensation to be paid the owner (Section 6 (f), RA 10752, 2014). However, there is no mention to set-up of grievance handling mechanism.	There is no law stipulating grievance handling mechanism.	A grievance handling mechanism shall be established for the Project.
11. Affected people are to be identified and recorded as early as possible in order to establish their eligibility through an initial baseline survey (including population census that serves as an eligibility cut-off date, asset inventory, and socioeconomic survey), preferably at the project identification stage, to prevent a subsequent influx of encroachers of others who wish to take advance of such benefits	There is no law/regulation which is applied to the item in Philippines.	There is no system for identification of PAPs at early stage.	A socio- economic survey targeting more than 20% of the PAPs shall be done at early stage.
12. Eligibility of benefits includes, the Project Affected Persons (PAPs) who have formal legal rights to land (including customary and traditional land rights recognized under law), the PAPs who don't have formal legal rights to land at the time of census but have a claim to such land or assets and the PAPs who have no recognizable legal right to the land they are occupying.	Government through the National Housing Authority, in coordination with the local government units and implementing agencies concerned, shall establish and develop squatter relocation sites, including the provision of adequate utilities and services, in anticipation of squatters that have to be removed from the right-of-way or site of future infrastructure projects. Whenever applicable, the concerned local government units shall provide and administer the relocation sites (Section 9, RA 8974, 2000). In case of untitled lands or failure to establish ownership over the land, but where improvements are introduced thereon, the apparent property owner may be entitled to compensation for the said improvements subject to Section 6.8 of this IRR of RA 10752.	None	It shall be accordance with laws/regulations in Philippines.
13. Preference should be given to land-based resettlement strategies for displaced persons whose livelihoods are land-based.	"Land swapping" is a process of land acquisition by exchanging land for another piece of land of equal value, which is one of modes of acquisition (Section 3 (j) and Section 10, RA 7279). It is noted that there is no mention to preference of compensation measure, either "land for land" or "cash for land", in any laws/regulations. Probably, it depends on cases.	None	In accordance with willingness of the PAPs, whether cash compensation or land for land compensation shall be determined.

JICA Guidelines	Laws in Philippines	Gap	Measures against gap
14. Provide support for the transition period (between displacement and livelihood restoration)	There is no law/regulation which is applied to the item in Philippines.	There is no law/regulation referring to support during transition period.	According to need, any supports shall be provided.
15. Particular attention must be paid to the needs of the vulnerable groups among those displaced, especially those below the poverty line, landless, elderly, women and children, ethnic minorities etc.	Equitable utilization of residential lands in urban and urban areas is needed with particular attention to the needs and requirements of the underprivileged and homeless citizens. (Section 2 (b) (1), RA 7279, 1992).	None	-
16. People who must be resettled involuntarily and people whose means of livelihood will be hindered or lost must be sufficiently compensated and supported, so that they can improve or at least restore their standard of living, income opportunities and production levels to pre-project levels	Government shall ensure that owners of real property acquired for national government infrastructure projects are promptly paid just compensation (Section 1, RA 8974, 2000). It is necessary to uplift the conditions of the underprivileged and homeless citizens in urban areas and in resettlement areas by making available to them decent housing at affordable cost, basic services, and employment opportunities (Section 2 (a), RA 7279, 1992).	None	-

Source: JICA Survey Team

7.3 General Conditions in and around the Target Area

The MMIP area consisting MMIP I and MMIP II is located in parts of 5 municipalities, namely, Carmen, Kabacan, Pikit, Datu Montawal and Pagalungan. The first 3 municipalities fall in Cotabato province, while the latter 2 municipalities in Maguindanao province (ARMM).

7.3.1 Meteorological Conditions

The project area has a tropical wet climate with no dry or cold season, represented with year-round rainfall. There is not much temperature fluctuation throughout a year, with a bit of increase in March - May which is the right before the onset of rainy season. The minimum monthly temperature is at around 20 Celsius degrees while the maximum one ranges from 33 to 35 Celsius degrees (see Figure 7.3.1).




Figure 7.3.1 Monthly Temperature Trend (Pikit Area)

Source: NCEP, US




Figure 7.3.2 Monthly Rainfall Trend (Pikit Area)

Source: NCEP, US

7.3.2 Positional Relation between the Target Area, Surrounding Rivers and Ligusan Marsh

Pikit observatory is located at 10 m elevation, and there is a tendency that elevation of northwest side

area of Pikit is high, while that of south side is low (see Figure 7.3.3). The Liguasan marsh consists of open water, wetland, shrub and so on. Liguasan marsh (one of three marshes formulating as called “Liguasan Marsh”, see Chapter 2.2.1 in detail) may be partly overlapped with southern part of Lower Malitubog area (see Figure 7.3.4), the boundary of Liguasan marsh is not clear, though.




Figure 7.3.3 Three-Dimension Map of Liguasan Marsh (Vegetation Distribution)

Source: JICA Survey Team

The Diversion Dam, which water for MMIP area is diverted from, is located at the north of MMIP I area, and the water source is Maridagao River. This river merges with Pulangi river (sometimes called as Mindanao River) since it is one of streams of Mindanao river). Further, Pulangi river flows into Liguasan marsh via Tunggol Bridge, and continuously goes along the southern border of the Lower Malitubog area.

It is noted that land use and inundation situation in and around the Lower Malitubog area is drastically changed in dry season and rainy season. Paddy and corn fields extend over southern part of the requested ODA area in dry season, while such area is inundated in rainy season as illustrated in Figure 7.3.5. In addition, the part of Liguasan marsh which may be overlapped with southern parts of the Lower Malitubog area has been already developed for farming and is not




Figure 7.3.4 Location Map of Liguasan Marsh and MMIP Area

Source: JICA Survey Team based on 1/50,000 Topographic Map

untouched natural land any more.




Figure 7.3.5 Land Use of Lower Malitubog Area in Rainy and Dry Seasons

Source: JICA Survey Team

7.3.3 Mindanao River Basin and Pulangi River Basin

The Mindanao River Basin is the second largest river system in the Philippines having a drainage area of 21,503 square kilometers, after the Cagayan river of Luzon and also the second longest river in the Country with a length of approximately 373 km. The river plays an important role for local economy, used mainly in transporting agricultural products. The Mindanao river headstream is in the mountains of Bukidnon Province, where it is called the Upper Pulangi River. Its lower portion, commonly known as the Lower Pulangi, flows into the Liguasan marsh.

Pulangi river meanders across the provinces of Bukidnon, Davao del Sur, Lanao del Sur, Maguindanao and Cotabato (see Figure 7.3.6). Its main river channel has a total stretch of 353.2 km. The river serves as the largest tributary of Mindanao river, drains an area of 4,099 km². It flows southwest to the Liguasan marsh, where it becomes the Mindanao river and directs to the west and then northwest. Notable tributaries of the Pulangi river system in the northern highlands are: Maridagao, Mulita, Kulama, Arakan, Kabacan, Manupali, Calabugao and Tigua Rivers.

The Mindanao River Basin is a large dendritic catchment coming from upstream sections of Pulangi (northern section) and




Figure 7.3.6 Main Rivers in Pulangi River Basin

Note1: The map is prepared by JICA Survey Team based on “Mindanao River Basin Integrated Management and Development Master Plan Pre- Feasibility Study Of An Integrated Flood Control, River Bank Protection and Rehabilitation Project For Pulangi River”

Note2: The “Pulangi River Basin” in the map is integrated some sub-basins of Mindanao River (see Figure 7.3.7), does not equal of sum of Upper Pulangi Sub-basin and Lower Pulangi Sub-basin.

Source: JICA Survey Team

Ala Valley (southern section) sub-watersheds. These waters enter into the Liguasan marsh and eventually flow into the Illana Bay in Cotabato City (see Figure 7.3.7).




Figure 7.3.7 Sub-basins in Mindanao River

Source: JICA Survey Team

7.3.4 Protected Areas around the Target Area

Based on the RA 7586 (1992)⁵, the protected areas to ensure the sustainable use of resources have

⁵ Act Providing for the Establishment and Management of National Integrated Protected Areas System, Defining its Scope and Coverage, and for Other Purposes

been identified, and 204 protected areas in total are specified as of 2004 in Philippines.⁶ The protected areas consists of; 1) 71 National Parks/Marine Parks and National Marine Reserves, 2) 8 Game Reserve and Bird Sanctuaries, 3) 16 Wilderness Areas, 4) 87 Watershed Forest Reserve, and 5) 27 Mangrove Swamps.

In Region XII, where the target area is located on, there are 5 protected area. The nearest one for the target area is Libungan Forest Reserve, which is around 25km away from the Project area as illustrated in following figure. The Forest Reserve is located on watershed of Libungan river, while the irrigation water for the target area belongs to Lower Pulangi River Basin. Therefore, any development activities in the target area would not cause adverse impacts on the Forest Reserve.



Figure 7.3.8 Location of Protected Areas around the Target Area
 Source: <http://philgis.org/general-county-datasets/protected-areas>

7.3.5 Main Income of MMIP Area

A socio-economic survey to gain baseline values of farm households in MMIP I area and LMSA was implemented by the JICA Survey Team in July 2017. Three villages (Barangay) in MMIP I area and six villages in MMIP II (LMSA) were chosen randomly considering locational balance as shown in Figure 7.3.9. Each 20 households were sampled from each village, as shown in the following table:




Figure 7.3.9 Location of Target Communities of Socio-economic Survey
 Source: JICA Survey Team


⁶ Biodiversity Management Bureau, "Statistics on Philippines Protected Areas and Wildlife Resources", 2004

Table 7.3.1 Target Villages of Socio-Economic Survey and No. of Interviewed Households


Area	Name of Village	Province	No. of Households Interviewed
MMIP I	1. UGALINGAN	Carmen	20
	2. GENERAL LUNA	Carmen	20
	3. KIBAYAO	Pagalungan	20
LMSA	4. BOLIOK	Pikit	20
	5. TALITAY	Pikit	20
	6. BAGO-INGED	Pikit	20
	7. GLI-GLI	Pikit	20
	8. MACABUAL	Pikit	20
	9. PUNOL	Pikit	20

Source: JICA Survey Team

The survey revealed that the people in LMSA have various incomes sources such as cropping, aquaculture, migrant work, while the residents in MMIP I area are mainly dependent on farming as shown in Figure 7.3.10. It is probably because that LMSA faces difficulties with crop cultivation due to frequent inundation in rainy season, while MMIP I Area is rarely influenced by flood. Such a situation can lead to a big difference of annual income, more than twice, namely, P206,305 and P88,786 for MMIP I and LMSA, respectively, as shown in Figure 7.3.11.

**Figure 7.3.10 Income Sources in LMSA and MMIP I Area**

Source: JICA Survey Team

**Figure 7.3.11 Annual Income in LMSA and MMIP I Area**

Source: JICA Survey Team

7.3.6 Farming in the MMIP II Area

1) Land Use and Planted Crops

Based on the satellite image analysis as of 2015-2016, land occupation percentage by purpose, such as cropped, non-cropped and open water by season in Lower Malitubog, is illustrated in following figure. Only 38% and 35% of the total area were covered by crop planting (sum of paddy, maize and tree crop) in rainy season and dry season, respectively, which implies that land use for agricultural purpose in the area is limited. On the other hand, open water area accounts for 15% of total area in rainy season, while it is 0% in dry season, and it is noted that such high occupation rate of water could be a constraint for agricultural development during rainy season.

There is no statistical data covering only the MMIP area specifically. However, the Project area spreads mainly in Pikit municipality, therefore, farming situation is discussed based on the statistical data of the municipality. In the municipality, paddy and maize are leading crops as shown in following figure and table. Fruits and tree crops, mainly coconut, could be important crops after paddy and corn. The other crops such as root crops, pulses, vegetables, etc. account for only 6% of the total area, and mung-bean, squash, eggplant, bitter-gourd and sugarcane are grown to only some extent in the area. The shares of each crops in Pikit Municipality is illustrated in following table.




Figure 7.3.12 Land Use in Lower Malitbog Area

Source: JICA Survey Team

Table 7.3.2 Crop Production in Pikit Municipality (Ave. 2014-16)

No	Crop	Harvested Area		Yield (ton/ha)	Production (ton)
		(ha)	(%)		
1	Paddy, irrigated	1,936.4	9.4	4.5	8,772.6
2	Paddy, rain-fed	3,986.3	19.4	3.5	14,113.4
	Paddy, total	5,922.7	28.8	3.9	22,886.0
3	Corn, yellow	1,209.0	5.9	4.2	5,127.1
4	Corn, white	6,184.6	30.0	3.9	23,925.7
	Corn, total	7,393.6	35.9	3.9	29,052.8
5	Root crops	76.4	0.4	-	-
6	Mung Bean	556.8	2.7	0.8	445.4
7	Squash	180.2	0.9	2.0	360.4
8	Bitter Gourd	65.3	0.3	3.3	167.0
9	Egg Plant	68.6	0.3	3.0	205.8
10	Miscellaneous vegetables	82.4	0.4	-	-
11	Sugarcane	196.8	1.0	48.0	9,446.4
	Root, vegetables, etc.	1,226.5	6.0	-	-
12	Coconut	4,684.3	22.7	3.6	16,863.5
13	Mango	820.6	4.0	2.5	2,051.5
14	Oil Palm	206.9	1.0	24.0	4,965.6
15	Rubber	109.8	0.5	2.4	263.5
16	Banana	96.0	0.5	14.5	1,392.0
17	Miscellaneous fruits	136.3	0.7	-	-
	Fruits & tree crops, total	6,053.9	29.4	-	-
	Total	20,596.7	100.0	-	-

Source: Office of the Provincial Agronomist, Cotabato Province

2) Rice Farming System⁷

A part of MMIP I and MMIP II is located in ARMM, which is the poorest area in the Philippines with poverty incidence ranging from 29.8 percent to 53.7 % in 2009, while poverty incidence for the entire country for the same period is 26.5% (WB, 2013)⁸. Following discusses the rice farming systems in ARMM comparing with those of average of whole Philippines and Region XII.

⁷ This sub-chapter is described based on “2013 Costs & Returns of Palay Production, Philippine Statistics Authority”

⁸ Source: <http://www.worldbank.org/en/results/2013/04/10/philippines-autonomous-region-in-muslim-mindanao-social-fund-project>

Average farm size of rice farmers is about 1.6 ha in Region XII, ARMM and entire Philippines. On the other hand, landowner farmer is the majority of rice farmers in the both regions (Region XII: 58% and ARMM: 64%), while the percentage of landowner farmer in the Philippines remains only at 37%, which means that the Region XII and ARMM have advantage in terms of land ownership. However, the percentage of paddy farming in irrigated area in ARMM is only 29%, while those in entire Philippines and Region XII are 61% and 66%, respectively. It means that irrigation system is not well developed in ARMM.

The percentage of rice farmers who own drawing animals (buffalo/cattle) in Region XII and ARMM are 50% and 59%, respectively, while the percentage of the Philippines is 42%. The percentage of 2-wheel tractor owners in Region XII is only 13%, which is almost half of the national average, while the percentage is only less than 4% in ARMM. Such conditions imply agricultural mechanization in ARMM is behind compared with other areas. (Source: 2013 Costs & Returns of Corn Production, Philippine Statistics Authority.)

Urea, ammonium sulphate and NPK (14-14-14) are popular chemical fertilizers among the rice farmers in Region XII and ARMM. In many cases, they much depend on nitrogen fertilizers and do not pay attention to apply the phosphate and the potash. It is, however, considered that the present level of nitrogen provided by the fertilizers might not be sufficient, if the farmers aim to get higher productivity, e.g. 5 – 6 ton/ha. The amount of chemical fertilizers used in ARMM is much lower than the national average as shown in Figure 7.3.13. Concerning amount of pesticide application, data in ARMM is not available, therefore, it can hardly be possible to discuss the matter.




Figure 7.3.13 Amount of Applied Fertilizers for Paddy

Source: 2013 Costs & Returns of Corn Production, Philippine Statistics Authority

3) Corn Farming System⁹

There are two types of corn in Philippines, namely, white corn and yellow one. Concerning farm size, average sizes of corn farmers in Region XII, ARMM and entire Philippines are almost same, 2.24ha, 1.80ha and 2.14ha, respectively. On the other hand, landowner farmer is the majority of corn farmers in ARMM, which accounts for 70% of all of farmers, while those in the Philippines and Region VII remains only 36% and 35%, respectively. The situation implies that the ARMM has advantage in terms of land ownership for corn planting as well as paddy production.




Figure 7.3.14 Amount of Applied Liquid Pesticide for Corn

Source: 2013 Costs & Returns of Corn Production, Philippine Statistics Authority

In case of white corn, most of farmers grow

⁹ This sub-chapter is described based on “2013 Costs & Returns of Corn Production, Philippine Statistics Authority”

OPV (Open Pollinated Varieties). While the most majority of the farmers in Region XII grow modern varieties of white corn, the farmers in ARMM prefer much native varieties. On the contrary, hybrid varieties are popular in yellow corn cultivation among the farmers. In Region XII and entire Philippines, the percentages of farmers growing hybrid yellow corn are 75% and 50%, respectively, whereas no farmers grow hybrid varieties even in yellow corn cultivation in ARMM.

As same as the case of rice farmers, urea, ammonium sulphate and NPK (14-14-14) are popular chemical fertilizers among corn farmers in Region XII and ARMM. The situation of chemical fertilizer use is characterized by limited use of organic fertilizers, heavily nitrogen-conscious application, low dependency on the basic dressing. Moreover, as well as paddy, amount of application in ARMM is low compared to them in Philippines and Region XII. Concerning pesticide application, amount of pesticide in ARMM is very limited compared with them in Philippines and Region XII as illustrated in Figure 7.3.14. As a whole, amount of farming inputs in ARMM is deemed to be small, which means that relatively extensive farming is operated at this moment.

7.4 Scoping

Due to the new construction works of irrigation/drainage canals and access roads, some environmental impacts, for instance, air pollution, water pollution, involuntary resettlement/land acquisition are anticipated. Prior to the specific investigation to assess any environmental impacts by the Project, scoping, which narrow down important parameters to be studied, was implemented. Following table discusses the scoping results:

Table 7.4.1 Scoping Result

Items	Evaluation		Reason for Evaluation
	Before and during construction	Operation stage	
1. Air Quality	B ⁻	C	<p>Construction stage: Dust and gas emission will be caused, which leads to air pollution in and around the construction site. However, as the area is not densely populated area, the extent of impact is limited.</p> <p>Operation stage: Increase of dust and gas emission is expected due to the access road construction, however, surrounding area is mostly used as farmland, which leads to very minor impact. Still, it is needed to confirm current situations.</p>
2. Water Quality	B ⁻	B ⁻	<p>Construction stage: Mud water from the construction site will be caused.</p> <p>Operation stage: Due to the development of farmland, total amount chemical to be applied can be increased and they can be discharged through drainage from paddy fields, however, the current amount is relatively small compared with average amount at the national level.</p>
3. Waste	B ⁻	D	<p>Construction stage: Waste from construction works and labor camps will be generated.</p> <p>Operation stage: No waste due to the operation of the constructed facilities is expected.</p>
4. Soil contamination	C	D	<p>Construction stage: Oil leakage from construction vehicles and equipment is expected.</p> <p>Operation stage: No soil contamination is expected.</p>
5. Noise and Vibration	B ⁻	C	<p>Construction stage: Noise and vibration due to construction works are expected.</p> <p>Operation stage: Traffic will be increased due to construction of the access roads, which leads to noise and vibration. However, considering surrounding area is generally used as farmland, there is low possibility of severe noise. It is needed to confirm the conditions along the proposed roads.</p>

Items	Evaluation		Reason for Evaluation
	Before and during construction	Operation stage	
6. Ground Subsidence	D	D	Construction stage /Operation stage: During construction and operation, ground subsidence will not be caused, since there is no plan to extract ground water.
7. Offensive Odor	D	D	Construction stage /Operation stage: Any works to caused offensive odor is not planned.
8. Bottom Sediment	D	D	Construction stage /Operation stage: Any works to caused bottom sediment is not planned.
9. Protected Area	D	D	Construction stage /Operation stage: There is no protected area in and around the project site.
10. Groundwater	D	D	Construction stage /Operation stage: Use of groundwater is not planned for the Project, which results in no damage to groundwater.
11. Hydrological Situation	C	B	Construction stage: During the construction, no water intake is planned. However, construction of canal embankment can prevent water drainage, which can lead to inundation. Operation stage: The entire MMIP plans to intake water, around 30 m ³ /s, at the existing diversion dam (just upstream of MMIP I area) in dry season. The resource of the dam is Maridagao River, and the river discharge will be reduced. However, the river flows into Pulangi river at 10 km downstream of the Diversion Dam. Pulangi River has sufficient discharge, around mean discharge 200-300 m ³ /s at the confluence of Pulangi and Kabacan through the year ¹⁰ , and the water intake at the Diversion Dam will not cause significant impact on the discharge of Pulangi River. Liguasan Marsh (one of three marshes) extends over from around 5 km downstream of the influent point between Pulangi River and Maridagao River. Given that not only Pulangi River but also Malasa River and other rivers flow into the marsh, intake of 30 m ³ /s water will not cause severe hydrological impact on the marsh.
12. Ecosystem	D	C	Construction stage Lands in and around the construction sites have been already developed for agricultural purpose and there is no virgin nature to be damaged by the Project. Operation stage: Construction of canals, drainages and access roads and water intake will not give a damage to Liguasan Marsh. However, detailed survey of the current ecosystem in the Marsh is necessary to confirm the current conditions, probably, the impacts by the Project will be limited, though.
13. Topography and Geographical features	D	D	Construction stage: Construction materials will be sold by the private land owners to the contractors directly, instead of establishment of a borrow area, and negative impact on topography and geographical features is not expected. Operation stage: There is no topographic change, once operation is started.
14. Involuntary Resettlement/ Land Acquisition	B	D	Before construction stage: For the purpose of the construction of roads, canals and drainages, resettlement and land acquisition are expected. The construction will be done by using budget of GoP, and it is recommended to compensate the PAPs for the impacts incurred. Construction/Operation stage: No impacts are expected.
15. The poor	C	C	Construction/Operation stage: It is needed to confirm the situations by the field survey and hearing from the governmental staff and the people concerned.
16. Indigenous and ethnic people	C	C	Before construction/Operation stage: Field based investigation to testify the absence/existence of indigenous people shall be implemented.

¹⁰ Mindanao Development Authority, River Basin Control Office and Office of Civil Defense, "Mindanao River basin integrated management and development master plan, Master Plan Report Volume II"

Items	Evaluation		Reason for Evaluation
	Before and during construction	Operation stage	
17. Livelihood/local economy	B/B ⁺	B ⁺	<p>Construction stage: Given that the Project will provide job opportunities as construction labors for the local people, positive impacts are expected. On the other hand, the Project will cause negative impacts on some people whose land will be acquired.</p> <p>Operation stage: Stable agricultural production can be performed due to stable irrigation water supply and shortening inundation period.</p>
18. Land use and local resource utilization	B ⁻	D	<p>Construction stage: It is needed to acquire lands for construction of canals, roads and drainages, which would change current land use.</p> <p>Operation stage: No negative impact on land use and local resource utilization is expected.</p>
19. Water Usage or Water Rights and Rights of Common	D	B ⁺	<p>Construction stage: The construction works will not give a change of water usage system or water use rights.</p> <p>Operation stage: Due to increase of water diversion for the LMSA, discharge of Maridagao River will be reduced. However, right bank area of Maridagao River is mountainous area where upland crops are partly cultivated without using irrigation system, while left bank area has been irrigated by lateral canals under MMIP I. Thus, no negative impact on water usage by the MMIP II is expected. In the beneficiary area, irrigation system will be introduced, which enables stable access to the irrigation water for the beneficiaries, and existing water rights will not be spoiled by the Project.</p>
20. Existing Social Infrastructures and Services	B ⁻	B ⁺ /B ⁻	<p>Construction stage: Due to increase of construction vehicles, traffic jam can be caused.</p> <p>Operation stage: Due to widening existing roads and new road construction, the people access to road more easily than before, while traffic would be increased.</p>
21. Social Institutions	C	C	<p>Construction/Operation stage: It is needed to confirm current conditions by the field survey and hearing from the governmental staff and the people concerned.</p>
22. Misdistribution of Benefit and Damage	B ⁻	D	<p>Before construction stage: Some land owners will lose their farmlands, while others are informed of the Project benefit, which may cause feeling of inequality for the PAPs.</p> <p>Operation stage: Construction of access roads, irrigation canals and drainages will not cause negative impacts on non-beneficiaries, which will not lead to misdistribution of benefit and damage.</p>
23. Conflict	D	B ⁻	<p>Construction /Operation stage: Any conflicts between the beneficial area and affected area are not expected, as far as sufficient compensation to the affected persons is provided.</p> <p>Construction /Operation stage: Due to the Project, stable irrigation water will be supplied to the beneficial area. There is a concern that uneven water distribution can lead to a conflict in the beneficiary area.</p>
24. Cultural Heritage	C	C	<p>Construction /Operation stage: It is needed to confirm by the field survey.</p>
25. Land Scape	D	D	<p>Construction /Operation stage: The areas in and around the project sites are mainly farmlands, therefore, special land scape to be reserved is not identified.</p>
26. Gender	D	D	<p>Construction /Operation stage: Negative impact on women is not expected.</p>
27. Rights of the Child	D	D	<p>Construction /Operation stage: Negative impact on children is not expected.</p>

Items	Evaluation		Reason for Evaluation
	Before and during construction	Operation stage	
28. Hazards (Risk), Infectious Diseases such as HIV/AIDS	B ⁻	D	Construction stage: There is a possibility that infectious disease HIV/AIDS could be caused by employment of workers from other areas. It is needed to confirm other cases. Operation stage: After the construction works, no disease is expected.
29. Work Environment	B ⁻	D	Construction stage: There is a concern of work accidents at the construction sites. It is needed to comply with the labor code for safety. Operation stage: No labor environmental change in the beneficial area is expected, since irrigation farming has been operated in the area.
30. Accident	B ⁻	B ⁻	Construction stage: There is a concern of traffic accident increase in and around the construction sites. Operation stage: Due to the access road construction, there can be some traffic accidents.
31. Transboundary Impact, Climate Change	D	D	Construction stage: Large amount of greenhouse gas, which can cause climate change, will not be emitted by the Project. Operation stage: The rivers concerned to the Project, finally merge into Mindanao River, which flow into the sea. There is no international river concerned.

*Further studies are needed for the highlighted environmental items.

A+/-: Significant positive/negative impact is expected.

B+/-: Positive/negative impact is expected to some extent.

C+/-: Extent of positive/negative impact is unknown. (A further examination is needed, and the impact could be clarified as the study progresses)

D: No impact is expected.

Source: JICA Survey Team

Based on the discussion in Table 7.4.1, for the parameters which can cause negative and unknown impacts, necessary environmental studies to assess environmental impacts and their extent are examined. Those studies are to be implemented through desk study, field survey, interviews to governmental staff concerned and the people in and around the Project area as in the following table:

Table 7.4.2 Terms of Reference for Environmental Examination

Environmental parameters	Study item	Method
1. Air quality	<ul style="list-style-type: none"> Confirmation of environmental standard in Philippines Examination of anticipated impacts during the construction stage 	<ul style="list-style-type: none"> Confirmation of environmental standards in Philippines Field survey and observation in the target area (distribution of houses, hospital and schools in and around the project sites) Data collection of similar projects
2. Water quality	<ul style="list-style-type: none"> Confirmation of environmental standard in Philippines 	<ul style="list-style-type: none"> Confirmation of environmental standards in Philippines Field survey Data collection of similar projects
3. Waste	<ul style="list-style-type: none"> Examination of waste disposal 	<ul style="list-style-type: none"> Data collection of similar projects for waste management Confirmation of environmental standards in Philippines
4. Soil Contamination	<ul style="list-style-type: none"> Examination of anticipated impacts during the construction stage 	<ul style="list-style-type: none"> Data collection of similar projects
5. Noise and vibration	<ul style="list-style-type: none"> Confirmation of environmental standards Noise and vibration by the Project 	<ul style="list-style-type: none"> Confirmation of environmental standards in Philippines Field survey (distribution of houses, hospital and schools in and around the project sites) Data collection of similar projects

Environmental parameters	Study item	Method
11. Hydrological situations	<ul style="list-style-type: none"> Confirmation of the current hydrological conditions Examination of the possibility of hydrological change 	<ul style="list-style-type: none"> Data collection of water discharge of rivers concerned to the Project Field observation Examination of change of water depth and area of Liguasan Marsh
12. Ecosystem	<ul style="list-style-type: none"> Ichthyological and bird survey targeting Liguasan Marsh Desk study of ecosystem in the Liguasan Marsh 	<ul style="list-style-type: none"> Desk study of the ecosystem in the Liguasan Marsh Field survey on range of fish and birds in Liguasan Marsh
14. Involuntary resettlement and land acquisition	<ul style="list-style-type: none"> Identification of areas to be resettle and acquired Preparation of a full-scale RAP or an abbreviated RAP depending on the result of case studies 	<ul style="list-style-type: none"> Review of laws and decrees regarding involuntary resettlement and land acquisition in Philippines Identification of affected area and PAPs Confirmation of land use of the area and existing structures to be affected
15. The poor	<ul style="list-style-type: none"> The poor in and around the project area 	<ul style="list-style-type: none"> Identification of the affected area Site survey and interview to the people Hearing to the governmental organization concerned
16. Indigenous people/minority people	<ul style="list-style-type: none"> Indigenous people/minority people in and around the project area 	<ul style="list-style-type: none"> Review of laws and decrees regarding indigenous people in Philippines Identification of the affected area Implementation of the field based investigation Hearing to the governmental organization concerned
17. Livelihood/local economy	<ul style="list-style-type: none"> Identification of affected area by involuntary resettlement and land acquisition 	<ul style="list-style-type: none"> Identification of the affected area Confirmation of land use of the area and existing structures to be affected
18. Land use and local resource utilization	<ul style="list-style-type: none"> Examination of area to be acquired 	<ul style="list-style-type: none"> Review of laws and decrees regarding land acquisition in Philippines Identification of the affected area Confirmation of current land use of the area to be affected
19. Water usage or water rights and rights of common	<ul style="list-style-type: none"> Confirmation of water distribution system of Maridagao River 	<ul style="list-style-type: none"> Hearing to the governmental organization concerned Site survey and interview to the people Data collection of other similar projects
20. Existing social infrastructure and services	<ul style="list-style-type: none"> Traffic jam due to the construction works 	<ul style="list-style-type: none"> Confirmation of road conditions around the construction sites Data collection of other similar projects
21. Social Institutions	<ul style="list-style-type: none"> Confirmation of Irrigator's Association and other institutions 	<ul style="list-style-type: none"> Hearing to the governmental organization concerned Interview to the leaders of such social institutions
22. Misdistribution of benefit and damage	<ul style="list-style-type: none"> Identification of areas to be resettle and acquired 	<ul style="list-style-type: none"> Identification of affected areas Confirmation of land use of the area and existing structures to be affected Data collection of similar projects
23. Conflict	<ul style="list-style-type: none"> Possibility of conflict due to misdistribution of benefit and damages 	<ul style="list-style-type: none"> Data collection of other similar projects Site survey and interview to the people Hearing to the governmental organization concerned
24. Cultural heritage	<ul style="list-style-type: none"> Cultural heritage in and around the project sites 	<ul style="list-style-type: none"> Identification of affected area Confirmation of existing structures to be affected Site survey and interview to the people Hearing to the governmental organization concerned
28. Hazard (Risk) Infectious diseases such as HIV/AIDS	<ul style="list-style-type: none"> Possibility of inflectional diseases occurrence by hiring of labors 	<ul style="list-style-type: none"> Data collection of other similar projects
29. Work environment including safety	<ul style="list-style-type: none"> Possibility of accident 	<ul style="list-style-type: none"> Data collection of other similar projects
30. Accident	<ul style="list-style-type: none"> Possibility of accident 	<ul style="list-style-type: none"> Data collection of other similar projects

*The number of each item in table above is unified with that in Table 7.4.1 Scoping Result.

Source: JICA Survey Team

7.5 Results of Environmental Examination

7.5.1 Ecological Survey

Following the Terms of Reference indicated in Table 7.4.2, a series of ecological survey in Liguasan Marsh was done in and around the Lower Malitubog Area in July 2017. 15 points were established as the fish sampling points as illustrated in following figure, and the caught fish species were identified. Moreover, interview survey was also implemented to gain further information related to fish range.




Figure 7.5.1 Fish Survey Points

Source: JICA Survey Team



Source: JICA Survey Team

As of July 2017, the surveyed area was inundated, and water depth of the survey points was around 3-4 m. The area around the survey points is vegetated in general, partly with coconut, bamboos, water hyacinth, banana, bamboo, while structures are rarely identified. Following photos illustrate current conditions in the survey points.

Concerning bird survey, both spot-survey and transect survey were applied to identify bird species in the area. The spot survey was implemented at 99 points, while 22 survey lines which have various length were established as the transect survey (see Figure 7.5.2). In addition to the surveys at the field, some interviews to the people were also done to gain further information related to fish and birds in the marsh.





Figure 7.5.2 Bird Survey Points and Transect Routes

Source: JICA Survey Team

1) Fish Survey Results

Ten fish species were identified by the spot-survey while two species were done by the interviews, in other words, 12 species in total were identified. It is unveiled that *Oreochromis niloticus* (Nile tilapia), *Channa striata* (Mudfish) and *Cyprinus carpio* (Common carp) are dominant, especially, the number of *Oreochromis niloticus* (Nile tilapia) is very big. Regarding *Anguilla sp.* (Eel), *Mesopristes sp* (Cross-Barred Grunter) and *Mesopristes sp* (Cross-Barred Grunter), only one was caught, respectively. The identified fish species are shown in Table 7.5.1 and Figure 7.5.3.



Anguilla Anguilla (European eel)



Cyprinus carpio (Common Carp)



Oreochromis niloticus (Nile Tilapia)



Channa striata (Mudfish)



Barbodes sirang (Sirang)

Source: JICA Survey Team

Table 7.5.1 Identified Fish Species

Fish species	No. of caught fish	No. of caught sites	Category in IUCN Red list
1. <i>Cyprinus carpio</i> (Common Carp)	79	13 sites	VU: Vulnerable
2. <i>Channa striata</i> (Mudfish)	54	7 sites	LC: Least concern
3. <i>Helostoma temminckii</i> (Kissing Gourami)	15	7 sites	LC: Least concern
4. <i>Oreochromis niloticus</i> (Nile Tilapia)	198	All 15 sites	Not categorized in IUCN Red List
5. <i>Anguilla sp.</i> (Eel)	1	1 site	CR: Critically Endangered
6. <i>Anabas testudineus</i> (Climbing Perch)	7	3 sites	Not categorized in IUCN Red List
7. <i>Barbodes sirang</i> (Sirang)	32	5 sites	VU: Vulnerable
8. <i>Mesopristes sp</i> (Cross-Barred Grunter)	3	1 site	LC: Least concern
9. <i>Hypostomus placostomus</i> (Janitor fish /Suckermouth catfish)	4	2 sites	Not categorized in IUCN Red List
10. <i>Clarias batrachus</i> (Catfish)	3	1 site	LC: Least concern
11. <i>Labeo rohita</i> (Indian rohu carp)			LC: Least concern
12. <i>Trichopodus pectoralis</i> (Siamese gourami)			LC: Least concern


CR: facing an extremely high risk of extinction in the wild, **EN:** facing a very high risk of extinction in the wild, **VU:** facing a high risk of extinction in the wild, **NT:** qualifying for or is likely to qualify for a threatened category in the near future, **LC:** not qualify for CR, E, VU and NT, widespread and abundant taxa are included in this category.

Source: JICA Survey Team

IUCN: International Union for Conservation of Nature

Remarks: Highlighted species are listed as daggered in IUCN Red list. DENR Administrative Order No. 2004-15 specifies endangered species to be conserved, however, no fish species is listed in the Order.

Source: JICA Survey Team

**Figure 7.5.3 Fish Population and Species by Spot**

Source: JICA Survey Team

In 1998, an ecological survey was implemented by NEDA Region XII Office in 1998 and the results were compiled as the “Liguasan Marsh Development Master Plan 1999-2025”. According to the survey in 1998, 33 fish species have ranged in Liguasan Marsh, while 12 species were identified as of July 2017. Following table compares the identified fish species in 1998 and 2017.

Table 7.5.2 Identified Fish Species in 1998 & 2017 and Impacts of Introduced Species

No	Name of Fish Species	Identified in 1998	Identified in 2017	Impact
1	<i>Anabas testudineus</i> (Climbing perch)	○	○	Beneficial
2	<i>Anguilla celebesensis</i> (Celebes eel)	○	None	
3	<i>Anguilla marmorata</i> (Marbled Eel)	○	None	
4	<i>Anguilla pacifica</i> (Blackhead eel)	○	None	
5	<i>Anguilla spengeli</i> (Short fin eel)	○	None	
6	<i>Anguilla spp.</i> (Eel)	None	○	

No	Name of Fish Species	Identified in 1998	Identified in 2017	Impact
7	<i>Barbodes sirang</i> (Sirang)	None	○	
8	<i>Channa striata</i> (<i>Ophicephalus striatus</i>) (Mudfish)	○	○	Invasive
9	<i>Chanos chanos</i> (Milkfish)	○	None	
10	<i>Clarias batrachus</i> (Catfish)	○	○	Invasive
11	<i>Clarias gill</i> (EeLeast Concernatfish)	○	None	
12	<i>Clarias microcephalus</i> (Freshwater catfish)	○	None	
13	<i>Ctenogobius criniger</i> (Gobby)	○	None	
14	<i>Cyprinus carpio</i> (Common carp)	○	○	Beneficial
15	<i>Glossogobius biocellatus</i> (Sleeping goby)	○	None	
16	<i>Glossogobius celebius</i> (Rock goby)	○	None	
17	<i>Glossogobius giurus</i> (White goby)	○	None	
18	<i>Hypophthalmichthys molitrix</i> (Silver carp)	○	None	Beneficial
19	<i>Helostoma temminckii</i> (Kissing gourami)	○	○	Beneficial
20	<i>Hypostomus placostomus</i> (Janitor fish /Suckermouth catfish)	None	○	
21	<i>Illana bicirrhosa</i> (Goby)	○	None	
22	<i>Labeo rohita</i> (Indian rohu carp)	○	○*	Beneficial
23	<i>Liza subviridis</i> (<i>Mugil sp.</i>) (Freshwater mullet)	○	None	
24	<i>Liza viagiensis</i> (<i>Liza viagiensis</i>)	○	None	
25	<i>Lutjanus sp.</i> (Snapper)	○	None	
26	<i>Megalops sp.</i> (Tarpon)	○	None	
27	<i>Mesopristes sp</i> (Cross-Barred Grunter)	None	○	
28	<i>Oreochromis mossambicus</i> (Mozambique tilapia)	○	None	Beneficial
29	<i>Oreochromis niloticus</i> (Nile tilapia)	○	○	Beneficial
30	<i>Osphronemus gourami</i> (<i>Giant gourami</i>)	○	None	Beneficial
31	<i>Puntius binotatus</i> (Common barb)	○	None	
32	<i>Puntius javanicus</i> (Javanese barb)	○	None	
33	<i>Scatophagus argus</i> (Scats/spotted butterfly fish)	○	None	
34	<i>Therapon cancellatus</i> (<i>Mesopristes cancellatus</i>)	○	None	
35	<i>Tilapia rendalli</i> (<i>Tilapia rendalli</i>)	○	None	
36	<i>Tilapia zilli</i> (<i>Tilapia zilli</i>)	○	None	
37	<i>Trichopodus pectoralis</i> (Siamese gourami)	○	○*	
Total		33	12	

* *Labeo rohita* (Indian rohu carp) and *Trichopodus pectoralis* (Siamese gourami) range in the marsh according to local fisher folks, however, they are not identified by the survey in 2017.

**Hatched fish species are endangered according to the IUCN Red list.

Source: 1) NEDA Region XII, 1998, The Liguasan Marsh Development Master Plan 1999-2025

2) JICA Survey Team, 2017

3) Rafael D. Guerreoro III, 2014, Philippine Journal of Science 143 (1), Impacts of Introduce Freshwater Fishes in the Philippines (1905-2013): A Review and Recommendations

In Philippines, various fish species have been introduced to inland water area for food, ornamental purpose, recreational fishing and mosquito control. Some of them are beneficial for income improvement, while others are invasive for epidemic species. Out of commonly identified fish species by the survey, two fish species, namely, *Channa striata* (*Ophicephalus striatus*) (Mudfish) and *Clarias batrachus* (Catfish) are classified as “invasive” as shown in table mentioned above.

It is noted that Regional Fisheries Training and Fisher folk Coordination Center (under the Bureau of Fisheries and Aquatic Resources XII) has produced and dispersed fingerlings of *Oreochromis niloticus* (Nile tilapia) to Local Government Units, fisher folk groups and individuals since 2002 every year. In 2017, Nile tilapia was released to inland waters, which means that the certain amount of the fish species reach to Liguasan Marsh by such activities of human beings. Considering those situations, it is probably difficult to know original fish ecosystem of the Liguasan Marsh at this moment.

Due to the Project, the conditions of Liguasan Marsh will not be changed, given that inundated area of the Marsh is seasonally and annually changed drastically even now. Southern part of the LMSA is inundated for only 0-20% of a year (=0 to 73 days per year). It means that the area is dried up most of the year and seasonal change is very big. Under such severe condition, the fish have survived so far.

The proposed construction works will not cause significant hydrological change, which leads to minor impact on the fish eco-system. However, there is a possibility that excessive fish catch and exotic fish introduction can lead to change of fish eco-system in the marsh, and balanced management is recommended.

2) Birds Survey Result

In total, 63 bird species were identified by the spot-survey, transect survey and interview to the people in July 2017 (see Appendix VII). They are mainly, *Ardeola speciosa* (Javan Pond Heron), *Ardea purpurea* (Purple Heron), *Ixobrychus sinensis* (Yellow Bittern), *Halias turindus* (Brahminy Kite), *Himantopus himantopus* (Black-winged Stilt), *Merops philippinus* (Blue-tailed Bee-eater) and *Gallinula chloropus* (Common Moorhen). The survey did not observe *Haliastur indus* (Philippine duck) and *Anhinga melanogaster* (Oriental darter) at the field, while the NEDA study did them in 1998. However, some key informants positively identified them in the survey area, therefore, these species are also included in the 63 bird species above. 53 species were identified by NEDA in 1998, and 23 species are common in the both survey results.



Source: JICA Survey Team

Out of identified species by the survey in 2017, *Haliastur indus* (Philippine duck) and *Anhinga melanogaster* (Oriental darter) are classified endangered species in the IUCN Red List. According to the people interviewed, Philippine duck is rarely observed recently, and they attribute the decline of the bird to hunting. IUCN also mentions that hunting is a major threaten for the species. Apart from those two species, DAO 2004-15 classifies five species out of 63 species identified, namely, *Haliastur indus* (Brahminy Kite) and so on to those which trade must be controlled. These endangered bird species are shown in following table.

Table 7.5.3 Endangered Bird Species Identified by the Survey

No	Name of Fish	IUCN Red list	DAO 2004 (As of 2014)
1	<i>Haliastur indus</i> (Brahminy Kite)	LC: Least Concern	EN II
2	<i>Elanus caeruleus</i> (Black-winged Kite)	LC: Least Concern	EN II
3	<i>Circus melanoleucos</i> (Pied Harrier)	LC: Least Concern	EN II
4	<i>Anas luzonica</i> (Philippines duck)*	VU: Vulnerable	VU
5	<i>Anhinga melanogaster</i> (Oriental Darter)*	NT: Near Threatened	VU
6	<i>Loriculus philippensis</i> (Philippine Haninging-parrot)	LC: Least Concern	EN (II)
7	<i>Bolbopsittacus lunulatus</i> (Guaiabero)	LC: Least Concern	EN (II)

EN I: species threatened with extinction. Trade in specimens of these species is permitted only in exceptional circumstances

EN II: species not necessarily threatened with extinction, but in which trade must be controlled in order to avoid utilization incompatible with their survival


*Philippine duck and Oriental darter were not identified by the spot and transect survey, however, they are observed by the people.

Source: JICA Survey Team

Haliastur indus (Brahminy Kite) and *Elanus caeruleus* (Black-winged Kite) were observed in plural survey points and transect routes, while *Circus melanoleucos* (Pied Harrier), *Loriculus philippensis* (Philippine Haninging-parrot) and *Bolbopsittacus lunulatus* (Guaiabero) were identified at very limited sites. However, the Project, construction of irrigation canal, drainage and access roads in LMSA is not expected to give a severe damage to habitat of those birds. Rather than the impacts by the Project, hunting of those bird species is probably a bigger issue to be managed.

7.5.2 Water Quality Test

Water samples were taken at the 15 points as well as the fish survey for the laboratory test to understand current water quality conditions as illustrated in following figure. The result of water quality check is compiled in Table 7.5.4.

**Figure 7.5.4 Water Sampling Points**

Source: JICA Survey Team

Table 7.5.4 Water Quality Check Result

Sampling point	Trial	Sampling Date	pH	Temperature (°C)	EC (µS/cm)	TDS (mg/l)	DO (ppm)	BOD (ppm)	COD (ppm)	Water Depth (m)
1	1	7/16/2017	7.96	28.2	282	176	4.12	10.6	36.7	4.1
	2		8.05	28.6	286	173	4.43	10.4	36.7	
2	1	7/17/2017	8.32	27.3	269	169	4.02	10.3	52.0	3.6
	2		8.24	26.8	274	175	4.19	10.3	52.0	

Sampling point	Trial	Sampling Date	pH	Temperature (°C)	EC (µS/cm)	TDS (mg/l)	DO (ppm)	BOD (ppm)	COD (ppm)	Water Depth (m)
3	1	7/18/2017	8.02	27.8	278	182	3.69	10.3	24.4	4.2
	2		8.11	27.5	272	184	3.83	10.2	27.5	
4	1	7/9/2017	7.68	27.6	253	189	4.45	10.5	3.0	3.2
	2		7.57	27.8	252	183	4.40	10.6	6.1	
5	1	7/10/2017	7.72	27.2	271	191	4.46	10.8	3.0	4.1
	2		7.66	27.6	261	182	4.36	10.7	3.0	
6	1	7/19/2017	7.89	27.6	283	186	4.63	10.1	43.9	2.3
	2		8.01	28.1	289	181	4.47	10.0	40.8	
7	1	7/20/2017	8.17	27.3	279	186	4.11	10.0	18.8	4.7
	2		8.28	27.7	281	191	4.17	9.9	15.7	
8	1	7/12/2017	8.19	31.1	258	182	4.84	10.7	58.1	3.6
	2		8.13	31.5	267	185	5.06	10.7	58.1	
9	1	7/3/2017	7.87	28.4	260	178	4.49	10.1	41.6	3.6
	2		7.73	28.6	266	190	4.57	10.0	38.4	
10	1	7/12/2017	7.76	33.7	374	263	4.46	10.4	27.5	3.4
	2		7.75	32.8	290	205	4.65	10.3	27.5	
11	1	7/7/2017	7.79	31.9	428	338	4.43	10.3	9.6	1.5
	2		7.62	27.6	446	285	4.38	10.3	9.6	
12	1	7/8/2017	7.92	27.7	324	234	4.39	10.6	3.2	4.0
	2		7.80	27.7	290	210	4.43	10.5	3.2	
13	1	7/11/2017	7.88	27.0	248	173	4.53	10.3	52.0	6.7
	2		7.78	27.3	243	170	4.50	10.3	48.9	
14	1	7/4/2017	8.11	23.7	281	196	4.65	10.2	51.2	4.0
	2		8.00	27.4	263	193	4.53	10.1	48.0	
15	1	7/5/2017	7.83	27.9	252	188	4.52	10.0	48.0	3.8
	2		7.63	28.3	258	192	4.51	9.9	44.8	
Standard in Philippines* (DAO No.34, 1991)			6.5-8.5			<1,000	>3.0 >5.0	<7.0 <10.0		

*1 Permissible threshold value of TDS is 1,000mg/l and less for Class C.

*2 Permissible threshold values of DO are 5mg/l and 3mg/l and more for Class C and Class D.

*3 Permissible threshold values of BOD are 7mg/l and 10mg/l and less for Class C and Class D.

Source: JICA Survey Team

According to the result, water salinity of the samples is within the standard set by DAO No.34, 1991, which is mentioned in Table 7.2.4. On the other hand, values of DO in some samples are not within the standard, while all of samples' BOD values exceed the standard. The reason for this situation is not clear, however, it is probably because that the water is stagnant with limited fresh water flow, considering that there are few houses discharging effluent around the sampling points. The Project in LMSA will not change the hydrological conditions, which leads to minor impacts on water quality.

7.6 Environmental Evaluation

1) Air Pollution

During construction stage, major construction machineries to be used are excavator, dozer, roller, loader, truck, and trailer truck. These machineries emit exhaust gasses to some extent. Moreover, dust may be generated by the construction works. However, the targets sites are located on along farmlands with few residential houses. Therefore, the expected impacts by the Project are not very significant.

Concerning operation stage, emission from vehicles will be increased due to the access road construction and increase of traffic. However, the proposed roads will pass through the areas where farmlands stretch widely with small number of houses. Moreover, busy season will be limited to planting and harvesting seasons. Therefore, the problem of air quality is expected to be minor.

2) Water Pollution

During the construction works, turbid water may be generated from construction sites; however, it can be caused only during the construction period. The level of the turbidity is not expected to be

significant and it is possible to establish sedimentation pond to minimize the mud water discharge. Therefore, such water pollution can be managed to the acceptable level, and it is not considered as a major issue.

As the water quality test shows, water quality in and around LMSA is almost equivalent to Class C, which is suitable for fishery, and it means that current water quality can be regarded as not very clean. Concerning application of chemical fertilizer and pesticide, amount of those materials will be increased after the Project. However, given that current amount of fertilizer and pesticide application is relatively small compared with national average as discussed in Chapter 7.3.6, expected negative impacts by the Project could not be very severe. Still, it is needed to organize training concerning proper application of fertilizers and pesticides.

3) Waste

Wastes, namely, excavation of soils will be generated during construction and it can be reused for the backfilling of embankment. Even after having re-used such waste, there may be a possibility that some excessive wastes still remain, in such case, remaining soil can be dumped along the canal. Other remaining materials shall be disposed at specified sites. In addition, waste from the labor camp will be generated, and it should be classified and disposed based on regulations in Philippines. Such waste generation will be limited to only construction stage.

4) Soil Contamination

At the construction stage leakages of liquids, such as oil and fuel, from the vehicles and other equipment could take place. However, this impact is short term, relatively low. Regular check of the construction vehicles is necessary to prevent oil leakage.

5) Noise/Vibration

Noise and vibration will be caused by the construction works and increase of traffic; however, the proposed canals, drainages and access roads are located on along farmlands and the number of residential houses in the area is limited. Therefore, noise and vibration generated from the works will not be significant.

In operation stage, noise/vibration will be increased compared with before due to establishment of the access roads and increase of traffic. However, as mentioned, the new roads will pass through farmlands instead of residential area, which will lead to minor impacts.

6) Hydrological Situations

During construction stage, there is a possibility that constructed embankment of canal can prevent water flow of small waterbodies such as creeks and streams within the inundated area for several days. Thus, it is needed to establish cross-drains in and around the site prior to the construction works to avoid negative effect to natural water bodies and inundation.

Amount of water intake at the diversion dam will be increased, which will reduce Maridagao River discharge. However, Maridagao River flows into Pulangi River soon, and severe hydrological change is not expected. On the other hand, construction of canals and drainages by the Project will shorten inundation period at the beginning of dry season, which will not cause dynamic change of water flow. The Liguasan Marsh and its surrounding inundated area change its size seasonally and annually at this moment, and expected change by the Project is minor compared with such changes. Therefore, it can be said that significant impact on hydrological situations by the Project will not be caused.

7) Ecosystem

As mentioned in Chapter 7.5.1, some rare fish species range in and around Liguasan Marsh. However, the construction of proposed facilities will not disturb migration of fish including rare species such as European eel, and habitat of other fish, considering that hydrological situations will not be changed significantly. *Barbodes sirang* is native in Philippines, and one of major threats on the fish is the fishing style by using dynamite or poison, which can kill all of them including fly according to IUCN. It is, thus, such fishing method should be controlled at first apart from the Project implementation.

Concerning bird species, it is also necessary to control illegal hunting to conserve endangered species such as Philippine duck and *Anhinga melanogaster* (Oriental Darter). Moreover, construction of canals, drainages and access roads will not disturb habitat area of birds, and it is judged that negative impacts on ecosystem of the Project will be minor.

8) Involuntary Resettlement and Land Acquisition

Detail situations are described in Chapter 7.10. Some lands had been acquired for the Project by NIA, and compensation for damage to crops/structures had been partly provided. On the other hand, identification of PAPs and damaged crops/structures in the area, where construction works will be started since 2019, has not been commenced. The PAPs, except only one household in MMIP I area, have not agreed at the proposed compensation rates for land loss. It is recommended for NIA-PMO to have meetings with PAPs to negotiate agreeable compensation rates, and to pay compensation for land loss prior to the construction works. Moreover, it is also recommended to pay compensation for land loss due to drainage construction, it is not planed at present, though.

9) The Poor

The socio-economic survey (JICA Survey Team, 2017) revealed that the average household income in LMSA is P88,786 (see Chapter 7.3.5), and the amount is between average ones in Region 12 and ARMM area, namely, P193,438 and P85,514, respectively. Average income per capita can be estimated at P16,912, when 88,786 mentioned above is divided by 5.25, average number of family members per household. The Philippines Statistics Authority sets the poverty line at P21,025 and P21,563 per capita for the Region 12 and ARMM, respectively, under the condition, the living standard in LMSA is categorized into “poor”. Still, given that the Project contributes to farming improvement, the Poor will not be negatively influenced by the Project.

10) Indigenous People/Minority People

Detail study results on indigenous people/minority people are mentioned in Chapter 7.11, and it is revealed that indigenous people who continue their unique and traditional life style are not identified in the MMIP area. Therefore, negative impact on such people is not expected.

11) Livelihood/Local Economy

Due to the canal construction, the people can operate irrigation farming in dry season, which leads to stable crop cultivation. Moreover, they have to wait for dry-up of their farmlands for a while at the beginning of dry season at this moment, however, the period for waiting can be shortened due to the drainage construction. As a whole, crop productivity will be improved after the construction works. In addition, the beneficiaries of MMIP I recognize that the increase of agricultural potential and establishment of access roads by MMIP I also have improved various public services including non-agricultural sectors (JICA Survey Team, 2017). Implementation of MMIP II is also expected to contribute to improvement of entire local economy.

12) Land Use and Local Resource Utilization

As discussed, land acquisition is necessary for the Project implementation, and it is needed to pay fair compensation for land loss. On the other hand, LMSA is generally used as farmland at this moment, main purpose of land use will not be changed by the Project.

13) Water Usage/ Water Rights

At the diversion dam, it had been planned to divert water for both MMIP I area and MMIP II area from the beginning, and the water diversion for LMSA has been already accepted. Therefore, it is not necessary to acquire new water right, and existing water right will not be spoiled by MMIP II.

14) Existing Social Infrastructure and Services

During the construction works, it is expected that traffic jam will be caused by the increase of construction vehicles, and actually, transportation becomes busy in some parts of LMSA, where the construction works are on-going. In operation period also, traffic will be busy due to the construction of access roads, however, the extent of traffic jam will not very significant considering that areas along the proposed roads are used as farmlands at this moment.

15) Social Institutions

There are 21 groups in LMSA, and they are categorized into social welfare (12 groups), farming (8 groups) and education (one group) in terms of purpose of the group. Those groups have experiences to be supported by the government so far, which means that these institutions are ready for functioning in the process of irrigation management transfer after the MMIP II completion. In addition, Irrigator's Association (IA) were set up by the governmental support in the MMIP I area, and the people recognize that the organizations function actively for water management after a series of training sessions (JICA Survey Team, 2017). Therefore, MMIP II would give positive impacts on the area by new organization establishment¹¹ and collaboration with existing groups.

16) Misdistribution of Benefit and Damage

Due to the Project, farm income would be stable by irrigation farming in dry season, while the PAPs will lose their farmlands and crops, which leads to misdistribution of benefit and damage. It is, thus, payment of compensation to the PAPs is very important to minimize such misdistribution.

17) Conflict

One of negative impacts by MMIP I, which were identified by the people, is increase of conflict on water distribution within a Barangay due to irrigation service commencement (JICA Survey Team, 2017). The same issue can be caused in LMSA also, it is, thus, necessary to take countermeasures. For instance, establishment of IA, rule setting for even water distribution, organization of training sessions by NIA and so on are to be practiced.

18) Cultural Heritage

Municipality of Pikit has a cultural heritage, namely, Fort of Pikit, which was built in 1893 by the Spanish Colonial Government. The National Historical Commission of the Philippine had declared the fort as a National Historical Landmark in March 2012. Except for Fort of Pikit, there is no cultural heritage in and around the LMSA.

¹¹ In LMSA, 13 Irrigators Associations have been established and 8 more associations are to be established.

19) Hazard (risk) of Infectious Diseases such as HIV/AIDS

There will be a number of labors hired during the construction stage. Under such situation, there may be a possibility of extending infectious diseases such as TB, and HIV/AIDS among the labors, though with reference to similar construction works, no noticeable examples have been reported so far. It is needed to always pay attention to the labors' health condition. Also, awareness creation on HIV/AIDS shall be made among the labors.

20) Work Environment /Accidents

There is a possibility of some accidents by the construction works and traffic accidents. Therefore, safety measures should be addressed prior to the commencement of the Project. It is needed to make a schedule to assign enough number of watchmen to avoid accidents. In addition, pre-explanation to workers employed at sites should be made well, so that the works will be done in a safe manner. In operation period also, there is a possibility that the number of traffic accidents is increased due to access road construction.

Table 7.6.1 Environmental Evaluation

Items	Scoping		Evaluation		Reason for Evaluation
	Before and during construction	Operation stage	Before and during construction	Operation stage	
1. Air Quality	B ⁻	C	B ⁻	D	<p>Construction stage: Dust and gas emission will be caused, which leads to air pollution in and around the construction site. However, as the area is generally farming area, the extent of impact is limited.</p> <p>Operation stage: Increase of vehicles is expected due to the access road construction, however, the purpose is transportation of harvested crops, and the proposed roads will pass through farmlands and cross some rural roads where houses are located on. Thus, issue of air quality will be negligible for the surrounding people.</p>
2. Water Quality	B ⁻	B ⁻	B ⁻	B ⁻	<p>Construction stage: Mud water from the construction site will be caused.</p> <p>Operation stage: Due to the development of farmland, total amount pesticides/fertilizers to be applied can be increased, however, the current amount is small compared with average amount at the national level, and the Project will not cause a severe problem.</p>
3. Waste	B ⁻	D	B ⁻	N/A	<p>Construction stage: Waste from construction works and labor camps will be generated.</p> <p>Operation stage: No waste due to the operation of the constructed facilities is expected.</p>
4. Soil Contamination	C	D	B ⁻	N/A	<p>Construction stage: Oil leakage from construction vehicles and equipment is expected.</p> <p>Operation stage: Negative impact on soil is not expected.</p>

Items	Scoping		Evaluation		Reason for Evaluation
	Before and during construction	Operation stage	Before and during construction	Operation stage	
5. Noise and Vibration	B ⁻	C	B ⁻	D	<p>Construction stage: Noise and vibration due to the construction works are expected.</p> <p>Operation stage: Traffic will be increased by the access road construction, however, the proposed roads will pass through farmlands and across some rural roads where some houses are located on along. Thus, noise/vibration will not be a big issue for the surrounding people.</p>
6. Ground Subsidence	D	D	N/A	N/A	<p>Construction stage /Operation stage: During construction and operation, ground subsidence will not be caused, since there is no plan to use ground water.</p>
7. Offensive Odor	D	D	N/A	N/A	<p>Construction stage /Operation stage: Any works to cause offensive odor is not planned.</p>
8. Bottom Sediment	D	D	N/A	N/A	<p>Construction stage /Operation stage: Any works to caused bottom sediment is not planned.</p>
9. Protected Area	D	D	N/A	N/A	<p>Construction stage /Operation stage: There is no protected area in and around the project site.</p>
10. Ground Water	D	D	N/A	N/A	<p>Construction stage /Operation stage: Use of groundwater is not planned for the Project, which results in no damage to groundwater.</p>
11. Hydrological Situation	C	B ⁻	B ⁻	D	<p>Construction stage: During the construction stage, construction of embankment can prevent drainage or water flow of natural waterbodies, which leads to inundation around the construction site.</p> <p>Operation stage: Construction of canals and drainages will not cause dynamic change of water flow. Furthermore, size and extent of Liguasan Marsh are changed seasonally and annually, and expected change by the Project is minor. It is, thus, significant impact on hydrological situations would not be caused.</p>
12. Ecosystem	D	C	N/A	D	<p>Construction stage Lands in and around the construction sites have been already developed for agricultural purpose and there is no virgin nature to be damaged by the Project.</p> <p>Operation stage: Fish and birds in and around Liguasan Marsh will not be influenced by the Project, considering no dynamic change of hydrological condition.</p>
13. Topography and Geographical Features	D	D	N/A	N/A	<p>Construction stage: Current farmlands are to be changed into canals, drainages, and roads. However, it is change of land use, not a topographical change.</p> <p>Operation stage: Once operation is started, not change will be caused.</p>
14. Involuntary Resettlement/ Land Acquisition	B ⁻	D	B ⁻	N/A	<p>Before construction stage: For the Project implementation, land acquisition, and damage to standing crops/structures are expected. Since some construction works have been started by NIA prior to payment for the land loss. It is requested for NIA to reach agreement with the PAPs for compensation rates and to finalize payment very soon.</p> <p>Construction/Operation stage: No impacts are expected.</p>

Items	Scoping		Evaluation		Reason for Evaluation
	Before and during construction	Operation stage	Before and during construction	Operation stage	
15. The poor	C	C	D	D	Construction/Operation stage: Negative impacts on the poor are not expected.
16. Indigenous and Ethnic People	C	C	D	D	Before construction/Operation stage: It was confirmed that there is no overlap between the entire MMIP site and the said Ancestral Domain (see Figure 7.11.2). No influence on indigenous people is expected.
17. Livelihood/Local Economy	B ⁻ /B ⁺	B ⁺	B ⁻ /B ⁺	B ⁺	Construction stage: Given that the Project will provide job opportunities as construction labors for the local people, positive impacts are expected. On the other hand, the Project will cause negative impacts on some people whose land will be acquired. Operation stage: Stable agricultural production can be performed due to stable irrigation water supply.
18. Land Use and Local Resource Utilization	B ⁻	D	B ⁻	N/A	Construction stage: It is needed to acquire lands for construction of canals, roads and drainages, which would change current land use. Operation stage: No negative impact on land use and local resource utilization is expected.
19. Water Usage or Water Rights and Rights of Common	D	B ⁻ /B ⁺	N/A	B ⁻ /B ⁺	Construction stage: The construction works will not give a change of water usage system or water use rights. Operation stage: Due to canal construction, the people will be able to access to irrigation water. However, conflict as for water distribution could be caused.
20. Existing Social Infrastructures and Services	B ⁻	B ⁺ /B ⁻	B ⁻	B ⁺ /B ⁻	Construction stage: Due to increase of construction vehicles, traffic jam can be caused. Operation stage: Due to construction of access roads, the people access to road more easily than before, while traffic will be increased.
21. Social Institutions	C	C	D	D	Construction stage: No negative impact is expected. Operation stage: There are some organizations, e.g., for social welfare, agriculture, education and so on. Those will not be negatively influenced by the Project. IA will function in MMIP II area, and it is expected to contribute to farming improvement.
22. Misdistribution of Benefit and Damage	B ⁻	D	B ⁻	D	Before construction stage: Some land owners will lose their farmlands, while others are informed of the Project benefit, which may cause feeling of inequality. It is, thus, needed to provide sufficient compensation. Operation stage: Due to the Project, the beneficiaries can enjoy the profit, while others whose farmland can be inundated are unhappy with the situations.
23. Conflict	D	B ⁻	N/A	B ⁻	Construction stage: Due to the construction works, conflict between the beneficial area and affected area is not expected. Operation stage: There is a possibility that any conflicts on water distribution are caused within a Barangay, considering the case of MMIP I area.

Items	Scoping		Evaluation		Reason for Evaluation
	Before and during construction	Operation stage	Before and during construction	Operation stage	
24. Cultural Heritage	C	C	D	D	Construction /Operation stage: There are no cultural heritages to be damaged by the Project.
25. Land Scope	D	D	N/A	N/A	Construction /Operation stage: The areas in and around the project sites are mainly farmlands, therefore, special land scape to be reserved is not identified.
26. Gender	D	D	N/A	N/A	Construction /Operation stage: Negative impact on women is not expected.
27. Rights of the Child	D	D	N/A	N/A	Construction /Operation stage: Negative impact on children is not expected.
28. Hazards (Risk), Infectious Diseases such as HIV/AIDS	B ⁻	D	B ⁻	N/A	Construction stage: There is a possibility that infectious disease HIV/AIDS could be caused by employment of workers from other areas. Operation stage: After the construction works, no disease is expected.
29. Work Environment	B ⁻	D	B ⁻	N/A	Construction stage: There is a concern of accident at the construction sites. It is needed to comply with the labor code for safety. Operation stage: No labor environmental change in the beneficial area is expected, since irrigation farming has been operated in the area.
30. Accident	B ⁻	B ⁻	B ⁻	B ⁻	Construction stage: There is a concern of traffic accident at the construction sites. Moreover, there is a concern of accident to construction of canals, which will be very limited. Operation stage: Due to the access road construction, there can be some traffic accidents.
31. Transboundary Impact, Climate Change	D	D	N/A	N/A	Construction stage: Large amount of greenhouse gas, which can cause climate change, will not be emitted by the Project. Operation stage: The rivers concerned to the Project, finally merge into Mindanao River, which flow into the sea. There is no international river concerned.

*Environmental impacts are anticipated for the highlighted environmental items.

A+/-: Significant positive/negative impact is expected.

B+/-: Positive/negative impact is expected to some extent.

C+/-: Extent of positive/negative impact is unknown. (A further examination is needed, and the impact could be clarified as the study progresses)

D: No impact is expected.

7.7 Mitigation Measures and Cost

Some adverse effects by the project, e.g., air pollution, wastes, noise/vibration are anticipated before construction stage/construction stage and operation stage. For the purpose of alleviation of such negative impacts by the Projects, following countermeasures shown in tables below are recommended to be done.

**Table 7.7.1 (1) Mitigation Measures to/against the Negative Impacts:
Before Construction/Construction Stage**

Negative impact	Alleviating or avoiding measures	Responsible Agency	Cost
1. Air Pollution Exhaust gas emission takes place. Dust occurs during the passage of	<ul style="list-style-type: none"> Conduct regular check and full maintenance of construction machineries and vehicles. Spray water in and around entrances of construction 	NIA	Included in construction cost

Negative impact	Alleviating or avoiding measures	Responsible Agency	Cost
construction vehicles.	sites and on the road, along which machineries are to move.		
2. Water Pollution Mud water can be discharged into downstream.	<ul style="list-style-type: none"> Prevent turbid water from going down by establishment of sedimentation pond 	NIA	Included in construction cost
3. Wastes Excavated earth evolves from some construction works and waste scrap pieces from construction works.	<ul style="list-style-type: none"> Dispose wastes such as used drums for the works according to construction regulation in Philippines Dumping of soil along the canals, drainages and roads 	NIA	Included in construction cost
4. Soil Contamination	<ul style="list-style-type: none"> Conduct regular check and full maintenance of construction machineries and vehicles. Ensure to minimize oil leakage in case of oil charge 	NIA	Included in construction cost
5. Noise/ Vibration During construction work, noise/ vibration evolve from the operation of back-hoes and passage of trucks., etc.	<ul style="list-style-type: none"> Refrain construction work at night in such areas where residential quarters are located. 	NIA	Included in construction cost
11. Hydrological Situation	<ul style="list-style-type: none"> Establishment of drainage system in and around the construction site for smooth drainage prior to the construction of irrigation canals 	NIA	Included in construction cost
14. Land Acquisition	<ul style="list-style-type: none"> Compensation for the land loss and damaged crops/structures to the affected persons 	NIA	Covered by budget of NIA
17. Livelihood/Local Economy	<ul style="list-style-type: none"> Compensation for the land loss and damaged crops/structures to the affected persons 	NIA	Covered by budget of NIA
20. Existing Social infrastructure and Services Traffic jam will be caused.	<ul style="list-style-type: none"> Prepare a schedule which deconcentrates vehicle operation 	NIA	Included in construction cost
22. Misdistribution	<ul style="list-style-type: none"> Compensation for the land loss and damaged crops/structures to the affected persons 	NIA	Covered by budget of NIA
28. Hazards (Risk) of Infectious Diseases such as HIV/AIDS During construction stage, infectious diseases such as TB and HIV/AIDS may take place among the workers.	<ul style="list-style-type: none"> Pay attention to the workers' health condition Awareness creation on HIV/AIDS among the workers and recommend them to voluntary check the status of HIV/AIDS. 	NIA	Included in construction cost
29. Work Environment 30. Accident During construction work, traffic and/or site-work accidents may take place.	<ul style="list-style-type: none"> Identify if there is too tight operation schedule or not, and if so rectify it. Place traffic control staff along the construction roads. Explain contents of the work to the workers with necessary care taking for their safety prior to the start of the work, and make daily confirming safe meeting before starting the work. 	NIA	Included in construction cost

Source: JICA Survey Team

Table 7.7.1 (2) Mitigation Measures to/against the Negative Impacts: Operation Stage

Negative impact	Alleviating or avoiding measures	Responsible Agency	Cost
2. Water Pollution Water quality deterioration by improper application of fertilizers and pesticides	<ul style="list-style-type: none"> Training of municipality officers and farmers Demo-farm setting to demonstrate proper fertilizer application 	ATI	Covered by ATI budget*
19. Water Usage or Water Rights and Rights of Common 23. Conflict Conflict as for water distribution can be caused	<ul style="list-style-type: none"> Establishment of IA Rule setting as for water distribution Assignment of water tenders 	NIA	Covered by NIA budget

*ATI can cover the budget as far as ODA loan is provided.

7.8 Monitoring Plan

Anticipated environmental impacts are expected in before construction/construction phase and operation phase, and thus related monitoring implementation is necessary in those phases. Recommended monitoring format is as follows:

Table 7.8.1 Recommended Monitoring Plan

(1) Pre-construction stage

(a) Public Consultation

No.	Date	Place	Contents of the consultation/ main comments and answers	Responsible Organization
1				NIA
2				NIA

(b) Progress of land acquisition

Land Acquisition Activities	Planned Total	Unit	Progress in Quantity			Progress in %		Expected Date of Completion	Responsible Organization
			During the Quarter	Till the Last Quarter	Up to the Quarter	Till the Last Quarter	Up to the Quarter		
Preparation RAP*									NIA
Employment of Consultants		Man-month							NIA
Implementation of Census Survey (including socioeconomic survey)									NIA
Approval of RAP			Date of Approval:						NIA
Finalization of PAPs List		No. of PAPs							NIA
Progress of Compensation Payment		No. of PAHs							NIA
Lot 1		No. of PAHs							NIA
Lot 2		No. of PAHs							NIA
Lot 3		No. of PAHs							NIA
Progress of Land Acquisition (all lots)		Ha							NIA
Lot 1		Ha							NIA
Lot 2		Ha							NIA
Lot 3		Ha							NIA

*Preparation of RAP is not a must for NIA, however, it is recommended to do that for proper compensation for land acquisition.
PAHs: Project affected households

(2) Construction Stage

(a) Response and actions by the government

Monitoring Item	Monitoring Results during Report Period	Responsible Organization
Number and contents of formal comments made by the public		NIA
Number and contents of responses from the people		NIA

(b) Pollution**- Air Pollution**

Item	Unit	Measured Value (Mean)	Measured Value (Max)	Country's Standards	Referred IFC Guidelines	Remarks (Measurement Point, Frequency, Method, etc.)	Responsible Organization
At construction site							
SO ₂	[µg/m ³] 24 hr			180	125 (Interim target-1) 50 (Interim target-2) 20 (guideline)	Once per month	NIA
PM10	[µg/m ³] 24 hour			150	150 (Interim target-1) 100 (Interim target-2) 75 (Interim target-3) 50 (guideline)	Once per month	NIA
NO ₂	[µg/m ³]			150 (24hr)	200 (hour)	Once per month	NIA
Ox	[µg/m ³] 8 hours daily max			60	100	Once per month	NIA
TSP	[µg/m ³] 24 hr			230	None	Once per month	NIA
Photochemical Oxidants	[µg/m ³] Hour			140	None	Once per month	NIA
Carbon Monoxide	[µg/m ³] 1 hour 8 hours			35 10	None	Once per month	NIA

- Maintenance of heavy machine

Type of machine	Kinds of disorder	Measures taken	Monitoring date	Responsible Organization
Hydraulic Excavator			Every day	Contractor
Hydraulic Breaker			Every day	Contractor
Track Dozer (Bulldozer)			Every day	Contractor
Wheel Loader			Every day	Contractor
Earth Work Vibration Roller			Every day	Contractor
Agitator Truck (Concrete Mixer Truck)			Every day	Contractor
Lowbed semi-Trailer Truck			Every day	Contractor
Dump Truck			Every day	Contractor
Concrete Pump Truck			Every day	Contractor
Workshop Equipment			Every day	Contractor

- Water pollution

Item	Unit	Measured Value (Mean)	Measured Value (Max)	Country's Standards	Referred IFC Guidelines (sanitary sewage water)	Remarks (Measurement Point, Frequency, Method, etc.)	Responsible Organization
Total Suspended Solid	mg/l			Not more than 30 mg/L increase*	<50	Once per month	NIA

*for Class C: Fishery water, recreational water class II, Industrial water supply class II

- Noise / Vibration

Item	Unit	Measured Value (Mean)	Measured Value (Max)	Country's Standards	Referred IFC Guidelines	Remarks (Measurement Point, Frequency, Method, etc.)	Responsible Organization
Noise	dB			<55 (daytime) <45 (night)	<55 (daytime) <45 (night)	Once per month	NIA

(c) Natural environment

Environmental parameter	Monitoring results	Measures taken	Monitoring date	Responsible Organization
Wastes Waste from the construction site shall be disposed at the specified sites following regulations			Every day	NIA
Hydrological situations Check of drainage from construction site			Every day	Contractor

(d) Social environment (Traffic Jam)

Environmental parameter	Monitoring results	Measures taken	Responsible Organization
Number of complaint about traffic jam			NIA

(e) Working environment (Include working safety)/ Accident

Environmental parameter	Monitoring results	Measures taken	Monitoring date	Responsible Organization
Safety check for carrying the heavy machineries into the work area.			First time of the construction work.	NIA
Safety check for refueling car accessing the work sites.			Every day	NIA
Safety check for carrying-out of the heavy machineries from the work sites.			Last time of the construction work	NIA
Checking of the heavy machineries if keeping correct routes and speed.			Every day	NIA
Installation of project sign board around the field.			First time of the construction work.	NIA

(f) Hazards (Risk) of Infectious diseases such as HIV/AIDS

Environmental parameter	Monitoring results	Measures taken	Monitoring date	Responsible Organization
Pay attention to the workers' health condition.			Every day	NIA
Arrange with the township health office to carry out awareness creation on HIV/AIDS among the workers.			Once half a year	NIA

Source: the Survey Team (2016)

(3) Operation Stage**(a) Response and actions by the government**

Comments and response	Monitoring results	Measures taken	Frequency	Responsible Organization
Number and contents of comments from the people, especially following matters: <ul style="list-style-type: none"> ● Even water distribution ● Conflict management 				NIA
Number and response to the comments from the government				NIA

Remarks: The format is to use for recording and reporting how the government (implementation agency) takes measures against any issues by the Project.

(b) Natural Environment

Environmental Parameter	Monitoring results	Measures taken	Frequency	Responsible Organization
Water pollution due to improper application of pesticides and fertilizers <ul style="list-style-type: none"> ● Regular training for proper application of pesticides and fertilizers 				NIA

Source: JICA Survey Team

7.9 Stakeholder Meeting

In the process of land acquisition for MMIP II, stakeholder meetings were organized several times to explain the Project and compensation policy since 2016 as shown in following table. It is noted that there should be more stakeholder meetings which have been organized by NIA PMO, however, no record is provided.

Table 7.9.1 Date and Target Barangay of Stakeholder Meeting

Date	Target Barangay	Municipality
July 23, 2014	Bulod	Pikit
July 9, 2015	Gligli	Pikit
Jan. 20, 2016	Macabual	Pikit
Jan. 26, 2016	Damalasak	Pikit
Jan. 27, 2016	Balong	Pikit
Jan. 28, 2016	Manaulanan	Pikit
Feb.5, 2018	Talitay	Pikit

*Participants numbers of male and female are 84 and 19, respectively.

Source: MMIP PMO

Minutes of each stakeholder meeting have not been prepared, however, main questions from the participants and answers are as follows:

Q1. What are the processes if the affected lot is not tilted?

A1. It is necessary to title at first, since payment is done based on the title.

Q2. We are tenant farmers, can we claim the compensation?

A2. You have right to claim only for damage to permanent crops you have planted.

Q3. How much compensation for permanent crops?

A3. There are tariff issued by the Provincial Assessors office. We will pay for damaged permanent crops based on the tariff.

Q4. Has this Project already been authorized by MILF?

A4. The Project has a clearance with MILF before the Project starts.

Q5. I am not an owner but I am titled the lots and it was justified by the previous Barangay Captain. Is it possible for me to get the compensation for the crop damage?

A5. Follow-up if there are still chances to justify the ownership by the ex-captain.



Meeting in Barangay Macabual

Source: NIA-PMO

7.10 Resettlement and Land Acquisition

7.10.1 Construction Progress

The construction of MMIP II in UMSA has been completed in 2014, and the construction has been on-going in the areas of PESA and mid-eastern part of LMSA since 2015, mid-part of LMSA since 2016, and western part of LMSA since 2017 as illustrated in following figure. Prior or in parallel with the physical construction, land acquisition has been progressing, and compensation for land loss and damaged crops/structures is still under the progress as well.




Figure 7.10.1 Construction Progress of MMIP II

Source: NIA-PMO, MMIP II

7.10.2 Land Acquisition

Components which need land acquisition are construction of main canal, lateral canals, drainages and access roads (intra-site road). Concerning the borrow area for the construction materials, the contractor will purchase the materials from the land owners through an agreement, therefore, land acquisition for the borrow area is not needed. Following tables show acquired area for each component. Construction works have been on-going in some parts of LMSA, and affected persons and damaged structures have been identified and compensated partly by NIA-PMO. However, the most southeastern part of LMSA had been initially planned to be covered by Japanese ODA loan (to be constructed after 2019), and no survey for identification of affected persons and structures has been implemented to date:

Concerning irrigation canals, areas to be acquired for **Case-1** and **Case-2** are 133 ha and 185 ha, respectively. As for drainages, there is no difference of length between both cases, and the acquired area will be 52 ha. Regarding access roads, N-2 will be excluded in **Case-1** due to flooding, therefore, acquired area will be 13 ha and 16 ha for **Case-1** and **Case-2**, respectively as shown in following tables:

Table 7.10.1 Land Acquisition Area in LMSA

Works	Area Required (ha)		Remarks
	Case-1	Case-2	
1. Irrigation Canals (LMSA)	133	185	Table 7.10.2
3. Drains (LMSA)	52	52	Table 7.10.3
4. Access Road (LMSA)	13	16	Table 7.10.4
Total	198	253	

Source: NIA-PMO, JICA Survey Team

Case-1: Construct some parts of the planned irrigation system and some parts of the drainage system within LMSA

Case-2: Construct the whole irrigation system and drainage system within LMSA

Source: JICA Survey Team

Table 7.10.2 Land Acquisition Area for Main and Lateral Canals in LMSA

No.	Canal Name	Case-1		Case-2	
		Length (m)	Area to be Acquired (ha)	Length (m)	Area to be Acquired (ha)
1	RMC-2	11,600	39.09	22,789	63.51
2	RMC-3	11,386	28.66	11,386	28.66

No.	Canal Name	Case-1		Case-2	
		Length (m)	Area to be Acquired (ha)	Length (m)	Area to be Acquired (ha)
3	LATERAL A	4,442	6.24	4,442	6.24
4	LATERAL B	1,369	1.61	1,369	1.61
5	LATERAL C	1,677	2.12	1,677	2.12
6	LATERAL D	4,640	9.62	6,341	11.85
7	LATERAL D-1	1,299	1.33	1,299	1.33
8	LATERAL D-2	2,250	1.17	2,250	1.17
9	LATERAL D-3	2,288	2.41	2,288	2.41
10	LATERAL E	0	0.00	1,948	2.14
11	LATERAL F	0	0.00	1,990	2.33
12	LATERAL G	0	0.00	2,653	2.71
13	LATERAL H	5,987	8.79	5,987	8.79
14	LATERAL H-1	3,037	3.68	3,037	3.68
15	LATERAL H-2	1,248	1.19	1,248	1.19
16	LATERAL H-3	3,007	3.23	3,007	3.23
17	LATERAL H-4	1,606	1.60	1,606	1.60
18	LATERAL I	1,648	1.70	1,648	1.70
19	LATERAL J	1,200	1.43	2,849	3.02
20	LATERAL K	1,300	1.67	2,302	2.78
21	LATERAL L	2,360	4.10	2,360	4.10
22	LATERAL L-1	1,000	1.18	2,114	2.36
23	LATERAL M	1,702	1.82	1,702	1.82
24	LATERAL N	2,500	3.81	3,510	4.78
25	LATERAL N-1	1,120	1.34	1,120	1.34
26	LATERAL N-2	1,000	1.19	1,921	1.90
27	LATERAL O	1,400	2.34	4,542	6.79
28	LATERAL O-1	0	0.00	2,320	2.83
29	LATERAL O1-1	0	0.00	1,077	1.16
30	LATERAL O-2	0	0.00	1,210	1.62
31	LATERAL O-3	0	0.00	1,794	2.29
32	LATERAL P	1,488	1.71	1,488	1.71
Total		72,554	133.03	107,274	184.77

Source: NIA-PMO

Table 7.10.3 Land Acquisition Area for Main and Lateral Drains in LMSA

No.	Drainage Name	Case-1		Case-2	
		Length (m)	Area to be Acquired (ha)	Length (m)	Area to be Acquired (ha)
1	LDC A1	547	0.21	547	0.21
2	LDC A2	1,079	0.48	1,079	0.48
3	LDC A3	1,275	0.46	1,275	0.46
4	LDC A4	882	0.49	882	0.49
5	LDC B1	2,746	1.53	2,746	1.53
6	LDC B2	1,941	0.97	1,941	0.97
7	LDC B3	651	0.26	651	0.26
8	LDC C1	1,082	0.47	1,082	0.47
9	LDC C2	874	0.36	874	0.36
10	LDC C3	1,161	0.61	1,161	0.61
11	LDC C4	689	0.28	689	0.28
12	LDC D1	1,760	0.79	1,760	0.79
13	LDC D2	1,220	0.46	1,220	0.46
14	LDC D3	940	0.32	940	0.32
15	LDC F	3,116	1.62	3,116	1.62
16	LDC H1	1,824	0.83	1,824	0.83
17	LDC H2	1,091	0.52	1,091	0.52
18	LDC H3	883	0.22	883	0.22
19	LDC H4	896	0.27	896	0.27
20	MDC-A	4,540	2.88	4,540	2.88
21	MDC-B	4,294	4.29	4,294	4.29
22	MDC-C	2,871	2.65	2,871	2.65
23	MDC-D	2,412	1.83	2,412	1.83

No.	Drainage Name	Case-1		Case-2	
		Length (m)	Area to be Acquired (ha)	Length (m)	Area to be Acquired (ha)
24	MDC-E	2,562	1.07	2,562	1.07
25	MDC-F	3,116	1.62	3,116	1.62
26	MDC-G	2,871	1.07	2,871	1.07
27	MDC-H	2,296	1.67	2,296	1.67
28	MDC-I	1,908	0.84	1,908	0.84
29	MDC-J	1,066	0.37	1,066	0.37
30	FAÇADE DRAIN	14,748	22.68	14,748	22.68
31	KALAWAG CREEK	8,460	0.00	8,460	0.00
Total		75,801	52.12	75,801	52.12

*MDC-K is also planned in LMSA, however, the length has not been fixed since it is still surveyed, and it is omitted.

**Area of Kalawag Creek is public land at this moment, and land acquisition is not necessary.

Source: NIA-PMO, JICA Survey Team

Table 7.10.4 Possible Land Acquisition Area for Access Roads in LMSA

No.	Road Name	Section of Access Road	Widening	Road Width	Case 1		Case 2	
					Length (m)	Land Acquisition (ha)	Length (m)	Land Acquisition (ha)
1	East to West Access Road	Access Road (E-1) (Existing Road) ₁₎	W=2.5 (m) x 2 (side)	W=2.5(m) x 2=5.0 (m) (widening both sides)	1,650	0.825	1,650	0.825
2		Access Road (N-1) (New Construction)	-	7.0 (m) +1.0 (m)x2 (both sides)=9.0 (m)	11,800	10.620	11,800	10.620
3	North to South Access Road-1	Access Road (N-2) (New Construction)	-	7.0 (m) +1.0 (m)x2 (both sides)=9.0 (m)	0	0	3,500	3.150
4	North to South Access Road-2	Access Road (N-3) (New Construction)	-	7.0 (m) +1.0 (m)x2 (both sides)=9.0 (m)	1,500	1.350	1,500	1.350
Total					14,950	127.950	18,450	159.450

Source: JICA Survey Team

The Project will be implemented by GOP, and preparation of a Resettlement Action Plan for the Project is not shouldered by the JICA Team. It means that the Survey does not cover identification of the PAPs, socio-economic survey of the PAPs, estimation of compensation cost, organization of public consultation meetings and so on. They are to be done by NIA-PMO in future.

Column: Progress of Compensation in LMSA by NIA

NIA-PMO prioritizes irrigation canal construction, parallel to the construction, identification of PAPs and compensation for damage to crops and structures by canal construction is on-going. However, the most southeastern part of LMSA has been initially planned to be covered by Japanese ODA loan. There is no construction or hauling of materials in this area, hence, as of to date there is no identification survey of PAPs done yet, more so compensation.

As for access road construction, the route for the access road is at the proposal stage as of July 2018, and it is still yet to be surveyed for alignment and design. Therefore, identification of PAPs, compensation rate setting, payment, explanation to the PAPs and so on for access road construction have yet to be done either to date.

Concerning drainage, affected structures/crops and PAPs identification are on-going, however, the final evaluation of which is still pending. According to the PMO however, it is their “practice” that PAPs are compensated on the affected crops and structures that will be damaged during the construction of the drainages; but no compensation for the acquisition of land itself.

1) Identification of Affected Persons

PAPs were identified by means of various information from LGU (Pikit) and Tax Declaration Office.

As of July 2018, 2,564 sites¹² and 110 residential structures are identified as affected. However, affected persons by construction of Lateral C, D, D-1, D-2, D-3, E, F and G have not been identified yet, since it had been planned to be covered initially by Japanese ODA loan (NIA-PMO planned the PAPs in this area would be identified under this JICA survey).

2) Socio-economic Survey

As of July 2018, a socio-economic survey targeting PAPs in MMIP II area has not been done, while it was implemented in MMIP I area. The PMO referred to the secondary data which were collected by other social surveys in MMIP II area.

3) Payment of Compensation

3.1) Compensation for damage to standing crops and structures

For irrigation canal construction in LMSA, 2,564 plots of damaged crops and 110 structures were identified as affected so far, and MMIP-PMO has already paid compensation for crop damage covering 1,261 plots and 54 structures, namely, around half of all affected crops/structures.

Identified crops to be compensated are mainly rice, corn, banana, nipa and so on, and the total area of damaged crops is 103 ha. The numbers of damaged major trees are 87,620, 13,638, 2,801 and 6,612 for banana, coconut, gemelina and nipa, respectively. On the other hand, damaged areas of rice and corn are 7.2 ha and 4.2 ha, respectively. Payment for the damaged crops and structures is still under progress as of July 2018, it is because that: 1) compensation rate is still under negotiation, and 2) official approval for payment is partly still under processing.

Regarding annual crop, NIA-PMO explained to PAPs that if possible not to plant crops, especially when there is Notice to Proceed issued to contractors. However, it is a usual scenario, especially during rainy season, when mobilization of contractors is delayed and in the same way, construction is delayed, farmers would take advantage of the availability of water and hence, planted rice and corn. And when the time comes when contractors mobilize, the crops are already maturing; hence, farmers would seek for compensation.

Some households have already shifted their residential structures. In general, they can re-construct their structures within their home compound area or its' nearby, and they do not have to resettle other unfamiliar places. They have been paid for damage to structures and they are waiting for compensation for land loss.



Location of the residence (within dot line) before demolition (left) and newly constructed house (right) of a project affected household along Main Canal 2. They are located on within the compound of the affected household.

Source: JICA Survey Team

¹² It is number of vouchers of compensation payment, not that of PAPs, which means that a person might be compensated for plural sites/structures.

3.2) Compensation for land loss

None of compensation for land loss has been finished as of July 2018. The reason for this situation is as follows:

- ✓ An evaluation survey of land value was implemented in 2003 to estimate compensation rates for irrigation facility construction, and it was revealed that actual land price varies from P11.32 - P12.5 per square meter, which is described in “ROW Committee Resolution No. 2003-01”. However, determined compensation rates for land loss for paddy field and other crop field were P10.5 and P7.5 per m², respectively, which were much less than actual ones. Still, the amounts are applied as the compensation rates even in 2018, which is not acceptable for the PAPs.
- ✓ Only one person in Upper Malitbog Area has agreed the rates and has been paid, which means that the construction works of canals in MMIP II have been started prior to the compensation payment for land loss. It is noted that at that time, installment of compensation is allowed in Philippines, and such a condition may not be a big issue on the ground level, thus the PAPs are waiting for compensation for land loss.

The situations mentioned in the column above are not against current laws/regulations in Philippines. Moreover, the most concern for the PAPs is compensation for damage to crops, rather than that for land loss, according to the Head of PMO. However, given that it is a principle of the JICA Guidelines to provide compensation for any losses due to projects prior to land acquisition and resettlement, such situations are to be improved. It is recommended for NIA-PMO to negotiate with the PAPs to settle down the matter.

7.11 Indigenous People Consideration

7.11.1 JICA’s Safeguard Policy on Indigenous Peoples

The Law No. 91 of 1993, THE BASIC ENVIRONMENT LAW of Japan stipulates that the Japanese Government shall take necessary measures to ensure proper environmental and social considerations not only within the country but also in implementing international cooperation in the areas outside Japan¹³. In line with the provision of the said law, the Japan International Cooperation Agency (JICA) has been applying its Guidelines for Environmental and Social Considerations to its technical and financial assistance projects.

According to the said JICA Guidelines, JICA tries to avoid any adverse impact of projects on Indigenous Peoples (IPs), among any other peoples, and when it is impossible to avoid it, the JICA will fully respect IPs’ rights in relation to land and resources. To this end, the consent on such a project by the IPs to be affected should be sought through “free, prior and informed consultations”, and an Indigenous People Plan (IPP) must be prepared with the contents listed up in table below.

Table 7.11.1 Outlines of Indigenous Peoples Plan (IPP)

CONTENTS	
1	A review of the <i>legal and institutional framework</i> applicable to IPs <ul style="list-style-type: none"> ▶ Legal instruments of the Philippines ▶ JICA Guidelines for Environmental and Social Considerations

¹³ Article 35 Considerations in Implementation of International Cooperation and Others of the Law No.91 of 1993. “The Basic Environment Law”

1. The State, in implementing international cooperation, shall make efforts to consider global environmental conservation etc. in the areas where the international cooperation is implemented.

2. The State shall make efforts to take necessary measures e.g. providing information to corporations, so that the corporations can properly consider global environmental conservation etc. in the areas outside Japan where these corporations conduct their business activities.

(Source: <http://www.env.go.jp/en/laws/policy/basic/index.html> [Accessed on 29th of June, 2018])

CONTENTS	
2	Baseline information on: <ul style="list-style-type: none"> ▶ the demographic, social, cultural and political characteristics of the affected IPs' communities; ▶ the land and territories that they have traditionally owned or customarily used or occupied; and ▶ the natural resources on which they depend.
3	Preparation for the consultations: <ul style="list-style-type: none"> ▶ Results of identification of <i>key project stakeholders</i> among the affected IPs' communities; ▶ Results of identification of <i>culturally appropriate process for consulting with the IPs</i> at each stage of project preparation and implementation
4	Results of the free, prior and informed consultation with the IPs to be affected on the potential adverse and positive effects of the project during the project preparation, including: <ul style="list-style-type: none"> ▶ Results of an analysis of the relative vulnerability of the IPs' communities to be affected; ▶ Results of identification and evaluation of necessary measures to avoid, minimize, mitigate adverse effect and to compensate for such effect; and ▶ Results of identification and evaluation of necessary measures for IPs to receive culturally appropriate benefits under the project.
5	A framework for ensuring free, prior and informed consultation with the affected IP's communities during the project implementation
6	An Action Plan of measures to ensure that the IPs receive social and economic benefits, including the capacity development of the implementing agencies, if necessary
7	An Action Plan of measures to avoid, minimize, mitigate or compensate for those identified adverse effects
8	Cost estimates and Financing plan for the implementation of IPP
9	Grievance procedures to address grievances by the affected IPs' communities arising from project implementation
10	Mechanisms for monitoring, evaluation and reporting on the implementation of IPP

Sources: JICA. 2010. JICA Guidelines for Environmental and Social Considerations.

World Bank. 2005. Operational Policy / Bank Procedures on Indigenous Peoples (OP/BP 4.10)

7.11.2 Scope of the Survey on Indigenous Peoples

The following are the assignments given to the Survey Team to clarify on IPs:

- (a) To confirm the existing legal instruments and government structure regarding the protection or promotion of IPs' rights;
- (b) To confirm the presence of IPs in the target project site for possible Japanese ODA Loan¹⁴ assistance;
- (c) To collect basic information on the IPs concerning the originally requested project site for Japanese ODA Loan, such as: population; social, cultural and political features; and land and resources, which are traditionally utilized by the IPs whose presence in the target project site is confirmed;
- (d) To identify appropriate means for the consultation with the concerned IPs for the objectives of stakeholder analysis and of the preparation, implementation and monitoring of the project to be implemented; and
- (e) To identify possible positive and negative impacts on the concerned IPs by the implementation of the project, by clarifying the number of IPs to be affected, features of impact, means of livelihoods of the IPs to be affected, their land or resource use, and their means of communication with outside of the community.

The Survey Team was engaged in above assignments, and since it was turned out that is no presence of IPs to be adversely affected by the implementation of the project, as a result of the assignment (b), there was no need to undertake the remaining assignments (c), (d) and (e). The following is the summary of results of the assignments (a) and (b).

Note that the ODA request was officially withdrawn by the Philippines government officials during an economic cooperation joint meeting held on June 21, 2018, and results of this IP survey would service

¹⁴ According to the Special Assistance for Project Formation (SAPROF) for MMIP II, it was believed that one Indigenous tribe, the Aromanen-Manobo tribe, was present in Pikit and Carmen Municipalities of Cotabato Province.

Philippines internal procedural approval on IPs issues.

7.11.3 Related Legal Instruments and Government Structure of the Philippines

1) Related Legal Instruments

Both the 1987 Constitution of the Republic of the Philippines and the Republic Act No. 8371, Indigenous People's Rights Act (IPRA) of 1997 respect Indigenous People's rights, and the latter also gives the legal backing to the establishment of the National Commission on Indigenous Peoples (NCIP), as government authority to protect and promote IP's rights. NCIP, in the sought of its mandates, has issued several guidelines to define related concepts and terms, as well as to establish the procedure of request, complaints, investigation and consultation. Relevant legal instruments of the Republic of the Philippines on IP's rights are listed in the following table:

Table 7.11.2 Legal Instruments on Indigenous People's Rights of the Philippines

Classification	Year	No.	Official Title	Remark
Constitution	1987	N/A	The Constitution of the Republic of the Philippines	The Constitution recognizes the rights of IPs to their Ancestral Domains(ADs), their lands and resources. Moreover, it respects their basic rights and their beliefs, customs and traditions tied to the land.
Republic Act	1997	8371	An Act to recognize, protect and promote the rights of Indigenous Cultural Communities/ Indigenous Peoples, creating the National Commission on Indigenous Peoples, establishing implementing mechanisms, appropriating funds therefore, and for other purposes	This Act is known as "The Indigenous Peoples' Rights Act of 1997" (IPRA) and recognizes the Indigenous Peoples' rights to ADs and self-governance. In addition, this Act justifies the establishment of the National Commission on Indigenous Peoples (NCIP) to protect the IP's rights.
NCIP Administrative Order	1998	No.1	Rules and regulations implementing Republic Act No. 8371, otherwise known as "The Indigenous Peoples' Rights Act Of 1997"	Rules and Guidelines to crystalize how to implement the 1997 IPRA on the ground
	2012	No.1	The Indigenous Knowledge Systems and Practices (IKSPs) and Customary Laws (CLs) Research and Documentation Guidelines	
	2012	No.2	The General Guidelines on the Confirmation of Indigenous Political Structures and the Registration of Indigenous Peoples' Organizations	
	2012	No.3	The Revised Guidelines on Free and Prior Informed Consent (FPIC) and related processes	
	2012	No.4	Revised Omnibus Rules on Delineation and Recognition of ADs and Ancestral Lands	

Source: Republic Act No. 8371

This JICA Survey adopts the following definition of IPs, which is provided by the Republic Act No. 8371 of 1997, IPRA, and it reads:

"a group of people or homogenous societies identified by self-ascription and ascription by others, who have continuously lived as organized community on communally bounded and defined territory, and who have, under claims of ownership since time immemorial, occupied, possessed and utilized such territories, sharing common bonds of language, customs, traditions and other distinctive cultural traits, or who have, through resistance to political, social and cultural inroads of colonization, non-indigenous religions and cultures, became historically differentiated from the majority of Filipinos. ICCs/IPs shall likewise include peoples who are regarded as indigenous on account of their descent from the populations which inhabited the country, at the time of conquest or colonization, or at the time of inroads of nonindigenous religions and cultures, or the establishment of present state boundaries, who retain some or all of their own social, economic, cultural and political institutions, but who may have been displaced from their traditional domains or who may have resettled outside their ancestral domains".

In addition to the above definition of IPs, the definitions of other important and relevant terms, such as “Ancestral Domains (ADs)”, “Ancestral Lands”, “Certificate of Non-Overlap”, “Certification Precondition”, “Field-Based Investigation”, “Free and Prior Informed Consent”, “Indigenous Cultural Community / Indigenous Peoples”, “Indigenous elder / leader”, and “Time Immemorial” are also found in the same Republic Act No. 8371 of 1997, IPRA or in the NCIP Administrative Order No. 3, Series of 2012. The Preparatory Survey has adopted the definitions of these terms in the survey to meet the scope mentioned above.

2) Government Structure: National Commission on Indigenous Peoples (NCIP)

NCIP was established upon the enactment of the Republic Act of No. 8371 of 1997, IPRA, with the mission to “formulate and implement policies, plans and programs for the recognition, promotion and protection of the rights and well-being of IPs with due regard to their ADs and lands, self-governance and empowerment, social justice and human rights, and cultural integrity”.

In particular, NCIP ensures the land rights of IPs by issuing the Certificate of Ancestral Domain Title/ Certificate of Ancestral Land Title (CADT/CALT), after conducting assessments by themselves upon the submission of applications by IPs. NCIP also recognizes indigenous political structures, based on the actually functional systems on the ground, which are commonly accepted justice systems, conflict resolution mechanisms, peace-building processes, and customary laws. NCIP also supports IPs to establish and control their educational systems and to protect indigenous knowledge systems and practices.

The target area for the Japanese ODA Loan originally requested belongs to the Lower Malitubog Service Area (LMSA), and the entire LMSA is located in the jurisdiction of the NCIP Regional Office of Region XII.

7.11.4 Screening of the Presence of IPs and ADs to be affected

1) Overview of IPs

Since there is no reliable data of the population of IPs in the Philippines, accurate figures of their populations at any level in the Country are unknown. However, according to results of a survey conducted by NCIP, the population of IPs at the national level could be estimated at between 12 and 15 million, constituting almost 10 to 15% of the total population of the Country. The IPs are classified into 110 ethno-linguistic groups, spreading over 65 out of the 78 provinces in the Country, with a concentration in Mindanao (61%) and Northern Luzon (Cordillera Administrative Region, 33%) .

As afore-mentioned, the IPs are concentrated in Mindanao sharing as much as 61%. In Mindanao, it has been confirmed the presence of Muslim IPs and other IPs who are neither Muslim nor Christian (called Lumad), in addition to settlers who are mainly Christians and originally from outside Mindanao Island.

2) Recognition on the Presence of IPs by Key Stakeholders

Key local stakeholders for the implementation of MMIP II asserted that there is no presence of IPs in the area for which Japanese ODA Loan was originally requested. Upon consulted in different occasions, the Coordinator of the Moro Islamic Liberation Front (MILF) for the Task Force formed for the Preparatory Survey on MMIP II, the officials of the PMO of MMIP of the National Irrigation Authority (NIA-PMO) and the Pikit Municipal Officers, respectively, stated that there is no presence of IPs in the target area for the requested Japanese ODA Loan. Having such statements by the key local stakeholders, the Survey Team contacted NCIP to confirm non-presence of IPs to be affected by the implementation of MMIP II in the concerned area.

3) Free and Prior Informed Consent Process for IPs, including the Field-Based Investigation Process

The contents of the NCIP Administrative Order No. 3, Series of 2012 are the “Revised Guidelines on Free and Prior Informed Consent (FPIC) and related processes”. This illustrates details of the FPIC process stipulated by the Republic Act No. 8371 of 1997, IPRA. The entire FPIC process is practically consisting of two parts: before and after the Field-Based Investigation (FBI) Process, as shown in Figure 7.11.1.

The application to start the FPIC process should be submitted by the appropriate regulatory agency or unit of government or by the proponent, who are owners of plan, project, program or activity to the NCIP Regional Office that has jurisdiction over the area where the concerned plan, project, program or activity are to be undertaken. Upon the receipt of such an application, the NCIP Regional Director assigns the FBI team by issuing a memorandum to start the process.




Figure 7.11.1 FBI Process & Preparation of IPP

Source: NCIP. 2012. Administrative Order No. 3

The purpose of the FBI is to determine: 1) whether or not the plan, program, project or activity overlaps with, or affects an ancestral domain; 2) the extent of the affected area; and 3) the Indigenous Cultural Communities (ICCs)/ IPs whose FPIC is to be obtained. To this end, the FBI team is tasked to fulfil the following duties;

- 1) Consult with the Ancestral Domain (AD) representatives, if applicable;
- 2) Conduct the pre-FBI Conference and along with the proponent, prepare the Work and Financial Plan (WFP) for FBI;
- 3) Undertake FBI to determine the particular area that will be affected, including the projection of the indorsed technical description/geographic coordinates in the AD, the probable effects of the plan, program, project or activity, and the number of ICCs/IPs that will be affected,
- 4) Identify the elders/leaders and determine presence of disputes/conflict with adjacent ancestral domain/s;
- 5) Prepare, under oath, and submit a report with recommendations to the Regional Director;
- 6) Liquidate all funds handled in accordance with standard accounting and auditing rules and regulations; and
- 7) Perform such other functions as may be directed by higher authorities.

The FBI team shall develop WFP of the FBI process, and once an agreement on WFP is made among the key stakeholders through the pre-FBI Conference, the FBI team can actually start to undertake their literature review and investigation on the ground. The FBI team should submit the FBI report to the NCIP Regional Director at the end of the FBI process, so that the Regional Director takes necessary actions in accordance with the conclusion of the FBI report.

If the FBI report concludes that there is no presence of ADs and IPs to be affected by the implementation of the concerned plan, program, project or activity, the Regional Director of the NCIP can issue the Certificate of Non-Overlap (CNO) and there will be no need to develop IPP. To the contrary, if the FBI report concludes that there are ADs or IPs to be affected, the NCIP Regional Director assigned the FPIC team to go through the FPIC process with the concerned IPs. Eventually, IPP shall be prepared and implemented to ensure that the IPs to be affected will receive social and economic benefits, while those adverse effects on the same IPs will be avoided, minimized, mitigated or compensated.

7.11.5 Results of the Field Based Investigation


Upon contacted by the Survey Team at the end of May 2017, NCIP decided to take the Field-Based Investigation (FBI) process for the target area initially requested for Japanese ODA Loan within LMSA through its Regional Office in Region XII. After going through the FBI process, on July 5 of 2017, the FBI report was submitted to the NCIP Regional Director of the Region XII by the leader of the FBI team, with the conclusion that there is no AD and IP in the target area to be affected by the implementation of the project. The actual FBI process took place as follows:

On May 29, 2017, the Director of the NCIP Region XII appointed the three officials at the regional level to form the ad-hoc FBI team. The FBI team and the Survey Team agreed to overlay the map of the target project site with the maps of two different ADs which are located nearby of the target project site. The results of the overlaying the map is shown in Figure 7.11.2. It clarifies that the target project site remains away from the two ADs, and there is no overlap between the target project site and the two ADs.

Concurrently, the FBI team convened the pre-FBI Conference on June 29, 2017 by inviting two indigenous leaders from the ADs mentioned above. Representatives from NIA-PMO and the JICA Team have also attended the same conference in order to inform the conference of the objectives and contents of MMIP II. As a result of the pre-FBI Conference, WFP for FBI was agreed by all the participants.

Subsequently, the FBI team conducted FBI in accordance with WFP, with financial and logistical support from the JICA Survey Team, and the FBI team prepared the FBI report based on the findings from FBI, and submitted it to the NCIP Regional Office XII for the approval on July 5, 2017. The said FBI report concluded as follows:

- 1) The Proposed project sites under MMIP II traversing Barangays Baguinged, Barungis, Buliok, Bulol, Kabasalan, Rajah Muda and Talitay all in the Municipality of Pikit, Cotabato are outside Ancestral Domain of Indigenous Cultural Communities/ Indigenous Peoples as per projection with the CADT maps and actual site inspection together with CADGT representatives;
- 2) There are no Indigenous Cultural Communities/ Indigenous Peoples present in the afore-said areas that will be affected during the implementation of the said Project;
- 3) The said Barangays are patently Bangsamoro territory;
- 4) The said Barangays are very suitable for rice production and it is highly recommended that an irrigation system will be implemented in the area; and
- 5) The Barangay Official/ Representatives expressed full support and cooperation on the role of concerned Barangay Officials and members of the community in the realization of the Malitubog-Maridagao Irrigation Project –II (MMIP II) that will surely address the food security in the area and in the Region as whole.



Note: KIMA 1 is the base point to locate the AD of CADT: 7° 12' 50.90295"N, 124° 34' 42.67226"E, Northing 797771.6801, Easting 453282.1548, Location Kimango.

Figure 7.11.2 Non-overlap among the Ancestral Domain, LAMP, CADT No. R12-CAR-0703-0009 and the Entire MMIP Site

Source: NCIP Region XII and NIA-PMO

Since it was confirmed that there is no presence of ADs and IPs to be affected by the implementation of the project in the target project site initially requested for Japanese ODA Loan, through the FBI process, there is no need to prepare IPP and to go through the FPIC process within the framework of this Preparatory Survey.

7.12 Recommendation

As discussed so far, some environmental impacts will be caused by the Project. However, the extent of impacts is not very significant, since the proposed components will not cause dynamic change of hydrological conditions. Still, it is noted that some bird species are threatened by hunting, and it is requested to control such illegal activity regardless of the Project. On the other hand, land acquisition and damage to standing crops/structures are caused for construction works and compensation is on-going. However, the PAPs have not accepted the proposed compensation rates for land loss due to its low amount. As a result, the construction works were started and are on-going without payment of compensation for land loss. It is recommended to negotiate with the PAPs to fix the compensation rates and to finalize the payment.

NIA-PMO has already organized a series of stakeholder meetings to explain the Project for the local residents so far. However, they did not prepare minutes of meetings including participant's lists in writing¹⁵. It is very important to keep records of such discussions in case any troubles are observed, and it is recommended to make minutes with participant lists when NIA-PMO organizes stakeholder meetings.

¹⁵ Participants list for Feb 5 2018 has been prepared.

CHAPTER 8 GLOBAL ISSUES

This chapter discusses the proposed components in relation to such global issues as poverty reduction, climate change, and gender. It means that this chapter explores the possibility of: 1) reduction of poverty for the beneficiaries covering both direct beneficiaries and indirect-beneficiaries, 2) mitigating or coping with negative impacts of climate change, and 3) relevance to gender significance:

8.1 Poverty Reduction

Following table shows the poverty ratios of 5 years from 1991 to 2015 and Figure 8.1.1 shows the poverty ratios in 2015 by region. For the Region XII and ARMM, the poverty ratios of Cotabato province and Maguindanao province are also indicated where the MMIP site falls in. In fact, the poverty ratios of Region XII and that of ARMM are very high, especially the ratio of ARMM/ Maguindanao is the highest in the Philippines; almost 3 times higher than that of whole nation, about 48% vs. 16.5% in 2015. Region XII is also ranked at the 2nd lowest group with Regions VIII, X and Caraga.




Figure 8.1.1 Poverty Ratio by Region (2015)

Source: National Statics Authority

Table 8.1.1 Poverty Ration by Region in Philippines (1991 – 2015)

Region/Province	Poverty Incidence among Families (%)				
	1991	2006	2009	2012	2015
Philippines	29.7	21.0	20.5	19.7	16.5
NCR	5.3	2.9	2.4	2.6	2.7
CAR	36.7	21.1	19.2	17.5	14.9
Region I	30.6	19.9	16.8	14.0	9.6
Region II	37.3	21.7	20.2	17.0	11.7
Region III	18.1	10.3	10.7	10.1	8.9
Region IV-A	19.1	7.8	8.8	8.3	6.7
Region IV-B	36.6	32.4	27.2	23.6	17.4
Region V	48.0	35.4	35.3	32.3	27.5
Region VI	32.3	22.7	23.6	22.8	16.6
Region VII	38.2	30.7	26.0	25.7	23.6
Region VIII	42.3	33.7	34.5	37.4	30.7
Region IX	36.4	40.0	39.5	33.7	26.0
Region X	42.6	32.1	33.3	32.8	30.3
Region XI	34.1	25.4	25.5	25.0	16.6
Caraga	48.5	41.7	46.0	31.9	30.8
Region XII	47.4	31.2	30.8	37.1	30.5
Cotabato	NA	25.6	23.4	44.8	34.5
ARMM	26.9	40.5	39.9	48.7	48.2
Maguindanao	NA	46.4	43.3	54.5	48.8

Source: Philippine Statistics Authority, 2016

Worse, the poverty ratios of Region XII and ARMM, including North Cotabato and Maguindanao, have not significantly reduced, or rather once increased in the year 2012. This trend is very much contrary to most of the other parts of Philippines. Though the overall poverty ration of Philippines has reduced from 29.7% in 1991 to 16.5% in 2015, by as much as 13.2 % over the 24 years, the ratios for Region XII and ARMM, including Cotabato and Maguindanao, have not reduced at all.

For example, ARMM started with relatively lower poverty ratio, 26.9% in 1991, and it has almost continuously increased reaching almost 50% nowadays. Maguindanao has followed almost the same

trend of ARMM with somewhat higher poverty incidences. Region XII started, on contrary, with higher poverty ratio with 47.4% in 1991, and reduced towards the year 2006, after which however the reduction of the poverty ratio had stopped. The poverty ratio has been more than 30% for the Region XII.

There are components which can raise the income of the beneficiaries through the increase of production of agricultural produces; namely, 1) irrigation and drainage development, and 2) agriculture and extension development. For these components, increase of the farm budgets is estimated as follows by comparing the before-after projects, showing approximately an increase of 70 - 89% in the farm budget (Table 8.1.2.); thus, the Project will contribute to mitigating the poverty of the beneficiaries:




Figure 8.1.2 Trend of Poverty Ratio by Region (1991-2015)

Source: National Statics Authority

Table 8.1.2 Estimated Farm Budget comparing the Before-After Projects

SN	Case	Estimated No. of Farm Household without Project; MMIP II Area overall (FHHs)	Estimated No. of Farm Household with Project; MMIP II Area overall (FHHs)	household Income without Project (Php/FHH)	household Income with project (Php/FHH)	Ratio b/t with & without Project, (%)
Case-1 (irrigation canals to be constructed within areas where inundation is not more than 50cm)						
1	C1-M2-D00	1,601	6,107	90,967	172,347	1.89
2	C1-M2-D30	1,601	6,107	90,967	167,995	1.85
3	C1-M2-D50	1,601	6,107	90,967	165,384	1.82
4	C1-M2-D80	1,601	6,107	90,967	161,322	1.77
Case-2(irrigation canals to be constructed as per the original plan covering whole LMSA)						
5	C2-M2-D00	1,601	8,429	90,967	166,858	1.83
6	C2-M2-D30	1,601	8,429	90,967	162,080	1.78
7	C2-M2-D50	1,601	8,429	90,967	159,212	1.75
8	C2-M2-D80	1,601	8,429	90,967	154,752	1.70

Source: The Survey Team, the detailed calculation is shown in Chapter V

8.2 Climate Change

8.2.1 Climate Change Review and Future Simulation

Philippine Atmospheric, Geophysical and Astronomical Services Administration (PAGASA) had conducted a climate change simulation by using PRECIS model¹ and shared the results in February 2011². The simulation, as the first step, reviewed about past 60 years climate change according to the actual records observed from 1951 to 2009 with the average for the period of 1971 – 2000 as the reference value. The key findings from the actual records are summarized as follows:

- 1) There has been an increase in annual mean temperature by 0.57 °C, meaning about 0.1 °C

¹ PRECIS stands for 'Providing Regional Climates for Impact Studies' model, which was developed by the UK Met Hadley Centre in the United Kingdom to facilitate impact, vulnerability and adaptation assessments in developing countries where capacities to do climate modeling are still not fully developed or do not exist.

² In 2009, the Government of the Philippines initiated the implementation of the Millennium Development Goals Fund (MDGF) Joint Programme entitled "Strengthening the Philippines' Institutional Capacity to Adapt to Climate Change". It was a three-year program funded by the Government of Spain through the United Nations Development Program (UNDP) Philippines and the various UN agencies (UNEP, FAO, WHO, UN Habitat, and others). Under this program, the climate change simulation was conducted.

increase per decade (see Figure 8.2.1);

2) In terms of maximum and minimum temperatures, the increases have been 0.35 °C and 0.94 °C;

3) Results of analysis of trends of tropical cyclone occurrence/ passage within the so-called Philippine Area of Responsibility (PAR) show that an annual average of 20 tropical cyclones cross the PAR per year with strong multi-decadal variability, that there still is no indication of increase in the frequency as shown in Figure 8.2.2. It is noted that in general frequency of tropical cyclones in Mindanao are few as compared to other parts of the Philippines, and further there may be a slight trend of the occurrence of cyclones being fewer.

4) The analysis of trends of extreme daily temperatures and extreme daily rainfall indicate significant increase in number of hot days but decrease of cool nights, and those of rainfall in terms of extreme rainfall intensity and frequency are not clear, both in magnitude (by what amounts) and direction (whether increasing or decreasing), with very little spatial coherence.




Figure 8.2.1 Trend of Annual Mean Temperature with Anomalies in the Philippines Based on 1971-2000 Normal Values

Source: PAGASA-DOST, Feb. 2011




Figure 8.2.2 Decadal Changes in Intense Tropical Cyclone Occurrence in the Three Main Islands in the Philippines (1951-2000)

Source: PAGASA-DOST, Feb. 2011

Following the examination of past actual records as above-summarized, PRECIS model simulated future climates in 2020 and 2050 under the mid-range climate change scenario³. The simulation results were presented in detail for the sole reason that future climates in the next 30 to 40 years will be greatly influenced by the past greenhouse gas emissions already there (i.e., lifetimes of carbon dioxide are estimated at a hundred years or more). The key findings for the simulation are:

- 1) All areas of the Philippines will get warmer, more so in the relatively warmer summer months;
- 2) Annual mean temperatures (average of maximum and minimum temperatures) in all areas in the Country are expected to rise by 0.9 °C to 1.1 °C in 2020 and by 1.8 °C to 2.2 °C in 2050;
- 3) Likewise, all seasonal mean temperatures will also have increases in the two-time slices of dry

³ In fact, three of the emission scenarios developed by the Intergovernmental Panel on Climate Change in its Special Report on Emission Scenarios (IPCC SRES) were chosen to run the PRECIS model; namely, A2 (high-range), A1B (mid-range), and B2 (low-range). However, in the PAGASA report, the mid range simulation results (A1B) were only highlighted because the future climates in the next 30-40 years will be greatly influenced by the past emissions, principally due to the long lifetimes of carbon, hence this chapter also refers to only the A1B scenario simulation results.

and wet seasons, and these increases during the four seasons, e.g., DJF⁴, MAM, JJA and SON, are quite consistent in all the provinces;


- 4) In terms of seasonal rainfall change, generally, there is a substantial spatial difference in the projected changes in rainfall in 2020 and 2050 in most parts of the Philippines, with reduction in rainfall in most provinces during the summer season (MAM) making the usually dry season drier, while rainfall increases are likely in most areas of Luzon and Visayas during the southwest monsoon (JJA) and the SON seasons, making these seasons still wetter, and thus with likelihood of both droughts and floods in areas where these are projected;
- 5) The northeast monsoon (DJF) season rainfall is projected to increase, particularly for areas characterized by Type II climate (shown along eastern seashores of the Philippines, see box right) with potential for flooding enhanced;
- 6) During the southwest monsoon season (JJA), larger increases in rainfall is expected in provinces in Luzon (0.9% to 63%) and Visayas (2% to 22%) but generally decreasing trends in most of the provinces in Mindanao in 2050;
- 7) However, projections for extreme events in 2020 and 2050 show that hot temperatures (indicated by the number of days with maximum temperature exceeding 35 °C) will continue to become more frequent, number of dry days (days with less than 2.5 mm of rain) will increase in all parts of the Country and heavy daily rainfall (exceeding 300 mm) events will also continue to increase in number in Luzon and Visayas.

Summarizing the above climate change in future over the Philippine islands, Figure 8.2.3 shows the projected seasonal (3-month) temperature increase in 2020 and in 2015. Mindanao island, where the MMIP II project is located, indicates bigger temperature increase as compared to other parts of the Philippines. In addition, the increase shows up bigger during the periods of March-April-May and June-July-August.

Concerning the 3-month seasonal rainfall shown in Figure 8.2.4, Mindanao island area clearly shows that at the year 2020 the seasonal rainfall increases in December – February, very much decreases from March to May, decreases from June to August and a little decreases from September to November. At the year 2050, the trend is more or less same as those of year 2020 though it is more intensified in the trend of increase or decrease.

Classification of climate in the Philippines:

The classification in the Philippines uses the Corona's four climate types (Types I to IV), based on monthly rainfall received during the year. A province is considered to have Type I climate if there is a distinct dry and a wet season; wet from June to November and dry, the rest of the year. Type II climate is when there is no dry period at all throughout the year, with a pronounced wet season from November to February. On the other hand, Type III climate is when there is a short dry season, usually from February to April, and Type IV climate is when the rainfall is almost evenly distributed during the whole year. The western part of Mindanao falls in Type III while mid to eastern parts of Mindanao dose in Type VI climate zone. The MMIP area falls somewhat in between the Type III and Type IV.



⁴ DJF means December, January, and February, and MAM, JJA and SON are as well, namely 3-month period is grouped in one season.




Figure 8.2.3 Projected Seasonal Temperature Increase

Source: PAGASA-DOST, Feb. 2011




Figure 8.2.4 Projected Seasonal Rainfall Increase, %

Source: PAGASA-DOST, Feb. 2011

PAGASA's report further elaborates the climate change in terms of temperature and rainfall by region and by major province. Since MMIP II area falls mostly in Cotabato province and partly Maguindanao province, ARMM, following tables excerpt seasonal (3-month) temperature increase and rainfall change for the Cotabato and Maguindanao area; Table 8.2.1 for temperature change and Table 8.2.2 for rainfall change. From those tables, following area deduced;

From the average temperature of 1971 – 2000, the temperature increases by about 1 °C or a little more than that for the both Cotabato and Maguindanao at the year 2020, and further by about 2 °C or more than that at the year 2050. With respect to rainfall, it is to increase from September to February at the year 2020 while the rainfall from March to August is to decrease for both Cotabato and Maguindanao area. At the year 2050, the rainfall from September to November now changes to decrease, and further the rainfall for December to February of Maguindanao also decreases.

Table 8.2.1 Seasonal Temperature Increases in 2020 and 2050 under Medium-range Emission Scenario

Province	Particulars	DJF	MAM	JJA	SON
Cotabato	1971-2000, observed, °C	26.8	27.9	27.0	27.1
	Change in 2020, °C	1.0	1.3	1.2	1.1
	Change in 2050, °C	2.1	2.5	2.4	2.1
Maguindanao	1971-2000, °C	27.6	28.3	27.5	27.6
	Change in 2020, °C	1.0	1.2	1.2	1.1
	Change in 2050, °C	2.1	2.3	2.4	2.1

Source: Climate Change in the Philippines, Feb. 2011, PAGASA

Table 8.2.2 Seasonal Rainfall Change in 2020 and 2050 under Medium-range Emission Scenario

Province	Particulars	DJF	MAM	JJA	SON
Cotabato	1971-2000, observed, mm	235.4	353.2	572.5	486.0
	Change in 2020, %	14.8	-5.9	-6.1	1.6
	Change in 2050, %	8.1	-4.5	-8.7	-4.2
Maguindanao	1971-2000, mm	293.8	369.4	661.5	562.2
	Change in 2020, %	7.2	-6.3	-7.2	0.3
	Change in 2050, %	-1.1	-4.6	-7.4	-3.6

Source: Climate Change in the Philippines, Feb. 2011, PAGASA

Further, Table 8.2.3 summarizes the frequency of extreme events for the past (1971 to 2000) and same

30 years with the mid year of 2020 and 2050. Note that the simulation result at Cotabato is not available, and therefore superseded by General Santos located in South Cotabato. The table shows clearly that there will be many hotter days, more than 35 °C, in future. Dry days where there is no rainfall would also increase in general. Torrential rainfall days do the same especially in Maguindanao area.

Table 8.2.3 Frequency of Extreme Events in 2020 and 2050 under Medium-range Emission Scenario

Province	Particulars	No. of days w/ Tmax > 35	No. of Dry Day	No. of Days w/ Rainfall > 150m
South Cotabato (General Santos)	1971-2000, observed	1,397	8,704	1
	2020, Projected	3,748	7,526	1
	2050, Projected	6,430	8,052	2
Maguindanao (Cotabato)	1971-2000, observed	383	3,516	2
	2020, Projected	3,382	5,471	10
	2050, Projected	5,994	5,788	5

Note: the number of counts is made for a period of 30 years covering both earlier and later years from 2020, and 2050.

Source: Climate Change in the Philippines, Feb. 2011, PAGASA

8.2.2 Project Intervention in the Climate Change

Major issues relating to climate change are probably: 1) temperature increase and 2) less amount of dry season (September to February) rainfall at the long run of year towards 2050 though the seasonal rainfall amount in the coming near 2020 is to increase, based on the past review of the climate change as well as the simulation result covering up to 2050.

A rise of 1 – 2 °C combined with lower solar radiation has a potential to cause rice spikelet sterility (i.e. infertile rice seeds). In general, rice becomes sterile if the paddy is exposed to temperature above 35 °C for more than one hour during flowering and consequently produces no grain⁵. Furthermore, higher temperatures would increase the incidence of crop diseases, insect pests and rodents. To avoid this sterility associated with high temperature, there should be a new variety, which can stand against the high temperature or otherwise the flowing and pollination should be made during not-day time but during early morning time. This kind of research is not included in the components proposed under this Project. This kind of research could better be undertaken by an international institute, e.g. IRRI.

On the other hand, the major component of MMIP II, the irrigation and drainage development, can cope with or at least mitigate the impact of climate change concerning anomalies of the rainfall pattern. The change of the monsoon season could be very much associated with intensive rainfall pattern, meaning the rain tends to fall at once with severer intensity, often resulting in torrential rain and flood, as has been already observed. The component of irrigation and drainage construction would work in mitigating this climate change, rainfall and monsoon season pattern change.

As per its nature, irrigation system to be developed would be able to supply on-time water at the onset of monsoon season which is predicted becoming unstable. The irrigation systems developed are expected to provide supplemental water to the unstable rainfall during monsoon season, and accordingly the developed system would contribute to mitigating and coping with the negative impact of climate change, especially the unstable rainfall pattern.

Irrigation water during monsoon season is supplemental to the rainfall, while the irrigation during the dry season is the essential one. The headworks to withdraw irrigation water are constructed on the Maridagao river, and there is no storage reservoir in the upstream. It means that the water availability

⁵ Referred to in the UNEP report 'Myanmar's National Adaptation Programme of Action (NAPA) to Climate Change (2012), Karim, Z., 1996. Agricultural Vulnerability and Poverty Alleviation in Bangladesh. In Climate Change and World Food Security, T.E. Downing (Ed.), NATO ASI Series, 137. Springer-Verlag, Berlin, Hiedelberg, 1996. pp. 307-346.

at the intake point is fully dependent on the rain falling in the catchment area. As obviously practiced, the water in the river for irrigation purpose is more than enough during the rainy season while that during dry season may become critical if the replenishing rainfall during the dry season becomes very marginal.

With the afore-mentioned Table 8.2.2, rainfall during monsoon season will decrease by 5 – 9 % which could work, in general, in reducing flooding/ inundation. On the other hand, dry season's rainfall in year 2020 is not so changed from the observed records from 1971 to 2000, or rather it is increased, and the rainfall is to decrease in the long run, say in the year 2050. This trend may imply that the dry season's river water may be reduced in the long-run, so that water management with water saving irrigation technology may have to be introduced.

Concerning the dry season's rainfall decrease, there is still an opportunity for keeping dry season irrigation as it has been. Cotabato rainfall from December to February still shows 8.1 % increase even in year 2050 (see Table 8.2.2). As is well known, paddy cultivation needs the maximum amount of irrigation water during the land preparation period, which means if the dry season paddy cultivation could start as early as the time right after the harvest of monsoon season paddy, there could be still enough amount of water in the river, or even more amount of water than the present condition due to the increased rainfall from December to February in future.

8.3 Gender

8.3.1 Current Gender Conditions in the Philippines

1) In the Philippines

According to JICA⁶, the Philippines is one of those six countries in the world, which have been able to significantly narrow gender gaps in education and health indicators. The values of economic indicators for women continue improving and women are achieving income equality for similar works. Based on what was mentioned above, the Philippines is the only country in the world where both women and men equally play in senior management roles in the society. Women have marked their salient achievements in different areas, including academic, professional, political and legislative areas.

However, at the same time, there are women suffering from sex and gender based abuses, such as domestic violence, economic disadvantages, discrimination at the workplace, exploitation as migrant workers, and adverse impact brought about by the intermittent wars in conflict affected areas. As in most countries affected by armed conflict, women and children make up the great majority of the displaced population in the Philippines. The intermittent wars affect women's livelihood, health, education and family life, among other things.

The Philippine Commission on Women (PCW) is the National Machinery⁷ on women and gender equality concerns. The PCW was formerly known as the National Commission on the Role of Filipino Women (NCRFW) until August 14, 2009. This was the date that NCRFW was renamed as PCW and its mandate was expanded by the enactment of Republic Act 9710, Magna Carta of Women (MCW).

Women's concerns were positioned at the heart of the government agenda with the integration of the gender equality principle in the 1987 Philippine Constitution. It was during this period, that the first Philippine Development Plan for Women (PDPW), 1989-1992 was adopted, and enacted shortly was the "Women in Nation-Building Act" (RA 7192), which promotes the integration of women as full and equal partners of men in development and nation-building.

⁶ JICA. 2008. Gender Profile of the Philippines.

⁷ http://www.gender.go.jp/english_contents/about_danjo/lbp/basic/toshin-e/org-e.html
<http://www.un.org/womenwatch/daw/news/natlmach.htm>

The Philippine Plan for Gender-Responsive Development (PPGD) 1995-2025 was adopted as the country's main vehicle for implementing the 1995 Beijing Declaration and Platform for Action (PFA). In order to operationalize the PPGD, the Framework Plan for Women (FPW) was developed in 2001, whose three priority areas are; 1) promotion of women's economic empowerment, 2) protection and advancement of women's rights, and 3) promotion of gender responsive governance.

Another milestone achievement was the passage of the legislation on the Gender and Development (GAD) Budget. The GAD Budget provision mandated all government agencies and instrumentalities including local government units (LGUs) to allocate a minimum of five percent (5%) of their total appropriations for GAD programs and project. This policy has since been incorporated annually in the General Appropriations Act (GAA), though revisions have been made to ensure effective implementation of the GAD budget policy.

2) In Mindanao, especially in Cotabato and Maguindanao Provinces

According to the Mindanao Commission on Women, the Moro and Lumad women are the poorest and most disadvantaged among the Mindanao population, affected by conflicts. Bride abduction, forced marriage and payment of bride price still persist as part of the culturally sanctioned practices in Mindanao. Further, cases of other forms of sexual violence are often reported in Mindanao, especially those in the remote areas.

In addition, poor access to public basic services has negatively affected women and children. For instance, the rate of government health practitioners serving the population, and the rate of births at the health facilities are lower than the national average as illustrated in Tables 8.3.1 to 8.3.4 below:

Table 8.3.1 Distribution of Government Doctors, Dentists, Nurses and Midwives per Region, 2008

Region	Population	Doctors	Dentists	Nurses	Midwives	Doctors /10,000 pop.	Dentists per 10,000 pop.	Nurses /10,000 population	Midwives /10,000 pop.
Philippines	88,566,732	2,838	1,891	4,576	17,437	0.32	0.21	0.52	1.97
Mindanao	21,586,741	581	331	1,009	4,492	0.27	0.04	0.11	0.51
Region 9	3,230,094	100	44	203	697	0.31	0.14	0.63	2.16
Region 10	3,952,437	138	74	241	1,052	0.35	0.19	0.61	2.66
Region 11	4,159,569	75	69	127	743	0.18	0.01	0.01	0.08
Region 12	3,830,500	113	56	194	878	0.30	0.01	0.02	0.10
Region 13	2,293,346	79	58	114	615	0.34	0.01	0.01	0.07
ARMM	4,120,795	76	30	130	507	0.18	0.00	0.01	0.06

Source: Cetrángolo et.al. 2013. Health Care in the Philippines: Challenges and Ways Forward

Table 8.3.2 Normal Type of Deliveries by Place

Area	TOTAL	NORMAL TYPE OF DELIVERIES							
		Total	%	Home	%	Health Facility	%	Other place	%
Philippines	1,904,528	1,785,906	93.77%	243,240	13.62%	1,526,965	85.50%	15,701	0.88%
Mindanao	489,291	460,172	94.05%	101,618	22.08%	350,771	76.23%	7,783	1.69%
Region 9	69,488	68,593	98.71%	10,013	14.60%	54,547	79.52%	4,033	5.88%
Region 10	104,965	89,756	85.51%	15,287	17.03%	73,186	81.54%	1,283	1.43%
Region 11	95,631	88,207	92.24%	13,943	15.81%	72,302	81.97%	1,962	2.22%
Region 12	90,254	85,476	94.71%	17,962	21.01%	67,159	78.57%	355	0.42%
Region 13	56,177	55,364	98.55%	5,780	10.44%	49,470	89.35%	114	0.21%
ARMM	72,776	72,776	100.00%	38,633	53.08%	34,107	46.87%	36	0.05%

Source: Epidemiology Bureau. Department of Health. Field Health Service Information System, Annual Report 2015

Table 8.3.3 Livebirths attended by Medical Doctors, Public Health Nurses and Midwives

Area	Total Livebirths	Livebirth attended							
		Total Livebirths attended by formal health practitioners		by MD		by PHN		by Midwives	
		Total	%	Total	%	Total	%	Total	%
Philippines	1,861,894	1,600,367	85.95%	900,527	48.37%	31,799	1.71%	668,041	35.88%
Mindanao	491,190	407,642	82.99%	203,344	41.40%	10,148	2.07%	194,150	39.53%
Region 9	71,690	60,961	85.03%	27,960	39.00%	3,588	5.00%	29,413	41.03%
Region 10	104,685	91,221	87.14%	57,645	55.07%	777	0.74%	32,799	31.33%
Region 11	95,631	80,779	84.47%	46,924	49.07%	813	0.85%	33,042	34.55%
Region 12	89,902	74,884	83.30%	28,752	31.98%	1,388	1.54%	44,744	49.77%
Region 13	56,165	50,905	90.63%	31,208	55.56%	1,461	2.60%	18,236	32.47%
ARMM	73,117	48,892	66.87%	10,855	14.85%	2,121	2.90%	35,916	49.12%

Source: Epidemiology Bureau. Department of Health. Field Health Service Information System, Annual Report 2015

Table 8.3.4 Livebirths attended by Traditional Birth Attendants and Others

Area	Livebirths attended						Livebirths not attended	
	Total Livebirths attended by informal attendants		by Hilot/TBA		by others			
	Total	%	Total	%	Total	%	Total	%
Philippines	181,719	9.76%	167,777	9.01%	13,942	0.75%	79,808	4.29%
Mindanao	79,050	16.09%	72,863	14.83%	6,187	1.26%	4,498	0.92%
Region 9	9,086	12.67%	8,446	11.78%	640	0.89%	1,643	2.29%
Region 10	13,464	12.86%	12,128	11.59%	1,336	1.28%	0	0.00%
Region 11	14,852	15.53%	12,751	13.33%	2,101	2.20%	0	0.00%
Region 12	15,018	16.70%	13,645	15.18%	1,373	1.53%	0	0.00%
Region 13	5,260	9.37%	5,088	9.06%	172	0.31%	0	0.00%
ARMM	21,370	29.23%	20,805	28.45%	565	0.77%	2,855	3.90%

Source: Epidemiology Bureau. Department of Health. Field Health Service Information System, Annual Report 2015

To show part of the reality in which women and men of (Northern) Cotabato and Maguindanao Provinces, the 2009 Gender Development Index of both the provinces and values of related indicators are shown in Table 8.3.5 below. The values of all the indicators listed in the table show that the situation in Maguindanao was worse in general than that of (North) Cotabato.

Table 8.3.5 Gender Development Index 2009 for Cotabato and Maguindanao Provinces

Province	GDI 2009		Life expectancy at birth 2009		Mean years of schooling 2008		Expected years of schooling 2008	
	Rank	Value	Male	Female	Male	Female	Male	Female
Northern Cotabato	51	0.472	68	58	7	8	11	12
Maguindanao	68	0.543	66	61	6	6	10	11

Province	Estimated earned income (PPP NCR 2009 pesos) 2009		Estimated earned income (PPP US\$) 2009		HDI rank minus GDI rank
	Male	Female	Male	Female	
Northern Cotabato	47,106	24,054	1,554	793	-13
Maguindanao	29,663	17,781	1,066	639	2

Source: Human Development Network. 2013. 2012/2013 Philippine Human Development Report

The Cotabato Provincial Office has been addressing gender gaps in the province. The Office has been supporting women in different aspects, and some of the achievements are reported as follows as at mid 2017:

- There is a favorable environment for women to participate in politics. Actually, the incumbent Governor, Vice Governor and some board members of the Cotabato Province are women and there are other female local political leaders, too.
- They have access to education, trainings and seminars conducted by the government.
- During public consultation of projects, the attendance of women is a must.

- d) Health services for women are also subsidized by the provincial government.
- e) Women also have access to credit, especially to micro lending.
- f) Household chores like farming activities are also shared between men and women.
- g) Women organizations in the province such as Kalipunan ng mga Liping Pilipina (KALUPI), Rural Improvement Clubs (RIC) and others are supported by the Provincial Government.

In addition, it is said that women can be a hope for conflict prone communities. According to Dwyer and Cagoco-Guiam, in Mindanao, Muslim women leaders traditionally play a mediator's role in community conflict cases.

8.3.2 Gender Mainstreaming in the Proposed Components

A quick research was conducted in July 2017 with the Municipal Agriculturist Offices of Pikit of Cotabato Province and Pagalungan of ARMM to understand gender gaps in farming activities in the LMSA. Table 8.3.6 below illustrates the distribution of labor by gender in farming activities recognized by Municipal Agriculturist Offices of Pikit and Pagalungan. Both the offices provided us with the same answers, and the only difference in their answers is who buys chemical inputs for farming as shown below:

Table 8.3.6 Distribution of Roles by Gender in Farming Activities

Particulars		Pikit			Pagalungan		
		Men only (✓)	Women only(✓)	Either or both (✓)	Men only (✓)	Women only(✓)	Either or both (✓)
1	Decisions	Land use	✓			✓	
2		Purchase of farming inputs	Labor	✓		✓	
3			Chemicals	✓		✓	
4			Equipment/machinery	✓		✓	
5		Commercialization (when, to where, to whom, how much, by which means, selling the produces)	✓			✓	
6		Others (Specify) – Post Harvest Activities such as Hauling, Drying & Milling	✓			✓	
7	Practice	Preparation of lands	✓			✓	
8		Purchase of farming inputs	Labor	✓		✓	
9			Chemicals			✓	
10			Equipment/machinery	✓			✓
11		Sowing	✓			✓	
12		Trans-planting			✓		✓
13		Watering	✓			✓	
14		Manual control of weeds			✓		✓
15		Application of fertilizers/pesticides	✓			✓	
16		Harvesting			✓		✓
17		Post-harvest treatments (Hauling, Drying & Milling)	✓			✓	
19		Marketing			✓		✓
20		Sales of the produce			✓		✓
21		Others (Value Adding to the product such as cooking of rice delicacies for additional income)		✓			✓

Source: Municipal Agriculturist's Office of Pikit and Pagalungan

Both the offices responded that men and women share works in farming, and there is a clear division of labors by gender. The criterion applied for the division of labor is the extent, to which physical power is required. Those works requiring more physical power are done by men, while other works requiring less physical power are done by both men and women or by either men or women. On the other hand, food processing to add value to their agricultural produce is done only by women. This criterion is common among farmer households in the project area, irrespective of their religion. Muslim women also play their roles in farming just like Christian women do.

However, all the major decisions on farming activities are made only by men in both the

Municipalities. This means that women do not have control in the farming activities and just offer their labor following the decision by men. Such division of labor by gender and concentration of decision-making power only in men should be considered in the operation and maintenance of the irrigation facilities through the formation and operation of Irrigators Associations (IA), as well as in the planning and implementation of the agricultural component of MMIP II.

Table 8.3.7 below illustrates the female ratio in IA by service area. The table shows that female ratio of MMIP II is higher than that of MMIP I regarding the total members in IA; however, their ratios are around 5% to 10% only. In terms of number of female in board members, there are several women as board members in a few IAs but most of the IAs have only one woman or otherwise NIL woman in the board member:

Table 8.3.7 Female Ratio in IAs of MMIP

Service Area	Female Ratio of Total (%)	Female Ratio in Board Members (%)
MMIP I/MSA	5.79	5.00
MMIP I/UMSA	5.73	9.09
MMIP II/UMSA	9.41	8.79
LAGUNDI PAMBUA* (MMIP II/UMSA)	47.95	11.11
MMIP II/ PESA	10.12	4.35
MMIP II/LMSA	8.61	5.74
TOTAL	9.23	6.42

Note*: LAGUNDI PAMBUA is one of IAs and it has much larger number of women than others.

Source: NIA-PMO

The Philippine Plan for Gender-Responsive Development (1995-2025) contains the long-term vision of women's empowerment and gender equality, and the Gender and Development (GAD) Budget Policy authorizes government agencies, municipalities, state universities and etc. to utilize at least 5% of their annual budget for GAD related activities. The Philippines placed 10th out of 144 countries in the global gender gap index in 2017 but there may be still some gaps especially in rural area, e.g. MMIP area.

On the other hand, the female ratio of total members in LAGUNDI PAMBUA, which is one of IAs, is high and it shares almost as much as half. It can be said that other IAs must have potential to increase their female members. Then, there should be such rule in establishing IA's management board by including women at least 30% or more, so the decision could also refer to the women's intent/ voice.

CHAPTER 9 CONCLUSION AND RECOMMENDATIONS

This Survey was initiated by a request for ODA loan financing as of January 2017 on the remaining (untouched) areas of MMIP II. However, with recognition not feasible technically and financially to construct protection and ring dykes protecting the Lower Malitubog Service Area (LMSA) from the floods of Pulangi river, NIA as well as the Government of Philippines have decided to withdraw the request and instead push through the MMIP II project on its own government budget. With this decision, the JICA Team summarizes the survey results, as conclusion, given of the following:

- 1) The flood protection and ring dykes originally designed by NIA-PMO should NOT be constructed from the view point that;
 - 1.1) As the foundation, on which protection and ring dykes are planned to be constructed, is expected to be very soft, the NIA designed ring dyke having around 7 m height would require consolidation settlement, probably reaching as much as 1.5 m and, in the worst case, would cause potential circular sliding through the foundation if no foundation treatment were to be done. Even if foundation treatment were to be done, such treatment would entail huge construction cost, say approximately 4 billion PHP, which apparently indicates economic non-viability.
 - 1.2) In addition to above, dikes, if constructed, would give on the Liguasan March such impacts of; 1) enlarging the inundation area by 19% - 34%, and 2) raising water level by 65 – 81 cm depending on the return-period (2, 10, 20, 30, 50 and 100 years) according to the flood simulation. This would cause resettlements of the houses on the left bank of the Pulangi river, or at least should provide a means of raising the floor of the houses. The dikes, if constructed, would thus cause social and environmental issues to the existing natural conditions and also on the people's life and livelihood.
 - 1.3) Further in addition, rain falling on the LMSA would cause inland ponding, inundating as much as 50% (80%) of the LMSA during rainy season under 2 (30) - year return period. With 30 nos of drainage sluice gates, each H2m x B2m, at a cost of 2.4 billion Php, the inundation would be released in November, enabling the dry season paddy cultivation under 2-year return period (50 gates under 30 years return period), yet large portions of the LMSA, say 50 – 80%, would anyway have to give up the rainy season's cultivation. If drainage pumps were to be installed, even the rainy season paddy could be cultivated; however it would need an additional cost of 4.2 billion Php under 10 years return period, not economically feasible.
 - 1.4) If dredging were to be tried on the Pulangi river in order to enlarge the flow capacity of the river, namely, mitigating the flood to the LMSA, a scale of 500m expansion of the river almost all along the target sections (94 km) would enable the LMSA almost free from the flooding. However, this measure would require 345 million CUM removal at a huge cost of 22 billion Php for the direct cost only. Besides, partial dredging for only the bottleneck area (13km reach), at which the width of Pulangi river becomes very narrow located at about 6-7 km downstream from the most western part of LMSA, was examined; however, it was revealed that even 500m expansion could have limited effects such as 198 ha, 206 ha, and 339 ha increases of beneficial area under 100-year, 30-year and 2-year return periods, respectively, with huge investments of 3.8 billion Php, 1.5 billion Php and 0.76 billion Php.
- 2) Without flood protection and ring dykes, there should be two options in terms of developing the canal network of the LMSA as to; 1) Case-1 limiting the canal network within the beneficial area less/least affected by inundation (2,810 ha for rainy season and 3,688 ha during dry season), or 2) Case-2 constructing the canal network as per the NIA-PMO original design (original 6,590 ha

cultivable during dry season while only 3,810 ha cultivable for rainy season). This Survey recommends the first option (Case-1) with the following reasons:

- 2.1) In the case of constructing all the canal network in LMSA as per the NIA-PMO original design (Case-2), there should be at least some flood protection works, e.g. canal slope protection, concrete flume introduction, etc., applied to strengthen the mid-terminal points of the canal network flooded every year. This flood protection works would require an additional direct cost of 269.65 million Php at least, which unfortunately would go beyond the originally NEDA approved budget. Further, maintenance cost for the Case-2 will be much higher than that of Case-1, approximately twice higher maintenance cost per unit area than that of Case-1.
- 2.2) In fact, EIRR showed higher return in the Case-2 than Case-1 as 11.87% vs. 10.90%, 10.73% vs. 10.07%, 10.18% vs. 9.68%, 9.32% vs. 9.07% respectively in the cases of NIL damage for wet season paddy, 30% damage, 50% damage and 80% damage for the whole MMIP II area. These EIRRs are however not much different each other, and thus the JICA Team would recommend the canal network development of Case-1 for which the canals are to be constructed mostly within the less/least flooded area and thus maintenance works would be much easier than that of Case-2. It is also indicated by comparing the maintenance costs of Case-2 and Case-1; the former unit cost per ha being almost double than that of the latter, again indicating easier maintenance works in terms of financial arrangement for the Case-1.
- 3) Though the JICA team recommends the Case-1 as afore-mentioned, should NIA want to develop all the LMSA with the Case-2 investment, JICA team would recommend a step-wise development, in that anyway NIA should complete MMIP II as early as possible with the Case-1 investment which is manageable within the available remaining budget, and then in future proceed to the Case-2 investment given additional budget.
- 4) Some of the facilities of MMIP I had been constructed already more than 20 years, requiring certain level of rehabilitation/ repair though lack of budgets has been hindering such rehabilitation works. Especially, gates installed on the headworks are out of order as of 2017, risking the structural stability during high flood season. NIA should prepare for enough budget to carry out necessary rehabilitation and/or improvement works, which may be named as MMIP III. This MMIP III investment may be combined with Case-2 investment.
- 5) Concerning environmental consideration, land acquisition is necessary for the Project implementation, however, as discussed in Chapter 7, almost all of the Project Affected Persons (PAPs) have not accepted the proposed compensation rates for the land loss due to their low amounts, which were fixed in 2003 and being applied even at this moment. As a result, the construction works were started and are on-going without payment of compensation for the land loss. It is recommended to negotiate with the PAPs to fix acceptable compensation rates and to finalize the payment.