

別添 5:テクニカル・ノート(T/N)



JICA Survey Team
CTI Engineering International Co., Ltd.



Tachibana Annex Building
2-25-14 Kameido
Koto-ku, Tokyo 136-0071, Japan

Phone: +81-3-3638-2561
Fax: +81-3-3638-2560

TECHNICAL NOTES
ON
PREPARATORY SURVEY ON THE PROJECT
FOR THE DISASTER RESTORATION OF TEOUMA BRIDGE
IN REPUBLIC OF VANUATU

The Preparatory Survey Team (Team) commissioned to undertake the Outline Design, under Japan International Cooperation Agency (JICA) conducted field surveys and review of existing documents and held several discussions on the technical aspect with the implementing agency and other relevant agencies in relation to "The Project for the Disaster Restoration of Teouma Bridge in Republic of Vanuatu".

This note is signed between The Team and Ministry of Infrastructure and Public Utilities (MIPU) to share mutual understandings and agreement as mentioned in Appendix-1.

Port Vila, 22nd May, 2018


Mr. Sam Namuri
Acting Director General
Ministry of Infrastructure and Public Utilities
(MIPU)




Mr. Yoshihisa NODA
Chief Consultant
JICA Preparatory Survey Team
CTI Engineering International Co., Ltd.

WITNESS:

Mr. Gorge Junior
Acting Director
Public Works Department(PWD)
Ministry of Infrastructure and Public Utilities
(MIPU)



1. Project Background

Most of the residents of Efate island where the capital locates are living along the ring road. And the ring road is playing an important role of the inland transportation. Teouma bridge has been constructed on the Teouma river which is the biggest in the island. It is located at the entrance to the capital from an eastern part of island.

The bridge was completely destroyed by the earthquake whose magnitude was M7.2 and earthquake center was on the western ocean of the Efate island. To response to that, the bridge was reconstructed by the Japan's Grant Aid Program "THE PROJECT FOR REHABILITATION OF BRIDGES ON THE RING ROAD IN THE EFATE ISLAND IN THE REPUBLIC OF VANUATU" in 2003. However, the reconstructed Teouma bridge had been blocked for six days due to the damage of the approach road on right bank by Cyclone Pam in 2015. The damage was caused by the changing of river channel. The bridge is in the state of emergency restoration and at a risk being of destroyed and blocked by the flood now.

In this situation, JICA conducted the data collection survey for reconstruction of Teouma bridge to confirm the causes and measures of the bridge. 1. Stabilization of the river channel 2. Increase of the discharge capacity by extension of the bridge and 3. Overflow approach road have been proposed. And, the government of Vanuatu has requested the full-scale rehabilitation work for Teouma bridge to the government of Japan.

2. General Items

2.1 Interim Report

- MIPU has basically agreed regarding the contents of the Interim Report (IT/R) submitted by the Team on May 04, 2018.

2.2 Project Scope

Project Scope which was proposed in the interim report has been confirmed by MIPU as follows.

- I. Bridge : Plate Girder Type, 2 spans, Road width 8m (Carriage way: $3.0\text{m} \times 2$ + Shoulder: $1.0\text{m} \times 2$)
- II. Riverbank Protection: Reinforced Concrete Crib Type, 250m upstream, 110m downstream
- III. Approach Road: Embankment approx. L=600m, Pipe Culvert $\phi 1.5 \times 6$ nos or equivalent

2.3 Consistency with Future Plan

MIPU clarified that currently there are no plans/projects for rehabilitation of Teouma bridge. Therefore, any development plan to be implemented after this project that is anticipated to affect this project will make its plan consistent with the scope of this project.

2.4 Utilization of Existing Bridge

Existing Pony Truss bridge shall not be utilized for the project for the disaster restoration of

Teouma bridge due to the insufficient width to comply with the requirement of Vanuatu Resilient Road Manual.

2.5 Provision of Temporary Bridge

The Team confirmed that MIPU does not have any temporary bridges in its possession that could be used on detours during the construction period.

2.6 Removal/Demolition of Existing Bridges

Since the reconstructed bridge is aligned along the present alignment, the Project will include removal of existing bridges and installation/removal of temporary detour roads.

2.7 Design Obstacles

The following facilities/objects are likely to be affected for the implementation. These facilities shall be appropriately relocated by the MIPU if these are really affected in the design.

No.	Potential Obstacles	Pictures
1	Overhead Power Line	
2	Fences	

[Handwritten signature]

3. Technical Items

3.1 Road Category and Road Standard

- The road classification of the road around Teouma bridge in accordance with the Vanuatu Resilient Roads Manual -June 2014- (VRRM) is Arterial roads.
- The traffic class at Teouma bridge in accordance with VRRM is T4.

Table 1 Traffic Class

Traffic Classes	TRAFFIC Vehicle per day) (vpd)	Design Parameter
T4	> 500	2 lanes
T3	200 - 500	2 lanes
T2	50 - 200	2 lanes
T1	< 50	1 lane

3.2 Applicable Standards

The following Vanuatu Resilient Roads Manual and/or International Standards such as Austroads, Australian Manual, and Japanese Standards would be applied for planning and design of bridge/roads, structures and road ancillaries.

- 1) Vanuatu Resilient Roads Manual -JUNE 2014- (VRRM)
- 2) Austroads (2009)
- 3) Australian Standards
- 4) Specifications for Highway Bridges (Japan Road Association) / Japanese Standard
- 5) Other reference documents and standards

3.3 Design Speed

Design speed in accordance with the Vanuatu Resilient Roads Manual is 60km/h as per the table below.

Table-2 Design Speed

Traffic Classes	T4	T3	T2	T1
Rolling	40 km/h	30 km /h	30 km / h	10 km / h
Flat	60 km /h	40 km /h	40 km /h	30 km /h

3.4 Hydrological Designing Parameters

Element	Criteria	Source / Comments
ARI (Average Recurrence Interval)	100 years	
Free board	50cm	
HWL	8.4m	

3.5 Road Alignment


Element	Criteria	Source / Comments
Horizontal Alignment	To follow the existing alignment	
Longitudinal Alignment	To be adjusted according to the new elevation of the bridge	
Bridge	To be constructed on the existing alignment	
Detour road / bridge	To be constructed downstream of the existing bridge	

3.6 Geometric Condition and Others

Element	Criteria	Source / Comments
Stopping sight distance	85 m	Adopted highest value of: Section 9.2.1 (c), VRRM
Minimum Curve Radius	100m	Section 9.2.1 (c), VRRM
Cross Section	2 x 3.0 m wide traffic lanes with 2 x 1.0 m wide shoulders on both sides	VRRM Appendix B, Section 9.2.1 (a)
Pavement Surfacing	Sprayed bituminous seal	Road: VRRM
Pavement Layers	Minimum 250 mm thick base course over minimum 5% CBR subgrade	Section 9.2.2 (a), VRRM Subject to traffic loading design during detailed design
Road Side Drains	Trapezoidal shape with maximum 2H:1V side slopes	Section 9.2.3, VRRM
Slope of proposed embankment	1:1.5 ~ 1:2.0	Section 9.2.3, VRRM
Guard Rail	More than 3m embankment	JIS (Japanese Industrial Standards)
Line Marking	Double white lines (BB) applied to all new pavement surfacing Edge lines to bridges and where required to delineate footways	AS1742.2

3.7 Bridge Type and Width

The type of the bridge shall be plate girder type due to the easy maintenance. The typical cross section is shown in Figure-1. Mount up footpath shall not be provided for uniformity of the approach road.



3.8 Bridge Design Condition

Element	Criteria	Source/Comment
Applied Specification	SPECIFICATION FOR HIGHWAY BRIDGES MARCH 2012 Issued by JAPAN ROAD ASSOCIATION	
Design	T20 Truck load, A-Live Load specified in SPECIFICATION FOR HIGHWAY BRIDGES	Equivalent to T44 truck load and L44 lane load
Seismic Condition	SPECIFICATION FOR HIGHWAY BRIDGES MARCH 2012	
Cross section	6.5m for carriage way (2×3m lane, 2×1.00m shoulders)	Following VRRM
Free Board	0.5m	In compliance with Australian Standard and Consistent with ADB project

3.9 Basic Condition of Riverbank Protection

Element	Description
Design horizontal alignment	The horizontal scoured alignment shall be improved. 250m upstream, 110m downstream shall be improved.
Design longitudinal alignment	1:1800 (vertical : horizontal)
Design Cross Section	Width at design flood level (8.4m) : 50m

	Design slope gradient : 1:1.5 Berm : 1.5m Maintenance road : 4m
Scoring depth	2m below the improved river bed
Right Bank	Bank protection shall be provided for the stabilization of the river. Elevation of the riverbank is the same as existing ground.
Left Bank	Elevation of the riverbank shall be EL 5.0m.

3.10 Riverbank Protection

Type : Reinforced Concrete Crib

Description : Concrete Crib (30cm) filled with concrete or concrete with cobble stone (grouted riprap) (20cm)

4. Temporary Yard

Temporary Yards shall be provided by MIPU side during the construction period. The Team confirmed that there should be one location, around 2km east side of Fletcher compound as shown in the Figure-1 in Attachment-1, approximately 10,000m², for establishing offices (consultant office and contractor's office), batching plant and other material stocks.

5. Soil Disposal Yard

The Team confirmed that there should be two locations, one is Etas rubbish dump for the unsuitable materials such as soil coming out from the clearing and grubbing, and river bed excavation, another is the temporary yard mentioned in the former chapter the suitable material coming out from the river bed excavation and the removal of the detour road, etc. as shown in the Figure-1 and 2 in Attachment-1.

6. Stock yard for the dismantled steel members of the existing Teouma bridge

Stock yard for the dismantled steel member of the existing Teouma bridge shall be provided by MIPU side prior to the commencement of the project. The Team confirmed that there should be PWD sheaf division as shown in Figure-3 in Attachment-1. How to reuse of existing Teouma bridge will be studied by MIPU.

7. Detour road during construction

The plan for the detour road during construction as of May 2018 is shown in Figure-4 in Attachment-1. This plan might be revised according to the results of the survey.

Attachment 1: Temporary Yard



Figure-1 Temporary Yard / Soil Disposal Yard for Suitable materials



Figure-2 Temporary Yard / Soil Disposal Yard for suitable materials

[Handwritten signature]



Figure-3 Stock yard for the dismantled steel member of the existing Teouma bridge






Figure-4 Plan for detour road during construction (Blue line)


AX

別添 6：概略設計図









RCC Reinforced Concrete Crib






REV	DESCRIPTION	BY	DATE	REPUBLIC OF VANUATU PUBLIC WORKS DEPARTMENT MINISTRY OF INFRASTRUCTURE AND PUBLIC UTILITIES	PROJECT: PREPARATORY SURVEY ON THE PROJECT FOR THE DISASTER RECONSTRUCTION OF TEOUA BRIDGE IN REPUBLIC OF VANUATU	DESCRIPTION: DETAILED PLAN AROUND ABUTMENT	CONSULTANTS REFERENCE				P.W.D. REFERENCE		SCALE	DRAWING NO.	SHEET NO.
							DRAWN	CHECKED	APPROVED	CHECKED	APPROVED	CHECKED			
													1:400		4

[illegible]




REV. DESCRIPTION		BY		DATE		PROJECT:		DESCRIPTION:		CONSULTANTS REFERENCE		P.W.D. REFERENCE		SCALE		DRAWING NO.		SHEET NO.	
REPUBLIC OF VANUATU PUBLIC WORKS DEPARTMENT MINISTRY OF INFRASTRUCTURE AND PUBLIC UTILITIES						PREPARATORY SURVEY ON THE PROJECT FOR THE DISASTER RECONSTRUCTION OF TEOUWA BRIDGE IN REPUBLIC OF VANUATU		TYPICAL CROSS SECTION (REVEMENT)		CTI ENGINEERING INTERNATIONAL CO., LTD. KOKUSAI KOGYO CO., LTD.		DRAWN		CHECKED		APPROVED		1:400	
																		6	






Detail of Drain Pipe S=1:50



Side View S=1:100




Section A - A


Section B - B

Section C - C

Detail of RC Pile S=1:50



Detail of Riprap S=1:50




Detail of Crib Concrete S=1:20

Detail of Base Concrete S=1:50


Detail of Top Concrete S=1:20

REV	DESCRIPTION	BY	DATE	PROJECT:	DESCRIPTION:	CONSULTANTS REFERENCE	DRAWN	CHECKED	APPROVED	P.W.D REFERENCE	CHECKED	APPROVED	SCALE	DRAWING NO.	SHEET NO.
				REPUBLIC OF VANUATU PUBLIC WORKS DEPARTMENT MINISTRY OF INFRASTRUCTURE AND PUBLIC UTILITIES	PREPARATORY SURVEY ON THE PROJECT FOR THE DISASTER RECONSTRUCTION OF TEOUA BRIDGE IN REPUBLIC OF VANUATU	CTI ENGINEERING INTERNATIONAL CO., LTD. KOKUSAI KOGYO CO., LTD.							AS SHOWN	8	8




Plan S=1:100

REV. DESCRIPTION		BY	DATE	REPUBLIC OF VANUATU PUBLIC WORKS DEPARTMENT MINISTRY OF INFRASTRUCTURE AND PUBLIC UTILITIES		PROJECT: PREPARATORY SURVEY ON THE PROJECT FOR THE DISASTER RECONSTRUCTION OF TEOUWA BRIDGE IN REPUBLIC OF VANUATU		DESCRIPTION: REVEITEMENT(2)		CONSULTANTS REFERENCE CTI ENGINEERING INTERNATIONAL CO., LTD. KOKUSAI KOGYO CO., LTD.				P.W.D. REFERENCE DRAWN CHECKED APPROVED		SCALE DRAWN (A3 SIZE) CHECKED APPROVED AS SHOWN		DRAWING NO.	SHEET NO.
																		9	




Plan S=1:100


Side View S=1:100




Detail of Riprap S=1:50



Detail of Steps S=1:50



Detail of Base Concrete S=1:50



Detail of Top Concrete S=1:20


Section A - A

Section B - B


Section C - C

Detail of RC Pile S=1:50


REV	DESCRIPTION	BY	DATE	PROJECT:	DESCRIPTION:	CONSULTANTS REFERENCE	DRAWN	CHECKED	APPROVED	P.W.D REFERENCE	SCALE	DRAWING NO.	SHEET NO.
				REPUBLIC OF VANUATU PUBLIC WORKS DEPARTMENT MINISTRY OF INFRASTRUCTURE AND PUBLIC UTILITIES	APPROACH STEPS(1)	CTI ENGINEERING INTERNATIONAL CO., LTD. KOKUSAI KOGYO CO., LTD.					AS SHOWN	10	




Side View (Side Concrete) S=1:100



Detail of Side Concrete S=1:20



Detail of Riprap (Side Concrete) S=1:50




Section A-A S=1:50


REV		DESCRIPTION	BY	DATE	PROJECT:		DESCRIPTION:		CONSULTANTS REFERENCE		DRAWN		CHECKED		P.W.D. REFERENCE		SCALE		DRAWING NO.		SHEET NO.	
					REPUBLIC OF VANUATU PUBLIC WORKS DEPARTMENT MINISTRY OF INFRASTRUCTURE AND PUBLIC UTILITIES		PROJECT: PREPARATORY SURVEY ON THE PROJECT FOR THE DISASTER RECONSTRUCTION OF TEOUA BRIDGE IN REPUBLIC OF VANUATU		CTI ENGINEERING INTERNATIONAL CO., LTD. KOKUSAI KOGYO CO., LTD.								AS SHOWN		11			

GENERAL VIEW OF TEQUMA BRIDGE


ELEVATION S=1:200



TYPICAL SECTION S=1:50






PLAN S=1:200



Design Conditions

Bridge Length	58.00m
Girder Length	57.60m
Span Length	28.40m=28.40m
Full Width	10.30m
Effective Width	9.50m
Clearance	AI=105° 11' 35" PI A2=102° 00' 00"
Curve Radius	R=735~R=∞
Longitudinal Gradient	0.73%
Super-elevation	2.5% ~ 1.08% ~ 2.5%
Live Load	A Live Load=TL
Pavement	Concrete Pavement t=20~15cm
Skid Coefficient	Wet 3
Superstructure	2 Span Continuous Steel Plate Girder
Substructure	T-Gravity Abutment (A1, A2), Nail Type Pier (P1)
Pile	Spiral Rotation Pile (MS EDO SPIRAL 6600)
Material for Superstructure	SS400, SM400, SM400 ST07 (Japan Industrial Standards)
Material for Substructure	Concrete: 24N/mm ² Re-Bar: 24N/mm ² Concrete: 24N/mm ² Re-Bar: 24N/mm ² Concrete: 24N/mm ² Re-Bar: 24N/mm ²
Bridge Grade	Grade A
Soil Type	Type III
Specification	Specifications for Highway Bridges 1~4 (2012)

PROJECT:	REPUBLIC OF VANUATU PUBLIC WORKS DEPARTMENT MINISTRY OF INFRASTRUCTURE AND PUBLIC UTILITIES	DESCRIPTION:	PREPARATORY SURVEY ON THE PROJECT FOR THE DISASTER RECONSTRUCTION OF TEQUMA BRIDGE IN REPUBLIC OF VANUATU	CONSULTANTS REFERENCE:	CTI ENGINEERING INTERNATIONAL CO., LTD. KOKUSAI KOGYO CO., LTD.	P.W.D. REFERENCE:	CHECKED	APPROVED	SCALE:	DRAWING NO.	SHEET NO.
REV.	DESCRIPTION	BY	DATE								12



Live Load	A Live Load-1L
Bridge Type	2 Span, Continuous Steel Plate Girder
Bridge Length	598.00m
Girder Length	57.60m
Span Length	28.40m+28.40m
Full Width	10.30m
Effective Width	7.00m
Slope	R=1:105' 11" 35', P1 A2=102' 00" 00"
Curve Radius	R=1715'-R=∞
Longitudinal Gradient	0.77%
Super elevation	2.5% ~ 1.04% ~ 2.5%
Slab	Re Slab t=184mm
Pavement	Concrete Pavement t=28~115.5mm
Seismic Coefficient	kh=0.3 (Level-1)
Steel	SS400, SM490Y, S10T
Material	Concrete
Re-Bar	σ _{yk} =24N/mm ²
Specification	SD345
	Specifications for Highway Bridges [~V (2012)]

[illegible]

(M)




Table of Elevation

	AI (onSI)						(Unit)
	G6	G5	G4	G3	G2	G1	
Road Elevation	10.871	10.884	10.875	10.856	10.821	10.786	
THK of Conc Surfacing	0.132	0.142	0.129	0.107	0.069	0.031	
THK of Slab	0.180	0.180	0.180	0.180	0.180	0.180	
Height of Haunch	0.080	0.080	0.080	0.080	0.080	0.080	
Elev. of top of FLG.	10.470	10.482	10.486	10.489	10.492	10.495	
Grider height	1.200	1.200	1.200	1.200	1.200	1.200	
THK of Low FLG.	0.028	0.015	0.013	0.013	0.015	0.028	
THK of Sole Plate	0.026	0.026	0.026	0.026	0.026	0.026	
Height of Shoe	0.166	0.166	0.166	0.166	0.166	0.166	
Shoe Elevation	9.959	9.075	9.081	9.084	9.085	9.075	
Height of Mortar	0.030	0.030	0.030	0.030	0.030	0.030	
Height of Shoe Bed	0.180	0.196	0.202	0.205	0.206	0.196	
Elevation of Bridge Seat	8.849	8.849	8.849	8.849	8.849	8.849	
Suener elevation			Level				

Design Conditions


Title	Specification
Superstructure	2 Span Continuous Non Composite Steel Girder
Substructure	1-Conversion Abutment
Soice Type	Moiv
Specified Overst Strength	24 N/mm ²
Re-Bar Grade	SD 345 (Japan Industrial Standards)
Splice Length	31.25 ϕ
Max. Re-Bar Length	12m
Pile Type	Spiral Rotation Pile, NS, Eco-Rotation Pile, ϕ 600

[illegible]


General View of A1 (2/2)

Wing Wall (Downstream)

Note) () shows inside dimension.


Wing Wall (Upstream) $B - B$

Note) () shows inside dimension.




Plan of Approach Slab




Note) $\frac{\text{Elev. of Road Surface FH}}{\text{Elev. of Approach Slab Surface FH}} - 1$ t=Thickness of Pavement




Support Details: 1:20



Plan


C
-
CD
-
D

Railing Detail $S=1:10$



Shoe Bed Details^{1:20}

Detail "a" §1:5







	G6	G5	G4	G3	G2	G1
h1	180	196	202	205	206	196
h2	190	206	212	215	216	206
h3	196	212	218	221	222	212
h4	164	180	186	189	190	180
h5	170	186	192	195	196	186

[illegible]



General View of P1

$$S=1:100$$


Side View
(Road Center)



Height of Shoe Bed




P6-16


Table of Elevation

		P1						Unit
		G1	G2	G3	G4	G5	G6	
	Road Elevation	10.556	10.592	10.629	10.676	10.585	10.543	
	THK of Conc Surfacing	0.023	0.061	0.101	0.101	0.062	0.023	
	THK of S Lab	0.180	0.180	0.180	0.180	0.180	0.180	
	Hght. of Haunch	0.080	0.080	0.080	0.080	0.080	0.080	
	Elev. of top of F.L.G.	10.273	10.271	10.268	10.265	10.263	10.260	
	Grider height	1.200	1.200	1.200	1.200	1.200	1.200	
	THK of Low F.L.G.	0.039	0.030	0.030	0.030	0.030	0.039	
	THK of Se Plate	0.026	0.026	0.026	0.026	0.026	0.026	
	Hght. of Shoe	0.247	0.247	0.247	0.247	0.247	0.247	
	Shoe Elevation	8.761	8.768	8.765	8.762	8.760	8.748	
Height of Mortar	0.030	0.030	0.030	0.030	0.030	0.030		
Height of Shoe Bed	0.123	0.130	0.127	0.124	0.122	0.110		
Elevation of Bridge Seat	8.608	8.608	8.608	8.608	8.608	8.608		
Span length		Level						

Plan of Shoe Position






Plan of Pile Cap



Design Conditions

Title	Specification
Superstructure Substructure	2 Span Continuous Non Composite Steel Girder
Shoe Type	Wall Type Pier
Shoe Type	Fix
Specified Concrete Strength	24 N/mm ²
Re-Bar Grade	SD 345 (Japan Industrial Standards)
Splice Length	31.25 ϕ
Max. Re-Bar Length	12m
Pile Type	Spiral Reinforced Pile (NS Form Pile)
	$\phi 600$

(M)



	A2 (ms2)						(Unit)
	G1	G2	G3	G4	G5	G6	
Road Elevation	10.323	10.371	10.408	10.405	10.364	10.322	
THK of Core Surfing	0.035	0.061	0.101	0.101	0.062	0.023	
THK of S lab	0.180	0.180	0.180	0.180	0.180	0.180	
Height of Haunch	0.080	0.080	0.080	0.080	0.080	0.080	
Elev. of top of F&G	10.052	10.050	10.047	10.044	10.042	10.039	
Girder Height	1.200	1.200	1.200	1.200	1.200	1.200	
THK of Low F&G	0.028	0.015	0.013	0.013	0.015	0.028	
THK of Sole Plate	0.026	0.026	0.026	0.026	0.026	0.026	
Height of Shoe	0.166	0.166	0.166	0.166	0.166	0.166	
Shoe Elevation	8.632	8.643	8.642	8.639	8.635	8.619	
Height of Mortar	0.030	0.030	0.030	0.030	0.030	0.030	
Height of Shoe Bed	0.183	0.194	0.193	0.190	0.186	0.170	
Elevation of Bridge Seat	8.419	8.419	8.419	8.419	8.419	8.419	
Super Elevation							Level


Title	Specification
Superstructure	2 Span Continuous Non Composite Steel Girder
Substructure	T-Convexity Abutment
Shoe Type	Move
Specified Concrete Strength	24 N/mm ²
Re-Bar Grade	SD 345 (Japan Industrial Standards)
Splice Length	31.25 ϕ
Max. Re-Bar Length	12m
Min. Re-Bar Length	Soil Rotation Pile (MS For Soil Pile) 4.600
Pile Type	MS For Soil Pile

[illegible]

(M)




Height of Shoe Bed						
	G1	G2	G3	G4	G5	G6
h1	183	194	193	190	186	170
h2	193	204	203	200	196	180
h3	199	210	209	206	202	186
h4	167	178	177	174	170	154
h5	173	184	183	180	176	160



Point	Station	Northing	Easting	Element	Distance
Main Road					
BP	0+00.000	8033842.557800	222161.173700	R=∞	15.996
BC 1.0	0+15.996	8033829.019157	222169.676586	R=259.208	132.136
EC 1.0	1+48.132	8033739.515822	222264.935398	R=∞	73.536
BC 2.0	2+21.668	8033704.301471	222329.490955	R=175.000	133.569
EC 2.0	3+55.236	8033688.988399	222468.938547	R=∞	98.783
BC 3.0	4+54.019	8033714.753430	222554.302106	R=200.000	126.865
EC 3.0	5+80.884	8033708.109376	222678.873431	R=∞	80.974
BC 4.0	6+61.858	8033678.794152	222754.354827	R=431.368	112.389
EC 4.0 (EP)	7+74.247	8033624.993732	222852.668240		

1	2	3	4
IP	IP	IP	IP
IA	IA	IA	IA
29.12.27.260	36.43.51.624	36.20.38.537	14.55.40.449
R	R	R	R
259.208	175.000	200.000	431.368
TL	TL	TL	TL
67.537	70.227	65.648	56.515
SL	SL	SL	SL
8.654	13.565	10.499	3.686
CL	CL	CL	CL
132.136	133.569	126.865	112.389

REV	DESCRIPTION	BY	DATE	PROJECT:	DESCRIPTION:	CONSULTANTS REFERENCE	P.W.D. REFERENCE	SCALE	DRAWING NO.	SHEET NO.
				REPUBLIC OF VANUATU PUBLIC WORKS DEPARTMENT MINISTRY OF INFRASTRUCTURE AND PUBLIC UTILITIES	PREPARATORY SURVEY ON THE PROJECT FOR THE DISASTER RECONSTRUCTION OF TEOUMA BRIDGE IN REPUBLIC OF VANUATU	CTI ENGINEERING INTERNATIONAL CO., LTD. KOKUSAI KOGYO CO., LTD.		1:2000	19	






[illegible]


End Point
STA+20.000

Box Culvert 2 5x3 5x2
STA+48.193


Teouma Bridge L=58.0m
STA.3+45.484 STA.4+3.484

Start Point
STA+0+00.000







Wet Stone Pitching (1)




Wet Stone Pitching (3)




Wet Stone Pitching (4)



Side View S=1:50






Development View S=1:200



Detail of PVC Pipe Drain S=1:20

Detail of Base Concrete S=1:20



REV	DESCRIPTION	BY	DATE	PROJECT:	DESCRIPTION:	CONSULTANTS REFERENCE	P.W.D. REFERENCE	SCALE	DRAWING NO.	SHEET NO.
				REPUBLIC OF VANUATU PUBLIC WORKS DEPARTMENT MINISTRY OF INFRASTRUCTURE AND PUBLIC UTILITIES	WET STONE PITCHING	CTI ENGINEERING INTERNATIONAL CO., LTD. KOKUSAI KOGYO CO., LTD.	CHECKED APPROVED	AS SHOWN	24	




Plan S=1:100

Side View S=1:100

Detail of Drain Pipe S=1:50



Detail of Crib Concrete S=1:20




RCC (1)


RCC (2)

Development View S=1:400


REV	DESCRIPTION	BY	DATE	PROJECT:	DESCRIPTION:	CONSULTANTS REFERENCE	P.W.D. REFERENCE	SCALE	DRAWING NO.	SHEET NO.
				REPUBLIC OF VANUATU PUBLIC WORKS DEPARTMENT MINISTRY OF INFRASTRUCTURE AND PUBLIC UTILITIES	PREPARATORY SURVEY ON THE PROJECT FOR THE DISASTER RECONSTRUCTION OF TEOUA BRIDGE IN REPUBLIC OF VANUATU	CTI ENGINEERING INTERNATIONAL CO., LTD. KOKUSAI KOGYO CO., LTD.	DRAWN CHECKED APPROVED	AS SHOWN	25	




RCC (3)




RCC (4)




RCC (5)




RCC (6)




RCC (7)



RCC (8)




RCC (9)




RCC (10)

Development View S=1:400


REVISION		CONSULTANTS REFERENCE		P.W.D. REFERENCE		SCALE		DRAWING NO.		SHEET NO.	
NO.	DESCRIPTION	BY	DATE	DESIGN	CHECKED	APPROVED	CHECKED	APPROVED	AS SHOWN	26	
				PROJECT:				DESCRIPTION:			
				REPUBLIC OF VANUATU PUBLIC WORKS DEPARTMENT MINISTRY OF INFRASTRUCTURE AND PUBLIC UTILITIES				PREPARATORY SURVEY ON THE PROJECT FOR THE DISASTER RECONSTRUCTION OF TEOUMA BRIDGE IN REPUBLIC OF VANUATU			
				REINFORCED CONCRETE CRIB (TYPE-B) (1)				CTI ENGINEERING INTERNATIONAL CO., LTD. KOKUSAI KOGYO CO., LTD.			




Detail of Drain Pipe




Detail of Base Concrete S=1:50



Detail of RC Pile S=1:50








Section C - C




Detail of Top Concrete S=1:20

AP6-27




Detail of Steps S=1:50

Section A-A S=1:50



Section A - A



Section C - C

Section B - B


Detail of RC Pile S=1:50

Detail of Top Concrete S=1:20


Detail of Base Concrete S=1:50

Detail of Side Concrete S=1:20


REV	DESCRIPTION	BY	DATE	PROJECT:	DESCRIPTION:	CONSULTANTS REFERENCE	P.W.D. REFERENCE	SCALE	DRAWING NO.	SHEET NO.
				REPUBLIC OF VANUATU PUBLIC WORKS DEPARTMENT MINISTRY OF INFRASTRUCTURE AND PUBLIC UTILITIES	APPROACH STEPS AT ROAD EMBANKMENT	CTI ENGINEERING INTERNATIONAL CO., LTD. KOKUSAI KOGYO CO., LTD.	CHECKED APPROVED	AS SHOWN	28	




Crash Barrier S=1:50




Maintenance Road S=1:50




Trapezoidal Drainage at Box Culvert S=1:100



Catch Basin (600x600x700) S=1:20



Pipe Culvert φ500 S=1:20



Pipe Culvert φ300 S=1:20




REPUBLIC OF VANUATU
PUBLIC WORKS DEPARTMENT
MINISTRY OF INFRASTRUCTURE AND
PUBLIC UTILITIES

PROJECT:
PREPARATORY SURVEY ON THE PROJECT
FOR THE DISASTER RECONSTRUCTION OF
TEOUWA BRIDGE IN REPUBLIC OF VANUATU


DESCRIPTION:
STRUCTURE

CONSULTANTS REFERENCE
CTI ENGINEERING INTERNATIONAL CO., LTD.
KOKUSAI KOGYO CO., LTD.


DRAWN
CHECKED
APPROVED
P.W.D. REFERENCE
CHECKED
APPROVED
SCALE
AS SHOWN
DRAWING NO.
29
SHEET NO.




STANDARD SECTION OF BOX CULVERT S=1:100




DETAIL OF WATER SEALANT S=1:40



JOINT SECTION S=1:100




SIDE VIEW S=1:200




PLAN VIEW S=1:200


REV	DESCRIPTION	BY	DATE	REPUBLIC OF VANUATU PUBLIC WORKS DEPARTMENT MINISTRY OF INFRASTRUCTURE AND PUBLIC UTILITIES	PROJECT: PREPARATORY SURVEY ON THE PROJECT FOR THE DISASTER RECONSTRUCTION OF TEOUWA BRIDGE IN REPUBLIC OF VANUATU	DESCRIPTION: GENERAL VIEW OF BOX CULVERT (1)	CONSULTANTS REFERENCE CTI ENGINEERING INTERNATIONAL CO., LTD. KOKUSAI KOGYO CO., LTD.	P.W.D. REFERENCE DRAWN CHECKED APPROVED	SCALE CHECKED APPROVED (A3 SIZE)	DRAWING NO. 30	SHEET NO.
-----	-------------	----	------	--	---	--	---	--	---	-------------------	-----------




PLAN S=1:200



A-A SECTION S=1:100



B-B SECTION S=1:100



C-C SECTION S=1:100



REPUBLIC OF VANUATU
PUBLIC WORKS DEPARTMENT
MINISTRY OF INFRASTRUCTURE AND
PUBLIC UTILITIES




PROJECT:
PREPARATORY SURVEY ON THE PROJECT
FOR THE DISASTER RECONSTRUCTION OF
TEOUA BRIDGE IN REPUBLIC OF VANUATU

DESCRIPTION:
GENERAL VIEW OF BOX CULVERT
(2)


CONSULTANTS REFERENCE
CTI ENGINEERING INTERNATIONAL CO., LTD.
KOKUSAI KOGYO CO., LTD.

DRAWN: _____ CHECKED: _____ APPROVED: _____
SCALE: AS SHOWN
P.W.D. REFERENCE: _____


DRAWING NO. 31
SHEET NO.




--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--



PROJECT:		DESCRIPTION:		CONSULTANTS REFERENCE				P.W.D. REFERENCE		SCALE		DRAWING NO.		SHEET NO.	
REPUBLIC OF VANUATU PUBLIC WORKS DEPARTMENT MINISTRY OF INFRASTRUCTURE AND PUBLIC UTILITIES		PREPARATORY SURVEY ON THE PROJECT FOR THE DISASTER RECONSTRUCTION OF TEOUMA BRIDGE IN REPUBLIC OF VANUATU		CTI ENGINEERING INTERNATIONAL CO., LTD. KOKUSAI KOGYO CO., LTD.				DRAWN		CHECKED		APPROVED		1:1000	
BY		DATE												33	



--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--




START
0+0.000

Slope Protection
L=30.0m
Bridge L=40.0m
Slope Protection
L=30.0m
Slope Protection
L=20.0m




Slope Protection
L=20.0m

END
6+44.918

Pipe Culvert 60x90
5+44.482



VERTICAL ALIGNMENT	FORMATION HEIGHT	GROUND HEIGHT	DISTANCE	STATION	HORIZONTAL CURVATURE	SUPER ELEVATION	WIDENING
8.140	8.114	7.51	20.000	EP	L=100.436 R=100	5.000	
7.51	7.51	7.51	20.000	STA.6		5.000	
7.51	7.51	7.51	20.000	BC 5-0		5.000	
7.51	7.51	7.51	20.000	STA.5		5.000	
7.51	7.51	7.51	20.000	BC 4-0		5.000	
7.51	7.51	7.51	20.000	STA.4		5.000	
7.51	7.51	7.51	20.000	BC 3-0		5.000	
7.51	7.51	7.51	20.000	STA.3		5.000	
7.51	7.51	7.51	20.000	BC 3-0		5.000	
7.51	7.51	7.51	20.000	STA.2		5.000	
7.51	7.51	7.51	20.000	BC 2-0		5.000	
7.51	7.51	7.51	20.000	STA.1		5.000	
7.51	7.51	7.51	20.000	BC 1-0		5.000	
7.51	7.51	7.51	20.000	BP		5.000	



REV	DESCRIPTION	BY	DATE	REPUBLIC OF VANUATU PUBLIC WORKS DEPARTMENT MINISTRY OF INFRASTRUCTURE AND PUBLIC UTILITIES	PROJECT: PREPARATORY SURVEY ON THE PROJECT FOR THE DISASTER RECONSTRUCTION OF TEOUWA BRIDGE IN REPUBLIC OF VANUATU	DESCRIPTION: TYPICAL CROSS SECTION (DETOUR ROAD)	CONSULTANTS REFERENCE				P.W.D REFERENCE		SCALE	DRAWING NO.	SHEET NO.
							DRAWN	CHECKED	APPROVED	CHECKED	APPROVED	APPROVED (A3 SIZE)			
													1:200	37	

別添 7：環境モニタリングフォーム(案)

Proposed Monitoring Form

Environmental Management Plan

Proposed monitoring forms, based on Table 1.3-19 Environmental Management and Monitoring Plan (EMMP), are shown below.

1. Response/Actions to Comments and Guidance from Government Authorities and the Public

Monitoring Item	Monitoring Results during Report Period
Number and contents of formal comments made by the public	
Number and contents of responses from Government agencies	

2. Pollution

1) Air Quality

Item	Unit	Situations of Dust Based on the observation	Measurement Point	Frequency
Dust	-	1. good 2. Acceptable level 3. bad	Construction site	Daily

2) Surface Water Quality

Item	Unit	Down-stream	Main point	Up-stream	Country Standards	Standards for Contract	Referred National Standards	Frequency
pH	-				-	6.5-9.5	NF T 90-008	weekly
Temperature	degree				-	<3		
Turbidity	NTU				-	≤2	standards for tap water in japan	
DO	mg/l				-	≥7.5	rivers categorized as AA, which water can be used as drinking water with simple filtering method in Japan	
Oil & grease	Yes/No				-	observed		

Result of the baseline survey and standards

Analysis	Sample 1	Sample 2	Sample 3	Unit	Standard
pH	8.03	8.01	8.27		>6.5 & < 9.5 (NF T 90-008)
Turbidity	2.74	1.98	0.5	NTU	(≤2 standards for tap water in japan)
Conductivity	455	462	457	μS/cm	

Source: Baseline survey (JICA study)

3) Noise and Vibrations

Item	Unit	Measured Value (mean)	Measured Value (Max)	Country Standards	Standards for Contract	Referred International Standards	Measurement Point	Frequency
Noise LAeq	dB(A)					70 (Japan)	Construction site/edge of the construction area (near houses)	Monthly
Vibrations	dB(A)					75 (Japan)	Construction site/edge of the construction area (near houses)	Monthly

Ambient noise standards in Japan

No	Area	Time During Day (hours)	Limits, dB(a)
1.	Commercial/Industrial Noise	6:00 – 22:00	70 dB or less
2.	Neighborhood Noise	6:00 – 22:00	55 dB or less

Result of the baseline survey

No	Area	Time During Day (hours)	Limits, dB(a)
1.			
2.			

4) Waste (Construction waste)

Date:

Item: Waste Management

Mark: "✓" if management is done as required

Location	Kind of waste	Volume of waste (m3)	Final disposal or reuse	Stored at designated place	Waste separation	Remark

5) Mitigation measures

Date:

Mark: "✓" if mitigation measure is done

No	item	Monitoring Site	Mitigation measure is done or not Conditions of facilities	Remarks
1	Check the conditions of vehicles (dust control)			
2	Watering (dust control)			
3	Covering truck load with a sheet (dust control)			
4	Using oil pan (water/soil pollution prevention)			
5	Temporary cofferdam			
6	Sedimentation pond/drainage			

3. Natural Environment

1) Biota and ecosystems

Item	Monitoring Results during Report Period	Measures to be Taken	Frequency
Clearance activities (visual inspection)			Weekly
Management of top soil (visual inspection)			Weekly

2) Hydrological Situation

Item	Monitoring Results during Report Period	Measures to be Taken	Frequency
Impact of construction work on steep slope (visual inspection)	Soil erosion		Weekly

4. Social Environment

1) Land acquisition

Pre-Construction phase

Resettlement, Land expropriation, and compensation for assets and crops (monthly report)

	Planned Total	Unit	2020.1		2020.2		2020.3				Expected completion date	Responsible organization
			Qty	%	Qty	%	Qty	%	Qty	%		
1.Update PAPs list and Final Asset Valuation												DOL
1-1 Identification of final PAHs	6 101	HH Business										
1-2 Announcement to Affected people	2	Time										
1-3 Inventory survey and final cost estimation for expropriation	1	Time										
1-4 Consultation meeting times	4	Time										
1-5 Agreement signed by PAHs	6 101	HH Business										
2. Progress of land acquisition												DOL
2-1 Permanent land acquisition Customary land	8,438	m2										
2-2 Permanent land acquisition Leased farm land	4,143	m2										
2-3 Temporary land acquisition Customary land	10,936	m2										
3.Progress of compensation in cash												DOL
3-1 Structure	6	structure										
Crop/trees	6	HH										
Compensation for loss of business	101	business										

Date				
------	--	--	--	--

Training programs

No	Date	Training	Agenda	Participant
1				
2				

During Construction
Safety management

Date:

No	item	Result	Remarks
1	Number of meetings organized since the previous monitoring		
2	Safety gear distribution (%)		
3	Keep records of accidents and injuries properly (Yes/No)		
4	Installation of fences, assignment of guards (Yes/No)		

Record of Accidents

No	Date	Details of accidents	Solution / Result / Any actions to be taken

4) Other checklist

Mark: “✓” if mitigation measure is done

Date:

No	item	Monitoring Site **	Mitigation measure is done or not	Remarks
1	Communities get the information on the construction schedule			
2	Communities know get the information of traffic management			
3	Installation of signboard			
4				

5) Record of Complaints

No	Date	Complains	Solution / Result / Any actions to be taken