Republic of Vanuatu Ministry of Infrastructure and Public Utilities, Public Works Department

PREPARATORY SURVEY ON THE PROJECT FOR THE DISASTER RECONSTRUCTION OF TEOUMA BRIDGE

FINAL REPORT

November 2019

JAPAN INTERNATIONAL COOPERATION AGENCY

CTI ENGINEERING INTERNATIONAL CO., LTD. KOKUSAI KOGYO CO., LTD.

EI JR 19-108

Republic of Vanuatu Ministry of Infrastructure and Public Utilities, Public Works Department

PREPARATORY SURVEY ON THE PROJECT FOR THE DISASTER RECONSTRUCTION OF TEOUMA BRIDGE

FINAL REPORT

November 2019

JAPAN INTERNATIONAL COOPERATION AGENCY

CTI ENGINEERING INTERNATIONAL CO., LTD. KOKUSAI KOGYO CO., LTD.

PREFACE

Japan International cooperation Agency (JICA) decided to conduct the preparatory survey and entrust the survey to the Consortium of CTI Engineering International Co., LTD. and Kokusai Kogyo Co., LTD.

The survey team held a series of discussions with the officials concerned of the Government of the Republic of Vanuatu, and conducted field investigations. As a result of further studies in Japan, the present report was finalized.

I hope that this report will contribute to the promotion of the project and to the enhancement of friendly relations between our two countries.

Finally, I wish to express my sincere appreciation to the officials concerned of the Government of the Republic of Vanuatu for their close cooperation extended to the survey team.

November 2019

Itsu ADACHI Director General Infrastructure and Peacebuilding Department Japan International Cooperation Agency

SUMMARY

1. OUTLINE

(1) Background and Outline of the Project

Most of the residents of Efate Island where the capital of the Republic of Vanuatu is located live along the Ring Road. The Ring Road plays an important role for inland transportation. Teouma Bridge has been constructed on the Teouma River which is the largest river in the island. It is located at the entrance to the capital from the eastern part of the island.

The bridge was completely destroyed by an earthquake of magnitude M7.2. In response, the bridge was reconstructed through the Japan's Grant Aid Program "The Project for Rehabilitation of Bridges on the Ring Road in the Efate Island in the Republic of Vanuatu" in 2003.

However, the rehabilitated Teouma Bridge had been blocked for six days due to the damage of the approach road on the right bank by Cyclone Pam in 2015. The damage was caused by the changing of the river course. The bridge has been temporarily rehabilitated and it is at the risk of being destroyed and blocked by another sever flood.

Under this circumstance, JICA conducted a data collection survey in 2016 to investigate and confirm the direction for the bridge rehabilitation. It has been proposed to implement three types of works, which are: 1) Stabilization of the river course; 2) Extension of the bridge to increase flow capacity; and 3) Overflow approach road.

Based on the survey results, background, purpose and content of the project has been identified in "The Project for the Disaster Reconstruction of Teouma Bridge in Republic of Vanuatu", based on the assumption that Japan's Grant Aid will be used. Effectiveness, human / technical / economic relevance was examined, outline design was conducted for the necessary and optimal project content and scale, and the approximate project cost was estimated. Moreover, the survey and study covered obligations of recipient country, drafted an implementation plan, operation and maintenance key points and considerations to achieve the project objectives.

(2) Summary of Vanuatu

Vanuatu is in the Pacific Rim orogenic belt extending from the Solomon Islands to Fiji and consists of more than 80 islands. The total land area is about 12,190 km² with a population of about 270,000 (2017 estimation). The area of Efate Island, where the capital city Port-Vila locates, is about 900km². This island has the highest population density in Vanuatu.

Real GDP of Vanuatu is US\$ 863,000,000 (The World Bank, 2017), and the economic growth rate has been positive since 2004 except in 2015 due to Cyclone Pam. In 2017, economic growth rate was estimated at 4.5% (The World Bank). Agriculture and tourism are two major economy sectors of Vanuatu.

Vanuatu climate is tropical oceanic with stable temperatures, high humidity, and rainy throughout the year. Wind is calm except during tropical storms (about 9.3 km/hour to18.5 km/hour). The Vanuatu climate can be classified into two seasons: dry season, from May to November, and the rest is rainy season. The annual average temperature is about 25 degrees Celsius. The average temperature of the hottest season,

that is in February, is about 27° C while the average temperature of the coolest season, that is in August is about 23° C. The average annual precipitation is about 2,100 mm.

(3) Result of the Survey and Contents of the Project

JICA dispatched four survey teams to Vanuatu from November 2017 to March 2019 as shown in Table 1 below.

The first field survey was conducted during the rainy season. Following discussions with concerned officials of Vanuatu, the survey team determined the scope of the project and carried out a field survey for road plans (width composition, pavement type, road geometry, etc.), bridge plans and selection of superstructure type, natural conditions and topography, procurement of construction materials and equipment as well as operation and maintenance system.

The second field survey was conducted during the dry season. The survey team carried out project site confirmation, natural conditions and geology, traffic volume survey, axle load survey, implementation plan and also cost estimation. The results of the first and second field surveys helped the survey team to design a bridge and road, draft an implementation plan as well as come up with a rough project cost estimation back in Japan.

During the third survey, Vanuatu side requested that a sidewalk be provided for the bridge. The team then redesigned the bridge as per the request.

During the fourth field survey, the design outline as well as obligations of Vanuatu side were confirmed.

Table-1 Field Survey Lenou						
Survey	Period					
First Field Survey (first team)	From 12 th Nov. 2017 to 22 nd Dec. 2017					
First Field Survey (second team)	From 16 th Jan. 2018 to 4 th Feb. 2018					
Second Field Survey	From 24 th Apr. 2018 to 7 th Jun. 2018					
Third Field Survey	From 19th Mar. 2019 to 3rd Apr. 2019					
Fourth Field Survey	From 25 th Aug. 2019 to 3 rd Sep. 2019					

Table-1 Field Survey Period

In this Survey, H.W.L. was set to 100-year precipitation return period for bridge design. The survey team selected seal pavement according to the local procurement situations and specification. The proposed outline of the plan is as follows.

[Bridge Type]	Superstructure : 2 Spans Continuous Steel Plate Girder				
	Substructure	: Reversed T Type Abutment and Wall Type Pier			
	Pile	: Spiral Steel Rotation Pile			
[Bridge Length]	58 m				
[Road Width]	Approach road	: Effective Width 8.0 m			
		(Lane 3.0 m * 2 + Shoulder 1.0 m * 2)			
	Bridge: Effecti	ve Width 9.5 m			
		(Lane 3.0 m * 2 + Shoulder 0.5 m * 2 + Sidewalk 1.25 m * 2)			
[Approach Road]	Total Length: 5	562 m (B.P. side 245.5 m, E.P. side 316.5 m),			

	20,000 m ³ Embankment
[River Improvement]	Total Length 482.5 m, Reinforced Concrete Revetment 100.0 m,
	Stone Pitching 302.5 m, Riprap 80.0 m

(4) Construction Period and Rough Cost of the Project

The construction period of the project is approximately 7 months (including the bidding period) for the detailed design, and 26 months for the construction of facilities. The project cost to be borne by the recipient country is estimated to be about 73 million Vanuatu Vatu (75 million Japanese Yen, VUV1.0=JPY1.039).

For confidentiality, the cost to be borne by the Japan' Grant Aid is not shown in this report.

(5) Project Evaluation

1) Relevancy

Implementations of this cooperation projects is recommended using Japan's grant aid as follows:

- 1. The beneficiaries' populations are almost half of the east Efate Island. It is a big number.
- 2. The project is urgently needed on the Ring Road to contribute to the strengthening of trunk road transport networks and to stabilize and improve the livelihoods of residents.
- 3. Vanuatu authorities could operate and maintain bridges and roads using internal resources and technologies. There is no need for sophisticated technology for operation and maintenance.
- 4. This project contributes to the environmental and economic objectives of Vanuatu national development plan: "Recovery from climate change and disasters" and "Improving infrastructure".
- 5. There is little negative environmental and social impact.
- 6. In addition to the necessity and superiority of using bridge construction technology of Japan, Japanese grant aid system allows the project to be implemented without any difficulty.

2) Effectiveness

a) Quantitative Effect

There is a high possibility of interruption of bridge service and closure of the connected road due to inundation and also scouring and erosion of approach road due to the progressive erosion of riverbanks in the upstream as well as potential change in river course. However, by implementation of this project, the risk of inundation will be highly reduced by raising the road elevation, and also the river course will be stabilized by river works and erosion prevention countermeasures.

The expected quantitative effect of the project implementation is shown in Table-2. The base value was measured in 2018 and the target value is set for three years after project completion.

Items	Base Value (FY2018 Actual)	Target Value (3 yrs after completion)
Traffic Volume (Unit/day)	2,980	3,600
Number of Passengers (person/day)	755	905
Weight of Cargo (ton/year)	60,000	72,000

 Table-2
 The Quantitative Effects Expected from the Implementation of the Projects

b) Qualitative effect

The qualitative effects of the project are:

- 1. Maintenance of economic activities and access to various services are ensured by eliminating the blockage of logistics and commuting due to flooding after heavy rain.
- 2. By changing from emergency rehabilitation to permanent restoration, there is no fear of a falling bridge and the toughness of the bridge is secured.
- 3. River erosion to private land on the upper right bank can be avoided.

Table of Contents

Preface Summary Contents


Location Map /	Perspective	
	Tow Dimensional Flood Simulation	
List of Figures		
Abbreviations		
CHAPTER 1	Basic Concept of the Project	1-1
	ne	
1.2 Natur	al Condition	1-1
1.2.1 C	limate and Hydrology	1-1
1.2.2 T	opography and Geology	1-5
1.2.2.1		
1.2.2.2	Geological Survey (Boring Survey)	1-9
1.2.2.3	Geological Survey (Material Testing)	1-13
1.3 Envir	onmental and Social Considerations	1-17
1.3.1 E	Invironmental Impact Assessment	1-17
1.3.1.1	Outline of Project Components with Socio-environmental Impacts	1-17
1.3.1.2	Current Socio-environmental Conditions	1-19
1.3.1.3	Policy, Legal, and Administrative Frameworks of Environmental and Social	
Conside	rations	1-28
1.3.1.4	Alternative Analysis including No Project (No Action)	1-37
1.3.1.5	Scoping	
1.3.1.6	ToR for Survey of Environmental and Social Considerations	1-44
1.3.1.7	Survey Result of Environmental and Social Considerations	1-46
1.3.1.8	Impact Assessment	1-60
1.3.1.9	Environmental Management Plan (Proposed Actions and Implementation Cost)	1-64
1.3.1.10	Environmental Management and Monitoring Plan (Implementation details,	
Method	ology and Cost)	1-67
1.3.1.11		
1.3.2 L	and Acquisition and Resettlement	1-75
1.3.2.1	Target Area for Action Plan	1-75
1.3.2.2	Outline of Laws and Regulations regarding Land Acquisition and Resettlement	
1.3.2.3	Practices in Resettlement and Land Acquisition	1-78
1.3.2.4	Comparison between JICA Policy and Vanuatu Resettlement Laws	1-79
1.3.2.5	Scale and Scope of Land Acquisition	1-84
1.3.2.6	Policies for Compensation and Assistance	1-90
1.3.2.7	Grievance Redress Mechanism (GRM) and Addressing Complaints	1-93
1.3.2.8	Implementation System	
1.3.2.9	Implementation Schedule	1-95
1.3.2.10	Costs Estimation	1-96
1.3.2.11		
1.3.2.12		
1.3.2.13		
	Contents of the Project	
	Concept of the Project and Design Policy	
	Basic Concept for Flood Disaster Countermeasure	
2.1.2 P	olicies for Flood Disaster Countermeasure	2-2

2.1.3 E	Design Policy of River Improvement Works				
	Policies for Utilization of Existing Teouma Bridge				
	Policies for Seismic Design Condition				
2.1.6 P	2.1.6 Policies for Bridge Planning				
2.1.7 P	Policies for Road Planning	2-23			
2.1.8 P	Policies for Procurement	2-25			
2.1.9 P	Policies for Utilization of Local Contractors	2-25			
2.1.10 P	Policies for operation and maintenance	2-25			
	ne Design of the Japanese Assistance				
2.2.1 E	Basic Plan				
2.2.1.1	Applicable Criteria				
2.2.1.2	Road Class and Specifications				
2.2.1.3	Design Speed				
2.2.1.4	Geometric Condition				
2.2.1.5	Traffic Demand Forecast				
2.2.1.6	Riverbank Protection Plan				
2.2.1.7	Bridge Plan				
2.2.1.8	Accessories of the Bridge				
2.2.1.9	Approach Road Plan				
	Dutline Design Drawing				
	mplementation Plan				
2.2.3.1	Implementation Policy				
2.2.3.2	Implementation Conditions				
2.2.3.3	Scope of Works				
2.2.3.4	Consultant Supervision				
2.2.3.5	Quality Control Plan				
2.2.3.6	Procurement Plan				
2.2.3.7	Soft Component Plan				
2.2.3.8	Implementation Schedule				
	ity Plan				
	ations of Recipient Country				
	ct Operation and Maintenance Plan				
	ct Cost Estimation				
5	nitial Cost Estimation				
	Government of Vanuatu's Contribution				
	Government of Vanuatu's Contribution				
2.6.1.3	Cost Estimation Condition				
2.6.2	Deration and Maintenance Cost				
	Project Evaluation				
	nditions				
	ssary Inputs by Recipient Country				
	rtant Assumptions				
1	ct Evaluation				
5	Relevancy				
	Effectiveness				
	Quantitative Effect				
3.4.2.2					


- [Appendices]1. Survey Team Member List2. Survey Schedule3. List of Stakeholder4. Minutes of Discussion/Meeting

- 5. Technical Note


- Outline Design Drawings
 Environment Monitoring Form
 Results of Geotechnical Investigation



LOCATION MAP



PERSPECTIVE



Target Area for Two-Dimensional Flood Simulation

List of Figures

Figure 1.2-1	Flood Hydrographs for Different Return Period at Teouma Bridge	1-4
Figure 1.2-2	Longitudinal Water Level Profile for Different Flood Return Periods	
Figure 1.2-3	Outline of Survey Results around Teouma Bridge	1-7
Figure 1.2-4	Location of Boring Survey Sites	1-9
Figure 1.2-5	Equipment used for boring survey	. 1-10
Figure 1.2-6	Boring logs of BH-1 to 4	. 1-12
Figure 1.2-7	Locations of CBR test samples around Teouma bridge	. 1-14
Figure 1.2-8	Location of Quarry	
Figure 1.3-1	Scope of Environmental Impact Assessment	. 1-18
Figure 1.3-2	Central Efate Forest Conservation Area	. 1-20
Figure 1.3-3	EIA Approval Process	. 1-34
Figure 1.3-4	Locations of Sampling Points	. 1-48
Figure 1.3-5	Location of Noise Level Measurement	
Figure 1.3-6	Location of sensitive facilities such as schools around the project area	. 1-51
Figure 1.3-7	Drainage Systems along the Flood-proofing Road	
Figure 1.3-8	Locations of Teouma Bridge, Stockyard, and Bouffa Landfill sites	
Figure 1.3-9	Location of Project Components	. 1-76
Figure 1.3-10	Location and Area of land necessary to acquire	. 1-86
Figure 2.1-1	Results of Flooding Simulation during Cyclone Pam	2-3
Figure 2.1-2	Changes of Hydraulics Parameters in River Widening	2-5
Figure 2.1-3	Flood Disaster Mitigation Alternatives and Longitudinal Profiles	2-6
Figure 2.1-4	Result of Flooding Simulation by Alternatives in 50-year return period flood	
Figure 2.1-5	Result of Flooding Simulation by Alternatives in 100-year Return Period Flood	2-9
Figure 2.1-6	Longitudinal Profile of Deepest Riverbed at Bend upstream of Teouma Bridge	. 2-11
Figure 2.1-7	River Cross-sectional Survey Location at Bend upstream of Teouma Bridge	. 2-11
Figure 2.1-8	Relation between Hmax/Hm and r/B at Bend	. 2-12
Figure 2.1-9	Relation between Fr, ho/dm and Z/D for Prediction of Scouring Depth	. 2-13
Figure 2.1-10	Teouma Bridge Damaged by Cyclone Pam	
Figure 2.1-11	Proposed Typical Cross Section of River Channel (at Bridge)	. 2-16
Figure 2.1-12	Types of Slope Protection	. 2-18
Figure 2.1-13	Comparison of Earthquake Response Spectra	. 2-21
Figure 2.1-14	Seal Pavement Structure	. 2-25
Figure 2.2-1	Survey Locations	. 2-29
Figure 2.2-2	Traffic Volume by Vehicle Type	. 2-30
Figure 2.2-3	Result of Roadside OD Interview Survey (Purpose of the Trip)	
Figure 2.2-4	Result of Roadside OD Interview Survey (Departure and Destination)	. 2-32
Figure 2.2-5	Determination of Bridge Length	. 2-38
Figure 2.2-6	Comparison of Live Load Strength	. 2-39
Figure 2.2-7	Geological Profile and Soil Model	. 2-42
Figure 2.2-8	Typical Cross Section of Approach Road	. 2-45
Figure 2.2-9	Photo of Local Concrete Plant and Quarry	. 2-55
Figure 2.2-10		
Figure 2.5-1	Organization of MIPU	. 2-59
Figure 2.5-2	Organization of PWD	. 2-59
-		

List of Tables

Table 1.2-1	Monthly Average of Major Climate Indicators of Port Vila	. 1-2
Table 1.2-2	Daily Rainfall Observed during Cyclone Pam	. 1-3
Table 1.2-3	Computation of Probable Daily Rainfall	. 1-3
Table 1.2-4	Probable Flood Discharges at Teouma Bridge	. 1-3
Table 1.2-5	Harmonic Analysis Results on Tidal Data at Port Vila	. 1-4
Table 1.2-6	Coordinates, elevation and drilling depth of each boring survey sites	. 1-9
Table 1.2-7	Boring Survey Equipment	
Table 1.2-8	Material test items at each laboratory	1-13
Table 1.2-9	Test results at the Japan Road Contractors Association Road Test Laboratory	1-13
Table 1.2-10	Test results at Material Laboratory of PWD	
Table 1.2-11	Classification based on compressive strength of Rubble (JIS5006)	1-14
Table 1.2-12	Result of Hydration Tests	
Table 1.2-13	Compaction Tests	1-16
Table 1.2-14	Result of CBR test / Atterberg's limit test	1-17
Table 1.3-1	Terrestrial Flora (Along the Ridge and Cliff of the Teouma-Etas Escarpment)	1-20
Table 1.3-2	Terrestrial Flora (Secondary Forest on Alluvial Soil)	1-21
Table 1.3-3	Freshwater Fauna	1-21
Table 1.3-4	Terrestrial Fauna	1-22
Table 1.3-5	Main source of income by region: Number of households and percentage	1-24
Table 1.3-6	Household Well-being Indicators	
Table 1.3-7	Main source of drinking water (Number of households and percentage)	1-25
Table 1.3-8	Household by alternative source of drinking water by region (only private houses)	1-26
Table 1.3-9	Reported HIV cases by province, 2015	
Table 1.3-10	STI situation	
Table 1.3-11	Comparison between JICA Guidelines and EIA Related Laws/Regulations	1-34
Table 1.3-12	Result of Scoping	
Table 1.3-13	ToR of survey of Environmental and Social Considerations	1-44
Table 1.3-14	Result of Baseline Survey	1-47
Table 1.3-15	Expected Noise Level	
Table 1.3-16	Construction Machinery Schedule	
Table 1.3-17	Result of Impact Assessment	
Table 1.3-18	Proposed Actions and Implantation Cost	
Table 1.3-19	Environmental Management and Monitoring Plan (EMMP)	
Table 1.3-20	Stakeholder Consultation Meeting	
Table 1.3-21	Questions and Answers	1-70
Table 1.3-22	Preparatory Stakeholder Inception Meeting	1-71
Table 1.3-23	Questions and Answers	1-72
Table 1.3-24	Public Consultation of the Environment & Social Impact Assessment (ESIA)	1-73
Table 1.3-25	Questions and Answers	
Table 1.3-26	Public Consultation of the Environment & Social Impact Assessment (ESIA)	1-74
Table 1.3-27	Questions and Answers	
Table 1.3-28	Comparison result of JICA Guidelines and Vanuatu Related Laws	1-80
Table 1.3-29	List of Affected Household and Population	
Table 1.3-30	Affected Land	
Table 1.3-31	Affected Structures	
Table 1.3-32	Affected Agricultural Products/ Trees/ Cattle	
Table 1.3-33	Age Composition of Household Heads	1-87
Table 1.3-34	Educational Background of Household Heads	
Table 1.3-35	Occupation of Household Heads	
Table 1.3-36	Household Size	

Table 1.3-37	Age Composition of Household Members	. 1-89
Table 1.3-38	Educational Background of Members	. 1-89
Table 1.3-39	Occupation of Household Members	. 1-90
Table 1.3-40	Household Income	. 1-90
Table 1.3-41	Draft Entitlement Matrix	. 1-92
Table 1.3-42	RAP Implementation Schedule	. 1-96
Table 1.3-43	Cost Estimation for RAP Implementation	. 1-96
Table 1.3-44	Internal Monitoring Indicators	. 1-98
Table 1.3-45	External Monitoring Indicators	. 1-99
Table 1.3-46	Outlines and Opinions/Attitude from Participants in each Consultation	1-100
Table 2.1-1	Hydrological Parameters for Design	2-1
Table 2.1-2	Results of Hydraulics Analysis for Channel Widening	2-4
Table 2.1-3	Comparative Study on Hydraulics Parameters of the Alternatives	2-6
Table 2.1-4	Overall Comparative Study Results of the Flood Disaster Mitigation Alternatives	. 2-10
Table 2.1-5	Changes of Hydraulics Analysis Results Considering Climate Change	
Table 2.1-6	Bank Sections to be Covered with Revetment	. 2-17
Table 2.1-7	Comparison of Slope Protection	. 2-19
Table 2.2-1	Overall Project Plan	. 2-26
Table 2.2-2	Traffic Classes	
Table 2.2-3	Design Speed	. 2-27
Table 2.2-4	Geometric Condition for Road and Bridge in Vanuatu	. 2-28
Table 2.2-5	Outline of the Traffic Survey	
Table 2.2-6	Result of Traffic Count Survey	
Table 2.2-7	Result of Traffic Count Survey (Pedestrian)	
Table 2.2-8	Result of Roadside OD Interview Survey	
Table 2.2-9	Outline of Axle Load Survey	
Table 2.2-10	Load Regulation for Road of Vanuatu	
Table 2.2-11	Number of Overloaded Truck and Its Rate	
Table 2.2-12	Traffic Demand Forecast	
Table 2.2-13	Design Top Elevation of Riverbanks	. 2-34
Table 2.2-14	Comparative Study for Bridge Location	
Table 2.2-15	Comparative Study on Superstructure Type	
Table 2.2-16	Comparative Study on Bridge Pier Type	
Table 2.2-17	Comparative Study for Pile Type	
Table 2.2-18	Daily Traffic Volume in 2031	. 2-45
Table 2.2-19	ESAL Conversion Factor by Vehicle Type	. 2-46
Table 2.2-20	Estimated ESAL Value from Year 2022 to Year 2031	
Table 2.2-21	Table of Contents of Drawings of Outline Design	. 2-47
Table 2.2-22	Responsibility of Each Government	. 2-50
Table 2.2-23	Quality Control Plan for Superstructure Works	. 2-52
Table 2.2-24	Quality Control Plan for Rotating Pile (Spiral Steel Pipe Pile) Works	. 2-53
Table 2.2-25	Quality Control Plan for Concrete Works	. 2-53
Table 2.2-26	List of Main Procurement Construction Materials	. 2-54
Table 2.2-27	List of Procurement Construction Equipment	. 2-56
Table 2.6-1	Approximate Cost Estimate of Vanuatu Contribution	
Table 2.6-2	Main Maintenance Items and Annual Cost	
Table 3.4-1	The Quantitative Effects Expected from the Implementation of the Projects	3-2

Abbreviations

AADT	:	Annual Average Daily Traffic
AASHTO	:	American Association of State Highway and Transportation Officials
ADB	:	Asian Development Bank
ARAP	:	Abbreviated Resettlement Action Plan
D/D	:	Detailed Design
EIA	:	Environmental Impact Assessment
E/N	:	Exchange of Notes
ESAL	:	Equivalent Single Axle Loadings
G/A	:	Grant Agreement
GDP	:	Gross Domestic Product
IEE	:	Initial Environmental Examination
IOL	:	Inventory of Loss
JICA	:	Japan International Cooperation Agency
JRA	:	Japan Road Association
MIPU	:	Ministry of Infrastructure and Public Utilities
PAPs	:	Project Affected Persons
PWD	:	Public Works Department
RAP	:	Resettlement Action Plan
ROW	:	Right of Way
VRRM	:	Vanuatu Resilient Road Manual
WB	:	World Bank

CHAPTER 1 Basic Concept of the Project

1.1 Outline

Most of the residents of Efate Island where the capital of the Republic of Vanuatu is located live along the Ring Road. The Ring Road plays an important role for inland transportation. Teouma Bridge has been constructed on the Teouma River which is the largest river in the island. It is located at the entrance to the capital from the eastern part of the island.

The bridge was completely destroyed by an earthquake of magnitude M7.2. In response, the bridge was reconstructed by the Japan's Grant Aid Program "The Project for Rehabilitation of Bridges on the Ring Road in the Efate Island in the Republic of Vanuatu" in 2003.

However, the rehabilitated Teouma Bridge had been blocked for six days due to the damage of the approach road on right bank by Cyclone Pam in 2015. The damage was caused by the changing of river course. The bridge has been temporarily rehabilitated and it is at the risk of being destroyed and blocked by another sever flood.

Under this circumstance, JICA conducted a data collection survey in 2016 to investigate and confirm the direction of the bridge rehabilitation. It has been proposed to implement three types of works, which are 1) Stabilization of the river course; 2) Extension of bridge to increase flow capacity; 3) Overflow approach road.

Based on the results of this survey, the Vanuatu government requested a full-scale reconstruction work for Teouma Bridge to the Government of Japan.

1.2 Natural Condition

1.2.1 Climate and Hydrology

(1) Climate

Vanuatu has tropical marine climate with uniform temperature, high humidity and large amount of rainfall. Wind speed is generally moderate (9.3 km/hr to 18.5 km/hr) except during tropical storms.

The climate of Vanuatu could be categorized in two distinct seasons according to the Vanuatu Meteorology & Geo-Hazards Department (VMGD), Ministry of Infrastructure and Public Utilities (MIPU): One is cold (dry) season from May to October and the other one is hot (wet/cyclone) season for the rest of year. Generally speaking, the highest temperature is observed in February and the lowest one in August. The annual average temperature in Port Vila is at about 25°C, ranging from average monthly high temperature of 27°C in February and average monthly lowest temperature in August at about 23°C.

Rainfall in Vanuatu is highly affected by monsoon and varies from southeast to northwest of the island. The predominant southeast wind-flow is often moisture saturated and contributes to an extremely variable rainfall pattern. More rainfall is observed in the southeast of the islands due to winds direction compared to the northwest of the island. Rainfall in Efate Island shows this particular pattern very well. In the coming wind direction, annual rainfall ranges from 2,400 mm to 3,000 mm. However. it is almost half

on the other side. Heavier rainfall is observed during La Niña years in the South Pacific Convergence Zone (SPCZ). Higher rainfall is usually observed from January to March. Flood occurs frequently during the cyclones or La Niña season at the lowland areas close to rivers. Heavy rainfall during La Nina sometimes causes severe damage to crops and farmlands.

Vanuatu is frequently hit by cyclones which is categorized as storm with the wind speed of over 63.0 km/hr (or 34 knots). Three cyclones hit Vanuatu every year on average.

Lower rainfall and drought is very much related to El Niño Southern Oscillation (ENSO). Average annual rainfall during El Niño with negative Southern Oscillation Index (SOI) is less than half of the normal year. Last drought conditions have been observed in 1982/83, 1994/95, and 1997/98. Drought damage is normally severely occurred in rain shadow areas.

Major monthly climate indexes of Port Vila are shown in Table 1.2-1.

Table	1.4-1	Monu		age o	i maju		ate mu	icators	01101	t v na		
Month	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Season		Ra	iny					Dry				Rainy
Rainfall (mm)	270	293	323	215	168	161	92	86	90	104	135	191
Min Temperature (°C)	22	22	22	22	20	19	18	17	18	18	20	21
Max Temperature (°C)	31	31	30	29	28	27	26	26	27	28	30	30
Sunshine Hour (hr)	198	172	176	173	169	139	159	180	182	208	200	196
Relative Humidity (%)	84	84	87	87	85	86	85	81	82	82	83	82

Table 1.2-1 Monthly Average of Major Climate Indicators of Port Vila

Source: Vanuatu Meteorology and Geo-Hazard Department

(2) Rainfall during Cyclone Pam and Computation of daily Rainfall Return Period

1) Rainfall Stations

The survey team collected a report of "Cyclone Dani Rehabilitation Project, Rainfall Analysis, January 2000" including historical rainfall data before 2000. As a result, daily rainfall time series of the following two stations were collected:

- Station 1: Port Vila established in 1948 with 68 years observation period, 6 years missing data, 33 years consecutive record
- Station 2: Bauerfield established in 1986 with 30 years observation period

2) Filling of Missing Data

In the time series of daily rainfall data of Bauerfield, the most critical data during Cyclone Pam was missing due to harsh climate condition and difficulties of reading hydro-meteorological parameters. Only data for three days rainfall were available in this station. However, Port Vila station, fortunately, has complete daily rainfall observation during Cyclone Pam as shown in Table 1.2-2. Therefore, missing daily rainfall data of Bauerfield station could be estimated during Cyclone Pam using Port Vila station data by a ratio of daily rainfall in 4 days. The allotment ratios are 0.814 (514 mm) on 13th, 0.185 (117 mm) on 14th, 0.001 (1 mm) on 15th, March 2015, respectively.

Date in March, 2015	Bauerfield	Port Vila
13	48 mm	388.5 mm
14	-	88.1 mm
15	-	0.4 mm
16	584 mm	0.0 mm
Total	632 mm	477.0 mm

 Table 1.2-2
 Daily Rainfall Observed during Cyclone Pam

Source: Vanuatu Meteorology and Geo-Hazard Department

3) Daily Rainfall Return Period

Daily rainfall data of Bauerfield and Port Vila stations as well as a few observations of Mt. Macdonald station located in the upstream of river basin have been studied. As a result, rainfall data observed at Bauerfield station is considered a better representative for spatial rainfall of Teouma river basin. Log-Pearson Type 3 has been fitted to 30 years observed data of Bauerfield station in order to estimate daily rainfall for different return period. The result is shown in Table 1.2-3.

_	•
Recurrence Period (Year)	Probable Daily Rainfall (mm)
2	167.9
5	261.9
10	338.3
20	423.4
50	553.0
100	666.4

 Table 1.2-3
 Computation of Probable Daily Rainfall

Source: JICA Survey Team

As described in section (2) above, maximum daily rainfall of 514 mm has been recorded on March 13 in 2015, during Cyclone Pam. This amount of rainfall is almost equal to daily rainfall with 50 years return period.

4) Flood Return Period and Flooding Situations during Cyclone Pam


Flood hydrographs at Teouma Bridge are developed using Muskingum Routing and river discharge is estimated by SCS (Soil Conservation Service, US) Unit Hydrograph method. The maximum daily floods for different return periods at Teouma Bridge are presented in Table 1.2-4 and Figure 1.2-1.

According to the interview survey on flooding during Cyclone Pam, maximum flood level was near road surface at Teouma Bridge, which was equivalent to about 7.6 m above MSL. Flood water extended widely over the left bank along the Ring Road.

		bischarges at reoun	la Dilage
Recurrence Period (Year)	Probable Daily Rainfall (mm)	Probable Flood Peak (m ³ /s)	Runoff Ratio
2	167.9	20	0.044
5	261.9	120	0.165
10	338.3	250	0.258
20	423.4	420	0.350
50	553.0	720	0.464
100	666.4	1020	0.544

 Table 1.2-4
 Probable Flood Discharges at Teouma Bridge

Source: JICA Survey Team



Source: JICA Survey Team

Figure 1.2-1 Flood Hydrographs for Different Return Period at Teouma Bridge

(3) Tidal Conditions at Teouma River Mouth

The following tidal information in Table 1.2-5 was obtained through the harmonic analysis using observed data by tidal recorder at Port Vila with reference to "Basic Design Study Report on the Project for Improvement of Port Vila Main Wharf in Public of Vanuatu, 2017, JICA". In this study, Highest High Water Level of +0.7 m above MSL (1.58 m) is adopted for an initial condition in hydraulic analysis.


Anharmonic Constant	Height above Base Level (m)	Height above Mean Sea Level (m)
Nearly Highest High Water Level	1.58	+0.7
High Water Level Ordinary Spring Tide	1.33	+0.4
Mean Sea Level	0.88	0.0
Low Water Level Ordinary Spring Tide	0.44	-0.4
Nearly Lowest Low Water Level	0.19	-0.7
Base Level	0.00	-0.9

 Table 1.2-5
 Harmonic Analysis Results on Tidal Data at Port Vila

Source: Basic Design Study Report on the Project for Improvement of Port Vila Main Wharf in Public of Vanuatu, 2007, JICA

(4) Flood Profile and River Channel Carrying Capacity

Non-uniform flood profiles have been developed for different return period of flood using river cross-sections and examining of river channel carrying capacity. Initial water level at river-mouth is set at +0.7m above MSL and roughness coefficient of river channel is set at 0.035. Simulation results are shown in Figure 1.2-2 and the followings are summary of particular features of flood carrying capacity of Teouma River.



Source: JICA Survey Team

Figure 1.2-2 Longitudinal Water Level Profile for Different Flood Return Periods

$1) \ Downstream \ of \ the \ Teouma \ Bridge$

Baneful discharge is a little less than 100 m³/s equivalent to 5-year return period flood (120 m³/s) or less.

2) Teouma Bridge Section

Since Teouma Bridge forms a man-made constriction, relatively rapid flow velocity and lowering of flood water level occurs at the bridge section. Further it accelerates water level rising in the upstream for a long distance in upstream.

3) Upstream of the Teouma Bridge

The flood carrying capacities in the upstream range from $120 \text{ to } 250 \text{ m}^3/\text{s}$ (5- to 10-year return period), excluding unstable segment of flood water level rising immediately upstream of the bridge due to constriction of the channel.

This shows any flood exceeding 10-year return period will cause flooding in the upstream of the bridge and inundation of Ring Road. The situation is even worse downstream as any flood exceeding 5-year return period could cause inundation of Ring Road.

1.2.2 Topography and Geology

1.2.2.1 Topographical Survey

The scope and details of conducted topographical survey are as follow:


(1) **River Survey**

- Benchmark installation: 2 points (TBM1 on the right bank side, TBM2 on the left bank side)
- Longitudinal survey: 1 section from 1,600m upstream of the bridge to 4,940m downstream of the bridge for a total of 6,540m.
- Cross-section survey: 32 cross-sections with 200m interval and 100 m width

(2) Floodplain Survey

- Benchmark installation: 2 points (TBM1 at the start point and TBM2 at the end point)
- Reference point installation: 6 points (POLY1 to POLY6)
- Longitudinal survey: 1 section from 320m upstream of bridge to 300m downstream of bridge for total 620m
- River cross-sections: 17 cross-sections with 40m interval and 100m width
- Road centerline survey: 1 survey line for 420m from each side of bridge, total of 840m, 20m interval
- Road longitudinal survey: 1 section for 420m from each side of bridge, total of 840m, 20m interval)

The outline of surveying points is shown in the following Figure 1.2-3.



Source: JICA Survey Team

Figure 1.2-3 Outline of Survey Results around Teouma Bridge

(3) Photos



Source: JICA Survey Team

1.2.2.2 Geological Survey (Boring Survey)

(1) Survey Location

Boring survey was conducted at four points (BH - 1 to 4) in order to grasp the ground conditions of target bridge and revetment works. Locations of boring survey sites are shown in Figure 1.2-4 and Table 1.2-6 below.



Source: JICA Survey Team

Figure 1.2-4 Location of Boring Survey Sites

ID		dinates nd longitude)	Elevation	Drilling depth
	Latitude(°)	Longitude(°)	(m)	(m)
BH-1	-17.76678	-168.38239	5.80	45.45
BH-2	-17.76670	-168.38258	5.80	37.50
BH-3	-17.76645	-168.38284	6.00	45.45
BH-4	-17.76600	-168.38226	5.50	20.00

Table 1.2-6 Coordinates, elevation and drilling depth of each boring survey sit

Source: JICA Survey Team

(2) Equipment

The equipment shown in Table 1.2-7 is used for the boring survey.

Tuske 1.2-7 Doring Survey Equipment					
Item	Specifications				
Drilling Machine	Trailer mounted drilling machine (Rotary type)				
Hole size	φ=86mm				
Sampler	High Quality triple tube sampler				
_	Raymond-type spoon sampler				

Table 1.2-7	Boring Survey	^v Equipment
--------------------	---------------	------------------------

Source: JICA Survey Team



Source: JICA Survey Team



(3) Photos






Source: JICA Survey Team

(4) Result of Boring Survey

The boring survey of BH-1 to BH-4 was conducted from May to June 2018. The maximum depth of drilling was -45.45m. Standard Penetration Tests (SPTs) are conducted every 1.5m. The boring logs are shown in Figure 1.2-6. No rock stratum has been found in the drilling survey.

	BH-1			2018/6/1	BI	H-2			2018/5/31		BH-3			2018/6/1	E	BH-4				2018/6/
EL(m)	Depth	SPT N-	Graphic	Sall Description	De	epth N-	Graphi	Soll D	escription		Depth	SPT N-	Graphic	Soil Description	[Depth	SPT N-	Graphic	Sall D	escription
EL(m)	(m)	Value	Log	Soil Description	(1	m) Value	Log	5011 Di	escription		(m)	Value	Log	Soil Description		(m)	Value	Log	5011 De	escription
7																				
6			EL=5.8m				EL=5.8						EL=6.0m							
5	0	-		Core Loss Colluvium		0 -	-	Core Loss Core Loss			0	-	-	Core Loss Core Loss		0		EL=5.5m	Core loss	
5	1	-		Silt		1 -		Core Loss			1	-		Core Loss			-		Core loss	
4	2	4		Sand Sand		- 2 -	-	Core Loss Core Loss			2	3	_	Core Loss Core Loss		1	-		Sand Sand	Organic
3		-		Core Loss		-		Core Loss				-		Core Loss		2	-	1999. 1999	Core loss	
2	3	6 -		Sand Core Loss		3 2		Silt Core Loss			3	2		Core Loss Core Loss		3	- 1		Sand Sand	
1	4			Sand		4 -		Silt Sand+Gravel			4			Core Loss		4			Sand Sand+Gravel	
1	5	-		Sand+Gravel Sand		9 5 -		Sand+Gravel			5	-		Core Loss Core Loss		4	1		Sand+Gravel	
0		- 10	sticetteda	Sand+Gravel Sand				Sand+Gravel Sand+Gravel				- 15		Core Loss Sand Organic		5			Core loss Core loss	
-1	6	-		Sand		6 9 -	-	Sand+Gravel			6	- 15	********	Sand Organic Core Loss		6	17		Sand	Organic
-2	7	- 9		Sand		7 - 5		Sand+Gravel Silt			7	12		Silt Organic Silt		7			Core loss Silt	
-2	8	-		Sand		8 -		Silt			8	12	-	Core Loss		·'	7		Sand	Wood/Shell
-3	9	- 7		Sand		- 9 19		Sand Sand			9	- 17		Core Loss Sand		8	-		Sand Sand	Wood/Shell Wood/Shell
-4		-		Sand		-		Sand				-		Core Loss		9	11		Sand	Wood/Shell
-5	10	- 17		Sand		10 - 16	-	Sand Sand			10	- 6		Sand Organic		10	-		Sand Sand	Wood/Shell Wood/Shell
	11	-	+	Sand Sand		11 -		Sand			11	-		Core Loss			7		Sand	Wood/Shell
-6	12	- 15		Sand		- 12 9		Sand Sand			12	- 17		Sand		11			Silt Silt	Shell
-7		-		Sand		-		Sand				-		Sand		12	1		Silt	Shell
-8	13	- 15		Sand		13 -	_	Sand Sand			13	- 12	-	Sand Sand		13	-		Silt Silt	Shell
	14	-		Sand		14 -		Sand	Organic/Shell		14			Silt Organic/Shell			1		Silt	Shell
-9	15	- 14		Sand		- 15 10	-	Sand Sand	Organic/Shell Organic/Shell		15			Silt Organic/Shell Silt Organic/Shell		14	-		Core loss Silt	Organic
-10				Silt Wood			-	Silt	Organic/Shell			-		Silt Organic/Shell		15	7		Silt	Organic/Shell
-11	16	- 10		Silt Organic/Shell Silt Organic/Shell		16 - 4		Silt Silt	Organic Organic		16	- 0		Silt Organic/Shell Silt Organic/Shell		16	-		Core loss Silt	Organic/Shell
10	17	-		Silt Organic/Shell Silt Organic/Shell		17 -		Core Loss Silt			17	-		Silt Organic/Shell Silt Organic/Shell		17	8		Silt	Organic/Shell
-12	18	- 1		Silt Organic/Shell Silt Organic/Shell		- 18 4		Silt			18	- 0		Silt Organic/Shell Silt Organic/Shell		17	-		Sand Silt	Organic/Shell
-13	19	-		Silt Organic/Shell Silt Organic/Shell		- 19 -		Core Loss			19	-		Silt Organic/Shell Silt Organic/Shell		18	0		Silt	Organic/Shell
-14	19	6		Silt Organic/Shell Silt Organic/Shell		19 -		Core Loss Silt	Organic/Shell		19	0		Silt Organic/Shell Silt Organic/Shell		19	-		Core loss Silt	Organic
-15	20	-		Core Loss Silt Organic/Shell		20 -	_	Silt Silt	Organic/Shell Organic/Shell		20	-		Silt Organic/Shell Silt Organic/Shell		20	2		Silt	Shell
-15	21			Core Loss		21 0	-	Silt	Organic/Shell		21	8		Silt Organic/Shell		20				
-16	22	-		Silt Organic/Shell Silt Organic		- 22 -		Silt Core Loss	Organic/Shell		22	-		Silt Organic/Shell Silt Organic/Shell						
-17	22	1		Silt		4		Silt	Organic		22			Sand Organic/Shell						
-18	23	-		Core Loss Silt		23 -		Silt Silt	Organic Organic		23	-		Sand Organic/Shell Sand Organic/Shell						
	24			Silt Wood		24 5		Core Loss			24	4		Sand Organic/Shell						
-19	25	-		Silt		- 25 -		Core Loss Silt			25	-		Sand Organic/Shell Sand Organic/Shell						
-20		21		Sand		6		Sillen				2		Sand Organic/Shell						
-21	26	-		Sand Sand		26 -	-	Sand Sand	Shell		26	-	-	Core Loss Core Loss				Legend		
	27	29		Sand		27 21		Sand	Shell		27	11		Sand Shell					Core loss	
-22	28	-		Sand		- 28 -		Sand Sand	Shell		28	-		Sand Shell Sand Shell					Colluvium Sand+Grav	el
-23		12		Sand		23		Sand	Shell			19		Sand Shell					Sand	
-24	29	-		Sand Sand		29 -		Sand Sand	Shell		29	-		Sand Shell Sand Shell					Sand Silt	Wood/Organic
25	30	12		Sand		30 17		Sand	Shell		30	11		Sand Shell					Silt	Wood/Organic
-25	31			Sand Sand		31 -	-	Silt	<u> </u>		31			Sand Shell Sand Shell					Goundwate	i ievel
-26	32	- 12		Sand Sand		17 32 -		Sand Sand			32	0		Sand Shell Core Loss						
-27		-		Sand		-		Core Loss				-		Core Loss						
-28	33	7		Sand Sand		33 -		Sand Sand	Shell		33	- 11		Sand Organic/Shell Sand Organic/Shell						
	34			Sand		34 -		Core Loss			34	-		Sand Organic/Shell						
-29	35	- 22		Sand Shell Sand Shell		- 35 -		Sand Sand			35	- 13		Sand Wood Sand Shell						
-30		-		Sand Sand		-		Core Loss		ļ				Sand Shell Sand Shell						
-31	36	- 18		Sand		36 -		Core Loss Sand	Wood		36	- 18		Sand Shell Sand Shell						
	37	-		Sand		37		-			37	-		Sand Shell						
-32	38	1		Sand Sand		38					38	- 16		Sand Shell Sand Shell						
-33		-		Sand								-		Sand Shell						
-34	39	- 12		Sand Sand							39	- 10		Sand Shell Silt Wood						
	40			Sand							40			Silt Wood						
-35	41	-		Sand Sand			-+				41	- 23		Silt Wood Silt Wood						
-36		-		Sand								-		Silt Wood						
-37	42	-		Sand Shell Sand Shell							42	- 21		Sand Shell Sand Shell						
-38	43	- 15		Sand Shell							43			Sand Shell						
	44			Sand Shell Sand Shell							44	- 10		Sand Shell Sand Shell						
-39	45	-		Sand Shell Sand Shell								-		Sand Shell Sand Shell						
		12	00000000000000	Janu Shell						1	45	9	10000000	Sand Shell						

Source: JICA Survey Team



1.2.2.3 Geological Survey (Material Testing)

(1) Laboratory Tests

All tests were conducted at Material Laboratory under Public Works Department, Ministry of Infrastructure and Public Utilities, Port Vila. A few tests were conducted at the Japan Road Contractors Association Road Test Laboratory as the tests could not be conducted at PWD material laboratory. The test items are shown in Table 1.2-8.

Tuble 112 0 Muterial test frems at each hubblatory				
Material Laboratory of PWD	Road Test Laboratory in Japan			
Bulk Density of Aggregate	Sieving test of aggregate			
Aggregate PSD	Organic impurity test of aggregate			
Flakiness Index	Stability test of aggregate with sodium sulfate			
Particle Density and Water Absorption	Alkali silica reactivity test of aggregate			
	(chemical method)			
Los Angeles Value	Aggregate sieving test			
Atterberg Limits	Organic impurity test of fine aggregate			
Particle Size Distribution	Stability test of aggregate with sodium sulfate			
Moisture Content	Chloride content test			
	Apparent specific gravity test			
	Water absorption test			
	Compressive strength test			

	Table 1.2-8	Material test items at each laboratory	
--	-------------	--	--

Source: JICA Survey Team

Results of the material tests are summarized in the following Table 1.2-9, Table 1.2-10 and Table 1.2-11.

Table 1.2-9	Test results at the Japan Road Contractors Association Road Test Laboratory
--------------------	---

	-	•
Coarse	Sieving test of aggregate	Loss mass fraction 0.4% (Less than 12%)
aggregate	Alkali silica reactivity test of	Harmless
	aggregate (chemical method)	
	Silt content	0.9% (Less than 1%)
	Organic impurity test	Colorless
Fine	Sieving test of aggregate	Loss mass fraction 0.9% (Less than 10%)
aggregate	Silt content	18.9% (Less than 5%)
	Organic impurity test	Colorless
	Chloride test	0.001%
Rubble	Apparent specific gravity test	2.293 g/cm ³ (Semi-hard stone)
(Semi-hard	Water absorption test	1.553 % (Hard stone)
stone)	Compressive strength test	2,908 N/cm ² (Semi-hard stone)

Source: JICA Survey Team

Table 1.2-10	Test results at Material Laboratory of PWD	

Coarse	Apparent specific gravity test	$2.43 (g/cm^3)$
aggregate	Water absorption test	6.0% (Less than 3.0%)
	Wear test	33% (Less than 30% : Asphalt)

Source: JICA Survey Team

Туре	Compressive Strength N/cm ²	Reference value	
		Water absorption rate	Apparent specific gravity (g/cm ³)
Hard Stone	More than 4903.3	Less than 5%	About 2.7 - 2.5
Semi-Hard Stone	Less than 4903.3	More than 5%	About 2.5 - 2.0
	More than 980.66	Less than 10%	
Soft stone	Less than 980.66	More than 10%	Less than 2.0

 Table 1.2-11
 Classification based on compressive strength of Rubble (JIS5006)


Source: JIS5006

(2) California Bearing Ratio (CBR) Test

CBR tests were carried out for seven samples in total, 3 base courses around the Teouma Bridge and 4 samples obtained from the neighboring quarry. At the same time, 45 samples from boring survey were tested for moisture content.

1) Location of Samples

7 samples in total: 3 base courses along the Efate Ring Road around the Teouma Bridge and 4 other samples from the quarry located 1.8km east of the Teouma Bridge. These locations are shown in Figure 1.2-7 and Figure 1.2-8.




Source: JICA Survey Team

Figure 1.2-7 Locations of CBR test samples around Teouma bridge



画像 ©2018 CNES / Airbus、地図データ ©2018 Google 200 m 🗆

Source: JICA Survey Team





Source: JICA Survey Team

3) Results

a) Hydration Tests

Results of the moisture content tests are shown in Table 1.2-12 below.

	Table 1.2-12 Result of Hydration Tests						
ID	Sample location	Sample Depth (m)	Moisture Content (%)	ID	Sample location	Sample Depth (m)	Moisture Content (%)
1	BH-1	0.00	47.2	27	BH-3	12.00	46.4
2	BH-1	7.95	92.5	28	BH-3	16.50	88.0
3	BH-1	9.00	49.2	29	BH-3	19.50	34.8
4	BH-1	15.45	89.0	30	BH-3	21.00	40.4
5	BH-1	16.50	66.0	31	BH-3	22.50	75.5
6	BH-1	25.50	51.5	32	BH-3	30.00	69.0
7	BH-1	24.50	64.5	33	BH-3	36.00	42.2
8	BH-1	27.45	53.0	34	BH-3	39.00	64.5
9	BH-1	30.00	64.5	35	BH-3	45.00	58.5
10	BH-1	34.50	63.0	36	BH-4	1.50	67.0
11	BH-1	39.00	67.5	37	BH-4	1.95	40.6
12	BH-1	40.50	71.0	38	BH-4	3.45	76.0
13	BH-2	3.00	76.0	39	BH-4	4.50	43.2
14	BH-2	4.95	54.0	40	BH-4	7.50	74.5
15	BH-2	7.50	72.0	41	BH-4	7.95	81.0
16	BH-2	9.45	53.5	42	BH-4	12.00	76.0
17	BH-2	10.95	62.5	43	BH-4	12.50	94.5
18	BH-2	15.45	85.0	44	BH-4	15.45	93.0
19	BH-2	19.50	74.5	45	BH-4	16.50	87.0
20	BH-2	19.95	82.0	46	CBR-1	Base course	14.3
21	BH-2	28.95	64.5	47	CBR-2	Base course	11.7
22	BH-2	30.00	66.5	48	CBR-3	Base course	10.4
23	BH-2	31.50	68.5	49	CBR-4	Base course	12.4
24	BH-3	6.00	54.0	50	CBR-5	Embankment fill	11.7
25	BH-3	7.50	60.5	51	CBR-6	Base course	10.9*
26	BH-3	10.00	39.2	52	CBR-7	Base course	11.8*

 Table 1.2-12
 Result of Hydration Tests

*Field moisture content from CBR test results

Source: JICA Survey Team

1) Compaction Tests

The results of the compaction test are shown in Table 1.2-13 below.

Table 1.2-15 Compaction Tests					
Sample	Maximum Dry Density (t/m ³)	Optimum Moisture Content (%)			
CBR-1	1.78	15.5			
CBR-2	1.97	11.5			
CBR-3	2.01	11.0			
CBR-4	1.93	15.5			
CBR-5	1.90	15.5			
CBR-6	1.96	14.0			
CBR-7	1.90	13.0			

 Table 1.2-13
 Compaction Tests

Source: JICA Survey Team

2) CBR Tests / Atterberg's Limit Tests

The results of the CBR test / Atterberg's limits test are shown in Table 1.2-14 below.

			0	
Sample	SampleCBR Value(%)		Plastic Limit	Plasticity Index
CBR-1	100	NOT Tested	NOT Tested	NOT Tested
CBR-2	110	NOT Tested	NOT Tested	NOT Tested
CBR-3	120	NOT Tested	NOT Tested	NOT Tested
CBR-4	50	NOT Obtainable	NOT Obtainable	NON-Plastic
CBR-5	50	NOT Obtainable	NOT Obtainable	NON-Plastic
CBR-6	60	NOT Obtainable	NOT Obtainable	NON-Plastic
CBR-7	160	NOT Obtainable	NOT Obtainable	NON-Plastic

Table 1.2-14	Decult of	CRP tost /	Attorborg's	limit tost
1 able 1.2-14	Result of	UDK lest /	Atterberg s	s mmit test

Source: JICA Survey Team

1.3 Environmental and Social Considerations

1.3.1 Environmental Impact Assessment

1.3.1.1 Outline of Project Components with Socio-environmental Impacts

(1) **Project Components**

Outline of project components is shown in Chapter 2. The following project components may have adverse environmental and social impacts in project area:

• River Improvement of Teouma River

Teouma River flows in wide meandering course through Rift Valley with approximately 1.5 km width between limestone terraces. The River bends sharply to the outer bank just at the upstream of the bridge, and this is the main cause of damages to the right bank abutment. The results of river hydrology and hydraulics analysis as explained in Chapter 3. It is suggested that the river width be increased from 30 m to 50 m for 100-year flood return period. Moreover, the river course should be straight around the bridge.

Teouma Bridge Replacement

The design of the new bridge is also based on 100-year flood return period. This means the existing bridge will be replaced by the new bridge with a length of 58 m, increased from 30 m at the moment. The bridge deck will be elevated from E.L. 7.7 m to E.L. 10.4 m in order to pass 100-year return period flood safely, while the width of the new bridge deck will be increased from 6.5m to 8.0 m in order to improve traffic safety.

Flood-proofing Road (Access road) Improvement

As the bridge deck has been risen from E.L.7.7 m to E.L.10.4 m, the approach road has been also risen and improved to flood-proof structure.


(2) **Project Area**

The Project area is located in the Eratap Region, Efate Island, Shefa Province. It consists of the following components: (1) Teouma Bridge, located on the Ring Road, over Teouma River, (2) Upstream

and downstream river banks from the bridge, and (3) Access road (400 m in the east and 300 m in the west side of the bridge).

(3) Area for Studying Environmental Impact Assessment

Area of the Environmental Impact Assessment is summarized in Figure 1.3-1 below. This area can be divided to two segments which would be affected by the project: (1) the construction segment including the above mentioned three components and (2) the floodplain segment in the east side of the river and downstream of the bridge.



Source: JICA Survey Team

Figure 1.3-1 Scope of Environmental Impact Assessment

Construction Area

Improvement of Teouma River

- River improvement (250 m in the upstream and 110 m in the downstream of the bridge)
 - ✓ River widening (from 30 m to 50 m)
 - ✓ River course straightening (around the bridge)
 - ✓ Riverbank protection

Replacement of the Teouma Bridge

- Replacement of the Teouma Bridge
 - \checkmark Elevation of bottom of the girder: elevated from E.L. 6.8 m to E.L. 8.9 m
 - ✓ Bridge length: from 30 m to 58 m
 - ✓ Number of spans: from 1 to 2
 - \checkmark Effective width: from 6.5 m to 9.5 m
- Construction of detour and a temporary bridge

Improvement of Flood-proofing Road (access road)

• Elevation of the road surface: from E.L. 7.7 m to E.L. 10.4 m

• Flood prevention measures: installation of drainage system (box culvert and trapezoidal drainage)

Other Areas

- Floodplain in the east side of Teouma River (elevation of the access road will increase flooding area in the north of road)
- Downstream of the construction area (the construction work could affect water quality, ecosystem, and downstream hydrology)

1.3.1.2 Current Socio-environmental Conditions

(1) Natural Conditions

1) Topography and Geology

Efate Island has a formation of raised limestone terraces and tuff rock. Teouma River has 86 km² of catchment area (at Teouma Bridge) and it is the largest catchment in Vanuatu. The river originates from McDonald Mountain at the elevation of 662 m. It meanders downstream towards the Rift Valley with width of approximately 1.5 km, sandwiched by limestone terraces.

2) Climate

Vanuatu climate is tropical marine climate with uniform temperature, high humidity and large amount of rainfall. Wind speed is moderate (9.3 km/hr to 18.5 km/hr) except during tropical storms. The climate of Vanuatu can be categorized by two seasons: cold (dry) season from May to October and hot (wet/cyclone) season for the rest of year. Temperature is rather high in February and relatively lower in August. Average annual temperature in Port Vila is at about 25°C, with average monthly maximum temperature in February is about 27°C and average monthly minimum temperature in August is about 23°C. Average annual rainfall is about 2,100 mm.

(2) Biological Conditions

The project area is located just outside of the Central Efate Forest Conservation area, as shown in the following Figure 1.3-2. The area along Teouma River is well vegetated, though modified by secondary vegetation (shrub). The diversity of freshwater fauna is low due to development activities.



Source: The World Database on Protected Areas (WDPA)

Figure 1.3-2 Central Efate Forest Conservation Area

The Terrestrial Flora survey was conducted along the Ridge and Cliff of Teouma River along with Freshwater Fauna survey inside the project area. Results of these surveys are shown in Table 1.3-1, Table 1.3-2 and Table 1.3-3 below. The survey team has not found any particular species necessary to be protected.

Species Name	Bislama Name	Native or Endemic	Introduced or Invasive
Antiaris toxicaria	Melektri	Native	
Coffa arabica	Kofi		Introduced
Hibiscus tiliaceus	Burao	Native	
Syzygium kajewskii	Wael Nakavika	Endemic	
Endospermum medulosum	Waetwud	Native cultivated	
Alangium vitiensis		Native	
Macaranga dioica	Navenu		
Veitchia montgomeryana	Pamtri	Endemic	
Ficus subcordata	Big rus Nabanga	Native	
Adenanthera pavonina	Bisa	Native	
Ficus virgata	Smol nabanga	Native	
Ventilago neocaledonica	Pen blong mat	Native	
Myristica fatua	Wael natongtong	Native	
Pangium edule	Navange	Native	
Dysoxylum amoroides	Stinkwud		
Anthocarapa nitidula		Native	
Dracontomelon vitiensis	Nakatambol	Native	
Calamus vanuatensis	Rattan	Endemic	
Chisoseton rexde	Big fruit stinkwud	Endemic	
Merremia peltata		Native	

 Table 1.3-1
 Terrestrial Flora

Source: JICA Study Team

		Secondary Forest on A	
Species Name	Bislama Name	Native or Endemic	Introduced or Invasive
Merremia peltata	Big lif rop		Invasive
Mikania micrantha	Mael minit		Invasive
Panicum maximum	Wael lemon grass		Invasive
Saccharum spp	Wael naviso	Native	
Glyricidia spp	Glyricidia		Introduced cultivated
	Elephant grass		Invasive
Pipturus argenteus	Nadamal	Native	
Trema Orientalis		Native	
Macaranga tanneries	Waet Navenu	Native	
Leucaena ieucocephala	Kasia		Invasive
Musa ssp	Banana		Introduced & cultivated
Cocos nucifera	Kokonas	Naturalised	Cultivated
Bambusa Vulgaris	Bambu	Naturalised	
Terminalia catappa	Natapoa	Native	
Ricinus communis	Kasrael		Invasive
Samonea saman	Rentri		Invasive
Ficus subcordata	Big rus Nabanga	Native	
Carica papaya	Роро		Introduced
Canarium indicum	Nangai	Naturalise	Cultivated
Cordia Alliodora	Kodia		Invasive
Casuarine equisetifolia	Oktri	Native	Cultivated
Sweetenia macrophylla			Introduced & Cultivated
Inocarpus fagifer	Namambe	Naturalised	Cultivated
Dendrocnide harveyi	Waet Nagalat	Native	
Syzygium malaccensis	Nakavika	Native	
Spondias dulcis	Naus	Native	
Tamarindus indica	Tamarin		Introduced & Cultivated.
Manihot Attillis	Maniok	Cultivated	
Zea mays	Kon	Cultivated	
Artocarpus altilis	Bredfrut	Cultivated	
Zea mays	Kon	Cultivated	
Artocarpus altilis	Bredfrut		Cultivated
Dioscorea alata	Yam	Naturalised	
Dioscorea nummularia	Wael yam	Native	
Heliconia indica	Lif Laplap	Native	
Hibiscus tiliaceus	Burao	Native	
Grewia maloccoca	Tri blong long tel	Native	1
Corida variegaa	Nasasa	Native	1
Polyscias fruticose	Nalalas	Native	
Coryline fruticosa	Nagaia	Native	

 Table 1.3-2
 Terrestrial Flora (Secondary Forest on Alluvial Soil)

Source: JICA Study Team

Table 1.3-3Freshwater Fauna

English Name	Scientific Name	Abundance
Prawn	Macrobracium formosense	15
	Caridina brevicarpalis	5

English Name	Scientific Name	Abundance
Gobie fish	Glosogobius cf celebius	7
Mosquitofish	Gambusia affinis	23
Tilapia	Mozambique tilapia	*
Gastropods	Melanopsis spp	300 +

Source: JICA study team

Birds

Literature review of terrestrial fauna was conducted for observed birds, mammals, reptiles, and amphibians in Vanuatu as shown in the following Table 1.3-4. There is no evidence of species listed in species in danger in project area and middle basin of Teouma River.

Scientific Name	Common Name	Conservation Status	Habitat
Ptilinopus tannensis	Tanna Fruit Dove	Least concern	Endemic to Vanuatu and could be observed in most islands. It inhabits old-growth rainforest, and also degraded habitats with large fruiting trees, including open woodland, parkland, plantations and gardens. It is most common in the lowlands and hills, but it is also present in mountains area up to 1,500m elevation.
Charmosyna palmarum	Green Palm Lorikeet	Vulnerable	Has a fluctuating range in the Santa Cruz Island of the Solomon Islands and also in Vanuatu. It appears to occupy high mountain altitude forest at elevations above 1,000 m, but flocks regularly descending to coastal trees, especially to feed on coconut blossoms
Aplonis zelandica rufipennis	Rusty- winged Starling	Not yet assessed	Central and North Vanuatu and Banks Group
Erythrura (cyaneovirens) regia	Royal Parrot Finch (nalaklak)		The bird is endemic to Vanuatu. It has been recorded from most islands in the archipelago but has not been observed for many years on several islands, such as Aneityum, and may be locally extinct on these. There are recent records, often of single birds, on Gaua, Espiritu Santo, Efate and Epi.
Zoesterops lateralis Ducula pacifica	Silver eye Pacific	Least concern Least concern	Bird is found in most islands of Vanuatu Bird is found in most islands of Vanuatu
	Imperial Pidgeon (Nawimba)		
Tyto alba	Wild duck Barn Owl	Least concern Least concern	This owl is found throughout Vanuatu and is not at risk of being lost as a species
Porphyrio porphyrio	Red Head	Least concern	This bird is found in most places around Efate
Rhipidura verreauxi	Vanuatu Streaked fantail	Least concern	Bird is found is most islands of Vanuatu
Tpodiramphis chloris	Collard Kingfisher	Least concern	Bird is found in most islands of Vanuatu
Gallirallus phillippensis	Buff Banded Rail	Least concern	Bird is found in most islands of Vanuatu
Lichmera incana	Grey Eared Honeyeater	Leas concern	Bird is found throughout Vanuatu

Source: Republic of Vanuatu, 2014; IUCN RedList 2016 and field survey Jan 12 2019

Mammals

Scientific Name	Common Name	Conservation Status	Habitat
Fruit bats (<i>Pteropodidae</i>)			
Notopteris macdonaldi	Fijian Blossom-bat	Vulnerable	Restricted to Fiji and Vanuatu. Observers in Efate and other islands. Roosts in caves and forages in lowland forests and intermediate altitude vegetation.
Insectivorous bats			
Miniopterus tristis	Great Bent- winged Bat	Least Concern	A native species, known from the islands of Espiritu Santo and Efate in Vanuatu. Roosts only in caves and forages in agricultural areas and disturbed lowland forest near sea Level
Miniopterus australis	Little Long- fingered Bat	Least concern	Native to Vanuatu, this bat is found roosting in colonies in caves and tunnels, and may also be found roosting in tree holes. It forages for insects in rainforest, Meleleuca swamps and dry sclerophyll forests. Unlikely to be affected by this proposal

Source: IUCN RedList and field survey of Jan 12 2019

Reptiles and amphibians

Scientific	Common	Conservation	Habitat
Name	Name	Status	Habitat
Amphibia			
Litoria aurea	Green and golden bell frog	Vulnerable	This frog was introduced to Vanuatu in the 1960s and is native to Australia. It is found in Efate, Malekula and Santo islands. The natural habitat requirements of the species have proved difficult to define because it has been associated with almost every type of water body except fast-flowing streams. There also appears to be some confusion over whether or not forested habitats are utilized by the species (Hero et al 2004).
Reptilia			
Brachylophus bulabula	Banded Iguana	Endangered	Banded Iguanas are native to Fiji and were introduced to Vanuatu by a reptile dealer in the 1960s. It is found on Efate Island. The Fiji Banded Iguana lives in both wet and dry forest, but wetter forests contain preferred plant species. Iguanas are sometimes found in marginal habitats of nonnative plants, native hibiscus, and degraded forest around resorts and also along ocean margins, but always where trees are at least six meters in height (Fisher et al 2012)
Gehyra oceanica	Oceanic Gecko	Least concern	This is a nocturnal, arboreal gecko. It occurs in primary and secondary forested habitats and coastal thickets. It also occurs in edificarian habitats such as rural gardens and urban areas and many populations are commensal with humans (Fisher et al 2015). IT is known to occur on Efate Island.
HeMIPU	Common	Least	This gecko was introduced to Vanuatu. It is a nocturnal species
DPWactylus	House	concern	which is found on boulders, beneath rocks or rotting logs, on
frenatus	Gecko		trees, and, most commonly on buildings. This species is found in both villages and large urban areas; it is usually found close to electric lights at dusk. In addition, this species also occurs in a diverse range of habitats, including rain forests, savannahs, and deserts (Ota and Whitaker 2010). This species is found on Efate Island.
Lepidodactylus	Vanuatu	Least	Endemic to Vanuatu, this gecko is known from Efate, Espiritu

Scientific Name	Common Name	Conservation Status	Habitat
vanuatuensis	Gecko	concern	Santo and Anatom Islands. It is likely, however, to occur on all main islands (Hamilton et al 2013).
Emoia nigromarginata	Vanuatu Silver Vineskink	Least Concern	Endemic to Vanuatu, it has been recorded from Efate Island, Pentecost Island, Malakula Island, Espiritu Santo Island, and Ambrym Islands, although it is possible that this species is limited to Efate Island and specimens from other islands may represent different species. This is an arboreal species, found in areas covered by seral or climax forest, and to a lesser extent, in areas with reduced tree cover such as strand forest, partly cleared forest, tree-studded pasture
Emoia sanfordi	Vanuatu Green Tree Skink	Least Concern	Endemic to Vanuatu, this skink is found from the Torres Islands south to Efate. This is a strongly arboreal species, and can be found in overgrown coconut plantations, primary forest, secondary forest, rural gardens, trees within villages (Harlow 2013).
Lipinia noctua	Moth Skink	Not yet assessed	An arboreal skink that occurs in Santo, Malo, Aore, Pentecost, Malakula, Ambrym, Epi, Efate, Tanna, and Anatom. (Reptiledatabase 2016)
Candoia carinata	Pacific Boa Constrictor	Least concern	Found throughout Melanesia and in Vanuatu it is probably introduced
Candoia carinata paulsoni	White bellied brown snake	Least concern	Snake is found in Efate and other islands

Source: IUCN Redlist, www.iucnredlist.org/ and field survey of Jan 12 2019

(3) Local Livelihood

As it shown in the Table 1.3-5 below, one-third of households in Eratap are depending to fish, crops, and handicraft as their main source of income.

Table 1.3-5 Main source of income by region: Number of households and percenta
--

				<u> </u>	(1 1				
	Main Source of household income (household number)								
Region	Wages/ salary	Landlord	Remittances	Rent House	Sale of fish/crops/ handicrafts	Individual business	Others	None	
Vanuatu	22,413	185	5,688	1,046	33,304	12,894	3,850	535	
Shefa	14,060	68	1,577	762	6,735	4,578	819	74	
Port Vila	9,810	21	580	638	1,496	2,027	148	20	
Eratap	767	11	93	7	682	462	20	2	

		Main Source of household income (household %)									
Region	Wages/ salary	Landlord	Remittances	Rent House	Sale of fish/crops/ handicrafts	Individual business	Others	None			
Vanuatu	28%	0%	7%	1%	42%	16%	5%	1%			
Shefa	49%	0%	5%	3%	23%	16%	3%	0%			
Port Vila	67%	0%	4%	4%	10%	14%	1%	0%			
Eratap	38%	1%	5%	0%	33%	23%	1%	0%			

Source: 2016 Post Pam Mini Census Report

(4) Poverty

Consumption-based poverty level of Vanuatu is 12.3% that is not high, but the level varies widely regionally. The poverty headcount rates are higher in North Malekula, Maewo, Pentecost and Tanna, and lower in prime agricultural areas of Santo and parts of Ambae and Ambrym.

The household well-being indicators such as poverty headcount ratio in Eratap region along with Port Villa are shown in the following Table 1.3-6.

Area Council	Number of households	Poverty headcount ratio	Distribution of the poor	Population density (per km ²)	Average monthly consumption (PCAE)	GINI coefficient	The inequality ratio (the 90 th /10 th percentile ratio)
VANUATU	47,373	12.3%	N/A	18.7	19,089	0.351	4.72
SHEFA	6,875	13.0%	14.2%	22.8	19,112	0.400	5.74
Port Villa	9,055	18.4%	29.6%	1,803.2	4,163	0.340	4.54
Eratap	721	3.1%	0.4%	51.5 3	1,890	0.399	5.83

Table 1.3-6 Household Well-being Indicators

Source: Population and Housing Census, 2009 and Household Income and Expenditure Survey, 2010

(5) Social Infrastructures

1) Source of Drinking Water

The sources of drinking water for households in the Eratap region are shown in the following Table 1.3-7 by number of households and percentage.

				0				-	0 ;	
	Total		Pipe		Rain	water	Bottled	Surface	Ground-	
Region	Households (Number)	Private	Shared	Village Stand	Private	Shared	water from shops	water	water	Other
Vanuatu	55,285	9,226	16,373	2,345	10,385	9,743	314	4,502	2,203	194
Shefa	19,913	5,627	6,792	420	3,175	2,377	248	449	681	144
Port Vila	10,965	4,178	5,470	147	438	295	170	40	210	17
Eratap	1,293	253	47	8	497	188	19	96	108	77
	Total		Pipe		Rain	water	Bottled	Surface	Ground- water	Other
Region	Households (Percentage)	Private	Shared	Village Stand	Private	Shared	water from shops	water		
Vanuatu	100%	17%	30%	4%	19%	18%	1%	8%	4%	0%
Shefa	100%	28%	34%	2%	16%	12%	1%	2%	3%	1%
Port Vila	100%	38%	50%	1%	4%	3%	2%	0%	2%	0%
Eratap	100%	20%	4%	1%	38%	15%	1%	7%	8%	6%

 Table 1.3-7
 Main source of drinking water (Number of households and percentage)

Source: 2016 Post Pam Mini Census Report

Then, the alternative sources of drinking water in the Eratap region are shown in the following Table 1.3-8.

Tuste 16 0 Trousenord by internative source of armining water by region (only private nouses)								,			
Total		Ріре			Rainwater		Bottled	Surface	Ground-		
Region	Households (Number)	Private	Shared	Village Stand	Private	Shared	water from shops	water	water	Other	
Vanuatu	1,949	2,581	1,842	2,816	758	4,358	834	6,259	11,248	4,397	
Shefa	742	904	722	1,556	298	1,806	355	4,578	1,591	1,115	
Port Vila	265	177	2	890	108	909	45	3,552	79	56	
Eratap	55	111	71	114	10	95	13	225	321	211	
	Total		Pipe		Rainv	water	water from		Surface	Ground-	
Region	Households (Percentage)	Private	Shared	Village Stand	Private	Shared		water		Other	
Vanuatu	3.5%	4.7%	3.3%	5.1%	1.4%	7.9%	1.5%	11.3%	20.3%	8.0%	
Shefa	3.7%	4.5%	3.6%	7.8%	1.5%	9.1%	1.8%	23.0%	8.0%	5.6%	
Port Vila	2.4%	1.6%	0.0%	8.1%	1.0%	8.3%	0.4%	32.4%	0.7%	0.5%	

 Table 1.3-8
 Household by alternative source of drinking water by region (only private houses)

Source: 2016 Post Pam Mini Census Report

It can be said local people depend on river and stream water as the sources of drinking water on the Efate Island. Judging from the observation at the Teouma Bridge, where local people often fetch water and wash clothes in the project area, the water of Teouma River is the most important water resources for domestic use.

2) Teouma River Water Use

An interview survey has been conducted, targeting local people who came to the bridge to fetch water or to do laundry. Outline and the result of the survey are summarized in the following:

Outline of the Interview Survey

Target:	Local people who visit the Teouma Bridge to fetch water and wash clothes
Purpose:	To understand Teouma River water use and users
Survey method:	Interview survey
Date:	June 20, 22, and 30, 2018

Result of the Interview Survey

Respondents Sex	Number	Percentage
Female	11	44%
Male	14	56%
Total	25	100%

Source: JICA study team

Residence location and means of transportation

The following table is regarding residence location and commuting. Four respondents came to the Bridge by bus.

Residence Location	Number	Percentage	Transportation
Eratap Village	2	8%	By bus (both)
Etas	2	8%	By bus (both)
Teouma Bridge	18	72%	On foot (all)

Residence Location	Number	Percentage	Transportation
Teouma Valley	2	8%	On foot (all)
Teouma White wood	1	4%	By car
Total	25	100%	

Source: JICA study team

Frequency to visiting the bridge

Those who live within walking distance of the bridge answered they come once or twice per day, while respondents from other villages come to the bridge once per week.

Location of	Frequency				
Residence	Once per week	Twice per week	Once per day	Twice per day	Total
Eratap Village	2				2
Etas	2				2
Teouma Bridge			14	4	18
Teouma Valley			1	1	2
Teouma White wood		1			1
Total	4	1	15	5	25

Source: JICA study team

Water Use

The below table shows water use by respondents who are living within walking distance (20 respondents). They are utilizing river water for various purposes.

Water Use	Number	%
Drinking and cooking	19	95%
Domestic use (such as clearing, shower, and so on)	20	100%
Farming	18	90%
Production	8	40%
Others (poultry & piggery, sandalwood nursery)	4	20%
Total	20	100%

Source: JICA study team

Water use for laundry (domestic work or business)

Out of 20 respondents who mention of water use for laundry, 3 of them were laundry for business.

Purpose of Laundry	Number	Total
for family	19	22
for business	3	22

Source: JICA study team

Water resources during the construction work

Five respondents answered they have other sources for drinking water such as well and water tank, while four respondents said they had no other choices. Two respondents asked for support.

The result of this survey shows Teouma River is very important source of water for local people. It is important to consider a place to fetch water and do laundry near the temporary bridge and to take necessary measures to prevent water pollution during the construction period.

(6) Current Situations of HIV/AIDs

There is no data on HIV/AIDS rate in Vanuatu. Governmental authorities only recognize number of people who are confirmed to be infected by voluntary counselling and testing. The number of reported HIV cases in 2015 is shown in the following Table 1.3-9.

		Number of reported cases by province					
	Torba	Penama	Sanma	Malampa	Shefa	Tafea	total
Male adult	0	0	0	0	2	1	3
Female adult	0	0	2	0	1	2	5
Child	0	0	0	0	1	1	2
Total	0	0	2	0	4	4	10

Table 1.3-9Reported HIV cases by province, 2015

Source: HIV and STI Unit, MOH

Since the number of people who are tested for infection is limited, it seems the actual rate would be much higher.

On the other hand, the prevalence rate of sexually transmitted infections (STI) is high as shown in Table 1.3-10 below, even though this data is rather old. It is very important to increase awareness on STI including HIV/AIDS in Vanuatu in order to prevent further spreading.

Variable	Percentage
Prevalence ANC women over 25 years	18%
Prevalence ANC women under 25 years	29%
Ever diagnosed with an STI: male youth	37%
At least one symptom STI: female youth	42%
% female youth with symptom(s) who sought treatment	30%
STI client sexual partner(s) treated: male	38%
STI client sexual partner(s) treated: female	28%

Source:Second Generation Surveillance Survey 2008

1.3.1.3 Policy, Legal, and Administrative Frameworks of Environmental and Social Considerations

(1) Relevant Policies in Vanuatu

National Sustainable Development Plan (NSDP 2016-2030)

The National Sustainable Development Plan or NSDP (2016-2030) is the overall national planning framework that replaces the Priorities and Action & Agenda (PAA) which came to the end in 2015. The NSDP incorporates two (2) important pillars of sustainable development that has been missing in all Vanuatu's national planning since 1980, environment and culture are two pillars to compliment two other important economic and social pillars. The overall vision of the NSDP is:

Our people and place are at the very heart of our development aspirations. Together we strive for a nation that is stable, sustainable and prosperous, so that all people have a just and equal opportunity to be

well educated, healthy and wealthy. Just as we strive to progress in a way that protects and preserves our natural resources for our children, and theirs.

Vanuatu 2030 is our National Sustainable Development Plan for the period of 2016 to 2030, and serves as the country's highest level policy framework. It is founded on our culture, traditional knowledge and Christian principles, and builds on our development journey since Independence in 1980. We have already achieved a great deal, as we have encountered many difficulties and setbacks, some from natural disasters.

The four (4) main development aspirations of the NSDP are:

- A vibrant cultural identity underpinning a peaceful, just and inclusive society; supported by responsive and capable state institutions delivering quality public services, including health and education, to all citizens;
- Maintaining a pristine natural environment on land and at sea that serves our food, cultural, economic and ecological needs;
- With enhanced resilience and adaptive capacity to climate change and natural disasters; and
- A stable economy based on equitable, sustainable growth that creates jobs and income earning opportunities accessible to all people in rural and urban areas.

Vanuatu Land Use Planning & Zoning Policy

The policy aims to guide land use planning by setting priorities and outlining legislative and institutional arrangements to enable and encourages best use of the land and at the same time allowing for future generations to equitably benefit from the same resources.

The land use planning policy covers rural communities to urban centres integrates and recognizes custom basis as being part of the land planning process. The policy seeks to address land use planning issues while at the same time integrate the policy principles of custom, equity and sustainable development. These land use planning issues include:

- Minimizing the impact of economic development pressures on customary land
- Acknowledging the importance and significance of multi-stakeholder processes in the governance of land
- Highlighting the under-utilization of Vanuatu's cultivable land for productive use
- Looming effects of urbanization and informal settlements in the major urban centers of Vanuatu
- Emphasizing the role of the land sector as an important part of the framework for environmental and natural resource management
- Mandating proper planning and development of the land asset; including the management of government and public lands, the management of common property resources, individual and community based land use planning and urban planning and development.

(2) Laws and Regulations related to Environmental Consideration

Constitution of the Republic of Vanuatu

Environmental management is enshrined in the 1980 Constitution of Vanuatu which states "to protect the Republic of Vanuatu and to safeguard the national wealth, resources and environment in the interests of the present generation and for future generation".

Environmental Management and Conservation Act (Cap 283)

The EPCA's objective is 'to provide for the conservation, sustainable development and management of the environment of Vanuatu, and the regulation of related activities' and applies 'throughout Vanuatu, including its lands, air and waters.¹

The Act defines "environment" as the components of the earth and includes all or any of the following:

- land and water;
- layers of the atmosphere;
- all organic and inorganic matter and living organisms; and
- the interacting natural, cultural and human systems.²

Part 2 of the Act provides for the Administration of the Act by the Director of the Department of Environmental Protection and Conservation and for all instruments established for its implementation, namely the Environmental Registry, the National State of the Environment Reports, and the National Policies and National Plans. Part 3 regulates environmental impact assessment (EIA), and Part 4 is concerned with Biodiversity and Conservation Areas. It provides for the declaration of community conservation areas, discussed in the first part of the legislative review.

Physical Planning Act

The Act regulates land development in Vanuatu. Land use and developments occurring outside foreshore land may impact on the foreshores through, example water contamination and land contamination by pesticides and other pollutants, or sedimentation of foreshore waters.

The Act provides for Municipal Councils or Local Government Councils to declare any area within their jurisdiction as physical planning areas and this is then published in the Gazette for public to view and any interested persons can submit their objections.

Pollution Control Act

The objects of this Act are to:

- minimize and manage the discharge of air and land waste pollutants, the emission of noise, odour and electromagnetic radiation into the environment;
- minimize the adverse effects of pollution on human health and the environment; and
- encourage all levels of government to work together to control the discharge and emission of pollution.

The government proposes to achieve these objectives by:

¹ In the title and section 1 of the Environmental Protection and Conservation Act [Cap 283].

² Section 2 of the Environmental Protection and Conservation Act [Cap 283].

- requiring owners and occupiers of property to take reasonable and practicable measures to prevent or minimize the discharge of waste and the emission of noise, odour or electromagnetic radiation from their property;
- establishing a permit regime for owners and occupiers who wish to cause or increase the discharge of waste or pollution, or the emission of noise, odour or electromagnetic radiation from their property;
- empowering the government to issue pollution abatement notices in circumstances where pollution is being or is likely to be discharged or emitted from premises into the environment;
- establishing offences for the discharge and emission of pollution from premises of owners or occupiers of property, that unreasonably interferes with the health and/or environment of others; and
- delegating enforcement powers to Municipal Councils and Provincial Government Councils.

Water Resources Management Act

The objective of the Act is 'to provide for the protection, management and use of water resources in the Republic of Vanuatu'. Water in the Water Resources Management Act includes any:

- river, stream, creek or other natural course for water;
- lake, lagoon, bay, swamp, marsh or spring, and estuarine or coastal sea water

The Act consists of 7 Parts including inter alia water use, water management (including planning) and administration of water resources.

Section 4 defines traditional rights of water users and the rights of land owners to use water on or adjacent to their land. In both cases other water user's right must not be adversely affected.

As the operation of hotel and building tower will generate substantial solid and liquid waste near a major water body in Fatumaru Bay, serious considerations have to be made to utilize state-of-the-art wastewater treatment facilities. One option will be provided to supplement what the company is proposing.

Health & Safety at Work Act [Cap 195]

With respect to the health and safety of the workforce as stipulated in the Health and Safety at Work Act [Cap 195] It is the duty of every employer and employee to ensure, so far as is reasonably practicable, the health, safety and welfare requirements at work are met. As discussed earlier the Act (CAP 195) makes it very clear that both employers and employees have a role to play regarding health and safety at work.

The employer has the "duty of care" to provide personal protective equipment (PPE) and make workplace safe (policies, procedures, code of conduct etc.) and the employee has "due diligence" of making sure all PPE and other safety at work policies and procedure of the company are followed and used properly and looked after. The specific occupational health and safety for the identified impacts are discussed below.

The requirements of worker's safety and welfare need careful consideration as over 100 workers are expected to work during construction and operation phases.

Public Health Act, 1994

The Public Health Act makes general provisions for public health in Vanuatu, including regulation of waste management, sanitation, and prohibiting water pollution.

The Act provides for prevention of public health disease resulting for unhealthy living conditions or unhealthy environments such as poor sanitation and indiscriminate waste disposal.

The construction site must have a healthy living atmosphere for workers who will spend over 8 hours per day at the site.

Waste Management Act

An Act to provide for the protection of the environment through encouragement of effective waste services and operations as follow:

- Implement International Conventions and Treaties that relate to management of hazardous waste
- Implement the National Waste Management Strategy
- Develop environmental standards
- Undertake audit of waste generation and disposal
- Establish and implement licensing system for waste management services/operations
- Develop standard operating procedures

Public Road Act

The Act provides is for designing, planning, administration, construction, and maintenance of public roads. The objectives of this Act are as follow:

- establish a procedure for identifying and designating public roads;
- assign a level of government to be responsible for each public road;
- provide a legislative basis for strategic planning and making policies for the public road network;
- apply technical standards to the public road network;
- clarify functions and provide powers to Road Authorities to design, construct and maintain public roads; and
- regulate access, utility works, encroachments and unauthorized activities on the public road network.

(3) Organizations related to environmental and social considerations in Vanuatu

Department of Environmental Protection and Conservation (DEPC)

The Department of Environmental Protection and Conservation is responsible for formulation and implementation of environmental policies with the aim of ensuring ecologically sustainable development in Vanuatu by Ministry of Climate Change Adaptation and its affiliated agencies such as Meteorology & Geo-Hazards, Environment, Energy and Disaster Management.

The Environmental Protection and Conservation Act [CAP 283] (the EPC Act) outline its role in the development, coordination and implementation of the Government's environmental policies and programs.

The Department has five divisions, and one of them is the Environmental Planning and Impact Assessment Division, and it is responsible for to managing Environmental Impact Assessment (EIA) in Vanuatu.

Public Works Department/ Ministry of Infrastructure and Public Utilities

The Public Works Department (PWD) under the Ministry of Infrastructure and Public Utilities (MIPU) is in-charge of infrastructure development projects and infrastructure maintenance.

The PWD is one of the few central government departments with line staff in such provinces as Shefa, Sanma, Malampa, Tafea, Penama, and Torba. Therefore, its roles to ensure the safeguard policies in the infrastructure projects in Vanuatu are critical. The Shefa office is responsible for the maintenance of Efate Ring Road.

National Disaster Management Office (NDMO)

The National Disaster Management Office (NDMO) is a government department under the Ministry of Climate Change and Adaptation. It is a government agency coordinating disaster preparedness, response and recovery operations in the Republic of Vanuatu.

One of tis tasks to increase the resilience of communities throughout Vanuatu by integrating the coordination of Disaster Risk Management and Climate Change Adaptation into sectoral plans, policies and budget.

Local government

Both local government and decentralization are enshrined in the constitution (Section 82 and 83).

The provincial and municipal governments in Vanuatu are responsible for reginal planning, waste collection and disposal, road, along with pre-school & primary education as well as primary care. Water and sanitation are managed by both national and local governments.

(4) EIA Approval Process

Under the Environmental Management and Conservation Act (Cap 283), any project, proposal or development that falls within the scope of the Act is subject to a two-step EIA process. The first step is a preliminary environmental assessment (PEA) pursuant to Section 14 of the Act. The second step of the EIA process takes place where the Director has determined that an EIA is required.

The Director develops an EIA terms of reference, with "special consideration to the need for consultation, participation and involvement of custom landowners, chiefs and other interested parties, and may consult with the National Council of Chiefs for that purpose"


The EIA Regulations order No. 175 of 2011 sets out the following processes and procedures for EIA studies including determining which activities require environmental assessments, the formulation of guidelines for conducting the EIA in the form of a Terms of Reference, and the decision making process for EIA. It also covers miscellaneous issues such as registration of consultants, fees to pay as well as compliance monitoring and enforcement of the EPC Act as well as this regulation etc.

In addition, the EIA Regulations 2011 requires to formulate the Environmental Management and Monitoring Plan (EMMP), which under this Regulations should: (i) describe proposal or development activity of project and the environmental protection measures that will put in place by the project proponent in case of project approval; (ii) include an environmental monitoring and surveillance program of actions; and (iii) Appointing an environmental monitoring manager by project proponent in consultation with DEPC

in order to verify EMMP and protection measures are being fulfilled and also adverse impacts of project as well as proposal or development activities are documented.

The DEPC has to undertake an environmental audit in an annual basis of all projects, proposals and development activities with EIA approval.

The process for obtaining EIA approval is shown in the following Figure 1.3-3.



Source: EIA and VIPA by DEPC

Figure 1.3-3 EIA Approval Process

(5) Comparison between JICA Guidelines and EIA Related Laws/Regulations in Vanuatu

An inter-comparison between the JICA Guidelines for Environmental and Social Considerations 2010 (hereinafter referred to as "JICA Guidelines") and EIA related laws and regulations in Vanuatu are summarized in the following Table 1.3-11.

No.	JICA Guideline	Related Laws/ Regulations in Vanuatu	Difference	Counter- measures
1	[complying with laws]	[Implementation of PEA and EIA]	No difference	
	The Project must comply	- Under the Environmental Protection and		
	with laws, regulations and	Conservation Act (EPCA) (2010), all activities		
	standards concerning	or proposed projects that impact or are likely to		

 Table 1.3-11
 Comparison between JICA Guidelines and EIA Related Laws/Regulations

No.	JICA Guideline	Related Laws/ Regulations in Vanuatu	Difference	Counter- measures
	environmental and social considerations established by the governments (central and local governments) where the Project is implemented. Furthermore, the Project must satisfy policies and plans concerning environmental and social considerations established by the governments where the Project is implemented.	 impact the environment must make an application for approval to the Department of Environmental Protection and Conservation (DEPC). Once an application is lodged and fee paid, the DEPC EIA Unit officers carry out a preliminary environmental assessment (PEA) and determine whether an EIA is required or not. An EIA is required for those activities/ projects that cause or are likely to cause significant impacts on "environment, social and/or custom". 		
2	[Examination of Avoidance and Mitigation Measures] During the implementation of the Project, from its planning stage, the impact on the natural and social environment of the Project must be studied and examined in the as early stage as possible. Alternative and mitigation measures to avoid and minimize the impact must be studied and the result must be reflected in the Project plan.	[Examination of avoidance and mitigation measures] The proponent is required to first submit an application containing a description of the proposed activity/ project and identification of likely environmental impacts and required measures to avoid or mitigate the impacts (EIA regulations (2011).	It is not clear whether the result of identification of measures to avoid or mitigate the impacts is reflected in the Project.	It is necessary to ensure that the identified required measures to avoid or mitigate the impacts are reflected in the Project plan.
3	[Examination of alternatives] In order to avoid and minimize the negative impact of the Project and to select the best option from the aspect of environmental and social consideration, several alternatives must be examined.	 [Notification of alternatives and mitigation measures] An EIA report must include a statement of the various alternatives that have been considered for the project, proposal or development activity, including the option of taking no action, and an outline of the reasons for choosing the proposed action. An EIA report must include a statement of the mitigation action proposed in respect of any adverse impacts identified in the report (EIA regulations (2011). 	No difference	
4	[Scope of study and examination] Regarding environmental and social considerations, the impact to be examined includes the impact on human health and security and that on the natural environment (including cross-border and global impact) through air, water, soil, waste, accidents, water use, climate change, ecosystem and	 [EIA-covered project] All projects, proposals or development activities that will do or are likely to do all or any of the following are subject to the EIA provisions: a) affect coastal dynamics or result in coastal erosion; b) result in the pollution of water resources; c) affect any protected, rate, threatened or endangered species, its habitat or nesting grounds; d) result in the contamination of land; e) endanger public health; f) affect important custom resources; 	The environmental standards are not mentioned in EPCA and EIA regulations. Referring to internationally acknowledged guidelines (WHO, IFC, etc.) or standards of	The expected impact shall be compared and examined.

No.	JICA Guideline	Related Laws/ Regulations in Vanuatu	Difference	Counter- measures
	fauna and flora. It also includes the impact with respect to social considerations.	 g) affect protected or proposed protected areas; h) affect air quality; i) result in the unsustainable use of renewable resources; and j) result in the introduction of foreign organisms and species. (Environmental Protection and Conservation Act) 	advanced countries.	
5	[Information disclosure and public involvement] As for the Project which is expected to put relatively big impact on the environment, from the early stage when alternatives of the Project are examined, the information should be disclosed. And then, it is necessary that the stakeholders such as local residents are fully consulted and that the result is reflected in the Project.	 [Decision-making] The project proponent must conduct public consultations on the project, proposal or development activity at times and places as determined by the Director and convenient for those likely to with to take part. At least one of the public consultation meetings must be held in the close vicinity of the area of the proposed development. Notices of public consultation meetings must be given by the project proponent in the manner directed by the Director and such notices must inform the public of: a) the locality and the nature of the project, proposal or development activity b) the location and the time of the public consultation meetings is to be met by the project proponent (EIA regulations (2011). [Decision-making on EIA] The project proponent must conduct public consultations on the project, proposal or development activity at times and places as determined by the Director and convenient for those likely to with to take part. At least one of the public consultation meetings must be held in the close vicinity of the area of the proposed development. If a public consultation meeting is held, notice of it must be given by the project proponent in the manner directed by the Director and must inform the public of: a) the locality and the nature of the project, proposal or development. 	It is not clear from which stage of the project public consultations take place. It is not clear whether the result of public consultations is reflected in the project.	Public consultations shall take place from as early stage of the project as possible. The result of the consultations shall be recorded and reflected in the project.
6	[Monitoring]	[Monitoring System]	It is not clear	The result of

No.	JICA Guideline	Related Laws/ Regulations in Vanuatu	Difference	Counter- measures
	The donor country shall check the monitoring results which are deemed important for a certain period in order to verify whether the host country considers the environmental and social impact. Information necessary for verifying the monitoring results shall be reported by the host country via a proper manner such as documentation etc.	 An environmental management and monitoring plan (EMMP) for a project, proposal or development activity must be submitted with the EIA report. An EMMP must: a) describe the environmental protection measures that will be put in place by the proponent; b) include and environmental monitoring and surveillance program of action; and c) provide for an environmental monitoring manager to be appointed by the project proponent to verify that the EMMP and protection measures are being fulfilled and adverse impacts are documented. 	whether the result of monitoring is documented in a proper manner.	monitoring shall be documented and submitted to relevant agencies.

Source: JICA study team

1.3.1.4 Alternative Analysis including No Project (No Action)

(1) High Risk of No Action

The abutment of existing Teouma Bridge in the right bank of Teouma river, along with the approach road, is seriously damaged by Cyclone Pam. The traffic of Ring Road was suspended for six days before implementation of an emergency reconstruction work. It is highly anticipated that another devastating cyclone cause a fatal damage to the bridge and this could lead to serious interruption of daily life in the Efate Island as well as the Vanuatu economy. Therefore, it is urgent for the Vanuatu government to replace the Teouma Bridge with the new one.

Items Option 0: No Action		Option 1: Embankment	Option 2: Embankment + Culvert	Option 3: Overflow management
Ring Road Inundation	× No change	Sag part of the Ring Road, the left side of the bridge, shall be elevated with soil fill embankment up to 8.7 m above MSL in height to prevent inundation of the Ring Road even at a 100- year return period flood event.	Sag part of the Ring Road, the left side of the bridge, shall be elevated with soil fill embankment up to a height of 8.4 m above MSL to prevent inundation of the Ring Road even at a 100-year return period flood event.	Ring Road with a decline slope of 3% will connect the bridge to the bottom of existing road in order to utilize existing drainage function of sag part of the Ring Road.
Overflow management	∆ No change	O No overflow in sag part of the Ring Road	O No overflow in sag part of the Ring Road	\triangle Flood water shall flow over sag part of the Ring Road by flood of 10-year return period or larger.

(2) Alternatives for Flood Countermeasure

Items	Option 0: No Action	Option 1: Embankment	Option 2: Embankment + Culvert	Option 3: Overflow management
Flood Management	∆ No Change	△ Flooding in the upstream of the Ring Road will be slightly worse.	C This is not increasing flooding in the upstream of the Ring Road.	O This is not increasing flooding in the upstream of the Ring Road.
Construction Cost	O No cost	O Low	∆ Medium	× High
Land Acquisition	O land acquisition	△ Embankment with the maximum height of 2.5 m requires a larger land area for construction.	\triangle Embankment with the maximum height of 2.5 m requires a larger land area for construction.	\triangle The Ring Road from the bridge entrance to sag part of the road will be filled with soil
Safety and Convenience	X Not good in road alignment	O Vertical alignment will be improved even at a 100- year return period flood event.	O Vertical alignment will be improved even at a 100- year return period flood event.	△ Vertical alignment will be improved, but the road risk grade is still large. The road might be blocked by food with 10-year return period or larger.
Overall Evaluation	Not recommended	Not recommended	Recommended	Not Recommended

 $*\bigcirc$: Good, \triangle : Fair, X: Not Acceptable

(3) Options for Bridge Type

Options Items	Option 0: No Action	Option 1: Warren Pony Truss	Option 2: Steel Plate Girder
Structural Features	No change	The bridge structural height of the pony truss is 1.1 m, lower than that of the plate girder type. The road elevation can be lower.	\triangle One of advantages of the Girder type is its simple structure. The bridge structural height is 1.5 m and it need to elevate the road 0.4m higher than that of pony truss type.
Safety	X The width of the road is narrow and does not meet the standards	\triangle There is risk of hitting the main steel (truss) by vehicle. Drivers also feel pressure when passing the bridge.	There is no risk that the vehicle may hit the main steel structure since it is a deck bridge. This type of bridge is superior to pony truss type in terms of road visibility.
Construction	O No construction	It is easier to manage the construction work, because the members are small and light. Special erection method is not required.	△ Crane erection method can be adopted, though the members are bigger. Special erection method is not required.
Cost	O No cost	△ Approx. 370 kg/m ² Total steel weight: approx. 211t (width:9.5m, length:60m)	Approx. 240 kg/m ² Total steel weight: approx. 137t (width:9.5m, length:60m)

Options Items	Option 0: No Action	Option 1: Warren Pony Truss	Option 2: Steel Plate Girder
Maintenance (15 Points)	X Intensive maintenance is required due to large number of the members. Sand sedimentation has been observed on lower chord member.	X Intensive maintenance is required due to large number of the members. Sand sedimentation has been observed on lower chord member.	O Numbers of members are not too many leading to an easier maintenance work.
Total	Not recommended	Not recommended	Recommended

 $*\bigcirc$: Good, \triangle : Fair, X: Not Acceptable

(4) Options for Approach Road Alignment

Ontion	Option 0:	Option 1:	Option 2:	Option 3:
Option	No Action	Existing	Upstream	Downstream
Obstacles	O No obstacle		\triangle Electrical line, poles and other utilities exist. It is	\triangle Electrical line, poles and other utilities exist.
		exist. It is necessary to relocate them during the construction.	necessary to relocate them during the construction.	It is necessary to relocate them during the construction.
Road alignment (Traffic Safety)	X Vertical alignment does not meet the standards	O Radius of curvature is not increased due to the extension of the bridge to the right side of the river. The alignment is the same.	O The road curve on the right bank side becomes gentler, and this enhances road safety.	\triangle The road curve on the left bank side becomes sharp, and this affects road safety
Construction period*	O No construction	\triangle The construction period of bridge and road will be longer, but the whole construction period depends on that of river improvement work.	\triangle The construction period of bridge and road will be shorter, but the whole construction period depends on that of river improvement work.	\triangle The construction period of bridge and road will be shorter, but the whole construction period depends on that of river improvement work.
Cost	O No cost	O No need to huge soil fill embankments and other construction in this option and also no need to structures such as retaining walls. Lowest cost for this option.	X Large amount of soil fill embankment and structures such as retaining walls causes increase in cost.	X Large amount of soil fill embankment and structures such as retaining walls causes increase in cost.

Ontion	Option 0:	Option 1:	Option 2:	Option 3:
Option	No Action	Existing	Upstream	Downstream
Environmental Impact	O No impacts	O No resettlement of residents is needed. Limited area of land is needed to be expropriated.	X A large area of land acquisition is required. The land on the left side of the river and north of the road is on the long- term lease contract and it is difficult to negotiate the land acquisition. At the time of traffic switch from the old bridge to the replaced bride, a detour is needed at the downstream side.	X A large area of land acquisition is required. At the time of traffic switch from the old bridge to the replaced bride, a detour is needed at the downstream side.
Socio-economic impacts	X Safe and smooth traffic is not secured, and this could cause problems for local economic development and social welfare	O Safe and smooth traffic would enhance economic development and social welfare.	O Safe and smooth traffic would enhance the local economic development and social welfare.	O Safe and smooth traffic would enhance the economic development and social welfare.
Total evaluation	Not recommended	Recommended	Not recommended	Not recommended

 $*\bigcirc$: Good, \triangle : Fair, X: Not Acceptable

1.3.1.5 Scoping

Under the Vanuatu EIA Procedures, a ToR developed by DEPC after visiting project sites and discussion with concerned organizations and people.

JICA survey team also conducted a scoping in cooperating with PWD and an EIA consultant team. Opinions and comments from residents and local governments at the first consultation meetings is reflected in the finalized scoping shown in Table 1.3-12.

			Evalu	ation	
Category		Items	Before/ During Construction	Operation	Reason
Anti- pollution measures	1	Air pollution	B-	С	[Before/During Construction] Ambient air quality will be affected by the dust and emission gas generated during the preparation and construction work, but the impacts will be limited due to the limited number of heavy vehicles and trucks. [Operation] After the completion of the work, along with the ADB road rehabilitation project, the traffic volume of the ring road is expected to increase, and this could affect the ambient air quality. (The second phase of the ADB project will not increase the traffic volume at the bridge)

			Evalu	ation	
Category		Items	Before/ During Construction	Operation	Reason
	2	Water pollution	B-	D	 [Construction] Excavation/embankment work along the river and the construction work of bridge pier could worsen river water quality during the construction period. Rainfall during or just after the embankment/Cut- earth work could cause soil erosion and river water pollution. [Operation] Slope protection work could mitigate soil erosion during the operation phase.
	3	Soil Pollution	С	D	[Construction] There is a possibility of soil contamination by oil during the maintenance work of heavy vehicles and trucks, but the area might be limited. [Operation] There are no works which could cause soil pollution.
	4	Waste ✓ Municipa l solid waste (MSW) ✓ Construct ion waste (CW)	B-	D	 [Construction] It is unlikely that camps for construction workers would be established, and the problems caused by general waste would be very limited. [Operation] There will be no works which generate general waste. [Construction] Construction waste such as excavated soil and concrete debris will be generated. Organic waste and soil including organic waste will be also generated after the site clearance.
	5	Noise and Vibrations	B-	С	[Construction] During the construction period, construction work will cause problems of noise and vibrations. [Operation] During the operation phase, same as air pollution, noise and vibration problems would worsen due to the increase in traffic volume.
	6	Ground subsidence	C-	C-	[Construction] No construction work could cause ground subsidence, but it is necessary to check based on the result of the ground survey. [Operation] There are no elements to cause ground subsidence.
		Soil erosion	B-	B-	 [Construction] Construction work to widen and change the channel could cause soil erosion. Rainfall during or just after the embankment/Cutearth work could cause soil erosion. [Operation] Change of river channel at and around the bridge could cause soil erosion in the downstream of the river, after the completion of the construction work.
	7	Offensive odors	D	D	[Construction]/[Operation] There is no activity to cause offensive odor.
Natural environme nt	8	Bottom sediment	B-	D	[Construction] Construction of a pier and excavation work would have negative impacts on bottom sediment. [Operation] No negative impacts are not expected.

			Evalu	ation	
Category		Items	Before/ During Construction	Operation	Reason
	9	Protection area	C-	С	[Construction]/[Operation] No national park or conservation areas inside the project area are identified so far. The EIA survey will check if there are any protected areas inside the project area.
	10	Biota and ecosystems	B-	D	[Before/During Construction] Channel widening and excavation work would have negative impacts on aquatic organisms, in particular Benthos. Need to collect the data on fauna and flora in and around the Teouma river. [Operation]
	11	Hydrology	B-	B-	[Construction] River improvement work could have impact on the hydrology of the downstream.[Operation] Modified river alignment upstream and downstream of the Teouma Bridge could have impacts on the alignment of the downstream.The elevated access road could worsen the flooding north of the access road.
	12	Geographical features/Lan dscape	В	С	[Construction/ Operation] Due to the elevation of the new bridge and access road, the landscape will be changed.
Social environme nt	13	Land acquisition and resettlement	B-	D	[Pre-construction] No households need to be resettled, but a certain area of land is needed to be permanently expropriated or temporarily used as the detour. Need to estimate the compensation amount for land, structures, trees and crops. [Operation] Compensation and support will be implemented based on the RAP during the preconstruction, this would minimize the negative impact.
	14	Vulnerable groups /Poor people	С	D	[Pre/During Construction] No issues of minority and indigenous people are identified, but If the result of social and economic survey finds issues to be solved, some kinds of support would be considered. Same as for poor people. [Operation] Issues identified during the surveys will be dealt with.
	15	Local economies	B+/-	B+	[Construction] The project will bring about some benefits such as job creation and economic opportunities to sell foods/goods to workers, while some households will lose a part of farmland. [Operation] During the flood, traffic of the ring road is secured, and this could contribute to the local economic development.
	16	Land use	B-	С	[Construction] A part of farmland and roadside cannot be temporarily or permanently used. [Operation] Due to the change of river channel around the bridge, there might be change of the river channel downstream, and this could restrict the use of the land.

			Evalu	ation	
Category		Items	Before/ During Construction	Operation	Reason
	17	Water use	B-	B+	[Construction] The construction work could worsen water quality and this would be problems of water use for both drinking and farming water purposes. The right-side riverbank just below the bridge is the place where people take water and do the laundry (some people come from other areas in order to do laundry by bus). During the construction work, they need to look for other places [Operation] the steps are planned to be installed in the bank, and this will make it easier for local people to access to river water.
	18	Existing social infrastructure s and Services	B-	B+	[Construction] The construction work will cause a problem of other infrastructure such as transmission line, as well as traffic congestion (not serious) [Operation] After the project, the transportation network in Efate Island will be improved.
	19	Social institutions	D	D	[Construction] Land expropriation issues could affect the consensus formation in the community. [Construction]/[Operation] The project will not affect the local social institutions and decision- making organization.
	20	Misdistributi on of benefits and damages	C-	C-	[Pre-Construction] The project could cause gaps among project affected households [Operation] The project could ensure the main transportation system in Efate Island during the cyclone and this is a benefit for all the local people. The change of river channel in the upstream of the bridge could affect the area in the downstream.
	21	Local conflicts of interest	D	D	[Pre-Construction/Construction] The main purpose of the project is the replacement of the bridges, and there could be no local conflicts. [Operation] The project will bring about benefits the whole community can enjoy, so the local conflict of interests will not be expected.
	22	Cultural heritage	С	D	[Construction] No local archeological, historical, cultural, and religious heritages are identified inside and near the project area, but the EIA survey will check the existence. [Operation] If the cultural heritage site is identified, a necessary measure will be taken.
	23	Landscape	B-	C-	[Construction] The construction work could affect the landscape, but the project site is not a tourist site or scenic spot and its impact might be limited. [Operation] The elevation of the bridge and access road could change the landscape.
	24	Gender/ Children's rights	С	D	[Operation] There could be a gender bias against the employment of construction workers. [Operation] The project is not expected to affect the gender/children's right related issues.

			Evalu	ation	
Category		Items	Before/ During Construction	Operation	Reason
	25	Infectious diseases such as HIV/AIDS	С	D	[Construction] Construction workers are planned to be employed locally, so the infectious diseases such as HIV/AIDS are not expected to be increased. [Operation] The negative impacts are not expected.
	26	Working conditions (work safety)	B-	D	[Construction] There would be accidents, injuries and health problems at the construction sites. [Operation] Problems related to working safety are not expected.
	27	Accidents	B-	B-	[Construction] There would be traffic accidents, involving local people, during the construction work. [Operation] Elevation of the access road could cause traffic accidents for a certain period after the completion of the construction work
	28	Global warming	D	С	[Construction] A limited amount of global warming gas (GHS) will be emitted. [Operation] The traffic volume might be slightly increased and this increases the emission amount of GHS gas, but the effect on the global warming will be very limited.

Rating:

A+/-: Significant positive/negative impact is expected.

B+/-: Positive/negative impact is expected to some extent.

C: Extent of positive/negative impact is unknown (Examination is needed. Impacts may become clear as study progresses.)

D: No impact is expected

Source: JICA study team

1.3.1.6 ToR for Survey of Environmental and Social Considerations

A ToR for the survey of Environmental and Social Consideration Survey was made based on the ToR made by DEPC and the result of scoping in Table 1.3-13.

		Environmental and Social Considerations
Items of Impact	Survey Items	Survey method
1. Air pollution	(1) Environmental	(1) literature survey (environmental standard, measuring
	standard, current situations	method)
	of ambient air	(2) project components, construction method, construction
	(2) Impact of construction	schedule, heavy vehicles/trucks, construction area, and so on
	work	(from JICA expert team)
2. Water pollution	(1) Environmental	(1) literature survey (environmental standard, measuring
	standard, current situations	method, monitoring data)
	of water quality	(2) project components, construction method, construction
	(2) Impact of construction	schedule, construction area, and so on (from JICA expert
	work	team)
		(3) Baseline data survey
		(4) Result of soil and ground survey (from JICA expert team)
4. Waste	(1) Laws and regulations	(1) literature survey (Solid management systems in Vanuatu)
	(2) Impact of construction	(2) project components, construction method, construction
	work	schedule, construction area, and so on (from JICA expert
		team)

 Table 1.3-13
 ToR of survey of Environmental and Social Considerations

Items of Impact	Survey Items	Survey method		
5. Noise and	(1) Environmental	(1) literature survey (environmental standard, measuring		
vibrations	standard, current situations	•		
	of ambient noise	(2) project components, construction method, construction		
	(2) Impact of construction	schedule, heavy vehicles/trucks, construction area, and so on		
	work	(from JICA expert team)		
<u> </u>		(3) Baseline data survey		
6. Soil erosion	(1) Impact of construction	(1) literature survey related to soil survey		
	work	(2) project components, construction method, construction schedule, construction area, and so on (from JICA expert		
		team)		
		(3) Result of soil and ground survey (from JICA expert team)		
10. Biota and	(1) data on fauna and flora	(1) literature survey (reports on fauna and flora along the		
ecosystems	(in particular endangered	river)		
ceosystems	species)	(2) project components, construction method, construction		
	(2) Impact of construction	schedule, construction area, and so on (from JICA expert		
	work	team)		
		(3) Baseline data survey		
11. Hydrology	(1) current situations	(1) literature survey (reports of similar projects)		
	(2) Impact of construction	(2) project components, construction method, construction		
	work	schedule, construction area, and so on (from JICA expert		
		team)		
		(3) Result of soil and ground survey (from JICA expert team)		
13. Resettlement/	(1) legal framework related	(1) literature survey (legal framework, reports of other		
land acquisition	to resettlement	projects)		
	(2) households needed to be resettled	(2) project components, construction method, construction schedule, construction area, and so on (from JICA expert		
	(3) compensation policies	team)		
	(5) compensation ponetes	(3) Socio-economic survey, Inventory survey, consultation		
		meetings		
14. Vulnerable	(1) Current situations	(1) literature survey		
groups		(2) Socio-economic survey and consultation meetings		
15. Local economy	(1) Impact of construction	(1) literature survey		
such as	work	(2) Socio-economic survey (RAP)		
employment and		(3) consultation meetings		
livelihood				
16. Utilization of	(1) Impact of construction	(1) literature survey		
land and local	work	(2) Socio-economic survey (RAP)		
resources		(3) consultation meetings		
17. Water use	(1) Impact of construction	(1) literature survey		
(drinking water)	work (during and after the	(2) Socio-economic survey (RAP)		
	construction work)	(3) consultation meetings		
		(4) Interview survey at the Teouma bridge		
18. Existing	(1) Impact of construction	(1) literature survey (EIA reports of other projects)		
social	work	(1) Consultation montance		
	work	(2) Consultation meetings (3) Site inspections		
infrastructures and	work	(2) Consultation meetings (3) Site inspections		
infrastructures and services		(3) Site inspections		
infrastructures and services 20. Misdistribution	(1) Impact of construction	(3) Site inspections(1) literature survey		
infrastructures and services 20. Misdistribution of benefits and		(3) Site inspections(1) literature survey(2) Socio-economic survey (RAP)		
infrastructures and services 20. Misdistribution of benefits and damages	(1) Impact of construction work	 (3) Site inspections (1) literature survey (2) Socio-economic survey (RAP) (3) consultation meetings 		
infrastructures and services 20. Misdistribution of benefits and damages 22. Cultural	(1) Impact of construction work(1) Impact of construction	 (3) Site inspections (1) literature survey (2) Socio-economic survey (RAP) (3) consultation meetings (1) literature survey 		
infrastructures and services 20. Misdistribution of benefits and damages	(1) Impact of construction work	 (3) Site inspections (1) literature survey (2) Socio-economic survey (RAP) (3) consultation meetings (1) literature survey (2) Consultation meetings 		
infrastructures and services 20. Misdistribution of benefits and damages 22. Cultural	(1) Impact of construction work(1) Impact of construction	 (3) Site inspections (1) literature survey (2) Socio-economic survey (RAP) (3) consultation meetings (1) literature survey 		

Items of Impact	Survey Items	Survey method		
24. Gender/	(1) Impact of construction	(1) literature survey		
Children's right	work	(2) Socio-economic survey (RAP)		
		(3) consultation meetings		
25. Infectious	(1) Impact of construction	(1) literature survey		
diseases such as	work	(2) interview survey with organizations concerned		
HIV/AIDS				
26. Work	(1) Impact of construction	(1) literature survey		
Conditions	work	(2) interview survey with organizations concerned		
including Work		(3) project components, construction method, construction		
Safety		schedule, construction area, and so on (from JICA expert		
		team)		
27. Accidents	(1) Impact of construction	(1) literature survey		
	work	(2) interview survey with organizations concerned		
28. Global	(1) Impact of construction	(1) literature survey		
warming	work	(2) project components, construction method, construction		
-		schedule, construction area, and so on (from JICA expert		
		team)		

Source: JICA study team

1.3.1.7 Survey Result of Environmental and Social Considerations

(1) Air Pollution

There are neither air quality standards nor emission standards for vehicles in Vanuatu. There are also very limited monitoring data on the ambient air³. An IEE report of AID project for Cyclone Pam Road Reconstruction Project⁴ stated air quality at the project site is very good.

Since the main source of air pollution is dust caused by excavation/embankment work and dump trucks running on the access roads, the qualitative monitoring will be done by observation during construction.

The following risks are expected during the construction and operation period.

[Construction phase]

- Air pollution caused by dust, which are generated from excavation/embankment work and dump trucks running on the access road at the project site, is the biggest concern. Soils from the buck of the dump trucks and tires would also cause air pollution along the road.
- Emission gas from trucks and heavy vehicles would also affect air quality, though its degree is limited due to the limited number of vehicles and limited total operation days, as shown in the table of Construction Machinery Schedule, in the section of 25) Global Warming.

The following countermeasures could mitigate the above mentioned problems.

• To use trucks and heavy vehicles of good conditions with certificates and conduct a regular check and maintenance of these vehicles

 $^{^3}$ One of the data available is the data on the annual mean concentrations of PM2.5, provided for the Gloval Buden of Disease Study 2015 by Brauer, M. et al. The value for PM2.5 air pollution, mean annual exposure (micrograms per cubic meter) in Vanuatu was 8.52 as of 2015. (The World Health Organization's air quality guidelines recommend that the annual mean concentrations of PM2.5 should not exceed 10 μ m/m³ and 20 μ m/m³ for PM10.) ⁴ Ministry of Infrastructure and Public Utilities, Initial Environmental Examination (VAN: Cyclone Pam Road Reconstruction Project - Additional Financing), June 2017, Asian Development Bank

- To implement regular watering at the construction site and stock yard and to wash tires of dump trucks
- To cover construction materials loaded on the back of the dump trucks

[Operation phase]

The result of the truck traffic volume estimation shows an increase in the light vehicle traffic volume by 15% in 2022, while the large size truck volume is estimated at the same level (refer to Chap 2.2.1.5). Due to the development of the residential area in the east side of the bridge, the volume of passenger cars and wagons (bus) would also be increased, but the current level of the traffic volume is small, and the impact of the traffic increase is very limited.

(2) Water Contamination

The result of the water quality survey under the baseline survey and the sampling locations are shown in Table 1.3-14 and Figure 1.3-4 below.

Tuble file fit i Result of Duschile Suf (eg					
Analysis	Sample 1	Sample 2	Sample 3	Unit	Standard
Fecal coliform (FC)	9	21	2	U/100ml	=0 (NF T 90-414) WHO Guideline
Enterococcus	2	19	0	U/100ml	=0 (NF T 90-416) WHO Guideline
рН	8.03	8.01	8.27		>6.5 & < 9.5 (NF T 90-008) WHO Guideline
Conductivity	455	462	457	μS/cm	
BOD	1	1	0	mg/l O	(<1 mg/l for rivers categorized as AA, which water can be used as drinking water with simple filtering method in Japan)
Nitrate	3.7	3.4	2.8	mg/l	<50 mg/l (WHO guideline)
Nitrite	0.2	0.3	0.2	mg/l	< 3 mg/l (WHO guideline)
Phosphor reactive (orthophosphate)	0	0.01	0	mg/l	
Turbidity	2.74	1.98	0.5	NTU	(≤ 2 standards for tap water in Japan)

 Table 1.3-14
 Result of Baseline Survey

Source: JICA study team



Source: JICA study team

Figure 1.3-4 Locations of Sampling Points

Teouma River water is clear, and concentration of organic/ inorganic matters is low, but the level of coliform is rather high for drinking water. The impacts of the project on water quality and countermeasures are summarized in the following:

[Construction Phase]

- Soil erosion caused by excavation/embankment work and piling work of the pier construction work, along with casting work, would cause water contamination.
- Heavy rain could cause soil erosion from embankment during the construction work or soon after the completion of the work.
- After watering and washing tires, wastewater with soil could pollute the river water
- Wastewater after washing tools and vehicles could pollute the river water.

Teouma River water is the most importance source of water for local people and its water is widely used as drinking water, domestic water, agricultural water, and so on. The following measures could prevent water contamination:

- Construction work at the riverbed will be done only during the dry season as much as possible.
- Excavation work and pier construction work will be done with temporary cofferdam method, using steel sheet pile or sandbags.
- A sedimentation pond or drainage will be installed in order to treat wastewater after watering and washing

(3) Soil Contamination

[Construction Phase]

The storage facilities of oil, chemicals and vehicle maintenance are installed at the site. In order to prevent or mitigate the problems caused by leakage, spillover prevention measures such as bunding are necessary.

There is a possibility of soil contamination by oil and grease, leaked from maintenance work. The use of oil tray could mitigate this kind of problem.

(4) Waste

[Pre-construction/Construction phase]

The organic waste and soils mixed with organic waste will be generated during the site-clearance work.

Excavated soil will be generated due to construction work, while general waste will be generated at the site office and construction site. Oil/grease waste will be also generated. In addition, due to the removal of abutment, concrete debris will be generated. A surplus soil of 10,000 m³, equivalent to the volume of 2,000 dump trucks, will be also generated by removal of detour and other facilities at the end of the construction work. The following measures are necessary to be implemented:

• Organic waste and soils mixed with organic waste is generated during the site clearance work. This waste will be disposed at the authorized Bouffa landfill operated by Port Vila city. Disposal fee:

small size and pick-up truck: VT 1,150/truck

middle size truck: VT 2,875/truck

large size truck: VT 5,750/truck

- 16 wheel truck: VT 9,780/truck
- Garbage containers and temporary toilets will be installed
- Management plan of oil & grease and chemicals should be prepared.
- Excavated soils will be used for embankment work
- Concrete debris will be reused as filling materials of riverbed (PWD will reuse the superstructure)
- Temporary storage places of excavated soil and concrete debris will be prepared for proper storage of these materials
- Surplus soil will be brought to the stock yard and reused later

(5) Noise and Vibrations

The result of the noise level survey is as follow:

LAeq, 10min	6:00 - 17:00			
Result	45.6 dB			


Survey date: February 4, 2019

Weather: fine

Location: in front of the market, west of the Teouma Bridge (See Figure 1.3-5)

The following Japanese standards are referred.

	Daytime (6:00-22:00)	Night (20:00-6:00)
Residential area	55 dB or less	45 dB or less
Commercial area	70 dB or less	60 dB or less
Residential area along the main road with 2 or more than 2 lanes each way	60 dB or less	55 dB or less
Commercial area along the main road with 2 or more than 2 lanes each way	65 dB or less	60 dB or less



Source: JICA study team

Figure 1.3-5 Location of Noise Level Measurement

Noise level is measured along the Ring Road, as shown in the above map. Compared to the Japanese standards for residential areas facing the main road with 2 or more than 2 lanes each way, the current noise level is very low. Houses near the construction area are located dozen meters away from the road and no houses are facing the road.

There are several schools in the neighboring areas but none of them are located near the project site, as shown in Figure 1.3-6.



Figure 1.3-6 Location of sensitive facilities such as schools around the project area

Construction noise will cause moderate to low disturbance to the neighboring community within the immediate semi-rural area, due to the need for the temporary use of a pile driver. The pile driver has been used in the assessment below as a worst case scenario. The village of Melemaat is located approximately 300 meters downslope. The immediate vicinity of the road is uninhabited and there is one house further upslope which has no direct line of sight to the sources of noise.

Using an attenuation rate of 6 dBA per doubling of distance, the projected noise was found to be within the standard at the main village, using accepted daytime level of 55 dBA for residential land use in the village. The numbers of receptors within the each area are also shown in the table. Most of the receptors are houses along with 3 markets and one tourist facility within 1 km from the bridge.

Noise level at the nearest houses can be below the standards, but if plural heavy vehicles and machines are used at one time, it is likely that the noise level exceeds the standard. Please refer to the following Table 1.3-15.

Table 1.5-15 Expected Police Level													
Distance from source (m)	15.24	30	61	122	244	488	975						
Number of Receptors	0	0	0	1	1	388	+338						
Vibrator Pile Driver	101	95	89	83	77	71	65						
Concrete Mixer Truck (dBA)	79	73	67	61	55	49	43						
Concrete Pump Truck (dBA)	81	75	69	63	57	51	45						
Dump Truck(dBA)	76	70	64	58	52	46	40						
Excavator (dBA)	81	75	69	63	57	51	45						

 Table 1.3-15
 Expected Noise Level

[Construction phase]

- Bridge construction work, in particular piling work, would cause noise and vibration problems
- The noise level caused by each excavation/embankment work by heavy vehicles and equipment or a dump truck/concrete pump truck would be within an acceptable level, but plural works are done simultaneously, it is likely that the noise level would exceed the standards.

The following countermeasure will be taken.

- Information on the construction work should be opened beforehand to local residents and authority, and the noisier construction work will be restricted to daytime.
- Low noise heavy vehicles and machines will be used.
- Simultaneous operation of plural noisy machines should be avoided as much as possible.
- The level of noise and vibrations will be regularly measured during the construction phase.

[Operation phase]

As mentioned in (1) Air pollution, the noise level would be worsening due the increase in the traffic volume, but the extent of the impact would be limited. Since the current noise level is law, the noise level during the operation would not exceed the noise standards.

(6) Soil erosion

[Construction phase]

The construction work of widening the width and changing the channel of Teouma River, would cause soil erosion. In addition, heavy rain could trigger soil erosion from the embankment during the construction work or the just after the completion of the construction work.

In order to prevent soil erosion, the following measures will be taken.

- Construction work at the riverbed is restricted to the dry season.
- Appropriate drainage plan will be formulated beforehand.
- Excavation work and pier construction work will be done with temporary cofferdam method, using steel sheet pile or sandbags.

[Operation phase]

In the past, Teouma River meandered freely through the rift valley with 1.5 km in width. The change of river course at the bridge could trigger the further meandering downstream. It is recommended to monitor the river morphology in the long term, from not only the environmental and social aspects but also disaster management aspect.

• The monitoring of the river course will be conducted once a year, as mentioned in the section of Hydrology.

(7) Bed sediment

[Construction phase]

The bridge construction and excavation/embankment work at the river could affect the bed sediment. The result of freshwater fauna survey shows very low biodiversity due to activities development along the river. There are no species to be protected necessarily.

The following measures could prevent further degradation.

- Construction work at the riverbed will be restricted to the dry season as much as possible.
- Appropriate drainage plan will be formulated beforehand.

(8) Biota and ecosystems

As shown in the section of 1.3.1.2(2) "Biological Conditions", the area along Teouma River is well vegetated, though modified with secondary vegetation (shrub). The diversity of freshwater fauna is low due to the development activities. There are no species to be protected necessarily. Along the river and road, there are no trees of significant height that will be affected.

But in order to prevent further degradation, the following measures will be taken.

- An attention will be paid to wildlife at the time of site clearance (to check if there are nests along the river sides, in particular during breeding period)
- Construction work at the riverbed will restricted to the dry season as much as possible
- During the site clearance, the loss of vegetation should be restricted inside the construction area
- Temporary expropriated farmland plots must be returned after rehabilitation with top soil.

(9) Hydrology

[Construction phase]

Since there would be soil erosion due to the river improvement work, the following countermeasures will be taken.

- Construction work at the riverbed will restricted to dry season as much as possible
- The loss of vegetation should be restricted inside the construction area

[Operation phase]

The change of river course at the bridge could trigger a further meandering downstream.

In addition, the elevated access road would block the flow of overflown water from north to south at the time of heavy rain and could widen flooding area in floodplain at the left side of the river.


The following measures will be taken in order to mitigate these concerns:

Countermeasures against change of river channel

- Long term monitoring of river course will be conducted
- Construction of permanent structures near the river downstream should be restricted

Countermeasures against widening inundation area

• The trapezoidal drainage system will be installed along the north side of the access road and a box culvert will be buried under the access road in order to drain overflown water of flood plain to the south of the elevated waterproofing road. Please see Figure 1.3-7 below.



Source: JICA study team

Figure 1.3-7 Drainage Systems along the Flood-proofing Road

(10) Geographical features/Landscape

Increasing elevation of the bridge and access road from 7.7 m to 10.4 m could change the landscape very much. It is a necessary action in order to protect new bridge for100-year return period flood. The following measures will assist to reduce and eliminate negative impacts of the landscape change to the daily life of local people:

- Steps to facilitate access to road and route along the riverbank under the bridge will be installed in order to connect both sides of the access road.
- Trapezoidal drainage system along the north of the access road with a box culvert will be installed, in order to prevent inundation.

(11) Resettlement and Land acquisition

There will be no involuntary resettlement, but permanent and temporary land acquisition would be necessary. It is important to estimate and arrange compensation for land plots, structures, trees, and crops.

[Pre-construction phase]

• Resettlement action plan is formulated and implemented properly (refer to 1.3.2 Land Acquisition and Resettlement).

(12) Vulnerable groups /Poor people

According to the result of the RAP survey, no vulnerable groups or poor families were identified at the project area.

(13) Local economy such as employment and livelihood

The project would have positive effect on local economies, such as job creation (e.g. construction workers) and also increase in sales of food to construction workers. However, some houses will suffer from partial loss of farmland and business opportunities of selling vegetables along the access road.

[Pre-construction phase]

• The resettlement action plan is formulated and implemented properly (refer to 1.3.2 Land Acquisition and Resettlement).

[Construction phase]

- The Contractor should hire local people as construction worker fairly and impartially, when it needs to employ workers from local people.
- A place to fetch water will be constructed near the temporary bridge, so that local people can continue to use the river water for their business as well as drinking and domestic water.

(14) Land use

[Pre-construction]

During the construction work, a part of land plots and street stalls along the access road cannot be used temporarily. The following measures will be taken.

• The resettlement action plan is formulated and implemented properly (refer to 1.3.2 Land Acquisition and Resettlement).

[Operation phase]

The change of river course at the bridge section would change the river morphology in downstream in long term. This could affect farmland and houses in downstream. The following measures will be taken:

- Long term monitoring of river course will be conducted.
- Construction of permanent structures near the river in downstream should be restricted.

(15) Water use

[Construction phase]

Since Teouma River is the main source of water for local people, water contamination would be a serious problem. In addition, during the construction work, local people will lose access to river water. In order to mitigate these problems, the following measures will be taken:

- Construction work at the riverbed will be restricted to dry season.
- Construction work of pier and riverbank will be done by temporary cofferdam method, using steel sheet pile or sandbags.

- A sedimentation pond or drainage will be installed in order to treat wastewater after watering and washing tires and vehicles. An oil separator will be used, just in case.
- River steps will be installed near temporary bridge.

[Operation phase]

Access steps will be installed at 4 places near the new bridge. This makes it easier for local people to use river water.

(16) Existing infrastructures and social services

Traffic of the Ring Road will be interrupted and installed infrastructures along the access road cannot be used such as electric cable.

[Pre-construction phase]

- The relocation plan of installed infrastructures along the access road will be formulated and implemented in consultation with owners and authorities.
- Traffic management plan will be formulated. This plan should be reflected in the construction management plan.

[Construction phase]

• Traffic management plan will be implemented in order to mitigate problems such as traffic congestions. [Operation phase]

- Turnoff will be constructed in the both side of the access road in order to secure the access to houses located on the both sides of the road.
- The pavements will be installed in both sides of the access and bridge road in order to secure the safety of pedestrians.

(17) Unjustified sharing of benefits and damages

[Pre-construction phase]

There would be economic gaps in project affected community and the following measures will be taken:

• A proper resettlement action plan will be formulated and implemented.

[Operation phase]

Traffic at the new Teouma Bridge will be secured even during 100-year return period flood. This is common benefit for all residents.

(18) Local conflict of interests

The main purpose of this project is replacing a bridge. No local conflicts of interest were observed during consultation meetings and interview surveys.

(19) Cultural heritage

No cultural heritages were identified in the project area during EIA survey.

(20) Landscape

[Operation phase]

Increasing in the elevation of bridge and access road could change the landscape. However, Teouma River is not a scenic place and this change will not be a serious issue. The following measures will help local communities to adapt with the changes:

- Well explanation of the new bridge design in the consultation meetings
- Take necessary measures to improve convenience of constructed facilities for local communities to access road and riverbank, etc.

(21) Gender and Children's right

No negative impacts of the project on gender and children's right are expected. However, it is recommended to pay attention in order to make sure of fair employment for female workers. Poorer states in Vanuatu have child labor issue in agricultural sector. However, this project site is in the area with very low poverty headcount rate. However, there is no comprehensive child protection law. It is recommended to check the age at the time of hiring even though child labor is not expected in this project.

(22) Infectious diseases such as HIV/AIDS

The project is not expected to spread the infectious diseases such as HIV/AIDS as construction workers will be recruited locally.

(23) Working conditions (work safety)

[Construction phase]

There would be accidents and injuries as well as health problems caused by dust and noise in the construction site. The following measures will be taken in order to mitigate these problems:

- The Work Safety Plan will be prepared based on the laws and regulations in Vanuatu and also international standards (OHSAS)
- Safety goods will be provided along with regular meetings and trainings as well as necessary measures such as watering will be implemented according to the safety plan.

(24) Accidents

[Construction phase]

There is risk of accidents involving local residents and passenger cars. The following measures will be taken:

- A community safety plan will be formulated.
- Information of the construction plan will be shared. Necessary facilities will be installed such as fences between the construction site and surrounding houses.
- A traffic management plan will be formulated.
- Trained guards will be assigned and necessary facilities such as signboards will be installed in order to prevent accidents.

[Operation phase]

Due to the change of road alignment (longitudinal) and increase in traffic volume, the number of accidents is expected to increase for a while. The following measures will be implemented.

- Signboards will be installed.
- Information on the new road alignment will be disseminated by radio and newspaper.

(25) Global Warming

Types, number and working days of trucks, heavy vehicles and machines are shown in the following Table 1.3-16:

								20	20								20	21										2022	,				
code	Name	Specification	unit	numbe	operat				<u> </u>							-	-	-	-								-	<u> </u>		<u> </u>	<u> </u>		Remarks
code	Name	Specification	unit	r	ion days	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10		12	1	2	3	4	5	6	7	8	9	Remarks
						1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	
			vehicle		670																										•••••	•	
		0.45m3	vehicle	1	609																												
3		0.0110	vehicle	1	670		ļ																										
4		101	vehicle	5																											-		
5	Motor grader	3.1m	vehicle	1					-	-																		-	+				
6	Road roller	10~12t	vehicle	1					-	-																			-				
7	Tire roller	8~20t	vehicle	1					-	-																							
8	Rough Terrain Crane	35t	vehicle	1	639				•••																						•••		
9	Rough Terrain Crane	35t	vehicle	1	61	1	[1			Ι	Γ	[(
10	Crawler crane	80t	vehicle	1	33																												
11	Vibro-hammer	60KW	vehicle	1	639	Τ	Γ	····								_	-	_		_										-	••		
12	Vibro-hammer	60KW	vehicle	1	61	Τ		····																		Γ		[[[
13	Large size breaker	1,300kg class	breaker	1						-	-																		1				
14	Generator	125/150KVA	generator	1	639															_											•••		
15	Generator	125/150KVA	generator	1	61	Τ	Γ					••													[l		[1	[
16	Generator	25KVA	generator	1	122		1		••						••										1	1		1	1				
17	Generator	25KVA	generator	1	518	1	1	1																					1				
18	Generator	25KVA	generator	1	122									_																			
19	Generator	25KVA	generator	1	700																												
20	Distributer	2000~3000l	distributer	1	7				•••••		••															1	•						
21	Line marker	walk behind type roller	marker	1			1	1		-															1	1		1	-				
22	Tamping rammer	60~80kg	rammer	1				-																				-					
23	Concrete pump truck	90~110m3/hr, boom type	vehicle	1		Τ	Γ	Γ	[[-	-	-			-	-	-	-	-	-	- 1	-	-		• -	-	•	Γ	[]			
		Nippon Sharyo DHJ-45	machine		68	1	Γ	I		[[[Γ		[[1		[
			1			1	1	1																	1	1	1	1	1		[
		Japan																										1					
		shipping periof	1	[1	1	1	1	1																1	1	1				[
			1				1	1																	t	†			1				

 Table 1.3-16
 Construction Machinery Schedule

Source: JICA study team

The following construction materials will be procured from an authorized quarry in Efate. This material will be stored in a stock yard, located 2.1 km north-west of the bridge. Dump trucks will commute between the construction site and stock yard to carry construction materials.

- Soil for embankment work: 25,000 m³ equivalent to volume of 5,000 dump trucks
- Stones: 2,000 m³ equivalent to volume of 400 dump trucks

The location of the construction site, stockyard, and Bouffa disposal sites are shown in Figure 1.3-8 below.



Figure 1.3-8 Locations of Teouma Bridge, Stockyard, and Bouffa Landfill sites

[Construction phase]

Greenhouse Gas (GHG) will be generated from trucks, heavy vehicles and machines. However, the volume of GHG is limited due to limited number of vehicles/machines. Mainly 4 heavy vehicles and 2 generators will travel in short distance between the stockyard and construction site.

CO₂ equivalent to GHG is estimated using the list of law emission vehicles and machines by Ministry of Land, Infrastructure, Transport and Tourism as well as based on reports of GHG generation amount by local governments and companies. It is assumed that the daily working hours of vehicles and machines are 6 hours. The result is shown in the table below.

Heavy Vehicles		kw	Working hours	Total working days	Fuel amount(l)	Basic Unit	CO2 (ton)	CO2 eq N2O(ton)
Bulldozer	21 ton	152	6	670	106,932	2.58	276	2.12
Backhoe	0.8m3	104	6	670	73,164	2.58	189	1.45
Backhoe (extream long boom)	0.4m3	60	6	609	38,367	2.58	99	0.76
Rough Terrain Crane	35 ton	257	6	700	92,820	2.58	239	1.84
Generstor	150 kVA	150	6	700	107,730	2.58	278	2.14
Generator	25 kVA	30	6	1,462	43,860	2.58	113	0.87
						Total	1,194	9.18

 CO_2 equivalent to GHG generated from dump trucks is also estimated assuming traveling distance of 6.0 km including 4.2 km for round trip and 1.8 km traveling inside the construction area. The result is shown in the table below.

Туре		No of trips	Travel Distance km	Total Travel Distance km	Fuel (l)	CO ₂ (ton)	CO ₂ eq CH ₄ (ton)	CO ₂ eq N ₂ O (ton)	Total (ton)
Dump Truck	10 ton	5400	6	32,400	9,299	24	0.01	0.14	24.1

Total amount of CO_2 equivalent GHG is estimated at around 1,000 ton. This would have little impact on Global Warming.

[Operation phase]

Target construction area is very limited and completed project is expected to mitigate the negative impacts of the global warming. As the result, the impact of the project on cross border effect is not assumed.

The traffic volume is expected to increase in a light rate and limited number. Therefore, the impact of project on global warming is not much expected.

1.3.1.8 Impact Assessment

Result of the impact assessment is shown in the following Table 1.3-17.

-		1	able 1.5-			mpace				
Category		Items	Evalua		Evaluat		Reason			
Category		items	Pre/ During Construction	Oper ation	Before/ During Construction	Opera tion	Ktason			
Anti- pollution measures	1	Air pollution	В-	С	B-	D	[Pre-Construction/Construction phase] Ambient air quality will be affected by the dust and emission gas generated during the preparation and construction work, but the impacts will be limited due to the limited number of heavy vehicles and trucks. [Operation phase] The traffic volume of the ring road is expected to increase, and this could affect the ambient air quality. But since the current volume is law, the impact of increased traffic volume is assumed to be small. The second phase of the ADB project will not increase the traffic volume at the bridge, since the main part of the work is in Port Vila.			
	2	Water pollution	В-	D	B-	D	[Construction phase] Excavation/ embankment work along the river and the construction work of bridge pier could worsen river water quality during the construction period. Rainfall during or just after the embankment/Cut-earth work could cause soil erosion and river water pollution. (slope protection work could mitigate soil erosion during the operation phase) [Operation] Slope protection could prevent soil runoff.			

 Table 1.3-17
 Result of Impact Assessment

			Evalua	tion	Evaluat	ion	
Category		Items	Pre/ During Construction	Oper ation	Before/ During Construction	Opera tion	Reason
	3	Soil Pollution	C	D	C-	D	[Construction phase] There is a possibility of soil contamination by oil during the maintenance work of heavy vehicles and trucks, but the area might be limited. There is also a risk of oil/chemical leakage from the storage facilities. [Operation phase] There are no element which cause soil pollution.
	4	Waste ✓ Municipal solid waste (MSW) ✓ Construction waste (CW)	В-	D	В-	D	[Construction phase] Camps for construction workers would not be arranged, and the problems caused by general waste would be very limited. Construction waste such as excavated soil and concrete debris will be generated. Organic waste and soil including organic waste will be also generated after the site clearance. [Operation phase] There are no works which generate waste during the operation.
	5	Noise and Vibrations	В-	С	B-	D	[Construction phase] During the construction period, construction work will cause problems of noise and vibrations. [Operation phase] Even though the traffic volume will be increased but the current noise level is now and the impact of the increased traffic volume on the noise level is limited and the noise level will not exceed the standards.
	6	Ground subsidence	D	D	D	D	There is no work which could cause ground subsidence. Based on the result of the ground survey, ground subsidence is not expected to occur
		Soil erosion	В-	B-	B-	B-	 [Construction phase] Construction work to widen and change the channel could cause soil erosion. Rainfall during or just after the embankment/Cut-earth work could cause soil erosion. [Operation phase] Change of river channel around the bridge could change the river channel downstream in the long term, and this would cause soil erosion, after the completion of the construction work.
	7	Offensive odors	D	D	D	D	[Construction]/[Operation] There is no activity to cause offensive odor.
Natural environ ment	8	Bottom sediment	В-	D	B-	D	[Construction phase] Construction of a pier and excavation work at the riverbed would have negative impacts on bottom sediment. [Operation phase] The negative impacts on bottom sediment is not expected.
	9	Protection area	D	D	D	D	No national park or conservation areas inside the project areas were identified.

			Evalua	tion	Evaluat	ion	
Category		Items	Pre/During Construction	Oper ation	Before/ During Construction	Opera tion	Reason
	10	Biota and ecosystems	B-	D	B-	D	[Construction phase] Channel widening and excavation work would have negative impacts on aquatic organisms, in particular Benthos. No endangered species were found. [Operation phase] No negative impacts on ecosystems are not expected.
	11 Hydrology 12 Geographical fastures/ coology		В-	B-	B-	B-	[Construction phase] River improvement work could have impact on the hydrology of the downstream. [Operation phase] Modified river alignment around the Teouma Bridge could have impacts on the alignment of the downstream. The elevated access road could worsen the flooding north of the access road (left side of the river), but installation of drainage systems along the access road could mitigate this problem.
	12	Geographical features/ geology	B-	С	B-	B-	[Construction phase] The elevated access road and bridge changes the geographical feature. [Operation phase] It is possible to mitigate problems caused by the change of the geographical feature, by installing steps to the access road and route along the river under the bridge to connect the both sides of the access road.
Social environ ment	13	Land acquisition and resettlement	B-	D	B-	D	[Pre-construction] No households need to be resettled, but a certain area of land is needed to be permanently expropriated or temporarily used as the detour. Need to estimate the compensation amount for land, structures, trees and crops. [Operation phase] No negative impacts are not expected.
	14	Vulnerable groups /Poor people	С	D	D	D	[Pre/During Construction] No issues of minority and indigenous people are identified, but if the result of social and economic survey finds issues to be solved, some kinds of support would be considered. Same as for poor people. [Operation] Issues identified during the surveys will be dealt with.
	15	Local economies	B+/-	B+	B+/-	B+	[Construction] The project will bring about some benefits such as job creation and economic opportunities to sell foods/goods to workers, while some households will lose a part of farmland. [Operation] During the flood, traffic of the ring road is secured and this could contribute to the local economic development.

		_	Evalua	tion	Evaluat	ion	
Category		Items	Pre/ During Construction	Oper ation	Before/During Construction	Opera tion	Reason
	16	Land use	В-	D	B-	B-	[Construction phase] A part of farmland and roadside cannot be temporarily or permanently used. [Operation phase] Modified river alignment around the Teouma Bridge could have impacts on the alignment of the downstream river in the long term, and this could affect the land use a little bit.
	17	Water use	В-	B+	В-	B+	[Construction] The construction work could worsen water quality and this would be problems of water use for both drinking and farming water purposes. The right side riverbank just below the bridge is the place where people take water and do the laundry (some people come from other areas in order to do laundry by bus). During the construction work, a temporary place for fetching water is necessary. [Operation] the river steps are planned to be installed at 4 places along the riverbank, and this will make it easier for local people to access to river water.
	18	Existing social infrastructures and Services	B-	B+	B-	B+	[Construction] The construction work will cause a problem of other infrastructure such as transmission line, as well as traffic congestion. [Operation] After the project, the transportation network in Efate Island will be improved.
	19	Social institutions	D	D	D	D	[Construction] Land expropriation issues could affect the consensus formation in the community. The project will not affect the local social institutions and decision-making body.
	20	Misdistribution of benefits and damages	B-	C-	B-	D	[Construction phase] The project could cause gaps among project affected households [Operation phase] The project could ensure the main transportation system in Efate Island during the cyclone and this is a benefit for all the local people.
	21	Local conflicts of interest	B-	D	D	D	[Construction phase] This is a project of bridge replacement and would not cause local conflicts. [Operation phase] No conflicts are expected.
	22	Cultural heritage	С	D	D	D	[Construction phase] No local archeological, historical, cultural, and religious heritages were identified inside and near the project area. [Operation phase] Since there is no cultural heritage, no problems are expected.
	23	Landscape	B-	C-	D	D	[Construction phase] The project site is not a tourist site or scenic spot, the construction work with heavy vehicles will not be a problem. [Operation phase] The elevation of the bridge and access road could change the landscape very much. At the consultation meetings, design and expected landscape were explained well and participants understood it.

~			Evalua	tion	Evaluat	ion	
Category		Items	Pre/ During Construction	Oper ation	Before/ During Construction	Opera tion	Reason
	24	Gender/ Children's rights	С	D	B-	B+	[Operation phase] Problems caused by gender bias and abuses of children's right are not expected to occur. [Operation phase] The project is expected to mitigate flood problems and could bring about benefit for communities. Newly installed river steps at 4 places would ease their work using water.
	25	Infectious diseases such as HIV/AIDS	С	D	D	D	[Construction phase] Construction workers are planned to be recruited locally, so the infectious diseases such as HIV/AIDS are not expected to spread by the project. [Operation phase] No spread of infectious disease is expected.
	26	Working conditions (work safety)	B-	D	B-	D	[Construction phase] There would be accidents, injuries and health problems at the construction sites. [Operation phase] No problems related to work safety are not expected.
	27	Accidents	B-	B-	B-	B-	[Construction phase] There would be traffic accidents, involving local people, during the construction work. [Operation phase] Elevation of the access road could cause traffic accidents for a certain period after the completion of the construction work
	28 G	Global warming	D	С	D	D	[Construction] A limited amount of global warming gas (GHS) will be emitted. [Operation] The traffic volume might be slightly increased, and this increases the emission amount of GHS gas, but the effect on the global warming will be very limited.

1.3.1.9 Environmental Management Plan (Proposed Actions and Implementation Cost)

Proposed mitigation measures and implementation cost of these measures are summarized in the following Table 1.3-18:

 Table 1.3-18
 Proposed Actions and Implantation Cost

No	Environmental Consideration	Suggested Actions and Mitigation Measures	Implementing Agencies	Responsible Organizations	Cost (USD)
Pre-c	construction phase				
1 5	Air pollution/ Noise and Vibrations	Procure low noise and low emission vehicles and machines	Contractor	PWD	
6	Soil contamination	• Procure soils and stones from quarries with permission	Contractor	DEPC/PWD	-
10	Ecosystems	• Pay attentions to wildlife and restricted site-clearance inside the project area	Contractor		-
13	Resettlement/ Land acquisition	 Land expropriation, arrangement of compensation, and supporting measures based on RAP 	PWD	PWD/DOL	RAP cost

No	Environmental Consideration	Suggested Actions and Mitigation Measures	Implementing Agencies	Responsible Organizations	Cost (USD)
15	Local economy such as	• Arrange the compensation and support based on the RAP	PWD	PWD/DOL	RAP cost
	employment and livelihood	 Employ local people as construction workers Make sure of no discrimination against women Check the age of workers 	Contractor		Included in BoQ
Cons	truction phase				
1	Air pollution	 Watering at storage place and construction site and washing tires of trucks Regular check of the conditions of heavy vehicles and trucks Try to avoid and minimize idling all vehicles Using sheet to cover truck box 	Contractor	DEPC/PWD	Included in BoQ
2	Water contamination	 Construction work in the riverbed will be done in dry season Temporary cofferdam method will be used at the time of pier construction and river embankment work After watering and washing tires, a countermeasure, such as sedimentation tank will be taken in order to prevent sediment from flowing out to the river directly. 	Contractor	DEPC/PWD	Included in BoQ
3	Waste	 Dispose of organic waste and soil mixed with organic waste after the site clearance work at the Bouffa Landfill. Store excavated soil and concrete debris at a temporary storage place and reuse as embankment soil and filling soil respectively Surplus soil will be brought back to the stock yard and reused later 	Contractor	DEPC/PWD	Included in BoQ
4	Soil Contamination	 Use oil tray at the time of maintenance work in order to prevent soil contamination Proper storage of oil and chemicals (oil spill over management) 	Contractor	DEPC/PWD	Included in BoQ
5	Noise and Vibrations	 Regular maintenance of heavy vehicle and machines will be implemented in order to prevent abnormal sound and vibrations Noisy heavy vehicles and machines will not be operated simultaneously as much as possible Safety goods are provided for workers who work near the machine, which causes noise and vibrations Noise levels will be regularly measured 	Contractor	DEPC/PWD	Included in BoQ
6	Soil erosion	 Construction work in the riverbed will be done in dry season Proper drainage will be planned in advance Temporary cofferdam method will be 	Contractor	DEPC/PWD	Included in BoQ

No	Environmental Consideration	Suggested Actions and Mitigation Measures	Implementing Agencies	Responsible Organizations	Cost (USD)
		used at the time of pier construction and river embankment work			
8	Bed sediments	 Construction work in the riverbed will be done in dry season Temporary cofferdam method will be used at the time of pier construction and river embankment work Proper drainage will be planned in advanced 			
10	Biota and ecosystems	 Construction work in the riverbed will be done in dry season Temporary expropriated farmland plots will be returned after rehabilitation. 	Contractor	DEPC/PWD	Included in BoQ
11	Hydrology	 Construction work in the riverbed will be done in dry season Proper drainage will be made beforehand 	Contractor	DEPC/PWD	Included in BoQ
18	Water use	 Same as water contamination A place for fetching water will be construction near the temporary bridge 	Contractor /WASAC	DEPC/PWD	Included in BoQ
19	Existing infrastructures and social services	 The relocation plan of infrastructures along the access road will be formulated and implemented, in consultation with owners of infrastructures. A traffic management will be planed The plan will be implemented, assigning a person who guides traffic and installing signboards, and so on 	Contractor	PWD/Police Force/Organiz ations concerned	Included in BoQ
26	Work Conditions including Work Safety	 Prepare for Work Safety Plan based on the Vanuatu laws and international standards such as OHSAS Provide safe goods such as masks and globes for workers Provide training programs of work safety and organize regular meetings with workers in order to promote awareness of work safety 	Contractor	PWD/	Included in BoQ
29	Accidents	 Development of a Community safety plan Take countermeasures such as disseminating information on construction work schedule, installing fences between construction site and houses, and assigning a trained guard, in order to prevent accidents Development of a traffic management plan Assign a guard to guide traffic and install signboards, in order to prevent accidents between trucks and private passenger vehicle 	Contractor	PWD/ Police Force/Local authority	Included in BoQ
	ation phase	• Monitor the river mount close in the	DWD		LISDEOO
11	Hydrology	Monitor the river morphology in the long term	PWD	PWD	USD600
29	Accidents	• Provide the information on new road		PWD	USD5000

No	Environmental	Suggested Actions and Mitigation	Implementing	Responsible	Cost
	Consideration	Measures	Agencies	Organizations	(USD)
		alignment on radio and other media and install signboardsCollect data on accidents			

1.3.1.10 Environmental Management and Monitoring Plan (Implementation details, Methodology and Cost)

The following Environmental and Monitoring Plan will be implemented in order to monitor mitigation measures during pre-construction, construction and operation/maintenance phase.

Environmenta l Issues	Monitoring Items	Parameter /Indicator	Location	Frequency	Responsible	Cost
Pre-construction	and site mobilization p	bhase				
Land expropriation, compensation payment and other support	Compensation for land and lost structure	Number of structures expropriated Area of land expropriated	Project area	Once before construction	PWD	RAP monitoring
	Complaints resolutions	GRM log book	Project area		DOL	RAP monitoring
Ecosystem	Site clearance activities	Approval of cutting trees Record of site clearance Records of waste disposal (Bouffa)				
Air Pollution/ Noise & vibrations	Equipment and automobiles with less emission gas and noise	Number of automobiles with certification on site		As appropriate	Contractor	No cost applicable to monitor.
Soil Erosion	Source of construction materials such as soil and stones	Quarry permission		once		No cost
Construction pha	ise					
Accident and Incident	Complaint (in general such as noise, traffic jam, and accidents)	Records of complaints	Project area		Contractor PWD	Constructio n cost
Air Pollution	Equipment and automobiles in good shape	Regular inspection and maintenance (daily check sheet)	Project area	Daily	Contractor	No cost applicable to monitor.

 Table 1.3-19
 Environmental Management and Monitoring Plan (EMMP)

Environmenta l Issues	Monitoring Items	Parameter /Indicator	Location	Frequency	Responsible	Cost
	Air quality	Level of dust: observed by	Project area	Daily	Contractor	Constructio n cost
		contractor Observed by community (community survey)		Quarterly		USD 2,000
	Mitigation measures such as spraying of water, washing tires, covering loaded materials	Records on water spay/ washing (check sheet)	Project area	Daily	Contractor	Constructio n cost
Water Contamination	Surface water quality	Temperature, pH, EC (by portable water quality meter) oil & grease (observation)	Upper site/ lower site of the river	Weekly	Contractor	US\$ 2,000
	Mitigation measures	Records of mitigation activities (check sheet)	Project area	Daily	Contractor	Constructio n cost
Noise and Vibrations	Restriction of noise/vibration emitting activities to working hours.	Noise level by portable noise meter Observed by community (community survey)	Project area	At the time of earth works Quarterly	Contractor	US\$ 1,000 (Along with air pollution)
Soil Contamination	Check prevention measures of oil contamination	Prevention measures are done or not (based on daily check sheet)	Project area	Monthly	Contractor	Constructio n cost
Soil Erosion	Check the conditions of river bank	Conditions (check sheet)	Project area	Monthly	Contractor	Constructio n cost
Waste	Management of excavated soil, concrete debris and others	Proper storage nor not (based on check sheet) reuse (check list)	Project area	Monthly	Contractor	Constructio n cost
Bed sediment/ Ecosystem	Management of general waste Mitigation measures	Records of waste disposal Mitigation measures are done or not (based on daily check sheet)	Project area Project area	Monthly Monthly	Contractor Contractor	Constructio n cost Constructio n cost
Work conditions	Occupational Safety and Health plan	Availability of OHS Plan		Monthly	Contractor	Constructio n cost

Environmenta l Issues	Monitoring Items	Parameter /Indicator	Location	Frequency	Responsible	Cost
1 1550C5	Meetings and	Number of				
	trainings	meetings and				
	trainings	trainings				
	Safety goods for	Number of		-		
	workers	workers with				
		safety gear				
	Noise and	(from noise and		(from noise	-	
	vibrations	vibrations)		and		
		,		vibrations)		
	Occurrence of	Records of	Project	Monthly	_	
	accidents and	accident and	area			
	injuries	injuries				
Accident/	Traffic	Availability of	Project	Monthly	Contractor	Constructio
Traffic	Management Plan	ТМР	area	-		n cost
Congestions						
	Implementation of	Availability of	Project	Monthly	Contractor	Constructio
	TMP	guard, signboard,	area	_		n cost
		and so on				
		(activity records)				
Water use	Mitigation	(from water				Constructio
	measures of water	pollution)				n cost
	quality					
	Conditions of place	Observation by the	Project	Monthly	Contractor	Constructio
	to fetch water	Contractor	area		community	n cost
		Observed by		Quarterly		(along with
		community				air
		(community				pollution)
		survey)				
Local	Local economy	Observed by	Communit	Quarterly		(along with
Economy	(sales,	community	ies near			air
	employment, and	(community	the project			pollution)
	so on)	survey)	area			
Operation phase	1	1				
Accident	Number of accident			Monthly	PWD	Operational
	Prevention					cost
	measures					
Hydrology	River morphology			One a year	PWD	Operational
	in downstream					cost
	Total cost for					USD 5,000
	monitoring					

Source: DEPC annual environmental audit (the Contractor will bear the cost)

1.3.1.11 Stakeholder Meetings

Formal stakeholder meetings were organized in three phases, (a) at the time of scoping, (b) during environmental, socio-economic and inventory survey phase, and (c) during drafting of EIA report/RAP phase. Notice of the meeting was given in advance in Daily Posts, along with on national radio and social medial especially Facebook.

These consultation meetings have been organized from May to December 2018 by participation of government agencies, landlords, community leaders and interested groups such as market vendors and female groups. The following were the main objectives of meetings:

- promote partnerships with stakeholder communities
- Information sharing on project and its components and activities •
- Communicate with stakeholders that their cooperation and participation is essential in Project activities including surveys, site investigations, planning, feasibility study and design, construction, monitoring and maintenance.

(1) **Project Scoping Phase**

The first two meetings held as stakeholder inception meetings to introduce the project and its scope. Outlines of these two meetings are summarized in the following Table 1.3-20.

1) Stakeholder consultation meetings on environmental & social considerations

,	Fable 1.3-20 Stakeholder Consultation Meeting			
Date:	23 May 2018			
Venue:	PWD Head Office – Conference Room			
Participants:	28 (Male – 21; Female – 7)			
Combination of	Local Residents – 14			
Participants:	• Officers from related government offices – 5			
	• JICA – 2			
	• JST – 7			
Agenda:	1. Presentation of the project (by PWD)			
	1) Objectives of meeting, 2) Background, 3) Review of former meeting (Dec.			
	2016), 4) Outline of the project, 5) Environmental & Social considerations in the			
	Project Area, 6) Compensation and Assistance, 7) Request for assistance, 8)			
	Tentative schedule, 9) Open forum.			

Source: JICA study team

Questions and Answers at the meetings are summarized in Table 1.3-21 below.

2. Exchange of opinions

No	Name	Questions/Suggestions	Responses
1	Harold	Priorities should be given to local residents in terms of jobs opportunities	This will be taken into consideration and will be informed to contractor (JST/PWD)
		for construction workers.	
2	J. Chabod	How about the acquisition of leased land in the upstream?	The acquired land will be compensated including properties based on the cost estimation report provided by the DOL. (JST/PWD).
3	Resident	How about compensation for properties?	All properties that will be affected by the project will be compensated and must be included in cost estimation report. (JST/PWD)
4	Resident	How about using acquired land for washing and swimming, etc?	The acquired land will not be fenced or restricted. So, residents can still use the land after the construction work finishes. It is necessary for the government to have unlimited access to this area for construction works and for maintenance purposes in the future. (JST/PWD)

 Table 1.3-21
 Questions and Answers

No	Name	Questions/Suggestions	Responses
5	SG SHEFA	Do we need compulsory acquisition, rather than just asking to have access to land?	The government intends to acquire land to minimize properties issue between government, and landowner during design, construction of concrete for river bank protection and also in the future for maintenance purposes. Some river works was stopped by one of tenant when the bridge was damaged by Cyclone PAM in 2015. The project has not continued since then. It is necessary to prevent this from happening again. (PWD)
6	Resident	Will concrete river protection cause any problems in future?	The works will include widening of the river from 30m to 50m, construction of concrete river bank protection wall to stop erosion on LHS upstream and a proper alignment of the river to ensure it flows in its correct path and also protect bridge from future disasters. (JST)
7	DOL officer	Ministry of Lands has received a letter from MIPU to start the process of compulsory land acquisition. DOL valuation team will then carry out their assessments with a submitted survey plan. Compensation will be done according to valuation report assessments and payments will be made to landowner. All rented properties will be also assessed for compensation. From now till 2019, all tenants should work closely with DOL to ensure they receive a fair compensation.	Noted (JST/PWD)

At the end of the meeting, PWD asked participants to help identify the unknown tenant for the leased land as shown in the map.

	Tuble Tie 22 Treparatory Standhorder Interprint Pretering		
Date:	13 June 2018, 0900 – 1100		
Venue:	PWD Head Office Conference Room		
Participants: 23	Local residents: 15 (M. Nasak et al)		
(Male: 16, Female: 7)	DOL: P. Gambetta, R. Aru		
Combination of Participants:	SHEFA Province : Z. Daniel		
	EIA Consultant (QC) : Y. Qualao		
	PWD : A. Nafuki		
	EIA consultant (AEA) : A. Williams, J. Williams		
Agenda:	Project Presentation		
	 Environmental & Social Impacts and Mitigation Measures 		
	Tentative Schedule		
	• Exchanging Ideas (Q&A)		
	Acceptance of the Project		

2) Preparatory Stakeholder Inception Meeting

 Table 1.3-22
 Preparatory Stakeholder Inception Meeting

Source: JICA study team

Questions and Answers at the meetings are summarized in Table 1.3-23 below.

			is and Answers
No	Name	Questions/Suggestions	Responses
1	Chief Representati ve K. Sandy	Compensation has been paid only for the expropriated farmland during the construction of the first bridge. Need to know the compensation policies clearly this time.	This is noted and will be taken up as part of the Consultation Process. This will be discussed with the government offices concerned too. (PWD/ JST)
2		Effluent from the landfill at Etas would pollute the water of Teouma River?	New bill passed in Parliament to deal with waste is a positive way forward. (JST)
3	Resident	Stated concern on safety of access to river water	Steps to access river water will be installed for the safe access to river water. (JST)
4	Chief rep	Is it expected to have more floods in the upstream areas due to increase in the elevation of road and blockage? Moreover, whether the increase in river width to 50 m will impact water flow/velocity or not?	Construction work will include excavation of river bed and an embankment to keep the elevation level enough for water flow. (JST/PWD)
5	Resident	Is sedimentation in the riverbed would cause more floods?	
6	Resident	Whether the drainage system planned to be installed under the access road could divert run-offs completely straight into river rather than block mid-way causing flooding on residential properties near the river banks?	It is taken note of and will be referred to project proponents for consideration in design. (JST/PWD)
7	Resident	Whether they will have another water source during the construction phase?	The Social Impact Assessment (SIA) will deal with concern during the consultation phase. (JST)
8	Chief rep	How river bank users will be compensated?	Director of Land (DOL) deals with land compensation process. DOL will evaluate damages to the agriculture products in gardens that need to be expropriated. DOL will work with PWD to verify boundaries. (PWD/DOL)
9	Resident	DOA has given them a form to fill up with lots of details of crops in their garden, etc. However, no support to fill it up. They need support on this.	EIA team will assist the residents to complete the forms. (JST)
10	Resident	Where will temp road be built?	At the moment, it is considering south of the current structure (JST/PWD)

 Table 1.3-23
 Questions and Answers

At the end of the meeting, participants agreed to hold next consultation meeting on Wednesday 20 June 2018 at Chief Jack Kalmet community hall.

(2) Survey Phase

1) First Public Consultation of the Environment & Social Impact Assessment (ESIA)

The third consultation meeting was organized as Public Consultation just before the start of the Environmental, Socio-economic and inventory survey. Outline of the meeting is summarized in the following Table 1.3-24.

	- · · · · ·		
Date:	20 June 2018, 0940 – 1145		
Venue:	Chief Andrew Kalpoilep's Community hall.		
Participants: 26	Local residents of project area: 15		
(Male: 19, Female: 7)	Local residents of other area: 2		
Combination of Participants:	DOL : I. Nango, D. Steve		
_	JICA : R. Boekara, K. Ohara		
	DEPC : O. Melenamu		
	PWD : U. Nafuki, A. Iatipu		
	EIA consultant (AEA and QC) : A. Williams, N. Tamara		
Agenda:	Project Presentation		
	Contents and schedule of the Environment and Social impact survey		

 Table 1.3-24
 Public Consultation of the Environment & Social Impact Assessment (ESIA)

Questions and answers at the meeting are summarized in Table 1.3-25 below.

Responses
)
)
ed and informed that they
e survey this week.
red (PWD/JST)
· · · · ·
with PWD will verify the
L/PWD)
IST)
has not decided yet, but
h of the existing road. The
vestigate which crops and
ld be affected. (JST)

Source: JICA study team

The EIA consultant asked participants from local communities to support ESIA survey. A community close to bridge agrees to meet with the consulting Team on Sunday 25th June 2018 at 3pm. They also agree to conduct interview survey with residents who work during daytime.

Paramount Chief has also agreed to utilize Chief Kalpoleb's community hall at any time for meetings and consultations related to the project.

(3) Draft Phase

1) Second Public Consultation of the Environment and Social Impact Assessment (ESIA)

The Public Consultation was organized in order to present the result of the ESIA survey including mitigation measures and to consult with stakeholders about the project plan. Outline of the meeting is shown in the following Table 1.3-26.

Date:	24 December 2018, 0945 – 1130		
Venue:	Chief Andrew Kalpoilep's Community hall.		
Participants: 20	Local Residents – 16		
(Male: 16, Female: 4)	Civil Servants (DOL& PWD - VGov) – 1		
Combination of Participants:	JICA - 1		
	AEA – 1		
	Other - 1		
Agenda:	Project Presentation		
	Environmental Conditions (EIA)		
	• Social Condition (Lands, Crops, Assets and Compensation including		
	business operations after the cut-off date)		
	Open Forum (Q&A/Discussions)		
	Acceptance of the Project		

 Table 1.3-26
 Public Consultation of the Environment & Social Impact Assessment (ESIA)

Source: JICA study team

The questions and answers at the public consultation are summarized in the following Table 1.3-27. The participants from communities in the project area asked mainly about policies and compensation procedures.

No	Name	Questions/Suggestions	Responses
1	Mr. Alilee	What is impacts of project on mamas market stall?	Markets stalls will be relocated and compensation for the loss of income will be arranged. (JST)
2		How will new bridge look?	The length will be extended to 58 m and the height increased by 3 m. (showing a slide)
3	Mr. Japheth	How about his leased land without pegs?	Due to the peg issues, revaluation has been done recently done by lands department. Original survey docs have required for the review.
4	Resident	Weather houses and other structures will be affected by project?	Any affected structures will be compensated. (JST)
5	Resident	Express concern about drainage system considered in the new road. It would be better than the current system?	The new design would improve the drainage functions. (JST)
6	Mr. Alilee	Weather riverbanks and walls will be enhanced? It is necessary to secure the access to the river water.	Yes, they will be enhanced. River steps will be installed. The locations will be decided based on the convenience of local residents. (JST)
7	Resident	Will construction work disturb commuters?	The detour will be constructed, and the construction work will not affect commuters.
8	Resident	Weather considering importance of access to clean water?	Yes, it is considered. (PWD/ JST)

9	Resident	Insisted to install pumps far away	This request is received. (PWD/JST)
		from river.	

At the end of the meeting, participants were asked the following questions:

- Do we support the project?
- Why we support or not?
- Will you be able to support the project?

All participants from local communities were supportive to thus project. Following people provided their motivation to support the project.

Commentator	Reason to Support			
Mr. Charles Rodin	Totally agree to support project.			
	The project will provide job opportunities for communities within and			
	surrounding the project area.			
Mr. Marakon Alililee	Fully support the project.			
	He believes design of new bridge will make it safer. He also mentioned water			
	issues are affecting communities. He says it is good to widen the river channel			
	with respect to climate change and potential more rainfall. Thus, communities			
	must support the project. More importantly the community population will			
	be given the priority to work in the project. He hopes it is not like some current			
	contractors of road works around Port Vila.			
Mr. Noel Takau (on behalf of				
Chief Andrew Kalpoilep)	He stated that bridge will help community members and so they will support			
	the project. It will facilitate and also encourage investors to come and invest			
	in the area. He further emphasized job opportunities for youths and			
	community members.			
Mrs Emma Japeth	Totally agree to support project.			
	She mentioned since the Chief and Landowner Rep have already promised to			
	support the project, all land and resource owners would like to do so.			
Other participants	They are all agreed to support the project to proceed.			
Number of participants who answ	rered yes or no to support the project			
Yes	14 participants (Approval rate: 100%)			
No	Zero			


1.3.2 Land Acquisition and Resettlement

1.3.2.1 Target Area for Action Plan

The following project components are selected as the priority project and become the target to develop a tangible land acquisition and resettlement action plan for the future project.

1. Rehabilitation Teouma Bridge	of	: Rehabilitation with extension of the old bridge from 30 m to 58 m and widening it from 6.5 m to 9.5 m.
2. Improvement Teouma River	of	: Improvement of both-side embankments and riverine from 250 m upstream to 110 m downstream of Teouma Bridge in 50 m width
3. Improvement access road	of	: Prevention of inundation and overflow by flood in upstream by increasing $+3$ m in elevation ($+3$ m)

Figure 1.3-9 shows locations of each component. Details of these project components are discussed in Chapter 2 of this report.



Source: JICA Study Team Figure 1.3-9 Location of Project Components

1.3.2.2 Outline of Laws and Regulations regarding Land Acquisition and Resettlement

(1) The Constitution 1980

The Constitution as "the supreme Law of Vanuatu, contains two sections related to land acquisition and resettlement. Chapter 5, Articles 29 to 32 of the Constitution refers to "National Council of Chiefs". Article 30, in particular, recognizes National Council of Chiefs membership having authority to discuss, and may be consulted on, any issue related to customs, culture and its preservation in any matter, as required by the National Government.

Chapter 12 is another chapter considering the traditional ties between Vanuatu nationals and the land. Therefore, the majority of discussions related to land have centered on Articles 30 (in Chapter 5) and Articles 73, 74, 75 and 76 of Chapter 12. However, it would be safer to consider all nine articles of Chapter 12 (articles 73 to 81) are related to Land Acquisition and Resettlement depending upon the situation. This following are summary articles:

• All land is owned by its traditional, customary owners; parliament prescribes the criteria for compensation payment for land;

- The Government may own and acquire land for State interest and may redistribute land away from traditional owners, in such cases as informal settlements and relocating of residents from other islands; and
- Disputes in land ownership.

(2) Land Reform Act 1980, last amended in 2014

This Act specifies all land titles are belonging to customary or transferred to the traditional owners, whose lineage can be traced back locally to 200 years. It specifically outlines indigenous owners and the non-indigenous land users.

(3) Land Leases Act 1988, last amended in 2013

The Act has 23 sections that discuss Land Records Office and laws regarding leases including its definition, terms, types, registration and obligations of landlord and tenant. Of relevance to a project are the discussions on requirement to provide rights of access, rights of water and rights to sites for government infrastructure.

The Act also discusses variation of agreements and condition of lease by the Ministry of Lands and Natural Resources (MOL). This is where a change of lease agreement using a prescribed form under this Act may be executed by both landlord and tenant prior to the expiration of the lease. A landlord also may sublease the land for the remaining life of the lease. The Act also includes the registration of caution or restrictions, including its definition such as mortgage or claims arising from bankruptcy, its placement and removal on a leased property. The leaseholder may also grant easement over his land. Fees imposed on subleasing of leaseholds are also provided in the Act.

(4) Land Acquisition Act 1992, last amended in 2000

The Act is the key law directly related to Land Acquisition and Resettlement. This Act, gives the MOL, full discretionary powers to acquire land on behalf of the Government. It covers to an extent, that which will be compensated under the Act:

- Compensation for damages made during the process of land valuation;
- Compensation entitlements for land and for rents and business losses;
- Basic rights for grievance and appeals; and
- Notice periods.

This Act does recognize market value compensation for land but is very vague in compensation entitlements for rents and businesses.

(5) Custom Land Management Act 2013, last amended in 2014

This Act strengthens the legal framework concerning title to custom land and also discusses management of custom land by customary institutions. It formalizes recognition of customary institutions termed 'NAKAMALS', which means the traditional meeting and 'Custom Area Land Tribunals' to determine the rules of custom as the basis of ownership and use of land in Vanuatu. In general, the Act aims at holding of custom land by owners as a cluster. Custom land means land owned or occupied, or land in which an interest is held, by one or more persons in accordance with the rules of custom. For the purposes of this Act, each island is divided into "Custom Areas". Larger islands are divided into many custom areas. The Act also provides for appointment of a National Coordinator of Land Dispute Management and provides with respect to the process of determination of custom owners and determination of land disputes by NAKAMALS or "Custom Area Land Tribunals and review of such determinations by court. A custom land must not be registered under the Land Leases Act unless the National Coordinator confirms by certification of the custom owners list, the names of the custom owners and the representatives of the custom owners, who may sign on behalf of the custom owners.

(6) Customary Land Tribunal Act 2001, last amended in 2014

As per the title, this Act details the set-up of the Customary Land Tribunal at village, island levels as well as its basic terms of reference (TOR) especially for dispute resolution and process for affected person to appeal the tribunal decision.

(7) Valuation of Land Act 2002

This Act stipulates relates to the organization of the "Valuation General Office" and their role. The Act does not stipulate minimum approach to valuation of the land, which is more directly specified in the "Land Acquisition Act". Furthermore, this Act is unclear about the role of the Valuation General Office in terms of relocation/involuntary displacement of households as well as valuation of structures, incomes and businesses.

1.3.2.3 Practices in Resettlement and Land Acquisition

(1) Identification of Areas for Acquisition

A majority of Government land acquisition in Vanuatu has been for smaller social services projects such as for village health facilities and educational institutions. The land acquisition legislation and process have not been utilized for urban development infrastructure projects. In the year prior to an infrastructure development project, each Ministry and other Government agencies will develop a work plans for the following fiscal year. This is inclusive of the other feasibility study requirements such as budgeting, environmental, engineering etc. At this time proposals for projects where land acquisition is involved should be submitted. This is subject to the approval of the Council of Ministers. There is no minimum standard that requires the projects to minimize land acquisition and impact on the community.

(2) **Process for Relocation and Land Acquisition**

On an annual basis, the Government allocates in its National budget 200 million VT (approximately 1.82 million USD, as of December 2018) for Government Land Acquisition projects. According to MOL, if the budget is not spent the remaining amount accrues on top of the normal, annual 200 million VT budget. In the event that the budget is used up, with finances still required, the Government and Ministry executing a project, is responsible to find further finances to cover the necessary Land Acquisition budget requirement.

Once a plot of land is selected for a government project, a notice signed by the Minister of MOL is provided to the customary owners/title holders and a public notice is erected in full public view. The notice is made for a minimum of 30 days.

After this period, the land is assessed and valued. The land valuation is stipulated by law, but generally involves valuing of the following:

- 1. Lease type residential/agricultural/commercial/special industrial;
- 2. Location of property from CBD, aesthetic view, amenities, waterfront, type of neighborhood;
- 3. Marketability number of properties marketed nearby in recent times and price range of those transactions;
- 4. Physical characteristics terrain, vegetation, soil type, improvements made and size; and
- 5. Intangibles interest, customary and other resource rights attached.

Valuations include both land and structures affected and may include value of income produced from land. However, this does not include "non-land producing" incomes such as income from shop business etc. Any damage to the land, caused by valuation investigations, is by law, liable for compensation to the existing owners. Once the valuation has been made and signed by the Minister, the owners have 30 days to file objections, at the same time, the MOL must disclose information on the valuation and proposed land acquisition over a 30-day period by radio at least 3 times on separate occasions, in one national newspaper each week, on the main notice boards and on the land itself. Objections must be lodged within this 30 days period, and on decision by the Minister, the objector, if dissatisfied, may appeal the Minister's decision through the Supreme Court of Vanuatu. However, if the issues are related to tradition and custom, then the National Council of Chiefs may be consulted, if necessary, although not compulsory.

(3) Carrying out the Acquisition of Land/Structures

After a 30-day notice period, and as long as all conflict claims and complaints are resolved, the physical compensation processes can then commence. The MOL is responsible for this process, monitored by the Ministry of Finance and Economic Management (MFEM). However, problems in moving through this stage may include complaints about the process of valuation to compensation itself; and process of the assessment of disputes. This is generally supposed to be settled through the Customary Lands Tribunal, or if unresolved, through the Supreme Court.

The land acquisition usually needs a period of 6 to 8 months from the application to completion. The period, however, can be shortened with the degree of project importance or interest by the Government of Vanuatu.

1.3.2.4 Comparison between JICA Policy and Vanuatu Resettlement Laws

(1) JICA Policy for Resettlement

JICA Policy for resettlement includes the following items:

- (a) Involuntary resettlement and loss of means of livelihood are to be avoided when feasible by exploring all viable alternatives.
- (b) When, after such an examination, avoidance is proved unfeasible, effective measures to minimize impact and to compensate for losses must be agreed upon with the people who will be affected.
- (c) People who must be resettled involuntarily and people whose means of livelihood will be hindered or lost must be sufficiently compensated and supported, so that they can improve or at least restore their standard of living, income opportunities and production levels to pre-project levels.
- (d) Compensation must be based on the full replacement costs as much as possible.
- (e) Compensation and other kinds of assistance must be provided prior to displacement.

- (f) For projects that entail large-scale involuntary resettlement, resettlement action plans must be prepared and made available to the public. It is desirable that the resettlement action plan include elements laid out in the World Bank Safeguard Policy, OP 4.12, Annex A.
- (g) In preparing a resettlement action plan, consultations must be held with the affected people and their communities based on sufficient information made available to them in advance. When consultations are held, explanations must be given in a form, manner, and language that are understandable to the affected people.
- (h) Appropriate participation of affected people must be promoted in planning, implementation, and monitoring of resettlement action plans.
- (i) Appropriate and accessible grievance mechanisms must be established for the affected people and their communities.
- (j) Above principles are complemented by World Bank OP 4.12, since it is stated in JICA Guideline that "JICA confirms that projects do not deviate significantly from the World Bank's Safeguard Policies". Additional key principle based on World Bank OP 4.12 is as follows.
- (k) Affected people are to be identified and recorded as early as possible in order to establish their eligibility through an initial baseline survey (including population census that serves as an eligibility cut-off date, asset inventory, and socioeconomic survey), preferably at the project identification stage, to prevent a subsequent influx of encroachers of others who wish to take advance of such benefits.
- (1) Eligibility of Benefits include, the PAPs who have formal legal rights to land (including customary and traditional land rights recognized under law), the PAPs who don't have formal legal rights to land at the time of census but have a claim to such land or assets and the PAPs who have no recognizable legal right to the land they are occupying.
- (m) Preference should be given to land-based resettlement strategies for displaced persons whose livelihoods are land-based.
- (n) Provide support for the transition period (between displacement and livelihood restoration.
- (o) Particular attention must be paid to the needs of the vulnerable groups among those displaced, especially those below the poverty line, landless, elderly, women and children, ethnic minorities etc.
- (p) For projects that entail land acquisition or involuntary resettlement of fewer than 200 people, abbreviated resettlement plan is to be prepared.

Source: JICA Guidelines for Environmental and Social Considerations, 2010

In addition to the above core principles of JICA Policy, it has also emphasis on a detailed resettlement policy inclusive of all the above points; specific resettlement plan; institutional arrangements for the plan implementation; monitoring and assessment; implementation schedule and detailed financial plan, etc.

(2) Comparison between JICA Guidelines and Vanuatu Related Laws

Table 1.3-28 discuses comparison and gap analysis of the policies for some key issues between JICA Guidelines for Environmental and Social Considerations, 2010, hereinafter referred to as "JICA Guidelines" and Vanuatu's relevant regulations. The gaps are treated basically in line with the JICA Guidelines as long as not violating laws in Vanuatu.

No.	JICA Guidelines	Vanuatu Related Laws/ Regulations	Differences	How to Bridge the Gap
1	[Avoidance of involuntary resettlement] Involuntary resettlement and loss of means of livelihood are to be	No provision.	There is no standard to minimize land acquisition and impact on the community.	The project shall adopt the objective of minimizing involuntary land acquisition and

 Table 1.3-28
 Comparison result of JICA Guidelines and Vanuatu Related Laws

No.	JICA Guidelines	Vanuatu Related Laws/ Regulations	Differences	How to Bridge the Gap
	avoided when feasible by exploring all viable alternatives.			resettlement impacts on community and business/ productive interests are avoided through careful technical design.
2	[Mitigation measures for displacement] When population displacement is unavoidable, effective measures to minimize impact and to compensate for losses should be taken.	No provision.	There is no standard to minimize land acquisition and impact on the community.	The project will ensure that all resettlement and land acquisition and impacts on community and business/ productive interests are minimized wherever possible.
3	[Securing livelihood and assistance] People who must be resettled involuntarily and people whose means of livelihood will be hindered or lost must be sufficiently compensated and supported, so that they can improve or at least restore their standard of living, income opportunities and production levels to pre- project levels.	 Compensation is determined based on issues including land type, crops etc. (Land Acquisition Act) Land is valued by Valuer- General in the MLNR. 	Compensation does not include "non-land producing" incomes such as income from shop business etc. Laws and practices in Vanuatu do not recognize the standards of living of the poor and vulnerable, in determining compensation for land acquisition and resettlement. There is no provision to improve or at least restore the livelihood of all DPs.	The project will ensure all resettlement and land acquisition and impacts on community and business/ productive interests are minimized whenever possible.
4	[Valuation based on replacement cost] Compensation must be based on the full replacement cost as much as possible.	 In Vanuatu valuation of land is stipulated by Law, and is conducted based on several factors regarding that specific plot of affected land such as lease and ownership type; location of property; amenities; market price of nearby properties; physical land characteristics; and intangibles. (Land Acquisition Act) The law specifically points out times for disclosure prior to valuation, time for objection to valuation and 	The law does not provide any clauses for prompt compensation, income restoration and entitlements.	The RAP includes a provision for restoration for APs under the project.

No.	JICA Guidelines Vanuatu Related Laws/ Regulations Differences		Differences	How to Bridge the Gap
5	[Compensation prior to displacement] Compensation and other kinds of assistance must be provided prior to displacement.	 acquisition of lands and assets. (Land Acquisition Act) Land is valued by Valuer General in MLNR. The VG will determine compensation requirements relating to land, land-based income losses. All other compensations (monetary and non-monetary) will be based on replacement at the existing market rates. Compensation will be provided after a period of disclosure and a period for settlements of objections. 	Legislation does not clearly state that compensation will be provided prior to commencement of construction, which	The project will ensure that land acquisition, resettlement and/ or compensation measures are
			force physical/ economic displacement impacts to occur.	completed prior to commencing of construction.
6	[Development and disclosure of RAP] For projects that entail large-scale involuntary resettlement, resettlement action plans must be prepared and made available to the public.	- Under Vanuatu Law, land acquisition and resettlement and compensation are carried out focusing on households affected and the values of the land and structures affected. (Land Acquisition Act)	An RAP per se is not necessarily required.	The project will ensure that a RAP is prepared and is updated at the time of detailed design.
7	[Holding public consultation meetings] In preparing a resettlement action plan, consultations must be held with the affected people and their communities based on sufficient information made available to them in advance.	- The law, and current practices, does require the land acquisition and relocation orders to be announced several times over radio and in the printed media for one month period and also display on project site. (ADB reports)	There is neither recognition of vulnerable groups nor the consultation with, or participation of APs/ DPs at any part of the process, except in the case of people given opportunity to make objections.	JICA GL will be enforced in that prepared RP and its implementation will require a level of participation and consultation.
8	[Use of local language] When consultations are held, explanations must be given in a form, manner, and language that are understandable to the affected people.	- A notice for land acquisition is writing in Bislama, English and French languages. (Land Acquisition Act)	Only the radio would be useful for the illiterate to become informed of any pending land acquisition and resettlement activity on a specific site.	The project will arrange public hearings/ meetings.
9	[Promoting public involvement]	- The law and current practices require that land acquisition and relocation	Only the radio would be useful for the illiterate to become	The project will arrange public hearings/ meetings.

No.	JICA Guidelines	Vanuatu Related Laws/ Regulations	Differences	How to Bridge the Gap
	Appropriate participation of affected people must be promoted in planning, implementation, and monitoring of resettlement action plans.	orders for a specific site be disclosed several times over radio and in the printed media for one month period, as well as display on project site. (ADB reports)	informed of any pending land acquisition and resettlement activity on a specific site.	
10	[Establishing grievance redness mechanism] Appropriate and accessible grievance mechanisms must be established for the affected people and their communities.	 Vanuatu already has a Grievance redress system for general village matters, followed by the chief. MLNR has also recently been set up at Provincial level, through the Customary Land Tribunal. (Land Acquisition Act, Customary Land Tribunal Act) 	No difference.	The project ensures an appropriate multiple level grievance redress system, which allows AP/DP participation, relatively rapid action and results, as well as encompassing existing grievance procedures.
11	[Identifying eligibility] Affected people are to be identified and recorded as early as possible in order to establish their eligibility through an initial baseline survey (including population census that serves as an eligibility cut- off date, asset inventory, and socioeconomic survey), preferably at the project identification stage, to prevent a subsequent influx of encroachers of others who wish to take advantage of such benefits. (WB OP 4.12 Para. 6)	- The law and current practice does specify census requirements and protocols for managing inflow of ineligible people. (Land Acquisition Act)	No difference.	For this project, a census of APs will be conducted including inventory of losses and basic socio- economic information at household level. The inventory of flosses will cover the value of impacted land, structures, business/ livelihoods and assets. The 'cut- off' date for the RAP will be the date when the inventory of affected people is completed and set out in the RAP.
12	[Eligibility requirements] Eligibility of benefits includes, the PAPs who have formal legal rights to land (including customary and traditional land rights recognized under law), the PAPs who don't have formal legal rights to land at the time of census but have a claim to such land or assets and the PAPs who have no recognizable legal right to the land they are occupying. (WB OP 4.12 Para. 15)	No provision	Laws have no clauses that recognize encroachers in any way to be entitled or NOT entitled to compensation or rehabilitation.	The project will recognize encroachers, who are legitimately affected at the time of the census/ detailed measurement survey conducted.

No.	JICA Guidelines	Vanuatu Related Laws/ Regulations	Differences	How to Bridge the Gap
13	[Land-to-land Compensation] Preference should be given to land-based resettlement strategies for displaced persons whose livelihoods are land-based. (WB OP 4.12 Para. 11)	- In Vanuatu, land acquisition, resettlement and compensation for land-based losses are included under the law. (Land Acquisition Act)	No difference	WB OP 4. 12 will be enforced to ensure that preference is given to land- based resettlement strategies for DPs whose livelihoods are land- based.
14	[Assistance during transition] Provide support for the transition period (between displacement and livelihood restoration). (WB OP 4. 12, para.6)	- In Vanuatu, land acquisition, resettlement and compensation for land-based losses are included under the law. (Land Acquisition Act)	Impacts on business and their employees are less clear and there is no recognizable transitional support mechanism under the law.	WB OP 4. 12 will be enforced in supplementing the Law of Vanuatu in order to cover transition assistance requirements, business and employees impacted, as required.
15	[Consideration to vulnerable group] Particular attention must be paid to the needs of the vulnerable groups among those displaced, especially those below the poverty line, landless, elderly, women and children, ethnic minorities etc. (WB OP 4.12 Para. 8)	No provision.	There is no recognition of vulnerable groups nor the consultation with or participation by APs at any part of the process, except in the case of people given the opportunity to make objections.	WB OP4.12 will be enforced. Prepared RAP and its implementation will require participation and consultation of vulnerable groups.

(3) Policy for Land Acquisition and Resettlement in the Project

As indicated in Table 1.3-28 crucial gaps are not identified in fundamental aspects despite of a few minor differences. For considering a more tangible policy in compensation and livelihood assistance in the future, the project examines a feasible way to satisfy both JICA Policy and Vanuatu laws in case there would be a gap between policies of these two frameworks.

1.3.2.5 Scale and Scope of Land Acquisition

The result of population census, asset valuation and socio-economic surveys are described in the following sections:

(1) Affected Households and Population

The number of affected households and population is shown in Table 1.3-29. Out of 8 households, 6 were family households and the rest of 2 were commercial facilities (a street stall for agricultural products and a tourism facility).

X 7 2 11	Affected Households			Affected Population		
Village	Legal	Illegal	Total	Legal	Illegal	Total
Teouma	8	0	8	148	0	148

 Table 1.3-29
 List of Affected Household and Population

Note: Approximately estimated 100 out of the 148 affected people are workers of a street stall for agricultural products.

(2) Affected Properties

1) Land

In Total 23,497 m² land will be affected in this project as it is shown in Table 1.3-30. Out of it, 4,123 m² (17.5% of the total) are leased farmland (agricultural land) and 19,374 m² (82.5% of the total) are customary land. In this project, leased farmlands are going to be compensated for eternal use and customary lands are going to be compensated both for eternal use and temporary use for temporary roads and so forth.

Village	Type of Use	Classification	Area (m ²)	Total (m ²)
Teouma	Permanent Use	Leased farmland (agricultural land)	4,123	12,561
		Customary Land	8,438	
	Temporary Use	Leased farmland (agricultural land)	0	10,936
		Customary Land	10,936	
	Total of Leased farmland (agricultural land)			4,123
	Total of Customary land			19,374
	Grand Total			23,497

 Table 1.3-30
 Affected Land

Source: JICA Study Team


The location and area of land and peripteries that are going to acquire by this project have been surveyed and determined by the Department of Lands, the Ministry of Climate Change Adaptation, Meteorology & Geo-Hazards, Energy, Environment and National Disaster Management Office (MCCA-DOL) based on the design result. The result of the land to be acquired for eternal and temporary use necessary in this project determined by DOL and it is shown in Figure 1.3-10. The red areas in the Figure are lands for eternal use for compensation and the yellow areas are lands for temporary use for compensation.

2) Structures

The affected structures are shown in Table 1.3-31. Out of 6 affected structures, one is residential, three commercial facilities, one cattle stall, and one house a subsidiary facility.

No.	Village	Type of Structure	Subtotal	Total
Residen	tial			
1	Teouma	Concrete one-story building	1	1
Comme	rcial Facilities			
2		Street stall for agricultural products	1	
3	Teouma	Ballroom for tourists	1	3
4		Kava Bar (Beverage Facility)	1	
Cattle S	tall			
5	Teouma	Pigsty	1	1
Facilitie	s with a House			
6	Teouma	Kitchen	1	1
G				

Table 1.3-31	Affected Structures
--------------	---------------------



Source: MCCA-DOL



3) Agricultural Products/ Trees/ Cattle

Table 1.3-32 shows affected agricultural products, trees and cattle.

	Table 1.5-52 Antered Agricultural Frounds/ Free/ Calue					
No.	Village	Type of Agricultural Products/ Trees/ Cattle	Subtotal	Total		
Agric	Agricultural Products					
1		Tomato	20			
2		Cucumber	20			
3	Teouma	Kumala (tubers)	100	440		
4		Cabbage	100			
5		Lettuce	200			
Trees						
6		Naus	1			
7		Sandalwood	1			
8		Banyan tree	2			
9		Mango	4			
10	Teouma	Nakatambol	4	90		
11		Coconut	5			
12		Natangra	7			
13		Pawpaw	15			
14		Banana	51			
Cattle						
15	Teouma	Pig	1	1		

 Table 1.3-32
 Affected Agricultural Products/ Trees/ Cattle

(3) Socio-Economic Situations

The following are result of socio-economic study of eight affected households.

1) Overview of Household Heads

a) Gender

Out of the eight households, 7 household heads are male (88%) except for the street stall for agricultural products. Householder of the street stall for agricultural products is considered as female as it is operated jointly by cooperation of women in neighborhood.

b) Age Composition

As is shown in Table 1.3-33 the mainstream of household heads is from their thirties to fifties. However, as the workers of the street stall for agricultural products are comprised of a wide age group from twenties to sixties, its age composition is considered as unspecified.

Tuble he de linge composition of household heuds				
Age Group	Number of Population	(%)		
Under 20	0	0		
21-30	1	12.5		
31-40	2	25.0		
41-50	2	25.0		
51-60	2	25.0		
Over 61	0	0		
Unspecified	1	12.5		
Total	8	100		

 Table 1.3-33
 Age Composition of Household Heads

Source: JICA Study Team

c) Educational Background

Table 1.3-34 shows the educational background of the household heads. 3 of them (37.5%), have finished secondary education (equivalent to junior high and high schools). Two (25.0%) have finished tertiary education (equivalent to universities). It was not able to specify the educational background of the workers of the street stall for agricultural products.

Educational Background	Number of Population	(%)
Primary	1	12.5
Secondary	3	37.5
Tertiary	2	25.0
Graduate	0	0
Vocational	1	12.5
Unspecified	1	12.5
Total	8	100

Table 1.3-34 Educational Background of Household Heads

Source: JICA Study Team

d) Occupation

Table 1.3-35 shows occupations of the household heads. Four self-employed (50.0%) are operating shops and Kava (local beverage) bars. The street stall for agricultural products is included in the category of the self-employed.

 Table 1.3-35
 Occupation of Household Heads

Occupation	Number of Population	(%)
Farmer	2	25.0
Self employed	4	50.0
NGO	1	12.5
Unemployed	1	12.5
Total	8	100

Source: JICA Study Team

2) Overview of Households

As for overview of households, the answers from 5 households out of 6 are summarized.

a) Household Size

Table 1.3-36 shows the household size. There was no household with less than five members, and the average household size was 9 members.

Tuble 1.5-50 Household Size				
Household Size	Number of Household	(%)		
Less than 5 members	0	0		
5-6 members	1	20.0		
7-8 members	1	20.0		
9-10 members	1	20.0		
11-12 members	2	40.0		
Total	5	100		

Table 1.3-36 Household Size

Source: JICA Study Team

b) Age Composition of Household Members

Table 1.3-37 shows the age composition of household members. The majority are younger generation (aged 20 or younger), followed by the twenties. Fifties and under consists mostly of the household members.

Age Group	Number of Members	(%)		
10 and under	6	13.0		
11-20	15	32.6		
21-30	9	19.6		
31-40	5	10.8		
41-50	9	19.6		
51-60	1	2.2		
61 and over	1	2.2		
Total	46	100		

 Table 1.3-37
 Age Composition of Household Members

Source: JICA Study Team

c) Educational Background of Household Members

Table 1.3-38 shows educational background of household members. As is the case with householders, the majority consisting of 23 members (50.0%) finished secondary education (equivalent to junior high and high school). There were 4 members (8.7%) in preschools. As a side note, the number of members for each educational background of primary and secondary education includes students being enrolled in those schools.

Table 1.5-50 Educational Dackground of Members				
Educational Background	Number of Members	(%)		
Preschool	4	8.7		
Primary	11	23.9		
Secondary	23	50.0		
Tertiary	4	8.7		
Graduate	0	0		
Vocational	3	6.5		
Unspecified	1	2.2		
Total	46	100		

 Table 1.3-38
 Educational Background of Members

Source: JICA Study Team

d) Occupation of Household Members

Table 1.3-39 shows occupation of household members. The majority consisting of 13 (28.3%) are agricultural workers (farmers), followed by the self-employed of 5(10.8%). Most of the unemployed are engaged in domestic help. Furthermore, the ratio of non-workers is also high; 16 students (34.8%) and 4 preschool children (8.7%).

Occupation	Number of Members	(%)
Farmer	13	28.3
Self employed	5	10.8
NGO	1	2.2
Student	16	34.8
Preschool	4	8.7
Unemployed	7	15.2
Total	46	100

 Table 1.3-39
 Occupation of Household Members

e) Household Income

Table 1.3-40 shows the annual income of 5 households who provided information. The minimum was 851,000 Vatu (approximately 7,530 USD). The poverty line defined by the Asian Development Bank (ADB) is 1.25 USD per day (approximately 141.3 Vatu per day), which means the poverty line of the average household size (9 members) per year is approximately 464,000 Vatu. Therefore, all above-mentioned households lived above the poverty line defined by ADB.

Annual Income Range (Vatu)	Number of Household	(%)
851,000-900,000	1	20.0
1,000,100-1,500,000	1	20.0
1,501,000-2,000,000	1	20.0
2,501,000-3,000,000	2	40.0
Total	5	100

 Table 1.3-40
 Household Income

Source: JICA Study Team

3) Opinion Regarding the Project

All affected households showed favor opening to the project. In addition, all households would like implementation of the project as soon as possible, implying a high expectation for the project.

4) Socially Vulnerable Households

All male householders were healthy at the time of survey. However, the members of the street stall for agricultural products consisted of some 100 women. Therefore, it could be regarded as the socially vulnerable household because the construction work might temporally disturb their income opportunity.

1.3.2.6 Policies for Compensation and Assistance

(1) Loss Compensation

Under this project, the followings are the target of compensation or at least livelihood assistance:

- Those that lose lands (including farm lands), structures, agricultural products, income, regular landuse rights and customary land-use rights by the implementation of this project.
- Tenant (regardless with or without registration)

The followings are details of compensation measures:

1) Land (Temporary use)

Qualified Persons: Lessees, Customary landholders, Tenant farmers

<u>Compensation Coverage</u>: Compensated by the leased land bill calculated based on the assessed value by the Valuation General Office of the Department of Land. It is calculated considering the market price.

Note: The duration is two years applied to the land for temporary roads.

2) Land (Permanent use)

Qualified Persons: Lessees, Customary landholders

<u>Compensation Coverage</u>: Compensated by the leased land bill calculated based on the value assessed by the Valuation General Office of the Department of Land. It is calculated considering the market price.

Qualified Persons: Illegal settlers

<u>Compensation Coverage</u>: Compensated for damages on non-land assets (agricultural products, trees, structures and etc.)

3) Agricultural Products and Trees

<u>Qualified Persons</u>: Producers of agricultural products (regardless of whether ones are legal or illegal)

<u>Compensation Coverage</u>: Made to be harvested as much as possible by issuing harvest notification before land acquisition. However, the agricultural products which cannot be harvested are going to be compensated at reasonable cost by cash.

4) Structures (Partial or total relocation)

Qualified Persons: Owners of structures (regardless whether ones are legal or illegal)

<u>Compensation Coverage</u>: Actual cost compensation necessary for damages and relocation by this project or assistance to search for a relocation site. Shops shall be paid for inconvenience fee during the interference of business.

5) Socially-vulnerable People

<u>Qualified Persons</u>: Households whose householders are the socially vulnerable affected by this project (householders are women, elderly persons or disabled persons, and the poor household)

Compensation Coverage: Livelihood assistance to householders by cash.

6) Relocation of Communal Facilities (if any)

Qualified Persons: Managers of such facilities

<u>Compensation Coverage</u>: Actual cost compensation necessary for the damages and relocation by this project or assistance for relocation.

7) Unforeseen or Unintended Impacts

Qualified Persons: Persons directly or indirectly affected by this project (unforeseen impacts)

<u>Compensation Coverage</u>: Applying the compensation coverage from a) to f), the others shall be compensated according to the JICA Guideline and etc.

The Cut-off date of this project is <u>20th of June 2018</u> which is the date of the public hearing before the start of this study.

(2) Livelihood Assistance Plan

Since this project is not going to cause resettlement or land acquisition in large scale, its impacts on the daily lives of residents are limited. Thus, it is not expected to cause forced loss or change of jobs. According to the socio-economic surveys and consultations, it became clear that the early implementation of this project is preferred. In addition, local residents expect to be actively employed as construction workers.

Furthermore, as the income of sellers and their related producers is going to be lost by the relocation of the street stall for agricultural products during the construction, livelihood compensation at uniform rate is going to be paid to the eligible persons.

(3) Entitlement Matrix

Table 1.3-41 shows the draft entitlement matrix which lists types of asset losses, application, definition of affected persons and compensation coverage.

Types of Loss	Application	Definition of Affected Persons	Compensation Coverage
Land for Temporary Use	Land to be used during construction	Lessor/ Lessee/ Customary Landholder/ Land user	Necessary to agree with landholders or affected persons. Affected landholders and persons shall be paid for an agreed lease expense. After use, the land shall be returned to owners after restoration of the land to its original condition.
Land for Eternal Use	Acquired land	Lessor/ Lessee/ Customary Landholder/ Land user	Compensation in money based on replacement cost or provision of land which has equivalent area and quality.
		Illegal settlers without legal rights (inside ROW)	Compensation for non-land assets (agricultural products, trees, structures and etc.) in land affected by this project.
Agricultural Products and Trees	Agricultural products and trees in affected land	Owners of agricultural products or trees (regardless with or without legal/ customary rights)	Harvest notification of agricultural products and trees is issued before land acquisition. If harvest is impossible, compensation is made in monetary form based on replacement cost (market price).
Partial or Total Clearance of Structures (Residence or Commercial Facilities)	Structures in affected land (residential or commercial)	All affected persons (regardless with or without legal rights)	Compensation for the costs of demolition or for transferring building materials or buildings themselves of structures based on replacement cost. In addition, support for the search for a relocation site. In case of building a new structure, it should be completed before the relocation of the covered structures. In case of commercial facilities, inconvenience fee shall be paid whose amount is equivalent to the duration

 Table 1.3-41
 Draft Entitlement Matrix

Types of Loss Application		Definition of Affected Persons	Compensation Coverage
			of impacts.
The Socially vulnerable	The socially vulnerable affected by the project (regardless with or without eligibility)	Socially vulnerable households specified by the socio-economic surveys (Its householders are female elder or disabled, or a poor household) and households severely affected	Livelihood support for householders of affected households including financial provision. Employment for construction works of this project.
Relocation of Communal Facilities (if any)	Communal facilities in affected land	A management representative specified through socio-economic surveys	Compensation by replacement cost based on market price for the affected parts of buildings. Necessary support for demolition and relocation of buildings for communities.
Unforeseen or Unintended Impacts	Impacts revealed by the detailed design	Affected residents	Application of a) to f) and compliance of the JICA guideline for any other cases.

1.3.2.7 Grievance Redress Mechanism (GRM) and Addressing Complaints

(1) Introduction

JICA Guidelines requires appropriate and accessible Grievance Redress Mechanisms (GRM) to be established for persons affected by involuntary land acquisition and also their communities. Specifically, OP 4.12 requires affordable and accessible procedures for third-party settlement of disputes arising from land acquisition. GRM should take into account availability of judicial recourse as well as community and traditional dispute settlement mechanisms.

In the Republic of Vanuatu, the affected people will be given several opportunities to review the survey results and compensation policies during the planning and implementation processes. In the course of the implementation, disputes may arise which require independent resolution. The affected people will be informed of their rights and GRM is available to them. These mechanisms include traditional forms of conflict resolution, legal and also political means.

Grievance and Complaints Procedures are set up to:

- Provide support to affected persons and affected parties on problems arising from land acquisition and associated impacts;
- Provide a means by which the various conflicting stakeholders may be consulted and negotiated agreement reached; and
- Specify names of and contact numbers of officers who will be responsible for handling grievance procedures.

(2) GRM and Addressing Complaints Procedures

It is discussed at different levels as in the following:

1) At Community Level

A community committee shall be set up by membership of department representatives, community representatives and representatives of the customary owners. The committee will meet in the case a complaint. A decision should be made within 7 days of the complaint being lodged. The committee will be chaired by the Village Chief. In the event that the Village Chief is a 'customary owner', the chair of the committee may be represented by the community's religious leader.

2) At Project Level

A complainant has the option to appeal at the project level if it is not satisfied with the decision at community level. The project level committee would be the same as the Project Management Unit (MIPU-PWD in this project). A decision must be made within 14 days of receipt of appeal.

3) Customary Land Tribunal

As per the current land acquisition law, the complainant may choose to appeal to the customary land tribunal if not satisfied with the project level decision. Under the law and current procedures in Vanuatu, a complaints procedure can last up to 30 days. The decision of the tribunal is generally final, unless the tribunal procedures are challenged.

4) Legal Procedures

Further appeal may be made through the Supreme Court of Vanuatu, only in the case that the customary tribunal procedures were faulty in the specific case.

1.3.2.8 Implementation System

(1) Driving Organizations

1) Public Works Department, Ministry of Infrastructure and Public Utilities (MIPU-PWD)

The MIPU-PWD is the main driving organization in this project and implements land acquisition and compensation through operating and supervising the project in coordination with related organizations. MIPU-PWD also receive budget at a suitable time during the RAP implementation to enforce.

2) Department of Lands, Ministry of Climate Change Adaptation, Meteorology, Geo-Hazards, Environment, Energy and Disaster Management (MCCA-DOL)

The MCCA-DOL is comprised of five sections such as 1) Land Survey, 2) Land Management, 3) Land Registry, 4) Customary Lands Tribunal and 5) Valuer General's Office. Therefore, the department is responsible for all procedures on land such as identification, valuation, computation of compensation values, tenure transfer and complaint handling for the land to be acquired, when endorsing a request from the project entity.

3) Ministry of Agriculture, Livestock, Forestry, Fisheries and Biosecurity (MALFFB)

The MALFFB plays a role in computing compensation for agricultural products and trees in land acquisition. The computation is based on the result of a socio-economic survey by the project entity. In collaboration with MCCA-DOL, the MALFFB evaluates the fair compensation values through confirming land classification and attribution.

(2) Supporting Organizations

1) Department of Environmental Protection and Conservation, Ministry of Climate Change Adaptation, Meteorology, Geo-Hazards, Environment, Energy and Disaster Management (MCCA-DEPC)

The MCCA-DEPC is responsible for all activities regarding the EIA in Vanuatu. A close collaboration with MCCA-DEPC is essential because land acquisition is tightly combined to the environmental policy.

2) Shefa Provincial Government

The Shefa provincial Government, in which the Teouma Bridge is located, collaborates with the central governmental units and local community mainly regarding land acquisition and complaint handling after being devolved by the central government.

3) Community in Teouma Area

In the community managed by the chief, most members are deemed stakeholders of the project. The chief is a title indicating a man who represents a community in a non-conventional context such as church or the state. The chief belongs to all communities, is selected with respect, and manages all issues regarding communities. The chief is a necessary person to conduct the project smoothly for acquiring customary lands and conflict resolution among the affected people.

4) NGOs

NGOs are those who support strict implementation of the project as a third party for land acquisition and external monitoring of compensation. For instance, Oxfam Vanuatu has been operating widely in Vanuatu dealing with gender issues to become prominent recently in the country. It has contributed to empowering the socially vulnerable and eliminating sexual violence.

1.3.2.9 Implementation Schedule

Table 1.3-42 shows the schedule for land acquisition/resettlement and compensation. The draft RAP will be amended and finalized with revising the location and area of the acquired land and re-computing the compensation values in case the content of overall designs would be revised during the detailed design stage. On the other hand, prior to these activities, the project entity establishes the project management unit, or PMU and GRM framework. In tandem with these activities, the project entity starts public consultations, advertising activity, complaint handling, and monitoring/ evaluation (internal and external) until the completion of the project. Negotiating with the affected people and attaining an agreement are commenced in accordance with the construction progress and payment of compensation shall be finished before resettlement. The project will start preparations of livelihood restoration assistance and others in tandem with the negotiation with affected people and its agreement.




Table 1.3-42 RAP Implementation Schedule

Source: JICA Study Team

1.3.2.10 Costs Estimation

Table 1.3-43 shows cost estimation for land acquisition and RAP implementation. The estimated costs will be updated in the review of RAP at time of the detailed design. Costs shown here shall be financed according to the budget rules of Vanuatu Island by project implementation organization (Public Works Department, Ministry of Infrastructure and Public Utilities: MIPU-PWD).

Item		Amount (Vatu)	Note
Properties	Land (Permanent Use)	22,899,000	Estimated based on valuation (replacement cost) by MCCC-DOL.
(Land/ Buildings) ^{*1}	Land (Temporary Use)	1,749,760	Valuation price by MCCC-DOL shall be discounted by the duration of use $(2+1 \text{ years})^{*2}$.
Dunuings)	Buildings/ Facilities with a Structure	730,000	Estimated based on replacement cost.
	Subtotal (1)	25,378,760	
Compensation/ Support	Agricultural products/ Trees	112,260	Estimated based on market price according to agricultural products and trees.
	Livelihood Support	300,000	Livelihood support for workers of the street stall for agricultural products and its suppliers who are forced to be relocated. It is estimated 10,000 Vatu per person for about 100 affected persons.
	Inconvenience Fee	400,000	Inconvenience fee paid to the tourism facility of Port Vila Cultural Tour located in the downstream of Teouma River that is expected to be affected by bank protection works. Inconvenience fee of 2,000 vatu per visitor is estimated to be paid for approximately 200 visitors.
	Support for Socially		Householders affected by this project are not socially
	Vulnerable	0	vulnerable and no need to relocation. Thus, this is
	Households		item is not applicable.
	Subtotal (2)	812,260	
	Total (3)	26,191,020	(1) + (2)

 Table 1.3-43
 Cost Estimation for RAP Implementation

Item		Amount (Vatu)	Note
RAP Activity Cost	(4)	3,928,650	15% of Total (3) (round-off)
Physical Contingency	(5)	1,505,980	5% of Total (3) + (4) (round-off)
Gra	Grand Total		(3) + (4) + (5)

*1: All lands to be acquired (leased and customary lands) are owned by the ministry of lands.

*2: Replacement Cost / Lease Period (50-75 years) * [Expected Duration of Use by this Project (2 years) + Original State Restoration & Preparatory Period (1 year)]

1.3.2.11 Monitoring System

A monitoring system will be conducted in order to evaluate resettlement activities are implemented as planned in the RAP or not. In the monitoring process regular data collection and analysis will be carried out throughout the entire resettlement activities.

(1) Internal Monitoring

The project entity (MIPU-PWD) will do supervision and in-house monitoring on implementation of the RAPs. So, they will be alternately called the Internal Monitoring Agent (IMA). The IMA will assign internal staff of MIPU or local consultants as the members of IMA. Tasks of IMA include:

- Regularly supervise and monitor the implementation of the RAPs in coordination with the related organizations and the community in Teouma area. The findings will be documented in the quarterly report to be submitted to JICA and the supervising body;
- Verify that the re-inventory baseline information of all project-affected households (PAHs) has been carried out and that the valuation of assets lost or damaged, the provision of compensation and other entitlements, and relocation, if any, has been carried out in accordance with the respective RAP;
- Ensure that the RAP is implemented as designed and planned; and
- Record all grievances and their resolution and ensure that complaints are dealt with promptly.

(2) External Monitoring

An External Monitoring Agent (EMA) will be commissioned by MIPU-PWD to undertake independent external monitoring and evaluation. The EMA for the project will be either a qualified individual or a consultancy firm with qualified and experienced staff. A local NGO, an academic institution or a local consulting firm may be commissioned for the EMA. The tasks of the EMA shall include:

- Verify results of internal monitoring;
- Verify and assess the results of the information campaign for PAHs rights and entitlements;
- Verify that the compensation process has been carried out with the procedures communicated with the PAHs during the consultations;
- Assess whether resettlement objectives have been met; specifically, whether livelihoods and living standards have been restored or enhanced;
- Assess efficiency, effectiveness, impact and sustainability of resettlement and implementation;

- Review on how compensation rates were evaluated; and
- Review of the handling of compliance and grievances cases.

(3) Monitoring Indicators

The monitoring indicators are set based on the ones shown in the LARRIPP in accordance with the conditions of priority projects and affected people. Table 1.3-44 and Table 1.3-45 show the monitoring indicators for internal and external monitoring activities in this RAP. The major monitoring indicators are as below.

• Internal Monitoring

Budget and timeframe, delivery of compensation and entitlements, public participation and consultation, benefit monitoring.

External Monitoring

Basic information on PAHs, restoration of living standards, restoration of livelihoods, levels of PAH satisfaction, effectiveness of resettlement planning, other impacts (unintended impacts).

Monitoring Indicators	Basis for Indicators						
1. Budget and	• Have all land acquisition and resettlement staff been appointed and mobilized for the						
Timeframe	field and office work on schedule?						
	• Have capacity building and training activities been completed on schedule?						
	• Are resettlement implementation activities being achieved against the agreed						
	implementation plan?						
	• Are funds for resettlement being allocated to resettlement agencies on time?						
	Have resettlement offices received the scheduled funds?						
	• Have funds been disbursed according to the RAP?						
	• Has the social preparation phase taken place as scheduled?						
	• Has all land been acquired and occupied in time for project implementation?						
2. Delivery of	• Have all Affected Persons (APs) received entitlements according to numbers and						
Compensation and	categories of loss set out in the entitlement matrix?						
Entitlements	• Have APs received payments for affected structures and lands on time?						
	• Have APs losing from temporary land borrow been compensated?						
	• Have all received the agreed transport costs, relocation costs, income substitution						
	support and any resettlement allowances, according to schedule?						
	• Have all replacement land plots or contracts been provided? Was the land developed as						
	specified? Are measures in train to provide land titles to APs?						
	 How many APs resorted to expropriation? 						
	How many APs households have received land titles?						
	• How many APs have received housing as per relocation options in the RAP?						
	• Does house quality meet the standards agreed?						
	 Have relocation sites been selected and developed as per agreed standards? 						
	• Are the APs occupying the new houses?						
	• Are assistance measures being implemented as planned for host communities?						
	 Is restoration proceeding for social infrastructure and services? 						
	• Are the APs able to access schools, health services, cultural sites and activities at the						
	level of accessibility prior to resettlement?						
	• Are income and livelihood restoration activities being implemented as set out in						
	income restoration plan? For example utilizing replacement land, commencement of						
	production, numbers of APs trained and provided with jobs, micro-credit disbursed,						
	number of income generating activities assisted?						
	 Have affected businesses received entitlements including transfer and payments for net 						
	losses resulting from lost business and stoppage of production?						
	iosses resulting from lost business and stoppage of production:						

 Table 1.3-44
 Internal Monitoring Indicators

Monitoring Indicators	Basis for Indicators							
3. Public Participation and	• Have consultations taken place as scheduled including meetings, groups, and community activities? Have appropriate resettlement leaflets been prepared and							
Consultation	distributed?							
	• How many APs know their entitlements? How many know if they have been received							
	• Have any APs used the grievance redress procedures? What were the outcomes?							
	• Have conflicts been resolved?							
	Was the social preparation phase implemented?							
4. Benefit	• What changes have occurred in patterns of occupation, production and resources use							
Monitoring	compared to the pre-project situation?							
	• What changes have occurred in income and expenditure patterns compared to pre-							
	project situation? What have been the changes in cost of living compared to pre-project							
	situation? Have APs' incomes kept pace with these changes?							
	• What changes have taken place in key social and cultural parameters relating to living standards?							
	What changes have occurred for vulnerable groups?							

	Table 1.5-45 External Wollitoring Indicators							
Monitoring Indicators	Basis for Indicators							
1. Basic	Location							
Information on	 Composition and structures, ages, education and skill levels 							
PAHs	Gender of household head							
	Ethnic group							
	 Access to health, education, utilities and other social services 							
	Housing type							
	 Land use and other resource ownership patterns 							
	Occupation and employment patterns							
	Income sources and levels							
	 Agricultural production data (for rural households) 							
	 Participation in neighborhood or community groups 							
	• Access to cultural sites and events							
	Value of all assets forming entitlements and resettlement entitlements							
2. Restoration of	• Were house compensation payments made free of depreciation, fees or transfer costs to							
Living Standards	the APs?							
	 Have perceptions of "community" been restored 							
	Have APs achieved replacement of key social cultural elements?							
3. Restoration of Livelihood	• Were compensation payments free of deduction for depreciation, fees or transfer costs to the APs?							
	• Were compensation payments sufficient to replace lost assets?							
	• Was the replacement place affordable at a proper level of cost?							
	• Did transfer and relocation payments cover these costs?							
	• Did income substitution allow for re-establishment of enterprises and production?							
	• Have enterprises affected received sufficient assistance to re-establish themselves?							
	• Have vulnerable groups been provided income-earning opportunities? Are these effective and sustainable?							
	• Do jobs provided restore pre-project income levels and living standards?							
4. Levels of APs'	How much do APs know about resettlement procedures and entitlements? Do APs							
Satisfaction	know their entitlements?							
	• Do APs know if these have been met?							
	• How do APs assess the extent to which their own living standards and livelihood been							
	restored?							
	How much do APs know about grievance procedures and conflict resolution							
	procedures? How satisfied are those who have used said mechanisms.							

 Table 1.3-45
 External Monitoring Indicators

Monitoring Indicators	Basis for Indicators
5. Effectiveness of	• Were the PAHs and their assets correctly enumerated?
Resettlement	 Was the time frame and budget sufficient to meet objectives?
Planning	• Were entitlements too generous?
	 Were vulnerable groups identified and assisted?
	• How did resettlement implementers deal with unforeseen problems?
6. Other Impacts	• Were there unintended environmental impacts?
-	Were there unintended impacts on employment or incomes?

1.3.2.12 Public Consultation

Public consultations on resettlement issues were held together with those for Environmental Impact Assessment (EIA) as impacts on project area and local people are considered minimum. The detailed contents of the consultations are explained in 1.3.1 Environmental Impact Assessment. Opinions and responses regarding land acquisition and compensation as well as interest in the project have been observed through 4 consultation meetings are presented in Table 1.3-46.

Table 1.5-40 Outlines and Opinions/Attitude from Farticipants in each Consultation									
Meeting No. & Date	Objective & Background	Major Questions & Opinions	Responses	Favor/ Disfavor					
1st 23 May 2018	Project introduction, request of cooperation and exchange ideas among related organizations and local representatives	 Scheme of land acquisition and compensation manner to make sure of a fair compensation River water use by local people in the future (whether laundry could be disturbed or not) 	 The value of compensation is computed through the site survey and will be paid to PAPs in line with JICA guidelines and domestic laws. Alternative sites are placed during construction. The planned embankment has facilities to access the river water. 	All participants expressed positive attitude and promised full cooperation.					
2nd 13 June 2018	Project introduction and also local contractor, request of cooperation and exchange ideas among related organizations and local representatives	 Confirmation of implementing of a fair compensation as of some problems in the past. Effectiveness of flood control project (Discharge capacity after widening river course and building embankments) Compensation for crops & trees. It is not easy to make a detailed list of crops for DOA. 	 The value of compensation will be estimated through a site survey and will be paid to PAPs in line with JICA guidelines and domestic laws. This project will contribute to flood controls in this area and the designs discharge will be based on a fair flood return period. Compensation will be estimated and paid based on market transaction values. 	Ditto					

 Table 1.3-46
 Outlines and Opinions/Attitude from Participants in each Consultation

Meeting No. & Date	Objective & Background	Major Questions & Opinions	Responses	Favor/ Disfavor
3rd 20 June 2018	Public consultation before on-site survey Outline of on-site survey, request of cooperation and exchange ideas (Informing cut-off date to local residents and stakeholders)	 The project is essential to Teouma area and there are no disputes on lands by area chief. Wish to implement compensation without failures (From a bad experiences in the past) Wish to know a particular leased or managing land would be involved or not 	 Noted. We would fully like to request local cooperation. The value of compensation will be estimated through the site survey and will be paid to PAPs in line with JICA guidelines and domestic laws. It will be revealed thru the on-site survey. However, a draft map has been showed for land acquisition 	Ditto
4th 24 Dec. 2018	Public consultation after on-site survey Outline of the results of on-site survey, request of cooperation and exchange ideas (To same stakeholders as the 3rd consultation)	 Impact on a stall along the road How to treat the leased land without border pegs? Wish to implement the project ASAP 	 We consider compensation for relocation. Livelihood assistance could be optional if necessary. DOL carried out a cadastral survey to clarify the boundary. Noted. We would fully like to request your cooperation. 	Ditto

In the 1st and 2nd consultation meetings, JICA survey team fostered enhancement of an understanding and cooperation for the project toward the related organizations and local representatives (including affected people) through interpreting the project. In the 3rd and 4th consultation meetings, all participants showed positive opinions and favor to the project since a mutual understanding had been developed in Teouma area. All stakeholders hope a rapid implementation of the project due to obtaining a high countenance since the pre-survey in 2016.

A steady implementation of compensation and supports in accordance with relevant laws was requested by some participants. They have experienced insufficient compensation and land expropriation for a public work in the past. In addition, an affirmative engagement of local people was requested during the construction phase.

1.3.2.13 Gender Equity

Attention to gender is essential. It is essential for women and men to equally benefit from and to participate in projects and do their best to avoid inequality. This study is to confirm policies and institutional arrangements related to gender equity as well as efforts on this by other donors. In case of land acquisition and resettlement, the study shall consider:

- 1) The gender balance of stakeholder consultation meetings;
- 2) The gender composition of project affected peoples,
- 3) Special considerations for female headed households and socially vulnerable households; and
- 4) Appropriate and steady measures for compensation and livelihood support.

In Vanuatu the Protection in the Pacific (ProPa) Network is established between the government and women's organizations in order to respond to cyclones and the climate change by the support of the UNDP. This study shall confirm the contents and directions of these activities for their use and application in this project.

The Government of Vanuatu addresses gender mainstreaming by formulating "National Gender Equality Policy 2015-2019⁵". The number of violence cases against women is still high and the women's social advancement is delayed. Therefore, considerations for and advancements of women is an urgent issue. The policy sets the following six principles:

- 1. The fundamental rights and freedoms of all men and women in Vanuatu are enshrined in the Constitution.
- 2. Gender equality is about all men and women.
- 3. Gender mainstreaming is a commitment in the Government agenda.
- 4. There is a high level of diversity among men and women and it must be recognized that women are more vulnerable than men.
- 5. The strategies and actions identified in this policy are practical, achievable, measurable and relevant to the Vanuatu context.
- 6. The policy framework is not prescriptive.

Furthermore, the policy prioritizes the following four strategic areas:

- 1. Reducing Domestic and Gender Based Violence
- 2. Enhancing Women's Economic Empowerment
- 3. Promoting Women's Leadership and Equal Political Participation
- 4. Building a Foundation of Gender Mainstreaming

With respect to the climate change, Vanuatu ratified the Convention on the Elimination of All Forms of Discrimination against Women (CEDAW) in 1995 and established the National Advisory Board on Climate Change & Risk reduction Project Management Unit (NAB-PMU) under the parliament in 2012. Though NBA-PMU in 2013, Vanuatu achieved gender participation in response to the increase of women in the process of the United Nations Framework Convention on Climate Change (UNFCCC). As a result, the half of the delegation from Vanuatu was women for the Conference of the Parties (COP) 19 held in Poland in 2013. In this way, it can be said that Vanuatu has addressed the advancement and utilization of women nationwide and recognized women as important actors in the field of disaster management. On the other hand, the followings are the current issues facing Vanuatu:

- Low rate of participation of women in disaster mitigation organizations;
- Limited participation of women at the community level;
- The Vanuatu Humanitarian Team (VHT) and the parliament struggle in order to ensure gender mainstreaming in policies for the climate change and disaster mitigation management. However, the activity still remains at the governmental level and does not spread to the citizen level; and

⁵ https://www.pacificclimatechange.net/sites/default/files/documents/NationalGenderEqualityPolicyJuly 2015.pdf

• Limitation of capacity of the Department of Women Affairs (DWA) in order to ensure gender mainstreaming at all levels of governments.

A relevant project to this project is the Cyclone Pam Road Reconstruction Project⁶ funded by the Asian Development Bank (ADB). The purpose of the project is to provide an opportunity to improve gender equality by securing continued access to markets, government services and basic social facilities (healthcare and education) to pregnant women, mothers of infants and children as well as men. The details are as below.

- Provision of concrete steps and footpaths to the edge of freshwater to make its access easy and construction and improvement of laundry facilities (for example in Mele, Tanoliu, Epau, Pangpang and Rentapau);
- Universal access provisions of all communal facilities (for example in Prima, Mele, Creek Ai, Tanoliu, Marona, Sara Epule, Lamin and Pangpang); and
- Provision of opportunities to secure income for women during construction (employment of nonskilled labor, procurement of local food and etc.).

One of NGOs active in Vanuatu on a large scale is Oxfam Vanuatu. It implements the following programs concerning gender support in collaboration with Oxfam Australia⁷.

1. Australian Humanitarian Partnership: Disaster Ready – Vanuatu

Humanitarian support program for four and half years (2018-2022) focusing on the enhancement of disaster resilience, the establishment of cash transfer schemes and the promotion of humanitarian collaboration in cooperation with the government of Vanuatu and local organizations.

2. Vanuatu Governance, Leadership and Accountability

Support program for the socially vulnerable for seven years (2012-2019) focusing on sharing purposes and achieving positive effects by reflecting the voice of the socially vulnerable including women in decision making.

3. Vanuatu Gender Justice, Youth and Livelihoods

Support program for the socially vulnerable for three years (2016-2019) promoting livelihood supports and facilitation of the access to resources and participation in policy making targeting at the socially vulnerable including LGBTQI⁸.

4. Pacific Climate Change Collaboration, Influencing and Learning

Participation program for the measures against the climate change for four years (2018-2022), with the purpose of reflecting opinions in the Pacific Islands Climate Action Network through gender equality activities.

5. Unblocked Cash: Piloting Accelerated Cash Transfer Delivery in Vanuatu

Development program of a multi-purpose cash transfer platform for one year (2018-2019) for the purpose of improving the speed of cash transfer, transparency and cost efficiency in Vanuatu and its surrounding areas with the aid of brock-chain technology.

⁶ ADB Vanuatu: Cyclone Pam Road Reconstruction Project (49319-001)

https://www.adb.org/projects/49319-001/main#project-overview

⁷ https://www.oxfam.org.au/country/vanuatu/

⁸ An abbreviation for Lesbian, Gay, Bisexual, Transgender, Queer and Intersex

CHAPTER 2 Contents of the Project

2.1 Basic Concept of the Project and Design Policy

2.1.1 Basic Concept for Flood Disaster Countermeasure

The following manual and guidelines highlight hydrological and hydraulic design such as setting-up of a freeboard and also flood return period:

- Vanuatu Resilient Roads Manual as a design guide for low volume rural roads in Vanuatu based on accessibility, security and sustainability (Australian Aid, June 2014)
- AUSTROADS Bridge Design Code, June 1998

Hydrological parameters for design are summarized in the following Table 2.1-1 using above documents:

Manual /Guidelines		oad Manual (VRRM)	AUSTROADS Bridge
Parameters	Minimum ARI	Desired ARI	Design
Secured Safety			
for Major Bridges	50-year	100-year	100-year ARI
for small Bridges	10-year	50-year	
Freeboard	-	-	500 mm
Remarks			Flooding could be considered in 100-year ARI

 Table 2.1-1
 Hydrological Parameters for Design

ARI: Average Recurrence Interval (Flood Return Period)

Source: JICA study team

Considering the importance of the ring road in Efate Island and the related ADB reconstruction project, policies for flood disaster countermeasures are summarized as follows:

- Bank protection structures shall be installed along the riverbank under erosion to prevent local scouring and washout damages around the bridge abutment. The structural damages occurred during Cyclone Pam in 2015.
- For this purpose, riverbank protection works shall be planned for 250 m of upstream and 100 m of downstream of the bridge.
- Furthermore, the main objectives of the above-mentioned river improvement works are prevention of bank erosion and also fixing of meandering channel. In the case of flood inundation risk in large flood such as 100-year design flood, floodwater in the river channel will flow downstream safely.

The followings are also solid working policies:

- Two-dimensional flooding simulation model will be set-up based on interview results of flooding situation during Cyclone Pam. The computation results of this 2-D flood simulation shall be utilized in bridge improvement design and necessary river improvement.
- 100-year return period flood shall be considered hydrological and hydraulic computation through the two-dimensional flooding simulation for alternative study on river and bridge improvement.
- In parallel with 100-year return period, 50-year return period flood shall be examined as well.
- Approximate cost of alternatives and their socio-economic impacts shall be examined comprehensively so that the optimum plan would be proposed.


2.1.2 Policies for Flood Disaster Countermeasure

(1) Model Configuration of Two-dimensional Flooding Simulation

Two-dimensional simulation model is constructed in the following procedure:

- Digital elevation model (DTM) of 10 m grid is developed after confirmation of good agreement between topographic data produced by LIDAR survey provided by Department of Land, Vanuatu as well as results of river cross-section and also road longitudinal section survey.
- Initial conditions for simulation such as water level at river mouth and flood hydrograph are already described in "1.2 Natural Conditions (Climate and Hydrology)" in the preceding Chapter.
- Observed daily rainfall of 514 mm in Bauerfield during Cyclone Pam is nearly equivalent to 50-year return period. Since hourly and spatial distribution of daily rainfall are unknown, a probable 50-year daily rainfall is used for identification of the simulation model. The highest flood level of 7.6 m at Teouma Bridge during Cyclone Pam is an index for verification of the model. Roughness coefficients of 0.035 in river channel and 0.20 of floodplain are obtained through trial and error. As the results of model simulation, a peak discharge of 650 m³/s might pass through the bridge. In addition, 60 m³/s overtop flow might be observed in 200 m width of the ring road on the left bank. The simulation results are illustrated thus:

The results of the simulation are shown in Figure 2.1-1.



Remarks: Maximum flood depth is depicted throughout the flood time. Source: JICA study team

Figure 2.1-1 Results of Flooding Simulation during Cyclone Pam

(2) Hydraulics Computation for River Width

From this point of view, The relationship between river width and hydraulic parameters in the river channel countermeasure section (about 400 m in length) shown in the "Data Collection Survey in 2017" are examined, and the results are shown in Table 2.2-1 and Figure 2.1-2.

In particular, the following items should be secured for a stable hydraulics flow condition:

- Average flow velocity should be kept lower than around 3 m/s in the bridge section.
- The flow capacity along with widening river width should be increased effectively.


Comparing the computation results illustrated in Figure 2.1-2, 50 m channel width is considered optimum. Flood discharge capacity of river channel is limited due to overbanking flooding in the

immediately upstream of the bridge. They are 680 m³/s (50-year flood return period) and 920 m³/s (100-year flood return period). The exceeding flood discharge overflows in the upper reaches and causing floodplain inundation are 40 m³/s and 100 m³/s for 50 and 100-year return period, respectively. In this case, less than 5 m³/s in 50-year and about 30 m³/s in 100-year will flow toward east along the upper part of the ring road.

Flood Magnitude		50-yr			100-yr					
River Channel Condition (Width)	Existing (30 m)	40 m	50 m	60 m	100 m	Existing (30 m)	40 m	50 m	60 m	100 m
Peak Discharge at Teouma Bridge (m ³ /s)	650	665	670	675	680	850	890	920	920	920
Overflow Discharge on the Ring Road(m ³ /s)	60	45	40	35	35	110	80	60	60	60
Water Level at Teouma Bridge (m MSL)	7.59	7.77	7.83	7.91	7.96	8.15	8.29	8.39	8.51	8.60
Flood Velocity at Teouma Bridge (m/s)	4.35	3.00	2.49	1.85	1.06	5.06	3.63	3.07	2.29	1.31

 Table 2.1-2
 Results of Hydraulics Analysis for Channel Widening

Source: JICA study team






Figure 2.1-2 Changes of Hydraulics Parameters in River Widening

(3) Comparative Study of Alternatives


Premises of Comparative Study and Alternatives in Brief

It is better to summarize premises for comparative study prior to setting-up of alternatives and conducting hydraulics computation as follows:

- Water level in 100-year return period flood is computed at 8.39 m for 50-m wide channel. Therefore, High Water Level (HWL) can be set at 8.4 m.
- Freeboard: By considering 0.5 m freeboard following guidelines, the soffit level of Teouma Bridge would be 8.9 m.
- Considering Steel I-girder type as described in the section 2.2.1.7 (4) of this section, the structural height is 1.5 m. Therefore, the proposed road elevation would be 10.4 m.

For that reason, the road surface will be elevated from the existing 7.7 m up to 10.4m. Flood disaster mitigation alternatives are how to approach from the planned bridge to the existing road surface on the left bank. The following are the proposed alternatives and their conceptual longitudinal profile is depicted in the following too:

- *Alternative Road Embankment Alt.:* Embankment road with height of 8.7 m above MSL will be planned from the bridge surface to convex ridge at a distance of 340 m east in order to discharge fully through bridge section.
- **Road Embankment & Drainage Culvert Alt.:** Box culvert (2.5 m x 2.5 m in 2 cells) with bottom height of 5 m above MSL along the lowest part of the existing ring road will be installed to discharge flooding water. Embankment road will be planned at elevation of 8.4 m above MSL with covering earth of 1.0 m thick.
- *Road Embankment & Overflow Section:* Approach road will decline with a slope of 3% connecting to the bottom of existing road, and will follow the existing ring road. Flood water will overtop the reinforced overflow section.





Comparative Study of Alternatives

Hydraulics parameters of alternatives by flood magnitude, 50-year and 100-year ARI (flood return period) are shown in Table 2.1-3 below. Flooding simulation results are also illustrated in Figure 2.1-4 and Figure 2.1-5 respectively.


Flood Magnitude		50-yr				100-yr					
Alternatives	Existing	Hmbank	ment &	Embank- ment & Overflow	Existing	Embank- ment	ment &	Embank- ment & Overflow			
Peak Discharge at Teouma Bridge (m ³ /s)	650	710	690	670	850	960	940	920			
Overtopping Discharge or Outflow through Box Culvert (m ³ /s)	60	0	20	40	110	0	30	60			
Water Level at Teouma Bridge (m MSL)	7.59	7.83	7.84	7.83	8.15	8.37	8.38	8.39			
Flow Velocity at Teouma Bridge (m/s)	4.35	2.61	2.53	2.51	5.06	3.21	3.14	3.07			
Water Level Upstream of Ring Road (m MSL)	7.80	8.05	7.93	7.72	8.38	8.63	8.56	8.35			
Water Level Downstream of Ring Road (m MSL)	7.74	7.55	7.76	7.66	8.32	8.11	8.29	8.26			

 Table 2.1-3
 Comparative Study on Hydraulics Parameters of the Alternatives

Flood Magnitude	50-yr			100-yr				
Alternatives	Existing	emnank-	ment &	Embank- ment & Overflow	Existing		ment &	Embank- ment & Overflow
Flow Velocity through Box Culvert (Case B)/of Overtopping Flow (Case C)(m/s)	-	-	1.67	0.48	-	-	2.10	0.50


Comparative study results are summarized in Table 2.1-4.

Based on the non-deterioration principle, road embankment alternative is ruled out at first. Compare to two remaining measures, Road Embankment and Drainage Culvert Alternative would be selected because as it is cheaper with almost similar effect as the other option.



Source: JICA study team

Figure 2.1-4 Result of Flooding Simulation by Alternatives in 50-year return period flood



Source: JICA study team

Figure 2.1-5 Result of Flooding Simulation by Alternatives in 100-year Return Period Flood


					Evaluation			
	Road Improvement	Flood Disaster			Druidution			
	(With/Without Overtopping)	Mitigation Measures	Flood Disaster Mitigation Effects	Cost	Land Acquisition	Convenience & Safety of Road	Traffic Safety	Overall Evaluation
	Ring road shall be	Embankment road	Flooding situation in the upstream of	Low	Due to embankment	All-weather	Fair	Medium
Road	elevated with soil up	to guide the	ring road slightly worsen from existing	(Only earth	road with highest	type		
Embankment	to a height of 8.7 m	flooding water to	conditions in both 50-year and 100-	embankment)	one of 2.5 m,			
Alt.	MSL not to be	the river channel	year floods.		necessary area of			
Alt.	overtopped by the	along the upstream			land is widest.			
	100-year flood.	side of ring road.						
	Ring road shall be	Existing lower part	Flooding situation in the upstream of	Medium	Due to embankment	All-weather	Fair	High
Road	elevated with soil up	of the road will not	ring road will not worsen from existing	(Box culverts	road with highest	type		
Embankment	to a height of 8.4 m	overtop the	conditions.	and earth	one of 2.5 m,			
& Drainage	MSL not to be	floodwater.		embankment)	necessary area of			
Culvert Alt.	overtopped by the				land is wide.			
	100-year flood.						-	-
	Utilizing existing	Floodwater will	Flooding situation in the upstream of	High	Due to embankment	Road will be	Low	Low
	drainage function of	overtop the	ring road will not worsen from existing	(Flood	road, but necessary	closed in		
Road	lower part of the ring	reinforced	conditions.	proofing road	area of land is not	more		
Embankment	road, road will	overflow section.	Overtopping situation	and earth	so wide.	intensive		
& Overflow	decline with a slope	Overtop starts in	50-year : overflow depth 1.5 m,	embankment)		than 10-year		
Section Alt.	of 3% connecting to	more intensive	velocity 0.48 m/s			flood		
	the bottom of	than 10-year flood.	100-year : overflow depth 2.1 m,					
	existing road.		velocity 0.50 m/s					

 Table 2.1-4
 Overall Comparative Study Results of the Flood Disaster Mitigation Alternatives

(4) Countermeasures to Protect Scouring of the Right Bank at Bend


Scouring Situation at River Bend

According to the results of river cross-sectional survey, significant scouring cannot be observed in the longitudinal riverbed profile (refer to Figure 2.1-6) and river cross-sections. A few large-scale cyclones still pass Efate Island after Cyclone Pam and riverbed materials mainly consisting of movable sand and fine gravels can easily be used to backfill scoured portion after any floods.



Source: JICA study team

Figure 2.1-6 Longitudinal Profile of Deepest Riverbed at Bend upstream of Teouma Bridge



Source: JICA study team

Figure 2.1-7 River Cross-sectional Survey Location at Bend upstream of Teouma Bridge

Scouring Depth Prediction

The following guidelines are referred to for estimation of scouring depth: Revised Version of Mechanical Designing for River Revetment Works (Japanese), Japan Institute of Countryology and Engineering (2007)

Below is the estimation process for scouring depth:

(1) Relation of maximum flow depth (Hmax) and average flow depth of an average annual maximum flood (Hm) shall be confirmed Refer to Figure 2.1-8.

Using curvature radius of river bend (r=140 m) and river width (B=50 m), r/B of 2.8 can be estimated. Checking the figure and using r/B of 2.8, Hmax/Hm of 2.3 can be made out in the rivers without formation of sandbar (dotted line in the figure).


(2) From average flow depth in average annual maximum flood (Hm), maximum flow depth in design flood (Hmax) can be estimated.

Assuming Hm of 1.0 m as average annual maximum flood (40 m³/s in 3 - 4 year ARI), Hmax can be estimated as follows, referring to the Guidelines.

Hmax = 1.0 x 2.3 x 1.3 = 3.0 m

(3) Setting-up of design foundation depth

Considering average water depth of 1.0 m, design foundation depth of 2.0 m the below riverbed design can be obtained.



Source: Rivised Revetment Dynamic Design Methods / Japan Institute of Country-ology and Engineering (2007)

Figure 2.1-8 Relation between Hmax/Hm and r/B at Bend

1) Scouring Prediction around Bridge Pier

a) Causal Factors of Local Scouring

According to HEC 23, riverbed scouring generally occurs in complex phenomena combining the following three independent factors:

• Riverbed aggradation/degradation: Channel scouring occurs by sediment balance situation. If human/natural activities or structures which influence the sediment balance situation in the upper reaches does not exist, then it is not necessary to consider this factor.

- River channel contraction: A large amount of floodwater flowed down along the river channel and simultaneously eroded the riverbank during Cyclone Pam, resulting in the widening of the river channel. As a result, Teouma bridge remained forming a constriction section. In the Outline Design, it is planned to widen the river channel and in doing so, this factor also may influence only negligible small effects.
- Structure's effect: Occurrence of vortex caused by bridge pier accelerates local scouring around the structure. This factor is major causal factor of local scouring.


b) Scouring Prediction around Bridge Pier

Based on the following article, the scouring depth around the bridge pier shall be computed: *Planning Guidelines for River Crossing Bridge (Draft)*, Japan Institute of Country-ology and Engineering, 2009


Based on the actual site conditions of Teouma Bridge, the necessary hydraulics parameters are:

- Average water depth (ho): 6 m
- Width of bridge pier(D): 2.0 m (Oval shape)
- Mean diameter of riverbed materials(dm): 1-0.5 mm (Coarse sand)
- Froude number (Fr): 0.4

Following the above figures, ho/D is 3 so that experimental result of ho/D between 2.75 to 3.50 can be used for estimation of local scouring depth. Fr is 0.4 and ho/dm ranges 6,000 to 12,000. Considering the figure below, ho/dm could be 6,000. As a result, non-dimensional scouring depth Z/D may be 1.7, and actual scouring depth Z could be computed as 3.4 m. The design scouring depth could be set at 3.5 m as a round number.



Source: Planning Guidelines for River Crossing Bridge (Draft), Japan Institute of Country-ology and Engineering, 2009



Assessment of the impact of climate change

Based on climate change projections, a two-dimensional flooding simulation was conducted. The results are shown in Table 2.1-5.

When climate change is considered in simulation, the maximum water level at Teouma Bridge would be 0.19 m above maximum water level without effect of climate change. However, 0.19 m is covered by free board 0.5 m. The water level at the left bank approach road 8.8 m is 0.1 m above the elevation of designed approach road 8.7 m. However, this 0.1m is absorbed in the super elevation of the approach road because this part is located in the curve section. Therefore, the increase of the water discharge due to climate change can be address by a newly design structure.

е .	·		0	0
	50-yr		100-yr	
	No Climate Change	Climate Change	No Climate Change	Climate Change
Peak Discharge (m ³ /s)	720	820	1020	1160
Peak Discharge at Teouma Bridge (m ³ /s)	690	780	950	1060
Water Level at Teouma Bridge (m MSL)	7.83	8.04	8.37	8.59
Water Level at left bank approach road of Teouma Bridge (m MSL)	7.90	8.18	8.57	8.80

 Table 2.1-5
 Changes of Hydraulics Analysis Results Considering Climate Change

Note : Teouma Bridge HWL ; 8.40 m MSL, *Water Level at left bank approach road ; 8.70 m MSL Source: JICA study team*

2.1.3 Design Policy of River Improvement Works

Based on the design policy of Flood Disaster Countermeasure described in 2.1.1 above, the following presents the design policy for river channel improvement works around the Teouma Bridge (a stretch of about 100m downstream and about 300 m upstream from bridge). A box culvert is also proposed under the road to drain flood overflow on the left bank.

At first, the present conditions of the river channel are investigated. Then, the design items of the channel improvement works such as alignment, longitudinal profiles and typical cross section are prepared. Furthermore, design policies are considered on excavation and embankment works to shape the proposed river channel. Bank slope protection works are needed for protection of vulnerable banks from erosion, and box culvert works are needed as drainage facility on the left bank. In addition, maintenance works are planned for completed channel.

(1) Site Conditions of River around Teouma Bridge

The present conditions of the river channel around the Teouma Bridge are described as follows:

- The River course shows a big bend towards the right (western) side in the upstream of the bridge using topographic data. River flow cause erosion severely in the right riverbank and hits the right approach road of the bridge. The river water then turns to the left and flows under the bridge. Fast-flow and/or turbulent water flow occurring due to flooding could cause erosion easily on the vulnerable riverbanks.
- During the flood caused by Cyclone Pam in 2015, severe erosion was observed on the approach road of the bridge on the right bank as shown in Figure 2.1-10 below (left photo). Emergency rehabilitation work using stones was done (right photo).





Urgent Rehabilitation Works of Right Approach Road (Present)

Figure 2.1-10 Teouma Bridge Damaged by Cyclone Pam

- Present width of riverbed is 20 to 30 m approximately. The riverbed elevation ranges from 1m above Mean Sea Level (MSL) to 1.5 m (hereafter presented by EL. 1 m or EL. 1.5 m). Top elevations of upstream riverbanks range from EL. 5 m to EL. 8.6 m at the right bank and EL. 6 m to 7 m at the left bank. Top elevations of downstream riverbanks are EL. 5 m at right bank and EL. 6 m at left bank. Height of riverbanks from riverbed are 4 m to 7 m.
- Present bank full flow capacity of river channel is estimated at 120m³/s which is less than 5-year return period.
- Material of river channel is fine sand.
- No riparian structures are found except gabion cylinders placed for abutments of Teouma Bridge.
- As for present land use, there is residential area for few houses on the right riverbank upstream and farm/bush land on left riverbank upstream and bush areas on both downstream riverbanks.
- At the area where a drainage facility is proposed under the road on the left bank 180 m from the bridge, there is a drainage pipe with 0.9 m diameter under the existing embanked road. Top of road is EL. 6.3 m and natural surface ground is about EL.5 m.

(2) Design Alignment, Longitudinal Profiles and Cross Section for Channel Improvement

As mentioned in 2.1.1 Design Policy for Flood Disaster Countermeasures, design flood level of EL.8.4m and design width of 50 m at the location of proposed new bridge are determined. Since the present river width is 20 m to 30 m, widening of channel is necessary.

Moreover, present alignment of river channel invading widely private land is not desirable due to bending. Re-alignment is necessary to stabilize the channel.

a. Design Alignment of River Channel

According to the collected land lot sketch map in the upstream area, the present river course invades the private area on the right riverbank. Old river course with a width of about 45 m is now filled with soils and bush land. Re-alignment of river channel is proposed to have almost the same as old channel considering the flowing:

• Alignments of new bridge and river channel should orthogonally intersect each other as much as possible, so that the bridge length can be shortened.

• Proposed alignment of river channel should be in the old river course (public land) to minimize the use of private land.

End of upstream of new river channel connects with the existing course 260 m upstream of bridge. On the other hand, end of downstream of new channel connects with existing course 110 m downstream of bridge.

b. Design Longitudinal Profile of Riverbed

Riverbed elevations of stretch to be re-aligned are determined following the existing riverbed profile; EL. 1.2 m at the downstream end and EL. 1.5 m at the upstream end. Then, the design longitudinal riverbed gradient becomes 1:1400 (vertical and horizontal direction).

c. Design Cross Section of River Channel


Design standard cross section is determined under the following policy:

• 50 m width is proposed as designed river channel width measured at the design flood level (EL. 8.4 m at bridge) with a freeboard of 0.5 m.

• Design slope gradient of riverbanks is 1:1.5 (vertical: horizontal) provided that the riverbank slope protection is constructed and 1:2.0 without slope protection.

• In case the slope height is more than 5.0 m, a 1.5 m wide berm, horizontal step, in the sloping profile is provided for stability.

Design width of the riverbed is 25.7 m which is almost the same as the existing one. The design standard cross-section of the river channel is showed in the following Figure 2.1-11.



Source: JICA study team

Figure 2.1-11 Proposed Typical Cross Section of River Channel (at Bridge)

(3) Excavation and Embankment Works to Make Re-Aligned River Channel

Excavation and embankment works are needed to shape proposed channel in accordance with the design alignment, design longitudinal profiles and design standard cross-section of river channel. Existing soil condition shows that excavation area comprises of sandy soil without any rocks found. Selected soils

from excavation work or borrow pit are to be used for necessary embankment. Cut/embankment slope gradient is designed to be 1:1.5 under the provision of slope protection and 1:2.0 for no provision of slope protection.

(4) Design Elevations of Riverbanks

Design top elevations of riverbanks are proposed to be almost the same as existing ground elevations.

(5) Bank Sections to be Covered with Revetment

Since the soil type of riverbanks is sandy and easily eroded by flood current, provision of revetments is proposed at curve portions and around the bridge structures as shown in Table 2.1-6 below:

Table 2.1-6 Bank Sections to be Covered with Revetment					
Location	Left Bank	Right Bank			
Downstream	There are curves at both bonks and banks are eroded. Revetments are to be				
of Bridge	provided on both bonks to fix the channel alignment.				
Around	Stronger revetments are to be provided to reinforce the bridge structure and				
Bridge	access roads.				
Upstream of	Since left bank is inside of curve,	This bank is concave curve. Curve			
Bridge	erosion of bank is not severe and area	would be more in progress if no any			
	on left bank is unused area. No	protection. Revetment along the curve			
	provision of revetment is proposed.	portion is proposed up to the existing			
		straight channel.			

 Table 2.1-6
 Bank Sections to be Covered with Revetment

Source: JICA study team

(6) Selection of Optimum Type of Slope Protection of Revetment

Revetment/Slope protection is designed based on the Japanese standards/guidelines on river engineering works.

Design of slope protection as part of revetment and placed on slope of riverbanks needs considerations of the subsoil condition, flood velocity, necessary height of slope protection, gradient of slope, depth of riverbed scouring, available space for construction, cost, maintenance works, etc.

- Fine sandy soil which is easily eroded
- Design flood velocity 3.2 m/s
- About 7 m water depth in case of design flood with 100-year return period
- Design flood level gradient of 1:550 (classified within rapid-middle stream having gradient of 1:500 to 1:2000)
- Design riverbed slope 1:1400
- Estimated potential scouring depth 2 m approximately
- Minimizing of land acquisition by slope gradient to avoid social issues
- Possible construction space for dry works under dry work condition in 26 m at riverbed
- Utilization of locally sourced materials which result in cost minimizing and easy maintenance works

As a first step in designing of slope protection, types of slope protections which might be applicable for this river course are listed as shown in Figure 2.1-12.



Figure 2.1-12 Types of Slope Protection

Comparison of types of slope protection is made in the following table (Table 2.1-7) considering the structural stability, applicable slope, locally available materials, cost, etc. As a result of comparison, "Dry Stone Masonry" and "Reinforced Concrete Crib" are selected. Strong reinforced concrete crib revetment is applied around the important bridge structure. Economical Dry-Stone Masonry revetment using local available stones is applied for area except bridge area.

Item	Slope	Typical Structural	Applicable	Applicability Evaluation
No.	Protection	Details	Slope	
1	Type Wet Stone	Cobble stones	Gradient	Hard stone is better. However, stone produced in
1	Masonry	(around 30 cm	1:1.5	Vanuatu is semi-hard stone.
	in a solid y	diameter) filled	to	v undud 15 senin hurd stone.
		with concrete	1:3.0	
2	Concrete	Concrete blocks		Factory-fabricated concrete blocks are not locally
	Block Wet	with thickness of		available.
	Masonry	20 cm filled with		
- 2	0	cement mortal		
3	Concrete	Concrete slab with thickness of		Similar to type below (item 4). However,
	Lining	20 cm (with steel		structural strength is not enough for river with high velocity. Since surface of slope protection is
		mesh-net, if		smooth, function of velocity reduction cannot be
		needed)		expected. This is generally used for river with
		,		relatively slow velocity. Construction cost is
				comparatively high.
4	Reinforced	Concrete cribs		Structure is strong and rigid. Velocity on surface
	Concrete	with 30 cm		of slope protection can be reduced by exposed
	Crib	sectional square and filled with		cribs. This type is frequently used for river with
		20cm thick		high velocity like this river. This is utilized around the important structure, because of high
		concrete lining		cost.
5	Gabion	Rocks filled in		This type is used for urgent works of disaster as
	Mattressess	Steel mesh box		temporary works. Durability is poor.
6	Steel Sheet	Slope protection	Vertical	This type is used where cofferdam construction
	Piling	on steel sheet	Wall	is too costly due to deep water at near sea, etc.
		piling		It is also preferable in urban area where land
				acquisition is difficult. However, construction
7	Dry Stone	Stones with	1:1.5	cost is too high. Locally available stones can be used, resulting in
/	Masonry	around 0.5m	1:1.5 to	low construction cost. Construction and
	wiasoni y	diameter are	1:3.0	maintenance are easy.
		placed. Void	1.0.0	
		between stones is		
		filled with small		
		stones.		

 Table 2.1-7
 Comparison of Slope Protection

Source: JICA study team

(7) Plan for Maintenance and River Water Use

Aggressive river flow can result in local erosion and damage of river channel. It is essential to regularly check the slope protection system and repairs should be carried out as soon as possible. A small damage could lead to a rapid deterioration of the total protection system. Moreover, local people are using

the river water for water intake, washing, etc. A step facility in bank slope is designed for the convenience of maintenance inspection and water use by local people.

(8) Box Culvert under Road for to Discharge Flood Overflow

A reinforced concrete box culvert with size of 2.5 m high by 2.5 m wide x 2 cells is proposed under the embanked road to drain smoothly the floodwater that overflows on the left bank. The structure design is made based on the Japanese design standards/guidelines.

2.1.4 Policies for Utilization of Existing Teouma Bridge

JICA team inspected existing Teouma bridge during the 1st site survey. The inspection result is described below.

- Rust had been found on many bolts of the existing bridge. If the existing bridge is to be utilized as a part of the new bridge, all bolts must be replaced.
- Rust on the bolts mainly was found on the upper chord members on the existing bridge. One of the reasons is considered that the airborne salt on the road surface may be rolled up by the vehicles passing the existing bridge which is located approximately 2 km form the coast.
- Peeling of galvanized corrosion protection was confirmed in a part of the main structural steel members, but it can be judged that it is sound as a base steel material.
- Road width of the existing bridge is 6.5 m (Carriageway:3.0 m x 2 + Side strip:0.25 m x 2). It does not satisfy the road design specification in VRRM which was enacted in June 2014.


Therefore, JICA team concluded that it is difficult to utilize the existing bridge as a part of the new bridge. In that case, utilization of the existing bridge shall not be considered in the new Teouma bridge planning.


2.1.5 Policies for Seismic Design Condition

Seismic load had been considered for bridge design in a project by ADB because of the frequent earthquakes that occur around Vanuatu. In bridge seismic design in Vanuatu, Australian standards normally apply. The Australian standard has been applied too in the ADB project.

By comparison of earthquake response spectra between Australian standard and Japanese standard is shown in Figure 2.1-13. The earthquake force in both standards is deemed mostly the same. Therefore, Japanese standard named "SPECIFICATIONS FOR HIGHWAY BRIDGES, PART V SEISMIC DESIGN, 2012" will be applied in seismic design of this project.

Going by the construction report of the existing bridge, the soil class around Teouma bridge was classified as Class-2, with a horizontal acceleration coefficient determined as $k_{\rm H}$ =0.26. But, based on the result of the soil investigation implemented in this survey, the soil class is classified as Class-3 (that is, softer than Class-2), with the horizontal acceleration coefficient determined as $k_{\rm H}$ =0.3.





Level 2 Earthquake (Exceedance probability 1/1000)

(b)Japanese Standard

Source: Specifications for Highway Bridges

```
Figure 2.1-13 Comparison of Earthquake Response Spectra
```

2.1.6 Policies for Bridge Planning

The following items shall be considered for the bridge planning such as bridge location, superstructure type, substructure type, etc.

- (1) The road alignment and bridge location shall be appropriately studied taking into consideration the construction plan.
- (2) The external requirement of the bridge planning, ex) live load and flood flow, shall be satisfied

⁽a)Australian Standard

- (3) Consideration of quality, easiness and rapidity shall be considered
- (4) The traffic safety and run-ability shall be considered
- (5) Ease of maintenance shall be considered.
- (6) The design standard shall be determined comparing both the Australian and Japanese standards.
- (7) The procurement condition for equipment and materials in Vanuatu shall be considered.
- (8) Utilization of the existing bridge is not possible.

(1) Condition on Bridge Location

Considering the function of the bridge as a trunk national road and the security of traffic flow during construction, three alternatives in the same location as well as upstream and downstream of the bridge will be compared and examined with respect to road alignment, obstacles, environmental impact, construction period and economic efficiency.

There are houses and street stalls around the Teouma Bridge. In the bridge planning, consideration shall be given to the geometric shapes of bridges and approach roads to minimize the relocation of these facilities and houses. When selecting a bridge type, the elevation of the road surface should be suppressed as much as possible. When the road surface height changes, consideration should be given to installing stairs, etc. in order to maintain access to facilities and houses.

(2) Condition on Bridge Profile

The High-Water Level (HWL) for the bridge design shall be determined based on Two-dimensional Flooding Simulation as mentioned in 2.1.1. The impact of climate change shall also be considered for HWL.

The appropriate freeboard and the cross-sectional area of the river shall be maintained to make the river flow smoothly during floods. The freeboard in this project is determined as 0.5 m in accordance with Australian standard as mentioned in 2.1.1.

(3) Condition on Cross Section

The following shall be considered for typical cross section:

- Width of carriage way and marginal strip shall comply with the VRRM.
- Typical cross section shall be considered to maintain the continuity of the existing ring road.
- Sidewalks shall be installed on both sides of the carriage way only on the bridge.

Sine there is a manual for road design (VRRM) in Vanuatu, the condition on road width shall be complied as per the VRRM. According to the VRRM, the width on ordinary road and bridge are not well-defined, and pedestrians will walk on the road shoulder. However, in this project, a sidewalk shall be installed only on the bridge area in respect to the strong request by the Vanuatu.

(4) Condition on Comparative Study of Bridge Planning

Bridge planning including bridge location, superstructure, substructure, pile etc., should be comprehensively determined in consideration of the following requirements:

- To select a proper location and road alignment for bridge construction
- To satisfy any external requirements for the bridge planning

- To be structurally stable and economical
- To consider the quality, ease and rapidity of construction
- To consider safety and comfort of driving
- To select structural type superior in easiness of bridge maintenance

(5) Condition on Comparative Study of Bridge Planning

The bearing layer of the bridge foundation shall be selected based on:

- The bearing layer of the bridge shall be determined based on the Standard Penetration Test (SPT). The N-value of bearing layer shall be more than or equal to 30 for the sand or gravel layer and 20 for the clay layer.
- The bearing layer shall be carefully decided for gravel layer to consider the errors due to existing of boulders, possibility of scouring and the scale of the structure. The N-value of more than or equal to 30 is not the absolute condition in case of gravel.
- The thin layer shall not be selected even if the N-value was satisfied.

2.1.7 Policies for Road Planning

(1) Policies for Plan of Approach Road Alignment

Approach road will be planned based on the following policies:

- In principal, to follow VRRM
- To refer to AUSTROADS Guide, Road Design Part 3: Geometric Design (hereinafter referred to as the "AGRD") or Government Order on Road Design Standards of Japan)
- To provide guardrail in high embankment section as a traffic safety measure
- To consider the ease of maintenance
- To maintain the continuity of the existing road
- To design with an emphasis on safety because the curve radius of existing road is small and the road is steep
- To plan to minimize land acquisition

1) Consideration of Road Alignment

In planning approach of the road alignment, the survey compared three options: See Table 2.2-14.

Option-1: Almost same alignment as existing road, Option-2: Moving the alignment to the upstream side, and Option-3: Moving the alignment to the downstream side. The items for comparison were:

Obstacles

High-voltage and low-voltage electric wires are laid around the Teouma bridge. The height of embankment will be 2.5 m to 3.0 m due to the elevation of new bridge. Therefore, the relocation of the poles and cables are indispensable for all options. In that case, the 3 options do not have much difference.

Environmental Impact

Vanuatu has a traditional customary land use system and this custom remains deeply rooted at present. Therefore, there are many lands where landowners are not clear. The land use situation around Teouma bridge is as follows: upstream side is leased land registered under the government and registered in the land registry, however, the downstream side is a customary land and the leader of the village substantially manages it. Land expropriation is very difficult in Vanuatu for both leased and customary land. Designed flood water level will be higher than the existing bridge. Accordingly, height of embankment also will be higher than existing road. Relocation of houses may occur with both option-2 and option-3. Therefore, Option-1, in which land expropriation doesn't occur except in some embankment sections, has an advantage compared to the other two options.

Alignment

In the case of option-3, the horizontal alignment on the right bank side has a smaller radius of curvature than the existing alignment due to the relationship with location of the bridge. This means driving safety will slightly decrease. In case of Option-1 or Option-2, the plan is not to deteriorate the approach road alignment.

Construction Period

In case of Option-1, it is necessary to construct a detour road before beginning of road and bridge works. Therefore, construction period takes longer than others.

On the other hand, as for Option-2 or Option-3, the construction period is shorter compared to Option-1 because the bridge can be constructed while the existing road is in service. However, since new road elevation is 2 or 3 m higher than present road, it is necessary to construct a detour road so as to not affect the new road in the overlap section between existing and new road alignment.

In addition, in order to ascertain the cross-sectional area of the river, it is necessary to remove existing bridge. Particularly, in case of Option-2 and Option-3, the existing bridge can be removed, and the revetment works can be done only after completion of the new bridge and approach road. Note: Revetment work can be done only in dry season, therefore, the 3 options have not much difference in this regard.

Cost

In the case of Option-1: Embankment constructed for main road is smaller than the other options, and installation of structure such as retaining walls is unnecessary. Therefore, the project cost is smaller than the other two options.

In the other hand, the project cost of Option-2 and Option-3 are more than Option-1 due to:

The length of the main road will be longer than the existing road in case of Option-2 and Option-3;

The amount of embankment will increase because the existing ground surface on the new alignment is lower than the existing road; and,

Retaining walls will be installed due to reducing area of land expropriation and amount of embankment.

Even though the cost for temporary works for Option-1 is more than the other two options due to the longer length of detour road and installation of temporary bridge, this is a small addition in comparison with the addition to the main construction cost.


2) Comparative Study Results

As a result of examining the approach road alignment, Option-1 has the overall advantage. This is in view of safety considerations and minimizing land acquisition with respect to the difficulty of land acquisition by customary land use system in South Pacific countries.

(2) Policies for Pavement Planning

Since there is no asphalt plant in Vanuatu, road surface types are limited to 2 types of unseal surface (earthen road) or seal surface (DBST / SBST). Double Bituminous Surface Treatment (DBST) is used on the existing road surface and the existing surface condition is very sound and also considering the simplicity of maintenance. Therefore, DBST will be applied in this project.

Appropriate pavement plan shall be prepared based on the results of the geotechnical survey and material tests (conducted during the second field survey). The pavement structure of seal surface (DBST) used in Vanuatu is shown in Figure 2.1-14 below.



Source: Report on the Project for Improvement of the Ring Road in EFATE Island in the Republic of VANUATU JICA 1997

Figure 2.1-14 Seal Pavement Structure

2.1.8 Policies for Procurement

The local construction business mainly consists of construction work such as small-scale buildings and private houses, and civil engineering work can only be seen as maintenance and repair work. Large civil works are carried out through foreign funding. The works are majorly implemented by foreign contractors, for example, from New Zealand and China. The construction market in Vanuatu is small, and there are no big contractors in Vanuatu. Such local circumstances shall be considered in this project.

2.1.9 Policies for Utilization of Local Contractors

The construction market in Vanuatu is very small and local construction companies are mostly very small. There is no company that can correspond as a sub-contractor to a Japanese construction company in Vanuatu. There are only a few suppliers of stone/crushed stone and a concrete manufacturing company as a supplier of materials. Only Local suppliers of soil and concrete materials shall be utilized in this project.

2.1.10 Policies for operation and maintenance

Maintenance works after completion of the Project will be carried out by the Office of Shefa belonging to the PWD under MIPU. Sufficient budget has been secured. Since advanced technology is not

required for maintenance, instruction on maintenance methods should be given during construction or after completion.

2.2 Outline Design of the Japanese Assistance

2.2.1 Basic Plan

The Overall project plan is shown in Table 2.2-1. The road width including shoulders in the section of approach road will be 8.0 m. In the bridge section, sidewalk with 1.25m width will be installed on both sides of the bridge. Its effective width will be 9.5 m.

	Standards and Quantity					
Longth					620.0 m	
	Length				(Bridge Section : 58.0 m)	
		D	Design S	Speed	60 km/h	
		General	neral STA.1+0.0m~2+37.7m,		9.6	
	Total	Section	n	STA.2+37.7m~7+20.0m	8.6 m	
Road	Width	Widenin	ng	STA 2 + 37.7m = 67.7m	13.6 m	
-		section	1	51A.2+57.711~07.711	15.0 III	
	Nu	mber of Lan	nes / Ce	arriage Way Width	2 lanes / 6.00 m	
-	T u			arriage way width	(3.00 m×2=6.00 m)	
-			Shoul	der	1.0 m	
	Box Culvert(2.5m×2.5m×2no			14.0 m		
-	Design Flood Level			E.L.=8.4 m		
-	Design River Width			50.0 m		
-	Riverbed Slope			1:1400		
River	Length			482.5 m		
	Riprap			80.0 m (4 Places)		
	Stone Pitching			302.5 m (Right Bank, 2 Places)		
	Reinforced Concrete Revetment			100.0 m (2 Places)		
			Structural Type		Plate Girder	
	Superstructu	atura		Bridge Length	58.0m	
			Girder Length		57.0m	
_			Span Length		28.4 m + 28.4 m	
				Abutment	2	
Bridge				Pier	1	
				Foundation Type	Spiral Steel Rotation Pile	
	Substructure	ture		Foundation Type	(Friction Pile)	
					A1=24.5 m/12 piles	
			Numbers of Pile /Pile Length		P1=24.5 m/28 piles	
					A2=22.5 m/14 piles	
	River	Road Width Nu	Road Total General Total Section Width Widenin Section Number of La Number of La Box Culv Box Culv Desi Image: Superstructure Image: Superstructure Bridge Image: Superstructure Image: Superstructure Image: Superstructure Image: Superstructure Image: Superstructure	Image: section in the sectio	Image: SubstructureImage: Section SpeedTotalGeneralSTA.1+0.0m~2+37.7m, STA.2+37.7m~7+20.0mTotalSectionSTA.2+37.7m~7+20.0mWidthWidening sectionSTA.2+37.7m~67.7mNumber of Lanes / Carriage Way WidthNumber of Lanes / Carriage Way WidthBox Culvert(2.5mRiverBox Culvert(2.5m<2.5m<2no	

2.2.1.1 Applicable Criteria

VRRM is used as a road design standard in Vanuatu and is used in the project. Reference is made to the AGRD for terms which are not covered in VRRM. AASHTO and Japanese relevant design standards shall be applied *mutatis mutandis* for other items.

- Vanuatu Resilient Road Manual (VRRM)
- AUSTROADS guide to road design Part 3 Geometric Design (AGRD)
- A Policy on Geometric Design of Highways and Streets: AASHTO •
- Design Specifications of Highway Bridges by Japan Road Association •
- Pavement Design Manual by Japan Road Association
- Government Ordinance for Structural Standard for River Administration Facilities by Japan River • Association

2.2.1.2 Road Class and Specifications

Road Class is classified as per the following table (Table 2.2-2) in VRRM 5.2 Traffic Class.

Traffic Classes	Traffic (Vehicles per day (vcd))	Number of lane
T4	>500	2 lanes
T3	200 - 500	2 lanes
T2	50 - 200	2 lanes
T1	<50	1 lane

Table 2.2-2 Traffic Classes

Source: VRRM

The daily traffic volume at Teouma bridge on a weekday is more than 5,000 vehicles, therefore, to the road is classified as T4.

2.2.1.3 Design Speed

The classification criterion for design speed in Vanuatu is as detailed in Table 2.2-3 below. The terrain around Teouma bridge is classified as flat with traffic classification of T4. Considering these, the design speed is set at 60 km/h.

Table 2.2-3 Design Speed					
Terrain	T4	Т3	T2	T1	
Rolling	40 km/h	30 km/h	30 km/h	10 km/h	
Flat	60 km/h	40 km/h	40 km/h	30 km/h	
<i>a</i>					

Source: VRRM

2.2.1.4 Geometric Condition

Standards and Geometric Conditions in Vanuatu are shown in Table 2.2-4.

	ltomo		Road Classification	Domosluo
Items			Τ4	Remarks
Design Speed (km/h) flat land			60	
Cross Section Configur	ration			
	Right of way (m)		30	
	Minimum Shouder Width	seal	1.0	
Road Cross Section	Lane Width(m)	seal	3.0	
	Pavement Thickness (m)		250	
Longitudinal Alignmen	t			
Minimum Vertical	carriageway		5.4	AGRD, P169
Clearance(m)	sidewalk		2.4	AGRD, P169
Traffic Volume	8		•	
Design Traffic Volume	(ADT)		>500	
Structure Loading			•	
Structure Live Loading	(minimum)		14, HS20 (or A-Load Ja	
Pavement Structure				
Douomont	Type of Surface	carriageway	Seal Pavement (DBST)	
Pavement	Crossfall (%)	seal	2.5	P.42
Geometric Conditions	•			
Horizontal Alignment				
Minimum Horizontal C	urvature	m	100	
Maximum Superelevati	on	%	8	
Superelevation Develop	oment Lengths	m	48	AGRD, P158
Vertical Alignment				
Maximum Gradient	Standard	%	12	
Gradient with Limitatio		%	12	
Gradient with Limitatio	ons	m	600	
Sight Diaton	Stopping	m	85	
Sight Distance	Passing	m	-	
Minimum Dadius	K-Value		9.2	AGRD, P183
Crest Curve	Dadius	m	920	AGRD, P183
Minimum Dadius	K-Value		9.2	AGRD, P183
sag Curve	Radius	m	920	AGRD, P183
Minimum Vertical Curv	ve Length	m	40	AGRD, P190

 Table 2.2-4
 Geometric Condition for Road and Bridge in Vanuatu

Source: JICA study team


2.2.1.5 Traffic Demand Forecast

(1) Traffic Survey Implementation Overview

Traffic Count Survey for 24 hours, Roadside OD Interview Survey and Axle Load Survey were conducted in order to understand the traffic situation around Teouma bridge and to carry out traffic demand forecast. The outline of the traffic surveys are shown in Table 2.2-5 below and the survey locations are shown in Figure 2.2-1.

		utilité di tilé fifullité du vég	
Items	Purpose of Survey	Contents of Survey	Remark
1. Traffic Count Survey	To understand information for road design based on traffic demand forecast	3 places (weekday/Sunday: 24hours) Vehicle Type Composition: 10 types and pedestrians (by gender)	
2. Roadside OD Interview Survey	To grasp vehicle trip pattern on the route	3 places (weekday: 12 hours) Vehicle Type Composition: 10 types	Interview
3. Axle Load Survey	To grasp axle situation of heavy truck on the route	1 place (weekday: 12 hours) Number of Samples: all	Observation by using simple truck scale

 Table 2.2-5
 Outline of the Traffic Survey



Source: JICA study team

Figure 2.2-1 Survey Locations


(2) Result of Traffic Survey

1) Traffic Count Survey


A 24-hour traffic count survey was conducted one day each on a weekday and holiday. The result is shown in Table 2.2-6 below.

Sta. No.	Survey day	Motorcycle/ Buggy	Car/ Taxi/ Pickup	Van (Van Taxi)	Bus	Truck	Heavy Truck	Total	Commercial Vehicles Ratio
No.1	Weekday	32	1,187	1,463	2	263	33	2,980	1.1%
NO.1	Holiday	55	1,447	1,756	4	221	5	3,488	0.1%
No.2	Weekday	31	1,806	2,580	19	543	53	5,032	1.1%
N0.2	Holiday	36	1,857	2,443	0	304	1	4,641	0.0%
No.3	Weekday	22	907	736	0	36	8	1,709	0.5%
10.5	Holiday	40	788	1,129	20	133	7	2,117	0.3%

 Table 2.2-6
 Result of Traffic Count Survey



Source: JICA study team



A count survey for pedestrians was also carried out. The number of pedestrians around Teouma bridge is 193 persons on a weekday and 294 persons on a holiday. The reasons for the increase in number on a holiday are presumed to be: The number of pedestrians on weekdays is composed only of people moving to the workshop or crop fields around the village, but on a holiday, most people in the village visit the Church. Thus, the increase in number of pedestrians on a holiday.

The survey sampled the number of pedestrians by gender too. On weekdays, the recorded number of males is 148 persons and females are 45 persons. The number of males on a holiday was recorded as 199 persons and females as 95 persons. The movements of the males on a weekday can be presumed to be persons moving to crop fields or workshops around the village. On the other hand, most of the pedestrians on a holiday are church goers. It is inferred that the difference in the ratio of male and female is small.

Sta.No.	Survey day	Number of Pedestrians
N- 1	Weekday	193
No.1	Holiday	294
N- 2	Weekday	154
No.2	Holiday	131
N- 2	Weekday	343
No.3	Holiday	533

 Table 2.2-7
 Result of Traffic Count Survey (Pedestrian)

Source: JICA study team

2) Roadside OD Interview Survey


The Roadside OD interview survey for 12 hours was carried out around Teouma bridge on weekdays. The survey targeted 20% of all vehicles except heavy trucks (more than 2 axles) and all heavy trucks. There is a difference between the result of number of the count survey and number of interview samples. The survey skipped interview survey of vehicles which had already been carried out. In general, there are lots of vehicles making round trips within the urban area which takes about 15 minutes from Teouma bridge and surrounding villages.

Classification	Number of Sample (OD)	Result of Count Survey	Rate
Bicycle	7	9	77.8%
Motorcycle	4	20	20.0%
Car/ Taxi/ SUV	64	846	7.6%
Van/Van Taxi	54	1078	5.0%
Bus	0	2	0.0%
2-Axle Truck or Trailer	80	211	37.9%
3-Axle Truck or Trailer	7	24	29.2%
4-Axle Truck or Trailer	2	3	66.7%
Agriculture Vehicle	0	1	0.0%
Another Special Vehicle	0	5	0.0%
Total	218	2199	9.9%

Table 2.2-8 Result of Roadside OD Interview Survey


Source: JICA study team

The traffic purposes are shown in Figure 2.2-3 below. Flow of traffic for private reason is 44% of the total, being the largest number. The totals for work and business is 43%, to/from school is 8%, and leisure or tourism is 3%, however, the percentage may increase to 20% on a day a cruise ship arrives as more people may arrive for sightseeing purposes.



Source: JICA study team

Figure 2.2-3 Result of Roadside OD Interview Survey (Purpose of the Trip)



Source: JICA study team

Figure 2.2-4 Result of Roadside OD Interview Survey (Departure and Destination)

Figure 2.2-4 shows spider network of the traffic on the ring road. Basically, more than half of the vehicles were going to Port Villa (urban district) from around the Teouma bridge or vice versa. In recent years, residential areas have been developed around the Teouma bridge, vehicles going to the urban area from the vicinity of Teouma bridge to commute for work or school are increasing. As other features, in addition to cars bound for the tourist spots scattered on the north side from the east side of the ring road, buses or cars carrying tourists traveling around the island were seen. In addition, when heavy trucks go to northern part of Efate Island, the trucks must trip counterclockwise from Port Villa because the high uphill slope with a very steep gradient and the hairpin curve are on the northwestern part of Efate Island, and the passage by the heavy vehicle from Port Villa to the north side is impossible.

3) Axle Load Survey

Axle load survey was conducted using portable axle load measurement at the Teouma bridge in order to understand the existing axle load situation. The outline of the axle load survey is shown in Table 2.2-9 below.

Type of Vehicle	Truck Traffic (not including Bus)
No. of Sample	100% Inspection
Methodology	by axle.
Survey Duration	1 weekday and 12 hours (From AM 6:00 to PM 18:00)

 Table 2.2-9
 Outline of Axle Load Survey

The axle load and gross load regulation of trucks as specified by the laws of Vanuatu are shown in Table 2.2-10 below.

 Table 2.2-10
 Load Regulation for Road of Vanuatu

Axle Load Regulation (per axle)	Gross Load Regulation (Total Loading)
8 t/axle	24 t/car

Source: Laws of the Republic of Vanuatu Road Traffic Control

The methodology of counting overloaded trucks is shown below. The result of counted overload is also shown in Table 2.2-11.

- 1. To sum up <u>the number of trucks(a)</u> surveyed with axle load survey
- 2. To sum up the number of trucks whose results exceed the limit values
- 3. To rule out the trucks without any cargo whose results exceed the limit values
- 4. To define the truck whose axle weight and/or vehicle weight is exceed the limit values as overloaded truck and to sum them up (b)
- 5. To calculate the conversion rate by total surveyed number of trucks for 24 hours(d) /(a)
- 6. To calculate the <u>number of overloaded trucks for 24 hours(e)</u> by multiplying (a) by conversion rate
- 7. To compute the rate of (e) over (d)

 Table 2.2-11
 Number of Overloaded Truck and Its Rate

	C	bserved Trucks		Expanded Truck by Traffic Cound Survey			
Number of Axle	Truck Volume (veh/day)	Overloaded Truck (veh/day)	Rate	Truck Volume (veh/day)	Overloaded Truck (veh/day)	Rate	
	(a)	(b)	(b)/(a)	(d)	(e)	(e)/(f)	
2 axles	74	1	1.4%	263	4	1.4%	
3 axles	11	7	63.6%	30	19	63.6%	
4 axles	0	0	0.0%	0	0	0.0%	
5 axles	0	0	0.0%	0	0	0.0%	
6 axles	1	0	0.0%	3	0	0.0%	
Total	86	8	9.3%	296	23	7.7%	

Source: JICA study team

(3) Traffic Demand Forecast

Total traffic volume for 10 years starting from 2022 (start of service year of the road) are estimated based on results of the traffic survey on May 2018 and economic growth rate. The results are shown in Table 2.2-12 below.

	Economic Growth	Small Truck		Heav	y Truck	Trailer	
year	Rate (%)	Daily Traffic Volume	Annual Traffic Volume	Daily Traffic Volume	Annual Traffic Volume	Daily Traffic Volume	Annual Traffic Volume
2014	2.30	235	85,640	27	9,769	3	977
2015	0.16	235	85,777	27	9,784	3	978
2016	3.47	243	88,753	28	10,124	3	1,012
2017	4.20	253	92,481	29	10,549	3	1,055
2018	3.80	263	95,995	30	10,950	3	1,095
2019	3.50	272	99,355	31	11,333	3	1,133
2020	3.00	280	102,335	32	11,673	3	1,167
2021	3.00	289	105,406	33	12,023	3	1,202
2022	3.00	297	108,568	34	12,384	3	1,238
2023	3.00	306	111,825	35	12,756	3	1,276
2024	3.00	316	115,179	36	13,138	4	1,314
2025	3.00	325	118,635	37	13,532	4	1,353
2026	3.00	335	122,194	38	13,938	4	1,394
2027	3.00	345	125,860	39	14,357	4	1,436
2028	3.00	355	129,636	41	14,787	4	1,479
2029	3.00	366	133,525	42	15,231	4	1,523
2030	3.00	377	137,530	43	15,688	4	1,569
2031	3.00	388	141,656	44	16,159	4	1,616
		Total	1,244,607		141,970		14,197

Table 2.2-12 Traffic Demand Forecast

Source: JICA study team

2.2.1.6 Riverbank Protection Plan

(1) Design Alignment, Longitudinal Profiles, Cross Section and Riverbank Elevation

Designing these items follows the design policy mentioned in 2.1.3. Design alignment of river channel for modification of present river course, longitudinal profiles of riverbed and banks, and cross sections are presented in 2.2.2 Outline Design Drawings. Table 2.2-13 shows the design top elevations of riverbanks.

Channel Stretch	Left Bank (East Side)	Right Banks (West Side)				
Downstream of Bridge	EL.5.0 m (Unused Area)	EL.5.0 m (Unused Area)				
Around Bridge	EL.5.0 m to EL.7.5 m to EL.5.0 m	EL.5.0 m to EL.7.5 m to EL.6.5 m				
	(EL. 7.5 m under bridge for	(EL. 7.5m under bridge for				
	maintenance of bridge, 1.4 m	maintenance of bridge, 1.4 m				
	clearance)	clearance)				
20 m to 60 m Upstream	EL.5.0 m	EL.6.5 m to EL.7.5 m				
from Bridge	(Unused Area)	(Several Houses)				
(Sta. 0+20 – Sta. 0+60)						
60 m to 200 m Upstream	EL.5.0 m	EL.7.5 m				
from Bridge	(Unused Area)	(Several Houses)				
(Sta. 0+60 – Sta. 2+00)						
200 m to 260 m Upstream	EL.5.0 m	EL.7.5 m to EL.5.0 m				
from Bridge	(Unused Area)	(Unused Area)				
(Sta. 2+00 – Sta. 2+60)						

 Table 2.2-13
 Design Top Elevation of Riverbanks

Source: JICA study team

(2) Detailed Planning of Reinforced Concrete Crib Revetment

Details of revetment having the selected slope protection (reinforced crib type) are shown in 2.2.2 Outline Design Drawings. It is further described below.

a. Foundation

Foundation supporting slope protection is designed as reinforced concrete structure which is generally applied. In addition, reinforced concrete piles (0. 2m x 0.2 m square section and 2.5 m long) supporting designed foundation for local scouring is also driven at 2.0 m interval.

b. Riprap for Countermeasure against Scouring at Foundation

There are many reported cases that collapse of slope protection is caused by the riverbed scouring. The potential depth of scoring is estimated at 2 m. It is too costly for slope protection to be embedded by 2.0 m under the design riverbed elevation. Construction (excavation and dewatering) is always difficult in the limited working space. In this regard, design 1m insert and riprap with 2 m width using locally available stones with 0.5 m diameter more or less in front. Sheet is provided under the riprap stones to prevent from sinking.

Design diameter of riprap stones are estimated based on Japanese technical guideline" Dynamics Design Method of Revetment", as follows.

$$Dm = \frac{V_0^2}{E_1^2 2g(\rho_s/\rho_w - 1)}$$

Where,

Dm : Average Diameter of Stones (m)

Vo : Representative Velocity (m/s)

 $Vo=\alpha \times Vm$

 $\begin{array}{l} Vm: Average \ Velocity \ (m/s) \\ \alpha = 1 + \Box Z/(2Hd) + B/(2r) \\ = 1 + Estimated \ Depth \ of \ Scouring/ \ (2 \ x \ Floodwater \ Depth) \\ + \ Riverbed \ Width \ / \ (2 \ x \ River \ Course \ Curve \ Radius) \\ = 1 + 2.0/(2x7) + 25/(2x140) = 1.23 \end{array}$

 $Vo = \alpha \times Vm = 1.23 \text{ x } 3.14 = 3.86 \text{ m/s}$

g : Gravitational Acceleration (9.8m/s^2)

 ρw : Water Density (1.0)

 ρS : Stone Density, $\rho S / \rho W = 2.29$ (based on laboratory sampling test conducted)

E1 : Experimental Coefficient for Flow Disturbance (ordinarily 1.20)

When riprap stones are placed horizontally on the riverbed,

Dm=3.86²/{1.2²×2×9.8×[2.29-1.0]}=0.41 m

Therefore, stones locally produced are applied with more or less 0.5 m diameter.

c. Reinforced Concrete Cribs

Type of Reinforced Concrete Crib Slope Protection composes of reinforced concrete crib (square 0.3 m by 0.3 m), 0.2 m thick concrete slab inside of cribs on 0.15 m thick crushed stones and 0.05 m thick concrete for reduction of underground water pressure. Cribs are exposed by 0.1 m to make roughness for reduction of flow velocity.

<u>d. Drain Pipe</u>

Since underground waters press the slope protection, 5 cm diameter drainpipes should be properly installed for 1 pipe per 2 m^2 .

e. Protection on Riverbank Crest

Adjoining crest of slope protection should be reinforced against scouring. A crib protection is extended on crest.

f. Expansion Joint

Since type of reinforced concrete crib is rigid, expansion joint is provided in an interval of about 10m for expansion due to change of temperature.

(3) Detailed Planning of Dry-Stone Masonry Revetment

Details of Dry-Stone Masonry Revetment are shown in 2.2.2 Outline Design Drawings and also described below.

a. Foundation

Foundation supporting slope protection is made of the same stones as slope protection.

b. Slope Protection

Sheet on selected soil fill is provided under stone foundation and dry stone masonry against sinking. Void of around 0.5 m thick dry-stone masonry is filled with small stones.

c. Reinforced End of Revetment and Riprap

Since the end of revetments is bound to be damaged by high-velocity flowing water, special attention is needed. A 20 m long dumped riprap works using locally available stones (0.5 m diameter more or less) should be applied continuously from dry stone masonry revetment. A sheet is also provided under the riprap stones to protect against sinking.

(4) Step Facility

Four step facilities on bank slope are to be provided for maintenance and convenience of people's water use, at the end of Reinforced Concrete Crib Revetment. Step walls are to be deeply embedded to protect revetment from scouring. Step facilities are accessible from steps provided on the slopes of main road embankment.

(5) Design of Box Culvert

As shown in 2.2.2 Outline Design Drawings, drainage box culverts (2.5 m height x 2.5 m width x 2 cells) are made of reinforced concrete.

- Design invert elevation: EL. 4.7 m considering present topographic condition and drainage plan of the road
- Provision of Cut-off considering scouring and erosion due water level difference between upstream and downstream
- Riprap on outlet bed against scouring

2.2.1.7 Bridge Plan

(1) Location

Location of new bridge should be considered with the function as national road and safety for public transportation during construction. Three options below have been studied in reference of site survey result.

Option-1: Upstream side

Option-2: Existing location

Option-3: Downstream side

Comparing the above three options in consideration with obstacles, environmental impact, road alignment, construction period, and economic efficiency, location of new bridge is shown in Table 2.2-14. Especially, Vanuatu has land problems such as customary land, and since landowners are not registered at the government office, land acquisition may take very long time. In consideration of such circumstances, JICA study team evaluated with an emphasis on "environmental impact". Since this project is a disaster reconstruction project, it is desired to implement projects promptly and reliably. Therefore, the new bridge will be reconstructed at the existing bridge position.

Plan	*Proposed road lines above do not accurate Option-1 Existing (Blue)	River direc	ct the road design standard.	P	Pentapao ort Vila View from downstream side Option-3 Downstream side (Green)	AREA WELL
Option			Option-2 Upstream side (Red)			
Obstacle	Electrical line, poles and other utilities are existed. It is necessary to relocate them during construction.		Electrical line, poles and other utilities are existed. It is necessary to relocate them during construction.		Electrical line, poles and other utilities are existed. It is necessary to relocate them during construction.	Fair
Road alingment	Not changed	Good	Not changed	Good	Road alignment of right bank side will be tighten than existing road alignment.	Fair
Construction period*	Same as other options.	Fair	Same as other options.	Fair	Same as other options.	Fair
Economic	Cost is not higher than other options due to low quantity of embankment Good		Cost is higher than Option-1 due to high quantity of embankment and structurl installation		Cost is higher than Option-1 due to high quantity of embankment and structurl installation	Poor
	Ressetlement of residents and land acquisition are not required. (If necessary, it is a little.)		Land acquisition is required. Poor		Land acquisition is required.	Poor
Total evaluation	Recommended		Not recommended		Not recommended	

 Table 2.2-14
 Comparative Study for Bridge Location

* In either case, detour road will be installed beside new constructed bridge.

Source: JICA study team

(2) Bridge Length and Span Length

The following points should be considered when deciding the bridge length:

• Secure design flow capacity of the river calculated from hydrological analysis

- Make flat space (more than 1.5 m width) in front of both abutments for bridge inspection and maintenance
- Determine the substructure location of the new bridge with a distance that does not interfere with the substructure of the existing bridge. It is difficult to remove the piles of the existing bridge.





Figure 2.2-5 Determination of Bridge Length

Since the bridge to be constructed in this project is crossing the Teouma river, it should be considered to ensure an appropriate span length and maintaining river flowing capacity (planned flow rate). Therefore, the new bridge length is determined to be 58.0 m with 2 spans (refer to Figure 2.2-5)

(3) Live Load

Both live load strength has been judged almost equal based on the Australian standard (T 44) and Japanese standard (Class-A in Specifications for Highway Bridges) as shown in Figure 2.2-6. Therefore, the Japanese standard (Class-A in Specifications for Highway Bridges) will be applied for the design of new Teouma bridge.



Source: JICA study team



(4) Superstructure Type

JICA study team carried out compressive test to the aggregate of concrete available near the project site. The uniaxial compressive strength of the aggregate was about 29 N/mm². JICA study team concluded that it is impossible to apply pre-stressed concrete girder using aggregate procured near the project site. As a result, steel bridge is the only suitable type of bridge as per the comparative study of the superstructure type in the Project.

Span length of the new Teouma Bridge was determined to be 29.0 m in Chapter 2.2.1.7 which is a short length for a steel bridge. Therefore, only two structure types of superstructure could be compared: pony truss and I-beam. In order to determine the optimum superstructure type from a comprehensive point of view, comparative study was carried out from the comparison items of (1) Structure, (2) Safety, (3) Construction, (4) Cost, and (5) Maintenance.

The following points were considered for each comparison item in order to weigh the evaluation according to its importance. The overall point was evaluated by the total points of each evaluation item (Refer to Table 2.2-15). The points of each evaluation item are as follows:

Comparative Study Item	Point 1
Structure	10 points
Safety	10 points

Construction	15 points
Cost	50 points
Maintenance	15 points
Overall Evaluation	100 points

Table 2.2-15 Comparative Study on Superstructure Type								
Option	Option-1 Pony Truss	Option-2 Steel I-Girder						
Typical Cross Section	9050 250250 8000 350250 For such as the second se	10000 400 1250 500 3000 500 1250 400 CL CL CL CL CL CL CL CL CL CL						
Structure (10 points)	Since around A1 is a curve section, it is necessary to widen the interval of truss structure member. The height of superstructure from the bottom of cross beam to road surface is about 1.0m. 8/10 Good	Simple and general structure. The height of superstructure from the bottom of girder to road surface is about 1.5 m. Therefore, proposed road elevation will be higher than Option-1.8/10Good						
Safety (10 points)	There is a risk that the traveling vehicle will collide with the main structure. And the driver feels a sense of pressure by the exposure of the truss member beside the roadway.	There is no risk that traveling vehicle will collide with the main structure. The driver doesn't feel a sense of pressure because only concrete barrier is onto the road.						
	6/10 Fair	10/10 Good						
Construction (15 points)	Transportability of the bridge member is superior because the size of the member is smaller than that of Option-2. No special machine for erection is required. 15/15 Good	Although the size of the member is larger than that of Option-1, crane erection method will be applicable installation, and no special machine is required.12/15Fair						
Cost (50 points)	Steel weight per 1 m ² : About 370 kg/m ² Approximate steel weight: 200 ton (Total width: 9.3 m, Bridge Length: 58 m) 40/50	Steel weight per 1 m ² : About 200 kg/m ² Approximate steel weight: 122 ton (Total width: 10.5 m, Bridge Length: 58 m) 50/50 Good						
Maintenance (15 points)	Number of require members are large and maintainability is inferior. Sedimentation on the lower truss member of the existing Teouma bridge has been confirmed.	The number of members is small, and maintainability is superior.						
Evolution	10/15 Fair	15/15 Good						
Evaluation	79/100	95/100 (Adopt)						

 Table 2.2-15
 Comparative Study on Superstructure Type

(5) Pier Type

Two columns pier and wall pier were compared for the comparative study of substructure types. As a result, wall pier that is superior to columns pier for all items shall be adopted.

Table 2.2-10 Comparative Study on Bridge Fler Type							
	Option-1 Two Columns + Coping Bea	m	Option-2 Wall Type				
Image							
Structure	Cylindrical cross section: φ 2,500 mm x 2. Rebar arrangement in the part of connecting column and coping beam will be complicated than Option-2.	Fair	Cross section: $10,500 \times 2,000$ mm Rebar arrangement will be simpler than Option-1.	Good			
Flow Capacity	Impediment ratio of river flow is larger than Option-2. Turbulence water flow occurs around the bridge piers at the time of flooding, the water flowing capacity is similar to Option-2.	Fair	Impediment ratio of river flow is smaller than Option-1. The water flowing capacity is superior to Option-1.	Good			
Construction	After construction of 2 columns, supporting for construction of coping beam is required temporary. Workability is inferior to Option-2.	Fair	Constructible from bottom to top of the piers uniformly. Workability is superior to Option-1.	Good			
Cost	Approximately concrete volume is approx. 102 m ³ . It is smaller than Option-2. River protection work will be required because the estimated scouring depth is deeper than that of Option-2. Therefore, the cost is almost same as Option-2.		Approximately concrete volume is approx. 187 m ³ . But river bed protection work is not required. Therefore, the cost is almost same as Option-1.	_			
Maintenance	River bed protection work is required because estimated scouring depth is about 6.0 m. River bed protection work will be subject of maintenance in the future.	Fair	Estimated scouring depth is about 3.5 m, and river bed protection work is not required. Therefore, maintainability in the future is superior to Option-1.	Good			
Evaluation	Not Recommended		Adopt				



Source: JICA study team


(6) Abutment Type

General reverse T shape abutment shall be adopted since abutment type has no special design conditions.

(7) Pile Type

The geological profile and soil model in longitudinal direction of the bridge collected by boring survey is shown in Figure 2.2-7.

. The boring survey was carried out to a depth of 45 m, but no definite bearing layer could be confirmed. Therefore, friction pile shall be applied.



Source: JICA study team

Figure 2.2-7 Geological Profile and Soil Model

3 options of steel pipe pile, cast-in place concrete pile and spiral steel pipe pile were compared for pile types. Spiral steel pipe pile shall be adopted because it can be expected to have higher friction bearing force than other option and possible to reduce the pile cap size (Refer to Table 2.2-17). In addition, spiral steel pipe pile has advantage that pile driving equipment is minimal, construction speed is faster as well as no excavated soil coming out. It is economical too.

(8) Steel and Painting

Considering the regional characteristics of the bridge location and long-term maintainability, the steel materials and painting specifications shown below are used for the main members of the bridge.

[Superstructure]	Steel materi	al that can be extended the repainting cycle, C5 paint system
	in Japanese J	paint specifications
[Reinforcement rehar	in RC slahl	Coating rehar

[Reinforcement rebar in RC slab] Coating rebar




Table 2.2-17 Comparative Study for Pile Type

 $*\bigcirc$: Good, \triangle : Fair, \times : Bad

2.2.1.8 Accessories of the Bridge

(1) Bridge Railing

The type of bridge railing shall be steel guard fence. This is in order to reduce the oppressive feeling by pedestrians and for its superior view. It shall be installed on the curb beside sidewalk.

(2) Bearing

Bearing shall be Fix-Move type.

(3) Expansion Joint

Rubber stretching apparatus with abundant experience in Japan shall be adopted for expansion joint.

(4) Unseating Prevention Structure

Seat length which is described in "Specifications for Highway Bridges, Part V, 2012" in Japan, will be ensured.

(5) Bridge Drainage System

The water on the bridge shall be discharged directly into river by drainage system on the bridge.

(6) Approach Slab

The approach slab shall be placed behind both abutments for prevention of subsidence of the road by settlement of the embankment. The length of the approach slab will be 5.0m, and its width will be same as the road width.

(7) Others

Power lines have been installed in the upper and lower sides of the Teouma Bridge, and communication lines shall also be laid in the future and shall be provided for on the eastern part of the Teouma Bridge. The construction work of these utility lines shall be done by the business operator, but the steel bracket for erection of these utility lines shall be installed in this project.

In consideration of the surrounding conditions and maintainability, lighting equipment shall not be installed.

2.2.1.9 Approach Road Plan

(1) Horizontal Alignment


New horizontal road alignment shall follow the existing road alignment.

(2) Vertical Alignment

According to the hearing survey, combination of a steep downslope of more than 10% and horizontal curve has caused frequent traffic accidents around Teouma Bridge. Since the height of bridge surface is 2.5 m higher than existing bridge, road surface is also raised by embankment to lower gradient, and the maximum gradient was set to 8%.

(3) Cross Section

The typical cross section is shown in Figure 2.2-8.



Source: JICA study team

Figure 2.2-8 Typical Cross Section of Approach Road

The design of the road width is 4.0 m x 2 on the roadway, 1.0 m x 2 on the shoulder, 0.3 x 2 on the guardrail installation width, and 8.6 m in total. The slope of the embankment is 1:2.0 equivalent to the existing slope. A Guardrail is installed in the section where the embankment height is 3.0 m or more.

(4) Pavement

1) Service Life

The service lifetime of the pavement design shall be 10 years from the commencement of service after completion of the project. New Teouma bridge and approach road is scheduled to open in 2022.

2) Calculus Equation

The basic formula of SN (Structural index required for total pavement thickness) for asphalt pavement is based on the AASHTO guideline and is calculated by the following formula.

$$\log_{10}(W_{13}) = Z_R \times S_0 + 9.36 \times \log_{10}(SN+1) - 0.20 + \frac{\log_{10}\left(\frac{\Delta PSI}{4.2 - 1.5}\right)}{0.40 + \frac{1094}{SN+1}} + 2.32 \times \log_{10}(M_R) - 8.07$$

3) Designed Traffic Volume

As it has been mentioned, the new Teouma Bridge and approach road is scheduled to open in 2022. The survey estimated designed traffic volume on the approach road by using the result of traffic survey conducted in May of 2018. The result of designed traffic volume is used for pavement design. Table 2.2-18 shows the estimated daily traffic volume for each type of vehicle in traffic demand forecast.

Type of Vehicle	Daily Traffic Volume
Small Truck	388
Heavy Truck	44
Trailer	4

Table 2.2-18Daily Traffic Volume in 2031

4) ESAL Conversion Factor

ESAL Conversion Factor by Vehicle Type used for pavement design was calculated based on the axle load survey results at the target bridge site (see Table 2.2-19). The traffic characteristics at the target bridge point are that the traffic of small vehicles (minivans, pickups, etc.) are the majority and the traffic volume of large vehicles is extremely small. Most supplies are being transported by small vehicles and small trucks. In addition, there is almost no full load of small trucks. However, dump trucks (heavy trucks) with full of earth and sand were observed since there are many quarry sites on the east side of the target bridge. The number of observed trailers was much smaller than small vehicles and the observed load of trailer also small. Therefore, the ESAL Conversion Factor for small truck and trailer is smaller than ordinal value. In addition, since there is no development plan that will increase the traffic of large vehicles in the future, these figures were adopted. However, a validity of pavement thickness will be verified by using the values of ESAL Conversion Factor of Trailer adopted in another country.

ESAL Conversion Factor
0.12
3.55
0.29

 Table 2.2-19
 ESAL Conversion Factor by Vehicle Type

Source: JICA study team

5) Estimation of Accumulative ESAL (18kip) Value of Trailer and Truck

The survey estimated accumulative ESAL of 10 years from the services commencement based on traffic demand forecast.

	Economic Sm		Truck	Dump	Dump Truck		Trailer		
Year	Grow Rate %	DTV	ATV	DTV	ATV	DTV	ATV	ESAL Value	
2022	3.00	297	108,568	34	12,384	3	1,238	57,351	
2023	3.00	306	111,825	35	12,756	3	1,276	59,072	
2024	3.00	316	115,179	36	13,138	4	1,314	60,844	
2025	3.00	325	118,635	37	13,532	4	1,353	62,669	
2026	3.00	335	122,194	38	13,938	4	1,394	64,549	
2027	3.00	345	125,860	39	14,357	4	1,436	66,486	
2028	3.00	355	129,636	41	14,787	4	1,479	68,480	
2029	3.00	366	133,525	42	15,231	4	1,523	70,534	
2030	3.00	377	137,530	43	15,688	4	1,569	72,651	
2031	3.00	388	141,656	44	16,159	4	1,616	74,830	
	Total		1,244,607		141,970		14,197	657,465	

 Table 2.2-20
 Estimated ESAL Value from Year 2022 to Year 2031

Source: JICA study team

6) Input Parameters and Result of Pavement Calculation

Inputted parameters and result of the pavement calculation is as follows.

1. Input Parameters	4) Standard Deviation (So): 0.49
1) Design Life): 10 years	5)Design Serviceability Loss: 1.7 (Initial (4.2) – Finale (2.5))
2) Reliability: 80% (National Road)	6) Resilient Modulus : 1500*CBR
3) Standard Normal Deviation(ZR): -0.841	7) Drainage Factor: 1.0

(inch) = 2.540 c m

	Result of SN Calculation on pavement structure						
Materia	I	Layer Factor (a)	Thickness (inch) (D)	Dranage Factor (m)	SN = a*D*m	Thickness (cm)(D)	Adopted Thickness (cm)
Base Course	New	0.140	16.654	_	2.331	42.3	45.0
Total			2.331	<	2.331	42.3	45.0
					OK		

. . .

CBR Value of actual subgrade (embankment) is more than 10, but CBR 10 is adopted for the SN calculation on Pavement Structure since this calculation of AASHO allows maximum CBR Value is 10. The thickness of base course shall be 45 cm from above calculation result. As a result of verification of a pavement design by the highest value 6.840 of ESAL Conversion Factor of trailer adopted in another country, it was confirmed that the required SN Value is 2.387, pavement thickness is 43.3 cm which was within adopted pavement thickness 45.0 cm.

(5) Accessory Facilities

1) Extension of shoulder

There is a direct farmer market built by residents in the roadside in downstream of right side bank. Residents sell their products to passing vehicles or tourists. However, according to the new road and bridge plan, market space and road will be separated by raised embankment and the residents could not continue their business at the same place. Therefore, it is planned to widen the shoulder at existing market to secure selling market and parking space and also to minimize the negative impact on the local economic activities.

2) Guardrail

A guardrail will be installed in the section where the height of embankment is 3.0 m or more in order to prevent the vehicles from falling down.

3) Road Marking

Center line (width; 15 cm, white, solid) and sideline (width; 10 cm, white, solid) will be planned on the new road. Incidentally, a "cat eye" will be installed at the boundary of sidewalk and roadway in the bridge section to take safety measure.

2.2.2 Outline Design Drawing

The table of contents of the drawing of Outline Design shown in Table 2.2-21 below. The drawings are attached in Appendix-6.

No.	Classification	Name
1	General	Overall Plan
2	Revetment	PLAN (REVETMENT)
3		River Alignment
4		Detailed Plan Around Abutment
5		Profile (Revetment)
6		Typical Cross Section (Revetment)
7		Riprap / Stone Pitching
8		Revetment (1)
9		Revetment (2)
10		Approach Steps (1)

 Table 2.2-21
 Table of Contents of Drawings of Outline Design

No.	Classification	Name
11		Approach Steps (2)
12	Bridge	General View of Teouma Bridge
13		General View of Superstructure
14		General View of A1 (1/2)
15		General View of A1(2/2)
16		General View of P1
17		General View of A2 (1/2)
18		General View of A2(2/2)
19	Road	Main Road Alignment
20		Plan (1) (Main Road)
21		Plan (2) (Main Road)
22		Profile (Main Road)
23		Typical Cross Section
24		Wet Stone Pitching
25		Reinforced Concrete Crib (Type A)
26		Reinforced Concrete Crib (Type B) (1)
27		Reinforced Concrete Crib (Type B) (2)
28		Approach Steps at Road Embankment
29		Drainage Structure
30	Box Culvert	General View of Box Culvert (1)
31		General View of Box Culvert (2)
32		General View of Box Culvert (3)
33	Temporary Work	Plan (1) (Detour Road)
34		Plan (2) (Detour Road)
35		Detour Road Alignment
36		Profile (Detour Road)
37		Typical Cross Section (Detour Road)

Source: JICA study team

2.2.3 Implementation Plan

2.2.3.1 Implementation Policy

The project implementation principles are:

- A cooperation project will be implemented in accordance with grant aid system of the government of Japan by concluding Note of Exchange (E/N) and Grant Agreement (G/A) for the project between the Government of Japan and Government of Vanuatu.
- The executing agency for implementation of the cooperation project is the Public Works Department (PWD) of the Ministry of Public Works of Vanuatu.
- The consulting services including detailed design, tender-related works and construction supervision services, will be provided by a Japanese consulting firm in accordance with the consultancy contract that shall be signed with the Republic of Vanuatu.
- The construction of the cooperation project will be executed by a Japanese construction firm that shall be selected through pre-qualification and bidding, in accordance with the construction work contract that shall be signed between the said construction firm and the Republic of Vanuatu.

The basic policies for the construction/procurement of this project are as follows:

- Equipment, materials and labor for construction shall be procured locally as much as possible. In cases where local procurement is not possible, they shall be procured either from a third country or from Japan considering price, quality and secured supply quantity.
- The construction method and construction process shall be consistent with the natural conditions such as the local climate, topography, geology, etc. as well as topographical conditions and river hydraulics characteristics of the site.
- Plan a general and easy construction method which shall not require the use of special or sophisticated equipment or technology from the viewpoint of construction such as reduction of construction period and quality assurance and cost.
- The contractor's site organization shall be planned to satisfy the established construction specifications and construction management standards set for this project. Likewise, the consultant's organization shall be based on such specified project management standards.
- An appropriate traffic management plan including deployment of traffic personnel at vantage positions shall be considered I order to ensure safety during construction.
- Appropriate preservation methods of the environment shall be adopted such as selection of temporary garbage dumping sites which were specified from the Republic of Vanuatu in order to reduce the influence of construction works on of the environment of project site.

2.2.3.2 Implementation Conditions

(1) Considerations for Natural Condition

The climate of Vanuatu is divided into rainy and dry seasons. Rainy season is from December to April. In the latter half of the rainy season, the water level around the site rises for a short period of time and the surrounding farmland might be inundated. Based on these changes in water level, construction works in river (revetment and bridge substructure work) shall be planned during dry season when the river water level is low in order to secure the safety and reliability of the construction as well as to reduce the cost of temporary works and also improve the effectiveness of the project.

(2) Traffic Control Plan during Construction Period

A detour road will be installed during construction period on the downstream side. The new bridge will be constructed in the current location. Regarding the detour road, it is planned to maintain the same level of functions as existing road based on discussion and request from local. Width, pavement structure, and minimum secured height of detour road will be specified in bidding document.

2.2.3.3 Scope of Works

The responsibilities to be borne by Japan and the Republic of Vanuatu are summarized in Table 2.2-22.

	Table 2.2-22 Responsibility			
Item	Contents	Japan	Vanuatu	Remarks
Land Acquisition			✓	
Procurement of materials	Procurement and transportation of materials	~		
	Customs clearance of materials and equipment		~	
Preparation work	Securing the site necessary for construction		~	Temporary yard, temporary road site
	Relocation of public utilities		~	Electric post, power line and communication line
	Other preparation work	✓		
Relocation / removal of construction obstacles	Relocation of obstacles		~	Electric post, power line, communication line and fences
Construction and removal of detour road	Construction and removal of detour road	~		
	Construction and removal of detour bridge	~		
Main work	Bridge reconstruction, improvement of river and approach road	~		New bridge, Revetment of the river, embankment and pavement of approach road
Demolition of the existing bridge	Disassembly and transportation of superstructure members. Partial demolition and removal of the abutment	~		Piles of the existing abutments shall be remained

 Table 2.2-22
 Responsibility of Each Government

Source: JICA study team

2.2.3.4 Consultant Supervision

Based on the contract agreement between the Japanese Consultant and the Government of Vanuatu, detailed design, bidding activities and the construction supervision shall be done by the consultant.

(1) Detailed Design

The major works to be carried out in the detailed design are as follows:

- Discussion on commencement with concerned authorities of Vanuatu and carry out field surveys,
- Detailed design and drawings preparation
- Project cost estimation

Duration to carry out the detailed design work is about 2.0 months.

(2) Bidding Activities

The major tasks to be undertaken between the time of inviting contractors to bid and the time for signing of contract for construction includes:

- Preparation of bid documents (in parallel with the detailed design).
- Bid announcement

- Pre-qualification of bidders
- Bidding
- Evaluation of bid documents
- Preparation of Contract Agreement

The duration of the bid-related activities is about 4.0 months.

(3) Construction Supervision

The Consultant will supervise the Contractor's planning and implementation of the construction contract. The major tasks under this stage include:

- Verification/Approval of related surveys and quantities
- Review/Approval construction plans
- Quality Control
- Process Control
- Work Output Control
- Safety Management
- Turnover Inspection and Acceptance

The duration of construction supervision is approximately 27.0 months. The construction supervision team shall consist of: 1-Resident/Chief Engineer (Japanese), 1-Construction Engineer (Japanese) for superstructure erection, 1-Construction Engineer (Local), 1-Clerk (Local) and 1-Utility Personnel (Local). A construction engineer for superstructure (Japanese) will be dispatched at the time of construction of superstructure.

The chief engineer is in charge of construction support, completion inspection, quality control meeting and dispatches engineers at the time of defect inspection.

During the construction period, special attention should be paid to safety management, and the supervision should be carried out to prevent accidents in advance by consulting and cooperating with the safety manager of the construction company.

2.2.3.5 Quality Control Plan

Regarding quality control, the contractor should submit the quality control plan. The construction works shall be commenced after the approval by the consultant. The main items requiring quality control during the construction period are as follows:

- Superstructure work
- Rotating pile (spiral steel pipe pile) work
- Concrete Work
- Reinforcement and formwork
- Earthwork
- Pavement work (DBST)
- Installation inspection of expansion joint, bearing shoe

The quality control standards are based on the standards of the Ministry of Land, Infrastructure, Transport and Tourism of Japan as well as local standards.

Based on the above, the quality control for superstructure works, rotating pile works and concrete works as typical quality control items are presented in Table 2.2-23, Table 2.2-24 and Table 2.2-25.

Item	Test item	Test method (Specification)	Test frequency
Material for superstructure		JIS G 3101, JIS G 3106, JIS G 3140	Mill sheet and inspection report
Factory painting	Painting Materials	JIS K 5551, JIS K 5552, JIS K 5553, JIS K 5659	Mill sheet and inspection report
	Coating thickness	C-5 paint system (Japanese paint specifications)	Inspection report
	Appearance		Visual inspection
Fabrication of steel	Welding		Inspection report for the various test result i.e. tensile test, bending test, impact test, groove weld test, fillet weld test, and Vickers hardness test
	Temporary assembly	Specifications for Highway Bridges (2012)	Check the quality of the temporary assembly by the Consultant
Ti	Erection		Check to camber and joints after temporary fastening by the Consultant in the site
	Tightening of high strength bolt		Site inspection and inspection report
	Erection completion		Check the camber, bearing installation after anchor bolt grout hardening, and fastening anchor bolt by the Consultant at the site
Field painting	Surface preparation		Check the rust removal on damaged and accessory parts
	Painting Materials	JIS K 5551, JIS K 5552, JIS K 5553, JIS K 5659	Mill sheet and inspection report
	Coating thickness		Inspection report
	Appearance		Visual inspection
Bearing	Product		Prior to delivery (Shipping)
	Installation		Site inspection after installation
	Completion		Check set bolt looseness, finished condition, filling condition of non-shrink mortar after pouring concrete
Expansion Joint	Product		Prior to delivery (Shipping)
	Installation		Site inspection after installation
	Completion		Check set bolt looseness, finished condition, filling condition of non-shrink mortar after pouring concrete
Drainage	Product		Prior to delivery (Shipping)

 Table 2.2-23
 Quality Control Plan for Superstructure Works

Item	Test item	Test method (Specification)	Test frequency
Material		JIS A 5525	Mill sheet and inspection report
Field Work	Test pile		Using the first pile as the test pile, grasp the measurement data (torque, penetration, etc.) during pile installation, and check the adequacy of the quality control method
	Measurement control		Torque, penetration depth, and overloading are measured in real time to control piling work

 Table 2.2-24
 Quality Control Plan for Rotating Pile (Spiral Steel Pipe Pile) Works

 Table 2.2-25
 Quality Control Plan for Concrete Works

Item	Test item	Test method (Specification)	Test frequency
Cement	Physical property test of cement	JIS R5201 and R5202	Once before construction work, once a month during construction. (By mill certificate)
Rebar	Acceptance inspection	JIS G 3112 or equivalent	Mill sheet and inspection report
Aggregate	Test for alkali aggregate reaction		Once before commencement of the construction, every 6 months during construction and when the production area changes (check supplier data)
Concrete	Total chloride		If the concrete placement straddles in the morning and afternoon, it is done before concrete casting in the morning, and if the test result is less than 1/2 of the total chloride limit, the afternoon test can be omitted. (The number of measurements in one test is three.) The judgment of the test is the average of three measurements.
	Unit water measurement		If it is 100 m ³ / day or more, it is twice / day (once in the morning and once in the afternoon).
	Slump test	JIS A 1101	Once at unloading Once or more per day, at least once every $20m^3$ to $150m^3$. In the case of the road bridge slab version, all vehicles are carried out.
	Air volume test.	JIS A 1116,1118,1128	Once at unloading 1 time / day or more, once every $20m^3$ to $150m^3$.
	Compressive Strength Test.	JIS A 1108	Once at unloading Once or more per day, at least once every $20m^3$ to $150m^3$. Six specimens per casting.

Source: JICA study team

2.2.3.6 Procurement Plan

(1) Procurement Plan for Main Construction Materials

Roadbed materials, stone materials, soil materials, and concrete materials are locally procured among main construction materials. Aggregate for asphalt pavement is procured from third countries. The procurement categories of main construction materials are shown in Table 2.2-26.

Item			Classificatio	on	Procurement	Procurement	
Product name	Specification	Local	Japanese	Third country	reason	route	
Structural materia	als						
Steel bridge	Plate girder		~		Quality, certainty of procurement	From Japan, ocean freight	
Deformed bar	D13-D32		~		Quality, certainty of procurement	From Japan, ocean freight	
Concrete	20-25 N/mm ²	~					
Gravel	150 – 200 mm	✓					
Boulder	40 - 100 cm	✓					
Upper subbase course material	Lime stone	>					
Lower subbase course material	Lime stone	►					
Embankment	Lime stone	~					
Asphalt emulsion			~		Quality, certainty of procurement	From Japan, ocean freight	
Asphalt aggregate	5-20 mm			✓	Quality and Cost	From Fiji, ocean freight in container	
Fuel		~					
Wood for formwork		>					
Plywood for formwork		>					
Temporary steel materials	H shaped steel, lining plate, steel sheet pile		~		Quality, certainty of procurement	From Japan, ocean freight	
Supportive material		~					
Other materials							
Steel bridge	Plate girder bridge		~		Quality, certainty of procurement	From Japan, ocean freight	
Shoe			~		Quality, certainty of procurement	From Japan, ocean freight	
Water stop			~		Quality, certainty of procurement	From Japan, ocean freight	

Table 2.2-26 List of Main Procurement Construction Materials

Source: JICA study team

Procurement of Ready-mixed Concrete

There are two ready-mixed concrete manufacturing plants within 15 km from the target site. The local manufacture has concrete plant of 30 m³/hour. Figure 2.2-9 shows the situation of ready-mixed concrete plant in operation.

Procurement of Roadbed materials/ Soil Materials/ Megalith Materials

There are several quarries within several kilometers from target site. Therefore, the contractor can procure from the quarries. However, regarding procurement of boulders 2 or more quarries are considered to meet the construction schedule.



Ready-mixed Concrete plant Source: JICA study team

Panoramic View of Quarry

Figure 2.2-9 Photo of Local Concrete Plant and Quarry

(2) **Procurement Plan for Special Construction Materials**

The special construction materials which cannot be procured in Vanuatu are plate girder, deformed reinforced bar, asphalt emulsion, aggregate for asphalt pavement (DBST), guardrail, bearing, telescopic device, drainpipe, and water stop. These materials shall be procured from abroad. The destinations and the reasons are highlighted below.

Plate Girder Bridge

There is no manufacturing capacity in Vanuatu, it is concluded that procurement from Japan is appropriate to secure the production quality and procurement security.

Deformed Reinforced Bar

Only small diameter deformed reinforced bar are imported from neighboring countries in Vanuatu. However, the quantity circulated in Vanuatu is very small in addition to poor storage condition. In the project, quantity of procurement is large and large diameter reinforced bar is required. Therefore, deformed reinforced bar shall be procured in Japan.

Asphalt Emulsion

There are no local items in Vanuatu, and the materials are imported from neighboring countries when necessary for repair. Therefore, Japanese procurement is appropriate to ensure quality and certainty of procurement.

Aggregate for Asphalt Pavement (DBST)

Most of the aggregates for asphalt pavement are being imported from neighboring countries like Fiji because quality is inappropriate. For assurance of quality and also certainty of procurement, it is judged that procurement from Fiji is appropriate.

Guardrail, Bearing, Telescopic Device, Drainpipe, Sealing Plate

There are no local items on site, and those are being imported from neighboring countries when necessary for repair. Therefore, Japanese procurement is appropriate from the viewpoint of ensuring quality and certainty of procurement.

(3) Procurement Plan for Construction Machineries

There are no companies that specialize in machine leasing and several general construction machines are owned by local aggregate manufacturers and foreign contractors. Basically, short-term leases can be considered, but long-term leases are difficult and expensive. Therefore, special equipment is to be procured from Japan. General equipment such as backhoe and bulldozer can be procured locally. However, if it is more economical to procure from Japan, it shall be procured from Japan. Table 2.2-27 shows a list of procurement categories for construction machine.

Item		T	Procur	ement class	ification		—
Machine name	Specs	Lease /Buy	Local	Japan	Third country	Procurement reason	Transport route
Backhoe (ultra-long boom)	0.4/0.3 m ³	Lease		~		Locally not available	Ocean Freight
Backhoe	0.8/0.6 m ³	Lease		✓		Cost	Ocean Freight
Pile rotating driving machine		Lease		~		Locally not available	Ocean Freight
Dump truck	10t Cap	Lease	✓				
Dump truck	4t Cap	Lease	 ✓ 				
Bulldozer	21 ton	Lease		✓		Cost	Ocean Freight
Bulldozer	15 ton	Lease	~				
Tire roller	8 to 20 ton	Lease	 ✓ 				
Road Roller	10 to 12 ton	Lease	 ✓ 				
Motor grader	W=3.1 m	Lease	 ✓ 				
Rough Terrain crane	35 ton	Lease		✓		Cost	Ocean Freight
Crawler crane	80 ton	Lease		✓		Locally not available	Ocean Freight
Vibrating Hammer	60 kW	Lease		✓		Locally not available	Ocean Freight
Heavy weight Breaker	1300 kg	Buy	 ✓ 				
Vibration Roller	3-4 ton	Buy	~				
Water pump	φ150 mm, 15 kW	Buy		~		Locally not available	Ocean Freight
Generator	20/25 kW	Lease		~		Quality, certainty of procurement	Ocean Freight
Generator	125/150 kW	Lease		~		Locally not available	Ocean Freight
Concrete pump		Lease	 ✓ 				
Distributor	2000 to 3000 ℓ	Lease		✓		Locally not available	Marine transport
Line marker		Lease		✓		Locally not available	Marine transport

 Table 2.2-27
 List of Procurement Construction Equipment


Source: JICA study team

2.2.3.7 Soft Component Plan

Soft component shall not be included in the project.

2.2.3.8 Implementation Schedule

Figure 2.2-10 shows construction implementation schedule.



Source: JICA study team

Figure 2.2-10 Construction Implementation Schedule

2.3 Security Plan

[Overview of security threat risk]

Among the South Pacific islands, it is said that security is particularly good, and atrocious crimes such as murders are rare. However, there is an increasing number of general crimes such as snatching, empty nests and sex crimes, mainly in the capital city of Port Vila.

[Safety measures items]

are:

- To avoid going to an unpopular place, walking alone and going out at night especially on weekends.
- To stay in the hotels or apartments with high security.
- To lock the door of the room of a hotel or home.
- Not to wear gorgeous and conspicuous clothes or brand-name precious metals or watches.

2.4 Obligations of Recipient Country

The undertakings required by the Government of Vanuatu for the smooth execution of this project

- · To acquire land for construction and to relocate affected houses;
- To secure land for a temporary yard, stock yard, site office, construction road and detour routes

and to shoulder tenancy payment for them;

- To secure borrow pits, spoil-banks, and industrial waste disposal area;
- To relocate all utilities such as electric poles, power lines, telecommunication cable and water pipeline which will disturb the Project works and to restore them on the new road and bridge;
- To bear the cost of bank charges such as the Advising commission and Payment commission to bank where an account related to the Project is opened;
- To arrange tax exemption and smooth custom clearance and to assist smooth inland transportation for imported materials
- To arrange for tax exemption for Vat for purchased materials, Japanese contractor's cooperate tax and income tax for the employees, including Japanese staff, local staff and staff employed from third counties.
- To provide necessary permissions that allow the personnel engaged in the construction work such as supervision engineer, construction workers etc., to enter and stay in Vanuatu.
- To provide necessary permission/certificate for environmental issues, construction of bridges, working inside river, earthwork and traffic control during the construction period, etc.
- To maintain new bridge and approach roads properly
- To assist in solving all conflicts raised by residents adjacent to the construction site and third parties.
- To bear all the expenses, other than those to be borne by the Grant Aid necessary for construction of facilities; and
- To monitor, analyze natural and social environment such as air and water quality during construction and public use, and take necessary actions based on the results of the monitoring and follow-up analysis.


2.5 Project Operation and Maintenance Plan

Public Works Department (PWD) of The Ministry of Infrastructure and Public Utilities (MIPU) executes the periodic inspection, routine maintenance and repair. Road and Bridge maintenance work conducted by PWD is as follows:


Periodic Inspection	: Bridge and Approach road
Routine Maintenance	: Pavement, Drainage Structure, Expansion Joint, Clearing, etc.
Repair Works	: Pavement, Drainage Structure, Concrete Structure,
	Incidental Facilities, Road marking, Revetment Structure, etc.


Since the bridge to be constructed in this project is durable against the environment in Vanuatu, serious repair is not expected in the immediate future. It is considered that there are no technical problems in carrying out the necessary maintenance work.

The organization of MIPU and PWD is shown in Figure 2.5-1 and Figure 2.5-2 respectively. The PWD, Shefa office will execute the maintenance, cleaning and repair works.



Source:PWD





Source: PWD

Figure 2.5-2 Organization of PWD

2.6 Project Cost Estimation

2.6.1 Initial Cost Estimation

2.6.1.1 Government of Vanuatu's Contribution

For confidentiality, the cost borne by the Japan's Grant Aid is not shown in this report.

2.6.1.2 Government of Vanuatu's Contribution

The approximate amount estimated for contribution from Vanuatu is shown in Table 2.6-1.

Table 2.6-1	Approximate Cost Estimate of Vanuatu Contribution

Item	Amount (VUV)		
1. Bank commission	3,583,000		
2. Land acquisition	28,810,000		
3. High voltage transmission line relocation	40,164,000		
Total	72,557,000		

2.6.1.3 Cost Estimation Condition

1.	Cost Estimation Month	: May 2018
2.	Exchange rate	 : US \$ 1.00 = 108.12 JPY (US Dollar vs. Japanese Yen Exchange Rate) VUV 1.00 = 1.039 JPY (Vanuatu vatu versus Japanese yen exchange rate)
3.	Implementation period	: Detailed design and period of construction to be required are shown in the implementation schedule.
4.	Others	: The estimate is carried out based on the Japanese Government's Grant Aid Scheme.

2.6.2 Operation and Maintenance Cost

Operation and maintenance expenses are being paid from the budget of the Ministry of Public Transport. The maintenance items and repair costs of bridges and approach road per one bridge are shown in Table 2.6-2.

Periodic	Component	Inspection items	Frequency	No. of persons	Materials and equipment	Required quantity	Amount (VUV)
c Inspection	Pavement	Crack, unevenness,		3 persons	Scoop,	36 people /	237,600
	D	potholes etc.	year		hammer,	day	
cti	Drainage facility	,	1 day / time		hook,		
on	Structure	damage, deformation,			barricade		
	_	dirt, peeling etc.					
	Revetment	Crack, damage,			Pick up	12 units	105,600
		collapse etc.				/year	
	Bridge	Bracket of Utilities,					
		Railings, etc					
						Subtotal	343,200
	_		_	No. of	Materials	Required	Amount
	Component	Inspection items	Frequency	persons	and	quantity	(VUV)
Daily				L	equipment		. ,
ily	Pavement	-		7 persons	Scoop,	56	384,000
	Drainage facility	Removal of soil,	vear		barricade,	persons/ye	
			-				
lain		obstacles. cleaning	2 days /		grass cutter,	ar	
lainter	Expansion Joint	obstacles. cleaning	-		grass cutter, broom,	ar	
laintenan	Expansion Joint	obstacles. cleaning	2 days /		C ,	ar	
Maintenance	Expansion Joint Bridge	obstacles. cleaning Removal of soil,	2 days /		broom, tooling	ar 8 units /	73,100
laintenance	•	obstacles. cleaning Removal of soil, obstacles. cleaning	2 days /		broom, tooling Small truck		73,100

 Table 2.6-2
 Main Maintenance Items and Annual Cost

	Component	Inspection items	Frequency	norconc	Materials and equipment	Required quantity	Amount (VUV)
	Pavement	Crack seal, repair of	1 time /	9 persons		36	246,800
		defect	year			persons/ye	
	Drainage facility	Repair of damaged	4 days /			ar	
		part	time				
	Structure	Repair of damaged			Compactor	4 units	33,600
		part				/year	
Repair	Bridge	Repair of damaged					
Dair		handrail					
	Pavement marking	Repair of lane			Small truck	4 units	47,500
		marking				/year	
	Revetment	Repair of damaged			-	0.36t ³ /year	31,800
	facilities	parts			emulsion		
						0.9m ³ /year	39,100
					asphalt		
					Lane marker	100m/year	20,900
					Seawall	10m ² /year	106,900
						Subtotal	526,600
						Total	1,326,900

CHAPTER 3 Project Evaluation

3.1 Preconditions

The Project preconditions related to the required undertakings of the Government of Vanuatu are as follows:

- To acquire land for the project and transport affected houses in 4 months after the conclusion of Exchange of Note.
- To secure land for temporary yard, stock yards, detour road, borrow pit and disposal area in 4 months after the conclusion of Exchange of Note.
- To relocate all utilities including underground utilities that will disturb the Project works to the place where the works will not be disturbed in 4 months after the conclusion of Exchange of Note.
- To take any necessary actions for tax exemption in compliance with E/N and G/A.
- To conduct quick custom clearance for the goods from Japan and third countries.
- This project does not require to process the EIA procedure. However, environmental mitigation measures and monitoring plan is described in 1.3.1.10 to monitor, analyze natural and social environment such as air and water quality during construction and public use.
- To provide necessary permits for extracting soil materials from borrow pits and cutting trees in 4 months after the conclusion of Exchange of Note.
- To assist to solve all conflicts with residents adjacent to the construction site and third parties.

3.2 Necessary Inputs by Recipient Country

The maintenance work for the Project is vital after handing it over in order to realize and sustain the effects of the overall project. In order to ensure the service life of bridge, approach roads and other ancillary facilities, the budget shown in Section 2.6.2 (about 1,326,900 VUV / year) shall be secured and regular inspections shall be carried out. If in case damage was confirmed, it is necessary to carry out appropriate repairs at the initial stage. In daily maintenance, it is necessary to clean the pavement surface and drainage facilities, such as removing sediment and obstacles, and to ensure safe traffic and services for users.

3.3 Important Assumptions

(1) Restriction of Overloaded Tracks

Restriction of overloaded trucks has not been conducted in Vanuatu. It is necessary to conduct a control system for the overloaded trucks in order to ensure the durability of the pavement.

(2) River Management

It is necessary to carry out river management so that the flow of the river is not obstructed when the development of the Teouma River basin progresses.

3.4 Project Evaluation

3.4.1 Relevancy

Implementations of this cooperation projects is recommended using Japan's grant aid as follows:

- 1. The beneficiaries' populations are almost half of the east Efate Island. It is a big number.
- 2. The project is urgently needed on the Ring Road to contribute to the strengthening of trunk road transport networks and to stabilize and improve the livelihoods of residents.
- 3. Vanuatu authorities could operate and maintain bridges and roads using internal resources and technologies. There is no need for sophisticated technology for operation and maintenance.
- 4. This project contributes to the environmental and economic objectives of Vanuatu national development plan: "Recovery from climate change and disasters" and "Improving infrastructure".
- 5. There is little negative environmental and social impact.
- 6. In addition to the necessity and superiority of using bridge construction technology of Japan, Japanese grant aid system allows the project to be implemented without any difficulty.

3.4.2 Effectiveness

3.4.2.1 Quantitative Effect

There is a high possibility of interruption of bridge service and closure of the connected road due to inundation and also scouring and erosion of approach road due to the progressive erosion of riverbanks in the upstream as well as potential change in river course. However, by implementation of this project, the risk of inundation will be highly reduced by raising the road elevation, and also the river course will be stabilized by river works and erosion prevention countermeasures.

The expected quantitative effect of the project implementation is shown in Table 3.4-1. The base value was measured in 2018 and the target value is set for three years after project completion.

	1 1	U
Items	Base Value (FY2018 Actual)	Target Value (3 yrs after completion)
Traffic Volume(Unit/day)	2,980	3,600
Number of Passengers(person/day)	755	905
Weight of Cargo(ton/year)	60,000	72,000

 Table 3.4-1
 The Quantitative Effects Expected from the Implementation of the Projects

3.4.2.2 Qualitative effect

The qualitative effects of the project are:

1. Maintenance of economic activities and access to various services are ensured by eliminating the blockage of logistics and commuting due to flooding after heavy rain.

- 2. By changing from emergency rehabilitation to permanent restoration, there is no fear of a falling bridge and the toughness of the bridge is secured.
- 3. River erosion to private land on the upper right bank can be avoided.