

APPENDIX FOR CHAPTER 3 ACTIVITIES IN EACH PILOT AREA

AF3.1 Tank Operation Simulation in Fawara Chowk GST and OHR

Waris Pura GST Simulation


Correction

Time	Inflow from TR gallon/h	Water Level feet	Outflow	
			Total gallon/h	To PC No.2 gallon/h
0	0	7.5	0	0
1	0	7.5	0	0
2	0	7.5	15,000	0
3	0	5.4	20,000	0
4	60,000	2.6	0	0
5	60,000	11.0	45,000	45,000
6	40,000	13.1	45,000	45,000
7	0	12.4	20,000	0
8	0	9.6	20,000	0
9	0	6.8	20,000	0
10	0	4.0	20,000	0
11	60,000	1.2	45,000	45,000
12	60,000	3.3	45,000	45,000
13	40,000	5.4	20,000	0
14	0	8.2	20,000	0
15	0	5.4	15,000	0
16	60,000	3.3	45,000	45,000
17	60,000	5.4	45,000	45,000
18	40,000	7.5	20,000	0
19	17,000	10.3	20,000	0
20	0	9.9	17,000	0
21	0	7.5	0	0
22	0	7.5	0	0
23	0	7.5	0	0
24	0	7.5	0	0
Total	497,000	7.5	497,000	270,000

Assumption: 4,000 connections are in Peoples Colony and others, they use 10.6/c/day of water

Capacity of GST	100,000	gallon
Area of GST	7,143	gallon/feet

Operational Water Level	H.W.L.	14.00	feet
	L.W.L.	0.00	feet




Waris Pura OHR Simulation

Correction


Time	Inflow from TR		Water Level feet	Outflow to Sarfraz gallon/h
	gallon/h	gallon/h		
0	0	4,525	4.5	4,525
1	0	4,525	3.6	4,525
2	15,000	4,525	2.7	4,525
3	20,000	4,525	4.8	4,525
4	0	6,787	7.9	6,787
5	0	9,049	6.5	9,049
6	0	13,574	4.7	13,574
7	20,000	15,836	2.0	15,836
8	20,000	13,574	2.8	13,574
9	20,000	11,312	4.1	11,312
10	20,000	9,049	5.8	9,049
11	0	11,312	8.0	11,312
12	0	13,574	5.7	13,574
13	20,000	13,574	3.0	13,574
14	20,000	9,049	4.3	9,049
15	15,000	9,049	6.5	9,049
16	0	11,312	7.7	11,312
17	0	13,574	5.4	13,574
18	20,000	11,312	2.7	11,312
19	20,000	11,312	4.4	11,312
20	17,000	9,049	6.1	9,049
21	0	6,787	7.7	6,787
22	0	4,525	6.3	4,525
23	0	4,509	5.4	4,509
24	-	-	4.5	-
Total	227,000	226,219		

Capacity of GST	50,000	gallon
Area of GST	5,000	gallon/feet

Operational Water Level	H.W.L.	10.00	feet
	L.W.L.	0.00	feet



AF3.2 Hydraulic Analysis Result in Sarfraz Pilot Area



Network Table – Nodes

Node ID	Elevation ft	Base Demand GPM	Pressure psi
Junc J2	609	0	6.93
Junc J3	609	0	0.24
Junc J4	611	0	-0.68
Junc J5	611	0	25.80
Junc J6	610	0	26.21
Junc J7	610	0	17.42
Junc J8	610	0	26.21
Junc J9	610	0	26.21
Junc J10	611	0	25.41
Junc J11	611	16	25.78
Junc J12	611	0.1	25.41
Junc J13	611	0	25.38
Junc J14	610	1.2	25.67
Junc J15	610	1.6	25.63
Junc J16	610	1	25.63
Junc J17	611	1	25.19
Junc J18	611	1.167	25.37
Junc J19	611	0.3472	25.37
Junc J20	613	2.722	24.49
Junc J21	612	8.75	24.70
Junc J22	613	8.361	24.19
Junc J23	610	9.333	25.68
Junc J24	610	7.778	25.52
Junc J25	608	3.11	26.36
Junc J26	608	0	26.37
Junc J27	611	5.389	25.09
Junc J28	613	2.5	24.23
Junc J29	612	5.389	24.71
Junc J30	612	2	24.73
Junc J31	612	3.7	24.70
Junc J32	611	3.11	25.13
Junc J33	610	2.2	25.61
Junc J34	609	2.2	26.04

Node ID	Elevation ft	Base Demand GPM	Pressure psi
Junc J35	610	1	25.61
Junc J36	611	1	25.19
Junc J37	614	1.45	23.75
Junc J38	614	2.9	23.75
Junc J39	613	4	24.18
Junc J40	607	1	26.78
Junc J41	606	4.167	27.21
Junc J42	607	3	26.78
Junc J43	607	1.5	26.78
Junc J44	609	7	25.76
Junc J45	611	8.167	24.99
Junc J46	612	7.583	24.49
Junc J47	611	1	25.05
Junc J48	611	1	25.04
Junc J49	611	1	25.03
Junc J50	606	3.7	27.18
Junc J51	606	8.2	27.10
Junc J52	605	8.4	27.53
Junc J53	611	1	25.02
Junc J54	611	4.6	25.02
Junc J55	604	4	28.08
Junc J56	609	2.2	26.23
Junc J57	611	0	25.41
Resvr R1	625	#N/A	0.00
Tank T1	661	#N/A	4.12
Tank T2	598	#N/A	4.98

Signature: *[Handwritten Signature]*

Date: 1-10-2017

Fawara Chowk OHR

Time	Zonal Meter	GST			Pump				Electricity/Power	By Pass	OHR		Remarks	
		Inlet Flow	Inlet Valve	Water Level (ft)	No. 1	No. 2	No. 3	No. 4			PC Valve	Water Level (ft)		SC Supply
06:00	Ch-2 205	Yes/No	Open/Close	9	On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close	12	Yes/No	
07:00	208	Yes/No	Open/Close	9	On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close	12	Yes/No	
08:00	213	Yes/No	Open/Close	8	On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close	12	Yes/No	
09:00	209	Yes/No	Open/Close	6	On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close	12	Yes/No	
10:00	199.97	Yes/No	Open/Close	3	On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close	11	Yes/No	طانی ماریا کے
11:00	208	Yes/No	Open/Close	1	On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close	10	Yes/No	طانی ماریا کے
12:00	215	Yes/No	Open/Close	9	On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close	12	Yes/No	طانی ماریا کے
13:00	203	Yes/No	Open/Close	6	On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close	12	Yes/No	طانی ماریا کے
14:00	207	Yes/No	Open/Close	2	On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close	11	Yes/No	طانی ماریا کے
15:00	192	Yes/No	Open/Close	6	On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close	8	Yes/No	
16:00	205	Yes/No	Open/Close	5	On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close	10	Yes/No	
17:00	207	Yes/No	Open/Close	9	On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close	12	Yes/No	
18:00		Yes/No	Open/Close		On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close	12	Yes/No	
19:00		Yes/No	Open/Close		On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close		Yes/No	
20:00		Yes/No	Open/Close		On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close		Yes/No	
21:00		Yes/No	Open/Close		On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close		Yes/No	
22:00		Yes/No	Open/Close		On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close		Yes/No	
23:00		Yes/No	Open/Close		On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close		Yes/No	
00:00		Yes/No	Open/Close		On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close		Yes/No	
01:00		Yes/No	Open/Close		On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close		Yes/No	
02:00		Yes/No	Open/Close		On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close		Yes/No	
03:00		Yes/No	Open/Close		On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close		Yes/No	
04:00		Yes/No	Open/Close		On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close		Yes/No	
05:00		Yes/No	Open/Close		On/Off	On/Off	On/Off	On/Off	Yes/No	Yes/No	Open/Close		Yes/No	

Ch-1
1-46
1-41
1-47
1-45
1-46
1-40
1-42
1-43
1-48
1-47
1-47
1-50

Comments:

AF3.4 Construction Record Sheet in Sarfraz Pilot Area


MD	DMD	D	DD	GIS		

Survey - Construction sheet

Normal • Urgent

Receipt NO

Division of work WATER (DQM)	receipt	Date	23/08/17	finish	23/08/17	
		Time				
WASA-No	番 号			staff		
Address or parcel No		P# 635 QA Awan road.		Contact info		
History/Justification		No.	Material used		Size	Quantity
Repairing of leakage.			Pvc Plug		1/2"	01
			M/S clamp		6" dia	01
Method/Activities		Excavated by excavator exposed 6" dia line damaged. also found old leakage domestic connection.		Manpower	Name	Time
				Rashid	F-C	8:30 PM
				WARI S	F-C	
				Equipment		
				Excavator	Mini	01
Results		Water quality				
1- Repaired 6" dia AC line 2- Disconnected old rusted connection. Properly.		Clolor				
		Odour				
		Chlorine				
Additional Information		Existing system			Certificate from work supervisor	
Leakage was not visible at grade however excavation of valve chamber made it visible.		Pipe material			ATIQ S/E Aliq Date _____ Signature _____	
		PVC • AC • PE • CI • DI • MS				
		Pipeline size				
		6" dia				
		Pipe line depth				
		5'				
		Pipe line alignment				
		6' from P# 635				





MD	DMD	D	DD	GIS		

Survey - Construction sheet

Normal • Urgent

Receipt NO _____

Division of work	Water (DGM)	receipt	Date	22/08/17	finish	22/08/17
			Time	3:30 PM		
WASA-No	番号			staff		
Address or parcel No						
St#01 in front of AL-Foreed Central Store						
Contact info						
History/Justification			Material used	Size	Quantity	
Site visited and found 3" dia cross network.			/	/	/	
Method/Activities			Manpower	Name	Time	
During the excavation of Pstcl lines Cross network of water found.			/	/	/	
Results			Equipment			
			Water quality	Clolor	N.A	
Odour	N.A					
Chlorine	N.A.					
Additional Information			Existing system		Certificate from work supervisor	
			Pipe material		ATIQ S/E  Date _____ Signature _____	
			PVC • AC • PE • CI • DI • MS			
			Pipeline size			
			3" and 4" dia			
			Pipe line depth			
			1.5'			
			Pipe line alignment			
			5' from wall			



AF3.5 Customer Survey Manual and Survey Sheet in Madina Town Pilot Area

Water supply situation survey


Survey area:

- Entire Madina Pilot Area (it is not the same as "Madina Town X block")

Survey items:

- Check house No. of resident.
- Does resident have water connection?
- If yes, make a sketch of the location of service pipe on the map.
- If yes, does this resident make water supply contract?
- If no, fill in the sheet of "illegal connection" with "yes"
- Does resident have sewer connection?
- Does resident have water meter?
- If yes, make a sketch of the location of water meter on the map.
- If yes, is meter properly installed?
- Does resident have illegal sucking pump?
- If yes, make a sketch of the location of sucking pump on the map.
- Does resident use groundwater?
- If yes, make a sketch of the location of groundwater pump on the map.
- Take a picture of house and check the sheet.
- Take a picture of bill with customer meter and check the sheet.

Example:




GP: Groundwater pump

SP: Sucking pump

CM: Customer Meter

S/N	Parcel ID	House No.	Street	Block	Consumer Name	Account No.	House Size (Marla)	Water Connection	Sewer Connection	Illegal Water Con.	Customer Meter	Sucking Pump	Groundwater Pump	House Picture	Bill & Meter Picture
example	12345	123	1	X	Mr. XX	w12345678	3.5	no	yes	yes	no	no	yes	x	x
1															
2															
3															
4															
5															
6															
7															
8															
9															
10															
11															
12															
13															
14															
15															
16															
17															
18															
19															
20															
21															
22															
23															
24															
25															

AF3.6 Hydraulic Analysis Result in Madina Town Pilot Area



Network Table – Nodes at 8:00 Hrs

Node ID	Elevation ft	Base Demand CFS	Pressure psi
Junc J1	582.34	0	-0.24
Junc J2	582.34	0	33.21
Junc J4	582.34	0	33.21
Junc J5	582.4	0.0013	0.09
Junc J6	582.6	0.003	0.00
Junc J7	582.32	0.0043	0.12
Junc J8	582.67	0.0043	0.00
Junc J9	582.6	0.0043	0.00
Junc J10	582.6	0	0.00
Junc J11	582.6	0	0.00
Junc J12	582	0	3.50
Junc J14	583	0.0013	31.95
Junc J15	583	0.0017	31.45
Junc J16	582.9	0.0172	31.48
Junc J17	583.56	0.018	31.36
Junc J18	583	0.0172	31.87
Junc J19	582.6	0.0026	33.09
Junc J20	582.1	0.0116	31.25
Junc J21	582	0.0086	30.98
Junc J22	582.36	0.0086	30.65
Junc J23	582.9	0.0094	30.32
Junc J24	583	0.0077	30.22
Junc J25	583.1	0.0094	30.15
Junc J26	582.67	0.0197	30.46
Junc J27	582.78	0.0073	30.45
Junc J28	582.3	0.0094	30.54
Junc J29	583.6	0.0082	29.98
Junc J30	582.88	0.0064	30.41
Junc J31	583	0.0052	30.32
Junc J32	583	0.0056	30.26
Junc J33	583.1	0.0069	30.16
Junc J34	582.9	0.0077	30.24
Junc J35	583	0.0077	30.18
Junc J36	583.1	0.0077	30.14
Junc J37	583.25	0.0086	30.08
Junc J38	583	0.0056	30.18
Junc J39	583	0.0041	30.18
Junc J40	583.2	0.0069	30.10
Junc J41	583.7	0.0086	29.90
Junc J42	583	0.015	30.17

Node ID	Elevation ft	Base Demand CFS	Pressure psi
Junc J43	582.6	0.0185	31.72
Junc J44	582.9	0.0028	30.22
Junc J45	582.6	0.0009	0.00
Junc J46	582.7	0.002	33.05
Junc J47	582.7	0	32.62
Junc J3	583.2	0.0085	31.47
Junc J48	583.2	0.0073	31.64
Junc J49	583.1	0.0094	31.56
Junc J50	582.9	0.0086	32.14
Junc J51	583	0.0064	31.76
Junc J52	583.2	0.0052	31.67
Junc J53	583	0.0086	31.91
Junc J54	583.1	0.0094	31.77
Junc J55	583.3	0.0056	31.59
Junc J56	583.25	0.0077	31.47
Junc J57	583.2	0.0077	31.48
Junc J58	583.4	0.0077	31.40
Junc J59	583	0.0086	31.55
Junc J60	583	0.0069	31.56
Junc J61	582.9	0.0069	31.60
Junc J62	582.85	0.015	31.63
Junc J64	583	0.0077	31.77
Junc J66	582	0	29.46
Resvr R1	570	#N/A	0.00
Tank T1	647	#N/A	5.21
Tank T2	572.34	#N/A	4.02

Network Table – Links at 8:00 Hrs

Link ID	Length ft	Diameter in	Flow CFS	Velocity fps
Pipe P3	126.47	12	0.76	0.96
Pipe P5	15.11	12	0.00	0.00
Pipe P8	3445.42	12	2.00	2.55
Pipe P9	149.79	12	0.00	0.00
Pipe P10	194.05	12	0.01	0.01
Pipe P12	139.48	12	0.00	0.00
Pipe P13	184.45	12	0.00	0.00
Pipe P14	368.48	12	0.00	0.00
Pipe P15	90.29	4	0.28	3.17
Pipe P16	118.82	4	0.02	0.25
Pipe P18	129.29	4	0.16	1.86
Pipe P19	97.43	4	0.02	0.28
Pipe P20	209.87	4	0.26	2.97
Pipe P21	1046.31	4	0.11	1.29
Pipe P22	1044.54	3	0.01	0.20
Pipe P24	141.16	4	0.08	0.90
Pipe P25	116.90	4	0.06	0.66
Pipe P26	131.69	4	0.04	0.44
Pipe P27	117.01	4	0.02	0.26
Pipe P28	46.49	4	0.02	0.17
Pipe P29	123.41	4	0.25	2.88
Pipe P30	128.22	4	0.18	2.03
Pipe P31	120.27	4	0.13	1.49
Pipe P32	125.08	4	0.10	1.11
Pipe P33	125.08	4	0.07	0.83
Pipe P34	131.43	4	0.04	0.44
Pipe P35	455.33	3	0.05	1.10
Pipe P36	226.77	3	0.04	0.74
Pipe P37	475.06	3	-0.01	0.12
Pipe P38	453.01	3	0.03	0.65
Pipe P39	448.73	3	0.02	0.35
Pipe P40	449.97	3	0.01	0.16
Pipe P41	448.73	4	0.01	0.15
Pipe P42	120.27	3	0.00	0.10
Pipe P43	128.37	3	0.03	0.52
Pipe P44	120.27	3	0.03	0.69
Pipe P45	129.88	3	0.03	0.64
Pipe P46	228.03	4	0.03	0.37
Pipe P48	117.01	3	0.03	0.53
Pipe P49	122.11	3	0.02	0.35

Link ID	Length ft	Diameter in	Flow CFS	Velocity fps
Pipe P50	128.37	3	0.01	0.14
Pipe P51	126.63	3	-0.01	0.12
Pipe P52	476.33	3	0.00	0.10
Pipe P53	474.04	3	0.00	0.07
Pipe P54	481.12	3	0.00	0.01
Pipe P55	991.22	4	0.01	0.16
Pipe P59	98.06	12	0.44	0.56
Pipe P60	142.28	4	0.20	2.25
Pipe P62	185.93	12	0.00	0.00
Pipe P63	245.42	12	0.00	0.00
Pipe P17	131.43	4	0.12	1.38
Pipe P58	405.54	4	0.01	0.13
Pipe P1	153.56	4	0.29	3.37
Pipe P2	349.93	4	0.07	0.76
Pipe P4	229.40	4	0.08	0.89
Pipe P7	461.93	4	0.03	0.39
Pipe P11	132.46	4	0.02	0.26
Pipe P23	134.56	4	0.20	2.25
Pipe P47	453.53	3	0.04	0.88
Pipe P56	125.04	3	0.02	0.48
Pipe P57	120.27	4	0.14	1.58
Pipe P64	126.90	4	0.09	1.08
Pipe P65	115.42	4	0.06	0.65
Pipe P67	449.97	3	0.03	0.57
Pipe P68	444.56	3	0.02	0.43
Pipe P69	113.98	3	0.03	0.56
Pipe P70	123.41	3	0.01	0.17
Pipe P71	228.57	3	0.04	0.79
Pipe P72	118.60	3	0.02	0.31
Pipe P73	117.01	3	-0.01	0.11
Pipe P74	115.47	3	-0.03	0.56
Pipe P75	461.35	3	0.01	0.17
Pipe P76	121.82	4	0.00	0.04
Pipe P77	470.49	3	0.01	0.15
Pipe P78	126.90	4	-0.01	0.12
Pipe P79	471.83	3	0.01	0.20
Pipe P80	123.41	4	-0.01	0.17
Pipe P81	1158.56	4	0.04	0.50
Pipe P82	126.90	4	-0.02	0.19
Pipe P6	70.77	12	2.00	2.55
Pipe P61	140	4	-0.01	0.14

Link ID	Length ft	Diameter in	Flow CFS	Velocity fps
Pipe P66	140	4	-0.01	0.12
Pump PU2	#N/A	#N/A	1.19	0.00
Pump PU3	#N/A	#N/A	2.00	0.00
Valve V4	#N/A	4	0.00	0.00
Valve V1	#N/A	12	0.44	0.56
Valve V2	#N/A	4	-0.24	2.74
Valve V3	#N/A	4	0.02	0.17
Valve V5	#N/A	4	0.00	0.02
Valve V6	#N/A	4	0.01	0.09
Valve V7	#N/A	4	0.01	0.09
Valve V8	#N/A	12	2.00	2.55

Network Table – Links at 8:00 Hrs

Link ID	Unit Headloss ft/Kft	Friction Factor
Pipe P3	0.40	0.028
Pipe P5	0.00	0.000
Pipe P8	2.41	0.024
Pipe P9	0.00	0.000
Pipe P10	0.00	0.000
Pipe P12	0.00	0.000
Pipe P13	0.00	0.000
Pipe P14	0.00	0.000
Pipe P15	13.01	0.028
Pipe P16	0.12	0.040
Pipe P18	4.85	0.030
Pipe P19	0.15	0.040
Pipe P20	11.51	0.028
Pipe P21	2.47	0.032
Pipe P22	0.11	0.044
Pipe P24	1.26	0.034
Pipe P25	0.72	0.035
Pipe P26	0.33	0.037
Pipe P27	0.13	0.040
Pipe P28	0.06	0.043
Pipe P29	10.92	0.028
Pipe P30	5.71	0.030
Pipe P31	3.23	0.031
Pipe P32	1.85	0.032
Pipe P33	1.09	0.034
Pipe P34	0.34	0.037
Pipe P35	2.57	0.034
Pipe P36	1.23	0.036
Pipe P37	0.04	0.047
Pipe P38	0.97	0.037
Pipe P39	0.30	0.040
Pipe P40	0.07	0.045
Pipe P41	0.04	0.044
Pipe P42	0.03	0.049
Pipe P43	0.65	0.038
Pipe P44	1.07	0.037
Pipe P45	0.95	0.037
Pipe P46	0.25	0.038
Pipe P48	0.66	0.038
Pipe P49	0.31	0.040

Link ID	Unit Headloss ft/Kft	Friction Factor
Pipe P50	0.06	0.046
Pipe P51	0.05	0.047
Pipe P52	0.03	0.049
Pipe P53	0.02	0.051
Pipe P54	0.00	0.122
Pipe P55	0.05	0.043
Pipe P59	0.15	0.030
Pipe P60	6.87	0.029
Pipe P62	0.00	0.000
Pipe P63	0.00	0.000
Pipe P17	2.81	0.031
Pipe P58	0.04	0.045
Pipe P1	14.56	0.028
Pipe P2	0.93	0.034
Pipe P4	1.23	0.034
Pipe P7	0.26	0.038
Pipe P11	0.12	0.040
Pipe P23	6.87	0.029
Pipe P47	1.69	0.035
Pipe P56	0.56	0.039
Pipe P57	3.58	0.031
Pipe P64	1.78	0.033
Pipe P65	0.69	0.035
Pipe P67	0.77	0.038
Pipe P68	0.46	0.039
Pipe P69	0.73	0.038
Pipe P70	0.08	0.045
Pipe P71	1.39	0.036
Pipe P72	0.25	0.041
Pipe P73	0.04	0.048
Pipe P74	0.72	0.038
Pipe P75	0.08	0.045
Pipe P76	0.00	0.053
Pipe P77	0.06	0.046
Pipe P78	0.03	0.046
Pipe P79	0.11	0.044
Pipe P80	0.06	0.043
Pipe P81	0.42	0.037
Pipe P82	0.07	0.042
Pipe P6	2.41	0.024
Pipe P61	0.05	0.062

Link ID	Unit Headloss ft/Kft	Friction Factor
Pipe P66	0.04	0.064
Pump PU2	-77.41	0.000
Pump PU3	-80.00	0.000
Valve V4	0.00	0.000
Valve V1	0.00	0.000
Valve V2	0.00	0.000
Valve V3	74.15	0.000
Valve V5	70.50	0.000
Valve V6	70.07	0.000
Valve V7	70.09	0.000
Valve V8	59.92	0.000

AF3.7 Construction Completion Books

Weekly Construction Schedule
Improvement of water supply distribution system in Madina Town pilot area

Work Item	Status	Feb 2018							Mar 2018							
		Mon	Tue	Wed	Thu	Fri	Sat	Sun	Mon	Tue	Wed	Thu	Fri	Sat	Sun	
Test pit excavation & disconnection	Planned															
Pit # 1-9 & 64	Actual															
Pit # 13-17	Actual															
Pit # 32-43	Actual															
Pit # 9-12	Actual															
Pit # 18-31	Actual															
Pit # 48-63	Actual															
Pipe & filling excavation & installation	Planned															
Pipe laying 1-3	Actual															
Pipe laying 3-4	Actual															
Pipe laying 4-5	Actual															
Pipe laying 5-6	Actual															
Pipe laying 6-8	Actual															
Pipe laying 8-10	Actual															
Back filling	Actual															
Hydrostatic field testing	Actual															
Zonal meter installation	Actual															
Connection works	Planned															
Main connections	Actual															
Branch connections	Actual															
Manhole Construction	Planned															
Pavement Restoration	Planned															

Weekly Schedule
Test Pit Result Record
Hydrostatic Test Report

IMPROVEMENT OF WATER SUPPLY DISTRIBUTION SYSTEM
IN MADINA TOWN AREA

15th Feb, 2018 ~

Contractor
MUHAMMAD HANIF ANJUM

Progress Sheet
Improvement of water supply distribution system in Madina Town pilot area

Work Item	Month	Total	Done	March							April								
				20	21	22	23	24	25	26	1	2	3	4	5	6	7	8	
1 Test pit excavation & disconnection		63	16																
Pit # 1-9 & 64		Planned: 8	Actual: 3																
Pit # 13-17		Planned: 5	Actual: 5																
Pit # 32-43		Planned: 17	Actual: 2																
Pit # 9-12		Planned: 4	Actual: 1																
Pit # 18-31		Planned: 14	Actual: 0																
Pit # 48-63		Planned: 15	Actual: 0																
2 Pipe & filling excavation & installation		1740	658																
Pipe laying 1-3		Planned: 270	Actual: 100																
Pipe laying 3-4		Planned: 350	Actual: 357																
Pipe laying 4-5		Planned: 210	Actual: 201																
Pipe laying 5-6		Planned: 165	Actual: 0																
Pipe laying 6-8		Planned: 425	Actual: 0																
Pipe laying 8-10		Planned: 320	Actual: 0																
3 Back filling																			
4 Hydrostatic field testing		Planned: 2	Actual: 0																
5 Zonal meter installation		Planned: 1	Actual: 0																
6 Connection works		21	0																
Main connections		Planned: 1	Actual: 0																
Branch connections		Planned: 20	Actual: 0																
7 Manhole Construction		Planned: 21	Actual: 0																
8 Pavement Restoration		Planned: 1300	Actual: 0																

Weekly Construction Schedule

Progress Sheet & Schedule
Improvement of water supply distribution system in Madina

Work Item	Month		April							May						
	Total	Done	30	1	2	3	4	5	6	7	8	9	10	11	12	13
1 Test pit excavation & disconnection	64	21														
Pit # 1-8 & 64	Planned 8	Actual 8														
Pit # 13-17	Planned 5	Actual 5														
Pit# 32-48	Planned 18	Actual 5														
Pit # 9-12	Planned 4	Actual 1														
Pit# 18-31	Planned 14	Actual 0														
Pit # 49-63	Planned 15	Actual 2														
2 Pipe excavation & installation	1824	1507														
Pipe laying 1-3	Planned 270	Actual 214														
Pipe laying 3-4	Planned 350	Actual 357														
Pipe laying 4-5	Planned 210	Actual 219														
Pipe laying 5-6	Planned 189	Actual 191														
Pipe laying 6-8	Planned 425	Actual 421														
Pipe laying 8-10	Planned 320	Actual 233														
Boring for road crossing	Planned 2	Actual 0														
Connection pipe	Planned 60	Actual 27														
3 Back filling	Planned 2	Actual 0														
4 Hydrostatic Field testing	Planned 1	Actual 0														
5 Zonal meter installation	Planned 1	Actual 0														
6 Connection works	21	10														
Main connections	Planned 1	Actual 0														
Branch connections	Planned 20	Actual 9														
7 Manhole Construction	Planned 26	Actual 0														
8 Pavement Restoration	Planned 1300	Actual 0														

Handwritten signature

Progress Sheet
Improvement of water supply distribution system in Madina Toan pilot

Work Item	Month		April							May						
	Total	Done	23	24	25	26	27	28	29	30	1	2	3	4	5	6
1 Test pit excavation & disconnection	64	21														
Pit # 1-8 & 64	Planned 8	Actual 8														
Pit # 13-17	Planned 5	Actual 5														
Pit# 32-48	Planned 18	Actual 5														
Pit # 9-12	Planned 4	Actual 1														
Pit# 18-31	Planned 14	Actual 0														
Pit # 49-63	Planned 15	Actual 2														
2 Pipe excavation & installation	1764	1405														
Pipe laying 1-3	Planned 270	Actual 190														
Pipe laying 3-4	Planned 350	Actual 357														
Pipe laying 4-5	Planned 210	Actual 219														
Pipe laying 5-6	Planned 189	Actual 191														
Pipe laying 6-8	Planned 425	Actual 421														
Pipe laying 8-10	Planned 320	Actual 233														
Boring for road crossing	Planned 2	Actual 0														
3 Back filling	Planned 2	Actual 0														
4 Hydrostatic Field testing	Planned 1	Actual 0														
5 Zonal meter installation	Planned 1	Actual 0														
6 Connection works	21	10														
Main connections	Planned 1	Actual 0														
Branch connections	Planned 20	Actual 9														
7 Manhole Construction	Planned 26	Actual 0														
8 Pavement Restoration	Planned 1300	Actual 0														

Work Done: Leased (2-2 April)
 1. Test pits = 2
 2. Pipe laying = 252 m
 3. Boring for road crossing
 4. Boring materials = 725 m
 This week: - (9-15)
 1. Pipe laying = 240 m
 2. Removal of earth = 200 m
 3. Connection pit
 4. Boring pit

Need NOC from TMA for working in the area IP1-IP3, IP6-IP10
 Need formal approval of route revision

Progress Sheet & Schedule
Improvement of water supply distribution system in Madina Toan pilot area

Work Item	Month		May																			
	Total	Done	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20
1 Test pit excavation & disconnection	64	25																				
Pit # 1-8 & 64	Planned 8	Actual 6																				
Pit # 13-17	Planned 5	Actual 5																				
Pit# 32-48	Planned 18	Actual 6																				
Pit # 9-12	Planned 4	Actual 1																				
Pit# 18-31	Planned 14	Actual 0																				
Pit # 49-63	Planned 15	Actual 2																				
2 Pipe excavation & installation	1824	1659																				
Pipe laying 1-3	Planned 270	Actual 214																				
Pipe laying 3-4	Planned 350	Actual 357																				
Pipe laying 4-5	Planned 210	Actual 219																				
Pipe laying 5-6	Planned 189	Actual 191																				
Pipe laying 6-8	Planned 425	Actual 421																				
Pipe laying 8-10	Planned 320	Actual 233																				
Boring for road crossing	Planned 2	Actual 0																				
Connection pipe	Planned 60	Actual 27																				
3 Back filling	Planned 2	Actual 0																				
4 Hydrostatic Field testing	Planned 1	Actual 0																				
5 Zonal meter installation	Planned 1	Actual 0																				
6 Connection works	21	10																				
Main connections	Planned 1	Actual 0																				
Branch connections	Planned 20	Actual 9																				
7 Manhole Construction	Planned 26	Actual 0																				
8 Pavement Restoration	Planned 1300	Actual 0																				

Handwritten signature

Progress Sheet & Schedule
Improvement of water supply distribution system in Madina

Work Item	Month		April							May						
	Total	Done	23	24	25	26	27	28	29	30	1	2	3	4	5	6
1 Test pit excavation & disconnection	64	21														
Pit # 1-8 & 64	Planned 8	Actual 8														
Pit # 13-17	Planned 5	Actual 5														
Pit# 32-48	Planned 18	Actual 5														
Pit # 9-12	Planned 4	Actual 1														
Pit# 18-31	Planned 14	Actual 0														
Pit # 49-63	Planned 15	Actual 2														
2 Pipe excavation & installation	1764	1405														
Pipe laying 1-3	Planned 270	Actual 190														
Pipe laying 3-4	Planned 350	Actual 357														
Pipe laying 4-5	Planned 210	Actual 219														
Pipe laying 5-6	Planned 189	Actual 191														
Pipe laying 6-8	Planned 425	Actual 421														
Pipe laying 8-10	Planned 320	Actual 233														
Boring for road crossing	Planned 2	Actual 0														
3 Back filling	Planned 2	Actual 0														
4 Hydrostatic Field testing	Planned 1	Actual 0														
5 Zonal meter installation	Planned 1	Actual 0														
6 Connection works	21	10														
Main connections	Planned 1	Actual 0														
Branch connections	Planned 20	Actual 9														
7 Manhole Construction	Planned 26	Actual 0														
8 Pavement Restoration	Planned 1300	Actual 0														

Progress Sheet & Schedule
 Improvement of water supply distribution system in Madina Town pilot area

Work Item	Month		May																												
	Total	Done	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29
1 Test pit excavation & disconnection	64	37																													
Pit # 1-8 & 64	Planned	5																													
Pit # 12-17	Planned	5																													
Pit# 32-48	Planned	18																													
Pit # 9-12	Planned	4																													
Pit# 18-31	Planned	14																													
Pit # 49-63	Planned	15																													
2 Pipe excavation & installation	Total	1824																													
Pipe laying 1-3	Planned	270																													
Pipe laying 3-4	Planned	350																													
Pipe laying 4-6	Planned	210																													
Pipe laying 5-8	Planned	199																													
Pipe laying 8-10	Planned	425																													
Boring for road crossing	Planned	2																													
Connection pipe	Planned	60																													
3 Back filling	Planned	2																													
4 Hydrostatic Field testing	Planned	2																													
5 Zonal meter installation	Planned	1																													
6 Connection works	Total	21																													
Main connections	Planned	1																													
Branch connections	Planned	20																													
7 Manhole Construction	Planned	26																													
8 Pavement Restoration	Planned	950																													

37

35

Test pit Result record



38

Progress Sheet & Schedule
 Improvement of water supply distribution system in Madina Town pilot ar

Work Item	Month		May																												June						
	Total	Done	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	1	2	3	
1 Test pit excavation & disconnection	Total	64																																			
Pit # 1-8 & 64	Planned	5																																			
Pit # 12-17	Planned	5																																			
Pit# 32-48	Planned	18																																			
Pit # 9-12	Planned	4																																			
Pit# 18-31	Planned	14																																			
Pit # 49-63	Planned	15																																			
2 Pipe excavation & installation	Total	1824																																			
Pipe laying 1-3	Planned	270																																			
Pipe laying 3-4	Planned	350																																			
Pipe laying 4-6	Planned	210																																			
Pipe laying 5-8	Planned	199																																			
Pipe laying 8-10	Planned	425																																			
Boring for road crossing	Planned	2																																			
Connection pipe	Planned	60																																			
3 Back filling	Planned	2																																			
4 Hydrostatic Field testing	Planned	2																																			
5 Zonal meter installation	Planned	1																																			
6 Connection works	Total	21																																			
Main connections	Planned	1																																			
Branch connections	Planned	20																																			
7 Manhole Construction	Planned	26																																			
8 Pavement Restoration	Planned	950																																			


Note:

36



2018/ 1

plan view map




No.	9
L	5000
W	1000
H	2000

site condition

free memo

Hard Stat
P.C.C Agg
BASE Sub Base
total D mix Agg
Soil 2000 mm

cross-section view




Signature

49

2 / 3 / 2018 / 1

plan view map



No.	7
L	6000
W	900
H	2400


site condition

free memo

Hard Stat 1000
Normal 1400

埋入 2/3
埋戻 3/3

cross-section view




Signature

47

2018/ 1

plan view map




No.	10
L	5000
W	900
H	2500

site condition

free memo

Soil Stat
1500 Hard Stat
Sub Base E1
P.C.C Agg Base
100mm normal
Soil

cross-section view




Signature

50

2018/ 1

plan view map




No.	8
L	6000
W	1000
H	2500

site condition

free memo

Hard Stat
Agg Stone
2500

cross-section view




Signature

48

plan view map

T-Shape @ Howk




No.	(3)
L	6000
W	1000
H	2500

site condition


free memo
Hard Soil
Slata
1000
Normal
Soil
1500

cross-section view



Signature

plan view map




No.	11
L	16'
W	3'
H	65'

site condition


free memo

cross-section view



Signature

plan view map




No.	(19)
L	6000
W	1000
H	25000

site condition


free memo
* Hard Soil
1000
* Normal
Soil
1500

cross-section view



Signature

plan view map




No.	12
L	3000
W	900
H	2000

site condition

free memo
* 1000 mm
Hard Slata
Agg Base + sub
Base in Soil
* 1000 mm
Normal Soil


cross-section view



Signature


plan view map

No.	(7)
L	6000
W	1000
H	2500



site condition
 free memo
 Hard soil
 Agg Stone
 Mix 2500


cross-section view



mm


plan view map

No.	(5)
L	6000
W	1000
H	2500



site condition
 free memo
 * Hard Soil
 1000
 * Normal Soil
 1500


cross-section view



mm


plan view map

No.	18
L	6000
W	1000
H	2500



site condition
 free memo
 # Hard Agg
 Mix Sub Base
 + Base + P.C.C
 Soil Mix Depth
 1500mm
 Normal Soil
 1000mm


cross-section view



mm


plan view map

No.	(6)
L	6000
W	1000
H	2500



site condition
 free memo
 Hard Stone
 Agg Stone
 2500mm

cross-section view




mm

2018/ /

plan view map

No.	20
L	5000
W	1000
H	2500




site condition

free memo

#Hard Slab
 B1M1 Agg Stone
 Mix + P.C. CDDing
 2500mm

cross-section view




Road Level

[Handwritten signature]

2018/ /

plan view map

No.	Addition 018A
	Near 18
L	5000+1500
W	1000
H	2500




site condition

free memo

#Hard Slab
 Agg Base + Sub
 Base P.C.C
 1500 mm
 and Normal
 Soil 1000mm

cross-section view




Road Level

[Handwritten signature]

2018/ /

plan view map

No.	21
L	8000
W	1000
H	2500




site condition

free memo

2000mm Hard
 Slab Agg Base
 Sub Base + P.C.C
 Mix Soil
 500 Normal
 Soil

cross-section view




Road Level

[Handwritten signature]

2018/ /

plan view map

No.	19
L	5000
W	900
H	2000




site condition

free memo

Slab Soil
 1000mm Agg
 Base & P.C.C
 Sub Base
 1000mm Normal
 Soil

cross-section view




Road Level

[Handwritten signature]

plan view map


No.	25
L	5000
W	1000
H	2500



site condition

free memo
 Street No 10
 Hard Slab
 Agg Base + Sub
 Base + P.C.C
 2000
 E₁ Normal
 Slab Soil
 500
 Road Level


cross-section view



Handwritten signature

plan view map


No.	23
L	5000
W	1000
H	2500



site condition

free memo
 * Hard Slab
 Agg Base
 Mix Soil
 + P.C.C Topping
 2000 mm
 Normal Soil
 500 mm


cross-section view



Handwritten signature

plan view map


No.	26
L	5000
W	1000
H	2500



site condition

free memo
 Street No 10
 * Hard Slab
 Mix with Road
 Cross + P.C.C E₁ Asphalt
 Depth 200
 Normal Soil
 500
 Road Level


cross-section view



Handwritten signature

plan view map


No.	24
L	6000
W	1000
H	2500







site condition

free memo
 * Agg Mix Base
 Sub Base + P.C.C
 old 2nd Road Exist
 at 1500 mm
 Agg Mix Soil
 1000 mm
 Mix Soil
 Soil 250 mm
 Road Level

cross-section view




Handwritten signature



2018/ 4/3

plan view map

No.	53
L	6000
W	900
H	2400




site condition

free memo

2400mm
P.c.c & Road
Agg Stone
Mix Soil
Brick Blastol
Soil data

cross-section view




73

2018/ 1

plan view map

No.	Addam Pit 30A Near Tanki
L	5000
W	1000
H	2500




site condition

free memo

Agg Base + P.c.c
Sub Base Brick
Blastol 1000mm
Normal Soil
1500

cross-section view




71

2018/ 4/3

plan view map

No.	54
L	6000
W	900
H	2400




site condition

free memo

2400mm
Hard Slata
Road Agg Stone
P.c.c Mix Soil

cross-section view




74

2018/ 1

plan view map

No.	31
L	6000
W	1000
H	2500




site condition





free memo

Hard Slata
Agg Base Mix
Sub Base + P.c.c
1000 & 1500
Normal Soil


cross-section view



72



plan view map




No.	40
L	5500
W	900
H	2200

site condition

free memo

1000mm Slab
PCC Agg Base +
Sub Base Mix
Soil & 1200mm
Soil & normal
Soil

cross-section view



plan view map




No.	38A
L	6000
W	900
H	2500

site condition


free memo

Hard Slab
Agg Base Mix & PCC
& Road Cryst
PCC
1500
Normal Soil
1000

cross-section view



plan view map




No.	41
L	5000
W	900
H	2200

site condition


free memo

Soil Slab
1200mm P.C.C
& Agg Base w/BM
+ Sub Base total
Road Cryst
1000mm Normal
Soil

cross-section view



plan view map




No.	39
L	4500
W	900
H	2200


site condition

free memo

Soil Slab
1000mm Agg
Base PCC
Sub Base Mix
Soil
1000 Normal
Soil

cross-section view







No.	46
L	4000
W	900
H	2000

site condition



free memo
Soil Stak
1000mm Soil
PCC + Agg Base
WBM & Agg Sub
Base Soil Max
1000mm is Normal
Soil Stak



No.	43
L	7000
W	7000
H	2500

site condition



free memo
* Hard Stak
Mud Agg
Base s.p.c.c
Road Cnst M ix
Soil 2.50m



No.	48
L	4000
W	900
H	2500

site condition


free memo
Hard Stak
1500mm Base
P.C.C. & Agg Sub
Base
Normal Soil
1000mm








No.	44
L	4500
W	900
H	2000

site condition

free memo
Soil Stak
1000mm Soil
P.C.C. Agg Base
& S.B. Base mix
1000mm Soil
Normal









No.	55
L	5000
W	900
H	2400

site condition
 free memo
 1000 P.C.C + Base
 Agg WBM + Agg Sub
 Base Soil &
 1400 Normal
 Soil




Road Level
 mpa




No.	53
L	4500
W	900
H	2500

site condition
 free memo
 1000 mm Slab
 Hard P.C.C + Base
 WBM + Sub Base
 Road CRUST Soil
 1500 mm Normal
 Soil




Road Level
 mpa




No.	56
L	4500
W	900
H	2000

site condition
 free memo
 1000mm
 P.C.C + Agg Base
 WBM + Sub Base
 Old Road Crust
 1000 mm Normal
 Soil Slab




Road Level
 mpa




No.	54
L	4000
W	900
H	2200

site condition
 free memo
 1000mm Slab
 P.C.C + Agg Slone
 Crushed + WBM +
 Sub Base Soil
 1200mm Normal
 Soil





Road Level
 mpa





No.	59
L	3500
W	900
H	2000

site condition
 free memo
 Soil Stat
 100mm P.C.C
 Agg Base w/BM
 & sub Base Mix
 Soil
 1000mm Normal
 Soil





No.	57
L	6000
W	900
H	2500

site condition
 free memo
 1000 Hard Agg Base
 + sub Base + pcc
 1500 Normal Soil




No.	60
L	3000
W	900
H	2000

site condition
 free memo
 Soil Stat
 1000mm Agg Base
 & pcc Sub Base
 Mix Soil
 1000mm Normal
 Soil




No.	58
L	6000
W	900
H	2400

site condition
 free memo
 Soil Stat
 1200mm Agg Base
 & pcc Sub Base
 Mix Soil
 1200mm Normal
 Soil




2/3/2018/ 1



No.	64
L	6000
W	900
H	2400


site condition
free memo
1000 Hand start
1600 Normal Soil



掘削 2/3
埋戻 2/3
map


101

2018/ 1



No.	61
L	3800
W	900
H	2000


site condition
free memo
Soil State
1000mm Agg Base
P.C.C & Sub Base
Mix Soil
1000mm Normal



Soil
Road Levels
map


99

2018/ 1



No.	66
L	6000
W	900
H	2500


site condition
free memo
Xing Pit
for Excavation
Lineament Pit
Sheet No.2



map


102

2018/ 1



No.	62
L	5000
W	900
H	2200

site condition
free memo
Soil State
1200mm
P.C.C & Base w/m
Agg Sub Base
Mix Soil
1000mm Normal



Soil
Road Levels
map

100

Improvement of water supply distribution system in Madina Town pilot area

Date 9-Mar-18
Location Pit #8



Date 9-Mar-18
Location Pit #8



Improvement of water supply distribution system in Madina Town pilot area

Date 5-Mar-18
Location Pit #1



Date 9-Mar-18
Location Pit #1



Date 5-Mar-18
Location Pit #2



P1053

P1031

Improvement of water supply distribution system in Madina Town pilot area

Date 9-Mar-18
Location Pit #13



P1064

Improvement of water supply distribution system in Madina Town pilot area

Date 5-Mar-18
Location Pit #4



Date 9-Mar-18
Location Pit #5



P1042

Improvement of water supply distribution system in Madina Town pilot area

Date 9-Mar-18

Location Pit #14



Date 9-Mar-18

Location Pit #15



Date 5-Mar-18

Location Pit #16




Hydrostatic Test Report

Improvement of water supply distribution system in Madina Town pilot area


Date 9-Mar-18

Location Pit #64





Test Phase
Time 19:35 hrs
Pressure 6.03 bar



Test Phase
Time 19:55 hrs
Pressure 5.95 bar

113

Hydrostatic Test Report

Name of Work	Improvement of water supply distribution network in Pilot Area Madina Town		
Date of Testing	14-May-18		
Test segment	CP-1 ~ IP-5	Tested Length	2800'
No. of Joints	121	Special/fittings	11 No valves
Pipe material	HDPE	Special/fittings	Bends, Tee, Red
Pipe Diameter		Special/fittings	
Working pressure actual	1.82 bar		
Working pressure max	3.7 bar		
Test Pressure	5.55	Standard	ASTM F-2164

Initial Expansion Phase

Start Time	17:10	Dial Reading	6.18 bar
30 min lap		Dial Reading	bar
60 min lap	18:20	Dial Reading	5.47 bar
90 min lap	18:55	Dial Reading	5.38 bar
120 min lap	19:10	Dial Reading	5.36 bar
150 min lap		Dial Reading	bar
180 min lap		Dial Reading	bar
240 min lap		Dial Reading	bar


Test Phase

Start Time	19:35	Dial Reading	6.03 bar
10 min lap	19:45	Dial Reading	5.99 bar
20 min lap	19:55	Dial Reading	5.95 bar
30 min lap	20:05	Dial Reading	5.91 bar
40 min lap	20:15	Dial Reading	5.88 bar
50 min lap	20:25	Dial Reading	5.86 bar
60 min lap	20:35	Dial Reading	5.84 bar


Remarks

Due to time restraints initial expansion phase reduced to 2 hrs
Total pressure loss during test phase is 0.19 bar against the allowable pressure drop of 0.3 bar.

111



Test Phase
Time 20:25 hrs
Pressure 5.86 bar



Test Phase
Time 20:35 hrs
Pressure 5.84 bar

114



Initial Expansion Phase
Time 17:10 hrs
Pressure 6.18 bar




Initial Expansion Phase
Time 18:20 hrs
Pressure 5.47 bar

112

Madina town pipe installation work Phase 1.2 S-free

Pipe Installation	total 1723.0m
Branch Connection	total 108.5m



118

117



Pressure releasing

115


Piping drawing
Pipe joint records
joint photos

IMPROVEMENT OF WATER SUPPLY DISTRIBUTION SYSTEM
IN MADINA TOWN AREA

15th Feb, 2018 ~

Constructor
MUHAMMAD HANIF ANJUM

pipe joint records management



day/month	6/5/18	6/5/18	6/5/18	6/5/18	6/5/18	6/5/18	6/5/18	6/5/18
mark (No)	CP1 321	322	V. Bed 324	V. R/P 325	V. Bed 326	V. R/P 327	328	CP2 329
pipe depth	7'	7'	6.5'	6.5'	4.5'	4.5'	3.5'	3.25'
offset R/L	17'	17'	16'	16'	16'	14'	13'	12'
joint condition	visual	5	3	4	4	4	4	4
	touch	4	4	3	3	5	5	3
status before back filling								
section distance		3'	1'	1'	1'	6'	40'	40'
notes								


confirmation person signature

Project Manager	Site Engineer	Site Supervisor

121

119

pipe joint records management




day/month	6/5/18	28/4/18						
mark (No)	CP2 321	322						
pipe depth	3.25'	3.75'						
offset R/L	4'	4.5'						
joint condition	visual	4						
	touch	4						
status before back filling								
section distance		18'						
notes								

confirmation person signature


Project Manager	Site Engineer	Site Supervisor

122

120



pipe joint records management



day/month	6/4/18	6/4/18				
mark (No)	IP1 306 307	CP2 308 309				
pipe depth	3	3				
offset R/L	4	4.5				
joint condition	visual	4				
repaired	touch					
		3				
	status before back filling					
section distance	5'	14'				
notes						

confirmation person signature	Project Manager	Site Engineer <i>M. J. Al...</i>	Site Supervisor
-------------------------------	-----------------	-------------------------------------	-----------------

125

pipe joint records management




day/month	15/4/18	28/4/18	28/4/18			
mark (No)	IP1 314	315	IP1 316 319			
pipe depth	3.75	2.75	2.75			
offset R/L	4.5'	4.5'	4.5'			
joint condition	visual	3	4			
repaired	touch					
		4	4			
	status before back filling		water leakage	down		
section distance	20'	15'				
notes			Now 6" HDPE LHD			

confirmation person signature	Project Manager	Site Engineer	Site Supervisor <i>M. J. Al...</i>
-------------------------------	-----------------	---------------	---------------------------------------

123

pipe joint records management




day/month	4/4/18	4/4/18	4/4/18	4/4/18	6/4/18		
mark (No)	IP2 301	302	303	304	IP1 305 307		
pipe depth	3.1	3.25	3.2	3	3		
offset R/L	3.5	3	3	3.25			
joint condition	visual	4	3	4	4		
repaired	touch						
		4	4	3	4		
	status before back filling						
section distance	40'	5'	40'	40'			
notes				backfilling			

confirmation person signature	Project Manager	Site Engineer <i>M. J. Al...</i>	Site Supervisor
-------------------------------	-----------------	-------------------------------------	-----------------

126

pipe joint records management



day/month	6/4/18	15/4/18	15/4/18	15/4/18		
mark (No)	CP3 308	309	310	311		
pipe depth	3	3	3	3		
offset R/L	4.5	6	5	5		
joint condition	visual	4	3	4		
repaired	touch					
		4	4	5		
	status before back filling					
section distance	14'	40'	40'			
notes						

confirmation person signature	Project Manager	Site Engineer	Site Supervisor
-------------------------------	-----------------	---------------	-----------------

124




Joint # 303
 Location IP2-40
 Straight
 Date 4-Apr



Joint # 304
 Location IP2-45
 Straight
 Date 4-Apr

pipe joint records management



Day/month	27/3/18	4/4/18	4/4/18						
mark (dist)	0	0	IP2 1.50						
pipe diam	3.1	3	3.1						
inlet RL	3	3	3						
joint	usual								
condition		4	3						
condition	touch								
	4	4							
condition	Mark								
	before								
condition	back filling								
section distance	4m	40'	16.5'						
notes									

confirmation person signature
 Project Manager Site Engineer Site Supervisor



Joint # 305
 Location IP2-85'
 Straight
 Date 4-Apr

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joint # 300
 Location IP2+16.5'
 Straight
 Date 4-Apr



Joint # 306, 307
 Location IP2-125'
 IP1
 Bend
 Date 6-Apr



Joint # 301, 302
 Location IP2
 Bend
 Date 4-Apr



Joint # 315
 Location CP3-144'
 Straight
 Date 28-Apr



Joint # 308, 309, 310
 Location IP1-5'
 CP-3
 Tee
 Date 6-Apr



Joint # 315
 Location CP3-162'
 IP1
 Bend
 Date 28-Apr



Joint # 312
 Location CP3-14'
 Straight
 Date 15-Apr

133

131




Joint # 319
 Location CP3-180'
 Straight
 Date 6-May



Joint # 313
 Location CP3-64'
 Straight
 Date 15-Apr



Joint # 320, 321
 Location CP3-182'
 CP2
 Straight
 Date 6-May



Joint # 314
 Location CP3-104'
 Straight
 Date 15-Apr

134

132



Joint # 336, 335
332, 334
Location CP2-86'
V-Bend
Date 6-May



Joint # 325
Location CP2-40'
Straight
Date 6-May




Joint # 331
Location CP2-90'
Stub end
Date 6-May



Joint # 339
Location CP2-80'
Straight
Date 6-May


137

135



CP3 ~ CP4

138




Joint # 338
Location CP2-86'
V-Bend
Date 6-May



Joint # 337
Location CP2-86'
V-Bend
Date 6-May

136



Joints # 21
 Location CP3-48.5'
 Straight
 Date 15-Mar

pipe joint records management

mark valve tee pipe connection point
 corner pipe 90° 45° 22° reducer


date/month	15/3/18	15/3/18					
mark (top)							
pipe diam	21	20	21				
offset H/L	3	3.1					
joint condition	4	3					
status	4	4					
notes	Sand fill	Sand fill + water					
section distance	40'	40					
notes	CP4						

confirmation
 person
 signature

Project Manager	Site Engineer	Site Supervisor


141

139



142

Improvement of water supply distribution system in Madina Town pilot area
 HDPE Pipe Joints



Joints # 1, 2, 3
 Location CP4
 Tee
 Date 14-Mar



Joints # 20
 Location CP3-8.5'
 Straight
 Date 15-Mar

140



Joints # 11
 Location CP4+59'
 Straight
 Date 14-Mar



Joints # 12
 Location CP4+99'
 Straight
 Date 14-Mar

pipe joint records management

mark valve tee pipe connection point
 corner pipe 90° 45° 22° reducer

day/month	14 Mar-18	14 Mar	14 Mar	14 Mar	14 Mar	14 Mar	14 Mar
mark (top)							
mark (bot)	1 2	10	11	12	13	14 15	19
mark depth	2.75	2.75	2.9	3	2.8	2.7	2.8
offset (ft)	4	4	3.9	3.9	3.9	3.7	3.8
joint condition	4	4	5	4	4	4	4
touch	4	5	4	5	3	4	5
section distance	Tee	19'	40'	40'	39'	2'	40'
notes	CP4	CP4+19	CP4+59	CP4+99	CP4+138	CP4+140	CP5+40

Pipe is crossing above sewer pipes at CP4+42-CP5

confirmation person	Project Manager	Site Engineer	Site Supervisor
signature			


145

143



Joints # 13, 14, 15
 Location CP5
 Straight + Tee
 Date 14-Mar

**Improvement of water supply distribution system in Medina Town pilot area
 HDPE Pipe Joints**



Joints # 1, 2, 3
 Location CP4
 Tee
 Date 14-Mar



Joints # 10
 Location CP4+19'
 Straight
 Date 14-Mar

146

144

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints




Joints # 14, 15
Location CP5
Tee
Date 14-Mar



Joints # 19
Location CP5+40'
Straight
Date 15-Mar

149



147

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints




Joint # 22
Location IP3 - 48'
(CP5+80')
Straight
Date 16-Mar



Joint # 23
Location IP3 - 40'
(CP5+88')
Straight
Date 16-Mar

150

pipe joint records management




day/month	15/3/18	16/3/18	16/3/18	17/3/18		
mark (ft)	14 15	19	22	23	24	25
pipe depth	2.75	2.8	3	2.75	2.9	
offset W/L	2.8	2.8	3	3	-	
joint	4	3	4	3		
condition						
condition	4	3	4	3		
condition	3	4	4	4		
condition	Sand	Under Sewer Pipe	Sand	Near Landgap point of existing W/S line through water chamber		
section distance	40'	40'	8'	40'		
notes	CP5		Sewer pipes 2Nus	IP3		inside water chamber

confirmation
person
signature

Project Manager	Site Engineer	Site Supervisor

148

pipe joint records management



day/month	18/5/18	18/5/18	19/5/18	21/5/18	21/5/18	22/5/18	22/5/18
mark (IP3)	24	25	26	27	28	29	30
pipe depth	3'	3'	3'	1.75'	2.25'	2.75'	3'
offset RL	4'	4.2'	4.5'	5'	5'	6'	6'
joint condition	4	3	5	4	4	4	5
visual							
branch	4	4	4	3	4	4	4
status before back filling						sewer leakage	
section distance	40'	40'	40'	40'	40'	40'	40'
notes	Under 3 sewer pipe	Under 3 sewer pipe	Above 4x3 sewer pipes 2' in 0' depth				

confirmation	Project Manager	Site Engineer	Site Supervisor
signature			

153

Improvement of water supply distribution system in Medina Town pilot area
HDPE Pipe Joints



Joint # 24, 25
Location IP3
Straight
Date 17-Mar

151


pipe joint records management



day/month	22/5/18	22/5/18	25/5/18	25/5/18	25/5/18	25/5/18	25/5/18
mark (IP3)	32	33	34	35	36	37	38
pipe depth	3'	3'	2.75'	2.75'	2.5'	2.5'	2.75'
offset RL	6'	5.75'	6'	6'	6.25'	6'	6.25'
joint condition	4	4	5	4	5	4	4
visual							
branch	4	4	4	4	5	3	3
status before back filling	Definitely repaired	was leakage water	was leakage water	was leakage water	was leakage water	was leakage water	leakage water
section distance	40'	40'	40'	40'	28'	4'	12'
notes	sewer pipe leakage		Underground existing pipe leakage	Existing 4x3 pipe in excavation	Existing 4x3 pipe in excavation	Existing 4x3 pipe in trench	Existing 4x3 pipe in trench


confirmation	Project Manager	Site Engineer	Site Supervisor
signature			

154



152

pipe joint records management




day/month	27/5/18	28/5/18	03/6/18	24/6/18	25/6/18	26/6/18		
mark (ft)	0	0	0	0	0	IP4	0	
pipe depth	2.5	2.75	2.5	2.75	2.75	2.5		
offset - RL	6.5	7	7	6.5	6.75	-		
joint condition	visual	4	5	4	3	5		
	touch		3	4	4	4		
status history	back filling							
						Recurve		
section distance	40'	40'	40'	20'	40'			
notes	Align		Align					

confirmation
 P E R S O N
 S I G N A T U R E

Project Manager	Site Engineer	Site Supervisor
	<i>[Signature]</i>	

157

pipe joint records management



day/month	25/5/18	25/5/18	26/5/18	26/5/18	26/5/18	26/5/18	24/5/18	27/5/18
mark (ft)	39	40	41	42	43	44	45	46
pipe depth	2.75	3	2.8	3	2.5	2.75	2.75	2.5
offset - RL	6.25	6	6.25	6	6.25	6.5	6.5	7
joint condition	visual	4	3	4	3	4	4	4
	touch		5	4	4	4	5	4
status history	back filling							
section distance	40'	40'	40'	40'	40'	40'	40'	40'
notes			use pipe	Align with	Align with	Align with	Align with	Align with

confirmation
 P E R S O N
 S I G N A T U R E

Project Manager	Site Engineer	Site Supervisor
	<i>[Signature]</i>	

155

Improvement of water supply distribution system in Madina Town pilot area
 HDPE Pipe Joints



Joint # 24, 25
 Location IP3
 Straight
 Date 17-Mar



Joint # 26
 Location IP3 + 40'
 Straight
 Date 18-Mar

pipe joint records management



day/month	27/5/18	27/5/18	27/5/18	27/5/18	27/5/18	27/5/18	27/5/18	27/5/18
mark (ft)	0	0	0	0	0	0	0	0
pipe depth	46	47	45	49	50	51	52	53
offset - RL	2.5	2.5	2.25	2.7	3	2.75	2.5	2.5
joint condition	visual	7	6.75	7	7	6.5	6.5	6.5
status history	back filling	5	5	4	4	5	3	4
		5	4	4	5	5	4	5
status history	back filling							
				Recurve	Recurve			
section distance	40'	37'	40'	40'	40'	20'	40'	
notes	Align	Align	Align	Align	Align	Align	Align	Align

confirmation
 P E R S O N
 S I G N A T U R E

Project Manager	Site Engineer	Site Supervisor
	<i>[Signature]</i>	

158

156



Joint # 31
Location IP3 +240'
Straight
Date 22-Mar



Joint # 27
Location IP3 +80'
Straight
Date 18-Mar



Joint # 32
Location IP3 +280'
Straight
Date 22-Mar



Joint # 28
Location IP3 +120'
Straight
Date 18-Mar

161

159



Joint # 33
Location IP3 +320'
Straight
Date 22-Mar



Joint # 29
Location IP3 +160'
Straight
Date 21-Mar



Joint # 34
Location IP3 +356'
Straight
Date 25-Mar




Joint # 30
Location IP3 +200'
Straight
Date 21-Mar

162

160



Joint # 39
Location IP3 +480'
Straight
Date 25-Mar



Joint # 35
Location IP3 +396'
Straight
Date 25-Mar



Joint # 40
Location IP3 +520'
Straight
Date 25-Mar




Joint # 36
Location IP3 +436'
Straight
Date 25-Mar

165

163



Joint # 41
Location IP3 +560'
Straight
Date 26-Mar



Joint # 37
Location IP3 +464'
Straight
Date 25-Mar



Joint # 42
Location IP3 +600'
Straight
Date 26-Mar




Joint # 38
Location IP3 +468'
Straight
Date 25-Mar

166

164



Joint # 47
Location IP3 +800'
Straight
Date 27-Mar



Joint # 43
Location IP3 +640'
Straight
Date 26-Mar



Joint # 48
Location IP3 +837'
Straight
Date 27-Mar



Joint # 44
Location IP3 +680'
Straight
Date 26-Mar

169


167



Joint # 49
Location IP3 +877'
Straight
Date 27-Mar



Joint # 45
Location IP3 +720'
Straight
Date 26-Mar



Joint # 50
Location IP3 +917'
Straight
Date 27-Mar



Joint # 46
Location IP3 +760'
Straight
Date 27-Mar

170

168



Joint # 55
 Location IP3 +1097'
 Straight
 Date 28-Mar



Joint # 51
 Location IP3 +957'
 Straight
 Date 27-Mar



Joint # 56
 Location IP3 +1137'
 Straight
 Date 28-Mar



Joint # 52
 Location IP3 +977'
 Straight
 Date 27-Mar

173

171

Joint # 57
 Location IP3 +1157'
 Straight
 Date 28-Mar



Joint # 53
 Location IP3 +1017'
 Straight
 Date 27-Mar



Joint # 58
 Location IP3 +1195'
 IP-4
 Bend
 Date 28-Mar



Joint # 54
 Location IP3 +1057'
 Straight
 Date 28-Mar

174

172

pipe joint records management



day/month	29/2/18	29/3/18	30/3/18	30/3/18
mark (ft)	CP6 65 64	66	67	CP7 69
pipe depth	2.75	2.35	2.75	3
offset (ft)	9.5	9	10	10
joint condition	visual	4	4	4
	touch			
	status before back filling	3	4	5
section distance	40	40	33	
notes		Align steel pipe + hole		Reduce 4 to 2.5" pipe

confirmation person signature


Project Manager	Site Engineer	Site Supervisor
	<i>[Signature]</i>	

177

IP4 ~ IP5

175

pipe joint records management



day/month	30/3/18	31/3/18	31/3/18	31/3/18	31/3/18
mark (ft)	CP7 68 67	71	72	73	CP8 74 76
pipe depth	3	2.75	2.35	3	2.75
offset (ft)	10	9.5	9.5	9.5	9.5
joint condition	visual	3	4	4	5
	touch				
	status before back filling	4	4	3	4
section distance	40	40	40	37	
notes					Reduce 4 to 2.5" pipe + align

confirmation person signature

Project Manager	Site Engineer	Site Supervisor
	<i>[Signature]</i>	

178

pipe joint records management




day/month	29/2/18	29/2/18	29/2/18	29/2/18	29/2/18
mark (ft)	CP6 65	66	67	68	CP6 65
pipe depth	2.5	3	2.5	3	2.75
offset (ft)	10	9.5	9	9.5	9.5
joint condition	visual	4	3	4	5
	touch				
	status before back filling	5	4	4	4
section distance	40	40	40	37	
notes					Align steel pipe + hole aligned

confirmation person signature

Project Manager	Site Engineer	Site Supervisor
	<i>[Signature]</i>	

176

pipe joint records management




day/month	1/4/18	1/4/18	1/4/18	24/4/18	24/4/18	24/4/18	24/4/18	24/4/18	27/4/18
mark (No)	CP 184			OX 180	OX 180				CP 183
pipe depth	2.75	3	3.25	3.25	3.25	3	3	3	3.25
offset R/L	9	9.5	10	10	10	10	10.5	10	
joint condition	visual								
visual		4	3	4	4	5	3	4	
touch									
touch		4	4	5	4	4	4	5	
status before back filling									
section distance		40'	40'	2'		40'	37'	2'	
notes						Existing mis label	Existing mis label	mis label	

confirmation person signature

Project Manager	Site Engineer	Site Supervisor
		<i>[Signature]</i>

181

pipe joint records management



day/month	30/3/18	30/3/18	1/4/18	1/4/18	1/4/18	1/4/18
mark (No)	CP 85					CP 80
pipe depth	2.75	3	2.75	2.9	2.5	3.5
offset R/L	9.5	9.5	10	10	9.5	9.5
joint condition	visual					
visual		4	5	4	4	4
touch						
touch		4	4	3	4	3
status before back filling						Power linkage
section distance		40'	40'	40'	40'	3'
notes	Power link & sensor CP					Power link CP 6'

confirmation person signature

Project Manager	Site Engineer	Site Supervisor
		<i>[Signature]</i>

179

pipe joint records management




day/month	22/4/18	22/4/18
mark (No)	CP 184	CP 183
pipe depth	3.25	7.5
offset R/L	10	10
joint condition	visual	
visual		4
touch		
touch		3
status before back filling		
section distance		4'
notes		Marked for change

confirmation person signature

Project Manager	Site Engineer	Site Supervisor
		<i>[Signature]</i>

182

pipe joint records management



day/month	1/4/18	1/4/18	1/4/18	2/4/18	1/4/18
mark (No)	CP 82				CP 84
pipe depth	3.5	2.75	2.9	3	2.75
offset R/L	9.5	9	9.5	9.5	9
joint condition	visual				
visual		4	4	4	3
touch					
touch		3	5	4	4
status before back filling					Power linkage
section distance		40'	40'	13'	9'
notes				Under backfill CP	

confirmation person signature

Project Manager	Site Engineer	Site Supervisor
		<i>[Signature]</i>

180

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 63, 64 & 65
Location IP4+157'
CP-6
Tee
Date 29-Mar

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 59
Location IP4
Bend
Date 28-Mar



Joint # 66
Location IP4+197'
Tee
Date 29-Mar



Joint # 60
Location IP4+40'
Straight
Date 29-Mar

185


183

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 67
Location IP4+237'
Straight
Date 30-Mar

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 61
Location IP4+80'
Straight
Date 29-Mar



Joint # 68, 69, 70
Location IP4+270'
CP-7
Tee
Date 30-Mar

Joint # 62
Location IP4+120'
Straight
Date 29-Mar

186

184

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 77
Location IP4+397'
Straight
Date 30-Mar

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 71
Location IP4+310'
Straight
Date 30-Mar



Joint # 78
Location IP4+403'
Straight
Date 1-Apr



Joint # 72
Location IP4+314'
Straight
Date 30-Mar

189

187

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 79
Location IP4+443'
Straight
Date 1-Apr

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 73
Location IP4+354'
Straight
Date 30-Mar



Joint # 80, 81, 82, 83
Location IP4+487
Straight
Tee
CP-9
Date 1-Apr



Joint # 74, 75, 76
Location IP4+357'
CP-8
Tee
Date 30-Mar

190

188

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 90
Location IP4+645'
Straight
Date 1-Apr



Joint # 91
Location IP4+658'
Straight
Date 1-Apr

193

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 84
Location IP4+527'
Straight
Date 1-Apr



Joint # 85
Location IP4+567'
Straight
Date 1-Apr

191

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 158
Location IP4+660'
Valve
Date 24-Apr



Joint # 159
Location IP4+660'
Valve
Date 24-Apr

194

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 86
Location IP4+595'
Straight
Date 2-Apr



Joint # 87, 88, 89
Location IP4+605'
Tee
CP-10
Date 1-Apr
2-Apr

192

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 150
Location IP4+737'
Bore (IP5)
V-Bend
Date 22-Apr

197

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 160
Location IP4+700'
Straight
Date 24-Apr

195



Joint # 161
Location IP4+735'
V-Bend
Date 24-Apr

IP5 ~ IP6

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 152, 153
Location IP4+737'
Bore (IP5)
V-Bend
Date 22-Apr




Joint # 151
Location IP4+737'
Bore (IP5)
V-Bend
Date 22-Apr

198

196

pipe joint records management



Day/month	6/4/18	6/4/18	11/4/18	11/4/18	11/4/18			
mark (ft)	CP-13 99				CP-14 117			
pipe depth	3.25	3'	3.25	3'	2'			
offset R/L	4.5'	4.5'	4'	4.5'	4'			
joint condition	visual	4	3	4	3			
seepage	touch							
	status before back filling	5	4	4	4			
notes				Some leakage	Some leakage			
section distance	40'	40'	40'	40'				

confirmation person signature	Project Manager	Site Engineer	Site Supervisor
-------------------------------	-----------------	---------------	-----------------

201

pipe joint records management




Day/month	22/4/18	23/4/18	23/4/18	23/4/18	23/4/18	23/4/18		
mark (ft)	V-1 151	CP-11 154	155	156	157	92		
pipe depth	7.5'	4'	4'	3.25'	3'			
offset R/L		5'	5'	4.5'	4.5'			
joint condition	visual	4	4	3	4			
seepage	touch							
	status before back filling	4	5	4	3			
section distance	40'	1'	40'	15'	40'			
notes		W/S leakage	W/S leakage	W/S leakage				

confirmation person signature	Project Manager	Site Engineer	Site Supervisor
-------------------------------	-----------------	---------------	-----------------

199

pipe joint records management




Day/month	11/4/18	11/4/18	11/4/18	14/4/18	14/4/18	14/4/18		
mark (ft)	CP-14 117					CP-6 123		
pipe depth	2'	3'	3.25'	2.75'	2.75'	2.5'		
offset R/L	4'	4.5'	4.5'	4.5'	4.5'	4.5'		
joint condition	visual	4	4	4	3	4		
seepage	touch							
	status before back filling	4	5	4	4	5		
notes				Some leakage				
section distance	30'	40'	34'	1'	7.25'			

confirmation person signature	Project Manager	Site Engineer	Site Supervisor
-------------------------------	-----------------	---------------	-----------------

202

pipe joint records management



Day/month	3/4/18	3/4/18	6/4/18	6/4/18	6/4/18			
mark (ft)	CP-9 94				CP-8 99			
pipe depth	3.25	3.25	3	3.25	3.25			
offset R/L	4.5	4.5	4.5	4.5	4.5			
joint condition	visual	4	4	4	4			
seepage	touch							
	status before back filling	4	3	5	4			
section distance		40'	40'	7'	40'			
notes								

confirmation person signature	Project Manager	Site Engineer	Site Supervisor
-------------------------------	-----------------	---------------	-----------------

200

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 92
Location IP5+95'
CP-12
Tee
Date 3-Apr

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 155
Location IP4+777
IP-5
CP11
MV
Date 23-Apr



Joint # 93
Location CP-12+1'
CP-12
Tee
Date 3-Apr
IP5+96'



Joint # 155
Location IP5
CP11
MV
Date 23-Apr

205

203

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 94
Location CP12
Tee
Date 3-Apr

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 156
Location IP5+40'
Straight
Date 23-Apr



Joint # 95
Location CP12+40'
Straight
Date 3-Apr
IP5+136'



Joint # 157
Location IP5+55'
Straight
Date 23-Apr

206

204

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joint # 113
 Location CP13+80'
 Straight
 Date 11-Apr
 IP5+303'



Joint # 114
 Location CP13+120'
 Straight
 Date 11-Apr
 IP5+343'

209

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joint # 96
 Location CP12+80'
 Straight
 Date 6-Apr
 IP5+176'



Joint # 97
 Location CP12+87'
 Straight
 Date 6-Apr
 IP5+183'

207

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joint # 115, 116, 117
 Location CP13+131'
 CP14
 Tee
 Date 11-Apr
 IP5+354'




Joint # 118
 Location CP14+30
 Straight
 Date 11-Apr
 IP5+384'

210

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joint # 98, 99, 100
 Location CP12+127'
 CP13
 Tee
 Date 6-Apr
 IP5+223'



Joint # 101
 Location CP13+40'
 Straight
 Date 6-Apr
 IP5+263'

208

IP6 ~ IP6a

213

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 119
Location CP14+70
Straight
Date 11-Apr
IP5+424'



Joint # 120
Location CP14+104
Valve
Date 14-Apr
IP5+458

211

pipe joint records management




day/month	14/4/18	14/4/18	7/4/18	7/4/18	7/4/18	7/4/18	7/4/18	7/4/18	8/4/18	8/4/18
mark (No)	122	124	102	105	104	105	106	107		
pipe depth	2.5	3	3	3	2.75	3	3.25	3.25		
offset ft/c	5.5	6	6	6.5	6	6	6	6.5		
joint condition		4	3	4	4	3	4	3		
visual	Blotch	5	4	5	4	3	4	4		
section distance	23'	40'	40'	40'	40'	40'	40'	40'		
notes		Edging with 10cm		Scum	Leakage					


confirmation person signature
Project Manager Site Engineer Site Supervisor

214

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Valve
Date 14-Apr
IP5+459'




Joint # 122
Location CP-14+113
Bend
IP-6
Date 14-Apr
IP5+467'

212

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints




Joint # 123
Location IP6
Date 14-Apr



Joint # 124
Location IP6+23'
Date 14-Apr

217

pipe joint records management



day/month	8/4/18	8/4/18	9/4/18	9/4/18	9/4/18	9/4/18
mark (No)	107	108	109	110	111	112
pipe depth	3.25	3'	3.25	3	3.25	3.25
offset R/L	6	6	6.5	7	7	7'
joint condition	visual	4	5	4	3	4
	touch	5	4	4	4	5
status before back filling						
section distance	40'	40'	40'	40'	9'	
notes						

confirmation person signature
Project Manager Site Engineer Site Supervisor
[Signature]

215

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints




Joint # 102
Location IP6+63'
Date 7-Apr



Joint # 103
Location IP6+103'
Date Straight 7-Apr

218

pipe joint records management




day/month	9/4/18	15/4/18	15/4/18	15/4/18
mark (No)	119	120	121	122
pipe depth	3	3.25	3	3.25
offset R/L	6.5	6.25	6.5	6.5
joint condition	visual	5	4	4
	touch	3	3	4
status before back filling				
section distance	9'	3'	11'	
notes		End of 1st day	End of 2nd day	

confirmation person signature
Project Manager Site Engineer Site Supervisor
[Signature]

216

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints




Joint # 108
Location IP6+303'
Straight
Date 8-Apr



Joint # 109
Location IP6+343'
Straight
Date 9-Apr

221

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 104
Location IP6+143'
Straight
Date 7-Apr



Joint # 105
Location IP6+183'
Straight
Date 7-Apr

219

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 110
Location IP6+403'
Straight
Date 9-Apr



Joint # 111
Location IP6+423'
Straight
Date 9-Apr

222

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints




Joint # 106
Location IP6+223'
Straight
Date 8-Apr



Joint # 107
Location IP6+263'
Straight
Date 8-Apr

220



225

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 112
Location IP6+432'
Straight
Date 9-Apr



Joint # 125
Location IP6+441'
Straight
Date 15-Apr

223

pipe joint records management



Day/months	15/4/18	15/4/18	15/4/18	15/4/18	15/4/18
mark (ft)	IP6a				IP6b
pipe depth	2.5'	3'	3'	2.75'	2.5'
offset R/L	7.5'	7.5'	7.25'	8.5'	8.5'
joint condition	visual				
empire		3	4	4	1
touch		4	5	5	4
status					
before					
back filling					
section distance		40'	40'	40'	4'
notes					

confirmation
person
signature

Project Manager	Site Engineer	Site Supervisor
		<i>[Signature]</i>

226

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 126
Location IP6+444
Straight
Date 15-Apr



Joint # 127, 128
Location IP6+456'
IP6a
Bend
Date 15-Apr

224

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 132, 133
Location IP6a+124'
IP6b
Date 18-Apr

229

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints




Joint # 127, 128
Location IP6a
Date 15-Apr



Joint # 129
Location IP6a+40'
Date 15-Apr

227



IP6b ~ IP6c

230

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 130
Location IP6a+80'
Date 15-Apr



Joint # 131
Location IP6a+120'
Date 18-Apr

228

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 135
Location IP6b+64'
Date 18-Apr




Joint # 136, 137
Location IP6b+104'
IP6c
CP15
Date 18-Apr

233

pipe joint records management


mark: valve tee pipe connection point
corner pipe 90° 45° 22°



day/month	15/4/18	15/4/18	15/4/18	15/4/18				
mark (ft)	IP6b 133	134	135	136 F15				
pipe depth	2.5	3	3	5				
offset ft	10'	7.5	7.5	6.5				
joint condition	visual	3	4	3				
touch		4	5	3				
status before pack filling								
section distance		24'	40'	40'				
notes								

confirmation person signature
Project Manager Site Engineer Site Supervisor

231



234

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 132, 133
Location IP6b
Date 18-Apr



Joint # 134
Location IP6b+24'
Date 18-Apr


232

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints

Joint # 139
Location IP6c+80'
Date 18-Apr

Photo missing

pipe joint records management



day/month	15/4/18	13/4/18	15/4/18	15/4/18				
mark (No)	139	138	137	140 141				
pipe depth	3'	3.25'	3.25'	3'				
offset R/L		23'	23.5'	24'				
joint condition	visual	5	3	4				
visual								
touch		3	4	4				
status before								
condition								
section distance	40'	0'	38'					
notes								

confirmation person signature
Project Manager Site Engineer Site Supervisor

237

235

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints

Joint # 143
Location IP7 +(1)
MV
Date 18-Apr



Joint # 144
Location IP7 +(1)
MV
Date 18-Apr

238

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints

Joint # 136, 137
Location IP6c
CP16
Date 18-Apr




Joint # 138
Location IP6c+40
Date 18-Apr



236

pipe joint records management



day/month	19/4/18	24/4/18	24/4/18	24/4/18	24/4/18	24/4/18	24/4/18	24/4/18
mark (ft)	149	150	151	152	155	157	158	159
pipe depth	3'	3'	3'	2.75'	3'	3.25'	3.25'	3'
offset R/L	9'	9'	9.5'	9'	9'	8.75'	8.5'	9'
joint condition	visual	4	3	4	5	4	5	4
	touch		4	4	4	4	5	3
	status before back filling							
section distance	40'	40'	40'	40'	40'	40'	40'	
notes				Above Sewer pipe				

confirmation person signature	Project Manager	Site Engineer	Site Supervisor
			<i>[Signature]</i>

241

IP7 ~ IP8

pipe joint records management




day/month	24/4/18	24/4/18	24/4/18	26/4/18	26/4/18	26/4/18
mark (ft)	159	160	161	162	163	164
pipe depth	3'	3.25'	2.75'	2.75'	3'	3'
offset R/L	9'	8.5'	9'	9.5'	8.75'	8.75'
joint condition	visual	4	3	4	5	3
	touch		5	4	3	4
	status before back filling					
section distance	40'	40'	40'	40'	9'	
notes				Sewer pipe Leaking		

confirmation person signature	Project Manager	Site Engineer	Site Supervisor
			<i>[Signature]</i>

242

pipe joint records management



day/month	18/4/18	18/4/18	19/4/18	19/4/18	19/4/18	19/4/18	19/4/18
mark (ft)	144	143	146	145	147	148	149
pipe depth	3'	3'	3'	3'	2.75'	3'	3'
offset R/L	9'	8'	8'	8.5'	8.5'	8.75'	9'
joint condition	visual	4	5	4	4	5	3
	touch		3	4	3	4	4
	status before back filling						
section distance	1'	1'	40'	40'	40'	40'	
notes					Sewer pipe		

confirmation person signature	Project Manager	Site Engineer	Site Supervisor
			<i>[Signature]</i>

240

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 148
Location IP7+122'
Straight
Date 19-Apr


Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 140, 141, 142
Location IP7
CP-17
Date 18-Apr



Joint # 149
Location IP7+162'
Straight
Date 19-Apr



Joint # 146
Location IP7+2'
Valve
Date 19-Apr

245

243

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 150
Location IP7+192'
Straight
Date 24-Apr

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 145
Location IP7+42'
Straight
Date 19-Apr



Joint # 151
Location IP7+232'
Straight
Date 24-Apr



Joint # 147
Location IP7+82'
Straight
Date 19-Apr

246

244

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 159
Location IP7+432'
Straight
Date 24-Apr

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 152
Location IP7+272'
Straight
Date 24-Apr



Joint # 160
Location IP7+472'
Straight
Date 24-Apr




Joint # 153
Location IP7+312'
Straight
Date 24-Apr

249

247

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 161
Location IP7+512'
Straight
Date 24-Apr

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 157
Location IP7+352'
Straight
Date 24-Apr



Joint # 162
Location IP7+552'
Straight
Date 26-Apr



Joint # 158
Location IP7+392'
Straight
Date 24-Apr

250

248

pipe joint records management



Day/month	26/4/18	26/4/18	29/4/18		
mark (ft)	164	166	167		
pipe depth	3'	3'	3'		
offset R/L		9'	9.5'		
joint condition	visual	4	3		
	touch	4	3		
	status before back filling				
section distance	11'	40'			
notes					

confirmation person signature

Project Manager	Site Engineer	Site Supervisor
		<i>[Signature]</i>

253

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints




Joint # 163
Location IP7+592'
Straight
Date 26-Apr



Joint # 164, 165
Location IP7+602'
IP8
Date 26-Apr

251

pipe joint records management




Day/month	26/4/18	26/4/18	29/4/18	01/5/18	01/5/18		
mark (ft)	165	166	167	168	169		
pipe depth	3'	3'	3'	3.25'	2.75'		
offset R/L		9'	9'	9.5'	9'		
joint condition	visual	4	3	4	4		
	touch	4	3	3	4		
	status before back filling						
section distance	11'	40'	40'	40'			
notes				knocking with 11" x 12" lagging			

confirmation person signature

Project Manager	Site Engineer	Site Supervisor
		<i>[Signature]</i>


254



IP8 ~ IP10

252

pipe joint records management




day/month	10/05/18	10/5/18	10/5/18	15/9/18	15/9/18
mark (No)	181 CP-19	182 183	186	187	188
pipe depth	2.25'	2.75'	3'	3'	2.5'
offset R/L	10'	9.5'	9.5'	9'	8.75'
joint condition	visual	4	3	4	4
	touch		3	3	5
	status before back filling				4
section distance	37'	40'	40'	9'	
notes	cutting with leakage of sewer		sewer leakage		cutting with leakage

confirmation person signature
Project Manager Site Engineer Site Supervisor
[Signature]

257

pipe joint records management



day/month	11/5/18	11/05/18	11/05/18	11/05/18	11/05/18
mark (No)	171 CP-19	172	173	174	175 CP-19
pipe depth	2.75'	3'	3.25'	3'	3.5'
offset R/L	9'	9.5'	9.5'	9.5'	10'
joint condition	visual	4	4	4	3
	touch		3	4	5
	status before back filling				4
section distance	40'	40'	40'	2'	
notes					As per call out for a corner pipe

confirmation person signature
Project Manager Site Engineer Site Supervisor
[Signature]

255

pipe joint records management




day/month	15/5/18	15/5/18	15/5/18	15/5/18	16/5/18
mark (No)	189 CP-20	190	194	195	196 CP-21
pipe depth	2.5'	3'	3'	3'	2.5'
offset R/L	8.75'	9'	9.5'	9.5'	10'
joint condition	visual	4	3	5	4
	touch		4	4	4
	status before back filling				5
section distance	40'	40'	40'	12'	
notes	A pa branch line				sewer leakage

confirmation person signature
Project Manager Site Engineer Site Supervisor
[Signature]

258

pipe joint records management



day/month	17/5/18	18/05/18	18/05/18	18/05/18	19/05/18
mark (No)	175 CP-19	176	177	179	180 CP-19
pipe depth	2.5'	2.75'	3'	2.75'	3.25'
offset R/L	9'	9.5'	9'	10'	10'
joint condition	visual	4	3	4	4
	touch		5	4	4
	status before back filling				3
section distance	40'	40'	7'	8'	
notes					cutting with leakage & refusal

confirmation person signature
Project Manager Site Engineer Site Supervisor
[Signature]

256

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints




Joint # 164, 165
 Location IP8
 Date 26-Apr



Joint # 166
 Location IP8+11'
 Straight
 Date 26-Apr

261

pipe joint records management



day/month	16/5/18	15/5/18	14/5/18	16/5/18	22/5/18	22/5/18	22/5/18
mark (No)	201	197	198	199	216	217	XI-218
pipe depth	2.5'	3'	3'	3.25'	5'	7'	7'
offset R/L	10'	10'	10'	10'	9.5'	9.5'	9.5'
joint condition							
visual		4	4	5	4	3	3
touch		5	4	3	3	3	3
status before back filling							
section distance		40'	40'	40'	40'	1'	
notes							

confirmation person signature
 Project Manager Site Engineer Site Supervisor

259

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints

Photo missing

Joint # 167
 Location IP8+51'
 Straight
 Date 29-Apr

IP8+51 onwards
 5 No pipe +1'
 Two tees
 Photo missing

Photo missing

Joint # 168
 Location IP8+91
 Straight
 Date 1-May



Photo missing

Joint # 169,170,171
 Location IP8+132
 CP-17
 Tee
 Date 1-May

Photo missing

Joint # 172
 Location IP8+172
 Straight
 Date 1-May

pipe joint records management



day/month	23/5/18	23/5/18	23/5/18	23/5/18	12/5/18	12/5/18	14/5/18	14/5/18
mark (No)	219	220	221	222	226	189	188	314
pipe depth	7'	8'	5.5'	3.5'	3.5'	3.5'	3.5'	8'
offset R/L	9.5'	Boundary	6.5'			2.5'	3.5'	3.5'
joint condition								
visual		4	4	5	4	3	5	4
touch		3	4	4	4	4	4	3
status before back filling								
section distance		40'	3'	30'	40'	40'	35'	3'
notes								


confirmation person signature
 Project Manager Site Engineer Site Supervisor

262

260

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joint # 179
 Location IP8+334'
 Straight
 Date 10-May




Joint # 180
 Location IP8+374'
 Straight
 Date 10-May

265

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joint # 173
 Location IP8+212
 Straight
 Date 1-May



Joint # 174
 Location IP8+252
 Straight
 Date 1-May


263

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joint # 181
 Location IP8+381'
 CP-19
 Tee
 Date 10-May



Joint # 182
 Location IP8+382
 CP-19
 Tee
 Date 10-May


266

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joint # 175, 176, 177
 Location IP8+254
 CP-18
 Tee
 Date 1-May




Joint # 178
 Location IP8+294
 Straight
 Date 10-May

264

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joint # 194
 Location IP8+548'
 Straight
 Date 15-May

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joint # 186
 Location IP8+419'
 Straight
 Date 10-May



Joint # 195
 Location IP8+588'
 Straight
 Date 15-May




Joint # 187
 Location IP8+459'
 Straight
 Date 10-May

269

267

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joint # 196
 Location IP8+628'
 Straight
 Date 15-May

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joint # 188
 Location IP8+499'
 Straight
 Date 15-May



Joint # 200
 Location IP8+640'
 CP-21
 Tee
 Date 16-May



Joint # 189, 190
 Location IP8+508'
 CP-20
 Tee
 Date 15-May

270

268

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joint # 216
 Location IP8+788'
 Straight
 Date 23-May

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints

Photo missing

Joint # 204
 Location IP8+640'
 Straight
 Date 16-May



Joint # 197
 Location IP8+668'
 Straight
 Date 15-May



Joint # 216
 Location IP8+804'
 Stub end
 Valve
 Date 23-May

273

271

Improvement of water supply distribution system in Madina Town pilot area


HDPE Pipe Joints



Joint # 219, 221, 220
 Location IP8+805'
 Stub end
 Tee
 CP-22
 Date 23-May

Improvement of water supply distribution system in Madina Town pilot area


HDPE Pipe Joints



Joint # 198
 Location IP8+708'
 Straight
 Date 16-May



Joint # 222
 Location IP8+845'
 Bore
 V-Bend
 Date 23-May




Joint # 199
 Location IP8+748'
 Straight
 Date 16-May

274

272

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints




Joint # 189
Location IP10+70
Date 12-May

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joint # 223
Location IP8+845'
Bore area
IP-10
V-bend
Date 23-May



Joint # 188
Location IP10+110
Date 12-May



Joint # 224
Location IP8+845'
IP-10
V-Bend
Date 23-May

277

275

Improvement of water supply distribution system in Madina Town pilot area


HDPE Pipe Joints



Joint # 344, 343
Location IP10+145
V-Bend
Date 14-May

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joint # 225
Location IP-10
V-Bend
Date 23-May



Joint # 342
Location IP10+145
V-pipe 3'
V-Bend
Date 14-May




Joint # 226
Location IP10+30
Date 23-May

278

276

pipe joint records management



day/month	6/5/13	6/5/13	6/5/13						
mark (ft)	3.4	3.4	3.4						
pipe depth	3.5'	3.5'							
offset (ft)	2'	2'							
joint condition	visual	4	4						
remarks	touch	4	3						
	status								
	surface								
	lock filling								
section distance	2'	5'							
notes									

confirmation person signature	Project Manager	Site Engineer	Site Supervisor
			<i>[Signature]</i>

281

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joint # 341
 Location IP10+145
 V-Bend
 Date 14-May



Joint # 340
 Location IP10+149
 Stub end
 Valve
 Date 14-May

279

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joints # 321
 Location CP2
 Tee
 Date 6-May


Photo missing

Joints # 322A,
 Location CP2+3
 Stub end
 Date 6-May



Joints # 323, 324
 Location CP2+7
 Stub end
 Enlarger
 Date 6-May

282



280


Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joints # 309
Location CP3
Tee
Date 6-Apr



Joints # 326
Location CP3+3
Straight
Date 8-May



285

283



Joints # 327
Location CP3+8
Straight
Date 8-May



Joints # 328, 329
Location CP3+17'
Reducer
Stub end
Date 8-May

pipe joint records management

mark valve tee pipe connection point
corner pipe 90° 45° 22° reducer

day/month	6/4/18	8/5/18	8/5/18	8/5/18					
mark (No)	309	306	307	308					
pipe depth	3'	2.75'	2.5'	2.5'					
offset R/L	4.5'	4'	4'	4'					
joint condition		4	4	3					
visual									
verysgood		4	3	3					
good									
fair									
poor									
status									
before									
verysbad									
back filling									
section distance	5'-5"	5'	8'						
notes		Existing w/s lockage	Existing w/s lockage	Existing Pipe lockage					

confirmation person signature

Project Manager	Site Engineer	Site Supervisor


286

284

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joints # 1, 2, 3
Location CP4
Tee
Date 14-Mar



Joints # 4, 5
Location CP4
Bend
Date 14-Mar

289

287



Joints # 6, 7
Location CP4
Bend
Date 14-Mar



Joints # 8, 9
Location CP4
Reducer
+ Valve
Date 14-Mar

290

AF3 - 85

pipe joint records management

mark valve tee pipe connection point
corner pipe 90° 45° 22° reducer

day/month	14/3/18	14/3/18	20/5/18	20/05/18	14/3/18	20/5/18	20/5/18	14/3/18
mark (No)	CP4 3	4	205	205	6	7	206	207
pipe depth	2.75	2.75	2.75	2.75	2.75	2.75	2.75	2.75
offset R/L	9.5	9.5	-	-	3'	3'	3'	3'
joint condition	visual	4	4	3	3	4	3	3
verified	touch	5	4	4	5	5	4	5
status before back filling								
section distance		4'	9'	1'	1'	1'	3'	1'
notes								

confirmation person signature

Project Manager	Site Engineer	Site Supervisor


288



293




Joints # 204
Location CP4
Straight
Date 20-May



Joints # 205
Location CP4
Straight
Date 20-May

291



294

CP5



Joints # 206
Location CP4
Straight
Date 20-May




Joints # 207
Location CP4
Straight
Date 20-May





292



297


pipe joint records management



day/month	14 Mar	14 Mar	14 Mar				
mark (top)	 16						
pipe depth	2.25'	2.25'	2.25'	2.25'			
joint	4	3	4	4			
condition	4	3	4	4			
reach							
status							
section							
distance	7'						
notes	Tee Tee Tee Tee				Branch Connection CP-5		

confirmation person signature	Project Manager	Site Engineer	Site Supervisor
			

295



298

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joints # 14, 15, 16
Location CP5
Tee
Date 14-Mar



Joints # 17, 18
Location CP5
Reducer
+ valve
Date 14-Mar

AF3 - 87


296

Improvement of water supply distribution system in Medina Town pilot area

HDPE Pipe Joints



Joint # 174, 175
 Location CP10+17'
 Bend
 Date 3-May



Joint # 176
 Location CP6+20'
 Straight
 Date 3-May

pipe joint records management

date/month	2/1/18	3/5/18	3/5/18	3/5/18	3/5/18	3/5/18
mark (ft)	173	174	176	177	178	179
pipe depth	2.75'	2.75'	2.75'	2.75'	2.75'	2.75'
offset R/L	4'	4'	-	-	3.5'	
joint condition	3	4	5	3	4	
pressure	4	4	4	4	4	
status						
notes						
section distance	13'	4'	3'	2'	5'	
notes						

confirmation person signature
 Project Manager Site Engineer Site Supervisor

Improvement of water supply distribution system in Medina Town pilot area

HDPE Pipe Joints



Joint # 177
 Location CP6+22'
 Straight
 Date 3-May



Joint # 178, 179
 Location CP6+27'
 Bend
 Reducer
 Stub end
 Date 3-May

Improvement of water supply distribution system in Medina Town pilot area

HDPE Pipe Joints



Joint # 63, 64 & 65
 Location IP4+157'
 CP-6
 Tee
 Date 29-Mar




Joint # 173
 Location CP6+13'
 Straight
 Date 3-May

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 68, 69, 70
Location IP4+270'
CP-7
Tee
Date 30-Mar



305

303



Joint # 162
Location CP7+6'
Straight
Date 30-Apr

306

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 163, 164
Location CP7+14'
Reducer
Stub end
Date 30-Apr

306

pipe joint records management

mark valve tee pipe connection point
corner pipe 90° 45° 22° reducer

Rev/ month	5/2/19	20/4/18	30/4/18						
mark (ft)	CP7 72	163	164						
pipe depth		2.5	2.5						
offset ft		0	5'						
joint condition	visual	4	4						
	touch	3	4						
status									
reason									
checked									
section distance		6'	6'						
notes									

confirmation person signature

Project Manager	Site Engineer	Site Supervisor
		<i>[Signature]</i>


304

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joint # 74, 75, 76
 Location IP4+357'
 CP-8
 Tee
 Date 30-Mar



309

307

Improvement of water supply distribution system in Madina Town pilot area


HDPE Pipe Joints



Joint # 166, 167
 Location CP8+14'
 Reducer
 Stub end
 Date 30-Apr

310

pipe joint records management



day/month	2x/2/15	2x/4/16	2x/4/16						
mark (ft)	75 4E	165	167						
pipe depth		3							
offset R/L		45	45						
joint condition	visual	4	4						
condition	issues								
	status	3	4						
	status								
	status								
section		6'	7'						
date/time									
notes									

confirmation person signature

Project Manager	Site Engineer	Site Supervisor
		<i>[Signature]</i>

308

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints




Joint # 80, 81, 82,
83
Location IP4+487
Straight
Tee
CP-9
Date 1-Apr



Joint # 168
Location CP9+8'
Straight
Date 3-May

313



311

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joint # 169, 170
Location CP9+21'
Reducer
Stub end
Date 3-May

314

pipe joint records management

mark valve corner pipe tee pipe 90° 45° 22° connection point reducer

day/month	4/4/10	3/5/10	3/5/08						
mark (ft)	82	168	169	170					
pipe depth		2.75'	2.75'						
offset		5'	5'						
joint condition	visual	3	4						
method	touch	3	3						
	static								
	dynamic								
	back filling								
section distance	3'	13'							
notes									

confirmation person signature


Project Manager	Site Engineer	Site Supervisor
		<i>M. H. H.</i>

312

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 87, 88, 89
Location IP4+605'
Tee
CP-10
Date 1-Apr
2-Apr



317

315




Joint # 171
Location CP10+5'
Straight
Date 3-May

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 172, 173
Location CP10+13'
Reducer
Stub end
Date 3-May



day/month	3/4/18	3/5/18	3/5/18						
mark (top)									
pipe depth		3'	3'						
offset H/L		6'	6'						
joint condition	visual	4	3						
reducer	touch								
	1	4	4						
	2								
	3								
section distance	2-4'	5'	3'						
notes									

confirmation person signature

Project Manager	Site Engineer	Site Supervisor

318


316

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints



Joint # 266, 267, 268
 Location CP-11
 Tee
 Stub end
 Valve
 Date 12-Jun



321

319

Improvement of water supply distribution system in Madina Town pilot area

HDPE Pipe Joints





Joint # 274
 Location CP-11+5
 Straight
 Date 12-Jun



Joint # 275, 276
 Location CP-11+8
 Bend
 Reducer
 Stub end
 Date 12-Jun

322

pipe joint records management




day/month	12/16/18	12/6/18	12/11/18	12/6/18	12/6/18
mark (No)	266 267 268	269 270 271	272 273	274	275 276
pipe depth	6'	6'	3.5'	3'	3.5'
offset R/L	-	-	-	-	-
joint condition	visual	4	3	4	3
verified	touch	3	3	5	4
status	before				
verified	back filling				
section distance	Extending with 2'	2'	2'	3'	
notes					

confirmation person signature

Project Manager	Site Engineer	Site Supervisor
		<i>[Signature]</i>

320

pipe joint records management



day/month	6/4/18	27/5/18	2/6/18	2/6/18	2/6/18	2/6/18	2/6/18	2/6/18
mark (No)	98	99	230	245	246	247	249	250
pipe depth	3.25'	3'	3'	3'	3'	3'	3'	3'
offset R/L	4.5'	5'	5'	5'	5'	3'		
joint condition	visual	4	4	5	4	3		
	touch	3	4	4	3	4		
status	before							
	back filling							
section distance	4'	1'	40'	40'	2'			
notes								

confirmation person signature

Project Manager	Site Engineer	Site Supervisor
		<i>[Signature]</i>

329

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



327

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints




Joint # 98, 99, 100
Location CP12+127'
CP13
Tee
Date 6-Apr
IP5+223'



Joint # 230
Location CP13+4'
Stub end
Valve
Date 27-May

330




328

Improvement of water supply distribution system in Medina Town pilot area
HDPE Pipe Joints



Joint # 249
Location CP13+86'
Bend
Date 2-Jun

Improvement of water supply distribution system in Medina Town pilot area
HDPE Pipe Joints



Joint # 245
Location CP13+4'
Valve
Stub end
Date 2-Jun



Joint # 250, 251
Location CP13+88'
Bend
Reducer
Stub end
Date 2-Jun



Joint # 246
Location CP13+44'
Straight
Date 2-Jun

333

331

Improvement of water supply distribution system in Medina Town pilot area
HDPE Pipe Joints



Improvement of water supply distribution system in Medina Town pilot area
HDPE Pipe Joints



Joint # 247
Location CP13+84'
Bend
Date 2-Jun



Joint # 248
Location CP13+85'
Bend
Date 2-Jun

334

332

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints




Joint # 117
Location CP-14
Tee
Date 11-Apr



Joint # 229
Location CP14+4'
Straight
Date 24-May

337



CP14

335

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints




Joint # 227, 228
Location CP-14+9'
Reducer
Stub end
Date 24-May



338

pipe joint records management



day/month	11/4/18	24/5/18	24/5/18						
mark (No)	116 	229 	228 						
pipe depth	2'	2.5'	2.5'						
offset R/L	4'	6'	6'						
joint condition	visual	4	4						
verified	touch								
3		3	5						
2									
1									
verified	before								
back filling									
section distance		3'	5'						
notes	Above Sewer pipe								

confirmation person signature	Project Manager	Site Engineer	Site Supervisor

336

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints




Joint # 136, 137
Location IP6b+104'
IP6c
CP15
Date 18-Apr



Joint #
Location
Date 31-May

341



339

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints





Joint #
Location
Date 6-Jun

Joint details missing

342

pipe joint records management



day/month	18/4/18	3/6/18	3/6/18	3/6/18				
mark (No)	CP-15 136 137	137	137	V-Box 25V V-Box 25V				
pipe depth	3'	3'	3'	3'	1'			
offset R/L	6.5'	-	-	-	-			
joint condition	visual	4	5	3	4			
very good	touch	4	4	4	3			
4								
3								
2								
1								
very bad								
status before back filling								
section distance	1'	2'	11'	1'				
notes								

confirmation person signature

Project Manager	Site Engineer	Site Supervisor
		<i>[Signature]</i>

340

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints




Location IP6c+118'
IP7
CP16
Date 18-Apr



Joints # 261, 262
Location CP16
Bend
Date 6-Jun

345



CP16

343



Joints # 265
Location CP16+2
Stub end
Valve
Date 6-Jun




Joints # 264, 263
Location CP16+19'
Bend
Date 6-Jun

346

pipe joint records management

mark valve tee pipe connection point
corner pipe 90° 45° 22°




day/month	18/4/18	6/6/18	6/6/18	6/6/18	6/6/18				
mark (No)	CP16 F1 142 140	263 261	X1 265	263 264	264 262				
pipe depth	3'	3'	3'	3'	2'				
offset R/L	-	-	-	7'	7'				
joint condition	visual	4	3	5	4				
verypoint	touch	4	4	4	3				
status									
before									
verypad	back filling								
section distance		1'	1'	17'	14'				
notes		Scaven with Leakage			Scaven with Leakage				

confirmation person signature

Project Manager	Site Engineer	Site Supervisor

344

pipe joint records management



day/month	01/05/18	20/05/18																		
mark (No)	CP17																			
pipe depth	2.75	2.5'																		
offset R/L	9'																			
joint	visual																			
condition		4																		
status	touch																			
status before		4																		
status after																				
location																				
notes	existing pipe angle in adjacent																			

confirmation person	Project Manager	Site Engineer	Site Supervisor
signature			

349



Joints # 266, 267
 Location CP16+33'
 Bend
 Reducer
 Date 6-Jun



347

Improvement of water supply distribution system in Madina Town pilot area


HDPE Pipe Joints

Joint # 169,170,171

Location IP8+132
 CP-17
 Tee

Date 1-May

Photo missing



Joint # 208, 209

Location CP18+4'
 Reducer
 Stub end

Date 20-May

350

348

pipe joint records management




day/month	10/5/18	10/5/18							
mark (No)	181 CP-19	182							
pipe depth	2.25'	2.25'							
offset R/L	10'	-							
joint condition	visual	4							
vertical	touch	3							
status	before								
checked	back filling								
section distance	5'								
notes	Location 1/2 today								

confirmation person signature	Project Manager	Site Engineer	Site Supervisor

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints




Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 183
Location IP8+382'
Tee
CP-19
Date 10-May



Joint # 184, 185
Location CP19+5'
Reducer
Stub end
Date 10-May



Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints




Joint # 193
Location IP8+508'
Tee
CP-20
Date 15-May




Joint # 191, 192
Location CP20+4'
Reducer
Stub end
Date 15-May

361



CP20

359



CP21

362

pipe joint records management




day/month	15/5/18	15/5/18							
mark (No)	189 CP-20 190 191 192	193							
pipe depth	2.5	2.5							
offset R/L	8.75	-							
joint condition	visual	4							
verified	5								
	4	5							
	3								
	2								
	1								
verified	status before back filling								
section distance	4'								
notes									

confirmation person signature

Project Manager	Site Engineer	Site Supervisor
		<i>[Signature]</i>


360



CP22

365

pipe joint records management




day/month	16/5/18	16/5/18							
mark (No)	CP22, 200 224, 221	202, 203 222, 223							
pipe depth	2.5	2.5							
offset R/L	10'	-							
joint condition	visual	4							
vergoed	touch	4							
	status before								
vergoed	back filling								
section distance	4'								
notes									

confirmation person signature	Project Manager	Site Engineer	Site Supervisor
			<i>[Signature]</i>

363

pipe joint records management



day/month	20/5/18	29/5/18	29/5/18	29/5/18	29/5/18	29/5/18	29/5/18
mark (No)	CP22, 219 221, 220	220	221	226	227 222, 233	234	
pipe depth	7'	7'	6'	5'	4'	3'	3'
offset R/L	9.5'	-	-	-	-	-	-
joint condition	visual	3	4	4	3	4	
vergoed	touch	3	5	4	4	3	
	status before						
vergoed	back filling						
section distance		3'	2'	2'	6"		
notes							


confirmation person signature	Project Manager	Site Engineer	Site Supervisor
			<i>[Signature]</i>

366

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 201
Location IP8+742
Tee
CP-21
Date 16-May



Joint # 202, 203
Location CP21+4'
Reducer
Stub end
Date 16-May

364

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 232
Location CP22+3'
Bend
Date 29-May



Joint # 233
Location CP22+10'
Bend
Date 29-May

369


Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 219, 221, 220
Location IP8+805'
Stub end
Tee
CP-22
Date 23-May

Photo missing

Joint # 230
Location CP22
Valve
Stub end
Date 29-May



Joint # 231
Location CP22+3'
Bend
Date 29-May

367

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 234
Location CP22+10'
Bend
Date 29-May

370

Improvement of water supply distribution system in Madina Town pilot area
HDPE Pipe Joints



Joint # 236
Location CP22+7'
Straight
Date 29-May



Joint # 237
Location CP22+11'
Bend
Date 29-May


368

AF3.8 Madina Town OHR Log Book

وقت	زونل میٹر	ٹینک		پانی کی سطح (ft)	بجلی	پمپ				پانی پاس	ٹنکی (ft)	دستخط:		تبصرہ
		بھر رہا ہے	پانی کی سطح (ft)			1	2	3	4			پانی کی فراہمی	دوسرے علاقے	
06:00 Morning		Yes/No		Yes/No	Yes/No					Yes/No				
07:00		Yes/No		Yes/No	Yes/No					Yes/No				
08:00		Yes/No		Yes/No	Yes/No					Yes/No				
09:00		Yes/No		Yes/No	Yes/No					Yes/No				
10:00		Yes/No		Yes/No	Yes/No					Yes/No				
11:00		Yes/No		Yes/No	Yes/No					Yes/No				
12:00		Yes/No		Yes/No	Yes/No					Yes/No				
01:00 Afternoon		Yes/No		Yes/No	Yes/No					Yes/No				
02:00		Yes/No		Yes/No	Yes/No					Yes/No				
03:00		Yes/No		Yes/No	Yes/No					Yes/No				
04:00		Yes/No		Yes/No	Yes/No					Yes/No				
05:00		Yes/No		Yes/No	Yes/No					Yes/No				
06:00		Yes/No		Yes/No	Yes/No					Yes/No				
07:00		Yes/No		Yes/No	Yes/No					Yes/No				
08:00		Yes/No		Yes/No	Yes/No					Yes/No				
09:00		Yes/No		Yes/No	Yes/No					Yes/No				
10:00		Yes/No		Yes/No	Yes/No					Yes/No				
11:00		Yes/No		Yes/No	Yes/No					Yes/No				
00:00 Midnight		Yes/No		Yes/No	Yes/No					Yes/No				
01:00		Yes/No		Yes/No	Yes/No					Yes/No				
02:00		Yes/No		Yes/No	Yes/No					Yes/No				
03:00		Yes/No		Yes/No	Yes/No					Yes/No				
04:00		Yes/No		Yes/No	Yes/No					Yes/No				
05:00		Yes/No		Yes/No	Yes/No					Yes/No				

Comments:

AF3.9 Hydraulic Analysis Result in Sitara Sapna Pilot Area



Network Table – Nodes at 12:00 Hrs

Node ID	Elevation ft	Base Demand CFS	Demand CFS	Pressure psi
Junc J1	573.9	0.0052	0.01	22.86
Junc J2	574.14	0.0124	0.02	22.72
Junc J3	574.83	0.0069	0.01	22.39
Junc J4	574.2	0.0028	0.00	22.65
Junc J5	574.47	0.0045	0.01	22.40
Junc J6	575	0.0045	0.01	22.16
Junc J7	575.1	0.0017	0.00	22.04
Junc J8	575	0.0043	0.01	22.07
Junc J9	575.7	0.0086	0.02	21.73
Junc J10	575.7	0.0086	0.02	21.53
Junc J11	575.1	0.0043	0.01	21.98
Junc J12	574	0.0047	0.01	22.36
Junc J13	574.2	0.0029	0.01	22.41
Junc J14	574.2	0.0029	0.01	22.39
Junc J15	574.5	0.006	0.01	22.26
Junc J16	574.55	0.003	0.01	22.02
Junc J17	574.5	0.0086	0.02	22.20
Junc J18	574.42	0.0064	0.01	22.23
Junc J19	575.78	0.006	0.01	21.63
Junc J20	574.5	0.0039	0.01	22.30
Junc J21	574.2	0.0064	0.01	22.38
Junc J22	574	0.0047	0.01	22.40
Junc J23	574	0.0123	0.02	22.27
Junc J24	574.14	0.0021	0.00	22.48
Junc J25	575.78	0.0069	0.01	21.79
Junc J26	575.78	0.0064	0.01	21.81
Junc J27	575	0.0043	0.01	22.18
Junc J28	574	0.0052	0.01	22.64
Junc J29	574	0.003	0.01	22.68
Junc J30	574.8	0.0086	0.02	22.16
Junc J31	574.42	0.0073	0.01	22.40
Junc J32	574.47	0.0073	0.01	22.39
Junc J33	574.11	0.006	0.01	22.58
Junc J34	574	0.0043	0.01	22.67
Junc J35	574.75	0.0021	0.00	22.35
Junc J36	576	0.0026	0.00	19.18
Junc J37	576.8	0.0043	0.01	18.73
Junc J38	575.9	.0043	0.01	19.22
Junc J39	576.1	0.0021	0.00	19.05
Junc J40	575	0.006	0.01	21.66

Node ID	Elevation ft	Base Demand CFS	Demand CFS	Pressure psi
Junc J41	575.1	0.0052	0.01	21.53
Junc J42	575.15	0.0052	0.01	21.42
Junc J43	575.14	0.009	0.02	21.42
Junc J44	575.3	0.009	0.02	21.29
Junc J45	575.4	0.0056	0.01	21.22
Junc J46	575.4	0.0052	0.01	21.21
Junc J47	575.4	0.0034	0.01	21.21
Junc J48	575.6	0.0053	0.01	21.12
Junc J49	575.12	0.0073	0.01	21.37
Junc J50	575.4	0.0039	0.01	21.22
Junc J51	575.8	0.0041	0.01	21.02
Junc J52	575.5	0.0047	0.01	21.16
Junc J53	575.78	0.003	0.01	21.04
Junc J54	575.7	0.003	0.01	21.08
Junc J55	576.2	0.0061	0.01	18.91
Junc J56	576.8	0.0073	0.01	18.64
Junc J57	576.25	0.008	0.01	18.89
Junc J58	576.2	0.0052	0.01	18.99
Junc J59	577	0.0052	0.01	18.60
Junc J60	577	0.0043	0.01	18.59
Junc J61	575.5	0.0012	0.00	21.15
Junc J62	575.85	0.0015	0.00	20.99
Junc J63	575.1	0.0012	0.00	21.53
Junc J64	575.8	0.0015	0.00	21.03
Junc J66	573	0	0.00	23.65
Junc J65	571	0	0.00	24.52
Junc J67	572	0	0.00	24.08
Resvr R1	571	#N/A	-0.58	0.00

Network Table – Links at 12:00 Hrs

Link ID	Length ft	Diameter in	Roughness	Flow CFS
Pipe P1	145.83	10	120	0.57
Pipe P2	139.11	10	120	0.53
Pipe P3	256.84	6	120	0.23
Pipe P4	35.84	6	120	0.20
Pipe P5	231.23	6	120	0.17
Pipe P6	113.55	6	120	0.10
Pipe P7	480.84	4	120	0.07
Pipe P8	630.24	3	120	-0.03
Pipe P9	835.37	3	120	0.09
Pipe P10	334.56	3	120	0.03
Pipe P11	176.51	3	120	-0.01
Pipe P12	96.35	3	120	0.05
Pipe P13	813.78	3	120	0.02
Pipe P14	72.96	8	120	0.29
Pipe P15	689.75	3	120	0.01
Pipe P16	15.11	3	120	0.03
Pipe P17	302.46	8	120	0.27
Pipe P18	540.48	3	120	0.00
Pipe P19	334.73	3	120	0.02
Pipe P21	771.72	3	120	0.03
Pipe P22	993.98	3	120	0.02
Pipe P23	221.81	3	120	-0.04
Pipe P24	33.91	3	120	-0.04
Pipe P25	403.59	3	120	0.00
Pipe P26	437.53	3	120	0.04
Pipe P27	433.86	3	120	-0.03
Pipe P28	195.41	3	120	0.01
Pipe P29	197.52	3	120	0.01
Pipe P30	437.78	3	120	0.00
Pipe P31	639.82	3	120	0.02
Pipe P32	433.26	3	120	-0.02
Pipe P33	429.12	4	120	-0.05
Pipe P34	189.42	3	120	-0.03
Pipe P35	198.76	4	120	-0.06
Pipe P36	157.47	6	120	-0.11
Pipe P37	293.44	4	120	0.05
Pipe P38	194.97	8	120	0.26
Pipe P39	198.49	8	120	0.25
Pipe P40	212.19	8	120	0.23
Pipe P41	208.47	8	120	0.19

Link ID	Length ft	Diameter in	Roughness	Flow CFS
Pipe P42	200.08	8	120	0.17
Pipe P43	251.71	3	120	-0.03
Pipe P44	500.79	3	120	0.02
Pipe P45	537.72	3	120	0.00
Pipe P46	208.20	3	120	-0.01
Pipe P47	198.84	3	120	-0.02
Pipe P48	194.42	3	120	-0.02
Pipe P49	537.14	3	120	0.01
Pipe P50	539.15	3	120	0.01
Pipe P51	740.56	3	120	0.04
Pipe P52	240.61	3	120	-0.05
Pipe P53	143.66	4	120	0.08
Pipe P54	216.54	4	120	0.07
Pipe P55	699.05	4	120	0.01
Pipe P56	257.78	4	120	0.05
Pipe P57	236.35	4	120	0.04
Pipe P58	278.61	4	120	0.02
Pipe P59	210.34	4	120	0.01
Pipe P60	244.08	4	120	0.00
Pipe P61	235.70	4	120	0.00
Pipe P62	209.70	3	120	0.01
Pipe P63	236.35	4	120	0.05
Pipe P64	240.11	4	120	0.04
Pipe P65	273.93	4	120	0.02
Pipe P67	687.92	3	120	0.00
Pipe P68	222.80	3	120	0.01
Pipe P69	240.43	3	120	0.00
Pipe P70	220.17	3	120	-0.01
Pipe P71	253.82	3	120	0.06
Pipe P72	269.90	3	120	0.00
Pipe P73	265.45	3	120	0.00
Pipe P74	420.55	3	120	0.02
Pipe P75	156.98	3	120	0.01
Pipe P76	58.59	3	120	0.03
Pipe P77	563.57	3	120	0.02
Pipe P78	235.36	3	120	0.00
Pipe P79	513.75	3	120	0.02
Pipe P80	421.45	3	120	0.01
Pipe P81	33.87	3	120	0.07
Pipe P82	177.46	3	120	0.00
Pipe P83	99.13	3	120	0.00

Link ID	Length ft	Diameter in	Roughness	Flow CFS
Pipe P84	158.02	3	120	0.00
Pipe P85	62.05	3	120	0.00
Pipe P86	1597.44	10	120	0.58
Pipe P20	7399.46	60	140	0.58
Pipe P66	4125.51	40	140	0.58
Pump PU1	#N/A	#N/A	#N/A	0.58

Network Table – Links at 12:00 Hrs

Link ID	Velocity fps
Pipe P1	1.04
Pipe P2	0.97
Pipe P3	1.16
Pipe P4	1.04
Pipe P5	0.86
Pipe P6	0.50
Pipe P7	0.86
Pipe P8	0.55
Pipe P9	1.76
Pipe P10	0.56
Pipe P11	0.15
Pipe P12	0.96
Pipe P13	0.34
Pipe P14	0.83
Pipe P15	0.27
Pipe P16	0.53
Pipe P17	0.78
Pipe P18	0.08
Pipe P19	0.31
Pipe P21	0.54
Pipe P22	0.32
Pipe P23	0.74
Pipe P24	0.78
Pipe P25	0.05
Pipe P26	0.72
Pipe P27	0.60
Pipe P28	0.13
Pipe P29	0.24
Pipe P30	0.02
Pipe P31	0.44
Pipe P32	0.33
Pipe P33	0.59
Pipe P34	0.58
Pipe P35	0.64
Pipe P36	0.58
Pipe P37	0.56
Pipe P38	0.75
Pipe P39	0.71
Pipe P40	0.67
Pipe P41	0.55

Link ID	Velocity fps
Pipe P42	0.48
Pipe P43	0.57
Pipe P44	0.31
Pipe P45	0.00
Pipe P46	0.26
Pipe P47	0.38
Pipe P48	0.46
Pipe P49	0.14
Pipe P50	0.14
Pipe P51	0.71
Pipe P52	1.11
Pipe P53	0.91
Pipe P54	0.78
Pipe P55	0.07
Pipe P56	0.57
Pipe P57	0.42
Pipe P58	0.21
Pipe P59	0.07
Pipe P60	0.05
Pipe P61	0.00
Pipe P62	0.24
Pipe P63	0.60
Pipe P64	0.43
Pipe P65	0.24
Pipe P67	0.05
Pipe P68	0.20
Pipe P69	0.00
Pipe P70	0.18
Pipe P71	1.22
Pipe P72	0.08
Pipe P73	0.09
Pipe P74	0.41
Pipe P75	0.26
Pipe P76	0.54
Pipe P77	0.36
Pipe P78	0.07
Pipe P79	0.34
Pipe P80	0.15
Pipe P81	1.41
Pipe P82	0.04
Pipe P83	0.04

Link ID	Velocity fps
Pipe P84	0.05
Pipe P85	0.05
Pipe P86	1.06
Pipe P20	0.03
Pipe P66	0.07
Pump PU1	0.00

AF4.1 Water Supply Faisalabad Regulations

EXTRA ORDINARY ISSUE

REGISTERED No. L-7532



The Punjab Gazette

PUBLISHED BY AUTHORITY

LAHORE THURSDAY OCTOBER 29, 2015

WATER AND SANITATION AGENCY (FDA) FAISALABAD

No. 551 /MD/WASA/2015

Dated 28 / 10 / 2015

NOTIFICATION

WATER SUPPLY FAISALABAD REGULATIONS – 2015

In exercise of the powers conferred under Section 44 of the Punjab Development of Cities Act, 1976, the Governing Body of Faisalabad Development Authority, Faisalabad in its 91st meeting held on 21/05/2015 is pleased to frame the regulations namely Faisalabad Development Authority (Water and Sanitation Agency) Faisalabad – Water Supply Faisalabad Regulations, 2015.

WATER SUPPLY FAISALABAD REGULATIONS – 2015

**PART – I
DEFINITIONS**

- 1. Short Title-**
These regulations shall be called the Faisalabad Development Authority (Water and Sanitation Agency) Water Supply Faisalabad Regulations – 2015.
- 2. Commencement –**
These Regulations shall come into force in Faisalabad at once.

Price Rs.10.00 Per Page

(2239)

3. **Definition** – In these regulations, unless there is anything contrary to the subject or context.

“**Agency**” means the Water and Sanitation Agency established under Punjab Development of Cities Act 1976.

“**Aquifer**” means a layer of water bearing rock or strata located underground that conveys water in sufficient quantity to pumping wells or natural springs.

“**Consumer**” means (1) any person, occupier, institution, organization or concern who in agreement with the Agency is entitled to use the facilities of the water supply as per terms of the agreement, and (2) any end user who receives water supply or sanitation services from the Agency.

“**Occupier**” means (a) a person in occupation or control of premises; and (b) in relation to premises where different parts of the premises are occupied by different persons, the respective persons in occupation or control of each part of the premises;

“**Engineer**” means an Engineer; employee of the Water and Sanitation Agency of the Faisalabad Development Authority for the purpose of enforcement of these regulations and shall include any officer or official deputed by the Engineer to act for him.

“**Ground Water**” means water located beneath the earth surface in soil pores / spaces and in fractures of rock formations or ecological formations.

“**Contractor**” means any person who for the time being is authorized by the Agency to carry out any work of water supply under these regulations.

“**Meter**” means any appliance, equipment or device used for the purpose of measuring the quantity of water supplied;.

“**Person**” means any person or body of persons whether corporate or incorporate.

“**Regulations**” means the Faisalabad Development Authority (Water and Sanitation Agency) Water Supply Regulations-2015.

“**Service Pipe or service water pipe**” means the pipe from the Agency’s distribution main / distribution network to inside the consumer’s property or any pipe for supplying water from the public mains to any premises which is subject to water pressure from the mains or would be so subject but for the closure of some taps or valves.

“**Water**”, means drinkable water supplied by Water and Sanitation Agency;

“**Water fittings**” includes pipes (other than the public mains), specials, taps, cocks, valves, ferrules, meters, sub-meters, cisterns, baths, water closets, hot water apparatus, soil pans and other similar apparatus or appliance used in connection with the supply and use of water;

“**Water Main**” means a water pipe or conduit carrying water for public use which is owned and operated by the Agency.

“**Water Quality**” means quality of water whereof is appropriate as per WHO Guidelines for the purpose it is supplied or used.

“**Water Service**” means the pipe and fittings used in connection with the supply of water from the Agency’s mains to any premises.

“**Water supply distribution area**” means (a) an area within which WASA is responsible to distribute and supply of water; and (b) in case of public private partnership project area, WASA is only responsible for bulk supply of water and distribution / maintenance will lie with private partner as per contract.

“Water supply services” means the abstraction and chlorination of ground water or treatment of surface water, the distribution and supply of drinkable or treated water to consumers, and includes the operation and maintenance of the water supply system;

“Water supply system” means the whole system incorporating transmission mains, collector mains, distribution mains, pipes, chambers, treatment plants, pumping stations, tube wells, service or balancing reservoirs or any combination thereof and all other structures, installations, buildings, equipment and appurtenances used and the lands where the same are located for the storage, abstraction, collection, conveyance, treatment, distribution and supply of water;

“Well” means a well sunk / drilled / bored for the search or abstraction of water by a person or persons for carrying out scientific investigations, exploration, development or management work for the survey and assessment of water resources or for providing water, and includes open well, dug well, bore well, dug-cum-bore well, tube well and collector well.

“Work of Water Supply” means the construction, alteration, extension, disconnection, removal, maintenance, repair, renewal or cleaning of any pipe or fitting of any water service communicating or intended to communicate directly or indirectly with any water main of the Agency.

PART – II APPLICATION AND GENERAL PROVISIONS

4. Existing Water Services –

Any water connection with or through the water main transferred to the Agency under the Act and lawfully existing on the date on which these regulations come into force shall be deemed to have been made under these regulations subject to the provisions herein contained.

5. Application for Installation –

- (a) No person shall carry out any water supply installation work or make, cause or permit any private connection pipe to connect directly or indirectly to any new or existing building or in any other premises and connect the same with the Agency’s main without first obtaining permission from the Agency.
- (b) Application for a new connection shall be submitted on the prescribed form along with copy of CNIC and evidence of Ownership. The application form can be obtained from any office of the Water and Sanitation Agency on payment of the appropriate fee.
- (c) A new water connection shall be allowed only on the request of or with the approval of the owner of the property.
- (d) If ownership lies with any Trust, the connection shall be made only with the permission of the Trust provided that a tenant or such other person occupying the premises or a part of the premises not owned by them may apply for a domestic supply of water with the approval of the owner but such connection will always be sanctioned in name of the owner. Upon transfer of legal ownership of the property, the responsibility lies with the new owner to intimate WASA in order to change the name of the consumer.
- (e) Water connection shall not be sanctioned if ownership of property is disputed.

6. False or Incorrect Description in the Application

In case the entries made in the application or documents attached with it are found false or incorrect at a later stage, WASA has the right to disconnect the water connection without any notice and confiscate the security amount deposited by the consumer. If there are any further dues payable by the consumer, he will have to clear the same in any case. The facility of water supply shall be resumed only after submission of correct information / description of particulars in accordance with these regulations.

7. Deposit of Plans –

The consumer when required shall deposit with the application request two copies of as-built plans and sections clearly and indelibly drawn on a durable material (to a scale of not less than one inch to eight feet which shall be clearly marked on each drawing) which shall show thereon every floor of the building in connection with which such water supply installation is to be used. The position, form, level and arrangements of several parts of such buildings shall be shown including proposed size and measurements of the pipe lines to be laid, stop valves, cisterns, sink taps, hot water boilers and all other fittings to which a supply of water line is to begin or from which a supply is to be taken.

8. Connection Requirement –

- a) All new connections shall be sanctioned as metered.
- b) The connection may not be given unless following conditions are fulfilled:
 - (i) Adequate drainage facilities are provided to the satisfaction of the Engineer.
 - (ii) A written consent of the owner giving his Computerized National Identity Card (CNIC) issued by the Government of Pakistan are accompanied by the application for water connection has been produced.
 - (iii) A deposit sufficient to cover the following items has been made by the applicant or owner as specified by the Agency.
 - (a) Connection fee;
 - (c) Cost of fixing meter and main stop valve;
 - (d) Security deposit;
 - (e) Regularization Fee (in case of illegal connection)
 - (f) Any other charges as per tariff
 - (iv) The deposit as per clause (iii) shall be in accordance with the scale which may from time to time be fixed by the Agency.
 - (v) For new water connection, construction of ground water tank is mandatory. For houses up to 5 Marlas steel, fiber glass or plastic tanks can be kept on surface. Water connection from the Agency's water main will be made directly with this tank. Water from the tank may be pumped to roof tank. Previously sanctioned connection should have this arrangement by the end of year 2016.

9. Inspection of Premises –

Presentation of the new connection application shall be deemed to authorize the Engineer to enter the premises after reasonable notice and to examine and test the applicant's pipes and fittings with which the connection is to be made and the drains, water closets, receptacles and latrines into which water received is to be discharged and also for reading meters, inspecting and testing any apparatus belonging to the Agency on the consumer's premises when water connection is provided.

10. Approval of Application –

The Engineer shall within ten days of the deposit of the application and such plans and sections as may be required, inform in writing the applicant as to whether the application, plans and sections are approved or not.

11. Alteration to Application –

The Engineer may direct an applicant to make alterations or improvements which appear to be necessary or desirable and the applicant shall comply and resubmit the plans and sections accordingly.

12. Service Connection –

(a) In case the aforesaid application is accepted by the Engineer, he shall thereupon cause the system of water pipes in the applicant's premises to be connected with the Agency water main by its own staff/contractor by a connecting pipe and appropriate water fittings of approved material extended from such water main to the terminal point of the applicant's water piping system which may be outside or inside the applicant's premises and therefore levy charges in accordance with the prescribed rate.

(b) No connection shall be made to the public mains until the estimated cost of making the connection has been deposited with the Agency and all the internal water fittings requisite for the supply of water have been erected and completed in accordance with any requirement.

13. Water Use for Other than Agreed Purpose –

The consumer is obliged to use water only for the purpose for which the connection was originally obtained as per agreement. For any other purpose the consumer shall have to seek written permission of the Engineer.

14. Permission of Water Use outside the Sanctioned property –

The consumer shall not permit the use of water by a neighbor or any person for outside the property with the water connection sanctioned. In case of violation of this rule, the consumer shall be responsible to pay all the costs of illegal use of water. It may also result in disconnection of the water supply to the consumer.

15. Separate Connection –

In the event of a consumer requiring a separate water connection for separate house or portion of the same property, the Engineer may permit a supply of water through common feeding pipes subject to the condition that:-

- (i) The service shall be maintained to the requirement of these regulations; and
- (ii) The owner shall not object to the tapping of the ferrule for giving connection to the applicant, provided that the number and particulars of the services do not exceed following unless otherwise approved by the Engineer:

Sr. No.	No. of houses, shop, flats, etc.	Ferrule size (inches)	HDPE pipe size (mm)	
			From main to meter	Within the curtilage of the property
1	1	1/4	25	1/2
2	2	1/4	32	3/4
3	03-05	1/4	50	1 1/4
4	06-10	3/4	60	1 1/2
5	11	1	75	1 1/2

16. Main Stop Valve Required –

A main stop valve preferably lockable magnetic stop valve is required on service water pipe before entering the premises of the consumer position to the convenience and satisfaction of the Engineer so that any disconnection may, if required, be arranged easily without disturbing the supply to the other consumers.

17. Average consumption in case of damaged/no meter**A) Domestic Water Service:**

If the meter is damaged or does not exist, the consumer shall be charged on the average consumption over one year or as detailed below whichever is higher:

Property Area	Average Monthly Consumption
Upto 2.5 Marlas	2500 gallons
Above 2.5 to 3.5 Marlas	3500 gallons
Above 3.5 to 5 Marlas	5000 gallons
Above 5 to 10 Marlas	10000 gallons
Above 10 to 20 Marlas	20000 gallons
Above 20 to 40 Marlas	40000 gallons
Above 40 Marlas	50000 gallons

B) Non Domestic Water Service:

- (a) A request for the grant of a water service for non-domestic purposes shall be made in the same manner as for a domestic service.
- (b) A non –domestic water service shall include a service for:
- (i) Any trade, manufacture, or business
 - (ii) Construction and building purposes

No connection shall be sanctioned for the following:

- (i) Watering or bathing of animals
- (ii) Washing vehicles when such vehicles kept for sale or hire.
- (iii) Swimming pools or for any environmental and mechanical purposes
- (iv) Gardens or for the purposes of irrigation;
- (v) Washing roads and paths.
- (vi) Public stand post

Keeping the meter in proper condition shall be the responsibility of the consumer. In case of any repair / replacement needed, the cost shall be borne by the consumer.

In case a meter is damaged, the consumer shall be charged on the average consumption over one year.

18. Auxiliary Temporary Water Services –

The Engineer may arrange a temporary or auxiliary water service in such a manner as he deems fit for any person or for any occasion and period in accordance with these regulations and charge the same at the prescribed rates or such other manner as may be approved by the Agency.

19. Adherence to Regulations –

The consumer shall obey and carry out, as the case may be, each and all provisions of these regulations, directions or order lawfully issued there under by the Agency.

20. Payment of Bills

Bills shall be regularly delivered to all consumers by the Agency. If due to any reason, the consumer does not receive a bill, he shall have either to personally get the bill from the Agency or use WASA official website and make payment within the stipulated period. Non receipt of a bill shall not be considered an excuse for nonpayment. If a tenant or any other resident does not pay dues of the Agency, the owner of the property shall have to pay and in this matter the owner shall not resort to any court of Law.

21. Places for and Procedure of Payment –

- (a) The bills shall be payable at such places in accordance with such procedure as the Agency may prescribe.
- (b) The employees of the Agency are not authorized to receive in cash or in any other form of the bill amount. It must be deposited in authorized banks. The Agency shall never be responsible for the amount of bill that is paid to any employee of the Agency.

22. Legal Actions on Recovery of Bill Amount –

In case of non-payment, the amount of bill shall be recovered as arrears of land revenue under the prevailing rules.

23. Complaints about Bills –

If any consumer has some objections on bill amount then he must pay the bill before registering complaint. Otherwise, connection can be disconnected. Submission of a complaint shall not be accepted as an excuse for non-payment of bill.

24. Calculation of Dues in Case of an out-of-Order Meter –

Taking due care of water meter shall be the responsibility of the consumer. If the meter goes out of order, the consumer shall accept the method of calculation of dues adopted by the Agency as elaborated in regulation 17.

25. Outstanding Dues of Water Used by Previous Owner –

Before purchasing a property, the consumer shall be bound to make sure that all the dues of water supply have been duly paid by the seller. If there are any outstanding dues of water used by previous owner, the new owner shall be responsible to pay all the dues. No excuse in this regard shall be acceptable.

26. Responsibility for the Water Service Installation –

The water service from the Agency's water main to the points of water supply in a consumer premises shall be installed by the WASA as explained in regulation 12. A water meter and main stop valve shall be fixed above the ground on firm support outside a consumer's premises through the Agency's staff/contractor. Installation of pipe line from ferrule up to the house shall be the responsibility of WASA at consumer's cost. The Consumer shall be responsible for the repair of service pipe and also prevent loss of water. In case of any damage because of water leakage from service pipe, the consumer shall be considered entirely responsible for it and his connection shall be disconnected without any notice, except that;

- i) If the water service installation under the public road outside a consumer's premises has any damage which is not clearly attributed to a consumer, such damage shall be repaired by the Agency with no cost to a consumer.
- ii) If a water meter is out of order (without apparent damage) or any fault is found in meter reading, such a meter shall be repaired by the Agency with no cost to the consumer. However, the average billing will be charged as per regulation 17 till repair /replacement of meter.

27 Keeping the Water Service Installation in Good Conditions –

A consumer shall be responsible to keep the water service installation in good conditions at all times with his goodwill and, if he finds any defect thereon, he shall immediately inform the Agency of it.

PART – III
INSTALLATION AND MAINTENANCE OF SERVICES

28. Water Supply and Pressure

WASA shall make its best efforts to provide water at adequate pressure but is not bound to supply water during some specified timings or at a specified pressure. If in case of uncontrollable circumstances, the water supply or pressure decreases, the consumer shall not have the right to reduce the amount of water bill payable by him.

29. Service in Good Order –

Every consumer whose water service is connected to an Agency's water main shall install, provide and at all times keep in good order and condition and free from defects, all water service pipes, fixtures and fittings thereof, upon the property and from the Agency's main to such property in accordance with the regulations. Failure to do so within three days of the serving of notice shall be an offence under these regulations.

30. Altered or Defective Service —

- 1) If any such water service pipe or fitting or fixture in the opinion of the Engineer:-
 - (i) is constructed, altered, added or used otherwise than in accordance with these regulations;
 - (ii) is or becomes of bad or defective quality or construction or is choked or placed or situated in a position contrary to these regulations;
 - (iii) is required to be removed, altered, extended, cleaned, repaired or disconnected from the water main of the Agency;
 - (iv) is causing damage to the property of the owner of a neighbor or subjecting property due to any kind to deterioration from the said water connection;
 - (v) is causing damage to the state owned infrastructurethe consumer to whom such water service pipe or fitting or fixtures belongs or in connection with which it is used, shall upon serving him a notice in writing signed by the Engineer, reconstruct, renew, remove, alter, extend, clean or repair to clear the choking or disconnect it from the water main of the Agency within 24 hours of the serving of notice.
- 2) Any fitting whether damaged or not, worn out or otherwise unserviceable, if connected or arranged in a faulty manner shall not be used or remain connected. It cannot be used if notwithstanding its use or connection does not contravene any of the regulations that it causes or permits undue consumption, misuse, erroneous measurement or contamination of water supplied by the Agency, or reverberation in pipes.
- 3) Any contravention of this regulation shall be an offence under these regulations.
- 4) If, through any act, neglect or default, any person has committed an offence and has caused damage to any public water supply system, that person shall, in addition to any penalty that may be imposed for that offence, be liable to make good the loss.
- 5) The amount to be paid in making good any damage under clause (4) shall, in case of dispute, be determined by the court by which the person causing such damage is convicted.
- 6) Any change in connection point with WASA main shall be intimated by the consumer to the Agency. The previous / old connection points if any may also be pointed out by consumers to their best knowledge.

31. Notice to Connect to Water Main –

The owner of a property may be required upon serving him a notice signed by the Engineer, requiring any work or things to be executed or done with such material within such time or in such a manner may be directed therein, for the purpose of providing a sufficient water supply for the use of the occupier of such premises to connect the said premises to a water main supply of the Agency, extended or laid subsequent to his getting the water connection. In the event of the owner agreeing in writing to the said work being undertaken by the Agency, the owner will forego all material, pipes, fittings and fixtures which are salvaged in moving the connection in the manner herein before described and will pay for such charges and shall be responsible for the provision of new or the replacement of any defective and affected material. Failure to comply with these requirements shall be an offence under these regulations.

32. Restriction on Work and Water Usage —

- 1) A consumer shall not —
 - (i) Permit any person other than Engineer /authorized contractor to lay, relay, repair, construct, connect, modify or in any way alter or add to his system of piping and no person other than Engineer /authorized contractor shall undertake any of the work in connection with the premises connected with a water main of the Agency;
 - (ii) Interfere with the main stop valve or meter on his supply line;
 - (iii) Use or permit to be used a water connection in such a way to cause damage or for any purpose other than that for which it had been obtained;
 - (iv) Use or permit to be used (by) or any connivance having the effect at any time of joining the (supplying) system with any other service of water.
 - (v) Carry out any works necessary to connect a private connection pipe to the Agency's pipeline within or outside the Agency's water supply distribution area;
 - (vi) Construct, install or modify any part of a water supply system;
 - (vii) Carry out maintenance services for a water supply system;
- 2) A person / consumer who fails to comply with clause (1) commits an offence and shall, on conviction, be liable to a fine not exceeding Rs.5,000/- (Rupees Five thousand).

33. Pump Directly Connected: —

- 1) No consumer shall be permitted to install a pump mechanically or manually operated, directly on a connection. In case the consumer fails to remove such an installation within 24 hours of the serving of notice, he shall be guilty of an offence under these regulations.
- 2) After the year 2016, a person who is found guilty as per clause (1), shall be liable to a fine not exceeding Rs.8,000/- (Rupees Eight thousand). Failure to pay the fine, the accused will undergo simple imprisonment up to one month. Previously sanctioned connection should comply with regulation 8(v).

PART – IV

**SPECIFICATION FOR THE LAYING OF
WATER SUPPLY PIPES AND FITTINGS**

34. Excavation, Laying and Fixing –

- 1) The material from the excavation shall be placed so as to cause the least possible obstruction and inconvenience to the public.
- 2) Proper barriers and lights shall be maintained where necessary to guard against accident during the progress of the work. On completion of refilling, the surface shall be restored as early as possible to the same condition as it was before the commencement of excavation unless the Engineer in writing otherwise requires. The formal approval of dismantling of pavement shall be obtained by the Engineer.
- 3) Unless otherwise approved, a water service pipe to any property shall be laid up to the Agency's Main at right angles, at a point opposite the property to be served as indicated by the Engineer.

35. Separate Supply to Property –

- 1) Each property shall have a separate and distinct supply from water main provided that where the Engineer approves more than one property to be supplied from one water service in such a manner as the Engineer may determine.
- 2) If a property is divided into two portions, each portion should have separate water connection. In case the second connection is not approved by the Engineer, it may be considered as an illegal connection. Rules and regulations for the illegal connection shall be applicable on it.

36. Pipe Through Foul Material –

No person shall lay any water service pipe or fitting through any sewer, drain, ash pit, cesspool or manure pit or through, in or into any place where in any event the water supplied by the Agency through such pipe or fitting shall be liable to be polluted or to escape without observation unless such pipe or fitting be laid to the satisfaction of the Engineer through a conduit of cast iron, or other approved material of sufficient length and strength to effect adequate protection to the same and to facilitate the detection of any leakage of water or unless in the case of water service pipe submerged in a sanitary flushing cistern or passing immediately below a waste pipe, it is to be constructed of a corrosion resistant material without seams or joints. The refilling of excavated area should be done with the suitable material with prior approval of Engineer.

37. Pipe Cover –

- 1) Every pipe laid in the ground shall, unless it is under a flooring of permanent character, be not less than 2 feet below the surface of the road. Provided that if by reason of some obstruction it is not reasonably practicable to lay the pipe or some part of a pipe at a depth of 2 feet or more, that pipe or part of a pipe be at the depth that is reasonably practicable.
- 2) Water service in street, where the soil is loose, shall have not less than 2 feet 6 inches of cover and in hard solid material or highly surfaced streets not less than 2 feet of cover.
- 3) Water service pipe on private property shall have not less than 12 inches of cover.

38. Pipe Clips –

Water service pipe shall be properly supported and secured by approved pipe hooks or clips. Wherever it is necessary to fix pipes clear of walls, approved extension clips shall be provided. Every water fitting whether inside or outside a building which is so placed as to be liable to damage from impact or some other cause shall be effectively protected from such damage.

39. Connection to Water Main –

Every water service pipe shall be connected to the water main by means of an approved ferrule, non-return valve, male-female adapters and bend etc. arranged in Engineer's specified manner, where necessary approved PVC saddle clamp shall be used to connect the water service main.

40. Location of Main Stop Valve –

It shall be placed outside the boundary of the property served preferably within 9 inches of the buildings line. The protection and firm fixing as per satisfaction of Engineer of main stop valve is the responsibility of consumer.

41. Stop Valve on Joint Services –

In all cases of joint water services where the stop valve is placed on private property, each house service must have separate stop valves within its own grounds in such a way that every outlet in each house can be shut off without the supply to any other houses being affected and the master valve must be fixed near the building line, in a similar position to that required for a single service.

42. Stop Valve on Meter Inlet –

Stop valve shall be fixed on the inlet coupling of all meters except where an existing stop valve is, in the opinion of the Engineer, suitably placed and close enough to act as a substitute therefor.

43. Valve on Meter Outlet –

In any case in which there is a danger of back water causing damage or being a nuisance when meters are being removed or cleaned, and in any other case ordered by the Engineer, a stop valve or reflux valve shall also be placed on the meter outlet.

44. Stop valve on Cistern Connection –

Every cistern supplied with water from the Agency mains shall have a stop valve on the outside of the cistern and in a convenient and accessible place. The stop valve shall be so placed that the cistern can be readily removed without closing any other valve. Where the water service is directly connected to the cistern, a union shall be furnished between the stop valve and the cistern, and the joint between the stop valve and the cistern and the joint between the water service pipe and cistern shall be made water tight by the use of back nuts.

45. Stop Valve on Renewed Cisterns –

In all cases where cisterns on water services as being renewed and the feed pipe to the cistern is not fitted with a stop valve, a stop valve, union and back nuts shall be fitted as part of the renewal operation.

46. Stop Valve on Private Premises –

Stop Valve shall also be fitted on any water services situated on private premises as the Engineer may direct.

47. Stop Valve to be Accessible –

All Stop valves fitted on water services and situated on private property shall, wherever practicable, be exposed to view above the ground and be in approved, protected and accessible position.

48. Missing Fittings –

In all cases where meters are being fitted or altered in position or where any renewals, alterations or repairs are being carried out on water services and any necessary stop valves, surface boxes or other fittings prescribed by the regulations do not exist, the deficiency shall be made as part of the work.

49. Services in Multi Storey Buildings –

In a building consisting of more than two floors:-

- (i) Every branch service at each floor shall be controlled by a stop valve, except as provided in clause (iii) below.
- (ii) Where two or more groups of fixtures are supplied from such a branch service each group shall be controlled by a separate stop valve; and
- (iii) Subject to the approval of the Engineer, the stop valve controlling each branch services at each floor may be omitted in cases where a vertical riser serves only one fixture or individual floor and a stop valve to control the supply is provided at the foot of such riser.

50. Stop Valve on Pipes Supplying Buildings –

- 1) Every pipe supplying water to a building (except a pipe conveying water from one building to another building the supply to which is not separately chargeable and which is within the same boundary) shall be fitted with a stop valve inside and as near as is reasonably practicable to the point where it enters that building.
- 2) Each pipe supplying water to a part of a building to which the supply is separately chargeable shall, unless the pipe passes through that part to another such part, be fitted with a stop valve inside and as near as is reasonably practicable, to the point where the pipe enters that part.
- 3) Where a pipe supplies water to a part of a building to which the supply is separately chargeable and passes through that part to another such part, every branch pipe connected to that pipe in the first mentioned part shall be fitted with a stop valve as near as is reasonably practicable, to the point of connection.
- 4) Where a service pipe supplies water to a part of a building to which the supply is separately chargeable and passes through one or more of such parts to another, it shall be so laid that before entering the first of the parts, it passes through a place, whether inside or outside the buildings to which the occupier of each of the parts has access, and in that place the pipeline shall be fitted with a stop valve, as near as is reasonably practicable, to the point where it enters the building.
- 5) Every pipe conveying water from a building to another building the supply to which is separately chargeable and which is within the same boundary but has no direct access from the first mentioned building, shall be fitted with a stop valve inside, as near as is reasonably practicable, to the point where it leaves the first mentioned building.
- 6) Where it is not reasonably practicable to fit a stop valve inside the first mentioned building, the side pipe shall be fitted with a stop valve inside and as near as is reasonably practicable the point where it enters the other building.
- 7) No stop valve fitted in accordance with any of the preceding paragraphs of this regulation portion shall be a plug cock or plug valve.
- 8) Failure to provide a stop valve within 7 days of the serving of a notice shall be an offence under these regulations.

51. Operation of Stop Valve –

Every stop valve shall be so placed that it can be readily tested by the means by which it is designed to be operated.

52. Location of Drain Taps –

No drain tap shall be buried in the ground or so placed that its outlet is in danger of getting flooded.

53. Buried or Sunken Cisterns –

- 1) No storage cistern shall be so placed that it is in danger of getting flooded.
- 2) No such cistern shall be buried or sunk in the ground unless:-
 - i. There is sufficient space around and beneath it for the purposes of maintenance, detection of leakage; and
 - ii. Either –
 - a) it is a closed vessel with a tightly fitted access cover, bolted or screwed in position, with an air inlet and overflow pipe or pipes all suitably screwed; or
 - b) its inlet pipe discharges into the air not less than 6 inches above its top edge.

54. Material of Storage Cisterns –

- (a) Every Storage cistern shall be watertight and of adequate strength and shall be constructed of galvanized iron, fiber glass, steel, copper, asbestos cement, concrete, masonry or such other material as may be supplied or approved by the Engineer.
- (b) Where the cistern is not made of a corrosion resistant material, it shall be effectively protected from corrosion.

**PART – V
SPECIFICATION OF MATERIAL**

55. Pipe Material –

All water service pipes shall be of High Density Polyethylene Pipe (HDPE) conforming to ISO 4427 or DIN 8074/8075 or equivalent standards of SDR 17 including PP (polypropylene) compression fittings and saddle clamp, FTA (Female Threaded Adaptor), coupler, bend, end cap, brass ferrule, including the manufacturer approved by Engineer or such other material as the Agency may from time to time approve or as may be approved in any particular case by the Engineer. (This includes FTA 25mm x3/4", equal bend 25mm, end cap 25mm, polyethylene saddle clamp including plugging of ends of polyethylene pipe).

56. Size of Service Pipe –

The size of service pipe shall conform to regulation 15.

57. Quality of Material –

- (a) All materials, pipes, bends, junctions, fittings and apparatus shall be of the best quality of their respective kinds, free from defects and of the kind or standard approved from time to time by the Agency.
- (b) To maintain the water quality no second hand material shall be used. If in any case, it is intended to be used in the internal plumbing, it may be done only with the prior approval of the Engineer on the written request of the owner of the property provided that such materials comply with the requirements of the regulation with regard to conditions, type, quality, soundness and efficiency.



58. Approved Material –

No person shall use any materials in or for any work of water supply which have not been approved by the Engineer, or which do not comply with the requirements of these regulations.

59. Pipes under Roads and Footpaths –

Where a water service is laid or renewed under a road way or footpath that part of the water service between the main and the stop valve shall be of High Density Polyethylene Pipe (HDPE) as mentioned in regulation 50 having casing of best galvanized steel tube or of such other materials as the Agency may specifically approve keeping minimum soil cover as inscribed in Regulation 37.

60. Pipe and Fitting

- (a) Water Service pipes of galvanized iron or steel tube, if allowed by the Engineer in special case, shall be circular in section, straight, properly galvanized, smooth, clean and free from internal flaws, blisters or other obstructions to the flow of water.
- (b) If allowed by the Engineer in special case, fittings shall be of welded, pressed iron or steel of suitable strength and formed to correct line and shape. They shall be free from internal obstructions to the flow of water.
- (c) Galvanized iron or steel pipes and fittings, shall be screwed internally or externally with British Standard Pipe thread to provide satisfactory water tight connections.

61. Joints and Washers –

Joints and washers for use in water services shall be of the best vegetable tanned, oil dressed hydraulic leather or such other material as may be approved by the Engineer.

62. Stop Valves –

- (a) Stop valves for use in water services shall be of the high pressure non rusting spindle, magnetic lockable ball valve or gate valve type, having a copper alloy body and brass or gunmetal spindle and shall conform to the standard adopted from time to time by the Agency.
- (b) Spindles on water service stop valve shall be properly packed with greasy cotton or flax, such packing to be held in position by a correctly shaped gland and gland nut.
- (c) All water service stop valves to be used below ground or in inaccessible situations shall have the bonnet secured to the body by means of a locking nut to prevent inadvertent un-screwing of the bonnet.
- (d) Stop valves shall be clearly marked with the test pressure and the manufacturers name or identification mark.
- (e) Main Stop Valve shall preferably be magnetic lockable ball valve having pressure rating of PN 20.

63. Alloy Fittings –

Alloy fittings used in connection with water services shall be of new metal without the admixture of old metal or scrap.

64. Concrete –

Concrete unless otherwise ordered shall consist by volume or by weight of one part Portland cement, two parts clean sharp sand and four parts approved hard stone not exceeding 1½ inch nominal gauge and shall be thoroughly and homogeneously mixed with clean water to such an extent as may be ordered or approved by the Engineer. In special circumstances, if required by Engineer, sulphate resisting cement (SR) and / or chemical admixtures shall be used.



65. Cement Mortar –

Cement mortar unless otherwise ordered shall consist by volume or by weight of one part Portland cement and two parts clean sharp sand thoroughly mixed with an approved proportion of clean water. In special circumstances, if required by the Engineer, sulphate resisting cement (SR) and / or chemical admixtures shall be used.

66. Cement and admixture –

- (a) Cement used in connection with any work of water supply shall be Portland cement or sulphate resisting cement (SR) of an approved brand and shall be submitted for test if so required by the Engineer. No cement or concrete shall be used which has been mixed for longer than one hour.
- (b) Appropriate admixtures depending upon the circumstances as per recommendation of the Engineer should be used.

**PART – VI
PROTECTIVE MEASURES**

67. Building Services –

Every draw-off cock used on building services shall be provided with an approved device, so fitted and maintained as to prevent the use of such cock whilst building operations are not in progress.

68. Support of Pipe –

Every pipe shall be adequately supported and shall be so arranged as to avoid any air lock or reverberation.

69. Protection of Pipe from Corrosion and Contact with Contaminating Substances:-

- (a) No pipe or pipe fitting shall be laid, installed or allowed to remain in or on the ground unless it is either of a corrosion resistant material or effectively protected from external corrosion.
- (b) No pipe shall pass into or through any ash pit, manure pit, sewer, drain, cesspool or refuse chute or any manholes connected therewith.
- (c) No pipe shall be laid, installed or allowed to remain in or on any foul soil or other substance which could cause contamination of the water in the pipe unless it is impracticable for the pipe to be elsewhere and all necessary measures are taken to avoid any risk of contaminating the water in the pipe.
- (d) No pipe made of any material susceptible to permeation by any gas or any other substance which could cause contamination of the water in the pipe shall be laid, installed or allowed to remain in position where such permeation could reasonably be expected to occur.

70. Inspection of Material and Work –

- (a) All material, pipes, fittings and apparatus shall be approved by the Engineer and where required by him shall be submitted to the Agency for examination and test.
- (b) No person shall cover up or conceal from view any underground or enclosed water service or put into use any water service until it has been inspected and approved by the Engineer.



- (c) Every Person and his employee carrying out or engaged on or in connection with any work of water supply shall afford every reasonable facility and information to enable the Engineer to make his inspection.
- (d) The Engineer shall ensure the inspection of material and work within 2 working days after receiving the inspection request.

**PART – VII
TESTS**

71. Test of Pipes and Fittings –

- (a) All pipes and fitting for use in water services shall be capable of withstanding a hydrostatic test pressure of 150 lbs. per sq. inch.
- (b) No brass or copper alloy fitting shall be used in any water services until it has been approved by the Agency.
- (c) The Engineer may order the application of a hydrostatic test or such other test or tests as he may require or approve and such test or tests shall be applied to any water services pipe or fitting.
- (d) The hydrostatic test shall be applied by filling the water service pipe or fitting with water, sealing all openings and by means of an approved test pump or other suitable apparatus subjecting the pipe or fitting to the specified pressure.
- (e) All equipment, materials, transport, power and labor necessary for inspection and tests shall be provided by the person to whom the permit for the work under test was issued.
- (f) Every fitting or apparatus submitted for approval and being of a type or design not previously approved by the Agency, shall be accompanied by a tracing of approved size. One print of same be submitted, together with the test fee as prescribed. The tracing and print shall constitute a fully dimensioned working drawing of the fitting or apparatus submitted and shall be retained by the Agency.
- (g) In the event of such fitting or apparatus not being approved by the Agency, an additional test fee shall be required for each subsequent submission.

**PART – VIII
ADDITIONAL INSTRUCTIONS**

72. Work by Engineer/contractor –

- (a) No person other than a Engineer/Contractor shall execute any work described in these regulations and no person shall permit any such work to execute except by Engineer/Contractor whose name is, at the time, included in the list of Engineer/Contractor.
- (b) All service pipes and fittings shall be supplied by the consumer for the work of laying such pipes and fittings shall be done by a Engineer/Contractor at the cost of the consumer.
- (c) The connection of a service pipe to an Agency main shall be done by an Agency plumber or contractor. In case of non-Agency plumber, intimation of the connection shall be made to the Agency, at least, three days before the connection activity.



73. Defective Work –

All pipes and fittings which on inspection or test are found to be defective shall be removed by the owner of the property and replaced by sound, approved pipes and fittings and all leaking or defective joints shall be made tight and good.

74. Maintenance –

Every Consumer who shall execute any work in connection with water supply shall, when so directed by the Agency, make good at his own expense any defect found within twelve months of the date of completion of such work, if in the opinion of the Agency, it is due to faulty workmanship or defective material.

75. Disconnection –

A water service provided by the Agency under these regulations may be cut off from the ferrule, service line or main stop valve without notice if:-

- (i) A consumer makes a written request that the services be disconnected at least 30 days prior to the required disconnection provided that such request is accompanied by the prescribed fee. He shall also clear all the dues before any action is taken by the Agency on his request;
- (ii) The consumer fails to pay the water charges and other allied charges within the specified time;
- (iii) In the opinion of the Engineer, temporary disconnection is essential in order to make another connection or repair., however the connection of these consumers will be restored, who have cleared all the outstanding dues of the Agency.
- (iv) It appears to the Engineer, that the supplying of water to any premises constitutes a danger or nuisance or has become un-necessary or is resulting in the misuse or wastage of water.
- (v) If, in the opinion of the Engineer, act(s) of the consumer is threatening the water quality of distribution main.
- (vi) Prior written notice, served on the consumer to arrange his services in accordance with the provisions of these regulations remains unattended.

76. Re-Connection –

- (a) A water service disconnected under regulation 75 (i) may be reconnected on application as if it were an application for a new connection.
- (b) A water service disconnected under regulation 75 (ii) may be reconnected on the request of consumer and on payment of any outstanding charges and the prescribed fee.
- (c) A disconnected water service shall not be reconnected without the approval of the Engineer.
- (d) For regulation 75 (iv) and (v), the reconnection will be provided only subject to removal of the cause of disconnection.

77. Disused Services –

Where any fixture on a water service is abolished or disused, the pipes to or from such fixture shall be sealed or removed and the service pipe sealed at the point of disconnection to the satisfaction of the Engineer.

78. Disconnected Services –

- 1) Misused water services shall be disconnected from the Agency's main in the following manner-
 - a. in the case of a main which is not under pressure, the main stop valve shall be removed and replaced by a galvanized wrought or galvanized malleable iron crowned plug securely screwed; or
 - b. in the case of a main which is under pressure, the main stop valve



shall be shut down, the union or coupling nut removed and the outlet of the valve securely closed with a galvanized wrought or galvanized malleable iron cap, socket or plug;

- c. in cases where a tee and valve have been inserted for the services, the disconnection shall be carried out in such manner as the Agency may direct;
 - d. the removal or sealing of a main valve shall be carried out under the supervision of the Engineer: and
 - e. The removal of tees and insertion of plug where necessary shall be affected only by employees of the Agency and the cost of such work shall be charged on the property previously supplied with water by the disused service and shall be recoverable from the owner of such property of the renewed work at the time of re-connection.
- 2) In all cases of removal of water services where tapping bends exist on metal mains of more than one inch diameter, or where plug cocks exist, such tapping bends and plug cocks shall be removed and new drilling of the main with an approved ferrule shall be made as part of the renewal work.

79. Private Source of Water Supply –

Private sources of water supply within the operation area of the Water and Sanitation Agency shall be subject to control, regulation and inspection by the Agency.

80. New Wells –

No new well, water pump or any other source of water for drilling purposes shall be dug, constructed or provided except with the prior sanction of the Agency. In case, a person fails to get such sanction, the Agency shall be competent to require the owner to abandon such service.

81. Penalties –

Any person contravening any of these regulations shall be liable to summary convictions to a fine not exceeding Rs.10,000/- (Rupees Ten Thousand) in respect of each offence and in the case of a continuing offence, to a further fine not exceeding Rs.100/- for each day during which the offence continues after conviction therefor if not mentioned against the regulation.

82 Offence of Contamination of Water

- 1) A person(s) who contaminates or causes to be contaminated any water supply line or the water supply system or any part of the water supply system with any act;
 - a. with or without intention to cause contamination;
 - b. which would likely endanger the life of any person, commits an offence.
- 2) A person(s) found guilty of an offence under clause (1), on conviction;
 - a. where death is the result of the act, shall be punished with imprisonment for a term following the clauses of Pakistan Penal Code;
 - b. where death is not the result of the act shall be liable to imprisonment as per Pakistan Penal Code or to a fine not exceeding Rs.10,000/- (Rupees Ten thousand) or both;
- 3) It shall not be a defense for the person who is with an offence under this regulation that the Agency may stop water supply to that person and all remedial work will be carried out at the expenses of that person.

83 Offence of Poisoning of Water

- 1) A person who poisons or causes to be poisoned any water supply line or the water supply system or any part of the water supply system with any substance—
 - (a) with the intention to cause death;
 - (b) with the knowledge that he is likely to cause death; or
 - (c) which would likely endanger the life of any person or community commits an offence.

- 2) A person found guilty of an offence under clause (1), on conviction—
 - (a) where death is the result of the act, shall be punished with death or imprisonment for a term following the clauses of Pakistan Penal Code;
 - (b) where death is not the result of the act but the substance which is used to contaminate / poison any water supply line or the water supply system or any part of the water supply system, shall be liable to imprisonment for a term following the clauses of Pakistan Penal Code.
 - (c) in any other case, shall be liable to a fine not exceeding Rs.100,000/- (one hundred thousand Pak Rupees) or to imprisonment for a term following the clauses of Pakistan Penal Code; or to both.

- 3) The Agency who owns the water supply system or who provides the water supply services shall immediately stop the supply of water. If the Agency does not do so, necessary action will be initiated under Pakistan Penal Code against the Agency's field staff responsible for operation and maintenance of water supply.

84 Damaging of Pipes.

- 1) A person(s) who—
 - (a) willfully, negligently or recklessly damages or causes to be damaged any water supply pipe, or structure, chamber, fixture, equipment, reservoir, cistern, pump, valve, meter, sub-meter or any part of any public water supply system ;
 - (b) flushes, draws off, diverts or takes water from any public water supply system or part of the system, unless the person is otherwise permitted under these By Laws or any Water Act or any other written law;
 - (c) bathes, wastes or throws any rubbish or creature, dead or alive, into any public water supply system or part of the system; or
 - (d) trespasses on any area of a service reservoir or booster station of a public water supply system,commits an offence.

- 2) A person(s) who is convicted for an offence under clause (1) shall be liable to pay compensation for such damage and such compensation shall be recoverable from such person by the Agency. Failure to pay the penalty will result in possible conviction under Pakistan Penal Court.



85 Illegal Connections

- 1) No person shall make or get any water connection from a public main without the permission of the Engineer.
- 2) A person(s) who contravenes clause (1) commits an offence and shall, on conviction, be liable to a fine not exceeding three years_Water Bill.

86 Illegal Reconnection

- 1) If a person or official re-connects the water supply illegally at the disconnection made by the Agency, it will be considered as an offence.
- 2) A person who commits an offence under clause (1) shall be liable to a fine not exceeding Rs. 10,000/- (Rupees Ten Thousand) or to imprisonment not exceeding for a term of one month or to both.

87. Tampering of Water Meter

A person or official who tampers with a meter or sub-meter or causes the tampering of a meter or sub-meter used for the measurement of water supplied to any premises in such a manner so as to cause the meter or sub-meter to show incorrect readings commits an offence and shall, on conviction, be liable to a fine not exceeding Rs.10,000/-(Rupees Ten Thousand).

88. Tampering of Water Supply System

A person(s) or official who tampers with any water pipe, structure, chamber, fixture and equipment, including any valve, hydrant or any part of a water supply system commits an offence and shall, on conviction, be liable to a fine not exceeding Rs.10,000/- (Rupees Ten Thousand) in addition to restoration charges for reinstating the connection.

89. Use of Unapproved material for Water Supply

A person(s) who use pipe of other than approved material shall be liable for a fine not exceeding Rs.1,000/- (Rupees One Thousand) in addition to charging the expenses of replacement of service pipe.

90. Wastage of Drinking Water

- 1) Consumers are required to adopt the practices of conservation of water. No drinking water should run or flow across the gates and accumulates on the roads due to washing of cars, floors or for the other purposes. If any water accumulates on the roads or in the streets which may cause the nourishment of mosquitoes then it shall be an offence under these regulations.
- 2) A person(s) who commits this offence shall be liable for following actions according to the order of committal:-
 - a. For the first time, a written warning shall be issued to him.
 - b. For the second time, a fine not exceeding Rs.1,000/- (Rupees One Thousand) shall be imposed on him.
- 3) For the third and subsequent times, a fine not exceeding Rs.5,000/- (Rupees Five Thousand) shall be imposed on him.

**For and on behalf of
Faisalabad Development Authority**



**MANAGING DIRECTOR
WATER AND SANITATION AGENCY
(FDA) FAISALABAD**