[APPENDICES]

# 1. Member List of the Survey Team

| Name                    | Designation   | Affiliation   |
|-------------------------|---|---|
| Dr. Mimpei ITO          | Leader  | Director<br>Environment Management Team 1<br>Environment Management Group<br>Global Environment Department, JICA        |
| Mr. Masanobu KASHIMURA  | Survey Planning   | Deputy Director<br>Environment Management Team 1<br>Environment Management Group<br>Global Environment Department, JICA |
| Mr. Hitoshi SHIMOKOCHI  | Project Manager / Sewerage Planning<br>1 / Sewage Treatment Facilities (Civil)<br>Planning 1 and Design | CTI Engineering International Co., Ltd.   |
| Mr. Masahide HANABUSA   | Deputy Project Manager / Sewerage<br>Planning 2   | Nippon Koei Co., Ltd.   |
| Mr. Yoshinobu HASEGAWA  | Sewage Treatment Facilities (Civil)<br>Planning 2   | CTI Engineering International Co., Ltd.   |
| Mr. Tsuyoshi MATSUSHITA | Soil / Land Formation / Natural<br>Condition Survey   | CTI Engineering International Co., Ltd.   |
| Mr. Toru ASAKURA        | Construction Planning / Cost<br>Estimation  | CTI Engineering International Co., Ltd.   |
| Mr. Makoto YAJIMA       | Financial Planning  | CTI Engineering International Co., Ltd.   |

## (1) First Field Survey in Cambodia (May 7 to July 8, 2018)

## (2) Second Field Survey in Cambodia (August 7 to October 7, 2018)

| Name                     | Designation   | Affiliation                                |
|--------------------------|---|--|
| Mr. Hitoshi SHIMOKOCHI   | Project Manager / Sewerage Planning<br>1 / Sewage Treatment Facilities (Civil)<br>Planning 1 and Design | CTI Engineering International Co., Ltd.    |
| Mr. Yoshihiro TAKAMURA   | Sewer Facilities (Civil)<br>Planning/Design   | Nippon Koei Co., Ltd.                      |
| Mr. Hisato TAKEDA        | Sewage Treatment Facilities<br>(Machinery and Electricity) Planning<br>and Design                       | CTI Engineering International Co., Ltd.    |
| Mr. Tsuyoshi MATSUSHITA  | Soil / Land Formation / Natural<br>Condition Survey   | CTI Engineering International Co., Ltd.    |
| Mr. Toru ASAKURA         | Construction Planning / Cost<br>Estimation  | CTI Engineering International Co., Ltd.    |
| Mr. Satoshi HIRANO       | Operation and Maintenance Planning  | Water and Sewer Bureau, City of Kitakyushu |
| Mr. Shin-ichiro TANIMOTO | Environmental and Social<br>Considerations  | Nippon Koei Co., Ltd.                      |

| Name                   | Designation                             | Affiliation                             |
|------------------------|---|---|
| Dr. Mimpei ITO         | Leader                                  | Director                                |
|                        |   | Environment Management Team 1           |
|                        |   | Environment Management Group            |
|                        |   | Global Environment Department, JICA     |
| Mr. Masanobu KASHIMURA | Survey Planning                         | Deputy Director                         |
|                        |   | Environment Management Team 1           |
|                        |   | Environment Management Group            |
|                        |   | Global Environment Department, JICA     |
| Mr. Hitoshi SHIMOKOCHI | Project Manager / Sewerage Planning     | CTI Engineering International Co., Ltd. |
|                        | 1 / Sewage Treatment Facilities (Civil) |   |
|                        | Planning 1 and Design                   |   |
| Mr. Masahide HANABUSA  | Deputy Project Manager / Sewerage       | Nippon Koei Co., Ltd.                   |
|                        | Planning 2                              |   |
|                        | -                                       |   |
| Mr. Toru ASAKURA       | Construction Planning / Cost            | CTI Engineering International Co., Ltd. |
|                        | Estimation                              |   |
|                        |   |   |

(3) Explanation on Draft Final Report in Cambodia (May 15 to May 25, 2019)

# 2. Survey Schedule [First Field Survey in Cambodia]

|     |        |     | Leader/<br>Survey Planning | Project Manager / Sewerage<br>Planning 1 / Sewage Treatment<br>Facilities (Civil) Planning 1 and<br>Design | Deputy Project Manager /<br>Sewerage Planning 2 | Sewage Treatment<br>Facilities (Civil)<br>Planning 2 | Sewer Facilities<br>(Civil)<br>Planning/Design | Sewage Treatment<br>Facilities (Machinery<br>and Electricity)<br>Planning and Design | Soil / Land Formation / Natural<br>Condition Survey       | Construction Planning / Cost<br>Estimation | Operation and<br>Maintenance<br>Planning | Financial Planning | Environmental and Social<br>Considerations |
|-----|--------|-----|----------------------------|--|---|--|--|--|---|--|--|--------------------|--|
| No. | Date   |     | ITO Minnai/                | SHIMOKOCHI   | HANADUSA  | HASECAWA   | TAKAMUDA                                       | TAKEDA   | MATCHCHITA  | ASAVIDA                                    | URANO                                    | VAIIMA             | TANIMOTO                                   |
|     |        |     | KASHIMURA<br>Masanobu      | Hitoshi  | Masahide  | Yoshinobu  | Yoshihiro                                      | Hisato   | Tsuyoshi  | Toru                                       | Satoshi                                  | Makoto             | Shin-ichiro                                |
| 1   | 7-May  | Mon |                            | *  |   |  |  |  |   |  |  |                    |  |
| 2   | 8-May  | Tue |                            | Meeting with MPWT  |   |  |  |  |   |  |  |                    |  |
| 3   | 9-May  | Wed |                            | Meeting with DPWT  |   |  |  |  |   |  |  |                    |  |
| 4   | 10-May | Thu |                            | Meeting with PPCC  |   |  |  |  | *   |  |  |                    |  |
| 5   | 11-May | Fri |                            | Meeting with JICA  |   |  |  |  | Meeting with JICA   |  |  |                    |  |
| 6   | 12-May | Sat |                            | Site Survey  |   |  |  |  | Site Survey   |  |  |                    |  |
| 7   | 13-May | Sun |                            | ditto  |   |  |  |  | ditto   |  |  |                    |  |
| 8   | 14-May | Mon |                            | Data Arrangement   |   |  |  |  | Preparation of TOR for Natural<br>Condition Surveys       |  |  |                    |  |
| 9   | 15-May | Tue |                            | ditto  |   |  |  |  | ditto   |  |  |                    |  |
| 10  | 16-May | Wed |                            | Data Arrangement   |   |  |  |  | Site Survey   |  |  |                    |  |
| 11  | 17-May | Thu |                            | Meeting with MOE   |   |  |  |  | Selection of Contractors for<br>Natural Condition Surveys |  |  |                    |  |
| 12  | 18-May | Fri |                            | Meeting with MOE   |   |  |  |  | ditto   |  |  |                    |  |
| 13  | 19-May | Sat |                            | Data Arrangement   |   |  |  |  | Data Arrangement  |  |  |                    |  |
| 14  | 20-May | Sun |                            | ditto  |   |  |  |  | ditto   |  |  |                    |  |
| 15  | 21-May | Mon |                            | Meeting with MOWRAM  | *   |  |  |  | Data Collection and Analysis                              |  |  |                    |  |
| 16  | 22-May | Tue | *                          | Data Arrangement   | Data Arrangement                                |  |  |  | ditto   |  |  |                    |  |
| 17  | 23-May | Wed | AM: Mee                    | eting with MLMUPC/ PM: M   | eeting with PPCC                                |  |  |  | ditto   |  |  |                    |  |
| 18  | 24-May | Thu | AM: Meeting                | with PPCC/ PM: Meeting wit   | h MPWT, Site Survey                             |  |  |  | ditto   |  |  |                    |  |
| 19  | 25-May | Fri | AM                         | M: Meeting with JICA/ PM: N  | ID Signing                                      |  |  |  | ditto   |  |  |                    |  |
| 20  | 26-May | Sat | •                          | Data Arrangement   | Data Arrangement                                |  |  |  | ditto   |  |  |                    |  |
| 21  | 27-May | Sun |                            | ditto  | ditto   |  |  |  | ditto   | *  |  |                    |  |
| 22  | 28-May | Mon |                            | Finalization of Natural Condition<br>Survey Items  | Data Collection                                 |  |  |  | Finalization of Natural Condition<br>Survey Items         | Data Collection                            |  |                    |  |
| 23  | 29-May | Tue |                            | ditto  | Analysis on Sewerage<br>Planning                |  |  |  | ditto   | ditto                                      |  |                    |  |
| 24  | 30-May | Wed |                            | ditto  | ditto   |  |  |  | ditto   | ditto                                      |  |                    |  |
| 25  | 31-May | Thu |                            | ditto  | ditto   |  |  |  | ditto   | ditto                                      |  |                    |  |
| 26  | 1-Jun  | Fri |                            | Analysis and Planning on<br>STP facilities   | ditto   |  |  |  | Analysis on Soil Conditions                               | ditto                                      |  |                    |  |
| 27  | 2-Jun  | Sat |                            | ditto  | •   |  |  |  | ditto   | ditto                                      |  |                    |  |
| 28  | 3-Jun  | Sun |                            | ditto  |   | *  |  |  | ditto   | ditto                                      |  |                    |  |
| 29  | 4-Jun  | Mon |                            | ditto  |   | Analysis on PTF                                      |  |  | ditto   | ditto                                      |  |                    |  |
| 30  | 5-Jun  | Tue |                            | ditto  |   | ditto  |  |  | ditto   | ditto                                      |  |                    |  |

|      |        |     | Leader/         | Project Manager / Sewerage                 | Deputy Project Manager / | Sewage Treatment      | Sewer Facilities           | Sewage Treatment    | Soil / Land Formation / Natural       | Construction Planning / Cost                             | Operation and | Financial Planning         | Environmental and Social |
|------|--------|-----|-----------------|--|--------------------------|-----------------------|----------------------------|---------------------|---------------------------------------|--|---------------|----------------------------|--------------------------|
| l    |        |     | Survey Planning | Facilities (Civil) Planning 1 and          | Sewerage Planning 2      | Planning 2            | (Civil)<br>Planning/Design | and Electricity)    | Condition Survey                      | Esumation  | Planning      |                            | Considerations           |
| Ne   | Date   |     |                 | Design                                     |                          |                       |                            | Planning and Design |                                       |  |               |                            |                          |
| 140. | Date   |     | ITO Minuri/     | SHIMOKOCHI                                 | HAMADUCA                 | HASECAWA              | TAVAMIDA                   | TAKEDA              | MATCHCHITA                            | A CA VIDA  | HIDANO        | VAIMA                      | TANIMOTO                 |
|      |        |     | KASHIMURA       | Hitoshi                                    | Masahide                 | HASEGAWA<br>Yoshinobu | Yoshihiro                  | Hisato              | MAISUSHIIA<br>Tsuyoshi                | Toru   | Satoshi       | Y AJIMA<br>Makoto          | Shin-ichiro              |
|      |        |     | Masanobu        | March Margaret                             |                          |                       |                            |                     | A 1 2 M 4 10                          | March 11 PDG 1   |               |                            |                          |
| 31   | 6-Jun  | Wed |                 | Meeting with EDC and<br>WMD/PPCC, PPWSA    |                          | Site Survey           |                            |                     | Analysis on Method for<br>Reclamation | Meeting with EDC and<br>WMD/PPCC                         |               |                            |                          |
| 32   | 7-Jun  | Thu |                 | Meeting with CMAC                          |                          | Analysis on PTF       |                            |                     | ditto                                 | Analysis on Construction                                 |               |                            |                          |
|      |        |     |                 | Mosting in Dongkor                         |                          | Thaiyob on T TT       |                            |                     | uno                                   | Planning and Cost Estimation<br>Mosting in Dangkor       |               |                            |                          |
| 33   | 8-Jun  | Fri |                 | Dumping Site                               |                          | ditto                 |                            |                     | ditto                                 | Dumping Site   |               |                            |                          |
| 34   | 9-Jun  | Sat |                 | Data Arrangement                           |                          | •                     |                            |                     | Data Arrangement                      | Data Arrangement   |               |                            |                          |
| 35   | 10-Jun | Sun |                 | ditto                                      |                          |                       |                            |                     | ditto                                 | ditto  |               |                            |                          |
| 36   | 11-Jun | Mon |                 | Analysis and Planning on<br>STP facilities |                          |                       |                            |                     | Analysis on Method for<br>Reclamation | Analysis on Construction<br>Planning and Cost Estimation |               | *                          |                          |
| 37   | 12-Jun | Tue |                 | ditto                                      |                          |                       |                            |                     | ditto                                 | Reporting  |               | Data Collection            |                          |
| 38   | 13-Jun | Wed |                 | ditto                                      |                          |                       |                            |                     | Reporting                             | ditto  |               | ditto                      |                          |
| 39   | 14-Jun | Thu |                 | Meeting with MLMUPC                        |                          |                       |                            |                     | ditto                                 | ditto  |               | Meeting with<br>JICA       |                          |
| 40   | 15-Jun | Fri |                 | Analysis and Planning on<br>STP facilities |                          |                       |                            |                     | ditto                                 | ditto  |               | Data Collection            |                          |
| 41   | 16-Jun | Sat |                 | ditto                                      |                          |                       |                            |                     | ditto                                 | ditto  |               | ditto                      |                          |
| 42   | 17-Jun | Sun |                 | ditto                                      |                          |                       |                            |                     | •                                     | •  |               | ditto                      |                          |
| 43   | 18-Jun | Mon |                 | ditto                                      |                          |                       |                            |                     |                                       |  |               | Data Analysis              |                          |
| 44   | 19-Jun | Tue |                 | Compiling Technical Note                   |                          |                       |                            |                     |                                       |  |               | ditto                      |                          |
| 45   | 20-Jun | Wed |                 | ditto                                      |                          |                       |                            |                     |                                       |  |               | ditto                      |                          |
| 46   | 21-Jun | Thu |                 | ditto                                      |                          |                       |                            |                     |                                       |  |               | ditto                      |                          |
| 47   | 22-Jun | Fri |                 | ditto                                      |                          |                       |                            |                     |                                       |  |               | ditto                      |                          |
| 48   | 23-Jun | Sat |                 | ditto                                      |                          |                       |                            |                     |                                       |  |               | ditto                      |                          |
| 49   | 24-Jun | Sun |                 | ditto                                      |                          |                       |                            |                     |                                       |  |               | ditto                      |                          |
| 50   | 25-Jun | Mon |                 | ditto                                      |                          |                       |                            |                     |                                       |  |               | N                          |                          |
| 51   | 26-Jun | Tue |                 | ditto                                      |                          |                       |                            |                     |                                       |  |               | Meeting with<br>MPWT/PPWSA |                          |
| 52   | 27-Jun | Wed |                 | ditto                                      |                          |                       |                            |                     |                                       |  |               |                            |                          |
| 53   | 28-Jun | Thu |                 | ditto                                      |                          |                       |                            |                     |                                       |  |               | N                          |                          |
| 54   | 29-Jun | Fri |                 | ditto                                      |                          |                       |                            |                     |                                       |  |               | PPCC PPCC                  |                          |
| 55   | 30-Jun | Sat |                 | ditto                                      |                          |                       |                            |                     |                                       |  |               | •                          |                          |
| 56   | 1-Jul  | Sun |                 | ditto                                      |                          |                       |                            |                     |                                       |  |               |                            |                          |
| 57   | 2-Jul  | Mon |                 | ditto                                      |                          |                       |                            |                     |                                       |  |               |                            |                          |
| 58   | 3-Jul  | Tue |                 | ditto                                      |                          |                       |                            |                     |                                       |  |               |                            |                          |
| 59   | 4-Jul  | Wed |                 | Meeting with MEF                           |                          |                       |                            |                     |                                       |  |               |                            |                          |
| 60   | 5-Jul  | Thu |                 | Reporting                                  |                          |                       |                            |                     |                                       |  |               |                            |                          |
| 61   | 6-Jul  | Fri |                 | JICA                                       |                          |                       |                            |                     |                                       |  |               |                            |                          |
| 62   | 7-Jul  | Sat |                 | Reporting                                  |                          |                       |                            |                     |                                       |  |               |                            |                          |
| 63   | 8-Jul  | Sun |                 | •  |                          |                       |                            |                     |                                       |  |               |                            |                          |

| No  | Data   |     | Leader/<br>Survey Planning | Project Manager / Sewerage<br>Planning 1 / Sewage Treatment<br>Facilities (Civil) Planning 1 and<br>Design | Deputy Project Manager /<br>Sewerage Planning 2 | Sewage Treatment<br>Facilities (Civil)<br>Planning 2 | Sewer Facilities<br>(Civil)<br>Planning/Design | Sewage Treatment<br>Facilities (Machinery<br>and Electricity)<br>Planning and Design | Soil / Land Formation / Natural<br>Condition Survey | Construction Planning / Cost<br>Estimation | Operation and<br>Maintenance<br>Planning | Financial Planning | Environmental and Social<br>Considerations |
|-----|--------|-----|----------------------------|--|---|--|--|--|---|--|--|--------------------|--|
| INO | . Date |     | ITO Minnai/                | SHIMOKOCHI   | HANADUSA  | UASECAWA   | TAKAMIDA                                       | TAKEDA   | MATSUSUITA  | A S A KI ID A                              | UID ANO                                  | VAIIMA             | TANIMOTO                                   |
|     |        |     | KASHIMURA<br>Masanobu      | Hitoshi  | Masahide  | Yoshinobu  | Yoshihiro                                      | Hisato   | Tsuyoshi  | Toru                                       | Satoshi                                  | Makoto             | Shin-ichiro                                |
| 1   | 6-Aug  | Mon |                            |  |   |  |  |  |   |  |  |                    |  |
| 2   | 7-Aug  | Tue |                            |  |   |  |  | *  |   |  |  |                    |  |
| 3   | 8-Aug  | Wed |                            |  |   |  |  | Site Survey  |   |  |  |                    |  |
| 4   | 9-Aug  | Thu |                            |  |   |  |  | Data Collection  |   |  |  |                    |  |
| 5   | 10-Aug | Fri |                            |  |   |  |  | ditto  |   |  |  |                    |  |
| 6   | 11-Aug | Sat |                            |  |   |  |  | ditto  |   | *  |  |                    |  |
| 7   | 12-Aug | Sun |                            |  |   |  |  | ditto  |   | Analysis on Construction<br>Planning       |  |                    |  |
| 8   | 13-Aug | Mon |                            |  |   |  |  | Planning on M&E<br>Facilities  |   | ditto                                      | *  |                    |  |
| 9   | 14-Aug | Tue |                            |  |   |  |  | ditto  |   | ditto                                      | Site Survey                              |                    |  |
| 10  | 15-Aug | Wed |                            |  |   |  |  | ditto  |   | ditto                                      | Meeting with<br>DPWT                     |                    |  |
| 11  | 16-Aug | Thu |                            |  |   |  |  | ditto  |   | ditto                                      | Data Collection                          |                    |  |
| 12  | 17-Aug | Fri |                            |  |   |  |  | ditto  |   | ditto                                      | ditto                                    |                    |  |
| 13  | 18-Aug | Sat |                            |  |   |  |  | ditto  |   | ditto                                      | ditto                                    |                    |  |
| 14  | 19-Aug | Sun |                            |  |   |  |  | ditto  |   | ditto                                      | ditto                                    |                    |  |
| 15  | 20-Aug | Mon |                            |  |   |  | *  | ditto  |   | Analysis on<br>Cost Estimation             | Reporting                                |                    |  |
| 16  | 21-Aug | Tue |                            | *  |   |  | Data Collection                                | ditto  |   | ditto                                      | ditto                                    |                    | *  |
| 17  | 22-Aug | Wed |                            | Analysis and Planning on<br>STP facilities   |   |  | Site Survey                                    | Site Survey  |   | ditto                                      | ditto                                    |                    | Site Survey                                |
| 18  | 23-Aug | Thu |                            | ditto  |   |  | Data Collection                                | Planning on M&E<br>Facilities  |   | ditto                                      | ditto                                    |                    | Confirmation on EIA regulations            |
| 19  | 24-Aug | Fri |                            | ditto  |   |  | ditto  | ditto  |   | ditto                                      | ditto                                    |                    | ditto                                      |
| 20  | 25-Aug | Sat |                            | ditto  |   |  | ditto  | ditto  |   | ditto                                      | ditto                                    |                    | Data Arrangement                           |
| 21  | 26-Aug | Sun |                            | ditto  |   |  | ditto  | ditto  |   | ditto                                      | ditto                                    |                    | ditto                                      |
| 22  | 27-Aug | Mon |                            | ditto  |   |  | Planning on<br>Sewer Facilities                | Reporting  |   | ditto                                      |  |                    | Preparation of TOR<br>for EIA and RAP      |
| 23  | 28-Aug | Tue |                            | ditto  |   |  | ditto  | ditto  | Analysis on Soil Conditions                         | ditto                                      |  |                    | Data Collection                            |
| 24  | 29-Aug | Wed |                            | Meeting<br>with DPWT   |   |  | Meeting<br>with DPWT                           | Meeting<br>with EDC  | ditto   | Meeting<br>with EDC                        |  |                    | ditto                                      |
| 25  | 30-Aug | Thu |                            | Analysis and Planning on<br>STP facilities   |   |  | Planning on<br>Sewer Facilities                | Reporting  | ditto   | Reporting                                  |  |                    | ditto                                      |
| 26  | 31-Aug | Fri |                            | ditto  |   |  | ditto  | •  | ditto   | ditto                                      |  |                    | ditto                                      |
| 27  | 1-Sep  | Sat |                            | ditto  |   |  | ditto  |  | ditto   | •  |  |                    | ditto                                      |
| 28  | 2-Sep  | Sun |                            | ditto  |   |  | ditto  |  | ditto   |  |  |                    | ditto                                      |
| 29  | 3-Sep  | Mon |                            | ditto  |   |  | ditto  |  | ditto   |  |  |                    | Selection of<br>Contractors                |
| 30  | 4-Sep  | Tue |                            | ditto  |   |  | ditto  |  | ditto   |  |  |                    | Data Collection                            |

|      |        |        | Leader/<br>Survey Planning             | Project Manager / Sewerage<br>Planning 1 / Sewage Treatment | Deputy Project Manager /<br>Sewerage Planning 2 | Sewage Treatment<br>Facilities (Civil) | Sewer Facilities<br>(Civil) | Sewage Treatment<br>Facilities (Machinery | Soil / Land Formation / Natural<br>Condition Survey | Construction Planning / Cost<br>Estimation | Operation and<br>Maintenance | Financial Planning | Environmental and Social<br>Considerations |
|------|--------|--------|--|---|---|--|-----------------------------|---|---|--|------------------------------|--------------------|--|
| No   | Dete   |        |  | Pacilities (Civil) Planning 1 and<br>Design                 |   | Planning 2                             | Planning/Design             | and Electricity)<br>Planning and Design   |   |  | Planning                     |                    |  |
| 190. | Date   |        | ITO Mimpei/                            | SHIMOKOCHI  | HANABUSA  | HASEGAWA                               | TAKAMURA                    | TAKEDA                                    | MATSUSHITA  | ASAKURA                                    | HIRANO                       | YAJIMA             | TANIMOTO                                   |
|      |        |        | KASHIMURA<br>Masanobu                  | Hitoshi   | Masahide  | Yoshinobu                              | Yoshihiro                   | Hisato                                    | Tsuyoshi  | Toru                                       | Satoshi                      | Makoto             | Shin-ichiro                                |
| 31   | 5-Sep  | Wed    |  | Analysis and Planning on<br>STP facilities                  |   |  | Reporting                   |   | Planning of Ground<br>Formulation                   |  |                              |                    | Data Collection                            |
| 32   | 6-Sep  | Thu    |  | ditto   |   |  | ditto                       |   | ditto   |  |                              |                    | ditto                                      |
| 33   | 7-Sep  | Fri    |  | ditto   |   |  | ditto                       |   | ditto   |  |                              |                    | ditto                                      |
| 34   | 8-Sep  | Sat    |  | ditto   |   |  | •                           |   | ditto   |  |                              |                    | ditto                                      |
| 35   | 9-Sep  | Sun    |  | ditto   |   |  |                             |   | ditto   |  |                              |                    | ditto                                      |
| 36   | 10-Sep | Mon    |  | Analysis and Planning on<br>STP facilities                  |   |  |                             |   | ditto   |  |                              |                    | Reporting                                  |
| 37   | 11-Sep | Tue    |  | ditto   |   |  |                             |   | ditto   |  |                              |                    | ditto                                      |
| 38   | 12-Sep | Wed    |  | ditto   |   |  |                             |   | ditto   |  |                              |                    | ditto                                      |
| 39   | 13-Sep | Thu    |  | ditto   |   |  |                             |   | ditto   |  |                              |                    | ditto                                      |
| 40   | 14-Sep | Fri    |  | ditto   |   |  |                             |   | ditto   |  |                              |                    | ditto                                      |
| 41   | 15-Sep | Sat    |  | ditto   |   |  |                             |   | ditto   |  |                              |                    | ditto                                      |
| 42   | 16-Sep | Sun    |  | ditto   |   |  |                             |   | ditto   |  |                              |                    | •  |
| 43   | 17-Sep | Mon    |  | ditto   |   |  |                             |   | Reporting   |  |                              |                    |  |
| 44   | 18-Sep | Tue    |  | ditto   |   |  |                             |   | ditto   |  |                              |                    |  |
| 45   | 19-Sep | Wed    |  | ditto   |   |  |                             |   | ditto   |  |                              |                    |  |
| 46   | 20-Sep | Thu    |  | ditto   |   |  |                             |   | ditto   |  |                              |                    |  |
| 47   | 21-Sep | Fri    |  | ditto   |   |  |                             |   | ditto   |  |                              |                    |  |
| 48   | 22-Sep | Sat    |  | ditto   |   |  |                             |   | ditto   |  |                              |                    |  |
| 49   | 23-Sep | Sun    |  | ditto   |   |  |                             |   | •   |  |                              |                    |  |
| 50   | 24-Sep | Mon    |  | ditto   |   |  |                             |   |   |  |                              |                    |  |
| 51   | 25-Sep | Tue    |  | ditto   |   |  |                             |   |   |  |                              |                    |  |
| 52   | 26-Sep | Wed    |  | ditto   |   |  |                             |   |   |  |                              |                    |  |
| 53   | 27-Sep | Thu    |  | ditto   |   |  |                             |   |   |  |                              |                    |  |
| 54   | 28-Sep | Fri    |  | Meeting with DPWT   |   |  |                             |   |   |  |                              |                    |  |
| 55   | 29-Sep | Sat    |  | ditto   |   |  |                             |   |   |  |                              |                    |  |
| 56   | 30-Sep | Sun    |  | ditto   |   |  |                             |   |   |  |                              |                    |  |
| 57   | 1-Oct  | Mon    |  | ditto   |   |  |                             |   |   |  |                              |                    |  |
| 58   | 2-Oct  | Tue    |  | Meeting with PPCC   |   |  |                             |   |   |  |                              |                    |  |
| 59   | 3-Oct  | Wed    |  | ditto   |   |  |                             |   |   |  |                              |                    |  |
| 60   | 4-Oct  | Thu    |  | ditto   |   |  |                             |   |   |  |                              |                    |  |
| 61   | 5-Oct  | Fri    |  | ditto   |   |  |                             |   |   |  |                              |                    |  |
| 62   | 6-Oct  | Sat    |  | ditto   |   |  |                             |   |   |  |                              |                    |  |
| 63   | 7-Oct  | Sun    |  | •   |   |  |                             |   |   |  |                              |                    |  |
|      | MPWT   | : Min  | istry of Public W                      | orks and Transport  |   |  |                             | $\star$ Mobilization to 1                 | Phnom Penh  |  | Saturday                     | Saturday           |  |
|      | MLMU   | PC: N  | /inistry of Land !<br>m Penh Capital C | Management and, Urban l                                     | Planning and Constructi                         | on                                     |                             | Demobilization i                          | from Phnom Penh                                     |  | Sunday                       | Sunday<br>Holiday  |  |
|      |        | 4 mm0. | i viin Capital C                       |   |   |  |                             |   |   |  | Honday                       | monuay             |  |

DPWT : Department of Public Works and Transport

PPWSA : Phnom Penh Water Supply Authority

| No. | Date   |     | Leader   | Survey Planning  | Project Manager / Sewerage<br>Planning 1 / Sewage Treatment<br>Facilities (Civil) Planning 1 and<br>Design | Deputy Project Manager /<br>Sewerage Planning 2 | Construction Planning / Cost<br>Estimation |  |  |
|-----|--------|-----|--|------------------|--|---|--|--|--|
|     |        |     | 110 Mimpei   | Masanobu         | Hitoshi  | HANABUSA<br>Masahide                            | ASAKURA<br>Toru                            |  |  |
| 1   | 15-May | Wed |  |                  | *  |   |  |  |  |
| 2   | 16-May | Thu |  |                  | Data Arrangement<br>Site Survey  |   |  |  |  |
| 3   | 17-May | Fri |  |                  | Meeting with DPWT<br>Meeting with PPCC   |   |  |  |  |
| 4   | 18-May | Sat |  |                  | Data Arrangement   |   |  |  |  |
| 5   | 19-May | Sun |  |                  | ditto  |   |  |  |  |
| 6   | 20-May | Mon | *  | *                | Data Arrangement   | Data Arrangement                                | Data Arrangement                           |  |  |
| 7   | 21-May | Tue |  | Discuss M        | inutes of Discussion (M/D) w   | ith PPCC including DPWT                         |  |  |  |
| 8   | 22-May | Wed | Data Arrangement   | Data Arrangement | Data Arrangement   | Data Arrangement                                | Data Arrangement                           |  |  |
| 9   | 23-May | Thu | Discuss and Sign Minutes of Discussion (M/D) between JICA Mission and PPCC |                  |  |   |  |  |  |
| 10  | 24-May | Fri | •  | Data Arrangement | Data Arrangement   | Data Arrangement                                | Data Arrangement                           |  |  |
| 11  | 25-May | Sat |  | •                | •  | •   | •  |  |  |

## [Explanation on Draft Final Report in Cambodia]

PPCC : Phnom Penh Capital City

DPWT : Department of Public Works and Transport

# 3. List of Parties Concerned in Cambodia

| Name<br>Phnom Penh Canital City: PPCC | Designation<br>(Head Office) | Organization  |
|---------------------------------------|------------------------------|---|
| H F Koeut Chhe                        | Vice Governor                | PPCC  |
| H.E. Nuon Pharath                     | Vice Governor                | PPCC  |
| H.E. Suy Serith                       | Vice Governor                | PPCC  |
| Hok Kimeong                           | Deputy Director              | Urbanization Division   |
| Long Thide                            | Vice Chief                   | Urbanization Division   |
| Their Smin                            | Vice Chief                   | Urbanization Division   |
|                                       | vice Chief                   | Urbanization Division   |
| Sor Dara                              | Chief                        | Urbanization Division   |
| Sor Fliara                            | Dimenter                     | Weste Management Division   |
| Nioa Kollharde                        | Director<br>Demotes Director | Waste Management Division   |
| Nuon Samnavutn                        | Deputy Director              | Waste Management Division   |
| Kim vainanak Tnida                    | Deputy Director              | A durinistration  |
| Chnay Sopeara                         | Assistant                    | Administration<br>Public Relations and International Cooperation Office |
| I neam Kithdeka                       | Director                     | Public Relations and International Cooperation Office                   |
| Soth Rothanurak                       | Deputy Director              |   |
| Keo Channarith                        | Chief of Landfill            | Dangkor Landfill Site   |
| Department of Public Works and        | Transport : DPWT/PPCC        |   |
| Sam Piseth                            | Director                     | DPWT/PPCC   |
| Chou Kimtry                           | Deputy Director              | DPWT/PPCC   |
| Moeung Sophan                         | Advisor                      | DPWT/PPCC   |
| Pheng Pharinet                        | Officer                      | DPWT/PPCC   |
| Drainage Pumping Station and Se       | wage Treatment Plant Offic   | e : DSO/DPWT  |
| Dourng Chansarath                     | Deputy Chief                 | DSO   |
| Chhorng Vantha                        | Deputy Chief                 | DSO   |
| Men Sokkhen                           | Deputy Chief                 | DSO   |
| Department of Land Managemen          | t, Urban Planning and Cons   | truction: DLMUPC/PPCC   |
| Mey Chettra                           | Deputy Director              | DLMUPC/PPCC   |
| Hoeung Rathsokha                      | Vice Chief                   | DLMUPC/PPCC   |
| Som Meakhbormey                       |                              | DLMUPC/PPCC   |
| <b>Department of Environment : DO</b> | <u>E/PPCC</u>                |   |
| Keo Chanarith                         | Director                     | DOE/PPCC  |
| Khuon Dara                            | Deputy Director              | DOE/PPCC  |
| Khans in Phnom Penh Capital Ci        | <u>ty</u>                    |   |
| Ma Sopheap                            | Deputy Governor              | Khan Meanchey   |
| Tema Sophea                           | Deputy Governor              | Khan Dangkor  |
| Keo Samol                             | Deputy Governor              | Khan Chamkarmon   |
| Neang Sophary                         | Deputy Governor              | Khan Po Senchey   |
| Huot Leapiseth                        | Deputy Governor              | Khan Prek Pnov  |
| Nu Keosokun                           | Chief                        | Khan Po Senchey, District Office of Public Works                        |
| Minister of Public Works and Tra      | <u>nsport: MPWT</u>          |   |
| Heng Rathpiseth                       | Director General             | General Directorate of Public Works                                     |
| Chao Sopheak Phibal                   | Director                     | Sewerage Management and Construction Department                         |
| Dr. Lim Soktay                        | Deputy Director              | Sewerage Management and Construction Department                         |
| Ministry of Land Management, U        | rban Planning and Constru    | ction: MLMUPC   |
| Dr. Pen Sophal                        | Secretary of State           | MLMUPC  |
| Dr. Chhann Sorphal                    | General Director             | General Department of Construction                                      |
| Dr. Chea Phalry                       | Deputy General Director      | General Department of Construction                                      |
| <b>Ministry of Environment : MOE</b>  |                              |   |
| Pak Sokharavuth                       | Deputy Director General      | General Directorate of Environmental Protection                         |
| Chandath Him                          | Deputy Director              | General Directorate of Environmental Protection                         |
| Chea Nara                             | Deputy Director              | Department of Air Quality and Noise Management                          |
| Phnom Penh Water Supply Autho         | ority : PPWSA                |   |
| Samreth Sovithiea                     | Deputy General Director      |   |
| Chea Satephoat                        | Director                     | Planning and Project Department   |

| <u>Embassy of Japan in Cambodia</u> |                             |  |
|-------------------------------------|-----------------------------|--|
| Atsushi Hirose                      | Second Secretary            | Embassy of Japan                           |
| <u>Electricité du Cambodge</u>      |                             |  |
| Chreng Karodine                     | Deputy Chief Officer        | Corporate Planning and Projects Department |
| Sim Chanthea                        | Deputy Chief                | System Analysis and GIS Office             |
| Oeng Lysorng                        | Technical Officer           | Corporate Planning and Projects Department |
| <b>Cambodian Mine Action Center</b> |                             |  |
| Oum Phumro                          | Deputy Director General     |  |
| JICA Cambodia                       |                             |  |
| Yuichi Sugano                       | Chief Representative        | JICA, Cambodia Office                      |
| Kotaro Tanaka                       | Deputy Chief Representative | JICA, Cambodia Office                      |
| Masashi Nishikawa                   | Project Formulation Advisor | JICA, Cambodia Office                      |
| Tomoyuki Yamada                     | Project Formulation Advisor | JICA, Cambodia Office                      |
| Say Bora                            | Program Officer             | JICA, Cambodia Office                      |
| Veng Samnang                        | Interpreter                 |  |
|                                     |                             |  |

## 4. Minutes of Discussions

#### 4.1 Minutes of Discussions (May 25, 2018)

#### **MINUTES OF DISCUSSIONS**

ON

#### THE PREPARATORY SURVEY ON

# THE PROJECT FOR SEWERAGE SYSTEM DEVELOPMENT IN THE PHNOM PENH CAPITAL CITY

In response to the request from the Government of the Kingdom of Cambodia (hereinafter referred to as " Cambodia "), the Government of Japan decided to conduct a Preparatory Survey on the Project for Sewerage System Development in the Phnom Penh Capital City (hereinafter referred to as "the Project"), and entrusted the Preparatory Survey to Japan International Cooperation Agency (hereinafter referred to as "JICA").

JICA sent the Preparatory Survey Team for the Outline Design (hereinafter referred to as "the Team") to Cambodia, headed by Dr. Ito Mimpei, Director of Environmental Management Team, Environmental Management Group, Global Environment Department, and the Team stayed in Cambodia from 22nd to 25th May, 2018.

The Team held a series of discussions with the officials concerned of the Government of Cambodia and conducted field surveys in the Project sites. In the course of the discussions, both sides have confirmed the main items described in the attached sheets. The Team will proceed to further works and prepare the Preparatory Survey Report.

Phnom Penh, 25th May, 2018



Dr.Ito Mimpei Leader Preparatory Survey Team Japan International Cooperation Agency Japan **H.E. Khuong Sreng** Governor Phnom Penh Capital City Cambodia

M. K. F

## ATTACHMENT

## 1. Objective of the Project

The objective of the Project is to minimize water pollution load to Cheung Aek Lake through construction of new sewerage treatment facilities, thereby contributing to protect and improve water and sanitation environment of Cheung Aek Lake.

## 2. Title of the Preparatory Survey

Both sides confirmed the title of the Preparatory Survey as "the Preparatory Survey on the Project for Sewerage System Development in the Phnom Penh Capital City".

## 3. Project Site

Cambodian side requested to change the original site (total 16.3 ha including 3.5 ha for the Project) of Sewerage Treatment Plant (hereinafter referred to as "STP") near St. 371 in Khan Mean Chey which was proposed in Pre-Feasibility Study on Priority Project of Sewage Management in "The Study on Drainage and Sewerage Improvement Project in Phnom Penh Metropolitan Area" with letter from Governor of Phnom Penh Capital Administration (hereinafter referred to as "PPCA") because many impacts to the underground utilities such as water networks, drainage networks, electricity networks, and optical cables networks as well as the people living there. Both sides agreed that the alternative site is fixed as shown in Annex 2 and the site will not be changed again in any reason.

## 4. Process of obtaining land title for STP

Both sides confirmed that the processes of obtaining of land title for STP are as follows;

- 1) To obtain permission from Prime Minister's office to change the status of land from National Public Land to Private State Land requested by PPCA
- 2) To prepare Sub-decree on transferring land title from National Public Land to Private State Land by PPCA in coordination with relevant ministries and institutions

Both sides also agreed that those two processes shall be completed by the end of 2018.

5. Sewer Line

The Team explained that there are two possibilities for developing sewer line. The first possibility is to develop under the road inside the private housing development area. The second possibility is to develop sewer line under the embankment of improved drainage channel. In either case, the Team requested PPCA to identify the position of sewer line by August, 2018. PPCA replied that PPCA needs to discuss with developer on the possibility of constructing sewer line under the road since the developer has a plan to construct road soon. PPCA further explained that the timing of identifying the route of sewer line depends on the meeting between PPCA and developer. Both sides confirmed the necessity of identifying the route as soon as possible and make their effort with the technical support from consultant team.

The Team also explained that the cost for constructing road inside the private housing developing area or improved drainage channel shall be borne by Cambodian side. The Cambodian side agreed it.

6. Line Agency and Executing Agency

Both sides confirmed the line agency and the executing agency as follows:

- 6-1. The line agency is the Phnom Penh Capital Administration (hereinafter referred to as "PPCA"), which would supervise the executing organization.
- 6-2. The executing agency is the Department of Public Works and Transport of PPCA (hereinafter referred to as "DPWT"), which shall coordinate with all the relevant

1

A. K & Kat

agencies/line departments to ensure smooth implementation of the Project and ensure that the Undertakings are taken by them properly and on schedule. The organization charts are shown in Annex 3.

- 7. Items requested by the Government of Cambodia
  - 7-1. As a result of discussions, both sides confirmed that the items requested by the Government of Cambodia for the Project are as shown in the Table below.

| Components  | Detailed Contents<br>(will be studied in the Preparatory Survey)   |
|---|--|
| Construction of Sewerage<br>Treatment Plant (STP)<br>(including Interception<br>Facilities) | <ul> <li>Capacity: 5,000m<sup>3</sup></li> <li>Treatment method: Pre-treated Trickling Filtration (PTF)</li> </ul> |
| Access Road/Sewer pipe<br>from Trabek Pumping<br>Station to STP                             | <ul> <li>Length: 2,000m</li> <li>Diameter of Sewer pipe: 500mm</li> </ul>  |

- 7-2. JICA will assess the appropriateness of the above requested items through the survey and will report findings to the Government of Japan. The final components of the Project would be decided by the Government of Japan.
- 8. Japanese Grant Aid Scheme
  - 8-1. The Cambodian side understands the Japanese Grant Scheme and its procedures as described in Annex 4, Annex 5 and Annex 6, and necessary measures to be taken by the Government of Cambodia.
  - 8-2. The Cambodian side agreed to take the necessary measures, as described in Annex 7 for smooth implementation of the Project. The contents of the Annex 7 will be elaborated and refined during the Preparatory Survey and be agreed in the mission dispatched for explanation of the Draft Preparatory Survey Report. The contents of Annex 7 will be updated as the Preparatory Survey progresses, and eventually, will be used as an attachment to the Grant Agreement.
- 9. Schedule of the Survey
  - 9-1. The Team will proceed with further survey in Cambodia until the end of September 2018.
  - 9-2. JICA will prepare a draft Preparatory Survey Report in English and will dispatch another mission to Cambodia in order to explain its contents around middle of April 2019.
  - 9-3. If the contents of the Draft Preparatory Survey Report is accepted in principle and the undertakings are fully agreed by the Cambodian side, JICA will complete the final report in English and send it to the Government of Cambodia around July 2019.
  - 9-4. The above schedule is tentative and subject to change due to the progress of the Survey.
- 10. Environmental and Social Considerations
  - 10-1. The Cambodian side confirmed to give due environmental and social considerations during implementation of the Project, and after completion of the Project, in accordance with "the ЛСА Guidelines for Environmental and Social Considerations [April, 2010]".
  - 10-2. The Project is categorized as B because the Project is not located in a sensitive area, nor has it sensitive characteristics, nor falls it into sensitive sectors under "the JICA guidelines for environmental and social considerations [April 2010]", and its potential adverse impacts on the environment are not likely to be significant. The Cambodian

2

A M. & Cut

side confirmed to conduct the necessary procedures concerning the environmental assessment (including stakeholder meetings, Environmental Impact Assessment (EIA) and information disclosure, etc.) and make EIA report of the Project. The EIA approval shall be received from the responsible authorities and submitted to JICA by April 2019.

10-3. Both sides confirmed that there is no expected PAP (Project Affected People) residing in the Project site. During the Survey, if clarified the Projects will result in involuntary resettlement, the Cambodian side confirmed to prepare a Resettlement Action Plan (RAP)/Abbreviated Resettlement Action Plan (ARAP) and make it available to the public. Both sides also confirmed that some residents living in surrounding area of STP site in Cheung Aek Lake may lose their agricultural income because of its reclamation. The Cambodian side confirmed to provide the affected people with sufficient compensation and/or support in accordance with RAP/ARAP, in a timely manner.

#### 11. Other Relevant Issues

11-1. Formal Request

Cambodian side confirmed that Formal request of the Project shall be submitted by December 2018 at the latest.

11-2. Reclamation of Cheung Aek Lake

Cambodian side explained that permission from PPCA after transferring land title is necessary to be obtained for reclamation of STP site. Both sides confirmed that detail of the reclamation including reclamation method, volume and source of soil for reclamation, sediment of ground of reclaimed area, will be researched in the Survey.

11-3. Sludge Treatment

Sewerage Management Master Plan in "The Study on Drainage and Sewerage Improvement Project in Phnom Penh Metropolitan Area" proposed sludge from STP would be delivered to Dangkor final disposal site after primary treatment in STP. Both sides agreed that detail of the treatment, deliver and disposal will be verified in the Survey.

- 11-4. Taxes borne by Cambodian side and its budget allocation
  - With reference to Annex 4 and Annex 5, both sides confirmed that customs duties, internal taxes and other fiscal levies which may be imposed in the country of the recipient with respect to the purchase of the products and/or the services be exempted by its designated authority without using the Grant.
- 11-5. Monitoring during the implementation

PPCA and DPWT agreed to monitor the Project every three (3) months during the implementation by using the Project Monitoring Report form as attached in Annex 8

11-6. Confidentiality of the Project

The Team explained that the Preparatory Survey Report to be prepared at the end of the survey would be disclosed to the public in Japan. However, the Team also explained that a confidential part which might affect bidding process such as cost estimation should be kept undisclosed until the bidding has been completed.

Annex 1 Project Sites

Annex 2 Comparison between original site and alternative site

Annex 3 Organization Chart

Annex 4 Japanese Grant

Annex 5 Flow Chart of Japanese Grant

- Annex 6 Financial Flow of Japanese Grant
- Annex 7 Major Undertakings to be taken by Recipient Government

Annex 8 Project Monitoring Report (template)

or 1 to the



ST M. K & Cuf



or Man & Cef



#### **Organization Chart of PPCA**

#### **Organization Chart of DPWT**



= Ming up

#### **JAPANESE GRANT**

The Japanese Grant is non-reimbursable fund provided to a recipient country (hereinafter referred to as "the Recipient") to purchase the products and/or services (engineering services and transportation of the products, etc.) for its economic and social development in accordance with the relevant laws and regulations of Japan. Followings are the basic features of the project grants operated by JICA (hereinafter referred to as "Project Grants").

#### 1. Procedures of Project Grants

Project Grants are conducted through following procedures (See "PROCEDURES OF JAPANESE GRANT" for details):

- (1) Preparation
  - The Preparatory Survey (hereinafter referred to as "the Survey") conducted by JICA
- (2) Appraisal

-Appraisal by the government of Japan (hereinafter referred to as "GOJ") and JICA, and Approval by the Japanese Cabinet

- (3) Implementation
  - Exchange of Notes

-The Notes exchanged between the GOJ and the government of the Recipient

Grant Agreement (hereinafter referred to as "the G/A")

-Agreement concluded between JICA and the Recipient

Banking Arrangement (hereinafter referred to as "the B/A")

-Opening of bank account by the Recipient in a bank in Japan (hereinafter referred to as "the Bank") to receive the grant

Construction works/procurement

-Implementation of the project (hereinafter referred to as "the Project") on the basis of the G/A

(4) Ex-post Monitoring and Evaluation

-Monitoring and evaluation at post-implementation stage

#### 2. Preparatory Survey

#### (1) Contents of the Survey

The aim of the Survey is to provide basic documents necessary for the appraisal of the the Project made by the GOJ and JICA. The contents of the Survey are as follows:

- Confirmation of the background, objectives, and benefits of the Project and also institutional capacity of

or M. > f lif

relevant agencies of the Recipient necessary for the implementation of the Project.

- Evaluation of the feasibility of the Project to be implemented under the Japanese Grant from a technical, financial, social and economic point of view.
- Confirmation of items agreed between both parties concerning the basic concept of the Project.
- Preparation of an outline design of the Project.
- Estimation of costs of the Project.
- Confirmation of Environmental and Social Considerations

The contents of the original request by the Recipient are not necessarily approved in their initial form. The Outline Design of the Project is confirmed based on the guidelines of the Japanese Grant.

JICA requests the Recipient to take measures necessary to achieve its self-reliance in the implementation of the Project. Such measures must be guaranteed even though they may fall outside of the jurisdiction of the executing agency of the Project. Therefore, the contents of the Project are confirmed by all relevant organizations of the Recipient based on the Minutes of Discussions.

#### (2) Selection of Consultants

For smooth implementation of the Survey, JICA contracts with (a) consulting firm(s). JICA selects (a) firm(s) based on proposals submitted by interested firms.

#### (3) Result of the Survey

JICA reviews the report on the results of the Survey and recommends the GOJ to appraise the implementation of the Project after confirming the feasibility of the Project.

#### 3. Basic Principles of Project Grants

#### (1) Implementation Stage

#### 1) The E/N and the G/A

After the Project is approved by the Cabinet of Japan, the Exchange of Notes (hereinafter referred to as "the E/N") will be singed between the GOJ and the Government of the Recipient to make a pledge for assistance, which is followed by the conclusion of the G/A between JICA and the Recipient to define the necessary articles, in accordance with the E/N, to implement the Project, such as conditions of disbursement, responsibilities of the Recipient, and procurement conditions. The terms and conditions generally applicable to the Japanese Grant are stipulated in the "General Terms and Conditions for Japanese Grant (January 2016)."

on M. K Clif

- 2) Banking Arrangements (B/A) (See "Financial Flow of Japanese Grant (A/P Type)" for details)
  - a) The Recipient shall open an account or shall cause its designated authority to open an account under the name of the Recipient in the Bank, in principle. JICA will disburse the Japanese Grant in Japanese yen for the Recipient to cover the obligations incurred by the Recipient under the verified contracts.
  - b) The Japanese Grant will be disbursed when payment requests are submitted by the Bank to ЛСA under an Authorization to Pay (A/P) issued by the Recipient.
- 3) Procurement Procedure

The products and/or services necessary for the implementation of the Project shall be procured in accordance with JICA's procurement guidelines as stipulated in the G/A.

#### 4) Selection of Consultants

In order to maintain technical consistency, the consulting firm(s) which conducted the Survey will be recommended by JICA to the Recipient to continue to work on the Project's implementation after the E/N and G/A.

#### 5) Eligible source country

In using the Japanese Grant disbursed by JICA for the purchase of products and/or services, the eligible source countries of such products and/or services shall be Japan and/or the Recipient. The Japanese Grant may be used for the purchase of the products and/or services of a third country as eligible, if necessary, taking into account the quality, competitiveness and economic rationality of products and/or services necessary for achieving the objective of the Project. However, the prime contractors, namely, constructing and procurement firms, and the prime consulting firm, which enter into contracts with the Recipient, are limited to "Japanese nationals", in principle.

#### 6) Contracts and Concurrence by JICA

The Recipient will conclude contracts denominated in Japanese yen with Japanese nationals. Those contracts shall be concurred by JICA in order to be verified as eligible for using the Japanese Grant.

#### 7) Monitoring

The Recipient is required to take their initiative to carefully monitor the progress of the Project in order to ensure its smooth implementation as part of their responsibility in the G/A, and to regularly report to JICA about its status by using the Project Monitoring Report (PMR).

#### 8) Safety Measures

The Recipient must ensure that the safety is highly observed during the implementation of the Project.

#### 9) Construction Quality Control Meeting

Construction Quality Control Meeting (hereinafter referred to as the "Meeting") will be held for quality assurance and smooth implementation of the Works at each stage of the Works. The member of the Meeting will be composed by the

or 1 = fut

Recipient (or executing agency), the Consultant, the Contractor and JICA. The functions of the Meeting are as followings:

- a) Sharing information on the objective, concept and conditions of design from the Contractor, before start of construction.
- b) Discussing the issues affecting the Works such as modification of the design, test, inspection, safety control and the Client's obligation, during of construction.

#### (2) Ex-post Monitoring and Evaluation Stage

1) After the project completion, JICA will continue to keep in close contact with the Recipient in order to monitor that the outputs of the Project is used and maintained properly to attain its expected outcomes.

2) In principle, JICA will conduct ex-post evaluation of the Project after three years from the completion. It is required for the Recipient to furnish any necessary information as JICA may reasonably request.

#### (3) Others

#### 1) Environmental and Social Considerations

The Recipient shall carefully consider environmental and social impacts by the Project and must comply with the environmental regulations of the Recipient and JICA Guidelines for Environmental and Social Considerations (April, 2010).

#### 2) Major undertakings to be taken by the Government of the Recipient

For the smooth and proper implementation of the Project, the Recipient is required to undertake necessary measures including land acquisition, and bear an advising commission of the A/P and payment commissions paid to the Bank as agreed with the GOJ and/or JICA. The Government of the Recipient shall ensure that customs duties, internal taxes and other fiscal levies which may be imposed in the Recipient with respect to the purchase of the Products and/or the Services be exempted or be borne by its designated authority without using the Grant and its accrued interest, since the grant fund comes from the Japanese taxpayers.

#### 3) Proper Use

The Recipient is required to maintain and use properly and effectively the products and/or services under the Project (including the facilities constructed and the equipment purchased), to assign staff necessary for this operation and maintenance and to bear all the expenses other than those covered by the Japanese Grant.

or 1 x 1 if

## 4) Export and Re-export

The products purchased under the Japanese Grant should not be exported or re-exported from the Recipient.

1. to gut



Annex 5

Financial Flow of Japanese Grant (A/P Type)

or 1. 1 for

#### PROCEDURES OF JAPANESE GRANT

| Stage                      | Procedures   | Remarks   | Recipient<br>Government | Japanese<br>Government | JICA       | Consultants | Contractors | Agent Bank |
|----------------------------|--|---|-------------------------|------------------------|------------|-------------|-------------|------------|
| Official Request           | Request for grants through diplomatic channel  | Request shall be submitted before appraisal stage.  | x                       | x                      |            | ~           |             |            |
| 1. Preparation             | (1) Preparatory Survey<br>Preparation of outline design and cost<br>estimate                                 |   | x                       |                        | x          | x           |             |            |
|                            | (2)Preparatory Survey<br>Explanation of draft outline design, including<br>cost estimate, undertakings, etc. | 0   | x                       |                        | x          | x           |             |            |
| 2. Appraisal               | (3)Agreement on conditions for implementation  | Conditions will be explained with the<br>draft notes (E/N) and Grant Agreement<br>(G/A) which will be signed before<br>approval by Japanese government. | x                       | x<br>(E/N)             | x<br>(G/A) |             |             |            |
|                            | (4) Approval by the Japanese cabinet   |   |                         | x                      |            |             |             |            |
|                            | (5) Exchange of Notes (E/N)  |   | x                       | x                      |            |             |             |            |
|                            | (6) Signing of Grant Agreement (G/A)   |   | x                       |                        | x          |             |             |            |
|                            | (7) Banking Arrangement (B/A)  | Need to be informed to JICA   | x                       |                        |            |             |             | x          |
|                            | (8) Contracting with consultant<br>and issuance of Authorization to Pay (A/P)                                | Concurrence by JICA is required   | x                       |                        |            | x           |             | x          |
|                            | (9) Detail design (D/D)  |   | x                       |                        |            | x           |             |            |
| 3. Implementation          | (10) Preparation of bidding documents  | Concurrence by JICA is required   | x                       |                        |            | x           |             |            |
|                            | (11) Bidding   | Concurrence by JICA is required   | x                       |                        |            | x           | x           |            |
|                            | (12) Contracting with contractor/supplier<br>and issuance of A/P   | Concurrence by JICA is required   | x                       |                        |            |             | x           | x          |
|                            | (13) Construction works/procurement  | Concurrence by JICA is required for<br>major modification of design and<br>amendment of contracts.  | x                       |                        |            | x           | x           |            |
|                            | (14) Completion certificate  |   | x                       |                        |            | x           | x           |            |
| 4. Ex-post<br>monitoring & | (15) Ex-post monitoring  | To be implemented generally after 1, 3,<br>10 years of completion, subject to<br>change   | x                       |                        | x          |             |             |            |
| evaluation                 | (16) Ex-post evaluation  | To be implemented basically after 3 years of completion   | x                       |                        | x          |             |             |            |

notes:

1. Project Monitoring Report and Report for Project Completion shall be submitted to JICA as agreed in the G/A.

2. Concurrence by JICA is required for allocation of grant for remaining amount and/or contingencies as agreed in the G/A.

or A. S. f Uf ka

## Annex 7

## Major Undertakings to be taken by Recipient Government

## 1) Before the Tender

| NO | Items   | Deadline   | In charge    | Estimated<br>Cost | Ref. |
|----|---|--|--------------|-------------------|------|
| 1  | To open Bank Account (Banking Arrangement (B/A))  | within 1 month<br>after G/A                            | PPCC         |                   |      |
| 2  | To issue A/P to a bank in Japan (the Agent Bank) for the payment to the consultant  | within 1 month<br>after the signing of<br>the contract | PPCC         |                   |      |
| 3  | To approve EIA (Conditions of approval should be fulfilled, if any) and secure<br>the necessary budget for implementation   | By the end of<br>April 2019                            | PPCC         |                   |      |
| 4  | To transfer land title from National Public Land to Private State Land for STP  | By the end of December 2018                            | PPCC<br>DPWT |                   |      |
| 5  | To identify the position of Access road/Sewer Line  | By August 2018   | PPCC<br>DPWT |                   |      |
| 6  | To secure the necessary budget and implement land acquisition and resettlement<br>(including preparation of resettlement sites), and compensation with full<br>replacement cost in accordance with ARAP | before start of the construction                       | MEF, PPCC    |                   |      |
| 7  | To secure sufficient spaces at the respective Project site/s for temporary facilities such as a contractor's office, workshop, building materials storage, etc. needed for the construction work.       | before notice of<br>the Tender                         | PPCC         |                   |      |
| 8  | To complete the investigation and removal of UXO and Mines in all construction areas (including sewer installation alignment).  | before notice of<br>the Tender                         | PPCC         |                   |      |

# 2) During the Project

| NO | Items   | Deadline  | In charge | Estimated<br>Cost | Ref. |
|----|---|---|-----------|-------------------|------|
| 1  | To issue A/P to a bank in Japan (the Agent Bank) for the payment to the Supplier(s)   | within 1 month after<br>the signing of the<br>contract(s) | PPCC      |                   |      |
| 2  | To bear the following commissions to a bank of Japan for the banking services based upon the B/A  |   |           |                   | _    |
|    | 1) Advising commission of A/P   | within 1 month after<br>the signing of the<br>contract    | PPCC      |                   |      |
|    | 2) Payment commission for A/P   | every payment   | PPCC      |                   |      |
| 3  | To ensure prompt unloading, customs clearance of the products at ports of<br>disembarkation in the recipient country and to assist internal transportation in<br>the country of the Recipient of the products   | during the<br>Project                                     | PPCC      |                   |      |
| 4  | To accord Japanese nationals whose services may be required in connection<br>with the supply of the products and the services under the verified contract such<br>facilities as may be necessary for their entry into the recipient country and stay<br>therein for the performance of their work | during the<br>Project                                     | PPCC      |                   |      |
| 5  | To ensure that customs duties, internal taxes and other fiscal levies which may<br>be imposed in the country of the Recipient with respect to the purchase of the<br>Products and/or the Services be exempted by its designated authority without<br>using the Grant                              | during the<br>Project                                     | PPCC      |                   |      |

5 1 × 1 Ufu

| 6  | To bear all the expenses, other than those to be borne by the Japanese Grant,<br>necessary for construction of the facilities as well as for the transportation and<br>installation of the equipment | during the<br>Project                                      | PPCC         |   |  |
|----|--|--|--------------|---|--|
| 7  | To provide temporary facilities for the availability or accessibility of electricity, water, etc. for the construction work  | prior to<br>commencement<br>of the<br>construction         | PPCC         |   |  |
| 8  | To provide facilities for distribution of electricity, water supply, drainage and<br>other incidental facilities necessary for the implementation of the Project<br>outside the site(s)              |  |              | 2 |  |
|    | 1) Electricity Distribution lines to the site  | -  | PPCC         |   |  |
|    | 2) Water Supply<br>City water distribution main to the site  |  | PPCC         |   |  |
|    | 3) Telecommunication Distribution lines to the site  |  | PPCC         |   |  |
| 9  | To implement EMP and EMoP  | during the construction                                    | PPCC,<br>DOE |   |  |
| 10 | To submit results of environmental monitoring to JICA, by using the monitoring form, on a quarterly basis as a part of Project Monitoring Report   | during the construction                                    | PPCC         |   |  |
| 11 | To implement ARAP (livelihood restoration program, if needed)  | for a period based on<br>livelihood<br>restoration program | PPCC         |   |  |
| 12 | To secure necessary conditions and environments on the site(s) in cooperation<br>with related authorities and local residents<br>(e.g. Security guards, traffic control, etc.)                       | during the construction                                    | PPCC         |   |  |

(EMP: Environmental Management Plan, EMoP: Environmental Monitoring Plan)

## 3) After the Project

| NO  | Items   | Deadline                                 | In charge     | Estimated<br>Cost | Ref. |
|-----|---|--|---------------|-------------------|------|
| 1   | To implement EMP and EMoP   | for a period based<br>on EMP and<br>EMoP | PPCC, DOE     |                   |      |
|     | <ul> <li>To submit results of environmental monitoring to JICA, by using the monitoring form, semiannually</li> <li>The period of environmental monitoring may be extended if any significant negative impacts on the environment are found. The extension of environmental monitoring will be decided based on the agreement between PPCC and JICA.</li> </ul> | for three years<br>after the Project     | PPCC, DOE     |                   |      |
| · 2 | To maintain and use properly and effectively the facilities constructed and<br>equipment provided under the Grant Aid<br>1) Allocation of maintenance cost<br>2) Operation and maintenance structure<br>3) Routine check/Periodic inspection  | after completion of<br>the construction  | PPCC,<br>DPWT |                   |      |

(B/A: Banking Arrangement, A/P: Authorization to pay, N/A: Not Applicable)

(Note) Progress of the specific obligations of the Recipient may be confirmed and updated from time to time with written agreement between JICA and the Recipient in the form other than the amendment of the G/A.

St 1. H & Ma

## Project Monitoring Report on Project Name Grant Agreement No. XXXXXXX 20XX, Month

# **Organizational Information**

|  |                   |               |           | <u> </u> |
|--|-------------------|---------------|-----------|----------|
|  |                   |               |           |          |
| Signer of the G/A  | Person in Charge  | (Designation) |           |          |
| (Recipient)  |                   |               |           |          |
|  | Contacts          | Address:      |           |          |
| and the second s |                   | Phone/FAX:    |           |          |
| and the second of the second o |                   | Email:        |           |          |
|  |                   |               |           |          |
|  | Person in Charge  | (Designation) |           |          |
| Executing  | r erson ni charge |               | , <u></u> |          |
| Agency   | Contacts          | Address:      | <u></u>   |          |
|  |                   | Phone/FAX:    | <u>.</u>  |          |
| the second second  |                   | Email:        |           |          |
| te"  |                   |               |           |          |
|  |                   |               |           |          |
|  | Person in Charge  | (Designation) |           |          |
| Line Ministry  |                   |               |           |          |
|  | Contacts          | Address:      | <u></u>   |          |
|  |                   | Phone/FAX:    |           |          |
| The state of the second  |                   | Email:        |           |          |

## **General Information:**

| Project Title     |   |             |
|-------------------|---|-------------|
| E/N               | Signed date:<br>Duration:                                   |             |
| G/A               | Signed date:<br>Duration:                                   |             |
| Source of Finance | Government of Japan: Not exceeding JPY<br>Government of (): | <u>mil.</u> |

of M. My lif

# 1: Project Description

## **1-1 Project Objective**

#### 1-2 Project Rationale

- Higher-level objectives to which the project contributes (national/regional/sectoral policies and strategies)
- Situation of the target groups to which the project addresses

## 1-3 Indicators for measurement of "Effectiveness"

| Indicators                            | Original (Yr )                        | Target (Yr ) |
|---------------------------------------|---------------------------------------|--------------|
| ······                                |                                       |              |
| <b>Dualitative indicators to meas</b> | sure the attainment of project object |              |

# 2: Details of the Project

#### 2-1 Location

| Components | Original                         | Actual |
|------------|----------------------------------|--------|
|            | (proposed in the outline design) |        |
| 1.         |                                  |        |
|            | ·                                |        |
|            |                                  |        |

## 2-2 Scope of the work

| Components | Original*                        | Actual* |
|------------|----------------------------------|---------|
|            | (proposed in the outline design) |         |
| 1          |                                  |         |
|            |                                  |         |
|            |                                  |         |
|            |                                  |         |

Reasons for modification of scope (if any).

(PMR)

or M. By In

2

## 2-3 Implementation Schedule

|       | Orig                  | inal                    |        |
|-------|-----------------------|-------------------------|--------|
| Items | (proposed in the      | (at the time of signing | Actual |
|       | 👔 outline design) 🖕 🖄 | the Grant Agreement)    |        |
|       |                       |                         |        |
|       |                       |                         |        |
|       |                       |                         |        |

Reasons for any changes of the schedule, and their effects on the project (if any)

- 2-4 Obligations by the Recipient2-4-1 Progress of Specific Obligations
  - See Attachment 2.
  - **2-4-2 Activities** See Attachment 3.
  - 2-4-3 Report on RD See Attachment 11.
- 2-5 Project Cost

## 2-5-1 Cost borne by the Grant(Confidential until the Bidding)

| <br>Components                                       | e de la carte                             | A C Millio   | ost -<br>m Yen) |
|--|---|--|-----------------|
| <ul> <li>(proposed in the outline design)</li> </ul> | Actual (in case of any ;<br>modification) | Original <sup>1),2),</sup><br>(proposed in<br>the outline<br>design) | Actual          |
| 1.   |   |  |                 |
|  |   |  |                 |
|  |   |  |                 |
| Total  |   |  |                 |

Note: 1) Date of estimation: 2) Exchange rate: 1 US Dollar = Yen

## 2-5-2 Cost borne by the Recipient

| Components                                   | <b>T 1 2</b> <i>1</i>            | Cost : (1,000 Ta   | ka)    |
|--|----------------------------------|--|--------|
| Original<br>(proposed in the outline design) | (in case of any<br>modification) | Original <sup>13,2</sup><br>t (proposed in<br>the outline :<br>design) | Actual |
| <br>1.                                       |                                  |  |        |
|  |                                  |  |        |

ar May up

3

Note: 1) Date of estimation: 2) Exchange rate: 1 US Dollar =

Reasons for the remarkable gaps between the original and actual cost, and the countermeasures (if any)

(PMR)

#### 2-6 Executing Agency

- Organization's role, financial position, capacity, cost recovery etc,
- Organization Chart including the unit in charge of the implementation and number of employees.

Original (at the time of outline design)

name:

role:

financial situation:

institutional and organizational arrangement (organogram): human resources (number and ability of staff):

Actual (PMR)

## 2-7 Environmental and Social Impacts

- The results of environmental monitoring based on Attachment 5 (in accordance with Schedule 4 of the Grant Agreement).

- The results of social monitoring based on in Attachment 5 (in accordance with Schedule 4 of the Grant Agreement).

- Disclosed information related to results of environmental and social monitoring to local stakeholders (whenever applicable).

## 3: Operation and Maintenance (O&M)

#### 3-1 Physical Arrangement

- Plan for O&M (number and skills of the staff in the responsible division or section, availability of manuals and guidelines, availability of spareparts, etc.)

**Original** (at the time of outline design)

Actual (PMR)

#### 3-2 Budgetary Arrangement

- Required O&M cost and actual budget allocation for O&M

**Original** (at the time of outline design)

# 4: Potential Risks and Mitigation Measures

- Potential risks which may affect the project implementation, attainment of objectives, sustainability
- Mitigation measures corresponding to the potential risks

## Assessment of Potential Risks (at the time of outline design)

| . (Description of Risk) | Probability: High/Moderate/Low                                   |
|-------------------------|--|
|                         | Impact: High/Moderate/Low  |
|                         | Analysis of Probability and Impact:                              |
|                         | Mitigation Measures:   |
|                         | Action required during the implementation stage:                 |
|                         | Contingency Plan (if applicable):                                |
| . (Description of Risk) | Probability: High/Moderate/Low                                   |
|                         | Impact: High/Moderate/Low<br>Analysis of Probability and Impact: |
|                         |  |
|                         | Mitigation Measures:   |
|                         | Action required during the implementation stage:                 |
|                         | Contingency Plan (if applicable):                                |
| (Description of Risk)   | Probability: High/Moderate/Low                                   |
|                         | Impact: High/Moderate/Low<br>Analysis of Probability and Impact: |
|                         | Mitigation Measures:   |
|                         | Action required during the implementation stage:                 |

or 1. 1 / ka

5

|                                      | Contingency Plan (if applicable): |
|--------------------------------------|-----------------------------------|
|                                      |                                   |
| Actual Situation and Countermeasures | 3                                 |
| (PMR)                                |                                   |
|                                      |                                   |
|                                      |                                   |

# 5: Evaluation and Monitoring Plan (after the work completion)

## 5-1 Overall evaluation

Please describe your overall evaluation on the project.

## 5-2 Lessons Learnt and Recommendations

Please raise any lessons learned from the project experience, which might be valuable for the future assistance or similar type of projects, as well as any recommendations, which might be beneficial for better realization of the project effect, impact and assurance of sustainability.

## 5-3 Monitoring Plan of the Indicators for Post-Evaluation

Please describe monitoring methods, section(s)/department(s) in charge of monitoring, frequency, the term to monitor the indicators stipulated in 1-3.

= 1. × f lef

#### Attachment

- 1. Project Location Map
- 2. Specific obligations of the Recipient which will not be funded with the Grant
- 3. Monthly Report submitted by the Consultant
- Appendix Photocopy of Contractor's Progress Report (if any)
  - Consultant Member List
  - Contractor's Main Staff List
- 4. Check list for the Contract (including Record of Amendment of the Contract/Agreement and Schedule of Payment)
- 5. Environmental Monitoring Form / Social Monitoring Form
- 6. Monitoring sheet on price of specified materials (Quarterly)
- 7. Report on Proportion of Procurement (Recipient Country, Japan and Third Countries) (PMR (final )only)
- 8. Pictures (by JPEG style by CD-R) (PMR (final)only)
- 9. Equipment List (PMR (final )only)
- 10. Drawing (PMR (final )only)
- 11. Report on RD (After project)

87 M. M. ful

Attachment 6

# Monitoring sheet on price of specified materials

| Ŀ.  | Initial Conditions (Confirmed) |                     |                           |                                   |                          |                   |                 |
|-----|--------------------------------|---------------------|---------------------------|-----------------------------------|--------------------------|-------------------|-----------------|
|     | frems of Specified Materials   | Lattial Volume<br>A | Initial Unit<br>Price (¥) | Initial total.<br>Prace<br>C-A-AB | 1% of Contracts<br>Price | Price (Decreased) | Price Texperies |
| -   | Item 1                         | Ot                  |                           | •                                 |                          | •                 |                 |
| 2   | Item 2                         | <b>O</b> t          | •                         | •                                 |                          |                   |                 |
| က   | Item 3                         |                     |                           |                                   |                          |                   |                 |
| 4   | Item 4                         |                     |                           |                                   |                          |                   |                 |
| So. | Item 5                         |                     |                           |                                   |                          |                   |                 |
|     |                                |                     |                           |                                   |                          |                   |                 |

- 2. Monitoring of the Unit Price of Specified Materials(1) Method of Monitoring : •••
- (2) Result of the Monitoring Survey on Unit Price for each specified materials

|        | Item 1<br>Item 2 | 0.44 P.0 |  |  |  |
|--------|------------------|----------|--|--|--|
| 02 4 a | Item 5<br>Item 5 |          |  |  |  |

(3) Summary of Discussion with Contractor (if necessary)

.

of M. K ful
Attachment 7

Report on Proportion of Procurement (Recipient Country, Japan and Third Countries) (Actual Expenditure by Construction and Equipment each)

|                             | e                    | T                   | Econim Decomment    | Total  |
|-----------------------------|----------------------|---------------------|---------------------|--------|
|                             | Domestic Procurement | Foreign Procurement | roreign rioculement | T OLAL |
|                             | (Recipient Country)  | (Japan)             | (Third Countries)   | Q      |
|                             | Α                    | В                   | С                   |        |
| Construction Cost           | (A/D%)               | (B/D%)              | (C/D%)              |        |
| Direct Construction<br>Cost | (A/D%)               | (B/D%)              | (C/D%)              |        |
| others                      | (%D%)                | (B/D%)              | (C/D%)              |        |
| Equipment Cost              | (%D/V)               | (B/D%)              | (C/D%)              |        |
| Design and Supervision Cost | (A/D%)               | (B/D%)              | (C/D%)              |        |
| Total                       | (A/D%)               | (B/D%)              | (C/D%)              |        |
|                             |                      |                     |                     |        |

or M. St fla

# 4.2 Minutes of Discussions (May 23, 2019) MINUTES OF DISCUSSIONS ON THE PREPARATORY SURVEY ON THE PROJECT FOR SEWERAGE SYSTEM DEVELOPMENT IN THE PHNOM PENH CAPITAL CITY (Explanation on Draft Preparatory Survey Report)

With reference to the minutes of discussions signed between Phnom Penh Capital Administration (hereinafter referred to as "PPCA") and the Japan International Cooperation Agency (hereinafter referred to as "JICA") on 25th May, 2018 and in response to the request from the Government of the Kingdom of Cambodia (hereinafter referred to as "Cambodia") dated 31st May, 2017, JICA dispatched the Preparatory Survey Team (hereinafter referred to as "the Team") for the explanation of Draft Preparatory Survey Report (hereinafter referred to as "the Draft Report") for the Project for Sewerage System Development in the Phnom Penh Capital City (hereinafter referred to as "the Project").

As a result of the discussions, both sides agreed on the main items described in the attached sheets.

Dr. Ito Mimpei Leader Preparatory Survey Team Japan International Cooperation Agency Japan

Penh, May 23rd, 2019 el 19 H.E. Khuong Sreng Governor

Governor Phnom Penh Capital City The Kingdom of Cambodia

#### ATTACHEMENT

### 1. Objective of the Project

The objective of the Project is to minimize water pollution load to Cheung Aek Lake through construction of new sewerage treatment facilities, thereby contributing to protect and improve water and sanitation environment of Cheung Aek Lake.

#### 2. Title of the Preparatory Survey

Both sides confirmed the title of the Preparatory Survey as "the Preparatory Survey on the Project for Sewerage System Development in the Phnom Penh Capital City".

#### 3. Project site

Both sides confirmed that the site of the Project is in Phnom Penh Capital City (hereinafter referred to as "PPCC"), which is shown in Annex 1.

4. Responsible authority for the Project

Both sides confirmed the authorities responsible for the Project are as follows:

- 4-1. The Department of Public Works and Transport (hereinafter referred to as "DPWT") of PPCA will be the executing agency for the Project. The Executing Agency shall coordinate with all the relevant authorities to ensure smooth implementation of the Project and ensure that the undertakings for the Project shall be taken care by relevant authorities properly and on time. The organization charts are shown in Annex 2.
- 4-2. The line ministry of the Executing Agency is PPCA. PPCA shall be responsible for supervising the Executing Agency on behalf of the Government of Cambodia.

#### 5. Contents of the Draft Report

After the explanation of the contents of the Draft Report by the Team, the Cambodian side agreed to its contents.

6. Cost estimate

Both sides confirmed that the cost estimate described in the Draft Report is provisional and will be examined further by the Government of Japan for its approval. Both sides confirmed that the cost estimate including the contingency explained by the Team is provisional and will be examined further by the Government of Japan for its approval. The contingency would cover the additional cost against natural disaster, unexpected natural conditions, etc.

the second

- Confidentiality of the cost estimate and technical specifications Both sides confirmed that the cost estimate and technical specifications of the Project should never be disclosed to any third parties until all the contracts under the Project are concluded.
- 8. Timeline for the project implementation The Team explained to the Cambodian side that the expected timeline for the project implementation is as attached in Annex 3.

# 9. Expected outcomes and indicators

Both sides agreed that key indicators for expected outcomes are as follows. The Cambodian side will be responsible for the achievement of agreed key indicators targeted in year 2027 and shall monitor the progress based on those indicators. [Quantitative indicators]

| indicators   | Present<br>(2018) | Future(2027):three years after<br>Completion of this Project |
|--|-------------------|--|
| Wastewater treated population (person)                       | 0                 | 19,000   |
| Amount of wastewater<br>treatment (m <sup>3</sup> /day)      | 0                 | 5,000  |
| Concentration of BOD<br>(discharged water quality)<br>(mg/L) | 195               | 30   |

[Qualitative indicators]

- > To improve water environment of public water body (Cheung Aek Lake)
- > To improve citizen's living environment in target area

# 10. Technical assistance ("Soft Component" of the Project)

Considering the sustainable operation and maintenance of the products and services granted through the Project, a series of technical assistance is planned under the Project. The Cambodian side confirmed to deploy necessary number of counterparts who are appropriate and competent in terms of its purpose of the technical assistance as described in the Draft Report.

11. Undertakings of the Project

Both sides confirmed the undertakings of the Project as described in Annex 4 which is updated from Annex 7 in "Minutes of Discussions on the Preparatory Survey on the Project for Sewerage System Development in the Phnom Penh Capital City

to up

signed on 25<sup>th</sup> May, 2018. With regard to exemption of customs duties, internal taxes and other fiscal levies as stipulated in item No. 5 at "2) During the Project" of Annex 4, both sides confirmed that such customs duties, internal taxes and other fiscal levies, which shall be clarified in the bid documents by DPWT during the implementation stage of the Project.

The Cambodian side assured to take the necessary measures and coordination including allocation of the necessary budget which are preconditions of implementation of the Project. It is further agreed that the costs are indicative, i.e. at Outline Design level. More accurate costs will be calculated at the Detailed Design stage. Both sides also confirmed that the Annex 4 will be used as an attachment of G/A.

### 12. Monitoring during the implementation

The Project will be monitored by the Executing Agency and reported to JICA by using the form of Project Monitoring Report (PMR) attached as Annex 5. The timing of submission of the PMR is described in Annex 4.

#### 13. Project completion

Both sides confirmed that the Project completes when all the facilities constructed and equipment procured by the grant are in operation. The completion of the Project will be reported to JICA promptly, but in any event not later than six months after completion of the Project.

### 14. Ex-Post Evaluation

JICA will conduct ex-post evaluation after three (3) years from the project completion, in principle, with respect to five evaluation criteria (Relevance, Effectiveness, Efficiency, Impact, Sustainability). The result of the evaluation will be publicized. The Cambodian side is required to provide necessary support for the data collection.

#### 15. Schedule of the Study

JICA will finalize the Preparatory Survey Report based on the confirmed items. The report will be sent to the Cambodian side around August, 2019.

#### 16. Environmental and Social Considerations

- 16-1 General Issues
- 16-1-1 Environmental Guidelines and Environmental Category

The Team explained that 'IICA Guidelines for Environmental and Social Considerations (April 2010)' (hereinafter referred to as "the Guidelines") is

y of

applicable for the Project. The Project is categorized as B because the Project is not located in a sensitive area, nor has sensitive characteristics, nor falls into sensitive sectors under the JICA guidelines for environmental and social considerations(April 2010), it is not likely to have a significant adverse impact on the environment.

16-1-2 Environmental Checklist

The environmental and social considerations including major impacts and mitigation measures for the Project are summarized in the Environmental Checklist attached as Annex 6. Both sides confirmed that in case of major modification of the content of the Environmental Checklist, the Cambodian side shall submit the modified version to JICA in a timely manner.

### 16-2 Environmental Issues

16-2-1 Environmental Impact Assessment (EIA)

Both sides confirmed that DPWT shall obtain approval of the EIA report from Ministry of Environment (hereinafter referred as to "MoE") by October 2019. Cambodian side agreed JICA's disclosure of the EIA report on its website.

## 16-2-2 Environmental Management Plan and Environmental Monitoring Plan

Both sides confirmed Environmental Management Plan (hereinafter referred to as "EMP") and Environmental Monitoring Plan (hereinafter referred to as "EMOP") of the Project are as Annex 7, respectively. Both sides agreed that environmental mitigation measures and monitoring shall be conducted based on the EMP and EMOP, which may be updated during the detailed design stage.

## 16-3 Social Issues

## 16-3-1 Land Acquisition and Resettlement

Cambodian side explained that process of changing land title from "state public property" to "state private property" for acquiring and utilizing necessary space(197,360m<sup>2</sup>) on Cheung Aek lake as reclaimed land for constructing Sewerage Treatment Plant (hereinafter referred to as "STP") was completed through being issued "Sub-Decree No.168 dated 13th December, 2018 on Amendment of Cheung Aek Lake area located in Meanchey District and Dangkor District, Phnom Penh Capital City and Takhmao City, Kandal Province". Both sides also confirmed no additional process is necessary for land acquisition for the Project.

Both sides confirmed that 22 households (154 persons) would be affected due to the implementation of the Project though their means of gaining income including cultivating morning glory are not legal.

St of

Both sides also confirmed that there is no involuntary resettlement affected by the implementation of the Project because there is no residence in the Project's site.

Though "Sub-decree No. 22 ANK/BK, 2018 on the Standard Operating Procedures (SOP) for Land Acquisition and Involuntary Resettlement (LAR) for Externally Financed Projects" stipulates illegal residents and/or developer is not target on (Abbreviated) Resettlement Action Plan (hereinafter referred to as "ARAP"), both sides agreed that sufficient compensation and/or restoration of livelihood shall be implemented for Project Affected Persons (hereinafter referred to as "PAPs") based on the ARAP prepared and authorized by DPWT during the Project in line with the Guidelines. Both sides also confirmed there was no objection in public consultations which were held at October 2018 and May 2019 from cultivator of morning glory in the Project site on Cheung Aek Lake about the proposed compensation of both supplying alternative cultivation site and monetary compensation for 3 months worth of their income loss as well as no objection from other PAPs. Both sides further confirmed that the total cost for ARAP implementation is as Annex 8 and PPCA will secure budget for the cost.

#### 16-4 Environmental and Social Monitoring

16-4-1 Environmental Monitoring

Both sides agreed that the Cambodian side will submit results of environmental monitoring to JICA with PMR by using the monitoring form attached as Annex 9. The timing of submission of the monitoring form is described in Annex 4.

In case JICA finds that there is a need for improvement in a situation with respect to environmental considerations after the agreed monitoring period, JICA may request to extend the period of monitoring and reporting until JICA confirms the issues have been properly addressed in accordance with the agreement between PPCA and JICA.

#### 16-4-2 Social Monitoring

Both sides confirmed that the Cambodian side will implement social monitoring about affection by the Project and compensation proposed in ARAP. The Cambodian side and the Team agreed that DPWT will submit results of social monitoring to JICA with PMR by using the monitoring form attached as Annex 9.

In case there is a remaining issue that needs to be addressed (e.g. insufficient restoration of livelihood of PAPs), JICA may request to extend the period of monitoring and reporting until JICA confirms the issues have been properly addressed and solved in accordance with the agreement between PPCA and JICA.

16-4-3 Information Disclosure of Monitoring Results

Both sides confirmed that the Cambodian side will disclose results of environmental

the server

monitoring to local stakeholders through their website / in their field offices. The Cambodian side agreed JICA will disclose results of environmental and social monitoring submitted by the Cambodian side as the monitoring forms attached as Annex 9 on its website.

- 17. Other Relevant Issues
- 17-1. Disclosure of Information

Both sides confirmed that the Preparatory Survey Report from which project cost is excluded will be disclosed to the public after completion of the Preparatory Survey. The comprehensive report including the project cost will be disclosed to the public after all the contracts under the Project are concluded.

17-2. Clearing and Leveling the illegally reclaimed land for developing Access road/Sewer line

Cambodian side explained that the space for basic planned route for Access road/Sewer line has been reclaimed illegally by an individual as shown in Annex 10. Cambodian side explained that PPCA demolish some parts of illegal reclaimed land not for the development of Access road/Sewer line but for tackling flood in rainy season which will start from June, deterioration of canal and odor. The Team recognized the Project has no affection to the demolition because it is implemented as PPCA's own project and requested to make an enough consensus for the demolition with the person and/or entity which implemented illegal reclamation. Cambodian side agreed it.

Both sides confirmed that the demolition is not target on the Guidelines.

#### 17-3. Sludge Management

Both sides confirmed that based on the analysis in the preparatory survey, "Sludge Digestion (Anaerobic Digestion) and Drying by Drying Bed" will be adopted for sludge treatment in the Project. Both sides also confirmed that dewatered sludge after drying will be transported to solid waste disposal sites at the expense of Cambodian side.

17-4. Future necessity of capacity expansion of STP for Cheung Aek Treatment Area In "Sewage Management Master Plan for Phnom Penh Capital City" which was drafted in "The Study on Drainage and Sewerage Improvement Project in Phnom Penh Metropolitan Area" and drafted in 2016, "Cheung Aek Treatment Area", in which wastewater from central area of PPCC is currently discharged to Cheung Aek Lake through existing combined drainage pipes/channels was set-up and "phased

× v × vf

sewerage facility development plan" for the treatment area, which consists of short, medium and long-term, was established to treat expected amount of wastewater (282,000m<sup>3</sup>/day) in 2035.

Both sides agreed to study the future expansion of STP continuously under the mutual cooperation.

17-6. Collaboration and Difference between the Project and JICA's Technical Cooperation Project

JICA's technical cooperation project "The Project for Capacity Development for Sewerage Management of Phnom Penh Capital Administration and Ministry of Public Works and Transport" (hereinafter referred to as "the technical cooperation project") has commenced from April, 2019. The main cooperation of the technical cooperation to DPWT is to strengthen legal and institutional framework mainly through drafting ordinance on sewerage management and structure of new offices/sections for sewerage management.

Both sides confirmed the importance of collaboration between the Project and the technical cooperation project considering difference with Soft Component of the Project.

Annex 1 Project Site

Annex 2 Organization Chart

Annex 3 Project Implementation Schedule

Annex 4 Major Undertakings to be taken by the Government of Cambodia

Annex 5 Project Monitoring Report (template)

Annex 6 Environmental Check List

Annex 7 Environmental Management Plan/Environmental Monitoring Plan

Annex 8 Total cost of ARAP implementation

Annex 9 Environmental and Social Monitoring Form

Annex 10 Illegal reclamation for the site of developing Access Road/Sewer Line

E uf





## **Organization Chart of PPCA**

ORGANIZATION CHART OF PHNOM PENH CAPITAL ADMINISTRATION 2019-201



### **Organization Chart of DPWT**



the cut

### Annex 3

# Timeline for the project implementation

# [Detailed Design and Tendering Stage]

| 110111                             | พี่งหน้า | 1         | 2           | 3  | 4         | 5            | 0  | 7         | 8   | 5 | 10 | 11         | 12 | 10   | 14   |
|------------------------------------|----------|-----------|-------------|--|-----------|--------------|----|-----------|-----|---|----|------------|----|------|------|
| Engagement of Consultant Agreement |          | 7         | ĪT          |  | Π         | ĪT           | Π  | $\square$ |     |   | 11 |            |    |      |      |
| Site Survey                        |          |           | 1           | H  | $\square$ | ┢┼┼          | ++ |           |     |   |    |            |    | +    | H    |
| Analysis and Detail Design         |          | [†        | ╞╧┷         | <b>I</b> ,                                   | +         |              |    |           | ╘╅╴ |   |    | <b>i</b> - |    | +i   | ┝╼┼─ |
| Preparation of Tender Documents    |          |           |             |  |           |              |    |           |     |   |    |            |    |      |      |
| Approval of Tender Documents       |          | $\square$ |             |  |           | <u> -</u>  - | H  |           |     | H |    |            |    | ┤┤   | +    |
| Notification of Proqualification   |          |           |             | <u>                                     </u> | 1         | -            |    |           |     |   |    |            |    | ╌┼╼┨ |      |
| Provision                          |          | $\square$ |             |  | ┢┤╌       |              |    |           | +   | + |    |            |    | +    |      |
| Tendening                          |          | $\square$ | <u> </u>  - |  | $\square$ | ┢┉┼─         |    |           | +   |   | F  | Ħ          |    | +    | -    |
| Evaluation of Tender               |          |           |             | $\vdash$                                     | ┟╌┼╌      | $\mathbb{H}$ |    | •         | +   |   |    |            |    | +    |      |
| Engagement of Contractor Agreement |          |           |             |  |           |              |    |           | Ì   |   |    | ÌÌ         |    | ┥    |      |

[Construction Stage]

|    | Γ       |  | Month |        | 1          | ż  | 3 | 4  | 5        | 6  | 7   | 1         |            | 9       | 10             | 11         | 12        | 13           | 14      | 15           | 16     | 17        | 18 | 19 | 20     | 21               | 22 | 23        | 24 | 25 | 2  | 5 2       | 712           | 8 2  | 913       | 301        | 31         | 32  | 33  | 34          | 35         | 36         | 37           |
|----|---------|--|-------|--------|------------|----|---|----|----------|----|-----|-----------|------------|---------|----------------|------------|-----------|--------------|---------|--------------|--------|-----------|----|----|--------|------------------|----|-----------|----|----|----|-----------|---------------|------|-----------|------------|------------|-----|---|-------------|------------|------------|--------------|
|    | Pre     | paration work  |       | Ţ      |            |    |   |    | Π        | Π  | Π   |           | Ţ          | Π       | Π              | Π          | T         | Π            | Т       |              | :      | Π         | İΤ | Π  | IT     | Π                | İΤ | Π         | Ī  | Π  | T  | 11        |               |      |           | T          | T          | Ť   | T   | T           | T          |            | Ť            |
|    | 8       | Pile and sheet pile works  | 1     | []     |            |    |   |    |          | 11 |     | 11        | 1          |         | 11             |            | ÷,        | 1            |         |              |        |           |    |    |        |                  | İ  | 11        | Î  |    | 11 | 11        | l             |      | ī         |            | 11         | Ħ   |   |             |            | ч.<br>Ц    |              |
|    | selliti | Excavation   |       | Π      | Π          | Π  |   |    | f        | Π  | Π   | 11        | T          | Ħ       | Π              | Ħ          | 11        | Ħ            |         | Н            | T      |           | Ť  |    |        | <u>-</u> +-      | Ħ  | Ħ         | Ħ  | Ħ  | ┢  |           | 1             | +    | ╉         | h          | Ħ          | Ħ   | +   | ++          | mH         | H          | H            |
| ļ  | 1 BA    | Structural works   |       | Π      | Ħ          |    |   | t  | H        | Ħ  | Ħ   | $\dagger$ | t          | H       | ╢              | Ħ          | ╢         |              |         |              |        |           | ╎  | H  | ┢╋╍    | $\left  \right $ | ╟  | ╟         | ╟  | ┢  | H  | Ħ         | Ħ             |      | ╧         | ╂          | $^{++}$    | H   | ╢   |             | ┝┼┦        |            | H            |
|    | Ē       | Backfilling and exterior works   |       | Ħ      | $\dagger$  | Π  | T | Ť  | T        | Ħ  | Ħ   | Π         |            |         |                | Ħ          | $\dagger$ |              | Π       |              |        |           | Ħ  |    | Ħ      | Ħ                | Ħ  | Ħ         | Ħ  | Ħ  | Ħ  | $\dagger$ | T             |      | t         | Ħ          | Ħ          | Ħ   | Ħ   | Ħ           | Ħ          | 11         | H            |
|    | Pag     | Reclamation and embankment   |       | Π      |            | t  |   | -  |          |    | Ì   | 11        | 1          | T       |                | Π          | Ħ         |              |         |              | T      | Ħ         |    | H  |        |                  | Ħ  | Ħ         |    | H  | Ħ  |           | t             |      | ╋         | H          | ╊          | Ħ   | ╢   | Ħ           | +          |            |              |
| ļ  | 14      | Sewer pipe installation  | Į     | Π      | 11         | Π  |   | Į  | T        | T  | Ħ   | Π         | T          | 1       | 11             | Π          |           | 1            |         | -            | T      | Н         | H  |    | H      |                  | Ħ  | Ħ         |    |    | Ħ  | $\dagger$ | $\uparrow$    | +    | $\dagger$ | H          | Ħ          | Ħ   | ╂   | Ħ           | +          | $^{+}$     |              |
| -  | ä       | Pavement and drainage works  |       |        |            |    |   |    |          |    |     |           |            |         |                |            |           |              | !!      |              |        |           |    |    |        |                  |    |           |    |    |    |           |               |      | I         |            | Ìİ         | ÌÌ  | ÌÌ  |             |            | Ìİ         |              |
|    |         | Cofferdam  |       |        |            |    |   |    |          | T  |     | Π         | Τ          | T       | T              | T          |           | Π            | Π       | T            | T      |           |    |    | T      | Ť                |    | Ħ         | Η  | T  |    |           | Π             |      | ╀         | T.         | Ħ          | Ħ   | Ħ   | Ħ           |            |            |              |
| 1  |         | Chaining (pumping out)   |       |        |            |    |   | 1- |          |    | Ϋ́Ψ | ┿┿        | -11<br>444 | 4       | ┝╋             | ļ†<br>μιμι | ††<br>7   |              | 11      |              |        |           |    |    |        |                  |    | -†-       |    |    |    |           | •†••†         |      |           |            |            | ++  |   | ++          |            |            | $\mathbb{H}$ |
|    |         | Dredging (removal of soft soil)  |       |        |            |    | Π | Ī  |          | Ţ  |     |           |            |         |                | Π          | T         |              | Π       | Π            |        |           | T  |    | 1      |                  |    | -         | T  |    | Π  | Ħ         |               | T    | T         | ſ          | Ħ          | Ħ   | 11  | Ħ           | $\ddagger$ | 11         | Ť.           |
| Ę  | ŀ       | Reclamation (1st stage)  |       |        | Π          | ĺ  |   |    |          |    |     |           |            |         |                | Π          | Π         | Π            |         |              | T      |           |    |    |        | T                |    | T         | -  | 1  | I  | ſ         | 11            |      | 1         | ſŤ         | Ħ          | Ħ   | Ħ   | 11          | 11         | $\ddagger$ | Ħ            |
| 15 |         | rkedamaoon (znu stage)   | 1     | гг<br> | 1 I<br>] ] |    |   | 11 | 1        |    | 11  | 11        |            |         |                |            |           | 11           |         | -†-†-<br>] ₹ |        |           |    |    | 11     | 1                |    |           |    |    |    | 11        | $\frac{1}{1}$ | -1-+ |           |            | ++         |     | ++  | ++          | -+-+       | ++         |              |
| ð  |         | Piling for main pump building and SLS  |       |        |            |    |   |    |          |    |     |           |            |         |                |            | 11        |              |         |              |        |           |    |    | 1      |                  |    |           |    |    |    |           |               |      | 1         |            |            |     |   |             |            |            |              |
|    |         | Construction of main pump building and SLS<br>(Underground civil structure)  |       | Π      | Ħ          | Ħ  | Ť | Ť  |          | İ  | Π   | Π         | T          | Ħ       | T              |            |           | <u>+-</u> +- | ╋       | Ħ            | T      |           |    |    | Ħ      |                  | Ť  | Ť         | -  | t  |    | Ħ         | Ħ             | ╋    | Η         |            | ╢          | Ħ   | Ħ   | ť           | Ħ          | ╈          | 1            |
|    |         | Piling for FSF, HTF and digestion facilities                                 |       | 11     |            | 11 | П | П  |          |    |     | 11        | Í          | ÌÌ      | ÌÌ             | İİ.        | ÌÌ        | İİ           | Ìİ      | İİ           | İİ     | II        | Ì  | H  | ∎İ İ   | İ                | ÌÌ | Ì         | jį | Ìİ | İİ | ÌΪ        | İİ            | İİ   | İ         | ıi'        | i i        | ij. | ii  | 11          | 11         | ìÌ         | ii.          |
|    | ß       | Construction of FSF and HTF  |       |        |            | Π  | Π | Π  |          |    | I   |           | Ţ          | Π       |                |            | Ħ         | Π            | Π       | T            |        |           | Ţ  | ŤÌ |        | t                |    |           |    | 1  |    | İŤ        | Ħ             | Ħ    | Ħ         | +          |            | Ħ   | Ħ   | Ħ           | Ħ          | Ħ          |              |
|    | Į       | Construction of chlorination chamber   |       | Π      | Π          | Π  | Π | Π  | T        | T  | Į   | Π         | Π          |         |                |            | Π         | Π            | TT      |              |        |           | Ì  |    |        |                  |    | T         |    | Ť  | -  | Ħ         | Ħ             | Ħ    | ħ         | $\uparrow$ | H          | Ħ   | Ħ   | Ħ           | Ħ          | ++         | 1            |
|    |         | Construction of Sludge drying bed  |       |        |            |    |   |    |          |    |     |           | ÌÌ         |         | Ì              |            | Ĥ         | ÌÌ           | Ì       | ÌÌ           |        | 11        | Ì  | ÌÌ | Ì      | Ì                |    |           | H  |    |    | İİ        | ÌÌ            | İİ   | İ         | Ì          | I          | I   | ii.   | li          | İİ         | ii         | 11           |
|    | i i     | Exterior works for STP site  |       |        | П          | Π  |   | Т  |          | Τ  |     | Π         | Π          | Π       | Π              |            | Π         | Π            | Π       | Π            | Π      | T         | T  | 11 | Π      | Π                | П  | T         | 1  |    |    | H         |               |      | Ħ         |            | T          | Ħ   | Ħ   | Ħ           | ŤŤ         | Ħ          | Ħ            |
|    |         | Construction of main pump building and SLS<br>(Overground building subscure) |       | ļļ     | Ħ          | 11 | Ħ | Π  | Ţ        | 1  | T   | 11        | T          | Π       | Ţ              |            | Ħ         | ļ†           | Ħ       | Ħ            | Ħ      | Ħ         |    |    |        |                  |    | $\dagger$ | +  | Ħ  | H  | Ħ         |               | 1+   | Ħ         | +          | H          | H   | Ħ   | Ħ           | $\dagger$  | #          | H            |
| ŀ  |         | Construction of administration building                                      |       |        | Π          |    | Π | Ϊİ |          | Ť  |     | Í         | Π          | 11      | Π              |            | Π         | Π            | Ħ       | ††           | Ħ      | Π         | Ħ  |    |        |                  |    |           | Ħ  | ÷  |    | H         | Ħ             | Ħ    | Ħ         | $^{+}$     |            | H   | Ħ   | Ħ           | Ħ          | Ħ          | +            |
|    |         | Mechanical works   |       |        |            | Π  | T | Ħ  | Π        |    | T   | IT        | T          | Ħ       | Π              |            | Π         | Ħ            | Ħ       | Ħ            | İ      |           | Ħ  | 11 | ╢      | İ                | Ħ  | t         | 1  |    |    |           |               |      |           | $\dagger$  |            | Ħ   | ╈   | Ħ           | Ħ          | Ħ          | $\dagger$    |
|    |         | Fightrical works   |       | FT.    | I          | Π  | Π | ţ  | 1        |    | Ţ   | ļ         | Ħ          | 11      |                |            | H         |              |         | Ħ            | 11     |           |    |    | 11     | 11               | 11 | Ħ         |    | Η  | t  | 2         |               | H    |           |            | $\uparrow$ | rt  | H   | H           | Ħ          | ₩          | Ħ            |
|    |         | Commissioning and site clearance   |       |        |            |    |   |    |          |    |     |           |            |         |                |            |           |              |         |              |        |           |    |    |        |                  |    |           |    |    |    |           |               |      |           |            | Ш          | Ľ   | Ц   | Ц           | Ц          | Ц          |              |
| 8  |         | Training Staff Engaging in Operation and Maintenance o<br>STP                | 1     | Τ      |            |    | Π |    |          |    | T   | Ħ         | Π          | Ħ       | Π              |            | Ħ         |              | Ħ       |              | Ħ      | $\dagger$ | Ħ  |    | Ħ      | $\dagger$        | Ħ  |           | Ħ  | Ħ  |    | ┢╋        | Ħ             | Ħ    | ļļ        | Ħ          | ⋣          | Ŧ   | <u></u> <u></u> <u></u> <u></u> <u></u> <u></u> <u></u> <u></u> <u></u> <u></u> <u></u> <u></u> <u></u> <u></u> | ⋢           | #          | ⋢          |              |
|    | 5       | Accistance for Formulating Financial Flor for SYP<br>Management              | <br>  |        |            |    |   |    | -+-+<br> |    | i   |           | 11         | +++<br> | <del>1</del> + |            |           |              | ++-<br> |              | ++<br> |           | ++ | ++ | ≁+<br> | ++               |    | ++        | ++ | ++ | +  | +-<br>    | ++<br>        |      | 1+<br>    | +++-<br>   |            | ┥┤┥ | ╞┼╴   | ┝┼┿<br>╋═╬┙ | ┼┼<br>╈╪   | ┿┿         | +√<br>≠∫     |

\* av

# Annex 4

# Major Undertakings to be taken by Recipient Government

# 1) Before the Tender

| NO | Items   | Deadline   | In charge     | Estimated<br>Cost | Ref. |
|----|---|--|---------------|-------------------|------|
| 1  | To open Bank Account (Banking Arrangement (B/A))  | within 1 month<br>after G/A                            | PPCA          |                   |      |
| 2  | To issue A/P to a bank in Japan (the Agent Bank) for the payment to the consultant  | within 1 month<br>after the signing of<br>the contract | PPCA          |                   |      |
| 3  | To approve EIA (Conditions of approval should be fulfilled, if any) and secure<br>the necessary budget for implementation   | By the end of<br>October 2019                          | PPCA          |                   |      |
| 4  | To complete drafting Abbreviated Resettlement Action Plan(ARAP) including compensation policy and obtain confirmation from JICA   | before signing of<br>Grant Agreement                   | PPCA          |                   |      |
| 5  | To obtain Land certificate for STP  | Completed on<br>December 2018                          | PPCA<br>DP.WT |                   |      |
| 6  | To obtain permission of developing Access road/Sewer pipe at reclaimed area   | Completed on<br>December 2018                          | PPCA<br>DPWT  |                   |      |
| 7  | To secure the necessary budget and implement compensation with full<br>replacement cost in accordance with Detail Resettlement Plan (DRP)   | before start of the construction                       | MEF, PPCA     |                   |      |
| 8  | To clear and level the construction site for Access road/Sewer pipe   | before notice of the Tender                            | PPCA          |                   |      |
| 9  | To secure sufficient spaces at the respective Project site/s for temporary facilities such as a contractor's office, workshop, building materials storage, etc. needed for the construction work. | before notice of<br>the Tender                         | РРСА          |                   | -    |
| 10 | To complete the investigation and removal of UXO and Mines in all the construction areas (including sewer installation alignment)   | before notice of the Tender                            | PPCA          |                   |      |

# 2) During the Project

| NO | Items   | Deadline  | In charge | Estimated<br>Cost | Ref. |
|----|---|---|-----------|-------------------|------|
| 1  | To issue A/P to a bank in Japan (the Agent Bank) for the payment to the Supplier(s)   | within 1 month after<br>the signing of the<br>contract(s) | PPCA      |                   |      |
| 2  | To bear the following commissions to a bank of Japan for the banking services based upon the B/A  |   |           |                   |      |
|    | 1) Advising commission of A/P   | within 1 month after<br>the signing of the<br>contract    | PPCA      |                   |      |
|    | 2) Payment commission for A/P   | every payment   | PPCA      |                   |      |
| 3  | To ensure prompt unloading, customs clearance of the products at ports of<br>disembarkation in the recipient country and to assist internal transportation in<br>the country of the Recipient of the products   | during the<br>Project                                     | PPCA      |                   |      |
| 4  | To accord Japanese nationals whose services may be required in connection<br>with the supply of the products and the services under the verified contract such<br>facilities as may be necessary for their entry into the recipient country and stay<br>therein for the performance of their work | during the<br>Project                                     | PPCA      |                   |      |
| 5  | To ensure that customs duties, internal taxes and other fiscal levies which may<br>be imposed in the country of the Recipient with respect to the purchase of the<br>Products and/or the Services be exempted by its designated authority without<br>using the Grant                              | during the<br>Project                                     | PPCA      |                   |      |
| 6  | To bear all the expenses, other than those to be borne by the Japanese Grant,<br>necessary for construction of the facilities as well as for the transportation and<br>installation of the equipment  | during the<br>Project                                     | РРСА      |                   |      |

2 up

| 7  | To provide temporary facilities for the availability or accessibility of electricity, water, etc. for the construction work   | prior to<br>commencement<br>of the<br>construction         | PPCA         |  |
|----|---|--|--------------|--|
| 8  | To provide facilities for distribution of electricity, water supply, drainage and<br>other incidental facilities necessary for the implementation of the Project<br>outside the site(s) |  |              |  |
|    | Electricity     Distribution lines to the site  |  | PPCA         |  |
|    | 2) Water Supply<br>City water distribution main to the site   |  | PPCA         |  |
| 9  | To implement EMP and EMoP   | during the construction                                    | PPCA,<br>DOE |  |
| 10 | To submit results of environmental monitoring to JICA, by using the monitoring form, on a quarterly basis as a part of Project Monitoring Report  | during the construction                                    | PPCA         |  |
| 11 | To implement DRP (livelihood restoration program, if needed)  | for a period based on<br>livelihood<br>restoration program | PPCA         |  |
| 12 | To secure necessary conditions and environments on the site(s) in cooperation<br>with related authorities and local residents<br>(e.g. Security guards, traffic control, etc.)          | during the construction                                    | PPCA         |  |

(EMP: Environmental Management Plan, EMoP: Environmental Monitoring Plan)

### 3) After the Project

| NO | Items  | Deadline                                      | In charge     | Estimated<br>Cost | Ref. |
|----|--|---|---------------|-------------------|------|
| 1  | To implement EMP and EMoP  | for a period based<br>on EMP and<br>EMoP      | PPCA, DOE     |                   |      |
|    | To submit results of environmental monitoring to JICA, by using the monitoring<br>form, semiannually<br>- The period of environmental monitoring may be extended if any significant<br>negative impacts on the environment are found. The extension of environmental<br>monitoring will be decided based on the agreement between PPCA and JICA. | for three years<br>after the Project          | PPCA, DOE     |                   |      |
| 2  | <ul> <li>To maintain and use properly and effectively the facilities constructed and equipment provided under the Grant Aid</li> <li>1) Allocation of maintenance cost</li> <li>2) Operation and maintenance structure</li> <li>3) Routine check/Periodic inspection</li> </ul>  | after<br>completion of<br>the<br>construction | PPCA,<br>DPWT |                   |      |

(B/A: Banking Arrangement, A/P: Authorization to pay, N/A: Not Applicable)

(Note) Progress of the specific obligations of the Recipient may be confirmed and updated from time to time with written agreement between JICA and the Recipient in the form other than the amendment of the G/A.

se a t cup t

# <u>Project Monitoring Report</u> on <u>Project Name</u> Grant Agreement No. <u>XXXXXXX</u>

20XX, Month

# Organizational Information

| <b>Signer of the G/A</b><br>(Recipient) | Person in Charge<br>Contacts | (Designation)<br>Address:<br>Phone/FAX:<br>Email: |
|---|------------------------------|---|
| Executing<br>Agency                     | Person in Charge<br>Contacts | (Designation)<br>Address:<br>Phone/FAX:<br>Email: |
| Line Ministry                           | Person in Charge<br>Contacts | (Designation)<br>Address:<br>Phone/FAX:<br>Email: |

# General Information:

| Project Title     |  |
|-------------------|--|
| E/N               | Signed date:<br>Duration:  |
| G/A               | Signed date:<br>Duration:  |
| Source of Finance | Government of Japan: Not exceeding JPY <u>mil</u><br>Government of (): |

se v fuf

# 1: **Project Description**

## 1-1 Project Objective

### 1-2 Project Rationale

- Higher-level objectives to which the project contributes (national/regional/sectoral policies and strategies)
- Situation of the target groups to which the project addresses

### 1-3 Indicators for measurement of "Effectiveness"

|   |           | <br> |
|---|-----------|------|
|   |           | <br> |
| litative indicators to measure the attainment of project of | viectives | <br> |

# 2: Details of the Project

#### 2-1 Location

| Components | Original<br>(proposed in the outline design) | Actual                                |
|------------|--|---------------------------------------|
| 1.         |  | · · · · · · · · · · · · · · · · · · · |

## 2-2 Scope of the work

| Components | Original*<br>(proposed in the outline design) | Actual* |
|------------|---|---------|
| 1.         |   |         |
|            |   |         |
|            |   |         |
|            |   |         |

Reasons for modification of scope (if any).

(PMR)

### 2-3 Implementation Schedule

|       | Or                               | iginal                                       |        |
|-------|----------------------------------|--|--------|
| Items | (proposed in the outline design) | (at the time of signing the Grant Agreement) | Actual |
|       |                                  |  |        |
|       |                                  |  |        |

Reasons for any changes of the schedule, and their effects on the project (if any)

# 2-4 Obligations by the Recipient

- 2-4-1 Progress of Specific Obligations See Attachment 2.
- 2-4-2 Activities See Attachment 3.
- 2-4-3 Report on RD See Attachment 11.

### 2-5 Project Cost

### 2-5-1 Cost borne by the Grant(Confidential until the Bidding)

|  | Cost   |  |   |        |
|--|--|--|---|--------|
|  | · · · · · · · · · · · · · · · · · · ·        | ·  | (Millior  | n Yen) |
|  | Original<br>(proposed in the outline design) | Actual<br>(in case of any<br>modification) | Original <sup>1),2)</sup><br>(proposed in<br>the outline<br>design) | Actual |
|  | 1.   |  |   |        |
|  |  |  |   |        |
|  | Total  |  |   |        |

Note: 1) Date of estimation: 2) Exchange rate: 1 US Dollar = Yen

### 2-5-2 Cost borne by the Recipient

| Components                                   | Cost                                       |   |        |
|--|--|---|--------|
|  | (1,000 Ta                                  | aka)  |        |
| Original<br>(proposed in the outline design) | Actual<br>(in case of any<br>modification) | Original <sup>1),2)</sup><br>(proposed in<br>the outline<br>design) | Actual |
| 1.   |  |   |        |

J Y N J UJ

Note: 1) Date of estimation:

2) Exchange rate: 1 US Dollar =

Reasons for the remarkable gaps between the original and actual cost, and the countermeasures (if any)

(PMR)

### 2-6 Executing Agency

- Organization's role, financial position, capacity, cost recovery etc,
- Organization Chart including the unit in charge of the implementation and number of employees.

Original (at the time of outline design) name:

role:

financial situation:

institutional and organizational arrangement (organogram): human resources (number and ability of staff):

Actual (PMR)

# 2-7 Environmental and Social Impacts

- The results of environmental monitoring based on Attachment 5 (in accordance with Schedule 4 of the Grant Agreement).

- The results of social monitoring based on in Attachment 5 (in accordance with Schedule 4 of the Grant Agreement).

- Disclosed information related to results of environmental and social monitoring to local stakeholders (whenever applicable).

# 3: Operation and Maintenance (O&M)

## 3-1 Physical Arrangement

- Plan for O&M (number and skills of the staff in the responsible division or section, availability of manuals and guidelines, availability of spareparts, etc.)

Original (at the time of outline design)

Actual (PMR)

### 3-2 Budgetary Arrangement

- Required O&M cost and actual budget allocation for O&M

Original (at the time of outline design)

to cef

# 4: Potential Risks and Mitigation Measures

- Potential risks which may affect the project implementation, attainment of objectives, sustainability
- Mitigation measures corresponding to the potential risks

### Assessment of Potential Risks (at the time of outline design)

| Potential Risks          | Assessment                                       |  |  |  |  |
|--------------------------|--|--|--|--|--|
| 1. (Description of Risk) | Probability: High/Moderate/Low                   |  |  |  |  |
|                          | Impact: High/Moderate/Low                        |  |  |  |  |
|                          | Analysis of Probability and Impact:              |  |  |  |  |
|                          | Mitigation Measures:                             |  |  |  |  |
|                          | Action required during the implementation stage: |  |  |  |  |
|                          | Contingency Plan (if applicable):                |  |  |  |  |
| 2. (Description of Risk) | Probability: High/Moderate/Low                   |  |  |  |  |
|                          | Impact: High/Moderate/Low                        |  |  |  |  |
|                          | Analysis of Probability and Impact:              |  |  |  |  |
|                          | Mitigation Measures:                             |  |  |  |  |
|                          | Action required during the implementation stage: |  |  |  |  |
|                          | Contingency Plan (if applicable):                |  |  |  |  |
| 3. (Description of Risk) | Probability: High/Moderate/Low                   |  |  |  |  |
|                          | Impact: High/Moderate/Low                        |  |  |  |  |
|                          | Analysis of Probability and Impact:              |  |  |  |  |
|                          | Mitigation Measures:                             |  |  |  |  |
|                          | Action required during the implementation stage: |  |  |  |  |
|                          | Contingency Plan (if applicable):                |  |  |  |  |

g uf

Actual Situation and Countermeasures (PMR)

# **5:** Evaluation and Monitoring Plan (after the work completion)

# 5-1 Overall evaluation

Please describe your overall evaluation on the project.

## 5-2 Lessons Learnt and Recommendations

Please raise any lessons learned from the project experience, which might be valuable for the future assistance or similar type of projects, as well as any recommendations, which might be beneficial for better realization of the project effect, impact and assurance of sustainability.

# 5-3 Monitoring Plan of the Indicators for Post-Evaluation

Please describe monitoring methods, section(s)/department(s) in charge of monitoring, frequency, the term to monitor the indicators stipulated in 1-3.

2 up

### Attachment

- 1. Project Location Map
- 2. Specific obligations of the Recipient which will not be funded with the Grant
- 3. Monthly Report submitted by the Consultant

Appendix - Photocopy of Contractor's Progress Report (if any)

- Consultant Member List
- Contractor's Main Staff List
- 4. Check list for the Contract (including Record of Amendment of the Contract/Agreement and Schedule of Payment)
- 5. Environmental Monitoring Form / Social Monitoring Form
- 6. Monitoring sheet on price of specified materials (Quarterly)
- 7. Report on Proportion of Procurement (Recipient Country, Japan and Third Countries) (PMR (final )only)
- 8. Pictures (by JPEG style by CD-R) (PMR (final)only)
- 9. Equipment List (PMR (final )only)
- 10. Drawing (PMR (final )only)
- 11. Report on RD (After project)

1 cm

| σī     | 4      | ယ      | N      |        | E .  |
|--------|--------|--------|--------|--------|--|
| Item 5 | Item 4 | Item 3 | Item 2 | Item 1 | Initial Conditions (Confirmed)<br>Items of Specified Materials   |
|        |        |        |        |        | Monitoring sheet on price of specified materialsAttachment 6Initial VolumeInitial UnitInitial total1% of ContractCondition of paymentAPricePricePricePricePrice (Decreased)BC=A×BDE=C-DF=C+D |
|        |        |        |        |        | fut  |

(2) Result of the Monitoring Survey on Unit Price for each specified materials

|   | σ      | Æ      | co     | ы      | ы      |                              |
|---|--------|--------|--------|--------|--------|------------------------------|
|   | Item 5 | Item 4 | Item 3 | Item 2 | Item 1 | Items of Specified Materials |
|   |        |        |        |        |        | 1st<br>•month, 2015          |
|   |        |        |        |        |        | 2nd<br>Omonth, 2015          |
|   |        |        |        |        |        | •month, 2015                 |
|   |        |        |        |        |        | 4th                          |
|   |        |        |        |        |        | 5th                          |
|   |        |        |        |        |        | 6th                          |
| 2 |        |        |        |        |        |                              |

(3) Summary of Discussion with Contractor (if necessary)

r

ı



| Ð   |    |                     |                     |                      |                             |
|-----|----|---------------------|---------------------|----------------------|-----------------------------|
|     |    | (C/D%)              | (B/D%)              | (A/D%)               | Total                       |
|     |    | (C/D%)              | (B/D%)              | (A/D%)               | Design and Supervision Cost |
|     |    | (C/D%)              | (B/D%)              | (A/D%)               | Equipment Cost              |
|     |    | (C/D%)              | (B/D%)              | (A/D%)               | others                      |
|     |    | (C/D%)              | (B/D%)              | (A/D%)               | Direct Construction<br>Cost |
|     |    | (C/D%)              | (B/D%)              | (A/D%)               | Construction Cost           |
|     |    | Q                   | B                   | A                    |                             |
| 0   | н  | (Third Countries)   | (Japan)             | (Recipient Country)  |                             |
| tal | То | Foreign Procurement | Foreign Procurement | Domestic Procurement |                             |

A4-48



# Annex 6

# **Environmental Check List**

| Category                  | Environmental Item                           | Main Check Items   | Yes: Y<br>No: N                    | Confirmation of Environmental<br>Considerations<br>(Reasons, Mitigation Measures)   |
|---------------------------|--|--|------------------------------------|---|
| 1 Permits and Explanation | (1) EIA and<br>Environmental<br>Permits      | <ul> <li>(a) Have EIA reports been already prepared in official process?</li> <li>(b) Have EIA reports been approved by authorities of the host country's government?</li> <li>(c) Have EIA reports been unconditionally approved? If conditions are imposed on the approval of EIA reports, are the conditions satisfied?</li> <li>(d) In addition to the above approvals, have other required environmental permits been obtained from the appropriate regulatory authorities of the host country's government?</li> </ul> | (a) N<br>(b) N<br>(c) N/A<br>(d) N | (a) EIA document is under preparation by<br>the Project and the environmental permit<br>is expected to be granted in October 2019.<br>(b), (c) & (d) Ditto  |
|                           | (2) Explanation to the<br>Local Stakeholders | <ul> <li>(a) Have contents of the project and the potential impacts been adequately explained to the Local stakeholders based on appropriate procedures, including information disclosure? Is understanding obtained from the Local stakeholders?</li> <li>(b) Have the comment from the stakeholders (such as local residents) been reflected to the project design?</li> </ul>   | (a) Y<br>(b) N                     | <ul> <li>(a) Public consultation meetings were held<br/>from 5 Oct. 2018 to 25 Feb. 2019,<br/>explaining potential impacts.</li> <li>(b) The comments from stakeholders shall<br/>be reflected in the detailed design.</li> </ul>   |
|                           | (3) Examination of<br>Alternatives           | (a) Have alternative plans of the project<br>been examined with social and<br>environmental considerations?  | (a) Y                              | (a) The results of examination of alternatives are shown in the final report.   |
| 2 Pollution Control       | (1) Water Quality                            | <ul> <li>(a) Do pollutants, such as SS, BOD, COD, pH contained in treated effluent from a sewage treatment plant comply with the country's effluent standards?</li> <li>(b) Does untreated water contain heavy metals?"</li> </ul>   | (a) N<br>(b) Y                     | <ul> <li>(a) Some parameters including heavy metals such as mercury exceed the country's effluent standards, but after the treatment it will be within the standard.</li> <li>(b) Heavy metal contamination is expected in untreated water but the concentration of the treated water will be within the standard.</li> </ul> |
|                           | (2) Wastes                                   | (a) Are wastes, such as sludge generated<br>by the facility operations properly treated<br>and disposed of in accordance with the<br>country's standards?  | (a) Y                              | (a) Sludge will be treated at the final damping sites.  |
|                           | (3) Soil Contamination                       | (a) If wastes, such as sludge are suspected<br>to contain heavy metals, are adequate<br>measures taken to prevent contamination<br>of soil and groundwater by leachates from<br>the wastes?  | (a) N                              | (a) Heavy metals in sludge will be dried at<br>the site properly and damped at the final<br>damping sites.  |
|                           | (4) Noise and<br>Vibration                   | (a) Do noise and vibrations generated<br>from the facilities, such as sludge<br>treatment facilities and pumping stations<br>comply with the country's standards?  | (a) Y                              | (a) Potential noise sources above ground<br>will be installed in RC structures. If further<br>reduction is required, necessity of hood<br>silencer and soundproof walls for sound<br>insulation will be considered.   |
|                           | (5) Odor                                     | (a) Are adequate control measures taken<br>for odor sources, such as sludge<br>treatment facilities?   | (a) Y                              | (a) Odor reduction facilities will be designed because the site is next to a residential area.  |
| 3 Natural En              | (1) Protected Areas                          | (a) Is the project site located in protected<br>areas designated by the country's laws or<br>international treaties and conventions? Is<br>there a possibility that the project will<br>affect the protected areas?  | (a) N                              | (a) There is no protected area in or near the Project site.   |
| vironment                 | (2) Ecosystem                                | (a) Does the project site encompass<br>primeval forests, tropical rain forests,<br>ecologically valuable habitats (e.g., coral<br>reefs, mangroves, or tidal flats)?   | (a) N<br>(b) N<br>(c) N<br>(d) N   | <ul> <li>(a) No protected area or valuable<br/>habitats exist in or near the site.</li> <li>(b) &amp;(c) According to the EIA survey, some<br/>endangered species were listed in zone B</li> </ul>  |

Jue b Jue b July uf

|                      |                              | <ul> <li>(b) Does the project site encompass the protected habitats of endangered species designated by the country's laws or international treaties and conventions?</li> <li>(c) If significant ecological impacts are anticipated, are adequate protection measures taken to reduce the impacts on the ecosystem?</li> <li>(d) Is there a possibility that the project will adversely affect aquatic environments, such as rivers? Are adequate measures taken to reduce the impacts on aquatic environments, such as aquatic organisms?</li> </ul>   |   | where relatively far (about 3 km) from the<br>project site. Considering the site<br>environment (e.g. DO is 0.3 mg/l), the<br>endangered species are not inhabit in and<br>around the project site, therefore negative<br>impact to the species by the project is<br>negligible. Furthermore, the environment<br>around the project site will be slightly<br>improved by the project, thus positive<br>impacts will be expected to ecosystem in<br>and around the project site.<br>(d) The objective of the Project is to<br>improve water environment. Although<br>most of the project site will be reclaimed,<br>but as the area of the project is small and<br>present aquatic environments are poor,<br>negative impact is not significant.  |
|----------------------|------------------------------|--|---|--|
| 4 Social Environment | (1) Resettlement             | <ul> <li>(a) Is involuntary resettlement caused by project implementation? If involuntary resettlement is caused, are efforts made to minimize the impacts caused by the resettlement?</li> <li>(b) Is adequate explanation on compensation and resettlement given to affected people prior to resettlement?</li> <li>(c) Is the resettlement plan, including compensation with full replacement costs, restoration of livelihoods and living standards developed based on socioeconomic studies on resettlement?</li> <li>(d) Is the compensations going to be paid prior to the resettlement?</li> <li>(e) Is the compensation policies prepared in document?</li> <li>(f) Does the resettlement plan pay particular attention to vulnerable groups or people, including women, children, the elderly, people below the poverty line, ethnic minorities, and indigenous peoples?</li> <li>(g) Are agreements with the affected people obtained prior to resettlement?</li> <li>(h) Is the organizational framework established to properly implement resettlement? Are the capacity and budget secured to implement the plan?</li> <li>(i) Are any plans developed to monitor the impacts of resettlement?</li> <li>(j) Is the grievance redress mechanism established?</li> </ul> | (a) N<br>(b) N/A<br>(c) N/A<br>(d) N/A<br>(e) N/A<br>(f) N/A<br>(j) N/A<br>(i) N/A<br>(j) Y | <ul> <li>(a), (b), (c), (d), (e), (f), (g), (h) &amp; (i)<br/>Involuntary resettlement is not expected<br/>in the Project.</li> <li>(J) The MEF will facilitate the<br/>establishment of a Municipal Grievance<br/>Redress Committee (MGRC) which will be<br/>responsible for addressing grievances for<br/>the project. The MGRC will be established<br/>by the Municipal Governor in consultation<br/>with the IRC.</li> <li>Any grievances of AHs in connection with<br/>the implementation of the BRP will be<br/>handled through negotiation with the aim<br/>of achieving consensus. Complaints will go<br/>through three stages before they may be<br/>elevated to a court of law as a last resort.</li> <li>GDR/IRC will shoulder all administrative<br/>and legal fees that will be incurred in the<br/>resolution of grievances and complaints.<br/>The handling of the complaint ends in the<br/>MGRC.</li> </ul> |
|                      | (2) Living and<br>Livelihood | <ul> <li>(a) is there a possibility that changes in land uses and water uses due to the project will adversely affect the living conditions of inhabitants?</li> <li>(b) Is there a possibility that the project will adversely affect the living conditions of inhabitants? Are adequate measures considered to reduce the impacts, if necessary?</li> </ul>  | (a) N<br>(b) N/A  | <ul> <li>(a) The Project will contribute to<br/>improvement hygiene and public health.</li> <li>(b) Adverse impacts to inhabitants' livings<br/>are not expected in the Project. Although<br/>their agriculture land will be moved, but<br/>adequate compensation and<br/>relocation/purchase of the land will be<br/>implemented.</li> </ul>  |
|                      | (3) Heritage                 | (a) Is there a possibility that the project<br>will damage the local archeological,<br>historical, cultural, and religious heritage?<br>Are adequate measures considered to<br>protect these sites in accordance with the<br>country's laws?   | (a) N/A   | (a) No cultural heritage exists in or near<br>the Project area.  |
|                      | (4) Landscape                | (a) Is there a possibility that the project<br>will adversely affect the local landscape?<br>Are necessary measures taken?   | (a) N   | (a) Project component will not affect the landscape significantly.   |

2 of

|          | (5) Ethnic Minorities<br>and Indigenous<br>Peoples | (a) Are considerations given to reduce<br>impacts on the culture and lifestyle of<br>ethnic minorities and indigenous peoples?   | (a) N/A<br>(b) N/A               | (a) & (b) No ethnic minorities or<br>indigenous peoples live in or near the<br>Project site.   |
|----------|--|--|----------------------------------|--|
|          | (6) Working<br>Conditions                          | <ul> <li>(a) Is the project proponent not violating any laws and ordinances associated with the working conditions of the country which the project proponent should observe in the project?</li> <li>(b) Are tangible safety considerations in place for individuals involved in the project, such as the installation of safety equipment which prevents industrial accidents, and management of hazardous materials?</li> <li>(c) Are intangible measures being planned and implemented for individuals involved in the project, such as the establishment of a safety and health program, and safety training (including traffic safety and public health) for workers etc.?</li> <li>(d) Are appropriate measures taken to ensure that security guards involved in the project not to violate safety of other individuals involved in the project not to violate safety of other</li> </ul> | (a) Y<br>(b) Y<br>(c) Y<br>(d) Y | (a), (b), (c) & (d) Safety aspects will be fully<br>considered in the detailed design.<br>Additionally, education programs will be<br>carried out by the contractor to improve<br>the workers' awareness of safety and<br>health conditions.   |
| 5 Others | (1) Impacts during<br>Construction                 | <ul> <li>(a) Are adequate measures considered to reduce impacts during construction (e.g., noise, vibrations, turbid water, dust, exhaust gases, and wastes)?</li> <li>(b) If construction activities adversely affect the natural environment (ecosystem), are adequate measures considered to reduce impacts?</li> <li>(c) If construction activities adversely affect the social environment, are adequate measures considered to reduce impacts?</li> <li>(d) If the construction activities might cause traffic congestion, are adequate measures measures?</li> </ul>  | (a) Y<br>(b) N<br>(c) N<br>(d) Y | <ul> <li>(a) They are mentioned in the final report.</li> <li>(b) &amp; (c) The Project will not cause significant adverse impact on natural and social environments. Adequate measures are described in the final report.</li> <li>(d) So far serious impact is not predicted with construction. Information on the construction activities would be disclosed to public through mass-media on a timely basis. Additionally, public consultation with the residents would be held.</li> </ul> |
|          | (2) Monitoring                                     | <ul> <li>(a) Does the proponent develop and<br/>implement monitoring program for the<br/>environmental items that are considered<br/>to have potential impacts?</li> <li>(b) What are the items, methods and<br/>frequencies of the monitoring program?</li> <li>(c) Does the proponent establish an<br/>adequate monitoring framework<br/>(organization, personnel, equipment, and<br/>adequate budget to sustain the<br/>monitoring framework)?</li> <li>(d) Are any regulatory requirements<br/>pertaining to the monitoring report<br/>system identified, such as the format and<br/>frequency of reports from the proponent<br/>to the regulatory authorities?</li> </ul>   | (a) Y<br>(b) -<br>(c) Y<br>(d)Y  | (a), (b), (c) & (d) Preliminary monitoring<br>system has been established and are<br>written in the final report based on JICA<br>Supplemental Study. It will be developed<br>during detail design stage referring<br>comments of MOE.   |
| 6 Note   | Note on Using<br>Environmental<br>Checklist        | (a) If necessary, the impacts to<br>transboundary or global issues should be<br>confirmed (e.g., the project includes<br>factors that may cause problems, such as<br>transboundary waste treatment, acid rain,<br>destruction of the ozone layer, or global<br>warming).   | (a) N/A                          | (a) The impacts to transboundary such as<br>waste is not expected. The project makes<br>positive impact to global warming  |

2 d hg cef

Annex 7

# **Environmental Management Plan**

Based on Environmental Certificate issued by MOE, environmental management and monitoring should be implemented during construction and operation stages.

| No.  | Environmental   | EMP   | Implementing | Responsible | Cost  |
|------|-----------------|---|--------------|-------------|---|
| Cons | truction        |   | agency       | Agency      |   |
| 1.   | Air pollution   | • The contractor will have to educate the   | Contractor   | PPCC/DPWT   | Included in   |
|      | *               | <ul> <li>staff-workers to understand about the sanitation, not to act open defecation and keep waste in the storage.</li> <li>Wet (sprinkle water) the constructing</li> </ul>  |              |             | construction cost.<br>Total estimated<br>cost is \$7,200.                 |
|      |                 | <ul> <li>access road regularly (the dirt road, at least 4 times per day, 7 AM, 11 AM, 1:30 PM and 4 PM that are the busy time) and well cover the soil, sand, rock and cements when transport.</li> <li>Contractor will educate the staff-worker about the risk of fire from the kitchen and welding as well as the fuel storage and</li> </ul>   |              |             |   |
| 2    | Water Pollution | other flammable material.   | Contractor   | DDCCODUUT   | Ter altrada da da   |
| 2.   | Water Pollution | <ul> <li>In the construction phase, the consultants that chosen by the Project will monitor carefully in soil works and concrete works as well as water pumping.</li> <li>The consultant must ensure that the contractor have educated the staff-workers about the sanitation by not to act the open defecation and must keep the waste in the storage which will be built in the temporary accommodation.</li> <li>Contractor must take the strong measure in wastewater management by build the temporary toilet far away from the lake and install the pipe with the depth of 1.5 to 2 m and diameter of 0.5 m as well as collect the solid waste to dump in the safe location without harm to environment.</li> <li>In order to manage the waste efficient, the contractor will have to must up the depth.</li> </ul> | Contractor   | PPCC/DPWT   | Included in<br>construction cost.<br>Total estimated<br>cost is \$13,600. |
|      |                 | <ul> <li>contractor will have to put up the sign in and near the project area in Khmer and English "Do not dump the waste" and so on.</li> <li>Fuel storage must be built according to the technical standard and make sure there is no spilling and leak to the environment.</li> <li>Contractors must follow the sub-degree No. 235 ANK/BK about the management of sewerage system dated on 25th December, 2017.</li> <li>In case that the contractor do not follow the guideline and mitigation measure as described, the consultant must report back to DPWT and JICA to take some of contraction budget for restoring</li> </ul>   |              |             |   |

₩ a/ ₩ Cef

|     |                                   |   |                        | Annex 7               |  |
|-----|-----------------------------------|---|------------------------|-----------------------|--|
| No. | Environmental<br>Items            | EMP   | Implementing<br>agency | Responsible<br>Agency | Cost   |
|     |                                   | environment.  |                        |                       |  |
| 3.  | Soil pollution                    | <ul> <li>Contractors will have to construct the fuel storage according to the national technical standard to ensure no spill or leak into the soil.</li> <li>Furthermore, they must maintain the machinery and generator not to spill or leak the fuel to the soil. The parking lot of</li> </ul>   | Contractor             | PPCC/DPWT             | Included in<br>construction cost   |
|     |                                   | <ul> <li>vehicle and machinery must have the concrete floor.</li> <li>The contractors will have to manage all kind of waste properly: not to pour the old lubricant on the land and keep other waste safe by implementing solid-liquid waste</li> </ul>   |                        |                       |  |
| 4.  | Noise/Vibration                   | <ul> <li>Contractor will use the machinery and vehicle with the exhaust pipe that install a qualified resonator and the generator is the Silent Generator type that cause slight noise and not disturb the neighbor.</li> <li>Contractors will educate the staff-workers not to create loud noise at the rest time and at night.</li> </ul>   | Contractor             | PPCC/DPWT             | Included in<br>construction cost.<br>Total estimated<br>cost is \$4,800. |
| 5.  | Soil Erosion and<br>Slope Failure | <ul> <li>The consultant chosen by JICA will monitor the embankment, canal and spoiled soil dumping to prevent the erosion and ensure that there will be proper grass plantation at all site stated in TOR.</li> <li>The dumping of soil mixed with water from the bottom of the lake will be monitored not to slide into Cheung Aek Lake. Sludge and water taken out will be stored in the pit of 5m x 5m x 2m (width x length x depth) in order to settle sludge and dewater and finally fill back sludge into the pit. Do not dump the mixture of sludge and water into Cheung Aek Lake in/near the project area to prevent pollution.</li> </ul>   | Contractor             | PPCC/DPWT             | Included in<br>construction cost   |
| 6.  | Ecosystem                         | <ul> <li>Monitoring team must ensure that contractors have consulted with the Department of Environment and Ministry of Agriculture, Forestry and Fisheries to educate the staff-workers to love the wildlife and prevent the hunting and trading the wild animal illegally.</li> <li>Contractors must pay high attention in environmental protection by implementing the solid-liquid waste management plan and build the bathroom and toilet, install pipe with 0.5 m of diameter, 1.5 to 2 m depth according to the number of workers not to drain the wastewater to the lake directly or build the toilet on the water.</li> <li>The contractor will have to manage all kind of waste by storing at the safe place</li> </ul> | Contractor             | PPCC/DPWT             | Included in<br>construction cost   |

se a to get

|     |                          |  |  | Annex 7               |   |
|-----|--------------------------|--|--|-----------------------|---|
| No. | Environmental<br>Items   | EMP  | Implementing<br>agency                               | Responsible<br>Agency | Cost  |
|     |                          | <ul> <li>according to the technical standard and<br/>CINTRI which is in charge of collect the<br/>waste to the city landfill.</li> <li>Educate the staff-workers to dump<br/>solid-liquid waste especially fuel and<br/>believe to the staff.</li> </ul>   |  |                       |   |
| 7.  | Resettlement             | <ul> <li>Project has already set the Basic Resettlement Plan (BRP) in 2019. The BRP will be implemented by the MEF as the leader and other relevant Ministry is the member including the DPWT for resolving the effects caused by the project.</li> <li>DPWT will work with ME F to monitor and track the impact on the aquatic crop to ensure that they have restored their living standard better than before the project.</li> <li>No living house will be affected, except one guarding house will be relocated. The project will compensate the structure cost and transportation allowance to the AHs. Other affected secondary structures (fence and awning) and trees also will be compansated. Income restoration program will be established during detail design stage by General Department of Resettlement. Other details are shown in section 1.5</li> </ul> | Inter-ministerial<br>Resettlement<br>Committee (IRC) | MEF                   | Included in<br>preparation cost.<br>The total<br>estimated cost is<br>60,198USD<br>(excluding land<br>cost) |
| 8.  | Employment               | <ul> <li>The monitor team who was chosen by JICA will ensure that the contractors employ the villagers from the local community when they apply for job.</li> <li>Contractors must follow the Labor Law of Kingdom of Cambodia by set work hours per day is 8 hours equal to 46 hours per week (article 137 of Labor Law). If there are works during the holiday or national ceremony day, the employers must provide them the overtime pay and increase 50% for the daytime works and 100% for the nighttime works (article 139 of Labor Law)</li> </ul>  | Contractor   | PPCC/DPWT             | Included in<br>construction cost  |
| 9.  | Water Use                | <ul> <li>Must solve the issue immediately by<br/>install another pipe to replace the old<br/>system and ensure that there is no<br/>problem on the daily water use of the<br/>people.</li> </ul>   | Contractor   | PPCC/DPWT             | Included in construction cost   |
| 10. | Road .                   | <ul> <li>The monitoring team will ensure that the contractors will access the road and use the truck as stated in TOR which has described above.</li> <li>In case that there is the damage of the road by the transportation of construction material, DPWT will be responsible to repair the road.</li> </ul>   | Contractor   | PPCC/DPWT             | Included in construction cost   |
| 11. | Satery and Public Health | <ul> <li>To reduce the impact on health and safety<br/>of the staff-workers and public health and<br/>safety, the contractors must implement the<br/>mitigation measure as following:</li> </ul>   | Contractor   | PPCC/DPWT             | included in construction cost   |

2 v Joy up

|      |                        |  |                        | Annex 7               |   |
|------|------------------------|--|------------------------|-----------------------|---|
| No.  | Environmental<br>Items | ЕМР  | Implementing<br>agency | Responsible<br>Agency | Cost  |
|      |                        | <ul> <li>Educating the staff and workers about both sanitation, self-protection from the social disease, and drinking the sterilized water or fresh water (bottle water).</li> <li>Educate staff and workers about how to protect themselves and prevent the disease in every 6 months.</li> <li>Reserve the medicine to prevent and treat the diseases.</li> <li>Build the toilets with septic tank far from water sources.</li> <li>Access clean water to the temporary accommodation before the staying of staff and worker or start of construction.</li> <li>Construct the first aid room with adequate medicine for treating the injury. This mean, DPWT will implement the safety and risk management plan and the planning for accommodation, health and hygiene of project staff-workers.</li> <li>Cooperate with the local authority to educate the staff-workers no to commit the sex trafficking (human trafficking) and drugs trafficking.</li> </ul>         |                        |                       |   |
| Oper | ation                  |  |                        | I                     |   |
| 1.   | Topography             | <ul> <li>The DPWT, will have to prepare the<br/>machinery to clean the soil that fall into<br/>the waterway and take the soil to store at<br/>the safe place and immediately repair the<br/>damaged part. The place that had fallen<br/>must plant the grass or trees or cover the<br/>mortar, keeping the hole to drain out the<br/>water properly.</li> </ul>  | PPCC/DPWT              | PPCC/DPWT             | Included in<br>operation and<br>maintenance cost.<br>Total cost for<br>erosion protection<br>is \$15,000. |
| 2.   | Water Pollution        | <ul> <li>DPWT, will have the staff trained by JICA to maintain the project and reserve the tool, spare part and budget to repair the faciliteis to run normally treatment process.</li> <li>DPWT cooperate with the laboratory of MOE will check and monitor the surface water quality at 3 locations. Location 1 is on the upstream of intake from Boeung Trabek pumping station with the coordinate X=0491822; Y=1274363. Location 2 is in Cheung Aek Lake downstream of the outlet of treated sewage in Sangkat Chak Angre Krom, Khan Mean Chey, with the coordinate X=0491299; Y=1272570. Location 3 is in Steung Chrov, downstream of the project area, flow into Steung Prek Thnot in Sangkat Deum Mean, Takmao town, Kandal Province with the coordinate X=0493103; Y=1268628. The water quality testing is done at least twice per year, in March (dry season) and September (rainy season) and the data will store in Microsoft Excel for the analysis</li> </ul> | PPCC/DPWT              | PPCC/DPWT             | Included in<br>operation and<br>maintenance cost.<br>Total WQT cost<br>is \$13,500.                       |

Z av Auf

|     | · · · · · ·                 |   |  |                        | Annex 7               |  |
|-----|-----------------------------|---|--|------------------------|-----------------------|--|
| No. | Environmental<br>Items      |   | EMP  | Implementing<br>agency | Responsible<br>Agency | Cost   |
|     |                             | • | purpose in the future.<br>The DPWT will pay closely attention in<br>waste management.<br>DPWT must maintain the treatment<br>system regularly not to delay the process<br>of treatment and have the budget plan for<br>the system maintains.   |                        |                       |  |
| 3.  | Ecosystem                   | • | Pay close attention in the environmental<br>protection. Thus, the staff-workers will<br>not eat or trading these aquatic birds.  | PPCC/DPWT              | PPCC/DPWT             | Included in operation and maintenance cost       |
| 4.  | Water Use                   | • | Pay close attention to managing all kinds<br>of solid-liquid waste including the<br>maintenance of this treatment system, and<br>improve the water quality of Cheung Aek<br>Lake and improve the quality of<br>vegetables planted by locals.   | PPCC/DPWT              | PPCC/DPWT             | Included in<br>operation and<br>maintenance cost |
| 5.  | Safety and<br>Public Health | • | In this phase, the DPWT will follow the<br>waste management plan, and when<br>transporting treated dried sludge via truck<br>must be well cover, do not harm to the<br>environment and society.<br>DPWT will works with local authorities to<br>prevent any accidents for STP operation. | PPCC/DPWT              | PPCC/DPWT             | Included in<br>operation and<br>maintenance cost |

•

-

# Environmental Monitoring Plan

For items that may be negatively impacted, monitoring would be conducted as shown in below.

| Resource         | Monitoring Locations  | Methodology and<br>Parameters   | Monitoring<br>Cycles   | Responsible/<br>implementing<br>Institutions | Monitoring<br>Institutions                             |
|------------------|---|---|------------------------|--|--|
| 1. Project Befor | e Construction Phase  |   |                        |  |  |
| 1.1 Socio-econo  | omy resource  |   |                        |  | -  |
| Resettlement     | - Along the access road   | - The monitoring on   |                        | 1. IRC-WG, IRC                               | 1. MoE   |
|                  | and sewerage  | compensation of   | Once every             | 2. DPWT                                      | 2. MEF   |
|                  | treatment plant   | resettlement and  | 6 months               | 3. Local                                     | 3. DoE   |
|                  | <ul> <li>Prek Takung 1 village</li> </ul>   | grievance redress   | [                      | authorities                                  | 4. DLMUPC  |
| 2. Project Const | ruction Phase   |   |                        |  |  |
| 2.1 Physical res | ource   |   |                        |  |  |
| Topography       | <ul> <li>Building construction<br/>site</li> <li>Access road</li> <li>Protection dike<br/>construction site</li> <li>Spoiled soil dumping<br/>site</li> </ul> | <ul> <li>The monitoring on the topography and the erosion at the infrastructure construction site</li> <li>The monitoring of erosion at the road, protection dike's embankment and spoiled soil dumping site</li> </ul> | Once every<br>6 months | 1. DPWT<br>2. contractor                     | 1. MoE<br>2. DoE<br>3. DoAFF<br>4. Local<br>authority  |
| Hydrology        | <ul> <li>Canal from Boeung<br/>Trabek pumping<br/>station</li> <li>Wastewater way<br/>downstream of the<br/>drainage to Hun</li> </ul>                        | <ul> <li>Monitoring the obstruct<br/>of the flow of pumping<br/>wastewater</li> </ul>   | Once every<br>6 months | 1. DPWT<br>2. contractor                     | 1. MoE<br>2. DoE<br>3. DOWRAM<br>4. Local<br>authority |

se al

| ·                                |  |  | <u> </u>               | Annex  | /  |
|----------------------------------|--|--|------------------------|--|--|
| Resource                         | Monitoring Locations   | Methodology and<br>Parameters  | Monitoring<br>Cycles   | Responsible/<br>implementing<br>Institutions | Monitoring<br>Institutions   |
|                                  | Neana road   | ······································   |                        | Institutions                                 | <u> </u>   |
| Surface water<br>quality         | 3 Sample locations near the<br>project area<br>- Location 1:<br>X=0491822,<br>Y=1274363<br>- Location 2:<br>X=0491299,<br>Y=1272570<br>- Location 3:<br>X=0493103,<br>Y=1268628<br>- Solid-liquid waste<br>storage   | <ul> <li>Monitoring on the water<br/>quality on the<br/>parameters:<br/>temperature; pH;<br/>Turbidity, TDS; TSS;<br/>DO; BOD; COD; SO<sub>4</sub>;<br/>TN; TP; Pb and Total<br/>Coliform</li> <li>Monitoring on<br/>solid-liquid waste<br/>management</li> </ul>              | Once every<br>6 months | 1. DPWT<br>2. contractor                     | 1. MoE<br>2. DoE<br>3. DOWRAM<br>4. Local<br>authority   |
| Soil quality                     | <ul> <li>Infrastructure<br/>construction site,<br/>generator and<br/>machinery storage</li> <li>Temporary shelter of<br/>staff-workers</li> </ul>  | <ul> <li>Monitoring on<br/>solid-liquid waste<br/>management</li> <li>Monitoring on the spill,<br/>leak of fuel on the soil.</li> </ul>  | Once every<br>6 months | 1. DPWT<br>2. contractor                     | <ol> <li>MoE</li> <li>DoE</li> <li>DOWRAM</li> <li>DoAFF</li> <li>Local<br/>authority</li> </ol> |
| Air Quality                      | <ul> <li>Infrastructure<br/>construction site</li> <li>Access road</li> <li>Temporary shelter of<br/>staff-workers</li> <li>2 location of air<br/>quality testing:<br/>location 1 X=0491356,<br/>Y=1272730, location 2<br/>X=0491031,<br/>Y=1272740</li> </ul>                                   | <ul> <li>Monitoring the material transportation on road No. 271</li> <li>Monitoring the odor condition at construction sites</li> <li>Monitoring on air quality parameters: TSP; CO; NO<sub>2</sub>, SO<sub>2</sub>, O<sub>3</sub>, PM10, PM2.5 and H<sub>2</sub>S</li> </ul>  | Once every<br>6 months | 1. DPWT<br>2. contractor                     | 1. MoE<br>2. DoE<br>3. DoT<br>4. Local<br>authority  |
| Noise and<br>vibration           | <ul> <li>Infrastructure<br/>construction site</li> <li>Road construction site<br/>from road No. 271 to<br/>construction site</li> <li>Temporary shelter of<br/>staff-workers</li> <li>Noise and vibration<br/>testing locations are<br/>the same to air quality<br/>testing locations</li> </ul> | <ul> <li>Monitoring on the noise<br/>and vibration from the<br/>material transportation,<br/>the operation of any<br/>machinery, generator and<br/>vehicle.</li> <li>Monitoring on noise and<br/>vibration (Unit: dB)</li> </ul>   | Once every<br>6 months | 1. DPWT<br>2. contractor                     | 1. MoE<br>2. DoE<br>3. DoT<br>4. Local<br>authority  |
| 2.2 Biological r                 | esources   |  | (                      |  |  |
| Ecosystem<br>(Fish)<br>Ecosystem | <ul> <li>Cheung Aek Lake near<br/>project area</li> <li>Temporary shelter of<br/>staff-workers</li> <li>Temporary shelter of</li> </ul>  | <ul> <li>Monitoring on<br/>solid-liquid waste<br/>management</li> <li>Monitoring on the water<br/>quality on the parameters<br/>temperature; pH;<br/>Turbidity, TDS; TSS;<br/>DO; BOD; COD; SO4;<br/>TN; TP; Pb Total<br/>Coliform</li> <li>Monitoring the crime on</li> </ul> | Once every<br>6 months | 1. DPWT<br>2. contractor                     | 1. MoE<br>2. DoE<br>3. DOWRAM<br>4. DoAFF<br>5. Local<br>authority<br>1. MoE                     |
| (Birds)                          | staff-workers  | wildlife especially the aquatic birds  | Once every<br>6 months | 1. DPWT<br>2. contractor                     | 2. DoE<br>3. DoAFF<br>4. Local   |

2 al

|   |  |  |                        | Annex  | 7   |
|---|--|--|------------------------|--|---|
| Resource  | Monitoring Locations   | Methodology and<br>Parameters  | Monitoring<br>Cycles   | Responsible/<br>implementing<br>Institutions | Monitoring<br>Institutions  |
|   |  |  |                        |  | authority   |
| 2.3 Socio-econo<br>Resettlement                                       | omic resources - Resident of AHs loss  | - Monitoring on the  |                        |  | 1 MoE   |
|   | their income in Prek<br>Takung 1 village.<br>- Area of 19.0736 ha for<br>construction and<br>expansion of the STP  | livelihood of AHs loss<br>their income 7 HHs.<br>- Monitoring to ensure<br>that no encroachment to<br>the STP area.  | Once every<br>6 months | 1. DPWT<br>2. Local<br>authority             | 2. MEF<br>3. DoE<br>4. DLMUPC<br>5. DOWRAM  |
| Livelihood,<br>occupations of<br>the local<br>community and<br>gender | <ul> <li>Prek Takung 1 village</li> <li>Temporary shelter of<br/>staff-workers</li> </ul>  | <ul> <li>Monitoring on the<br/>staff-worker selection by<br/>prioritize the locals,<br/>gender equality as well<br/>as the disability</li> <li>Monitoring on work<br/>safety</li> </ul>  | Once every<br>6 months | 1. DPWT<br>2. contractor                     | 1. MoE<br>2. DoE<br>3. DoLVT<br>4. Local<br>authority.  |
| Road  | <ul> <li>Road No. 271, Hun<br/>Sen Road (60m) and<br/>Oknha Hun Neang<br/>Road.</li> <li>Access road</li> </ul>  | <ul> <li>Monitoring on the<br/>transportation (speed and<br/>load)</li> <li>Monitoring on the<br/>parking</li> <li>Monitoring on the repair<br/>the damaged road by the<br/>project</li> </ul>   | Once every<br>3 months | 1. DPWT<br>2. contractor                     | <ol> <li>MoE</li> <li>DoE</li> <li>DPWT</li> <li>Local<br/>authority</li> <li>(local traffic<br/>police)</li> </ol> |
| Public Health<br>and Safety   | <ul> <li>Infrastructure<br/>construction site</li> <li>Generator, vehicle and<br/>machinery storage</li> <li>Temporary shelter of<br/>staff-workers</li> <li>First aid room</li> </ul>   | <ul> <li>Monitoring on<br/>solid-liquid waste<br/>management at<br/>temporary shelter</li> <li>Monitoring the clean<br/>water supply and<br/>sanitation</li> <li>Monitoring the safety<br/>equipment and work<br/>safety</li> <li>Monitoring the first aid<br/>room</li> </ul> | Once every<br>3 months | 1. DPWT<br>2. contractor                     | 1. MoE<br>2. MOT<br>3. DoE<br>4. DoLVT<br>5. DoH<br>6. Local<br>authority   |
| <ol><li>Project Operat</li></ol>                                      | ion Phase  |  |                        |  |   |
| 3.1 Physical Re   | sources  | · · · · · · ·  | r=                     |  |   |
| Surface water<br>quality  | <ul> <li>- 3 Sample locations<br/>near the project area</li> <li>- Location 1:<br/>X=0491822,<br/>Y=1274363</li> <li>- Location 2:<br/>X=0491299,<br/>Y=1272570</li> <li>- Location 3:<br/>X=0493103,<br/>Y=1268628</li> <li>- Solid-liquid waste<br/>storage and filter<br/>system cleaning site</li> </ul> | <ul> <li>Monitoring on the water quality on the parameters: temperature; pH; Turbidity, TDS; TSS; DO; BOD; COD; SO4; TN; TP; Pb and Total Coliform</li> <li>Monitoring on solid-liquid waste management</li> <li>Monitoring the filter system cleaning</li> </ul>              | Once every<br>6 months | 1. DPWT<br>2. contractor                     | 1. MoE<br>2. DoE<br>3. DOWRAM<br>4. Local<br>authority  |
| Air quality   | <ul> <li>Treatment plant, filter<br/>site</li> <li>Sludge storage</li> <li>Solid-liquid waste<br/>storage</li> </ul>   | <ul> <li>Monitoring on<br/>solid-liquid waste<br/>management</li> <li>Monitoring on air quality<br/>parameters: TSP; CO;<br/>NO<sub>2</sub>; SO<sub>2</sub>, <sub>O3</sub>, PM10,</li> </ul>   | Once every<br>6 months | 1. DPWT                                      | 1. MoE<br>2. DoE<br>3. DoT<br>4. Local<br>authority   |

se or f uf

|   |  |  |                        | Annex  | /   |
|---|--|--|------------------------|--|---|
| Resource  | Monitoring Locations   | Methodology and<br>Parameters  | Monitoring<br>Cycles   | Responsible/<br>implementing<br>Institutions | Monitoring<br>Institutions  |
|   |  | PM2.5 and H2S<br>- Monitoring on odor from<br>waste storage and along<br>the access road.  |                        |  |   |
| Noise and<br>vibration  | <ul> <li>Treatment plant, at<br/>mechanic room,<br/>pumping room.</li> </ul>   | <ul> <li>Monitoring on the noise<br/>and vibration from the<br/>operation by measure its<br/>level at the locations<br/>same as air quality<br/>testing locations</li> </ul>   | Once every<br>6 months | 1. DPWT                                      | 1. MoE<br>2. DoE<br>3. DoT<br>4. Local<br>authority                       |
| 3.2 Biological F  | Resources  | ubung rooutons   | I                      | L  |   |
| Ecosystem<br>(Fish)   | - Cheung Aek Lake near<br>the project area   | <ul> <li>Monitoring on the water<br/>quality on the<br/>parameters:<br/>temperature ; pH;<br/>Turbidity, TDS; TSS;<br/>DO; BOD; COD;SO<sub>4</sub> ;<br/>TN; TP; Pb and Total<br/>Coliform</li> <li>Monitoring on<br/>solid-liquid waste<br/>management</li> <li><u>Note:</u> Comparing the<br/>increasing of fish species<br/>near the project area.<br/>Before the project, study<br/>team caught only 6<br/>species.</li> </ul>   | Once every<br>6 months | 1. DPWT                                      | 1. MoE<br>2. DoE<br>3. DOWRAM<br>4. DoAFF<br>5. Local<br>authority        |
| 3.3 Socio-econo   | omic Resources   |  |                        |  |   |
| Resettlement<br>(living<br>standard of<br>affected<br>household<br>monitor) | <ul> <li>Residential of the 7<br/>households who are<br/>affected by project</li> </ul>  | <ul> <li>Monitoring on the living<br/>standard of the people<br/>who get their aquatic<br/>crop by ensure that they<br/>will have a better living<br/>before the project exist</li> </ul>  | Once every<br>6 months | 1. DPWT<br>2. Local authorities              | 1. MoE<br>2. MEF<br>3. DoE<br>4. DLMUPC<br>5. DOWRAM                      |
| Public health<br>and safety   | <ul> <li>Building, the filter<br/>tanks</li> <li>Place with the safety<br/>equipment, fire<br/>extinguisher, safety<br/>System, fire alarm,<br/>etc.)</li> <li>Pipe system</li> <li>Electricity system</li> <li>Solid waste storage</li> <li>Shelter</li> <li>Access road</li> </ul> | <ul> <li>Monitoring on the atmosphere, temperature, and airing.</li> <li>Monitoring on the management and operation of the safety equipment (Fire safety system, fire extinguisher, fire alarm, etc.)</li> <li>Monitoring on solid-liquid waste management</li> <li>Monitoring on the clean water supply and sanitation</li> <li>Monitoring on the durable and safety</li> <li>Monitoring on the provision of safety equipment</li> <li>Monitoring the chloring the chloring the safety</li> </ul> | Once every<br>6 months | 1. DPWT                                      | 1. MoE<br>2. MOT<br>3. DoE<br>4. DoLVT<br>5. DoH<br>6. Local<br>authority |

\* a Fg uf

|          |   |  |                        | Annex  | 7   |
|----------|---|--|------------------------|--|---|
| Resource | Monitoring Locations  | Methodology and<br>Parameters  | Monitoring<br>Cycles   | Responsible/<br>implementing<br>Institutions | Monitoring<br>Institutions  |
|          |   | <ul> <li>Monitoring the medical<br/>facility for first aid</li> </ul>  |                        |  |   |
| Road     | <ul> <li>The intersection of<br/>road No. 271 and<br/>project's road</li> <li>Access road</li> </ul>  | <ul> <li>Monitoring the damage<br/>and repairing the road</li> <li>Monitoring the safety on<br/>access road</li> <li>Monitoring on the<br/>transportation, speed and<br/>traffic congestion</li> <li>Monitoring the<br/>installation of the traffic<br/>sign along the access<br/>road.</li> </ul> | Once every<br>6 months | 1. DPWT<br>2. Contractor                     | 1. MoE<br>2. DoE<br>3. DPWT<br>4. Local<br>authority<br>(traffic police |
| Safety   | <ul> <li>Households and<br/>buildings in project<br/>area</li> <li>Material and fuel<br/>storage</li> <li>Electric cable room or<br/>box</li> <li>Place with the safety<br/>equipment, fire<br/>extinguisher, safety<br/>System, fire alarm,<br/>etc.)</li> </ul> | <ul> <li>Monitoring the electricity system, emergency exit in and outside the building</li> <li>Monitoring the oil and fuel storage</li> <li>Monitoring on the management and operation of the safety equipment (Fire safety system, fire extinguisher, fire alarm etc.)</li> </ul>                | Once every<br>6 months | 1. DPWT<br>2. Relevant<br>company            | 1. MoE<br>2. MoT<br>3. DoE<br>4. DoLVT<br>5. Local<br>authority         |

\* fuf
| No. | ltems                          | Unit           | Quantity | Rate<br>(\$/Unit) | AMOUNT<br>(US\$) |
|-----|--------------------------------|----------------|----------|-------------------|------------------|
| Α   | LAND                           |                |          | ·····             |                  |
| 1   | Flooded land (Agricultural)    | m <sup>2</sup> | 0        | -                 | 0                |
| 2   | Filled up land (Residential)   | m <sup>2</sup> | 0        | -                 | 0                |
| В   | STRUCTURES                     |                |          |                   | 24,281.40        |
| 3   | Guarding house                 | m <sup>2</sup> | 106.20   | 110.00            | 11,682.00        |
| 4   | Bath room                      | m <sup>2</sup> | 7.80     | 115,00            | 897.00           |
| 5   | Shelter                        | m <sup>2</sup> | 73.40    | 25.00             | 1,835.00         |
| 6   | Awning (AW1)                   | m <sup>2</sup> | 36.00    | 15.00             | 540.00           |
| 7   | Awning (AW2)                   | m <sup>2</sup> | 120.80   | 23.00             | 2,778.40         |
| 8   | Brick wall, 100mm              | m <sup>2</sup> | 18.60    | 15.00             | 279.00           |
| 9   | Brick fence, 100mm             | m <sup>2</sup> | 90.00    | 27.00             | 2,430.00         |
| 10  | Brick bund wall, 200mm         | m <sup>2</sup> | 120.00   | 32.00             | 3,840.00         |
| С   | TREES AND FRUIT TREES          |                |          |                   | 1,912.00         |
| 11  | Mango tree                     | tree           | 37       | 51.00             | 1,887.00         |
| 12  | Banana tree                    | tree           | 10       | 2.50              | 25.00            |
| D   | ALLOWANCES                     |                |          |                   | 5,005.20         |
| 13  | Transport Allowance            | AH             | 1        | 150.00            | 150.00           |
| 14  | Income Loss <sup>1</sup>       | person         | 34       | 142.80            | 4,855.20         |
|     | SUBTOTAL                       |                |          |                   | 31,198.60        |
| 15  | Administrative cost            | ls             | -        | -                 | 15,000.00        |
| 16  | External Monitoring            | ls             | -        | -                 | 7,000.00         |
| 17  | Livelihood Restoration Program | ls             | -        | _                 | 7,000.00         |
|     | GRAND TOTAL                    |                |          |                   | 60,198.60        |

2 V Agug

<sup>&</sup>lt;sup>1</sup> The National Poverty Line for Phnom Penh-2013 is 47.60 \$/month/capita. The income loss allowance is calculated based on formula in entitlement matrix: [(MPR) x (Number of members in AH) x 3] • which is equivalent to USD 4,855.20 (34person x 47.60\$ x 3months). ote: -7 AHs (renter) equal to 34 household members.

Note:

<sup>-</sup> MPR instates a Monthly Poverty Rate.

# MONITORING FORM

-If environmental reviews indicate the need of monitoring by JICA, JICA undertakes monitoring for necessary items that are decided by environmental reviews. JICA undertakes monitoring based on regular reports including measured data submitted by the project proponent. When necessary, the project proponent should refer to the following monitoring form for submitting reports.

-When monitoring plans including monitoring items, frequencies and methods are decided, project phase or project life cycle (such as construction phase and operation phase) should be considered.

| Environment<br>al Resource | Monitoring Locations    | Methodology and Parameters | Monitoring<br>Cycles | Responsible/<br>implementing | Monitoring<br>Institutions |
|----------------------------|-------------------------|----------------------------|----------------------|------------------------------|----------------------------|
| 1. Project Be              | fore Construction Phase |                            |                      | mouterio                     |                            |
| 1.1 Socio-eco              | nomy resource           |                            | · · · · · · · · ·    | <u> </u>                     |                            |
| Land use                   | •                       |                            | 1                    |                              |                            |
| and                        |                         |                            |                      |                              |                            |
| Resettlement               |                         |                            |                      |                              |                            |
| 2. Project Co              | nstruction Phase        |                            |                      |                              |                            |
| 2.1 Physical               | resource                |                            |                      |                              |                            |
| Topography                 |                         |                            |                      |                              |                            |
| and erosion                |                         |                            |                      |                              |                            |
| Hydrology                  |                         |                            |                      |                              |                            |
| Surface                    |                         |                            |                      |                              |                            |
| water                      |                         |                            |                      |                              |                            |
| quality                    |                         |                            |                      |                              |                            |
| Soil quality               |                         |                            |                      |                              |                            |
| Air Quality                |                         |                            |                      |                              |                            |
| Noise and                  |                         |                            |                      |                              |                            |
| vibration                  |                         |                            |                      |                              |                            |
| 2.2 Biological             | resources               |                            | -                    |                              |                            |
| Fishes                     |                         |                            |                      |                              |                            |
| Protected                  |                         |                            |                      |                              |                            |
| Area /                     |                         |                            |                      |                              |                            |
| Protected                  |                         |                            |                      |                              |                            |
| Forest                     |                         |                            |                      |                              |                            |
| Forest                     |                         |                            |                      |                              |                            |
| Wildlife                   |                         |                            |                      |                              |                            |
| corridor                   |                         |                            |                      |                              |                            |
| Wildlife                   |                         |                            |                      |                              |                            |
| 2.3 Socio-eco              | nomic resources         |                            |                      |                              |                            |
| Land use                   |                         |                            |                      |                              |                            |
| and                        |                         |                            |                      |                              |                            |
| Resettlement               |                         |                            |                      |                              |                            |
| Livelinood,                |                         |                            |                      |                              |                            |
| of the local               |                         |                            |                      | -                            |                            |
| community                  |                         |                            | 1                    | ĺ                            |                            |
| and gender                 |                         |                            | ļ                    |                              |                            |
| Tradition                  |                         |                            |                      |                              |                            |
| Culture and                |                         | ļ                          |                      |                              |                            |
| Religion                   |                         |                            |                      | Ì                            |                            |

ty up

| Environment<br>al Resource | Monitoring Locations | Methodology and Parameters | Monitoring<br>Cycles | Responsible/<br>implementing<br>Institutions | Monitoring<br>Institutions |
|----------------------------|----------------------|----------------------------|----------------------|--|----------------------------|
| Gender                     |                      |                            |                      |  |                            |
| Water use                  |                      |                            |                      |  |                            |
| Recreation                 |                      |                            |                      |  |                            |
| /Tourism                   |                      |                            |                      |  |                            |
| site                       |                      |                            |                      |  |                            |
| Road and                   |                      |                            |                      |  |                            |
| traffic                    |                      |                            |                      |  |                            |
| Public<br>Uselth and       |                      |                            |                      |  |                            |
| Safety                     |                      |                            |                      |  |                            |
| Aesthetics                 |                      |                            |                      |  |                            |
| and                        |                      |                            |                      | •  |                            |
| landscapes                 |                      |                            |                      |  |                            |
| Risk                       |                      |                            |                      |  |                            |
| 3. Project Or              | veration Phase       |                            |                      |  | L                          |
| 3.1 Physical               | Resources            |                            | <u></u>              |  | <u> </u>                   |
| Topography                 |                      |                            |                      |  |                            |
| and erosion                |                      |                            |                      |  |                            |
| Hydrology                  |                      |                            |                      |  |                            |
| Surface                    |                      |                            |                      |  |                            |
| water                      |                      |                            |                      |  |                            |
| quality                    |                      |                            |                      |  |                            |
| Soil quality               |                      |                            |                      |  |                            |
| Air Quality                |                      |                            |                      |  | ·                          |
| Noise and                  |                      |                            |                      |  |                            |
| vibration                  |                      |                            |                      |  |                            |
| 3.2 Biological             | Resources            |                            |                      |  |                            |
| Fishes                     |                      |                            |                      |  |                            |
| Protected                  |                      |                            |                      |  |                            |
| Area /                     |                      |                            |                      |  |                            |
| Protected                  |                      |                            |                      |  |                            |
| Forest                     |                      |                            |                      |  |                            |
| Forest                     |                      |                            |                      |  |                            |
| Wildlife                   |                      |                            |                      |  |                            |
| corridor                   |                      |                            |                      |  |                            |
| Wildlife                   |                      |                            |                      |  |                            |
| 3.3 Socio-eco              | nomic Resources      | <u> </u>                   | ,,,                  |  |                            |
| Land use                   | ·····                |                            |                      |  |                            |
| and                        |                      |                            |                      |  |                            |
| Resettlemen                |                      |                            |                      |  |                            |
| t                          |                      |                            |                      |  |                            |
| Livelihood,                |                      |                            |                      |  |                            |
| occupations                |                      |                            |                      |  |                            |
| or the local               |                      |                            |                      |  |                            |
| and gender                 |                      |                            |                      |  |                            |
| Tradition                  |                      |                            |                      |  |                            |
| Culture and                |                      |                            |                      |  |                            |
| Religion                   |                      |                            |                      |  |                            |
| Gender                     |                      |                            |                      |  |                            |
| Water use                  |                      |                            |                      |  |                            |
|                            |                      |                            | 1                    | 1  |                            |

er of

.

| Environment<br>al Resource | Monitoring Locations                  | Methodology and Parameters | Monitoring<br>Cycles | Responsible/<br>implementing<br>Institutions | Monitoring<br>Institutions |
|----------------------------|---------------------------------------|----------------------------|----------------------|--|----------------------------|
| Recreation                 | · · · · · · · · · · · · · · · · · · · |                            |                      |  |                            |
| /Tourism                   |                                       |                            |                      |  |                            |
| site                       |                                       |                            |                      |  |                            |
| Road and                   |                                       |                            |                      |  |                            |
| traffic                    |                                       |                            |                      |  |                            |
| Public                     |                                       |                            |                      |  |                            |
| Health and                 |                                       |                            |                      |  |                            |
| Safety                     |                                       |                            |                      |  |                            |
| Aesthetics                 |                                       |                            |                      |  |                            |
| and                        |                                       |                            |                      |  |                            |
| landscapes                 | •                                     |                            |                      |  |                            |
| Risk                       |                                       |                            |                      |  |                            |

t y

•



to the se

# 5. Soft Component (Technical Assistance) Plan

## **Table of Contents**

| 1. Background of Formulation of the Soft Component Plan1            |
|---|
| 1.1 Background of the Project1                                      |
| 1.2 Overall Goal and Project Objective                              |
| 1.3   Basic Concept of the Project                                  |
| 1.4 Necessity of the Soft Component (Technical Assistance)          |
| 1.4.1 Capacity Development in Operation and Maintenance of STP      |
| 1.4.2 Assistance for Formulating Financial Plan for STP Management  |
| 2. Objectives of the Soft Component                                 |
| 3. Output of the Soft Component                                     |
| 3.1 Capacity Development in Operation and Maintenance of STP5       |
| 3.2 Assistance for Formulating Financial Plan for Management of STP |
| 4. Methodology for Confirmation of Achievement                      |
| 5. Activities of the Soft Component                                 |
| 5.1 Capacity Development in Operation and Maintenance of STP        |
| 5.2 Assistance for Formulating Financial Plan for STP Management    |
| 5.3 Inputs for the Soft Component                                   |
| 6. Arrangement and Inputs of Dispatched Experts                     |
| 7. Implementation Schedule of the Soft Component                    |
| 8. Output of Activities of the Soft Component                       |
| 9. Responsibility of Cambodian Side                                 |

# 1. BACKGROUND OF FORMULATION OF THE SOFT COMPONENT PLAN

#### 1.1 Background of the Project

Wastewater generated in Phnom Penh Capital City (hereinafter referred to as "PPCC"), the capital city of the Kingdom of Cambodia, has been increasing mainly due to rapid urbanization and population increase (from approximately 1.0 million in 1998 to 1.5 million in 2008). In general, the wastewater from PPCC is introduced to septic tanks in each household or business establishment. Supernatant liquid from the tanks are discharged to swamps/lakes through drainage pipe/channels and purified by natural purification function to some extent. However, the water environment in PPCC is seriously deteriorated due to the insufficient maintenance of the septic tanks, decrease of natural purification function in the swamps/lakes because of unregulated land reclamation and development. In particular, Cheung Aek Lake, where wastewater is discharged from the project area, decreases its area especially from 2003 to

2015 and thus deterioration of environmental and living condition of the people around the lake is accelerated.

Taking the above conditions into consideration, Japan International Cooperation Agency (hereinafter referred to as JICA), implemented "The Study on Drainage and Sewerage Improvement Project in Phnom Penh Metropolitan Area" from year 2014 to 2016, in response to the official request from the RGC. In this Study, Sewage Management and Drainage Improvement Master Plan (hereinafter referred to as M/P), was formulated for the target year of 2035. In the M/P, Cheung Aek Treatment Area, in which wastewater from central area of PPCC is currently discharged to Cheung Aek through existing combined Lake drainage pipes/channels, is set-up,



Fig1.1 Target Area of This Project

applying off-site sewage treatment. Furthermore, phased implementation plan for the treatment area, which consists of short-term (up to 2020), medium-term (from 2021 to 2030) and long-term (from 2031 to 2040), was established.

This project aims to construct Sewage Treatment Plant (STP) and Sewer (Interceptor), based on the short-term program in the phased implementation plan.

#### 1.2 Overall Goal and Project Objective

#### 1.2.1 Overall Goal

Sewage sector in Cambodia has overall goals/objectives, consisting of national level and capital city level, as described below.

#### (1) National Strategic Development Plan: NSDP

The RGC places top priority on establishing good governance (Fighting Corruption, Legal and Judicial Reforms, Public Administration Reform, Reform of Armed Forces) for national strategy that becomes the foundation of the national development plan. The RGC also set up "Rectangular Strategy", listing the most important issues: "1. Promotion of Agriculture Sector"; "2. Development of Physical Infrastructure"; "3. Private Sector Development and Employment"; and "4. Capacity Building and Human Resources Development".

The RGC announced NSDP 2009-2013 as a development plan based on rectangular strategy in June 2010. In this NSDP 2009-2013, installation and maintenance of sewage/drainage facilities is ranked as priorities in the large cities located along national highway including Phnom Penh. In the latest NSDP 2014-2018, that is also ranked as priorities.

#### (2) City Development Strategy: CDS

PPCC formulated CDS for the target year 2015 based on NSDP in 2005. In order to develop Phnom Penh and to improve civic life, CDS has listed the following five key visions: (1) Land use and housing; (2) Environment and natural resources; (3) Infrastructure and transportation; (4) Social services; and (5) Economic development. Under these 5 visions, there are goals such as "Prevention of water pollution", "Promotion of sewage treatment" and "Improvement of drainage system". Under the key visions, "Prevention of Water Pollution" and "Promotion of Wastewater Treatment" are listed under Vision (2) and "Drainage Improvement" is listed under Vision (3).

#### (3) White Book on Development and Planning of Phnom Penh

PPCC with the support of the French government and the City of Paris formulated the White Book for target year 2020 on the basis of CDS in 2007. Then, PPCC revised it by expanding the target year to 2035. It was approved by the committee for land management and urban planning for the capital which was established by the decree and finally approved by the issuance of sub-decree dated 23rd December 2015.

The White Book suggests plans such as "Development of suburbs and expansion of the capital area to prevent the overconcentration of PPCC", "Promotion of public-private partnerships in the housing and land development" and "Establishment of identity as an aesthetic and environmental city". The Book

also shows the strategy for development policy of sewage/drainage sector and suggests construction of a new sewage treatment plant at Cheung Aek Lake.

#### 1.2.2 Project Objective

The objective of the Project is to minimize water pollution load discharged to Cheung Aek Lake through construction of new sewerage treatment facilities, thereby contributing to protect and improve water environment of the Cheung Aek Lake as well as living and sanitation condition of the people in PPCC.

#### **1.3 Basic Concept of the Project**

The outline of the project is as follows.

Table 1.1Contents of the Request from RGC based on Minutes of Discussion (M/D)

| Components   |   | Detailed content   |
|--|---|--|
| Construction of Sewage Treatment Plant(STP)<br>(including Intake Facilities) | - | Capacity: 5,000m <sup>3</sup> /day<br>Treatment method: Pre-treated Trickling Filtration (PTF) |
| Maintenance Road/Sewer (interceptor) Pipe from Trabek Pumping Station to STP | - | Length: 2,000m<br>Diameter of Sewer Pipe: 500mm  |

Note) As a result of the technical study, pressure pipe is to be installed with 300mm diameter.

#### 1.4 Necessity of the Soft Component (Technical Assistance)

PPCC has so far no experience of sewage management utilizing STP and no staff who has experience in operation and maintenance of STP. Therefore, to guarantee sustainable operation of the STP constructed in this project, it is essential to train the staff of PPCC by implementing soft components in this Project. The soft components are categorised into two components, namely, "Capacity Development in Operation and Maintenance of STP" and "Assistance for Formulating Financial Plan for STP Management".

#### (1) Capacity Development in Operation and Maintenance of STP

As described above, PPCC has so far no experience of sewage management utilizing STP. Therefore, it is necessary to train the staff, aiming to technology transfer and capacity development for operation and maintenance of sewage treatment facilities, including wastewater treatment, sludge treatment, sludge disposal, water quality control and so on. This component also aims to develop comprehensive management skill of STP. For this purpose, basic knowledge of mechanism of wastewater treatment will be lectured and organization development and administration skill will be transferred. Thorough out those activities, DSO staffs will obtain enough capacity to manage STP operation independently.

#### (2) Assistance for Formulating Financial Plan for STP Management

STP regularly requires various costs such as electric power, chemicals, sludge disposal and repairing/replacing equipment. Without the budget to cover the costs, it is impossible to keep operating STP and it is important for DSO to grasp accurate cost of operation and maintenance of the STP. Therefore, the soft component to train staff to obtain knowledge of the budget and

expenditure management for the STP is also implemented.

The required activities for operation and maintenance of STP is illustrated in the following figure. In addition, the soft component includes the training of the staff as responsible officials to consult with the financial departments in PPCC for securing budget for sustainable operation and maintenance of STP.



Figure 1.2 Relations between Contents for STP Management and Activities in Soft Component

#### **1.5** Targeted Personnel for the Soft Component

#### 1.5.1 Capacity Development in Operation and Maintenance of STP

Drainage Pumping Station and Sewage Treatment Plant Office (DSO) will be in charge of operation and maintenance of the STP. Organization chart of DSO is shown in the **Attachment (c)** with the number of staff (breakdown of the number of regular and contracted employee). As shown in the organization chart, only two regular staff in Treatment Plant Team are assigned for operation and maintenance of the

STP, belonging to "Pumping Station, STP and Pond Canal Maintenance Section". In addition, they are at present engaged in maintenance of pumping station and canal, since STP is not in operation in PPCC.

On the other hand, the member requited to operate and maintenance of the constructed facilities in this project is shown in the **Attachment (d)**. The targeted personnels in the soft component are Custodian, Mechanical and /Electrical Engineer and Water Quality Management Engineer, four members in total. The members shall be hired by DPWT before the commencement of the soft component.

#### 1.5.2 Assistance for Formulating Financial Plan for STP Management

Targeted personnels for this soft component are i) one staff of Finance and Planning Office, which is managing the budget of DPWT, ii) one staff of Administration and Personnel Section of DSO. This soft component focuses on transferring knowledge/skills for proper budget and expenditure management. On the other hand, transferring knowledge/skills for public enterprise accounts is not included.

In this soft component, the one staff of Administration and Personnel Section of DSO is in principle trained to have capacity of daily accounting as well as analyzing operational expenditure. On the other hand, the one staff of Finance and Planning Office is trained to have capacity for formulating budget plan of STP.

## 2. OBJECTIVES OF THE SOFT COMPONENT

Objectives to be achieved in the soft component are as follows:

- STP is sustainably operated, maintained and managed, and STP's performance is optimized.
- Sound financial foundation is established for sustainable operation and maintenance of STP.

## **3. OUTPUT OF THE SOFT COMPONENT**

#### 3.1 Capacity Development in Operation and Maintenance of STP

Output of the training, targeting DSO's staff, are as follows.

- DSO can achieve the operation and maintenance skills of STP, including water treatment/sludge treatment/disposal.
- DSO can formulate the maintenance plan by themselves and they can implement maintenance works based on the plan.

#### 3.2 Assistance for Formulating Financial Plan for Management of STP

Output of the assistance, targeting DSO's staff, are as follows.

- DSO can achieve financial planning skills for the manegement of STP.
- DSO can formulate financial report for management of STP by themselves.

## 4. METHODOLOGY FOR CONFIRMATION OF ACHIEVEMENT

Methodology for confirmation of achievement of the soft components is shown in the following table.

| Items   | Point to be checked  | Method for Checking   |
|---|--|---|
|   | - Is the capacity of STP O&M,<br>including O&M for equipment,<br>water monitoring and sludge<br>management of STP, developed?  | <ul> <li>Conducting proficiency test of O&amp;M and<br/>management items for STP.</li> <li>STP O&amp;M plan is established.</li> </ul>  |
| Capacity Development in<br>Operation and<br>Maintenance of STP        | <ul> <li>Is the capacity of STP O&amp;M, based<br/>on the understanding of biological<br/>treatment and countermeasures for<br/>fluctuation of water quality in<br/>operation, developed?</li> </ul> | <ul> <li>Conducting proficiency test for basic knowledge of biological treatment and operation skills of wastewater treatment equipment.</li> <li>Troubleshooting methods of wastewater treatment and suggestions on operation for various case of water quality and sludge conditions will be incorporated on to the standard operational manual delivered by Contractor, to finalize operation manual for STP.</li> </ul> |
|   | - Is the organization for sustainable STP O&M is established?  | • The members shown in the Attachment (d) are hired by DPWT.  |
|   | - Is the capacity to use accounting form for STP developed?  | <ul> <li>Accounting form is established.</li> <li>Conducting proficiency test of accounting form for STP.</li> </ul>  |
| Assistance for formulating<br>financial plan for<br>management of STP | - Are documents related to financial<br>plan and Equipment renewal plan<br>for STP prepared?   | <ul> <li>Annual financial plan for STP operation<br/>and budget plan for maintenance and<br/>renovation of STP are formulated.</li> <li>STP O&amp;M plan and budget plan is<br/>explained by DPWT staff to the sections<br/>in charge of budgetary management in<br/>PPCC (the results are confirmed by the<br/>minutes of meeting).</li> </ul>   |

Table 4.1Methodology for Confirmation of Achievement

## **5.ACTIVITIES OF THE SOFT COMPONENT**

Two (2) Japanese experts, assigned as "STP Operation and Maintenance Expert" and "Financial Planning Expert", shall be dispatched.

The STP Operation and Maintenance Expert shall be in charge of training for systematic operation of the STP. On the other hand, the Financial Planning Expert shall be in charge of assistance of financial management for STP in collaboration with the STP Operation and Maintenance Expert.

#### 5.1 Capacity Development in Operation and Maintenance of STP

One (1) Japanese expert assigned as "STP Operation and Maintenance Expert" shall be dispatched. The expert shall be a specialist in the field of STP operation and maintenance who can provide the targeted personnel with advanced knowledge and technology. In addition, the expert shall have overall management skill to supervise all the activities during implementation of the soft component.

The STP Operation and Maintenance Expert shall train DSO staffs to understand comprehensive operation and maintenance skills, including sludge management (disposal) and water quality management. The expert shall evaluate the skill of staff by conducting proficiency test on the operation and maintenance skills in the each stage of the activities.

Since the STP is facilities introduced in PPCC for the first time, the expert shall pay attention to whether the organization proposed in this project is established and support formulation of STP operation and maintenance plan (annually/monthly) considering smooth operation of the facilities, safety management and environmental aspects, in consultation with the DSO.

#### 5.2 Assistance for Formulating Financial Plan for STP Management

One (1) Japanese expert, assigned as "Financial Planning Expert" shall be dispatched. The expert shall have professional knowledge and skills to train staff on financial planning for smooth and sustainable operation and management of STP.

The Financial Planning Expert shall train i) the one staff of Administration and Personnel Section of DSO to develop the capacity of daily accounting as well as analyzing operational expenditure, and ii) one staff of Finance and Planning Office to develop the capacity for formulating annual budget plan and Equipment renewal plan for STP. It is noted that the two targeted personnel shall participate all the activities to know each other's work contents. At the same time, the expert encourages PPCC to allocate the budget to sustainably operate and maintain the STP.

#### 5.3 Inputs for the Soft Component

Inputs for the soft component is estimated at (i) 2.53 MM for dispatch of "STP Operation and Maintenance Expert", and (ii) 1.34 MM for dispatch of "Financial Planning Expert", totaling 3.87 MM. Details of inputs are as follows.

#### (1) STP Operation and Maintenance Expert: 2.53 MM

The STP Operation and Maintenance Expert shall be dispatched for three times to train staff. The expert shall supervise their works throughout the soft component, and report progress to JICA Cambodia office at the time of arrival and returning. On the completion of the project, the expert shall summarize all the activities of soft component.

#### Major Activities

- 1<sup>st</sup> Term: The Expert shall i) explain overall plan of the project to the participants in DPWT and ii) teach basic knowledge and mechanism of STP which is not limited to classroom but on-site lecture for deeper understanding, and iii) train DSO staffs to formulate work list and organization chart for STP O&M and confirm necessary staffs described in the organization chart.
- 2<sup>nd</sup> Term: The expert shall i) teach sludge and water quality management required for STP O&M, ii) check and monitor the skill of the staff obtained in the Commission Test and iii) support formulation of STP operation and maintenance plan, based on the result of the Commissioning Test
- 3<sup>rd</sup> Term: The Expert shall i) review operational method, which depends on the fluctuation of methodological condition to identify problems to solve and assist DSO staffs to make solutions, ii) finalize STP O&M plan and Operation Manual, based on the operational results in the operation experience through the dry season.

#### Detailed Schedule for STP Operation and Maintenance Expert is shown below.

| D  | ate | 1st Term  | 2nd Term  | 3rd Term  |
|----|-----|---|---|---|
| 1  | Sun |   | Move from Japan to Cambodia   | •   |
| 2  | Mon | <ul> <li>Explanation of overall plan to DPWT and DSO<br/>from 2nd Term to 3rd Term</li> <li>Explanation of activities to JICA Cambodia Of</li> </ul>  | in 1st Term, and activities plan for each term  |   |
| 3  | Tue | <ul> <li>Preparation of training materials (schedule,<br/>textbook and meeting memo with the<br/>Contractor)</li> <li>Explanation of contents of activities in the soft<br/>component to DSO staff</li> </ul> | <ul> <li>Preparation of training materials (check list<br/>for activities on the site and meeting memo with<br/>the Contractor)</li> <li>Explanation of objectives and contents of<br/>activities to DSO staff</li> </ul> | <ul> <li>Preparation of training materials (data<br/>analysis form for activities on the site and<br/>meeting memo with the Contractor)</li> <li>Explanation of objectives and contents of<br/>activities to DSO staff</li> </ul> |
| 4  | Wed | Training on basic of sewage treatment and O&M of STP (principles and objectives)  | Training on O&M items and task responsibility<br>(daily works such as site patrol, operational<br>records and staff arrangement) at the site  | Water sampling and analysis on the water<br>quality of the operations in the dry season   |
| 5  | Thu | Assistance for formulating list of STP O&M items and task responsibilities.   | Training on O&M items and task responsibility<br>(basic of sewage treatment, and principles and<br>objectives of O&M) at the site   | Analysis on the operational data (sludge<br>generation and power consumption) from 2nd<br>term and the subsequent 6 months  |
| 6  | Fri | Confirmation of the list formulated by the DSO<br>staff and follow-up of items insufficiently<br>understood   | Ditto (* Training in the Commissioning Test is<br>conducted in parallel)  | Interview with DSO staff on the O&M activities<br>and analysis on the data collected from 2nd term<br>and the subsequent 6 months   |
| 7  | Sat |   | Holiday   |   |
| 8  | Sun |   | Holiday   |   |
| 9  | Mon | Review of the list formulated in terms of<br>organizational setup and human resources to be<br>secured  | Training on O&M items and task responsibility<br>(water quality management: sampling and<br>handlining of samples) at the site  | Re-training on sludge management (because<br>character of sludge may be different between<br>the starting of the Commissioning Test and the<br>dry season   |
| 10 | Tue | Consultation on the human resources to be secured (if any)  | Training on O&M items and task responsibility<br>(water quality management: analysis and items<br>to be subcontract) at the site  | Ditto   |
| 11 | Wed | Discussion with the Contractor on the contents<br>and schedule of the activities in 2nd Term  | Training on O&M items and task responsibility<br>(sludge management: visit sludge dumping site<br>and confirmation of procedures) at the site   | Study on the issues to sustainably operate and<br>maintain STP, based on the analysis in the<br>preceding week  |
| 12 | Thu | Train the DSO staff at the construction site on<br>the operation of each water treatment equipment<br>to understand the principal and system of<br>wastewater treatment                                       | Training on O&M items and task responsibility<br>(sludge management: input and output of sludge<br>to equipment, handling of dried sludge) at the<br>site   | Implementation of activities, based on the study<br>in the preceding day (for example, consultation<br>with the sludge dumping site and water quality<br>lab)   |
| 13 | Fri | Train the DSO staff at the construction site on<br>the operation of each sludge treatment<br>equipment and water monitoring to understand<br>the STP O&M  | Conducting proficiency test on the O&M skills,<br>based on the activities at the site   |   |
| 14 | Sat |   | Holiday   |   |

Detailed Schedule for STP Operation and Maintenance Expert

| D  | ate | 1st Term   | 2nd Term  | 3rd Term   |
|----|-----|--|---|--|
| 15 | Sun |  | Holiday   |  |
| 16 | Mon | Follow-up of items insufficiently understood in the Commissioning Test   | Training the staff on troubleshooting,<br>considering various situation   | <ul> <li>Analysis on the water monitoring results in the<br/>dry season and feedback those results to the<br/>Operation Manual and STP O&amp;M plan</li> </ul> |
| 17 | Tue | Report to DPWT and DSO and follow-up of<br>securing staff required for the STP O&M   | Assistance for drafting of Operation Manual,<br>which incorporate experience of<br>troubleshooting training   | Conducting proficiency test on operation skills<br>depending on the fluctuation of water quality<br>and follow-up of items insufficiently understood           |
| 18 | Wed | Review of training contents (basic knowledge,<br>task responsibility and activities in the<br>Commissioning Test) and issues in the next<br>term | Conducting proficiency test on the O&M skills,<br>based on the O&M manual and identification of<br>contents not understood                              | Review of the Operation Manual, based on the<br>results of the consultation held in the preceding<br>day   |
| 19 | Thu | Report to JICA Cambodia Office, and move to Japan  | Analysis on the sludge generation and power<br>consumption in the Commissioning Test for<br>formulating STP O&M plan                                    | Analysis on the materials for simple repair,<br>which can be procured in Cambodia  |
| 20 | Fri | Arrival at Japan   | Assistance for formulation of STP O&M plan<br>by the staff of DSO   | Analysis on the TOR for procurement, based on<br>the results in the preceding day  |
| 21 | Sat | -  | Hol   | iday   |
| 22 | Sun | -  | Hol   | iday   |
| 23 | Mon | -  | Assistance for formulation of STP O&M plan  | Assistance for finalization of STP O&M plan  |
| 24 | Tue | -  | Handover the information related to financial<br>plan such as power consumption and amount of<br>sludge disposal, to the "Financial Planning<br>Expert" | Bookbinding and distribution of the Operation<br>Manual and STP O&M plan and explanation to<br>the relevant organizations                                      |
| 25 | Wed | -  | Follow-up of items insufficiently understood in<br>the formulation of STP O&M plan, prepared by<br>DSO  | Preparation of completion report compiling all<br>activities in the soft component   |
| 26 | Thu | -  | Report to DPWT and DSO, as well as review of training results and issues in the next term   | <ul> <li>Preparation of completion report</li> <li>Report to DPWT and DSO</li> </ul>   |
| 27 | Fri | -  | Report to JICA Cambodia Office, and move to Japan   | Report to JICA Cambodia Office, and move to Japan  |
| 28 | Sat | -  | Arrival   | at Japan   |

#### (2) Financial Planning Expert: 1.50 MM

The Financial Planning Expert shall be dispatched for two times to carry out the following works.

#### Major Activities

- 1<sup>st</sup> Term: The Expert shall i) teach the importance of securing budget for operation and maintenance of the STP, ii) create the form of accounting and annual financial report for STP management and train staff to fill out them and iii) review the annual financial report based on the result of the Commission Test.
- 2<sup>nd</sup> Term: The Expert shall i) review the annual financial report based on the operational results in the dry season, especially focusing on the result of power consumption and amount of sludge disposal, ii) follow-up and improve the skill of staff in terms of utilization of accounting form and iii) train staff to compute cost for STP operation and maintenance plan, as well as Equipment renewal plan for STP. and iv) encourage PPCC to allocate budget for the sustainable STP O&M

Detailed Schedule for STP Operation and Maintenance Expert is shown below.

| D  | ate | 1st Term   | 2nd Term  |
|----|-----|--|---|
| 1  | Sun | Move from Jap  | oan to Cambodia   |
| 2  | Mon | <ul> <li>Explanation of overall plan to DPWT and DSO in 1st Ter</li> <li>Explanation of activities to JICA Cambodia Office</li> </ul>  | rm, and activities plan for each term   |
| 3  | Tue | <ul> <li>Explanation of contents of activities in the soft<br/>component to the targeted staff</li> <li>Handover the information related to financial plan such<br/>as power consumption and amount of sludge disposal,<br/>from the "STP Operation and Maintenance Expert"</li> </ul> | <ul> <li>Explanation of contents of activities in the soft<br/>component to the targeted staff</li> <li>Handover the information related to financial plan such<br/>as impact on cost arising from fluctuation of water quality,<br/>from the "STP Operation and Maintenance Expert"</li> </ul> |
| 4  | Wed | Training on basic of financial plan of STP O&M   | Review and updating of accounting form based on the<br>training result and follow-up items insufficiently<br>understood   |
| 5  | Thu | Training on basic of financial plan of STP O&M<br>(continued) and follow-up of items insufficiently<br>understood  | Analysis on the O&M cost based on the operational results<br>in the dry season  |
| 6  | Fri | Training on formulation of accounting form for STP   | Review and update of annual financial plan for STP  |
| 7  | Sat | Но   | liday   |
| 8  | Sun | Но   | liday   |
| 9  | Mon | Follow-up of accounting form for STP prepared by DSO   | Assistance for finalization of annual financial plan for STP  |
| 10 | Tue | Training on formulation of annual financial plan for STP   | Training on formulation of renovation plan for STP  |
| 11 | Wed | Follow-up of annual financial plan for STP, prepared by DPWT   | Assistance for finalization of renovation plan for STP, prepared by DPWT  |
| 12 | Thu | Training on the analysis of the cost obtained in the<br>Commissioning Test   | Ditto   |
| 13 | Fri | Training on updating of annual financial plan for STP  | Analysis and review of activities (including conducting proficiency test)   |
| 14 | Sat | Но   | liday   |
| 15 | Sun | Но   | liday   |
| 16 | Mon | Conducting proficiency test and follow-up of items insufficiently understood   | Assistance for consultation carried out by the DPWT staff<br>with departments in charge of financial matter in PPCC,<br>on the financial plan of STP management   |
| 17 | Tue | Report to and consult with DPWT and DSO about the forecast of O&M cost based on the annual financial plan  | <ul> <li>Feedback of results of consultation held in the preceding<br/>day for the future consultation on the financial issues</li> <li>Preparation of completion report</li> </ul>   |
| 18 | Wed | Analysis on the necessity of updating the annual financial<br>plan based on the consultation held in the preceding day   | Preparation of completion report  |
| 19 | Thu | <ul><li>Review of activities and issues for the next term</li><li>Report to JICA Cambodia Office, and move to Japan</li></ul>  | <ul> <li>Report to DPWT and DSO</li> <li>Report to JICA Cambodia Office, and move to Japan</li> </ul>   |
| 20 | Fri | Arrival at Japan   | Arrival at Japan  |

**Detailed Schedule for STP Operation and Maintenance Expert** 

| Componente  |      |   |     |      | Month |   |   |   |      | Man/  | Month    |
|---|------|---|-----|------|-------|---|---|---|------|-------|----------|
| Components  | 1    | 2 | 3   | 4    | 5     | 6 | 7 | 8 | 9    | Local | Domestic |
| Capacity Development in Operation and<br>Maintenance of STP     | 0.67 |   | 0.9 | 3    |       |   |   |   | 0.93 | 2.53  | 0.00     |
| Assistance for Formulating Financial Plan for<br>STP Management |      |   |     | 0.67 |       |   |   |   | 0.67 | 1.34  | 0.00     |
| Total   |      |   |     |      |       |   |   |   |      | 3.87  | 0.00     |

Figure 5.1

Inputs Plan for the Soft Component

## 6. ARRANGEMENT AND INPUTS OF DISPATCHED EXPERTS

For the implementation of the soft component, experienced Japanese Experts shall be dispatched for the following reasons:

- PPCC has so far no experience of sewage management utilizing STP.
- There are few engineers who can strictly manage the progress of the work based on the planned schedule.
- Special knowledge and experience are required, because the STP constructed in this project applies Japan's unique technology(PTF).

## 7. IMPLEMENTATION SCHEDULE OF THE SOFT COMPONENT

Overall schedule of soft component is shown in the following figure.

|  | 20 202         | 5            |               | 2022       |             |             | 2023        |             |    |
|--|----------------|--------------|---------------|------------|-------------|-------------|-------------|-------------|----|
| Year/Wonth   | 12 1 2 3 4 5 6 | 7 8 9 10 11  | 12 1 2 3      | 4 5 6 7    | 8 9 10 11   | 12 1 2 3    | 4 5 6 7     | 7 8 9 10 1  | 12 |
| Total Months   | 1 2 3 4 5 6 7  | 8 9 10 11 12 | 13 14 15 16 1 | 7 18 19 20 | 21 22 23 24 | 25 26 27 28 | 29 30 31 32 | 33 34 35 36 | 37 |
| Preparatory Work   |                |              |               |            |             |             |             |             |    |
| Cofferdam/Drainage Work  |                |              |               |            |             |             |             |             |    |
| Construction of Maintenance Road   |                |              |               |            |             |             |             |             |    |
| Construction of Intake Facilities  |                |              |               |            |             |             |             |             |    |
| Construction of STP  |                |              |               |            |             |             |             |             |    |
| - Embankment/Civil/Architect Works   |                |              |               |            |             |             |             |             |    |
| - Equipment Fabrication and<br>Transportation  |                |              |               |            |             |             |             |             |    |
| - Mechanic/Electric Works  |                |              |               |            |             |             |             |             |    |
| Commissioning Test   |                |              |               |            |             |             |             |             | _  |
| Soft Component   |                |              |               |            |             |             |             |             |    |
| - Capacity Development in Operation and<br>Maintenance of STP  |                |              |               |            |             |             |             |             |    |
| - Assistance for formulating Plan for STP<br>Management  |                |              |               |            |             |             |             |             |    |
|  |                |              |               |            |             |             |             |             |    |
| Total Months   | 29 30          | 31           | 32            | 33         | 34          | 35          | 36          | 37          |    |
| 1.Capacity Development in Operation and<br>Maintenance of STP  |                |              |               |            |             |             |             |             | 1  |
| <ol> <li>To teach basic knowledge of treatment<br/>through out lecture in class and on-site and<br/>formulate matrix of task responsibility</li> </ol> |                |              |               |            |             |             |             |             |    |
| (2) To teach comprehensive skill for STP O&M,<br>assist to formulate STP O&M plan and<br>monitor the capacity of staff for STP O&M                     |                |              |               |            |             |             |             |             |    |
| (3) To finalize the STP O&M plan and Operation<br>Manual based on the operational results in the<br>dry season   |                |              |               |            |             |             |             |             |    |
| 2.Assistance for Formulating Financial Plan<br>for STP Management  |                |              |               |            |             |             |             |             |    |
| <ol> <li>To assist to formulate accounting form<br/>and annual financial plan for STP</li> </ol>   |                |              |               |            | -           |             |             |             |    |
| (2) To finalize annual financial plan and<br>renovation plan for STP, based on the<br>operational results in the dry season                            |                |              |               |            |             |             |             |             |    |
|  |                |              |               |            |             |             |             |             |    |

Fig.7.1 Implementation Schedule of the Soft Component

## 8. OUTPUT OF ACTIVITIES OF THE SOFT COMPONENT

Outputs of the soft component shall be as follows:

- STP O&M plan, which includes matrix of task responsibility, organaizations to implemete, monthly/annually timeline and manuals of O&M works.
- Operation Manual, which include troubleshooting methods of wastewater treatment and suggestions on operation for various case of water quality and sludge conditions in addition to the standard operational manual delivered by Contractor.
- Results of proficiency test on the training contents in the Commissioning Test implemented by the contoractor.
- Results of proficiency test on the other O&M items such as sludge and water quality management
- Accounting form for STP and results of proficiency test on the understandig of the form
- Annual financial plan (draft) for STP.
- Equipment renewal plan for STP.
- Meeting materials for explanation of Annual financial plan and Equipment renewal plan.
- Completion report for all activities.

## 9. RESPONSIBILITY OF CAMBODIAN SIDE

Responsibility of the Cambodian side for the soft component is enumerated below.

#### (1) Appropriate Planning

DSO shall create STP operation and maintenance plan utilizing knowledge obtained in the soft component. DPWT shall encourage PPCC to secure budget based on the financial plans prepared by the Financial and Planning Office of DPWT.

#### (2) Securing Budget

PPCC shall allocate the budget in accordance with the proposed plan. DPWT shall check the achievement of DSO's works of the proposed plan.

#### (3) Employment of Staff for Sustainable Operation and Maintenance of STP

DSO shall regularly employ young staff as human resources for the next generation. This staff shall be a civil engineer, mechanical/electrical engineer. In addition, water quality management staff shall also be employed for the future provision.

#### (4) Sustainable Capacity Development

DPWT shall assign a supervisor who can supervise all the works to inherit the STP operation and maintenance skills.

#### (5) Establish Reporting/Monitoring System for Sustainable Activities

DPWT shall establish reporting system from DSO to DPWT, as well as monitoring system of DSO to record/update their activities, including formulation of STP operation and maintenance

13

plan sustainably, regularly and voluntarily.

## Attachment



(b) Organization Chart of DPWT (Targeted Section of Soft Component is shown in Red Frame)



#### (c) Organization Chart of DSO (Targeted Section of Soft Component is shown in Red Frame)

| Job                               | No. | Description  |  |
|-----------------------------------|-----|--|--|
| Custodian                         | 1   | Facilities manager   |  |
| Mechanical/Electrical Engineer    | 2   | O&M of sewerage treatment facilities                       |  |
| Water Quality Management Engineer | 1   | Water Quality Sampling, Test and Analysis                  |  |
| Clerical Officer                  | 1   | General Affairs, Public Relations (deal with visitor etc.) |  |
| Worker (Wastewater Treatment)     | 2   | Removal of Scum  |  |
| Worker (Sludge Treatment)         | 4   | Disposal of Sludge and Cleaning of Facilities              |  |
| Total                             | 11  |  |  |
|                                   |     |  |  |
|                                   |     |  |  |

Targeted member of soft component (Operation and Maintenance of STP)

#### (d) Proposed Member of STP O&M constructed in this Project

## 6. References

| Items                                    | JICA Guideline (Environmental  | Environmental Legislation in   | The measure to be   |
|--|--|--|---|
|  | and Social Considerations Required for Intended Projects)  | Cambodia   | held in the current<br>project  |
| 1. Underlying<br>Principles              | <ol> <li>The earliest possible<br/>environmental assessment to<br/>incorporate the<br/>avoidance/minimization /mitigation<br/>of the impact into the project plan.</li> <li>Quantitative and qualitative<br/>analysis covering social and<br/>environment harmonizing economic,<br/>financial, institutional, social and<br/>technical analysis.</li> <li>Provision of alternatives and<br/>mitigation measures in<br/>consideration. EIA report for the<br/>large adverse impact.</li> <li>Organizing a committee of experts<br/>for the particularly large adverse<br/>impacts)</li> </ol> | In Chapter III, in the Law on<br>Environmental Protection and Natural<br>resource Management, 1996 provides;<br>An environmental impact assessment<br>shall be conducted on every project<br>and activity of the private or public,<br>and shall be approved by the Ministry<br>of Environment before being<br>submitted to the Royal Government<br>for decision.<br>The nature and size of the proposed<br>projects and/ or activities (proposed<br>and existing) both private and public,<br>that shall be subject an environmental<br>impact assessment which shall be<br>defined by sub-decree following a<br>proposal of the Ministry of<br>Environment.  | No particular large<br>gap in between.  |
| 2.<br>Examination<br>of Measures         | <ol> <li>Examination of the multiple<br/>alternatives to avoid, minimize<br/>mitigate of the impact.)</li> <li>Preparation of appropriate follow<br/>up plans and systems such as<br/>monitoring plans and environmental<br/>management plans.</li> </ol>  | There is no particular description<br>about alternatives in the<br>Environmental Protection and Natural<br>resource Management, 1996, Sub-<br>decree on Environmental Impact<br>Assessment (EIA) Process 1999 and<br>Declaration on General Guideline for<br>conducting IEIA/EIA Reports 2009.<br>Chapter7 of Anex1 in Declaration on<br>General Guideline for conducting<br>IEIA1/EIA Reports 2009. Includes<br>EMP description including fund and<br>organizational setup, methodologies<br>and monitoring schedule.   | Although contents<br>of the study are<br>similar in both<br>policies, alternative<br>should be provided<br>for considering<br>Master Plan and<br>priority projects.   |
| 3. Scope of<br>Impacts to be<br>Assessed | <ol> <li>Impacts on human health and<br/>safety, as well as on the natural<br/>environment, transmitted through<br/>air, water, soil, waste, accidents,<br/>water usage, climate change,<br/>ecosystems, fauna and flora,<br/>including trans-boundary or global<br/>scale impacts.</li> <li>Examining derivative, secondary,<br/>and cumulative impacts indivisible<br/>from the project.</li> </ol>  | The impacts on human health and<br>safety, as well as on the natural<br>environment which listed in the JICA<br>guideline are generally covered even<br>in the Cambodian system although<br>those categories are slightly different.<br>In the Annex1 in Declaration on<br>General Guideline for conducting<br>IEIA/EIA Reports 2009, required<br>information in the report is described.<br>Those are;<br>Physical Resources: -Soil, Weather,<br>Air quality, Hydrology<br>Biological Resources; Forest, Fauna<br>species, rarely species, endanger<br>species and migration, Habitats,<br>Biodiversity and ecology system, Wet<br>land system, Protected areas, Sensitive<br>environmental area,<br>Socio-economic Resources;<br>Demography and settlement,<br>Economic Status, Land use, Water use. | No particular large<br>gap in between.<br>Although principal<br>ideas such as<br>contents and timing<br>of the<br>environmental study<br>are covered to meet<br>the JICA guideline,<br>SEA application is<br>not described in<br>Cambodian<br>legislation. In the<br>study, encourage<br>relevant<br>organization for the<br>environmental and<br>social consideration<br>at early stage<br>explaining SEA. |

# 6.1 Comparison between JICA Guidelines and Environmental Legislation in Cambodia

| Items   | JICA Guideline (Environmental<br>and Social Considerations Required<br>for Intended Projects)  | Environmental Legislation in<br>Cambodia   | The measure to be<br>held in the current<br>project |
|---|--|--|---|
|   |  | Energy use, Infrastructure system,<br>Education, Public health, Cultural<br>heritages, Historical buildings,<br>Ancient temples, Pagodas,<br>religion/traditions, Ethnic minority or<br>Indigenous people, Tourism area.<br>There is no particular description<br>related Examining derivative,<br>secondary, and cumulative impacts<br>indivisible from the project.  |   |
| 4.Compliance<br>with Laws,<br>Standards,<br>and Plans | <ol> <li>Compliance with Laws, Standards,<br/>Policies and Plans.</li> <li>Avoidance of the protected and<br/>conservation area of natural or<br/>cultural heritage designated by laws<br/>and ordinances.</li> </ol>  | In Protected Areas Law 2008, All<br>clearances and bulldozing within the<br>open land or forestland in protected<br>areas for the purposes of building all<br>types of public infrastructures through<br>the core zone and conservation zone<br>shall be strictly prohibited. (Article<br>36)<br>These activities can only be carried out<br>in the sustainable use zone and<br>community zone with approval from<br>the Royal Government of Cambodia at<br>the request of the Ministry of<br>Environment. (Article 36)<br>Also, in Article 44, To minimize<br>adverse impacts on the environment<br>and to ensure that management<br>objectives of protected areas are<br>satisfied, an Environmental and Social<br>Impact Assessment shall be required<br>on all proposals and investment for<br>development within or adjacent to<br>protected area boundary by the<br>Ministry of Environment with the<br>collaboration from relevant ministries<br>and institutions.<br>The procedures for Environmental and<br>Social Impact Assessment for any<br>projects or activities shall comply with<br>provisions pertaining to the process of<br>Environmental and Social Impact<br>Assessment. | No particular large<br>gap in between.              |
| 5. Social<br>Acceptability                            | <ol> <li>Adequate social coordination for<br/>their acceptance. In case of the large<br/>impact, sufficient consultation with<br/>local stakeholders via information<br/>disclosure at early stage to be<br/>incorporated into project plan.)</li> <li>Consideration of the vulnerable<br/>people</li> </ol> | Public participation is one of the<br>important contents in the EIA report in<br>Annex1 in Declaration on General<br>Guideline for conducting IEIA1/EIA<br>Reports, 2009.  | No particular large<br>gap in between.              |
| 6. Ecosystem<br>and Biota                             | <ol> <li>Avoidance of the degradation of<br/>the natural resource</li> <li>Avoidance of the illegal logging</li> </ol>   | The information related to the impact<br>to the biological features is described<br>in the Declaration, Anex-1, as 4.1.2<br>Biological resources, (Forest: forest<br>land area, forest species and forest<br>classification, Fauna species, rarely<br>species, endanger species and<br>migration, habitats, Biodiversity and   | No particular large<br>gap in between.              |

| Items                         | JICA Guideline (Environmental<br>and Social Considerations Required<br>for Intended Projects)   | Environmental Legislation in<br>Cambodia  | The measure to be<br>held in the current<br>project  |
|-------------------------------|---|---|--|
|                               |   | ecosystem, wetland system (attached with relevant maps).  |  |
| 7.Involuntary<br>Resettlement | <ol> <li>Avoidance and minimization of<br/>the involuntary resettlement</li> <li>Sufficient compensation to PAPs<br/>with timely manner</li> <li>Appropriate participation of PAPs<br/>throughout the planning,<br/>implementation and monitoring of<br/>the RAPs with the appropriate<br/>grievance mechanisms</li> <li>At large scale involuntary<br/>resettlement, advance information<br/>disclosure to the PAPs should be<br/>made with the understandable way<br/>covering the elements in the World<br/>Bank Safeguard Policy, OP 4.12,<br/>Annex A.)</li> </ol> | No particular description about<br>avoidance and minimization of the<br>resettlement in the EIA related<br>legislations such as Law on<br>Environmental Protection and Natural<br>Resource Management 1996, Sub-<br>decree on EIA Process 1999,<br>Declaration on General Guideline for<br>conducting IEIA/EIA Reports 2009.<br>But in February 2018 RGC issued<br>Sub-Decree no. 22 ANK/BK on The<br>Promulgation of the Standard<br>Operating Procedures for Land<br>Acquisition and Involuntary<br>Resettlement for Externally Financed<br>Project in Cambodia. Appendix and 4<br>as Outline Resettlement Framework<br>and Outline Detailed Resettlement<br>Plan, point B the project set out the<br>measures taken to void or minimize<br>resettlement. | No particular large<br>gap in between.<br>However, the living<br>situation for resident<br>in Cambodia are<br>complicated<br>especially in terms<br>of land tenure/use<br>right. Adequate<br>study in later stage<br>should be<br>recommended. |
| 8. Indigenous<br>Peoples      | <ol> <li>Avoidance and minimizing<br/>impacts to indigenous people</li> <li>Respect for Indigenous people's<br/>right obtaining their consent in a<br/>process of free, prior and informed<br/>consultation</li> <li>Adequate measure to the adverse<br/>impact for indigenous people as<br/>Indigenous Peoples Plan with<br/>understandable way covering the<br/>elements of the World Bank<br/>Safeguard Policy, OP4.10, Annex B.</li> </ol>  | Land tenure by community was<br>described in the land law.<br>Also, situation of the indigenous<br>people is should be included in the EIA<br>report as one of the items,<br>"Religion/traditions, ethnic minority<br>or indigenous people", described in the<br>Annex 1 in the Prakas (Declaration) on<br>General Guideline for conducting<br>IEIA1/EIA Reports 2009. In the Sub-<br>Decree no. 22 ANK/BK dated<br>February 2018 also focused on<br>Indigenous Peoples Plan stated in para<br>97.  | No particular large<br>gap in between.<br>However, the living<br>situation for resident<br>in Cambodia are<br>complicated<br>especially in terms<br>of land tenure/use<br>right. Adequate<br>study in later stage<br>should be<br>recommended. |
| 8. Monitoring                 | <ol> <li>Adequate monitoring of the predicted mitigation measures and occurrence of unforeseeable situation.</li> <li>Feasible monitoring plan at planning</li> <li>Available monitoring process to local project stakeholders</li> <li>Resolving problems through an occasion of the discussion and examination in public with the sufficient stakeholder's participation</li> </ol>   | There is no particular description for<br>the implementing monitoring and<br>detail public participation in Law and<br>Sub-decrees refer to the IESA. But, in<br>the sub-decree no. 22 ANK/BK dated<br>February 2018 also have procedure of<br>Monitoring (internal or external) for<br>the implementations of the<br>resettlement plan.<br>The monitoring plan is included in the<br>requirement in environmental<br>management plan in the Annex1 in<br>Declaration on General Guideline for<br>conducting IEIA1/EIA Reports 2009.<br><u>Note:</u> ESIA report will subtract of<br>Resettlement Policies and Grievant<br>Redress from the Resettlement Plan of<br>the Project included total affected<br>households, assets and economic trees.           | No particular large<br>gap in between.<br>Adequate study for<br>developing<br>monitoring works<br>will be<br>recommended.  |

| No | Stake<br>holder   | Comment on the project   | Suggestion  | Solution from the Project   |
|----|---|--|---|---|
| 1  | Administ<br>rative of<br>Phnom<br>Penh<br>Capital<br>City<br>(Project<br>Owner) | <ul> <li>The necessary of this project is to improve the environment in the Phnom Penh Capital City and improve welfare of the people because this sewage treatment plant will use the latest technology from Japan which reduces the stench, water pollution in Choeung Ek Lake. In addition, there are sewage treatment system in Siem Reap and Sihanoukville, but none in Phnom Penh.</li> <li>The total construction cost is about US \$ 35-38 million, including over \$ 5 million worth of concrete entrance to Beoung Salang.</li> <li>Land possession issues in project areas by people are state's public land, which is provided in sub-decree 124 on September 3, 2008 for 520 ha of Choeung Ek Lake. In the project area, there hasn't the sub-division from the royal government yet. However, Administration of PPCC has already request for sub-division of 19 ha of area to develop this project and hope to hear the news soon.</li> <li>The land in the project area has not yet been issuedthe possession. In case of there is complaint with the land owner, Administrative of PPCC will solve this problem. Solving problem is the work of royal government and Administrative of PPCC has experience in this field.</li> <li>The Administrative of PPCC has experience in this field.</li> </ul> | <ul> <li>Build the articulated concrete block to prevent the soil erosion.</li> <li>This treatment system should consider of treating antibiotics that being used in the health sector.</li> <li>The project will open the construction in July 2019, and JICA has already agreed.</li> <li>The lakes in the project area are state public lands, which are governed by sub-decree. Therefore, any possess of the land in this sub-decree is illegal.</li> <li>Please the team follows the JICA guidelines and work quickly and this study shall take great national interest.</li> <li>Please help to improve the water quality and reduce the waterborne diseases for people living there.</li> </ul> | <ul> <li>JICA will design the<br/>embankment and the soil<br/>storage will have the<br/>articulated block and<br/>compress it accordingly to<br/>the techniques of the soil<br/>work and also plant grass to<br/>prevent landslide.</li> <li>This project is the latest<br/>technology from Japan and<br/>we believe that it will help to<br/>treat the toxic substance in<br/>the wastewater.</li> <li>JICA will try to finish this<br/>project design as quick as<br/>possible and open the public<br/>auction then open the<br/>construct as soon as<br/>possible.</li> <li>Administrative of PPCC will<br/>cooperate with Ministry of<br/>Economic and Finance to<br/>solve the land dispute in this<br/>project.</li> <li>ESIA Team will try best and<br/>carefully finish this study as<br/>planned.</li> <li>JICA will design the project<br/>carefully based on technical<br/>standard of Japan and the<br/>treated sewage is based on<br/>standard of Cambodia.</li> </ul> |
| 2  | Relevant<br>Departm<br>ents and<br>Units  | by 13 departments and 2<br>units in total: because it is<br>the needs for development<br>and it is really good to<br>have the project of sewage  | clearly for spreading this<br>information to sub-national<br>level.   | Assessment Team is working<br>hard and focused on detailed<br>study, including outreach to<br>all stakeholders to fully<br>understand the project   |

## 6.2 Summary of Results of the Public Consultation

| No | Stake<br>holder | Comment on the project  | Suggestion  | Solution from the Project   |
|----|-----------------|---|---|---|
|    |                 | <ul> <li>the first project of the state based on the environmental aspect.</li> <li>This project is beneficial to the general public, especially the people near the area.</li> <li>The solid waste collecting service in Phnom Penh is provided regularly by CINTRI at the city center and sub-urban twice a week. If the waste truck broke down, it will cause the service jamming and the waste will remain uncollected.</li> <li>Department of Environment hope that after this treatment plant is executed, the stench will be reduce and hope the citizens will support this project.</li> <li>Hope that citizen will understand this project through the public announcement because they also want the cleanness and dislike the stench.</li> <li>This project is really good because it will also treat the sludge from the treatment tank which make it special because there haven't any companies done like this.</li> <li>Project provided many benefit to biodiversity, fishes, animal and human around the project.</li> <li>This Project will reduce the impact on the water resources.</li> <li>It is really good that the project of sewage treatment plant is developed because it is the first project of the state based on environmental aspect.</li> </ul> | <ul> <li>construction as soon as possible.</li> <li>The project owner, please help to train the human resource of Cambodia on this skill.</li> <li>The size of sewage discharge is greater and the treatment capacity, 5000m3/day which is about 2% of the discharge. Should think of the 100% treatment in the future.</li> <li>Should reserve the area for the expansion later to avoid the needs of land that can be difficult to solve.</li> <li>Build the sewage canal with cover to avoid the stench.</li> <li>Please prevent further land-grabbing in order to reserve the area for expansion this project in the future.</li> <li>The work hour is 8 hours from Monday to Friday in a week.</li> <li>When there are the incidents during works, contractor must compensate to victims.</li> <li>If there is worker complaint or the employers dislike any workers, the contractor or employer must inform legally to department in order to find the problem.</li> <li>Must follow the standard of work and technical stated in work condition regulation.</li> <li>Please nake a proper contract.</li> <li>Please make a proper contract.</li> <li>Please make a proper contract.</li> <li>Please make a proper contract.</li> <li>Please make a proper contract.</li> <li>Please follow the standard of work and technical stated in work condition regulation.</li> <li>Please follow the standard of work and technical stated in work condition regulation.</li> <li>Please make a proper contract.</li> <li>Please don't discriminate the disables. If can, please provide them suitable job.</li> <li>Project owner should discuss with Ministry for the sub-division of area for project construction and plan for the future.</li> <li>All satellite cities must have the drainage and sewage treatment system.</li> </ul> | <ul> <li>complete a project plan<br/>quickly and will be<br/>auctioned publicly and will<br/>open as soon as possible.</li> <li>The project plans to train<br/>Cambodian staff about the<br/>skill in maintain the project<br/>well.</li> <li>The Phnom Penh Capital<br/>City Administration has<br/>collaborated with JICA to<br/>make a master plan for<br/>sewage treatment projects<br/>throughout Phnom Penh. But<br/>there is a shortage of funds<br/>and will try to find the budge<br/>to build it.</li> <li>The government issued Sub-<br/>decree No 168 dated<br/>December 13, 2018 about<br/>the sub-division of Choeung<br/>Ek Lake about 19.0736 ha<br/>that will be used to build this<br/>project and extend it to the<br/>future.</li> <li>JICA has planned to<br/>construct a sewage drainage<br/>pipeline (well covered) into<br/>the treatment plant already.</li> <li>The Capital Hall and Khan<br/>Mean Chey try to prevent<br/>land encroachment into the<br/>land in sub-decree No 123,<br/>which are 520 ha.</li> <li>The Capital Hall and JICA<br/>comply with Cambodia's<br/>labor laws and other<br/>formalities.</li> <li>Administrative of PPCC and<br/>JICA must abide by<br/>Cambodian labor law,<br/>especially the regulations<br/>and labor standards of the<br/>Ministry of Labor and<br/>Vocational Training.</li> <li>Projects will not<br/>discriminate against persons<br/>with disabilities and will<br/>facilitate them a suitable job.</li> <li>The government issued Sub-<br/>decree No 168 dated<br/>December 13, 2018 about<br/>the sub-division of Choeung<br/>Ek Lake about 19.0736 ha<br/>that will be used to build this<br/>project and extend it to the<br/>future.</li> <li>The Phnom Penh Capital<br/>City Administration, in<br/>cooperate with the Ministry</li> </ul> |

| No | Stake<br>holder | Comment on the project  | Suggestion  | Solution from the Project   |
|----|-----------------|---|---|---|
|    |                 | <ul> <li>and Boeung Trabek area<br/>haven't registered in the<br/>system yet.</li> <li>This project doesn't give<br/>the serious impact and if<br/>the project get in the state's<br/>land, it also fine since the<br/>project is the state's<br/>project.</li> <li>This project will help to<br/>raise city's reputation.</li> <li>It is the proud for<br/>Cambodia that the JICA<br/>support both financial and<br/>advance technology.</li> <li>For the water resource,<br/>there is no impact by the<br/>project and only get the<br/>benefit as long as the<br/>construction is safe and<br/>qualify.</li> <li>Project locates in the area<br/>of 520 ha in the sub-degree<br/>No. 124 under<br/>MOWRAM.</li> <li>Appreciate that the JICA's<br/>project in PP are all with<br/>quality.</li> <li>When the sewage is treated<br/>match the standard, then it<br/>will improve the beauty of<br/>city and attract more tourists.</li> <li>This project help promoting<br/>the region's potential<br/>indicators and other region<br/>will treat it as model,<br/>meaning that good areas need<br/>to have a clean city<br/>competition.</li> <li>This project doesn't impact to<br/>city landscape.</li> <li>This kind of project is the<br/>future goal, both financial<br/>and technical.</li> <li>This project will reduce<br/>many impact on environment<br/>both health and ecology.</li> <li>This project is really good<br/>and helps to create job for<br/>engineer, workers and people<br/>and reduce the migration.</li> <li>This project's capacity is<br/>smaller than the wastewater<br/>from whole PP discharge into<br/>Choeung Ek Lake, thus<br/>concern that it will be<br/>unbalanced. However, it<br/>should be fine since this is a<br/>pilot project.</li> </ul> | <ul> <li>New city has the modern<br/>building but the drainage and<br/>sewage treatment system is not<br/>modern, thus, from this hour<br/>onward, if build the building,<br/>please include the sewage<br/>treatment system in order to<br/>improve the city landscape and<br/>reduce the impacts on<br/>environment.</li> <li>Please expand this system in<br/>order to improve the welfare<br/>for citizen and ecosystem.</li> <li>The government, relevant<br/>ministry and department this<br/>water and sanitation, please<br/>continue to work hard on this<br/>sector and find qualify partner<br/>to work with such as JICA.</li> <li>Please, the project owner as<br/>well as JICA trains this skill to<br/>officer and student.</li> <li>In whole PP should have better<br/>solid and liquid waste<br/>management that will improve<br/>the environment and tourism<br/>sector.</li> <li>Please the project owner, after<br/>constructed the project, let the<br/>tourist and student to visit this<br/>treatment plant.</li> <li>If the project impact to poor<br/>family, please compensate them<br/>properly to restore their<br/>livelihood.</li> <li>In general, the area with 700<br/>families must have 1 health<br/>center.</li> <li>If possible, project owner as<br/>well as government should<br/>develop more sewage treatment<br/>system in hospital because the<br/>hospitals in Cambodia don't<br/>this system yet.</li> <li>During the construction of this<br/>sewage treatment system,<br/>please the project owner care<br/>about the workers' health.</li> <li>Nurse should be available in<br/>the construction site for<br/>preparing the eventual<br/>incident.</li> <li>Please build the bathroom<br/>separately for women and men.</li> </ul> | <ul> <li>b) Environment, is working hard to clean up wastewater, especially in the management of sewage drainage and sewage treatment system, in the satellite city, factories where the excess liquid waste must build the treatment plant with ability to reduce water pollution.</li> <li>The Phnom Penh Capital City Administration has cooperated with JICA to draft a master plan for sewage treatment projects throughout Phnom Penh. But there is a shortage of funds and will try to find budget to build it.</li> <li>The project plans to train Cambodian about the skill of the project's maintenance.</li> <li>The Phnom Penh Capital City Administration in collaboration with the Ministry of Environment is working hard to manage waste so that Phnom Penh is a beautiful city for tourism.</li> <li>The Administrative of PPCC will open a student-study program that will be proposed</li> <li>The project has a plan to address the impact on the people, which is the responsibility of the Cambodian government.</li> <li>Government and the Capital Administration are working hard to build a health center for the people of Phnom Penh and also all over Cambodia.</li> <li>The Phnom Penh Capital Administration has cooperated with JICA to draft a Master Plan for sewage Treatment Project in Phnom Penh. But there is a shortage of funds and will try to find budget to build it.</li> <li>Phnom Penh Capital City administration and JICA have high regard for the safety of the principal as well as the temporary accommodation of the project staff as stated in</li> </ul> |

| No | Stake<br>holder | Comment on the project  | Suggestion   | Solution from the Project  |
|----|-----------------|---|--|--|
|    |                 | <ul> <li>In PP, especially Khan Mean<br/>Chey, the waterborne disease<br/>and Lungs diseases cover 2%<br/>only, for Malaria is 0.001%.</li> <li>Before, there are a lot of<br/>communicable diseases that<br/>occur in cycle (5 years cycle).</li> <li>Royal government has the<br/>policy to supply the medical<br/>such as vitamin, vaccine and<br/>deworming twice per year<br/>(once in 6 months) and the<br/>disease rate drop down.</li> <li>In general, infrastructure<br/>especially the drainage<br/>system is not enough yet<br/>which cause the illness and<br/>most illness are occur in the<br/>area with insufficient<br/>infrastructure.</li> <li>Thanks to JICA that support<br/>to Cambodia both financial<br/>and technical to develop this<br/>project and this project is<br/>really important that can raise<br/>awareness of the water usage<br/>and wastewater treatment.</li> <li>This project is good for<br/>agriculture because the<br/>output sewage will not<br/>impact to water usage in<br/>agriculture, can reduce the<br/>pollution of water and not<br/>harmful to farmers who<br/>contact with this water.</li> <li>This project has no impact on<br/>fishery or fish, because there<br/>are no Fishing lots or<br/>conservation areas to<br/>preserve fish breeds in the<br/>area, only Climbing perch,<br/>Common Snakehead, Moon<br/>light gourami, Three spot<br/>gourami and so on.</li> <li>This sewage treatment<br/>system is really good; it is<br/>studies directly by Japan and<br/>also contacts us many times<br/>already.</li> <li>Water Supply Authorities use<br/>around 120-150 liters per<br/>person. In present day, water<br/>supply is 500,000m<sup>3</sup>/day and<br/>in 2024, the supply will<br/>increase to 1,000,000m<sup>3</sup>/day.</li> <li>For this treatment plant, the<br/>water will be taken from<br/>clean water treatment plant<br/>Niroth which equipped with<br/>a 1,400 mm of size of water<br/>pipe under Boeung Trabek</li> </ul> | <ul> <li>Please provide the equity for women and men of the salary for the same work.</li> <li>If the women worker have small children or pregnant, please give them right to off from work early to have time care of their health and children.</li> <li>Please provide women the work.</li> <li>Please provide women the work.</li> <li>Please take care of women and children.</li> <li>Please prevent the impact on people such as noise, odor and dust.</li> <li>Please provide temporary accommodation with good atmosphere.</li> <li>Project owner should spread the information of this development project to citizens.</li> <li>Please cooperate with local authorities to find the solution for the effecting on local people.</li> <li>Please conduct the study clearly about the output sewage to avoid the flood around the project area.</li> <li>The installation of transformer in Boeung Trabek pumping station is not match the standard of EDC that is difficult to maintain and repairs. Thus, the installation of the electrical appliances in this treatment plant shall be follow the standard of EDC and when install them please get the agreement from EDC.</li> <li>When construction, JICA and project owner and JICA tell to contractor to use the sand from the legal investor and cooperate with local authorities to fine the location of sand.</li> </ul> | <ul> <li>Chapters 4, 4.12 and 4.13<br/>above.</li> <li>The JICA Study Team will<br/>install drug box and<br/>coordinate with a nearby<br/>hospital to a backup project<br/>when there is eventual<br/>accident occurs.</li> <li>JICA Study Team will<br/>construct toilets and<br/>bathrooms for women and<br/>men separately, according to<br/>the number of people.</li> <li>The project will respect<br/>equality of gender, such as<br/>equal payment or equal<br/>salary for the same work.</li> <li>Projects respect women's<br/>rights and make it easier for<br/>women to take care of<br/>children.</li> <li>The Administrative of PPCC<br/>and JICA have been paying<br/>great attention to minimizing<br/>environmental and social<br/>impacts in the development<br/>of this project.</li> <li>Phnom Penh Capital City<br/>administration and JICA<br/>have high regard for the<br/>safety of the principal as<br/>well as the temporary<br/>accommodation of the<br/>project staff as stated in<br/>Chapters 4, 4.12 and 4.13<br/>above.</li> <li>Through the ESIA Team, the<br/>meeting to announce project<br/>information and<br/>consultations with all<br/>stakeholders has been done<br/>already.</li> <li>The Ministry of Economy<br/>and Finance and the Phnom<br/>Penh Administration will<br/>solve the effecting on<br/>citizens legally.</li> <li>The JICA has studied and<br/>designed to avoid flooding,<br/>or harming the people<br/>around the project. The<br/>project will have a positive<br/>impact on the surrounding<br/>environment.</li> <li>JICA will work in<br/>collaboration with EDC for<br/>electrical work in<br/>compliance with Cambodia<br/>standards.</li> <li>Construction contractors<br/>will be choose the legal one</li> </ul> |

| No | Stake<br>holder   | Comment on the project   | Suggestion  | Solution from the Project  |
|----|---|--|---|--|
|    |   | <ul> <li>pumping station to Hun<br/>Neang road is about three<br/>kilometers away.</li> <li>10% budget get from the<br/>sewage service in clean water<br/>receipts will be given to<br/>Administrative of PPCC.</li> <li>This project is really good<br/>because the Japanese partner<br/>studied and discuss with us,<br/>EDC, directly many times<br/>already.</li> <li>EDC can supply power to<br/>JICA's needs in medium or<br/>low voltage.</li> <li>JICA has two options. One,<br/>connect from the electricity<br/>network from Boeung Trabek<br/>pumping station that<br/>managed by City Hall. Two,<br/>connect from EDC's network<br/>nearby he project area.</li> <li>The project will pay for<br/>electricity use accordingly to<br/>the use.</li> <li>About mines in project area,<br/>the department does not have<br/>ability to know it availability<br/>unless the Ministry conducts<br/>the exploration research.</li> <li>For sand to fill in project<br/>area, mostly they took it from<br/>other resources from river<br/>and deliver to the project area.</li> <li>Wish that this project will<br/>be successes</li> </ul> |   | and requiring them to have<br>licenses or legal<br>registrations   |
| 3  | Relevant<br>Authoriti<br>es<br>(Khan,<br>Sangkat,<br>Village) | <ul> <li>100% support from Khan<br/>Mean chey, both Sangkats,<br/>and 01 village: Because it is a<br/>requirement for development<br/>and also make people<br/>healthier, free from<br/>waterborne disease.</li> <li>The sewage Treatment<br/>Project is the proud of our<br/>Khan Mean Chey because<br/>this project is the first project<br/>for Phnom Penh, especially<br/>in Khan Mean Chey,<br/>however the impact must be<br/>fairly compensated as<br/>requested.</li> <li>An environmental<br/>improvement project that will<br/>make the region gain more<br/>economic potential in the<br/>future.</li> <li>In the project area, the local<br/>authority (Khan, sangkat) is<br/>not aware of the names of the</li> </ul>   | <ul> <li>For this project, it should<br/>work with local authorities<br/>to resolve land-use activities<br/>for the people. But the<br/>impact on the people is only<br/>little.</li> <li>Project owners please find<br/>appropriate solutions for the<br/>people affected by the<br/>project.</li> <li>Please help address the<br/>impact if there is an impact<br/>on residents in Sangkat Chak<br/>Angre Krom.</li> <li>Please implement the project<br/>with quality and technical<br/>standards.</li> <li>Should build treatment plant<br/>with capacity to treat all<br/>wastewater because it affects<br/>Choeung Ek Lake.</li> <li>The project will reduce<br/>offensive odor.</li> </ul> | <ul> <li>Project owner and JICA are cooperating with all levels of authorities and units in addressing the challenges in order to develop this project smoothly.</li> <li>The Ministry of Economy and Finance and the Phnom Penh Administration will address the impact of Cambodia's citizens legally.</li> <li>The project owner has technical advisers that JICA is recruiting for planning and supervising the construction of the project in accordance with Japanese technical standards.</li> <li>The Phnom Penh Capital Administration has cooperated with JICA to draft a Master Plan for sewage Treatment Project in Phnom Penh. But there is a</li> </ul> |

| No | Stake<br>holder   | Comment on the project   | Suggestion   | Solution from the Project   |
|----|---|--|--|---|
|    |   | <ul> <li>landowners because they<br/>only buy and sell themselves.<br/>To the north of the<br/>construction site, we know<br/>that there is Oknha Louk<br/>Hour possessed the land there<br/>through the construction of<br/>concrete wall and plantation.</li> <li>This project will be able to<br/>reduce diseases caused by<br/>contaminated water for<br/>people there.</li> <li>Sewage is bad water that<br/>makes the crops that people<br/>plant in this area are of poor<br/>quality. When the project<br/>runs it will improve the<br/>water, leading to the quality<br/>of crop increase and<br/>customers will buy it more<br/>with higher price.</li> <li>This project will make people<br/>healthier, free from diseases<br/>caused by water, and the<br/>authorities will cooperate<br/>well to develop country like<br/>other countries.</li> <li>People in Khan Mean Chey<br/>support this project.</li> <li>The wastewater flowing into<br/>the Choeung Ek Lake today<br/>affects the health of the<br/>people living in this area and</li> </ul> |  | shortage of funds and will<br>try to find budget to build it.   |
| 4  | Affected<br>families<br>(on<br>crops)<br>and<br>People<br>near the<br>project<br>area | <ul> <li>Affect crop have six<br/>household and interviewed<br/>the representative of the<br/>families' heads, 100%<br/>because it is a need for<br/>development, and hopefully<br/>there will be a sewage<br/>treatment system with<br/>modern technology, and<br/>reduce the pollution of the<br/>environment.</li> <li>Concern about this project<br/>won't compensate for<br/>affected people.</li> <li>This project is hoped to clean<br/>the lake better than before.</li> <li>The dirty water that flows<br/>into Choeung Ek Lake today<br/>affects the health of people<br/>living in Prek Takung 1<br/>village because the children<br/>bathe it even the elder told<br/>not to.</li> <li>Hopefully, this project<br/>reduces diseases due to direct<br/>exposure to contaminated</li> </ul>  | <ul> <li>Please solve the problem of affecting the crop for people.</li> <li>Please compensate directly to the affected people such as effected on crop, and so on</li> <li>Please monitor and maintain the project properly after constructed.</li> </ul> | <ul> <li>The Ministry of Economy and<br/>Finance and the Phnom Penh<br/>Administration will address<br/>the impact of Cambodia's<br/>citizens legally.</li> <li>The project owner has<br/>technical advisers that JICA<br/>is recruiting for planning<br/>and supervising the<br/>construction of the project in<br/>accordance with Japanese<br/>technical standards.</li> </ul> |

| No | Stake<br>holder | Comment on the project  | Suggestion | Solution from the Project |
|----|-----------------|---|------------|---------------------------|
|    |                 | <ul> <li>water because many people depend on aquatic crops.</li> <li>Hopefully, this project will help to improve water quality and increase the numbers of fishes in the lake and safe for eating. The fish that fished out from the lake are not really good.</li> <li>There are concerns that floods will affect the lives of people, animals, houses, and crops of the people near the project site.</li> </ul> |            |                           |

| No | JICA Guideline/ WB OP<br>4.12   | Cambodian Legislation  | Gap  | Measures Taken for the<br>Project   |
|----|---|--|--|---|
| 1  | Involuntary resettlement<br>and loss of means of<br>livelihood are to be<br>avoided when feasible by<br>exploring all viable<br>alternatives.   | According to "Circular on<br>the Resettlement<br>Implementation Procedure<br>for Development Projects,<br>No. 006 MEF, 2016",<br>possibility of avoidance of<br>resettlement shall be<br>studied in feasibility study.   | No Gap   | In accordance to JICA<br>Guidelines and WB OP<br>4.12, project design shall<br>be considered to avoid/<br>mitigate land acquisition<br>and resettlement.  |
| 2  | People who must be<br>resettled involuntarily and<br>people whose means of<br>livelihood will be hindered<br>or lost must be sufficiently<br>compensated and<br>supported, so that they can<br>improve or at least restore<br>their standard of living,<br>income opportunities and<br>production levels to pre-<br>project levels. | Above circular indicates to<br>minimize impact; however<br>actual procedures have not<br>been developed.<br>Concession of public land<br>is indicated; however, it<br>will not be sufficient due to<br>limitation of area of land,<br>usage, etc.  | No significant gap, but<br>actual procedures are<br>unclear.                           | In accordance to JICA<br>Guidelines and WB OP<br>4.12, project design shall<br>be considered to avoid/<br>mitigate land acquisition<br>and resettlement. If not<br>avoided/ mitigated,<br>assistance shall be<br>provided to the PAPs to<br>improve or restore their<br>livelihood to at least pre-<br>project level. |
| 3  | People who must be<br>resettled involuntarily and<br>people whose means of<br>livelihood will be hindered<br>or lost must be sufficiently<br>compensated and<br>supported, so that they can<br>improve or at least restore<br>their standard of living,<br>income opportunities and<br>production levels to pre-<br>project levels. | According to the Circular<br>No. 2 Illegal Holding of<br>State Land 2007, illegal<br>state land holders are not<br>entitled for compensation<br>but may receive<br>preferential treatment in<br>obtaining appropriate size<br>of land for making their<br>livelihood based on their<br>actual situation.<br>However actual procedures<br>have not been issued. | No significant gap, but<br>actual procedures are<br>unclear.                           | In accordance to JICA<br>Guidelines and WB OP<br>4.12, assistance shall be<br>provided to the PAPs to<br>minimize impact and to<br>improve or restore their<br>livelihood to at least pre-<br>project level.  |
| 4  | Compensation must be<br>based on the full<br>replacement cost as much<br>as possible.   | Land Acquisition Law<br>indicates to secure fair and<br>appropriate compensation<br>before resettlement in the<br>article 2.   | No actual estimation<br>method for<br>compensation to secure<br>full replacement cost. | In accordance to JICA<br>Guidelines and WB OP<br>4.12, full replacement cost<br>shall be given as much as<br>possible.  |
| 5  | Compensation and other<br>kinds of assistance must be<br>provided prior to<br>displacement.   | According to the Law on<br>Expropriation 2010,<br>expropriation of the<br>ownership of immovable<br>property can be exercised<br>only if the Expropriation<br>Committee has paid fair<br>and just compensation to<br>the property's owner in<br>advance.   | No gap   | In accordance to JICA<br>Guidelines and WB OP<br>4.12, it is encouraged<br>Cambodian side to give<br>compensation and supports<br>to the PAPs in advance.   |
| 6  | For projects that entail<br>large-scale involuntary<br>resettlement, resettlement<br>action plans must be<br>prepared and made<br>available to the public. It is<br>desirable that the<br>resettlement action plan<br>include elements laid out in  | SOPs indicates procedure<br>of information disclosure.<br>While some items to be<br>surveyed in the ARAP may<br>not meet JICA<br>requirements (e.g.full-scale<br>census survey, calculation<br>of replacement cost)  | No significant gap, but<br>actual procedures are<br>unclear.                           | In accordance to JICA<br>Guidelines and WB OP<br>4.12, it is encourage<br>Cambodian side to open<br>information public, and<br>also JICA WEB site is used<br>for public disclosure.   |

# 6.3 Policy Gap Analysis between the JICA Environmental Guidelines and Cambodia's Country System (Land Acquisition and Resettlement)

| No | JICA Guideline/ WB OP<br>4.12   | Cambodian Legislation  | Gap  | Measures Taken for the<br>Project   |
|----|---|--|--|---|
|    | the World Bank Safeguard<br>Policy, OP 4.12, Annex A.   |  |  |   |
| 7  | In preparing a resettlement<br>action plan, consultations<br>must be held with the<br>affected people and their<br>communities based on<br>sufficient information<br>made available to them in<br>advance. When<br>consultations are held,<br>explanations must be given<br>in a form, manner, and<br>language that are<br>understandable to the<br>affected people | It is indicated that IRC is<br>responsible to organize a<br>public forum with relevant<br>organization to disclose<br>project description,<br>resettlement policy, etc.<br>In addition, Land<br>Acquisition Law issues to<br>conduct public<br>consultation. | No significant gap, but<br>actual procedures are<br>unclear. | In accordance to JICA<br>Guidelines and WB OP<br>4.12, public consultation<br>would be held.<br>Special consideration with<br>social profile,<br>organizations of PAPs shall<br>be given when invitees are<br>selected. |
| 8  | Appropriate participation<br>of affected people must be<br>promoted in planning,<br>implementation, and<br>monitoring of resettlement<br>action plans.  | Sub-Decree on Social Land<br>Concessions, 2003<br>indicates that commune<br>council shall lead to make<br>a plan, and encourage<br>public participation.<br>While public participation<br>is not legal requirement.  | Public participation<br>will be voluntary basis.             | In accordance to JICA<br>Guidelines and WB OP<br>4.12, public participation<br>shall be encouraged.   |
| 9  | Appropriate and accessible<br>grievance mechanisms<br>must be established for the<br>affected people and their<br>communities.  | Land Acquisition Law<br>issues to establish<br>Grievance Committee;<br>however Actual procedure<br>for grievance mechanisms<br>has not been set.   | No significant gap, but<br>actual procedures are<br>unclear. | In accordance to JICA<br>Guidelines and WB OP<br>4.12, it is encouraged<br>Cambodian site to establish<br>accessible grievance<br>mechanisms.   |
### 6.4 Monitoring Form

6.4.1 EIA

# MONITORING FORM

-If environmental reviews indicate the need of monitoring by JICA, JICA undertakes monitoring for necessary items that are decided by environmental reviews. JICA undertakes monitoring based on regular reports including measured data submitted by the project proponent. When necessary, the project proponent should refer to the following monitoring form for submitting reports.

-When monitoring plans including monitoring items, frequencies and methods are decided, project phase or project life cycle (such as construction phase and operation phase) should be considered.

| Environmental<br>Resource     | Monitoring Item           | Result | Baseline | Standard<br>(MOE) | Standard<br>(Japan)   | Remarks |  |  |  |  |
|-------------------------------|---------------------------|--------|----------|-------------------|-----------------------|---------|--|--|--|--|
| 1. Project Befo               | ore Construction Ph       | lase   |          | <i></i>           |                       |         |  |  |  |  |
| 1.1 Socio-econ                | omy resource              |        |          |                   |                       |         |  |  |  |  |
| Land use and                  | - The monitoring          |        |          | -                 | -                     |         |  |  |  |  |
| Resettlement                  | on                        |        |          |                   |                       |         |  |  |  |  |
|                               | compensation of           |        |          |                   |                       |         |  |  |  |  |
|                               | resettlement and          |        |          |                   |                       |         |  |  |  |  |
|                               | grievance                 |        |          |                   |                       |         |  |  |  |  |
|                               | redress                   |        | [        |                   | l                     |         |  |  |  |  |
| 2. Project Construction Phase |                           |        |          |                   |                       |         |  |  |  |  |
| 2.1 Physical re               | source                    | ſ      | ſ        | I                 |                       |         |  |  |  |  |
|                               | - Confirmation of         |        |          | -                 | -                     |         |  |  |  |  |
|                               | license issued by         |        |          |                   |                       |         |  |  |  |  |
| C .: 1                        | Ministry of               |        |          |                   |                       |         |  |  |  |  |
| Soll erosion                  | Mines and                 |        |          |                   |                       |         |  |  |  |  |
| and slope                     | Energy and<br>Ministry of |        |          |                   |                       |         |  |  |  |  |
| failure                       | Water Descurace           |        |          |                   |                       |         |  |  |  |  |
|                               | and                       |        |          |                   |                       |         |  |  |  |  |
|                               | Meteorology               |        |          |                   |                       |         |  |  |  |  |
|                               | - The monitoring          |        |          | -                 | _                     |         |  |  |  |  |
|                               | on the                    |        |          |                   |                       |         |  |  |  |  |
|                               | topography and            |        |          |                   |                       |         |  |  |  |  |
|                               | the erosion at            |        |          |                   |                       |         |  |  |  |  |
|                               | the                       |        |          |                   |                       |         |  |  |  |  |
|                               | infrastructure            |        |          |                   |                       |         |  |  |  |  |
| Topography                    | construction site         |        |          |                   |                       |         |  |  |  |  |
| and erosion                   | - The monitoring          |        |          |                   |                       |         |  |  |  |  |
|                               | of erosion at the         |        |          |                   |                       |         |  |  |  |  |
|                               | road, protection          |        |          |                   |                       |         |  |  |  |  |
|                               | dike's                    |        |          |                   |                       |         |  |  |  |  |
|                               | and spoiled soil          |        |          |                   |                       |         |  |  |  |  |
|                               | dumping site              |        |          |                   |                       |         |  |  |  |  |
|                               | – Monitoring the          |        |          |                   |                       |         |  |  |  |  |
|                               | obstruct of the           |        |          | -                 | -                     |         |  |  |  |  |
| Hydrology                     | flow of pumping           |        |          |                   |                       |         |  |  |  |  |
|                               | wastewater                |        |          |                   |                       |         |  |  |  |  |
| Surface water                 | - Monitoring on           |        |          | pH:6.5-8.5        | pH:6.5-8.5            |         |  |  |  |  |
| quality                       | the water quality         |        |          | TSS:1-15          | TSS:<15               |         |  |  |  |  |
| 1 2                           | on the                    |        |          | 7.0               | DU:>5<br>COD:<5       |         |  |  |  |  |
|                               | parameters:               |        |          | COD:<8            | TN:<1                 |         |  |  |  |  |
|                               | temperature;              |        |          | TN:0.5-1.0        | TP<0.1                |         |  |  |  |  |
|                               | pH; Turbidity,            |        |          | TP:0.005-         | Pb:<0.01              |         |  |  |  |  |
|                               | TDS; TSS; DO;             |        |          | 0.05<br>Pb:<0.01  | As:\0.01<br>Cd:<0.003 |         |  |  |  |  |

| Environmental    | Monitoring Item              | Result | Baseline | Standard              | Standard        | Remarks |
|------------------|------------------------------|--------|----------|-----------------------|-----------------|---------|
| Resource         |                              | 1000   | 20000000 | (MOE)                 | (Japan)         |         |
|                  | BOD; COD;                    |        |          | As:<0.01<br>Cd:<0.001 | Hg: $< 0.0005$  |         |
|                  | SO <sub>4</sub> ; IN; IP; PD |        |          | Hg:<0.0005            | Total           |         |
|                  | and Iotal                    |        |          | (mg/l)                | Coliform:<      |         |
|                  | Contorm<br>Monitoring on     |        |          | Total                 | 50              |         |
|                  | - Montoring on               |        |          | 1000                  | (MPN/100<br>ml) |         |
|                  | waste                        |        |          | (MPN/100              | iiii)           |         |
|                  | management                   |        |          | ml)                   |                 |         |
|                  | - Monitoring on              |        |          | As:<15                | As:<150         |         |
|                  | solid-liquid                 |        |          | Cd:<0.8               | Cd:<150         |         |
|                  | waste                        |        |          | Cr:<100(Cr            | Cr:<250(Cr      |         |
| Soil quality     | management                   |        |          | 6)<br>Ph:<85          | o)<br>Ph:<150   |         |
| Son quanty       | - Monitoring on              |        |          | Hg:<0.3               | Hg:<15          |         |
|                  | the spill, leak of           |        |          | Se:<0.7               | Se:<150         |         |
|                  | fuel on the soil.            |        |          | (mg/kg-               | (mg/kg)         |         |
|                  | – Monitoring the             |        |          | CO:20                 | CO:20           |         |
|                  | material                     |        |          | NO2:0.1               | NO2:0.04-       |         |
|                  | transportation on            |        |          | SO2:0.3               | 0.06            |         |
|                  | road No. 271                 |        |          | O3:0.2                | SO2:0.1         |         |
|                  | - Monitoring the             |        |          | PM10:<0.0             | TSP:0.2         |         |
|                  | odor condition               |        |          | 5                     | PM2.5:<0.0      |         |
|                  | at construction              |        |          | PM2.5:<0.0            | 35              |         |
| Air Quanty       | sites                        |        |          | 25<br>Pb:0.005        | (mg/m3)         |         |
|                  | - Monitoring on              |        |          | H2S:0.001             |                 |         |
|                  | air quality                  |        |          | (mg/m3)               |                 |         |
|                  | parameters:                  |        |          |                       |                 |         |
|                  | TSP; CO; $NO_{2}$ ;          |        |          |                       |                 |         |
|                  | $SO_2, O_3, PM10,$           |        |          |                       |                 |         |
| Naina and        | PM2.5 and H <sub>2</sub> S   |        |          | Dav: 60               | Dav: 55         |         |
| Noise and        | - Monitoring on              |        |          | Evening: 50           | Night: 45       |         |
| vibration        | vibration from               |        |          | Night: 45             | (dB)            |         |
|                  | the material                 |        |          | (dB)                  |                 |         |
|                  | transportation               |        |          |                       |                 |         |
|                  | the operation of             |        |          |                       |                 |         |
|                  | any machinery.               |        |          |                       |                 |         |
|                  | generator and                |        |          |                       |                 |         |
|                  | vehicle.                     |        |          |                       |                 |         |
|                  | - Monitoring on              |        |          |                       |                 |         |
|                  | noise and                    |        |          |                       |                 |         |
|                  | vibration (Unit:             |        |          |                       |                 |         |
|                  | dB)                          |        |          |                       |                 |         |
| 2.2 Biological i | resources                    |        |          | 1                     | 1               |         |
|                  | - Monitoring on              |        |          |                       |                 |         |
|                  | solia-liquid                 |        |          |                       |                 |         |
|                  | waste                        |        |          |                       |                 |         |
|                  | – Monitoring on              |        |          |                       |                 |         |
|                  | the water quality            |        |          |                       |                 |         |
|                  | on the                       |        |          |                       |                 |         |
| Fish             | parameters                   |        |          |                       |                 |         |
|                  | temperature;                 |        |          |                       |                 |         |
|                  | pH; Turbidity,               |        |          |                       |                 |         |
|                  | TDS; TSS; DO;                |        |          |                       |                 |         |
|                  | BOD; COD;                    |        |          |                       |                 |         |
|                  | SO <sub>4</sub> ; TN; TP; Pb |        |          |                       |                 |         |
|                  | Total Coliform               |        |          |                       |                 |         |
| Dist             | - Monitoring the             |        |          |                       |                 |         |
| BIRUS            | wildlife                     |        |          |                       |                 |         |
| 1                | WILLING                      |        | 1        | 1                     | 1               | 1       |

| Environmental<br>Resource   | Monitoring Item  | Result | Baseline | Standard<br>(MOE)   | Standard<br>(Japan)   | Remarks |
|---|--|--------|----------|---|---|---------|
|   | especially the   |        |          |   |   |         |
| 2.3 Socio-econ  | omic resources   |        |          |   |   |         |
| Land use and<br>Resettlement  | <ul> <li>Monitoring on<br/>the livelihood of<br/>AHs loss their<br/>income 7 HHs.</li> <li>Monitoring to<br/>ensure that no<br/>encroachment to<br/>the STP area.</li> </ul>   |        |          |   |   |         |
| Livelihood,<br>occupations<br>of the local<br>community<br>and gender | <ul> <li>Monitoring on<br/>the staff-worker<br/>selection by<br/>prioritize the<br/>locals, gender<br/>equality as well<br/>as the disability</li> <li>Monitoring on<br/>work safety</li> </ul>  |        |          |   |   |         |
| Road  | <ul> <li>Monitoring on<br/>the<br/>transportation<br/>(speed and load)</li> <li>Monitoring on<br/>the parking</li> <li>Monitoring on<br/>the repair the<br/>damaged road<br/>by the project</li> </ul>   |        |          |   |   |         |
| Public Health<br>and Safety   | <ul> <li>Monitoring on<br/>solid-liquid<br/>waste<br/>management at<br/>temporary<br/>shelter</li> <li>Monitoring the<br/>clean water<br/>supply and<br/>sanitation</li> <li>Monitoring the<br/>safety<br/>equipment and<br/>work safety</li> <li>Monitoring the<br/>first aid room</li> </ul> |        |          |   |   |         |
| 3. Project Ope  | ration Phase   |        |          |   |   |         |
| Surface water   | - Monitoring on  |        |          | pH:6.5-8.5  | pH:6.5-8.5  |         |
| quality   | the water quality<br>on the<br>parameters:<br>temperature;<br>pH; Turbidity,<br>TDS; TSS; DO;<br>BOD; COD;<br>$SO_4$ ; TN; TP; Pb<br>and Total<br>Coliform   |        |          | TSS:1-15<br>DO:>2.0-<br>7.0<br>COD:<8<br>TN:0.5-1.0<br>TP:0.005-<br>0.05<br>Pb:<0.01<br>As:<0.01<br>Cd:<0.001<br>Hg:<0.0005<br>(mg/l) | TSS:<15<br>DO:>5<br>COD:<5<br>TN:<1<br>TP<0.1<br>Pb:<0.01<br>As:<0.01<br>Cd:<0.003<br>Hg:<0.0005<br>(mg/l)<br>Total<br>Coliform:< |         |

| Environmental  | Monitoring Item                | Result | Baseline | Standard<br>(MOF)      | Standard             | Remarks |
|----------------|--------------------------------|--------|----------|------------------------|----------------------|---------|
| Resource       | - Monitoring on                |        |          | Coliform:<             | (Japan)<br>(MPN/100  |         |
|                | - Montoring on<br>solid-liquid |        |          | 1000                   | ml)                  |         |
|                | waste                          |        |          | (MPN/100               |                      |         |
|                | management                     |        |          | ml)                    |                      |         |
|                | - Monitoring the               |        |          |                        |                      |         |
|                | filter system                  |        |          |                        |                      |         |
|                | cleaning                       |        |          |                        |                      |         |
|                | - Monitoring on                |        |          | CO:20                  | CO:20                |         |
|                | solid-liquid                   |        |          | NO2:0.1                | NO2:0.04-            |         |
|                | waste                          |        |          | 03:0.2                 | SO2:0.1              |         |
|                | management                     |        |          | TSP:0.33               | O3:0.06              |         |
|                | - Monitoring on                |        |          | PM10:0.05              | TSP:0.2              |         |
|                | air quanty                     |        |          | 5 PM12.5:0.02          | 35                   |         |
| Air Quality    | TSP: CO: NO.:                  |        |          | Pb:0.005               | (mg/m3)              |         |
| All Quality    | $SO_{2} \propto PM10$          |        |          | H2S:0.001              |                      |         |
|                | PM2.5 and H2S                  |        |          | (mg/m3)                |                      |         |
|                | - Monitoring on                |        |          |                        |                      |         |
|                | odor from waste                |        |          |                        |                      |         |
|                | storage and                    |        |          |                        |                      |         |
|                | along the access               |        |          |                        |                      |         |
|                | road.                          |        |          |                        |                      |         |
| Noise and      | - Monitoring on                |        |          | Day: 60<br>Evening: 50 | Day: 55<br>Night: 45 |         |
| vibration      | the noise and                  |        |          | Night: 45              | (dB)                 |         |
|                | the experision hy              |        |          | (dB)                   |                      |         |
|                | measure its level              |        |          |                        |                      |         |
|                | at the locations               |        |          |                        |                      |         |
|                | same as air                    |        |          |                        |                      |         |
|                | quality testing                |        |          |                        |                      |         |
|                | locations                      |        |          |                        |                      |         |
| 3.2 Biological | Resources                      |        |          |                        |                      |         |
|                | - Monitoring on                |        |          |                        |                      |         |
|                | the water quality              |        |          |                        |                      |         |
|                | on the                         |        |          |                        |                      |         |
|                | parameters:                    |        |          |                        |                      |         |
|                | temperature ;                  |        |          |                        |                      |         |
|                | $TDS \cdot TSS \cdot DO$       |        |          |                        |                      |         |
|                | BOD.                           |        |          |                        |                      |         |
|                | COD:SO4 : TN:                  |        |          |                        |                      |         |
|                | TP; Pb and Total               |        |          |                        |                      |         |
|                | Coliform                       |        |          |                        |                      |         |
| Ecosystem      | - Monitoring on                |        |          |                        |                      |         |
|                | solid-liquid                   |        |          |                        |                      |         |
|                | waste                          |        |          |                        |                      |         |
|                | management                     |        |          |                        |                      |         |
|                | Note: Comparing                |        |          |                        |                      |         |
|                | fish species near              |        |          |                        |                      |         |
|                | the project area               |        |          |                        |                      |         |
|                | Before the                     |        |          |                        |                      |         |
|                | project, study                 |        |          |                        |                      |         |
|                | team caught                    |        |          |                        |                      |         |
|                | only 6 species.                |        |          |                        |                      |         |
| 3.3 Socio-econ | omic Resources                 |        |          |                        |                      |         |
| Land use and   | - Monitoring on                |        |          |                        |                      |         |
| Resettlement   | the living                     |        |          |                        |                      |         |
|                | standard of the                |        |          |                        |                      |         |
|                | people who get                 |        |          |                        |                      |         |

| Environmental<br>Resource   | Monitoring Item   | Result | Baseline | Standard<br>(MOE) | Standard<br>(Japan) | Remarks |
|-----------------------------|---|--------|----------|-------------------|---------------------|---------|
|                             | their aquatic<br>crop by ensure<br>that they will<br>have a better<br>living before the<br>project exist.   |        |          |                   |                     |         |
| Road                        | <ul> <li>Monitoring the damage and repairing the road</li> <li>Monitoring the safety on access road</li> <li>Monitoring on the transportation, speed and traffic congestion</li> <li>Monitoring the installation of the traffic sign along the access road.</li> </ul>              |        |          |                   |                     |         |
| Public Health<br>and Safety | <ul> <li>Monitoring the electricity system, emergency exit in and outside the building</li> <li>Monitoring the oil and fuel storage</li> <li>Monitoring on the management and operation of the safety equipment (Fire safety system, fire extinguisher, fire alarm etc.)</li> </ul> |        |          |                   |                     |         |

### 6.4.2 Land Acquisition / Involuntary Resettlement

### Draft Monitoring Form (Land Acquisition / Involuntary Resettlement)

Name of person in charge and filling this monitoring form:

Date of filling this monitoring form:

### A. Preparation of Resettlement Site (\*If needed)

| No. | Explanation of the site                     | Status | Details such as:<br>(1) Site selection process and identification of<br>candidate sites<br>(2) Discussion record with PAPs<br>(3) Development of the site including infrastructure<br>(4) Main reasons for delay (if delayed)<br>(5) Additional information (if any) | Complete Date or<br>Expected Date of<br>Completion |
|-----|---|--------|--|--|
| 1   | Location:<br>Area:<br>Number of Households: |        | <ul> <li>(1)</li> <li>(2)</li> <li>(3)</li> <li>(4)</li> <li>(5)</li> </ul>  |  |
| 2   | Location:<br>Area:<br>Number of Households: |        | <ul> <li>(1)</li> <li>(2)</li> <li>(3)</li> <li>(4)</li> <li>(5)</li> </ul>  |  |
| 3   | Location:<br>Area:<br>Number of Households: |        | (1)<br>(2)<br>(3)<br>(4)<br>(5)  |  |

### **B.** Public Consultations

| No. | Date | Place | Contents of the consultation / main comments and answers |
|-----|------|-------|--|
| 1   |      |       |  |
| 2   |      |       |  |
| 3   |      |       |  |
| 4   |      |       |  |
| 5   |      |       |  |
| 6   |      |       |  |
| 7   |      |       |  |
| 8   |      |       |  |
| 9   |      |       |  |
| 10  |      |       |  |

### C. Resettlement Activities

|   |                  |      | Pro                      | Progress in Quantity        |                      |                             | Progress in %        |                       |                              |  |  |
|---|------------------|------|--------------------------|-----------------------------|----------------------|-----------------------------|----------------------|-----------------------|------------------------------|--|--|
| Activities  | Planned<br>Total | Unit | During<br>the<br>Quarter | Till the<br>Last<br>Quarter | Up to the<br>Quarter | Till the<br>Last<br>Quarter | Up to the<br>Quarter | Date of<br>Completion | Responsible<br>Organizations |  |  |
| Preparation of resettlement                       |                  |      |                          |                             |                      |                             |                      |                       |                              |  |  |
| Approval of<br>BRP and<br>submission to<br>IRC    |                  |      |                          |                             |                      |                             |                      |                       | MPWT                         |  |  |
| Approval of<br>BRP                                |                  |      |                          |                             |                      |                             |                      |                       | MEF                          |  |  |
| BRP disclosure<br>on JICA<br>Website              |                  |      |                          |                             |                      |                             |                      |                       | ЛСА                          |  |  |
| Budget securing<br>for resettlement<br>activities |                  |      |                          |                             |                      |                             |                      |                       | MEF, MPWT                    |  |  |

|  |                  |                                | Pro                      | gress in Qua                | ntity                | Progre                      | ss in %              |                                   |                              |
|--|------------------|--------------------------------|--------------------------|-----------------------------|----------------------|-----------------------------|----------------------|-----------------------------------|------------------------------|
| Activities   | Planned<br>Total | Unit                           | During<br>the<br>Quarter | Till the<br>Last<br>Quarter | Up to the<br>Quarter | Till the<br>Last<br>Quarter | Up to the<br>Quarter | Expected<br>Date of<br>Completion | Responsible<br>Organizations |
| Loan<br>Agreement /<br>Exchange of<br>Notes  |                  |                                |                          |                             |                      |                             |                      |                                   | GOC, JICA                    |
| Contract with<br>Independent<br>consultant for<br>Replacement<br>Cost Survey       |                  | ММ                             |                          |                             |                      |                             |                      |                                   | MEF, MPWT,<br>IRC            |
| Contract with<br>Independent<br>consultant for<br>Income<br>Restoration<br>Program |                  | ММ                             |                          |                             |                      |                             |                      |                                   | MEF, MPWT,<br>IRC            |
| Contract with<br>External<br>Monitoring<br>Agency                                  |                  | ММ                             |                          |                             |                      |                             |                      |                                   | MEF, MPWT,<br>IRC            |
| Establishment<br>of necessary<br>organizations<br>such as IRC-<br>WG               |                  | Number of<br>Organizati<br>ons |                          |                             |                      |                             |                      |                                   | MEF, MPWT,<br>IRC            |
| Income<br>Restoration<br>Program (IRP)<br>preparation                              |                  |                                |                          |                             |                      |                             |                      |                                   | Independent<br>Consultant    |
| Detailed<br>Measurement<br>Survey (DMS)  |                  | Number of<br>PAPs              |                          |                             |                      |                             |                      |                                   | IRC                          |
| Finalization of<br>PAPs List based<br>on DMS                                       |                  | Number<br>of PAPs              |                          |                             |                      |                             |                      |                                   | IRC                          |
| Submission of<br>Replacement<br>Cost Survey<br>report                              |                  |                                |                          |                             |                      |                             |                      |                                   | Independent<br>Consultant    |
| Calculation of<br>compensation<br>amount to be<br>paid to PAPs                     |                  |                                |                          |                             |                      |                             |                      |                                   | IRC                          |
| BRP Updating<br>(DRP) and<br>submit to JICA<br>for Review and                      |                  |                                |                          |                             |                      |                             |                      |                                   | IRC                          |

|   |                  |                   | Pro                      | Progress in Quantity        |                      |                             | ess in %             |                                   |                                  |
|---|------------------|-------------------|--------------------------|-----------------------------|----------------------|-----------------------------|----------------------|-----------------------------------|----------------------------------|
| Activities  | Planned<br>Total | d Unit            | During<br>the<br>Quarter | Till the<br>Last<br>Quarter | Up to the<br>Quarter | Till the<br>Last<br>Quarter | Up to the<br>Quarter | Expected<br>Date of<br>Completion | Responsible<br>Organizations     |
| Concurrence   |                  |                   |                          |                             |                      |                             |                      |                                   |                                  |
| Approval of<br>DRP                                    |                  |                   |                          |                             |                      |                             |                      |                                   | IRC                              |
| Disclosure of<br>Approval DRP<br>at Commune<br>Office |                  |                   |                          |                             |                      |                             |                      |                                   | IRC, Commune<br>Office           |
| Submission of<br>External<br>monitoring<br>report     |                  |                   |                          |                             |                      |                             |                      |                                   | External<br>Monitoring<br>Agency |
| Implementation  | of resettleme    | ent               |                          |                             |                      |                             |                      |                                   |                                  |
| Negotiation   |                  | Number<br>of PAPs |                          |                             |                      |                             |                      |                                   |                                  |
| Section 1<br>* Elaborated<br>later                    |                  | Number<br>of PAPs |                          |                             |                      |                             |                      |                                   |                                  |
| Section 2   |                  | Number<br>of PAPs |                          |                             |                      |                             |                      |                                   |                                  |
| Section 3   |                  | Number<br>of PAPs |                          |                             |                      |                             |                      |                                   |                                  |
| Payment of compensation                               |                  | Number<br>of PAPs |                          |                             |                      |                             |                      |                                   |                                  |
| Section 1   |                  | Number<br>of PAPs |                          |                             |                      |                             |                      |                                   |                                  |
| Section 2   |                  | Number<br>of PAPs |                          |                             |                      |                             |                      |                                   |                                  |
| Section 3   |                  | Number<br>of PAPs |                          |                             |                      |                             |                      |                                   |                                  |
| Provision of<br>land plots                            |                  | Number<br>of PAPs |                          |                             |                      |                             |                      |                                   |                                  |

|  |                  |                                     | Progress in Quantity     |                             |                      | Progre                      | ess in %             | Exposted                          |                              |
|--|------------------|-------------------------------------|--------------------------|-----------------------------|----------------------|-----------------------------|----------------------|-----------------------------------|------------------------------|
| Activities                                 | Planned<br>Total | Unit                                | During<br>the<br>Quarter | Till the<br>Last<br>Quarter | Up to the<br>Quarter | Till the<br>Last<br>Quarter | Up to the<br>Quarter | Expected<br>Date of<br>Completion | Responsible<br>Organizations |
| Section 1                                  |                  | Number                              |                          |                             |                      |                             |                      |                                   |                              |
|  |                  | of PAPs                             |                          |                             |                      |                             |                      |                                   |                              |
| Section 2                                  |                  | Number                              |                          |                             |                      |                             |                      |                                   |                              |
|  |                  | of PAPs                             |                          |                             |                      |                             |                      |                                   |                              |
| Section 3                                  |                  | Number                              |                          |                             |                      |                             |                      |                                   |                              |
|  |                  | of PAPs                             |                          |                             |                      |                             |                      |                                   |                              |
| Provision of apartment in                  |                  | Number                              |                          |                             |                      |                             |                      |                                   |                              |
| resettlement<br>sites                      |                  | of PAPs                             |                          |                             |                      |                             |                      |                                   |                              |
| Section 1                                  |                  | Number                              |                          |                             |                      |                             |                      |                                   |                              |
|  |                  | of PAPs                             |                          |                             |                      |                             |                      |                                   |                              |
| Section 2                                  |                  | Number                              |                          |                             |                      |                             |                      |                                   |                              |
|  |                  | of PAPs                             |                          |                             |                      |                             |                      |                                   |                              |
| Section 3                                  |                  | Number                              |                          |                             |                      |                             |                      |                                   |                              |
|  |                  | of PAPs                             |                          |                             |                      |                             |                      |                                   |                              |
| Provision of assistance for                |                  | Number                              |                          |                             |                      |                             |                      |                                   |                              |
| Vulnerable<br>PAPs                         |                  | of PAPs                             |                          |                             |                      |                             |                      |                                   |                              |
| Section 1                                  |                  | Number                              |                          |                             |                      |                             |                      |                                   |                              |
|  |                  | of PAPs                             |                          |                             |                      |                             |                      |                                   |                              |
| Section 2                                  |                  | Number                              |                          |                             |                      |                             |                      |                                   |                              |
|  |                  | of PAPs                             |                          |                             |                      |                             |                      |                                   |                              |
| Section 3                                  |                  | Number                              |                          |                             |                      |                             |                      |                                   |                              |
|  |                  | of PAPs                             |                          |                             |                      |                             |                      |                                   |                              |
| Provision of<br>assistance for<br>Business |                  | Number<br>of affected<br>businesses |                          |                             |                      |                             |                      |                                   |                              |
| Section 1                                  |                  | Number of<br>affected<br>businesses |                          |                             |                      |                             |                      |                                   |                              |

|  |                  |                                     | Progress in Quantity     |                             |                      | Progre                      | ss in %              | - Expected                        |                              |
|--|------------------|-------------------------------------|--------------------------|-----------------------------|----------------------|-----------------------------|----------------------|-----------------------------------|------------------------------|
| Activities   | Planned<br>Total | Unit                                | During<br>the<br>Quarter | Till the<br>Last<br>Quarter | Up to the<br>Quarter | Till the<br>Last<br>Quarter | Up to the<br>Quarter | Expected<br>Date of<br>Completion | Responsible<br>Organizations |
| Section 2  |                  | Number of                           |                          |                             |                      |                             |                      |                                   |                              |
| Section  |                  | businesses                          |                          |                             |                      |                             |                      |                                   |                              |
| Section 3  |                  | Number of<br>affected<br>businesses |                          |                             |                      |                             |                      |                                   |                              |
| Site clearance   |                  | Number<br>of PAPs                   |                          |                             |                      |                             |                      |                                   |                              |
| Section 1  |                  | Number<br>of PAPs                   |                          |                             |                      |                             |                      |                                   |                              |
| Section 2  |                  | Number<br>of PAPs                   |                          |                             |                      |                             |                      |                                   |                              |
| Section 3  |                  | Number<br>of PAPs                   |                          |                             |                      |                             |                      |                                   |                              |
| Income<br>Restoration<br>Program (IRP)<br>implementatio<br>n |                  | Number<br>of PAPs                   |                          |                             |                      |                             |                      |                                   |                              |
| Section 1  |                  | Number<br>of PAPs                   |                          |                             |                      |                             |                      |                                   |                              |
| Section 2  |                  | Number<br>of PAPs                   |                          |                             |                      |                             |                      |                                   |                              |
| Section 3  |                  | Number<br>of PAPs                   |                          |                             |                      |                             |                      |                                   |                              |
| Grievance<br>Redress   | -                | Number<br>of cases                  |                          |                             |                      |                             |                      |                                   |                              |
| Section 1  | -                | Number<br>of cases                  |                          |                             |                      |                             |                      |                                   |                              |
| Section 2  | -                | Number<br>of cases                  |                          |                             |                      |                             |                      |                                   |                              |

|            |                  |                    | Pro                      | gress in Qua                | ntity                | Progre                      | ess in %             | Expected<br>Date of<br>Completion | Responsible<br>Organizations |
|------------|------------------|--------------------|--------------------------|-----------------------------|----------------------|-----------------------------|----------------------|-----------------------------------|------------------------------|
| Activities | Planned<br>Total | Unit               | During<br>the<br>Quarter | Till the<br>Last<br>Quarter | Up to the<br>Quarter | Till the<br>Last<br>Quarter | Up to the<br>Quarter |                                   |                              |
| Section 3  | -                | Number<br>of cases |                          |                             |                      |                             |                      |                                   |                              |

### **D.** Record of Grievances

| No. | Date | Place | Status<br>(Received/On<br>Going/Solved) | Contents of Grievance | Response against Grievance | Responsible organization |
|-----|------|-------|---|-----------------------|----------------------------|--------------------------|
| 1   |      |       |   |                       |                            |                          |
| 2   |      |       |   |                       |                            |                          |
| 3   |      |       |   |                       |                            |                          |
| 4   |      |       |   |                       |                            |                          |
| 5   |      |       |   |                       |                            |                          |
| 6   |      |       |   |                       |                            |                          |
| 7   |      |       |   |                       |                            |                          |
| 8   |      |       |   |                       |                            |                          |

END

| Category   | Environmental Item                      | Main Check Items   | Yes: Y<br>No: N                    | Confirmation of Environmental<br>Considerations<br>(Reasons, Mitigation Measures)   |
|--|---|--|------------------------------------|---|
| 1 Permits and Explanation  | (1) EIA and<br>Environmental<br>Permits | <ul> <li>(a) Have EIA reports been already prepared in official process?</li> <li>(b) Have EIA reports been approved by authorities of the host country's government?</li> <li>(c) Have EIA reports been unconditionally approved? If conditions are imposed on the approval of EIA reports, are the conditions satisfied?</li> <li>(d) In addition to the above approvals, have other required environmental permits been obtained from the appropriate regulatory authorities of the host country's government?</li> </ul> | (a) N<br>(b) N<br>(c) N/A<br>(d) N | <ul> <li>(a) EIA document is under preparation by<br/>the Project and the environmental permit<br/>is expected to be granted in October 2019.</li> <li>(b), (c) &amp; (d) Ditto</li> </ul>  |
| (2) Explanation to the Local Stakeholders       (a) Have contents of the project and the potential impacts been adequately explained to the Local stakeholders based on appropriate procedures, including information disclosure? Is understanding obtained from the Local stakeholders?         (b) Have the comment from the stakeholders (such as local residents) been reflected to the project design?         (3) Examination of Alternatives       (a) Have alternative plans of the project been examined with social and environmental considerations?         (1) Water Quality       (a) Do pollutants, such as SS, BOD, COD, |   |  |                                    | <ul> <li>(a) Public consultation meetings were held<br/>from 5 Oct. 2018 to 25 Feb. 2019,<br/>explaining potential impacts.</li> <li>(b) The comments from stakeholders shall<br/>be reflected in the detailed design.</li> </ul>   |
|  | (3) Examination of<br>Alternatives      | (a) Have alternative plans of the project been examined with social and environmental considerations?  | (a) Y                              | (a) The results of examination of alternatives are shown in the final report.   |
| 2 Pollution Control  | (1) Water Quality                       | <ul> <li>(a) Do pollutants, such as SS, BOD, COD, pH contained in treated effluent from a sewage treatment plant comply with the country's effluent standards?</li> <li>(b) Does untreated water contain heavy metals?"</li> </ul>   | (a) N<br>(b) Y                     | <ul> <li>(a) Some parameters including heavy metals such as mercury exceed the country's effluent standards, but after the treatment it will be within the standard.</li> <li>(b) Heavy metal contamination is expected in untreated water but the concentration of the treated water will be within the standard.</li> </ul> |
|  | (2) Wastes                              | (a) Are wastes, such as sludge generated<br>by the facility operations properly treated<br>and disposed of in accordance with the<br>country's standards?  | (a) Y                              | (a) Sludge will be treated at the final damping sites.  |
|  | (3) Soil Contamination                  | (a) If wastes, such as sludge are suspected<br>to contain heavy metals, are adequate<br>measures taken to prevent contamination<br>of soil and groundwater by leachates from<br>the wastes?  | (a) N                              | (a) Heavy metals in sludge will be dried at<br>the site properly and damped at the final<br>damping sites.  |
|  | (4) Noise and<br>Vibration              | (a) Do noise and vibrations generated<br>from the facilities, such as sludge<br>treatment facilities and pumping stations<br>comply with the country's standards?  | (a) Y                              | (a) Potential noise sources above ground<br>will be installed in RC structures. If further<br>reduction is required, necessity of hood<br>silencer and soundproof walls for sound<br>insulation will be considered.   |
|  | (5) Odor                                | (a) Are adequate control measures taken<br>for odor sources, such as sludge<br>treatment facilities?   | (a) Y                              | (a) Odor reduction facilities will be designed because the site is next to a residential area.  |
| 3 Natural En   | (1) Protected Areas                     | (a) Is the project site located in protected<br>areas designated by the country's laws or<br>international treaties and conventions? Is<br>there a possibility that the project will<br>affect the protected areas?  | (a) N                              | (a) There is no protected area in or near the Project site.   |
| vironment  | (2) Ecosystem                           | (a) Does the project site encompass<br>primeval forests, tropical rain forests,<br>ecologically valuable habitats (e.g., coral<br>reefs, mangroves, or tidal flats)?   | (a) N<br>(b) N<br>(c) N<br>(d) N   | <ul> <li>(a) No protected area or valuable<br/>habitats exist in or near the site.</li> <li>(b) &amp;(c) According to the EIA survey, some<br/>endangered species were listed in zone B</li> </ul>  |

## 6.5 Environmental Check List Environmental Check List

| Category             | Environmental Item           | Main Check Items   | Yes: Y<br>No: N  | Confirmation of Environmental<br>Considerations<br>(Reasons, Mitigation Measures)  |
|----------------------|------------------------------|--|--|--|
|                      |                              | <ul> <li>(b) Does the project site encompass the protected habitats of endangered species designated by the country's laws or international treaties and conventions?</li> <li>(c) If significant ecological impacts are anticipated, are adequate protection measures taken to reduce the impacts on the ecosystem?</li> <li>(d) Is there a possibility that the project will adversely affect aquatic environments, such as rivers? Are adequate measures taken to reduce the impacts on aquatic organisms?</li> </ul>   |  | where relatively far (about 3 km) from the<br>project site. Considering the site<br>environment (e.g. DO is 0.3 mg/l), the<br>endangered species are not inhabit in and<br>around the project site, therefore negative<br>impact to the species by the project is<br>negligible. Furthermore, the environment<br>around the project site will be slightly<br>improved by the project, thus positive<br>impacts will be expected to ecosystem in<br>and around the project site.<br>(d) The objective of the Project is to<br>improve water environment. Although<br>most of the project site will be reclaimed,<br>but as the area of the project is small and<br>present aquatic environments are poor,<br>negative impact is not significant.  |
| 4 Social Environment | (1) Resettlement             | <ul> <li>(a) Is involuntary resettlement caused by project implementation? If involuntary resettlement is caused, are efforts made to minimize the impacts caused by the resettlement?</li> <li>(b) Is adequate explanation on compensation and resettlement given to affected people prior to resettlement?</li> <li>(c) Is the resettlement plan, including compensation with full replacement costs, restoration of livelihoods and living standards developed based on socioeconomic studies on resettlement?</li> <li>(d) Is the compensation going to be paid prior to the resettlement?</li> <li>(e) Is the compensation policies prepared in document?</li> <li>(f) Does the resettlement plan pay particular attention to vulnerable groups or people, including women, children, the elderly, people below the poverty line, ethnic minorities, and indigenous peoples?</li> <li>(g) Are agreements with the affected people obtained prior to resettlement?</li> <li>(h) Is the organizational framework established to properly implement resettlement? Are the capacity and budget secured to implement the plan?</li> <li>(j) Is the grievance redress mechanism established?</li> </ul> | (a) N<br>(b) N/A<br>(c) N/A<br>(d) N/A<br>(e) N/A<br>(f) N/A<br>(g) N/A<br>(h) N/A<br>(i) N/A<br>(j) Y | <ul> <li>(a), (b), (c), (d), (e), (f), (g), (h) &amp; (i)<br/>Involuntary resettlement is not expected<br/>in the Project.</li> <li>(J) The MEF will facilitate the<br/>establishment of a Municipal Grievance<br/>Redress Committee (MGRC) which will be<br/>responsible for addressing grievances for<br/>the project. The MGRC will be established<br/>by the Municipal Governor in consultation<br/>with the IRC.</li> <li>Any grievances of AHs in connection with<br/>the implementation of the BRP will be<br/>handled through negotiation with the aim<br/>of achieving consensus. Complaints will go<br/>through three stages before they may be<br/>elevated to a court of law as a last resort.</li> <li>GDR/IRC will shoulder all administrative<br/>and legal fees that will be incurred in the<br/>resolution of grievances and complaints.<br/>The handling of the complaint ends in the<br/>MGRC.</li> </ul> |
|                      | (2) Living and<br>Livelihood | <ul> <li>(a) Is there a possibility that changes in<br/>land uses and water uses due to the<br/>project will adversely affect the living<br/>conditions of inhabitants?</li> <li>(b) Is there a possibility that the project<br/>will adversely affect the living conditions<br/>of inhabitants? Are adequate measures<br/>considered to reduce the impacts, if<br/>necessary?</li> </ul>  | (a) N<br>(b) N/A   | <ul> <li>(a) The Project will contribute to<br/>improvement hygiene and public health.</li> <li>(b) Adverse impacts to inhabitants' livings<br/>are not expected in the Project. Although<br/>their agriculture land will be moved, but<br/>adequate compensation and<br/>relocation/purchase of the land will be<br/>implemented.</li> </ul>  |
|                      | (3) Heritage                 | (a) Is there a possibility that the project<br>will damage the local archeological,<br>historical, cultural, and religious heritage?<br>Are adequate measures considered to<br>protect these sites in accordance with the<br>country's laws?   | (a) N/A  | (a) No cultural heritage exists in or near the Project area.   |
|                      | (4) Landscape                | (a) Is there a possibility that the project  | (a) N  | (a) Project component will not affect the  |

| Category | Environmental Item                                 | Main Check Items  | Yes: Y<br>No: N                  | Confirmation of Environmental<br>Considerations<br>(Reasons, Mitigation Measures)  |  |
|----------|--|---|----------------------------------|--|--|
|          |  | will adversely affect the local landscape?<br>Are necessary measures taken?   |                                  | landscape significantly.   |  |
|          | (5) Ethnic Minorities<br>and Indigenous<br>Peoples | (a) Are considerations given to reduce impacts on the culture and lifestyle of ethnic minorities and indigenous peoples?  | (a) N/A<br>(b) N/A               | (a) & (b) No ethnic minorities or<br>indigenous peoples live in or near the<br>Project site.   |  |
|          | (6) Working<br>Conditions                          | <ul> <li>(a) Is the project proponent not violating any laws and ordinances associated with the working conditions of the country which the project proponent should observe in the project?</li> <li>(b) Are tangible safety considerations in place for individuals involved in the project, such as the installation of safety equipment which prevents industrial accidents, and management of hazardous materials?</li> <li>(c) Are intangible measures being planned and implemented for individuals involved in the project, such as the establishment of a safety and health program, and safety training (including traffic safety and public health) for workers etc.?</li> <li>(d) Are appropriate measures taken to ensure that security guards involved in the project not to violate safety of other individuals involved, or local residents?</li> </ul> | (a) Y<br>(b) Y<br>(c) Y<br>(d) Y | (a), (b), (c) & (d) Safety aspects will be fully<br>considered in the detailed design.<br>Additionally, education programs will be<br>carried out by the contractor to improve<br>the workers' awareness of safety and<br>health conditions.   |  |
| 5 Others | (1) Impacts during<br>Construction                 | <ul> <li>(a) Are adequate measures considered to reduce impacts during construction (e.g., noise, vibrations, turbid water, dust, exhaust gases, and wastes)?</li> <li>(b) If construction activities adversely affect the natural environment (ecosystem), are adequate measures considered to reduce impacts?</li> <li>(c) If construction activities adversely affect the social environment, are adequate measures considered to reduce impacts?</li> <li>(d) If the construction activities might cause traffic congestion, are adequate measures considered to reduce impacts?</li> </ul>   | (a) Y<br>(b) N<br>(c) N<br>(d) Y | <ul> <li>(a) They are mentioned in the final report.</li> <li>(b) &amp; (c) The Project will not cause significant adverse impact on natural and social environments. Adequate measures are described in the final report.</li> <li>(d) So far serious impact is not predicted with construction. Information on the construction activities would be disclosed to public through mass-media on a timely basis. Additionally, public consultation with the residents would be held.</li> </ul> |  |
|          | (2) Monitoring                                     | <ul> <li>(a) Does the proponent develop and<br/>implement monitoring program for the<br/>environmental items that are considered<br/>to have potential impacts?</li> <li>(b) What are the items, methods and<br/>frequencies of the monitoring program?</li> <li>(c) Does the proponent establish an<br/>adequate monitoring framework<br/>(organization, personnel, equipment, and<br/>adequate budget to sustain the<br/>monitoring framework)?</li> <li>(d) Are any regulatory requirements<br/>pertaining to the monitoring report<br/>system identified, such as the format and<br/>frequency of reports from the proponent<br/>to the regulatory authorities?</li> </ul>  | (a) Y<br>(b) -<br>(c) Y<br>(d)Y  | (a), (b), (c) & (d) Preliminary monitoring<br>system has been established and are<br>written in the final report based on JICA<br>Supplemental Study. It will be developed<br>during detail design stage referring<br>comments of MOE.   |  |
| 6 Note   | Note on Using<br>Environmental<br>Checklist        | (a) If necessary, the impacts to<br>transboundary or global issues should be<br>confirmed (e.g., the project includes<br>factors that may cause problems, such as<br>transboundary waste treatment, acid rain,<br>destruction of the ozone layer, or global<br>warming).  | (a) N/A                          | (a) The impacts to transboundary such as<br>waste is not expected. The project makes<br>positive impact to global warming  |  |

### 6.6 Water Quality Standards related to the Project

### (1) Water Quality and Effluent Standard

The Sub-Decree on Water Pollution Control, 1999 was enacted on 6<sup>th</sup> April 1999, aiming to prevent water pollution in Cambodia. This sub-decree defines "Classification of waste and hazard discharge", "Water Quality Standard", "Effluent Standard", "Responsibility of polluter", "Monitoring", "Discharge Permit", "Inspection" and "Penalty", etc.

Water quality standard in public water areas such as river, lakes, reservoirs and coastal water is set for bio-diversity conservation (**Table 1**). In addition, twenty-five parameters are set as water quality standard in public water areas for public health protection (**Table 2**).

|                             | No | Parameter         | Unit      | Standard Value |
|-----------------------------|----|-------------------|-----------|----------------|
|                             | 1  | pН                | -         | 6.5 - 8.5      |
|                             | 2  | BOD <sub>5</sub>  | mg/l      | 1 – 10         |
| 1. River                    | 3  | Suspended Solid   | mg/l      | 2.4 - 100      |
|                             | 4  | Dissolved Oxygen  | mg/l      | 2.0 - 7.5      |
|                             | 5  | Coliform          | MPN/100ml | < 5,000        |
|                             | 1  | pН                | -         | 6.5 - 8.5      |
|                             | 2  | COD <sub>Mn</sub> | mg/l      | 1 - 8          |
| 2 Labras and                | 3  | Suspended Solid   | mg/l      | 1 – 15         |
| 2. Lakes and<br>Recomposite | 4  | Dissolved Oxygen  | mg/l      | 2.0 - 7.5      |
| Reservoirs                  | 5  | Coliform          | MPN/100ml | < 1,000        |
|                             | 6  | Total Nitrogen    | mg/l      | 1.0 - 0.6      |
|                             | 7  | Total Phosphorus  | mg/l      | 0.005 - 0.05   |
|                             | 1  | pН                | -         | 7.0 - 8.3      |
|                             | 2  | COD <sub>Mn</sub> | mg/l      | 2 - 8          |
|                             | 3  | Suspended Solid   | mg/l      | 2 - 7.5        |
| 3. Coastal Water            | 4  | Coliform          | MPN/100ml | < 1,000        |
|                             | 5  | Oil Content       | mg/l      | 0              |
|                             | 6  | Total Nitrogen    | mg/l      | 0.2 - 1.0      |
|                             | 7  | Total Phosphorus  | mg/l      | 0.02 - 0.09    |

 Table 1 Water Quality Standard for Bio-Diversity Conservation

\* Some parameters have 'lower limit' and 'upper limit'. As the result of inquiry to MOE about 'lower limit', setting up of the 'lower limit' (excluding pH) is not correct and those should be revised but the schedule of the revision is not fixed.

Source: Sub-Decree on Water Pollution Control, Annex 4: Water Quality Standard in public water areas for biodiversity conservation.

 Table 2 Water Quality Standard for Public Health Protection

| No. | Parameter             | Standard Value (µg/l) |
|-----|-----------------------|-----------------------|
| 1   | Carbon tetrachloride  | < 12                  |
| 2   | Hexachloro-benzene    | < 0.03                |
| 3   | DDT                   | < 10                  |
| 4   | Endrin                | < 0.01                |
| 5   | Diedrin               | < 0.01                |
| 6   | Aldrin                | < 0.005               |
| 7   | Isodrin               | < 0.005               |
| 8   | Perchloroethylene     | < 10                  |
| 9   | Hexachlorobutadiene   | < 0.1                 |
| 10  | Chloroform            | < 12                  |
| 11  | 1,2 Trichloroethylene | < 10                  |
| 12  | Trichloroethylene     | < 10                  |
| 13  | Trichlorobenzene      | < 0.4                 |

| No. | Parameter           | Standard Value (µg/l) |
|-----|---------------------|-----------------------|
| 14  | Hexachloroethylene  | < 0.05                |
| 15  | Benzene             | < 10                  |
| 16  | Tetrachloroethylene | < 10                  |
| 17  | Cadmium             | < 1                   |
| 18  | Total mercury       | < 0.5                 |
| 19  | Organic mercury     | 0                     |
| 20  | Lead                | < 10                  |
| 21  | Chromium, valent 6  | < 50                  |
| 22  | Arsenic             | < 10                  |
| 23  | Selenium            | < 10                  |
| 24  | Polychlorobiohenyl  | 0                     |
| 25  | Cyanide             | < 0.005               |

Source: Sub-decree on Water Pollution Control, Annex 5: Water Quality Standard in public water areas for public health protection.

"Effluent standard for pollution sources discharging wastewater to public water areas or sewer" is defined in this sub-decree (**Table 3**). "Protected public water area" is set in this standard. All effluent including industries in PPCC should comply with the standard for "Public water area and sewer" since the protected area is currently not yet specified.

| No  | Domonoston                        | Linit          | Stan                        | dard                        |
|-----|-----------------------------------|----------------|-----------------------------|-----------------------------|
| INO | Parameter                         | Unit           | Protected Public Water Area | Public Water Area and Sewer |
| 1   | Temperature                       | <sup>0</sup> C | < 45                        | < 45                        |
| 2   | pН                                |                | 6 – 9                       | 5 – 9                       |
| 3   | BOD <sub>5</sub> (5 days at 20°C) | mg/l           | < 30                        | < 80                        |
| 4   | COD <sub>Cr</sub>                 | mg/l           | < 50                        | < 100                       |
| 5   | Total Suspended Solids            | mg/l           | < 60                        | < 120                       |
| 6   | Total Dissolved Solids            | mg/l           | < 1,000                     | < 2,000                     |
| 7   | Grease and Oil                    | mg/l           | < 5.0                       | < 15                        |
| 8   | Detergents                        | mg/l           | < 5.0                       | < 15                        |
| 9   | Phenols                           | mg/l           | < 0.1                       | < 1.2                       |
| 10  | Nitrate (NO <sub>3</sub> )        | mg/l           | < 10                        | < 20                        |
| 11  | Chlorine (free)                   | mg/l           | < 1.0                       | < 2.0                       |
| 12  | Chloride (ion)                    | mg/l           | < 500                       | < 700                       |
| 13  | Sulphate (as SO <sub>4</sub> )    | mg/l           | < 300                       | < 500                       |
| 14  | Sulphate (as Sulphur)             | mg/l           | < 0.2                       | < 1.0                       |
| 15  | Phosphate (PO <sub>4</sub> )      | mg/l           | < 3.0                       | < 6.0                       |
| 16  | Cyanide (CN)                      | mg/l           | < 0.2                       | < 1.5                       |
| 17  | Barium (Ba)                       | mg/l           | < 4.0                       | < 7.0                       |
| 18  | Arsenic (As)                      | mg/l           | < 0.10                      | < 1.0                       |
| 19  | Tin (Sn)                          | mg/l           | < 2.0                       | < 8.0                       |
| 20  | Iron (Fe)                         | mg/l           | < 1.0                       | < 20                        |
| 21  | Boron (B)                         | mg/l           | < 1.0                       | < 5.0                       |
| 22  | Manganese (Mn)                    | mg/l           | < 1.0                       | < 5.0                       |
| 23  | Cadmium (Cd)                      | mg/l           | < 0.1                       | < 0.5                       |
| 24  | Chromium (Cr <sup>+3</sup> )      | mg/l           | < 0.2                       | < 1.0                       |
| 25  | Chromium (Cr <sup>+6</sup> )      | mg/l           | < 0.05                      | < 0.5                       |
| 26  | Copper (Cu)                       | mg/l           | < 0.2                       | < 1.0                       |
| 27  | Lead (Pb)                         | mg/l           | < 0.1                       | < 1.0                       |
| 28  | Mercury (Hg)                      | mg/l           | < 0.002                     | < 0.05                      |
| 29  | Nickel (Ni)                       | mg/l           | < 0.2                       | < 1.0                       |
| 30  | Selenium (Se)                     | mg/l           | < 0.05                      | < 0.5                       |
| 31  | Silver (Ag)                       | mg/l           | < 0.1                       | < 0.5                       |
| 32  | Zinc (Zn)                         | mg/l           | < 1.0                       | < 3.0                       |
| 33  | Molybdenum (Mo)                   | mg/l           | < 0.1                       | < 1.0                       |
| 34  | Ammonia (NH <sub>3</sub> )        | mg/l           | < 5.0                       | < 7.0                       |
| 35  | DO                                | mg/l           | >2.0                        | >1.0                        |

 Table 3 Effluent Standard for Public Water Areas or Sewer

| Na  | Denometer                | Linit | Stan                        | dard                        |
|-----|--------------------------|-------|-----------------------------|-----------------------------|
| INO | Parameter                | Unit  | Protected Public Water Area | Public Water Area and Sewer |
| 36  | Polychlorinated Byphenyl | mg/l  | < 0.003                     | < 0.003                     |
| 37  | Calcium                  | mg/l  | <150                        | <200                        |
| 38  | Magnesium                | mg/l  | <150                        | <200                        |
| 39  | Carbon tetrachloride     | mg/l  | <3                          | <3                          |
| 40  | Hexachloro benzene       | mg/l  | <2                          | <2                          |
| 41  | DTT (Dithiothreitol)     | mg/l  | <1.3                        | <1.3                        |
| 42  | Endrin                   | mg/l  | < 0.01                      | < 0.01                      |
| 43  | Dieldrin                 | mg/l  | < 0.01                      | < 0.01                      |
| 44  | Aldrin                   | mg/l  | < 0.01                      | < 0.01                      |
| 45  | Isodrin                  | mg/l  | < 0.01                      | < 0.01                      |
| 46  | Perchloro ethylene       | mg/l  | <2.4                        | <2.4                        |
| 47  | Hexachloro butadiene     | mg/l  | <3                          | <3                          |
| 48  | Chloroform               | mg/l  | <1                          | <1                          |
| 49  | 1,2 Dichloro ethylene    | mg/l  | <2.4                        | <2.4                        |
| 50  | Trichloro ethylene       | mg/l  | <1                          | <1                          |
| 51  | Trichloro benzene        | mg/l  | <2                          | <2                          |
| 52  | Hexaxhloro cyclohexene   | mg/l  | <2                          | <2                          |

Note: "Protected public water area" is set in this standard. All effluents including those of industries should be subject to the standard of "Public water area and sewer" since the protected area is not yet currently specified. Source: Sub-Decree on Water Pollution Control, Annex 2: Effluent standard for pollution sources discharging wastewater to public water areas or sewer

### 1.1.2 Sub-decree on the Management of Drainage and Wastewater Treatment System

This sub-decree is updated one related to management of drainage and wastewater treatment system, which was issued on 25<sup>th</sup> November 2017. This sub-decree stipulates 1) demarcation of responsibility of related ministries (MPWT, MOE and MOI) as well as local governments such as capital and provincial administrations, 2) measures for the management of wastewater, drainage and wastewater treatment system, 3) duties of related authorities for managing and providing services for sewerage and wastewater treatment system, 4) Monitoring and inspection and 5) penalties. In this sub-decree, effluent discharge standards for commercial building, private residential development area and resort or recreation centers are provided as shown in **Table 4**.

| No. | Parameter                               | Unit | Permissible Standard       |                            |  |  |
|-----|---|------|----------------------------|----------------------------|--|--|
|     |   |      | Discharged to the          | Discharges Directly to the |  |  |
|     |   |      | Drainage/Sewerage System   | Public Waterbody or        |  |  |
|     |   |      | connected to Centralized   | Drainage/Sewerage System   |  |  |
|     |   |      | Wastewater Treatment Plant |                            |  |  |
| 1   | pН                                      | -    | 5-9                        | 6-8                        |  |  |
| 2   | Total Suspended Solids (TSS)            | mg/l | < 150                      | < 80                       |  |  |
| 3   | Oil or Grease                           | Mg/l | < 20                       | < 5                        |  |  |
| 4   | BOD <sub>5</sub> (5 days at 20°C)       | mg/l | < 80                       | < 30                       |  |  |
| 5   | COD <sub>Cr</sub>                       | mg/l | < 120                      | < 50                       |  |  |
| 6   | Detergents- LAS                         | mg/l | < 15                       | < 7                        |  |  |
| 7   | Total Nitrogen (T-N)                    | mg/l | < 10                       | < 6                        |  |  |
| 8   | Total Phosphorus (T-P)                  | mg/l | < 1                        | < 0.5                      |  |  |
| 9   | Ammonium Nitrogen (NH4 <sup>+</sup> -N) | mg/l | < 8                        | < 5                        |  |  |
| 10  | Coliform                                |      | -                          | 500-2,500                  |  |  |

Table 4 Effluent Discharge Standard from Commercial Building, Borey, Satellite City and<br/>Resort or Recreation Center

Source: Sub-decree on the Management of Drainage and Wastewater Treatment System (Table of Annex 1 and Annex 2)

### 6.7 Discussion on Water Quality

### 1. Influent Condition

### 1.1 Wastewater Analysis Result by MOE

MOE has been implementing analysis work of wastewater sampled around the Trabek pumping station from January 2012 to December 2017. The analysis results might be applicable for the STP design because the sampling point is close to the planned intake point. Since the data was widely fluctuated regardless season but reason of fluctuation was unclear, the data was statistically examined applying Smirnov-Grubbs test in order to be minimized error. **Figure 1-1** shows the wastewater analysis data after carried out the statistical test, **Table 1-1** shows that the summarized figures.







|                    | pН   | TSS    | BOD    | T-N    | T-P    |
|--------------------|------|--------|--------|--------|--------|
|                    | (-)  | (mg/L) | (mg/L) | (mg/L) | (mg/L) |
| Average            | 7.39 | 142    | 197    | 8.1    | 2.1    |
| Median             | 7.40 | 138    | 205    | 8.2    | 2.1    |
| Maximum            | 8.20 | 218    | 288    | 12.4   | 2.9    |
| Minimum            | 6.75 | 80     | 98     | 3.7    | 1.2    |
| Standard Deviation | 0.41 | 38.4   | 53     | 2.5    | 0.5    |

 Table 1-1
 Analysis Data Summary (After Smirnov-Grubbs Test)

Source: Survey Team, based on data provided by MOE

Simple average of pH, Total Suspended Solids (TSS), Biochemical Oxygen Demand (BOD), Total Nitrogen (T-N), and Total Phosphorus (T-P) in wastewater sampled during said period are 7.39, 142, 197 8.1, and 2.1 respectively.

### 1.2 Difference between Wet Season and Dry Season

Climate in Cambodia is classified into 2 seasons, namely dry season which generally runs from December to April, and wet season from May to November. Since wastewater treated by the project comes with rainwater, amount of rainfall may directly affect the wastewater quality. **Figure 1-1** also shows rainfall data from year 2012 to 2015 and classifies seasons by color. **Figure 1-2** shows relationship between amount of monthly rainfall and wastewater quality, correlation however among them is not clearly confirmed.



Source: Survey Team Figure 1-2 Relationship between Rainfall and Wastewater Quality

Thus, comparison by statistical approach was tried, in order to confirm whether differences between dry and wet season are found or not. **Figure 1-3** shows box plot of indicators comparing between dry and wet season using data collected in year 2012 to 2017. Dry season is set from December to April and remaining is wet season. The result of each *p-value* obtained by *t-test* is also shown in the Figure. In general, in case p-value>0.05, the average on each data is presumed not different, based on this understanding, it is concluded that only T-P differs among the season. One of the reasons may be that the sampling has not been carried out during raining, and the influence of rainwater becomes small at timing of sampling after stop raining, because rainwater runs faster.



Source: Survey Team



### 1.3 Wastewater Analysis Result by this Survey

In order to confirm the accuracy of data provided by MOE, wastewater sampling was carried out on 22nd August 2018 at Trabek Pumping station. At upstream and downstream of the pumping station, 4 samples were collected when the pumps were being operated. **Figure 1-4** shows the location of Sampling points, and **Table 1-2** shows the analysis result. T-BOD was fluctuated between 115 and 180 mg/L and average was 149 mg/L. Average of TSS was 54.5 mg/L, considerably smaller than the data provided by MOE. T-N and T-P in average were 30.3 mg/L and 1.38 mg/L respectively.



Source: Google Earth Pro®





Photo 1-1 Sampling Work at Trabek pumping Station

| Table 1-2 Summary of Wastewater Analysis Result |               |                 |               |                 |                     |  |  |  |  |  |
|---|---------------|-----------------|---------------|-----------------|---------------------|--|--|--|--|--|
| Sampling No                                     | W1 Upstream-1 | W1 Downstream-1 | W1 Upstream-2 | W1 Downstream-2 | Average             |  |  |  |  |  |
| Sampling Time                                   | 10:30am       | 10:30am         | 14:00pm       | 14:00pm         | (min-max)           |  |  |  |  |  |
| pН  | 6.95          | 7.18            | 7.09          | 7.26            | 7.12<br>(6.95-7.26) |  |  |  |  |  |
| T-BOD (mg/L)                                    | 115           | 180             | 155           | 145             | 149<br>(115-180)    |  |  |  |  |  |
| S-BOD (mg/L)                                    | 63.0          | 61.0            | 65.0          | 59.0            | 62.0<br>(59.0-65.0) |  |  |  |  |  |
| TSS (mg/L)                                      | 62.0          | 42.0            | 46.0          | 68.0            | 54.5<br>(42.0-68.0) |  |  |  |  |  |
| T-N (mg/L)                                      | 29.4          | 32.2            | 30.1          | 29.5            | 30.3<br>(29.4-32.2) |  |  |  |  |  |
| NH <sup>4+</sup> -N (mg/L)                      | 11.2          | 14.0            | 12.6          | 11.8            | 12.4<br>(11.2-14.0) |  |  |  |  |  |
| T-P (mg/L)                                      | 1.43          | 1.34            | 1.35          | 1.40            | 1.38<br>(1.34-1.43) |  |  |  |  |  |

 Table 1-2
 Summary of Wastewater Analysis Result

Sampling date: 22nd August 2018

Source: Survey Team

### 1.4 Wastewater Quality set for STP Design

BOD in wastewater in the Master Plan (M/P) is set at 195mg/l which is calculated from loading rate of each segment (domestic/commercial and industrials), and TSS is calculated by BOD X 105%. Since the average of BOD shown in **Table 1-1** is very close to the figure in M/P, 195mg/l is applicable. TSS in **Table 1-1** is smaller than the M/P's figure but higher figure namely 205mg/l should be adopted from a conservative point of view for plant design. Value of pH is set at 7.5. **Table 1-3** summarizes the set wastewater quality for STP design. Since the planned STP is adopted PTF system which does not fundamentally remove nitrogen and phosphorus, T-N and T-P in final discharge is not be regulated. Thus, these figures are not set in wastewater as well.

 Table 1-3
 Wastewater Quality set for STP design

|                              | рН(-) | TSS (mg/L) | BOD (mg/L) |
|------------------------------|-------|------------|------------|
| Adopted Value for STP Design | 7.5   | 205        | 195        |
| Source: Survey Team          |       |            |            |

### 2. Limitation of Nitrogen and Phosphorus removal by PTF

A guideline<sup>1</sup> for introducing PTF describes that PTF is applicable for STP with final discharge standard of BOD is exceeding 10 mg/l and not more than 15 mg/l, not applicable with standalone to any advanced treatment facility to remove nitrogen and phosphorus. On the other hand, a result of PTF pilot plant test<sup>2</sup> performed in Da Nang city in Vietnam shows that some of nitrogen and phosphorus were removed. **Table 2-1** shows average on pilot plant test result. The report has not shown organic nitrogen (Org-N) but it is calculated by total nitrogen (T-N) minus nitrate (NO<sub>3</sub><sup>-</sup>-N) and minus nitrite (NO<sub>2</sub><sup>-</sup>-N).

| Tuble 2 1 Triverage of Water Quanty Marysis Result on each Process |                     |                     |                     |                     |                     |                     |                      |                     |  |
|--|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|----------------------|---------------------|--|
|  | BOD                 | SS                  | T-N                 | Org-N <sup>*2</sup> | $NH_4^+$ -N         | $NO_2^{-}-N$        | NO 3 <sup>-</sup> -N | T-P                 |  |
| _  | $(mg \cdot L^{-1})$ | $(mg \cdot L^{-1})$ | $(mg \cdot L^{-1})$ | $(mg \cdot L^{-1})$ | $(mg \cdot L^{-1})$ | $(mg \cdot L^{-1})$ | $(mg \cdot L^{-1})$  | $(mg \cdot L^{-1})$ |  |
| Influent   | 65.8                | 101.6               | 19.4                | 6.6                 | 12.4                | 0.1                 | 0.3                  | 4.4                 |  |
| FSF Effluent   | 51.8                | 46.8                | 16.3                | 4.7                 | 11.2                | 0.1                 | 0.3                  | -                   |  |
| HTF Effluent   | 16.2                | 28                  | 8.9                 | 2.5                 | 2.6                 | 0.1                 | 3.7                  | -                   |  |
| SLS Effluent *1  | 7.3                 | 7                   | 8.2                 | 1.6                 | 2.1                 | 1.1                 | 3.4                  | 0.7                 |  |
| Removal Efficienc  | y 88.9%             | 93.1%               | 57.7%               |                     |                     |                     |                      | 84.1%               |  |

 Table 2-1
 Average of Water Quality Analysis Result on each Process

\*1 with filter

\*2 Org-N caluculated by  $(T-N) - [(NH_4^+ - N) + (NO_2 - N) + (NO_3 - N)]$ 

Source: Japan Sewage Works Agency, Technology Verification Report Advanced Energy Saving Wastewater Treatment Process (March 2014).

Average of T-N in wastewater was 19.4 mg/L, final discharge, namely effluent from SLS was 8.2 mg/L, total removal efficiency was obtained at 57.7%. In case of phosphorus, total removal efficiency was achieved at 84.1% calculated by 4.4 mg/L, in wastewater and 0.7 mg/L, in final discharge.

In this project, Nitrogen and Phosphorus in wastewater are not set because of no regulation. Average of actual analysis result of T-N and T-P sampled near intake point show in **Table 1-1**, and **Table 1-2** but these figures are considerably higher than the case of Da Nang.

In addition, the planed STP for Phnom Penh will equip sludge digestion process in order to minimize amount of sludge disposal and GHG emission. By biodegradation in anaerobic digestion process, organic matter decomposes into low molecules, nitrogen and phosphorus in organic matter are transferred to ammonia (NH<sub>4</sub><sup>+</sup>-N) and phosphate (PO<sub>4</sub><sup>3-</sup>-P) and dissolved into supernatant. The supernatant is returned to wastewater treatment system to treat again. Therefore, it is said that anaerobic digestion process affects to wastewater treatment process, concentration of nitrogen (T-N) and phosphorus (T-P) in the final discharge may be higher.

Considering these points, JICA Study team made a simulation to clarify how much T-N and T-P could be reduced. **Figure 2-1** shows the simulation result, relationship between influent and effluent concentration

<sup>&</sup>lt;sup>1</sup> National Institute for Land and Infrastructure Management, MLITT Japan, B-DASH project No.12 Guideline for introducing a Technology for Advanced Pre-Treatment Trickling Filter System, ISSN1346-7238, No.951 (February 2017).

<sup>&</sup>lt;sup>2</sup> Japan Sewage Works Agency, Technology Verification Report Advanced Energy Saving Wastewater Treatment Process (March 2014).

of T-N and T-P, as well as removal efficiency.

The removal efficiency of T-N and T-P is depending on influent concentration, decreasing when influent concentration becomes high. For instance, when T-N in influent is 20 mg/L, effluent is expected at 9.8 mg/L, removal efficiency is 49%, should T-N in influent be 40 mg/L, effluent is 25 mg/L, removal efficiency is 38%. Comparing with the result of Da Nang at 19.4 mg/L of influent T-N, difference of effluent among them is approximately 0.8 mg/L higher than Da Nang. Also Difference at 4.4 mg/L of T-P influent is approximately 1.0 mg/L higher. These differences come from sludge digestion.



Figure 2-1 Expected T-N and T-P in Final Discharge and Removal Efficiency

### 3. Estimation of Effluent T-N and T-P for STP proposed in the Project

Based on the simulation discussed in the previous chapter, possible effluent T-N and T-P applying proposed process is estimated as summarized in the following table

| Tuble e 1 Estimation of Efficient 1 i tor S11 proposed in the Project |                    |  |     |   |  |  |  |  |
|---|--------------------|--|-----|---|--|--|--|--|
|   | Influent           | Estimated Effluent Removal<br>Efficiency |     | Remarks   |  |  |  |  |
|   | (mg/L)             | (mg/L)                                   | (%) |   |  |  |  |  |
| T-N, Case 1   | 8.11)              | 2.5                                      | 69  | 1) average of MOE' data<br>(see Table 1-1)                      |  |  |  |  |
| T-N, Case 2   | 30.3 <sup>2)</sup> | 16.9                                     | 44  | 2) average of water monitoring<br>result at W-1 (see Table 1-2) |  |  |  |  |
| T-P, <sub>Case-1</sub>  | 2.1 <sup>3)</sup>  | 0.3                                      | 86  | 3) average of MOE' data (see Table 1-1)                         |  |  |  |  |
| T-P, Case-2   | 1.384)             | 0.13                                     | 91  | 4) average of water monitoring<br>result at W-1 (see Table 1-2) |  |  |  |  |
|   |                    |  |     |   |  |  |  |  |

 Table 3-1
 Estimation of Effluent T-N and T-P for STP proposed in the Project

Source: Survey Team

#### 6.8 Alternative Study on Sludge Treatment Method (Detailed Calculation)

#### CAPEX 1.

Table 1.1 shows estimate of CAPEX (direct cost) of each case. <u>Case 2</u> is the most expensive than others.

|                                   | Estimat                                       | e Result of CALL   | A of Sludge Heat            | ment System                                |
|-----------------------------------|---|--|-----------------------------|--|
| Case                              | Case 1  | Case 2   | Case 3                      | Case 4                                     |
| Treatment System                  | Sludge Dewatering by<br>Mechanical Dehydrator | Sludge Digestion +<br>Dewatering by Mechanical<br>Dehydrator | Sludge Drying by Drying Bed | Sludge Digestion + Drying by<br>Drying Bed |
| Civil and Structural              | USD31,900.00                                  | USD52,200.00   | USD397,800.00               | USD219,300.00                              |
| Mechanical and<br>Piping          | USD479,300.00                                 | USD622,700.00  | USD75,100.00                | USD252,700.00                              |
| Electrical and<br>Instrumentation | USD3,100.00                                   | USD17,100.00   | USD1,700.00                 | USD15,600.00                               |
| Others                            | USD10,400.00                                  | USD11,300.00   | USD1,100.00                 | USD2,000.00                                |
| Total                             | USD524,700.00                                 | USD703,300.00  | USD475,700.00               | USD489,600.00                              |

Table 1.1 Estimate Result of CAPEX of Sludge Treatment System

Source: Survey Team

#### 2. **OPEX**

Table 1.2 shows estimate of OPEX of each case. It includes personnel cost, sludge transportation cost and maintenance cost of sludge treatment facility, but not include sludge disposal cost. Maintenance cost of civil & structural, mechanical & piping and electrical & instrumental are estimated at 1%, 3% and 2% of each CAPEX respectively. <u>Case 1</u> and <u>2</u> are extremely expensive than <u>Case 3</u> and <u>4</u>, due to polymer consumption for dewatering, also highly skilled technician for operation of mechanical dehydrator is required.

| Case                        |                                | Case 1        |   | Case               | Case 2                             |   | Case 3        |                             |                |                    |  |
|-----------------------------|--------------------------------|---------------|---|--------------------|------------------------------------|---|---------------|-----------------------------|----------------|--------------------|--|
|                             |                                | Unit Cost     | Sludge Dewatering by Mechanical<br>Dehydrator |                    | Sludge Digestion +<br>Mechanical D | Sludge Digestion + Dewatering by<br>Mechanical Dehydrator |               | Sludge Drying by Drying Bed |                | ying by Drying     | Remark   |
|                             |                                | (USD)         | Amount  | Cost<br>(USD/year) | Amount                             | Cost<br>(USD/year)  | Amount        | Cost<br>(USD/year)          | Amount         | Cost<br>(USD/year) |  |
| Electricity                 |                                | 0.15USD/kWh   | 24,700kWh/year                                | 3,705.00           | 54,200kWh/year                     | 8,130.00  | 4,000kWh/year | 600.00                      | 39,500kWh/year | 5,925.00           |  |
| Chemicals                   | Polymer                        | 4.00USD/kg    | 6,643kg/year                                  | 26,572.00          | 3,541kg/year                       | 14,164.00   | 0kg/year      | 0.00                        | 0kg/year       | 0.00               |  |
| Personnel                   | Technician Class               | 3,600USD/year | 2person                                       | 7,200.00           | 2.5person                          | 9,000.00  | 0.5person     | 1,800.00                    | 1 person       | 3,600.00           |  |
|                             | Labor Class                    | 1,800USD/year | 1 person                                      | 1,800.00           | 1 person                           | 1,800.00  | 6person       | 10,800.00                   | 3person        | 5,400.00           |  |
|                             | Truck Driver                   | 1,800USD/year | 2person                                       | 3,600.00           | 1 person                           | 1,800.00  | 1person       | 1,800.00                    | 0.5person      | 900.00             |  |
| Vehicle Fue<br>Transportati | l for Sludge<br>ion            | 1.00USD/L     | 7,384L/year                                   | 7,384.00           | 2,347L/year                        | 2,347.00  | 2,464L/year   | 2,464.00                    | 1,174L/year    | 1,174.00           | 3tons/times,<br>Distance:20km(round trip),<br>Fuel Consumption:2km/L |
| Sludge Disp                 | osal                           | 0USD/kg       | 2,215tons/year                                | 0.00               | 704tons/year                       | 0.00  | 739tons/year  | 0.00                        | 352tons/year   | 0.00               | No charge for sludge disposal  |
| Mentenance                  | e Civil & Structural           | 1% of CAPEX   |   | 320.00             |                                    | 530.00  |               | 3,980.00                    |                | 2,190.00           |  |
|                             | Mechanical &<br>Piping         | 3% of CAPEX   |   | 14,380.00          |                                    | 18,690.00   |               | 2,260.00                    |                | 7,580.00           |  |
|                             | Electrical and<br>Instrumental | 2% of CAPEX   |   | 70.00              |                                    | 350.00  |               | 40.00                       |                | 310.00             |  |
| Total                       |                                |               |   | 65,031.00          |                                    | 56,811.00   |               | 23,744.00                   |                | 27,079.00          |  |

Table 1.2 **OPEX of Sludge Treatment System** 

Source: Survey Team

#### 3. **Comparison of Greenhouse Gases (GHGs) Emission**

Nitrous Oxide (N<sub>2</sub>O). Also, biodegradable matter in sludge decomposes and generates CH<sub>4</sub> at the final disposal site. The total amount of GHGs generated through sludge treatment and disposal is calculated by following formula;

$$GHGs_{Total} = GHGs_{Electricity} + GHGs_{Fuel} + GHGs_{Disposal}$$
(1)

Where,

GHGSTotal : Greenhouse Gases Emission in Total (kg-CO<sub>2Eq</sub>/year) GHGs<sub>Electricity</sub> : Greenhouse Gases Emission caused by electricity consumption (kg-CO<sub>2Eq</sub>/year) : Greenhouse Gases Emission caused by vehicle fuel consumption (kg-CO<sub>2Eq</sub>/year) **GHGS**<sub>Fuel</sub> GHGs<sub>Disposal</sub> : Greenhouse Gases Emission caused by sludge disposal (kg-CO<sub>2Eq</sub>/year)

### 3.1 GHGs Emission caused by Electricity Consumption

GHGs generated by electricity consumed is calculated by following formula;

$$GHGs_{Electricity} = EF_{Grid} \cdot EC_{Grid}$$
(2)

Where,

 $EF_{Grid}$ : Emission Factor by electricity consumption (625.7 kg-CO<sub>2Eq</sub>/MWh<sup>\*</sup>) \*Source)https://www.env.go.jp/earth/coop/lowcarbon-asia/localgov2/data/FY2013\_FS16\_JP\_V1.pdf

*EC<sub>Grid</sub>* : Electricity Consumption (MWh/year)

Table 3.1 shows GHGs emission by electricity consumed. GHGs emission is proportional with electricity consumption, sludge treatment system having digestion system generates much GHGs due to power consumption for agitation in the digester.

| Table 3.1G                                      | GHGs Emission by Electricity Consumed |              |                                   |  |  |  |  |
|---|---------------------------------------|--------------|-----------------------------------|--|--|--|--|
| Treatment System                                | EF Grid                               | EC Grid      | GHGs Electricity                  |  |  |  |  |
| Sludge Dewatering by Mechanical Dehydrator      |                                       | 24.7MWh/year | 15,455 kg-CO <sub>2Eq</sub> /year |  |  |  |  |
| Sludge Digestion + Dewatering by Mechanical Deh | hydrator                              | 54.2MWh/year | 33,913 kg-CO <sub>2Eq</sub> /year |  |  |  |  |
| Sludge Drying by Drying Bed                     | $023.7$ kg- $CO_{2Eq}/101$ w II       | 4.0MWh/year  | 2,503 kg-CO <sub>2Eq</sub> /year  |  |  |  |  |
| Sludge Digestion + Drying by Drying Bed         |                                       | 39.5MWh/year | 24,715 kg-CO <sub>2Eq</sub> /year |  |  |  |  |
| Source: Survey Team                             |                                       |              |                                   |  |  |  |  |

### 3.2 GHG Emission caused by Vehicle Fuel Consumption for Sludge Disposal

By consuming vehicle fuel, not only CO<sub>2</sub>, but also CH<sub>4</sub> and N<sub>2</sub>O are generated. Since the conversion factor of CH<sub>4</sub> and N<sub>2</sub>O into CO<sub>2</sub> are 25 and 298 respectively, GHGs generated by vehicle fuel consumed is calculated by following formula;

$$GHGs_{Fuel} = (EF_{CO2} + 25 \cdot EF_{CH4} + 298 \cdot EF_{N20}) \cdot Fuel_{Diesel}$$

Where,

| EF <sub>CO2</sub>      | : Emission Factor (CO <sub>2</sub> ) by fuel consumption (74,100 kg-CO <sub>2</sub> /TJ*)           |
|------------------------|---|
| EF <sub>CH4</sub>      | : Emission Factor (CH <sub>4</sub> ) by fuel consumption (3.9 kg-CH <sub>4</sub> /TJ <sup>*</sup> ) |
| EF <sub>N20</sub>      | : Emission Factor (N <sub>2</sub> O) by fuel consumption (3.9 kg-N <sub>2</sub> O/TJ <sup>*</sup> ) |
| Fuel <sub>Diesel</sub> | : Diesel Fuel Consumed (= Fuel Consumed X LHV of Diesel fuel; 37.7MJ/L)                             |
| * Source) 2006         | IPCC Guideline for National Greenhouse Gas Inventories, Vol.2 Energy, Chapter 3 Mobile Combustion   |

(3)

Table 3.2 shows GHGs emission by vehicle fuel consumed. GHGs emission is proportional with sludge generation amount to be disposed. Since sludge drying after digestion generates minimizes sludge disposal, this system is the best way to be minimize of GHGs emission.

| Table 3.2GHGs Em                                       | nission by Vehicle Fuel Consumed |              |                                   |  |  |  |
|--|----------------------------------|--------------|-----------------------------------|--|--|--|
| Treatment System                                       | Fuel Consumed                    | Fuel Diesel  | GHGs Fuel                         |  |  |  |
| Sludge Dewatering by Mechanical Dehydrator             | 7,690L/year                      | 0.290TJ/year | 21,848 kg-CO <sub>2Eq</sub> /year |  |  |  |
| Sludge Digestion + Dewatering by Mechanical Dehydrator | 2,444L/year                      | 0.092TJ/year | 6,944 kg-CO <sub>2Eq</sub> /year  |  |  |  |
| Sludge Drying by Drying Bed                            | 2,567L/year                      | 0.097TJ/year | 7,293 kg- $CO_{2Eq}$ /year        |  |  |  |
| Sludge Digestion + Drying by Drying Bed                | 1,224L/year                      | 0.046TJ/year | 3,477 kg-CO <sub>2Eq</sub> /year  |  |  |  |
| Contract Contract Toom                                 |                                  |              |                                   |  |  |  |

Source: Survey Team

### 3.3 GHSs Emission caused by Sludge Disposal

Disposed sludge generates CH<sub>4</sub> at the final disposal site. The CH<sub>4</sub> generation potential of the sludge that is disposed in a certain year will decrease gradually throughout the following decades. In this process, the release of CH<sub>4</sub> from this specific amount of sludge decreases gradually.

The equations for estimating the CH<sub>4</sub> generation are given by "2006 IPCC Guideline for National Greenhouse Gas Inventories, Vol.5 Waste, Chapter 3 Solid Waste Disposal". The CH<sub>4</sub> potential that is generated throughout the years can be estimated on the basis of the amounts and composition of the waste disposed into disposal site and the management practices at the sites.

$$DDOC_m = \mathbf{W} \cdot DOC \cdot DOC_f \cdot MCF \tag{4}$$

Where,

| $DDDC_m$  | : mass of decomposable degradable organic carbon deposited (Gg/year) |  |  |  |  |
|---|--|--|--|--|--|
| W   | : mass of sludge deposited (Gg/year)                                 |  |  |  |  |
| DOC   | : degradable organic carbon in the year of deposition,               |  |  |  |  |
|   | fraction (Gg-Carbon/Gg-Sludge)                                       |  |  |  |  |
| $DOC_f$ : fraction  | on of DOC that can decompose $(=0.5^*)$                              |  |  |  |  |
| MCF : CH <sub>4</sub> correction factor for aerobic decomposition in the year of deposition |  |  |  |  |  |

(=0.8\*, in case of unmanaged -deep (>5m waste) and/or high water table)

\* Source) 2006 IPCC Guideline for National Greenhouse Gas Inventories, Vol.5 Waste, Chapter 3 Solid Waste Disposal

$$DDOC_{m \, decomp_T} = DDOC_{ma_{T-1}} \cdot (1 - e^{-k}) \tag{5}$$

Where,

**DDOC**<sub>mdecompr</sub>: DDOC<sub>m</sub> decomposed in the disposal site in year T, (Gg)

 $DDOC_{ma_{T-1}}$  :  $DDOC_m$  accumulated in the disposal site at the end of year T-1, (Gg)

*T* : Inventory year (=20years)

k : reaction constant (0.4 year<sup>-1\*</sup>)

\* Source) 2006 IPCC Guideline for National Greenhouse Gas Inventories, Vol.5 Waste, Chapter 3 Solid Waste Disposal

$$CH_{4 generated_T} = DDOC_{m \, decomp_T} \cdot F \cdot \frac{16}{12} \tag{6}$$

$$GHGs_{Disposal} = 25 \cdot CH_{4 \, Generated_T} \cdot 1,000,000 \,/\, T \tag{7}$$

Where,

 $CH_{4 \ Generated \ T}$  : amount of CH<sub>4</sub> generated from decomposable material (Gg)  $DDOC_{m \ decomp \ T}$  :  $DDOC_m \ decomposed$  in year, T (Gg) F : fraction of CH4, by volume, in generated landfill gas (=0.5<sup>\*</sup>) \* Source) 2006 IPCC Guideline for National Greenhouse Gas Inventories, Vol.5 Waste,

Chapter 3 Solid Waste Disposal

**Table 3.3** shows GHGs emission by sludge disposal in case the inventory year set at 20years. *GHGs*<sub>Disposal</sub> in the table shows the average value for 20years. Sludge treatment system having sludge digestion generates smaller amount of GHGs than without digestion because organic carbon in sludge is already digested in STP.

Table 3.3GHGs Emission by Sludge Disposal

| Treatment System  | W              | DOC    | $DDOC_{m}$     | DDOC m decomp T   | CH 4 generated T  | GHGs Disposal                      |
|---|----------------|--------|----------------|-------------------|-------------------|------------------------------------|
| Sludge Dewatering by<br>Mechanical Dehydrator             | 2.3068 Gg/year | 0.03   | 0.0277 Gg/year | 0.8056 Gg/20years | 0.5371 Gg/20years | 671,343 kg-CO <sub>2Eq</sub> /year |
| Sludge Digestion + Dewatering<br>by Mechanical Dehydrator | 0.7329 Gg/year | 0.0375 | 0.0110 Gg/year | 0.3200 Gg/20years | 0.2133 Gg/20years | 266,625 kg- $CO_{2Eq}$ /year       |
| Sludge Drying by Drying Bed                               | 0.7691 Gg/year | 0.09   | 0.0277 Gg/year | 0.8057 Gg/20years | 0.5371 Gg/20years | 671,343 kg-CO <sub>2Eq</sub> /year |
| Sludge Digestion + Drying by<br>Drying Bed                | 0.3665 Gg/year | 0.075  | 0.0110 Gg/year | 0.3200 Gg/20years | 0.2133 Gg/20years | 266,625 kg-CO <sub>2Eq</sub> /year |

Source: Survey Team

### 3.4 Total GHSs Emission

From the above, GHGs in total is calculated as shown in **Table 3.4**. Sludge drying after digestion can minimize GHGs emission in 4 types of sludge treatment system.

|  |                  |           | (un           | it: kg-CO <sub>2Eq</sub> /year) |
|--|------------------|-----------|---------------|---------------------------------|
| Treatment System                                       | GHGs Electricity | GHGs Fuel | GHGs Disposal | GHGs Total                      |
| Sludge Dewatering by Mechanical Dehydrator             | 15,455           | 21,848    | 671,343       | 708,646                         |
| Sludge Digestion + Dewatering by Mechanical Dehydrator | 33,913           | 6,944     | 266,625       | 307,482                         |
| Sludge Drying by Drying Bed                            | 2,503            | 7,293     | 671,343       | 681,139                         |
| Sludge Digestion + Drying by Drying Bed                | 24,715           | 3,477     | 266,625       | 294,818                         |
| Source: Survey Team                                    |                  |           |               |                                 |

### Table 3.4 Total GHGs Emission of Sludge Treatment and Disposal

Source: Survey Team

### 6.9 Capacity Calculation

### 1. Design Criteria

- (1) Flow Rate (Max. Daily, Fixed)  $5,000 \text{ m}^3/\text{day}$
- (2) Characteristics of Raw Wastewater

|       | Dry Season |              | Rainy Season |            |
|-------|------------|--------------|--------------|------------|
| T-BOD | 195 mg/l,  | 975 kg/day   | 100 mg/l,    | 500 kg/day |
| S-BOD | 130 mg/l,  | 650 kg/day   | 70 mg/l,     | 350 kg/day |
| TSS   | 205 mg/l,  | 1,025 kg/day | 90 mg/l,     | 450 kg/day |

### 2.Design

### 2.1. Grit Chamber

### (1) Design Conditions

- Surface Loading Rate:  $1,800 \text{ m}^3/\text{m}^2/\text{day}$
- No of Series: 2 ( 1 for duty, 1 for stand-by)

(2) Design Calculation

- Section Area of the Chamber 5,000 m<sup>3</sup>/day / 1,800 m<sup>3</sup>/m<sup>2</sup>/day / 1 chamber = 2.8 m<sup>2</sup>

Grid Chamber Dimension: 3.0 m X 1.0 m X 0.5 m H(Water Depth) - Surface Area: 3.0 m<sup>2</sup> - Surface Loading Rate: 1,667 m<sup>3</sup>/m<sup>2</sup>/day

### 2.2. Automatic Bar Screen

### (1) Design Conditions

- No of Series: 1 for duty
- Width of Channel: 1.0 m

### (2) Design

Automatic Bar Screen W 1,000mm x H 2,000mm x Op. 15mm x 0.025kW x 1unit duty

### 2.3. Fixed Bar Screen

(1) Design Conditions

- No of Series: 1 for Stand-by
- Width of Channel: 1.0 m

(2) Design

Fixed Bar Screen

W 1,000mm x H 2,000mm x Op. 15mm x 1unit stand-by

### 2.4. Reservoir Tank

(1) Design Conditions

- Flow Rate:

|   | Dry Season                  | Rainy Season                |
|---|-----------------------------|-----------------------------|
| Raw Wastewater                                | 5,000 m <sup>3</sup> /day   | 5,000 m <sup>3</sup> /day   |
| Overflow from HTF                             | 284.5 m <sup>3</sup> /day   | 285.4 m <sup>3</sup> /day   |
| Supernatant from Primary Sedimentation Tank   | 1,119.6 m <sup>3</sup> /day | 570.5 m <sup>3</sup> /day   |
| Supernatant from Biogas Settler               | 35.7 m <sup>3</sup> /day    | 11.5 m <sup>3</sup> /day    |
| Leachate from Sludge Drying Bed               | 8.8 m <sup>3</sup> /day     | 2.8 m <sup>3</sup> /day     |
| Total   | 6,448.6 m <sup>3</sup> /day | 5,870.2 m <sup>3</sup> /day |
| dopted Flow Rate: 6,448.6 m <sup>3</sup> /day |                             |                             |
| Io of the Tank: 1                             |                             |                             |
| etention Time: 0.5 hours                      |                             |                             |

(2) Design Calculation

- Capacity of the Tank: 6,448.6 m<sup>3</sup>/day X 0.5 / 24 = 135 m<sup>3</sup>

| Reservoir Tank |                   |         |                      |  |
|----------------|-------------------|---------|----------------------|--|
| Dimension:     | 5.5 m X           | 7.0 m X | 3.5 m H(Water Depth) |  |
| Capacity:      | $135 \text{ m}^3$ |         |                      |  |
| <b>2.5. Reservoir Tank Mixer</b> (1) Design Conditions         - Capacity of the Tank:       135 m <sup>3</sup> - Mixing Method: Submergible Mixer         - Mixing Strength:       1.0 m <sup>3</sup> /m <sup>3</sup> /hour         - No of Mixer:       1  |
|--|
| <ul> <li>(2) Design Calculation</li> <li>- Capacity of the Mixer:</li> <li>135 m<sup>3</sup> X 1.0 m<sup>3</sup>/m<sup>3</sup>/hour / 60 / 1 unit = 2.3 m<sup>3</sup>/min</li> </ul>   |
| Reservoir Tank Mixer<br>Capacity:2.6 m³/min X dia.250 mm X1.5 kW X1 Unit   |
| <ul> <li>2.6. Raw Water Pump</li> <li>(1) Design Conditions <ul> <li>Flow Rate:</li> <li>6,448.6 m<sup>3</sup>/day</li> <li>No of Pump:</li> <li>2 (1 for duty, 1 for stand-by)</li> </ul> </li> </ul>   |
| (2) Design Calculation<br>- Capacity of the Pump:<br>$6,448.6 \text{ m}^3/\text{day}/24/60 / 1 \text{ unit} = 4.5 \text{ m}^3/\text{min}$  |
| Raw Water Pump<br>Capacity:5.1 m³/min X17 mH X dia250 mm X30 kW X2 Units   |
| <ul> <li>2.7. Distribution Gutter 1</li> <li>(1) Design Conditions <ul> <li>Flow Rate from Raw Water Pump:</li> <li>6,448.6 m<sup>3</sup>/day(Dry Season)</li> <li>5,870.2 m<sup>3</sup>/day(Rainy Season)</li> <li>Adopted Flow Rate:</li> <li>6,448.6 m<sup>3</sup>/day</li> </ul> </li> <li>No of Chamber: 1 <ul> <li>Retention Time:</li> <li>1 min</li> </ul> </li> </ul> |
| (2) Design Calculation<br>- Capacity of the Chamber:<br>$6,448.6 \text{ m}^3/\text{day X}$ 1 min / 60 / 24 = 4.5 m <sup>3</sup>  |
| Distribution Gutter 1Dimension:1.0 m XCapacity:6.63 m³   |

# 2.8. Floating Sponge Filtration Tank (FSF)

2

(1) Design Conditions

- No of Tank:
- Wastewater Flow Rate and Quality:

Calculated Flow Rate and Quality (Dry Season)

|                          | Flow Rate             | Flow Rate T-BOD |          | S-B    | OD       | TSS    |          |
|--------------------------|-----------------------|-----------------|----------|--------|----------|--------|----------|
|                          | (m <sup>3</sup> /day) | (mg/l)          | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |
| Raw Wastewater           | 5,000.0               | 195             | 975.0    | 130    | 650.0    | 205    | 1,025.0  |
| Overflow from HTF        | 284.5                 | 116             | 33.0     | 98     | 27.9     | 50     | 14.2     |
| Supernatant from PST     | 1,119.6               | 122             | 136.2    | 85     | 94.8     | 212    | 237.1    |
| Supernatant from BS      | 35.7                  | 541             | 19.3     | 500    | 17.9     | 1,528  | 54.6     |
| Leachate from Drying Bed | 8.8                   | 529             | 4.7      | 500    | 4.4      | 1,114  | 9.8      |
| Total                    | 6,448.6               | 181             | 1,168.2  | 123    | 795.0    | 208    | 1,340.7  |

### Calculated Flow Rate and Quality (Rainy Season)

|                          | Flow Rate             | low Rate T-BOD |          | S-B    | OD       | TSS    |          |  |
|--------------------------|-----------------------|----------------|----------|--------|----------|--------|----------|--|
|                          | (m <sup>3</sup> /day) | (mg/l)         | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |  |
| Raw Wastewater           | 5,000.0               | 100            | 500.0    | 70     | 350.0    | 90     | 450.0    |  |
| Overflow from HTF        | 285.4                 | 71             | 20.3     | 54     | 15.4     | 50     | 14.3     |  |
| Supernatant from PST     | 570.5                 | 67             | 38.0     | 41     | 23.1     | 114    | 65.1     |  |
| Supernatant from BS      | 11.5                  | 590            | 6.8      | 500    | 5.8      | 1,522  | 17.5     |  |
| Leachate from Drying Bed | 2.8                   | 562            | 1.6      | 500    | 1.4      | 1,107  | 3.1      |  |
| Total                    | 5,870.2               | 97             | 566.7    | 67     | 395.7    | 94     | 550.0    |  |

#### Input Value for Convergent Calculation

|                      | Flow Rate   | T-BOD  |          | S-BOD  |          | TSS    |          |
|----------------------|-------------|--------|----------|--------|----------|--------|----------|
|                      | $(m^3/day)$ | (mg/l) | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |
| Total (Dry Season)   | 6,448.6     | 181    | 1,168.2  | 123    | 795.3    | 208    | 1,340.6  |
| Total (Rainy Season) | 5,885.2     | 96     | 566.9    | 67     | 395.7    | 93     | 549.9    |

- Adopted Flow Rate:  $6,448.6 \text{ m}^3/\text{day}$ 

- Surface Loading Rate:  $150 \text{ m}^3/\text{m}^2/\text{day}$ 

- Height of Sponge Media: 0.6 m

- TSS after filtration: 50 mg/l

- P-BOD Removal Rate by FSF: 0.9143 X (TSS Removal Rate) (%) (P-BOD) = (T-BOD) - (S-BOD)

- S-BOD Removal Rate by FSF: 20 %

- Frequency of Backwashing: TSS Conc. X Surface Loading rate / 0.83

# (2) Design Calculation

- Surface Area: 6,448.6 m<sup>3</sup>/day / 150 m<sup>3</sup>/m<sup>2</sup>/day / 2 units = 22 m<sup>2</sup>/Tank

Floating Sponge Filtration Tank (FSF)

| Dimension:      | 3 m X        | 8 m X                                | 0.6 m H(heigh             | t of Sponge N | Iedia) X 2 Tanks        |
|-----------------|--------------|--------------------------------------|---------------------------|---------------|-------------------------|
| Surface Area of | Sponge Media | Required:                            | 24.2 m <sup>2</sup> /Tank | Adopted:      | 24 m <sup>2</sup> /Tank |
| Surface Loading | g: 134       | m <sup>3</sup> /m <sup>2</sup> /day( | Dry Season)               |               |                         |
|                 | 122          | $m^3/m^2/day($                       | Rainy Season)             |               |                         |

- TSS and BOD Removal TSS Dry Season 208 mg/l -Removed: 50 mg/l =158 mg/l Removal Rate: ( 208 mg/l - 50 mg/l) / 208 mg/l = 76.0 %Rainy Season Removed: 93 mg/l -50 mg/l =43 mg/l Removal Rate: (93 mg/l - 50 mg/l)/93 mg/l = 46.2 % S-BOD Dry Season: Removed: 123 mg/l X 20 %= 25 mg/l Remaining: 123 mg/l - 25 mg/l =98 mg/l Rainy Season Removed: 67 mg/l X 20 %= 13 mg/l 67 mg/l - 13 mg/l = Remaining: mg/l 54 P-BOD Dry Season: Removed: (181 mg/l - 123 mg/l) X 76.0 X 0.9143 % =40 mg/l Remaining: 181 mg/l - 123 mg/l - 40 mg/l = 18 mg/lRainy Season Removed: (96 mg/l - 67 mg/l) X 46.2 X 0.9143 % =12 mg/l Remaining: 96 mg/l - 67 mg/l - 12 mg/l = 17 mg/l T-BOD Dry Season: Removed: 25 mg/l + 40 mg/l = 65 mg/l181 mg/l - 65 mg/l = 116 mg/lRemaining: Rainy Season Removed: 13 mg/l + 12 mg/l = 25 mg/l96 mg/l - 25 mg/l = 71 mg/l Remaining: - Amount of Backwashing Water per event 24.2 m<sup>2</sup>/Tank X 1.2 mH = 29  $m^3/Tank/time$ - Frequency of Backwashing  $134 \text{ m}^3/\text{m}^2/\text{day}$  / Dry Season: 208 mg/l X 2 Tanks X 0.83kg/m<sup>2</sup>/day /1,000 17 times/day/Tank =  $122 m^{3}/m^{2}/day /$ 93 mg/l X 2 Tanks X 0.83kg/m<sup>2</sup>/day /1,000 Rainy Season: 7 times/day/Tank - Total Amount of Backwashing Water per day 29 m<sup>3</sup>/Tank/time X 2 Tanks X 17 times/day/Tank = 986.0  $m^{3}/day$ Dry Season:  $29 \text{ m}^3/\text{Tank/time X}$ Rainy Season: 2 Tanks X 7 times/day/Tank =  $406.0 \text{ m}^3/\text{day}$ 

- Flow Rate and Quality of Effluent from FSF

|              | Flow Rate   | T-BOD  |          | S-BOD  |          | TSS    |          |
|--------------|-------------|--------|----------|--------|----------|--------|----------|
|              | $(m^3/day)$ | (mg/l) | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |
| Dry Season   | 5,462.6     | 116    | 633.7    | 98     | 535.3    | 50     | 273.1    |
| Rainy Season | 5,479.2     | 71     | 389.0    | 54     | 295.9    | 50     | 274.0    |

- Flow Rate and Quality of Backwashing Water

|              | Flow Rate   | T-BOD  |          | w Rate T-BOD S-BOD TSS |          | T-BOD S-BOD |          | SS |
|--------------|-------------|--------|----------|------------------------|----------|-------------|----------|----|
|              | $(m^3/day)$ | (mg/l) | (kg/day) | (mg/l)                 | (kg/day) | (mg/l)      | (kg/day) |    |
| Dry Season   | 986.0       | 278    | 274.5    | 98                     | 96.6     | 1,083       | 1,067.5  |    |
| Rainy Season | 406.0       | 192    | 78.1     | 54                     | 21.9     | 680         | 275.9    |    |

## 2.9. Distribution Gutter 2

(1) Design Conditions

- Flow Rate from Raw Water Pump: 5,462.6 m<sup>3</sup>/day(Dry Season) 5,479.2 m<sup>3</sup>/day(Rainy Season)
- Adopted Flow Rate:  $5,479.2 \text{ m}^3/\text{day}$
- No of Chamber: 1

- Retention Time: 0.5 min

(2) Design Calculation

- Capacity of the Chamber:

 $5,479.2 \text{ m}^3/\text{day X}$  0.5 min / 60 / 24 = 2.0 m<sup>3</sup>

Distribution Gutter 2 Dimension: 1.6 m x 2 m X 0.65 m H(Water Depth) Capacity: 2.08 m<sup>3</sup>

#### 2.10. High Rate Trickling Filter (HTF)

(1) Design Conditions

- No of Tank:
- No of Chamber: 4 /Tank ( 8 chambers, total)
- BOD Loading Rate:  $1.6 \text{ kg-BOD/m}^3/\text{day}(A)$
- height of Filter Media: 2.5 m(B)

2

- TSS in Effluent from HTF: 6.2335 X Ln(*A*) + 22.233
- S-BOD in Effluent from HTF: (0.7538 X Ln(A) +2.6562) X (9.87715 X  $B^{-0.92}$ ) / 4.25
- P-BOD in Effluent from HTF: 0.9143 X (TSS in Effluent)
- Frequency of Backwashing: Every 8 days
- Soaking Time: 10 hours/time
- Media Porosity: 90%

(2) Design Calculation

- Flow Rate and Quality of Influent to HTF

|              | Flow Rate   | T-BOD  |          | S-BOD  |          | TSS    |          |
|--------------|-------------|--------|----------|--------|----------|--------|----------|
|              | $(m^3/day)$ | (mg/l) | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |
| Dry Season   | 5,462.6     | 116    | 633.7    | 98     | 535.3    | 50     | 273.1    |
| Rainy Season | 5,479.2     | 71     | 389.0    | 54     | 295.9    | 50     | 274.0    |

- Capacity of HTF:

From BOD Loading Rate:

| Dry Season:          | $633.7 \text{ kg/day} / 1.6 \text{ kg/m}^3/\text{day} / 2 \text{ units} =$ | 199 m <sup>3</sup> /Tank |
|----------------------|--|--------------------------|
|                      | $199 \text{ m}^3$ /Tank / $2.5 \text{ m} = 80 \text{ m}^2$ /Tank           |                          |
| Rainy Season:        | $389.0 \text{ kg/day} / 1.6 \text{ kg/m}^3/\text{day} / 2 \text{ units} =$ | 122 m <sup>3</sup> /Tank |
|                      | $122 \text{ m}^3/\text{Tank} / 2.5 \text{ m} = 49 \text{ m}^2/\text{Tank}$ |                          |
| Adopted Surface Area | 80 m <sup>2</sup> /Tank  |                          |

High Rate Trickling Filter (HTF)

| 0 0               |  |  |
|-------------------|--|--|
| Dimension: Octago | on Dia. 10.0 m X 2.5 m H(Hei               | ight of Filter Media) X 2 Tanks            |
| Capacity: 205     | $m^3$ , Surface Area of HTF: 82 $m^2/$     | Tank                                       |
| Surface Loading:  | 16.7 $m^3/m^2/day$ (Dry Season)            | 16.8 $m^3/m^2/day$ (Rainy Season)          |
| BOD Loading:      | 1.6 kg-BOD/m <sup>3</sup> /day(Dry Season) | 1 kg-BOD/m <sup>3</sup> /day(Rainy Season) |

- TSS in Effluent  $1.6 \text{ kg-BOD/m}^3/\text{day}) + 22.233 = 26 \text{ mg/l}$ 6.2335 X Ln( -P-BOD in Effluent 0.9143 X 26 mg/l = 24 mg/l-S-BOD in Effluent  $2.5 \text{ m}^{-0.92}$ ) / 4.25 =1.6 kg-BOD/m<sup>3</sup>/day) +2.6562) X (9.87715 X (0.7538 X Ln( 4 mg/l From conservative point of view, S-BOD in Effluent is set at 10 mg/l -T-BOD in Effluent 24 mg/l + 10 mg/l = 34 mg/l- Amount of Overflow Dry Season: 5,462.6  $m^3/day / 2 tanks /$  $284.5 \text{ m}^3/\text{day}$ 4 chambers/tank X 10 hours/24 = Rainy Season: 10 hours/24 =285.4 m<sup>3</sup>/day  $5,479.2 \text{ m}^3/\text{day}/2 \text{ tanks}/$ 4 chambers/tank X - Amount of Wastewater per event per chamber  $\pi/4$  X (Dia. 10.0 m)<sup>2</sup> X 2.5 mH / 49.1 m<sup>3</sup>/time/chamber 4 chamber/Tank = - Daily Average of Wastewater 49.1  $m^3$ /time/chamber X 2 Tanks / 49.1  $m^{3}/day$ 4 chamber/Tank X 8 days =

- Flow Rate and Quality of Overflow from HTF

|              | Flow Rate   | T-BOD  |          | S-BOD  |          | TSS    |          |
|--------------|-------------|--------|----------|--------|----------|--------|----------|
|              | $(m^3/day)$ | (mg/l) | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |
| Dry Season   | 284.5       | 116    | 33.0     | 98     | 27.9     | 50     | 14.2     |
| Rainy Season | 285.4       | 71     | 20.3     | 54     | 15.4     | 50     | 14.3     |

- Flow Rate and Quality of Effluent from HTF

|              | Flow Rate   | T-BOD  |          | S-BOD  |          | TSS    |          |
|--------------|-------------|--------|----------|--------|----------|--------|----------|
|              | $(m^3/day)$ | (mg/l) | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |
| Dry Season   | 5,129.0     | 34     | 174.4    | 10     | 51.3     | 26     | 133.4    |
| Rainy Season | 5,144.7     | 34     | 174.9    | 10     | 51.4     | 26     | 133.8    |

- Flow Rate and Quality of Wastewater from HTF per event

|              | Flow Rate               | T-BOD  |          | S-B    | OD       | TSS    |          |  |
|--------------|-------------------------|--------|----------|--------|----------|--------|----------|--|
|              | (m <sup>3</sup> /event) | (mg/l) | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |  |
| Dry Season   | 49.1                    | 34     | 1.7      | 10     | 0.5      | 26     | 1.3      |  |
| Rainy Season | 49.1                    | 34     | 1.7      | 10     | 0.5      | 26     | 1.3      |  |

### 2.11. Distribution Gutter 3

(1) Design Conditions

- Flow Rate from Raw Water Pump: 5,129.0 m<sup>3</sup>/day(Dry Season) 5,144.7 m<sup>3</sup>/day(Rainy Season)
- Adopted Flow Rate:  $5,144.7 \text{ m}^3/\text{day}$
- No of Chamber: 1

- Retention Time: 1 min

(2) Design Calculation

- Capacity of the Chamber:

5,144.7 m<sup>3</sup>/day X 1 min / 60 / 24 =  $3.6 \text{ m}^3$ 

Distribution Gutter 3 Dimension: 3.9 m X 1.1 m X 1.3 m H(Water Depth) Capacity: 5.577 m<sup>3</sup>

#### 2.12. Final Solid Liquid Separation Tank(SLS)

(1) Design Conditions - No of Tank: 2 - Adopted Flow Rate:  $5,144.7 \text{ m}^3/\text{day}$ 150  $m^3/m^2/day$  at Filtering Part - Surface Loading Rate: - Height of Sponge Media: 0.7 m - TSS Removal Rate by SLS: 0.2549 X (TSS conc. in Influent to SLS) +78.088 (%) - P-BOD in Effluent from SLS: 1.4008 X (TSS conc. in Effluent from SLS) (mg/l) - S-BOD Removal Rate by SLS: Not Removed - Concentration of Settled Sludge: 5,000 mg/l - TSS Collection Rate by Settling: 0.8 3 kg-TSS/m<sup>2</sup> - Frequency of Washing: Every - Time for Backwashing: 30 min (2) Design Calculation - Surface Area of Filtering Part: 18 m<sup>2</sup>/Tank  $5,145 \text{ m}^3/\text{day}$  /  $150 \text{ m}^{3}/\text{m}^{2}/\text{day}$  / 2 Tanks = Final Solid Liquid Separation Tank(SLS) 4.0 m X Dimension: 5.0 m X 0.7 m H(height of Filter) (Filtering Part) 20.0 m<sup>2</sup>/Tank Surface Area of Filter: 129  $m^3/m^2/day$ (Dry Season) Surface Loading of Filtering Part: 129 m<sup>3</sup>/m<sup>2</sup>/day(Rainy Season)

- TSS Removal Rate: 0.2549 X 26 mg/l + 78.088 =84.7 % From conservative point of view, TSS Removal Rate is set at 60 % - TSS in Effluent: 26 mg/l X (1 -60 %) = 11.0 mg/l 4,999.0 m<sup>3</sup>/day X 55.0 kg/day Dry Season 11.0 mg/l / 1000 =Rainy Season  $5,014.7 \text{ m}^3/\text{day X}$ 11.0 mg/l / 1000 =55.2 kg/day -P-BOD in Effluent 1.4008 X 11.0 mg/l =16.0 mg/l -S-BOD in Effluent : 10 mg/l -T-BOD in Effluent 16.0 mg/l +10.0 mg/l =26.0 mg/l - Frequency of Washing 20.0 m<sup>2</sup>/Tank /  $3 \text{ kg-TSS/m}^2$ ) 24 hours/day /( 2 Tanks / Dry Season 133 kg/day / = every 22 hours/Tank 20.0 m<sup>2/</sup>Tank /  $3 \text{ kg-TSS/m}^2$ ) Rainy Season 24 hours/day /( 134 kg/day / 2 Tanks / = every 22 hours/Tank - Amount of Settled Sludge (Daily Average) ( 133.4 kg/day -Dry Season 55 kg/day) X 0.8 = 62.7 kg/day 5,000 mg/l/1000 =12.6  $m^{3}/day$ 62.7 kg/day / Rainy Season ( 133.8 kg/day -55.2 kg/day) X 62.9 kg/day 0.8 = 62.9 kg/day / 5,000 mg/l/1000 = $12.6 \text{ m}^3/\text{day}$ - Amount of TSS reaching to the Filter (Daily Average) Dry Season 133.4 kg/day -55.0 kg/day-62.7 kg/day = 15.7 kg/day 133.8 kg/day -Rainy Season 55.2 kg/day-62.9 kg/day = 15.7 kg/day -Amount of Washing Water Dry Season 129  $m^{3}/m^{2}/day X$ 20.0  $m^2/Tank X$ 53.8 m<sup>3</sup>/Tank/time 30 min/time / 1,440 =53.8 m<sup>3</sup>/Tank/time X 24 / 22 X 2 Tanks = 117.4  $m^{3}/day$ Rainy Season 129  $m^{3}/m^{2}/day X$ 20.0  $m^3$ /Tank X 30 min/time / 1,440 =53.8 m<sup>3</sup>/Tank/time 53.8 m<sup>3</sup>/Tank/time X 24 / 117.4  $m^{3}/day$ 22 X 2 Tanks =

- Flow Rate and Quality of Effluent from SLS (Daily Average)

|              | Flow Rate   | T-BOD  |          | S-BOD  |          | TSS    |          |
|--------------|-------------|--------|----------|--------|----------|--------|----------|
|              | $(m^3/day)$ | (mg/l) | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |
| Dry Season   | 4,999.0     | 26.0   | 130.0    | 10.0   | 50.0     | 11.0   | 55.0     |
| Rainy Season | 5,014.7     | 26.0   | 130.4    | 10.0   | 50.1     | 11.0   | 55.2     |

- Flow Rate and Quality of Settled Sludge from SLS (Daily Average)

|              | Flow Rate   | T-BOD  |          | S-B    | OD       | TSS    |          |  |
|--------------|-------------|--------|----------|--------|----------|--------|----------|--|
|              | $(m^3/day)$ | (mg/l) | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |  |
| Dry Season   | 12.6        | 2,817  | 35.5     | 10     | 0.1      | 5,000  | 62.7     |  |
| Rainy Season | 12.6        | 2,825  | 35.6     | 10     | 0.1      | 5,000  | 63.0     |  |

- Flow Rate and Quality of Washing Water from SLS (Daily Average)

|              | Flow Rate   | T-BOD  |          | S-B    | OD       | TSS    |          |  |
|--------------|-------------|--------|----------|--------|----------|--------|----------|--|
|              | $(m^3/day)$ | (mg/l) | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |  |
| Dry Season   | 117.4       | 76     | 8.9      | 10     | 1.2      | 134    | 15.7     |  |
| Rainy Season | 117.4       | 76     | 8.9      | 10     | 1.2      | 134    | 15.7     |  |

2.13. Chlorination Tank (1) Design Conditions - Flow Rate: 5,014.7 m<sup>3</sup>/day - Adopted Flow Rate: - No of the Tank: 1 - Retention Time: 15 min (2) Design Calculation - Capacity of the Tank: 5,014.7 m<sup>3</sup>/day X 15 / 60 / 24 = 53  $m^3$ Chlorination Tank Dimension: 2.0 m X 16.2 m X 2.0 m H(Water Depth) 58.3 m<sup>3</sup> 64.8 m<sup>3</sup>/Tank Capacity required: Adopted: 2.14. Chlorine Dosing Pump (1) Design Conditions - Chlorine Dosing Rate: 3 mg/l - Effective Chlorine Conc.: 70% - Conc. of Chlorine Solution: 12% - No of Pump: 2 ( 1 for duty, 1 for stand-by) (2) Design Calculation - Chlorine Consumption: Dry Season 4,999.0 m3/day X mg/1 = 15 kg/day 3 15 kg/day / 70% = 21.5 kg/day (Solid Chemical) 15 kg/day / 12% = 125 L/day (Solution) Rainy Season: 15.1 kg/day 5,014.7 m3/day X mg/l =3 15.1 kg/day / 70% = 21.6 kg/day (Solid Chemical) 15.1 kg/day / 12% =126 L/day (Solution) Adopted Flow Rate: 126 L/day - Capacity of the Pump: 126.0 L/day / 24 /60 / 0.09 L/min 1 unit =Chlorine Dosing Pump 0.3 MPa X 0.2 kW X 2 Units Capacity: 0.4 L/min X 2.15. Chlorine Solution Tank (1) Design Conditions - Polymer Consumption: 126 L/day - No of the Tank: 1 - Retention Time: 10 day (2) Design Calculation - Capacity of the Tank: 1.26 m<sup>3</sup>/Tank 126 L/day X 10 day / Tank /1000= 1 Chlorine Solution Tank Dimension: Dia. 1.2 m X 1.5 m H X 1 Tanks 1.6 m<sup>3</sup>/Tank X Capacity: 1 Tanks

#### A6-56

#### 2.16. Storage Tank

(1) Design Conditions

- No of the Tank:

- Retention Time: 2 hours

- Flow Rate of Inlet

|                            | Dry Season                  | Rainy Season              |
|----------------------------|-----------------------------|---------------------------|
| Backwashing Water from FSF | 986.0 m <sup>3</sup> /day   | 406.0 m <sup>3</sup> /day |
| Backwashing Water from SLS | 117.4 m <sup>3</sup> /day   | 117.4 m <sup>3</sup> /day |
| Wastewater from HTF        | 49.1 m <sup>3</sup> /day    | 49.1 m <sup>3</sup> /day  |
| Supernatant from ST        | 62.0 m <sup>3</sup> /day    | 24.1 m <sup>3</sup> /day  |
| Total                      | 1,214.5 m <sup>3</sup> /day | 596.6 m <sup>3</sup> /day |

- Adopted Flow Rate:

1,214.5 m<sup>3</sup>/day

(2) Design Calculation

- Capacity of the Tank:

1,214.5 m<sup>3</sup>/day X 2 / 24 =  $102 \text{ m}^3$ 

1

| Storage Tank |                     |       |                    |  |
|--------------|---------------------|-------|--------------------|--|
| Dimension:   | 5.5 m X             | 7 m X | 3 m H(Water Depth) |  |
| Capacity:    | $115.5 \text{ m}^3$ |       |                    |  |

# 2.17. Storage Tank Mixer

(1) Design Conditions

- Capacity of the Tank: 115.5 m<sup>3</sup>

1

- Mixing Method: Submergible Mixer
- Mixing Strength:  $1.0 \text{ m}^3/\text{m}^3/\text{hour}$
- No of Mixer:

(2) Design Calculation

- Capacity of the Mixer:

 $115.5 \text{ m}^3 \text{ X}$  1.0 m<sup>3</sup>/m<sup>3</sup>/hour / 60 / 1 unit = 2 m<sup>3</sup>/min

Storage Tank Mixer Capacity: 2.2 m<sup>3</sup>/min X dia. 250 mm X 1.5 kW X 1 Unit

### 2.18. Backwashing Water Transfer Pump

(1) Design Conditions

- Flow Rate:  $1,214.5 \text{ m}^3/\text{day}$
- No of Pump: 2 ( 1 for duty, 1 for stand-by)

(2) Design Calculation

#### - Capacity of the Pump:

1,214.5 m<sup>3</sup>/day) /24/60 / 1 unit =  $0.9 \text{ m}^3/\text{min}$ 

| Backwashing Wate | er Transfer Pump          |   |          |         |      |     |      |   |       |  |
|------------------|---------------------------|---|----------|---------|------|-----|------|---|-------|--|
| Capacity:        | 1.1 m <sup>3</sup> /min X | 6 | mH X dia | 125x100 | mm X | 3.7 | kW X | 2 | Units |  |

### 2.19. Primary Sedimentation Tank

(1) Design Conditions

- Flow Rate and Quality

Dry Season

| 5                          |             |        |          |        |          |        |          |
|----------------------------|-------------|--------|----------|--------|----------|--------|----------|
|                            | Flow Rate   | T-E    | T-BOD    |        | S-BOD    |        | SS       |
|                            | $(m^3/day)$ | (mg/l) | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |
| Backwashing Water from FSF | 986.0       | 278    | 274.5    | 98.00  | 96.6     | 1,083  | 1,067.5  |
| Wastewater from HTF        | 49.1        | 34     | 1.7      | 10     | 0.5      | 26     | 1.3      |
| Backwashing Water from SLS | 117.4       | 76     | 8.9      | 10     | 1.2      | 134    | 15.7     |
| Supernatant from ST        | 62.0        | 400    | 24.8     | 76     | 4.6      | 1,631  | 101.1    |
| Total                      | 1,214.5     | 255    | 309.8    | 85     | 102.9    | 976    | 1,185.6  |

Rainy Season

|                            | Flow Rate             | T-F    | BOD      | S-B    | OD       | TSS    |          |
|----------------------------|-----------------------|--------|----------|--------|----------|--------|----------|
|                            | (m <sup>3</sup> /day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |
| Backwashing Water from FSF | 406.0                 | 192    | 78.0     | 54     | 21.9     | 680    | 276.1    |
| Wastewater from HTF        | 49.1                  | 34     | 1.7      | 10     | 0.5      | 26     | 1.3      |
| Backwashing Water from SLS | 117.4                 | 76     | 8.9      | 10     | 1.2      | 134    | 15.7     |
| Supernatant from ST        | 24.1                  | 424    | 10.2     | 31     | 0.6      | 1,340  | 32.3     |
| Total                      | 596.6                 | 166    | 98.8     | 41     | 24.2     | 545    | 325.4    |

- Adopted Flow Rate:

 $35 \text{ m}^3/\text{m}^2/\text{day}$ - Surface Loading Rate:

- Concentration of Settled Sludge: 10,000 mg/l

- TSS Collection Rate by Settling: 0.8

- P-BOD Removal Rate by Sedimentation: 0.8

- S-BOD Removal Rate by Sedimentation: 0 1

- No of the Tank:

- Effective Depth: 3 m 1,214.5 m<sup>3</sup>/day

(2) Design Calculation

# - Surface Area:

 $1,214.5 \text{ m}^3/\text{day} / 35 \text{ m}^3/\text{m}^2/\text{day} / 1 \text{ units} = 35.0 \text{ m}^2/\text{Tank}$ 

| Primary Sedimen   | tation Tank                        |                                       |                                     |  |
|-------------------|------------------------------------|---------------------------------------|-------------------------------------|--|
| Dimension:        | Dia. 7.0 m X                       | 3.0 m H                               |                                     |  |
| Surface Area:     | $38.4 \text{ m}^2$ I               | Retention Time:                       | 2.3 hours                           |  |
| Surface Loa       | ding Rate: 31.63                   | $3 \text{ m}^3/\text{m}^2/\text{day}$ |                                     |  |
|                   |                                    |                                       |                                     |  |
| - Amount of TSS   | in Settled Sludge                  |                                       |                                     |  |
| Dry Season        | 1,185.6 kg/day X                   | 0.8 =                                 | 948.5 kg/day                        |  |
| Rainy Season      | 325.4 kg/day X                     | 0.8 =                                 | 260.3 kg/day                        |  |
|                   |                                    |                                       |                                     |  |
| - Flow Rate of Se | ettled Sludge                      |                                       |                                     |  |
| Dry Season        | 948.5 kg/day /                     | 10,000 mg/1/1                         | $000 = 94.9 \text{ m}^3/\text{day}$ |  |
| Rainy Season      | 260.3 kg/day /                     | 10,000 mg/1/1                         | $000 = 26.1 \text{ m}^3/\text{day}$ |  |
|                   |                                    |                                       |                                     |  |
| - Amount of TSS   | in Supernatant                     |                                       |                                     |  |
| Dry Season        | 1,185.6 kg/day -                   | 948.5 kg/day                          | = 237.1 kg/day                      |  |
| Rainy Season      | 325.4 kg/day -                     | 260.3 kg/day                          | = 65.1  kg/day                      |  |
|                   |                                    |                                       |                                     |  |
| - Flow Rate of Su | pernatant                          |                                       |                                     |  |
| Dry Season        | $1,214.5 \text{ m}^3/\text{day}$ - | 94.9 m <sup>3</sup> /day              | = 1119.6 m <sup>3</sup> /day        |  |
| Rainy Season      | 596.6 m <sup>3</sup> /day -        | 26.1 m <sup>3</sup> /day              | = 570.5 m <sup>3</sup> /day         |  |
|                   | -                                  | -                                     | -                                   |  |

- Flow Rate and Quality of Settled Sludge

|              | Flow Rate   | T-BOD   |          | S-B    | OD       | TSS    |          |  |
|--------------|-------------|---------|----------|--------|----------|--------|----------|--|
|              | $(m^3/day)$ | (mg/l)  | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |  |
| Dry Season   | 94.9        | 1,829.8 | 173.7    | 85.0   | 8.1      | 10,000 | 948.5    |  |
| Rainy Season | 26.1        | 2,328.9 | 60.8     | 41.0   | 1.1      | 10,000 | 260.3    |  |

- Flow Rate and Quality of Supernatant

|              | Flow Rate   | T-BOD  |          | S-B    | OD       | TSS    |          |  |
|--------------|-------------|--------|----------|--------|----------|--------|----------|--|
|              | $(m^3/day)$ | (mg/l) | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |  |
| Dry Season   | 1,119.6     | 121.6  | 136.2    | 85.0   | 94.8     | 211.8  | 237.1    |  |
| Rainy Season | 570.5       | 66.7   | 38.0     | 41.0   | 23.1     | 114.1  | 65.1     |  |

# 2.20. Settled Sludge Transfer Pump

(1) Design Conditions

- Flow Rate:  $94.9 \text{ m}^3/\text{day}$ 

- No of Pump: 2 ( 1 for duty, 1 for stand-by)

(2) Design Calculation

- Capacity of the Pump:

94.9 m<sup>3</sup>/day) /24/60 / 1 unit = 0.1 m<sup>3</sup>/min

| Sludge Transfer | Pump                      |   |          |    |      |                   |
|-----------------|---------------------------|---|----------|----|------|-------------------|
| Capacity:       | 0.2 m <sup>3</sup> /min X | 6 | mH X dia | 50 | mm X | 0.75 kW X 2 Units |

## 2.21. Sludge Thickener

(1) Design Conditions

- Sludge Loading Rate: 60 kg/m<sup>2</sup>/day
- Surface Loading Rate: 20  $m^3/m^2/day$
- Water Depth: 4 m
- No of the Tank: 1
- Sludge Recovery Rate: 90%
- Thickened Sludge Conc.: 20,000 mg/l
- Flow Rate and Quality of Inlet

#### Dry Season

|                           | Flow Rate   | Flow Rate T-BOD |          | S-BOD  |          | TSS    |          |
|---------------------------|-------------|-----------------|----------|--------|----------|--------|----------|
|                           | $(m^3/day)$ | (mg/l)          | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |
| Thickened Sludge from PST | 94.9        | 1,830           | 173.7    | 85     | 8.1      | 10,000 | 948.5    |
| Settled Sludge from SLS   | 12.6        | 2,817           | 35.5     | 10     | 0.1      | 5,000  | 62.7     |
| Total                     | 107.5       | 1,946           | 209.2    | 76     | 8.2      | 9,407  | 1,011.2  |

Rainy Season

|                           | Flow Rate             | w Rate T-BOD |          | S-BOD  |          | TSS    |          |
|---------------------------|-----------------------|--------------|----------|--------|----------|--------|----------|
|                           | (m <sup>3</sup> /day) | (mg/l)       | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |
| Thickened Sludge from PST | 26.1                  | 2,329        | 60.8     | 41     | 1.1      | 10,000 | 260.3    |
| Settled Sludge from SLS   | 12.6                  | 2,825        | 35.6     | 10     | 0.1      | 5,000  | 63.0     |
| Total                     | 38.7                  | 2,491        | 96.4     | 31     | 1.2      | 8,354  | 323.3    |

- Adopted Flow Rate: 107.5 m<sup>3</sup>/day

- Adopted Amount of TSS: 1,011.2 kg/day

| (2) Design Calculation   |    |
|--|----|
| - Surface Area of the Thickener:   |    |
| From Sludge Loading Rate   |    |
| $1,011.2 \text{ kg/day} / 60 \text{ kg/m}^2/\text{day} / 1 \text{ Tank} = 16.9 \text{ m}^2$                          |    |
| From Surface Loading Rate  |    |
| $107.5 \text{ m}^3/\text{day} / 20 \text{ m}^3/\text{m}^2/\text{day} / 1 \text{ Tank} = 6.0 \text{ m}^2$             |    |
| Adopted Surface Area $16.9 \text{ m}^2$  |    |
|  |    |
| Sludge Thickener   |    |
| Dimension: Dia. 5.5 m X 4.0 m H  |    |
| Surface Area: $23.7 \text{ m}^2$ Retention Time: $21.2 \text{ hours}$  |    |
| Sludge Loading Rate: $42.67 \text{ kg/m}^2/\text{day}$ Surface Loading Rate: $4.536 \text{ m}^3/\text{m}^2/\text{d}$ | ay |
|  |    |
| - Amount of Thickened Sludge   |    |
| Dry Season 1,011.2 kg/day X 90% = 910.1 kg/day   |    |
| 910.1 kg/day / 20,000 mg/l X 1,000 = $45.5 \text{ m}^3/\text{day}$   |    |
| Rainy Season 323.3 kg/day X 90% = $291.0$ kg/day   |    |
| $291.0 \text{ kg/day} / 20,000 \text{ mg/l X } 1,000 = 14.6 \text{ m}^3/\text{day}$                                  |    |
|  |    |
| - Amount of Supernatant  |    |
| Dry Season $1,011.2 \text{ kg/day} - 910.1 \text{ kg/day} = 101.1 \text{ kg/day}$                                    |    |
| $107.5 \text{ m}^3/\text{day} - 45.5 \text{ m}^3/\text{day} = 62.0 \text{ m}^3/\text{day}$                           |    |
| Rainy Season 323.3 kg/day - $291.0$ kg/day = $32.3$ kg/day   |    |
| $38.7 \text{ m}^3/\text{dav} - 14.6 \text{ m}^3/\text{dav} = 24.1 \text{ m}^3/\text{dav}$                            |    |
| ,  |    |
|  |    |

- Flow Rate and Quality of Thickened Sludge (Daily Average)

|              | Flow Rate   | ate T-BOD |          | S-B    | OD       | TSS    |          |
|--------------|-------------|-----------|----------|--------|----------|--------|----------|
|              | $(m^3/day)$ | (mg/l)    | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |
| Dry Season   | 45.5        | 4,052     | 184.4    | 76     | 3.5      | 20,000 | 910.1    |
| Rainy Season | 14.6        | 5,902     | 86.2     | 31     | 0.5      | 20,000 | 291.0    |

- Flow Rate and Quality of Supernatant (Daily Average)

|              | Flow Rate   | Flow Rate T-BOD |          | S-B    | SOD      | TSS    |          |
|--------------|-------------|-----------------|----------|--------|----------|--------|----------|
|              | $(m^3/day)$ | (mg/l)          | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |
| Dry Season   | 62.0        | 400             | 24.8     | 76     | 4.6      | 1,631  | 101.1    |
| Rainy Season | 24.1        | 424             | 10.2     | 31     | 0.6      | 1,340  | 32.3     |

# 2.22. Thickened Sludge Transfer Pump

(1) Design Conditions

- Flow Rate:  $45.5 \text{ m}^3/\text{day}$
- No of Pump: 2 ( 1 for duty, 1 for stand-by)

(2) Design Calculation

- Capacity of the Pump:

 $45.5 \text{ m}^3/\text{day}/24/60 / 1 \text{ unit} = 0.04 \text{ m}^3/\text{min}$ 

| Raw Water Pump |                           |    |          |       |      |     |      |   |       |
|----------------|---------------------------|----|----------|-------|------|-----|------|---|-------|
| Capacity:      | 0.1 m <sup>3</sup> /min X | 18 | mH X dia | 50x40 | mm X | 2.2 | kW X | 2 | Units |

#### 2.23. Biogas Digester and Biogas Settler

(1) Design Conditions - Flow Rate:  $45.5 \text{ m}^3/\text{day}$ - Loading Rate of Digester: 4 kg-TSS/m<sup>3</sup>/day 910.1 - TSS conc. In Thickened Sludge: kg-TSS/day - Hydraulic Retention Time (HRT): 20 days (Digester + Settler) - Removal Rate of TSS: 40% - Removal Rate of BOD: 80% - CH<sub>4</sub> Generation Rate: 0.3 m<sup>3</sup><sub>N</sub>-CH<sub>4</sub>/kg-TSS Removed  $60 \quad \%^{\rm V}/_{\rm V}$ - CH<sub>4</sub> Conc. In Biogas - Settled Sludge conc.: 50,000 mg/l - Sludge Recovery Rate: 90% (2) Design Calculation - Capacity of the Digester and Settler: 45.5  $m^{3}/day X$ 910 m<sup>3</sup> 20 days =- Capacity of the Digester: 910.1 kg-TSS/day 4 kg-TSS/m<sup>3</sup>/day =  $228 \text{ m}^3$ Biogas Digester Dimension: Dia. 7.5 m X 11.0 m H (Water Depth)  $485.9 \text{ m}^2$ Tank Volume: TSS Loading Rate: 1.87 kg-TSS/m<sup>3</sup>/day HRT 10.6 days **Biogas Settler** Dimension: Dia. 7.5 m X 10.0 m H (Water Depth) 441.7 m<sup>2</sup> Tank Volume: HRT 9.7 days 927.6 m<sup>3</sup> HRT total  $20.3 \text{ m}^3$ Total Volume - TSS after digestion kg/day Dry Season 910.1 kg/day X (1 -40%)= 546.1 291.0 kg/day X (1 -Rainy Season 40%)= 174.6 kg/day - Amount of Digested Sludge 546.1 kg/day X Dry Season 90% = 491.5 kg/day491.5 kg/day / 50,000 mg/l X 1,000 = 9.8  $m^3/day$ Rainy Season 174.6 kg/day X 90% = 157.1 kg/day $3.1 \text{ m}^3/\text{day}$ 157.1 kg/day / 50,000 mg/l X 1,000 = - Amount of Supernatant Dry Season 546.1 kg/day -491.5 kg/day = 54.6 kg/day  $45.5 \text{ m}^{3}/\text{day}$  -9.8  $m^{3}/day =$  $35.7 \text{ m}^3/\text{day}$ 174.6 kg/day -157.1 kg/day = 17.5 kg/day Rainy Season  $14.6 \text{ m}^3/\text{day}$  - $3.1 \text{ m}^3/\text{day} =$ 11.5  $m^{3}/day$ 

- BOD after digestion

| 0            |                     |        |      |        |
|--------------|---------------------|--------|------|--------|
| Dry Season   | 184.4 kg/day X (1 - | 80% )= | 36.9 | kg/day |
| Rainy Season | 86.2 kg/day X (1 -  | 80% )= | 17.2 | kg/day |

- Flow Rate and Quality of Digested Sludge

|              | Flow Rate   | Flow Rate T-BOD |          | S-B    | OD       | TSS    |          |
|--------------|-------------|-----------------|----------|--------|----------|--------|----------|
|              | $(m^3/day)$ | (mg/l)          | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |
| Dry Season   | 9.8         | 1,792           | 17.6     | 500    | 4.9      | 50,000 | 491.5    |
| Rainy Season | 3.1         | 3,371           | 10.4     | 500    | 1.6      | 50,000 | 157.1    |

- Flow Rate and Quality of Supernatant

|              | Flow Rate   | Flow Rate T-BOD |          | S-BOD  |          | TSS    |          |
|--------------|-------------|-----------------|----------|--------|----------|--------|----------|
|              | $(m^3/day)$ | (mg/l)          | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |
| Dry Season   | 35.7        | 541             | 19.3     | 500    | 17.9     | 1,528  | 54.6     |
| Rainy Season | 11.5        | 590             | 6.8      | 500    | 5.8      | 1,522  | 17.5     |

| 1 10 m Rule Of CH4 Ocher | aled           |       |   |                                     |
|--------------------------|----------------|-------|---|-------------------------------------|
| Dry Season 910.1         | kg/day X 40% X | X 0.3 | $m^3_N$ -CH <sub>4</sub> /kg =            | 109.2 $m^3_N$ -CH <sub>4</sub> /day |
| Rainy Season 291.0       | kg/day X 40% X | X 0.3 | $m^3$ <sub>N</sub> -CH <sub>4</sub> /kg = | $34.9 m^3_{\rm N}\text{-}CH_4/day$  |

- Flow Rate of Biogas Generated

| Dry Season   | $109.2 \text{ m}^{3}\text{N}-CH_{4}/day /$                    | $60 \%'/_v X =$  | 182.0 m <sup>3</sup> <sub>N</sub> -Biogas/day |
|--------------|---|------------------|---|
| Rainy Season | $34.9  \text{m}^3_{\text{N}}\text{-}\text{CH}_4/\text{day}$ / | $60 \%' /_v X =$ | 58.2 m <sup>3</sup> <sub>N</sub> -Biogas/day  |

### 2.24. Digested Sludge Transfer Pump

(1) Design ConditionsFlow Rate: 9.8 m<sup>3</sup>/day

- Operation Hour for sludge return: 23 hours/day, 7 days/week
- Operation Hour for desludging: 1 hours/day, 5 days/week
- Sludge Return Rate: 200% of Feeding
- No of Pump: 2 ( 1 for duty, 1 for stand-by)

(2) Design Calculation

| - Capacity of the Pump    | for slud | ge retur | nin | g:    |           |   |        |                               |
|---------------------------|----------|----------|-----|-------|-----------|---|--------|-------------------------------|
| 9.8 m <sup>3</sup> /day X | 200%     | X 7 /    | 7   | X 24/ | 23 / 60 / | 1 | unit = | $0.35 \text{ m}^3/\text{min}$ |

- Capacity of the Pump for desludging: 9.8 m<sup>3</sup>/day / 1 hours/day X 7 / 5 / 60 / 1 unit = 0.23 m<sup>3</sup>/min
- Adopted Design Value  $0.35 \text{ m}^3/\text{min}$

| Digested Sludge | Transfer Pump             |    |          |       |      |     |      |   |       |
|-----------------|---------------------------|----|----------|-------|------|-----|------|---|-------|
| Capacity:       | 0.4 m <sup>3</sup> /min X | 18 | mH X dia | 80x65 | mm X | 5.5 | kW X | 2 | Units |

| <b>2.25. Gas Holder</b> (1) Design Conditions- Flow Rate of Biogas:182.0 $m_N^3/day$ - Retention Time:2 hours- Gas temperature:35 °C- Gas Pressure:2 kPa  |
|---|
| (2) Design Calculation<br>- Flow Rate of Biogas(actual):<br>182.0 $m^{3}_{N}/day X (273.15 + 35) / 273.15 X (101.325 + 2) / 101.325 = 209.4 m^{3}/day$<br>- Capacity of Flare Stack:<br>209.4 $m^{3}/day X = 2 / 24 = 17 m^{3}$ |
| Gas HolderTank Volume:20.0 m²Retention Time2.3 hours  |
| <ul> <li>2.26. Flare Stack</li> <li>(1) Design Conditions <ul> <li>Flow Rate of Biogas: 209.4 m<sup>3</sup>/day</li> <li>Capacity: 3 times of Biogas Flow generated</li> </ul> </li> </ul>                                      |
| (2) Design Calculation<br>- Capacity of Flare Stack:<br>209.4 m <sup>3</sup> /day / 24 X 3 times = 26 m <sup>3</sup> /hour  |
| Flare StackCapacity:30.0 m³/hourOperation Hours7.0 hours/day  |

# **2.** (1

| <ul> <li>2.27. Sludge Drying Bed</li> <li>(1) Design Conditions <ul> <li>Flow Rate:</li> <li>9.8 m<sup>3</sup>/day</li> <li>Solid Conc. in Feeding Sludge:</li> <li>50,000 mg/l</li> <li>Operation Hour:</li> <li>1 hours/day,</li> <li>5 days/week</li> </ul> </li> </ul> |
|--|
| <ul> <li>Moisture Content of Dried Sludge: 50%</li> <li>Solid Recovery Rate: 98%</li> <li>Retention Time: 20 days</li> <li>No of Drying Beds: 20 Beds</li> <li>Sludge Depth of Drying Beds 0.3 m</li> </ul>  |
| (2) Design Calculation   |
| - Amount of Dried Sludge:<br>Dry Season 491.5 kg/day X 98% kg/day = 481.7 kg-DB/day<br>481.7 kg/day / (1- 50%) = 963 kg-WB/day<br>Rainy Season 157.1 kg/day X 98% kg/day = 154.0 kg-DB/day<br>154.0 kg/day / (1- 50%) = 308 kg-WB/day                                      |
| - Surface Area of Drying Bed   |
| 9.8 $m^3/day / 0.3 m = 32.7 m^2/day$   |
| Sludge Drying BedDimension:8 m X5 m X0.3 m H (Sludge Depth)Surface Area:40 m² X20 Beds   |
| - Amount of Leachate   |

Dry Season 9.8 m<sup>3</sup>/day -0.963 tons/day =  $8.8 \text{ m}^3/\text{day}$ Rainy Season: 3.1 m<sup>3</sup>/day - 0.308 tons/day =  $2.8 \text{ m}^3$ / - Flow Rate and Quality of Leachate (Daily Average)  $2.8 \text{ m}^3/\text{day}$ 

|              | Flow Rate   | T-BOD  |          | S-BOD  |          | TSS    |          |
|--------------|-------------|--------|----------|--------|----------|--------|----------|
|              | $(m^3/day)$ | (mg/l) | (kg/day) | (mg/l) | (kg/day) | (mg/l) | (kg/day) |
| Dry Season   | 8.8         | 529    | 4.7      | 500    | 4.4      | 1,114  | 9.8      |
| Rainy Season | 2.8         | 562    | 1.6      | 500    | 1.4      | 1,107  | 3.1      |

#### 2.28. Air Compressor

(1) Design Conditions - LV for FSF : 1.0 m/min 24.0 m<sup>2</sup>/Tank - Surface Area of FSF : - Compressed Air Requirement for Actuators: 0.1 m<sup>3</sup>/min - No of Air Compressor: 2 ( 1 for duty, 1 for stand-by) (2) Design Calculation - Air Compressor Capacity: 24.0 m<sup>2</sup>/Tank X 1.0 m/min + 0.1 m<sup>3</sup><sub>N</sub>/min = 24.1 m<sup>3</sup><sub>N</sub>/min Air Compressor Capacity: 500.0 L<sub>N</sub>/min X 0.8 MPa X 5.5 kW X 2 Units 2.29. Air Blower (1) Design Conditions - LV for HTF : 1.5 m/min - LV for SLS : 0.4 m/min 82.0 m<sup>2</sup>/Tank - Surface Area of HTF : - No of Chamber: 4 /Tank - Surface Area of SLS : 20.0 m<sup>2</sup>/Tank 2 ( 1 for duty, - No of Blower: 1 for stand-by) (2) Design Calculation - Air Requirement for HTF: 82.0  $m^2/Tank /$ 4 chambers X 1.5 m/min = $30.8 \text{ m}^3$ <sub>N</sub>/min - Air Requirement for SLS:  $8.0 \text{ m}^3_{N}/\text{min}$ 20.0  $m^2$ /Tank X 0.4 m/min =  $30.8 \text{ m}^{3}\text{N/min}$ - Blower Capacity: Air Blower 32.7 m<sup>3</sup><sub>N</sub>/min X 3,000 mmH<sub>2</sub>O X Capacity: 30 kWX 2 Units 2.30. Exhaust Fan (1) Design Conditions 5,479.2 m<sup>3</sup>/day - Flow Rate of HTF Inlet : - G/L: 6  $m_N^3$ -Air /  $m^3$ -Wastewater - No of HTF: 2 - Blower Air Flow Rate to HTF 32.7  $m_N^3/min/series$ - Capacity of Exhaust Fan: 110% of Air Flow - No of Fan: 2 (2) Design Calculation - Required Air for Ventilation:  $5,479.2 \text{ m}^3/\text{day}/24/60 \text{ X}$  6  $\text{m}^3_{\text{N}}$ -Air /  $\text{m}^3$ -Wastewater / 2 = 11.5  $\text{m}^3_{\text{N}}/\text{min/unit}$ 11.5  $m_N^3/min/unit < 30.8 m_N^3/min$ - Capacity of the Fan: 30.8  $m_N^3/min X$  $110\% = 33.9 \text{ m}^{3}\text{N/min}$ Exhaust Fan  $36.1 \text{ m}^{3}\text{N/min X}$ 3.0 kPa X Capacity: 3.7 kW X 2 Units

End of Document



# [ANNEX] OUTLINE DESIGN DRAWINGS

# THE PREPARATORY SURVEY ON THE PROJECT SEWERAGE SYSTEM DEVELOPMENT IN THE PHNOM PENH CAPITAL CITY LIST OF DRAWINGS

| TITLE  | SCALE | DWG NO.    | TITLE  | SCALE | DWG NO.    | TITLE  | SCALE | DWG NO. |
|--|-------|------------|--|-------|------------|--|-------|---------|
|  |       |            |  |       |            |  |       |         |
| GENERAL MAP  |       |            | Administration Building                                    |       |            | MECHANICAL AND ELECTRICAL WORK                                       |       |         |
| General Map  |       | GM-001     | Administration Building Floor Plan                         |       | STP-AB-001 | Mechanical Work  |       |         |
| General Note   |       | GM-002     | Administration Building Elevation                          |       | STP-AB-002 | General Flow Diagram   |       | MW-001  |
|  |       |            | Administration Building Detail Section                     |       | STP-AB-003 | Mechanical Equipment Layout for Main Pump Building (1/2)             |       | MW-002  |
| SEWAGE TREATMENT PLANT   |       |            | Administration Building Finish Schedule                    |       | STP-AB-004 | Mechanical Equipment Layout for Main Pump Building (2/2)             |       | MW-003  |
| General  |       |            | Administration Building Structural Drawing                 |       | STP-AB-005 | Mechanical Equipment Section Layout for Main Pump Building (1/4)     |       | MW-004  |
| General Layout of Sewage Treatment Plant                       |       | STP-GN-001 | Administration Building Door & Window Schedule 1           |       | STP-AB-006 | Mechanical Equipment Section Layout for Main Pump Building (2/4)     |       | MW-005  |
| Hydraulic Profile  |       | STP-GN-002 | Administration Building Door & Window Schedule 2           |       | STP-AB-007 | Mechanical Equipment Section Layout for Main Pump Building (3/4)     |       | MW-006  |
| General Layout of Wastewater Treatment Facilities              |       | STP-GN-003 |  |       |            | Mechanical Equipment Section Layout for Main Pump Building (4/4)     |       | MW-007  |
|  |       |            | Landscaping  |       |            | Mechanical Equipment Layout for Filtering Tank (1/4)                 |       | MW-008  |
| Main Pump Building   |       |            | Layout of Yard Piping                                      |       | STP-LS-001 | Mechanical Equipment Layout for Filtering Tank (2/4)                 |       | MW-009  |
| Main Pump Building Plan (1/3)                                  |       | STP-MB-001 | Profile and Detail of Yard Piping                          |       | STP-LS-002 | Mechanical Equipment Layout for Filtering Tank (3/4)                 |       | MW-010  |
| Main Pump Building Plan (2/3)                                  |       | STP-MB-002 | Layout of Pavement, Drainage, Gate & Wall                  |       | STP-LS-003 | Mechanical Equipment Layout for Filtering Tank (4/4)                 |       | MW-011  |
| Main Pump Building Plan (3/3)                                  |       | STP-MB-003 | Detail of Pavement & Drainage                              |       | STP-LS-004 | Mechanical Equipment Section Layout for Filtering Tank (1/4)         |       | MW-012  |
| Main Pump Building Section (1/4)                               |       | STP-MB-004 | Detail of Outfall (1/2)                                    |       | STP-LS-005 | Mechanical Equipment Section Layout for Filtering Tank (2/4)         |       | MW-013  |
| Main Pump Building Section (2/4)                               |       | STP-MB-005 | Detail of Outfall (2/2)                                    |       | STP-LS-006 | Mechanical Equipment Section Layout for Filtering Tank (3/4)         |       | MW-014  |
| Main Pump Building Section (3/4)                               |       | STP-MB-006 | Detail of Gate & Wall                                      |       | STP-LS-007 | Mechanical Equipment Section Layout for Filtering Tank (4/4)         |       | MW-015  |
| Main Pump Building Section (4/4)                               |       | STP-MB-007 | Landscaping Pond   |       | STP-LS-008 | Mechanical Equipment Layout for Solid-liquid Separation Tank         |       | MW-016  |
| Main Pump Building Elevation                                   |       | STP-MB-008 | Layout of Yard Cabling & Lighting                          |       | STP-LS-009 | Mechanical Equipment Section Layout for Solid-liquid Separation Tank |       | MW-017  |
| Main Pump Building Finish Schedule                             |       | STP-MB-009 | Detail of Handhole, Trench Excavation and Yard Lighting    |       | STP-LS-010 | Mechanical Equipment Plan & Section for Chlorination Tank            |       | MW-018  |
| Main Pump Building Door & Window List                          |       | STP-MB-010 |  |       |            | Mechanical Equipment Layout for Sludge Digestion Facilities(1/2)     |       | MW-019  |
|  |       |            | Land Fill  |       |            | Mechanical Equipment Layout for Sludge Digestion Facilities(2/2)     |       | MW-020  |
| Filtering Tank (FSF and HTF)                                   |       |            | Layout Plan of Cofferdam                                   |       | STP-LF-001 |  |       |         |
| Filtering Tank Plan (1/4)                                      |       | STP-HT-001 | Section of Cofferdam(1/2)                                  |       | STP-LF-002 | Electrical Work  |       |         |
| Filtering Tank Plan (2/4)                                      |       | STP-HT-002 | Section of Cofferdam(2/2)                                  |       | STP-LF-003 | Single Line Diagram for Sewage Treatment Plant (1/2)                 |       | EW-001  |
| Filtering Tank Plan (3/4)                                      |       | STP-HT-003 | Layout Plan of Dredging                                    |       | STP-LF-004 | Single Line Diagram for Sewage Treatment Plant (2/2)                 |       | EW-002  |
| Filtering Tank Plan (4/4)                                      |       | STP-HT-004 | Section of Dredging(1/2)                                   |       | STP-LF-005 | Single Line Diagram for Interception Facility                        |       | EW-003  |
| Filtering Tank Section (1/4)                                   |       | STP-HT-005 | Section of Dredging(2/2)                                   |       | STP-LF-006 | System Configuration   |       | EW-004  |
| Filtering Tank Section (2/4)                                   |       | STP-HT-006 | Layout Plan of Landfill                                    |       | STP-LF-007 | Cabling Layout for Power Supply (1/4)                                |       | EW-005  |
| Filtering Tank Section (3/4)                                   |       | STP-HT-007 | Section of Landfill(1/2)                                   |       | STP-LF-008 | Cabling Layout for Power Supply (2/4)                                |       | EW-006  |
| Filtering Tank Section (4/4)                                   |       | STP-HT-008 | Section of Landfill(2/2)                                   |       | STP-LF-009 | Cabling Layout for Power Supply (3/4)                                |       | EW-007  |
|  |       |            |  |       |            | Cabling Layout for Power Supply (4/4)                                |       | EW-008  |
| Solid-Liquid Sepatration Tank (SLS)                            |       |            | INTERCEPTION FACILITY & SEWER PIPE                         |       |            |  |       |         |
| Solid-Liquid Sepatration Tank Plan                             |       | STP-SL-001 | General Layout of Interception Facility & Sewer Pipe (all) |       | ISP-001    | Transformer House  |       |         |
| Solid-Liquid Sepatration Tank Section                          |       | STP-SL-002 | General Layout of Interception Facility & Sewer Pipe (1/3) |       | ISP-002    | Transformer House Plan and Section & Elevation                       |       | TH-001  |
|  |       |            | General Layout of Interception Facility & Sewer Pipe (2/3) |       | ISP-003    | Transformer House Finish Schedule and Door & Window List             |       | TH-002  |
| Chlorination Tank  |       |            | General Layout of Interception Facility & Sewer Pipe (3/3) |       | ISP-004    |  |       |         |
| Chlorination Tank Plan & Section                               |       | STP-CT-001 | Channel Maintenance Road Detail                            |       | ISP-005    |  |       |         |
| Chlorination Tank Elevation                                    |       | STP-CT-002 | Channel Maintenance Road Section (1/2)                     |       | ISP-006    |  |       |         |
| Chlorination Tank House Finish Schedule and Door & Window List |       | STP-CT-003 | Channel Maintenance Road Section (2/2)                     |       | ISP-007    |  |       |         |
|  |       |            | Site Plan of Interception Facility                         |       | ISP-008    |  |       |         |
| Sludge Digestion Facilities                                    |       |            | Section of Interception Facility (1/2)                     |       | ISP-009    |  |       |         |
| Sludge Digestion Facilities Plan & Section (1/2)               |       | STP-SD-001 | Section of Interception Facility (2/2)                     |       | ISP-010    |  |       |         |
| Sludge Digestion Facilities Plan & Section (2/2)               |       | STP-SD-002 | Layout Plan & Sections of Interception Facility            |       | ISP-011    |  |       |         |
|  |       |            |  |       |            |  |       |         |
| Sludge Drying Bed  |       |            |  |       |            |  |       |         |
| Sludge Drying Bed Plan   |       | STP-DB-001 |  |       |            |  |       |         |
| Sludge Drying Bed Plan & Section                               |       | STP-DB-002 |  |       |            |  |       |         |
|  |       |            |  |       |            |  |       |         |



#### **GENERAL NOTES**

#### 1. GENERAL

- 1.1 THESE NOTES SHALL APPLY UNLESS SPECIFICATION OTHERWISE INDICATED IN THE RESPECTIVE DRAWINGS.
- 1.2 UNLESS OTHERWISE SPECIFIED, ALL DIMENSION SHOWN ON THE DRAWINGS ARE IN MILLIMETERS.
- 1.3 ALL DIMENSIONS RELATING TO THE EXISTING STRUCTURES AND FACILITIES SHALL BE VERIFIED BY THE CONTRACTOR BEFORE COMMENCEMENT OF THE WORKS.

#### 2. EARTHWORK

- 2.1 AREAS FOR PERMANENT STRUCTURES AND ALL BORROW PITS, QUARRY AND STOCKPILE SITES SHALL BE CLEARED AND GRUBBED. TOP SOIL SHALL BE STRIPPED BEFORE COMMENCEMENT OF CONSTRUCTION.
- 2.2 BACKFILL SHALL BE PLACED IN HORIZONTAL LAYERS NOT MORE THAN 30 CENTIMETERS THICK AND BE THOROUGHLY COMPACTED IN ACCORDANCE WITH THE SPECIFICATIONS. MAXIMUM SIZE OF ROCK IN THE BACKFILL SHALL BE 150mm.

#### 3. CONCRETE WORK

3.1 CLASSIFICATION OF CONCRETE IS AS SHOWN BELOW :

| CLASS | USAGE   | MINIMUM COMPRESSIVE<br>STRENGTH (28DAYS) |                   |  |  |
|-------|---|--|-------------------|--|--|
|       |   | Kgf/cm <sup>2</sup>                      | N/mm <sup>2</sup> |  |  |
| А     | PRE-STRESSED CONCRETE PILE<br>(PRE-STRESS: MORE THAN 4 N/mm <sup>2</sup> )                      | 400                                      | 40                |  |  |
| B1    | REINFORCED CONCRETE<br>(RELATED SEDIMENT CHAMBER AT Rd.240,<br>MANHOLE, DRAINAGE PIPE AND ETC.) | 240                                      | 24                |  |  |
| B2    | NON-REINFORCED CONCRETE   | 210                                      | 21                |  |  |
| С     | LEVELING CONCRETE AND LEAN CONCRETE   | 180                                      | 18                |  |  |

TYPE OF CONCRETE SHALL BE AS SHOWN IN THE SPECIFICATIONS AND DIRECTED BY THE CONSULTANT.

- 3.2 ALL STRUCTURAL CONCRETE MEMBERS OF ABOVE-GROUND PART SHALL BE PROVIDED WITH 20mm MINIMUM CHAMBER ON ALL EXTERIOR EDGES AND CORNERS.
- 3.3 COVERING IN THE DRAWINGS RELATING TO REINFORCING BAR ARRANGEMENT OF MANHOLE SHALL MEAN THE DISTANCE FROM SURFACE OF THE CONCRETE TO CENTER OF THE MAIN REINFORCING BAR (SEE THE FOLLOWING ILLUSTRATION).



- 3.4 UNLESS OTHERWISE SPECIFIED, THE MINIMUM CONCRETE COVER FOR REINFORCEMENTS MEASURED FROM THE SURFACE OF THE CONCRETE TO THE FACE OF REINFORCING BARS SHALL NOT BE LESS THAN 50 mm.
- 3.5 CONSTRUCTION JOINTS OTHER THAN THOSE SHOWN ON THE PLANS SHALL HAVE THE CONSULTANT'S PRIOR APPROVAL.
- 3.6 ALL REINFORCING STEEL SHALL BE DEFORMED BAR CONFORMING TO JIS G3112.
- 3.7 CLEAR DISTANCE BETWEEN PARALLEL BARS EXCEPT IN COLUMNS AND BETWEEN MULTIPLE LAYERS, SHALL BE NOT LESS THAN 4/3 TIMES MAXIMUM SIZE OF COARSE AGGREGATE.
- 3.8 ALL BAR SPLICE LAPS AND BENDS SHALL CONFORM TO THE MINIMUM REQUIREMENT AS FOLLOWS:

(1) LAP SPLICE, BENDING RADIUS AND LENGTH

# LAP LAP

| JULE    |         |                |               |               |  |  |
|---------|---------|----------------|---------------|---------------|--|--|
| (SD295) | MANHOLE | BOX<br>CULVERT | RADIUS<br>(R) | LENGTH<br>(L) |  |  |
|         | (30D)   | (35D)          | (10.5D)       |               |  |  |
| D13     | 390     | 455            | 140           | 220           |  |  |
| D16     | 480     | 560            | 170           | 267           |  |  |
| D19     | 570     | 665            | 200           | 314           |  |  |
| D22     | 660     | 770            | 240           | 377           |  |  |
| D25     | 750     | 875            | 270           | 424           |  |  |

BENDING RADIUS (r) (mm)

STIRRUP AND HOOP BAR

(2 0D)

26

32

38

44

50

#### 4. OTHER WORKS

- 4.1 UNLESS OTHERWISE SPECIFIED, CEMENT MORTAR FOR STRUCTURES SHALL BE PROPORTIONED BY VOLUME OF ONE (1) PART OF CEMENT TO THREE (3) PARTS OF SAND AND FOR REVETMENT.
- 4.2 PROVISION AND REMOVAL OF THE FALSE WORKS AND CENTERINGS SHALL BE SUBJECT TO APPROVAL BY THE CONSULTANT.
- 4.3 LOCATIONS OF EXISTING DRAINAGE STRUCTURES INDICATED ON THE PLANS SHALL BE VERIFIED IN THE FIELD AND THE LOCATIONS OF PURPOSED DRAINAGE STRUCTURES SHALL BE ADJUSTED TO SUIT FIELD CONDITIONS.
- 4.4 THE FINAL PC PILE LENGTH SHALL BE DETERMINED BY THE RESULT OF STATIC LOAD AND MECHANICAL BORING DATA DURING THE IMPLEMENTATION PERIOD.

#### 5. OTHERS

#### ABBREVIATIONS

| -GENERA | L-                       |     |                            |
|---------|--------------------------|-----|----------------------------|
| В       | WIDTH                    | MIN | MINIMUM                    |
| CTC     | CENTER TO CENTER         | N   | NORTH                      |
| D       | DIAMETER OF DEFORMED BAR | NO  | NUMBER                     |
| DWG     | DRAWING                  | R   | RADIUS                     |
| E       | EAST                     | RB  | REINFORCING BAR            |
| EL      | ELEVATION                | S   | SOUTH                      |
| GL      | GROUND LEVEL             | T,t | THICKNESS                  |
| GH      | GROUND HEIGHT            | Ŵ   | WEST                       |
| FH      | FORMATION HEIGHT         | @   | SPACING OF REINFORCING BAR |
| Н       | HEIGHT                   | ø   | DIAMETER OF ROUND BAR      |
| L       | LENGTH                   |     |                            |
| MAX     | MAXIMUM                  |     |                            |
|         |                          |     |                            |

LEGEND

| PLAN & PROP        | FILES         |   |
|--------------------|---------------|---|
| PROPOSED           | DRAINAGE PIPE |   |
|                    | MANHOLE       |   |
|                    | INLET PIPE    |   |
| AREA OF<br>CUTTING |               |   |
| AREA OF<br>FILLING |               |   |
| BENCH MARK         | <             | - |



|  |  | _ |
|--|--|---|
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |
|  |  |   |

THE PREPARATORY SURVEY ON THE PROJECT FOR SEWERAGE SYSTEM DEVELOPMENT IN THE PHNOM PENH CAPITAL CITY (2) HOOKS

BAR SIZE

D13

D16

D19

D22

(SD295

90° HOOK

HOOKS

(2.5D)

33

40

48

55

63

General Note



#### LEGEND






















# EXTERIOR FINISH SCHEDULE

|                 | MAIN PUMP BUILDING   | CHLORINE SOLUTION TANK HOUSE |
|-----------------|--|------------------------------|
| ROOF            | PORCH   Protection : Concrete thickness 80mm with wire mesh<br>Isolation cloth : Flat yarn cloth   Insulator board : Polystyrene foam board   Waterproofing : Asphalt prepared roofing 30kg/roll   Concrete face : Concrete steel trowel finish   ROOF TOP STAIR HOUSE & PORCH   Protection : Concrete thickness 80mm with wire mesh<br>Isolation cloth : Flat yarn cloth   Insulator board : Polystyrene foam board   Waterproofing : Asphalt prepared roofing 30kg/roll   Concrete face : Concrete steel trowel finish |                              |
| WALL            | Fair-faced concrete AEP  |                              |
| BASEBOARD       | Cement mortar steel trowel finish H=250 and joint  |                              |
| DOORS & WINDOWS | WINDOWS : Aluminum fixed louver<br>DOORS : Steel door SOP  |                              |
| THE OTHER       | PORCH<br>Floor : Concrete steel trowel finish<br>Column : Fair-faced concrete AEP<br>Ceiling : Fair-faced concrete AEP<br>APRON : Concrete steel trowel finish   |                              |

|            | MAIN PUMP BUILDING   | CHLORINE SOLUTION TANK HOUSE   |
|------------|--|--|
| FLOOR AREA | 364.50m <sup>2</sup>   | 34.78m²  |
| USE        | MECHANICAL ROOM,<br>RESIDUE COLLECTION ROOM                              | CHLORINE SOLUTION TANK ROOM  |
| STRUCTURE  | REINFORCE CONCRETE STRUCTURE   | CONCRETE BLOCK STRUCTURE   |
| SCOPE      | ONE-STORY BUILDING   | ONE-STORY BUILDING   |
| HEIGHT     | 8,500mm (from GROUND LEVEL)<br>8,000mm (from SURFACE OF CIVIL STRUCTURE) | 5,200mm (from GROUND LEVEL)<br>3,400mm (from SURFACE OF CIVIL STRUCTURE) |
|            |  |  |
|            |  |  |
|            |  |  |
| REMARKS    |  |  |
|            |  |  |
|            |  |  |

## INTERIOR FINISH SCHEDULE

|                    | ROOM NAME                      | FLOOR<br>LEVEL | FLOOR  | BASEBOARD                        | WALL   | CEILING                 | CEILING HEIGHT<br>(mm) | REMARKS                   |
|--------------------|--------------------------------|----------------|--|----------------------------------|--|-------------------------|------------------------|---------------------------|
| Main Pump Building | MECHANICAL ROOM                | ±0             | Concrete steel trowel finish W/Epoxy resin<br>coating Light-weight concrete t300 | Concrete mortar t200 AEP<br>H300 | Fair-faced concrete AEP                            | Fair-faced concrete AEP | 5,000                  | Side ditch with steel lid |
|                    | RESIDUE COLLECTION<br>ROOM     | ±0             | Concrete steel trowel finish W/Epoxy resin<br>coating Light-weight concrete t300 | Concrete mortar t200 AEP<br>H300 | Fair-faced concrete AEP                            | Fair-faced concrete AEP | 5,000                  | Side ditch with steel lid |
|                    | STAIR ROOM                     | ±0             | Concrete steel trowel finish   | Concrete mortar t200 AEP<br>H150 | Fair-faced concrete AEP                            | Fair-faced concrete AEP | Varies                 |                           |
| CHROLINE SOLUTION  | CHLORINE SOLUTION<br>TANK ROOM | ±0             | Concrete steel trowel finish   | Concrete mortar t200 AEP<br>H150 | Concrete mortar t200 AEP<br>on concrete block wall | Fair-faced concrete AEP | 3400                   |                           |
|                    |                                |                |  |                                  |  |                         |                        |                           |
|                    |                                |                |  |                                  |  |                         |                        |                           |
|                    |                                |                |  |                                  |  |                         |                        |                           |
|                    |                                |                |  |                                  |  |                         |                        |                           |
|                    |                                |                |  |                                  |  |                         |                        |                           |
|                    |                                |                |  |                                  |  |                         |                        |                           |
|                    |                                |                |  |                                  |  |                         |                        |                           |

BUILDING OUTLINE

| MAIN PUMP BUILDING        |   |   |  |                           |                            |  |  |  |  |
|---------------------------|---|---|--|---------------------------|----------------------------|--|--|--|--|
| TYPE<br>KEY NUMBER &      | SD Steel Double Swinging Door                                       | SD Steel Single Swinging Door   | AG Aluminium Fixed Louver                          | AG Aluminium Fixed Louver | SS Steel Shutter           |  |  |  |  |
| QUANTITY                  | 4   | 2 3   | 9  | 2 6                       | 1                          |  |  |  |  |
| ELEVATION                 |   | 5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>5100<br>510<br>51 |  |                           |                            |  |  |  |  |
| LOCATION                  | Entrance, Mechanical Room, Retidue Collection Room                  | Stairs  | Entrance, Mechanical Room, Residue Collection Room | Retidue Collection Room   | Service Entrance           |  |  |  |  |
| FRAME ; MATERIAL & FINISH | Steel S.O.P.  | Steel S.O.P.  | Alminium electro coloring                          | Alminium electro coloring | Steel S.O.P.               |  |  |  |  |
| THRESHOLD or SILL         | sus   | SUS   |  | <u> </u>                  |                            |  |  |  |  |
| DOOR MATERIAL & FINISH    | Steel S.O.P.  | Steel S.O.P.  | Alminium electro coloring                          | Alminium electro coloring | Starl S.O.P.               |  |  |  |  |
| WINDOW<br>& THICKNESS     | 40 mm   | 40 mm   |  |                           |                            |  |  |  |  |
| GLASS & SCREEN            | TP 5mm  | TP Smm  |  | —                         |                            |  |  |  |  |
| HARDWARE                  | Door shook, Door knob, Hinge(SUS), Look,<br>Door stop, Hardware set | Door shock, Door knob, Hinge(SUS), Look,<br>Door stop, Hardware ast   | Flashing, Hardware act                             | Flashing, Hardware set    | Sinatter Box, Hardware set |  |  |  |  |
| REMARKS                   |   |   |  |                           |                            |  |  |  |  |

CHLORINATION TANK HOUSE



NOTES or REVISIONS :



#### SYMBOL LEGEND

WD : Wooden Door WWL : Wooden Window Louver

- AWL : Aluminum Window Louver
- AW : Aluminum Window
- AD : Aluminum Door
- SD : Steel Door SG : Steel Louver
- AG : Aluminum Louver

## FINISH LEGEND

- C.W.P. : Clear Wood Preservative
- S.O.P. : Ready-mixed Synthetic Resin Paint
- A.E.P. : Acrylic Resin Emulsion Paint
- S.V : Oil Stain Varnish



THE PREPARATORY SURVEY ON THE PROJECT FOR SEWERAGE SYSTEM DEVELOPMENT IN THE PHNOM PENH CAPITAL CITY

SEWAGE TREATMENT PLANT Main Pump Building Door & Window List

























## EXTERIOR FINISH SCHEDULE

|                 | CHLORINE SOLUTION TANK HOUSE |  |
|-----------------|------------------------------|--|
| ROOF            |                              |  |
|                 |                              |  |
|                 |                              |  |
|                 |                              |  |
|                 |                              |  |
| WALL            |                              |  |
| BASEBOARD       |                              |  |
| DOORS & WINDOWS |                              |  |

|            | CHLORINE SOLUTION TANK HOUSE   |  |
|------------|--|--|
| THE OTHER  |  |  |
|            |  |  |
|            |  |  |
| FLOOR AREA | 34.78m <sup>2</sup>  |  |
| USE        | CHLORINE SOLUTION TANK ROOM  |  |
| STRUCTURE  | CONCRETE BLOCK STRUCTURE   |  |
| SCOPE      | ONE-STORY BUILDING   |  |
| HEIGHT     | 5,200mm (from GROUND LEVEL)<br>3,400mm (from SURFACE OF CIVIL STRUCTURE) |  |

#### INTERIOR FINISH SCHEDULE

|                                 | ROOM NAME                      | FLOOR<br>LEVEL | FLOOR                        | BASEBOARD                        | WALL   | CEILING                 | CEILING HEIGHT<br>(mm) | REMARKS |
|---------------------------------|--------------------------------|----------------|------------------------------|----------------------------------|--|-------------------------|------------------------|---------|
| CHROLINE SOLUTION TANK<br>HOUSE | CHLORINE SOLUTION<br>TANK ROOM | $\pm 0$        | Concrete steel trowel finish | Concrete mortar t200 AEP<br>H150 | Concrete mortar t200 AEP<br>on concrete block wall | Fair-faced concrete AEP | 3400                   |         |
|                                 |                                |                |                              |                                  |  |                         |                        |         |

BUILDING OUTLINE



NOTES or REVISIONS :



#### SYMBOL LEGEND

WD : Wooden Door

- WWL : Wooden Window Louver AWL : Aluminum Window Louver
- AW : Aluminum Window
- AD : Aluminum Door
- SD : Steel Door SG : Steel Louve
- SG : Steel Louver AG : Aluminum Louver

#### FINISH LEGEND

- C.W.P. : Clear Wood Preservative
- S.O.P. : Ready-mixed Synthetic Resin Paint
- A.E.P. : Acrylic Resin Emulsion Paint
- S.V : Oil Stain Varnish

THE PREPARATORY SURVEY ON THE PROJECT FOR SEWERAGE SYSTEM DEVELOPMENT IN THE PHNOM PENH CAPITAL CITY CTI ENGINEERING INTERNATIONAL CO., LTD. NIPPON KOEI CO.,LTD. WATER AND SEWER BUREAU,CITY OF KITAKYUSHU

SEWAGE TREATMENT PLANT Chlorination Tank House

Finish Schedule and Door & Window List















| EXTERIOR FINISH | SCHEDULE  |
|-----------------|---|
|                 | ADMINISTRATION BUILDING   |
| ROOF            | Monier roof tile /resinous batten @300<br>Waterproofing: Asphalt prepared roofing 30kg/roll<br>Roof Board: Cemented excelsior board t25<br>Purlin: C-100×50×20×2.3@450<br>Verge board: Calcium silicate board t16 AEP<br>EAVES GUTTER: Cement mortar t20 AEP on concrete t150 |
| WALL            | Cement mortar t20 AEP on concrete block t150  |
| BASEBOARD       | Cement plaster t20  |
| DOORS & WINDOWS | WINDOWS: Aluminum sash Window<br>DOORS: Steel door SOP  |
| THE OTHERS      | PORCH<br>Floor:Ceramic tile 300×300 on cement mortar<br>Wall:Cement mortar t20 AEP on concrete block t150<br>Ceiling:Calcium silicate board t6 AEP<br>OTHER ENT. Floor:Concrete steel trowel finish   |

| BUILDING OUTLINE |  |  |  |  |  |  |
|------------------|--|--|--|--|--|--|
|                  | ADMINISTRATION BUILDING  |  |  |  |  |  |
| FROOR AREA       | 372.69m2   |  |  |  |  |  |
| USE              | ADMINISTRATION ROOM, OPERATION ROOM, MEETING ROOM<br>LABORATORY, TOILET, WORKER'S ROOM |  |  |  |  |  |
| STRUCTURE        | REINFORCED CONCRETE STURUCTURE   |  |  |  |  |  |
| SCOPE            | ONE-STORY BUILDING   |  |  |  |  |  |
| HEIGHT           | 7600mm (RIDGE LEVEL)   |  |  |  |  |  |
|                  |  |  |  |  |  |  |
|                  |  |  |  |  |  |  |
| REMARKS          |  |  |  |  |  |  |
|                  |  |  |  |  |  |  |
|                  |  |  |  |  |  |  |

# INTERIOR FINISH SCHEDULE

|          | ROOM NAME           | FLOOR<br>LEVEL | FLOOR  | BASEBOARD                     | WALL  | CEILING                            | CEILING HIGHT<br>(mm) | REMARKS   |
|----------|---------------------|----------------|--|-------------------------------|---|------------------------------------|-----------------------|---|
|          | ADMINISTRATION ROOM | ±0             | Ceramic tile 300×300 on cement mortar                                    | Ceramic tile H100             | Cement mortar t20 AEP<br>on concrete block t150                     | Plaster board t9.5 AEP /LGS        | 3000                  |   |
| BOILDING | OPERATION ROOM      | ±0             | Ceramic tile 300×300 on cement mortar                                    | Ceramic tile H100             | Cement mortar t20 AEP<br>on concrete block t150                     | Plaster board t9.5 AEP /LGS        | 3000                  |   |
|          | MEETNG ROOM         | ±0             | Ceramic tile $300 \times 300$ on cement mortar                           | Ceramic tile H100             | Cement mortar t20 AEP<br>on concrete block t150                     | Plaster board t9.5 AEP /LGS        | 3000                  |   |
|          | LABORATORY          | ±0             | Ceramic tile $300 \times 300$ on cement mortar                           | Ceramic tile H100             | Cement mortar t20 AEP<br>on concrete block t150                     | Plaster board t9.5 AEP /LGS        | 3000                  | Laboratory table  |
|          |                     | 70             | Concrete steel trowel finish W/Floor paint<br>Light-weight concrete t300 | Cement mortar t20 AEP<br>H150 | Cement mortar t20 AEP<br>on concrete block t150                     | Plaster board t9.5 AEP /LGS        | 3500                  | Side ditch with steel lid<br>Concrete base                                |
|          | WORKER'S ROOM       | ±0             | Ceramic tile 300×300 on cement mortar                                    | Ceramic tile H100             | Cement mortar t20 AEP<br>on concrete block t150                     | Plaster board t9.5 AEP /LGS        | 3000                  |   |
|          | TOILET-W,M          | ±0             | Porcelain tile on concrete steel trowel finish                           | Porcelain tile                | Porcelain tile on concrete block t150                               | Calcium silicate board t6 AEP /LGS | 2400                  | Booth screen:Polyester plywood<br>Lining:Porcelain tile on concrete block |
|          | DRESSING ROOM       | ±0             | Ceramic tile 300×300 on cement mortar                                    | Ceramic tile H100             | Cement mortar t20 AEP<br>on concrete block t150                     | Plaster board t9.5 AEP /LGS        | 2400                  | Lining: Cement mortar t20 AEP<br>on concrete block                        |
|          | SHOWER ROOM         | ±0             | Porcelain tile on concrete steel trowel finish<br>W/Waterploof coating   | Porcelain tile                | Porcelain tile on concrete block t150<br>W/Waterploof coating H1800 | Calcium silicate board t6 AEP /LGS | 2400                  | Lining:Porcelain tile on concrete block                                   |
|          | ENTRANCE HALL       | ±0             | Ceramic tile 300×300 on cement mortar                                    | Ceramic tile H100             | Cement mortar t20 AEP<br>on concrete block t150                     | Plaster board t9.5 AEP /LGS        | 3000                  |   |
|          | CORRIDOR            | ±0             | Ceramic tile 300×300 on cement mortar                                    | Ceramic tile H100             | Cement mortar t20 AEP<br>on concrete block t150                     | Plaster board t9.5 AEP /LGS        | 3000                  |   |

SEWAGE TREATMENT PLANT Administration Building Finish Schedule



|   |   |   |   | -  |   |  |
|---|---|---|---|--|---|--|
| KEY NUMBER &                              | AW Aluminium Double Sliding Window  | AW Aluminium Double Sliding Window  | AW Aluminium Double Sliding Window                                  | AD Aluminium Double Swinging Doors               | NOTES or REVISONS:  |  |
| QUANTITY                                  | 9   | 2 2   | 3   |  | Type Symbol   |  |
| ELEVATION                                 | Classical Mindow Frame:<br>Wooden frame SOP   | Inside Window Frame:<br>Wooden frame SOP  | Close Window Frame:<br>Wooden frame SOP                             | Inside Window Frame: Steel-PLt1.6 Processing SOP | Reference Number<br><u>AW</u><br>1<br><u>AD</u><br><u>WD</u><br>1<br><u>WD</u><br>1<br><u>SIMBOL LEGEND</u><br>WD : Wooden Door<br>WWL : Wooden Window Louver<br>AWL : Aluminum Window Louver   |  |
| LOCATION                                  | ADMINISTRATION ROOM MEETING ROOM ELECTRIC ROOM<br>OPERATION ROOM LABORATORY WORKER'S ROOM |   | _ELSHOWER ROOM  | 25 900 900 25<br>1850<br>ENTRANCE HALL           | AW - Aluminum Window<br>AD - Aluminum Door<br>SD - Steel Door<br>SG - Steel Louver<br>AG - Aluminum Louver  |  |
| FRAME; MATERIAL & FINISH                  | Alminium electro coloring   | Alminium electro coloring   | Alminium electro coloring   | Alminium electro coloring                        | FINISH LEGEND   |  |
| THRESHOLD or SILL                         |   |   |   | SUS  | C.W.P. : Clear Wood Preservative<br>S.O.P. : Ready-mixed Synthetic Resin Paint  |  |
| DOOR,<br>WINDOW                           | Alminium electro coloring   | Alminium electro coloring   | Alminium electro coloring   | Alminium electro coloring                        | A.E.P : Acrylic Resin Emulsion Paint  |  |
| & THICKNESS<br>LOUVER                     | 6mm   | 5mm   | 5mm   | 6mm  | S.V : Oil Stain Varnish   |  |
| GLASS & SCREEN                            | FL  | FL  | FL  | TP   | GLASS   |  |
| HARDWARE                                  | Flashing, Crescent, Hardware set<br>Fly Net (Mosquito Gauze)                              | Flashing, Crescent, Hardware set<br>Fly Net (Mosquito Gauze)  | Flashing, Crescent, Hardware set<br>Fly Net (Mosquito Gauze)        | Hardware set                                     | FL : Float Glass<br>CW : Cross Wired Sheet Glass  |  |
| REMARKS                                   | Inside Window Frame   | Inside Window Frame   | Inside Window Frame   | Inside Window Frame                              | TP : Tempered Glass<br>F : Figured Glass  |  |
| KEY NUMBER<br>&<br>QUANTITY               | SD Steel Double Swinging Door 1   | SD Steel Single Swinging Door 2   | SD Steel Single Swinging Door 1                                     |  |   |  |
| ELEVATION                                 | 88<br>1100<br>100<br>100<br>100   |   |   |  | C.P.T : Printumblers Lock with Thumb-tum<br>S.B : Slide Bolt<br>OTHER ABBREVIATION<br>DK : Door Knob<br>FMH : Full-Mortise Hinge<br>LJH : Loose Joint Hinge<br>GH : Gravity Hinge<br>DC : Door Closer<br>DH : DoorHolder<br>DS : Door Stop<br>FB : Flush Bolt |  |
| LOCATION                                  | ELECTRIC ROOM   | WORKER'S ROOM CORRIDOR  | ELECTRIC ROOM   |  |   |  |
| FRAME; MATERIAL & FINISH                  | Steel S.O.P.  | Steel S.O.P.  | Steel S.O.P.  |  | _   |  |
| THRESHOLD or SILL                         | SUS   | 505   |   |  | _   |  |
| DOOR,<br>WINDOW THICKNESS                 | Steel S.O.P.  | 40 mm   | 40 mm   |  |   |  |
| LOUVER GLASS & SCREFN                     |   | TP 5mm  |   |  |   |  |
| HARDWARE                                  | Door check, Door knob, Hinge(SUS), Lock,<br>Flush Bolt, Door stop, Hardware set           | Door check, Door knob, Hinge(SUS), Lock,<br>Door stop, Hardware set   | Door check, Door knob, Hinge(SUS), Lock,<br>Door stop, Hardware set |  |   |  |
| REMARKS                                   |   |   |   |  |   |  |
|   |   |   | · · · · · · · · · · · · · · · · · · ·                               | SCALE 1:50                                       |   |  |
|   |   |   |   |  |   |  |
| THE PRE<br>THE PROJECT FOR S<br>IN THE PE | EPARATORY SURVEY ON<br>SEWERAGE SYSTEM DEVELOPMENT<br>INOM PENH CAPITAL CITY              | CTI ENGINEERING INTERNATIONAL CO., LTD.<br>NIPPON KOEI CO.,LTD.<br>WATER AND SEWER BUREA U.CITY OF KITAKYUSHI | U   | AB-006   | SEWAGE TREATMENT PLANT<br>Administration Building Door & Window Schedule 1  |  |

| KEY NUMBER 8.  | WD Wooden Double Swinging Door  | WD Wooden Single Swinging Door  | WD Wooden S                               | ingle Swinging Door    |  |  | NOTES or REVISONS:   |
|--|---|---|---|------------------------|--|--|--|
| QUANTITY   | 1   | 2 4   | 3   | 4                      |  |  | Type Symbol  |
| ELEVATION  |   |   | 2100<br>20200 1300 200200                 |                        |  |  | $\begin{array}{c c} \hline \bullet \\ \hline \bullet \\ \hline \bullet \\ \hline \bullet \\ \hline \end{array} \\ \hline Reference Number \\ \hline \hline \\ \hline \hline \\ \hline \\ \hline \\ \hline \\ \hline \\ \hline \\ \hline \\ $                 |
| LOCATION   | MEETNG ROOM   | ADMINISTRATION ROOM OPERATION ROOM LABORATORY TOILET-W,M DRESSING ROOM  |   |                        |  |  | AG : Aluminum Louver   |
| FRAME; MATERIAL & FINISH   | Hard Wood Straight Grain Timber S.O.P.  | d Wood Straight Grain Timber S.O.P. Hard Wood Straight Grain Timber S.O.P. Hard Wood Straight Grain Timber S.O.P. |   |                        | FINISH LEGEND<br>C.W.P. : Clear Wood Preservative<br>S.O.P : Ready-mixed Synthetic Resin Paint |  |  |
| THRESHOLD or SILL  |   |   |   |                        |  |  |  |
| DOOR,<br>WINDOW  | Polyester plywood Polyester   |   |   |                        |  |  | A.E.P : Acrylic Resin Emulsion Paint   |
| & THICKNESS<br>LOUVER  | 40 mm 40 mm   |   | 40 mm                                     |                        |  | S.V : Oil Stain Varnish  |  |
| GIASS & SCALER   | or check, Door knob, Hinge, Lock, Elush Bolt, Door check, Door knob, Hinge, Lock, Door stop |   | Door check Door knob Hinge Lock Door stop |                        |  |  | - GLASS  |
| HARDWARE   | Door stop, Hardware set   | Hardware set  | Hardware set                              | inige, zeek, zeer stop |  |  | CW Cross Wired Sheet Glass   |
| REMARKS  |   |   |   |                        |  |  | TP : Tempered Glass<br>F : Figured Glass   |
| KEY NUMBER<br>&<br>QUANITTY  |   |   |   |                        |  |  | LOCK   |
| ELEVATION  |   |   |   |                        |  |  | C.P.T : Pintumbleus Lock with Thumb-tum<br>S.B : Slide Bolt<br>OTHER ABBREVIATION<br>DK : Door Knob<br>FMH : Full-Mortise Hinge<br>LJH : Loose Joint Hinge<br>GH : Gravity Hinge<br>DC : Door Closer<br>DH : DoorHolder<br>DS : Door Stop<br>FB : Flush Bolt |
| LOCATION   |   |   |   |                        |  |  |  |
| FRAME; MATERIAL & FINISH   |   |   |   |                        |  |  | -  |
| THRESHOLD or SILL  |   |   |   |                        |  |  | -  |
| DOOR,<br>WINDOW  |   |   |   |                        |  |  | -  |
| LOUVER   |   |   |   |                        |  |  | -  |
| HARDWARE   |   |   |   |                        |  |  |  |
| REMARKS  |   |   |   |                        |  |  |  |
| SCALE 1:50   |   |   |   |                        |  |  |  |
| THE PREPARATORY SURVEY ON<br>THE PROJECT FOR SEWERAGE SYSTEM DEVELOPMENT<br>IN THE PHNOM PENH CAPITAL CITYCTI ENGINEERING INTERNATIONAL CO., LTD.<br>NIIPON KOEI CO.,LTD.<br>WATER AND SEWER BUREAU,CITY OF KITAKYUSHUSTPAB-007Adu |   |   |   |                        |  | SEWAGE TREATMENT PLANT<br>ninistration Building Door & Window Schedule 2 |  |
















































**CROSS SECTION - C+000** 12 12 ± 8 ≚ 4 5.30 Low Water A=5, 55m2 п > 0 9.18 8.92 9.95 10.01 Ground Level 0+340 -0+343 -0+300 0+320 Offset ĪĪ

















## Channel Maintenance Road

<u>Section(1/2)</u> Scale 1:800

THE PREPARATORY SURVEY ON THE PROJECT FOR SEWERAGE SYSTEM DEVELOPMENT IN THE PHNOM PENH CAPITAL CITY CTI ENGINEERING INTERNATIONAL CO., LTD. NIPPON KOEI CO.,LTD. WATER AND SEWER BUREAU,CITY OF KITAKYUSHU

INTERCEPTION FACILITY & SEWER PIPE Channel Maintenance Road Section (1/2)

**CROSS SECTION -C+800** 12 12 +8.50 High Water ± 8 ∴ 4 A=6. 44m2 +5 30 Low Mater Level п > 0 10.00 Ground Level 1.28 5.08 79 0+418-0+360 0+380 8 Offset

















<u>Section (2/2)</u> <u>Scale 1:800</u>

THE PREPARATORY SURVEY ON THE PROJECT FOR SEWERAGE SYSTEM DEVELOPMENT IN THE PHNOM PENH CAPITAL CITY CTI ENGINEERING INTERNATIONAL CO., LTD. NIPPON KOEI CO.,LTD. WATER AND SEWER BUREAU,CITY OF KITAKYUSHU INTERCEPTION FACILITY & SEWER PIPE Channel Maintenance Road Section (2/2)









































MECHANICAL AND ELECTRICAL WORK

3,000

500

ۍ.

Cheung Ask Lake DCIP ¢ 350

Mechanical Equipment Layout for Solid-Liquid Separation Tank

Chrolination Tank


























| EXTERIOR FINISH SCHEDULE |                 |                   |  |  | BUILDING OUTLINE |                               |  |  |
|--------------------------|-----------------|-------------------|--|--|------------------|-------------------------------|--|--|
|                          |                 | TRANSFORMER HOUSE |  |  |                  | CHLORINE SOLUTION TANK HOUS   |  |  |
|                          | ROOF            |                   |  |  | THE OTHER        |                               |  |  |
|                          |                 |                   |  |  |                  |                               |  |  |
|                          |                 |                   |  |  | FLOOR AREA       | 36.00m <sup>2</sup>           |  |  |
|                          |                 |                   |  |  | USE              | TRANSFORMER ROOM              |  |  |
|                          | WALL            |                   |  |  | STRUCTURE        | CONCRETE BLOCK STRUCTURE      |  |  |
|                          | BASEBOARD       |                   |  |  | SCOPE            | ONE-STORY BUILDING            |  |  |
|                          | DOORS & WINDOWS |                   |  |  | HEIGHT           | 5,000mm (Ridge Level from GL) |  |  |

|            | CHLORINE SOLUTION TANK HOUSE  |  |
|------------|-------------------------------|--|
| THE OTHER  |                               |  |
| FLOOR AREA | 36.00m <sup>2</sup>           |  |
| USE        | TRANSFORMER ROOM              |  |
| STRUCTURE  | CONCRETE BLOCK STRUCTURE      |  |
| SCOPE      | ONE-STORY BUILDING            |  |
| HEIGHT     | 5,000mm (Ridge Level from GL) |  |

## INTERIOR FINISH SCHEDULE

|                   | ROOM NAME        | FLOOR<br>LEVEL | FLOOR                        | BASEBOARD                  | WALL  | CEILING             | CEILING HEIGHT<br>(mm) | REMARKS |
|-------------------|------------------|----------------|------------------------------|----------------------------|---|---------------------|------------------------|---------|
| TRANSFORMER HOUSE | TRANSFORMER ROOM | ±0             | Concrete steel trowel finish | Cement plaster t20<br>H150 | Concrete mortar t20 AEP on concrete block wall t150 | Plaster Board t=9.5 | 4000                   |         |
|                   |                  |                |                              |                            |   |                     |                        |         |



| NOTES | or I | REV | ISIO | NS |
|-------|------|-----|------|----|



SYMBOL LEGEND

- WD : Wooden Door WWL : Wooden Window Louver
- AWL : Aluminum Window Louver
- AW : Aluminum Window AD : Aluminum Door
- SD : Steel Door
- SG : Steel Louver AG : Aluminum Louver
- FINISH LEGEND
- C.W.P. : Clear Wood Preservative
- S.O.P. : Ready-mixed Synthetic Resin Paint
- A.E.P. : Acrylic Resin Emulsion Paint S.V : Oil Stain Varnish

THE PREPARATORY SURVEY ON THE PROJECT FOR SEWERAGE SYSTEM DEVELOPMENT IN THE PHNOM PENH CAPITAL CITY MECHANICAL AND ELECTRICAL WORK Transformer House Finish Schedule and Door & Window List