

**Government of India
Government of Tamil Nadu
Highways & Minor Ports Department (HMPD)
Tamil Nadu Infrastructure Development Board (TNIDB)**

**PREPARATORY STUDY
FOR
CHENNAI PERIPHERAL RING ROAD
DEVELOPMENT
IN
INDIA**

**FINAL REPORT
VOL.1**

December 2018

Japan International Cooperation Agency (JICA)

**JICA Study Team constituted by
NIPPON KOEI CO., LTD.**

**EAST NIPPON EXPRESSWAY CO., LTD.
CTI ENGINEERING INTERNATIONAL CO., LTD.
PADECO CO., LTD.**

4R
JR(P)
18-057



EXISTING CONDITIONS (1/2)



⑩



⑪



⑫



⑬



⑭



⑮



⑯



⑰



⑱

EXISTING CONDITIONS (2/2)

PREPARATORY STUDY FOR CHENNAI PERIPHERAL RING ROAD DEVELOPMENT IN INDIA

FINAL REPORT VOL.1

TABLE OF CONTENTS

Abbreviations

Summary

CHAPTER 1 INTRODUCTION.....	1-1
1.1 Outline of the Study	1-1
1.1.1 Background of the Study.....	1-1
1.1.2 Objectives of the Study	1-1
1.1.3 Target Sections of the Study	1-1
1.1.4 Scope of the Study	1-1
1.1.5 Work Schedule of the Study	1-2
1.1.6 Objectives of the Final Report	1-3
1.1.7 Components of the Final Report	1-3
1.1.8 Organization of the Study	1-3
1.2 Record of Meetings	1-4
1.2.1 Meetings with Concerned Agencies of CPRR.....	1-4
1.2.2 Meetings with Concerned Agencies of CPRR ITS	1-10
1.2.3 Meetings with Other Organizations	1-11
CHAPTER 2 PRESENT CONDITION AND CIRCUMSTANCES OF THE PROJECT....	2-1
2.1 Outline of the Chennai Peripheral Ring Road (CPRR) Development Project.....	2-1
2.1.1 Objectives of the Project	2-1
2.1.2 Past Studies on the Project.....	2-1
2.2 Present Condition and Identified Issues of Roads and Traffic in the Study	
Area	2-2
2.2.1 Present Condition and Issues of Road Network.....	2-2
2.2.2 Present Condition and Issues of Traffic in the Study Area	2-5
2.2.3 Present Condition and Issues of Intelligent Transport System (ITS) Facilities in the Study Area.....	2-18
2.3 Organizations Related to Road and ITS Development.....	2-21
2.3.1 Highways and Minor Ports Department (HMPD)	2-21
2.3.2 Tamil Nadu Infrastructure Development Board (TNIDB).....	2-21
2.3.3 Chennai Metropolitan Development Authority (CMDA).....	2-22
2.3.4 Chennai Traffic Police (CTP)	2-23
2.3.5 Greater Chennai Corporation (GCC).....	2-23
2.3.6 Chennai Smart City Limited (CSCL).....	2-24
2.3.7 Tamil Nadu Road Development Company (TNRDC).....	2-25
2.3.8 Tamil Nadu Road Infrastructure Development Corporation (TNRIDC)	2-26
2.3.9 Metropolitan Transport Corporation (MTC).....	2-26
2.3.10 Tamil Nadu State Data Center	2-26
2.3.11 Chennai Metro Rail.....	2-27
2.4 Development Plans and Projects Related to CPRR.....	2-28
2.4.1 Superior Development Plans.....	2-28
2.4.2 Urban Development Plans and Projects.....	2-29
2.4.3 Road Development Plans and Projects Other than CPRR	2-38
2.4.4 Intelligent Transport System (ITS) Development Plans and Projects.....	2-39

2.4.5	Present Condition of ITS for Arterial Roads.....	2-40
CHAPTER 3 TRAFFIC SURVEY, ANALYSIS, AND FORECAST		3-1
3.1	Traffic Survey.....	3-1
3.1.1	Objectives of the Project	3-1
3.1.2	Results of the Traffic Survey	3-4
3.2	Hearing Survey for Related Development Plans.....	3-5
3.2.1	Port Development Plans.....	3-5
3.2.2	Development Plans along the CPRR.....	3-5
3.2.3	Results of Hearing Survey	3-6
3.3	Traffic Demand Forecast.....	3-15
3.3.1	Reproduction of Present Traffic Situation	3-15
3.3.2	Estimate of Developed Traffic Volume	3-27
CHAPTER 4 PRIORITIZATION AND FORMULATION OF THE PROJECT FOR JICA LOAN SCHEME.....		4-1
4.1	Chennai Peripheral Ring Road (CPRR) Components.....	4-1
4.1.1	Approved Alignment and Sectioning of CPRR	4-1
4.2	ITS Components.....	4-2
4.2.1	Overall ITS Components	4-2
4.3	Prioritization of Components for Implementation.....	4-3
4.3.1	Prioritization of CPRR Components.....	4-3
4.4	Consulting Services for the Prioritized Project.....	4-10
4.4.1	CPRR	4-10
4.4.2	CPRR ITS	4-12
CHAPTER 5 HIGHWAY OPERATION AND MAINTENANCE (O&M) STRUCTURE		5-1
5.1	Outline of Roads in Tamil Nadu	5-1
5.1.1	National Highways (NHs).....	5-1
5.1.2	State Highways (SHs)	5-1
5.1.3	Major District Roads (MDRs).....	5-1
5.1.4	Other District Roads (ODRs).....	5-1
5.2	Highways and Minor Ports Department (HMPD), Tamil Nadu.....	5-2
5.2.1	Organization of HMPD.....	5-2
5.2.2	Highways Department.....	5-2
5.2.3	Construction and Maintenance Wing.....	5-3
5.2.4	Tamil Nadu Road Development Company Ltd (TNRDC)	5-6
5.2.5	Tamil Nadu Road Infrastructure Development Corporation (TNRIDC)	5-9
5.3	Financial Situation of the Highways Department	5-10
5.3.1	Changes in Annual Financial Allotment	5-10
5.3.2	Breakdown of Annual Financial Allotment	5-11
5.3.3	Non-Plan Maintenance Works	5-12
5.4	Recent Model Contracts for Operations and Maintenance in India	5-13
5.4.1	Performance Based Maintenance Contract (PBMC)	5-13
5.4.2	Operation-Maintenance-Transfer (OMT) Contract.....	5-15
5.4.3	Toll-Operate-Transfer (TOT) Contract.....	5-15
5.4.4	Engineering-Procurement-Construction (EPC) Contract (Maintenance Clause)	5-16
5.4.5	Public-Private-Partnership (PPP) Contract (Maintenance Clause)	5-18
5.4.6	Maintenance Requirements (Schedule-K in PPP and Schedule-E in EPC)	5-19
5.5	Operations and Maintenance (O&M) of Chennai Outer Ring Road (CORR).....	5-21
5.5.1	O&M Requirements	5-21
5.5.2	O&M Team	5-22
5.5.3	Traffic Management.....	5-22
5.5.4	Highway Maintenance	5-25
5.6	Recommendations on the O&M Plan.....	5-28
5.6.1	Basic Data of CPRR for O&M	5-28

5.6.2	Proposal on O&M Plan	5-32
CHAPTER 6 DESIGN REVIEW OF CHENNAI PERIPHERAL RING ROAD (CPRR) ..6-1		
6.1	General.....	6-1
6.1.1	Objectives and Scope of Design Review of CPRR.....	6-1
6.1.2	Natural Conditions Survey.....	6-2
6.1.3	Road Classification and Design Standards to be Applied.....	6-3
6.1.4	Design Speed and Design Criteria	6-5
6.1.5	Number of Lanes.....	6-6
6.1.6	Typical Cross Sections.....	6-12
6.2	Highway Design (All Sections)	6-22
6.2.1	Alignment	6-22
6.2.2	Entry/Exit and Service Road.....	6-38
6.2.3	Junctions (Intersections/Junctions)	6-39
6.2.4	Pavement.....	6-46
6.2.5	Drainage.....	6-58
6.3	Interchange Design (All Sections).....	6-63
6.3.1	Obtained Documents and Drawings.....	6-63
6.3.2	Location and Type of Interchange	6-63
6.3.3	Geometric Design Standard of Interchange	6-65
6.3.4	Outline of Interchange Design and Recommendation of Improvement	6-66
6.4	Structural Design (All Sections).....	6-80
6.4.1	Types of Structures	6-80
6.4.2	Obtained Documents and Drawings.....	6-81
6.4.3	Major Bridges (MJB).....	6-84
6.4.4	Minor Bridges (MNBs).....	6-94
6.4.5	Railway Over Bridge (ROB).....	6-99
6.4.6	Underpasses	6-104
6.4.7	Box Culverts (BC)	6-112
6.4.8	Interchange (IC)	6-120
6.4.9	Structure List and General Drawings.....	6-127
6.5	Design Update (Section 1).....	6-128
6.5.1	Main Renewed Points	6-128
6.5.2	Design Quantity	6-134
6.5.3	Recommendation on Detailed Design of Section 1	6-134
CHAPTER 7 PRELIMINARY DESIGN OF CHENNAI PERIPHERAL RING ROAD INTELLIGENT TRANSPORT SYSTEM (CPRR ITS).....7-1		
7.1	General.....	7-1
7.1.1	Scope and Objectives of Preliminary Design of the Chennai Peripheral Ring Road Intelligent Transport System (CPRR ITS).....	7-1
7.1.2	Target Section for CPRR ITS and Overall System Configuration.....	7-1
7.2	Highway Traffic Management System (HTMS)	7-4
7.3	Toll Management System (TMS).....	7-7
CHAPTER 8 IMPLEMENTATION ORGANIZATION FOR CPRR ITS.....8-1		
8.1	Organizational Framework of Project	8-1
8.2	Operation and Maintenance (O&M) Plan for Chennai Peripheral Ring Road Intelligent Transport System (CPRR ITS).....	8-2
8.2.1	Highway Traffic Management System (HTMS).....	8-2
8.2.2	Toll Management System (TMS)	8-8
CHAPTER 9 PROCUREMENT PLAN, CONSTRUCTION PLAN, AND COST ESTIMATE.....9-1		
9.1	Review of DPR Cost Estimate (All Sections)	9-1
9.1.1	Target of Review.....	9-1
9.1.2	Summary of Project Cost in DPR	9-1
9.1.3	Sharing Ratio of DPR Project Cost.....	9-2
9.1.4	Establishment of Work Item and Application Status to Each Section.....	9-4

9.1.5	Review of DPR Unit Price	9-5
9.1.6	Updated Project Cost	9-6
9.2	General Procurement Situation in Tamil Nadu	9-7
9.2.1	Outline of Procurement Situation.....	9-7
9.2.2	Influence of Procurement Circumstances on the Project	9-10
9.3	Cost Estimate for CPRR (Sec-1)	9-11
9.3.1	Procurement and Construction Plan.....	9-11
9.3.2	Summary of Project Cost (Sec-1)	9-13
9.3.3	Summary of Project Cost (Sec-2 to Sec-5)	9-20
CHAPTER 10 IMPLEMENTATION SCHEDULE OF SECTION 1		10-1
10.1	General.....	10-1
10.2	Tentative Implementation Schedule for CPRR.....	10-1
CHAPTER 11 ENVIRONMENTAL AND SOCIAL CONSIDERATIONS		11-1
11.1	Objectives of Environmental and Social Considerations	11-1
11.1.1	Basic Principles Regarding Environmental and Social Considerations	11-1
11.2	Review of the DPR EIA/SIA/RAP for All Sections	11-2
11.2.1	Analysis for Alternative Plans	11-2
11.2.2	Screening.....	11-12
11.2.3	Review of the DPR EIA and SIA/RAP.....	11-13
11.3	Environmental and Social Considerations in Section 1 (Main Road and TPP Link Road (Original Alignment))	11-21
11.3.1	General Condition of the Project Area.....	11-21
11.3.2	Legal Framework of the Environmental and Social Safeguards.....	11-27
11.3.3	Expected Impacts (Scoping) for Section 1 (Main Road and TPP Link Road (Original Alignment))	11-33
11.3.4	TOR for Further EIA Study	11-37
11.3.5	Survey Results	11-40
11.3.6	Impact Assessment.....	11-63
11.3.7	Mitigation Measures and Implementation Budget.....	11-67
11.3.8	Monitoring Plan	11-76
11.3.9	Implementation Mechanism of Mitigation and Monitoring Measures	11-80
11.3.10	Grievance Redress Mechanism	11-82
11.3.11	Consultation with Stakeholders and Concerned Public	11-84
11.4	Land Acquisition and Resettlement of Section 1.....	11-90
11.4.1	Necessity of Land Acquisition and Resettlement in the Project	11-90
11.4.2	Legal Framework of Land Acquisition and Resettlement	11-90
11.4.3	Size and Target of Land Acquisition and Resettlement.....	11-105
11.4.4	Plan for Compensation and Assistance	11-123
11.4.5	Grievance Redress Mechanism.....	11-133
11.4.6	Institutional Arrangement in the Implementation of RAP	11-135
11.4.7	Implementation Schedule.....	11-139
11.4.8	Budget and Funding	11-140
11.4.9	Monitoring and Evaluation	11-144
11.4.10	Consultations with PAPs.....	11-147
11.5	Stakeholder and Public Consultation on Environmental Impact Assessment (EIA) and RAP for Section 1.....	11-148
11.5.1	First Public Consultation Following JICA Guidelines.....	11-148
11.5.2	Second Public Consultation Based on JICA Guidelines.....	11-157
11.5.3	Focus Group Discussions with Vulnerable Groups	11-165
11.5.4	Actions Taken Following the Results of Public Consultations.....	11-165
11.6	Environmental and Social Considerations of the TPP Link Road (New Alignment).....	11-166
11.6.1	Outline of Alternative Alignment	11-166
11.6.2	Alternative Study	11-168

11.6.3	Environmental and Social Considerations of TPP Link Road (New Alignment)	11-170
11.6.4	Land Acquisition and Relocation of Residents and Businesses Caused by TPP Link Road (New Alignment)	11-179
11.6.5	Stakeholder Meetings.....	11-194
11.7	Draft Monitoring Forms.....	11-198
11.7.1	Environmental Monitoring Forms (Construction Phase).....	11-198
11.7.2	Environmental Monitoring Forms (Operation Phase).....	11-201
11.7.3	Land Acquisition and RAP Implementation Monitoring Forms.....	11-203
11.8	Environmental and Social Considerations for Section 2, Section 3, and Section 5.....	11-210
11.8.1	General Condition.....	11-210
11.8.2	Survey Results	11-217
CHAPTER 12	PROJECT EVALUATION	12-1
12.1	Methodology	12-1
12.1.1	Economic Analysis	12-1
12.1.2	Financial Analysis.....	12-4
12.2	Project Evaluation on CPRR (Examination of Priority with Comparing All Sections)	12-7
12.2.1	Project Cost of CPRR (All Sections).....	12-7
12.2.2	EIRR Calculation	12-13
12.3	Project Evaluation on Priority Section (Section 1) of CPRR.....	12-17
12.3.1	Project Cost of Section 1.....	12-17
12.3.2	Traffic Volume.....	12-17
12.3.3	EIRR Calculation	12-18
12.3.4	FIRR Calculation	12-18
CHAPTER 13	CONCLUSIONS AND RECOMMENDATIONS	13-1
13.1	Necessity and Effect of the Chennai Peripheral Ring Road (CPRR) Project Section 1	13-1
13.2	Confirmation of Appropriateness of the Project Components	13-1

APPENDICES

Appendix-1: Minutes of Meeting with Concerned Agencies

Appendix-2: Correlationship of Concerned Organizations

Appendix-3: Traffic Demand Forecast for Pavement Design

Appendix-4: TOR for Social and Environmental Managers

Appendix-5: Sample TORs for INGO/EMA

Appendix-6: TOR for appointment of External Monitoring and Avaluation Agency

Appendix-7: List of Bridge Structures

Appendix-8: General Drawings of Bridge Works

Appendix-9: Documents for Environmental and Social Considerations

List of Figures

Figure 2.2.1	Road Network in CMA-----	2-3
Figure 2.2.2	Issues due to Traffic Signal Shortage-----	2-5
Figure 2.2.3	Installation of Barricades-----	2-5
Figure 2.2.4	Crossing Pedestrians -----	2-6
Figure 2.2.5	Issues due to Small Processing Capacity and Inefficient Operation at the Chennai Port -----	2-7
Figure 2.2.6	Location of Container Freight Stations-----	2-8
Figure 2.2.7	Traffic around Chennai Port-----	2-8
Figure 2.2.8	Street Parking of the Large Vehicles around the Container Freight Station -----	2-9
Figure 2.2.9	Waiting Queue of Large Vehicles-----	2-9
Figure 2.2.10	Issues due to Road Structure and Operation-----	2-10
Figure 2.2.11	Undeveloped Junction in ORR-----	2-11
Figure 2.2.12	Undeveloped Sidewalk -----	2-11
Figure 2.2.13	Misuse of Sidewalks -----	2-12
Figure 2.2.14	Lanes Occupied by Parked Vehicles-----	2-12
Figure 2.2.15	Inefficient Operation of Intersection-----	2-13
Figure 2.2.16	U-Turn Point-----	2-13
Figure 2.2.17	Problems due to Deterioration of Pavement-----	2-14
Figure 2.2.18	Road Collapse due to Deterioration of Pavement -----	2-14
Figure 2.2.19	Large Vehicles around the Industrial Park-----	2-15
Figure 2.2.20	Buses Occupying the Road -----	2-16
Figure 2.2.21	Occupation of Roads by Loading and Unloading on Roads -----	2-17
Figure 2.2.22	Animal Crossing the Road-----	2-17
Figure 2.2.23	Reduction of Lane due to Sidewalk Stalls -----	2-17
Figure 2.2.24	Standby Auto-Rickshaw -----	2-18
Figure 2.2.25	Images of Bus Tracking System and Passenger Information System -----	2-19
Figure 2.2.26	Existing Traffic Signal and CCTV Camera at Junction-----	2-20
Figure 2.2.27	VMS and Displayed Message-----	2-20
Figure 2.3.1	Organization Structure of Tamil Nadu Infrastructure Development Board-----	2-22
Figure 2.3.2	Organization Structure of Chennai Traffic Police-----	2-23
Figure 2.3.3	Organizational Structure of the Executive Committee of Greater Corporation of Chennai -----	2-23
Figure 2.3.4	Organizational Structure of the Administrative Body of Greater Corporation of Chennai -----	2-24
Figure 2.3.5	Organization Structure of Chennai Smart City Limited -----	2-25
Figure 2.3.6	Organization Structure of Metropolitan Transport Corporation-----	2-26
Figure 2.3.7	Organization Structure of Electronic Corporation of Tamil Nadu and Tamil Nadu State Data Center -----	2-27
Figure 2.4.1	Concept of Smart City Project -----	2-40
Figure 2.4.2	Overview of the Current Situation of the Arterial Roads in Chennai -----	2-41
Figure 3.1.1	Traffic Survey Points -----	3-2
Figure 3.1.2	Traffic Survey -----	3-3
Figure 3.1.3	Outline of Traffic Volume Survey Results -----	3-4
Figure 3.2.1	Access to Ennore Port -----	3-6
Figure 3.2.2	Access to Chennai Port-----	3-7
Figure 3.2.3	Vicinity of the Entrance and Exit Gates of Kattupalli Port-----	3-7
Figure 3.2.4	Projects to be Completed by Year 2035 (Ennore Port)-----	3-8
Figure 3.2.5	Prediction of Cargo Handled by Year 2035 (Ennore Port)-----	3-11
Figure 3.2.6	Prediction of Cargo Handled by Year 2035 (Chennai Port)-----	3-12
Figure 3.2.7	Cargo Handled from 2014 to 2016 (Kattupalli Port) -----	3-14
Figure 3.2.8	Estimation Result of Container Cargo Handled (Kattupalli Port)-----	3-14
Figure 3.3.1	Flow of Traffic Demand Estimate-----	3-15
Figure 3.3.2	Road Network Adopted in Traffic Analysis-----	3-16

Figure 3.3.3	Development Status of ORR -----	3-17
Figure 3.3.4	Development Status of Sec. 4 of CPRR-----	3-18
Figure 3.3.5	QV Conditions -----	3-18
Figure 3.3.6	Zone Divisions -----	3-19
Figure 3.3.7	Zone Division Adopted in Traffic Analysis-----	3-19
Figure 3.3.8	Traffic Assignment Flow-----	3-25
Figure 3.3.9	Survey Result and Estimation Result-----	3-26
Figure 3.3.10	Traffic Assignment Result-----	3-27
Figure 3.3.11	Original Unit of Trip Generation Volume by Scale of Manufacturing Industry ---	3-28
Figure 3.3.12	Future Road Network-----	3-31
Figure 3.3.13	Traffic Assignment Result-----	3-33
Figure 3.3.14	Location of the Container Freight Stations-----	3-34
Figure 3.3.15	Prediction of Cargo Handled by Year 2035 (Chennai Port)-----	3-35
Figure 3.3.16	Connection of ORR and CPRR-----	3-35
Figure 3.3.17	Problems of Intersection of NH205 and SH57-----	3-36
Figure 3.3.18	The Result of Sensitivity Analysis -----	3-37
Figure 4.2.1	Overall ITS Components for Japanese ODA Loan Project-----	4-2
Figure 4.3.1	Results of Traffic Simulation for the Comparison of Sections -----	4-3
Figure 4.3.2	Reduction in Total Travel Time Made by Every Section for Each Case -----	4-4
Figure 4.3.3	Assumed Project Implementation Schedule for Sections 1, 2, 3, and 5-----	4-8
Figure 4.3.4	Assumed Project Implementation Schedule for Section 4-----	4-8
Figure 4.4.1	Proposed Organization Structure of D/D Review Consultant -----	4-11
Figure 4.4.2	Proposed Organization Structure of C/S Consultant-----	4-12
Figure 4.4.3	Proposed Organization Structure of ITS Consultant (CPRR: B/D)-----	4-14
Figure 4.4.4	Proposed Organization Structure of ITS Consultant (CPRR ITS: T/A) -----	4-14
Figure 4.4.5	Proposed Organization Structure of ITS Consultant (CPRR ITS: C/S)-----	4-15
Figure 4.4.6	Proposed Organization Structure of ITS Consultant (CPRR ITS: O/M) -----	4-15
Figure 5.2.1	Organizational Structure of HMPD -----	5-2
Figure 5.2.2	Organizational Structure of the Highways Department-----	5-3
Figure 5.2.3	Organizational Structure of Construction & Maintenance Wing-----	5-4
Figure 5.2.4	Location Map of Chennai Outer Ring Road (CORR)-----	5-8
Figure 5.2.5	Location Map of Oragadam Industrial Corridor-----	5-10
Figure 5.3.1	Changes in Annual Financial Allotment to the Highways Department-----	5-11
Figure 5.3.2	Breakdown of Annual Financial Allotment to the Highways Department-----	5-11
Figure 5.3.3	Changes in Annual Financial Allotment to the Highways Department for Non- Plan Maintenance-----	5-12
Figure 5.5.1	CORR and O&M Field Office -----	5-22
Figure 5.5.2	Organizational Chart of O&M Team -----	5-22
Figure 5.5.3	Control Room and Ambulance-----	5-23
Figure 5.5.4	Emergency Service Procedure -----	5-24
Figure 5.5.5	Traffic Control for Work Zone Safety-----	5-25
Figure 5.5.6	Examples of Maintenance Equipment-----	5-26
Figure 5.6.1	Location of Project Road and Crossing Roads-----	5-29
Figure 5.6.2	Typical Cross Sections of Each Road Section -----	5-30
Figure 5.6.3	Highways Divisions Responsible for O&M of CPRR -----	5-33
Figure 5.6.4	Structure of Thiruvallur Highways Division-----	5-33
Figure 5.6.5	Examples of Field Office and Maintenance Work -----	5-34
Figure 5.6.6	Inspection Assessment Methodology for Preventive Maintenance-----	5-36
Figure 5.6.7	Locations of Toll Plazas in Section 1 of CPRR -----	5-37
Figure 5.6.8	Highway Traffic Management System Equipment Deployment Plan -----	5-38
Figure 6.1.1	Typical Cross Sections (Section 1)-----	6-13
Figure 6.1.2	Typical Cross Sections TPP Link Road (New Alignment)-----	6-14
Figure 6.1.3	Typical Cross Sections (Section 2)-----	6-16
Figure 6.1.4	Typical Cross Sections (Section 3)-----	6-18
Figure 6.1.5	Typical Cross Sections (Section 4)-----	6-19

Figure 6.1.6	Typical Cross Sections (Section 5)-----	6-21
Figure 6.2.1	Alignment at Ch.99+600 and Drivers' View-----	6-38
Figure 6.2.2	Crossing at Entry and Exit Ramps -----	6-39
Figure 6.2.3	Present Condition of Beginning Point-----	6-40
Figure 6.2.4	Plan of the Present Design of Beginning Point -----	6-40
Figure 6.2.5	Improvement Plan of Beginning Point -----	6-41
Figure 6.2.6	Present Condition of Bifurcation Point-----	6-41
Figure 6.2.7	Plan and Profile of the Present Design of Bifurcation Point -----	6-42
Figure 6.2.8	Improvement Plan of Bifurcation Point -----	6-42
Figure 6.2.9	Present Condition of End Point -----	6-43
Figure 6.2.10	Plan of the Present Design of End Point -----	6-43
Figure 6.2.11	Recommended Plan -----	6-44
Figure 6.2.12	Present Condition of Crossing Point of SH48 -----	6-44
Figure 6.2.13	Projected Plan and Profile -----	6-45
Figure 6.2.14	Improvement Plan of Connection with SH48-----	6-46
Figure 6.2.15	Pavement Layer Structure of DPR -----	6-50
Figure 6.2.16	Example of the Design Catalogue Shown in the Adopted IRC-----	6-50
Figure 6.2.17	Result of Pavement Design Made by the JICA Study Team (Case 1) -----	6-56
Figure 6.2.18	Result of Pavement Design Made by the JICA Study Team (Case 2) -----	6-57
Figure 6.2.19	Proposed Longitudinal Drain in the DPR-----	6-58
Figure 6.3.1	Location of Interchange -----	6-64
Figure 6.3.2	Shape of Acceleration and Deceleration Lanes in the Ramp Terminal -----	6-66
Figure 6.3.3	Present Condition of IC-1 -----	6-66
Figure 6.3.4	Plan of IC-1 -----	6-68
Figure 6.3.5	Recommended Plan for IC-1 -----	6-69
Figure 6.3.6	Present Condition of IC-2-----	6-70
Figure 6.3.7	Plan of IC-2 -----	6-71
Figure 6.3.8	Proposal of the Abovementioned Improvement -----	6-72
Figure 6.3.9	Present Condition of IC-3 -----	6-73
Figure 6.3.10	Plan of IC-3 -----	6-74
Figure 6.3.11	Recommended Plan for IC-3 -----	6-75
Figure 6.3.12	Present Condition of IC-4 -----	6-76
Figure 6.3.13	Plan of IC-2 -----	6-78
Figure 6.3.14	Recommended plan for IC-4 -----	6-79
Figure 6.4.1	Planned Number of Lanes of the Bridge (Completed Structure for All Sections) -----	6-80
Figure 6.4.2	Location of Major Bridges-----	6-85
Figure 6.4.3	Draft Railroad Plan at MJB101 Start Point-----	6-86
Figure 6.4.4	Sample of Adopted Hybrid Structures as Abutments in India -----	6-88
Figure 6.4.5	Bridge Cross Section (MJB101) -----	6-89
Figure 6.4.6	Ends of Bridge Constructed at Section 4 (Concrete Wearing Coat) -----	6-89
Figure 6.4.7	MJB501 : Type of Substructure Located at Bridge Ends (Abutment)-----	6-90
Figure 6.4.8	Revision of Bridge End Structure of MJB-----	6-91
Figure 6.4.9	Typographical Error in Drawing-----	6-92
Figure 6.4.10	Mistake in Plan & Profile -----	6-93
Figure 6.4.11	Substructure Located at Bridge Ends of MNB (Abutment Type) -----	6-97
Figure 6.4.12	Bridge Cross Section (MNB101) -----	6-97
Figure 6.4.13	Several Piers on the River (MNB501) -----	6-98
Figure 6.4.14	Bridge Location (MNB103) -----	6-98
Figure 6.4.15	Location of Railway Over Bridges-----	6-100
Figure 6.4.16	Clearance Below the Girder -----	6-101
Figure 6.4.17	Pier Arrangement (ROB101) -----	6-102
Figure 6.4.18	Bridge Cross Section (ROB) -----	6-103

Figure 6.4.19	VUP in the ORR (Box, Block Wall) -----	6-111
Figure 6.4.20	VUP Shown in the Plan&Profile -----	6-111
Figure 6.4.21	Location of Road Crossing (Near Section 3 Ch. 70+020) -----	6-112
Figure 6.4.22	Box Culvert (ORR)-----	6-112
Figure 6.4.23	Proposed Correction of Retaining Wall Structure on Box-----	6-119
Figure 6.4.24	Location of Interchanges -----	6-121
Figure 6.4.25	Vertical Clearance (IC/NH5) -----	6-123
Figure 6.4.26	Bridge Cross Section (IC/NH5) -----	6-124
Figure 6.4.27	Cross Section of Reinforced Earth Wall (IC) -----	6-126
Figure 6.4.28	Proposed Cantilever Length of Slab -----	6-126
Figure 6.4.29	Proposed Revision of Pier Support-----	6-127
Figure 6.5.1	MJB101 Extension Plan-----	6-128
Figure 6.5.2	Plan of IC-1 -----	6-129
Figure 6.5.3	Traffic Operation Chart of IC-1 -----	6-129
Figure 6.5.4	Toll Barrier on CPRR Ch.15+800-----	6-130
Figure 6.5.5	Toll Barrier on CPRR Ch.2+200 -----	6-130
Figure 6.5.6	Toll Barrier on TPP Link Road Ch.1+200-----	6-131
Figure 6.5.7	Traffic Control Center on CPRR Ch.8+600-----	6-131
Figure 6.5.8	Connecting Point with ORR at the South End of TPP Link Road (New Alignment)-----	6-132
Figure 6.5.9	Alignment Change Plan of TPP Link Road -----	6-133
Figure 6.5.10	Layout Plan of Entrance and Exit -----	6-134
Figure 6.5.11	Plan of JCT-1 -----	6-135
Figure 6.5.12	Plan of JCT-2-----	6-135
Figure 6.5.13	Traffic Control Center on CPRR Ch.8+600-----	6-136
Figure 6.5.14	Abutment of MJB101-----	6-137
Figure 6.5.15	Cross Section of MJB101 and Constructed Bridge in Section 4 (Concrete Pavement)-----	6-137
Figure 6.5.16	VUP in the Outer Ring Road (Box, Block Wall) -----	6-138
Figure 6.5.17	Proposed Cantilever Length of Slab -----	6-138
Figure 6.5.18	Cross Section of Reinforced Earth Wall (IC) -----	6-139
Figure 6.5.19	Proposed Bearing Position (MJB101)-----	6-139
Figure 7.1.1	Scope of CPRR ITS for the Project -----	7-1
Figure 7.1.2	Target Section of CPRR ITS for the Project -----	7-2
Figure 7.1.3	Overall System Configuration of the Components of CPRR ITS-----	7-3
Figure 7.2.1	Location Plan of Roadside Equipment of HTMS -----	7-5
Figure 7.2.2	Location Plan for Traffic Management Center (HTMS)-----	7-6
Figure 7.2.3	Building Plan of Traffic Management Center (HTMS)-----	7-6
Figure 7.3.1	Locations of Toll Plazas-----	7-7
Figure 7.3.2	Entire Location Plan of the Toll Plaza-----	7-8
Figure 7.3.3	Horizontal Image of the Skywalk -----	7-9
Figure 7.3.4	Vertical Image of the Skywalk-----	7-9
Figure 7.3.5	Plan of Toll Plaza Building-----	7-10
Figure 8.1.1	Organizational Framework of ITS Project for CPRR -----	8-1
Figure 8.2.1	Organizational Structure and Number of Staff for O&M of HTMS-----	8-2
Figure 8.2.2	Examples of Information Exchange between Traffic Management Center of HTMS for CPRR and Related Organizations -----	8-7
Figure 8.2.3	Organization Structure and Number of Staff for O&M of TMS -----	8-8
Figure 8.2.4	Explanatory Figure for Toll Collection Method and Location of Toll Plazas -----	8-13
Figure 9.1.1	Project Cost Proportion of DPR -----	9-2
Figure 9.3.1	Project Schedule of CPRR Section-1 -----	9-12
Figure 9.3.2	Composition of Project Budget -----	9-13
Figure 10.2.1	Project Schedule of CPRR Section 1 -----	10-2
Figure 11.2.1	Original Plan and New Plan of CPRR-----	11-4

Figure 11.2.2	Comparison of the Original Plan and the New Plan (1)	11-5
Figure 11.2.3	Comparison of the Original Plan and the New Plan (2)	11-6
Figure 11.2.4	District Boundary and Sections of the CPRR Project	11-11
Figure 11.2.5	Location Map of Public Consultation Meeting 2014	11-17
Figure 11.2.6	Photos from Public Consultations in 2014	11-18
Figure 11.3.1	Images of the Land Use on ROW of Section 1 and Nearby Area	11-22
Figure 11.3.2	Average Monthly Rainfall and Highest and Lowest Temperature in Chennai	11-22
Figure 11.3.3	Mangrove Vegetation on the Kosasthalaiyar River	11-23
Figure 11.3.4	Mangrove Vegetation on Kosasthalaiyar River (Close-up)	11-24
Figure 11.3.5	Pucca House Example	11-25
Figure 11.3.6	Semi-Pucca House Example	11-25
Figure 11.3.7	Kutchra House Example	11-26
Figure 11.3.8	Flowchart to Obtain EC in Tamil Nadu	11-28
Figure 11.3.9	Section 1 and CRZ	11-31
Figure 11.3.10	Weather Data for Chennai (November 2017)	11-46
Figure 11.3.11	Weather Data for Chennai (March 2018)	11-46
Figure 11.3.12	Air, Noise, and Vibration Monitoring Locations	11-47
Figure 11.3.13	Sulphur Dioxide Monitoring Results	11-48
Figure 11.3.14	Nitrogen Dioxide Monitoring Results	11-48
Figure 11.3.15	PM ₁₀ Monitoring Results	11-48
Figure 11.3.16	PM _{2.5} Monitoring Results	11-49
Figure 11.3.17	Types of Waste Expected to be Generated from Section 1	11-49
Figure 11.3.18	Water Sampling Locations	11-50
Figure 11.3.19	Noise Monitoring Results	11-51
Figure 11.3.20	Vibration Monitoring Results	11-52
Figure 11.3.21	Ecological Monitoring Stations	11-53
Figure 11.3.22	Site Photos	11-55
Figure 11.3.23	Location of Approved Quarry Sites	11-62
Figure 11.3.24	Implementation Structure during the Construction Phase	11-81
Figure 11.3.25	Implementation Structure During the Operation Phase	11-81
Figure 11.3.26	Steps of Grievance Redress on EIA	11-83
Figure 11.4.1	Procedure of Land Acquisition Based on TN Highways Act 2001	11-92
Figure 11.4.2	Common Property Resources to be Affected	11-109
Figure 11.4.3	Process of Grievance Redressal Mechanism	11-133
Figure 11.4.4	Institutional Arrangement in the Implementation of RAP	11-138
Figure 11.5.1	Locations of Stakeholders and Public Consultation Meetings in 2018	11-148
Figure 11.5.2	Public Notice on English Newspaper (left) and for Tamil Paper/Posting/Handout (right)	11-150
Figure 11.5.3	Handout Explaining Section 1	11-150
Figure 11.5.4	Publication of Information about the First Meetings	11-151
Figure 11.5.5	Photos of the Minjur First Meeting	11-154
Figure 11.5.6	Photos of the Panchetti First Meeting	11-156
Figure 11.5.7	Publication of Information about the Second Meeting	11-157
Figure 11.5.8	Announcement to the General Public (the Notice) and the Cover Page of the Draft Handbook on Policy Framework Distributed in the Meeting (Tamil)	11-158
Figure 11.5.9	Photos of the Minjur Second Meeting	11-161
Figure 11.5.10	Photos of the Panchetti Second Meeting	11-164
Figure 11.5.11	Focus Group Discussion with Agriculture Labourers Working on the Affected Land	11-165
Figure 11.6.1	Alignment Change Plan of TPP Link Road	11-167
Figure 11.6.2	Comparing of the Alternative Route Plan of the TPP Link Road	11-168
Figure 11.6.3	Locations of PAHs Residences and Proposed Resettlement Site	11-193
Figure 11.6.4	Consultations by Door-to-Door Visit	11-194
Figure 11.6.5	Group Discussion and Site Visit at Bharathi Nagar	11-196
Figure 11.8.1	Land Use at or Near the Planned ROW	11-210

Figure 11.8.2	Section 3 and Mannur RF-----	11-212
Figure 11.8.3	Section 3 and Mannur RF-----	11-213
Figure 11.8.4	Existing Condition of Mannur RF-----	11-213
Figure 11.8.5	Section 5 and Thirutteri and Sengundram RFs -----	11-214
Figure 11.8.6	View of Thirutteri RF-----	11-214
Figure 11.8.7	Relationship with Section 5 (white line), Thirutteri RF (left), and Sengundram RF -11-215	11-215
Figure 11.8.8	Relationship with Section 5 (white line) and Thirutteri RF -----	11-215
Figure 11.8.9	Relationship with Section 5 (white line), Sengundram RF, and Flora in Undulation Areas (yellow circle)-----	11-216
Figure 11.8.10	Sengundram RF (front) and Native Vegetation on a Hill (back) -----	11-216
Figure 11.8.11	Weather Data for Chennai (November 2017)-----	11-222
Figure 11.8.12	Weather Data for Chennai (March 2018)-----	11-222
Figure 11.8.13	Air, Noise, and Vibration Monitoring Locations-----	11-223
Figure 11.8.14	Sulphur Dioxide Monitoring Results -----	11-224
Figure 11.8.15	Nitrogen Dioxide Monitoring Results-----	11-224
Figure 11.8.16	PM ₁₀ Monitoring Results-----	11-225
Figure 11.8.17	PM _{2.5} Monitoring Results -----	11-225
Figure 11.8.18	Water Sampling Locations-----	11-226
Figure 11.8.19	Noise Monitoring Results-----	11-227
Figure 11.8.20	Vibration Monitoring Results -----	11-228
Figure 11.8.21	The Location of RF Compensation Site-----	11-229
Figure 11.8.22	Photos of the RF Compensation Site -----	11-230
Figure 12.3.1	Location Map of CPRR and Toll Gate -----	12-17
Figure 13.2.1	Implementation Schedule of Section 1 of the Project -----	13-5

List of Tables

Table 1.1.1	Work Schedule of the Study-----	1-2
Table 1.2.1	Meeting List with Concerned Agencies of CPRR-----	1-4
Table 1.2.2	Meeting List with Concerned Agencies of CPRR ITS -----	1-10
Table 2.1.1	Composition of DPR-----	2-2
Table 2.2.1	Existing Roads in Tamil Nadu State-----	2-4
Table 2.2.2	Details of Roads in Tamil Nadu State-----	2-4
Table 2.3.1	Members of Chennai Metropolitan Development Authority-----	2-22
Table 2.4.1	Target Figure of Modal Share in 2026 against 2008-----	2-28
Table 2.4.2	Proposed Infrastructure Development: Short, Mid and Long Term -----	2-29
Table 2.4.3	Estimated Investment Cost -----	2-29
Table 2.4.4	Population Projection -----	2-30
Table 2.4.5	Employment Projection in CMA -----	2-30
Table 2.4.6	Total Water Demand in CMA-----	2-30
Table 2.4.7	Goals of Water Supply System in Chennai City Area-----	2-30
Table 2.4.8	Goals of Sewerage System in Chennai City Area-----	2-31
Table 2.4.9	Goals of Solid Waste Management System in CMA -----	2-31
Table 2.4.10	Daily Trip Projection in CMA -----	2-31
Table 2.4.11	Goals of Transportation in CMA -----	2-32
Table 2.4.12	Population Projection-----	2-32
Table 2.4.13	Land Use -----	2-33
Table 2.4.14	GRDP Share by Sector -----	2-34
Table 2.4.15	Summary of Investment in Urban Infrastructure -----	2-35
Table 2.4.16	Projected Population in Ponneri Node-----	2-35
Table 2.4.17	Real GDP Growth Rate in India -----	2-35
Table 2.4.18	Land Use Plan-----	2-36
Table 2.4.19	Road Development Plan-----	2-36
Table 2.4.20	Water Demand of Ponneri Node-----	2-37
Table 2.4.21	Construction Cost of Water Infrastructures -----	2-37
Table 2.4.22	O&M Cost of Water Infrastructures -----	2-37
Table 2.4.23	Cost of Solid Waste Management Infrastructure-----	2-38
Table 2.4.24	Responsible Organization for Arterial Roads and Project Implementation Scheme-----	2-40
Table 2.4.25	Current Situation of ITS Facilities for Arterial Roads-----	2-42
Table 3.1.1	Outline of Traffic Survey -----	3-1
Table 3.1.2	Outline of Traffic Survey -----	3-3
Table 3.2.1	Results of the Hearing Survey -----	3-5
Table 3.2.2	Outline of Traffic Survey -----	3-5
Table 3.2.3	Outline of the Project (Ennore Port) -----	3-8
Table 3.2.4	Outline of the Project (Chennai Port)-----	3-9
Table 3.2.5	Outline of the Project (Kattuppalli Port)-----	3-10
Table 3.2.6	Prediction of Cargo Handled by Year 2035 (Ennore Port)-----	3-11
Table 3.2.7	Prediction of Cargo Handled by Year 2035 (Chennai Port)-----	3-13
Table 3.3.1	Recommended Design Service Volume-----	3-16
Table 3.3.2	Daily Capacity -----	3-16
Table 3.3.3	List of Zones (1) -----	3-20
Table 3.3.4	List of Zones (2) -----	3-21
Table 3.3.5	List of Zones (3) -----	3-22
Table 3.3.6	List of Zones (4) -----	3-23
Table 3.3.7	List of Zones (5) -----	3-24
Table 3.3.8	Trip Mode Categories, Passenger Car Unit, Number of Passengers per Vehicle ---	3-25
Table 3.3.9	Growth Rate of Future Traffic Demand for Target Years Estimated by this Study from Current Origin-Destination Data (2016) -----	3-27
Table 3.3.10	Modal Share of Future Traffic Demand for Target Years -----	3-28
Table 3.3.11	Trip Generation Rate at Mahindra Industrial Park Chennai-----	3-28

Table 3.3.12	Modal Split of Traffic Handled-----	3-29
Table 3.3.13	Increase of Traffic Handled per Year-----	3-29
Table 3.3.14	Increase of Traffic Handled per Day-----	3-29
Table 3.3.15	Load Capacity by Car Type -----	3-30
Table 3.3.16	Increase of Traffic Handled using Road -----	3-30
Table 3.3.17	Future Increase of Trucks at the Port -----	3-30
Table 3.3.18	Opening Year of Major Road -----	3-31
Table 3.3.19	Modal Share of Future Traffic Demand for Target Years -----	3-37
Table 3.3.20	Total Travel Time of Each Analysis Case (unit: Vehicle Hour) -----	3-37
Table 4.1.1	Outline of Sections of CPRR-----	4-1
Table 4.3.1	Traffic Volume of Every Section for Each Case -----	4-3
Table 4.3.2	Reduction in Total Travel Time Made by Every Section for Each Case -----	4-4
Table 4.3.3	Large Vehicle Rate of Every Section for Each Case -----	4-5
Table 4.3.4	Area of Forest Land to be Diverted -----	4-5
Table 4.3.5	Impact on CRZ-----	4-5
Table 4.3.6	Area of Land to be Acquired-----	4-6
Table 4.3.7	Project Costs of CPRR Estimated in DPR-----	4-7
Table 4.3.8	EIRR for Each Case-----	4-8
Table 4.3.9	Evaluation Criteria for Prioritization -----	4-9
Table 4.3.10	Evaluation Results for Prioritization-----	4-10
Table 5.1.1	Details of Road Network in Tamil Nadu (as of 2016)-----	5-1
Table 5.3.1	Non-Plan Financial Allocation and Expenditure (Rs. in Lakhs) -----	5-12
Table 5.4.1	Minimum Mandatory Requirement of Plant and Equipment -----	5-13
Table 5.4.2	Repair/Rectification of Defects and Deficiencies (Annex-I)-----	5-20
Table 5.5.1	Recommended Length of Traffic Control Zones-----	5-24
Table 5.5.2	Frequency of Inspection-----	5-27
Table 5.5.3	Maintenance Standards of O&M Manual for CORR-----	5-27
Table 5.5.4	Frequency of Operations for Horticultural Maintenance -----	5-28
Table 5.6.1	Details of Each Road Section (New Construction Portion Only) -----	5-31
Table 5.6.2	Examples of O&M Costs (INR in Crore)-----	5-34
Table 5.6.3	Annual O&M Cost of CPRR (INR in Crore) -----	5-34
Table 5.6.4	Merits and Contents of Preventive Maintenance -----	5-35
Table 5.6.5	Cost Estimate of ITS O&M (INR in Crore)-----	5-37
Table 6.1.1	Volumes of DPR for Review-----	6-1
Table 6.1.2	Scope of Design Review -----	6-1
Table 6.1.3	Natural Conditions Survey to be Conducted in Next Design Phase-----	6-3
Table 6.1.4	Terrain Category and Ground Slope -----	6-4
Table 6.1.5	Technical Standards Applied in DPR-----	6-4
Table 6.1.6	Design Speed-----	6-5
Table 6.1.7	Design Criteria -----	6-5
Table 6.1.8	Future Traffic Volume (L: Main Road, R: Service Road) with Limitation of LOS B in DPR -----	6-6
Table 6.1.9	Future Traffic Volume and LOS (Section 1)-----	6-7
Table 6.1.10	Future Traffic Volume and LOS (Section 2)-----	6-8
Table 6.1.11	Future Traffic Volume and LOS (Section 3)-----	6-9
Table 6.1.12	Future Traffic Volume and LOS (Section 4)-----	6-10
Table 6.1.13	Future Traffic Volume and LOS (Section 5)-----	6-11
Table 6.2.1	Assessment of Horizontal Elements -----	6-23
Table 6.2.2	Assessment of Vertical Elements (1/5)-----	6-28
Table 6.2.3	Assessment of Vertical Elements (2/5)-----	6-30
Table 6.2.4	Assessment of Vertical Elements (3/5)-----	6-32
Table 6.2.5	Assessment of Vertical Elements (4/5)-----	6-34
Table 6.2.6	Assessment of Vertical Elements (5/5)-----	6-36
Table 6.2.7	Location and Type of Junction-----	6-39
Table 6.2.8	Summary of Survey and Investigation Shown on DPR-----	6-46

Table 6.2.9	Lane Distribution Factor Shown on DPR of CPRR -----	6-48
Table 6.2.10	Average Annual Daily Traffic Shown on DPR-----	6-48
Table 6.2.11	Growth Rate for Pavement Design Shown on DPR -----	6-48
Table 6.2.12	VDF for Pavement Design Shown in the DPR -----	6-49
Table 6.2.13	Proposed Pavement Thickness of Main Carriageway on DPR -----	6-50
Table 6.2.14	Proposed Pavement Thickness of Service Road in the DPR -----	6-51
Table 6.2.15	Preparation of Scenarios of Design Traffic Volume of the JICA Study Team -----	6-52
Table 6.2.16	Adopted Parameters of Pavement Design Based on AASHTO -----	6-53
Table 6.2.17	Adopted Parameters of Pavement Design Based on Japanese Standard-----	6-53
Table 6.2.18	Result of Pavement Design Made by the JICA Study Team-----	6-55
Table 6.2.19	Number of Box Culverts and Pipe Culverts in General Arrangement Drawings of CPRR -----	6-58
Table 6.2.20	Summary of Drainage Calculation of Brick Lined Trapezoidal Open Drain in the DPR -----	6-60
Table 6.2.21	Summary of Drainage Calculation of RCC Rectangular Covered Drain in the DPR -----	6-61
Table 6.3.1	Location and Type of Interchange -----	6-63
Table 6.3.2	Geometric Design Standard of Rampway of Interchange -----	6-65
Table 6.3.3	Outline of Design of IC-1 -----	6-67
Table 6.3.4	Outline of IC-2 -----	6-70
Table 6.3.5	Outline of IC-3 -----	6-73
Table 6.3.6	Outline of IC-4 -----	6-76
Table 6.4.1	Planned Number of Lanes -----	6-80
Table 6.4.2	Partially Requested Materials and Availability-----	6-82
Table 6.4.3	Comparison of the Number of Planned Structures-----	6-83
Table 6.4.4	MJB Specifications-----	6-86
Table 6.4.5	Confirmation of the Clearance Below Girders and the Vertical Alignment (MJB) -----	6-87
Table 6.4.6	Confirmation of Span Length and Type of Superstructure of MJB-----	6-88
Table 6.4.7	Confirmation Result of Reinforced Earth Wall Height (MJB) -----	6-90
Table 6.4.8	Revision Suggestions on the Substructure Located at Bridge Ends (MJB) -----	6-91
Table 6.4.9	Estimation of Cost Fluctuation Due to Substructure Revision (MJB101-LA3)-----	6-92
Table 6.4.10	MNB Specification-----	6-94
Table 6.4.11	Confirmation of the Clearance Below Girders and Vertical Alignment (MNB)-----	6-95
Table 6.4.12	Confirmation of Span Length and Type of Superstructure (MNB)-----	6-96
Table 6.4.13	ROB Specifications -----	6-101
Table 6.4.14	Confirmation of Span Length and Type of Superstructure (ROB) -----	6-102
Table 6.4.15	Confirmation Result of Reinforced Earth Wall Height (ROB)-----	6-103
Table 6.4.16	VUP and LVUP Specification -----	6-104
Table 6.4.17	Vertical Clearance-----	6-106
Table 6.4.18	Vertical Clearance (IRC-87:2013 Page15) -----	6-106
Table 6.4.19	Result of Vertical Clearance Verification (VUP, LVUP) -----	6-107
Table 6.4.20	Confirmation of Span Length and Type of Superstructure (VUP • LVUP) -----	6-108
Table 6.4.21	Confirmation Result of Reinforced Earth Wall Height (VUP • LVUP) (1/2)-----	6-109
Table 6.4.22	Confirmation Result of Reinforced Earth Wall Height (VUP • LVUP) (2/2)-----	6-110
Table 6.4.23	Box Culvert Specification (1/6) -----	6-113
Table 6.4.24	Box Culvert Specification (2/6) -----	6-114
Table 6.4.25	Box Culvert Specification (3/6) -----	6-115
Table 6.4.26	Box Culvert Specification (4/6) -----	6-116
Table 6.4.27	Box Culvert Specification (5/6) -----	6-117
Table 6.4.28	Box Culvert Structure List (6/6) -----	6-118
Table 6.4.29	Interchange Specification -----	6-122
Table 6.4.30	Confirmation of Span Length and Type of Superstructure (IC)-----	6-123
Table 6.4.31	Confirmation Result of Reinforced Earth Wall Height (IC) -----	6-125

Table 6.5.1	Suggestion on the Abutment Type (MJB101) -----	6-136
Table 6.5.2	Major Influence of Climate Change on Roads-----	6-140
Table 6.5.3	Adaptation Measures against Climate Change in the Project-----	6-140
Table 7.2.1	Design Concept of HTMS -----	7-4
Table 7.2.2	Location Plan Concept and Quantity of Roadside Equipment of HTMS-----	7-5
Table 7.3.1	Toll Lane Composition -----	7-7
Table 8.2.1	Roles of the Project Director -----	8-3
Table 8.2.2	Roles of the Staff of the HTMS O&M Team -----	8-3
Table 8.2.3	Example of Shift Arrangement of HTMS O&M Team -----	8-7
Table 8.2.4	Required Number of Staff and Shift Arrangement for O&M of TMS for Two Toll Plazas -----	8-9
Table 8.2.5	Roles of the Project Director -----	8-10
Table 8.2.6	Roles of Staff of TMS O&M Team -----	8-10
Table 8.2.7	Example of Shift Arrangement of TMS O&M Team -----	8-12
Table 8.2.8	Cash Collection: Toll Collection Method for Each Case of Vehicle Traveling ----	8-13
Table 8.2.9	ETC: Toll Collection Method for Each Case of Vehicle Traveling -----	8-14
Table 9.1.1	Component and Cost Estimate in DPR-----	9-1
Table 9.1.2	Summary of Civil Work Direct Cost -----	9-1
Table 9.1.3	Cost Summary, Section 1 to 5 in DPR -----	9-3
Table 9.1.4	Work Items and Application Status of Each Section -----	9-4
Table 9.1.5	Basis of Base Cost of DPR -----	9-5
Table 9.1.6	Basis of Base Cost of DPR -----	9-6
Table 9.1.7	Ratio of Unit Price Inflation-----	9-6
Table 9.2.1	Employment Labour Relations Laws-----	9-7
Table 9.2.2	Classification of GST-----	9-9
Table 9.3.1	Project Cost Item and Coverage of Japanese Loan -----	9-14
Table 9.3.2	Pre-condition of Cost Estimate for CPRR -----	9-15
Table 9.3.3	Price Escalation -----	9-15
Table 9.3.4	Cost Breakdown of Consultant Fee for CPRR-----	9-16
Table 9.3.5	Construction Cost Summary of CPRR (Civil Works)-----	9-17
Table 9.3.6	Cost Summary of CPRR (ITS for CPRR) -----	9-18
Table 9.3.7	Cost Summary of Operation and Maintenance of ITS for CPRR -----	9-18
Table 9.3.8	Summary of Project Cost CPRR (Sec-1) -----	9-19
Table 9.3.9	Summary of Project Cost CPRR (Sec-2) -----	9-20
Table 9.3.10	Summary of Project Cost CPRR (Sec-3) -----	9-20
Table 9.3.11	Summary of Project Cost CPRR (Sec-4) -----	9-21
Table 9.3.12	Summary of Project Cost CPRR (Sec-5) -----	9-21
Table 11.0.1	Scope of Section 1-----	11-1
Table 11.1.1	Seven Principles of JICA Environmental and Social Consideration -----	11-2
Table 11.2.1	Consideration of Avoidance, Mitigation, and Minimization of Impacts in the New Plan-----	11-3
Table 11.2.2	Comparison of Alternative Plans -----	11-7
Table 11.2.3	Categorization Criteria of the JICA Guidelines -----	11-12
Table 11.2.4	Highway Project that Requires an EIA Report and Its Approval -----	11-12
Table 11.2.5	Summary of Environmental and Social Impacts Described in DPR EIA Report -	11-13
Table 11.2.6	Planned Length of Project Road by Section-----	11-15
Table 11.2.7	Summary of Existing Preliminary RAP Survey in DPR-----	11-16
Table 11.2.8	Summary of Implementation of Public Consultations-----	11-17
Table 11.2.9	Information Disseminated in Public Consultation -----	11-18
Table 11.2.10	Opinions and Suggestions Expressed in Public Consultations in 2014 -----	11-18
Table 11.3.1	Current State of Land Use -----	11-21
Table 11.3.2	Population and Household-----	11-24
Table 11.3.3	Housing Environment -----	11-26
Table 11.3.4	Economic Condition in Tamil Nadu State in 2014/2015 -----	11-26
Table 11.3.5	Highway Project that Requires an EIA Report and Its Approval-----	11-27

Table 11.3.6	Gaps between JICA Guidelines and Indian System, and Bridging Measures -----	11-29
Table 11.3.7	Summary of the CRZ Objectives and Relevance to Section 1-----	11-30
Table 11.3.8	Area to be Designated as Coastal Regulation Zone-----	11-31
Table 11.3.9	Classification of Coastal Regulation Zone -----	11-31
Table 11.3.10	Project Components and Typically Expected Environmental and Social Impacts	11-33
Table 11.3.11	Scoping of Potential Impacts-----	11-34
Table 11.3.12	Item, Content, and Method for Environmental and Social Study -----	11-37
Table 11.3.13	Environmental Baseline Monitoring Plan -----	11-40
Table 11.3.14	Summary of Survey Results-----	11-40
Table 11.3.15	Air, Noise, and Vibration Monitoring Sites -----	11-47
Table 11.3.16	Water Sampling Results-----	11-49
Table 11.3.17	Section-wise Details of Ecological Monitoring Stations-----	11-52
Table 11.3.18	List of Tree Species Recorded in the Ecological Survey -----	11-55
Table 11.3.19	List of Mammals Recorded in the Ecological Survey-----	11-56
Table 11.3.20	List of Birds Recorded in the Ecological Survey-----	11-57
Table 11.3.21	List of Amphibians and Reptiles Recorded in the Ecological Survey-----	11-58
Table 11.3.22	List of Insects Recorded in the Ecological Survey-----	11-59
Table 11.3.23	List of Fishes Recorded in the Ecological Survey -----	11-60
Table 11.3.24	List of Molluscans, Crabs and Shrimps Recorded in the Ecological Survey -----	11-60
Table 11.3.25	List of Planktons Recorded in the Ecological Survey -----	11-60
Table 11.3.26	Details of the Number of Trees to be Affected -----	11-61
Table 11.3.27	Water Resources- Section 1 -----	11-61
Table 11.3.28	Impact Assessment and Evaluation -----	11-63
Table 11.3.29	Environmental Mitigation Plan -----	11-67
Table 11.3.30	Environmental Monitoring Plan -----	11-76
Table 11.3.31	Summary Details of Reporting Formats -----	11-80
Table 11.3.32	Roles and Responsibility of Line Departments and Stakeholders -----	11-82
Table 11.3.33	Grievance Redressal Mechanism-----	11-83
Table 11.3.34	Queries, Suggestions, and Replies in the Minjur First Meeting-----	11-84
Table 11.3.35	Queries, Suggestions and Replies in Panchetti First Meeting -----	11-85
Table 11.3.36	Queries, Suggestions, and Replies in Panchetti Second Meeting -----	11-85
Table 11.3.37	TNSPCB Consultations -----	11-86
Table 11.3.38	Discussions in Kanheepuram District -----	11-86
Table 11.3.39	Discussions in Kanheepuram District -----	11-87
Table 11.4.1	Planned Length of Project Road by Section-----	11-90
Table 11.4.2	System, Target, and Process of Compensation and Assurances Defined by LARRA 2013-----	11-91
Table 11.4.3	Structure and Contents of Tamil Nadu Rules 2017 to LARRA 2013 -----	11-92
Table 11.4.4	First Publication Dates of 15(2) Notification Based on Tamil Nadu Highways Act-11- 93	
Table 11.4.5	Procedure of SIA and Land Acquisition in TNRSR -----	11-93
Table 11.4.6	Procedure of Land Acquisition and Minimum Days Required in TNRSR -----	11-94
Table 11.4.7	Gaps Between JICA Guideline and Standard Land Acquisition of HMPD and Policies Taken in Project-----	11-96
Table 11.4.8	Project Affected Assets in Section 1 (Main Road and TPP Link Road (Original Alignment))-----	11-105
Table 11.4.9	Location of PAFs to be Relocated-----	11-106
Table 11.4.10	Village-wise Land Area to be Acquired-----	11-106
Table 11.4.11	Use, Types, and Number of Floors of Structures to be Affected-----	11-107
Table 11.4.12	Impacts on Structure - Tenure Wise -----	11-107
Table 11.4.13	Extent of Loss - Floor Area-----	11-108
Table 11.4.14	Common Property Resources to be Affected -----	11-108
Table 11.4.15	Trees Owned by PAH and to be Affected -----	11-109
Table 11.4.16	Vulnerable PAH to be Affected -----	11-110
Table 11.4.17	Willingness to Cooperate for Resettlement Process -----	11-110

Table 11.4.18	Age Classification-----	11-110
Table 11.4.19	Mother Tongue-----	11-111
Table 11.4.20	Religion-----	11-111
Table 11.4.21	Social Stratification-----	11-111
Table 11.4.22	Education Profile of the PAH Members-----	11-111
Table 11.4.23	Occupation Profile of the PAH Members-----	11-112
Table 11.4.24	Monthly Family Income-----	11-112
Table 11.4.25	Period of Stay-----	11-113
Table 11.4.26	Housing Facilities-----	11-113
Table 11.4.27	Household Assets-----	11-114
Table 11.4.28	Average Monthly Expenditure of a Household-----	11-114
Table 11.4.29	Source of Drinking Water-----	11-115
Table 11.4.30	Mode of Transport-----	11-115
Table 11.4.31	Business and Commerce to be Affected by Section 1-----	11-115
Table 11.4.32	Annual Net Income from Business-----	11-116
Table 11.4.33	Business is the Primary Source of Income-----	11-116
Table 11.4.34	Other Sources of Income Besides Businesses to be Affected-----	11-116
Table 11.4.35	Perceived Positive Impacts-----	11-116
Table 11.4.36	Perceived Negative Impacts-----	11-117
Table 11.4.37	Gender - Absentee Land Owners-----	11-117
Table 11.4.38	Age Distribution - Absentee Land Owners-----	11-118
Table 11.4.39	Religion - Absentee Land Owners-----	11-118
Table 11.4.40	Social Strata - Absentee Land Owners-----	11-118
Table 11.4.41	Occupation Pattern - Absentee Land Owners-----	11-119
Table 11.4.42	Sources of Income - Absentee Land Owners-----	11-119
Table 11.4.43	Income Pattern from Agricultural Source- Absentee Land Owners-----	11-119
Table 11.4.44	Place of Stay - Absentee Land Owners-----	11-120
Table 11.4.45	Type of Land - Absentee Land Owners-----	11-120
Table 11.4.46	Holding of Land Parcels - Absentee Land Owners-----	11-120
Table 11.4.47	Irrigated Land-----	11-121
Table 11.4.48	Cropping Pattern-----	11-121
Table 11.4.49	Irrigation Source-----	11-121
Table 11.4.50	Harvesting Times in a Year-----	11-121
Table 11.4.51	Cropping Area Ratio of Irrigated Land-----	11-121
Table 11.4.52	Consumption Pattern of Produce from Land-----	11-122
Table 11.4.53	Leased Land-----	11-122
Table 11.4.54	Size of Owned Land Before and After the Project-----	11-122
Table 11.4.55	Awareness on Loss of Land Conducted by Government-----	11-123
Table 11.4.56	Awareness on Land Acquisition Process and R&R Benefits-----	11-123
Table 11.4.57	Sources of Awareness on LA Process and R&R Benefits-----	11-123
Table 11.4.58	Dates of the First Publication of the 15 (2) Notification on Papers-----	11-124
Table 11.4.59	Plan of Compensation for Loss of Assets-----	11-124
Table 11.4.60	Plan of Livelihood Rehabilitation Assistances-----	11-126
Table 11.4.61	Detailed Checklist for Selection of Resettlement Site-----	11-127
Table 11.4.62	Entitlement Matrix-----	11-128
Table 11.4.63	Roles and Responsibility of the Committees-----	11-133
Table 11.4.64	Institutional Arrangement in the Implementation of RAP-----	11-136
Table 11.4.65	RAP Implementation Schedule-----	11-139
Table 11.4.66	Estimate of Direct Land Cost-----	11-140
Table 11.4.67	Cost Estimate for Land Acquisition-----	11-141
Table 11.4.68	Unit Cost Used for Estimation of Structure Compensation-----	11-141
Table 11.4.69	Type-wise Floor Area to be Affected-----	11-141
Table 11.4.70	Compensation Cost for Structures to be Affected-----	11-142
Table 11.4.71	Compensation Cost for Common Property Resources-----	11-142
Table 11.4.72	Resettlement and Rehabilitation Cost for Land Title Holders-----	11-143

Table 11.4.73	Resettlement and Rehabilitation Cost for Non-Title Holders - Squatters -----	11-143
Table 11.4.74	Resettlement and Rehabilitation Cost for Non-Title Holders - Tenants (Residential and Commercial) -----	11-143
Table 11.4.75	Assistance for Vulnerable Households -----	11-143
Table 11.4.76	Resettlement and Rehabilitation Cost for Non-Title Holders - Workers -----	11-143
Table 11.4.77	Management and Operation Cost and Total Cost of RAP Implementation -----	11-144
Table 11.4.78	Indicators Suggested for Internal Monitoring-----	11-144
Table 11.4.79	Indicators and Methods Suggested for External Monitoring-----	11-146
Table 11.5.1	NGOs and Specialists Invited and Participated-----	11-149
Table 11.5.2	Summary of the First Meetings -----	11-152
Table 11.5.3	Queries, Suggestions, and Replies in the Minjur First Meeting -----	11-152
Table 11.5.4	Queries, Suggestions and Replies in the Panchetti First Meeting -----	11-155
Table 11.5.5	Summary of the Second Meetings -----	11-158
Table 11.5.6	Queries, Suggestions, and Replies in the Minjur Second Meeting -----	11-159
Table 11.5.7	Queries, Suggestions, and Replies in the Panchetti Second Meeting-----	11-162
Table 11.6.1	Comparative Route Study of the TPP Link Road -----	11-169
Table 11.6.2	Scope of Potential Impacts and Changes with the New Alignment of the TPP Link Road -----	11-171
Table 11.6.3	Summary of Survey Results after Alignment Change of the TPP Link Road ----	11-175
Table 11.6.4	Impact Assessment and Evaluation -----	11-177
Table 11.6.5	Plan of Section 1 (Main Road and TPP Link Road (New Alignment))-----	11-179
Table 11.6.6	Project Affected Assets in Section 1 (Main Road and TPP Link Road (New Alignment))-----	11-180
Table 11.6.7	Village-wise Land Area to be Acquired-----	11-181
Table 11.6.8	Use, Type, and Number of Floors of Structures to be Affected -----	11-181
Table 11.6.9	Impacts on Structure -----	11-181
Table 11.6.10	Extent of Loss - Floor Area-----	11-182
Table 11.6.11	Trees Owned by PAHs and Trees to be Affected -----	11-182
Table 11.6.12	Vulnerable PAHs to be Affected -----	11-182
Table 11.6.13	Willingness for Resettlement Site -----	11-182
Table 11.6.14	Age of the PAH Members -----	11-183
Table 11.6.15	Mother Tongue-----	11-183
Table 11.6.16	Religion-----	11-183
Table 11.6.17	Social Stratification -----	11-184
Table 11.6.18	Education-----	11-184
Table 11.6.19	Occupation-----	11-184
Table 11.6.20	Monthly Family Income-----	11-185
Table 11.6.21	Stay in the Structure-----	11-185
Table 11.6.22	Housing Facilities -----	11-186
Table 11.6.23	Owned -----	11-186
Table 11.6.24	Average Monthly Expenditure of a Household-----	11-186
Table 11.6.25	Source of Drinking Water-----	11-186
Table 11.6.26	Mode of Transport-----	11-187
Table 11.6.27	Loss of Rental Income-----	11-187
Table 11.6.28	Perceived Positive Benefits of the TPP Link Road (New Alignment) -----	11-187
Table 11.6.29	Perceived Negative Impacts -----	11-188
Table 11.6.30	Gender of Affected Absentee Land Owners -----	11-188
Table 11.6.31	Age Distribution -----	11-188
Table 11.6.32	Religion-----	11-188
Table 11.6.33	Social Strata -----	11-189
Table 11.6.34	Occupations of Absentee Land Owners-----	11-189
Table 11.6.35	Main Source of Income of Absentee Land Owners-----	11-189
Table 11.6.36	Location of Affected Land and Residence-----	11-189
Table 11.6.37	Type of Land to be Affected -----	11-190
Table 11.6.38	Number of Owned Land Parcels-----	11-190

Table 11.6.39	Crop Types-----	11-190
Table 11.6.40	Irrigated Land -----	11-190
Table 11.6.41	Land Given for Lease-----	11-190
Table 11.6.42	Assets on Land Parcels in ROW Owned by Absentee Land Owners -----	11-191
Table 11.6.43	Area of Affected Land Parcels After the Project-----	11-191
Table 11.6.44	Awareness on Government Intention of Land Acquisition-----	11-191
Table 11.6.45	Awareness on Land Acquisition Process and Resettlement and Rehabilitation Benefits-----	11-191
Table 11.6.46	Sources of Awareness on Land Acquisition Process and R&R Benefits -----	11-191
Table 11.6.47	Information on Proposed Resettlement Site-----	11-192
Table 11.6.48	Information Disseminated in the Stakeholder Meetings -----	11-195
Table 11.6.49	Queries and Opinions Obtained During Door-to-Door Consultation -----	11-195
Table 11.6.50	Suggestions and Comments in the Group Discussion-----	11-197
Table 11.8.1	Current State of Land Use -----	11-210
Table 11.8.2	Relationship to Areas with Development Regulation and Project -----	11-211
Table 11.8.3	Summary of Survey Results-----	11-217
Table 11.8.4	Air, Noise, and Vibration Monitoring Site -----	11-223
Table 11.8.5	Water Sampling Results-----	11-226
Table 11.8.6	Number of Trees to be Affected-----	11-228
Table 11.8.7	Plant Species in RF Compensation Site-----	11-229
Table 11.8.8	Water Resources - Section 2 -----	11-231
Table 11.8.9	Water Resources - Section 3 -----	11-231
Table 11.8.10	Water Resources - Section 5 -----	11-232
Table 12.1.1	VOC by Type of Vehicle in 2009 -----	12-2
Table 12.1.2	VOC by Velocity and Type of Vehicle in 2017 -----	12-2
Table 12.1.3	GDP Deflator-----	12-2
Table 12.1.4	Travel Time Cost (2017)-----	12-3
Table 12.1.5	Base Rate-----	12-5
Table 12.1.6	Applicable Rate for Toll -----	12-5
Table 12.1.7	Wholesale Price Index-----	12-5
Table 12.2.1	Project Cost in Market Price (Section 1–Excluding TPP Link Road)-----	12-7
Table 12.2.2	Project Cost in Market Price (TPP Link Road, Original Alignment) -----	12-8
Table 12.2.3	Project Cost in Market Price (Section 2)-----	12-9
Table 12.2.4	Project Cost in Market Price (Section 3)-----	12-10
Table 12.2.5	Project Cost in Market Price (Section 4)-----	12-11
Table 12.2.6	Project Cost in Market Price (Section 5)-----	12-12
Table 12.2.7	EIRR for Each Case-----	12-13
Table 12.2.8	Cash Flow Table for EIRR Calculation (Case No. 1) -----	12-13
Table 12.2.9	Cash Flow Table for EIRR Calculation (Case No. 2) -----	12-14
Table 12.2.10	Cash Flow Table for EIRR Calculation (Case No. 3) -----	12-15
Table 12.2.11	Cash Flow Table for EIRR Calculation (Case No. 4) -----	12-16
Table 12.3.1	Future Traffic Demand Forecast (2024, 2030, 2040) TPP Link Road (Original Alignment)-----	12-18
Table 12.3.2	Future Traffic Demand Forecast (2024, 2030, 2040) TPP Link Road (New Alignment)-----	12-18
Table 12.3.3	Cash Flow Table for EIRR Calculation (Section 1; After the Alignment Change)-----	12-19
Table 12.3.4	Cash Flow Table for FIRR Calculation (Section 1; After the Alignment Change)-----	12-20
Table 13.1.1	Result of Prioritization-----	13-1

Abbreviations

ATIS	Advance Traveler Information System
ATCC	Automatic Traffic Counter cum Classifier
ATCS	Area Traffic Signal Control System
BC (B/C)	Benefit Cost Ratio
BRT	Bus Rapid Transit
BTS	Bus Tracking System
BP	Beginning Point
CE	Chief Engineer
CEO	Chief Executive Officer
CFO	Chief Financial Officer
CFS	Container Freight Station
CCTV	Closed-Circuit Television
CMA	Chennai Metropolitan Area
CMDA	Chennai Metropolitan Development Authority
CMRL	Chennai Metropolitan Rail Limited
CMWSSB	Chennai Metropolitan Water Supply and Sewerage Board
CP (C/P)	Counterpart
CPRR	Chennai Peripheral Ring Road
CRZ	Coastal Regulation Zone
C/S	Construction Supervision
CSCL	Chennai Smart City Limited
CTP	Chennai Traffic Police
CTTS	Comprehensive Traffic and Transportation Study
D/D	Detailed Design
DEA	Department of Economic Affairs
DFR (DF/R)	Draft Final Report
DOE	Department of Environment
DPR	Detailed Project Report
EC	Environmental Clearance
ECR	East Coast Road
EIA	Environmental Impact Assessment
EIRR	Economic Internal Rate of Return
EMP	Environmental Management Plan
EP	End Point
ETC	Electronic Toll Collection
ETMS	Electronic Ticket Management System
F/F	Fact Finding
FIDIC	Federation International des Ingenious-Conseils
FIRR	Financial Internal Rate of Return
FMB	Field Measurement Book
FR (F/R)	Final Report
GCC	Greater Chennai Corporation
GOI	the Government of India
GOJ	the Government of Japan
GoTN	the Government of Tamil Nadu
GPS	Global Positioning System
GST	Goods and Service Tax
HMPD	Highways & Minor Ports Department
HTMS	Highway Traffic Management System
IC	Interchange
ICR (IC/R)	Inception Report
IHMCL	Indian Highways Management Company Limited

IIT	Indian Institute of Technology
IPCC	Intergovernmental Panel on Climate Change
IRC	Indian Road Congress
IRR	Inner Ring Road/Internal Rate of Return
IT	Information Technology
ITMS	Integrated Traffic Management System
ITR	Interim Report
ITS	Intelligent Transport System
JCT (Jct)	Junction
JICA	Japan International Cooperation Agency
JST	JICA Study Team
LA (L/A)	Loan Agreement
LARAP	Land Acquisition & Resettlement Action Plan
LPS	Land Plan Schedule
LVUP	Light Vehicle Under Pass
MJB	Major Bridge
MM (M/M)	Man-Month
MNB	Minor Bridge
MTC	Metropolitan Transport Corporation
MORTH	Ministry of Road Transport and Highways
NEXCO	Nippon Expressway Co., Ltd.
NH	National Highway
NHAI	National Highway Authority of India
NPV	Net Present Value
NURM	National Urban Renewal Mission
NUTP	National Urban Development Plan
OD	Origin & Destination
ODA	Official Development Assistance
OM (O&M)	Operation & Maintenance
ORR	Outer Ring Road
PAF	Project Affected Family
PAH	Project Affected Household
PAP	Project Affected Person
PIS	Passenger Information System
PIT	Project Implementation Team
PMC	Project Management Consultant
PWC	Pricewaterhouse Cooper
PQ	Pre-Qualification
RAP	Resettlement Action Plan
RF	Reserved Forest
RFID	Radio Frequency Identifier
ROB	Railway Overhead Bridge
ROW	Right of Way
SBD	(JICA) Standard Bidding Documents
SEC (Sec)	Section
SH	State Highway
SIA	Social Impact Assessment
SLA	Service Level Agreement
SPM	Suspended Particulate Matter
SS	Suspended Solids
STL	Sub Team Leader
SPV	Special Purpose Vehicle
TANGEDCO	Tamil Nadu Generation and Distribution Corporation
TEU	Twenty-foot Equivalent Unit
TIS	Traffic Information System

TL	Team Leader
TMS	Traffic Management System
TN	Tamil Nadu
TNIDB	Tamil Nadu Infrastructure Development Board
TNRDC	Tamil Nadu Road Development Company
TNRSP	Tamil Nadu Road Sector Project
TNSDC	Tamil Nadu State Data Center
TNSEAC	Tamil Nadu State Expert Appraisal Committee
TNSEIAA	Tamil Nadu State Environmental Impact Assessment Authority
TNSPCB	Tamil Nadu State Pollution Control Board
TPP	Tiruvottiyur Ponneri Pancheti
TPY	Truck Parking Yard
TUFIDCO	Tamil Nadu Finance and Infrastructure Development Corporation
UNFCCC	United Nations Framework Convention on Climate Change
VGf	Viability Gap Funding
VMS	Variable Message Signs
VUP	Vehicle Under Pass
WB	World Bank
WIM	Weigh-In-Motion

1. INTRODUCTION

1.1 Background of the Study

As in other major cities in India, traffic congestion is getting worse in Chennai Metropolitan Area (hereinafter referred to as “CMA”), which is the target area of the study, because road infrastructure improvements have not caught up with the increase in traffic demand due to population growth and economic development.

The Government of Tamil Nadu (GoTN) is promoting the development of roads and public transportation as a countermeasure to traffic congestion in CMA. The major arterial road network in CMA consists of National Highways No. 5, No. 205, No. 4, and No. 45 as major radial roads, and Inner Ring Road (IRR), Chennai Bypass, and Outer Ring Road (ORR) as ring roads. The implementation of the Chennai Peripheral Ring Road (CPRR) Project is expected to contribute to the further expansion of the Radial-Ring Road Network corresponding to the growing traffic demand.

In addition, as a countermeasure to alleviate congestion at the center of CMA where the development site for road infrastructure is limited, the improvement of Intelligent Transport System (ITS) facilities that promote efficient use of the road is an issue.

Based on this background, the Government of India (GoI) has prepared the Detailed Project Report (DPR) describing the development plan of CPRR and ITS and has requested the Government of Japan (GoJ) for loan assistance.

1.2 Objectives of the Study

The study aims to collect necessary information to appraise the Project for it to be implemented under the Official Development Assistance (ODA) scheme through the confirmation of the objectives and the outline of the Project, including project cost, implementation schedule, procurement and construction method, project organization, capability of operation and maintenance, as well as social and environmental conditions.

1.3 Target Sections of the Study

The DPR presents the implementation plan for the following:

- Construction of CPRR (widening section: 36.5 km, new section: 96.9 km, total: 133 km), and
- Development of ITS facilities for CPRR and for the CMA road network.

1.4 Components of the Final Report

The subject of this study was originally the CPRR Project and the Chennai City ITS Project; however, the procedure for environmental and social consideration of the CPRR Project was delayed. For this reason, JICA decided to separate the Chennai City ITS Project from the CPRR Project and aimed only for the Chennai City ITS project as the initial goal for the March 2018 Loan Agreement (L/A). For the CPRR project, JICA and HMPD confirmed that the section 1 will be the priority for the ODA loan.

With this, the CPRR Project is compiled as Volume 1 and the Chennai City ITS Project as Volume 2 in this report.

2. PRESENT CONDITION AND CIRCUMSTANCES OF THE PROJECT

2.1 Outline of the Chennai Peripheral Ring Road (CPRR) Development Project

Objectives of the Project

The objective of the project is to address the rapidly increasing road traffic demand in the Chennai Metropolitan Area (CMA) by constructing CPRR and developing Intelligent Transport System (ITS) facilities, thereby contributing to the sustainable economic growth in CMA. The Project is expected to improve the connectivity in and around Chennai City by:

- Formulating the Radial-Ring Road Network in CMA in collaboration with other ring roads such as the Inner Ring Road (IRR), the Chennai Bypass, and the Outer Ring Road (ORR) in order to provide alternate routes for traffic as well as to improve redundancy of the road network,

- Providing a direct access to Ennore Port and Kattupalli Port from industrial clusters located in suburban areas of CMA in order to accelerate industrial and economic growth, and
- Improving efficiency in the use of the road network by providing ITS facilities such as a traffic information system and a traffic management system for CPRR and the central area of CMA.

Past Studies on the Project

CPRR was conceptualized to provide better connectivity around the city catering to future traffic requirements, and to provide efficient commercial transportation by enhancing port connectivity. This road will facilitate container movement from the southern districts to Ennore Port and Kattupalli Port.


According to the DPR, the alignment of CPRR was approved by the Steering Committee and was finalized by the Principal Secretary of HMPD on 9 July 2014.

The JICA Study Team requested HMPD to provide all volumes of the DPR; however, some volumes were not available because they were under the process of obtaining concurrence from other concerned departments such as the Public Works Department (PWD) and the Water Resource Department (WRD). Although some parts of the DPR such as “Design Report (Structures)” and “Rate Analysis” were not available at the time of review, these were finally provided after February 2018. As such, the JICA Study Team obtained all documents except “Technical Specifications”. However, further modification and updating by HMPD are still ongoing, even after receiving additional parts of the DPR; thus, there are inconsistencies among the series of the provided report.

2.2 Present Condition and Issues of Road Network

Roads in CMA have been developed following the pattern of the Radial-Ring Road Network as shown in Figure 2.2.1. Major radial roads which originate at the center of Chennai City are NH4 (towards Mumbai via Bengaluru), NH5 (towards Kolkata), NH45 (towards Madurai), and NH205 (towards Tirupathi). With respect to ring roads, the IRR was first proposed as a city bypass road in 1968, and construction started in the 1980s from its central arm connecting NH45 to NH5. Subsequently, the northern and southern arms were developed. Then, the second ring road, the Chennai Bypass, was opened in 2008. However, since the urbanized area of Chennai is rapidly expanding, these two ring roads were incorporated into the built-up area. Therefore, the third ring road, or the ORR, is currently being developed, and the CPRR was even proposed to enhance the road network for further expansion of the metropolitan area and increase of traffic demand.

Tamil Nadu State has highways and roads of 62,468 km in length, and a large part of National Highways (NH) and State Highways (SH) have double or more lanes (99% for NH and 97% for SH).



Source: JICA Study Team based on OpenStreetMap

Figure 2.2.1 Road Network in CMA

The issues of the road network in CMA are summarized as follows:

Concentration of Traffic in the Core Area of Chennai

The incompleteness of the road network development in the pattern of the Radial-Ring Road Network in CMA (construction of ring roads has not caught up with the increase in traffic demand) is causing serious traffic congestion in major roads towards the city center. Traffic is concentrated particularly in the core area of Chennai. It was found that more than 200,000 vehicles per day are traversing NH45 and IRR, including motorbikes. On the other hand, the traffic volume on the same road but in the suburbs is less than 70,000 vehicles per day. Similar characteristics were found in other major roads. As a result, the travel speed of traffic towards Chennai City in the morning peak hour becomes less than 30 km/hr in the city center.

It is therefore required to disperse incoming traffic before it comes into the city center.

High Proportion of Large Vehicles

A high ratio of large vehicles is found in the suburban section of NH5, NH4, and NH45. This indicates that these roads are used by a large number of commercial vehicles, such as heavy lorries and trailers, to access the industrial areas and the Kattupalli/Ennore/Chennai Ports. The high proportion of slow-moving large vehicles causes a decrease in the overall travel speed of traffic.

A large number of large vehicles are frequently passing through small villages in the suburbs. Thus, there are a lot of pedestrians and motorcycles in the villages that are always facing high risks of traffic accidents.

Hence, a new link connecting industrial areas in the suburban area to ports shall be developed to ease the load of existing highways.

Expansion of Built-up Areas

Rapid economic growth and increase in the population of CMA is encouraging the urbanized built-up area to expand, thereby changing the classification of IRR and Chennai Bypass from bypass roads to urban highways. The ORR which is currently being constructed will be, once it opens, the newest ring road with the largest radius of 20 to 30 km; however, urban development is approaching such current outskirts.

The necessity of the development of further ring roads has been recognized to enhance the road network as well as improve redundancy of the network.

2.3 Present Condition and Issues of Traffic in the Study Area

Traffic Signal Shortage

There are many intersections without traffic signals in Chennai. At such intersections, barricades and roundabouts are adopted as alternative facilities. However, such facilities cause problems such as traffic congestion and increase in travel time. In addition, pedestrian safety is threatened because crossing at intersections without signals involves great danger.

In short, the lack of signals causes traffic congestion and prolonged travel time. Therefore, it is necessary to secure efficient traffic operation and pedestrian safety by installing traffic signals.

Processing Capacity and Operation at the Chennai Port

Due to the small processing capacity and the inefficient operation of the Chennai Port, large vehicles flow into community roads and form a long queue on roads.

Since improvements to the operation of Chennai Port and the utilization of Ennore Port are in progress, some developments to the situation are expected.

Issues due to the Road Structure/Operation

Although the ORR is partially open to public, there are problems of connection with the main radial roads. The junction at the connecting point with NH4 and NH45 is still under construction. Therefore, the ORR is not effectively utilized.

In Chennai, there are many sections where sidewalks and parking lots are not provided. In such sections, the risk of traffic accidents involving pedestrians is high, as parked vehicles occupy a lane, cause traffic jams, and increase travel time.

In addition, at many intersections of trunk roads, vehicles travelling on service roads cannot go straight or turn right, but must take a detour instead.

These road structure and operational problems lead to traffic congestion, increase in travel time, and fatal accidents. Therefore, it is required to improve the efficiency of traffic flow and pedestrian safety by reviewing the road structure and operations.

Deterioration of Pavement

There are sections where roads are depressed due to deterioration of pavement. Pavement deterioration lowers travel speed, making overtaking difficult. Especially in Chennai, where many industrial parks are located in suburbs, there is a large volume of heavy vehicles in the access roads, and depression of roads are also evident. Pavement deterioration also causes logistics problems such as damage in handling and transport of trucks and increase of logistics time. Therefore, it is necessary to improve road pavements to allow smooth flow of traffic.

3. TRAFFIC SURVEY, ANALYSIS, AND FORECAST

3.1 Traffic Survey

Objectives of the Project

The target of the traffic survey is the central urban area which is the introduction area for the traffic signal control system and the Chennai Peripheral Ring Road (CPRR). In the central urban area, traffic survey was carried out inside the Inner Ring Road (IRR) and the information technology (IT) corridor, in which the number of IT companies increased remarkably. In the CPRR, traffic survey was carried out at the starting point and cross section of each section.

Table 3.1.1 Outline of Traffic Survey

Survey	Objectives	Contents
Intersection Traffic Volume Survey	Indicators for measuring the effect of introducing intelligent transport system (ITS)	Inside IRR × 6 places
	Check traffic distribution	Around the IT corridor × 2 places
	Update the Origin-Destination (OD) table	CPRR × 8 places


Source: JICA Study Team

Results of the Traffic Survey

The outline and the summary of the results of the traffic volume survey are shown in the figure below. In the city, inbound traffic is high in the morning, and outbound traffic increases in the evening. On the other hand, traffic tends to increase in the suburbs from evening to midnight.

The pie chart shows the ratio by type of vehicle. Gray portions indicate the proportion of two-wheeled vehicles. There are many motorcycles in the center of the Chennai, such that two-wheeled vehicles account for 39% in SH49A. On the other hand, the proportion of large vehicles is relatively higher in the suburbs than in the city.

As such, the city road is used for commuting in the morning and evening, while the suburban road is used for large vehicles such as heavy trucks from evening to midnight.



Source: JICA Study Team

Figure 3.1.1 Outline of Traffic Volume Survey Results

3.2 Hearing Survey for Related Development Plans

Traffic Demand Forecast

In this survey, traffic demand forecast was reasonably carried out using network analysis of the “Data Collection Survey for Chennai Metropolitan Region Intelligent Transport System” in 2017. Specifically, the method and year of estimation of traffic demand forecast were set to be the same as that of the survey. The following points were also considered:

- Data update using the result of traffic volume survey.
- Future traffic demand considering the development plan along CPRR and port development plan.

Future Traffic Demand Forecast


The results of the future traffic demand forecast for short term, mid-term and long term are shown in the figure below.

In the short term, the traffic capacity of the access road to the Ennore Port is expected to increase due to the increase in the cargo volume brought about by the improvement of the processing capacity at the Ennore Port. In addition, it is expected that there will be no problem in increasing the traffic volume of the ORR and the CPRR (Section 4), but it is expected that congestion will occur in the section from the ORR to the Ennore Port.


In the mid-term, it is expected that the congestion in the section from the ORR to the Ennore Port will be alleviated by constructing the CPRR (Section 1).

In the long term, traffic congestion occurs in the city due to the increase in total traffic volume.


Short Term (2021) Sec. 4




Mid Term (2026) Sec. 1 + Sec. 4




Mid Term (2026) Sec. 2 + Sec. 4




Mid Term (2026) Sec. 3 + Sec. 4




Mid Term (2026) Sec. 4




Mid Term (2026) Sec. 5 + Sec. 4



Mid Term (2026) Full Line Service



Long Term (2036) Full Line Service



Source: JICA Study Team

Figure 3.2.1 Traffic Assignment Result

4. PRIORITIZATION AND FORMULATION OF THE PROJECT FOR JICA LOAN SCHEME

4.1 Approved Alignment and Sectioning of CPRR

According to the Detailed Project Report (DPR), the alignment for CPRR was approved by the Steering Committee and was finalized by the Principal Secretary of the Highways and Minor Ports Department (HMPD) on 9 July 2014. The CPRR starts at Ennore Port and ends at Poonjeri Junction (KM 56/800 of ECR) in Mahabalipuram. The alignment connects four national highways, namely NH5, NH205, NH4, and NH45, as well as eight state highways, namely SH51, SH50A, SH50, SH48, SH57, SH49B, SH49A (OMR), and SH49 (ECR). The length of the alignment is 133 km and is divided into five sections as follows:

- Sec. 1: Northern Port Access Road-Ennore Port to Thatchur on NH5, and CPRR (Ch.6+200) to Tiruvottiyur Ponneri Pancheti (TPP) Road via TPP Link Road (Connected point on TPP Road differs in original alignment and new alignment)
- Sec. 2: Thatchur on NH5 to the start of Thiruvallur Bypass
- Sec. 3: Start of Thiruvallur Bypass to Sriperumbudur on NH4
- Sec. 4: Sriperumbudur on NH4 to Singaperumalkoil on NH45
- Sec. 5: Singaperumalkoil on NH45 to Mahabalipuram

The outline of the sections is summarized in Table 4.1.1.

Table 4.1.1 Outline of Sections of CPRR

		Sec.1		Sec.2	Sec.3	Sec.4	Sec.5	TOTAL
		Main Road	TPP Link	Main Road	Main Road	Main Road	Main Road	
Section Length		21.51km	3.6km	25.61km	29.55km	24.85km	27.5km	132.62km
Scope of Work	New Construction	21.51km	3.6km (4.21km)	25.61km	19.95km	0km	25.5km	96.17km
	Improvement	0km	0km	0km	9.6km	24.85km	2km	36.45km
ROW		100m	45-60m	60m	60m	40-60m	60m	
Land Acquisition Area		255ha		188ha	208ha		163ha	814ha
Number of Lane	Main Line	2x2Lane	2x2Lane	2x3Lane	2x3Lane	2x3Lane	2x2Lane	
	Service Rd	2x2Lane	2x2Lane	2x2Lane	2x2Lane	2x2Lane	2x2Lane	
BP		Ch.0+000 /Ennore Port	TPP Link Ch.0+351 /CPRR (Ch.6+200)	Ch.21+506 /NH5 (29/000)	SH57 (50/500)	NH4 (42/100)	NH45 (47/400)	
EP		Ch.21+506 /NH5 (29/000)	TPP Link Ch.3+950 /TPP Rd	SH57 (50/500)	NH4 (42/100)	NH45 (47/400)	Ch.129+171 (Poonjeri)	
Structures	IC	0	0	1	2	0	1	4
	ROB	1	1	0	1	0	1	4
	MJB	1	0	2	1	0	1	5
	MNB	1	0	6	8	0	11	26
	VUP	6	0	5	6	9	6	32
	LVUP	6	0	4	2	4	7	23
	BC	39	0	0	1	0	7	47
	PC	8	0	204	107	0	132	451
	Entry/Exit Ramps	0	0	2	2	0	2	6

Source: Land Acquisition Area: STUP's Letter E/14518/149/NJW/GK/0132 dated 11 Aug 2017,

Chainage of BP/EP of each section: JICA Study Team estimates, Other Items: DPR Main Report, From P7-2 To P7-5

Note: 1) CPRR: Chennai Peripheral Ring Road, IC: Interchange, ROB: Railway Over Bridge, MJB: Major Bridge, MNB: Minor Bridge, VUP: Vehicular Underpass, LVUP: Light Vehicular Underpass, BC: Box Culvert, PC: Pipe Culvert

2) BC and PC are planned for irrigation and utility crossings.


3) MJB: Sec.1: Buckingham Canal, Sec.3: Kannigaipper Tank, Kosathalai River, Sec.4: Coovam River, Sec.5: Sengundram Tank

4) The alignment of TPP Link was modified and the section length was changed from 4.21km to 3.6km.

With respect to the TPP Link Road, HMPD conducted a survey on alternate alignments in May to June 2018, as the inhabitant's opposition were encountered on the original alignment. In early July, the state government decided that the new alignment would start from the TPP road around Minjur to the Northern Port Access Road (NPAR) (as a main line of Section 1), having a length of 3.6 km, Also, the new alignment connects to the Outer Ring Road (ORR) near Minjur.

4.2 ITS Components

Figure 4.2.1 shows the overall Intelligent Transport System (ITS) components which are candidates for the Japanese ODA Loan Project. As described in 1.1 in this report, the ITS for CPRR was considered separately from the City ITS. The system linkage with the City ITS, as shown in Figure 4.2.1, will be established after introducing the ITS for CPRR.



Source: JICA Study Team

Figure 4.2.1 Overall ITS Components for Japanese ODA Loan Project

Regarding the Touch & Go System, the Japan International Cooperation Agency (JICA) Study Team recommended to adopt the common mobility card which can be used for other transport modes, e.g., Chennai Metro Rail, city buses, etc. In case the common mobility card does not exist yet in Chennai, the Touch & Go System should be introduced after the framework of the common mobility card is established in Chennai.

4.3 Prioritization of CPRR Components

In this Study, the prioritization is made by setting out the evaluation criteria shown in Table 4.3.1.

As a result, it is recommended that the 1st priority be given to Section 1, the 2nd priority to Sections 2 and 3, and the 3rd priority to Section 5 considering that Sections 2 and 3 shall be developed simultaneously since they will form a united road section from the viewpoint of completeness of the CPRR.

Table 4.3.1 Evaluation Criteria for Prioritization

Criteria	Indicator	Evaluation (Score)			
		High	Middle	Low	
1	Effect on Improvement of Traffic Situation	Traffic Volume (pcu/day)	10: 100,001- 9: 75,001-10,000 8: 50,001-75,000	7: 40,001-50,000 6: 30,001-40,000 5: 20,001-30,000 4: 10,001-20,000	3: 7,501-10,000 2: 5,001-7,500 1: 2,501-5,000 0: -2,500
		Reduction in Total Travel Time (vehicle hour)	10: 100,001- 9: 75,001-10,000 8: 50,001-75,000	7: 40,001-50,000 6: 30,001-40,000 5: 20,001-30,000 4: 10,001-20,000	3: 7,501-10,000 2: 5,001-7,500 1: 2,501-5,000 0: -2,500
		Large Vehicle Rate (%)	10: 41- 9: 36-40 8: 31-35	7: 26-30 6: 21-25 5: 16-20 4: 10-15	3: 8.0-9.9 2: 6.0-7.9 1: 4.0-5.9 0: -3.9
2	Magnitude of Environmental and Social Impact	Impact on Reserved Forest and Coastal Regulation Zone	5: RF: - 5: CRZ: -	2: RF: 0-4ha 2: CRZ: III	0: RF: 5ha- 0: CRZ: I, II
		Area of Land to be Acquired (ha)	10: -50 9: 51-100 8: 101-150	7: 151-200 6: 201-250 5: 251-350 4: 351-400	3: 401-600 2: 601-800 1: 801-1,000 0: 1,001-
3	Economic Rationality	EIRR (%)	10: 28.0- 9: 24.0-27.9 8: 21.0-23.9	7: 18.0-20.9 6: 15.0-17.9 5: 12.0-14.9 4: 9.0-11.9	3: 8.0-8.9 2: 7.0-7.9 1: 6.0-6.9 0: -5.9

Source: JICA Study Team

Table 4.3.2 Evaluation Results for Prioritization

Criteria	Indicator	Sec.1	Sec.2	Sec.3	Sec.5	
1	Effect on Improvement of Traffic Situation	Traffic Volume (pcu/day)	58,324	31,184	89,528	43,282
		SCORE	8	6	9	7
		Reduction in Total Travel Time (vehicle hour)	54,871	45,192	67,494	26,239
2	Magnitude of Environmental and Social Impact	Large Vehicle Rate (%)	76	13	25	27
		SCORE	10	4	6	7
		Impact on Reserved Forest and Coastal Regulation Zone	RF: - CRZ: Cat..III	RF: - CRZ: -	RF: 0.28 CRZ: -	RF: 9.95 CRZ: -
3	Economic Rationality	Area of Land to be Acquired (ha)	255	188	208	163
		SCORE	5	7	6	7
		EIRR (%)	18.1	19.7	20.2	12.8
TOTAL SCORE		45	41	43	36	
PRIORITY		1	3	2	4	

Source: Land Acquisition Area: STUP's Letter E/14518/149/NJW/GK/0132 dated 11 Aug 2017,
Project Cost: Construction Cost shown in DPR Main Report, P9-3

1st 2nd 3rd

During the consultation with inhabitants around the site of the TPP Link Road (Original Alignment), it was found that it is very important to obtain social consensus for the road construction. As an alternative solution to minimize the social impact, the south end of the TPP Link Road is to be shifted approximately 1.5 km west of the original alignment. This new alternative alignment has a total length of 3.6 km from the connecting point with Northern Port Access Road to the southern end. The length of 1.65 km in the northern part is the same as the original alignment, and the remaining 1.95 km in the southern part is different from the original alignment.

4.4 Consulting Services for the Prioritized Project

4.4.1 CPRR

Mode of Contract Scheme

A model of the Engineering, Procurement, and Construction (EPC) contract mode has been published by the Planning Commission for highway projects in India based on past experiences in infrastructure development, where the conventional item-rate contract is said to be generally prone to time and cost overruns. This is particularly evident in the national highway sector, resulting in enhanced cost to the financing institutions, and also considerable delay in the completion of projects.

Most of the EPC contracts in India, except for the projects financed by the multilateral development banks World Bank and Asian Development Bank awarded since 2014, seem to have been affected by Local Competitive Bidding (LCB) in accordance with the procedures used in India. EPC has also been introduced in state highway projects, and applications of the EPC for CPRR is one of options according to HMPD.

Tender Method of Consultant Procurement

A supervising consultant selected by the executing agency through International Competitive Bidding (ICB) will discharge the functions and duties of an Authority's Engineer (AE) as per the Terms and Conditions of the EPC Agreement.

With the intention of maintaining high quality in the works executed by the contractor, the JICA Study Team recommends applying 'Procurement of Works' of the 'JICA Standard Bidding Documents Under Japanese ODA Loans (Works)' which follows the general conditions of the Federation International des Ingenieurs-Conseils (FIDIC MDB) Harmonized Edition. Detailed design is also recommended to supplement further design related information from the DPR to be used for bidding by the JICA SBD.

4.4.2 CPRR ITS

Mode of Contract Scheme

The 'Design Build' scheme, i.e., design, supply, and installation, wherein the employer prescribes the requirement of the systems and performance and the contractor carries out the detailed design, is best suited because ITS is a project which is mainly composed of systems and equipment.

The 'Design Build' scheme was also adopted to other public projects of ITS in India. Some major examples are the MITRA Project of the City Bus Monitoring and Passenger Information System in Mysore in Karnataka State (World Bank), the KSRTC Project of the Inter-City Bus Monitoring and Passenger Information System in Karnataka State (state budget), and the B-TRAC Project of the Traffic Management System of Bengaluru traffic police in Karnataka State (state budget).

The 'Procurement of Electrical and Mechanical Plant, and for Building and Engineering Works, Designed by the Contractor' from the 'JICA Standard Bidding Documents Under Japanese ODA Loans (SBD)' which is based on FIDIC is recommended to be used for this Japanese ODA Loan Project. This SBD has been used in the ITS project under the Japanese ODA Loan Project in other city in India.

Tender Method of Consultant Procurement

It is very important that the requirements are clearly defined/prescribed so that bidders can properly reflect the requirement on their proposals, particularly because the ITS project utilizes advanced technology. This is a different method from 'Turn Key Project' or EPC, where the contractor takes almost the entire responsibility regarding the design and construction. In particular, the Indian local contractors do not have sufficient experience on ITS projects yet. As such, ensuring the quality throughout the project, particularly the upper stage (basic design and contractor procurement), is very important because the quality of the upper

stage will affect the entire project including the stages of implementation, operation, and maintenance. Therefore, procuring the Consultant through ICB, including the stages of basic design and contractor procurement, is recommended.

(3) Selection Method of Contractor Procurement: Quality and Cost Based Selection (QCBS)

ITS facilities such as an emergency call box, traffic counter, CCTV, weather monitoring facility, VMS, and center system are all obligated to be installed on national highways under the jurisdiction of NHAI, where a certain level of traffic volume is expected (i.e., more than 40,000 daily traffic volume). However, there is currently no road where these facilities have been installed correctly, and no information is actually provided. As for the City ITS in India, Ahmadabad in Gujarat State is the only city where the dynamic traffic information has been provided in real time by an installed traffic information system. The system was introduced by a Japanese company under a support scheme of the Japanese small and medium enterprise overseas business developments by JICA.

It is considered that the above situation of ITS in India is caused by the fact that the contractors who have sufficient technical capabilities for developing and handling the advanced system are not selected, and the selection method of the contractor procurement is considered one of the predominant factors behind this. ITS consists of several subsystems wherein technical aspects are vitally important, such as software processing methods, interface between subsystems or external systems, and integration of systems. Therefore, selecting a contractor with enough technical capabilities determines the success of a project. To properly evaluate the technical capabilities of bidders and to select an appropriate contractor, adopting QCBS as an evaluation point of technical evaluation as reflected in addition to the financial evaluation is strongly recommended.

5. HIGHWAY OPERATION AND MAINTENANCE (O&M) STRUCTURE

5.1 Recommendations on the O&M Plan

Proposal on O&M Contracting

The Highways and Minor Ports Department (HMPD) of the Government of Tamil Nadu will oversee the construction and O&M of the CPRR. Most probably, the Project Wing of the Highways Department will take charge of the construction of CPRR, and the Construction and Maintenance Wing will take charge of the O&M.

During the meeting held in February 2018 between HMPD and JICA, HMPD agreed in principle to apply the Standard Bidding Documents (SBD) issued by JICA for the contract for Section 1, although HMPD and JICA are discussing which particular SBD is to be applied in the project. The JICA mission stated that the SBD for "Procurement of Works" is generally mandatory in similar types of Japanese ODA Loan Projects.

When the construction of CPRR is completed, the supervision of O&M will be shifted from the Project Wing to the Construction and Maintenance Wing.

After the completion of construction, most probably a PBMC will be used for the O&M works. Currently, the Highways Department has been switching one-by-one to PBMC from the conventional single-year maintenance contract. It is being introduced successively to one of the highway divisions in eight circles in the state, and up to date, four highway divisions are using PBMC, namely Pollachi, Krishnagiri, Ramanathapuram, and Thiruvallur. Now the PBMC scheme will be extended to the Virudhunagar Highways Division in the current financial year.

Section 1, Section 2, and a part of Section 3 of CPRR fall under the jurisdiction of the Thiruvallur Highways Division, where PBMC was introduced on 24 February 2016. The O&M of SHs and MDRs with a total length of 498 km is being carried out with the contract worth INR 630.38 crore.

PBMC includes ordinary maintenance, initial rectification works, minor improvement works, periodic maintenance works, and emergency works. The amount as stated in a contract is a provisional estimate excluding emergency works. Ordinary maintenance will be payable as a proportionate monthly lumpsum over the 60-month period of the contract. Other works will be measured and paid based on the actual work output.

Cost Estimate of O&M

1) O&M Structure

Regarding the O&M for Section 1 of CPRR, it is assumed that the execution entity TNRDC will be in charge. The maintenance work will be contracted out to private companies.

Section 2 and a part of Section 3 of the CPRR will fall under the jurisdiction of the Thiruvallur Highways Division. Regarding the remaining sections, Section 3, Section 4, and Section 5 will fall under the jurisdiction of the neighboring Chengalpattu Highways Division. The Thiruvallur Highways Division has been contracting out to private O&M contractors with PBMC and will incorporate newly completed sections into the contract. It is assumed that the PBMC will be introduced to the Chengalpattu Highways Division by the time the CPRR is completed. If the introduction is delayed, a single-year maintenance contract will be used.

The structure of the Thiruvallur Highways Division consists of one divisional engineer, six assistant divisional engineers, and eight assistant engineers. The Thiruvallur Highways Division will outsource the work of maintenance/patrol/traffic control with PBMC to an O&M contractor. There is a plan to collect toll for Section 1. When this is carried out, toll collection work will also be outsourced to a toll contractor. There is one field office for the divisional engineer and six field offices for the assistant divisional engineers taking charge of road construction other than large-scale projects and maintenance for SHs and MDRs

2) Cost Estimate of O&M

Table 5.1.1 shows the examples of O&M costs for the four highways divisions that have already introduced the PBMC and the CORR. Although the cost of CORR is about 30% higher than those of other roads, it is assumed that the higher cost comes from the road composition of CORR, which contains service roads on both sides. The road composition of CPRR is like that of CORR and INR 0.223 crore/year/km is adopted for the calculation of the O&M cost.

Table 5.1.1 Examples of O&M Costs (INR in Crore)

No.	Highways Division	Length (km)	5-year Cost	5-year/km	1-year/km
1	Pollachi	377	233.9	0.620	0.124
2	Krishnagiri	581	450.0	0.775	0.155
3	Ramanathapuram	569	460.0	0.808	0.161
4	Thiruvallur	776	630.4	0.812	0.162
5	CORR	30	33.0	1.113	0.223

Source: JICA Study Team

By using the unit rate of INR 0.223 crore/year, the 133.23-km CPRR will produce an annual O&M cost of INR 29.71 crore.

This part is intentionally left blank

Proposal on Improvement in O&M Manual

Regarding O&M of CPRR, an O&M manual, which will be a guideline for the work, should be prepared. The IRC: SP: 95-2011¹ will be the basis for the preparation. The road maintenance standards stipulated in this document is also the basis for Schedule-K in the model contract agreement for PPP and Schedule-E in the standard agreement for EPC.

Although the O&M manual for CORR covers all aspects of O&M activities, there are some points that need to be improved. Especially for the methodology in preventive maintenance, the description is no more

¹ IRC: SP: 95-2011 Model Contract Document for Maintenance of Highways

than a concept. As for preventive maintenance standards, the Guidelines for Expressways² compiled by MORTH stipulates a detailed methodology. The O&M manual can be improved by incorporating this part. The JICA Study Team proposes that the detailed methodology in preventive maintenance should be incorporated to improve the O&M manual.

Proposal on O&M of ITS

The total length of CPRR is 133.23 km (including the original alignment of TPP Link Road), and it is divided into five sections. Section 1, or the Northern Port Access Road (NPAR), is connected to the Ennore Port. Although it has not been decided yet, the Government of Tamil Nadu is considering to make Section 1 an access-controlled toll road. Therefore, it is recommended that a toll management system (for Section 1) and a highway traffic management system (for all sections) be introduced as ITS components for the CPRR.

Proposal on Training in Japan for Technical Enhancement in O&M

It is very valuable for the staff of the Highways Department of Tamil Nadu State, who are in charge of the CPRR, to learn this example as precedent of the Metropolitan Inter-City Expressway. The JICA Study Team proposes a training in Japan for technical enhancement in O&M, where attendees can acquire wide-ranging practical knowledge including O&M structures, actual examples of O&M manuals, responses to various traffic incidents at site, information dissemination at traffic control centers, structure and management of toll collection, emergency response to disasters/accidents, and ways to enhance road functions among others.

6. DESIGN REVIEW OF CHENNAI PERIPHERAL RING ROAD (CPRR)

6.1 Objectives and Scope of Design Review of CPRR

In order to confirm the reasonability of providing the Japan International Coordination Agency (JICA) Loan to the CPRR Project, the review is undertaken on the design made in the Detailed Project Report (DPR).

Table 6.1.1 shows the volumes of DPRs with the version provided to the JICA Study Team.

Table 6.1.1 Volumes of DPR for Review

Vol.	Report Title	Version/Date	Availability
I	Main Report	Unknown	Provided by JICA
II-A	Design Report (Highways)	Ver.R0, 9 Jan. 2017	Aug. 2017
II-B	Design Report (Structures/Box Culvert)	Unknown (Cover shows Aug. 2016)	Feb. 2018
II-C	Design Report (Structures/Minor Bridge)	Unknown (Cover shows Aug. 2016)	Feb. 2018
II-D	Design Report (Structures/Major Bridge)	Unknown (Cover shows Aug. 2016)	Feb. 2018
II-E	Design Report (Structures/Underpass)	Unknown (Cover shows July. 2016)	Feb. 2018
II-F	Design Report (Structures/Interchange)	Unknown (Cover shows Nov. 2016)	Feb. 2018
II-G	Design Report (Structures/Sec-1 Link Road)	Unknown (Cover shows Sep. 2016)	Feb. 2018
II-H	Design Report (Structures/ROB)	Unknown (Cover shows Aug. 2016)	Feb. 2018
III	EIA & Management Plan	Unknown	Provided by JICA
IV	Social Impact Assessment & RAP	Unknown	Provided by JICA
V	Technical Specifications	-	Not Available
VI	Rate Analysis	Ver.R0, 9 Jan. 2017	Feb. 2018
VII	Bill of Quantities	Ver.R0, 9 Jan. 2017	Nov. 2017
VIII	Cost Estimate	Ver.R0, 9 Jan. 2017	Aug. 2017
IX-A	Drawing (Highways)	Unknown	Aug. 2017
IX-B	Drawing (Structures/ Drainage)	Unknown	Aug. 2017
IX-C	Drawing (Structures/Bridges)	Unknown	Aug. 2017
IX-D	Drawing (Structures/underpass)	Unknown	Aug. 2017
IX-E	Drawing (Structures/Interchange)	Unknown	Aug. 2017

Note: Shaded text is a report not provided at the time of review.

Source: DPR Main Report P1-6 and JICA Study Team

The scope of the design review is set out as shown in Table 6.1.2 considering the objectives of the design

² MORTH. 2010. Guidelines for Expressways. New Delhi. IRC

review and the provided volumes of DPR at the time of review.

Table 6.1.2 Scope of Design Review

Item	Description in Provided DPR	Scope of Design Review
Traffic Analysis	The traffic survey was carried out in 2013. Future traffic volumes of CPRR (Sec. 2-5) were estimated by the elasticity method stipulated in the Indian Road Congress (IRC).	The traffic survey is carried out in 2017. Future traffic volumes of CPRR (Sec. 1-5) are to be estimated by network analysis using the JICA STRADA software.
Natural Conditions Survey	Topographic Survey: Control point survey using GPS, planimetric survey, and route survey (centerline, profile, and cross section) using a total station were carried out. Details of survey methodology and results including calculations are not provided. Geotechnical Investigation: CBR tests for subgrade and boring survey at proposed sites for structures were carried out. Results of the boring survey, including N values, are not presented in the provided DPRs. Hydrological Survey: No specific surveys were carried out. Standard values recommended in IRC were applied to the rainfall intensity in drainage design.	Survey results are not clearly presented in the provided DPRs; thus, natural conditions survey is not to be reviewed. Contents of surveys to be made in the next design phase of the Project are to be suggested in this Study.
Design		
Design Conditions	Design conditions such as road classification, technical standards to be applied, design speed and design criteria are presented in the design approach of the DPR report.	Validity of descriptions and consistency within DPR reports are to be reviewed.
Highway Design	Alignment: Elements and applied values can be read in the drawings (plan and profile). Pavement: Adopted design traffic volume and design CBR as well as design calculations are presented in the DPR report. Drainage: Approach to drainage facilities arrangement as well as typical drainage calculations are illustrated in the DPR report.	Alignment: The alignment is to be reviewed based on the applied technical standards Pavement: Design results are to be evaluated by comparing with the results of AASHTO and other standards. Drainage: Design approach and design calculations are to be reviewed.
Interchange Design	Design reports of DPR (structures/interchanges) were not provided. In the provided reports, applied design criteria and general drawings are available.	The number of lanes for the main road and service road are to be evaluated based on the directional traffic movements that are estimated in this Study. Furthermore, geometric design of interchanges is to be reviewed.
Structure Design	Design reports of DPR (structures/bridges) were not provided. Drawings of structures (General Arrangement Drawings (GADs)) were provided. N values are not presented in boring logs.	Structural design is to be reviewed based on GAD. Foundations including piles could not be reviewed.
ITS Design	Interim results of the Chennai ITS Study are presented in DPR. No original proposals are included.	Updating ITS Design is to be made.
Cost Estimate	Rate analysis was not provided. Design quantities are shown in summarized manner and calculations for quantity take-off are not presented in the DPR report.	Unit rates are to be updated for the year 2017-2018 based on the schedule of rates of Tamil Nadu District. Design quantities are to be preliminarily reviewed for the major items.

Source: JICA Study Team

6.2 Road Classification and Design Standards to be Applied

Design Standards

The road design made in the DPR was conducted in accordance with IRC standards.

Design Speed

The DPR Design Report (Vol. II, Design Report-Highways) explains that design speeds of 100 km/h (ruling) and 80 km/h (minimum) are adopted in accordance with IRC:73-1980 Geometric Design Standards for Rural Highways as shown in Table 6.2.1. Since the minimum radius of horizontal curves applied to Section 4 is R=200 m, it is desirable to improve those curves in the future to ensure the consistency of the minimum design speed of 80 km/h throughout the route.

Table 6.2.1 Design Speed

Terrain Category	Slope of Ground (%)	Design Speed (km/h)	
		Ruling	Minimum
Plain and Rolling	-25	100	80
Mountainous and Steep	25-	60	40

Source: IRC:73-1980 Geometric Design Standards for Rural Highways

Design Criteria

Table 6.2.2 shows the design criteria that is clarified in the DPR Design Report (Vol. II, Design Report-Highways).

Table 6.2.2 Design Criteria

Road Category: SH Terrain: Mostly Plain, Partially Rolling		Ruling / Desirable	Minimum
Design Speed		100 km/h	80 km/h
Cross Section	Right of Way (ROW)	100 m: Section 1 of CPRR, TPP Link Road (Original Alignment) 100 m: North half of TPP Link Road (New Alignment) 45-60 m: South half of TPP Link Road (New Alignment) 60 m: Sections 2 to 5	
	Carriageway	3.5 m Widening 0.9 m (R: 75 m-100 m) 0.6 m (R: 101 m-300 m)	
	Median	5.0 m (0.5 m+4.0 m+0.5 m) (Sec. 1, 2, 3, 5) 1.5 m (0.25 m+1.0 m+0.25 m) (Sec. 4)	
	Shoulder	Paved Shoulder 1.5 m + Earthen Shoulder 2.0 m (Section 1) Paved Shoulder 1.5 m (Sections to 5)	
	Sidewalk	3.0 m (Sections 2, 3, 5) 2.5 m (Section 4) 2.0 m (Section 1)	
Crossfall		2.5% (Earthen Shoulder 3.0%)	
Embankment Slope		2H:1V (H: -3 m) 1.5H:1V Stone Pitching (H: 3 m)	
Maximum Super-elevation		7.0% (R: -400 m) 5.0% (R: 400 m)	
Minimum Horizontal Curve Radius		400 m	250 m
Stop Sight Distance		360 m (V: 100 km/h) 260 m (V: 80 km/h)	180 m (V: 100 km/h) 130 m (V: 80 km/h)
Maximum Gradient		2.5%	3.3%
Clearance	Horizontal	Road Width	
	Vertical	5.5 m (Vehicle Underpass) 4.5 m (Light Vehicle Underpass)	

Source: DPR Vol.II, Design Report-Highways

6.2.1 Number of Lanes

Although there is no clear clarification on the required number of lanes in the DPR, future traffic volumes of Sections 2 to 5 are presented with the limitation of Level of Service (LOS) B. According to this information, in 2028, after 10 years from 2018 as of this report, Section 2 needs 8 lanes, Sections 3 and 4 need more than 12 lanes, and Section 5 needs 6 lanes to ensure LOS B. Although the opening year that was


assumed in the DPR is not clear, there is a concern that traffic of CPRR will be unstable soon after opening, considering the numbers of lanes that were proposed in the DPR (Section 1: 4-lane, Sections 2 to 4: 6-lane, Section 5: 4-lane).

On the other hand, the LOS estimated based on future traffic volumes forecasted in this Study and the numbers of lanes proposed in the DPR (Section 1: 4-lane, Sections 2 to 4: 6-lane, Section 5: 4-lane). It is assumed that the remaining works of Section 4 will be completed in 2021, and construction of Sections 1, 2, 3, and 5 will be completed and the entire stretch will open in 2024. In 2028, after 10 years from 2018 as of this report, the LOS ranges from B to D, which is considered reasonable.

6.2.2 Typical Cross Sections


Typical cross sections proposed in the DPR were designed in accordance with the number of lanes stated above and the requirements of the applied design standards. They are shown in Figure 6.2.1 to Figure 6.2.2.

TYPICAL CROSS SECTION (1-1) :DPR Drawing:Typical Cross Section




Source: JICA Study Team based on DPR

Figure 6.2.1 Typical Cross Sections (Section 1)



Flyover Section (ROW 45 m)



Approach Section (ROW 60 m)

Source: STUP

Figure 6.2.2 Typical Cross Sections TPP Link Road (New Alignment)

6.3 Design Update (Section 1)

As described earlier in this report, some missing parts of the DPR such as “Design Report (Structures)”, “Drawings”, and “Rate Analysis” were provided after the review period. Major changes in the newly provided materials are: design update by HMPD, modifications for the JICA Study Team comments at IT/R2, agreement issues in the JICA mission held in February and April 2018, and other updates. However, further modification and updating of the DPR are still ongoing by HMPD even at the time of the DFR, and this situation results in inconsistencies among the series of provided materials, such as report, drawing, and quantities.

In this section, the result of the review of the provided materials and suggestions to be considered in the further detailed design stage are described.


6.3.1 Main Renewed Points

Bridge Extension Near the Beginning Point (MJB101)

The end chainage of MJB101 was originally Ch.1+200 but it will be revised to approx. Ch.2+500 as per TNRDC meeting held on April 24, 2018. The JICA Study Team considered the extension but could not be reviewed since there is no detailed plan yet. Therefore, a thorough design review of the extension must be carried out during the detailed design.

The following are considered in the cost estimate of the JICA Study Team:

- Extension of MJB end chainage to Ch. 2+500 from Ch. 1+200
- The bridge type is initially set as a 30 m span PC box girder according to the DPR
- One bridge and four box culverts are removed from this section: MNB101, BC2/1~BC2/3 and BC3/1



Source: JICA Study Team

Figure 6.3.1 MJB101 Extension Plan

Changing of IC-1 (NH5) to Section 1

When the review of the DPR was executed for the whole section, IC-1 was included in Section 2. However, when the meeting with HMPD was held in February 2018, it was decided that IC-1 will be included in Section 1. Therefore, the end point of Section 1 became the edge of the retaining wall (Ch.21+506) which is connected to the interchange bridge (this position was confirmed at the TNRDC meeting on April 24, 2018). For this reason, the access to Section 2 becomes unnecessary. The study of traffic operation and the stage construction for connection with Section 1 and NH5 are required.

Installation of Toll Barrier

Partial access control of toll road was studied in which it is possible to access the service road from the entry and exit to the service road except in interchange considering the type of interchange (clover leaf is unfavorable to install toll gate) and the connection with the service road. Therefore, open system was adopted, and some toll barriers were planned in order to reduce the inequality of the toll rate. Toll barrier was planned at the location with high visibility of the toll gate at the grand horizontal and vertical alignment, avoiding the structure section, and also away from at-grade intersection. Locations of toll barriers were at Ch.15+800 and Ch.2+200 on CPRR, and at Ch.1+200 on TPP Link Road. Moreover, the toll booth and the toll office were planned within the right of way (ROW 100 m) in consideration of the installation of ETC lane and the width of the island. As a result, the service road was shifted outside at the toll barrier section. The width and the length of the island conformed to the Indian expressway design standard (IRC-SP99-2013).


Installation of Traffic Control Center

Traffic control center (TCC) was planned in the earthwork section within Section 1 in consideration of road alignment and land area which is for office building and parking area. The location of TCC was planned at Ch.8+600 on CPRR. Acceleration lane and deceleration lane were planned in consideration of traffic safety because there are exits and entrances at the connection between the main road and TCC.

Alignment Change of TPP Link Road

The road stretch of Section 1 consists of Northern Port Access Road (NPAR) and TPP Link Road. During consultation with inhabitants around the site of TPP Link Road (original alignment), it was found that it is important to obtain social consensus for the road construction. As an alternative solution to minimize the social impact, the south end of TPP Link Road is to be shifted approximately 1.5 km west from the original alignment. This new alternative alignment has a total length of 3.6 km from the connecting point with NPAR to the southern end. The length of 1.65 km in the northern part is the same as the original alignment, and the remaining 1.95 km in the southern part is different from the original alignment.

At the southern end of TPP Link Road (new alignment), it is planned to cross overhead of the TPP Link Road near Minjur and connect directly to the ORR. In the TPP Link Road (new alignment), the section subject to ODA loan will be a stretch from Ch.0+350 (the north end) up to Ch.3 + 950, and the south is to be constructed under the ORR development project.



Source: JICA Study Team

Figure 6.3.2 Alignment Change Plan of TPP Link Road

6.3.2 Design Quantity

Since design quantities are presented in a summarized manner and detailed quantities of each structure are not available in the DPR reports, preliminary check on major items was conducted in this Study. As a result, no fatal errors were found in the design quantities of major items. Therefore, in the cost estimate in this Study, design quantities presented in the DPR are to be utilized while unit prices are to be updated.

6.3.3 Recommendation on Detailed Design of Section 1

Based on the review results above, suggestions to be noted at the detailed design stage of Section 1 are as follows. In general, further examination is recommended on the contents of the DPR which were provided after conducting the review of the JICA Study Team.


Suggestion on Road Design

1) Road Alignment

Vertical alignment was corrected by the JICA Study Team because some vertical curve length of the main road (CPRR) did not satisfy the design standard (IRC73-1980).

2) Connection of Main Road and Service Road

The connection between acceleration and deceleration lane of main road and service road with small radius curve was changed to rampway type by the JICA Study Team. Therefore, traffic safety will improve because vehicles can wait on the rampway. Moreover, it is necessary to add traffic signs in the detailed design because the visibility of connecting point becomes worse with the small intersecting angle, although the safety will increase by changing to a one-way road. Layout of entry and exit is shown in Figure 6.3.3 below.



Source: DPR


Figure 6.3.3 Layout Plan of Entrance and Exit

3) Improvement on IC-1 (NH5)

The service road was changed to one-way traffic according to the JICA Study Team. The box culverts were installed under the main road and H5 in order to connect each service road within the interchange area.

As a result of this, the connectivity was improved, but it became difficult to guide to destination.

The left-turning traffic from CPRR main road to NH5 passes through the service road (it is not direct connection ramp). Therefore, increase of travel time and decrease of traffic safety are expected because of the increase of future traffic volume. Refer to the plan of IC-1.




Source: JICA Study Team

Figure 6.3.4 Plan of IC-1

4) Improvement on JCT-1 (Beginning Point)

In the Interim Report, north-south direction traffic at the beginning point was suggested to pass on the ground instead of the flyover (frontage road is provided for north-south direction). However, afterwards, the direction of the alignment of the north side was changed from the north direction to the east direction. Therefore, it became dangerous because the small radius curve continues after the straight and steep alignment at the north side of the beginning point. Consequently, it is necessary to improve safety by enlarging the radius of curve and installing traffic sign in the detailed design. Plan of JCT-1 is shown in Figure 6.3.5.




Source: JICA Study Team

Figure 6.3.5 Plan of JCT-1

5) Improvement on JCT-2 (Connect with TPP Link Road)


It is recommended again to add the left turn only lane in order to increase traffic safety and the traffic capacity of the left turn traffic from the main road to TPP Link Road. Plan of JCT-2 is shown in Figure 6.3.6.

It is proposed as an alternative to change the intersection angle from 60 degrees to 90 degrees between the main road and the TPP Link Road. It can increase the capacity by reducing the intersection area and increase the safety by improving the visibility. Alternative plan of JCT-2 is shown in Figure 6.3.7.



Source: JICA Study Team

Figure 6.3.6 Plan of JCT-2



Source: JICA Study Team

Figure 6.3.7 Traffic Control Center on CPRR Ch.8+600

Suggestion on Structure Design

6) Inclusion of the Railway Plan (MJB101)

HMPD states that MJB101 is planned to be connected by railroad in the north and south. Details of MJB101 railroad plan such as clearances, determination of bridge type based on construction limits, span arrangement and others must be reflected in the detailed design.

7) River Conditions (MJB, MNB)

Although the cross section and water level (FWL) are shown in the final DPR (drawing), it could not be verified on site. Verification of the cross section and water level by means of tests must be done prior to the detailed design. The water level during construction must be checked as well.

8) Abutment Type (MJB101, 202, 301)


The structure of some river bridge abutments is not found to be a common abutment structure but a combined structure of reinforced earth wall and pier.

Although HMPD stated that these structures are not affected by the water current, it would be better to adopt the abutment structure and hydraulic force countermeasures because the common reinforced earth wall is weak against hydraulic force. During the detailed design, it is necessary to review and study the abutment structures upon conducting hydrologic surveys and upon checking the water level.

Table 6.3.1 Suggestion on the Abutment Type (MJB101)

Sec.	No.	STRUCTURE CODE	Location	Revision Suggestion		
				Plan of DPR	Affected by running water	Suggestion
Sec.1	1	MJB101-1 Str.No.1/1	A1(Start point)	Pier + RE Wall	No (land)	→ No change
			A3 End point	Pier + RE Wall	Yes	→ Change from pier to Abutment
		MJB101-2 Str.No.1/1	A2(End point)	Pier + RE Wall	No (land)	→ No change

Source: JICA Study Team



Source: JICA Study Team based on DPR (Drawing)


Figure 6.3.8 Abutment of MJB101

9) Reduction of Substructures on River (MJB, MNB)

The bridge plan in the final DPR is based on the minimum span of concrete bridges excluding ROBs. Although the ease of superstructure construction could be the major consideration in the plan, constructability becomes inferior by placing several piers due to the increase of path obstruction rate and cost of temporary construction equipment particularly in MNBs on narrow rivers. The current plan is considered economical by HMPD as opposed to the opinion of the JICA Study Team. This is an important matter that must be reviewed in the detailed design.

10) Type of Pavement (All Bridges)

In the final DPR, the planned bridge pavement material is concrete. However, asphalt pavement is used in the vicinity of earthworks section as well as ORR, while concrete asphalt is used in the already constructed bridge at the end of Section 4. Although material procurement could be the main consideration, others such as consistency must also be considered in the determination of pavement material during the detailed design.



Source: JICA Study Team based on DPR (Drawing)

Source: JICA Study Team

Figure 6.3.9 Cross Section of MJB101 and Constructed Bridge in Section 4 (Concrete Pavement)

11) Consultation with the Railway Company (ROB)

The ROB's design condition, construction limits, and bridge plan must be confirmed during the consultation with the railway company. Since there is no record of consultation in the DFR, the railway company must be consulted to confirm details such as the sequence and the bridge plan and to obtain approval.

12) Further Investigation About Superstructure and Substructure Type (VUP)

In the final DPR, the adopted structure is a reinforced concrete girder with minimum span while in ORR, a simply supported box girder bridge is adopted. The type of structure must be finalized in the detailed design considering economy and constructability. In addition, by adopting a box girder bridge, expansion joint and bearing may be omitted resulting to ease of maintenance.




Source: JICA Study Team

Figure 6.3.10 VUP in the Outer Ring Road (Box, Block Wall)

13) Slab Cantilever Length (IC/NH5)

The deck cantilever is about 4.5 m. Although this design is valid in HMPD, it is preferable not to set the length to maximum considering deterioration and unexpected loadings. Adjustment of edge curvature or box girder width in order to attain the preferable length is advised.




Source: JICA Study Team based on DPR Drawing (14518/E/IC/NH5/DD001: SH-2 OF 3)

Figure 6.3.11 Proposed Cantilever Length of Slab

14) Number of Face of Reinforced Earth Walls (IC)

Reinforced earth walls are placed between each gap of the upper and lower lanes of IC. The total number of faces is four. The said gap is about 3 m high if it is filled with soil. There will be two installation faces of reinforced earth wall which in turn will be economical. For bridges other than IC, there are two faces, but this should be reviewed in the detailed design.




Source: JICA Study Team based on DPR Drawing (14518/E/IC/NH5/DD001: SH-2 OF 3)

Figure 6.3.12 Cross Section of Reinforced Earth Wall (IC)

15) Bearing Position and Width of Substructure (All Bridges)

The bearings are located under the end cross beams and as compared with the superstructure width, the coping width of some substructures is found to be extremely small. It is advised that the bearing position and the coping width be reviewed in order to be certain of the vertical support load and to ensure bridge fall prevention in case unexpected forces occur.



Source: JICA Study Team based on DPR Drawing

Figure 6.3.13 Proposed Bearing Position (MJB101)

Suggestion on Possible Adoption Measures Against Climate Change

16) Influence of Climate Change on Roads

In recent years, disasters caused by extreme meteorological phenomena such as strong typhoon, hurricane, local heavy rain, drought and heat wave have occurred and caused enormous damage all over the world. To address the influence of global climate change, adaptation measures against already surfaced impact and unavoidable effect in the medium to long term are required as well as mitigation measures, including reduction of greenhouse gas emissions.

Table 6.3.2 shows major influence of climate change on roads.

Table 6.3.2 Major Influence of Climate Change on Roads

Cause	Influence
Increase in Rainfall and Rainfall Intensity	<ul style="list-style-type: none"> • Flood on roads • Inundation and wash away of roads • Destabilization of road structure and collapse of road embankment • Reduction in drainage capacity due to sediment runoff
Rise in Temperature	<ul style="list-style-type: none"> • Deterioration and damage of pavement
Increase in Wind Force	<ul style="list-style-type: none"> • Reduction of stability of bridges

Source: JICA Study Team

17) Possible Adaptation Measures in the Project

The CPRR, forming arterial road network in Chennai, is expected to play important roles such as emergency transport route, route for police and fire fighting, and others. To develop a safe and reliable road, it is desirable to undertake adaptation measures against climate change as shown in Table 6.3.3 during the detailed design and/or construction supervision stages.

Table 6.3.3 Adaptation Measures against Climate Change in the Project


Item	Adaptation Measures against Climate Change
Road Embankment	<ul style="list-style-type: none"> • Setting out of the proposed elevation based on recent rainfall trend • Proper design of slope protection in inundation-prone areas • Design of embankment and soft ground treatment considering lowering of groundwater level
Drainage	<ul style="list-style-type: none"> • Design of drainage facilities considering lowering of capacity due to sediment runoff
Pavement	<ul style="list-style-type: none"> • Application of superelevation for drainage • Use of sound material for pavement
Bridge	<ul style="list-style-type: none"> • Design of bridges based on recent rainfall trend and appropriate design discharge • Consideration of appropriate wind load

Source: JICA Study Team

7. PRELIMINARY DESIGN OF CHENNAI PERIPHERAL RING ROAD INTELLIGENT TRANSPORT SYSTEM (CPRR ITS)

7.1 Scope and Objectives of Preliminary Design of the Chennai Peripheral Ring Road Intelligent Transport System (CPRR ITS)

The scope of the CPRR ITS Project, which will be introduced to CPRR by Japanese official development assistance (ODA) loan, was determined based on the studies carried out so far and discussions with Tamil Nadu State as shown in Figure 7.1.1. There are two components, i.e., Highway Traffic Management System (HTMS) and Toll Management System (TMS), and each is composed of some subsystems. The preliminary design of these components, including identifying the quantity of equipment and cost estimation, was carried out for the formulation of this Japanese ODA Loan Project.



Source: JICA Study Team

Figure 7.1.1 Scope of CPRR ITS for the Project

7.2 Highway Traffic Management System (HTMS)

The design concept of HTMS is shown in Table 7.2.1.

Table 7.2.1 Design Concept of HTMS

Subsystem	Design Concept
CCTV System (CCTV)	<ul style="list-style-type: none"> • It monitors the traffic situation on CPRR from the center. • The details of the traffic event detected by VIDS are confirmed from the center using the PTZ function (*); accordingly, the necessary actions are to be taken, e.g., dispatching the patrol cars, and informing the relevant organizations. • The film footages taken are kept in the server for a certain period and are shared to the relevant organizations upon request, e.g., traffic police. • The operation status of the facilities and system are monitored, and the maintenance team is dispatched in case of failure.
Video Incident Detection System (VIDS)	<ul style="list-style-type: none"> • It detects incidents occurred on CPRR, and an alarm is automatically issued. • The video is automatically taken when detected and kept in the server for a certain period. • The number/frequency of occasion of the incident is summarised and reported to TNRDC in such format as weekly, monthly, and yearly report. • The operation status of the facilities and system are monitored, and the maintenance team is dispatched in case of failure.
Automatic Traffic Counter Cum System (ATCC)	<ul style="list-style-type: none"> • It counts traffic volume by vehicle type. • The measured data is kept in the server for a certain period and summarised by time and day. • The result is reported to TNRDC in such format as weekly, monthly, and yearly report. • The operation status of the facilities and system are monitored, and the maintenance team is dispatched in case of failure.
Meteorological System (MET)	<ul style="list-style-type: none"> • It measures precipitation, wind velocity, and visibility, and the alarm is automatically issued when the measured results reach the threshold value. • The alarm messages are provided to road users through VMS and internet in case the threshold value is reached. • The measured data which reached the threshold value is kept in the server for a certain period, and the number/frequency of occurrence of reaching the threshold value is summarised. • The operation status of the facilities and system are monitored, and the maintenance team is dispatched in case of failure.
Variable Message Sign Board System (VMS)	<ul style="list-style-type: none"> • Information, such as accidents, road work, lane restrictions, and actions that need to be taken by the road users, is provided. • The provided information is updated every five minutes as necessary. • Information to be provided is made by combining the preset messages that are prepared by the operators in advance. Free messaging can also be provided. • The languages to be used are selected from English, Hindu or Tamil, or automatically switched. • The operation status of the facilities and system are monitored, and the maintenance team is dispatched in case of failure.
Internet System	<ul style="list-style-type: none"> • Information, such as accidents, road work, lane restrictions, and actions that need to be taken by the road users, is provided. • The provided information is updated every five minutes as necessary. • The languages to be used are selected from English, Hindu or Tamil by the internet users. • The operation status of the facilities and system are monitored, and the maintenance team is dispatched in case of failure.

(*) PTZ Function: PTZ is an abbreviation of 'Pan' which means moving the camera lens to the direction of right or left, 'Tilt' which means moving the camera lens to the direction of up and down and 'Zoom' which means zooming. PTZ Function refers to those functions of CCTV.


Source: JICA Study Team

(1) Location Plan and Quantity of Roadside Equipment of HTMS

CCTV and VIDS are proposed to be installed at the merging point of on/off ramps to/from the carriage way of CPRR and the merging point between CPRR and Tiruvottiyur Ponneri Pancheti (TPP) Link Road. The measurement equipment of the meteorological system is proposed to be installed on both ends of CPRR. The sensors of the Automatic Traffic Counter cum Classifier (ATCC) are proposed to be installed between (i) the toll barrier of CPRR (Ch.15+800) and the junction of TPP Link Road (Ch.6+200), (ii) the junction of TPP Link Road (Ch.6+200) and the end point of CPRR near the port (Ch.0+700), and (iii) the junction of

TPP Link Road (Ch.6+200) and the start point of TPP Link Road, for a total of three locations. VMS boards are proposed to be installed between (i) NH5 and the toll barrier of CPRR (Ch.15+800), (ii) the end point of CPRR near the port (Ch.0+700) and the junction of TPP Link Road (Ch.6+200), and (iii) the start point of TPP Link Road and the toll barrier on TPP Link Road (Ch.1+200), for a total of three locations.

The locations of roadside equipment of the HTMS and the location plan concept and quantity of equipment are shown in Figure 7.2.1 and Table 7.2.2, respectively.



Source: JICA Study Team

Figure 7.2.1 Location Plan of Roadside Equipment of HTMS

Table 7.2.2 Location Plan Concept and Quantity of Roadside Equipment of HTMS

Facilities	Location Plan Concept	Quantity
CCTV System (CCTV)	It will be installed to confirm the situation, e.g., accident at site detected by VIDS, equipped with PTZ function.	10
Video Incident Detection System (VIDS)	It will be installed at black-spot locations, i.e., merging points of service roads entering CPRR and around the junction of CPRR and TPP Link Road.	10
Automatic Traffic Counter Cum System (ATCC)	It will be installed to measure the traffic volume by section. The proposed locations are between (i) the end point of CPRR near the port and TPP Link Road junction, (ii) the TPP Link Road junction and CPRR toward NH5, and (iii) the TPP-link junction and start point of TPP Link Road. The sensors are proposed to be installed at one location in both directions at those places.	6
Meteorological System (MET)	It will be installed to measure the precipitation, wind direction/velocity, and visibility at two locations, i.e., both ends of CPRR. The alarm messages will be issued in case the measured data reaches the threshold value.	2
Variable Message Sign System (VMS)	It will be installed to provide information on the traffic situation ahead of the vehicles entering CPRR and TPP Link Road. The information to be provided are accident, congestion, road work, lane restrictions, etc.	3


Source: JICA Study Team

Fiber optic cables will be laid on the shoulders on both sides of the CPRR, and the roadside equipment will be connected by this communication network exclusive for CPRR.

Center for HTMS: Traffic Management Center

The Center for HTMS: Traffic Management Center, is proposed to be located at a different location from the toll plaza because of the different natures of work. The Traffic Management Center will be for highway management, whereas the toll plaza will be engaged in handling the toll. It is proposed that the Traffic Management Center will be constructed at Ch.8+600, which satisfies the conditions that (i) it is almost at the mid-point of Section 1 from a viewpoint of operation and management for the target section, (ii) there is sufficient space for the Center in terms of right of way (ROW), and (iii) it does not affect the parking area for the large vehicles planned nearby.

Figure 7.2.2 shows the location plan for the Traffic Management Center.



Source: JICA Study Team

Figure 7.2.2 Location Plan for Traffic Management Center (HTMS)


7.3 Toll Management System (TMS)

(1) Toll Collection Method

Manual toll collection and electronic toll collection (ETC) (RFID method: FASTag) will be adopted. The Touch-and-Go system using an interchange (IC) card will not be adopted because the plan towards realizing the common mobility card or electronic settlement, which can be used across different transport modes, is still under discussion in Chennai, and it is not clear when such payment method will become available in Chennai. Thus, it is anticipated that sufficient increase of Touch-and-Go usage cannot be expected and that the convenience for road users are limited by the IC card, which can be used only for Section 1 of CPRR. Regarding the tariff system, the distance-based system will be adopted. (More details are given in Chapter 8.)

Locations of Toll Plazas

According to discussions with Tamil Nadu Road Development Company (TNRDC), it has been determined that toll plazas will be constructed in two locations as shown in Figure 7.3.1. As shown below, the toll barriers will be located on the main carriageway of CPRR (Ch.15+800) and TPP Link Road (Ch.1+200). (The reasons of determining those locations are given in Chapter 8)



Source: JICA Study Team

Figure 7.3.1 Locations of Toll Plazas


8. IMPLEMENTATION ORGANIZATION FOR CPRR ITS

8.1 Organizational Framework of Project

The following figure shows the organizational framework of the Intelligent Transport System (ITS) Project for Chennai Peripheral Ring Road (CPRR). The Tamil Nadu Road Development Company (TNRDC) will be responsible for the implementation of Section 1 of the Project as shown in the figure below. Under TNRDC, the Consultants for civil construction and ITS will be procured. The Consultant for ITS will be in-charge of basic design, tender assistance, and supervision of construction and operation and maintenance (O&M).

The O&M for the Highway Traffic Management System (HTMS) will be carried out by the supplier of the system who is in-charge of the detailed design and installation. As for the Toll Management System (TMS), the detailed design and installation will be completed by the supplier of the system, but the O&M contractor will be procured separately.

The Chennai Smart City Limited (CSCL) will engage in the Project, taking an advisory role and assisting as necessary.



(BD: Basic Design, DD: Detailed Design, TA: Tender Assistance, CS: Construction Supervision, OM: Operation and Maintenance)

Source: JICA Study Team

Figure 8.1.1 Organizational Framework of ITS Project for CPRR


8.2 Operation and Maintenance (O&M) Plan for Chennai Peripheral Ring Road Intelligent Transport System (CPRR ITS)

CPRR ITS has two ITS components, i.e., HTMS and TMS. This clause describes the required ITS O&M structure, roles, number of staff, and their shift arrangement. TNRDC, which is the responsible organization for tender and O&M, intends to hire two different O&M companies for HTMS and TMS, respectively. Therefore, the O&M plans for HTMS and TMS were considered separately.

8.2.1 Highway Traffic Management System (HTMS)

Organizational Structure for O&M of HTMS

The organizational structure for O&M of the HTMS and the required number of staff are shown in the figure below.



*1: The number of staff in the figure above indicates the total number including shifts. The shift plans are described in the subsequent clauses.

Source: JICA Study Team


Figure 8.2.1 Organizational Structure and Number of Staff for O&M of HTMS

The HTMS O&M Team consists of the staff of the O&M contractor which will be formed under the Project Director of TNRDC. All staff of the HTMS O&M Team will work in the Traffic Management Center building.

Collaboration with Other Related Organizations in the Transport Sector in Chennai

The planned route of CPRR will connect industrial parks in the suburbs, such as Oragadam and Mahindra World City, and the ports, such as Ennore Port and Kattupalli Port, and will contribute to the mitigation of the incoming flow of large vehicles into the city. The coordination of traffic information between CPRR ITS

and City ITS and the collaboration with related organisations are vitally important to control the traffic flow, maximizing the efficient use of the road network in Chennai. The figure below shows the examples of information exchange between CPRR ITS, i.e., Traffic Management Center of HTMS, and the related organisations. The collaboration shall be executed among the related organisations and centers in Chennai as shown below.




Source: JICA Study Team

Figure 8.2.2 Examples of Information Exchange between Traffic Management Center of HTMS for CPRR and Related Organizations

8.2.2 Toll Management System (TMS)

Organizational Structure for O&M of TMS

The organisational structure for the O&M of TMS and the required number of staff are shown below.



*1: The number of staff in the figure above indicates the total number including the shifts. The shift plans are described in the subsequent clauses.

Source: JICA Study Team

Figure 8.2.3 Organization Structure and Number of Staff for O&M of TMS

The TMS O&M Team consists of the staff of the O&M contractor, which will be formed under the project director of TNRDC. All the staff of the TMS O&M will work in the two toll plazas.

Toll Fare System (Distance Based Toll Collection) and Toll Collection Method

As a result of discussions with TNRDC, it was decided to adopt Distance Based Toll Collection as the toll fare system based on the TNRDC policy for the target section of the Project. It was also agreed with TNRDC that toll barriers will be installed at two locations, i.e., on the west side of CPRR main carriageway and on TPP Link Road, with consideration of the following matters:

- A part of the toll plaza to be constructed should be on the embankment.
- Sufficient space should be secured next to a toll plaza for the toll plaza building and parking.
- Enough space for the toll plaza square should be secured.
- The longitudinal gradient should be less than 3%.
- A certain distance should be secured from the edge of the toll plaza square to the entrance/exit ramp.
- The distance between the grade junction point and the taper end of toll plaza square should be more than 600 m (by IRC).

The Distance Based Toll Collection method was considered for cash and ETC payments, on the condition that two toll barriers will be constructed. The explanatory image for consideration is shown in Figure 8.2.4, where the letters A, B, C, and D are given to explain the relation between the traveling section of vehicles and the toll fare for each case where E and F represent Toll Barriers on CPRR and TPP Link Road,

respectively. There are many entrance/exit ramps where the vehicles can enter the target section for free from the parallel service roads.



Source: JICA Study Team

Figure 8.2.4 Explanatory Figure for Toll Collection Method and Location of Toll Plazas

9. PROCUREMENT PLAN, CONSTRUCTION PLAN, AND COST ESTIMATE

This part is intentionally left blank

This part is intentionally left blank

This part is intentionally left blank

This part is intentionally left blank

This part is intentionally left blank

10. IMPLEMENTATION SCHEDULE OF SECTION 1

10.1 General

The subject of this study was originally the Chennai Peripheral Ring Road (CPRR) Project and the Chennai City Intelligent Transport System (ITS) Project. However, the procedure for environmental social consideration of CPRR was delayed. For this reason, JICA decided to separate the Chennai City ITS Project from the CPRR Project and aimed only for the Chennai City ITS Project as the initial goal of the March 2018 loan agreement (L/A). The Tamil Nadu Infrastructure Development Board (TNIDB) applied to the DEA to list Chennai City ITS Project separately from CPRR Project and to list it in the rolling plan independently. Based on the above, the project implementation schedule of the CPRR Project and the Chennai City ITS Project was independently examined. Regarding the Chennai City ITS project, the study results are compiled in Vol. 2 of this report.

10.2 Tentative Implementation Schedule for CPRR

Between consultation with Japan International Cooperation Agency (JICA), it had high economic validity, most advanced land acquisition progress, and highest priority among sections. During consultation with inhabitants around the site of the Tiruvottiyur Ponneri Pancheti (TPP) Link Road (Original Alignment), it was found that it is important to obtain social consensus for the road construction. As an alternative solution to minimise the social impact, the south end of TPP Link Road is to be shifted approximately 1.5 km west

from the original alignment. This new alternative alignment totals 3.6 km from the connecting point with Northern Port Access Road (NPAR) to the southern end. The 1.65-km section in the northern part is the same as the original alignment, and the remaining 1.95 km in the southern part is different from the original alignment. Through an additional survey at the alternate site, social consensus was confirmed for the new alignment. Therefore, it is expected that NPAR and TPP Link Road (New Alignment) will become the object of the Japanese official development assistance (ODA) loan project as Section 1. Sections 2, 3, and 4 are also confirmed for economic validity of the project in "4.3 Prioritization of Components for Implementation".

Figure 10.2.1 shows the proposed project schedule of CPRR Section 1.

11. ENVIRONMENTAL AND SOCIAL CONSIDERATIONS

The Chennai Peripheral Ring Road (CPRR) Project is divided into five sections. The first stage of this study reviewed all the sections and finally selected Section 1 as priority section. After the selection of the priority section, Section 1 was examined in detail. Therefore, the main scope of the Project is Section 1.

Section 1 consists of the Northern Port Access Road (NPAR) and the TPP Link Road. After the detailed survey and consultation with local residents, it was concluded that social consensus was not yet formed on the TPP Link Road. The Highways and Minor Ports Department (HMPD) moved the southern end of the TPP Link Road about 1.5 km west of the original alignment. The length of the new alignment is 3.6 km, with the original 1.65 km in the north and the new 1.95 km in the south. Social consensus on TPP Link Road (new alignment) was confirmed. It is expected, therefore, that Section 1 (main road (Northern Port Access Road) and TPP Link Road (new alignment)) will be the target of the Japanese ODA Loan Project.

The objective of this study is for the JICA Study Team 1) to review the environmental impact assessment (EIA) and resettlement action plan (RAP) reports prepared by HMPD, 2) to study the gaps between the above reports and the requirements of the JICA guidelines, and 3) to conduct additional studies to fill in the gap if there is any.

11.1 Review of the DPR EIA/SIA/RAP for All Sections

11.1.1 Screening

The Project is categorized A according to the JICA Environmental and Social Guidelines 2010 because the road sector is likely to have significant adverse impacts on the environment, and its components are likely to have significant adverse impacts on the society regarding large-scale involuntary resettlement.

Environmental Notification 2006, with its amendment in 2009, 2011, and 2013, stipulates the conduction of EIA, Environmental Clearance (EC), and their procedures according to the type, size, and location of the proposed project. The proposed project can start only after the EC is granted. For a State Highway (SH) project, acquiring an EC is stipulated. The proposed project includes new construction highway intervals; therefore, the Project is categorized B in 7(f) (i) wherein an EC is required.

The HMPD (Chengalpattu Divisional Engineer (H)) has applied for EIA TOR for the CPRR Project on 26 October 2017. The Tamil Nadu State Environmental Impact Assessment Authority (TNSEIAA) issued the EIA TOR on 5 March 2018 to HMPD. HMPD submitted the draft EIA report to Tamil Nadu State Pollution Control Board (TNSPCB) on 11 April 2018. TNSPCB called for public comments, then, conducted public consultation meetings in Kancheepuram District on 10 July 2018 and in Thiruvallur District on 12 July 2018. The collected comments/opinions and records of the meeting were reflected on the final EIA report, and the report was submitted to TNSEIAA on 20 July 2018.

11.1.2 Review of the DPR EIA and SIA/RAP

Initial environmental evaluation and public consultations were also implemented to disseminate the Project, the survey results on environmental and social impacts, plan and policy on land acquisition, and framework of compensation and other assistances.


The environmental impacts expected to be caused by the CPRR are the same as those caused by the ordinal road construction works and existence of artery roads. In this sense, the prediction of impacts described in the DPR EIA was agreed in principle by the JICA Study Team.

11.2 Environmental and Social Considerations in Section 1

11.2.1 General Condition of the Project Area

The alignment of the link road is not significantly changed. The general condition of the Project area applies also to TPP Link Road (New Alignment).

The study area is located on the east coastal plain of India. The topography of the area is almost flat. The Thiruvallur District is located in Section 1, the share of wasted land and unculturable land is 46.1%, and the other 34% is agriculture and pasture land. Land use of Section 1 ROW shows the same components with that of the district in general.



Source: JICA Study Team

Figure 11.2.1 Images of the Land Use on ROW of Section 1 and Nearby Area

The ROW of Section 1 is not located in or near any protected areas designated by Tamil Nadu or Indian governments. Section 1 is located in the Coastal Regulation Zone.

In India, national parks and wildlife sanctuaries are designated for the areas where there are certain necessities for natural environment protection under the Wildlife Protection Act 1972. The CRZ within the project area is not designated as such and is not classified as ‘Protected Area’ according to the definition of the JICA Guidelines.

11.2.2 Impact Assessment

Based on the survey results, final impact assessment in the planning, construction, and operation phases are described in and Table 11.2.1. The table explains the impact assessment for Section 1, together with specific considerations necessary for other sections.

Table 11.2.1 Impact Assessment and Evaluation

	Impacts	Scoping of Potential Impacts		Main Road & TPP Link Road (Original Alignment)		Main Road & TPP Link Road (New Alignment)	
		Planning & Construction	Operation	Planning & Construction	Operation	Planning & Construction	Operation
Pollution Control							
1	Air Pollution	B-	B±	B-	B±	B-	B±
2	Water Pollution	B-	B-	B-	B-	B-	B-
3	Waste	B-	D	B-	D	B-	D
4	Soil Contamination	B-	D	B-	D	B-	D
5	Noise and Vibration	B-	B±	B-	B±	B-	B±
6	Ground Subsidence	C	C	D	D	D	D
7	Offensive Odor	D	D	D	D	D	D
8	Bottom Sediment	D	D	D	D	D	D
Natural Environment							
9	Sanctuary	D	D	D	D	D	D
10	Ecosystem	B-	B-	B-	B-	B-	B-
11	Hydrological Situation	B-	B-	B-	B-	B-	B-
12	Topography and Geographical Features	B-	D	D	D	D	D
13	Involuntary Resettlement, Loss of	A-	D	A-	D	A-	D

	Impacts	Scoping of Potential Impacts		Main Road & TPP Link Road (Original Alignment)		Main Road & TPP Link Road (New Alignment)	
		Planning & Construction	Operation	Planning & Construction	Operation	Planning & Construction	Operation
	Land and Asset, Business Relocation						
14	The Poor	B-	D	B-	D	B-	D
15	Ethnic Minorities, Indigenous Peoples	D	D	D	D	D	D
16	Local Economy, Employment and Living, Livelihood	B±	B+	Section 1 B+ Section2 B+ Section3, Section5 B±	B+	Section 1 B+	Section 1 B+
17	Land Use, Local Resource Use	D	D	D	D	D	D
18	Water Use, Water Rights	B-	B-	B-	B-	B-	B-
19	Existing Public Facilities, Road and Transportation Facilities, Social Infrastructure, Social Services	B-	B±	B-	B±	B-	B±
20	Social Capitals, Local Decision-making Systems, Social Organizations	D	D	D	D	D	D
21	Uneven Distribution of Project Impact and Benefit	D	D	D	D	D	D
22	Local Conflicts of Interest	D	D	D	D	D	D
23	Split of Community	B-	C	B-	Section 1 D Section2 D Section3 Section5 B-	B-	Section 1 D
24	Historical Heritage, Cultural Resources	D	D	D	D	D	D
25	Landscape	D	D	D	D	D	D
26	Gender	D	D	D	D	D	D
27	Children's Rights	B-	B-	B-	B-	B-	B-
28	Sanitation, Public Health, Transmittable Diseases including HIV/AIDS	B-	D	B-	D	B-	D
29	Work Environment, Occupational Safety and Health	B-	B-	B-	B-	B-	B-
30	Accidents, Crime	B-	B±	B-	B±	B-	B±
31	Climate Change, Cross-border Impacts	B-	B±	B-	B±	B-	B±

A+/-: Remarkably positive/serious negative impact is predicted.

B+/-: Positive/negative impact is expected to some extent.

C: Extent of impact is unknown. (Further study is necessary.)

D: Impact is very small or nil, and further survey is not required.

Source : JICA Study Team

11.3 Land Acquisition and Resettlement of Section 1

11.3.1 Project Affected Structures, Households and Businesses in Section 1 (Main Road and TPP Link Road (Original Alignment))

Project affected households and businesses in Section 1 are shown in Table 11.3.1. In total, 206 structures and households, 24 businesses, and 16 public facilities are to be displaced. The Census Survey by HMPD in 2017 recorded the number of households and businesses within the ROW. The size of a household was asked in the Socio-economic Survey which resulted to an average household size of 4.1 persons. The number of persons to be displaced was estimated at 845 persons by multiplying the number of PAH by 4.1 (206 x 4.1 = 844.6).

Table 11.3.1 Project Affected Assets in Section 1 (Main Road and TPP Link Road (Original Alignment))

Ownership	Category		Displaced			Non-displaced		
			Main Road	TPP Link Road (Original Alignment)	Total	Main Road	TPP Link Road (Original Alignment)	Total
Owner	Residential	a	15	135	150	0	0	0
	Commercial	b	4	9	13	0	0	0
	Residential and Commercial	c	2	7	9	0	0	0
	Others	d	-	-	-	9	2	11
	Abandoned	e	-	-	-	8	2	10
	Under construction	f	0	5	5	0	0	0
	Structures to be affected with minor impact (less than 1/3)	g	-	-	-	0	4	4
	Subtotal		21	156	177	17	4	21
Squatters	Residential	h	17	2	19	0	0	0
	Commercial	i	1	0	1	0	0	0
	Residential and Commercial	j	0	0	0	0	0	0
	Others	k	-	-	-	0	0	0
	Abandoned	l	-	-	-	0	0	0
	Subtotal		18	2	20	0	0	0
Tenants	Residential	m	0	8	8	-	-	-
	Commercial	n	1	0	1	-	-	-
	Residential and Commercial	o	0	0	0	-	-	-
	Subtotal		1	8	9	-	-	-
Total Structures and Households		p	40	166	206	17	4	21
Business Total b+c+i+j+n+o		q	8	16	24	0	0	0
Public Facilities		r	11	5	16	0	0	0
Non-residential Land Owners		s	-	-	-	448	549	997
Workers		t	-	-	-	5	6	11

Squatter: Illegal occupants of private and public land

Source : DPR RAP July 2018 Table 5.40, Table 5.41

11.3.2 Project Affected Structures, Households and Businesses in Section 1 (Main Road and TPP Link Road (New Alignment))

Project affected households and businesses in Section 1 (Main Road and TPP Link Road (New Alignment)) are shown in Table 11.3.2. In total, 60 structures and households, 8 businesses, and 11 public facilities are to be displaced. The census conducted by HMPD in 2017 recorded the number of households and businesses within the ROW. The size of a household was asked in the Socio-Economic Survey, and the average household size was determined to be 4.1 persons. The number of persons to be displaced was

estimated by multiplying the number of PAH by 4.1, thus arriving at 246 persons (60 x 4.1 = 246).

Among the 60 structures to be displaced, 40 structures are located on the ROW of the Main Road and 20 structures are located on the ROW of TPP Link Road (New Alignment).

Table 11.3.2 Project Affected Assets in Section 1 (Main Road and TPP Link Road (New Alignment))

Ownership	Category	Displaced			Non-Displaced		
		Main Road	TPP Link Road (New Alignment)	Total	Main Road	TPP Link Road (New Alignment)	Total
Owner	a Residential	15	12	27	0	0	0
	b Commercial	4	0	4	0	0	0
	c Residential and Commercial	2	0	2	0	0	0
	d Others (i.e. wells)	-	-	-	9	0	9
	e Abandoned	-	-	-	8	0	8
	Subtotal		21	12	33	17	0
Squatters	f Residential	17	0	17	0	0	0
	g Commercial	1	0	1	0	0	0
	h Residential and Commercial	0	0	0	0	0	0
	i Others	-	-	-	0	0	0
	j Abandoned	-	-	-	0	0	0
	Subtotal		18	0	18	0	0
Tenants	k Residential	0	8	8	-	-	-
	l Commercial	1	0	1	-	-	-
	m Residential and Commercial	0	0	0	-	-	-
	Subtotal		1	8	9	-	-
Structures and Households Total	n	40	20	60	17	0	17
Business Total b+c+g+h+l+m	o	8	0	8	0	0	0
Public facilities	p	11	0	11	0	0	0
Non-residential land Owners	q	-	-	-	448	296	744
Workers	r	-	-	-	5	0	5

Squatter: Illegal occupants of private and public land
Source: DPR RAP 2018 p.iv, Table 5.43

11.3.3 Project Affected Structures, Households and Businesses in Section 1 (Main Road and TPP Link Road (New Alignment))

The land area necessary for land acquisition for Section 1 (Main Road and TPP Link Road (New Alignment)) is 250.81 ha, as shown in Table 11.3.3.

Table 11.3.3 Land Area for Acquisition

	Private Land (ha)	Public Land (ha)	Total (ha)
Main Road	152.42	73.89	226.31
TPP Link Road (New Alignment)	18.84	5.66	24.50
Total	171.26	79.55	250.81

Source: 31 July 2018 HMPD

11.4 Stakeholder Meetings

Public consultations following JICA guidelines are held twice.

Besides the above consultations, TNSPCB held public consultations on the draft EIA report submitted by HMPD for all sections in Chengalpattu, Kancheepuram District on 10 July 2018, and at Thamaraiykkam in Thiruvallur District on 12 July 2018.

During the census for the PAHs of the TPP Link Road (New Alignment) in July 2018, consultation at each house was conducted for all the 20 PAHs. Out of all the PAHs, three HHs were absent during the visit. There were four HHs represented by women during the meetings. The consultation included information dissemination about the project, free queries and answers, and question on willingness to relocate to the proposed relocation site. The stakeholder meeting and site visit for the PAHs of the TPP Link Road (New Alignment), including ROW title holders, absentee land owners, local residents, road users of TPP Road, and general public, was organized at the project area, or Bharathi Nagar, on 12 July 2018 from 2:00 pm to 4:00 pm. Bharathi Nagar is the residential area located at the southern end of the TPP Link Road (New Alignment).

Table 11.4.1 Summary of the First Meetings

Sl. No.	Description	Minjur	Panchetti
1	Date	11:00 to 14:00, Monday, 9 April 2018	11:00 to 14:00, Tuesday, 10 April 2018
2	Venue	Block Development Office, Minjur	Village Panchayat Office, Panchetti
3	Officials Present	<ul style="list-style-type: none"> ● HMPD Assistant Divisional Engineer, Ponneri and Thiruvallur ● TNRDC, SM ● HMPD Consultant (STUP) 	<ul style="list-style-type: none"> ● HMPD Assistant Divisional Engineer, Ponneri and Thiruvallur ● TNRDC, SM ● HMPD Consultant (STUP)
4	No. of Participants	More than 250 including NGOs (lady participants: 45)	More than 90 including NGOs (lady participants: 4)
5	Attendance Signed	145	47

Source: HMPD

Table 11.4.2 Summary of the Second Meetings

No.	Description	Minjur	Panchetti
1	Date	11:00 to 14:00, Friday, 11 May 2018	11:00 to 14:00, Saturday, 12 May 2018
2	Venue	Block Development Office, Minjur	Village Panchayat Office, Panchetti
3	Officials Present	<ul style="list-style-type: none"> ● HMPD Assistant Divisional Engineer, Ponneri and Thiruvallur ● TNRDC, SM ● HMPD Consultant (STUP) 	<ul style="list-style-type: none"> ● HMPD Assistant Divisional Engineer, Ponneri and Thiruvallur ● TNRDC, SM ● HMPD Consultant (STUP)
4	No. of Participants	More than 200 including NGOs (lady participants: 22)	More than 75 including NGOs (lady participants: 1)
5	Attendance Signed	63	22

Source: HMPD

Table 11.4.3 TNSPCB Consultations

Dates	Locations
10 July 2018	Divisional Engineers Office, Chengalpattu, Kancheepuram District
12 July 2018	S.V. Rajammal Marriage Hall, Thamaraiykkam, Thiruvallur District

Source: http://www.environmentclearance.nic.in/writereaddata/FormB/EC/Public_Hearing/20072018CDTZ15DIAAnnexure-DocumentofPublicHearing.pdf

12. PROJECT EVALUATION

12.1 Economic Analysis

The main objective of this economic analysis is to examine the investment efficiency of the project from the viewpoint of the national economy using cost-benefit analysis in the case where it can be applied. Market prices are converted to economic costs where the influence of market distortion is removed (so-called shadow prices). Opportunity costs are used for the costs of goods and services if their markets do not exist. Economic Internal Rate of Return (EIRR) is used as an indicator of the efficiency of a project investment.

A main objective of this financial analysis is to examine the efficiency of a project investment from the viewpoint of the project implementation body using cost-benefit analysis. Market prices are used. An Internal Rate of Return (IRR) is used as the indicator of the efficiency of a project investment. IRR used in financial evaluation is called the Financial Internal Rate of Return (FIRR).

This part is intentionally left blank

13. CONCLUSIONS AND RECOMMENDATIONS

13.1 Necessity and Effect of the Chennai Peripheral Ring Road (CPRR) Project

With regard to the necessity and development effect of Chennai Peripheral Ring Road (CPRR) Project, the effects of traffic congestion mitigation and economic validity were examined and evaluated taking into account the traffic situation as of 2017. As a result, this project diverts through traffic as a peripheral ring road forming a ring and radial road network constituting the Chennai Metropolitan Area (CMA), and by provision of access between industrial area and regional transportation facilities, and improvement of the urban environment in CMA. It was confirmed that this project greatly contributes to economic development of CMA.

As a result of economic analysis based on the future traffic demand and project cost of each sections, the

Economic Internal Rate of Return (EIRR) of this project was calculated as follows: Section 1: 18.1%, Section 2: 19.7%, Section 3: 20.2%, and Section 5: 12.8%. Regarding Section 4, development was implemented by the state government's own funds, and as a subject for loan project, a comprehensive evaluation including the degree of environmental and social impact is added to the economic analysis, resulting in the table below.

Table 13.1.1 Result of Prioritization

Criteria		Indicator	Sec.1	Sec.2	Sec.3	Sec.5
1	Effect on Improvement of Traffic Situation	Traffic Volume (pcu/day)	58,324	31,184	89,528	43,282
		SCORE	8	6	9	7
		Reduction in Total Travel Time (vehicle hour)	54,871	45,192	67,494	26,239
		SCORE	8	7	8	5
		Large Vehicle Rate (%)	76	13	25	27
		SCORE	10	4	6	7
2	Magnitude of Environmental and Social Impact	Impact on Reserved Forest and Coastal Regulation Zone	RF: - CRZ: Cat..III	RF: - CRZ: -	RF: 0.28 CRZ: -	RF: 9.95 CRZ: -
		SCORE	7	10	7	5
		Area of Land to be Acquired (ha)	255	188	208	163
		SCORE	5	7	6	7
3	Economic Rationality	EIRR (%)	18.1	19.7	20.2	12.8
		SCORE	7	7	7	5
TOTAL SCORE			45	41	43	36
PRIORITY			1	3	2	4

Source: Land Acquisition Area: STUP's Letter E/14518/149/NJW/GK/0132 dated 11 Aug 2017,
Project Cost: Construction Cost shown in DPR Main Report, P9-3

1st 2nd 3rd

Source: JICA Study Team

With respect to Tiruvottiyur Ponneri Pancheti (TPP) Link Road, Highways and Minor Ports Department (HMPD) conducted a survey on the alternate alignment from May to June of 2018, as inhabitants' opposition was given to the original alignment. In early July, the government decided a new alignment of 3.6 km from the TPP Link Road around Minjur to Northern Port Access Road (NPAR) (as a main line of Section 1). Also, the new alignment connects to the Outer Ring Road (ORR) near Minjur.

13.2 Confirmation of Appropriateness of the Project Components

As a result of the review on the Detailed Project Report (DPR) and social environmental-related reports of CPRR, some issues were found. To be appropriate project under the official development assistance (ODA) scheme, the DPR of CPRR needs to consider the following:

Horizontal Alignment

Significant issues are not found for the horizontal curve radius. However, the spiral length is not sufficient in some sections. Thus, it is desirable to improve those sections.

Vertical Alignment

There is no issue with the gradient since all the applied values meet the Indian Road Congress (IRC) requirement throughout the route. However, the vertical curve length is not sufficient in some sections. Thus, it is desirable to improve those sections.

Entry/Exit and Service Road

Two-lane service roads that are to be operated as two-way roads are proposed on both sides of the main road. This system requires crossing at entries to enter the main road, and there is a concern of incursions and collisions at exits. Therefore, it is recommended to have a one-way operation on the service road at least in the vicinity of entries and exits.

Junctions

Traffic jam is expected at the at-grade intersection because of the increase in future traffic volume (large vehicles such as trailers) at the beginning point. It is proposed to have a separation of road for the through traffic (south to north) and left turn (south to west and west to north) and right turn (west to south and north to west).

Traffic jam is expected at the at-grade intersection between the main line and the TPP Link Road because of increase in future traffic volume (large vehicles such as trailers). To increase the capacity of the intersection, an exclusive lane for left turn (free left turn) is proposed instead of a left turn (east to south).

Traffic flow at the intersection of the ending point is complicated due to a roundabout. The installation of traffic signals is proposed at the crossing point to improve safety at the intersection.

Interchanges

Four interchanges are planned to connect the project road and the national roads.

As for interchanges (IC) 1, 2, and 3, left-turning traffic on the project road exit to the service road before the interchange. Vehicles enter the project road from the service road. Therefore, it takes a longer time and causes congestion on the service road. Additional direct ramps for left-turning traffic and a service road located outside of the ramps are proposed.

As for IC-1, 2, 3, the curve radius of the loop rampway is 70 m. However, the transition curve is not inserted between the straight line and curve. Therefore, the horizontal alignment and transition of super-elevation is not smooth. It is desirable to insert the transition curve between straight line and curve ($R=70$ m, $e=5\%$).

As for IC-1, 2, 3, the weaving is occurred between the merging point and the diverging point at the connected section of the main road and the rampway. There are four lanes in this section ($W=16$ m), including the rampway (one lane). The distance between the merging point and the diverging point is 240 m. It is expected that congestion is caused by the decrease of running speed considering the future traffic volume (weaving traffic and non-weaving traffic). It is recommended to increase the rampway width (one more lane) outside of the main road. The total width becomes 19.5 m (five lanes).

As for IC-2, the curve radius of the ramp terminal of the beginning side of the project road is 525 m. It has a small and steep super-elevation (5%). It is dangerous for cars passing with high speed, even with the installation of speed limitation signs (80 km/h). To improve safety, it is recommended to apply a radius bigger than 700 m, which is prescribed in the Road Structure Ordinance Standards of Japan. The curve radius of the ramp terminal of the main road follows a design speed of 80 km/h.

As for IC-3, the shape of this interchange is not symmetrical, avoiding the Hinduism Temple. Therefore, the distance between the merging nose and the diverging nose is short, and the weaving becomes difficult. Also, it is difficult to guide and safety is low. It is recommended to provide the distributing lane (design speed 40 km/h), which is parallel to NH5 at the end point side, and to connect the distributing lane and rampway. Moreover, the weaving distance becomes longer because the rampway alignment is changed.

As for IC-4, the elevated roundabout type is adopted, and the shape of the roundabout is an ellipse. The small radius is 35 m and big radius is 100 m. The distance between the merging nose and the diverging nose is longer, and the on-ramp and off-ramp are separated in order to decrease the influence of weaving. However, it is expected that congestion is caused by weaving, considering the future traffic volume. It is recommended to add the separated left-turn rampway outside of the roundabout in order to increase the capacity of the roundabout.

Major Bridge Design

There are piers planned as hybrid structures (bridge piers + reinforced earth walls) and piers planned as abutments (from Plan & Profile, Drawing). Hybrid structures are being constructed in many places in India. However, in areas affected by running water, maintenance and management will be a concern from the viewpoint of anti-erosion and protection from running water. The substructure at the ends of the bridge subject to the impact of flowing water is proposed to be constructed as an abutment type for the purpose of protecting from erosion and protecting the back soil from the reinforced earth wall.

Also, about bridge piers in the DPR drawing, there is no width allowance for the superstructure's bearing in the substructure's coping. It is preferable to provide an allowance in case unexpectedly large forces, such as earthquakes, occur. The width of the substructure, bearing width allowance, and other details must be reconsidered in the detailed design.

Minor Bridge Design

The minimum span of several minor bridges (MNBs) is set as 10 m. The DPR considers improving the accuracy of the bridge plan, including structural investigation at the time of the detailed design by setting

the short span and economical reinforced concrete slab bridge as the design standard. Investigation to increase economic efficiency by lengthening the span and reducing the number of piers, study to improve the river flow and constructability by reducing pier on the river, and confirmation of bridge plan details by consultation with environmental authorities should be examined and confirmed at the time of detailed design.

Interchange Bridge

The sectional view of a reinforced earth wall is in the drawing, and “Terre Armee” is placed between the northbound and southbound lanes. The total count is four planes. However, for bridges other than ICs, there is no cross-section drawing, but the number is counted in two-surface construction where no reinforced earth wall is placed between the northbound and southbound lanes.

The distance between the northbound and southbound lanes is about 4 m. If the reinforcing earth wall is arranged at the back of the bridge end, two sides can be constructed, and the structure is economical. Therefore, a plan for the reinforced earth wall of the IC with two-side construction is proposed.

There is a concern that the cantilever length of the slab is large and does not have sufficient reaction against the assumed dead load and live load. (The cantilever slab length is about 4 m based on the scale of the drawing.)

It is generally preferable that the cantilever length of the PC slab is within 3 m, and a review of the structure of the PC box girder for the purpose of reducing the cantilever length is proposed. It is better to plan a three-box girder because the space is wide. In addition, concerning the width of the beam of piers, it is necessary to revise the structure as well as review the box girder. The position of the bearing that supports the superstructure is based on the cross beams, and the spacing of the outer main girders is greater than the width of the beam of the pier.

To ensure that the vertical load is supported and to preserve the rigidity of the main girder, it is proposed that the beam width be larger than the outer main girder spacing and that the bearing be placed under the main girders.

Box Culvert

There is a part where the connection between the box culvert and the retaining wall structure on the box is simplified and integrated. Since the collision load of the guardrail vehicle may act on the top of the retaining wall. Attention should be focused on the following:

In order to ensure the rigidity of the end of the retaining wall, it is preferable to separate the box and retaining walls at the ends of the foundation.

The base of the retaining wall should be a spread foundation after carrying out the member calculation and stability calculation as a protective fence foundation.

Cost Estimate

The main report of DPR and Volume VIII [Cost Estimate] is not consistent with the contents and the results of the cost estimate. Therefore, Volume VIII, which was published in a new period, is regarded as a review subject in this study. It is noted that the ITS component is not included in the breakdown of Volume VIII.

DPR Volume VI [Rate Analysis] has not been provided to the Japan International Cooperation Agency (JICA) Study Team, and the basis for setting each unit price was unknown as of December 2017. For this reason, the unit price review of this survey was conducted to refer to the material above and to check whether there is any obvious mistake in the unit price setting. The JICA Study Team rebuilt unit prices based on the estimate materials of the Ministry of Road Transport and Highways (MORTH) Standard DATA Book for major work items with a high proportion of overall project cost such as borrow material and rebars. Because of evaluating the appropriateness of the DPR's unit price setting by comparing the unit price of each, it was considered that there is no obvious error in DPR because none of them have large deviations.

ITS for CPRR

As the ITS component for CPRR is not included in the cost breakdown of Volume VIII. The ITS component for CPRR should be examined and included in the DPR.

Project Scheme

HMPD expressed that the project scheme of CPRR is not PPP, and HMPD will prepare and implement

the project, complying with JICA procurement guidelines, namely the “Guidelines for the Employment of Consultants under Japanese ODA Loans” dated April 2012 and the “Guidelines for Procurement under Japanese ODA Loans” dated April 2012.

HMPD agreed in principle to apply Standard Bidding Documents (SBD) issued by JICA for the contract for Section 1 though HMPD, and JICA is discussing which particular SBD is to be applied for the project.

Project Implementation Schedule

The road stretch of Section 1 consists of Northern Port Access Road (NPAR) and TPP Link Road. During consultation with inhabitants around the site of the TPP Link Road (Original Alignment), it was found that it is important to obtain social consensus for the road construction. As an alternative solution to minimise the social impact, the south end of the TPP Link Road is to be shifted approximately 1.5 km west from the original alignment. This new alternative alignment has a total length of 3.6 km from the connecting point with the NPAR to the southern end. The 1.65 km stretch in the northern part is the same as the original alignment, and the remaining 1.95 km in the southern part is different from the original alignment. Through an additional survey at the alternate site, social consensus was confirmed for the new alignment. Therefore, it is expected that NPAR and TPP Link Road (New Alignment) will become the Section 1 of the Japanese ODA Loan Project. The proposed implementation schedule of Section 1 of the project is shown in Figure 10.2.1.

O&M

The Highways Division of the Construction and Maintenance Wing responsible for each area of CPRR will take over the O&M.

Section 1, Section 2, and a part of Section 3 of the CPRR will fall under the jurisdiction of Thiruvallur Highways Division. The remaining portions of Section 3, Section 4, and Section 5 will fall under the jurisdiction of the neighbouring Chengalpattu Highways Division. It is assumed that Performance Based Maintenance Contract (PBMC) will be introduced to the Chengalpattu Highways Division by the time the CPRR is completed. If the introduction should be delayed, the single-year maintenance contract will be used.

The structure of the Thiruvallur Highways Division consists of one divisional engineer, six assistant divisional engineers, and eight assistant engineers. This Highways Division will outsource the work of maintenance/patrol/traffic control with PBMC to an O&M contractor. There is a plan to collect toll for Section 1, and when it is carried out, toll collection will also be outsourced to a contractor. There is one field office for the divisional engineer and six field offices for the assistant divisional engineers taking charge of road construction other than large-scale projects and maintenance for state highways and major district roads.

Environmental and Social Considerations

HMPD agreed to implement land acquisition and resettlement process, complying with the “JICA Guidelines for Environmental and Social Considerations” dated April 2010.

CHAPTER 1 INTRODUCTION

1.1 Outline of the Study

1.1.1 Background of the Study

As in other major cities in India, traffic congestion is getting worse in Chennai Metropolitan Area (hereinafter referred to as “CMA”), which is the target area of the study, because road infrastructure improvements have not caught up with the increase in traffic demand due to population growth and economic development.

The Government of Tamil Nadu (GoTN) is promoting the development of roads and public transportation as a countermeasure to traffic congestion in CMA. The major arterial road network in CMA consists of National Highways No. 5, No. 205, No. 4, and No. 45 as major radial roads, and Inner Ring Road (IRR), Chennai Bypass, and Outer Ring Road (ORR) as ring roads. The implementation of the Chennai Peripheral Ring Road (CPRR) Project is expected to contribute to the further expansion of the Radial-Ring Road Network corresponding to the growing traffic demand.

In addition, as a countermeasure to alleviate congestion at the center of CMA where the development site for road infrastructure is limited, the improvement of Intelligent Transport System (ITS) facilities that promote efficient use of the road is an issue.

Based on this background, the Government of India (GoI) has prepared the Detailed Project Report (DPR) describing the development plan of CPRR and ITS and has requested the Government of Japan (GoJ) for loan assistance.

1.1.2 Objectives of the Study

The DPR presents the implementation plan for the following:

- Construction of CPRR (widening section: 36.5 km, new section: 96.9 km, total: 133 km), and
- Development of ITS facilities for CPRR and for the CMA road network.

The study aims to collect necessary information to appraise the Project for it to be implemented under the Official Development Assistance (ODA) scheme through the confirmation of the objectives and the outline of the Project, including project cost, implementation schedule, procurement and construction method, project organization, capability of operation and maintenance, as well as social and environmental conditions.

1.1.3 Target Sections of the Study

As shown in the location map of Chennai, CPRR is classified into Sections 1 to 5. In this study, preliminary investigation for the whole section was carried out as a first step of the project, and the result is that the priority is Section 1. After deciding the priority ranking, the JICA Study Team conducted a detailed investigation of Section 1. The road stretch of Section 1 consists of the Northern Port Access Road and the Tiruvottiyur Ponneri Pancheti (TPP) Link Road.

During the consultation with inhabitants around the site of the TPP Link Road (Original Alignment), it was found that it is very important to obtain social consensus for the road construction. As an alternative solution to minimizing the social impact, the south end of TPP Link Road is to be shifted approximately 1.5 km to the west of the original alignment. This alternative alignment has a total length of 3.6 km from the connecting point with Northern Port Access Road to the south end. The length of 1.65 km in the northern part is the same as the original alignment, and the remaining 1.95 km in the southern part is different from the original alignment. Through an additional survey at the alternative site, social consensus was confirmed for the new alignment. Therefore, it is expected that Northern Port Access Road and TPP Link Road (New Alignment) will become the Section 1 of the Japanese ODA Loan Project.

1.1.4 Scope of the Study

In accordance with the agreement between JICA and the Consultant, the following work items are carried out in the study:

- [1] Preparation and Discussion of Inception Report (IC/R)
- [2] Review of the Background of the Project
- [3] Survey on the Current Situation and Issues of Chennai Peripheral Ring Road (CPRR)
- [4] Traffic Survey and Traffic Demand Forecast
- [5] Formulation of the Project
- [6] Prioritization of Project Components
- [7] Preliminary Design
- [8] Construction Planning
- [9] Study on the Procurement Method
- [10] Formulation of Project Implementation Schedule
- [11] Confirmation of Project Implementation Structure
- [12] Confirmation of Operation and Maintenance (O&M) Structure
- [13] Environmental and Social Considerations
- [14] Study on Countermeasures against Climate Change
- [15] Project Cost Estimate
- [16] Study on Points to Consider for Project Implementation
- [17] Project Evaluation
- [18] Preparation of Basis of ITS Technical Specifications
- [19] Preparation and Discussion on Draft Final Report (DF/R)
- [20] Preparation of Final Report (F/R)

1.1.5 Work Schedule of the Study

The study was started in the middle of July 2017, and the F/R will be submitted in November 2018. Table 1.1.1 shows the work schedule of the study.

Table 1.1.1 Work Schedule of the Study

	Year 2017						Year 2018											
	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	
【Confirmation of Existing Condition and Project Prioritization】																		
[1] Preparation and Discussion on Inception Report (IC/R)	□																	
[2] Review on Background of the Project		■																
[3] Survey on the Current Situation and Issues of Chennai Peripheral Ring Road (CPRR)		■	■															
[4] Traffic Survey and Traffic Demand Forecast			■	■									■	■				
[5] Formulation of the Project				■	■													
[6] Prioritization of the Project Components				■	■													
【Preliminary Design】																		
[7] Preliminary Design				■	■	■	■	■	■			■	■	■	■			
[8] Construction Planning					■	■	■	■	■				■	■	■			
[9] Study on Procurement Method					■	■	■	■	■				■	■	■			
[10] Implementation Schedule of the Project					■	■	■	■	■				■	■	■			
[11] Confirmation of Project Implementation Structure					■	■	■	■	■				■	■	■			
[12] Confirmation of Operation and Maintenance (O&M) Structure					■	■	■	■	■				■	■	■			
[13] Environmental and Social Considerations		■	■	■	■	■	■	■	■	■	■	■	■	■	■	■	■	■
[14] Study on Countermeasures against Climate Change				■	■													
[15] Project Cost Estimate					■	■	■	■	■				■	■				
[16] Study on Points to Consider for Project Implementation					■	■	■	■	■				■	■				
[17] Project Evaluation					■	■	■	■	■				■	■	■			
[18] Preparation of Basis of Technical Specifications of ITS					■	■	■	■	■		■	■						
[19] Preparation and Discussion on Draft Final Report (DF/R)													■	■	■	■	■	■
[20] Preparation of Final Report (F/R)																		□
(Reports)																		
Inception Report (IC/R)		▲																
Interim Report (IT/R)						▲												
Interim Report-2 (IT/R-2)									▲	▲								
Draft Final Report (DF/R)																		▲
Final Report (F/R)																		▲

Source: JICA Study Team

1.1.6 Objectives of the Final Report

The objectives of Final Report (F/R) are:

- To compile the results of the preliminary design of the Chennai City ITS Project and the design review of the CPRR Project into the report, and
- To update environmental and social consideration procedures for early project implementation.

1.1.7 Components of the Final Report

The subject of this study was originally the CPRR Project and the Chennai City ITS Project; however, the procedure for environmental and social consideration of the CPRR Project was delayed. For this reason, JICA decided to separate the Chennai City ITS Project from the CPRR Project and aimed only for the Chennai City ITS project as the initial goal for the March 2018 Loan Agreement (L/A). For the CPRR project, JICA and HMPD confirmed that the section 1 will be the priority for the ODA loan.

With this, the CPRR Project is compiled as Volume 1 and the Chennai City ITS Project as Volume 2 in this report.

1.1.8 Organization of the Study

JICA entrusted the study to the Consultant, and the Consultant dispatched the JICA Study Team to India, comprised the following 16 members:

JICA Study Team

- | | |
|---------------------------|--|
| 1) Mr. Takayasu Nagai | Team Leader/Road Planning |
| 2) Mr. Ippei Iwamoto | Deputy Team Leader/Road Planning 2/Road Design |
| 3) Mr. Hiroya Totani | ITS Planning/Design 1 |
| 4) Mr. Noboru Kondo | ITS Planning/Design 2 |
| 5) Mr. Akira Magario | Road Structure Design 1 (Geometric, Interchange (IC)) |
| 6) Mr. Seiya Hikino | Road Structure Design 2 (Viaduct, Bridge, Road Structures) |
| 7) Mr. Eiji Wakatsuki | ITS Operation |
| 8) Mr. Hisanari Ushirooka | Traffic Demand Forecast 1 |
| 9) Mr. Yuki Sugiyama | Traffic Demand Forecast 2 |
| 10) Mr. Makoto Yajima | Economic and Financial Analysis |
| 11) Mr. Kiyoshi Dachiku | Road Operation and Maintenance Planning |
| 12) Mr. Kenichi Moritani | Natural Condition Survey |
| 13) Mr. Daisaku Kiyota | Social Environmental Consideration |
| 14) Ms. Natsumi Hara | Environmental Consideration |
| 15) Ms. Kakiko Ide | Social Consideration |
| 16) Mr. Motoki Iwamaru | Construction Planning (Procurement/Cost Estimate) |

The following two agencies are designated to be the counterparts (C/P) in the Government of Tamil Nadu.

C/P Agencies

- 1) Highways and Minor Ports Department (HMPD)
- 2) Tamil Nadu Infrastructure Development Board (TNIDB)

1.2 Record of Meetings

The JICA Study Team had several meetings with various stakeholder organizations of the CPRR Project and the Chennai City ITS Project to carry out confirmation of the current situation and proposal on the prioritized section for the Japanese ODA Loan Project.

HMPD is a C/P agency for the CPRR Project, and TNIDB is a C/P agency for the Chennai City ITS Project.

Kick-off meetings with HMPD and TNIDB are held individually, and the JICA Study Team explained the procedure of the Japanese ODA Loan Projects from the preparatory survey to the signing of L/A, as well as the position of the preparation survey and the Japanese ODA Loan Projects to C/Ps.

1.2.1 Meetings with Concerned Agencies of CPRR

HMPD is conducting the preparation of a DPR of CPRR through STUP Consultants Pvt. Ltd. (hereinafter “STUP”), who is an assignee of HMPD.

A list of the meetings with HMPD and relevant agencies which presents the main agenda and the results of the meetings is shown in Table 1.2.1.

Table 1.2.1 Meeting List with Concerned Agencies of CPRR

Date	Agency	Major Agenda	Results
19 Jul. 2017	HMPD Headquarters (HQ)	Kick-off Meeting a) Explanation of Inception Report b) Proposal of Steering Committee c) Request for DPR d) Organizational Framework e) Progress of Social and Environmental Works and Land Acquisition f) Mode of Implementation g) Request Coordination with the Environmental Impact Assessment (EIA) Expert h) Section Prioritization	• DPRs were not provided.
27 Jul. 2017	HMPD HQ	a) Request for DPR	• DPRs were not provided.
28 Jul. 2017	HMPD HQ	a) Request for DPR	• DPRs were not provided.
2 Aug. 2017	HMPD HQ	a) Request for DPR b) Request for clarification of the environmental clearance (EC) process	• DPRs were not provided.
4 Aug. 2017	HMPD Division Office STUP Consultants	a) Request for DPR b) Request for clarification of the EC process	• Some DPR volumes were provided.
10 Aug. 2017	HMPD HQ STUP Consultants	a) Request for clarification of the EC process	• HMPD commented that EC is not necessary before declaration of state highway (SH). Environmental Impact Assessment (EIA)/ Resettlement Action Plan (RAP) reports were prepared, and public consultations were held in 2014.
22 Aug. 2017	STUP Consultants	a) Request for clarification of the EC process	• STUP commented that EC is not necessary before declaration of SH.
29 Aug. 2017	HMPD HQ	a) Request for clarification of the EC process	
31	Department of	a) Request for clarification of the	• DoE commented that the State Expert

Date	Agency	Major Agenda	Results
Aug. 2017	Environment (DoE), Tamil Nadu	b) EC process Request for clarification of the necessity of EC for CPRR	Appraisal Committee (SEAC) would answer after receipt of the EC application.
6 Sep. 2017	HMPD HQ	a) Request for application of EC for JICA Loan	<ul style="list-style-type: none"> HMPD commented that EC application was submitted and that HMPD would find the application. The L/A Act of 2013 can be applied to CPRR. Public consultations were held in 2014.
7 Sep. 2017	Tamil Nadu State Pollution Control Board (TNSPCB)	a) Request for clarification of the necessity of EC for CPRR	<ul style="list-style-type: none"> TNSPCB commented that CPRR should submit the EC application for the judgement of SEAC.
12 Sep. 2017	Tamil Nadu Road Development Company (TNRDC)	a) Request for clarification of the environmental procedure	<ul style="list-style-type: none"> TNRDC commented that the clearance of the Coastal Regulation Zone (CRZ) has not yet started; that the notice as per Highways Act 15(2) would be completed by March 2018 for Section 1; and that the L/A Act of 2013 for non-title holders would not be applied.
14 Sep. 2017	HMPD Division Office STUP Consultants	a) Request for clarification of Land Acquisition of Section 1 b) Request for confirmation of Land Plan Schedule (LPS) and Field Measurement Book (FMB) of Sections 2,3, and 5.	<ul style="list-style-type: none"> LPS and FMB were shown to the JICA Study Team.
15 Sep. 2017	HMPD Division Office STUP Consultants	a) Request for clarification of the EC process b) Explanation of the social and environmental survey conducted by the JICA Study Team c) Request for the cooperation in the social and environmental survey d) Request for the clarification of the clearance of the Reserved Forest (RF) e) Request for application of the L/A Act of 2013 to Sections 2,3, and 5	<ul style="list-style-type: none"> Application of the EC was provided. A letter related to the RF clearance was provided.
20 Oct. 2017	HMPD HQ	Request for clarification of the EC process	HMPD reported that the application of the EC is about to be submitted.
23 Oct. 2017	State Secretariat (HMPD)	JICA Fact Finding (F/F) (Kick-off Meeting) a) Applicable Law for RAP b) Implementation of Public Consultation c) Environmental Clearance, Disclosure of EIA d) Clearance of RF, CRZ e) Nodal Ministry of the Project Compensation Policy for the Ministry of Road Transport and Highways (MoRTH)	JICA requested HMPD to clarify the discussion agenda in a wrap-up meeting.
24 Oct. 2017	TNRDC STUP Consultants	a) Request for clarification of the EC process b) RAP and Land Acquisition Project Financial Scheme of Section 1	<ul style="list-style-type: none"> The status of RF and CRZ clearance related to environmental clearance was reported by the STUP Consultant. TNRDC agreed to introduce the same procedure with Tamil Nadu Road Sector Project (TNRSP) into the RAP

Date	Agency	Major Agenda	Results
			of Section 1. TNRDC is considering a project financial scheme based on JICA assistance.
	DoE, Tamil Nadu	Request for clarification of the EC process	JICA Study Team confirmed a detailed procedure for EC to DoE.
25 Oct. 2017	HMPD HQ	a) Applicable Law for RAP b) Implementation of Public Consultation c) EC, Disclosure of EIA d) Clearance of RF, CRZ e) Nodal Ministry of the Project f) Compensation Policy for MoRTH g) Detailed Procedure for EC Detailed Procedure for RAP	A detailed discussion regarding the agenda of the kick-off meeting was made between JICA and HMPD.
26 Oct. 2017	HMPD Nodal Officer	a) Detailed Procedure for EC Detailed Procedure for RAP	HMPD agreed on the proposed detailed procedure for EC and RAP by JICA.
27 Oct. 2017	State Secretariat (HMPD)	JICA F/F (Wrap-up meeting) a) EC b) RAP and Land Acquisition c) Line Ministry of the Project d) Compensation Policy for MoRTH e) Implementation Structure in Section 1 Others	<ul style="list-style-type: none"> • HMPD stated that the target time to obtain an EC should be March 2018. • HMPD agreed that the procedures required by the JICA Guidelines for Environmental and Social Considerations should be added to the standard flow of land acquisition as stipulated in the Tamil Nadu Highways Act of 2001. • HMPD will confirm the nodal ministry of the project. • JICA explained that it is not able to provide a loan to a Project implemented under Public-Private Partnership (PPP) mode. HMPD will answer questions about the project financial scheme. • A superintendent engineer is assigned as the nodal person of the project. <p>HMPD agreed that the ITS portion would be implemented ahead by separating loan packages.</p>
7 Nov. 2017	HMPD HQ	a) EC Implementation Structure in Section 1	<ul style="list-style-type: none"> • HMPD informed that EC application was uploaded to the online site. <p>HMPD informed that the implementation structure in Section 1 is not yet decided in HMPD.</p>
17 Nov. 2017	HMPD HQ	a) Line Ministry and Agreement with the National Highway Authority of India (NHAI) b) Implementation Structure in Section 1 c) EC, CRZ, RF d) RAP and Land Acquisition Provision of Data for DPR Review Works by JICA	<ul style="list-style-type: none"> • Chief Engineer (CE) will confirm the line ministry and the agreement with NHAI to the secretary by 21 November 2017. • HMPD informed that the implementation structure in Section 1 is not yet decided in HMPD. • HMPD informed that presentation to the State Environmental Impact Assessment Authority (SEIAA) about the EC application is scheduled in December. <p>• HMPD agreed on the proposed detailed</p>

Date	Agency	Major Agenda	Results
			<p>procedure for EC and RAP based on TNRSP by JICA.</p> <p>HMPD agreed to provide the requested DPR data to the JICA Study Team.</p>
8 Dec. 2017	HMPD HQ	<p>a) Line Ministry and Agreement with NHAI</p> <p>b) Implementation Structure in Section 1</p> <p>c) EC, CRZ, RF</p> <p>d) RAP and Land Acquisition</p> <p>Provision of Data for DPR Review Works by JICA</p>	<ul style="list-style-type: none"> • HMPD will visit MoRTH on 27 December 2017 for follow-up on the issue. • HMPD informed that the implementation structure in Section 1 is not yet decided in HMPD. CE will confirm with the secretary. • HMPD informed that the presentation to SEIAA about EC application is scheduled in February. • HMPD informed that the special team for RAP will be formulated by January. <p>HMPD agreed to provide the requested DPR data to the JICA Study Team.</p>
21 Dec. 2017	HMPD HQ	<p>a) Line Ministry and Agreement with NHAI</p> <p>b) Implementation Structure in Section 1</p> <p>c) EC, CRZ, RF</p> <p>d) RAP and Land Acquisition</p> <p>Provision of Data for DPR Review Works by JICA</p>	<ul style="list-style-type: none"> • HMPD will visit MoRTH on 27 December 2017 for follow-up on the issue. • HMPD informed that the implementation structure in Section 1 is not yet decided in HMPD. CE will confirm with the secretary. • HMPD informed that the presentation to SEIAA about EC application is scheduled in February. • HMPD informed that the special team for RAP will be formulated by January. <p>HMPD informed that the rate analysis, geological survey report, hydrological report, and river cross sections will not be shared considering the fact that the reports and designs have not yet been approved.</p>
7 Feb. 2018	DOE, HMPD	<p>a) Importance of CPRR</p> <p>b) EIA Schedule for the Implementation of the Project of Section 1 as a Japanese ODA Loan Project</p> <p>c) Progress of each Procedure</p> <ul style="list-style-type: none"> - CRZ Clearance - Forest Clearance - Environmental Clearance 	<p>JICA explained the following:</p> <ul style="list-style-type: none"> • The purpose and importance of the CPRR construction project. • Section 1 will be selected as the priority for the Japanese ODA Loan project. • EC must be approved by May 2018 because the disclosure of the EIA report that acquired EC is required 120 days before L/A.
23 Apr. 2018	HMPD	<p>JICA F/F-2 (Kick-Off Meeting)</p> <p>a) Schedule and Procedure for the Signing of L/A</p> <p>b) Schedule and Procedure of FF-2 Agenda</p> <p>c) Financial Procedure for the Japanese ODA Loan Project</p> <p>d) Aid Memoire and Minutes</p>	<ul style="list-style-type: none"> • JICA explained the schedule and the outline of the loan financing examination.
24 Apr.	HMPD, TNRDC	a) Implementation Schedule	<ul style="list-style-type: none"> • JICA explained the implementation

Date	Agency	Major Agenda	Results
2018		b) Cost Estimate	<p>schedule and the cost estimate of the project.</p> <ul style="list-style-type: none"> • HMPD informed that the following updates for the current DPR is still on-going: <ul style="list-style-type: none"> a) Extension of a major bridge (MJB) up to Ch.2+500 b) Shifting the end point of Section-1 from Ch. 20+900 to Ch. 21+506 (The whole NH5 IC will be included in Section 1) c) Introduce toll gates in two locations d) Introduce a traffic control center
25 Apr. 2018	HMPD	a) EIA/RAP	<ul style="list-style-type: none"> • HMPD shared the progress of the EIA and RAP preparation.
26 Apr. 2018	TNRDC	<ul style="list-style-type: none"> a) Implementation Organization b) Project Evaluation Criteria 	<ul style="list-style-type: none"> • TNRDC shared the organizational chart of the TNRDC Project Implementation Team. • TNRDC suggested to apply the following in the Project Evaluation Criteria: <ul style="list-style-type: none"> - Annual average daily traffic (AADT) (vehicle/day, passenger car unit (PCU)/day) - Freight flow (ton/year) - Required driving time through the typical route in CMA (minute) • To consider each road leading to the Ennore Port as a toll road in the condition of the Traffic Demand Forecast. <ul style="list-style-type: none"> - ORR (under TNRDC): scheduled to be charged in half a year - Chennai Bypass (under NHAI) to be run as a toll road - Port access section in Kattupalli Road (under Ennore Port) scheduled to be charged after 2 years - IRR scheduled to be charged • To consider 25 years after completion as a project evaluation period in the economic internal rate of return (EIRR) calculation.
26 Apr. 2018	HMPD, TNRDC	<p>JICA F/F-2 (Wrap-up Meeting)</p> <ul style="list-style-type: none"> a) FF-2 Overview b) Aid Memoire 	<ul style="list-style-type: none"> • Discussed issues in F/F-2 are confirmed. • HMPD suggested to study the possibility of shortening the project implementation process.
21 May 2018	TNRDC	<p>JICA F/F-3 (Kick-Off Meeting)</p> <ul style="list-style-type: none"> a) Implementaion Schedule, Cost 	<ul style="list-style-type: none"> • JICA explained revised implementation schedule, cost

Date	Agency	Major Agenda	Results
		Estimate, IRR, Project Effectiveness Index b) Issue on social environment consideration of TPP Link Road	estimate, IRR, and project effectiveness index. • It was discussed how to respond to the strong opposition from southern part of TPP Link Road.
22 May 2018	HMPD, TNRDC	a) Issue on social environment consideration of TPP Link Road b) Draft agreement on the document on environmental and social considerations (EIA, RAP)	• It was discussed how to respond to the strong opposition from southern part of TPP Link Road. • It was confirmed the contents pertaining to the draft agreement on environmental and social considerations (EIA, RAP).
23 May 2018	HMPD, TNRDC	Issue on social environment consideration of TPP Link Road	• It was discussed how to respond to the strong opposition from southern part of TPP Link Road.
24 May 2018	HMPD, TNRDC	JICA F/F-3 (Wrap-Up Meeting) a) Time Bound Action Plan c) Implementaion Schedule, Cost Estimate, IRR, Project Effectiveness Index b) Issue on social environment consideration of TPP Link Road	• It was confirmed status of Time Bound Action Plan (NHAI agreement for the revenue loss, updated RAP, etc.). • Shortening of implementation schedule, revised cost estimate•IRR• Project Effectiveness Index are explained and agreed by HMPD. • Measures for improving strong opposition from southern part of TPP Link Road was discussed and agreed.
9 July 2018	HMPD, TNRDC	JICA F/F-4 (Kick-Off Meeting) a) Time Bound Action Plan b) Schedule for L/A c) Implementation schedule d) Realignment of TPP Link Road	• It was confirmed status of Time Bound Action Plan (Official request, EC, updated RAP, etc.). • It was explained signing of loan agreement is scheduled after predge and 120 days of EIA disclosure. • Revised implementation schedule is explained. • HMPD made explanation of design matters and environmental and social considerations concerning the realignment of TPP Link Road.
11 July 2018	HMPD, TNRDC	a) Cost estimate b) Realignment of TPP Link Road	• Detaile of the revised cost estimate was explained. • JICA explained HMPD that the necessary matters concerning design and environmental and social considerations for inclusion of the realignment of TPP Link Road in Phase-1.
12 July 2018	TNRDC	a) Realignment of TPP Link Road	• TNRDC made a detailed explanation of design matters concerning the realignment of TPP Link Road including question and answer session with JST. JST discussed about scope of the realignment of TPP Link Road with TNRDC.
13 July	HMPD	JICA F/F-4 (Wrap-Up Meeting)	• JICA informed HMPD that the

Date	Agency	Major Agenda	Results
2018		a) Realignment of TPP Link Road b) Time Bound Action Plan	necessary matters concerning design and environmental and social considerations for inclusion of the realignment of TPP Link Road in Phase-1 is generally satisfied. However, there are partial insufficiency and JICA explained to carry forward the judgment to their headquarter. <ul style="list-style-type: none"> • JICA reminded HMPD to take prompt action for Time Bound Action Plan (Official request, Clarification of Nodal Ministry, EC, updated RAP, etc.).

Source: JICA Study Team

1.2.2 Meetings with Concerned Agencies of CPRR ITS

‘Data Collection Survey for Chennai Metropolitan Region ITS’ which was completed in March 2017 proposed two ITS components for CPRR, i.e., (i) Highway Traffic Management System (HTMS) and (ii) Toll Management System (TMS).

The meetings for the Japanese ODA Loan Project were held with the following agencies related to these ITS components. The major agenda and results of each meeting are shown below. The minutes of the meetings are presented in Appendix 1.

Table 1.2.2 Meeting List with Concerned Agencies of CPRR ITS

Date	Agency	Major Agenda	Results
18 Apr. 2018	HMPD	a) Request for clarification of the Project Implementation Unit (PIU) establishment b) Request for clarification of the implementation structure for the Japanese ODA Loan Project	<ul style="list-style-type: none"> • It was confirmed that the establishment of PIU had already been requested to the Governemnt of Tamil Nadu and that it will be approved soon. • It was confirmed that PIU will be established under HMPD and its key role is to coordinate organizations below. • Responsible organization for each section of CPRR was confirmed as follows: Section 1: TNRDC Section 2, 3, and 5: HMPD Section 4: TNRIDC • As shown above, TNRDC will implement Section 1 of the project with responsibility for procurement, installation, construction, and O&M. • It was confirmed that the Chennai Smart City Limited (CSCL) will be involved in the implementation of the project, and will be taking advisory roles.
24 Apr. 2018	TNRDC	a) Request for clarification of the basic matters for toll road section b) Request for clarification of the basic matters for O&M	The following basic matters for the toll road section (Section 1) were confirmed by mutual agreement: <ul style="list-style-type: none"> • Toll tariff rules: distance-based • Toll plaza: two toll plazas • Toll plaza lane: 5x5 lanes • Lane designation: one electronic toll

Date	Agency	Major Agenda	Results
			<p>collection (ETC) dedicated lane, three lanes for both manual collection and ETC, and one free lane for emergency vehicles, motorcycles, and auto-rickshaws.</p> <ul style="list-style-type: none"> • ETC: FASTag by NHAI • Toll area crossing facility for toll collectors: bridge type <p>The following matters for O&M were confirmed by mutual agreement:</p> <ul style="list-style-type: none"> • TMS O&M Contractor: TNRDC will procure. • HTMS O&M Contractor: system integrator will be in charge of O&M after the development of the system. • O&M period: 3 years • Defects liability period: 1 year
25 Apr. 2018	TNRDC	<ul style="list-style-type: none"> a) Concept of toll fare table b) Request for clarification of the O&M structure 	<ul style="list-style-type: none"> • It was agreed that the concept of the toll fare table based on the rules of toll tariff for Section 1 will be calculated by distance. • O&M structures for HTMS and TMS were confirmed by mutual agreement.
25 Apr. 2018	HMPD, TNRDC, CSCL	<ul style="list-style-type: none"> a) ITS components b) O&M organization 	<ul style="list-style-type: none"> • It takes time until the final decision of the toll system adopted for CPRR. Facility planning is subject to introduce distance-based charges. • Two toll gates (main line barrier type) are introduced, one on the main line (west side) and another on TPP Link Road. • • Not to introduce a toll gate between the main road and service roads (free entry/exit). • • The level of toll is to follow the Toll Act.
2 May 2018	TNRDC	<ul style="list-style-type: none"> a) Section 1: Request for clarification of cooperation with external organizations related to O&M b) Request for clarification of toll plazas on ORR 	<ul style="list-style-type: none"> • Cooperation with traffic police, fire authorities, and medical institutions (including response to natural disasters) for road operation after opening of Section 1 was confirmed. • A condition of the site for toll plazas to be constructed on ORR was confirmed.

Source: JICA Study Team

1.2.3 Meetings with Other Organizations

A meeting with Japan External Trade Organization (JETRO) was held on 26 July 2017 to make an interview about the requested and desired road projects by Japanese-related organizations in Tamil Nadu State.

CHAPTER 2 PRESENT CONDITION AND CIRCUMSTANCES OF THE PROJECT

2.1 Outline of the Chennai Peripheral Ring Road (CPRR) Development Project

2.1.1 Objectives of the Project

The objective of the project is to address the rapidly increasing road traffic demand in the Chennai Metropolitan Area (CMA) by constructing CPRR and developing Intelligent Transport System (ITS) facilities, thereby contributing to the sustainable economic growth in CMA. The Project is expected to improve the connectivity in and around Chennai City by:

- Formulating the Radial-Ring Road Network in CMA in collaboration with other ring roads such as the Inner Ring Road (IRR), the Chennai Bypass, and the Outer Ring Road (ORR) in order to provide alternate routes for traffic as well as to improve redundancy of the road network,
- Providing a direct access to Ennore Port and Kattupalli Port from industrial clusters located in suburban areas of CMA in order to accelerate industrial and economic growth, and
- Improving efficiency in the use of the road network by providing ITS facilities such as a traffic information system and a traffic management system for CPRR and the central area of CMA.

2.1.2 Past Studies on the Project

CPRR was conceptualized to provide better connectivity around the city catering to future traffic requirements, and to provide efficient commercial transportation by enhancing port connectivity. This road will facilitate container movement from the southern districts to Ennore Port and Kattupalli Port.

Section 1 of CPRR, the section from Ennore to Thatchur, used to be recognized as Northern Port Access Road (NPAR). The Feasibility Study Report for NPAR was originally prepared by the National Highways Authority of India (NHAI) in 2008, and NHAI handed over the NPAR project to the Government of Tamil Nadu (GoTN). Then, according to Government Order (Ms) No. 94, dated 23 April 2012 and concerning the Industries Department, Tamil Nadu Road Development Company (TNRDC) is appointed as the Managing Associate and the Highways and Minor Ports Department (HMPD) is appointed as the Monitoring Department for the NPAR Project. Subsequently, the land alignment details were prepared by TNRDC and were handed over to the State Industries Promotion Corporation of Tamil Nadu (SIPCOT) to undertake the development. Furthermore, according to Government Order (Ms) No. 69, dated 18 April 2013 and concerning HMPD, M/s. CDM Smith is entrusted the work of updating the Detailed Feasibility Report.

Subsequently, NPAR was taken as Section 1 of CPRR, and the Detailed Project Report (DPR) for CPRR was prepared by HMPD entrusting the work to M/s. STUP Consultants together with other sections (i.e., Sections 2 to 5). The concept of CPRR is to form a new ring road with a radius of 40 to 60 km in the outskirts of Chennai City, connecting Mahabalipuram to Ennore Port.

According to the DPR, the alignment of CPRR was approved by the Steering Committee and was finalized by the Principal Secretary of HMPD on 9 July 2014.

The DPR consists of the various volumes listed in Table 2.1.1. The JICA Study Team requested HMPD to provide all volumes of the DPR; however, some volumes were not available because they were under the process of obtaining concurrence from other concerned departments such as the Public Works Department (PWD) and the Water Resource Department (WRD).

Although some parts of the DPR such as “Design Report (Structures)” and “Rate Analysis” were not available at the time of review, these were finally provided after February 2018. As such, the JICA Study Team obtained all documents except “Technical Specifications”. However, further modification and updating by HMPD are still ongoing, even after receiving additional parts of the DPR; thus, there are inconsistencies among the series of the provided report.

Table 2.1.1 Composition of DPR

Vol.	Report Title	Version/Date	Availability
I	Main Report	Unknown	Provided by JICA
II-A	Design Report (Highways)	Ver.R0, 9 Jan. 2017	Aug. 2017
II-B	Design Report (Structures/Box Culvert)	Unknown (cover shows Aug. 2016)	Feb. 2018
II-C	Design Report (Structures/Minor Bridge)	Unknown (cover shows Aug. 2016)	Feb. 2018
II-D	Design Report (Structures/Major Bridge)	Unknown (cover shows Aug. 2016)	Feb. 2018
II-E	Design Report (Structures/Underpass)	Unknown (cover shows Jul. 2016)	Feb. 2018
II-F	Design Report (Structures/Interchange)	Unknown (cover shows Nov. 2016)	Feb. 2018
II-G	Design Report (Structures/Sec-1 Link Road)	Unknown (cover shows Sep. 2016)	Feb. 2018
II-H	Design Report (Structures/ROB)	Unknown (cover shows Aug. 2016)	Feb. 2018
III	EIA & Management Plan	Unknown	Provided by JICA
IV	Social Impact Assessment & RAP	Unknown	Provided by JICA
V	Technical Specifications	-	Not Available
VI	Rate Analysis	Ver.R0, 9 Jan. 2017	Feb. 2018
VII	Bill of Quantities	Ver.R0, 9 Jan. 2017	Nov. 2017
VIII	Cost Estimate	Ver.R0, 9 Jan. 2017	Aug. 2017
IX-A	Drawing (Highways)	Unknown	Aug. 2017
IX-B	Drawing (Structures/ Drainage)	Unknown	Aug. 2017
IX-C	Drawing (Structures/Bridges)	Unknown	Aug. 2017
IX-D	Drawing (Structures/underpass)	Unknown	Aug. 2017
IX-E	Drawing (Structures/Interchange)	Unknown	Aug. 2017


Source: DPR Main Report P1-6 and the JICA Study Team

2.2 Present Condition and Identified Issues of Roads and Traffic in the Study Area

2.2.1 Present Condition and Issues of Road Network

Roads in CMA have been developed following the pattern of the Radial-Ring Road Network as shown in Figure 2.2.1. Major radial roads which originate at the center of Chennai City are NH4 (towards Mumbai via Bengaluru), NH5 (towards Kolkata), NH45 (towards Madurai), and NH205 (towards Tirupathi). With respect to ring roads, the IRR was first proposed as a city bypass road in 1968, and construction started in the 1980s from its central arm connecting NH45 to NH5. Subsequently, the northern and southern arms were developed. Then, the second ring road, the Chennai Bypass, was opened in 2008. However, since the urbanized area of Chennai is rapidly expanding, these two ring roads were incorporated into the built-up area. Therefore, the third ring road, or the ORR, is currently being developed, and the CPRR was even proposed to enhance the road network for further expansion of the metropolitan area and increase of traffic demand.

Table 2.2.1 and Table 2.2.2 show the statistics on the road network in Tamil Nadu State. There are highways and roads of 62,468 km in length, and a large part of National Highways (NH) and State Highways (SH) have double or more lanes (99% for NH and 97% for SH).



Source: JICA Study Team based on OpenStreetMap

Figure 2.2.1 Road Network in CMA

Table 2.2.1 Existing Roads in Tamil Nadu State

Classification of Road	Length (km)
National Highways (NH wing-1985 & NHAI-3009)	4,994
State Highways	12,095
Major District Roads	11,628
Other District Roads & Sugarcane Roads	33,751
Total	62,468

Source Highway Department

Table 2.2.2 Details of Roads in Tamil Nadu State

Unit: km

No.	Category wise	Single Lane	Intermediate Lane	Double Lane	Multi Lane	Total
1	National Highways	12	26	2,731	2,225	4,994
2	State Highways	56	350	9,795	1,894	12,095
3	Major District Roads	422	7,663	3,367	176	11,628
4	Other District Roads	29,287	3,507	893	64	33,751
Total		29,777	11,546	16,786	4,359	62,468

Source Highway Department

The issues of the road network in CMA are summarized as follows:

(1) Concentration of Traffic in the Core Area of Chennai

The incompleteness of the road network development in the pattern of the Radial-Ring Road Network in CMA (construction of ring roads has not caught up with the increase in traffic demand) is causing serious traffic congestion in major roads towards the city center. Traffic is concentrated particularly in the core area of Chennai. It was found that more than 200,000 vehicles per day are traversing NH45 and IRR, including motorbikes. On the other hand, the traffic volume on the same road but in the suburbs is less than 70,000 vehicles per day. Similar characteristics were found in other major roads. As a result, the travel speed of traffic towards Chennai City in the morning peak hour becomes less than 30 km/hr in the city center.

It is therefore required to disperse incoming traffic before it comes into the city center.

(2) High Proportion of Large Vehicles

A high ratio of large vehicles is found in the suburban section of NH5, NH4, and NH45. This indicates that these roads are used by a large number of commercial vehicles, such as heavy lorries and trailers, to access the industrial areas and the Kattupalli/Ennore/Chennai Ports. The high proportion of slow-moving large vehicles causes a decrease in the overall travel speed of traffic.

A large number of large vehicles are frequently passing through small villages in the suburbs. Thus, there are a lot of pedestrians and motorcycles in the villages that are always facing high risks of traffic accidents.

Hence, a new link connecting industrial areas in the suburban area to ports shall be developed to ease the load of existing highways.

(3) Expansion of Built-up Areas

Rapid economic growth and increase in the population of CMA is encouraging the urbanized built-up area to expand, thereby changing the classification of IRR and Chennai Bypass from bypass roads to urban highways. The ORR which is currently being constructed will be, once it opens, the newest ring road with

the largest radius of 20 to 30 km; however, urban development is approaching such current outskirts.


The necessity of the development of further ring roads has been recognized to enhance the road network as well as improve redundancy of the network.

2.2.2 Present Condition and Issues of Traffic in the Study Area

(1) Traffic Signal Shortage

There are many intersections without traffic signals in Chennai. At such intersections, barricades and roundabouts are adopted as alternative facilities. However, such facilities cause problems such as traffic congestion and increase in travel time. In addition, pedestrian safety is threatened because crossing at intersections without signals involves great danger.

In short, the lack of signals causes traffic congestion and prolonged travel time. Therefore, it is necessary to secure efficient traffic operation and pedestrian safety by installing traffic signals.



Source: JICA Study Team

Figure 2.2.2 Issues due to Traffic Signal Shortage

1) Reduction of Travel Speed by Barricades

Barricades are installed to reduce the travel speed of vehicles at some crosswalks and intersections. They are installed even in trunk roads with three lanes per direction. However, high speed vehicles suddenly need to change lanes to avoid barricades. Thus, it is assumed that barricades lower travel speeds but also induce accidents by sudden lane changing.



Source: JICA Study Team

Figure 2.2.3 Installation of Barricades


2) Crossing Pedestrian

There are crosswalks on trunk roads with over six lanes, but no signals are installed in most cases. Therefore, pedestrians are forced to cross the road amidst heavy traffic which causes accidents.

There are some sections where barricades are installed in front of crosswalks to decrease the speeds of vehicles and to shorten the crossing distance. Regardless, pedestrians are still in danger.

In cases where a school is located along a trunk road, a large number of students cross the road in the morning and evening as many of them use public transport. Even when a pedestrian bridge is installed near the school, students still tend to cross the road. It is assumed that the reason for this is the long distance between the pedestrian bridge and the bus stop.

For these reasons, it is said that there is a high risk of traffic accidents around schools.




Source: JICA Study Team

Figure 2.2.4 Crossing Pedestrians

(2) Processing Capacity and Operation at the Chennai Port

As shown in Figure 2.2.5, due to the small processing capacity and the inefficient operation of the Chennai Port, large vehicles flow into community roads and form a long queue on roads.

Since improvements to the operation of Chennai Port and the utilization of Ennore Port are in progress, some developments to the situation are expected.




Source: JICA Study Team

Figure 2.2.5 Issues due to Small Processing Capacity and Inefficient Operation at the Chennai Port

1) Influence of Large Vehicles on Community Roads

The yard of Chennai Port is narrow, and the capacity to handle containers is limited. Container cargo landing from a ship must be immediately taken out of the yard. Therefore, there are container freight stations around the port to compensate for the shortage of port capacity (Figure 2.2.6).

However, there are cases wherein container freight stations are located in the suburbs, where trunk roads are not constructed, so there are sections where large vehicles pass through community roads (Figure 2.2.7).



Source: JICA Study Team

Figure 2.2.6 Location of Container Freight Stations




Source: JICA Study Team

Figure 2.2.7 Traffic around Chennai Port

2) On-Street Parking due to Lack of Standby Space for Large Vehicles

On the road around the container freight station, large vehicles are waiting for loading and unloading on the service road and the main road as shown in Figure 2.2.8. These vehicles cause a decrease in traffic capacity and worsened traffic congestion.



Source: JICA Study Team

Figure 2.2.8 Street Parking of the Large Vehicles around the Container Freight Station

3) Track Queue

There are 3,000 to 4,000 container vehicles that enter and exit the port each day. The entry and exit of trucks to Chennai Port is limited to nighttime only, and there is only one entrance on the north side of the port. Therefore, trucks that cannot enter the terminal form a long queue on the access road to the port. These vehicles occupy a lane, cause traffic congestion, and increase travel time.

In addition, according to the interview survey conducted by the JICA Study Team, the average waiting time of these large vehicles is 30 to 40 hours, and the burden on the truck driver is also high.



Source: JICA Study Team

Figure 2.2.9 Waiting Queue of Large Vehicles


(3) Issues due to the Road Structure/Operation

Although the ORR is partially open to public, there are problems of connection with the main radial roads. The junction at the connecting point with NH4 and NH45 is still under construction. Therefore, the ORR is not effectively utilized.

In Chennai, there are many sections where sidewalks and parking lots are not provided. In such sections, the risk of traffic accidents involving pedestrians is high, as parked vehicles occupy a lane, cause traffic jams, and increase travel time.

In addition, at many intersections of trunk roads, vehicles travelling on service roads cannot go straight or turn right, but must take a detour instead.

These road structure and operational problems lead to traffic congestion, increase in travel time, and fatal accidents. Therefore, it is required to improve the efficiency of traffic flow and pedestrian safety by reviewing the road structure and operations.




Source: JICA Study Team

Figure 2.2.10 Issues due to Road Structure and Operation

1) Undeveloped Junction of ORR

Although the ORR is partially open to public, it is not effectively used because the traffic volume of ORR is only 10% of the IRR. The reasons are as follows:

- The connection between NH4 and ORR is still under construction, and vehicles are forced to take a detour.
- The connection between NH45 and ORR is under construction, and vehicles are forced to pass through a narrow community road.



Source: JICA Study Team

Figure 2.2.11 Undeveloped Junction in ORR

2) Undeveloped Sidewalk

There are many sections where sidewalks are not provided, and pedestrians are forced to walk on the carriageway. Also, pedestrians precariously walk on the inner side of the road to avoid parked vehicles and stalls that are on the road.

It is necessary to construct sidewalks to separate pedestrians and vehicles and to secure a safe walking space.



Source: JICA Study Team

Figure 2.2.12 Undeveloped Sidewalk

3) Misuse of Sidewalks

As shown in Figure 2.2.13, there are many areas where sidewalks are occupied by parked vehicles or are obstructed by trees. In such situations, pedestrians are forced to walk on the carriageway.

In order for sidewalks to serve their proper function, it is necessary to install motorcycle parking lots and to prohibit planting of trees on sidewalks.




Source: JICA Study Team

Figure 2.2.13 Misuse of Sidewalks

4) Lanes Occupied by Parked Vehicles

As parking lots are not installed, many vehicles park on carriageways. There are some sections where one lane is covered by sand and cannot be recognized as a lane because it is not used for traffic as shown in Figure 2.2.14. Also, trucks occupy roads near the port and the industrial parks.

It is necessary to install parking lots in order to accommodate the parked and waiting vehicles on the road and maximize the road capacity.




Source: JICA Study Team

Figure 2.2.14 Lanes Occupied by Parked Vehicles

5) Inefficient Operations of Intersection

At signal intersections on arterial roads such as NH 45, as shown in the figure below, the traffic on the intersecting road cannot cross the arterial road. In this case, traffic flow is inefficient because vehicles on the service road are forced to make a detour.



Source: JICA Study Team

Figure 2.2.15 Inefficient Operation of Intersection

If straight and right turns are prohibited, vehicles are forced to make a U-turn then occupy one lane, which also reduces traffic capacity and decreases travel speed.




Source: JICA Study Team

Figure 2.2.16 U-Turn Point

(4) Deterioration of Pavement


There are sections where roads are depressed due to deterioration of pavement. Pavement deterioration lowers travel speed, making overtaking difficult. Especially in Chennai, where many industrial parks are located in suburbs, there is a large volume of heavy vehicles in the access roads, and depression of roads are

also evident. Pavement deterioration also causes logistics problems such as damage in handling and transport of trucks and increase of logistics time. Therefore, it is necessary to improve road pavements to allow smooth flow of traffic.



Source: JICA Study Team

Figure 2.2.17 Problems due to Deterioration of Pavement



Source: JICA Study Team


Figure 2.2.18 Road Collapse due to Deterioration of Pavement

(5) Other Issues

1) Street Parking of Large Vehicles around the Industrial Park

At the CPRR (Section 4) around the Oragadam Industrial Park, there are situations where large vehicles and corporate buses occupy the road as shown in Figure 2.2.19.

In the future, if the connecting point between the CPRR (Section 4) and the arterial road (NH4, NH45) is improved, traffic volume is expected to increase. Reduction of traffic capacity caused by on-street parking of large vehicles may cause traffic congestion.



Source: JICA Study Team

Figure 2.2.19 Large Vehicles around the Industrial Park

2) Buses Occupying the Road

Covered bus stops are installed around the railway station in Chennai. Many buses stop at designated locations, but there are also some that stop and load and unload passengers along carriageways. This becomes a factor of the decline in traffic capacity. If there is no designated stop, some buses occupy one lane, which also causes traffic congestion near the railway stations.

Even if bus bays are installed at the bus stops along the main roads, passengers wait for buses on the bus bay itself. It is assumed that passengers take such action to ensure that they get on the bus. Because passengers occupy the bus bay, the bus is forced to stop in the carriageway.



Source: JICA Study Team

Figure 2.2.20 Buses Occupying the Road

3) Unloading on Roads

Because there is no parking lot for freight cars, loading and unloading on roads become an obstacle to other vehicles.



Source: JICA Study Team

Figure 2.2.21 Occupation of Roads by Loading and Unloading on Roads

4) Decrease in Travel Speed due to Wildlife Crossing

On suburban roads, there are many instances where vehicles wait for animals to cross, causing traffic slowdown.



Source: JICA Study Team

Figure 2.2.22 Animal Crossing the Road

5) Reduction of Lane due to Sidewalk Stalls

There are many areas where one lane is occupied by people and vehicles that stop by sidewalk stalls. As a result, traffic capacity decreases and traffic congestion occurs. Also, since pedestrians cannot pass on the sidewalk, they are forced to walk on the roadway, which increases the risk of meeting traffic accidents.



Source: JICA Study Team

Figure 2.2.23 Reduction of Lane due to Sidewalk Stalls

6) Reduction of Lane due to Parked Auto-Rickshaw

Many auto-rickshaws are on standby in busy areas such as hotels and shopping malls. A lane is occupied by auto-rickshaws on standby which decreases traffic capacity and speed.



Source: JICA Study Team

Figure 2.2.24 Standby Auto-Rickshaw

7) Congestion due to Wedding Ceremonies and Other Events

When there are events such as wedding ceremonies, many vehicles of guests gather and queue at the event venue, thus disrupting the flow of traffic.

2.2.3 Present Condition and Issues of Intelligent Transport System (ITS) Facilities in the Study Area

The present condition of the entire ITS in Chennai is described in the Final Report of the Data Collection Survey for Chennai Metropolitan Region ITS which was completed in March 2017. This clause reports the latest conditions of ITS updated in this study, which are directly related to the ITS components of the Japanese ODA Loan Project.

(1) City Bus System of Metropolitan Transport Corporation (MTC)

The City Bus System is composed of the following components:

- Bus Tracking System
- Passenger Information System
- Electronic Ticket Management System

The Bus Tracking System and Passenger Information System are systematically linked to function (the Electronic Ticket Management System functions independently). Both systems are shown in Figure 2.2.25.




Figure 2.2.25 Images of Bus Tracking System and Passenger Information System

1) Bus Tracking System

This system is used for bus management, showing the current locations of city buses on the video wall at the command control center of the bus operator. The bus location information is collected from the GPS device installed on the bus. It was found that the Bus Tracking System has not yet been introduced.

2) Passenger Information System

This system provides information on bus operations (e.g., arrival/departure time) through Variable Message Sign Boards (VMS) at bus stops, websites, mobile applications, etc. The information is generated based on the bus location data obtained by the Bus Tracking System. It was found that this system has not yet been introduced.

3) Electronic Ticket Management System

This system is used for the collection of fare payment made by passengers and for management of revenue. It was found that this system has already been introduced. Approximately 8,000 handy ticketing devices were procured. The device is currently used only for ticket issuing, not for IC card usage. The hardware is compatible with both Type A and Felica. When the software is installed, this device can be used for both types of IC cards.

(2) Traffic Management System of Chennai Traffic Police (CTP)

The current Traffic Management System of CTP was confirmed as follows:

1) Command Control Center

The Command Control Center has been established in the CTP building, and limited functions are in operation.

2) Call Center in Command Control Center

Approximately 20 operators are stationed in the Command Control Center for 24 hours a day, handling emergency calls, inquiries, claims, etc.

3) Traffic Signal System and CCTV Camera

Traffic signals have been installed at 385 junctions in the city. The current signals are of the fixed pattern type, not the signal coordination type. The signal patterns are adjusted or changed by the police officers as necessary. There are many signals that are not working or are turned off. CCTV cameras have also been installed at the junctions. A typical image of the existing traffic signal together with a CCTV is shown in Figure 2.2.26.



Source: JICA Study Team

Figure 2.2.26 Existing Traffic Signal and CCTV Camera at Junction

4) Variable Message Sign Board (VMS)

VMS have been installed at 53 junctions in the city. The existing VMS provides static messages such as warnings on traffic rules, not dynamic traffic information. Two different languages, i.e. English and Tamil, are shown. A typical image of the VMS is shown in Figure 2.2.27.



Source: JICA Study Team

Figure 2.2.27 VMS and Displayed Message

5) E-Challan System

E-Challan System is used for traffic violation enforcement. The handy terminals deployed to the police officers issue the enforcement ticket for the fine imposed on the traffic violation at the site. The data inputted on the handy terminal is collected at the Command Control Center, and the system manages the traffic violation record. E-Challan System has already been introduced to the CTP, and approximately 400 handy terminals are in use as of now.

6) Advance Traveler Information System (ATIS)

The ATIS provides traffic information to road users as pre-trip information. A prototype system was developed by the Indian Institute of Technology (IIT)-Madras, and the pilot was carried out in a relatively

limited area, i.e., on the roads surrounding the campus of IIT Madras. The project is funded by the Government of India, and related government organizations such as CTP are aimed to utilize the system.

(3) Chennai Metro Rail Limited (CMRL)

Smart cards which can be used only for Chennai Metro have been introduced. There are two card types, i.e., Type-A (Mifare) and Felica. Multi-type card readers which can read and write both types of cards have been introduced at the gates of Chennai Metro stations. The ticketing and recharging terminals for both types of cards are also available in these stations.

The clearinghouse has already been developed in Chennai Metro and was designed to handle a maximum of 32 operators, taking into consideration the introduction of a common mobility card in Chennai in the future. It functions as a management system of the cards as well. The memory of both types of the cards has also been designed to accommodate the same number of operators. A card initializing process is required upon issuance. Simple card issuance terminals for the initialization, which are processed by manual operation not automatic, are used because there are still a relatively small number of cards used for the metro.

2.3 Organizations Related to Road and ITS Development

Organizations related to road and ITS development are described in this section. The correlation of the organizations is presented in Appendix-2.

2.3.1 Highways and Minor Ports Department (HMPD)

HMPD manages SHs and minor ports in Tamil Nadu State. CPRR is supposed to be an SH once it opens, but it is not declared at this moment; thus, the implementation agency for the construction of CPRR will be HMPD. Even NHs inside Chennai City are under the jurisdiction of HMPD. Details of HMPD are described in Section 6.2 of this report.


2.3.2 Tamil Nadu Infrastructure Development Board (TNIDB)

TNIDB is a nodal agency for planning and coordination of infrastructure development in Tamil Nadu State. It was established to facilitate the infrastructure development projects under the Ministry of Finance according to the Tamil Nadu Infrastructure Development Act 2012. It formulates, prioritizes, and evaluates the projects and coordinates with the related departments to acquire the state budgets and financial support from the central government. It also prepares feasibility study reports and detailed project reports and monitors the projects.

TNIDB is involved in the projects undertaken by the government (public project) and through Public Private Partnership (PPP project). The act stipulates that TNIDB is involved in the public project with more than INR 500 crores of the project cost and the PPP project with more than INR 10 crores.

The chair person is the Chief Minister and the vice-chair person is the Finance Minister. Under the chair person, the executive committee is formed. The executive committee is chaired by Chief Secretary. It consists of 10 concerned departments with officials and experts. The chief executive officer (CEO) under the executive committee deals with the day-to-day duties of TNIDB. Under the CEO, there are a core in-house team, external consultants and experts.

The organization structure is shown below.



Source: Edited by JICA Study Team based on TNIDB's website

Figure 2.3.1 Organization Structure of Tamil Nadu Infrastructure Development Board

2.3.3 Chennai Metropolitan Development Authority (CMDA)

CMDA is a planning agency for Chennai Metropolitan Area including Chennai District, part of Kanchipuram District and part of Thiruvallur District. CMDA prepares plans such as master plan and new town development plan. The plan is implemented by the individual government agencies in charge. Minister of Housing and Urban Development represents CMDA and there are following members for decision making.

Table 2.3.1 Members of Chennai Metropolitan Development Authority

Honorable Minister for Housing and Urban Development	Chairman
Vice- Chairman, CMDA	Vice Chairman
Member-Secretary, CMDA	Member
Secretary to Government H&UD, Finance, Industries, Transport	Member
Commissioner, Corporation of Chennai	Member
Managing Director CMWSS Board	Member
Director, Town & Country Planning	Member
Chief Urban Planner, CMDA	Member
Chief Engineer, Highways & Rural Works Department	Member
Chief Architect to Government	Member
Joint Director, Town & Country Planning	Member
Chairman, Tamil Nadu Housing Board	Member
Chairman Tamil Nadu Slum Clearance Board	Member
Member of the State Legislative Assembly	Member

Source: Summarized by JICA Study Team based on the Information on Website of CMDA


There are following units under the members

- Area Plans Unit
- Area Development Unit
- Master Plan Unit
- Road and Rail Unit
- Enforcement Cell (dealing with permission and authorization such as issuance of completion certificate of project, etc.)
- Construction Wing and General Unit.

2.3.4 Chennai Traffic Police (CTP)

CTP under Chennai Police manages traffic. They are responsible for regulating traffic and enforcing traffic rules in Chennai District. The Chennai Police is under the Ministry of Home, Prohibition and Excise and is headed by the Commissioner of Police. The Chennai Traffic Police is headed by the Additional Commissioner of Police. The jurisdiction area is divided into four (4) regions; North, South, East and West and each region is represented by Deputy Commissioner. There are also a Planning Division of Traffic Management under Chennai Traffic Police.

The organization structure is shown below.



* Addl.COP: Additional Commissioner of Police, JC: Joint Commissioner, DC: Deputy Commissioner, AC: Additional Commissioner

Source: Edited by JICA Study Team based on Website of Tamil Nadu Police Department


Figure 2.3.2 Organization Structure of Chennai Traffic Police

2.3.5 Greater Chennai Corporation (GCC)

GCC is an autonomous body of Chennai, a designated city by the Government Ordinance in Tamil Nadu State. GCC consists of administrative agencies with 200 members headed by the mayor and the City Council. The mayor and each City Council member are chosen by direct election, and the deputy mayor is elected among the City Council members by votation. The mayor and the deputy mayor preside over several Standing Committees. The Commissioner represents the administrative agency and controls each administrative service department such as Education, Insurance, and Health.


GCC has jurisdiction over the development and maintenance of city roads with a total length of approximately 5,560 km, excluding NH and SH in Chennai and roadside facilities such as bus stops, street lights, road signs, markings, drainage, sidewalks, and skywalks. The ownership of these facilities belongs to GCC. As for traffic signals, CTP carries out the maintenance, and the ownership belongs to them.

The organization structure is shown below.



Source: Edited by the JICA Study Team based on website of Greater Corporation of Chennai

Figure 2.3.3 Organizational Structure of the Executive Committee of Greater Corporation of Chennai



Source: Edited by the JICA Study Team based on website on Greater Corporation of Chennai

Figure 2.3.4 Organizational Structure of the Administrative Body of Greater Corporation of Chennai

2.3.6 Chennai Smart City Limited (CSCL)

CSCL is a Special Purpose Vehicle (SPV) for the Smart City Mission in Chennai. The roles of CSCL are planning, implementing, and managing the projects of Smart City Mission, as well as operating and maintaining the introduced facilities and systems.


It was established in 2016 according to the Smart City Guidelines issued by the Government of India in June 2015. The coverage domain of CSCL includes several sectors as follows:

(The following are the descriptions of the objectives under the Smart City Mission which are extracted from the Smart City Guidelines.)

- *Adequate water supply,*
- *Assuring electricity supply,*
- *Sanitation including solid waste management,*
- *Efficient urban mobility and public transport,*
- *Affordable housing, especially for poor,*
- *Robust IT connectivity and digitalization,*
- *Good governance, especially e-Governance and citizen participation,*
- *Sustainable environment,*
- *Safety and security of citizens, particularly women, children and the elderly, and*
- *Health and education.*

Source: Smart City Guideline 2015, Government of India

Figure 2.3.5 shows the organization structure of CSCL.



Source: Edited by the JICA Study Team based on interviews with CSCL and related materials

Figure 2.3.5 Organization Structure of Chennai Smart City Limited

CSCL was established under the GCC. The Commissioner of GCC serves as the Chairperson, the Deputy Commissioner of GCC serves as the Managing Director, the CEO represents the CSCL, and the Chief Financial Officer (CFO) and Company Secretary constitute the CSCL as members.

For decision making, there are Board Members above the Chairperson who are in charge of the approval of projects. The Board Members are the secretaries of the related government organizations such as GCC, Tamil Nadu Finance and Infrastructure Development Corporation (TUFIDCO), etc. There is a High-powered Committee above the Board Members for the final approval of the project. It is constituted by the related government organizations.

For the implementation of the project, GCC established a Dedicated Special Project Team which consists of 20 persons. They provide support on a regular basis for CSCL. Other related organizations such as Chennai Metropolitan Water Supply and Sewerage Board (CMWSSB), Tamil Nadu Generation and Distribution Corporation (TANGEDCO), etc. are nominated nodal persons as supporting team. The Project Management Consultant (PMC) takes management roles for the projects of the Smart City Mission such as preparing the Detailed Project Report (DPR) and overseeing the consultants hired for the individual projects. The current PMC is Pricewaterhouse Coopers Limited.

There are 20 cities in India that were selected for the first round of the Smart City Mission. The Government of India created the Smart City Fund and INR 200 crores were delivered to the individual cities. The Smart City Fund Account was opened for the states included in the Smart City Mission.

2.3.7 Tamil Nadu Road Development Company (TNRDC)

TNRDC is a government company responsible for the implementation of tolled SHs which have been established under the HMPD. It raises funds, constructs, operates, and maintains. It is a joint venture corporation of Tamil Nadu Industrial Development Corporation Ltd (TIDCO) and Tidel Park Ltd. (TIDEL). TIDCO and TIDEL are 100% government-owned companies and have equal share of TNRDC.

TNRDC was appointed by Government Order No. 94, Industries Department, dated 23 April 2012 as Managing Associate for the Northern Port Access Road Project which is currently recognized as Section 1 of CPRR. In this connection, TNRDC is currently on preparation work for the project including land acquisition and resettlement procedure for Section 1.

Details of TNRDC are described in Section 5.2.4 of this report.

2.3.8 Tamil Nadu Road Infrastructure Development Corporation (TNRIDC)


TNRIDC was established in 2005 as a non-profitable organization to implement, upgrade, and maintain road infrastructure in the State of Tamil Nadu. The Oragadam Industrial Corridor Project and the four-laning project of the Madurai Ring Road are being implemented by TNRIDC.

Details of TNRIDC are described in Section 5.2.5 of this report.

2.3.9 Metropolitan Transport Corporation (MTC)

MTC is a public city bus operator in CMA. It is a government agency under the Ministry of Transport. Metropolitan Transport Corporation offers almost 48,000 daily bus services on 842 bus routes. They own approximately 4,000 buses, and approximately 3,700 buses are operated. There are 32 bus depots, 71 bus terminals, and 151 major bus stops. There are also a number of small bus stops across Chennai. They carry approximately 4.5 million daily passengers. They operate several different types of buses with different fare categories such as ordinary, express deluxe, express, and Volvo AC services.

Metropolitan Transport Corporation is headed by the Board of Director. There are several departments and wings, such as Administration and Operation, and there are about 24,480 employees. The organizational structure is shown below.



Source: Edited by the JICA Study Team based on the website of GCC

Figure 2.3.6 Organization Structure of Metropolitan Transport Corporation

2.3.10 Tamil Nadu State Data Center

Tamil Nadu State Data Center is an ISO-certified data center of GoTN. It has been established under the National e-Governance Initiative of GoI. It offers single-point services for e-governance of Tamil Nadu State such as providing server rooms equipped with a cooling system, electric supply system by UPS, generators, data communication network, operation/maintenance of servers, user applications, etc. for computer services of various departments of the state government.


Tamil Nadu State Wide Area Network is established in Tamil Nadu State and is a major backbone network used for Tamil Nadu State Data Center. Bharat Sanchar Nigam Limited communication network is also used. A security policy for data protection is applied such as a firewall. Under the security policy, two backup data centers have been prepared, one in Bharat Sanchar Nigam Limited data center in Chennai and the other in Pune for disaster measure. Another backup center is planned in Tiruchy in Tamil Nadu State.

The basic services offered by Tamil Nadu State Data Center are to provide the server spaces in the protected environment as above and operation/maintenance of servers for each department. In some cases, depending on the service agreement with the department, user applications are also prepared/procured, hosted on the server, and maintained by Tamil Nadu State Data Center. The examples of the applications

hosted include the services for tax collection/management, government’s revenue management, land registrations, medical records of public hospital, etc. The servers of the Chennai Metro System are also located in Tamil Nadu State Data Center.

The Electronics Corporation of Tamil Nadu, established under the Government of Tamil Nadu, is an implementing agency that manages Tamil Nadu State Data Center and offers these services.

The figure below shows the organization structure of Electronic Corporation of Tamil Nadu and Tamil Nadu State Data Center.



*TRG: Technical Resource Group, ITP&D: Information Technology Promotion and Development,

GM: General Manager, TNSDC: Tamil Nadu State Data Center, TNSWAN: Tamil Nadu State Wide Area Network

Source: Edited by the JICA Study Team based on details of ELCOT website

Figure 2.3.7 Organization Structure of Electronic Corporation of Tamil Nadu and Tamil Nadu State Data Center

2.3.11 Chennai Metro Rail

Chennai Metro Rail Limited is an SPV for the construction and operation of the Chennai Metro. It was formed in March 2007 by the Government of India and the Government of Tamil Nadu with equal equity.

The Chennai Metro Rail is a rapid transit system in Chennai. The project is divided into two phases. Phase 1 is under construction and partially in operation. There are two corridors in Phase 1, totaling 45 km in length. About 55% of the Phase 1 corridor is underground and the rest of the structures are elevated. The following corridors are located along the arterial roads in the core area of Chennai City: Anna Salai (Mount Road or NH45), E.V. R Periyar Salai (P.H Road or NH4), and Nehru Salai (100 Ft Road or Inner Ring Road). The first stretch began its operation in June 2015. It is along Nehru Salai from Koyambedu to Alandur with 10 stations of approximately 10 km in length.

2.4 Development Plans and Projects Related to CPRR

2.4.1 Superior Development Plans

(1) National Urban Transport Policy (NUTP)

NUTP is a high-level urban transport policy in India. It was formulated by the Government of India, specifically the Ministry of Road Transport and Highways in 2006. The urban transport planning and implementation which are under the jurisdiction of the state government are to be carried out under the NUTP. The prime focuses are given to the following policies:

- To develop urban mass transport systems in the metropolises in India
- To develop urban transport infrastructure harmonized with urban development plans
- To implement various measures to shift the demand to the public transport
- To utilize ITS to solve issues of urban transport
- To develop road spaces for pedestrian and parking space
- To develop the bicycle pass
- To set Unified Metropolitan Transport Authority (UMTA) for cities with more than 40 lakhs (4 million) population.

(2) Comprehensive Traffic and Transportation Study

The Comprehensive Traffic and Transportation Study has been prepared by Chennai Metropolitan Development Authority in 2010. It envisages the vision and sets out the target and strategies for the target year of 2026 as follows:

1) Vision Envisaged by the Comprehensive Traffic and Transportation Study

The Comprehensive Traffic and Transportation Study states the vision under the framework of the second Chennai Master Plan and Vision Tamil Nadu 2026 as shown below:

“Provide safe, efficient, affordable and modern transport choices to people and businesses integrating economic, land use and transport concerns of Chennai Metropolitan Area to be fully prepared to take on the transport challenges of Chennai - the Megapolis.”

2) Goals

The following indicators of modal share for the target year of 2026 are set as goals of the Comprehensive Traffic and Transportation Study.

Table 2.4.1 Target Figure of Modal Share in 2026 against 2008

Index	2008	Goal (2026)
Public Transport	41%	70%
IPT (auto, taxi, etc.)	11%	8%
Private Transport	48%	22%

Source: Summarized by the JICA Study Team based on CTTS, Chennai

Note1: The above table excludes non-motorized transport.

Note2: Construction of Mass Rail Transit, Metro Rail, Mono Rail, Light Rail Transit, Bus Rapid Transit based on plan is required, so that the public transport share rises to 70%. In addition, it is also important that parking lots, transfer stations, traffic information systems, etc. adjacent to the transport hub such as a bus stop or a railroad station is constructed. Besides, as measures of the policies, improvement of user convenience by introducing the common card and securing a regular schedule of trains are required. Most city buses, which are citizen's main transportation, are time-worn vehicles having low comfort. Thus, it is recommended that new vehicles are introduced to improve the comfort of the user. It is necessary for these measures to be carried out totally so that public transport share rises to 70%.

3) Strategy

To realize the vision and to achieve the goals stated above, the infrastructure development plan in phases (short, mid, and long term) is proposed as shown in the table below:

Table 2.4.2 Proposed Infrastructure Development: Short, Mid and Long Term

Term	Proposed Development
Short Term (2010-2015)	Pedestrian facilities (footpaths), bicycle network, traffic management, parking regulation, signal improvement, junction improvements, road markings, and signage
Medium Term (2016-2021)	Pedestrian subways, multi-level parking facilities, grade separators, flyover and underpass, traffic management centers, and skywalks
Long Term (2022-2026)	MRTS, Metro, monorail, LRT, suburban rail and BRT, intermodal stations, truck terminals, intercity bus terminals, elevated roads, freight corridors, missing roadway links, and major road widening

Source: Summarized by the JICA Study Team based on CTTS, Chennai

The cost estimates for the proposed developments are shown in the table below:

Table 2.4.3 Estimated Investment Cost

Term	Estimated Investment Cost
Short Term (2010-2015)	INR 52,689 crores
Medium Term (2016-2021)	INR 21,899 crores
Long Term (2022-2026)	INR 7,532 crores
Total	INR 82,120 crores

Source: Summarized by the JICA Study Team based on CTTS, Chennai

2.4.2 Urban Development Plans and Projects

(1) Development Plan for Chennai Metropolitan Area, 2006

Outline

The plan was issued in 2006 by Jawaharlal Nehru National Urban Renewal Mission (JNNURM), a massive city modernization scheme launched by the Government of India under the Ministry of Urban Development. The plan consists of 1) Introduction, 2) Demography, 3) Economy, 4) Land Use and Structure of Chennai, 5) Municipal Infrastructure, 6) Environment and Disaster Management, 7) Traffic and Transportation, 8) Urban Basic Services for the Poor, 9) Social Facilities, 10) Municipal Finances, 11) Vision and Goals and Strategies, and 12) Capital Investment Plan and Financing Strategy.

Objectives

The main objectives of the development plan are to have a strategy for the sustainable and planned growth of the city with appropriate policy and strategic interventions. The plan outlines the strategic policy and investment interventions to achieve the formulated vision for Chennai and comprised the following:

- Assessment of the existing situation with regard to demographic and economic growth, infrastructure services, municipal finances, etc.;
- Identification of gaps in service delivery including the issues faced by the urban poor;
- Vision and goal formulation for each sector to achieve the objectives enunciated above; and
- Formulation of a city investment plan with appropriate financing strategies for the identified interventions.

In addition, the plan also focuses on the reforms to be carried out at the state and local level in consonance with the vision and strategic plan outlined to sustain the planned interventions.

Population Projection

Population projections were carried out for the CMA based on the past trends. It is estimated that the CMA would increase to 12.6 million by 2026, of which Chennai City alone would account for 5.8 million.

Table 2.4.4 Population Projection

Unit: million

Description	Actual	Projection				
	2001	2006	2011	2016	2021	2026
CMA	7.041	7.896	8.871	9.966	11.197	12.582
Chennai City	4.343	4.628	4.950	5.239	5.540	5.856

Source: Development Plan for Chennai Metropolitan Area, 2006

Economic Growth

The plan did not make explicit projections of the Gross Regional Domestic Products (GRDP). Instead, the plan made the employment projection in CMA. It was worked out based on the existing and envisaged economic developments and past trends.

Table 2.4.5 Employment Projection in CMA

Unit: million

Description	Year			
	2011	2016	2021	2026
Male Willing to Work	2.791	3.225	3.725	4.298
Female Willing to Work	0.837	1.064	1.341	1.719
Total	3.628	4.289	5.065	6.017
Additional Jobs to Be Created	1.009	1.670	2.447	3.399

Source: Development Plan for Chennai Metropolitan Area, 2006

Water Demand

The plan projected the water demand in CMA for the future development of a water supply system.

Table 2.4.6 Total Water Demand in CMA

Unit: million liters per day

Description	Year			
	2011	2016	2021	2026
Resident Population	1,165	1,284	1,431	1,606
Office and Commercial	349	385	429	482
Industry	116	128	143	160
Total	1,630	1,797	2,003	2,248

Source: Development Plan for Chennai Metropolitan Area, 2006

The goals of the water supply system in the Chennai City area are as follows:

Table 2.4.7 Goals of Water Supply System in Chennai City Area

Description	Year		
	2011	2016	2021
Network Coverage for General Households	100%	100%	100%
Network Coverage for Urban Slum Households	100%	100%	100%
Per capita Supply	150 lpcd	150 lpcd	150 lpcd
Hours of Supply	6 hours/day	18 hours/day	24 hours/day
24 Hours and 7 Days' Supply	4 zones	8 zones	All 16 zones
Quality of Water	Safe and good	Safe and good	Safe and good
Non-Revenue Water	20%	15%	12%
O&M Cost Recovery	100%	100%	100%
Collection Efficiency	100%	100%	100%
Customer Satisfaction	Good	Good	Good

lpcd: liter per capita per day

Source: Development Plan for Chennai Metropolitan Area, 2006

Goals of Sewerage

The goals of the sewerage system in the Chennai City area are as follows:

Table 2.4.8 Goals of Sewerage System in Chennai City Area

Description	Year		
	2011	2016	2021
Coverage (Access)	100%	100%	100%
Treatment and Disposal	100%	100%	100%
Recycle and Reuse	25%	40%	50%
Customer Satisfaction	Good	Good	Good

Source: Development Plan for Chennai Metropolitan Area, 2006

Goals of Solid Waste Management

The goals of the solid waste management system in CMA are as follows:

Table 2.4.9 Goals of Solid Waste Management System in CMA

Description	Year		
	2011	2016	2021
Collection within the City	100%	100%	100%
Collection within the Urban Local Bodies	75%	100%	100%
Collection in Other Urban Agglomeration Areas	50%	100%	100%
Door to Door Collection	50%	75%	100%
Source Segregation	50%	75%	100%
Scientific Disposal	80%	100%	100%
Waste to Energy Generation	40%	70%	100%
Cost Recovery of O&M	50%	75%	100%

Source: Development Plan for Chennai Metropolitan Area, 2006

Transport

The plan projected the daily trips by public transport in CMA.

Table 2.4.10 Daily Trip Projection in CMA

Unit: million

Description		Actual	Projection				
		2001	2006	2011	2016	2021	2026
Population		7.041	7.896	8.871	9.966	11.197	12.582
Daily Per Capita Trips		1.30	1.34	1.50	1.60	1.60	1.65
Total Daily Person Trips		9.153	10.581	13.307	15.939	17.917	20.760
Modal Split (%)	Private	60.00	55.00	45.00	40.00	35.00	30.00
	Public	40.00	45.00	55.00	60.00	65.00	70.00
Total Daily Person Trips by Public Transport		3.661	4.761	7.319	9.564	11.646	14.532
By Rail (%)		12.00	16.00	25.00	30.00	35.00	40.00
By Road (%)		88.00	84.00	75.00	70.00	65.00	60.00
Daily Trips by Rail		0.439	0.762	1.830	2.869	4.076	5.813
Daily Trips by Road		3.222	3.999	5.489	6.694	7.570	8.719

Source: Development Plan for Chennai Metropolitan Area, 2006

The goals of the transportation system in CMA are as follows:

Table 2.4.11 Goals of Transportation in CMA

Description	Year		
	2011	2016	2021
Road Network as % of Total Area	12%	15%	15%
Share of Public Transport	45%	55%	75%
Rail Transport as share of Total Public Transport	10%	30%	40%
Average Speed (km/h)	20	30	35
Sidewalk Length to Total Road Length	50%	75%	95%
Reduction of Road Accidents	25%	50%	70%

Source: Development Plan for Chennai Metropolitan Area, 2006

(2) Second Master Plan for Chennai Metropolitan Area 2026, 2008

Outline

The plan was issued in 2008 by Chennai Metropolitan Development Authority. The plan consists of three volumes. Volume I contains 1) Review of the First Master Plan, 2) Demography, 3) Economy, 4) Traffic and Transportation, 5) Shelter, 6) Infrastructure, 7) Social Facilities, 8) Solid Waste Management, 9) Macro Drainage System in CMA, 10) Disaster Management, 11) Environment, 12) Special Strategy and Land Use Planning, 13) Development Regulations, and 14) Monitoring and Implementation of Master Plan. Volume II contains the details of Development Regulations. Volume III contains the Sectoral Background. The City Development Plan by JNNURM was also taken into consideration.

Objectives

The plan is the successor of the First Master Plan, which was issued in 1976 and has a target year of 2001. The master plan proposes (a) the manner in which the land in the planning area shall be used; (b) the allotment or reservation of land for residential, commercial, industrial and agricultural purposes, as well as for parks, playfields, and open spaces; (c) the provision for national highways, arterial roads, ring roads, major streets, lines of communication including railways, airports and canals; (d) the provision for regulating the zone, location, height, number of stories, and size of buildings and other structures, as well as the size of yards and other open spaces and the use of buildings, structures, and land; and, (e) the stages by which the master plan shall be carried out.

Population Projection

Population projections were carried out for CMA based on past trends. The following assumptions were made:

- (1) The declining trend in the growth rate will also continue in the future years
- (2) Past growth rates, existing density, potential for development, area available for development, accessibility to public transport system (especially the rail system), and the proximity to employment generating centers could be the basis for working out future projections and assignments.

The projection results are the same with the Development Plan for Chennai Metropolitan Area, 2006, as shown below:

Table 2.4.12 Population Projection

Unit: million

Description	Actual	Projection					
	2001	2006	2011	2016	2021	2026	Density*
Chennai City	4.343	4.628	4.950	5.239	5.540	5.856	333
Municipalities	1.581	1.852	2.175	2.560	3.020	3.569	149
Town Panchayats	0.386	0.473	0.589	0.741	0.945	1.222	78
Village Panchayats	0.731	0.870	1.059	1.296	1.599	1.988	32
CMA (Total)	7.041	7.896	8.871	9.966	11.197	12.582	105

*: Gross density (persons/ha) in 2026

Source: Second Master Plan for Chennai Metropolitan Area 2026, 2008

Economic Growth

The plan did not make explicit projections of the Gross Regional Domestic Products (GRDP), but made employment projections in CMA instead. It was worked out based on the existing and envisaged economic developments and past trends. The projection results are the same with the Development Plan for Chennai Metropolitan Area, 2006.

Projection of Travel Demand

The travel demands were projected based on the increase in per capita trips. The per capita trip that had been 1.44 in 2005 was projected to 1.60 by 2016 and 1.65 by 2026. The projection results are the same with the Development Plan for Chennai Metropolitan Area, 2006.

Water Demand

The future water demand at the rate of 150 liter per capita per day (lpcd) for the city and 100 lpcd for the rest of CMA were estimated. The estimates are the same with the Development Plan for Chennai Metropolitan Area, 2006.

Land Use Plan

The existing Land Use Plan for 2006 and the proposed Land Use Plan for 2026 are given in the table below.

Table 2.4.13 Land Use

Description	Chennai City				Rest of CMA			
	2006		2026		2006		2026	
	Extent (ha)	Share	Extent (ha)	Share	Extent (ha)	Share	Extent (ha)	Share
Residential ¹⁾	9,523	54.25%	8,343	47.36%	22,877	21.87%	45,594	45.01%
Commercial	1,245	7.09%	714	4.05%	390	0.37%	880	0.87%
Industrial ²⁾	908	5.17%	823	4.67%	6,563	6.28%	10,690	10.55%
Institutional	3,243	18.48%	2,869	16.28%	3,144	3.01%	3,889	3.84%
Open Space and Recreation	366	2.09%	1,001	5.68%	200	0.19%	393	0.39%
Agricultural	99	0.56%	0	0.00%	12,470	11.92%	7,296	7.20%
Non-Urban	82	0.47%	113	0.64%	2,433	2.33%	2,333	2.30%
Others ^{3),4)}	2,087	11.89%	3,755	21.31%	56,507	54.03%	30,223	29.84%
Total	17,553	100.00%	17,618	100.00%	104,584	100.00%	101,298	100.00%

Notes 1): Data in 2026 contains "Mixed Residential Use"

2): Data in 2026 contains "Special and Hazardous Industrial Use"

3): Data in 2006 consists of "Vacant, Forest, Hills, Low Lying, Water Bodies, etc."

4): Data in 2026 consists of "Urbanizable, Roads, Water Bodies, Hills, Redhills Catchments Area, etc."

Source: Second Master Plan for Chennai Metropolitan Area 2026, 2008

(3) Vision Tamil Nadu 2023 (Strategic Plan for Infrastructure Development in Tamil Nadu), 2012

Outline

The plan was issued in 2012 by Tamil Nadu State with the assistance of ADB. The plan consists of three phases. Phase I contains vision formulation, namely: 1) Executive Summary, 2) Key Outcomes of the Vision, 3) Growth Strategies, and 4) Sectoral Investment Plans. Phase II contains detailed sector reports and project profiles. Phase III contains implementation road maps.

Objectives

The main objectives are 1) formulating a vision and growth strategy for the Tamil Nadu State, with sector-specific substrategies, 2) identifying thrust areas for growth and bottlenecks in such areas, and 3) identifying critical projects in important sectors including power, roads, port development, agriculture, irrigation, housing, health, higher education, urban development, public transport, industry, and tourism.

Population Projection

The plan does not clearly indicate the population projection. It just expects 15% increase over the next 11 years (1.28% in annual average). The goal of per capita gross domestic product (GDP) was set based on this population growth rate.

Economic Growth

Since one of the objectives is to formulate a growth strategy, the plan set the target of GRDP growth rates with GRDP shares for economic sectors. In addition, per capita income will increase from USD 1,625 in 2010 to USD 10,000 in 2023, which means that India will become an upper middle income nation in the world.

Table 2.4.14 GRDP Share by Sector

Sector	GDRP Share			Average Annual Growth Rate
	2004/05	2010/11	2022/23	
Primary	12.0%	12.6%	7.0%	5.1%
Manufacturing	20.0%	16.6%	22.0%	13.8%
Non-manufacturing	11.0%	9.2%	8.0%	9.5%
Services	57.0%	61.6%	63.0%	11.1%
Total	100.0%	100.0%	100.0%	10.9%

Source: Vision Tamil Nadu 2023 (Strategic Plan for Infrastructure Development in Tamil Nadu), 2012

Investment in Urban Infrastructure

The investment was focused on the following items with the purpose of developing state-of-the-art infrastructure, both physical and social, ensuring seamless connectivity between cities and rest of the state:

- development of Chennai City into a megapolis,
- development of ten world class cities,
- rehabilitation of 1.5 million families living in slums,
- universal access to 24 hours and 7 days water supply and sanitation services, and
- access to mass transit systems for efficient urban transport.

The summary of investment plan is shown below:

Table 2.4.15 Summary of Investment in Urban Infrastructure

Unit: billion INR

Project	Amount
Chennai City development	500
Urban development for the rest of Tamil Nadu	500
Development of ten world class cities (urban facilities estimated INR 100 billion per city)	1,000
Housing including housing for economically weaker sections	750
Total	2,750

Source: Vision Tamil Nadu 2023 (Strategic Plan for Infrastructure Development in Tamil Nadu), 2012

(4) Ponneri Industrial Node Development Plan in Comprehensive Integrated Master Plan for Chennai Bengaluru Industrial Corridor, 2015

Outline

The Ponneri Industrial Node Development Plan was formulated in 2015 under the Comprehensive Integrated Master Plan for Chennai Bengaluru Industrial Corridor (CBIC) with the assistance of JICA. The plan consists of 1) Executive Summary, 2) Introduction, 3) Overview of Thiruvallur District and Ponneri Industrial Node, 4) Node Development Vision, 5) Industrial Development Analysis, 6) Land Use Planning for Ponneri Node, 7) Infrastructure Development Plan, 8) Economic Cost Benefit Assessment, 9) Financial Assessment and Planning, 10) Environmental and Social Considerations for Node Development Plan, 11) Institutional & Financing Framework, 12) Investment Environment Improvement, and 13) Way Forward.

Objectives

The plan was formulated in consultation with related stakeholders with the following objectives:

- To prepare a Comprehensive Regional Perspective Plan for the Chennai-Bengaluru Industrial Corridor Region, along with the developing strategy for transforming the region into a globally competitive investment destination,
- To identify suitable nodes to be taken up for industrial development within the project influence area (States of Karnataka, Andhra Pradesh, and Tamil Nadu) and prepare a Master Plan and a Development Plan for at least two selected industrial nodes (amongst the various nodes identified under the study), and
- To identify components of infrastructure that need to be created and corrected to enable better functioning of the economy and industry and to enable development of the above nodes as a starting point to promote manufacturing and growth in the CBIC region.

Population Projection

The future population of the node, consisting of the working population and residential population, was projected in conjunction with the projected land offtake.

Table 2.4.16 Projected Population in Ponneri Node

	2016–2019	2020–2024	2025–
Working Population	90,665	373,475	888,074
Residential Population	0	0	400,000

Source: Ponneri Industrial Node Development Plan in Comprehensive Integrated Master Plan for Chennai Bengaluru Industrial Corridor, 2015

Economic Growth

Real GDP growth rate in India was projected as follows:

Table 2.4.17 Real GDP Growth Rate in India

Description	Actual		Projection		
	1980–1999	2000–2012	2013–2020	2021–2030	2030–
Real GDP Growth Rate (p.a.)	5.6%	6.9%	6.3%	6.9%	6.9%
Ratio to Previous Period	-	1.23	0.91	1.10	1.00

Source: Ponneri Industrial Node Development Plan in Comprehensive Integrated Master Plan for Chennai Bengaluru Industrial Corridor, 2015

Land Use Plan

Based on the development framework and the development concepts, the required area for each land use category in the priority area and the whole node area were estimated.

Table 2.4.18 Land Use Plan

Unit: ha

	2016-2019	2020-2024	2025-	Total
Industrial Area	399	622	2,885	3,906
Residential Area	0	0	1,054	1,054
Existing Settlement	0	0	885	885
Infrastructure (Road and Plant)	199	28	310	536
Water Body and Green Area	83	129	440	652
Others	319	36	403	757
Total	999	814	5,976	7,789
Existing Port Area				1,100
Grand Total				8,889

Source: Ponneri Industrial Node Development Plan in Comprehensive Integrated Master Plan for Chennai Bengaluru Industrial Corridor, 2015

Road Development Plan

Based on the proposed internal node development plan and the identified projects, the implementation plan for internal node development was proposed as shown below:

Table 2.4.19 Road Development Plan

Unit: million INR

	2016	2017	2018	2019	2020	2021	2022	2023	2024-30	2031-33
Internal Road Works	109	147	133	0	0	6	32	41	0	186
Inter Section Works	0	4	2	0	0	0	0	0	0	0
River Bridge Works	13	13	13	7	7	7	7	7	0	0
Flyover Bridge Works	32	26	23	2	2	2	2	0	0	0
Road Facilities	146	157	168	0	0	0	0	8	0	0
Internal Public Transport Facilities	0	1	22	0	0	0	1	22	0	0
Major River Bridge Works	17	17	17	0	0	0	0	0	0	0
Total	317	365	378	9	9	15	42	78	0	186

Note: Figures in 2024-30 and 2031-33 are the same every year.

Source: Ponneri Industrial Node Development Plan in Comprehensive Integrated Master Plan for Chennai Bengaluru Industrial Corridor, 2015

Water Supply

The domestic and industrial water demand in Ponneri Node was estimated as shown in the table below:

Table 2.4.20 Water Demand of Ponneri Node

Unit: million liters per day

Description	2018	2022	2033
Domestic Water			
Residential People Excluding Employees	0	0	38.6
Employees from the Inside of Node	0	0	15.4
Employees from the Outside of Node	3.4	10.4	34.8
Total	3.4	10.4	88.8
Including Water Loss	3.8	11.8	98.7
Industrial Water	16.2	41.4	158.6
Including Water Loss	18.0	46.0	176.2
Grand Total	21.8	57.8	274.9

Note: Water loss was assumed at 15% of water supply.

Source: Ponneri Industrial Node Development Plan in Comprehensive Integrated Master Plan for Chennai Bengaluru Industrial Corridor, 2015

The summary of the cost estimate of the construction are presented in the table below:

Table 2.4.21 Construction Cost of Water Infrastructures

Unit: million INR

Item	2016–2018	2019–2021	2022–2033	Total
Portable Water Supply Works	665	521	12,863	14,049
Non-portable Water Supply Works	2,878	1,725	8,278	12,880
Domestic Sewerage Works	337	256	2,521	3,114
Treated Sewerage and Industrial Effluent Collection Works	671	595	4,427	5,693
Drainage Works	492	781	3,208	4,480
Total	5,042	3,878	31,296	40,216

Source: Ponneri Industrial Node Development Plan in Comprehensive Integrated Master Plan for Chennai Bengaluru Industrial Corridor, 2015

The summary of the cost estimate of the O&M are presented in the table below:

Table 2.4.22 O&M Cost of Water Infrastructures

Unit: million INR

Item	2016–2018	2019–2021	2022–2033	Total
Portable Water Supply Works	69	268	5,172	5,509
Non-portable Water Supply Works	311	1,120	6,611	8,042
Domestic Sewerage Works	48	149	1,485	1,682
Treated Sewerage and Industrial Effluent Collection Works	89	324	2,786	3,199
Drainage Works	74	318	2,254	2,646
Total	591	2,180	18,307	21,078

Source: Ponneri Industrial Node Development Plan in Comprehensive Integrated Master Plan for Chennai Bengaluru Industrial Corridor, 2015

Solid Waste Management

Summary of cost estimate are presented in the table below.

Table 2.4.23 Cost of Solid Waste Management Infrastructure

Unit: million INR

Item	2014–2018	2019–2023	2024–2033	Total
Construction Cost				
Hazardous Waste Infrastructure	0.0	316.3	1178.0	1494.3
Municipal Solid Waste Infrastructure	31.1	34.1	819.8	885.0
O&M Cost				
Hazardous Waste Infrastructure	0.0	36.0	2017.7	2053.7
Municipal Solid Waste Infrastructure	10.6	34.6	797.7	842.9

Source: Ponneri Industrial Node Development Plan in Comprehensive Integrated Master Plan for Chennai Bengaluru Industrial Corridor, 2015

2.4.3 Road Development Plans and Projects Other than CPRR

(1) Outer Ring Road (ORR)

The ORR is being constructed in phases. The section of Phase 1 of ORR that has been opened is from Vandalur on NH45 to Nemilinchery on NH205. The section of Phase 2 is under construction from Nemilinchery on NH205 to Minjur on NH5. The project is being implemented by TNRDC which was formed under HMPD.

(2) Widening of NH205 Including Construction of Thiruvallur Bypass

The National Highways Authority of India (NHAI) is widening the Thiruninravur-Thiruttani-Tirupati Section of NH205 to four lanes, and construction is in progress. As part of the project, NHAI is constructing a bypass for Thiruvallur town. The bypass starts at KM 43/800 of NH205 on western side of Thiruvallur, crosses SH57 at KM 44/500 on the northern side of Thiruvallur, ends at KM 50/600 of NH 205, starts again at KM 50/800, and ends at KM 52/000 of NH205.

(3) Widening of Section of SH57 from Singaperumalkoil to Sriperumbudur

A section of SH57 from Singaperumalkoil to Sriperumbudur is ongoing widening to six lanes with service roads by TNRDC. The SH57 crossing the railway lines with manned level crossing in Singaperumalkoil for which the Project Wing of the Highways Department of GoTN is constructing a Road over Bridge (ROB).

(4) Widening of Old Mahabalipuram Road (OMR) (Phase-II)

The IT Corridor Project, is an initiative of GoTN to develop OMR as a world-class facility. TNRDC has incorporated an SPV called 'IT Expressway Ltd' (ITEL) to develop the IT Corridor Project. The entire stretch will be built as six-lane road with service roads and footpaths on both sides. The project is being implemented in two phases – Phase-I (20 km) between Madhya Kailash Temple Junction and Siruseri, and Phase-II (26 km) between Siruseri and Mahabalipuram. As the improvement of Phase-I is completed, ITEL is now planning to widen Phase-II to a 6-lane carriageway with service roads on both sides. As part of Phase-II, two bypasses are proposed for Kelambakkam and Thiruporur.

(5) Widening of East Coast Road (ECR) (Phase-I)

The stretch of ECR from KM 22/300 (Akkarai) to KM 135/500 (Puducherry) is maintained as a toll road by TNRDC. Recognizing the rapid recreational, commercial, and residential developments along the ECR and its influencing areas, TNRDC has decided to upgrade the road as a dual two-lane facility with improved geometry in two phases. Phase-I spans from KM 22/300 to KM 55/800 (Mahabalipuram), and Phase-II is from KM 55/800 to KM 135/500. Phase-I is under construction.

(6) Improvement of Grid Roads along ORR

The State Highways Department and CMDA have jointly identified 18 road networks to be developed on either side of Chennai ORR. The DPR for the development of grid roads along the ORR is under preparation.

(7) Construction of Elevated Road along OMR

Due to enormous growth in employment at IT companies and other commercial and major institutional development that has taken place along OMR, Phase-I is experiencing traffic congestion which has resulted in considerable increase in travel time. Huge residential area developments coupled with Special Economic Zones are sprawling along OMR. These ongoing and contemplated developments are likely to have huge impacts on traffic flow along the corridor. Road widening requires considerable land acquisition which cause more social impact. Hence, GoTN desired to construct an elevated highway corridor along OMR from Taramani to Siruseri under Phase-I and Siruseri to Mahabalipuram under Phase-II, for a length of 45 km. The DPR for the project is under preparation.

(8) Construction of Elevated Road along NH45

NH45 is the gateway to Chennai from the southern part of Tamil Nadu. The stretch between the airport and Chengalpattu traverses through major urbanized areas and has major developments such as IT center, gated communities, malls, educational institutions, major industrial center, and SEZs. This area is also witnessing fast growth, and it will continue to attract more developments in the future also. The stretch experiences frequent traffic jam, and vehicles cannot move fast resulting to decrease in travel speed. Therefore, CMDA is preparing a detailed feasibility study report for construction of an exclusive elevated road for the thorough traffic from the Chennai Airport to the toll-plaza near Chengalpattu along NH45.

(9) Widening Project of TPP Road (State Highway 104)

TNRDC is executing the widening and improvement project of the road section from the IRR intersection to North Terminal Road, as “Ennore-Manali Road Improvement Project”.

2.4.4 Intelligent Transport System (ITS) Development Plans and Projects

(1) Integrated Traffic Management System (ITMS) Project

ITMS Project is the project of CTP that introduces systems and facilities for traffic management. It includes the replacement of traffic signals at approximately 100 junctions in the city and enforcement systems utilizing Automatic Number Plate Recognition (ANPR) cameras.

The tender for ITMS was awarded to M/s Purple InfoTech Ltd. a few years ago, but the termination notice was issued because of several reasons. For instance, the contractor did not carry out the first phase of the project in time. The project is under litigation.


(2) Smart City Project

There is a plan under the Smart City Initiative to establish an Integrated Command Control Center (ICCC) and to develop information systems in several different sectors such as water, energy, environment, safety, etc. The ICCC will be developed under CSCL, and the information systems will collect data. The collected data will be aggregated in the ICCC and will be used for analysis. The analyzed data will be utilized for necessary measures. The Smart City Project targets to commence a part of service of any of the information systems from May 2018, and preparation of the specifications is underway.

The Chennai Traffic Information System, or Chennai Traffic Information Center (C-TIC), which is proposed to be developed by Japanese ODA Loan Project will be one of the information systems in the transport sector under the ICCC. The data collected by C-TIC will be shared and utilized by the ICCC in the future.

ICCC will be established in the building of GCC, and C-TIC will be in the building of CTP.

Figure 2.4.1 illustrates the concept of the Smart City Project establishing the ICCC and the information systems.



Source: Edited by the JICA Study Team based on interviews with related organizations and the report on the Data Collection Survey for Chennai Metropolitan Region ITS

Figure 2.4.2 Overview of the Current Situation of the Arterial Roads in Chennai

(2) Toll Plaza Plans

The locations for toll plazas in Chennai are shown in Figure 2.4.2 in the previous page. The current free roads of Section 1 (in service) and Section 2 (under construction) of ORR and IRR (in service) are planned to be converted into toll roads with new toll plazas to be built. The Kattupalli Port Access Road is also considered to be converted into a toll road.

(3) ITS Facilities for Arterial Roads

Highway Traffic Management Systems (HTMS) and Traffic Management Systems (TMS) have been introduced to arterial roads in Chennai. HTMS has been introduced only to ORR (Section 1) with limited facilities.

TMS has been introduced to NHs and Chennai Bypass under NHAI with the electronic toll collection (ETC) system of Radio Frequency Identifier (RFID) called FASTag, touch-and-go system using IC card, and manual toll collection system by cash. As for SH49 and SH49A under TNRD, touch-and-go system, and manual toll collection system have been introduced. The introduction of the ETC System is planned on ORR. The IC cards adopted for touch-and-go system are not the common type that can be used across different sections and/or transport modes; therefore, each card is available only for each specific road.

The following table shows the current situation for each road.

Table 2.4.25 Current Situation of ITS Facilities for Arterial Roads

Road Category		HTMS		TMS	
		Current Situation	Plan	Current Situation	Plan
SH	IRR	—	—	—	Cash
	ORR: Section 1	VMS, Emergency Call Box, Weather Observation	—	—	Cash, Touch & GO, ETC (FASTag)
	ORR: Section 2 (under construction)	—	VMS, Emergency Call Box, Weather Observation	—	Cash, Touch & GO, ETC (FASTag)
	SH49	—	—	Cash, Touch & Go	—
	SH49A	—	—	Cash, Touch & Go	—
NH	Chennai Bypass	—	—	Cash, ETC (FASTag)	—
	NH5	—	—	Cash, Touch & GO, ETC (FASTag)	—
	NH205	—	—	Cash	—
	NH4	—	—	Cash, Touch & GO, ETC (FASTag)	—
	NH45	—	—	Cash, Touch & GO, ETC (FASTag)	—

Source: Edited by the JICA Study Team based on interviews with related organizations and the report on the Data Collection Survey for Chennai Metropolitan Region ITS