資料6 参考資料

(5) 水道メータの調達・設置技術

水道メータの調達・設置技術

1. パンジャブ州におけるメータ調達の動向

2018年9月、パンジャブ州政府は、5つの WASA に対して、メータ調達のために 15億 PKR の 予算を確保する旨の発表をした。しかし、その後、PPP でのメータ調達の議論が活発化し、開発 事業(ADP)の予算に当該予算は計上されたまま、凍結されている。図1にPPPとADP調達のイ メージを示す。

PPP mode for meter procurement

ADP mode for meter procurement (Without Budget) Government of Government of Punish Puniab (1) Budget (2) Budget Request Allocation (1) Tender (3) Tender 5 WASAs 5 WASAs (6) Bill Collection (6) Meter Installation (5) Report (7) Payment (4) Contract (2) Funding (5) Meter Procurement Meter Private Sector Manufacturer (3) Meter Procurement (4) Meter Installation

図1 PPP と ADP によるメータ調達のイメージ

従来の ADP スキームでは、毎年、WASA がメータ調達に掛かる予算を申請する。予算が州政府 によって承認されると、予算が WASA へ配分される。その予算の範囲内で、WASA は、必要な数 量のメータを直接、調達できる。従って、WASAが主導しながら、きめ細かにメータの仕様を定 め、調達することができる。

PPP スキームでは、民間セクターはメータ調達のみならず、メータ設置まで含めた資金を調達 する。民間セクターがメータを設置した地区を、WASA は従量制に切り替え、水道料金の増収分 を民間セクターに支払う。そのため、本スキームでは、州政府の支出が不要となることから、州 政府にとっては好ましいスキームである。

パンジャブ州において、ラホール上下水道局(WASA-L)が PPP スキームを適用し、700,000 個 のメータ調達の発注を検討している。WASA-L と民間セクターの契約期間は、10 年程度を想定し ている。他の WASA は PPP でのメータ調達に向けた実質的な動き出しはしておらず、WASA-Lの 動向を静観している状況である。

2. 水道メータの設置技術

WASA-F は、M/P プロジェクトのパイロット活動で作成された給水装置設置マニュアルに基づ き、2か所のパイロット地区に水道メータを設置し、さらに、全市への水平展開も図られている。 そのため、給水装置設置に関して、十分な技術を WASA-F は保有している。

3. WASA-F によるメータ調達への提言

本プロジェクトによって、給水量および給水圧の増加によって給水サービスの向上が見込まれ る。また、WASA-F はメータを調達し、従量制へ移行することを計画している。従量制へ移行さ れると、収入が増加し、財務改善が期待できる。

WASA-Fによるメータ調達は、PPP スキームあるいは ADP スキームのいずれかになる。いずれの場合も、安定したサービスの提供および継続的な技術革新を目的とし、給水装置設置技術やメータ仕様などを検討できる組織体制の形成を提言する。

Annex 1 G/A NO. XXXXXXX PMR prepared on 15/12/2020

Project Monitoring Report on Project Name Grant Agreement No. XXXXXXX

2020, December

Organizational Information

Signer of the G/A (Recipient)	Person in Charge Contacts	(Designation) Address: Phone/FAX: Email:
Executing Agency	WASA Faisalaba Person in Charge Contacts	Address: Near Allied Hospital, Jail Road Faisalabad, Pakistan Phone/FAX: +92 41 921 0049 / 0054 Email: info@wasafaisalabad.gop.pk
Line Ministry	Ministry of Ecor Person in Charge Contacts	

General Information:

Project Title	The Project for Improvement of Water Treatment Plant and Water Distribution System in Faisalabad		
E/N	Signed date: Duration:		
G/A	Signed date: Duration:		
Source of Finance	Government of Japan: Not exceeding JPYmil. Government of Pakistan:		

1: Project Description

1-1 Project Objective

Living environment in Faisalabad is improved through an improvement of the water supply capacity by renewing and expanding the existing WTP and development of transmission and distribution facilities.

1-2 Project Rationale

- Higher-level objectives to which the project contributes (national/regional/sectoral policies and strategies)
- Situation of the target groups to which the project addresses

Higher-level objectives:

Water supply facilities are developed according to M/P Project through the financial improvement of WASA-F as a result of an increase in income by an increase in a number of the customers and the tariff collection rate.

Situation of the target groups:

Water supply demand has been increased by an increase in population. Consequently, it is expected that the (maximum) daily demand for Faisalabad in 2023 will exceed the current water supply capacity by approximately 30%. Furthermore, improper segmentation of the service area and inadequate water distribution management have caused low water pressure and intermittent water supply limited for about six hours per day in the area.

1-3 Indicators for measurement of "Effectiveness"

Quantitative indicators to measure the attainment of project objectives					
Indicators	Original (Yr 2020)	Target (Yr 2027)			
Production volume by WTP*1	6,800 m³/day	14,800 m³/day			
Distribution pressure	approximately 0 - 8 m (average: 1.7 m) *2	25 m or higher*3			

Qualitative indicators to measure the attainment of project objectives

- Improvement of living environment and public health for citizens, and contribution in promoting infection control measures by improving water supply services such as water supply hours
- Improvement of WASA-F's financial status by increasing a number of customers and the income from water tariff

Note:

- *1: Average of production volume by WTP without closing period of RBC approximately for 3 weeks per year
- *2: Average of maximum pressure at tap surveyed in 2019-20
- *3: Measurement at flowmeter room of OHR

2: Details of the Project

2-1 Location

Components	Original	Actual
	(proposed in the outline design)	
Construction of WTP	i) Old JK WTP, ii) Abudulah Pur, and iii) Madina	
and transmission /	Town in Faisalabad	
distribution facilities		

2-2 Scope of the work

Components	Original	Actual
-	(proposed in the outline design)	
1. Construction of Intake	- Intake mouth, branch valve chamber	
(10 MGD)	- Raw water pump station	
2. Construction of Water	- Receiving and distribution tank	
Treatment Plant (5 MGD)	- Mixing tank	
	- Flocculation tank	
(Applicable to expand the	- Settling tank	
capacity to 10 MGD)	- Rapid sand filter	
	- Clear water reservoir	
	- Transmission pump station	
	- Waste water and sludge tank	
	- Sludge thickener	
	- Sludge extraction pump house	
	- Sludge drying bed	
	- Chemical building	
	- Administration building	
	- Power receiving and transforming, and generator	
	house	
	- Electricity meter house	
3. Construction of	- Ground reservoir (2 ponds)	
Distribution Center	- Overhead reservoir (2 ponds)	
4. Construction of	- Transmission main (4.1 km)	
Transmission and	- Distribution primary main (1.2 km)	
Distribution Main	- Distribution secondary main (1.9 km)	
(Applicable to transmit a		
capacity of 10 MGD		
partially)		

Reasons for modification of scope (if any).	
(PMR)	

2-3 Implementation Schedule

•	Ori		
Items	(proposed in the outline design)	(at the time of signing the Grant Agreement)	Actual
Cabinet Approval	12/2020		
E/N	2/2021		
G/A	2/2021		
Consultant Contract	3/2021		
Detailed Design	3/2021 - 9/2021		
Prequalification	10/2021		
Bidding	12/2021		
Contract with Contractor	1/2022		
Construction	1/2021 - 5/2024		
Soft component	4/2024 - 9/2024		

Defect Liability Period	4/2025	
Project Completion	4/2025	

Reasons for any changes of the schedule, and their effects on the project (if any)

2-4 Obligations by the Recipient

2-4-1 Progress of Specific Obligations

See Attachment 2.

2-4-2 Activities

See Attachment 3.

2-4-3 Report on RD

See Attachment 11.

2-5 Project Cost

2-5-1 Cost borne by the Grant (Confidential until the Bidding)

Components			Cost	
	·			
	Original (proposed in the outline design)	Actual (in case of any modification)	Original ^{1),2)} (proposed in the outline design)	Actual
	1.		uesign)	
Total				

Note: 1) Date of estimation:

2) Exchange rate: 1 US Dollar = Yen

2-5-2 Cost borne by the Recipient

Components	Cost			
			(millio	n PKR)
Original	Act	ual	Original ^{1),2)}	Actual
(proposed in the outline design)	(in case of any	modification)	(proposed in	
(1			the outline	
			design)	
Rehabilitation of Raw Water Reservoir A			59.38	
Dismantling of Existing Facilities			29.97	
Relocation of WASA-F and FDA Staff			19.98	
Electrical Works			22.29	
Total			131.62	

Note:

1) Date of estimation:

2) Exchange rate: 1 US Dollar = 105.74 JPY

Reasons for the remarkable gaps between the original and actual cost, and the countermeasures (if any)

(PMR)			

2-6 Executing Agency

- Organization's role, financial position, capacity, cost recovery etc,
- Organization Chart including the unit in charge of the implementation and number of employees.

Original (at the time of outline design)

- Name: Water and Sanitation Agency Faisalabad
- Role: To provide water supply, sewerage and drainage services to citizen of Faisalabad
- Financial situation: The financial sources for the development and the non-development budget of WASA-F are subsidy from the provincial government and the income from water tariff, etc. The income from water tariff has been increased as a result of the pilot activities on the Master Plan Project.
- Institutional and organizational arrangement (organogram): The organization is headed by MD and formed by three DMDs sectionalized in i) finance & revenue, ii) engineering, and iii) services.
- Human resources (number and ability of staff): Total number of staff is 2,567. The staff of WDM is responsible and properly working for the operation of WTP and distribution management.

Actual (PMR)			
Tittudi (1 1/11t)			

2-7 Environmental and Social Impacts

- The results of environmental monitoring based on Attachment 5 (in accordance with Schedule 4 of the Grant Agreement).
- The results of social monitoring based on in Attachment 5 (in accordance with Schedule 4 of the Grant Agreement).
- Disclosed information related to results of environmental and social monitoring to local stakeholders (whenever applicable).

3: Operation and Maintenance (O&M)

3-1 Physical Arrangement

- Plan for O&M (number and skills of the staff in the responsible division or section, availability of manuals and guidelines, availability of spare parts, etc.)

Original (at the time of outline design)

Operator/Maintenance Engineer (2), Process Engineer (1), Plant Operator (3), Mechanic / Helper Mechanic (3), Electrician / Helper Electrician (3), Laboratory specialist / Assistant (4), Plumber / Helper Automation (3)

Actual	(PMR)
Actual	111111111111111111111111111111111111

3-2 Budgetary Arrangement

- Required O&M cost and income by water tariff

Original (at the time of outline design)

O&M cost and income from water tariff at water transmission of 20,450 m³/d are projected as follows:

- O&M cost: 101 million PKR/year
- income from water tariff at collection rate of 40%: 113 million PKR

Actual (PMR)

4: Potential Risks and Mitigation Measures

- Potential risks which may affect the project implementation, attainment of objectives, sustainability
- Mitigation measures corresponding to the potential risks

Assessment of Potential Risks (at the time of outline design)

Potential Risks	Assessment
1. Air Pollution	Probability: High/Moderate/Low
	Impact: High/Moderate/Low
	Analysis of Probability and Impact:
	During Construction
	Temporary deterioration of air quality is expected due to operation of construction machineries and vehicles.
	Mitigation Measures:
	- Use of construction equipment with exhaust gas emission control
	- Careful operation and self-regulation of speed of construction machineries and vehicles
	- Watering to prevent dust
	Action required during the implementation stage:
	Contingency Plan (if applicable):
2. Water Pollution	Probability: High/Moderate/Low
	Impact: High/Moderate/Low
	Analysis of Probability and Impact:
	<u>During Construction</u>
	Due to construction of the intake facility, temporary water pollution such as soil runoff downstream is expected.
	*
	Mitigation Measures:
	- Control of soil flown out to RBC from the working area of intake facility
	- Preventive maintenance of construction machineries and vehicles
	- Wastewater control at accommodation for workers

	Action required during the implementation stage:
	Contingency Plan (if applicable):
3. Solid Waste	Probability: High/Moderate/Low
	Impact: High/Moderate/Low
	Analysis of Probability and Impact:
	<u>During Construction</u>
	Generation of construction debris and waste materials
	is expected.
	During Operation
	Sludge will be generated from the water treatment
	plant, and the generated sludge is planned to be
	transported to the waste treatment plant as waste.
	Mitigation Measures:
	- Proper waste handling at waste disposal site and
	treatment plant
	- Guidance to workers on construction site cleaning
	Action required during the implementation stage:
	7 Kuon required during the implementation stage.
	Contingency Plan (if applicable):
Actual Situation and Countermeasure	s
(PMR)	
5: Evaluation and Monitoring	Plan (after the work completion)
5. Evaluation and Monitoring	g Flair (after the work completion)
5-1 Overall evaluation	
Please describe your overall evaluation o	on the project.
	- /
5-2 Lessons Learnt and Recomme	endations
	he project experience, which might be valuable for the
•	ects, as well as any recommendations, which might be
• • • • • • • • • • • • • • • • • • • •	ject effect, impact and assurance of sustainability.
beneficial for better realization of the pro	get effect, impact and assurance of sustamavinty.

5-3 Monitoring Plan of the Indicators for Post-Evaluation

Please describe monitoring methods, section(s)/department(s) in charge of monitoring, frequency, the term to monitor the indicators stipulated in 1-3.


The production volume by WTP and the distribution pressure are monitored and recorded in SCADA installed at WTP.

Attachment

- 1. Project Location Map
- 2. Specific obligations of the Recipient which will not be funded with the Grant
- 3. Monthly Report submitted by the Consultant (not available in current version)

Appendix - Photocopy of Contractor's Progress Report (if any)

- Consultant Member List
- Contractor's Main Staff List
- 4. Check list for the Contract (including Record of Amendment of the Contract/Agreement and Schedule of Payment) (not available in current version)
- 5. Environmental Monitoring Form / Social Monitoring Form
- 6. Monitoring sheet on price of specified materials (Quarterly)
- 7. Report on Proportion of Procurement (Recipient Country, Japan and Third Countries) (PMR (final)only)
- 8. Pictures (by JPEG style by CD-R) (PMR (final)only) (not available in current version)
- 9. Equipment List (PMR (final)only) (not available in current version)
- 10. Drawing (PMR (final)only) (not available in current version)11. Report on RD (After project) (not available in current version)



Location Map

Specific obligations of the Government of Pakistan ("the Recipient" of the Grant) which will not be funded with the Grant

(1) Before the Bidding

No	Refore the Bidding Items	Deadline	In charge	Estimated	Ref
110	remo	Beadine	in charge	Cost	TCOI.
1	To open bank account (B/A)	within 1 month after the signing of the G/A	WASA-F	_	
	To issue A/P to a bank in Japan (the Agent Bank) for the payment to the consultant	within 1 month after the signing of the contract	WASA-F	6,000 JPY/each issue 4,000 JPY/each amendme nt	
	To approve IEE/EIA(Conditions of approval should be fulfilled, if any) and secure the necessary budget for implementation.	before the announcement of tender	WASA-F	1.5 million PKR (for entire period until "After the Project")	
	To complete the relocation of WASA-F and FDA officials living around the distribution centers of Abudulah Pur and Madina Town No. 2 where the overhead reservoirs will be demolished for the Project	before the signing	WASA-F	19.98 million PKR	
5	 To secure and clear the following lands Site for Old JK WTP (existing rapid sand filter, storage etc.) Site for the distribution centers of Abudulah Pur and Madina Town No. 2 	before the announcement of tender	WASA-F	29.97 million PKR	
6	To rehabilitate the raw water reservoir A	before the announcement of tender	WASA-F	59.38 million PKR	
	To bring power to Old JK WTP and distribution centers of Abudulah Pur and Madina Town No. 2	before the announcement of tender	WASA-F	22.29 million PKR	
	To submit Project Monitoring Report (with the result of Detailed Design)	before the announcement of tender	WASA-F	_	
	To establish Project Implementation Unit and assign WASA-F staff	soon after Detailed Design starts	WASA-F	1.25 million PKR/mon th	
	To coordinate and acquire permission/approval from relevant agencies/organizations when any types of permission are required for construction under the Project		WASA-F	16 million PKR	

(B/A: Banking Arrangement, A/P: Authorization to pay, N/A: Not Applicable)

(2) During the Project Implementation

Ĺ	During the Project Implementation	D 11:	т 1	Estimated	D.C
NO	Items	Deadline	In charge	Cost	Ref.
1	To issue A/P to a bank in Japan (the Agent Bank) for the payment to the Suppliers (s).	within 1 month after the signing of the contract(s)	WASA-F	6,000 JPY/each issue	
				4,000 JPY/each amendme nt	
2	To bear the following commissions to a bank in Japan for the banking services based upon the B/A			_	
	1) Advising commission of A/P	within 1 month after the signing of the contract(s)		6,000 JPY/each issue	
			WASA-F	4,000 JPY/each amendme nt	
	2) Payment commission for A/P	every payment	WASA-F	0.1% of every payment	
3	To handle duty (tax) exemption procedures and to take necessary measures as well as provide requisite legal and/or administrative documentations for customs clearance to the customs broker/forwarder to be employed by the Supplier(s) at the port of disembarkation for the materials and equipment imported for the Project as well as sending back of any defective equipment and/or spare parts to the manufacturer for repair at the factory or replacement and importation thereof into the country of the Recipient during the implementation and warranty periods of the Project.	during the Project	EAD WASA-F	_	
	To accord Japanese physical persons and/or physical persons of third countries whose services may be required in connection with the supply of the products and the services such facilities as may be necessary for their entry into the country of the Recipient and stay therein for the performance of their work.	during the Project	EAD WASA-F	_	
	To ensure that customs duties, internal taxes and other fiscal levies which may be imposed in the country of the Recipient with respect to the purchase of the products and/or the services be exempted. (with regard to the internal taxes, the total percentages of rates of the sales tax imposed on the said purchase shall be zero percent (0%) or the sales tax imposed on the said purchase shall be exempted.)	during the Project	EAD WASA-F	-	
6	To arrange the maximum countermeasures and ensure the appropriate security of the whole Project sites and of the Japanese and other foreign nationals assigned to the Project, with deployment of city police through its Administration & Security Branch in addition to the private security arrangement by the Suppliers(s). 1) To arrange security around the Project sites with the police. 2) To arrange security around the accommodation(s) of the Suppliers(s) with the police. 3) To arrange escort guard with the police during movements between the accommodation(s) of the Supplier(s) and the Project sites. 4) To install monitoring cameras at Old JK WTP and distribution centers of Abudulah Pur and Madina Town No. 2.	prior to the commencement of and during implementation of the Project	WASA-F through District Police	10 million PKR	

	7				
	5) To repair the wall around distribution centers of Abudular Pur.				
7	To provide facilities for distribution of electricity, water supply and drainage and other incidental facilities necessary for the implementation of the Project outside the site(s).			_	
	1) Electricity The distributing line to the site including utilization of electricity for trial operation	before start of the construction	WASA-F		
	2) Water Supply The city water distribution main to the site including utilization of water for trial operation and construction works such as cleaning sites and facilities, pressure test, etc.	before start of the construction	WASA-F		
	3) Drainage The city drainage main (for storm, sewer and others) to the site including utilization of drainage main for trial operation and construction works such as wastewater from cleaning sites and facilities, pressure test, etc.	before start of the construction	WASA-F		
8	To provide necessary working spaces for the Project Office of the Suppliers(s).	during the Project	WASA-F		
9	To bear all the expenses, other than those to be covered by the Grant, necessary for the implementation of the Project.	during the Project	Govt. of Punjab & WASA-F	_	
10	To implement EMP and EMoP	during the construction	WASA-F	_	
	To submit results of environmental and social monitoring to JICA, by using the monitoring form, on a quarterly basis as a part of Project Monitoring Report	during the construction	WASA-F	_	
12	To take necessary measures on controlling traffic and/or detouring traffic for securing safety to workers and all types of the traffic	during the construction	WASA-F	_	
13	1)To submit Project Monitoring Report	every month	WASA-F	_	
	2)To submit Project Monitoring Report (final)	within 1 month after issuance of Certificate of Completion for the works under the contract(s)	WASA-F	_	
14	To submit a report concerning completion of the Project	within 6 months after completion of the Project	WASA-F	_	

(Suppliers(s): suppliers, contractors and/or consultants)

(3) After the Project

NO	Items	Deadline	In charge	Estimated Cost	Ref.
1	To implement EMP and EMoP	for a period based	WASA-F		
		on EMP and		_	
		EMoP			
2	To submit results of environmental and social monitoring to JICA,	for three years	WASA-F		
	by using the monitoring form, semiannually	after the Project			
	- The period of environmental and social monitoring may be			_	
	extended if any significant negative impacts on the environment are				
	found. The extension of environmental and social monitoring will be				
	decided based on the agreement between WASA-F and JICA.				
	To maintain and use properly and effectively the facilities	After completion	WASA-F		
	constructed and equipment provided under the Grant Aid	of the			
	1) Allocation of maintenance cost	construction		_	
	2) Allocation of additional staff for operation and maintenance				
	3) Routine check/Periodic inspection				

Environmental and Social Monitoring Form (Draft)

(1) Pollution Control Measures

1) Air Pollution: During Construction

a) Observation

Monitoring Item				Remarks		
Dust generated at construction site	Construction	site,	Four	times/year,	Physical	observation
	(existence of o	lust)				

b) Measurement (Environmental Standard)

Item (Unit)	Measured Value (Mean)	Measured Value (Maximum)	Local Standard	Japanese Standard	Remarks (Measurement point, frequency, method)
CO (mg/m ³)			<5	<11.5	Air quality measurement around
$SO_2 (\mu g/m^3)$			<120	<105	construction site, Four times/year, Air
NOx (μg/m ³)			<80	_	quality measurement
$PM_{10} (\mu g/m^3)$			<150	<100	

2) Water Pollution (Effluent/Drinking Water Quality Standard): During Construction

Item (Unit)	Measured Value (Mean)	Measured Value (Maximum)	Local Standard	Japanese Standard	Remarks (Measurement point, frequency, method)
COD (mg/L)			<150	≤160	Effluent quality measurement around
SS (mg/L)			<200	≤200	construction site, Twice/year, Water quality analysis
pН			6.5-8.5	5.8-8.6	Drinking water quality downstream of
Odour			NO	NO	construction site at intake facility, Twice/year, Water quality analysis
Taste			NO	NO	Twice/year, water quanty analysis
Colour (Pt-Co)			≤15 TCU	≤5 CU	
Turbidity (NTU)			<5	≤2	
Total Hardness (mg/L)			< 500	≤ 300	
TDS (mg/L)			<1000	≤500	
Cl (mg/L)			< 250	≤200	
CN (mg/L)			≤0.05	≤0.01	
F (mg/L)			≤ 1.5	≤0.8	
NO ₂ - (mg/L)			≤3	≤0.04 (as N)	
NO ₃ - (mg/L)			≤ 50	$\leq 10 \text{ (NO}_3^ \text{N} + \text{NO}_2^ \text{N)}$	
Phenol (mg/L)			_	≤0.005	
Residual Cl (mg/L)			0.2-0.5	_	
Al (mg/L)			≤ 0.2	≤0.2	
Pesticides (mg/L)			_	_	
Cd (mg/L)			0.01	≤0.003	
Cu (mg/L)			2	≤1.0	

Item (Unit)	Measured Value (Mean)	Measured Value (Maximum)	Local Standard	Japanese Standard	Remarks (Measurement point, frequency, method)
Cr (mg/L)			≤ 0.05	≤0.02 (Cr ⁶⁺)	
Hg (mg/L)			≤ 0.001	≤0.0005	
Sb (mg/L)			≤ 0.005	_	
Ni (mg/L)			≤ 0.02	_	
Zn (mg/L)			5.0	≤1.0	
As (mg/L)			≤ 0.05	≤0.01	
Ba (mg/L)			0.7	_	
Mn (mg/L)			≤ 0.5	≤0.05	
B (mg/L)			0.3	≤1.0	
Pb (mg/L)			≤ 0.05	≤0.01	
Se (mg/L)			0.01	≤0.01	
Total Coliforms			0/100ml	≤100/1ml (Common bacteria)	
Faecal Coliforms			0/100ml	Not to be detected (E. Coli)	

3) Solid Waste

a) During Construction

	Monitoring Item	Remarks
•	Proper waste handling at disposal site	Construction site and disposal site, Once/month, Physical
	and treatment plant	observation (proper disposal, cleaning situation)
•	Cleaning of construction site by	
	workers	

b) During Operation

Monitoring Item	Remarks
Proper removal and disposal of generated	Water treatment plant, Once/month, Physical observation (status
sludge	of sludge removal and disposal)

4) Soil Contamination: During Construction

Monitoring Item	Remarks
Proper storage and disposal of fuel, soil etc.	Construction site, Once/month, Physical observation (status of
	fuel and oil storage and disposal.)

5) Noise and Vibration: During Construction/During Operation

Item (Unit)	Measured Value (Mean)	Measured Value (Maximum)	Local Standard	Japanese Standard	Remarks (Measurement point, frequency, method)
Noise Level (dB)			<75	<85	During construction: Daytime industrial area surrounding construction site, Twice/year, Sound level meter During operation: Daytime industrial area surrounding water treatment plant. Every 6 months, Sound level meter

(2) Natural Environment

Hydrological Conditions: During Construction

Monitoring Item	Remarks
Water level near intake mouth	Around intake, Once/week, Water level measurement

(3) Social Environment

1) Local Economy (Livelihood, Employment, etc.): During Construction

Monitoring Item	Remarks
Efficient traffic regulation to reduce impact	Around construction site, Once/week, Inquiries to relevant
on local economy	persons (residents, local businesses, shop owners, etc.) and
	physical observation (conducting of traffic control and
	installation of signboards)
Economic impact on shops and offices due	Around construction site, Once/week, Inquiries to relevant
to reduced access due to the construction	persons (residents, local businesses, shop owners, etc.) and
	physical observation (existence of temporary closure of shops
	and offices)

2) Water Use and Water Rights

a) During Construction

Monitoring Item	Remarks
Fluctuations in water quantity and quality	Canal downstream the intake of WTP Once/week, Inquiries to
in canal due to the construction of intake	relevant person and physical observation (fluctuation in water
facility	quantity and quality in canal)

b) During Operation

Monitoring Item	Remarks
Changes in amounts of irrigation water to	Agricultural lands downstream the intake of WTP, Quarterly,
downstream agricultural lands especially	Physical observation and inquiries to the Irrigation Department
during drought periods	(change in amount of irrigation water)

3) Existing Social Infrastructures and Social Services: During Construction

Monitoring Item	Remarks
Traffic obstacles and reduced access to	Around construction site, Once/week, Inquiries to relevant
existing infrastructures	persons and physical observation (existence of traffic obstacles
	and reduced access to existing infrastructure)

4) Landscape: During Construction

Monitoring Item	Remarks
Changes in landscape around construction	Around construction site, Once/month, Physical observation
site	(change in landscape)

5) Infectious Diseases such as HIV/AIDS: During Construction

Monitoring Item	Remarks
Implementation of guidance on prevention	In the construction site, Once/month, Physical observation
of infectious diseases	(execution status of guidance)

6) Working Conditions: During Construction

Monitoring Item	Remarks
Execution of occupational safety and health	In the construction site, Once/week, Physical observation
guidance and periodic safety meetings	(execution status of guidance and meetings) and reports on
	workshops and safety meetings

7) Accidents: During Construction

Monitoring Item	Remarks
Installation of safety mesaures such as fences and warning signs	Around construction site, Once/week, Inquiries to relevant persons and physical observation (Installation of safety
reflects and warning signs	measures)

8) The Poor: During Operation

Monitoring Item	Remarks
Impact from water tariff system to	In the project site, Every 6 months, Inquiries to relevant persons
household economy of poverty group	(impact from water tariff system to the poverty group)

1. Initial Conditions (Confirmed)

		1t.:1 V	Initial Unit	Initial total	1% of Contract	Condition of payment	of payment
	Items of Specified Materials	initiai voiume	Price (¥)	Price	Price	Price (Decreased)	Price (Increased)
		\mathbf{A}	В	$C=A\times B$	D	$oxed{ E=C-D } oxed{ F=C+D}$	F=C+D
1	Item 1	••t	•	•	•	•	•
2	Item 2	1••	•	•	•		
3	3 Item 3						
4	Item 4						
5	Item 5						

2. Monitoring of the Unit Price of Specified Materials (1) Method of Monitoring : ●●

(2) Result of the Monitoring Survey on Unit Price for each specified materials

Troms of Change Motomials 1st	• eriais • month, 2015			
2nd	•month, 2015			
3rd	•month, 2015			
4th				
5th				
eth				

(3) Summary of Discussion with Contractor (if necessary)

Report on Proportion of Procurement (Recipient Country, Japan and Third Countries) (Actual Expenditure by Construction and Equipment each)

	Domestic Procurement	Foreign Procurement	Foreign Procurement	Total
	(Recipient Country)	(Japan)	(Third Countries)	D
	A	В	C	
Construction Cost	(A/D%)	(B/D%)	(C/D%)	
Direct Construction Cost	(A/D%)	(B/D%)	(C/D%)	
others	(A/D%)	(B/D%)	(C/D%)	
Equipment Cost	(A/D%)	(B/D%)	(C/D%)	
Design and Supervision Cost	(A/D%)	(B/D%)	(C/D%)	
Total	(A/D%)	(B/D%)	(C/D%)	

資料 - 7 その他の資料・情報

資料7 その他の資料・情報 (1) 配水圧調査結果

Water Pressure Records on Water Servise Pipes

One day for each point from Oct 2019 to Mar 2020


Macausing Time						Supply Time			
Sr#	DMA	Measuring Time		Pressure (bar)					
		Date	From	То	Lower	Ave/Upper	A.M.	P.M.	
	DMA-II-1	22-1-2020	9:30 AM	5:30 PM	0.15	0.24	5:30 to 7:30	4:30 to 6:30	
	DMA-II-1	11-2-2020	10:00 AM	5:00 PM	0.50	0.77	5:30 to 7:30	4:30 to 6:30	
	DMA-II-1	12-2-2020	10:00 AM	5:00 PM	0.10	0.20	5:30 to 7:30	4:30 to 6:30	
	DMA-II-1	13-2-2020	11:50 AM	5:00 PM	0.12	0.12	5:30 to 7:30	4:30 to 6:30	
	DMA-II-1	17-2-2020	10:00 AM	5:00 PM	0.00	0.00	5:30 to 7:30	4:30 to 6:30	
	DMA-II-1	18-2-2020	10:30 AM	5:00 PM	0.10	0.40	5:30 to 7:30	4:30 to 6:30	
	DMA-II-2	19-2-2020	10:20 AM	5:00 PM	_	0.10	5:30 to 7:30	4:30 to 6:30	
	DMA-II-2	21-1-2020	10:20 AM	5:30 PM		0.25	5:30 to 7:30	4:30 to 6:30	
	DMA-II-2	4-2-2020	10:25 AM	5:00 PM	_	0.00	5:30 to 7:30	4:30 to 6:30	
	DMA-II-2	5-2-2020	10:00 AM	5:00 PM	0.23	0.38	Tube wel		
	DMA-II-2	21-10-2019	10:15 AM	5:45 PM	0.00	0.23	-	4:00 to 6:00	
	DMA-II-2	10-2-2020	10:20 AM	5:30 PM	_	0.00	5:30 to 7:30	4:30 to 6:30	
	DMA-II-3	23-1-2020	9:30 AM	6:30 PM	0.15	0.24	5:30 to 7:30	4:30 to 6:30	
	DMA-II-3	27-1-2020	9:40 AM	5:45 PM	0.00	0.14	5:30 to 7:30	4:30 to 6:30	
	DMA-II-3	28-1-2020	11:10 AM	5:00 PM	_	0.00	5:30 to 7:30	4:30 to 6:30	
16	DMA-II-3	29-1-2020	10:00 AM	5:10 PM	_	0.00	5:30 to 7:30	4:30 to 6:30	
17	DMA-II-3	30-1-2020	10:00 AM	5:30 PM	_	0.20	5:30 to 7:30	4:30 to 6:30	
18	DMA-II-3	3-2-2020	9:45 AM	5:00 PM	_	0.18	5:30 to 7:30	4:30 to 6:30	
19	DMA-II-4	25-2-2020	10:10 AM	5:00 PM	_	0.00	5:30 to 7:30	4:30 to 6:30	
20	DMA-II-4	24-2-2020	10:10 AM	5:00 PM	0.00	0.10	5:30 to 7:30	4:30 to 6:30	
21	DMA-II-4	20-2-2020	10:20 AM	5:00 PM	_	0.10	5:30 to 7:30	4:30 to 6:30	
22	DMA-II-4	30-10-2019	9:45 AM	5:15 PM	0.00	0.27	_	4:00 to 6:00	
23	DMA-II-4	4-11-2019	10:00 AM	5:00 PM	0.06	0.10	_	4:00 to 6:00	
24	DMA-II-4	6-11-2019	10:00 AM	5:30 PM	0.00	0.03	_	4:00 to 6:00	
25	DMA-I-1	22-10-2019	9:30 AM	5:30 PM	0.20	0.23	-	4:00 to 6:00	
26	DMA-I-1	3-3-2020	10:20 AM	5:00 PM	0.14	0.30	5:30 to 7:30	4:30 to 6:30	
27	DMA-I-1	2-3-2020	10:00 AM	5:00 PM	_	0.10	5:30 to 7:30	4:30 to 6:30	
28	DMA-I-1	27-2-2020	10:20 AM	5:00 PM	0.20	0.50	5:30 to 7:30	4:30 to 6:30	
29	DMA-I-1	26-2-2020	10:25 AM	5:00 PM	-	0.12	5:30 to 7:30	4:30 to 6:30	
30	DMA-I-1	24-10-2019	10:00 AM	5:30 PM	-	0.22	-	4:30 to 6:30	
31	DMA-I-2	29-10-2019	9:30 AM	5:30 PM	0.00	0.03	_	4:00 to 6:00	
32	DMA-I-2	9-3-2020	10:15 AM	5:00 PM	-	0.12	5:30 to 7:30	4:30 to 6:30	
	DMA-I-2	5-3-2020	10:15 AM	5:00 PM	-	0.00	5:30 to 7:30	4:30 to 6:30	
	DMA-I-2	4-3-2020	10:20 AM	5:00 PM	0.10	0.30	5:30 to 7:30	4:30 to 6:30	
	DMA-I-2	31-10-2019	10:00 AM	5:15 PM	0.00	0.10	_	4:00 to 6:00	
	DMA-I-2	5-11-2019	10:00 AM	5:30 PM	0.00	0.08	_	4:30 to 6:30	
				min	0.00	0.00			
				ave	0.10	0.17			


0.77

0.50

max

1 22-1-2020 (Consumer Comments: low pressure problems, use pumps for fill up tanks)



















2 11-2-2020 (Consumer Comments: Water pressure good due to water supply from tubewells)













3 12-2-2020 (Consumer Comments: Water pressure low)













4 13-2-2020 (Consumer Comments: Water pressure low)















5 17-2-2020 (Consumer Comments: Water pressure too low, consumers not using water due to low pressure)















6 18-2-2020 (Consumer Comments: Water pressure too low, Consumers not satisfy with pressure)
















7 19-2-2020 (Consumer Comments: Poor water pressure)
















8 21-1-2020 (Consumer Comments: (pressure is not good)







31°25'02.4"N 73°07'20.8"E

31.417330, 73.122437



9 4-2-2020 (Consumer Comments: very low pressure)



















10 5-2-2020 (Consumer Comments: pressure is good due to direct supply from tube wells of 8" line)












11 21-10-2019(Consumer Comments: low pressure problems)








12 10-2-2020 (Consumer Comments: Water pressure very low)















23-1-2020 (Consumer Comments: low pressure problems, use pumps)






MADINA TOWN

14 27-1-2020 (Consumer Comments: Pressure is not good)

















15 28-1-2020 (Consumer Comments: very low pressure)







16 29-1-2020 (Consumer Comments: very low pressure)














17 30-1-2020 (Consumer Comments: (pressure is not good)








18 3-2-2020 (Consumer Comments: low pressure problems, use pumps for fill up tanks)



















19 25-2-2020 (Consumer Comments: Poor water pressure, not using water due to very low pressure)















20 24-2-2020 (Consumer Comments: Poor water pressure)















21 20-2-2020 (Consumer Comments: Poor water pressure)














22 30-10-2019(Consumer Comments: Pressure is satisfying due to nearest point of Main Line)






















23 4-11-2019(Consumer Comments: Very low pressure)








24 6-11-2019(Consumer Comments: Very low pressure)

















25 22-10-2019(Consumer Comments: Pressure is very low)

















26 3-3-2020 (Consumer Comments: low water pressure, use without motor)















27 2-3-2020 (Consumer Comments: low water pressure, mixing of sewerage water complain)













28 27-2-2020 (Consumer Comments: low water pressure, use water by pumping)















29 26-2-2020 (Consumer Comments: low water pressure, use water by pumping)














30 24-10-2019(Consumer Comments: Pressure is very low and water quality problem)



















31 29-10-2019(Consumer Comments: water not come whole day)







32 9-3-2020 (Consumer Comments: Low water pressure, not used daily due to low pressure)













33 5-3-2020 (Consumer Comments: disconnect water connection due to low pressure)













34 4-3-2020 (Consumer Comments: not using water due to low pressure and mixing with sewerage)


















35 31-10-2019(Consumer Comments: Water pressure and water quality problem)








36 5-11-2019(Consumer Comments: Water has zero pressure)
















資料7 その他の資料・情報 (2) 地質調査結果





LOCATION OF BH1 AND BH2





LOCATION OF BH3 AND BH4



























Project for Improvement of Water Treatment Plant and Water Distribution System, Faisalabad



Table 6: Summary of Laboratory Results

	Depth		NMC	Specific	Bulk	Partic	Particle Size Distribution	oution	Particle	Particle Size Distribution	bution	Direct	Direct Share Test
BH No.	(m)	Sample	(%)	ڻ ن	(kN/m³)	Gravel (%)	Sand	Silt & Clay	(%) T.T	P.L (%)	P.I	Cohesion	Angle of internal
	,	(Sec.)	0 0 7	9,0		c	(/0)	(0/)				(NI a)	
	Ţ	1 (DS)	5.61	2.60	' (0	11	60	' (' (1	•
	3	29 (UDS)	27.3	2.67	19.3	0	6	9.1	29	20	6	•	
	2	30 (UDS)	22	2.68	20	0	10	06	27	20	7	1	1
	10	2 (DS)	14	2.65		0	96	4		-	-	-	-
	12	15 (UDS)	-	-	17.3	-	1	1	-	-	-	1.4	29
BH-1	17	16 (UDS)	-	-	17.9	-	-	-	-	-	-	8.0	30
	20	3 (DS)	10.6	2.66	1	0	26	3	1	-	1	-	-
	22	17 (UDS)	1		16.7	-	-	•	1	-	ì	1	31
	27	18 (UDS)	1	1	18.1	-	-		1	-	1	6.0	32
	32	19 (UDS)	-	-	17.2	-	-	1	-	-	-	1.1	32
	40	4 (DS)	28.3	2.67	1	0	26	3	-	-	-	-	•
	1	5 (DS)	17.3	2.68	-	26	23	51	-	-	-	-	•
	3	31 (UDS)	17	2.67	18.4	0	12	88	25	20	5	-	-
	5	32 (UDS)	14.1	2.69	19.6	12	7	81	28	20	8	-	-
	10	6 (DS)	13.6	2.67	1	0	96	4	-	1	-	-	1
	12	20 (UDS)	-	1	17.3	1	1	1	-	1	-	0.4	29
BH-2	17	21 (UDS)	1	-	16.2	ı		1	-	-	-	0.8	30
	20	7 (DS)	22.7	2.65	1	0	97	3	-	-	-	-	-
	22	22 (UDS)	1	1	17.6	-	1	t	-	-	-	1.1	32
	27	23 (UDS)	1	-	16.6	-	-	1	-	-	-	0.4	32
	36	24 (UDS)	-	-	16.9	-	-	-	-	-	-	1.2	33
	40	8 (DS)	20.1	2.66	1	12	89	20	-	-	-	1	
	1	9 (DS)	4.7	2.69	-	0	93	7	-	1	-	-	1
	2	25 (UDS)	1	1	16	1	-	1	-	1	-	1.8	27
BH-3	3	10 (DS)	5.8	2.65	1	0	68	11	-	1	-	1	ı
	4	26 (UDS)	1	1	16.6	1	_	1	-	-	-	1.6	29
	5	11 (DS)	4.8	2.66	1	0	93	7	-	1	-	-	-
	1	12 (DS)	10.1	2.67	1	0	92	8	-	-	-	-	-
	2	27 (UDS)	1	-	16.1	1	1	1	-	-	-	1.6	28
BH-4	3	13 (DS)	6.1	2.66	1	0	95	5	-		1	-	1
	4	86 (UDS)	1	1	16.1	1	1	1	-			1.4	29
	5	14 (DS)	4.7	2.67	_	1	92	7	-		-	1	ı



App 7(2)-13

			ECO	OS L	td.;	GEC	TEC	CHNI	ICAI	L SERVICES	
		Loca	tion: WT							Project: WASA Master Plan	
		Bore	Hole No	.: 01						Fig No.	
B	ORE HOLE LOG	Туре	of Borin	g: Ro	tary					Date Started: 30-11-17	
			nination							Date Completed: 02-12-17	
		Grou	ınd Wate	er Tak	ole: 3					Logger: Umer	_
		loq					etrat			Recovery	
Depth(m)	Sample Description	Classification Symbol	Legend	Sample Type	Moisture	150		150 mm	N-Values	N- Profile N- Profile SD SD SD SD SD SD SD S	Remarks
2	clay	CL		DS		1	1	1	2	29	
4	Silty clay	CL-N	1L	DS		1	1	2	3	2 27	
6	Silty sand	SM		DS		5	9	9	18		
8	Fine graind sand	SW		DS		8	11	12	23		
10	do	SW		DS		8	10	14	24	10 36	
12	do	SW		DS		9	11	12	23	12 33	
14	do	SW		DS		10	14	19	33	14 34	
16	do	SW		DS		18	22	23	45	16 36	
18	do	SW		DS		10	12	15	27	18 40	
20	do	sw		DS		17	20	18	38	20 38	
22	do	SW		DS		12	10	10	20	22 40	
24	do	SW		DS		12	12	21	33	24 40	
	Silty clay	CL-N	1L	DS		9	13	27	40	26 25	
	Silty sand	SM		DS		10	14	27	41	28 30	
	Medium graind sand	SW		DS		11	19	20	39	30	
32	do	SW		DS		11	26	45	71	32 27	
	do	SW		DS		13	27	50	77	35	
	Med-course sand	SW		DS		14	28	50	78	36 28	
38		SW		DS		20	26	38	64	38	
40	do	SW		DS		30	36	50	86	40	
Che	cked By:										

			ECO	OS L	td.;	GEC	TEC	CHNI	CAL	L SERVICES				
		Loca	tion: WT							Project: WASA Master Plan				
		Bore	Hole No	.: 02						Fig No.				
B	ORE HOLE LOG	Турє	of Borin	g: Ro	tary					Date Started: 03-12-2017				
			nination							Date Completed: 04-12-17				
			ınd Wate	r Tak	ole: 1					Logger: Umer				
		loq					etrat 'alue				Re	cove	ry	
Depth(m)	Sample Description	Classification Symbol	Legend	Sample Type	Moisture	150		150	N-Values	N- Profile 0 20 40 60 80 100	SPT (cm)	CR %	RQD %	Remarks
2	clay	CL		DS		5	5	7	12	0	39			
4	Silty clay	CL-N	1 1	DS		5	6	8	14	2	33			
6	Silty sand	SM		DS		6	7	11	18	'	36			
8	Fine graind sand	SW		DS		8	13	14	27		30			
10	do	SW		DS		9	11	13	24	10	29			
12	do	SW		DS		9	11	16	28	12	30			
14	do	SW		DS		10	14	16	30	14	31			
16	do	sw		DS		25	30	31	61	16	35		_	
18	do	SW		DS		20	24	25	49	18	34			
20	do	SW		DS		17	25	29	54	20	30			
22	do	SW		DS		15	16	16	32	22	22			
24	do	SW		DS		16	18	20	38	24	25		_	
	do	SW		DS		8	17	25	42	26	32		_	
1	Clay	CL		DS		15	14	31	45	28	27		_	
	Medium graind sand	SW		DS		16	19	26	45	30	39		_	
32		SW		DS		18	21	24	45	32	28		_	
34		SW		DS		22	26	28	54	34	38		_	
	Med-course sand	SW		DS		25	30	35	65	1	28	-	\dashv	
38		SW		DS		30	45	40	75	1	25		\dashv	
40	do	SW		DS		40	40	50	90	40	14			
Che	cked By:													

			ECC	OS L	td.;	GEC	TEC	CHNI	ICAL	L SERVICES	
		Loca	tion: WT							Project: WASA Master Plan	
		Bore	Hole No	.: 03						Fig No.	
В	ORE HOLE LOG	Туре	of Borin	g: Ro	tary					Date Started: 05-12-2017	
		Tern	nination	Dept	h: 40	m				Date Completed: 06-12-2017	
		Grou	ınd Wate	er Tak	ole: 2					Logger: Umer	
		bol					etrat			Recovery	
Depth(m)	Sample Description	Classification Symbol	Legend	Sample Type	Moisture			150 mm	N-Values	N- Profile 0 20 40 60 80 100 CB % W W W W W W W W W W W W W W W W W W	Reilidiks
2	clay	CL		DS		2	3	4	7	30	
4	Silty Sand	SM		DS		2	6	10	16	20 20	
6	Silty sand	SM		DS		8	11	12	23		
8	Fine graind sand	SW		DS		10	12	15	27		
10	do	SW		DS		12	18	20	38	10 27	
12	do	SW		DS		12	17	22	39	12 29	
14	do	SW		DS		22	32	35	67	14 35	
16	do	sw		DS		17	17	29	37	16 35	
18	do	SW		DS		11	14	18	32	18	
20	do	SW		DS		22	26	23	39	20 32	
22	do	SW		DS		15	18	21	39	22 32	
24	do	SW		DS		15	19	21	40	24 30	
	do	SW		DS		15	20	35	55	26 28	
I .	Silty sand	SM		DS		23	30	32	62	28 35	
	Medium graind sand	SW		DS		19	29	38	67	30 33	
	do	SW		DS		14	38	50	88	32 30	
	do	SW		DS		20	29	30	59	34 32	
-	Med-course sand	SW		DS		11	36	50	88	36 40	
38	do	SW		DS		20	39	50	89	<u> </u>	
40	do	SW		DS		12	30	50	80	40 38	
Che	cked By:										

			ECO	OS L	td.;	GEC	OTEC	CHN	CAL	L SERVICES	
		Loca	tion: WT							Project: WASA Master Plan	
		Bore	Hole No	.: 04						Fig No.	
В	ORE HOLE LOG	Турє	of Borin	g: Ro	tary					Date Started: 07-12-2017	
			nination							Date Completed: 08-12-17	
		Grou	ınd Wate	er Tak	ole: 2					Logger: Umer	
		pol					etra			Recovery	
Depth(m)	Sample Description	Classification Symbol	Legend	Sample Type	Moisture		/alue 150 mm	150	N-Values		Remarks
2	clay	CL		DS		4	9	10	19	35	
4	Silty clay	CL		DS		5	9	12	21	39	
6	Silty sand	SM		DS		10	10	13	23	33	
8	Fine graind sand	SW		DS		7	11	12	23	30	
10	do	SW		DS		9	14	16	30	33	
12	do	SW		DS		11	14	15	29	33	
14	do	SW		DS		9	16	19	35	28	
16	do	SW		DS		13	15	15	30	34	
18	do	SW		DS		11	13	16	29	38	
20	do	SW		DS		17	17	15	32	28	
22	do	sw		DS		11	14	16	30	32	
24	do	SW		DS		18	21	23	44	35	
	Silty clay	CL		DS		10	35	34	69	31	
I .	Silty sand	SM		DS		24	27	36	63	32	
	Medium graind sand	SW		DS		25	34	39	73	28	
	do	SW		DS		11	27	35	62	25	
	do	SW		DS		25	29	37	66	33	
	Med-course sand	SW		DS		27	30	28	58	25	
38	do	SW		DS		25	30	31	61	33	
40	do	SW		DS		19	18	24	42	34	
Che	cked By:										

			ECO	OS L	td.;	GEC	TEC	CHNI	CAL	L SERVICES			
		Loca	tion: Abo							Project: WASA Master Plan			
		Bore	Hole No	.: 05						Fig No.			
B	ORE HOLE LOG		of Borin							Date Started: 10-12-2017			
			nination							Date Completed: 11-12-2017			
			ınd Wate	er Tak	ole: 1					Logger: Umer			
		 oqu					etrat 'alue			R	ecove	ery	
Depth(m)	Sample Description	Classification Symbol	Legend	Sample Type	Moisture	150		150	N-Values	N- Profile 0 20 40 60 80 100	CR %	RQD %	Remarks
2	Silty clay	CL-N	1L	DS		3	2	4	6	30			
4	Silty Sand	SM		DS		5	6	8	14	34	_		
6	Silty sand	SM		DS		8	12	14	26	32			
8	Fine graind sand	SW		DS		10	13	16	29	34	<u> </u>		
10	do	SW		DS		11	13	12	25	30			
12	do	sw		DS		13	15	19	34	29			
14	do	sw		DS		20	22	23	45	30			
16	Claye Silt	ML		DS		16	19	21	40	35			
18	Fine graind sand	sw		DS		10	17	19	36	35			
20	do	SW		DS		7	14	27	41	38			
22	do	SW		DS		9	15	30	45	22			
24	do	SW		DS		14	22	16	38	38			
26	Silty clay	CL-N	1L	DS		4	15	26	41	25			
28	Silty sand	SM		DS		18	20	24	44	34			
l	Medium graind sand	SW		DS		14	15	22	37	29			
32	do	SW		DS		13	40	50	90	25			
34		SW		DS		10	20	39	59	29			
	Med-course sand	SW		DS		12	33	29	62	32			
38		SW		DS		19	26	33	63	28			
40		SW		DS		30	45	50	95	32			
	cked By:												

			ECC	OS L	td.;	GEC	TEC	CHN	ICAI	L SERVICES				
			tion: Ma		Tow	n OH	IR NC).2		Project: WASA Master Plan				
_			Hole No							Fig No.				
B	ORE HOLE LOG		of Borin							Date Started: 13-12-2017				
			nination							Date Completed: 14-12-2017				
			ınd Wate	eriak	oie: 1		etrat	ion I		Logger: Umer				
		oqu					/alue				Re	cove	ry	
Depth(m)	Sample Description	Classification Symbol	Pegend	Sample Type	Moisture	150	150 mm	150	N-Values	N- Profile 0 20 40 60 80 100	SPT (cm)	CR %	RQD %	Remarks
2	clay	CL		DS		4	5	7	12		25			
4	Clayey Silt	ML		DS		5	7	10	17		30			
6	Silty sand	SM		DS		11	14	16	30		35			
8	Silty sand	SM		DS		10	16	17	33		22			
10	Fine graind sand	SW		DS		9	10	12	22		31			
12	do	SW		DS		15	15	21	36		33			
14	do	SW		DS		11	14	18	32		28			
16	do	SW		DS		15	10	22	32		30			
18	do	SW		DS		15	17	21	38		30			
20	do	SW		DS		13	17	18	35		28			
22	do	SW		DS		9	29	45	74		27			
24	do	SW		DS		22	34	35	69		33			
26	do	SW		DS		12	18	35	53		27			
28	do	SW		DS		18	28	37	65		27			
30	Medium graind sand	SW		DS		20	31	42	73		35			
32	do	SW		DS		30	41	50	91		35			
34	do	SW		DS		29	42	47	89		48			
36	Med-course sand	SW		DS		30	37	49	86		28			
38		SW		DS		30	33	35	68		26			
١	do	SW		DS		32	35	40	75		22			
Che	cked By:													



University of Engineering & Technology, Lahore Department of Civil Engineering Geotechnical Engineering Laboratory

SUMMARY OF THE TEST RESULTS

Geotechnical Investigation for WASA Master Plan, Faisalabad

Project:

Client: M/S ECOS Ltd

BH/ TP No.	Sample No	Depth (m)	NMC (%)	Bulk Density (kN/m³)	Specific Gravity G _s
	1 (UDS)	-	21.68	19.21	2.7
	2 (UDS)	7	25.05	18.64	2.67
	3 (NDS)	14	17.96	14.55	2.65
-	4 (UDS)	19	18.27	16.08	2.67
-0-La	(SOD)	25	24.24	20.55	2.65
	(SQN) 9	30	23.88	15.74	2.66
	(Sau) 7	35	25.17	13.48	2.69
	8 (NDS)	40	17.67	15.90	2.68
	(SQN) 6	က	9.61	20.48	2.7
	10 (UDS)	7	7.50	18.93	2.67
	11 (UDS)	15	7.32	16.97	2.67
00	12 (UDS)	20	4.32	16.31	2.66
70-110	13 (UDS)	25	17.34	19.79	2.65
	14 (UDS)	30	27.66	18.30	2.67
	15 (UDS)	35	14.41	12.48	2.67
	16 (UDS)	40	19.27	18.44	2.65

