



**Republic of Indonesia, Ministry of Public Works
Directorate General of Water Resources**

**Indonesia
Expert Dispatch Scheme
Dam Design and Construction
Advisory Services**

**Completion Report
Supporting Report 3
Establishment of Risks Management System
in Dam Construction**

**Study on
"The necessity and Methods of Risk Management"
(presented in Workshop, INACOLD Seminar in 2023/2024)**

February 2025



Japan International Cooperation Agency



**CTI Engineering International Co., Ltd.
CTI Engineering Co., Ltd.**

GE
JR
25-047



**Republic of Indonesia, Ministry of Public Works
Directorate General of Water Resources**

**Indonesia
Expert Dispatch Scheme
Dam Design and Construction
Advisory Services**

**Completion Report
Supporting Report 3
Establishment of Risks Management System
in Dam Construction**

**Study on
"The necessity and Methods of Risk Management"
(presented in Workshop, INACOLD Seminar in 2023/2024)**

February 2025



Japan International Cooperation Agency



**CTI Engineering International Co., Ltd.
CTI Engineering Co., Ltd.**

Preface

We, JICA Dam Advisors, have been assessing the risks that have arisen in ongoing dam construction projects in Indonesia for two years. Based on the results of this assessment, we confident the necessity of "the Risk Management in Dam Design and Construction" to minimize the risks in dam construction. This idea was presented in the workshops as "Dam Risk Management" at the INACOLD Seminars 2023 and 2024.

The study has been carried out as following process:

- 1) Definition of risks in dam construction
- 2) Risk Analysis of Ongoing Dams in Indonesia: Preparation of a database and their analysis including several studies
- 3) Approach to application of "Dam Risk Management" in Indonesia

Currently, in Indonesia, to ensure the safety of dams, the Dam Safety Committee (KKB) and its unit conduct technical reviews at each stage of dam design, impoundment, and operation. This system is working very effectively.

However, during our visit to the dam construction site, we found that many risks have arisen at the site due to design oversights and misinterpretation of geological structures.

Dam construction is inherently risky because of the uncertainties and diverse factors involved in dam projects. To minimize risks in dam construction, it is believed that the current inspection system by the Dam Safety Committee and the introduction of a "risk management system" into local design and construction would be effective.

In the future, we wish that PU (DSC, DSU, BTB) will continue an activities discussing and establishing system how to improve the dam construction situation in Indonesia.

February 2025

Team Leader

Hiroshi SHIMIZU

Establishment of Risks Management System in Dam Construction
Follow up Study on "The necessity and Methods of Risk Management"
presented in Workshop, INACOLD Seminar in 2023 and 2024.

Table of Contents

PART 1	DAM RISKS IN DAM DESIGN & CONSTRUCTION.....	1-1
1.	BACKGROUND OF THE STUDY.....	1-1
1.1	Current Situations of Indonesian Dam Construction.....	1-1
1.2	Dam Safety Organization in Indonesia.....	1-2
2.	RISK MANAGEMENT IN DAM DESIGN AND CONSTRUCTION.....	1-3
2.1	Necessity of Risk Management in Dam Project.....	1-3
3.	DEFINITION OF DAM RISK.....	1-4
3.2	Basic Policy on Risk Management.....	1-5
3.3	Approach to Establishing Risk Management System in Dam Construction Projects.....	1-6
3.4	Effects Expected by "Risk Management".....	1-6
3.5	Utilizing of Dam Risk Database in Risk Management.....	1-6
3.6	Risk Factor: Human-Errors (Examples in Japan).....	1-7
3.7	Proposal of Establishment of Risk Management System in Indonesia.....	1-8
PART 2	Risks Analysis in Dam Projects	2-1
1.	METHOD OF RISK ANALYSIS.....	2-1
2.	COLLECTION AND ORGANIZATION OF CASES IN INDONESIA.....	2-1
2.1	Dam Risk Entry Form.....	2-2
2.2	Summarizing Recognized Risks.....	2-4
2.3	Assessment of Results of Risk Analysis.....	2-5
2.4	Findings.....	2-7
PART 3	Establishment of Dam Risk Management System.....	3-1
1.	INITIATIVES IN JAPAN IN RISK MANAGEMENT IN CIVIL ENGINEERING PROJECT.....	3-1
1.1	Background of Japanese Guideline.....	3-1
1.2	Concept of Risk Management Guideline.....	3-1
1.3	Basic Policy for Preparation of Guideline.....	3-2
1.4	Focus Points.....	3-2
1.5	Application of ISO31000 Risk Management.....	3-2
2.	IMPLEMENTATION METHOD OF RISK MANAGEMENT IN PROJECTS.....	3-3
2.1	General.....	3-3
2.2	Implementation Procedures.....	3-3
2.3	Contents of Each Step.....	3-3
2.4	Organizing Risk Management Team.....	3-5
2.5	Timing of Risk Management.....	3-7
2.6	Configuring the System in Other Countries (reference).....	3-9
3.	ESTABLISHMENT OF INDONESIAN DAM RISK MANAGEMENT GUIDELINE.....	3-8
4.	CONCLUSION AND RECOMMENDATION.....	3-10
PART 4	Considerations on Geological Issues in Each Phase.....	4-1
1.	INTRODUCTION.....	4-1
1.1	Background and Purpose of This Study.....	4-1
1.2	Define and Identify Risk.....	4-1

1.3 Geological Risk Factor (Georisk Factor)	4-1
2. CONSIDERATIONS FOR EACH PHASE	4-2
2.1 Planning & Preliminary Design	4-2
2.2 Detailed Design.....	4-8
2.3 Construction.....	4-22
2.4 Operation.....	4-27
3. ENGINEERING SENSE	4-29
3.1 Perspective and Imagination	4-29
3.2 Integrated interpretation.....	4-30

Attachments

Attachment 1	Dam Safety System in Indonesia: Dam Safety Commission
Attachment 2	Completed Dam Risk Entry Form
Attachment 3	Minutes of Discussion on Dam Risk Management

PART 1 DAM RISKS IN DAM DESIGN & CONSTRUCTION

1. Background of the Study

Indonesia is a country habitually suffered with water-related disasters due to its fragile volcanic geology and frequent floods caused by torrential rain, like Japan. In response to these disasters, the GOI has been constructing multi-purpose dams with technical assistance from foreign countries since the 1960s.

According to Rencana Strategi 2020-2024 (current plan), 61 dams are proposed in five years from 2015 to 2024. More than 20 dams have already been completed and 13 dams will be completed in this year. In addition, 11 new dam projects are planned to be implemented.

Most of the dam projects are handled by Indonesian engineers in survey, planning, design and construction stages taking advantage of past experience in the dam construction. However, at the dam construction sites, many issues on design, geological judgment and construction methods have arisen, and it has been confirmed that there are many cases in which these problems have not been dealt with appropriately.

In response to this situation, GOJ/JICA has dispatched the dam construction advisors to the Indonesia to support an improvement of the quality of dam construction in the Indonesia, in accordance with the request of the Government of Indonesia.

In the activities of the Advisors, the advisors have recognized that the lack of risk management at sites. This has convinced of the importance of a system for awareness, identifying and responding to risks during the design and construction stages.

1.1 Current Situations of Indonesian Dam Construction

More than 200 dams have been constructed in Indonesia in cooperation with Japan and other countries. Indonesian dam engineers have accumulated experience in these cooperation projects and inherited their skills. In recent years, most of the dams have been constructed by the Indonesian Engineers themselves and have been facing to many problems and settled them but there have been issues cannot be adequately addressed.

In order to timely and appropriately aware the various risks that need to be taken into account in safely and smoothly implementing dam projects, it is essential to establish "Techniques/Systems for awareness and dealing with risks in dam projects".

Indonesia has an approval application system for dam construction, where information and data on dams proposed for construction, impounding, operation and damage/repair are submitted to the Dam Technical Centre (Balai Teknik Bendungan, BTB) for each approval application. And the results of DSU technical review and DSC comments are also stored in BTB, so it is possible to browse basic information from that BTB.

Since these documents are digitized at the time of application for review, they will be obtained from BTB as information at each review stage.



Location of Objective 61 Dams (Progress as of Dec 2024)

1.2 Dam Safety Organization in Indonesia

As stated in Ministerial Regulation Number 72/PRT/1997, in order to carry out the dam safety, Minister of Public Works and Housing has been assisted by dam safety organization consisting of Dam Safety Commission and Dam Safety Unit.

The DSC and DSU have been monitoring the works at site and making comments and giving advises to settle issues occurred in the works. For details of their activities, see Appendix 1.

(1) Dam Safety Commission (DSC)

Dam Safety Commission (DSC) provides recommendation and suggestion to the minister. The tasks of dam safety commission are as follow:

- Giving the recommendation about dam safety to the minister in every phase of dam development such as design, construction, operation, rehabilitation, and dam closure.
- Evaluating Dam Safety Unit activities in order to suggest to the minister
- Preparing the accountability report to the minister

(2) Dam Safety Unit (DSU, under SDA-PU)

Main duty of Dam Safety Unit is to provide technical support to DSC as below:

- Analyzing and evaluating dam safety in every phase of dam development such as design, construction, operation, rehabilitation, and dam removal.
- Collecting and managing data of dam
- Inspecting dam in order to analyze dam behavior to evaluate the safety of the dam

(3) Risk Assessment in Indonesia

To avoid the dam risks, following “Risk Assessment” has been recommended to carry out in Indonesia.

(a) Risk Assessment at Feasibility Study Stage

Risk assessment at the feasibility study stage is very important for high-risk dam construction activities. Based on UURI No. 24 of 2007 and PP No. 21 of 2008, disaster risk analysis must be carried out for dams with a high hazard class. The hazard risk is influenced by the probability of dam failure and the impact of the failure, which can cause losses due to flooding downstream. Risk identification is carried out through topographic maps and local data, although flood inundation information is often not available at this stage. The main risks faced include floods, earthquakes, and seepage.

(b) Risk Assessment at the Detailed Design Stage

At the detailed design stage, a risk assessment is conducted to deepen the analysis that has been done at the feasibility study stage. More complete data allows for a more accurate risk assessment, including dam failure analysis. This assessment helps in making decisions regarding safety and improving the dam design.

(c) Risk Assessment at the Management Stage (Operation and Maintenance)

Risk assessment at the management stage aims to evaluate the risk profile and determine whether the risk is tolerable. If not, risk reduction options need to be planned. Risk assessment is also used to compare risks between several dams in the portfolio, assisting in prioritizing dam rehabilitation. An example of a dam that has undergone risk assessment at this stage is the Cirata Hydroelectric Dam.

(d) Risk Assessment at the Dam Removal Stage

Before removing the dam function, a risk assessment needs to be carried out to identify potential hazards and consequences of various treatment options. An example of a risk assessment at this stage is carried out on the Namuk Dam.

(e) Dam Risk Assessment Frequency

For dams that are already in operation, risk assessments need to be conducted periodically, recommended every 10 years, especially for dams with a height above 75 m or large storage volume. This aims to ensure that the risk remains within the tolerance limit and does not threaten the safety of the dam.

2. Risk Management in Dam Design and Construction

2.1 Necessity of Risk Management in Dam Project

Dam is constructed by maximum use of the regional geology, climate, and natural resources. Planning, design, and construction of dam are forced to carry out in the face to

nature that is difficult to control, so there are almost always many issues that arise during construction stage.

In response to these challenges, dam engineers need to:

(1) Design Stage:

To predict risks that may arise during construction and operation in advance as much as possible and reflect them in the design.

(2) Construction Stage,

To establish a system that allows for rapid and timely response.

In order to promote awareness of these issues, one effective method would be to create a database of issues that have occurred at construction sites and how to deal with them, and a system that allows access to past cases.

If engineers are able to recognize expected risks during investigation and design, communicate with experts, and prepare countermeasures, the quality of the design will improve and risks will be avoided during construction.

3. Definition of Dam Risk

Prior to the discussion, it is important to point out that the Dam Risk to be presented herewith is different from the risk of dams in ICOLD.

(1) ICOLD

Since the mid-1990s, ICOLD has been discussing dam risk assessment in light of factors such as the aging of dams, the application of risk analysis to the nuclear and aircraft industries, and responses to climate change. However, the majority of papers focused on risks related to safety assessment of existing dams, rather than issues occurring in design and construction stage. After further discussions, in 2003 ICOLD published the "ICOLD BULLETIN Risk Assessment in Dam Safety Management".

ICOLD defines dam risk in its Bulletin as follows.

"The degree of probability and significance of an undesirable impact on human life, health, property or the environment. In the general case, risks are estimated by scenarios, probabilities of occurrence and consequences. In special cases, the average risk is It is estimated by the mathematical expectation of the outcome of an event (the product of the probability of occurrence and the outcome combined across all scenarios).

And also, the term "Dam Risks" in the ICOLD is defined as "the risk of dam collapse or malfunction that may occur after the construction of a dam."

- The term risk when used in the context of dam safety is comprised of following three parts:
 - ✓ the likelihood of occurrence of a load (e.g. flood, earthquake, etc.),
 - ✓ the likelihood of an adverse structural response (e.g. dam failure, damaging spillway discharge, etc.), and
 - ✓ the magnitude of the consequences resulting from that adverse event (life loss, economic damages, environmental damages, etc.).

- Risk and Hazard: The definitions of risk and hazard given in the glossary are:
 - ✓ Risk: Measure of the probability and severity of an adverse effect to life, health, property or the environment.
 - ✓ Hazard: A threat or condition that may result from either an external cause (e.g. earthquake, flood or human agency) or an internal vulnerability with the potential to initiate a failure mode. A source of potential harm or a situation with the potential to cause loss.

Risk is a measure of the probability and severity of an adverse effect on life, health, property, or the environment.

In general, risk is estimated by combining the impact of all three combinations: scenarios, probabilities, and associated consequences. As a special case, the average (annual) risk can be estimated by the mathematical expectation of the outcome of an adverse event occurring (i.e., the combined probability and consequences across all scenarios).

(2) US Army

Risk is a function of three components:

- The potential hazards or future loading,
- the dams performance given that loading and
- the consequences of a dam breach if the dam does not perform as intended.

Potential hazards include large regional floods, earthquakes, landslides, rapid pool fluctuations, and other events. The expected performance of the dam is evaluated based on criteria used at the time of its design, construction documentation, historical performance, site investigations and advanced analysis. Consequences are estimated based on computer simulations of flood inundation extents, flood wave arrival times, warning times, the time of day at breach, and other factors.

(3) This Study

The risks to be discussed in this "Dam Risk Management System" are defined as "risks that arise during dam surveys, design, and construction. By identifying these risks in advance and taking measures to the greatest extent possible, we aim not only to ensure the safety of the dam after completion, but also to prevent accidents, delays, and rising construction costs during the construction period."

This is a proactive approach and different from the ideas of ICOLD and US Army.

3.2 Basic Policy on Risk Management

The risk management for dam project proposed here is a strategic approach to predict and minimize risks during design and construction. It can be clarified and evaluated risks and determining response policies.

The following points should be considered when implementing:

- ✧ To correctly grasp possible risks and their characteristics at each stage of conception/planning, investigation, design, construction, and maintenance, and respond at the most appropriate time
- ✧ To correctly grasp risks and their characteristics based on information available at each stage and process of the project, and information obtained by additional surveys, etc. as necessary

- ◇ To respond at the most appropriate project stage or process depending on the characteristics of the identified risks
- ◇ To implement risk management continuously in consideration of how to respond to risks, including reviewing organizations and structures, taking into account at which stage it is optimal to respond to risks

3.3 Approach to Establishing Risk Management System in Dam Construction Projects

Following considerations were carried out as preparatory work for establishing a risk management system in dam construction projects.

- a. Collection and organization of Risks arising in Dam Projects
- b. Proposal of a risk management system
- c. Considerations for Risk Management for Dam Construction Project in particular practical geological issues

3.4 Effects Expected by “Risk Management”

In order to ensure the efficient implementation and safety of civil engineering projects, including dam projects, handling and response to the risks which are overlooked or unrecognized risks in particular geological risks, which used to be tacit knowledge, should be presented as explicit knowledge as much as possible, and risks should be appropriately evaluated. It is effective to introduce risk management system, which involves taking the optimal response. This can be expected to address the lack of experienced personnel and reduce human errors.

In addition, it is known that significant benefits can be expected if the appropriate timing for risk management is selected according to the type of risk. In particular, it has been confirmed that if risk management is carried out at the investigation and design stage, risks that occur during construction can be significantly reduced.

To avoid such human error risks, it is well known that Risk Management is functioned effectively.

Expected effects are;

Effect 1: Adequate Response to Risks in Advance

It is difficult to ensure the efficient and safety of dam Projects, since the uncertainty issues or geological issues has been handled depending on the experience of field engineers.

Effect 2: Appropriate Evaluation of Uncertain Risks

Supporting the lack of experienced personnel and reducing human errors.

Effect 3: Appropriate Timing for Risk Response

Conducting the risk response in appropriate timing (during survey and design stages), arising risks (during construction stage) can be significantly reduced.

3.5 Utilizing of Dam Risk Database in Risk Management

Database of Risk Cases that have occurred in past dam projects, can help reach a cases and common consensus on dam risks. To accumulate such risk Information, data shall be shared among the Engineers and reconfirm or update them at each phase (planning, investigation, design, construction and maintenance).

And such Database will help, in particular, to achieve early awareness of risks, reduction of oversight of risks, and rational response to risks in "Risk Management in dam construction projects".

3.6 Risk Factor: Human-Errors (Examples in Japan)


During project implementation, due to unexpected troubles/issues occurred at construction sites, a number of problems have occurred, such as accidents during construction, delays of construction work, increases in construction costs, and malfunctions after operation started.

To clarify the cause of such issues, in Japan, information from construction sites had been accumulated, analyzed, and assessed. It was verified that "Natural Factors" account for 20% of the overall issues, while "Human Factors" account for 80%.

As shown in this assessment results Project owner, Consultant and Contractors must recognize that "Human Factors play an important role in the occurrence of risk and to avoid such risks is own responsibility".

So, looking at the results of the assessment on risks of civil engineering projects in Japan, it is found that many risks can be prevented by:

- a. recognizing risks during planning and design stages and
- b. considering how to deal with them in advance (before construction starts) .



Risk Factors in Japanese Infrastructure Project (Geological Issues)

Risk Factors	Details of Risk Factor	Number	Sub-Total	Percentage
<i>Risk factors that are difficult to avoid</i>				
Geology difficult to Predict or Understand	Difficult to predict where risk will occur	2	15	20.0%
	Difficult to predict when risk will occur	10		
	Heterogenous and irregularity geology	3		
<i>Risk factors that are considered to be human-caused</i>				
Error in interpretation or engineering judgment	Overlooking risks related to terrain	11	30	40.0%
	Overlooking risks related to geological structure/characteristics	10		
	Insufficient investigation and evaluation of soil properties	1		
	Misjudging terrain risks	3		
	Misidentification of risk signs (events)	3		
	Misidentification of risks related to geological structures	2		
Lack of knowledge	Unsuitable design for geological conditions	1	3	4.0%
	Inappropriate Construction	2		
Lack of Quality and Quantity of Geotechnical Survey	Geological survey not conducted	7	20	26.7%
	Inadequate investigation plan	10		
	Insufficient accuracy of topographic maps	3		
Inadequate information sharing and communication regarding risks		5	5	6.7%
Inappropriate Construction (Prioritize cost and schedule)		2	2	2.7%
Total		75		100%

Source : Guidelines for geological and Foundation risk management in civil engineering projects ; 2020, MLIT (Ministry of Land, Infrastructure, Transport and Tourism) with PWRI (Public Works Research Institute)

3.7 Proposal of Establishment of Risk Management System in Indonesia

As mentioned above, many of the issues that arose at dam construction sites are due to human error and can be avoided in advance. Furthermore, it is considered that knowledge of past cases will enable quick and appropriate responses when problem occurred at the site. Therefore, by creating a database of past events that occurred during dam construction and building a risk management system that can utilize this database, it is expected that future dam construction in Indonesia will become safer and more efficient.

PART 2 Risks Analysis in Dam Projects

In order to prepare a dam risk database, 100 cases of issues that arose during the construction period and concerned by DSC as problematic issues in the 61 on-going dams were extracted and compiled, then analyzed and assessed in the type and location of the issues, their causes, and responses.


1. Method of Risk Analysis

Based on dam design documents and materials for technical session submitted to the Dam Safety Commission, 100 risk cases were extracted and assessed for 61 dams across Indonesia. However, it should be noted that the information is mainly limited to the DSC's comments made during technical sessions and site inspections, so that the amount of information is limited.

In sorting out the 100 risk cases, a format was filled for each identified risk. The items classified in this form were sorted into:

- 1) Risk factors,
- 2) Situation (location, occurrence), and
- 3) Response and problematic items.

These results will provide valuable information for identifying risks involved in proceeding with dam projects in Indonesia.



Example of Database Format

Note: In this case, during foundation excavation, it was found that the colluvium was distributed at a much thicker than estimated thickness at the time of design, raising concerns about the insufficient strength of the dam and spillway foundations and the leakage/piping through the colluvium.

However, it was not possible to judge accurately whether the cause of the risk occurrence was human-related or not based on the collected data like Japanese assessment case (for example, insufficient amount of investigation, insufficient technical ability, experience and knowledge of the engineers in charge, inadequate management, etc.).

This entry form need be confirmed by engineers at each dam construction site who will know how the issue arose.

2. Collection and Organization of Cases in Indonesia

This study compiled major issues occurred at site and assessed possible risks at Indonesian dam construction sites, based on the results of reviews, inspections and

discussions conducted by the Dam Safety Committee for dams completed or under construction since 2015.

2.1 Dam Risk Entry Form

The collected risk data was compiled in “Dam Risk Entry Form” shown in right figures. The completed form prepared in this survey is attached as Attachment 2. For reference, The Example of filling the form is shown in the following page:

Table-1

When the risk was recognized	When the risk was recognized
1. Project phase in which risks were recognized	1. Cause
2. Location (Structure/Area)	2. Part of hazard
3. Content of risk	3. Part of hazard
4. Risk source	4. Part of hazard
5. Event in which risks were recognized	5. Part of hazard
6. Condition/Reason for risk realization	6. Part of hazard
7. Impact of the risk realization	7. Part of hazard
8. Other Job items	8. Part of hazard

Risk factors, categories, etc.

Risk realization process and response

Event	Response
1. Risk realization	1. Risk realization
2. Risk realization	2. Risk realization
3. Risk realization	3. Risk realization
4. Risk realization	4. Risk realization
5. Risk realization	5. Risk realization
6. Risk realization	6. Risk realization
7. Risk realization	7. Risk realization
8. Risk realization	8. Risk realization
9. Risk realization	9. Risk realization
10. Risk realization	10. Risk realization
11. Risk realization	11. Risk realization
12. Risk realization	12. Risk realization
13. Risk realization	13. Risk realization
14. Risk realization	14. Risk realization
15. Risk realization	15. Risk realization
16. Risk realization	16. Risk realization
17. Risk realization	17. Risk realization
18. Risk realization	18. Risk realization
19. Risk realization	19. Risk realization
20. Risk realization	20. Risk realization
21. Risk realization	21. Risk realization
22. Risk realization	22. Risk realization
23. Risk realization	23. Risk realization
24. Risk realization	24. Risk realization
25. Risk realization	25. Risk realization
26. Risk realization	26. Risk realization
27. Risk realization	27. Risk realization
28. Risk realization	28. Risk realization
29. Risk realization	29. Risk realization
30. Risk realization	30. Risk realization
31. Risk realization	31. Risk realization
32. Risk realization	32. Risk realization
33. Risk realization	33. Risk realization
34. Risk realization	34. Risk realization
35. Risk realization	35. Risk realization
36. Risk realization	36. Risk realization
37. Risk realization	37. Risk realization
38. Risk realization	38. Risk realization
39. Risk realization	39. Risk realization
40. Risk realization	40. Risk realization
41. Risk realization	41. Risk realization
42. Risk realization	42. Risk realization
43. Risk realization	43. Risk realization
44. Risk realization	44. Risk realization
45. Risk realization	45. Risk realization
46. Risk realization	46. Risk realization
47. Risk realization	47. Risk realization
48. Risk realization	48. Risk realization
49. Risk realization	49. Risk realization
50. Risk realization	50. Risk realization

Risk Situation

Table-2

Project Phase	Project Phase
1. Project Phase	1. Project Phase
2. Project Phase	2. Project Phase
3. Project Phase	3. Project Phase
4. Project Phase	4. Project Phase
5. Project Phase	5. Project Phase
6. Project Phase	6. Project Phase
7. Project Phase	7. Project Phase
8. Project Phase	8. Project Phase
9. Project Phase	9. Project Phase
10. Project Phase	10. Project Phase
11. Project Phase	11. Project Phase
12. Project Phase	12. Project Phase
13. Project Phase	13. Project Phase
14. Project Phase	14. Project Phase
15. Project Phase	15. Project Phase
16. Project Phase	16. Project Phase
17. Project Phase	17. Project Phase
18. Project Phase	18. Project Phase
19. Project Phase	19. Project Phase
20. Project Phase	20. Project Phase
21. Project Phase	21. Project Phase
22. Project Phase	22. Project Phase
23. Project Phase	23. Project Phase
24. Project Phase	24. Project Phase
25. Project Phase	25. Project Phase
26. Project Phase	26. Project Phase
27. Project Phase	27. Project Phase
28. Project Phase	28. Project Phase
29. Project Phase	29. Project Phase
30. Project Phase	30. Project Phase
31. Project Phase	31. Project Phase
32. Project Phase	32. Project Phase
33. Project Phase	33. Project Phase
34. Project Phase	34. Project Phase
35. Project Phase	35. Project Phase
36. Project Phase	36. Project Phase
37. Project Phase	37. Project Phase
38. Project Phase	38. Project Phase
39. Project Phase	39. Project Phase
40. Project Phase	40. Project Phase
41. Project Phase	41. Project Phase
42. Project Phase	42. Project Phase
43. Project Phase	43. Project Phase
44. Project Phase	44. Project Phase
45. Project Phase	45. Project Phase
46. Project Phase	46. Project Phase
47. Project Phase	47. Project Phase
48. Project Phase	48. Project Phase
49. Project Phase	49. Project Phase
50. Project Phase	50. Project Phase

Risk response history

Special Notes

Keyword

References

Dam Risk Entry Form

Filling Example of Dam Risk Entry Form

ID:	Name: Bagong	Dam Type: Rock-fill dam with central core	Dam Height: 82.0 m
Contents of Risk	1	When the risk was identified (date)	7-Jul-22
	2	Project phase in which risks were recognized	Construction
	3	Location (Structure/Area)	Dam / Foundation, Spillway / Foundation
	4	Contents of risk	Instability of the foundation, Piping of the foundation
	5	Risk factors	Sliding of colluvium (rock mass sliding) used as foundation, Unequal settlement
	6	Events in which risks were recognized	Sliding of the right bank cut slope occurred during the foundation excavation
	7	Condition/Situation for risk realization	Foundation deterioration over time, Impounding, Heavy rains, Earthquakes
	8	Impact if the risk realize	Dam breach causing flooding downstream, Damage to spillway
Perspectives on Risk Classification	9	Where risk exists	Geology / Strength, Perm eability, Design / Foundation treatment
	10	Character*1	B: Mainly due to technical factors
	11	Phase of Realization*2	II : Operation, III : Due to large-scale external force action, IV: Due to long-term use
	12	Impact if the risk realize*3	S: Affects dam safety / F: Affects dam function
	13	Corresponding to risks*4	a: Basically risk avoidance
Overview of Causal Relationships			
Explanatory Diagram (Schematic Diagram/ Photos, etc.)			
	<p>Figure-1 Right bank geologic cross section based on additional survey results</p>		

ID:	Name: Bagong	Dam Type: Rock-fill dam with central core	Dam Height: 82.0 m
History	Recognition or not in the past	Unrecognized	
	When the risk was recognized	Project Phase: Construction	Date: 7-Jul-22
	Status of corresponding	Considering countermeasure methods	
Project Phase	History of correspond to risks		
Plan	Design	<p>The design was to use bedrock as the foundation.</p> <p>As the distribution of thick colluvial soil was confirmed during foundation excavation, the use of colluvial soil as the foundation is being considered.</p>	
	Construction	<p>Figure-1 Dam axis geologic cross section (During investigation/design)</p> <p>Figure-2 Geological cross section of the dam axis (Site plan after additional investigation)</p>	
Investigation /analysis	Investigation/analysis to identify factors, etc.	-	
	Research/analysis, etc. to assess impact	-	
How to respond to risk	Analysis, etc. to determine the need for and methods of response	-	
	Contents of measures (avoidance, reduction, transfer) or retention	Reduction	
Special Notes	Measures	How to deal with	<Foundation Treatment> Spillway: Pile foundation+Secant Pile Dam: Secant Pile
	Reason (no measures)	Basis for decision	Ground conditions, Construction cost
	Availability and method of monitoring	Reason	-
	Availability and method of information sharing	Expected impact	-
Applicable standards	<p>Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.</p> <p>1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.)</p> <p>The geological conditions at the dam site differed significantly between the geological investigation/design and construction phases. The following risks should be considered once again when adopting the current countermeasure plan.</p> <p>1) Sliding along the boundary between the collapsed soil and bedrock 2) Piping at the foundation where the spillway meets the dam due to unequal settlement</p>		
	Keywords	(Describe standards related to geological study, dam design, and countermeasure design.)	
References	Meeting Minutes:	2023.09.21 RDTSpillway Bagong [Z-AF]+ CL (rev), Cap 226-KKB Laporan Inspeksi dim rangka Pelaksanaan Konstruksi B. Bagong	
	Meeting Materials:	Papanar BTB shimita	
	Other:	LAPORAN AKHIR STUDY/NEOTEKNIK, Laporan Progress Pengolahan hasil MAS W	

2.3 Assessment of Results of Risk Analysis


In order to understand the trends of risks that may arise in dam construction projects in Indonesia, we checked the frequency of occurrence of events for each item such as Risk Factor, Risk Location, Risk Content, Risk triggers, natural or human factors, and so on.

2.3.1 Risk Factor

Risk factors means factors that have the potential to realize a risk.

The results of risk analysis on Risk Factor, revealed that more than 60% of the risks at dam sites were related to the geology, including embankment materials, while 20% were related to design and construction management, and 3% were due to external factors such as floods and earthquakes.


Of the internal factors, approximately 70% are design related.



2.3.2 Location of Risk Occurs

Risks observed in almost all areas of dam construction site, and the cause is largely related to geology.


Approximately 50% of the risk factors are identified in the dam body, foundations and materials, with the rest in spillways, tunnels and reservoirs.



2.3.3 Type of Risk

The risks are mainly classified into four types:

- Water leakage and spring water (from dam foundation, dam body, tunnel and other structures),
- Deformation (foundation, dam body (in particular core zone), tunnels and other structures including sliding at structural foundation),
- Landslides (collapse of natural slopes and cut slopes), and
- Erosion at waterway.



The percentage of each type is as shown in right figure and three types of risks, namely Leakage, deformation and Landslide, account for just under 90% of the total.


2.3.4 Trigger: Human -related Factor

Risk triggers can be classified into natural and human factors. Natural factors include weather and earthquakes or unforeseen events, human factors include inadequate engineering and management judgement.

Through this study, it was assumed that most of risks (classified as Human-related factor) can be avoided (94%) in case carrying out adequate survey and design.

During each stage of survey and design, therefore, risk analysis and assessment, namely "RISK Management" should be conducted to recognize the potential risks and respond them.


Furthermore, It is expected that risks can be avoided or mitigated as each engineer accumulate their experience and improves their technical capabilities.



2.3.5 Risk Similarity

Many of the risks observed in each dam construction site are similar, so the risks were categorized and analyzed according to their similarities as follows:

- ◇ Risks that can be recognized at other sites
 - High: Response methods have been established.
 - Middle: Response methods have not been established or responses vary from site to site
 - Low: Risks that be expected difficult
(only similar topographical and geological conditions, etc.)



- ◇ Risks that arise due to special conditions at each site (special dam operations, etc.)

60% of the identified risks are similar to risks identified at other sites, so It is expected that risks will be respond efficiently based on similar risk cases.

40% of the identified risks are due to the characteristics of the site.

The goal is to respond to the risks efficiently by applying "learned from risk analysis".


2.3.6 Results of Response to Risk

Of the recognized risks, 46% are avoided, 30% are reduced, and 24% are retained.

Each term is defined as follows:

- ✧ Avoidance refers to redesign and providing countermeasures,
- ✧ Reduction refers to mainly repairs, and
- ✧ Retention involves only monitoring.

Even if these risks can be addressed after completion, it is essential that risks are eliminated before the dam is completed.




2.3.7 Project Phase for Risk Response

Most of the risk cases organized in this study were identified during the construction and operation phases, but from the perspective of risk management, many of them are better to identify ideally during the DD phase.

Because the cost of avoiding or reducing risks depends on the project phase. By identifying risks in an early phase and handling them at the appropriate phase, it is often possible to avoid increased costs.

By reassessing the project phase in which the risks collected this time could be addressed based on our opinion, it can be judged that more than 80% of the risks can be addressed during the survey, design, and construction phases.



Note : "Ideal" refers to a reevaluation result of events in construction stage whether it could be dealt with during planning and design stages.

2.4 Findings

Through the assessment of the dam risks occurred in Indonesian on-going dams, followings were founded:

- ✧ Geological Risks : more than 60%

- ◇ Importance of appropriate geological surveys, improvement of the capabilities of geological engineers and advice from experienced engineers.
- ◇ Most Risks are due to Human Factors (insufficient investigation, misinterpretation of geology, inappropriate design, etc.)
- ◇ Improve the capabilities of dam engineers and have experienced engineers' review.
- ◇ Of the identified risks, approximately 60% were Similar Risks that were observed in other dams.
- ◇ If risks are recognized earlier, measures can be taken .
- ◇ 55% of risks were Recognized during Construction Stage and 44% after completion.
- ◇ More than 50% of risks can be recognized at the time of survey and design stage. Many risks can be prevented if risks are recognized.

PART 3 Establishment of Dam Risk Management System

According to the results of risk analysis compiled here, the majority of risks in dam construction are caused by human related factors. In other words, if risks are recognized and addressed at the survey, design, and construction management stages, a significant number of risks occurring on-site can be prevented.

One method for achieving this is to introduce a risk management system.

There is a view that Risk Assessment is highly valuable as an supporting tool in decision-making regarding dam safety, and as a meaningful method of decision-making from both safety and economic standpoints when deciding on the modification/upgrading of existing dams or the development of new dam projects, and it is hopefully expected that risk assessment would be implemented in Indonesia's dam projects, in particular planning and design stages, in future. And such risk assessment should be conducted the engineer in charge of the work inviting experts.

To achieve this, it is essential to establish an organization and to prepare the guidelines for implementation.

1. Initiatives in Japan in Risk Management in Civil Engineering Project

1.1 Background of Japanese Guideline

In Japan, there are Damages/Accidents caused by Geological Issues in construction or after completion, same as in Indonesia, and many "Geological Risks", containing in dam projects, have been treated through so-called "Tacit Knowledge" of the well experienced engineers. However, currently, due to a "Lack of Experienced Engineers", it has become difficult to expect this.

Furthermore, Social Monitoring has become stricter, because of several issues at site such as serious accidents, cost increases, delay of schedule, and modification/change of projects. So "More Efficient Project Implementation" is required,

In response to this, in 2020, MLIT (Ministry of Land, Infrastructure, Transport and Tourism) with PWRI (Public Works Research Institute) published the "Guidelines for Geological and Ground Risk Management in Civil Engineering Projects"*1).

This guideline aims "to Eliminate Undesirable Elements" that occur during construction and management by conducting risk management for uncertain elements in the promotion of civil engineering projects.

1.2 Concept of Risk Management Guideline

The guideline was prepared based on the following concepts:

- ◇ To make clear Procedure of Risk Recognition
 - To manage risks in the Projects, firstly recognizing expected risks.
 - how to handle various risks in projects;
 - how to respond to them, as well as the structure and process of general risk management.
- ◇ Practical Uses of Risk Management System in Project

- Implementation Procedures of risk management in recognition of risks
- Methods and Notable Points that can be applied during implementation.

1.3 Basic Policy for Preparation of Guideline

This guideline has been prepared with the following objectives:

- a. To present the concept and basic ideas of risk management in civil engineering projects.
- b. To propose the roles and functions of the project office and related parties implementing risk management, as well as the ideal form of collaboration.
- c. To present the procedures and methodology for introducing and implementing geological/geotechnical risk management.
- d. To indicate points to note when implementing geological/geotechnical risk management.
- e. To refer to the concepts of ISO 31000 (Risk management - Guidelines) and apply them to civil engineering projects.

1.4 Focus Points

The guideline was prepared with a focus on the following two points:

- a. Impact of Uncertainties on Projects
 - Geology and ground are formed naturally, and their distribution and properties are nonuniformity and complex.
 - This uncertainty causes an impact on project safety, such as the occurrence of accidents.
- b. Handling of Uncertainties on Projects
 - It is necessary to evaluate risks after understanding the estimation and uncertainty of geological and ground conditions.
 - There is a need for a framework for stakeholders to recognize and share geological and ground uncertainties, and a mechanism for assessing the impact on projects and responding to risks.

1.5 Application of ISO31000 Risk Management

This guideline compiles the concepts of frameworks and procedures, as well as their introduction and operation, in accordance with the concepts of ISO 31000 (Risk Management - Guidelines).

Risk management for civil engineering projects, including dam projects, has not only a purpose to avoid unfavorable impacts such as accidents and losses, but also to obtain advantageous opportunities such as to select a geologically advantageous damsite or dam type.

ISO 31000 (Risk Management - Guidelines) also defines risk management as “Creating and Protecting Value.”

In other words, by creating an optimal plan and design for the entire project, we aim to create new value through efficient project Implementation so the goals of both are the same.

2. Implementation Method of Risk Management in Civil Projects

2.1 General

Risk management in projects is applied to various stages of the project and is implemented continuously throughout the project to optimize risk response. For this reason, it is necessary to establish clear policies not only for procedures such as risk assessment and risk response methods, but also for the operation of the management process, such as risk management planning, communication and discussion, and continuous improvement of management.



Therefore, the risk management will be implemented as shown in following ISO-31000 methodology.

2.2 Implementation Procedures

Risk management consists of the following five steps. By continually repeating this process for identified risks throughout the project, more effective results can be achieved.

- 1) Communication and consultation
- 2) Risk Management Plan
- 3) Risk Assessment
- 4) Risk Treatment
- 5) Continuous Improvement of Risk Management



2.3 Contents of Each Step

(1) Communication and Consultation

"Communication and Consultation" is the most important element in the risk management framework and process. It is important to continuously carry out "communication and Consultation" in the risk management process and keep risk awareness and response always up to date.

"Communication and consultation" consists of the following:

- a. Internal communication and discussion
- b. External communication and consultation

Notable Points for Communication and Consultation are;

- Carrying out communication continuously in Risk Assessment and Treatment,
- Estimating/Confirming the roles, abilities, and functions of those involved in system and organization,



- It should be conducted prior to drafting a risk management plan.

Specifically, it will be as follows:

- confirmation of the relationship and uncertainty of the performance required for the design and construction of a project or structure,
- reorganization of the potential of risks from performance of foundation, geological structure and other conditions which obtained from surveys and analysis, etc., and
- share an understanding of aware risks.

Although such discussion have traditionally been set up for process adjustments and project execution, it is important to have communication and discussions with a clear purpose, rather than simply sharing information.

(2) Risk Management Plan

Establishment of a Management Policies and Processes in advance applicable to all stages.

Policies and management processes will need to be Modified/Updated in accordance with actual conditions of each project stages.

When risk management at each stage is planned, followings shall be considered and confirmed;

- Purpose and Role of Risk Management at objective stage in the whole project and Relationship with other stages,
- Management Plan shall be In line with the overall policy.



(3) Risk Assessment

The purpose of risk assessment in dam project is to evaluate;

- a. What kind of results will occur as a result of the combination of the construction of dam with geological characteristics and other conditions or external forces, and
- b. What kind of impact will there be on the project?

In other words, risk assessment is a task that provides materials for determining risk responses and their priorities. It is necessary to grasp the estimated performance of the dam based on the limited information required for the design and construction or structure has been obtained, and the degree of uncertainty. It is also necessary to clarify the prerequisites for information such as investigations and analyses as materials necessary for judgment.



Of the tasks of risk assessment, investigations are not always carried out prior to risk identification and risk analysis. Sometimes, it may be carried out as a result of risk identification and risk evaluation, or when it is determined that additional investigations are necessary as an option for risk response.

In order not to overlook risks with large impacts, it is important to recognize risks at an early stage of the project, confirm the necessity, and carry out additional investigations and analyses.

(4) Risk Treatment

Risk response is the process of modifying recognized risks by avoiding, reducing, transferring, retaining, etc. Risk response is the process of making decisions on response policies, in which the characteristics of the risks evaluated in the risk assessment and the magnitude of their impact are compared with the risk criteria, and the optimal response option is selected and implemented.

As the business progresses, information on these recognized risks is updated, and as the design progresses, their content and magnitude change. For this reason, it is necessary to revise risk responses, such as (1) making the response measures in the previous stage more detailed, (2) changing the response policy, or (3) selecting the response measures for the remaining risks in the previous stage at that time. For this reason, it is important that risk response does not simply select the response measures for the risks, but also indicates the risk response status and the monitoring concept, including cases where the selection of the response measures for the risks is postponed.




(5) Continuous Improvement of Risk Management

It is important to continue Risk Management throughout the entire project and at each stage of the project, and it is necessary to consider reviewing the organization and system in line with progress.

For continuous improvement of Risk Management in the Project;

- a. Monitoring project progress, changes in external conditions, changes in risk information, and the current status of systems and organizations
- b. Conducting Reviews to determine whether appropriate responses can be taken.



**Proposed Process
Geological Risk Management**

It is also necessary to record the whole works to ensure that the information obtained through risk management and its results are shared and passed on.

3. Organizing Risk Management Team

3.1 Implementation Team

When implementing geological/ground risk management, the operator shall involve internal and external parties with the necessary skills and knowledge, and clarify the coordination system of these parties, their functions, roles, and responsibility divisions. shall be. In addition, all parties concerned shall confirm in advance the division of roles

and responsibilities of each person, and endeavor to ensure that they have the necessary abilities and functions to fulfill their assigned roles.


In dam risk management, close cooperation between each party is important as well as the roles and responsibilities of each party. In particular, because geological conditions in damsite and reservoir (mountain Area) are uncertain, unexpected situations often occur. In doing so, it is important to note that there are many cases in which work that was not initially set out is required, and in such cases, gaps in roles and responsibilities arise, such as insufficient communication of information or insufficient sharing of information regarding risks, leading to undesirable results. is necessary.

Therefore, it is important to work together on a regular basis, closely share information on risks, have a common understanding, and handle risks in a ONE-TEAM system.

3.2 Team Composition and Its Role

Right figure shows an example of the structure of the team involved in geological/ground risk management proposed in the Japanese Guideline. Since this is based on the general project of the MLIT, Japan, the system in Indonesia may be implemented with a different system, structure, and role division depending on the Indonesian project implementation system.

Since Dam Risks cover multiple specialized technical fields, it is basically handled by a team made up of related specialists according to the process. The following are examples of things that play a role as a team within a risk management system.



Risk identification team:

A team to extract and identify risks without overlooking them.

Risk analysis team:

A team that analyzes risks

Risk assessment team:

A team that evaluates risks

Risk response review team:

Develops risk response measures based on risk assessment results.

Construction risk response team:

A team that responds to risks arised during construction.


3.3 Proposed Dam Risk Management Team Composition in Indonesia

Following table shows a sample of members of dam risk management team in Indonesia.

In Indonesia, Dam Safety Commission

Table Sample of Members of Dam Risk Management Team

	Role
Implementing Agency (Dam Office / BWS)	A person who makes decisions of project implementation, planning and management of geological surveys, etc., and risk treatment.
Risk Manager (Appointed by IA)	A person in charge of overall dam engineering (structural/geological) risk management in/from the Implementing Agency.
Risk Sub-Manager (Appointed by IA)	A person who assists in the operation of risk management conducted by the risk manager.
Dam/geology Risk Advisors (Commissioned / DSC)	A dam and geology specialists who supports dam risk managers and risk management operations from a professional standpoint.
Dam Design Engineer (Consultant/dam engineer)	A person who designs dam/structures, etc.
Geotechnical Engineer (Consultant/geologist)	A person who conducts geological survey and analysis, etc.
Construction Engineer (Contractor)	A person who constructs structures, etc. based on the design.
OM Engineer (if necessary) (Consultant)	A person who conducts inspections in the maintenance and management of structures.



The team shall be composed of members with necessary skills and knowledge.

4. Timing of Risk Management

Risk management is a concept that can be applied at any stage of a project, but analysis of data collected to develop the guidelines in Japan has confirmed that implementing it early can have a greater impact.

The benefits of starting early are:

- a. More Options for dealing with uncertainty and risk can be considered.
- b. Damage can be minimized, and
- c. Better Results can be achieved (even if starting midway through the project).
- d. More benefits can be expected.

Example of Benefit

- ◇ a. In dam projects, there is a possibility to avoid a risky damsite in an early stage, but once the project has commenced, it becomes difficult to change the site, and due to countermeasures, there is a high risk of increasing of construction cost and extending of construction time.
- ◇ b. In case information would not be obtained sufficiently, decision making for finalizing the treatment may be postponed. Because an insufficient information or many assumptions, even though carrying out the precise design, the result will be in overdesign, or in the worst case, too optimistic assumptions may derive accidents.

By Identifying risks early which have a large impact and Responding strategically, the project may be implemented more efficiently.

5. Implementation Procedure of the Dam Risk Management System

Followings are idea of procedure for implementing with dam projects while being aware of risks, as well as methods that can be applied during implementation and points to keep in mind.

- a. Timings of Risk Management are mainly set based on the technical session by dam safety commission (but the session maybe need more frequently).
- b. Before the technical session, the dam implementation agency (such as BWS), etc.) shall conduct a "Risk Recognition in the project using Event Summary Report and Database."
- c. Prior to the technical session, Preliminary Discussions regarding the content of the check list shall be carried out with specialists (such as BTB (DSU), PUSAIR, BINTEK, etc.)
- d. Applying this process, all dam implementing agencies can prepare the Individual Event Summary Report at the necessary stage.

6. Establishment of Indonesian Guideline for Dam Risk Management

The following points should be considered when establishing a dam risk management system in Indonesia.

6.1 Risk Management Plan

- (1) No Need to built up a fixed system :

It is implemented using the most appropriate system available at the time, depending on the purpose and characteristics of the project. In Indonesia, a review system by the Dam Safety Committee has been established, so it is necessary to consider how to link the DSC with this dam risk management system and how to utilize the DSC.

- (2) Maximum Use of Existing System:

If there is an existing management system, it may be possible to utilize and reorganize this and add or improve the necessary parts to the system.

6.2 Risk Assessment

Sets Up the Data Compiling and Display of Risk Level, based on the policy of risk assessment.

For setting them up

- to consider to be applicable in the risk assessment and risk treatment,
- "Communication and Consultation" within the team shall be held,
- Select applicable methods based on the purpose of the project and target structures.

7. Preparation of Guidelines of Risk Management

The Contents of Dam Risk Management Guideline may be as shown below:

Table of Content

- Dam Construction Risk Management
- Basic Concept of These Guidelines
 - 1. Purpose of the Guidelines
 - 2. Applicable Subjects
 - 3. Definition of Terms
 - 4. Basics of Dam Risk Management
 - 4.1 Basic Policy for Dam Risk Management
 - 4.2 Dam Risk Management System and Organization
 - 4.3 Structure and Process of Dam Risk Management
 - 5. Dam Risk Management Implementation Methods
 - 5.1 General
 - 5.2 Communication and Consultation
 - 5.3 Risk Management Planning
 - 5.3.1 Setting Objectives and Targets
 - 5.3.2 Establishment of the System
 - 5.3.3 Planning
 - 5.4 Risk Assessment
 - 5.4.1 Survey of Geology, Ground Conditions, Design etc.
 - 5.4.2 Risk Identification
 - 5.4.3 Risk Analysis
 - 5.4.4 Risk Assessment
 - 5.5 Risk Response
 - 5.6 Monitoring and Review
 - 5.7 Continual Improvement of Risk Management
 - 5.8 Record-keeping and Reporting

8. Configuring the System in Other Countries (reference)

8.1 Risk Management System in Other Countries

A concept of risk management has been introduced and operated in civil engineering projects in overseas countries for a long time.

Table shows the technical methods of risk assessment and risk management systems used in overseas countries.

Various methods are used depending on the circumstances of each country.

However, in many cases, risk management systems are introduced for the purpose of "Avoiding Conflicts" between ordering parties".

Description	UK	U.S.A	New Zealand	Swiss	Netherlands	Canada	Nepal	Singapore
Assessment Methods	Risk Matrix	✓	✓	✓	✓			
	Failure mode and effect analysis		✓					
	Event tree analysis		✓					
	Quantitative							
Management Tool	Markov chain Monte Carlo simulation		✓	✓				
	Uncertain analysis (@RISK)		✓				✓	
	B/T B: Boling Length T: Tunnel Length						✓	
	Pessimistic/Optimistic Geological map				✓			
Risk management table			✓					
System	GBR :Geotechnical Baseline Report	✓	✓			✓		✓
	Geological risk							✓
	Ground certification	✓						
	Insurance system	✓						✓
Geo - advisor (Geotechnical advisor)	✓							

8.2 Comparison with Japanese Guideline

The risk management systems in overseas countries are different from the risk management systems that take into account civil engineering projects that emphasize cooperative relationships, such as those in Japan.

Japanese guideline: proposes a Qualitative Method for assessment.

The concepts are as follows:

- ◇ Information shall be added and updated in the risk management applying the latest survey results and progress of construction.
- ◇ Risks and measures shall be re-evaluated the uncertainties and be compared with original design conditions.
- ◇ The implementation method of risk management shall be reviewed and modified from time to time in accordance with latest information.
- ◇ The system is based on ISO-31000 (Risk Mitigation and Creating Value).

In this presentation, the Japanese guidelines was introduced, but when introducing a risk management system to Indonesia, it is necessary to make a decision after detailed research and deep consideration.

9. Recommendation and Conclusion

9.1 Recommendation

Currently, in Indonesia, DSC/DSU is conducting technical studies at each stage of dam design, water storage, and operation to ensure dam safety. This system is working very effectively. However, when we inspected many dam construction sites with DSC, it was verified that there were many issues arising at the site due to oversights during the survey and design stages and misunderstandings due to insufficient geological investigation.

When constructing a dam, there are geological uncertainties, and risks cannot be avoided. But it is supposed that risks in dam construction can be minimized by incorporating the "Risk Management System for Civil Engineering Projects" proposed here into the current Dam Safety Committee review system.

Furthermore, by accumulating and creating a database of issues that arise, their responses, and results, it is possible to improve the risk management system one by one. This database can also be used as a reference for the next risk response. In particular, BTB has been storing data related to the risks of all dams in Indonesia, and the materials for establishing this system are already available.

By creating such a system, i.e., organizational structure, risk management methods, database and guidelines showing organizational structure, and utilizing it in the field, it is possible to minimize the damage currently occurring in the field.

Using the management system proposed here,

- a. Identify risks and reflect them in the design once the dam survey is complete
- b. As the design progresses, we take measures to address newly identified risks during the design process.
- c. If construction is carried out and it is found that there is some deviation from the design, the risk will be reflected in changes in the design or construction method in advance.

This will likely lead to delays in construction, increased costs, and the prevention of accidents.

So, it is recommended introducing this system to design and construction sites in Indonesia.

9.2 Conclusion

- ✧ Currently, to ensure the safety of dams, Dam Safety Commission and Unit have been conducting technical reviews at each stage of dam design, impounding, and operation, in Indonesia. This system has been working very effectively.
- ✧ During my dam construction site inspection, however, I found many risks arising at site due to oversight in design, mis-interpretation of geological structure and so on.
- ✧ Risks are unavoidable in dam construction due to uncertain and diverse factors in Dam Project.
- ✧ It is supposed that adaptation of "Risk Management System" into the current review system by Dam Safety Commission as well as the design and construction on project site will help to minimize risks in dam construction.
- ✧ We hope that Indonesian dam-related parties (Benda, BTB, DSC etc.) will continue to discuss this concept and system and make efforts to make dam construction in Indonesia safer and smoother. We would like to continue to support them.

PART 4 Considerations on Geological Issues in Each Phase

1. Introduction

1.1 Background and Purpose of This Study

As a result of analyzing risk cases for 61 dams, the following was found.

- ◇ Many of the risk factors are geological.
- ◇ If many of the issues identified during the construction phase had been recognized before the detailed design stage, it may have been possible to reduce the costs of countermeasures against the risks, or to improve the safety and functionality of the completed structures.

Therefore, based on risk case studies and risk analysis results for 61 dams, this study proposes considerations for dam risk management at each project stage from a topographical and geological perspective.

1.2 Define and Identify Risk

The definition of risk in this study is as follows:

- ◇ In our study, risk refers to a situation/condition where the occurrence of an event may have significant undesirable impacts on the dam project.
- ◇ The impacts refer to dam breaches and the failure of dam functions, as well as negative effects of the projects on stakeholders.

Dam risk management aims to achieve the following goals by managing the above risks.

- ◇ Dam safety and functionality.
- ◇ Rationalization of Project Costs

1.3 Geological Risk Factor (Georisk Factor)

Risk is identified through issues or events in planning, investigation, design, construction, and operation phase. The risk identification, analysis, assessment, and response in our study are positioned in a cause-and-effect relationship as shown in the Figure 1.1.

This relationship is a case of dam foundation of Bagong dam. At the Bagong Dam site, foundation excavation during the construction phase revealed the "distribution of thick colluvium" which had not been estimated at the detailed design phase, and this was identified as a geological risk factor (hereafter referred to as georisk factor). To reduce or avoid the risks expected due to geological factors, additional geological surveys were carried out and the foundation treatment and foundation excavation lines were reconsidered. In this study, the considerations at each project phase were examined, focusing on the geological risk factors such mentioned above.




Figure 1.1 Cause-and-Effect Relationship for Risk Management (Bagong Dam)

2. Considerations for Each Phase

2.1 Planning & Preliminary Design

(1) Active Fault

Active faults have a significant impact on dam projects depending on their distribution. Furthermore, regarding the active faults distributed around the proposed dam site, it may not be sufficient to simply refer to existing active fault maps. For this reason, it is recommended that active fault study be carried out during the planning and preliminary design phase. Furthermore, active fault study also helps to identify the georisk factors of potential dam sites from the perspective of regional structural geology. Here, geological risk factors refer to loosening of rock mass, landslides, reservoir sedimentation, etc.

Figure 2.1 shows the flowchart of active fault study around reservoirs in Japanese dam projects. In this process, red text indicates judgment and evaluation.

(A) Literature Review, (B) Topographic Interpretation, (C) Site Inspection, (D) Comprehensive Evaluation based on the results of (A), (B) and (C). If there is a possibility of active faults existing at the dam site, go to (E) Geological Survey, (F) Comprehensive Evaluation based on the results of (E). When assessing that active faults are distributed at the dam site, Better to change the dam site.

However, there are a few cases overseas where fault displacement is considering in the design.

Here, the reason why lineaments and faults with a length of 10 km or more are targeted, because it is empirically believed that faults on the ground surface are formed by magnitude 6.5 or more and the length 10 km or more. The 3 km distance is based on the idea of a group of faults.




Figure 2.1 Flow of Active Fault Study for Dam Projects in Japan

Figure 2.2 is an example of photograph and sketch of trench in active fault surveys in Japan. A fault is considered active if it cuts or deforms strata that were formed within the past tens of thousands of years. In addition, samples are taken based on the fault's structure and C14 dating is carried out to study the activity history of the fault.




Figure 2.2 Example of Trench Survey of Active Fault in Japan

(2) Reservoir Sedimentation

Reservoir Sedimentation has a huge impact on maintaining the dam functions. For this reason, it is recommended that sediment yield study be carried out during the planning and preliminary design phase. Furthermore, since the topographical and geological conditions of the basin greatly affect sediment yield potential, it is effective to have geological engineers involved in reservoir sediment management (Figure 2.3). For reference, a literature shows the suspended sediment yield around Indonesia as shown in the Figure 2.4.




Figure 2.3 Different Topography of Sediment Yield



Figure 2.4 Suspended Sediment Yield around Indonesia

Source: Walling & Web (1983)

【Reference】 Sediment Yield Intensity Map

In Japan, the sediment volume for dam design is determined based on the actual sediment volumes of existing dams that have similar topography and geology to the basin of the proposed dam. Figure 2.5 estimates the potential sediment yield of Japan using an estimation formula developed based on the actual sediment volumes of existing dam reservoirs. The estimation formula uses the topography and geology of the basin as parameters. Such studies are useful for planning new dams.




Figure 2.5 Example of Sediment Yield Map of Japan

Note : This potential sediment yield is the long-term annual average value, and the amount of sediment runoff during floods would be much greater.

(3) Landslides around Reservoir

The occurrence of large-scale landslides or many landslides around the reservoir would have a huge impact on the safety and functionality of the dam. The construction of countermeasures after impounding often results in increased costs. For this reason, it is recommended that potential landslide study around the reservoir be carried out during the planning and preliminary design phase.

Figure 2.6 shows the flowchart of potential landslide study around reservoirs in Japanese dam projects. In this process, red text indicates judgment and evaluation. (A) Literature Review, (B) Topographic Interpretation, (C) Site Inspection, (D) Comprehensive Evaluation based on the results of (A), (B) and (C), determine the need for additional geological surveys and analysis, if necessary, go to (E), in (F), determine the need for countermeasures based on the results of process (E).

Furthermore, it is important to prepare ledgers of potential landslides based on the site inspection results shown in Figure 2.7, and to update the ledger after geological study, design of countermeasures, and construction them, and use them for monitoring after impounding.




Figure 2.6 Flow of Potential Landslide Study for Dam Projects in Japan




Figure 2.7 Ledger of Potential Landslide

Figure 2.8 shows a large landslide that occurred in a dam reservoir in Japan in 2008 by a magnitude 7.2 earthquake. The landslide was about 900m wide and 1,300m long, 67 million m³ volume. Fortunately, this landslide occurred about 1 km upstream from the dam, so the dam breach did not occur.

This landslide had been identified as a potential landslide before the earthquake, but the risk of a landslide was retained, considering the likelihood of occurrence and the countermeasure cost. After the landslide, countermeasures were carried out to stabilize the cliff, suppression of sediment runoff, and stabilize the end block of the landslide.



Figure 2.8 Large-scale Landslide in the Dam Reservoir in Japan

Figure 2.9 shows a large landslide that occurred in a dam reservoir in Japan in 2008 by a magnitude 7.2 earthquake. The landslide was about 900m wide and 1,300m long, 67 million m³ volume. Fortunately, this landslide occurred about 1 km upstream from the dam, so the dam breach did not occur.

This landslide had been identified as a potential landslide before the earthquake, but the risk of a landslide was retained, considering the likelihood of occurrence and the countermeasure cost. After the landslide, countermeasures were carried out to stabilize the cliff, suppression of sediment runoff, and stabilize the end block of the landslide.



Figure 2.9 Large-scale Landslide in the Upstream of Bili-Bili Dam (2004)

(4) Keep in Mind

These are things to keep in mind during the planning and preliminary design phase.

- Consider how to deal with the risks identified in the planning and preliminary design phase.

- All information regarding risks identified in the planning and preliminary design phase will be carried over to the detailed design phase without exception.
- During the detailed design phase, investigations and considerations will be carried out on risks that cannot be avoided during the planning and preliminary design phase.

2.2 Detailed Design

(1) Dam Foundation

The risks located in the dam foundation have a huge impact on the safety of the dam body. Redesigning a dam foundation during construction would delay the project schedule and increase costs. For this reason, during the detailed design phase, it is important that the geological conditions of the site are interpreted properly, and reasonable excavation line are designed.

Figure 2.10 is a geological cross section of Bagong Dam. The above figure is design phase, and the below is construction phase. On both the left and right banks, the thickness of the colluvial layer distribution was significantly different between the detailed design phase and the construction phase.

It is estimated that the cause of this was a lack of geological surveys and incorrect geological interpretation in design phase.




Figure 2.10 Example of Change in Foundation Excavation Line (Bagong Dam)

The following are some considerations for designing a rational foundation excavation line.

(a) Seismic Exploration

Seismic exploration is also called elastic wave exploration. Generally, rock foundations can be evaluated using P waves, while soil foundations can be

evaluated using S waves. Figure 2.11 shows a seismic exploration analysis result of rock mass foundation. There is a correlation like this between P-wave velocity and rock grade (D to CH).




Figure 2.11 Schematic Analysis Result of Seismic Exploration Dam)

(b) Grouting: Characteristics of Each Geology

According to the results of our risk case analysis, the main risk factors for leakage are extrusive rocks and pyroclastic rocks. For this reason, grouting will be adopted and designed considering such geological characteristics shown in Table 2.1.

Table 2.1 Grouting: Characteristics of Each Geology

Rock Type	Geological Characteristics	Precautions for Grouting
Pre-Neogene sedimentary rocks	Intact rocks are hard, but because the bedrock has many faults, open cracks develop in the weathered areas. Limestone areas have cavities and are highly permeable.	Improvement is relatively easy. Cement milk with a high mortar concentration is often used to fill cavities in limestone.
Crystalline schist	The fractures are highly anisotropic and often involve large fault zones parallel to the foliation.	The improvement effect is often dependent on the schistosity. It is necessary to consider a method for seaming the schistosity of the surface.
Granite	Weathering occurs deep down to form decomposed sand. The strongly weathered zone is thick on the gently sloping ridge. Some fault fracture zones are large in scale.	Weathered granite has a permeability of 10 Lu or more and a low critical pressure. In embankment dams, there are many issues with excavation lines and grouting methods.
Neogene sedimentary rocks	Sandstone and conglomerate are relatively well consolidated, but mudstone and tuff are prone to weathering and slaking. Large-scale faults can be seen in tuffs.	Since the properties of strata vary depending on the rock type, the improvement effect varies widely, and improvement may be difficult in some areas.
Quaternary strata	The strata are generally unconsolidated to lowly consolidated, and there are cases where the gravel layer is thick.	There are many highly permeable layers. Careful consideration is required regarding methods and materials.
Extrusive rocks	It is accompanied by columnar and tabular joints, autofracture and autoalteration. The intrusive rock may be accompanied by alteration zones.	Generally, the permeability is high, a large amount of grouting material is required, and the total grouting hole length is long. Setting improvement areas is relatively difficult.
Pyroclastic rocks	The agglomerates and tuff breccias are heterogeneous with soft and brittle matrices. The welded tuff is heterogeneous and interbedded with unconsolidated layers. The volcanic gravel layer is unconsolidated and highly permeable.	There are many issues with deformation of the unconsolidated layer and piping, and large-scale treatment is required. When the critical pressure is low and the Lugeon value is high, improvement is difficult.

(c) Grouting: Lugeon Map

To design a reasonable curtain grouting, it is necessary to study the Lugeon map considering the geological stratigraphy, geological structure, and rock grade.

This is because the permeability of rock mass depends on the distribution and continuity of fractures.




Figure 2.12 Grouting : Lugeon Map

(d) Grouting: Curtain Grouting Area

The area of the curtain and rim grouting is designed so that the dam body and foundation work together to provide watertightness.

(i) Width (Rim)

From the foundation to the intersection of the groundwater level with the reservoir water level or with the low permeability zone (Figure 2.13).

(ii) Depth (Curtain)

From the foundation to the low permeability zone. However, empirically, the depth is set to between half the dam height and the equivalent of the dam height.

In addition, to carry out reasonable grouting work, it is important to conduct a review of the improvement areas based on the results of pilot hole grouting during the construction phase.




Figure 2.13 Basic Concept of Curtain Grouting Area

(e) Reasonable Excavation Line

The foundation excavation line is examined comprehensively based on the strength and deformability required for the foundation (refer to Rock grade), water permeability (refer to Lugeon map) and improvement by grouting (refer to Grouting test results).

For example, in Figure 2.14, CL class is selected as the foundation from the perspective of strength and deformability. If it is appropriate to excavate rock mass with 10 Lu or more as much as possible from the perspective of grouting improvement and cost, the excavation line may be designed like this.




Figure 2.14 Example of Excavation Line Setting for Impervious Zone Foundation

(2) Cut Slope

At dam sites, large cut slopes are often constructed around spillways, intake towers, and tunnel entrances. The occurrence of a landslide on a large cut slope can have a huge impact on the safety and functionality of a dam. For this reason, during the detailed design phase, the layout of facilities*, the cutting gradient, drainage facilities and protective works are designed considering the loosening and strength reduction due to excavation and georisk factors. Here, the layout of the facilities is related to the scale and direction (Relationship with geological structure: dip slope, reverse dip slope, etc.) of the cut slope.

(a) Geological Study Flow

Geological study to design large cut slope is carried out using the process shown in Figure 2.15 in Japan. (A) Literature Review, (B) Topographic Interpretation, in process (B), it is necessary to focus on the such topographical risk factors shown in the Figure 2.16, (C) Site inspection, (D) Comprehensive Evaluation, based on the results of (A), (B) and (C), determine the need for geological surveys, if necessary, go to (E), (F), determine the need for countermeasure works based on the results of process (E).




Figure 2.15 Geological Study Flow for Large Cut Slope Design in Japan




Figure 2.16 Examples of Topographical Factors to be Focused

(b) Loosening due to Excavation

According to the idea of SRR (Stress Release Ratio), empirically, sliding of a maximum thickness equivalent to the cutting thickness is estimated in the middle part of the cut slope. This indicates that the impact of loosening due to excavation is large.




Figure 2.17 Idea of SRR (Stress Release Ratio)

Source: Kimura et.al (2015)

(c) Georisk Factors

Cut slopes will be designed considering the following georisk factors.

(i) Discontinuity

The strength of the surface layer reduces due to the opening of cracks caused by stress release during excavation, the infiltration of groundwater into the cracks, and the progression of weathering along the cracks (Figure 2.18 a)).

(ii) Hydrogeological Structure

Water easily seeps into the slope, causing the phreatic surface to rise and the strength of the hydraulic boundary to decrease (Figure 2.18 b)).

(iii) Slaking/Swelling

The swelling of clay minerals and repeated drying and wetting destroy the rock structure and significantly reduce its strength (Figure 2.18 c)).




Figure 2.18 Georisk Factors of Cut Slope

(d)

(i) Discontinuity

Figure 2.19 shows a case of a landslide caused by discontinuities. This landslide occurred at the intake tower site of Rukoh Dam. The scale of

the sliding has grown over time. Fold structures have developed around the dam site, and the sandstone-dominated alternation distributed at the dam site are inclined at high angles. It is estimated that under such geological conditions, high-angle faults have also developed in the bedrock, which led to this large-scale collapse.

Considering these geological conditions, it is necessary to change the shape of the cut slope during the excavation or measures are needed to prevent the bedrock from loosening.




Figure 2.19 Large-scale Sliding Occurred on Cut Slope (Rukoh Dam)

(ii) Hydrogeological Structure

Figure 2.20 shows a case of a landslide caused by hydrogeological structures. This landslide occurred at the spillway site of Temef Dam. The geology of the cut slope is a claystone layer with an overlying limestone layer. In addition to the hydrogeological structure, the claystone layer was also a cause of the landslide because it was scaly clay. Considering these geological conditions, measures are needed to prevent the bedrock from loosening and to remove groundwater from the slope as much as possible.




Figure 2.20 Large-scale Sliding Occurred on Cut Slope (Temef Dam)

(iii) Slaking/Swelling

Figure 2.21 shows a case of a landslide caused by slaking. This landslide occurred at the intake tower site of Jragung Dam. The geology of the cut slope is claystone. There is also a folded structure around the dam site, with small high-angle faults as shown in the photo. I believe this was also a cause of the landslide. Considering these geological conditions, measures are needed to prevent deterioration of the bedrock and to prevent the infiltration of surface water into the cut slope.



Figure 2.21 Large-scale Sliding Occurred on Cut Slope (Jragung Dam)

【Reference】 Slope Countermeasure Method

Figure 2.22 shows some countermeasures that are commonly used in Japan. Anchors can withstand higher earth pressure than rock bolts.




Figure 2.22 Slope Countermeasure Method

(3) Tunnel

Deformation or collapse of the intake and discharge tunnels has a significant impact on the schedule and cost during construction, maintaining the dam's functions after impounding. For this reason, during the detailed design phase, reasonable supports system will be designed, considering deformability of the ground and georisk factors.

For reference, geological study to design tunnel is carried out using this process shown in Figure 2.23 in Japan. (A) Desk Study, (B) Site Inspection, (C) Geological Survey, in (D) Comprehensive Evaluation, based on the results of (A), (B) and (C), determine the need for additional geological surveys, if necessary, go to (E), in (F), determine the need for special or auxiliary measures based on the results of process (E).




Figure 2.23 Geological Study Flow for Tunnel Design in Japan

The following are some points to consider for rational support design.

(a) Seismic Exploration

To obtain sufficient geological information along the planned tunnel, seismic exploration will be used in addition to drilling surveys (Figure 2.24). If possible, it is more efficient to determine the locations of drilling survey based on the results of seismic exploration. In addition, the tunnel entrance must be designed considering thin ground and distribution of weathered rock.




Figure 2.24 Seismic Exploration Results and Drilling Survey Layout

(b) Crack Coefficient and Competence Factor

To evaluate the tunnel ground, “Crack coefficient (Cr)” is useful as an index for cracked rock mass, while “Competence factor (Cf)” is useful as an index for soft rock mass. The crack coefficient Cr is calculated from the ratio of the elastic wave velocity of the ground to that of intact rock. Table 2.2 shows the Cr index depending on the rock condition.

The competence factor Cf is calculated from the ratio of the compressive strength of the rock mass to the overburden pressure. If the rock mass is without cracks, the compressive strength is almost equal to that of intact rock. The compressive strength of rock mass with many cracks can be

calculated using that of intact rock and the crack coefficient C_r . The C_f index less than 2 indicates a high risk of deformation due to plastic pressure (Table 2.3).

Crack coefficient: $C_r = 1 - (V_{p1}/V_{p0})^2$

Competence factor: $C_f = qu/P$

for Fissured rock mass: $C_f = qu'/P$

$qu' = (1 - C_r) \times qu$, $P = \gamma H$

Here, V_{p1} : P-wave velocity of rock mass

V_{p0} : P-wave velocity of rock

qu : Compressive strength of rock

qu' : Compressive strength of fissured rock mass

P : Overburden pressure

γ : Unit Weight

H : Overburden height

Table 2.2 Relationship between C_r and Rock mass condition

<i>C_r (%)</i>	<i>Rock mass condition</i>
< 25	Fresh with almost no cracks.
25 - 50	Fresh and with few cracks.
50 - 70	Slightly weathered and has some cracks.
70 - 80	Weathered and has relatively many cracks.
> 80	Strongly weathered and has many cracks.

Table 2.3 Relationship between C_f and Earth Pressure Characteristics

<i>C_f</i>	<i>Earth pressure characteristics</i>
> 10	Soft rock mass stands up well.
4 - 10	No plastic earth pressure occurs.
2 - 4	Plastic earth pressure may occur.
< 2	Plastic earth pressure often occurs.

(c) Georisk Factors

The tunnel will be designed considering the following georisk factors same as the cut slopes.

- ✓ Discontinuity: Direction of development of discontinuities
- ✓ Hydrogeological Structure: Large amounts of spring water
- ✓ Swelling: Deformation due to swelling (swelling pressure)

However, since it is difficult to estimate in advance whether a large amount of spring water will occur, if the risk is high, ahead survey can be carried out during construction. The next chapter describes a geological survey method (ahead exploration) that can help solve this problem. The survey methods are presented in the next section.

(i) Discontinuity

Figure 2.25 shows a case of roof collapse in the diversion tunnel of Bagong Dam. The cause of the collapse, the georisk factor, was a low-angle discontinuity developed along the bedding plane. Since such geological structures can be predicted in advance, it is possible to design auxiliary works such as fore poling at the design phase.





Figure 2.25 Auxiliary Construction for Tunnel Roof Collapse

(ii) Slaking/Swelling

Figure 2.26 shows a case of the deformation in the spillway tunnel of Manikin Dam. The cause is the swelling pressure of scaly clay.



Conceptual Diagram of Tunnel Deformation due to Swelling

Figure 2.26 Tunnel Deformation due to Swelling (Manikin Dam)

There are two main types of support systems that respond to swelling pressure (Figure 2.27). One is a flexible support system that can follow deformation, and the other is a heavy support system that can resist swelling pressure. The left image shows a flexible support system called a Yielding Support, and the right image shows a Multiple Steel Rib Support used in NATM.




Figure 2.27 Tunnel Deformation due to Swelling (Manikin Dam)

(d) Keep in Mind

These are things to keep in mind during the detailed design phase.

- ✓ Consider how to deal with the risks identified in the detailed design phase.
- ✓ All information regarding risks identified in the detailed design phase will be carried over to the construction phase without exception.

- ✓ During the construction phase, additional investigations and considerations will be carried out on risks that were carried over from the detailed design phase to avoid or reduce risks.

2.3 Construction

(1) Dam Foundation: Checking Excavation Surface

Geological engineers will check the excavation surface and evaluate its suitability as a dam foundation in terms of strength, deformability, and permeability, and will propose the implementation of dental work and auxiliary grouting if necessary.

For reference, geological checking, and response to excavate foundation is carried out using this process shown in Figure 2.28 in Japan.

(A) Checking Excavation Surface, Record (sketch) the geology and rock conditions and compare them with the estimates at the design phase, in (B) Based on the results of (A), Determine the need for additional geological survey and analysis, if necessary, go to (C), in (D), Determine the need for additional measures based on the results of process (C).




Figure 2.28 Dam Foundation: Checking Excavation Surface

For reference, Figure 2.29 shows a sketch of a rockfill dam foundation in Japan. The orange and yellow parts are bedrock, mainly dacite. The light blue parts are terrace deposits.




Figure 2.29 Geotechnical Sketch of Rockfill Dam Foundation (Geology)

Figure 2.30 shows a sketch of a rockfill dam foundation in Japan. Green is CM class, yellow is CL class and red is D class. The blue box here is the dental work area of the fault zone.

In Japan, dam foundations are traditionally recorded in detail for cracks and spring points. Such information is used for monitoring after impounding. Sketching not only the dam foundation but also the spillway foundation can help investigate the cause of leakage confirmed after impounding.



Figure 2.30 Geotechnical Sketch of Rockfill Dam Foundation (Rock Grade)

(2) Cut Slope: Checking Excavation Surface

Geological engineers will check the excavation surface and evaluate the suitability of the cut slope design. If necessary, they will propose countermeasures such as re-excavation, or the slope protection.

It is recommended for large cut slopes to measure the surface displacement by surveying during construction. If a large surface displacement is confirmed, underground displacement will also be measured using borehole inclinometers etc. to design the countermeasures.

For reference, geological checking and response to excavate slope is carried out using this process same as foundation excavation surface (Figure 2.31).

(A) Checking Excavation Surface, Record (sketch) the geology and rock conditions and compare them with the estimates at the design phase, in (B) Based on the results of (A), determine the need for additional geological survey and analysis, if necessary, go to (C), in (D), determine the need for additional measures based on the results of process (C).




Figure 2.31 Geological Study Flow for Large Cut Slope construction in Japan

For reference, Figure 2.32 shows a geological sketch of a large cut slope in Japan. At this site, framework was constructed in the green area, considering the direction of the faults on the cut slope and the bedrock conditions. By having geologists check the excavation surface and implementing countermeasures based on the results, the safety of the completed cut slope can be further increased.




Figure 2.32 Geotechnical Observations of a Large Cut Slope

Source: Okazaki et al. (2005)

Figure 2.33 shows a large cut slope of the spillway of Ameroro Dam. This is an example where the excavation surface was checked well by geological engineers. At this site, Geo-net was used in the upstream area where fresh bedrock is distributed, and shotcrete (10 cm thick) and concrete walls (15 cm thick) were constructed in the downstream area where weathered rock is distributed, based on the condition of the cut slope (rock grade).



Figure 2.33 Construction of Countermeasures based on Geotechnical Observations (Ameroro Dam)

(3) Tunnel: Ahead Survey

For the safety of construction and the selection of a reasonable support system, it is useful to understand the geological conditions ahead of the tunnel face in advance. There are the following survey methods.

(a) Drilling Survey

Horizontal drilling is used to take core samples to confirm the geology ahead of the face, and if there is confined groundwater, this drilling can reduce the confined water pressure to prevent the collapse of the tunnel face (Figure 2.34).



Figure 2.34 Drilling Survey (Horizontal)

Source: https://www.kajima.co.jp/gallery/const_museum/tunnel/gijutsu/article/tunnel_g_06.html

(b) Drilling Exploration

This method includes drilling horizontally, similar to drilling surveys, but instead of taking core samples, the ground conditions are evaluated based on the drilling speed and drilling resistance (Figure 2.35).




Figure 2.35 Drilling Exploration

Source: <https://kensetsu.ipros.jp/product/detail/2000557827>

(c) Elastic Wave Exploration

This is conducted using the excavation vibrations of a hydraulic breaker as the vibration source and using the heads of rock bolts installed at regular intervals on the tunnel wall as the receiving points for reflected waves (Figure 2.36).




Figure 2.36 Elastic Wave Exploration

Source: <https://www.shimz.co.jp/company/about/about/news-release/2019/2019034.html>

(4) Keep in Mind

These are things to keep in mind during the construction phase.

- All information regarding the results of risk responses during the construction phase, as well as any newly identified risks, will be carried over to the operation phase.
- All records of design changes and quality control during construction will be carried over to the operation phase.

2.4 Operation

(1) Reservoir Sedimentation

The progression of reservoir sedimentation, which far exceeds the initial plan, could have a significant impact on the dam function in the future. For this reason,

Regular surveys of reservoir sedimentation are recommended as part of dam operation and maintenance.

As shown in the Figure 2.37, early response to the progression of sedimentation reduces costs and technical difficulty.




Figure 2.37 Changes in Sediment Volume Over Time

Figure 2.38 show recent bathymetry technology, Multibeam Echo Sounding and Airborne Laser Bathymetry. In Multibeam Echo Sounding, water depth is measured in three dimensions by transmitting sound waves in a fan shape (Figure 2.38 a)). In Airborne Laser Bathymetry, water depth is calculated based on the difference in reflection time between a green laser and an infrared laser (Figure 2.38 b)).




Figure 2.38 Recent Bathymetry Technology

(2) Landslides around Reservoir

The inflow of large amounts of sediment into a reservoir due to a large landslide can have a significant impact on the dam function. For this reason, it is desirable to develop methods that can monitor efficiently the movement of slopes around reservoirs.

As shown in Figure 2.39, large-scale slope movements can be measured using SAR (Synthetic Aperture Radar) mounted on a satellite, and this technology is expected to be useful for monitoring the landslide around the reservoir. In the Figure 2.40, blue indicates subsidence and red indicates uplift. It is estimated to be rotational movement caused by a large landslide.




Figure 2.39 Conceptual Diagram of Measurement by SAR (Synthetic Aperture Radar)




Figure 2.40 Displacement Distribution Map by SAR

Source:

3. Engineering Sense

This chapter describes the keep in mind that geological engineers should have to contribute to risk management (Figure 3.1).



Figure 3.1 Displacement Distribution Map by SAR

Source: <https://www.istockphoto.com/jp/>

3.1 Perspective and Imagination

It is recommended to imagine the geological conditions of the site not only at the normal scale but also at the macro-scale and micro-scale to avoid overlooking the georisks of the project site.

- ◇ Macro-scale: Wide-area topographical and geological features, distribution of active faults, as well as the arrangement of plates and the formation of islands, etc.
- ◇ Micro-scale: The rocks that make up the bedrock, the minerals that make up those rocks, the types of minerals and their chemical properties, etc.
- ◇ Normal-scale: Site and outcrop inspections consideration macro- and micro-scale site geology.

3.2 Integrated interpretation.

Geological analysis requires integrated interpretation of findings from different types and scales, and this interpretation is essential for identifying and assessing georisks (Figure 3.2). Appropriate geological interpretation and collaboration between geologists and design engineers are essential for reasonable design. Thinking the distribution of strata and geological structures in three dimensions is one of the good practices for integrated interpretation.




Figure 3.2 Image of Integrated Interpretation

【Reference】 CIM: Construction Information Modeling/Management

In relation to three-dimensional analysis, for reference, we would like to introduce the Construction Information Modeling/Management in Japan. We believe that CIM can also be used for risk management.

In recent years, CIM has been introduced into the design of civil engineering structures in Japan to improve the efficiency of construction and maintenance. CIM has the following main features:

- ◇ It is a three-dimensional model, and survey and test results can also be stored as attribute data (Figure 3.3).
- ◇ CIM can be shared among stakeholders, and information can be easily carried over to the design, construction, and operation phases (Figure 3.4).




Figure 3.3 3D Model of Cut Slope for Design (Rock Grade)

Source: <https://www.oyogeotools.com/products/octas.html>




Figure 3.4 Basic Concepts of CIM

Attachments

- | | |
|--------------|---|
| Attachment 1 | Dam Safety System in Indonesia: Dam Safety Commission |
| Attachment 2 | Completed Dam Risk Entry Form |
| Attachment 3 | Minutes of Discussion on Dam Risk Management |

Attachment 1


**Dam Safety System in Indonesia: Dam
Safety Commission**

Dam Safety System in Indonesia

1. Dam Project Approval System in Indonesia

In Indonesia, the safety management of dam construction was introduced in 1989 by the Ministry of Public Works with the publication of the Dam Safety Guideline (SNI No.1731-1989-F). This guideline describes the establishment of a commission in charge of approving dam safety assessments, including technical assessments on construction, impounding, operation, and dam removal. In 1997, the Ministry of Public Works also issued Ministerial Regulation 72/PRT/1997 on Dam Safety. This dam safety regulation requires that technical assessments to minimize damage caused by dams at each stage of dam development (design, construction, impounding, operation, rehabilitation, and dam removal) must be conducted by the Dam Safety Commission (DSC) and the Dam Safety Unit (DSU) and approved by the Minister. In addition, regulations on dams were issued in Water Resources Law No. 7 of 2004 and Government Regulation No. 37 of 2010 on Dams. The regulation clearly states the requirement for licensing at all stages of dam development and management and also includes the need for Emergency Action Plans as part of the dam safety concept.

In this way, the concept of dam safety in Indonesia is not limited to technical aspects of safety before construction but also takes into consideration post-construction maintenance and responses to unexpected events, and is legally regulated.



❖ **Figure 2-1 Dam safety concept**

1.1 Legal background (Ministerial Order on dam construction approval)

Ministerial Decree of the Ministry of Public Works and Housing of the Republic of Indonesia on Dams No. 27/PRT / M/ 2015 BENDUNGAN DENGAN RAHMAT TUHAN YANG MAHA ESA MENTERI PEKERJAAN UMUM DAN PERUMAHAN RAKYAT The Indonesian Republic (Republik Indonesia) enacted the 2015 Act (Document 1) , which reiterates the requirements for dam construction.

The translation of the preamble to this Act is as follows:

- a. As per Article 15 of the Government Rules 35 of 1991 on Rivers, for the purpose of public welfare and safety, it is necessary to construct reservoirs to store water as part of water resources development, to store excess water during rainy season and to meet the demand for water as required and also to control the destructive power of water.
- b. The environmental and safety reservoirs in question include dams for storing water, as well as **dams for storing mine waste** (tailings dams) and dams for handling sludge.
- c. In order to store the water, mine waste and mud mentioned in a and b, dams need to be built.
- d. In order to construct a dam that functions in line with development objectives, technical regulations are necessary to ensure the safety of the dam.
- e. It is essential to maintain and manage the reservoir in order to ensure the sustainability of its function in line with the development objectives under Article 16 of the 1991 Government Decree on Rivers, Article 35.
- f. Pursuant to Articles a, b, c, d and Law No. 11 of 1974 on Irrigation, the Minister of Public Works and Housing has the authority and responsibility to manage the operation of water resources and carry out projects;
- g. In order to provide a basis and guidance for the construction and management of the reservoirs mentioned in a and e, it is necessary to formulate guidelines for the construction and management of dams and their reservoirs.
- h. Based on considerations a, b, c, d, e, f and g, the Minister of Public Works and Housing has formulated regulations regarding this dam.

The following six laws have been established as relevant laws.

1. Law No. 11 of 1974 on Irrigation (Supplement to the Annual Report of the Republic of Indonesia No. 65 of 1974, National Gazette No. 3046).
2. Law No. 23 of 2014 on Local Government (Supplement to the National Gazette of the Republic of Indonesia No. 244 of 2014, No. 5587 of the National Gazette of the Republic of Indonesia);
3. Government Regulation No. 22 of 1982 on Water Management (Supplement to Article 37, No. 3225 of the National Gazette of the Republic of Indonesia of 1982).
4. Article 7 of the Presidential Regulation of the Republic of Indonesia on the Organization of the Ministry of State (Ministry of State of the Republic of Indonesia No. 8 of 2015).
5. Article 15 of the Presidential Regulation of the Republic of Indonesia of 2015 on the Minister of Public Works and Housing (National Gazette of the Republic of Indonesia No. 16 of 2015).

6. Regulation of the Minister of Public Works No. 08/PRT/M/2010 on the organization and working procedures of the Ministry of Public Works (Ministry of State of the Republic of Indonesia Year 2010 No. 1304);

1.2 Dams subject to approval

Dams that are eligible for approval are large dams that meet the following criteria. Furthermore, eligible for approval are large dams that meet the following criteria including not only reservoir dams, but also tailings dams, erosion control dams, and mudflow storage dams.

- 1) The dam capacity is more than 100,000 m³ and the dam height is more than 15 meters
- 2) A dam with a reservoir capacity of more than 500,000 m³ even if the dam height is less than 15 m
- 3) Dams that qualify as water infrastructure as separately defined by the Dam Safety Committee

1.3 Overview of dam construction approval

The dam construction approval review is carried out by the Dam Safety Commission (DSC) , which is governed by Ministerial Decree No. 72/PRT/1997 on Dam Safety, and covers the design, construction, operation, maintenance, redevelopment and demolition of dams.

The details of the implementation are summarized in the Presentation on Dam Safety Concept & Regulation prepared by the Dam Safety Committee. Although this document was prepared in 2008, the Department of Dams of the Ministry of Public Works and Housing has confirmed that there have been no changes to the content other than the members of the committee.

Anissa Mayangsari and Mr. Tri Bayu Adji, who were members of the Dam Safety Unit in 2015 , gave a brief overview of dam approval in Indonesia to Hydropower. The report was presented at the 2015 Symposium on Dam Safety in Indonesia held in Stavanger, Norway on June 15-16, 2015 (Document 3).

The outline of the dam construction approval is as follows:

(1) Types of Dam Safety Approvals

dam safety approvals:

(a) Design Certification (Design Certification/Construction Permit)

A review of the design, required for construction work to commence. Obtained before placing an order for construction work.

(b) Initial Impounding Certification

At the end of construction, the construction work (especially the quality control and progress control results) is reviewed to ensure that impoundment (or disposal of tailings in the case of tailings dams) will not cause any problems. Once construction has

progressed to a certain extent, an application for approval can be submitted. Impoundment can begin only after approval has been issued.

(c) Operation Certificate

impoundment is completed (the reservoir reaches the designed water level) or two years have passed since impoundment began, the results of test impoundment (including an analysis of the dam's behavior) will be obtained to determine whether the dam can be operated safely.

(d) Abandonment Certification

When a dam is to be abandoned, a dam abandonment plan, including removal methods, must be presented in advance and an application for dam removal permission must be filed before the dam can be removed.

(2) Organization

The following two organizations are responsible for a series of inspections and approvals related to dam safety, and their activities are supported by the Ministry of Public Works and Housing.


a) Dam Safety Commission (DSC)

b) Dam Safety Unit (DSU)

The DSC is the body that assists the Minister in managing dam safety, and the Dam Safety Unit is an organization established to provide technical assistance to the DSC and to carry out technical reviews (specifically, members of the PU-PR Balai Bendungan (Ministry of Public Works and Housing's Department of Dams)).

In addition, if a dam development is deemed to require technical studies on dam safety such as those listed below, the dam owner (project implementer) must establish a "Dam Panel" as proposed by the DSC and DSU. The Dam Panel will function during the design, construction and impoundment of the dam reservoir.

- a. When new technologies are applied in the design and construction of dams;
- b. Dams with a height of 75 m or more and a storage capacity of 100 million cubic meters or more and
- c. Dams deemed to be at high risk



❖ Figure 2-2 Organizational chart of the Dam Safety Committee

Ministerial Decree No. 1234/KPTS/M/2023 appointed the members of the Dam Safety Committee from 2023 onwards. The members of the committee are as shown in Table 2-1.

Table 2-1 DSC Members

Tim Inti/Anggota Tetap			
NO	INSTANSI/NAMA	JABATAN/BIDANG KEAHLIAN	KEDUDUKAN DALAM KOMISI
1	2	3	4
1	Kementerian Pekerjaan Umum dan Perumahan Rakyat, Direktorat Jenderal Sumber Daya Air	Direktur Jenderal Sumber Daya Air	Ketua merangkap Anggota
2	Kementerian Pekerjaan Umum dan Perumahan Rakyat, Direktorat Bendungan dan Danau	Direktur Bendungan dan Danau	Wakil Ketua merangkap Anggota
3	Kementerian Pekerjaan Umum dan Perumahan Rakyat, Balai Teknik Bendungan	Kepala Balai Teknik Bendungan	Sekretaris merangkap Anggota
4	Kementerian Pekerjaan Umum dan Perumahan Rakyat, Direktorat Bina Teknik	Direktur Bina Teknik Sumber Daya Air	Anggota
5	Kementerian Pekerjaan Umum dan Perumahan Rakyat, Direktorat Bina Operasi dan Pemeliharaan	Direktur Bina Operasi dan Pemeliharaan	Anggota
6	Dr. Ir. Hari Suprayogi, M.Eng	Ahli Hidrologi, KNIBB, HATHI	Anggota
7	Ir. Bambang Hargono, DIPL.HE, M.Eng	Ahli Hidrolika, KNIBB, HATHI	Anggota
8	Dr. Ir. Ni. Made Sumiarsih, M.Eng	Ahli Teknik Bendungan Besar, KNIBB, HATHI	Anggota
9	Ir. Tri Bayu Adji, MA	Ahli Hidromekanikal, KNIBB	Anggota
10	Dr. Ir. Paulus Kurniawan, MBA	Ahli Geologi, HATTI, IAGI	Anggota
11	Duki Malindo, ST. MCM.	Ahli Project Manajement, KNIBB	Anggota
12	Dr. Ir. Aries F. Firman, M.Sc	Ahli Geoteknik, KNIBB	Anggota
13	Ir. Agus Djatiwiryono, ME	Ahli Operasi dan Pemeliharaan Bendungan, KNIBB, HATHI	Anggota

In addition to these two organizations, the Indonesian Association of Dam Engineers and the Indonesian Council for Large Dams (INACOLD) (also members of the DSC) provide technical support when necessary.

The technical review of the dam itself will be carried out by experts from INACOLD and HATHI as well as technical staff from the Dam Bureau.

(3) Criteria used in the review

The criteria applied to the review are as follows, but are not limited to these as necessary.

Table 2-2 Criteria applicable to the review

No.	Document	Status	Decree
A.	General Guidelines		
1.	Ministerial Regulation on Dam Safety ^{1/1}	OV	Kep Men PU No.296/KPTS/M/2001
2.	Government Regulation on Dams & Reservoirs	UP	RPP Waduk dan Bendungan
3.	Organization & Management of Dam Safety	OV	SNI No. 1731 – 1989 F
4.	Registration and Inventory of Dams	I/OV	Prakata Ketua KKB Okt 2002
5.	Guidelines & Operational Procedures for DSC	I	Keputusan Ketua KKB No.01/KPTS/2002
6.	Guidelines for Development & Decommissioning of Dams	I	Prakata Ketua BKB, Okt 2002
B.	Technical Guidelines		
1.	General Guidelines on Dam Development	D	Kata Sambutan Direktur Bina Teknik, Des 2003
2.	General Dam Design Criteria	R	Keputusan Ketua KKB : 05/KPTS/2003
3.	Filling of Reservoirs	I	Keputusan KKB : 03/KPTS/2002
4.	Safety Inspection & Evaluation of Dams	I	Keputusan KKB : 05/kpts/2003
5.	Dam Safety Review	I	Keputusan KKB : 05/KPTS/2003
6.	Revision of Guideline on Downstream Hazard Classification of Dams	OV/D	Keputusan Dirjen SDA 108/KPTS/A/1998
7.	Revision of Emergency Action Plans	UP	Keputusan Dirjen SDA 94/KPTS/A/1998
8.	Dam Safety Unit (DSU) Development Plan	OV/UP	COLENCO 1998
9.	Guidelines & Operational Procedures for DMUS	UP	COLENCO 1996
10.	Operations, Maintenance & Surveillance of Dams: Phase I- General	I	Keputusan Dirjen SDA No. 199/KPTS/D/2003
11.	Operations, Maintenance & Surveillance of Dams: Phase II- Management	I	Keputusan Dirjen SDA No. 199/KPTS/D/2003
12.	O&M & Surveillance of Dams: Phase III- Dam Instrumentation & Monitoring Systems	I	Keputusan Dirjen SDA No. 199/KPTS/D/2003
13.	O&M & Surveillance: Phase IV- Inspection of Hydro-Mechanical and Electrical Equipment	I	Keputusan Dirjen SDA No. 199/KPTS/D/2003
14.	O&M & Surveillance: Phase V- Standard Operating Procedures for Hydro-Mechanical and Electrical Equipment	I	Keputusan Dirjen SDA No. 199/KPTS/D/2003
15.	Selection of Hydro-Mechanical Equipment	I	Keputusan Dirjen SDA No. 199/KPTS/D/2003
16.	Calculation of Flood Handling Capacity of Reservoirs & Spillways	D	COLENCO 2002
17.	DAMOSY Manual	D/OV	COLENCO 2002
18.	Guideline for Tailings Dams	D	Kata Pengantar Direktur Bina Teknik, Nov 2004
19.	Construction of Earth Dams	D	Kata Pengantar Direktur Bina Teknik, Nov 2004
20.	Dam Sedimentation Control & Mitigation	D	Kata Pengantar Direktur Bina Teknik, Nov 2004
21.	Visual Inspection Manual	D	Kata Pengantar Direktur Bina Teknik, Nov 2004
22.	Guidelines for Tunneling	-	
23.	Grouting Manual	D	Kata Pengantar Direktur SDW, Des 2004
24.	Cut-Off Wall/Trench Guidelines	D	Kata Pengantar Direktur SDW, Des 2004
25.	Design Criteria for Concrete Dams	U	Kata Pengantar Direktur SDW, Des 2004
26.	Roller Compacted Concrete Dams	-	
27.	Concrete Face Rockfill Dams	-	
28.	Dam Development on Soft Soils	D	SK KKB 04/KPTS/D/2007
29.	Testing of Earth Dam Embankments During Construction	-	

In addition to the above, the following standards are typically used in design, and technical discussions are based on these standards:

- ♦ 03-PRT-M-2009 The Social Engineering Guidelines for dam development
- ♦ Pd T-08-2004-A The Instrumentation of Dam Body for Earth -fill and Embankment type
- ♦ Pd T-14-2004-A The Stability Analysis of Fill Dam type due to Earthquake loads
- ♦ Pd. M-01-2004-A Construction Quality Tests for Dam Body for Fill type Dam
- ♦ Pt-M-03-2000-A The Quantification Capillarity Method for Reservoir Storage
- ♦ RSNI M-02-2002 Analysis Method of Water Seepage Control Way for fill (Urugan) Type Dam
- ♦ RSNI M-03-2002 Static Slope Stability Analysis Method of Fill (Urugan) Type Dam
- ♦ RSNI T-01-2002 The Body Design of Fill (Urugan) Type Dam
- ♦ Pdm-18-1995-03 Data Processing Methods of Climatology
- ♦ Pd T-02-2005-A Carrying capacity analysis of shallow foundation soils in the hydrological structure
- ♦ Pd T-03.1-2005-A Geotechnical Investigation for the foundation of hydrological structure vol. 1 to 3
- ♦ Pd T-03-2005-A Geotechnical Investigation Guidelines for the foundation of hydrological structure vol. 1
- ♦ Pd T-06-2004-A River Discharge Forecasting
- ♦ Pd T-10-2004-A measurement and mapping of Terrestris River
- ♦ Pd T-40-2000-A Procedures of describing and investigating field conditions in soil project
- ♦ Pd. M-01-2004-A quality test for dam body in fill (urugan) type Dam
- ♦ Pd T-44-2000-A Soil Compaction Procedures
- ♦ RSNI M-01-2002 Method of measuring the potential of land collapse in the laboratories
- ♦ SNI 03-1724-1989 Planning procedures for hydrology and hydraulics for structure on the river
- ♦ SNI 03-2415-1991 Flood discharge calculation method
- ♦ SNI 03-2435-1991 Method of laboratory testing for soil samples
- ♦ SNI 03-2849-1992 Procedures of geological mapping technique
- ♦ SNI 03-3422-1994 Testing method for soil shrinkage threshold
- ♦ SNI 03-3637-1994 Method of soil testing for weight mold with fine-grained objects test
- ♦ SNI 03-3637-1994 Method of testing the strong cohesive soil-free press
- ♦ Pd M-22-1996-03 Triaxial testing methods of cohesive soil in the absence of drainage and consolidation
- ♦ SNI 03-3961-1991 Testing methods of sediment content laying levels using gravimetric with precipitation
- ♦ SNI 03-3962-1995 Testing methods of distribution of grains of sediment laying using gravimetric with sieve
- ♦ SNI 03-4145-1996 Testing method of weight types of sediment laying with pycnometer
- ♦ Dynamic analysis guidelines-of Fill (Urugan) Type Dam, Ditjen SDA, 2008
- ♦ Construction Guidelines for Rockfill Type dam with concrete membrane (CFRD), Ditjen SDA, 2011
- ♦ Guidelines for dams hazard classification, Ditjen SDA, 2011.
- ♦ Planning criteria-Irrigation planning standard, Ditjen of Water Resources December 1986 and its revisions.
- ♦ Technical requirements section of the PT 01, 02, 03 and 04, Irrigation standard planning, Ditjen of Water Resources , December 1986 and its revisions.
- ♦ Structure Standard for Irrigation BI-01 and irrigation structure type BI-02, Irrigation standard planning, Ditjen of Water Resources, December 1986 and those revisions.
- ♦ Construction guidelines for Fill (urugan) Type Dam: An hydrological analysis, Ditjen of Water Resources, July 1999.
- ♦ Feasibility study guidelines for irrigation development, Ditjen of Water Resources, September 1998.
- ♦ Seismic map in Indonesia for dynamic analysis of hydrological structure, the Center for research and development of water resources, Ministry of Public Work, December 2012.

1.4 Documents to be Submitted

The documents to be submitted for design approval are as follows:

- (1) Permissions (prepared by the owner)
 - (a) Permissions for Dam Location and Water Use
Dam site permission from local government
 - (b) Environmental Impact Assessment (AMDAL)
Certificate of Approval from the Local Government Environment Agency (BAPEDALDA) for the Environmental Impact Assessment and Environmental Monitoring Plan
- (2) Feasibility Study Report (Business plan: loaned by the owner to the contractor)
- (3) Finalized Design Reports (Technical documents related to design: Prepared by the contractor. However, past survey and design documents are provided by the client)
 - (a) Main Report
 - (b) Executive Summary Report
 - (c) Supporting Report
Design Criteria (Design criteria applied to the project)
Geotechnical Investigation Report
Hydrological Analysis
Measurement Report
Model Test (Flood spillway hydraulic model test report: prepared by test contractor)
Design Calculation (specially stability analysis and seismic design of dams are discussed)
Design Note (Design background data collection)
Operation and Initial Maintenance (Maintenance Manual)
Technical Specification (Tender Documents)
Design Drawings
BoQ (Bulk of Quantity), etc.
 - (d) Review Design (If a design review is performed: The owner will prepare the optimum design revisions. The contractor will provide support.)
 - (e) Executive Summary on Environmental Analysis (ANDAL), Environmental Management Plan (RKL), Environmental Monitoring Plan (RPL) (Environmental Impact Assessment, Environmental Management Plan, Monitoring Plan: Prepared by the Owner).
These documents are required for the Environmental Authorization (AMDAL) issued by the Environment Agency.
 - (f) Brief description on matters related to design, including the items as attached

is "Daftar Simak"

A checklist of documents to be submitted and a summary of their outline. Also, a list of questions, etc. For example, a plan to conduct additional design studies (a document proving the plan to conduct additional necessary studies and the start of their implementation)

(g) Dam Technical Data (Project Feature of the Dam)

A dam plan outline in accordance with the Dam Safety Committee format

(h) Prospective Location for Dam Body

Photo collection of dam sites, reservoirs, quarries, etc.

Soft copies of these documents will also be required at the time of filing. A sample of list of submitted documents for dam construction is shown in table below:

Table 2-3 Documents to be submitted and responsible person


Required Documents	Remarks
(1) Permissions	
(a) Permissions for Dam Location and Water Use	地方政府によるダムサイトの使用許可
(b) Environmental Impact Assessment (ANDAL)	環境影響評価と環境モニタリングプランの地方政府の環境局 (BAPEDALDA) による承認証
(2) Feasibility Study Report	事業計画書: 施主が請負者に貸与
(3) Finalized Design Reports	(設計にかかる技術資料: 請負者が準備。但し、過去の調査・設計資料は施主が提供)
(a) Main Report	
(b) Executive Summary Report	
(c) Supporting Report	
• Design Criteria	事業に適用した設計基準
• Geotechnical Investigation Report	地質調査報告書。ボーリングログ・試験データ含む。
• Hydrological Analysis	水文解析報告書
• Measurement Report	測量結果
• Model Test	洪水吐水理模型実験報告書: 実験請負者が準備。実験結果に基づく設計修正必要
• Design Calculation	
• Design Note	
• Operation and Initial Maintenance	
• Technical Specification	技術特記仕様書のみで入札図書は、おそらく不要。
• Design Drawings	
• BoQ	工事数量表
(d) Review Design	設計のレビューを行っている場合に必要。VE による修正は、施主が準備。請負者がサポート
(e) Executive Summary on Environmental Analysis (ANDAL),	
• Environmental Management Plan (RKL),	環境影響評価 (ANDAL)、環境管理計画 (PKL)、モニタリング計画 (RPL)。
• Environmental Monitoring Plan (RPL)	これらの図書は、環境局が発行する環境認可 (AMDAL) に必要。
(f) Brief description on matters related to design, including the items as attached is "Daftar Simak"	提出書類のチェックリストとその概要をまとめたもの質問事項などのリスト。例えば、設計の追加検討の実施予定 (追加で必要な検討の実施予定 と実施にとりかかることを証明する物)。
(g) Dam Technical Data (Project Feature of the Dam)	ダム安全委員会の書式に則ったダムの計画概要書
(h) Prospective Location for Dam Body	ダムサイトや貯水池、採石場などの写真集

1.5 Process for Certificate Acquisition

The process leading up to design approval is shown in the flowchart created by DSU in Figure 2-2. Specifically, the following procedures are to be followed:

1. Preliminary meeting with DSU, presentation of dam plan and design
2. Send a letter of request for review to the DSC Secretary
3. Submit documents, reports and data to DSU

4. Document review by DSU
5. DSU site visits and comments submitted (several times)
6. Responses from project implementers
7. Technical Session (usually 2 sessions) and Q&A
8. Repeatedly modify the design and explain to DSU to create and submit the final answer
9. Plenary Session (DSC General Meeting. Held at each dam)
10. Design modification (0.5 months). DSC made recommendation to the Minister of PUPR for certification.
11. Planning approval (subject to Ministerial agenda)



◇ Figure 2-3 Screening Flowchart

2. Implementation Schedule for Certificate Acquisition

As mentioned above, the approval process involves a site inspection by the Dam Safety Committee, a technical conference, and a general meeting, so even if the application is submitted with all the necessary documents, past examples show that it takes at least four months at the earliest, and usually six months to a year.

An example of an implementation schedule that has actually been obtained is shown in Table 3-1. In this case, AMDAL (environmental impact assessment) and spillway hydraulic model tests were conducted in parallel with the approval process. In this way, even if all documents are not available, the review can begin if the implementation schedule is clear.

The general process is as follows:

- ① First comment received in _____ about two months from submission
- ② About one month has passed since the first Technical Session, which was held after the reply and correction to the comments.
- ③ About one month has passed since the second technical session started.
- ④ about one month after replying to comments and making corrections
- ⑤ Minor revisions to the report and approval by the Minister of PUPR (not finalized due to the Minister's circumstances) will take _____ approximately one month.

Table 3-1 Example of dam approval application implementation process

No	Activity Description	Concern Bodies	April				May				June				July				August				September				October				November				December			
			1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4
1	DD, Doc submitted To: DSC & Dit DGWR	Project/ Consultant																																				
2	Presentation to Directorate SDW	Project/ Consultant																																				
3	Request to DSU	Project/ Consultant																																				
4	Site visit & discussion	DSU/ Project/ Consultant																																				
5	Issuance question during site visit	DSU																																				
6	Dam Safety Evaluation	DSU																																				
7	Answering the question	Project/ Consultant																																				
8	Technical Meeting DSU I	DSU/ Project/ Consultant																																				
9	Improvement	Project/ Consultant																																				
10	Improvement	DSU																																				
11	Technical Meeting DSU II	DSU/ Project/ Consultant																																				
12	DSU report to DSC Preparation	DSU																																				
13	DSC Technical Meeting	DSU/DSC/Project/ Consultant																																				
14	Improvement	DSU/Project																																				
15	Report to DSC	DSU																																				
16	Plenary Meeting	DSC/DSU/ Project																																				
17	Issue Certificate	DSC																																				



Note: Implementation process up to approval of reservoir dams in Indonesia



Attachment 2 Completed Dam Risk Entry Form

LIST OF CONTENTS
Risk Awareness

TABLE OF CONTENTS	i
1. Tapin Dam	1
1.1. Spillway Crack	1
1.2. Diversion Leakage	3
1.3. Calculutte	5
1.4. Meratus Fault	7
2. Tukul Dam	9
2.1. Fault Foundation	9
2.2. Pore Pressure	11
2.3. Immediate Settlement	13
2.4. High Sedimentation	15
3. Napungete Dam	17
3.1. Dam Seepage	17
3.2. Dam Stability	19
3.3. Settlement	21
4. Kuningan Dam	23
4.1. Grouting	23
4.2. Settlement	25
5. Way Sekampung Dam	27
5.1. Outlet Channel	27
5.2. Spring	29
6. Bendo Dam	31
6.1. Intake Slope	31
6.2. Spillway	33
6.3. Drilling on Dam	35
6.4. Material	37
7. Pasalloreng Dam	39
7.1. Spillway Scouring	39
7.2. Tunnel Leakage	41
8. Kuereuto Dam	43
8.1. Spillway Chute	43
9. Tigadhajit Dam	45
9.1. Tunnel Sinkhole	45
9.2. Dam Foundation	47
9.3. Rockfill Material	49
10. Lausimeme Dam	51
10.1. Weakzone foundation	51
10.2. Core Material	53
11. Margatiga Dam	55
11.1. RSI Potential	55
11.2. Core Material	57
12. Gongseng Dam	59
12.1. Grouting	59
13. Pidekso Dam	61
13.1. Dam Uplift Potential	61
13.2. V-Notch	63
13.3. Cracking	65
14. Tugu Dam	67
14.1. Spillway Slope	67
14.2. Sedimentation	69
15. Karian Dam	71
15.1. Wet Core	71
16. Ciawi Dam	73
16.1. Stilling Basin Slope	73
16.2. Sliding Potential	75
17. Sukamahi Dam	77
17.1. Core Material	77
18. Leuwikeris Dam	79
18.1. Water seepage	79
19. Cipanas Dam	81
19.1. Fault	81
19.2. Saddle Dam Sliding	83
19.3. Unconformity	85
20. Semantok Dam	87
20.1. Seepage	87
21. Bener Dam	89
21.1. No Grouting	89
21.2. Concrete Slab	91
22. Sadawarna Dam	93
22.1. Fault	93
23. Bagong Dam	95
23.1. Right Bank Colluvium	95
23.2. Left Bank Colluvium	97
24. Randugunting Dam	99
24.1. Sliding Potential	99
25. Jantah Dam	101
25.1. Permeable Foundation	101
25.2. Cut off wall	103
26. Jragung Dam	105
26.1. Dam Foundation	105
27. Marangkayu Dam	107
27.1. Gas Well	107
28. Sepaku Semoi Dam	109
28.1. Differential settlement	109
29. Karalloe Dam	111
29.1. Tunnel Seepage	111
29.2. Spring on Dam Body	113
30. Lolak Dam	115

30.1. Flash Flooding	115	45.2. Grouting	177
31. Kuwil Kwangkong Dam	117	46. Rukoh Dam	179
31.1. Tunnel Seepage	117	46.1. Tunnel	179
31.2. Material	119	46.2. Inlet Sliding	181
32. Ladongi Dam	121	46.3. Spillway Drain	183
32.1. Landslide Spill	121	47. Payaseunara Dam(No Issue Data)	-
33. Pamukkulu Dam	123	48. Bajumati Dam	187
33.1. Sliding	123	48.1. Crest Crack	187
33.2. Concrete crack	125	49. Nipah Dam(No Issue Data)	-
34. Bulango Ulu Dam	127	50. Rajui Dam(No Issue Data)	-
34.1. Fault	127	51. Titab Dam	189
34.2. Side Seepage	129	51.1. Toe Seepage	189
34.3. Dam Material	131	51.2. Spring	191
35. Budong-Budong Dam	133	52. Jatigede Dam	193
35.1. Alluvial Foundation	133	52.1. Slope Stability	193
35.2. Dam Design	135	53. Teritip Dam	195
36. Ameroro Dam	137	53.1. Sliding	195
36.1. Arching	137	53.2. Settlement	197
36.2. Stilling Design	139	54. Gondang Dam	199
37. Sidan Dam	141	54.1. Dam Stability	199
37.1. Spillway Design	141	55. Sei Gong Dam	201
38. Tamblang Dam	143	55.1. Dam Slope Protection	201
38.1. Grouting	143	55.2. Landslide Spillway	203
38.2. Dam Body Leakage	145	56. Raknamo Dam	205
39. Bintang Bano Dam	147	56.1. Dam Drilling	205
39.1. Crest Crack	147	56.2. Deformation	207
39.2. Riprap	149	57. Rotiktot Dam	209
40. Temef Dam	151	57.1. Landslide History	209
40.1. Slope Fail	151	58. Tanjung Dam	211
40.2. Swelling	153	58.1. Crack Spillway	211
41. Meninting Dam	155	58.2. Riprap	213
41.1. Slope Spill	155	59. Milia Dam (No Issue Data)	-
41.2. Landslide Quarry	157	60. Sidanghuela Dam (No Issue Data)	215
41.3. Dam Material	159	61.1. Reservoir Landslide	215
42. Beringin Sila Dam	161	61.2. Conduit Seepage	217
42.1. Flash Flooding	161	61.3. Hyacinths	219
42.2. Grouting	163		
43. Tiu Suntut Dam	165		
43.1. Sliding	165		
43.2. Grouting	167		
44. Manikin Dam	169		
44.1. Tunnel Swelling	169		
44.2. Spillway Channel	171		
44.3. Abutment	173		
45. Way Apu Dam	175		
45.1. Tunnel Collapse	175		

ID:	1	Name:	Tajun	Dam Type:	Rock-filled dam with central core	Dam Height:	70.0 m
Contents of Risk	1	When the risk was identified (date)	April 2022				
	2	Project phase in which risks were recognized	2 years after impounding				
	3	Location (Structure/Area)	Upper Spillway and spillway weir				
	4	Contents of risk	Water flow, crack of spillway				
	5	Risk factors	Scouring of spillway, Spillway failure				
	6	Events in which risks were recognized	When water reservoir under spillway threshold elevation				
	7	Condition/Situation for risk realization	groundwater pressure, Dam reservoir pressure, Flooding discharge				
	8	Impact if the risk realize	Unstable water flow, Scouring due to water flow, Damage to spillway				
	9	Where risk exists	Material quality, Water pressure				
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above <input type="checkbox"/> Project Implementation				
	11	Phase of Realization	<input type="checkbox"/> Operation <input type="checkbox"/> Due to large-scale external force action <input type="checkbox"/> Due to long-term use <input type="checkbox"/> Others				
	12	Impact if the risk realize	<input type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.				
	13	Corresponding to risks	<input type="checkbox"/> Risk retention under certain conditions				
Perspectives on Risk Classification	Inspection after dam impounding → Water leakage at upper part of spillway with many crack → Water flow, crack of spillway → Scouring of spillway, Spillway failure → Spillway failure, dam break, flooding downstream → Risk reduction → Grouting on spillway						
	Overview of Causal Relationships						
Explanatory Diagram (Schematic Diagrams/ Photos, etc.)	 <p>Photo-1 Condition of spillway crack before improvement</p>						
	 <p>Photo-2 Condition of spillway crack after grouting improvement</p>						




ID:	1	Name:	Tajun	Dam Type:	Rock-filled dam with central core	Dam Height:	70.0 m
History	When the risk was recognized	Project Phase: After impounding	Date: April 2022				
	Status of corresponding	Grouting improvement had been conducted					
Project Phase	History of correspond to risks						
	Plan						
Design	 <p>Figure-1 Grouting location of spillway during construction (shop drawing construction)</p>						
	Construction	 <p>Figure-2 Grouting Depth of spillway during construction (shop drawing construction)</p>					
Impounding/ Operation/ maintenance	Leakage was found on the downstream wall of the spillway due through the segment connection gap with a discharge of 0.1 liters.						
	Investigation /analysis	Investigation analysis to identify factors, etc. Research analysis, etc. to assess impact Analysis, etc. to determine the need for and methods of response Contents of measures (avoidance, reduction, transfer or retention)					
How to respond to risk	Measures	How to deal with	Grouting				
	Retention (no measures)	Risk for decision Reason	Safety issues				
Special Notes	Expected impact	Availability and method of monitoring					
	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.) 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response- 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.						
Applicable standards	1) Technical issues 2) Spillway function 1) There may be a significant difference in settlement between the embankment and the concrete spillway structure 2) Depth of the crack reaches the reservoir water level, reservoir water will flow into the damage 3) Intensified monitoring of the area should be carried out 4) Investigation should be conducted to ensure the depth of crack						
	Meeting Minutes:	Risolah Sidang Plano Pelaksanaan Pengisian Awal Waduk dan Kesiapan Operasi, 9 September 2022					
References	Meeting Materials:	Sidang Plano Serifikasi Operasi dan Pemeliharaan, 13 Januari 2023					
	Other:	Sidang Plano Serifikasi Operasi dan Pemeliharaan, 24 Agustus 2022					

ID: 1		Name: Tajun	Dam Type: Rock-filled dam with central core	Dam Height: 70.0 m
Contents of Risk	1	When the risk was identified (date)	April 2022	
	2	Project phase in which risks were recognized	2 years after impounding	
	3	Location (Structure/Area)	Conduit of diversion	
	4	Contents of risk	Water flow, Cement dissolution	
	5	Risk factors	Conduit/tunnel collapse	
	6	Events in which risks were recognized	leaks at the top wall of the tunnel with a discharge of 1.67 liters/s	
	7	Condition/Situation for risk realization	groundwater pressure, Material dissolution,	
	8	Impact if the risk realize	Unstable top wall diversion, damage to intake channel	
	9	Where risk exists	Material strength	
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above <input type="checkbox"/> Project Implementation <input type="checkbox"/> Operation	
	11	Phase of Realization	<input type="checkbox"/> Due to large-scale external force action <input type="checkbox"/> Due to long-term use <input type="checkbox"/> Others	
	12	Impact if the risk realize	<input type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.	
	13	Corresponding to risks	<input type="checkbox"/> Risk retention under certain conditions	
Overview of Causal Relationships				
Explanatory Diagram (Schematic Diagrams/ Photos, etc.)				

ID: 1		Name: Tajun	Dam Type: Rock-filled dam with central core	Dam Height: 70.0 m
History	When the risk was recognized	Unrecognized		
	Project Phase: After impounding	Date: April 2022		
Status of corresponding		Additional Study		
History of correspond to risks				
Project Phase	Plan			
Plan	Design			
Design				
Construction	<p>Figure-1 Geological profile of diversion and leakage location (blue dot)</p>			
Impounding/ Operation/ maintenance				
Investigation /analysis	Investigation/analysis to identify factors, etc.			
	Research/analysis, etc. to assess impact /analysis, etc. to determine the need for and methods of response			
How to respond to risk	Contents of measures (avoidance, reduction, transfer) or retention	reduction, retention		
	Measures	How to deal with	special study of tunnel leakage	
Special Notes	Reason	How to deal with	safety, operation	
	Expected impact	Reason	Availability and method of information sharing	
Applicable standards /References	Availability and method of information sharing	Expected impact	<p>Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.) 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.</p> <p>1) Operation issue 2) Difficulty in maintenance 3) Correlation between the leak and the reservoir water level fluctuations should be studied 4) Equip the backfill with drainage 5) The conduit contains hydromechanical equipment, so the leaks can disrupt operations and maintenance</p>	
	Other:			
Meeting Minutes:	<p>(Describe standards related to geological study, dam design, and countermeasure design.)</p> <p>Diversion, leakage, seepage, cement dissolution</p> <p>Risalah Sidang Pleno Pelaksanaan Pengisian Awal Waduk dan Kesiapan Operans, 9 Sep7ember 2022</p>			
Meeting Materials:	<p>Sidang Pleno Sertifikasi Operans dan Pemeliharaan, 13 Januari 2023</p> <p>Sidang Pleno Sertifikasi Operans dan Pemeliharaan, 24 Agustus 2022</p>			
Other:	<p>Shop Drawing Spillway.</p>			


ID:	1	Name:	Tapin	Dam Type:	Rock-filled dam with central core	Dam Height:	70.0 m
Contents of Risk	1	When the risk was identified (date)	Jun 2023				
	2	Project phase in which risks were recognized	2 years after impounding				
	3	Location (Structure/Area)	Dam structure building				
	4	Contents of risk	seismically activity				
	5	Risk factors	Active fault				
	6	Events in which risks were recognized	During technical discussion				
	7	Condition/Situation for risk realization	Earthquake				
	8	Impact if the risk realize	dam breach				
	9	Where risk exists	Geology / strength, seismicity				
	10	Character	<input checked="" type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above <input type="checkbox"/> Project Implementation <input type="checkbox"/> Operation <input type="checkbox"/> Due to large-scale external force action <input type="checkbox"/> Due to long-term use <input type="checkbox"/> Others				
	11	Phase of Realization	<input type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affects the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input checked="" type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.				
	12	Impact if the risk realize	<input type="checkbox"/> Risk retention under certain conditions <input type="checkbox"/> dam breach				
	Perspectives on Risk Classification	13	Corresponding to risks	<input type="checkbox"/> Earthquake <input type="checkbox"/> Seismic activity <input type="checkbox"/> dam breach			
		Overview of Meratus	<input type="checkbox"/> at eastern part of Kalimantan, Meratus Fault is on one of active fault <input type="checkbox"/> Instrument monitoring <input type="checkbox"/> Risk Mitigation				
Explanatory Diagram (Schematic Diagram/ Photos, etc.)							
			Figure-1 Location of Meratus Fault and Tapin Dam (PUSGEN, 2017)				

ID:	1	Name:	Tapin	Dam Type:	Rock-filled dam with central core	Dam Height:	70.0 m
History		Recognition or not in the past	Unrecognized				
		When the risk was recognized	Project Phase: After Impounding	Date: April 2022			
Project Phase		Status of corresponding	-				
		History of correspond to risks	-				
Plan			-				
		Design	the information of design report there was no fault observer, only joint was observed around the lipan dam				
Construction							
			Figure-1 Geological map of Tapin Dam				
Impounding Operation/ maintenance			-				
			-				
Investigation /analysis		Investigation analysis to identify factors, etc.	-				
		Research analysis, etc. to assess impact	-				
		Analysis, etc. to determine the need for and methods of response	-				
		Contents of measures (avoidance, reduction, transfer) or retention	Retention				
How to respond to risk		Measures	-				
		How to deal with	-				
		Basis for decision	-				
		Reason	active fault meratus is >100 km away from Tapin dam				
		Expected impact	No direct impact from meratus fault, small seismicity activity				
		Availability and method of monitoring	-				
Special Notes		Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operations, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.	-				
		1) technical issue	-				
Applicable standards		leakage, seepage, cement dissolution	-				
		Meeting Minutes:	Risalah Sidang Pleno Pelaksanaan Pengisian Awal Waduk dam Kesatuan Operasi, 9 September 2022				
References		Meeting Materials:	Sidang Pleno Sertifikasi Operasi dan Pemeliharaan, 13 Januari 2023 Sidang Pleno Sertifikasi Operasi dan Pemeliharaan, 24 Agustus 2022				
		Other:	Shop Drawing Spillway				

ID:	2	Name:	Tukul	Dam Type:	Rock random zonal with central core	Dam Height:	70.3 m
Concepts of Risk	1	When the risk was identified (date)	2012				
	2	Project Phase in which risks were recognized	Design, Investigation				
	3	Location (Structure/Area)	Dam foundation				
	4	Contents of risk	Piping of foundation				
	5	Risk factors	Dam material leaching				
	6	Events in which risks were recognized	Many fault observed during foundation clearing and excavation				
	7	Condition/Situation for risk realization	Earthquake, Impounding				
	8	Impact if the risk realize	Dam break causing flooding				
	9	Where risk exists	Geology, Permeability, water pressure				
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above				
	11	Phase of Realization	<input type="checkbox"/> Project Implementation <input type="checkbox"/> Operation <input type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others				
	12	Impact if the risk realize	<input type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affects the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input checked="" type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.				
	13	Corresponding to risks	<input type="checkbox"/> Risk retention under certain conditions				
Overview of Causal Relationships	some faults were observed during design investigation		during excavation for construction more much fault were observed => detailed geological mapping	fault through foundation => excavation for soft material and replaced by	Grouting and installing tools on e/fault	piping, dam break and flooding	early warning for mitigation
	additional instrument for other fault for monitoring						
Explanatory Diagram (Schematic Diagram/ Photos, etc)				Photo-1 Fault at dam foundation (F3 Fault)			
							

ID:	2	Name:	Tukul	Dam Type:	Rock random zonal with central core	Dam Height:	70.3 m
History	recognition or not in the		Unrecognized				
	If the risk was recognized						
	Status of corresponding		Project Phase: Design	Date: 2012			
	History of correspond to risks						
Plan	grouting recommendation for dam improvement						
Design	grouting recommendation for dam improvement						
Construction	Instrument installation for all fault to monitor						
Impounding Operation/ maintenance	Investigation/analysis to identify factors, etc.		visual outcrop				
	Research/analysis, etc. to assess impact of response		additional instrument installation				
How to respond to risk	Contents of measures (avoidance, reduction, transfer) or retention		How to deal with Basis for decision Reason Expected impact	clearing the weak material and replaced with dental concrete Dam safety			
	Availability and method of information sharing						
	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.						
	Special Notes						
Applicable standards	1) piezometer can be installed from upstream to downstream so that a thorough observation can be carried out.						
References	(Describe standards related to geological study, dam design, and countermeasure design.) Evaluasi Pelaksanaan Aval Waduk dan Kesepakatan Operasional, 25 Agustus 2022 Laporan Abstr (PT Global Parasindo Jaya, 2012) Dit Pembangunan Waduk Tukul						

ID:	2	Name:	Tukul	Dam Type:	Rock random zonal with central core	Dam Height:	70.3 m	
Concerns of Risk	1	When the risk was identified (date)	2012					
	2	Project phase in which risks were recognized	Impounding					
	3	Location (Structure/Area)	Dam core material					
	4	Contents of risk	Piping of dam					
	5	Risk factors	Pore water pressure					
	6	Events in which risks were recognized	Piezometer monitoring show that there is high pore water pressure in dam body					
	7	Condition/Situation for risk realization	Impounding					
	8	Impact if the risk realize	Dam break causing flooding					
Perspectives on Risk Classification	9	Where risk exists	Geology, Permeability, water pressure, core material					
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above					
	11	Phase of Realization	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others					
	12	Impact if the risk realize	<input checked="" type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affects the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input checked="" type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.					
	13	Corresponding to risks	<input type="checkbox"/> Risk retention under certain conditions <input type="checkbox"/> Risk reduction					
	Overview of Causal Relationships		high water pressure at piezometer reading	Monitoring after impounding, there is indication of high pressure in dam body	high water level increases the pore pressure	piping occurs due to pore pressure	dam break and flooding	early warning for mitigation



ID:	2	Name:	Tukul	Dam Type:	Rock random zonal with central core	Dam Height:	70.3 m
History		When the risk was recognized	Unrecognized				
		Status of corresponding	Continuing monitoring				
Project Phase					History of correspond to risks		
Plan							
Design							
Construction							
Impounding							
Operation/maintenance							
Investigation/analysis							
How to respond to risk		Measures	How to deal with				
		Retention (no measures)	Basis for decision				
Special Notes		Availability and method of information sharing	Reason				
		Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.	Expected impact				
Applicable standards							
Keywords							
References							

ID:	2	Name:	Tukul	Dam Type:	Rock random zonal with central core	Dam Height:	70.3 m	
Contents of Risk	1	When the risk was identified (date)	August 2022					
	2	Project phase in which risks were recognized	Impounding					
	3	Location (Structure/Area)	Dam core material					
	4	Contents of risk	Dam deformation, cracking					
	5	Risk factors	Dam settlement, core material					
	6	Events in which risks were recognized	Multilayer settlement instrument show high settlement of dam body (>1%)					
	7	Conditions/Situation for risk realization	Overburden					
	8	Impact if the risk realize	Water leakage, dam break					
	9	Where risk exists	Core material					
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above					
	Perspectives on Risk Classification	11	Phase of Realization	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others				
		12	Impact if the risk realize	<input checked="" type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affects the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input checked="" type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.				
		13	Corresponding to risks	<input type="checkbox"/> Risk retention under certain conditions				
Overview of Causal Relationships		Immediate settlement	Multilayer settlement instrument show high settlement of dam body (~1%)	Overburden, consolidation of core material	Dam deformation, cracking	Water leakage, dam break	early warning for mitigation	
							Monitoring instrument of dam body	
Explanatory Diagram (Schematic Diagram/ Photos, etc)								
		<p>Figure-1 Graphic of multilayer settlement at dam body</p>						

ID:	2	Name:	Tukul	Dam Type:	Rock random zonal with central core	Dam Height:	70.3 m
History		When the risk was recognized	Unrecognized				
		Status of corresponding	Continuing monitoring				
Project Phase		History of correspond to risks					
Plan							
Design		no wet core material initiation during design stage					
Construction		no information					
Impounding		there is indication of wet core for core material from the dam settlement more than 1%.					
Operation/ maintenance							
Investigation /analysis		Investigation/analysis to identify factors, etc.					
		Research/analysis, etc. to assess impact					
How to respond to risk		Analysis, etc. to determine the need for and methods of response					
		Contents of measures (avoidance, reduction, transfer) or retention					
Special Notes		Measures	How to deal with				
		Retention (no measures)	Basis for decision				
		Availability and method of monitoring	Reason				
		Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.	Expected impact				
Applicable standards		Technical issues					
Keywords		The condition during construction should be studied in detail					
References		(Describe standards related to geological study, dam design, and countermeasure design.) Settlement, dam deformation Meeting Minutes: Evaluasi Pelaksanaan Awal Waduk dan Kesiapan Operasional, 25 Agustus 2022 Meeting Materials: Paparan Persiapan OP, 25 Agustus 2022 Other: Laporan Akhir (PT Global Parasindo-Java, 2012) Dd Pembangunan Waduk Tukul					

ID:	2	Name:	Tukul	Dam Type:	Rock random zonal with central core	Dam Height:	70.3 m					
Contents of Risk	1	When the risk was identified (date)	2012									
	2	Project Phase in which risks were recognized	Design									
	3	Location (Structure/Area)	Reservoir area									
	4	Contents of risk	Decreasing storage capacity									
	5	Risk factors	Sedimentation									
	6	Events in which risks were recognized	Raining, erosion, landslide									
	7	Condition/Situation for risk realization	Decreasing flooding control function									
	8	Impact if the risk realize	Core material									
	9	Where risk exists	<input checked="" type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above									
	10	Character	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others									
	11	Phase of Realization	<input type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input checked="" type="checkbox"/> Consider mitigation measures as risk avoidance is difficult. <input type="checkbox"/> Risk retention under certain conditions									
	12	Impact if the risk realize										
	13	Corresponding to risks										
Overview of Causal Relationships	High sedimentation		During design had been mentioned that Tukul Dam has high sedimentation potential		During sedimentation study at design stage		Raining, erosion, landslide		Decreasing flooding control function		Reduction	
					Construction sediment control building							
Explanatory Diagram (Schematic Diagram/ Photos, etc)												

ID:	2	Name:	Tukul	Dam Type:	Rock random zonal with central core	Dam Height:	70.3 m
History	When the risk was recognized		Recognized				
	Project Phase:		Design	Date: 2012			
Status of corresponding		Considering to built sediment control at the dam upstream					
History of correspond to risks							
Project Phase							
Plan							
Design							
Construction							
Impounding							
Operation/ maintenance							
Investigation /analysis	Investigation/analysis to identify factors, etc.						
	Research/analysis, etc. to assess impact						
	Analysis, etc. to determine the need for and methods of response						
	Contents of measures (avoidance, reduction, transfer or retention)						
How to respond to risk	Measures		How to deal with		Sabot or sediment control building at upstream area		
	Retention (no measures)		Basis for decision		Dam function		
	Availability and method of monitoring		Reason				
			Expected impact				
Availability and method of information sharing							
Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.							
Technical issues							
Special Notes							
a. Prepare a program for the construction of the Sabot dam system to reduce the discharge of sediment entering the reservoir;							
b. Coordinate with related agencies to carry out integrated upstream watershed conservation by involving various related agencies and the community.							
Applicable standards							
(Describe standards related to geological study, dam design, and countermeasure design.)							
Keywords							
Sedimentation, sediment control							
Meeting Minutes:							
Evaluasi Pelaksanaan Awal Waduk dan Kesiapan Operasional, 25 Agustus 2022							
Meeting Materials:							
Paparan Persiapan OP, 25 Agustus 2022							
Other:							
Laporan Akhir (PT Global Parasindo-Java, 2012) Dd Pembangunan Waduk Tukul							

ID:	3	Name:	Napun Gete	Dam Type:	Rock-filled dam with central core	Dam Height:	52.0 m
Concepts of Risk	1	When the risk was identified (date)	June 22				
	2	Project Phase in which risks were recognized	After impounding				
	3	Location (Structure/Area)	Dam body				
	4	Contents of risk	Dam stability				
	5	Risk factors	Sliding of dam body				
	6	Events in which risks were recognized	Inspection after impounding for dam operation permit				
	7	Conditions/Situation for risk realization	heavy rain, flooding				
	8	Impact if the risk realize	dam break causing flooding				
	9	Where risk exists	Dam body, Dam material				
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above				
	11	Phase of Realization	<input type="checkbox"/> Operation <input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others				
	12	Impact if the risk realize	<input checked="" type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affects the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.				
	13	Corresponding to risks	<input type="checkbox"/> Risk retention under certain conditions				
Overview of Causal Relationships	Dam design → during inspection for operation permit, the leakage of dam body was observed in downstream of dam (dam toe and abutment)		Discharge monitoring → further study → dam break				
	additional counter-weight, controlling water pressure at abutment		Risk reduction				
Explanatory Diagram (Schematic Diagram/ Photos, etc)							
	Figure-1 Water leakage location at downstream of dam body (blue dot)						

ID:	3	Name:	Napun Gete	Dam Type:	Rock-filled dam with central core	Dam Height:	52.0 m
History	When the risk was recognized	Unrecognized					
	Project Phase: after impounding	Project Phase: after impounding					Date: June 2022
Project Phase	Status of corresponding	Further study to unidentified water source					
	History of correspond to risks						
Plan							
Design	During the excavation of the foundation (construction phase), there were several springs/seepage formed due to excavation of the main dam foundations. Along with the cement grout injection of grouting work on the foundation footprint, some seepage that originally appeared on the surface of the maindam excavation began to disappear, leaving 2 locations at sta. 340 and sta. 540.						
Construction				Photo-1 Spring at STA 340 during construction of Napun Gete Dam			
				Figure-1 Engineering geology profile of Napun Gete Dam show shallow water level and cut by slope excavation			
Impounding/Operational/maintenance							
Investigation/analysis	Investigation/analysis to identify factors, etc.						
	Research/analysis, etc. to assess impact						
How to respond to risk	Analysis, etc. to determine the need for and methods of response						
	Contents of measures (avoidance, reduction, transfer) or retention						
Special Notes	Measures	How to deal with	Counter Weight (considering)				
	Retention (no measures)	Basis for decision Reason	Water source, uplift				
Applicable standards	Availability and method of information sharing	Expected impact					
	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.						
References	1) Technical issue						
	1) Routine monitoring of seepage or leaks should be carried out 2) A cross-sections should be made for further analysis of the creep length and the amount of uplift at the leak points in the downstream part of the dam body. 3) Consultant should also recommend treatment, for example, by adding a counterweight to the downstream part						
Applicable standards	(Describe standards related to geological study, dam design, and countermeasure design.)						
Keywords	Leakage, Dam Body						
References	Meeting Minutes:						
	Risetlah Sidang Pleno Pembahasan Pengisian Awal Waduk dalam rangka Izin Operasi, 12 Januari 2023 Risetlah Sidang Teknis Pelaksanaan Pengisian Awal Waduk dan Keselamatan Operasi, 31 Oktober 2022 Laporan Abstr (PT. Indra Karya, 2016): Detail Desain dan Model Test Bendungan Napun Gete						

ID:	3	Name:	Napun Gete	Dam Type:	Rock-filled dam with central core	Dam Height:	52.0 m
Concepts of Risk	1	When the risk was identified (date)	October 2022				
	2	Project phase in which risks were recognized	Impounding				
	3	Location (Structure/Area)	Dam body				
	4	Contents of risk	Dam stability				
	5	Risk factors	Condition of construction material during technical discussion the dam stability analysis show sliding in large zone				
	6	Events in which risks were recognized	Earthquake, impounding				
	7	Condition/Situation for risk realization	Dam breach				
	8	Impact if the risk realize	Dam material strength,				
	9	Where risk exists	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above				
	10	Character	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others				
	11	Phase of Realization	<input type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input checked="" type="checkbox"/> Consider mitigation measures as risk avoidance is difficult. <input type="checkbox"/> Risk retention under certain conditions				
	12	Impact if the risk realize					
	13	Corresponding to risks					
Perspectives on Risk Classification	After impounding stability analysis was carried out and show that sliding plane through the rock fill zone deeply		Rock material of construction need to be stabilized in more detail	Unstable dam body	Dam break	Risk reduction	
	Dam stability analysis after impounding						
Overview of Causal Relationships							
Explanatory Diagram (Schematic Diagram/ Photos, etc)							






Figure-1 Dam stability analysis for upstream slope of napun gete dam (FK=1.29 with seismic load)

Figure-2 Dam stability analysis for downstream slope of napun gete dam (FK=1.40 with seismic load)

ID:	3	Name:	Napun Gete	Dam Type:	Rock-filled dam with central core	Dam Height:	52.0 m
History	Recognition or realization		Unrecognized				
	When the risk was recognized		October 2022				
Project Phase	Project Phase:		Impounding				
	Status of corresponding		Further study				
Plan	History of correspond to risks						
	During Design there was random zone (zone 4)						
Design	Figure-1 Typical design of napun gete dam during design stage						
	In the construction phase there is no random zone, but in the stability analysis almost the entire landslide plane goes through the rockfill zone						
Construction	Figure-2 Asbuild drawing of napun gete dam						
	The safety factor of dam stability is above the specified requirements						
Impounding/Operation/maintenance	Investigation/analysis to identify factors, etc.		-				
	Research/analysis, etc. to assess impact of response		-				
How to respond to risk	Contents of measures (avoidance, reduction, transfer) or retention		Reduction				
	Measures		How to deal with	under confirmation of material condition			
Special Notes	Basis for decision		Reason	dam material, dam safety			
	Expected impact		Availability and method of information sharing	-			
Applicable standards/References	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.						
	Technical issue						
Applicable standards/References	It is necessary to ensure that zone 4 is a rock-fill zone or random rock.						
	(Describe standards related to geological study, dam design, and countermeasure design.)						
Meeting Minutes:	Dam stability, rock fill dam						
	Risalah Sidang Pleno Pembahasan Pengisian Awal Waduk dalam rangka Zin Operasi, 12 Januari 2023						
Other:	Risalah Sidang Teknis Pelaksanaan Pengisian Awal Waduk dan Keselamatan Operasi, 31 Oktober 2022						
	Paparan Sidang Pleno Pembahasan Pengisian Awal Waduk dalam rangka Zin Operasi, 12 Januari 2023						
Other:	Laporan Akhir (PT. Indra Karya, 2016): Detail Desain dan Model Test Bendungan Napun Gete						

1	When the risk was identified (date)	August 2021
2	Project phase in which risks were recognized	Impounding
3	Location (Structure/Area)	Dam body / core zone
4	Contents of risk	Dam deformation
5	Risk factors	Internal cracking
6	Events in which risks were recognized	during monitoring of multi layer settlement, sudden settlement was observed
7	Conditions/Situation for risk realization	Impounding, loading
8	Impact if the risk realize	Water leakage, dam breach
9	Where risk exists	Dam material, construction
10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above
11	Phase of Realization	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others
12	Impact if the risk realize	<input type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance
13	Corresponding to risks	<input checked="" type="checkbox"/> Consider mitigation measures as risk avoidance is difficult. <input type="checkbox"/> Risk retention under certain conditions



Recognition or not in the past	Unrecognized
When the risk was recognized	Project Phase: Impounding
Status of corresponding	Considering investigation and continuing monitoring of dam body and instrumentation
Project Phase	History of correspond to risks
Plan	
Design	

Based on investigation during design, the borrow area has clay material that characterized by most of dry density is less 1.2 gram/cm² and liquid limit more than 70%.

The implementation of core material embankment during construction in accordance with specifications

Table-1 Specification and laboratory test result of core zone material

No	Uraian	Setiaan	Spesifikasi	Head Uji Laboratorium	Jumlah Pengujian	Hasil Uji Pelaksanaan	Jumlah pengujian	Keterangan
1	Moisture Ratio	mm	50	38.10	12	38.10	4	
2	Gravel Content	%	-	6.50 - 8.71	12	10.2 - 18.57	6	SM (G-10-100)
3	Clay Content	%	-	23.61 - 36.58	12	24.68 - 27.1	6	
4	Clay Content	%	-	31.01 - 47.53	12	24.30 - 30.43	6	SM (G-10-275)
5	LL (Liquid Limit)	%	70	64.09 - 73.63	12	63.36 - 66.01	6	
6	Plastic Limit (PI)	%	<50% (Dusman Wert)	32.07 - 47.1	12	34.30 - 39.53	6	SM (G-10-600)
7	PI (Plastic Index)	%	11.45	21.08 - 34.41	12	23.20 - 29.26	6	SM (G-10-100)
8	PI (Plastic Index)	%	11.45	21.08 - 34.41	12	23.20 - 29.26	6	SM (G-10-100)
9	PI (Plastic Index)	%	11.45	21.08 - 34.41	12	23.20 - 29.26	6	SM (G-10-100)
10	Sub Maximum Dry Density (SMDD)	g/cm ³	1.97 (Dusman Wert)	1.28 - 1.41	12	1.22 - 1.25	6	SM (G-10-200)
11	Initial Dry Density (ID)	g/cm ³	1.00 (G-1)	-	-	1.12 - 1.18	105	SM (G-10-200)
12	Final Water Content	%	15	-	-	15.00 - 36.34	105	SM (G-10-200)
13	Degree of Density (DD)	%	95	-	-	95.42 - 98.26	105	SM (G-10-200)
14	SDS Permissible (P)	cm/sec	14.10 (Dusman Wert)	-	-	1.05 - 1.08	105	SM (G-10-200)
15	SDS Permissible (P)	cm/sec	14.75 (Design Value)	-	-	1.05 - 1.08	105	SM (G-10-200)
16	Shear Stress dan Rata-rata	kg/cm ²	0	0.144	-	0.144	3	0.140
17		kg/cm ²	0	0.144	-	0.144	3	0.140
18		kg/cm ²	0	0.144	-	0.144	3	0.140
19		kg/cm ²	0	0.144	-	0.144	3	0.140
20		kg/cm ²	0	0.144	-	0.144	3	0.140

sudden settlement occurred 8 month after impounding

Investigation/analysis to identify factors, etc.	-
Research/analysis, etc. to assess impact	-
Analysis, etc. to determine the need for and methods of response	-
Contents of measures (avoidance, reduction, transfer) or retention	Mitigation
Measures	Monitoring
How to deal with	design condition
Basis for decision	-
Reason	-
Expected impact	-
Availability and method of monitoring	-
Availability and method of information sharing	-

Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.

Technical issues

An inspection should be carried out whether the dam body material includes collapsible soil. Collapsible soil is kind of soil that is very susceptible to collapse due to saturation.

Settlement, crack

(Describe standards related to geological study, dam design, and countermeasure design.)

Meeting Minutes: Risetlah Sidang Pleno Pembahasan Pengisian Awal Waduk dalam rangka Izin Operasi, 12 Januari 2023


Meeting Materials: Risetlah Sidang Teknis Pelaksanaan Pengisian Awal Waduk dan Keseluruhan Operasi, 31 Oktober 2022

Other: Laporan Akhir (PT. Indra Karya, 2016). Detail Desain dan Model Test Bendungan Napun Gate

Paparan Sidang Pleno Pembahasan Pengisian Awal Waduk dalam rangka Izin Operasi, 12 Januari 2023

Laporan Akhir (PT. Indra Karya, 2016). Detail Desain dan Model Test Bendungan Napun Gate

1	When the risk was identified (date)	June 2022
2	Project phase in which risks were recognized	Impounding
3	Location (Structure/Area)	Dam Foundation
4	Contents of risk	Piping of foundation, uplift of dam body
5	Risk factors	Ineffective grouting indication
6	Events in which risks were recognized	Piezometer monitoring of foundation
7	Conditions/Situation for risk realization	High water level of reservoir
8	Impact if the risk realize	Dam break causing flooding
9	Where risk exists	Geology, Permeability, Design/Foundation treatment
10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above <input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others <input checked="" type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affects the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult. <input checked="" type="checkbox"/> Risk retention under certain conditions
11	Phase of Realization	
12	Impact if the risk realize	
13	Corresponding to risks	



at the time of dam construction the dam foundation piezometer pressure in the downstream section has a smaller value, but at the time of impounding the downstream and upstream piezometer readings are almost the same.




Figure-1 Piezometer reading at dam foundation (downstream and upstream of grouting)

History	Unrecognized Project Phase: Impounding Date: June 2022
Project Phase	History of correspond to risks
Plan	
Design	using grouting to improve permeability of dam foundation During construction grouting was conducted for foundation improvement
Construction	<p>Figure-1 Layout of grouting during construction</p>
Impounding/Operation/maintenance	Indicative grouting indication from piezometer monitoring
Investigation/analysis	<ul style="list-style-type: none"> Investigation/analysis to identify factors, etc. Research/analysis, etc. to assess impact Analysis, etc. to determine the need for and methods of expense Contents of measures (avoidance, reduction, transfer) or retention
How to respond to risk	<ul style="list-style-type: none"> Measures Retention (no measures) Availability and method of monitoring Availability and method of information sharing <p>Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.</p> <p>1) technical issues 2) dam safety</p>
Special Avotes	<ul style="list-style-type: none"> Flow to deal with Basic for decision Reason Expected impact <p>The uplift potential in the dam foundation should be checked to ensure that the dam body is in a safe/stable condition from the potential uplift.</p>
Applicable standards	(Describe the standards related to geological study, dam design, and countermeasures design.)
Keywords	Grouting, dam foundation
Meeting Minutes:	Draf Rasalah Diskusi Teknis pelaksanaan Pengisian Awal Waduk dam Kesapan Operasi, 21 September 2023
Meeting Materials:	Paparan Sidang Penuh Impounding, 10 Juni 2021
Other:	Laporan Akhir (PT. Tata Guna Patria, 20 Oktober 2009) Detail Desain Waduk Cileleung di Kabupaten Kumang

ID: 4		Name: Kuningan	Dam Type: Zonal with vertical core	Dam Height: 43.0 m
Concepts of Risk	1	When the risk was identified (date)	January 2019	
	2	Project phase in which risks were recognized	Construction	
	3	Location (Structure/area)	Dam body, core material	
	4	Contents of risk	Settlement	
	5	Risk factors	Material / core consolidation	
	6	Events in which risks were recognized	Multi layer settlement instrument monitoring	
	7	Condition/Situation for risk realization	Material consolidation, embankment load	
	8	Impact if the risk realize	Dam body deformation, overtopping, cracking on dam	
	9	Where risk exists	Dam material, dam body	
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above <input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation	
	11	Phase of Realization	<input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others	
	12	Impact if the risk realize	<input checked="" type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.	
	13	Corresponding to risks	<input checked="" type="checkbox"/> Risk retention under certain conditions	
Overview of dam deformation during construction and after impounding	Monitoring of dam deformation	Multi layer settlement monitoring during construction and after impounding		
	Consolidation of core material	High settlement Overtopping, cracking on dam Retention		

Settlement that occurred on Kuningan Dam is more than 60 cm where the dam is 43 m. The amount of settlement that occurs is highly correlated with the condition of the material at the time it is filled and the way it is filled.




Figure-1 Settlement graph of Kuningan dam

ID: 4		Name: Kuningan	Dam Type: Zonal with vertical core	Dam Height: 43.0 m
History	Recognition or non recognition	Recognized		
	When the risk was recognized	Construction		
	Status of corresponding	History of correspond to risks		
	Project Phase	History of correspond to risks		
Plan	Plan	History of correspond to risks		
	Design	History of correspond to risks		
Construction	Construction	<p>Figure-1 graphic of field density test of Kuningan Dam (core zone)</p> <p>Figure-1 Grain size distribution of Kuningan dam core material</p>		
	Impounding	High settlement was observed after impounding		
Operational maintenance	Operational maintenance	Multi layer settlement monitoring		
	Investigation /analysis	Investigation/analysis to identify factors, etc. Research/analysis, etc. to assess impact Analysis, etc. to determine the need for and methods of response Contents of measures (avoidance, reduction, transfer) or retention		
How to respond to risk	Measures	How to deal with		
	Retention (no measures)	Reason Further investigation will be conducted water leakage from dam body		
Special Notes	Availability and method of information sharing	Availability and method of information sharing		
	Challenges	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.		
Applicable standards	Applicable standards	1) Technical issue 2) Operation issue		
	Remarks	<ul style="list-style-type: none"> The cause of the high settlement at the dam's left abutment should be evaluated, examining the possibility of the embankment slope being too steep. The amount of settlement should be calculated at the time of completion of construction until completion of consolidation to confirm the accuracy of the counter height that has been installed. 		
References	References	(Describe standards related to geological study, dam design, and countermeasure design.)		
	Other:	Draf Riset/Diskusi Teknis pelaksanaan Pengisian Awal Waduk dan Kesepakatan Operansi, 21 September 2023 Laporan Sidang Pleno Impounding, 10 Juni 2021 Laporan Akhbar (PT. Jata Guna Patra, 20 Oktober 2009) Detail Desain Waduk Cileunwang di Kabupaten		

ID:	5	Name:	Way Sekampung	Dam Type:	Rock-filled dam with central core	Dam Height:	47.0 m
Perspectives on Risk Classification	1	When the risk was identified (date)	2022				
	2	Project Phase in which risks were recognized	Inspection after impounding for operation permit				
	3	Location (Structure/tree)	Outlet channel				
	4	Contents of risk	Unstable slope; Slope sliding				
	5	Risk factors	Slope without protection				
	6	Events in which risks were recognized	Some erosion and surface sliding were found after impounding				
	7	Conditions/Situation for risk realization	Rain water run off				
	8	Impact if the risk realize	landslide at downstream of outlet channel, disturbed function				
	9	Where risk exists	Slope stability, slope protection				
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above				
	11	Phase of Realization	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation				
	12	Impact if the risk realize	<input type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others <input type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.				
	13	Corresponding to risks	<input checked="" type="checkbox"/> Risk retention under certain conditions				
Overview of Causal Relationships	<div style="display: flex; justify-content: space-around; align-items: center;"> <div style="border: 1px solid black; padding: 5px; text-align: center;"> slope excavation for channel </div> <div style="text-align: center;"> → erosion and surface sliding when inspection for operational permit </div> <div style="border: 1px solid black; padding: 5px; text-align: center;"> no action </div> <div style="text-align: center;"> → unstable slope due to surface erosion </div> <div style="border: 1px solid black; padding: 5px; text-align: center;"> slope failure; material fill up the channel </div> </div>						
	<div style="display: flex; justify-content: space-around; align-items: center;"> <div style="border: 1px solid black; padding: 5px; text-align: center;"> protection for slope surface => minimized erosion </div> <div style="text-align: center;"> ↕ </div> <div style="border: 1px solid black; padding: 5px; text-align: center;"> Risk reduction </div> </div>						
Explanatory Diagram (Schematic Diagram/ Photos, etc)	rock conditions are weathered and are tuff sandstones which is sensitive to air						

Photo-1 Condition of slope at outlet channel

ID:	5	Name:	Way Sekampung	Dam Type:	Rock-filled dam with central core	Dam Height:	47.0 m
History	When the risk was recognized	Project Phase: Inspection (impounding)	Date: 2022				
	Status of corresponding	recommended to protect the slope and install the drainage					
Project Phase	History of correspond to risks						
	Plan						
Design	the unstable slope is sandstone-conglomerate lithology unit (yellow color), with moderately to highly weathered and rock class D at upper part and CL at lower part						
Construction	Figures-1 Situation surrounding outlet channel on geological map						
Impounding/Operational/maintenance							
Investigation/analysis	Investigation/analysis to identify factors, etc.						
	Research/analysis, etc. to assess impact						
Measures	Analysis, etc. to determine the need for and methods of response						
	Contents of measures (avoidance, reduction, transfer or retention)						
How to respond to risk	Measures	How to deal with	protected the slope with concrete on slope surface				
	Retention (no measures)	Basis for decision Reason	rock condition				
Special Notes	Availability and method of information sharing	Expected impact					
	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.) 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.						
1) Technical issue							
The rock condition is easily eroded by water and sensitive to the air, surface protection should be consulted to minimize erosion. The location that landslide had occurred can be filled with rock material and surface drainages should be installed too.							
Applicable standards/References	(Describe standards related to geological study, dam design, and countermeasure design.)						
	Landslide, Slope Stability, Weathered						
Meeting Minutes:							
	Meeting Minutes:						
References	Papanan Sidiang, Teknik Perencanaan Operasi dan Pemeliharaan, : 13 April 2022						
	Laporan Rangkaiasan (PT, Indra Karya, 2016). Scitifikasi Desain Bendungan Way Sekampung						
Other:							

ID:	5	Name:	Way Selampung	Dam Type:	Rock-filled dam with central core	Dam Height:	47.0 m
Contents of Risk	1	When the risk was identified (date)	2017				
	2	Project phase in which risks were recognized	Construction				
	3	Location (Structure/tree)	downstream of main dam, dam abutment, near to outlet tunnel				
	4	Contents of risk	Sliding, outlet tunnel damage				
	5	Risk factors	Water seepage				
	6	Events in which risks were recognized	During excavation around the tunnel				
	7	Conditions/Situation for risk realization	ground water level				
	8	Impact of the risk realize	Tunnel structure damage, channel/instrument damage				
Pe representatives of Risk Classification	9	Where risk exists	Geology, groundwater				
	10	Cha meter	<input checked="" type="checkbox"/> Mainly caused by external forces <input type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above				
	11	Phase of Realization	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input checked="" type="checkbox"/> Due to large-scale external force action <input type="checkbox"/> Due to long-term use <input type="checkbox"/> Others				
	12	Impact of the risk realize	<input type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Fastlately risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.				
	13	Co responding risks	<input type="checkbox"/> Risk retention under certain conditions				
	Overview of Cause-Relationship	Seepage comes out of excavation area increased outlet traffic		Causing slope seepage	Sliding outlet tunnel damage / channel/instrument damage	Risk retention	Creeping water flow
		Spring comes out of excavation area increased outlet traffic		Causing slope seepage	Sliding outlet tunnel damage / channel/instrument damage	Risk retention	Creeping water flow
	Explanatory Diagram (Schematic Diagram/Photo, etc.)			Figure-1 Location of seepage/ spring			
				Figure-2 Geology profile of tunnel from inlet to outlet			

ID:	5	Name:	Way Selampung	Dam Type:	Rock-filled dam with central core	Dam Height:	47.0 m
History	Recognition of risk in the project phase		Recognized				
	Status of core project phase		Construction				Date: 2017
Project Phase	Status of core project phase		Recognized				
	Status of core project phase		Construction				
Plan	Status of core project phase		Recognized				
	Status of core project phase		Construction				
Description	Status of core project phase		Recognized				
	Status of core project phase		Construction				
Construction	Status of core project phase		Recognized				
	Status of core project phase		Construction				
Impact	Status of core project phase		Recognized				
	Status of core project phase		Construction				
Operation/maintenance	Status of core project phase		Recognized				
	Status of core project phase		Construction				
Special Notes	Status of core project phase		Recognized				
	Status of core project phase		Construction				
Applicable standards	Status of core project phase		Recognized				
	Status of core project phase		Construction				
References	Status of core project phase		Recognized				
	Status of core project phase		Construction				

1	When the risk was identified (date)	June 21
2	Project phase in which risks were recognized	Construction
3	Location (Structure/Area)	Intake
4	Contents of risk	Unstable slope
5	Risk factors	Intake slope failure, Intake damage
6	Events in which risks were recognized	Many cracks and discontinuity on intake slope so doublehill during technical season
7	Condition/Situation for risk realization	Impounding, Earthquake
8	Impact if the risk realize	Landslide, Intake damage, Intake malfunction
9	Where risk exists	Discontinuity, Foundation
10	Character	<input checked="" type="checkbox"/> Mainly caused by external forces <input type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above <input type="checkbox"/> Project Implementation
11	Phase of Realization	<input checked="" type="checkbox"/> Operation <input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others
12	Impact if the risk realize	<input checked="" type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.
13	Corresponding to risks	<input checked="" type="checkbox"/> Risk retention under certain conditions
Overview of Causal Relationships	Incline shaft intake located on steep slope with many	During technical season, intake slope was doublehill about the stability
	protection using sortcrete and reinforcement	unstable slope causing sliding additional reinforcement by sealing grout and surface drainage damage to intake, malfunction of intake Risk reduction



Photo-1 Location of sliding potential near to intake








Figure-1 Geographical profile of intake slope

History	Recognition or non-recognition of risk	Unrecognized
	If the risk was recognized	Project Phase: Construction
Project Phase	Status of corresponding	Sortcrete and anchor installation
	History of correspond to risks	
Plan		
Design	first intake design is drop and level to incline shaft considering several conditions	
	Based on consultation and base:	
Construction	Figure-1 Stability analysis of intake slope	Figure-2 Protection and reinforcement of slope
	Dam initial impounding was carried out in July 2021	
Operational/maintenance	Investigation/analysis to identify factors, etc.	Slope stability analysis
Investigation/analysis	Research/analysis, etc. to assess impact of response	Morgenstern Price method and Spencer
	Contents of measures (avoidance, reduction, transfer) or retention	Reduction
How to respond to risk	Measures	Conducting sortcrete for surface slope and abutting to 8 m depth for reinforcement
	Retention (no measures)	Intake safety, dam function
Special Notes	How to deal with	
	Reason	
Applicable standards/References	Expected impact	
	Availability and method of information sharing	
References	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.	
	1) Technical issue	
Other:	It is recommended that all cracks and rock cracks on the intake slopes and the platforms above should be covered with sealing grout. Adequate and permanent surface drainage should be arranged.	
	(Describe standards related to geological study, dam design, and countermeasure design.)	
Meeting Minutes:	Sidang Teknis Pembahasan Konstruksi Bendungan Bendu, 21 Juni 2021	
Meeting Materials:	Sidang Plano Pembahasan Konstruksi Bendungan Bendu, 29 Juli 2021	
Other:	Persiapan Impounding Waduk Bendu Laporan Akhir (PT. Indra Karya, 2004): Details Design Bendungan Bendu.	

ID:	6	Name:	Bendo	Dam Type:	Zonal with vertical core	Dam Height:	74.0 m
Concepts of Risk	1	When the risk was identified (date)	Mar-21				
	2	Project Phase in which risks were recognized	Construction				
	3	Location (Structure/area)	Spillway				
	4	Contents of risk	Landslide, rockfall, spillway function				
	5	Risk factors	Slope slope with many discontinuity				
	6	Events in which risks were recognized	During excavation of spillway, unstable slope was observed				
	7	Conditions/Situation for risk realization	earthquake, heavy rain				
	8	Impact if the risk realize	disturbance of spillway building, spillway malfunction				
	9	Where risk exists	Rock strength, Slope stability				
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above				
	11	Phase of Realization	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others				
	12	Impact if the risk realize	<input type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input checked="" type="checkbox"/> Consider mitigation measures as risk avoidance is difficult. <input type="checkbox"/> Risk retention under certain conditions				
	13	Corresponding to risks					
Overview of Causal Relationships	<div style="display: flex; justify-content: space-between;"> <div style="border: 1px solid black; padding: 5px;">Slope stability around spillway</div> <div style="border: 1px solid black; padding: 5px;">allowing the existence of cliffs with monitoring</div> <div style="border: 1px solid black; padding: 5px;">unstable slope due to heavy rain/ earthquake</div> <div style="border: 1px solid black; padding: 5px;">slope failure, rock fall, damage to spillway</div> </div>						
	<div style="display: flex; justify-content: space-between;"> <div style="border: 1px solid black; padding: 5px;">Slope of hill around spillway was observed steep with many discontinuities => Additional investigation and rock sampling</div> <div style="border: 1px solid black; padding: 5px;">excavating slope to gentle slope</div> <div style="border: 1px solid black; padding: 5px;">Risk avoidance</div> </div>						
Explanatory Diagram (Schematic Diagram/ Photos, etc)	<p>During construction monitoring of the slope, after shear stakes were installed, no change in the position or movement of the slope was observed. No movement of slope after blasting of the spillway, earthquake, and rainy season.</p>						
	<div style="display: flex; justify-content: space-around;">   </div> <p style="text-align: center;">Photo-1 Steep slope with many discontinuity at upstream of spillway</p> <div style="text-align: right;">  <p>Figure-1 Location of the slope (blue color)</p> </div>						


ID:	6	Name:	Bendo	Dam Type:	Zonal with vertical core	Dam Height:	74.0 m
History	Recognition or realization		Recognized				
	When the risk was recognized	Project Phase:	Construction				
Project Phase	Status of corresponding		Installation of shear stakes for movement monitoring				
	History of correspond to risks						
Plan	during design stage, only slope protection is recommended						
Design	detail condition of the slope had been conducted, shear stakes was installed at the top of slope to monitor the slope movement.						
Construction	 <p style="text-align: center;">Photo-1 wide discontinuity of the slope</p>						
	Impounding Operation/ maintenance						
	Investigation /analysis						
	Investigation/analysis to identify factors, etc. Research/analysis, etc. to assess impact Analysis, etc. to determine the need for and methods of response Contents of measures (avoidance, reduction, transfer or retention)						
	How to respond to risk	Measures	How to deal with	Installation of shear stakes for movement monitoring			
		Retention (no measures)	Reason	slope condition,			
		Availability and method of monitoring	Expected impact	shear stake monitoring			
		Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.					
	Special Notes	1) Technical issue 2) Potential of dam function disturbance If necessary, instruments can be installed, such as inclinometers and sliding stakes, to monitor movement in areas prone to landslides upstream of the spillway that have the potential for landslides.					
		Because of the dimension of landslide is not to wide, cutting the slope and weak zone to gentle slope is better.					
	Applicable standards	(Describe standards related to geological study, dam design, and countermeasure design.)					
	Remarks	Slope stability, landslide, slope cutting					
	Meeting Minutes:	Sidang Teknis/Pembahasan Konstruksi Bendungan Bendo, 21 Juni 2021					
Meeting Materials:	Sidang Plano/Pembahasan Konstruksi Bendungan Bendo, 29 Juli 2021						
Other:	Persiapan Impounding Waduk Bendo						
	Laporan Akhir (PT. Indra Karya,2004): Details Design Bendungan Bendo.						

ID:	6	Name:	Bendo	Dam Type:	Zonal with vertical core	Dam Height:	74.0 m
Concepts of Risk	1	When the risk was identified (date)	-				
	2	Project Phase in which risks were recognized	Impounding				
	3	Location (Structure/Area)	Dam body				
	4	Contents of risk	hydraulic fracture, piping				
	5	Risk factors	Drilling pressure, air/water pressure				
	6	Events in which risks were recognized	malfuction of inclinometer and will be installed the new one				
	7	Condition/Situation for risk realization	pressure during drilling				
	8	Impact if the risk realize	instable dam, dam break				
	9	Where risk exists	Dam material, method				
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above <input type="checkbox"/> Project Implementation <input type="checkbox"/> Operation <input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others				
	11	Phase of Realization	<input type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input checked="" type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.				
	13	Corresponding to risks	<input type="checkbox"/> Risk retention under certain conditions				
	Overview of Causal Relationships	Malfuction of inclinometer → Drilling on dam body will be conducted to monitor the dam → pressure during drilling may cause material condition changing of dam → Drilling near to previous inclinometer → Instable dam, dam break → Risk transfer or and reduction					
Changing drilling location to avoid deep drilling → Risk transfer or and reduction							
Explanatory Diagram (Schematic Diagram/ Photos, etc)	Photo-1 Inclinometer installation at construction						



Figure-1 Location of inclinometer installation during construction (2 locations)

ID:	6	Name:	Bendo	Dam Type:	Zonal with vertical core	Dam Height:	74.0 m
History	Recognition or not in the organizational	Unrecognized					
	When after risk was recognized	Project Phase: Impounding					
Project Phase	Status of corresponding	considering of changing the drilling location					
	History of correspond to risks	-					
Plan	-	-					
Design	Construction	Inclino meter had been installed in 2 location					
	-	The inspection after impounding inform that the inclinometer is not working properly due to the bottom of inclinometer is not installed deep enough in foundation.					
Impounding	-	-					
	-	-					
Operation/ maintenance	Investigation/analysis to identify factors, etc.	-					
	Research/analysis, etc. to assess impact Analysis, etc. to determine the need for and methods of response	-					
How to respond to risk	Contents of measures (avoidance, reduction, transfer) or retention	Transfer and reduction					
	Measures	Changing drilling location around the abutment to avoid deep drilling					
Retention (no measures)	Basics for decision	Dam safety					
	Reason	-					
Availability and method of monitoring	Expected impact	-					
	Availability and method of information sharing	-					
Special Notes	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.	-					
	Technical issue	-					
Applicable standards	To avoid deep drilling, consider installing inclinometer pipes near the left and right abutment or in areas with geological structures and/or weak zones where the embankment height is less than the maximum height of the dam.	-					
	Drilling in the dam body poses a very high risk to the dam's safety. Before drilling for installation of the inclinometer and OSP is carried out, a Drilling Program Plan (P3) should be prepared.	-					
Keywords	Drilling inclinometer, hydraulic fracture	-					
	Meeting Minutes:	Sidang Teknis Pembahasan Konstruksi Bendungan Bendo, 21 Juni 2021 Sidang Pleno Pembahasan Konstruksi Bendungan Bendo, 29 Juli 2021					
References	Meeting Materials:	Persiapan Impounding Waduk Bendo					
	Other:	Laporan Akhir (PT. Indra Karya,2004); Details Design Bendungan Bendo					



Figure-1 Long section of Bendo dam



1	When the risk was identified (date)	2021
2	Project phase in which risks were recognized	Impounding
3	Location (Structure/tree)	Dam body
4	Contents of risk	Mechanical parameter changes of dam material
5	Risk factors	Fine grained material at the top of coarse grained material
6	Events in which risks were recognized	During technical discussion
7	Condition/Situation for risk realization	Rain
8	Impact if the risk realize	Changing stability parameter of dam
9	Where risk exists	Dam material.
10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above <input type="checkbox"/> Project Implementation <input type="checkbox"/> Operation
11	Phase of Realization	<input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others
12	Impact if the risk realize	<input type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affects the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.
13	Corresponding to risks	<input checked="" type="checkbox"/> Risk retention under certain conditions



Recognition or not in the	Unrecognized
When the risk was recognized	Project Phase: Construction
Project Phase	Project Phase: Construction
History	Considering the stability analysis take zone 3a parameter same as 3b parameter
Status of corresponding	History of correspond to risks
Project Phase	History of correspond to risks
Plan	
Design	
Construction	
Impounding	
Operation/ maintenance	
Investigation/ analysis	
How to respond to risk	
Applicable standards	
Keywords	
References	
Other:	



Investigation/ analysis	Investigation/analysis to identify factors, etc.
How to respond to risk	Research/analysis, etc. to assess impact
Applicable standards	Analysis, etc. to determine the need for and methods of responses
Keywords	Contents of measures (avoidance, reduction, transfer) or retention
References	Retention
Other:	Retention
	Measures
	How to deal with
	Basis for decision
	Reason
	Expected impact
	Availability and method of monitoring
	Availability and method of information sharing
	Challenges: 1) Technical issues; 2) Constraints in project implementation requirements (Construction time, costs, etc.); 3) Constraints in dam operation; 4) Issues due to human and organizational factors; results of risk response - 5) Impact on processes, costs, etc.; 6) Reflection points (room for improvement of risk management methods), etc.
	Technical issue
	This value should be evaluated. If there is a change in the material during landfilling, a vibrating table test should be carried out following the material change so that the density test of the different materials is compared with the new vibrating table test results.
	A slope stability analysis should be carried out with zone 3A conditions having the same parameters as zone 3B to evaluate the dam's safety in these conditions.
	(Describe standards related to geological study, dam design, and countermeasure design.)
	Dam stability.
	Meeting Minutes: Sidang Teknis Pembahasan Konstruksi Bendungan Bendo, 21 Juni 2021
	Meeting Materials: Sidang Pleno Pembahasan Konstruksi Bendungan Bendo, 29 Juli 2021
	Other: Laporan Akhir (PT. Indra Karya,2014) Details Design Bendungan Bendo

ID:	7	Name:	Pasellong	Dam Type:	Earth-filled/zonal with central core	Dam Height:	42.0 m
Concepts of Risk	1	When the risk was identified (date)	June 2023				
	2	Project phase in which risks were recognized	Inspection after impounding				
	3	Location (Structure/Area)	Spillway wall, spillway floor				
	4	Contents of risk	Material quality				
	5	Risk factors	Scouring of spillway, Spillway failure				
	6	Events in which risks were recognized	Inspection for operation permit				
	7	Condition/Situation for risk realization	Water pressure, flooding discharge, water runoff				
	8	Impact if the risk realize	Unstable water flow, Scouring due to water flow, Damage to spillway				
	9	Where risk exists	Material strength, permeability				
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above				
	11	Phase of Realization	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input type="checkbox"/> Due to large-scale external force action <input type="checkbox"/> Due to long-term use <input type="checkbox"/> Others				
	12	Impact if the risk realize	<input type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.				
	13	Corresponding to risks	<input checked="" type="checkbox"/> Risk retention under certain conditions				
Overview of Causal Relationships							
	<p>At the connection of the left wall and spillway floor during visual inspection, seepage and scour were found at the elevation touching the apron (elv 46.00m) seepage was seen especially after rain, this scour eroded the surface of the left wall of the spillway, while the next finding was that the right bank or drainage channel downstream of the dam did not functioning properly, due to the blockage of the drainage channel, so that water flow through the drainage spilled over the right bank wall. While the next finding on the right wall of the chute channel looks settle dimensions and an average depth of 1.00 to 1.5 meters.</p>						
Explanatory Diagram (Schematic Diagram/ Photos, etc)							
	<p>Photo-1 Condition of spillway of Pasellong Dam</p>						

ID:	7	Name:	Pasellong	Dam Type:	Earth-filled/zonal with central core	Dam Height:	42.0 m
History	Recognition or realization		Unrecognized				
	When the risk was recognized		Project Phase: Alter impounding				
	Status of corresponding		Date: June 2023				
	History of correspond to risks						
Project Phase	Plan						
	Design						
Construction	<p>Figure-1 Cross section of spillway</p>						
	Impounding Operation/maintenance						
	Investigation/analysis						
	Investigation/analysis to identify factors, etc. Research/analysis, etc. to assess impact Analysis, etc. to determine the need for and methods of response Contents of measures (avoidance, reduction, transfer) or retention						
	How to respond to risk	Measures	How to deal with	Reduction			
		Retention (no measures)	Basis for decision Reason	Grouting Safety issues			
		Availability and method of monitoring	Expected impact				
		Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.					
	Special Notes	1) Technical issues, 2) Spillway function Improvements need to be carried out immediately because there have been traces of scouring that occur Location where scouring occur, material replacement should be carried out to prevent scouring area become wider					
		Applicable standards Remarks: (Describe standards related to geological study, dam design, and countermeasure design.) Meeting Minutes: Meeting Materials: Other:					
References: Diskusi Sertifikasi Izin Operasi, 4 Juli 2023 Sidang teknis Izin operasi 17 Oktober 2023 Dasar: Design On Pasellong Dam, Nippon Koei 2000							



ID: 7	Name: Paseloreng	Dam Type: Earth-filled zonal with central core	Dam Height: 42.0 m
1	When the risk was identified (date)	June 2023	
2	Project Phase in which risks were recognized	After impounding	
3	Location (Structure/Area)	diversion tunnel	
4	Contents of risk	Water flow, Cement dissolution	
5	Risk factors	tunnel collapse	
6	Events in which risks were recognized	during inspection leakage almost observed along the tunnel	
7	Condition/Situation for risk realization	Water pressure, Material dissolution	
8	Impact if the risk realize	Unstable wall tunnel, Tunnel collapse	
9	Where risk exists	Material strength	
10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above <input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others <input type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.	
11	Phase of Realization		
12	Impact if the risk realize		
13	Corresponding to risks		
Overview of Causal Relationships	<div style="display: flex; justify-content: space-around; align-items: center;"> <div style="border: 1px solid black; padding: 5px; text-align: center;">observed leakage water of tunnel</div> <div style="border: 1px solid black; padding: 5px; text-align: center;">seepage at lining concrete of tunnel</div> <div style="border: 1px solid black; padding: 5px; text-align: center;">water pressure</div> <div style="border: 1px solid black; padding: 5px; text-align: center;">Water flow, Cement dissolution</div> <div style="border: 1px solid black; padding: 5px; text-align: center;">diversion collapse operation disruption</div> </div> <p style="text-align: center; color: red; margin-top: 10px;">↓ additional drainage, grouting ↑ Risk reduction</p>		
Explanatory Diagram (Schematic Diagram/ Photos, etc)			



Photo-1 Water leakage at tunnel of Paseloreng Dam

ID: 7	Name: Paseloreng	Dam Type: Earth-filled zonal with central core	Dam Height: 42.0 m
History	Recognition or not in the past	Recognized	
	Project Phase	After impounding	Date: June 2023
	Status of corresponding	no information	
Project Phase	History of correspond to risks		
Plan			
Design			
Construction	most of the leakage was observed at the connection between tunnel and grouting hole plugging		
Impounding	<p style="text-align: center;">Figure-1 Location of largest water leakage in tunnel of Paseloreng Dam</p>		
Operation/ maintenance	Investigation/analysis to identify factors, etc.		
Investigation/analysis	Research/analysis, etc. to assess impact		
	Analysis, etc. to determine the need for and methods of response		
	Contents of measures (avoidance, reduction, transfer or retention)	Reduction	
How to respond to risk	Measures	How to deal with	no information
	Retention (no measures)	Basis for decision	water pressure
	Availability and method of monitoring	Reason	
		Expected impact	
Special Notes	Availability and method of information sharing		
	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methodology, etc.)		
	1) Technical issue		
	2) Disturbance of dam operation		
	Leaking conditions if left unchecked will become a problem in the long term, eroding cement dissolution will occur and reduce its quality. In low reservoir water conditions, grouting can be considered to avoid large pressures. However, further studies should also be conducted.		
Applicable standards			
Keywords	Tunnel Water leakage, Material dissolution		
Meeting Minutes	(Describe standards related to geological study, dam design, and countermeasure design.)		
References			
	Diskusi Sertifikasi Izin Operasi, 4 Juli 2023		
	Sidang teknis izin operasi, 17 Oktober 2023		
Other:	Basic Design On Paseloreng Dam, Nippon Koei 2000		

ID: 8	Name: Keureuto	Dam Type: Zonal random rock with central core	Dam Height: 74.0 m
Concerns of Risk	1	When the risk was identified (date)	June 2023
	2	Project Phase in which risks were recognized	Construction
	3	Location (Structure/area)	Spillway floor/foundation
	4	Contents of risk	Uplift of spillway, Foundation piping
	5	Risk factors	Ground water/ Water pressure
	6	Events in which risks were recognized	after spillway was constructed several water leakage observed
	7	Conditions/Situation for risk realization	Impounding, Heavy rain
	8	Impact if the risk realize	Damage to spillway, spillway function
	9	Where risk exists	Rock strength, Permeability
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above
	11	Phase of Realization	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input type="checkbox"/> Due to large-scale external force action <input type="checkbox"/> Due to long-term use <input type="checkbox"/> Others
	12	Impact if the risk realize	<input type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.
	13	Corresponding to risks	<input type="checkbox"/> Risk retention under certain conditions
Perspectives on Risk Classification	<div style="display: flex; justify-content: space-around;"> <div style="border: 1px solid black; padding: 5px;">Inspection after dam impounding</div> <div style="border: 1px solid black; padding: 5px;">Several spot of water leakage at spillway</div> <div style="border: 1px solid black; padding: 5px;">Water pressures, uplift of spillway, decrease quality of material</div> <div style="border: 1px solid black; padding: 5px;">spillway failure, spillway modification</div> </div>		
	<div style="display: flex; justify-content: space-around;"> <div style="border: 1px solid black; padding: 5px;"> <input checked="" type="checkbox"/> Grouting on spillway, drainage installation </div> <div style="border: 1px solid black; padding: 5px;"> <input checked="" type="checkbox"/> Risk reduction </div> </div>		
Overview of Causal Relationships	<p>Seepage occurred at the Spillway launcher and the spillway's side walls, based on geophysical survey, there is water accumulation under it.</p>		
Explanatory Diagram (Schematic Diagram/ Photos, etc)	<p>Photo-1 water leakage on chute of spillway (dash red mark) and spring water location (dash black mark)</p>		

ID: 8	Name: Keureuto	Dam Type: Zonal random rock with central core	Dam Height: 74.0 m
History	When the risk was recognized	Recognized	
	Project Phase: Construction		Date: June 2023
	Status of corresponding geophysics survey surrounding spillway location		
Project Phase	History of correspond to risks		
Plan			
Design			
Construction			
Impounding/Operational/maintenance			
Investigation/analysis	Investigation/analysis to identify factors, etc. Research/analysis, etc. to assess impact Analysis, etc. to determine the need for and methods of response Contents of measures (avoidance, reduction, transfer) or retention		
How to respond to risk	Measures	How to deal with	
	Retention (no measures)	Basis for decision Reason	
	Availability and method of monitoring	Expected impact	
Special Notes	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operations, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc. 1) Technical issue Considerate of groundwater relations in case of impounding. There is no drainage system behind the side walls, additional discharge pipes is needed.		
Applicable standards			
References	(Describe standards related to geological study, dam design, and countermeasure design.)		
Meeting Minutes:	diskusi teknis pembahasan hidromekamil bendungan keureuto, 27 Juni 2023		
Meeting Materials:	Proyek Penyelesaian Pembangunan Bendungan Keureuto, 20 Juni 2023		
Other:			

ID:	9	Name:	Tiga Dibaaji	Dam Type:	Rock fill with central core	Dam Height:	122.0 m
Concepts of Risk	1	When the risk was identified (date)	21 Dec 2022				
	2	Project Phase in which risks were recognized	Construction				
	3	Location (Structure/Area)	Tunnel / top of tunnel				
	4	Contents of risk	Cavity of tunnel, sinkhole				
	5	Risk factors	sinkhole appearance causing unstable dam material collapse from top of tunnel during tunneling				
	6	Events in which risks were recognized	earthquake, vibration				
	7	Condition/Situation for risk realization	tunnel collapse, dam foundation disturbance				
	8	Impact if the risk realize	geology, rock mass, permeability, foundation				
	9	Where risk exists	<input type="checkbox"/> Mainly caused by external forces				
	10	Character	<input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above				
	Perspectives on Risk Classification	11	Phase of Realization	<input checked="" type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation			
		12	Impact if the risk realize	<input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others			
		13	Corresponding to risks	<input checked="" type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affects the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult. <input checked="" type="checkbox"/> Risk retention under certain conditions			
Overview of Causal Relationships	Tunnel collapse	tunnel excavation and loose material collapse from above => Sinkhole distributions => replaced with concrete + additional steel rib	machine vibration during construction => tunnel collapse, sinkhole for dam foundation	unstable dam foundation, dam break			
				Revetment replacing sinkhole with concrete, additional steel rib for tunnel			
Explanatory Diagram (Schematic Diagram/ Photos, etc)	 <p>Figure-1 Sinkhole location during tunneling</p>						
	 <p>looses material collapse</p> <p>Figure-2 loose material collapse from tunnel</p>						

ID:	9	Name:	Tiga Dibaaji	Dam Type:	Rock fill with central core	Dam Height:	122.0 m
History	Recognition or realization	Unrecognized					
	When the risk was recognized	Project Phase: Construction					
	Status of corresponding	Replaced by concrete					
Project Phase	History of correspond to risks						
	Plan						
Design	Using steelrib for Tunnel reinforcement						
	Using canopy steelrib fort tunnel reinforcement and replaced sinkhole with concrete						
Construction	 <p>Illustration Steel Rib Canopy</p>  <p>Figure-1 Additional canopy steelrib for tunnel reinforcement</p> <p>Figure-2 concrete replacement to sinkhole</p>						
	Impounding Operations/ maintenance						
Investigation /analysis	Investigation/analysis to identify factors, etc.						
	Research/analysis, etc. to assess impact						
Contents of measures (avoidance, reduction, transfer) or retention	Analysis, etc. to determine the need for and methods of response						
	Retention						
How to respond to risk	Measures	Retention					
	How to deal with	Installation canopy steelrib for tunnel at sinkhole location and concrete replacement for sinkhole					
Retention (no measures)	Basis for decision	geological condition					
	Reason						
Availability and method of monitoring	Expected impact						
Special Notes	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.						
	1) technical issue 2) construction time and cost						
It should be considered that for the downstream tunnel segment of the Dam side that passes through the loose sand layer, a drainage pipe equipped with a filter/geotextile should be installed so that the saturation level of the sand layer below the downstream slope can be reduced to minimize the liquefaction potential.							
Applicable standards	(Describe standards related to geological study, dam design, and countermeasure design.)						
Remarks	Tunnel, sinkhole, steelrib						
Meeting Minutes:	Susan Pined Alhi Bebas (HMF, Bottom Outlet), 16 Mei 2023						
Meeting Materials:	Kronologi Cave In dan Sinkhole, Penanganan Pasir Lepas pada Fondasi, Maret 2023						
Other:							






ID:	9	Name:	Tiga Dibaaji	Dam Type:	Rock fill with central core	Dam Height:	122.0 m
Concepts of Risk	1	When the risk was identified (date)	April 2021				
	2	Project phase in which risks were recognized	Design				
	3	Location (Structure/tree)	Dam / dam foundation				
	4	Contents of risk	Instability of foundation, liquefaction, reservoir leakage, loose sand as foundation				
	5	Risk factors	earthquake, impounding				
	6	Events in which risks were recognized	liquefaction, instable foundation, dam break,				
	7	Conditions/Situation for risk realization	Foundation, geology, permeability				
	8	Impact if the risk realize	<input type="checkbox"/> Mainly caused by external forces				
	9	Where risk exists	<input checked="" type="checkbox"/> Mainly due to technical factors				
	10	Character	<input type="checkbox"/> Factors other than the above				
	11	Phase of Realization	<input checked="" type="checkbox"/> Project Implementation				
	12	Impact if the risk realize	<input checked="" type="checkbox"/> Operation <input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input checked="" type="checkbox"/> Others <input checked="" type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input checked="" type="checkbox"/> Affects the schedule and costs of the projects <input checked="" type="checkbox"/> Basically risk avoidance <input checked="" type="checkbox"/> Consider mitigation measures as risk avoidance is difficult. <input checked="" type="checkbox"/> Risk retention under certain conditions				
	13	Corresponding to risks	<input checked="" type="checkbox"/> Risk retention under certain conditions				
Perspectives on Risk Classification	Cyclog of dam foundation		loose sand was observed during investigation at design stage => foundation treatment by dynamic compaction				
	Earthquake causing unstable foundation		liquefaction of foundation, foundation leakage				
Overview of Causal Relationships	Cyclog of dam foundation		unstable foundation, uplift foundation, dam leakage				
	Earthquake causing unstable foundation		liquefaction of foundation, foundation leakage				
Explanatory Diagram (Schematic Diagram/ Photos, etc)							

Figure-1 Distribution of loose sand at dam foundation (blue and light blue color)

Figure-2 Foundation treatment of loose sand by cyclop concrete replacing

ID:	9	Name:	Tiga Dibaaji	Dam Type:	Rock fill with central core	Dam Height:	122.0 m
History	Recognition or realization		Recognized				
	When the risk was recognized		Design				
	Status of corresponding		Considering deep mixing method or grouting				
Project Phase	History of correspond to risks						
	Using dynamic compaction for thick layer of loose sand during construction grouting trial for loose sand was conducted						
Plan							
Design							
Construction							
Impounding/ Operation/ maintenance	Investigation/analysis to identify factors, etc.						
	Research/analysis, etc. to assess impact						
Investigation /analysis	Analysis, etc. to determine the need for and methods of response						
	Contents of measures (avoidance, reduction, transfer) or retention						
How to respond to risk	Measures	How to deal with	reduction by conducting grouting for loose sand				
	Retention (no measures)	Basis for decision	grouting for loose sand				
	Availability and method of monitoring	Reason	time and cost				
Special Notes	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.						
	Technical issues						
Applicable standards	To anticipate this condition, the contact area between the loose sand surface and the downstream rockfill base should be coated with a relatively thick transition zone.						
References	Cyclops concrete may be porous, so it has the potential to be a source of seepage. To anticipate this, cyclops concrete should be grouted until it meets the required Luqoon value.						
Meeting Minutes:	(Describe standards related to geological study, dam design, and countermeasure design.)						
	Grouting, liquefaction, loose sand						
Meeting Materials:	Sutan Pined Alii Rebus (HMF, Bottom Outlet), 16 Mei 2023						
	Kronologi Caving dan Sinkhole, Penanganan Pasir Lepas pada Fondasi, Maret 2023						
Other:							

ID: 9		Name: Tiga Dibiagi		Dam Type: Rock fill with central core		Dam Height: 122.0 m	
Concepts of Risk	1	When the risk was identified (date)	April 2022	Unrecognized			
	2	Project phase in which risks were recognized	Construction	Project Phases: Construction			
	3	Location (Structure/Area)	Dam body, dam material	Date: April 2022			
	4	Contents of risk	Decreasing material quality	Status of corresponding			
	5	Risk factors	Rock properties	History of correspond to risks			
	6	Events in which risks were recognized	The quarry location at design stage has 30 m overburden that cause cost increasing				
	7	Conditions/Situation for risk realization	Dam construction				
	8	Impact if the risk realize	Dam stability, dam breach, increasing material volume				
	9	Where risk exists	Geology, dam material				
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above				
	11	Phase of Realization	<input checked="" type="checkbox"/> Project Implementation <input type="checkbox"/> Operation <input type="checkbox"/> Due to large-scale external force action <input type="checkbox"/> Due to long-term use <input type="checkbox"/> Others				
	12	Impact if the risk realize	<input type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affects the schedule and costs of the projects <input checked="" type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult. <input type="checkbox"/> Risk retention under certain conditions				
	13	Corresponding to risks					




Table-1 Rockfill material changing from initial design

No.	Perubahan	Detail Awal	Perubahan
1	Lokasi Quarry Area	Perubahan lokasi Quarry dari Desa Peranti dengan jarak sekitar 11-15 km.	Perubahan lokasi Quarry dari Desa Peranti dengan jarak sekitar 11-15 km.
2	Finis Material	Material tumpukan sebagai timbunan batu kerapuh Breksi	Material tumpukan sebagai bahan timbunan batu kerapuh Breksi
3	Prinsip Volume	Material tumpukan memiliki estimasi volume 41,5 juta m ³	Material tumpukan sebagai bahan timbunan batu kerapuh Breksi
4	Volume Daur-ulang	Overburden dan padu Quarry Payaman memiliki kerakalihan hingga 30 m dengan estimasi volume 8,5 juta m ³	Overburden dan padu Quarry Payaman memiliki kerakalihan hingga 30 m dengan estimasi volume 8,5 juta m ³
5	Jalan Akses	Harus membuat jalan dan Dam Prinsip material Dam	Harus membuat jalan dan Dam Prinsip material Dam
6	Parameter Stabilitas	Some daya tarik material Hutan Leuhung (Paku)	Some daya tarik material Hutan Leuhung (Paku)




ID: 9		Name: Tiga Dibiagi		Dam Type: Rock fill with central core		Dam Height: 122.0 m	
Explanatory Diagram (Schematic Diagram/ Photos, etc)	History	When the risk was recognized	Unrecognized	Project Phases: Construction			
	Project Phase	Status of corresponding	History of correspond to risks				
	Plan						
	Design						
	Construction						
	Impounding Operation/ maintenance						
	Investigation/analysis						
	How to respond to risk						
	Special Notes						
	Applicable standards						
	Keywords						
	References						

ID:	10	Name:	Laisiainsine	Dam Type:	Zonal Rock-filled Dam with Centre Core	Dam Height:	77.0 m
Contents of Risk	1	When the risk was identified (date)	2022				
	2	Project phase in which risks were recognized	Construction				
	3	Location (Structure/tree)	Dam foundation				
	4	Contents of risk	Piping of foundation				
	5	Risk factors	uplift of dam, material leaching				
	6	Events in which risks were recognized	a weak zone was observed during excavation of foundation u/s to d/s foundation				
	7	Conditions/Situation for risk realization	high reservoir water level, impounding, earthquake				
	8	Impact if the risk realize	dam break				
	9	Where risk exists	geology, permeability				
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above				
	11	Phase of Realization	<input checked="" type="checkbox"/> Project Implementation <input type="checkbox"/> Operation				
	12	Impact if the risk realize	<input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others <input type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.				
	13	Corresponding to risks	<input checked="" type="checkbox"/> Risk retention under certain conditions				
Overview of Causal Relationships	<div style="border: 1px solid black; padding: 5px; width: fit-content;"> weak observed during foundation excavation </div>	<div style="border: 1px solid black; padding: 5px; width: fit-content;"> during excavation for construction a weak zone was observed => detailed geological mapping </div>	<div style="border: 1px solid black; padding: 5px; width: fit-content;"> impounding, earthquake </div>	<div style="border: 1px solid black; padding: 5px; width: fit-content;"> piping of dam foundation, uplift of dam </div>	<div style="border: 1px solid black; padding: 5px; width: fit-content;"> dam break, flooding </div>	<div style="border: 1px solid black; padding: 5px; width: fit-content;"> Risk reduction </div>	<div style="border: 1px solid black; padding: 5px; width: fit-content;"> replacing grouting with second pile </div>
<p>Explanatory Diagram (Schematic Diagram/ Photos, etc)</p>							


Figure-1 Engineering geology map of core foundation

ID:	10	Name:	Laisiainsine	Dam Type:	Zonal Rock-filled Dam with Centre Core	Dam Height:	77.0 m
History	Recognition on the time		Unrecognized				
	When the risk was recognized		Project Phase: Construction				
	Status of corresponding		Considering additional / extending grouting				
	History of correspond to risks						
Project Phase	Plan	grouting recommendation for dam foundation improvement					
	Design	During construction the grouting depth considered is insufficient to cover the cracks in the weak zone completely					
Construction							
Impounding/Operation/maintenance	Investigation/analysis to identify factors, etc.						
	Research/analysis, etc. to assess impact						
Investigation/analysis	Analysis, etc. to determine the need for and methods of repair measures (avoidance, reduction, transfer or retention)						
	Measures		How to respond to risk		Retention (no measures)		
Special Notes	Availability and method of monitoring		Availability and method of information sharing		Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.		
	1) Technical issue						
<p>weak zones or faults that are not too wide, can be improved by excavating weak zone material/squeeze material to a depth of 1.5 the width of the weak/lean zone, then backfilling with wedge-shaped concrete and combining it with grouting. To monitor the pore water pressure in the weak zone, at least 2 (two) piezometers should also be installed</p>							
Applicable standards							
Keywords							
Meeting Minutes:							
Meeting Materials:							
Other:							

ID:	10	Name:	Lausimeme	Dam Type:	Zonal Rock-filled Dam with Centre Core	Dam Height:	77.0 m
Contents of Risk	1	When the risk was identified (date)	-	Construction	-	-	-
	2	Project phase in which risks were recognized	-	Dam body	-	-	-
	3	Location (Structure/Area)	-	Material displacement	-	-	-
	4	Contents of risk	-	Material gradation	-	-	-
	5	Risk factors	-	Defence sieve when material is confirmed by laboratory testing	-	-	-
	6	Events in which risks were recognized	-	Reservoir water fluctuation	-	-	-
	7	Condition/Situation for risk realization	-	Dam deformation, dam slope sliding	-	-	-
	8	Impact if the risk realize	-	Dam material, design	-	-	-
	9	Where risk exists	-	<input type="checkbox"/> Mainly caused by external forces	-	-	-
	10	Character	-	<input checked="" type="checkbox"/> Mainly due to technical factors	-	-	-
	11	Phase of Realization	-	<input type="checkbox"/> Factors other than the above	-	-	-
	12	Impact if the risk realize	-	<input checked="" type="checkbox"/> Project Implementation	-	-	-
	13	Corresponding to risks	-	<input checked="" type="checkbox"/> Operation	-	-	-



ID:	10	Name:	Lausimeme	Dam Type:	Zonal Rock-filled Dam with Centre Core	Dam Height:	77.0 m
History	When the risk was recognized	Unrecognized	-	-	-	-	-
	Project Phase: Construction	-	-	-	-	-	-
Project Phase	Status of corresponding	Recognized by adjusting filter to core material condition	-	-	-	-	-
	History of correspond to risks	-	-	-	-	-	-
Plan	Design	The core material requirement at design stage is 7%-50% for fine material content	-	-	-	-	-
	Design	The core material properties during construction is confirmed that the fine material content is more than 70%	-	-	-	-	-
Construction	Impounding/ maintenance	-	-	-	-	-	-
	Investigation/ analysis	Investigation analysis to identify factors, etc.	-	-	-	-	-
How to respond to risk	Measures	How to deal with	-	-	-	-	-
	Reason (for measures)	Reason	-	-	-	-	-
Special Notes	Design criteria	Design criteria	-	-	-	-	-
	Applicable standards/ reviews	(Describe the standards related to geological study, dam design, and countermeasure design.)	-	-	-	-	-
References	Meeting Minutes:	Diskusi Teknis Pembahasan Pelaksanaan Konstruksi, 24 Maret 2023	-	-	-	-	-
	Meeting Materials:	Pembangunan Bendungan Lausimeme, 16 Mei 2023	-	-	-	-	-
Other:	Detail Desain Perencanaan, November 2015, PT. Wahana Adya KSO, PT. Teknika CIP'a Konsultan	-	-	-	-	-	-
	Detail Desain Geoteknik, November 2015, PT. Wahana Adya KSO, PT. Teknika CIP'a Konsultan	-	-	-	-	-	-



ID:	10	Name:	Lausimeme	Dam Type:	Zonal Rock-filled Dam with Centre Core	Dam Height:	77.0 m
Investigation/ analysis	Research analysis, etc. to assess impact	-	-	-	-	-	-
	Analysis, etc. to determine the need for and methods of response	-	-	-	-	-	-
How to respond to risk	Contents of measures (avoidance, reduction, transfer) or retention	Avoidance	-	-	-	-	-
	Measures	Changing filter criteria for construction	-	-	-	-	-
Special Notes	Design criteria	Design criteria	-	-	-	-	-
	Applicable standards/ reviews	(Describe the standards related to geological study, dam design, and countermeasure design.)	-	-	-	-	-
References	Meeting Minutes:	Diskusi Teknis Pembahasan Pelaksanaan Konstruksi, 24 Maret 2023	-	-	-	-	-
	Meeting Materials:	Pembangunan Bendungan Lausimeme, 16 Mei 2023	-	-	-	-	-
Other:	Detail Desain Perencanaan, November 2015, PT. Wahana Adya KSO, PT. Teknika CIP'a Konsultan	-	-	-	-	-	-
	Detail Desain Geoteknik, November 2015, PT. Wahana Adya KSO, PT. Teknika CIP'a Konsultan	-	-	-	-	-	-

ID: 11		Name: Margatiga	Dam Type: gravity concrete-rock-fill dam, central core	Dam Height: 20.0 m
Concepts of Risk	1	When the risk was identified (date)	December 2022	
	2	Project phase in which risks were recognized	Construction	
	3	Location (Structure/Area)	Reservoir	
	4	Contents of risk	Local seismic hazard (Reservoir-Induced Seismicity)	
	5	Risk factors	Fault	
	6	Events in which risks were recognized	There is a fault on regional geology map	
	7	Condition/Situation for risk realization	Impounding water pressure	
	8	Impact if the risk realize	Earthquake in small scale, foundation damage	
	9	Where risk exists	Geology, Fault	
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above	
	11	Phase of Realization	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others	
	12	Impact if the risk realize	<input checked="" type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input checked="" type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.	
	13	Corresponding to risks	<input type="checkbox"/> Risk retention under certain conditions	
Overview of Causal Relationships	Fault based on regional geology map → There is a fault on regional geology map that recognized during technical discussion → Impounding and water pressure of reservoir causing reservoir induced earthquake in small scale (local earthquake) → Foundation damage			
	Fault based on regional geology map → Instrument installation for fault monitoring → Early warning system, mitigation			
Explanatory Diagram (Schematic Diagram/ Photos, etc)				
	Figure-1 Estimated Fault base on regional geology map of surround Margatiga Dam (S. Andi Mengga, et al., 1993)			

ID: 11		Name: Margatiga	Dam Type: gravity concrete-rock-fill dam, central core	Dam Height: 20.0 m
History	When the risk was recognized	Unrecognized	Project Phase: Impounding	Date: December 2022
	Status of corresponding	-	History of correspond to risks	
Plan	Based on investigation during design and construction of Margatiga Dam, no fault was observed around the site, because of the dam foundation nearly seal.			
Design	<p>Figure-1 Geological map of Margatiga Dam</p>			
Construction	Investigation/analysis to identify factors, etc. - Research/analysis, etc. to assess impact - Analysis, etc. to determine the need for and methods of response - Contents of measures (avoidance, reduction, retention) - Measures - How to respond to risk - Retention (no measures) - Availability and method of monitoring - Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.			
Operational/maintenance	Investigation/analysis - Research/analysis, etc. to assess impact - Analysis, etc. to determine the need for and methods of response - Contents of measures (avoidance, reduction, retention) - Measures - How to respond to risk - Retention (no measures) - Availability and method of monitoring - Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.			
Special Notes	Technical issue One should be aware of the occurrence of reservoir-induced seismicity due to the presence of these faults during and after the initial impounding of the reservoir and during the operation and maintenance period by checking the treatments that have seismic potential.			
Applicable standards	(Describe standards related to geological study, dam design, and countermeasure design.)			
References	Risaiah Sidiq Pheno Pelaksanaan Konstruksi dan Keselamatan Pengisian Awal, 5 Desember 2022 Laporan Sidang Pleno, 28 November 22 Laporan Utama Review Desain (PT. Virama Karya, 2015)			

ID: 11	Name: Margatiga	Dam Type: gravity concrete-rock-fill dam, central core	Dam Height: 20.0 m		
Concepts of Risk	1	When the risk was identified (date)	Construction		
	2	Project Phase in which risks were recognized	Dam body		
	3	Location (Structure/area)	Dam deformation, instability of dam		
	4	Contents of risk	Material quality / quality control		
	5	Risk factors	Some material doesn't meet requirement		
	6	Events in which risks were recognized	Impulsing, material loading		
	7	Conditions/Situation for risk realization	Cracking on core material, dam break		
	8	Impact if the risk realize	Core material, quality control		
	9	Where risk exists	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above		
	10	Character	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others		
Perspectives on Risk Classification	11	Phase of Realization	<input checked="" type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.		
	12	Impact if the risk realize	<input checked="" type="checkbox"/> Risk retention under certain conditions		
	13	Corresponding to risks			
Overview of Causal Relationships	Quality of core material	Some water content of material does not meet the requirement of water content percentages	High settlement on core material	Water out through core material, dam break	Risk retention
	Monitoring instrumentation on material				




Figure-1 field water content of core material at Margatiga Dam

Explanatory Diagram (Schematic Diagram/ Photos, etc)

ID: 11	Name: Margatiga	Dam Type: gravity concrete-rock-fill dam, central core	Dam Height: 20.0 m
History	Recognition of nor time	Unrecognized	
	When the risk was recognized	Project Phase: Construction	Date: -
Project Phase	Status of corresponding	Monitoring the instrumentation at core material	
		History of correspond to risks	
Plan			
Design			
Construction			Some field water content for core material at margatiga dam does not meet requirement that exceed of specification. The guideline for core material should be not less -1% of OMC and not higher +3% of OMC (optimum moisture content)
Impounding Operation/ maintenance			
Investigation /analysis	Investigation/analysis to identify factors, etc.	-	
	Research/analysis, etc. to assess impact	-	
How to respond to risk	Analysis, etc. to determine the need for and methods of response	-	
	Retention	-	
Measures	Retention	Retention	
	How to deal with	-	
Retention (no measures)	Basis for decision	-	
	Reason	Cost	
Availability and method of monitoring	Expected impact	High settlement	
		Piezometer and inclinometer	
Special Notes	Availability and method of information sharing	-	
	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points from for improvement of risk management methods, etc.		
Technical issue			
The number and percentage of test results that do not meet the requirements should be mapped (station and elevation), even though improvements have been made so that they meet the requirements.			
Applicable standards			
Keywords	(Describe standards related to geological study, dam design, and countermeasure design.)		
Meeting Minutes:			Risalah Sidang Pleno Pelaksanaan Konstruksi dan Kestapan Pengisian Awal, 5 Desember 2022
Meeting Materials:			Paparan Sidang Pleno, 28 November 22
Other:			Laporan Utama Review Desain (PT. Virama Karya, 2015)

ID:	12	Name:	Gongseng	Dam Type:	Rock-filled dam with central core	Dam Height:	34.0 m
Concepts of Risk	1	When the risk was identified (date)	Jan 2019				
	2	Project Phase in which risks were recognized	Construction				
	3	Location (Structure/Area)	Dam foundation				
	4	Contents of risk	Piping of foundation, uplift of dam body				
	5	Risk factors	Ineffective grouting indication Piezometer monitoring of foundation				
	6	Events in which risks were recognized	High water level of reservoir				
	7	Condition/Situation for risk realization	Dam break causing flooding				
	8	Impact if the risk realize	Geology, Permeability, Design/ Foundation treatment				
	9	Where risk exists	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above				
	10	Character	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others				
	11	Phase of Realization	<input type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input checked="" type="checkbox"/> Consider mitigation measures as risk avoidance is difficult. <input type="checkbox"/> Risk retention under certain conditions				
	12	Impact if the risk realize					
	13	Corresponding to risks					
Perspectives on Risk Classification	Grouting of dam foundation		Piezometer monitoring at upstream and downstream of grouting almost has same pressure value	long term of high reservoir water level of	uplift of dam body, piping of foundation	dam break causing flooding	
							mitigation monitoring of instrument and dam deformation => socialization of warning system
Overview of Causal Relationships	During Construction, monitoring of VW piezometer at AD 04+7.5 that installed in dam foundation show the pressure is almost same.						
Explanatory Diagram (Schematic Diagram/ Photos, etc)	Figure-1 Piezometer reading at dam foundation during construction						
	Figure-2 Lugeon profile of main dam at AD-04 based on pilot hole (before grouting)						

ID:	12	Name:	Gongseng	Dam Type:	Rock-filled dam with central core	Dam Height:	34.0 m
History	Recognition or non-recognition		Recognized				
	If non-risk was recognized						
Project Phase	Project Phase:		Construction				
	Status of corresponding						
Plan	History of correspond to risks						
	using grouting to improve permeability of dam foundation						
Design	ineffective grouting was observed during dam embankment implementation from piezometer monitoring at foundation						
Construction	Figure-2 Geological profile of dam axis						
	Figure-2 Lugeon profile of main dam at AD-04 based on check hole (after grouting)						
Impending Operation/ maintenance	Investigation/analysis to identify factors, etc.						
	Research/analysis, etc. to assess impact						
Investigation /analysis	Analysis, etc. to determine the need for and methods of response						
	Contents of measures (avoidance, reduction, transfer) or retention						
How to respond to risk	Measures		How to deal with				
	Retention (no measures)		Basis for decision Reason				
Special Notes	Availability and method of information sharing		Expected impact				
	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.						
Applicable standards	1) technical issues						
	2) dam safety						
References	a. The contour depiction should be rechecked						
	b. Check the effectiveness of the grouting that has been done						
		c. Check for possible seepage or springs from the foundation downstream of the dam.					
		(Describe standards related to geological study, dam design, and countermeasure design.)					
Meeting Minutes:		Pelaksanaan Konstruksi Pembangunan Gongseng, 14 September 2021					
Meeting Materials:		Pembahasan Konstruksi untuk pengisian awal waduk					
Other:		Laporan Akhbar (2013), Sertifikasi Desain Bandungan Gongseng.					

ID:	13	Name:	Pidaksio	Dam Type:	Random emb-fill with central core	Dam Height:	44.0 m
Contents of Risk	1	When the risk was identified (date)	2021				
	2	Project Phase in which risks were recognized	Construction				
	3	Location (Structure/Area)	Instrumentation, V-Notch				
	4	Contents of risk	Dam seepage				
	5	Risk factors	Water / groundwater				
	6	Events in which risks were recognized	Monitoring V-notch before impounding water come through V-notch				
	7	Condition/Situation for risk realization	Groundwater level condition, seepage during construction				
	8	Impact if the risk realize	Seepage monitoring accuracy				
	9	Where risk exists	Dam body, permeability				
	10	Character	<input checked="" type="checkbox"/> Mainly caused by external forces <input type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above <input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others				
	11	Phase of Realization	<input type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.				
	12	Impact if the risk realize	<input checked="" type="checkbox"/> Risk retention under certain conditions				
	Perspectives on Risk Classification	13	Corresponding to risks	<input checked="" type="checkbox"/> Risk retention under certain conditions			
13		Corresponding to risks	<input checked="" type="checkbox"/> Risk retention under certain conditions				
Overview of Causal Relationships	13	Overview of Causal Relationships	<div style="border: 1px solid black; padding: 5px;"> <p>V-Notch monitoring during construction</p> <p>↑</p> <p>water at V-notch is influenced by rain -> In April to June 2021 there no rain and water is still come out through V-Notch</p> <p>↑</p> <p>Increasing groundwater level, during impounding will be larger</p> <p>↑</p> <p>Difficulty of seepage monitoring</p> <p>↑</p> <p>Seepage monitoring accuracy</p> <p>↑</p> <p>Risk retention</p> </div>				
	13	Overview of Causal Relationships	<div style="border: 1px solid black; padding: 5px;"> <p>V-Notch monitoring during construction</p> <p>↑</p> <p>water at V-notch is influenced by rain -> In April to June 2021 there no rain and water is still come out through V-Notch</p> <p>↑</p> <p>Increasing groundwater level, during impounding will be larger</p> <p>↑</p> <p>Difficulty of seepage monitoring</p> <p>↑</p> <p>Seepage monitoring accuracy</p> <p>↑</p> <p>Risk retention</p> </div>				
Explanatory Diagram (Schematic Diagram/ Photos, etc)	13	Explanatory Diagram (Schematic Diagram/ Photos, etc)					
	13	Explanatory Diagram (Schematic Diagram/ Photos, etc)					

ID:	13	Name:	Pidaksio	Dam Type:	Random emb-fill with central core	Dam Height:	44.0 m
History	13	Recognition or non-recognition of the risk	Unrecognized				
	13	Project Phase	Construction				
	13	When the risk was recognized	2021				
	13	Status of corresponding	Monitoring				
Project Phase	13	Project Phase	Construction				
	13	History of correspond to risks					
Plan	13	Plan					
	13	Design					
Construction	13	Construction					
	13	Impounding Operation/ maintenance					
Investigation /analysis	13	Investigation/analysis to identify factors, etc.					
	13	Research/analysis, etc. to assess impact of response					
How to respond to risk	13	Contents of measures (avoidance, reduction, transfer) or retention					
	13	Measures	How to deal with				
Special Notes	13	Retention (no measures)	Reason				
	13	Availability and method of information sharing	Expected impact				
Applicable standards	13	Technical issue					
	13	Technical issue					
References	13	Origin of the seepage water should be explained, including whether it is also influenced by foundation seepage, or whether there are springs during construction that come out at the current v-notch. This condition needs to be correlated with the foundation piezometer readings, to determine the pore water pressure at the time of construction completion prior to inundation.					
	13	Applicable standards	(Describe standards related to geological study, dam design, and countermeasure design.)				
Other:	13	Meeting Minutes:	Draft- Pisalah Stang Plano, 4 Oktober 2021				
	13	Meeting Materials:	Sliding Plano Pelaksanaan Konstruksi dalam Rangka Etn Pengisian Awal, 4 Oktober 2021				
Other:	13	Other:	Laporan Abstr, 28 Maret 2011, PT. Matiana; Review FS dan DD Waduk Pidaksio				
	13	Other:					

ID: 13	Name: Pidekso	Dam Type: Random earth-fill with central core	Dam Height: 44.0 m	
Concepts of Risk	1	When the risk was identified (date)	-	
	2	Project phase in which risks were recognized	Construction	
	3	Location (Structure/area)	Dam foundation/ rock foundation of core	
	4	Contents of risk	Water leakage from foundation	
	5	Risk factors	Cracking along the core foundation	
	6	Events in which risks were recognized	During foundation excavation long crack was observed	
	7	Conditions/Situation for risk realization	Impounding, water pressure	
	8	Impact if the risk realize	core material leached, dam stability, dam breach,	
	9	Where risk exists	Geology, permeability, foundation treatment	
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above	
	Perspectives on Risk Classification	11	Phase of Realization	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others
		12	Impact if the risk realize	<input type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input checked="" type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.
	Overview of Causal Relationships	13	Corresponding to risks	<input type="checkbox"/> Risk retention under certain conditions
			<div style="display: flex; justify-content: space-between;"> <div style="border: 1px solid black; padding: 5px; width: 30%;"> long crack along the foundation </div> <div style="border: 1px solid black; padding: 5px; width: 30%;"> During foundation excavation long crack was observed but no information about long crack at design stage </div> <div style="border: 1px solid black; padding: 5px; width: 30%;"> water can flow through the crack during impounding </div> </div> <div style="display: flex; justify-content: space-between; margin-top: 10px;"> <div style="border: 1px solid black; padding: 5px; width: 30%;"> Water leakage from foundation </div> <div style="border: 1px solid black; padding: 5px; width: 30%;"> core material leached, dam stability, dam breach </div> </div> <div style="display: flex; justify-content: space-between; margin-top: 10px;"> <div style="border: 1px solid black; padding: 5px; width: 30%;"> Conducting special grouting for crack </div> <div style="border: 1px solid black; padding: 5px; width: 30%;"> Risk reduction </div> </div>	
Explanatory Diagram (Schematic Diagram/ Photos, etc)			<p>Photo-1 Crack condition during construction implementation</p>	

ID: 13	Name: Pidekso	Dam Type: Random earth-fill with central core	Dam Height: 44.0 m
History	Recognition of risk in the	Unrecognized	
	When the Risk was recognized	Project Phase: Construction	Date: -
Project Phase	Status of corresponding	History of correspond to risks	
	Plan	long crack is not identified when design investigation	
Design	Design	Long crack was observed during foundation excavation, zig-zag grouting was conducted to improve the dam foundation.	
	Construction		
Impounding Operation/ maintenance		Piezometer instalation	
	Investigation /analysis	Research/analysis, etc. to assess impact	
How to respond to risk	Measures	Analysis, etc. to determine the need for and methods of response Contents of measures (avoidance, reduction, transfer) or retention Reduction Conducting grouting along the cracking zone	
	Retention (no measures)	How to deal with Basis for decision Reason Expected Impact	
Special Notes	Availability and method of monitoring	Geological condition, permeability improvement Piezometer	
	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, cost, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.	Availability and method of monitoring Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, cost, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.	
Applicable standards	Keywords	Technical issue There is seepage at downstream of the dam at elevation +163 m, check the possible continuity of the fracture at the dam to the point where the seepage occurs. To determine the effectiveness of handling and correlation of seepage downstream, measurement data of OW (Observation Well) 7 downstream of the fracture should also be presented, especially when the reservoir water level is already at MAN +185 m.	
Meeting Minutes:	Meeting Materials:	(Describe standards related to geological study, dam design, and countermeasure design)	
Other:		Draft- Risalah Siang Pleno, 4 Oktober 2021 Sidang Pleno Pelaksanaan Konstruksi dalam Rangka Izin Pengisian Awal, 4 Oktober 2021 Laporan Akhir, 28 Maret 2011, PT. Metana. Review FS dan DD Waduk Pidekso	

ID:	14	Name:	Tugu	Dam Type:	Zonal with vertical core	Dam Height:	89.9 m
Concepts of Risk	1	When the risk was identified (date)	Feb 2021	Construction	Spillway hill / right bank	Spillway clogging	Sliding of excavation hill
	2	Project Phase in which risks were recognized					
	3	Location (Structure/tree)					
	4	Contents of risk					
	5	Risk factors					
	6	Events in which risks were recognized	Sliding occur at right hill of spillway during excavation of spillway construction				
	7	Conditions/Situation for risk realization	Heavy rain, earthquake				
	8	Impact if the risk realize	Landslide material cloggin spillway, damage to spillway building				
	9	Where risk exists	Geology, rock mass, erosion				
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above				
	11	Phase of Realization	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others				
	12	Impact if the risk realize	<input type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.				
	13	Corresponding to risks	<input checked="" type="checkbox"/> Risk retention under certain conditions				
Overview of Causal Relationships	Slope cutting at spillway bank → Sliding occur at spillway collation and weathered rock → heavy rain, earthquake, steep cutting may trigger the landslide → disturbance spillway channel and damage to it → Risk reduction						
	Gentle slope excavation, drainage, surface protection → Risk reduction						
Explanatory Diagram (Schematic Diagram/ Photos, etc)							
	Photo-1 spillway bank slope condition with no protection at 'C' zone						

ID:	14	Name:	Tugu	Dam Type:	Zonal with vertical core	Dam Height:	89.9 m
History	Recognition or realization		Unrecognized	Project Phase:	partial protection	Date:	Feb 2021
	If the risk was recognized						
Project Phase	History of correspond to risks						
	Plan						
	Design						
Construction			partially slope was protected, water erosion was observed at unprotected slope				
			Photo-2 Trace of landslide and partial protection of slope				
Impounding							
Operational maintenance							
Investigation/analysis	Investigation/analysis to identify factors, etc.						
	Research/analysis, etc. to assess impact						
How to respond to risk	Analysis, etc. to determine the need for and methods of response						
	Contents of measures (avoidance, reduction, transfer) or retention						
Measures	Retention						
	How to deal with						
Retention (no measures)	Basis for decision						
	Reason						
Availability and method of information sharing	Expected impact						
	erosional surface that can trigger landslide at spillway bank slope						
Special Notes	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.						
	Technical issue						
Applicable standards/References	It should be handled comprehensively and designed for long-term stability, including improvements to the surface system and its 'sub-surface drainage'						
	(Describe standards related to geological study, dam design, and countermeasure design.)						
Meeting Minutes:	Kajian Keamanaan Bendungan, 13 SepTember 2021						
	Monitoring dan Evaluasi Pasca Impounding, 15 SepTember 2022						
Other:	Laporan Akhir, 27 Agustus 2013						

ID:	14	Name:	Tugu	Dam Type:	Zonal with vertical core	Dam Height:	89.9 m
Contents of Risk	1	When the risk was identified (date)	-				
	2	Project Phase in which risks were recognized	Design				
	3	Location (Structure/Area)	Reservoir area				
	4	Contents of risk	Decreasing storage capacity				
	5	Risk factors	Sedimentation in reservoir				
	6	Events in which risks were recognized	the sedimentation calculation show that tugu dam has high sedimentation				
	7	Condition/Situation for risk realization	River stream, landslides, erosion				
	8	Impact if the risk realize	Flooding control is not operated optimally, clogging the channel				
Perspectives on Risk Classification	9	Where risk exists	Material sedimentation, landslides				
	10	Character	<input checked="" type="checkbox"/> Mainly caused by external forces <input type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above <input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input type="checkbox"/> Due to large-scale external force action <input type="checkbox"/> Due to long-term use <input type="checkbox"/> Others				
	11	Phase of Realization	<input type="checkbox"/> Operation <input type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult. <input type="checkbox"/> Risk retention under certain conditions				
	12	Impact if the risk realize					
	13	Corresponding to risks					
	Overview of Causal Relationships						
		<p>High sedimentation → Tugu dam has high sedimentation that may reducing the life of the dam → sediment filled the reservoir → no act => Decreasing storage capacity → Flooding control is not operated optimally, clogging the channel → Risk reduction</p> <p>↑ build sabo dam or sediment control ↑</p>					
	Explanatory Diagram (Schematic Diagrams/ Photos, etc)						

ID:	14	Name:	Tugu	Dam Type:	Zonal with vertical core	Dam Height:	89.9 m
History	Recognition of risk in time		Recognized				
	When the risk was recognized	Project Phase: design	Date: -				
Project Phase	Status of corresponding	Budget proposal					
	History of correspond to risks						
Plan	No sediment control building						
Design	No sediment control building						
Construction	considering sedimentation control building like sabo dam						
Impounding							
Operation/ maintenance							
Investigation /analysis	Investigation/analysis to identify factors, etc.	-					
	Research/analysis, etc. to assess impact	-					
How to respond to risk	Analysis, etc. to determine the need for and methods of response	-					
	Contents of measures (avoidance, reduction, transfer) or retention	Reduction					
Measures	How to deal with	Considering sedimentation building					
	Basis for decision	Dam function, budget proposal					
	Reason	-					
	Expected impact	-					
Retention (no measures)	Availability and method of monitoring	-					
	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.	-					
Special Notes	Technical issues	-					
	To reduce the rate of reservoir sedimentation, integrated watershed conservation efforts should be carried out involving various related agencies and the community.	-					
Applicable standards	(Describe standards related to geological study, dam design, and countermeasure design.)						
Keywords	Sedimentation, reservoir, sabo dam						
References	Meeting Minutes:	Kajian Keamanan Bendungan, 13 September 2021					
	Meeting Materials:	Monitoring dan Evaluasi Pasca Impounding, 15 September 2022					
Other:	Laporan Akhir, 27 Agustus 2013						

1	When the risk was identified (date)	2014
2	Project phase in which risks were recognized	Design
3	Location (Structure/area)	Dam body / core zone
4	Contents of risk	High settlement of dam
5	Risk factors	Wet core material for core zone
6	Events in which risks were recognized	During technical discussion for impounding permit
7	Condition/Situation for risk realization	Soil consolidation
8	Impact if the risk realize	Dam body deformation, overtopping, cracking on dam
9	Where risk exists	Dam material
10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above <input checked="" type="checkbox"/> Project Implementation <input type="checkbox"/> Operation
11	Phase of Realization	<input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others
12	Impact if the risk realize	<input checked="" type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.
13	Corresponding to risks	<input type="checkbox"/> Risk retention under certain conditions
Overview of Core-Canal Relationships	Using wet core for core zone	during design investigation core material was recognized has high atterberg index Soil consolidation → high settlement of dam body → Dam body deformation, overtopping, cracking on dam → Warning system => mitigation ↳ Instrument monitoring

Table-1 Test Results of Embankment Material of Main Dam (Zone 1)

No	Soil Parameters	Technical specifications, Maximum Allowable Average of Tests	Test Results	Number of Tests	Remarks				
1	Maximum Size	mm	100	15					
2	Gravel Content	%	0.0	0.3	15				
3	Clay Content	%	05.0	33.41	43.60	15			
4	Liquid Limit (LL)	%	< 40	77.13	60.26	66.65	15	Meet the specifications	
5	Plastic Limit (PL)	%	38.4	49.06	5.81	39.20	42.67	15	Meet the specifications
6	Plastic Index (PI)	%	19.28	32.44	18.11	25.90	15	Meet the specifications	
7	Lab. Compaction (DMC)	%	26.16	44.86	42.6	36.4	36.8	15	Meet the specifications
8	Lab. Max. Dry Density (MDD)	g/cm ³	1.103	1.335	1.198	1.178	1.225	15	Meet the specifications
9	Field Dry Density (DD)	g/cm ³	1.11	1.172	1.104	1.104	1.104	1826	Meet the specifications
10	Field Water Content (WC)	%	46.07	45.63	56.68	43.25	49.65	1620	Meet the specifications
11	Degree of Density (DD)	%	95%	107.01	92.71	97.27	100.0	1820	Meet the specifications
12	Field Permeability (k)	cm/sec	11.00E-05	9.97E-06	11.6E-07	2.84E-06	9.81		Meet the specifications




Photo-1 Documentation of core material compaction (left) and field density test (right)

History	When the risk was recognized	Recognized
	Project Phase	Design
Project Phase	Status of corresponding	Instrument monitoring
	History of correspond to risks	
Plan		
Design		
Construction		
Impounding/Operation/maintenance		
Investigation/analysis	Investigation/analysis to identify factors, etc.	-
	Research/analysis, etc. to assess impact of response	-
	Analysis, etc. to determine the need for and methods of response	-
	Contents of measures (avoidance, reduction, transfer) or retention	retention
How to respond to risk	Measures	Instrument installation and monitoring
	Retention	Material condition
	Reason	Multi-layer settlement instrument
	Availability and method of monitoring	-
	Availability and method of information sharing	-
	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.	
Special Notes	Technical issue	
	Construction method of wet core should be explained, especially compaction method at the site. Consideration in the wet core is usually slightly higher than each 3% of the embankment height) and should be in the installation of instrumentation by considering the length of cable or tubing, etc.	
Applicable standards	Settlement, core material	
Keywords	(Describe the standards related to geological study, dam design, and countermeasure design.)	
Meeting Minutes	Pembahasan Pelaksanaan Konstruksi dan Keselamatan Pengisian Awal Waduk Bendungan Karim, 21 Maret 2022	
Meeting Materials	Dokumen Teknis Pengisian Awal Waduk, 21 Maret 2023	
Other	Review Design Report (PT. Kore Rural, 2015), Consulting Supervision For Construction Of Karim Multipurpose Dam Project	




Figure-1 Relationship Between Dry Density & Water Content




Figure-2 Multi-layer settlement reading period January to December 2021

1	When the risk was identified (date)	18 Jul 2022
2	Project phase in which risks were recognized	construction
3	Location (Structure/tree)	Stilling Basin Slope
4	Contents of risk	Spillway function, spillway damage
5	Risk factors	Sliding of slope, slope failure
6	Events in which risks were recognized	Sliding occur at excavation slope of stilling basin that had been protected
7	Condition/Situation for risk realization	Heavy rain, flooding, high water level of dam
8	Impact if the risk realize	Spillway malfunction due to clogged of landslide material
9	Where risk exists	Rock strength, Slope stability
10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above
11	Phase of Realization	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation
12	Impact if the risk realize	<input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others <input type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.
13	Corresponding to risks	<input checked="" type="checkbox"/> Risk retention under certain conditions





Figure-1 Engineering geology profile of spillway slope (landslide)

History	When the risk was recognized	Unrecognized
	Project Phase: Construction	Date: 18 Jul 2022
Status of corresponding Additional horizontal drainage, reinforcement, sloping		
History of correspond to risks		
Project Phase		
Plan		
Design	Slope improvement is done in 3 ways: - Slope Reduction 1,2 - Installation of 2 lanes Soldier Pile - Horizontal construction	
Construction	<p>Figure-1 Slope improvement at spillway of Ciawi Dry Dam</p>	
Impounding/Operational/maintenance	Investigation/analysis to identify factors, etc. Drilling and geophysical survey	
Investigation/analysis	Research/analysis, etc. to assess impact landslide occur due to pore water pressure Analysis, etc. to determine the need for and methods of response Reduction	
How to respond to risk	Contents of measures (avoidance, reduction, transfer or retention)	Reduction
	Measures	How to deal with Slope reduction, drainage installation, pile installation
	Retention (no measures)	Reason Ground condition, water level condition
	Availability and method of monitoring	Expected impact
Special Notes	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc. 1) Technical issue 2) Intersitation of flooding Features that areas with the potential for landslides have an adequate drainage system to direct surface flow. This reduces slope loads due to high groundwater levels, reducing landslide potential. To release uplift, consider that downcast the spillway is equipped with a relief well which can also function as an observation well. To monitor slope movement, consider adding inclinometer instruments and observation wells around the landslide location.	
Applicable standards	(Describe standards related to geological study, dam design, and countermeasure design.)	
Remarks	Stilling basin, landslide, slope stability	
References	Meeting Minutes: Sliding Plano Pemahaman Pelaksanaan Konstruksi Dan Kesiapua Pengisian Awal Waduk, 13 Desember 2022 Meeting Materials: Pelaksanaan Pembangunan Bendungan Ciawi (13 Desember 2022)	
Other:		

Name: Ciawi • Type: Zonal with inclined core		Dam Height: 55.0 m	
1	When the risk was identified (date)	-	
2	Project phase in which risks were recognized	Construction	
3	Location (Structure/Area)	Reservoir area	
4	Contents of risk	Slope stability, Sedimentation	
5	Risk factors	Landslide	
6	Events in which risks were recognized	After construction	
7	Condition/Situation for risk realization	Impounded, rain, ground water	
8	Impact if the risk realize	Slope failure, decreasing of storage capacity	
9	Where risk exists	Geology, permeability, cutting slopes	
10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above <input type="checkbox"/> Project Implementation <input type="checkbox"/> Operation	
11	Phase of Realization	<input type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others <input type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input checked="" type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.	
12	Impact if the risk realize		
13	Corresponding to risks		
Overview of Causal Relationships	Landslide potential	During construction many landslide occurred -> study and improvement are carried out	heavy rain, rising ground water level
			Slope stability, Sedimentation Slope failure, decreasing of storage capacity Risk retention Instream installation for monitoring

ID: 16	Name: Ciawi	Dam Type: Zonal with inclined core	Dam Height: 55.0 m
History	Recognition or when the risk was recognized	Unrecognized	
	Project Phase:	Construction	Date: -
Project Phase	Status of corresponding	Considering instrument monitoring	
	History of correspond to risks		
Plan			
Design			
Construction			
Impounding/Operation/maintenance			
Investigation/analysis	Investigation analysis to identify factors, etc. Research/analysis, etc. to assess impact Analysis, etc. to determine the need for and methods of response. Contents of measures (avoidance, reduction, transfer) or retention		
How to respond to risk	Measures	How to deal with	
	Retention (no measures)	Basis for decision	
	Availability and method of monitoring	Reason	
	Challenges: 1) Technical issues, 2) Constraints in project implementation equipments (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (rooms for improvement of risk management methods), etc.	Expected impact	
Special Notes	Technical issue a. Slopes with potential landslides should be depicted on the dam and reservoir basin layout map, with each location numbered. b. In the vicinity of these locations, intensive visual inspections and instrument monitoring should be carried out, with greater frequency, in conditions before and during the initial filling of the reservoir later. The need for intensive monitoring should be included in the OP Guidelines. c. The existence of the potential for landslides should be included as an indication of danger in the RFD Document. d. The monitoring plan to be carried out and the evaluation procedures should be included in the OP guidelines.		
Applicable standards/standards	(Describe standards related to geological study, dam design, and countermeasure design.)		
Meeting Minutes:	Sidang Pleno Pemahasan Pelaksanaan Konstruksi Dan Keampunan Pengisian Awal Waduk, 13 Desember 2022		
Meeting Materials:	Pelaksanaan Pembangunan Bendungan Ciawi (13 Desember 2022)		
Other:			

1	When the risk was identified (date)	2016
2	Project phase in which risks were recognized	Design
3	Location (Structure/area)	Dam body / core zone
4	Contents of risk	High settlement of dam
5	Risk factors	Wet core material for core zone
6	Events in which risks were recognized	During technical discussion for impounding permit
7	Condition/Situation for risk realization	Soil consolidation
8	Impact if the risk realize	Dam body deformation, overtopping, cracking on dam
9	Where risk exists	Dam material
10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above <input type="checkbox"/> Project implementation
11	Phase of Realization	<input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others
12	Impact if the risk realize	<input checked="" type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.
13	Corresponding to risks	<input type="checkbox"/> Risk retention under certain conditions
Overview of Causal Relationships	Using wet core for core zone	during design investigation core material was recognized has high atterberg index → high settlement of dam body → Dam body deformation, overtopping, cracking on dam → Warning system => mitigation
	Soil consolidation	Instrument monitoring → Warning system => mitigation

Table-1 Test Results of Embankment Material of Main Dam (Zone 1)

No	Parameter	MSL ± 0.00	MSL ± 0.10	MSL ± 0.20	MSL ± 0.30	MSL ± 0.40	MSL ± 0.50	MSL ± 0.60	MSL ± 0.70	MSL ± 0.80	MSL ± 0.90	MSL ± 1.00
1	Wet Core Material	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00
2	Wet Core Material	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00
3	Wet Core Material	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00
4	Wet Core Material	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00
5	Wet Core Material	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00
6	Wet Core Material	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00
7	Wet Core Material	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00
8	Wet Core Material	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00
9	Wet Core Material	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00
10	Wet Core Material	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00
11	Wet Core Material	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00
12	Wet Core Material	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00
13	Wet Core Material	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00
14	Wet Core Material	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00
15	Wet Core Material	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00
16	Wet Core Material	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00
17	Wet Core Material	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00
18	Wet Core Material	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00
19	Wet Core Material	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00
20	Wet Core Material	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00

Unit: kN/m² (1 kN/m² = 0.1 t/m²)

Recognition of risk in the construction	Recognized
When the risk was recognized	Design
Status of corresponding instrument monitoring	Instrument monitoring
History	Date: 2016
Project Phase	History of correspond to risks
Plan	
Design	The material has a difference in NVC and OMC values between 4-12%, where the NVC value is higher than the OMC value, the core material should be lined before compaction.
Construction	No information about embankment implementation of method of sukamahi dam
Impounding	Sukamahi dam is dry dam
Operation/maintenance	Based on the multilayer settlement graph there is a settlement up to 63 cm, where the height of the Sukamahi dam is 50 m, a settlement occurs more than 1%.




Figure-1 Multilayer settlement graph monitoring of Sukamahi Dam

Investigation/analysis	Investigation analysis to identify factors, etc.
How to respond to risk	Research analysis, etc. to assess impact
	Analysis, etc. to determine the need for and methods of response measures (avoidance, reduction, retention)
Measures	Retention
	How to deal with
	Basis for decision
Retention (no measures)	Soil condition
	High settlement
Availability and method of monitoring	
Special Notes	a. To be aware, in embankments of soft (wet) soil material, embankment settlement exceeding 1% is very likely to occur, only the extent to which this settlement can exceed the plastic limit of the embankment material requires a more detailed evaluation. b. A deformation analysis should be carried out to determine the dam body's plastic and elastic limit values, then compared with the dam deformation instrument readings (multilayer settlement, inclinometer, and shear stakes) (Describe standards related to geological study, dam design, and countermeasure design.)
Applicable standards	
Meeting Minutes:	Risalah Diskusi Teknis Pembahasan Pelaksanaan Konstruksi Dam Kesepakatan Pengisian Awal Waduk, 25 November 2022
Meeting Materials:	Rencana Operasi dan Pemeliharaan, 24 September 2022
Other:	Laporan Akhir, PT. Indra Karya, Agustus 2016

Concepts of Risk	1	When the risk was identified (date)	2023
	2	Project phase in which risks were recognized	Construction
	3	Location (Structure/tree)	Dam foundation
	4	Contents of risk	Constraint in embankment, dam seepage, water pressure
	5	Risk factors	Ground water
	6	Events in which risks were recognized	in the implementation of embankment materials a lot of groundwater comes out
	7	Conditions/Situation for risk realization	Impounding, raising
	8	Impact if the risk realize	score material cannot be compacted, increasing water pressure, dam stability
	9	Where risk exists	Geology, permeability, water pressure.
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above
	11	Phase of Realization	<input checked="" type="checkbox"/> Project Implementation <input type="checkbox"/> Operation <input type="checkbox"/> Due to large-scale external force action <input type="checkbox"/> Due to long-term use <input type="checkbox"/> Others
	12	Impact if the risk realize	<input checked="" type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affects the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input checked="" type="checkbox"/> Consider mitigation measures as risk avoidance is difficult. <input type="checkbox"/> Risk retention under certain conditions
	13	Corresponding to risks	<input checked="" type="checkbox"/> Risk retention under certain conditions <input type="checkbox"/> Risk reduction

Overview of Causal Relationships

```

    graph TD
      A[Ground water level] --> B[a lot of groundwater comes out -> Geophysical survey]
      B --> C[Impounding, raising]
      C --> D[uncompacted material, water pressure, dam pressure, dam]
      D --> E[Risk reduction]
      F[Concrete pad installation, dewatering system] --> E
  
```

Figure-1 Lugen profile show slope cut water level

Photo-1 Water seepage at right abutment

History	Recognition or not in the	Unrecognized
	If not the risk was recognized	Project Phase: Construction
Project Phase	Status of corresponding	concrete pad installation and dewatering system
	History of correspond to risks	
Plan		
Design		
Construction		<p>After geophysical survey, concrete pad at left and right abutment is installed to withhold the water seepage and dewatering well is constructed to lowering ground water level.</p> <p>Photo-1 Concrete pad installation at right and left abutment</p>
Impounding/operation/maintenance		
Investigation/analysis	Investigation/analysis to identify factors, etc.	Geophysical survey
	Research/analysis, etc. to assess impact of response	Ground water level near to surface dewatering well additional
How to respond to risk	Contents of measures (avoidance, reduction, transfer) or retention	Reduction
	Measures	concrete pad installation and dewatering system
How to deal with risk	How to deal with	Water level condition, construction time
	Reason	
Availability and method of information sharing	Expected impact	
	Reason	
Special Notes	Technical issues	
	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.	
Applicable standards		
References		
Meeting Minutes:		
Meeting Materials:		
Other:		

Concepts of Risk	1	When the risk was identified (date)	-	
	2	Project phase in which risks were recognized	Construction	
	3	Location (Structure/Area)	Dam Foundation	
	4	Contents of risk	Water seepage, foundation deformation	
	5	Risk factors	Fault, foundation deformation during excavation of dam foundation	
	6	Events in which risks were recognized	Earthquake	
	7	Conditions/Situation for risk realization	Foundation seepage, Dam breach	
	8	Impact if the risk realize	Geology, permeability, foundation treatment	
	9	Where risk exists	<input type="checkbox"/> Mainly caused by external forces	
	10	Character	<input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above	
	Perspectives on Risk Classification	11	Phase of Realization	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation
		12	Impact if the risk realize	<input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others
		13	Corresponding to risks	<input checked="" type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affects the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input checked="" type="checkbox"/> Consider mitigation measures as risk avoidance is difficult. <input type="checkbox"/> Risk retention under certain conditions




Figure-1 No fault was observed during design investigation (PT. Indrakarya 2016)

Figure-2 fault was observed during construction (PT. Rayakonsult (KS))

History	When the risk was recognized	Unrecognized
	Project Phase: Construction	Date: -
Status of corresponding		
History of correspond to risks		
Plan	no fault is mentioned at dam foundation at design stage	
Design	fault was observed during excavation of dam foundation at construction stage. This was improved by grouting (Stitch treatment).	
Construction	<p>Figure-1 Foundation improvement at Cipanas Dam with dental concrete-Stitchgrouting (blue) and dental LUGION TERBUK</p> <p>Figure-1 Lugeon profile of main Dam for pilot hole(top) tersier (middle) and check hole (bottom)</p>	
	Impounding/Operational/maintenance	Investigation/analysis to identify factors, etc.
Investigation/analysis	Research/analysis, etc. to assess impact of response	-
	Analysis, etc. to determine the need for and methods of response	-
Measures	Contents of measures (avoidance, reduction, transfer) or retention	Reduction
	How to deal with	conducting grouting fault at core zone foundation along the fault
Retention (no measures)	Basis for decision	geological condition
	Reason	-
Availability and method of monitoring	Expected impact	-
	Availability and method of information sharing	-
Special Notes	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.) 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc. 6) Reflection points (room for improvement of risk management methods), etc.	-
	Technical issues	-
Applicable standards	It should be explained that the existence of the fault regarding outcrop at the field, preservation zone, width of fracture etc. Considering cipanas dam is located around to active of Baribis, it could has high seismicity	-
	(Describe standards related to geological study, dam design, and countermeasure design.)	-
References	Fault, seismic hazard	-
	Meeting Minutes:	Risalah Sidang Pleno Pembahasan Konstruksi Dam Kesiapan Pengisian Awal Waduk, 12 April 2013
Other:	Meeting Materials:	Penyajian Dearth Gemangan Waduk
		Laporan Ringkas (PT. Indra Karya,2017), Sertifikasi Desain Bendungan Cipanas (Tahap I)

ID:	19	Name:	Cipanas	Dam Type:	Rock-filled dam with central core	Dam Height:	71.7 m
Concepts of Risk	1	When the risk was identified (date)	March 7, 2020				
	2	Project phase in which risks were recognized	Construction				
	3	Location (Structure/Area)	Saddle dam foundation, saddle dam body				
	4	Contents of risk	Saddle breach				
	5	Risk factors	Sliding on saddle body and foundation				
	6	Events in which risks were recognized	Sliding occurred during embankment implementation of saddle dam				
	7	Condition/Situation for risk realization	Increasing embankment height, rain, earthquake, impounding				
	8	Impact if the risk realize	Saddle dam breach, flooding at downstream				
	9	Where risk exists	Geology, dam material, foundation				
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above				
	11	Phase of Realization	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation				
	12	Impact if the risk realize	<input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others <input checked="" type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affects the schedule and costs of the projects <input checked="" type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.				
	13	Corresponding to risks	<input type="checkbox"/> Risk retention under certain conditions				
Overview of Causal Relationships	Flatt excavation for saddle dam → Sliding was occurred during embankment implementation of saddle dam → Increasing embankment height, rain, earthquake, impounding → Sliding on saddle body and foundation → Saddle dam failure						
	Flatt excavation for saddle dam → Sliding was occurred during embankment implementation of saddle dam → Increasing embankment height, rain, earthquake, impounding → Sliding on saddle body and foundation → Saddle dam failure → Risk reduction						
Explanatory Diagram (Schematic Diagram/ Photos, etc)							

ID:	19	Name:	Cipanas	Dam Type:	Rock-filled dam with central core	Dam Height:	71.7 m
History	Recognition or realization		Unrecognized				
	When the risk was recognized	Project Phase:	Construction				
	Status of corresponding	Date:	March 7, 2020				
Project Phase	History of correspond to risks						
Plan	During design the foundation cutting is flat for saddle dam						
Design	After sliding occur on saddle dam, consultant improved saddle dam foundation by lengthen or deepen the upstream foundation foot with zone 3 (rock) embankment						
Construction							
Impounding/Operational/maintenance	Photo-1 Condition of cipanas dam after improvement						
Investigation/analysis	Investigation/analysis to identify factors, etc. Research/analysis, etc. to assess impact of response Analysis, etc. to determine the need for and methods of response Contents of measures (avoidance, reduction, transfer) or retention						
How to respond to risk	Measures	How to deal with	Risk reduction				
	Retention (no measures)	Basis for decision	lengthen or deepen the upstream foundation				
	Availability and method of monitoring	Reason	Ground condition.				
	Expected impact	Expected impact	-				
Special Notes	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.						
	Technical issue						
Applicable standards/References	In the saddle dam the installation other instruments should be considerate, for example V-notch, piezometer, etc. (Describe standards related to geological study, dam design, and countermeasure design.)						
Meeting Minutes:	Risalah Sidang Plano Pembahasan Konstruksi Dam Kesajapan Pengisian Awal Waduk, 12 April 2023						
Meeting Materials:	Penyajian Dearth Geoteknik Waduk						
Other:	Laporan Rangka (PT. Indra Karya,2017), Sertifikasi Desain Bendungan Cipanas (Tahap 1)						

ID:	19	Name:	Cipanas	Dam Type:	Rock-filled dam with central core	Dam Height:	71,7 m
Contents of Risk	1	When the risk was identified (date)	-				
	2	Project phase in which risks were recognized	Construction				
	3	Location (Structure/Area)	Spillway foundation				
	4	Contents of risk	Uplift of spillway floor, spillway deformation, scouring				
	5	Risk factors	Uniformity of rock foundation				
	6	Events in which risks were recognized	Uniformity was observed during excavation for spillway foundation				
	7	Condition/Situation for risk realization	Impounding, rising of ground water level				
	8	Impact if the risk realize	Damage to spillway, foundation failure				
	9	Where risk exists	Geology, responsibility, design				
	10	Character	<input checked="" type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above <input type="checkbox"/> Project Implementation				
	11	Phase of Realization	<input checked="" type="checkbox"/> Operation <input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others				
	12	Impact if the risk realize	<input checked="" type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.				
	13	Corresponding to risks	<input type="checkbox"/> Risk retention under certain conditions				
Overview of Causal Relationships	Unconformity under spillway excavation → Unconformity was observed during spillway foundation excavation → Unconformity under spillway rising ground water level → Unconformity under spillway floor, spillway deformation, scouring → Damage to spillway						
	Unconformity under spillway excavation → Unconformity under spillway rising ground water level → Unconformity under spillway floor, spillway deformation, scouring → Damage to spillway						
Explanatory Diagram (Schematic Diagram/ Photos, etc.)							

Figure-1 Geological map and profile of Cipanas dam spillway

ID:	19	Name:	Cipanas	Dam Type:	Rock-filled dam with central core	Dam Height:	71,7 m
History	Recognition of risk in the operational		Unrecognized				
	Status of corresponding		to be confirmed				
Project Phase	When the risk was recognized		Project Phase: Construction				
	History of correspond to risks						
Plan	No information about unconformity at design stage						
	Unconformity was observed during excavation of spillway foundation.						
Design	Impounding had been conducted in May 2023, no further information after impounding						
	Operation/ maintenance						
Investigation /analysis	Investigation/analysis to identify factors, etc.		-				
	Research/analysis, etc. to assess impact of response		-				
How to respond to risk	Analysis, etc. to determine the need for and methods of response		-				
	Contents of measures (avoidance, reduction, transfer) or retention		-				
Measures	How to deal with		-				
	Basis for decision		-				
Retention (no measures)	Reason		-				
	Expected impact		-				
Special Notes	Availability and method of monitoring		-				
	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.						
Applicable standards	Technical issues						
	(Describe standards related to geological study, dam design, and countermeasure design.)						
References	Unconformity: spillway						
	Meeting Minutes:		Risalah Sidang Pleno Pembahasan Konstruksi Dan Kesiapan Pengisian Awal Waduk , 12 April 2023				
Other:	Meeting Materials:		Perencanaan Daerah Cernagan Waduk				
	Other:		Laporan Ringkas (PT. Indra Karya,2017): Sertifikasi Desain Bandungan Cipanas (Tahap II)				

ID: 20		Name: Semantok	Dam Type: Zonal Earth-Filled Dam, Central core	Dam Height: 30.0 m
Contents of Risk	1	When the risk was identified (date)	-	-
	2	Project phase in which risks were recognized	Construction	-
	3	Location (Structure/Area)	Dam foundation, reservoir area	-
	4	Contents of risk	Water leakage	-
	5	Risk factors	Permeable reservoir rock, permeable dam foundation	-
	6	Events in which risks were recognized	Comparing to another dam surrounding has seepage problem	-
	7	Condition/Situation for risk realization	Impounding	-
	8	Impact if the risk realize	no spilling out / long time spilling out	-
	9	Where risk exists	permeability, geology / rock condition	-
	10	Character	<input checked="" type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above <input type="checkbox"/> Project Implementation <input type="checkbox"/> Operation	-
	11	Phase of Realization	<input type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others <input type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.	-
	13	Corresponding to risks	<input type="checkbox"/> Risk retention under certain conditions	-
	Overview of Causal Relationships	<div style="display: flex; justify-content: space-between;"> <div style="border: 1px solid black; padding: 5px;">Leakage water from reservoir</div> <div style="border: 1px solid black; padding: 5px;">Impounding</div> <div style="border: 1px solid black; padding: 5px;">Reservoir water leakage</div> <div style="border: 1px solid black; padding: 5px;">no spilling out / long time spilling out</div> </div>		<div style="display: flex; justify-content: space-between;"> <div style="border: 1px solid black; padding: 5px;">Comparing to another dam surrounding with same lithology has seepage problem</div> <div style="border: 1px solid black; padding: 5px;">Reservoir water leakage</div> </div>
<div style="border: 1px solid black; padding: 5px;"> <p style="color: red; text-align: center;">blanket additional at the potential leakage location</p> </div>		<div style="border: 1px solid black; padding: 5px;"> <p style="color: red; text-align: center;">Risk avoidance</p> </div>		
Explanatory Diagram (Schematic Diagram/ Photos, etc.)				
	Photo-1 Condition of Semantok (image by Google, picture taken feb 2024)			

ID: 20		Name: Semantok	Dam Type: Zonal Earth-Filled Dam, Central core	Dam Height: 30.0 m	
History	When the risk was recognized	Unrecognized	-	-	
	Status of corresponding	Project Phase: Construction	-	Date: -	
Project Phase	History of correspond to risks				
Plan	No information about reservoir leakage during design stage				
Design	there was reservoir water leakage potential				
Construction	the current condition, Semantok dam can be impounded (to be confirmed of first spillout)				
Impounding					
	Photo-1 Condition of Semantok (image by Google, picture taken feb 2024)				
	Operation/ maintenance	Investigation/analysis to identify factors, etc.			
	Investigation /analysis	Research/analysis, etc. to assess impact	-		
		Analysis, etc. to determine the need for and methods of response	-		
		Contents of measures (avoidance, reduction, transfer) or retention	-		
	How to respond to risk	Measures	How to deal with	-	
		Retention (no measures)	Basis for decision	-	
			Reason	-	
		Expected impact	-		
Special Notes	Availability and method of monitoring	-			
	Availability and method of information sharing	-			
Applicable standards	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.				
	Technical issues				
References	It should be paid Attention to the possibility of a similar incident at the Semantok Dam due to the similarity of the geological conditions with the foundations of the Bening or Widas Dam and the Pacal Dam				
Keywords	(Describe standards related to geological study, dam design, and countermeasure design.)				
Meeting Minutes:	Reservoir leakage				
Meeting Materials:	Risalah sidang pleno pelaksanaan konstruksi, 26 Agustus 2022				
Other:	Sidang Pleno Pelaksanaan Konstruksi, 28 Juni 2022				
	Laporan Utama, Juli 2017, PT. Virama Karya				

<p>Contents of Risk</p> <p>1 When the risk was identified (date)</p> <p>2 Project phase in which risks were recognized</p> <p>3 Location (Structure/area)</p> <p>4 Contents of risk</p> <p>5 Risk factors</p> <p>6 Events in which risks were recognized</p> <p>7 Conditions/Situation for risk realization</p> <p>8 Impact if the risk realize</p> <p>9 Where risk exists</p> <p>10 Character</p> <p>11 Phase of Realization</p> <p>12 Impact if the risk realize</p> <p>13 Corresponding to risks</p>	<p>March 2023</p> <p>Construction</p> <p>Dam foundation</p> <p>Uplift, slab damage, seepage through foundation</p> <p>No grouting</p> <p>Regarding the lithology of foundation, it is estimated no grouting needed</p> <p>Impounding</p> <p>dam breach, water leakage, flooding</p> <p>Geology, permeability, dam material</p> <p><input type="checkbox"/> Mainly caused by external forces</p> <p><input checked="" type="checkbox"/> Mainly due to technical factors</p> <p><input type="checkbox"/> Factors other than the above</p> <p><input checked="" type="checkbox"/> Project Implementation</p> <p><input checked="" type="checkbox"/> Operation</p> <p><input checked="" type="checkbox"/> Due to large-scale external force action</p> <p><input checked="" type="checkbox"/> Due to long-term use</p> <p><input checked="" type="checkbox"/> Others</p> <p><input checked="" type="checkbox"/> Affects dam safety</p> <p><input checked="" type="checkbox"/> Affects the schedule and costs of the projects</p> <p><input checked="" type="checkbox"/> Basically risk avoidance</p> <p><input checked="" type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.</p> <p><input type="checkbox"/> Risk retention under certain conditions</p>
	<p>Foundation improvement by grouting at</p> <p>grouting is needed at design stage -> supervisor construction convey no need for grouting due to lithology condition</p> <p>impounding</p> <p>Uplift, slab damage, seepage through foundation</p> <p>dam breach, water leakage, flooding</p> <p>Risk reduction</p>
	<p>Overview of Causal Relationships</p>
	<p>Figure-1 Lugeon profile of Bener dam (mostly lugeon is more than 5)</p>
	<p>Explanatory Diagram (Schematic Diagram/ Photos, etc)</p>
	<p>Figure-2 The trial grouting configuration to confirm permeability of rock foundation</p>

<p>Recognition of risk in the economical</p> <p>Project Phase: Design</p> <p>Date: March 2023</p> <p>History</p> <p>When the risk was recognized</p> <p>Status of corresponding</p> <p>Trial grouting to confirm rock condition</p> <p>History of correspond to risks</p>	<p>Plan</p> <p>Design</p> <p>Construction</p>
<p>Plan</p> <p>Design</p> <p>Construction</p>	<p>Photo-1 Drilling log result of CH-1 at depth 0 to 25 meter shows that some joints was observed and had oxidation color, oxidation color indicated that water can flow through the rock joint</p> <p>Table-1 Result of trial grouting test</p>
<p>Impounding</p> <p>Operation</p> <p>maintenance</p>	<p>Trial grouting test</p>
<p>Investigation/analysis</p>	<p>Investigation/analysis to identify factors, etc.</p> <p>Research/analysis, etc. to assess impact</p> <p>Analysis, etc. to determine the need for and methods of response</p> <p>Contents of measures (avoidance, reduction, transfer or retention)</p>
<p>How to respond to risk</p>	<p>Measures</p> <p>How to deal with</p> <p>Risk for decision</p> <p>Reason</p> <p>Retention (no measures)</p> <p>Expected impact</p> <p>Availability and method of information sharing</p> <p>Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.</p>
<p>Special Notes</p>	<p>Technical issue</p> <p>a) The RQD value of the foundation rock should be explained to provide an overview of the geotechnical condition of the rock foundation.</p> <p>b) The grouting criteria need to be determined first, taking into account the condition of the foundation rock mass based on the reference or NSPK regarding foundation repairs.</p>
<p>Applicable standards</p> <p>Keywords</p> <p>References</p> <p>Other:</p>	<p>(Describe the standards related to geological study, dam design, and countermeasure design)</p> <p>Grouting, Dam foundation, Pilot</p> <p>Meeting Minutes:</p> <p>Diskusi Teknis Pembahasan Konstruksi Bendungan Bener, 27 Maret 2023</p> <p>Meeting Materials:</p> <p>Power Point Trial Grouting - K88 Manet 23</p> <p>Progress Pembangunan Bendungan 20 Maret 2023</p> <p>Laporan ringkasan (PT. Indra Karya, 2015), Desain Lanjutan dan Seritifikasi</p>

1	When the risk was identified (date)	2015		
2	Project phase in which risks were recognized	Design		
3	Location (Structure/Area)	Dam body / dam material		
4	Contents of risk	Water leakage, dam stability		
5	Risk factors	Cracking on impermeable membrane (concrete slab)		
6	Events in which risks were recognized	During technical discussion of construction implementation		
7	Conditions/Situation for risk realization	Dam deformation, earthquake, in-pounding		
8	Impact if the risk realize	Dam breach, water leakage through dam body		
9	Where risk exists	Dam material, permeability		
10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above		
11	Phase of Realization	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input type="checkbox"/> Due to large-scale external force action <input type="checkbox"/> Due to long-term use <input type="checkbox"/> Others		
12	Impact if the risk realize	<input type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affects the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.		
13	Corresponding to risks	<input type="checkbox"/> Risk retention under certain conditions		
Overview of Causal Relationship	Bener dam is design to be concrete face rock-filled dam	Dam deformation, earthquake, in-pounding	Water leakage, dam stability	Dam breach, water leakage through dam body
	During technical discussion CRFD is risk for crack due to deformation of dam body or from the concrete its self	Dam deformation, earthquake, in-pounding	Water leakage, dam stability	Risk reduction




Figure-1 Typical design of bener dam (169 m dam height)

Table-1 Laboratory Testing Results of Rock Quarry Materials and allowed criteria rock fill material for CRFD (Design, 2015)

No.	Jenis Pengujian	Contoh Batuan Dari Sekitar lokasi Quarry (Hand specimen)						Kriteria Yang diizinkan
		Q-1	Q-2	Q-3	Q-4	Q-5	Q-6	
1.	Specific gravity	2.648	2.662	2.697	2.722	2.730	2.176	> 2.5
2.	Absorption (%)	2.06	1.97	1.63	1.24	1.03	7.13	< 3%
3.	Soundness (%)	1.01	0.97	1.02	1.05	0.96	9.91	< 12%
4.	Abrasion (%)	18.72	15.80	17.83	18.30	15.90	45.33	< 40%
5.	Compressive Strength (Kg/cm²)	707.52	822.96	708.32	755.57	845.26	247.73	> 700 kg/cm²

Explanatory Diagram (Schematic Diagram/ Photos, etc)

History	When the risk was recognized	Project Phase: Design	Date: 2015
Project Phase	Status of corresponding	History of correspond to risks	
Plan	At the design stage the material of rockfilled was explained, considering Bener dam has height upto 169 m that classified to very high dam.		
Design	For construction of concrete membrane, the supervisor consultant will use Curb method. For rock material no information about the embankment		
Construction			
Impounding	Investigation (analysis to identify factors, etc)		
Operation/ maintenance	Research analysis, etc. to assess impact		
Investigation analysis	Analysis, etc. to determine the need for and methods of response of measures (avoidance, reduction, transfer or retention)		Reduction
	Measures	How to deal with	High quality control for rock fill material of embankment
How to respond to risk	Retention (no measures)	Reason	Dam safety, construction implementation
	Availability and method of maintaining	Expected impact	
Special Notes	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (construction time, cost, etc.) 3) Constraints in dam operation. 4) Issues due to human and organisational factors. results of risk response - 5) Impact on processes, cons, etc. 6) Reflection points (room for improvement of risk management methods), etc.		
	1) Technical issue 2) Dam material requirement - gradation of embankment material (adjust to the spec gradation prepared based on embankment experiments), granular shape (avoid flat shapes), - use fresh and hard rock (avoid using weathered or soft rock), - use heavy vibrator rollers or impact compaction rollers, which are commonly used in high CRFD and optimum compaction layer thickness (stone size does not exceed 2/3 of the compaction layer thickness), - Watering requirements during compaction (around 100-250 l/m³).		
Applicable standards	(Describe standards related to geological study, dam design, and countermeasure design)		
Keywords	CRFD, Concrete membrane		
Meeting Minutes:	Diskusi Teknis Pembahasan Konstruksi Bendungan Bener, 27 Maret 2023		
Meeting Materials:	Power Point Trial Granting -Kbb Maret 23		
Other:	Proses Pembanguan Bendungan 20 Maret 2023 Laporan inghasan (PT - Indra Karya,2015); Desain Lanjutan dan Sertifikasi		

ID:	22	Name:	Sadawarna	Dam Type:	Earth-filled dam, central core	Dam Height:	40.0 m						
Concerns of Risk 1 When the risk was identified (date) 2 Project phase in which risks were recognized 3 Location (Structure/Area) 4 Contents of risk 5 Risk factors 6 Events in which risks were recognized 7 Condition/Situation for risk realization 8 Impact if the risk realize 9 Where risk exists 10 Character 11 Phase of Realization 12 Impact if the risk realize 13 Corresponding to risks	2019-2022	Construction	Spillway, combat, dam foundation*	Dam building structure damage	Fault reactivation	Fault was observed surrounding dam sit during excavation	Foundation deformation, Dam break	Geology / Strength, Permeability, Design / Foundation treatment	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation	<input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others	<input checked="" type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affects the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input checked="" type="checkbox"/> Consider mitigation measures as risk avoidance is difficult. <input type="checkbox"/> Risk retention under certain conditions	
	Overview of Causal Relationship Many faults were observed during excavation for construction more much fault were observed => Special study, dam's fault to the basement fault (Barbiss Fault)		fault through foundation excavation for soft material and replaced by dental concrete and filter		Disposition of dam foundation		break and flooding		special stud for fault and instrument for other fault for monitoring		early warning for mitigation		
	Explanatory Diagram (Schematic Diagram/ Photos, etc) 												

Figure-1 Geological Map of Sadawarna Dam that many thrust fault was observed

Photo-1 Thrush fault of Sadawarna Dam at Conduit channel





ID:	22	Name:	Sadawarna	Dam Type:	Earth-filled dam, central core	Dam Height:	40.0 m	
History Project Phase Plan Design Construction Impounding Operation/ maintenance Investigation/ analysis How to respond to risk Special Notes Applicable standards Keywords Meeting Minutes: Meeting Materials: Other:	Recognized	Project Phase: Construction	2019-2022	When the risk was recognized Considering Special study of fault				
	Status of corresponding History of correspond to risks							
	The fault was identified during design and fault treatment was explained							
	Figure-1 Typical of Fault treatment of Sadawarna Dam							
	Figure-2 Fault treatment implementation during construction							
	Investigation/analysis to identify factors, etc. Research/analysis, etc. to assess impact Analysis, etc. to determine the need for and methods of expense Contents of measures (avoidance, reduction, transfer) or retention Mitigation							
	Measures conducting special study regarding to the fault Source of active fault							
	Retention (no measures) Reason Availability and method of monitoring							
	Availability and method of information sharing Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.							
	1) Technical issues a) Further investigation should be carried out regarding this part of the barbiss fault and its influence on the safety of the Sadawarna Dam. b) In identified locations as potentially affected by faults, intensive visual inspection and instrument monitoring should be carried out. c) The potential effect of the fault on the dam's safety should be included as an indication of the hazard in the RTD Document.							
	(Describe standards related to geological study, dam design, and countermeasure design.)							
Draft-Risalah Sidang Pleno Pelaksanaan Konstruksi dan Keseluruhan Bergesam Awal Waduk, 19 Oktober 2022 Sidang Pleno Impounding, 19 Oktober 2022 Laporan Akhir, Desember 2016, PT. Tata Guna Pania: Pekerjaan Review Desain Dan Sertifikasi Bendungan Sadawarna (05c)								



Figure-1 Typical of Fault treatment of Sadawarna Dam

Figure-2 Fault treatment implementation during construction

Figure-1 Geological Map of Sadawarna Dam that many thrust fault was observed

Photo-1 Thrush fault of Sadawarna Dam at Conduit channel

ID:	23	Name:	Bagong	Dam Type:	Rock-fill dam with central core	Dam Height:	82.0 m
Concepts of Risk	1	When the risk was identified (date)	7-Jul-22	Construction			
	2	Project phase in which risks were recognized					
	3	Location (Structure/tree)		Dam / Foundation, Spillway / Foundation			
	4	Contents of risk		Instability of the foundation, Piping of the foundation			
	5	Risk factors		Sliding of colluvium (rock mass sliding) used as foundation, Unequal settlement			
	6	Events in which risks were recognized		Sliding of the right bank cut slope occurred during the foundation excavation.			
	7	Conditions/Situation for risk realization		Foundation deterioration over time, Impounding, Heavy rains, Earthquakes			
	8	Impact if the risk realize		Dam breach causing flooding downstream, Damage to spillway			
	9	Where risk exists		Geology / Strength, Permeability, Design / Foundation treatment			
	10	Character		<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above			
	11	Phase of Realization		<input type="checkbox"/> Operation <input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others			
	12	Impact if the risk realize		<input checked="" type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affects the schedule and costs of the projects			
	13	Corresponding to risks		<input checked="" type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult. <input type="checkbox"/> Risk retention under certain conditions			
Overview of Causal Relationships	Foundation excavation as designed → Sliding of the right bank cut slope occurred → Additional geological survey → Recognition of the foundation as colluvium as foundation		Foundation using colluvium as foundation → (Content stability of the foundation, Piping of the foundation) → Dam breach causing flooding	Risk avoidance ↳ Redesign without using colluvium as foundation (to be determined)			
	Foundation excavation as designed → Sliding of the right bank cut slope occurred → Additional geological survey → Recognition of the foundation as colluvium as foundation		Foundation using colluvium as foundation → (Content stability of the foundation, Piping of the foundation) → Dam breach causing flooding	Risk avoidance ↳ Redesign without using colluvium as foundation (to be determined)			
Explanatory Diagram (Schematic Diagram/ Photos, etc)							
							

ID:	23	Name:	Bagong	Dam Type:	Rock-fill dam with central core	Dam Height:	82.0 m
History	Recognition or realization		Unrecognized	Project Phase:	Construction	Date:	7-Jul-22
	If the risk was recognized		Unrecognized	Status of corresponding	Considering countermeasure methods		
Project Phase	History of correspond to risks						
Plan	The design was to use bedrock as the foundation.						
Design	As the distribution of thick colluvial soil was confirmed during foundation excavation, the use of colluvial soil as the foundation is being considered.						
Construction	Figure-1 Dam axis geologic cross section (During investigation/design)						
	Figure-2 Geological cross section of the dam axis (Site plan after additional investigation)						
Impounding/Operational/maintenance							
Investigation/analysis	Investigation/analysis to identify factors, etc.						
How to respond to risk	Research/analysis, etc. to assess impact of response						
	Contents of measures (avoidance, reduction, transfer or retention)						
Measures	Reduction						
	- Foundation Treatment- Spillway, Pile foundation-Scant Pile Dam-Scant Pile Ground conditions, Construction cost						
Retention (no measures)	-						
Availability and method of monitoring	-						
Special Notes	<p>Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.) 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.</p> <p>1) Technical issues.</p> <p>2) Constraints in project implementation requirements (Construction time, costs, etc.)</p> <p>The geological conditions of the dam site differed significantly between the geological investigation/design and construction phases.</p> <p>The following risks should be considered once again when adopting the current countermeasure plan.</p> <p>1) Sliding along the boundary between the collapsed soil and bedrock</p> <p>2) Piping at the foundation where the spillway meets the dam due to unequal settlement</p>						
Applicable standards	(Describe standards related to geological study, dam design, and countermeasure design.)						
Remarks	Colluvium, Weathering, Creep						
Meeting Minutes:	2023.09.21 RDT Spillway Bagong [Z-AF] + CL (rev)						
Meeting Materials:	Cap 22c-KSD Laporan Inspeksi dan evaluasi Pelaksanaan Konstruksi B. Bagong						
Other:	LAPORAN AKHIR STUDY NEOTEKNIK, Laporan Progress Pengboran hasil MASW						

ID:	23	Name:	Blagong	Dam Type:	Rock-fill dam with central core	Dam Height:	82.0 m
Concerns of Risk	1	When the risk was identified (date)	7-Jul-22	Construction			
	2	Project phase in which risks were recognized		Dam / Foundation			
	3	Location (Structure/tree)		Piping of the foundation, instability of the foundation			
	4	Contents of risk		Sliding of colluvium used as foundation, Unequal settlement			
	5	Risk factors		Sliding of the right bank cut slope occurred during the foundation excavation			
	6	Events in which risks were recognized		Foundation deterioration over time, Impounding, Heavy rains, Earthquakes			
	7	Condition/Situation for risk realization		Dam breach causing flooding downstream			
	8	Impact if the risk realize		Geology / Strength, Permeability, Design / Foundation treatment			
Perspectives on Risk Classification	9	Where risk exists		<input type="checkbox"/> Mainly caused by external forces			
	10	Character		<input checked="" type="checkbox"/> Mainly due to technical factors			
				<input type="checkbox"/> Factors other than the above			
	11	Phase of Realization		<input type="checkbox"/> Project Implementation			
				<input checked="" type="checkbox"/> Operation			
				<input checked="" type="checkbox"/> Due to large-scale external force action			
				<input checked="" type="checkbox"/> Due to long-term use			
12	Impact if the risk realize		<input type="checkbox"/> Others				
			<input checked="" type="checkbox"/> Affects dam safety				
			<input type="checkbox"/> Affects dam function				
			<input type="checkbox"/> Affect the schedule and costs of the projects				
13	Corresponding to risks		<input checked="" type="checkbox"/> Basically risk avoidance				
			<input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.				
			<input type="checkbox"/> Risk retention under certain conditions				
Overview of Causal Relationships		Foundation excavation as designed		Recessing using colluvium as foundation		Dam breach causing flooding	
		Sliding of the right bank cut slope occurred => Additional geological survey => Recognition of the		Recessing without using colluvium as foundation (to be determined)		Risk avoidance	








Figure-2 Secant pile construction plan

ID:	23	Name:	Blagong	Dam Type:	Rock-fill dam with central core	Dam Height:	82.0 m
History	Recognition or not of the risk	Unrecognized		Project Phase:	Construction	Date:	7-Jul-22
	Status of corresponding	Considering countermeasure methods		History of correspond to risks			
	Project Phase						
Plan	Design	The design was to use bedrock as the foundation. As the distribution of thick colluvial soil was confirmed during foundation excavation, the use of colluvial soil as the foundation is being considered.					
	Construction	 					
Investigation/ maintenance	Investigation analysis to identify factors, etc.						
	Research/analysis, etc. to assess impact /analysis, etc. to determine the need for and methods of response	Reduction					
How to respond to risk	Measures	Installation of an impervious wall with a secant pile in the collapsed soil of the foundation.					
	Reasons for decision	Ground conditions, Construction cost					
Applicable standards	Availability and method of monitoring						
	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.) 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc. 6) Reflection points (room for improvement of risk management methods), etc.						
Special Notes	1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.)						
	The geological conditions at the dam site differed significantly between the geological investigation design and construction phases. It should be noted that unequal settlement between the core zone foundation and the rock zone foundation should be taken into account. It is also recommended to extend the construction area of the secant pile to the top of the dam.						
Keywords	Colluvium, Weathering, Topographical interpretation						
	Meeting Minutes:	2023.09.21 RDT Spillway Blagong [ZAF] - CI (rev), Cap 226-SKKE Laporan Inspeksi dan rangka Pelaksanaan Konstruksi B. Blagong					
References	Meeting Materials:	Paparan BTB shimitzu					
	Other:	LAPORAN AKHIR STUDY NEOTEKNIK, Laporan Progress Pekerjaan basal MASSIV					

ID:	24	Name:	Randaugingting	Dam Type:	Zonal with vertical core	Dam Height:	31.0 m
Contents of Risk	1	When the risk was identified (date)	1 Jan 2022				
	2	Project phase in which risks were recognized	Impounding				
	3	Location (Structure/Area)	Reservoir area				
	4	Contents of risk	Dam function disruption				
	5	Risk factors	Sliding at reservoir				
	6	Events in which risks were recognized	Sliding potential was observed during inspection after impounding				
	7	Conditions/Situation for risk realization	Rain, earthquake, impounding (water fluctuation)				
	8	Impact if the risk realize	Damage to building facility				
	9	Where risk exists	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above				
Perspectives on Risk Classification	10	Character	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others				
	11	Phase of Realization	<input type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult. <input checked="" type="checkbox"/> Risk retention under certain conditions				
	12	Impact if the risk realize					
Overview of Causal Relationship	13	Corresponding to risks					
			Sliding potential was observed at reservoir are a near to building facility	Sliding potential was observed during inspection after impounding	Rain, earthquake, water fluctuation	Dam function disruption	Damage to building facility
Explanatory Diagram (Schematic Diagram/ Photos, etc)							



ID:	24	Name:	Randaugingting	Dam Type:	Zonal with vertical core	Dam Height:	31.0 m
History		Recognition or not in the	Unrecognized				
		When the risk was recognized	1-Jan-22				
Project Phase		Project Phase:	Impounding				
		Status of corresponding	Considering sloping, reinforcement and protection				
Plan		History of correspond to risks					
Design							
Construction							
Impounding							
Operation/ maintenance							
Investigation /analysis							
How to respond to risk							
Special Notes							
Applicable standards							
References							



ID:	25	Name:	Jlajah	Dam Type:	Gravel Pebble Random, Central Core	Dam Height:	70.0 m
Concepts of Risk	1	When the risk was identified (date)	-	Construction			
	2	Project Phase in which risks were recognized		Dam Foundation			
	3	Location (Structure/tree)		Material leaching / washout, Foundation seepage			
	4	Contents of risk		Permeable foundation			
	5	Risk factors		After check hole of grouting, the lagoon value doesn't reach requirement			
	6	Events in which risks were recognized		Impounding			
	7	Conditions/Situation for risk realization		Dam breach, instability-dam, possibility doesn't determined water level			
	8	Impact if the risk realize		Geology / Strength, Permeability, Design / Foundation treatment			
	9	Where risk exists		<input type="checkbox"/> Mainly caused by external forces			
	10	Character		<input checked="" type="checkbox"/> Mainly due to technical factors			
				<input type="checkbox"/> Factors other than the above			
	11	Phase of Realization		<input checked="" type="checkbox"/> Project Implementation			
	12	Impact if the risk realize		<input checked="" type="checkbox"/> Due to large-scale external force action			
13	Corresponding to risks		<input checked="" type="checkbox"/> Due to long-term use				
Perspectives on Risk Classification			<input checked="" type="checkbox"/> Others				
			<input checked="" type="checkbox"/> Affects dam safety				
			<input checked="" type="checkbox"/> Affects dam function				
Overview of Causal Relationships			<input checked="" type="checkbox"/> Affect the schedule and costs of the projects				
			<input checked="" type="checkbox"/> Basically risk avoidance				
			<input checked="" type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.				
Explanatory Diagram (Schematic Diagram/ Photos, etc)			<input type="checkbox"/> Risk retention under certain conditions				
			<input type="checkbox"/> Impounding of dam				
			using grouting for foundation improvement				
			Lagoon value doesn't meet requirement confirmed by check hole of grouting				
			Material leaching/washout Foundation seepage				
			Instability dam, unreached water level determined, dam break				
			additional cut-off wall				
			Risk avoidance				




Figure-1 Lugeon profile of pilot hole



Figure-2 Lugeon profile of check hole (after grouting)

ID:	25	Name:	Jlajah	Dam Type:	Gravel Pebble Random, Central Core	Dam Height:	70.0 m
History		Recognition or non-recognition	recognized	Project Phase:	Construction	Date:	-
		If the risk was reassessed		Status of corresponding	additional cut-off wall for foundation improvement		
		History of correspond to risks					
Plan		Using grouting for dam foundation improvement					
		after grouting was conducted, the lagoon value doesn't meet requirement then the consultant propose to add cut-off wall for foundation					
Design							
Construction							
Impounding/Operation/maintenance							
Investigation/analysis		Investigation/analysis to identify factors, etc.					
		Research/analysis, etc. to assess impact of response					
How to respond to risk		Contents of measures (avoidance, reduction, transfer) or retention	avoidance				
		Measures	additional insulation of cut-off wall to improve permeability of foundation				
Special Notes		How to deal with	Ground condition				
		Reason	Expected impact				
		Availability and method of monitoring					
		Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.) 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.					
		1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.)					
		the advantages and disadvantages of various alternative foundation improvement methods, the conclusions should be presented in a comparison matrix from the aspects of dam safety/success in achieving quality targets, effectiveness of foundation repair results, ease of implementation, time and cost, taking into account the geological conditions of the foundation					
Applicable standards			(Describe standards related to geological study, dam design, and countermeasure design.)				
Remarks			Grouting, lagoon permeability				
References			Risalah Diskusi Teknis Pemalsuan Perubahan Peraturan Fondasi, 2 Mei 2023				
			Pembangunan Bendungan Jlajah, Feb 2023				
			Other:				





Figure-1 Design cross-section of foundation improvement with cut-off wall

ID:	25	Name:	Jlantah	Dam Type:	Gravel Pebble Random, Central Core	Dam Height:	70.0 m
Contents of Risk	1	When the risk was identified (date)	-	Construction			
	2	Project phase in which risks were recognized		Dam foundation			
	3	Location (Structure/Area)		Water seepage, uplift			
	4	Contents of risk		weak zone of cut-off wall connection			
	5	Risk factors		overlap of curtain grouting and cut off wall is weak zone			
	6	Events in which risks were recognized		Impounding			
	7	Condition/Situation for risk realization		Dam break			
	8	Impact if the risk realize		Geology, permeability, Desain			
	9	Where risk exists		<input type="checkbox"/> Mainly caused by external forces			
	10	Character		<input checked="" type="checkbox"/> Mainly due to technical factors			
Perspectives on Risk Classification	11	Phase of Realization		<input type="checkbox"/> Factors other than the above			
	12	Impact if the risk realize		<input checked="" type="checkbox"/> Project Implementation			
	13	Corresponding to risks		<input checked="" type="checkbox"/> Operation			
Overview of Causal Relationships	Foundation improvement		Grouting was chosen for foundation improvement => grouting is insufficient for foundation improvement	Several part still has high lugason value after grating	Water seepage still can through foundation that may cause uplift	Dam break	
							Risk reduction
Explanatory Diagram (Schematic Diagram/ Photos, etc)							
	<p>Figure-1 Lugeon profile of check hole / after grouting</p>						

ID:	25	Name:	Jlantah	Dam Type:	Gravel Pebble Random, Central Core	Dam Height:	70.0 m
History	When the risk was recognized	Unrecognized		Project Phase:	Construction	Date:	-
	Status of corresponding	Considering cut off wall		History of correspond to risks			
Project Phase	History of correspond to risks						
Plan	Grouting is used for dam improvement						
Design	Grouting was conducted for dam improvement but several part still has high value of lugeon test. Additional Cut off wall for permeability improvement is considered.						
Construction							
Impounding							
Operation/maintenance							
Investigation /analysis	Investigation/analysis to identify factors, etc.						
How to respond to risk	Research/analysis, etc. to assess impact	-					
	Analysis, etc. to determine the need for and methods of response.	-					
	Contents of measures (avoidance, reduction, transfer) or retention	Reduction					
	Measures	How to deal with	Additional cut of wall				
	Retention (no measures)	Basis for decision	Ground condition, dam safety				
Availability and method of monitoring	Reason	-					
	Expected impact	-					
	Availability and method of monitoring	-					
Special Notes	<p>Availability and method of information sharing</p> <p>Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.</p> <p>Technical issue</p> <p>The contact area between the curtain grouting structure and the diaphragm wall is a weak zone that can become a foundation seepage path. To assess the effectiveness of the cut off wall to be implemented, the pumping well test can be used.</p>						
Applicable standards	(Describe standards related to geological study, dam design, and countermeasure design.)						
Keywords	Dam foundation, permeable zone, cut-off wall						
References	Risetah Diskusi Teknis Pembahasan Perubahan Perbaikan Fondasi, 2 Mei 2023						
Other:	Pembangunan Bendungan Jlantah, Feb 2023						

ID: 26	Name: Jragung	Dam Type: Zonal with centre core	Dam Height: 59.5 m	
Concepts of Risk	1	When the risk was identified (date)	January 2022	
	2	Project phase in which risks were recognized	Construction	
	3	Location (Structure/area)	Dam / Foundation	
	4	Contents of risk	Instability of the foundation	
	5	Risk factors	Unequal settlement, groyne damage causing crack	
	6	Events in which risks were recognized	colluvium layer was observed during the foundation excavation	
	7	Conditions/Situation for risk realization	Foundation deterioration over time, groyne cracking due to settlement	
	8	Impact if the risk realize	Dam breach causing flooding downstream	
	9	Where risk exists	Geology / Strength, Permeability, Design / Foundation treatment	
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above	
	Perspectives on Risk Classification	11	Phase of Realization	<input type="checkbox"/> Operation <input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others
		12	Impact if the risk realize	<input type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affects the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.
	Overview of Causal Relationships	13	Corresponding to risks	<input checked="" type="checkbox"/> Risk retention under certain conditions
			<div style="display: flex; justify-content: space-around; align-items: center;"> <div style="border: 1px solid black; padding: 5px;">Foundation was observed during dam foundation excavation => identify distribution of colluvium</div> <div style="border: 1px solid black; padding: 5px;">Foundation improvement for colluvium</div> <div style="border: 1px solid black; padding: 5px;">Instability of the foundation</div> <div style="border: 1px solid black; padding: 5px;">Dam breach, groyne damage</div> </div> <div style="margin-top: 10px;"> ↓ Dam foundation improvement using CTB (cement treated base). </div>	



ID: 26	Name: Jragung	Dam Type: Zonal with centre core	Dam Height: 59.5 m
History	Recognition or non-recognition of the risk	Unrecognized	
	When the risk was recognized		
	Project Phase: Construction		Date: January 2022
	Status of corresponding improvement using CTB (cement treated base)		
Project Phase	History of correspond to risks		
	Plan		
Design	Using sandstone and claystone as dam foundation		
	Construction	<p>Figure-1 Geological profile of STA 1+150</p>	
Impounding Operation/ maintenance			
	Investigation/analysis	Investigation/analysis to identify factors, etc. Research/analysis, etc. to assess impact Analysis, etc. to determine the need for and methods of response	
How to respond to risk	Contents of measures (avoidance, reduction, transfer) or retention	Avoidance foundation improvement using Cement Treated Base	
	Measures	Cost, Groyne installation	
Special Notes	How to deal with	-	
	Retention (no measures)	-	
Applicable standards	Availability and method of information sharing	-	
	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.	-	
References	1) Technical issues,	-	
	2) Constraints in project implementation	-	
Remarks	From the results of some consideration on colluvium location will be carried out using CTB (Cement Treated Base) with mixture: Cement: 118 kg, Aggregate: 232 kg and Water: 100. On site 28 will produce K100-0.25. The CTB should be compacted and the dental cement conducted on surface, because of there is a groyne -cap, it is necessary to add contact groyne than check holes should be carried out for groyne results.		
Meeting Minutes:	(Describe standards related to geological study, dam design, and countermeasure design.)		
Meeting Materials:	laporan inspeksi bendungan Jragung, 14 Juni 2023		
Other:	Diskusi Teknis 31 Januari 2023 Kondisi Geologi Bendungan Final Report Geolistrik - Jragung Semarang - Alhappya Juni 2022		

ID:	27	Name:	Maringkayu	Dam Type:	Homogeneous Dam	Dam Height:	154 m
Contents of Risk	1	When the risk was identified (date)	2013				
	2	Project Phase in which risks were recognized	Impounding				
	3	Location (Structure/Area)	Reservoir				
	4	Contents of risk	External factor				
	5	Risk factors	The reservoir impound gas well				
	6	Events in which risks were recognized	Gas wells were observed will be drawn by dam impounding				
	7	Condition/Situation for risk realization	Diversion plugging				
	8	Impact if the risk realize	External factor				
Perspectives on Risk Classification	9	Where risk exists	Impounding, water level				
	10	Character	<input type="checkbox"/> Mainly caused by external forces <input type="checkbox"/> Mainly due to technical factors <input checked="" type="checkbox"/> Factors other than the above				
	11	Phase of Realization	<input checked="" type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input type="checkbox"/> Due to large-scale external force action <input type="checkbox"/> Due to long-term use <input type="checkbox"/> Others				
	12	Impact if the risk realize	<input checked="" type="checkbox"/> Affects dam safety <input checked="" type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.				
Overview of Causal Relationships	13	Corresponding to risks	<input type="checkbox"/> Risk retention under certain conditions				
			<div style="display: flex; justify-content: space-around; align-items: center;"> <div style="border: 1px solid black; padding: 5px; width: 15%;"> Dam reservoir at NWL as +110m </div> <div style="border: 1px solid black; padding: 5px; width: 30%;"> before impounding at reservoir there were several gas well will be drawn => identify elevation of gas well </div> <div style="border: 1px solid black; padding: 5px; width: 30%;"> Impounding diversion plugging </div> <div style="border: 1px solid black; padding: 5px; width: 15%;"> gas well will be drawn (gas well operation) </div> </div> <div style="margin-top: 10px; display: flex; justify-content: space-around;"> <div style="border: 1px solid red; padding: 5px; width: 30%; color: red;"> Impounded below the gas well elevation </div> <div style="border: 1px solid red; padding: 5px; width: 30%; color: red;"> Risk avoidance </div> </div>				
Explanatory Diagram (Schematic Diagram/ Photos, etc)							
			<p>Figure-1 Situation of drawn well (red mark) at dam NWL (elv. +110 m)</p>				

ID:	27	Name:	Maringkayu	Dam Type:	Homogeneous Dam	Dam Height:	154 m
History		Recognition or realization	Unrecognized				
		When the risk was recognized	2013				
Project Phase		Project Phase:	Impounding				
		Status of corresponding	Considering lowering reservoir water level				
Plan		History of correspond to risks					
Design			The reservoir was planned at elevation of +110 m for normal water level				
			Dam was constructed at elevation of +110 m for normal water level				
Construction			The initial impounding will be engaged at elevation of +107.23 m by using emergency spillway				
Operational maintenance							
Investigation/analysis							
How to respond to risk							
Special Notes							
Applicable standards							
References							

ID:	28	Name:	Sepaku Semol	Dam Type:	Homogeneous Dam	Dam Height:	22.0 m
Concepts of Risk	1	When the risk was identified (date)	-	Construction			
	2	Project phase in which risks were recognized	-	Dam foundation			
	3	Location (Structure/area)	-	Differential settlement			
	4	Causes of risk	-	High difference modulus value of rock foundation and concrete for treatment			
	5	Risk factors	-	During excavation cavity was observed			
	6	Events in which risks were recognized	-	Embankment load			
	7	Condition/Situation for risk realization	-	Cracking at core material, water leakage, dam breach			
	8	Impact if the risk realize	-	Geology / strength, construction material, treatment			
	9	Where risk exists	-	<input type="checkbox"/> Mainly caused by external forces			
	10	Character	-	<input checked="" type="checkbox"/> Mainly due to technical factors			
	11	Phase of Realization	-	<input type="checkbox"/> Factors other than the above			
	12	Impact if the risk realize	-	<input type="checkbox"/> Project Implementation			
	13	Corresponding to risks	-	<input checked="" type="checkbox"/> Operation			
Perspectives on Risk Classification			<input checked="" type="checkbox"/> Due to large-scale external force action				
			<input checked="" type="checkbox"/> Due to long-term use				
Overview of Causal Relationships			<input checked="" type="checkbox"/> Others				
			<input checked="" type="checkbox"/> Affects dam safety				
Explanatory Diagram (Schematic Diagram/ Photos, etc)			<input type="checkbox"/> Affects dam function				
			<input type="checkbox"/> Affect the schedule and costs of the projects				
			<input type="checkbox"/> Basically risk avoidance				
			<input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.				
			<input checked="" type="checkbox"/> Risk retention under certain conditions				
			loading of embankment				
			During excavation cavity was observed => foundation treatment by dental concrete K225				
			Differential settlement				
			Cracking at core material, water leakage, dam breach				
			Risk reduction				
			using concrete which has same modulus of rock foundation				



Photo-1 Rock foundation condition of Sepaku Semol Dam

ID:	28	Name:	Sepaku Semol	Dam Type:	Homogeneous Dam	Dam Height:	22.0 m
History		Recognition or not in the	Unrecognized				
		If the risk was recognized	Project Phase: Construction				
Project Phase		Status of corresponding	Foundation improvement using dental concrete K225				
		History of correspond to risks					
Plan							
Design		No cavity information during the investigation at design stage					
		Foundation improvement by dental concrete K225 at cavity that the modulus of concrete and rock foundation has high modulus difference					
Construction							
Impounding/Operational/maintenance							
Investigation/analysis		Investigation/analysis to identify factors, etc.	-				
		Research/analysis, etc. to assess impact of response	-				
How to respond to risk		Analysis, etc. to determine the need for and methods of response	-				
		Contents of measures (avoidance, reduction, transfer) or retention	Reduction				
Measures		How to deal with	conducting dental concrete				
		Basis for decision	Rock foundation condition				
Retention (no measures)		Reason	-				
		Expected impact	-				
Availability and method of information sharing		Availability and method of information sharing	-				
		Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.					
Special Notes		Technical issues					
		Anything that needs to be considered is the potential for differential settlement if the dental modulus value of the concrete is significantly different from the modulus value of the surrounding rock					
Applicable standards/References		Statement, limestone					
		Meeting Minutes:	Risalah Sidang Pengisian Awal Waduk, 26 Juni 2023				
		Meeting Materials:	Diskusi Pesiapan Impounding				
		Other:	Executive Report, November 2019, PT. Tekniks CIPta Konsultan				

Concepts of Risk	1	When the risk was identified (date)	July 2023
	2	Project phase in which risks were recognized	After impounding
	3	Location (Structure/Area)	Intake tunnel
	4	Contents of risk	Water flow, material dissolution tunnel collapse
	5	Risk factors	during inspection seepage was observed at the intake tunnel
	6	Events in which risks were recognized	Water pressure, water flow
	7	Condition/Situation for risk realization	Unstable wall tunnel
	8	Impact if the risk realize	Seepage, permeability, concrete material
	9	Where risk exists	<input type="checkbox"/> Mainly caused by external forces <input type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above
	10	Character	<input type="checkbox"/> Project Implementation <input type="checkbox"/> Operation
	11	Phase of Realization	<input type="checkbox"/> Due to large-scale external force action <input type="checkbox"/> Due to long-term use <input type="checkbox"/> Others
	12	Impact if the risk realize	<input type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance <input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.
	13	Corresponding to risks	<input type="checkbox"/> Risk retention under certain conditions


Seepage at intake tunnel → during inspection seepage was observed at the intake tunnel = Debit monitoring

Water come out through tunnel wall due to Water pressure. → material dissolution => Decreasing material quality → Unstable wall tunnel, Tunnel collapse → Risk retention

SI water discharge and condition monitoring → Risk retention

Figure-1 Geological profile along the tunnel of Karalloe Dam

History	Recognition or not in the past	Unrecognized
	When the risk was recognized	Project Phase: Impounding
	Status of corresponding	Risk retention and monitoring
	Project Phase	History of correspond to risks
	Plan	
Design		
Construction		



Operation/ maintenance	Investigation analysis to identify factors, etc.	-
	Research analysis, etc. to assess impact	-
How to respond to risk	Analysis, etc. to determine the need for and methods of response	-
	Contents of measures (avoidance, reduction, transfer or retention)	Retention
Special Notes	Measures	How to deal with
	Reason (for measures)	Reservoir water level is not effect to discharge at tunnel seepage
Applicable standards	Availability and method of monitoring	Decreasing quality of concrete material of tunnel
	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operations, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection technical issue	Installation v-notch
Keywords	Seepage, tunnel	
References	Meeting Minutes	
Other:	Meeting Materials	Diskusi Teknis Karalloe, Pemantauan Setelah Impounding Bendungan Karalloe, 7 Januari 2022
		Pendahuluan-Sertifikasi Izin Operasi, 4 Juni 2023
		Laporan Akhir (PT, Metana, 2014): Desain Bendungan Karalloe (Sertifikasi Karalloe,2014)

Contents of Risk	1	When the risk was identified (date)	-
	2	Project phase in which risks were recognized	Construction
	3	Location (Structure/Area)	Dam foundation
	4	Contents of risk	material leaching, water leakage
	5	Risk factors	water seepage
	6	Events in which risks were recognized	several springs were observed in dam foundation
	7	Condition/Situation for risk realization	increasing ground water level, impounding
	8	Impact if the risk realize	pipng, dam stability
	9	Where risk exists	<input type="checkbox"/> Mainly caused by external forces <input checked="" type="checkbox"/> Mainly due to technical factors <input type="checkbox"/> Factors other than the above
	10	Character	<input type="checkbox"/> Project Implementation <input checked="" type="checkbox"/> Operation <input checked="" type="checkbox"/> Due to large-scale external force action <input checked="" type="checkbox"/> Due to long-term use <input type="checkbox"/> Others
	11	Phase of Realization	<input checked="" type="checkbox"/> Affects dam safety <input type="checkbox"/> Affects dam function <input type="checkbox"/> Affect the schedule and costs of the projects <input type="checkbox"/> Basically risk avoidance
	12	Impact if the risk realize	<input type="checkbox"/> Consider mitigation measures as risk avoidance is difficult. <input checked="" type="checkbox"/> Risk retention under certain conditions




Figure -1 Location of seepage under geological map of dam foundation (white circle)

Explanatory Diagram (Schematic Diagram/ Photos, etc)

History	Recognition of risk time	Unrecognized
	When the risk was recognized	Project Phase: Construction
Project Phase	Status of corresponding	Retention
	History of correspond to risks	
Plan		
Design		
Construction	Based on consultant information that water seepage found downstream to the right of the dam above the river trough has a discharge of about 1 l/s and did not increase during construction, so that after being buried by zone 3e embankment material during construction until post impounding.	
Impounding/ Operation/ maintenance	The seepage also flows on the surface and merges with the water whose volume is recorded at the V-notch. The volume recorded at the V-notch in the dry season is about 7.5 l/s and in the rain season 40-50 l/s.	
Investigation /analysis	Investigation/analysis to identify factors, etc.	-
	Research/analysis, etc. to assess impact	-
How to respond to risk	Analysis, etc. to determine the need for and methods of response	-
	Contents of measures (avoidance, reduction, transfer) or retention	Retention
Special Notes	Measures	How to deal with
	Retention (no measures)	Basis for decision
	Availability and method of monitoring	Reason
	Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organizational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.	Expected impact
Applicable standards	Technical issue	Material leaching
	Keywords:	(Describe standards related to geological study, dam design, and countermeasure design.)
References	Meeting Minutes:	-
	Meeting Materials:	Diskusi Teknis Karalloe, Pemantauan Setelah Impounding Bendungan Karalloe, 7 Januari 2022 Pendahuluan-Sertifikasi Izin Operasi, 4 Juni 2023
	Other:	Laporan Akhir (PT. Meitama, 2014); Desain Bendungan Karalloe (Sertifikasi Karalloe,2014)

ID:	30	Name:	Lobak	Dam Type:	Zonal with central core	Dam Height:	58.0 m
Contents of Risk	1	When the risk was identified (date)	-	Construction			
	2	Project phase in which risks were recognized		Dam body			
	3	Location (Structure/Area)		Over topping, reservoir capacity			
	4	Contents of risk		Flash Flooding, sedimentation			
	5	Risk factors		Historical of flash flooding is conveyed when technical discussion			
	6	Events in which risks were recognized		Heavy rain at watershed area			
	7	Conditions/Situation for risk realization		Dam breach due to over topping			
	8	Impact if the risk realize		Design, morphology			
	9	Where risk exists		<input checked="" type="checkbox"/> Mainly caused by external forces			
	10	Character		<input checked="" type="checkbox"/> Mainly due to technical factors			
				<input type="checkbox"/> Factors other than the above			
				<input type="checkbox"/> Project Implementation			
	11	Phase of Realization		<input checked="" type="checkbox"/> Operation			
			<input checked="" type="checkbox"/> Due to large-scale external force action				
			<input checked="" type="checkbox"/> Due to long-term use				
			<input type="checkbox"/> Others				
12	Impact if the risk realize		<input checked="" type="checkbox"/> Affects dam safety				
			<input checked="" type="checkbox"/> Affects dam function				
			<input type="checkbox"/> Affect the schedule and costs of the projects				
			<input type="checkbox"/> Basically risk avoidance				
13	Corresponding to risks		<input checked="" type="checkbox"/> Consider mitigation measures as risk avoidance is difficult.				
			<input checked="" type="checkbox"/> Risk retention under certain conditions				
Overview of Causal Relationships							
	<p>Explanatory Diagram (Schematic Diagram/ Photos, etc)</p>						

ID:	30	Name:	Lobak	Dam Type:	Zonal with central core	Dam Height:	58.0 m
History	When the risk was recognized or not in time		-	Project Phase:		Date:	-
	Status of corresponding			History of correspond to risks			
Plan	No information about flashflooding potential						
Design	no data						
Construction	no data						
Impounding	no data						
Operation/ maintenance	-						
Investigation/ analysis	Investigation/analysis to identify factors, etc.		-				
	Research/analysis, etc. to assess impact		-				
Analysis, etc. to determine the need for and methods of expense		-					
Contents of measures (avoidance, reduction, transfer) or retention		-	Retention				
How to respond to risk	Measures		How to deal with	Early warning system			
	Retention (no measures)		Basis for decision	Climate condition			
	Reason		Expected impact				
	Availability and method of monitoring						
Availability and method of information sharing							
Challenges: 1) Technical issues, 2) Constraints in project implementation requirements (Construction time, costs, etc.), 3) Constraints in dam operation, 4) Issues due to human and organisational factors, results of risk response - 5) Impact on processes, costs, etc., 6) Reflection points (room for improvement of risk management methods), etc.		Technical issue					
Special Notes		<p>1. Should be able to use an early warning system as was done in previous studies to minimize the impact of flash floods.</p> <p>2. Response to flooding if using the model will take time. The guideline should be able to provide that the Dam Management Unit can hold to respond to future floods</p>					
Applicable standards		(Describe standards related to geological study, dam design, and countermeasures design.)					
Keywords							
Meeting Minutes:		Risalah Diskusi Teknis Pembahasan Kesiapan Pengisian Awal Bendungan Lobak, 11 Agustus 2023					
Meeting Materials:		Pembahasan Kesiapan Pengisian Awal, 11 Agustus 2023					
Other:		Laporan Akhir, Perencanaan DD Bendungan Lobak, 2007 Laporan Akhir, Serifikast Bendungan Lobak, PT. Indrakarya, Desember, 2014					