

**Appendix I-18 Construction Cost for Quiula Power Station*****I. Summary of Construction Cost for Quiula Power Station***

Unit: US\$

<i>Work Item</i>	<i>Construction Cost</i>	<i>Remarks</i>
<b><i>1. Preliminary Works</i></b>	<b>16,482</b>	
(1) Access Road	7,053	
(2) Facilities for Construction Office	3,677	Cost of Civil Works x 0.05
(3) Transportation cost	5,752	492.55ton x \$11.68/ton
<b><i>2. Cost for Environmental Measures</i></b>	<b>735</b>	Cost of Civil Works x 0.01
<b><i>3. Civil Works</i></b>	<b>73,555</b>	
(1) Weir	2,221	
(2) Intake	7,177	
(3) Settling Basin	7,465	
(4) Headrace	4,299	
(5) Head Tank	14,950	
(6) Penstock & Spillway Channel	16,810	
(7) Power House	17,650	
(8) Outlet	2,983	
(9) Miscellaneous Work	0	
<b><i>4. Hydraulic Equipment</i></b>	<b>46,900</b>	
(1) Gate & Screen	4,909	
(2) Penstock	0	
(3) PVC (φ600)	26,851	
(4) PVC (φ315)	7,381	
(5) Others	7,759	
<b><i>5. Electrical Equipment</i></b>	<b>53,900</b>	
<b><i>6. Direct Cost</i></b>	<b>191,572</b>	1.+2.+3.+4.+5.
<b><i>7. Engineering Cost</i></b>	<b>19,157</b>	6. x 0.1: Detailed Design and Supervision
<b><i>8. Contingent Budget</i></b>	<b>18,271</b>	6. x 0.095
<b><i>9. IGV</i></b>	<b>43,510</b>	19.00%
<b><i>10. Total Cost</i></b>	<b>272,510</b>	

**II. Detailed Statement of Transportation Cost for Quiula Power Station**

<i>Items</i>	<i>Unit</i>	<i>Quantity</i>	<i>Remarks</i>
<b>(1) Wier</b>		<b>17.05</b>	
a. Cements	ton	3.57	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		13.24	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		0.23	
<b>(2) Intake</b>		<b>65.27</b>	
a. Gate	ton	0.37	
b. Screen		0.18	
c. Cements		13.48	Cement: 0.27ton per concrete 1m <sup>3</sup>
d. Coarse aggregate		49.93	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
e. Reinforcement Bars		1.30	
<b>(3) Settling Basin</b>		<b>50.40</b>	
a. Cements	ton	10.16	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		37.64	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		2.59	
<b>(4) Headrace</b>		<b>5.99</b>	
a. PVC (φ600)	ton	5.99	Weight: 450m x 79.8kg/6m
<b>(5) Head Tank</b>		<b>82.50</b>	
a. Cements	ton	16.86	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		62.45	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		3.19	
<b>(6) Penstock &amp; Spillway Channel</b>		<b>154.84</b>	
a. Penstock Steel (φ300)	ton	0.00	
b. Penstock PVC (φ315)		3.48	Weight: 170m x 122.833kg/6m
c. Cements		32.18	Cement: 0.27ton per concrete 1m <sup>3</sup>
d. Coarse aggregate		119.18	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
e. Reinforcement Bars		0.00	
<b>(7) Power House</b>		<b>104.83</b>	
a. Cements	ton	21.33	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		78.99	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		4.52	
<b>(8) Outlet</b>		<b>11.68</b>	
a. Cements	ton	2.27	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		8.39	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		1.02	
<b>(9) Subtotal</b>		<b>492.55</b>	
<b>(10) Transportation Cost</b>		<b>5,753</b>	(9) x \$11.68/ton

**III. Detailed Statement of Civil Works Cost for Quiula Power Station**

Unit: US\$

<b>Work Items</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Quantity</b>	<b>Cost</b>	<b>Remarks</b>
<b>(1) Wier</b>				<b>2,221</b>	
a. Excavation	m <sup>3</sup>	5.53	67.0	370	
b. Concrete	m <sup>3</sup>	93.05	13.2	1,231	
c. Reinforcement Bars	ton	1,070.00	0.2	250	
d. Others	-			370	(a+b+c) x 0.2 (including coffer dam construction, etc.)
<b>(2) Intake</b>				<b>7,177</b>	
a. Excavation	m <sup>3</sup>	5.53	37.0	204	
b. Concrete	m <sup>3</sup>	93.05	49.9	4,645	
c. Reinforcement Bars	ton	1,070.00	1.3	1,392	
d. Others	-			936	(a+b+c) x 0.15 (including coffer work, etc.)
<b>(3) Settling Basin</b>				<b>7,465</b>	
a. Excavation	m <sup>3</sup>	5.53	92.5	511	
b. Concrete	m <sup>3</sup>	93.05	37.6	3,502	
c. Reinforcement Bars	ton	1,070.00	2.6	2,774	
d. Others	-			678	(a+b+c) x 0.10 (including other works)
<b>(4) Headrace</b>				<b>4,299</b>	
a. Excavation	m <sup>3</sup>	5.53	648.0	3,583	
b. Concrete	m <sup>3</sup>	93.05	0.0	0	
c. Reinforcement Bars	ton	1,070.00	0.0	0	
d. Others	-			716	(a+b+c) x 0.20 (including filling works)
<b>(5) Head Tank</b>				<b>14,950</b>	
a. Excavation	m <sup>3</sup>	5.53	264.1	1,460	
b. Concrete	m <sup>3</sup>	93.05	62.5	5,811	
c. Reinforcement Bars	ton	1,070.00	3.2	3,408	
d. Others	-			4,271	(a+b+c) x 0.40 (including gate, screen)
<b>(6) Penstock &amp; Spillway Channel</b>				<b>16,810</b>	
a. Excavation	m <sup>3</sup>	5.53	758.4	4,193	
b. Concrete	m <sup>3</sup>	93.05	119.2	11,089	
c. Reinforcement Bars	ton	1,070.00	0.0	0	
d. Others	-			1,528	(a+b+c) x 0.10 (including filling works)
<b>(7) Power House</b>				<b>17,650</b>	
a. Excavation	m <sup>3</sup>	5.53	251.7	1,391	
b. Concrete	m <sup>3</sup>	93.05	79.0	7,349	
c. Reinforcement Bars	ton	1,070.00	4.5	4,837	
d. Others	-			4,073	(a+b+c) x 0.30 (including drainage work, wooden)
<b>(8) Outlet</b>				<b>2,983</b>	
a. Excavation	m <sup>3</sup>	5.53	131.4	726	
b. Concrete	m <sup>3</sup>	93.05	8.4	780	
c. Reinforcement Bars	ton	1,070.00	1.0	1,088	
d. Others	-			389	(a+b+c) x 0.15 (including coffer work, etc.)
<b>(9) Miscellaneous Work</b>				<b>0</b>	$\Sigma(1)-(8) \times 0.05$ not consider
<b>(10) Subtotal</b>				<b>73,555</b>	

**IV. Detailed Statement of Hydraulic Equipment Cost for Quiula Power Station**

Unit: US\$

<i>Work Items</i>	<i>Unit</i>	<i>Unit Price</i>	<i>Quantity</i>	<i>Cost</i>	<i>Remarks</i>
<b>(1) Weir &amp; Spillway</b>				<b>0</b>	
a. Gate	ton	8,811.04	0.00	0	
<b>(2) Intake</b>				<b>4,909</b>	
a. Gate	ton	8,811.04	0.37	3,288	
b. Screen	ton	8,811.04	0.18	1,621	
<b>(3) Penstock Steel (φ315)</b>	ton	3,100.00	0.00	<b>0</b>	
<b>(4) PVC (φ600) for headrace</b>	m	59.67	450	<b>26,851</b>	
<b>(5) Penstock PVC (φ315) C-10</b>	m	43.42	170	<b>7,381</b>	
<b>(6) Subtotal</b>				<b>39,141</b>	
<b>(7) Others</b>				<b>7,759</b>	19.82%
<b>(8) Total</b>				<b>46,900</b>	

## V. Quantity

### (1) Weir

Excavation:	$V_e =$	$8.69 \times (H_d \times L)^{1.14}$	$=$	<b>67.01</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$8.64 \times (H_d^2 \times L)^{0.726}$	$=$	<b>13.24</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.0274 \times V_c^{0.830}$	$=$	<b>0.23</b>	(ton)
Weight of Gate:	$W_g =$	$0.145 \times Q_f^{0.692}$	$=$	<b>0.00</b>	(ton) (unconsidered)

Where,

$H_d$ :	Height of Dam =	<b>0.30</b>	(m)
$L$ :	Length of Dam =	<b>20.00</b>	(m)

### (2) Intake

Excavation:	$V_e =$	$171 \times (R \times Q)^{0.666}$	$=$	<b>37.02</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$147 \times (R \times Q)^{0.470}$	$=$	<b>49.93</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.0145 \times V_c^{1.15}$	$=$	<b>1.30</b>	(ton)
Weight of Gate:	$W_g =$	$1.27 \times (R \times Q)^{0.533}$	$=$	<b>0.37</b>	(ton)
Weight of Screen:	$W_s =$	$0.701 \times (R \times Q)^{0.582}$	$=$	<b>0.18</b>	(ton)

Where,

$D$ :	Diameter of Waterway =	<b>1.00</b>	(m)		
$R$ :	Radius of Waterway =	<b>0.50</b>	(m)	$D/2$	Assumption; Waterway Gradient = 1/1,000
$Q$ :	Maximum Discharge =	<b>0.201</b>	(m <sup>3</sup> /s)		

### (3) Settling Basin

Excavation:	$V_e =$	$515 \times Q^{1.07}$	$=$	<b>92.52</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$169 \times Q^{0.936}$	$=$	<b>37.64</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.120 \times V_c^{0.847}$	$=$	<b>2.59</b>	(ton)
Weight of Gate:	$W_g =$	$0.910 \times Q^{0.613}$	$=$	<b>0.34</b>	(ton)
Weight of Screen:	$W_s =$	$0.879 \times Q^{0.785}$	$=$	<b>0.25</b>	(ton)

Where,

$Q$ :	Maximum Discharge =	<b>0.201</b>	(m <sup>3</sup> /s)
-------	---------------------	--------------	---------------------

### (4) Headrace

In the case of PVC $\phi$ 600:

Excavation:	$V_e = B \times H \times L$	$=$	<b>648.00</b>	(m <sup>3</sup> )
Concrete:	$V_c = ((H \times t \times 2) + (B + 2t) \times t) \times L$	$=$	-	(m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.577 \times (V_c/L)^{0.888} \times L$	$=$	-	(ton)

Where,

$Q$ :	Maximum Discharge =	<b>0.201</b>	(m <sup>3</sup> /s)	
$L$ :	Length of Channel =	<b>450.00</b>	(m)	
$B$ :	Width of Channel =	<b>1.20</b>	(m)	for excavation (2D from RIBLOC Brochure)
$H$ :	Height of Channel =	<b>1.20</b>	(m)	for excavation (2D from RIBLOC Brochure)
$t$ :	Thickness of Concrete =	-	(m)	

### (5) Head Tank

Excavation:	$V_e =$	$808 \times Q^{0.697}$	$=$	<b>264.08</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$197 \times Q^{0.716}$	$=$	<b>62.45</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.051 \times V_c$	$=$	<b>3.19</b>	(ton)

Where,

$Q$ :	Maximum Discharge =	<b>0.201</b>	(m <sup>3</sup> /s)
-------	---------------------	--------------	---------------------

**(6) Penstock & Spillway Channel**

**Penstock (Steel)φ315:**

Excavation:	$V_{e1} = 10.9 \times D_m^{1.33} \times L$	=	0.00 (m <sup>3</sup> )
Concrete:	$V_{c1} = 2.14 \times D_m^{1.68} \times L$	=	0.00 (m <sup>3</sup> )
Reinforcement Bars	$W_{r1} = 0.018 \times V_c$	=	0.00 (ton)

Where,

$D_m$ : v.g. Diameter of Penstock =	0.00 (m)
L: Length of Penstock =	0.00 (m)

Weight of Penstock	$W_{p1} = 7.85 \times \pi \times D_m \times t_m \times 10^{-3} \times 1.15 \times L$	=	0.00 (ton)
Thickness of Penstock:	$t_m = 0.0362 \times H \times D_m + 2$	=	2.00 (mm)

Where,

$W_{p1}$ : Weight of Penstock	0.00 (ton)	(Tensile allowable Stress: 1,150 kgf/cm <sup>2</sup> )
$t_m$ : Thickness of Penstock	2.00 (mm)	
$D_m$ : v.g. Diameter of Penstock =	0.00 (m)	
H: Design Head =	78.00 (m)	(Intake Water Level - Tailrace Water Level)
L: Length of Penstock =	0.00 (m)	

**Penstock (PVC)φ315:**

Excavation:	$V_e = B \times H \times L$	=	143.89 (m <sup>3</sup> )
-------------	-----------------------------	---	--------------------------

Where,

Q: Maximum Discharge =	0.201 (m <sup>3</sup> /s)	
L: Length of Channel =	170.00 (m)	
B: Width of Channel =	0.92 (m)	from TUBOPLAST Brochure
H: Height of Channel =	0.92 (m)	from TUBOPLAST Brochure

**Spillway Channel:**

	$(B \times H)^{0.5} = 1.09 \times Q^{0.379}$	=	0.59
Excavation:	$V_e = 6.22 \times ((B \times H)^{0.5})^{1.04} \times L$	=	614.48 (m <sup>3</sup> )
Concrete:	$V_c = H \times t \times 2 + (B + 2t) \times L$	=	119.18 (m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.577 \times (V_c/L)^{0.888} \times L$	=	0.00 (ton)

Where,

Q: Maximum Discharge =	0.201 (m <sup>3</sup> /s)
L: Length of Channel =	170.00 (m)
B: Width of Channel =	0.40 (m)
H: Height of Channel =	0.60 (m)
t: Thickness of Concrete =	0.15 (m)

**Total Quantity of Penstock and Spillway Channel:**

Excavation:	$V_e = V_{e1} + V_{e2}$	=	758.37 (m <sup>3</sup> )
Concrete:	$V_c = V_{c1} + V_{c2}$	=	119.18 (m <sup>3</sup> )
Reinforcement Bars	$W_r = W_{r1} + W_{r2}$	=	0.00 (ton)
Weight of Penstock	$W_p = W_{p1}$	=	0.00 (ton)

**(7) Power House**

Excavation:	$V_e = 97.8 \times (Q \times H_e^{2/3} \times n^{1/2})^{0.727}$	=	251.65 (m <sup>3</sup> )
Concrete:	$V_c = 28.1 \times (Q \times H_e^{2/3} \times n^{1/2})^{0.795}$	=	78.99 (m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.046 \times V_c^{1.05}$	=	4.52 (ton)

Where,

Q: Maximum Discharge =	0.201 (m <sup>3</sup> /s)
$H_e$ : Effective Head =	78.00 (m)
n: quantity Unit of Turbine =	1.00

**(8) Outlet**

Excavation:	$V_e = 395 \times (R \times Q)^{0.479}$	=	131.41 (m <sup>3</sup> )
Concrete:	$V_c = 40.4 \times (R \times Q)^{0.684}$	=	8.39 (m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.278 \times V_c^{0.610}$	=	1.02 (ton)

Where,

D: Diameter of Waterway =	1.00 (m)	
R: Radius of Waterway =	0.50 (m)	D/2
Q: Maximum Discharge =	0.201 (m <sup>3</sup> /s)	


<span style="background-color: yellow; border: 1px solid black; display: inline-block; width: 10px; height: 10px;"></span> : Input Cell
<span style="background-color: lightgreen; border: 1px solid black; display: inline-block; width: 10px; height: 10px;"></span> : Calculation Cell
<span style="background-color: lightblue; border: 1px solid black; display: inline-block; width: 10px; height: 10px;"></span> : Reference Cell

**VI. Unit Price**

1USD = **3.00** S/. (as of November, 2007)

<b>(1) Civil Works</b>		
Excavation		
Open	:	<b>5.53</b> (US\$/m <sup>3</sup> ) * (8.70+2.35) x 0.5 = \$5.53/m <sup>3</sup> , from CAPAECO and Fainal study on Omia <Human power and Machine excavation>
Tunnel	:	- (US\$/m <sup>3</sup> )
Concrete		
Open	:	<b>93.05</b> (US\$/m <sup>3</sup> ) * from CAPAECO (average of foundation, wall and structure concrete)
Tunnel	:	- (US\$/m <sup>3</sup> )
Reinforcement Bar	:	<b>1,070.00</b> (US\$/ton) *\$1.07/kg, from CAPAECO
<b>(2) Hydraulic Equipment</b>		
Gate & Screen	:	<b>8,811.04</b> (US\$/ton) * from final study on Omia
Steel Penstock	:	<b>3,100.00</b> (US\$/ton) including installation
PVC (φ600)	:	<b>59.67</b> (US\$/m) RIB LOC for Headrace
PVC (φ315)	:	<b>43.42</b> (US\$/m) TUBOPLAST for Penstock (C-10), The number of joints is 215. This price include joint price. 190m/6m =30 (joint), 30 x \$2.7 =81\$, 81\$/190m =0.43\$/m, 42.99\$/m (PVC) + 0.43\$/m (joint) = 43.42\$/m
<b>(3) Others</b>		
Access Road	:	<b>979.65</b> (US\$/m) Repair Work for Existing Unpaved Road
<b>(4) Transportation Cost</b>		
Lima to the site	:	<b>11.68</b> (US\$/ton) 94 km (road)

# Quiula Map





**Appendix I-19 Construction Cost for Aichiyacu Power Station*****I. Summary of Construction Cost for Aichiyacu Power Station***

Unit: US\$

<i>Work Item</i>	<i>Construction Cost</i>	<i>Remarks</i>
<b><i>1. Preliminary Works</i></b>	<b>58,604</b>	
(1) Access Road	0	
(2) Facilities for Construction Office	3,058	Cost of Civil Works x 0.05
(3) Transportation cost	55,546	463.70ton x \$119.79/ton
<b><i>2. Cost for Environmental Measures</i></b>	<b>611</b>	Cost of Civil Works x 0.01
<b><i>3. Civil Works</i></b>	<b>61,171</b>	
(1) Weir	2,221	
(2) Intake	3,347	
(3) Settling Basin	3,487	
(4) Headrace	5,574	
(5) Head Tank	8,089	
(6) Penstock & Spillway Channel	30,349	
(7) Power House	6,744	
(8) Outlet	1,360	
(9) Miscellaneous Work	0	
<b><i>4. Hydraulic Equipment</i></b>	<b>58,200</b>	
(1) Gate & Screen	2,092	
(2) Penstock	0	
(3) PVC (φ500)	35,002	
(4) PVC (φ200)	11,464	
(5) Others	9,642	
<b><i>5. Electrical Equipment</i></b>	<b>24,800</b>	
<b><i>6. Direct Cost</i></b>	<b>203,386</b>	1.+2.+3.+4.+5.
<b><i>7. Engineering Cost</i></b>	<b>20,339</b>	6. x 0.1: Detailed Design and Supervision
<b><i>8. Contingent Budget</i></b>	<b>20,275</b>	6. x 0.100
<b><i>9. IGV</i></b>	<b>46,360</b>	19.00%
<b><i>10. Total Cost</i></b>	<b>290,360</b>	

**II. Detailed Statement of Transportation Cost for Aichiyacu Power Station**

<i>Items</i>	<i>Unit</i>	<i>Quantity</i>	<i>Remarks</i>
<b>(1) Wier</b>		<b>17.05</b>	
a. Cements	ton	3.57	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		13.24	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		0.23	
<b>(2) Intake</b>		<b>31.35</b>	
a. Gate	ton	0.16	
b. Screen		0.07	
c. Cements		6.49	Cement: 0.27ton per concrete 1m <sup>3</sup>
d. Coarse aggregate		24.05	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
e. Reinforcement Bars		0.56	
<b>(3) Settling Basin</b>		<b>22.67</b>	
a. Cements	ton	4.54	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		16.82	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		1.31	
<b>(4) Headrace</b>		<b>7.21</b>	
a. PVC (φ500)	ton	7.21	Weight: 840m x 51.522kg/6m
<b>(5) Head Tank</b>		<b>44.55</b>	
a. Cements	ton	9.11	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		33.72	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		1.72	
<b>(6) Penstock &amp; Spillway Channel</b>		<b>296.35</b>	
a. Penstock Steel (φ200)	ton	0.00	
b. Penstock PVC (φ200)		2.75	Weight: 330m x 50.000kg/6m
c. Cements		62.42	Cement: 0.27ton per concrete 1m <sup>3</sup>
d. Coarse aggregate		231.18	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
e. Reinforcement Bars		0.00	
<b>(7) Power House</b>		<b>40.31</b>	
a. Cements	ton	8.22	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		30.43	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		1.66	
<b>(8) Outlet</b>		<b>4.21</b>	
a. Cements	ton	0.78	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		2.90	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		0.53	
<b>(9) Subtotal</b>		<b>463.70</b>	
<b>(10) Transportation Cost</b>		<b>55,546</b>	(9) x \$119.79/ton

**III. Detailed Statement of Civil Works Cost for Aichiyacu Power Station**

Unit: US\$

<b>Work Items</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Quantity</b>	<b>Cost</b>	<b>Remarks</b>
<b>(1) Wier</b>				<b>2,221</b>	
a. Excavation	m <sup>3</sup>	5.53	67.0	370	
b. Concrete	m <sup>3</sup>	93.05	13.2	1,231	
c. Reinforcement Bars	ton	1,070.00	0.2	250	
d. Others	-			370	(a+b+c) x 0.2 (including coffer dam construction, etc.)
<b>(2) Intake</b>				<b>3,347</b>	
a. Excavation	m <sup>3</sup>	5.53	13.2	72	
b. Concrete	m <sup>3</sup>	93.05	24.1	2,238	
c. Reinforcement Bars	ton	1,070.00	0.6	601	
d. Others	-			436	(a+b+c) x 0.15 (including coffer work, etc.)
<b>(3) Settling Basin</b>				<b>3,487</b>	
a. Excavation	m <sup>3</sup>	5.53	36.8	203	
b. Concrete	m <sup>3</sup>	93.05	16.8	1,565	
c. Reinforcement Bars	ton	1,070.00	1.3	1,402	
d. Others	-			317	(a+b+c) x 0.10 (including other works)
<b>(4) Headrace</b>				<b>5,574</b>	
a. Excavation	m <sup>3</sup>	5.53	840.0	4,645	
b. Concrete	m <sup>3</sup>	93.05	0.0	0	
c. Reinforcement Bars	ton	1,070.00	0.0	0	
d. Others	-			929	(a+b+c) x 0.20 (including filling works)
<b>(5) Head Tank</b>				<b>8,089</b>	
a. Excavation	m <sup>3</sup>	5.53	144.9	801	
b. Concrete	m <sup>3</sup>	93.05	33.7	3,137	
c. Reinforcement Bars	ton	1,070.00	1.7	1,840	
d. Others	-			2,311	(a+b+c) x 0.40 (including gate, screen)
<b>(6) Penstock &amp; Spillway Channel</b>				<b>30,349</b>	
a. Excavation	m <sup>3</sup>	5.53	1099.4	6,079	
b. Concrete	m <sup>3</sup>	93.05	231.2	21,511	
c. Reinforcement Bars	ton	1,070.00	0.0	0	
d. Others	-			2,759	(a+b+c) x 0.10 (including filling works)
<b>(7) Power House</b>				<b>6,744</b>	
a. Excavation	m <sup>3</sup>	5.53	105.2	581	
b. Concrete	m <sup>3</sup>	93.05	30.4	2,831	
c. Reinforcement Bars	ton	1,070.00	1.7	1,776	
d. Others	-			1,556	(a+b+c) x 0.30 (including drainage work, wooden)
<b>(8) Outlet</b>				<b>1,360</b>	
a. Excavation	m <sup>3</sup>	5.53	62.4	345	
b. Concrete	m <sup>3</sup>	93.05	2.9	269	
c. Reinforcement Bars	ton	1,070.00	0.5	569	
d. Others	-			177	(a+b+c) x 0.15 (including coffer work, etc.)
<b>(9) Miscellaneous Work</b>	-			<b>0</b>	Σ(1)-(8) x 0.05 not consider
<b>(10) Subtotal</b>				<b>61,171</b>	

**IV. Detailed Statement of Hydraulic Equipment Cost for Aichiyacu Power Station**

Unit: US\$

<b>Work Items</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Quantity</b>	<b>Cost</b>	<b>Remarks</b>
<b>(1) Weir &amp; Spillway</b>				<b>0</b>	
a. Gate	ton	8,811.04	0.00	0	
<b>(2) Intake</b>				<b>2,092</b>	
a. Gate	ton	8,811.04	0.16	1,436	
b. Screen	ton	8,811.04	0.07	656	
<b>(3) Penstock Steel (φ200)</b>	ton	3,100.00	0.00	<b>0</b>	
<b>(4) PVC (φ500) for headrace</b>	m	41.67	840	<b>35,002</b>	
<b>(5) Penstock PVC (φ200) C-10</b>	m	34.74	330	<b>11,464</b>	
<b>(6) Subtotal</b>				<b>48,558</b>	
<b>(7) Others</b>				<b>9,642</b>	19.86%
<b>(8) Total</b>				<b>58,200</b>	

## V. Quantity

### (1) Weir

Excavation:	$V_e =$	$8.69 \times (H_d \times L)^{1.14}$	$=$	<b>67.01</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$8.64 \times (H_d^2 \times L)^{0.726}$	$=$	<b>13.24</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.0274 \times V_c^{0.830}$	$=$	<b>0.23</b>	(ton)
Weight of Gate:	$W_g =$	$0.145 \times Q_f^{0.692}$	$=$	<b>0.00</b>	(ton) (unconsidered)

Where,

$H_d$ :	Height of Dam =	<b>0.30</b>	(m)
$L$ :	Length of Dam =	<b>20.00</b>	(m)

### (2) Intake

Excavation:	$V_e =$	$171 \times (R \times Q)^{0.666}$	$=$	<b>13.15</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$147 \times (R \times Q)^{0.470}$	$=$	<b>24.05</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.0145 \times V_c^{1.15}$	$=$	<b>0.56</b>	(ton)
Weight of Gate:	$W_g =$	$1.27 \times (R \times Q)^{0.533}$	$=$	<b>0.16</b>	(ton)
Weight of Screen:	$W_s =$	$0.701 \times (R \times Q)^{0.582}$	$=$	<b>0.07</b>	(ton)

Where,

$D$ :	Diameter of Waterway =	<b>0.50</b>	(m)	
$R$ :	Radius of Waterway =	<b>0.25</b>	(m)	$D/2$ Assumption; Waterway Gradient = 1/1,000
$Q$ :	Maximum Discharge =	<b>0.085</b>	(m <sup>3</sup> /s)	

### (3) Settling Basin

Excavation:	$V_e =$	$515 \times Q^{1.07}$	$=$	<b>36.84</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$169 \times Q^{0.936}$	$=$	<b>16.82</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.120 \times V_c^{0.847}$	$=$	<b>1.31</b>	(ton)
Weight of Gate:	$W_g =$	$0.910 \times Q^{0.613}$	$=$	<b>0.20</b>	(ton)
Weight of Screen:	$W_s =$	$0.879 \times Q^{0.785}$	$=$	<b>0.13</b>	(ton)

Where,

$Q$ :	Maximum Discharge =	<b>0.085</b>	(m <sup>3</sup> /s)
-------	---------------------	--------------	---------------------

### (4) Headrace

In the case of PVC $\phi$ 500:

Excavation:	$V_e = B \times H \times L$	$=$	<b>840.00</b>	(m <sup>3</sup> )
Concrete:	$V_c = ((H \times t \times 2) + (B + 2t) \times t) \times L$	$=$	-	(m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.577 \times (V_c/L)^{0.888} \times L$	$=$	-	(ton)

Where,

$Q$ :	Maximum Discharge =	<b>0.085</b>	(m <sup>3</sup> /s)	
$L$ :	Length of Channel =	<b>840.00</b>	(m)	
$B$ :	Width of Channel =	<b>1.00</b>	(m)	for excavation (2D from RIBLOC Brochure)
$H$ :	Height of Channel =	<b>1.00</b>	(m)	for excavation (2D from RIBLOC Brochure)
$t$ :	Thickness of Concrete =	-	(m)	

### (5) Head Tank

Excavation:	$V_e =$	$808 \times Q^{0.697}$	$=$	<b>144.95</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$197 \times Q^{0.716}$	$=$	<b>33.72</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.051 \times V_c$	$=$	<b>1.72</b>	(ton)

Where,

$Q$ :	Maximum Discharge =	<b>0.085</b>	(m <sup>3</sup> /s)
-------	---------------------	--------------	---------------------

**(6) Penstock & Spillway Channel**

**Penstock (Steel)φ200:**

Excavation:	$V_{e1} = 10.9 \times D_m^{1.33} \times L$	=	0.00 (m <sup>3</sup> )
Concrete:	$V_{c1} = 2.14 \times D_m^{1.68} \times L$	=	0.00 (m <sup>3</sup> )
Reinforcement Bars	$W_{r1} = 0.018 \times V_c$	=	0.00 (ton)

Where,

$D_m$ : avg. Diameter of Penstock =	0.00 (m)
L: Length of Penstock =	0.00 (m)

Weight of Penstock	$W_{p1} = 7.85 \times \pi \times D_m \times t_m \times 10^{-3} \times 1.15 \times L$	=	0.00 (ton)
Thickness of Penstock:	$t_m = 0.0362 \times H \times D_m + 2$	=	2.00 (mm)

Where,

$W_{p1}$ : Weight of Penstock	0.00 (ton)	(Tensile allowable Stress: 1,150 kgf/cm <sup>2</sup> )
$t_m$ : Thickness of Penstock	2.00 (mm)	
$D_m$ : avg. Diameter of Penstock =	0.00 (m)	
H: Design Head =	46.90 (m)	(Intake Water Level - Tailrace Water Level)
L: Length of Penstock =	0.00 (m)	

**Penstock (PVC)φ200:**

Excavation:	$V_e = B \times H \times L$	=	249.78 (m <sup>3</sup> )
-------------	-----------------------------	---	--------------------------

Where,

Q: Maximum Discharge =	0.085 (m <sup>3</sup> /s)	
L: Length of Channel =	330.00 (m)	
B: Width of Channel =	0.87 (m)	from TUBOPLAST Brochure
H: Height of Channel =	0.87 (m)	from TUBOPLAST Brochure

**Spillway Channel:**

	$(B \times H)^{0.5} = 1.09 \times Q^{0.379}$	=	0.43
Excavation:	$V_e = 6.22 \times ((B \times H)^{0.5})^{1.04} \times L$	=	849.66 (m <sup>3</sup> )
Concrete:	$V_c = H \times t \times 2 + (B + 2t) \times L$	=	231.18 (m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.577 \times (V_c/L)^{0.888} \times L$	=	0.00 (ton)

Where,

Q: Maximum Discharge =	0.085 (m <sup>3</sup> /s)
L: Length of Channel =	330.00 (m)
B: Width of Channel =	0.40 (m)
H: Height of Channel =	0.60 (m)
t: Thickness of Concrete =	0.15 (m)

**Total Quantity of Penstock and Spillway Channel:**

Excavation:	$V_e = V_{e1} + V_{e2}$	=	1,099.44 (m <sup>3</sup> )
Concrete:	$V_c = V_{c1} + V_{c2}$	=	231.18 (m <sup>3</sup> )
Reinforcement Bars	$W_r = W_{r1} + W_{r2}$	=	0.00 (ton)
Weight of Penstock	$W_p = W_{p1}$	=	0.00 (ton)

**(7) Power House**

Excavation:	$V_e = 97.8 \times (Q \times H e^{2/3} \times n^{1/2})^{0.727}$	=	105.19 (m <sup>3</sup> )
Concrete:	$V_c = 28.1 \times (Q \times H e^{2/3} \times n^{1/2})^{0.795}$	=	30.43 (m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.046 \times V_c^{1.05}$	=	1.66 (ton)

Where,

Q: Maximum Discharge =	0.085 (m <sup>3</sup> /s)
He: Effective Head =	46.90 (m)
n: quantity Unit of Turbine =	1.00

**(8) Outlet**

Excavation:	$V_e = 395 \times (R \times Q)^{0.479}$	=	62.43 (m <sup>3</sup> )
Concrete:	$V_c = 40.4 \times (R \times Q)^{0.684}$	=	2.90 (m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.278 \times V_c^{0.610}$	=	0.53 (ton)

Where,

D: Diameter of Waterway =	0.50 (m)	
R: Radius of Waterway =	0.25 (m)	D/2
Q: Maximum Discharge =	0.085 (m <sup>3</sup> /s)	

<span style="background-color: yellow; border: 1px solid black; display: inline-block; width: 10px; height: 10px;"></span>	: Input Cell
<span style="background-color: lightgreen; border: 1px solid black; display: inline-block; width: 10px; height: 10px;"></span>	: Calculation Cell
<span style="background-color: lightpurple; border: 1px solid black; display: inline-block; width: 10px; height: 10px;"></span>	: Reference Cell

**VI. Unit Price**

1USD = 3.00 S/. (as of November, 2007)

<b>(1) Civil Works</b>		
Excavation		
Open	: 5.53 (US\$/m <sup>3</sup> )	* (8.70+2.35) x 0.5 = \$5.53/m <sup>3</sup> , from CAPAECO and Fainal study on Omia <Human power and Machine excavation>
Tunnel	: - (US\$/m <sup>3</sup> )	
Concrete		
Open	: 93.05 (US\$/m <sup>3</sup> )	* from CAPAECO (average of foundation, wall and structure concrete)
Tunnel	: - (US\$/m <sup>3</sup> )	
Reinforcement Bar	: 1,070.00 (US\$/ton)	*\$1.07/kg, from CAPAECO
<b>(2) Hydraulic Equipment</b>		
Gate & Screen	: 8,811.04 (US\$/ton)	* from final study on Omia
Steel Penstock	: 3,100.00 (US\$/ton)	including installation
PVC (φ500)	41.67 (US\$/m)	RIB LOC for Headrace
PVC (φ200)	: 34.74 (US\$/m)	80% of TUBOPLAST( φ 315) for Penstock (C-10) = 43.42 x 0.8 = 34.74
<b>(3) Others</b>		
Access Road	: - (US\$/m)	-
<b>(4) Transportation Cost</b>		
Chachapoyas to the site	: 119.79 (US\$/ton)	367 km (road) + 117km (river) = 21.12 + 98.67 = 119.79 US\$/ton

# Aichiyacu Map



POTENCIA :	30 kW
CAUDAL :	0.085 m <sup>3</sup> /s
VIVIENDAS :	190
ALTITUD BOCATOMA :	350 m.s.n.m
ALTITUD CASA DE MAQUINAS :	300 m.s.n.m
ALTURA BRUTA :	50 m
LONGITUD CANAL :	0.84 km
LONGITUD TUBERIA DE PRESION :	0.33 km
DATOS CUENCA :	AREA 820.4 km <sup>2</sup>
	PERIMETRO 157.7 km

**LEYENDA**

- BOCATOMA
- CASA DE MAQUINAS
- LOCALIDADES
- CANAL
- TUBERIA DE PRESION
- RED EN MEDIA TENSION
- VIA ASFALTADA
- VIA AFIRMADA
- VIA TROCHA
- RIO
- CURVAS DE NIVEL (msnm)
- NEVADOS
- LIMITE DEPARTAMENTAL
- LIMITE PROVINCIAL
- LIMITE DISTRITAL
- LAGOS
- ISLAS
- CUENCA

ESCALA GRAFICA  
2.5 1.25 0 1.25 2.5 km

Nº	FECHA	REVISIONES	REV.	APROB.

**MINISTERIO DE ENERGIA Y MINAS**  
 DIRECCION EJECUTIVA DE PROYECTOS

DISEÑADO: N.A.S.    DIBUJADO: N.A.S.    REVISADO: H.S.S.    APROBADO: R.A.A.    FECHA: OCT 2007

**PROYECTO C.H. AICHYACU**  
 TITULO:  
**UBICACION DEL AREA DEL PROYECTO**

PROYECTO Nº:	UBICACION
ESCALA:	DEPARTAMENTO: LORETO
1 : 200 000	PROVINCIA: VARIOS
HOJA:	DISTRITO: VARIOS
1/1	PLANO Nº:
FORMATO: A-3	



## Appendix I-20 Construction Cost for Balsapuerto Power Station (in the case of PVC for Headrace)

### I. Summary of Construction Cost for Balsapuerto Power Station

Unit: US\$

<i>Work Item</i>	<i>Construction Cost</i>	<i>Remarks</i>
<b>1. Preliminary Works</b>	<b>123,973</b>	
(1) Service Road	65,597	
(2) Facilities for Construction Office	4,199	Cost of Civil Works x 0.05
(3) Transportation cost	54,177	Tarapoto to the site, 410ton x \$132/ton
<b>2. Cost for Environmental Measures</b>	<b>839</b>	Cost of Civil Works x 0.01
<b>3. Civil Works</b>	<b>83,995</b>	
(1) Weir	3,248	
(2) Intake	4,919	
(3) Settling Basin	3,811	
(4) Headrace	28,563	
(5) Head Tank	9,109	
(6) Penstock & Spillway Channel	19,551	
(7) Power House	12,483	
(8) Outlet	2,311	
(9) Miscellaneous Work	0	
<b>4. Hydraulic Equipment</b>	<b>150,000</b>	
(1) Gate & Screen	3,158	
(2) Penstock	1,751	
(3) PVC (φ630)	113,373	
(4) PVC (φ315)	6,816	
(5) Others	24,902	
<b>5. Electrical Equipment</b>	<b>57,800</b>	
<b>6. Direct Cost</b>	<b>416,607</b>	1.+2.+3.+4.+5.
<b>7. Engineering Cost</b>	<b>41,661</b>	6. x 0.1: Detailed Design and Supervision
<b>8. Contingent Budget</b>	<b>40,732</b>	6. x 0.098
<b>9. IGV</b>	<b>94,810</b>	19.00%
<b>10. Total Cost</b>	<b>593,810</b>	

**II. Detailed Statement of Transportation Cost for Balsapuerto Power Station**

<i>Items</i>	<i>Unit</i>	<i>Quantity</i>	<i>Remarks</i>
<b>(1) Wier</b>		<b>24.68</b>	
a. Cements	ton	5.18	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		19.18	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		0.32	
<b>(2) Intake</b>		<b>44.67</b>	
a. Gate	ton	0.24	
b. Screen		0.12	
c. Cements		9.24	Cement: 0.27ton per concrete 1m <sup>3</sup>
d. Coarse aggregate		34.22	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
e. Reinforcement Bars		0.84	
<b>(3) Settling Basin</b>		<b>23.91</b>	
a. Cements	ton	4.79	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		17.74	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		1.37	
<b>(4) Headrace</b>		<b>25.27</b>	
a. PVC (φ600)	ton	25.27	Weight: 1,900m x 79.8kg/6m = 17.3ton
<b>(5) Head Tank</b>		<b>46.41</b>	
a. Cements	ton	9.49	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		35.13	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		1.79	
<b>(6) Penstock &amp; Spillway Channel</b>		<b>168.65</b>	
a. Penstock Steel (φ300)	ton	0.57	
b. Penstock PVC (φ315)		3.21	Weight: 157m x 122.833kg/6m = 3.2ton
c. Cements		35.03	Cement: 0.27ton per concrete 1m <sup>3</sup>
d. Coarse aggregate		129.74	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
e. Reinforcement Bars		0.10	
<b>(7) Power House</b>		<b>69.97</b>	
a. Cements	ton	14.25	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		52.76	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		2.96	
<b>(8) Outlet</b>		<b>6.88</b>	
a. Cements	ton	1.31	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		4.84	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		0.73	
<b>(9) Subtotal</b>		<b>410.44</b>	
<b>(10) Transportation Cost</b>		<b>54,177</b>	(9) x \$132/ton: Tarapoto to Balsa Puerto

**III. Detailed Statement of Civil Works Cost for Balsapuerto Power Station**

Unit: US\$

<i>Work Items</i>	<i>Unit</i>	<i>Unit Price</i>	<i>Quantity</i>	<i>Cost</i>	<i>Remarks</i>
<b>(1) Wier</b>				<b>3,248</b>	
a. Excavation	m <sup>3</sup>	8.70	67.0	582	
b. Concrete	m <sup>3</sup>	93.05	19.2	1,784	
c. Reinforcement Bars	ton	1,075.00	0.3	341	
d. Others	-			541	(a+b+c) x 0.2 (including coffer dam construction, etc.)
<b>(2) Intake</b>				<b>4,919</b>	
a. Excavation	m <sup>3</sup>	8.70	21.7	188	
b. Concrete	m <sup>3</sup>	93.05	34.2	3,184	
c. Reinforcement Bars	ton	1,075.00	0.8	906	
d. Others	-			641	(a+b+c) x 0.15 (including coffer work, etc.)
<b>(3) Settling Basin</b>				<b>3,811</b>	
a. Excavation	m <sup>3</sup>	8.70	39.2	340	
b. Concrete	m <sup>3</sup>	93.05	17.7	1,651	
c. Reinforcement Bars	ton	1,075.00	1.4	1,474	
d. Others	-			346	(a+b+c) x 0.10 (including other works)
<b>(4) Headrace</b>				<b>28,563</b>	
a. Excavation	m <sup>3</sup>	8.70	2736.0	23,803	
b. Concrete	m <sup>3</sup>	93.05	0.0	0	
c. Reinforcement Bars	ton	1,075.00	0.0	0	
d. Others	-			4,760	(a+b+c) x 0.20 (including filling works)
<b>(5) Head Tank</b>				<b>9,109</b>	
a. Excavation	m <sup>3</sup>	8.70	150.8	1,312	
b. Concrete	m <sup>3</sup>	93.05	35.1	3,269	
c. Reinforcement Bars	ton	1,075.00	1.8	1,926	
d. Others	-			2,602	(a+b+c) x 0.40 (including gate, screen)
<b>(6) Penstock &amp; Spillway Channel</b>				<b>19,551</b>	
a. Excavation	m <sup>3</sup>	8.70	643.0	5,593	
b. Concrete	m <sup>3</sup>	93.05	129.7	12,072	
c. Reinforcement Bars	ton	1,075.00	0.1	109	
d. Others	-			1,777	(a+b+c) x 0.10 (including filling works)
<b>(7) Power House</b>				<b>12,483</b>	
a. Excavation	m <sup>3</sup>	8.70	174.0	1,513	
b. Concrete	m <sup>3</sup>	93.05	52.8	4,909	
c. Reinforcement Bars	ton	1,075.00	3.0	3,181	
d. Others	-			2,880	(a+b+c) x 0.30 (including drainage work, wooden)
<b>(8) Outlet</b>				<b>2,311</b>	
a. Excavation	m <sup>3</sup>	8.70	89.4	778	
b. Concrete	m <sup>3</sup>	93.05	4.8	450	
c. Reinforcement Bars	ton	1,075.00	0.7	782	
d. Others	-			301	(a+b+c) x 0.15 (including coffer work, etc.)
<b>(9) Miscellaneous Work</b>				<b>0</b>	$\Sigma(1)-(8) \times 0.05$ not consider
<b>(10) Subtotal</b>				<b>83,995</b>	

**IV. Detailed Statement of Hydraulic Equipment Cost for Balsapuerto Power Station**

Unit: US\$

<i>Work Items</i>	<i>Unit</i>	<i>Unit Price</i>	<i>Quantity</i>	<i>Cost</i>	<i>Remarks</i>
<b>(1) Weir &amp; Spillway</b>				<b>0</b>	
a. Gate	ton	8,811.04	0.00	0	
<b>(2) Intake</b>				<b>3,158</b>	
a. Gate	ton	8,811.04	0.24	2,142	
b. Screen	ton	8,811.04	0.12	1,016	
<b>(3) Penstock Steel (φ315)</b>	ton	3,100.00	0.57	<b>1,751</b>	
<b>(4) PVC (φ600) for headrace</b>	m	59.67	1,900	<b>113,373</b>	
<b>(5) Penstock PVC (φ315) C-10</b>	m	43.42	157	<b>6,816</b>	
<b>(6) Subtotal</b>				<b>125,098</b>	
<b>(7) Others</b>				<b>24,902</b>	19.91%
<b>(8) Total</b>				<b>150,000</b>	

## V. Quantity

### (1) Weir

Excavation:	$V_e =$	$8.69 \times (H_d \times L)^{1.14}$	$=$	<b>67.01</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$8.64 \times (H_d^2 \times L)^{0.726}$	$=$	<b>19.18</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.0274 \times V_c^{0.830}$	$=$	<b>0.32</b>	(ton)
Weight of Gate:	$W_g =$	$0.145 \times Q_f^{0.692}$	$=$	<b>0.00</b>	(ton) (unconsidered)

Where,

$H_d$ :	Height of Dam =	<b>0.50</b>	(m)
$L$ :	Length of Dam =	<b>12.00</b>	(m)

### (2) Intake

Excavation:	$V_e =$	$171 \times (R \times Q)^{0.666}$	$=$	<b>21.68</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$147 \times (R \times Q)^{0.470}$	$=$	<b>34.22</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.0145 \times V_c^{1.15}$	$=$	<b>0.84</b>	(ton)
Weight of Gate:	$W_g =$	$1.27 \times (R \times Q)^{0.533}$	$=$	<b>0.24</b>	(ton)
Weight of Screen:	$W_s =$	$0.701 \times (R \times Q)^{0.582}$	$=$	<b>0.12</b>	(ton)

Where,

$D$ :	Diameter of Waterway =	<b>1.00</b>	(m)	
$R$ :	Radius of Waterway =	<b>0.50</b>	(m)	$D/2$
$Q$ :	Maximum Discharge =	<b>0.090</b>	(m <sup>3</sup> /s)	Assumption; Waterway Gradient = 1/1,000

### (3) Settling Basin

Excavation:	$V_e =$	$515 \times Q^{1.07}$	$=$	<b>39.16</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$169 \times Q^{0.936}$	$=$	<b>17.74</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.120 \times V_c^{0.847}$	$=$	<b>1.37</b>	(ton)
Weight of Gate:	$W_g =$	$0.910 \times Q^{0.613}$	$=$	<b>0.21</b>	(ton)
Weight of Screen:	$W_s =$	$0.879 \times Q^{0.785}$	$=$	<b>0.13</b>	(ton)

Where,

$Q$ :	Maximum Discharge =	<b>0.090</b>	(m <sup>3</sup> /s)
-------	---------------------	--------------	---------------------

### (4) Headrace

In the case of PVC $\phi$ 600:

Excavation:	$V_e = B \times H \times L$	$=$	<b>2,736.00</b>	(m <sup>3</sup> )
Concrete:	$V_c = ((H \times t \times 2) + (B + 2t) \times t) \times L$	$=$	<b>-</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.577 \times (V_c/L)^{0.888} \times L$	$=$	<b>-</b>	(ton)

Where,

$Q$ :	Maximum Discharge =	<b>0.090</b>	(m <sup>3</sup> /s)	
$L$ :	Length of Channel =	<b>1,900.00</b>	(m)	
$B$ :	Width of Channel =	<b>1.20</b>	(m)	for excavation (2D from RIBLOC Brochure)
$H$ :	Height of Channel =	<b>1.20</b>	(m)	for excavation (2D from RIBLOC Brochure)
$t$ :	Thickness of Concrete =	<b>-</b>	(m)	

### (5) Head Tank

Excavation:	$V_e =$	$808 \times Q^{0.697}$	$=$	<b>150.84</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$197 \times Q^{0.716}$	$=$	<b>35.13</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.051 \times V_c$	$=$	<b>1.79</b>	(ton)

Where,

$Q$ :	Maximum Discharge =	<b>0.090</b>	(m <sup>3</sup> /s)
-------	---------------------	--------------	---------------------

**(6) Penstock & Spillway Channel**

**Penstock (Steel)φ315:**

Excavation:	$V_{e1} = 10.9 \times D_m^{1.33} \times L$	=	43.96 (m <sup>3</sup> )
Concrete:	$V_{c1} = 2.14 \times D_m^{1.68} \times L$	=	5.66 (m <sup>3</sup> )
Reinforcement Bars	$W_{r1} = 0.018 \times V_c$	=	0.10 (ton)

Where,

$D_m$ : avg. Diameter of Penstock =	0.30 (m)
L: Length of Penstock =	20.00 (m)

Weight of Penstock	$W_{p1} = 7.85 \times \pi \times D_m \times t_m \times 10^{-3} \times 1.15 \times L$	=	0.57 (ton)
Thickness of Penstock:	$t_m = 0.0362 \times H \times D_m + 2$	=	3.32 (mm)

Where,

$W_{p1}$ : Weight of Penstock	0.57 (ton)	(Tensile allowable Stress: 1,150 kgf/cm <sup>2</sup> )
$t_m$ : Thickness of Penstock	3.32 (mm)	
$D_m$ : avg. Diameter of Penstock =	0.30 (m)	
H: Design Head =	121.60 (m)	(Intake Water Level - Tailrace Water Level)
L: Length of Penstock =	20.00 (m)	

**Penstock (PVC)φ315**

Excavation:	$V_e = B \times H \times L$	=	132.88 (m <sup>3</sup> )
-------------	-----------------------------	---	--------------------------

Where,

Q: Maximum Discharge =	0.090 (m <sup>3</sup> /s)	
L: Length of Channel =	157.00 (m)	
B: Width of Channel =	0.92 (m)	from TUBOPLAST Brochure
H: Height of Channel =	0.92 (m)	from TUBOPLAST Brochure

**Spillway Channel:**

	$(B \times H)^{0.5} = 1.09 \times Q^{0.379}$	=	0.44
Excavation:	$V_e = 6.22 \times ((B \times H)^{0.5})^{1.04} \times L$	=	466.11 (m <sup>3</sup> )
Concrete:	$V_c = H \times t \times 2 + (B + 2t) \times L$	=	124.08 (m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.577 \times (V_c/L)^{0.888} \times L$	=	0.00 (ton)

Where,

Q: Maximum Discharge =	0.090 (m <sup>3</sup> /s)
L: Length of Channel =	177.00 (m)
B: Width of Channel =	0.40 (m)
H: Height of Channel =	0.60 (m)
t: Thickness of Concrete =	0.15 (m)

**Total Quantity of Penstock and Spillway Channel:**

Excavation:	$V_e = V_{e1} + V_{e2}$	=	642.96 (m <sup>3</sup> )
Concrete:	$V_c = V_{c1} + V_{c2}$	=	129.74 (m <sup>3</sup> )
Reinforcement Bars	$W_r = W_{r1} + W_{r2}$	=	0.10 (ton)
Weight of Penstock	$W_p = W_{p1}$	=	0.57 (ton)

**(7) Power House**

Excavation:	$V_e = 97.8 \times (Q \times H_e^{2/3} \times n^{1/2})^{0.727}$	=	174.01 (m <sup>3</sup> )
Concrete:	$V_c = 28.1 \times (Q \times H_e^{2/3} \times n^{1/2})^{0.795}$	=	52.76 (m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.046 \times V_c^{1.05}$	=	2.96 (ton)

Where,

Q: Maximum Discharge =	0.090 (m <sup>3</sup> /s)
He: Effective Head =	121.60 (m)
n: quantity Unit of Turbine =	1.00

**(8) Outlet**

Excavation:	$V_e = 395 \times (R \times Q)^{0.479}$	=	89.43 (m <sup>3</sup> )
Concrete:	$V_c = 40.4 \times (R \times Q)^{0.684}$	=	4.84 (m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.278 \times V_c^{0.610}$	=	0.73 (ton)

Where,

D: Diameter of Waterway =	1.00 (m)	
R: Radius of Waterway =	0.50 (m)	D/2
Q: Maximum Discharge =	0.090 (m <sup>3</sup> /s)	

<span style="background-color: yellow; border: 1px solid black; display: inline-block; width: 15px; height: 10px;"></span>	: Input Cell
<span style="background-color: lightgreen; border: 1px solid black; display: inline-block; width: 15px; height: 10px;"></span>	: Calculation Cell
<span style="background-color: lightpurple; border: 1px solid black; display: inline-block; width: 15px; height: 10px;"></span>	: Reference Cell

**VI. Unit Price**      1USD = **3.00** S/. (as of November, 2007)

<b>(1) Civil Works</b>		
Excavation		
Open	: <b>8.70</b> (US\$/m <sup>3</sup> )	* \$8.70/m <sup>3</sup> , from CAPECO <only Human power excavation>
Tunnel	:      - (US\$/m <sup>3</sup> )	
Concrete		
Open	: <b>93.05</b> (US\$/m <sup>3</sup> )	* from CAPAECO (average of foundation, wall and structure concrete)
Tunnel	:      - (US\$/m <sup>3</sup> )	
Reinforcement Bar	: <b>1,075.00</b> (US\$/ton)	* \$1.075/kg, from CAPAECO
<b>(2) Hydraulic Equipment</b>		
Gate & Screen	: <b>8,811.04</b> (US\$/ton)	* from final study on Omia
Penstock & Conductor	: <b>3,100.00</b> (US\$/ton)	including installation
PVC (φ600)	: <b>59.67</b> (US\$/m)	RIB LOC for Headrace
PVC (φ315)	: <b>43.42</b> (US\$/m)	TUBOPLAST for Penstock (C-10), The number of joints is 215. This price include joint price. 157m/6m =25 (joint), 25 x \$2.7 =67.5\$, 67.5\$/157m =0.43\$/m, 42.99\$/m (PVC) + 0.43\$/m (joint) = 43.42\$/m
<b>(3) Others</b>		
Access Road (1)	: <b>979.65</b> (US\$/m)	Balsa Puerto - Canoa Puerto
Access Road (2)	: <b>5,877.89</b> (US\$/m)	Canoa Puerto - Powerhouse
Access Road (3)	: <b>2,938.94</b> (US\$/m)	Powerhouse - Intake Site
<b>(4) Transportation Cost</b>		
Tarapoto to the site	: <b>132.00</b> (US\$/ton)	US\$33.33/ton (Tarapoto-Yurimaguas) + US\$98.67/ton (Yurimaguas-Balsa Puerto) =132US\$/ton

(1) Balsapuerto

**TRANSPORTATION COST TO BALSAPUERTO**

truck by 10ton

1ST STAGE: (by road)

LIMA - LAMBAYEQUE - TARAPOTO - YURIMAGUAS - alternative 1	103.05	US\$/TON
LIMA - CAJAMARCA - TARAPOTO - YURIMAGUAS - alternative 2	128.42	US\$/TON
TARAPOTO - YURIMAGUAS - alternative 3	33.33	US\$/TON

2ND STAGE: (by river)

YURIMAGUAS - BALSAPUERTO	98.67	US\$/TON
--------------------------	-------	----------

<b>TOTAL</b>		
FROM LIMA TO BALSAPUERTO	201.72	US\$/TON
FROM TARAPOTO TO BALSAPUERTO	132.00	US\$/TON

**BY ROAD:**

**ALTERNATIVE 1:**

ROUTE	DISTANCE KM	ACCUM. DISTANCE KM	COST S/./ton	ACCUM. COST S/./ton	COST US\$/ton	ACCUM. COST US\$/ton
Lima - Lambayegue	775.64	775.64	128.09	128.09	42.70	42.70
Lambayegue - Tarapoto	889.63	1665.27	146.91	275.00	48.97	91.67
Tarapoto - Yurimaguas	206.90	1872.17	34.16	309.16	11.39	<b>103.05</b>

Source: Ministry of Transport and Communications MTC  
Upgraded up to June 2007

**ALTERNATIVE 2:**

ROUTE	DISTANCE KM	ACCUM. DISTANCE KM	COST S/./ton	ACCUM. COST S/./ton	COST US\$/ton	ACCUM. COST US\$/ton
Lima - Trujillo	557.24	557.24	92.01	92.02	30.67	30.67
Trujillo - Cajamarca	317.87	875.11	52.49	144.51	17.50	48.17
Cajamarca - Chachapoyas	841.35	1716.46	138.94	283.45	46.31	94.48
Chachapoyas - Moyobamba	299.35	2015.81	49.44	332.89	16.48	110.96
Moyobamba - Tarapoto	110.95	2126.76	18.32	351.21	6.11	117.07
Tarapoto - Yurimaguas	206.12	2332.88	34.04	385.25	11.35	<b>128.42</b>

Source: Ministry of Transport and Communications MTC  
Upgraded up to June 2007

**ALTERNATIVE 3:**

ROUTE	DISTANCE KM	ACCUM. DISTANCE KM	COST S/./ton	ACCUM. COST S/./ton	COST US\$/ton	ACCUM. COST US\$/ton
Tarapoto - Yurimaguas	206.12	206.12	100.00	100.00	33.33	<b>33.33</b>

SOURCE: Upner Av- Tours de la selva - Tarapoto Telf. (042) 531489

**BY RIVER:**


ROUTE	DISTANCE KM	ACCUM. DISTANCE KM	COST S/./ton	ACCUM. COST S/./ton	COST US\$/ton	ACCUM. COST US\$/ton
Yurimaguas - Balsapuerto	136.00	136.00	296.00	296.00	98.67	<b>98.67</b>

SOURCE: Agencia Fluvial Dos Mil EIRL - Yurimaguas. Telf. (065) 352174

US\$ 1.00 = S/. 3.00




# Balsapuerto Map



POTENCIA :	80 kW
CAUDAL :	0.100 m <sup>3</sup> /s
VIVIENDAS :	487
ALTITUD BOCATOMA :	425 m.s.n.m
ALTITUD CASA DE MAQUINAS :	300 m.s.n.m
ALTURA BRUTA :	125 m
LONGITUD CANAL :	1.9 km
LONGITUD TUBERIA DE PRESION :	0.54 km
DATOS CUENCA :	AREA 26.5 km <sup>2</sup>
	PERIMETRO 22 km

LEYENDA	
	BOCATOMA
	CASA DE MAQUINAS
	LOCALIDADES
	CANAL
	TUBERIA DE PRESION
	RED EN MEDIA TENSION
	VIA ASFALTADA
	VIA AFIRMADA
	VIA TROCHA
	RIO
	CURVAS DE NIVEL (msnm)
	NEVADOS
	LIMITE DEPARTAMENTAL
	LIMITE PROVINCIAL
	LIMITE DISTRITAL
	LAGOS
	ISLAS
	CUENCA



Nº	FECHA	REVISIONES	REV.	APROB.

**MINISTERIO DE ENERGIA Y MINAS**  
 DIRECCION EJECUTIVA DE PROYECTOS

DISEÑADO: N.A.S.    DIBUJADO: N.A.S.    REVISADO: H.S.S.    APROBADO: R.A.A.    FECHA: FEB 2008

PROYECTO Nº:	UBICACION
ESCALA:	DEPARTAMENTO: LORETO
1 : 100 000	PROVINCIA: VARIOS
HQ/A:	DISTRITO: VARIOS
1/1	PLANO Nº:
FORMATO: A-3	

**PROYECTO C.H. Balsa Puerto**

**UBICACION DEL AREA DEL PROYECTO**

**Appendix I-21 Construction Cost for San Antonio Power Station*****I. Summary of Construction Cost for San Antonio Power Station***

Unit: US\$

<i>Work Item</i>	<i>Construction Cost</i>	<i>Remarks</i>
<b><i>1. Preliminary Works</i></b>	<b>219,084</b>	
(1) Access Road	105,801	
(2) Facilities for Construction Office	7,384	Cost of Civil Works x 0.05
(3) Transportation cost	105,899	1,073.27ton x \$98.67/ton
<b><i>2. Cost for Environmental Measures</i></b>	<b>1,476</b>	Cost of Civil Works x 0.01
<b><i>3. Civil Works</i></b>	<b>147,687</b>	
(1) Weir	2,221	
(2) Intake	7,159	
(3) Settling Basin	7,432	
(4) Headrace	13,855	
(5) Head Tank	14,896	
(6) Penstock & Spillway Channel	74,690	
(7) Power House	24,458	
(8) Outlet	2,976	
(9) Miscellaneous Work	0	
<b><i>4. Hydraulic Equipment</i></b>	<b>157,400</b>	
(1) Gate & Screen	4,896	
(2) Penstock	20,717	
(3) PVC (φ600)	86,521	
(4) PVC (φ315)	19,104	
(5) Others	26,162	
<b><i>5. Electrical Equipment</i></b>	<b>107,800</b>	
<b><i>6. Direct Cost</i></b>	<b>633,447</b>	1.+2.+3.+4.+5.
<b><i>7. Engineering Cost</i></b>	<b>63,345</b>	6. x 0.1: Detailed Design and Supervision
<b><i>8. Contingent Budget</i></b>	<b>63,208</b>	6. x 0.100
<b><i>9. IGV</i></b>	<b>144,400</b>	19.00%
<b><i>10. Total Cost</i></b>	<b>904,400</b>	

**II. Detailed Statement of Transportation Cost for San Antonio Power Station**

<i>Items</i>	<i>Unit</i>	<i>Quantity</i>	<i>Remarks</i>
<b>(1) Wier</b>		<b>17.05</b>	
a. Cements	ton	3.57	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		13.24	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		0.23	
<b>(2) Intake</b>		<b>65.11</b>	
a. Gate	ton	0.37	
b. Screen		0.18	
c. Cements		13.45	Cement: 0.27ton per concrete 1m <sup>3</sup>
d. Coarse aggregate		49.81	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
e. Reinforcement Bars		1.30	
<b>(3) Settling Basin</b>		<b>50.17</b>	
a. Cements	ton	10.12	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		37.47	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		2.58	
<b>(4) Headrace</b>		<b>19.29</b>	
a. PVC (φ600)	ton	19.29	Weight: 1,450m x 79.8kg/6m
<b>(5) Head Tank</b>		<b>82.21</b>	
a. Cements	ton	16.80	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		62.23	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		3.17	
<b>(6) Penstock &amp; Spillway Channel</b>		<b>682.89</b>	
a. Penstock Steel (φ300)	ton	6.68	
b. Penstock PVC (φ315)		9.01	Weight: 440m x 122.833kg/6m
c. Cements		141.61	Cement: 0.27ton per concrete 1m <sup>3</sup>
d. Coarse aggregate		524.47	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
e. Reinforcement Bars		1.12	
<b>(7) Power House</b>		<b>144.93</b>	
a. Cements	ton	29.46	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		109.12	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		6.35	
<b>(8) Outlet</b>		<b>11.64</b>	
a. Cements	ton	2.26	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		8.36	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		1.02	
<b>(9) Subtotal</b>		<b>1,073.27</b>	
<b>(10) Transportation Cost</b>		<b>105,900</b>	(9) x \$98.67/ton

**III. Detailed Statement of Civil Works Cost for San Antonio Power Station**

Unit: US\$

<b>Work Items</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Quantity</b>	<b>Cost</b>	<b>Remarks</b>
<b>(1) Wier</b>				<b>2,221</b>	
a. Excavation	m <sup>3</sup>	5.53	67.0	370	
b. Concrete	m <sup>3</sup>	93.05	13.2	1,231	
c. Reinforcement Bars	ton	1,070.00	0.2	250	
d. Others	-			370	(a+b+c) x 0.2 (including coffer dam construction, etc.)
<b>(2) Intake</b>				<b>7,159</b>	
a. Excavation	m <sup>3</sup>	5.53	36.9	204	
b. Concrete	m <sup>3</sup>	93.05	49.8	4,634	
c. Reinforcement Bars	ton	1,070.00	1.3	1,388	
d. Others	-			933	(a+b+c) x 0.15 (including coffer work, etc.)
<b>(3) Settling Basin</b>				<b>7,432</b>	
a. Excavation	m <sup>3</sup>	5.53	92.0	508	
b. Concrete	m <sup>3</sup>	93.05	37.5	3,486	
c. Reinforcement Bars	ton	1,070.00	2.6	2,763	
d. Others	-			675	(a+b+c) x 0.10 (including other works)
<b>(4) Headrace</b>				<b>13,855</b>	
a. Excavation	m <sup>3</sup>	5.53	2088.0	11,546	
b. Concrete	m <sup>3</sup>	93.05	0.0	0	
c. Reinforcement Bars	ton	1,070.00	0.0	0	
d. Others	-			2,309	(a+b+c) x 0.20 (including filling works)
<b>(5) Head Tank</b>				<b>14,896</b>	
a. Excavation	m <sup>3</sup>	5.53	263.2	1,455	
b. Concrete	m <sup>3</sup>	93.05	62.2	5,790	
c. Reinforcement Bars	ton	1,070.00	3.2	3,395	
d. Others	-			4,256	(a+b+c) x 0.40 (including gate, screen)
<b>(6) Penstock &amp; Spillway Channel</b>				<b>74,690</b>	
a. Excavation	m <sup>3</sup>	5.53	3236.9	17,900	
b. Concrete	m <sup>3</sup>	93.05	524.5	48,801	
c. Reinforcement Bars	ton	1,070.00	1.1	1,199	
d. Others	-			6,790	(a+b+c) x 0.10 (including filling works)
<b>(7) Power House</b>				<b>24,458</b>	
a. Excavation	m <sup>3</sup>	5.53	338.2	1,870	
b. Concrete	m <sup>3</sup>	93.05	109.1	10,153	
c. Reinforcement Bars	ton	1,070.00	6.3	6,791	
d. Others	-			5,644	(a+b+c) x 0.30 (including drainage work, wooden)
<b>(8) Outlet</b>				<b>2,976</b>	
a. Excavation	m <sup>3</sup>	5.53	131.1	724	
b. Concrete	m <sup>3</sup>	93.05	8.4	778	
c. Reinforcement Bars	ton	1,070.00	1.0	1,086	
d. Others	-			388	(a+b+c) x 0.15 (including coffer work, etc.)
<b>(9) Miscellaneous Work</b>	-			<b>0</b>	Σ(1)-(8) x 0.05 not consider
<b>(10) Subtotal</b>				<b>147,687</b>	

**IV. Detailed Statement of Hydraulic Equipment Cost for San Antonio Power Station**

Unit: US\$

<i>Work Items</i>	<i>Unit</i>	<i>Unit Price</i>	<i>Quantity</i>	<i>Cost</i>	<i>Remarks</i>
<b>(1) Weir &amp; Spillway</b>				<b>0</b>	
a. Gate	ton	8,811.04	0.00	0	
<b>(2) Intake</b>				<b>4,896</b>	
a. Gate	ton	8,811.04	0.37	3,279	
b. Screen	ton	8,811.04	0.18	1,617	
<b>(3) Penstock Steel (φ315)</b>	ton	3,100.00	6.68	<b>20,717</b>	
<b>(4) PVC (φ600) for headrace</b>	m	59.67	1,450	<b>86,521</b>	
<b>(5) Penstock PVC (φ315) C-10</b>	m	43.42	440	<b>19,104</b>	
<b>(6) Subtotal</b>				<b>131,238</b>	
<b>(7) Others</b>				<b>26,162</b>	19.93%
<b>(8) Total</b>				<b>157,400</b>	

## V. Quantity

<b>(1) Weir</b>					
Excavation:	$V_e =$	$8.69 \times (H_d \times L)^{1.14}$	$=$	<b>67.01</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$8.64 \times (H_d^2 \times L)^{0.726}$	$=$	<b>13.24</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.0274 \times V_c^{0.830}$	$=$	<b>0.23</b>	(ton)
Weight of Gate:	$W_g =$	$0.145 \times Q_f^{0.692}$	$=$	<b>0.00</b>	(ton) (unconsidered)
Where,					
$H_d$ :	Height of Dam =	<b>0.30</b>	(m)		
L:	Length of Dam =	<b>20.00</b>	(m)		

<b>(2) Intake</b>					
Excavation:	$V_e =$	$171 \times (R \times Q)^{0.666}$	$=$	<b>36.90</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$147 \times (R \times Q)^{0.470}$	$=$	<b>49.81</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.0145 \times V_c^{1.15}$	$=$	<b>1.30</b>	(ton)
Weight of Gate:	$W_g =$	$1.27 \times (R \times Q)^{0.533}$	$=$	<b>0.37</b>	(ton)
Weight of Screen:	$W_s =$	$0.701 \times (R \times Q)^{0.582}$	$=$	<b>0.18</b>	(ton)
Where,					
D:	Diameter of Waterway =	<b>1.00</b>	(m)		
R:	Radius of Waterway =	<b>0.50</b>	(m)	D/2	Assumption; Waterway Gradient = 1/1,000
Q:	Maximum Discharge =	<b>0.200</b>	(m <sup>3</sup> /s)		

<b>(3) Settling Basin</b>					
Excavation:	$V_e =$	$515 \times Q^{1.07}$	$=$	<b>92.03</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$169 \times Q^{0.936}$	$=$	<b>37.47</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.120 \times V_c^{0.847}$	$=$	<b>2.58</b>	(ton)
Weight of Gate:	$W_g =$	$0.910 \times Q^{0.613}$	$=$	<b>0.34</b>	(ton)
Weight of Screen:	$W_s =$	$0.879 \times Q^{0.785}$	$=$	<b>0.25</b>	(ton)
Where,					
Q:	Maximum Discharge =	<b>0.200</b>	(m <sup>3</sup> /s)		

<b>(4) Headrace</b>					
<b>In the case of PVCφ600:</b>					
Excavation:	$V_e = B \times H \times L$		$=$	<b>2,088.00</b>	(m <sup>3</sup> )
Concrete:	$V_c = ((H \times t \times 2) + (B + 2t) \times t) \times L$		$=$	-	(m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.577 \times (V_c/L)^{0.888} \times L$		$=$	-	(ton)
Where,					
Q:	Maximum Discharge =	<b>0.200</b>	(m <sup>3</sup> /s)		
L:	Length of Channel =	<b>1,450.00</b>	(m)		
B:	Width of Channel =	<b>1.20</b>	(m)	for excavation (2D from RIBLOC Brochure)	
H:	Height of Channel =	<b>1.20</b>	(m)	for excavation (2D from RIBLOC Brochure)	
t:	Thickness of Concrete =	-	(m)		

<b>(5) Head Tank</b>					
Excavation:	$V_e =$	$808 \times Q^{0.697}$	$=$	<b>263.17</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$197 \times Q^{0.716}$	$=$	<b>62.23</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.051 \times V_c$	$=$	<b>3.17</b>	(ton)
Where,					
Q:	Maximum Discharge =	<b>0.200</b>	(m <sup>3</sup> /s)		

**(6) Penstock & Spillway Channel**

**Penstock (Steel)φ315:**

Excavation:	$V_{e1} = 10.9 \times D_m^{1.33} \times L$	=	483.53 (m <sup>3</sup> )
Concrete:	$V_{c1} = 2.14 \times D_m^{1.68} \times L$	=	62.29 (m <sup>3</sup> )
Reinforcement Bars	$W_{r1} = 0.018 \times V_c$	=	1.12 (ton)

Where,

$D_m$ : v.g. Diameter of Penstock =	0.30 (m)
L: Length of Penstock =	220.00 (m)

Weight of Penstock	$W_{p1} = 7.85 \times \pi \times D_m \times t_m \times 10^{-3} \times 1.15 \times L$	=	6.68 (ton)
Thickness of Penstock:	$t_m = 0.0362 \times H \times D_m + 2$	=	3.57 (mm)

Where,

$W_{p1}$ : Weight of Penstock	6.68 (ton)	(Tensile allowable Stress: 1,150 kgf/cm <sup>2</sup> )
$t_m$ : Thickness of Penstock	3.57 (mm)	
$D_m$ : v.g. Diameter of Penstock =	0.30 (m)	
H: Design Head =	144.60 (m)	(Intake Water Level - Tailrace Water Level)
L: Length of Penstock =	220.00 (m)	

**Penstock (PVC)φ315:**

Excavation:	$V_e = B \times H \times L$	=	372.42 (m <sup>3</sup> )
-------------	-----------------------------	---	--------------------------

Where,

Q: Maximum Discharge =	0.200 (m <sup>3</sup> /s)	
L: Length of Channel =	440.00 (m)	
B: Width of Channel =	0.92 (m)	from TUBOPLAST Brochure
H: Height of Channel =	0.92 (m)	from TUBOPLAST Brochure

**Spillway Channel:**

	$(B \times H)^{0.5} = 1.09 \times Q^{0.379}$	=	0.59
Excavation:	$V_e = 6.22 \times ((B \times H)^{0.5})^{1.04} \times L$	=	2,380.96 (m <sup>3</sup> )
Concrete:	$V_c = H \times t \times 2 + (B + 2t) \times L$	=	462.18 (m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.577 \times (V_c/L)^{0.888} \times L$	=	0.00 (ton)

Where,

Q: Maximum Discharge =	0.200 (m <sup>3</sup> /s)
L: Length of Channel =	660.00 (m)
B: Width of Channel =	0.40 (m)
H: Height of Channel =	0.60 (m)
t: Thickness of Concrete =	0.15 (m)

**Total Quantity of Penstock and Spillway Channel:**

Excavation:	$V_e = V_{e1} + V_{e2}$	=	3,236.90 (m <sup>3</sup> )
Concrete:	$V_c = V_{c1} + V_{c2}$	=	524.47 (m <sup>3</sup> )
Reinforcement Bars	$W_r = W_{r1} + W_{r2}$	=	1.12 (ton)
Weight of Penstock	$W_p = W_{p1}$	=	6.68 (ton)

**(7) Power House**

Excavation:	$V_e = 97.8 \times (Q \times H_e^{2/3} \times n^{1/2})^{0.727}$	=	338.18 (m <sup>3</sup> )
Concrete:	$V_c = 28.1 \times (Q \times H_e^{2/3} \times n^{1/2})^{0.795}$	=	109.12 (m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.046 \times V_c^{1.05}$	=	6.35 (ton)

Where,

Q: Maximum Discharge =	0.200 (m <sup>3</sup> /s)
He: Effective Head =	144.60 (m)
n: quantity Unit of Turbine =	1.00

**(8) Outlet**

Excavation:	$V_e = 395 \times (R \times Q)^{0.479}$	=	131.10 (m <sup>3</sup> )
Concrete:	$V_c = 40.4 \times (R \times Q)^{0.684}$	=	8.36 (m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.278 \times V_c^{0.610}$	=	1.02 (ton)

Where,

D: Diameter of Waterway =	1.00 (m)	
R: Radius of Waterway =	0.50 (m)	D/2
Q: Maximum Discharge =	0.200 (m <sup>3</sup> /s)	

<span style="background-color: yellow; border: 1px solid black; display: inline-block; width: 10px; height: 10px;"></span>	: Input Cell
<span style="background-color: lightgreen; border: 1px solid black; display: inline-block; width: 10px; height: 10px;"></span>	: Calculation Cell
<span style="background-color: lightpurple; border: 1px solid black; display: inline-block; width: 10px; height: 10px;"></span>	: Reference Cell


**VI. Unit Price**

1USD = **3.00** S/. (as of November, 2007)

<b>(1) Civil Works</b>		
Excavation		
Open	: 5.53 (US\$/m <sup>3</sup> )	* (8.70+2.35) x 0.5 = \$5.53/m <sup>3</sup> , from CAPAECO and Fainal study on Omia <Human power and Machine excavation>
Tunnel	: - (US\$/m <sup>3</sup> )	
Concrete		
Open	: 93.05 (US\$/m <sup>3</sup> )	* from CAPAECO (average of foundation, wall and structure concrete)
Tunnel	: - (US\$/m <sup>3</sup> )	
Reinforcement Bar	: 1,070.00 (US\$/ton)	*\$1.07/kg, from CAPAECO
<b>(2) Hydraulic Equipment</b>		
Gate & Screen	: 8,811.04 (US\$/ton)	* from final study on Omia
Steel Penstock	: 3,100.00 (US\$/ton)	including installation
PVC (φ600)	: 59.67 (US\$/m)	RIB LOC for Headrace
PVC (φ315)	: 43.42 (US\$/m)	TUBOPLAST for Penstock (C-10), The number of joints is 215. This price include joint price. 190m/6m =30 (joint), 30 x \$2.7 =81\$, 81\$/190m =0.43\$/m, 42.99\$/m (PVC) + 0.43\$/m (joint) = 43.42\$/m
<b>(3) Others</b>		
Access Road	: 5,877.89 (US\$/m)	Construction of Unpaved Road (3.0m Width)
<b>(4) Transportation Cost</b>		
Yurimaguas to the site	: 98.67 (US\$/ton)	75 km (river)



# San Antonio Map



**Appendix I-22 Construction Cost for Santa Catalina Power Station*****I. Summary of Construction Cost for Santa Catalina Power Station***

Unit: US\$

<i>Work Item</i>	<i>Construction Cost</i>	<i>Remarks</i>
<b><i>1. Preliminary Works</i></b>	<b>693,643</b>	
(1) Access Road	176,336	
(2) Facilities for Construction Office	78,346	Cost of Civil Works x 0.05
(3) Transportation cost	438,961	4,448.78ton x \$98.67/ton
<b><i>2. Cost for Environmental Measures</i></b>	<b>15,669</b>	Cost of Civil Works x 0.01
<b><i>3. Civil Works</i></b>	<b>1,566,932</b>	
(1) Weir	11,523	
(2) Intake	22,080	
(3) Settling Basin	39,664	
(4) Headrace	1,083,303	
(5) Head Tank	56,635	
(6) Penstock & Spillway Channel	265,592	
(7) Power House	78,174	
(8) Outlet	9,961	
(9) Miscellaneous Work	0	
<b><i>4. Hydraulic Equipment</i></b>	<b>69,900</b>	
(1) Gate & Screen	17,126	
(2) Penstock	41,179	
(3) PVC for Headrace	0	
(4) PVC for Penstock	0	
(5) Others	11,595	
<b><i>5. Electrical Equipment</i></b>	<b>291,200</b>	
<b><i>6. Direct Cost</i></b>	<b>2,637,344</b>	1.+2.+3.+4.+5.
<b><i>7. Engineering Cost</i></b>	<b>263,734</b>	6. x 0.1: Detailed Design and Supervision
<b><i>8. Contingent Budget</i></b>	<b>258,922</b>	6. x 0.098
<b><i>9. IGV</i></b>	<b>600,400</b>	19.00%
<b><i>10. Total Cost</i></b>	<b>3,760,400</b>	

**II. Detailed Statement of Transportation Cost for Santa Catalina Power Station**

<i>Items</i>	<i>Unit</i>	<i>Quantity</i>	<i>Remarks</i>
<b>(1) Wier</b>		<b>97.57</b>	
a. Cements	ton	20.53	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		76.04	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		1.00	
<b>(2) Intake</b>		<b>190.87</b>	
a. Gate	ton	1.25	
b. Screen		0.69	
c. Cements		39.22	Cement: 0.27ton per concrete 1m <sup>3</sup>
d. Coarse aggregate		145.26	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
e. Reinforcement Bars		4.44	
<b>(3) Settling Basin</b>		<b>285.76</b>	
a. Cements	ton	58.33	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		216.04	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		11.39	
<b>(4) Headrace</b>		<b>2223.51</b>	
a. Cements	ton	318.57	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		1179.90	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		725.04	
<b>(5) Head Tank</b>		<b>314.02</b>	
a. Cements	ton	64.18	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		237.71	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		12.12	
<b>(6) Penstock &amp; Spillway Channel</b>		<b>825.10</b>	
a. Penstock Steel (φ700)	ton	13.28	
b. Penstock PVC		0.00	
c. Cements		136.65	Cement: 0.27ton per concrete 1m <sup>3</sup>
d. Coarse aggregate		506.11	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
e. Reinforcement Bars		169.05	
<b>(7) Power House</b>		<b>458.89</b>	
a. Cements	ton	93.05	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		344.61	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		21.23	
<b>(8) Outlet</b>		<b>53.05</b>	
a. Cements	ton	10.72	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		39.71	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		2.63	
<b>(9) Subtotal</b>		<b>4,448.78</b>	
<b>(10) Transportation Cost</b>		<b>438,961</b>	(9) x \$98.67/ton

**III. Detailed Statement of Civil Works Cost for Santa Catalina Power Station**

Unit: US\$

<i>Work Items</i>	<i>Unit</i>	<i>Unit Price</i>	<i>Quantity</i>	<i>Cost</i>	<i>Remarks</i>
<b>(1) Wier</b>				<b>11,523</b>	
a. Excavation	m <sup>3</sup>	5.53	264.4	1,461	
b. Concrete	m <sup>3</sup>	93.05	76.0	7,075	
c. Reinforcement Bars	ton	1,070.00	1.0	1,067	
d. Others	-			1,920	(a+b+c) x 0.2 (including coffer dam construction, etc.)
<b>(2) Intake</b>				<b>22,080</b>	
a. Excavation	m <sup>3</sup>	5.53	168.1	929	
b. Concrete	m <sup>3</sup>	93.05	145.3	13,516	
c. Reinforcement Bars	ton	1,070.00	4.4	4,755	
d. Others	-			2,880	(a+b+c) x 0.15 (including coffer work, etc.)
<b>(3) Settling Basin</b>				<b>39,664</b>	
a. Excavation	m <sup>3</sup>	5.53	681.9	3,770	
b. Concrete	m <sup>3</sup>	93.05	216.0	20,102	
c. Reinforcement Bars	ton	1,070.00	11.4	12,187	
d. Others	-			3,605	(a+b+c) x 0.10 (including other works)
<b>(4) Headrace</b>				<b>1,083,303</b>	
a. Excavation	m <sup>3</sup>	5.53	3,105.0	17,170	
b. Concrete	m <sup>3</sup>	93.05	1,179.9	109,789	
c. Reinforcement Bars	ton	1,070.00	725.0	775,794	
d. Others	-			180,550	(a+b+c) x 0.20 (including filling works)
<b>(5) Head Tank</b>				<b>56,635</b>	
a. Excavation	m <sup>3</sup>	5.53	970.1	5,364	
b. Concrete	m <sup>3</sup>	93.05	237.7	22,119	
c. Reinforcement Bars	ton	1,070.00	12.1	12,971	
d. Others	-			16,181	(a+b+c) x 0.40 (including gate, screen)
<b>(6) Penstock &amp; Spillway Channel</b>				<b>265,592</b>	
a. Excavation	m <sup>3</sup>	5.53	2,435.6	13,468	
b. Concrete	m <sup>3</sup>	93.05	506.1	47,093	
c. Reinforcement Bars	ton	1,070.00	169.1	180,887	
d. Others	-			24,144	(a+b+c) x 0.10 (including filling works)
<b>(7) Power House</b>				<b>78,174</b>	
a. Excavation	m <sup>3</sup>	5.53	967.9	5,352	
b. Concrete	m <sup>3</sup>	93.05	344.6	32,066	
c. Reinforcement Bars	ton	1,070.00	21.2	22,716	
d. Others	-			18,040	(a+b+c) x 0.30 (including drainage work, wooden)
<b>(8) Outlet</b>				<b>9,961</b>	
a. Excavation	m <sup>3</sup>	5.53	390.2	2,158	
b. Concrete	m <sup>3</sup>	93.05	39.7	3,694	
c. Reinforcement Bars	ton	1,070.00	2.6	2,810	
d. Others	-			1,299	(a+b+c) x 0.15 (including coffer work, etc.)
<b>(9) Miscellaneous Work</b>				<b>0</b>	$\Sigma(1)-(8) \times 0.05$ not consider
<b>(10) Subtotal</b>				<b>1,566,932</b>	

**IV. Detailed Statement of Hydraulic Equipment Cost for Santa Catalina Power Station**

Unit: US\$

<i>Work Items</i>	<i>Unit</i>	<i>Unit Price</i>	<i>Quantity</i>	<i>Cost</i>	<i>Remarks</i>
<b>(1) Weir &amp; Spillway</b>				<b>0</b>	
a. Gate	ton	8,811.04	0.00	0	
<b>(2) Intake</b>				<b>17,126</b>	
a. Gate	ton	8,811.04	1.25	11,040	
b. Screen	ton	8,811.04	0.69	6,086	
<b>(3) Penstock Steel (φ700)</b>	ton	3,100.00	13.28	<b>41,179</b>	
<b>(4) PVC for headrace</b>	m	-	0	<b>0</b>	
<b>(5) Penstock PVC</b>	m	-	0	<b>0</b>	
<b>(6) Subtotal</b>				<b>58,305</b>	
<b>(7) Others</b>				<b>11,595</b>	19.89%
<b>(8) Total</b>				<b>69,900</b>	

**V. Quantity**

**(1) Weir**

Excavation:	$V_e =$	$8.69 \times (H_d \times L)^{1.14}$	$=$	<b>264.36</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$8.64 \times (H_d^2 \times L)^{0.726}$	$=$	<b>76.04</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.0274 \times V_c^{0.830}$	$=$	<b>1.00</b>	(ton)
Weight of Gate:	$W_g =$	$0.145 \times Q_f^{0.692}$	$=$	<b>0.00</b>	(ton) (unconsidered)

Where,

$H_d$ :	Height of Dam =	<b>1.00</b>	(m)
$L$ :	Length of Dam =	<b>20.00</b>	(m)

**(2) Intake**

Excavation:	$V_e =$	$171 \times (R \times Q)^{0.666}$	$=$	<b>168.14</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$147 \times (R \times Q)^{0.470}$	$=$	<b>145.26</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.0145 \times V_c^{1.15}$	$=$	<b>4.44</b>	(ton)
Weight of Gate:	$W_g =$	$1.27 \times (R \times Q)^{0.533}$	$=$	<b>1.25</b>	(ton)
Weight of Screen:	$W_s =$	$0.701 \times (R \times Q)^{0.582}$	$=$	<b>0.69</b>	(ton)

Where,

$D$ :	Diameter of Waterway =	<b>1.50</b>	(m)		
$R$ :	Radius of Waterway =	<b>0.75</b>	(m)	$D/2$	Assumption; Waterway Gradient = 1/1,000
$Q$ :	Maximum Discharge =	<b>1.300</b>	(m <sup>3</sup> /s)		

**(3) Settling Basin**

Excavation:	$V_e =$	$515 \times Q^{1.07}$	$=$	<b>681.91</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$169 \times Q^{0.936}$	$=$	<b>216.04</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.120 \times V_c^{0.847}$	$=$	<b>11.39</b>	(ton)
Weight of Gate:	$W_g =$	$0.910 \times Q^{0.613}$	$=$	<b>1.07</b>	(ton)
Weight of Screen:	$W_s =$	$0.879 \times Q^{0.785}$	$=$	<b>1.08</b>	(ton)

Where,

$Q$ :	Maximum Discharge =	<b>1.300</b>	(m <sup>3</sup> /s)
-------	---------------------	--------------	---------------------

**(4) Headrace**

**In the case of Opoen Channel (1,500 x 1,000):**

Excavation:	$V_e = B \times H \times L$	$=$	<b>3,105.00</b>	(m <sup>3</sup> )
Concrete:	$V_c = ((H \times t \times 2) + (B + 2t) \times t) \times L$	$=$	<b>1,179.90</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.577 \times (V_c/L)^{0.888} \times L$	$=$	<b>725.04</b>	(ton)

Where,

$Q$ :	Maximum Discharge =	<b>1.300</b>	(m <sup>3</sup> /s)	
$L$ :	Length of Channel =	<b>2,070.00</b>	(m)	
$B$ :	Width of Channel =	<b>1.50</b>	(m)	for excavation
$H$ :	Height of Channel =	<b>1.00</b>	(m)	for excavation
$t$ :	Thickness of Concrete =	<b>0.15</b>	(m)	

**(5) Head Tank**

Excavation:	$V_e =$	$808 \times Q^{0.697}$	$=$	<b>970.13</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$197 \times Q^{0.716}$	$=$	<b>237.71</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.051 \times V_c$	$=$	<b>12.12</b>	(ton)

Where,

$Q$ :	Maximum Discharge =	<b>1.300</b>	(m <sup>3</sup> /s)
-------	---------------------	--------------	---------------------

**(6) Penstock & Spillway Channel**

**Penstock (Steel)φ700:**

Excavation:	$V_{e1} = 10.9 \times D_m^{1.33} \times L$	=	1,153.07 (m <sup>3</sup> )
Concrete:	$V_{c1} = 2.14 \times D_m^{1.68} \times L$	=	199.81 (m <sup>3</sup> )
Reinforcement Bars	$W_{r1} = 0.018 \times V_c$	=	3.60 (ton)

Where,

$D_m$ : avg. Diameter of Penstock =	0.70 (m)
L: Length of Penstock =	170.00 (m)

Weight of Penstock	$W_{p1} = 7.85 \times \pi \times D_m \times t_m \times 10^{-3} \times 1.15 \times L$	=	13.28 (ton)
Thickness of Penstock:	$t_m = 0.0362 \times H \times D_m + 2$	=	3.94 (mm)

Where,

$W_{p1}$ : Weight of Penstock	13.28 (ton)	(Tensile allowable Stress: 1,150 kgf/cm <sup>2</sup> )
$t_m$ : Thickness of Penstock	3.94 (mm)	
$D_m$ : avg. Diameter of Penstock =	0.70 (m)	
H: Design Head =	76.40 (m)	(Intake Water Level - Tailrace Water Level)
L: Length of Penstock =	170.00 (m)	

**Penstock (PVC):**

Excavation:	$V_e = B \times H \times L$	=	0.00 (m <sup>3</sup> )
-------------	-----------------------------	---	------------------------

Where,

Q: Maximum Discharge =	1.300 (m <sup>3</sup> /s)	
L: Length of Channel =	0.00 (m)	
B: Width of Channel =	0.00 (m)	from TUBOPLAST Brochure
H: Height of Channel =	0.00 (m)	from TUBOPLAST Brochure

**Spillway Channel:**

	$(B \times H)^{0.5} = 1.09 \times Q^{0.379}$	=	1.20
Excavation:	$V_e = 6.22 \times ((B \times H)^{0.5})^{1.04} \times L$	=	1,282.55 (m <sup>3</sup> )
Concrete:	$V_c = H \times t \times 2 + (B + 2t) \times L$	=	306.30 (m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.577 \times (V_c/L)^{0.888} \times L$	=	165.46 (ton)

Where,

Q: Maximum Discharge =	1.300 (m <sup>3</sup> /s)
L: Length of Channel =	170.00 (m)
B: Width of Channel =	1.50 (m)
H: Height of Channel =	1.00 (m)
t: Thickness of Concrete =	0.15 (m)

**Total Quantity of Penstock and Spillway Channel:**

Excavation:	$V_e = V_{e1} + V_{e2}$	=	2,435.62 (m <sup>3</sup> )
Concrete:	$V_c = V_{c1} + V_{c2}$	=	506.11 (m <sup>3</sup> )
Reinforcement Bars	$W_r = W_{r1} + W_{r2}$	=	169.05 (ton)
Weight of Penstock	$W_p = W_{p1}$	=	13.28 (ton)

**(7) Power House**

Excavation:	$V_e = 97.8 \times (Q \times H_e^{2/3} \times n^{1/2})^{0.727}$	=	967.94 (m <sup>3</sup> )
Concrete:	$V_c = 28.1 \times (Q \times H_e^{2/3} \times n^{1/2})^{0.795}$	=	344.61 (m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.046 \times V_c^{1.05}$	=	21.23 (ton)

Where,

Q: Maximum Discharge =	1.300 (m <sup>3</sup> /s)
He: Effective Head =	76.40 (m)
n: quantity Unit of Turbine =	1.00

**(8) Outlet**

Excavation:	$V_e = 395 \times (R \times Q)^{0.479}$	=	390.24 (m <sup>3</sup> )
Concrete:	$V_c = 40.4 \times (R \times Q)^{0.684}$	=	39.71 (m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.278 \times V_c^{0.610}$	=	2.63 (ton)

Where,

D: Diameter of Waterway =	1.50 (m)	
R: Radius of Waterway =	0.75 (m)	D/2
Q: Maximum Discharge =	1.300 (m <sup>3</sup> /s)	

<span style="background-color: yellow; border: 1px solid black; display: inline-block; width: 15px; height: 10px;"></span>	: Input Cell
<span style="background-color: lightgreen; border: 1px solid black; display: inline-block; width: 15px; height: 10px;"></span>	: Calculation Cell
<span style="background-color: lightpurple; border: 1px solid black; display: inline-block; width: 15px; height: 10px;"></span>	: Reference Cell


**VI. Unit Price**

1USD = **3.00** S/. (as of November, 2007)

<b>(1) Civil Works</b>			
Excavation			
Open	:	<b>5.53</b> (US\$/m <sup>3</sup> )	* (8.70+2.35) x 0.5 = \$5.53/m <sup>3</sup> , from CAPAECO and Fainal study on Omia <Human power and Machine excavation>
Tunnel	:	- (US\$/m <sup>3</sup> )	
Concrete			
Open	:	<b>93.05</b> (US\$/m <sup>3</sup> )	* from CAPAECO (average of foundation, wall and structure concrete)
Tunnel	:	- (US\$/m <sup>3</sup> )	
Reinforcement Bar	:	<b>1,070.00</b> (US\$/ton)	*\$1.07/kg, from CAPAECO
<b>(2) Hydraulic Equipment</b>			
Gate & Screen	:	<b>8,811.04</b> (US\$/ton)	* from final study on Omia
Steel Penstock	:	<b>3,100.00</b> (US\$/ton)	including installation
PVC for Headrace	:	- (US\$/m)	
PVC for Penstock	:	- (US\$/m)	
<b>(3) Others</b>			
Access Road	:	<b>5,877.89</b> (US\$/m)	Construction of Unpaved Road (3.0m Width)
<b>(4) Transportation Cost</b>			
Iquitos to the site	:	<b>98.67</b> (US\$/ton)	745 km (river)



# Santa Catalina Map



**Appendix I-23 Construction Cost for Challapampa Power Station*****I. Summary of Construction Cost for Challapampa Power Station***

Unit: US\$

<i>Work Item</i>	<i>Construction Cost</i>	<i>Remarks</i>
<b><i>1. Preliminary Works</i></b>	<b>20,442</b>	
(1) Access Road	11,755	
(2) Facilities for Construction Office	2,447	Cost of Civil Works x 0.05
(3) Transportation cost	6,240	385.46ton x \$16.45/ton
<b><i>2. Cost for Environmental Measures</i></b>	<b>489</b>	Cost of Civil Works x 0.01
<b><i>3. Civil Works</i></b>	<b>48,952</b>	
(1) Weir	2,221	
(2) Intake	2,823	
(3) Settling Basin	2,565	
(4) Headrace	2,972	
(5) Head Tank	6,309	
(6) Penstock & Spillway Channel	22,974	
(7) Power House	7,943	
(8) Outlet	1,145	
(9) Miscellaneous Work	0	
<b><i>4. Hydraulic Equipment</i></b>	<b>35,000</b>	
(1) Gate & Screen	1,729	
(2) Penstock	1,123	
(3) PVC (φ400)	18,431	
(4) PVC (φ200)	7,885	
(5) Others	5,832	
<b><i>5. Electrical Equipment</i></b>	<b>35,000</b>	
<b><i>6. Direct Cost</i></b>	<b>139,883</b>	1.+2.+3.+4.+5.
<b><i>7. Engineering Cost</i></b>	<b>13,988</b>	6. x 0.1: Detailed Design and Supervision
<b><i>8. Contingent Budget</i></b>	<b>13,129</b>	6. x 0.094
<b><i>9. IGV</i></b>	<b>31,730</b>	19.00%
<b><i>10. Total Cost</i></b>	<b>198,730</b>	

**II. Detailed Statement of Transportation Cost for Challapampa Power Station**

<i>Items</i>	<i>Unit</i>	<i>Quantity</i>	<i>Remarks</i>
<b>(1) Wier</b>		<b>17.05</b>	
a. Cements	ton	3.57	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		13.24	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		0.23	
<b>(2) Intake</b>		<b>26.60</b>	
a. Gate	ton	0.14	
b. Screen		0.06	
c. Cements		5.51	Cement: 0.27ton per concrete 1m <sup>3</sup>
d. Coarse aggregate		20.42	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
e. Reinforcement Bars		0.47	
<b>(3) Settling Basin</b>		<b>16.41</b>	
a. Cements	ton	3.28	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		12.14	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		0.99	
<b>(4) Headrace</b>		<b>4.81</b>	
a. PVC (φ400)	ton	4.81	Weight: 700m x 41.214kg/6m
<b>(5) Head Tank</b>		<b>34.72</b>	
a. Cements	ton	7.10	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		26.28	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		1.34	
<b>(6) Penstock &amp; Spillway Channel</b>		<b>228.98</b>	
a. Penstock Steel (φ200)	ton	0.36	
b. Penstock PVC (φ200)		1.89	Weight: 227m x 50.000kg/6m
c. Cements		48.19	Cement: 0.27ton per concrete 1m <sup>3</sup>
d. Coarse aggregate		178.48	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
e. Reinforcement Bars		0.06	
<b>(7) Power House</b>		<b>47.42</b>	
a. Cements	ton	9.66	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		35.79	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		1.97	
<b>(8) Outlet</b>		<b>3.36</b>	
a. Cements	ton	0.62	Cement: 0.27ton per concrete 1m <sup>3</sup>
b. Coarse aggregate		2.28	Coarse aggregate: 1ton per concrete 1m <sup>3</sup>
c. Reinforcement Bars		0.46	
<b>(9) Subtotal</b>		<b>379.34</b>	
<b>(10) Transportation Cost</b>		<b>6,240</b>	(9) x \$16.45/ton

**III. Detailed Statement of Civil Works Cost for Challapampa Power Station**

Unit: US\$

<i>Work Items</i>	<i>Unit</i>	<i>Unit Price</i>	<i>Quantity</i>	<i>Cost</i>	<i>Remarks</i>
<b>(1) Wier</b>				<b>2,221</b>	
a. Excavation	m <sup>3</sup>	5.53	67.0	370	
b. Concrete	m <sup>3</sup>	93.05	13.2	1,231	
c. Reinforcement Bars	ton	1,070.00	0.2	250	
d. Others	-			370	(a+b+c) x 0.2 (including coffer dam construction, etc.)
<b>(2) Intake</b>				<b>2,823</b>	
a. Excavation	m <sup>3</sup>	5.53	10.4	57	
b. Concrete	m <sup>3</sup>	93.05	20.4	1,900	
c. Reinforcement Bars	ton	1,070.00	0.5	498	
d. Others	-			368	(a+b+c) x 0.15 (including coffer work, etc.)
<b>(3) Settling Basin</b>				<b>2,565</b>	
a. Excavation	m <sup>3</sup>	5.53	25.4	140	
b. Concrete	m <sup>3</sup>	93.05	12.1	1,129	
c. Reinforcement Bars	ton	1,070.00	1.0	1,063	
d. Others	-			233	(a+b+c) x 0.10 (including other works)
<b>(4) Headrace</b>				<b>2,972</b>	
a. Excavation	m <sup>3</sup>	5.53	448.0	2,477	
b. Concrete	m <sup>3</sup>	93.05	0.0	0	
c. Reinforcement Bars	ton	1,070.00	0.0	0	
d. Others	-			495	(a+b+c) x 0.20 (including filling works)
<b>(5) Head Tank</b>				<b>6,309</b>	
a. Excavation	m <sup>3</sup>	5.53	113.7	628	
b. Concrete	m <sup>3</sup>	93.05	26.3	2,445	
c. Reinforcement Bars	ton	1,070.00	1.3	1,434	
d. Others	-			1,802	(a+b+c) x 0.40 (including gate, screen)
<b>(6) Penstock &amp; Spillway Channel</b>				<b>22,974</b>	
a. Excavation	m <sup>3</sup>	5.53	762.4	4,216	
b. Concrete	m <sup>3</sup>	93.05	178.5	16,607	
c. Reinforcement Bars	ton	1,070.00	0.1	63	
d. Others	-			2,088	(a+b+c) x 0.10 (including filling works)
<b>(7) Power House</b>				<b>7,943</b>	
a. Excavation	m <sup>3</sup>	5.53	122.0	674	
b. Concrete	m <sup>3</sup>	93.05	35.8	3,330	
c. Reinforcement Bars	ton	1,070.00	2.0	2,106	
d. Others	-			1,833	(a+b+c) x 0.30 (including drainage work, wooden)
<b>(8) Outlet</b>				<b>1,145</b>	
a. Excavation	m <sup>3</sup>	5.53	52.8	292	
b. Concrete	m <sup>3</sup>	93.05	2.3	212	
c. Reinforcement Bars	ton	1,070.00	0.5	492	
d. Others	-			149	(a+b+c) x 0.15 (including coffer work, etc.)
<b>(9) Miscellaneous Work</b>				<b>0</b>	Σ(1)-(8) x 0.05 not consider
<b>(10) Subtotal</b>				<b>48,952</b>	

**IV. Detailed Statement of Hydraulic Equipment Cost for Challapampa Power Station**

Unit: US\$

<i>Work Items</i>	<i>Unit</i>	<i>Unit Price</i>	<i>Quantity</i>	<i>Cost</i>	<i>Remarks</i>
<b>(1) Weir &amp; Spillway</b>				<b>0</b>	
a. Gate	ton	8,811.04	0.00	0	
<b>(2) Intake</b>				<b>1,729</b>	
a. Gate	ton	8,811.04	0.14	1,193	
b. Screen	ton	8,811.04	0.06	536	
<b>(3) Penstock Steel (φ200)</b>	ton	3,100.00	0.36	<b>1,123</b>	
<b>(4) PVC (φ400) for headrace</b>	m	26.33	700	<b>18,431</b>	
<b>(5) Penstock PVC (φ200) C-10</b>	m	34.74	227	<b>7,885</b>	
<b>(6) Subtotal</b>				<b>29,168</b>	
<b>(7) Others</b>				<b>5,832</b>	19.99%
<b>(8) Total</b>				<b>35,000</b>	

## V. Quantity

<b>(1) Weir</b>					
Excavation:	$V_e =$	$8.69 \times (H_d \times L)^{1.14}$	$=$	<b>67.01</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$8.64 \times (H_d^2 \times L)^{0.726}$	$=$	<b>13.24</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.0274 \times V_c^{0.830}$	$=$	<b>0.23</b>	(ton)
Weight of Gate:	$W_g =$	$0.145 \times Q_f^{0.692}$	$=$	<b>0.00</b>	(ton) (unconsidered)
Where,					
$H_d$ :	Height of Dam =	<b>0.30</b>	(m)		
$L$ :	Length of Dam =	<b>20.00</b>	(m)		
<b>(2) Intake</b>					
Excavation:	$V_e =$	$171 \times (R \times Q)^{0.666}$	$=$	<b>10.43</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$147 \times (R \times Q)^{0.470}$	$=$	<b>20.42</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.0145 \times V_c^{1.15}$	$=$	<b>0.47</b>	(ton)
Weight of Gate:	$W_g =$	$1.27 \times (R \times Q)^{0.533}$	$=$	<b>0.14</b>	(ton)
Weight of Screen:	$W_s =$	$0.701 \times (R \times Q)^{0.582}$	$=$	<b>0.06</b>	(ton)
Where,					
$D$ :	Diameter of Waterway =	<b>0.50</b>	(m)		
$R$ :	Radius of Waterway =	<b>0.25</b>	(m)	$D/2$	Assumption; Waterway Gradient = 1/1,000
$Q$ :	Maximum Discharge =	<b>0.060</b>	(m <sup>3</sup> /s)		
<b>(3) Settling Basin</b>					
Excavation:	$V_e =$	$515 \times Q^{1.07}$	$=$	<b>25.38</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$169 \times Q^{0.936}$	$=$	<b>12.14</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.120 \times V_c^{0.847}$	$=$	<b>0.99</b>	(ton)
Weight of Gate:	$W_g =$	$0.910 \times Q^{0.613}$	$=$	<b>0.16</b>	(ton)
Weight of Screen:	$W_s =$	$0.879 \times Q^{0.785}$	$=$	<b>0.10</b>	(ton)
Where,					
$Q$ :	Maximum Discharge =	<b>0.060</b>	(m <sup>3</sup> /s)		
<b>(4) Headrace</b>					
<b>In the case of PVC<math>\phi</math>400:</b>					
Excavation:	$V_e = B \times H \times L$		$=$	<b>448.00</b>	(m <sup>3</sup> )
Concrete:	$V_c = ((H \times t \times 2) + (B + 2t) \times t) \times L$		$=$	-	(m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.577 \times (V_c/L)^{0.888} \times L$		$=$	-	(ton)
Where,					
$Q$ :	Maximum Discharge =	<b>0.060</b>	(m <sup>3</sup> /s)		
$L$ :	Length of Channel =	<b>700.00</b>	(m)		
$B$ :	Width of Channel =	<b>0.80</b>	(m)	for excavation (2D from RIBLOC Brochure)	
$H$ :	Height of Channel =	<b>0.80</b>	(m)	for excavation (2D from RIBLOC Brochure)	
$t$ :	Thickness of Concrete =	-	(m)		
<b>(5) Head Tank</b>					
Excavation:	$V_e =$	$808 \times Q^{0.697}$	$=$	<b>113.71</b>	(m <sup>3</sup> )
Concrete:	$V_c =$	$197 \times Q^{0.716}$	$=$	<b>26.28</b>	(m <sup>3</sup> )
Reinforcement Bars	$W_r =$	$0.051 \times V_c$	$=$	<b>1.34</b>	(ton)
Where,					
$Q$ :	Maximum Discharge =	<b>0.060</b>	(m <sup>3</sup> /s)		

<b>(6) Penstock &amp; Spillway Channel</b>			
<b>Penstock (Steel)φ200:</b>			
Excavation:	$V_{e1} = 10.9 \times D_m^{1.33} \times L$	=	29.48 (m <sup>3</sup> )
Concrete:	$V_{c1} = 2.14 \times D_m^{1.68} \times L$	=	3.30 (m <sup>3</sup> )
Reinforcement Bars	$W_{r1} = 0.018 \times V_c$	=	0.06 (ton)
Where,			
$D_m$ : avg. Diameter of Penstock =	0.20 (m)		
L: Length of Penstock =	23.00 (m)		
Weight of Penstock	$W_{p1} = 7.85 \times \pi \times D_m \times t_m \times 10^{-3} \times 1.15 \times L$	=	0.36 (ton)
Thickness of Penstock:	$t_m = 0.0362 \times H \times D_m + 2$	=	2.78 (mm)
Where,			
$W_{p1}$ : Weight of Penstock	0.36 (ton)	(Tensile allowable Stress: 1,150 kgf/cm <sup>2</sup> )	
$t_m$ : Thickness of Penstock	2.78 (mm)		
$D_m$ : avg. Diameter of Penstock =	0.20 (m)		
H: Design Head =	107.40 (m)	(Intake Water Level - Tailrace Water Level)	
L: Length of Penstock =	23.00 (m)		
<b>Penstock (PVC)φ200:</b>			
Excavation:	$V_e = B \times H \times L$	=	171.82 (m <sup>3</sup> )
Where,			
Q: Maximum Discharge =	0.060 (m <sup>3</sup> /s)		
L: Length of Channel =	227.00 (m)		
B: Width of Channel =	0.87 (m)	from TUBOPLAST Brochure	
H: Height of Channel =	0.87 (m)	from TUBOPLAST Brochure	
<b>Spillway Channel:</b>			
	$(B \times H)^{0.5} = 1.09 \times Q^{0.379}$	=	0.38
Excavation:	$V_e = 6.22 \times ((B \times H)^{0.5})^{1.04} \times L$	=	561.11 (m <sup>3</sup> )
Concrete:	$V_c = H \times t \times 2 + (B + 2t) \times L$	=	175.18 (m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.577 \times (V_c/L)^{0.888} \times L$	=	0.00 (ton)
Where,			
Q: Maximum Discharge =	0.060 (m <sup>3</sup> /s)		
L: Length of Channel =	250.00 (m)		
B: Width of Channel =	0.40 (m)		
H: Height of Channel =	0.60 (m)		
t: Thickness of Concrete =	0.15 (m)		
<b>Total Quantity of Penstock and Spillway Channel:</b>			
Excavation:	$V_e = V_{e1} + V_{e2}$	=	762.41 (m <sup>3</sup> )
Concrete:	$V_c = V_{c1} + V_{c2}$	=	178.48 (m <sup>3</sup> )
Reinforcement Bars	$W_r = W_{r1} + W_{r2}$	=	0.06 (ton)
Weight of Penstock	$W_p = W_{p1}$	=	0.36 (ton)
<b>(7) Power House</b>			
Excavation:	$V_e = 97.8 \times (Q \times H e^{2/3} \times n^{1/2})^{0.727}$	=	122.02 (m <sup>3</sup> )
Concrete:	$V_c = 28.1 \times (Q \times H e^{2/3} \times n^{1/2})^{0.795}$	=	35.79 (m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.046 \times V_c^{1.05}$	=	1.97 (ton)
Where,			
Q: Maximum Discharge =	0.060 (m <sup>3</sup> /s)		
He: Effective Head =	107.40 (m)		
n: quantity Unit of Turbine =	1.00		
<b>(8) Outlet</b>			
Excavation:	$V_e = 395 \times (R \times Q)^{0.479}$	=	52.84 (m <sup>3</sup> )
Concrete:	$V_c = 40.4 \times (R \times Q)^{0.684}$	=	2.28 (m <sup>3</sup> )
Reinforcement Bars	$W_r = 0.278 \times V_c^{0.610}$	=	0.46 (ton)
Where,			
D: Diameter of Waterway =	0.50 (m)		
R: Radius of Waterway =	0.25 (m)	D/2	
Q: Maximum Discharge =	0.060 (m <sup>3</sup> /s)		
<div style="display: flex; align-items: center; margin-top: 10px;"> <div style="width: 15px; height: 15px; background-color: yellow; margin-right: 5px;"></div> : Input Cell         </div> <div style="display: flex; align-items: center; margin-top: 5px;"> <div style="width: 15px; height: 15px; background-color: lightgreen; margin-right: 5px;"></div> : Calculation Cell         </div> <div style="display: flex; align-items: center; margin-top: 5px;"> <div style="width: 15px; height: 15px; background-color: lightpurple; margin-right: 5px;"></div> : Reference Cell         </div>			


**VI. Unit Price**

1USD = **3.00** S/. (as of November, 2007)

<b>(1) Civil Works</b>		
Excavation		
Open	: 5.53 (US\$/m <sup>3</sup> )	* (8.70+2.35) x 0.5 = \$5.53/m <sup>3</sup> , from CAPAECO and Fainal study on Omia <Human power and Machine excavation>
Tunnel	: - (US\$/m <sup>3</sup> )	
Concrete		
Open	: 93.05 (US\$/m <sup>3</sup> )	* from CAPAECO (average of foundation, wall and structure concrete)
Tunnel	: - (US\$/m <sup>3</sup> )	
Reinforcement Bar	: 1,070.00 (US\$/ton)	*\$1.07/kg, from CAPAECO
<b>(2) Hydraulic Equipment</b>		
Gate & Screen	: 8,811.04 (US\$/ton)	* from final study on Omia
Steel Penstock	: 3,100.00 (US\$/ton)	including installation
PVC (φ400)	: 26.33 (US\$/m)	RIB LOC for Headrace
PVC (φ200)	: 34.74 (US\$/m)	80% of TUBOPLAST( φ 315) for Penstock (C-10) = 43.42 x 0.8 = 34.74
<b>(3) Others</b>		
Access Road	: 979.65 (US\$/m)	Repair Work for Existing Unpaved Road
<b>(4) Transportation Cost</b>		
Juliaca to the site	: 16.45 (US\$/ton)	232 km (road)




# Challapampa Map



POTENCIA :	45 kW
CAUDAL :	0.064 m <sup>3</sup> /s
VIVIENDAS :	329
ALTITUD BOCATOMA :	4650 m.s.n.m
ALTITUD CASA DE MAQUINAS :	4550 m.s.n.m
ALTURA BRUTA :	110 m
LONGITUD CANAL :	0.7 km
LONGITUD TUBERIA DE PRESION :	0.25 km
DATOS CUENCA :	AREA 50 km <sup>2</sup>
	PERIMETRO 33.72 km

LEYENDA	
	BOCATOMA
	CASA DE MAQUINAS
	LOCALIDADES
	CANAL
	TUBERIA DE PRESION
	RED EN MEDIA TENSION
	VIA ASFALTADA
	VIA AFIRMADA
	VIA TROCHA
	RIO
	CURVAS DE NIVEL (msnm)
	LIMITE DEPARTAMENTAL
	LIMITE PROVINCIAL
	LIMITE DISTRITAL
	LAGOS
	ISLAS
	CUENCA
	NEVADOS



<b>MINISTERIO DE ENERGIA Y MINAS</b> DIRECCION EJECUTIVA DE PROYECTOS										
<b>PROYECTO C.H. CHALLAPAMPA</b>										
<b>UBICACION DEL AREA DEL PROYECTO</b>										
Nº	FECHA	REVISIONES	REV.	APROB.	DISEÑADO: N.A.S.	DIBUJADO: N.A.S.	REVISADO: H.S.S.	APROBADO: R.A.A.	FECHA: SET 2007	

PROYECTO Nº:	UBICACION
ESCALA:	DEPARTAMENTO: PUNO
1 : 125 000	PROVINCIA: VARIOS
HOJA:	DISTRITO: VARIOS
1/1	PLANO Nº:
FORMATO: A-3	